2
WSRC-TR-92-1178

ORGANIC EVAPORATOR STEAM VALVE FAILURE (U)

by R. A. Jacobs
Westinghouse Savannah River Company
Savannah River Site
Aiken, South Carolina 29808

WSRC-TR--92-1178
DE93 004877

Other Authors:

This paper was prepared in connection with work done under Contract No. DE-AC09-89SR18035 with the U. S. Department of Energy. By acceptance of this paper, the publisher and/or recipient acknowledges the U. S. Government's right to retain a nonexclusive, royalty-free license in and to any copyright covering this paper, along with the right to reproduce and to authorize others to reproduce all or part of the copyrighted paper.

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

Westinghouse
Savannah River Company

INTER-OFFICE MEMORANDUM

WSRC-RP-92-1178

Keywords: DWPF, Organic
Evaporator, Salt Process
Cell, PVVS

Retention period: Permanent

cc: J. T. Carter, 704-1T
L. F. Landon, 704-T
D. P. Lambert, 704-1T
SRL Records (4)*

September 29, 1992

TO: E. W. HOLTZSCHEITER, 773-A

FROM: R. A. JACOBS, 704-T

ORGANIC EVAPORATOR STEAM VALVE FAILURE (U)

Summary and Conclusions

DWPF Technical has requested an analysis of the capacity of the Organic Evaporator (OE) condenser (OEC) be performed to determine its capability in the case where the OE steam flow control valve fails open. Calculations of the OE boilup and the OEC heat transfer coefficient indicate the OEC will have more than enough capacity to remove the heat at maximum OE boilup. In fact, the Salt Cell Vent Condenser (SCVC) should also have sufficient capacity to handle the maximum OE boilup. Therefore, it would require simultaneous loss of OEC and/or SCVC condensing capacity for the steam valve failure to cause high benzene in the Process Vessel Vent System (PVVS).

Discussion

Background

One of the scenarios included in the Salt Process Cell (SPC) fault tree analysis is failure of the Organic Evaporator steam valve in the open position with benzene in the OE. This occurrence is postulated to result in a flammable benzene

C. T. Randall, 704-T

Authorized Derivative Classifier

concentration in the PVVS by overwhelming the capability of the condensers (both OEC and SCVC) to condense the benzene boiled up. The purpose of the following calculations is to show that other simultaneous failures are required for the postulated scenario to occur.

Calculations

Assumptions and Notes

- Assumed cooling water supply temperature is 35°C
- Boiling and condensing is assumed to occur at the aqueous boiling temperature observed in the Precipitate Hydrolysis Experimental Facility (PHEF) operating experience indicates this is 72-74°C; 72°C is used for this analysis.
- Inert flow during this scenario is low, especially compared to the maximum benzene boilup rate. Therefore, nearly all condensation occurs at the boiling temperature; that is, it is reasonable to assume constant temperature condensation.
- Heat transfer coefficients (U's) are from PHEF OE operation and are consistent with similar values for the Precipitate Reactor.
- Other data (areas, flow rates, pressures, etc) were provided by DWPF personnel.
- 1 PCU = 1.8 Btu

Maximum OE Boilup

Maximum boilup is determined by assuming that heat transfer is limited by the heat transfer coefficient; that is, steam can be supplied at sufficient rate to maintain the steam coil at the 85 psig steam supply pressure (maximum steam condensing temperature).

$$+ \text{ Temperature of 85 psig steam} = 164^{\circ}\text{C}$$

$$+ \text{ OE steam coil area} = 51 \text{ ft}^2$$

$$+ U \text{ OE steam coil} = 200 \frac{\text{PCU}}{\text{hr-ft}^2\text{-}^{\circ}\text{C}}$$

$$+ Q_{\text{stm}} = UA\Delta T = 200 \frac{\text{PCU}}{\text{hr-ft}^2\text{-}^{\circ}\text{C}} * 51 \text{ ft}^2 *$$

$$(164-72)^{\circ}\text{C} = 938400 \frac{\text{PCU}}{\text{hr}}$$

For steam with $\Delta H_{\text{vap}} = 494 \text{ PCU/lb}$, this is equivalent to $\sim 1900 \text{ lbs/hr steam}$.

Heat Removed by OE cooling coil

If an interlock puts cooling water (CW) on the OE cooling coil, it will remove some of the heat provided by the steam.

$$+ \text{ CW supply temperature} = 35^{\circ}\text{C}$$

$$+ \text{ CW supply flow} = 100 \text{ gpm}$$

$$+ \text{ OE cooling coil area} = 15 \text{ ft}^2$$

$$+ U \text{ OE cooling coil} = 250 \frac{\text{PCU}}{\text{hr-ft}^2\text{-}^{\circ}\text{C}}$$

$$+ \Delta t_{\text{CW}} = \frac{(72-35) + (72-t_e)}{2} = 54.5 - 0.5t_e$$

$$+ Q_{\text{clng coil}} = mC_p \Delta t_{\text{CW}} = UA \Delta T,$$

substituting gives

$$100 \frac{\text{gal}}{\text{min}} * 500 \frac{\text{lbs/hr}}{\text{gal/min}} * 1 \frac{\text{PCU}}{\text{hr-ft}^2\text{-}^{\circ}\text{C}} * (t_e - 35)^{\circ}\text{C} =$$

$$15 \text{ ft}^2 * 250 \frac{\text{PCU}}{\text{hr-ft}^2\text{-}^{\circ}\text{C}} * (54.5 - 0.5t_e)^{\circ}\text{C}$$

$$t_e = 37.7^{\circ}\text{C} \Rightarrow \Delta t_{\text{CW}} = 2.7^{\circ}\text{C}$$

$$+ Q_{\text{clng coil}} = 100 \frac{\text{gal}}{\text{min}} * 500 \frac{\text{lbs/hr}}{\text{gal/min}} * 1 \frac{\text{PCU}}{\text{hr-ft}^2\text{-}^{\circ}\text{C}} * (2.7)^{\circ}\text{C} =$$

$$= 135000 \frac{\text{PCU}}{\text{hr}} \Rightarrow Q_{\text{OEC}} = 803400 \frac{\text{PCU}}{\text{hr}}$$

For ΔH_{vap} of benzene = 94 PCU/lb, the benzene boilup rate is ~ 8550 lbs/hr.

Required U for OEC

Given the heat load, determine the required heat transfer coefficient and compare to expected values and/or experience.

$$+ \text{ CW supply temperature} = 35^{\circ}\text{C}$$

$$+ \text{ CW supply flow} = 150 \text{ gpm}$$

$$+ \text{ OEC area} = 576 \text{ ft}^2$$

$$+ \Delta t_{\text{CW}} = \frac{Q}{mC_p} = \frac{803400 \frac{\text{PCU}}{\text{hr}}}{150 \frac{\text{gal}}{\text{min}} * 500 \frac{\text{lbs/hr}}{\text{gal/min}} * 1 \frac{\text{PCU}}{\text{hr-ft}^2\text{-}^{\circ}\text{C}}} = 10.7^{\circ}\text{C}$$

$$\Rightarrow t_e = 45.7^{\circ}\text{C}$$

$$+ \Delta T_{\text{lm}} = \frac{(72-35) - (72-45.7)}{\ln \frac{72-35}{72-45.7}} = 31.35^{\circ}\text{C}$$

$$+ U_{\text{OEC reqd}} = \frac{Q}{A\Delta T_{\text{lm}}} = \frac{803400 \frac{\text{PCU}}{\text{hr}}}{576 \text{ ft}^2 * 31.35^{\circ}\text{C}} = 44.5 \frac{\text{PCU}}{\text{hr-ft}^2\text{-}^{\circ}\text{C}}$$

This heat transfer coefficient is low for condensing; it would be expected to be several times higher. Typical values (Table 7-1, *Basic Heat Transfer*, Kreith & Black) are 175-700 PCU/hr-ft²-°C for steam/water (tube side/shell side) condensation and 50-175 PCU/hr-ft²-°C for organic vapor/water condensation. For organic vapors, the higher values are for lighter, lower-boiling, thinner organics while the lower values are for heavier, higher-boiling, thicker materials (benzene falls in the former category). U's of 80 or so have been measured in PHEF at aqueous boiling but the condensers do not have sufficient load on them to use all the area for heat transfer; therefore the calculated U's (which use the total heat exchanger area) would be low.

OEC without OE cooling coil

This is the same as the previous calculation except $Q = 938400 \text{ PCU/hr}$.

$$+ \Delta t_{CW} = \frac{Q}{mC_p} = \frac{938400}{150 * 500 * 1} = 12.5^{\circ}\text{C}$$

$$\Rightarrow t_e = 47.5^{\circ}\text{C}$$

$$+ \Delta T_{lm} = \frac{(72-35) - (72-47.5)}{\ln \frac{72-35}{72-47.5}} = 30.32^{\circ}\text{C}$$

$$+ U_{OEC} \text{ reqd} = \frac{Q}{A \Delta T_{lm}} = \frac{938400}{576 * 30.32} = 53.7 \frac{\text{PCU}}{\text{hr-ft}^2\text{-}^{\circ}\text{C}}$$

SCVC without OEC or OE cooling coil

This is the same analysis except that

$$+ \text{CW supply temperature} = 10^{\circ}\text{C}$$

$$+ \text{CW supply flow} = 100 \text{ gpm}$$

$$+ \text{SCVC area} = 584 \text{ ft}^2$$

$$+ \Delta t_{CW} = \frac{Q}{mC_p} = \frac{938400}{100 * 500 * 1} = 18.8^{\circ}\text{C}$$

$$\Rightarrow t_e = 28.8^{\circ}\text{C}$$

$$+ \Delta T_{lm} = \frac{(72-10) - (72-28.8)}{\ln \frac{72-10}{72-28.8}} = 52.03^{\circ}\text{C}$$

$$+ U_{scvc} \text{ reqd} = \frac{Q}{A \Delta T_{lm}} = \frac{938400}{584 * 52.03} = 53.7 \frac{\text{PCU}}{\text{hr-ft}^2\text{-}^{\circ}\text{C}}$$

Again, this condenser should have no problem handling the full boilup.

Quality Assurance

Heat transfer coefficients are derived from PHEF operating data stored by the Vantage data collection system running on the VAX computer located in 679-T. The heat transfer calculations were peer reviewed by D. P. Lambert.

9-30-92
D. P. Lambert, 704-1T
Peer Reviewer

END

DATE
FILMED

4/1/1993