DOE/PC/90300--T7

DOE/PC/90300--T7

DE93 004932

TECHNICAL PROGRESS REPORT

CONTRACT TITLE: Rapid Pressure Swing Absorption Cleanup of Post-Shift
Reactor Synthesis Gas

CONTRACT NUMBER: DE-FG22-90PC90300

CONTRACT PERIOD: 9/7/90 - 8/31/93

CONTRACTOR'S NAME: Dept. of Chemistry and Chemical Engineering
Stevens Institute of Technology
Hoboken, NJ 07030

SUBCONTRACTOR'S NAME: Department of Chemical Engineering, Chemistry
and Environmental Science
New Jersey Institute of Technology
Newark, NJ 07102

INVESTIGATORS: Dr. K. K. Sirkar
AT NJIT Dr. S. Majumdar
Mr. S. Bhaumik

REPORT NUMBER: 7

REPORT PERIOD: 4/1/92 - 7/31/92

REPORTING DATE: September 24, 1992

PREVIOUS REPORT DATE: April 30, 1992

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

MASTER

Overview of Progress

Before we proceed to RAPSAB studies with reactive absorbents, it is necessary to make an effort to compare experimental results with those predicted by the models. The only model developed so far (see Technical Progress Report No. 2) involved a type of RAPSAB cycle (Mode 3) for which limited data were acquired earlier. A number of experiments have, therefore, been conducted in this mode to characterize the absorption part of the cycle. A new and more compact module (Module No. 5) was made using 840 fibers and a teflon casing inside the stainless steel shell to exactly define the fiber packing density. This allows an exact calculation of Happel's free surface radius (see Technical Progress Report No. 2). Experiments were carried out using a CO₂ - N₂ mixture of around 10% CO₂ and balanced N₂ using both modules 4 and 5 over a wide range of absorption times.

Fabrication of Hollow Fiber Module #5

A new module (#5) containing 840 hydrophobic microporous Celgard X-10 fibers (Hoechst Celanese, SPD, Charlotte, NC) was fabricated. Fabrication involved preparation of a fiber bundle, inserting it in a shell and potting the ends of fiber set with a resin mixture to form a tube sheet. Finally, the module had to be tested for any leakage before using it in the experimental setup. Leakage test was done before making the fiber bundle to check fiber leakage if any.

A mat of fibers (ID: 100 μ m; OD: 150 μ m; number: 840) was first prepared on a polyethylene sheet over a laboratory bench top taking out six fibers at a time from a bobbin containing the fibers. They were cut to the desired length using a pair of scissors and both ends of the fibers were attached to a strip of scotch tape. The fibers were close to each other. Once such a mat was ready, the middle section of the fibers was kept straight and separated while the fiber ends at each side were potted in a 2 inch long hexagonal nipple (Cajon) first with a silicone rubber adhesive (RTV11, General Electric,

Waterford, NY) and then using an epoxy mixture prepared with 80:20 ratio of C-4 resin to activator D (Beacon Chemical Co., Mt. Vernon, NY). The hollow fibers were then pressurized internally with distilled water up to a pressure level of 50 psig. No fibers were found to be defective. The extra length of the fibers was then separated and discarded and the remaining part was rolled to prepare the fiber bundle. Distilled water was sprayed over the mat for easy handling of the fibers. Cotton threads (wetted) were tied loosely in the middle section as well as at the ends to keep the fibers together throughout the entire length. They were removed slowly as the fiber bundle was inserted into a specially constructed permeator shell. A $\frac{1}{8}$ " teflon pipe (ID: 0.24 inch; OD: 0.406 inch; Cole Parmer, Chicago, IL) was inserted into a 1/2 inch schedule 40 stainless steel pipe (length: 5 feet) to make a shell. Epoxy resin was used to fill the annular space between the two concentric pipes. The pipe was fitted with a 1/2 inch stainless steel street tee connection at each end. One opening of the tee was used to take out the fibers.

The shell was completely immersed in water when the fiber bundle was gently pulled through the shell assembly by using a cotton thread tied at one end of the bundle. Once the bundle was through both the ends, the excess water was removed and the assembly was air dried overnight. The fibers were potted at both ends with an epoxy resin (resin C4; activator: D; ratio: 4:1; Beacon Chemical Co., Mt. Vernon, NY) mixture. After the tube sheet formation was complete, the effective length of the module was determined to be 160 cm. The details of module are given in Table 1.

Before the new permeator was used, it was necessary to test it for any leak which could be either in the tube sheet due to incomplete wetting of the fibers by the resin or due to a defect or defects on the fiber surface or wall. Leak testing was done as follows.

The permeator shell was filled with distilled water and the shell side was pressurized by a N_2 cylinder, keeping the other shell side port completely closed. The pressure was increased slowly to 50 psig in steps of 10 psig. Observations were made at

each pressure level for any sign of water coming out through the tube sides. Finally, the pressure was maintained at 50 psig for two hours and the permeator was checked for any further leakage of water through the tube sides.

Experimental Procedure

The earliest setup with some modifications as reported in Technical Progress Report No.3 was used for all experiments. The schematic of the setup is given in Figure 1. All experiments were done in the following manner.

The feed gas was allowed to enter through the feed entrance port of the three way solenoid valve (3-WSV) (Figure 2) while the other end of the three-way solenoid valve was closed. The two-way (2-WSV) solenoid valve at the exit end of the permeator was opened simultaneously to withdraw the purified front of the mixture of gases. After some time the feed entrance port of the three-way solenoid valve as well as the two-way solenoid valve at the exit end were closed and simultaneously the other end of the three-way solenoid valve was opened for vacuum desorption for a certain length of time. This completed one whole cycle of operation. The time for the absorption part of the cycle was changed in different experiments. The desorption time of 15 seconds was maintained constant in all experiments.

After 1 to 2 hours of operation, purified gas mixture was injected into the GC periodically to find out the gas composition. A constant flow rate from the surge drum was maintained using a metering valve. This mode of operation is identified as **Mode 3**. Modes 1 and 2 are identified in Technical Progress Report No. 4.

Results

The time duration for absorption and desorption part of the simple cycle in Mode

3, the feed flow rate, and the purified product flow rate for all experiments are identified in Table 2 along with the purified gas composition in each case. The feed gas flow rate was kept constant for any given module as the absorption time was changed. One observes that as the absorption time increases the purified product gas flow rate increases; simultaneously the CO₂ content of the purified outlet product gas increases signifying lower levels of purification. For module 4, an absorption time of 10 seconds yielded the best product quality, e.g., 2.5% CO₂. Whereas for module 5, the same length of absorption time achieved a much lower CO₂ composition (1.48%).

The low absorption time experiments are, however, characterized by a low level of gas pressure in the system (~5 psi), a severe deficiency. This suggested the need for a delay time during which the two way solenoid valve at the outlet would remain closed allowing the gas pressure to rise to high levels. We have already implemented this in earlier experiments in Modes 1 and 2 (Technical Progress Report Nos. 4 and 5). The desorption time was maintained always at 15 seconds since the earlier studies indicated this to be the shortest time needed for effective desorption (see Technical Progress Report No. 6).

Table 1. Characteristics of Hollow Fiber Module No. 5

Effective Length	160 cm
No. of Fibers	840
Fiber ID	100 μm
Fiber OD	150 μm
Surface Area	6333 cm^2
Void Fraction	49.14%

Table 2. Experimental Results

Mode 3

Feed Composition: CO₂: 10.2%, N₂: Balance

Experiment No.	Module No.	Absorption Time (Seconds)	Desorption Time (Seconds)	Feed Flow Rate (cc/min)	Feed Pressure (psig)	Product Outlet Composition*	Product Flow Rate (cc/min)
7-1	4	10	15	150	5~10	CO ₂ : 2.50%	~5
7-2	4	13	15	150	10~15	CO ₂ : 2.68%	~8
7-3	4	16	15	150	~15	CO ₂ : 2.95%	~18
7-4	4	20	15	150	15~20	CO ₂ : 3.12%	~25
7-5	5	10	15	120	~5	CO ₂ : 1.48%	~5
7-6	5	12	15	120	~10	CO ₂ : 1.82%	~10
7-7	5	15	15	120	~15	CO ₂ : 2.39%	~15
7-8	5	18	15	120	~20	CO ₂ : 2.85%	~22
7-9	5	19.5	15	120	~25	CO ₂ : 3.42%	~32
7-10	5	21	15	120	~30	CO ₂ : 4.55%	~40
7-11	5	22.5	15	120	~30	CO ₂ : 5.64%	~50

* Balance N₂

Figure 1. Setup for RAPSAB Experiment

Figure 2. Solenoid Valve Locations in RAPSAB Apparatus

**DATE
FILMED**

2 / 9 / 93