DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

**BENCH-SCALE TESTING OF THE MULTI-GRAVITY
SEPARATOR IN COMBINATION WITH MICROCEL**

Contract No: DE-AC22-92PC92205
Second Quarterly Report

Reporting Period:
January 1, 1993 to March 31, 1993

Prime Contractor:

Center for Coal and Minerals Processing
Virginia Polytechnic Institute and State University
Blacksburg, Virginia 24061-0258

Subcontractors:

Carpco, Inc.
Roberts & Schaefer Company
Consolidation Coal Company
Kerr-McGee Coal Corporation

Prepared for:

Pittsburgh Energy Technology Center
U.S. Department of Energy
P.O. Box 10940
Pittsburgh, Pennsylvania 15236

Date Submitted: April 30, 1993

Contracting Officer's Representative: Carl Maronde

U.S./DOE Patent Clearance is not required prior to the publication of this document.

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DOE/PC/92205-T2
MAY 17 1993
RECEIVED
JUN 14 1993
OSTI

TABLE OF CONTENTS

TABLE OF CONTENTS	1
1.0 Abstract	2
2.0 Project Objectives	2
3.0 Project Task Updates	3
3.1 <u>Task 1.0 - Project Planning</u>	3
3.1.1 <i>Project Reporting</i>	3
3.2 <u>Task 4.0 - Sample Characterization</u>	4
3.2.1 <i>Preliminary Characterization</i>	4
3.2.2 <i>Release Analysis Characterization</i>	4
3.3 <u>Task 5.0 - Flowsheet Development/Engineering Design</u>	5
3.3.1 <i>Flowsheet Development</i>	5
3.3.2 <i>Engineering Design</i>	10
3.3.2.1 Circuit Layout	10
3.3.2.2 Piping	10
3.3.2.3 Instrumentation	11
3.3.2.4 Controls	11
3.3.2.5 Motor Control Center	12
3.3.2.6 Detailed Equipment Specifications	12
3.3.3 <i>Cost Analysis</i>	12
3.4 <u>Task 6.0 - Procurement and Fabrication</u>	12
3.4.1 <i>Bidding</i>	12
3.4.2 <i>Procurement and Fabrication</i>	13
3.5 <u>Task 12.0 - Sample Analysis</u>	14
3.5.1 <i>Standard Analysis</i>	14
Appendix I: Particle size and assay for Pittsburgh #8 and Illinois #6 seam coals.	15
Appendix II: ET Circuit engineering design drawings.	19

1.0 Abstract

Work this quarter focused on the development of the engineering design specifications for the ET Test Circuit. Process flowsheets and detailed equipment specifications were finalized. Based on this information, bid packages were assembled and purchase orders were issued for all of the necessary process equipment. The design and procurement information is summarized in the *ET Circuit Design Report* submitted to the DOE's COR this quarter. Final drafts of the *ET Circuit - System Safety Analysis*, *Nuclear Density Gauge - System Safety Analysis* and *Operating Manual/SOP* were also completed and submitted to the COR this quarter.

Preliminary characterization studies were also initiated this quarter. Tests were conducted to determine the grinding conditions required to achieve the desired particle size distributions for the characterization work. Flotation release analysis tests were conducted on both the Pittsburgh #8 and Illinois #6 seam coals as a function of grind size.

2.0 Project Objectives

The primary objective of the proposed work is to design, install, and operate an advanced fine coal processing circuit combining the Microcel and Multi-Gravity-Separator (MGS) technologies. Both of these processes have specific advantages as stand-alone units. For example, the Microcel column effectively removes ash-bearing mineral matter, while the MGS efficiently removes coal-pyrite composites. By combining both unit operations into a single processing circuit, synergistic advantages can be gained. As a result, this circuit arrangement has the potential to improve coal quality beyond that achieved using the individual technologies.

In addition to the primary objective, secondary objectives of the proposed test program include:

- *Circuit Optimization:* The performance of each unit operation, individually and combined, will be optimized by conducting parametric studies as a function of key operating variables. The goal of this work is to maximize the rejections of pyritic sulfur and ash while maintaining a high energy recovery.
- *Process Variability:* The steady-state performance of the optimized processing circuit will be studied (i) by conducting several long-duration test runs over a period of several days and (ii) by testing coal samples from other sources specified by the participating coal companies.
- *Process Evaluation:* Detailed technical and economic evaluations will be conducted to examine the feasibility of the proposed concept for fine coal cleaning on an industrial scale. This evaluation will include a projected cost-benefit analysis and a review of all test data, engineering analyses, scale-up procedures, and process deficiencies.

The test work will be conducted at the Pittsburgh Energy Technology Center's Coal Preparation Process Research Facility (CPPRF) located in Pittsburgh, Pennsylvania. The CPPRF is a state-of-the-art pilot-scale facility for coal preparation research and testing. The Emerging Technology (ET) section of the pilot plant will be used for testing the combined Microcel and MGS circuit. The ET area, and subsequently installed mezzanine, is adjacent to the pilot plant and was established for testing new and emerging technologies in coal preparation. This facility is ideally suited for pilot-scale test work due to the availability of all necessary ancillary facilities (i.e., bulk solids handling, preparation, and waste disposal). In addition, the necessary environmental, safety and health aspects related to the handling and disposal of waste are already in place.

3.0 Project Task Updates

3.1 Task 1.0 - Project Planning

3.1.1 *Project Reporting*

The required monthly project reports have been submitted as outlined in the final Project Work Plan. These reports were submitted on the twenty-fifth of each month (starting in November, 1992) and include the following:

- Project Status Report
- Summary Report
- Milestone Schedule Status
- Cost Management Report

In addition, several topical reports were also submitted this quarter. These include the following:

ET Circuit Design Report - This document details all aspects of the ET Test Circuit. Process flowsheets, equipment layouts, piping and instrumentation, and electrical layouts were described in detail.

ET Circuit - System Safety Analysis - This report provides a detailed description of the flowsheet and all associated equipment. An extensive hazard evaluation was completed for the test site and all process equipment. Worker safety training, health hazards, and weekly safety meetings were discussed.

Nuclear Density Gauge - System Safety Analysis - This document parallels the ET Circuit System Safety Analysis; however, it specifically addresses personnel and environmental safety regarding the on-line nuclear density gauges.

Operating Manual/SOP - This manual describes the operation of the various components in the ET circuit and outlines the responsibilities of the project participants involved in the day-to-day operation and evaluation of the circuit. Specifications are provided regarding normal start-up, operation, and shutdown procedures. Emergency shutdown procedures are also provided.

A design review meeting was held at PETC on February 4, 1993. The following representatives from the CCMP and Roberts & Schaefer were present.

- *CCMP:* Jerry Luttrell - Associate Professor
Mike Mankosa - Research Scientist
- *Roberts & Schaefer:* Bob Jackson - Project Manager
Bob Schaefer - Process Engineer
Wayne Kirkpatrick - Electrical Engineer

The complete ET Test Circuit design specifications were presented to DOE at that time. Based on the results of this meeting, the draft ET Circuit Design Report was assembled and submitted to DOE.

3.2 Task 4.0 - Sample Characterization

3.2.1 *Preliminary Characterization*

A variety of laboratory characterization studies are planned to evaluate the potential cleanability of the base coal samples. These include (at a minimum) centrifugal washability and release analysis. Preliminary plans include evaluating each coal at three different grind sizes (-28 mesh, -65 mesh and -200 mesh). In each case, a 90% passing size will be used as the defining criteria.

3.2.2 *Release Analysis Characterization*

To characterize the performance of the flotation column in the ET Test Circuit, release analysis tests were conducted at several grind sizes for both the Pittsburgh #8 and Illinois #6 seam coals. The release analysis test provides an indication of the ultimate cleanability for a particular coal by flotation.

Each feed coal was pulverized in a laboratory hammer mill. Several different product size distributions were used for the test work: -28 mesh, -65 mesh and -200 mesh. Similar particle size distributions will be used in both the laboratory and pilot-scale tests, allowing for comparison of the release analysis results to those obtained by the ET circuit column. The product particle size distributions and size-by-size ash and total sulfur contents for each coal are shown in Tables 1.0-5.0 in Appendix I.

To determine the reliability of the release analysis test procedure, several duplicate tests were conducted on -65 mesh Illinois #6 seam coal. Results from these tests, shown in Figures 1 and 2, indicate that the release analysis procedure provides reproducible results. In this case, combustible recovery was plotted as a function of ash and sulfur rejection to normalize the effect of changes in feed quality.

Figures 3 and 4 show the results of release analysis tests conducted on an Illinois #6 coal as a function of grind size (i.e., -28 and -65 mesh). As expected, an increase in product ash rejection is observed with a reduction in particle size; however, essentially no improvement was observed in sulfur rejection. This finding can be explained by either the inadequate liberation of pyritic sulfur, or the natural floatability of coal pyrite. The latter is the subject of an ongoing DOE investigation (DE-AC22-92PC92246).

Figure 5 shows similar results for release analysis tests conducted on -28, -65 and -200 mesh Pittsburgh #8 seam coal. As shown, a slight improvement in product ash rejection occurs as the particle size is reduced. In addition, and similar to the Pittsburgh coal, particle size does not appear to dramatically impact the total sulfur rejection (Figure 6). These findings support the conclusion that a flotation-based separation process is acceptable for the rejection of ash-bearing minerals; however, it is less effective for the removal of pyritic sulfur. As previously stated, a density-based separation would be more effective for the rejection of pyritic sulfur due to the large difference in specific gravities of coal and pyrite.

In addition to the previously described work, additional release analysis tests will be conducted on products obtained using different grinding techniques. As shown in Tables 1.0-5.0, a significant portion of fines were generated by the grinding process in most cases. This is typical of an impact-type crusher, such as a hammer mill. It is recommended that future grinding tests use a laboratory rod mill to minimize the production of fines; thus providing a better indication of the effect of particle size on flotation performance.

3.3 Task 5.0 - Flowsheet Development/Engineering Design

3.3.1 *Flowsheet Development*

The bulk, run-of-mine samples will be held at a near-by storage facility. This material will be transferred by truck in 5-ton increments and off-loaded to the coarse coal storage bins at the CPPRF. The run-of-mine coal will be fed from the storage silos to the CPPRF comminution circuit to produce feed slurries for the ET circuit. Slurry will enter the test circuit through a three-way automatic valve located above the sludge storage tank, elev. 1106'-6". The automatic valve will be configured to either send feed slurry to the ET circuit, or by-pass it into the sludge storage tank. From this point, the feed slurry can be directed to any of the three process feed sumps (Unit No.'s 101, 102 and 103), allowing each circuit to operate independently.

Figure 1. Combustible recovery versus total ash rejection obtained from replicate release analysis tests on -65 mesh Illinois #6 seam coal.

Figure 2. Combustible recovery versus total sulfur rejection obtained from replicate release analysis tests on -65 mesh Illinois #6 seam coal.

Figure 3. Combustible recovery versus ash rejection for -28, and -65 mesh Illinois #6 seam coal.

Figure 4. Combustible recovery versus total sulfur rejection for -28 and -65 mesh Illinois #6 seam coal.

Figure 5. Combustible recovery versus ash rejection for -28, -65 and -200 mesh Pittsburgh #8 seam coal.

Figure 6. Combustible recovery versus total sulfur rejection for -28, -65 and -200 mesh Pittsburgh #8 seam coal.

The process feed sumps will be arranged so that the Microcel, water-only cyclone, or MGS can be independently operated. This approach allows each device to be tested separately without being influenced by the performance of other unit operations. The process sumps will be equipped with side-mounted mixers to maintain the solids in a homogeneous suspension. In addition, the process sumps will be designed with dished-shaped bottoms to facilitate mixing.

Each process sump will be equipped with a variable speed (split sheave) pump to allow for variations in pressure and flow in each test circuit. Slurry from the pump discharge will be circulated at relatively high velocities to the point of discharge and returned to the sump. This approach ensures that the solids remain in suspension throughout the circuit. Feed for each unit operation will be bled-off the respective circulation line through a pneumatic pinch valve. Feed rate to each unit operation will be determined using mass flow sensors. Water addition lines will also be provided for each sump to regulate the feed solids concentration. The flow rate of dilution water will also be regulated by pneumatic pinch valves.

Each sump/pump combination will be equipped with a drain line and a constant head overflow box. These lines will be directed to the ET waste sump located on ground floor (elev. 1086'-6). In addition, the products from all test circuits will be discharged to the ET waste sump. Slurry from the waste sump will be pumped directly to the CPPRF thickener feed de-aeration tank for disposal. Emergency overflow from the waste sump will report to the CPPRF's existing ground floor trenches and sent to the thickener via ground floor sump pumps.

The ET circuit is designed to allow for testing of the following four circuit configurations:

- Microcel,
- Multi-Gravity Separator,
- Microcel/Multi-Gravity Separator, and
- Microcel/Water-Only Cyclone/Multi-Gravity Separator.

The Microcel and MGS circuits allow for independent operation of each unit, providing a direct comparison of the performance of each device. The Microcel/MGS circuit will be used to determine the advantages of the combined processing scheme. In this circuit, the flotation product from the Microcel will be de-aerated and fed directly to the MGS. The final circuit incorporates a water-only cyclone to remove a portion of clean coal from the column product prior to feeding to the MGS. The intent of this circuit is to unload the MGS unit to provide a higher circuit throughput. In each of the above described circuits all final product and reject streams will be discharged to the ET waste sump. The material-balanced flowsheets for each circuit are included in Appendix II.

The process feed sumps will be arranged so that the Microcel, water-only cyclone, or MGS can be independently operated. This approach allows each device to be tested separately without being influenced by the performance of other unit operations. The process sumps will be equipped with side-mounted mixers to maintain the solids in a homogeneous suspension. In addition, the process sumps will be designed with dished-shaped bottoms to facilitate mixing.

Each process sump will be equipped with a variable speed (split sheave) pump to allow for variations in pressure and flow in each test circuit. Slurry from the pump discharge will be circulated at relatively high velocities to the point of discharge and returned to the sump. This approach ensures that the solids remain in suspension throughout the circuit. Feed for each unit operation will be bled-off the respective circulation line through a pneumatic pinch valve. Feed rate to each unit operation will be determined using mass flow sensors. Water addition lines will also be provided for each sump to regulate the feed solids concentration. The flow rate of dilution water will also be regulated by pneumatic pinch valves.

Each sump/pump combination will be equipped with a drain line and a constant head overflow box. These lines will be directed to the ET waste sump located on ground floor (elev. 1086'-6). In addition, the products from all test circuits will be discharged to the ET waste sump. Slurry from the waste sump will be pumped directly to the CPPRF thickener feed de-aeration tank for disposal. Emergency overflow from the waste sump will report to the CPPRF's existing ground floor trenches and sent to the thickener via ground floor sump pumps.

The ET circuit is designed to allow for testing of the following four circuit configurations:

- Microcel,
- Multi-Gravity Separator,
- Microcel/Multi-Gravity Separator, and
- Microcel/Water-Only Cyclone/Multi-Gravity Separator.

The Microcel and MGS circuits allow for independent operation of each unit, providing a direct comparison of the performance of each device. The Microcel/MGS circuit will be used to determine the advantages of the combined processing scheme. In this circuit, the flotation product from the Microcel will be de-aerated and fed directly to the MGS. The final circuit incorporates a water-only cyclone to remove a portion of clean coal from the column product prior to feeding to the MGS. The intent of this circuit is to unload the MGS unit to provide a higher circuit throughput. In each of the above described circuits all final product and reject streams will be discharged to the ET waste sump. The material-balanced flowsheets for each circuit are included in Appendix II.

DO NOT MICROCCEL
THIS PAGE

3.3.2 *Engineering Design*

3.3.2.1 **Circuit Layout**

The column/MGS circuit will be installed in the newly-constructed mezzanine area adjacent to the ET test area. The lower three levels of the PTI test module will also be re-used. The top level will be removed to allow crane access for installation of equipment. Detailed plan and elevation drawings showing the equipment layout are provided in Appendix II.

As shown in the plan drawings, the process waste sump/pump circuit will be located on the ground floor (elev. 1086'-6), allowing for gravity transport of slurry from all sump overflows, drain lines and unit operations. The process feed sumps and Microcel base will be located on the first mezzanine level (elev. 1096'-6). The MGS and cyclone feed sump/pumps will be located on the existing PTI structure and the column feed sump/pump on the west side of the existing sludge storage tank. The latter was necessary to provide sufficient access around all process equipment. The Microcel base is located in the northeast corner of elevation 1086'-6 and the column passes through the 1096'-6 elevation. The water-only cyclone will be mounted directly to the cyclone feed sump. The column overflow weir, reagent feeders and MGS will be located on the second mezzanine level (elev. 1106'-6). The MGS will be placed on the PTI structure and the reagent feeders will be located against the north wall of the facility.

The above described circuit layout was selected to minimize piping runs and installation costs, while maximizing the space between adjacent process equipment. The latter facilitates equipment maintenance and ensures safe working conditions. In addition, this circuit layout will provide an opportunity to re-use existing mechanical systems installed by PTI.

3.3.2.2 **Piping**

System utilities (i.e. compressed air, clarified water, and process water) will be provided by DOE/PETC. Tie-in points to the CPPRF utility circuits will be arranged with and approved by DOE/PETC prior to installation. Maximum anticipated utility consumption will be as follows:

- Process Water - 50 gpm
- Air - 25 scfm @ 80 psi (process)
10 scfm @ 80 psi (instrument)

All incoming utility piping will be equipped with manual shut-off valves located at the tie-in points to completely isolate the test circuit if necessary. Water/slurry lines and pneumatic lines will be constructed of CPVC (80 psi minimum rating) and schedule 40 steel (150 psi minimum rating), respectively. Detailed diagrams showing the proposed piping layout are provided in Appendix II.

3.3.2.3 Instrumentation

Several different types of remote sensors will be used in the ET test circuit. These include the following:

- venturi flow meters,
- magnetic flow meters,
- nuclear density gauges,
- paddlewheel flow meters,
- differential pressure transmitters, and
- high/low level indicators.

The venturi flow meter will be used to meter air to the Microcel flotation column. A magnetic flowmeter and nuclear density gauge will be used on each unit process sump/pump circulation system to monitor mass flow rates. Paddlewheel flow meters will be used exclusively for water flow measurement. The DP cells and high/low level indicators will be used for level detection in the Microcel and waste sump, respectively. All instrumentation will be equipped with a remote 4-20 mA signal output. In addition, a number of pneumatically-actuated control valves will be used to regulate process liquid and slurry flow rates. A complete instrumentation diagram is provided in Appendix II.

3.3.2.4 Controls

The ET circuit control panel will be located on the second mezzanine level (elev. 1106'-6) next to the sludge storage tank. The control panel will house all of the necessary electrical and pneumatic instrumentation interfaces, including:

- LED displays for all water and slurry flow meters,
- LED displays for all density meters,
- LED displays for all pressure sensors,
- LED display for column air flow measurement,
- PID controller for column level control,
- PID controller for column hold-up control,
- Pressure regulators/gauges for pneumatic valve control,
- Start/stop switches for all motor drives, and
- Emergency stop button.

A layout diagram of the instrument control panel is included in Appendix II.

The bulk of the above described instrumentation and controls are provided for on-line sensing and operation; however, two stabilizing control loops will also be installed in the ET circuit. The first controls the column level. In this loop, a pressure reading provided by a DP cell is used to control the column tailings discharge rate which, in turn, is regulated by a

pneumatic pinch valve. Valve response is controlled by a stand-alone PID controller. Similarly, a second control loop will be installed to regulate frother addition to the bubble generation circuit. In this case, frother rate is adjusted to maintain a constant volume air fraction in the column. This fractional air hold-up is determined from differential pressure measurements in the column collection zone. It is anticipated, however, that this latter control loop will only be necessary if wide fluctuations occur in either the circuit volume feed rate or percent solids. Finally, a high/low sump level controller will be installed on the ET circuit waste sump as a safety precaution. This controller will prevent overflow and/or dry pumping conditions within the waste sump.

3.3.2.5 Motor Control Center

All power to the ET test circuit will be supplied from a central motor control center (MCC) located on the east side of the sludge storage tank on elevation 1106'-6". A single supply line will be connected to the ET MCC from the existing CPPRF MCC to power the test circuit. All equipment in the ET circuit will be powered by the local MCC. This approach minimizes the impact to the existing CPPRF MCC and facilitates installation of the test circuit. All electricals will have a NEMA 4 rating and will not be interlocked to any existing CPPRF equipment. Detailed electrical schematics for the MCC and all associated equipment are provided in Appendix II.

3.3.2.6 Detailed Equipment Specifications

A detailed listing of all major equipment in the ET circuit has been assembled. This listing provides unit dimensions, capacities and requirements for air, water and power. Note that the CCMP plans to use several pieces of equipment currently used by PTI. These include the reagent feed tanks and a magnetic flow meter. In addition, the CCMP will provide several pumps required for the circuit.

3.3.3 Cost Analysis

A detailed breakdown of estimated costs for equipment/materials, spare parts, and the installation subcontract, along with preliminary vendor selection, has been completed. The costs have been included in the ET Circuit Design Report.

3.4 Task 6.0 - Procurement and Fabrication

3.4.1 Bidding

Bid packages were released by Roberts & Schaefer during the first quarter of this year for all of the major equipment within the test circuit. Detailed specifications were provided for

the process sumps, pumps, mixers and electronics. The following list details the equipment specifications and bid responses.

Item	Description	Bid Responses
Mixers	To maintain a uniform suspension of 3/4-mm x 0 coal (s.g. 1.5) in a water slurry throughout an open-top tank. Abrasion resistant, 460 VAC, 3ph., 60 Hz, TEFC.	Philadelphia Mixers EMI Incorporated Lightnin
Pumps	Slurry will be 3/4-mm x 0 coal in water at 10% weight concentration with 1.05 slurry s.g. Pump to be cast iron, vari-speed V-belt drive, overhead motor mounts; 460 VAC, 3ph., 60 Hz, TEFC.	ITT A-C Pump Wilfley Goulds Cole-Parmer
Electronics	MCC enclosure and all necessary electrical items per detailed design drawings (9234-E0 thru 9234-E7).	McJunkin
Electronics Assembly	Assemble and shop wire the Motor Starter Panel as shown on R&S dwgs. 9234-E2, E4, E5 and E6.	Cross Electronics
Sumps	Process sumps fabricated from 1/4-inch M.S. plate; dish bottom, flange drain and pump connections, overflow, baffle and support legs. Two coat shop paint.	McGrew Welding & Fabricating, Inc.

3.4.2 Procurement and Fabrication

Based on responses to the above bid packages, vendors were selected for the major process equipment. The following vendors were selected based on either competitiveness or technical superiority.

- *Mixers* - Lightnin
- *Pumps* - Goulds/Cole-Parmer Instrument Co.
- *Electronics* - McJunkin
- *Component Assembly* - Cross Electronics, Inc.
- *Sumps* - McGrew Welding and Fabricating, Inc.

Purchase orders were issued by Roberts & Schaefer for requisition of the above equipment. All equipment is scheduled for delivery to the DOE/PETC CPPRF at the beginning of Task 7.0 (Process Module Installation).

3.5 Task 12.0 - Sample Analysis

3.5.1 *Standard Analysis*

Sample analysis is being conducted as required for the characterization studies. All samples are routinely analyzed for moisture, volatile matter, fixed carbon, ash, heating content, pyritic, and total sulfur content. Particle size analyses are being conducted as required to characterize the feed particle size distributions.

Appendix I: Particle size and assay for Pittsburgh #8 and Illinois #6 seam coals.

Table 1.0 - Size-by-size sulfur and ash percent for Illinois #6 seam coal (28 mesh x 0).

Size (Mesh)	Wt (%)	Cumulative Wt (%)	Ash (%)	Total Sulfur (%)
+28	0.71	100.0	51.72	3.25
28 x 35	4.91	99.29	44.70	4.91
35 x 48	6.16	94.38	46.75	4.00
48 x 65	11.64	88.22	46.50	5.77
65 x 100	8.18	76.58	33.79	4.36
100 x 150	11.02	68.40	33.88	5.01
150 x 200	8.62	57.38	30.64	4.85
200 x 270	5.62	48.76	33.20	5.75
270 x 400	8.24	43.14	32.80	5.84
-400	34.90	34.90	56.53	3.48

Table 2.0 - Size-by-size sulfur and ash for Illinois #6 seam coal (65 mesh x 0).

Size (Mesh)	Wt (%)	Cumulative Wt (%)	Ash (%)	Total Sulfur (%)
+65	7.54	100	55.49	5.04
65 x 100	10.89	92.46	46.70	5.99
100 x 150	13.10	81.57	33.60	5.82
150 x 200	14.02	68.47	33.56	5.11
200 x 270	9.54	54.45	32.67	5.36
270 x 400	11.10	44.91	36.43	5.86
-400	44.70	33.81	56.53	3.52

Table 3.0 - Size-by-size sulfur and ash percent for Pittsburgh #8 seam coal (28 mesh x 0).

Size (Mesh)	Wt (%)	Cumulative Wt (%)	Ash (%)	Total Sulfur (%)
+28	0	100.0	0	0
28 x 35	28.06	100.0	29.71	3.64
35 x 48	19.17	71.94	14.07	3.47
48 x 65	14.34	52.27	13.33	4.13
65 x 100	9.91	38.43	14.10	4.07
100 x 150	9.09	28.52	13.93	4.03
150 x 200	5.25	19.43	8.99	3.52
200 x 270	3.85	14.18	13.73	4.96
270 x 400	2.71	10.33	12.93	4.40
-400	7.62	7.62	21.78	3.55

Table 4.0 - Size-by-size sulfur and ash for Pittsburgh #8 seam coal (65 mesh x 0).

Size (Mesh)	Wt (%)	Cumulative Wt (%)	Ash (%)	Total Sulfur (%)
+65	5.78	100.0	17.15	3.48
65 x 100	7.98	94.22	14.10	3.76
100 x 150	14.71	86.24	13.42	3.48
150 x 200	14.11	71.53	12.05	3.80
200 x 270	10.57	57.42	12.25	3.75
270 x 400	13.25	46.85	12.70	3.76
-400	33.60	33.60	17.52	2.93

Table 5.0 - Size-by-size sulfur and ash for Pittsburgh #8 seam coal (200 mesh x 0).

Size (Mesh)	Wt (%)	Cumulative Wt (%)	Ash (%)	Total Sulfur (%)
100 x 150	0	100.00	0	0
150 x 200	5.43	100.00	13.14	3.38
200 x 270	24.16	94.57	12.16	3.77
270 x 400	39.57	70.41	12.29	4.06
-400	30.84	30.84	31.70	3.67

Appendix II: ET Circuit engineering design drawings.

DETAILED LIST OF MAJOR EQUIPMENT

QUAN. REQ'D	EQUIPMENT DESCRIPTION	UNIT SIZE	CAPACITY	POWER	AIR	WATER
1	Microcel Column (VCCMP)	30" I.D. x 15 ft. H	500 lbs./hr. 10 GPM	-	25 SCFM @ 25 PSI	25-30 GPM
1	MGS Unit (VCCMP)	5'-5" L x 2'-4" W x 3'-8" H	200 lbs./hr. 3 GPM	0.92 KW	-	1-3 GPM
1	2" W.O. Cyclone (VCCMP)	4" L x 3 1/2" W x 10" H	500 lbs./hr. 10 GPM	-	-	-
1	Microcel Sump	2'-6" dia. x 4'-3" H	100 Gal.	-	-	-
1	MGS Sump	2'-6" dia. x 4'-3" H	100 Gal.	-	-	-
1	Cyclone Sump	2'-6" dia. x 4'-3" H	100 Gal.	-	-	-
1	Waste Sump	5' Dia. x 5'-6" H	587 Gal.	-	-	-
1	Microcel Aeration Pump (VCCMP)	45" L x 25" W x 45" H	400 GPM	10 HP	-	1 GPM
1	MGS Feed Pump	20" L x 9 1/2" W x 9 5/16" H	0.1 - 3.5 GPM	1/4 HP	-	-
1	MGS Recycle Pump	43" L x 21" W x 38" H	30 GPM	3 HP	-	1 GPM
1	Microcel Recycle Pump	43" L x 21" W x 38" H	30 GPM	3 HP	-	1 GPM
1	Waste Sump Pump	43" L x 21" W x 38" H	50 GPM	3 HP	-	1 GPM
1	Cyclone Recycle Pump	43" L x 21" W x 38" H	30 GPM	5 HP	-	1 GPM
2	Reagent Pumps (VCCMP)	5" Dia. x 10" L	6 ML/Min.	115 VAC	-	-
2	Reagent Feed Tanks (PTI)	15" dia. x 18" H	5 Gal.	-	-	-
3	Sump Mixers - (Microcel, MGS, & Cyclone)	12" Dia. x 60" L	-	0.65 HP	-	-
1	Sump Mixer - (Waste Sump)	15" dia. x 78" L	-	2.3 HP	-	-
1	Foam Breaker Pump - (VCCMP)	18" L x 12" W x 24" H	20 GPM	2 HP, 440 V	-	-
1	MCC Panel	72" L x 22" W x 56" H	-	35 HP	-	-
1	Control Panel	36" L x 10" W x 48" H	-	115 VAC	10 SCFM - 80 PSI	-
3	Coriolis Mass Flow Meters (VCCMP)	15" L x 5" W x 21" H	33 GPM	16 W	-	-
1	Magnetic Flowmeter - (VCCMP/PTI)	8" dia. x 14" L	30 GPM	115 VAC	-	-
1	Miscellaneous (Instruments, Control Valves)	-	-	115 VAC	10 SCFM - 80 PSI	-

NO.	DATE	DESCRIPTION OF REVISION	NO.	DATE	DESCRIPTION OF REVISION

PLAN @ EL. 1106'-6" / PLATFORM

DOE CONTRACT NO. DE-AC22-92PC92205

ROBERTS & SCHAFFER
DIVISION OF STEEL NATIONAL INDUSTRIES
ENGINEERS AND ARCHITECTS
CHICAGO - PITTSBURGH - SALT LAKE CITY

LAYOUT - PLAN VIEWS
VIRGINIA POLYTECHNIC INSTITUTE & STATE UNIVERSITY
BENCH-SCALE TESTING OF ADS & MICROCEL UNITS
AT PITTSBURGH ENERGY TECHNOLOGY CENTER

DATE BY J. DeBenedictis

ENGINEER BY C.W. [Signature]

ARCHITECT BY [Signature]

SCALE 1/4" = 1'-0"

DATE 1-25-98

9234-L1

This Drawing in Design and Detail is our Property and must not be used except in connection with our work. All Rights of Design or Invention are Reserved.

SECTION A-A

SECTION B-B

NO.	DATE	DESCRIPTION OF REVISION	NO.	DATE	DESCRIPTION OF REVISION

ROBERTS & SCHAEFER
DIVISION OF SLOAN BATHING, HEATING AND
Company
ENGINEERS AND CONTRACTORS
CHICAGO · PITTSBURGH · SALT LAKE CITY

MADE BY <i>J. DeMarino</i>	
RECEIVED BY <i>C. W.</i>	CONDUCTED <i>[Signature]</i>
APPROVED BY	

Serial	4210	Date	1-22-93
9234-L2			

THIS DRAWING IN DESIGN AND DETAIL, IS OUR PROPERTY AND MUST NOT BE USED EXCEPT IN CONNECTION WITH OUR WORK. ALL RIGHTS OF DESIGN OR INVENTION ARE RESERVED.

PLAN P. 1106-6 T/PLATFORM

O.O.C. CONTRACT NO. DE-AC22-92 PL 92205

ROBERTS & SCHAEFER
DIVISION OF FLOW NATIONAL INDUSTRIES, INC.
 ENGINEERS AND CONTRACTORS
 CHICAGO · PITTSBURGH · SALT LAKE CITY

PIPING - PLAN VIEWS
 VIRGINIA POLYTECHNIC INSTITUTE & STATE UNIVERSITY
 SPARK-SCALE TESTING OF HGS & MICROCEL UNITS
 AT PITTSBURGH ENERGY TECHNOLOGY CENTER

DATE: J. DeMaggio
 CHECKED BY: E. Schaefer
 APPROVED BY:

SCALE: 1" = 1'-0"
 DATE: 1-25-93
 9234-PI

This Drawing is Design and Detail, is the Property of the Company and must not be used except in connection with the work for which it was prepared. All Rights of Invention are Reserved.

SECTION D-D

SECTION C-C

D.O.E. CONTRACT NO. DE-AC22-92PC92205

ROBERTS & SCHAFER
 COMPANY
 DIVISION OF BAKER INTERNATIONAL, INC.
 CHICAGO - PITTSBURGH - SALT LAKE CITY

PIPING - ELEVATION SECTIONS
 VIRGINIA POLYTECHNIC INSTITUTE & STATE UNIVERSITY
 BENCH-SCALE TESTING OF MES & MICROCEL UNITS
 AT PITTSBURGH ENERGY TECHNOLOGY CENTER

DESIGNED BY J. DeThorne	SCALE 1" = 1'-0"	SHEET NO. 1-35-RJ
CHECKED BY R. SWANER	9234-P2	
APPROVED BY		

THIS DRAWING IS DESIGN AND DETAIL, IS OUR PROPERTY AND MUST NOT BE USED EXCEPT IN CONNECTION WITH OUR WORK. ALL RIGHTS OF DESIGN OR INVENTION ARE RESERVED.

REV	DATE	DESCRIPTION OF REVISION	REV	DATE	DESCRIPTION OF REVISION

LEGEND

(XX-X)	DEVICE LOCATED AT CONTROL PANEL
(XX-X)	DEVICE LOCATED IN FIELD
---	AIR PIPING
---	ELECTRICAL SIGNAL
⊗	PNEUMATIC PINCH VALVE
⊗	MANUAL BALL VALVE
I/P-X	CURRENT TO PRESSURE TRANSDUCER
PG-X	PRESSURE GAUGE
PR-X	PRESSURE REGULATOR
PT-X	PRESSURE TRANSMITTER
FT-X	FLOW TRANSMITTER
LT-X	LEVEL TRANSMITTER
LED-X	LED DISPLAY
LC-X	LEVEL CONTROLLER
AFC-X	AIR FLOW CONTROLLER
MFT-X	MASS FLOW TRANSMITTER

COLUMN/MCS/CYCLONE

REV	DATE	DESCRIPTION OF REVISION	REV	DATE	DESCRIPTION OF REVISION

IRCUIT

DOE CONTRACT NO. DE-AC22-92PC92205

ROBERTS & SCHAEFER
DIVISION OF ELEM INDUSTRIES, INC.
ENGINEERS AND CONTRACTORS
CHICAGO-SALT LAKE CITY-PITTSBURGH

P & ID DIAGRAM
VIRGINIA POLYTECHNIC INSTITUTE & STATE UNIVERSITY
BENCH-SCALE TESTING OF MGS & MICROCEL UNITS
AT PITTSBURGH ENERGY TECHNOLOGY CENTER

DESIGNED BY S. GRAHAM

ENGINEERED BY

APPROVED BY

SCALE NONE

SHEET 2-3-83

9234-PID

ALL RIGHTS ARE RESERVED BY THE DESIGNER. NO PART OF THIS DOCUMENT MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT PERMISSION IN WRITING FROM THE DESIGNER.

NO.	DATE	DESCRIPTION OF REVISION	NO.	DATE	DESCRIPTION OF REVISION

DOE CONTRACT NO. DE-AC22-92PC92205		NAME OF: WLK		SCALE: 3"=1'-0"	DATE: 1-19-93
CONTROL PANEL LAYOUT		DESIGNED BY:	APPROVED BY:	PROJECT NO.	
VIRGINIA POLYTECHNIC INSTITUTE & STATE UNIVERSITY				9234-E1	
BENCH-SCALE TESTING OF MGS & MICROCELL UNITS					
AT PITTSBURGH ENERGY TECHNOLOGY CENTER					

ROBERTS & SCHAPIRO
DIVISION OF EICHMANN INDUSTRIES, INC.
ENGINEERS AND CONTRACTORS
CHICAGO-SALT LAKE CITY-PITTSBURGH

DOE CONTRACT NO. DE-AC22-92PC92205

ROBERTS & SCHAEFER
DIVISION OF ELGIN NATIONAL INDUSTRIES, INC.
ENGINEERS AND CONTRACTORS
CHICAGO-SALT LAKE CITY-PITTSBURGH

INSTRUMENTATION & CONTROL PANEL WIRING
VIRGINIA POLYTECHNIC INSTITUTE & STATE UNIVERSITY
BENCH-SCALE TESTING OF MGS & MICROCEL UNITS
AT PITTSBURGH ENERGY TECHNOLOGY CENTER

DATE: 1/19/83	BY: WLK	REVIEWED BY: WLK	APPROVED BY: WLK
9234-E4			◆

REV.	DATE	DESCRIPTION OF REVISION	REV.	DATE	DESCRIPTION OF REVISION

DOE CONTRACT NO. DE-AC22-92PC92205

ROBERTS & SCHAEFER
DIVISION OF ECH NATIONAL INDUSTRIES, INC.
ENGINEERS AND CONTRACTORS
CHICAGO-SALT LAKE CITY-PITTSBURGH

INSTRUMENTATION & CONTROL PANEL WIRING		DESIGNED BY	W.J.K.	SCALE	NONE	DATE	2-2-83
VIRGINIA POLYTECHNIC INSTITUTE & STATE UNIVERSITY		DRAWN BY		CHECKED BY		APPROVED BY	
BENCH-SCALE TESTING OF MGS & MICROCEL UNITS		9234-E7					
AT PITTSBURGH ENERGY TECHNOLOGY CENTER							

THIS DRAWING IS THE PROPERTY OF ROBERTS & SCHAEFER AND SHALL NOT BE LOANED, REPRODUCED, COPIED, OR IN ANY MANNER DISSEMINATED WITHOUT THE WRITTEN PERMISSION OF ROBERTS & SCHAEFER.

MOTOR DATA

[illegible][illegible]

[illegible]

DOE CONTRACT NO. DE-AC22-92PC92205

ROBERTS & SCHAEFER
DIVISION OF ELGIN NATIONAL INDUSTRIES, INC. *Company*
ENGINEERS AND CONTRACTORS
CHICAGO-SALT LAKE CITY-PITTSBURGH

MOTOR DATA CHART		WAX	NONE	1-19-83
VIRGINIA POLYTECHNIC INSTITUTE & STATE UNIVERSITY		DESIGNED BY	APPROVED BY	9234-E0
BENCH-SCALE TESTING OF MGS & MICROCEL UNITS				
AT PITTSBURGH ENERGY TECHNOLOGY CENTER

SIDE PANEL

MCC

REV	DATE	DESCRIPTION OF REVISION	REV	DATE	DESCRIPTION OF REVISION

REL	DATE	DESCRIPTION OF REVISION	REL	DATE	DESCRIPTION OF REVISION

DOE CONTRACT NO. DE-AC22-92PC92205

ROBERTS & SCHAEFER
 DIVISION OF ELMER NATIONAL INDUSTRIES, INC.
 ENGINEERS AND CONTRACTORS
 CHICAGO-SALT LAKE CITY-PITTSBURGH

MCC SINGLE LINE
 VIRGINIA POLYTECHNIC INSTITUTE & STATE UNIVERSITY
 BENCH-SCALE TESTING OF MGS & MICROCEL UNITS
 AT PITTSBURGH ENERGY TECHNOLOGY CENTER

DESIGNED BY S. GRAMM	SCALE NONE	DATE 3/1/83
CHECKED BY MLK	APPROVED BY	9234-E3

THIS DRAWING IS THE PROPERTY OF ROBERTS & SCHAEFER AND SHALL NOT BE USED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF ROBERTS & SCHAEFER.

CON.

REV.	DATE	DESCRIPTION OF REVISION	REV.	DATE	DESCRIPTION OF REVISION

ED ON E6

CONT'D ON E6

ROBERTS & SCHAEFER
DIVISION OF ELMER NATIONAL INDUSTRIES, INC.
ENGINEERS AND CONTRACTORS
CHICAGO-SALT LAKE CITY-PITTSBURGH

MCC PANEL WIRING
VIRGINIA POLYTECHNIC INSTITUTE & STATE UNIVERSITY
BENCH-SCALE TESTING OF MGS & MICROCEL UNITS
AT PITTSBURGH ENERGY TECHNOLOGY CENTER

DESIGNED BY S. GRAHAM	DRAWN BY NONE	DATE 2-2-83
CHECKED BY WLK		
9234-E5		

CONT'D FROM E5

DATE	DESCRIPTION OF REVISION	DATE	DESCRIPTION OF REVISION

CONT'D FROM E5

LEGEND

⬡	- LOCATED IN MCC - TERMINAL IN MCC
⬢	- LOCATED IN CONTROL - PANEL
□	- TERMINAL IN CONTROL - PANEL
*	- LOCATED IN FIELD

DOE CONTRACT NO. DE-AC22-92PC92205

ROBERTS & SCHAEFER
DIVISION OF ELMON NATIONAL INDUSTRIES, INC.
ENGINEERS AND CONTRACTORS
CHICAGO-SALT LAKE CITY-PITTSBURGH

MCC PANEL WIRING
VIRGINIA POLYTECHNIC INSTITUTE & STATE UNIVERSITY
BENCH-SCALE TESTING OF MGS & MICROCELL UNITS
AT PITTSBURGH ENERGY TECHNOLOGY CENTER

DESIGNED BY S. GRAHAM	APPROVED BY NONE	DATE 2-2-93
DRAWN BY WUX	CHECKED BY	
9234-E6		◇

END

**DATE
FILMED
7/13/93**