DOE/PC/88885--T5

REVISED 7/24/90

DOE/PC/88885--T5

DE93 008032

PROOF OF CONCEPT AND PERFORMANCE
OPTIMIZATION OF HIGH GRAVITY BATCH
TYPE CENTRIFUGE FOR DEWATERING
FINE COAL

QUARTERLY TECHNICAL PROGRESS REPORT #3 (REVISED)

FOR THE PERIOD

MARCH 20, 1990 TO JUNE 20, 1990

BY

LLOYD B. SMITH
THOMAS E. DURNEY, JR.

July 24, 1990

WORK PERFORMED UNDER CONTRACT #DE-AC22-89PC88885

FOR

U.S. DEPARTMENT OF ENERGY
PITTSBURGH ENERGY TECHNOLOGY CENTER
P.O. BOX 10940
PITTSBURGH, PENNSYLVANIA 15236

BY

COAL TECHNOLOGY CORPORATION
103 THOMAS ROAD
BRISTOL, VIRGINIA 24201

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

JPZ

REVISED 7/24/90

EXECUTIVE SUMMARY

This report describes the work performed by Coal Technology Corporation (formerly UCC Research Corporation) from March 21, 1990 thru June 20, 1990 under DOE Contract #DE-AC22-89PC88885, "Proof of Concept and Performance Optimization of High-Gravity Batch Type Centrifuge for Dewatering Fine Coal." One objective of this project is to generate and record a data base with the prototype centrifuge. A further objective is to use the data base to determine the appropriateness of the system for coal processing and to determine how the more vital systems can be balanced so that the centrifuge can achieve optimum performance. This project began on September 20, 1989, and is scheduled to be completed on September 21, 1991. This is the third quarterly report.

The following is a summary of our accomplishments:

Task 1 The project work plan has been completed and approved. This completed Task 1.

Task 2 This task included the upgrading and testing of both the hardware and software of the data logging system. It also included improving and testing the data transducers as well as those support hardware systems which were preventing the logging of the primary data in real time. This task has been completed.

Task 3 The first sub-task in Task 3, consists of feasibility tests of the technology. In particular it is designed to demonstrate the ability of the non-blinding filter system to operate successfully over extended periods of time. The second sub-task in Task 3, demonstrates the ability of the system to dry a variety of coals from various coal fields to satisfactory moisture levels. Task 3 is on schedule.

Task 4 This task is designed to optimize the operation and the interactions of the six most important systems in the new centrifugal dryers. The work plan schedule called for this task to begin at the completion of Task 3. However, during the testing in Tasks 2 and 3, it became evident that it would be necessary to perform some of the Task 4 optimization ahead of schedule. The earlier test work had uncovered serious problems with some of the systems scheduled to be optimized during Task 4, and so it was deemed to be appropriate to move ahead and address the problems earlier to enhance the value of Tasks 2 and 3. Task 4 is ahead of schedule.

The project is on budget and on schedule.

JUL 27 1990

REVISED 7/24/90

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
INTRODUCTION	1
TASK 1: Project Planning	2
TASK 2: Modification of Data System	2
TASK 3: Proof of Concept Tests	4
TASK 4: Performance Optimization Tests.....	8

LIST OF FIGURES

FIGURE 1: Slurry Density vs. Productivity.....	7
FIGURE 2: Reconstituting System	9
FIGURE 3: Clay in Load.....	11
FIGURE 4: Wiper Scoop	12
FIGURE 5: Analysis of Coal Before/After Drying.....	13

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

REVISED 7/24/90

INTRODUCTION

Coal Technology Corporation (CTC) believes that the new CTC high gravity, high production, batch type centrifugal dryer technology can play a significant role in improving the product quality as well as costs of operation in coal processing plants. It is further believed that the new centrifugal dryer technology can form an important part in systems used to clean up the millions of tons of coal fines in refuse piles and ponds. It is anticipated that the new centrifuge can become an important ancillary to the advanced deep cleaning processes for coal. Because of these convictions, CTC has been engaged in a pioneering research effort into the new art of drying fine clean coal in high gravity, high production, batch type centrifuges, since 1981. This work has progressed to the point where the new centrifugal dryer technology is nearly ready for commercialization. It promises to provide needed fine coal drying capability at somewhat lower capital costs and at substantially lower operating costs than competitive systems. It also promises to do so with no detrimental effects on either the coal quality or the environment.

The primary objective of this project is to prove the concept in a commercial coal processing plant environment. The proof of concept tests will also include testing with a variety of coals from different regions. A further objective will be to optimize the efficiency and the cost effectiveness of the new centrifugal dryer technology.

REVISED 7/24/90

TASK 1: PROJECT PLANNING

Objective

The objective was to develop the Project Work Plan.

Discussions and Accomplishments

The Project Work Plan was completed and mailed on October 11, 1989. After answers were supplied to the questions raised by the Contracting Officer's Representative, on November 6, 1989, the Project Work Plan was accepted.

TASK 2: MODIFICATION OF DATA SYSTEMS

Objective

The objective of this task was to improve the systems for collecting, processing and recording the considerable data which define the quality of performance of the centrifugal dryer during testing. The work is broken down into:

- Modification of the data collection systems
- Modifications to the computer and controller
- Modifications to the software

Discussions and Accomplishments

These requirements under Task 2 have been accomplished:

- Increased capacity of dry coal scale.
- Prepared overflow weight system for weight recording.
- Prepared filtrate weight system for weight recording.
- Set up specific gravity system for logging.
- Installed signal processor for logging slurry pump speed/time sequence.
- Provided power consumption recording.
- Installed moisture measurement system.
- Completed all hard wiring and hardware changes.

REVISED 7/24/90

- Completed dry coal sampling point indicator.
- Installed and tested fill system modulation unit with linear potentiometer transducer.
- Installed and tested:
 - Texas Microsystems Industrial Logger Computer
 - Westinghouse Numalogic Programmable Controller
 - Modified "Genesis" Software
- Performed 75 cycle shakedown test of all systems. All systems are operational.
- Completed precision calibration of:
 - Dry coal weight system
 - Overflow weight system
 - Filtrate weight system
 - Bowl vibration monitor
 - Gimbal vibration monitor
- The Quadra-Beam 2 moisture meter has been installed, tested and given a first calibration. Final calibration will be done concurrently with Subtask 3.1.
- Completed tests comparing ASTM moisture tests with the microwave oven tests now in use with the centrifuge. These tests correlated to less than 0.1% difference.

These items not specified in the test plan, but considered vital to the project, have been accomplished:

- Measured vibration range of main bearing vibration instrument and had processor modified for velocity read out.
- Installed and tested new faster cutter screw system (supplied at no charge to DOE by Roberts & Schaefer).
- Installed new high natural frequency pads on main bearing system.
- Installed and successfully tested new ceramic cutter blade.

Task 2 has been completed.

REVISED 7/24/90

TASK 3: PROOF OF CONCEPT TESTS

Objectives of Subtask 3.1

The objectives of this subtask are to:

- Test the general feasibility of the centrifuge.
- Test the ability of the non-blinding filter to operate over long periods of time.

Discussion and Accomplishments

Successful operation of the subject centrifuge involves balancing a number of independent variables so that the final moistures, productivity levels and energy consumptions are acceptable. The principal variables involved in successful operation are:

INDEPENDENT VARIABLES IN CENTRIFUGAL CYCLE

- Slurry density
- Fill
 - Speed
 - Constant vs. changing speed
 - Fill rate, first
 - Fill rate, second
 - Fill time, first
 - Fill time, second
 - Nozzle size
 - Nozzle shape
- Delay (settling time after fill)
- Wipe
 - Time span
 - Attack rate
 - Pressure
- Acceleration time span
- Dwell at high speed
 - Speed (gravity level)
 - Constant speed vs. acceleration
- Deceleration time span
- Cut
 - Time span
 - Beginning speed of bowl
 - Constant speed vs. deceleration
 - Rate of attack

INDEPENDENT VARIABLES IN THE FILTER SYSTEM

- Depths of bed cake left from previous load
- Cross sectional area of restrictive orifices

REVISED 7/24/90

Since a factorial matrix involving 22 independent variables at 3 levels would be impractical, an Evolutionary Operational Testing format was followed for the first 500 cycles. During this period, an appropriately designed cycle was determined.

The last 500 cycles of Task 3.1 will follow a test matrix which will probably contain no more than 4 independent variables.

In quarterly report No. 2, it was reported that there were indications that higher filling speeds were beneficial. It was also reported that a speed limit of the order of 1,400 rpm appeared to be appropriate for the wiping function in which the clay bearing water, which forms on the inner surface of each new load of coal as it is being formed, is squeegeed away. These early findings were further reinforced by the work during the current reporting period.

During the reporting period, the fine coal received from the host plant, has had progressively more and more clays in it. This has necessitated the use of higher levels of flocculent in order to enable the plant to process the higher clay product. Both clays and flocculent are detrimental to the centrifugal drying process. CTC has considered it to be an advantage to be able to test this very difficult to dry coal. Testing under these conditions has meant that the centrifuge could be more highly perfected and this situation gave very strong indications that the following factors will improve the productivity and final moisture levels, especially when difficult coals are being processed:

- Feed slurry densities should be as thick as is practical.
- Filling speeds should be as high as is practical.
- The wiping system should be as efficient as possible in removing the clay bearing surface water from the newly formed load.
- The nozzle velocity should be high and the nozzles should cover the area of the inner surface of the load fully and evenly.

The feed slurry density is indicated to have correlated directly with the moisture and productivity. While the slurry density/moisture data obtained during the reporting period are not well defined, examination of these data along with observations of the testing, yielded strong indications that there is a correlation between slurry density and moisture. However, in the case of slurry density versus productivity, the testing has already shown a correlation of significance. The preliminary test results concerning this relationship are summarized on Figure 1, on page 7.

REVISED 7/24/90

The depth to which a dried load of coal is cut, interacts with the total cross sectional area of the metering orifices in the bowl in the non-blinding filter technology. It had been theorized at CTC, that shallower cuts might improve the moistures obtained with the higher clay, heavily flocced coal. This proved to be an erroneous theory. The data taken during the reporting period indicate that the 6.1 inch deep cutting depth, which has been used throughout the project, yielded better moistures with the high clay, heavily flocced coal than did 5.3 inch deep cuts which were recently tested. Because deeper cuts also enhance the very important productivity response, definitive testing of cut depth versus moisture and productivity, will be included in the matrices being formulated for the remaining testing in Tasks 3 and 4.

A recent inspection of the bowl showed that there is a slight erosion of the bowl due to the turbulent action of the slurry during the few seconds in which the new loads of coal solidify. This is, so far as has been determined to date, the only wear occurring in the bowl. The effect is minimal and it was corrected by simply reglazing the bowl with epoxy. A study of the problem has revealed that the application of a ceramic armor with a ceramic base and an epoxy matrix, will be a simple and total solution to the problem for the production centrifuges. Because of the minor nature of the erosion after nearly two years of testing, the epoxy glaze is considered to be sufficient for the present.

Objective of Subtask 3.2

The objective of Subtask 3.2 is to confirm the ability of the new dryer system to dry an adequate variety of coals from various coal fields efficiently.

Discussion and Accomplishments

A system has been constructed and tested for receiving, reconstituting and transporting to the centrifuge holding tank, samples of clean coal filter cake from Pennsylvania, West Virginia, Southern Illinois and Alabama as called for in the Work Plan. The system is complete with drum handling, air and mechanical mixing devices, and a pump-over system for moving the reconstituted slurry to the centrifuge for testing. The system has been given preliminary tests and it is operational. It is illustrated on Figure 2, on page 9.

Samples are scheduled to be received at the host plant from Pennsylvania and Alabama in late July. Samples from West Virginia and Southern Illinois will be received in August. In each case the testing will be completed shortly after receipt of the samples. While the subject centrifuge was designed for drying typical froth flotation product containing 28 mesh x 0 coal with

SLURRY DENSITY VS PRODUCTIVITY

FIGURE 1

REVISED 7/24/90

35% minus 325 mesh, it was decided that test results of Subtask 3.2 would be the more valuable if both courser and finer samples could be included in the various samples to be tested. With this in view and after discussions with prospective sample suppliers, it was decided that the samples would include the following:

- From Alabama, a coarse sample will be tested. This sample will contain 8 mesh x 0 coal with 20% maximum at minus 325 mesh size.

- From Pennsylvania, a very fine sample will be received. This sample will have 100 mesh x 0 coal with 50% minus 325 mesh size.

Task 4: Performance Optimization Tests

Objective of Subtask 4.3

This subtask is aimed at optimizing the filling system hardware and the manner in which it is used to fill the bowl to form the successive loads of coal.

Summary and Accomplishments

Since the turbulence created when the feed nozzles introduce the coal slurry to the bowl is important to the filling process, the number and diameter of the feed nozzles are being tested for productivity and moisture responses. It was found during the testing that the existing slurry feed pump cannot maintain sufficient pressure head with more than 15.3 sq in of nozzle area (11 nozzles of 1 1/4 pipe size). When a larger total cross sectional area was used the pressure head at the nozzles fell off substantially. This resulted in less turbulence during the fill and there were indications that this caused more clays to progress down through the load to potentially blind the filter.

When 1 inch pipe nozzles were tested, it was found that the pressure head remained about the same as with the 1 1/4 nozzles. The result was slower filling and less turbulence, also a very detrimental condition. It was concluded that for now and until a change is made in the feed pump, a full complement of 1 1/4 inch feed nozzles gives the most satisfactory result.

Because of the higher clay content in the product now being received from the host plant, it was decided to address the need to more quickly and effectively remove the clay laden water which collects on the surface of the newly formed loads of coal. Figure 3 on page 11, illustrates a 45 mil thick layer of almost pure clay which was formed when a freshly formed load of coal was interrupted before the wiper removed any of the clay. When the clay bearing water is quickly removed prior to the wiping process, most of the illustrated clay is removed.

MIXER/PUMP SYSTEM OF A BENTONITE PASTE
FOR THE REMEDIATION OF A SITE

MIXING CHAMBER OF MIXER/PUMP SYSTEM

REVISED 7/24/90

To remove this clay laden water, a device designated a "wiper scoop" was designed and built. This device is illustrated on Figure 4 on page 12. When the wiper is lowered onto the freshly formed load of coal, the scoop, using the 70 mph velocity of the water, quickly removes most of the water along with the clay suspended in it from the surface of the newly formed load.

An unexpected benefit of this development has been to greatly enhance the cutting operation. The benefits of the wiper scoop are especially important when high clay product is being dried. High clay product which had been impossible to cut out in earlier tests, is now being cut out in as low as 22 seconds. Lab tests of the before drying sample and of the dried product, show that the ash is lowered and the BTU/lb (dry basis) is increased significantly by the drying process. The amounts of improvement are shown on Figure 5 on page 13.

Objective of Subtask 4.6

The objective of this subtask is to improve the performance of the cutting hardware and process to the point where it is able to perform at practical production rates.

Discussion and Accomplishments

Three developments have improved the cutting hardware to the point where it is performing at or near production readiness. They are:

- CERAMIC CUTTER BLADE This blade consisting of six segments of ceramic about six inches long each, is bolted and cemented to a steel backing. It wears quite well and it is very inexpensive.

- CERAMIC LINER AND SCREW COATING The material consists of a ceramic powder in an epoxy matrix which is painted onto the steel so as to form a wear resistant non-stick surface. The result has been a complete solution to the long standing problems of sticking of the dried coal to the housing and screw and the resulting partial stalling of the screw.

- WIPER SCOOP As described above the removal of much of the clay which had previously formed on the surface of the newly formed loads of coal, has greatly improved the cutting out rates.

1945-6: 40,000; 1946: 40,000; 1947: 40,000;
 1948: 40,000; 1949: 40,000; 1950: 40,000

1-800-762-6842

FIGURE 3
11

FIGURE 4
12

COMMERCIAL TESTING & ENGINEERING CO.
 GENERAL OFFICES: 1910 SOUTH HIGHLAND AVE., SUITE 210-B, LOMBARD, ILLINOIS 60148 • (708) 953-0388

May 2, 1990

COAL TECHNOLOGY CORPORATION
 103 Thomas Road
 Bristol VA 24201

Sample Identification by
 Coal Technology

SAMPLE ID

Kind of sample
 reported to us Coal

Sample taken at XXXXX

Sample taken by XXXXX

Date sampled _____

Date received April 16, 1990 (picked up sample)

Peteroom
 Filter Cake
 4/16/90
 1651 - NF

COMMERCIAL TESTING & ENGINEERING CO.
 GENERAL OFFICES: 1910 SOUTH HIGHLAND AVE., SUITE 210-B, LOMBARD, ILLINOIS 60148 • (708) 953-0388

May 2, 1990

COAL TECHNOLOGY CORPORATION
 103 Thomas Road
 Bristol VA 24201

Sample Identification by
 Coal Technology

SAMPLE ID

Kind of sample
 reported to us Coal

Sample taken at XXXXX

Sample taken by XXXXX

Date sampled _____

Date received April 16, 1990 (picked up sample)

Peteroom
 Filter Cake
 4/16/90
 1651 - NF

Analysis Report No. 68-65136

SIEVE ANALYSIS

Fraction	Retained On	Wt. Weight	CUMULATIVE PERCENT	
			% Retained	% Passing
100 Mesh	100 Mesh	38.6	38.6	100.0
200 Mesh	200 Mesh	16.5	55.1	61.4
300 Mesh	325 Mesh	10.0	65.1	44.9
325 Mesh	0	34.9	100.0	34.9

Analysis Report No. 68-65136

SHORT PROXIMATE ANALYSIS

As Received	dry Basis	
% Moisture	21.38	XXXXX
% Ash	9.09	11.54
Btu/lb	10766	13494
% Sulfur	0.69	0.88

MAP 15484

% EQUILIBRIUM MOISTURE = 1.0

ANALYSIS OF SAMPLE FROM HOST PLANT

Rachay Campbell
 Rachay Campbell
 Manager, Physical Laboratory

Rachay Campbell
 Rachay Campbell
 Manager, Physical Laboratory

COMMERCIAL TESTING & ENGINEERING CO.
 GENERAL OFFICES: 1910 SOUTH HIGHLAND AVE., SUITE 210-B, LOMBARD, ILLINOIS 60148 • (708) 953-0388

May 2, 1990

COAL TECHNOLOGY CORPORATION
 103 Thomas Road
 Bristol VA 24201

Sample Identification by
 Coal Technology

SAMPLE ID

Kind of sample
 reported to us Coal

Sample taken at XXXXX

Sample taken by XXXXX

Date sampled _____

Date received April 16, 1990 (picked up sample)

Clean Coal
 Filter Cake
 4/16/90
 1651-MC

COMMERCIAL TESTING & ENGINEERING CO.
 GENERAL OFFICES: 1910 SOUTH HIGHLAND AVE., SUITE 210-B, LOMBARD, ILLINOIS 60148 • (708) 953-0388

May 2, 1990

COAL TECHNOLOGY CORPORATION
 103 Thomas Road
 Bristol VA 24201

Sample Identification by
 Coal Technology

SAMPLE ID

Kind of sample
 reported to us Coal

Sample taken at XXXXX

Sample taken by XXXXX

Date sampled _____

Date received April 16, 1990 (picked up sample)

Clean Coal
 Filter Cake
 4/16/90
 1651-MC

Analysis Report No. 68-65136

SIEVE ANALYSIS

Fraction	Retained On	Wt. Weight	CUMULATIVE PERCENT	
			% Retained	% Passing
100 Mesh	100 Mesh	49.9	49.9	100.0
200 Mesh	200 Mesh	16.5	66.4	50.1
300 Mesh	325 Mesh	9.7	76.2	33.8
325 Mesh	0	23.8	100.0	23.8

Analysis Report No. 68-65136

SHORT PROXIMATE ANALYSIS

As Received	dry Basis	
% Moisture	14.97	XXXXX
% Ash	7.75	9.11
Btu/lb	12059	14182
% Sulfur	0.83	0.97

MAP 15483

ANALYSIS OF COAL AFTER DRYING

Rachay Campbell
 Rachay Campbell
 Manager, Physical Laboratory

Rachay Campbell
 Rachay Campbell
 Manager, Physical Laboratory

REVISED 7/24/90

Tasks 3 and 4 are expected to be completed on schedule.

No work has been done on Task 5.

Respectfully submitted,

A handwritten signature in cursive script, appearing to read "Lloyd B. Smith".

Lloyd B. Smith
Vice President, Development

LBS/af

Enclosures

cc: Ted Durney
Dick Wolfe

END

DATE
FILMED
3/19/93