DRAFT

DOE/PC/79654--T10

DE93 011505

TECHNICAL PROGRESS REPORT

OCTOBER - DECEMBER 1989

For:

**U.S. Department of Energy
Pittsburgh Energy Technology Center**

Under:

**DOE Contract No. DE-AC22-87PC79654
Development of a Retrofit Coal Combustor for
Industrial Applications (Phase II)**

By:

**MANUFACTURING AND TECHNOLOGY CONVERSION
INTERNATIONAL, INC.**

P.O. Box 21, Columbia, Maryland 21045-0021

January 1990

DRAFT

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

PREFACE

A detailed description of the background, technology and application for the development of a retrofit coal combustor for industrial applications was provided in the first quarterly report for the period January 1987 - March 1987. In June of 1988, DOE Contract No. DE-AC22-87PC79654 was modified with the addition of a new task, as a Phase IA, to bridge the gap between Phase I and II of the program. That material is omitted from this report. Phase II was initiated on April 3, 1989. This report covers the period October 2, 1989 through December 24, 1989.

The results of over 200 hours of shakedown testing on the 7.5 MMBtu/hr unit indicated that the performance specifications for the full-size tandem unit can be achieved. A new refractory and refractory installation design was selected to resolve the issue of extending its (refractory) structural integrity under the acoustic conditions in the combustor. In the 15 MMBtu/hr unit, heating up and cooling down will be well controlled to eliminate any thermal stresses arising from operations. Combined with the new refractory material, performance lifetimes and reliability are anticipated to approach, if not meet commercialization requirements.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

TABLE OF CONTENTS

	<u>Page</u>
1.0 PROGRAM DESCRIPTION AND WORK STATUS	1
1.1 PROGRAM DESCRIPTION	1
1.2 TASK DESCRIPTIONS - PHASE II, PILOT-SCALE COMBUSTOR DEVELOPMENT	3
1.2.1 Task 1: Fabrication of the Pilot-Scale Combustor	3
1.2.2 Task 2: Technical and Laboratory- Scale Support	5
1.2.3 Task 3: Design of a Retrofit Combustor System for Field Demonstration	5
1.3 SUMMARY STATUS	6
2.0 TECHNICAL DISCUSSION OF WORK COMPLETED DURING THE REPORTING PERIOD	7
2.1 FABRICATION OF PILOT-SCALE COMBUSTOR	
2.1.1 Subtask 1.2: Testing and Engineering Evaluation	7
3.0 PLANNED ACTIVITY FOR THE NEXT PERIOD	17

LIST OF FIGURES

	<u>Page</u>
FIGURE 1 PROGRAM LOGIC FOR THE DEVELOPMENT OF AN ADVANCED PULSED-COAL COMBUSTOR FOR RETROFIT APPLICATIONS	2
FIGURE 2 POST-TEST PHOTOGRAPH OF THE PULSE COMBUSTOR CHAMBER WITH CRACKS IN REFRACTORY	8
FIGURE 3 CONFIGURATION FOR SYSTEM DESIGN	13
FIGURE 4 REFRACTORY-LINED SECTION WITH AIR-COOLED ANNULUS	15

LIST OF TABLES

TABLE 1 PHYSICAL AND CHEMICAL PROPERTIES FOR ULTRA-GREEN 90 . . .	9
--	---

SECTION 1.0

PROGRAM DESCRIPTION AND WORK STATUS

1.1 PROGRAM DESCRIPTION

The objective of Phase I of the program for the development of a retrofit pulse coal combustor for industrial applications was to design, fabricate, test and evaluate advanced chamber designs at the laboratory-scale utilizing several fuels (Task 1). The activities were structured to provide design criteria for scaling up to the pilot-scale level for the demonstration of a pulse combustor fired with coal-water mixtures for industrial boiler and process heater retrofit applications. The program logic is depicted in Figure 1.

The design data and information acquired during Task 1 of the initial phase was to develop scale-up design criteria for scaling the laboratory-scale design to pilot-scale including interface requirements for the field demonstration. The scale-up pilot unit design was to be sufficiently developed to allow fabrication of the unit for testing in the existing test facility upon DOE exercising its option for the follow-on activities of this program. These follow-on activities (Phase II) included the fabrication, test, and engineering evaluation of the pilot-scale combustor as well as technical and laboratory test support activities for reducing the technical risks and costs of development at the pilot-scale. Based on the information, test, data and technical support activities, a retrofit combustor system was to be designed for field demonstration as shown on the left in Figure 1.

An additional effort - Phase IA - was added to the contract by modification A005. This modification added a Phase IA in place of the original Task 2 of Phase I activity. This interim phase consisted of three technical tasks that were described in previous quarterly reports. Phase II was initiated in April 1989. The task structure for the Phase II Statement of Work is now provided in Section 1.2. An additional task (Task 4) entitled "Management and Reporting" is not included in the following discussion.

FIGURE 1: PROGRAM LOGIC FOR DEVELOPMENT OF A PULSE COAL COMBUSTOR FOR RETROFIT APPLICATIONS

1.2 TASK DESCRIPTIONS - PHASE II, PILOT-SCALE COMBUSTOR DEVELOPMENT

1.2.1 TASK 1: FABRICATION OF THE PILOT-SCALE COMBUSTOR

The Contractor shall undertake a pilot-scale development and test activity which is aimed at the pilot-scale demonstration of a pulse coal combustor fired with dry, pulverized coal for industrial boiler and process heater retrofit applications. In conducting the pilot-scale demonstration, the Contractor shall undertake the following two subtasks:

SUBTASK 1.1: PILOT-SCALE COMBUSTOR FABRICATION

The scaled-up design, developed under Phase I, shall be fabricated and integrated to a boiler test facility and prepared for conducting the testing and engineering evaluations described below under Subtask 1.2.

In fabricating the scale-up combustor and integrating it in the test facility, the Contractor shall procure all the necessary materials, equipment, instrumentation and supplies and shall provide for all facility modifications for fuel and air supplies and sound-muffling provisions.

SUBTASK 1.2: TESTING AND ENGINEERING EVALUATION

The Contractor shall initially conduct tests of the pilot-scale pulse combustor with natural gas. This shall be followed by tests which employ dry, pulverized coal.

In implementing this task, the Contractor shall prepare a test plan (for each test fuel) detailing the combustor design, facility modifications and the planned sequence, procedures and test data acquisition for conducting the test activities. The test plan shall be supplied to the DOE Technical Program Monitor for review and approval.

Test activities shall include shakedown runs to establish stable performance and overall facility readiness. Mass and energy balance

calculations shall also be undertaken by the Contractor to develop procedures and methods suitable for reliable determination of the combustion efficiency.

During each test run, the Contractor shall periodically record the following measurements:

- Fuel mass flow rate and combustor pressure wave intensity,
- Primary and secondary air flow rates (time average) and temperatures,
- Unburned carbon loss, and
- Flue gas analysis (O_2 , CO_2 , CO, SO_x , NO_x , etc.).

In addition, the following test data will be taken on an as-required basis:

- Flue gas analysis of the pulsating combustor's exit gas stream using analytical equipment to determine the level of unburned hydrocarbons, if any,
- Primary and secondary air flow rate vs. time,
- Pressure measurements (locations determined during testing),
- Chemical and size analyses of fuel feedstock, slag and fly ash, and
- Heat absorbed by the furnace, flue gas flow rate, and furnace exit temperature.

The Contractor shall reduce the test data and analyze and correlate the reduced data as a function of the combustor load. The pilot-scale data shall be compared with the integrated small industrial-scale pulse combustor data (Phase IA) to assess the effect of scale-up on the combustor performance.

The Contractor shall also employ the test results to undertake an assessment of the commercial retrofit applications to industrial boilers and process heaters. In addition, the Contractor shall document all the operating experience including maintenance-related experiences and shall employ such information in the assessment of the commercial application of the combustor technology.

1.2.2 TASK 2: TECHNICAL AND LABORATORY-SCALE SUPPORT

In support of the pilot-scale development and demonstration, defined in 1.4.1 above, the Contractor shall undertake technical evaluation and laboratory test activities to reduce the technical risks and associated costs of the combustor development at the pilot-scale.

This shall include engineering analysis of modifications contemplated for the pilot-scale system and laboratory-scale testing of such modifications or subsystems prior to incorporating them at the pilot-scale.

In supporting the pilot-scale combustor development, the Contractor shall employ and enhance the empirical computer code for combustor performance and scale-up analysis developed in Phase I and shall employ supplemental laboratory-scale tests to address technical issues resulting from the pilot-scale development work.

1.2.3 TASK 3: DESIGN OF A RETROFIT COMBUSTOR SYSTEM FOR FIELD DEMONSTRATION

Based on the results of both Tasks 1 and 2 defined above, the Contractor shall formulate Prototype Systems Designs for two firing rates having a commercially viable opportunity in the small industrial boiler retrofit market. These systems will have firing rates of 15 MMBtu/hr and 25 MMBtu/hr, with the primary fuel being dry coal and the secondary fuel being natural gas.

The designs shall be in accordance with all the applicable codes and according to the standard design practice employed in the design of boilers and fired heaters.

The design performance goal of the retrofit combustor shall be equal to or exceed the performance requirements articulated in PRDA RA22-86PC90259, issued by DOE/PETC, for the industrial boiler and process heater retrofit applications. The retrofit combustor system shall include fuel storage facilities, fuel feed subsystems, the retrofit combustor, ash removal subsystem, other particulate emission control devices, if any, and instrumentation suitable for field demonstration of performance and controls.

The Contractor shall prepare and deliver to DOE all drawings and specifications required for procurement, fabrication and field installation of the retrofit combustor systems.

The Contractor shall clearly designate drawings and related specifications proprietary as deemed appropriate, should the Contractor need to secure proprietary information protection for the material, under the applicable procurement regulation and contract provisions.

1.3 SUMMARY STATUS

The test facility was re-located from Santa Fe Springs, California to Baltimore, Maryland. The pulse combustor unit was moved to the new facility and assembly of the 15 MMBtu/hr unit initiated. A 300-HP York-Shipley fire-tube boiler with a 300-gallon water tank, controls and pumps has also been delivered to the Baltimore facility.

An analysis of the data toward the end of the shakedown testing indicated that lower peak-to-peak pressure fluctuations than in the earlier tests under similar firing rate and conditions. The unit was dismantled to check the integrity of the refractory inside the combustion chamber and inspection revealed several cracks inside its chamber. The cracks had developed both radially and longitudinally.

At this point, a search was initiated to select a refractory material to solve this problem. After consulting with several refractory specialists, an ultra-low cement castable (Ultra-Green 90) was chosen with the properties anticipated to maintain integrity over long periods of time.

Notwithstanding the refractory damage to the 7.5 MMBtu/hr unit, the excellent performance of the 7.5 MMBtu/hr unit in gas-fired mode (high combustion efficiency, low emissions, and robust pulsations) and the excellent performance of the 750 KBtu/hr subscale unit on both gas and coal have provided sufficient confidence to proceed to the design and fabrication of the 1.5 MMBtu/hr tandem unit.

SECTION 2.0
TECHNICAL DISCUSSION OF WORK COMPLETED
DURING THE REPORTING PERIOD

**2.1 TASK 1: FABRICATION OF
PILOT-SCALE COMBUSTOR**

**2.1.1 SUBTASK 1.2: TESTING AND
ENGINEERING EVALUATION**

A summary of the shakedown tests performed on the pulse combustor unit with natural gas as the main fuel to the pulse combustor was provided in the last quarterly progress report.

An analysis of the data indicated that during Test Numbers 9-12 through 9-18, a lower peak-to-peak pressure fluctuation was observed than in the earlier tests with similar firing rate and conditions. Therefore, the unit was dismantled to check the integrity of the refractory inside the combustion chamber. An inspection revealed several cracks inside the pulse combustion chamber. The cracks had developed both radially and longitudinally. The chamber exit throat had lost its circular shape, due to crack development and also to displacement of the refractory. Figure 2 shows a picture of the pulse combustion chamber after the cracks had developed.

At this point, a search was initiated to select a refractory material with the following properties: 1) high thermal shock resistance, due to very sharp temperature gradient across the refractory section, during the start-up of the pulse combustor unit, 2) high surface temperature, since the instantaneous chamber temperature can reach up to 3200°F, 3) slag penetration resistance, since this unit will operate in slagging mode. After consulting with several refractory specialists, an ultra-low cement castable was chosen. Table 1 gives the chemical and physical properties for the Ultra-Green 90.

**FIGURE 2: POST-TEST PHOTOGRAPH OF THE PULSE COMBUSTOR
CHAMBER WITH CRACKS IN REFRACTORY**

TABLE 1: PHYSICAL AND CHEMICAL PROPERTIES FOR ULTRA-GREEN 90

TECHNICAL DATA - GREEN 9C86 (ULTRA GREEN 90)

Ultra-Low Cement Vibrating Castable		
MAXIMUM RECOMMENDED TEMPERATURE -----	3400°F	1870°C
QUANTITY REQUIRED -----	182 lb/ft ³	2.92 g/cc
QUANTITY IN PLACE	lb/ft ³	g/cc
Cured and Then Dried at 220°F (105°C) -----	180-184	2.89-2.95
Heated at 1500°F (815°C) -----	180-184	2.89-2.95
APPARENT POROSITY - ASTM C20		Approximately
Cured and Then Dried at 220°F (105°C) -----		11-16%
Heated at 1500°F (815°C) and Then Cooled -----		12-17%
WATER REQUIRED FOR MIXING		Approximately
Per 100 POUNDS -----	3 1/2-4 1/2 pints (US)	1.7-2.1 liters
MAXIMUM TIME FROM ADDING WATER TO PLACING MATERIAL		
MINUTES -----		20
PERMANENT LINEAR CHANGE - ASTM C113 AND C865		
Expansion or Shrinkage		Nil
Cured and Then Dried at 220°F (105°C) -----		
Heated at 1500°F (815°C) and Then Cooled -----		0 to 0.6% shr
Heated at 2000°F (1095°C) and Then Cooled -----		0 to 0.6% shr
Heated at 2500°F (1370°C) and Then Cooled -----		0 to 0.6% shr
Heated at 2900°F (1595°C) and Then Cooled -----		0 to 0.8% exp
Heated at 3200°F (1760°C) and Then Cooled -----		0.5% to 1.5% exp
MODULUS OF RUPTURE - ASTM C133 AND C865	lb/in ²	MPa
Cured and Then Dried at 220°F (105°C) -----	1200	8.3
Heated at 1500°F (815°C) and Then Cooled -----	2200	15.3
Heated at 2000°F (1095°C) and Then Cooled -----	1800	12.5
Heated at 2500°F (1370°C) and Then Cooled -----	1500	10.4
HOT MODULUS OF RUPTURE - ASTM C503 AND C865		
Heated at 1500°F (815°C) -----	3500	24.3
Heated at 2500°F (1370°C) -----	2000	13.9
Heated at 2700°F (1480°C) -----	700	4.9
Heated at 2900°F (1595°C) -----	250	1.7

TABLE 1: PHYSICAL AND CHEMICAL PROPERTIES FOR ULTRA-GREEN 90
(CONTINUED)

GREEN 9C86

COLD CRUSHING STRENGTH - ASTM C133 AND C965		lb/in ²	MPa
Dried and Then Dried at 220°F (105°C) -----		8000	55.5
Heated at 1800°F (915°C) and Then Cooled -----		10000	69.4
Heated at 2000°F (1095°C) and Then Cooled -----		12000	83.3
Heated at 2500°F (1370°C) and Then Cooled -----		15000	104.1
ABRASION LOSS - ASTM C704			cc
Heat at 1800°F (915°C) and Then Cooled -----			3.5-5.5
Heat at 2500°F (1370°C) and Then Cooled -----			3.5-6.5
PARTICLE SIZE - ASTM C92			
Retained on 6 Mesh Tyler Screen (3.33 mm opening)			
Wet Analysis -----			Less Than 3%
THERMAL CONDUCTIVITY		Btu-in ft ² hr ² F	W/m°C
At a Mean Temperature of			
400°F (205°C) -----		14.84	2.14
800°F (425°C) -----		14.87	2.14
1200°F (650°C) -----		15.06	2.17
1600°F (870°C) -----		15.42	2.22
2000°F (1095°C) -----		15.94	2.30
2400°F (1315°C) -----		16.64	2.40
CHEMICAL ANALYSIS			
Calcined Basis			
Silica - SiO ₂ -----			12.0 - 14.0%
Alumina - Al ₂ O ₃ -----			84.0 - 88.0%
Iron Oxide - Fe ₂ O ₃ -----			Trace - 0.3%
Lime - CaO -----			0.3 - 0.6%
Titanium - TiO ₂ -----			Trace - 0.1%
Alkalies - Na ₂ O + K ₂ O -----			0.1 - 0.3%

The test data shown above are based on average results of control tests and are subject to normal variation on individual tests. These results cannot be taken as maximum or minimum requirements for specification purposes.

During this reporting period, the test facility was re-located from Santa Fe Springs, California to Baltimore, Maryland. The pulse combustor unit was moved to the new facility and work is underway to assemble the 15 MMBtu/hr unit. A 300-HP York-Shipley fire-tube boiler with a 300-gallon water tank, controls and pumps has been purchased and moved from St. Louis, Missouri to the Baltimore facility.

A summary of the results of the shakedown testing on the 7.5 MMBtu/hr unit indicating the performance achievements for the various tests in the series are as follows:

- Scale-up completed for gas-firing
- Firing rate of up to 9 MMBtu/hr in a single combustor
- Combustion efficiency of 99+%
- CO emissions of less than 300 ppm without decoupling chamber and without air staging
- NO_x emissions in the 25 - 50 ppm range without air staging
- Typical turndown of 5 to 1.
- Combustion chamber peak-to-peak in the 10 - 15 psi range
- Boost pressure of up to 15 inches of water
- Unit tunes in self-aspirating mode
- Over 200 hours of operation.

Although all of the above were not achieved in a single test, the results of the test series indicated the potential of the combustor to achieve the performance goals anticipated.

Notwithstanding the refractory damage to the 7.5 MMBtu/hr unit, budget constraints indicated that the excellent performance of the 7.5 MMBtu/hr unit in gas-fired mode (high combustion efficiency, low emissions, and robust pulsations) and the excellent performance of the 750 KBtu/hr subscale unit on both gas and coal had been demonstrated to a sufficient level to permit proceeding to the design and fabrication of the 1.5 MMBtu/hr tandem unit.

The configuration used for system design is shown in Figure 3. The system includes several components such as air plenum, aerovalve, pulse combustion chamber, tailpipe, and decoupler. The computer code that has been developed for scale-up performs mass balance, combustion, heat balance, fluid dynamics, heat transfer, materials selection and mechanical design calculations. The input data to the program includes the desired firing rate and the fuel specifications. The program generates the dimensions for the components which in turn facilitates the development of component drawings using AUTOCAD.

The design alternatives considered for the different components include:

- Combustion chamber - water-cooled or refractory-lined.
- Tailpipe - water-cooled or refractory-lined.
- Decoupler - air-cooled or water-cooled.
- Steam circuit - independent or coupled for the boiler and the water-cooled components.

Based on the program calculations, estimated temperature profiles, fabrication considerations, and the objective to operate in the slagging mode, the following choices were made:

- Combustion chamber - refractory-lined. The 7.5 MMBtu/hr single combustor size presents a surface area to volume ratio that is still not small enough to favor direct water-cooling. One layer of refractory lining is required for water-cooling and this poses a problem for fabrication due to the complicated chamber geometry. Therefore, it was decided to retain the two-layer refractory-lined configuration for the chamber.
- Tailpipe - water-cooled. Direct water cooling is preferred due to additional combustion in the tailpipe, the need to lose heat to avoid excessive flue gas temperature, and the formation of a slag layer that impedes excessive heat transfer to the water.

FIGURE 3: CONFIGURATION FOR SYSTEM DESIGN

- Decoupler - water-cooled. Two geometries were investigated for preheating air. One was a refractory-lined section with an air-cooled annulus as shown in Figure 4 and another was a refractory-lined section with staggered, tubular passages in the refractory for flow of air. Thermal network analysis accounting for conduction, convection, and radiation (the nonlinear equations were solved by the Newton-Rhapson technique) indicated that the air required for combustion can be preheated to a temperature of about 450°F. However, due to considerations of mechanical integrity, high refractory requirement and cost, and anticipated fabrication difficulties (refractory anchoring), the air-cooled design was dropped. The computer code indicated that the decoupler should include one layer of high-density refractory and then the water jacket to maintain a molten slag layer on the inside.

- Steam circuit - partial coupling. Since it was decided to water-cool the tailpipe and decoupler, there was a need to determine the water circulation route. The initial inclination was to keep the boiler water circuit separate from the tailpipe and decoupler water circuit. This, however, necessitated a large steam drum and extensive plumbing for the tailpipe and decoupler water circuit. Based on further evaluation, it was considered more advantageous to connect the decoupler water jacket to the boiler and keep the tailpipe water circuit separate. The decoupler elevation is lower than that of the boiler and therefore it is possible to provide the hook-up of the decoupler water jacket to the boiler and maintain natural circulation. The tailpipe is, however, at a higher elevation than that of the boiler and warrants a separate water circuit with a small steam drum. The tailpipe water jacket will be connected to the steam drum via a downcomer and a steam riser. A sketch of the steam circuit will be included in the next monthly report. This arrangement of the steam circuit actually enables the boiler to generate steam beyond rated capacity and does not derate the boiler for coal-firing as is the norm.

**FIGURE 4: REFRACTORY-LINED SECTION
 WITH AIR-COOLED ANNULUS**

The boiler (York-Shipley Series 576 SPH 300N - 12,500 PPH steam @ 220 psig equipped with gas burner) has been received at the Baltimore laboratory. An inspection revealed missing and damaged parts (gaskets, seals, etc.) and subsystems. Parts have been procured and rehabilitation has been carried out. This included extensive work on the blowdown subsystem. The boiler water circuit is being changed from a recycle arrangement to a once-through arrangement. Plumbing for water and gas and electrical hookup are in progress.

SECTION 3.0

PLANNED ACTIVITY FOR THE NEXT PERIOD

- Complete system design
- Complete boiler installation

END

**DATE
FILMED**

5 / 11 / 93