Occupational and Environmental Protection Section

LOCATIONS OF CRITICALITY ALARMS AND
NUCLEAR ACCIDENT DOSIMETERS AT HANFORD

August 1992

Prepared for
the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830

Pacific Northwest Laboratory
Richland, Washington 99352

MASTER

CONTENTS

	<u>Page No.</u>	<u>Issue Date</u>
1.0 INTRODUCTION	1	8/92
1.1 MANUAL CONTENTS	1	8/92
1.2 FLOOR PLAN SYMBOLS	1	8/92
2.0 NAD DEFINITION, DESCRIPTION, AND EXCHANGE	1	8/92
3.0 CRITERIA AND INSTRUCTIONS FOR NAD PLACEMENT	1	8/92
3.1 GENERAL PLACEMENT CONSIDERATIONS	1	8/92
3.2 PLACEMENT CRITERIA	1	8/92
3.3 PLACEMENT INSTRUCTIONS	2	8/92
REFERENCE	1	8/92
APPENDIX A - MASTER LIST OF NAD LOCATIONS	1	8/92
APPENDIX B - 100 AREA CRITICALITY ALARM AND NAD LOCATIONS	1	8/92
105-KE BUILDING	2	8/92
105-KW BUILDING	3	8/92
105-N REACTOR PLANT	4	8/92
APPENDIX C - 200-EAST AREA CRITICALITY ALARM AND NAD LOCATIONS	1	8/92
202-A BUILDING	2	8/92
APPENDIX D - 200-WEST AREA CRITICALITY ALARM AND NAD LOCATIONS	1	8/92
234-5 FACILITIES	2	8/92
2736-Z AND 2736-ZB BUILDINGS	9	8/92

	<u>Page No.</u>	<u>Issue Date</u>
APPENDIX E - 300 AREA NAD LOCATIONS	1	8/92
303 BUILDINGS	2	8/92
304 BUILDING	6	8/92
306 BUILDING	7	8/92
308 BUILDING	9	8/92
313 BUILDING	13	8/92
324 BUILDING	14	8/92
325 BUILDING	20	8/92
327 BUILDING	24	8/92
328 BUILDING	27	8/92
329 BUILDING	29	8/92
333 BUILDING	30	8/92
3712 BUILDING	32	8/92
3716 BUILDING	33	8/92
3720 BUILDING	34	8/92
3730 BUILDING	36	8/92
APPENDIX F - 400 AREA NAD LOCATIONS	1	8/92
FFTF FACILITIES	2	8/92

FIGURES

	<u>Page No.</u>	<u>Issue Date</u>
2.1 Nuclear Accident Dosimeter	2	8/92
B.1 Floor Plan of the Ground Floor of the 105-KE Building Showing Criticality Alarm and NAD Locations	2	8/92
B.2 Floor Plan of the Ground Floor of the 105-KW Building Showing Criticality Alarm and NAD Locations	3	8/92
B.3 Floor Plans of the 105-N Reactor Plant Ground Floor and Sub-Basement Showing Criticality Alarm and NAD Locations	5	8/92
C.1 Floor Plan of the 202-A Building Crane Lab Gallery Showing NAD Locations	4	8/92
C.2 Floor Plan of the 202-A Building Pipe and Operating Gallery Showing Criticality Alarm and NAD Locations	5	8/92
C.3. Floor Plan of the 202-A Building Sample Gallery Level Showing Criticality Alarm and NAD Locations	6	8/92
C.4 Floor Plan of the 202-A Building Storage Gallery Showing Criticality Alarm and NAD Locations	7	8/92
D.1 Floor Plan of the 234-5 Building First Floor Showing Criticality Alarm and NAD Locations	6	8/92
D.2 Floor Plans of the 234-5 Building Second Floor and Duct Level Showing Criticality Alarm and NAD Locations	7	8/92
D.3 Floor Plan of the 236-Z Building Showing Criticality Alarm and NAD Locations	8	8/92
D.4 Floor Plans of the 2736-Z Storage Building and the 2736-ZB Building Showing Criticality Alarm and NAD Locations	10	8/92

Issued: 8/92

Supersedes: 6/90

PNL-MA-583

Section
Page

Contents
4 of 5

	<u>Page No.</u>	<u>Issue Date</u>
E.1 Floor Plan of the 303-A Building Showing NAD Location	3	8/92
E.2 Floor Plan of the 303-B Building Showing NAD Location	3	8/92
E.3 Floor Plan of the 303-E Building Showing Criticality Alarm and NAD Locations	4	8/92
E.4 Floor Plan of the 303-G Building Showing NAD Location	4	8/92
E.5 Floor Plan of the 3707-G Building Showing Location of NAD That Is Intended to Cover an Event in 303-K Building	5	8/92
E.6 Floor Plan of the 303-M Oxide Burner Facility Showing NAD Location	5	8/92
E.7 Floor Plan of the 304 Building Showing NAD Location	6	8/92
E.8 Floor Plans of the 306 Building First and Second Floors Showing Criticality Alarm and NAD Locations	8	8/92
E.9 Floor Plans of the 308 Building First and Second Floors Showing Criticality Alarm and NAD Locations	11	8/92
E.10 Floor Plans of the 308 Building Tunnel and Service Corridor Showing Criticality Alarm Locations	12	8/92
E.11 Floor Plan of the 313 Building Showing Criticality Alarm and NAD Locations	13	8/92
E.12 Floor Plan of the 324 Building First Floor Showing Criticality Alarm and NAD Locations	16	8/92
E.13 Floor Plan of the 324 Building Second Floor Showing Criticality Alarm and NAD Locations	17	8/92
E.14 Floor Plan of the 324 Building Third Floor Criticality Alarm and NAD Locations	18	8/92
E.15 Floor Plan of the 324 Building Basement Showing Criticality Alarm and NAD Locations	19	8/92

Issued: 8/92

Supersedes: 6/90

PNL-MA-583

Section
Page Contents
5 of 5

	<u>Page No.</u>	<u>Issue Date</u>
E.16 Floor Plan of the 325 Building First Floor Showing Criticality Alarm and NAD Locations	21	8/92
E.17 Floor Plan of the 325 Building Basement Showing Criticality Alarm and NAD Locations	22	8/92
E.18 Floor Plan of the 325 Building Second Floor Showing Criticality Alarm Locations	24	8/92
E.19 Floor Plans of the 327 Building First Floor and Basement Showing Criticality Alarm and NAD Locations	25	8/92
E.20 Floor Plan of the 327 Building Roof Showing Criticality Alarm Locations	26	8/92
E.21 Floor Plan of the 328 Building First Floor Showing Criticality Alarm Locations	27	8/92
E.22 Floor Plans of the 328 Building Second and Third Floor Showing Criticality Alarm Locations . . .	28	8/92
E.23 Floor Plan of the 329 Building First Floor Showing the NAD Location	29	8/92
E.24 Floor Plan of the 333 Building Showing Criticality Alarm and NAD Locations	31	8/92
E.25 Floor Plan of the 3712 Building Showing NAD Locations	32	8/92
E.26 Floor Plan of the 3716 Building Showing Criticality Alarm and NAD Locations	33	8/92
E.27 Floor Plan of the 3720 Building Showing NAD Locations	35	8/92
E.28 Floor Plan of the 3730 Building Showing NAD Location	36	8/92
F.1 Floor Plans of the FFTF Reactor Support Buildings at the 550-ft and 533-ft Levels Showing NAD Locations	3	8/92
F.2 Floor Plans of the 405 Reactor Containment Building at the 500-ft and 489-ft Levels Showing NAD Location	4	8/92
F.3 Floor Plan of the 403 Building Fuel Storage Facility Ground Floor Showing NAD Location	5	8/92

CHAPTER 1.0

INTRODUCTION

1.0 INTRODUCTION

Hanford facilities that contain fissionable materials capable of achieving critical mass are monitored with nuclear accident dosimeters (NADs) in compliance with the requirements of DOE Order 5480.11, Chapter XI, Section 4.c. (DOE 1988). The U.S. Department of Energy (DOE) Richland Field Office (RL) has assigned the responsibility for maintaining and evaluating the Hanford NAD system to the Instrumentation and External Dosimetry (I&ED) Section of Pacific Northwest Laboratory's (PNL's) Health Physics Department. This manual provides a description of the Hanford NAD, criteria and instructions for proper NAD placement, and the locations of these dosimeters onsite.

The manual shall be updated every two years by August 1 of that year. It is intended for use by individuals who monitor radiation protection activities. If a criticality occurs, this information will be necessary to locate and quickly retrieve the NADs for dose assessment.

1.1 MANUAL CONTENTS

The manual consists of three chapters and six appendixes. The three chapters contain general information, such as descriptions of and placement criteria for NADs and an NAD master list. Appendix A contains a master list of NAD locations in the 100, 200-East, 200-West, 300, and 400 Areas. Appendixes B through F contain exact descriptions and floor plans of NAD locations by area. Although the floor plans show the criticality alarm systems associated with the NADs, descriptions of these systems or other information about them are not provided.

1.2 FLOOR PLAN SYMBOLS

The floor plans are grouped by the five main operating areas at Hanford (i.e., 100, 200-East, 200-West, 300, and 400 Areas). These floor plans show the exact locations of the NADs and associated criticality alarm systems within specific facilities. Each symbol on the map represents an important element as described below:

1.2 FLOOR PLAN SYMBOLS (contd)

Nuclear accident dosimeters provide neutron and gamma dose information and are described in more detail in the next chapter. The number assigned to the NAD is located beside the symbol.

Critical radiation event detectors are high-level gamma or neutron radiation detectors that are grouped (not necessarily physically) in sets of three or more. At least two of the detectors in the group must be tripped before the criticality alarm sounds. These are the detectors used in the majority of Hanford facilities.

Critical radiation event alarms are located throughout facilities with critical radiation event detectors. When activated, these alarms produce a howling "ooh-gah" sound that means "evacuate the premises immediately."

Comparator panels are wall-mounted cabinets containing the electronics interconnecting sets of critical radiation event detectors. This electrical system evaluates the operating status of each detector and determines whether or not a criticality alarm should be sounded. Indicator lights on the panel can be used to verify trouble or an alarm condition.

Criticality alarm detector stations consist of three interconnected gamma criticality alarm detectors (CADs) and are a part of the new criticality detector and alarm system located only in the following 200-Area facilities: 202-A, 234-5, 236-Z, 2736-Z and hallway. At least two CADs must be tripped to sound the criticality alarm.

Criticality alarm howlers are located in the following 200-Area facilities: 202-A, 234-5, 236-Z, and 2736-Z. The alarm howlers are a part of the new criticality detector and alarm system. When activated, these alarms produce a howling "ooh-gah" sound that means "evacuate the premises immediately."

Criticality alarm neutron detector stations consist of neutron detectors grouped in sets of three or more (up to six) and are part of the new criticality detector and alarm system found only in the 2736-Z Facility.

CHAPTER 2.0

NAD DEFINITION, DESCRIPTION, AND EXCHANGE

2.0 NAD DEFINITION, DESCRIPTION, AND EXCHANGE

Definition

The Hanford NAD is a stationary device that provides neutron and gamma dose information following a criticality or high-level radiation event. This information is used to determine the neutron dose in rad, the gamma dose in the presence of neutrons from 10 to 10^4 rad, and the neutron fluence in each of five energy intervals (which permits calculation of neutron dose equivalent in rem).

Description

The NAD (see Figure 2.1) is a paraffin-filled aluminum cylinder, 23 cm in diameter and 30-cm high, containing a polyethylene candlestick (sometimes referred to as a wand). The candlestick has an inner and outer dosimetry package and is 32 1/2-cm long.

The components of the inner dosimetry package at the center of the paraffin moderator measure the approximate tissue dose (in rad) from neutron and photon exposures. The inner dosimetry package contains a plastic holder containing a gold foil to measure thermalized neutrons, a TLD-600 chip to measure neutrons, and a TLD-700 chip to measure photons.

The outer dosimetry package is used to measure the gamma dose (TLD-700 chip) and to calculate the neutron spectrum from analysis of neutron activation products found in the indium, gold, and copper foils, and a sulfur pellet. The indium, gold, and copper foils are located within a cadmium shield at one end of the package. Additional indium and gold foils, a sulfur pellet, and a TLD-700 chip are located outside the cadmium shield.

NOTE: *The numbers in parentheses in Figure 2.1 are the numbers assigned to the individual chips and foils.*

Exchange

The candlestick part of the dosimeter should be exchanged routinely, usually annually. However, a more frequent exchange schedule may be arranged with I&ED.

Candlestick exchange is conducted by I&ED according to established schedules. The contractor is sent replacement candlesticks and instructed to return the used ones. Shortly thereafter, a report listing the accumulated neutron and gamma doses for each candlestick is sent to the contractor.

FIGURE 2.1. Nuclear Accident Dosimeter

CHAPTER 3.0

CRITERIA AND INSTRUCTIONS FOR NAD PLACEMENT

3.0 CRITERIA AND INSTRUCTIONS FOR NAD PLACEMENT

Each contractor is responsible for the specific placement of NADs; however, the placement criteria described in this chapter should be used to determine the correct position for each dosimeter.

3.1 GENERAL PLACEMENT CONSIDERATIONS

The NADs must be placed as close to the actual work locations as possible to allow for accurate extrapolation of dose to personnel. The number of dosimeters required to monitor a given location is determined by the type of operation performed. For example, the dosimeter requirements for isolated hoods where serious radiation events could occur are different from those for processing lines where an event could occur anywhere along the line.

Because NADs integrate the dose for both neutron and gamma radiation, the accumulation of excessive background radiation before an event could significantly affect the dose interpretation.

For areas where unsuitable environmental conditions exist (e.g., high temperatures) or where high background doses occur routinely, methods of dose measurement other than the Hanford NAD may be satisfactory. In such instances, I&ED should be contacted to discuss alternatives.

In addition to technical placement considerations, the practical aspect of placing dosimeters where they will not interfere with normal work practices should be considered.

3.2 PLACEMENT CRITERIA

NADs are required for monitoring the following areas:

- any location accessible to personnel where a criticality or high-level radiation event could conceivably occur (e.g., wherever there is the potential for a critical mass)
- any location accessible to personnel where radiation dose rates ≥ 100 mrem/h could conceivably occur as a result of a radiation accident

3.2 PLACEMENT CRITERIA (contd)

- any location where a criticality or serious radiation event of a similar magnitude is conceivable, regardless of the considerations of the above two items.

Consideration must also be given to the following factors:

- The background neutron dose rate at the NAD location should be as low as possible, generally not exceeding 20 mrem/h or 175 rem/yr. To monitor locations where the neutron dose rates exceed 20 mrem/h, the NADs should be positioned at a distance sufficient to reduce the chronic dose rates to the prescribed dose-rate levels. For areas with higher background dose rates, a more frequent candlestick exchange should be arranged with I&ED.
- The background gamma radiation exposure rate at the NAD location should be as low as possible, not exceeding 3 mR/h or 25 R/yr. For areas with higher background dose rates, a more frequent exchange schedule should be arranged with I&ED.

3.3 PLACEMENT INSTRUCTIONS

NADs should be placed where they can be easily retrieved and where the shielding and obstruction between the dosimeter and the potential radiation source are minimal. For example, place them in a hallway near the room to be monitored if the shielding provided between the hallway and the room is nominal. If this location is not practical, consider placing them near a doorway to facilitate their retrieval.

For discrete event sites (e.g., single hoods, storage vaults, hot cells, reactors, etc.), place the NADs as close to the potential source as practical, while considering the other placement instructions. In general, NADs should be positioned at 2 m, 15 m, and at the maximum available distance from the radioactive source within the facility to provide optimum dose measurement.

For processing lines or other large sources with dimensions >8 m, place the NADs so that each point on the processing line or source is within 8 m of a NAD. Wherever practical, dosimeters should also be positioned on approximate 15-m centers, with each NAD within 2 m of the source material.

REFERENCE

Issued: 8/92

Supersedes: 6/90

PNL-MA583

Section Reference
Page 1 of 1

REFERENCE

U.S. Department of Energy (DOE). 1988. Radiation Protection for Occupational Workers. DOE Order 5480.11, Washington, D.C.

APPENDIX A

MASTER LIST OF NAD LOCATIONS

APPENDIX A

MASTER LIST OF NAD LOCATIONS

This appendix provides the master list of NAD locations indicating the dosimeter number, area, building, and responsible contractor.

<u>Dosimeter No.</u>	<u>Area</u>	<u>Building</u>	<u>Contractor</u>
104-105	300	3720	PNL
106	300	306-W	PNL
108	300	306-W	PNL
109	300	325	PNL
113	300	303-E	WHC
115	300	306-W	PNL
116	300	306-E	WHC
117	300	306-W	PNL
118	300	303-A	WHC
119	300	333	WHC
120	300	313	WHC
122-123	300	313	WHC
124-125	300	325	PNL
126-130	300	333	WHC
133-136	300	327	PNL
137	300	333	WHC
138-139	300	327	PNL
140-141	200-E	202-A	WHC
142	300	308	WHC
143	300	3730	PNL
144	300	303-M	WHC
146	200-E	2736-Z	WHC
153	400	405	WHC
154	300	327	PNL
155	400	4717	WHC
156-157	400	405	WHC
158-159	200	202-A	WHC
160	400	403	WHC
164	200-W	234-5	WHC
165-166	200-E	202-A	WHC
169	200-E	202-A	WHC
175	200-E	202-A	WHC
178-182	200-E	202-A	WHC
184-189	200-E	202-A	WHC
190-194	300	325	PNL
198-200	300	308	WHC

MASTER LIST OF NAD LOCATIONS (contd)

<u>Dosimeter No.</u>	<u>Area</u>	<u>Building</u>	<u>Contractor</u>
203-204	300	308	WHC
205	300	3720	PNL
206-211	300	308	WHC
225	300	333	WHC
226	100-K	105-KE	WHC
239	300	303-B	WHC
240	100-K	105-KE	WHC
241	300	3707-G for 303-K	WHC
242	200-W	2736-ZB	WHC
245	100-K	105-KW	WHC
246	200-W	2736-ZB	WHC
247	300	3716	WHC
248	200-W	2736-ZB	WHC
249	300	313	WHC
250	300	3716	WHC
254	200-W	2736-ZB	WHC
256-258	200-W	234-5	WHC
261	200-W	236-Z	WHC
262-267	200-W	234-5	WHC
268	200-W	236-Z	WHC
269	200-W	234-5	WHC
270	200-W	236-Z	WHC
271-273	200-W	234-5	WHC
274-279	200-W	236-Z	WHC
280-281	200-W	234-5	WHC
282	200-W	236-Z	WHC
283-286	200-W	234-5	WHC
290	200-W	234-5	WHC
297	100-K	105-KE	WHC
298	100-K	105-KW	WHC
301	300	304	WHC
302	300	303-G	WHC
303	300	3712	WHC
304	300	313	WHC
305	300	3712	WHC
306	300	308	WHC
307-315	100-N	105-N	WHC
321	300	3720	PNL
323-324	300	308	WHC
327	300	308	WHC
330	300	333	WHC
336	100-K	105-KW	WHC
337	100-N	105-N	WHC

MASTER LIST OF NAD LOCATIONS (contd)

<u>Dosimeter No.</u>	<u>Area</u>	<u>Building</u>	<u>Contractor</u>
340	300	324	PNL
342-346	300	324	PNL
348	300	324	PNL
350-351	300	324	PNL
354	300	329	PNL
358-361	300	324	PNL
364-369	300	324	PNL
377	100-N	105-N	WHC
382	300	306-W	PNL
385	300	308	WHC

APPENDIX B

100 AREA CRITICALITY ALARM AND NAD LOCATIONS

APPENDIX B

100 AREA CRITICALITY ALARM AND NAD LOCATIONS

This appendix describes the criticality alarm and NAD locations in the 100 Area, by building. The buildings are arranged in numerical (from low to high numbers) and alphabetical order. At least one page is devoted to descriptions of the numbered NADs and their locations. A floor plan of each building is also provided to pinpoint criticality alarm and NAD locations within each building.

105-KE BUILDING

100-K AREA

<u>Dosimeter No.</u>	<u>Location</u>
226	Mounted on the north wall of the storage area, on a vertical column 40 ft west of the wash-pad area and 5 ft above the door.
240	Mounted near the vertical concrete column in the storage area west of the pickup chutes, 5 ft above the floor.
297	Mounted on the vertical steel column at the east end of the transfer area, 5 ft above the floor.

- ⊕ Critical Radiation Event Detector
- ⚡ Critical Radiation Event Alarm
- Ⓢ Nuclear Accident Dosimeter

39207013.3

FIGURE B.1. Floor Plan of the Ground Floor of the 105-KE Building Showing Criticality Alarm and NAD Locations

105-KW BUILDING

100-K AREA

<u>Dosimeter No.</u>	<u>Location</u>
245	Mounted near the vertical concrete column in the storage area in front of the pickup chutes, 5 ft above the floor.
298	Mounted on the vertical steel column at the east end of the transfer area, 5 ft above the floor.
336	Mounted on the north wall of the storage area on a vertical column, 20 ft west of the wash-pad area.

- ⊕ Critical Radiation Event Detector
- ⚡ Critical Radiation Event Alarm
- ⊙ Nuclear Accident Dosimeter

39207013.2

FIGURE B.2. Floor Plan of the Ground Floor of the 105-KW Building Showing Criticality Alarm and NAD Locations

105-N REACTOR PLANT100-N AREA

<u>Dosimeter No.</u>	<u>Location</u>
<u>Ground Floor</u>	
307	Mounted on the center section of the north wall of the Metal Preparation Room (Room 181), 6 ft above the floor.
308	Mounted on the east wall of the Metal Preparation Room (Room 181), 18 ft north of entrance door and 6 ft above the floor.
309	Mounted on the north wall of Metal Storage Room (Room 182), 2 ft east of the entrance door and 6 ft above the floor.
310	Located outside of the W elevator railing at the northwest end of the elevator, 2 ft from the north end of the railing, and 2 ft from the elevator door.
311	Mounted on the north wall of Storage Basin Area (Room 192), 1 ft east of door to Corridor 22, and 6 ft above the floor.
313	Located outside of the W elevator railing at the northeast end of the elevator, 2 ft from the north end of the railing.
314	Mounted on the west wall of the Discharge Pit Area (Room 175), 4 in. from Corridor 7, and 5 ft above the Corridor 7 floor.
315	Mounted on the west wall of the Metal Preparation Room (Room 181), 3 ft north of entrance door, and 7 ft above the floor.
337	Mounted on the wall of the northwest corner of the storage basin, 6 ft north of the north transfer pit, and 6 ft above the floor.
377	Mounted on the I-beam, 1 ft 6 in. southwest of the south transfer pit, 7 ft from the south wall, and 7 ft above the floor.
<u>Sub-Basement</u>	
312	Mounted in Corridor 5 at the southwest entrance to Room 29, on the west wall, 1 ft south of the door, and 5 ft above the floor.

FIGURE B.3. Floor Plans of the 105-N Reactor Plant Ground Floor and Sub-Basement Showing Criticality Alarm and NAD Locations

APPENDIX C

200-EAST AREA CRITICALITY ALARM AND NAD LOCATIONS

APPENDIX C

200-EAST AREA CRITICALITY ALARM AND NAD LOCATIONS

This appendix describes the criticality alarm and NAD locations in the 200-East Area, by building. The buildings are arranged in numerical (from low to high) and alphabetical order. At least one page is devoted to descriptions of the numbered NADs and the locations. A floor plan of each building displays the criticality alarm and NAD locations within the building.

202-A BUILDING200-EAST AREA

<u>Dosimeter No.</u>	<u>Location</u>
<u>Crane Cab Gallery Level</u>	
140	Mounted on the north wall of the east crane cab, 7 ft 6 in. west of the crane cab entrance.
141	Mounted 7 ft 6 in. east of the cab entrance.
<u>Pipe and Operating (P&O) Gallery Level</u>	
169	Mounted on the north wall of the White Room opposite Rack 74, Column 5, and 5 ft 4 in. above the floor.
180	Mounted on the north wall of P&O Gallery west stairway, 5 ft from the west wall, and 5 ft 9 in. above the floor
185	Mounted on the south wall behind the Central Control Room panel, 40 ft from the east wall, and 5 ft 9 in. above the floor.
187	Mounted on the north wall of the P&O Gallery, 2 ft 5 in. from the SWP Lobby entrance into the P&O Gallery, and 5 ft above the floor.
<u>Sample Gallery Level</u>	
166	Mounted on the north wall of the Sample Gallery, 17 ft from Stairway 2 (SWP stairwell), and 5 ft 7 in. above the floor.
178	Mounted on the north wall of the Sample Gallery, 1 ft from emergency exit door to the Aqueous Make-Up Room (AMU), and 4 ft 11 in. above the floor.
179	Mounted on the north wall of the Sample Gallery across from L-2 sample station and 4 ft 10 in. above the floor.

202-A Building, 200-East Area (contd)

<u>Dosimeter No.</u>	<u>Location</u>
<u>Storage Gallery Level</u>	
158	Mounted on the west wall of the Hot Shop Lobby, 5 ft south of airlock door, and 5 ft above the floor.
159	Mounted on the north wall of the N-Cell Control Room, 1 ft east of the entry door from the Product Receiving (PR) corridor, and 6 ft 3 in. above the floor.
165	Mounted on the south wall of the second floor of N-Cell, 26 ft from the west wall, and 5 ft 9 in. above the floor.
175	Mounted on the north wall of the Q-Cell Loadout Room airlock, 4 ft 11 in. from the east entrance and 6 ft 2 in. off the floor.
181	Mounted on the north wall of the N-Cell second floor Control Room, 4 ft 6 in. from the stairwell door, and 5 ft 9 in. above the floor.
182	Mounted on the north wall of the PR Corridor, 1 ft 3 in. from entrance door to R-Cell, and 5 ft 8 in. above the floor.
184	Mounted on the north wall of the PR Corridor across from N-Cell Control Room entrance, 5 ft 10 in. above the floor.
186	Mounted on the south wall of the first floor N-Cell, opposite Calciner Glovebox N-4.
188	Mounted on the south wall of the PR Room, 1 ft from the east wall, and 5 ft 10 in. above the floor.
189	Mounted on the north wall of the PR Room, in back of L-10 Labyrinth at the bottom of the stairwell, 5 ft 11 in. above the floor.

FIGURE C.1. Floor Plan of the 202-A Building Crane Lab Gallery Showing NAD Locations

39207013.4

FIGURE C.2. Floor Plan of the 202-A Building Pipe and Operating Gallery Showing Criticality Alarm and NAD Locations

39207013.7

FIGURE C.3. Floor Plan of the 202-A Building Sample Gallery Level Showing Criticality Alarm and NAD Locations

39207013.6

FIGURE C.4. Floor Plan of the 202-A Building Storage Gallery Showing Criticality Alarm and NAD Locations

APPENDIX D

200-WEST AREA CRITICALITY ALARM AND NAD LOCATIONS

APPENDIX D

200-WEST AREA CRITICALITY ALARM AND NAD LOCATIONS

This appendix describes the criticality alarm and NAD locations in the 200-West Area, by building. The buildings are arranged in numerical (from low to high) and alphabetical order, except for those that are grouped under "234-5 Facilities." At least one page is devoted to descriptions of the numbered NADs and the locations. A floor plan of each building displays the criticality alarm and NAD locations within the building.

234-5 FACILITIES200-WEST AREA

<u>Dosimeter No.</u>	<u>Bldg. No.</u>	<u>Location</u>
	<u>234-5</u>	<u>First Floor</u>
164		Mounted on south wall inside Room 221 (Health Physics Office), 2 ft 6 in. west of entrance, 6 ft above floor level.
256		Mounted on the south wall of Corridor 3, 4 ft from the east exit, and 5 ft 6 in. above the floor.
257		Mounted on the west wall of Corridor 4B, 6 ft 3 in. south of the airlock entrance, and 5 ft 5 in. above the floor.
258		Mounted on the south wall of Corridor 4C, 1 ft 8 in. from the south outside exit, and 5 ft 5 in. above the floor.
262		Mounted on west wall of Room 232 adjacent to entrance to 9-A Control Room, 4 ft north of door, and 4 ft 7 in. above the floor.
263		Mounted on the north wall of the 229 Mezzanine at the top of the stairwell, 4 ft 2 in. above the floor.
264		Mounted on the north wall of Corridor 5, 4 ft west of door to 228-A, 4 ft from the floor.
265		Mounted on the south wall of Room 228-C, 2 ft west of entrance, between Columns 10 and 11, and 5 ft 6 in. above the floor level.
266		Mounted on the west wall of Room 228-C, 6 in. from the south wall, between Columns 12 and 13, and 5 ft 10 in. above floor level.

234-5 Facilities, 200-West Area (contd)

<u>Dosimeter No.</u>	<u>Bldg. No.</u>	<u>Location</u>
	234-5	<u>First Floor (cont)</u>
267		Mounted on the west wall of Room 166, 20 in. south of west exit, near Column 12, and 4 ft 8 in. above the floor.
269		Mounted on the south wall of Room 228-C, 6 in. from the south wall, between Columns 12 and 13, and 5 ft 10 in. above the floor.
271		Mounted on the south wall of Room 179B, 5 ft 2 in. east of the outside exit, and 5 ft 4 in. above the floor.
272		Mounted on the south wall of the airlock to the office annex, 11 in. from the west wall, and 5 ft 3 in. above the floor.
273		Mounted on the south wall of Corridor 10, 4 ft 4 in. east of the door to Room 184, and 5 ft 3 in. above the floor.
280		Mounted on the east wall of Corridor 13A, 1 ft south of north exit door, and 4 ft 11 in. above the floor level.
281		Mounted on the east wall of Corridor 14-A, between Columns 12 and 13, 5 ft 9 in. south of north exit door, and 5 ft 5 in. above the floor level.
283		Mounted on the north wall of the main entrance lobby, 6 in. east of emergency exit Door 102, and 4 ft 8 in. above the floor.
290		Mounted on the west wall of Room 169, 2 ft 2 in. from the south wall, and 5 ft 9 in. above the floor.
284		Mounted on the outside of the north wall of the Power Office (Room 321) 1 ft 6 in. west of the entrance, near Column 17, and 5 ft 5 in. above the floor.

234-5 Facilities, 200-West Area (contd)

<u>Dosimeter No.</u>	<u>Bldg. No.</u>	<u>Location</u>
	<u>234-5</u>	<u>Second Floor</u>
285		Mounted on the north wall of Corridor 1, near Column 9, 8 ft 3 in. west of the entrance to Room 303, and 5 ft 4 in. above the floor.
286		Mounted on the east wall of Corridor 2, at Column 3, 2 ft 4 in. from the airlock door to Room 308, and 5 ft 5 in. above the floor.
	<u>236-Z</u>	<u>First Floor</u>
261		Mounted on the east wall of Corridor 14, 2 ft north of the east entrance, and 5 ft 10 in. above the floor.
268		Mounted on the west wall of Corridor 11, 6 feet north of west entrance, and 4 ft 9 in. above floor.
		<u>Second Floor</u>
270		Mounted on the east wall of Corridor 25, 2 ft south of the east entrance and 4 ft 9 in. above the floor.
274		Mounted on the west wall of Corridor 21, 7 ft 6 in. north of the west entrance, and 4 ft 9 in. above the floor.
		<u>Third Floor</u>
282		Mounted on the south wall of Corridor 31, 7 ft east of the west entrance, and 4 ft 9 in. above the floor.
		<u>Fourth Floor</u>
275		Mounted on the west wall of Room 41, 6 ft west of the south entrance, and 4 ft 10 in. above the floor.

234-5 Facilities, 200-West Area (contd)

<u>Dosimeter No.</u>	<u>Bldg. No.</u>	<u>Location</u>
276	236-Z	Mounted on the east wall of Room 43, 3 ft 7 in. north of the south outside entrance, and 4 ft 9 in. above the floor.
279		Mounted on the west wall of Room 44, 2 ft 4 in. south of the west entrance, and 4 ft 10 in. above the floor.
		<u>Fifth Floor</u>
277		Mounted on the south wall of Room 50, 1 ft 5 in. east of the west entrance, and 4 ft 9 in. above the floor.
		<u>Sixth Floor</u>
278		Mounted on the south wall of Room 60, 1 ft 5 in. east of the west entrance, and 4 ft 9 in. above the floor.

39207013.15

FIGURE D.1. Floor Plan of the 234-5 Building First Floor Showing Criticality Alarm and NAD Locations

39207013.17

FIGURE D.2. Floor Plans of the 234-5 Building Second Floor and Duct Level Showing Criticality Alarm and NAD Locations

39207013.16

FIGURE D.3. Floor Plan of the 236-Z Building Showing Criticality Alarm and NAD Locations

2736-Z AND 2736-ZB BUILDINGS200-WEST AREA

<u>Dosimeter No.</u>	<u>Bldg. No.</u>	<u>Location</u>
	2736-Z	
146		Mounted on the west wall of the corridor of the Plutonium Storage Vault (2736-Z Building), 3 ft from the south door, and 5 ft above the floor.
	2736-ZB	
242		Mounted on the north wall of the Neutron Detector Analysis Room 637, 1 ft 6 in. east of the door, and 4 ft 4 in. above the floor.
246		Mounted on the north wall between Rooms 643 and 644, and 4 ft 4 in. above the floor.
248		Mounted on the wall in the corridor between Rooms 600 and 602, 2 ft 6 in. south of the west door, and 4 ft 4 in. up from the floor level.
254		Mounted on the east wall of shipping Room 641, 3 ft north of the door, and 4 ft 4 in. above the floor.

FIGURE D.4. Floor Plans of the 2736-Z Storage Building and the 2736-ZB Building Showing Criticality Alarm and NAD Locations

APPENDIX E

300 AREA CRITICALITY ALARM AND NAD LOCATIONS

APPENDIX E

300 AREA CRITICALITY ALARM AND NAD LOCATIONS

This appendix describes the criticality alarm and NAD locations in the 300 Area, by building. The buildings are arranged in numerical (from low to high) and alphabetical order. At least one page is devoted to descriptions of the numbered NADs and the locations. A floor plan of each building displays the criticality alarms and NAD locations within the building.

303 BUILDINGS300 AREA

<u>Dosimeter No.</u>	<u>Bldg. No.</u>	<u>Location</u>
118	303-A	Mounted on the north wall, 15 ft from northwest corner, and 6 ft above the floor.
239	303-B	Mounted on the north wall, 14 ft 6 in. from the northwest corner, and 6 ft above the floor.
113	303-E	Mounted on the north wall, 13 ft from the northwest corner, and 6 ft above the floor.
302	303-G	Mounted on the south wall, 15 ft from the southwest corner, and 6 ft above the floor.
241 ^(a)	3707-G	Mounted on the east wall, 2 ft from northeast corner, and 5 ft above the floor.
144	303-M	Mounted on the west wall of the southeast end of the Operations Room, 6 ft south of the personnel entrance door, and 6 ft above the floor.

(a) This dosimeter is intended to cover an event in 303-K. It has been placed in 3707-G because of the more favorable neutron detection conditions there.

FIGURE E.1. Floor Plan of the 303-A Building Showing NAD Location

FIGURE E.2. Floor Plan of the 303-B Building Showing NAD Location

FIGURE E.3. Floor Plan of the 303-E Building Showing Criticality Alarm and NAD Locations

FIGURE E.4. Floor Plan of the 303-G Building Showing NAD Location

FIGURE E.5. Floor Plan of the 3707-G Building Showing Location of NAD That Is Intended to Cover an Event in 303-K Building

FIGURE E.6. Floor Plan of the 303-M Oxide Burner Facility Showing NAD Location

39207013.46

304 BUILDING

300 AREA

<u>Dosimeter No.</u>	<u>Bldg. No.</u>	<u>Location</u>
301	304	Mounted on the north wall, 1 ft east of the door, and 5 ft 6 in. above the floor.

Ⓓ Nuclear Accident Dosimeter

39207013.27

FIGURE E.7. Floor Plan of the 304 Building Showing NAD Location

306 BUILDING300 AREA

<u>Dosimeter No.</u>	<u>Location</u>
<u>306-W Building</u>	
106	Mounted just inside exterior Door 2 at the west end of the Room 142, 2 ft 2 in. north of Door 2, and 3 ft 11 in. above the floor.
108	Mounted just inside the south exterior door to Room 128, 1 ft 3 in. west of the door, and 3 ft 11 in. above the floor.
115	Mounted on the west wall of the corridor between Rooms 163 and 164 in the Powder Laboratory, 3 ft 5 in. above the floor, and 10 in. north of the single door.
117	Mounted on the north wall in the east end of Room 160 (the Induction Heating Facility in the North High Bay), centered between doors 9 and 9A, 9 in. west of single door, and 3 ft 9 in. above the floor.
382	Mounted on the south wall of the corridor outside Room 108, 1 ft 2 in. west of the exterior door, and 4 ft above the floor.
<u>306-E Building</u>	
116	Mounted on the south wall of Room 170 (Central Assembly Area), 1 ft 2 in. east of southwest entry door, and 5 ft 7 in. above the floor.

39207013.35

FIGURE E.8. Floor Plans of the 306 Building First and Second Floors Showing Criticality Alarm and NAD Locations

308 BUILDING306 AREA

<u>Dosimeter No.</u>	<u>Location</u>
<u>First Floor</u>	
142	Mounted on the east wall of Room 154, 3 ft south of the high bay door, and 6 ft 4 in. above the floor.
198	Mounted on the west wall of Room 102, 1 ft 6 in. north of the hall door, and 6 ft 7 in. above the floor.
199	Mounted on the east wall in the south end of Corridor 4, 2 ft from the door to Room 106, and 6 ft 8 in. above the floor.
200	Mounted on the south wall of Room 112, 9 in. from door to Room 102, and 6 ft 7 in. above the floor.
203	Mounted on the south wall of Room 114, 2 ft east of the corridor door (entrance), and 7 ft above the floor (candle hits ceiling when removed).
204	Mounted on the east wall of Room 119, 10 in. from the door, and 6 ft 9 in. above the floor.
206	Mounted on the east wall of Room 120, 1 ft 4 in. from the emergency exit door, and 6 ft 7 in. above the floor.
207	Mounted on the south wall of Room 131, 2 ft from the door to Room 125, and 6 ft 8 in. above the floor.
208	Mounted on the south wall of Room 138, 8 ft 3 in. from the west wall, and 7 ft above the floor.
306	Mounted on the south wall of Room 162, 2 ft east of the west door to Room 160, and 6 ft above the floor.
323	Mounted on the east wall of Room 113, 6 ft 6 in. north of the door, and 7 ft above the floor (have to lift pot off wall to get candle out).

308 Building, 300 Area (contd)Dosimeter No.Location

324 Mounted on the west wall of Room 101, 8 in. south of the door, and 6 ft above the floor.

327 Mounted on the south wall of Room 101, 1 ft east of the south door, and 6 ft above the floor.

Second Floor

209 Mounted on the south wall of Room 208, 8 in. from the door, and 6 ft 8 in. above the floor.

210 Mounted on the east wall of Room 219, 1 ft 5 in. from the door, and 6 ft 8 in. above the floor.

211 Mounted on the north wall of Room 221, 2 ft from the door to Room 231, and 6 ft 8 in. above the floor.

385 Mounted on the north wall of Room 213, 15 in. from the door to Room 215, and 7 ft 5 in. above the floor.

39207013.26

FIGURE E.9. Floor Plans of the 308 Building First and Second Floors Showing Criticality Alarm and NAD Locations

FIGURE E.10. Floor Plans of the 308 Building Tunnel and Service Corridor Showing Criticality Alarm Locations

313 BUILDING

300 AREA

<u>Dosimeter No.</u>	<u>Location</u>
120	Mounted on the east wall of the east corridor outside the Engineering Pilot Plant, 4 ft north of the outside roll-up door at the southeast corner of the building, and 6 ft above the floor.
122	Mounted in the corridor opposite the wall of the northwest corner of the Slug Recovery Room, 1 ft south of the corner, and 5 ft 6 in. above the floor.
123	Mounted on the east wall of the east corridor opposite the component preparation area, 6 ft south of the corner, and 5 ft 6 in. above the floor.
249	Mounted on the west wall of the Slug Recovery Room, 3 ft north of the door, and 5 ft 6 in. above the floor.
304	Mounted on the north wall of the component preparation area, 1 ft east of the west door, and 5 ft 6 in. above the floor.

39207013.24

FIGURE E.11. Floor Plan of the 313 Building Showing Criticality Alarm and NAD Locations

324 BUILDING300 AREA

<u>Dosimeter No.</u>	<u>Location</u>
<u>First Floor</u>	
340	Located in the northeast corner of the Module 4 I-beam (south side of I-beam), Engineering Development Laboratory (EDL) 102, 5 ft 5 in. above the floor.
342	Mounted on the west wall of Room 139, 1 ft 10 in. north of the west entrance door, and 3 ft 3 in. above the floor.
344	Mounted on the north wall of Room 139, 1 ft 5 in. east of the door to EDL 146, and 3 ft 6 in. above the floor.
345	Mounted on the east wall of Room 139, 1 ft 9 in. north of emergency exit Door 113, and 3 ft 3 in. above the floor.
351	Located on the south wall inside the entry foyer, 6 ft 5 in. west of the entry door, and 3 ft 7 in. above the floor.
358	Mounted on the northwest corner wall of the B-Cell Operating Gallery, 10 in. north of the door to Corridor 10, and 3 ft 3 in. above the floor.
359	Mounted on the north wall of the A-Cell Operating Gallery, 5 ft 4 in. east of the door to Stairway 8, and 3 ft 3 in. above the floor.
360	Mounted on the south wall of the C-Cell Operating Gallery, 3 ft 4 in. east of the door to Corridor 13, and 3 ft 3 in. above the floor.
361	Mounted on the north wall of the cask-handling area, 2 ft east of the small door to the load-out station, and 3 ft 3 in. above the floor.
364	Mounted on the north wall of the Regulated Shop, 2 ft west of the small outside Door 114, and 3 ft 3 in. above the floor.

324 Building, 300 Area (contd)Dosimeter No.LocationSecond Floor

- 343 Mounted on the north wall inside the stairwell south of Room 236, 8 in. west of the east wall, and 3 ft 8 in. above the floor.
- 365 Mounted on the south wall of the B-Cell Operating Gallery, 2 ft west of the entrance from the D-Cell Operating Gallery and 4 ft above the floor.
- 366 Mounted on the northwest wall of the B-Cell Operating Gallery, 9 in. north of the door to Corridor 20, and 2 ft 11 in. above the floor.
- 367 Mounted on the north wall of the A-Cell Operating Gallery, 11 in. east of the door to Stairway 8, and 3 ft 11 in. above the floor.
- 368 Mounted on the south wall of the D-Cell Operating Gallery, 1 ft 3 in. east of the door to Stairway 7, and 3 ft 3 in. above the floor.

Third Floor

- 369 Mounted 5 ft 11 in. east of the elevator door on the north end wall of the corridor/stairwell, and 5 ft 6 in. above the floor.

Basement

- 346 Located in the northwest corner of the corridor outside Room 3A, 1 ft 7 in. south of Door 104, and 4 ft 11 in. above the floor.
- 348 Mounted 4 in. west of Door 101 (Room 3H), 1 ft 6 in. above the floor.
- 350 Mounted at the south side of the door to Room 3D, 1 ft 1 in. south of the door, and 3 ft 1 in. above the floor.

- Critical Radiation Event Detector
- Critical Radiation Event Alarm
- Nuclear Accident Dosimeter
- Comparator Panel

38207013.40

FIGURE E.12. Floor Plan of the 324 Building First Floor
Showing Criticality Alarm and NAD Locations

39207013.41

FIGURE E.13. Floor Plan of the 324 Building Second Floor Showing Criticality Alarm and NAD Locations

FIGURE E.14. Floor Plan of the 324 Building Third Floor
Criticality Alarm and NAD Locations

39207013.38

FIGURE E.15. Floor Plan of the 324 Building Basement Showing Criticality Alarm and NAD Locations

325 BUILDING300 AREA

<u>Dosimeter No.</u>	<u>Location</u>
<u>First Floor</u>	
109	Mounted on the east wall of 325-A inside Room 603, 3 ft 7 in. north of the inside roll-up door from the truck lock, and 6 ft 1 in. above the floor.
124	Mounted on the east wall at the south end in Corridor 200, 1 ft 6 in. north of Corridor 100, and 5 ft 10 in. above the floor. Candle 388 will be replaced with Candle 124 in October 1992.
125	Mounted on the east wall inside the airlock at the east end of Corridor 700, 5 ft south of the north outside door and 4 ft 2 in. above the floor. Candle 389 will be replaced with Candle 125 in October 1992.
191	Mounted on the entry foyer east wall in the main entry corridor, 6 ft 3 in. above the floor, and 23 ft 11 in. north of the inner entry door.
192	Mounted on the west wall of Corridor 600, 1 ft 8 in. south of east door to Room 510, and 6 ft 6 in. above the floor.
193	Mounted on the east wall of Corridor 500, 9 ft 7 in. south of door to Room 528, 6 ft 5 in. above the floor.
194	Mounted on the north wall of Corridor 700, 1 ft 6 in. west of the 300 Corridor, and 6 ft 4 in. above the floor.
<u>Basement</u>	
190	Mounted outside the west wall of the Storage Cage (Room 44), 5 in. south of the cage access gate, near the east stairs, 5 ft 6 in. above the floor.

39207013-37

FIGURE E.16. Floor Plan of the 325 Building First Floor Showing Criticality Alarm and NAD Locations

FIGURE E.17. Floor Plan of the 325 Building Basement Showing Criticality Alarm and NAD Locations

39208076.1

FIGURE E.18. Floor Plan of the 325 Building Second Floor Showing Criticality Alarm Locations

327 BUILDING300 AREA

<u>Dosimeter No.</u>	<u>Location</u>
133	Mounted on the west wall of the main corridor from the change room to the canyon entrance, 12 ft 7 in. south of the door into the canyon, and 5 ft 11 in. above the floor.
134	Mounted on the north wall of canyon in the northeast corner, 7 ft 2 in. west of the east wall, and 6 ft above the floor.
135	Mounted in the airlock off the main (north) receiving dock's west wall, 5 ft 8 in. south of the door, and 5 ft 11 in. above the floor.
136	Mounted on the south wall of old Burst Test Room, 1 ft 9 in. west of the door, and 6 ft above the floor.
154	Mounted on the west wall of the lunch room, 2 ft 10 in. south of the north wall, and 6 ft 3 in. above the floor. Candle 390 will be replaced with Candle 154 in October 1992.

Basement

138	Mounted on the east side of Column B-19 by lower SERF cell, 7 ft 4 in. south, and 10 ft 2 in. east of the stairwell entrance, and 5 ft 7 in. above the floor.
139	Mounted on the north side of Column H-18 in the equipment room, 18 ft 9 in. west of the outside entrance, and 5 ft 4 in. above the floor.

FIGURE E.19. Floor Plans of the 327 Building First Floor and Basement Showing Criticality Alarm and NAD Locations

39208076.4

FIGURE E.20. Floor Plan of the 327 Building Roof Showing Criticality Alarm Locations

**K Critical Radiation Event Alarm
(Part of 325 Building System)**

39208076.2

FIGURE E.21. Floor Plan of the 328 Building First Floor
Showing Criticality Alarm Locations

Critical Radiation Event Alarm
(Part of 325 Building System)

39208076.3

FIGURE E.22. Floor Plan of the 328 Building Second and Third Floors
Showing Criticality Alarm Locations

329 BUILDING

300 AREA

Dosimeter No.

Location

354

Located on the north wall of Room 4D (between the loading dock and Room 14C), 13 ft north of the loading dock door, 4 ft 7 in. west of the east (loading dock) wall, and 6 ft 11 in. above the floor.

Ⓓ Nuclear Accident Dosimeter

39207013.42

FIGURE E.23. Floor Plan of the 329 Building First Floor
Showing the NAD Location

333 BUILDING300 AREA

<u>Dosimeter No.</u>	<u>Location</u>
119	Mounted on the east wall of the weld area, 2 ft north of the north door, and 6 ft above the floor.
126	Mounted on the north wall of the Press Room, 2 ft west of the door to the Chemical Bay, and 6 ft above the floor (blue safety light directly above it).
127	Located on the opposite side of the north wall of the Chemical Bay, 5 ft 6 in. east of the east door, and 5 ft 6 in. above the floor.
128	Located on the opposite side of east wall of the component cleaning section on the west side of corridor, 9 ft from the northeast corner, and 6 ft above the floor.
129	Mounted on the north wall of the Final Assembly Room, 4 ft east of the west door, and 6 ft above the floor.
130	Mounted on the fourth pillar south of the north wall of the Autoclave Area, 6 ft above the floor.
137	Located outside the east wall of Building 333, 2 ft from the northeast corner of the building, and 5 ft 6 in. above the ground (paraffin leaking out of the front edge of the pot).
225	Mounted on the west wall of the Press Room, 3 ft south of the Press Room supervisor's office door, and 6 ft above the floor.
330	Mounted on the west wall of the east corridor, 20 ft from the southeast door at the southeast corner of the building, and 6 ft above the floor.

FIGURE E.24. Floor Plan of the 333 Building Showing Criticality Alarm and NAD Locations

3712 BUILDING300 AREA

<u>Dosimeter No.</u>	<u>Location</u>
303	Mounted on the south wall of the building, 1 ft 6 in. east of the east door, and 5 ft 6 in. above the floor.
305	Mounted on the northeast corner of the building, 1 ft west of the east wall, and 6 ft above the floor.

FIGURE E.25. Floor Plan of the 3712 Building Showing NAD Locations

3716 BUILDING

300 AREA

<u>Dosimeter No.</u>	<u>Location</u>
247	Mounted on the west wall, 4 ft north of the door, and 5 ft above the floor.
250	Mounted on the south wall, 6 ft west of the door, and 6 ft above the floor.

39207013.21

FIGURE E.26. Floor Plan of the 3716 Building Showing Criticality Alarm and NAD Locations

3720 BUILDING300 AREA

<u>Dosimeter No.</u>	<u>Location</u>
104	Mounted on the east wall of the 100 Corridor, 3 ft 2 in. north of the southern corridor entrance Door S-5, and 4 ft 11 in. above the floor.
105	Mounted on the southwest corner of the main entrance alcove outside and south of entrance E-7, 1 ft 2 in. north of the south-side alcove glass, and 4 ft 11 in. above the floor.
205	Mounted on the west wall of the 200 Corridor, 4 ft 11 in. north of the southern corridor entrance Door S-2, and 4 ft 11 in. above the floor.
321	Mounted on the east wall of Room 601, 9 in. north of the entrance Door E-3, and 5 ft 8 in. above the floor.

FIGURE E.27. Floor Plan of the 3720 Building Showing NAD Locations

3730 BUILDING

300 AREA

FIGURE E.28. Floor Plan of the 3730 Building Showing NAD Location

APPENDIX F

400 AREA NAD LOCATIONS

APPENDIX F

400 AREA NAD LOCATIONS

This appendix describes the NAD locations in the 400 Area, by building. The buildings are arranged in numerical (from low to high) and alphabetical order. At least one page is devoted to descriptions of the numbered NADs and the locations. A floor plan of each building displays the NAD locations within the building.

FFTF FACILITIES400 AREA

<u>Dosimeter No.</u>	<u>Bldg. No.</u>	<u>Location</u>
153	405	Mounted on Girder 18 in the Reactor Containment Building (405), 7 ft above the floor. This location is just east of the heavy equipment airlock and approximately 14 ft from the top of the IEM Cell (line of sight).
155	4717	Mounted on the girder immediately adjacent to Room 366 (west side) in the Reactor Service Building (4717), 11 ft above the floor.
156	405	Mounted in Cell 560, 9 ft 6 in. above the floor. It is directly above Panel C1191C (Pressurization and Purge System Panel), approximately 12 ft (line of sight) from the nearest IEM Cell window. Cell 560 is on the 500-ft level of the Reactor Containment Building (405).
157	405	Mounted in Cell 550, between JB 479 and 2D2C, 11 ft (line of sight) from the nearest IEM Cell window and 10 ft 6 in. above the floor. Cell 550 is approximately at the 530-ft level, extending into the 533-ft level from the 520-ft level of the Reactor Containment Building (405).
160		Mounted on the well wall of the high-bay area (Room 916 of 403 Building - Fuel Storage), approximately 7 ft above the floor, and 3 ft north of the door to Room 919 on a vertical structural girder.

39207013.45

FIGURE F.1. Floor Plans of the FFTF Reactor Support Buildings at the 550-ft and 533-ft Levels Showing NAD Locations

FIGURE F.2. Floor Plans of the 405 Reactor Containment Building at the 500-ft and 489-ft Levels Showing NAD Location

39207013.43

FIGURE F.3. Floor Plan of the 403 Building Fuel Storage Facility Ground Floor Showing NAD Location

DISTRIBUTIONNo. of
CopiesNo. of
Copies

2 DOE/Office of Scientific
and Technical Information

15 Pacific Northwest Laboratory

M. R. Peterson
S. R. Reese (10)
Manual Administration
Publishing Coordination
Technical Report Files (2)

ONSITE

2 U.S. Department of Energy
Richland Field Office

D. C. Clark
G. R. Yesberger

END

**DATE
FILMED**

5 / 3 / 93