TECHNICAL PROGRESS REPORT

OCTOBER - DECEMBER 1988

For:

**U.S. Department of Energy
Pittsburgh Energy Technology Center**

Under:

**DOE Contract No. DE-AC22-87PC79654
Development of a Retrofit Coal Combustor for
Industrial Applications (Phase I-A)**

By:

**MANUFACTURING AND TECHNOLOGY CONVERSION
INTERNATIONAL, INC.**
P.O. Box 21, Columbia, Maryland 21045

March 1989

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

PREFACE

A detailed description of the background, technology and application for the development of a retrofit coal combustor for industrial applications was provided in the first quarterly report for the period January 1987 - March 1987. That material is omitted from this report. In June of 1988, DOE Contract No. DE-AC22-87PC79654 was modified with the addition of a new task, as a Phase IA, to bridge the gap between Phase I and II of the program. The descriptions of these tasks are now included in Section 1.1. Phase IA was initiated on June 7, 1988. This report covers the period October 3, 1988 through December 25, 1988. It also includes Section 1.2, Task Descriptions, that provides the task structure for the Phase IA of the development effort.

During this reporting period, the integrated system was completed. The remaining ancillary components were fabricated and incorporated into the unit. The subsystem and integrated system were tested in order to establish initial combustor performance.

Testing with dry coal and coal slurry was performed, permitting injector position optimization and combustion performance improvement. It also provides a baseline for test comparison. This preliminary testing also served to familiarize the operators with the unit.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

TABLE OF CONTENTS

	<u>Page</u>
1.0 PROGRAM DESCRIPTION AND WORK STATUS	1
1.1 PROGRAM DESCRIPTION	1
1.2 TASK DESCRIPTIONS	3
1.2.1 Task 1: Optimization of the Laboratory-Scale Combustor	3
1.2.2 Task 2 (Modified): Integrated Small Industrial-Scale Pulse Combustor System (modified task)	3
1.3 PHASE 1A, INTEGRATED SMALL INDUSTRIAL- SCALE COMBUSTOR SYSTEM DEVELOPMENT	4
1.3.1 Task 1 (Phase 1A): Fabrication of the Integrated Small Industrial-Scale Combustor System	4
1.3.2 Task 2 (Phase 1A): Technical and Laboratory-Scale Support	6
1.3.3 Task 3 (Phase 1A): Scale-Up Pilot Unit Design	6
1.4 STATUS	7
2.0 TECHNICAL DISCUSSION OF WORK COMPLETED DURING THE REPORTING PERIOD	9
2.1 INTEGRATED SMALL INDUSTRIAL-SCALE COMBUSTOR SYSTEM	9
2.2 SYSTEM TESTING	16
3.0 PLANNED ACTIVITY FOR THE NEXT PERIOD	26

LIST OF FIGURES

	<u>Page</u>
FIGURE 1 PROGRAM LOGIC FOR THE DEVELOPMENT OF AN ADVANCED PULSED-COAL COMBUSTOR FOR RETROFIT APPLICATIONS	2
FIGURE 2 INDUSTRIAL SYSTEM	10
FIGURE 3 INTAKE PLENUM	11
FIGURE 4 AEROVALVES	13
FIGURE 5 THRUST AUGMENTER	15
FIGURE 6 SLURRY INJECTOR	17
FIGURE 7 SLURRY INJECTOR LOCATION	21
FIGURE 8 TIP OF IMPROVED SLURRY INJECTOR	22
FIGURE 9 ADIABATIC FLAME TEMPERATURES OF COAL AND GAS	25

SECTION 1.0

PROGRAM DESCRIPTION AND WORK STATUS

1.1 PROGRAM DESCRIPTION

The objective of Phase I of the program for the development of a retrofit pulse coal combustor for industrial applications was to design, fabricate, test and evaluate advanced chamber designs at the laboratory-scale utilizing several fuels (Task 1). The activities were structured to provide design criteria for scaling up to the pilot-scale level for the demonstration of a pulse combustor fired with coal-water mixtures for industrial boiler and process heater retrofit applications. The program logic is depicted in Figure 1.

The design data and information acquired during Task 1 of the initial phase was to develop scale-up design criteria for scaling the laboratory-scale design to pilot-scale including interface requirements for the field demonstration. The scale-up pilot unit design was to be sufficiently developed to allow fabrication of the unit for testing in the existing test facility upon DOE exercising its option for the follow-on activities of this program. These follow-on activities included the fabrication, test, and engineering evaluation of the pilot-scale combustor as well as technical and laboratory test support activities for reducing the technical risks and costs of development at the pilot-scale. Based on the information, test, data and technical support activities, a retrofit combustor system was to be designed for field demonstration as shown on the left in Figure 1.

An additional effort - Phase IA - was added to the contract by modification A005. This modification substitutes the following for the original Task 2 of Phase I and added a Phase IA consisting of three technical tasks which are also subsequently described herein.

FIGURE 1: PROGRAM LOGIC FOR DEVELOPMENT OF A PULSE COAL COMBUSTOR FOR RETROFIT APPLICATIONS

1.2 TASK DESCRIPTIONS

1.2.1 TASK 1: OPTIMIZATION OF THE LABORATORY-SCALE COMBUSTOR

The specific objectives of this task are to optimize the chamber design of the feasibility units developed under Contract No. DE-AC22-83PC60419 for optimized performance with coal and coal-water slurry fuels and to reduce performance sensitivity to variations in fuel specifications.

To meet these objectives, two advanced combustion chamber configurations will be designed and fabricated at the laboratory-scale (1 - 2 MMBtu/hr) size. Design options will include both bare metal and refractory-lined units to permit both air-cooled and adiabatic operation. These advanced designs will be fabricated and then tested to evaluate the performance with respect to the following parameters:

- Combustion intensity and heat release rates,
- Staging capability,
- Dry sulfur capture and ash rejection performance,
- Carbon burnout efficiency,
- NO_x emissions performance, and
- Sensitivity to changes in fuel specifications.

Refractory-lined combustor tests will be conducted employing both the feasibility unit chamber design and one of the advanced chamber designs selected on the basis of the evaluation tests.

1.2.2 TASK 2 (MODIFIED TASK): INTEGRATED SMALL INDUSTRIAL-SCALE PULSE COMBUSTOR SYSTEM

Upon accrual of sufficient data from Task 1, Subtasks B and D, the Contractor shall develop the design for an integrated pulse combustor at the small industrial scale. The unit shall be equipped with a refractory-lined, cyclonic slag separator with a water-cooled slag collection vessel. The

design shall be in sufficient detail to allow fabrication and shall take into consideration all the requirements to interface with the boiler simulator to be used in testing under Phase IA.

1.3 PHASE 1A, INTEGRATED SMALL INDUSTRIAL- SCALE COMBUSTOR SYSTEM DEVELOPMENT

The following tasks were added by modification to the original contract and are comprised of four tasks, including a management and reporting task (Task 4). That task is not included in the following discussion.

1.3.1 TASK 1 (PHASE 1A): FABRICATION OF THE INTEGRATED SMALL INDUSTRIAL-SCALE COMBUSTOR SYSTEM

A development and test activity which is aimed at the demonstration of an integrated pulse coal combustor system fired with coal-water mixture and dry ultrafine coal for small industrial boiler and process heater applications shall be undertaken. In conducting the demonstration, the Contractor shall undertake the following two subtasks:

A. SUBTASK 1.1: INTEGRATED SMALL INDUSTRIAL- SCALE COMBUSTOR SYSTEM FABRICATION

The integrated small industrial-scale combustor system design, developed under Phase I, shall be fabricated and interfaced with a boiler simulator facility and prepared for conducting the testing and engineering evaluations described below under Subtask 1.2.

In fabricating the integrated small industrial-scale combustor system and interfacing it with the test facility, all the necessary materials, equipment, instrumentation and supplies for all facility modifications for fuel and air supplies and sound muffling provisions shall be procured.

B. SUBTASK 1.2: TESTING AND ENGINEERING EVALUATION

The Contractor shall initially conduct tests of the integrated small industrial-scale pulse combustor system with natural gas. This shall be followed by tests that employ coal-water mixtures and dry ultrafine coal.

In implementing this task, the Contractor shall prepare a test plan (for each test fuel) detailing the combustor design, facility modifications and the planned sequence, procedures and test data acquisition for conducting the test activities. The test plan shall be supplied to the DOE technical program monitor for review and approval.

Test activities shall include preliminary check-out runs to establish stable performance and overall facility readiness. Mass and energy balance calculations shall also be undertaken by the Contractor to develop procedures and methods suitable for reliable determination of the combustion efficiency.

During each test run, the Contractor shall periodically record the following measurements:

- Fuel mass flow rate and combustor pressure wave intensity
- Primary and secondary air flow rates (time average) and temperatures
- Unburned carbon loss
- Flue gas analysis (O_2 , CO_2 , CO , SO_x , NO_x , etc.)

In addition, the following test data will be taken on an as-required basis:

- Flue gas analysis of the pulsating combustor's exit gas stream using analytical equipment to determine the level of unburned hydrocarbons, if any
- Primary and secondary air flow rate vs. time
- Pressure measurements (locations determined during testing)
- Chemical and size analyses of fuel feedstock, slag and fly ash

- Heat absorbed by the furnace, flue gas flow rate, and furnace exit temperature

The Contractor shall reduce the test data and analyze and correlate the reduced data as a function of the combustor load. The data shall be compared with the combustor data obtained in Phase I to assess the effect of system integration on the combustor performance.

The Contractor shall also employ the test results to undertake an assessment of the applications to small industrial boilers and process heaters. In addition, the Contractor shall document all the operating experience including maintenance-related experiences and shall employ such information in the assessment of the commercial application of the combustor technology.

1.3.2 TASK 2 (PHASE 1A): TECHNICAL AND LABORATORY-SCALE SUPPORT

In support of the integrated system development and demonstration, defined in 1.3.1 above, the Contractor shall employ an empirical computer code for combustor performance and scale-up analysis developed in Phase I and shall employ supplemental component tests to address technical issues resulting from the integrated small industrial-scale system development work.

1.3.3 TASK 3 (PHASE 1A): SCALE- UP PILOT UNIT DESIGN

The Contractor shall develop design scale-up criteria for scaling the small industrial-scale design to pilot-scale. These criteria shall include consideration of the effect of scale-up on combustor operating frequency, firing intensity (in MMBtu/hr cu.ft.), and the intensity of pressure fluctuation with increased firing rate. The scale-up design shall also take into consideration all the interface requirements of the pilot-scale development activities at the subcontractor test site.

The combustor scale-up design developed under this task shall be in sufficient detail to allow fabrication should DOE exercise its option to proceed with Phase II.

1.4 STATUS

In the last quarter reporting period, the 3.5 - 5.0 MMBtu/hr tandem-fired pulse combustion unit was designed and fabricated. The configuration is of two combustion chambers cast in a single monolith, tailpipes cast separately with annular air preheating capability, and a cyclonic decoupler. Design analysis and evaluations were performed to optimize the system with respect to minimizing heat losses, size, and cost. Heat losses from the combustor and decoupler walls are predicted to be approximately 3 percent. The final designs for the ancillary items (slag quench, tertiary air addition, scrubber and sampling system) were completed and fabrication and installation initiated. A Cleaver-Brooks 150 hp-4 pass boiler was delivered and installed and modifications for interfacing with the retrofit pulse combustor unit completed. A below-ground slag collection pit was excavated to permit direct in-line coupling of the combustor to the boiler and to reduce head-room requirements. The pit is 30-inches deep and lined with waterproof and fireproof siding.

Fabrication and installation of ancillary components were completed during this reporting period. The intake plenum, aerovalves, scrubber, thrust augments, slurry injector, and instrumentation were added to the system. Testing on the subsystems and integrated system were made to establish initial combustor performance.

Slurry fuel testing was performed to optimize injector positioning and to improve combustion performance by the formation of a slag coating on the combustor wall to provide improved heat radiation and increased coal residence time. Dry coal tests were performed to provide a baseline for test comparison.

The preliminary testing performed during this reporting period emphasized defining qualitative performance and range of operating stoichiometry. It also served to familiarize the operators with the unit and its control and operation.

SECTION 2.0
TECHNICAL DISCUSSION OF WORK COMPLETED
DURING THE REPORTING PERIOD

**2.1 INTEGRATED SMALL INDUSTRIAL-
SCALE COMBUSTOR SYSTEM**

FABRICATION

Fabrication and installation of ancillary components were completed during the reporting period. The intake plenum and control panel were fabricated and installed as well as the components supplying the air, natural gas, and ignition to the combustors. A UV flame sensor and burner control system were also installed and checked out. Figure 2 shows a picture of the installed system.

INTAKE PLENUM

The intake plenum, as seen in Figure 3, was constructed out of carbon steel plate and welded to the top of the combustors. The intake plenum serves three purposes: first, it supplies the combustors with a pressure-controllable air source. Second, it muffles the noise generated from the combustors; and third, it prevents any coal blow-back from escaping into the laboratory. The volume of the intake plenum must also be sufficient (approximately 10 to 30 times the chamber volume) to eliminate any coupling or resonating in the intake plenum. The volume of the intake plenum is approximately 17.5 ft³ or 25 times the volume of each chamber. By coupling the two chambers through the aerovalve to promote antiphase operation, the volume needed to avoid resonating in the intake plenum is reduced.

FIGURE 2: INDUSTRIAL SYSTEM

FIGURE 3: INTAKE PLENUM

AEROVALVES

The aerovalves were installed without inserts to allow for the installation of the natural gas and air lines. The valves were made 8 inches long with a 3.5 inches internal diameter. Three different inserts were designed to be used in the tuning tests. These inserts, as seen in Figure 4, have minimum diameters of 1.5 inches, 2 inches, and 2.5 inches. They will be used and modified to tune the units and adjust the air flows. It is possible that the firing rate of the unit can be increased or decreased to some degree simply by changing the insert. The smaller the diameter, the less air the combustor will induct for the same peak-to-peak pressures.

For gas-tuning purposes, four natural gas injectors are evenly spaced around the base of the aerovalves. This will provide a uniform gas distribution with a minimum of pressure drop. Coal (both dry and slurry) will be injected axially through the aerovalves.

SCRUBBER

Fabrication and testing of the scrubber was completed and installed in the system. The counter flow scrubber will recirculate 40 GPM of water with a maximum flue gas flow of 1000 CFM. Eight spray nozzles will evenly distribute the spray across the scrubber. The flue gas will enter the scrubber at approximately 300°F and will have few particulates. The gas will exit the scrubber below 200°F and will be exhausted to the atmosphere through standard ducting.

TESTING

The unit was cured for 2 days by firing a 300,000 Btu/hr flame into the decoupler and igniting the pilots in the combustion chamber. The units were also allowed to air cure for over one month before any heat was applied to them.

FIGURE 4: AEROVALVES

Once the units were cured they were fired for a short time (less than 1 minute). The initial firing was aimed at checking the reliability of the ignitor and the reliability of the pilot flame in igniting the main flame. The only parameter monitored was the chamber temperature in order to heat the chamber slowly since the curing process had only proceeded to 400°F. The initial firing did not utilize the aerovalve inserts. The thrust augments was not used since it was only desired to test one chamber at a time.

Fabrication of the thrust augments and aerovalve inserts was completed. The exhaust pipe and exhaust ducting were also installed with the scrubber placed in-line. After preliminary tuning tests were conducted, the slurry injectors were fabricated and installed. A gas sampling system was also installed to collect gas samples after the boiler.

THRUST AUGMENTER

The thrust augments, as seen in Figure 5, was fabricated from a straight section of three-inch pipe, two three-inch elbows, and two conical sections. The dimensions of the thrust augments are critical to its performance. If the volume of the thrust augments is excessive, the response to the supercharging effect of each combustor will be diminished due to the capacitances associated with the compressibility of the gases. If the diameter of the augments is too small, the impedance seen by the gases will be excessive. The size and shape of the conical section is also a factor, determining how much air the augments will induce. Although these factors are important, the overall performance of the coupled combustors will be dependent upon additional factors not directly related to the thrust augments design.

SLURRY INJECTORS

The slurry injectors fabricated for these tests are conceptually similar to the injectors used in Phase 1 of this project. The injectors incorporated an annular design with an outer water jacket and an inner annulus for

FIGURE 5: THRUST AUGMENTER

conveying air to atomize the slurry. They differed from the previous injector designs only by the elimination of 90-degree bends to allow injection down the straight aerovalves (Figure 6). They consist of four concentric tubes with the diameters of 3/4, 1/2, 3/8 and 1/4 inches. The slurry passes through the inner 1/4-inch tube and atomization air passes through the 3/8-inch tube. The two larger tubes are used to contain the flow of cooling water through the injector.

INSTRUMENTATION

Instrumentation added to the system included a water-flow totalizer to monitor the steaming rate of the boiler and three tungsten-rhenium thermocouples to monitor the high-temperature internal environment of the combustor. Thermocouples were placed in each chamber and a single thermocouple was placed in the decoupler.

2.2 SYSTEM TESTING

Initial short duration firing tests were performed on subsystems to assess and check out basic operation of flame ignitors, sensors, etc., prior to initial tuning tests on the integrated system. System tests were conducted initially with 2.5-inch diameter aerovalve inserts. Although low-boost pressures were observed for both chambers (1/2-inch water), the units achieved strong peak pressure (up to 7.5 psi) fluctuations. The length of the aerovalve was varied while the unit was operated with the air plenum open to atmospheric conditions. The optimum length was found to be at the minimum insert length, although the unit exhibited a relatively low sensitivity to insert length near the optimum position. Several inserts of varying throat diameter were tested. It was found that a 2-inch throat diameter provided the optimum balance between strong pressure fluctuations and minimum blow-back from the aerovalve. Tests using the 1.5-inch insert indicated that the inlet air flow was excessively restricted. Tests using the 2- and 2.5-inch inserts were conducted under positive pressure conditions (5-inch pressure in the intake plenum). The performance distinctly improved as the plenum pressure was increased.

FIGURE 6: SLURRY INJECTOR

The tandem combustors were tested at a maximum firing rate of 2 MMBtu/hr/chamber. The maximum firing rate achieved was limited only due to the maximum available gas supply pressure. Thus, the unit appears to be capable of operating at 5 MMBtu/hr on slurry fuels.

COAL TESTS

Initial slurry fuels testing was undertaken during this reporting period. Two tests were conducted with slurry fuels. The purpose of these tests was twofold. First, basic injector position needed to be optimized for proper combustion of the slurries. And second, the combustors and decoupler had to be heated to slagging temperatures to allow formation of a continuous slag coating on the combustor walls. The effect of slag coating on improving combustion performance has been discussed in earlier Phase I reporting.

During testing in Phase I operation, it was discovered that better combustion efficiencies were achieved once the combustor and decoupler walls were coated with slag. The reasoning behind this was twofold. First, the slag coated walls would radiate heat more intensely than refractory walls and second, the larger coal particles impinge the slag coated walls thereby increasing their residence time and allowing more complete combustion. Therefore, gathering of combustion performance data will be made only after sufficient shakedown testing has been conducted to ensure good slag coverage of chamber walls.

It was also noted in these tests that the temperature in the decoupler rose to over 3400°F which is near the melting point of the refractory. In prior Phase I tests, high heat losses limited the temperatures achieved within the combustor. In the new combustors, heat losses have been reduced. Therefore, it is evident that fuel or air staging will be necessary to control combustion temperature over a reasonable range.

The initial slurry injection location tested was approximately 1/2 inches below the minimum throat diameter of the aerovalve insert. It was thought this would allow the maximum drying time for the slurry and any blow-back out

of the aerovalve would be fed through the thrust augments into the other chamber. However, injection of the slurry close to the minimum diameter resulted in a build-up of caked slurry on the insert wall. Also, slurry adhered to the thrust augments. A deeper injector position is anticipated to resolve these problems.

Eight coal tests were conducted during this reporting period, six on slurry and two on dry coal. The goal of this series of tests was to determine the optimum injection method and location and to serve as preliminary shakedown tests for combustor operation on slurry fuels. Three different injection locations and two different injectors were tested with slurry. Dry coal was tested at a single injection location.

The two different slurries tested in MTCI's retrofit tandem pulse combustors were UE3-205 slurry provided by Energy International and an older OXCE SplashDam slurry used in MTCI's initial pulse combustion projects. The high ash fusion point of the UE3-205 slurry (2857°F) is somewhat atypical of slurry fuels anticipated for commercial use in the combustor. For this reason, additional coals were tested to compare their slagging characteristics in the tandem unit. During preliminary tests, MTCI's combustors were capable of slagging both coals equally well; however, slag collection efficiency differed for each coal.

As anticipated, slurry injection proved to be a critical aspect of the combustor operation. Substantial heat must be released in the chamber to evaporate the water, devolatilize the coal, combust the char, and drive the pulsations. A high level of carbon conversion must therefore be achieved before the coal leaves the decoupler to allow efficient slagging and collection of the ash. The intensity of the pulsation as well as the oxygen content in the flue gas will affect the rate of carbon conversion and therefore the effectiveness of the ash collection.

To maximize the available time for water evaporation and coal devolatilization, the initial slurry injection location was positioned 1/2-inch below the throat of the aerovalve. During the initial two tests, undried slurry coated the lower portions of the aerovalve, finally forcing the unit to be shut down. The injection location was lowered 3 inches; however, deposition in the aerovalve was still observed. Finally, the injectors were lowered another 3 inches. The further lowering of the injectors enabled the slurry to avoid contact with the aerovalve walls. Although the further lowering of the injectors improved injector performance, problems with injector plugging arose believed to be due to an increase in radiant heat from the combustor. Figure 7 shows the injection and slurry buildup locations.

A second injector design, Figure 8, was utilized to decrease the spray angle and allow an increase in injector height. As seen in Figure 2, the spray nozzles differ in injection by passing the slurry through the annulus of two tubes, spraying slurry through orifices into the center tube where it is picked up by air and injected into the combustors. The new injector sprays the slurry into the air line where it is reatomized instead of deflecting the air into the slurry flow. Since the air stream is never deflected, the spray angle is considerably smaller. The improved injector design resulted in successful injection being achieved at the middle injection point.

Dry coal was used for two tests to provide baseline data for comparing combustor performance on slurry. These tests were followed by several slurry runs.

TEST RESULTS

During the preliminary testing, the primary emphasis was on monitoring the qualitative performance of the combustor, familiarizing operators with control of the unit, and determining the operating stoichiometric range of the combustor. In addition, the decoupler was inspected after each test to determine slag build-up.

FIGURE 7: SLURRY INJECTOR LOCATION

FIGURE 8: TIP OF IMPROVED SLURRY INJECTOR

Determining the range of combustor performance is essential to the analysis of combustor characteristics. It is desirable to find an operating condition which provides an optimum balance between NO_x reduction, sulfur capture, and ash rejection. However, in some cases tradeoffs must be made due to the competitive nature of these phenomena. Two important and interrelated variables are stoichiometry and temperature. High temperatures are needed to slag the ash; however, this may result in increased NO_x production. Operating under substoichiometric conditions will lower the NO_x emissions although make it more difficult to obtain good ash rejection.

The initial strategy was to run the combustors substoichiometric to reduce the NO_x formation. Temperatures would be maintained such that the ash would slag in the decoupler. Tertiary air would be added to the flue gas to complete combustion.

Observations indicated that efficient slag removal was not achieved under substoichiometric conditions. This may be due to the high ash fusion temperature of the slurry tested. It is anticipated that testing under superstoichiometric conditions will provide for effective slag removal.

Difficulty in slagging the ash is twofold. First, significant carbon levels in the ash will inhibit the slag from depositing on the combustor walls. Running under substoichiometric conditions reduces the rate of carbon conversion, slowing the slag formation. Under superstoichiometric conditions the carbon burns leaving the slag to deposit on the decoupler wall. This problem is complicated by the high ash fusion point of the slurry.

Preliminary estimates of the ash rejection efficiencies are between 30 and 50 percent under substoichiometric conditions. This was based on a cursory inspection of decoupler, chambers, and ash collected in the boiler and scrubber.

THEORETICAL VALUES

Adiabatic flame temperatures and flue gas composition were calculated for operation of the combustor on slurry at various substoichiometries. Data was collected from 70 to 99 percent theoretical air. Data was also collected for operation with support gas at 10 and 20 percent levels. Due to the moisture in the slurry, flame temperatures ran hotter with support gas than without (Figure 9). As seen, the maximum theoretical temperature achievable on slurry is 3506°F. With support gas the theoretical temperature reaches 3600°F. It can also be seen from this data that while running with more than 74 percent stoichiometric air, the adiabatic flame temperature is sufficient to slag the ash. For coal with lower ash fusion temperatures this value is even lower. Since the indicated temperature should be sufficient to slag the ash, other factors such as carbon in the ash appear to be contributing to the observed effect.

COAL FUEL ANALYSIS

The proximate and ultimate analysis of the coal fuel used in this test can be seen in Appendix 1. The coal contains 36.22 percent volatiles, 6.32 percent ash, and 0.7 percent sulfur. The heating value of the coal is 14225 Btu/lb. As seen in Appendix 1, the ash has a high ash melting point. The T-250 temperature of the ash is 2857°F. This unusually high melting point makes operating under slagging conditions more difficult. It is believed that the ash characteristics of this coal are not representative of a broad range of coal types anticipated for use in the combustor. Thus, an attempt will be made to procure and test coal slurries with lower ash fusion points.

FIGURE 9: ADIABATIC FLAME TEMPERATURES OF COAL AND GAS

SECTION 3.0

PLANNED ACTIVITY FOR THE NEXT PERIOD

The work schedule for the next quarter will include the identification and optimization of important performance variables. The goal is to operate the unit without support gas. New slurry injectors will be tested in the combustor system. These injectors will include in-house and outside manufacturer designs.

Slurry testing will be performed on the unit. Tests will focus on tuning the unit so that natural gas support will not be necessary. Preliminary check-out runs to establish stable performance and overall facility readiness will be made. Mass and energy balance calculations, experimental measurements of key parameters, and preliminary data analyses will be made during these experiments as required.

Observations of unit performance will be recorded and evaluated. Action, if required, will be taken to improve unit operation and performance.

APPENDIX 1

TITLE: cwfid SAMPLE IDENTIFICATION NO: UE3-205-CWF-F NO: 205

SAMPLE DESCRIPTION: Std. grind slurry from high ash UE3 for MTCI

PARENT COAL ID: UE3-206-WRM-E
BED NAME: Upper Elkhorn #3
BED NO: 151
LOCAL NAME: Taggart Seam
MINING COMPANY: Westmoreland Coal Co.
MINE NAME: Wentz #1
WASH PLANT: Wentz
STATE: Virginia
COUNTY: Wise

PROXIMATE ANALYSIS:
Moisture ---%
Volatile Matter 36.22%
Fixed Carbon 57.46%
Ash 6.32%
Sulfur 0.70%
Btu/lb 14225
Btu/lb (as received) 8825*

ASH CHEMISTRY:

SiO ₂	50.63%
Al ₂ O ₃	32.65%
TiO ₂	1.45%
Fe ₂ O ₃	6.06%
CaO	2.36%
MgO	0.88%
K ₂ O	2.28%
Na ₂ O	0.63%
SO ₃	2.20%
P ₂ O ₅	0.41%
SrO	0.28%
BaO	0.17%
Mn ₃ O ₄	0.00%

ULTIMATE ANALYSIS:
Carbon 81.23%
Hydrogen 4.86%
Nitrogen 1.39%

ASH FUSION: Reducing
Initial 2570°F
Softening +2570°F
Fluid +2700°F

FREE-SWELLING INDEX: N/A

HARDGROVE GRINDABILITY: N/A

FORMS OF SULFUR:
Pyritic 0.14%
Sulfate 0.01%
Organic (diff.) 0.55%

BASE ACID RATIO: 0.14
T-250 TEMPERATURE: 2857°F

COAL-WATER FUEL ANALYSIS

% Solids: 62.04	Viscosity: 247 cps @ 100/sec, 70°F
Density: 1.174	
pH: 6.8	Particle Size Analysis
% Sulfur: 0.43*	-----
% Ash: 4.32*	Wt.% <100 mesh: 98.85
	Mean Particle Size: 31.8 μm

*Based on weight of coal in slurry

FROM: OXCE FUEL COMPANY	AMOUNT: 600 gallons	DATE: _____
TO: MTCI		
Tecogen		
EI		

END

DATE
FILMED
5/12/93