2)

A. F. MEYER AND ASSOCIATES, INC.

ENVIRONMENTAL, NOISE, AND OCCUPATIONAL HEALTH CONSULTANTS

DOE/ET/13650-2

DISCLAIMER

This book was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

REVIEW OF THE ORNL ENGINEERING EVALUATION
OF IITRI PROJECT ON DESIGN, ENGINEERING,
AND EVALUATION OF REFRACTORY LINERS
FOR SLAGGING GASIFIERS

JANUARY 1981

MASTER

Prepared for
Office of Assistant Secretary for Fossil Energy
U. S. Department of Energy
Under
Contract DE-AM01-80ET-13650.002

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

1317 VINCENT PLACE McLEAN, VIRGINIA 22101 (703) 734-9093

1102 DECK BUILDING, SUITE 100, LEBANON, OHIO 44033

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

REVIEW OF THE ORNL ENGINEERING EVALUATION
OF IITRI PROJECT ON DESIGN, ENGINEERING,
AND EVALUATION OF REFRACTORY LINERS
FOR SLAGGING GASIFIERS

by

Timothy Hurley

January 1981

Prepared by

A. F. Meyer and Associates, Inc.

1317 Vincent Place

McLean, Virginia 22101

Under

DOE Contract DE-AM01-80ET-13650.002

NOTICE

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Department of Energy, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights.

DISTRIBUTION

DOE/OPTA - 5

DOE/TIC - 2

AFMA - 5

Contents

	Page
Abstract.	1
Project Description	2
Review Summary.	3
Schedule Summary.	3
Specific Review Findings.	3

ABSTRACT

This report is a brief review of the ORNL Engineering Evaluation of IITRI Project on Design, Engineering and Evaluation of Refractory Liners for Slagging Gasifiers, and is limited to safety and hazard analysis. The major finding is that the existing project cannot provide a safe operating environment chiefly due to inadequate documentation and safety and hazard analysis.

PROJECT DESCRIPTION

This report is written in response to the request of John Abrahams to review the adequacy of the safety analysis and documentation of the ORNL Design, Engineering and Evaluation of Refractory Liners for Slagging Gasifiers. The review was initiated in October 1980, using AFMA, Inc. staff resources under DOE contract.

1.0 Review Summary

The review of the ORNL Engineering Evaluation IITRI Project on Design, Engineering and Evaluation of Refractory Liners for Slagging Gasifiers, while brief and limited to safety and hazard analysis, indicates that the existing project cannot provide a safe operating environment. The major findings and recommended actions are:

1. The project is inadequately documented through design and publications to achieve operating safety at a known hazard level.
2. No safety or hazard analyses have been performed except for FMEA's. Failures do not equate to hazards. A hazard can exist without a failure and failures can occur without hazards.
3. The nature of this project is such that particular emphasis should be placed on performing safety and hazard analyses now in order to achieve net cost reductions should the technology be applied to subsequent facilities.

2.0 Schedule Summary

A review of the schedules indicates that little or no time is available for safety and hazard analysis. The schedule should be reaccomplished to provide for SARS.

3.0 Specific Review Findings

Technical findings by ORNL adequately address the specific problems noted. Consequently, only general comments relating to safety and hazards are provided. These are:

1. This document addresses safety and health by definition of objectives (pg.1) but relies excessively on Failure Mode and Effects Analysis. Hazards are not synonymous with failures. A hazard can exist whether or not a failure occurs. As a result the primary stated purpose of this study to answer the question "Is it safe?" is left unresolved.

2. Additional work on safety and hazard analysis is acknowledged as required by UCC-ND but the cost findings in the document do not appear to have incorporated the cost of safety analysis.
3. The document does not adequately address hazards and safety. Even though most of the requirements for additional technical analysis are implicitly or explicitly related to hazards and safety, they are addressed only from a technical point of view.
4. Additional work on hazards and safety is justified particularly since this project is for design, engineering and evaluation. Additional efforts on hazards and safety at this time could result in a net reduction of cost associated with SARS since these efforts would not need to be reaccomplished under subsequent projects using this technology. The results of any safety related findings could be incorporated by reference into subsequent projects.
5. Design and reporting procedures in use by IITRI are not adequate to anticipate problems or to detect when variances are occurring which may result in problems. No lead time is provided by existing procedures for establishing safety procedures. Consequently, a SAR should be done now to establish a hazard anticipation program by which safety can be achieved through controls on mitigation of hazards. This possibly results from the implied presumption of the program that only failures are hazards which can result in safety concerns. Operating hazards which exist without failure or faults of equipment need to be addressed.
6. Significantly, ORNL's engineering evaluation highlights a number of safety concerns. These need to be resolved as quickly as possible.