A REVIEW OF OCCUPATIONAL SAFETY AND HEALTH
ISSUES RELEVANT TO THE ENVIRONMENTAL
RESTORATION PROGRAM: SELECTED CASE
HISTORIES AND ASSOCIATED ISSUES

A. M. Lesperance
M. R. Siegel
M. D. McKinney

October 1992

Prepared for
the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830

Pacific Northwest Laboratory
Richland, Washington 99352

MASTER

EB

SUMMARY

This report describes a study conducted by Pacific Northwest Laboratory (PNL) to determine the impact of occupational safety and health (OSH) issues on the environmental restoration process at U.S. Department of Energy sites. PNL selected three remediation projects to study: 1) the 618-9 Burial Ground Expedited Removal Action at the Hanford Site, 2) the Chemical Consolidation Interim Response Action at the Weldon Spring Site, 3) and the 200 West Area Carbon Tetrachloride Expedited Removal Action and VOC-Arid Integration Demonstration at the Hanford Site. The first two case studies involve sites where a remediation activity has been complete. The third case study involves a remediation activity in its early stages of development. This study identifies OSH issues related to actual cleanup, time, documentation, training, and technology development. These issues need to be considered by DOE before making long-term planning efforts. Section 4.0 of this report describes recommendations for addressing these issues.

ACKNOWLEDGMENTS

The authors acknowledge the following individuals who contributed to this project: Wayne Johnson, Mike Hagood, Jil Frain, and Kim Koegler from Westinghouse Hanford Company; Tom Brouns and George Last from Pacific Northwest Laboratory; Dave Hixson and Robert Owens from Jacobs Engineering Group Inc.; and employees from MK-Ferguson and Dames and Moore at the Weldon Spring Site.

GLOSSARY

AEC	Atomic Energy Commission
ALARA	as low as reasonably achievable
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
DOE	U.S. Department of Energy
EPA	U.S. Environmental Protection Agency
ER	Environmental Restoration
ERA	Expedited Response Action
ERMC	Environmental Restoration Management Contractor
ES&H	environment, safety, and health
GAC	granulated activated carbon
GOCO	government-owned, contractor operated
HASP	Health and Safety Plan
HEPA	high-efficiency particulate air
HWOP	Hazardous Waste Operations Permit
IRA	Interim Response Action
IRLG	Interagency Regulatory Liaison Group
MIBK	methyl isobutyl ketone
MOU	Memorandum of Understanding
NCP	National Contingency Plan
NIOSH	National Institute for Occupational Safety and Health
NPL	National Priorities List
NRC	U.S. Nuclear Regulatory Commission
OSH	occupational safety and health
OSHA	Occupational Safety and Health Administration

PMC	Project Management Contractor
PNL	Pacific Northwest Laboratory
RCRA	Resource Conservation and Recovery Act
RI/FS	Remedial Investigation/Feasibility Study
SARA	Superfund Amendment and Reauthorization Act
TSCA	Toxic Substances Control Act
VOC	Volatile Organic Compound
WHC	Westinghouse Hanford Company
WSSRAP	Weldon Spring Site Remedial Action Project
WSCP	Weldon Spring Chemical Plant

CONTENTS

SUMMARY	iii
ACKNOWLEDGMENT	v
GLOSSARY	vii
1.0 INTRODUCTION	1.1
1.1 PURPOSE AND APPROCH	1.2
2.0 OVERVIEW OF THE REGULATORY FRAMEWORK	2.1
2.1 FEDERAL IMPLEMENTATION OF THE OCCUPATIONAL SAFETY AND HEALTH ACT	2.1
2.1.1 Specific DOE Regulations and Proposed Regulations . . .	2.2
2.1.2 DOE Directives, Notices and Orders	2.3
2.1.3 Relationship of OSH Act to Environmental Laws and Regulations	2.7
3.0 SELECTED CASE STUDIES AND ASSOCIATED OCCUPATIONAL SAFETY AND HEALTH ISSUES	3.1
3.1 CASE STUDY #1 - HANFORD SITE 618-9 BURIAL GROUND EXPEDITED REMOVAL ACTION	3.1
3.1.1 Site Description and Background	3.1
3.1.2 Occupational Safety and Health Activities	3.5
3.1.3 Occupational Safety and Health Issues	3.6
3.2 CASE STUDY #2 - WELDON SPRING CHEMICAL CONSOLIDATION ACTIVITY INTERIM RESPONSE ACTION	3.8
3.2.1 Site Description and Background	3.8
3.2.2 Occupational Safety and Health Activities	3.11
3.2.3 Occupational Safety and Health Issues	3.12
3.3 CASE STUDY #3 - HANFORD'S 200 WEST AREA CARBON TETRACHLORIDE EXPEDITED REMOVAL ACTION AND VOC-ARID INTEGRATED DEMONSTRATION	3.14
3.3.1 Site Description and Background	3.14

3.3.2 Occupational Safety and Health Activities	3.18
3.3.3 Occupational Safety and Health Issues	3.19
4.0 DISCUSSION OF FINDINGS AND RECOMMENDATIONS	4.1
5.0 REFERENCES	5.1
APPENDIX A - QUESTIONNAIRE	A.1

FIGURES

2.1 Interrelationship Between OSH Issues and the CERCLA Cleanup Process	2.9
3.1 Hanford Site 618-9 Burial Ground	3.3
3.2 Weldon Spring Chemical Plant Site	3.10
3.3 Hanford's 200 West Area	3.16

1.0 INTRODUCTION

Since the 1940s, U.S. Department of Energy (DOE) sites have been used for nuclear materials processing and production, warhead testing, and weapons research and development. These activities have resulted in extensive environmental contamination. DOE has established a goal to cleanup and restore the groundwater, soils, sediments, and surface water at its facilities across the nation. To achieve this goal, many workers will be needed to conduct the cleanup. These workers will need training and will be required to follow occupational safety and health (OSH) regulations and guidelines.

Compliance with OSH regulations and guidelines will have an enormous influence on the schedule, money, and technology needed for environmental restoration. Therefore, one area that must be considered in the early stages of long-term planning is the impact of OSH issues on the environmental restoration process. The DOE Office of Environmental Restoration and Waste Management has requested that the Pacific Northwest Laboratory (PNL) investigate the impact of these issues on the environmental restoration process.

The first step of this study was to gain an overview of the OSH regulations and guidelines that are relevant to environmental restoration at DOE sites. Next, the broad OSH issues that could impact environmental restoration were identified. Then, case studies were conducted. An effort was made to identify sites with unique DOE problems, such as radioactive mixed waste. Three sites were identified.

The first two case studies (at the Hanford Site and Weldon Spring) are sites where a remediation activity has been completed. The third case study (at the Hanford Site) involves a remediation activity in its early stages of development.

1.1 PURPOSE AND APPROACH

The purpose of this report is twofold:

- Discuss the OSH regulatory framework.
- Illustrate, via case studies, how OSH considerations impact DOE in its long-term environmental restoration planning efforts.

The understanding of OSH issues as they occur in the field is key to DOE's success and effectiveness in its long-term cleanup efforts. These issues may include human factors issues related to the deployment of innovative environmental technologies, scheduling issues that arise due to the regulatory requirements, and other broad OSH issues. The emphasis will be on issues that should be considered and integrated into the environmental restoration planning process.

Several sources of information were used to accomplish the objectives of this report. A literature search was conducted and interviews were held with DOE contractor staff who have extensive experience in OSH issues at DOE sites. This background information was necessary to gain an understanding of the role the Occupational Safety and Health Administration (OSHA) and state agencies have with regard to remediation efforts at DOE sites.

Next, interviews were conducted with contractors directly involved in these activities to gain an understanding of the operational and occupational issues that arise during remediation activities. In addition, internal documentation related to the remediation activities was also reviewed. A questionnaire was developed to help guide the interviews and categorically collect information for the case studies. A copy of the questionnaire is in Appendix A.

This report is organized according to the main components of the investigation. The regulatory and institutional framework (i.e., the roles of OSHA, the U.S. Environmental Protection Agency [EPA], DOE, and the states in worker safety issues) is highlighted Chapter 2.0. This section also gives an overview of the worker safety issues related to the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) process. Chapter 3.0 contains three case studies of remediation activities performed at

selected DOE sites and the OSH issues that have arisen as a result of those activities. Chapter 4.0 presents a discussion of the findings and recommendations.

2.0 OVERVIEW OF THE REGULATORY FRAMEWORK

The Occupational Safety and Health Act (OSH Act) specifically excludes employees of federal, state, and local agencies. However, many of the standards established by the act and its implementation have a significant impact on these employees and agencies through Executive Orders and internal agency directives. Federal regulations and guidelines established to implement the OSH Act in the federal sector and a discussion of DOE sites are provided in this section.

2.1 FEDERAL IMPLEMENTATION OF THE OCCUPATIONAL SAFETY AND HEALTH (OSH) ACT

The OSH Act was enacted in 1970 to decrease injuries and illnesses in the workplace by ensuring "safe and healthful" working conditions for employees in the United States. The Act is administered by OSHA, a part of the Department of Labor.

The OSH Act was designed by Congress to be primarily enforced through the use of specific standards. The standards direct employers as to what must be done to achieve a safe and healthy working environment. Many thousands of OSH standards have been adopted in a continuing process.

Congress intended the OSH Act to have broad coverage; however, sections 3(5) and 4(b)(1) of the Act exclude federal employees from the specific standards and protection of the Act.^(a) Although omitted from the general provisions of the Act, Section 19(a) of the OSH Act places responsibility on the head of each federal agency to "establish and maintain an effective and comprehensive occupational safety and health program which is consistent with standards promulgated under Section 6 of the Act..."^(b) This responsibility

-
- (a) OSH Act, Section 3(5), 29 USC 652(5). Section 4(b)(1) states that the Act is not applicable to the working conditions of employees to which other federal and/or state agencies, acting under section 274 of the Atomic Energy Act of 1954, exercise statutory authority to prescribe or enforce standards or regulations affecting OSH.
 - (b) OSHA has promulgated regulations which outline basic program elements for a federal agency's employee OSH program. These regulations are found at 29 CFR Part 1960.

was further emphasized by a 1980 Executive Order that requires these agencies to implement workplace safety and health standards similar to those required in the OSH Act.^(a)

Executive Order 12196 compels federal agencies to furnish their employees with a workplace that is free of recognized hazards that are causing or are likely to cause death or serious physical harm. The Executive Order directs agencies to comply with OSHA standards issued under Section 6 of the OSH Act, as well as implement health and safety grievance procedures, provide supervisors with safety and health training, and maintain accurate records.

It has been recently announced that an Memorandum of Understanding (MOU) will be signed soon to formalize a relationship between DOE and OSHA. The details of this MOU are not known; however, DOE has announced the following:

- A five-year plan for safety and health will be prepared.
- OSHA compliance will be addressed in the FY 1993 budget.
- A new Office of Occupational Safety Programs will be established.
- DOE Orders will be revised to reflect OSHA regulations (Helminski 1991).

2.1.1 Specific DOE Regulations and Proposed Regulations

As required by Executive Order 12196 and Section 19 of the OSH Act, DOE has promulgated regulations that confront employee safety and health concerns in the workplace. The regulations place general requirements on DOE contractors to encourage and take actions to protect worker safety and health. These requirements include the following:

- Safety and Health Requirements (48 CFR 970.5204-2). DOE contractors are required by this regulation to take all reasonable precautions in the performance of their work to protect the safety and health of employees and the public.
- Award Fee (48 CFR 970.5204-54, 54 FR 48614). This section of the DOE acquisition regulations provides for administration of the award fee system. The DOE fee determination official is authorized

(a) Occupational Safety and Health Programs for Federal Employees, Executive Order 12196, February 26, 1980, effective July 2, 1980.

to withhold the entire award fee at his/her discretion if a contractor's performance is considered unacceptable in any area of contract performance covered in the performance evaluation plan. A consideration included in this determination is the contractor's OSH performance and plan.

- **Extend or Compete Decisions (48 CFR 970.0001).** This section of the DOE acquisition regulations discusses the renewal of management and operating contracts. A consideration in the renewal, extend, or compete decision involves the evaluation of the contractor's performance in the OSH area.
- **DOE's Contractor Employee Protection Program (10 CFR Part 708 Final Rule published 57 FR 7533, March 3, 1992, effective April 2, 1992).** This rule establishes procedures and standards for implementing DOE's Contractor Employee Protection Program. The program's goal is to protect contractor employees from reprisals for disclosing to DOE information regarding practices by their employers that may be in violation of a law, rule, or regulation. OSH violations would be included in this program.
- **NOTICE OF PROPOSED RULEMAKING: Acquisition Regulation Amendments (56 FR 42584, August 28, 1991).** This proposed amendment will require contractors to develop a specific health and safety clause for their subcontractors. Through adoption of this rule, DOE hopes to more clearly communicate the importance of safety and health considerations.
- **NOTICE OF PROPOSED RULEMAKING: Radiation Protection for Occupational Workers (56 FR 64334, December 9, 1991).** DOE proposes adoption of primary standards for the radiation protection for occupational workers. The rule would be applicable to the control of radiation exposures from normal operations under control of DOE and DOE contractor personnel.

2.1.2 DOE Directives, Notices and Orders

The DOE has issued a number of orders and directives implementing their employee OSH program. These orders and directives provide DOE offices and contractors specific guidance concerning OSH requirements. In some instances, the requirements contained in these orders and directives are then further defined with DOE Program Office memoranda and directives. Many of the DOE field offices have also implemented directives. The field office directives implement DOE Headquarter's employee OSH program and may incorporate various requirements of a particular state. As a result, these field office

directives often impose additional requirements/protection for its employees and their contractor's employees.

The directives issued by DOE that involve employee OSH are discussed below.

- DOE 3790.1A Federal Employee Occupational Safety and Health Program. This order sets forth DOE's policy for the implementation and administration of the Federal Employee Occupational Safety and Health Program as required by 29 CFR Part 1960 and Executive Order 12196. The order addresses many topics including, inspection/abatement procedures, reporting requirements, dissemination of information procedures, responsible DOE personnel, as well as safety and health training responsibilities. The order asserts that the minimum occupational health standards are to include all OSHA standards as well as the criteria discussed in 29 CFR Part 1960.
- DOE 5000.2A Multiprogram Laboratory Appraisals. This order establishes policies and procedures for DOE's appraisal of multiprogram laboratories. One area of appraisal is operations support performance which includes OSH and environmental protection activities.
- DOE 5480.1B Environment, Safety, and Health Program for DOE Operations. DOE Order 5480.1B establishes the Environment, Safety, and Health (ES&H) Program for DOE operations. All DOE elements and contractors performing work for the Department are covered by the order. The order states that it is DOE policy to:
 - ensure safe and healthful workplaces and conditions of employment for all DOE and contractor employees
 - require DOE line management to be responsible for effective ES&H performance in their programs. The order goes on to assign various implementation and program responsibilities.
- DOE 5480.4 Environmental Protection, Safety, and Health Protection Standards. This order specifies and establishes mandatory ES&H standards applicable to all DOE and DOE contractor operations. Attachment 1 to the order states that no OSH requirements are required as a matter of statute. Attachment 2 contains OSH requirements that DOE has chosen to make mandatory as a matter of policy. Included are the OSHA standards for general industry at 29 CFR 1910 and the OSHA standards for the construction industry at 29 CFR 1926. In addition, a number of industry and industry consensus standards (e.g., ANSI standards) are made mandatory. Attachment 2 also includes procedures for seeking an exemption from a mandatory requirement. Attachment 3 to the order contains a list of good practice standards that are not mandatory. There is an extensive

list related to occupational safety. Attachment 4 contains addresses that can be used to obtain industry standards.

- DOE 5480.5 Safety of Nuclear Facilities. This order established DOE's nuclear facility safety program. The goal is to ensure that DOE's nuclear facilities are sited, designed, constructed, modified, operated, maintained, and decommissioned in accordance with generally uniform standards consistent with those applied to comparable licensed nuclear facilities. The DOE order establishes an ES&H program and ensures that safety and health issues will be "comprehensively addressed and receive an objective review." This order has been interpreted in a memorandum from EM-1 dated February 6, 1991. The memorandum clarifies the application of the order to many of DOE facilities, and emphasizes the importance of the safety and health issues.
- DOE 5480.8 Contractor Occupational Medical Program. This order establishes occupational medical program requirements for DOE contractors. A written occupational medical plan is required. Occupational health physicians are to perform periodic worksite visits to review working conditions and recommend, if appropriate, corrective actions or preventive measures. Such visits are to be coordinated with appropriate industrial hygienists, toxicologists, and paramedical and safety personnel. Requirements for employee health examinations are included in this order.
- DOE 5480.9 Construction Safety and Health Program. All firms bidding on or selected for DOE construction contracts are to be made fully aware of the requirement to comply with applicable safety and health standards listed in DOE 5480.4. Before commencing work, each construction contractor is to submit to DOE an outline of the contractor's programs for industrial safety, health protection, and fire prevention and protection. The order also provides for periodic onsite construction inspections by DOE personnel.
- DOE 5480.10 Contractor Industrial Hygiene Program. This order establishes requirements for the industrial hygiene programs of DOE contractors. The policy statement in the order states that it is DOE policy to:
 - provide places and conditions of employment that are free from or protected against recognized hazards that cause or are likely to cause sickness, impaired health and well-being, or significant discomfort and inefficiency among workers or those with whom they come into contact
 - ensure that contractor employees and employee representatives have the opportunity to participate in the operation of the contractor employee industrial hygiene program

- ensure that contractors make well-defined assignments of responsibilities within their organization for the conduct of an employee industrial hygiene program. The order contains information on responsibilities and authorities, preparation and implementation of DOE directives related to industrial hygiene, required features of contractor industrial hygiene programs, control of carcinogens, industrial hygiene staff qualifications, and record keeping requirements.
- DOE 5482.1B. Environment, Safety, and Health Appraisal Program. This order establishes the ES&H appraisal program for DOE and its contractors. Each DOE field office is to conduct periodic functional and management appraisals of ES&H activities conducted by federal or contractor employees at least every 3 years. These appraisals are in addition to appraisals to establish the level of an award fee. Contractors are also to conduct internal appraisals. Considered in the appraisal process are the extent to which contractors are in compliance with DOE directives, and performance in the areas of organization and administration, staffing, training, communication, documentation, incident reporting, planning and spending, and follow up of the results of prior appraisals.
- DOE 5483.1A Occupational Safety and Health Program for DOE Contractor Employees at Government-Owned, Contractor Operated (GOCO) Facilities. This order establishes requirements and procedures to ensure that contractor employees receive OSH protection that is consistent with the protection afforded employees directly covered by the OSH Act. The order notes that the OSH Act does not directly apply to the working conditions of DOE contractor employees working in GOCO facilities since DOE exercises statutory authority under the Atomic Energy Act to prescribe and enforce safety and health standards at these facilities.

DOE 5483.1A is divided into three chapters. Chapter I repeats the DOE prescribed CSHA standards that are elsewhere identified in DOE 5480.4. It contains information on requests for variances and exceptions to the applicable standards and requirements for disseminating OSH information to employees. The chapter also requires DOE field offices to conduct unannounced OSH compliance inspections at least annually. Chapters II and III cover OSH complaints by employees and discrimination against employees filing such complaints. These chapters would be affected if the proposed rules cited earlier (55 FR 9326, March 13, 1990) become effective.

- DOE 5484.1 Environmental Protection, Safety, and Health Protection Information Requirements. This order establishes the requirements and procedures for reporting ES&H information. It applies to DOE prime contractors and certain subcontractors. Chapter IV of the order covers preparation of ES&H summary and investigative reports.

- DOE N 4220.3 Award Fee Contracts. This notice requires that the award fee pool for management and operating contracts involving defense production facilities be allocated such that at least 51% of the pool is assigned to ES&H functions.

2.1.3 Relationship of OSH Act to Environmental Laws and Regulations

Environmental laws regulate such varied subjects as hazardous waste, polluted water and air, toxic substances, and endangered species. Environmental law is aimed at protecting the general environment while the OSH Act protects the workplace. Conflicts generally arise when an environmental law regulates a substance that is also regulated by the OSH Act. For example, many court battles have resulted from EPA's regulation of toxic substances and OSHA's application of the OSH Act to the same substances. These conflicts have resulted in the addition of Section 9 to the Toxic Substances Control Act (TSCA). Section 9 contains procedures to be followed when jurisdictional conflict develops. TSCA is only one environmental law which regulates substances that are also regulated by OSHA. The Clean Air Act; Federal Water Pollution Control Act; and the Federal Insecticide, Fungicide, and Rodenticide Act also regulate substances under the jurisdiction of OSHA in some circumstances.^(a) During the late 1970s, many federal agencies came together and formed an interagency working group called the Interagency Regulatory Liaison Group (IRLG) in an effort to coordinate regulation of certain substances. The IRLG was disbanded in the early 1980s, and dual regulation of certain substances continues (Moran 1991). The OSH Act contains a provision that anticipates some of the regulatory overlap. When other federal agencies adopt conflicting OSH regulations for the workplace, the OSH Act will not apply.^(b) This is the second possible conflict (i.e., environmental laws that contain provisions which specifically regulate or effect the workplace as opposed to the conflicts which arise when a substance is regulated by both). Most environmental

-
- (a) Section 307 of the Federal Water Pollution Control Act; Section 112 of the Clean Air Act; Section 136 of the Federal Insecticide, Fungicide, and Rodenticide Act.
 - (b) Section 4(b)(1) of the Act says that when other federal agencies exercise statutory authority to prescribe or enforce standards or regulations affecting occupational safety or health, the OSH Act generally will not apply to those working conditions. 29 USC 653(b)(1).

laws do not contain such OSH provisions; however, cleanup/management of hazardous wastes is one area of environmental law that does directly address OSH issues.

The disposal and treatment of hazardous wastes under the Resource Conservation and Recovery Act of 1976 (RCRA) and CERCLA create a significant and often unique risk to the safety and health of employees who work in these operations. These risks were recognized and addressed by the Superfund Amendments and Reauthorization Act of 1986 (SARA), which was incorporated into CERCLA at Section 110. Congress required the Secretary of Labor, pursuant to Section 6 of the OSH Act, to issue interim final worker protection regulations 60 days after the date of the enactment of SARA and to promulgate permanent standards within 1 year of its enactment. These regulations were to provide no less protection for hazardous waste operations workers than the protection provided by EPA manuals and existing OSHA standards under Subpart C of 29 CFR Part 1926. CERCLA specifies 11 worker protection standards to be implemented.^(a) These standards were to encompass the following areas:

- site analysis
- training
- medical surveillance
- protective equipment
- engineering controls
- maximum exposure limits
- informational programs
- handling of wastes
- new technology programs
- decontamination procedures
- emergency response provisions.

(a) Section 126(b)(1)-(11) of Title I, SARA, incorporated in CERCLA Section 110.

Figure 2.1 depicts the interrelationship that OSH issues have with the CERCLA cleanup process. The language of CERCLA itself identifies 11 worker protection standards that must be implemented. These 11 issues can be combined into three general OSH issues: 1) training and job orientation, 2) identification of unknown workplace hazards, and 3) control and monitoring of known workplace hazards. Figure 2.1 attempts to graphically depict the relationship between these OSH issues and CERCLA. Each of the various stages of a site cleanup can involve one or more of the OSH issues. The figure includes both those issues that are required to be addressed (DOE Orders, Executive Orders, etc) as well as the issues that have been identified as factors in the individual stages but are not explicitly required.

On March 6, 1989, the Department of Labor (through OSHA) published its Hazardous Waste Operations and final rule. The scope of the rule is very broad covering four major areas/specific worker populations. These areas include:

FIGURE 2.1. Interrelationship Between OSH Issues and the CERCLA Cleanup Process

1. cleanup operations at uncontrolled hazardous waste disposal sites that have been identified for cleanup by a governmental health or environmental agency
2. routine operations at hazardous waste treatment, storage, and disposal facilities or those portions of any facility regulated by 40 CFR Parts 264 and 265
3. emergency response operations at sites where hazardous substances have been or may be released
4. corrective actions at RCRA sites.^(a)

In addition to these regulations, OSHA has issued various guidance manuals, both individually and in cooperation with other organizations, that specifically confront the workplace concerns regarding hazardous waste. These manuals provide recommended standards, procedures, and programs for operation of hazardous waste sites (NIOSH et al. 1985).

The impact of OSHA's standards at hazardous waste sites on federal facilities is through indirect means. As previously mentioned, the DOE falls outside of OSHA's jurisdiction. However, DOE and contractor employees are protected by DOE's own rules, regulations, and orders that incorporate many of OSHA's standards. This indirect impact is most recently evidenced by DOE's December 1991 guidance regarding training of employees working at hazardous waste sites.

(a) 54 FR 9295, 9296, March 6, 1989, codified at 10 CFR Part 708(a).

3.0 SELECTED CASE STUDIES AND ASSOCIATED OCCUPATIONAL SAFETY AND HEALTH ISSUES

Case studies were conducted to evaluate the impact of OSH regulations and DOE orders on three environmental restoration projects: 1) the Hanford Site 618-9 Burial Ground Expedited Removal Action (ERA), 2) the Weldon Spring Chemical Consolidation Interim Response Action, 3) and the Hanford Site 200 West Area Carbon Tetrachloride Expedited Removal Action and VOC-Arid Integrated Demonstration.

3.1 CASE STUDY #1 - HANFORD SITE 618-9 BURIAL GROUND EXPEDITED REMOVAL ACTION (ERA)

A description of the site and the OSH activities related to site remediation are provided in the sections below. The following OSH-related issues arose during the conduct of the 618-9 Burial Ground ERA:

- Field preparation time limits the time spent each day on actual cleanup work.
- Workdays will be lost due to events unrelated to site remediation.
- Knowledge of OSH required documentation is not apparent.
- Traditional safety risk analysis for environmental restoration work may be inappropriate.
- Training requirements for site workers must be coordinated and appropriate.

These OSH-related issues are discussed in Section 3.1.3.

3.1.1 Site Description and Background

On December 20, 1990, DOE was instructed by the EPA and the State of Washington Department of Ecology to initiate planning necessary to implement an ERA for the 618-9 Burial Ground at the Hanford Site (DOE 1991a). An ERA, also known as an interim response action under CERCLA, is an action taken at waste sites where early remediation will abate potential threats to human health and the environment or prevent significant increased degradation that

might occur if action were delayed until completion of the Remedial Investigation/Feasibility Study (RI/FS) and subsequent remedial action.

Throughout the history of the Hanford Site, prior to comprehensive legislation regarding the disposal of hazardous waste, chemical waste products were disposed of by burial in trenches. One such trench is the 618-9 Burial Ground. The 618-9 Burial Ground (located on the Hanford Site) is approximately 1 mile west of the Columbia River and north of Richland, Washington. (see Figure 3.1). It is a 185-ft-long trench. Originally it was 10 to 15 ft deep, 18 ft wide at the bottom, and had been excavated to a 40-ft width at the top. The soil consists of gravel and fine sand. There are no wetlands in the vicinity of the 618-9 Burial Ground and the climate is semiarid.

It was suspected that the 618-9 Burial Ground contained approximately 5,000 gallons of uranium-contaminated organic solvent derived from laboratory studies in the late 1940s and early 1950s. The solvent was thought to have been contained in 55-gallon drums. Although it was believed the trench contained approximately 100 drums, the number of drums buried was not well documented.

The ERA, although not a specific Tri-Party Agreement (TPA) milestone, was carried out under the general TPA provisions related to ERAs. The ERA for the 618-9 Burial Ground was originally divided into two phases: Phase 1 involved the time-critical activities associated with removing human health and environmental hazards, Phase 2 involved the remediation of contaminated soils.

The preliminary investigations provided the data necessary to initiate excavation at the site. It was thought that buried objects would be found at approximately 4 ft below ground. Organic vapors were suspected as a potential safety concern because the soil gas survey indicated the presence of some unidentified organic vapors. Historical information and personnel interviews provided the information necessary to prepare the required safety and emergency planning documentation. Documentation prepared prior to excavation activities discussed the potential to uncover a variety of organic solvents and a large quantity of uranium.

FIGURE 3.1. Hanford Site 618-9 Burial Ground

Excavation of the 618-9 Burial Ground commenced on February 28, 1991 (DOE 1991a). The ERA was carried out by employees of Westinghouse Hanford Corporation (WHC). All drums were located in the east and west ends of the 618-9 Burial Ground, covered by 10 ft of overburden (6 ft deeper than originally expected). In addition, construction and miscellaneous debris were found in the trench. The 120 drums in the western end of the trench were fairly well preserved, and approximately 1,600 gallons of solvents were recovered. Drums in the eastern end of the trench were severely corroded and could not be counted due to their condition. After the materials were removed from the trench, sampling activities were conducted to determine the precise nature of contamination in the 618-9 Burial Ground.

Methyl isobutyl ketone (MIBK), also known as hexone, was the primary solvent listed in historical records as having been disposed at the 618-9 Burial Ground. During excavation activities, the solvent was recovered in liquid form, but was not detected in soil samples. Levels of other potential contaminants of concern did not turn out to be a significant problem at the site. Radiological data analyses are not complete; however, field readings and total activity scans indicated no radiological constituents. The laboratory data are expected to confirm the field results. In addition, a former Hanford employee indicated that carbon tetrachloride was buried at the site. However, none was detected.

During this first phase of activities, completed in May 1991, approximately 700 gallons of hexone and 900 gallons of kerosene were recovered from 42 drums in the 618-9 Burial Ground. Interviews were also conducted with personnel who worked at the site in the 1950s, who indicated that kerosene was also buried at the location. In addition to these solvents, over 80 empty drums were removed, along with a significant amount of scrap process equipment/building debris. Extensive follow-up sampling has detected no hexone and relatively insignificant amounts of kerosene. It was recommended that the following actions occur: 1) perform final disposal of the recovered solvent and other waste generated during excavation, 2) backfill and revegetate the site, and 3) survey the trench boundaries for future reference.

Few of the major radiological and chemical hazards that were anticipated at this site were encountered during the ERA. WHC personnel were able to complete the ERA in a shorter time period and for less cost than originally anticipated. No significant OSH problems were encountered during the ERA.

3.1.2 Occupational Safety and Health Activities

A substantial amount of documentation related to OSH activities was required prior to commencement of the ERA at the 618-9 Burial Ground. The principal OSH-related document prepared for this ERA was the Hazardous Waste Operations Permit (HWOP). Preparation of this document was an internal WHC requirement and written by the health and safety officer for the ERA. The primary purpose of the HWOP was to outline the various tasks involved in the ERA, identify associated potential occupational hazards, and provide plans for addressing potential occupational hazards.

The primary concerns associated with this task were the potential volatility and flammability of the drum contents. To prevent fires and explosions, a number of procedures were implemented:

- Where possible, actual contact with drums was done remotely.
- Non-sparking pumps and other tools were used.
- Monitoring for combustible gases was carried out continuously.
- Plans were in place to cease operations if temperatures exceeded 60°F.
- Drums were grounded during opening, sampling, and pumping operations.

Because of uncertainty regarding the contents of the drums and other materials that might be found in the burial ground, Level B personnel protective equipment was required for all personnel carrying out the ERA work onsite. This included the use of supplied air, full body coveralls, PVA gloves, steel-toed boots, and hard hats.

Other potential safety hazards noted in the HWOP included those associated with work in confined spaces, on uneven terrain, and in trenches. Hazards related to the use of heavy equipment were also noted.

3.1.3 Occupational Safety and Health Issues

Time Spent Each Day on Actual Cleanup Work

Project managers reported that time spent actually cleaning up the site was no more than 2 to 4 hours per 8-hour workday. The primary limiting factor for cleanup was the amount of time workers could conduct an activity while wearing the necessary personal protection equipment, including supplied air respirators and chemical protection clothing. Heat stress was the principal concern associated with the chemical protection clothing. It is likely that this would have been a more limiting factor had the ERA not been carried out during the winter and early spring months. In addition, daily briefings and other job preparation limited the amount of actual work carried out each day.

Lost Workdays

Of the 60 workdays for the 618-9 Burial Ground ERA, no actual cleanup work occurred on approximately 10%, or 5 to 6 days. The reasons for these lost workdays were largely related to OSH concerns. For example, there was a requirement that two individuals carry out radiation monitoring at the site, one in the actual trench area and the other outside the immediate restricted zone. On several occasions, either because of illness or scheduled vacation, one of the radiation monitoring personnel did not arrive. Project managers reported they had no advance notice of these absences, even with scheduled vacations, and no replacement individuals were provided. During the days that these absences occurred, no actual cleanup work could be done. This example is just one of several causes of lost workdays.

Additional delays likely would have occurred if adverse conditions had materialized. A major safety consideration involved the flash point for hex-one at 63°F. If temperatures near this point, the risk of drum explosions increases significantly. Site work would eventually have been curtailed if cleanup activity continued into the spring months. The ERA could not have been carried out during the summer, when temperatures at the Hanford Site frequently exceed 100°F.

Knowledge of OSH Required Documentation

The OSH officer for the 618-9 Burial Ground ERA developed a format for the HWOP because, to the best of his knowledge, no form existed for this type of cleanup activity. The HWOP format he developed was based largely on OSHA requirements. Others on the project, however, said that WHC did have a standard HWOP format. WHC does have a standardized HWOP format that can be located in two management manuals. The HWOP is an internal document that contains the excavation permit and radiation workers permit, among other documents. This HWOP is required by 29 CFR 1920.120.

Appropriateness of Using Traditional Safety Risk Analysis for Environmental Restoration Work

OSH planning for the 618-9 Burial Ground focussed on compliance with applicable OSH requirements. In addition, the project was required by the WHC safety office to comply with various safety analysis mandates. Those involved in the ERA expressed the opinion that while the various safety analyses produced some useful information, they were either largely irrelevant to the work or were redundant with activities required under OSHA. For example, the health and safety officer had to investigate whether the City of Richland would be exposed to hexone in the event all hexone drums exploded. This activity had little to do with protecting onsite workers. Project managers generally felt that actions and planning required by OSHA to protect workers onsite would certainly address any issues of concern in the safety analyses.

A broader issue was raised: How relevant to environmental restoration work are safety analysis requirements that were traditionally applied to specific facilities? Many felt that these analysis are not applicable to the environmental restoration work. The analogy of applying U.S. Nuclear Regulatory Commission (NRC) rules to a drill site was mentioned to describe the inappropriateness of this requirement. The requirement to perform the safety analyses did not present a substantial impediment to the ERA, primarily because this activity was a high priority for WHC. It is unlikely, however, that future ERAs and remedial actions will have such priority status, and substantial delays in projects could result if such requirements were imposed.

Training Requirements for Site Workers

A substantial number of training requirements exist for workers carrying out environmental restoration activities. These include 40-hour OSHA training, annual OSHA refresher, radiation workers training, respirator user training, and in some instances, noise control training. Project managers stated that it was difficult to keep track of the training and certification status of site workers. They reported that the certifications for some of the site workers expired while the ERA was underway. These workers had to be pulled off the job to get them retrained. This resulted either in delays in the work or the need to identify others to carry out the responsibilities of those being trained.

3.2 CASE STUDY #2 - WELDON SPRING CHEMICAL CONSOLIDATION ACTIVITY INTERIM RESPONSE ACTION (IRA)

A description of the site and the OSH activities related to site remediation are provided in the sections below. The following OSH-related issues arose during the conduct of the Weldon Spring container consolidation Interim Response Action (IRA):

- OSH planning and implementation by the subcontractor lacks detail.
- Field preparation time limits the time spent each day on actual cleanup work.
- Traditional safety risk analysis may be inappropriate for environmental restoration work.
- Site designations may be necessary to reduce, where appropriate, training requirements.

These issues are discussed in Section 3.2.3.

3.2.1 Site Description and Background

The Weldon Spring Site is located about 30 miles west of St. Louis, Missouri. The site was originally used in the 1940s by the Army to manufacture explosives. In 1956, the Atomic Energy Commission (AEC) acquired approximately 220 acres from the Army for use as a uranium feed materials plant. Following shutdown of the Feed Materials Plant at Weldon Spring in 1966, the

AEC transferred the facility back to the Army for conversion to a chemical defoliant plant. Work on the defoliant project was cancelled in 1969 before renovation of the facility was complete; therefore, no herbicide was produced at Weldon Spring. Little or no activity took place at the site through the early-1980s, when DOE initiated environmental restoration activities under a single project, the Weldon Spring Site Remedial Action Project (WSSRAP). On October 1, 1986, the MK-Ferguson and Jacobs Engineering Team assumed responsibilities as the Project Manager Contractor (PMC) for the WSSRAP. The Weldon Spring Site was placed on the National Priorities List (NPL) in 1987.

The Weldon Spring Site is located in a rural area comprised of small, vegetated rolling hills. A wildlife preserve is located adjacent to the site and contains several small lakes that receive drainage from the site. The Weldon Spring Chemical Plant (WSCP) contains 5 process buildings, 8 support buildings, and over 30 auxiliary buildings (see Figure 3.2).

In 1990, the Weldon Spring PMC initiated an IRA under CERCLA to identify and dispose of containerized waste at the Weldon Spring Site.^(a) The goals of this IRA were as follows:

- Mitigate the potential for sudden or unexpected release to the environment of hazardous substances resulting from improper container storage, continued container degradation, or increased site remedial activities that may increase the potential for such releases.
- Identify and remove those materials that create potential exposure risks to the health and safety of site personnel during subsequent WSSRAP activities. The work for this IRA was carried out primarily by a subcontractor to the PMC.

The IRA focussed on materials that were still in containers. These materials included liquids, solids, sediments, and sludges that were in surface and subsurface storage tanks, process vessels, sumps, drums, fuel tanks, laboratory containers, gas cylinders, fire extinguishers, batteries, bags, boxes, jars, cans, and other miscellaneous containers.

(a) MK-Ferguson Company and Jacobs Engineering Group, Inc. 1987. Weldon Spring Chemical Plant Containerized Waste Assessment and Removal Plan. Draft report prepared for DOE.

FIGURE 3.2. Weldon Spring Chemical Plant Site

Prior to the initiation of the IRA, it was estimated that hazardous wastes constituted 55% of the total volume of material, non-hazardous wastes constituted 45% of the volume, and radiologically contaminated wastes made up 5% of the volume. The PMC identified 310 container groups, consisting of approximately 4,000 individual containers. It was estimated that approximately 5,000 gallons of liquids and approximately 2,500 ft³ of solids were in the containers. Many of the containers were empty or partially full, and many were not labelled. Based upon previous surveys, it were estimated that approximately one-third of the containers were unlabelled or the contents were otherwise unknown.

Sampling, consolidating, and repacking the wastes were expected to involve potential exposure to chemically hazardous substances via skin contact, inhalation, and ingestion. Radioactive contamination existed primarily as both fixed and removable surface contamination on structural material and containers. In some instances, the material inside the containers was radioactively contaminated. Because of the plant's history, the radiological contaminants were assumed to be natural uranium, natural thorium, and associated daughter products, although uranium was the primary radiological contaminant of concern.

The IRA was conducted in two phases. Phase I involved two activities, container inventory and chemical characterization, and was carried out by the subcontractor. The information gathered in the first phase was used to develop subcontractor bid specifications and other documents necessary to award a subcontract to perform Phase II activities. Phase II work, performed by the PMC, included site preparation for container staging, container sampling, and waste bulking.

3.2.2 Occupational Safety and Health Activities

The principal OSH-related document prepared for this IRA was the Safety and Health Plan (HASP). The purpose of this document was to outline safety and health procedures for the project and to describe work conditions that were likely to be encountered. In addition, a job safety analysis was prepared for the IRA. Both of these documents were intended to outline the various tasks involved in container consolidation, identify associated potential

occupational risks, and provide plans for addressing potential occupational hazards. In addition, a containerized waste assessment and removal plan was prepared for this IRA.

The primary physical hazards of concern were cold stress, noise, sharp objects, radiological contamination, and the possibility of explosions and/or fires, slips, and falls. In addition, the risk of exposure to hazardous chemicals via inhalation and skin contact was considered high. The job safety analysis identified a number of specific hazards, including:

- uncontrollable fire caused by field cutting necessary to expose containers for removal
- rupture of containers due to mixing of incompatible chemicals
- unexpected rupture of pressurized gas cylinders
- chemical or radiological exposure of employees during sampling, bulking, and relocation operations
- build-up of static electric charge during transfer of flammable liquids creating a potential for fire
- exposure of downwind employees to hazardous dusts due to improper handling of dry, solid wastes.

The HASP required the appropriate use of institutional and administrative controls to minimize the exposure of workers to hazardous substances. In addition, the Plan required the use of appropriate personal protective equipment, up to the use of Level A protection, consisting of a fully encapsulating suit with attached gloves, boots, and headpiece with an air-supplied respirator. Although Level A protection was stated for use in the HASP if needed, this level of protection was never actually required during the onsite activities. Level B protection with supplied air respirators was commonly used during this IRA.

3.2.3 Occupational Safety and Health Issues

The following OSH-related issues arose during the conduct of the case study.

OSH Planning and Implementation by Subcontractor

A concern was expressed by the PMC project managers regarding the quality of the OSH planning documentation prepared by the subcontractor for the IRA. They felt that the subcontractor did not put in the level of effort needed to develop the OSH planning documents. They also indicated that the subcontractor's plans were much too general and lacked detail. This in turn resulted in a HASP that was perceived as not being as strong as what is used in the private sector. The PMC managers said that health and safety planning may have suffered because a lump-sum subcontracting mechanism was used. The current contractor has since developed an overall HASP which is included in every subcontract. This detailed guidance document provides more details than the subcontractor's plan. The subcontractors still prepare their own "safe work plans;" however, these are not very task specific.

Time Spent Each Day on Actual Cleanup Work

The cleanup occurred in two phases and spanned all seasons. Project managers reported that time spent each day actually carrying out the container consolidation IRA was no more than 4 hours. The primary limiting factor was the amount of time workers could carry out cleanup activities while wearing the necessary personal protective equipment (i.e., dress up, dress down, shower). Required briefings and training also limited the amount of time devoted to actual cleanup work.

Appropriateness of Using Traditional Safety Risk Analysis for Environmental Restoration Work

Although this issue did not directly impact the work on the container consolidation IRA, the project managers were concerned about the impact of applying safety analysis requirements used for nuclear facilities on environmental restoration activities at Weldon Spring. These safety analysis requirements were viewed as being largely redundant to efforts already in place to protect workers and provided no added value to ensure worker health was protected.

Using Site Designations to Reduce, Where Appropriate, Training Requirements

Careful attention was given by project managers when designating areas that did or did not contain hazardous substances or that presented higher risks to worker safety and health. This was to help ensure that workers received only the training that was appropriate for the type and location of work they were conducting. For example, workers entering hazardous waste areas are often required to undergo a substantial amount of training. Site managers cited a hypothetical example of an electrician who may need 24 hours of training to go onto a site to perform a 1-hour job. This situation was avoided by designating as hazardous only the actual area that contained hazardous substances or presented other significant hazards.

3.3 CASE STUDY #3 - HANFORD'S 200 WEST AREA CARBON TETRACHLORIDE EXPEDITED REMOVAL ACTION (ERA) AND VOC-ARID INTEGRATED DEMONSTRATION (ID)

A description of the site and the OSH activities related to site remediation are provided in the sections below. The following OSH-related issues arose during the planning and initial stages of the Hanford 200 West Area Carbon Tetrachloride ERA and VOC-Arid Integrated Demonstration:

- Field preparation time limits time spent each day on actual cleanup work.
- Numerous organizations with OSH oversight exist.
- Traditional safety risk analysis may be inappropriate for environmental restoration work.
- Lost workdays will be minimized as a result of planning.
- Training requirements for site workers will be coordinated.
- Worker safety is a key component in technology development.

These issues are discussed in Section 3.3.3.

3.3.1 Site Description and Background

On December 20, 1990, EPA and the State of Washington Department of Ecology asked DOE to assess the carbon tetrachloride contamination located in

the unsaturated soils beneath the 200 West Area of the Hanford Site and to evaluate cleanup alternatives (DOE 1991b). This ERA was initiated because of the concern that the contaminants would continue to migrate from the soils to the groundwater.

The 200 West Area is approximately 7 miles east of the western boundary of the Hanford Site and approximately 5 miles south of the Columbia River (see Figure 3.3). Three carbon tetrachloride disposal sites are located in the 200 West Area where chemical processing plants have been operating since the 1940s. The disposal sites include the 216-Z-1A Tile Field, 216-Z-9 Trench, and the 216-Z-18 Crib. The 216-Z-1A Tile Field is approximately 200 by 360 ft at the surface. The 19-ft deep excavation has sloping which results in a floor dimension of approximately 115 ft by 275 ft. The base of the 216-Z-9 Trench is a 60- by 30 ft excavation, 21 ft below the surface. The 216-Z-18 Crib consists of five parallel excavations, 207 by 10 by 18 ft deep. It is estimated that between 1955 and 1973, 575 to 925 metric tons of carbon tetrachloride from the Z Plant (waste from the plutonium recovery process) were disposed of at these three sites. The concentration of carbon tetrachloride, a suspected carcinogen, in the groundwater is 10 to 1000 times greater than EPA's maximum level of 5 parts per billion for drinking water. In addition to the carbon tetrachloride contamination, other organics and their degradation by-products, and radionuclides (i.e., plutonium and americium) are also present.

In 1991 a preliminary site characterization was conducted to evaluate the extent of the contamination and the remedial options. In addition to describing the physical characteristics of the site, the nature and extent of contamination were investigated. Carbon tetrachloride vapors were detected throughout the 200-ft thick unsaturated zone. Soil vapor extraction was tested and proposed for remediation in the first phase of the ERA. In January 1992, DOE was authorized by EPA and the Washington State Department of Ecology to proceed with the remediation of the carbon tetrachloride in the unsaturated soils. The soil vapor extraction system will apply a vacuum in the area of the carbon tetrachloride vapor plume. The carbon tetrachloride, along with other volatile organics, will be adsorbed into granulated activated carbon

FIGURE 3.3. Hanford's 200 West Area

(GAC) canisters. Treatment of the 7- mi² carbon tetrachloride groundwater plume located under the disposal sites may need to be addressed in the future. Field test site development will continue through 1992 and 1993, with initial tests of microbial stimulation scheduled for 1994.¹

The ERA is closely linked to the VOC-Arid Integrated Demonstration. The VOC-Arid Integrated Demonstration was initiated in 1991 by DOE's Office of Technology Development. Integrated demonstrations are part of an innovative program to accelerate the development and testing of innovative technologies do not exist to adequately meet DOE needs. The VOC-Arid Integrated Demonstration program is co-managed by WHC and PNL. The VOC-Arid Integrated Demonstration program is demonstrating technologies at the Hanford 200 West Area in five major areas:

- site characterization and monitoring
- retrieval and ex-situ treatment of contaminants
- in-situ destruction or immobilization of contaminants
- remediation system design and evaluation
- enhanced drilling.

A top priority of the VOC-Arid Integrated Demonstration is to transfer new technologies to the on-going carbon tetrachloride ERA after they have been determined to be technically sound and have gained both regulatory and public acceptability. These technologies are also being developed to meet the needs of the other arid sites.

The ERA is being conducted before the completion of the CERCLA RI/FS work of the 200-ZP-1 and 200-ZP-2 operable units, where the carbon tetrachloride and disposal sites are located. Field test site development will continue through 1992 and 1993, with initial tests of microbial stimulation scheduled for 1994.

¹ T. M. Brouns, M. C. Hagood, V. J. Rohay, and P. J. Valcich, March 1-5, 1992. "Combining Expedited Cleanup with Innovative Technology Demonstrations." In Proceedings of Waste Management '92 Conference, publication pending.

3.3.2 Occupational Safety and Health Activities

The two greatest OSH concerns that have the potential to shutdown the ERA are fugitive emissions and the off-gassing of wells from the soil column. To address these concerns, monitoring stations will be used to conduct site monitoring. Canisters with double backup will be used in the event of breakthrough from the original canister.

One of the earliest ERA events to occur related to OSH involved the identification and screening of removal alternatives for the 200 West Area carbon tetrachloride vapor plume. Several technologies were eliminated from consideration because they were not judged to provide overall public health and/or environmental protection to meet the regulatory requirements. Examples of these technologies include the following:

- Soil flushing, an in situ process used to extract contaminants from the soil, was identified as not being applicable for the high-radiation zones in the near-surface soil below the three disposal locations. Although flushing would remove some of the radionuclides, it would cause other contaminants to migrate further into the subsurface. Severe solvent treatment problems and unnecessary personnel radiation exposures were also identified to occur with its use (DOE 1991b).
- Drilling and well completion through contaminated soils were recognized as health and safety concerns, with the potential for onsite workers to be exposed to carbon tetrachloride vapors and radiological contamination (DOE 1991b).
- Accumulation of radioactive particulates in the inlet high-efficiency particulate air (HEPA) filters would result in unnecessary personnel exposures when the filters are removed for disposal. If such accumulations occur at initial extraction locations, the accumulations of radionuclide particulates cannot be avoided, and the entire project may be closed down. In any case, radiation emissions will be minimized or avoided entirely (DOE 1991b).

After all the removal options were evaluated, it was determined that the use of soil vapor extraction met the criteria and provided protection to the occupational worker. To minimize potential exposure to occupational workers, monitoring will occur on the soil vapor extraction unit where fittings, hose

connections, and carbon canisters are located. In-line monitors, calibrated to detect concentrations of carbon tetrachloride, will shutdown the process if the limits are exceeded (DOE 1991b).

Drilling of new characterization boreholes is needed to further characterize the site. Drilling through contaminated soils is also a health and safety concern, because onsite workers may be exposed to carbon tetrachloride vapors and radiological contamination. A HASP was prepared by the ERA and another HASP was prepared for the VOC-Arid Integrated Demonstration team to address the potential OSH issues for the characterization phase of the project. The HASP included a site description, types and sources of contamination, general safety and training issues, and plans for onsite control and emergency action.

Many internal OSH organizations required documentation relating to the ERA and VOC-Arid Integrated Demonstration. An HWOP was prepared for the ERA and used for the characterization phase of the ERA. The HWOP addressed worker health and safety for the soil vapor extraction field demonstration test. An additional HWOP addressed the issues associated with the well perforation activities. In addition, WHC prepared job safety analysis for various tasks. Any VOC-Arid Integrated Demonstration technologies that will be tested will require appropriate safety plans.

3.3.3 Occupational Safety and Health Issues

Time Spent Each Day on Actual Cleanup Work

Because of the temperature extremes during the summer and winter, fall and spring are the most productive times for remediation work at Hanford. Fewer hours (between 3-4 hours) may be possible in the summer because of heat stress. One program manager noted that there is a tendency to require additional worker protection (for example, supplied air when working with carbon tetrachloride) while ignoring the human factors limitations imposed on the worker from this additional protection, especially when weather conditions may not be optimal. One researcher felt that it took longer to accomplish tasks because current workers lack experience in radiation zones and are much more cautious.

Numerous Organizations with OSH Oversight

To accomplish the ERA tasks, there are at least six safety organizations, each with its own reporting requirements, involved in OSH issues for this activity. Many represent different contractors on the site.

It was reported that much of the documentation required by these organizations has little or no benefit to worker safety and health. It was felt that current OSHA reporting requirements have sufficient mechanisms to protect worker safety and health and that involving additional organizations with this activity is inefficient. It was also stated by contractor staff that as activities with the VOC-Arid Integrated Demonstration progress, similar documentation, if not more, would be required by these organizations to demonstrate the technologies. Further documentation and requirements were felt to be ineffective, costly, and could result in delays in accomplishing the goals of the ERA and VOC-Arid Integrated Demonstration.

Appropriateness of Using Traditional Safety Risk Analysis for Environmental Restoration Work

Although the ERA's vapor extraction system is being used for remediation in the field, it is viewed by one of the safety organizations as a nuclear facility according to a February 1, 1991, memo that discussed definitions of facilities. Because of this classification, a safety assessment report was required to be completed for a 2-week pilot test of the soil vapor extraction unit. Preparation of this report took several months to complete and cost \$70,000 with what project managers felt was little value added. (Preparation of this report in conjunction with procurement was just one factor responsible for this delay.) Project managers said the OSHA requirements to protect hazardous waste workers onsite were sufficient to address the issues of concern in the safety analysis.

Lost Workdays

The ERA and VOC-Arid Integrated Demonstration teams are aware of the potential publicity surrounding the cleanup of the carbon tetrachloride plume and the precautions that must be taken to ensure health and safety protocols are fully complied. To avoid substantial loss in field work due to

tour-related disruptions, the team will designate and set aside 1 to 2 days per month exclusively for tours. Other factors may also contribute to lost workdays as described in the following section.

Training Requirements for Site Workers

The ERA demonstration operations staff will track all worker training requirements with the intent to avoid some of the lost days that are associated with last-minute notifications of some workers to attend training sessions. Any offsite principal investigators who demonstrate their technology onsite will track their own training requirements. The investigators will have to meet WHC requirements to gain access to the field and must bring acceptable documentation with them to demonstrate that they have received the training.

The WHC VOC-Arid Integrated Demonstration team produced a field access guide for visitors to the VOC-Arid Integrated Demonstration site. The guide assists visitors from both DOE and non-DOE sites in completing the WHC training requirements needed to work at the VOC-Arid Integrated Demonstration Site. This document provides information on security badges, medical clearances, and hazardous waste worker clearance needed for admittance to the site.

Technology Development and Worker Safety

Technology evaluation criteria have been developed for the VOC-Arid Integrated Demonstration. These criteria will be used to evaluate the performance of the new technologies against the performance of the soil vapor extraction baseline technology currently in use at the 200 West site. One criterion will be how the new technology performs with regard to worker health and safety. Technology developers are being asked to design their technologies to minimize occupational exposures to the remediation workers who use them.

4.0 DISCUSSION OF FINDINGS AND RECOMMENDATIONS

Selected findings from the three case studies suggest that certain OSH-related constraints or requirements have the potential to significantly impact DOE's environmental restoration activities, budgets, and milestones, perhaps in unforeseen ways. EM should alert field organizations to potential delays that may be precipitated by OSH-related issues and, more importantly, should collaborate closely with EH to provide field organizations with guidance regarding steps that could be taken now to anticipate, prepare for, and mitigate against OSH-related delays. As the rate of cleanup activities and the size of the involved workforce increase, various publics, unions, and the media will have an increasingly proactive interest and involvement in OSH factors. DOE should consider that the following findings have the potential to grow into problems that could lead to missed milestones or, if ignored, could contribute to or precipitate work slowdowns or strikes.

Finding 1. At one case study site, interviews indicated that no more than 2-4 hours per typical 8-hour day were spent on actual clean-up.

Moreover these delays did not reflect any major unforeseen problems that were encountered at the site. Rather, they are attributable to routine activities necessary to ensure worker health and safety. Had unforeseen technical problems or adverse weather conditions developed during the cleanup, the delay would have been exacerbated. Field preparation time, requisite OSH-related briefings and debriefings, and vagaries of climate and weather can all serve to significantly discount the number of hours available for actual clean-up activities in a given day, month, or year.

Recommendation At the site level, long-term cleanup schedules and strategies should be reviewed to determine if adequate consideration has been given to delays that may be encountered due to OSH

requirements. Current estimates of environmental restoration schedules and budgets are based in part on best engineering judgements that are predicated on contractor experiences gained from clean-up of non-nuclear, private sector sites, perhaps in other geographic locations. Finding 1 suggests the possibility that good faith estimates of manhours necessary to complete a task may be overly optimistic unless the time necessary to comply with OSH-related activities has been taken into account. This raises the possibility that unforeseen OSH-related constraints on worker productivity may impact proposed or negotiated milestones. Sites should be advised to implement an ongoing effort to document instances where schedules or milestones have slipped due to OSH-related delays. Such documentation could provide strong, legitimate support for renegotiation of milestones. In a related vein, DOE should consider negotiating adequate flexibility for "OSH-related delays" language into future agreements and schedules. Finally, there are a number of engineering oriented industries or activities that have rigid OSH requirements as well as environmentally mandated limitations on the number of hours that workers may perform on the job (e.g., ocean engineering, and arctic research, exploration and mining). DOE should consider how best to avail itself of the work force scheduling experiences of these and similar sources.

Finding 2. At one case study site, the certification of some site workers expired while work was underway, resulting in slipped schedules and cost overruns.

As the number of ERMCS increases, the number of contractor personnel working at DOE sites will increase dramatically. It is reasonable to expect that many of these workers will be newly hired and will have little or no experience with site-specific OSH requirements, or for that matter with site

security requirements. In addition, the needs for recertification will need to be considered.

Recommendation At the site level, DOE should implement reviews to verify that available training resources and facilities are sufficient to accommodate the projected influx of new workers. Sites such as Hanford with many operable units may experience a growing backlog of required recertification training. Finding 2 demonstrates that even in the early stages of site restoration, lapses in required training can impact schedules and budgets. Sites should critically evaluate the implications of an influx of additional hundreds or thousands of workers who may require initial training and periodic recertification. There may be opportunities to leverage or cluster required training at proximate operable units. Likewise, it may be possible to minimize lost cleanup time by synchronizing off-site safety and health training, on-site job training, and annual refresher courses. The results should be factored into revisions to long-term planning, negotiations, and manpower needs projections. Sites should also examine approaches to eliminate or minimize unnecessary training requirements. For example, hazardous zones requiring training for access should be minimized to the maximum extent consistent with safety and health. In addition, automated systems for tracking worker training requirements should be developed.

Finding 3. DOE's traditional approach to OSH issues at weapons production facilities may be inappropriate for environmental restoration sites. As a result, internal conflicts are arising relative to the definition of what constitutes a necessary and sufficient degree of OSH-related activity.

As DOE's mission focus continues its transition from weapons production to environmental restoration, some OSH-related

requirements traditionally applied to production sites are being applied at sites that are now primarily or exclusively restoration sites. For example, preparation of a safety assessment report, a standard practice for weapons production facilities, is now required for some restoration sites. The relevance of this type of report is defended by some safety and health organizations that have been traditionally involved in weapons facility operations. However its relevance is challenged by some environmental restoration contractor staff. On the other hand, some environmental restoration contractor staff believe that many traditional health and safety staff personnel are ignorant and untrained with regard to environmental restoration site activities and requirements.

Recommendation In 1991, Dr. Zeimer, Assistant Secretary for ES&H, announced that an MOU was to be signed shortly to formalize a relationship between DOE and OSHA. This announcement came as a response to an OSHA evaluation that was completed as a part of the Tiger Team Assessments. Among other actions specified by Dr Zeimer, he indicated worker safety and health orders will be revised to conform to OSHA regulations. EM should capitalize on this MOU as an opportunity to revisit and resolve outstanding OSH-related issues. EM should request sites that are experiencing overlapping or conflicting OSHA-related protocols to prepare a bill of particulars specifying instances where DOE's traditional "weapons production" approach to OSH related issues seem now to be in conflict with an "environmental restoration" approach. Based on such a review, and consistent with the provisions of the MOU, EM should draft proposed language for a DOE Order or regulation that would articulate and implement DOE policy regarding OSH-related protocols.

Finding 4. Currently, OSHA does not provide routine oversight of DOE facilities.

Because OSHA regulations under 29 CFR 1919.120 do not necessarily apply to federal sites, DOE facilities remain self regulating and are not subject to regular inspection by OSHA. Interpretation of and compliance with the applicable regulations remains the responsibility of the private contractors who are operating onsite. However, this fact was not cited as a concern by interviewees. To the contrary, all interviewees emphasized the high priority given to OSH issues.

Recommendation Site-specific public participation plans should capitalize on the current positive perceptions articulated by contractor staff in the case studies. Certain stakeholder groups may hold the foregone, and formerly justified, conclusion that self-regulation and the lack of independent OSHA oversight are tantamount to a public health threat. If properly articulated in a timely manner, the views of workers regarding the extent of EM's sensitivity and commitment to OSH compliance could go a long way towards assuaging any possible public concerns.

Finding 5. OSH factors could make or break an emerging technology.

Recommendation Innovative environmental restoration technologies should be evaluated against criteria designed to ensure that worker exposure to hazardous substances is minimized. Although this is occurring with some EM projects, general guidance is needed for technology developers to ensure that they are designing technologies with worker health and safety issues in mind. General guidance should be also be prepared for DOE field offices that support technology development activities to ensure that they are aware of, and can provide guidance to, technology developers.

5.0 REFERENCES

Helminski, E. (editor). 1991. "OSHA Says DOE Has Not Adopted New Safety Culture." Weapons Monitor Complex 2:10:4-7, Exchange Publications, Washington, D.C.

Moran, R. D. 1991. "The Occupational Safety and Health Act." Environmental Law Handbook, 11th Ed., Government Institutes, Inc.

National Institute of Occupational Safety and Health (NIOSH), Occupational Safety and Health Administration (OSHA), U.S. Coast Guard (USCG), and U.S. Environmental Protection Agency (EPA). 1985. Occupational Safety and Health Guidance Manual for Hazardous Waste Site Activities. NIOSH No. 85-115, U.S. Department of Health and Human Services, Atlanta, Georgia.

U.S. Department of Energy (DOE). 1991a. Engineering Evaluation of the 618-9 Burial Ground Expedited Response Action. DOE/RL-91-38 Draft B, DOE, Richland, Washington.

U.S. Department of Energy (DOE). 1991b. Expedited Response Action Proposal (EE/CA R EA) for the 200 West Area Carbon Tetrachloride Plume. DOE/RL-91-32 Draft B, DOE, Richland, Washington.

APPENDIX A

QUESTIONNAIRE

APPENDIX A

QUESTIONNAIRE

Site name _____
Name of interviewee _____
Position _____
Telephone number _____
Affiliation _____

I. Site Description:

1. Provide a description of the past activities that have occurred at this site related to the targeted activity.
 - a. What activities have occurred to date?
 - b. What other activities are planned for this site?
 - c. What are the contaminants of concern? In which media are can they be found?

II. Regulatory and Institutional Framework:

1. Which regulatory agencies are involved with occupational safety and health (OSH) issues related to the site?
 - a. Federal
 - b. State
 - c. Local

What other organizations are involved on the site related to OSH? What is their level of involvement?

- a. unions
- b. NGOs
- c. universities
- d. others

2. To what extent have the regulators been involved with past OSH activities?

- a. periodic reviews or monitoring
- b. meetings
- c. informal discussions
- d. other _____

3. What were the results or major findings of those reviews?

4. With which issues are the regulators most concerned?

5. How do you keep up to date on OSH regulations?

6. Are you provided with adequate information on OSH?

7. Who decides if you have adequate information?

8. Have you identified any gaps/overlaps in the guidance?

9. Who is responsible for implementing the OSH regulations?

- a. COCO/GOCO
- b. contractors

10. Has the change in some contractors role from "operations" to "remediation" impacted OSH activities? In what way(s)?

III. OSH Findings

What type of OSH documentation is maintained? Who maintains it?

1. Do you have an OSH plan?

2. Who prepared it?

3. What is the background of the people who prepared the plans?
4. When was it prepared? How often is it updated?
5. What data/information was used when it was prepared?
6. Does it contain any contingency plans? Have they ever been used?
7. To what degree is the OSH plan used to set milestones? Meet milestones?
8. What are the major elements contained in an OSH plan?
Is it a standard form? If not, please explain.
9. Have any OSH risks identified on the site resulted in a major milestone not being met? Explain.
10. What criteria are used to decide if something is an OSH issue?
11. Who decides?
12. Personal Protective Equipment (PPE)
 - a. Who decides which equipment to use?
 - b. Where is this equipment obtained?
 - c. In radioactive areas, who decides which equipment to use and the length of time a worker may be in an area?
 - d. What are the limitations, if any, regarding PPE.
13. Have there been any OSH incidents related to this site?
Explain (categories).
14. Have any unexpected OSH events arisen during the cleanup phase? Have any "seasonal issues" arisen? Explain.

DISTRIBUTION

No. of
CopiesNo. of
CopiesOFFSITE

12 DOE/Office of Scientific and
Technical Information

2 Bartlesville Project Office
P.O. Box 1395
220 N. Virginia
Bartlesville, OK 74005
ATTN: A. Crawley
T. Wesson

E. Bean
Kansas City Area Office
P.O. Box 410202
Kansas City, MO 64141-0202

J. Bellows
Los Alamos Area Office
528 35th St.
Los Alamos, NM 87544

3 Bonneville Power
Administration
P.O. Box 3621
Portland, OR 97208
ATTN: A. Morrell
S. Sander
B. Sherer

Jack Craig
FEMP
P.O. Box 398704
Cincinnati, OH 45239-8704

W. Jamison
U.S. Department of Energy
Western Area Power
Administration
P.O. Box 3402
Golden, CO 80401

G. Johnson
Pinellas Area Office
P.O. Box 2900
Largo, FL 34649

B. Kaiser
U.S. Department of Energy
Nevada Operations Office
Yucca Mountain Project Office
P.O. Box 98518
Las Vegas, NV 89193-8518

J. Keller
Naval Petroleum Reserves in
California
P.O. Box 11
Tupman, CA 93276

M. Keller
Pittsburgh Energy Technology
Center
P.O. Box 10940
Pittsburgh, PA 15236-0940

D. McCollum
Morgantown Energy Technology
Center
P.O. Box 880
3610 Collins Ferry Rd.
Morgantown, WV 26507-0880

W. R. Miller
Morgantown Energy Technology
Center
P.O. Box 880
3610 Collins Ferry Road
Morgantown, WV 26507-0880

J. Morley
U.S. Department of Energy
Dayton Area Office
P.O. Box 66
Mearnesburg, OH 45342-0066

No. of
Copies

D. Newquist
Naval Petroleum Reserves in
California
800 Werner Ct, Suite 342
Casper, WY 82601

P. Ramey
U.S. Department of Energy
Amarillo Area Office
P.O. Box 30030
Amarillo, TX 79120-0030

Remedial Action Program
Information Center
Building 200
P.O. Box 2008
Oak Ridge, TN 37831-6050

A. Seepo
Schenectady Naval Reactors
Office
P.O. Box 1069
Schenectady, NY 12301

E. Shollenberger
Pittsburgh Naval Reactors
Office
P.O. Box 109
W. Mifflin, PA 15122-0109

2 Southwestern Power
Administration
P.O. Box 1619
Tulsa, OK 74101
ATTN: D. Hayes
J. Lloyd

Strategic Petroleum Reserve
Project Office
Project Management Office
900 Commerce Road E.
New Orleans, LA 70123

No. of
Copies

5 U.S. Department of Energy
Albuquerque Operations Office
P.O. Box 5400
Albuquerque, NM 87115
ATTN: J. Bickel
A. Chernoff
D. Krenz
R. Sena
J. Themelis

2 U.S. Department of Energy
Albuquerque Operations Office
Uranium Mill Tailings Remedial
Actions Project Offices
P.O. Box 5400
Albuquerque, NM 87115
ATTN: M. Matthews, Jr.
T Plessinger

3 U.S. Department of Energy
Chicago Operations Office
9800 South Cass Avenue
Chicago, IL 60439
ATTN: B. Fritz
J. Haugen
J. Kennedy

53 U.S. Department of Energy
1000 Independence Ave.
Washington, DC 20585
ATTN: T. Barbosa, EH-40
R. Berube, EH-20
C. Bradley, NE-33
R. Bradley, S-1
S. Brocoum, RW-22
S. Cowan, EM-30
R. Dailey, EH-231
H. Delaplane, FE-421
W. Dennison, GC-11
J. Disbrow, EI-531
C. Ebbecke, NP-20
J. Farley, ER-8.2

No. of
Copies

J. Fiore, EM-42
 R. Fleming, EM-431
 J. Ford, DP-63
 C. Frank, EM-50
 S. Frank, NP-54
 R. Gisch, NE-60
 K. Goodwin, DP-161
 P. Grimm, EM-2
 C. Halsted, DP-13
 S. Hanna, PA-3
 D. Isbell, EM-431
 D. Jewett, FE-222
 R. Jones, EH-41
 A. Joseph, ER-40
 J. Knight, DP-12
 R. Langum, EM-431
 R. Lightner, EM-45
 J. Lytle, EM-30
 C. Magnuson, EM-431
 S. Mann, EM-44
 W. Mess, ER-20
 R. Moore, EI-23.1
 D. Moses, PE-70
 H. Myers, CE-64
 G. Parker, RW-333
 R. Peterson, DP-222
 H. Pettengill, EH-40
 T. Pflaum, DP-3
 S. Richardson, DP-60
 R. Scott, EM-20
 G. Sherwood, NE-12
 D. Smith, EM-6
 L. Stevens, EM-33
 P. Strider, EM-431
 D. Swink, FE-4
 T. Traceski, EH-231
 G. Turi, EM-433
 P. P. Whitfield, EM-40
 W. Wisenbaker, EM-43
 R. Wood, ER-74
 J. Yates, ER-42

No. of
Copies

5 U.S. Department of Energy
 Idaho Operations Office
 785 DOE Place
 Idaho Falls, ID 83402
 ATTN: J. Barry
 P. Hinman
 J. Lyle
 W. Sato
 J. Zimmerman (INEL)

4 U.S. Department of Energy
 Nevada Operations Office
 P.O. Box 98518
 Las Vegas, NV 89193-8518
 ATTN: B. Church
 D. Elle
 J. Fiore
 S. Mellington

5 U.S. Department of Energy
 Oak Ridge Operations Office
 P.O. Box 2001
 Oak Ridge, TN 37831
 ATTN: S. Garland (ORNL/ER)
 P. Gross
 H. W. Hibbitts
 A. Perkins
 R. Sleeman

5 U.S. Department of Energy
 Rocky Flats Office
 P.O. Box 928
 Golden, CO 80402-0928
 ATTN: S. Grace
 J. Hartman
 F. Lockhart
 T. Lukow
 R. Schassburger

No. of
Copies

- 4 U.S. Department of Energy
San Francisco Operations
Office
1333 Broadway
Oakland, CA 94612
ATTN: J. Cullen
J. Davis
J. Juettan
M. Kamiya
- 4 U.S. Department of Energy
Savannah River Operations
Office
P.O. Box A
Aiken, SC 29802
ATTN: L. Goidell
T. Heenan
L. Sjostrum
S. Wright
- 2 U.S. Department of Energy
Waste Isolation Pilot Plant
Project Office (WIPP)
P.O. Box 3090
Carlsbad, NM 88221
ATTN: A. Hunt
J. Newhinney
- B. Vocke
Los Alamos National Laboratory
HSE/DO/ER MS K481
P.O. Box 1665
Los Alamos, NM 87545
- R. Waldman
U.S. Department of Energy
Alaska Power Administration
2770 Sherwood Ln #2B
Juneau, AK 99801-8545

ONSITE

- 6 DOE Richland Operations Office
- E. A. Bracken, A5-19
R. M. Carosino, A4-52
R. D. Freeberg, A5-19

No. of
Copies

- R. G. Holt, A5-15
R. D. Izatt, A5-15
L. E. Little, A5-22
- 4 Battelle Washington Office
- W. E. Fallon
J. D. Longstreth
R. D. Quinn
J. E. Shorett
- 2 Environmental Management
Operations (EMO)
- J. Hartly
T. Page
- 5 Westinghouse Hanford Company
- M. R. Adams, H4-55
J. G. Fidds, H4-55
K. Leonard, B2-19
T. Wincest, H4-55
J. G. Woolard, H4-55
- 24 Pacific Northwest Laboratory
- J. P. Amaya, K6-55
G. R. Bilyard, K6-26
C. A. Geffen, K6-52
J. F. Keller, K1-21
A. M. Lesperance, K6-26 (10)
M. D. McKinney, K6-63
P. L. Miller, K6-26
R. D. Quinn, K6-59
M. R. Siegel, K6-26
Publishing Coordination
Technical Report Files (5)

END

DATE
FILMED

4 / 7 / 93