PNL--8426

PNL-8426
UC-310

DE93 009078

RECEIVED
MAR 11 1993
OSTI

IMPACT EVALUATION OF AN ENERGY SAVINGS PLAN
PROJECT AT SATHER MANUFACTURING

G. P. Sullivan
G. E. Spanner

December 1992

Prepared for
Sheila Riewer,
Program Evaluation Section,
Office of Energy Resources,
Bonneville Power Administration,
the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830

Pacific Northwest Laboratory
Richland, Washington 99352

MASTER

ds
DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor Battelle Memorial Institute, nor any of their employees, makes any warranty, expressed or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof, or Battelle Memorial Institute. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

PACIFIC NORTHWEST LABORATORY
operated by
BATTELLE MEMORIAL INSTITUTE
for the
UNITED STATES DEPARTMENT OF ENERGY
under Contract DE-AC06-76RLO 1830

SUMMARY

This impact evaluation of an energy conservation project that was recently installed at Sather Manufacturing (Sather) was conducted for the Bonneville Power Administration (Bonneville) as part of an evaluation of its Energy Savings Plan (ESP) Program. The Program makes acquisition payments to firms that install ECMs in their industrial processes. The objective of this impact evaluation was to assess how much electrical energy is being saved at Sather as a result of the ESP and to determine how much the savings cost Bonneville and the region.

The impact of the project was evaluated with a combination of engineering analysis, financial analysis, interviews, and submittal reviews (Sather's Proposal and Completion Report). The project consists of replacing an old coreless induction furnace with a new, more efficient, induction furnace.

Energy savings from this project are expected to be 1,122,000 kWh/yr, or 0.13 average megawatts. On a per-ton basis, this project will save 447 kWh/ton, which is a reduction of approximately 41% of electricity consumed per ton of steel produced. The project cost \$293,469 to install, and Sather received payment of \$123,780 from Bonneville for the acquisition of energy savings. Based on a simple payback analysis calculated by Pacific Northwest Laboratory and conversations with Sather management personnel, it was determined that this project would not have been implemented without the acquisition payment from Bonneville. The levelized cost of these energy savings to Bonneville will be 10.8 mills/kWh over the project's expected 15-year life, and the levelized cost to the region will be 24.9 mills/kWh.

CONTENTS

SUMMARY	iii
1.0 INTRODUCTION	1.1
1.1 APPROACH FOR IMPACT EVALUATION	1.2
1.2 PROJECT DESCRIPTION	1.2
1.3 SUMMARY OF PROJECT IMPACTS	1.4
2.0 IMPACT EVALUATION	2.1
2.1 ENERGY SAVINGS AND FUEL SWITCHING	2.1
2.2 IMPACTS TO THE FIRM	2.2
2.3 IMPACTS TO THE UTILITY	2.3
2.4 LEVELIZED COSTS	2.3
2.4.1 Bonneville Perspective	2.4
2.4.2 Regional Perspective	2.4
2.5 IMPACT ATTRIBUTABLE TO E\$P	2.4
3.0 REFERENCES	3.1
APPENDIX A - FINANCIAL EVALUATION DETAILS	A.1
APPENDIX B - COVER SHEET FROM SATHER MANUFACTURING'S PROPOSAL	B.1

IMPACT EVALUATION OF AN ENERGY SAVINGS
PLAN PROJECT AT SATHER MANUFACTURING

1.0 INTRODUCTION

This letter report describes Pacific Northwest Laboratory's (PNL's)^(a) evaluation of the impact of an energy conservation project installed at Sather Manufacturing (Sather) in Everett, Washington. The project at Sather is one of about thirty energy conservation projects to have its impact evaluated by PNL. All of the projects have received or will receive acquisition payments from the Bonneville Power Administration (Bonneville) under the Energy Savings Plan (ESP) Program.

The ESP is being offered to acquire electrical energy savings in the industrial sector of the Pacific Northwest. For the Sather project, the acquisition payment offered under the program was equal to the lesser of 15¢/kWh estimated to be saved in the first year or 80% of eligible project costs.

The general objective of the impact evaluation was to determine how much electrical energy is saved by the project and at what cost to Bonneville and to the region. In support of this general objective, answers were sought to the following questions:

1. How much electrical energy is saved annually by the energy conservation project in terms of kilowatt-hours, kilowatt-hours per unit of plant output, and average megawatts (aMW)? Also, did any fuel switching result from implementing this project?
2. If the project improved the productivity of the process, did the firm then increase output of the process to take advantage of the productivity improvement? Did the change in output result in a net increase or decrease in energy used by the process? Did the change in output cause changes in output at the firm's other plants in the region?

(a) Pacific Northwest Laboratory is operated for the U.S. Department of Energy by Battelle Memorial Institute under Contract DE-AC06-76RLO 1830.

3. What was the net impact to the serving utility in terms of electrical energy consumption (in kilowatt-hours) from implementing the project?
4. What are the levelized costs of the project from the perspectives of Bonneville and the region?
5. How much of the project's impact can be attributed to the E\$P?

1.1 APPROACH FOR IMPACT EVALUATION

Before selecting individual energy conservation projects for impact evaluation, PNL developed a general impact evaluation methodology (Spanner et al. 1988). The major finding of the methodology development was that in the industrial sector, energy conservation projects must be evaluated on a case-by-case basis. Accordingly, the general methodology consists of a variety of impact evaluation techniques that can be applied to individual projects according to the specific circumstances.

To evaluate the impact of replacing an existing induction furnace with a new furnace at Sather, five techniques were selected from the general methodology: engineering analysis, financial analysis (see Appendix A), site visit and interview, vendor interview, and review of Sather's submittals. On-site submetering by PNL was not necessary because the metering performed by Sather (utility billing records) in accordance with E\$P program requirements is adequate to determine the project's impact.

Representatives from PNL visited Sather on July 15, 1992, to view the project firsthand and to interview the president of the firm.

1.2 PROJECT DESCRIPTION

Sather is a jobbing iron foundry which produces grey- and ductile-iron castings. Sather's primary products are manhole frames and covers of varying sizes. To a lesser degree, Sather produces custom cast parts for a variety of industries. Sather melts scrap metal and then uses the sand-casting process to cast manholes and custom parts. The foundry consists of two furnaces (each run on alternate days), a power supply, a muller (sand mixing equipment), a compressor, conveyors, and various auxiliary pumps and fans.

The energy conservation project at Sather replaced a 12-year-old, Pillar-580-kW, coreless induction furnace with a new, more efficient, Inductotherm-600-kW, coreless induction furnace. The old furnace was experiencing technical problems that required a charge of iron to be melted at a much slower rate (longer cycle time), while calling for an electrical demand about equal to the new furnace. The technical problem, never fully understood by either the manufacturer (Pillar) or Sather personnel, also required periodic replacement of expensive power controlling circuitry. Included in the new installation were the two furnace assemblies, a power supply, and the required air and water cooling systems. According to Sather personnel, the new furnace, although having a higher capacity, will continue to be operated at the current average production of approximately 10 tons per day.

The energy savings in this project result in a reduction in energy consumption per unit of iron melted by reducing the production time (from 20.5 hours to 12.5 hours) required to melt the average daily production of 10 tons. This eight-hour reduction in production time decreases the time that the auxiliary equipment (bag-house, blowers, muller, compressor, and conveyors) needs to operate. Another benefit of installing the new furnace is that the power factor was significantly increased by over 14%, from approximately 0.83 to 0.95.

Sather submitted two documents to Bonneville: a Proposal and a Completion Report. The Proposal described the project and presented Sather's cost and benefit expectations. A Completion Report was submitted to Bonneville after the project was installed and Sather had verified the resulting energy savings. This document listed the actual costs of the project along with a calculation of the energy savings that had been achieved. A copy of the cover sheet from the Completion Report is included as Appendix B.

The total cost of this project was \$293,469 and Bonneville paid \$123,780 (15¢/estimated kWh saved in the first year) for the energy saved. Sather pays approximately 5¢/kWh for electricity.

1.3 SUMMARY OF PROJECT IMPACTS

This E\$P project is expected to save 1,122,000 kilowatt-hours annually (0.13 aMW). Over the assumed 15-year life of this project, levelized costs to Bonneville will be 10.8 mills/kWh (1 mill = 1/1000 of a dollar), and cost to the region will be 24.9 mills/kWh. These costs are in real dollars and do not include additional savings that accrue if transmission and distribution losses are considered. The levelized cost to Bonneville including transmission and distribution losses will be 10.1 mills/kWh, and the cost to the region will be 23.2 mills/kWh.

Without the acquisition payment from Bonneville, this project did not meet Sather's funding criteria; however, it did meet the criteria with the acquisition payment. Therefore, we conclude that it would not have been installed in the absence of the E\$P.

2.0 IMPACT EVALUATION

The following section addresses the five major objectives of the impact evaluation as stated in the introduction.

2.1 ENERGY SAVINGS AND FUEL SWITCHING

1. How much electrical energy is saved annually by the project in terms of kilowatt-hours, kilowatt-hours per unit of plant output, and average megawatts? Also, did any fuel switching result from implementing this project?

Energy Savings

To verify savings for this project, electric meter readings were taken two weeks before and two weeks after the project installation; the difference in these readings represents the savings over the two-week period. These electric savings were then extrapolated over the entire year, resulting in a yearly savings of 1,441,000 kWh. The calculations in the Completion Report assumed a constant production level during the metering periods and 52 full weeks of production per year.

In discussions with Sather personnel, PNL learned more detailed information about production levels during metering and annual operating schedules. First, Sather provided the actual production numbers during the two-week metering periods. For the two weeks before installation, Sather reported 223,962 pounds (11.2 tons/day) produced; for the two weeks after the installation, Sather reported 207,230 pounds (10.4 tons/day). Secondly, Sather explained that yearly production is reduced by 9 days taking into account holidays and downtime. And lastly, to extrapolate the energy savings over the whole year, PNL used an average daily production of 10 tons as reported by Sather. PNL used this information in conjunction with the meter readings to arrive at an estimated yearly electricity savings of 1,122,000 kWh (0.13 aMW). While this represents a reduction in the savings value as compared with the Completion Report, it is still significantly above the 868,032 kWh/year estimated in the proposal.

On a per-ton basis, this project will save 447 kWh/ton, which is a reduction of approximately 41% in electricity consumed per ton of steel produced.

Fuel Switching

Fuel switching to a natural gas furnace was a possibility for Sather; however, because of pollution regulations it was not considered feasible.

2.2 IMPACTS TO THE FIRM

2. If the project improved the productivity of the process, did the firm then increase output of the process to take advantage of the productivity improvement? Did the change in output result in a net increase or decrease in energy used by the process? Did the change in output cause changes in output at the firm's other plants in the region?

Installation of this project did improve the productivity (steel produced per kWh consumed) of the production process by reducing the time required to melt the iron. Sather, even though it now has the ability to increase production, expects production to remain constant at 10 tons/day for the foreseeable future. The output at Sather is determined largely by market conditions, which are not expected to change significantly. If market conditions do eventually change for the better, however, Sather will increase output in response.

Either the furnace or the molding department could be the limiting factor to Sather's output, depending on the product mix manufactured at the plant. Even with the old furnace, Sather had excess capacity to increase output a certain amount because that furnace ran 20.5 hours/day. The new furnace, which runs for only 12.5 hours/day, will allow a greater increase in output than the old furnace. In summary, output at Sather might increase in the future, but it will be the result of changes in market conditions, not the replacement of the furnace. If output does eventually increase, the iron will be produced with 447 kWh/ton less electricity than it was before the furnace was replaced.

Sather has no other plants in the region that perform this type of metal casting, so no impacts will occur at other plants.

2.3 IMPACTS TO THE UTILITY

3. What is the net impact to the serving utility in terms of electrical energy consumption (in kilowatt-hours) from implementing the project?

Because this project had no cogeneration or other complicating factors, all of the energy savings from this project will be reflected in reduced load at the utility, Snohomish County Public Utility District, the net impact to the servicing utility from this project will be a 1,122,000 kWh/yr reduction in electrical load.

2.4 LEVELIZED COSTS

4. What are the levelized costs of the project from the perspectives of Bonneville and the region?

Levelized annual costs are used to compare the attractiveness of various projects or investment alternatives. The levelized cost is the annual cost that would be incurred over the life of the project, accounting for the time value of money. (See Appendix A for complete definitions and formula.) Levelized costs provide a single figure of merit for comparing energy conservation alternatives. In addition, levelized costs can be used to compare conservation projects with options for new generating capacity and to optimize the ranking of these options. The objective of using levelized costs to evaluate these energy conservation projects is to determine the financial impact of each project to Bonneville (\$/kWh saved) and to the region (Bonneville and Sather levelized cost combined).

In the industrial sector, it is not possible to accurately predict the life of an energy conservation project because any number of external factors could cause the project to have longer or shorter life than expected when it is installed. To allow comparisons of levelized costs among projects installed under the E\$P, all projects are assumed by PNL to have a life of 15 years. Even though some projects will have longer or shorter lives, 15 years is considered a conservative but likely life for typical energy conservation projects in the industrial sector.

2.4.1 Bonneville Perspective

To determine the levelized costs to Bonneville and to the region, we must know the project costs (acquisition payment, capital costs, etc.) and the energy savings, and must assume a discount rate and project life. With energy savings of 1,122,000 kWh/yr, the project's levelized cost from Bonneville's perspective will be 10.8 mills/kWh (see Appendix A). Bonneville's levelized cost decreases to 10.1 mills/kWh when transmission and distribution losses are considered. These losses increase the energy savings at the point of generation by 7.5%.

The levelized costs calculated in this impact evaluation include the acquisition payment by Bonneville as well as the administrative and evaluation costs associated with this project.

2.4.2 Regional Perspective

To calculate the levelized cost to the region, the costs to Bonneville and Sather are combined. The acquisition payment by Bonneville is included as a cost to Bonneville and as a reduction in cost to Sather. This approach is taken because the acquisition payment has federal income tax consequences to the company and, therefore, is not a net zero cost to the region.

The levelized costs to the region for acquiring annual energy savings of 1,122,000 kWh is 24.9 mills/kWh saved. Including transmission and distribution losses, the levelized cost decreases to 23.2 mills/kWh saved.

2.5 IMPACT ATTRIBUTABLE TO E\$P

5. How much of the project's impact can be attributed to the E\$P?

Sather uses simple payback to select plant improvement projects, but it does not have a predetermined threshold that a project must meet for implementation. When this project was proposed to Bonneville, it was expected to cost \$290,990 and result in electrical cost savings of \$43,400/yr ($868,032 \text{ kW/yr} \times \$0.05/\text{kWh} = \$43,400/\text{yr}$) for a simple payback of about 6.7 years based solely on energy savings. Sather had considered this project for several years, but it became feasible only after Bonneville's payment of \$123,780 reduced the simple payback to 3.9 years.

Considering the facts presented above, we conclude that this project would not have been implemented without the acquisition payment from Bonneville and that all of the project's impact can be attributed to the ESP.

3.0 REFERENCES

Spanner, G. E., D. R. Brown, D. R. Dixon, B. A. Garrett, R. W. Reilly, J. M. Roop, and S. A. Weakley. 1988. Potential Techniques for Evaluating the Impact of Industrial Energy Conservation Projects under Bonneville's Energy Savings Plan. Letter Report. PNL-6628, Pacific Northwest Laboratory, Richland, Washington.

APPENDIX A

FINANCIAL EVALUATION DETAILS

APPENDIX A

FINANCIAL EVALUATION DETAILS

A.1 DEFINITIONS

Levelized Cost - A single figure of merit that expresses the cost per unit of benefit (in this case, energy savings) accounting for the time value of money. This annualized cost would be constant over the entire project life. An infinite number of cash flow scenarios (costs incurred at different times in the project life) could result in the same annualized cost.

Levelized Cost to Bonneville Power Administration (Bonneville) - The annualized costs to Bonneville, direct and indirect, per unit of energy saved by the conservation project. Costs included are the acquisition payment and the program administrative costs, as well as the costs to evaluate the impact of this project.

Levelized Cost to the Region - The sum of annualized costs to Bonneville, Snohomish County PUD, and Sather Manufacturing (Sather) per unit of energy saved by the energy conservation project. This would include the same costs to Bonneville as above, plus the initial capital and ongoing incremental production costs to the firm. Any non-electrical savings that result from the project are not considered in this analysis.

A.2 LEVELIZED COST FORMULA

$$LC = \{ [PVC I + PVIC I + (PVOM + PVPT + PVOTE) \cdot (1-itf) - PVD \cdot itf] / (1-itf) \} \cdot (CRF/AES)$$

where LC = levelized cost (real \$)

PVCI = present value of initial capital costs

PVICI = present value of interim capital costs

PVOM = present value of operating and maintenance (O&M) costs

PVPT = present value of property taxes

PVOTE = present value of one-time expenses

itf = combined state and federal income tax fraction

PVD = present value of depreciation

CRF = capital recovery factor (spreads the costs over the project life in real dollar terms)

AES = annual energy savings (kWh/yr).

A.3 GENERAL ASSUMPTIONS

The following general assumptions were made in the levelized cost calculations:

1. All cash flows are expressed in nominal terms (with inflation) and are discounted to present value at a nominal discount rate of 8.15% (combines a real discount rate of 3.0% and an inflation rate of 5.0%). The costs are annualized over the life of the project using the capital recovery factor at a real discount rate of 3.0%.
2. Equal annual energy savings (kilowatt-hours/year) is constant over the life of the project. This assumes no loss in efficiency of the equipment with time.
3. Transmission and distribution losses equal 7.5%, increasing the energy savings at the source by a corresponding 7.5%.
4. In the regional cost calculation, the acquisition payment from Bonneville is treated as a cost to Bonneville and, at the same time, a cash inflow to Sather rather than a net zero cost. This is done because Sather will incur a tax liability from the acquisition payment, thus a net cost to the region.

A.4 BONNEVILLE LEVELIZED COST CALCULATIONS

Input: one-time expenses

Acquisition payment paid (year 0) = \$123,780

Administrative and evaluation costs (year 0) = \$20,378

Tax rate = 0%

Energy savings (annual) = 1,122,000 kWh

Output: levelized cost = 10.8 mills/kWh

A.5 REGIONAL LEVELIZED COST CALCULATIONS (BONNEVILLE + SATHER)

A. Sather

Input: initial capital

Equipment = \$293,469

One-time expenses (revenues)

Acquisition payment received = (\$123,780)

Tax rate = 30%

Project life = 15 years

Depreciation = 5 years

Energy savings (annual) = 1,122,000 kWh

Output: levelized cost = 14.1 mills/kWh

B. Regional levelized cost = Bonneville levelized cost + Sather levelized cost

= 10.8 mills/kWh + 14.1 mills/kWh

= 24.9 mills/kWh

A.6 LEVELIZED COSTS ALLOWING FOR TRANSMISSION AND DISTRIBUTION LOSSES

Input: transmission and distribution losses = 7.5%

Bonneville levelized cost = 10.8 mills/kWh/1.075 = 10.1 mills/kWh

Regional levelized cost = 24.9 mills/kWh/1.075 = 23.2 mills/kWh

APPENDIX B

COVER SHEET FROM SATHER MANUFACTURING'S PROPOSAL

Cover Sheet

Requirement 2.

PROPOSAL

I. Project

Project Title: Melting Furnace Replacement

Categorically Excluded: (See Attachment 2, Program Description Booklet)

Technologies:

Coreless Induction Melting

Yes

No

☐☒☐☐☐☐☐☐☐☐☐☐

RECEIVED

MAY - 2

TBA

Confidential or Proprietary Information: ☐ Yes ☒ No

Industry

FOUNDRY

Name: Sather Mfg. Co., Inc.

Address: 3330 McDougall Ave.

City: Everett

State: WA Zip: 98201

Attention: (206) 259-5133
Aron Stephenson

Contact:

☒ Same as Industry contact

☐ Utility Representative, if utility-operated program

Name: Ken Satre

Phone: 206-347-1737 EXT 1891

SIC Code: 991

Utility Service Area: Snohomish County PUD

Utility-Operated Program: ☒ Yes ☐ No

II. Project Summary

A Brief Project(s) Description: We would replace our existing 12 year old 580 KW coreless induction melting furnace with a new 600 KW unit. Because of the advances made in induction furnace technology, the new furnace would use much less energy to melt the same amount of metal. It would also melt much faster. Our daily production of 12 ton, which now takes 20½ hours, could be melted in 12½ hours. This would allow us to shut down our auxiliary equipment 8 hours sooner each day.

III. Estimated Energy Savings and Costs

Average Annual Energy Savings:

868,032 KWH

Total Project Cost:

290,990

Estimated Incentive:

123,694 ✓

END

**DATE
FILMED**

5 / 11 / 93