Derivative Classifier

RECEIVED

FEB 12 1993

OSTI

DEMONSTRATION OF
EASTMAN CHRISTENSEN
HORIZONTAL DRILLING SYSTEM
INTEGRATED DEMONSTRATION SITE
SAVANNAH RIVER SITE

Approved by:

D. B. Moore-Shedrow, Manager
Environmental Sciences Section

December 1992

Westinghouse Savannah River Company
Savannah River Technology Center
Aiken, South Carolina 29808

Prepared for the Department of Energy under Contract DE-AC09-89SR18035

MASTER

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P. O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401.

Available to the public from the National Technical Information Service, U. S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

TABLE OF CONTENTS

LIST OF ACRONYMS	iii
EXECUTIVE SUMMARY	iv
1.0 INTRODUCTION	1
1.1 M Area Basin Background and Description	1
1.2 Objectives	4
1.3 Technical Approach	5
2.0 GEOLOGIC SETTING	6
2.1 Regional Setting	6
2.2 A/M-Area Geology and Hydrogeology	7
2.2.1 Geology	7
2.2.2 Hydrogeology	10
3.0 DRILLING PROGRAM	14
3.1 Drilling Fluid System	14
3.2 Directional Drilling Tools	15
3.3 Drilling Procedure	18
3.4 Survey Methods	20
3.5 Filter Pack Installation	20
3.6 Well Development	21
4.0 WELL SUMMARIES	21
4.1 Vadose Zone Well (AMH-4)	26
4.1.1 AMH-4 First Attempt	26
4.1.2 AMH-4 Second Attempt	27
4.1.3 AMH-4 Third Attempt	28
4.1.4 AMH-4 Fourth Attempt	29
4.1.5 AMH-4 Fifth Attempt	30
4.1.6 AMH-4 Sixth Attempt	32
4.2 Water Table Aquifer Well (AMH-3)	34
4.2.1 AMH-3 First Attempt	34
5.0 COMPARISON OF TECHNOLOGIES FOR HORIZONTAL DRILLING	38
5.1 Advantages and Disadvantages	45
6.0 CONCLUSIONS AND RECOMMENDATIONS	48
REFERENCES	REF 1
APPENDICES	
Appendix A - Detailed Well Plans	
Appendix B - Integrated Demonstration Site Hydrogeologic Cross Section	
Appendix C - Survey Data	
Appendix D - Well Abandonment Reports	

TABLE OF CONTENTS (continued)

List of Figures

Figure 1.1	Site Location and Physiographic Setting	2
Figure 1.2	Horizontal Well Locations at the Integrated Demonstration Site	3
Figure 2.1	Stratigraphic Column for the SRS	8
Figure 2.2	Comparison of Chronostratigraphic, Lithographic, and Hydrostratigraphic Units at the SRS	11
Figure 2.3	Hydrostratigraphic Chart for the A/M Area	13
Figure 3.1	Bottom Hole Assembly (BHA)	16
Figure 3.2	Schematic of Downhole Motor with Stabilizers	17
Figure 3.3	Well Section Orientation and Associated Terminology	19
Figure 4.1	Plan and Cross-Sectional View of Well Attempts	22
Figure 4.2	AMH-4 Well Construction Diagram (Vadose Zone Well)	35
Figure 4.3	Wellhead Details for AMH-4	36
Figure 4.4	AMH-3 Well Construction Diagram (Water Table Aquifer Well)	39
Figure 4.5	Isometric and Plan View of Final AMH-3 and AMH-4 Boring Alignments	40

List of Tables

Table 4.1	Well Attempt and Completion Summaries	23
Table 4.2	Survey Data for Horizontal Well Attempts and Completions	24
Table 4.3	Drilling Condition Summaries of Each Installation Attempt	25
Table 5.1	Comparison of Short-Radius and ECES System Technologies	42
Table 5.2	Comparison of Drilling Performance	46

List of Acronyms

BHA	Bottom Hole Assembly
bls	below land surface
CaCl ₂	Calcium Chloride
DHM	Down-Hole Motor
ECES	Eastman Christensen Environmental Services
EOC	End of Curve
ft	feet
ft ³	cubic feet
gpm	gallons per minute
HDPE	High Density Polyethylene
ID	inside diameter
KOP	Kickoff Point
lbs	pounds
lbs/gal	pounds per gallon
MD	Measured Depth
OD	outside diameter
psi	pounds per square inch
SRTC	Savannah River Technology Center
SRS	Savannah River Site
SCWSR	South Carolina Well Standards and Regulations R.61-71
TFI	Tool Face Indicator
TVD	Total Vertical Depth
VOC	Volatile Organic Compound

EXECUTIVE SUMMARY

Demonstration of an innovative horizontal drilling technology was performed from February through June of 1991. The objective of this task was to demonstrate the application of an innovative directional drilling system to the installation of horizontal wells at the Integrated Demonstration Site located near the A/M Area of the Savannah River Site (SRS). The drilling system was designed by Eastman Christensen Environmental Services (ECES) and consisted of a downhole motor with directional control capabilities, electronic borehole surveying equipment, and an adjustable drill rig mast for drilling at angles less than vertical. Eastman Christensen (Houston, Texas) was contracted to perform well installation and SEC Donohue was contracted to provide technical oversight.

The two wells (AMH-3 and AMH-4) were designed to have horizontal sections of 300 feet. The target depths for the vadose zone and water table aquifer well were 105 (+10) feet below land surface (ft bls) and 150 (+10) ft bls, respectively. Both wells were constructed of a 14-inch diameter steel conductor pipe installed to a shallow (20 ft bls) kickoff point (KOP), followed by a 10-inch diameter polyethylene casing installed to the end of the curve (EOC), followed by a 6-inch diameter polyethylene casing/screen assembly in the horizontal section. The conductor pipe was installed using solid-stem augers, and the curve and horizontal sections of the well were installed using mud-rotary methods. The curved and horizontal sections of the boreholes were drilled using a bottom hole assembly (BHA) consisting of a tool face indicator (TFI), steerable downhole motor (DHM), and an underreamer wing bit.

The vadose zone well (AMH-4) was installed first to determine the effects of lost circulation and borehole stability in the unsaturated sediments. Due to the experimental nature of the demonstration project, six attempts at well installation were necessary before successful completion of the well. Field adjustments were made to address mechanical, electrical, and geological issues encountered. Specifically, drilling fluid rheology and circulation, skin friction between well casing/screen assembly and borehole, malfunctioning electronic survey equipment, and design of well casing materials were identified as major contributing factors which prevented successful well completion in the early attempts. In addition, initial drilling rates were too fast to allow sufficient removal of cuttings from the borehole. The time required to assemble rods and casing at the rig using

the rig hydraulics was slower than desired giving the stability of the borehole drilled by this method.

.

Several modifications to the drilling program were made prior to the successful completion of well AMH-4. The following changes resulted in the successful completion of well AMH-4 to a measured depth (MD) of 300 feet and 101 total vertical depth (TVD):

- Implementation of an engineered mud program consisting primarily of maintaining a low weight, high viscosity mud with polymers and bentonite extenders
- Drilling rates were reduced to less than 1 minute/foot on the lateral section to provide for sufficient circulation of drill cuttings from borehole
- Pull down pressures on the casing/screen assembly were reduced to prevent assembly from advancing over the drill bit
- A pilot hole was drilled for the lateral section without the casing/screen assembly before assembly installation

The water table aquifer well (AMH-3) was installed using the above modifications to the drilling program except the casing was installed as the boring was advanced. As a result, well AMH-3 was successfully installed on the second attempt.

A comparison of the short radius technology, used for the installation of wells AMH-1 and AMH-2, and the drilling system described herein, indicates that horizontal wells were placed with each technique. For comparative purposes, the drilling system described herein will be referred to as the ECES system. Upon weighing the advantages and disadvantages of each technology, the following criteria have been identified which make the ECES system preferable to short radius technology for the installing horizontal wells at the SRS:

- better steering and directional control of downhole drilling assembly for the installation of the curved and lateral section of the well

- greater directional accuracy by using real-time data for surveying
- less time consuming procedure for well drilling and installation

Although several mechanical, electrical, and geological problems were encountered which impeded well installation, problems of this type are inherent in any experimental drilling project. It should be noted that knowledge obtained during the course of installing well AMH-4 was applied in the installation of well AMH-3 which was successfully completed after two attempts. The following modifications and recommendations for future horizontal drilling projects of this type are based on information and knowledge gained through the course of this project:

- Begin the project with an engineered mud program and modify it as time and site specific conditions require
- Drill a pilot borehole of the horizontal section of the well prior to attempting to install the casing/screen assembly
- Simplify the mechanics of the drill rig to reduce the number of procedures required to drill, make connections and trip drill pipe
- Equip the drill rig with a more durable and powerful mud pumping system to increase fluid flow to decrease downtime due to mechanical failures
- Reduce the diameter of surface casing and well casing. Use of smaller boreholes would enhance hole stability and facilitate removal of cuttings

This project demonstrated the application of the second of two technologies for installing horizontal wells in unconsolidated sediments at the SRS. The project identified the advantages of the ECES system relative to short radius technology, the other proven technique for installing horizontal wells in the unconsolidated sediments at the SRS. Cooperation among members of the field team resulted in recommendations for improved use of this technique.

The knowledge gained in this and the short radius technology study is key to implementation of horizontal well technology in the field. Such advances are essential to achieving faster, more effective remedial actions in the DOE complex and throughout the regulated community.

1.0 INTRODUCTION

An innovative horizontal drilling system was used to install two horizontal wells as part of an integrated demonstration project at the Savannah River Site (SRS), Aiken, South Carolina. The SRS is located in south-central South Carolina in the upper Coastal Plain physiographic province (Figure 1.1). The demonstration site is located near the A/M Area, as shown on Figure 1.1, and is currently known as the Integrated Demonstration Site.

The Department of Energy's Office of Technology Development initiated an integrated demonstration of innovative technologies for cleanup of volatile organic compounds (VOCs) in soils and groundwater at the SRS in 1989. The overall goal of the program is to demonstrate, at a single location, multiple technologies in the fields of drilling, characterization, monitoring, and remediation. Innovative technologies are compared to one another and to baseline technologies in terms of technical performance and cost effectiveness. Transfer of successfully demonstrated technologies and systems to DOE environmental restoration organizations, to other government agencies, and to industry is a critical part of the program.

1.1 M-Area Basin Project Background and Description

Previous hydrologic investigations at SRS have shown that plant operations have resulted in the contamination of the groundwater with VOCs near the M-Area Settling Basin. Waste organic solvents were discharged to a process sewer line in M Area that discharged to the M-Area Settling Basin. Contamination of the vadose zone soils and the underlying groundwater with VOCs resulted from leaks in the process sewer line and from the settling basin itself. The layout of the site, including the locations of the completed horizontal wells, is shown on Figure 1.2. A remedial action program consisting of groundwater pumping followed by above-ground air stripping was implemented in 1985 to address groundwater contamination in M Area. However, residual concentrations of VOCs present in the vadose zone provide a continuous source of contaminants to the groundwater, and recent investigations have focused on identifying and implementing innovative remedial techniques to address removal of VOCs from both the soils in the vadose zone and the groundwater using in-situ technologies.

In order to test new remediation technologies, the Environmental Sciences Section of the Savannah River Technology Center (SRTC) performed a successful pilot study of an in-situ vacuum extraction system. The system removed significant quantities of VOCs from the vadose zone,

**DEMONSTRATION OF ECES
HORIZONTAL DRILLING SYSTEM
INTEGRATED DEMONSTRATION SITE, SRS**

**WSRC-TR-92-577
DECEMBER 1992**

FIGURE 1.1 SITE LOCATION AND PHYSIOGRAPHIC SETTING

**DEMONSTRATION OF ECES
HORIZONTAL DRILLING SYSTEM
INTEGRATED DEMONSTRATION SITE, SRS**

**WSRC-TR-92-577
DECEMBER 1992**

FIGURE 1.2 HORIZONTAL WELL LOCATIONS AT THE INTEGRATED DEMONSTRATION SITE

indicating the suitability of vapor extraction technology for the conditions present in M Area. This remedial design concept was incorporated into SRTC's horizontal vapor extraction/air injection well system. In an effort to increase the recovery rate of VOCs from the subsurface and to extend the zone of remediation below the water table, an air injection system was combined with the vacuum extraction design in the first set of horizontal wells (AMH-1 and AMH-2). Wells AMH-1 and AMH-2 are aligned approximately parallel to the process sewer line in a northerly direction, toward the M-Area Facility. Well AMH-2 was installed above the water table for vapor extraction and well AMH-1 was installed below the water table for air injection. Recent demonstrations using the horizontal wells at M Area have included in-situ remediation of VOCs from the groundwater and vadose zone soils using air stripping as well as nutrient injection for bioremediation. The innovative remediation systems have proven to be more effective in the removal of VOCs from the subsurface than conventional recovery well technology.

This report describes the well installation procedures, problems, and well construction details of two additional horizontal wells (AMH-3 and AMH-4) installed to the south of wells AMH-1 and AMH-2 (see Figure 1.2). Wells AMH-3 and AMH-4 follow the abandoned process sewer line in a southerly direction, toward the M-Area Seepage Basin.

Eastman-Christensen Environmental Services (ECES), (Houston, Texas) was the drilling contractor for the project and was employed for their directional drilling tools and drilling experience. ECES installed the first set of horizontal wells (AMH-1 and AMH-2) using short-radius technology. Subsequently, ECES designed a new system for environmental applications which consisted primarily of steerable downhole motor (DHM) technology. In addition, the drill rig was equipped with an adjustable mast for drilling at angles less than vertical. The prototype system was brought to the SRS for the first full-scale demonstration, and is referred to herein as the ECES system. SEC Donohue was retained to: (1) provide technical oversight, (2) document project activities, and (3) generate the well completion report.

1.2 Objectives

The objective of this task was to demonstrate an innovative directional drilling system that uses down-hole motor technology to install horizontal wells to specified depths and lengths. The two wells were designed to have horizontal sections of 300 feet, measured laterally from the end of the curve to the end of the well screen. The target depth for the shallow vadose zone well was 105 (± 10) feet below land surface (bls), and 150 (± 10) feet bls for the water table aquifer well.

1.3 Technical Approach

The procedures used incorporated technologies from the river crossing and petroleum drilling industries which were modified for environmental applications. Typically, piping or conduit is advanced using down-hole motors and down-hole electronic survey tools to direct the bit to arc. The length and jointing of the bottom-hole assembly (BHA) governs the radius of the arc, or curve. Modifications to the drilling procedure allowed a lateral section to be drilled after the curve was completed. The procedure required alternating the drill bit orientation periodically in the casing so that the bit would alternate drilling a curve up, then rotate and drill a curve down. The resultant lateral section of the well consisted of a series of consecutive concave and convex arcs. This procedure is explained in greater detail in Section 3.3.

Eastman-Christensen prepared initial well design for the proposed wells. The detailed well plans that were prepared prior to startup are included as Appendix A. Because this was the first full-scale field demonstration of the prototype system, many of the original well-design specifications were modified as the project progressed.

The technical approach for well design, drilling, and installation of the two wells was essentially the same for both. Target zones for the lateral sections of each well were selected using available geologic, geophysical and water quality data. The air injection well was targeted in the water table aquifer about 10-15 feet below the water table surface where elevated concentrations of VOCs have been identified in the groundwater. The vadose zone well was targeted just below a clayey zone known to contain a significant mass of the vadose zone contamination. This positioning for the vapor extraction well would allow a more complete sweep of the unsaturated zone during vapor extraction than was the case in the AMH-1 and AMH-2 system design.

The well design called for drilling a 16-inch diameter borehole using augers methods and subsequently installing a grouted-in-place 12-3/4-inch outside diameter (OD) steel surface casing (conductor pipe). This was to be followed by installation of the curved section of the well using the BHA and mud rotary drilling methods. The BHA consisted of a 12-1/4-inch rotary drill bit with expanding wings, a steerable down-hole motor (DHM), and the tool face indicator (TFI) which linked to the drill rods by a circulating sub. Ten-inch diameter solid High Density Polyethylene (HDPE) casing was to be advanced with the BHA as the borehole was drilled. Off-bottom single shot and multi-shot downhole surveys were to be performed on a regular basis during drilling of the curved sections to verify inclination and tool face orientation readings from the TFI. The radius of curvature for both wells was to be 110 feet. The measured depths (MD) of

the end of the curves (EOC) for the vadose zone and water table wells was to be 161 feet and 223 feet, respectively. Once the casing had been advanced to the targeted zone, the 10-inch diameter HDPE was to be grouted in place using a casing shoe, knuckle joint, and 2-7/8-inch diameter drill pipe.

The lateral portions of the borings were to be drilled utilizing the same BHA equipped with an 8-5/8-inch wing bit. A 6-inch OD casing/screen assembly was to be advanced with the BHA during drilling. Survey data from the TFI were to be continuously monitored during drilling as performed during curve installation. In addition, off-bottom, single-shot surveys were to be conducted periodically to insure proper borehole orientation, and a multi-shot survey of the entire borehole was to be performed upon completion of the boring. Both drilling and circulation of drilling fluid had to be suspended during each survey.

The curved and lateral sections were to be drilled using mud rotary techniques. The initial well plan called for the drilling fluid to be a bentonite and water mixture with a viscosity ranging from 40 to 45 seconds (Marsh funnel viscosity). The use of drilling fluid additives was not part of the original well plan.

The design called for an artificial filter media (HDPE beads) to be installed in the same manner as the grout using a casing shoe, knuckle joint, and 2-7/8-inch diameter drill pipe. The artificial filter media was to be capped with neat cement grout to land surface.

The shallow vadose zone well (AMH-4) was to be installed first to investigate the effects of lost circulation and borehole stability in dry sediments before applying the technology in the saturated sediments. Lessons learned during the installation of the vadose zone well would be applied during the installation of the water table well.

2.0 GEOLOGIC SETTING

2.1 Regional Setting

The Savannah River Site is located on the Aiken Plateau in the Upper Atlantic Coastal Plain Physiographic Province (see Figure 1.1). The Aiken Plateau is bounded by the Savannah and Congaree Rivers, is dissected by streams, and is characterized by broad interfluvial areas with narrow steep-sided valleys.

The Atlantic Coastal Plain is comprised of a wedge of southeast-dipping unconsolidated and semi-consolidated sediments, which increase in thickness from zero at the Fall Line to more than 4,000 feet near the Atlantic Coast. These sediments range from Late Cretaceous (≈ 100 million years) to Holocene (present) in age and extend to the seaward edge of the Continental Shelf. The Coastal Plain sediments generally consist of strata of gravel, sand, silt, clay, and limestone, which were deposited in a variety of fluvial, deltaic, and marine depositional environments. The base of the Coastal Plain sediments lies unconformably on top of crystalline metamorphic and granitic rocks in the northern portion of the SRS, and on top of Triassic sedimentary rocks, deposited in a rift basin, in the southern part of the SRS.

2.2 A/M-Area Geology and Hydrogeology

Extensive hydrogeologic information is currently available for the A/M Area. Horizontal well design for the Integrated Demonstration Site was based on the site hydrogeology and the known contaminant plume geometry. The following summary is based on a review of the available literature and information on the A/M Area.

2.2.1 *Geology*

The subsurface geology underlying SRS includes crystalline basement rock overlain by approximately 900 feet of Cretaceous and younger Coastal Plain sediments (Siple, 1967). Wells near A/M Area indicate basement rock occurs at an elevation of about 400 feet below msl (approximately 750 feet bls). The coastal plain sediments were laid down and reworked as the result of a periodic process of sea level rise and fall. During periods of high sea level, sands and clays were deposited. As sea level receded, the sediments were exposed to periods of erosion. The result is an interbedded sequence of sands and clays. The sedimentary units thin westward, toward the Fall Line.

The Coastal Plain stratigraphic units, from oldest to youngest, are the Cape Fear Formation, the Lumbee Group, the Black Mingo Group, the Orangeburg Group, and the Barnwell Group (Figure 2.1). Since the horizontal wells discussed in this report are constructed only in the upper geologic units above a clay unit known as the "green clay", only the upper geologic units are discussed in this section (in ascending order). A detailed description of the A/M-Area geology is provided in WSRC (1992a).

**DEMONSTRATION OF ECES
HORIZONTAL DRILLING SYSTEM
INTEGRATED DEMONSTRATION SITE, SRS**

**WSRC-TR-92-577
DECEMBER 1992**

Modified from Aadland and Bledsoe, 1990

FIGURE 2.1 STRATIGRAPHIC COLUMN FOR THE SRS
(From WSRC-TR-92-355)

Orangeburg Group

The Orangeburg Group (Middle Eocene) is subdivided into the Congaree/Fishburne, Warley Hill, and Santee Limestone Formations. The Congaree Formation is composed of tan, moderately to well sorted, fine to coarse quartz sands with thin clay laminae throughout. The Congaree and the underlying Fishburne Formation are similar in lithology (i.e., well sorted, clean, coarse-grained sands, indicative of shallow marine deposition) and will be characterized together. The "Congaree/Fishburne" is approximately 60 feet thick in A/M Area.

The Warley Hill Formation rests directly above the sand of the "Congaree/Fishburne". The Warley Hill Formation in A/M Area is mostly orange and yellow, fine to coarse, poorly to well sorted quartz sand interbedded with discontinuous clay beds.. Pebbles and clay clasts are common in places, and muscovite is fairly common. In M-Area borehole MSB-40, a section of micritic, shelly limestone was encountered within the Warley Hill interval. This is the only carbonate lithology encountered in A/M Area.

The Santee Limestone is subdivided into the Caw Caw and the McBean Members. At SRS, the Santee Limestone varies in lithology from carbonates and calcareous quartz sands to quartz and glauconitic sands and clays. Although not present over most of A/M Area, the Caw Caw Member may be present as a thin clay above the Warley Hill sediments (as in borehole MSB-40). "Warley Hill/Caw Caw" sediment type and fossils indicate deposition in shallow marine and bay or lagoonal environments. The Warley Hill and Caw Caw sediments are often referred to as the "green clay" over most of the SRS, however, these thin silty clays, overlying the "Congaree/Fishburne" interval, are often tan or grayish tan. The "green clay" is considered a confining unit.

The McBean Member of the Santee Limestone is composed of tan, fine to coarse, poorly to well sorted sands and interbedded green, yellow to brown clays up to eight feet thick. The formation thickness ranges from 30 to 45 feet in A/M Area. The target zone for well AMH-3 (150 ± 10 ft bls) likely included the upper portions of the McBean Member.

Barnwell Group

The Barnwell Group (Late Eocene) is subdivided into the Clinchfield, Dry Branch, and Tobacco Road Formations. The Clinchfield Formation is present at some locations, but it is not continuous enough to be correlated across the SRS. The Dry Branch Formation is similar in lithology to the

Santee Formation (McBean Member) with tan, green, yellow, and brown clays which occur in places at various stratigraphic levels within the formation. The Dry Branch Formation is cleaner (less clay content) than the underlying McBean Member sands, or the overlying Tobacco Road Formation sediments. The Dry Branch Formation varies in thickness from not present to 110 feet in A/M Area borings. The sand of the Dry Branch Formation probably accumulated in a shallow marine environment. The target zone for well AMH-3 (105 ± 10 ft bls) was in the lower portion of the Dry Branch, while the target zone of well AMH-4 (150 ± 10 ft bls) was in the mid-upper portion of the Dry Branch Formation.

The Tobacco Road Formation consists of orange, red, brown, yellow, tan, and purple fine to coarse, poorly to well sorted sands. Pebbly layers are common, especially near the base. Clay clasts are fairly common, and clay layers up to four feet thick have been encountered in some borings. The formation outcrops at the surface at many locations throughout the SRS. The Tobacco Road Formation was probably deposited in a shallow marine environment.

The Upland Unit (previously mapped at SRS as the Hawthorn Formation) in A/M Area is composed of yellow, orange, purple, red, brown, and tan, fine to very coarse, poorly sorted, clayey, silty quartz sands. Weathered feldspar grains are abundant in some locations. Clay lenses interbedded with these sands are up to 50 feet thick. Thickness varies from not present to approximately 60 feet. The "Upland Unit" sediments were probably deposited in high energy fluvial channels, point bars, flood plains, and abandoned channels (Aadland et al. 1992; WSRC 1992a).

2.2.2 Hydrogeology

A multilayer hydrologic system exists in the Coastal Plain sediments at the SRS. Confining units within the system are interspersed with more transmissive units. Aadland and Bledsoe (1990) have developed a hydrostratigraphic nomenclature system (Figure 2.2) for SRS. Within this nomenclature, the basement complex underlying the Coastal Plain deposits is referred to as the Piedmont Hydrogeologic System. This system is overlain by two aquifer systems of Coastal Plain deposits, the Dublin-Midville Aquifer System, and the Floridan Aquifer System. Discussion here is limited to the uppermost aquifers since the horizontal wells are constructed in the water table aquifer and the overlying vadose zone. The reader is referred to Aadland et al. (1992) for the most recent description of SRS hydrogeology.

The Floridan Aquifer System (II) is divided into the Gordon Aquifer and the Upper Three Runs

FIGURE 2.2 COMPARISON OF CHRONOSTRATIGRAPHIC, LITHOSTRATIGRAPHIC, AND HYDROSTRATIGRAPHIC UNITS AT THE SRS (From WSRC-TR-92-355)

Aquifer by the Gordon Confining Unit. "Congaree/Fourmile" sands comprise the Gordon Aquifer, and sands of the Santee Limestone and Tobacco Road Formation comprise the Upper Three Runs Aquifer. "Warley Hill/Caw Caw" clays (including the "green clay") comprise the Gordon Confining Unit. Northwest of Upper Three Runs Creek, as in the A/M-Area, the individual confining beds separating the two Aquifer Systems become thin and discontinuous. Figure 2.3 is a hydrostratigraphic chart for A/M Area. In this area of SRS, the two Aquifer Systems combine to form the single, larger Floridan-Midville Aquifer System. This is due to the thin and sporadic character of the clay and silty clay beds correlative with the Meyers Branch Confining System and the Allendale Confining Unit.

In A/M Area, the Floridan-Midville Aquifer System is divided into three aquifer units from base upwards: McQueen Branch Aquifer, the Crouch Branch Aquifer, and the Steed Pond Aquifer, separated by the McQueen Branch Confining Unit and the Crouch Branch Confining Unit. In A/M Area, the Gordon Aquifer and the Upper Three Runs Aquifer are in hydraulic communication due to the thin, and intermittent character of the intervening clay beds. The aquifers coalesce in the A/M Area to form the single aquifer unit, Steed Pond Aquifer. The Steed Pond Aquifer is divided into the "Lost Lake" aquifer zone and the "M-Area" aquifer zone by the "green clay" confining zone. These are equivalent to the Gordon Aquifer, the Upper Three Runs Aquifer, and the Gordon Confining Unit, respectively. North of the A/M Area, where the confining zone thins and becomes absent, the "Lost Lake" aquifer zone and the "M-Area" aquifer zone coalesce into the Steed Pond Aquifer. The thickness of the "green clay" confining zone ranges from 2 feet to 28 feet. The thickness of the confining zone may include sand layers. A hydrogeologic cross-section of the Integrated Demonstration Site which illustrates the location of the M-Area and Lost Lake Aquifer Zones relative to site stratigraphy, is presented in Appendix B.

The water table is located in the "M-Area" aquifer zone (Aadland et al. 1992). The "M-Area" aquifer zone is the uppermost aquifer zone within the Steed Pond Aquifer in which the water table well (AMH-3) was installed. This aquifer zone is laterally discontinuous to the north due to the pinching out of the "green clay" confining zone. Where the confining zone is absent, the "M-Area" aquifer zone coalesces with permeable sediments in the northern portion of the A/M Area, forming the water table portion of the Steed Pond Aquifer. Where present, the "M-Area" aquifer zone ranges in thickness from 37 to 180 feet. The horizontal hydraulic gradient for the aquifer zone averages 0.005 ft/ft and the vertical hydraulic gradient averages 0.28 ft/ft. Model derived horizontal and vertical hydraulic conductivities of 9.0 ft/day and 0.0061 ft/day, respectively, and vertical and horizontal seepage velocities of 0.009 ft/day (3.3 ft/yr.) and 0.225 ft/day (82.13 ft/yr.), respectively, were determined for the "M-Area" aquifer zone (Papadopoulos 1986).

FIGURE 2.3 HYDROSTRATIGRAPHIC CHART FOR THE A/M AREA
(From WSRC-TR-92-355)

3.0 DRILLING PROGRAM

ECES of Houston, Texas drilled the horizontal boreholes. ECES developed a specialized drill rig to provide the torque and power requirements for the directional drilling of these types of horizontal borings. The drilling rig used was a DRECO™ slant-hole custom-designed mud-rotary drill rig. This rig generates a maximum of 500-horsepower with a maximum rig torque rating of 10,000 foot/pounds for the casing drive at 160 revolutions per minute.

Horizontal drilling with the ECES system in the unconsolidated sediments at SRS required proper drilling fluid control to maintain borehole stability, down-hole directional tools for surveying and directional control, and timely implementation of drilling and well construction activities.

3.1 Drilling Fluid System

The drilling fluid system was a critical part of drilling and well installation, providing efficient removal of drill cuttings from the borehole, maintaining adequate flow in the annular space to reduce casing skin friction, and providing adequate borehole stability. The drilling fluid was pumped through the drill rods (inside the casing) and recirculated through the annulus to the surface with a hydraulic 325-horsepower mud pump. The mud pump used was a three piston pump with a maximum flow rate of 350 gallons per minute (gpm) and a maximum pump pressure of 1200 pounds per square inch (psi).

The functions of the drilling fluid were to open and close the bit, lubricate the bit, and remove cuttings from the borehole. Whereas, the drilling fluid may lubricate installation of the casing/screen assembly somewhat, advancing the assembly behind the drill bit is the primary mechanism of assembly placement. Accordingly, the most important purpose of the mud program was to carry cuttings from the bit out of the borehole.

The drilling fluid used during the early course of the project was primarily bentonite powder mixed with water. The viscosity, as measured with a Marsh funnel, was monitored periodically and maintained at a range of 30-50 seconds. The weight of the mud at that viscosity was approximately 8-9 lbs/gal. As drilling progressed in each attempt, sloughing of the borehole impeded the progress of well installation. Delays due to rig and survey tool performance also contributed to borehole instability which resulted in sloughing. The drilling fluid program was modified after all efforts to improve drilling and downhole survey tool performance failed to overcome the geologic conditions. A Milkem™ mud engineer was subcontracted to modify the

drilling fluid program which included the use of bentonite extenders and polymers.

The modified mud program improved hole stability, controlled fluid loss, and improved overall drilling performance. The fluid characteristics used for successful completion of both wells included the following:

- low weight (8.6 to 9.0 lbs/gal)
- high viscosity (Marsh funnel viscosity of 95 to 105 seconds)
- high lubricity (utilizing polymers)

The preferred drilling fluid with the above properties consisted of a fresh-water based system with the following constituents:

- non-peptized bentonite gel for viscosity
- bentonite extender (Ben-Ex™) to prolong bentonite gel life
- powdered polymers (New-Drill™) for greater viscosity with minimal fluid weight increase and stronger filter cake formation

3.2 Directional Drilling Tools

The direction and orientation of the curve and lateral sections of the boreholes were controlled by the BHA, which consisted of the expandable wing drill bit (underreamer)¹, the steerable DHM, the TFI, and casing attachments. Each of these components was connected with knuckle-joints, which allowed the BHA to form a three-point geometry. The knuckle-joints allowed each tool to be set at an angle to each other, creating an arc composed of the bit, DHM, and TFI. A conceptual schematic of the BHA is illustrated in Figure 3.1.

Drilling fluid pressure provided the hydraulic driving force necessary for the DHM to rotate the drill bit and cut through the sediments. Flow rates from 150 to 300 gpm generated from 18 to 40 horsepower at the bit. The DHM had eccentric stabilizers which were used to create off-set between the bit and the TFI, creating an arc which determined the radius of the curve. Figure 3.2 presents a more detailed illustration of the steerable DHM.

¹ The expandable wing drill bit is referred to as an underreamer for the following reason. A bit (wings contracted) is passed through a casing slightly larger in diameter than the bit itself. After exiting the casing, the wings on the bit expand and a borehole with a diameter larger than the casing can be drilled. The term underreamer is used because the sediments under the casing are reamed out.

FIGURE 3.1 BOTTOM HOLE ASSEMBLY (BHA)

NOTE
MOTOR ASSEMBLY CONNECTED TO TFI
BY KNUCKLE-JOINT ATTACHMENTS.

NOT TO SCALE

FIGURE 3.2 SCHEMATIC OF DOWNHOLE MOTOR WITH STABILIZERS

The TFI measured the orientation of the tool in relation to its position in the casing and the inclination (measured from horizontal in the lateral section and vertical in the curved section) of the drill bit at that point. TFI data was sent by electronic impulse through the drilling fluid to a recorder on the drilling platform. The TFI was located approximately 15 feet behind the drill bit so direction and measured depth were extrapolated geometrically to the bit using location data received from the TFI.

The BHA was seated inside a 10-inch ID HDPE casing and steel shoe. The BHA could be extended as far as drilling conditions would allow, however, the retraction of the BHA was limited to approximately 1-foot by a shoulder inside the shoe. This shoe prevented the casing from sliding over the bit. The stabilizers were set prior to drilling the curve and then re-set prior to drilling the lateral section.

The hydraulic pressure of the drilling fluid expanded wings on the drill bit cutting a hole with sufficient diameter to permit a 10-inch or 6-inch diameter casing to be installed behind the drill bit. The casing was attached to the DHM behind the last eccentric stabilizer. The wings were expanded by a piston driven by drilling fluid pressure. The wings were retracted by venting drilling fluid pressure from the surface, allowing the wings to collapse into the bit housing. The bit was then pulled out of the borehole through the casing.

3.3 Drilling Procedure

Each borehole was drilled in three segments: from land surface to the kick-off point (KOP); the curved portion from the KOP to the end of curve (EOC); and the horizontal section. Figure 3.3 illustrates the location of each segment relative to one another and the associated terminology. The angled portion of each boring to KOP was augered using solid-stem augers. The boreholes were then cased with 14-inch OD steel conductor pipe with a flanged joint at the top end. A bell nipple was bolted to the flange joint. The bell nipple was used to direct drilling fluid and serve as a housing for material and tool installation. The casing was pressure grouted in place with neat cement grout containing calcium chloride (CaCl_2) and bentonite.

After allowing the grout to cure, a tri-cone roller bit was used to drill out the grout seal at the bottom of the surface casing (conductor pipe). Mud rotary drilling methods were used from this point on. Subsequent to drilling out the grout seal at the base of the surface casing, the TFI and DHM were assembled and attached to a collapsible 10-inch diameter wing-bit. The TFI was calibrated and tested at land surface prior to insertion into the borehole. Eccentric stabilizers were set to define the off-set of the bit. The off-set was such that when the BHA was assembled,

DEMONSTRATION OF ECES
HORIZONTAL DRILLING SYSTEM
INTEGRATED DEMONSTRATION SITE, SRS

FIGURE 3.3 WELL SECTION ORIENTATION AND ASSOCIATED TERMINOLOGY

the steerable motor would lie on a flat surface and the bit and TFI would be raised at an angle off the surface. That is, the centerline through all three components of the BHA would not be straight, or parallel to the steerable motor. Drilling of the curve section of the boreholes required advancing the BHA and the attached 10-inch inside diameter (ID) HDPE casing through the 110-foot radius curve.

The horizontal section of the borehole was advanced utilizing the BHA assembly equipped with an 8-5/8-inch diameter wing-bit. Drilling of the horizontal sections of the boreholes required drilling a series of concave and convex arcs to form the lateral section. The BHA was initially assembled with a length and curvature that defined a predetermined radial curve. The tool bit was then rotated in the casing at calculated intervals to drill up or down. This alternating drilling orientation created a series of concave and convex arcs, that, overall, defined a horizontal trend. Slotted, 6-inch diameter HDPE well casing was secured to the backside of the DHM and advanced with the BHA. The direction and angle were maintained in the same manner as for the curved section, except angles were maintained close to 90° from vertical and directions near $S10^{\circ}E (\pm 10^{\circ})$.

3.4 Surveying Methods

During the drilling of the curved and horizontal sections of the boreholes, the drilling engineers monitored TFI data sent by impulse through the drilling fluid to a recorder on the drilling platform. The TFI provided inclination and tool face orientation only.

Downhole surveys were performed on a regular basis as the curved and horizontal sections of the boreholes were being drilled. Two methods of surveys, each employing different down-hole tools, were used during drilling. Off bottom single-shot surveys measured the azimuth and inclination of the drill rod in the borehole at a point. This was used periodically during drilling to verify the TFI readings coming from the DHM. Upon completion of each curved and horizontal section, magnetic multi-shot surveys were performed that measured the same parameters as the single-shot, but in incremental lengths throughout the entire length of the borehole. All survey data collected are presented as Appendix C.

3.5 Filter Pack Installation

Subsequent to the successful installation of the casing/screen assemblies, installation of artificial filter material was attempted. The artificial filter material consisted of HDPE plastic beads injected through an aluminum casing shoe installed at the end of the casing. Sloughing of the boreholes

precluded the installation of the HDPE beads through the casing shoe, and resulted in a natural formation filter pack around the lateral section of each well. HDPE beads were installed in the open annulus of each borehole and capped with bentonite pellets installed through a tremie pipe. Subsequent to bentonite hydration, the remaining annulus was pressure grouted with neat cement grout containing 2% sodium metasilicate.

3.6 Well Development

Well development was performed after the wells had been properly constructed to remove drilling fluid and consolidate the filter materials around the screens. The development procedures varied slightly for each well. For the vadose zone well (AMH-4), filter compressed air and water were pumped into the well to displace and flush out excess drilling fluid. Fresh, potable water was flushed in through a side-discharge tremie pipe. The bottom of the tremie pipe was swabbed up and down (right and left laterally in cross-sectional view) inside the casing/screen assembly until clear, sediment free water was produced. This procedure was performed for approximately 24 hours.

The water table aquifer well (AMH-3) was swabbed with a surge block and filtered compressed air, and used the formation water to flush the screen and well materials. Swabbing and surging was performed for approximately 24 hours until clear, sediment free water was produced.

The procedures outlined above were used for each attempt and the final completion of both wells. Variations in design and construction of the wells allowed for changes in the basic process. The procedures used during each attempt of well installation are discussed in the following well summaries.

4.0 WELL SUMMARIES

As previously described, this project was the first full-scale demonstration of an innovative directional drilling system designed by ECES. As a result of the prototype nature of the system, several modifications were necessary for the successful completion of the two wells. Six attempts were required to install the shallow vadose zone well. As a result of lessons learned during the installation of the vadose zone well, the water-table aquifer well was completed with one attempt. Figure 4.1 presents plan and cross-sectional views of all well attempts and completions. Table 4.1 presents borehole data for each well attempt and completion. In addition, Table 4.2 presents location survey data for each well attempt and completion. Table 4.3 details drilling fluid properties and summarizes rig performance data.

**DEMONSTRATION OF ECES
HORIZONTAL DRILLING SYSTEM
INTEGRATED DEMONSTRATION SITE, SRS**

**WSRC-TR-92-577
DECEMBER 1992**

Modified from Eastman Christensen

Note: Attempts 1 and 1A for AMH-3 are designated #7 by ECES as presented on this figure and in Appendix C.

FIGURE 4.1 PLAN AND CROSS-SECTIONAL VIEW OF WELL ATTEMPTS

TABLE 4.1 WELL ATTEMPT AND COMPLETION SUMMARIES

ATTEMPT SEQUENCE		EOC	TVD	MD
AMH-4	1	228	95-125	442
	2	169	134	169*
	3	---	85 55+	109 69+
	4	169	99	169*
	5	168	96-100	310
	5A	---	96-100	346 230+
	6	148	99-105	300+
AMH-3	1	230	153-155	347
	1A	230	153-155	488

* Well could not be completed beyond EOC.

+ Surveyed depth differs from reported depth due to sloughing of the borehole

EOC - End of Casing

TVD - Total Vertical Depth

MD - Measured Depth from the Well Head

Note: Attempt 5A was completed from the same curved section as attempt 5. Attempt number 1A for the deep well was completed from the same curved section as attempt 1.

Attempts 1 and 1A for AMH-3 are designated #7 on Figure 4.1 and in Appendix C.

TABLE 4.2 SURVEY DATA FOR HORIZONTAL WELL ATTEMPTS

Well Number Attempt Number	SRS Northing (feet)	SRS Easting (feet)	TOC Elevation (ft msl)
<u>AMH-4</u> 1, 2, &3 (same location)	102, 727.19 LAT 33°-19'- 57.28"	48,800.32 LONG 81°- 44'-16.39"	362.91
4	102,730.30 LAT 33°-19'- 57.31"	48,801.76 LONG 81°- 44'-16.40"	363.09
5	102,741.86 LAT 33°-19'- 56.5"	48,809.51 LONG 81°- 44'-16.41"	362.60
*6	102,680.80 LAT 33°-19'- 56.65"	48,784.56 LONG 81°- 44'-16.22"	362.40
<u>AMH-3</u> *1	102,670.53 LAT 33°-19'- 56.71"	48,779.61 LONG 81°- 44'-16.19"	362.10

* Actual location of installed well

-- No elevation recorded as of 12-92

SRS Savannah River Site

Note: Attempt AMH-3/1 is designated #7 on Figure 4.1 and in Appendix C.

TABLE 4.3 Drilling Condition Summaries of Each Well Installation Attempt

Attempt Identification	Drilling Fluid Rheology		Drilling Conditions			
	weight (lbs/gal)	viscosity (seconds)	Drilling Fluid Flow Rate (gpm)	Drilling Fluid Pump Pressures (psi)	Drilling Speed (ft/min)	Pull-down Pressure (thousand lbs)
AMH-4/1	8-10	40 ($\pm$ 10)	300-350		2	5
AMH-4/2	8-10	40 ($\pm$ 10)	285-300	300-350 *450	2	5 *11
AMH-4/3	8-10	60-70	•225 250-300	200-600 500-950	2	•5 8 - 10 *10- 11
AMH-4/4	8-10	40 ($\pm$ 10) *65	260-310	N/R	<1	5-10
AMH-4/5	8-10	60 *90	285-320	N/R	<1	•5 - 7 9 - 11 *14 - 17.5
AMH-4/5A	8-10	60 *85	•150-200 300	N/R	N/R	•7 10 *11
AMH-4/6	8-10	•105 120 *182	285-300 *350	•200-400 300-550	N/R	•2 5-6
AMH-3/1	8.6-9.0	90-100	280-300	500-900	N/R	3000-9000
AMH-3/1A	8.6-9.0	90-100	280-300	500-900	N/R	3000-9000

• lowest values recorded

* highest values recorded

NR Not Recorded

Note: Attempt AMH-4/5A was from the same curve section as attempt AMH-4/5.

Attempt AMH-3/1A was from the same curve section as attempt AMH-3/1.

Attempts AMH-3/1 and AMH-3/1A are designated #7 on Figure 4.1 and in Appendix C.

The following well summaries include a description of the actual drilling procedures used, the problems encountered, and the corrective actions implemented to overcome the difficulties of each attempt. Final well completion data are provided with the section discussing the final attempt for each well.

4.1 Vadose Zone Well (AMH-4)

4.1.1 *AMH-4 First Attempt*

Drilling for AMH-4 began on February 19, 1991, 50 feet north of the existing horizontal well AMH-1 location in the M Area at SRS (see Figure 4.1). A pilot hole was drilled at an inclination of 30° from the vertical using 16-inch diameter solid-stem augers. Subsequent to pilot hole completion to 20 feet MD, a 14-inch diameter steel conductor pipe was installed and grouted in place with neat cement grout containing 4% Milgel™ and 2% CaCl₂. After allowing sufficient time for the grout to cure (9 to 10 hours), a 12-inch diameter tri-cone roller bit was used to drill out the grout plug at the base of the conductor pipe and to the KOP at 41 feet MD.

The curve was drilled from the KOP using the BHA with 10-inch diameter HDPE well casing attached. The planned completion depth of the curve was to be approximately 150 feet MD with a TVD of 105 feet at an uncorrected orientation of S10°E. While drilling the curve, the BHA tended to build angle too quickly. A single-shot survey conducted at 57 feet MD indicated that the build rate was too great and would have put the EOC above the target zone at 88 feet TVD. Consequently, the drill rod was rotated 180° in the borehole to allow the BHA to form a convex arc downward, straighten the curve, and reach the target zone. Once the build angle was reduced, the drill rods were re-oriented and drilling resumed as planned. The EOC was reached at 228 feet MD and 90.5 feet TVD, with an orientation of S16°E. Measured depth to the EOC was greater than planned due to the adjustment required in the build rate of the curve. The TVD was shallower than the target depth but the BHA was oriented during the initial phase of horizontal drilling to "drift" downward into a target depth. The orientation of S16°E was only 6° from the planned direction and was acceptable. The 10-inch diameter casing was pressure grouted in place with neat cement grout containing 2% CaCl₂ and 4% Milgel™.

Drilling of the lateral section began after allowing the grout to cure. Drilling proceeded in accordance with the original drilling plan and drilling conditions are summarized in Table 4.3. The borehole was advanced laterally with a few minor problems related to drill rig hydraulics and design specifications, none of which affected the drilling performance. However, as the lateral

section was advanced, resistance against the bit and casing increased and excessive downpressure was required to continue advancing the casing/screen assembly. As the casing/screen assembly was advanced to approximately 300 feet MD, a small quantity of drilling fluid was noted circulating up through the inside of the casing/screen assembly, and small pieces of HDPE shavings were noted in the drilling fluid. At 442 feet MD (214 feet past EOC) and 105 feet TVD, the resistance on the bit and DHM was too great to advance the casing/screen assembly further. Repeated attempts to flush out the hole, increase pulldown pressure, and pushing and pulling of the assembly failed to move the assembly forward. With approval of WSRC personnel, the drilling contractor prepared to complete the well at 442 feet MD and 105 feet TVD, with a horizontal section of 214 feet from the EOC.

As the drill rod and BHA were being removed from the well through the HDPE casing, it became stuck in the area of the curve where adjustments to the build rate had been made. Pulling the drill rods failed to recover the stuck drillstring. As a final effort, the drilling contractor slowly rotated the BHA inside the screened casing, and freed it and the drill rods from the borehole. Rotating the drill rods and BHA wrapped the screen around the drill rods, severely damaging the casing/screen assembly. After several unsuccessful attempts to recover the damaged casing/screen assembly remaining in the borehole, the borehole was abandoned with neat cement grout in accordance with South Carolina Well Standards and Regulations (R.61-71 SCWSR). Well abandonment details are contained in Appendix D.

4.1.2 *AMH-4 Second Attempt*

The second attempt was performed at the same location as the previous attempt without moving the drill rig. The drilling plan was modified at this time to drill the pilot hole for the conductor at an angle of 15° from vertical, and drill the borehole to KOP using solid stem augers rather than mud-rotary methods. The mast was raised, which moved the drilling location in towards the rig (north about 10 feet in plan view). This new pilot hole angle required a shallower KOP (28 feet MD and 24 foot TVD) and a shorter radius curve to be built than at an inclination of 30°.

Drilling conditions during curve installation are summarized in Table 4.3. As drilling of the curve proceeded, single-shot surveys were performed periodically to confirm the direction and the angle of the bit at specific points along the curve. A single-shot survey point near the EOC showed the bit angle to be near 30° at 109 foot MD and 54 feet TVD. At this MD, drill bit inclination should have been approximately 60°. In addition, the orientation of the curve was recorded on the single-shot survey instrument to be N15°W. The orientation of the curve was expected to be S10°E, as

planned.

Due to conflicting TFI and single-shot survey data, the 10-inch diameter casing was removed from the borehole and a multi-shot survey was conducted through the entire length of the open borehole. The results of the multi-shot survey indicated that the curve had actually been drilled in the correct direction and orientation, and that the single-shot survey data was inaccurate. The inaccurate data were attributed to the location of the single-shot survey tool adjacent to a steel centralizer. The revised survey showed the curve to be inclined at 53° and oriented S16°E. The orientation was within the acceptable range of deviation of ten degrees.

Drilling resumed with the 10-inch diameter casing connected to the BHA to 169 feet MD and 100 feet TVD. However, the orientation was reading S86°E or about 70° off of target. The casing was removed and a multi-shot survey was taken of the curve which confirmed the MD and the true orientation. However, the TVD was determined to be 133 feet at that MD with an inclination of 35° from vertical. The inclination near the EOC should be near 90° from vertical. The inclination was too small and TVD was too deep to be able to re-direct the bit and BHA with attached casing upward to reach the target zone. Because correction of the bit direction from this inclination and TVD to reach the target zone was impossible, the second attempt was abandoned.

The casing was removed from the borehole, and the borehole abandoned with neat cement grout in accordance with SCWSR requirements (See abandonment reports in Appendix D).

4.1.3 *AMH-4 Third Attempt*

After abandonment of the second attempt was complete, the rig was moved approximately 10 feet north and set up to drill a third attempt (see Figure 4.1). Installation of the conductor pipe and drilling of the borehole to the KOP were performed as outlined for the second attempt. The KOP was located at 28 feet MD and 24 feet TVD.

The curve was drilled with down-pressure on the bit (3,000 lbs) less than that used previously. As a result, drilling rates averaged less than one foot per minute. Prior to drilling, the articulating arms of the drill rig were adjusted to work faster to reduce the time required to assemble the drill rods. The mud weights and viscosities were consistent with previous attempts. Table 4.3 summarizes drilling conditions.

As the BHA approached 109 feet MD, resistance on the bit increased requiring pull-down pressure to be increased to over 19,000 lbs. No progress was made at that down-pressure. Additional attempts to advance casing using a down-pressure of 19,000 lbs were discontinued because the casing was buckling slightly at that pressure and permanent damage was possible. After the BHA was removed from the casing, a multi-shot survey was performed. However, formation sand had flowed 40 feet up into the casing. As a result, a complete multi-shot survey of the entire borehole could not be performed. A MD of 109 feet was recorded through a casing tally and a surveyed depth of 69 feet was recorded. The multi-shot survey indicated a MD of 69 feet and 55 feet TVD. The calculated TVD for the measured length to end of the casing was 85 feet.

Due to borehole instability resulting in flowing sands, the borehole was abandoned with the casing in place. The borehole was pressure grouted with neat cement grout in accordance with SCWSR (see abandonment reports in Appendix D).

The project team suspended work for two weeks at this time to allow for delivery of additional well materials and evaluate performance to date. During the two week break, the single-shot survey instrument was re-calibrated at the Eastman-Christensen shop in Houston, Texas. In addition, ECES modified well casing joints to reduce the time required for casing assembly during lateral drilling. The new design incorporated push-lock joints rather than standard threaded joints.

4.1.4 *AMH-4 Fourth Attempt*

The fourth attempt was initiated at a location approximately 25 feet north of the third (see Figure 4.1). Drilling to install the conductor pipe began as soon as all support trucks and equipment were in place. The borehole and conductor pipe were installed at 15° from vertical to 20 feet MD. The KOP was at 28 feet MD and 24 feet TVD. Drilling of the curve proceeded smoothly to the EOC at 169 feet MD and 99 feet TVD, and was completed in 4.5 hours. Drilling conditions for the curved section are summarized in Table 4.3.

A multi-shot survey confirmed the results of the single-shot survey of the curve (169 feet MD and 99 feet TVD). However, the direction of the bit was determined to be S44°W, which was over 50° out of alignment with the target zone. [This deviation was attributed to faulty readings from the TFI]. After reviewing survey data of the curve and plotting the points in plan view, it was discovered that the EOC was only a few feet from the vertical riser of existing well AMH-1, which was completed for the first demonstration project.

The feasibility of correcting the borehole by curving the lateral section of the well towards the east was evaluated. After review of the survey data and an assessment of the technical ability of the drill rig, it was determined that with the technology available, the BHA and attached casing/screen assembly could not negotiate the short radius required to re-enter the target zone. In addition, curving the lateral section past well AMH-1 was too risky to guarantee the integrity of the well. Therefore, the borehole was abandoned with neat cement grout in accordance with SCWSR.

4.1.5 *AMH-4 Fifth Attempt*

The fifth attempt was initiated at a location approximately 100 feet south of AMH-4 (see Figure 4.1). Mobilization of all equipment took several days due to grading and excavation of the new site. Once drilling began, both the conductor and borehole to KOP were completed at 15° from vertical in the same manner as described in the previous attempts. Subsequently, the curve was completed in thirteen hours to 168 feet MD and 96 feet TVD. The direction of the bit was oriented S21°E, which was approximately 10° from the target azimuth. The 10-inch diameter casing was grouted in place as previously described.

After extensive down-time for repairs and modification to the rig, drilling began for the lateral section. Drilling conditions are summarized for this effort in Table 4.3 under attempt 5A. As drilling approached 300 feet MD (132 feet lateral section), drilling fluid was observed circulating out of the top of the 6-inch diameter casing/screen assembly above the conductor pipe. This indicated that the fluid flow out of the bit was being restricted; most probably by fine sand or some accumulation of clayey material. At approximately 307 feet MD, the downpressure required to advance the casing/screen assembly became too great to continue drilling without damaging the HDPE casing and BHA. Drilling stopped at 310 feet MD. Between approximately 200-300 feet MD, field logs indicated that the sand content in the drilling fluid returns decreased, and gravel-size clay nodules were noted on the shaker screen.

After evaluating drill rig performance and survey data, ECES began to pull the casing/screen assembly out of the borehole to determine the cause of leakage and bit resistance. After approximately 130 feet of screen was removed, a section of separated screen was recovered. Apparently a coupling had separated, causing drilling fluid to circulate up through the casing/screen assembly rather than flow through the well annulus to the surface. A survey was performed to determine the leading end of the remaining section of screen in the borehole. Several days were spent trying to remove the remaining screen from the borehole. After all attempts failed to recover the screen, the borehole was temporarily abandoned with high viscosity drilling fluid (150

seconds) and sealed with a steel plate welded to the top of the conductor.

ECES suspended drilling for two weeks to evaluate performance, plan a modified approach to drilling, repair and calibrate survey equipment, and order new well construction materials. Factors hindering the advancement of the bit and casing beyond the curve into the lateral section were assessed. Potential factors considered to be affecting drilling progress included:

- Initial drilling rates may have been too fast to allow the drilling fluid to sufficiently circulate cuttings out of the borehole.
- Excessive time required for the rig hydraulics to assemble the rods and casing at the rig surface may have allowed the suspended cuttings in the drilling fluid time to settle out and accumulate in the base of the borehole.
- Electronic survey equipment needed recalibration.
- Geologic factors such as hard clays and dense sands could have been causing the bit to deflect and wander, therefore impeding successful completion. In addition, soft, loose sands could have resulted in drilling fluid loss to the formation, thereby reducing flow velocities required to remove drill cuttings from the borehole.

The reason for incompleteness of this latest attempt was attributed to the separation of the factory weld. No changes or alterations to the rig or equipment were performed at this time, and another attempt was performed through the same conductor pipe and curve.

Continuation of Fifth Attempt

Prior to drilling, the heavy, viscous mud used in temporary abandonment was reconditioned with fresh drilling fluid. Subsequently, the BHA and casing/screen assembly were tripped back into the borehole to the upper end of the abandoned screen (approximately 275 feet MD and 107 feet past the EOC). The drill bit was then rotated and drilling began parallel to the abandoned screen of the previous attempt. Table 4.3 summarizes drilling conditions.

As drilling proceeded, problems with the drilling fluid mixing tanks occurred which slowed drilling progress. At 307 feet MD the bit became sand locked in the borehole. The BHA and casing/screen assembly were surged back and forth with alternating forward and reverse pull-down

pressures in an attempt to free the assembly. After four hours, this surging action freed the bit and casing. During surging, HDPE shavings were noted in the drilling fluid circulating out of the borehole. Once the casing was freed, drilling resumed. Drilling proceeded to 346 feet MD at which point further advancement of the borehole was not possible. After several hours of surging, the casing/screen assembly worked free and ECES began pulling all tools and casing from the borehole to conduct a multi-shot survey. After seven lengths of casing were removed, the BHA became stuck in the borehole. Prior to the bit becoming stuck, drilling fluid circulation stopped. Drilling fluid was pumped down the borehole at approximately 150 gpm for 3-4 hours with no circulation to the surface. After regaining circulation, the flow rate was increased for about 10 minutes to circulate drill cuttings out of the borehole. Subsequently, eight more casing lengths were removed and the BHA was retrieved. After the BHA was brought to the surface, the drill bit was examined for wear. From the appearance of the bit, excessive wear had occurred, forming a notch on the backside of the wings of the bit. Apparently, the screened casing was slipping over the attachment bands and pushing against the wings of the bit restricting their ability to open fully. Consequently, the bit could not ream the borehole to a diameter sufficient to allow installation of the casing/screen assembly. The HDPE shavings previously noted circulating up the borehole in the drilling fluid were apparently a result of this problem.

ECES resumed the removal of the casing/screen assembly from the borehole. Before one full length could be retrieved, the casing/screen assembly separated at a factory weld. The borehole and remaining casing/screen sections were abandoned with neat cement grout in accordance with SCWSR.

4.1.6 *AMH-4 Sixth Attempt*

Prior to initiation of the sixth attempt, preparations were made to incorporate two modifications to the drilling plan. First, a drilling mud engineer from Milkem™ was mobilized to the site to monitor and modify drilling fluid properties to accommodate changing conditions. Second, a pilot horizontal borehole would be drilled without the HDPE casing/screen assembly attached. Third, the BHA would be advanced at a slower rate and with decreased pull-down pressure to allow sufficient time for drill cuttings removal, and to preclude the advancement of the casing/screen assembly into the bit.

The drill rig was moved approximately 5 feet north for the sixth attempt (see Figure 4.1). The conductor pipe and borehole to KOP were installed at 15° from vertical. The KOP was at 35 feet MD and 30 feet TVD. The curve was drilled to 148 feet MD in less than 7 hours. Drilling

conditions are summarized in Table 4.3. A multi-shot survey indicated the EOC to be 148 feet MD at 102 feet TVD, with an azimuth of S1°E. Inclination at the EOC was 81° from vertical. The 10-inch diameter casing was then pressure grouted with neat cement grout as previously described.

After allowing the grout to cure, drilling of a pilot horizontal borehole was performed without the casing/screen assembly attached to the BHA. Due to the non-horizontal orientation of the EOC, the drilling contractor had to build angle to bring the borehole alignment to a horizontal position. At 236 feet MD, the TVD was approaching 120 feet, well below target depth and immediately above the water table. After evaluating drilling performance and project requirements, all tools were removed, and the lateral borehole was backgrouted to the EOC (148 feet MD).

After the grout had sufficiently cured (12 hours), the second attempt at a lateral section was initiated through the same conductor and curve. The lateral section was drilled to 297 feet MD (149 feet from EOC) in less than 16 hours. Drilling conditions are summarized in Table 4.3. Upon removal of the drillstring to conduct a multi-shot survey, the BHA became sandlocked in the borehole, apparently as a result of the loss of circulation of the drilling fluid. After resuming circulation of the drilling fluid for nearly one hour and then using a combination of surging and rotating the drill bit in the borehole, the bit was freed and drilling resumed. No survey was performed. At this time the drilling mud engineer increased the viscosity to approximately 110 seconds while maintaining a weight of 8.5 lb/ft³. The borehole was advanced to 322 feet MD at which time advancement of the BHA required excessive pull-down pressures and drilling was discontinued. A multi-shot survey indicated the borehole to be 320 feet MD at 105 feet TVD, with an azimuth of S22°E.

Well Completion and Development

After the drillstring was tripped out of the borehole, the 6-inch diameter casing/screen assembly with a 20-inch wash-sub (downhole tool designed to clean the borehole with drilling fluid pressure) was advanced to the end of the borehole. Sloughing at the end of the borehole made advancement of the casing/screen assembly impossible beyond about 300 feet MD. Upon approval of WSRC, the well was completed at 300 feet MD and 105 feet TVD, with an azimuth of S16°E.

Prior to installation of the filter material (HDPE beads), the borehole was circulated with fresh, low viscosity (55 seconds) drilling mud. This procedure removed drill cuttings remaining in the borehole, allowed for easier placement of the artificial filter material, and stabilized the borehole walls. Subsequently, a grout shoe attached to tremie pipe was inserted through the casing

assembly to the end of the casing. The grout shoe was seated in place with quick setting neat cement grout containing CaCl_2 . The HDPE filter beads then were poured in the mud tanks and pumped to the end of the casing through the tremie pipe. Pumping proceeded for only a short time before the tremie pipe became clogged and circulation of drilling fluid (with beads) stopped. The drill crews attempted to unclog the tremie pipe by using backpressure, increasing pumping rates and surging the drilling fluid within the circulation system. After trying these techniques, it became apparent that the beads would not flow out of the end of the grouting shoe because of an obstruction outside the casing/screen assembly. Apparently, the formation sand had collapsed around the casing/screen assembly and formed a natural filter pack around the well screen. Permission was granted by WSRC to complete the well, and develop it with the natural filter pack. The tremie pipe was removed from the grouting shoe and pulled back up the casing to be used to install the HDPE beads into the annulus above the EOC. The HDPE filter material was installed from approximately 20 feet above the EOC to the ground surface. The screen extended to 5 feet below the top of the conductor pipe (approximately 3 feet bls). A two-foot-thick bentonite seal was installed above the filter material by pouring bentonite pellets from the top of the conductor pipe. The drill crew then poured potable water over the pellets and allowed them to hydrate for 2 hours. A one-foot-thick grout cap was poured above the bentonite seal. Well construction details are presented in Figure 4.2. Detailed well head construction is shown in Figure 4.3.

The well was then developed using potable water and filtered compressed air as described in Section 3.6. Well development was performed for approximately 24 hours.

4.2 Water Table Aquifer Well (AMH-3)

A target zone of 151 - 157 feet below ground level was selected for the water table aquifer well (AMH-3). Drilling began on June 9, 1991 approximately 30 feet north of AMH-4 in the Integrated Demonstration Site (see Figure 4.1). The well was drilled with the mast of the drill rig in the vertical position.

4.2.1 AMH-3 First Attempt

The vertical section of the well was augered to a depth of 18 feet bls. A 14-inch diameter steel surface casing (conductor pipe) was grouted in the borehole with neat cement grout containing CaCl_2 and bentonite. After allowing sufficient time for the grout to cure, a roller cone bit was used to drill out the cement plug at the base of the conductor pipe and a nominal 12-inch diameter borehole to the KOP (35 feet MD). The modified drilling fluid properties developed for the shallow vadose zone well were maintained during drilling of the curve and lateral sections. In

DEMONSTRATION OF ECES
HORIZONTAL DRILLING SYSTEM
INTEGRATED DEMONSTRATION SITE, SRS

FIGURE 4.2 AMH-4 WELL CONSTRUCTION DIAGRAM (VADOSE ZONE WELL)

FIGURE 4.3 WELLHEAD DETAILS FOR AMH-4

addition, the casing was advanced with the BHA, as specified in the original drilling plan.

The curve was drilled with the BHA from the KOP (35 feet MD) to 89 feet MD. A single-shot survey was performed to determine the orientation of the borehole. The survey indicated the curve to be at an inclination of 30° from vertical at 89 feet MD. From this survey, it appeared that the bit was building angle too rapidly and causing the curve to be too short. ECES compensated by adjusting the TFI orientation from 045° to 270° left. This procedure decreased the build rate of the bit and maintained the surveyed borehole direction to a TVD of 150 feet. At approximately 135 feet MD, the BHA encountered a dense clay which created a thick drilling mud and packed the drill bit. The bit was replaced with a 12.25-inch diameter wing bit designed to cut clay. Drilling rates increased, and the curve was completed to 230 feet MD and 151 feet TVD. After the curve was completed, a multi-shot survey of the entire curve was conducted. A final TVD of 150.8 feet was obtained with an initial bearing of $S14^{\circ}E$, indicating the borehole to be within the anticipated target zone and azimuth. The 10-inch diameter casing was grouted into place with neat cement grout containing $CaCl_2$ and bentonite.

The horizontal section of the borehole was drilled using an 8-5/8-inch diameter wing bit. Table 4.3 summarizes the drilling conditions. Drilling proceeded from the EOC to 265 feet MD before the casing/screen assembly could not be advanced further. As a result, ECES elected to pull two sections of the casing/screen assembly and remove the drillstring from the borehole. The BHA and the TFI were examined in an attempt to determine the cause. No excessive wear was noted on the BHA and a second attempt was initiated in the same borehole. The project team decided that a centralizer had deformed under pressure and halted progress on this attempt.

Continuation of First Attempt

After a two-week break to obtain more materials, the bit was cleaned, the drilling fluid was reconditioned, and minor repairs were performed before drilling resumed. Drilling of the horizontal section proceeded smoothly to 283 feet MD. At this depth, the TFI indicated that the bit and casing had deviated from the projected line, and the drillstring was removed from the borehole. The drill bit was examined and found acceptable, and a multi-shot survey was performed to determine the extent of deviation. Survey results indicated that the downhole deviation was not as great as the TFI had reported, and drilling was resumed.

Drilling proceeded slower to allow for increased circulation of drill cuttings from the borehole. Drilling fluid viscosity ranged from 56 - 60 seconds. Drilling rates and cutting returns increased as the bit approached 350 feet MD. Some HDPE shavings were accumulating on the shaker table,

and it appeared as though the eccentric centralizers were chaffing the casing as the borehole was advanced. The borehole was then circulated and New-Drill™ was added to condition the mud. Excellent cutting returns were reported after mud conditioning. Table 4.3 summarizes drilling conditions.

After conditioning the mud, drilling proceeded to 448 feet MD. At this point, circulation of drill cuttings from the borehole became difficult. Pull down forces recorded while advancing the borehole at this depth (MD) ranged from 7000 to 9000 lbs. After drilling to 488 feet MD, the mud pump liner wore out and drilling was stopped. After evaluating the time required to repair the mud pump (3 hours), and the possibility of sand locking the drill bit and casing/screen assembly in the borehole after shutting the pumps down, ECES, upon the approval of SRTC, decided to complete the well at 488 feet MD. Well completion at 488 feet MD (258 feet past EOC) was performed upon approval of SRTC.

Well Completion and Development

The drill rods were tripped out of the hole, and a grouting shoe attached to a tremie was tripped into and seated in the toe of the casing. The well and annular spacing were then flushed with fresh potable water allowing natural formation sand to fill the annular space around the horizontal section of the screen. After flushing the well, a multi-shot survey was performed. Final survey data is presented in Appendix C. Nine sacks of HDPE beads were then poured into the annulus, followed by five sacks of bentonite powder, and 20 gallons of water. The crew then attempted to insert the tremie pipe for grouting. The tremie encountered an obstruction at 87 feet MD which appeared to be bentonite powder that had bridged off around a centralizer and had begun to harden. A small volume of neat cement grout containing CaCl_2 was then pumped into the open annulus. After allowing sufficient time for the grout cap to cure, the annular space was pressure grouted to ground surface. Figure 4.4 presents well construction details of AMH-3. Figure 4.5 presents isometric and plan views of the location of well AMH-3 relative to well AMH-4.

The well was then developed using filtered compressed air and formation water as described in Section 3.6. Well development was performed for approximately 24 hours.

5.0 COMPARISON OF TECHNOLOGIES FOR HORIZONTAL DRILLING

Two different technologies have been used at SRS to install horizontal wells. The first technology used was a short-radius drilling technique adopted from the petroleum drilling industry. This technology was used to install wells AMH-1 and AMH-2, is fully described in a previous report

DEMONSTRATION OF ECES
HORIZONTAL DRILLING SYSTEM
INTEGRATED DEMONSTRATION SITE, SRS

FIGURE 4.4 AMH-3 WELL CONSTRUCTION DIAGRAM (WATER TABLE AQUIFER WELL)

FIGURE 4.5 ISOMETRIC VIEWS OF FINAL AMH-3 AND AMH-4 BORING ALIGNMENTS

(Kaback, et al., 1989). The second technology, described herein, incorporated DHM technology utilized in the river crossing industry, and electronic borehole surveying equipment utilized in the petroleum drilling industry. The drilling system used was designed by Eastman Christensen Environmental Services, and for comparative purposes, will be referred to as the ECES system. Both techniques successfully installed horizontal wells. This section compares the two methods and outlines issues for future planning purposes. A general comparison of the two technologies is included in Table 5.1.

Short Radius Technology

Short radius drilling technology achieves installation of a horizontal well section by curving over a short radius (generally 35 to 40 feet horizontally) from the vertical borehole into the horizontal target zone. Initially, a vertical borehole is drilled down to the target zone. The borehole is then grouted back up to the KOP. The grout is allowed to harden. The grout provides a foundation for the drilling tools and bearing strength against the heavy loads induced by the rig during the drilling process. After the grout cures, the whipstock is placed on top of it. The whipstock is essentially a steel pipe, open 180 degrees on one side, with a plate welded diagonally across the closed side. The beveled plate deflects the drill guide from the vertical to initiate the curve at the kickoff point. The whipstock provides a seat at the kickoff point that initiates the curve, determines its bearing, and defines initial angle of curvature.

Once the outer casing and whipstock are installed, the curve is drilled by flexible drill rods steered by the curved drill guide. The curved drill guide (a non-rotary part of the assembly) essentially extends the deflection of the whipstock throughout the curve. The bit, rotated by the flexible drill rods, drills the curve defined by the guide. After the curve has been completed, the curved drill guide is removed and drilling of the horizontal borehole section is begun. The horizontal section of the well is then drilled by a rigid drill mandrel driven by flexible drill rods. The trajectory of the horizontal drilling (referred to as build rate for specific borehole intervals) is controlled by configuration of the whipstock and rigid drill mandrel.

Standard mud rotary drilling techniques are used to drill the horizontal borehole. A specialized drilling fluids program is required to maintain hole stability. The borehole can be drilled in two stages: (1) drilling a pilot borehole to establish the orientation and location, and (2) reaming the borehole using an over-reamer bit to create an adequate diameter borehole for well materials to be installed.

TABLE 5.1
COMPARISON OF SHORT-RADIUS AND ECES SYSTEM TECHNOLOGIES

CRITERIA	SHORT-RADIUS	ECES SYSTEM
Initial Borehole	Vertical	Slant (typical)
Curve Development	Whipstock/curved drill guide	Steerable drill bit/Conductor casing
Borehole advancement and guidance	Whipstock, rigid drill mandrel, mud control, penetration rates	Steerable drill bit and conductor casing
Well Installation	Remove drill string and install casing and screen. Relies on hole stability through drilling fluid control	Installed directly behind bit. Bit and drill stem withdrawn through screen and casing. Intrinsically stable hole not established.
Filter Pack	Generally natural pack	Polyethylene beads installed while flushing, or natural pack
Directional Drilling information	Downhole surveys	Electronic pulses read from TFI by pressure transducer through drilling mud. Information displayed on surface computer at 60 second intervals. Downhole Surveys.
Horizontal expression of radius of curvature	35 to 40 ft	90 to 110 ft
Drill Stem	Flexible drill pipe	Drill stem inside well casing
Drill Bit	Rigid Mandrel	Steerable bit with concentric stabilizers and internal hydraulic motor with eccentric motor stabilizers.

Once the total MD of the borehole is attained, the borehole is stabilized and the drilling tools are removed. The casing and screen are then installed in the borehole. The casing is seated with packers between the outer and inner strings. Generally, a natural formation filter pack is formed during well development.

Information on the orientation of the horizontal and vertical direction of the borehole is obtained by using single and multi-shot down-hole surveys. Single-shot surveys are conducted periodically throughout the drilling, and multi-shot surveys are performed upon the completion of the curved and horizontal sections of the borehole. Survey procedures are essentially the same as described in this report. The short-radius drilling technology relies primarily on the whipstock to guide the horizontal drilling. However, some control can be maintained by varying the rate of penetration and by the drilling fluids program. The drilling performance using short-radius technology is generally controlled by the geologic formation (percent fines), rigid drill mandrel configuration, drill bit speed and weight, and drilling fluid pump rates.

During drilling of AMH-1 and AMH-2 using short-radius technology, several problems were encountered. These included the following:

- Loss of 90 degree deflection angle in geologic sediments containing less than about 20 percent fines. Angle is needed to maintain horizontal trajectory during drilling
- Inability to steer drill bit.
- Drift to the right caused by bit rotation in less cohesive formations
- Bit direction influenced by changes in geologic formation.
- Stuck tools if borehole is not sufficiently stabilized prior to stopping mud circulation.
- Unlined curved borehole deteriorates rapidly with each trip into hole to drill, ream, and install well materials.

ECES System

The ECES system has been described previously in this report. A number of elements of this system will be reiterated here to highlight differences between the two technologies. Initially, a

borehole is augered, generally at an angle, to accommodate the surface casing (conductor pipe). Subsequent to surface casing installation, the curve is drilled using a steerable down hole motor and drill bit rather than a curved drill guide. The curve is built at a slower rate than in the short-radius technology, with a radius of curvature of approximately 90 to 110 feet. A deeper outer casing is then installed once the curved portion of the borehole has been completed.

The horizontal portion of the borehole is drilled using a steerable drilling assembly, rather than the rigid drill mandrel and flexible drill rod. Cuttings are removed through circulation of drilling fluids. However, the drilling fluids are used primarily to drill the hole and lubricate downhole tools, and not to create an intrinsically stable borehole as is needed using short-radius technology.

Information on the direction of drilling is provided by the TFI which travels behind the bit and relays drill bit orientation and inclination through a telemetry system to a computer located at the drill rig. This information is nearly real-time data in that it is provided at 60 second intervals. This reduces the frequency of downhole surveys. However, down-hole surveys are used to check the accuracy of the data provided by the TFI because it does not provide information on directions, TVD, and MD. These values must be estimated or determined with the single-shot survey.

The flexible HDPE outer casing and inner casing/screen assembly are advanced directly behind the drilling assembly, eliminating the need to remove the tools prior to installing the well. The drilling tools are removed through the casing after collapsing the drill bit. Once the casing/screen assembly has been installed, a filter pack consisting of HDPE beads may be installed through the end of the casing/screen assembly. This is accomplished by circulating fluid while pumping in the filter pack material.

During drilling of AMH-3 and AMH-4 using the ECES system, several technical issues were encountered. These included the following:

- The drilling fluid program designed to lubricate downhole tools and stabilize borehole by removal of cuttings may not be adequate to address geotechnical issues. This was evidenced by stuck tools and difficulty in advancing the bit and casing/screen assembly after interruption of mud circulation during borehole surveys. These observations point to a need for more stringent control of the fluid program.
- Casing and screen became stuck in the borehole, likely due to skin friction caused by the inadequate annular space and excess sand volumes remaining in boreholes

- Inaccurate survey data recorded by the TFI (note: more recent, sophisticated oil field TFI will now provide real-time data on the orientation and progress of the drill bit.
- Power of rig was able to advance casing and bit faster than cuttings could be removed, requiring great finesse in drilling
- When excessive down pressure is used, the HDPE casing can be pushed over the drill bit resulting in damages to the casing. This also does not allow full expansion of the wing bit. Restriction of bit wings results in an inadequate borehole diameter for proper circulation and cuttings removal and casing advancement
- Formation collapse during filter pack emplacement, and general inability to install filter pack through casing.

5.1 Advantages and Disadvantages

Both technologies were ultimately successful in installing horizontal wells in uncemented sediments at the SRS. Each of the technologies described above has specific advantages and disadvantages which are summarized in Table 5.2. As research continues, it may be found that each technology has specific circumstances under which it is best applied.

Short Radius Technology

The major advantage to the short-radius technology is that the curve can be built in less horizontal distance. This could be an advantage in areas where space is limited. Another potential advantage is that an intrinsically stable borehole must be maintained. This provides more flexibility in the types of well that can be installed. In addition, various drill bits may be used and an under-reamer is not necessary. This should provide an advantage in both rate of penetration and in drilling harder, more consolidated materials.

There are several major disadvantages to using short-radius technologies, some of which are apparent from the problems encountered during the installation of the first two horizontal wells (AMH-1 and -2). The major disadvantage of short-radius technology is the lack of down-hole directional control. The only controls are the orientation of the whipstock, the configuration of the rigid drill mandrel, i.e., the number and type of stabilizers used, and the manner in which the hole is drilled (bit rotation, rate of penetration, and drilling fluid program). There is no steerable BHA.

TABLE 5.2
COMPARISON OF DRILLING PERFORMANCE

Short Radius Technology	ECES System
<i>Advantages</i>	<i>Advantages</i>
Less lateral distance/space required to drill the curve	Steerable drill bit (better directional control)
Intrinsically stable borehole provides for:	Down-hole survey tools travel with bit
1) More flexibility in drill bit selection	Casing installed as hole is drilled
2) More flexibility in the type of well construction materials which can be installed	Casing does not rotate minimizing lateral drift
	Whipstock is not necessary and kick off procedures are simplified eliminating unnecessary procedures
	More flexibility in drilling shallower or deeper horizontal wells. Well head may be displaced laterally from target zone (i. e. target zone beneath a building or lagoon)
<i>Disadvantages</i>	<i>Disadvantages</i>
Lack of down-hole directional control	Lateral distance between well head and horizontal screen increased: unsuitable where working area is limited
Drilling tools must be removed prior to casing installation	Excessive skin friction on casing/screen assembly during installation
High bit rotation increases potential for lateral drift	Rig had too much power for types of sediments, requiring great finesse in drilling
Down-hole surveys must be performed periodically to obtain information on drilling performance	Drilling must be performed utilizing an underreamer wing bit when casing/screen assembly installed during borehole installation
Installation of a whipstock is necessary for directional control	Formation collapse around casing/screen assembly precludes the installation of artificial filter pack

This leads to several of the problems previously listed including drift caused by rapid bit rotation, and loss of angle in loose formations. In addition, if the whipstock is disturbed during the drilling process, the horizontal borehole may be drilled in the wrong direction. Disturbances of the whipstock could easily occur due to the larger force (20,000 lbs down pressure) often used in drilling, resulting in deflection of the bit away from the target azimuth.

A second major disadvantage is that the drilling tools must be removed prior to installation of the well. While this provides the opportunity to use various standard drill bits, it also could result in borehole collapse before the well is completed.

ECES System

The major advantage to the ECES system is that a steerable BHA is used. This allows corrections and adjustments to be made from the surface as needed. The down-hole survey tools travel with the drill bit providing nearly real-time data on the direction of the borehole. In addition, the casing is advanced with the BHA while drilling, which reduces the potential for drift in unconsolidated sediments. The net result of the advantages described above is better directional accuracy. In addition, the steerable motor compensates for loss of angle in the softer sediments. The off-set of the BHA, as set by the centralizers, reduces the chance of angle loss during drilling of the horizontal section.

Two other advantages to the ECES system are also evident. The critical step of setting a whipstock is not necessary which simplifies the procedure at the KOP. In addition, shallower horizontal wells, and wells of various depths can be drilled in a much simpler manner. The system used during this project also provides an advantage to hitting the target zone by using an adjustable mast tophead drive drill rig. The rig can drill at an angle to a KOP to hit very shallow target zones, regardless of the radius of the curve used to drill to the horizontal section.

Several disadvantages of the ECES system are also apparent. Due to the large radius of curvature (relative to short-radius technology), more distance between the well head and the horizontal screen is required. This could be a disadvantage when space is a constraint but it can be an advantage when the target zone is beneath a building or lagoon. Loss of angle can also be a problem, but this appears to be less acute than with short radius technology.

Another disadvantage is the type of drill bit used. Whenever the casing is installed as the borehole is drilled, the drill rods travel inside the casing. Consequently, the drill bit, which drills a larger

hole than the outside diameter of the casing, must be withdrawn through the casing. Therefore, an underreamer (wing bit) is required. This type of bit does not cut a borehole as effectively as standard roller-cone drill bits and its rate of penetration is typically slower. More consolidated formations such as clay lenses are difficult to drill using this type of bit. In addition, excessive down pressure on the casing during drilling may cause the casing to slip over the bit preventing the wings from opening fully. This results in a borehole diameter inadequate for cuttings removal and casing advancement. It could also result in directly pushing the casing through the formation. This could damage the casing and ultimately result in stuck tools. In some cases, it may be necessary to drill a pilot hole to minimize the amount of cutting by the under reamer. It should be noted that wells AMH-3 and AMH-4 were successfully installed by first advancing a pilot borehole and subsequently installing the casing/screen assembly in the resultant reamed borehole. The contractor reverted back to the single pass borehole with attached casing/screen assembly on the deeper well, AMH-3.

Another disadvantage of the ECES system in unconsolidated sandy formations is that excessive skin friction between the borehole wall and the casing may build up as the casing is advanced. The DHM drilling method utilizes the arc of the BHA to drill a consecutive set of concave and convex arcs through the lateral section of the target zone. This can be a cause of excessive drag and friction on the casing/screen assembly resulting in slower drilling rates, damaged well materials, and/or stuck tools.

In conclusion, when compared to the conventional horizontal drilling techniques, the ECES system is a more efficient, simple method of installing horizontal wells primarily because of the steerable drill bit. The ECES system offers greater accuracy by using real-time data for surveying and better steering and directional control in the lateral section. The system could be enhanced by incorporating advanced oil field TFI technology. This could provide better real-time directional data than was available for this project. Unfortunately, at the time of this project, that equipment was not capable of negotiating the relatively short radius curves employed for shallow drilling. The equipment is currently undergoing miniaturization and should be available for future horizontal drilling projects.

6.0 CONCLUSIONS AND RECOMMENDATIONS

Horizontal wells provide improved injection and extraction technologies for effective remediation of soils and groundwater. The purpose of this project was to demonstrate the feasibility of using the ECES system to install horizontal wells. Two wells were to be installed parallel to each other,

one in the vadose zone and one below the water table, to specific target depths, target lengths, and positioned within target orientations. The prototype drilling system utilized was designed by Eastman Christensen for environmental applications. This project was the first full-scale demonstration of the capabilities of the system and consequently, several deficiencies were identified. As a result of persistent geologic and mechanical conditions experienced at the site, certain modifications were made to the planned procedures to successfully complete the wells. In order to complete the project in a timely manner, the following modifications were implemented:

- wells were installed to shorter MD's than planned
- final well borings were drilled with an improved mud program under the direction of a mud engineer
- pilot horizontal boreholes were drilled without casing/screen assemblies; casing/screen assemblies were installed subsequent to initial borehole advancement

The original work plan called for two horizontal wells to be installed with horizontal lengths of 300 feet. Both wells were completed shorter than that distance, but were installed very accurately within their target depths and acceptable accuracy within target orientations. The completed well lengths were limited in part to the drilling fluid circulation system. Although the drill rig could advance the bit and casing at relatively rapid rates, the circulation system was unable to remove the formation cuttings generated by the rapid rate of penetration. This problem was aggravated when it was necessary to stop pumping in order to perform a downhole survey. Production models of the pumps, which are based on larger, less portable oil field pumps, will be more rugged than the prototypes used on this project, and will be less subject to downtime and delays.

An important modification to the proposed plan was an engineered mud program designed to improve borehole stability during drilling. During the original drilling program, a constant drilling mud viscosity and weight were maintained during the entire length of the borehole. The low viscosity mud was unable to retain sediments in suspension efficiently without a corresponding increase in velocity or reduction in sediment volume. As a result, the mud program was modified to include the addition of polymers to increase the viscosity without increasing the mud weight. In addition to the use of polymers, the mud weight and viscosities were varied through the course of the borehole. For example, the volume of sand removed from the borehole was monitored by observing sand volume on the shaker screen. If sand volume decreased while advancing the drill bit, additional polymers were added to the mud to increase the viscosity and entrain/remove more solids from the borehole. Conversely, dispersants or water were added to reduce viscosity or weight and cause sand to drop out of suspension. Modification of the mud program improved

drilling performance on the final attempts of well installation. The following drilling fluid properties and additives were used for the successful completion of both wells:

- low weight (8.6 to 9.0 lbs/gal)
- high viscosity (Marsh funnel viscosity 95 to 105 seconds)
- bentonite gel
- bentonite extenders (Ben-Ex™)
- polymer (New-Drill™)

Another important modification to the proposed plan was drilling the borehole without the casing. The original plan called for the casing/screen assembly to be installed in the borehole behind the drill bit. However, the casing was determined to restrict advancement of the borehole due to the added weight and increased friction on the borehole walls. In addition, the slotted screen was believed to produce a flow restriction effect reducing the effectiveness of the drilling fluid to remove the cuttings from the borehole. Consequently, pilot boreholes were drilled without the casing/screen assemblies in the successful attempts. This reduced drag on the bit, pull-down-increased the pressure on the drill string, and allowed cuttings to be brought to the surface more efficiently. Advancing the BHA without pulling the casing increased the risk of borehole collapse and associated difficulties with well construction.

As expected for innovative drilling programs, the original design had to be modified to accommodate field conditions and acceptable targeted depths and lengths. The drill rig and directional tools performed as planned, with a few modifications, and the steering motor with eccentric stabilizers accurately guided the casing to the target locations. The drilling fluid program and well installation procedures underwent considerable modification to successfully complete the wells. Geologic and mechanical conditions were overcome by modification to the survey equipment, drill rig mechanics and mud program, and the wells were installed essentially to the target depths and orientations. The target depths were not reached without several modifications to the program plan, as noted in the final section.

By incorporating lessons learned from this program, the ECES system can be a viable method for more routine installation of horizontal wells at SRS and in unconsolidated sediments elsewhere. The use of this system is a simplification and improvement over the methods employed in the first phase of the demonstration project (short radius technology). However, further improvement to the system and procedures can increase drilling performance and enhance successful well completion. The following modifications and recommendations are based on information and

knowledge gained through the course of this project:

- Begin the project with an engineered mud system and modify it as time, field conditions and experience require.
- Simplify the mechanics of the drill rig to reduce the number of procedures required to drill, and the time needed to make connections and trip drill pipe.
- Drill a small diameter pilot hole in the lateral section of the well prior to reaming with underreamer and casing/screen assembly installation.
- Equip the drill rig with a more durable mud pumping system to decrease downtime due to mechanical failures.
- Reduce the diameter of surface casing and well casing. Smaller boreholes are easier to retain stability and remove cuttings.
- More sophisticated and reliable downhole survey instruments to give direction and TVD and MD as the BHA is being advanced.

REFERENCES

- Aadland, R. K. and H. W. Bledsoe, 1990, *Classification of Hydrostratigraphic Unit at the Savannah River Site, South Carolina*. WSRC-RP-90-987, Westinghouse Savannah River Company, Savannah River Laboratory, Aiken, SC
- Aadland, R. K., A. D. Smits, and P. A. Thayer, 1992, *Geology and Hydrostratigraphy of the A/M Area, Savannah River Site (SRS), South Carolina (U)*, WSRC-RP-92-440, Westinghouse Savannah River Company, Savannah River Site, Aiken, SC 29808
- Kaback, D. S., B. B. Looney, J. C. Corey, and L. M. Wright, 1989, *Well Completion Report on Installation of Horizontal Wells for Insitu Remediation Tests*, WSRC-RP-89-784, Westinghouse Savannah River Company, Savannah River Site, Aiken, SC 29808
- Papadopoulos, S.S. and Associates, Inc., 1986, *Hydrogeologic Conditions in the Vicinity of the M-Area Settling Basin and Lost Lake*, Prepared for E. I. du Pont de Nemours and Company, Savannah River Plant, Aiken, SC 29808
- SCDHEC, 1985, South Carolina Well Standards and Regulations R.61-71, Groundwater Protection Division, South Carolina Department of Health and Environmental Control.
- Siple, G. E., 1967, *Geology and Groundwater of the Savannah River Plant and Vicinity, South Carolina*. U. S. Geological Survey Water-Supply Paper 1841, 113 p
- Westinghouse Savannah River Company, 1992a, *Hydrogeologic Setting of the A/M Area: Framework for Groundwater Transport (U)*, WSRC-TR-92-355, Prepared for Westinghouse Savannah River Company, Savannah River Site, Aiken, SC 29808

APPENDIX A
DETAILED WELL PLANS

**Horizontal Well Constuction Plan
for the Savannah River Site**

prepared for

Westinghouse Savannah River Company

by

Eastman Christensen Environmental Systems

January 1991

Horizontal Well Construction Plan for the Savannah River Site

Table of Contents

1. Introduction and Overview	3
2. Directional Drilling Plan	4
3. Drilling Plan for the Shallow Well	9
4. Drilling Plan for the Deep Well	18
5. Material and Tool List	27
6. Clearance Report	32

1. Introduction and Overview.

This is the operations plan for constructing two horizontal wells at the Savannah River Site. These wells are being drilled to demonstrate downhole motor drilling technology for installing horizontal wells and to test new approaches for remediation of soil and groundwater.

The job objectives are (1) place a 300' long horizontal section above the water table at -105' elevation and (2) place a 300' long horizontal section below the water table at -170' elevation. These wells are to be drilled parallel to the process sewer line that runs from the M area to the basin area, with the shallow well being placed directly over the deep well.

The purpose of this plan is to (1) establish guidelines for the well construction, (2) provide a sequence of the events that will occur, and (3) help identify the tools, materials, and operations that are required.

The general plan is to rig up, construct the shallow well (-105' elevation) from 30° rig position, then construct the deep well (-170' elevation) from the vertical position.

The drilling operations at the SRS will be conducted 24 hours per day. This will require each drilling crew to work one 12 hour shift per day. A daily meeting will be conducted with Eastman Christensen, oversight, and Westinghouse personnel to discuss the daily drilling activities.

2. Direction Drilling Plan

The horizontal drilling project at the SRS requires Eastman Christensen to drill two horizontal wells. These wells are to be constructed below the process sewer line path that runs from the M area to the basin. The shallow well will be drilled first with the horizontal section above the water table. The deeper well will be drilled below the water table directly underneath the shallow well.

2.1 The shallow well directional drilling plan is as follows:

2.1.1 Well data:

Kick off point (KOP)	46' M.D.
Mast position	30° from vertical
Conductor hole diameter	16"
Desired direction	S10E (uncorrected)
Desired depth	105' ($\pm$ 10' elevation)
Zone top	95'

2.1.2 Shallow well drilling program overview

Auger 16" hole for placement of the conductor pipe. The conductor pipe will extend 24" from ground level.

Auger 12" hole to a measured depth of 46'.

The KOP is now set at 46'. We will now build a 110' radius curve to a measured depth of 161'.

From this point we will drill the horizontal section of the well. Inclination will be maintained at 90° during this 300' section.

2.2. The deep well directional drilling plan is as follows:

2.2.1 Well Data:

Kick off point (KOP)	50'
Mast position	Vertical
Conductor hole diameter	16"
Desired direction	S10E (uncorrected)
Desired depth	170' elevation ($\pm 10'$)
Zone top	160'

2.2.2 Deep well drilling program overview

Auger 16" hole for placement of the conductor pipe. The conductor pipe will extend 24" from ground level.

Auger 12" hole to a measured depth of 50'.

The KOP is now set at 50'. We will now build a 110' radius curve to a measured depth of 223'.

From this point we will drill the horizontal section of the well. Inclination will be maintained at 90° during this 300' section.

2.3 Directional Control

2.3.1. Both wells will be drilled using bottom hole assemblies designed to build a 110' radius curve. The BHA for both wells will consist of the following downhole tools:

A specially designed expanding/collapsing drill bit. This will allow us to case the hole as we drill.

A "short" motor (10') used to provide power to the bit.

A tool face indicator (TFI) used to provide real time downhole parameters (inclination and tool face orientation) every 60 seconds.

2.3.2 Orienting the drill string will be done using surveys provided by the Tool Face Indicator. Keeping tool face at "high side" will allow us to maintain the desired direction. Off bottom surveys will be taken periodically to insure proper orientation. Upon completion of each section drilled (curve and horizontal) a Magnetic Multi-Shot will be run to insure wellpath accuracy.

2.3.3. Plot no. 1 represents the well path for both proposed wells. The shallow well will be drilled to a measured depth of 461'. The deep well will be drilled to a measured depth of 523'. The horizontal sections, end of build to the end of hold, of both wells will be within $\pm 10'$ of the desired depth.

2.3.4 Plot no. 2 is a represents the two proposed wells in relationship to AMH-1 which was drilled by Eastman Christensen in 1988. The plan view shows that the two proposed wells will be drilled to the southeast and AMH-1 was drilled to the northeast. There is little concern that the well paths will be in conflict (see the attached Clearance Report).

EASTMAN CHRISTENSEN

Structure : Environmental Well : Horizontal
Field : Savannah River Location : Savannah River

EASTMAN CHRISTENSEN
A Baker Hughes company

EASTMAN CHRISTENSEN

Structure : Environmental

Well : Horizontal

Field : Savannah River Location : Savannah River

EASTMAN CHRISTENSEN
A Baker Hughes company

3. Drilling Plan for the Shallow Well

3.1 Well Data:

Desired depth	-105' elevation $\pm 10'$
Desired direction	S10°E uncorrected
Kick off point	46' MD
Mast position	30° from vertical
Conductor hole diameter	16"
Conductor OD	12" nom (12 3/4")
Conductor length	20' (-17.4' elevation)

3.2 The general plan for constructing the shallow well is auger and set a 12 3/4" conductor, drill the curve to intersect the top of the target zone, and drill 300' of horizontal wellbore. The planned drilling operations are as follows:

3.2.1. Place 4 mil plastic sheeting on the location so that it will be under all the trailers. Spot the rig, pipe, and fluid trailers for drilling from the 30° position at S10°E (reference magnetic north). Finish the location preparation, locate the water source, fill the rig and generator fuel tanks.

3.2.2. Set up an area to steam clean our drilling equipment and well materials. Place 4 mil plastic sheeting under steam clean area. Steam clean the conductor, 14" auger, 12" auger, 10" casing, drill pipe, motors, TFI, and bits.

3.2.3. Prepare to auger 16" hole for the conductor pipe. Make up 16" auger bit, 14" fluted auger, and drive adaptor to the top drive. Make up any 2 7/8 IF connections to the minimum recommended make up torque of 5600 ft-lbs. Keep the top drive torque below 3000 ft-lbs when drill pipe is used in the auger string.

3.2.4. Strap the conductor and auger the conductor hole to allow 24" of the conductor pipe to extend above the ground. Pull and lay down the augering tools. Set the conductor into the the hole. Mix and grout the conductor using grout mixer. Grout the conductor to the surface through a 1" tremie tube with portland cement mixed with 2% CaCl₂. This should take 10-12 sks of cement.

3.2.5. Clean up the auger tools and finish rigging up while waiting for the conductor grout to set, perform rig maintenance and make any needed repairs, install the shaker screens, tally the drill string, make up the bit to the motor, and assemble the lower casing joint. Fill the steel pits with water and mix the drilling fluid. Mix in 9 sacks of bentonite to give 15 ppb gel in the drilling fluid (adjust the vis to 40-45 seconds).

3.2.6. Pick up the 12" auger and drill out the conductor to the kick off point.

3.2.7. Nipple up the bell nipple and spacer spools onto the conductor. Fit the flowline to the shale shaker possum belly.

3.2.8. Finish assembling the lower joint and lower it into the hole. Turn on and initialize the TFI tool. Make up the TFI to the motor and bit and check the orientation and pulser. Lower the curve drilling BHA into the lower joint with the crane. Screw into the curve drilling BHA with the top drive. Pull up and surface test the TFI, motor and bit.

3.2.9. Pick up the first dual joint and make it up to the motor assembly and shoe joint. The first joint of drill pipe will be the joint of non-magnetic drill pipe.

3.2.10. Orient the "toolface" to high side to build angle for the curve. Lower the bit within 3' of bottom and record the drag. Do not tag bottom with the pump off to avoid sticking the bit wings. Bring the mud pump on to open the bit wings. Record the depth, pump pressure, flowrate, time, and remarks.

3.2.11. Start drilling the curve with 150 GPM and keep the toolface oriented to high side. Drill as fast as possible to minimize the effects of hole erosion on the angle build rate. Record the depth, WOB, pump pressure, flowrate, time, toolface orientation, and remarks on 1' to 5' intervals.

Install a stand off band at each connection below the conductor.

3.2.12. Plot the hole inclination as a function of measured depth. Project the well path depth for 88°-90° inclination.

3.2.13. Drill to the end of the curve, pull the drilling assembly, run final curve surveys if needed, and complete any remaining curve drilling operations. Circulate bottoms up or until the returns clean up. It will be necessary to space out the curve casing so that the top joint of casing can be landed with the mast in the down position.

3.3 Curve Grouting Procedure

The curve casing is grouted to isolate open zones in the curve and to provide structural support for the curve casing. The grouting will be accomplished using a procedure similar to a stab-in cementing system. This system uses drill pipe inside the casing to place cement around the 10" curve casing.

3.3.0 Well Data:

Conductor depth	-17.4' elevation
Estimated TD	-105' elevation
Hole size	12 1/4" (.1882 cu. ft/ft)
Casing	10", 15.5 SDR, HDPE
Drill pipe	2 7/8", 2 7/8" IF
Cement Plug	Baker Oil Tools

3.3.1. Pick up the curve cementing plug and knuckle joint and run in the well on drill pipe. Tally the drill string and adjust the length to set the plug into the casing shoe with the drill pipe landed in the lower tong. Fill the casing and drill pipe annulus as the plug is run through the casing. Monitor the the force required to push the plug through the curve. The last 20', flush out the casing shoe by circulating through the drill pipe and cementing plug with the rig pump. Set 500 lbs force on the plug.

Check the seal on the plug by filling the drill pipe casing annulus, draining the riser, and observing the fluid level and the flow line.

3.3.2. Circulate drilling fluid with the rig pump at 100 - 200 GPM

through the drill pipe and plug while preparing to mix cement.

3.3.3. Pump 10 bbls of water for a spacer.

3.3.4. Batch mix and pump a lead slurry of 22 sacks of cement grout or until good cement is seen at the surface. The cement grout is Portland Cement Type 1, with 10% NaCl, 2% sodium metasilicate, and 10% gypsum. Cement volume is annular capacity plus 50% excess.

The grout slurry density = 13 ppg, yield=2.26 ft³/sack, water =12.14 gallons/sack, thickening time 3 hrs, 24 min, free water 0%.

Materials needed for the 22 sks of lead slurry:

22 sks of Portland Cement @ 94 lbs/sk = 2068 lbs

10% NaCl/sk=10.125 lbs/sk @ 22 sks=223 lbs

2% sodium metasilicate/sk=1.88 lbs/sk @ 22 sks=41 lb

10% gypsum/sk=9.4 lbs/sk @ 22 sks=207 lbs

12.14 gallons/sack of water @ 22 sks=267 gal.

Batch mix and pump a tail slurry to place a stronger cement slurry around the casing shoe and bottom 20' of casing. Pump 10 sks of Portland cement with 2% CaCl₂, yield=1.18 ft³/sk, density=15.6 ppg, water=5.6 gallons/sk.

Materials needed for the 10 sks of tail slurry:

10 sks of Portland Cement @ 94 lbs/sk = 940 lbs

2% CaCl₂/sk=.934 lbs/sk @ 10 sks=9.34 lbs

5.6 gallons/sack of water @ 10 sks=56 gallons

Note: NaCl and CaCl₂ are measured in weight percent of water the other additives are measured in weight percent of the dry cement.

A word of caution is in order at this point. As the cement grout slurry enters the annulus the curve casing will start to float. The force required to keep the casing from floating out the hole is the buoyancy ΔTVD of the cement grout slurry.

$$\text{Floating force} = \Delta \text{TVD grout} \cdot (d_1 - d_2) \cdot \text{area} \cdot .052$$

$$= 85 \cdot (13 - 8.4) \cdot 10.75^2 \cdot \pi / 4 \cdot .052$$

$$= 2270 \text{ lbs}$$

Here ΔTVD grout is the vertical height of the cement grout column, d_1 is the density of the grout (ppg), d_2 is the density of displacing fluid (ppg), and area is the cross sectional area of the curve casing.

3.3.5. Monitor the grout density with a mud balance. Collect wet samples of the grout during the cement job. The wet samples will be allowed to set on surface and will give an indication that the cement is thickening.

3.3.6. Break off the cementing hose and flush the cementing lines up to the drill pipe pin. Drop the drill pipe plug and displace the cement grout out of the drill string with 26 gallons of water. (pump the capacity of the drill string). Bump the plug with 200 psi.

Open the valves on the conductor and flush the cement from the bell nipple and spacer spools. Clean up any cement circulated to the surface.

Have 20# of sugar on hand to disperse cement if needed.

3.3.7. Hold the cementing plug in place and monitor the drill pipe ID and the drill pipe/casing annulus for leakage. Monitor the surface samples to help estimate the thickening time. As the cement starts to harden rotate the plug 1 to 2 revolutions every 30 minutes to weaken the cement bond on the casing plug. Once the cement has hardened pull the pipe and plug free. The plug will take ≈ 8000 lbs to shear it from the running tool. If the plug will not readily pull free try to break the bond with right hand rotation and pushing and pulling on the drill pipe. If this fails to release the plug, try to backout the center of the plug with left hand rotation. Caution: Do not exceed 3000 ft-lbs of torque (≈ 1000 psi rig pressure) when turning to the left to avoid backing off in the drill pipe.

If left hand rotation fails to release the plug center, pull out of the shear pins in the running tool. The plug will have to be removed with a rotary shoe on a 4 3/4" motor.

- 3.3.8. Pull out of the hole with the drill string and cementing plug.
- 3.3.9. If the cement does not return to surface or falls back, prepare to tremie grout into the annulus. Run 3/4" nom. OD steel tubing into the annulus to the cement top or as far as possible.
- 3.3.10. Establish circulation through the tremie tube.
- 3.3.11. Mix and pump the appropriate grouting materials.
- 3.3.12. Pull the tremie pipe to -10' elevation to grout the upper annulus with cement grout. Grout the upper section of the well. Pull the tremie tube from the well and lay it down.
- 3.3.13. Clean the cement lines and mixing equipment, disassemble the cementing lines and rig down the cement equipment. Clean up any cement that is circulated to surface
- 3.3.14. WOC and continue to hold the curve casing in place at the surface until the cement develops enough strength to support the casing. Observe the wet samples to determine if the cement grout is hardening.
- 3.3.15. While WOC, perform needed rig maintenance, clean and store the curve drilling tools, clean out the mud tank if needed. Steam clean all the horizontal drilling tools and well materials.
- 3.3.16. Tally and prepare tools and casing to drill the lateral section. Assemble the lower casing joints and casing shoe. Install the 6 5/8" OD casing collet in the casing drive and 6 5/8 jaws in mast clamp.
- 3.3.17. Pull the riser and cut off the excess casing after the cement grout has set enough to support the curve casing. Re-install the riser and flowline.
- 3.3.18. Pre-treat the drilling fluid with 1/4 ppb of soda ash to reduce the effects of cement contamination. Make up the 8 1/2" bit, xo sub, and 4 3/4" motor to drill out the 10" casing shoe (the motor

will require the special oversize stabilizers). Run in the hole to the shoe and drill out 4'-5' of rat hole. Ream the rat hole and circulate the hole clean. Pull out of the hole to drill the horizontal section.

3.4 Horizontal Drilling

Drilling the horizontal section is the next operation performed after the cementing plug is removed. The horizontal section will be casing drilled to install a 6" nom. HDPE screen into the well. The plan for drilling the horizontal section is outlined as follows:

3.4.1. Assemble and torque the 8 5/8" expanding bit, 4 3/4" motor, tool face indicator, knuckle joint and top sub. Turn on and initialize the TFI tool. Make up the TFI to the motor and bit and check the orientation and pulser.

3.4.2. Pick up the lower casing joint and set it in the mast clamp. Pick up the horizontal motor assembly screw into it with the top drive and test the TFI, motor, and bit wings.

3.4.3. Trip in hole with dual string to end of the curve casing, monitor and record the pull down force while tripping in. The first joint of drill pipe will be non-mag and the slotted 6" HDPE will be used to line the hole. Install centralizers at each screen connection.

3.4.4. Trip to the 10" casing shoe start the mud pump, orient to desired direction. Do not tag bottom to avoid sticking the bit wings. Adjust the drilling variables such as WOB, flowrate, and motor pressure as needed to effectively drill. If the drilling rate is over 20 feet per hour be sure the hole is being cleaned by the drilling fluid.

3.4.5. Continue to drill the slotted screen into place. Drill with solid casing to place unslotted pipe at the top 20' to 30' of the well. Survey when needed. Record the drilling data on 1' to 5' intervals while drilling.

3.5. Shallow well development and filter pack

Development plan for shallow horizontal well requires that the screen slots be cleaned and a gravel pack installed between the 6" slotted screen and the well bore. The plan for the shallow well development and filter pack is:

3.5.1. Casing drill 300' of 6" HDPE slotted screen in the horizontal section.

3.5.2. Circulate the hole clean, take any needed surveys, and pull out of the hole with the inner drilling assembly.

3.5.3. Dump the drilling fluid, clean the steel pits, and fill them with clean water.

3.5.4. Make up the 6" casing plug, plug running tool, and wash sub. Run in the hole to the 6" shoe joints. Wash the last 20' and set the plug into the casing shoe.

3.5.5. Set the plug in the 6" casing shoe with up to 2000 lbs. Release the 6" casing plug from the running tool by pulling back on the drill pipe.

3.5.6. Pull the wash sub back to the screen slots , drop the ball to seal the plug running tool.

3.5.7. Pull out of the hole and wash the 6" slotted screen at 300 GPM with clear water. Keep the pipe moving while washing the screen to avoid damaging the plastic casing.

3.5.8. Continue to wash the well screen until the returns are clean. Be sure to wash the entire screened interval.

3.5.9. Lay down the wash sub and retrieve the ball.

3.5.10. Trip in the hole with plug running tool and set down on the casing plug. Establish circulation with water.

- 3.5.11. Mix and pump HDPE pellets to start the filter pack. When HDPE pellets reach the surface lift the riser, install the 6"x10" annular pellet screen, cut hole into 6" pipe above the flow line.
- 3.5.12. Continue to pump HDPE pellets. Monitor the pump pressure and the amount of HDPE pellets that are pumped (a pressure increase indicates the beads are packing off). The bulk density of the HDPE pellets is 45 lbs/cubic foot.
- 3.5.13. Pull the running tool off the plug, pump clean water to flush the HDPE pellets out of the drill pipe.
- 3.5.14. Set back down on plug, pump the dart to seal plug.
- 3.5.15. Trip out of the hole with the drill pipe.
- 3.5.16. Pull the riser and flowline. Remove the HDPE pellets from the top 10' of the 10" X 6" casing annulus.
- 3.5.17. Run a tremie tube down to the top of the HDPE pellets. Mix and pump portland cement with 2% bentonite to the surface to seal the 6" X 10" casing annulus.
- 3.5.18. Cut off the 6" casing leaving 24" above ground level. Install a 6" 8-round adaptor on the 6" casing stub and cap the casing.
- 3.5.19. Construct a wooden form to place 6" x 5' x 5' concrete pad around the well head. Mix sack crete and pour into the form. Install 4" posts in each corner and fill posts with concrete.

4. Drilling Plan for the Deep Well

4.1. Well Data

Desired depth	-170' elevation $\pm 10'$
Desired direction	S10°E uncorrected
Kick off point	46' elevation
Mast position	Vertical
Conductor hole diameter	16"
Conductor OD	12" nom (12 3/4")
Conductor length	20' (-18' elevation)

4.2. The general plan for constructing the deep well is auger and set a 12 3/4" conductor, drill the curve to intersect the top of the target zone, and drill 300' of horizontal wellbore. The planned operations are as follows:

4.2.1. Raise the mast to it's vertical position, move the pipe and fluid trailers if necessary.

4.2.2. Steam clean the drilling equipment and well materials. Steam clean the conductor, 14" auger, 12" auger, 10" casing, drill pipe, motors, TFI, and bit.

4.2.3. Prepare to auger 16" hole for the conductor pipe. Make up the 16" auger bit, 14" fluted auger, and drive adaptor to the top drive. Make up any 2 7/8 IF connections to the minimum recommended make up torque of 5600 ft-lbs. Keep the top drive torque below 3000 ft-lbs when drill pipe is used in the auger string.

4.2.4. Strap the conductor and auger the conductor hole to allow 24" of the conductor pipe to extend above the ground. Pull and lay down the augering tools. Set the conductor into the the hole. Mix and grout the conductor with the grout mixer. Grout the conductor to the surface through a 1" tremie tube with portland cement mixed with 2% CaCl₂. This should take 10-12 sks of cement.

4.2.5. Clean up the auger tools and prepare to drill the curve section while while waiting for the conductor grout to set. Clean up, perform rig maintenance, and make any needed repairs. Check the

shaker screens for holes and empty the sand trap if it is full. Tally the drill string, make up the bit to the motor, and assemble the lower casing joint. Mix more drilling fluid if needed.

4.2.6. Pick up the 12" auger and drill out the conductor to -50' elevation.

4.2.7. Nipple up the bell nipple and spacer spools onto the conductor. Fit the flowline to the shale shaker possum belly.

4.2.8. Finish assembling the lower joint and lower it into the hole. Turn on and initialize the TFI tool. Make up the TFI to the motor and bit and check the orientation and pulser. Lower the curve drilling BHA into the lower joint with the crane. Screw into the curve drilling BHA with the top drive. Pull up and surface test the TFI, motor and bit.

4.2.9. Pick up the first dual joint and make it up to the motor assembly and shoe joint. The first joint of drill pipe will be the joint of non-mag drill pipe.

4.2.10. Orient the "toolface" to the desired hole direction to build angle for the curve. Lower the bit within 3' of bottom and record the drag. Do not tag bottom with the pump off to avoid sticking the bit wings. Bring the mud pump up to open the bit wings. Record the depth, pump pressure, flowrate, time, and remarks.

4.2.11. Start drilling the curve with 150 GPM and keep the toolface oriented to high side. Drill as fast as possible to minimize the effects of hole erosion on the angle build rate. Record the depth, WOB, pump pressure, flowrate, time, toolface orientation, and remarks on 1' to 5' intervals.

Install a stand off band at each 10" casing connection.

4.2.12. Plot the hole inclination as a function of measured depth. Project the well path depth for 88°-90° inclination and at this depth pull the curve drilling assembly.

4.2.13. Circulate the hole clean, pull the inner assembly, and take the final surveys if they are needed. Prepare to cement the curve casing.

4.3 Deep Well Curve Grouting Procedure

The curve casing is grouted to isolate open zones in the curve and to provide structural support for the curve casing. The grouting will be accomplished using a procedure similar to a stab-in cementing system. The plan is to grout the casing around the curve to the KOP from the bottom up then tremie cement grout to surface.

4.3.0. Well Data

Conductor depth	-18'
Estimated TD	223' MD
Hole size	12 1/4"
Casing	10", 15.5 SDR, HDPE
Drill pipe	2 7/8", 2 7/8" IF
Cement Plug	Baker Oil Tools

4.3.1. Pick up the curve cementing plug and knuckle joint and run in the well on drill pipe. Tally the drill string and adjust the length to set the plug into the casing shoe with the drill pipe landed in the lower tong. Fill the casing and drill pipe annulus as the plug is run through the casing. Monitor the the force required to push the plug through the curve. The last 20', flush out the casing shoe by circulating through the drill pipe and cementing plug with the rig pump. Set 500 lbs force on the plug.

Check the seal on the plug by filling the drill pipe casing annulus, draining the riser, and observing the fluid level and the flow line.

4.3.2. Circulate drilling fluid with the rig pump at 100 - 200 GPM through the drill pipe and plug while preparing to mix cement.

4.3.3. Pump 10 bbls of water for a spacer.

4.3.4. Batch mix and pump a lead slurry of 25 sacks of cement grout. The cement grout is Portland Cement Type 1, with 10% NaCl, 2% sodium metasilicate, and 10% gypsum.

The grout slurry density = 13 ppg, yield=2.26 ft³/sack, water =12.14 gallons/sack, thickening time 3 hrs, 24 min, free water 0%.

Materials needed for the 25 sks of lead slurry:

25 sks of Portland Cement @ 94 lbs/sk = 2350 lbs
10% NaCl/sk=10.125 lbs/sk @ 25 sks=253 lbs
2% sodium metasilicate/sk=1.88 lbs/sk @25 sks=47 lbs
10% gypsum/sk=9.4 lbs/sk @ 20 sks=235 lbs
12.14 gallons/sack of water @ 20 sks=304 gallons

Batch mix and pump a tail slurry to place a stronger cement slurry around the casing shoe and bottom 20' of casing. Pump 10 sks of Portland cement with 2% CaCl₂, yield=1.18 ft³/sk, density=15.6 ppg, water=5.6 gallons/sk.

Materials needed for the 10 sks of tail slurry:

10 sks of Portland Cement @ 94 lbs/sk = 940 lbs
2% CaCl₂/sk=.934 lbs/sk @ 10 sks=9.34 lbs
5.6 gallons/sack of water @ 10 sks=56 gal.(1.33 bbls)

Note: NaCl and CaCl₂ are measured in weight percent of water the other additives are measured in weight percent of the dry cement.

A word of caution is in order at this point. As the cement grout slurry enters the annulus the curve casing will start to float. The force required to keep the casing from floating out the hole is the buoyancy Δ TVD of the cement grout slurry.

$$\begin{aligned}\text{Floating force} &= \Delta\text{TVD grout} \cdot (d_1 - d_2) \cdot \text{area} \cdot .052 \\ &= 170' \cdot (13 - 8.4) \cdot 10.75^2 \cdot \pi / 4 \cdot .052 \\ &= 3700 \text{ lbs}\end{aligned}$$

Here Δ TVD grout is the vertical height of the cement grout column, d_1 is the density of the grout (ppg), d_2 is the density of displacing fluid (ppg), and area is the cross sectional area of the curve casing.

4.3.5. Monitor the grout density with a mud balance. Collect wet samples of the grout during the cement job. The wet samples will

be allowed to set on surface and will give an indication that the cement is thickening.

4.3.6. Break off the cementing hose and flush the cementing lines up to the drill pipe pin. Drop the drill pipe plug and displace the cement grout out of the drill string with 40 gallons of water. (pump the capacity of the drill string). Bump the plug with 200 psi.

Open the valves on the conductor and flush any cement from the bell nipple and spacer spools. Clean up any cement circulated to the surface.

Have 20# of sugar on hand to disperse cement if needed.

4.3.7. Hold the cementing plug in place and monitor the drill pipe ID and the drill pipe/casing annulus for leakage. Monitor the surface samples to help estimate the thickening time. As the cement starts to harden rotate the plug 1 to 2 revolutions every 30 minutes to weaken the cement bond on the casing plug. Once the cement has hardened pull the pipe and plug free. The plug will take ≈ 8000 lbs to shear it from the running tool. If the plug will not readily pull free try to break the bond with right hand rotation and pushing and pulling on the drill pipe. If this fails to release the plug, try to backout the center of the plug with left hand rotation. Caution: Do not exceed 3000 ft-lbs of torque (≈ 1000 psi rig pressure) when turning to the left to avoid backing off in the drill pipe.

If left hand rotation fails to release the plug center, pull out of the shear pins in the running tool. The plug will have to be removed with a rotary shoe on a 4 3/4" motor.

4.3.8. Pull out of the hole with the drill string and cementing plug.

4.3.9. Run 3/4" nom. OD steel tubing into the annulus to the cement top or as far as possible.

4.3.10. Establish circulation through the tremie tube.

4.3.11. Mix and pump the cement grout mixed the same as the lead

slurry for the curve grout.

4.3.12. Pull the tremie pipe to -10' elevation to grout the upper annulus with cement grout. Grout the upper section of the well. Pull the tremie tube from the well and lay it down.

4.3.13. Clean the cement lines and mixing equipment, disassemble the cementing lines and rig down the cement equipment. Clean up any cement that is circulated to surface

4.3.14. WOC and continue to hold the curve casing in place at the surface until the cement develops enough strength to support the casing. Observe the wet samples to determine if the cement grout is hardening.

4.3.15. While WOC, perform needed rig maintenance, clean and store the curve drilling tools, clean out the mud tank if needed. Steam clean all the horizontal drilling tools and well materials.

4.3.16. Tally and prepare tools and casing to drill the lateral section. Assemble the lower casing joints and casing shoe. Install the 6 5/8" OD casing collet in the casing drive and 6 5/8 jaws in mast clamp.

4.3.17. Pull the riser and cut off the excess casing after the cement grout has set enough to support the curve casing. Re-install the riser and flowline.

4.3.18. Pre-treat the drilling fluid with 1/4 ppb of soda ash to reduce the effects of cement contamination. Make up the 8 1/2" bit, xo sub, and 4 3/4" motor to drill out the 10" casing shoe (the motor will require the special oversize stabilizers). Run in the hole to the shoe and drill out 3'-4' of rat hole. Ream the rat hole and circulate the hole clean. Pull out of the hole to drill the horizontal section.

4.4 Deep Well Horizontal Drilling

Drilling the horizontal section is the next operation performed after the cementing plug is removed. The horizontal section will be casing drilled to install a 6" nom. HDPE screen into the well. The plan for drilling the horizontal section is outlined as follows:

4.4.1. Prepare to drill horizontal while WOC. Steam clean all the horizontal drilling tools and well materials. Tally and load drill pipe into the 6" casing. Mark casing on 1' intervals. Assemble the lower casing joints and casing shoe. Assemble and torque the 8 5/8" expanding bit, 4 3/4" motor with stabilizers for horizontal drilling, knuckle joint, tool face indicator, knuckle joint and orientation sub. Install the 6 5/8" OD casing collet in the casing drive and 6 5/8 jaws in mast clamp.

4.4.2. Pick up the lower casing joint and set it in the mast clamp. Pick up the horizontal motor assembly screw into it with the top drive and test the TFI, motor, and bit wings.

4.4.3. Trip in hole with dual string to end of the curve casing, monitor and record the pull down force while tripping in. The first joint of drill pipe will be non-mag and the slotted 6" HDPE will be used to line the hole. Install centralizers at each connection.

4.4.4. Trip to the 10" casing shoe start the mud pump, orient to desired direction. Do not tag bottom to avoid sticking the bit wings. Adjust the drilling variables such as WOB, flowrate, and motor pressure as needed to effectively drill. If the drilling rate is over 20 feet per hour be sure the hole is being cleaned by the drilling fluid.

4.4.5. Continue to drill the slotted screen into place. Drill with solid casing to place unslotted pipe from the surface to the end of the curve. Survey when needed. Record the drilling data on 1' to 5' intervals while drilling.

4.5. Deep well development

Development plan for deep horizontal well (-170' elevation) requires that the screen slots be cleaned and well pumped for 10 hours. This well is to be used for injection of air and methane to determine the effectiveness of air stripping and bio-remediation.

The plan to develop the deep well is as follows:

4.5.1. Casing drill 300' of 6" HDPE slotted screen in the horizontal section.

4.5.2. Circulate the hole clean, take any needed surveys, and pull out of the hole with the inner drilling assembly.

4.5.3. Dump the drilling fluid, clean the steel pits, and fill them with clean water.

4.5.4. Make up the 6" casing plug, plug running tool, and wash sub. Trip the plug to the 6" shoe on drill pipe. Monitor the hole drag. Wash the last 20' to flush out the shoe joint.

4.5.5. Set the plug in the 6" casing shoe with up to 2000 lbs. Pump down the plug sealing dart to seal the center of the 6" casing plug. Release the 6" casing plug from the running tool by pulling up on the drill pipe.

4.5.6. Pull the wash sub into the slotted screen section, drop the ball to seal the plug running tool.

4.5.7. Pull out of the hole and wash the 6" slotted screen at 300 GPM with clear water. Keep the pipe moving while washing the screen to avoid damaging the plastic casing.

4.5.8. Continue to wash the well screen until the returns are clean.

4.5.10. Finish tripping out of the hole with the drill pipe.

4.5.11. RIH to jet or pump on well for 10 hours (to jet the well with air will require a compressor that has a filtered discharge).

4.5.12. Pull the drill pipe.

4.5.13. Run tremie tube into the 10" X 6" casing annulus to the KOP or point of refusal to make a cement grout seal. Mix and pump portland cement with 2% bentonite to the surface.

4.5.14. Cut off the 6" casing leaving 24 " above ground level. Install a 6" 8-round adaptor on the 6" casing stub and cap..

4.5.15. Construct wooden form to place a 6" x 5' x 5' concrete pad around the well head. Mix sack crete and pour into form around well. Install 4" posts in each corner and fill posts with concrete.

5. Material and Tool List

This is a list of the materials and tools needed for horizontal drilling project at the Savannah River Site.

5.1. Casing Materials

- 12" nom Steel Conductors, 12 3/4" OD, .188" wall
- 10" casing, three wells, 740' (37 jts)
- 10" bowspring casing shoe
- 10" casing stabilizer
- 6" casing, three wells, 740' (37 jts)
- 6" screen, three wells, 900' (45 jts)
- 6" bowspring casing shoe
- 6" bowspring casing stabilizer
- 10 3/4" standoff bands
- 6 5/8" centralizers
- 10" O rings
- 6" O rings
- 10" cement plugs
- 6" casing plugs
- drill pipe darts
- 6" Cruway 8 round thread adaptor for HDPE pipe
- 6" 8 round cap to seal well

5.2. Drilling fluid additives

- bentonite
- PHPA
- LCM
- soda ash
- caustic

5.3. Grouting and development materials

- Portland Cement
- NaCl
- sodium metasilicate
- gypsum
- CaCl₂
- drill pipe dart

HDPE pellets
Bentonite pellets

- 5.4. Location materials
 - 4 mil plastic sheeting
 - 6'-4" steel posts
 - sak-crete for well pad
 - 6" high concrete form for well pad
 - rope and posts for isolating rig
- 5.5. Misc. Supplies
 - drill pipe dope
 - rig filters (fuel, oil, hydraulic)
 - hydraulic oil
 - motor oil
 - 1" tubing
 - 3/4" tubing
 - shaker screens
 - rig soap
 - markers for HDPE
 - paint sticks/chalk markers
 - sugar
 - WD-40
 - electra clean
 - rags
 - oil soaks
 - absorbent material
 - sample sacks
 - teflon tape and pipe thread compound
 - soft rope
 - electrical tape
 - duct tape
 - Johnson Screens with XO's and end caps
- 5.6. Rig Equipment
 - rig trailer, casing collects, casing clamps, stairs, ladders
 - hydraulic hoses
 - pipe trailer, electric power cords, stairs
 - fluid trailer, mud hose, cementing hose, stairs

steam cleaner
bell nipple and spacer spools
studs and nuts for the flanges
flow line, dresser sleeves, and dresser sleeve gaskets
gasket material for 12" flanges
2" valve, hose, and plug for the conductor outlets
slings, chains, boomers, snatch blocks, and shackles
drill collar clamp with wrench

5.7. Auger Tools

14" auger
12" auger
auger drive adapter
auger drive extension
extra auger blades

5.8. Drilling tools

drill pipe
non-mag drill pipe
mud motors, 2-6 3/4", 2-4 3/4"
motor stabilizers for drilling the curve, horizontal, cement
8 5/8 & 12 1/4 expanding bits, extra wings, O rings, pistons
4" Varel roller bit with shortened 2 3/8 reg. pin
8 1/2" mill tooth bit
3-5' drill pipe subs
2-10" drill pipe sub
42" sub, 2 7/8 1" box by pin
24" XO sub, 3 1/2 reg pin by 4 1/2 reg box
circulation subs with sleeves and shear pins
knuckle joints
plug running tool
shear pins
drill pipe pin for cementing through the drill pipe

5.9 Tools

tool box with hand tools
electric chain saw
sledge hammers, 16 lb and 4 lb
electric drill
electric grinder

shovels, spade and square
grout hoes
wheel barrow
2-50' 2" water hoses
garden hose
2-50' electric cords
pop rivet tool
wire brushes
chain tongs
2-60" pipe wrenches
Clamps and lift subs for motors
load cell
mud balance
vis funnel and cup
kitchen scale
derrick tape
tape measures
level
mercury angle indicator
scrub brushes and buckets

- 5.10 Survey equipment
 high angle single shot kit
 multi-shot kit and reader
 aluminum survey pipe
 non mag XO
 TFI, computer, printer, pressure transducer, surface units
 MacIntosh computer, printer

- 5.11. Safety Equipment
 coveralls
 steel toed boots
 face shields and goggles
 hard hat
 safety glasses with side shields
 respirators
 first aid kit
 ear plugs
 gloves

fire extinguishers
derrick belt
hard hats
safety signs

EASTMAN CHRISTENSEN
Environmental
AMH-1
Savannah River
Savannah River

CLEARANCE REPORT

Your ref :
Our ref : svy27
Other ref :

Date printed : 21-Jan-91
Date created : 11-Jan-91
Last revised : 16-Jan-91

Field is centred on n33 0 0.000,w80 0 0.000,-81
Structure is centred on n33 0 0.000,w80 0 0.000,-81

Main calculation performed with 3-D minimum distance method

Object wellpath	Closest approach			
	Last revised	Distance	M.D.	Diverging from
Deep,,Horizontal,Environmental	16-Jan-91	67.6	120.0	175.0
shallow,,Horizontal,Environmental	21-Jan-91	78.1	0.0	112.0

Reference wellpath

Object wellpath : Deep,,Horizontal,Environmental

H.D.	T.V.D.	Rect Coordinates		H.D.	T.V.D.	Rect Coordinates		Angle fm HighSide	Min'm Dist	ICyl Dist
0.0	0.0	0.0W	0.0E	0.0	0.0	60.0W	50.0E	+39.8	78.1	78.1
112.0	112.0	0.0W	0.0E	132.5	125.0	31.6W	57.9E	+62.0	67.2	69.0
114.0	114.0	0.0W	0.0E	135.4	127.1	29.6W	58.5E	+53.2	66.8	68.8
116.0	116.0	0.0W	0.0E	136.8	128.0	28.7W	58.7E	+53.8	66.4	68.1
118.0	118.0	0.1W	0.0E	138.2	129.0	27.8W	59.0E	+54.6	66.1	67.7
120.0	120.0	0.1W	0.0E	139.5	130.0	26.8W	59.3E	+55.8	65.7	67.6
122.0	122.0	0.3W	0.1E	140.8	130.8	25.9W	59.5E	+57.2	65.3	67.8
124.0	124.0	0.6W	0.1E	142.0	131.6	25.0W	59.8E	+58.9	64.9	68.3
126.0	125.9	1.0W	0.2E	143.8	132.8	23.7W	60.1E	+61.1	64.5	68.9
128.0	127.8	1.5W	0.3E	144.7	133.4	23.1W	60.3E	+62.7	64.0	69.9
130.0	129.7	2.2W	0.4E	145.4	133.9	22.6W	60.4E	+64.1	63.5	70.7
132.0	131.6	3.0W	0.6E	146.0	134.3	22.1W	60.6E	+65.7	63.0	72.6
134.0	133.3	3.9W	0.7E	146.5	134.6	21.7W	60.7E	+67.8	62.6	74.1
136.0	135.0	4.9W	0.9E	146.9	134.8	21.5W	60.8E	+70.9	62.1	76.7
138.0	136.6	6.1W	1.1E	147.1	134.9	21.4W	60.8E	+72.6	61.6	79.4
140.0	138.1	7.4W	1.2E	147.1	135.0	21.3W	60.8E	+74.2	61.2	83.0
142.0	139.5	8.9W	1.4E	147.0	134.9	21.4W	60.8E	+74.7	60.9	87.8
144.0	140.8	10.4W	1.5E	146.7	134.7	21.6W	60.7E	+75.1	60.6	93.7
146.0	142.0	12.0W	1.7E	146.4	134.5	21.8W	60.6E	+75.0	60.2	94.0
148.0	143.2	13.6W	1.9E	146.0	134.3	22.2W	60.6E	+74.4	60.0	99.9
150.0	144.3	15.2W	2.1E	145.5	133.9	22.5W	60.5E	+73.7	59.7	106.4
152.0	145.3	17.0W	2.4E	144.9	133.6	22.9W	60.3E	+73.0	59.5	112.0
154.0	146.2	18.7W	2.6E	144.3	133.2	23.4W	60.2E	+72.0	59.2	114.7
156.0	147.1	20.5W	3.0E	143.6	132.7	23.9W	60.1E	+71.6	59.0	116.3
158.0	147.9	22.3W	3.2E	142.9	132.2	24.4W	59.9E	+71.4	58.8	117.8
160.0	148.7	24.1W	3.5E	142.1	131.7	25.0W	59.8E	+70.8	58.7	123.4
163.0	149.6	26.9W	4.0E	143.6	132.7	23.9W	60.1E	+72.2	58.7	150.2
165.0	150.1	28.8W	4.3E	141.7	131.4	25.3W	59.7E	+70.5	58.6	-
167.0	150.4	30.8W	4.6E	140.6	130.7	26.0W	59.5E	+69.9	58.4	-
169.0	150.6	32.7W	5.0E	139.5	129.9	26.8W	59.2E	+69.1	58.3	-
171.0	150.6	34.7W	5.4E	138.2	129.1	27.7W	59.0E	+68.2	58.2	-
173.0	150.6	36.6W	5.7E	136.9	128.2	28.6W	58.8E	+67.3	58.2	-
175.0	150.6	38.6W	6.1E	135.6	127.2	29.5W	58.5E	+66.3	58.1	-
177.0	150.6	40.6W	6.4E	134.4	126.3	30.3W	58.3E	+65.3	58.2	-
179.0	150.7	42.6W	6.8E	133.1	125.4	31.2W	58.0E	+64.4	58.3	-
181.0	150.7	44.5W	7.1E	136.0	127.5	29.2W	58.6E	+66.9	58.5	-
191.0	151.0	54.4W	8.8E	128.9	122.3	33.9W	57.3E	+61.8	60.0	-
201.0	151.4	64.2W	10.5E	129.0	122.4	33.8W	57.3E	+63.4	62.9	-
211.0	151.8	74.1W	12.2E	122.0	117.0	38.1W	56.1E	+59.9	66.6	-
221.0	152.1	83.8W	14.6E	117.0	112.9	41.0W	55.3E	+56.4	70.9	-
231.0	151.7	93.4W	17.4E	117.0	112.9	40.9W	55.3E	+56.1	75.4	-
241.0	151.4	102.9W	20.3E	112.2	109.0	43.5W	54.6E	+59.6	80.7	-
251.0	151.8	112.4W	23.4E	108.1	105.4	45.6W	54.0E	+59.6	86.9	-
261.0	152.5	121.9W	26.5E	107.8	105.1	45.7W	54.0E	+64.1	93.8	-
271.0	153.6	131.4W	29.6E	108.3	105.6	45.4W	54.1E	+67.4	101.4	-
281.0	154.8	140.8W	32.6E	105.5	103.2	46.8W	53.7E	+68.3	109.3	-
291.0	156.1	150.2W	35.8E	102.7	100.8	48.0W	53.3E	+68.1	117.5	-
301.0	157.4	159.5W	39.1E	100.0	98.3	49.2W	53.0E	+69.0	125.9	-
311.0	158.7	168.8W	42.5E	112.7	109.4	43.2W	54.7E	+76.0	135.5	-
321.0	160.2	178.1W	46.0E	100.3	98.5	49.1W	53.0E	+71.9	143.1	-
331.0	161.6	187.5W	49.2E	97.9	96.4	50.1W	52.8E	+72.2	152.0	-
341.0	163.2	196.8W	52.3E	95.8	94.5	50.9W	52.5E	+75.3	161.3	-
351.0	165.1	206.2W	55.3E	100.2	98.4	49.2W	53.0E	+77.5	170.6	-
361.0	167.0	215.5W	58.3E	98.6	97.0	49.8W	52.8E	+77.7	179.9	-

All data is in feet unless otherwise stated
Coordinates are from AMH-1 and TVDs are from wellhead.
Vertical section is from wellhead on azimuth 14.14 degrees.
Calculation uses the minimum curvature method.

EASTMAN CHRISTENSEN
Environmental, Horizontal
Savannah River, Savannah River

CLEARANCE LISTING Page 2
Your ref :
Last revised : 16-Jan-91

Reference wellpath

Object wellpath : Deep,,Horizontal,Environmental

M.D.	T.V.D.	Rect Coordinates		M.D.	T.V.D.	Rect Coordinates		Angle fm HighSide	Min'm Dist	TCyl Dist
371.0	168.7	224.8W	61.6E	96.9	95.5	50.5W	52.6E	+75.3	189.2	-
381.0	170.2	234.0W	65.2E	95.0	93.8	51.2W	52.4E	+75.5	198.5	-
394.0	171.9	245.9W	70.1E	92.5	91.5	52.2W	52.2E	+74.2	210.6	-
404.0	173.1	254.8W	74.5E	114.4	110.8	42.4W	54.9E	+79.3	222.3	-
414.0	174.1	263.6W	79.2E	96.7	95.3	50.6W	52.6E	+75.0	228.6	-
424.0	174.9	272.3W	84.1E	94.9	93.6	51.3W	52.4E	+74.2	237.6	-
434.0	175.6	280.9W	89.2E	92.9	91.8	52.0W	52.2E	+72.9	246.5	-
444.0	176.0	289.5W	94.2E	90.8	89.8	52.8W	52.0E	+72.2	255.4	-
454.0	176.3	298.1W	99.3E	88.4	87.6	53.6W	51.8E	+71.1	264.4	-
464.0	176.3	306.6W	104.6E	86.0	85.3	54.4W	51.6E	+70.5	273.3	-
474.0	176.3	314.9W	110.1E	83.6	83.0	55.1W	51.4E	+70.7	282.2	-
484.0	176.2	322.9W	116.2E	90.9	90.0	52.8W	52.0E	+70.9	290.7	-

All data is in feet unless otherwise stated
Coordinates are from AMH-1 and TVDs are from wellhead.
Vertical section is from wellhead on azimuth 14.14 degrees.
Calculation uses the minimum curvature method.

Reference wellpath Object wellpath : shallow,,Horizontal,Environmental

M.D.	T.V.D.	Rect Coordinates		M.D.	T.V.D.	Rect Coordinates		Angle fm HighSide	Min'm Dist	TCyl Dist
0.0	0.0	0.0N	0.0E	22.2	19.2	49.3N	53.0E	+48.8	74.9	78.1
112.0	112.0	0.0N	0.0E	104.2	80.5	1.4S	67.1E	+91.1	74.2	-
114.0	114.0	0.0N	0.0E	103.8	80.3	1.0S	67.0E	+80.5	75.0	-
116.0	116.0	0.0N	0.0E	107.6	82.1	4.2S	67.9E	+83.2	76.0	-
118.0	118.0	0.1N	0.0E	105.8	81.2	2.7S	67.5E	+81.9	76.9	-
120.0	120.0	0.1N	0.0E	105.1	80.9	2.1S	67.3E	+80.6	77.9	-
122.0	122.0	0.3N	0.1E	105.8	81.3	2.8S	67.5E	+79.7	78.8	-
124.0	124.0	0.6N	0.1E	106.5	81.6	3.3S	67.7E	+78.2	79.8	-
126.0	125.9	1.0N	0.2E	107.1	81.9	3.8S	67.8E	+76.8	80.8	-
128.0	127.8	1.5N	0.3E	107.6	82.1	4.2S	67.9E	+75.1	81.8	-
130.0	129.7	2.2N	0.4E	107.9	82.2	4.5S	68.0E	+73.6	82.9	-
132.0	131.6	3.0N	0.6E	108.1	82.3	4.7S	68.0E	+71.6	83.9	-
134.0	133.3	3.9N	0.7E	108.2	82.4	4.7S	68.1E	+70.5	84.9	-
136.0	135.0	4.9N	0.9E	108.1	82.3	4.6S	68.0E	+69.5	85.9	-
138.0	136.6	6.1N	1.1E	107.8	82.2	4.4S	68.0E	+68.0	86.9	-
140.0	138.1	7.4N	1.2E	107.4	82.0	4.1S	67.9E	+66.3	87.9	-
142.0	139.5	8.9N	1.4E	106.9	81.8	3.6S	67.8E	+64.1	88.9	-
144.0	140.8	10.4N	1.5E	106.2	81.5	3.1S	67.6E	+61.8	89.8	-
146.0	142.0	12.0N	1.7E	105.5	81.1	2.4S	67.4E	+60.9	90.8	-
148.0	143.2	13.6N	1.9E	104.7	80.7	1.8S	67.2E	+58.6	91.7	-
150.0	144.3	15.2N	2.1E	111.4	83.8	7.5S	68.8E	+61.0	92.9	-
152.0	145.3	17.0N	2.4E	105.6	81.1	2.5S	67.4E	+56.2	93.4	-
154.0	146.2	18.7N	2.6E	109.8	83.1	6.2S	68.5E	+57.9	94.5	-
156.0	147.1	20.5N	3.0E	103.6	80.2	0.9S	67.0E	+53.8	95.0	-
158.0	147.9	22.3N	3.2E	108.0	82.3	4.6S	68.0E	+56.2	96.0	-
160.0	148.7	24.1N	3.5E	104.5	80.6	1.6S	67.2E	+53.4	96.7	-
163.0	149.6	26.9N	4.0E	102.8	79.8	0.2S	66.8E	+50.3	97.8	-
165.0	150.1	28.8N	4.3E	101.5	79.1	0.8N	66.5E	+47.7	98.4	-
167.0	150.4	30.8N	4.6E	100.2	78.4	2.0N	66.2E	+45.4	99.0	-
169.0	150.6	32.7N	5.0E	98.7	77.6	3.1N	65.9E	+43.6	99.5	-
171.0	150.6	34.7N	5.4E	97.2	76.8	4.3N	65.5E	+42.4	99.9	-
173.0	150.6	36.6N	5.7E	104.6	80.6	1.7S	67.2E	+46.0	100.7	-
175.0	150.6	38.6N	6.1E	97.4	76.9	4.2N	65.6E	+43.0	100.8	-
177.0	150.6	40.6N	6.4E	101.7	79.2	0.7N	66.6E	+45.5	101.5	-
179.0	150.7	42.6N	6.8E	94.4	75.2	6.6N	64.9E	+42.6	101.8	-
181.0	150.7	44.5N	7.1E	96.3	76.3	5.1N	65.3E	+44.0	102.4	-
191.0	151.0	54.4N	8.8E	89.2	72.1	10.7N	63.8E	+42.7	105.6	-
201.0	151.4	64.2N	10.5E	92.0	73.8	8.5N	64.4E	+46.4	109.7	-
211.0	151.8	74.1N	12.2E	82.5	67.9	15.6N	62.4E	+44.5	113.9	-
221.0	152.1	83.8N	14.6E	79.7	66.0	17.6N	61.8E	+43.4	118.4	-
231.0	151.7	93.4N	17.4E	76.9	64.1	19.6N	61.3E	+41.1	122.6	-
241.0	151.4	102.9N	20.3E	74.7	62.6	21.1N	60.8E	+47.2	127.4	-
251.0	151.8	112.4N	23.4E	73.4	61.6	22.0N	60.6E	+49.2	133.0	-
261.0	152.5	121.9N	26.5E	68.2	57.9	25.4N	59.7E	+51.6	139.2	-
271.0	153.6	131.4N	29.6E	68.1	57.7	25.5N	59.6E	+54.6	145.9	-
281.0	154.8	140.8N	32.6E	73.4	61.7	22.0N	60.6E	+59.2	153.5	-
291.0	156.1	150.2N	35.8E	64.3	54.8	27.8N	59.0E	+57.0	160.5	-
301.0	157.4	159.5N	39.1E	60.1	51.6	30.3N	58.3E	+57.9	168.1	-
311.0	158.7	168.8N	42.5E	72.7	61.1	22.5N	60.5E	+63.8	176.8	-
321.0	160.2	178.1N	46.0E	58.0	49.9	31.5N	57.9E	+60.5	183.8	-
331.0	161.6	187.5N	49.2E	60.3	51.7	30.2N	58.3E	+62.6	192.0	-
341.0	163.2	196.8N	52.3E	56.8	49.0	32.2N	57.8E	+65.7	200.5	-
351.0	165.1	206.2N	55.3E	53.6	46.3	34.0N	57.3E	+65.9	209.2	-
361.0	167.0	215.5N	58.3E	64.5	55.0	27.7N	59.0E	+69.7	218.7	-

All data is in feet unless otherwise stated
Coordinates are from AMH-1 and TVDs are from wellhead.
Vertical section is from wellhead on azimuth 14.14 degrees.
Calculation uses the minimum curvature method.

Reference wellpath

Object wellpath : shallow,,Horizontal,Environmental

M.D.	T.V.D.	Rect Coordinates		M.D.	T.V.D.	Rect Coordinates		Angle fm HighSide	Min'm Dist	TCyl Dist
371.0	168.7	224.8N	61.6E	61.7	52.9	29.4N	58.5E	+67.4	227.2	-
381.0	170.2	234.0N	65.2E	51.0	44.1	35.3N	56.9E	+65.7	235.4	-
394.0	171.9	245.9N	70.1E	46.9	40.6	37.4N	56.3E	+64.4	246.8	-
404.0	173.1	254.8N	74.5E	51.5	44.5	35.1N	57.0E	+65.3	255.2	-
414.0	174.1	263.6N	79.2E	48.6	42.1	36.6N	56.5E	+65.0	263.6	-
424.0	174.9	272.3N	84.1E	52.8	45.6	34.4N	57.1E	+65.8	272.1	-
434.0	175.6	280.9N	89.2E	49.9	43.2	35.9N	56.7E	+64.6	280.3	-
444.0	176.0	289.5N	94.2E	46.7	40.5	37.5N	56.3E	+63.8	288.6	-
454.0	176.3	298.1N	99.3E	44.6	38.6	38.5N	56.0E	+63.1	297.0	-
464.0	176.3	306.6N	104.6E	41.3	35.8	40.1N	55.6E	+62.6	305.3	-
474.0	176.3	314.9N	110.1E	38.0	33.0	41.7N	55.1E	+62.8	313.4	-
484.0	176.2	322.9N	116.2E	34.9	30.2	43.2N	54.7E	+61.2	321.4	-

All data is in feet unless otherwise stated
Coordinates are from AMH-1 and TVDs are from wellhead.
Vertical section is from wellhead on azimuth 14.14 degrees.
Calculation uses the minimum curvature method.

Du Pont
Poupin
AMH-1
Savannah River

SURVEY LISTING

Your ref :
Our ref : svy36
Other ref :

Date printed : 11-Jan-91
Date created : 11-Jan-91
Last revised : 11-Jan-91

Field is centred on 0.000,0.000,0.00000,+
Structure is centred on 0.000,0.000,0.00000,+

Du Pont
Poupi's, AMH-1
Savannah River,

SURVEY LISTING Page 1
Your ref :
Last revised : 11-Jan-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S		Dogleg Deg/100ft	Vert Sect
0.00	0.00	0.00	0.00	0.00 M	0.00 E	0.00	0.00
112.00	0.00	0.00	112.00	0.00 M	0.00 E	0.00	0.00
114.00	1.00	11.00	114.00	0.02 M	0.00 E	50.00	0.02
116.00	0.50	11.00	116.00	0.04 M	0.01 E	25.00	0.04
118.00	1.00	11.00	118.00	0.07 M	0.01 E	25.00	0.07
120.00	3.00	11.00	120.00	0.14 M	0.03 E	100.00	0.14
122.00	6.00	11.00	121.99	0.29 M	0.06 E	150.00	0.30
124.00	10.00	11.00	123.97	0.56 M	0.11 E	200.00	0.57
126.00	13.75	11.00	125.93	0.97 M	0.19 E	187.50	0.98
128.00	18.00	11.00	127.85	1.50 M	0.29 E	212.50	1.53
130.00	21.50	11.00	129.73	2.17 M	0.42 E	175.00	2.20
132.00	26.00	11.00	131.56	2.96 M	0.58 E	225.00	3.01
134.00	30.00	10.00	133.33	3.88 M	0.74 E	201.37	3.95
136.00	35.00	8.00	135.02	4.94 M	0.91 E	255.68	5.02
138.00	39.25	7.00	136.61	6.14 M	1.07 E	214.63	6.21
140.00	43.50	6.00	138.11	7.45 M	1.22 E	215.05	7.52
142.00	47.50	6.00	139.51	8.87 M	1.37 E	200.00	8.94
144.00	51.50	6.00	140.81	10.38 M	1.53 E	200.00	10.44
146.00	53.00	6.00	142.04	11.96 M	1.69 E	75.00	12.01
148.00	56.00	7.00	143.20	13.57 M	1.88 E	155.42	13.62
150.00	59.00	8.00	144.27	15.24 M	2.10 E	155.81	15.30
152.00	61.50	9.00	145.26	16.96 M	2.35 E	132.32	17.02
154.00	63.00	10.00	146.19	18.71 M	2.64 E	87.08	18.79
156.00	64.50	10.00	147.08	20.47 M	2.96 E	75.00	20.58
158.00	66.25	9.00	147.91	22.27 M	3.26 E	98.60	22.39
160.00	68.50	9.00	148.68	24.09 M	3.55 E	112.50	24.23
163.00	74.00	9.00	149.65	26.90 M	3.99 E	183.33	27.06
165.00	78.50	10.00	150.12	28.81 M	4.31 E	230.18	28.99
167.00	83.50	10.00	150.43	30.76 M	4.65 E	250.00	30.96
169.00	87.50	11.00	150.59	32.72 M	5.02 E	206.12	32.95
171.00	90.00	10.00	150.63	34.68 M	5.38 E	134.62	34.94
173.00	90.00	10.00	150.63	36.65 M	5.73 E	0.00	36.94
175.00	90.00	10.00	150.63	38.62 M	6.08 E	0.00	38.94
177.00	89.50	10.00	150.64	40.59 M	6.42 E	25.00	40.93
179.00	89.00	10.00	150.67	42.56 M	6.77 E	25.00	42.92
181.00	88.50	9.00	150.71	44.53 M	7.10 E	55.89	44.92
191.00	88.00	10.00	151.02	54.39 M	8.75 E	11.18	54.88
201.00	87.75	10.00	151.39	64.23 M	10.48 E	2.50	64.85
211.00	87.00	10.00	151.85	74.07 M	12.22 E	7.50	74.81
221.00	90.00	17.00	152.11	83.78 M	14.55 E	76.13	84.80
231.00	95.00	16.00	151.67	93.36 M	17.39 E	50.99	94.78
241.00	88.00	18.00	151.41	102.91 M	20.31 E	72.80	104.75
251.00	87.50	18.00	151.80	112.41 M	23.40 E	5.00	114.72
261.00	84.50	18.00	152.50	121.90 M	26.48 E	30.00	124.68
271.00	83.25	18.00	153.57	131.36 M	29.55 E	12.50	134.60
281.00	82.50	18.00	154.81	140.79 M	32.62 E	7.50	144.50
291.00	83.00	19.00	156.07	150.20 M	35.77 E	11.11	154.39
301.00	82.25	20.00	157.35	159.55 M	39.08 E	12.43	164.26
311.00	81.75	21.00	158.75	168.82 M	42.54 E	11.09	174.10
321.00	82.00	20.00	160.16	178.10 M	46.01 E	10.21	183.94
331.00	82.00	18.00	161.55	187.46 M	49.24 E	19.80	193.81
341.00	79.00	18.00	163.20	196.84 M	52.28 E	30.00	203.65
351.00	79.00	18.00	165.11	206.18 M	55.32 E	0.00	213.44

All data is in feet unless otherwise stated
Coordinates are from AMH-1 and TVDs are from wellhead.
Vertical section is from wellhead on azimuth 14.14 degrees.
Calculation uses the minimum curvature method.

Du Pont
Poups, AMH-1
Savannah River,

SURVEY LISTING Page 2
Your ref :
Last revised : 11-Jan-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S		Dogleg Deg/100ft	Vert Sect
361.00	79.00	18.00	167.02	215.51 M	58.35 E	0.00	223.24
371.00	81.50	21.00	168.71	224.80 M	61.64 E	38.72	233.05
381.00	81.50	21.00	170.19	234.03 M	65.18 E	0.00	242.87
394.00	83.00	24.00	171.94	245.93 M	70.11 E	25.61	255.61
404.00	84.00	28.00	173.08	254.86 M	74.47 E	40.98	265.33
414.00	84.50	29.00	174.08	263.60 M	79.22 E	11.14	274.97
424.00	85.50	30.00	174.95	272.27 M	84.12 E	14.12	284.58
434.00	87.00	31.00	175.60	280.87 M	89.18 E	18.02	294.15
444.00	88.00	30.00	176.04	289.48 M	94.26 E	14.14	303.74
454.00	89.25	31.00	176.28	298.09 M	99.33 E	16.00	313.33
464.00	90.00	32.00	176.34	306.62 M	104.55 E	12.50	322.87
474.00	90.00	36.00	176.34	314.91 M	110.14 E	40.00	332.28
484.00	92.00	38.00	176.17	322.89 M	116.16 E	28.28	341.49

All data is in feet unless otherwise stated
Coordinates are from AMH-1 and TVDs are from wellhead.
Vertical section is from wellhead on azimuth 14.14 degrees.
Calculation uses the minimum curvature method.

EASTMAN CHRISTENSEN
Environmental
Shallow
Savannah River
Savannah River

P R O P O S A L L I S T I N G

Your ref : shallow
Our ref : prop146
Other ref :

Date printed : 21-Jan-91
Date created : 11-Jan-91
Last revised : 21-Jan-91

Field is centred on n33 0 0.000,w80 0 0.000,-81
Structure is centred on n33 0 0.000,w80 0 0.000,-81

EASTMAN CHRISTENSEN
Environmental, Horizontal
Savannah River, Savannah River

PROPOSAL LISTING Page 1
Your ref : shallow
Last revised : 21-Jan-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S		Dogleg Deg/100Ft	Vert Sect
0.00	30.00	164.40	0.00	0.00 M	0.00 E	0.00	0.00
46.19	30.00	164.40	40.00	22.24 S	6.21 E	0.00	23.09
88.59	52.09	164.40	71.78	48.90 S	13.65 E	52.09	50.76
161.38	90.00	164.40	95.00	114.00 S	31.83 E	52.09	118.36
200.00	90.00	164.40	95.00	151.19 S	42.21 E	0.00	156.98
300.00	90.00	164.40	95.00	247.51 S	69.11 E	0.00	256.98
461.38	90.00	164.40	95.00	402.94 S	112.50 E	0.00	418.36

All data is in feet unless otherwise stated
Coordinates are from Shallow and TVDs are from wellhead.
Vertical section is from M 0.00 E 0.00 on azimuth 164.40 degrees.
Calculation uses the minimum curvature method.

EASTMAN CHRISTENSEN
Environmental
Deep
Savannah River
Savannah River

P R O P O S A L L I S T I N G

Your ref : Deep
Our ref : prop147
Other ref :

Date printed : 21-Jan-91
Date created : 11-Jan-91
Last revised : 16-Jan-91

Field is centred on n33 0 0.000,w80 0 0.000,-81
Structure is centred on n33 0 0.000,w80 0 0.000,-81

EASTMAN CHRISTENSEN
Environmental, Horizontal
Savannah River, Savannah River

PROPOSAL LISTING Page 1
Your ref : Deep
Last revised : 16-Jan-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S		Dogleg Deg/100ft	Vert Sect
0.00	0.00	0.00	0.00	0.00 W	0.00 E	0.00	0.00
50.00	0.00	0.00	50.00	0.00 W	0.00 E	0.00	0.00
100.00	26.04	164.40	98.30	10.76 S	3.00 E	52.09	11.17
200.00	78.13	164.40	157.65	84.16 S	23.50 E	52.09	87.37
222.79	90.00	164.40	160.00	105.95 S	29.58 E	52.09	110.00
500.00	90.00	164.40	160.00	372.95 S	104.13 E	0.00	387.21
522.79	90.00	164.40	160.00	394.90 S	110.26 E	0.00	410.00

All data is in feet unless otherwise stated
Coordinates are from Deep and TVDs are from wellhead.
Vertical section is from W 0.00 E 0.00 on azimuth 164.40 degrees.
Calculation uses the minimum curvature method.

APPENDIX B
INTEGRATED DEMONSTRATION SITE HYDROGEOLOGIC CROSS-SECTION

SOUTH

INTEGRATED D

ONSTRATION SITE HYDROGEOLOGIC CROSS-SECTION

NORTH

MHT-1C

MHT 2C

LEGEND:

■ CALCAREOUS SAND

▨ CLAYEY SAND

□ SAND

▨ GRAVELLY SAND

■ SILT/CLAY

■ SANDY CLAY

⊗ NO RECOVERY

▨ SCREENED INTERVAL

TD = TOTAL DEPTH

— = CONFINING ZONE, UNIT, AND SYSTEM BOUNDARIES

- - - = WATER TABLE (DASHED WHERE INFERRED)

DISTANCE ROUNDED TO THE NEAREST FOOT
SCALE

HORIZONTAL: 0 5 10 15 20

VERTICAL: 0 5 10 15 20

NEW 000417

UNITED STATES DEPARTMENT OF ENERGY			
SAVANNAH RIVER SITE			
NO.	DATE	REVISION	DATE
1	11-12-88	1	11-12-88
A/M AREA		T.S. MOULT	
INTEGRATED DEMONSTRATION SITE		11-12-88	
HYDROGEOLOGIC CROSS-SECTION		11-12-88	

APPENDIX C

SURVEY DATA

Westinghouse Savannah River Site

Structure : Horizontal Wells

Field : 300-M

Location : Aiken, South Carolina

Westinghouse Savannah River Site
Horizontal Wells
AHH-7 Deep
300-M
Aiken, South Carolina

S U R V E Y L I S T I N G

Your ref : June 9, 1991
Our ref : svy72
Other ref :

Date printed : 19-Jul-91
Date created : 19-Jul-91
Last revised : 19-Jul-91

Field is centred on n33 19 57.280,e81 44 16.39
Structure is centred on n33 19 57.280,e81 44 16.39

Westinghouse Savannah River Site
Horizontal Wells, AMH-7 Deep
300-M, Aiken, South Carolina

SURVEY LISTING Page 1
Your ref : June 9, 1991
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S	Dogleg Deg/100Ft	Vert Sect
0.00	0.00	0.00	0.00	0.00 N	0.00 E	0.00
35.00	1.00	155.50	35.00	0.28 S	0.13 E	2.86
38.00	1.00	155.50	38.00	0.32 S	0.15 E	0.00
41.00	1.00	155.50	41.00	0.37 S	0.17 E	0.00
44.00	2.75	156.50	44.00	0.46 S	0.21 E	58.34
47.00	4.00	157.50	46.99	0.62 S	0.28 E	41.71
50.00	6.00	154.50	49.98	0.86 S	0.38 E	67.21
53.00	8.00	155.50	52.96	1.20 S	0.54 E	66.79
56.00	10.75	158.50	55.92	1.64 S	0.73 E	93.07
59.00	13.00	160.50	58.85	2.22 S	0.94 E	76.23
62.00	15.00	160.50	61.76	2.91 S	1.19 E	66.67
65.00	16.75	162.50	64.65	3.69 S	1.45 E	61.11
68.00	18.75	161.50	67.50	4.56 S	1.73 E	67.43
71.00	20.50	160.50	70.33	5.51 S	2.06 E	59.40
74.00	22.50	158.50	73.12	6.54 S	2.44 E	70.99
77.00	24.00	158.50	75.88	7.64 S	2.88 E	50.00
80.00	26.00	159.50	78.60	8.82 S	3.33 E	68.14
83.00	27.75	159.50	81.27	10.09 S	3.81 E	58.33
86.00	29.25	158.50	83.91	11.43 S	4.32 E	52.47
89.00	31.00	158.50	86.50	12.83 S	4.87 E	58.33
92.00	32.25	159.50	89.06	14.30 S	5.43 E	45.18
95.00	34.00	160.50	91.57	15.84 S	6.00 E	61.11
98.00	35.25	162.50	94.04	17.46 S	6.54 E	56.31
101.00	36.50	165.50	96.47	19.15 S	7.02 E	71.89
104.00	38.00	166.50	98.86	20.91 S	7.46 E	53.92
107.00	39.00	168.50	101.21	22.73 S	7.86 E	53.23
110.00	40.00	164.50	103.52	24.58 S	8.31 E	91.11
113.00	41.00	168.50	105.80	26.48 S	8.76 E	92.77
116.00	42.50	166.50	108.04	28.43 S	9.19 E	66.86
119.00	44.00	164.50	110.23	30.42 S	9.71 E	67.72
122.00	45.25	164.50	112.36	32.45 S	10.27 E	41.67
125.00	46.25	162.50	114.45	34.51 S	10.88 E	58.23
128.00	47.75	166.50	116.50	36.62 S	11.47 E	109.57
131.00	49.00	161.50	118.49	38.78 S	12.09 E	131.34
134.00	50.25	160.50	120.44	40.94 S	12.83 E	48.79
137.00	51.75	160.50	122.32	43.14 S	13.61 E	50.00
140.00	53.00	160.50	124.16	45.38 S	14.40 E	41.67
143.00	54.25	160.50	125.94	47.65 S	15.21 E	41.67
146.00	56.00	160.50	127.65	49.97 S	16.03 E	58.33
149.00	57.25	160.00	129.30	52.33 S	16.88 E	43.93
152.00	58.75	160.50	130.89	54.72 S	17.74 E	51.96
155.00	60.00	159.50	132.42	57.15 S	18.62 E	50.58
158.00	62.00	158.50	133.87	59.60 S	19.56 E	72.76
161.00	62.50	158.50	135.27	62.07 S	20.53 E	16.67
164.00	63.50	156.50	136.63	64.54 S	21.56 E	68.11
167.00	64.75	155.50	137.94	67.00 S	22.65 E	51.34
170.00	66.00	153.50	139.19	69.47 S	23.83 E	73.54
173.00	67.00	157.50	140.39	71.97 S	24.97 E	126.73
176.00	68.00	158.50	141.54	74.54 S	26.01 E	45.38
179.00	68.50	159.50	142.65	77.14 S	27.00 E	35.16
182.00	69.75	160.50	143.72	79.77 S	27.96 E	52.02
185.00	70.25	161.50	144.74	82.44 S	28.88 E	35.48
188.00	71.00	162.50	145.74	85.13 S	29.76 E	40.17

All data is in feet unless otherwise stated
Coordinates are from AMH-7 Deep and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH-7 Deep
300-M, Aiken, South Carolina

SURVEY LISTING Page 2
Your ref : June 9, 1991
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S		Dogleg Deg/100Ft	Vert Sect
191.00	72.25	163.50	146.68	87.85 S	30.59 E	52.31	91.83
194.00	74.00	162.50	147.56	90.60 S	31.43 E	66.48	94.68
197.00	75.00	161.50	148.36	93.35 S	32.32 E	46.29	97.54
200.00	76.00	160.50	149.11	96.09 S	33.27 E	46.40	100.41
203.00	77.00	158.50	149.81	98.83 S	34.29 E	72.89	103.28
206.00	77.50	157.50	150.47	101.54 S	35.38 E	36.53	106.14
209.00	78.25	156.50	151.10	104.24 S	36.53 E	41.07	109.00
212.00	79.50	155.50	151.68	106.93 S	37.73 E	52.97	111.86
215.00	81.75	155.50	152.17	109.62 S	38.96 E	75.00	114.72
218.00	83.00	155.50	152.57	112.33 S	40.19 E	41.67	117.60
221.00	85.00	155.50	152.88	115.04 S	41.42 E	66.67	120.49
224.00	87.00	155.50	153.09	117.76 S	42.67 E	66.67	123.38
226.00	88.00	155.50	153.18	119.58 S	43.50 E	50.00	125.32
228.00	88.50	155.50	153.24	121.40 S	44.32 E	25.00	127.25
230.00	88.50	155.50	153.29	123.22 S	45.15 E	0.00	129.19
232.00	88.25	156.50	153.35	125.05 S	45.97 E	51.52	131.13
234.00	88.00	157.50	153.41	126.89 S	46.75 E	51.51	133.08
236.00	88.75	157.50	153.47	128.74 S	47.51 E	37.50	135.03
238.00	89.00	157.50	153.51	130.58 S	48.28 E	12.50	136.98
240.00	89.25	157.50	153.54	132.43 S	49.04 E	12.50	138.93
242.00	90.00	157.50	153.55	134.28 S	49.81 E	37.50	140.89
244.00	91.00	158.50	153.53	136.13 S	50.56 E	70.71	142.84
246.00	91.50	158.50	153.49	137.99 S	51.29 E	25.00	144.80
248.00	92.00	158.50	153.43	139.85 S	52.02 E	25.00	146.76
250.00	92.00	158.50	153.36	141.71 S	52.76 E	0.00	148.72
252.00	92.00	157.50	153.29	143.56 S	53.50 E	49.97	150.68
254.00	92.00	158.50	153.22	145.42 S	54.25 E	49.97	152.63
256.00	92.00	157.50	153.15	147.27 S	55.00 E	49.97	154.58
258.00	92.00	157.50	153.08	149.12 S	55.77 E	0.00	156.54
260.00	91.75	156.50	153.02	150.96 S	56.55 E	51.51	158.48
262.00	90.00	155.50	152.98	152.78 S	57.36 E	100.77	160.42
264.00	88.75	155.50	153.01	154.60 S	58.19 E	62.50	162.36
266.00	88.00	154.50	153.06	156.42 S	59.04 E	62.48	164.29
268.00	87.00	154.50	153.15	158.22 S	59.90 E	50.00	166.22
270.00	86.00	154.50	153.27	160.02 S	60.76 E	50.00	168.14
272.00	85.25	155.50	153.42	161.83 S	61.60 E	62.38	170.07
274.00	85.00	155.50	153.60	163.64 S	62.42 E	12.50	172.00
276.00	84.50	157.50	153.78	165.47 S	63.22 E	102.67	173.93
278.00	84.75	157.50	153.96	167.31 S	63.98 E	12.50	175.88
280.00	85.00	158.50	154.14	169.16 S	64.73 E	51.34	177.82
282.00	85.00	158.50	154.32	171.01 S	65.46 E	0.00	179.78
284.00	85.00	159.50	154.49	172.87 S	66.17 E	49.81	181.73
286.00	85.50	159.50	154.66	174.74 S	66.87 E	25.00	183.69
288.00	86.25	157.50	154.80	176.59 S	67.60 E	106.56	185.65
293.00	87.00	153.50	155.10	181.13 S	69.67 E	81.26	190.48
298.00	88.75	157.50	155.28	185.68 S	71.74 E	87.27	195.32
303.00	90.75	157.50	155.30	190.30 S	73.65 E	40.00	200.20
308.00	92.25	156.50	155.17	194.90 S	75.61 E	36.05	205.07
313.00	92.50	155.50	154.97	199.46 S	77.64 E	20.60	209.91
318.00	92.25	154.50	154.76	203.99 S	79.75 E	20.60	214.74
323.00	93.00	152.50	154.53	208.46 S	81.98 E	42.68	219.53
328.00	93.25	149.50	154.26	212.82 S	84.40 E	60.12	224.25
338.00	92.75	153.50	153.73	221.60 S	89.16 E	40.26	233.72

All data is in feet unless otherwise stated
Coordinates are from AMH-7 Deep and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH-7 Deep
300-N, Aiken, South Carolina

SURVEY LISTING Page 3
Your ref : June 9, 1991
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S			Dogleg Deg/100Ft	Vert Sect
343.00	92.00	154.50	153.53	226.09 S	91.35 E	24.99	238.52	
348.00	91.75	155.50	153.36	230.62 S	93.46 E	20.60	243.34	
353.00	89.00	153.50	153.33	235.13 S	95.62 E	68.00	248.16	
358.00	89.00	152.50	153.42	239.58 S	97.89 E	20.00	252.94	
363.00	88.00	151.50	153.55	244.00 S	100.23 E	28.28	257.70	
368.00	87.50	149.50	153.74	248.35 S	102.69 E	41.20	262.41	
373.00	87.00	152.50	153.98	252.71 S	105.11 E	60.76	267.13	
378.00	87.00	153.50	154.25	257.16 S	107.38 E	19.97	271.90	
383.00	87.00	153.50	154.51	261.63 S	109.61 E	0.00	276.69	
388.00	87.00	153.50	154.77	266.10 S	111.84 E	0.00	281.48	
393.00	86.50	152.50	155.05	270.55 S	114.10 E	22.33	286.25	
398.00	86.50	150.50	155.36	274.93 S	116.48 E	39.92	290.98	
403.00	87.25	149.50	155.63	279.26 S	118.98 E	24.98	295.68	
408.00	88.75	148.50	155.80	283.54 S	121.55 E	36.05	300.34	
413.00	89.00	75.00	155.92	285.27 S	125.88 E	1469.68	302.79	
418.00	91.50	149.50	155.89	287.03 S	130.19 E	1490.70	305.28	
423.00	93.25	148.50	155.69	291.31 S	132.77 E	40.30	309.94	
428.00	95.00	147.50	155.33	295.54 S	135.41 E	40.28	314.56	
433.00	94.75	146.50	154.90	299.72 S	138.12 E	20.54	319.15	
438.00	94.75	145.50	154.49	303.85 S	140.91 E	19.93	323.70	
443.00	94.50	143.50	154.08	307.91 S	143.80 E	40.18	328.20	
448.00	93.00	143.50	153.76	311.92 S	146.77 E	30.00	332.66	
453.00	90.25	143.50	153.62	315.94 S	149.74 E	55.00	337.14	
458.00	88.25	144.50	153.68	319.98 S	152.68 E	44.72	341.63	
463.00	88.00	145.50	153.84	324.07 S	155.55 E	20.60	346.16	
468.00	88.00	145.50	154.02	328.19 S	158.38 E	0.00	350.71	
473.00	87.00	143.50	154.24	332.26 S	161.28 E	44.69	355.22	
478.00	87.50	143.50	154.48	336.27 S	164.25 E	10.00	359.68	
483.00	87.00	143.50	154.72	340.29 S	167.22 E	10.00	364.15	
488.00	87.00	143.50	154.98	344.30 S	170.19 E	0.00	368.62	AMH-7

All data is in feet unless otherwise stated
Coordinates are from AMH-7 Deep and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH-7 Deep
300-M, Aiken, South Carolina

SURVEY LISTING Page 4
Your ref : June 9, 1991
Last revised : 19-Jul-91

				Comments in wellpath
				=====
MD	TVD	Rectangular Coords.		Comment

488.00	154.98	344.30 S	170.19 E	AMH-7

All data is in feet unless otherwise stated
Coordinates are from AMH-7 Deep and TVDs are from wellhead.
Vertical section is from W 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells
AMH 6 Shallow #6
300-M
Aiken, South Carolina

S U R V E Y L I S T I N G

Your ref : 5-18-91
Our ref : svy71
Other ref :

Date printed : 19-Jul-91
Date created : 19-Jul-91
Last revised : 19-Jul-91

Field is centred on n33 19 57.280,e81 44 16.39
Structure is centred on n33 19 57.280,e81 44 16.39

Westinghouse Savannah River Site
Horizontal Wells, AMH 6 Shallow #6
300-M, Aiken, South Carolina

SURVEY LISTING Page 1
Your ref : 5-18-91
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S		Dogleg Deg/100Ft	Vert Sect
0.00	0.00	0.00	0.00	0.00 N	0.00 E	0.00	0.00
21.00	16.50	172.50	20.71	2.98 S	0.39 E	78.57	3.00
24.00	16.50	169.50	23.59	3.82 S	0.52 E	28.40	3.85
27.00	16.50	169.50	26.46	4.66 S	0.68 E	0.00	4.70
30.00	17.00	159.50	29.34	5.49 S	0.91 E	97.38	5.56
33.00	17.50	159.50	32.20	6.32 S	1.22 E	16.67	6.44
36.00	18.00	160.50	35.06	7.18 S	1.54 E	19.52	7.34
39.00	19.00	162.50	37.90	8.08 S	1.84 E	39.47	8.28
41.00	20.00	164.50	39.79	8.72 S	2.03 E	60.11	8.94
44.00	21.50	165.50	42.60	9.75 S	2.30 E	51.37	10.00
47.00	23.00	165.50	45.37	10.85 S	2.59 E	50.00	11.13
50.00	25.25	167.50	48.11	12.04 S	2.87 E	79.79	12.36
53.00	27.00	168.50	50.80	13.33 S	3.14 E	60.15	13.68
56.00	28.50	167.50	53.46	14.70 S	3.44 E	52.35	15.07
59.00	30.00	167.50	56.08	16.13 S	3.75 E	50.00	16.54
61.00	32.00	168.50	57.79	17.14 S	3.97 E	103.26	17.56
64.00	33.50	169.50	60.31	18.73 S	4.28 E	53.15	19.19
67.00	35.50	171.50	62.78	20.41 S	4.56 E	76.61	20.89
70.00	38.00	168.50	65.19	22.17 S	4.87 E	102.57	22.68
73.00	39.50	168.50	67.53	24.01 S	5.24 E	50.00	24.56
76.00	41.50	168.50	69.81	25.92 S	5.63 E	66.67	26.51
79.00	43.50	169.50	72.02	27.91 S	6.02 E	70.36	28.53
82.00	45.00	169.50	74.17	29.97 S	6.40 E	50.00	30.62
85.00	47.00	171.00	76.25	32.10 S	6.76 E	75.75	32.78
88.00	49.50	171.50	78.25	34.31 S	7.10 E	84.26	35.02
91.00	51.25	169.50	80.16	36.59 S	7.49 E	77.71	37.33
94.00	53.00	169.50	82.01	38.92 S	7.92 E	58.33	39.70
97.00	54.75	169.50	83.77	41.30 S	8.36 E	58.33	42.12
100.00	56.50	169.50	85.47	43.73 S	8.81 E	58.33	44.60
103.00	58.50	170.50	87.08	46.22 S	9.25 E	72.35	47.13
106.00	60.00	170.50	88.61	48.77 S	9.68 E	50.00	49.71
109.00	63.00	170.50	90.04	51.37 S	10.11 E	100.00	52.34
112.00	64.25	170.50	91.38	54.02 S	10.55 E	41.67	55.03
115.00	66.00	170.50	92.64	56.70 S	11.00 E	58.33	57.75
118.00	67.50	170.50	93.82	59.42 S	11.46 E	50.00	60.51
121.00	69.00	170.50	94.94	62.17 S	11.92 E	50.00	63.29
124.00	70.00	170.50	95.99	64.94 S	12.38 E	33.33	66.10
127.00	70.50	170.50	97.00	67.72 S	12.85 E	16.67	68.93
130.00	72.00	174.50	97.96	70.54 S	13.22 E	135.79	71.76
133.00	74.50	174.50	98.83	73.40 S	13.49 E	83.33	74.63
136.00	75.00	174.50	99.62	76.28 S	13.77 E	16.67	77.51
139.00	74.00	174.50	100.42	79.16 S	14.05 E	33.33	80.40
142.00	78.00	174.50	101.15	82.06 S	14.33 E	133.33	83.30
150.00	79.00	176.50	102.74	89.87 S	14.94 E	27.50	91.10
155.00	81.00	176.50	103.61	94.78 S	15.24 E	40.00	95.99
160.00	82.00	175.50	104.35	99.72 S	15.59 E	28.13	100.91
165.00	85.00	175.50	104.91	104.67 S	15.98 E	60.00	105.85
170.00	88.00	174.50	105.22	109.64 S	16.41 E	63.23	110.82
175.00	88.00	173.50	105.39	114.61 S	16.93 E	19.99	115.81
180.00	89.00	173.50	105.52	119.58 S	17.50 E	20.00	120.80
185.00	90.00	173.50	105.57	124.54 S	18.07 E	20.00	125.79
190.00	90.50	172.50	105.55	129.51 S	18.68 E	22.36	130.78
195.00	90.50	171.50	105.50	134.46 S	19.37 E	20.00	135.78

All data is in feet unless otherwise stated
Coordinates are from AMH 6 Shallow #6 and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH 6 Shallow #6
300-M, Aiken, South Carolina

SURVEY LISTING Page 2
Your ref : 5-18-91
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S			Dogleg Deg/100ft	Vert Sect
200.00	91.00	170.50	105.44	139.40 S	20.15 E	22.36	140.78	
205.00	91.00	169.50	105.35	144.32 S	21.02 E	20.00	145.78	
210.00	91.00	168.50	105.26	149.22 S	21.98 E	20.00	150.77	
215.00	92.00	166.50	105.13	154.10 S	23.06 E	44.71	155.77	
220.00	93.00	165.50	104.91	158.95 S	24.27 E	28.27	160.75	
225.00	93.50	162.50	104.63	163.75 S	25.64 E	60.73	165.72	
230.00	93.50	163.50	104.32	168.52 S	27.10 E	19.96	170.67	
235.00	93.50	164.50	104.02	173.32 S	28.48 E	19.96	175.63	
240.00	93.50	164.50	103.71	178.13 S	29.81 E	0.00	180.60	
245.00	93.00	166.50	103.43	182.96 S	31.06 E	41.17	185.58	
250.00	92.50	167.50	103.19	187.83 S	32.18 E	22.34	190.56	
255.00	92.00	169.50	103.00	192.72 S	33.18 E	41.20	195.56	
260.00	93.50	170.50	102.76	197.64 S	34.05 E	36.04	200.55	
265.00	64.50	171.50	103.70	202.44 S	34.81 E	580.32	205.41	
270.00	93.50	170.50	104.64	207.23 S	35.57 E	580.32	210.26	
275.00	93.50	170.50	104.34	212.16 S	36.39 E	0.00	215.25	
280.00	92.50	170.50	104.08	217.08 S	37.22 E	20.00	220.24	
285.00	90.00	169.50	103.97	222.00 S	38.08 E	53.85	225.24	
290.00	88.00	167.50	104.05	226.90 S	39.08 E	56.56	230.24	
295.00	86.00	166.50	104.32	231.76 S	40.20 E	44.71	235.23	
300.00	84.50	163.50	104.73	236.58 S	41.49 E	66.90	240.19	
305.00	86.00	162.50	105.14	241.34 S	42.95 E	36.02	245.14	
310.00	87.50	159.50	105.43	246.06 S	44.58 E	66.99	250.06	
315.00	90.50	158.50	105.51	250.73 S	46.37 E	63.24	254.97	
320.00	93.00	158.50	105.36	255.38 S	48.20 E	50.00	259.87 AMH 6	

All data is in feet unless otherwise stated
Coordinates are from AMH 6 Shallow #6 and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH 6 Shallow #6
300-M, Aiken, South Carolina

SURVEY LISTING Page 3
Your ref : 5-18-91
Last revised : 19-Jul-91

				Comments in wellpath
				=====
MD	TVD	Rectangular Coords.		Comment

320.00	105.36	255.38 S 48.20 E	AMH 6	

All data is in feet unless otherwise stated
Coordinates are from AMH 6 Shallow #6 and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells
AMH 5 Shallow #5
300-M
Aiken, South Carolina

S U R V E Y L I S T I N G

Your ref : 4-13-91
Our ref : svy69
Other ref :

Date printed : 19-Jul-91
Date created : 19-Jul-91
Last revised : 19-Jul-91

Field is centred on n33 19 57.280,e81 44 16.39
Structure is centred on n33 19 57.280,e81 44 16.39

Westinghouse Savannah River Site
Horizontal Wells, AMH 5 Shallow #5
300-M, Aiken, South Carolina

SURVEY LISTING Page 1
Your ref : 4-13-91
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S		Dogleg Deg/100Ft	Vert Sect
0.00	0.00	0.00	0.00	0.00	N	0.00	0.00
24.00	16.50	161.50	23.67	3.25	S	1.09	3.39
34.00	21.50	161.50	33.12	6.34	S	2.12	6.61
39.00	24.25	161.50	37.73	8.18	S	2.74	8.54
44.00	27.00	161.50	42.24	10.23	S	3.42	10.67
49.00	29.25	158.50	46.64	12.45	S	4.23	12.99
54.00	32.00	157.50	50.95	14.81	S	5.19	15.48
59.00	35.00	156.50	55.12	17.35	S	6.27	18.17
64.00	37.75	156.50	59.14	20.07	S	7.45	21.06
69.00	40.00	155.50	63.03	22.93	S	8.72	24.10
74.00	42.50	154.50	66.79	25.92	S	10.12	27.28
79.00	45.25	154.50	70.40	29.05	S	11.61	30.62
84.00	48.50	154.50	73.81	32.34	S	13.18	34.14
89.00	50.50	154.50	77.06	35.77	S	14.82	37.80
94.00	53.50	155.50	80.14	39.34	S	16.48	41.61
99.00	56.50	155.50	83.01	43.07	S	18.18	45.57
104.00	59.50	155.50	85.66	46.93	S	19.94	49.68
109.00	61.50	155.50	88.12	50.89	S	21.74	53.89
114.00	64.00	155.50	90.41	54.93	S	23.59	58.19
119.00	67.00	155.50	92.48	59.07	S	25.47	62.60
124.00	69.50	155.50	94.33	63.30	S	27.40	67.09
129.00	72.00	156.50	95.98	67.61	S	29.32	71.67
134.00	75.00	156.50	97.40	72.01	S	31.23	76.34
139.00	78.50	156.50	98.55	76.47	S	33.17	81.07
144.00	81.50	156.50	99.42	80.98	S	35.13	85.85
149.00	84.75	156.50	100.01	85.54	S	37.11	90.68
154.00	87.50	156.50	100.35	90.11	S	39.10	95.53
159.00	91.00	159.50	100.42	94.74	S	40.97	100.42
164.00	93.50	159.50	100.22	99.42	S	42.72	105.33
169.00	93.50	158.50	99.92	104.08	S	44.51	110.23
174.00	91.25	158.50	99.71	108.73	S	46.34	115.13
179.00	90.00	158.50	99.65	113.38	S	48.18	120.02
184.00	89.00	158.50	99.70	118.03	S	50.01	124.92
189.00	87.25	158.50	99.86	122.68	S	51.84	129.82
194.00	86.50	157.50	100.13	127.31	S	53.71	134.70
199.00	85.00	157.50	100.50	131.92	S	55.62	139.57
204.00	85.00	157.50	100.94	136.52	S	57.52	144.44
209.00	85.00	158.50	101.38	141.14	S	59.39	149.31
214.00	84.50	159.50	101.83	145.79	S	61.17	154.20
219.00	84.75	161.50	102.30	150.48	S	62.84	159.10
224.00	85.00	161.50	102.75	155.20	S	64.42	164.03
229.00	84.50	162.50	103.21	159.94	S	65.95	168.96
234.00	84.75	161.50	103.67	164.67	S	67.49	173.89
239.00	85.00	160.50	104.12	169.38	S	69.11	178.81
244.00	86.00	158.50	104.51	174.05	S	70.86	183.71
249.00	86.25	158.50	104.85	178.69	S	72.69	188.60
254.00	87.25	156.50	105.14	183.30	S	74.60	193.47
259.00	88.00	155.50	105.34	187.86	S	76.63	198.32
264.00	90.00	153.50	105.43	192.38	S	78.78	203.14
269.00	91.00	154.50	105.39	196.87	S	80.97	207.94
274.00	91.50	155.50	105.28	201.40	S	83.09	212.77
279.00	92.00	156.50	105.12	205.97	S	85.12	217.62
284.00	91.50	157.50	104.97	210.57	S	87.07	222.49

All data is in feet unless otherwise stated
Coordinates are from AMH 5 Shallow #5 and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH 5 Shallow #5
300-M, Aiken, South Carolina

SURVEY LISTING Page 2
Your ref : 4-13-91
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S		Dogleg Deg/100Ft	Vert Sect
289.00	90.00	163.50	104.91	215.28 S	88.74 E	123.68	227.42
294.00	88.50	163.50	104.97	220.07 S	90.16 E	30.00	232.38
299.00	87.50	164.50	105.15	224.87 S	91.54 E	28.28	237.35
304.00	86.50	164.50	105.41	229.69 S	92.87 E	20.00	242.32
309.00	87.50	165.50	105.67	234.51 S	94.16 E	28.26	247.30 FISH

All data is in feet unless otherwise stated
Coordinates are from AMH 5 Shallow #5 and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH 5 Shallow #5
300-M, Aiken, South Carolina

SURVEY LISTING Page 3
Your ref : 4-13-91
Last revised : 19-Jul-91

				Comments in wellpath =====
MD	TVD	Rectangular Coords.		Comment
309.00	105.67	234.51 S	94.16 E	FISH

All data is in feet unless otherwise stated
Coordinates are from AMH 5 Shallow #5 and TVDs are from wellhead.
Vertical section is from W 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells
AMH 5 Shallow #5
300-M
Aiken, South Carolina

S U R V E Y L I S T I N G

Your ref : horiz B around fish
Our ref : svy70
Other ref :

Date printed : 19-Jul-91
Date created : 19-Jul-91
Last revised : 19-Jul-91

Field is centred on n33 19 57.280,e81 44 16.39
Structure is centred on n33 19 57.280,e81 44 16.39

Westinghouse Savannah River Site
Horizontal Wells, AMH 5 Shallow #5
300-M, Aiken, South Carolina

SURVEY LISTING Page 1
Your ref : horiz B around fish
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S		Dogleg Deg/100Ft	Vert Sect
0.00	0.00	0.00	0.00	0.00 N	0.00 E	0.00	0.00
24.00	16.50	161.50	23.67	3.25 S	1.09 E	68.75	3.39
34.00	21.50	161.50	33.12	6.34 S	2.12 E	50.00	6.61
39.00	24.25	161.50	37.73	8.18 S	2.74 E	55.00	8.54
44.00	27.00	161.50	42.24	10.23 S	3.42 E	55.00	10.67
49.00	29.25	158.50	46.64	12.45 S	4.23 E	53.14	12.99
54.00	32.00	157.50	50.95	14.81 S	5.19 E	55.93	15.48
59.00	35.00	156.50	55.12	17.35 S	6.27 E	61.00	18.17
64.00	37.75	156.50	59.14	20.07 S	7.45 E	55.00	21.06
69.00	40.00	155.50	63.03	22.93 S	8.72 E	46.72	24.10
74.00	42.50	154.50	66.79	25.92 S	10.12 E	51.71	27.28
79.00	45.25	154.50	70.40	29.05 S	11.61 E	55.00	30.62
84.00	48.50	154.50	73.81	32.34 S	13.18 E	65.00	34.14
89.00	50.50	154.50	77.06	35.77 S	14.82 E	40.00	37.80
94.00	53.50	155.50	80.14	39.34 S	16.48 E	62.03	41.61
99.00	56.50	155.50	83.01	43.07 S	18.18 E	60.00	45.57
104.00	59.50	155.50	85.66	46.93 S	19.94 E	60.00	49.68
109.00	61.50	155.50	88.12	50.89 S	21.74 E	40.00	53.89
114.00	64.00	155.50	90.41	54.93 S	23.59 E	50.00	58.19
119.00	67.00	155.50	92.48	59.07 S	25.47 E	60.00	62.60
124.00	69.50	155.50	94.33	63.30 S	27.40 E	50.00	67.09
129.00	72.00	156.50	95.98	67.61 S	29.32 E	53.44	71.67
134.00	75.00	156.50	97.40	72.01 S	31.23 E	60.00	76.34
139.00	78.50	156.50	98.55	76.47 S	33.17 E	70.00	81.07
144.00	81.50	156.50	99.42	80.98 S	35.13 E	60.00	85.85
149.00	84.75	156.50	100.01	85.54 S	37.11 E	65.00	90.68
154.00	87.50	156.50	100.35	90.11 S	39.10 E	55.00	95.53
159.00	91.00	159.50	100.42	94.74 S	40.97 E	92.19	100.42
164.00	93.50	159.50	100.22	99.42 S	42.72 E	50.00	105.33
168.00	93.50	158.70	99.98	103.15 S	44.15 E	19.96	109.25
170.00	90.25	158.50	99.91	105.01 S	44.88 E	162.81	111.21
172.00	91.50	157.50	99.88	106.87 S	45.63 E	80.03	113.17
174.00	92.00	157.50	99.82	108.72 S	46.39 E	25.00	115.12
176.00	92.00	157.50	99.75	110.56 S	47.16 E	0.00	117.07
178.00	91.00	157.50	99.70	112.41 S	47.92 E	50.00	119.02
180.00	89.75	157.50	99.68	114.26 S	48.69 E	62.50	120.98
182.00	89.50	157.50	99.70	116.10 S	49.45 E	12.50	122.93
184.00	89.00	157.50	99.72	117.95 S	50.22 E	25.00	124.88
186.00	88.25	157.50	99.77	119.80 S	50.98 E	37.50	126.83
188.00	87.50	157.50	99.85	121.64 S	51.75 E	37.50	128.78
190.00	87.00	157.50	99.94	123.49 S	52.51 E	25.00	130.73
192.00	86.75	157.50	100.05	125.34 S	53.28 E	12.50	132.68
194.00	86.00	157.50	100.18	127.18 S	54.04 E	37.50	134.63
196.00	85.75	157.50	100.32	129.02 S	54.80 E	12.50	136.58
198.00	85.50	157.50	100.47	130.86 S	55.57 E	12.50	138.53
200.00	85.25	157.50	100.64	132.71 S	56.33 E	12.50	140.47
202.00	85.25	156.50	100.80	134.54 S	57.11 E	49.83	142.41
204.00	85.00	156.50	100.97	136.37 S	57.90 E	12.50	144.35
206.00	85.00	156.50	101.14	138.20 S	58.70 E	0.00	146.29
208.00	85.00	156.50	101.32	140.02 S	59.49 E	0.00	148.23
210.00	85.00	157.50	101.49	141.86 S	60.27 E	49.81	150.17
212.00	85.00	157.50	101.67	143.70 S	61.03 E	0.00	152.11
214.00	84.50	157.50	101.85	145.54 S	61.79 E	25.00	154.06

All data is in feet unless otherwise stated
Coordinates are from AMH 5 Shallow #5 and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH 5 Shallow #5
300-M, Aiken, South Carolina

SURVEY LISTING Page 2
Your ref : horiz B around fish
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S	Dogleg Deg/100Ft	Vert Sect
216.00	84.50	158.50	102.04	147.38 S 62.54 E	49.77	156.00
218.00	84.75	159.50	102.23	149.24 S 63.25 E	51.32	157.96
220.00	85.00	159.50	102.41	151.11 S 63.95 E	12.50	159.92
222.00	85.00	161.50	102.58	152.99 S 64.62 E	99.62	161.88
224.00	85.00	161.50	102.76	154.88 S 65.25 E	0.00	163.85
226.00	85.25	161.50	102.93	156.77 S 65.88 E	12.50	165.82
228.00	85.75	161.50	103.08	158.66 S 66.51 E	25.00	167.80
230.00	86.00	161.50	103.23	160.55 S 67.15 E	12.50	169.77 AMH 5

All data is in feet unless otherwise stated
Coordinates are from AMH 5 Shallow #5 and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH 5 Shallow #5
300-M, Aiken, South Carolina

SURVEY LISTING Page 3
Your ref : horiz 8 around fish
Last revised : 19-Jul-91

Comments in wellpath =====				
MD	TVD	Rectangular Coords.		Comment
230.00	103.23	160.55 S	67.15 E	AMH 5

All data is in feet unless otherwise stated
Coordinates are from AMH 5 Shallow #5 and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells
AMH 4-4 Shallow #4
300-M
Aiken, South Carolina

S U R V E Y L I S T I N G

Your ref : 4-1-91
Our ref : svy68
Other ref :

Date printed : 19-Jul-91
Date created : 19-Jul-91
Last revised : 19-Jul-91

Field is centred on n33 19 57.280,e81 44 16.39
Structure is centred on n33 19 57.280,e81 44 16.39

Westinghouse Savannah River Site
Horizontal Wells, AMH 4-4 Shallow #4
300-M, Aiken, South Carolina

SURVEY LISTING Page 1
Your ref : 4-1-91
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S		Dogleg Deg/100Ft	Vert Sect
0.00	0.00	0.00	0.00	0.00	N	0.00	0.00
18.00	18.25	168.50	17.70	2.78	S	0.57 E	2.84
21.00	19.00	172.50	20.54	3.73	S	0.72 E	3.80
24.00	20.00	172.50	23.37	4.72	S	0.85 E	4.80
27.00	20.50	165.50	26.18	5.74	S	1.05 E	5.84
30.00	22.00	168.50	28.98	6.80	S	1.30 E	6.92
33.00	23.00	169.50	31.75	7.93	S	1.52 E	8.07
36.00	25.00	172.50	34.49	9.13	S	1.70 E	9.29
39.00	26.50	174.50	37.19	10.43	S	1.85 E	10.59
42.00	28.00	176.50	39.86	11.80	S	1.96 E	11.96
45.00	29.75	177.50	42.49	13.24	S	2.03 E	13.39
48.00	31.00	178.50	45.08	14.76	S	2.09 E	14.90
51.00	32.50	179.50	47.63	16.34	S	2.11 E	16.46
54.00	32.25	180.50	50.16	17.94	S	2.11 E	18.04
57.00	36.00	181.50	52.64	19.62	S	2.08 E	19.69
60.00	38.00	182.50	55.04	21.43	S	2.02 E	21.45
63.00	39.00	182.50	57.39	23.30	S	1.94 E	23.28
66.00	40.75	184.50	59.69	25.21	S	1.82 E	25.15
69.00	42.00	185.50	61.94	27.19	S	1.65 E	27.06
72.00	44.00	187.50	64.13	29.22	S	1.42 E	29.02
75.00	45.50	188.50	66.26	31.31	S	1.12 E	31.03
78.00	47.50	189.50	68.33	33.46	S	0.78 E	33.09
81.00	49.00	190.50	70.33	35.67	S	0.39 E	35.19
84.00	50.50	190.50	72.26	37.92	S	0.02 W	37.34
87.00	52.00	191.50	74.14	40.21	S	0.47 W	39.52
90.00	53.00	192.50	75.97	42.54	S	0.96 W	41.73
93.00	55.00	193.50	77.73	44.91	S	1.51 W	43.96
96.00	56.50	194.50	79.42	47.31	S	2.11 W	46.23
99.00	58.25	194.50	81.04	49.76	S	2.74 W	48.53
102.00	60.00	195.50	82.58	52.25	S	3.41 W	50.86
105.00	61.00	195.50	84.06	54.76	S	4.11 W	53.22
108.00	62.00	196.50	85.49	57.30	S	4.84 W	55.59
111.00	63.75	197.50	86.85	59.85	S	5.62 W	57.96
114.00	65.00	197.50	88.15	62.43	S	6.43 W	60.36
117.00	67.00	198.50	89.37	65.04	S	7.28 W	62.78
120.00	68.50	198.50	90.51	67.67	S	8.16 W	65.22
123.00	70.00	199.50	91.57	70.32	S	9.07 W	67.68
126.00	71.50	200.50	92.56	72.98	S	10.04 W	70.13
129.00	72.50	202.50	93.49	75.64	S	11.08 W	72.56
132.00	74.50	203.50	94.34	78.28	S	12.21 W	74.97
135.00	76.00	204.50	95.10	80.93	S	13.39 W	77.38
138.00	77.50	205.50	95.79	83.58	S	14.62 W	79.77
141.00	79.00	206.50	96.40	86.22	S	15.91 W	82.15
144.00	80.00	207.50	96.95	88.85	S	17.25 W	84.50
147.00	81.25	209.50	97.44	91.45	S	18.66 W	86.82
150.00	83.00	210.50	97.85	94.02	S	20.15 W	89.10
153.00	83.50	212.50	98.20	96.56	S	21.70 W	91.33
156.00	84.50	213.50	98.51	99.06	S	23.33 W	93.51
159.00	85.00	214.50	98.79	101.54	S	25.00 W	95.66
162.00	85.00	215.50	99.05	103.99	S	26.72 W	97.77
165.00	85.00	216.50	99.31	106.41	S	28.47 W	99.85
169.00	86.50	217.50	99.61	109.59	S	30.87 W	102.57 AMH 4-4

All data is in feet unless otherwise stated
Coordinates are from AMH 4-4 Shallow #4 and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH 4-4 Shallow #4
300-M, Aiken, South Carolina

SURVEY LISTING Page 2
Your ref : 4-1-91
Last revised : 19-Jul-91

				Comments in wellpath
				=====
MD	TVD	Rectangular Coords.		Comment

169.00	99.61	109.59 S	30.87 W	AMH 4-4

All data is in feet unless otherwise stated
Coordinates are from AMH 4-4 Shallow #4 and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells
AMH 4-3 shallow #3
300-M
Aiken, South Carolina

S U R V E Y L I S T I N G

Your ref : 3-26-91
Our ref : svy67
Other ref :

Date printed : 19-Jul-91
Date created : 19-Jul-91
Last revised : 19-Jul-91

Field is centred on n33 19 57.280,e81 44 16.39
Structure is centred on n33 19 57.280,e81 44 16.39

Westinghouse Savannah River Site
Horizontal Wells, AMH 4-3 shallow #3
300-M, Aiken, South Carolina

SURVEY LISTING Page 1
Your ref : 3-26-91
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S			Dogleg Deg/100Ft	Vert Sect
0.00	0.00	0.00	0.00	0.00 N	0.00 E	0.00	0.00	0.00
27.00	21.00	163.50	26.40	4.69 S	1.39 E	77.78	4.86	
28.00	21.00	163.50	27.33	5.03 S	1.49 E	0.00	5.22	
29.00	21.00	163.50	28.27	5.38 S	1.59 E	0.00	5.57	
30.00	24.00	162.50	29.19	5.74 S	1.70 E	302.42	5.95	
31.00	25.00	162.50	30.10	6.14 S	1.83 E	100.00	6.36	
32.00	26.00	161.50	31.00	6.55 S	1.96 E	108.87	6.79	
33.00	28.50	161.50	31.89	6.98 S	2.11 E	250.00	7.24	
34.00	31.00	161.50	32.76	7.45 S	2.26 E	250.00	7.73	
35.00	33.50	161.50	33.60	7.96 S	2.44 E	250.00	8.26	
37.00	36.00	161.50	35.25	9.04 S	2.80 E	125.00	9.39	
39.38	38.00	161.50	37.15	10.40 S	3.25 E	84.03	10.80	
41.00	40.00	162.50	38.41	11.37 S	3.57 E	129.42	11.82	
43.00	42.00	163.50	39.92	12.62 S	3.95 E	105.24	13.12	
45.00	44.00	164.50	41.38	13.93 S	4.32 E	105.65	14.47	
47.00	44.00	164.50	42.82	15.27 S	4.70 E	0.00	15.86	
49.00	44.00	164.50	44.26	16.61 S	5.07 E	0.00	17.24	
51.00	50.00	168.50	45.62	18.03 S	5.41 E	333.65	18.70	
53.00	51.25	168.50	46.89	19.55 S	5.71 E	62.50	20.24	
55.00	53.00	168.50	48.12	21.10 S	6.03 E	87.50	21.82	
57.00	54.50	168.50	49.30	22.68 S	6.35 E	75.00	23.43	
59.00	56.00	171.50	50.44	24.29 S	6.64 E	144.26	25.08	
61.00	57.00	172.50	51.54	25.94 S	6.87 E	65.10	26.74	
63.00	59.00	174.50	52.60	27.63 S	7.06 E	131.11	28.44	
65.00	59.00	174.50	53.63	29.34 S	7.22 E	0.00	30.15	
67.00	59.00	174.50	54.66	31.04 S	7.39 E	0.00	31.86	
69.00	59.00	174.50	55.69	32.75 S	7.55 E	0.00	33.56	AMH 4-3

All data is in feet unless otherwise stated
Coordinates are from AMH 4-3 shallow #3 and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH 4-3 shallow #3
300-M, Aiken, South Carolina

SURVEY LISTING Page 2

Your ref : 3-26-91

Last revised : 19-Jul-91

				Comments in wellpath
				=====
MD	TVD	Rectangular Coords.		Comment
69.00	55.69	32.75 S	7.55 E	AMH 4-3

All data is in feet unless otherwise stated
Coordinates are from AMH 4-3 shallow #3 and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells
AMH 4-2 shallow #2
300-M
Aiken, South Carolina

S U R V E Y L I S T I N G

Your ref : 3-9-91
Our ref : svy66
Other ref :

Date printed : 19-Jul-91
Date created : 19-Jul-91
Last revised : 19-Jul-91

Field is centred on n33 19 57.280,e81 44 16.39
Structure is centred on n33 19 57.280,e81 44 16.39

Westinghouse Savannah River Site
Horizontal Wells, AMH 4-2 shallow #2
300-M, Aiken, South Carolina

SURVEY LISTING Page 1
Your ref : 3-9-91
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S		Dogleg Deg/100Ft	Vert Sect
0.00	0.00	0.00	0.00	0.00 N	0.00 E	0.00	0.00
7.00	17.00	165.50	6.90	1.00 S	0.26 E	242.86	1.03
10.00	17.00	165.50	9.77	1.85 S	0.48 E	0.00	1.90
13.00	17.00	165.50	12.64	2.70 S	0.70 E	0.00	2.78
16.00	17.00	165.50	15.50	3.54 S	0.92 E	0.00	3.65
19.00	17.00	162.50	18.37	4.39 S	1.16 E	29.23	4.52
22.00	17.00	166.50	21.24	5.23 S	1.39 E	38.98	5.40
25.00	17.00	165.50	24.11	6.08 S	1.60 E	9.74	6.27
28.00	16.50	165.50	26.98	6.92 S	1.82 E	16.67	7.13
31.00	16.50	164.50	29.86	7.74 S	2.04 E	9.47	7.98
34.00	17.00	163.50	32.73	8.58 S	2.28 E	19.24	8.84
37.00	18.00	162.50	35.59	9.44 S	2.54 E	34.81	9.74
40.00	19.50	161.50	38.44	10.35 S	2.84 E	51.13	10.69
43.00	21.00	160.50	41.25	11.34 S	3.10 E	51.31	11.72
46.00	22.50	160.50	44.04	12.38 S	3.55 E	50.00	12.81
49.00	23.50	160.50	46.80	13.49 S	3.94 E	33.33	13.97
52.00	24.75	160.50	49.54	14.64 S	4.35 E	41.67	15.18
55.00	26.00	160.50	52.24	15.86 S	4.78 E	41.67	16.45
58.00	27.75	160.50	54.92	17.14 S	5.23 E	58.33	17.78
61.00	29.00	160.50	57.56	18.48 S	5.71 E	41.67	19.19
64.00	30.75	158.50	60.16	19.88 S	6.23 E	67.12	20.66
67.00	32.50	158.50	62.72	21.34 S	6.81 E	58.33	22.20
70.00	33.50	159.50	65.23	22.87 S	7.40 E	37.96	23.80
73.00	35.00	160.50	67.71	24.45 S	7.97 E	53.40	25.47
76.00	36.00	160.50	70.15	26.10 S	8.55 E	33.33	27.18
79.00	38.00	160.50	72.55	27.80 S	9.16 E	66.67	28.96
82.00	39.75	160.50	74.89	29.57 S	9.78 E	58.33	30.82
85.00	41.00	160.50	77.17	31.40 S	10.43 E	41.67	32.74
88.00	42.50	159.50	79.41	33.28 S	11.12 E	54.70	34.71
91.00	44.50	158.50	81.58	35.21 S	11.86 E	70.50	36.73
94.00	46.00	158.50	83.70	37.19 S	12.64 E	50.00	38.82
97.00	48.00	158.50	85.74	39.23 S	13.44 E	66.67	40.97
100.00	49.50	158.50	87.72	41.33 S	14.27 E	50.00	43.18
103.00	51.25	158.50	89.63	43.48 S	15.12 E	58.33	45.44
106.00	52.50	158.50	91.49	45.68 S	15.98 E	41.67	47.76
109.00	53.50	156.50	93.29	47.89 S	16.90 E	62.81	50.10
112.00	54.00	155.50	95.07	50.10 S	17.88 E	31.63	52.44
115.00	54.25	154.50	96.82	52.30 S	18.91 E	28.27	54.79
118.00	54.50	152.50	98.57	54.48 S	20.00 E	54.82	57.13
121.00	55.00	150.50	100.30	56.64 S	21.17 E	56.94	59.45
124.00	55.00	149.50	102.02	58.77 S	22.40 E	27.30	61.76
127.00	54.25	152.50	103.76	60.90 S	23.58 E	85.28	64.07
130.00	53.00	144.50	105.54	62.96 S	24.84 E	218.64	66.32
133.00	52.00	142.50	107.37	64.88 S	26.26 E	62.52	68.45
136.00	50.50	141.50	109.25	66.72 S	27.70 E	56.35	70.52
139.00	49.50	140.50	111.17	68.50 S	29.14 E	41.99	72.52
142.00	48.00	138.50	113.15	70.22 S	30.61 E	70.79	74.47
145.00	47.00	136.50	115.18	71.85 S	32.10 E	59.38	76.33
148.00	46.00	134.50	117.24	73.40 S	33.62 E	58.73	78.13
151.00	44.50	132.50	119.36	74.87 S	35.17 E	68.85	79.84
154.00	42.50	131.50	121.53	76.25 S	36.70 E	70.50	81.47
157.00	40.00	129.50	123.79	77.54 S	38.21 E	94.21	82.99
160.00	38.75	127.50	126.11	78.72 S	39.70 E	59.36	84.42

All data is in feet unless otherwise stated
Coordinates are from AMH 4-2 shallow #2 and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH 4-2 shallow #2
300-M, Aiken, South Carolina

SURVEY LISTING Page 2
Your ref : 3-9-91
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S			Dogleg Deg/100Ft	Vert Sect
163.00	37.50	125.50	128.47	79.82 S	41.18 E	58.56	85.76	
166.00	36.25	123.50	130.87	80.84 S	42.67 E	57.76	87.02	
168.00	35.00	121.50	132.49	81.47 S	43.65 E	85.43	87.81 AMH 4-2	

All data is in feet unless otherwise stated
Coordinates are from AMH 4-2 shallow #2 and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH 4-2 shallow #2
300-M, Aiken, South Carolina

SURVEY LISTING Page 3
Your ref : 3-9-91
Last revised : 19-Jul-91

				Comments in wellpath =====
MD	TVD	Rectangular Coords.		Comment
168.00	132.49	81.47 S	43.65 E	AMH 4-2

All data is in feet unless otherwise stated
Coordinates are from AMH 4-2 shallow #2 and TVDs are from wellhead.
Vertical section is from W 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells
AMH 4-1 (shallow #1)
300-M
Aiken, South Carolina

S U R V E Y L I S T I N G

Your ref :
Our ref : svy65
Other ref :

Date printed : 19-Jul-91
Date created : 19-Jul-91
Last revised : 19-Jul-91

Field is centred on n33 19 57.280,e81 44 16.39
Structure is centred on n33 19 57.280,e81 44 16.39

Westinghouse Savannah River Site
Horizontal Wells, AMH 4-1 (shallow #1)
300-M, Aiken, South Carolina

SURVEY LISTING Page 1
Your ref :
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S		Dogleg Deg/100Ft	Vert Sect
0.00	0.00	0.00	0.00	0.00	N	0.00	0.00
26.00	33.50	173.50	24.54	7.34	S	0.84	7.37
38.00	36.50	170.50	34.37	14.15	S	1.80	14.25
47.00	41.00	163.50	41.39	19.63	S	3.08	19.86
56.00	45.00	162.50	47.97	25.50	S	4.88	25.96
65.00	47.00	157.50	54.23	31.57	S	7.10	32.33
74.00	51.00	149.50	60.14	37.64	S	10.13	38.82
83.00	55.25	143.50	65.54	43.63	S	14.11	45.41
92.00	61.00	141.50	70.29	49.68	S	18.76	52.19
101.00	68.50	142.50	74.13	56.10	S	23.77	59.37
110.00	75.00	142.50	76.94	62.87	S	28.97	66.95
119.00	81.75	144.50	78.76	69.96	S	34.21	74.83
128.00	86.00	145.50	79.72	77.28	S	39.34	82.94
137.00	87.00	146.50	80.27	84.73	S	44.36	91.15
146.00	85.00	147.50	80.89	92.26	S	49.26	99.41
155.00	83.00	150.50	81.83	99.93	S	53.86	107.77
164.00	81.50	150.50	83.05	107.69	S	58.26	116.17
173.00	79.00	154.50	84.57	115.56	S	62.35	124.63
182.00	76.50	155.50	86.48	123.53	S	66.07	133.12
191.00	74.00	157.50	88.77	131.51	S	69.54	141.59
200.00	73.00	163.50	91.33	139.64	S	72.42	150.09
209.00	77.50	159.50	93.62	147.89	S	75.18	158.70
218.00	87.00	164.50	94.84	156.36	S	77.93	167.51
227.00	90.00	166.50	95.07	165.07	S	80.18	176.48
238.00	89.28	166.50	95.14	175.76	S	82.75	187.46
239.00	90.16	166.50	95.15	176.73	S	82.98	188.46
242.00	93.04	166.50	95.06	179.65	S	83.68	191.45
243.00	93.28	166.50	95.01	180.62	S	83.92	192.45
248.00	94.60	166.50	94.66	185.47	S	85.08	197.43
250.00	93.92	166.50	94.52	187.41	S	85.55	199.42
255.00	93.60	166.50	94.19	192.26	S	86.71	204.40
263.00	91.25	166.50	93.85	200.03	S	88.58	212.38
271.00	91.25	166.50	93.67	207.81	S	90.44	220.36
280.00	86.40	166.50	93.86	216.56	S	92.54	229.34
285.00	85.12	166.50	94.23	221.40	S	93.71	234.31
286.00	84.80	166.50	94.32	222.37	S	93.94	235.31
291.00	83.52	166.50	94.82	227.21	S	95.10	240.27
294.00	82.56	166.50	95.19	230.11	S	95.80	243.24
298.00	82.24	166.50	95.72	233.96	S	96.72	247.20
304.00	80.64	166.50	96.61	239.73	S	98.11	253.12
308.00	79.04	166.50	97.32	243.56	S	99.03	257.05
315.00	77.12	166.50	98.76	250.22	S	100.62	263.89
320.00	76.16	166.50	99.92	254.95	S	101.76	268.75
327.00	74.56	166.50	101.69	261.53	S	103.34	275.51
331.00	73.60	166.50	102.78	265.27	S	104.24	279.34
336.00	72.64	166.50	104.24	269.93	S	105.36	284.12
338.00	72.00	166.50	104.84	271.78	S	105.80	286.02
340.00	71.68	166.50	105.47	273.63	S	106.24	287.92
345.00	72.00	166.50	107.02	278.25	S	107.35	292.66
348.00	72.64	166.50	107.94	281.03	S	108.02	295.52
355.00	74.88	166.50	109.89	287.56	S	109.59	302.22
358.00	75.84	166.50	110.65	290.38	S	110.27	305.12
361.00	76.16	166.50	111.38	293.21	S	110.95	308.02

All data is in feet unless otherwise stated
Coordinates are from AMH 4-1 (shallow #1) and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH 4-1 (shallow #1)
30C-M, Aiken, South Carolina

SURVEY LISTING Page 2
Your ref :
Last revised : 19-Jul-91

Measured Depth	Inclin. Degrees	Azimuth Degrees	True Vert. Depth	R E C T A N G U L A R C O O R D I N A T E S		Dogleg Deg/100Ft	Vert Sect
365.00	75.84	166.50	112.34	296.99 S	111.85 E	8.00	311.90
370.00	76.16	166.50	113.56	301.70 S	112.99 E	6.40	316.74
375.00	76.80	166.50	114.72	306.43 S	114.12 E	12.80	321.59
385.00	78.08	166.50	116.90	315.92 S	116.40 E	12.80	331.34
395.00	79.37	166.50	118.85	325.46 S	118.69 E	12.90	341.12
404.00	80.64	166.50	120.42	334.08 S	120.76 E	14.11	349.97
414.00	81.92	166.50	121.93	343.69 S	123.06 E	12.80	359.84
424.00	83.20	166.50	123.23	353.33 S	125.38 E	12.80	369.73
429.00	84.48	166.50	123.76	358.16 S	126.54 E	25.60	374.70
444.00	86.00	166.50	125.01	372.70 S	130.03 E	10.13	389.62 AMH 4-1

All data is in feet unless otherwise stated
Coordinates are from AMH 4-1 (shallow #1) and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

Westinghouse Savannah River Site
Horizontal Wells, AMH 4-1 (shallow #1)
300-M, Aiken, South Carolina

SURVEY LISTING Page 3
Your ref :
Last revised : 19-Jul-91

MD	TVD	Rectangular Coords.	Comments in wellpath	
			=====	Comment
444.00	125.01	372.70 S 130.03 E	AMH 4-1	

All data is in feet unless otherwise stated
Coordinates are from AMH 4-1 (shallow #1) and TVDs are from wellhead.
Vertical section is from N 0.00 E 0.00 on azimuth 170.00 degrees.
Calculation uses the minimum curvature method.

APPENDIX D
WELL ABANDONMENT REPORTS

Effective Date: 08/01/89

SRS WELL ABANDONMENT REPORT

GENERAL INFORMATION

Well number AMH-4C (1st attempt) Location M Area
Project name Horizontal Wells
Custodian H. Blodsoe Custodial Dept. Environmental Science
SRS Coordinates: North 102,727.19 East 48,800.32
Or: Latitude 33-19-57.28 Longitude 81-44-16.39
Location description 300-Area, near M-Area Settling Basin
Savannah River Plant County Aiken
Installation contractor Eastman Christensen Date installed 3 / 4 / 91
Abandonment contractor Eastman Christensen Driller Eastman - Christiansen
Oversight contractor Sirrine Environmental Oversight R. Paulling
Well abandonment: Date started 3 / 5 / 91 Date completed 3 / 5 / 91

WELL DATA FILE REVIEW

Note: Depths are measured from ground surface to the nearest 0.1 ft.

Height of well seal or top of well casing above ground surface 0.0

Depth of well below ground surface (from data file) N/A

Measured depth from ground surface to bottom of well 91 feet (true vertical depth)

Depth from ground surface to static water level well above water table

Total drilled depth of borehole 442 feet Diameter (in.) 10 inches

Ground surface elevation (mean sea level) ~375 feet.

Reason for well abandonment Installation of well AMH-4C was unsuccessful
and therefore abandoned, because of ^{irreparable} damage done to screen
using when removing drill rods. cwb

Known problems with well materials or construction sand-locked ^{bit} in place.

Cannot complete well to contract depth and length. cwb

WELL CASING:

Type of Material	Schedule or Thickness	Nominal I. D. (in.)	Type Joint	From (ft.)	To (ft.)
HDPE			Flush		

WELL SCREEN(S):

Type of Material	Nominal I. D. (in.)	Slot Type	Type Size (in)	From (ft.)	To (ft.)
HDPE		machined	0.02 0.20		

WELL SUMP AND SUMP CAP:

Type of Material	Schedule or Thickness	Nominal I. D. (in.)	Type Joint	From (ft.)	To (ft.)
N/A					

Type of sump cap installed N/A Length (ft.) N/A
 Depth from ground surface to bottom of sump cap N/A

ANNULAR GROUT:

Type of Grout	Annular Thickness (in.)	From (ft.)	To (ft.)
Portland Cement	approx 1" to 2"	0'	120' TVD

WELL SEAL:

Type of Seal	From (ft.)	To (ft.)
N/A		

FILTER PACK:

Average Grain Size (mm)	From (ft.)	To (ft.)
<u>n/a</u>	<u>n/a</u>	<u>n/a</u>

GEOPHYSICAL LOGGING

Geophysical logs performed during well construction n/a

Geophysical logging subcontractor n/a

Geophysical logs performed during well abandonment n/a

Date logged / /

Geophysical logging subcontractor n/a

Logging truck operator n/a Oversight n/a

Geophysical logging comments n/a

WELL ABANDONMENT

General abandonment method(s) used (check where applicable):

☒ Pumping of grout through tremie pipe to fill inside of well screen and casing.

☐ Pressurized injection of grout into filter pack, screen and casing; pressure maintained until grout sets.

WELL ABANDONMENT - CONT'D

- _____ Cutting of casing and pressurized injection of grout into permeable zones; pressure maintained until grout sets.
- _____ Over-reaming of well casing and screen, pulling casing and screen from hole.
- _____ Milling out of casing and screen.
- _____ Drilling out well casing, screen and grout to original borehole diameter, removal of materials by flushing.
- _____ Pumping of grout through tremie pipe to fill borehole.
- _____ Other (describe) _____

Describe the actual method used to abandon this well _____

Inserted drill pipe to bottom of hole, injected grout at approx 25 to 30 GPM until grout flowed out of the top of well

Footage actually abandoned (From/To) Approx 300' Horizontal and 78' Vertical

Abandonment problems or deviations from abandonment specifications _____

Grout mix used Portland Type I Cement 941b sacks with 21bs
of Millgel and 7 gallons H₂O

GROUT PUMPED:

Number of Cubic Yards	Weight as Pumped	Date Pumped
241 (TOTAL)*	13 - 15 lbs/gal	3 / 5 / 91
		1 / 1
		1 / 1

* Approx 5 ft of settlement on top next day. Topped off grout, welded cap to steel conduit pipe. Volume based on calculated 10 in dia. hole at 442 ft.

SITE CLEANUP

Disposal of well pad, posts and other materials N/A

Disposal of well screen(s) and casing Left on site for inspection

Disposal of drilling mud N/A

Disposal of excess grout N/A

Date site cleanup completed 3 / 5 / 91

Site inspected by Ron Paulling Date 3 / 5 / 91

Report prepared by C. Budinger Date 3 / 12 / 91

Data accuracy verified by C. Budinger Date 3 / 12 / 91

WELL ABANDONMENT COMMENTS

SRS WELL ABANDONMENT REPORT

GENERAL INFORMATION

Well number AMH-4C (2nd attempt) Location M Area Basin - 300 Area
 Project name Horizontal well - SRS

Custodian Horace Bledsoe Custodial Dept. Environmental Science

SRS Coordinates: North 102,727.19 East 48,800.32

Or: Latitude 33-19-57.28 Longitude 81-44-16.39

Location description North of M-Area Settling Basin

County Aiken

Installation contractor Eastman-Christensen Date installed 3 / 10 / 91

Abandonment contractor Eastman-Christensen Driller Roy Jones / Joe Boyd

Oversight contractor Sirrine Oversight Bill Joyce

Well abandonment: Date started 3 / 10 / 91 Date completed 3 / 11 / 91

WELL DATA FILE REVIEW

Note: Depths are measured from ground surface to the nearest 0.1 ft.

Height of well seal or top of well casing above ground surface 0.0

Depth of well below ground surface (from data file) ~~104'~~ 133 feet cbs

Measured depth from ground surface to bottom of well 169'

Depth from ground surface to static water level 120'

Total drilled depth of borehole 169' (MD.) Diameter (in.) 12

Ground surface elevation (mean sea level) _____

Reason for well abandonment The ^{direction} configuration of the well was 44° off from its target configuration and ^{EOL} was too deep to finish within target zone.

- Known ^{lateral} problems with well materials or construction Surveyors question validity of some of their down hole survey readings. Also, a "dart" was dropped down the drill pipe ~~to~~ to prevent the down hole motor from turning; apparently there was a piece of equipment in the way, and the DHR turned which cut a section of the casing.

WELL CASING:

Type of Material	Schedule or Thickness	Nominal I. D. (in.)	Type Joint	From (ft.)	To (ft.)
HDPE	1/2"	10	push	0	169
Steel	1/8"	16	N/A	0	24

WELL SCREEN(S):

Type of Material	Nominal I. D. (in.)	Slot Type	Type Size (in)	From (ft.)	To (ft.)
N/A	N/A	N/A	N/A	N/A	N/A

WELL SUMP AND SUMP CAP:

Type of Material	Schedule or Thickness	Nominal I. D. (in.)	Type Joint	From (ft.)	To (ft.)
N/A	N/A	N/A	N/A	N/A	N/A

Type of sump cap installed N/A Length (ft.) N/A
 Depth from ground surface to bottom of sump cap N/A

ANNULAR GROUT:

Type of Grout	Annular Thickness (in.)	From (ft.)	To (ft.)
Type I	1 to 3	0	169

WELL SEAL:

Type of Seal	From (ft.)	To (ft.)
N/A	N/A	N/A

FILTER PACK:

Average Grain Size (mm)	From (ft.)	To (ft.)
<u>N/A</u>	<u>N/A</u>	<u>N/A</u>

GEOPHYSICAL LOGGING

Geophysical logs performed during well construction N/A

Geophysical logging subcontractor N/A

Geophysical logs performed during well abandonment N/A

Date logged / /

Geophysical logging subcontractor N/A

Logging truck operator N/A Oversight N/A

Geophysical logging comments N/A

WELL ABANDONMENT

General abandonment method(s) used (check where applicable):

☒ Pumping of grout through tremie pipe to fill inside of well screen and casing.

☐ Pressurized injection of grout into filter pack, screen and casing; pressure maintained until grout sets.

WELL ABANDONMENT - CONT'D

- _____ Cutting of casing and pressurized injection of grout into permeable zones; pressure maintained until grout sets.
- _____ Over-reaming of well casing and screen, pulling casing and screen from hole.
- _____ Milling out of casing and screen.
- _____ Drilling out well casing, screen and grout to original borehole diameter, removal of materials by flushing.
- ✓ _____ Pumping of grout through tremie pipe to fill borehole.
- _____ Other (describe) _____
- _____
- _____
- _____
- _____

Describe the actual method used to abandon this well Grout mixed as per project work plan, then tremied into hole bottom with 1" diameter tremie pipe to existing ground surface. Grout allowed to settle overnight; then capped off to ground surface. A steel plate was then welded to the steel casing at the ground surface.

Footage actually abandoned (From/To) 0 to 169

Abandonment problems or deviations from abandonment specifications None

Grout mix used One (94 lb. sack Type I Cement) per seven gallons of water and two lbs. of millgell.

GROUT PUMPED:

Number of Cubic Yards	Weight as Pumped	Date Pumped
135	13-14 lbs/gal.	3 / 11 / 91
		1 / 1
		1 / 1

SITE CLEANUP

Disposal of well pad, posts and other materials N/A

Disposal of well screen(s) and casing N/A

Disposal of drilling mud N/A

Disposal of excess grout Grout tanks and lines flushed with water and allowed to run off on ground surface.

Date site cleanup completed 3 / 11 / 91

Site inspected by ~~Bill Joyce~~ Ron Paulling Date 3 / 11 / 91

Report prepared by Ron Paulling Date 3 / 11 / 91

Data accuracy verified by Chuck Budinger Date 3 / 11 / 91

WELL ABANDONMENT COMMENTS

SRS WELL ABANDONMENT REPORT

GENERAL INFORMATION

Well number AMH-4C (310441) Location M- Area Basin
Project name Horizontal Well - Task 4
Custodian Horace Bledsoe Custodial Dept. Environmental Science
SRS Coordinates: North 102,727.19 East 48,800.32
Or: Latitude 33-19-57.28 Longitude 81-44-16.39
Location description 300 Area, north of M- Area Storage Basin
County Aiken
Installation contractor Eastman-Christensen Date installed — 1 — 1 —
Abandonment contractor Eastman-Christensen Driller Joe Boyd / Roy Jones
Oversight contractor Wirrine Environmental Oversight Ron Paulling
Well abandonment: Date started 3 / 27 / 91 Date completed 3 / 28 / 91

WELL DATA FILE REVIEW

Note: Depths are measured from ground surface to the nearest 0.1 ft.

Height of well seal or top of well casing above ground surface N/A
Depth of well below ground surface (from data file) _____
Measured depth from ground surface to bottom of well 109 Feet
Depth from ground surface to static water level approx 120 Feet
Total drilled depth of borehole 109 Diameter (in.) 10
Ground surface elevation (mean sea level) _____
Reason for well abandonment Unsatisfactory installation.

Known problems with well materials or construction Two (2) 10" diameter HDPE sections of casing separated when the drilling contractor was trying to loosen the down hole motor assembly.

WELL CASING:

Type of Material	Schedule or Thickness	Nominal I. D. (in.)	Type Joint	From (ft.)	To (ft.)
HDPE	1/2"	10	push	0	109
STEEL	1/8"	12	N/A	0	27

WELL SCREEN(S):

Type of Material	Nominal I. D. (in.)	Slot Type	Type Size (in)	From (ft.)	To (ft.)
N/A	N/A	N/A	N/A	N/A	N/A

WELL SUMP AND SUMP CAP:

Type of Material	Schedule or Thickness	Nominal I. D. (in.)	Type Joint	From (ft.)	To (ft.)
N/A					

Type of sump cap installed N/A Length (ft.) _____

Depth from ground surface to bottom of sump cap N/A

ANNULAR GROUT:

Type of Grout	Annular Thickness (in.)	From (ft.)	To (ft.)
Cement/Bembrite	1" to 2"	27	109

WELL SEAL:

Type of Seal	From (ft.)	To (ft.)
N/A		

WELL ABANDONMENT - CONT'D

- _____ Cutting of casing and pressurized injection of grout into permeable zones; pressure maintained until grout sets.
- _____ Over-reaming of well casing and screen, pulling casing and screen from hole.
- _____ Milling out of casing and screen.
- _____ Drilling out well casing, screen and grout to original borehole diameter, removal of materials by flushing.
- _____ Pumping of grout through tremie pipe to fill borehole.
- _____ Other (describe) _____

Describe the actual method used to abandon this well The well was abandoned by pumping the grout to the well bottom through 2 7/8" diameter drilling pipe until grout was observed returning to the existing ground surface. The grout was allowed to set up overnight. On March 28, 1991, the top of the grout was approximately 8' below grade. This was copped with fresh grout to the top of the 12" diameter steel casing, and a steel plate was welded over the casing.

Footage actually abandoned (From/To) 0' to 109'

Abandonment problems or deviations from abandonment specifications _____

Effective Date: 08/01/89

Grout mix used One (1) 94 lb sack of Type I cement to seven (7) gallons of water to four (4) lbs of millgel.

GROUT PUMPED:

Number of Cubic Yards	Weight as Pumped	Date Pumped
<u>90</u>	<u>13-14 lb/sol</u>	<u>3 127 91</u>
		<u>3 128 91</u>
		<u>1 1</u>

SITE CLEANUP

Disposal of well pad, posts and other materials N/A

Disposal of well screen(s) and casing N/A

Disposal of drilling mud N/A

Disposal of excess grout Mixed with extra water and washed into run off trench.

Date site cleanup completed 3 129 91

Site inspected by Ron Paulline Date 4 1 15 91

Report prepared by Ron Paulline Date 4 1 15 91

Data accuracy verified by Charles Budinger Date 4 1 16 91

WELL ABANDONMENT COMMENTS

SRS WELL ABANDONMENT REPORT

GENERAL INFORMATION

Well number AMH-4 (4th Attempt) Location M-Area
Project name Horizontal Wells
Custodian Horace Bledsoe Custodial Dept. Environmental Science
SRS Coordinates: North 102,730.30 East 48,801.76
Or: Latitude 33-19-57.31 Longitude 81-44-16.40
Location description North of M-Area Settling Basin
County Aiken
Installation contractor Eastman-Christensen Date installed 4 / 3 / 91
Abandonment contractor Eastman-Christensen Driller Joe Boyd / Carlos Keuda
Oversight contractor Sirrine Environmental Consultants Oversight C. Budinger
Well abandonment: Date started 4 / 3 / 91 Date completed 4 / 4 / 91

WELL DATA FILE REVIEW

Note: Depths are measured from ground surface to the nearest 0.1 ft.

Height of well seal or top of well casing above ground surface flush with surface

Depth of well below ground surface (from data file) 96 feet (true vertical depth)
Measured depth from ground surface to bottom of well 169 feet (curved section)
Depth from ground surface to static water level ~120 feet
Total drilled depth of borehole 169 feet Diameter (in.) 12 inches
Ground surface elevation (mean sea level) _____
Reason for well abandonment borehole curved in wrong direction.

Known problems with well materials or construction none.

WELL CASING:

Type of Material	Schedule or Thickness	Nominal I. D. (in.)	Type Joint	From (ft.)	To (ft.)
HDPE	1/2 in.	10 in.	Flush	0	169

WELL SCREEN(S):

Type of Material	Nominal I. D. (in.)	Slot Type	Type Size (in)	From (ft.)	To (ft.)
N/A	N/A	N/A	N/A	N/A	N/A

WELL SUMP AND SUMP CAP:

Type of Material	Schedule or Thickness	Nominal I. D. (in.)	Type Joint	From (ft.)	To (ft.)
N/A	N/A	N/A	N/A	N/A	N/A

Type of sump cap installed N/A Length (ft.) N/ADepth from ground surface to bottom of sump cap N/A

ANNULAR GROUT:

Type of Grout	Annular Thickness (in.)	From (ft.)	To (ft.)
Portland Type I	1-2 inches	28	169 feet

WELL SEAL:

Type of Seal	From (ft.)	To (ft.)
N/A	N/A	N/A

FILTER PACK:

Average Grain Size (mm)	From (ft.)	To (ft.)
<u>N/A</u>	<u>N/A</u>	<u>N/A</u>

GEOPHYSICAL LOGGING

Geophysical logs performed during well construction N/A

Geophysical logging subcontractor N/A

Geophysical logs performed during well abandonment N/A

_____ Date logged — / — / —

Geophysical logging subcontractor N/A

Logging truck operator N/A Oversight N/A

Geophysical logging comments N/A

WELL ABANDONMENT

General abandonment method(s) used (check where applicable):

- ☒ Pumping of grout through tremie pipe to fill inside of well screen and casing.
- ☐ Pressurized injection of grout into filter pack, screen and casing; pressure maintained until grout sets.

WELL ABANDONMENT - CONT'D

- _____ Cutting of casing and pressurized injection of grout into permeable zones; pressure maintained until grout sets.
- _____ Over-reaming of well casing and screen, pulling casing and screen from hole.
- _____ Milling out of casing and screen.
- _____ Drilling out well casing, screen and grout to original borehole diameter, removal of materials by flushing.
- _____ Pumping of grout through tremie pipe to fill borehole.
- _____ Other (describe) _____
- _____
- _____
- _____
- _____

Describe the actual method used to abandon this well. Grout pumped through 2 7/8" diameter drill rod from the bottom of casing. Grout was pumped until it returned to surface. Top of grout column was topped-off April 4 with neat cement. The grout pumped the previous day had only settled ~1 foot.

Footage actually abandoned (From/To) 0 / 169.

Abandonment problems or deviations from abandonment specifications _____

Note: Annulus grouted after curve was installed using a grout shoe and pressure-pumped.

Grout mix used One (1) 94-lb sack of Type I Cement to seven (7) gallons of water to 4 lbs of bentonite powder powder (~4% by weight)

GROUT PUMPED:

Number of Cubic Yards	Weight as Pumped	Date Pumped
135 yds ³	13-14 lbs/gal	4 / 3 / 91
		1 / 1
		1 / 1

SITE CLEANUP

Disposal of well pad, posts and other materials N/A

Disposal of well screen(s) and casing N/A

Disposal of drilling mud N/A

Disposal of excess grout N/A

Date site cleanup completed 4 / 4 / 91

Site inspected by Charles Budinger Date 4 / 4 / 91

Report prepared by Charles Budinger Date 4 / 4 / 91

Data accuracy verified by Charles Budinger Date 4 / 16 / 91

WELL ABANDONMENT COMMENTS

Top of steel conductor pipe well head welded shut (after topped-off with grout) with metal plate.

SRS WELL ABANDONMENT REPORT

GENERAL INFORMATION

Well number AMH-4C^{5th} attempt^{cap} Location M-Area Basin
Project name Horizontal Well
Custodian Horace Bledsoe Custodial Dept. Environmental Science
SRS Coordinates: North 102,741.86 East 48,809.51
Or: Latitude 33-19-57.45 Longitude 81-44-16.41
Location description North of M-Area Settling Basin
County Aiken
Installation contractor Eastman-Christiansen Date installed 5 / 4 / 91
Abandonment contractor Eastman-Christiansen Driller Roy Jones / J. Smith
Oversight contractor Sirrine Oversight C. Travis
Well abandonment: Date started 5 / 5 / 91 Date completed 5 / 6 / 91

WELL DATA FILE REVIEW

Note: Depths are measured from ground surface to the nearest 0.1 ft.

Height of well seal or top of well casing above ground surface 0.0 ft.

Depth of well below ground surface (from data file) _____

Measured depth from ground surface to bottom of well 165 ft. (curved section) 177 ft. (later)

Depth from ground surface to static water level ~120 ft.

Total drilled depth of borehole 165 ft. 346 ft. Diameter (in.) 12

Ground surface elevation (mean sea level) 362.60 ft.

Reason for well abandonment Drill rods became sand locked in the hole and casing separated at factory weld when pulling out drill rods and casing.

Known problems with well materials or construction N/A

WELL CASING:

Type of Material	Schedule or Thickness	Nominal I. D. (in.)	Type Joint	From (ft.)	To (ft.)
HDPE	1/2 in.	10 in.	push	0	148 347

WELL SCREEN(S):

Type of Material	Nominal I. D. (in.)	Slot Type	Type Size (in.)	From (ft.)	To (ft.)
N/A HDPE	6 in.	machine slotted	0.020	169	347

WELL SUMP AND SUMP CAP:

Type of Material	Schedule or Thickness	Nominal I. D. (in.)	Type Joint	From (ft.)	To (ft.)
N/A	N/A	N/A	N/A	N/A	N/A

Type of sump cap installed N/A Length (ft.) N/A
 Depth from ground surface to bottom of sump cap N/A

ANNULAR GROUT:

Type of Grout	Annular Thickness (in.)	From (ft.)	To (ft.)
Portland Type I	1-2 in.	0	80

WELL SEAL:

Type of Seal	From (ft.)	To (ft.)
N/A	N/A	N/A

FILTER PACK:

Average Grain Size (mm)	From (ft.)	To (ft.)
<u>N/A</u>	<u>N/A</u>	<u>N/A</u>

GEOPHYSICAL LOGGING

Geophysical logs performed during well construction N/A

Geophysical logging subcontractor N/A

Geophysical logs performed during well abandonment N/A

Date logged — / — / —

Geophysical logging subcontractor N/A

Logging truck operator N/A Oversight N/A

Geophysical logging comments N/A

WELL ABANDONMENT

General abandonment method(s) used (check where applicable):

☐ Pumping of grout through tremie pipe to fill inside of well screen and casing.

☐ Pressurized injection of grout into filter pack, screen and casing; pressure maintained until grout sets.

WELL ABANDONMENT - CONT'D

- ☒ Cutting of casing and pressurized injection of grout into permeable zones; pressure maintained until grout sets.
- ☐ Over-reaming of well casing and screen, pulling casing and screen from hole.
- ☐ Milling out of casing and screen.
- ☐ Drilling out well casing, screen and grout to original borehole diameter, removal of materials by flushing.
- ☐ Pumping of grout through tremie pipe to fill borehole.
- ☐ Other (describe) _____
- _____
- _____
- _____
- _____

Describe the actual method used to abandon this well Grout pumped through 2 7/8" diameter drill rod to the well bottom at ~80' below land surface. Grout observed reaching surface. Grout allowed to properly set up.

Footage actually abandoned (From/To) 80' to 0'

Abandonment problems or deviations from abandonment specifications N/A

Grout mix used 4% bentonite, 2% CaCl mixed with 94 lb.
bags of Type I cement

GROUT PUMPED:

Number of Cubic Yards	Weight as Pumped	Date Pumped
<u>20</u>	<u>13-15 lbs/gal</u>	<u>5 / 6 / 91</u>
		<u>1 / 1</u>
		<u>1 / 1</u>

SITE CLEANUP

Disposal of well pad, posts and other materials N/A

Disposal of well screen(s) and casing Left on site for inspection.

Disposal of drilling mud N/A

Disposal of excess grout Grout lines and tanks flushed with
fresh water and allowed to run off adjacent to drill rig.

Date site cleanup completed 5 / 7 / 91

Site inspected by J. Terry Date 5 / 7 / 91

Report prepared by _____ Date 1 / 1

Data accuracy verified by C. Budinger Date 1 / 1

WELL ABANDONMENT COMMENTS

This abandonment was completed for a second attempt to install the
lateral section of the well from the same conductor and curved section.
The first borehole lateral was temporarily abandoned with 150 sec viscosity
mud. The first lateral was not injected with grout prior to beginning
the second lateral attempt.

SRS WELL ABANDONMENT REPORT

GENERAL INFORMATION

Well number AMH-4(7th attempt)^{6th} Location M-Area Basin^{cub}
 Project name Horizontal Well
 Custodian Horace Bledsoe Custodial Dept. Environmental Science
 SRS Coordinates: North 102,664.39 East 48,778.24
 Or: Latitude 33-19-56.65 Longitude 81-44-16.16
 Location description North of M-Area Settling Basin
 County Aiken
 Installation contractor Eastman-Christiansen Date installed 5/10/91
 Abandonment contractor Eastman-Christiansen Driller Joe Boyd
 Oversight contractor Sirrinc Oversight C. Budinger
 Well abandonment: Date started 5/10/91 Date completed 5/10/91

WELL DATA FILE REVIEW

Note: Depths are measured from ground surface to the nearest 0.1 ft.

Height of well seal or top of well casing above ground surface 0.0 ft.

Depth of well below ground surface (from data file) 101.8 ft. (true vertical depth)

Measured depth from ground surface to bottom of well 148 ft. (curved sections)

Depth from ground surface to static water level ~120 ft.

Total drilled depth of borehole 148 ft. Diameter (in.) 12
~~250 ft. cub~~

Ground surface elevation (mean sea level) _____

Reason for well abandonment Incorrect borehole angle and total vertical depth (TVD) was too low to continue in vadose zone.

Known problems with well materials or construction N/A N/A

Only lateral section of borehole was abandoned.

Borehole drilled without casing, therefore no information available for well casing / well screens section.

WELL CASING:

Type of Material	Schedule or Thickness	Nominal I. D. (in.)	Type Joint	From (ft.)	To (ft.)
HDPE	1/2 in.	10	Push		133

WELL SCREEN(S):

Type of Material	Nominal I. D. (in.)	Slot Type	Type Size (in.)	From (ft.)	To (ft.)
N/A	N/A	N/A	N/A	N/A	N/A

WELL SUMP AND SUMP CAP:

Type of Material	Schedule or Thickness	Nominal I. D. (in.)	Type Joint	From (ft.)	To (ft.)
N/A	N/A	N/A	N/A	N/A	N/A

Type of sump cap installed N/A Length (ft.) N/A
 Depth from ground surface to bottom of sump cap N/A

ANNULAR GROUT:

Type of Grout	Annular Thickness (in.)	From (ft.)	To (ft.)
N/A	N/A	N/A	N/A

WELL SEAL:

Type of Seal	From (ft.)	To (ft.)
Portland Type I	148	230

FILTER PACK:

Average Grain Size (mm)	From (ft.)	To (ft.)
<u>N/A</u>	<u>N/A</u>	<u>N/A</u>

GEOPHYSICAL LOGGING

Geophysical logs performed during well construction N/A

Geophysical logging subcontractor N/A

Geophysical logs performed during well abandonment N/A

Date logged - / - / -

Geophysical logging subcontractor N/A

Logging truck operator N/A Oversight N/A

Geophysical logging comments N/A

WELL ABANDONMENT

General abandonment method(s) used (check where applicable):

☐ Pumping of grout through tremie pipe to fill inside of well screen and casing.

☐ Pressurized injection of grout into filter pack, screen and casing; pressure maintained until grout sets.

WELL ABANDONMENT - CONT'D

- _____ Cutting of casing and pressurized injection of grout into permeable zones; pressure maintained until grout sets.
- _____ Over-reaming of well casing and screen, pulling casing and screen from hole.
- _____ Milling out of casing and screen.
- _____ Drilling out well casing, screen and grout to original borehole diameter, removal of materials by flushing.
- _____ Pumping of grout through tremie pipe to fill borehole.
- ✓ _____ Other (describe) Placed cement plug from 148 feet to 230 feet

Describe the actual method used to abandon this well The well was abandoned by pumping grout via 2 7/8" tremie forming plug desired from 148-230 feet below surface.

Footage actually abandoned (From/To) 230' - 148'

Abandonment problems or deviations from abandonment specifications N/A

Grout mix used Type I cement mixed with 2-4% CaCl to add strength.

GROUT PUMPED:

Number of Cubic Yards	Weight as Pumped	Date Pumped
<u>15</u>	<u>13-15 lbs/gal</u>	<u>5 110 191</u>
		<u>1 1</u>
		<u>1 1</u>

SITE CLEANUP

Disposal of well pad, posts and other materials N/A

Disposal of well screen(s) and casing N/A

Disposal of drilling mud N/A

Disposal of excess grout Grout tank and lines flushed with fresh water, excess allowed to run off on ground adjacent to drill rig.

Date site cleanup completed 5 112 191

Site inspected by C. Travis Date 5 112 191

Report prepared by _____ Date 1 1

Data accuracy verified by C. Budinger Date 1 1

WELL ABANDONMENT COMMENTS

Hole was plugged to allow for drilling above zone.
Attempt #8 will be drilled horizontally above plug.

END

**DATE
FILMED**

5 / 4 / 93