199

8-31-78

MASTER

MASTER

UCRL-52445

LH. 423

MARVEL REVISITED: EXPERIMENT DESIGN AND DATA ANALYSIS

J. M. Thomsen

February 28, 1978

Work performed under the auspices of the U.S. Department of
Energy by the UCLLL under contract number W-7405-ENG-48.

LAWRENCE
LIVERMORE
LABORATORY
University of California / Livermore

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

LAWRENCE LIVERMORE LABORATORY
University of California, Livermore, California 94550

NOTICE
This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Department of Energy, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights.

UCRL-52445

MARVEL REVISITED: EXPERIMENT DESIGN AND DATA ANALYSIS

J. M. Thomsen

MS. date: February 28, 1978

NOTICE MN ONLY

**PORTIONS OF THIS REPORT ARE ILLEGIBLE. It
has been reproduced from the best available
copy to permit the broadest possible avail-
ability.**

CONTENTS

Abstract	1
Introduction	1
Emplacement Geometry	3
General Emplacement	3
Zero Room	10
Instrumentation	10
Overview	10
SLIFER Cables	11
Side Shock Tubes	11
Tourmaline TOA Gages	13
Stress Gages	26
Cavity-Pressure Measurement System	28
Results of Experiment	29
Shock TOA along Tunnel	29
SLIFER Data	31
Side-Shock-Tube Data	32
Tourmaline-Crystal TOA Data	32
Shock TOA off Tunnel	32
SLIFER Data	34
Stress-Gage Data	34
Cavity-Pressure-Experiment Data	34
Free-Field TOA	35
Data Analysis and Comparison of TOA Results along the Tunnel	35
Method for Time-Correcting MARVEL Data	36
Comparison of Corrected Data	37
Derivation of Shock Velocity and Peak Pressure vs Range in MARVEL Tunnel	40
Summary and Conclusions	43
Acknowledgments	44
References	45
Appendix	46

MARVEL REVISITED: EXPERIMENT DESIGN AND DATA ANALYSIS

ABSTRACT

As part of the research performed for the Defense Nuclear Agency program defining the in-trench environment for the MX missile system, the nuclear data base was reviewed to determine if any of it was applicable to the problem of air-shock attenuations in long, shallowly-buried tubes. Because of its unique shock-tube geometry, the LLL MARVEL event, fired in 1967, was judged one of the few relevant nuclear events.

This report describes the MARVEL event, including emplacement geometry and emplacement of instrumentation to measure shock time-of-arrival (TOA) in the shock tube. TOA data from the event, including uncertainties, are discussed and analyzed. Finally, using shock-tube theory, the flow parameters D (shock-tube velocity) and P (peak pressure in the air behind the shock front) are derived from a fit to the MARVEL TOA data. The data derived from those parameters are consistent.

INTRODUCTION

The Earth Sciences (K) Division of Lawrence Livermore Laboratory (LLL) has been supporting the efforts of the Defense Nuclear Agency (DNA) to define precisely the in-trench environment of the MX missile system. Part of LLL's effort included examining its nuclear data base and making available data from past nuclear experiments that may be relevant to the definition of in-trench environment.

This year efforts have concentrated on a particular previous LLL event, MARVEL. This event was detonated on September 21, 1967, in Yucca Flat of the Nevada Test Site (NTS) in drill hole U10ds at a depth of burial (DOB) of 176 m. The measured nuclear yield was 2.2 kt.

A large portion of the DNA program defining the in-trench environment is concerned with air-shock attenuation in large-diameter (~4 m) concrete tubes, buried at a shallow depth (~2 m). Although it was not specifically designed to answer pressing MX questions, the MARVEL experiment did yield some data relevant to the part of the program concerned with air-shock attenuation. The MARVEL experiment consisted of a long horizontal shaft, in which a 122-m long, 0.99-m (39-in.) i.d. Transite line-of-sight (LOS) pipe was emplaced. This LOS pipe was air-filled and connected directly to the device zero room. Diagnostics designed to measure initial radiation, shock propagation, radioactivity,

and cavity pressure were emplaced along the LOS pipe in four alcoves, and in an alcove at the end of the LOS. The MARVEL event geometry is shown in Fig. 1; this figure is taken from a previously published report by Crowley, Glenn, and Marks.¹

The specific purpose of MARVEL was to obtain data on the flow of energy and device debris through the tunnel. Thus, it was a test of the Project Plowshare "get lost" concept, as applied to nuclear cratering. To reduce the amount of nuclear products released on a nuclear cratering event, it was proposed that the emplacement hole beneath the nuclear device be left unstemmed, so that the device debris would be channeled down this open hole and trapped there. MARVEL, however, was not a cratering experiment, and the "get lost" hole was the horizontal shaft. The diagnostics along the tunnel were designed to obtain information concerning the TOA of the shock through the tunnel, the amount of channeled energy, and the fraction of channeled device debris.

Various aspects of MARVEL have been published previously¹⁻⁴; these include most of the experimental data and at least a cursory description of experiment emplacement and technique. These reports are referenced herein, on the assumption that the reader has access to them. Many of the experiment design and emplacement details, however, come from previously unpublished LLL event files,

Fig. 1. The MARVEL event.

and are reported here for the first time. We hope that by combining the experiment design, emplacement, and results with some new analysis, we can

determine the uncertainties inherent in the MARVEL data. The experiment data can then be used with increased confidence.

EMPLACEMENT GEOMETRY

MARVEL was emplaced in hole U10ds at the NTS of the U.S. Atomic Energy Commission (AEC).^{*} Figure 2 shows the exact location in Area 10, which is in the northern part of Yucca Flat. A discussion of the general details of construction and emplacement, including the zero room and tunnel geometry, follows.

General Emplacement

The MARVEL site, seen from the air, is shown in Fig. 3. With a view to the north, Fig. 3(a) shows the ground-zero area during the emplacement operation. In the background is the crater lip of SEDAN, a Plowshare cratering experiment. Figure 3(b) is a closeup of the ground-zero area. The rig is directly over the access shaft, U10ds; the horizontal drift in which the tunnel was emplaced extends to the right.

In addition to the access shaft, 10 other vertical holes were drilled preshot. The location of each hole is shown in Fig. 4. The drift was mined due west of the access hole, and cable holes were drilled at the end of each of the four alcoves and at the end of the tunnel; two exploratory holes and a free-field instrumentation hole were also drilled very close to the access hole. The purpose of each of these 10 holes and its distance from the access hole is summarized in Table 1.

After the drift and alcoves were mined, a concrete pad was poured along the tunnel to facilitate emplacement of the 0.99-m (39-in.) i.d., 1.07-m (42-in.) o.d. Transite pipe sections. To facilitate emplacement of the chemical-tracer sections, 6.1-m (20-ft) gaps in this concrete pad were left at five places along the tunnel. These sections had a larger o.d. than the Transite pipe sections and were constructed in place. Figure 5 shows the view down the drift prior to instrumentation emplacement.

After emplacement of instrumentation, the four alcoves along the tunnel were grouted. The grout was designed by the Concrete Laboratory of the U.S. Army Engineer Waterways Experiment Station, Vicksburg, MS, to match the properties of the alluvium found at the MARVEL site. The con-

stituents and properties of the grout are summarized in Table 2. Figure 6 shows views inside one of the alcoves during the grouting operation. The alcove at the tunnel end was not grouted, but filled with sandbags before emplacement of the Transite pipe. Figure 7 shows Alcove 5 after it was backfilled.

Next, the Transite pipe sections were installed along the drift, as shown in Fig. 3.^{*} The space between each section was filled with a waterproof epoxy sealant. Space provided for each chemical-tracer section remained unfilled to permit construction. Figure 9 shows the inside of the tunnel after completion.

Following installation of the Transite pipe, the entire drift and the accompanying cable holes were partly grouted and stemmed with sand, as shown in Fig. 10. The zero room was then furnished with the equipment, the region around it was backfilled with sand bags, and the access hole (U10ds) was backfilled with NTS sand. The MARVEL event was ready for execution.

^{*}The emplacement of the Transite pipe sections is discussed in Ref. 2.

Table 1. Distance of MARVEL drill holes from U10ds and purpose of each hole.

Hole	Surface distance from: U10ds, m	Purpose
U10ds	0	Emplacement hole
U10ds-1	20	Exploratory hole
U10ds-2e	15	Exploratory hole
U10ds-6	8	Free-field instrument hole
U10ds-1A	31	Alcove 1 cable hole
U10ds-2	61	Alcove 2 cable hole
U10ds-3	81	Alcove 3 cable hole
U10ds-4	100	Alcove 4 cable hole
U10ds-5	126	Alcove 5 (end of tunnel) cable hole
U10ds-8	125	Reaction history cable hole
U10ds-VH	5	Vent hole

^{*}NTS is now part of the U.S. Department of Energy.

Fig. 2. Location of the MARVEL event at the Nevada Test Site.

Fig. 3. Ground-zero area of MARVEL event. (a) Looking north, with crater lip of SEDAN in background. (b) Closeup, with shock tube drift extending to right.

Fig. 4. Location of MARVEL preshot drill holes

Fig. 5. View down the MARVEL drift showing concrete pad. Area in foreground has been left open for emplacement of a chemical-tracer section.

(a)

(b)

Fig. 6. Grouting the alcoves along the tunnel. (a) In the early stage, grout just covers the floor of the alcove. (b) In the later stage, grout covers most of the instrumentation.

Table 2. Constituents and properties of MARVEL alluvium-matching grout.

Constituents		Properties		
Materials required, lb./ft. ³		Age, d	Compressive strength, MPa (psi)	Velocity, m/s (ft/s)
Type III cement	20.0	3	1.0 (150)	1155 (3790)
Fly ash	36.2	7	1.5 (220)	1445 (4740)
Gel	4.5	14	1.9 (275)	1612 (5290)
Water	39.4			
Aluminum powder	0.009			
	100.1 ^a			

^aActual unit weight expected was 91 ± 2 lb.

Fig. 7. View of Alcove 5 (tunnel end) showing sandbag backfill.

Fig. 8. Emplacement of Transite pipe sections.

Fig. 9. View inside the Transite pipe (0.99 m i.d.) after emplacement. Sections of the form for the chemical-tracer section have been left temporarily as a pathway.

Fig. 10. MARVEL drill-hole and drift-stemming plan.

Zero Room

The MARVEL zero room was a cylindrical steel tank 1.05 m (3.4 ft) in diameter and 1.5 m (5.0 ft) long. The nuclear source was placed at the approximate center of the room, and the remaining volume inside the tank was filled with material having a density of 0.9 Mg/m^3 . Thin sheets of lead were placed at each end of the tank. Figure 11 is a generalized schematic of the zero room.

A detailed drawing of the zero room, actually more complicated than described here, will be included in (the classified) part of this report.⁵ Calculations showed that the details of the zero room did not appear to affect the tunnel flow significantly, therefore Fig. 11 is adequate for the analysis presented in this report.

Fig. 11. Generalized sketch of MARVEL zero room.

INSTRUMENTATION

Overview

The emplacement of the MARVEL instrumentation related to shock TOA is listed and briefly described and discussed in detail later. This instrumentation included the following:

1. *SLIFER Cables*—SLIFER, an acronym for "Shorted Location Indicator by Frequency of Electrical Resonance," is a method for continuously measuring the position of a shock front involving an oscillator and a shorted coaxial cable.⁶ As the cable is crushed by the shock, the cable inductance, and thus the oscillator frequency, changes. The oscillator frequency is recorded as a function of time and converted to uncrushed cable length vs time. This is directly related to shock-front position vs time, if the initial length and position of the cable are known.

On MARVEL, seven SLIFER cables, located immediately outside the Transite pipe, measured the position of the shock front inside the tunnel as a function of time. Two additional cables were emplaced in the vertical instrument hole, U10ds-6, to measure the free-field shock arrival in the alluvium.

2. *Side Shock Tubes*—In each of the four alcoves perpendicular to the tunnel, a small-diameter shock tube was positioned so that it looked directly into the main tunnel. The side shock tubes measured, more directly than the SLIFER cables, the position of the shock

front inside the tunnel at four discrete positions. Light pipes were emplaced along the length of each side shock tube, to measure the exact position of the shock. This data was then plotted and, by extrapolation, we could determine the TOA of the shock in the main tunnel. A thorough discussion of the design and purpose of the side shock appears in Ref. 2.

3. *Tourmaline TOA Gages*—Off-the-shelf tourmaline-crystal stress gages were used to check the performance of the side shock tubes at two of their four locations. These gages measured shock TOA only. The gages were strapped to the side shock tubes on the working-point (WP) side, directly against the Transite pipe. Thus, for direct comparison with the side shock tube data, we had to allow for the shock transit time through the Transite pipe.
4. *Stress Gages*—Tourmaline stress gages also measured stress waveforms in the alcoves and in the instrument hole. In the alcoves, the gages were oriented to observe either the radial shock wave off the tunnel or the free-field wave from the WP. In the instrument hole, the gages were oriented to observe the free-field wave from the WP.

Although 19 such gages were fielded, data from these gages, except tabular TOA and peak stress, is sparse because the original stress waveforms are no longer available.

5. *Cavity-Pressure Gages*—One attempt was made to measure late-time cavity pressure at the far end of the MARVEL tunnel. Three pressure gages were located in a gage assembly close to the tunnel, and a surplus U.S. Navy gun barrel protected the cables from the ground motion.

Figure 12¹ schematically shows the location of some of the MARVEL shock TOA instrumentation discussed above. The measurements from each type of instrumentation will be discussed in the next section.

SLIFER Cables

Seven SLIFER cables were emplaced along the MARVEL drift to measure shock TOA through the tunnel. In addition, two SLIFER cables were emplaced in a vertical instrument hole, U10ds-6, centered on the pipe 9.14 m from the WP (see Appendix). These were grouted in place to measure free-field shock TOA.

All cables were 1/4-inch foam heliax, wrapped with lead tape to reduce radiation interference. The 2-Mc oscillators were all located downhole. The cables from the oscillators were brought to the surface through the vertical cable holes located at the end of each alcove.

All SLIFER cables were emplaced along the tunnel on the concrete floor in a prepared groove. This geometry is shown in Fig. 13, and is detailed in the appendix. From this figure and the wall thickness of the Transit pipe (41.3 mm), the calculated approximate closest distance from the SLIFER cable to the inside of the Transit pipe is 52 mm. The cables were routed from the grooves close to their ends in order to attach the oscillators. The oscillators were located either along the tunnel or in the alcoves. This geometry is shown in Fig. 14. More detailed information on the tunnel SLIFER emplacement is given on the engineering drawing in the appendix. Because the chemical-tracer pipe sections were significantly wider than the Transit pipe sections, they interfered with the typical SLIFER emplacement. In such instances, the cables were emplaced in wood trays on the concrete tunnel floor as close to the pipe as possible. In all cases, however, the distance from the SLIFER to the inside of the tunnel was greater than for the typical prepared-groove emplacement. Figure 14 also shows the location of these tracer sections.

All SLIFER systems were emplaced and grouted prior to emplacement of the Transit pipe. Figures 15-22 show a typical SLIFER oscillator

assembly and an oscillator and cable emplacement for each of the tunnel SLIFER cables (H1M-H7M). The SLIFER systems were carefully emplaced so that the cable would be stationary during the subsequent Transit pipe emplacement or tunnel grouting operations.

Side Shock Tubes

To measure the TOA of the air shock inside the Transit pipe, small-diameter shock tubes were mounted perpendicular to the main tunnel. One side shock tube was emplaced in each of the four MARVEL experiment alcoves before the transit pipe sections were emplaced. After the Transit pipe was in place and both the experiment alcoves and the tunnel were grouted, holes were drilled through the Transit pipe to expose each shock tube directly to the tunnel environment. The emplacement of the diagnostics associated with the side shock tubes are discussed in this section; the experimental technique is reviewed more thoroughly in Ref. 2.

The side shock tubes were steel cylindrical pipes, with a 50.8-mm i.d., a 152.4-mm o.d., and a 3.20-m length. Ten light pipes (fiber optics), spaced at 0.305-m intervals along the tube, monitored the propagation of the air shock inside the shock tube. The end of each light pipe was recessed 3.2 mm in the steel wall; a small opening (3.2-mm i.d.) allowed the light pipe to view the inside of the shock tube directly. The light pipes were alternately fed into one of two photodetectors, as shown in Fig. 23.²

At the center of the tube, two light pipes were mounted, each feeding into a different photodetector. Such placement provided redundancy at this position. The signal from the photodetector was split. One signal from each went to one of two oscilloscopes; the other signal from each detector was fed to another oscilloscope with a different sweep time.

The ranges of the side shock tubes from the WP and from the lead diaphragm are given in Table 3. These ranges differ from those reported by Glenn

Table 3. Ranges of side shock tubes from the WP and from the lead diaphragm.

Side shock tube in alcove	Range from WP, m	Range from lead diaphragm, m
1	28.90	28.15
2	59.05	58.30
3	80.47	79.72
4	98.53	97.78

Fig. 12. Location of MARVEL shock TOA instrumentation.

Fig. 13. Tunnel cross section showing (a) the typical view and (b) a dimensional drawing of concrete pad for the Transite pipe and SLIFER cables.

and Crowley²; however, the latter agree with the ranges given on the appropriate engineering drawing in the appendix. The reason for the discrepancy is an arithmetic error on the engineering drawing, which gives dimension G as the distance from the center of the side shock tube to the WP. Dimension H is given as the center-to-center distance between

the side shock tubes and the ion gages. Dimension G is correct for Alcove 1, which did not contain an ion gage, but dimension G for Alcoves 2, 3, and 4 is the distance from the center of the ion gage to the WP. For those alcoves, therefore, the distance from the center of the side shock tube to the WP is G minus H; this figure is listed in Table 3.

The above calculation can be substantiated by combining the SLIFER cable survey with photographs of the as-built configuration taken in each alcove. Figures 24-27 show views of the shock tubes in each of the four alcoves. All show that the SLIFER oscillators (emplaced and surveyed *before* emplacement of the side shock tubes) located in the alcoves were further from the WP than the side shock tubes were. In fact, except for Alcove 1, the side shock tubes were located very close to the position where the SLIFER cable left its prepared groove and bent into the alcove. If dimension G on the engineering drawing were correct, the shock tubes would be located further from the WP than the SLIFER oscillators. The error was propagated into Glenn and Crowley's paper,² so that the TOA data plotted there are incorrect by ~ 2 m.

After grouting the alcoves and emplacing and grouting the Transite pipe sections, we cut holes in the Transite pipe wall to expose the side shock tubes directly to the tunnel. Figure 28 shows the typical final emplacement from inside the tunnel.

Tourmaline TOA Gages

To check the operation of the side shock tubes, tourmaline TOA gages were installed in Alcoves 1 and 3. These gages measured TOA only, as discussed in Ref. 2. Figure 29 schematically shows the emplacement of these gages. The tourmaline crystal was potted in epoxy and surrounded on three sides by lead. Between the face of the crystal and the inside of the Transite pipe were 0.54 mm (1/8 in.) lead and 38.1 mm (1-1/2 in.) polyurethane foam, in addition to the 41.3-mm (1.63-in.) Transite pipe wall itself. The total distance was 80 mm.* The units were strapped to the WP side shock tubes.

The center-to-center distance between the side shock tube and the gage was 0.15 m. Hence, the ranges from the WP to the tourmaline gages in Alcoves 1 and 3 were 28.75 m and 80.32 m, respectively. Some photographs of the tourmaline gage emplacement appear in Fig. 30.

*This was further away than the SLIFER cables (52 mm).

Fig. 14. Pictorial summary of location of MARVEL side shock tube, SLIFER, and chemical-tracer sections.

Fig. 15. Typical emplacement of SLIFER oscillator showing (a) disassembled oscillator, (b) oscillator in lead box, (c) oscillator sieved with lead shot, and (d) final assembly.

Fig. 16. SLIFER H1M emplacement. (a) SLIFER H1M in prepared groove with oscillator in foreground. Tunnel floor was left uncemented for later emplacement of first chemical-tracer section (20 m from WP). (b) Beginning of SLIFER H1M in prepared groove prior to grouting (8.9 m from WP).

Fig. 17. SLIFER H2M emplacement. (a) SLIFER H2M oscillator, located in Alcove 1, looking towards back of alcove (30 m from WP). (b) SLIFER cable H2M after grouting as it bends from the tunnel into Alcove 1. In the background is the beginning of SLIFER H3M (29 m from WP).

(a)

(b)

Fig. 18. SLIFER H3M emplacement. (a) SLIFER H3M grouted in wood tray around area left open for emplacement of second chemical-tracer section (39 m from WP). (b) SLIFER oscillator H3M along tunnel (43 m from WP).

(a)

(b)

(c)

Fig. 19. SLIFER H4M emplacement. (a) SLIFER oscillator H4M, located in Alcove 2, looking towards back of alcove (60 m from WP). (b) SLIFER cable H4M in prepared groove prior to grouting. Side shock tube is in foreground (61 m from WP). (c) SLIFER cable H4M where it enters Alcove 2 after grouting (60 m from WP).

(a)

(b)

(c)

Fig. 20. SLIFER H5M emplacement. (a) SLIFER oscillator H5M, located in Alcove 3, looking towards back of alcove (81 m from WP). (b) SLIFER cable H5M after grouting as it bends into Alcove 3. Side shock tube is in background (81 m from WP). (c) Beginning of SLIFER cable H5M after grouting. Area left open for emplacement of fourth chemical-tracer section is in background (72 m from WP).

Fig. 21. SLIFER H6M emplacement. (a) SLIFER oscillator H6M located in Alcove 4 (99 m from WP). (b) Beginning of cable H6M in prepared groove prior to grouting (89 m from WP). (c) SLIFER cable H6M along tunnel after grouting. Side shock tube is in background (100 m from WP).

Fig. 22. SLIFER H7M emplacement. (a) SLIFER oscillator H7M along tunnel. Area in foreground is left open for emplacement of fifth chemical-tracer section (119 m from WP). (b) SLIFER cable H7M grouted in wood tray as it bypasses chemical-tracer emplacement section.

Fig. 23. Technique employing shock tube, light pipe, and photodetector to determine air shock TOA in main tunnel.

(a)

(b)

Fig. 24. Side shock tube in Alcove 1. (a) Looking back into alcove, WP is to the right. Three stress gages and SLIFER H2M are to the left (24.1 m from WP). (b) Side view showing light pipes and photodetectors (31 m from WP).

Fig. 25. Side shock tube in Alcove 2. (a) Side view showing tight pipes and photodetectors (60 m from WP). (b) Looking towards tunnel. Note position of SLIFER cable and oscillator H4M (60 m from WP). (c) Looking towards back of alcove. Note position of SLIFER cable and oscillator (60 m from WP).

(a)

(b)

Fig. 26. Side shock tube in Alcove 3. (a) Side view, looking towards WP, showing light pipes and photodetectors (81 m from WP). (b) End view looking towards tunnel. SLIFER cable and oscillator HSM are to the right (85 m from WP).

Fig. 27. Side shock tube in Alcove 4, looking towards WP, showing light pipes and photodetectors (100 m from WP).

Fig. 28. Entrance to pipe for the side shock tube in Alcove 3, seen from inside grouted Transite pipe.

Fig. 29. Shielding and geometry of tourmaline-crystal pressure gages mounted in Alcoves 1 and 3.

Fig. 30. Tourmaline-crystal gage emplacement in Alcove 1 (a) before strapping to side shock tube and (b) final position. The plywood served as a dam during grouting.

Stress Gages

For MARVEL, 19 tourmaline stress gages were emplaced to measure the shot-induced ground motion and the response of the grout in the tunnel and alcoves to the shock in the tunnel. Three gages were emplaced in each of the four grout-filled alcoves; two were perpendicular to the tunnel to measure the strength of the radial shock resulting from flow

through the tunnel, and the third was parallel to the tunnel to measure ground motion. Three gages, surrounded by sandbags, were located at the end of and parallel to the tunnel to measure the response at the tunnel end to the flow inside. Finally, four gages were placed in MARVEL instrument hole 6: two at 11.5 m and two at 30.2 m from the WP. Table 4 summarizes the location and orientation of all stress gages; more detailed information appears in the appendix.

Cables from the gages were brought to the surface through the cable holes at the end of each alcove and the tunnel end and at instrument hole 6. The 19-mm diam, 3.2-mm-thick piezoelectric crystals were emplaced in small, 76.2-mm o.d., 1.6-mm-thick-walled stainless steel cylindrical canisters. These canisters were then filled with the same type of grout used to stem the alcoves and tunnel drift along the pipe. This is shown in more detail in the appendix. The canisters were mounted in the alcoves on aluminum stands as shown in Fig. 31. This is a typical emplacement; note that the crystal face is located in front of the stand to minimize the shock-reflection effects of the stand. Figure 32 shows the typical emplacement (e.g., Alcove 3) for all three stress gages. The tunnel end was stemmed with sandbags, and the gage canisters were placed in the correct position on top of the sandbags and covered, as shown in Fig. 23. The distances of these gages from the end of the tunnel were ~2.6 m (CR 13), 4.5 m (CR 14), and 5.6 m (CR 15), respectively.

Fig. 31. Typical as-built configuration of stress gages in alcoves.

Table 4. Stress gage location and orientation.

Gage	Location	Orientation	Distance from tunnel centerline, m	Distance from WP, m
CR 1	Alcove 1	T ^a	0.98	29.56
2	Alcove 1	T	3.57	29.56
3	Alcove 1	WP ^b	6.01	29.35
4	Alcove 2	T	0.98	59.74
5	Alcove 2	T	3.57	59.74
6	Alcove 2	WP	6.01	59.52
7	Alcove 3	T	0.98	81.38
8	Alcove 3	T	3.57	81.38
9	Alcove 3	WP	6.01	81.16
10	Alcove 4	T	0.92	99.66
11	Alcove 4	T	3.57	99.66
12	Alcove 4	WP	6.01	99.45
13	End of tunnel	WP, T	0.23	124.63
14	End of tunnel	WP, T	0.23	126.46
15	End of tunnel	WP, T	0.23	127.60
16	Instrument hole 6	WP	7.01	115.2
17	Instrument hole 6	WP	7.01	11.52
18	Instrument hole 6	WP	28.79	30.21
19	Instrument hole 6	WP	28.79	30.21

^aTunnel.^bWorking point.

Fig. 32. As-built emplacement of three stress gages in Alcove 3, looking towards back of alcove. Two gages face tunnel; the third faces WP (to the right).

Fig. 33. Emplacement of stress gage canister CR 15 at end of tunnel showing (a) gage on top of sandbags, (b) face of gage covered, and (c) gage totally covered.

Cavity-Pressure Measurement System

In Alcove 4, a system was installed to measure late-time cavity pressure. Three pressure gages were mounted at the front of a surplus U.S. Navy gun barrel (used to protect the cables), and except for the pressure-transducer housing itself, the gages were exposed directly to the tunnel environment.

The cavity pressure system was located 100.6 m from the WP. Figure 34 is a photograph of the as-built system before Alcove 4 was grouted. The appropriate engineering drawing in the appendix shows more detail. The pressure transducers were located approximately 1.65 m from the inside wall of the tunnel. The access pipe was open from the tunnel wall to the steel transducer housing assembly (0.9 m). The caps at both ends and the lead bricks

Fig. 34. MARVEL cavity pressure system emplaced in Alcove 4.

inside the "grout form" tube against the tunnel wall were removed after grouting was completed.

The transducer assembly itself was located inside a thick-walled steel tube, which was fastened to the end of the gun barrel. The housing was 0.76 m long and 0.20 m in diam. A 0.21-m-long tube filled with Dow Corning No. 200 silicone oil traversed the housing diagonally. Three pressure transducers, a Norwood gage (100-kpsi rating), an LLL-designed coil gage (100-kpsi rating), and another Norwood gage (15-kpsi rating), were placed at the end of the oil-filled tube. The low-range Norwood gage was placed behind an orifice (4-msec oil-flow time constant) to protect it from initial high-shock pressures. The system was calibrated preshot at the LLL high-explosive test facility (Site 300),⁷ and again after in-

Fig. 35. Hole in Transite pipe exposing cavity pressure system to the tunnel.

stallation in Alcove 4, by statically pressurizing the system to 10,000 psi. The 100-kpsi LLL coil gage consistently read 30% higher than the 100-kpsi Norwood gage. The two Norwood gages, however, agreed.

After grouting was completed, a hole was cut in the appropriate section of the Transite pipe to expose the cavity pressure system to the tunnel environment. All covering plates and lead blocks were removed. Figure 35 views the opening in the Transite pipe from inside the tunnel.

The cavity-pressure experiment was "one-of-a-kind"; although attempts to use long-lasting instrumentation had been made on some Plowshare events, no instrumentation had been designed to survive as long as that of the MARVEL system.

RESULTS OF EXPERIMENT

Much shock TOA data was obtained from the gages and other instrumentation fielded on MARVEL. These data are reported for three distinct areas: (1) shock TOA along the tunnel, (2) shock TOA in the alcoves off the tunnel and in the alcove at the tunnel end, and (3) free-field shock TOA.

Shock TOA along Tunnel

The main results for shock TOA along the 122-m-long MARVEL tunnel came from the SLIFER cables, the side shock tubes, and the tourmaline TOA gages. Figure 36 shows these TOA data, with

Fig. 36. MARVEL event plot of experimental data along tunnel.

range measured from the WP and time measured from nuclear zero time; no corrections are applied to the data (e.g., to correct the SLIFER data for shock-transit time through the tunnel wall) in Fig. 36. These data are discussed in detail below.

SLIFER Data

SLIFER data were obtained from all seven cables (H1M to H7M) along the tunnel. The SLIFER records were not noisy, but contained blank spots resulting from strong, induced-current pulses that interfered with the oscillator, especially on the cables near the WP. On all cables, the frequency of any signal was easily read and the crushing was remarkably regular although the amplitude of the signal varied somewhat. No "irregular, "step-function" crushing (or shearing) of the cables occurred further from the WP.⁷ Figure 36 plots the SLIFER data and compares them with the other TOA data along the tunnel. The SLIFER data were digitized from the original data plot.⁸ Errors in plotting or reading the SLIFER data necessitated an uncertainty of ± 0.2 m in range and ± 10 μ s in time.

The digitized SLIFER data from each cable appear below, along with the valid range over which data could be collected on each cable. It should be noted that, although each cable was placed in a prepared groove along the tunnel, it was removed from that groove to be connected to the SLIFER oscillator or routed around a chemical-tracer section (see Fig. 14). Figure 36 shows the valid data range for each cable, as well as the location of each of the five chemical-tracer pipe sections.

1. SLIFER Cable H1M

Located in a prepared groove 0.052 m from the inside wall of the Transite pipe, positioned 8.9-19.5 m from the WP.

Range (m $\pm$ 0.2 m)	Time (μ s $\pm$ 10 μ s)
12.2	99
13.6	109
16.8	144
19.1	154

2. SLIFER Cable H2M

Located like cable H1M, positioned 23.7-29.4 m from the WP.

Range (m $\pm$ 0.2 m)	Time (μ s $\pm$ 10 μ s)
24.5	194
24.9	199
26.1	204
27.5	209
28.0	219
29.3	229

3. SLIFER Cable H3M

Located like cable H1M, positioned 30.5-37.8 m from the WP. Between 38.6-42.7 m, the cable was 0.26 m from the inside wall of the Transite pipe, to bypass a chemical-tracer LOS pipe section.

Range (m $\pm$ 0.2 m)	Time (μ s $\pm$ 10 μ s)
31.5	259
34.6	289
36.7	299
37.5	304
38.0	314
38.5	344
39.5	369
41.6	384

4. SLIFER Cable H4M

Located like cable H1M, positioned 48.8-58.6 m from the WP.

Range (m $\pm$ 0.2 m)	Time (μ s $\pm$ 10 μ s)
49.1	424
49.6	449
52.1	494
54.5	534
56.0	549
57.0	569

5. SLIFER Cable H5M

Located like cable H1M, positioned 71.3-80.2 m from the WP.

Range (m $\pm$ 0.2 m)	Time (μ s $\pm$ 10 μ s)
71.3	834
73.1	889
74.6	924
76.2	974
79.2	1049
79.8	1059

6. SLIFER Cable H6M

Located like cable H1M, positioned 88.4-98.7 m from the WP.

Range (m $\pm$ 0.2 m)	Time (μ s $\pm$ 10 μ s)
88.5	1374
89.1	1414
90.5	1489
92.4	1584
93.8	1639
94.9	1694
95.9	1774
96.2	1779
97.9	1879

7. SLIFER Cable H7M

Located like cable H1M, positioned 109.2-117.1 m from the WP. Between 117.8-119.2 m, the cable was

0.118 m from the inside wall of the Transit pipe; between 119.9-120.5 m, the cable was 0.148 m from the inside wall to bypass a chemical-tracer LOS pipe section.

Range (m ± 0.2 m)	Time $\mu\text{s} \pm 10 \mu\text{s}$
109.7	2634
110.0	2664
110.1	2694
111.0	2744
111.5	2794
112.4	2844
113.5	2979
114.8	3079
115.0	3099
116.1	3234
116.8	3259
117.9	3479
118.0	3489
118.1	3504
118.7	3579
119.9	3984
120.0	4004

Side-Shock-Tube Data

The side shock tubes, except the one located in Alcove 4, worked as planned. Data from all four appear in Fig. 37, with the time referenced to the TOA of the shock in the tunnel for each shock tube.⁹ The TOA of the shock in the tunnel, found by extrapolating the side-shock-tube data, appear in Table 5.

For each side shock tube, the uncertainty in the range from the WP is small, ± 0.02 m. We estimated the uncertainties in TOA's based on the data plotted in Fig. 37. In the side shock tube in Alcove 4, the

Fig. 37. Comparison of side shock tube data from Alcoves 1, 2, 3, and 4.

Table 5. Side-shock-tube TOA results.

Alcove No.	Range from WP	TOA
1	28.90 m ± 0.02 m	229.6 $\mu\text{s} \pm 5 \mu\text{s}$
2	59.05 m ± 0.02 m	556.9 $\mu\text{s} \pm 5 \mu\text{s}$
3	80.47 m ± 0.02 m	1012.8 $\mu\text{s} \pm 5 \mu\text{s}$
4	98.53 m ± 0.02 m	1819.7 $\mu\text{s} \pm 10 \mu\text{s}$

light intensity of the signal was not great enough to trigger the scopes for the first four light-pipe positions, so no signals were obtained. The signal at the fifth light-pipe position was intense enough because two light pipes were embedded there, thus reinforcing the signal enough to trigger the scope. Therefore, instead of extrapolating the side-shock-tube data a distance of 0.3 m (1 ft) as we did for Alcoves 1, 2, and 3, we had to extrapolate the data from Alcove 4 by 1.5 m (5 ft). Thus, the TOA uncertainty for the side shock tube in Alcove 4 is greater than for the data from the other alcoves.

Tourmaline-Crystal TOA Data

The tourmaline-crystal TOA gages strapped to the side shock tubes in Alcoves 1 and 3 gave good data. The uncertainty in both range (± 0.02 m) and time ($\pm 1 \mu\text{s}$) is small. The TOA data appear in Table 6.

Table 6. Tourmaline-crystal TOA results.

Alcove No.	Range from WP	TOA
1	28.7 m ± 0.02 m	224.1 $\mu\text{s} \pm 1 \mu\text{s}$
3	80.3 m ± 0.02 m	1088.4 $\mu\text{s} \pm 1 \mu\text{s}$

Shock TOA off Tunnel

Data on the cylindrically diverging shock wave propagating away from the tunnel wall came from two primary sources: the straight portion of the SLIFER cables and the stress gages oriented towards the tunnel wall. Shock TOA information was also obtained from the three transducers located in the cavity-pressure assembly in Alcove 4. This section summarizes the raw data from the above experiments. All pertinent data is summarized in Fig. 38.

Fig. 38. Summary of shock TOA data off the tunnel.

SLIFER Data

SLIFER data were obtained from the portions of the cables perpendicular to the main tunnel in each of the first four alcoves.⁸ The length of the straight section of cable varied from 3.95 m (13 ft) in Alcove 1 to 0.66 m (2.2 ft) in Alcove 4. These cables were H2M (Alcove 1), H4M (Alcove 2), H5M (Alcove 3), and H6M (Alcove 4). Initially, they paralleled the main tunnel along the main drift, and then bent 90° into their respective alcoves where they were connected to oscillators.

Figure 38 plots the data for each alcove; the dashed line drawn through the data is the experimenter's best fit.⁸ The data from Alcove 1 shows very regular crushing of the cable along its entire length, indicating a strong shock. The data are more erratic in Alcoves 2, 3, and 4, indicating a somewhat weaker shock, which would cause the SLIFER to crush irregularly.

Stress-Gage Data

Data from all 19 stress gages fielded on MARVEL are summarized in Table 7.⁴ Data recovery

was not as good as expected due to gage losses from bad cable connections, EM interference, or underestimation of the stress environment. All times in Table 6 are referenced to nuclear zero time.

Figure 38 plots both the relevant TOA data and the SLIFER data. In Alcoves 3 and 4, elastic precursors developed in the grout before arrival of the shock wave, so where possible, the TOA of the peak stress is also plotted. In general, agreement is good between the SLIFER and stress gage data close to the tunnel.

Cavity-Pressure-Experiment Data

We conducted a series of dynamic tests with the MARVEL cavity pressure system to verify the performance of the gages and the orifice systems. We hoped that the massive hardware would protect the electronics and signal cables through the shock wave, but the system failed at about 17 ms, presumably from ground motion which resulted in severed cables at the back of the alcove.

The 100-kpsi variable-reluctance pressure gage (LRL coil) went into "resonant saturation" with the

Table 7. Results of experiment as recorded on MARVEL stress gages.

Location	Gage No.	Orientation	Distance from tunnel centerline, m	Distance from WP, m	TOA, ms	Peak stress recorded, MPa (kb)
Alcove 1	1	T ^a	0.98	29.56	0.36	c
	2	T	3.57	29.56	1.69	c
	3	WP ^b	6.01	29.35	5.70	5.1 MPa (0.51)
Alcove 2	4	T	0.98	59.74	0.87	c
	5	T	3.57	59.74	d	d
	6	WP	6.01	59.52	d	d
Alcove 3	7	T	0.98	81.38	1.48	e
	8	T	3.57	81.38	2.91	14 MPa (0.14)
	9	WP	6.01	81.16	f	f
Alcove 4	10	T	0.98	99.66	2.02	175 MPa (1.75)
	11	T	3.57	99.66	2.88	6.5 MPa (0.065)
	12	WP	6.01	99.45	3.98	—
End of tunnel	13	WP, T	0.23	124.63	5.65	35 MPa (0.35)
	14	WP, T	0.23	126.46	e	e
	15	WP, T	0.23	127.60	6.95	55 MPa (0.55)
Instrument hole 6	16	WP	7.01	11.52	3.05	c
	17	WP	7.01	11.52	3.05	c
	18	WP	28.79	30.21	16.79	28.5 MPa (0.285)
	19	WP	28.79	30.21	16.79	32.5 MPa (0.325)

^aGage oriented towards tunnel.

^bGage oriented towards WP.

^cPeak stress exceeded gage limit (15 kbar).

^dGage lost, bad connection.

^eTransducer had low resistance.

^fSwamped by electromagnetic interference.

onset of pressure. The 100-kpsi bridge-type gage (Norwood) performed well and recorded a 2-ms-wide initial pressure pulse with an amplitude of 25 kpsi.¹⁰ The 15-kpsi Norwood gage was operational but gave little information because it was behind an orifice whose oil flow time constant was 4 ms. Table 8 summarizes the test results; the gage records of the test appear in Refs. 1 and 4.

Although two of the three pressure gages operated for 17 ms after the MARVEL detonation, the pressure signals were different from what we had expected. Stress gages in the alcove also indicated the initial pulse shown by the 100-kpsi pressure gage at the same time. This could indicate that the initial "pressure" pulse was due to a shock wave passing through the alcove, not gas pressure. However, the later (TOA = 8.15 ms) 15-kpsi-peak-amplitude signal may actually have been a gas-pressure signal from the tube. The early system failure, however, made it impossible to determine the long-range character of the latter signal.

Pressure-gage data, also plotted in Fig. 38, do not agree with the SLIFER and stress-gage data in Alcove 4 because the open section at the front of the system allowed the shock from the tunnel to reach these gages more quickly.

Free-Field TOA

The SLIFER cables and stress gages in the MARVEL instrument hole gave good results. Figure 39 summarizes these data. The stress-gage TOA and peak values from instrument hole 6 appear in Table 7.

The geometry of the cable causes an abrupt change in the slope of the SLIFER crush curve at about 2 ms. As shown by previously performed calculations, the change results from the convergence of the radial shock off the tunnel and the free-field shock. A complete discussion and analysis of the free-field TOA data appears in Ref. 1.

Table 8. Results of experiment as recorded on MARVEL cavity-pressure gages.

Gage	Principle	TOA, ms	Peak pressure, kbar	Maximum range, kbar
Norwood	Strain gage	2.10	1.70	6.8
		8.09	1.02	
LRL coil	Variable reluctance	2.18	Saturated	6.8
Norwood ^a	Strain gage	2.22	≈0	1.0

^aGage located behind orifice. Gage response time calculated to be 4 ms.

Fig. 39. MARVEL free-field data.

DATA ANALYSIS AND COMPARISON OF TOA RESULTS ALONG THE TUNNEL

The data reported in the preceding section can be used to determine a continuous shock TOA curve along the MARVEL tunnel (10-100 m). Four data points, i.e., the results obtained from the four side shock tubes, can be used directly in this analysis. Other data, e.g., data from the SLIFERS and tourmaline TOA gages, must be corrected to account for the shock-wave transit time through the Transite

pipe, grout, etc. Three procedural steps in the handling of the data to be adjusted are discussed below: (1) finding the time corrections for the data, (2) comparing all data by alcove and preparing a summary TOA plot, (3) making a "best fit" to these corrected data, and calculating the shock velocity and peak pressure of the shock in the tunnel based on the derivative of this best-fit curve.

Method for Time-Correcting MARVEL Data

To time-correct the data, we used the SLIFER data obtained in each of the four alcoves to determine the radial shock velocity, D , at each location. Figure 38 shows these data; Table 9 summarizes the four calculated data points. Figure 40 plots D as a function of range, R . The shock velocity decreases approximately linearly with R according to the equation

$$D \text{ (m/ms)} = -0.031 R + 3.52 \quad (1)$$

Since the distance from the inside wall of the tunnel to each gage or SLIFER cable is known (see section entitled "Instrumentation"), a shock-transit time, t_{sh} , can be calculated if D is known.

Many assumptions are inherent in this procedure. First, we assume that D so calculated at a distance 0.6 m or more from the Transite pipe wall is valid also at distances much closer to the pipe wall, where the SLIFERS and tourmaline TOA gages are located. At those close distances, D might be larger because the pressure pulse in the grout would not have decayed. Second, we assume that D varies linearly with range, but there is no *a priori* reason that D should respond in this way. Finally, we assume that the material properties of Transite and other materials that are near the gages or SLIFER cables are similar to those of the grout.

Since only a first order correction is needed, the method employed, with the above inherent assumptions, is adequate. Other approaches, such as assuming a peak pressure inside the pipe and calculating the shock velocity decay in the grout may also be valid, but the objective of the analysis is to determine the peak pressure inside the pipe, not the means by which it is obtained. We attempted to use only MARVEL data in this analysis to determine time corrections.

The SLIFER cables were located at closest approach, 0.052 mm from the inside of the Transite pipe wall. The total correction time, t_c , is

$$t_c = t_{sh} + t_{sc} \quad (2)$$

where t_{sc} is the time needed for the SLIFER cable to crush after the shock reaches the cable. Because the diameter of the cables is 0.0063 m (1/4 in.), the maximum closure distance needed to short the cable is 0.003 m. The particle velocity, U , is related to D for a strong shock by

$$U = \frac{2}{\gamma + 1} D \quad (3)$$

Table 9. Shock velocity in each alcove as obtained from the SLIFER data.

Alcove No.	Range from WP, m	Shock velocity (D), m/ms
1	30.09	2.50
2	59.43	1.75
3	81.00	0.94
4	99.28	0.51

Fig. 40. Shock velocity, D , vs range; data points represent SLIFER data in the alcoves.

For asymmetric SLIFER closure, it is assumed that U (m/ms) doubles when the shock reaches the outer jacket; thus

$$t_{sc} = 0.003/2U = \frac{0.003(\gamma + 1)}{4D} \quad (4)$$

For grout in compression at relatively low pressures (1-50 kb), $\gamma \approx 1.5$. Thus, $t_{sc} \approx 0.002/D$.

The total correction time, t_t (ms), is

$$\begin{aligned} t_c &= t_{sh} + t_{sc} \\ &= 0.052/D + 0.002/D \\ &= 0.054/D. \end{aligned} \quad (5)$$

It is readily seen that the time needed to short the SLIFER cable is small compared to the shock-transit time through the grout and Transite. The above expression for t_c , coupled with the equation derived earlier for D as a function of R, is applied to the SLIFER data within 10-100 m from the WP.

The two tourmaline TOA gages were also time-corrected. The total thickness of material between the inside of the tunnel wall and the gage was 0.98 m. Hence, a maximum t_c could be found merely by dividing this thickness by D at the proper range for each gage. Table 10 summarizes the results of this division. However, the material between the inside tunnel wall and the crystal face was not grout; it consisted of 42 mm lead and transite, and 38 mm polyurethane foam, the density of which was not recorded. Thus, another (minimum) t_c was found by the same method used to determine the SLIFER closure time, t_{sc} , i.e., by assuming that the polyurethane foam had a very low density and could be replaced with air in the time-correction calculations. In that case, the particle velocity would double when the shock reached the foam; the calculated t_c would, therefore, be smaller. The results of this calculation appear in Table 10.

The difference between the minimum and maximum calculated values of t_c is only ~20%. The t_c values listed in Table 10 are consistent with, but slightly greater than, those calculated previously by Glenn² (Alcove 1 = 19 μ s, Alcove 3 = 49 μ s).

The cavity-pressure measurement system data can also be used to obtain shock TOA in the main tunnel in Alcove 4. Only the 100-ksi Norwood gage gave a readable TOA and peak; this was consistent with shock arrival, not late-time cavity pressure. Since this gage was located 1.65 m from the inside of the tunnel wall, a time correction was applied to obtain TOA of the shock at the appropriate range in the tunnel. The first 0.9 m of the cavity pressure system was open to the tunnel; using the shock tube data from Alcove 4, the shock-transit time is 110 μ s from the inside of the main tunnel wall to the front of the 0.75-m-long stainless-steel pressure-transducer assembly. The sound speed in stainless steel is about 5.8 m/ms. Therefore, an additional 130 μ s must be added for the shock-transit time through the transducer assembly. The total time correction for the cavity-pressure gage is then 240 μ s, and the arrival of the shock at the range of the cavity pressure system in the main tunnel is 1.86 ms.

We also attempted to time-correct the TOA values for the stress gages in the first four alcoves. Although the nominal sound speed in the grout was 1612 m/s (14-day cure), the actual sound speed,

Table 10. Time-correction range for tourmaline TOA gages.

Alcove No.	Range, m	Shock velocity, m/ms	Maximum t_c (all grout), μ s	Minimum t_c (grout + air), μ s
1	28.7	2.63	30	25
3	80.3	1.03	78	64

measured from the stress gages, varied 2-3 m/ms. Since the stress gages were so far from the inside wall of the tunnel (0.48 m), time corrections could range from 240 to 160 μ s. This is a much larger spread than that derived for any of the gages close to the tunnel. Because of the large time correction uncertainty and the lack of original gage traces, the stress gage analysis is not included in this report.

Comparison of Corrected Data

Time corrections for shock-transit time for each gage or SLIFER cable, as derived above, were applied to the raw data. The data for each alcove is discussed below.

Figure 41 summarizes the TOA data in the vicinity of Alcove 1. Data from SLIFER cables H1M, H2M, and H3M, from the tourmaline TOA gage, and from the side shock tube were used. Excellent agreement between the SLIFER and tourmaline TOA data was obtained; the side shock tube data is clearly later than all the rest by 15-30 μ s. We have found no satisfactory explanation for this.

In the vicinity of Alcove 2, only SLIFER and side-shock-tube TOA data were used, as shown in Fig. 42. The side shock tube TOA agrees very well with the SLIFER data set, H4M.

Figure 43 shows the tunnel TOA data in the vicinity of Alcove 3. Here SLIFER (cable H5M), tourmaline-TOA-gage, and side-shock-tube data were used. Agreement among the data is excellent.

In the vicinity of Alcove 4, SLIFER data (cable H5M), side-shock-tube data, and one TOA measurement from the cavity pressure system were used (see Fig. 44). Agreement among the various data is also excellent at this location.

A summary plot of TOA vs range in the MARVEL tunnel of 0-100 m from the WP appears in Fig. 45. A relatively continuous curve can be drawn through the data. Table 11 summarizes all the MARVEL TOA data for the corrected SLIFER, tourmaline TOA, and cavity-pressure data and for the side-shock-tube data.

Fig. 41. MARVEL tunnel TOA data in the vicinity of Alcove 1.

Fig. 43. MARVEL tunnel TOA data in the vicinity of Alcove 3.

Fig. 42. MARVEL tunnel TOA data in the vicinity of Alcove 2.

Fig. 44. MARVEL tunnel TOA data in the vicinity of Alcove 4.

Fig. 45. Corrected shot TOA in the MARVEL inset.

Table 11. Summary of side-shock-tube (SST), corrected tourmaline gage (TC), corrected SLIFER cable (H-M), and corrected cavity pressure (CP) MARVEL tunnel TOA data.

	Time, ms	R, m		Time, ms	R, m
H1M	0.082	12.2	SST	0.5569	59.05
	0.092	13.6			
	0.127	16.8			
	0.136	19.1			
H2M			H5M	0.794	71.3
	0.175	24.5		0.848	73.1
	0.180	24.9		0.881	74.6
	0.185	26.1		0.929	76.2
	0.190	27.5		1.000	79.2
	0.199	28.0		1.009	79.8
	0.209	29.3	TC	1.010-1.024	80.32
TC	0.194-0.199	28.75	SST	1.0128	80.47
H3M	SST	0.2296		1.307	88.5
				1.345	89.1
				1.416	90.5
	0.239	31.5	H6M	1.505	92.4
	0.268	34.6		1.554	93.8
	0.278	36.7		1.604	94.9
	0.282	37.5		1.679	95.9
	0.292	38.0		1.682	96.2
	0.322	38.5		1.772	97.9
H4M			SST	1.8197	98.53
	0.398	49.1			
	0.423	49.6	CP	1.86	100.6
	0.467	52.1			
	0.506	54.5			
	0.519	56.9			
	0.539	57.3			

Derivation of Shock Velocity and Peak Pressure vs Range in MARVEL Tunnel

Experiment design, results, and analysis of those results have been discussed earlier. Figure 45 presented the final results of shock TOA vs time in the MARVEL tunnel experiment. These results can be used to obtain information about other variables of interest, such as the shock velocity, D , and the peak pressure, P , as a function of distance through the tunnel.

Using the least-squares method, the data set shown in Fig. 45 was fitted by a sixth order polynomial of the form $R(t)$:

$$R(t) = A_1 + A_2 t + \dots + A_7 t^6;$$

the coefficients, $A_1 \dots A_7$, were:

$$A_1 = -1.591199$$

$$A_2 = 178.4022$$

$$A_3 = -183.5543$$

$$A_4 = 131.1180$$

$$A_5 = -56.08275$$

$$A_6 = 11.75495$$

$$A_7 = -0.72003.$$

Figure 46 plots the polynomial fit $R(t)$ with the actual MARVEL data points. This fit is valid in time 0.082-1.82 ms, and in range 11.9-98.8 m. Figure 46 shows that the sixth-order-polynomial fit places a continuous and smooth curve through the actual data points. The shock velocity, D , is merely

$$D(t) = \frac{dR(t)}{dt}, \quad (6)$$

Fig. 46. Sixth order, least-squares fit to MARVEL tunnel TOA data.

the first time derivative of $R(t)$. $D(t)$ then equals

$$D(t) = A_2 + 2A_3t + \dots + 6A_7t^5. \quad (7)$$

$D(t)$ and $R(t)$ then are parametric equations in t which can be solved simultaneously to yield D as a function of R . This was done, and the results are plotted in Fig. 47. The plot shows that D decays from 155 m/ms (15.5 cm/ μ s) at 10 m to ~ 20 m/ms (2.0 cm/ μ s) at 95 m.

Finally, if D is known, the peak pressure vs range can be calculated by the relation ¹¹

$$P = \frac{2}{\gamma + 1} \rho_0 D^2. \quad (8)$$

For air at STP, $\rho_0 = 0.001225$ Mg/m³ (0.001225 g/cm³), but γ varies with P over the pressure range of interest, 1-30 GPa (10-300 kbar), because of ionization. Zel'dovich, ¹¹ however, gives a table which relates P to D for a shock propagating into air at STP. This information is plotted in Fig. 48. The equation for $D(R)$, coupled with Fig. 48 can be used to determine $P(R)$ graphically. The results of this computation are plotted in Fig. 49. Figure 49(a) presents a log-log plot of $P(R)$ vs R ; Fig. 49(b), shows a linear plot. Table 12 lists the data points used in these plots.

The peak pressure curve so obtained is continuous, with the slope constantly changing. At ~ 30 m, the pressure is attenuating as $1/R$; at 75-95 m the pressure is attenuating as $1/R^6$.

Fig. 47. Shock velocity vs range through the MARVEL tunnel.

Fig. 48. Peak-shock pressure vs shock velocity.

Table 12. Summary table of shock velocity and peak pressure vs range in the MARVEL tunnel.

Range, m	D, m/ms	P, kbar	P, kpsi
10	154	260	3820
15	144	240	3528
20	134	210	3087
25	124	180	2646
30	113	145	2132
35	103	122	1793
40	95	105	1544
45	85	85	1250
50	78	70	1029
55	69	55	808
60	60	42	617
65	53	33	485
70	45	24	353
75	40	19	279
80	34	14	206
85	27	8.5	125
90	22	5.6	82
95	20	4.6	68

Fig. 49. Peak pressure vs range in MARVEL tunnel shown by (a) log-log plot and (b) linear plot.

SUMMARY AND CONCLUSIONS

In 1967, the LLL MARVEL event was fired at the Nevada Test Site in a vertical drill hole. It was a unique experiment because it had a 122-m-long, 0.99-m-i.d. horizontal air-filled shock tube (or tunnel) attached to the zero room. Shock TOA data were taken along the length of the tunnel.

Because of the nature of the MARVEL experiment, the data were applicable to the DNA MX in-trench environment research program. In this program, much information was needed concerning nuclear explosion-induced shock velocity, peak pressure, and total impulse vs range in long, shallowly buried trenches.

The flow variables of interest can be obtained, within limits, from a shock TOA curve, provided that all data are consistent with each other and that the uncertainties are small.

Part of the task involved examining the techniques, instrumentation emplacement, and recorded data from MARVEL; placing uncertainty bounds

on that data; and rederiving the shock TOA curve inside the MARVEL tunnel. This curve had previously been published four times, but those four curves were slightly inconsistent with each other. To derive most shock tube flow variables of interest, the first time-derivative of the TOA curve had to be taken. The earlier inconsistencies led to large variations in the slope of the MARVEL TOA curve, so, from the published data, it was difficult to calculate the flow variables to the accuracy required for the MX program.

During this investigation, the emplacement of all instrumentation designed to measure the characteristics of the air shock in the MARVEL tunnel (including SLIFER cables, side shock tubes, and various stress and pressure gages) was thoroughly examined. The uncertainties in the "raw" experimental data were found to be small. Time corrections were applied to the data set as required to account for shock-transit time from the inside of

the tunnel to the location of the instrument. These time corrections were derived from the MARVEL data set only. The result is a set of very consistent shock TOA data inside the MARVEL tunnel at 10-100 m from the WP. We fit the TOA data set with sixth-order polynomial using the least-squares method. Finally, by a time derivative of the polynomial fit, we obtained the shock velocity vs range in the MARVEL tunnel. From that curve, we calculated the peak pressure in the air behind the shock front, using elementary shock-tube theory. These results show that the peak pressure in the tunnel decayed from 260 kbar at 10 m to 4.6 kbar at 95 m in a very regular manner.

We can draw the following major conclusions from this report:

1. The details of the emplacement of the MARVEL shock instrumentation are known precisely.
2. The uncertainties in the shock TOA data points are known; all are relatively small.
3. When these TOA data are corrected for shock-transit time, the data set becomes much more self-consistent, and a remarkably regular tunnel shock TOA curve emerges.
4. The derived peak pressure curve shows a $1/R^6$ dependence at 75-95 m.
5. Through scaling or calculations, the MARVEL data can now be applied to actual MX emplacement configurations with increased confidence.

ACKNOWLEDGMENTS

The MARVEL event was designed and executed by LLL staff members in A, B, and K Physics Division, the Nuclear Test Engineering Division, the Chemistry Department, and the Plowshare Field-Test Engineering group. L. Rogers was the project physicist. B. Killian, D. Glenn, E. Pelsor, and P. Compton contributed to the experiment design and predictions. R. Marks, D. Glenn, C. Sisemore, and P. Compton designed the instruments, and R. Guido was the event engineer. The overall project was under the direction of Dr. G. C. Werth, Associate Director of Plowshare, and Dr. G. H. Higgins, K-Division Leader. Other individuals whose names I do not know undoubtedly made significant contributions to this unique effort at the time of the event before I became involved in the work. To them I offer thanks also.

Many people were helpful in this postshot analysis, including Dr. R. E. Duff, who asked many pertinent questions about the published MARVEL data and the experimental design; and B. Killian, R. Marks, and D. Glenn, all of whom willingly sup-

plied much needed first-hand information about the experiment and the experimental results. J. Harri, R. Rossman, and B. Maranville of the Nuclear Test Engineering Division supplied much needed information on the emplacement of the instrumentation. Dr. G. H. Higgins supplied information on the overall purpose of the MARVEL event.

Dr. George Ullrich was the DNA contract monitor, and Dr. Eugene Sevin was the head of the Strategic Structures Division of DNA during the period of this investigation. Both provided welcome support for the effort.

Finally, I wish to thank S. Lauffer of LLL, Nevada, who reproduced more than a hundred photographs taken during the MARVEL event, and L. Burrow, whose efforts in preparing the initial manuscript are deeply appreciated.

Work was performed for the Defense Nuclear Agency under contract No. IACRO 77-811 under auspices of the U.S. Department of Energy under contract No. W-7405-Eng-48.

REFERENCES

1. B. K. Crowley, H. D. Glenn and R. E. Marks, "An Analysis of Marvel—A Nuclear Shock Tube Experiment," *J. Geo. Res.* **76**,14, (1971).
2. H. D. Glenn and B. K. Crowley, "MARVEL—Nuclear Driven Shock Tube Experiment," *Jour. App. Phys.* **41** (2), 689 (1970).
3. B. K. Crowley and H. D. Glenn, "The MARVEL Experiment," *Nuc. Tech.* **11** (July 1971).
4. L. A. Rogers, *Summary of the MARVEL Experiment*, Lawrence Livermore Laboratory, Livermore, Calif., Rept. UCRL-50388 (1968) (title U, report SRD).
5. J. M. Thomsen, *DNA MX Program Progress Report: LLL Presentation to MX C-5 Trench Environment Review Meeting*, Lawrence Livermore Laboratory, Livermore, Calif., Rept. COPK 77-12, May 1977 (title U, report SRD).
6. M. Heusinkveld and F. Holzer "A Method of Continuous Shock Front Position Measurement," *Rev. Sci. Inst.*, **35**, (9) 1105 (1964).
7. R. E. Marks, private communication, Dec. 1977.
8. W. Hurdlow, *Preliminary Report on Slifer Measurements of Shock Position in the MARVEL Experiment*, Lawrence Livermore Laboratory, Livermore, Calif., Rept. UOPKB 67-149, December 1967 (title U, report C).
9. H. D. Glenn, private communication (Jan. 1978).
10. R. E. Marks, unpublished Lawrence Livermore Laboratory report manuscript.
11. Y. B. Zel'dovich and Y. P. Raizer, *Physics of Shock Waves and High-Temperature Phenomena*, Vol. 1, (Academic Press, New York City, New York 1966).

APPENDIX

MARVEL ENGINEERING DRAWINGS

Nine engineering drawings, Figs. A1-A9, showing pertinent design and emplacement details for each of the major active ground motion and tunnel flow experiments on the MARVEL event, constitute this appendix.

Fig. A2. SLIFER and stress gage emplacement in MARVEL instrument hole 6.

Fig. A3. Tunnel and alcove construction plan.

[illegible]

119266-0

[illegible]

Fig. A4. Tunnel SLIFER emplacement.

FLAN

Run	Time (min)	Conc. (mg/ml)
1	94.8	0.36
2	96.36	0.45
3	270.34	0.6
4	329.91	0.81

SECTION 8-B
(ALCOVE 2 & 3)

Side Shock Tube

ALL LOVE 12345

DATE	A	B	C	D	E	1ST ATTEMPT	2ND ATTEMPT	3RD ATTEMPT
NO.	NO.	NO.	NO.	NO.	NO.	NO.	NO.	NO.
1	12.15	40.15	58.15	72.00	84.00	1	2	3
2	12.15	55.00	1.10	74.15	84.50	4	5	6
3	12.15	55.50	1.10	74.00	84.00	2	3	4
4	12.15	55.50	1.10	74.00	84.00	2	3	4

[illegible][illegible]

Fig. A5. Side shock tube (and ion gage) design and emplacement.

[illegible]

Fig. A6. Stress-gage emplacement.

REV	DATE	BY	CHK	DATE	ZONE	CHARGE
A	8/20/74	TKL	TKL			REDUCED ASSY LENGTH FROM 12.00" TO 7.00"
						ADDED ITEM 9

67-108152-0A

9	67-10707-04	TUBE	1				
8		CABLE-GUITAR REPAIR	1	ALLOY	AMPHENOL	CORP M21-373 (REF)	
7		INSULATING TAPE	1	BLACK	TEFLON		
6	68-117217-00	PAGE 1 SOLDER SOLDERING	1		CORP		
5	61-122348-00	PAGE 2 COLLAR	1		CORP		
4	65-111337-00	SINGLE ROLL PRESS TANDUM	1				
3	65-100781-00	SLEEVE	1		BRASS		
2	67-107036-00	END R	1		BRASS SOL		
1		ROLL PIN 1/8" DIA X 3/16"	3		STEEL		

ITEM	PART NO.	DESCRIPTION	NO. REQD	MATERIAL	SPEC. NO.	STOCK NO.
UNLESS OTHERWISE SPECIFIED:						
A. TOLERANCES: DEC-TWO PLACES ± .01 THREE PLACES ± .001 FRACTIONS ± 1/16 ANGLES ± 30°						
B. BREAK EDGES .015 MAX.						
C. 30° CHAMFER ENDS OF SCREW THREADS.						
D. 1/16 PITCH THREAD RELIEF WITH ROUND NOSE TOOL ON BRONING CUT SCREW THREADS.						
E. ON WELDMENTS REMOVE BURRS, LOOSE SCALE AND SPATTER.						
F. SURFACE ROUGHNESS PER MIL-STD 32.						
CLASSIFICATION						
1. THIS DRAWING IS THE PROPERTY OF THE LAWRENCE RADIATION LABORATORY AND SHALL BE RETURNED TO THE LABORATORY WHEN REQUESTED BY THE USER. 2. NO REPRODUCTION OR TRANSMISSION OF THIS DRAWING IS TO BE MADE WITHOUT THE WRITTEN PERMISSION OF THE LAWRENCE RADIATION LABORATORY. 3. THIS DRAWING IS NOT TO BE USED FOR ANY OTHER PURPOSE WITHOUT THE WRITTEN PERMISSION OF THE LAWRENCE RADIATION LABORATORY.						
LAWRENCE RADIATION LABORATORY UNIVERSITY OF CALIFORNIA						
DRAWING NO. AAA67-108152-0A						
C SCALE 1/4" = 1" COPY						

Fig. A7. Stress-gage canister assembly.

Fig. A8. Cavity-pressure system design and emplacement.

Fig. A9. Cavity-pressure transducer assembly.