DOE/PC/91257-T16
(DE93013617)

**MOLTEN-CAUSTIC-LEACHING (GRAVIMELT) SYSTEM INTEGRATION PROJECT
PHASE II**

Topical Report for Test Circuit Operation

February 1993

Work Performed Under Contract No. AC22-86PC91257

**For
U.S. Department of Energy
Pittsburgh Energy Technology Center
Pittsburgh, Pennsylvania**

**By
TRW Space and Electronics Group
Redondo Beach, California**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615)576-8401.

Available to the public from the National Technical Information Service, U. S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

**MOLTEN-CAUSTIC-LEACHING (GRAVIMELT)
SYSTEM INTEGRATION PROJECT
PHASE II**

**TOPICAL REPORT FOR TEST
CIRCUIT OPERATION**

CONTRACT NUMBER DE-AC22-86-PC91257

FEBRUARY 1993

**PREPARED BY APPLIED TECHNOLOGY DIVISION
TRW SPACE AND ELECTRONICS GROUP
ONE SPACE PARK
REDONDO BEACH, CA 90278**

**PREPARED FOR
U.S. DEPARTMENT OF ENERGY
PITTSBURGH ENERGY TECHNOLOGY CENTER
P.O. BOX 10940
PITTSBURGH, PA 15236**

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States nor any agency thereof, nor any of their employees, makes any warranty, expressed or implied, or assumes any legal liability or responsibility for any third party's use or the results of such use of any information, apparatus, product, or process disclosed in this report or represents that its use by such third party would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government of any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

TABLE OF CONTENTS

	<u>Page</u>
Abstract	xiii
1. INTRODUCTION AND SUMMARY	1-1
1.1 PROCESS DESCRIPTION	1-3
1.2 BACKGROUND.	1-8
1.2.1 Phase I Test Results	1-8
1.2.2 Phase II Modifications and Off-Line Testing.	1-8
1.3 OPERATIONS TEST RESULTS	1-10
1.3.1 Test Run No. 10.	1-10
1.3.2 Test Run No. 11.	1-11
1.3.3 Wash Train Test Following Run No. 11	1-12
1.3.4 Coal/Water Separation Tests.	1-12
1.4 RECOMMENDATIONS	1-13
1.5 REPORT OUTLINE.	1-13
2. TEST RUN NO. 10 (JUNE 3 TO 7, 1991).	2-1
2.1 CHRONOLOGY OF OPERATIONS.	2-2
2.2 KILN OPERATIONS (SECTION 100)	2-2
2.2.1 Test Description	2-2
2.2.2 Kiln Feed Rate	2-7
2.2.3 Kiln Discharge Rate.	2-7
2.2.4 Sulfur, Ash and Volatiles.	2-9
2.3 WASH TRAIN OPERATIONS (SECTIONS 200 AND 300).	2-9
2.3.1 Background	2-9
2.3.2 Test Description	2-12
2.3.3 Material Balance	2-16
2.3.4 Coal Fines/Size Distribution	2-16
2.3.5 Product Coal Analysis.	2-23
2.3.5.1 Sulfur Removal.	2-23
2.3.5.2 Ash, Volatiles and Heating Value.	2-23
2.3.6 Product Coal Moisture.	2-23
2.3.7 Observations	2-23
2.4 CAUSTIC REGENERATION OPERATIONS (SECTION 400)	2-27

TABLE OF CONTENTS (CONTINUED)

	<u>Page</u>
2.4.1 Test Description	2-27
2.4.2 Carbonate Removal	2-29
2.4.3 Silica, Alumina, Iron, Sulfur and Humics Removal	2-32
2.5 CAUSTIC EVAPORATION OPERATIONS (SECTION 500).	2-32
2.5.1 Background	2-32
2.5.2 Test Description	2-33
2.5.3 Moisture Content	2-36
2.5.4 Observations	2-36
3. TEST RUN NO. 11 (MAY 14 TO 21, 1992)	3-1
3.1 CHRONOLOGY OF OPERATIONS.	3-2
3.2 KILN OPERATIONS (SECTION 100)	3-2
3.3 WASH TRAIN OPERATIONS (SECTIONS 200 AND 300).	3-13
3.3.1 Background	3-13
3.3.2 Test Description	3-14
3.3.3 Effect of pH	3-15
3.3.4 Product Coal Analysis.	3-19
3.3.5 Sulfur Removal	3-24
3.3.6 Ash Removal.	3-26
3.3.7 Mineral Constituents of the Product Coal	3-29
3.3.8 Acid Wash Effluent Stream Composition.	3-33
3.3.9 Product Coal Moisture.	3-33
3.3.10 Product Coal Size Distribution	3-36
3.3.11 Heating Value.	3-36
3.3.12 Sulfur Forms	3-39
3.3.13 Volatiles Content.	3-39
3.3.14 Carbonate Content.	3-39
3.3.15 Humics Content	3-41
3.3.16 Total Organic Carbon (TOC) Content	3-41
3.3.17 Partition of Sulfur, Silica, Alumina and Iron.	3-41
3.4 CAUSTIC REGENERATION OPERATIONS (SECTION 400)	3-45
3.4.1 Caustic Solution Analysis.	3-46
3.4.1.1 Carbonate	3-46
3.4.1.2 Sulfur, Silica, Alumina and Iron.	3-46
3.4.2 Centrifuge Cake Analysis	3-51
3.4.3 Effect of Extended Residence Time.	3-54
3.5 CAUSTIC EVAPORATION OPERATIONS (SECTION 500).	3-58
3.5.1 Moisture Content	3-58
3.5.2 Caustic Flake Analysis	3-61
3.5.3 Heat Transfer Coefficients	3-61

TABLE OF CONTENTS (CONTINUED)

	<u>Page</u>
3.6 MATERIAL BALANCE.	3-67
3.7 SUMMARY OF TEST RUN NO. 11 - OBSERVATIONS AND CONCLUSIONS . .	3-67
4. WASH TRAIN TEST FOLLOWING RUN NO. 11 (JUNE 24-25, 1992).	4-1
5. SCALEUP COAL/WATER SEPARATION TESTS IN A 9-INCH CENTRIFUGE	5-1

LIST OF FIGURES

	<u>Page</u>
Figure 1-1. Block Diagram of the MCL Process.	1-4
Figure 1-2. Schematic of the MCL Process.	1-6
Figure 2-1. MCL Operations Chronology - Test Run No. 10	2-3
Figure 2-2. Rotary Kiln Reaction System	2-6
Figure 2-3. Kiln Discharge Rate vs. Time, Run 10D Kiln Wall Temperature = 750°F (400°C)	2-8
Figure 2-4. Water Washing System.	2-10
Figure 2-5. Vacuum Filtration System.	2-13
Figure 2-6. Acid Washing System	2-14
Figure 2-7. Caustic Regeneration System	2-28
Figure 2-8. Evaporation System.	2-34
Figure 3-1. MCL Operations Chronology - Test Run No. 11	3-3
Figure 3-2. Kiln Temperatures and Sulfur Content - Test Run No. 11.	3-10
Figure 3-3. Sodium Carbonate - Sodium Hydroxide - Water System.	3-16
Figure 3-4. Acid Wash System pH - Test Run No. 11	3-17
Figure 3-5. Product Coal Sulfur - Test Run No. 11	3-25
Figure 3-6. Product Coal Ash - Test Run No. 11.	3-28
Figure 3-7. Regeneration System - Percent NaOH in Regeneration Feed/Regenerated Alkali - Test Run No. 11	3-48
Figure 3-8. Regeneration System - Percent Na ₂ CO ₃ in Regeneration Feed/Regenerated Alkali - Test Run No. 11	3-49
Figure 3-9. Procedure for Preparing Regeneration Centrifuge Cake Sample for Analysis - Test Run No. 11	3-53
Figure 3-10. Evaporator Temperatures - Test Run No. 11.	3-65
Figure 5-1. Flow Schematic for MCL Tests in 9-Inch Centrifuge	5-2

LIST OF TABLES

	<u>Page</u>
Table 2-1. Run Condition Summary - Test Run No. 10.	2-4
Table 2-2. Kiln Discharge Solids Analytical Results - Test Run No. 10	2-11
Table 2-3. Kiln Material Balance - Test Run No. 10.	2-17
Table 2-4. Coal Fines in Filtrate Samples	2-18
Table 2-5. Kiln Discharge Coal Size Distribution.	2-19
Table 2-6. Product Coal Size Distribution	2-21
Table 2-7. Comparison of Analyses for Pittsburgh No. 8 Coal	2-22
Table 2-8. Product Coal Analytical Results - Test Run 10D	2-24
Table 2-9. Feed Coal Analysis (1988).	2-25
Table 2-10. Product Coal Moisture Levels - Test Run 10D	2-26
Table 2-11. Regeneration Unit - Carbonate Analytical Results - Test Run 10D	2-30
Table 2-12. Regeneration Unit - Silica, Alumina, Iron, Sulfur and Humics Analytical Results - Test Run 10D.	2-31
Table 2-13. Caustic Evaporation Unit Product Flake Moisture Content	2-37
Table 3-1. Feed Coal Analysis (Dry Basis) - Test Run No. 11	3-5
Table 3-2. Run Condition Summary - Test Run No. 11.	3-6
Table 3-3. Log of Caustic in Mix Transferred to Kiln Feed Hopper Test Run No. 11.	3-7
Table 3-4. Total Quantity of Coal/Caustic Fed to Kiln - Test Run No. 11	3-8
Table 3-5. Kiln Off-Gas Analysis - Test Run No. 11.	3-12
Table 3-6. Product Coal Analyses Performed by TRW - Test Run No. 11	3-20
Table 3-7. Product Coal Sulfur, Sulfur Forms, Heating Value, and Ash Analyses Performed by Standard Laboratories - Test Run No. 11	3-23
Table 3-8. Product Coal Sulfur Removal Results - Test Run No. 11. .	3-27

LIST OF TABLES (CONTINUED)

	<u>Page</u>
Table 3-9. Kiln and Acid Wash Train pH Test Matrix - Test Run No. 11	3-30
Table 3-10. Product Coal Ash Content vs. Kiln Conditions/Acid Wash pH - Test Run No. 11	3-31
Table 3-11. Product Coal Ash Ultimate Analysis - Test Run No. 11. .	3-32
Table 3-12. Mineral Constituents of Product Coal - Test Run No. 11.	3-34
Table 3-13. Acid Wash Effluent to Water Treatment Section - Test Run No. 11.	3-35
Table 3-14. Product Coal Size Analysis - Test Run No. 11.	3-37
Table 3-15. Coal Feed Size Distribution - Test Run No. 11	3-38
Table 3-16. Vacuum Filter F-201 Filtrate Analysis - Coal Fines, Caustic, Carbonate and Humics - Test Run No. 11	3-40
Table 3-17. Regeneration Feed Total Organic Carbon (TOC) - Test Run No. 11.	3-42
Table 3-18. Vacuum Filter F-201 Filtrate Analysis - Sulfur, Silica, Alumina and Iron - Test Run No. 11.	3-43
Table 3-19. Comparison of Sulfur, Silica, Alumina and Iron Oxide in Feed Coal Versus Filtrate to Regeneration - Test Run No. 11.	3-44
Table 3-20. Regenerated Alkali Analysis - Test Run No. 11.	3-47
Table 3-21. Regeneration Feed/Regenerated Solution Analysis - Test Run No. 11	3-50
Table 3-22. Ash and Sulfur Rejection from MCL Facility - Test Run No. 11.	3-52
Table 3-23. Regeneration Unit Centrifuge Cake Sample Analysis - Test Run No. 11	3-55
Table 3-24. Regeneration Unit Centrifuge Cake "Coal" Fraction Analysis - Test Run No. 11.	3-56
Table 3-25. Soluble Sulfur in Centrifuge Cake - Test Run No. 11 . .	3-57
Table 3-26. Results of Extended Residence Time in Regeneration System - Test Run No. 11.	3-59

LIST OF TABLES (CONTINUED)

	<u>Page</u>
Table 3-27. Regenerated Caustic Flake Moisture Content - Test Run No. 11.	3-60
Table 3-28. Caustic Flake Analysis - Test Run No. 11.	3-62
Table 3-29. Caustic Flake Sulfur and Mineral Matter Analysis - Test Run No. 11	3-63
Table 3-30. Evaporator Performance Data - Test Run No. 11	3-64
Table 3-31. MCL Caustic Evaporation Off-Line Tests Prior to Test Run No. 11	3-66
Table 3-32. Overall Coal Material Balance - Test Run No. 11	3-68
Table 3-33. Overall Sulfur Material Balance - Test Run No. 11	3-69
Table 4-1. MCL Water Wash Train Test Product Coal Sulfur/Ash.	4-3
Table 5-1. MCL Coal/Water 9-Inch Solid Bowl Centrifuge Separator Performance Results.	5-3

ABSTRACT

The objective of the task (Task 6) covered in this document was to operate the refurbished/modified test circuit in a continuous integrated manner to obtain the engineering and operational data necessary to assess the technical performance and reliability of the circuit. This data is critical to the development of this technology as a feasible means of producing premium clean burning fuels that meet New Source Performance Standards (NSPS). Significant refurbishments and design modifications had been made to the facility (in particular to the vacuum filtration and evaporation units) during Tasks 1 and 2, followed by off-line testing (Task 3). Two weeks of continuous around-the-clock operation of the refurbished/modified MCL test circuit were performed (in June 1991 and May 1992). During the second week of testing, all sections of the plant were operated in an integrated fashion for an extended period of time, including a substantial number of hours of on-stream time for the vacuum filters and the caustic evaporation unit. Product coal produced over a 90-hour period during the second week of testing contained less than 0.3 wt% sulfur (less than 0.44 lbs SO₂/million Btu). This represents a 90% reduction in sulfur from the 4.5 lbs SO₂/million Btu for the raw run-of-mine (ROM) coal, thus meeting the most stringent U.S. standards. Product coal was produced with a sulfur content as low as 0.11 wt% (0.17 lbs SO₂/million Btu or 198 mg SO₂/Nm³) which corresponds to a 96% reduction in sulfur from ROM and which is one-half of the EC standard of 400 mg SO₂/Nm³. A new process configuration was tested in which centrate from the acid wash train (without acid addition) was used as the water makeup for the water wash train, thus eliminating the one remaining process waste water stream. A 9-inch centrifuge was tested at various solids loadings and at flow rates up to 400 lbs/hr of coal feed to obtain a twenty-fold scaleup factor over the MCL integrated test facility centrifuge performance data.

1. INTRODUCTION AND SUMMARY

This is a report of the results obtained from the continuous around-the-clock operation of the integrated test circuit of the Molten-Caustic-Leaching (MCL or Gravimelt) process for the desulfurization and demineralization of coal. The project is sponsored by the Pittsburgh Energy Technology Center of the U.S. Department of Energy under Contract No. DE-AC22-86-PC91257.

The test circuit was constructed and operated under the previous program (referred to in this document as the Phase I program). The added scope to this program is referred to in this document as the Phase II program. Specific objectives of the Phase II program are:

1. To repair, refurbish, and modify the existing MCL test circuit systems to enable off-line unit operation testing following by continuous long term integrated test operations.
2. To determine the optimal operating parameters for each of the unit operations in the test circuit and to demonstrate those optimal conditions within the limitations of the test circuit.
3. To obtain the necessary engineering and operational data to assess the technical and economic viability of the process in consideration of scaleup to a production unit.
4. To obtain large quantities of MCL treated coals in order to conduct fuel characterization and utilization testing for determining the utility and value of the product coal.

A detailed description of the Phase II maintenance, refurbishment and modifications made to the test circuit (Tasks 1 and 2), and the off-line circuit component test results (Task 3) are presented in a separate document entitled "Topical Report for Test Circuit Maintenance, Refurbishment, Modification, and Off-Line Operation".

The work performed on Task 6 of the Phase II program is covered in this report. The objective of this task was to operate the refurbished/modified test circuit in a continuous integrated manner maximizing recycle of chemicals and water and minimizing process waste.

This task was accomplished by the operation of the plant on a 24-hour per day basis for 5 to 7 days, enough time to allow the system to reach steady-state with respect to recycle streams. The goal of this task was to obtain the engineering and operational data necessary to assess the technical performance and reliability of the circuit as a whole, which cannot be obtained on an off-line or semicontinuous operating basis.

Tasks 1, 2 and 3 (maintenance, refurbishment, modification, and off-line testing) were completed without the addition of major capital equipment but rather with the replacement of parts and materials and with modification of the existing equipment to upgrade them to original performance levels. The overall strategy for the Phase II program was to allow for the earliest startup of the Task 6 integrated operations with a minimum of up front costs attributed to plant modifications. The plan was to implement only those modifications that were required in order that the plant can be operated in an integrated continuous manner. The most critical modifications were those affecting the operation of the vacuum filters and the evaporator that were necessary for integrated operation.

Two weeks of continuous around-the-clock operation of the refurbished/modified MCL test circuit were performed (in June 1991 and May 1992). The objectives of the continuous test operations were:

- To evaluate the long term performance characteristics of the refurbishments and design modifications made to the facility (in particular those made to the filtration and evaporation units).
- To demonstrate continuous, integrated operations with all the process components of the MCL facility on-stream at the same time.

During the June 1991 operations, a substantial number of hours of on-stream time were logged for the first time for the vacuum filters operating in series with the rest of the water washing train. The caustic evaporation unit was put on-stream at the end of the week.

During the May 1992 integrated operations, all sections of the plant were operated in an integrated fashion for an extended period of time. Product

coal produced during a 90-hour period contained less than 0.3 wt% sulfur (less than 0.44 lbs SO₂/million Btu). This represents a 90% reduction in sulfur from the 4.5 lbs SO₂/million Btu for the raw run-of-mine (ROM) coal, thus meeting the most stringent U.S. standards. Product coal was produced with a sulfur content as low as 0.11 wt% (0.17 lbs SO₂/million Btu or 198 mg SO₂/Nm³) which corresponds to a 96% reduction in sulfur from ROM and which is one-half of the EC standard of 400 mg SO₂/Nm³.

A new process configuration was tested in which centrate from the acid wash train (without acid addition) was used as the water makeup for the water wash train, thus eliminating the one remaining process waste water stream. The elimination of acid washing and of the subsequent liming of the extract results in significant cost savings to the process.

1.1 PROCESS DESCRIPTION

The MCL process utilizes a melt of sodium hydroxide or mixtures of sodium and potassium hydroxides at reaction temperatures of 325 to 415°C to remove (at the high end of this temperature range) virtually all of the sulfur and mineral matter from coal. The process is a potential replacement for the costly flue gas desulfurization systems contemplated for smaller utilities and industrial boilers. The product coal might also displace oil in some turbine and diesel engines and may be used in the retrofit of oil-fired boilers to coal-fired boilers. Product MCL coal may also have application as an inexpensive pre-activated or activated carbon for extraction of pollutants from waste water or to cleanup and concentrate radioactive or toxic waste.

The test circuit consists of six unit operations (Figure 1-1) which together provide a continuous system for leaching coal with caustic and then regenerating the caustic. These units are:

- A kiln for reacting molten caustic with coal (Section 100)
- A seven-stage water washing section for recovering caustic from the coal (Section 200)
- A three-stage acid washing section for removing residual metals and alkali and providing an ultra-pure coal product (Section 300)
- A regeneration section to provide purified aqueous caustic (Section 400)

Figure 1-1. Block Diagram of the MCL Process

- An evaporator section to provide molten or flaked caustic for recycle to the kiln reactor (Section 500)
- A water treatment section to provide either dischargeable or recyclable water (Section 600).

The integrated test circuit facility that was constructed at the TRW San Juan Capistrano test site in California contains about 150 pieces of commercial equipment including filters, centrifuges, tanks, reactors, feeders, a kiln, and a rising film evaporator. It occupies 3700 square feet and is fitted with more than 6000 feet of piping, 425 valves, 80 instruments and controls as well as a computer control room and a data acquisition and reduction system.

A schematic of the MCL process is shown in Figure 1-2. Feed coal is premixed with anhydrous sodium hydroxide, or mixed sodium and potassium hydroxides, and then fed to a rotary kiln reactor (Section 100) where the mixture is heated to reaction temperatures of 325 to 415°C causing the caustic to: 1) melt and become sorbed in the coal matrix, 2) react with the coal sulfur and mineral matter, and 3) dissolve the reaction products containing sulfur and inorganic components.

The reaction mixture is cooled in the cooling section of the kiln such that the mixture exits the rotary kiln in the form of pellets that are then washed with water in a seven-stage countercurrent separation system consisting of two filters and five centrifuges (Section 200). As an example, four weights of wash water per weight of coal may be used resulting in a 50% aqueous reacted caustic solution exiting the first stage of filtration. A large part of the coal-derived iron and a small amount of the sodium and/or potassium remain with the coal cake exiting this countercurrent washing system.

The coal cake is next washed to remove the residual iron and caustic in a countercurrent three-stage centrifuge system (Section 300). Sulfuric acid is added to the first stage to produce a pH of about 2 in order to dissolve the residual alkali and iron hydroxide. As an example, three weights of wash water per weight of coal may be used resulting in an acid extract leaving the

Figure 1-2. Schematic of the MCL Process

first stage containing 5,900 ppm of mixed sodium and potassium sulfates and 12,500 ppm of iron sulfate. The product coal exiting this acid washing system contains about one weight of sorbed water.

All of the iron sulfate and a major portion of the alkali sulfates can be removed from the acid extract water by a sequence of heating and lime treatment (Section 600) to form insoluble minerals such as gypsum. This water can then be recycled to the water wash train. Under some (very carefully controlled) conditions, the precipitate formed can be a jarosite-like double salt which can be easily disposed of or land-filled.

A new process configuration, with potentially large cost savings to the process, was tested in which the centrate from the acid wash train (without acid addition) was used as the makeup wash water for the water wash train, thus eliminating the acid extract waste water stream along with an entire plant section (Section 600). This configuration resulted in a product coal with low sulfur and moderate ash content suitable for those commercial applications that do not require low ash coal. Eliminating the acid washing and the acid waste water treatment steps could result in a potential reduction in processing costs of nearly 25%, reducing process cost forecasts to under \$45/ton (17 mils/kW-hr) and placing the MCL Process in a significantly advantageous cost position relative to FGD for boilers and furnaces smaller than 200 MW_e.

The aqueous caustic recovered from the first countercurrent washing circuit is limed to remove the coal-derived mineral matter, sulfur compounds, and carbonates (Section 400). The mixture is provided with sufficient residence time to permit precipitation of the impurities before being centrifuged. The purified liquid is preheated and sent to a caustic evaporator (Section 500) where the water is recovered for recycle to the first wash train, while producing anhydrous caustic (as either a molten liquid or as flakes) for reuse in the initial leaching of the coal in Section 100.

A detailed description of the modified test circuit is presented in Section 2 of the topical report entitled "Topical Report for Test Circuit Maintenance, Refurbishment, Modification, and Off-Line Operation".

1.2 BACKGROUND

1.2.1 Phase I Test Results

The test circuit was operated on a continuous basis during the Phase I program for 100 hours of shakedown operation in December 1988 and for nine operating weeks from January to June 1989 resulting in 750 additional hours of matrix testing. The program objectives were met in part as a result of this operation and the data produced during operation was assessed in detail. Several important conclusions were drawn from the Phase I operations:

- 1) The combination of continuous operation, exclusion of air from the system, and mild reactor conditions allowed the production of MCL coal with low carbonate production, low volatiles loss, and low retention of moisture in washing operations.
- 2) Using mild reactor operating conditions, MCL coal can be water washed to very low residual caustic concentrations with the current number of wash stages. It may be possible to reduce the number of countercurrent wash stages required and thus lower the operating and capital costs.
- 3) The use of NaOH only as the caustic media produced coal product meeting New Source Performance Standards (NSPS), thus eliminating the need for the addition of the more expensive KOH.

Although most of the program objectives were met and demonstrated during the Phase I operations, there were often equipment problems and failures that prevented operation in an integrated manner where all units were operating at optimum processing conditions. Many of the equipment problems were breakdowns that would be expected in a startup mode of operation for any chemical process. In many cases, budget constraints did not allow for the replacement or repair of equipment. Instead operation continued at less than optimal conditions. For a detailed description of the Phase I test circuit operations see the report entitled "Topical Report for Test Circuit Operation", dated November 1990.

1.2.2 Phase II Modifications and Off-Line Testing

In order to overcome the deficiencies of the original test circuit and operate the plant in an integrated manner at optimal conditions, several

repairs and modifications to the configuration and procedures were required. This is the primary purpose of the current phase (Phase II) of the program.

There existed several specific problem areas that needed to be addressed in the current Phase II program to enable integrated operation using the basic, existing equipment layout. The most critical modifications necessary for integrated operation were those affecting the operation of the vacuum filters and the evaporator.

The inability to operate the vacuum filters in a continuous and reliable mode during the Phase I test operations due to intermittent flows to and from the filters resulted in the vacuum filters being bypassed during most of Phase I testing. The vacuum filter system was extensively modified during the current Phase II program. The system was replumbed so that the flow rates to the filters were greatly increased (spillback lines to the dissolver/feed tanks were provided along with filtrate recycle). Line sizes were increased and the feed pumps to the filters were replaced with higher capacity pumps. Level switches in the filtrate tanks were replaced with bubbler level indicators. The level indicator readings in the filtrate and dissolver/feed tanks are now fed to the computer which automatically adjusts four newly installed control valves such that the levels in the tanks are maintained at preset levels by recycling some filtrate back to the dissolver/feed tanks. After successful off-line filter tests using manual control, the filter system was successfully tested off-line in the automatic control mode.

The evaporation system was not operated during most of the Phase I test operations because the vacuum filters were bypassed and the caustic solutions produced as a result were too dilute for the evaporator. However, off-line evaporator tests during Phase I experienced limited throughput, low overall heat transfer coefficients, and periodic surges or upsets. In the current Phase II program, the overhead vent system on the evaporator was modified to reduce the back pressure and prevent flow surges and uneven evaporation rates. The line sizes on the evaporator vent were increased from 1 inch to 2 inches. A preheater was installed on the evaporator feed to remove the sensible heating requirement from the evaporator. The evaporator is now used strictly for boiling. Hot oil jacketing and improved thermal insulation were

installed on the molten caustic line from the evaporator to the flaker in order to allow for operation with NaOH only rather than the lower melting point NaOH/KOH mixture used during the Phase I program. When the new evaporator preheater was put on-line, heat transfer coefficients for boiling DI water were calculated to be in excess of 250 Btu/hr-ft²-°F. The evaporator performed well in an off-line test with a fresh 50% NaOH feed and produced a flaked caustic product with a moisture content of 5 to 6 percent. With regenerated caustic, however, the evaporator continued to experience periodic upsets.

Based on the results obtained from the vacuum filtration and caustic evaporation off-line tests, TRW recommended to the DOE project office that the program go forward with Task 6 continuous integrated operation.

1.3 OPERATIONS TEST RESULTS

Two weeks of Task 6 continuous around-the-clock operation of the refurbished/modified MCL test circuit were performed. Also as part of Task 6 operations, a wash train test using a new process configuration was performed in addition to scaleup tests in a 9-inch centrifuge. Since the nine weeks of operation from January to June 1989 during the Phase I program were called Runs 1 through 9, the two around-the-clock tests performed during the current program were called Runs 10 and 11.

1.3.1 Test Run No. 10

A week (5 days) of around-the-clock test operations, commencing on June 3, 1992, was conducted in the recently refurbished/modified MCL integrated test facility. This test operation was called Test Run No. 10. The three objectives of this week of continuous operations were:

- To perform a shakedown of the MCL facility, which had undergone significant refurbishments and design modifications, after having been dormant (and subject to out of doors exposure) for two years.
- To evaluate the long term performance characteristics of the recent design modifications to the facility (in particular those made to the filtration and evaporation units).
- To operate the MCL facility in an integrated fashion with all processing units on-stream at the same time.

During this test, for the first time, a substantial number of hours of on-stream time were logged for the vacuum filters operating in series with the rest of the water washing train. The caustic evaporation unit was put on-stream at the end of the week. However, the high level of coal fines (up to 85% minus 100 mesh) in the kiln discharge material and the resulting high coal fines losses to the vacuum filter filtrate (~25% of the feed material) during this test indicated that the three-year old coal from inventory used for this test might be weathered. Coal analysis were compared to the original analysis provided when the coal was purchased. The analysis indicated weathering as noted by the increase in sulfate sulfur and the decrease in heating value. Fresh coal was purchased for the remaining Phase II testing.

1.3.2 Test Run No. 11

A week (7 days) of around-the-clock test operations, commencing on May 14, 1992, was conducted in the MCL integrated test facility. This test operation was called Test Run No. 11. The objectives of this week of testing were:

- To demonstrate continuous, integrated operations of all the process components of the MCL facility with regenerated caustic recycled to the kiln.
- To simultaneously produce low sulfur product coal.

All sections of the plant were operated in an integrated fashion for an extended period of time. Fresh Pittsburgh coal was used. The test can be summarized as follows:

- A total of 650 pounds (dry basis) of product coal was produced during the test run, with product coal produced during a 90-hour period containing less than 0.3 wt% sulfur (less than 0.44 lbs SO₂/million Btu). This represents a 90% reduction in sulfur from the 4.5 lbs SO₂/million Btu for the raw run-of-mine (ROM) coal, thus meeting the most stringent U.S. standards. Product coal was produced with a sulfur content as low as 0.11 wt% (0.17 lbs SO₂/million Btu or 198 mg SO₂/Nm³) which corresponds to a 96% reduction in sulfur from ROM and which is one-half of the EC standard of 400 mg SO₂/Nm³.
- Approximately 9% of the caustic is being converted to carbonate.

- The acid wash train was operated at a number of different pH levels during the test run. Even without acidification, a very significant removal of ash from the product coal was achieved.
- A new process configuration was tested in which centrate from the acid wash train (without acid addition) was used as the water makeup for the water wash train. The coal product produced has a moderate ash level. This configuration eliminates the need for waste water treatment of the acid wash centrate and has the potential of large cost savings to the process.
- The caustic evaporator performed as expected based on pre-run off-line tests. A total of 119 hours of run time was achieved for this unit. Regenerated caustic flake was produced and recycled to the kiln.

1.3.3 Wash Train Test Following Run No. 11

A wash train test was performed utilizing kiln discharge solids collected during Run No. 11 to test a new process configuration in which an acid wash of the MCL coal product was not performed, although the acid wash train equipment (consisting of three centrifuges) was used for additional stages of water washing. The centrate from the acid wash train (without acid injection) was used as makeup wash water for the water wash train. This test duplicated part of Run No. 11 when this new test configuration was first used. Eliminating acid washing had no effect on the sulfur levels of the product coal but increased the ash levels and has the potential of significantly reducing the cost of the process for those commercial applications that do not require low ash coal.

1.3.4 Coal/Water Separation Tests

A series of MCL coal/water separation tests were performed in a 9-inch solid bowl centrifuge. The objective of these tests was to generate scaleup data on centrifuge performance with MCL coal in a machine that is more representative (L/D ratio) of commercial equipment than the 6-inch solid bowl centrifuges used to date in the MCL integrated test facility. The tests with the 9-inch centrifuge were conducted at various flow rates (up to 400 lbs/hr of coal feed) over a range of feed water to coal ratios including an operating point (5:1 water:coal) close to that expected in a full scale MCL plant. This represents a twenty-fold scaleup factor over the MCL integrated test facility.

1.4 RECOMMENDATIONS

It is recommended that the U.S. Government review its position regarding further funding of the MCL technology in order to provide key data that is still required prior to full pilot/commercial demonstration. The further testing required is as follows:

- Evaluation of the coal-derived mineral matter reject from Section 400. The current program only funds simple precipitation of this mineral matter reject in order that the regenerated caustic can be successfully recycled and reused many times. This reject needs to be stabilized and washed to recover absorbed caustic and to provide a landfill material consisting of cementitious silica, alumina and gypsum. The testing required includes:
 - Operation of the complete molten caustic leaching integrated test circuit to produce quantities of mineral matter reject,
 - Addition of washing stages or off-line use of the existing wash train to cleanup the reject and recover absorbed caustic,
 - Heat treatment and roasting operations to stabilize the cementitious mineral matter, and
 - Applications testing of the thus stabilized purified product.
- Product coal applications. The several tons of product coal produced during the mineral matter reject study described above need to be evaluated as pulverized fuel, as briquetted fuel and as coal water slurry, and for application as a toxic water cleanup medium.

Accomplishment of these tests will answer the major questions still associated with the MCL Process as to the environmental impact of the process mineral matter reject and applications of the MCL product coal. The process should then be ready for application both in the United States and on a world-wide export basis.

1.5 REPORT OUTLINE

The following sections of this report contain a description of the June 1991 week of testing (Run No. 10), the May 1992 week of integrated testing (Run No. 11), the wash train test of the new process configuration, and scaleup tests in a 9-inch centrifuge.

2. TEST RUN NO. 10 (JUNE 3 TO 7, 1991)

A week (5 days) of around-the-clock test operations, commencing on June 3, 1991, was conducted with the recently refurbished/modified MCL integrated test facility. The three objectives of this week of continuous operations were:

- 1) To perform a shakedown of the MCL facility, which had undergone significant refurbishments and design modifications after having been dormant for two years (the last integrated MCL test (Run No. 9) was completed on June 2, 1989). Most of the plant equipment is located out of doors and the effect, if any, of non-operational exposure to the elements on elastomeric materials, normally lubricated components, carbon steel parts, etc. was uncertain.
- 2) To evaluate the long term performance characteristics of the recent design modifications to the facility (in particular those made to the filtration and evaporation units) which to this point have undergone only short duration (~4 hours) off-line testing.
- 3) To operate the MCL facility in an integrated fashion with all processing units on-stream at the same time.

The week of test operations successfully met objective (1) above. Each process component of the facility was operated and a number of equipment items were identified that will require maintenance/refurbishment before the next long-term test of the plant.

The week of test operations also provided long-term performance data as outlined in objective (2) above. In particular, a substantial number of hours of on-stream time was logged, for the first time, for the vacuum filters operating in series with the rest of the water washing train. The design modifications made to the filters, which resulted in good off-line test results, also lived up to expectations in this long duration test run. Problems with filter cloth blinding and excessive coal fines losses to the filtrate were traced to the weathered (highly friable) coal that was used during this test run.

Unfortunately, an area wide power outage occurred at 01:30 on June 7 (the last day of the test run) and lasted for an hour, followed by a number of

momentary power outages until 06:30. Despite the power outages, the evaporation unit was put on-stream at 12:15 on June 7 and operated (in conjunction with the regeneration unit) for approximately 5 hours. The evaporation unit performed well, processing regenerated solution and producing flake of low moisture content (5 to 7 percent). The evaporation unit, however, continued to experience the periodic upsets that were noticed in earlier Phase I tests.

If the area wide power outage had not occurred when it was too late in the week to recover fully from it, objective (3) above would have been met and all units of the MCL facility would have been on-stream at the same time. (The kiln and the wash trains had been shutdown as a result of the power outages before the evaporator was brought on-line.)

For a detailed description of the modifications that had been made to the vacuum filters and the evaporation unit and a description of the off-line circuit component tests performed prior to this test run see the report entitled "Topical Report for Test Circuit Maintenance, Refurbishment, Modification, and Off-Line Operations" for Phase II of the Molten Caustic Leaching System Integration Project.

2.1 CHRONOLOGY OF OPERATIONS

A chronology of plant operations for the week of testing is given in Figure 2-1. Notes have been appended to this figure describing the causes of the major disruptions to plant operations.

A detailed discussion of the operation of each of the individual plant sections follows.

2.2 KILN OPERATIONS (SECTION 100)

2.2.1 Test Description

The kiln operating conditions for Run No. 10 are summarized in Table 2-1. All the operations for the week were conducted with a 2:1 caustic:coal mixture being fed to the kiln. The caustic consisted of fresh sodium hydroxide (NaOH) bead. Three-year old Pittsburgh No. 8, 14 mesh coal

	6/3	6/4	6/5	6/6	6/7
KILN	<div> <div>(1)</div> <div>(2)</div> </div>				
WASH TRAINS	<div> <div>(3)</div> <div>(4)</div> <div>(5)</div> <div>(6)</div> <div>(7)</div> </div>				
REGENERATION	<div> <div>(7)</div> </div>				
EVAPORATION	<div> <div>(7)</div> </div>				

2-3

- (1) Kiln heaters down for ~1 hour due to malfunctioning overtemperature switch.
- (2) Kiln down for ~1 hour due to area wide power outage.
- (3) Stopped solids feed to wash train to clear plugs in wash train equipment.
- (4) Second vacuum filter taken out of service.
- (5) Wash train taken out of service due to sudden high discharge rate of solids from kiln.
- (6) Stopped solids feed to wash train to clear plugs in wash train equipment.
- (7) Filtrate flowed into the regeneration unit for ~4 hours. The additional time logged was with this charge of material in the regeneration reactor at a temperature of 150°F.

TABLE 2-1

Run Condition Summary

Operating Run No. 10, 6/3-6/7/91

Run No.	Operating Time Span for Kiln		Coal Type	Caustic Type	Caustic:Coal	Kiln Feed Rate, lbs/hr	Kiln Skip* Temps °C
	Date From/To	Time From/To					
10A	6/03	0150-1530	Pittsburgh #8 14 Mesh	NaOH, fresh	2:1	~40	380
10B	6/03 6/04	1530 - 0640	Pittsburgh #8 14 Mesh	NaOH, fresh	2:1	~27	380
10C	6/04 6/05	0640 - 0125	Pittsburgh #8 14 Mesh	NaOH, fresh	2:1	~27	360
10D	6/05 6/07	0125 - 1000	Pittsburgh #8 14 Mesh	NaOH, fresh	2:1	~27	400

* It has been calculated that it takes ~8 hours for the coal to get through the kiln and wash trains. Therefore, when relating product coal collected to kiln conditions, this 8 hour lag time must be taken into account.

** Internally measured temperature is 25 to 50°C lower.

(leftover from the previous Phase I program) was utilized as the feed coal. A schematic of the rotary kiln reactor system is shown in Figure 2-2.

During Run 10A the solids mix was fed to the kiln at a rate of ~40 lbs/hour. The kiln was inclined at a slope 1/8-inch per foot and was rotated at a speed of 1 RPM. No solids were observed to backup into the kiln feed breech. The solids feed rate of ~40 lbs/hour was considerably higher than the feed rates (20 to 30 lbs/hr) employed during the Phase I MCL program (except for several hours during Run No. 6 when feed rates up to 53 lbs/hr were employed). The kiln skin temperatures in all four (4) heated zones of the kiln were controlled at 380°C (716°F).

The kiln solids feed rate was reduced to ~27 lbs/hour during Run 10B with all other kiln conditions unchanged. The reduction in kiln feed was made in an attempt to alleviate operating problems in the wash train, which at the times were perceived to be due to an excessive solids loading (see Section 2.3.2).

In Run 10C the kiln skin temperatures were reduced from 380°C to 360°C. This change also was made to alleviate problems (filter cloth blinding) in the wash train.

Finally in Run 10D the kiln skin temperatures were increased to 400°C. Run 10D accounts for ~60% of the total hours logged for the kiln during the week of operations. The solids feed rate for Run 10D was ~27 lbs/hr.

Unfortunately, an area wide power outage occurred during Run 10D at 01:30 on Friday June 7 and lasted for an hour. During this time the kiln was rotated manually to avoid warpage of the kiln tube. The kiln temperatures dropped from ~400°C to ~260°C (~500°F) during the power outage. A number of momentary power outages were also experienced until 06:30. By this time the wash train was depleted of solids since the kiln discharge solids were bagged during the power outages. Since the time remaining in the test week was insufficient to re-establish steady-state in the wash train, it was decided to shutdown the kiln and wash trains. Thus neither the kiln nor the wash train was on-line when the evaporator was put on-stream at 12:15 on June 7 (see Figure 2-1).

CONTRACT NO. DE-AC22-86-PC31257	CFD-1	1/93
U.S. DEPARTMENT OF ENERGY		
PITTSBURGH ENERGY TECHNOLOGY CENTER		
DRUM	JLA	3-90
CHECKED		
ENGINEER		
APPROVAL		
SECTION 108		
REACTION SECTION		
CONCEPTUAL FLOW DIAGRAM		
SCALE	REV 1	SHEET 1 OF

Figure 2-2. Rotary Kiln Reaction System

2.2.2 Kiln Feed Rate

A total of 2,890 pounds of 2:1 caustic:coal mix was added to the kiln feed hopper during the week of test operations. The amount of solids remaining in the feed hopper at the end of the run was not recorded. However, the kiln was fed for a total of 94 hours-30 minutes as follows: 13 hours-40 minutes with the feed screw set at 0.625 RPM (Run 10A) and 80 hours-50 minutes with the screw set at 0.417 RPM (Runs 10B, 10C and 10D). The kiln feed rates and total solids fed for each of the runs were calculated and are summarized as follows:

<u>RUN NUMBER</u>	<u>KILN FEED RATE, LBS/HR</u>	<u>TIME</u>	<u>POUNDS</u>
10A	40.9	13hr-40min	559
10B	27.3	80hr-50min	2207
10C	27.3		
10D	27.3		
			<u>2766</u>

This calculation which estimates that ~2766 pounds of material were actually screw fed into the kiln is based on the assumption that the kiln feed hopper (4.3 ft³ capacity) was ~50% full at the end of the run. The maximum variation in feed rate, if the feed hopper was either empty or full at the end of the run (versus the 50% full assumed), is $\pm 5\%$, assuming a coal:caustic mix density of 55 lb/ft³.

2.2.3 Kiln Discharge Rate

During this week of kiln operations, the discharge rate of solids from the kiln was observed to be erratic. During a period of wash train upset due to a plug, the kiln discharge solids were collected in plastic bags (see note 6 in Figure 2-1). Figure 2-3 is a plot of kiln discharge rate versus time over a period of approximately 13 hours on June 6 (Run 10D). The discharge rate was at times as much as 40% above or 30% below the average discharge rate for this period of 24.5 lbs/hr (318.6 pounds collected over 13 hours). The average discharge rate, however, is what would be expected at the prevailing kiln feed rate (27.3 lbs/hr). It was concluded that the kiln was in a steady-state condition and that an erratic discharge rate may be

KILN DISCHARGE RATE VERSUS TIME
KILN WALL TEMPERATURE = 750°F (400°C)

Figure 2-3. Kiln Discharge Rate vs. Time, Run 10D
Kiln Wall Temperature = 750°F (400°C)

characteristic of this piece of equipment. However, this erratic discharge rate of solids had an effect on the wash train and, in particular, on the vacuum filters which are the first pieces of equipment in the wash train (see Figure 2-4). The effect of an erratic discharge rate from the kiln is dampened out as the coal moves down the wash train due to the solids inventory in each reslurry tank (Figure 2-4). This characteristic of kiln operation became apparent during the Phase I program and methods of smoothing the flow (increased line sizes, larger pumps, continuous circulation through the filter feed pan with spillback, and computer control of levels in the filter feed and filtrate tanks) were incorporated during the Task 2 modification of the vacuum filter system.

2.2.4 Sulfur, Ash and Volatiles

Several samples were taken of kiln discharge solids. The analytical results are presented in Table 2-2. The trends in sulfur and ash removal and volatiles content are consistent with the increase in kiln skin temperature from 380°C in Runs 10A and 10B to 400°C in Run 10D, with higher sulfur and ash removal and devolatilization at the higher temperature.

2.3 WASH TRAIN OPERATIONS (SECTIONS 200 AND 300)

2.3.1 Background

One of the Phase II plant modifications having the highest priority was to upgrade the vacuum filtration system to allow for operation with caustic concentrations up to 50% in the water washing system. The inability to operate the vacuum filters in a continuous and reliable mode during the Phase I test operations in 1989 due to intermittent flows to and from the filters resulted in the vacuum filters being bypassed and in the use of excess wash water in order to bring the caustic concentration down to a level (<15% caustic) that would allow for separations in the downstream centrifuges. When doing this, the evaporation system became overloaded with respect to the amount of water that had to be evaporated in order to recover and recycle anhydrous caustic. One of the purposes of the current Phase II program was to modify the vacuum filter system to perform as designed, so that the two vacuum filter separations could be made at higher caustic concentrations and that the aqueous caustic leaving the wash system and

Figure 2-4. Water Washing System

TABLE 2-2. KILN DISCHARGE SOLIDS ANALYTICAL RESULTS
MCL TEST RUN NO. 10

RUN NO.	KILN TEMP. (°C)	NO. OF DATA POINTS	% S	% ASH	% VOLATILES
10A	380	1	1.58	0.86	37.15
10B	380	1	1.49	0.78	34.48
10D	400	1	1.02	0.42	30.28

feeding the regeneration system would range from 30 to 50% caustic. The evaporator then would be able to process the caustic to anhydrous and allow for caustic recycle, completing the integration of all the plant unit operations.

The vacuum filter system was extensively modified during Tasks 1 and 2 of the current Phase II program. The system was replumbed so that the flow rates to the filters were greatly increased (spillback lines to the dissolver/feed tanks were provided along with filtrate recycle). Line sizes were increased and the feed pumps to the filters were replaced with higher capacity pumps. Level switches in the filtrate tanks were replaced with bubbler level indicators. The level indicators in the filtrate and dissolver/feed tanks are now fed to the computer which automatically adjusts four newly installed control valves such that the levels in the tanks are maintained at preset levels by recycling some filtrate back to the dissolver/feed tanks. Figure 2-5 is a schematic of the replumbed, automated filtration system.

Six off-line vacuum filter tests were performed between February and May 1991 as part of Task 3. Four successful off-line filter tests of the modified system using manual control were performed followed by two successful off-line filter tests in the automatic control mode. Filtrates with caustic concentrations of up to ~34% were produced. Based on the results of the off-line vacuum filter tests, TRW recommended to the DOE project office that the program go forward with Task 6 continuous integrated test operation.

2.3.2 Test Description

The entire water wash train (2 vacuum filters, 5 centrifuges) and the acid wash train (3 centrifuges) were put into operation at the start of the Test Run No. 10. Schematics of the water wash system and the acid wash system are shown in Figures 2-4 and 2-6, respectively.

Approximately 3 hours after the first kiln solids entered the dissolver tank, T-101, a decision was made to bypass the fourth centrifuge, C-204, in the water wash train because of excess leakage at the case end of the

REVISIONS		
LTR	DESCRIPTION	DATE

T-304
PRODUCT COAL
RECEIVER

T-302, T-303
SLURRY TANKS

C-301, C-302, C-303
CENTRIFUGES

T-301
ACID CONTACTOR

CONTRACT NO. DE-AC22-80-PC31237 U.S. DEPARTMENT OF ENERGY PITTSBURGH ENERGY TECHNOLOGY CENTER				CFD-3	1/93
DRAWING		JLA	3-90	SECTION 300 ACID WASHING CONCEPTUAL FLOW DIAGRAM	
CHECKED					
ENGINEER					
APPROVAL				SCALE	REV 1 SHEET 1 OF

Figure 2-6. Acid Washing System

machine. This centrifuge had been disassembled prior to this test run for inspection/replacement of the seals and bearings. It had been reassembled per instructions of a Bird Machinery representative who visited the test site.

Approximately 28 hours after the first introduction of solids into the wash train, the second vacuum filter, F-202, was taken out of service. This unit was not forming sufficient filter cake on the drum to keep up with the solids input to the system. It appeared that the filter cloth was blinding. Both filters were dressed with 40 mesh filter cloths (the same cloths used in the preceding off-line filter test). A number of computer control software changes had to be made to bypass F-202. Also, a stator/rotor had to be replaced in feed pump P-203 to change it from filter (high flow) to centrifuge (low flow) service. The changes were completed in approximately 6 hours at which time kiln discharge solids (which were being collected in bags) were again fed into the dissolver tank.

Problems were experienced from the start of the test run in controlling the level in tanks T-209 (C-203 feed tank) and T-210 (C-203 cake reslurry tank, see Figure 2-4). This necessitated the periodic draining of slurry from these tanks. Consequently, very little coal was reaching the acid wash train and thus very little coal was being collected as product coal. It was initially suspected that problems were experienced with the progressive cavity pumps that pump the slurry out of tanks T-209 and T-210. A stator was replaced in one of the pumps with no resultant improvement in operations. The problem was eventually traced to the C-203 centrifuge which was completely plugged with coal - probably residual coal from the Phase I program. (This was not one of the centrifuges that was disassembled for refurbishment.) At this point, 75 hours after the start of solids flow into the wash train, C-203 was bypassed and C-204 put back on-stream. The wash train worked well from this time until the end of the test run. In fact, product coal was now being collected from the final centrifuge, C-303, in the acid wash system (see Figure 2-6) at about the expected rate.

The water wash train problems were apparently solved by late in the evening of June 6, the fourth day of the test run. In fact, calculations

indicated that steady-state had been reached in the water wash system by this time. Regeneration operations had been initiated at 22:40 on June 5 and the plan was to put the evaporation unit on-line early on June 7. Unfortunately, an area wide power outage occurred at 01:30 on June 7 and lasted for an hour, followed by a number of momentary power outages until 06:30. By this time the wash train was depleted of solids (kiln discharge solids were bagged during the power outages). Since the time remaining in the test week was limited (the plan was to shutdown on Friday June 7 and cleanup the plant) and thus insufficient to re-establish steady-state in the wash train, it was decided to shutdown the kiln and wash trains. Thus the wash train was not on-line when the evaporator was put on-stream at 12:15 on June 7.

During this week of testing, problems with filter cloth blinding became apparent after several hours of operation had elapsed. Blinding problems did not surface during the off-line tests to date which generally lasted less than four hours.

2.3.3 Material Balance

A material balance was performed which indicated that a close to steady-state condition had been achieved in the wash train. The material balance calculation details are shown in Table 2-3. A material balance closure of 95% (in/out) was achieved.

2.3.4 Coal Fines/Size Distribution

In reviewing the material balance calculation in Table 2-3, it was noted that the coal loss to filtrate fines was quite high, ~25% of the coal fed to the dissolver. A high fines content was seen in all of the F-201 filtrate samples taken during the test run (see Table 2-4).

A size distribution was performed on a sample of kiln discharge coal collected on June 5 at 15:15 (not in material balance period). The screen analysis is presented in Table 2-5 and shows a much higher (85.6%) minus 100 mesh cut than was seen for any of the kiln discharge coals analyzed in the Phase I program which averaged about 39% minus 100 mesh. A screening of a second kiln discharge sample, collected about an hour earlier in the test

TABLE 2-3. KILN MATERIAL BALANCE - MCL TEST RUN NO. 10
(FOR THE PERIOD JUNE 6, 20:15 TO JUNE 7, 00:15)

-
1. 'Average' kiln processed coal fed to dissolver tank, T-101

= Coal feed to kiln - Coal weight loss in kiln*

* Coal weight loss in kiln is due to moisture vaporization, gas make, desulfurization, deashing, and carbonate make. Based on the product coal sulfur and ash analysis, a feed coal moisture content of 2.6%, and coal conversions to gas and carbonate from the Phase I program at similar kiln conditions, a coal weight loss of ~20% in transit through the kiln was estimated.

Thus, 'Average' kiln processed coal to T-101

= 9.0 lbs/hr - 0.2 x 9.0 lbs/hr = 7.2 lbs/hr

2. 'Average' wet product coal collected from centrifuge C-303

= 12.9 lbs/hr

Lbs/hr dry product coal, based on 1.3 parts moisture per part dry coal = (12.9 lbs/hr)/2.3 = 5.6 lbs/hr

3. Coal fines loss to filtrate stream to regeneration (based on sample taken @ June 5, 20:00 - not in material balance time period):

Wt% fines in F-201 filtrate = 2.77%

%NaOH in filtrate = 24.2%

Filtrate flow (based on 18 lbs/hr average NaOH flow into T-101 from kiln)

= (18 lbs/hr)/(0.242 wt fraction NaOH) = 74.4 lbs/hr

Thus, coal fines loss to filtrate = 74.4 lbs/hr x 0.0277

= 2.0 lbs/hr

Coal into wash train = stream (1) = 7.2 lbs/hr

Coal out of wash train = streams (2) + (3)

= 5.6 + 2.0 lbs/hr = 7.6 lbs/hr

or material balance closure

= (7.2 lbs/hr)/(7.6 lbs/hr) x 100 = 95%

TABLE 2-4. COAL FINES IN FILTRATE SAMPLES

DATE	TIME	COAL FINES, %
6/5/91	08:20	4.82
6/5	15:45	1.83
6/5	16:50	1.96
6/5	20:00	2.77*

* Data point used in item 3 of kiln material balance shown in Table 2-3.

TABLE 2-5. KILN DISCHARGE COAL SIZE DISTRIBUTION

% Retained On:	First Kiln Discharge Coal Sample 6/5 15:15	Second Kiln Discharge Coal Sample Collected 6/5 13:40	
		'Chunk' Portion	"Powder" Portion
40 mesh screen	0.21	0.22	3.99
60 mesh screen	1.67	1.56	18.95
80 mesh screen	6.26	6.47	12.72
100 mesh screen	7.10	7.37	6.98
200 mesh screen	37.37	37.28	22.69
collected in pan	48.23	47.54	34.91
	85.60	84.82	57.60 <100 mesh

run, was performed to confirm the initial findings. The second kiln discharge sample was segregated into its 'powdery' and 'chunk' forms to determine the importance of selecting a 'representative' sample for the screening analysis. The results of the screenings are presented in Table 2-5.

As can be seen, the 'chunk' portion of the second kiln discharge coal sample had a size consist almost identical to the kiln discharge material analyzed earlier. Most likely, the operator selectively chose the 'chunk' form when sending the first kiln discharge sample for analysis. The 'powder' form of the kiln discharge sample actually has a much lower (57.6%) minus 100 mesh content than the chunk form. This is probably related to the greater surface adhesion of the small particles that make up the chunks.

The high fines content of the kiln discharge coal could explain the high fines loss to the filtrate. Screenings were also performed on two wash train product coal samples. The results are shown in Table 2-6. In comparing the size consist of the product coal with those obtained in the Phase I program, it appears that the coal product at about 77 to 81% minus 200 mesh is considerably reduced in particle size from coal produced in the Phase I program (~67% minus 200 mesh).

The problems with filtration during this test run indicated that there was evidence that the three-year old Pittsburgh coal in inventory at TRW used for this test might be weathered. Coal samples were analyzed for comparison to the original analysis provided when the coal was purchased in June 1988. The analysis indicated weathering as noted by the increase in sulfate sulfur and the decrease in heating value (Table 2-7). It is believed that the weathering of the coal was responsible for the high level of coal fines (up to 85% minus 100 mesh) in the kiln discharge material, for the high losses of coal fines to the filtrate (~25% of the feed material), and for the blinding of the filter cloth during this test run. Weathered coal is highly friable. Based on this information, it was concluded that it was risky to attempt further integrated tests using the coal feedstocks in inventory since control of fines losses and fines content of the feed slurries to the dewatering equipment was critical to successful operation of the plant. As a result,

TABLE 2-6. PRODUCT COAL SIZE DISTRIBUTION

% Retained On:	Sample 1	Sample 2	Phase I Program 'Typical'
100 mesh screen	3.42	4.47	12
150 mesh screen	7.53	7.82	
200 mesh screen	8.22	10.61	21
325 mesh screen	14.38	22.91	
collected in pan	66.44	54.19	
	80.82	77.10	67% <200 mesh

TABLE 2-7. COMPARISON OF ANALYSES FOR PITTSBURGH NO. 8 COAL

LOT NO.	10		4		6		7
	JUNE 88	JUNE 91	JUNE 88	JULY 91	JUNE 88	JULY 91	
DATE*							
SULFUR FORMS, wt% (dry)							
PYRITIC	1.87	0.95	1.79	1.52	1.89	1.74	0.26
SULFATE	0.03	0.66	0.02	0.60	0.02	0.28	0.58
ORGANIC	2.36	2.59	2.46	2.30	2.30	2.46	3.62
TOTAL	4.26	4.20	4.27	4.42	4.21	4.48	4.46
HHV, Btu/lb (dry)	13,219	12,785	13,114	12,665	13,065	12,870	12,646
MOISTURE, wt%	2.84	2.75	2.39	2.07	2.74	2.16	2.08

* June 88 analyses by Tra-Det
June 91 and July 91 analyses by Warner Labs

fresh coal was purchased for the remaining Phase II testing and the coal in inventory at TRW was disposed of (it was sent to a coal-fired power plant where it was burned).

2.3.5 Product Coal Analysis

Several samples of the wash train product coal were collected for analysis during Run 10D (kiln temperature = 400°C). The results of the product coal analysis are presented in Table 2-8. Feed coal analyses from 1988 are presented in Table 2-9.

2.3.5.1 Sulfur Removal

On the average, the product coal contained 1.52 lbs SO₂/million Btu. Based on a value of 6.55 lbs SO₂/million Btu for the Pittsburgh No. 8 feed coal fed to the kiln and a value of 11.10 lbs SO₂/million Btu for run-of-mine Pittsburgh No. 8, sulfur reductions achieved were 76.8% SO₂ removed from the feed coal and 86.4% from run-of-mine coal.

2.3.5.2 Ash, Volatiles and Heating Value

On the average, the product coal contained 0.82 wt% ash (see Table 2-8). Based on a value of 11.57 wt% ash for the Pittsburgh No. 8 coal fed to the kiln (see Table 2-9), the ash reduction achieved was ~93%. The product coal has retained a relatively high volatiles content (average volatiles = 30.37% versus 38.6% for the feed coal) and high heating value (average MAF heating value = 13,650 Btu/lb versus 14,719 for the feed coal) which reflect the mild kiln treating conditions utilized.

2.3.6 Product Coal Moisture

The moisture contents of the product coal samples collected for analysis during Run 10D are presented in Table 2-10. On the average, the product coal collected contained 1.23 parts of moisture per part of dry coal.

2.3.7 Observations

A total of ~150 pounds of product coal (wet basis) was collected during the week of operations. As was mentioned in Section 2.3.2 above, it was not until essentially the last full day of operation that the bottleneck (plugged

TABLE 2-8. PRODUCT COAL ANALYTICAL RESULTS
MCL TEST RUN 10D (400°C KILN WALL TEMPERATURE)

DATE	TIME	ANALYZER	WT% S	WT% ASH	WT% VOLATILES	MAF HEATING VALUE, BTU/LB
6/5/91	20:00	TRW	1.08	0.79	35.04	-
		WARNER LABS	1.01	0.99	29.05	13,764
6/6	20:15	TRW	1.00	1.18	31.67	-
		WARNER LABS	0.97	1.14	28.37	13,626
6/7	00:15	TRW	1.07	0.48	30.93	-
		WARNER LABS	1.06	0.38	28.08	13,573
6/7	04:00	TRW	1.06	0.65	32.03	-
		WARNER LABS	1.05	0.95	27.82	13,636
		AVERAGE	1.04	0.82	30.37	13,650

TABLE 2-9. FEED COAL ANALYSIS (1988)

Coal	Dry Basis, wt%			Heat Content, Btu/Lb		Lbs SO ₂ / Million Btu
	Sulfur	Ash	Vols	MF	MAF	
Pittsburgh No. 8*						
Run of Mine	5.08	34.90	--	9144	--	11.10
Mine Cleaned	4.27	11.57	38.60	13016	14719	6.55

* Powhatan No. 6 Mine (Powhatan Point, Ohio) Nacco Division, North American Coal Company

TABLE 2-10. PRODUCT COAL MOISTURE LEVELS
MCL TEST RUN 10D (400°C KILN WALL TEMPERATURE)

DATE	TIME	WT% SOLIDS	LBS MOISTURE TO LB DRY COAL RATIO
6/5/91	20:00	45.36	1.20
6/6	20:15	45.20	1.21
6/7	00:15	43.84	1.28
6/7	04:00	44.69	1.24
AVERAGE		44.77	1.23

centrifuge C-203) in the wash train was removed and significant quantities of coal were collected at the discharge of the acid wash train.

The design modifications made to the vacuum filters (increased line sizes, larger pumps, continuous circulation through the filter feed pan with spillback, and computer control of levels in the filter feed and filtrate tanks) performed very well during the test run. There were problems with the filtrate system due to the large quantity of coal fines which were traced to weathered feed coal. Fresh coal will be used for the remaining Phase II testing. In addition, the 40 mesh filter cloth size used on both filters will be reevaluated as a means of reducing the fines loss to the filtrate.

Because of equipment problems (plugs) caused by residual coal left in the system from earlier tests, the procedures for water flushing the equipment after each test were modified.

2.4 CAUSTIC REGENERATION OPERATIONS (SECTION 400)

2.4.1 Test Description

A schematic of the caustic regeneration system is shown in Figure 2-7. The regeneration unit was put on stream at 22:40 on June 5. Starting at this time, filtrate from vacuum filter F-201 was processed through bag filter F-203 (for removal of coal fines) and sent to stirred tank regeneration reactor T-401. (Prior to this time, the filtrate was sent directly to waste storage and was eventually hauled away by a waste disposal company.) Caustic bead was metered into tank T-401 by a screw feeder to increase the caustic concentration of the filtrate from an estimated value of ~25% to ~45%. This was done in an attempt to precipitate carbonate from the regenerating solution before the solution was fed to the evaporation unit. Excess carbonate in the caustic solution could cause tube scaling in the evaporation unit. The incoming filtrate/NaOH bead was mixed with a small amount of fresh 50% NaOH solution which was added earlier to tank T-401 to provide a mixing and heat sink for the dissolving NaOH bead. Filtrate/bead was added to T-401 until 02:15 on June 6 when a disruption in the wash train due to a plug caused the operators to discontinue kiln solids flow into dissolver tank, T-101 (see notes 6 and 7 on Figure 2-1). No lime was added to tank T-401 during the test run.

Figure 2-7. Caustic Regeneration System

The contents of T-401 were maintained at -150°F by band heaters on the tank. Through an oversight, the NaOH bead screw feeder was not shut off at the same time as the filtrate flow into T-401. By the time this was noticed, a substantial amount of undissolved caustic had accumulated in the cone bottom of T-401, blocking the discharge from the tank. Water was added to T-401, and the tank was stirred until the caustic had dissolved.

It was estimated that ~20 gallons of F-201 filtrate was added to T-401 between 22:40 on June 5 and 02:15 on June 6. The contents of T-401 were continuously agitated and maintained at 150°F until 13:00 on June 7 (approximately 35 hours from the time filtrate flow to T-401 was discontinued). By this time the caustic evaporator, which had been started up about an hour earlier (at 12:15) with fresh 50% caustic feed, was ready to be switched over to regenerated caustic feed. At this time, the contents of T-401 were pumped into the second regeneration reactor, T-402 (see Figure 2-7). A small amount of fresh 50% NaOH solution had been added to T-402 prior to this transfer operation. This was to assure that the mixing blades in T-402 were immersed in solution in order to keep precipitated solids in suspension once the transfer of the contents of T-401 to T-402 was started. The regenerated solution was then pumped from T-402 to centrifuge C-401, and the centrate collected in centrate tank, T-404 (see Figure 2-7). Finally, the centrate (regenerated solution) was pumped through bag filters F-401/402 into the evaporator feed tank, T-405. Samples were taken upstream of the centrifuge and downstream of the bag filter. The analytical results for these samples are presented in Tables 2-11 and 2-12.

2.4.2 Carbonate Removal

As can be seen in Table 2-11, approximately 50% of the carbonate present in the regenerated solution had precipitated and was removed in the centrifuge/bag filters. There was no significant amount of cake discharged from the centrifuge. However, given the relatively small volume of liquid fed to the centrifuge and the low carbonate content of the feed solution, it is likely that much of the precipitate separated in the centrifuge had not had a chance to work its way out of the centrifuge bowl before the test was terminated.

TABLE 2-11. REGENERATION UNIT - CARBONATE ANALYTICAL RESULTS
MCL TEST RUN NO. 10D

SAMPLE	WT% ALKALINITY	WT% CARBONATE
CENTRIFUGE FEED	42.84	3.75
CENTRIFUGE/BAG FILTER EFFLUENT SOLUTION	40.49	1.81

TABLE 2-12. REGENERATION UNIT - SILICA, ALUMINA, IRON, SULFUR AND HUMICS
ANALYTICAL RESULTS - MCL TEST RUN NO. 10D

SAMPLE	Si (ppm)	Al (ppm)	Fe (ppm)	S (wt%)	HUMICS (wt%)	COAL FINES (wt%)
CENTRIFUGE FEED	888	254	116	0.13	0.018	0.13
CENTRIFUGE/ BAG FILTER EFFLUENT SOLUTION	846	230	95	0.09	0.005	0.02

2.4.3 Silica, Alumina, Iron, Sulfur and Humics Removal

As can be seen in Table 2-12, little, if any, silica, alumina, iron and sulfur compounds were removed in the centrifuge/bag filters as precipitate. This is not surprising since in a once through mode of operation (no regenerated caustic recycled to the kiln), it is unlikely that the solubility limits for the silica, alumina, iron and sulfur compounds in caustic would be reached.

A significant percentage of humics appeared to have precipitated from solution in the regeneration reactor, T-401, and was removed in the centrifuge/bag filter. The centrifuge/bag filter also appeared to be quite effective in reducing the coal fines content of the regenerated solution.

2.5 CAUSTIC EVAPORATION OPERATIONS (SECTION 500)

2.5.1 Background

One of the Phase II plant modifications having the highest priority was to upgrade the evaporation unit to operate as designed. The evaporation system was not operated during most of the Phase I test operations because the vacuum filters were bypassed and the caustic solutions produced were too dilute for the evaporator. However, off-line evaporator tests during Phase I experienced limited throughput, low overall heat transfer coefficients, and periodic surges or upsets. Fouling/plugging of the evaporator tubes was suspected.

In the current Phase II program, the overhead vent system on the evaporator was modified to reduce the back pressure and prevent flow surges and uneven evaporation rates. The line sizes on the evaporator vent were increased from 1 inch to 2 inches. A preheater was installed on the evaporator feed to remove the sensible heating requirement from the evaporator. Thus the evaporator is now used strictly for boiling. This should increase the overall heat transfer coefficient for the evaporator. Hot oil jacketing and improved thermal insulation were installed on the molten caustic line from the evaporator to the flaker in order to allow for operation with pure NaOH rather than the lower melting point NaOH/KOH mixture used during the Phase I program.

Analysis of scale from an evaporator tube indicated mainly nickel hydroxide and nickel oxide, the base metal of the Inconel tube. A evaporator test during Task 3 using DI water indicated that the tubes were clean and that the limited throughputs and the low overall heat transfer coefficients observed during Phase I testing were probably not due to scaling but to the large heat transfer surface area required for preheating the caustic to its initial boiling point. When the new evaporator preheater was put on-line, heat transfer coefficients for boiling DI water were calculated to be in excess of 250 Btu/hr-ft²-°F. The evaporator performed well in an off-line test with a fresh 50% NaOH feed and produced a flaked caustic product with a moisture content of 5 to 6 percent. With regenerated caustic, however, the evaporator continued to experience periodic upsets.

Based on the results obtained from the evaporation off-line tests, TRW recommended to the DOE project office that the program go forward with Task 6 continuous integrated operation.

2.5.2 Test Description

A schematic of the modified evaporation unit is shown in Figure 2-8. Regeneration operations had been initiated on June 5 and the plan was to put the evaporation unit on-line early on June 7. Unfortunately, an area wide power outage occurred at 01:30 on June 7 and lasted for an hour, followed by a number of momentary power outages until 06:30. By this time the wash train was depleted of solids (kiln discharge solids were bagged during the power outages). Since the time remaining in the test week was limited (the plan was to shutdown on Friday June 7 and cleanup the plant) and thus insufficient to re-establish steady-state in the wash train, it was decided to shutdown the kiln and wash trains. Thus neither the kiln nor the wash train was on-line when the evaporator was put on-stream (se Figure 2-1).

Fresh 50% NaOH caustic feed solution was started to the evaporation unit at 12:15 on June 7. The circulating hot oil temperature to the shell of the rising film evaporator was controlled at 700°F. The first caustic product flake was produced at approximately 12:25. The evaporator overhead temperature had reached 510°F by this time. The hot oil flow to the

recently installed caustic feed preheater, E-504, was adjusted to raise the caustic feed temperature from its storage temperature (in T-405) of -150°F to -275°F (the initial boiling point of 50% NaOH is 290°F).

Between 12:15 and $-13:00$, the caustic evaporator feed consisted of fresh, 50% NaOH solution which had been added to feed tank T-405. The feed rate for this period of operation was -140 lbs/hour. Flake production was -77 lbs/hour. The design feed rate for the evaporation unit when processing 50% caustic is 130 lbs/hour. (This is not the limiting rate; an alternative design case of 180 lbs/hour of 30% caustic is the limiting case for the unit.) An overall heat transfer coefficient of -53 Btu/hr-ft²- $^{\circ}\text{F}$ was calculated for this period of operation. This is considerably higher than the coefficients of -30 Btu/hr-ft²- $^{\circ}\text{F}$ obtained during the Phase I program when processing fresh 50% caustic. This improvement in heat transfer is most likely attributable to the recent addition of a feed preheat exchanger, E-504, which removed the sensible heating requirement from the evaporator. Preheating the feed solution in the tubes of the rising film evaporator is a very inefficient use of evaporator heating surface due to the poor heat transfer at the very low liquid velocities in the lower part of the tubes.

Starting at about 13:00, regenerated solution was pumped from regeneration reactor, T-402, through the centrifuge, into the evaporator feed tank, T-405 (to mix with the residual fresh 50% caustic still in that tank) and was fed to the evaporator. The test run continued until 17:00 when the time remaining in this last shift of the test week dictated that the evaporator be shutdown (the final shift of the week ended at 21:00) so it could be cooled down and thoroughly flushed with water. By this time the fresh caustic content of T-405 had long been displaced and the evaporator was being fed with only regenerated solution. The evaporation unit had been operated (in conjunction with the regeneration unit) for approximately 5 hours.

It was observed during the test run that the evaporation unit operated more smoothly with a fresh caustic feed than with a regenerated caustic feed. In fact, once the switch to regenerated caustic was made, the operators observed what they called the 'dragon effect'. That is, the

evaporator would periodically begin to 'roar' and then belch a larger than normal amount of molten caustic (and steam) into the pan of the flaker. This would upset the ability of the rotary drum flaker to solidify molten caustic. It also caused, because of the momentary high velocity of liquid/steam into the flaker pan, some spillage of the molten caustic over the edge of the pan. Once the unit had played the 'dragon', it would resume its normal mode of operation. These periodic upsets were also noticed in earlier Phase I evaporator tests. The causes of these periodic upsets are not completely understood. However, towards the end of the evaporator test run, it was discovered that by increasing the feed preheat using the recently installed feed preheater, E-504, to a temperature above the initial boiling point of the feed solution, the frequency and severity of the upsets could be eliminated, or at least reduced.

A total of ~320 pounds of caustic flake was produced during the test run. This calculates to an average production rate of 68 lbs/hour. This is an amount of caustic that is sufficient to support MCL plant operations at the following conditions: 15 lbs/hour coal feed to the kiln, 2:1 caustic:coal, 30% caustic in the filtrate to regeneration augmented to 50% caustic if necessary by addition of caustic bead to the regeneration reactor.

2.5.3 Moisture Content

Table 2-13 gives the moisture analysis of several samples of caustic flake taken during the test run. The flake moisture content varied from 4.9 to 7.5 wt%.

2.5.4 Observations

The recently installed hot oil jackets for the molten caustic piping, flanges and valves worked well. In fact, the utility of this recent evaporator modification was demonstrated before starting the evaporation test. When trying to flush the unit with water, a plug was discovered in the molten caustic line. This was probably caused by some residual caustic from the previous test run. By flowing hot oil through the jacketed pipe, the operators were able to melt the plug. This would not have been possible with the ineffective electrical tracing that was originally provided with the evaporation unit.

TABLE 2-13. CAUSTIC EVAPORATION UNIT
PRODUCT FLAKE MOISTURE CONTENT

DATE	TIME	FLAKE MOISTURE CONTENT, WT%
6/7/91	13:00	4.9
6/7	14:30	7.5
6/7	16:00	7.1

The recently installed hot oil heated caustic feed preheat exchanger, E-504, worked well. The feed to the evaporator was heated to as high a temperature as 350°F. It was observed that maximizing the preheat temperature had a very beneficial effect in 'smoothing out' the performance of the evaporator.

The new level controls installed for the steam condensate system worked well. These controls allowed condensate to be pumped from the evaporation unit to a water storage tank, T-601, for eventual recycle to the wash section.

It was observed that there was not sufficient cooling water flow to the flaker drum. This may have caused incomplete utilization of the drum surface and some spillover of molten caustic from the flaker pan.

3. TEST RUN NO. 11 (MAY 14 TO 21, 1992)

A week (7 days) of around-the-clock test operations, commencing on May 14, 1992, was conducted in the MCL integrated test facility. The goals of this test were: 1) to demonstrate continuous, integrated operations of all the process components of the MCL facility with regenerated caustic recycled to the kiln, and 2) to simultaneously produce low sulfur product coal.

Both of these goals were successfully met during the week of test operations. All sections of the plant were operated in an integrated fashion for an extended period of time. That is, the product from one unit operation became the feed to another unit operation while regenerated caustic was recycled to the kiln and Gravimelt coal was produced. A total of 152 operating hours were recorded for the kiln (Section 100), including ~95 hours feeding recycled regenerated caustic. Approximately 119 hours of operation were recorded for the caustic evaporation unit (Section 500). The wash and regeneration units (Sections 200/300 and 400) logged operating times of 137 hours and 124 hours, respectively. A total of ~650 pounds (dry basis) of product coal was produced during the run. Product coal produced during a 90-hour period contained less than 0.3 wt% sulfur (less than 0.44 lbs SO_2 /million Btu). This represents a 90% reduction in sulfur from the 4.5 lbs SO_2 /million Btu for the raw run-of-mine (ROM) coal, thus meeting the most stringent U.S. standards. Product coal was produced with a sulfur content as low as 0.11 wt% (0.17 lbs SO_2 /million Btu or 198 mg SO_2/Nm^3) which corresponds to a 96% reduction in sulfur from ROM and which is one-half of the EC standard of 400 mg SO_2/Nm^3 .

Some minor mechanical problems and short duration interruptions were experienced in some of the individual unit operations during the test. However, due to the presence of surge capacity (in the form of holding tanks as would also be present in a commercial plant), the MCL plant continued to operate in an integrated fashion for the seven day duration of the test.

A new process innovation was also successfully demonstrated during the test run. TRW was able to delete the acid washing of the coal and still

achieve a low sulfur, reduced ash product coal. For MCL coal applications that do not require an ultra low ash product, this process variation can offer significant cost savings.

3.1 CHRONOLOGY OF OPERATIONS

The previous around-the-clock test operations of the refurbished/modified MCL integrated test facility (Test Run No. 10) took place during the week of June 3, 1991. During that week, problems were experienced with excessive coal fines losses to the filtrate and with filter cloth blinding which were traced to the weathered (highly friable) feed coal that was used. The weathered coal in inventory at TRW was disposed of and fresh coal was purchased for the remaining tests.

A successful off-line test of the MCL rotary drum vacuum filtration system was conducted on May 1, 1992 at process conditions similar to those planned for the upcoming around-the-clock Test Run No. 11. The off-line test was conducted with a 100 mesh filter cloth on the rotary drum of the first vacuum filter, F-201, and with a 40 mesh cloth on the drum of F-202. (During Test Run No. 10, both filters were dressed with 40 mesh cloths.) Fines capture by the 100 mesh cloth was fairly complete, with fines losses to the filtrate of ~5% of the feed coal. For Test Run No. 11, the 40 mesh cloth on the second filter was also replaced with a 100 mesh cloth.

Test Run No. 11 took place during the week of May 14 through 21, 1992. A chronology of plant operations for the week of testing is given in Figure 3-1.

A detailed discussion of the operation of each of the individual plant sections follows.

3.2 KILN OPERATIONS (SECTION 100)

The recently acquired minus 14 mesh Pittsburgh No. 8 coal (CONSOL's Blacksville No. 2 or BV2) was utilized as the feed coal for Run No. 11. An analysis of the raw run-of-mine coal was given to TRW in April of 1992 by Dr.

FIGURE 3-1. MCL OPERATIONS CHRONOLOGY
TEST RUN NO. 11, 5/14-5/21/92

	5/14	5/15	5/16	5/17	5/18	5/19	5/20	5/21	
KILN									Σ = 152 Hrs
WASH TRAINS									Σ = 137 Hrs
REGENERATION									Σ = 124 Hrs
EVAPORATION									Σ = 119 Hrs

IMPROVEMENT IN ON-LINE TIME FROM PREVIOUS RUN (RUN 10, 6/2-6/7/91)

	<u>HOURS ON LINE</u>	
	<u>RUN 10</u>	<u>RUN 11</u>
KILN	103	152
WASH TRAINS	61	137
REGENERATION	41	124
EVAPORATION	5	119

Fonseca of the Consolidation Coal Company (CONSOL). This information is presented in Table 3-1. Dr. Fonseca said that these figures represent the most recent (September 1991) coal analysis for this particular mine. A mine cleaned coal analysis for this same coal was also provided by Dr. Fonseca and is included in Table 3-1. The CONSOL coal was dried and sized to TRW's specifications by Tra-Det, Inc. of Wheeling, West Virginia. Tra-Det, at TRW's request, also performed analyses on each of the four lots (each weighing ~1 ton) of coal they shipped to TRW. The Tra-Det coal analysis for Lot No. 2, the coal that was utilized in Run No. 11, is presented in Table 3-1.

The kiln operating conditions for Run No. 11 are summarized in Table 3-2. All the operations for the week were conducted with a ~2.5:1 caustic:coal mixture being fed to the kiln. The caustic was sodium hydroxide (NaOH). A schematic of the rotary kiln reactor system is shown in Figure 2-2.

During the first 32 hours of the test, the NaOH feed to the kiln consisted of fresh NaOH bead. At this point, inventories of caustic had built up in the kiln and in the regeneration tank reactors, and a moderate amount of regenerated caustic flake had been produced in the evaporator/flaker. From this point in the run until the end of the run, except for short periods of time, regenerated caustic was mixed with the coal feed and recycled to the kiln. Table 3-3 gives the type of caustic (fresh or regenerated) mixed with the coal feed to the kiln as a function of run time. Table 3-4 gives the total quantities of fresh/regenerated caustic and feed coal blended and fed to the kiln. Excluding the ~800 pounds of fresh caustic bead used to startup the system, ~80% of the remaining ~2700 pounds of caustic fed to the kiln during the test run was recycled regenerated caustic flake. It should be noted that while the kiln feed was blended at a ratio of 2.5:1 caustic:coal when using fresh caustic bead, this ratio was increased to ~2.7:1 when using regenerated caustic flake. Fresh NaOH bead has a moisture content of ~2%, whereas, the moisture content of the regenerated caustic flake is ~10%. The caustic:coal ratio when using regenerated flake was increased in an attempt to maintain the same NaOH(dry):coal ratio that was used when feeding a NaOH(bead):coal mixture to the kiln.

TABLE 3-1. FEED COAL ANALYSIS (DRY BASIS)
MCL TEST RUN NO. 11

COAL TYPE: PITTSBURGH NO. 8 COAL
SOURCE: CONSOL-BLACKSVILLE NO. 2 MINE

ANALYSIS	RAW, RUN-OF-MINE COAL	MINE-CLEANED COAL	TRA-DET DRIED* AND SIZED**-LOT 2
SULFUR FORMS, wt%			
PYRITIC	1.67	1.04	0.65
ORGANIC	1.08	1.20	1.20
SULFATE	<u>0.05</u>	<u>0.02</u>	<u>0.01</u>
TOTAL	2.80	2.26	1.86
ASH, wt%	16.9	7.9	7.4
VOLATILES, wt%	35.2	38.7	NA
FIXED CARBON, wt%	47.9	53.3	NA
HEAT CONTENT, Btu/lb			
DRY	12,450	13,910	14,042
MAF	14,982	15,103	15,165
LBS SO ₂ /MILLION BTU (dry)	4.5	3.25	2.65

* Coal dried to 1.68% moisture

** Coal sized at minus 14 mesh

NA Not Available

Table 3-2

Run Condition Summary

Operating Run No. 11, 5/14-5/21/92

Run No.	Operating Time Span for Kiln*		Coal Type	Caustic Type	Caustic:Coal**	Kiln Feed Rate, lbs/hr	Kiln Skin Temps ^{OC} ***	Acid Wash pH
	Date From/To	Time From/To						
11A	5/15 5/17	0330 - 1200	Pittsburgh #8 14 Mesh (BV2)	NaOH only	2.5:1	-32	424	2-8
11B	5/17	1200-1800	Pittsburgh #8 14 Mesh (BV2)	NaOH only	2.5:1	-32	434	2-8
11C	5/17 5/18	1800 - 0000	Pittsburgh #8 14 Mesh (BV2)	NaOH only	2.5:1	-32	434	10 (no acid injection)
11D	5/18	0000-0600	Pittsburgh #8 14 Mesh (BV2)	NaOH only	2.5:1	-32	434	1-2
11E	5/18 5/21	0600 - 0410	Pittsburgh #8 14 Mesh (BV2)	NaOH only	2.5:1	-32	434	10 (no acid injection)****

* It has been calculated that it takes ~8 hours for the coal to get through the kiln and wash trains. Therefore, when relating product coal collected to kiln conditions, this 8 hour lag time must be taken into account.

** Based on NaOH with 2% moisture (NaOH bead). When processing recycle caustic flake with ~10% moisture content, the caustic:coal ratio was increased from 2.5:1 to 2.7:1.

*** Internally measured temperature varied from 20°C to 80°C lower than skin temperature.

**** Eliminated separate wash water makeup flows to water and acid wash trains. Fresh wash water added to acid wash train and centrate from acid wash subsequently used as wash water makeup to water wash train.

TABLE 3-3. LOG OF CAUSTIC IN MIX TRANSFERRED TO KILN FEED HOPPER
MCL TEST RUN NO. 11

DATE	TIME	CAUSTIC TYPE
5/14/92	13:45	FRESH BEAD
	18:00	
	21:00	
5/15/92	05:00	↓ REGENERATED FLAKE
	14:50	
	22:55	
5/16/92	03:40	↓ REGENERATED FLAKE
	06:10	
	08:50	
	11:20	
	15:45	
	20:20	
5/17/92	04:40	↓ FRESH BEAD
	09:55	
	12:50	
	14:55	
	16:25	
	18:07	
5/18/92	22:00	↓ REGENERATED FLAKE
	00:25	
	04:15	
	08:30	
5/19/92	10:00	↓ FRESH BEAD
	15:01	
	20:20	
	02:30	
	03:00	
	08:20	
5/20/92	11:50	↓ REGENERATED FLAKE
	14:10	
	17:10	
	20:20	
	22:50	
	03:16	
	06:25	
	08:10	
	11:40	
	14:30	
	17:30	↓ FRESH BEAD REGENERATED FLAKE REGENERATED FLAKE FRESH BEAD REGENERATED FLAKE

TABLE 3-4. TOTAL QUANTITY OF COAL/CAUSTIC FED TO KILN
MCL TEST RUN NO. 11

LBS COAL	LBS CAUSTIC	CAUSTIC TYPE	CAUSTIC:COAL RATIO
490	1225	FRESH NaOH BEAD	2.50:1
847	2263	REGENERATED NaOH FLAKE	2.67:1*
<u>1337</u>	<u>3488</u>		
$\Sigma 1337 + 3488 = 4825 \text{ lbs}$			

$$\text{AVERAGE KILN FEED RATE} = \frac{4825 \text{ LBS}}{152 \text{ HRS OF OPERATION}} = 31.75 \text{ LBS/HR}$$

- * Caustic:coal ratio increased when feeding regenerated flake to compensate for the moisture content (~10%) of this material relative to the moisture content (~2%) of fresh NaOH bead.

Referring to Table 3-2, the kiln was operated initially at skin temperatures in the four (4) heated zones of $\sim 795^{\circ}\text{F}$ (424°C). Product coal with a sulfur content of ~ 0.5 wt% was produced during this period. This can be seen in Figure 3-2 where the heated Zone 2 kiln skin temperatures, the internal kiln temperature and the product coal sulfur content have been plotted against run time. It should be noted that in order to relate the product sulfur content to the kiln conditions, eight hours have been subtracted from the actual coal product sampling time. This is an estimate of the time it takes the coal (if it moved in plug flow) to transit the kiln and wash trains.

Starting at $\sim 23:00$ on May 16, the kiln skin temperatures were increased in small increments until a new steady-state temperature of $\sim 813^{\circ}\text{F}$ (434°C) was reached. The kiln temperature was increased in order to reduce the coal product sulfur content from the ~ 0.5 wt% level. Figure 3-2 shows that the increase in skin temperatures had the intended effect. For the balance of the test run with the kiln skin temperatures maintained at $\sim 813^{\circ}\text{F}$ (434°C), the average sulfur content of the product coal was ~ 0.35 wt%. It should be noted that the kiln internal temperature (measured by a thermocouple in a well in the second heated zone) fluctuated significantly during the run. Assuming that this temperature was accurate (smoke was noticed coming from the well late in the test run and a hole was discovered in the well on inspection after the test run), it would seem to indicate that material was periodically building up and then dropping off the walls of the kiln.

This was borne out on one occasion by actual observation of the material discharging from the kiln. Starting at $\sim 01:20$ on May 18 and continuing for perhaps 90 minutes, large chunks of material were discharged from the kiln at a high rate of flow. In fact, since this high kiln solids discharge rate caused problems in the downstream dissolver tank, the kiln discharge solids were collected in a plastic bag during this time period. Over a period of ~ 90 minutes, approximately 109 pounds of kiln discharge material were collected, initially at a rate of ~ 80 lbs/hour. By the end of the 90 minutes, the kiln discharge rate had returned to the expected ~ 30 lbs/hour and the size consist of the material had also returned to normal. At this

MCL INTEGRATED TEST OPERATION KILN TEMPERATURES & SULFUR CONTENT

Figure 3-2. Kiln Temperatures and Sulfur Content - Test Run No. 11

time, feeding of the kiln solids to the wash train was resumed. It can be seen in Figure 3-2 that shortly after this upset, the internal kiln temperature registered its highest readings (smallest ΔT 's between the skin and internal temperature indicating a relatively clean kiln wall). This internal temperature more truly reflects the processing temperature than does the skin temperatures. As can be seen in Figure 3-2, the lowest product coal sulfur values (as low as 0.11 wt% sulfur) were obtained during this period of time (May 18, 10:00 to May 19, 07:00) when the internal temperature was within 20 to 25°C of the skin temperatures. However, during the period May 18, 10:00 to May 19, 07:00, fresh caustic was being fed to the kiln rather than regenerated recycled caustic. This may have also contributed to the ultra low coal product sulfur values achieved during this period.

During Run No. 11, the solids mix was fed to the kiln at a rate of ~32 lbs/hours (~9 lbs/hour coal at an average caustic:coal ratio of 2.6:1). The kiln was inclined at a slope of 1/8-inch per foot and was rotated at a speed of 1 RPM. No solids were observed to backup into the kiln feed breach. During Run No. 11, a total of 1337 pounds of coal was fed into the kiln over a period of 152 hours for an average coal feed rate of 8.8 lbs/hour.

Two samples of kiln off-gas were collected during the run (1 hour apart) at the same kiln conditions. The analytical results are presented in Table 3-5. The high oxygen content of the first sample collected may reflect an incompletely evacuated sample bomb or an air leak into the bomb at the sampling connection. The sum total of the gas components does not add to 100%, and the unaccounted for component (about 2 to 4% of the total) is probably mainly uncondensed water vapor. At a GN_2 feed rate to the kiln of 17 SCFM during the sampling period and a coal feed rate to the kiln of ~9 lbs/hour, the average weight percent coal converted to CH_4 is 1.83% and to C_2+ is 0.48%. Less than 0.06% of the weight of the coal was converted to hydrogen. While a total weight of coal converted to hydrogen and volatile hydrocarbon gases of 2.4% is not out of line with the average coal weight loss to volatiles with other coals processed during Phase I testing (2.85%), the conversion of coal to hydrogen is about an order of magnitude lower than that seen previously (hydrogen content of the kiln off-gas averaged 2.4 mole percent during Phase I testing versus <0.1 mole percent for this test run).

TABLE 3-5. KILN OFF-GAS ANALYSIS
MCL TEST RUN NO. 11

DATE	May 19, 1992	May 19, 1992
TIME	17:00	18:00
COMPONENT	MOLE %	MOLE %
HYDROGEN	<0.1	<0.1
OXYGEN (& ARGON)	5.8	<0.01
NITROGEN	91.9	95.2
CARBON MONOXIDE	<0.01	<0.01
CARBON DIOXIDE	<0.01	<0.01
METHANE	0.30	0.41
GASEOUS ORGANICS OTHER THAN METHANE	0.043	0.058
TOTAL	<u>98.1</u>	<u>95.7</u>
WT% COAL FEED TO KILN OFF-GAS*	2.05	2.69

* Based on 17 SCFM GN₂ sweep gas into kiln and 9 lbs/hr coal feed to kiln.

The very small amount of hydrogen observed in the kiln off-gas raises questions about the mechanism of carbonate formation in the kiln. One reaction mechanism theorized to explain carbonate formation is:

If this mechanism is correct, hydrogen will be formed. At the carbonate make seen in Run No. 11 (~10% of caustic converted to carbonate), the hydrogen level in the kiln off-gas (exclusive of any hydrogen driven from the coal itself as it is heated) would calculate to ~2.0 mole percent versus the <0.1 mole percent observed. Another possible mechanism for carbonate formation is:

The source of the CO₂ could be: 1) CO₂ evolved from the coal during heatup, or 2) a small amount of air leakage into the kiln to form CO₂ by combustion of a small amount of the coal. Since the coal tested is of relatively high rank (bituminous), it is doubtful that the coal would have evolved (during heatup) more than a small fraction of the CO₂ needed to account for the observed carbonate make. The air leakage into the kiln needed to account for the observed carbonate make would be ~0.8 SCFM (or ~5% of the GN₂ volume used to sweep the kiln). It should be noted that the kiln is normally operated under a slightly positive pressure (<1" H₂O) to avoid the in-leakage of air.

The ~25 gallon inventory of dilute (10%) caustic solution that was used in the venturi scrubber for the scrubbing of the kiln off-gas was analyzed at the end of the test run for total organic carbon (TOC) content. The solution had a TOC of 550 micrograms/gram.

3.3 WASH TRAIN OPERATIONS (SECTIONS 200 AND 300)

3.3.1 Background

During Test Run No. 10 (June 3 to 7, 1991), highly friable, weathered feed coal was responsible for the high level of coal fines (up to 85% minus 100 mesh) in the kiln discharge material, for the high losses of coal fines

to the filtrate (~25% of the feed coal), and for blinding of the filter cloth. That coal was subsequently disposed of and fresh coal was purchased. A successful off-line test of the MCL rotary drum vacuum filtration system was conducted on May 1, 1992 with fresh feed coal, with a 100 mesh filter cloth on the rotary drum of the first vacuum filter, F-201, and with a 40 mesh cloth on the drum of F-202. (Both filters were dressed with 40 mesh cloths during Test Run No. 10.) Fines capture by the 100 mesh cloth during the off-line test was fairly complete, with fines losses to the filtrate from the first filter of ~5% of the feed coal.

For Test Run No. 11, the 40 mesh cloth on the second filter was also replaced with a 100 mesh cloth. This should ensure that the fines will be retained with the filter and centrifuge cakes and will exit the system with the washed coal product. If the more open 40 mesh cloth had been left on the drum of the second filter, the question would remain as to how much fines were being passed by the second vacuum filter. Since the filtration system operates in a countercurrent fashion, any fines that are passed by the second filter would become part of the feed recycle stream to the first filter. Concerns have been raised that this could lead to the buildup of a large inventory of circulating fines between the filters which could eventually impact the performance of the filtration system.

3.3.2 Test Description

The entire water wash train (2 vacuum filters, 5 centrifuges) and the acid wash train (3 centrifuges) were put into operation at the start of the test run. Schematics of the water wash system and the acid wash system are shown in Figures 2-4 and 2-6, respectively.

The first kiln discharge solids entered the dissolver tank T-101 at 19:40 on May 14. The first cake appeared on the rotary drum of the first vacuum filter (F-201) at 20:20 and on the drum of the second vacuum filter (F-202) at 20:35. However, as in previous test runs, problems quickly developed with the operation of the second vacuum filter. The cake formed on the drum of this filter was extremely thin, and the filter was obviously not separating coal from the solution at the rate that the coal was being added to the dissolver tank. The second filter gave every indication of experiencing

filter cloth blinding. With no obvious short term fix for this problem and the solids content of the slurry feed to the second vacuum filter rapidly increasing, the decision was made to bypass this filter at 00:30 on May 15 (approximately 5 hours after putting F-202 on-stream). The plumbing was reconfigured and the balance of the run was conducted without the second vacuum filter on-stream.

The flow rate of deionized water to the water wash train was 0.18 GPM (90 lbs/hour). This flow rate was selected to give a filtrate stream to regeneration low enough in caustic content (<20%) to assure that the carbonate formed in the kiln (as predicted by pre-run laboratory studies) would completely dissolve in the filtrate solution. A plot of literature solubility data for the Na_2CO_3 - NaOH - H_2O system has been attached as Figure 3-3. As can be seen from this figure, a 20% caustic solution should readily hold at least 5% carbonate (versus the 2 to 3% carbonate expected) in solution. The flow rate of deionized water into the acid wash train was set at 0.24 GPM (120 lbs/hour) to obtain good washing of the final product coal. The first product coal appeared at the discharge of the last centrifuge (C-303) in the acid wash train at 02:25 on May 15.

3.3.3 Effect of pH

A new process innovation, with potentially large cost savings, was tested during the test run. In all test runs to date, an acid wash step has been used in the MCL circuit to produce a very low ash product coal. This step follows the water washing of the coal and results in removal of the iron, residual mineral matter and the near trace amounts of sodium left on the coal product exiting the water wash train. The acidified coal is water washed and this results in an aqueous waste stream that must be treated for removal of sodium and iron salts. Since many applications require only low sulfur coal, and ultra low ash content is not a consideration, it was concluded that the acid wash train should be eliminated, if possible. This concept was tested late in the test week.

First, however, the pH in the acid wash section was adjusted to see what impact pH had on the ash content on the product coal. The acid wash train was operated at three (3) different pH levels, as shown in Figure 3-4, over

SODIUM CARBONATE - SODIUM HYDROXIDE - WATER SYSTEM

Figure 3-3. Sodium Carbonate - Sodium Hydroxide - Water System

MCL INTEGRATED TEST OPERATION ACID WASH pH

Figure 3-4. Acid Wash System pH - Test Run No. 11

the course of the week-long operations. The pH was varied to determine the effect of pH on the ash and sulfur content of the final product coal. During the first part of the run (period #1 in Figure 3-4), an attempt was made to maintain the pH in tank T-301 (feed tank for the first centrifuge, C-301, in the acid wash train, see Figure 2-6) at about 5 to determine if iron could be rendered soluble at this elevated pH. As can be seen in Figure 3-4, the operators were not very successful in maintaining the pH at a constant value of 5.

The method of pH control (which worked well at the normal pH level of 1 to 2) was at fault. Concentrated (98%) sulfuric acid is fed to T-301 by a small chemical metering pump. However, at a pH of 5, the acid demand is so small that the pump cannot be run continuously, even at its lowest setting. The method of pH "control" employed was for the operators to periodically read the pH probe in T-301 and stroke the acid pump a few times to add a small amount of acid when the pH reading exceeded ~5. To maintain a pH close to 5 using this method would have required constant operator attention; this was not practical with a small operating crew which had many other demands on its time. The pH probably "averaged" 5 during the initial part of the run but varied over a range of 2 to 8. In the future, should this experiment be repeated, it is proposed that the concentrated (98%) acid be diluted to the 5 to 10% range. This will increase the acid volume demand by a factor of 10 to 20 and allow the acid metering pump to be set to run continuously at an appropriate rate to give the desired pH in T-301. The quantity of water added with the small amount of dilute H_2SO_4 will not significantly affect the plant water balance.

On May 17, the unit was operated for a period of ~6 hours (period #2 in Figure 3-4) without any acid injection into T-301. The pH rose to >10 in T-301. There is some question as to the accuracy of this pH value as it was outside the calibration range of the pH probe in T-301. Late on May 17 and into the early hours of May 18 (period #3 in Figure 3-4), the unit was operated for a period of ~6 hours at a pH of 1 to 2 in T-301.

Finally, the acid injection into T-301 was again eliminated (period #2A in Figure 3-4). This last period of operation differed from the earlier experiment (period #2 in Figure 3-4) in that the use of separate wash water

streams into the acid and water wash trains was eliminated. The wash water in this instance was introduced only into the acid wash train. However, instead of sending the wash water from the acid wash train to water treatment (for iron and sulfate removal), which is the normal procedure, this stream was diverted (in a temporary jumper line) to tank T-211 (feed tank for the last centrifuge, C-205, in the water wash train, see Figure 2-4) to replace the fresh wash water normally added to T-211. That is, the centrate from C-301 was rerouted from waste treatment into reslurry tank T-211, and the wash water flow to this tank was then stopped. In this configuration, no waste water leaves the MCL circuit, and the only source of wash water for the wash train is the water added to the reslurry tank after C-302 (see Figure 2-6).

During acid curtailment, the wash water was off for a period of time sufficient for solids to accumulate and plug the C-204 centrifuge discharge chute. Centrifuge C-204 was then taken out of service.

This process modification -- eliminating the acid wash step, the acid waste water treatment step, and one of two wash water streams -- resulted in a product coal with low sulfur and moderate ash content (hopefully low in sodium) for which commercial applications exist. This process modification could result in a substantial reduction in processing costs (up to 25%), placing the MCL Process in a significantly advantageous cost position relative to FGD for boilers and small furnaces.

3.3.4 Product Coal Analysis

The results of the in-house product coal sample analyses for Run No. 11 are given in Table 3-6. Approximately seventy (70) product coal samples were analyzed in-house during the test run for sulfur, ash, volatiles, fixed carbon and moisture content. Selected samples of the product coal were also sent to an outside test laboratory (Standard Laboratories) for determination of sulfur, ash (as a check of in-house analyses), sulfur forms, and heating value. These analytical results are given in Table 3-7. As can be seen by comparing the product coal sulfur and ash values reported in Tables 3-6 and 3-7, the results reported by TRW and the outside laboratory were in close agreement.

TABLE 3-6. PRODUCT COAL ANALYSES PERFORMED BY TRW
MCL TEST RUN NO. 11 (MAY 14 TO MAY 21, 1992)

SAMPLE DATE	SAMPLE TIME	SAMPLE TYPE*	% MOISTURE	% VOL	% ASH	% FIXED CARBON	% SULFUR	% ORIGINAL MOISTURE
5/15/92	07:35	P.C.	0.85	28.86	1.18	69.96	0.49	51.3
5/15/92	05:40	P.C.	11.55	23.86	1.28	74.86	0.48	48.6
5/15/92	04:35	P.C.	1.40	31.54	1.54	66.92	0.48	49.8
5/15/92	03:30	P.C.	1.07	29.45	1.60	68.95	0.48	48.3
5/16/92	09:35	P.C.	0.16	29.28	2.41	68.31	0.62	40.6
5/16/92	01:30	P.C.	0.88	27.89	1.37	70.74	0.49	51.8
5/15/92	23:35	P.C.	1.08	28.08	1.17	70.75	0.53	51.0
5/15/92	18:30	P.C.	0.08	27.76	1.43	70.81	0.47	46.6
5/15/92	14:30	P.C.	0.08	29.44	2.00	68.56	0.48	42.7
5/15/92	12:00	P.C.	0.07	28.52	1.97	69.51	0.48	44.7
5/16/92	13:30	P.C.	0.41	31.30	2.64	66.06	0.71	40.0
5/16/92	12:30	K.D.	1.05	26.74	0.86	72.40	0.65	
5/16/92	11:15	P.C.	0.61	24.49	1.86	73.65	0.42	42.6
5/16/92	17:30	P.C.	0.70	29.36	1.95	68.69	0.53	40.8
5/17/92	03:35	P.C.	0.54	24.79	1.55	73.66	0.39	42.5
5/17/92	05:45	P.C.	0.71	25.11	1.67	73.22	0.38	44.9
5/17/92	09:30	P.C.	1.16	23.76	1.84	74.40	0.34	52.3
5/17/92	11:30	P.C.	0.69	24.73	1.75	73.52	0.40	47.3
5/17/92	13:30	P.C.	0.63	27.99	1.72	70.22	0.44	46.0
5/16/92	15:30	K.D.	0.85	24.09	4.89	71.02	0.44	
5/17/92	13:10	K.D.	0.94	22.25	7.27	70.48	0.36	
5/17/92	15:30	P.C.	0.64	28.90	2.24	68.86	0.50	49.9
5/17/92	22:10	P.C.	0.19	22.29	5.42	72.29	0.25	
5/17/92	24:00	P.C.	0.27	22.61	2.01	75.38	0.37	
5/18/92	01:00	P.C.	0.13	19.74	0.61	79.65	0.40	
5/18/92	04:00	P.C.	0.14	19.87	0.41	79.72	0.44	
5/18/92	06:00	P.C.	0.15	22.42	0.49	77.09	0.43	

TABLE 3-6. PRODUCT COAL ANALYSES PERFORMED BY TRW (CONTINUED)
MCL TEST RUN NO. 11 (MAY 14 TO MAY 21, 1992)

SAMPLE DATE	SAMPLE TIME	SAMPLE TYPE*	% MOISTURE	% VOL	% ASH	% FIXED CARBON	% SULFUR	% ORIGINAL MOISTURE
5/18/92	08:00	P.C.	0.27	22.73	1.46	75.81	0.37	
5/17/92	15:00	K.D.	0.08	23.02	0.71	76.27	0.50	
5/17/92	19:00	P.C.	0.19	23.55	2.32	74.13	0.28	51.9
5/18/92	10:00	P.C.	0.05	26.94	2.68	70.38	0.52	47.1
5/18/92	12:00	P.C.	0.26	27.50	3.02	69.48	0.51	47.3
5/15/92	07:50	K.D.	0.57	27.92	4.29	67.79	0.36	
5/18/92	14:15	P.C.	0.19	30.88	3.08	66.04	0.36	49.3
5/18/92	16:15	P.C.	0.21	26.13	3.82	70.05	0.33	44.8
5/18/92	19:30	P.C.	0.55	27.64	3.19	69.17	0.23	47.8
5/18/92	21:00	P.C.	0.26	25.89	3.03	71.08	0.17	48.9
5/19/92	00:20	P.C.	0.40	26.66	3.21	70.13	0.14	46.7
5/19/92	02:15	P.C.	0.46	29.07	2.95	67.98	0.13	50.1
5/19/92	06:35	P.C.	0.52	26.80	3.33	69.87	0.21	50.1
5/18/92	14:15	P.C.					0.31	38.0
5/18/92	16:15	P.C.					0.29	38.6
5/18/92	19:30	P.C.					0.22	43.4
5/18/92	21:00	P.C.					0.14	45.2
5/19/92	00:20	P.C.					0.11	46.0
5/19/92	04:15	C-204	9.78	21.78	1.77	76.45	0.14	45.7
5/19/92	08:00	P.C.	4.68	23.29	2.80	73.91	0.22	46.6
5/19/92	10:00	P.C.	7.68	21.11	2.82	76.07	0.14	46.2
5/19/92	12:00	P.C.	8.66	21.89	1.54	76.57	0.11	47.3
5/19/92	14:00	P.C.	12.27	24.80	3.04	72.16	0.14	42.5
5/19/92	16:00	P.C.	11.99	25.58	3.54	70.88	0.26	41.4
5/19/92	18:00	P.C.	13.60	25.19	3.76	71.05	0.34	39.0
5/19/92	20:00	P.C.	4.91	25.78	4.37	69.85	0.45	44.3
5/19/92	24:00	P.C.	9.27	25.74	3.48	70.78	0.36	42.6

TABLE 3-6. PRODUCT COAL ANALYSES PERFORMED BY TRW (CONTINUED)
MCL TEST RUN NO. 11 (MAY 14 TO MAY 21, 1992)

SAMPLE DATE	SAMPLE TIME	SAMPLE TYPE*	% MOISTURE	% VOL	% ASH	% FIXED CARBON	% SULFUR	% ORIGINAL MOISTURE
5/20/92	02:10	P.C.	7.30	24.74	3.74	71.52	0.41	44.3
5/19/92	22:00	P.C.	1.46	24.82	3.88	71.30	0.50	42.2
5/20/92	04:22	P.C.	9.83	23.93	3.55	72.52	0.37	41.8
5/20/92	06:00	P.C.	7.35	26.50	3.22	70.28	0.27	42.4
5/20/92	08:00	P.C.	7.71	27.65	2.97	69.38	0.28	42.3
5/20/92	10:00	P.C.	0.52	23.58	3.09	73.33	0.33	47.3
5/20/92	12:00	P.C.	0.32	24.82	3.82	71.80	0.44	44.8
5/20/92	14:00	P.C.	0.36	24.17	3.53	72.30	0.51	46.5
5/20/92	16:05	P.C.	0.26	25.54	3.46	71.00	0.51	45.5
5/20/92	18:05	P.C.	0.16	27.01	3.48	69.51	0.38	47.1
5/20/92	19:00	P.C.	0.36	24.12	3.88	72.00	0.30	47.7
5/20/92	20:00	P.C.	0.37	25.91	3.91	70.18	0.25	49.3
5/20/92	21:00	P.C.	0.27	26.73	3.78	69.49	0.24	49.7
5/20/92	22:00	P.C.	0.07	23.78	3.58	72.64	0.23	50.3
5/21/92	01:00	P.C.	0.32	25.84	3.84	70.32	0.27	50.1
5/21/92	02:00	P.C.	0.37	23.51	4.52	71.97	0.39	49.6
5/21/92	03:00	P.C.	0.10	26.51	4.12	69.37	0.38	48.8
5/21/92	04:10	P.C.	0.08	26.93	4.47	68.60	0.52	47.5

* P.C. = Product Coal
K.D. = Kiln Discharge
C-204 = Centrifuge C-204 Cake

TABLE 3-7. PRODUCT COAL SULFUR, SULFUR FORMS, HEATING VALUE, AND ASH
ANALYSES PERFORMED BY STANDARD LABORATORIES
MCL TEST RUN NO. 11 (5/14-5/21/92)

DATE	TIME	SULFUR FORMS				HEATING VALUE (BTU/LB)			LBS SO ₂ /	
		% SULFUR	% PYRITIC	% ORGANIC	% SULFATE	DRY	MAF	MILLION BTU	% ASH	
5/15	03:30	0.49				14,303	14,576	0.68	1.87	
5/15	05:40	0.49				14,465	14,662	0.68	1.35	
5/15	12:00	0.48	0.06	0.41	0.01	14,553	14,853	0.68	2.02	
5/15	18:30	0.48				14,528	14,750	0.66	1.50	
5/16	09:35	0.66	0.10	0.55	0.01	14,573	14,958	0.90	2.57	
5/16	13:30	0.74	0.09	0.64	0.01	14,538	14,971	1.02	2.89	
5/17	09:30	0.35	0.09	0.23	0.03	14,147	14,438	0.49	2.01	
5/17	13:30	0.45				14,342	14,649	0.63	2.10	
5/17	19:00	0.27				14,117	14,512	0.38	2.72	
5/17	22:10	0.26	0.07	0.17	0.02	13,949	14,491	0.37	3.74	
5/18	04:00	0.42	0.01	0.18	0.23	14,085	14,143	0.60	0.41	
5/18	12:00	0.54	0.11	0.41	0.02	14,284	14,834	0.76	3.71	
5/18	16:15	0.33				13,635	14,271	0.48	4.45	
5/18	21:00	0.16				13,162	13,745	0.24	4.24	
5/19	00:20	0.12				13,015	13,624	0.18	4.47	
5/19	06:35	0.20				13,206	13,777	0.30	4.15	
5/19	12:00	0.14				13,139	13,725	0.21	4.27	
5/19	20:00	0.49	0.23	0.21	0.05	13,601	14,344	0.72	5.18	
5/20	04:22	0.41				13,793	14,430	0.59	4.41	
5/20	10:00	0.36	0.12	0.20	0.05	13,729	14,273	0.52	3.81	
5/20	14:00	0.58				13,892	14,509	0.83	4.25	
5/20	20:00	0.26				13,133	13,818	0.40	4.96	
5/21	01:00	0.33				13,133	13,842	0.50	5.12	
5/21	04:10	0.55	0.16	0.29	0.10	13,312	14,082	0.83	5.47	

3.3.5 Sulfur Removal

The sulfur content of the product coal versus run time is presented in Figure 3-5. Low sulfur coal was produced for the entire week of operations regardless of the pH in the acid wash section (see Figure 3-4). In fact, the lowest sulfur content (0.1 to 0.2 wt%) product coal was produced during the period of operation (early on May 19, period #2A in Figure 3-4) when no acid was injected. As long as there is efficient water washing of the coal, the sulfur content of the product coal appears to be determined primarily by kiln conditions. The average sulfur content of the product coal produced during the entire week of operations was 0.36 wt% sulfur. At an average heating value of 13,860 Btu/lb for the week of operations, the average sulfur content of the product coal computes to 0.52 lb SO₂/million Btu. This represents an ~88.5% reduction from the 4.5 lb SO₂/million Btu for the raw, run-of-mine coal.

The average sulfur content of the product coal produced during the ~90 hours of the test run after the kiln temperature was raised on May 17 (from 424°C to 434°C skin temperature, see Table 3-2) was 0.29 wt% sulfur. At an average coal product heating value for that period of operation of 13,620 Btu/lb, the sulfur content of the product coal computes to 0.43 lbs SO₂/million Btu. This represents a 90.5% reduction from the 4.5 lbs SO₂/million Btu for the raw, run-of-mine coal.

Finally, for the ~21 hour period (May 18, 10:00 to May 19, 07:00) when the kiln internal temperature most closely approached the kiln skin temperatures, indicating a relatively clean kiln wall (see Figure 3-2), the average sulfur content of the product coal produced (May 18, 18:00 to May 19, 15:00, adding ~8 hours to the kiln time for transit through the kiln and wash trains) was 0.17 wt% sulfur. At an average product coal heating value for that period of 13,200 Btu/lb, the sulfur content of the product coal computes to 0.26 lbs SO₂/million Btu or a 94.2% reduction in sulfur from the raw, run-of-mine coal.

Within the aforementioned 21-hour period, the lowest sulfur value recorded for the product coal was 0.11 wt% sulfur. At a coal heating value of 13,000 Btu/lb, this computes to 0.17 lbs SO₂/million Btu (or 198 mg

MCL INTEGRATED TEST OPERATION PRODUCT COAL SULFUR

Figure 3-5. Product Coal Sulfur - Test Run No. 11

SO₂/Nm³), a 96.2% reduction in sulfur from the raw, run-of-mine coal. This corresponds to one-half of the EC standard of 400 mg SO₂/Nm³. The sulfur reduction figures are summarized in Table 3-8.

3.3.6 Ash Removal

The ash values for the product coal samples analyzed in-house are given in Table 3-6. The product coal ash values are plotted as a function of run time in Figure 3-6. The average product coal ash content for the entire week of operation was 2.75 wt% or an 84% reduction of ash from the 16.9% ash content of the raw, run-of-mine coal. The pH level employed in the acid wash train had a very significant effect on the product coal ash content. Referring to Figure 3-4, during period #1 in which the "average" pH in T-301 was ~5, the average ash in the product coal collected was 1.7%. During period #2 in which no acid was being injected and the pH in T-301 increased to ~10, the average ash content (based on only two data points) of the product coal was ~2.2%. During period #3 in which acid was injected to give a pH of 1 to 2 in T-301, the average ash content of the product coal fell to ~0.5%. Finally in period #2A during which no acid was being injected and the effluent wash water from the acid wash section was used as the water feed to the water wash section, the average ash content of the product coal was 3.5%.

Unfortunately, the results of this last test period in the pH matrix were adversely affected by an upset which occurred in the caustic evaporator shortly after the start of pH test period #2A. At ~14:00 on May 18, a plug developed in the evaporator's molten caustic downcomer line. An attempt was made to dissolve the plug by flushing the evaporator with water. Unfortunately, since the plug did not break through immediately, some of the flush water, heavily laden with caustic, backed up through the evaporator overhead steam line and was collected in the evaporator overhead condensate receiver. The contaminated water was then pumped from the condensate receiver, as recycle, into the deionized water storage tank, T-601, a 300-gallon tank which serves as the deionized water supply for the acid and water wash trains.

Once this problem was discovered, an attempt was made to remedy the situation without shutting down the wash train. Tank T-601 was partially

TABLE 3-8. PRODUCT COAL SULFUR REMOVAL RESULTS
MCL TEST RUN NO. 11 (5/14-5/21/92)

	WT % S	HEATING VALUE BTU/LB	LBS SO ₂ / MILLION BTU	% SULFUR REDUCTION FROM ROM COAL*
I. Average values for Run 11 - 152 hours	0.36	13,860	0.52	88.5
II. Average values for kiln with 434°C skin temperatures - 90 hours	0.29	13,620	0.43	90.5
IIA. Minimum ΔT (skin-internal) - 21 hours	0.17	13,200	0.26	94.2
IIA1. Average of 7 of 14 samples collected in IIA ~10 hours product	0.13	13,000	0.20	95.5
IIA2. Lowest value in IIA - 2 of 14 samples collected	0.11	13,000	0.17	96.2

* Raw, run-of-mine (ROM), CONSOL BV2 coal used during MCL Test Run No. 11 has a sulfur content of 2.8% and a heating value (dry basis) of 12,450 Btu/lb. Therefore, this coal contains 4.5 lbs SO₂/million Btu.

MCL INTEGRATED TEST OPERATION PRODUCT COAL ASH

Figure 3-6. Product Coal Ash - Test Run No. 11

drained and fresh makeup deionized water was brought into the tank. This probably did not result in the complete decontamination of the tank. It is felt that the product coal ash values (and the NaOH content of the ash) was artificially increased during this last part of the test run by the use of the caustic contaminated wash water. This was later confirmed in an ~24 hour wash train test conducted about a month later (June 24-25, 1992) in which ~700 pounds of kiln discharge solids bagged during Run No. 11 was processed through the wash trains under the same conditions as test period #2A in Figure 3-4, but using fresh deionized water as the makeup wash water to the acid wash train (see Section 4 for more details of this wash train test). The average ash content of the product coal produced during this later wash train test was 2.7% as compared to the 3.5% ash product coal produced in Run No. 11 during period #2A under the same conditions but using caustic contaminated wash water.

A summary of the kiln and acid wash train pH test matrix and the resulting average product coal ash values are presented in Tables 3-9 and 3-10, respectively.

3.3.7 Mineral Constituents of the Product Coal

A number of product coal samples were sent to Standard Labs for ultimate (9 component) analysis of the ash. The results of the analyses are presented in Table 3-11. The component analyses as received were normalized to agree with the reported total ash analysis (which was determined by a different ASTM procedure from the ash ultimate analysis). The product coal samples that were sent to Standard Labs for ultimate ash mineral analysis were not necessarily "typical" of the sub-run they were taken from. In particular, the last three samples in Table 3-11 (from sub-run 11E) are the highest ash content samples collected during the entire week of testing and compare to an "average" ash content of 3.5% during sub-run 11E.

A calculation was performed to determine the amounts of each ash component that could be expected if no ash removal were accomplished in the MCL facility. The calculation is based on an assumed recovery of 0.85 pounds of MAF product coal per pound of MAF coal fed to the kiln, 7.4% ash in the

TABLE 3-9. KILN AND ACID WASH TRAIN pH TEST MATRIX
MCL TEST RUN NO. 11 (5/14-5/21/92)

SUBRUN NO.	TIME PERIOD	KILN CONDITION NO.	ACID WASH CONDITION NO.
11A	5/15 03:30 - 5/17 12:00	1	1
11B	5/17 12:00 - 5/17 18:00	2	1
11C	5/17 18:00 - 5/18 00:00	2	2
11D	5/18 00:00 - 5/18 06:00	2	3
11E	5/18 06:00 - 5/21 04:10	2	2A

DESCRIPTION OF PROCESS CONDITIONS FOR TEST RUN NO. 11

KILN CONDITIONS:

- #1 2.5:1 caustic:coal, 424°C skin temperatures
- #2 2.5:1 caustic:coal, 434°C skin temperatures

ACID WASH TRAIN CONDITIONS:

- #1 pH in T-301 ~2-8 (average = 5)
- #2 pH in T-301 ~10 (no acid injection)
- #3 pH in T-301 ~1-2
- #2A pH in T-301 ~10 (no acid injection; acid wash effluent water used as wash water feed to water wash train)

TABLE 3-10. PRODUCT COAL ASH CONTENT VS. KILN CONDITIONS/ACID WASH pH
MCL TEST RUN NO. 11 (5/14-5/21/92)

pH TEST MATRIX PERIOD NO.	pH	TEST DURATION, HOURS	PRODUCT COAL ASH CONTENT, WT%
1	5*	-60	1.7
2	10**	6	2.2
3	1-2	6	0.5
2A***	10**	-70	3.5 (2.7****)
AVERAGE FOR TEST NO. 11			2.75

* pH varied from 2 to 8.

** pH of 10 may not be accurate - outside of calibration range of pH probe.

*** Acid wash effluent H₂O used as makeup H₂O to water wash train. Deionized wash H₂O to acid wash train wash contaminated with caustic during period 2A.

**** Wash train operated on 6/24-6/25/92 with kiln discharge solids from from Run No. 11 and at #2A conditions but with clean, deionized H₂O.

TABLE 3-11. PRODUCT COAL ASH ULTIMATE ANALYSIS
MCL TEST RUN NO. 11 (5/14-5/21/92)

DATE	TIME	SUBRUN	ASH MINERAL COMPOSITION, WT%***									TOTAL WT% ASH*
			SiO ₂	Al ₂ O ₃	Fe ₂ O ₃	TiO ₂	P ₂ O ₅	CaO	MgO	Na ₂ O	K ₂ O	
5/15	12:00	11A	0.67	0.44	0.31	0.07	0.0	0.28	0.04	0.11	0.10	2.02
5/16	09:35		0.76	0.76	0.36	0.08	0.0	0.30	0.04	0.14	0.13	2.57
5/16	13:30		0.72	0.73	0.45	0.10	0.0	0.41	0.06	0.24	0.18	2.89
5/17	09:30	11C	0.33	0.60	0.28	0.06	0.0	0.43	0.06	0.14	0.11	2.01
5/17	22:10		0.59	0.65	0.50	0.09	0.0	0.76	0.07	0.90	0.18	3.74
5/18	04:00	11D	0.09	0.15	0.04	0.02	0.0	0.06	0.01	0.01	0.03	0.41
5/18	06:00		0.19	0.10	0.11	NA	0.0	0.02	0.01	0.05	0.01	0.49
5/18	12:00	11E	0.77	0.95	0.43	0.13	0.0	0.57	0.09	0.59	0.18	3.71
5/19	20:00		1.39	0.66	0.24	0.07	0.01	0.49	0.07	1.17	0.08	5.18
5/21	01:00		0.68	0.40	1.01	0.06	0.01	0.60	0.08	2.20	0.08	5.12
5/21	04:10		0.77	0.45	1.39	0.07	0.02	0.59	0.07	2.03	0.08	5.47

* As determined by ASTM D3174.

** As determined by ASTM D2795 and D3682. Results normalized to equal total ash.

kiln feed, and a "typical" ash elemental analysis of mine cleaned BV2 coal provided by CONSOL. The results of this calculation are summarized in Table 3-12. While the absolute values of the percent ash removal figures shown in this table are questionable, the relative recoveries provide some worthwhile information. Looking at the major ash constituents (SiO_2 , Al_2O_3 and Fe_2O_3) which account for ~85% of the ash in the feed coal, a trend can be seen in which the removal of these major constituents from the coal increases as the pH of the acid wash train decreases. On the other hand, the Na_2O content of the product coal is only reduced to levels below that in the feed coal when the pH of the acid wash train is maintained at a value of 1 to 2. At higher pH values in the acid wash train, the Na_2O in the product coal increases (with increasing pH) to levels greater than that in the feed coal. The coal from the water wash train, in which the caustic leaching agent is removed from the coal, still contains a small amount of ionically bound sodium. The extent to which this ionically bound sodium is removed from the coal in the acid wash section is dictated by the pH.

3.3.8 Acid Wash Effluent Stream Composition

Samples were taken of the aqueous effluent from the acid wash train for analysis before this stream was eliminated (by sending it to the water wash train as makeup wash water instead of to water treatment) midway through the week of operations. The analytical results are presented in Table 3-13. As can be seen in this table, the increasing iron content of the acid wash effluent stream with decreasing pH confirms that acidification of the coal from the water wash train is effective in removing iron (probably present as iron hydroxide) from the coal.

3.3.9 Product Coal Moisture

Table 3-6 presents the product coal moisture values under the heading "% Original Moisture". The average moisture content of the product coal for Run No. 11 was 45.3% or 0.83 pounds of moisture per pound of dry product coal. The driest product coal produced contained 38.0% moisture or 0.61 pounds of moisture per pound of dry product coal. At this moisture level, the product coal appears "dry". It is probable that at this moisture level, any water present is not surface moisture but is rather moisture that has

TABLE 3-12. MINERAL CONSTITUENTS OF PRODUCT COAL
MCL TEST RUN NO. 11 (5/14-5/21/92)

NUMBERS IN PARENTHESES ARE PERCENT FEED COAL MINERALS REMOVED

MINERAL CONTENT OF PRODUCT COAL, WT%				
WITHOUT ASH REMOVAL	TEST AVG.*	ACID WASH pH=1-2**	ACID WASH pH=2-8***	ACID WASH pH=10****
SiO ₂	3.55	0.52 (85)	0.14 (96)	0.62 (83)
Al ₂ O ₃	1.85	0.55 (70)	0.12 (93)	0.63 (66)
Fe ₂ O ₃	1.87	0.31 (83)	0.07 (96)	0.35 (81)
TiO ₂	0.08	0.08 (0)	0.02 (75)	0.08 (0)
P ₂ O ₅	0.03	0.00 (100)	0.00 (100)	0.00 (100)
CaO	0.47	0.35 (25)	0.04 (91)	0.35 (25)
MgO	0.08	0.05 (37)	0.01 (87)	0.05 (37)
Na ₂ O	0.08	0.27 (0)	0.03 (62)	0.16 (0)
K ₂ O	0.12	0.11 (8)	0.02 (83)	0.13 (0)
				0.68 (81)
				0.80 (57)
				0.46 (75)
				0.11 (0)
				0.00 (100)
				0.66 (0)
				0.08 (0)
				0.74 (0)
				0.18 (0)

* Did not include last 3 samples in table as they were atypical.

** Run 11D

*** Run 11A

**** Run 11C plus 5/18 12:00 sample from Run 11E

Kiln feed ash elemental analysis (per CONSOL for cleaned Pittsburgh BV2 coal, 2x0", Sept. 1991).

WT% OF ASH

SiO ₂	41.2
Al ₂ O ₃	21.2
Fe ₂ O ₃	21.5
TiO ₂	0.92
P ₂ O ₅	0.4
CaO	5.4
MgO	0.97
Na ₂ O	0.94
K ₂ O	1.4
Sb ₃	4.5
TOTAL	98.4%

TABLE 3-13. ACID WASH EFFLUENT TO WATER TREATMENT SECTION
MCL TEST RUN NO. 11 (5/14-5/21/92)

DATE	TIME	pH in T-301	Si	Al	Fe	Na
5/16/92	05:30	2-8	0.15%	510 ppm	583 ppm	0.18%
5/17	22:00	10	0.18%	382 ppm	101 ppm	1.03%
5/18	06:00	1-2	0.11%	246 ppm	924 ppm	0.16%

been sorbed into the internal pores of the coal particles. The highest product coal moisture content recorded for the week was 52.3% or 1.10 pounds moisture per pound of dry product coal.

3.3.10 Product Coal Size Distribution

Size analyses were performed for several product coal samples using a set of microsieves. The results of the size analyses are presented in Table 3-14. On the average, 68% of the product coal passed through a 200 mesh screen (seive opening = 74 microns or 0.074 mm) and collected in the pan. Less than 0.4% of the product coal was too large to pass through a 40 mesh screen (sieve opening = 420 microns or 0.42 mm).

A size distribution for the feed coal fed to the kiln during Run No. 11 was prepared by Tra-Det, Inc. (the firm that sized and dried the coal) and is presented as Table 3-15. The feed coal consisted of 88% plus 200 mesh material versus an average of 32% plus 200 mesh in the final product coal. Considerable size reduction of the coal takes place as the coal transits the kiln and the wash trains.

3.3.11 Heating Value

A number of product coal heating values, as determined by Standard Labs, are included in Table 3-7. The average heating value of the product coal (for the 24 samples analyzed) is 13,860 Btu/lb on a dry basis and 14,345 Btu/lb on an MAF basis. This compares with the kiln feed coal MAF heating value of 15,165 Btu/lb. The average heating value of the product coal collected during the first part of the test run when the kiln skin temperature was 424⁰C (it was later raised to 434⁰C) was 14,430 Btu/lb on a dry basis and 14,725 Btu/lb on a MAF basis. Raising the kiln temperature had the intended effect of reducing the sulfur content of the product coal but at the expense of some loss in heating value. Finally, the average heating value of the product coal corresponding to the period when the kiln wall was free of deposits and the process temperature most closely approached the kiln skin temperature (May 18, 10:00 to May 19, 07:00, Figure 3-2) was 13,130 Btu/lb on a dry basis and 13,720 Btu/lb on a MAF basis.

TABLE 3-14. PRODUCT COAL SIZE ANALYSIS
TEST RUN NO. 11 (5/14-5/21/92)

DATE	TIME	% RETAINED ON SCREEN*						Loss
		40 Mesh 0.42mm	60 Mesh 0.25mm	80 Mesh 0.18mm	100 Mesh 0.15mm	200 Mesh 0.074mm	Pan- 0mm	
5/15	03:30	0.2	0.2	0.2	0.2	7.7	91.9	-0.4
5/15	14:30	0.2	0.8	1.1	1.8	24.2	72.1	-0.1
5/16	09:35	0.2	1.1	2.1	2.3	24.2	70.5	-0.4
5/16	13:30	0.6	2.4	3.5	3.4	19.5	70.8	-0.3
5/16	17:30	0.5	0.7	1.6	2.3	22.8	72.2	-0.0
5/17	03:35	1.6	1.9	3.3	4.0	22.1	67.2	-0.1
5/17	15:30	0.3	0.8	1.5	2.2	18.3	76.6	0.3
5/18	04:00	0.1	4.3	12.9	10.7	31.0	40.9	0.1
5/18	16:15	0.3	0.9	2.4	3.1	27.2	65.8	0.4
5/19	06:35	0.3	1.0	3.0	3.4	25.4	66.7	0.3
5/19	16:00	0.1	1.7	3.7	4.1	28.6	61.3	0.4
5/20	04:22	0.1	0.5	1.8	2.4	25.7	68.4	1.0
5/20	16:05	0.2	1.0	2.2	3.3	29.6	63.4	0.2
5/21	04:10	0.4	1.3	2.1	2.6	24.1	70.2	-0.8

* The screen sizes are given in both mesh size (40 mesh to pan) and in the size of the corresponding screen opening (0.42mm to zero).

TABLE 3-15. COAL FEED SIZE DISTRIBUTION*
MCL TEST RUN NO. 11 (5/14-5/21/92)

SIZE	PERCENT BY WEIGHT
Plus 9 Mesh	0.06
9 Mesh X 10 Mesh	0.12
10 Mesh X 14 Mesh	1.54
14 Mesh X 28 Mesh	35.01
28 Mesh X 100 Mesh	41.69
100 Mesh X 200 Mesh	9.63
200 Mesh X 325 Mesh	2.96
Minus 325 Mesh	<u>8.99</u>
Cumulative	100.00

* As prepared by Tra-Det, Inc. for Lot No. 2 of the Pittsburgh No. 8 coal (CONSOL-Blacksville No. 2) shipped to TRW in April 1992.

3.3.12 Sulfur Forms

A total of ten (10) product coal samples were analyzed for sulfur forms. The results of these analyses are given in Table 3-7. On average, of the sulfur remaining in the product coal, 68% was organic sulfur, 21% was pyritic sulfur and 11% was sulfate sulfur. The May 18, 04:00 product coal sample shows a very high sulfate content. This sample was taken during the period when the maximum amount of sulfuric acid was being injected to control the pH of the acid wash train in the range of 1 to 2. It is suspected that the washing of the product coal was not as thorough as possible and residual sulfates may have been left on the coal.

3.3.13 Volatiles Content

The average volatiles content of the product coal during the week of operations was 25.7% (Table 3-6). During the first part of the run when the kiln skin temperature was 424°C (it was later raised to 434°C), the average volatiles content of the product coal was 27.6%. The average volatiles content of the product coal corresponding to the period when the kiln wall was free of deposits and the process temperature approached the kiln skin temperature (May 18, 10:00 to May 19, 07:00, Figure 3-2) was 25.2%, which is not much different than the average product coal volatiles content for the test run.

3.3.14 Carbonate Content

At the other end of the wash train, samples were taken of the aqueous caustic filtrate from vacuum filter F-201 (see Figure 2-4). This is the stream that is sent to the caustic regeneration system (Section 400). These samples were analyzed for NaOH, Na₂CO₃, humics and coal fines. The results of these analyses are presented in Table 3-16. Eight (8) of the filtrate samples were taken upstream of polishing bag filter F-203 and two (2) of the samples downstream of the bag filter (see Figure 2-4). Based on an average caustic concentration of 14.9% and an average carbonate concentration of 2.8%, an average conversion of caustic to carbonate of 13.1% was calculated. This assumes that no carbonate is introduced to the kiln with the recycled regenerated caustic flake. In fact, there was carbonate in this caustic, which when accounted for reduced the average caustic conversion

TABLE 3-16. VACUUM FILTER F-201 FILTRATE ANALYSIS - COAL FINES, CAUSTIC, CARBONATE AND HUMICS
MCL TEST RUN NO. 11 (5/14-5/21/92)

LOCATION	DATE	TIME	% COAL FINES	% NaOH	% Na ₂ CO ₃	% HUMIC ACID
Before F-203	5/15/92	15:20	1.86	17.35	1.18	0.60
After F-203	5/15	15:20	2.09	16.87	1.31	0.02
Before F-203	5/16	05:30	2.82	16.00	2.03	0.04
After F-203	5/16	05:30	2.46	14.01	1.82	1.42
Before F-203	5/16	15:15	2.73	11.24	2.79	0.42
Before F-203	5/17	22:00	1.75	11.54	2.86	0.25
Before F-203	5/18	06:00	2.44	12.04	2.18	0.32
Before F-203	5/19	13:30	2.13	15.42	5.06	0.30
Before F-203	5/20	10:50	3.76	18.73	3.86	0.89
Before F-203	5/20	21:00	1.89	15.90	4.71	0.41

to carbonate to 8.8%. This will be discussed in more detail in the caustic regeneration and evaporation sections (see Sections 3.4.1.1 and 3.5.2). Considering the range of carbonate concentrations in the filtrate (1.18 to 4.71%), these average conversion figures should be used with caution.

3.3.15 Humics Content

The average humics contents of the filtrate was 0.47 wt% (Table 3-16). Accounting for the humics recycled to the kiln with the regenerated caustic flake, the conversion of coal to humics was calculated to be 5.5%. This is high compared to the ~1 to 2% conversion levels seen in the Phase I program with other coals at kiln temperatures in excess of 400°C. As a cautionary note against placing too much confidence in the conversion figure, the conversion calculation was based on an average humic concentration in the filtrate of 0.47%, whereas the range of humic concentration (0.02% to 1.42%) was very broad.

3.3.16 Total Organic Carbon (TOC) Content

The filtrate was analyzed for total organic carbon content (TOC). This is the residual organic material remaining in solution after a sample of solution has been acidified to precipitate humics and represents the "phenols" in solution. Table 3-17 summarizes the filtrate TOC analysis. At an average TOC of 260 mg/l or ~0.024 wt% (for a filtrate s.g.=1.1), and assuming that there are no phenolics in the caustic flake recycled to the kiln, the conversion of coal to phenols is ~0.3%. Historical data for coal conversion to phenolics are not available from the test runs in the Phase I program.

3.3.17 Partition of Sulfur, Silica, Alumina and Iron

The filtrate was also analyzed for sulfur, silica, alumina and iron. The results of these analyses are presented in Table 3-18. Calculations were performed, using the average and maximum end-of-run component values in Table 3-18, to determine the quantities of these components in the filtrate. The results of these calculations are summarized in Table 3-19. It can be seen that the amount of the components in each instance exceeds the quantity present in the fresh feed coal. The explanation for this is that these

TABLE 3-17. REGENERATION FEED TOTAL ORGANIC CARBON (TOC)*
MCL TEST RUN NO. 11 (5/14-5/21/92)

DATE	TIME	TOC, mg/l
5/15/92	10:50	280
5/17	22:00	280
5/20	10:50	220

* Organics remaining in solution after humics are removed by acidification. These are the phenolic compounds dissolved in the solution.

TABLE 3-18. VACUUM FILTER F-201 FILTRATE ANALYSIS - SULFUR, SILICA, ALUMINA AND IRON
MCL TEST RUN NO. 11 (5/14-5/21/92)

DATE	TIME	SULFUR WT%	SiO ₂ WT%	Al ₂ O ₃ WT%	Fe ₂ O ₃ WT%
5/15	15:20	0.10	0.39	0.17	0.20
5/16	05:30	0.15	0.36	0.14	0.27
5/16	15:15	0.12	0.52	0.17	0.18
5/18	06:00	0.13	0.55	0.15	0.09
5/19	13:30	0.22	0.86	0.29	0.19
5/20	10:50	0.23	0.91	0.38	0.41
5/20	21:00	0.26	0.88	0.34	0.09
AVERAGE		0.17	0.63	0.23	0.20

TABLE 3-19. COMPARISON OF SULFUR, SILICA, ALUMINA AND IRON OXIDE IN
FEED COAL VERSUS FILTRATE TO REGENERATION
MCL TEST RUN NO. 11 (5/14-5/21/92)

	LBS/HR		
	SULFUR	SiO ₂	Al ₂ O ₃ Fe ₂ O ₃
FEED COAL*	0.16	0.27	0.14 0.14
FILTRATE TO REGENERATION**			
AVERAGE	0.19	0.70	0.26 0.22
MAXIMUM @ END OF RUN***	0.28	0.99	0.41 0.45

* For 8.8 lbs/hr feed coal to kiln at 1.86% sulfur, 7.40% ash (41.2% SiO₂, 21.2% Al₂O₃, 21.5% Fe₂O₃).

** For 109 lbs/hr filtrate.

*** The maximum values for the two samples from May 20 (see Table 3-18) were used.

components are being extracted from the coal but are not being completely rejected from the caustic solution in the regeneration unit. These components are not expected to be completely rejected from the regenerated caustic as each of these components has a solubility in caustic. The values of these components will continue to build in the regenerated caustic recycled to the kiln until they reach their individual solubility limits in the caustic. It is not apparent from the data in Table 3-18 whether steady-state conditions have been reached.

It should be noted that the filtrate has a significant iron content. It was thought that most of the iron extracted from the coal would travel through the water wash train with the coal solids as insoluble (in caustic) iron hydroxide. This iron hydroxide theory may have to be revised in view of the high iron content exhibited by the wash train filtrate solution that is sent to regeneration.

3.4 CAUSTIC REGENERATION OPERATIONS (SECTION 400)

Caustic filtrate flows from the first water wash train vacuum filter F-201 through polishing bag filter F-203 into regeneration reactor T-401. A schematic of the caustic regeneration system is shown in Figure 2-7. Flow from the filter averaged ~0.2 GPM. (Wash water flow to the wash water train was 0.18 GPM.) This flow exceeded the capacity of the downstream caustic evaporation unit. Therefore, to avoid building inventory in the regeneration system, ~0.05 GPM (or ~25%) of the wash train filtrate was diverted ahead of T-401 and sent to waste disposal.

Caustic flake was added to the filtrate in T-401 to concentrate the solution and drive some sodium carbonate from solution. The caustic was fed from a hopper into T-401 using a screw feeder. This unit malfunctioned (screw plugged and/or screw drive shut-off accidentally) several times during the test run which resulted in an intermittent flow of caustic into T-401. No lime was added to tank T-401 during Test Run No. 11.

Tank T-401 level averaged ~65% full, giving a liquid inventory of ~50 gallons in the tank. At a flow rate of ~0.15 GPM (9 GPH) into the tank, the residence time for regeneration was ~6 hours. The caustic solution from

T-401 was centrifuged and the centrate stored in T-405, the feed tank for the caustic evaporator. The residence time of the caustic in this feed tank was also ~6 hours. The caustic solutions in both T-401 and T-405 were maintained at $>130^{\circ}\text{F}$.

3.4.1 Caustic Solution Analysis

The regeneration unit feed (water wash train filtrate) analysis has already been summarized in an earlier section (see Tables 3-16 through 3-19). Regenerated caustic (effluent from T-401 which has been centrifuged in C-401 for removal of precipitated solids) was analyzed for caustic, carbonate, humics and coal fines, and the results are summarized in Table 3-20.

3.4.1.1 Carbonate

The caustic and carbonate contents of the feed solution (to regeneration reactor T-401) and of the regenerated solution (centrate from the centrifuge C-401) are plotted graphically in Figures 3-7 and 3-8, respectively. As can be seen in these figures, there was an extended period in the middle of the test run during which no caustic flake was being added to the regeneration reactor. This resulted in a dilute regenerated alkali stream with very little carbonate removal (precipitation) from solution. Late in the test run when the caustic flake addition to the reactor was restored, a significant fraction of the carbonate in the regenerator feed was removed from solution.

3.4.1.2 Sulfur, Silica, Alumina and Iron

Analyses of the sulfur, silica, alumina and iron (assumed to be iron oxide) in the feed solution (to regeneration reactor T-401) and in the regenerated solution (from centrifuge C-401) are summarized in Table 3-21. As can be seen, it is only in the latter part of the test run (5/19 and 5/20) when any removal of sulfur, silica, alumina and iron from solution in the regeneration reactor and centrifuge was seen. Each of these components has a solubility in caustic and it is probable that the solubility limits were approached only after several days of operations. The relatively slow buildup of these constituents is a direct result of the continuous purge of these constituents from the MCL unit in the ~25% of the wash water train

TABLE 3-20. REGENERATED ALKALI ANALYSIS
MCI TEST NO. 11 (5/14-5/21/92)

DATE	TIME	% NaOH	% Na ₂ CO ₃	% COAL FINES	% HUMICS
5/15/92	15:20	27.88	1.73	0.63	0.08
5/16	05:30	30.60	1.54	1.76	0.06
5/16	15:15	32.10	1.84	2.06	0.33
5/17	22:00	15.46	3.65	0.26	0.14
5/18	06:00	12.97	2.92	0.17	0.13
5/19	13:30	32.75	1.68	0.46	0.29
5/20	10:50	36.47	1.10	1.24	0.14
5/20	18:20	34.35	0.93	1.54	0.09
5/20	21:00	32.58	1.09	1.35	0.08

NaOH IN REGENERATION FEED/REGENERATED SOLUTION

Figure 3-7. Regeneration System - Percent NaOH in Regeneration Feed/Regenerated Alkali - Test Run No. 11

Na₂CO₃ IN REGENERATION FEED/REGENERATED SOLUTION

Figure 3-8. Regeneration System - Percent Na₂CO₃ in Regeneration Feed/Regenerated Alkali - Test Run No. 11

TABLE 3-21. REGENERATION FEED/REGENERATED SOLUTION ANALYSIS
MCL TEST RUN NO. 11 (5/14-5/21/92)

	DATE	TIME	WT % IN SOLUTION			
			SULFUR	SiO ₂	Al ₂ O ₃	Fe ₂ O ₃
FEED*	5/16	15:15	0.12	0.52	0.17	0.18
REGENERATED	5/17	22:00	0.24	0.69	0.18	0.13
FEED*	5/18	06:00	0.13	0.55	0.15	0.09
REGENERATED	5/18	06:00	0.18	0.75	0.17	0.13
FEED*	5/19	13:30	0.22	0.86	0.29	0.19
REGENERATED	5/19	13:30	0.16	0.45	0.08	0.07
FEED*	5/20	10:50	0.23	0.91	0.38	0.41
REGENERATED	5/20	10:50	0.20	0.64	0.17	0.02

* Filtrate from vacuum filter F-201.

filtrate which was diverted ahead of regeneration reactor T-401 and sent to waste disposal.

Table 3-22 is a comparison of: 1) the rate of addition of sulfur, silica, alumina and iron to the MCL process in the fresh coal fed to the kiln, 2) the amount of these constituents removed from the coal, and 3) the amount of these constituents in the wash water train filtrate diverted to waste disposal, using the filtrate analyses for 5/19 and 5/20 given in Table 3-21. At this point late in the run, with no waste stream from the acid wash system, the only outlets for these constituents from the process are the 25% of the wash water train filtrate diverted to waste disposal and the solids reject from the regeneration centrifuge C-401. As can be seen in Table 3-22, in most instances the portion of the filtrate stream diverted to waste disposal contained all or most of the constituents that were removed from the feed coal. Thus, a "steady-state" condition may have been achieved and the levels of these constituents in the regeneration feed stream would not be expected to increase any further with continued testing. It is possible that at these concentrations, the saturation levels of these constituents in the caustic solution were being approached. If this were the case, little, if any, of these constituents would be expected to precipitate from solution in the regeneration reactor.

3.4.2 Centrifuge Cake Analysis

Solids from centrifuge C-401, which is located downstream of regeneration reactor T-401, were analyzed. In some instances the solid samples were quite wet. The procedure used for preparing the samples for analysis is shown in Figure 3-9. Each sample was dissolved/washed with water to remove the water soluble components (NaOH , Na_2CO_3 , Na_2S) in the cake and then filtered. The filter cake was rinsed with additional water and then dried. The dried cake was analyzed by an outside laboratory for sulfur, ash and heat content. The filtrate (plus cake rinse water) was analyzed for NaOH , Na_2CO_3 , and sulfur. The composition of the original sample was reconstructed from the results of the analyses and from the sample weights in each step of the procedure outlined in Figure 3-9.

TABLE 3-22. ASH AND SULFUR REJECTION FROM MCL FACILITY
MCL TEST RUN NO. 11 (5/14-5/21/92)

	AMOUNT IN FEED COAL*	ESTIMATE REMOVED FROM COAL**	IN STREAM TO WASTE DISPOSAL***
SULFUR	0.16 lb/hr	0.14 lb/hr	0.07 lb/hr
SiO ₂	0.27	0.22	0.23
Al ₂ O ₃	0.14	0.08	0.09
Fe ₂ O ₃	0.14	0.11	0.08

* Based on 8.8 lbs/hr coal into kiln with 1.86 wt% sulfur and 7.4 wt% ash (41.2% SiO₂, 21.2% Al₂O₃, 21.5% Fe₂O₃).

** See Table 3-12. For pH = 10 in acid wash train, percent removal from coal for SiO₂ = 81%, Al₂O₃ = 57%, and Fe₂O₃ = 75%. Sulfur removal from feed coal ~85%.

*** Based on 0.05 GPM or 3 GPH (~27 lbs/hr) of wash train filtrate flow to waste disposal.

TRW

PROCEDURE FOR PREPARING
REGENERATION CENTRIFUGE
CAKE SAMPLE FOR ANALYSIS

DRAWN EMB DATE 2/16/93

SCALE REV SHEET 1 OF 1

SAMP-ANAL

Figure 3-9. Procedure for Preparing Regeneration Centrifuge Cake Sample for Analysis - Test Run No. 11

Table 3-23 summarizes the relative amounts of the liquid/solid fractions of the regeneration centrifuge cake samples and the composition of the solid fraction of the samples. As can be seen in Table 3-23, on May 18 when no caustic flake was being added to T-401 to concentrate the solution in caustic and thus to precipitate the Na_2CO_3 from solution, the solids in the centrifuge cake consisted entirely of "coal" fines. Later in the test run when caustic flake was added to T-401, the solids in the centrifuge cake consisted primarily of precipitated Na_2CO_3 .

Table 3-24 summarizes the analyses of the "coal" fraction of the regeneration centrifuge cake samples. It can be seen that the "coal" fraction, excluding the initial sample, contains sulfur at about the level seen in the plant product coal. The ash content of the "coal" fraction (9.6 to 18.8%), however, is much higher than the ash seen in the plant product coal (average ~3% ash) and indeed is higher than that in the feed coal to the kiln (7.4% ash). This high ash content could be interpreted as coal fines that passed through the vacuum filter plus mineral matter that has precipitated from the regenerated solution. The MAF heating value of the "coal" fraction at about 13,500 to 14,200 Btu/lb shows that this material is indeed fines of kiln-treated product coal (MAF heating value = 13,700 to 14,400 Btu/lb).

The regenerated cake sample filtrate (see Figure 3-9) was also analyzed for soluble sulfur (see Table 3-25). The sulfur levels, corrected for the amount of dilution utilized in sample preparation, were 2 to 8 times those seen in the regenerated centrate solution from C-401 (Table 3-21). This could be interpreted to mean that Na_2S precipitate was present in the centrifuge cake and was redissolved in water when the cake sample was prepared for analysis. No humics were seen in the centrifuge cake samples.

3.4.3 Effect of Extended Residence Time

Approximately two weeks after the completion of the test run, the inventories in regeneration reactor T-401 and evaporator feed tank T-405 (which provides additional residence time for regeneration) were sampled (liquid had been retained in the tanks) to see if additional regeneration had taken place. The tanks had not been maintained at temperature. The tanks

TABLE 3-23. REGENERATION UNIT CENTRIFUGE CAKE SAMPLE ANALYSIS
MCL TEST RUN NO. 11 (5/14-5/21/92)

DATE	TIME	SAMPLE CONSISTS OF		SOLID FRACTION CONSISTS OF	
		% LIQUID	% SOLID	% "COAL"	% Na ₂ CO ₃
5/18/92	16:00	62	38	100	0
5/19	12:50	52	48	12	88
5/19	20:06	57	43	14	86
5/20	12:40	84	16	20	80

TABLE 3-24. REGENERATION UNIT CENTRIFUGE CAKE "COAL" FRACTION ANALYSIS
MCL TEST RUN NO. 11 (5/14-5/21/92)

DATE	TIME	% SULFUR	% ASH	HEATING VALUE BTU/LB MAF
5/18/92	16:00	0.98	11.62	14,044
5/19	12:50	0.17	18.82	13,555
5/19	20:06	0.36	10.75	13,843
5/20	12:40	0.53	9.62	14,223

TABLE 3-25. SOLUBLE SULFUR IN CENTRIFUGE CAKE
MCL TEST RUN NO. 11 (5/14-5/21/92)

DATE	TIME	SULFUR IN SAMPLE ANALYZED	SAMPLE DILUTION FACTOR FROM LIQUID FRACTION OF CAKE	SULFUR IN LIQUID FRACTION OF CAKE	SULFUR IN REGENERATED SOLUTION
5/18/92	16:00	0.05 wt%	X 13.9 =	0.70% vs.	0.18%
5/19	12:50	0.07 wt%	X 19.3 =	1.35% vs.	0.16%
5/19	20:06	0.07 wt%	X 14.7 =	1.03% vs.	0.16%
5/20	12:40	0.08 wt%	X 3.6 =	0.29% vs.	0.20%

were sampled at the top, middle, and bottom levels. These samples and a sample of solids taken from T-401 were analyzed for NaOH, Na_2CO_3 , sulfur, Si, Al, and iron. The results are summarized in Table 3-26. A comparison of these analyses with the last analyses of regenerated solution (C-401 centrate) taken near the end of the test run (also shown in Table 3-26) shows no obvious change in the sulfur, Si, Al or iron content of the liquid in these tanks. This indicates that no significant regeneration had taken place in the time (2 weeks) that had elapsed since the end of the test run.

3.5 CAUSTIC EVAPORATION OPERATIONS (SECTION 500)

A schematic of the evaporation unit is shown in Figure 2-8. The caustic evaporation system was operated for 119 hours during Run No. 11. A total of ~2,500 pounds of caustic flake was produced in the system at an average of 21 lbs/hour of flake. The concentration of the regenerated aqueous caustic feed to the evaporation unit varied during the week of operations from a low of 13 wt% NaOH (plus ~3% Na_2CO_3) to a high of 36 wt% NaOH (plus ~1% Na_2CO_3 , see Figures 3-7 and 3-8). On a few occasions feed to the evaporation unit had to be interrupted because of plugging in either the evaporator feed line or the molten caustic product line feeding the caustic flaker. These plugs were cleared by flushing the unit with water. The "surging" that was observed in this unit during earlier test operations continued but not to the extreme degree noted previously.

The caustic flake was collected, mixed with fresh coal, and recycled back into the kiln. Due to the size of the caustic flake, pneumatic transfer of the flake was not attempted. The coal/recycled caustic was instead transferred directly from barrels into the kiln feed hopper.

3.5.1 Moisture Content

Samples of the caustic flake produced during the test run were analyzed for moisture content. The results of this analysis are summarized in Table 3-27. The flake moisture content ranged from 3 to 14 percent, with the flake becoming drier as the test progressed.

TABLE 3-26. RESULTS OF EXTENDED RESIDENCE TIME IN REGENERATION SYSTEM
MCL TEST RUN NO. 11 (5/14-5/21/92)

SAMPLE DATE	SAMPLE LOCATION	% NaOH	% Na ₂ CO ₃	% SULFUR	% Si	Al	Fe
6/2/92	T401-Top	32.37	1.23	0.24	0.29	880 ppm	0.13%
	T401-Middle	32.47	0.84	0.26	0.22	871 ppm	0.11%
	T401-Bottom	32.46	3.53	0.29	0.26	1100 ppm	0.24%
	T401-Solids	29.79	11.34	0.35	0.17	718 ppm	0.27%
5/20 21:00	T405-Top	33.88	1.18	0.22	0.14	687 ppm	789 ppm
	T405-Middle	33.89	1.06	0.22	0.18	749 ppm	657 ppm
	T405-Bottom	33.31	1.89	0.26	0.19	916 ppm	1100 ppm
5/20 21:00	C401-Centrates	32.58	1.09				
5/20 10:50	C401-Centrates			0.20	0.30	930 ppm	140 ppm

Note: Stopped flow into T-401 @ 5/20 21:50.

TABLE 3-27. REGENERATED CAUSTIC FLAKE MOISTURE CONTENT
MCL TEST RUN NO. 11 (5/14-5/21/92)

DATE	TIME	% MOISTURE
5/16/92	05:30	14.1
5/17	22:00	10.1
5/18	06:00	13.8
5/18	06:00	11.9
5/19	16:40	7.3
5/19	16:40	6.9
5/20	10:50	2.4
5/20	18:10	3.0

3.5.2 Caustic Flake Analysis

Caustic flake samples were also analyzed for NaOH and Na₂CO₃ content. These analyses are summarized in Table 3-28. Note that in most instances the ratio of NaOH to Na₂CO₃ in the caustic flake corresponds closely to the NaOH to Na₂CO₃ ratio in the evaporator feed solution. NaOH, Na₂CO₃ and H₂O accounts for 92 to 97% of the weight of the flake. The remainder is attributable to the small amount of coal fines, humics, sulfides and mineral matter present in the regenerated flake. Table 3-20 gives the percent coal fines and humics in the caustic evaporator feed. Multiplying these figures by the concentration factor achieved in the evaporator (2.5 to 5.3) results in the coal fines and humics accounting for 1.6 to 3.5% of the weight of the caustic flake.

Caustic flake samples were analyzed for sulfur, silica, alumina and iron oxide. These results are presented in Table 3-29. According to these results, Na₂S plus mineral matter could account for 2 to 3% of the weight of the caustic flake.

3.5.3 Heat Transfer Coefficients

Heat transfer calculation were performed for the caustic evaporation unit at selected times during the test operations. The results of the calculations are summarized in Table 3-30. Figure 3-10 shows the key temperature measurements required for the heat transfer coefficient calculations. The overall heat transfer coefficient varied from a low of 28 Btu/hr-ft²-°F in the middle of the run (May 18, 04:00 to 11:00), during a period in which intermittent evaporator feed line and molten product line plugging problems were being experienced, to a high of 40 Btu/hr-ft²-°F at the end of the test run. The increase in heat transfer coefficient observed from the middle to the end of the test run may be attributed to the cleansing action of the periodic flushes of the evaporator with deionized water that were made during that period.

Table 3-31 summarizes the heat transfer coefficients that were obtained in the caustic evaporator during off-line tests that were conducted in the evaporation unit prior to Test Run No. 11. It can be seen that the heat

TABLE 3-28. CAUSTIC FLAKE ANALYSIS
MCL TEST RUN NO. 11 (5/14-5/21/92)

DATE	TIME	(1) % NaOH	(2) % Na ₂ CO ₃	(3) % MOISTURE	% Σ(1)+(2)+(3)	FLAKE NaOH:Na ₂ CO ₃	FEED* NaOH:Na ₂ CO ₃
5/18/92	06:00	68.73	15.14	12.9	96.8	4.54	4.44
5/19	16:40	83.60	4.32	7.1	95.0	19.35	19.49
5/20	18:10	85.33	3.85	3.0	92.2	22.16	36.94

* Based on a regenerated caustic sample (C-401 centrate) taken at about the same time as caustic flake sample. Note that the evaporator feed tank T-405 provides an additional ~6 hours of residence time for the caustic solution before it is fed to the caustic evaporator.

TABLE 3-29. CAUSTIC FLAKE SULFUR AND MINERAL MATTER ANALYSIS
MCL TEST RUN NO. 11 (5/14-5/21-92)

DATE	TIME	% SULFUR	% SiO ₂	% Al ₂ O ₃	% Fe ₂ O ₃
5/18/92	06:00	0.46	1.22	0.51	0.36
5/19	16:40	0.34	0.86	0.30	0.26
5/20	18:10	0.29	0.96	0.38	0.11

TABLE 3-30. EVAPORATOR PERFORMANCE DATA
MCL TEST RUN NO. 11 (5/14-5/21/92)

DATE	TIME PERIOD	EVAPORATOR FEED			HOT OIL TEMP IN/OUT, °F	FLAKE LBS/HR	TEMPERATURE APPROACH, °F	OVERALL HEAT TRANSFER COEFFICIENT BT/HR-FT ² -°F
		% NaOH*	LBS/HR	TEMP, °F				
5/16	08:50-13:37	27	98	252	698/697	31.1	124	33
5/17	01:30-09:30	27	98	264	700/688	30.0	104	35
5/18	04:00-11:00	18	90	243	700/688	19.2	159	28
5/19	00:50-06:36	27	98	252	702/690	27.9	90	37
5/19- 5/20	23:30-04:00	27	98	278	701/688	32.4	81	40

* Based on specific gravity measurements.

MCL EVAPORATOR TEMPERATURES

Figure 3-10. Evaporator Temperatures - Test Run No. 11

TABLE 3-31. MCL CAUSTIC EVAPORATION OFF-LINE TESTS
PRIOR TO TEST RUN NO. 11

DATE	FEED RATE (lb/hr)	FEED TEMP. (deg F)	OIL TEMP. (deg F)	U overall (Btu/hr-ft ² -°F)	FLAKE RATE (lb/hr)
05/05/92	76 40% fresh	366	704	24	34
05/06/92	79 40% fresh	354	703	30	35
05/06/92	97 40% fresh	300	702	36	43
05/06/92	93 40% regen.	262	703	31	41
05/07/92	84 40% regen.	291	696	34	37
05/07/92	97 40% regen.	337	695	39	43
05/07/92	93 40% regen.	284	697	38	41

Assumptions

- Feed rate based on measured flake rate
- Approximately 10% moisture in flake

transfer coefficients were in the 35 to 40 Btu/hr-ft²-°F range which is similar to the performance achieved during Test Run No. 11.

3.6 MATERIAL BALANCE

An overall coal material balance was performed for the week of test operations. The material balance is summarized in Table 3-32. A total of 1193 pounds of MAF coal was fed to the kiln. The MAF product coal collected totaled 634 pounds. The 695 pounds of kiln discharge bagged during the test run were estimated to contain 172 pounds of coal. Approximately 2.4% (or 32 pounds) of the coal fed to the kiln was converted to volatiles in the kiln off-gas. Another 5.8% (or 69 pounds) of the coal feed was converted to humics and phenols. Approximately 3.5% (41 pounds) of the feed coal was converted to carbonate. A total of ~34 pounds of coal was accounted for as coal fines in bag filters. An estimated 21 pounds of sulfur were removed from the coal. The coal left in the wash train and kiln at the end of the run was estimated at 25 pounds and 10 pounds, respectively. The coal fines in the ~250 gallons of caustic filtrate (at 2.4% coal fines) sent to waste disposal were estimated at 58 pounds. The coal fines in the regeneration unit centrifuge cake collected were estimated to be 45 pounds. The 125-gallon liquid inventory of T-401 and T-405 at the end of the test run was estimated to contain 19 pounds of coal fines. Finally, the 235 pounds of regenerated caustic flake on hand at the end of the test run were estimated to contain 9 pounds of coal fines. A total of 1169 pounds of coal was accounted for as compared to the 1193 pounds of coal fed to the kiln. The material balance closure was therefore 98.0%.

An overall sulfur balance was performed for the week of test operations. The material balance is summarized in Table 3-33. Approximately 76% of the sulfur in the coal fed to the kiln was accounted for. This is not a bad balance considering: 1) the relatively small quantity of sulfur that was being tracked, and 2) that average analytical results from a few samples were taken as representative of the entire week of operations.

3.7 SUMMARY OF TEST RUN NO. 11 - OBSERVATIONS AND CONCLUSIONS

- All sections of the MCL plant were operated in an integrated fashion for an extended period of time.

TABLE 3-32. OVERALL COAL MATERIAL BALANCE
MCL TEST RUN NO. 11 (5/14-5/21/92)

LOCATION	POUNDS
Coal Product (1b MAF)	634
Coal in Kiln Discharge Collected (1b MAF)	172
Volatiles in Kiln Off-Gas	32
Humics + Phenols	69
Carbon in Carbonates	41
Coal Fines in Bag Filters	34
Sulfur Removed from Coal	21
Coal Left in Wash Section (1b MAF)	25
Coal Left in Kiln (1b MAF)	10
Coal in Filtrate to Waste Disposal	58
Coal Fines in Regeneration Unit Centrifuge Cake	45
Coal Fines in Caustic Inventory in T-401 and T-405 at End-of-Run	19
Coal Fines in Evaporator Flake at End-of-Run	<u>9</u>
Total Coal and Coal Products	1169
Coal Feed to Kiln (1b MAF)	1193
Material Balance Closure	98.0%

TABLE 3-33. OVERALL SULFUR MATERIAL BALANCE
MCL TEST RUN NO. 11 (5/14-5/21/92)

LOCATION	POUNDS
Sulfur in Product Coal	2.4
Sulfur in Kiln Discharge Collected	3.5
Sulfur in Filtrate to Waste Disposal	5.3
Sulfur in Regeneration Unit Centrifuge Cake	2.1
Sulfur in T-401 and T-405 Inventory at End-of-Run	4.0
Sulfur in Regenerated Caustic Flake at End-of-Run	1.2
Sulfur in Residual Coal in Bag Filters, Kiln and Wash Train at End-of-Run	<u>0.2</u>
Total Sulfur Accounted For	18.7
Sulfur in Coal Feed to Kiln	24.5
Material Balance Closure	76.3%

- A total of 650 pounds (dry basis) of product coal was produced during the test run, with product coal produced during a 90-hour period containing less than 0.3 wt% sulfur (less than 0.44 lbs SO₂/million Btu). This represents a 90% reduction in sulfur from the 4.5 lbs SO₂/million Btu for the raw run-of-mine (ROM) coal, thus meeting the most stringent U.S. standards. Product coal was produced with a sulfur content as low as 0.11 wt% (0.17 lbs SO₂/million Btu or 198 mg SO₂/Nm³) which corresponds to a 96% reduction in sulfur from ROM and which is one-half of the EC standard of 400 mg SO₂/Nm³.
- The use of an internal auger does not completely prevent the buildup of a layer of material which sticks to the inner surface of the kiln tube. This insulating layer reduces the actual process temperature (for a given outer tube wall temperature) and results in somewhat reduced sulfur removal from the coal. In addition, this layer occasionally breaks free of the kiln wall resulting in a sudden large increase in kiln solids discharged into the wash train. This upsets the operation of the water wash train.
- Approximately 9% of the caustic is being converted to carbonate. The mechanism of carbonate formation is not well understood at this time. The lack of hydrogen in the kiln off-gas would seem to preclude the NaOH-steam-carbon reaction as the source of carbonate formation. It is also thought unlikely that a leakage of air into the kiln, which is normally operated at a slightly positive pressure, is the source of the carbonate formation.
- As in previous test runs, blinding problems were experienced with the second vacuum filter in the water wash train. This filter was taken off-line after a few hours. The caustic solutions in the front end of the water wash train are "live". The fact that blinding problems were not experienced in the first filter (which had the same filter cloth as the second filter) suggests a time dependency for "blinding" components to come out of solution. Perhaps if the total residence time in both filters can be significantly reduced, the "blinding" problem could be shifted down the wash train to the centrifuges where it would not cause a problem (evidenced by the fact that this was the mode of operation with the single filter on-line).
- The acid wash train was operated at a number of different pH levels (in T-301) during the test run. As expected, reducing the pH (increased acidification) is effective in removing additional ash from the product coal. However, even without acidification, a very significant removal of ash from the product coal was achieved.
- A new process configuration was tested during the test run in which centrate from the acid wash train (without acid addition) was used as the water makeup for the water wash train. This configuration eliminates the need for waste water treatment (addition of Fe₂(SO₄)₃ and lime) of the acid wash centrate. The coal product produced has a moderate ash level. For applications where a low ash level is not critical, this process configuration could mean significant savings in both capital and consumables. One caveat - an acid wash (at low pH) will be required if it is necessary that the

product coal contain sodium in levels no higher than the feed coal. Water washing of the coal is not very effective in removing ionically bound sodium which is present in the coal from the water wash train at levels significantly higher than the sodium in the feed coal.

- A large amount of mineral matter was not being rejected from solution in the caustic regeneration system. Due to capacity limitations in the caustic evaporation unit, a significant fraction (~25%) of the regeneration feed solution was purged to waste disposal. The removal of mineral matter in this purge stream most likely prevented the buildup of the mineral matter components in the regenerator feed solution to the higher levels required to exceed the individual component solubility limits necessary for precipitate formation.
- The caustic evaporator performed as expected based on pre-run off-line tests. A total of 119 hours of run time was achieved for this unit, which is a significant improvement compared to the 5 hours achieved in Run No. 10. More importantly, the evaporator was kept on-line, with occasional short interruptions for water flushing, to supply the necessary amount of regenerated caustic flake to the kiln. It appears that the caustic evaporator can sustain a flake production rate of at least 25 lbs/hour which at a caustic to coal ratio to the kiln of 2.75:1 (for 10% moisture caustic flake) can support a kiln coal feed rate of ~9 lbs/hours.

4. WASH TRAIN TEST FOLLOWING RUN NO. 11 (JUNE 24-25, 1992)

During Test Run No. 11 (May 14 to 21, 1992), a new process configuration was tested (Run 11E) in which an acid wash of the MCL coal product was not performed, although the acid wash train equipment (consisting of three centrifuges) was used for additional stages of water washing. Furthermore, the wash effluent from the acid wash train (without acid injection) was used as makeup wash water for the water wash train rather than being sent to water treatment, thus eliminating the one remaining liquid process waste stream.

This process modification (eliminating the acid addition/wash step, the acid waste water treatment step (Section 600), and one of two wash water streams) could result in a potential reduction in processing costs of nearly 25%, reducing process cost forecasts to under \$45/ton (17 mils/kW-hr). This would place the MCL Process in a significantly advantageous cost position relative to FGD for boilers and furnaces smaller than 200 MW_e for those applications for which a low sulfur, but "moderate" ash content coal is acceptable.

Unfortunately, during Test Run No. 11, for the period (Run 11E) in which this new process configuration was tested, the deionized wash water feed to the acid wash train (without acid injection) had been contaminated with caustic. An upset in the caustic evaporator resulted in an overhead condensate of high caustic content. This condensate was recycled to the deionized water storage tank. The contamination of the deionized water during Run 11E resulted in the production of MCL coal during this period with higher than anticipated ash content.

Following the completion of Test Run No. 11, a decision was made to utilize kiln discharge solids collected during that run to perform a wash train test in which the conditions existing in the wash trains during Run 11E would be duplicated but this time conducting the test with a supply of uncontaminated deionized wash water.

A few modifications were made to the wash train after Test Run No. 11 to improve its operation. These included: 1) limiting the maximum flow of the

slurry pumps so as to prevent them from periodically overwhelming the wash train centrifuges, and 2) modifying the lines between the centrifuges and centrate tanks to include surge capacity along with overflow spill capability to prevent centrate from occasionally backing up into the centrifuge cake.

The wash train test was conducted on June 24 to 25, 1992. Over a period of 18 hours, approximately 640 pounds of coal/caustic kiln discharge solids (generated from a 2.5:1 caustic:coal kiln feed mixture) were metered by a screw feeder into the grinder feeding the dissolver tank. A screw feeder had been moved from the regeneration section and recalibrated for the coal/caustic kiln discharge solids. Deionized water was fed into the acid wash train at a rate of 0.18 GPM. No acid was injected into the acid wash train. The effluent water from the acid wash train was utilized as makeup water to the water wash train. At the start of the wash train test both vacuum filters were put into service. However, as in Test Run No. 11, four to five hours after the start of the test, the second vacuum filter (with a 100 mesh screen) began to exhibit signs of filter cloth blinding. This filter was then bypassed for the remainder of the wash train test.

A number of samples of coal product were taken for analysis during the wash train test. The analytical results are summarized in Table 4-1. The table also includes comparative results from Run 11E which was conducted under identical conditions but with contaminated wash water (and from Run 11D in which an acid wash was performed on the MCL product coal). As can be seen in this table, during Run 11E the average ash content of the product coal was 4.23 wt%. This was reduced to 3.58 wt% after two additional laboratory water washes were performed on the product coal. Most likely this ash reduction was the result of the removal of residual sodium hydroxide from the coal. In comparison, the average ash content of the product coal collected during the June 24 to 25 wash train test was 2.70 wt%. This was reduced to 2.36 wt% after two additional laboratory water washes. The product coal sulfur levels achieved in Run 11E and in the June 24 to 25 wash train test are approximately the same.

As mentioned above, the product coal samples from the June 24 to 25 wash train test that were given two additional water washes in the laboratory were

TABLE 4-1. MCL WATER WASH TRAIN TEST (JUNE 24 TO 25, 1992)
PRODUCT COAL SULFUR/ASH

	WT% S	WT% ASH	
<u>COAL FEED</u>	-2.3	-7.9	
<u>COAL PRODUCT</u>			
• <u>May 14-21 Test (Run 11D):</u>			
w/ Acid Wash, pH=1-2			
5/18 06:00	0.43	0.49	
No Acid Wash (Run 11E) (Note 1)			
5/19 20:00	0.45	4.37	} Avg. 4.23%
5/21 01:00	0.27	3.84	
5/21 04:10	0.52	4.47	
After 2 Additional Lab DI Water Washes			
5/19 20:00	NA	3.71	} Avg. 3.58%
5/21 01:00	NA	3.13	
5/21 04:10	NA	3.91	
• <u>June 24-25 Test:</u>			
No Acid Wash (Note 2)			
6/25 01:00	0.28	2.27	} Avg. 2.70%
6/25 05:00	0.36	2.84	
6/25 09:00	0.40	2.99	
After 2 Additional Lab DI Water Washes			
6/25 01:00	NA	2.14	} Avg. 2.36%
6/25 05:00	NA	2.32	
6/25 09:00	NA	2.63	

NOTE 1: Acid wash train equipment used for additional stages of water washing. Water used for washing during this time period was contaminated with caustic.

NOTE 2: Acid wash train equipment used for additional stages of water washing. Clean deionized water was used for washing during this time period.

analyzed for ash content. The sodium content of these samples was also determined. These samples contained 0.26 to 0.32 wt% sodium. Since the laboratory water washes were quite thorough, this coal sodium level is probably about as low as can be practically obtained with water washing. This is to be contrasted with a coal sodium level of ~0.03 wt% that was obtained in Run 11D when the product coal was acid washed at a pH of 1 to 2. To put these figures in the proper perspective, if (1) all of the sodium in the fresh coal fed to the kiln (Na_2O is ~1% of the 7.4% ash in the coal or ~0.07% of the coal) is retained in the coal, and (2) if all of the NaOH used for leaching is washed from the coal, an MCL product coal with a sodium content of ~0.07 wt% would be expected.

Therefore, acid washing at a pH of 1 to 2 (following water washing) of the MCL coal removed a significant fraction of the sodium originally in the coal fed to the kiln. Water washing alone increased the sodium in the MCL product coal by a factor of ~4 above the level expected if only the sodium in the feed coal remained in the product coal. The extra sodium in the product coal is most likely ionically bound sodium that cannot be removed by water washing alone. It does not take much residual sodium hydroxide content on the coal to elevate the sodium content of the coal to the levels seen when water washing alone is employed. In fact, 99.9% of the NaOH fed to the kiln with the coal was removed from the product coal in the MCL water washing equipment (plus the two additional laboratory washes).

The modifications that were made to the wash train after Test Run No. 11, which were described above, worked well during the wash train test. The slurry pumps worked properly and at no time during this wash train test was a centrifuge overwhelmed with slurry. The modified centrate tank system worked well during this test preventing centrate from backing up into the cake. The level control bubblers in the slurry tanks had also been modified to prevent plugging. The bubbler modifications did not perform as well as expected and the bubblers continued to cause problems with plugging which resulted in occasional erroneous level readings in the slurry tanks.

5. SCALEUP COAL/WATER SEPARATION TESTS IN A 9-INCH CENTRIFUGE

In July 1992, a series of MCL coal/water separation tests were performed in a 9-inch solid bowl centrifuge. The objective of these tests was to generate scaleup data on centrifuge performance with MCL coal in a machine that is more representative (L/D ratio of 3) of commercial equipment than the 6-inch solid bowl centrifuges (L/D ratio of 2) used to date in the MCL integrated test facility. The tests conducted to date with the 6-inch machines have not yielded scaleup capacity data for the centrifuges due to the limited pumping range of the centrifuge feed and centrate pumps in the MCL wash train. The tests with the 9-inch centrifuge were conducted at various flow rates over a range of feed water to coal ratios including an operating point (5:1 water:coal) close to that expected in a full scale MCL plant. The tests were conducted at coal feed rates up to 400 lbs/hr of coal. This represents a twenty-fold scaleup factor over the MCL integrated test facility (~20 lbs/hr coal feed).

A sketch of the test equipment configuration utilized is shown in Figure 5-1. Batches of coal slurry of the desired water to coal ratios were prepared for the centrifuge tests in a ~300 gallon vertical, cone bottomed stirred tank. A metered amount of water was first added to the tank. The agitator and tank circulation pump were then turned on. A specified amount of MCL product coal (from available plant inventory) was then manually added to the tank. When the coal was well dispersed in the water, flow to the centrifuge (a 9-inch Bird Machinery solid bowl centrifuge with on-line pool depth adjustment) commenced. The centrifuge flow control valve (which had been calibrated with water) was opened to the degree required for the desired centrifuge flow (2.5 and 5 GPM). Centrifuge cake and centrate samples were collected in separate 55-gallon drums, each mounted on scales. Samples of the cake were taken for analysis of moisture content. Samples of the centrate were taken for analysis of fines content.

Table 5-1 summarizes the centrifuge test results. At centrifuge feed rates of 2.5 and 5 GPM and water to coal ratios of 10:1 and 5:1, coal feed rates ranged from 100 to 400 lbs/hr (versus ~20 lbs/hr for the MCL integrated

Figure 5-1. Flow Schematic for MCL Tests in 9-Inch Centrifuge

TABLE 5-1. MCL COAL/WATER 9-INCH SOLID BOWL
CENTRIFUGE SEPARATOR PERFORMANCE RESULTS

NOMINAL FEED WATER:COAL RATIO	10:1	10:1	5:1	5:1
TOTAL GPM FEED (COAL PLUS WATER)	2.5	5.0	2.5	5.0
COAL FEED, LBS/HR	100	200	200	400
% MOISTURE IN CENTRIFUGE CAKE	40%	43%	44%	44%
% SOLIDS IN CENTRATE	<0.1%	1%	<0.1%	2%

test facility). A cake product with a moisture content of 40 to 44% was obtained. The solids carryover to the centrate in the 9-inch machine was <0.1% at a centrifuge feed rate of 2.5 GPM. Solids carryover to the centrate increased to 1% and 2% at a centrifuge feed rate of 5 GPM and feed water:coal ratios of 10:1 and 5:1, respectively.

END

**DATE
FILMED**

8 / 13 / 93