**U.S. Department of Energy
Washington, DC 20585**

**Environment, Safety and Health
Office of Environmental Audit**

**Environmental Survey
Preliminary Report**

**Nevada Test Site
Mercury, Nevada**

April 1988

MASTER

td

PREFACE
TO
THE DEPARTMENT OF ENERGY
NEVADA TEST SITE
ENVIRONMENTAL SURVEY PRELIMINARY REPORT

This report contains the preliminary findings based on the first phase of the Environmental Survey at the Department of Energy (DOE) Nevada Test Site (NTS), located at Mercury, Nevada. The Survey is being conducted by DOE's Office of Environment, Safety and Health.

The NTS Survey is a portion of the larger, comprehensive DOE Environmental Survey encompassing all major operating facilities of DOE. The DOE Environmental Survey is one of a series of initiatives announced on September 18, 1985, by Secretary of Energy, John S. Herrington, to strengthen the environmental, safety, and health programs and activities within DOE. The purpose of the Environmental Survey is to identify, via a "no-fault" baseline Survey of all the Department's major operating facilities, environmental problems and areas of environmental risk. The identified problem areas will be prioritized on a Department-wide basis in order of importance in 1989.

The findings in this report are subject to modification based on the results from the Sampling and Analysis Phase of the Survey. The findings are also subject to modification based on comments from the Nevada Operations Office concerning their technical accuracy. The modified preliminary findings and any other appropriate changes will be incorporated into an Interim Report. The Interim Report will serve as the site-specific source of environmental information generated by the Survey, and ultimately as the primary source of information for the DOE-wide prioritization of environmental problems in the Survey Summary Report.

April 1988
Washington, D.C.

PRELIMINARY

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
EXECUTIVE SUMMARY	ES-1
1.0 INTRODUCTION	1-1
2.0 GENERAL SITE INFORMATION	2-1
2.1 Site Setting	2-1
2.2 Overview of Major Site Operations	2-9
2.2.1 Nevada Test Site	2-9
2.2.2 Las Vegas Operations (LVO)	2-14
2.2.3 EG&G/EM Aerial Measurements	2-14
2.3 State/Federal Concerns	2-15
3.0 MEDIA-SPECIFIC SURVEY FINDINGS	3-1
3.1 Air	3-1
3.1.1 Background Environmental Information	3-1
3.1.2 General Description of Pollution Sources/Controls	3-7
3.1.2.1 Radioactive Air Contaminants	3-9
3.1.2.1.1 Downhole Shots	3-9
3.1.2.1.2 Tunnel Shots	3-12
3.1.2.1.3 Resuspension of Contaminated Surface Soils	3-15
3.1.2.2 Nonradioactive Air Contaminants at the NTS	3-15
3.1.2.2.1 Fuel-Burning Sources and Controls	3-15
3.1.2.2.2 Process Sources and Controls	3-20
3.1.2.2.3 Fugitive Dust Sources and Controls	3-25
3.1.3 Environmental Monitoring Program	3-26
3.1.3.1 On-Site Radiological Monitoring	3-26
3.1.3.2 Off-Site Environmental Monitoring Program	3-28
3.1.3.3 Pre-Shot Meteorological Monitoring and Release	3-32
3.1.4 Pathway Prediction	3-32
3.1.4 Findings and Observations	3-33
3.1.4.1 Category I	3-33
3.1.4.2 Category II	3-33
3.1.4.3 Category III	3-33
3.1.4.4 Category IV	3-33
3.2 Soils	3-37
3.2.1 Background Environmental Information	3-37
3.2.2 General Description of Pollution Sources/Controls	3-41
3.2.2.1 Surface Soil Contamination	3-41
3.2.2.2 Subsurface Soil Contamination from Underground Nuclear Testing	3-45
3.2.2.3 Near-Surface Soil Contamination from Waste Disposal Practices	3-46
3.2.3 Environmental Monitoring Program	3-51
3.2.3.1 Soil Contamination Characterization Projects	3-51
3.2.3.2 Routine Environmental Monitoring	3-58
3.2.3.3 Soil Sampling at Inactive Leachfields	3-60
3.2.3.4 Inactive Contaminated Waste Dumps	3-64
3.2.4 Findings and Observations	3-65
3.2.4.1 Category I	3-65
3.2.4.2 Category II	3-65
3.2.4.3 Category III	3-65

TABLE OF CONTENTS (CONTINUED)

SECTION	PAGE
3.2.4.4	3-68
3.3	3-69
3.3.1	3-69
3.3.2	3-78
3.3.2.1	3-78
3.3.2.2	3-80
3.3.2.3	3-81
3.3.2.4	3-82
3.3.2.5	3-85
3.3.3	3-85
3.3.3.1	3-94
3.3.3.2	3-94
3.3.3.3	3-97
3.3.3.4	3-100
3.3.3.5	3-100
3.3.4	3-106
3.3.4.1	3-106
3.3.4.2	3-106
3.3.4.3	3-111
3.3.4.4	3-113
3.4	3-116
3.4.1	3-116
3.4.1.1	3-116
3.4.1.2	3-119
3.4.1.3	3-127
3.4.2	3-129
3.4.2.1	3-129
3.4.2.2	3-139
3.4.2.3	3-144
3.4.2.4	3-146
3.4.2.5	3-148
3.4.2.6	3-149
3.4.2.7	3-152
3.4.3	3-154
3.4.4	3-172
3.4.4.1	3-172
3.4.4.2	3-172
3.4.4.3	3-172
3.4.4.4	3-176
4.0	4-1
4.1	4-1
4.1.1	4-1
4.1.2	4-4

TABLE OF CONTENTS (CONTINUED)

<u>SECTION</u>		<u>PAGE</u>
4.1.2.1	Nevada Test Site	4-4
4.1.2.1.1	Hazardous Waste	4-4
4.1.2.1.2	Radioactive Waste	4-12
4.1.2.1.3	Mixed Waste	4-34
4.1.2.1.4	Nonhazardous Waste	4-38
4.1.2.2	North Las Vegas Facilities	4-42
4.1.2.2.1	Hazardous Waste	4-42
4.1.2.2.2	Radioactive Waste	4-45
4.1.2.2.3	Mixed Waste	4-45
4.1.2.2.4	Nonhazardous Waste	4-46
4.1.3	Findings and Observations	4-46
4.1.3.1	Category I	4-46
4.1.3.2	Category II	4-46
4.1.3.3	Category III	4-53
4.1.3.4	Category IV	4-55
4.2	Toxic and Chemical Materials	4-56
4.2.1	General Description of Pollutant Sources/Controls	4-56
4.2.1.1	Toxics Management	4-56
4.2.1.2	Tank Farm Facilities	4-58
4.2.1.2.1	Underground Storage Tanks	4-58
4.2.1.2.2	Above Ground Storage Tanks	4-66
4.2.1.2.3	Liquefied Gaseous Fuels (LGF) Spill Test Facility	4-68
4.2.1.3	Polychlorinated Biphenyls (PCBs)	4-70
4.2.1.4	Pesticides	4-76
4.2.1.5	Asbestos	4-79
4.2.1.6	Chlorofluoroalkanes	4-81
4.2.2	Findings and Observations	4-81
4.2.2.1	Category I	4-81
4.2.2.2	Category II	4-81
4.2.2.3	Category III	4-85
4.2.2.4	Category IV	4-88
4.3	Radiation	4-91
4.3.1	Background Environmental Information	4-91
4.3.2	General Description of Data Handling Procedures	4-93
4.3.3	Environmental Monitoring Program	4-98
4.3.3.1	External Gamma Radiation Monitoring	4-98
4.3.3.2	Dose Assessments	4-101
4.3.4	Findings and Observations	4-107
4.3.4.1	Category I	4-107
4.3.4.2	Category II	4-107
4.3.4.3	Category III	4-107
4.3.4.4	Category IV	4-110
4.4	Quality Assurance	4-112
4.4.1	General Description of Pollution Sources/Controls	4-112
4.4.1.1	On-site Radiological Monitoring Program	4-112
4.4.1.1.1	Media Monitoring	4-112
4.4.1.1.2	Radiation Level Monitoring	4-115
4.4.1.2	Off-site Radiological Monitoring	4-115

TABLE OF CONTENTS (CONTINUED)

<u>SECTION</u>	<u>PAGE</u>
4.4.1.3 On-Site Nonradiological Monitoring Program	4-118
4.4.2 Findings and Observations	4-119
4.4.2.1 Category I	4-119
4.4.2.2 Category II	4-119
4.4.2.3 Category III	4-120
4.4.2.4 Category IV	4-120
4.5 Inactive Waste Sites and Releases	4-121
4.5.1 Background Information	4-121
4.5.2 General Description of Pollution Sources/Controls	4-123
4.5.2.1 Underground Test Shots/Tunnel Tests	4-123
4.5.2.2 Past Atmospheric Tests	4-124
4.5.2.3 Inactive Contaminated Waste Dumps	4-124
4.5.2.4 Inactive Radioactive Waste Consolidation Sites	4-130
4.5.2.5 Inactive Contaminated Muck Piles	4-131
4.5.2.6 Inactive Storage Tanks	4-132
4.5.2.7 Inactive Leachfields	4-132
4.5.2.8 Nuclear Rocket Development Station	4-149
4.5.2.9 Jet Fuel Release at the Desert Rock Airstrip	4-156
4.5.2.10 Inactive Horn Silver Mine	4-157
4.5.2.11 BJY Pad	4-160
4.5.2.12 Catchbasin Near Control Point 2	4-160
4.5.2.13 Experimental Farm Facility	4-162
4.5.2.14 Inactive Subdock Complex	4-166
4.5.2.15 LANL Core Handling Facility	4-167
4.5.2.16 U9y Storage Tank and Adjacent Area	4-169
4.5.2.17 Tory Reactor	4-170
4.5.2.18 Super Kukla Reactor Facility	4-170
4.5.2.19 Other Inactive Sites where Hazardous Substances are Likely to be Found	4-171
4.5.3 Findings and Observations	4-173
4.5.3.1 Category I	4-173
4.5.3.2 Category II	4-173
4.5.3.3 Category III	4-173
4.5.3.4 Category IV	4-181
REFERENCES	R-1
APPENDICES	
A SURVEY PARTICIPANTS	A-1
B SURVEY PLAN	B-1
C SITE-SPECIFIC SURVEY ACTIVITIES	C-1
D CHEMICAL SYMBOLS, ABBREVIATIONS, AND ACRONYMS	D-1

TABLES

<u>NUMBER</u>		<u>PAGE</u>
3-1	Ambient Air Quality Standards for Nonradioactive Pollutants	3-3
3-2	EPA Designation of Air Quality Status	3-5
3-3	Airborne Background Activity Levels for Selected Cities in Southwestern United States	3-8
3-4	Inventory of Fuel-Oil-Fired Steam and Hot-Water Boilers	3-16
3-5	Plutonium Contamination at NAEG Study Sites	3-52
3-6	Summary of Aerial Survey Report Topics	3-56
3-7	Summary of RIDP Report Contents	3-59
3-8	USGS Data for Year 1984 - Colorado River Below Hoover Dam	3-71
3-9	USGS Data for Year 1984 - Las Vegas Wash Near Boulder City, Nevada	3-73
3-10	North Las Vegas Waste Water Sources	3-86
3-11	Sanitary Sewage Lagoons	3-95
3-12	Average of Open Reservoir Data for Gross Beta Activity	3-98
3-13	1985 Annual Contaminated Pond Average Radionuclide Concentrations ($\mu\text{Ci/ml}$)	3-99
3-14	Mixed Waste Study Analyses	3-101
3-15	First Round Baseline Monitoring Data (mg/l)	3-103
3-16	Second Round Baseline Monitoring Data (mg/l)	3-104
3-17	Printed Circuit Plating Shop 20-Day Baseline Monitoring Results (mg/l)	3-105
3-18	Nevada Test Site Septic tanks	3-112
3-19	1980-1984 Water Supply Sources and Amounts in Areas of Clark and Nye Counties Near the Nevada Test Site	3-128
3-20	Major Ions and Groundwater Quality Parameters for Water Supply Wells	3-159
3-21	Trace Metals and Miscellaneous Parameters for Water Supply Wells	3-164
4-1	Hazardous Waste Generation During 1986	4-5
4-2	Radioactive Waste Definitions	4-14
4-3	Active Radioactive Waste Management Facilities and Sites	4-16
4-4	Discharges to Active Area 12 Tunnel Ponds	4-20
4-5	Summary of Defense Waste Acceptance Criteria	4-32
4-6	Estimated Annual Quantity of Mixed Waste to be Received at the Area 5 RWMS	4-39
4-7	Hazardous Waste Generated During 1986 North Las Vegas, Nevada Facilities	4-44
4-8	Underground Storage Tanks Used to Store Waste and Non-Waste Toxic and Chemical Materials	4-59
4-9	Underground Storage Tanks with a Capacity of Greater than 1,000 Gallons Used to Store Heating Oil	4-62
4-10	Underground Storage Tanks Identified During Environmental Survey	4-64
4-11	Above Ground Storage Tanks	4-67
4-12	Materials Approved for Testing at the Spill Test Facility, Frenchman Flat	4-69
4-13	PCB and PCB-Contaminated Equipment or Fluids in Service, Stored for Reuse or Disposed in CY1985	4-71
4-14	PCB and PCB-Contaminated Equipment in -Service or Stored for Reuse at the Time of the Environmental Survey	4-72
4-15	Pesticides Approved for Use at NTS in FY 1987	4-77
4-16	Pesticide Usage During 1986	4-80
4-17	Chlorofluoroalkane Usage at NTS in FY 1986	4-82

TABLES (CONTINUED)

<u>NUMBER</u>		<u>PAGE</u>
4-18	Average U.S. Annual Effective Dose Equivalent to Humans from Natural Background Radiation	4-92
4-19	Reported Radionuclide Releases from the NTS 1982-1986, in Curies	4-96
4-20	Radonucleide Concentrations Used for the Perimeter Dose Assessment	4-104
4-21	Perimeter Radiation Doses for 1985	4-106
4-22	Off-Site Radiation Dose Assessments from Radioactivity of Recent NTS Origin	4-108
4-23	Summary of Quality Control Analyses for NTS On-Site Radiological Monitoring Program	4-114
4-24	Contents of EPA/EMSL Quality Assurance Project Plan	4-116
4-25	Inactive Contaminated Waste Dumps (CWD)	4-125
4-26	Environmental Data for Inactive Contaminated Waste Dumps	4-126
4-27	Inactive Contaminated Muck Piles	4-133
4-28	Inactive Leachfields	4-135
4-29	Radioactivity Data for Six Inactive Leachfields	4-136
4-30	Hazardous Chemical Data for Three Inactive Leachfields	4-146
4-31	Other Inactive Sites Where Hazardous Substances are Likely to be Found	4-172

FIGURES

<u>NUMBER</u>		<u>PAGE</u>
2-1	Location Map of the Nevada Test Site	2-2
2-2	Population of Arizona, California, Nevada, and Utah Counties Near the Nevada Test Site (1985)	2-3
2-3	Communities Within 80 Kilometers of CP-1	2-4
2-4	Topographic Features at the Nevada Test Site	2-6
2-5	Groundwater Flow Systems Around the Nevada Test Site	2-8
2-6	Layout of Test Areas	2-10
3-1	Schematic of Tunnel Line-Of-Sight Pipe Configuration	3-13
3-2	Cement and Additive Storage and Blending Plant	3-23
3-3	Locations of Off-Site Air Surveillance Network Stations	3-29
3-4	Locations of Off-Site Noble Gas and Tritium Surveillance Network Sampling Stations	3-31
3-5	Predicted Trajectory and External Gamma Exposure	3-34
3-6	Areas of Elevated Radiation at the Nevada Test Site	3-57
3-7	Surface Water Near Nevada Test Site	3-70
3-8	Natural Surface Water at Nevada Test Site	3-74
3-9	Boundaries of Basins and Directions of Surface Drainage	3-75

FIGURES (CONTINUED)

<u>NUMBER</u>		<u>PAGE</u>
3-10	Water Systems	3-83
3-11	Regional Water Table Map	3-121
3-12	Generalized Groundwater Flow Beneath Frenchman Flat and Yucca Flat	3-124
3-13	Geological Cross-Section at E-Tunnel, Rainier Mesa	3-126
3-14	Water Supply Wells at the Nevada Test Site	3-130
3-15	Nuclear Detonations Fired Below the Water Table	3-131
3-16	Locations of Experimental Sites for the Radionuclide Migration Program	3-135
3-17	Contaminated Drill Holes and Probable Sources	3-141
3-18	LTHMP Sampling Locations Near the NTS	3-156
3-19	LTHMP Sampling Locations on the NTS	3-157
4-1	Area 6 Waste Management Facilities	4-7
4-2	Area 23 Active Waste Management Sites	4-9
4-3	Active Radioactive and Mixed Waste Management Sites	4-18
4-4	Area 3 Radioactive Waste Management Site	4-23
4-5	Existing Facilities at Area 5 Radioactive Waste Management Site	4-26
4-6	Area 5 Radioactive Waste Management Site	4-27
4-7	Active Nonhazardous/Nonradioactive Waste Management Sites	4-40
4-8	Location of Off-Site TLD Monitoring Stations	4-100
4-9	Dose Assessment Pathways	4-102
4-10	Location of Leachfield for Industrial Hygiene Lab (Building 155)	4-150
4-11	NRDS Installation	4-152
4-12	Desert Rock Airstrip	4-158
4-13	Location of Horn Silver Mine	4-159
4-14	Locations of U9y Crater, BJY Pad, and Former Subdock Complex	4-161
4-15	Location of Catch Basin Near Control Point 2 Building	4-163
4-16	Experimental Farm Facility	4-165
4-17	CANL Core Handling Facility	4-168

EXECUTIVE SUMMARY

Introduction

This report presents the preliminary findings from the first phase of the Environmental Survey of the United States Department of Energy (DOE) Nevada Test Site (NTS), conducted June 22 through July 10, 1987.

The Survey is being conducted by a multidisciplinary team of environmental specialists, led and managed by the Office of Environment, Safety and Health's Office of Environmental Audit. Individual team members are outside experts being supplied by a private contractor. The objective of the Survey is to identify environmental problems and areas of environmental risk associated with the NTS. The Survey covers all environmental media and all areas of environmental regulation. It is being performed in accordance with the DOE Environmental Survey Manual. This phase of the Survey involves the review of existing site environmental data, observations of the operations and activities performed at the NTS, and interviews with site personnel.

The Survey team developed a Sampling and Analysis Plan to assist in further assessing certain environmental problems identified during its on-site activities. The Sampling and Analysis Plan is being executed by the Battelle Columbus Division under contract with DOE. When completed, the results will be incorporated into the NTS Environmental Survey Interim Report. The Interim Report will reflect the final determinations of the NTS Survey.

Site Description

The NTS occupies 1,350 square miles (3,500 square kilometers) of restricted access, Federally owned land located in southern Nevada. The NTS is bordered on its west, north, and east sides by 4,127 square miles (10,700 square kilometers) of land comprising the Nellis Air Force Range, another Federally owned, restricted-access area. The southernmost point of the NTS is situated approximately 65 miles (100 kilometers) northwest of Las Vegas, Nevada. The NTS is operated by the Reynolds Electrical & Engineering Company Inc. (REECo) under contract to DOE.

The NTS is currently used to conduct all United States nuclear weapons tests. These tests are conducted underground for containment of the detonation products. The NTS was chosen in 1950 to provide a continental proving ground for nuclear weapons testing to reduce the expense and logistical problems of testing in the Pacific. The site was initially operated for a few months each

year by the Test Division of the Albuquerque Operations Office. In 1962, the Nevada Operations Office (NVO) was created and assumed responsibility for operations and programs at the NTS. Nuclear weapons testing at the NTS then became a year-round effort. The NTS is also used for the storage and disposal of low-level and transuranic wastes from DOE's nuclear weapons laboratories and production facilities. This mission began in the 1960s, and expansion plans include the continued disposal of low-level and transuranic wastes and future disposal of mixed (radioactive and hazardous) wastes.

The Survey team met with representatives of the state regulatory agencies on May 7, 1987. The meeting was primarily a question and answer session; no major issues concerning the NTS were raised. Although representatives from the Environmental Protection Agency (EPA), Region IX were unable to attend the meeting, the results of their recent Resource Conservation and Recovery Act (RCRA) inspection of the hazardous waste trenches and the hazardous material and waste storage and holding facility in Area 23 of the NTS were provided through the Operations Office to the Survey team.

Summary of Findings

The following are major preliminary findings of the Environmental Survey of the NTS:

- Surface soils within the NTS and select areas of Nellis Air Force Range are contaminated with radioactive materials in excess of the EPA and DOE interim standards for unrestricted use, and are potentially contaminated with beryllium from past atmospheric nuclear detonations, safety tests, and other experiments. Contaminated areas have been identified and posted with warning signs, and access to these areas is restricted. However, there is a potential for the spread of this contamination through saltation, surface creep, and air resuspension, particularly if the desert pavement is disturbed.
- Underground nuclear detonations conducted near or below the water table have resulted in the radioactive contamination of the groundwater, principally with tritium, within and surrounding the test chimneys and cavities. Creation of fractures from the detonation and the combination of natural and event-related hydraulic forces could result in more widespread groundwater contamination. However, the potential for off-site migration is low because of slow groundwater flow rates and the decay of radionuclides before the site boundaries are reached.

- Wastewaters are being discharged at several areas of NTS without the required State discharge permits. The unpermitted discharges identified during the Survey fall into four distinct categories: discharges to land surfaces, including drainage ditches; discharges to injection wells; discharges to sumps, lagoons, and ponds; and discharges to leachfields.
- Potentially hazardous and/or mixed wastes are being discharged to several waste management facilities (e.g., ponds, sumps, craters, post-shot holes, wells, leachfields) that do not have RCRA permits or RCRA interim status (i.e., have not been included in RCRA Part A permit applications for NTS). The waste streams discharged to these facilities contain solvents, acids, caustics, and metals. Additionally, solid waste landfills and trenches are receiving potentially hazardous wastes streams that have not been analyzed for RCRA-listed substances or hazardous characteristics.
- Over 50 inactive waste disposal, spill, and release sites (other than underground test sites) have been identified as known or possible sources of contamination to soils.

Overall Conclusions

The Survey found no environmental problems at the NTS that represent an immediate threat to human life. The preliminary findings identified at NTS by the Survey do indicate that the site is affected by a number of environmental problems and regulatory issues. The most pressing environmental concerns facing the site, at present, appear to be radionuclide contamination of surface soils from past atmospheric tests; radionuclide contamination of groundwater on-site where underground tests near and below the water table are conducted; unpermitted discharges of wastewaters; and disposal of wastes at unpermitted facilities. NTS has several contaminated soil and groundwater investigations under way and is actively gathering the necessary data to apply for discharge and disposal permits.

The environmental problems described in this report vary in terms of their magnitude and risk. Although the Survey-related sampling and analysis being performed at the NTS will assist in further identifying environmental problems at the site, a complete understanding of the significance of some of the environmental problems identified requires a level of study and characterization that is beyond the scope of the Survey. Actions currently under way or planned at the site, particularly the Radionuclide Migration Program, the Radionuclide Inventory and Distribution Program, and the Basic Environmental Compliance and Monitoring Program, will contribute toward meeting this requirement.

Transmittal and Follow-Up of Findings

The preliminary findings of the Environmental Survey of the NTS were shared with the Nevada Operations Office and the site contractor at the Survey closeout briefing held July 10, 1987. By August 1987, the Nevada Operations Office had developed a draft action plan to address the Survey preliminary findings. The Operations Office presented this plan to the State of Nevada Division of Environmental Protection and the EPA Region IX Office at meetings on August 14 and 21, 1987, respectively. A final action plan addressing all the Survey findings cited herein will be prepared by the Nevada Operations Office within 45 days of receiving this Preliminary Report. Problems that involve extended studies and multi-year budget commitments will be the subject of the Environmental Survey Summary Report and the DOE-wide prioritization.

Within the Office of the Assistant Secretary for Environment, Safety and Health, the Office of Environmental Guidance and Compliance has immediate responsibility for monitoring environmental compliance and the status of the NTS Survey Findings. The Office of Environmental Audit will continue to assess the environmental problems through the program of systematic environmental audits that will be initiated toward the conclusion of the DOE Environmental Survey in 1989.

1.0 INTRODUCTION

The purpose of this report is to present the preliminary findings made during the Environmental Survey, June 22 through July 10, 1987, of the Department of Energy's (DOE) Nevada Test Site (NTS) at Mercury, Nevada. The contents of the preliminary report are subject to revisions, in the Interim Report, based on the Nevada Operations Office (NVO) review and comments on the technical accuracy, the results of the sampling and analysis program, and other information that may come to the Survey team's attention prior to issuance of the Interim Report. NTS is operated for DOE by Reynolds Electrical & Engineering Company, Inc.

The NTS Survey is part of the larger, DOE-wide, Environmental Survey effort announced by Secretary John S. Herrington on September 18, 1985. The purpose of this effort is to identify, via "no fault" baseline Surveys, existing environmental problems and areas of environmental risk at DOE facilities and to rank them on a DOE-wide basis. This ranking will enable DOE to more effectively establish priorities for addressing environmental problems and to allocate the resources necessary to correct these problems. Because the Survey is "no fault" and is not an "audit," it is not designed to identify specific, isolated incidents of noncompliance or to analyze environmental management practices. Such incidents and/or management practices will, however, be used in the Survey as a means of identifying existing and potential environmental problems.

The NTS Environmental Survey was conducted by a multidisciplinary team of technical specialists headed and managed by a Team Leader and Assistant Team Leader from DOE's Office of Environmental Audit. A complete list of the NTS Survey participants and their affiliations is provided in Appendix A.

The Survey team focused on all environmental media, using Federal, state, and local environmental statutes and regulations, accepted industry practices, and professional judgment to make the preliminary findings included in this report. The team carried out its activities in accordance with the guidance and protocols in the Environmental Survey Manual (August 1987). Substantial use of existing information and of interviews with knowledgeable field office and site-contractor personnel accounted for a large part of the on-site effort. The Survey Plan is presented in Appendix B, and a summary of the site-specific Survey activities is presented in Appendix C. Appendix D is a list defining symbols, abbreviations, and acronyms used in this report.

The preliminary Survey findings, in the form of existing and potential environmental problems, are presented in Sections 3.0 and 4.0. Section 3.0 includes those findings that pertain to a specific environmental medium (e.g., air or soil), whereas Section 4.0 includes those that are non-media

specific (e.g., waste management, radiation, and quality assurance). Because the findings are highly varied in terms of magnitude, risk, and characterization, and consequently require different levels of management attention and response, they are further subdivided into four categories within Sections 3.0 and 4.0.

The criteria for placing a finding into one of the four categories are as follows:

- Category I includes only those findings which, based upon the information available to the Team Leader, involve immediate threat to human life. Findings of this type shall be immediately conveyed to the responsible environmental safety and health personnel at the scene or in control of the facility or location in question for action. Category I findings are those environmental problems where the potential risk is highest, the confidence in the finding, based on the information available, is the strongest, and the appropriate response to the finding is the most restrictive in terms of alternatives.
- Category II findings encompass one or more of the following situations:
 - Multiple or continuing exceedances, past or present, of a health-based environmental standard where there is immediate potential for human population exposure, or a one-time exceedance where residual impacts pose an immediate potential for human population exposure.
 - Evidence that a health-based environmental standard may be exceeded, as discussed in the preceding situation, within the time-frame of the DOE-wide Survey.
 - Evidence that the likelihood is high for an unplanned release due to, for example, the condition or design of pollution abatement or monitoring equipment or other environmental management practices.
 - Noncompliance with significant regulatory procedures, (i.e., those substantive technical regulatory procedures designed to directly or indirectly minimize or prevent risks, such as inadequate monitoring or failure to obtain required permits).

Category II findings include those environmental problems where the risk is high but where the definition of risk is broader than in Category I. The information available to the Team Leader is adequate to identify the problem but may be insufficient to fully characterize it. Finally, in this category, most discretion is available to the Operations

Offices and Program Offices as to the appropriate response; however, the need for that response is such that management should not wait for the completion of the entire DOE-wide Survey to respond. Unlike Category I findings, a sufficient, near-term response by the Operations Office may include further characterization prior to any action taken to rectify the situation.

- Category III findings encompass one or both of the following criteria:
 - The existence of pollutants or hazardous materials in the air, water, groundwater, or soil resulting from DOE operations that pose or may pose a hazard to human health or the environment.
 - The existence of conditions at a DOE facility that pose or may pose a hazard to human health or the environment.

Category III findings are those environmental problems for which the broadest definition of risk is used. As in Category II, the information available to the Team Leader may not be sufficient to fully characterize the problem. Under this strategy, the range of alternatives available for response, and the corresponding timeframes for response, are the greatest. Environmental problems included within this category will typically require lengthy investigation and remediation phases, and multiyear budget commitments. These problems will be included in the DOE-wide prioritization effort to ensure that DOE's resources are used most effectively.

In general, the levels of pollutants or materials that constitute a hazard or potential for hazard are those that exceed some Federal, state, or local regulations for release of, contamination by, or exposure to such pollutants or materials. However, in some cases, the Survey may determine that the presence of some nonregulated material is in a concentration that presents a concern for local populations or the environment that is sufficient to be included as an environmental problem. Likewise, the presence of regulated materials in concentrations that, even below those established by regulatory authorities, nevertheless present a potential for hazard or concern, may be classified as an environmental problem. In general, however, conditions that meet regulatory or other requirements, where such exist, should not present a potential hazard and will not be identified as environmental problems.

Conditions that pose or may pose a hazard are generally those which are violations of regulations or requirements (e.g., improper storage of hazardous chemicals in unsafe tanks). Such conditions present a potential hazardous threat to human health and the environment and should be identified as an environmental problem. Additionally, potentially hazardous conditions are those where the likelihood of the occurrence of release is high. The definition of the term environmental problem is broad and flexible to allow for the wide difference among the DOE sites and operations. Therefore, a good deal of professional judgment must be applied to the identification of environmental problems.

- Category IV findings include instances of administrative noncompliance and management practices that are indirectly related to environmental risk, but are not appropriate for inclusion in Categories I-III. Such findings can be based upon any level of information available to the Team Leader, including direct observations by the team members. Findings in this category are generally expected to lend themselves to relatively simple, straightforward resolution without further evaluation or analysis. These findings, although not part of the DOE-wide prioritization effort, will be passed along to the Operations Office and appropriate Program Office for their action.

Based on the professional judgment of the Team Leader, the findings within categories are arranged in order of relative significance. Comparing the relative significance of one finding to another, either between categories within a section or within categories between sections, is neither appropriate nor valid. The categorization and listing of findings in order of significance within this report is only the first step in a multi-step iterative process to prioritize DOE's problems.

The subsequent phase of the NTS Survey involved sampling and analysis (S&A). Battelle Columbus Division provided the S&A team for NTS Survey. Prior to sampling, an S&A plan was prepared in accordance with the protocols in the Survey Manual. The S&A plan was designed to fill existing data gaps or weaknesses. The results generated by the S&A effort will be used to assist the Survey team in further defining the existence and extent of potential environmental problems identified during the Survey.

An Interim Report will be prepared 6 to 8 weeks after the completion of the S&A effort. The Interim Report will incorporate the results of the S&A effort as well as any changes or comments resulting from the review of the Preliminary Report. Based on the S&A results, the preliminary findings and observations made during the on-site Survey may be modified, deleted, or moved within or between categories. The Interim Report will serve both as the site-specific repository for information

generated by the Survey, and ultimately as the site-specific source of information for the DOE-wide prioritization of environmental problems.

It is clear that certain of the findings and observations contained in this report, especially those in Category II, can and should be addressed in the near-term (i.e., prior to the DOE-wide prioritization effort). It is also clear that the findings and observations in this report vary greatly in terms of magnitude, risk, and characterization. Consequently, the priority, magnitude, and timeliness of near-term responses will require careful planning to ensure appropriate and effective application. The information in this Preliminary Report, albeit provisional, will assist the NVO in the planning of these near-term responses.

The NVO submitted a draft action plan dated January 6, 1988, to address the preliminary findings presented at the conclusion of the on-site Survey activities and summarized in the NTS Survey Status Report prepared for the Assistant Secretary for Environment, Safety and Health. The draft action plan for the NTS Survey has been reviewed by the Office of Environmental Guidance and Compliance (OEG), which has immediate responsibility for monitoring the status and overseeing the adequacy of corrective actions taken by the Operations Office in response to the Survey findings.

As required in the December 2, 1987, memorandum from the Assistant Secretary for Environment, Safety and Health to the Operations Office Managers entitled, Follow-up of Environmental Survey Findings, the Nevada Operations Office will prepare and submit a final action plan to the Deputy Assistant Secretary for Environment within 45 days of receiving this Preliminary Report. The final action plan for the NTS Survey will address all of the preliminary findings cited herein, and will incorporate OEG's comments on the draft action plan.

2.0 GENERAL SITE INFORMATION

2.1 Site Setting

Location

The Nevada Test Site (NTS) is located in southern Nevada, with its southernmost point about 100 kilometers (65 miles) northwest of Las Vegas (Figure 2-1). The site consists of 3,500 square kilometers (1,350 square miles) of restricted access, Federally owned land, which ranges from 46 to 56 kilometers (28 to 35 miles) in width (east-west) and from 64 to 88 kilometers (40 to 55 miles) in length (north-south).

The NTS is bordered on its west, north, and east sides by 10,700 square kilometers (4,130 square miles) of land comprising the Nellis Air Force Base Range Complex, another Federally owned, restricted access area. The southern boundary is conterminous with public access land. The northwestern portion of the Nellis Air Force Base Range Complex includes the Tonopah Test Range, which is a government-owned facility that is operated for the Department of Energy (DOE) by the Sandia National Laboratories primarily for airdrop tests of ballistic shapes. The combined area of the three facilities is 14,200 square kilometers (5,480 square miles), which is one of the largest unpopulated areas in the United States. The NTS was established in this unpopulated desert area for the purpose of conducting nuclear weapons tests.

Population Distribution

Population distribution data, developed from 1980 census figures, for counties surrounding the NTS, are shown in Figure 2-2 (Patzner et al., 1987). The population density within 150 kilometers (93 miles) of the main Control Point (CP-1) at the NTS (excluding Las Vegas and Clark County) is about 0.5 person per square kilometer. For comparison, the 48 contiguous states (1980 census) had a population density of about 29 persons per square kilometer, and the State of Nevada had about 2.8 persons per square kilometer.

The off-site area within 80 kilometers (50 miles) of CP-1 (Figure 2-3), the area in which dose assessments for radionuclide releases are made, is predominantly rural. The population in this area has been estimated at 6,360 (Patzner et al., 1987), with most of that population located in Pahrump, and lesser numbers in Beatty, Indian Springs, Cactus Springs, Lathrop Wells, and Springdale.

FIGURE 2-1

LOCATION MAP OF THE NEVADA TEST SITE
NEVADA TEST SITE - MERCURY, NV

FIGURE 2-2
POPULATION OF ARIZONA, CALIFORNIA, NEVADA, AND UTAH
COUNTIES NEAR THE NEVADA TEST SITE (1985)
NEVADA TEST SITE - MERCURY, NV

FIGURE 2-3

COMMUNITIES WITHIN 80 KILOMETERS OF CP-1
NEVADA TEST SITE - MERCURY, NV

Land Uses

A wide variety of land uses exist within a 300-kilometer (188-mile) radius of the NTS, such as farming, grazing, mining, camping, fishing, and hunting. Terrain features range in elevation from 85 meters (280 feet) below sea level in Death Valley to 4,420 meters (14,500 feet) in the Sierra Nevada Range (Mt. Whitney). Parts of two major agricultural valleys (Owens and San Joaquin) are located to the west in California. To the north and northeast, grazing and alfalfa farming are common. In the Amargosa Valley to the south and Virgin River Valley to the east, small-scale but intensive farming produces a variety of crops. A major portion of the local residents grow or have access to locally grown fruits and vegetables.

Topography

The topography of the NTS consists of north-south trending, rugged mountains separated by broad, flat-floored and gentle-sloped valleys (Figure 2-4). The highest elevations at the NTS are on Pahute Mesa, about 2,205 meters (7,235 feet), and Rainier Mesa, 2,345 meters (7,694 feet) above sea level. The lowest elevations are in Frenchman Flat and Jackass Flats, both at about 910 meters (3,000 feet) above sea level.

There are three principal valleys within the NTS: (1) Yucca Flat, a north-south elongated, closed basin with a dry lake (playa) at the southern end; (2) Frenchman Flat, an oval-shaped, closed basin with a playa at the center, and (3) Jackass Flats, a valley that drains off the NTS at its southwest corner.

Major Water Bodies

Because of its location in a desert area, there are no natural, surface-water bodies on the NTS. The major water body in the vicinity is Lake Mead, which is located about 160 kilometers (100 miles) southeast of the NTS. Lake Mead was formed when Hoover Dam was constructed on the Colorado River in the 1930s. The lake and dam provide water to the Las Vegas area, hydroelectric power to the Los Angeles area, recreational opportunities, and flood control to downstream communities. Water used at the NTS comes from local wells. The Amargosa River is an ephemeral stream that lies along the Nevada-California border.

FIGURE 2-4

TOPOGRAPHIC FEATURES AT THE NEVADA TEST SITE
NEVADA TEST SITE - MERCURY, NV

Hydrology

Two major hydrologic systems exist on the NTS (Figure 2-5). Groundwater in the northwestern part of the NTS, or in the Pahute Mesa area, has been reported to flow at a rate of 2 meters to 180 meters (6.6 feet to 590 feet) per year to the south and southwest toward the Ash Meadows Discharge Area in the Amargosa Desert. It is estimated that the groundwater to the east of the NTS moves from north to south at a rate of not less than 2 meters (6.6 feet) nor greater than 220 meters (720 feet) per year. Carbon-14 analyses of this eastern groundwater indicate that the lower velocity is nearer the true value. At Mercury Valley in the extreme southern part of the NTS, the eastern groundwater flow shifts southwestward toward the Ash Meadows Discharge Area.

The aquifers underlying the NTS vary in depth from about 200 meters (650 feet) beneath the surface of valleys in the southeastern part of the site to more than 500 meters (1,640 feet) beneath the surface of highlands to the north.

Climate

The climate of the NTS and surrounding area is variable, due to variations in elevation and its rugged terrain. Generally, the climate is referred to as continental arid. Throughout the year, there is insufficient water to support the growth of common food crops without irrigation.

The NTS average annual precipitation ranges from about 10 centimeters (4 inches) at the lower elevations to around 30 centimeters (12 inches) on the higher elevations. During the winter months, the plateaus may be snow-covered for a period of several days or weeks. Snow is uncommon on the flats. Temperatures vary considerably with elevation, slope, and local air currents. The average daily temperatures at the lower elevations range between 26°F and 53°F (-3°C and 12°C) in January and from 62°F to 97°F (17°C and 36°C) in July, with extremes of -30°F and 115°F (-34°C and 46°C). Corresponding average daily temperature ranges on the plateaus are 27°F to 37°F (-3°C and 3°C) in January and 61°F to 77°F (16°C and 25°C) in July (ERDA, 1977).

The wind direction, as measured on a 30-meter (100-foot) tower at an observation station about 9 kilometers (5.5 miles) north-northwest of Yucca Lake, is predominantly northerly except during the months of May through August, when winds from the south-southwest predominate. However, because of the prevalent mountain/valley winds in the basins, south to southwest winds predominate during daylight hours of most months. During the winter months, southerly winds have only a slight edge over northerly winds for a few hours during the warmest part of the day.

GROUNDWATER FLOW SYSTEMS AROUND THE
NEVADA TEST SITE
NEVADA TEST SITE - MERCURY, NV

FIGURE 2-5

These wind patterns may be quite different at other locations on the NTS because of local terrain effects and differences in elevation.

2.2 Overview of Major Site Operations

The NTS was chosen in 1950 to provide a continental proving ground for nuclear weapons testing to reduce the expense and logistical problems of testing in the Pacific. The site was initially operated for a few months each year by the Test Division of the Albuquerque Operations Office. In 1962, the Nevada Operations Office (NVO) was created and assumed responsibility for operations and programs at the NTS. Nuclear weapons testing then became a year-round effort. In addition to the activities at the NTS, NVO is responsible for operations at the Las Vegas Support Facility in North Las Vegas. Activities at the NTS and at the Las Vegas Support Facility are described briefly in the next sections.

Reynolds Electrical & Engineering Company Inc. (REECo), a wholly-owned subsidiary of EG&G, Inc., is the prime support contractor at the NTS. User contractors include the Lawrence Livermore National Laboratory, the Los Alamos National Laboratory, the Sandia National Laboratory, and the Department of Defense. The work force at the NTS between 1980 and 1985 has ranged from about 4,000 to about 5,500 people.

2.2.1 Nevada Test Site

The NTS is currently used to conduct all United States nuclear weapons tests. These tests are conducted underground, for containment of the detonation products (NVO, 1986a). Two techniques are used for emplacing nuclear test weapons so that the explosion will be contained. The most common method is to emplace a test device at the bottom of a vertically drilled hole (downhole shots). The other technique is to emplace a test device within a tunnel that has been mined horizontally into Rainier Mesa. The downhole shots are performed primarily to evaluate the performance of the device itself, while the tunnel shots are performed to evaluate the effects of the radiation produced on various materials and apparatus. Tests are limited to a maximum yield of 150 kilotons under terms of the Threshold Test Ban Treaty of 1974.

Downhole Test Shots

Downhole shots are designed and conducted by the Lawrence Livermore National Laboratory and the Los Alamos National Laboratory. Areas used for this testing are shown in Figure 2-6.

FIGURE 2-6

**LAYOUT OF TEST AREAS
NEVADA TEST SITE - MERCURY, NV**

After a suitable site has been selected, generally in Yucca Flat or on Pahute Mesa, an emplacement hole is drilled. Special techniques developed at the NTS permit drilling of holes up to 3.7 meters (12 feet) in diameter to depths as great as 1,525 meters (5,000 feet). A test rack or canister, often about 3 to 3.7 meters (10 to 12 feet) in diameter and up to 61 meters (200 feet) in length, is partially assembled off-site and completed on-site while suspended over the hole. The finished canister containing the test device and the diagnostic equipment is lowered into the hole along with a considerable bundle of electrical cables that connect the firing systems and the diagnostic systems to instrumentation at the surface. After the device and related equipment are lowered into the hole, the hole is carefully backfilled (a procedure referred to as "stemming," which will be discussed further in Section 3.1.2.1) to prevent leakage of cavity gas to the atmosphere.

When all is in readiness, the test device is fired by electrical signals sent from a remote firing location at the Control Point (CP-1) in Area 6 (see Figure 2-6). During and following the test, diagnostic data are transmitted to instrumentation located at the surface in trailers and shelters.

When a nuclear explosive is detonated underground, the energy released immediately produces extremely high temperatures in the device and the surrounding medium. These solid materials are vaporized, and pressures exceeding a million atmospheres are produced. An outgoing shock wave develops that is initially so strong that it vaporizes more of the surrounding medium. As the shock wave expands, its intensity weakens until the medium is melted rather than vaporized. The size of the underground cavity is dependent upon the amount of energy released by the explosion, the depth of burial, and the physical properties of the medium in which it is detonated. At 2 to 4 times the cavity radius, the shock wave is sufficiently weak that its effect is limited to fracturing and heating of the medium. The generally spherical cavity is filled with vaporized material and lined with melted rock. After the cavity forms, the vaporized rock condenses and the molten rock flows toward the bottom, the residual gases cool, the pressure subsides, and collapse of the upper walls of the cavity begins. The cavity collapse is commonly initiated within a few minutes to several hours of its formation. Occasionally, it may be delayed for several days or weeks, but, once started, the collapse proceeds rapidly. This collapse continues upward, producing a vertical, rubble-filled column known as a rubble chimney.

Following most nuclear tests, the chimneying process proceeds upward until it reaches the ground surface. The process terminates by the formation of a conical or bowl-shaped depression from several tens of meters to a few hundred meters in diameter and up to 50 meters (165 feet) deep. These depressions are known as subsidence craters.

After the crater forms and the area is surveyed and deemed safe, a drill rig is moved into place alongside the crater and a "drill-back" operation is started, the objective of which is to sample the reaction products contained within the explosion cavity. After drill-back and sample recovery are completed, the drill hole is sealed.

Tunnel Test Shots

Underground tests conducted in the Rainier Mesa area (see Area 12, Figure 2-6) are weapons-effects tests that are performed in tunnels mined horizontally into the Mesa. In these tests, DOE works with the Defense Nuclear Agency and Sandia National Laboratory in measuring the effects of blast-produced radiation on military hardware, such as rocket nosecones, warheads, satellites, and communications equipment.

A nuclear device is placed in the end of a tunnel, and a test chamber (as large as about 5.5 meters [18 feet] in diameter) is placed a few hundred feet (meters) to as much as 600 meters (2,000 feet) down the tunnel from the device. A horizontal line-of-sight (LOS) pipe, which tapers from a diameter of about 18 centimeters (7 inches) at the device to about 5.5 meters (18 feet) at the test chamber, connects the device and the test chamber.

After the equipment is installed in the tunnel and leak testing completed, the firing and diagnostic cables are attached. Starting at the device end, the tunnel is then backfilled to contain the explosion products. Backfilling extends down the tunnel past the point on the LOS pipe where a Tunnel and Pipe Seal (TAPS) device is located. Additional devices are installed in the tunnel to ensure containment, details of which will be discussed in Section 3.1.2.1.

The nuclear device is fired by electrical signals sent from a remote firing location at the Control Point (CP-1). Radiation from the nuclear explosion speeds through a vacuum in the LOS pipe and impacts the test materials and equipment mounted in the chamber. In milliseconds after the explosion is initiated, closure devices mounted along the LOS pipe are actuated to contain debris and gases, thus preventing physical damage to the test chamber and its contents.

After the device is detonated, prescribed safety procedures (Metcalf, undated) are followed to reenter the tunnel, and to remove the irradiated test materials and equipment from the test chamber for further evaluation.

Spill Test Facility

A Spill Test Facility that is operated at Frenchman Lake on the NTS (Area 5, Figure 2-6) involves the controlled release and monitoring of various hazardous, nonradioactive materials. The DOE-managed facility is also available for use by other Federal agencies and private industry. The spill testing simulates accidental releases of cryogenic fluids, such as liquefied natural gas, and noncryogenic fluids, such as ammonia, that are normally stored and shipped as pressurized liquids. The information obtained from these tests is used to determine the safety problems presented by accidental spills and to develop better models to predict the dispersion behavior in the atmosphere of these heavy gases.

Radioactive Waste Management Site

DOE manages a Radioactive Waste Management Site in Area 5 that accepts packaged, low-level radioactive waste for storage and disposal from other DOE facilities. DOE is attempting to obtain a permit from the State of Nevada under the Resource Conservation and Recovery Act for this site to accept mixed radioactive and hazardous waste from DOE facilities. For further discussion of radioactive waste management, see Section 4.1.2.1.2.

Past Activities with Residual Contaminants

Since the NTS was established in December 1950 as a continental proving ground, a number of activities have taken place that have resulted in residual contamination at the site. The earliest and most prominent activity was the detonation of nuclear devices in the atmosphere. The first such test, which was conducted on January 27, 1951, involved an airdrop and detonation of a 1-kiloton device over Frenchman Flat. A total of 84 atmospheric detonations were conducted prior to the signing of a Limited Test Ban treaty in August 1963 (ERDA, 1977).

In addition, safety tests were conducted to determine the vulnerability of certain device designs to possible accidents. From 1951 through 1958, 31 safety experiments were conducted that produced only slight or no nuclear yield (NVO, undated). However, these tests resulted in residual radioactive and nonradioactive (e.g., beryllium) contamination of the soil.

Nuclear cratering tests have been conducted as a military experiment for the Department of Defense and as part of the peaceful applications (Plowshare) program. These tests involved shallow underground detonations of nuclear devices to develop large-scale excavation techniques.

The atmospheric tests, safety tests, and nuclear cratering tests are discussed in greater detail in Section 3.2.2.1.

The Nuclear Rocket Development Station (NRDS) at NTS (Area 25, Figure 2-6) was used during the 1960s and early 1970s to test nuclear reactors for space propulsion techniques. Subsequently, the facility was used to reclaim and package nuclear fuel from those reactors and from Tory II C, an air-breathing, nuclear, ram-jet engine. In addition, highly radioactive, spent, unprocessed reactor fuel from commercial nuclear power plants was used in a research and demonstration program for handling and storage.

An experimental farm was operated at NTS (Area 15, Figure 2-6) for DOE by the U.S. Environmental Protection Agency (EPA) to study radionuclide uptake on various farm animals and crops. The 16-year program included studies of the metabolism and biological transfer rates of radionuclides, heavy metals, and other environmental contaminants. Operations at the experimental farm were concluded in 1981 (NVO, undated).

2.2.2 Las Vegas Operations (LVO)

EG&G Energy Measurements, Inc. (EG&G/EM) provides technical support to the Nevada Operations Office and the weapons laboratories from support facilities at a site consisting of about 40 hectares (100 acres) in North Las Vegas. The overall mission is to produce and install diagnostic systems for collecting data associated with underground nuclear detonations at NTS. Major activities at EG&G/EM LVO include the assembly of diagnostic canisters that are used to contain nuclear devices and assorted test apparatus. These canisters are transported to NTS where electrical cable connections are made, the nuclear device mounted, and the completed assembly is lowered downhole. Trailers are outfitted at the North Las Vegas facility with instrumentation to process and record data generated in a test shot.

2.2.3 EG&G/EM Aerial Measurements

Facilities located at McCarran Airport, south of Las Vegas, house operations related to aerial measurements activities. These activities include aerial photography and aerial surveys of radioactivity at DOE facilities.

2.3 State/Federal Concerns

As a part of the NTS pre-Survey visit, a meeting was held in Carson City, Nevada, with officials of the Nevada Division of Health and the Nevada Environmental Protection Division on May 7, 1987. This meeting was held to advise these agencies of the scope and objectives of the Environmental Survey. The agency personnel were asked to express any concerns they might have related to the environmental conditions at the NTS so that these issues could be addressed, as appropriate, during the Survey. The Nevada agency personnel asked questions concerning details of future Survey activities, but did not express any specific concerns related to the NTS. The Environmental Protection Agency (EPA) Region IX was also invited to attend the meeting, but declined. The EPA did express concern over some issues identified during its annual RCRA inspection conducted on February 11, 1987. These issues are summarized below:

- Hazardous wastes had accumulated in storage since April 15, 1986.
- Ignitable wastes were being stored uncovered and exposed to direct sunlight. This situation creates a potential for drum rupture, spillage, and/or explosion.
- Incompatible wastes were being stored adjacent to each other without physical separation.
- A copy of the closure plan for the hazardous waste storage area and hazardous waste landfill area (Area 23 hazardous waste trenches) was not available at the time of the inspection.

In September 1986, it was determined that the NTS had received low-level radioactive wastes containing RCRA hazardous constituents at parts per billion concentrations from the Rocky Flats Plant. At the time of the receipt of this material, the NTS was not authorized to dispose of hazardous waste or mixed radioactive and hazardous waste. This issue is discussed in Sections 4.1.1 and 4.1.2.1.2.

3.0 MEDIA-SPECIFIC SURVEY FINDINGS

The discussions in this section pertain to existing or potential environmental problems in the air, soil, surface water, and groundwater media. The discussions include a summary of the available background environmental information related to each medium, a description of the sources of pollution and their control techniques, a review of the environmental monitoring program specific to each medium, and a categorization and explanation of the environmental problems found by the Survey team related to each medium.

3.1 Air

3.1.1 Background Environmental Information

The air portion of the Environmental Survey of the Nevada Test Site (NTS) is designed to address existing and potential environmental impacts associated with releases of contaminants to the atmosphere, and includes a critical evaluation of air pollution sources and controls, and compliance with air pollution regulations and Department of Energy (DOE) Orders. Adherence to established environmental procedures is evaluated from the standpoint of environmental problems or risks. Principal regulations and DOE Orders relating to air emissions used as guidance during the Survey include

- The Clean Air Act (CAA) and amendments
- Federal regulations, including
 - National Ambient Air Quality Standards (NAAQS) (40 CFR 50)
 - National Emission Standards for Hazardous Air Pollutants (NESHAP) (40 CFR 61)
- Nevada Air Regulations, State Environmental Commission.

The release of radionuclides to the environment from a DOE facility is regulated by DOE Order 5480.1A. In 1985, the DOE adopted, as an amendment to this Order, an interim radiation protection standard to be implemented in calendar year 1985 (Vaughan, 1985). This interim standard incorporates guidance from the National Council on Radiation Protection and Measurement (NCRP), as well as the air emission standards of 40 CFR 61, Subpart H. Included in the interim standard is a revision of the dose limits for members of the public and tables of radiation dose conversion factors to be used for calculating dose from intakes of radioactive materials. The dose factors are based on International Commission on Radiological Protection (ICRP) Publication 30, methodology for radiation dosimetry. Effluent-air derived concentration guides (DCG) were

provided in a memorandum from Robert J. Stern dated February 28, 1986 (Stern, 1986). The DCG applies to inhalation of air by members of the general public.

The assessment of the environmental impacts of airborne radiological emissions from the NTS considered the DOE interim standards referenced above; National Emission Standards for Hazardous Air Pollutants (NESHAP), 40 CFR 61, Subpart H; and NRC limits for concentrations of radionuclides in air above natural background, 10 CFR 20, Appendix B. Although the NRC standards do not directly apply to DOE facilities, they provide a health-based reference for comparisons with site radionuclide releases.

Ambient air quality standards for nonradiological pollutants have been established by the EPA and by the State of Nevada. These standards are presented and compared in Table 3-1. The Nevada standards are equivalent to or, in some respects, more stringent than the national standards. The Nevada regulations require that the standards not be exceeded in areas where the general public has access.

In addition to the air standards mentioned above, the State of Nevada is also concerned about toxic or hazardous air contaminants. According to the Nevada Administrative code (445.717), a substance is defined as a toxic or hazardous air contaminant if it is listed in "Threshold Limit Values for Chemical Substances in the Work Environment 1983-84," and the allowable concentration is based on the toxicity of the substance. Exceptions include substances to which a national or state ambient air quality standard, a new source performance standard, or a national emission standard for hazardous air pollutants is applicable.

The NTS is located in Nye County, Nevada, remote from any major populated area, and therefore not part of any designated Federal Air Quality Control Region (AQCR). The support facilities in North Las Vegas and at McCarran Airport, however, are located in Clark County, which is part of the Las Vegas Valley AQCR. The air quality in the Las Vegas Valley AQCR has been designated by the EPA as "better than national standards" for sulfur dioxide (SO_2); "nonattainment" (does not meet standards) for total suspended particulates (TSP) and carbon monoxide (CO); and "cannot be classified or better than national standards" (insufficient data to make determination) for ozone (O_3) and nitrogen dioxide (NO_2). Air quality in the "rest of state," which includes those portions of the state without an AQCR (such as the NTS), has been designated "better than national standards" for TSP and SO_2 , and "cannot be classified or better than national standards" for O_3 , CO, and NO_2 . These designations are summarized in Table 3-2.

TABLE 3-1

**AMBIENT AIR QUALITY STANDARDS FOR NONRADIOACTIVE POLLUTANTS
NEVADA TEST SITE, MERCURY, NEVADA**

Pollutant	Averaging Time	Nevada Standards ⁽¹⁾	National Standards ⁽²⁾	
		Concentration	Primary ⁽³⁾⁽⁴⁾	Secondary ⁽³⁾⁽⁵⁾
Ozone	1 hour	235 $\mu\text{g}/\text{m}^3$ (0.12 ppm)	235 $\mu\text{g}/\text{m}^3$ (0.12 ppm)	Same as primary
Ozone Lake Tahoe Basin	1 hour	195 $\mu\text{g}/\text{m}^3$ (0.10 ppm)	--	--
Carbon Monoxide below 5,000 feet mean sea level	8 hour	10,000 $\mu\text{g}/\text{m}^3$ (9.0 ppm)	10 mg/m^3 (9.0 ppm)	Same as primary
Carbon Monoxide at or above 5,000 feet mean sea level	8 hour	6,670 $\mu\text{g}/\text{m}^3$ (6.0 ppm)	10 mg/m^3 (9.0 ppm)	Same as primary
Carbon Monoxide at any elevation	1 hour	40,000 $\mu\text{g}/\text{m}^3$ (35 ppm)	40 mg/m^3 (35 ppm)	Same as primary
Nitrogen Dioxide	Annual Arithmetic Mean	100 $\mu\text{g}/\text{m}^3$ (0.05 ppm)	100 $\mu\text{g}/\text{m}^3$ (0.05 ppm)	Same as primary
Sulfur Dioxide	Annual Arithmetic Mean	80 $\mu\text{g}/\text{m}^3$ (0.03 ppm)	80 $\mu\text{g}/\text{m}^3$ (0.03 ppm)	Same as primary
Sulfur Dioxide	24 hour	365 $\mu\text{g}/\text{m}^3$ (0.14 ppm)	365 $\mu\text{g}/\text{m}^3$ (0.14 ppm)	Same as primary
Sulfur Dioxide	3 hour	1,300 $\mu\text{g}/\text{m}^3$ (0.5 ppm)	--	1,300 $\mu\text{g}/\text{m}^3$ (0.5 ppm)
Suspended Particulate Matter	Annual Geometric Mean	75 $\mu\text{g}/\text{m}^3$	75 $\mu\text{g}/\text{m}^3$	60 $\mu\text{g}/\text{m}^3$
Suspended Particulate Matter	24 hour	150 $\mu\text{g}/\text{m}^3$	260 $\mu\text{g}/\text{m}^3$	150 $\mu\text{g}/\text{m}^3$
Lead (Pb)	Quarterly Arithmetic Mean	1.5 $\mu\text{g}/\text{m}^3$	1.5 $\mu\text{g}/\text{m}^3$	Same as primary

TABLE 3-1
AMBIENT AIR QUALITY STANDARDS FOR NONRADIOACTIVE POLLUTANTS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE TWO

Pollutant	Averaging Time	Nevada Standards ⁽¹⁾	National Standards ⁽²⁾	
		Concentration	Primary ⁽³⁾⁽⁴⁾	Secondary ⁽³⁾⁽⁵⁾
Visibility	Observation	In sufficient amount to reduce the prevailing visibility to less than 30 miles when humidity is less than 70%	--	--
Hydrogen Sulfide	1 hour	112 $\mu\text{g}/\text{m}^3$ (0.08 ppm)	--	--

SOURCE: Nevada Administrative Code, 445.582, September 7, 1982.

- (1) These standards must not be exceeded in areas where the general public has access.
- (2) These standards, other than for ozone and those based on annual average or annual geometric means, must not be exceeded more than once per year. The ozone standard is attained when the expected number of days per calendar year with a maximum hourly average concentration above the standard is equal to or less than one.
- (3) Concentration expressed first in units in which it was adopted and is based upon a reference temperature of 25°C and a reference pressure of 760 mm of mercury. All measurements of air quality are to be corrected to a reference temperature of 25°C and a reference pressure of 760 mm of Hg (1,013.2 millibars); ppm in this table refers to ppm by volume, or micromoles of pollutant per mole of gas.
- (4) National primary standards are the levels of air quality necessary, with an adequate margin of safety, to protect the public health. Each state must attain the primary standards no later than 3 years after that state's implementation plan is approved by the Environmental Protection Agency.
- (5) National secondary standards are the levels of air quality necessary to protect the public welfare from any known or anticipated adverse effects of a pollutant. Each state must attain the secondary standards within a "reasonable time" after an implementation plan is approved by the Environmental Protection Agency.

TABLE 3-2

**EPA DESIGNATION OF AIR QUALITY STATUS
NEVADA TEST SITE, MERCURY, NEVADA**

	Las Vegas Valley AQCR	Rest of State (NTS)
Total Suspended Particulates	A	B
Sulfur Dioxide	B	B
Ozone	C	C
Carbon Monoxide	A	C
Nitrogen Dioxide	C	C

SOURCE: 40 CFR 81.329, July 1, 1987.

NTS = Nevada Test Site
 AQCR = Air Quality Control Region
 A = Does not meet primary standards
 B = Better than national standards
 C = Cannot be classified or better than national standards

Wind patterns at the NTS have been studied extensively at four meteorological towers located to record wind data in the valley flats areas as well as on hills and atop a mesa (Quiring, 1968). The wind direction, as measured on a 100-foot (30-meter) tower at an observation station about 5.6 miles (9 km) north-northwest of Yucca Lake near CP-1, is predominantly northerly, except during May through August, when winds from the south-southwest predominate. Because of the prevalent mountain/valley winds in the basins, south to southwest winds predominate during daylight hours of most months. During the winter months, southerly winds have only a slight edge over northerly winds for a few hours during the warmest part of the day. These wind patterns are often quite different at other locations on the NTS because of local terrain effects and difference in elevation (Grossman et al., 1986). Because of these differences and because the NTS is not a production operation with relatively continuous emissions, an annual wind rose is not presented here.

Nuclear weapons testing at NTS produces a wide variety of radionuclides through the fission process, activation of structural materials used in tests, and activation of soil constituents. Uranium and plutonium are used in weapons fabrication, and there are some quantities of these nuclides on the NTS from previous tests. In addition, other activities such as radioactive waste disposal, nuclear rocket testing, and high-level radioactive waste research programs result in the presence of various radionuclides at the NTS. A complete listing of all the radionuclides that might be used, produced by nuclear reactions, or disposed of at the NTS would contain more than 500 entries. Airborne releases of radionuclides from the NTS could contain any of the materials present at the site, although the list of those that are the most likely to be released is limited and includes primarily gaseous and volatile radionuclides such as xenon, krypton, iodine, and cesium isotopes. Strontium-90 and barium-140, although not highly volatile materials, are produced with high relative abundances in nuclear reactions, so these might also be observed as releases from the NTS, should a major containment failure occur during a weapons test. Test containment is discussed in Section 3.1.2. Plutonium may be present in the air at the NTS through resuspension of plutonium-contaminated soils. These soils were contaminated as a result of experiments using high explosives in which there was little or no nuclear yield but plutonium was distributed throughout portions of the eastern and northeastern portions of the NTS. This is discussed in Section 3.2.2.

For the purposes of this discussion, background radioactivity in the vicinity of NTS will be defined as all environmental radioactivity exclusive of any releases from current activities or conditions at the NTS. The background radioactivity in the vicinity of the NTS contains both natural and manmade components. Most of the radionuclides that might be released from current activities or conditions at the NTS are likely to be present as background in the environment as a result of fallout from pre-1963, world-wide, nuclear weapons tests; nuclear power-plant operation; nuclear fuel

reprocessing plants; industrial processes involving radioactive materials; various research and medical applications; and nuclear reactor accidents such as the one at Chernobyl in the Soviet Union, which occurred in April 1986. Background levels of radionuclides in the air will vary with time and location because of meteorological conditions and unusual releases from world-wide sources.

To determine whether current NTS activities or conditions are contributing to radionuclide concentrations in the air, it is necessary to have some knowledge of the background radionuclide contributions from other sources. Because of the many factors that may influence the radionuclide-in-air concentrations, it is not possible to exactly predict background levels in a given area. It is possible, however, to estimate background levels of a radionuclide. One approach to this is to determine the radionuclide concentrations at a location that is nearby, but sufficiently removed that the observed radionuclide levels would not be affected by the potential pollutant source.

EPA's Environmental Monitoring Systems Laboratory (EPA-EMSL) conducts off-site radiological environmental monitoring for the NTS. Included within the EPA-EMSL program are 88 air-sampling stations that are sufficiently remote from NTS that many would be representative of background levels unless a major release of radioactivity from the NTS were to occur. Should a release occur that is large enough to influence the most distant of the monitors, the relative magnitudes of airborne radioactivity observed at nearby and remote stations would allow an accurate assessment of the release. EPA-EMSL reports the results of its monitoring on an annual basis (Patzner et al., 1987).

In addition, EPA's Eastern Environmental Radiation Facility (EPA-EERF) administers a program for radiation monitoring throughout the United States. EPA-EERF reports airborne concentrations of gross-beta activity and plutonium on a quarterly basis. For the period January through March 1987, EPA conducted sampling for gross-beta activity at 63 locations throughout the United States. For that period, the United States average observed activity was $1.1 \times 10^{-14} \mu\text{Ci}/\text{cm}^3$ with a standard deviation of $0.4 \times 10^{-14} \mu\text{Ci}/\text{cm}^3$. Table 3-3 presents airborne background data for four locations in the southwestern portion of the United States (EPA, 1987a). The most recent plutonium-in-air data that has been reported by the EPA is also presented in Table 3-3 (EPA, 1987b). The airborne background activity levels (i.e., exclusive of current activities or conditions) at the NTS would be comparable to levels observed elsewhere in southwestern United States.

3.1.2 General Description of Pollution Sources/Controls

The major activity at the NTS involves weapons-related or weapons-effects tests that produce nuclear explosions. Those tests have the potential to introduce large quantities of radioactive materials into the atmosphere. Other activities conducted in support of the nuclear testing emit or

TABLE 3-3

**AIRBORNE BACKGROUND ACTIVITY LEVELS
FOR SELECTED CITIES IN SOUTHWESTERN UNITED STATES**

	Gross Beta 01/87 - 3/87 ($\times 10^{-14}$ $\mu\text{Ci}/\text{cm}^3$)			Plutonium-238 07/86-12/86 ($\times 10^{-18}$ $\mu\text{Ci}/\text{cm}^3 \pm 2s$)	Plutonium-239 07/86-12/86 ($\times 10^{-18}$ $\mu\text{Ci}/\text{cm}^3 \pm 2s$)
	Average	Minimum	Maximum		
Phoenix, AZ	1.7	0.0	3.0	1.3 ± 1.8	0.4 ± 0.6
Santa Fe, NM	1.0	0.0	4.0	0.2 ± 0.5	0.1 ± 0.2
Los Angeles, CA	1.3	0.0	2.0	0.0 ± 0.9	0.0 ± 0.9
Las Vegas, NV	1.7	1.0	4.0	0.6 ± 1.9	0.6 ± 0.8

Source: EPA 1987a, 1987b.

s = Counting uncertainty, in $\mu\text{Ci}/\text{cm}^3$.

can potentially emit nonradioactive pollutants. In the following sections, the sources of radioactive and nonradioactive air pollutants are described and the techniques used to prevent or minimize atmospheric emissions are discussed.

3.1.2.1 Radioactive Air Contaminants

Prior to 1962, most of the nuclear detonations conducted at the NTS were atmospheric tests. The first full-scale underground nuclear detonation that was specifically designed to contain all radioactivity was fired at the NTS in 1957 in a sealed tunnel. Since late 1962, all U.S. nuclear weapons tests have been conducted underground.

At the NTS, there are three major potential sources that can introduce radioactive contaminants into the atmosphere. These three sources are (1) underground shots conducted in vertical holes (downhole shots), (2) underground shots conducted in horizontal tunnels mined into Rainier Mesa (tunnel shots), and (3) resuspension of surface soils contaminated in the past by atmospheric tests, safety tests, and nuclear rocket development tests. These potential sources, as well as the techniques used to control and prevent emissions, are described below.

3.1.2.1.1 Downhole Shots

The most common method for emplacing nuclear test weapons to contain the explosion and its products is to emplace a test device at the bottom of a vertically drilled hole. Site selection, drilling of the hole, emplacement of the device and diagnostic equipment, and stemming (backfilling of the hole) constitute major activities in the emplacement process. Each of these activities is considered part of the containment process to prevent and control the release of radioactive materials to the atmosphere. For each shot, the containment design is reviewed by a Containment Evaluation Panel (EPA, 1984). The design must be approved before emplacement of a test device.

Several factors are involved in the site selection process. Some of these are

- Past experience in the vicinity under consideration.
- Distances to nearby expended and open emplacement holes.
- Properties of the geologic media.
- Depth of the water table.
- Location and character of ground faults.
- Proximity of geological discontinuities.

- Geophysical logs from nearby holes.
- Potential for carbon dioxide (CO₂) gas production from carbonate rocks.

After a site is selected, the surface area is prepared, and a drilling rig and associated equipment are moved into place. During the actual drilling operation, the geologic formations being penetrated are sampled and the data compared with expected properties. Often, depending on the character of the geologic medium encountered, the emplacement holes are lined with steel casing (cemented in place) to assure integrity of the hole and to provide more convenient access. Holes as large as 12 feet (3.7 meters) in diameter and as deep as 5,000 feet (1,525 meters) are used. When the hole is completed, the drilling rig and associated equipment are moved to a new site.

The emplacement of a test device and diagnostic equipment for a downhole shot usually involves a cylindrical test rack or canister, which is partially assembled at the North Las Vegas Support Facility. At the NTS, a crane is used to lift the canister, which is generally about 200 feet (61 meters) in length, to a vertical position and to suspend it over the hole. A multistory mobile service tower is then moved into place surrounding the canister to provide shelter and workspace while the installation of diagnostic equipment and cable connections are completed. Lead shielding is also installed to protect the equipment from radiation damage in the microsecond interval between detonation of the device and physical destruction of the canister. The test device is then installed, and the service tower is removed. The next step in the emplacement process involves lowering the canister to the bottom of the hole.

After the canister is lowered into the hole, closure activities are undertaken. The closure system for downhole shots consists of a programmed backfilling (known as "stemming") of the hole with carefully prepared materials. In the first stage of the stemming operation, magnetite sand is placed in the hole to fill voids in and around the canister. The magnetite sand serves as an additional shielding material to provide a degree of protection to the diagnostic equipment when detonation occurs. The remainder of the hole is backfilled with alternating layers of 3/8-inch (1-centimeter) gravel (40 to 65 feet [12 to 20 meters] deep) and a fine sand (10 feet [3 meters] deep) that includes 25 percent bentonite or drilling clay. The activities involved in producing these materials on-site are discussed in Section 3.1.2.2. The stemming materials are introduced into the hole at a filling rate of 200 to 300 feet (61 to 91 meters) per 8-hour shift. This rate is controlled to allow adequate time for settling to occur.

Stemming is continued to a point that the hole is filled to within about 10 feet (3 meters) of the bottom end of the steel casing. At this point, a 10-foot-thick (3-meters thick) plug consisting of a mixture of a two-part epoxy resin and an aggregate is placed in the hole. The epoxy resin is allowed

to cure and harden; then additional stemming materials are added, and a second epoxy plug is installed inside the steel casing. A minimum of 2 plugs are used per test hole. At each epoxy plug, the cables are "fanned out" and are protected with field-installed gas blocks, which prevent the cables from acting as conduits from the explosion-produced cavity to the surface.

Some vertical holes use grout (concrete) plugs in place of the two-part epoxy mixture and some holes use cable fan-outs in a fines layer. Also, on occasion, a vertically emplaced test may include a line-of-site (LOS) pipe, in which case normal stemming materials and plugs are used outside the pipe, and appropriate mechanical closures are used within the pipe.

When all systems are ready and meteorological conditions are appropriate (pre-shot meteorological monitoring is described in Section 3.1.3.3), the test device is fired by electrical signals sent from a remote facility in Area 6 (see Figure 2-6), called the Control Point (CP-1). The cavity formation that results from the explosion, cavity collapse, rubble-chimney formation, and surface subsidence events are described in Sections 2.2.1 and 3.4.2.1.

After the surface subsidence occurs and the area is deemed safe (radiologically), equipment is moved into place near the crater rim to begin drilling back into the explosion cavity to sample the explosion debris. A hole about 100 feet (30 meters) deep is drilled initially and lined by a casing that is cemented in place. A blow-out preventer device is installed at the top of the casing to prevent blow out of radioactive gases. During the drill-back operation, pressure is applied to the drilling mud in the casing to force effluent gases back down the drill hole. Following the post-event drill back and sample recovery, the drill hole is sealed.

Despite the extensive measures taken to prevent the release of radioactive materials to the atmosphere, the possibility of a release exists with every shot. Such releases could occur through venting or through seepage. Venting is a dynamic release of material through large cracks or fissures in the ground, while seepage is a slow leaking of gases through tiny channels leading to the ground surface. The most recent venting occurred in December 18, 1970, following the BANE BERRY event (Thalgott and Weart, 1971), and the most recent seepage occurred on September 25, 1980, after the RIOLA event (NVO, 1980). Despite extensive controls, radioactive gases can also be released to the atmosphere during drill-back operations. Atmospheric monitoring for possible releases of radioactive materials is discussed in Sections 3.1.3.1 and 3.1.3.2.

3.1.2.1.2 Tunnel Shots

A second technique used in nuclear testing at the NTS is to emplace a test device within a tunnel that has been mined horizontally into Rainier Mesa to a location that is sufficiently deep to provide containment. Tunnel experiments generally include a horizontal LOS pipe and a test chamber within the mined tunnel, and the usual purpose is to determine the effects of radiation from a nuclear explosion on instruments and materials of construction mounted in the test chamber. The descriptions of containment devices and techniques discussed below represent minimal efforts that are supplemented by additional protection on a case-by-case basis.

A typical tunnel shot involves two parallel tunnels that are known as the main drift and the utility drift. These are shown schematically in Figure 3-1. (For some shots, only a main drift is used.) In addition to the parallel tunnels, several interconnecting passageways are mined to provide working access to various points along the main drift. At the deep end of the main drift, a chamber is installed to house the nuclear device. This location is known as the working point or ground zero. A test chamber to house instrumentation and materials of construction that will be exposed to radiation from the nuclear explosion is located several hundred to 2,000 feet (601 meters) down the main drift. An LOS pipe that tapers from about 7 inches (18 centimeters) in diameter at the working point and to about 18 feet (5.5 meters) in diameter at the test chamber connects the two chambers.

After the nuclear device is installed at the working point and all utility connections completed, the main drift, the utility drift, and connecting passageways are backfilled with stemming materials to a point between the tunnel-and-pipe-seal (TAPS) area and the test chamber. A rock-matching grout is used at the working point and for the first few feet from it. A super lean grout, which is a very weak cement/sand grout, is used as stemming material over the next several feet along the LOS pipe. This material tends to be pushed along the LOS pipe by the ground shock, exerting pressure on and collapsing and sealing the pipe. Regular concrete forms the remainder of the stemming material. In the utility drift, all electrical cables are provided with gas blocks. Air and cooling water lines in the stemmed area of the utility drift are fitted with redundant ball valves.

The stemmed area constitutes vessel No. 1 of a 3-vessel containment system. Three closure devices are used on the LOS pipe within containment vessel No. 1 to protect the test chamber from physical damage by debris and gases from the explosion. These devices, which are designed to close the LOS pipe in milliseconds after the nuclear device is exploded, allow the fast-moving radiation to pass but stop any flying debris or gases. The three devices, in the order of their location from the working point, are (1) a fast-acting closure for a low-yield device or a modified auxiliary closure (MAC) if a

FIGURE 3-1

SCHEMATIC OF TUNNEL LINE-OF-SIGHT PIPE CONFIGURATION NEVADA TEST SITE - MERCURY, NV

Source: Ashbaugh, 1987

high-yield device is used, (2) a gas-sealed auxiliary closure (GSAC), and (3) a tunnel and pipe seal (TAPS).

Containment vessel No. 2 extends from the end of stemming down the tunnels to about 3,000 feet (915 meters) from the working point. At this point, a drift protection plug (DPP) is installed. The DPP is designed to withstand a temperature of 1,000°F (524°C) and a pressure of 1,000 pounds per square inch (6,895 kilonewtons per square meter [kN/m^2]), and is intended to provide the same degree of protection as the surrounding overburden. Within vessel No. 2, there are several alcoves that house diagnostic equipment. These alcoves are protected by other plugs, known as alcove protection plugs.

Containment vessel No. 3 consists of an area between the DPP and a poured concrete, gas-seal plug (GSP) in the tunnel leading to the portal. When the GSP is in place, the tunnel inside the GSP is pressurized with freon to test for leaks. The ground surface on the mesa above the tunnel is checked for freon emissions, and any leaks are sealed with an expansive grout. As a final device to prevent gases from entering the tunnel leading to the portal, a gasket-sealed steel door is installed and pressure tested to 15 pounds per square inch (103 kN/m^2).

An extensive network of remote-area monitors is installed both in the tunnel and on the Mesa surface (Metcalf, undated). These detectors supply information about the radiation levels for surface and tunnel reentry personnel, and give early quantity estimates in the event of a release. In addition, gas sampling lines are installed at selected locations in the main drift, the utility drift, and at the drift protection plug through which post-shot gas samples can be drawn. Also, air samplers are installed in vent lines (two in the tunnel vent-line system that exhaust on the mesa and one in the vent-line system serving the tunnel portal) for post-shot evaluation.

Shortly after a tunnel shot is fired, gas samples are drawn from within the tunnel for analysis. On the day following the shot, reentry procedures to recover equipment and records are initiated with the opening of the gas-seal door and ventilation of the tunnel to the gas-seal plug. Ventilation or purging of a tunnel involves the displacement of tunnel air with clean air make-up, filtration of displaced air through particulate and charcoal filters, and dilution with clean make-up air prior to release to the atmosphere. This procedure captures most of the radioactive particulates and reactive gases, releasing essentially only radioactive noble gases.

When the amount of radioactivity contained in the tunnel is high enough that it may be detectable off-site, tunnel ventilation is performed only when the wind will carry the radioactivity away from populated areas to minimize potential exposures (Black et al., 1986).

3.1.2.1.3 Resuspension of Contaminated Surface Soils

Surface soils at several areas of the NTS are contaminated with radioactive materials as a result of past activities, including atmospheric nuclear detonations, "equation-of-state" studies, safety tests, near-surface cratering tests, and nuclear rocket motor tests. The potential for transport of radioactive materials from the NTS by entrainment or resuspension in air has been studied extensively by NVO in its Nevada Applied Ecology Group studies and the Radionuclide Inventory and Distribution Program. The contamination of surface soils and these studies are discussed in Section 3.2.2.

3.1.2.2 Nonradioactive Air Contaminants at the NTS

Sources of nonradioactive air contaminants at the NTS consist of three distinct types: (1) fuel-burning sources, (2) process sources, and (3) sources of fugitive emissions. Each of these three types is discussed below, along with the applicable regulations from the Nevada Administrative Code.

3.1.2.2.1 Fuel-Burning Sources and Controls

- Boilers

The NTS has 23 boiler units that range in size from 0.45×10^6 to 12.7×10^6 British thermal units (Btu) per hour (0.46×10^9 to 12.98×10^9 Joules [J] per hour) of heat input. All 23 units are designed to be fired with No. 2 fuel oil. Nine units produce steam, and the remaining 14 are water heaters. An inventory of the boilers is shown in Table 3-4. All of the boilers operate without emission control devices, which are not required by existing permits.

The Nevada Administrative Code (445.704 and 445.705) requires that fuel-burning equipment having a rating of 4.0×10^6 Btu per hour (4.09×10^9 J per hour) or more must obtain a registration certificate and an operating permit. Although the regulation is not specific, it may be inferred from 445.711 that the decision to obtain the certificate and permit should be based on rated heat input rather than rated heat output. On that basis, six of the NTS boilers are required to have registration certificates and operating permits; only three of the six had the stipulated certificate and permit at the time of the Survey (see Finding No. 1 in Section 3.1.4.4).

TABLE 3-4

**INVENTORY OF FUEL-OIL-FIRED STEAM AND HOT-WATER BOILERS
NEVADA TEST SITE, MERCURY, NEVADA**

NTS Number	Location	User	Service	Manufacturer	Model Number	Serial Number	Heat Input Rating, 106 Btu/hr	Air Permit Number
701037	Bldg. 754	Cafeteria	Steam	Ajax	SOXFD-4000	83-35648	4.0	(a)
700682	Bldg. 210	DOD	Steam	Birchfield	NA	7560	NA	NO
700996	Bldg. CP-1 #1	Control Point	Steam	Cleaver Brooks	CB-100-50	L-65293	2.092	NR
700065	Bldg. CP-1 #2	Control Point	Steam	Cleaver Brooks	CB-100-50	L-65294	2.092	NR
700952	Bldg. CP-9	CADAC	Steam	Ajax	SOX-200	74-27839	NA	NO
701033	Bldg. 6-605	Decon	Steam	York Shipley	SPLY-125-2	82-14857	4.184	1036
700903	Bldg. 12-30	Cafeteria	Steam	Ajax	SOXFD-4500	73-26979	4.5	(a)
NA	Area 25-A&E	NA	Steam	Kewanee	M-265-FO	M-7321	2.65	NR
173046	Portable	None	Steam	Superior	HSB 92990	1342, 1576	12.7	1035(b)
NA	Warehouse 7	LLNL	Hot Water	Ajax	WOFD-250	79-32023	NA	
700616	Bldg. 111	DOE	Hot Water	Ajax	WO-600	20293-6U	0.6	NR
136862	Bldg. 128	LLNL	Hot Water	Rite	105-X	10992-P-10	1.05	NR
700714	Bldg. 156	USGS	Hot Water	Ajax	WO-450	21686-10V	0.45	NR
NA	Bldg. 536	Dorm	Hot Water	Ajax	WOFD-2250	85-37453	2.25	NR
701039	Bldg. 753	Fleet Ops	Hot Water	Ajax	WOFD-6500	83-35651	6.5	925
701038	Bldg. 754	Cafeteria	Hot Water	Ajax	WOFD-4000	83-35625	4.0	(a)

TABLE 3-4
INVENTORY OF FUEL-OIL-FIRED STEAM AND HOT-WATER BOILERS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE TWO

NTS Number	Location	User	Service	Manufacturer	Model Number	Serial Number	Heat Input Rating, 10 ⁶ Btu/hr	Air Permit Number
700953	Bldg. CP-9	CADAC	Hot Water	Ajax	WO-1050	74-27838	1.05	NR
136864	Bldg. CP-10	Sandia	Hot Water	Rite	48	10990	0.48	NR
700927	Bldg. 6-605	Decon	Hot Water	Ajax	WOXFD-700	75-28536	0.7	NR
700849	Bldg. 6-607	Decon Laundry	Hot Water	Bock	136-E	5-78-352	0.91	NR
701034	Bldg. 6-607	Decon Laundry	Hot Water	Bock	136-E	12-82-344	0.91	NR
700810	Bldg. 11-2	Tweezer	Hot Water	Rite	65-X	6085 K4	0.63	NR
700717	Bldg. 12-16	REECo	Hot Water	Ajax	WO-2250	22632-9W	2.25	NR

SOURCE: Adapted by DOE Environmental Survey team, 1987, from REECo data sheets dated 7/21/86 and 10/6/86.

(a) Air Quality Operating Permit required based on heat input rating of 4.0 x 10⁶ Btu/hour or more. At the time of the Environmental Survey, no application had been filed with the State of Nevada, Department of Conservation and Natural Resources.

(b) Out of service indefinitely.

NA Not Available.

NO Not Operated.

NR Permit Not Required.

Air Quality Operating Permits (No. 925, 1035, and 1036) issued for three of the NTS boilers with rated heat input values greater than 4.0×10^6 Btu per hour (4.09×10^9 J per hour) require that the boilers be operated in compliance with Nevada Administrative Code 445.430 through 445.846 (including calculations to determine the maximum allowable particulate and sulfur emissions rates, and testing and sampling to determine compliance). During the on-site Survey, no evidence was available to demonstrate that these requirements had been met. However, a monthly sampling of exhaust gases is taken to check the opacity of the smoke (degree of staining of a paper filter) and to evaluate boiler efficiency.

The operating permits also require an annual analysis of fuel for sulfur content and Btu heating value. Reports of analysis on fuel oil for 1984, 1985, and 1986 show sulfur contents ranging between 0.29 and 0.43 weight percent (existing permits do not specify a sulfur content limit) and Btu content from 136,871 to 141,264 Btu per gallon (38,148 to 39,373 kilojoules per cubic meter). In addition, monthly reports are prepared showing on-line time for each of the three permitted boilers.

- Aggregate Dryer

A rotary dryer is operated at the Shaker Plant in Area 1 (Figure 2-6) to reduce the moisture content of aggregate used in downhole stemming operations. Air Quality Operating Permit No. 923 covers the dryer operation. The dryer uses No. 2 fuel oil, which is burned in the dryer such that the flame is in direct contact with the aggregate. Particulate emissions from the aggregate are controlled by an Envirotech baghouse. Emissions are also controlled by a limitation on operating hours (1,000 hours per year, maximum). Production data for calendar year (CY) 1986 that were provided to the Nevada Air Quality Officer show that the dryer was operated for 275 hours, with a production level of 8,806 cubic yards (6,737 cubic meters) (Frazier, 1987a).

The Nevada Administrative Code provides a particulate emission limitation that is based on process weight (445.732[3]). For the aggregate dryer, that limitation is calculated using the following equation:

$$E = 55P^{0.11} - 40$$

where E = maximum allowable particulate emission rate in pounds per hour, and

P = process weight rate in tons per hour.

Thus, the maximum allowable particulate emission rate (E) would be

$$E = 55(250)^{0.11} - 40$$

$$E = 61 \text{ pounds (27.7 kilograms) per hour.}$$

During the on-site Survey, no test results were available to demonstrate compliance with this limitation. An annual compliance inspection report from the state indicates that the dryer is in compliance with state regulations (Freeman, 1987).

- Stationary Diesel Engines

The Nevada Administrative Code (445.721) imposes limitations on the opacity of emissions from stationary sources, which includes stationary diesel engines. An exception is granted (445.722[5]) for a 15-minute warm-up period to achieve operating temperatures.

During the course of the on-site Survey at NTS, a limited number of stationary diesel engines were observed in operation in Area 20 at U20ax providing power to air compressors and electrical generators. Barely visible emissions were apparent from some of those engines, which had been in operation beyond the 15-minute warm-up period. However, because the Survey observer was not a trained and certified smoke observer, the opacity levels were not estimated.

- Open Burning

The Nevada Administrative Code (445.753) prohibits open burning of combustible materials, except as specifically exempted, unless such burning has been approved in advance by the Director of the State Department of Conservation and Natural Resources. In the recent past, the NTS has obtained advance approval for limited time periods to conduct open burning for fire-rescue exercises and radiological emergency response training (McCleary, 1986), as well as to evaluate the survivability of a tank by igniting the tank's fuel supply and letting it burn (McCleary, 1987). These permits specified conditions under which the burn could be conducted, and provided a limited timeframe in which the permitted burn could occur.

Other open-burning activities are conducted at the NTS without obtaining prior approval. Two such activities (see Findings in Section 3.1.4.4., Nos. 4 and 5) are the burning of solvent-contaminated paper wipes in a wire cage (8 feet long x 5 feet wide and 5 feet

high) at Area 27, and disposal of high explosives and cartons at Area 11 (see Section 4.1.2.1.1, Hazardous Waste). The former activity appears to take place on a fairly regular, routine basis, while the latter is only conducted once or twice per year.

3.1.2.2.2 Process Sources and Controls

- Shaker Plant

A screening facility, known as the shaker plant, is located in Area 1, near a strip mine where desert soil and rock are recovered. The mined materials are transported a short distance by truck to the screening operation, where pea-gravel and fines fractions are recovered. These screened products are used as stemming materials in downhole shots.

The facility consists of three triple-deck screens, various conveyor systems, and storage bins. A baghouse is used to control emissions of particulates from the screening operations and conveyor transfer points. An Air Quality Operating Permit (No. 922) limits operations to 1,520 hours per year. During CY 1986, the facility was operated for 1,093 hours to produce 71,966 cubic yards (55,054 cubic meters) of product (Frazier, 1987a).

For each of the screening stations, the Nevada Administrative Code (455.732[3]) provides a particulate emission limitation that is based on the maximum allowable production rate. That limitation is calculated using the following equation:

$$E = 55P^{0.11 - 40}$$

where E = maximum allowable particulate emission rate in pounds per hour, and
P = process weight rate in tons per hour

Thus, the maximum allowable particulate emission rate (E) would be

$$E = 55(500)^{0.11 - 40}$$

$$E = 69 \text{ pounds (31.4 kilograms) per hour}$$

During the on-site Survey, no test results were available to demonstrate compliance with this limitation. An annual compliance inspection report from the state indicates that the plant is in compliance with state regulations, but that fugitive dust has been a problem

because the product is required to have a moisture content of less than 5 percent (Freeman, 1987).

During the on-site Survey, the facility was observed while in operation. The emissions of particulates from the screening operations and from transfer points appeared to be well controlled by the baghouse. However, heavy emissions of fugitive dust were evident when raw materials were transferred to the feed hopper by means of a front-end loader.

A second facility in the vicinity of the shaker plant is an aggregate plant that consists of feeder bins, a crusher, screens, sand screws, and conveyors. The facility produces aggregate materials for use in concrete. Nevada Air Quality Operating Permit No. 1287 limits throughput to 150 tons per hour (136 metric tons per hour) and (based on Nevada Administrative Code 445.839) sets a maximum allowable particulate emission rate of 6.6 pounds per hour (2.99 kilograms per hour). The permit requires at least 91 percent control efficiency using enclosed transfer points and water sprays. The permit also limits operations to no more than 9 hours per day, nor more than 1,125 hours per year.

During the on-site Survey, no test results were available to demonstrate that the facility complied with the particulate emission limitation or that the control efficiency had been met. During CY 1986, the aggregate plant operated for a total of 524 hours with a throughput of 23,578 cubic yards (18,037 cubic meters) (Frazier, 1987a). Based on a bulk density of 2,200 pounds per cubic yard (1.3 metric ton per cubic meter), this equates to an average throughput of 49.5 tons (45 metric tons) per hour, well below the allowable limit. Observation of the operation during the on-site Survey showed that the only apparent particulate emission came from the crusher, where small particles were being generated. At all other potential emission points, water sprays were effective in controlling particulate emissions.

- Cement Storage and Concrete Batch Plants

A cement storage and blending facility, which operates under Air Quality Operating Permit No. 918, is located in Area 6 (see Figure 2-6). The facility consists of storage silos where various grades of cement and additives are stored, along with equipment that is used to transfer materials into and out of the silos. Production data show that 26,080 tons (23,709 metric tons) were produced in CY 1985 and 21,552 tons (19,593 metric tons) were produced in CY 1986 (Bruesch, 1986 and Bartlett, 1987). Incoming cement and additives, in the form of finely divided particles, are transferred from delivery trucks to storage silos

in pipelines, using air to move the powdered materials. According to the permit, emissions of particulates from the vents on the silos are controlled by the use of three baghouses; however, correspondence with the Nevada Division of Environmental Protection indicates that a new dust-collection system consisting of filters was constructed in place of the baghouses between October 29, 1985 and March 21, 1986 (Bartlett, 1985 and Cross, 1986). These changes were made without revision being made to the Air Quality Registration Certificate (No. 780) or the Air Quality Operating Permit (No. 918).

The transfer of cement or additives from the storage silos to a truck is accomplished by connecting the silo and the truck by means of a pipeline. Air is used to transport the powdered materials into the truck bins (Figure 3-2). The transport air leaving the truck bin travels through an underground pipeline to a dust knock-out tank and then through a baghouse before being exhausted to the atmosphere.

During the on-site Survey, this system was observed while a truck was being filled with cement. The baghouse appeared to be ineffective in controlling dust emissions, because heavy emissions of cement dust were observed. From the appearance of the exhaust plume, the filter bags were either broken or missing (see Finding No. 3 in Section 3.1.4.4). Although an Air Quality Operating Permit (No. 918) exists for the cement storage facility, the truck loading operation and the baghouse are not described in the permit.

Two concrete batch plants are located at the NTS, one of which is in Area 12 and the other in Area 1. The plant in Area 12 produces concrete mixes for use in tunnel stemming and sealing applications. The plant is covered by Air Quality Operating Permit No. 928, which limits production to no more than 8 hours per day and no more than 296 hours per year. During CY 1986, the plant was operated for a total of 60.5 hours producing 541 cubic yards (414 cubic meters) of concrete (Frazier, 1987a). An inspection conducted by the state in 1987 indicated no air-quality or permit violations (Freeman, 1987). The plant was observed in operation during the on-site Survey, with only minor evidence of visible emissions of cement dust from concrete mixing trucks.

The concrete plant in Area 1 produces concrete or grout, which are used in downhole operations. The plant is covered by Air Quality Operating Permit No. 1082, which restricts plant operation to no more than 500 hours per year. During CY 1986, the plant was operated for 231 hours, producing 6,319 cubic yards (4,834 cubic meters) of concrete and grout (Frazier, 1987a). A state inspection in 1987 indicated no permit or air-quality violations.

Source: DOE Environmental Survey team, 1987.

FIGURE 3-2

CEMENT AND ADDITIVE STORAGE AND BLENDING PLANT NEVADA TEST SITE - MERCURY, NV

- Downhole Stemming

The activities involved in closure of a vertical test hole (known as "stemming") to ensure containment of the radioactive materials produced in the nuclear explosion were discussed in Section 3.1.2.1. Because of the nature of the materials used in stemming (gravel and fine sand) and a requirement to keep moisture below 5 percent, the stemming operation is a source of nonradioactive particulate emissions to the atmosphere. Two types of stemming facilities are used by Los Alamos National Laboratory and Lawrence Livermore National Laboratory. Those facilities and the associated particulate emissions are discussed below.

Los Alamos National Laboratory uses equipment that is mounted on a semi-trailer that can readily be moved to and positioned at the test hole. The equipment consists of four double hoppers with remotely operated discharge gates, and conveyor belts that transport stemming materials from the hoppers to the test hole at a controlled rate. Two of the hoppers handle 3/8-inch (1-centimeter) gravel and the other two are used for fine sand. The conveyors are covered and discharge spouts are enclosed, as required by Air Quality Operating Permit No. 1089, to minimize dust emissions. Also required by the permit is an annual report of operating hours and production. During calendar year 1986, the facility was operated for 225 hours, processing 17,850 cubic yards (13,655 cubic meters) of stemming materials (Frazier, 1987a).

During the Environmental Survey, the stemming operation at the Midland Test Site was observed. Dust emissions from the conveyor belt and from the conveyor discharge were minimal (as surmised from the lack of dust rising from the hole). However, when the hoppers were refilled by means of a front-end loader, substantial clouds of dust were released. Also, when the front-end loader was overfilled with fine sand, spillage and dust emissions occurred during transit from the nearby storage pile to the stemming facility (see Finding No. 7 in Section 3.1.4.4). The emission rates have not been measured nor have they been estimated.

The Lawrence Livermore National Laboratory uses a stemming-facility design that consists of a charging hopper, a conveyor to move the aggregate into a weigh hopper, and one or two conveyors (depending on accessibility of test hole) from the weigh hopper to the test hole. The discharge end of each conveyor is enclosed and the conveyor from the charging hopper to the weigh hopper is covered to minimize dust emissions. The conveyor(s) from

the weigh hopper to the hole is shielded but not covered. Two essentially identical stemming facilities are covered by Air Quality Operating Permit Nos. 957 and 958. These permits do not require annual reports of operating hours and production. Neither of the facilities was in operation during the on-site Survey.

3.1.2.2.3 Fugitive Dust Sources and Controls

- Surface Disturbances - The Nevada Administrative Code [445.734(3)] requires that an air-quality registration certificate and an operating permit be obtained prior to disturbing 20 or more acres (8 hectares) of land. The purpose of this requirement is to minimize the potential for windblown dust emissions from exposed surfaces. At the time of the on-site Environmental Survey, the State of Nevada had issued two registration certificates and two operating permits for surface disturbances at the Nevada Test Site.

Registration Certificate No. 974 (issued April 19, 1985) covers a surface-area disturbance of about 1,940 acres (785 hectares) in Area 6, where a Device Assembly Facility is to be constructed. Much of the initial grading work had been completed and natural vegetation had begun to cover the surface at the time of the Environmental Survey. Also, the access road to the area had been paved. A second Registration Certificate (No. 1367) was issued on March 17, 1987, to cover surface disturbances in preparation for underground nuclear test shots and all other surface disturbances at the Test Site. This certificate requires that an annual report be filed, reporting all surface-area disturbance of 5 acres (2 hectares) or greater. Also, the certificate requires that any area initially disturbed and left inactive for more than 6 months be controlled by chemical stabilization, revegetation, or other approved method.

An Air Quality Operating Permit (No. 921) was issued on December 3, 1984, for a surface-area disturbance in Area 5 consisting of a pit area of 76 acres (30 hectares) and a storage yard of 44 acres (18 hectares). This area had been used as a source for downhole stemming materials, but because that activity ceased, the area has naturally revegetated.

Air quality Operating Permit No. 1084 was issued January 30, 1986, for a surface-area disturbance in Area 1, which consists of the 205-acre (83-hectare) borrow pit, a 51-acre (21-hectare) storage area, 8 acres (3 hectares) of haul and access roads, and a 19-acre (7-hectare) processing plant area. The operating facility is known as the Area 1 Shaker Plant, which produces materials for downhole stemming activities.

- Reentrainment of Unpaved-Road Dust - The Nevada Administrative Code (445.734) prohibits any activity relating to unpaved roads that would allow controllable particulate matter to become airborne. The Code further requires that measures be taken to prevent the reentrainment of particulate matter. At the NTS, frequent applications of water to unpaved roads and work areas were observed to be highly effective in minimizing dust emissions. However, long haul roads between work areas were not watered, and sporadic dust clouds were observed as a result of vehicular movements along those roads (see Finding No. 8 in Section 3.1.4.4).

3.1.3 Environmental Monitoring Program

3.1.3.1 On-Site Radiological Monitoring

Routine environmental monitoring for airborne radionuclides for the NTS is conducted by both NTS personnel and the EPA's Environmental Monitoring Systems Laboratory (EPA-EMSL). The NTS personnel are responsible for monitoring within the site boundaries, and EPA-EMSL is responsible for maintaining an off-site monitoring network.

The results of the on-site monitoring for calendar year 1985 were reported by NTS in a report published in September 1986 (González, 1986). In 1985, the NTS on-site air monitoring network consisted of 47 stations for particulates and radioiodines, 8 stations for noble gases, and 17 stations for tritium. The locations of the sampling stations were chosen to provide optimum occupational monitoring, although factors such as complete geographical coverage, access to the locations, and availability of power were also considered.

The particulate/iodine sampling units consist of positive displacement pumps drawing air at approximately 3.5 cubic feet (100 liters) per minute through Whatman GF/A filters for particulates, followed by a charcoal cartridge for halogens. Samples are collected weekly and analyzed following a 7-day delay to allow decay of naturally occurring radon and its short-lived decay products. The particulate filters are analyzed for gross-beta activity and gamma-emitting radionuclides. The charcoal cartridges are analyzed for radioiodines by gamma spectrometry. On a monthly basis, the weekly particulate filters are composited and analyzed for plutonium-239.

Separate sampling units are used for the collection of water vapor samples to permit analyses for tritium in air. The samplers draw air at a rate of approximately 0.5 liter/minute, and water vapor is removed from the air stream by silica gel columns. The water vapor is removed from the silica gel by

heating in a distillation apparatus and collecting the condensed vapor. The collected water vapor, including tritiated water (HTO), is analyzed for tritium by liquid scintillation spectrometry. Samples are collected and analyzed every 2 weeks.

Noble gas samples are collected using a third type of sampler. The samplers consist of three metal air cylinders connected in series. A vacuum is maintained on the first bottle. This vacuum results in a steady flow of air of approximately 0.5 cubic centimeter per minute into the 2 collection bottles. The sample volume is approximately 10.6 cubic feet (0.3 cubic meter). Noble gases are separated from other gases and each other by cryogenic stripping and gas chromatographic techniques. The separated radioactive noble gases are quantified by liquid scintillation spectrometry.

For 1985, the annual average gross-beta activities ranged from a high of 1.9×10^{-14} microcuries/cm³ to a low of 1.4×10^{-14} $\mu\text{Ci}/\text{cm}^3$. The network average was 1.7×10^{-14} $\mu\text{Ci}/\text{cm}^3$. Analytical uncertainties for these data were not reported by NTS. The observed gross-beta activities are comparable to the United States average background gross-beta activity levels of 1.0×10^{-14} $\mu\text{Ci}/\text{cm}^3$ (EPA, 1987a). There is no DOE-derived concentration guideline (DCG) for gross-beta activity in air; however, strontium-90 has one of most restrictive DCGs for beta-emitting radionuclides at 9×10^{-12} $\mu\text{Ci}/\text{cm}^3$ in an unrestricted area. The maximum annual-average gross-beta activity observed at NTS during 1985 was only 0.2 percent of the strontium-90 DCG.

For plutonium-239 in air, the 1985 annual average activity for 44 of the 47 stations was on the order of 1×10^{-17} $\mu\text{Ci}/\text{cm}^3$. Three stations exhibited average activity levels significantly higher than the network average: Area-3 300 Bunker, 32×10^{-17} $\mu\text{Ci}/\text{cm}^3$; Area-9 300 Bunker, 113×10^{-17} $\mu\text{Ci}/\text{cm}^3$; and Area-9 300 Bunker No. 2, 152×10^{-17} $\mu\text{Ci}/\text{cm}^3$. The average concentration at the Area-9 300 Bunker No. 2 station (location of the highest reading) was 7.6 percent of the DCG for an uncontrolled area (2×10^{-14} $\mu\text{Ci}/\text{cm}^3$) and 0.08 percent of the DOE occupational DCG (2×10^{-12} $\mu\text{Ci}/\text{cm}^3$). The presence of plutonium-239 is primarily a result of resuspension of soils contaminated with plutonium during atmospheric nuclear detonations, safety experiments, and nuclear rocket engine test conducted prior to 1960. This contamination is discussed in greater detail in Section 3.2.2.

Tritium-in-air concentrations during 1985 ranged from a low of 6.6×10^{-13} $\mu\text{Ci}/\text{cm}^3$ to a high of 1.2×10^{-7} $\mu\text{Ci}/\text{cm}^3$. Annual averages ranged between $<2.9 \times 10^{-12}$ and $<8.0 \times 10^{-9}$ $\mu\text{Ci}/\text{cm}^3$. The maximum observed tritium concentration was at Building 650 in Area 23. The annual average at this location was $<8.0 \times 10^{-9}$ $\mu\text{Ci}/\text{cm}^3$. The maximum value is 60 percent of the environmental DCG (2×10^{-7} $\mu\text{Ci}/\text{cm}^3$) and 0.4 percent of the occupational DCG (3×10^{-5} $\mu\text{Ci}/\text{cm}^3$). Since Building 650 is located in an area that is not generally accessible to members of the general public, the occupational

DCG would apply to concentrations of tritium in air. Samples containing tritium from drill-back operations are processed in Building 650, and some tritium is released. The proximity of the sampler to this building is most likely responsible for the elevated activity.

The noble gas releases reported at NTS during 1985 were krypton-85 and xenon-133. Krypton-85 concentrations have been increasing world-wide from releases at nuclear power reactors and nuclear fuel processing facilities. The maximum krypton-85 concentrations observed at NTS ranged from $28 \times 10^{-12} \mu\text{Ci}/\text{cm}^3$ to $129 \times 10^{-12} \mu\text{Ci}/\text{cm}^3$. World-wide krypton-85 background levels are approximately $35 \times 10^{-12} \mu\text{Ci}/\text{cm}^3$ (NWN, 1987). The highest observed concentrations were at the Area 20 Camp. The elevated concentrations at Area 20 are attributed, by NTS personnel, to seepage from weapons testing events. The maximum observed xenon-133 concentrations ranged from values below the detection limits to a high of $1.16 \times 10^{-9} \mu\text{Ci}/\text{cm}^3$. The highest value was observed at the Area 20 Camp. All detectable concentrations of xenon-133 and concentrations of krypton-85 above background were directly related to seepage and drillback from nuclear weapons testing events and the venting of tunnels following weapons effects tests.

The concentrations of krypton-85 and xenon-133 that would yield the DOE exposure limit of 100 mrem/yr to a member of the general public (for continuous exposure) are $3 \times 10^{-6} \mu\text{Ci}/\text{cm}^3$ (krypton-85) and $4.8 \times 10^{-7} \mu\text{Ci}/\text{cm}^3$ (xenon-133). The maximum observed concentrations of krypton-85 and xenon-133 were 4.3×10^{-3} percent and 0.24 percent of these values, respectively.

3.1.3.2 Off-Site Environmental Monitoring Program

The off-site environmental monitoring for the NTS is conducted by EPA-EMSL (Patzner et al., 1987). EPA-EMSL maintains two monitoring networks for airborne radionuclides:

- Air Surveillance Network (ASN)
- Noble Gas and Tritium Surveillance Network (NGTSN)

The ASN is designed to monitor locations within 220 miles (350 km) of the NTS, with some of the stations concentrated in the prevailing downwind direction. The ASN sampling stations monitor for airborne radioactive particulates and radioiodines. During 1986, the ASN consisted of 30 continuously operating stations (Figure 3-3), supplemented by a standby network of 83 stations that covers the contiguous states west of the Mississippi River.

The ASN samplers draw air through 2-inch (5-cm) glass-fiber particulate filters backed with charcoal cartridges to collect gaseous radioiodines. During 1986, filters and cartridges were changed every

2-3 days, after a total sample flow of about 5,650 to 12,170 cubic feet (160 to 360 cubic meters [(m³)). Samplers are operated by nearby residents trained by EPA-EMSL. The samplers in the standby network are identical to the ASN samplers and are operated by state and municipal health department personnel or local residents. During 1986, the standby network was operated for 1 to 2 weeks per quarter at most locations, and for several weeks following the Chernobyl accident in the Soviet Union.

All filters and cartridges from the ASN and the standby network are analyzed by EPA-EMSL for gamma-emitting nuclides. Samples from 5 stations are analyzed for gross-beta activity, and samples from 15 states are composited and analyzed for plutonium-238 and -239. EPA-EMSL concluded that during 1985, no airborne radioactivity related to nuclear testing at the NTS was detected on any sample from the ASN or the standby network (Patzner et al., 1987). All plutonium results were less than the minimum detectable concentrations, which varied from 2 to 500×10^{-18} Ci/m³. The networks detected several gamma-emitting radionuclides, but these were all either naturally occurring beryllium-7 or fission product debris from the Chernobyl accident in the Soviet Union. The gross-beta results also exhibited the influence of the Chernobyl debris.

The NGTSN is designed to detect emissions of tritium and noble gases from the NTS. Samplers are located near the NTS, particularly in drainage wind channels leading from the test areas and at more remote locations that serve as background indicators. The samplers also permit long-term tracking of potential releases. In 1986, the network consisted of 17 stations (Figure 3-4).

Samples in the NGTSN are collected continuously, and the sample tanks and collection media changed weekly. For tritium sampling, up to 353 cubic feet (10 m³) of air are drawn through molecular sieves, trapping only water vapor from the air stream. The water containing tritiated water (HTO) adsorbed on the molecular sieves is recovered, and the tritium content is determined by liquid scintillation spectrometry.

Noble gas samples are collected by one of two methods: (1) direct compression, or (2) cryogenic liquefaction. Either technique collects approximately 35 cubic feet (1 m³) of air. Noble gases are separated from other components of air by cryogenic stripping and gas chromatography; separate fractions of krypton and xenon are analyzed by liquid scintillation spectrometry.

The tritium concentrations observed in the weekly water vapor samples collected from the NGTSN were generally below the minimum detectable concentration (MDC) of about 400 pCi/l of water. Only 11 of the 870 samples were above the MDC, with a maximum tritium-in-air concentration of 21 pCi/m³. The mean tritium-in-air concentration for all of the network stations was 0.45 pCi/m³ of

FIGURE 3-4
LOCATIONS OF OFF-SITE NOBLE GAS AND
TRITIUM SURVEILLANCE NETWORK SAMPLING STATIONS
NEVADA TEST SITE - MERCURY, NV

air. EPA-EMSL considered all detectable tritium concentrations to be representative of environmental background (Patzner et al., 1987).

Krypton-85 was detected at all of the NGTSN stations. The average krypton-85 concentrations at the individual stations ranged between 24 and 26 pCi/m³. The average concentration for the network was 25 pCi/m³ with a standard deviation of 0.5 (Patzner et al., 1987). This concentration is representative of world-wide levels of krypton-85 and is not solely related to current weapons testing at NTS. The krypton-85 present in the environment is primarily a consequence of nuclear power plant releases and fuel reprocessing activities.

Detectable levels of xenon-133 of NTS origin were observed off-site on two occasions during 1986: (1) following a drill-back operation at the NTS (March), and (2) during tunnel purging following the MIGHTY OAK event (April). Xenon-133 was detected at a sampling location in Lathrop Wells, Nevada at a concentration of 84 pCi/m³ following the drill back and at Penoyer Farms, Nevada at a concentration of 68 pCi/m³ during the tunnel purging. These concentrations are 0.02 percent and 0.01 percent respectively, of the xenon-133 concentration that would yield a dose equal to the DOE limit of 100 mrem/yr to members of the general public (Patzner et al., 1987).

3.1.3.3 Pre-shot Meteorological Monitoring and Release Pathway Prediction

As part of the pre-shot contingency planning process, predictions of radiation dispersion and radiation exposure to off-site populations are made, based on the assumption that each nuclear test shot will result in a massive release of radioactive materials (EMSL, 1984). The meteorological data required for use in the prediction are provided by the Weather Service Nuclear Support Office (WSNSO), which is part of the National Oceanic and Atmospheric Administration.

A weather observatory near the Desert Rock Airstrip routinely provides twice-daily upper-air observations of pressure, temperature, humidity, and winds aloft to altitudes of nearly 90,000 feet (27,400 meters) above mean sea level. Similar observations are taken in Yucca Flat to at least 25,000 feet (7,620 meters) above mean sea level for event support. At the Yucca Flat station, upper-air data are taken 4 to 6 hours prior to an event and again at detonation time. These data, as well as data from as many as seven additional stations surrounding the NTS, are used routinely to define air-flow patterns for each event.

In the hours preceding a scheduled event, predictions are made of the fallout dispersion pattern and the maximum radiation exposures that might occur in the event of a release of radioactive materials. An example is shown in Figure 3-5. The centerline is the predicted hotline of the fallout for a massive

release, marked with anticipated arrival times of the cloud along this hotline. The lines on either side of the hotline indicate the predicted fallout pattern. The dashed line and the dotted line crossing the dispersion pattern boundaries identify distances within which people might receive an external gamma exposure of at least 170- or 500-milliroentgens (mR), respectively. (For gamma radiation, an exposure of 1 mR is equivalent to a dose of 1 mrem.) Based on these predictions, a scheduled test would be postponed if the winds would carry any accidental release of radioactive materials in excess of established exposure guidelines into populated areas where protective actions cannot be taken.

3.1.4 Findings and Observations

3.1.4.1 Category I

None.

3.1.4.2 Category II

None

3.1.4.3 Category III

None.

3.1.4.4 Category IV

1. Three Boilers Without Required Air Operating Permits. Three boilers with rated heat inputs of 4.0 million Btu/hour or more do not have required air operating permits per Nevada Administrative Code 445.704 and 445.705. This documentation deficiency does not create any environmental degradation. The unpermitted boilers are

- NTS No. 700903 in Area 12, Building 12-30.
- NTS No. 701037 in Area 23, Building 754.
- NTS No. 701038 in Area 23, Building 754.

FIGURE 3-5

PREDICTED TRAJECTORY AND EXTERNAL GAMMA EXPOSURE
NEVADA TEST SITE - MERCURY, NV

2. Fume Hoods Exhaust Substances Considered to be Air Contaminants by the Nevada Administrative Code Without Required Certificate of Registration. Vents serving laboratory fume hoods in Building 650 (Area 23) are exhausting substances considered to be toxic or hazardous air contaminants by the state.

Eleven hoods in Health Physics laboratories and five hoods in Industrial Hygiene laboratories exhaust such materials as acid fumes, flammable gases, and solvents. Some specific materials used include

- Nitric, hydrochloric, perchloric, and hydrofluoric acids.
- Benzene, toluene, and other organic solvents.
- Flammable gases including acetylene and methane.

No data were available concerning emission rates of any of these materials.

The Nevada Administrative Code (NAC) addresses the subject of toxic or hazardous air contaminants in NAC 445.717, et seq., requiring a certificate of registration and an operating permit for sources of these air contaminants. In addition, if a source emits more than 0.25 pound or 113 grams of a contaminant per 8-hour shift and exceeds the acceptable ambient-air concentration for that substance, best available control technology (BACT) is required.

While only limited amounts of chemicals are being used in the laboratory fume hoods and would therefore not require BACT, the hoods are exhausting materials considered to be toxic or hazardous without a certificate of registration or an operating permit.

3. Baghouses Used During Truck-Loading of Cement Not in Permit. A system exists to reduce emissions of cement dust during the transfer of cement from storage silos to trucks, which consists of a small baghouse. A second baghouse (in parallel) is planned to allow simultaneous filling of two trucks. Although an air-quality operating permit exists for the cement batch plant that covers emission control devices that serve the silo vents, the baghouses used and planned during truck-loading are not covered by a Certificate of Registration or an air-quality operating permit.
4. Disposal of High Explosives and Containers in Area 11 Without Required State Approval. Once or twice per year, accumulations of unwanted, high-explosive materials are disposed of in Area 11 by detonating the materials in an open crater. This activity has been practiced in the

past for the purpose of elimination of hazards without prior approval by the State (as required by Regulation No. 445.753). In addition, paper and cardboard containers are accumulated and burned in this area without prior state approval. RCRA aspects of this disposal practice are discussed in Section 4.1.3.2, Finding No. 2.

5. Unpermitted Open Burning in Area 27. Waste paper and paper towels saturated with solvents, among other materials, are being disposed of by burning in a wire cage at Area 27. No open-burning permit exists for this activity. RCRA aspects of this disposal are discussed in Section 4.1.3.2, Finding No. 2. There are no records of quantities or frequency of disposal.
6. Uncalibrated Gas-Flow Meters Being Used in On-Site Sampling of Airborne Radionuclides. Because the Rockwell liquified petroleum gas (LPG) meters being used at 47 sampling stations for particulate and gaseous radionuclides in ambient air have not been calibrated, the potential exists for errors in the reported concentrations of radionuclides at on-site sampling locations. However, measured concentrations have been less than one percent of the DOE-derived concentration guidelines. It is therefore unlikely that any errors due to the lack of calibration would result in an undetected exceedance.
7. Particulate Emission Rates from Stemming Activities are Unknown. Downhole stemming activities involve the use of dry aggregate materials and a fines fraction, both of which emit copious dust clouds when handled. The stemming facilities function under air quality operating permits that require compliance with the Nevada Administrative Code. In 445.732 of those regulations, a formula is given that provides for calculation of an allowable particulate emission rate based on process weight rate.
8. Particulate Emissions from Unpaved Roads. Although an extensive watering activity is practiced to minimize fugitive dust emissions from unpaved surfaces in areas with high levels of vehicular activity, no program exists to prevent or minimize fugitive dust emissions from the many miles of unpaved roads at the site. State Regulation 445.734 requires application of measures to prevent particulate matter from becoming airborne.

3.2 Soils

Soils are important both because of their role as a supporting medium and source of nutrition for plants and because of their physical and chemical properties in retarding contaminant migration. The primary concern with regard to soils at the Nevada Test Site (NTS) has been the deposition onto surface soils of airborne radionuclides from various kinds of above-ground testing. Radionuclides present in soil can be incorporated metabolically into plants through root uptake. Radionuclides or other contaminants deposited on leaf surfaces can be taken up by the plant, or can be transferred directly to animals that consume contaminated foliage. Deposition on leaf surfaces can occur through wind resuspension of contaminated soils, by splattering of soil on the plant during rains, and through direct contact between the soil surface and plant surfaces. Most transuranic nuclides form particles or associate with particles, so that mechanisms that move solid particles are most relevant to migration of plutonium contamination. However, other radionuclides may be more influenced by physical and chemical properties of soil, such as ion exchange and adsorption of liquids and gases.

3.2.1 Background Environmental Information

The Nevada Test Site (NTS) can be divided roughly into two major areas--the mesas in the northwestern portion and the flats in the eastern and southern portions. Soils in the mesa or upland areas developed in residuum that weathered in place from the bedrock. In the eastern and southern parts of NTS, the small mountain ranges and ridges that separate the various flats and valleys from each other are topped either by bare rock or by thin residual soil over fractured bedrock. The slopes of these ranges are covered by alluvial fans, which are cone-shaped deposits of sand, gravel, and fine material dropped by intermittent streams when these streams reach the valley floor. The coarsest materials are found near the mountain ranges. Finer textured sediments are found in the valleys and flats. Soils on the slopes and flats developed in these sediments, which were washed from the surrounding mountains and laid down by water. In some places, these sediments were reworked by wind to form sand dunes. The sediments were derived mainly from tuff and limestone. In some parts of the site, sediments also include material from quartzite, shale, dolomite, and granite. Where a high proportion of limestone is present, the soils have high carbonate levels. Soils in general are alkaline (pH 8-9).

Soil-forming processes that produce soil horizons operate slowly under conditions of low moisture and high temperature. Soil horizons are layer-like zones within the soil, approximately parallel to the ground surface. A soil profile is a vertical section of the soil through all its horizons, extending into the parent material. These horizons are formed by weathering and alteration processes at or

near the ground surface. These processes include the downward percolation of water, which may carry inorganic and organic material in solution or suspension; swelling and shrinking in response to wetting and drying or freezing and thawing; chemical reactions leading to the formation of clay minerals or iron and manganese oxides; and mechanical mixing (Case et al., 1984). Soils on the NTS can be classified into two broad categories: Entisols (recent soils) and Aridisols (dry soils). Entisols have a deep layer of loose, incoherent rock material that shows no profile development (Kearl, 1982). Aridisols are desert soils that have a light-colored surface horizon which is usually underlain by a layer of caliche. Caliche is a natural concrete consisting of gravel, sand, or desert debris cemented by calcium carbonate. It is formed by the near-surface crystallization of calcite from solutions containing dissolved calcium carbonate. Calcium carbonate is leached from the surface soil and redeposited a few feet down, where downward migration of water is balanced by upward movement due to evaporation. Deposition probably occurs during upward movement of water, since rock fragments in soil are usually coated with calcium carbonate on their undersides. The material below the caliche is partially weathered parent material, which is transitional to unaltered parent material. The term hardpan is also used for a hardened or cemented soil layer. Caliche is a calcium carbonate hardpan. For a hardpan in general, the soil material may be sandy or clayey, and it may be cemented by iron oxide, silica, calcium carbonate, or other substances. Both calcium carbonate and silica cements are found at the NTS.

Sometimes the soil above the caliche layer is removed by erosion, leaving the cemented material exposed at the surface. These cemented layers, which have become exposed at the surface, (duricrusts) are not to be confused with desert pavement or erosion pavement. Desert pavement is a layer of coarse fragments of gravel or stones on the ground surface, which remains after the fine particles are removed by erosion. No chemical deposition or cementation is involved in the formation of desert pavement.

The vegetative cover at the NTS is composed of desert shrubs and grasses, typical of the cover found in semi-arid areas of the Southwest. This vegetative cover contributes little organic matter to the soil. Organic soil components are plant, animal, and microorganism remnants in various stages of decomposition. These organic components greatly affect soil fertility and production. Because of the extremely arid climate at the NTS, the organic fraction of the soil is small. The vegetative cover also affords little protection against erosion and provides little shade for the soil. High temperature, limited shade, and low organic matter content produce an adverse habitat for soil microorganisms; thus, there is little microbial activity during much of the year (Leavitt and Mason, 1971).

Soils tend to be well drained, although drainage through the hardpan, where present, is very slow. Permeability is moderately rapid to rapid. Deep soil water movement (below the depth of active

evaporation and transpiration) is possible in areas such as mesa tops, fractured bedrock surfaces, wash bottoms, and craters. In each of these areas, precipitation can be concentrated in ponds, channels, or fractures. The surface is highly permeable, and therefore water can move downward rapidly (Tyler, 1987a). Water that permeates beneath the zone of evapotranspiration can move through the unsaturated zone, picking up contaminants as it goes, and can eventually reach the groundwater table.

Adsorption and ion exchange in soil systems are the principal mechanisms that retard the migration of radioactive and hazardous wastes. Adsorption is the adhesion of molecules of gases, or of ions or molecules in solutions, to the surface of solids in contact with them. Ion exchange is a reversible interchange of one kind of ion held on an insoluble solid with another ion present in a solution surrounding the solid. The most common example of ion exchange is water softening, in which calcium ions are removed from water by exchange with sodium ions attached to a natural or synthetic solid material.

Soils act as solid materials to which positively charged ions (cations) can be attached. Soils all have negative charges, which are derived from both organic and inorganic constituents. The negative charges in soil organic matter result from the presence of carboxyl, phenolic, and amino groups. The contribution of soil organic matter to the total negative charge is minor for NTS soils, since the organic content of these soils is very low. The inorganic contribution to negative charge results from ionization of hydroxyl groups and from the substitution of one atom for another atom of similar size but lower valence in the mineral crystal structure, such as the substitution of Al^{3+} for Si^{4+} . The total of these negative charges per given weight of a particular soil is called the Cation Exchange Capacity (CEC) of that soil. On each of these negatively charged sites an exchangeable cation is absorbed and is subject to interchange with cations in water migrating through the soil. This reaction continues until equilibrium is reached between the cations in the soil water phase and the exchange site on the soil solid phase; however, the cation exchange process is dynamic and the equilibrium condition is always changing.

The CEC is given in milliequivalents (meq)/100 grams of dry soil, a soil size fraction, or a mineral (a milliequivalent is a unit of chemical combining power). Most of the CEC of a soil is due to the fine-grained fractions (silt and clay) of that soil. Silt particles are 0.004 to 0.063 millimeters in size and clay particles are less than 0.004 millimeters. The term "clay" may refer either to a size fraction or to a mineral type, although the clay size fraction often contains clay minerals. Clay minerals have sheetlike crystal structures (like a deck of cards) and can expand by picking up water molecules between the structural sheets or layers. Both the ability of clay minerals to pick up water and their relatively high CECs are important in contaminant retardation. For example, the clay mineral

montmorillonite, which is used in drilling muds, has a high CEC of 80-120 meq/100 grams and can thus immobilize ionic constituents.

The mineral clinoptilolite has an even higher CEC of 170-220 meq/100 grams (Kautsky, 1984). Clinoptilolite is not a clay mineral but a zeolite. Zeolites, which are relatively common at the NTS, have a crystal structure which is a three-dimensional framework rather than a sheetlike structure. The framework structure of zeolites contains open channels that provide easy access to the interior of the crystal and allow the entry of water molecules. Zeolites have a high internal surface area with an abundance of sites for cation attachment. Some zeolites are used commercially as natural water softeners. Zeolites vary in chemical composition, channel dimensions, and ability to exchange cations of various sizes. Clinoptilolite has the property of preferential sorption of cesium, a useful property at the NTS where the fission product cesium-137 is present in cavities and chimneys from nuclear detonations and in radioactive waste disposed of at the Radioactive Waste Management Site in Area 5.

Soils at any location throughout the world will contain radionuclides from natural sources as well as fallout from past atmospheric nuclear weapons tests. The natural radionuclides are primarily uranium, thorium, and members of their decay chains. Other natural radionuclides, such as potassium-40, carbon-14, and beryllium-7, will also be found in soils. Background levels of fallout radionuclides have been decreasing since the United States and the Soviet Union ceased atmospheric nuclear testing following the signing of a 1963 treaty that banned atmospheric nuclear tests. Most of the relatively short-lived radionuclides (half-life ≤ 5 years) originally found in fallout have decayed to levels not readily detectable. Fallout radionuclides currently found in soils include strontium-90, cesium-137, cobalt-60, and the plutonium isotopes. Because of the atmospheric testing that had occurred at the NTS, large areas of the site are contaminated with radionuclides in excess of worldwide fallout levels. This contamination is discussed in Sections 3.2.2 and 3.2.3.

There are no regulations that limit the concentrations of radionuclides in soils. However, there is some guidance available from the Nuclear Regulatory Commission (NRC) and the Environmental Protection Agency (EPA). DOE has established guidelines for residual radioactivity at Formerly Utilized Sites Remedial Action Program (FUSRAP) sites and Remote Surplus Facilities Management Program (SFMP) sites (DOE, 1985). The guidelines specify concentrations for thorium-232, thorium-230, radium-228, and radium-226 of 5 pCi/g averaged over the first 15 centimeters of soil below the surface and 15 pCi/g averaged over 15-centimeter-thick layers of soil more than 15 centimeters below the surface. These guidelines take into account the in-growth of the radioactive decay products. For other radionuclides or mixtures, the soil concentration guidelines

must be derived, on a site-specific basis, from a basic dose limit of 100 mrem/year to an individual, from all pathways (e.g., ingestion, inhalation, and direct exposure).

In 1977, the EPA released a guidance document in draft form, "Proposed Guidance on Dose Limits for Persons Exposed to Transuranium Elements in the General Environment" (EPA, 1977). The guidance provides a screening level for transuranics in soil ($0.2 \mu\text{Ci}/\text{m}^2$). These screening levels are values that indicate a need for further testing to determine whether dose limits are exceeded in areas having uncontrolled access. This is equivalent to a plutonium concentration in soils of $13.3 \text{ pCi}/\text{g}$, assuming a 1 centimeter sampling depth and a soil density of $1.5 \text{ g}/\text{cm}^3$.

3.2.2 General Description of Pollution Sources/Controls

3.2.2.1 Surface Soil Contamination

Surface soils on large portions of NTS have been contaminated with radionuclides and possibly beryllium by weapons tests conducted at or near the surface. The first nuclear detonation at the NTS was conducted on January 27, 1951. This was a 1-kiloton device dropped from an airplane into the Frenchman Flat area. From 1951 through 1985, 119 announced atmospheric nuclear tests were conducted at the NTS. Thirty-one of these tests were so-called safety experiments in which conventional explosives were detonated in proximity to a nuclear device. These experiments were conducted to verify that weapon designs were adequate to prevent accidental fission reactions, and generally had little or no nuclear yield, but resulted in the deposition of plutonium over wide areas of the NTS. Atmospheric safety experiments were conducted in Area 11 at a location known as "Plutonium Valley" where there were 4 test sites, Area 5 at the GMX site, Area 8 at CERES and OBERON sites, Area 13 at the Project 59 site, and off-site on the Tonopah Test Range (TTR) of the Nellis Air Force Range. Area 13 is located north of Area 15 within the Nellis Air Force Range and is no longer included on NTS maps; however, the area is monitored by NTS personnel, who also maintain warning signs and fences. The TTR was used for four safety experiments conducted by Sandia National Laboratory (SNL); DOUBLE TRACK, and CLEAN SLATE 1, 2, and 3. The TTR contamination will be addressed in a separate report as a part of the SNL Environmental Survey.

In addition to the safety experiments, during the same period there were 88 weapons-related or weapons-effects tests that produced nuclear fission reactions. These included 1 at the surface, 1 rocket, 1 airburst fired from a cannon, 2 cratering experiments, 5 in tunnels, 19 dropped from aircraft, 23 suspended from balloons, and 36 at the top of steel or wooden towers. Those tests conducted above or near the surface resulted in contamination of soils with fission products, activation products, and uranium. In 1958, nuclear testing was suspended by President Eisenhower,

but was resumed in 1961. All but 5 of the weapons tests conducted since 1961 have been deep underground. Four of these were at or near the surface, and one was a cratering test. In addition, six cratering tests were conducted as a part of the Plowshare Program, a program to develop peaceful uses of nuclear explosions. Atmospheric weapons tests were conducted in or have contributed to soil contamination in Areas 1, 2, 3, 4, 5, 7, 8, 9, 10, 12, 15, 16, 18, 19, 20, and 30. Since the signing of the Limited Test Ban Treaty on August 15, 1963, all weapons tests have been conducted underground.

During the 1960s and early 1970s, facilities in Area 25 and Area 26 were used to test nuclear reactors for use as rocket engines. On two occasions, explosions of test engines resulted in contamination of the surrounding soils. One explosion occurred near Test Cell C in Area 25. This explosion was initiated as a part of the testing program. NTS personnel stated that the area where the explosion took place remains contaminated and is inventoried by NTS as a radiation exclusion (RADEX) area (Shugart, 1987). In addition, an accidental explosion occurred in Test Cell A. This explosion resulted in contamination within the test cell and some contamination of nearby soil. Test Cell A and the adjacent area are considered RADEX areas.

It is anticipated that some portions of the NTS may be contaminated with beryllium. Because of its desirable nuclear properties, beryllium is often used in the construction of nuclear weapons. Consequently, there will be a potential for beryllium contamination in any area that has been used for atmospheric weapons testing, including nuclear detonation, safety experiments, and nuclear-rocket engine explosion experiments. Beryllium is considered to be a potential carcinogen. This contamination is being addressed by the Basic Environmental Compliance and Monitoring Program (BECAMP). At the time of the Environmental Survey, NVO was conducting a records search to identify potential areas of beryllium contamination. A program to characterize the extent of the contamination will be developed on the basis of the results of this survey. In addition, NVO has conducted soil sampling for beryllium in Area 5 at the location of the SUGARBUNKER safety experiment (Bingham, 1987a). At the time of the Environmental Survey, there were no data available on the level of beryllium contamination at the NTS.

The primary controls applied to the contaminated soils are posting of the areas and control of access. Access to the entire NTS is restricted. In addition, all areas with alpha contamination or radiation levels in excess of 5 millirem/hour have been inventoried as RADEX areas, fenced, and posted with warning signs by the NTS Radsafe Department. NTS personnel stated that these areas are surveyed annually to verify that signs and fences are intact and that contamination is not observable outside of the controlled areas (Shugart, 1987). Warning signs define the nature of the danger (e.g.,

contaminated area, or radiation area) and state that access is prohibited without prior notification of the Radsafe Department.

In 1970, the Nevada Operations Office established the Nevada Applied Ecology Group (NAEG) in response to the National Environmental Policy Act. The emphasis of the NAEG was on the study of radioecology, particularly the radioecology of plutonium. The NAEG included a number of scientific organizations with expertise in soils, biology, physics, chemistry, radiochemistry, and related disciplines. Specific objectives of the NAEG included identification of contaminated areas, determination of the concentration of radionuclides in ecosystem components, quantification of rates of radionuclide movement among ecosystem components, and the evaluation of the potential human radiological dose from the plutonium and other radionuclides. The NAEG was terminated at the end of fiscal year 1986. There have been numerous reports published on the NAEG studies (e.g., NAEG, 1987, 1982, 1978, 1977, 1976). At the time of the Environmental Survey, summaries of the overall program effort were being prepared for publication. Dr. Lynn Anspaugh of Lawrence Livermore National Laboratory discussed the NAEG studies with the Environmental Survey team and provided the team with an understanding of key elements of the studies. In addition, the Survey reviewed selected publications of the NAEG. Some of the major accomplishments and conclusions of the NAEG include the following:

- Quantification of plutonium contamination in Areas 5, 11, and 13 and at the Tonopah Test Range (Gilbert et al., 1975; Gilbert, 1977).
- Developed a general model for the resuspension of contaminated soils (Anspaugh et al., 1975; Shinn et al., 1986).
- Developed a comprehensive model for plutonium dose prediction (Martin and Bloom, 1980; Kercher and Anspaugh, 1984).
- Performed a successful cleanup test of plutonium-contaminated soils in Area 11 using a vacuum method of soil removal (Orcutt, 1982).
- Concluded that the biological availability of plutonium to small mammals is low (Anspaugh, 1987).
- Concluded that the rate of movement of plutonium off the NTS is extremely slow (Anspaugh, 1987).

Another program to characterize contamination on the NTS is the Radionuclide Inventory and Distribution Program (RIDP). The RIDP was originally an element of the NAEG for the study of plutonium contamination. As the scope of the study expanded, it was separated from the NAEG. The objective of the RIDP was to provide a complete inventory of the radionuclides of NTS origin in the NTS surface soil and to provide isopleth maps that define areas and levels of contamination. The stated goal was to provide a final inventory that is known with 95 percent confidence to within at least a factor of 2. Although the RIDP was scheduled for completion during fiscal year 1987, publication of the final reports was not completed. The RIDP made use of aerial radiation surveys, in-situ gamma spectrometry, and soil analysis. Radionuclides of major interest included cobalt-60; strontium-90/yttrium-90; cesium-137; europium-152, -154, and -155; plutonium-238, -239, and -240; and americium-241. At the time of the Survey, reports had been published on the Galileo Area (Area 1) (McArthur and Kordas, 1983); Areas 2 and 4 (McArthur and Kordas, 1985); and Areas 3, 7, 8, 9, and 10 (McArthur and Mead, 1987a). A draft report on Areas 18 and 20 was available to the Survey team (McArthur and Mead, 1987b). At the time of the Survey, there were plans to prepare reports for Areas 5, 11, 12, 15, 16, 17, 18, 19, 25, 26, and 30, but no draft reports or data were available to the Survey team. Data from the RIDP are discussed in Section 3.2.3 of this report.

The study and monitoring of soil contamination throughout the NTS will continue under the Basic Environmental Compliance and Monitoring Program (BECAMP). BECAMP was initiated by NVO in 1987. Its primary objective was the assessment of long-term changes in the radiological and ecological condition of the NTS. The following objectives have been developed for BECAMP (BECAMP, undated):

- Maintain and enhance knowledge of radionuclide inventory and study the movement of surface and subsurface contaminants on and around the NTS.
- Maintain and update human dose-assessment models for the NTS and its environs and periodically conduct field studies to test the predictions of the models.
- Maintain and update an understanding of the spatial distribution and changes over time of the flora and fauna on the NTS.
- Provide a major, thematic, peer-reviewed publication yearly to address important issues related to the potential environmental impacts of past, present, and future activities on the NTS.
- Comply with applicable environmental laws.

FY1987 BECAMP activities were primarily related to program planning. No data reports on BECAMP activities were available at the time of the Survey.

3.2.2.2 Subsurface Soil Contamination from Underground Nuclear Testing

Underground nuclear testing at the NTS includes both downhole and tunnel shots, as described in Section 2.2.1. All tunnel shots and many of the downhole tests occur in the unsaturated zone (subsurface soil and rock above the water table). The primary source of radioactivity at the NTS is the combination of weapon materials, fission products, and neutron-induced radioactivity generated at each underground nuclear test location (ERDA, 1977). Such tests will continue to create and add to the large, buried, radioactive waste inventory that requires long-term surveillance and restricted access. It is probable that this waste is actually mixed (radioactive and hazardous) waste because of the lead shielding used for the instrumentation in such tests. Since this waste is uncontained, except for that fraction incorporated into glass, it is actually released and available for migration. (See Section 3.4.2.1 for a description of what happens in the subsurface environment as a result of an underground nuclear detonation.) Subsurface releases that occur as a result of the underground nuclear testing program are subject to regulation under Section 120 of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) (Bingham, 1987b).

The mobility of the waste at each site is dependent mainly upon groundwater transport; it is unlikely that any of this contamination could ever reach a receptor except by the groundwater pathway. As a generalization, the amount of water available in the unsaturated zone is very small and the movement of this water through the unsaturated zone is very slow. Therefore, the contamination produced by underground nuclear tests above the water table is relatively immobile soil contamination.

The mobility of this waste can be examined in greater detail. The most mobile contaminant is the tritium produced in thermonuclear explosions, which mixes with the water released and condensed from vaporized and melted rock. This tritiated water behaves like any other groundwater. Water in the unsaturated zone moves through the spaces between soil particles (interstitially). However, interfacial tension (surface tension) in the pore spaces of unsaturated granular rocks will exceed gravitational forces until the saturation level becomes quite high. Because the interfacial forces tend to bind the water to the rock granules, it is likely that little overall motion will occur until sufficient water has moved into the pore space to increase the saturation to the level at which gravitational forces exceed the interfacial tension. In the region of an underground nuclear explosion in the unsaturated zone, little water is available relative to the total volume of unsaturated pore space.

Thus, it is unlikely that enough rock would be saturated to permit significant flow of water. For this reason, one would not expect movement of tritiated water in the unsaturated zone much beyond the region in which the forces of the explosion placed it (Crow, 1976).

The amount of water available for filling pore spaces depends on the amount of infiltration of precipitation. Infiltration of surface runoff caught in subsidence craters will be somewhat greater than through the undisturbed preshot soil because of the increased permeability of the rubble beneath the crater. However, there is some evidence that infiltration into and around the nuclear cavity will be slowed by a layer of clay, which accumulates in the bottom of many subsidence craters; by the explosion-compacted, glassy envelope surrounding the cavity itself; and, under favorable geologic conditions, by the presence of low-permeability rocks that do not maintain open fractures. In addition, the zeolitized zones within many of the volcanic rock units will retard contaminant migration because of high ion-exchange capacities and large surface areas for adsorption. Only tritium as tritiated water can be expected to move through the system at the same rate as the groundwater, but even then its concentration will be reduced by radioactive decay (with a half-life of 12.3 years), dispersion, and dilution during migration. Any recharge reaching the water table, therefore, may carry tritium and very dilute concentrations of other radionuclides; however, the process will take hundred of years, and the contaminants must traverse a long and circuitous path to reach off-site areas (ERDA, 1977).

3.2.2.3 Near-Surface Soil Contamination from Waste Disposal Practices

Near-surface soil contamination from waste disposal practices may extend to unknown depths at both active and inactive sites. These suspected sources of soil contamination are listed here by type of source and by area. Sewage lagoons that apparently receive only sanitary wastes are not included in this section because they are not considered to be sources of soil contamination. They are discussed in Sections 3.3.2.2, and 3.3.3.1. Burial sites and solid waste dumps with no liquid phase to promote contaminant migration are also not included because such sites are unlikely to produce soil contamination in the absence of major climatic change to less arid conditions. Various kinds of active and inactive waste disposal sites containing immobile waste are discussed in Sections 4.1.2.1 and 4.5.2, but the presence of immobile waste in an intentional burial site is not considered a source of soil contamination.

Probable sources of soil contamination are as follows:

1. Direct discharges to the land surface or overflow from wastewater ponds and sumps create probable soil contamination and the potential for transport of contamination by storm runoff or flash flooding. Such areas include
 - The ditch under the discharge pipe from the Area 12 Industrial Wastewater Sump. The sump receives flow from the Fleet Operations Buildings. The sump itself is a source of soil contamination by infiltration, although transport of contaminated soil by storm runoff or wind will not occur for the area beneath the sump (see Sections 4.1.2.1.1 and 3.3.4.2).
 - Three discharges from unidentified sources at the Area 23 Fleet Operations Facilities that enter the ditch on the east side of the Mercury Highway Bypass.
 - Disposal of potentially hazardous steam jenny sump waters, including pesticide rinsewaters, in the Area 23 sewage trenches (see Section 4.1.2.1.1).
 - The ditch north of Building A-5 at the EG&G North Las Vegas Facility which receives runoff from an outdoor lead storage area (see Section 3.3.2.5).
 - Discharges of wash water from mixing trucks for epoxy-based stemming materials (see Section 4.1.2.1.1).
 - Discharge of small amounts of tritiated water to the land surface at Well UE-7ns, the BOURBON Radionuclide Migration study site (see Section 3.4.2.1).
2. Discharges of wastewater into shallow injection wells and pits are creating probable soil contamination and the potential for groundwater contamination. Such wells and pits include
 - A wastewater disposal pit at the Area 1 Subdock Steam Cleaning Pad (see Section 3.3.4.2).
 - Two wastewater disposal holes at the REECO Bit Cutter Rebuild Shop and a sump at the LLNL post-shot facility in the Area 2 support facilities (see Section 4.1.2.1.1).
 - A water disposal hole that receives water from the Steam Cleaning Control Pad sump at the Area 3 post-shot facility (see Section 3.3.4.2). Water that collects in the Blow-off

Preventer Servicing Cellars at this same facility is pumped occasionally into a casing that is another probable disposal hole.

- An inactive wastewater disposal well at the Core Storage Yard in Area 3 (see Section 4.5.2.15).
 - The J-6 classified waste disposal hole in Area 3, which is known to be used for wash water from contaminated drilling equipment (see Section 4.1.2.1.2). Hole J-11, also in Area 3, may be used similarly.
3. Wastewater discharges into sumps, lagoons, and ponds may be causing contaminants to build up in subsurface soil, and provide a source of recharge for potential groundwater contamination. (The sewage lagoons included here may be receiving wastes other than sanitary wastes.) These surface impoundments include
- The wastewater pit at the Area 2 Photo Skid (see Section 3.3.4.2).
 - The sewage lagoons south of CP-1 and west of Mercury Highway in Area 6. These lagoons are receiving effluent from unknown sources (see Section 3.3.4.2).
 - Sewage Lagoons I and II and the domestic sewage lagoon at Yucca Lake in Area 6 (see Section 3.3.4.2). These lagoons should receive discharges only from sanitary systems, but it is possible that cross-connections exist or that wastes other than sanitary wastes are being disposed of into sanitary sinks and drains.
 - Steam Cleaning Effluent Pond I at the Building 6-623 Machine and Welding Shop and Steam Cleaning Effluent Pond II at the Building 6-800 Heavy Duty Repair Shop in Area 6 (see Section 4.1.2.1.1).
 - The Decontamination Pond in Area 6 (see Sections 4.1.2.1.2 and 4.1.2.1.3).
 - The Well 3 Yard truck washing drain pit in Area 6 (see Section 3.3.4.2).
 - The sewage pit at the Area 11 LLNL Technical Facilities (see Section 3.3.4.2).
 - The Area 12 Industrial Wastewater Sump mentioned previously (see Section 4.1.2.1.1).

- The sewage lagoons in Area 23, which receive flows from the Building 650 Industrial Hygiene Laboratory. This laboratory disposes of relatively small quantities of analytical chemicals into laboratory sinks (see also Section 4.1.2.1.1).

- The sewage lagoons south of Test Cell C in Area 25 (see Section 3.3.4.2).

- An inactive seepage/evaporation pond that received tritium-contaminated water pumped from Well UE-2ce, the NASH Radionuclide Migration study site (see Section 3.4.2.1).

4. Wastewater discharges into leachfields, both active and inactive, create probable soil contamination. The NTS Environmental Compliance Atlas lists many wastewater disposal sites as both evaporation ponds or sumps and as leachfields. Some are shown on maps as evaporation ponds or lagoons.

Data are available from soil sampling at some of these sites so that they can be categorized into (a) known sources of soil contamination; (b) sites for which existing data indicate no or negligible contamination; and (c) probable sources for which no data exist.

The known sources of soil contamination are

- The Reactor Maintenance, Assembly, and Disassembly Building (R-MAD) inactive radwaste leachfield in Area 25 (a CERCLA site). (All listed CERCLA sites on the NTS were identified as such under the CERCLA Phase I Assessment required by DOE Order 5480.14.)
- The Test Cell C inactive leachfield in Area 25 (a CERCLA site).
- 401 MAD Building inactive leachfield from the Tory reactor project in Area 26 (a CERCLA site).

The sites for which existing data indicate no or negligible contamination are

- The CP-2 inactive decontamination leachfield in Area 6 (a CERCLA site). Building CP-2 was a laundry operation. The laundry and a decontamination pad discharged water first to this leachfield and later to a lagoon which was decontaminated and removed. Further information on these operations is presented in Section 4.5.2.12.

- The Engine Maintenance, Assembly, and Disassembly Building (E-MAD) inactive radwaste leachfield in Area 23 (a CERCLA site).
- Test Cell A inactive leachfield in Area 25 (a CERCLA site).

Probable sources of soil contamination for which no data exist include

- Inactive sumps at the abandoned Area 3 Subdock Complex (see Section 4.5.2.14).
- The BJY (BJ Wye) inactive decontamination pad sump at the junction of Areas 1, 3, 4, and 7 (see Section 4.5.2.11).
- A roped-off area near an empty tank at the U9y crater site in Area 9 (see Section 4.5.2.16).
- The EPA farm Radsafe waste sump in Area 15 (see Section 4.5.2.13).
- The Building 155 inactive leachfield in Area 23, which may have received wastewater from the former industrial hygiene laboratory (see Section 4.5.2.7).
- The Building 650 leachfield in Area 23 that receives flows from the radiochemistry laboratories, the decontamination shower, the photographic laboratory, and the silver recovery unit. Chlorinated solvents, acids, and caustics are disposed of into laboratory sinks (see Sections 4.1.2.1.2 and 4.1.2.1.3).

5. Leaks and discharges of materials other than wastewater create known soil contamination. These sites include

- Discharges of drilling mud contaminated with radionuclides into craters U2bu and U3ai-be (see Section 4.1.2.1.2). These craters may also receive decontamination rinsewater. Although this material may be a mixed waste, it is possible that no actual migration of contaminants into the soil occurs. Disposal of low-permeability drilling muds in crater bottoms has been suggested as a means of reducing infiltration of precipitation and runoff into craters and chimneys and thus retarding radionuclide transport from detonation cavities into groundwater (Tyler, 1987a). Ponding and evaporation of decontamination rinsewater over this low-permeability barrier would presumably occur under these conditions rather than infiltration into soil. The same conditions also occur at the mud plant disposal crater U3ag, which is used for uncontaminated drilling mud

disposal and at the inactive crater U9y which has been used for disposal of contaminated drilling mud (see Sections 4.1.2.1.2 and 4.1.2.1.4).

- Discharge of cutting oils onto the land surface at the Area 6 Machine and Welding Shop (Bldg. 6-623) (see Section 4.1.2.1.1).
- The December 1986 leak of Jet-A fuel from an underground storage tank at the Desert Rock Airstrip in Area 22 (see Section 4.5.2.9).
- The Hazardous Waste Landfill in Area 23, used primarily for disposal of uncontained liquids (see Section 4.1.2.1.1).

6. "Burial" sites in which contaminated material is not covered but remains at the surface can cause soil contamination by resuspension. Such sites include two inactive contaminated waste dumps (CWD), one at R-MAD in Area 25 and CWD No. 2 in Area 11 (see Sections 3.2.3.4 and 4.5.2.3).

3.2.3 Environmental Monitoring Program

3.2.3.1 Soil Contamination Characterization Projects

NAEG

As a part of the NAEG, plutonium concentrations in soil were studied at various safety-experiment sites on the Nevada Test Site, the Tonopah Test Range and the Nellis Air Force Range. The Tonopah Test Range contamination is not within the scope of the NTS Survey and will not be discussed here. The Nellis Air Force Range contamination is in an area adjacent to the NTS that is referred to as Area 13; this area will be discussed. The contamination within the current boundaries of the NTS is in Area 11 (Plutonium Valley) and Area 5 (GMX Site). Estimates of the plutonium inventories have been prepared, and areas of contamination in the study areas have been defined (Gilbert et al., 1975 and Gilbert, 1977). The estimates were obtained by dividing each study area into activity strata on the basis of field radiation-level surveys, analyzing random samples for plutonium-239 and -240 concentrations to obtain an estimated average activity concentration for each stratum, and multiplying these concentrations by the areas of the respective strata.

Table 3-5 presents the estimated plutonium contamination levels within study areas of the NTS. The Area 11 contamination resulted from four separate test sites: A, B, C, and D. Portions of the C and

TABLE 3-5

**PLUTONIUM CONTAMINATION AT NAEG STUDY SITES
NEVADA TEST SITE, MERCURY, NEVADA**

AREA 5

Site	Strata(1)	Size of Area (Square Meters)	Contamination Mean $\pm$ S.E. ($\mu\text{Ci}/\text{m}^2$)	Estimated Inventory $\pm$ S.E. (Curies)	Estimated 95% C.L. on Inventory (Curies)	
					Lower	Upper
GMX	1	111,300	3.1 ± 0.66	0.35 ± 0.073	0.20	0.50
	2	8,400	42 ± 9.1	0.35 ± 0.076	0.20	0.50
	3	800	270 ± 64	0.22 ± 0.051	0.11	0.33
	4	1,000	530 ± 150	0.53 ± 0.15	0.22	0.84
	5	3,800	4.6 ± 1.6	0.02 ± 0.006	0.007	0.03
TOTAL		125,300		1.5 ± 0.19	1.1	1.9

AREA 11

<5,000 cpm Region	1	4,672,000	0.97 ± 0.30	4.5 ± 1.4	1.7	7.3
CD Overlap	6	62,200	12 ± 5.2	0.75 ± 0.32	-0.07	1.6
B Site	2	8,200	30 ± 18	0.25 ± 0.15	-0.08	0.58
	3	6,000	220 ± 55	1.3 ± 0.33	0.59	2.0
	4	3,300	$1,400 \pm 300$	4.6 ± 0.99	2.6	6.7
Total		17,500		6.2 ± 1.1	4.0	8.4
C Site	2	16,400	34 ± 22	0.56 ± 0.36	-0.23	1.4
	3	5,600	88 ± 25	0.49 ± 0.14	0.17	0.81
	4	3,500	$1,400 \pm 390$	4.9 ± 1.4	1.9	7.9
	5	300	$6,200 \pm 2,800$	1.9 ± 0.84	-0.26	4.1
Total		25,800		7.8 ± 1.7	4.4	11.2
D Site	2	32,300	46 ± 9.5	1.5 ± 0.31	0.80	2.2
	3	13,300	220 ± 86	2.9 ± 1.1	0.48	5.3
	4	4,900	990 ± 370	4.9 ± 1.8	1.1	8.7
	5	2,900	$2,700 \pm 840$	7.8 ± 2.4	2.6	13
Total		53,400		17.1 ± 3.2	11	24
TOTAL		4,830,900		36 ± 4	28	44

TABLE 3-5
PLUTONIUM CONTAMINATION AT NAEG STUDY SITES
NEVADA TEST SITE, MERCURY, NEVADA
PAGE TWO

AREA 13

Site	Strata ⁽¹⁾	Size of Area (Square Meters)	Contamination Mean $\pm$ S.E. ($\mu\text{Ci}/\text{m}^2$)	Estimated Inventory $\pm$ S.E. (Curies)	Estimated 95% C.L. on Inventory (Curies)	
					Lower	Upper
Project 57	1	1,245,000	1.9 ± 0.34	2.4 ± 0.42	1.6	3.2
	2	2,547,000	5.8 ± 1.4	15 ± 3.6	7.7	22
	3	108,000	23 ± 4.3	2.5 ± 0.46	1.5	3.5
	4	74,000	54 ± 8.8	4.0 ± 0.65	2.6	5.4
	5	19,000	110 ± 19	2.1 ± 0.36	1.3	2.9
	6	24,000	820 ± 340	20 ± 8.2	3.5	37
TOTAL		4,017,000		46 ± 9.0	28	64

Source: Gilbert et al., 1975; Gilbert, 1977

(1) For each area, the activity strata are defined as follows:

Strata	Radiation Level ($\times 10^3$ cpm)		
	Area 5	Area 11	Area 13
1	0.5-5	< 5	0-1
2	5-25	5-25	1-5
3	25-50	25-100	5-10
4	> 50	100-500	10-25
5	0-50	> 500	25-50
6	-	5-10	> 50

S.E. = Standard Error

D sites overlap and the contamination within those areas is combined and reported as "CD Overlap." The contamination at the A site is primarily uranium-235, although the area does have some low levels of plutonium contamination. The Site A plutonium is included with the large stratum of <5,000 net counts per minute from the radiation level survey.

Activity estimates are for the top 5 centimeters of soil, and there was no attempt made to quantify any plutonium at greater depths, since plutonium is of primary concern in surface soils, where it may be readily resuspended. The total plutonium inventories for the NTS were 1.5 ± 0.19 , 36 ± 4 , and 46 ± 90 curies per gram for sites in Areas 5, 11, and 13, respectively. The highest observed level of contamination was in Area 11 (C site) where approximately 300 m² had a mean contamination level of $6,200 \pm 2,800$ μ Ci/m². The contaminated areas ranged in size from 125,300 m² in Area 5 to 4,017,000 m² in Area 13 and 4,830,900 m² in Area 11. The inventory of uranium (of NTS origin) at Site A in Area 11 was estimated at 938 ± 274 grams of uranium-235 and $1,920 \pm 1,150$ grams of uranium-238 (Gilbert, 1977).

Aerial Surveys

EG&G Energy Measurements, Inc. (EG&G/EM) has conducted aerial radiological surveys of the NTS. The surveys are designed to measure gamma radiation emanating from both natural and man-made radionuclides in surface soils.

During 1970 and 1971, 14 areas on the NTS and adjacent off-site locations, with a total of approximately 1,000 square miles, were surveyed with fixed wing aircraft (EG&G, 1972). Coverage included all of the NTS accessible to fixed wing aircraft. For these surveys, an array of 14 sodium iodide detectors (10 cm diameter by 10 cm thick) was employed. Flight lines, spaced 0.8 kilometer apart, were flown at an altitude of 90 meters. The products of this effort were gamma ray exposure-rate maps of the surveyed area. The only areas outside the boundaries of the NTS where exposure rates were the result of radionuclides that were not naturally occurring was on the Nellis Air Force Range. Elevated exposure rates that were observed on both the NTS and Nellis were attributable to nuclear tests and to radioactive waste storage or disposal areas.

All subsequent aerial surveys have been flown with a helicopter-mounted system in order to cover a larger area of the NTS as well as to improve the sensitivity and spatial resolution for areas previously surveyed. The current detection system is comprised of an array of 20 sodium iodide detectors (12.7 cm diameter by 5 cm thick). This array, coupled with the lower altitude and lower ground speed of the helicopter, provides improved sensitivity and resolution.

The results of the individual surveys were generally reported as isopleth contour maps for gamma exposure rates, and in some cases, for radionuclide concentrations. In addition, in some areas, inventory estimates have been prepared. Table 3-6 summarizes the information addressed in the aerial survey reports. Figure 3-6 illustrates areas where the aerial surveys have detected radiation above background levels (EG&G, 1983a). All elevated radiation levels were attributable to contamination from atmospheric nuclear tests and safety experiments, nuclear rocket engine testing, and the storage or handling of radioactive materials. The highest radiation levels observed in the survey were greater than 5 mR/hour at an area approximately 2 km southwest of Test Cell C. The principal radionuclide at this location was cobalt-60. This is the area identified to the Survey team as being the location of a nuclear rocket engine explosion. The highest contamination level associated with atmospheric nuclear testing was in Area 20 near the ground-zero location for the PALANQUIN event. The maximum exposure rate in this area was in the 0.9-2 mR/hour (at 1 meter) range.

RIDP

The primary objective of the RIDP was to prepare an inventory of the radionuclides in the NTS surface soils. The project incorporates data from three sources:

- Field measurements of external exposure rate and radionuclide activities by in-situ spectrometry. These measurements provide the primary data base for the inventory calculations and distribution maps.
- Aerial surveys of external exposure rate. The results of these surveys are used as the basis for sampling plans for the field measurements.
- Soil samples. Calibration of the in-situ measurement system requires parameters such as soil density, soil attenuation, and the depth distribution of the various radionuclides in the soil. In addition, radiochemical analysis of soil samples provides information about radionuclides that do not emit gamma rays and therefore cannot be measured by in-situ spectrometry.

Such an approach was necessary because the large size of the NTS made it impractical to rely completely on the laboratory analysis of soil samples to provide the necessary data.

The program's strategy was to first identify areas of high activity from an aerial survey of external exposure rate. Sampling points for these areas were then selected, and a spectrum of the gamma

TABLE 3-6

**SUMMARY OF AERIAL SURVEY REPORT TOPICS
NEVADA TEST SITE, MERCURY, NEVADA**

NTS Area(s) Surveyed	Date of Survey	Isopleths Reported	Reference
12, 15, 17, 19	October- November 1984	Gamma exposure Cs-1137 concentrations	(EG&G, 1986)
11	January 1982	Gamma exposure ⁽¹⁾ Am-241 concentrations, Cs-137 concentrations, U-235 concentrations	(EG&G, 1983b)
18, 20	October- November 1980	Gamma exposure Cs-137 count rate, Co-60 count rate	(EG&G, 1985)
1, 2, 3, 4, 6, 7, 8, 9, 10, 12, 15, 17	August- September 1978	Gamma exposure ⁽²⁾	(EG&G, 1982)
13	December 1977	Transuranic concentrations ⁽³⁾	(EG&G, 1979a)
25, 26	September 1976	Gamma exposure	(EG&G, 1979b)

Source: Prepared by DDE Environmental Survey team.

(1) Inventory estimates for transuranics and uranium-235 were also prepared.

(2) Inventory estimates for cobalt-60, europium-152, and cesium-137 were also prepared.

(3) Inventory estimates for americium-241 and plutonium-239 and -240 were also prepared.

FIGURE 3-6

AREAS OF ELEVATED RADIATION AT THE NEVADA TEST SITE
NEVADA TEST SITE - MERCURY, NV

radiation given off by radionuclides in the soil recorded at each sampling point. Several soil samples were also collected in each area and analyzed to determine radionuclide distributions with depth in the soil and to measure radionuclides that do not emit strong gamma rays. Parameters computed from the soil measurements were used to calculate radionuclide activities from the gamma-ray spectra, and the activity data then analyzed statistically to estimate the total inventory and distribution of each radionuclide (McArthur and Kordas, 1983).

While the locations of the ground-zero points for any test can be accurately identified, the contaminated regions associated with the tests may overlap and may be observed in more than one NTS project area. Consequently, RIDP results were reported on the basis of general areas of contamination rather than identifying specific tests. At the time of the on-site portion of the survey, four reports had been published or were available to the survey team in draft form. RIDP results were reported in the form of tables of inventory estimates of radionuclides, tables of observed radionuclide concentrations, and isopleth contours of radionuclide concentrations. Table 3-7 summarizes the contents of the completed RIDP reports, the estimated total transuranic and fission product/activation product inventories, and the sizes of the contaminated areas. In general, the largest inventories of contamination were in Areas 8 and 10. Two previous safety experiments in this area account for the high levels of transuranics. Transuranic levels as high as 1.6×10^6 pCi/g of surface soils were observed in this region. In all the regions, some locations exhibited transuranic contamination in excess of the EPA screening limit for transuranics in soil of 0.2 mCi/m² (approximately 13 pCi/g). The EPA limit is only applicable to areas accessible to members of the general public and is included here for comparison only.

3.2.3.2 Routine Environmental Monitoring

There is no routine monitoring program for radionuclides in soils. However, one of the objectives of BECAMP (see Section 3.2.2) is to maintain monitoring of contaminated areas at the NTS to determine the extent to which the contamination is migrating. At the time of the on-site portion of the Survey, no data were available from BECAMP studies.

EPA-EMSL conducts biomonitoring at the NTS and nearby locations. During 1986, samples of muscle, lung, liver, kidney, blood, and bone were collected from cattle from commercial herds that graze areas northeast of the NTS. These samples were analyzed for gamma-emitters, tritium, strontium, and plutonium. In late fall, 1985, bone and kidney samples from desert bighorn sheep collected throughout southern Nevada were analyzed. These kinds of samples have been collected and analyzed for up to 20 years to determine long-term trends. During 1986, following the MIGHTY OAK test, four NTS mule deer were collected and sampled in the same manner as the cattle.

TABLE 3-7

**SUMMARY OF RIDP REPORT CONTENTS
NEVADA TEST SITE, MERCURY, NEVADA**

NTS Location	Contaminated Area (mi ²) (approximate)	Radionuclide Transuranics	Inventory (Ci) Fission/Activation Products	RIDP Reference
Area 1 (Galileo Area)	10	0.7	30	McArthur and Kordas, 1983.
Areas 2 and 4	22	77	156	McArthur and Kordas, 1985.
Areas 3, 7 and 9	37	162	200	McArthur and Mead, 1987a.
Areas 8 and 10	18	278	348	McArthur and Mead, 1987a.
Area 18	6	181	24	McArthur and Mead, 1987b.
Area 20	6	96	73	McArthur and Mead, 1987b.

Source: Prepared by DOE Environmental Survey team.

No radionuclides other than naturally occurring potassium-40 were detected in kidneys of the bighorn sheep. Strontium-90 levels in the bone sample ash averaged 3.2 pCi/g of ash. This level is consistent with previous years and is an indication that the source of the strontium-90 is global fallout from past atmospheric nuclear tests (Patzner et al., 1987).

Eight beef cattle were sampled during 1986, four in May and four in October. Iodine-131 was detected at levels ranging from 1.5 to 27 pCi/g in the thyroids of the cattle collected in May. EPA-EMSL speculated that the source of the iodine was worldwide fallout associated with the Chernobyl reactor accident in the U.S.S.R. The only other gamma-emitting radionuclide detected in soft tissue was naturally occurring potassium-40. Tritium was not detected in any of the blood samples. The cattle bone ash samples averaged 1.2 pCi of strontium-90 per gram of ash. None of the samples contained plutonium-238 concentrations that exceeded the counting errors, and only two samples exceeded the counting error for plutonium-239 (14 ± 7 fCi/g ash and 4 ± 3.9 fCi/g ash.) The cattle liver samples did not contain detectable concentrations of either plutonium-238 or -239. These levels of strontium and plutonium are consistent with worldwide fallout levels (Patzner et al., 1987).

Following the MIGHTY OAK test (April 10, 1986), NTS personnel decided to collect mule deer that drank the waters draining from the T-tunnel complex in Area 12 of the NTS. A total of four deer were collected, including one control that was collected in Area 17, well away from the Area 12 ponds. Several fresh fission products were detected in the tissue and ingesta samples from the deer drinking from the tunnel ponds: iodine-131, ruthenium-103 and 106, zirconium-95, and strontium-89. These radionuclides indicate that the source was a recent fission event, most likely the MIGHTY OAK test. EPA-EMSL estimated the radiological effective dose equivalent that might be received by individuals consuming the deer. EPA-EMSL estimated that if a deer with the highest observed concentrations of cesium-137 and iodine-131 were consumed by a family of four, each individual would receive a dose of 1.9 mrem (Patzner et al., 1987). This dose is less than 2 percent of the DOE interim standard of 100 mrem/year for continuous exposure of any member of the public.

3.2.3.3 Soil Sampling at Inactive Leachfields

Eleven release sites were identified on the NTS under the CERCLA Phase I Assessment required by DOE Order 5480.14 (Fauver, 1986). All 11 sites were known to contain radioactive materials in unknown quantities. Six of the identified sites were thought to also contain nonradioactive hazardous material, primarily solvents used for decontamination of equipment, laundry, and facilities. These six sites are

- CP-2 Leachfield
- R-MAD Leachfield
- E-MAD Leachfield
- Test Cell A Leachfield
- Test Cell C Leachfield
- Area 26 Leachfield

Analytical results are available from preliminary soil sampling at these six inactive sites. These sites are also discussed in Section 4.5.2.7. The other CERCLA sites are contaminated waste dumps (see Section 4.5.2.3). These have varying levels of radioactivity, as discussed in Section 3.2.3.4.

The CP-2 Leachfield in Area 6 has been identified as CERCLA Site No. 1 (there are actually 2 leachfields I and II coded as 6-LFP-1 and 6-LFP-2 in the NTS Environmental Compliance Atlas). The CP-2 Leachfield was operational between 1951 and 1971, and was used for the disposal of liquid wastes from the decontamination of laundry and equipment. The liquid wastes contained radionuclides, as well as chemical solvents and degreasers used in conjunction with the process. The release of radioactive material into this leachfield was documented. There was no documentation as to the type or quantity of solvents released at this site. The area is enclosed by a 50-foot by 50-foot fence.

The maximum level of radioactive contamination detected at the CP-2 Leachfield was $1,070 \pm 0.126$ pCi/gram of cesium-137 (Cs-137). The only nonradioactive hazardous substances detected at this site were cadmium (0.04 mg/l of extract) and silver (0.05 mg/l) at concentrations well below the limits for the EP toxicity test (cadmium, 1 mg/l; silver, 5 mg/l). On the basis of these results, the site is considered to be essentially uncontaminated.

The Reactor Maintenance, Assembly and Disassembly building (R-MAD) Leachfield in Area 25 (CERCLA Site No. 5) was used between 1958 and 1973 to dispose of liquid wastes generated primarily by decontamination operations. The release of radioactive material to this leachfield was documented. Trichloroethene is known to have been released; the disposal of other solvents or degreasers is probable but unconfined.

No solvents (volatile organic compounds) were found at this site. None would be expected after 13 years in a desert climate. Moreover, no other nonradioactive contaminants were found. Radioactive contamination, however, is significant at this site. Cs-137 activity levels reach 493 ± 41 pCi/gram at the surface (0-15 cm), $11,900 \pm 1,012$ pCi/gram at a hot spot (76-91 cm depth),

and $21,700 \pm 1,845$ pCi/gram at a manhole bottom. No direct measurements of strontium were made, but the cesium-to-strontium ratio can be assumed to be approximately 1 to 1. Therefore, equivalent amounts of strontium-90 (Sr-90) are probably also present. The manhole bottom is also contaminated with cobalt-60 (Co-60) at an activity level of 632 ± 60 pCi/gram. Lower levels of cobalt-60, beryllium-7 (Be-7), and rhodium-106 (Rh-106) were also reported from surface, tailings, or hot-spot samples. [The presence of Rh-106 is anomalous because both it and its parent nuclide have short half-lives (1 year maximum), and it would not be expected at a site that has been inactive for 13 years.]

The Engine Maintenance, Assembly, and Disassembly Building (E-MAD) Leachfield in Area 25 (CERCLA Site No. 11) was used between 1966 and 1973 to dispose of liquid wastes generated primarily by decontamination operations. The release of radioactive material to this leachfield was documented. The type and quantity of solvents released is unknown (Fauver, 1986). No nonradioactive hazardous materials were detected here, and the maximum level of radioactive contamination found was 1.51 ± 0.165 pCi/g of Cs-137 at a hot spot 76-91 centimeters deep. The maximum radiation reading found was 100 μ R/hour at the bottom (305 cm depth) of a standpipe. No soil samples were taken at standpipes. Contamination at this site is considered to be negligible.

The Reactor Test Cell A Leachfield in Area 25 (CERCLA Site No. 6) was used from 1958 to 1966 for the disposal of liquid wastes generated primarily by decontamination operations. Test Cell A was designed for testing nuclear reactors for use as rocket engines. A chemical laboratory used in conjunction with equipment testing could also have contributed to the liquid waste stream. The leachfield is known to contain radioactive material; suspected nonradioactive releases include solvents, degreasers, acids, and other chemical wastes (Fauver, 1986). Methylene chloride was found in a soil sample from this site, at a concentration of 64 μ g/kg (ppb). This result is probably due to laboratory contamination and not to solvent actually present at the leachfield after 10 years of desert conditions. Concentrations in blanks for these particular analyses are not available, but a blank value of 75 ppb of methylene chloride was reported for similar analyses (Fleischhauer et al., 1986). Thus, laboratory contamination at this level is a reasonable interpretation. The only other nonradioactive hazardous substance detected at this site was cadmium (0.01 mg/l of extract) at a concentration well below the 1 mg/l limit for cadmium for the EP toxicity test.

Anomalies exist in the radioactivity data for this site. Potassium-40 (K-40) activity is 10 pCi/g higher on the east side of the leachfield than on the west side (40 pCi/g versus 30 pCi/g). The K-40 activity level most commonly found in these analyses from Area 25 soil samples is approximately 30 pCi/g, so that anything higher can be considered to be elevated. A value of 109 ± 16 pCi/g was reported for a "water sample" taken at a manhole bottom. Although this sample was probably wet mud and was

therefore probably potassium-rich clay, the activity level is still anomalously high. It is possible that the K-40 enrichment could be due to neutron activation of natural K-39. (A Cs-137 value of 1,560 pCi/g was also reported for this "water sample.") Cobalt-57 (Co-57) was also reported in a tailings sample at an activity level of 0.207 ± 0.063 pCi/g. The presence of this nuclide is unexpected. It is not a fission product, is produced by proton bombardment of iron-56 rather than by neutron bombardment, and is used primarily as a calibration source. The detection of this nuclide is also surprising because 13 half-lives (271.8 days for Co-57) have passed since the site was active, and this decay should have reduced the nuclide to undetectable levels. Perhaps a calibration source was disposed of at this leachfield at a later time. Despite these theories, the reasons for these anomalies in the radioactivity data for the Test Cell A Leachfield remain unknown. Contamination at this site is negligible except for the "water sample" from the manhole bottom.

The Reactor Test Cell C Leachfield in Area 25 (CERCLA Site No. 7) was used for disposal of liquid wastes generated by the decontamination of test reactors and the cleaning of stainless steel pipe in Test Cell C. Test Cell C, which was operational from 1961 to 1973, was used for testing nuclear reactors for rocket engine development. The liquid waste released contained radioactive material (fission products) as well as chemical solvents used during the decontamination and cleaning. The only known solvent used was trichloroethene, which was released in unknown quantities. Other types and quantities of chemical waste releases are unknown (Fauver, 1986).

No solvents were found at this site and none would be expected because of the effects of a desert climate on volatile organic compounds. The only nonradioactive hazardous substance detected at this leachfield was cadmium (0.02 mg/l of extract) at a concentration well below the 1 mg/l limit for cadmium for the EP toxicity test. Radioactive contamination, however, is significant. Cs-137 activity levels are as high as 328 ± 28 pCi/g at the surface and $735,000 \pm 62,475$ pCi/g at the bottom (290-305 cm) of this leachfield. Other radionuclides found are cadmium-109 (Cd-109) at an activity of 5.85 ± 1.68 pCi/g, europium-155 (Eu-155) maximum 2.27 ± 0.368 pCi/g, and antimony-125 (Sb-125) maximum $4.22 \pm .96$ pCi/g.

The Area 26 (Tory Reactor) Leachfield is CERCLA Site No. 9. This site is also known as the Area 401 Maintenance, Assembly, and Disassembly Building (MAD). It was used to dispose of liquid wastes generated by decontamination operations at the Tory Reactor from 1958 to 1964. The program involved development of a nuclear reactor for a ramjet engine as a part of Project Pluto. Between 1961 and 1964, four tests of the Tory II-A and two tests of the Tory II-C nuclear reactors were conducted. A leachfield was constructed adjacent to the disassembly building to handle radioactive liquids resulting from these tests. The field is approximately 250 feet by 250 feet (6,300 m²) and is fenced and marked (ERDA, 1977).

The maximum level of radioactive contamination detected at this site was 222 ± 19 pCi/g of Cs-137 for a sample designated as No. 1 surface 0-15 centimeters. Another sample designated No. 1 surface 0-8 centimeters, from a surface cleanup, had $4.94 \pm .435$ pCi/g of Cs-137. It is unclear whether these two samples are related. All other Cs-137 activity levels measured were less than 1 pCi/g. Other radionuclides detected were U-235 at 18.1 ± 1.64 pCi/g and Rh-106 at 0.499 ± 0.126 pCi/g. As discussed above for the R-MAD Leachfield, the presence of Rh-106 is anomalous. No nonradioactive hazardous contaminants were found. These results indicate that some hot spots or anomalies may exist, although the general level of contamination is negligible.

In summary, an evaluation of preliminary soil sampling data for six inactive leachfields suggest that the Test Cell C and R-MAD Leachfields are clearly contaminated with radionuclides. The Area 26 Leachfield may have some hot spots, and the Test Cell A Leachfield shows anomalous radionuclide results. The E-MAD and CP-2 Leachfields have no or negligible contamination. None of the six was clearly identified as containing mixed waste at the present time, although all were suspected of receiving decontamination solvents.

3.2.3.4 Inactive Contaminated Waste Dumps

Contaminated waste dumps (CWDs) include shallow, buried, contaminated waste which has been deposited at that location from several events or activities. Five of these dumps were identified in the CERCLA Phase I Installation Assessment (Fauver, 1986) and sampled for radionuclides. No disposal of nonradioactive hazardous materials was suspected at these sites, and gamma spectrometry and a single Pu-239 analysis were apparently the only analyses performed. Descriptions of these sites and analytical data are presented in Section 4.5.2.3. Such burial sites should have little or no potential for soil contamination if no liquid phase is present to promote contaminant migration and if the material is covered to prevent resuspension. Thus, if no contamination is present at the surface, there is little or no potential in an arid climate for environmental contamination. This appears to be the case for three of the five CWDs. These three are the E-MAD CWD in Area 25, the Tory Reactor CWD in Area 26, and CWD No. 1 in Area 11. At the E-MAD CWD, the only elevated radioactivity is 34.7 ± 2.9 pCi/g of Cs-137 at the bottom of Pit No. 1 (see data table in Section 4.5.2.3) and 17.4 ± 1.5 pCi/g of Cs-137 at the bottom of Pit No. 2. Radioactivity in surface samples is not elevated, although the presence of $0.351 \pm .098$ pCi/g of anomalous Rh-106 (see Section 3.2.3.3) was detected. The Tory Reactor CWD and the Area 11 CWD No. 1 show no elevated radionuclide levels at any depth.

The remaining two CWDs are the R-MAD CWD in Area 25 and the Area 11 CWD No. 2. Pit No. 3 at the R-MAD CWD is essentially uncontaminated, and Pit No. 2 has elevated radioactivity levels only at the bottom (211 ± 20 pCi/g Cs-137; 98.2 ± 13 pCi/g Ra-226; $3.34 \pm .38$ pCi/g Co-60). However, Pit No. 1 at the R-MAD CWD shows elevated radioactivity at the surface (53.8 ± 4.5 pCi/g Cs-137; 25.4 ± 10.4 pCi/g Ra-226; 11.2 ± 1.0 pCi/g Co-60). Bottom levels in this pit are as high as 403 ± 34 pCi/g Cs-137.

The most contaminated CWD is the Area 11 CWD No. 2. Moreover, this contamination is present at the surface. Radioactivity levels are as high as $4.950 \pm 1,160$ pCi/g Pu-239 and 563 ± 48 pCi/g Am-241. This dump was used for the disposal of Pu-239 contaminated wastes generated from safety shots (see Section 4.3.2).

3.2.4 Findings and Observations

3.2.4.1 Category I

None.

3.2.4.2 Category II

None.

3.2.4.3 Category III

1. Contamination of Surface Soils by Radionuclides and Beryllium. Surface soils within the boundaries of the NTS and outside the site boundaries on the Nellis Air Force Range are contaminated with radioactive materials and potentially contaminated with beryllium from past atmospheric test activities, including nuclear detonations, safety experiments, hydrodynamic experiments, nuclear-rocket explosion experiments, and a nuclear-rocket accident.

Contaminated areas have been identified and posted with warning signs by NTS personnel, and access to these areas is restricted. However, there is a potential for the spread of this contamination to uncontrolled, presently uncontaminated areas through saltation, surface creep, and air resuspension, particularly if the desert pavement is disturbed. Contamination levels are such that unrestricted use of these areas could result in an individual receiving a radiation exposure in excess of the DOE interim standard of 100 mrem/year for continuous

exposure of any member of the public. In areas with radiation levels in excess of 0.3 mrem/hour (e.g., Areas 2 and 4, and Yucca Flat), the DOE interim standard could be exceeded in less than 350 hours of presence. In addition to this external exposure pathway, an individual in these areas could receive internal exposure through the inhalation and ingestion pathways. Consequentially, these areas must be controlled indefinitely or decontaminated prior to unrestricted release.

Soil contamination on the NTS has been studied as a part of the NAEG programs and RIDP. NAEG studies characterized the contamination on the Nellis Air Force Range, including a location to the north of NTS Area 15 that was previously known as Area 13 (see Section 3.2.2.1). The Survey team has received published reports from RIDP that delineate and inventory the radionuclide contamination in Areas 1, 2, 3, 4, 6, 7, 8, 9, 10, 18, and 20. In these areas, 100 square miles were identified as being contaminated with transuranic elements, activation products, and fission products. The total inventory of radionuclides in these areas is 795 curies of transuranics, and 831 curies of fission products and activation products combined. In all of these areas, the mean transuranic levels exceed the proposed EPA screening guideline for exposure of members of the general public to transuranics in surface soils of $0.2 \mu\text{Ci}/\text{m}^2$. RIDP reports on the remainder of the NTS are expected to be published in FY1988 (Anspaugh, 1987).

Beryllium contamination of surface soils is suspected to be present in some locations on the NTS. This contamination is being addressed as a part of BECAMP. NVO is currently conducting a records search to identify potential areas of beryllium contamination. A program to characterize the extent of the contamination will be developed on the basis of the results of the records search. In addition, NVO has conducted some soil sampling for beryllium in Area 5 at the location of the SUGARBUNKER safety experiment. At the time of the on-site portion of the Environmental Survey, the analytical data for this sampling were not completed, and there were no data available concerning levels of beryllium contamination on the NTS.

2. Contamination of Subsurface Soils from Underground Nuclear Testing. Subsurface soils in some areas of the NTS are contaminated with large inventories of fission products and lesser amounts of activation products and transuranics in the chimneys and cavities of past underground nuclear detonations. There have been more than 400 underground nuclear detonations at the NTS within the unsaturated zone (subsurface soil and rock above the water table). The migration potential for radioactive material within the unsaturated zone is very low, because the amount of water available is very small and the movement of this water is very slow.

3. Surface and Near-Surface Soil Contamination From Waste Disposal Practices. Near-surface soil contamination from waste and wastewater disposal may extend to unknown depths at both active and inactive sites. The sites identified during the Survey are listed in Section 3.2.2.3 and described in more detail in the sections given as cross-references in that list. Further information is presented in Sections 4.5.2 and 3.4.2. Category II findings on the regulatory aspects of many of these sites are presented in Waste Management Sections 4.1.3.2.1 and 4.1.3.3.1 and Surface Water Section 3.3.4.2.

These suspected or known sources of soil contamination are of several types:

- Discharges of wastewater to the land surface are creating probable soil contamination and the potential for transport of contamination by storm runoff or flash flooding. Either direct discharges or overflow from wastewater ponds and sumps may be causing contaminants to build up. Repeated discharge or precipitation may move such contamination downward in the unsaturated zone.
- Discharges of wastewater into shallow injection wells and pits create probable soil contamination. However, the presence of contaminants in these discharges has not been determined.
- Wastewater discharges into sumps, lagoons, and ponds may be causing contaminants to build up in subsurface soil. Such impoundments also provide a source of recharge for potential groundwater contamination (see Section 3.4.2.6). If these impoundments become inactive, contaminated sediments become surface soil contamination.
- Wastewater discharges into leachfields, both active and inactive, create probable soil contamination. Radioactive contamination is known to be present at the R-MAD and Test Cell C leachfields in Area 25 and the Area 26 leachfield at the 401 MAD building. Details are given in Section 3.2.3.3.

- Leaks and discharges of material other than wastewater create known soil contamination. Such materials are cutting oil, jet fuel, and waste liquids of various kinds. Findings on these waste sites and releases are presented in Waste Management (Sections 4.1.3.2.1, 4.1.3.2.3, and 4.1.3.3.1) and Inactive Waste Sites and Releases (Section 4.5.3.3).
- Some, but not all, inactive contaminated waste dumps have radioactive contamination at the surface and are therefore sources of surface soil contamination (see Sections 3.2.3.4 and 4.5.2.3).

3.2.4.4 Category IV

None.

PRELIMINARY

3.3 Surface Water

3.3.1 Background Environmental Information

The closest major surface water body to NTS is Lake Mead (Figure 3-7). This man-made lake is formed by the waters of the Colorado River held behind Hoover Dam, which is located approximately 85 miles (136 kilometers) southeast of Mercury. The lake is 110 miles long (175 kilometers) with 550 miles (880 kilometers) of shore line and stores more than 27 million acre-feet (36 billion cubic meters) of water, or 3 years of the rivers average annual flow (ERDA, 1977). None of the water from NTS reaches this river, although the discharge from the North Las Vegas Support Facility (NLVF) to the City of North Las Vegas Sewer System does. The U.S. Geological Survey (USGS) maintains water-quality sampling stations on the Colorado River below Hoover Dam and on Las Vegas Wash near Boulder City, Nevada. Las Vegas Wash conveys storm waters, industrial discharges, and municipal treatment plant effluents from the Las Vegas area to the Colorado River. Tables 3-8 and 3-9 show the average, maximum and minimum results of analyses of samples collected at these two locations.

Other surface-water bodies closer to NTS (Figure 3-7) are springs and their pools in Ash Meadows, 25 miles (40 km) southwest of Mercury; Death Valley, 50 miles (80 km) southwest of Mercury; and Oasis Valley (near Beatty, Nevada), 45 miles (72 km) northwest of Mercury. The pools in Ash Meadows include Devils Hole, a sinkhole habitat for the endangered desert-pupfish species 'Cypridodon diabolis' (see Section 3.4.1.2). The springs in Oasis Valley produce enough water that there is flow in the Amargosa River north of Beatty. However, there is usually no flow south of Beatty because of evaporation and percolation into the ground.

These waters, and those springs and seep on NTS (Figure 3-8) itself, are in the Great Basin geological province. Therefore, there is no outlet for the surface waters to reach the ocean. There are two dry lake beds or playas, (Frenchman Flat and Yucca Flat) on the NTS itself, and four (Gold Flat, Kawich Valley, Groom Lake Valley, and Papoose Lake Valley) on the adjoining Nellis Air Force Range that receive surface water drainage from NTS. These playas are the result of the valleys having no external drainage. They are covered with water for short periods of time (days or weeks) after infrequent heavy rains. These basins are shown in Figure 3-9. This figure also shows the drainage patterns for surface runoff to the west and south of the site, which could flow to the Amargosa River if the storm intensity and duration is great enough. The infrequency of flow in this climate is demonstrated by information in the USGS Water Resources Data (Frisbie et al., 1985), which shows flow on only 2 days during water year 1984 (October 1983-September 1984) at the stream-gauging station in Lee Canyon in Toiyabe National Forest (Figure 3-7). This location is 30 miles (48 km)

FIGURE 3-7

SURFACE WATER NEAR NEVADA TEST SITE
NEVADA TEST SITE - MERCURY, NV

TABLE 3-8

USGS DATA FOR YEAR 1984
 COLORADO RIVER BELOW HOOVER DAM
 ARIZONA - NEVADA

	Average	Maximum	Minimum
Flow (CFS)	26,340	50,800	3,300
Conductivity (umhos/cm)	937	990	890
pH(S.U.)	--	8.2	7.9
Temperature (°C)	13.2	14.0	12.5
Turbidity (NTU)	0.55	0.80	0.30
Dissolved oxygen (mg/l)	8.7	10.4	6.8
Hardness (as CaCO ₃) (mg/l)	307	330	290
Calcium (mg/l)	78	84	74
Magnesium (mg/l)	27	28	25
Sodium (mg/l)	89	94	82
Potassium (mg/l)	4.3	4.7	4.0
Alkalinity (mg/l as CaCO ₃)	135	139	133
Sulfate (mg/l)	263	280	240
Chloride (mg/l)	73	78	64
Fluoride (mg/l)	0.32	0.40	0.30
Silica (mg/l)	8.2	8.4	8.0
Dissolved Solids (mg/l)	641	667	605
Nitrogen NO ₂ + NO ₃ (mg/l as N)	0.317	0.380	0.120
Nitrogen, ammonia (mg/l as N)	0.038	0.080	<0.010
Nitrogen, ammonia & organic (mg/l as N)	0.60	0.80	<0.20
Phosphorus, total (mg/l as P)	0.010	0.010	<0.010
Suspended sediment (mg/l)	4	9	2
Aluminum (µg/l)	<10	<10	<10
Arsenic (µg/l)	2	2	2
Barium (µg/l)	110	110	110

TABLE 3-8
USGS DATA FOR YEAR 1984
COLORADO RIVER BELOW HOOVER DAM
ARIZONA - NEVADA
PAGE TWO

	Average	Maximum	Minimum
Beryllium (µg/l)	< 0.6	< 1	< 0.5
Cadmium (µg/l)	< 1	< 1	< 1
Chromium (µg/l)	1	2	< 1
Cobalt (µg/l)	< 3	< 3	< 3
Copper (µg/l)	1	2	1
Iron (µg/l)	5	10	< 3
Lead (µg/l)	1	2	< 1
Lithium (µg/l)	49	55	42
Manganese (µg/l)	3	7	< 1
Mercury (µg/l)	< 0.1	0.1	< 0.1
Molybdenum (µg/l)	< 10	< 10	< 10
Nickel (µg/l)	2	3	< 1
Selenium (µg/l)	3	3	3
Silver (µg/l)	< 1	< 1	< 1
Strontium (µg/l)	1,020	1,100	990
Vanadium (µg/l)	< 6	< 6	< 6
Zinc (µg/l)	10	14	6

Source: Frisbie et al., 1985.

TABLE 3-9

USGS DATA FOR YEAR 1984
LAS VEGAS WASH NEAR BOULDER CITY, NEVADA

	Average	Maximum	Minimum
Flow (CFS)	118	165	91
Conductivity (μ mhos/cm)	2,820	3,200	2,550
pH(S.U.)	--	8.1	7.7
Temperature ($^{\circ}$ C)	18.2	26.0	11.0
Dissolved Oxygen (mg/l)	8.7	10.6	7.2
Hardness (as CaCO_3) (mg/l)	990	1,200	800
Calcium (mg/l)	245	330	180
Magnesium (mg/l)	90	100	85
Sodium (mg/l)	285	310	260
Potassium (mg/l)	27	34	22
Alkalinity (mg/l as CaCO_3)	134	148	118
Sulfate (mg/l)	1,020	1,200	840
Chloride (mg/l)	355	410	300
Fluoride (mg/l)	0.65	0.70	0.60
Silica (mg/l)	27	28	26
Dissolved solids (mg/l)	2,060	2450	1,960
Nitrogen $\text{NO}_2 + \text{NO}_3$ (mg/l as N)	2.8	4.9	1.0
Nitrogen, ammonia (mg/l as N)	6.02	7.90	4.90
Nitrogen, ammonia & organic (mg/l as N)	8.5	14	6.0
Phosphorus, total (mg/l as P)	0.774	1.80	0.430
Suspended sediment (mg/l)	1,469	7,230	113

Source: Frisbie et al., 1985.

FIGURE 3-8

NATURAL SURFACE WATER AT NEVADA TEST SITE
NEVADA TEST SITE - MERCURY, NV

FIGURE 3-9

**BOUNDARIES OF BASINS AND DIRECTIONS OF SURFACE DRAINAGE
NEVADA TEST SITE - MERCURY, NV**

southeast of Mercury and is the closest permanent stream-gauging station to NTS, for which data are reported in that document. Because of this lack of flow, there are no water quality data for the Amargosa River or the stream in Lee Canyon.

The surface water portion of the Environmental Survey of the NTS would normally address existing and potential environmental impacts associated with releases to adjacent surface waters. Since only the NLVF has even an indirect discharge to a permanent surface water body, this section consists of a discussion of pollution sources and controls and compliance with drinking water and water discharge regulations. Principal regulations used as guidance during the Survey include

- The Clean Water Act (CWA)
- The Safe Drinking Water Act (SDWA)
- Federal Regulations, including
 - National Pollutant Discharge Elimination System (NPDES) (40 CFR 122-125)
 - National Primary and Secondary Drinking Water Regulations (40 CFR 141 and 143)
- The Nevada Water Pollution Control Law
- State Regulations, Including
 - Nevada Water Pollution Control Regulations, Nevada Administrative Code (NAC 445.070-445.174), Division of Environmental Protection
 - Public Water System Regulations, (NAC 445.244-445.262), Division of Health
 - Regulations Governing Individual Sewage Disposal Systems (NAC 444.750-444.840), Division of Health
- North Las Vegas Municipal Code Title 4, Chapter 4.14, Industrial Wastes

The Nevada Water Pollution Control Law requires a permit for the discharge of pollutants to any waters of the state or to any treatment works or the injection of fluids through a well into any waters of the state. Waters of the state include, but are not limited to, all streams, lakes, ponds, impounding reservoirs, marshes, watercourses, waterways, wells, springs, irrigation systems, and drainage systems; and all bodies or accumulations of water, surface and underground, natural and artificial. The law also requires that permits be obtained prior to beginning the construction of treatment works. Treatment works are any devices or system used in the storage, treatment, recycling, and reclamation of municipal sewage or industrial wastes of a liquid nature.

The water used at NTS comes from deep wells (600-2,400 feet to static water level). Data on water quality of these wells is presented in Section 3.4.1.3.

The background radioactivity in the vicinity of the NTS contains both natural and manmade components. Nuclear weapons testing at NTS produces a wide variety of radionuclides through the fission process, activation of structural materials used in tests, and activation of soil constituents. Uranium and plutonium are used in weapons fabrication, and there are some quantities of these nuclides on the NTS from previous tests. In addition, other activities such as radioactive waste disposal, nuclear rocket testing, and high-level radioactive waste research programs result in various radionuclides being present at the NTS. A complete listing of all the radionuclides that might be used, produced by nuclear reactions, or disposed of at the NTS would contain more than 500 entries. Surface water on the NTS or at nearby locations could potentially be contaminated with any of the materials present at the site.

Most of the radionuclides that might be released from the NTS are likely to be present in the environment from pre-1963 world-wide nuclear weapons tests, nuclear power-plant operation, nuclear fuel reprocessing plants, industrial processes involving radioactive materials, various research and medical applications, and nuclear reactor accidents such as the one at Chernobyl in the Soviet Union that occurred in April 1986. Background levels of radionuclides in the surface water from these sources will vary with time and location because of meteorological conditions and unusual releases from world-wide sources.

To determine whether the NTS is contributing to radionuclide concentrations in water, it is necessary to have some knowledge of the radionuclide contributions from other sources. Because of the many factors that may influence the radionuclide-in-water concentrations, it is not possible to exactly predict background levels in a given area. It is possible, however, to estimate background levels of a radionuclide. One approach to this is to determine the radionuclide concentrations at a location that is nearby, but sufficiently removed that the observed radionuclide levels would not be affected by the potential pollutant source. EPA's Eastern Environmental Radiation Facility (EPA-EERF) administers a program for radiation monitoring throughout the United States. EPA-EERF reports tritium on a quarterly basis, and gamma-emitting nuclides, gross-alpha, and gross-beta on annual composites. For the period January-March 1987, EPA-EERF sampled tritium in drinking water at 78 locations throughout the United States. Tritium concentrations ranged from a low of 0.1 ± 0.2 nCi/l at several locations to a high of 1.2 ± 0.2 nCi/l at Savannah, Georgia. For Las Vegas, Nevada, the measured tritium concentration was 0.2 ± 0.2 nCi/l (EPA, 1987b). The most recent gross alpha and beta activity and gamma analyses were reported for 1985 (EPA, 1987a). For 1985, no

specific gamma activity was detected. The gross-alpha activity ranged from a negative result at Columbus, Ohio, (-0.9 ± 2.2 pCi/l) to a high of 21.4 ± 7.1 pCi/l at Platteville, Colorado. The gross-alpha activity at Las Vegas, Nevada, for the same period was 3.8 ± 4.5 pCi/l. For gross-beta, the data ranged from a negative value (-1.2 ± 1.0 pCi/l) at Seneca, South Carolina, to a high of 18.2 ± 10.6 pCi/l at Columbus, Ohio. The Las Vegas, Nevada, measurement for this period was 6.6 ± 3.9 pCi/l. The background activity levels at the NTS would be comparable to those observed at Las Vegas, Nevada.

3.3.2 General Description of Pollution Sources/Controls

Since there is no surface water on or adjacent to NTS, there is no actual surface water pollution at the site itself. The liquid discharges at NTS can be sources of soil and/or groundwater contamination, depending upon whether they percolate through the soil to reach the groundwater or evaporate, leaving contaminants in the soil. The North Las Vegas facility can be a source of surface water pollution because its discharge to the city sewer system eventually flows into the Colorado River. The following sections discuss these liquid discharges at NTS and NLVF.

3.3.2.1 Industrial Wastewater

There are no manufacturing processes at NTS other than those needed to support the primary mission of conducting nuclear tests. These support activities include light machine shops (lathes, drill presses, etc.), analytical laboratories, photo laboratories, decontamination pads, vehicle repair and maintenance shops, drill bit repair facilities, and concrete batch plants. The waste waters associated with these operations are not discharged off-site. Furthermore, these industrial wastewater flows are intermittent because the operations are not continuous and a good portion of the on-site activity is during the day shift.

There are industrial waste lagoons (ponds) in Areas 6 and 12 and pits or disposal wells (an excavation whose depth is greater than its longest surface dimension) in Areas 1, 2, 3, 6, 11, and 25. Leachfields also have been and are presently being used for the disposal of liquid waste streams (usually containing radioactive material) at NTS.

The industrial waste lagoons in Area 6 include the following:

- Steam cleaning pond No. 1, which receives the effluent from the steam cleaning pad at the Machine and Welding Shop (Building 6-623).
- Steam cleaning pond No. 2, which receives the effluent from the steam cleaning pad at the Heavy Duty Repair Shop (Building 6-800).
- The Decontamination Pond, which receives the liquid supernatant effluents from four sumps at the Decontamination Facility (Building 6-605) and the Decontamination Laundry (Building 6-607). These are the two sumps that receive the wastes from the two decontamination pads, the laundry wastewater effluent sump, and the septic tank used to treat sanitary waste at the Decontamination Area.

The industrial lagoons in Area 12 are the industrial wastewater pond, which receives effluents from the Construction Shops (Building 12-8) and the Motor Pool Equipment Maintenance Shop (Building 12-16), and the 16 tunnel ponds, which receive the groundwater that seeps into the tunnels used for the nuclear tests. The use of these ponds is discussed in greater detail in Sections 3.4.2.3 and 4.1.2.1.2.

The water in the above lagoons (ponds) can either evaporate or percolate into the ground under the lagoons because they are not lined. If the capacity of the lagoon is exceeded, the water simply overflows onto the adjacent desert and either evaporates or is absorbed by the soil. None of this water would leave the site, except in the unlikely event that it would reach the groundwater, because the lagoons in these two areas are in one of the playa drainage basins.

A variety of liquid waste streams are discharged to pits and/or disposal wells at NTS. In Area 1, the Subdock Steam Cleaning Pad wastes drain to a 24-inch diameter hole in the center of the concrete pad. The Area 2 Cutter Rebuild Shop has two wells that are used for wastewater disposal. One well inside the shop is used to receive water from cutter washing, and another outside the shop is used for water from roller washing. Both these wells have a 52-inch surface casing which narrows to 20 inches approximately 4 feet below the ground surface. The LLNL post-shot facility in Area 2 also has a pit that receives wastewater from servicing drill-back equipment in the southwest portion of this building.

The Area 2 Photo Skid has a rectangular shallow pit that receives wastes discharged from the photographic laboratory. Water entering the Steam Cleaning Control Pad Sump at the Area 3

post-shot facility reportedly drains to an 88-inch diameter, 100-foot deep hole that is located under a 3/8-inch steel plate under the wooden parts storage rack just south of the pit. The Area 3 Blow-off Preventer Servicing Area is used to service equipment used in the drill-back operation after nuclear tests. Water that collects in the Blow-off Preventer Servicing Cellars is pumped out about two times per month to a casing adjacent to the lineman's shop next door. This casing is painted yellow and is about 6-7 feet in diameter. A 20 x 30 foot pit in the Well 3 Yard in Area 6 receives drainage from the trench washing areas in the maintenance garages. The LANL Technical Facilities in Area 11 discharge both sanitary and photographic wastes to a 15 x 15 foot pit west of the double-fenced portion of the facility.

The pits and disposal wells do not provide for any release of the waters in them except by evaporation or seepage into the ground.

Leachfields are networks of perforated pipes set several inches below the ground surface with the intended purpose of distributing liquid discharges over a large enough area of soil so that the liquid percolates (leaches) into the underlying soil and does not form muddy areas on the surface. All industrial, as well as sanitary, wastewaters in Area 27 and the flows from the radiochemistry laboratories, the decontamination shower, the photographic laboratory, and the silver recovery unit in Building 650 in Area 23 are discharged to leachfields at the present time. Past discharges of industrial wastewater to leachfields in Areas 3, 6, 23, 25, and 26 are discussed in Section 4.5.2.

No permits have been obtained from either the state or EPA for any of these discharges.

3.3.2.2 Sanitary Wastewater

The sanitary sewage at NTS is handled by either septic tanks or sewage lagoons. Septic tanks used to treat sanitary sewage also discharge to leachfields. A list of these locations is included in Table 3-18 in Section 3.3.4.2.

Four, and possibly five, lagoon systems in Area 6 receive sanitary wastes. Four lagoons east of Mercury Highway, by the Helipad, receive the sewage from CP-1. The Decontamination Pond in Yucca Lake, discussed previously in Section 3.3.2.1, receives sanitary wastes from the decontamination facility. The Yucca Lake domestic sewage system consists of three ponds in series that receive the sanitary waste from the Yucca Lake Heavy Duty Equipment Area. Sewage Lagoons I and II operate in parallel and receive the sanitary wastes from the other shop facilities located at Yucca Lake. The fifth lagoon system, consisting of two ponds in series, is located south of CP-1 on the west side of Mercury Highway. Industrial hygiene personnel were not aware of its existence and did

not know where the influent was coming from. The sewer system in Areas 2, 12, 22, and 23 deliver this flow to a single lagoon system in each area.

Only the six primary lagoons at Area 23 presently have aerators to provide additional oxygen to treat the sewage. NTS is in the process of designing new facilities for lagoons in Areas 6, 12, 22, and 23. These will include additional aeration capacity to improve the treatment efficiency. Efficiency must be increased to meet the state requirements of 30 mg/l daily average and 45 mg/l daily maximum for both biochemical oxygen demand (BOD) and total suspended solids (TSS) that will most likely be imposed when the sewage permits are issued. Sludges removed from the sewage lagoons are dried and chlorinated adjacent to the lagoons before being hauled to a sanitary landfill for disposal.

Chemical toilets are used in those areas which are not served by a sewer system that is connected to a lagoon or septic tank. These wastes (containing formaldehyde) are pumped into tank trucks and are then buried in trenches on-site. The location and operation of landfills and trenches used for the on-site disposal of nonhazardous wastes are discussed in Section 4.1.2.1.4.

3.3.2.3 Storm Water

Since rainfall is so infrequent at NTS, there is no storm sewer system. The water is simply allowed to percolate into the desert. In the case of built-up areas such as those in Areas 6, 12, and 23, it is directed to the nearest natural drainage course. In this case, short, underground, sewer lines are used in some paved areas. As can be seen in Figure 3-9, the stormwater from Area 6 and 12 would drain into the dry lakes on Yucca and/or Frenchman Flats and storm water from Area 23 could flow off-site, if the storm had the intensity and duration to provide enough water for overland flow.

The topography and climatology of NTS are such that flash flooding can occur on-site. The lack of vegetation to retard runoff water, the slope of the land surface which facilitates rapid flow to lower elevations, the possibility of slow penetration of water into the soils due to the formation of hardpans (see Section 3.2.1), and the local intensity of infrequent storm events all contribute to the possibility of flash flooding at NTS. The sewage lagoons in Areas 12 and 23, the tunnel ponds in Area 12, and possibly the sewage lagoons located south of CP-1 and west of the Mercury Highway in Area 6 appear to be in areas that would allow them to be flooded or eroded away in a heavy storm event. The actual environmental impact of such an occurrence would be minimal, since only the Area 23 sewage ponds material could possibly be carried off-site, and in all likelihood, material from any of the ponds would be spread over the adjacent desert and evaporate, once the storm event passed. However, the probability of the frequency and magnitude of flood events at a particular

location has to be determined specifically, as was done for the Radioactive Waste Management Site (French and Lombardo, 1984).

3.3.2.4 Water Distribution System

There are six potable and one nonpotable water distribution systems at NTS. In addition there are several wells that are used or could be used to supply water to sumps and truck fill stands adjacent to the wells. The locations of these systems and wells are shown in Figure 3-10.

The potable water system in Areas 12 and 2 (served by Well 8), and that in Area 23 (served by Wells 5b, 5c, and Army Well No. 1) are designated community water systems because of the number of people they serve. The potable systems in Area 3 (served by Well A), Area 6 (served by Wells C, C-1 and 4), Area 1 (served by Well UE 16d), and Area 25 (served by Wells J-12 and J-13) are designated non-community water systems. These designations determine the frequency of sampling required for these systems, as discussed in Section 3.3.3.2.

The following permits for these potable water systems have been issued by the Nevada State Division of Health:

Area	Permit Number	Classification
2 and 12	NY-4099-12C	Community
23	NY-360-12C	Community
3	NY-4097-12NC	Non-Community
25	NY-4098-12NC	Non-Community
6	NY-5000-12NC	Non-Community
1	NY-5024-12NC	Non-Community

The nonpotable system located in Areas 19 and 20 in the northwest portion of NTS consists of two wells, Well 19c and Well 20. These wells only provide construction water for these areas. Potable water used in Areas 19 and 20 is trucked in from other systems.

Wells 2 (Area 2), UE-15d (Area 15), and UE1r (Area 1) are just used to supply water to the open construction water sumps and truck fill stands that they serve. They are not connected to a distribution system at present.

FIGURE 3-10

WATER SYSTEMS NEVADA TEST SITE - MERCURY, NV

The well pumps at NTS lift the water out of the ground into a construction water sump or a forebay tank. The construction water sumps are earthen reservoirs that are used to supply water to users by truck or temporary aboveground pipe lines. If the well water is to be used for a potable water supply, it is delivered to a forebay tank by the well pump. Water from the same well can be used for either potable or construction water use. No water that is to serve potable uses is put into an open reservoir prior to being put into the potable distribution system. Water from a potable distribution system, however, can be used to supply a construction reservoir.

In addition to the above controls, backflow preventers have been installed with all new construction since 1980 at NTS. Backflow preventers are used to keep contaminated water from a service connection from entering a water main if pressure is lost in the main. There is no formal written procedure for inspecting and maintaining backflow preventers at NTS.

The waters from Wells C, C-1 and the Army Well have a high hardness content (Section 3.4.1.3) and are passed through zeolite softeners before they enter the forebay tank. When water containing calcium and magnesium hardness passes through a zeolite softener, the calcium and magnesium become attached to the particles of exchange material and are replaced by an equivalent amount of sodium in solution. After a period of time, the exchange bed becomes exhausted (i.e., loses its ability to remove hardness from the water). It then must be regenerated by passing a solution of salt (sodium chloride) through the softener. During this regeneration operation, sodium is replaced onto the particles of the exchange material and the capacity for removing hardness is thus restored. The calcium and magnesium accumulated during the previous softening run are discharged to waste in the spent brine. Spent brine must be rinsed from the exchange bed before the unit can be returned to service (i.e., failure to rinse a bed sufficiently may contaminate the water system with chloride, calcium, and magnesium). At the time of the Survey, NTS did not have permits for the discharge of spent brine and rinsewater to the drainage pits that receive these wastes (Section 3.3.4.2).

Gaseous chlorine is added as a disinfectant to all potable water distribution systems. Some of the waters are also treated with sodium phosphate (Clow F-44) to prevent corrosion and scale deposition in the water lines.

When tanker trucks are used to supply potable water to facilities not connected to one of the potable water distribution systems, a sodium hypochlorite solution (laundry bleach) is used to provide the chlorine for disinfection. This solution is added by hand to the storage tanks at the facilities.

3.3.2.5 North Las Vegas Facility

In performing its mission to provide instrumentation packages and support for the test programs at NTS, the North Las Vegas Facility (NLVF) manufactures and assembles electronic printed circuit boards and chassis. Waste rinse waters from the printed circuit board plating, aluminum anodizing, descaling/electropolishing, and photographic developing operations are discharged to the City of North Las Vegas sewer-system under Permit No. 85-1 issued by the city on August 9, 1985. The concentrated spent baths from these operations are transferred into other containers and are retained on-site for later disposal as hazardous wastes (Section 4.1.2.2.1).

Table 3-10 lists the location, constituents, and disposition of the various process baths used in these operations. Monitoring by NLVF (Section 3.3.3.5) has shown that these waste rinsewater discharges are out of compliance with the metal finishing pretreatment standards for copper, lead, and chromium as promulgated in 40 CFR 433 (Section 3.3.4.3). At the time of the survey, NLVF was working with a consultant to conduct an investigation and to design a treatment system to bring it into compliance with the regulations.

Paragraph 4.14.060(e) of the North Las Vegas Municipal Code limits the length of time for which a permit may be issued to two years and requires the user to apply for reissuance of the permit a minimum of 180 days prior to the expiration date. Permit 85-1 was due to expire on August 9, 1987, and application for its renewal was made on July 7, 1987, during the on-site portion of the Survey.

During the tour of the facility, it was pointed out to the Survey team by NLVF staff that runoff from the paved area adjacent to Building A-1, which is used as a lead storage area, could flow onto off-site, unpaved, ground. While it is unlikely that there is enough precipitation to solubilize a sufficient amount of lead to contaminate the adjacent ground, it might be possible that particulates have been transported to this area and accumulated over time.

3.3.3 Environmental Monitoring Program

Because the NTS has no permits to discharge water, it does not do routine environmental or bioassay monitoring of surface water. The nonradiological supplement to the NTS Environmental Monitoring Report for Calendar Year 1985 contains the statement "No effluent monitoring is required" under the heading of Water Pollution. However, NTS has taken some samples for special studies, and is required to monitor discharges at the North Las Vegas Support Facility as part of the permit issued by the City of North Las Vegas.

TABLE 3-10

**NORTH LAS VEGAS WASTEWATER SOURCES
NEVADA TEST SITE, MERCURY, NEVADA**

Location	Unit I.D. No.	Process Bath	Bath Constituents	Disposition
Plating Shop	1	Solder Stripper	Fluoboric Acid, Hydrogen Peroxide, pH < 2	Retained for Disposal
	2	Rack Stripper	50% Nitric Acid pH < 2 Copper Contaminated	Retained for Disposal
	3	Pyro Copper	Copper Ammonia Phosphates pH 8-8.5	Retained for Disposal
	4	Spray Water Rinse	Pyro Contaminated	Discharged to Sewer
	5	Electroless Copper (1175A)	Surfactants, Monoethanolamine Chelated Copper pH > 9	Retained for Disposal
	6	Hot Water Rinse	1175A Contaminated	Discharged to Sewer
	7	Ammonium Persulfate (A.P.)	20-30% A.P. pH < 2	Retained for Disposal
	8	Water Rinse	A.P. Contaminated	Discharged to Sewer
	9	Sulfuric Acid	10% Acid pH < 2	Retained for Disposal
	10	Water Rinse	Acid Contaminated	Discharged to Sewer
	11	Hydrochloric Acid	10-25% Acid pH < 2	Retained for Disposal

TABLE 3-10
NORTH LAS VEGAS WASTEWATER SOURCES
NEVADA TEST SITE, MERCURY, NEVADA
PAGE TWO

Location	Unit I.D. No.	Process Bath	Bath Constituents	Disposition
Plating Shop (cont'd)	12	Catalyst 9F	Hydrochloric Acid Stannous and Stannic Chloride Palladium Chloride pH < 2	Retained for Disposal
	13	Water Rinse	Catalyst Contaminated	Retained for Disposal
	14	Water Rinse	Trace Catalyst Contaminant	Discharged to Sewer
	15	Accelerator 19	Fluoboric Acid pH 5-6	Retained for Disposal
	16	Water Rinse	Accelerator 19 Contaminated	Discharged to Sewer
	17&18	Electroless Copper	Sodium Hydroxide Formaldehyde Copper Sulfate Potassium Sodium Tartrate	Retained for Disposal
	19	Water Rinse	Electroless Contaminated	Discharged to Sewer
	20	Water rinse	Trace Electroless Contaminants	Discharged to Sewer
	21	Sulfuric Acid	3% Acid, pH < 2	Retained for Disposal
	22	Water Rinse	Acid Contaminated	Discharged to Sewer
	23	Spray Water Rinse	Acid Contaminated	Discharged to Sewer
	24	Water Rinse	Acid Contaminated	Discharged to Sewer
	25	Sulfuric Acid	3% Acid, pH < 2	Retained for Disposal

TABLE 3-10
NORTH LAS VEGAS WASTEWATER SOURCES
NEVADA TEST SITE, MERCURY, NEVADA
PAGE THREE

Location	Unit I.D. No.	Process Bath	Bath Constituents	Disposition
Plating Shop (cont'd)	26	Water Rinse		Discharged to Sewer
	27	Ammonium Persulfate	30% A.P., pH < 2 Copper	Retained for Disposal
	28&29	Water Rinse	A.P./Copper Contaminated	Discharge to Sewer
	30	Cleaner 1175A	Surfactants Monoethanolamine, Chelated Copper, pH > 9	Retained for Disposal
	31	Tin/Lead Plating	Stannous Tin Lead Fluoboric Acid Boric Acid Peptone pH < 2	Retained for Disposal
	32	Spray Water Rinse	Tin/Lead Contaminated	Discharged to Sewer
	33	Fluoboric Acid	3% Acid pH < 2	Retained for Disposal
	34	Water Rinse	Ammonium Persulfate Contaminated	Retained for Disposal
	35	Ammonium Persulfate	30% A.P. Copper Contaminants pH < 2	Retained for Disposal
	36	Water Rinse	A.P./Copper Contaminated	Discharged to Sewer
	37	Water Rinse	A.P./Copper Contaminated	Discharged to Sewer

TABLE 3-10
NORTH LAS VEGAS WASTEWATER SOURCES
NEVADA TEST SITE, MERCURY, NEVADA
PAGE FOUR

Location	Unit I.D. No.	Process Bath	Bath Constituents	Disposition
Plating Shop (cont'd)	38	Copper Etcher	Chromic Acid Sulfuric Acid Copper Contaminants pH < 2	(1)
	39	Photo Resist Stripper	Acrylic Resins Ethanolamine 2-(2-Butoxyethoxy) Ethanol	Retained for Disposal
	40	Deburring Machine (filtered)	Copper Particulates Water	Discharged to Sewer
	41	Sink	Pumice Water Detergent	Discharged to Sewer
	42	Scrubber (filtered)	Copper Particulates Water	Discharged to Sewer
	43	Washer	Detergent Water	Discharged to Sewer
	44	Fusing Machine		No Discharge
	45	Orosene Gold Bath	Gold pH 4-4.5 Monopotassium Phosphate Cobalt Nickel Iron	Retained for Disposal

TABLE 3-10
NORTH LAS VEGAS WASTEWATER SOURCES
NEVADA TEST SITE, MERCURY, NEVADA
PAGE FIVE

Location	Unit I.D. No.	Process Bath	Bath Constituents	Disposition
Plating Shop (cont'd)	46	Nickel Sulfamate	Nickel Sulfamate Chloride Boric Acid pH 3.5-4.2	Retained for Disposal
	47	Spray Water Rinse	Gold and Nickel Bath Dragout	Discharged to Sewer
Screen & Image Rooms	48	(a) Ink Reducer (b) Riston Developer	Ferrous Sulfate 2-Butoxyethanol	Discharged to Sewer Discharged to Sewer
	49	Sink	Water	
Anodizing Room	50	Alkaline Detergent	Detergent	Retained for Disposal
	51	Water Rinse	Detergent Dissolved Aluminum	Discharged to Sewer
	52	Alum-Etch	Sodium Hydroxide Aluminum	Retained for Disposal
	53	Water Rinse	Alum Etch Contaminants	Discharged to Sewer
	54	Sulfuric Acid	2-10% Acid	Retained for Disposal
	55	Water Rinse	Acid Contaminants	Discharged to Sewer
	56	Water Rinse	--	Discharged to Sewer
	57	Black Anodizing Bath	DisazoChrome Complex pH 4-4.5	Retained for Disposal

TABLE 3-10
NORTH LAS VEGAS WASTEWATER SOURCES
NEVADA TEST SITE, MERCURY, NEVADA
PAGE SIX

Location	Unit I.D. No.	Process Bath	Bath Constituents	Disposition
Anodizing Room (cont'd)	58	Hot Water Seal	Anodizing Bath Contaminants	Discharged to Sewer
	59	Deoxide Bath	Sodium Fluoride Aluminum, Iron pH < 2	Retained for Disposal
	60	Water Rinse	Dioxide and Iridite Contaminants	Discharged to Sewer
	61	Iridite Chromating Bath	Chromic Acid Nitric Acid pH < 2	Retained for Disposal
Hybrid Lab	62	Acid Dip Bath	Any Diluted Acid	Discharged to Sewer
	63	Acid Dip Bath	Any Diluted Acid	Discharged to Sewer
	64	Sink for Water	Any Diluted Acid	Discharged to Sewer
	65	Solvent Cleaning Sink	Any Organic Solvent	Retained for Disposal
	66	Solvent Cleaning Sink	Any Organic Solvent	Retained for Disposal
	67	Solvent Cleaning Sink	Any Organic Solvent	Retained for Disposal
	68	Collecting Sump for Acid Dip Baths and Sinks	Dilute Acids Water Detergent pH 2-5	Discharged to Sewer
Detector Production	69	MB-12 Metal Cleaner	Chromic Acid Sulfuric Acid pH < 2	Retained for Disposal

TABLE 3-10
NORTH LAS VEGAS WASTEWATER SOURCES
NEVADA TEST SITE, MERCURY, NEVADA
PAGE SEVEN

Location	Unit I.D. No.	Process Bath	Bath Constituents	Disposition
Detector Production (cont'd)	70	Water Rinse Sink	MB-12 Contaminants	Discharged to Sewer
	71	Power Clean Metal Descaler	Sulfuric Acid Phosphoric Acid pH < 2	Retained for Disposal
	72	Water Rinse Sink	Power Clean Contaminants	Discharged to Sewer
	73	Electrolytic Cleaners	Phosphoric Acid	Retained for Disposal
Photo Lab (2)	74	Black and White Developing Bench w/o silver reclaimer	Developers Fixers	Discharged to Sewer
	75	Kodolith Processor	Developers Fixers	Discharged to Sewer
	76	Color Processing Sink for Film and Negatives	Developers Fixers Stop Baths	Discharged to Sewer
	77	C-41 Color Negatives Processing	Developers Fixers	Discharged to Sewer
	78	Same as 81		
	79	Color Print Machine	Developers Bleach Fixers	Discharged to Sewer
	80	Sink	Photo Process Contaminants	Discharged to Sewer
	81	Black and White Developer with Silver Reclaimer	Versatone 857 Fixer	Discharged to Sewer

TABLE 3-10
NORTH LAS VEGAS WASTEWATER SOURCES
NEVADA TEST SITE, MERCURY, NEVADA
PAGE EIGHT

Source: Maddox, 1986.

Notes:

- (1) The copper etcher has 2 internal rinse chambers.
The second rinse is discharged into a floor drain.
The bulk spent acid is handled as a hazardous waste.
- (2) The following chemicals are used in the Photo Lab:

Kodak Ektaprint - 2 (19 gal./mo. average)	Developer A - Benzyl Alcohol, 25%-30%
	Developer B - Hydroxylamine Sulfate, 15%-20%
	Developer C - 4-Amino-N-Ethyl-N-(8-Methanesulfonamidoethyl) M-Toluidine Sulfate monohydrate, 20%-25%
	Developer D - Potassium Hydroxide, 5%
	Potassium Carbonate 45%-50%
Kodak Flexcolor (8 gal./mo. average)	AR Developer A - N/A
	AR Developer B - Hydroxylamine Sulfate 20%-25%
	AR Developer C - 4-Amino-3-Methyl-N-Ethyl-N-(8-Hydroxyethyl) - Aniline Sulfate 50%-55%
	Bleach - Acetic Acid 5% - 10%
C41 (8 gal./mo. average)	Hardener & Replenisher A - Acetic Acid
	Hardener & Replenisher B - Aluminum Sulfate 20%-25%
	Hardener & Replenisher C - N/A
	Stabilizer - Formaldehyde 35%-40%
	Developer A - Hydroquinone 15%-20%
	Developer B - Hydroxylamine Sulfate 21%-26%
	Developer C - 4-(N-Ethyl-N-2-Hydroxyethyl) -2-Methylphenylene-Diamine Sulfate
	Hydroquinone 15%-20%
Kodalith Developer - (24 gal./mo. average)	Rapid Fixer - Acetic Acid 5%-10%

3.3.3.1 Sewage Lagoon Monitoring

NTS has taken infrequent samples of sewage lagoons in Areas 6, 12, and 23 for nonradiological analyses. The results of the analyses of these samples are presented in Table 3-11. The Area 6 sample is from the lagoons serving the Control Point. They were obtained from the files in the Industrial Hygiene Department at NTS (Bullock, 1987a). These data show that these lagoons would not consistently meet state requirements of 30 mg/l daily average and 45 mg/l daily maximum for either BOD or Total Suspended Solids (Porter, 1987). In addition sewage lagoons in Areas 6, 12, and 23 are sampled annually for radionuclides, as discussed in Section 3.3.3.3. No other sewage sampling is done at NTS. No Survey related sampling of the water in the sewage lagoons is planned.

3.3.3.2 Potable Water Monitoring

Monitoring of the potable water supply wells for inorganic chemicals is done every 3 years as required by the regulations in 40 CFR 141.23 under the Safe Drinking Water Act (SDWA). NTS also samples the water supply wells on a monthly basis for radioactivity. Only gross beta activity and tritium are determined on these samples. The results of these analyses are presented in Section 3.4.3, and a discussion of the characteristics of the various groundwaters on-site may be found in Section 3.4.1.3.

To comply with the radioactivity analytical requirements of the Safe Drinking Water Act, the potable water distribution systems are sampled quarterly. Analyses for gross alpha, gross beta, and tritium are performed quarterly and the results averaged for the year. The strontium-90 analysis is performed once a year on a composite of the four quarterly samples. These results for 1985 were all within the SDWA limits of 5 pCi/l for gross alpha, 15 pCi/l for gross beta, 20,000 pCi/l for tritium, and 8 pCi/l for strontium-90 (Gonzalez, 1986).

The NTS Maintenance Department personnel check the chlorine residual daily and make adjustments to the chlorine feeders, if necessary. Representatives of the NTS Industrial Hygiene Department check the systems for chlorine residual and collect the samples, which are sent to the state for bacteriological analysis monthly for the community water systems and quarterly for the non-community water systems. Records of these analyses back to 1980 were available in the Industrial Hygiene Office. Earlier records are in archive storage. The bacteriological results were all negative and therefore in compliance with the regulations of the State Division of Health. No reports of bacteriological tests are required to be submitted by NTS because the analyses are run by the state. No Survey related sampling of the potable water system is planned.

TABLE 3-11

**SANITARY SEWAGE LAGOONS
NEVADA TEST SITE, MERCURY, NEVADA**

Location	Date	pH (Standard Units)		Total Suspended Solids (mg/l)		Fecal Coliform (colony-forming units/100 ml)		BOD (mg/l)		COD (mg/l)		Dissolved Oxygen (mg/l)	
		Influent	Effluent	Influent	Effluent	Influent	Effluent	Influent	Effluent	Influent	Effluent	Influent	Effluent
Area 6	8-19-85	-	-	224	88	-	-	12	3	320	110	1.5	1.0
	8-26-85	-	-	104	76	-	-	90	76	500	206	3.9	4.5
	9-2-85	-	-	62	56	-	-	96	50	93	63	4.5	3.9
	9-9-85	-	-	70	35	-	-	108	20	140	6.0	4.9	5.6
	9-16-85	-	-	88	44	-	-	72	10	114	108	2.2	2.9
Area 12	1-26-82	7.2	7.4	221	144	2.5×10^7	2.4×10^5	191	113	487	255	-	-
	2-10-82	8.6	7.3	43	75	1.6×10^6	570	31	132	417	216	-	-
	3-10-82	7.1	9.3	43	74	1.4×10^6	350	141	69	125	148	-	-
	4-7-82	7.2	9.3	217	75	1.0×10^8	1.5×10^4	619	235	480	110	-	-
	6-3-82	6.1	7.6	441	87	1.7×10^8	3.5×10^4	430	72	2,310	608	-	-
	7-8-82	7.1	7.7	153	82	1.9×10^7	300	291	96	485	243	-	-
	8-3-82	6.0	8.0	718	8	3.3×10^7	3,000	360	111	3,756	154	-	-
	9-9-82	6.1	9.9	328	85	1.0×10^8	1,600	408	99	1,500	205	-	-
	8-19-85	-	-	990	100	-	-	357	3	680	150	0	1.9
	8-26-85	-	-	292	84	-	-	180	80	480	166	0	4.8
	9-2-85	-	-	700	88	-	-	930	120	840	173	0	4.8
	9-9-85	-	-	152	87	-	-	120	44	254	133	1.3	6.5
	9-16-85	-	-	480	106	-	-	198	38	374	111	0	5.9

TABLE 3-11
SANITARY SEWAGE LAGOONS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE TWO

Location	Date	pH (Standard Units)		Total Suspended Solids (mg/l)		Fecal Coliform (colonies/100 ml)		BOD (mg/l)		COD (mg/l)		Dissolved Oxygen (mg/l)	
		Influent	Effluent	Influent	Effluent	Influent	Effluent	Influent	Effluent	Influent	Effluent	Influent	Effluent
Area 23	1-26-82	7.6	7.8	157	29	1.4×10^6	900	228	24	945	111	-	-
	2-10-82	7.1	8.0	464	86	4.8×10^5	3,600	523	81	1,471	101	-	-
	3-10-82	8.4	8.5	60	55	1.4×10^5	600	150	57	172	188	-	-
	4-7-82	7.8	9.4	66	49	4.3×10^7	60	191	159	140	96	-	-
	5-6-82	7.6	8.6	290	41	1.2×10^9	4,400	420	93	1,240	223	-	-
	5-3-82	8.8	9.7	100	121	1.2×10^7	3,400	220	120	279	291	-	-
	7-8-82	8.0	9.9	55	166	5.9×10^6	4,000	162	138	262	304	-	-
	8-3-82	6.7	9.9	111	204	5.7×10^7	1,700	372	96	808	369	-	-
	9-9-82	7.5	9.7	79	141	2.9×10^7	2,400	158	90	258	277	-	-
	8-19-85	-	-	248	160	-	-	132	36	280	160	0	1.8
	8-26-85	-	-	180	166	-	-	258	118	420	260	0	1.2
	9-2-85	-	-	206	88	-	-	120	78	180	107	0	1.2
	9-9-85	-	-	172	68	-	-	114	68	199	152	0.4	5.4
	9-16-85	-	-	216	192	-	-	174	10	209	108	0.5	2.9

Source: Bullock, 1987a.

3.3.3.3 Radiological Monitoring

NTS maintains sixteen open reservoirs as a part of the principal water distribution systems discussed in Section 3.3.2.4. These reservoirs are used to supply water for industrial purposes. None of the reservoirs are used as drinking water supplies, although they may be supplied with water from wells that also supply water to the drinking water system. Fifteen locations were monitored for radionuclides on a monthly basis during 1985. The remaining reservoir was dry during 1985. All samples were analyzed for gross-beta activity. Table 3-12 presents the average 1985 annual gross-beta activity for the NTS open reservoirs. The beta activities ranged from a low of $<2.2 \times 10^{-9} \mu\text{Ci/ml}$ to a high of $25.1 \times 10^{-9} \mu\text{Ci/ml}$. DOE does not have a Derived Concentration Guide (DCG) for gross beta activity. However, for comparison, it may be assumed that the activity is strontium-90, which has one of the lowest DCGs at $1 \times 10^{-6} \mu\text{Ci/ml}$. The highest observed gross-beta activity ($25.1 \times 10^{-9} \mu\text{Ci/ml}$) is 2.5 percent of the DCG. DCGs apply to drinking water. Although the reservoirs are not drinking water sources, this comparison is useful to illustrate the relatively low concentrations of radionuclides present in the reservoirs. (Gonzalez, 1986).

NTS also reported that the highest tritium level reported at the 15 reservoirs sampled was $1.1 \times 10^{-6} \mu\text{Ci/ml}$ at the Area 2 Mud Plant Reservoir. This is 0.06 percent of the DOE DCG for drinking water. Only two measurements yielded detectable plutonium; these were from the Area 5 Reservoir. The concentrations were reported as 1.1×10^{-10} and $9.7 \times 10^{-11} \mu\text{Ci/ml}$. The higher of these is 0.04 percent of the DOE DCG for drinking water.

NTS also conducted sampling of contaminated ponds at eight locations during 1985. Seven ponds are located in Area 12 and serve as impoundments for water seepage from tunnel test areas discussed in Section 3.4.2.3 and 4.1.2.1.2; the other pond is the Decontamination Pond (also referred to as the Yucca Waste Pond) discussed in Section 3.3.2.1 in Area 6. The annual averages of tritium and gross-beta concentrations observed in the contaminated ponds are presented in Table 3-13. All of the Area 12 ponds had average tritium concentrations in excess of the DOE DCG for tritium in drinking water ($2 \times 10^{-3} \mu\text{Ci/ml}$). The average tritium in the Area 6 pond was 0.18 percent of the DCG. The average gross-beta activities for the three Area 12 N-tunnel ponds and the three Area 12 T-tunnel ponds sampling locations exceed the DOE DCG for strontium-90 ($1 \times 10^{-6} \mu\text{Ci/ml}$). Since none of these ponds are used as drinking water sources or discharge into any surface water bodies that may be used as drinking water sources, the DCGs do not actually apply but are provided here for reference (Gonzalez, 1986).

TABLE 3-12

**AVERAGES OF OPEN RESERVOIR DATA FOR GROSS BETA ACTIVITY
NEVADA TEST SITE, MERCURY, NEVADA**

Station	Gross Beta Yearly Average (1985)
	(X 10 ⁻⁹ μ Ci/ml)
Area 2 Well 2 Reservoir	5.8
Area 2 Mud Plant Reservoir	6.4
Area 3 Well A Reservoir	8.4
Area 3 Mud Plant Reservoir	7.7
Area 5 Well 5B Reservoir	10.3
Area 5 Well Ue5c Reservoir	6.1
Area 5 Reservoir	25.1
Area 6 Well 3 Reservoir	7.4
Area 6 Well C1 Reservoir	6.6
Area 18 Camp 17 Reservoir	< 3.7
Area 18 Well 8 Reservoir	6.5
Area 19 Well 19c Reservoir	< 2.2
Area 20 Well 20A Reservoir	< 3.5
Area 23 Swimming Pool	6.2
Area 25 Well J-11 Reservoir	4.4

Source: Gonzalez, 1986.

TABLE 3-13

**1985 ANNUAL CONTAMINATED POND AVERAGE
RADIONUCLIDE CONCENTRATIONS ($\mu\text{Ci/ml}$)
NEVADA TEST SITE, MERCURY, NEVADA**

Station	Tritium Yearly Average	Gross Beta Yearly Average
Area 6 Yucca Waste Pond	3.6×10^{-6}	3.6×10^{-7}
Area 12 N Tunnel Upper	4.1×10^{-3}	6.7×10^{-6}
Area 12 N Tunnel Middle	2.9×10^{-3}	4.3×10^{-6}
Area 12 N Tunnel Lower	2.9×10^{-3}	4.4×10^{-6}
Area 12 G Tunnel Waste	5.9×10^{-3}	6.7×10^{-8}
Area 12 T Tunnel Upper (1)	1.3×10^{-2}	1.4×10^{-5}
Area 12 T Tunnel Middle (1)	1.3×10^{-2}	1.9×10^{-5}
Area 12 T Tunnel Lower (1)	1.2×10^{-2}	1.6×10^{-5}

Source: Gonzalez, 1986.

(1) In the source document these are listed as Mint Lake rather than T Tunnel Ponds.

There are six other ponds on the NTS that were analyzed for radionuclide concentrations in 1985. These are the final effluent ponds from the Area 12, Area 23, and the Area 6 Yucca Lake Domestic Sewage Systems as well as Yucca Lake Sewage Lagoons I and II and the Yucca Lake Steam Cleaning Pond No. 2. The highest annual average gross-beta activity was 3.8×10^{-8} $\mu\text{Ci/ml}$. This is 4 percent of the DOE DCG for strontium-90. Plutonium and tritium concentrations were below the minimum detectable concentrations at all locations (Gonzalez, 1986).

Because there are no off-site surface waters that receive waters from the NTS, there is no off-site radiological surface-water monitoring.

3.3.3.4 Other Surface Water Monitoring

Monitoring of surface waters at NTS for parameters other than radionuclides is not done on a routine basis. The results shown in Table 3-14 were obtained as a result of a site study conducted in June of 1986 to determine if mixed (i.e., radioactive and hazardous) wastes were being generated at NTS. These samples were taken from the Area 6 Decontamination Pond and the effluents and ponds at E, N, and T Tunnels. A scan for the complete set of toxic semivolatile and volatile organic compounds and inorganic metals as listed in 40 CFR 122 (The National Pollutant Discharge Elimination System) was run. Results are listed only for those compounds which were determined at concentrations at or above the detection limit for the procedures used. Of those parameters for which drinking water standards have been set, only lead was found in one sample at a concentration greater than the primary drinking water standard of 0.05 mg/l, and only iron and manganese were detected in other samples at concentrations higher than the secondary drinking water standards of 0.3 and 0.05 mg/l respectively. The secondary drinking water standards control contaminants in drinking water that primarily affect the aesthetic qualities rather than the health effects of a water supply. Health effects are regulated by the primary standards. Since none of these ponds are used for drinking water, these standards are only provided for reference for the reader.

3.3.3.5 North Las Vegas Monitoring

Under the terms of the permit issued in August 1985, the NLVF is required to supply quarterly reports of the monitoring of its discharges to the City of North Las Vegas. To satisfy this requirement, NLVF submitted reports in December 1985 for the months of September, October, and November 1985 and in March 1986 for the months of December 1985, January, and February 1986. These reports listed the estimated amounts of chromium and nickel discharged from the facility in grams for each month. During a visit on May 13, 1986, by representatives of the City of North Las Vegas and the

TABLE 3-14

MIXED WASTE STUDY ANALYSES
NEVADA TEST SITE, MERCURY, NEVADA

	Area 6 Decon Pond	T-Tunnel		E-Tunnel		N-Tunnel	
		Effluent	Pond 1	Pond 2	Effluent	Pond 1	Pond 2

Semivolatile Organics (µg/l)

Bis (2 ethyl/hexyl) phthalate	100	--	--	--	--	--	--
----------------------------------	-----	----	----	----	----	----	----

Volatile Organics (µg/l)

Methylene chloride	45	3,450	9,300	1,800	--	--	--
Chlorobenzene	250	--	--	--	--	--	--
Acetone	130	--	--	--	--	--	--
Xylenes (Total)	36	--	--	--	--	--	--

Metals (mg/l)

Aluminum	0.5	--	--	--	2.5	2.0	6.0	5.5
Arsenic	--	--	.002	--	--	--	--	--
Barium	0.5	0.1	0.1	--	0.4	0.2	0.4	0.3
Calcium	1.75	2.10	0.80	1.90	5.00	2.20	2.13	1.85
Chromium	0.04	--	--	--	0.02	0.04	0.03	--
Copper	0.06	--	--	--	--	--	--	--
Iron	0.5	0.1	--	--	0.8	0.8	1.3	1.4
Lead	0.10	--	--	--	--	--	--	--
Lithium	1.0	--	--	--	0.051	--	.08	.08
Magnesium	1.50	0.19	0.06	0.12	1.85	0.49	1.50	1.45
Manganese	0.03	0.02	--	--	.02	.02	.06	.06
Potassium	42.0	1.18	0.52	0.98	14.0	13.0	16.5	15.5
Selenium	--	--	.001	.001	.001	--	--	--
Sodium	3,600	800	900	1,200	1,000	1,000	1,000	1,000
Strontium	0.05	--	--	--	.05	--	.05	.05

Source: Bicker, 1986.

State of Nevada, the format of the report was discussed and the NLVF was requested to report estimated discharges in milligrams per liter (mg/l). However, at the time of the on-site portion of the Survey, NLVF had discontinued sampling for the quarterly reports and therefore had not implemented the change in report format (Kessler, 1987a).

Furthermore, Section 403.12(e) in the General Pretreatment Regulations for Existing and New Sources of Pollution (40 CFR 403) requires dischargers to submit to the Control Authority (in this case, the City of North Las Vegas) a report indicating the nature and concentration of pollutants in the effluent which are limited by a categorical pretreatment standard to which the discharge is subject. Because of the operations at NLVF (printed circuit board manufacture, anodizing, etc.), NLVF is required to comply with the regulations applicable to the Metal Finishing Point Source Category (40 CFR 433). Cadmium, copper, lead, silver, zinc, cyanide and total toxic organics (TTO) are also limited by 40 CFR 433 and therefore should have been included in the monitoring reports, in addition to chromium and nickel.

In addition to the above reporting requirements, a baseline monitoring report was also to be submitted to the City. To comply with this requirement NLVF took grab samples from the printed circuit board plating shop, the aluminum anodizing shop, and the detector production shop on three separate days. The results of this first round of analyses (Table 3-15) were reported to the City on October 8, 1986. However, upon reviewing the data, the facility believed that the results may not have been representative of true conditions because of the intermittent operation of the processes served. NLVF took additional samples (5 to 7 hour composites on 3 separate days over a 2 week period) from the printed circuit board and anodizing shops and reported these on January 12, 1987. The results of these analyses are shown in Table 3-16. Samples were not taken at the descaling/ electropolishing operation in the detector production shop because a scheduled change in chemicals used in that operation had not taken place. Because of the wide variation in the results obtained from the printed circuit board samples, yet another round of additional samples (composite samples for 20 consecutive working days) was taken at this location. A summary of these results, shown in Table 3-17, indicated that the daily maximum limitations for chromium, copper, lead, and nickel and the monthly average limitations for chromium, copper, and lead were being exceeded. As a result of demonstrated continued noncompliance evidenced by these results, NLVF sent a letter to the city on March 31, 1987, advising it that a consultant would be hired to investigate the problems.

TABLE 3-15

FIRST ROUND BASELINE MONITORING DATA (mg/l)
NEVADA TEST SITE, MERCURY, NEVADA

Parameter	Printed Circuit Plating			Aluminum Anodizing			Detector Production			Discharge Limits	
	1	2	3	1	2	3	1	2	3	Daily Maximum	Monthly Average
Cadmium	0.013	0.094	0.030	<0.005	0.006	<0.005	<0.005	<0.005	<0.005	0.69	0.26
Chromium (Total)	--	--	--	0.28	0.80	2.3	22.0	0.034	9.9	2.77	1.71
Copper	--	--	--	<0.05	<0.05	<0.05	1.4	0.067	73	3.38	2.07
Lead	<0.10	0.13	2.6	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	0.69	0.43
Nickel	--	--	--	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	3.98	2.38
Silver	--	--	--	<0.01	<0.01	<0.01	0.016	<0.01	<0.01	0.43	0.24
Zinc	--	--	--	0.012	0.14	0.020	0.60	<0.01	0.33	2.61	1.48
Cyanide (Total)	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	1.20	0.65
Cyanide (Amenable to Chlorination)	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	0.01	<0.01	<0.01	--	--
Total Toxic Organics	--	--	--	--	--	--	--	--	--	2.13	--

Source: Beck, 1986.

TABLE 3-16

**SECOND-ROUND BASELINE MONITORING DATA (mg/l)
NEVADA TEST SITE, MERCURY, NEVADA**

Parameter	Printed Circuit Plating			Aluminum Anodizing			Discharge Limit	
	1	2	3	1	2	3	Daily Maximum	Monthly Average
Cadmium	0.0099	0.0198	0.0139	0.0059	<0.005	0.0059	0.69	0.26
Chromium (Total)	42.8	0.070	<0.05	0.341	0.250	0.391	2.77	1.71
Copper	20.1	0.353	1.43	<0.02	<0.02	<0.02	3.38	2.07
Lead	0.667	0.120	0.070	0.059	<0.05	0.059	0.69	0.43
Nickel	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04	3.98	2.38
Silver	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	0.43	0.24
Zinc	0.0997	0.0179	0.0359	0.13	0.122	0.142	2.61	1.48

Source: Tuma, 1987.

TABLE 3-17

**PRINTED CIRCUIT PLATING SHOP
20-DAY BASELINE MONITORING RESULTS (mg/l)
NEVADA TEST SITE, MERCURY, NEVADA**

Parameter	Maximum	Minimum	Average	Discharge Limit	
				Daily Maximum	Monthly Average
Cadmium	0.04	BDL ⁽¹⁾	0.07	0.69	0.26
Chromium (Total)	16.1	BDL	2.91	2.77	1.71
Copper	70.44	0.2	8.52	3.38	2.07
Lead	4.50	BDL	1.60	0.69	0.43
Nickel	9.25	BDL	0.67	3.98	2.38
Silver	0.08	BDL	0.015	0.43	0.24
Zinc	0.11	BDL	0.04	2.61	1.48

Source: Kesler, 1987b.

(1) BDL = Below Detection Limit.

3.3.4 Findings and Observations

3.3.4.1 Category I

None.

3.3.4.2 Category II

1. Unpermitted Discharges of Wastewater At the time of the on-site portion of the Survey, permits had not been obtained from the State of Nevada for any wastewater discharges at NTS.

The Nevada Water Pollution Control Law (Nevada Revised Statutes, Title 40, Public Health and Safety, Chapter 445) requires that a permit be obtained for the discharge of pollutants to any waters of the state or to any treatment works or for the injection of fluids through a well into any waters of the state. The law also requires that permits be obtained prior to beginning construction of a treatment works. Waters of the state include, but are not limited to, all streams, lakes, ponds, impounding reservoirs, marshes, watercourses, waterways, wells, springs, irrigation systems, and drainage systems; and all accumulations of water, surface and underground, natural and artificial. Treatment works are any devices or systems used in the storage, treatment, recycling and reclamation of municipal sewage or industrial wastes of a liquid nature.

Discharges regulated under the National Pollutant Discharge Elimination System are administered by the State Department of Conservation and Natural Resources, Division of Environmental Protection whereas discharges to injection wells and individual sewage disposal systems are administered by the Division of Health.

The state program has been approved by the Administrator of the EPA; therefore, state-issued permits are sufficient to satisfy the requirements of the Federal regulations.

The following listing of discharges that may require permits is divided into four groups: discharges to land surfaces and/or drainage ditches; discharges to injection wells; discharges to sumps, lagoons or ponds; and discharges to septic tanks and leach fields. These groupings are based on the presumption that different groups within the state regulatory agencies will be administering the permits. In addition some of the facilities (sumps, lagoons, etc.) receiving these discharges may also require RCRA permits because they are surface impoundments used

to treat, store, or dispose of hazardous wastes. See Section 4.1.3.2 for a finding regarding lack of RCRA permits and Section 4.1.2.1 for a discussion of these facilities which may be handling hazardous wastes.

Survey-related S&A was recommended for a number of these sites. However, because of recent resource reallocations, the sites marked with an asterisk (*) were eliminated from the NTS S&A.

- Direct discharges to land surfaces and/or drainage ditches.
 - Three discharge points from the Area 23 Fleet Operations Facility (vehicle maintenance) enter a drainage ditch on the east side of the Mercury Highway By-Pass. Solvents and oil and grease could be present in these streams.*
 - Three or four times per year, drums (55-gallon) of aqueous based cutting fluids are emptied onto the ground north of the Area 6 Machine and Welding Shop (Building 6-623). These wastes may contain metals from the machining operations.
 - Water used to wash off the trucks that mix epoxy-based stemming material (containing toluene diisocyanate) simply runs onto the ground. This occurs where ever there is a stemming operation using this material.
- Wastewaters from steam jenny operations (steam cleaning of equipment) in Area 12 (Fleet Operations Area) and Area 3 (on east side of Angle Road) are not collected but flow onto the ground. Oil and grease may be present in these wastes.
- Potentially radioactive water from the Radionuclide Migration Study Well 25 is discharged into a ditch and then flows into a seepage/evaporation pond in Area 5. The pond (located in the Frenchman Lake Bed) is frequently dry.
 - In addition to the above discharges directly to ditches and/or land surfaces, the ponds or lagoons listed below will overflow to drainage ditches or the ground surface if their capacity to contain their influent flow is exceeded.

- Discharges to sumps, ponds and/or lagoons.

- The wastewater pit at the Area 2 photo skid was dry at the time of the on-site portion of the Survey. It receives wastes from the photographic developing laboratory when it is operating.*
- There are two sewage lagoons in Area 2. Domestic sewage flows through them in series (the effluent from the first lagoon enters the second lagoon). At the time of the on-site Survey, evaporation and seepage from the first lagoon was sufficient to handle the entire flow, and there was no overflow into the second lagoon.
- Steam cleaning effluent Ponds I and II. Steam cleaning effluents from the Area 6 Machine and Welding Shop (Building 6-623) and the Heavy Duty Repair Shop (Building 6-800), both of which use corrosives and RCRA-listed solvents, are discharged to two separate unlined ponds at Yucca Lake. Pond II which receives effluent from Building 6-800 also may overflow during storm events. The water level of the pond was near the top of the berm at the time of the on-site portion of the Survey.
- Sewage Lagoons I and II and the domestic sewage lagoons at Yucca Lake in Area 6 (see Section 3.3.2.2). These lagoons should receive discharges only from sanitary systems; however, it is not known if cross-connections exist or if wastes are being disposed of into sanitary sinks and drains that discharge into these lagoons.*
- The Area 6 Decontamination Pond receives wastes containing organic solvents and radioactivity from this decontamination facility. Flow to the pond in 1986 was estimated to be 3.6×10^6 gallons (Clark, 1987).
- The four sewage lagoons near the helicopter pad in Area 6, which receive the sanitary wastes from CP-1.
- The two sewage lagoons south of CP-1 and west of Mercury Highway in Area 6. These lagoons are receiving effluent from unknown sources.*
- The drain pit in the Well 3 Yard at Area 6, which receives the discharge from truck washing activities. This discharge is likely to contain oil and grease in addition to the dirt that accumulates on the trucks.*

- The sewage pit at the LLNL Technical Facilities in Area 11 receives both sanitary sewage and wastes from photographic developing at this site.*
 - Wastewater from the Area 12 Construction Shops (Building 12-8) and from the Motor Pool Equipment Maintenance Shop (Building 12-16), which use RCRA-listed solvents, is discharged to an unlined pond (i.e., the Area 12 industrial wastewater sump). There is evidence that this pond also overflows sometimes via a discharge pipe onto the land.
 - The sanitary sewage from Area 12 flows to four primary lagoons, then to two evaporation/seepage ponds operated in series. At the time of the on-site Survey, the final pond was not receiving flow, although there was a small amount of water accumulated in the bottom of the pond.
 - The 16 ponds that receive the water discharged from the tunnels in Area 12 can contain both solvents and radioactivity, as discussed in Sections 3.4.2.3 and 4.1.2.1.2.
 - Three lagoons/ponds in the system at the Main Gate in Area 22 receive sanitary sewage from the offices at that location.
 - The Area 23 sewage system consists of six primary lagoons equipped with aerators followed by four evaporation/seepage ponds, which operate in series. The sewage system receives flows from laboratories and maintenance operations at Mercury and therefore may contain hazardous (i.e., RCRA-listed) substances as well as sanitary sewage.
 - Most of the facilities in Area 25 were inactive at the time of the on-site Survey. There are sanitary sewage lagoons south of the Engine Test Stand (2), south of Test Cell C (2), south of the Reactor Control Point (3), and south of the Central Support Area (2). Inactive waste facilities in this area are discussed in Section 4.5.*
- Discharges to Injection Wells

Wells are defined by both state and Federal regulations as being a bored, drilled, or driven shaft, or a dug hole, whose depth is greater than the largest surface dimension. Injection wells are "wells" into which fluids are being injected. Therefore, many sumps, pits, and/or holes used for disposal of liquid wastes at NTS may be classed as injection wells and thus may require permits under the State's Underground Injection Control Program.

- The pit at the Area 1 Subdock Steam Cleaning Pad receives runoff from the cleaning operation. This pit is 24 inches in diameter and is deeper than it is wide.*
- The LLNL Post-Shot Facility Building in the Area 2 support facilities has a pit in the southwest portion of the building. This pit receives wastewaters generated in servicing drill-back equipment.*
- Cleaning wastes generated at the Area 2 Cutter Rebuild Shop contain RCRA-listed solvents and are discharged down two shallow wells. One is located inside the shop where the cutters are cleaned, and the other is located outside the shop where the rollers are cleaned. Both wells are reportedly 48 feet deep with a 20-inch casing below a 52-inch casing.
- Water entering the Steam Cleaning Control Pad Sump at the Area 3 post-shot facility reportedly drains to an 88-inch diameter, 100-foot deep hole that is located under a 3/8-inch steel plate under the wooden parts storage rack just south of the pit.*
- Two blow-off preventer servicing cellars in Area 3 collect wastewaters from the cleaning and servicing of the equipment used in drill-back operations. The contents of these cellars are pumped out twice a month to a 7-foot diameter casing adjacent to the lineman's shop next door.*
- The Radionuclide Migration Study on Pahute Mesa pumped 1×10^6 gallons of water into post-shot hole U20ac from 1983 to 1985. It is planned to pump additional water from UE20n into U20av as a part of this study.
- Disposal of radioactive liquid wastes is discussed in Section 4.1.2.1.2. The J-6 classified waste disposal hole in Area 3 receives washwater from contaminated drilling equipment. This hole received 6,600 gallons in the 2-1/2 years from June 1984 to December 1986. Hole U8d in Area 8 received 80,000 gallons during the same time period. In Area 9, hole U91TS-Y30-PSI is also used for disposal of contaminated liquid wastes.

- Discharges to Septic Tanks and Leach Fields

Septic tanks are watertight, covered receptacles that receive sewage, separate the solids from the liquid, digest the organic matter, provide storage space for the digested solids, and allow for the discharge of the clarified liquid. Leachfields used for the distribution of liquids from sewage systems are preceded by a septic tank, whereas leachfields used for distributing process liquid wastes may or may not be preceded by a settling tank, depending upon the presence of suspended solids in the wastewater.

- Active septic tanks at NTS are listed in Table 3-18.
- The Building 650 leachfield in Area 23 that receives flows from the radiochemistry laboratories, the decontamination shower, the photographic laboratory, and the silver recovery unit. Chlorinated solvents, acids, and caustics are disposed of into laboratory sinks.
- Inactive leachfields, which were used for radioactive and other nondomestic sewage waste disposal in Areas 6, 25, and 26, are discussed in Section 4.5.

3.3.4.3 Category III

1. Discharge to POTW Exceeds Guidelines. Monitoring by the NLVF has shown that the discharge to the City of North Las Vegas sewer system consistently exceeds the limits for chromium, copper, and lead as set forth in 40 CFR 433 (Tables 3-15 through 3-17). During the 20 continuous working days on which the data presented in Table 3-17 were collected, the daily maximum limitation for chromium (2.77 mg/l) was exceeded 7 times, with the highest value being 16.1 mg/l; the daily maximum limitation for copper (3.38 mg/l) was exceeded 9 times, with the highest value being 70.44 mg/l; the daily maximum limitation for lead (0.69 mg/l) was exceeded 14 times, with the highest value being 4.5 mg/l; whereas the daily maximum limitation for nickel (3.98 mg/l) was exceeded only once by a value of 9.25 mg/l, with the next highest value being 1.0 mg/l (25% of the limit). As can be seen in the table, the average concentration of the 20 samples also exceeded the monthly average limitations for chromium, copper, and lead. These metals come from the rinse waters at NLVF. The facility has advised the city of this, and NLVF is working with a consultant to characterize and remediate the problem. A treatment unit to bring NLVF into compliance is expected to be installed and operational by the end of CY1987 or early in CY 1988 (Kesler, 1987c).

TABLE 3-18

NEVADA TEST SITE SEPTIC TANKS
NEVADA TEST SITE, MERCURY, NEVADA

Area	Number of Septic Tanks	Tank Locations
1	1	Subdock, east of Weld Shop
2	2	New Annex, west end of Cable Yard
3	2	Southwest of Cafeteria, Northeast of LASL Building
5	6	Building 5-6, Liquified Gaseous Fuels Spill Test Facilities, CCDAS Building
6	10	Building 6-619, Building 6-175, Building 6-762, Building CP-400, Building CP-95 and 90, Building CP-100, Building CP-162, Building CP-10, Building 6-3f1, DOD Facility
11	1	Tweezer Facility, Building 11-1
15	1	EPA Farm
20	1	Support Facilities
22	2	Desert Rock Weather Station, Desert Rock Airport
23	1	Building 1010
25	7	Test Cell A; Test Cell C; Engine Test Stand #1; RMAD, southeast of Warehouse; EMAD, south of EMAD; Fire Station; CP
26	6	Building 2101, Building 2103, Building 2105, Building 2201, Building 2203, Building 2205
27	4	5100 Series Buildings, 5200 Series Buildings, Building 5310, Building 5430
28	2	Bren Gate, Bren Tower

Source: Skivers, 1987.

2. Wastewater Lagoons located in drainage swales can be flooded or washed away during heavy storm events. This would allow the contents of the lagoons to be spread over the adjacent desert, where it would evaporate or percolate into the soil. The magnitude of the resulting environmental problem would of course depend upon the contents of the lagoon at the time of flooding. However, it is expected that the impact would be minimal, given the arid climate and resulting limited biotic population. As discussed in Section 3.3.2.3, the probability of such an occurrence has to be determined specifically for any particular site. Lagoons at NTS that appear to be in such areas are

- Area 12 Tunnel Ponds and sewage lagoons
- The Area 23 sewage ponds
- The lagoons south of CP-1 in Area 6

3. Contamination of off-site soil with lead particles is possible at NLVF. Runoff from the paved area adjacent to Building A-1, which is used as a lead storage area, could flow onto off-site, unpaved, ground. While it is unlikely that there is enough precipitation to solubilize a sufficient amount of lead to contaminate the adjacent ground, it might be possible that particulates have been transported to this area and accumulated over time. Survey-related sampling and analysis was recommended for this off-site area. However, because of recent resource reallocations, they were eliminated from NTS sampling and analysis.

3.3.4.4 Category IV

1. Lack of a monitoring program. Neither NTS nor the NLVF are monitoring wastewater discharges on a routine basis.

- Data for parameters other than radionuclides are sparse for wastewater discharges at NTS because no discharge permits with associated monitoring requirements were in place at NTS at the time of the on-site Survey.

Data is only obtained for special studies. One such study (discussed in Sections 3.3.3.4, 3.4.2.3, and 4.1.2.1.3) was conducted in 1986 to determine whether the Tunnel Ponds in Area 12 and the Decontamination Pond in Area 6 contained mixed (hazardous and radioactive) wastes. Other tests were run in 1982 and 1985 (Section 3.3.3.1) to determine the effectiveness of the sewage treatment lagoons in Areas 6, 12 and 23.

- The North Las Vegas Facility received a permit August 9, 1985, for discharges to the city sewer system. One of the conditions contained in the permit was that quarterly reports would be submitted to the City of North Las Vegas. These reports would include the analysis of the chromium and nickel in the wastewater discharge to the sewer, an estimate of the amount of chromium and nickel used by the facility in the three-month period, and the amount of water used by the facility in the three month period. NLVF submitted reports in December 1985 for the months of September, October, and November 1985 and in March 1986 for the months of December 1985 and January and February 1986. These reports listed the estimated amounts of chromium and nickel discharged from the facility in grams for each month. During a visit on May 13, 1986, by representatives of the City of North Las Vegas and the State of Nevada, the format of the report was discussed and the NLVF was requested to report estimated discharges in milligrams per liter (mg/l). However, at the time of the on-site portion of the Survey, NLVF had discontinued sampling for the quarterly reports and therefore had not implemented the change in report format (Kesler, 1987a).

Furthermore, Section 403.12(e) in the General Pretreatment Regulations for Existing and New Sources of Pollution (40 CFR 403) requires dischargers to submit to the Control Authority (in this case, the City of North Las Vegas) a report indicating the nature and concentration of pollutants in the effluent which are limited by a categorical pretreatment standard to which the discharge is subject. Because of the operations at NLVF (printed circuit board manufacture, anodizing, etc.), the facility is required to comply with the regulations applicable to the Metal Finishing Point Source Category in 40 CFR 433. Cadmium, copper, lead, silver, zinc, cyanide, and total toxic organics (TTO) are also limited by 40 CFR 433 in addition to chromium and nickel and therefore should have been included in the monitoring reports.

2. Lack of Backflow Preventer Inspection and Maintenance Program. Contamination of potable waters may be possible because neither the test site nor the NLV facility has a backflow preventer inspection and maintenance program.

Backflow preventers are installed on process water lines to prevent the accidental contamination of potable water lines by the process water in the event that there is a pressure loss in the potable water distribution system. At the North Las Vegas facility photo laboratory, a backflow preventer that had been installed originally was replaced by check valves. Check valves are not usually acceptable as a substitute for a properly operating backflow preventer under local regulations. An inspection and maintenance program would have discovered and corrected this change.

PRELIMINARY

3.4 Groundwater (Hydrogeology)

3.4.1 Background Environmental Information

3.4.1.1 Site-Specific Geology

The Nevada Test Site (NTS) lies in the southern part of the Great Basin Section of the Basin and Range physiographic province. The NTS and nearby areas occur in a broad topographic slope that separates high, topographically closed basins of central Nevada from low, connected basins of the Amargosa Desert-Death Valley drainage system (Sinnock, 1982). Topographically high areas of the NTS are dominated by a large volcanic plateau, Pahute Mesa, which is bounded on the south by a roughly circular, extinct volcano at Timber Mountain (see Figure 2-4 in Section 2.0). The eastern edge of Pahute Mesa is formed by Rainier Mesa. Jackass Flats, Yucca Flat, and Frenchman Flat are sub-basins within a larger basin that occupies the eastern and southern portions of the NTS. The sub-basins are separated by small, irregularly oriented ranges. Peaks within these ranges rarely exceed 6,000 feet in elevation and range crests generally rise only 500 to 1,500 feet above the basin floor. In contrast, the Pahute Mesa-Timber Mountain uplands exceed 7,000 to 8,000 feet in elevation and rise more than 2,000 feet above the surrounding basins (Sinnock, 1982). Thus, the NTS can be divided roughly into two major areas--the mesas in the northwestern portion and the flats in the eastern and southern portions.

Alluvial fans characteristically occur at the bases of the ranges. These cone-shaped deposits form where intermittent streams from the mountains reach the lowlands. These fans are generally featureless, gently concave slopes descending toward a central basin drainage line or playa. Jackass Flat drains to the Amargosa Desert, but Yucca Flat and Frenchman Flat are closed basins containing playas. These playas (dry lake beds) are mud flats where broad, shallow sheets of water gather and quickly evaporate. A million years ago, in Pleistocene time, these lakes held water on a more permanent basis, and lake-deposited sediments are present beneath the surficial mud flats.

The general geology of the test site can be described in terms of three major rock units. These are (1) complexly folded and faulted sedimentary rocks of Paleozoic age overlain at many places by (2) volcanic tuffs and lavas of Tertiary age, which in the valleys or flats are covered by (3) alluvium of late Tertiary and Quaternary age, which was derived from erosion of the nearby hills of Tertiary and Paleozoic rocks (ERDA, 1977). The volcanic rocks in the valleys are displaced along steeply dipping, normal faults of late Tertiary age; the overlying alluvium is rarely faulted, but a few prominent faults can be observed.

The sedimentary rocks of Paleozoic age are many thousands of feet thick and are of mostly carbonate rocks (limestone and dolomite) in the upper and lower parts, separated by a middle section of shale and quartzite. The volcanic rocks of Tertiary age are predominantly tuffs (rocks formed of compacted volcanic fragments which cooled in air and settled to the ground) and lavas (rocks formed from liquid which cooled on the ground surface). The thickness of these volcanic rocks varies from place to place at the NTS because of erosion or nondeposition. Alluvial materials can attain thicknesses of 600 to 900 meters (2,000 to 3,000 feet) in the central portion of the flats.

The alluvium in Yucca Flat is vertically offset along a predominant north-south trending fault, the Yucca Fault. The Yucca Fault is noticeable as bumps in the unpaved roads or abrupt changes in topography in various parts of northern and central Yucca Flat. The alluvium at the surface is geologically young, and therefore the changes in topography indicate that movement has occurred along the Yucca Fault sometime during the last few thousands to tens of thousands of years (Sinnock, 1982). Considerable effort has been devoted by research scientists to the estimation of the probability of occurrence of geologic phenomena, such as renewed movement along faults with consequent earthquakes. Other phenomena that have been considered are renewed volcanic activity and climatic changes resulting in increased rainfall. Such estimations have been conducted to demonstrate the suitability of the area for high-level (off-site) and low-level (on-site) radioactive waste disposal.

The southern Nevada region is generally characterized as an area of moderate earthquake activity. Approximately 4,000 earthquakes were recorded between 1900 and 1974 within an area of 95,000 square miles (246,000 square kilometers) centered on the NTS. Only 21 of these earthquakes had magnitudes of 5.5 or larger on the Richter scale. The closest event to the test site had a magnitude of 5.6 and occurred in 1949 about 82 miles (132 kilometers) to the west. The largest event on record was the Owens Valley earthquake of 1872, which had a magnitude of 8.3 and was located 100 miles (160 kilometers) west of the NTS (ERDA, 1977).

Most of the seismic events located on the NTS itself are the result of underground nuclear tests and aftershocks related to these tests. An underground nuclear explosion produces an initial seismic signal, which has characteristics similar to those of an earthquake and which can be detected worldwide with appropriate seismometers. All underground nuclear explosions are followed by a series of small earthquakes, which may persist for hours or days, and sometimes up to several months. For smaller-yield events, these aftershocks usually cease with cavity collapse. Studies of megaton-yield tests (conducted prior to the 1974 Threshold Test Ban, which limits tests to a maximum yield of 150 kilotons) showed the following: (1) 95 percent of the induced earthquake activity is confined to within 8.7 miles (14 kilometers) of ground zero and to within 3 miles

(5 kilometers) of the surface, (2) the strongest aftershock is usually two or more magnitude units less than the explosion, and (3) the location of aftershocks appears to be controlled by preexisting geologic structures such as faults. Stress is apparently relieved by movement along preexisting faults within the immediate vicinity of the explosion site. Except for this immediate area, it appears that the underground nuclear testing program does not produce a detectable influence on the natural pattern of earthquake activity (ERDA, 1977).

Effects within the immediate area of an underground test at Yucca Flat include the collapse of rocks into underground cavities and the formation of subsidence craters. The ground surface is cracked within the subsidence crater and for several tens of meters outside the crater rim. These cracks are radial and circumferential, and are related to uplift of the ground surface at the time of the explosion and to the subsequent collapse forming the subsidence crater. Craters in Yucca Flat range from about 40 feet to 1,500 feet in diameter (Sinnock, 1982). The cavity is commonly connected to the surface crater by a rubble chimney. Cavity diameters generally range from about 30 to 120 feet and chimney heights from 30 to 1,500 feet. Intense fracturing around the cavity extends about 2 to 4 times the radial distance from the explosion point to the cavity wall. The cavity commonly contains glassy material intermixed with rock rubble, whereas the chimney is rock rubble only. The chimney may not extend to the surface, particularly for deep explosions in consolidated rocks. Neither craters nor radial and circumferential fracture patterns develop for Pahute Mesa tests, because there is well-consolidated volcanic rock instead of alluvium at the surface on Pahute Mesa.

Both natural and induced earthquakes are most likely to occur where faults intersect. Such fault intersections occur near the Radioactive Waste Management Site, a shallow land burial waste disposal site in Area 5. In order to preserve the integrity of this site, nuclear testing near this area is avoided. Current underground testing occurs well to the north and northwest of this area, in Yucca Flat and up on the mesas.

One other geologic phenomenon has been observed at the NTS: this is the appearance of giant fractures on the surface of Yucca Lake (Sinnock, 1982). These cracks are not the common polygonal cracks due to drying that are found in many desert playas. They were observed between about 1950 and 1969, and were a series of northeast trending fractures that migrated southeast across the surface of the lake. They were thought to extend to significant depths, perhaps to rocks beneath the alluvium. This was inferred from the fact that water, if present in Yucca Lake at the time when a crack opened, would rapidly pour into the crack. This rapid loss of water would cause the cracks to fill with sediment and become inactive. A new crack would then abruptly form to the southeast at some later time. The cracks were observed to lie along a known zone of faulted alluvium that extends northward from Mercury, but no displacements of the playa surface were noted along the

cracks. The origin of these giant cracks is unknown. Apparently, none have been observed since 1969. This is fortunate, since several wastewater disposal facilities are located on the dry lake bed (see Section 3.4.2.6).

3.4.1.2 Site-Specific Hydrogeology

Two regional groundwater systems are present beneath the NTS. (Refer to Figure 2-5 in Section 2.0.) The eastern two-thirds of the NTS, as well as a vast area to the north and east of the site, are within the Ash Meadows groundwater system. The Pahute Mesa groundwater system encompasses the western one-third of the NTS as well as an extensive area to the west and north (ERDA, 1977).

Recharge and Discharge Areas

Recharge to the regional systems tends to be localized in the areas of higher elevation such as Pahute Mesa, the Belted Range, and Timber Mountain. Recharge depends upon average annual precipitation, which may be 2 to 3 times higher (25 to 30 cm compared to approximately 10 cm) in these upland areas than at lower elevations.

Discharge for both regional systems is to the Amargosa Desert, southwest and south of the NTS. Groundwater in the Ash Meadows system generally moves downward through alluvium and volcanic rocks to the Paleozoic carbonate rocks, in which it then flows generally southwestward to discharge at the large springs in Ash Meadows, about 40 km (25 miles) southwest of Mercury. In addition to this flow towards the Amargosa Desert, it is possible that some groundwater flow in the carbonates may be southeastward towards Indian Springs and the Las Vegas flow system. This possibility cannot yet be evaluated because of insufficient hydrologic data, but further well drilling in this area has been proposed as part of the Radionuclide Migration (RNM) program of the Nevada Operations Office (NVO, 1986b).

Groundwater in the Pahute Mesa system in part moves southward beneath Pahute Mesa, Fortymile Canyon (or Wash), and Crater Flat (west of NTS) toward the Amargosa Desert, and in part flows southwestward to Oasis Valley near Beatty. Groundwater in Oasis Valley moves southward into the Amargosa Desert through gravels and sands laid down in former channels of the Amargosa River, and probably moves also through the underlying fractured rocks. Further well drilling has also been proposed as part of the RNM program in the Thirsty Canyon area southwest of Pahute Mesa to investigate the extent of flow toward Oasis Valley (Beatty area). This is the direction of nearest population to the NTS.

Most of the annual discharge (an estimated 33 million cubic meters) from the two groundwater systems is transpired by plants or evaporated from soil and playas in the Amargosa Desert. A small amount of groundwater (less than 1,000,000 cubic meters) may continue to flow southward through the Amargosa River channel deposits. Some groundwater may flow westward from the Amargosa Desert through fractured rock of the Funeral Mountains to discharge at springs in Death Valley. Alternatively, these springs may be fed by groundwater from the carbonate rocks of the Spring Mountains southeast of the NTS (Jacobson, 1987a).

One other feature of the discharge areas potentially affected by the NTS is the presence at Ash Meadows of the only known surviving wild population of the endangered Devils Hole pupfish (Cyprinodon diabolis). The pupfish lives in a single, spring-fed, sinkhole pool. From 1967 to 1970, an extensive well field was developed for irrigation of privately owned lands in the Ash Meadows area. Withdrawals of groundwater from parts of this well field caused a 0.8-meter (2.5-foot) reduction in the water level of the pool and thereby threatened the survival of the pupfish. A 1976 ruling by the U.S. Supreme Court ordered a restriction in pumping from specific wells in the Devils Hole area and required maintenance of the water table at a level adequate for the pupfish habitat (OCRWM, 1986).

Water Table

The top of the groundwater flow systems is the water table. The water table is a surface with an irregular configuration; higher areas on this underground surface coincide with higher topographic elevations on the land surface. Rocks and other subsurface materials are saturated with water from the top of the water table downward. Soil, rocks, and unconsolidated deposits between the land surface and the top of the water table form the unsaturated zone. Water moves downward through the unsaturated zone until it reaches the water table. Water then moves both horizontally and vertically in response to head differences (hydraulic gradients). Perched groundwater may occur in the unsaturated zone where downward movement of water is retarded by low-permeability zones such as clay layers.

The water table is shown by lines (contours) connecting points of equal elevation. Groundwater flows from higher to lower areas on this surface, in a direction perpendicular to the contours. Figure 3-11 is a water-table contour map developed by Boughton (1986) for the NTS. This map represents the elevation to which water rises in a well under hydrostatic pressure; it is therefore a map of the hydraulic head in an aquifer, or a potentiometric surface. The map is based on data from all holes containing saturated geologic units. Data points that were anomalously high or low by comparison with surrounding water levels were eliminated. Such points were thought to indicate perched water or incomplete recovery from pumping. The water levels shown may be composite

FIGURE 3-11

REGIONAL WATER-TABLE MAP NEVADA TEST SITE - MERCURY, NV

where wells tap more than one aquifer. This map includes head data from tuff, carbonate, and alluvial aquifers, and thus the contours represent regional patterns (Boughton, 1986).

Aquifer Characteristics

Winograd and Thordarson (1975) identified six major aquifers and five major aquitards at the NTS. For a general understanding of NTS hydrogeology, the most important of these are the lower carbonate aquifer (Cambrian through Devonian age), the welded-tuff aquifer and the tuff aquitard in volcanic rocks of Tertiary age, and the valley-fill (alluvial) aquifer of Tertiary and Quaternary age. These hydrogeologic units are explained in more detail below.

Flow in both the Pahute Mesa and the Ash Meadows regional groundwater systems occurs mainly through fractures in massive volcanic or carbonate rocks. The alluvial aquifer is important only in local groundwater flow systems in the NTS flats. In the alluvial aquifer, which is in unconsolidated deposits rather than consolidated rocks, flow occurs interstitially, i.e., in the spaces or pores between particles such as sand grains. It is important to remember that groundwater flow depends not only on the size and shape of the spaces within subsurface materials, but also on the size, shape, and extent of interconnections between these spaces. A rock may have high porosity (ratio of the volume of the spaces to the total volume of rock, usually expressed as a percentage) but low permeability (ability to transmit a fluid) if the spaces are poorly connected.

The following descriptions of hydrogeologic units are taken directly from Winograd and Thordarson, 1975.

The highly fractured to locally brecciated, lower carbonate aquifer consists of limestone and dolomite. On the basis of pumping tests of 10 wells and regional flow analysis, the coefficient of transmissibility of the aquifer ranges from 600 to several million gallons per day per foot. Core examination indicates a fracture porosity of a fraction of 1 percent. The effective intercrystalline porosity of 25 cores ranges from 0.0 to 9.0 percent and has a median value of 1.1 percent. The coefficient of permeability of 13 cores ranges from 0.00002 to 0.1 gpd per square foot and has a median value of 0.00008 gpd per square foot.

The water-bearing fractures are probably solution-modified joints, fault zones, and breccia. Drill-stem tests in eight holes suggests that the water-bearing fractures are few and widely spaced, are present to depths of at least 1,500 feet beneath the top of the aquifer and as much as 4,200 feet below land surface, do not increase or decrease with depth, and are no more abundant or

permeable immediately beneath the Tertiary-pre-Tertiary unconformity than elsewhere in the aquifer.

The lower carbonate aquifer contains several solution caverns in outcrop. One of the caverns, Devils Hole, reportedly extends at least 300 feet vertically into the zone of saturation. The caverns probably do not constitute a hydraulically integrated network of solution openings, except possibly near major discharge areas; variations in fracture transmissibility control the regional movement of groundwater through the aquifer.

The tuff aquitard consists primarily of nonwelded ash-flow tuff, ash-fall (or bedded) tuff, tuff breccia, tuffaceous sandstone and siltstone, claystone, and freshwater limestone. Despite the widely differing origins of these strata, they generally have one feature in common: their matrices consist principally of zeolite or clay minerals, which are responsible in part for the very low interstitial permeability of these relatively porous rocks. Strata composing the aquitard have moderate to high interstitial effective porosity (median values ranging from 10 to 39 percent), negligible coefficient of permeability (median values ranging from 0.00006 to 0.006 gpd per square foot), and very low coefficient of transmissibility (less than 200 gpd per foot). Evidence from several miles of tunnels indicates that the regional movement of groundwater through the tuff aquitard is probably controlled by interstitial permeability rather than by fracture transmissibility.

The welded-tuff aquifer consists of moderately to densely welded ash-flow tuff. The coefficient of transmissibility of the aquifer at 4 well sites ranges from 200 to more than 100,000 gpd per foot and is probably controlled principally by interconnected primary (cooling) and secondary joints; interstitial permeability is negligible.

The valley-fill aquifer consists of alluvial-fan, mudflow, fluvial deposits, and lake beds. The coefficient of transmissibility of the valley-fill aquifer at 6 well sites ranges from 800 to about 34,000 gpd per foot; average interstitial permeabilities range from 5 to 70 gpd per square foot (Winograd and Thordarson, 1975).

The behavior of these hydrogeologic units is best illustrated by examining specific areas of the NTS. Figure 3-12 is a generalized north-south geologic cross-section of Yucca Flat, Frenchman Flat, and Mercury Valley showing directions of groundwater flow. In the flats, the water table generally occurs in alluvium and volcanic rocks above the regional carbonate aquifer. The welded-tuff aquifer is believed to lie above the lower carbonate aquifer in this portion of the NTS. (This welded tuff is made up of numerous ash flows hardened by the combined action of the heat retained by the volcanic ash particles and the enveloping hot gases. Welding decreases porosity but promotes the

SECTION		
SYMBOL	GEOLOGIC UNIT	HYDROGEOLOGIC UNIT
Qtal	QUATERNARY AND TERTIARY VALLEY FILL	VALLEY - FILL AQUIFER
Tt	TERTIARY TUFF, LAKE BEDS, & LAVA FLOWS	WELDED TUFF AQUIFER & TUFF AQUITARD
Pzc	PALEOZOIC CARBONATE ROCKS	LOWER CARBONATE AQUIFER

Source: Burbey and Wheatcraft, 1986.

FIGURE 3-12

GENERALIZED GROUNDWATER FLOW BENEATH FRENCHMAN FLAT AND YUCCA FLAT NEVADA TEST SITE - MERCURY, NV

development of joints which allow groundwater to flow.) Overlying the welded tuff is the tuff aquitard, which includes friable material that does not maintain open fractures or joints, and which has spaces filled with clay and zeolite minerals. (For a discussion of zeolites, see Section 3.2.1.) This aquitard retards vertical flow between the overlying alluvial (valley-fill) aquifer and the underlying welded tuff and carbonate aquifers. The alluvial aquifer is surrounded on all sides at the edge of the various flats by older rocks, so that horizontal flow has to pass through the tuff aquitard. Thus, horizontal movement of groundwater from the alluvial aquifer is restricted. Instead, as shown on Figure 3-12, groundwater moves downward slowly through the aquitard and then horizontally southward through the carbonate (Burbey and Wheatcraft, 1986).

Downward flow through the tuff aquitard is less than 0.05 meter (0.2 foot) per year. Estimates for groundwater velocities are 2 to 180 meters (6 to 600 feet) per year in the carbonate aquifer. A velocity near the lower end of this range is supported by carbon-14 data (ERDA, 1977).

At Rainier Mesa, the regional water table is located 1,070 meters (3,600 feet) below the summit in the Paleozoic carbonate rocks (Figure 3-13). Water found in the volcanic rocks above the regional groundwater table is frequently perched within poorly connected fractures and fault zones in the tuff aquitard. This perched water has been tapped in the process of mining new drifts for tunnel tests. (See Section 2.2 for a description of these tests.) Water stored in these fractures tends to be depleted rapidly when the zone is tapped, but seepage continues to occur as groundwater from recharge on the mesa surface moves slowly downward through the tuff. The perched water in these fractures in the tuff aquitard is about 370 to 430 meters (1,200 to 1,400 feet) beneath the surface of the mesa in the area of the tunnels, or about 600 meters (1,970 feet) above the water table within the underlying carbonate aquifer (Jacobson et al., 1986).

In the Pahute Mesa area, there is no deep, underlying aquifer similar to the carbonate aquifer. The geologic units beneath the mesa consist of a complex series of interbedded volcanic rocks with extreme contrasts in permeability both laterally and vertically. Pahute Mesa contains fractured lava flows and welded tuffs that are considered to be aquifers. Nonwelded and altered tuffs generally act as aquitards, with the altered tuffs containing substantial amounts of zeolite minerals (Jacobson et al., undated).

Estimated groundwater velocities beneath Pahute Mesa range from 2 to 76 meters (7 to 250 feet) per year. Low-permeability blocks between fractures may result in velocities that vary as much as two or three orders of magnitude over short distances. The most probable groundwater velocity, based on an assumed 10 percent porosity, is 5 meters (15 feet) per year. If this velocity is used, water from sites of Pahute Mesa tests could not leave government-controlled land (including the Nellis Air Force

FIGURE 3-13

GEOLOGIC CROSS-SECTION AT E-TUNNEL, RAINIER MESA
NEVADA TEST SITE - MERCURY, NV

Range) for more than 1,000 years (ERDA, 1977). As mentioned above, well drilling has been proposed in the Thirsty Canyon area southwest of Pahute Mesa to provide actual data to check these assumptions. A well in this area is part of the Five Well Program proposed by the RNM program (NVO, 1986a).

3.4.1.3 Groundwater Use

Since the only surface water body in the vicinity of the NTS is Lake Mead (85 miles [136 km] away), nearly all water supplies are groundwater (wells and springs). Lake Mead supplies 60 percent of the water for Las Vegas and North Las Vegas; the remaining 40 percent comes from wells. Water in southern Nevada (excluding the Las Vegas area) is used chiefly for irrigation and to a lesser extent for livestock, municipal needs, and domestic supplies. Almost all the required water is pumped from the ground, although some springs supply water to establishments in Death Valley. Springs in Oasis Valley near Beatty are a significant source of water for public and domestic needs and for irrigation. In Nye County centralized water supply services are available only in Beatty, Tonopah, Mercury, and Gabbs, and within parts of Pahrump. These utilities served about 64 percent of the county population in 1980. Table 3-19 summarizes available information on water supply sources and amounts in areas of Clark and Nye counties near the NTS. This table and all regional water use information in this section are taken from OCRWM (1986).

The main areas of existing and potential future agricultural water use are in the Amargosa and Pahrump Valleys. The community of Lathrop Wells, now also called Amargosa Valley, was named after irrigation wells. (The unincorporated Town of Amargosa Valley includes this community and two other population concentrations referred to as the Amargosa Farm area and the American Borate housing complex). Actual agricultural water use (with or without certified permits) in the Amargosa Valley in 1983 was 11.2×10^6 cubic meters (9,105 acre-feet). In the Pahrump Valley, agricultural use is declining as land is developed for residential use. Actual agricultural use is about 49×10^6 cubic meters (40,000 acre-feet) per year. New permits for irrigation are not being granted because of overdraft conditions (long-term withdrawal exceeds replenishment). Even if the balance between withdrawal and replenishment for the Pahrump Valley in general is restored, local effects such as land subsidence and well interference can result from sustained residential and commercial development. This has occurred from excessive groundwater pumpage in Las Vegas.

There is no use of groundwater in the immediate vicinity of the NTS other than at Lathrop Wells, and specific details on location and level of use of individual wells at Lathrop Wells are unavailable. An inventory of wells within 2 miles of the NTS is being developed by the NVO. These wells are of three types: (1) unused wells in the Lathrop Wells area, for which little information is available; (2) old

TABLE 3-19

**1980-1984 WATER SUPPLY SOURCES AND AMOUNTS IN AREAS
OF CLARK AND NYE COUNTIES NEAR THE NEVADA TEST SITE
NEVADA TEST SITE, MERCURY, NEVADA**

Community	Estimated Population Accounted For	Water Sources	Estimated Water Use	
			acre-feet/ year ⁽¹⁾	mgd
Amargosa Valley	540	Domestic wells.	418	0.373
Beatty	1,200-1,500	Four municipal wells.	165	0.147
Crystal	42	Domestic wells 160 feet deep.	30	0.03
Indian Springs	912	Municipal well capable of supplying 0.8 mgd to 53 customers, plus approximately 80 domestic wells with unknown capacity.	700	0.6
Indian Springs Air Force Base	500	Two wells supplying 0.2 mgd potable water.	300	0.3
Pahrump	1,260	Wells in valley-fill aquifer	1,700	1.5

Source: OCRWM, 1986.

- (1) 1 acre-foot = 1,234 cubic meters; mgd = million gallons per day, 1 mgd = 1,120.55 acre-feet per year. Values for acre-feet are rounded to the same number of significant digits as in the mgd data.

hydrologic test holes with no water use; and (3) recently installed test wells just west of the NTS at Yucca Mountain, which are part of a hydrologic investigation for the proposed high-level nuclear waste repository.

Water supply wells on-site at the NTS are shown on Figure 3-14. These wells are sampled monthly by the site operating contractor, Reynolds Electrical and Engineering Company, Inc. (REECo), and are referred to as the REECo monthly supply wells in various site documents.

Groundwater quality depends on the rock type from which a well draws water. Of these water supply wells, Wells 2, UE-16d, C-1, C, and Army Well 1 are in carbonates, Wells A, 5B, and 5C are in alluvium, and Wells 4, UE-15d, 8, J-12, J-13, UE-5c, UE-19c, and U-20 are in volcanic rocks (tuffs and lava flows). Analyses of major cations and anions indicate that calcium bicarbonate water predominates in the carbonate aquifer. Sodium-potassium bicarbonate waters are present in the volcanic rocks. Waters of intermediate type occur in some tuff aquifers and in alluvial wells (Boughton, 1986). Wells C, C-1 and Army Well 1 require water softening treatment because of their calcium and magnesium content. Wells C and C-1 also exceed the drinking water standards of 500 mg/l for total dissolved solids. These results are not surprising for wells in water-soluble limestone (calcium carbonate). Water quality is better in volcanic rocks, except for fluoride. Wells J-12, J-13, and 19c exceed the Nevada drinking water standard for fluoride (1.6 mg/l), and the same problem occurs in three of the four municipal wells in Beatty, Nevada (OCRWM, 1986). Detailed analytical data from environmental monitoring of the NTS water supply wells are presented in Section 3.4.3.

In addition to these supply wells for potable and construction water, there are numerous other wells of various kinds on the NTS. These are listed by the NVO as "known open wells," "injection wells," or exploratory holes. Many of these are hydrologic test holes. Some have been included in environmental monitoring programs in the past, and some are still included in the Long-Term Hydrological Monitoring Program (see Section 3.4.3). Individual holes from these various categories will be discussed in the following sections as appropriate.

3.4.2 General Description of Pollution Sources/Controls

3.4.2.1 Groundwater Contamination from Underground Nuclear Testing Near or Below the Water Table

At the NTS, as of April 1987, there were 419 announced underground tests above the water table and 108 announced underground tests below the water table (Clark, 1987). Figure 3-15 shows the

FIGURE 3-14

WATER SUPPLY WELLS AT THE NEVADA TEST SITE NEVADA TEST SITE - MERCURY, NV

Source: Clark, 1987.

FIGURE 3-15

**NUCLEAR DETONATIONS FIRED BELOW THE WATER TABLE
NEVADA TEST SITE - MERCURY, NV**

locations where tests below the water table have been conducted. It is possible that some tests only a short distance above the water table are included in the count of 419 and that, in fact, the cavities or at least the fracture systems formed from these tests extend below the water table.

It may be useful to review what happens in the subsurface environment as a result of an underground nuclear detonation. The following discussion is taken from Crow, 1976. All the material in the immediate vicinity of a nuclear explosion is vaporized. In addition to the material that is vaporized, rock in the zone immediately surrounding the expanding vaporized material is melted by the shock wave from the explosion. Within the cavity, there is a mixture of vaporized and melted material. As the temperature and pressure peaks from the explosion decline, the less-volatile species begin to condense. After cavity growth stops, the vaporized rock condenses to a liquid and the molten rock begins to cool. As cooling continues, melted materials gravitate to the bottom of the cavity. At about this time, the fractured rock above the cavity begins to collapse into the molten rock (or puddle glass) at the bottom of the cavity. Addition of this cooler material causes the glassy substance to cool and solidify faster. The remainder of the materials associated with the explosion, including the more volatile radionuclides, remain as vapor in the chimney. During further cooling, the materials condense on the surface of the shattered rock in the chimney. Surface effects, including both surface tension and sorption, immobilize nearly all of the condensed radionuclides at or near their condensation sites.

Eventually, when there has been sufficient cooling, the water vaporized by the explosion condenses, groundwater flows into the chimney, and some of the soluble radionuclides deposited on the rock rubble dissolve in the water. The radionuclides ruthenium-106 (Ru-106), antimony-125 (Sb-125), and cesium-137 (Cs-137) have been found in chimney water at the NTS. Transport of most radionuclides through granular rock is retarded significantly by sorption, so that, as a first approximation, one would not expect to find most radionuclides very far from the site at which they condense. The situation is complicated by the variable extent of sorption for different nuclides and by the possibility that colloidal transport may operate for nuclides sorbed to extremely fine particles. (The role of colloidal transport is discussed in Section 3.4.2.1.)

Tritium, however, is not significantly retarded by sorption and moves with the water in which it is incorporated. The tritium produced in the explosion is mixed with the vaporized water that was originally present in the rock, at temperatures sufficiently high to cause dissociation of the water molecules and incorporation of the tritium in some of them. The tritiated water in the explosion cavity is moved radially outward by the pressure pulse associated with the explosion. While this pulse lasts only a relatively short time, it is important because of its large magnitude. Other operative forces include the gas pressure and the heat effects of the explosion. The total effect of

these forces is to move tritiated water vapor from the cavity radially outward into the fractured zones beyond it. It is known that groundwater forms a mound above the site of an underground nuclear explosion as a result of such forces. While some of the water in the mound moves inward to the chimney of the nuclear explosion after the initial forces have declined, there remains an outward hydraulic component from the mound. In addition to radial movement, tritiated water also moves upward in the permeable chimney rubble by mechanisms such as vapor refluxing and water-phase convection. These mechanisms act to mix the tritiated water produced in the explosion cavity with the water in the chimney above the cavity for a substantial distance above the working point of the explosion. Tritiated water remains as a vapor in the chimney and adjacent region until cooling below the boiling point of water results in condensation.

Within a fairly short period after an underground nuclear explosion, the forces due to the explosion decline substantially, and further movement of groundwater is due largely to regional hydraulic gradients. Both vertical and horizontal hydraulic gradients are important. For example, in Yucca Flat, groundwater in saturated tuff leaks slowly downward to the carbonate aquifer and then moves horizontally in response to regional head differences.

As water in the tuff leaks downward into the regional carbonate aquifer, the transport of contamination in the water is slowed by passage through many lithologic units with the ability to sorb radionuclides (ERDA, 1977). This mechanism will act to broaden the distribution of contaminants and suppress peak radionuclide concentrations. Radionuclides reaching the regional carbonate aquifer would be transported at, or slower than, the groundwater velocity which is estimated at 2 to 180 meters (6 to 600 feet) per year. Little is known of the retardation and dispersion characteristics of the carbonate aquifer, although its sorption capability is likely to be less than that of the tuffs. Even in the absence of sorption, radioactivity in the regional carbonate aquifer beneath Yucca Flat would require a century to arrive at Frenchman Flat. Any test-derived tritium in the water would have decayed by a factor of about 250 during this time.

In the Ash Meadows groundwater system, the area beneath Frenchman Flat also receives flow from the east from outside the NTS boundaries. This interbasin flow from the east may be as much as an order of magnitude greater than the contribution coming from beneath Yucca Flat. The flow from Yucca Flat is thought to be about 430,000 cubic meters annually. Dispersive mixing along the boundaries of the 2 volumes of water would ultimately dilute the concentration of any tritium by another factor of 10. An additional century will have passed before this water arrives under Mercury Valley and thus time will be allowed for further radioactive decay. Under Mercury Valley, the greatest proportion of Ash Meadows flow is derived from the Spring Mountain Range recharge, which enters the system from the southeast. Again, dispersive mixing will occur when this large

volume of water comes in contact with that which enters from under the NTS. There remains another hundred-year journey before these waters arrive at the Ash Meadows discharge area.

The combination of 300 years for radioactive decay and dispersive mixing over the long migration path will reduce any tritium concentrations by at least a factor of 10^9 . The reduction factor for tritium due to radioactive decay alone is 2×10^7 during this 300-year journey. It has been calculated (ERDA, 1977) that more than 420 billion curies of tritium per year would need to be introduced into the carbonate aquifer beneath Yucca Flat to produce an activity of 1×10^6 pCi/l at the springs in the Ash Meadows discharge area. This value is based on the annual discharge of about 21 million cubic meters of water at the spring line, the 21,000 curies of tritium required for mixing with this annual discharge to attain such a concentration, and the 2×10^7 radioactive decay factor. The 420 billion curies of tritium amount to over 42,000 kg (50 tons), which is many orders of magnitude above all the tritium associated with nuclear testing at the NTS.

Similar calculations could be performed for sites on Panute Mesa, where it has been estimated that groundwater from these sites would not leave government-controlled land for 1,000 years. Thus, tritium migration is not expected to become a future hazard off-site because of slow groundwater flow rates and radioactive decay. However, continued monitoring and continued scientific investigation is essential because groundwater flow rates could be increased by continued rock fracturing from nuclear testing, because flow rates are not well defined in many areas, and because the movement of contaminants by mechanisms such as dynamic injection and colloidal transport are incompletely understood.

The channel for scientific investigation of contaminant migration by the groundwater pathway is the Radionuclide Migration (RNM) program of the Nevada Operations Office. The RNM program is a multi-agency research project involving the Lawrence Livermore National Laboratory (LLNL), the Los Alamos National Laboratory (LANL), the Desert Research Institute of the University of Nevada (DRI), and the U.S. Geological Survey (USGS). The RNM program has several experimental sites (Figure 3-16) where data are collected on the actual, rather than theoretical, movement of radionuclides and some nonradioactive chemical species out of test cavities and chimneys.

The first of these studies was the the BILBY (U3cn) site. BILBY occurred on September 13, 1963. It was the first event detonated below the water table in Yucca Flat, had a yield of approximately 200 kt, was buried at a depth of 2,339 feet (712.9 m) below the surface in the tuff underlying the alluvium, and produced a cavity with a radius of about 285 feet (87 m) (Buddemeier and Isherwood, 1985.) A post-shot hole, U3cn PS2, was drilled into the BILBY rubble chimney and used for sampling and for water-level monitoring. Filling of the chimney and cavity by local groundwater

FIGURE 3-16

LOCATIONS OF EXPERIMENTAL SITES FOR THE
RADIONUCLIDE MIGRATION PROGRAM
NEVADA TEST SITE - MERCURY, NV

was not complete until 1969, when the water level returned to the pre-shot water table elevation. Five pumping tests were run and samples taken by the USGS (Garber, 1971). Tritium levels in the chimney decreased from 1×10^8 pCi/l to 4.1×10^7 pCi/l over a 16-year period. Other radionuclides are present at low activities of 1×10^4 pCi/l to 1×10^6 pCi/l (NVO, 1986b). Detailed data may be found in Buddemeier and Isherwood, 1985.

A satellite well (U3cn P55) was drilled in 1965 at a location 400 feet (16 m) southeast of the chimney well. This well was drilled through the alluvium and tuff into the underlying Paleozoic carbonate rocks. It was cased to produce water only from the carbonates and was intended to test for radionuclide migration from the overlying tuff in which the event was detonated. This satellite well was monitored for more than 10 years without detecting any radioactivity. Thus, for this particular nuclear test, it appears that there was no communication between the tuff aquifer and the carbonate aquifer.

A somewhat different situation exists for two nuclear tests that were detonated above the water table in the Paleozoic carbonate rocks but apparently produced contamination below the water table in the regional carbonate aquifer. These are NASH (U2ce) and BOURBON (U7n).

NASH was expended in January 1967 at a depth of 364 m (1,194 feet), approximately 70 m (230 feet) above the water table. Anomalous seismic signals were recorded for this event; NVO therefore decided to drill a post-shot exploratory hole (satellite well) to determine the geological and geophysical characteristics of the site and to determine the water-table depth. By installing a pump to create an artificial gradient, the potential for radionuclide migration from the NASH chimney could also be tested.

The NASH satellite well UE-2ce (also known as USGS water well 2-WSW-1) was drilled in 1977 to a depth of 502 m (1,647 feet), which was 138 m (453 feet) deeper than the NASH explosion level, and cased to 8 m (26 feet) of its total depth so it would produce water only from the carbonates. The well is located 57 m (187 feet) south of the detonation point for NASH.

The well is thought to produce water from fractures in carbonate rock. During early stages of pumping, a rapid increase of tritium was seen. In 1986 the well was producing water containing $1.5\text{--}2.0 \times 10^7$ pCi/l tritium and small amounts of krypton-85 (Kr-85), sodium-22 (Na-22), strontium-90 (Sr-90), and cesium-137 (Cs-137). Since the event took place above the water table, it is likely that the tritium and Kr-85 seen in the water samples were forced into the groundwater along existing or newly formed fractures at the time of the event. The presence of Na-22, the activation product of naturally occurring Na-23 (by absorption of a neutron followed by emission of two neutrons),

indicates that the nuclear explosion generated a large flux of fast neutrons. Under these circumstances, the Na-22 found in the water samples could be from the Na-23 contained in the surrounding rock and water at the time of the event, and may not represent leaching of the melt glass (NVO, 1986b). Na-22 activity has been as high as 0.44 pCi/l.

The NASH satellite well was part of the RNM program and provided the best opportunity to study radionuclide migration from the unsaturated zone to the saturated zone. It was formerly sampled monthly for tritium by REECO although it is not a water supply well. It was sampled for other radionuclides at "regular but infrequent intervals" (NVO, 1986b) and was to be sampled annually by LLNL. Discharge from the well entered a seepage/evaporation pond with a total area of 240 square feet. The average annual discharge was 81 Ci. The average concentration was 1×10^7 pCi/L of tritium. This RNM study site is no longer active because the pump failed and no replacement is planned (Tyler, 1987b). It was apparently active from 1977 to 1986.

BOURBON was also detonated in 1967, at a depth of 560 m (1,837 feet), which is 17 m (56 feet) below the top of the Paleozoic carbonates but is still in the unsaturated zone. Like NASH, BOURBON demonstrated anomalous seismic signals, and a post-shot exploratory hole (satellite well) was drilled to study the geological and geophysical characteristics of the site. The BOURBON satellite well, UE-7ns, was drilled in 1976 to a depth of 672 m (2,204 feet), which is 71 m (233 feet) below the water table. It was cased to produce only from the carbonates. A pump was installed for hydrologic testing and sampling, but the well produced very little water and the samples taken were believed to be too small to be representative of the local groundwater. Later, the UE-7ns site became the location of the Photovoltaic Utilization Program. The program uses solar power to run a low-capacity pump, which provides continuous water samples and thus allows collection of larger volumes. Because of the low flow from this well, a seepage basin constructed at the site is not needed. Only a trickle of water was being discharged to the ground surface from the pumping system during the on-site Survey.

The UE-7ns well is part of the monthly long-term hydrologic monitoring program (LTHMP, see Section 3.4.3), but sampling is not necessarily done every month. Since 1979, tritium levels have ranged from 990 to 4,600 pCi/l. These values are higher than the 100-700 pCi/l regional tritium background but lower than the EPA drinking water limit of 20,000 pCi/l. No other radionuclides have been detected above background levels. It is not known whether the BOURBON cavity intersects the saturated zone or whether there is an interconnected fracture system between the cavity and the satellite well. NASH and BOURBON are similar in geologic setting, but the tritium levels in their respective satellite wells differ by four orders of magnitude. The low water flow in the

BOURBON satellite well probably indicates a poorly developed fracture system, which would in turn allow little tritium migration.

The CHESHIRE (U20n) site on Pahute Mesa is the only RNM site for study of contaminant migration within the tuff aquifer. CHESHIRE was fired on February 14, 1976, with an announced yield in the 200- to 500-kt range. The size of this shot provided a larger source term for study than most of the other RNM sites. The location was also of interest since it was only 5 miles (8 km) from the western boundary of the NTS. The fact that the cavity rapidly refilled with water indicates that the ability of the aquifer to transmit water was reasonably high. A post-shot hole (U20n PS1) was drilled into the lower part of the cavity and sampled a few months after the detonation and again in 1983. Detailed results are presented in Buddemeier and Isherwood, 1985. The maximum radionuclide concentration was 2×10^9 pCi/l for tritium.

Filtration studies were conducted on some of the samples from the CHESHIRE site in order to examine the role of colloidal transport in radionuclide migration. Colloids are very fine particles in the size range of approximately 0.001 to 1 μm . Unlike larger particles, which remain in place as groundwater moves slowly through soil and rock, small colloidal particles may be transported by groundwater flow. Therefore, radionuclides attached to such particles by sorption could be more mobile than expected.

Normally, the nuclides of greatest interest from the standpoint of migration are those present in dissolved form, and therefore water samples are filtered through 0.45 μm filters to remove particulate matter. The filtrate is considered to represent dissolved material, but in fact it contains both dissolved and colloidal fractions. Ultrafiltration using a membrane filter that retained particles as small as 0.006 μm was performed on the filtrate from the 0.45 μm filter. It was found that the manganese, cobalt, cesium, and europium activity and much of the ruthenium activity was associated with the 0.006-0.45 μm colloidal fraction. This observation is important for prediction of the movement of these elements. More recent work (McCarthy and Wobber, 1986) has confirmed that colloids do occur in the subsurface environment, are capable of binding organic and inorganic contaminants, and do alter the mobility of contaminants. Further work on colloidal transport has been planned by the RNM program, using the CAMBRIC site.

CAMBRIC (U5e) was detonated in alluvium below the water table on May 14, 1965. In 1974, two holes were drilled for radionuclide migration studies. Hole RNM-1 is a reentry well into the CAMBRIC cavity; hole RNM-2S is a satellite well located 300 feet (91 m) from CAMBRIC. In 1975, water was pumped from the satellite well to induce an artificial gradient sufficient to draw water from the CAMBRIC cavity and provide an opportunity for the study of radionuclide migration under field

conditions. CAMBRIC was chosen for this study for several reasons. It is within the NTS Area 5 water-supply aquifer, and there was particular interest in possible contamination of water supplies. The CAMBRIC detonation point was only 964 feet (294 m) below ground surface, and thus drilling and sampling would be less difficult and less expensive than for more deeply buried tests. Also, the small yield (0.75 kt) was expected to have had little effect on the local hydrology (NVO, 1986b).

The mobile constituents found at RNM-25 include tritium, krypton-85 (Kr-85), chlorine-36 (Cl-36), and iodine-129 (I-129). Kr-85 apparently moves with tritium as a gas dissolved in water. Cl-36 moves ahead of tritium because of anion exclusion. This effect, in which anions move faster than cations or neutral species, correlates well with the cation exchange capacity (CEC) of the soil. The surface of clay minerals attracts cations but repels anions, thus excluding negatively charged species while admitting both water and positively charged species. I-129, as well as Cl-36, may be present as an anion. It is not retarded by sorption. Studies of I-129 mobility are particularly useful because, like all iodine isotopes, it is biologically active and human exposure is of concern.

The water pumped from Well RNM-25 flows along a discharge ditch to a seepage/evaporation pond at the edge of Frenchman Lake (see Section 4.1.2.1.2). Tritiated water from this ditch infiltrates the unsaturated zone and is called the CAMBRIC plume. Since the input water has been well characterized, it becomes a natural tracer for studies of water movement through the unsaturated zone. Dispersion and retardation of radionuclides other than tritium can also be studied, either from the migration of those already present in the water, or by addition of stable (nonradioactive) analogs of these nuclides. The ditch is well instrumented and used for continuing studies. Data from the CAMBRIC site may be found in Buddemeier and Isherwood, 1985, which also includes an extensive bibliography of other scientific reports for this location.

3.4.2.2 Groundwater Contamination in Areas Other Than Cavities and Chimneys

It is sometimes stated that there are no identified sites of groundwater contamination on the NTS except within the immediate vicinity of the underground detonation points (Clark, 1987). This is true if "immediate vicinity" is defined to include areas 1,100 to 1,400 feet away from a test cavity. Groundwater has been found to be contaminated with tritium and other radionuclides in such areas not immediately adjacent to cavities and chimneys. These areas are referred to by the NVO as "expended drill holes that contained radionuclides." This terminology refers to emplacement holes that were found to be contaminated when initially drilled, prior to device emplacement. The holes were later used for nuclear tests (expended). The contamination may result from creation of fractures during detonation and the movement of fission products by a combination of natural and explosion-related hydraulic forces. This detonation-related mechanism results in localized

movement of radionuclides, and should be distinguished from normal migration of contaminants in response to more generally applicable hydraulic and geochemical factors. However, as underground nuclear testing continues and more of these pathways for localized movement are created, overlap of these local zones may occur and pathways for enhanced contaminant migration may be generated.

Only four occurrences of this type of contamination have been reported from the hundreds of emplacement holes that have been drilled at the NTS. Therefore, this type of radionuclide movement is apparently uncommon. It is, however, unpredictable at the current level of scientific understanding. The four documented occurrences include U9ITS-U29 in 1971, STANYAN (U2aw) in 1974, ICEBERG (U4g) in 1977, and ALEMAN (U3kz) in 1985-1986. These incidents and some additional discoveries in associated holes are described below. The locations of these holes are shown on Figure 3-17.

The U9ITS-U29 emplacement hole was completed in February 1971 to a total depth of 1,135 feet. Radioactive contamination was found on a vacuum truck and on the drilling rig used at the hole. Gamma logs showed that the hole was contaminated from 360 to 1,134 feet, with a zone of more intense contamination from 716 to 788 feet. A TV/stereo camera run showed a vertical fracture at the 690 to 720 feet level, and unidentified blackened material underneath the mud cake on the borehole wall. The hole walls were then washed with clear water from 640 to 840 feet, a process which caused 35 feet of water to collect in the bottom of the hole. The TV/stereo camera runs were then repeated to detect fractures, which were found between 700 and 753 feet. Sidewall cores were taken at depths of interest, and samples from three depths (760, 740, and 726 feet) were analyzed by gamma spectrometry. Samples at 760 feet had cesium-137 (Cs-137), cerium-141 (Ce-141), iridium-192 (Ir-192), ruthenium-103 (Ru-103), and rhodium-106 (Rh-106); those at 740 feet had all the above nuclides plus barium-140 (Ba-140), lanthanum-140 (La-140), and iodine-131 (I-131); and, those at 726 feet had Ce-141, Ir-192, Ru-103, and Rh-106. With the exception of Cs-137, the maximum half-life for any of these radionuclides is 74 days. The presence of these fission products with relatively short half-lives indicated that a fairly recent detonation was the probable source.

Exploratory hole U9ITS-UE-U29 No. 1 was drilled at a location east of U9ITS-U29, between U9ITS-U29, where the contamination was found, and U9ITS-X29, which was thought to be a possible source. No radioactivity was detected in this exploratory hole, either in cutting samples and cores or by gamma logs. Exploratory hole U9ITS-UE-U29 No. 2 was then drilled at a location southwest of U9ITS-U29, between U9ITS-U29 and another possible source. Cs-137 was found at a depth of 670 feet in this exploratory hole, a fact which confirmed the possibility of a pathway to U9ITS-U29. In April 1971, fission products were found to have leaked into the stemming at the source hole. The isotopes

FIGURE 3-17

CONTAMINATED DRILL HOLES AND PROBABLE SOURCES NEVADA TEST SITE - MERCURY, NV

identified were Ir-192, Ba-140, La-140, Ru-103, and Rh-103. The leak was traced to a rupture at the slip-joints of the Pinex (vertical line-of-sight) pipe used for this test. (A slip-joint in a Pinex pipe is a section that allows the pipe below this point to move upward 10 feet before motion is transmitted to the upper sections (Thalgott and Weart, 1971). The rupture was at a depth of 417 feet and the eventual depth to water measured in the pipe was 419 feet, so that transmission of radionuclides by groundwater is likely. Although no conclusions were drawn in the two reports of observations related to U9ITS-U29 (Oswald, 1971; Shockley, 1971), it is possible that forces causing a pipe rupture could have caused fracturing and dynamic injection of contamination 172 meters (566 feet) to the U9ITS-U29 location.

The next documented occurrence was at STANYAN (U2aw). This occurrence is considered the first observation of tritium in groundwater outside chimneys of underground nuclear explosions. In the prior incident at U9ITS-U29, fission products other than tritium were detected, and these fission products were found in samples from the borehole wall and not in groundwater. However, no attempt was made to check specifically for tritium.

During construction of the STANYAN emplacement chamber in April 1974, tritiated water was observed flowing from a fracture in the wall (Crow, 1976). The tritium activity level was 2.4×10^6 pCi/l. An adjacent exploratory hole, UE-2aw, had a tritium activity of 1.06×10^5 pCi/l. Background levels from a water supply well in the area were 100-700 pCi/l. The emplacement chamber, which was apparently a mined chamber enlarged from the borehole, was 465 meters (1,400 feet) from the nearest nuclear explosion detonated beneath the water table. This probable source was COMMODORE (U2am), which was detonated in 1967. The level of tritium activity in the water flowing into the STANYAN chamber rose to 1.1×10^7 pCi/l by September 1974. For purposes of comparison, this is 5.5 times the DOE Derived Concentration Guide (2×10^6 pCi/l) for tritium in public drinking water and 5,500 times the EPA drinking water standard (2×10^4 pCi/l). The rise in tritium levels is thought to result from pumping of the chamber to control the inflow of groundwater. Such pumping would tend to move more highly contaminated water from the source cavity. One sample was analyzed for gamma-emitting radioisotopes, and none were found. Therefore, it is presumed that soluble nuclides such as Cs-137, antimony-125 (Sb-125), and ruthenium-106 (Ru-106), which have been found in groundwater in chimneys, were retarded by sorption processes and had not yet reached the sampling point at U2aw. Observations at U2aw were terminated when the hole was expended for the STANYAN test in September 1974.

An exploratory hole, UE-2ar, was sampled in May 1975. This hole was 980 meters (3,214 feet) south of the STANYAN emplacement hole. Tritium levels reached a maximum of 4.7×10^5 pCi/l, which is 23.5X the EPA drinking water standard. The source of this contamination is thought to be

AGILE (U2v), which is 361 meters (1,184 feet) northeast of UE-2ar. AGILE was detonated below the water table in February 1967.

Emplacement hole U4g was completed in December 1976. In February 1977 it was discovered that the mud taken from U4g had anomalously high levels of tritium (about 1,000 pCi/g). Further investigation showed both tritium and Cs-137 within U4g. This hole had been drilled to a total depth of 2,440 feet. Since it extended below the water table it was lined from 1,482 to 2,391 feet. Such linings are used to keep water from entering the hole until after the nuclear test has been performed. The static water level was found at $1,665 \pm 25$ feet.

Tritium was measured from sidewall samples. The tritium activity peaked at about 5,000 pCi/ml at the static water level. The activity was at background levels from about 1,400 feet to the surface, and averaged about 2,000 pCi/ml from 1,800 feet to the total depth. (For comparison, this tritium activity is equivalent to the 2×10^6 pCi/l DOE Derived Concentration Guide for water used by members of the general public and 100 times greater than the 2×10^4 pCi/l EPA drinking water limit for tritium.)

Washed cuttings were analyzed for gamma activity. The predominant radioisotope was Cs-137. This radionuclide was concentrated primarily in three specific locations: (1) about 50 pCi/g activity at about 1,675 feet, just below the static water level, (2) 30 pCi/g at 1,840 feet, and (3) about 40 pCi/g at 2,210 feet. The latter two depths mark the contacts (boundaries) between various volcanic rock units.

The closest nuclear test to U4g is U4d (LATIR), which was expended in February 1974. This hole was drilled to 2,252 feet, so the working point (WP, depth location of the device within the hole) may have been as much as 200 feet above the maximum depth of U4g (2,440 feet). The LATIR event was 1,030 feet (314 m) northwest of U4g. The next closest event was U4c (ZAZA), which was expended in September 1967 and is 1,253 feet (382 meters) southeast of U4g. This hole was 2,250 feet deep, similar to the depth of the LATIR hole. It is possible that explosion-induced fracturing followed the contacts between rock units (horizontal) or the natural north, northeast, and northwest joint trends (roughly vertical).

Hole U4g was expended for the ICEBERG event in March 1978. In later study of the contamination occurrence, it was apparently decided that the LATIR event was the probable source for the contamination found in U4g, and a particular rock unit was implicated as a possible path for radionuclide transport at U4d-U4g (App, 1986). The ICEBERG occurrence was north of the ALEMAN occurrence described below, within a geologic sequence of rock units bounded on the east by the

Yucca Fault and on the west by the Topgallant fault (i.e., within the same geologic structural block). The northward extent of the Topgallant fault and the possible significance of this structural block to the observations at STANYAN have not been determined (see Figure 3-17).

ALEMAN was designed for execution in emplacement hole U3kz, and the shot was eventually fired in 1986. However, the hole itself was found in 1985 to show tritium levels as high as 6×10^7 pCi/l. Other radionuclides detected were Ru-106, Sb-125, Cs-137, Pu-238, Pu-239, and Pu-240. These are fission products and possible undetonated nuclear materials. The emplacement hole had been lined from 1,473 to 2,198 feet (449 to 670 m) to create a dry environment beneath the water table for the proposed working point. Groundwater entered a leak in this liner (casing), rose to the top of the casing and flowed out into unsaturated tuff. More than 500,000 gallons of water containing a total of 100 Ci of tritium are estimated to have moved through this hole. Analysis of samples from U3kz showed fission products sorbed on colloidal particles in the water flowing into the hole, a fact which demonstrated that, in this case, colloid particles carried fission products in groundwater.

The SANDREEF (U7aq) event, 1,150 feet (350 m) north of U3kz, is thought to be the source of the fission products found in U3kz. The SANDREEF event had been executed in 1977. Assuming that the 100 curies of tritium came from SANDREEF, this would constitute a significant percentage of the original SANDREEF tritium source term and would thus suggest movement toward ALEMAN along a preferred path. The rate of transport of 1,150 feet (350 m) in less than 8 years is unexpectedly high. It is not known how far the radionuclides moved dynamically as a result of the SANDREEF event and how far they moved by groundwater transport.

In July 1986, exploratory hole UE-3e was drilled about 200 feet (60 m) north of U3kz, between U3kz and SANDREEF. Fission products were found in a small fracture in UE-3e, a fact that confirmed the U3kz observations. Drilling of UE-3e established that the contaminated zone between SANDREEF and U3kz could be entered at a site other than U3kz. After further studies, a sodium bromide tracer was pumped into UE-3e, the UE-3e hole was stemmed, and the ALEMAN shot was executed in the U3kz hole in September, 1986. (The use of a tracer in UE-3e accounts for the appearance of this hole on lists of injection wells-see Section 3.4.2.4). Further discussion of the ALEMAN phenomena may be found in Sewell, 1987.

3.4.2.3 Tunnel Ponds

Nuclear testing has been conducted since 1957 within the adit or tunnel system mined into the southeast side of Rainier Mesa at the Nevada Test Site. The tunnels reach nearly 3 kilometers into the center of the mesa and are between 240 meters and 700 meters below the mesa surface. The

regional groundwater system is approximately 3,000 feet (900 m) below the mesa surface. However, saturated fractures and perched water lenses are present within the formation where most of the nuclear testing is done.

Contaminated water from groundwater seepage into these tunnels is discharged into ponds through subsurface pipes. Water from these ponds can eventually infiltrate the regional carbonate aquifer because the carbonate rocks are exposed at the surface in this area. Consequently, the lowermost ponds can overflow directly into fractures in the carbonates rather than seeping downward through tuff. The ponds also receive decontamination wastes, which are generated outside the tunnels from decontamination operations conducted in the area. Rinsewater from cleaning out grout trucks has also gone into these ponds. (Grout is a fluid mixture of cement and water, sometimes including sand, bentonite, or hydrated lime.)

The ponds constitute an unpermitted discharge to waters of the state (groundwater). The wastewater in these ponds is contaminated with tritium and low levels of other fission products. Methylene chloride has been found in the T tunnel effluents and ponds, a fact that creates a mixed waste issue. Sampling and analysis of tunnel effluents, pond water, and pond sediments is also planned by the Survey to determine if these ponds receive hazardous materials and are an unpermitted facility subject to RCRA (see Section 4.1.3.2.1).

There is an active system of tunnel ponds at both N and T tunnels, an inactive system of dry ponds at E tunnel, and an inactive tunnel (G tunnel). A dry pond, which was apparently not constructed as a holding pond, was visible at G tunnel. Effluent from this tunnel is apparently contained in a 400-gallon steel holding tank. Groundwater continues to enter inactive tunnels so that some effluent may be present at both E and G tunnels. In a June 1986 sampling round, effluent was present at E tunnel but not at G tunnel. Another tunnel, P tunnel, is under construction and was not yet active at the time of the Environmental Survey.

There are six ponds at T tunnel, but the first one is essentially filled with grout. Records indicate that the total area of five ponds, presumably the remaining five, is 0.6 acres. There are also six ponds at N tunnel, two of which are full of grout. The total area of three ponds is recorded as 0.25 acre (NVO, 1986c). It is unclear which pond was not included.

The average concentration of tritium is stated to be 1.4×10^6 pCi/l at T tunnel, 6.8×10^5 pCi/l at N tunnel, and 5.0×10^5 pCi/l at G tunnel. The average annual tritium discharge is 2.7 Ci at T tunnel, 7.2 Ci at N tunnel, and 1.0 Ci at G tunnel (NVO, 1986c). The maximum tritium activity found was 8.17×10^8 pCi/l in a June 12, 1986 sampling round at T tunnel pond 2.

Methylene chloride levels were 3,450 µg/l in T tunnel effluent, 9,300 µg/l in T tunnel pond 1, and 1,800 µg/l in T tunnel pond 2. It is possible that this chemical contamination was due to an isolated, small spill rather than to any continuing discharge. Survey-related sampling of the T tunnel effluent should clarify this situation.

These ponds are also discussed in Surface Water Sections 3.3.4.2.3 and 3.3.4.2.6, as well as Waste Management Section 4.1.2.1.2 and 4.1.2.1.3.

3.4.2.4 Injection Wells

The term "injection wells" is used loosely at the NTS, and does not necessarily refer to Class I through Class V wells as usually defined in state and federal Underground Injection Control Programs. Injection wells at the NTS include hydrologic test holes used for injection of dye, inorganic, or radioactive tracers, shallow (100 feet or less) holes used for wastewater disposal from cleaning operations, holes used for discharge water from well pumping done as part of radionuclide migration studies, and deep holes used for disposal of radioactive wastes. In the latter two cases, radioactive contaminants are being disposed of in the vicinity of nuclear test cavities, where radioactive contamination already exists from the testing program regardless of any additions from waste disposal.

Considerable effort was expended during the on-site Survey to determine the use and history of various wells appearing on maps and lists of "injection wells." These include Hagestad No. 1 (12-InW-1), UE-3e (3-InW-1), UE-20ac (20-InW-2), U20av PS No. 1 (20-InW-3), water disposal holes 2-InW-1 and 3-InW-2, Pahute Mesa No. 1 (20-InW-1, formerly USGS HTH No. 9), and U8d (8-CMD-1, known to be a disposal hole for liquid radioactive waste). "InW" is the NTS Environmental Compliance Atlas code for injection wells and "CMD" is the code for core and drill mud disposal. Prefixes to these codes are area designation.

Hagestad No. 1 (named after the drilling company) is an exploratory hole located in Area 12 near the E Tunnel. It was apparently used for fluorescein dye tracer studies, probably by the U.S. Geological Survey. Therefore it appears on injection well maps and lists (Gayle, 1987a). This hole was sealed off about 15 years ago (Phillips, 1987).

UE-3e is an exploratory hole drilled as part of the ALEMAN investigation (see Section 3.4.2.2). A sodium bromide tracer was pumped into this hole, and the hole was then plugged back and

stemmed prior to ALEMAN detonation in September 1986 (App and Hawkins, 1986). The use of a tracer in this hole is the apparent reason for its inclusion on injection well maps and lists.

An injection well at the U20ac site on Pahute Mesa was used for disposal of 1 to 6 million gallons of water pumped from U20n PS 1 from 1983 through 1985 (Jacobson, 1987b). This work was a study of radionuclide migration from the CHESHIRE (U20n) cavity, discussed above in Section 3.4.2.1. In such investigations, water contaminated by radionuclides from a nuclear test cavity is returned to the subsurface in the same general area. Details of radionuclide concentrations in samples of this water may be found in Buddemeier and Isherwood, 1985; NVO, 1986b; and Jacobson et al., undated. The maximum radionuclide concentration found was for tritium at 2×10^9 pCi/l. Another well in the same area, U20av PS1a, will reportedly be used for disposal of the same type of water generated from RNM studies.

One of the wells at the REECO bit cutter rebuild shop in Area 2 is thought to be the water disposal hole listed as 2-InW-1 in the NT5 Environmental Compliance Atlas. The bit cutter rebuild shop uses two wells for wastewater disposal. One well inside the shop is used for water from cutter washing, and another outside the shop is used for water from roller washing. The outside well was observed to have an oily film on the water surface. It is not clear which of the two wells is 2-InW-1. The Fenix and Scisson Drilling and Mining Summary for Area 2 describes this hole as being 48 feet deep with a diameter of 64 inches. Work on the hole was suspended on June 24, 1980. The hole may have been intended as an emplacement hole, but found to be unsuitable after boring to a relatively shallow depth. The present hole has a 52-inch collar (surface casing), with a 20-inch casing beginning at a depth of 4 feet.

Water entering the Steam Cleaning Control Pad Sump at the Area 3 post-shot facility reportedly drains to an 88-inch-diameter, 100-foot-deep hole that is located under a 3/8-inch steel plate under the wooden parts storage rack just south of the pit. This hole may be the disposal hole listed as 3-InW-2 in the Environmental Compliance Atlas. The Fenix and Scisson Drilling and Mining Summary for Area 3 lists this hole as being 100 feet deep, 64 inches in diameter, and cased to 35 feet with 98-inch-diameter casing.

Conflicting information exists on whether Pahute Mesa No. 1 (also known as USGS Test Hole No. 9) was ever used as an "injection well." It may have received water from test cavity pumping, fluids from drilling operation, or wastes of unknown kind. This open well is an example of a possible uncontrolled waste disposal well. The area surrounding this well was once a camp for work on Pahute Mesa. The well is an open hole covered only by a steel plate weighted down with a drill bit. The only barrier is a water pipe, which must be driven over to reach the well. The well was

completed May 5, 1964, to a depth of 7,858 feet. However, it was logged in 1983/84 and found to be approximately 7,400 feet deep, due to collapse or filling of the borehole. Depth of water was measured as 2,099 feet in 1984. (Evert, 1987).

A post-shot (PS1a) reentry hole at U8d (the BANE BERRY test location -- see Section 4.3.2) has been used for disposal of liquids contaminated with radioactivity, including liquid waste from an experimental farm (see Section 4.5.2.13). Another liquid waste disposal hole, U9ITS-Y 30-PS1a, was apparently used for similar wastes (Forry, 1987). No information is available for this second deep hole. However, the U8d-PS1a hole received an estimated annual volume of 2.5×10^4 gallons during 1986. The cumulative volume since June 1984 is 8.0×10^4 gallons (Clark, 1987). Both cobalt-60 and cesium-137 were present in these wastes. No breakdown between these two nuclides is available, but the average concentration is 1.0×10^4 pCi/l and the average annual discharge is 7.0×10^{-5} Ci (NVO, 1986c).

The wells used only for tracer studies should probably not be considered as injection wells at all. However, wastewater disposal, return of contaminated water to the subsurface, and disposal of liquid wastes are all practices that fall under more conventional definitions of injection wells. Such practices may create both regulatory issues and groundwater contamination concerns. Even though groundwater may already be contaminated from underground nuclear testing, the addition of other waste materials, including wastewater, may increase the migration potential of existing radionuclides, as well as serving as an additional source term for radioactive and nonradioactive contaminants.

3.4.2.5 Sources of Soil Contamination but not Groundwater Contamination

As pointed out in Section 3.2.2.3, direct discharges to the land surface or overflow from wastewater ponds and sumps create probable soil contamination and the potential for transport of contamination by storm runoff or flash flooding. However, they do not create a potential for groundwater contamination because evaporation occurs rapidly and infiltration is very unlikely.

Inactive leachfields are also considered sources of soil contamination but not groundwater contamination. Their shallow depth promotes evaporation rather than infiltration. Such inactive leachfields are discussed in Sections 3.2.3.3 and 4.5.2.7.

Sections 3.2.2.3 and 4.5.2 describe a number of other inactive sumps, pits, and areas which are probable sources of soil contamination. Sections 4.1.2.1.2 and 4.1.2.1.4 discuss craters used for

drilling mud disposal. Because of the low migration potential of drilling muds, such waste disposal sites do not create groundwater contamination and may not cause actual soil contamination.

Surface soil contamination is created by the discharge of cutting oils onto the land surface at the Area 6 Machine and Welding Shop (Building 6-623) (see Section 4.1.2.1.1). The Building 650 leachfield in Area 23 is a probable source of soil contamination. This active leachfield receives flows from the radiochemistry laboratories, the decontamination shower, the photographic laboratory, and the silver recovery unit. Chlorinated solvents, acids, and caustics are disposed of into laboratory sinks (see Sections 4.1.2.1.2 and 4.1.2.1.3). The amount of water introduced into this leachfield is probably insufficient to move contaminants to any significant depth. Neither of these situations is considered to be a threat to groundwater.

3.4.2.6 Potential Sources of Groundwater Contamination

As a general rule, it is unlikely that groundwater contamination will occur as a result of surface operations at the Nevada Test Site, because of the great depth to the regional water table (500-3,000 feet below the surface). (The tunnel ponds discussed in Section 3.4.2.3 are considered an exception because they can infiltrate the regional carbonate aquifer more directly than is possible for most of the other surface facilities.) However, in any situation where infiltration, rather than evaporation, becomes a major pathway for movement of liquid and where repeated recharge occurs, the potential for groundwater contamination still exists, although it may be unlikely.

Wastewater disposal into shallow wells and pits promotes infiltration rather than evaporation. Such discharges create the potential for groundwater contamination. Three such facilities have been discussed in Section 3.4.2.4 because they appeared to correspond with listed injection wells. These are the two wastewater disposal holes at the REECO Bit Cutter Rebuild Shop in Area 2 and the disposal hole that receives water from the Steam Cleaning Control Pad sump at the Area 3 post-shot facility. Additional wells and pits include the following:

- A wastewater disposal pit at the Area 1 Subdock Steam Cleaning Pad (see Section 3.3.4.2).
- A probable disposal hole for water that collects in the Blow-Off Preventer servicing cellars at the Area 3 post-shot facility (see Section 3.3.4.2).
- A sump at the LLNL post-shot facility in the Area 2 support facilities (see Section 3.3.4.2).

- The J-6 classified waste disposal hole in Area 3, which is known to be used for wash water from contaminated drilling equipment (see Section 4.1.2.1.2). Hole J-11, also in Area 3, may be used in a similar manner.
- An inactive wastewater disposal well at the Core Storage Yard in Area 3 (see Section 4.5.2.15).

For any inactive surface facility in an arid climate where a deep water table is present, the potential for continuing groundwater contamination is very low. However, such contamination may have occurred during the active life of the facility.

Even for an active facility, intermittent use may allow the mobile phase (water) to evaporate before any significant depth of migration is reached. In such a case, only subsurface soil contamination would result, with an extremely low potential for groundwater contamination. Intermittent use may also determine the extent to which groundwater contamination can occur as a result of wastewater sumps, lagoons, and ponds at the NTS. These surface impoundments probably cause contaminants to build up in subsurface soil, but their recharge effect on groundwater depends on frequency of use. If all water evaporates between uses, groundwater contamination is less likely than if standing wastewater is maintained in an impoundment.

Surface impoundments with a potential for groundwater contamination include

- The wastewater pit at the Area 2 Photo Skid (see Section 3.3.4.2).
- The sewage lagoons south of CP-1 and west of Mercury Highway in Area 6. Sewage lagoons that receive only biodegradable sanitary wastes are not normally considered sources of environmental contamination, but these particular lagoons are receiving effluent from unknown sources (see Section 3.3.4.2).
- Sewage Lagoons 1 and II and the domestic sewage lagoon at Yucca Lake in Area 6 (see Section 3.3.4.2). These lagoons should receive discharges only from sanitary systems, but it is possible that cross-connections exist or that wastes other than sanitary wastes are being disposed of into sanitary sinks and drains.
- Steam Cleaning Effluent Pond I at the Building 6-623 Machine and Welding Shop and Steam Cleaning Effluent Pond II at the Building 6-800 Heavy Duty Repair Shop in Area 6 (see Section 4.1.2.1.1).

- The Decontamination Pond in Area 6 (see Section 4.1.2.1.2 and 4.1.2.1.3).
- The Well 3 Yard truck washing drain pit in Area 6 (see Section 3.3.4.2).
- The sewage pit at the Area 11 LLNL Technical Facilities (see Section 3.3.4.2). Discharges from a photography laboratory and a materials testing facility are known to enter this pit. Fuel oil spills may have occurred in this area. The pit was dry at the time of the on-site Survey. However, the amount of discharge under normal operating levels may be much greater.
- The Area 12 Industrial Wastewater Sump, which receives flow from the Fleet Operations Buildings (see Section 4.1.2.1.1).
- The sewage lagoons in Area 23, which receive flows from the Building 650 Industrial Hygiene Laboratory. This laboratory disposes of relatively small quantities of analytic chemicals down laboratory sinks (see Section 4.1.2.1.1). (Other facilities in Building 650 discharge wastewater into a leachfield rather than into sanitary lines to the sewage lagoons.)
- The sewage lagoons south of Test Cell C in Area 25 (see Section 3.3.4.2), which were not on site maps and which are receiving flows from unknown sources.

The NTS Environmental Compliance Atlas lists many wastewater disposal sites as both evaporation ponds or sumps and as leachfields. Some are shown on maps as evaporation ponds or lagoons. As discussed in Section 3.4.2.5, inactive leachfields are considered to be sources of soil contamination but not necessarily groundwater contamination. However, if some of these sites were actually operated as ponds with standing water during their active life, the potential for groundwater recharge and possible contamination existed at that time. Such distinctions in historical usage could not be clarified by discussion with site personnel. In the absence of information to the contrary, such sites are considered to have an extremely low potential for groundwater contamination.

The Hazardous Waste Landfill in Area 23 was used primarily for disposal of uncontained liquids and therefore has the potential for groundwater contamination. This site is described in Section 4.1.2.1.1. Subsurface soil contamination was generated by the December 1986 leak of Jet-A fuel generated from an underground storage tank at the Desert Rock Airstrip in Area 22 (see

Section 4.5.2.9). Because this fuel has a viscosity similar to that of kerosene and thus is likely to contain relatively mobile constituents, it has the potential for groundwater contamination.

3.4.2.7 Probable Non-Sources Such as the Area 5 Radioactive Waste Management Site (RWMS)

The Area 5 Radioactive Waste Management Site (RWMS) is a shallow land disposal facility for low-level radioactive waste. It also includes deep disposal boreholes, known as greater confinement disposal (GCD) boreholes. This site is to be expanded to include mixed (radioactive and hazardous) waste. A detailed description of these facilities and the waste types handled at the Area 5 RWMS may be found in Section 4.1.2.1.2.

A RCRA Part A and B application was submitted to the EPA in 1985 for the expansion of the facility to include mixed waste disposal cells. (It was later determined that some of the waste already buried in the existing facility was probably mixed waste.) By agreement with the State, a new RCRA Part A and the original Part B application was submitted to the State of Nevada in 1987 with the understanding that a revised Part B application would be prepared. On September 17, 1987, the State granted the RWMS interim status as a commercial mixed waste storage and disposal facility (Fitzsimmons, 1987a). An environmental assessment (EA) for the facility is also being prepared. The results of the EA will determine whether an environmental impact statement is required by the changes entailed in the RCRA permit.

The Part B application included requests for waivers of double-liner, leachate collection system, and groundwater monitoring requirements, based on the site setting. The state has authorized DOE to proceed with storage and disposal of mixed waste without liners and groundwater monitoring. However, an alternative to groundwater monitoring and liners needs to be developed before the state RCRA permit can be issued (e.g., soil moisture monitoring). In addition, NTS was required to submit to the state a statement prepared by a certified geologist demonstrating that there is little potential for migration of hazardous materials to the groundwater.

Under Part 264.90(b)(4) of 40 CFR, a waiver of groundwater monitoring requirements can be granted if the applicant can demonstrate that there is no potential for liquid migration from the regulated unit to the uppermost aquifer during the active life of the regulated unit and during the post-closure care period. The 1985 RCRA Part B application cites the following facts in support of the waiver request:

- A combination of site factors, including the extreme depth to water (800 to 900 feet), the low amount of annual precipitation (average 4.6 inches), and the naturally low moisture content of the soils (3 to 9 percent) restrict water movement through the unsaturated zone to an extremely slow rate under natural conditions. The low moisture content of the soil is caused by low precipitation and high evaporation. For liquids to flow from the land surface to the water table, the moisture content must increase to field capacity. (Field capacity is the moisture content required for the drainage of liquid water under the influence of gravity.) Field capacity for the soils at the RWMS is 12.9 percent. Unsaturated hydraulic conductivity at field capacity is approximately 5×10^{-8} cm/sec. Porosity is approximately 32 percent.
- Studies indicate that the maximum depth of infiltrating water during periods of higher precipitation (such as the Pleistocene) was approximately 7 feet below the land surface.
- Simulation of a 500-year rainfall (Kearl 1982) showed that the maximum depth of infiltrating water for this event was 3 feet below the land surface and that the moisture content of soils at depths of 17 feet was not increased significantly by the simulated event or by naturally occurring rains during the 6-month study period.

The request for a waiver from the requirements for liners or leachate control/detection systems is based on the argument that these systems would not significantly lengthen the time of waste migration to the uppermost aquifer. Another argument against liners is that the use of liners in desert regions is an unsafe practice for radioactive waste because the liner would produce a perched moisture zone in the waste. A potential would then exist for desert shrubs to sink roots into this zone and thus to transport the water and included radionuclides to the biosphere. A third argument is that liners could not be used in the GCD boreholes. A liner requirement would therefore eliminate this form of disposal for wastes unsuitable for shallow land burial but not requiring a high-level waste repository.

The fundamental justification for waivers of monitoring wells, liners, and leachate collection systems is that the hydrogeologic regime is too dry for the required systems to operate in a timely manner. As long as the waste zone is dry, there is no potential for waste migration to occur other than by gaseous diffusion. Therefore an appropriate monitoring plan would be one which detects moisture in the waste zone and detects movement of waste as a gas. Unsaturated-zone monitoring for water content by the use of neutron probes lowered through access tubes in drilled holes has been used at the NTS. (Neutron probes measure the hydrogen content of the soil, which is related to the amount of water present.) Actual waste migration by gaseous diffusion could be detected by soil-gas

monitoring. The most mobile waste constituent, tritium, would act as an intrinsic tracer in soil gas (McGrath, 1987). It is probable that techniques such as these will be proposed for the alternative monitoring systems required for the state RCRA permit.

In summary, this site is not a potential source of groundwater contamination and has a very low potential as a source of subsurface soil contamination. With respect to its low to non-existent potential as a source of environmental contamination, it is considered to be similar to the Area 3 RWMS and the disposal holes for core samples (see Section 4.1.2.1.2), construction landfills (see Section 4.1.2.1.4), most of the inactive contaminated waste dumps (see Section 4.5.2.3), inactive contaminated muck piles (see Section 4.5.2.3), and the Horn Silver Mine (see Section 4.5.2.10). An active or inactive waste management site is not necessarily a source of soil contamination. Immobile wastes are not soil, and immobile wastes in intentional burial sites are a form of land use but not of environmental contamination.

The Area 5 RWMS will become a special case within this group of sites because of its status as the first commercial mixed waste storage and disposal site to be undergoing the permitting process. It will therefore receive considerable attention and its actual, rather than potential, condition with regard to waste migration is likely to be determined.

3.4.3 Environmental Monitoring Program

Three major groundwater monitoring programs are conducted at the NTS. These are the REECO monthly monitoring program for water supply wells (radioactivity only), the Long-Term Hydrological Monitoring Program (LTHMP) carried out by the U.S. Environmental Protection Agency (EPA) Environmental Monitoring Systems Laboratory (EMSL) (radioactivity only), and REECO sampling for nonradioactive parameters required by the Safe Drinking Water Act. All sampling is done on water supply wells that were never intended as monitoring wells and are therefore not necessarily located upgradient or downgradient of source areas.

The REECO monthly samples for monitoring radioactivity are taken from spigots near the water supply wells. Sampling is done by the REECO Site Maintenance Department under the supervision of the Superintendent of Water Systems. A written sampling procedure exists in draft form (dated January 1987) as Section M14.3.4 of the NTS Environmental Surveillance Program. The sampling crew was not aware of the existence of this written procedure at the time of the Environmental Survey. Two minor discrepancies between the actual sampling and the draft written procedure were brought to the attention of the site. The description of potable water sampling in the written procedure indicated that samples were taken for quarterly gross alpha and annual strontium-90

analyses from both the potable water distribution points and from the potable water supply wells. In fact, such samples are taken only from the distribution points. The description in the procedure of the compositing method for these quarterly and annual potable water samples also differed from the method actually used.

Wells are sampled by turning on the well pump, if the well is not being pumped continuously, and allowing the pump to run for an unspecified time. No attempt is made to deal specifically with well purging. According to the draft written sampling procedure, samples are collected in new, chemically clean, 1-liter glass bottles with lids. Water is allowed to run from the spigot for a short time, both the outside and inside of the bottle are thoroughly rinsed, and the bottle is overfilled so that the contents wash the bottle lip. The lid is set firmly and excess water is removed from the outside of the bottle and lid with a clean Kimwipe or paper towel. Masking tape is used to label each water sample bottle with sample type, location, and date of collection. The same information is listed on a Daily Monitoring Trip Record.

Only gross beta and tritium analyses are performed on these monthly samples taken from spigots near the wells. Data from calendar year 1985 (Gonzalez, 1986) show that the highest gross beta average activity found on-site was at Well C-1s Area 6. This average was 10.5 pCi/l, with several data points for the year falling between 10 and 20 pCi/l. Earlier data from 1982 and 1983 suggest that gross beta activities correlate with naturally occurring potassium-40 (Gonzalez, 1986). This is reasonable, since wells C and C-1 have the highest potassium concentrations found on-site (up to 12.9 mg/l). The maximum tritium concentration found on-site during 1985 at a water supply well was $2,400 \pm 340$ pCi/l at Well J-12. This is well below the EPA drinking water standard of 20,000 pCi/l. There is no evidence of radioactive contamination at any water supply well on the NTS.

The LTHMP involves both off-site and on-site radiological sampling. Off-site sampling locations are shown on Figure 3-18; these locations are mostly supply wells for potable water but some are spring-fed pools. On-site locations are indicated on Figure 3-19. The water supply wells in the REECo monthly monitoring program are included in the LTHMP. This duplication provides independent confirmation of the REECo results. Furthermore, EMSL performs tritium enrichment (an analytical method in which the sample is concentrated by electrolysis followed by distillation) if tritium concentrations by conventional analysis are less than 700 pCi/l; REECo does not have this analytical capability. In addition to the pump-equipped water supply wells, the LTHMP includes various hydrological test holes. EMSL is able to sample deep wells without pumps by using a truck-mounted bailer system.

FIGURE 3-18

LTHMP SAMPLING LOCATIONS NEAR THE NTS
NEVADA TEST SITE - MERCURY, NV

FIGURE 3-19

LTHMP SAMPLING LOCATIONS ON THE NTS NEVADA TEST SITE - MERCURY, NV

Sampling procedures for the LTHMP wells are documented in a Field Monitoring Standard Operating Procedure, SOP NRO-11, dated January 1984. Water levels are measured prior to sampling, using an M-scope for shallow wells. A motor-operated water-level probe is part of the deep well sampling system. Well purging is not addressed in the sampling procedure. Field measurement of temperature, pH, and conductivity are made. Samples for tritium analyses are collected in 500-ml glass bottles. Samples for gamma spectrometry are collected in a 11-liter stainless steel bottle or tank, from which they are field filtered into 3.5-liter polyethylene cubitainers. Filtration is done by sealing the tank, pressurizing it with an air compressor and connecting it to a membrane filtration apparatus. Nitric acid preservative is added to the filtered samples in the cubitainers. The stainless steel tank and the containers are rinsed with distilled water or the source water or both prior to collection.

The only man-made radionuclide detected in groundwater by the LTHMP is tritium. Tritium is found only at background levels in off-site groundwater. The locations at the NTS for which tritium has been consistently elevated are Well UE-7ns and Test Well B. (Well J-12, which had elevated tritium in a single REECO sampling round during 1985, is an alternate to J-13 for the LTHMP and was not sampled by EMSL during 1985.) Well UE-7ns and Test Well B are on-site wells that are not used for drinking water. The tritium levels reported for these wells for 1986 were 130-320 pCi/l at Test Well B and 2,300-3,200 pCi/l at UE-7ns. The corresponding values for 1985 were 140-170 pCi/l at test Well B and 2,000-3,100 pCi/l at UE-7ns. UE-7ns is a satellite well for the BOURBON event, which was detonated in carbonate rock just above the water table. The tritium detected in this well indicates migration from the BOURBON cavity in the unsaturated zone to the satellite well in the saturated zone. No specific source is obvious for the low tritium levels found at Test Well B.

Nonradioactive parameters are monitored by REECO for water supply wells at 3- to 4-year intervals. Table 3-20 shows major ions and groundwater quality parameters. Table 3-21 shows trace metals and miscellaneous parameters. Values exceeding drinking water limits are noted in these tables. Exceedances are found both for wells used for drinking water and for those used only for construction site water. The only parameters exceeding these limits are nitrate, fluoride, iron, manganese, total dissolved solids, and a single exceedance each for mercury, lead, and color. (The fluoride limit of 1.6 mg/l is a Nevada standard based on the annual average of the maximum daily air temperature. The EPA Maximum Contaminant Level (MCL) for fluoride is 4.0 mg/l. A secondary MCL of 2.0 mg/l also exists. Secondary standards primarily affect the aesthetic qualities relating to the public acceptance of drinking water.) These analyses are performed by Montgomery Laboratories in Pasadena, California. No written procedure exists for this sampling, and no details of sampling methodology are available. However, the samples are taken from spigots near the wells.

TABLE 3-20

MAJOR IONS AND GROUNDWATER QUALITY PARAMETERS FOR WATER SUPPLY WELLS
NEVADA TEST SITE, MERCURY, NEVADA

Chemical Analysis Performed	Maximum Contaminant Levels Allowed	Units	J-12				J-13				C				A			
			1973	1977	1981	1984	1973	1977	1981	1984	1973	1977	1981	1984	1973	1977	1981	1984
Calcium (Ca)	2,500	mg/l	14	15	18	14.2	13	11	18	12.5	76	71	84.2	75.7	22	21	30.1	22
Magnesium (Mg)		mg/l	3	5	13.4	2.2	3	6	12.2	1.8	29	28	35.3	29.6	7	8	14.6	7
Sodium (Na)		mg/l	-	42	38	NA	-	47	40.7	NA	127	120	115	NA	52	50	48.7	NA
Potassium (K)		mg/l	-	5.1	4	NA	-	3.9	4	NA	12	12.9	7.3	NA	7.4	7.4	7.3	NA
pH	1	mg/l	7.8	7.4	7.4	7.6	7.7	7.4	7.4	7.5	7.1	7.3	7.2	7.7	8	7.6	7.7	7.8
Carbonate (CO ₃)		mg/l	ND	-	ND	NA	ND	-	ND	NA	-	-	ND	NA	-	-	ND	NA
Bicarbonate (HCO ₃)		mg/l	117	120	128	NA	120	131	134	NA	574	568	574	NA	214	190	214	NA
Alkalinity			NA	NA	NA	105	NA	NA	NA	106	NA	NA	NA	479	NA	NA	NA	175
Sulfate (SO ₄)	250	mg/l	23	26	22	11.7	20	20	19	10	58	69	62	33.7	7	21	18	10.7
Chloride (Cl)	250	mg/l	8	12	13	7	7	12	15	6	38	37	40	35	9	18	13	7
Nitrate (NO ₃)	10	mg/l	7	13.5	4.24	1.7	8.1	4.7	2.8	1.9	Trace	2.4	< 0.1	0.2	4.7	13.5	0.879	1.8
Fluoride (F)	1.6	mg/l	1.85	2.0	2.1	2.1	2.09	2.35	2.6	2.5	1.53	1.2	1.05	1.1	0.76	0.64	0.8	0.7
Specific Conductance		µmhos/cm	-	250	260	NA	-	260	270	NA	1,060	950	1,030	NA	388	345	380	NA
Boron (B)		mg/l	-	ND	< 0.5	NA	-	ND	2.4	NA	ND	0.8	0.6	NA	ND	ND	0.12	NA
Silica (SiO ₂)		mg/l	-	50	16	NA	-	56	23	NA	26	25	15	NA	67	62	26	NA
Nitrite (NO ₂)		mg/l	-	0.1	< 0.1	NA	-	0.07	< 0.1	NA	0.03	0.07	< 0.1	NA	0.05	0.01	< 0.1	NA
Iron (Fe)	0.3	mg/l	0.02	0.17	0.035	0.94	0	0.36	0.025	0.26	ND	0.98	0.406	0.088	ND	0.03	0.11	0.049
Manganese (Mn)	0.05	mg/l	-	ND	0.003	0.046	-	ND	0.012	0.017	ND	ND	0.02	< 0.12	ND	ND	0.003	< 0.12
TDS	500	Units	210	207	240	208	221	215	230	220	670	786	685	528	324	286	320	286
Hardness (as CaCO ₃)		mg/l	52	58	10	NA	44	50	95	NA	310	292	355	NA	84	88	135	NA
Sodium, Percent Total Cations			-	59	43.8	NA	-	65	46.9	NA	46	46	40.7	NA	55	53	43	NA

TABLE 3-20
MAJOR IONS AND GROUNDWATER QUALITY PARAMETERS FOR WATER SUPPLY WELLS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE TWO

Chemical Analysis Performed	Maximum Contaminant Levels Allowed	Units	Army Well #1				58				5C				UE-5C			
			1973	1977	1981	1984	1973	1977	1981	1984	1973	1977	1981	1984	1973	1977	1981	1984
Calcium (Ca)		mg/l	4.6	44	49.1	45.4	7.4	12	15	7.4	2	ND	5	0.7	7	6	**	8.7
Magnesium (Mg)		mg/l	22	23	33.4	27.4	1.6	4	3	2.2	1.2	2	1.3	0.2	3	3	**	2
Sodium (Na)		mg/l	33	38	32.7	NA	99	42	78	NA	132	48	122	NA	78	77	**	NA
Potassium (K)		mg/l	3.9	4.7	5.33	NA	8.6	10.9	13.5	NA	5.1	5.5	8.4	NA	5.1	5.5	**	NA
pH		mg/l	7.7	7.4	7.4	7.6	6.7	8.1	7.9	8.5	8.9	8.5	8.2	8.9	8.4	8.3	**	8.4
Carbonate (CO ₃)		mg/l	ND	ND	ND	NA	15	--	ND	NA	36	38	ND	NA	12	17	**	NA
Bicarbonate (HCO ₃)		mg/l	259	242	259	NA	153	197	140	NA	238	226	250	NA	153	141	**	NA
Alkalinity			NA	NA	NA	222	NA	NA	NA	152	NA	NA	NA	262	NA	NA	**	151
Sulfate (SO ₄)	250	mg/l	45	53	50	23.6	45	57	59.1	28	17	26	26.3	13.5	29	42	**	22
Chloride (Cl)	250	mg/l	19	20	25	16	27	25	30	23	14	14	15	9	14	10	**	12
Nitrate (NO ₃)	10	mg/l	1.7	2.85	0.068	0.2	8.4	15.6	2.1	2.8	5.5	9	1.9	1.6	4.6	6.3	**	1.3
Fluoride (F)	16	mg/l	1.2	1.1	1	1.1	0.9	0.84	0.65	0.9	0.9	0.91	0.7	1.0	2.3	1.55	**	1.8
Specific Conductance		µmhos/cm	530	500	530	NA	500	500	440	NA	560	520	530	NA	410	400	**	NA
Boron (B)		mg/l	ND	0.6	0.12	NA	ND	0.72	<0.5	NA	ND	0.72	<0.5	NA	ND	0.43	**	NA
Silica (SiO ₂)		mg/l	15	16	10	NA	54	48	--	NA	48	44	--	NA	58	48	**	NA
Nitrite (NO ₂)		mg/l	0.02	0.07	<0.1	NA	0.02	0.09	<0.5	NA	0.02	0.06	<0.5	NA	0.04	0.42	**	NA
Iron (Fe)	0.3	mg/l	ND	0.17	0.03	<0.50	ND	0.24	0.018	0.048	ND	0.03	0.038	<0.30	0.73	0.29	**	0.68
Manganese (Mn)	0.05	mg/l	ND	ND	0.003	0.024	ND	ND	<0.01	<0.12	ND	ND	<0.01	<0.12	ND	ND	**	0.049
TDS	500	Units	370	389	325	310	408	357	300	325	426	366	345	374	340	294	**	302
Hardness (as CaCO ₃)		mg/l	205	202	260	NA	25	45	28	NA	8	7	10	NA	30	28	**	NA
Sodium, Percent Total Cations			27	28	21	NA	86	78	91.8	NA	97	95	92.6	NA	82	82	**	NA

TABLE 3-20
MAJOR IONS AND GROUNDWATER QUALITY PARAMETERS FOR WATER SUPPLY WELLS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE THREE

Chemical Analysis Performed	Maximum Contaminant Levels Allowed	Units	UE-15d				8				19C		
			1973	1977	1981	1984	1973	1977	1981	1984	1977	1981	1984
Calcium (Ca)		mg/l	32	39	**	34.6	54	52	62.1	58.3	ND	**	1.1
Magnesium (Mg)		mg/l	13	10	**	14.6	14	18	24.9	15.8	4	**	<0.1
Sodium (Na)		mg/l	28	29	**	NA	86	80	56	NA	72	**	NA
Potassium (K)		mg/l	5.5	5.9	**	NA	11	14.1	13.3	NA	0.8	**	NA
pH		mg/l	7.8	7.7	**	7.5	7.3	7.5	7.2	7.4	7.1	**	8.6
Carbonate (CO ₃)		mg/l	--	--	**	NA	--	--	ND	NA	--	**	NA
Bicarbonate (HCO ₃)		mg/l	204	200	**	NA	390	374	360	NA	165	**	NA
Alkalinity			NA	NA	**	188	NA	NA	NA	330	NA	**	66
Sulfate (SO ₄)	250	mg/l	9	24	**	12.3	38	35	35	21	14	**	4.1
Chloride (Cl)	250	mg/l	10	8	**	6	19	24	23	14	7	**	2
Nitrate (NO ₃)	10	mg/l	3.8	11	**	1.3	1.1	3.5	0.053	0.4	4.7	**	0.6
Fluoride (F)	1.6	mg/l	0.48	0.38	**	0.4	1.6	4.22	0.75	1.3	5.9	**	2.0
Specific Conductance		µmhos/cm	376	340	**	NA	730	650	650	NA	270	**	NA
Boron (B)		mg/l	ND	ND	**	NA	ND	ND	0.12	NA	ND	**	NA
Silica (SiO ₂)		mg/l	46	42	**	NA	14	24	24	NA	38	**	NA
Nitrite (NO ₂)		mg/l	0.03	0.06	**	NA	0.01	0.05	<0.01	NA	0.09	**	NA
Iron (Fe)	0.3	mg/l	ND	0.03	**	<0.30	ND	0.03	38.9	8.4	0.08	**	1.2
Manganese (Mn)	0.05	mg/l	ND	ND	**	<0.12	ND	ND	0.036	0.13	ND	**	0.049
TDS	500	Units	246	282	**	270	530	533	445	214	152	**	102
Hardness (as CaCO ₃)		mg/l	134	138	**	NA	195	205	258	NA	15	**	NA
Sodium, Percent Total Cations			30	30	**	NA	47	44	30.7	NA	91	**	NA

TABLE 3-20
MAJOR IONS AND GROUNDWATER QUALITY PARAMETERS FOR WATER SUPPLY WELLS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE FOUR

Chemical Analysis Performed	Maximum Contaminant Levels Allowed	Units	UE-104			4		UE-1r
			77	84	84	81	84	
Calcium (Ca)		mg/l	68	76.2	75.7	26	22.6	20
Magnesium (Mg)		mg/l	30	23.1	24.4	7.1	24.4	9.4
Sodium (Na)		mg/l	28	60.7	NA	41	NA	NA
Potassium (K)		mg/l	7.8	6.67	NA	4.9	NA	NA
pH		mg/l	7.8	7.3	7.4	7	7.4	7.8
Carbonate (CO ₃)		mg/l	ND	ND	NA	0.1	NA	NA
Bicarbonate (HCO ₃)		mg/l	270	378	NA	158.6	NA	NA
Alkalinity			NA	NA	310	NA	138	206
Sulfate (SO ₄)	250	mg/l	49	75	28	40	28	13
Chloride (Cl)	250	mg/l	9.2	20	9	11	10	7
Nitrate (NO ₃)	10	mg/l	--	<.01	<.015	3.3	3.7	0.8
Fluoride (F)	1.6	mg/l	0.4	0.8	0.60	0.9	0.8	1.7
Specific Conductance		umhos/cm	590	720	NA	400	NA	NA
Boron (B)		mg/l	--	<.05	NA	0.26	NA	NA
Silica (SiO ₂)		mg/l	--	16	NA	3.7	NA	NA
Nitrite (NO ₂)		mg/l	--	<.01	NA	ND	NA	NA
Iron (Fe)	0.3	mg/l	0.18	0.204	0.17	0.034	0.14	0.44
Manganese (Mn)	0.05	mg/l	--	0.034	0.03	0.019	0.03	0.035
TDS	500	Units	--	530	380	240	278	276
Hardness (as CaCO ₃)		mg/l	--	285	NA	95	NA	NA
Sodium, Percent Total Cations			--	31	NA	48	NA	NA

TABLE 3-20
 MAJOR IONS AND GROUNDWATER QUALITY PARAMETERS FOR WATER SUPPLY WELLS
 NEVADA TEST SITE, MERCURY, NEVADA
 PAGE FIVE

** Not tested in 1981 since not used as potable water
 ND None detected
 NA Not analyzed

NOTES

1. The "Safe Drinking Water Act" establishes maximum contaminant levels for community water systems. The second column from the left defines those limits.
2. The bold values are those which exceed the limits.
3. Milligrams per liter (mg/l) is approximately equal to parts per million (ppm).

Source: REECo data compilation, unpublished.

TABLE 3-21

TRACE METALS AND MISCELLANEOUS PARAMETERS FOR WATER SUPPLY WELLS
NEVADA TEST SITE, MERCURY, NEVADA

Chemical Analysis Performed	Maximum Contaminant Levels Allowed	Units	J-12				J-13			
			1973	1977	1981	1984	1973	1977	1981	1984
Aluminum (Al)		mg/l	ND	ND	0.291	NA	—	ND	1.6	NA
Arsenic (As)	0.05	mg/l	ND	ND	0.001	0.007	0.01	ND	0.007	0.008
Lead	0.05	mg/l	—	ND	0.006	0.023	—	ND	<0.005	0.002
Selenium (Se)	0.01	mg/l	—	0.001	<0.001	0.002	—	0.001	<0.001	<0.001
Barium (Ba)	1	mg/l	—	ND	<0.1	<0.012	—	ND	<0.1	<0.012
Zinc (Zn)	5	mg/l	—	0.015	0.215	0.009	—	0.02	0.146	0.007
Copper (Cu)	1	mg/l	—	ND	0.003	<0.007	—	ND	0.004	<0.007
Mercury (Hg)	0.002	mg/l	—	ND	<0.001	0.004	—	ND	<0.001	<0.003
Chromium (Cr)	0.05	mg/l	—	ND	<0.002	<0.029	—	ND	0.015	<0.029
Cadmium (Cd)	0.01	mg/l	—	ND	<0.002	<0.003	—	ND	<0.001	0.004
Suspended Solids		mg/l	—	6	<1.0	NA	—	ND	2	NA
Cyanide (CN)		mg/l	—	ND	<0.001	NA	—	ND	<0.001	NA
Silver (Ag)	0.05	mg/l	—	ND	0.001	0.006	—	ND	<0.001	0.008
Foaming Agents	0.5	mg/l	—	0.02	<0.001	NA	—	0.02	<0.001	NA
Hydrogen Sulfide (H-H-S)	0.05	mg/l	—	ND	<0.05	NA	—	ND	<0.05	NA
Turbidity		JTU	0.62	23	0.6	7.0	0.43	0.43	0.6	0.8
Color	15	units	5	30	1	<3	6	1	2	<3
Odor	3	units	—	1	2	17@	—	1	2	17@
Polychlorinated Biphenyls (PCB)			—	ND	ND	NA	—	ND	ND	NA

TABLE 3-21
TRACE METALS AND MISCELLANEOUS PARAMETERS FOR WATER SUPPLY WELLS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE TWO

Chemical Analysis Performed	Maximum Contaminant Levels Allowed	Units	C				A			
			1973	1977	1981	1984	1973	1977	1981	1984
Aluminum (Al)		mg/l	ND	ND	0.291	NA	ND	ND	0.147	NA
Arsenic (As)	0.05	mg/l	ND	ND	0.008	0.004	ND	ND	0.007	0.005
Lead	0.05	mg/l	ND	0.02	0.006	< 0.002	ND	ND	< 0.005	< 0.002
Selenium (Se)	0.01	mg/l	ND	0.002	< 0.001	< 0.001	ND	0.002	< 0.001	0.001
Barium (Ba)	1	mg/l	ND	0.6	< 0.1	0.11	ND	ND	< 0.1	< 0.12
Zinc (Zn)	5	mg/l	--	0.015	0.013	0.011	--	0.227	0.031	< 0.07
Copper (Cu)	1	mg/l	--	0.014	0.003	< 0.007	--	0.006	0.003	< 0.07
Mercury (Hg)	0.002	mg/l	--	ND	< 0.001	< 0.003	--	ND	< 0.001	< 0.003
Chromium (Cr)	0.05	mg/l	ND	ND	0.018	< 0.029	ND	ND	0.006	< 0.29
Cadmium (Cd)	0.01	mg/l	ND	ND	0.009	< 0.003	ND	ND	0.006	< 0.003
Suspended Solids		mg/l	ND	ND	3	NA	ND	ND	< 0.1	NA
Cyanide (CN)		mg/l	--	ND	< 0.001	NA	--	ND	< 0.001	NA
Silver (Ag)	0.05	mg/l	--	ND	< 0.001	< 0.005	--	ND	< 0.001	< 0.005
Foaming Agents	0.5	mg/l	--	0.04	< 0.001	NA	--	0.04	< 0.001	NA
Hydrogen Sulfide (H-H-S)	0.05	mg/l	--	ND	< 0.05	NA	--	ND	< 0.5	NA
Turbidity		JTU	3	0.25	0.62	0.5	3	1.2	0.5	0.4
Color	15	units	3	1	< 0.5	< 3	3	1	< 0.5	3
Odor	3	units	0	1	1	8@	0	1	1	8@
Polychlorinated Biphenyls (PCB)			--	ND	ND	NA	--	ND	ND	NA

TABLE 3-21
TRACE METALS AND MISCELLANEOUS PARAMETERS FOR WATER SUPPLY WELLS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE THREE

Chemical Analysis Performed	Maximum Contaminant Levels Allowed	Units	Army Well #1				5 B			
			1973	1977	1981	1984	1973	1977	1981	1984
Aluminum (Al)		mg/l	ND	ND	0.147	NA	ND	ND	<0.1	NA
Arsenic (As)	0.05	mg/l	0.01	ND	0.009	0.006	0.01	ND	0.01	0.006
Lead	0.05	mg/l	ND	ND	<.005	<.002	ND	ND	<.005	<.002
Selenium (Se)	0.01	mg/l	0.003	ND	<.001	<.001	ND	ND	<.002	0.001
Barium (Ba)	1	mg/l	ND	ND	<.10	0.08	ND	ND	<.05	<.012
Zinc (Zn)	5	mg/l	--	0.27	0.02	<.007	--	0.29	0.026	<.007
Copper (Cu)	1	mg/l	--	0.011	<.001	<.007	--	0.013	0.042	<.007
Mercury (Hg)	0.002	mg/l	--	ND	<.001	<.0003	--	ND	<.001	.0007
Chromium (Cr)	0.05	mg/l	ND	ND	0.012	<.029	ND	ND	0.001	<.029
Cadmium (Cd)	0.01	mg/l	ND	ND	<.001	0.007	ND	ND	0.003	<.003
Suspended Solids		mg/l	ND	ND	3	NA	2	ND	<.01	NA
Cyanide (CN)		mg/l	--	ND	<.001	NA	--	ND	0.001	NA
Silver (Ag)	0.05	mg/l	--	ND	<.001	<.005	--	ND	0.001	0.009
Foaming Agents	0.5	mg/l	--	0.08	<.001	NA	--	0.09	<.001	NA
Hydrogen Sulfide (H-H-S)	0.05	mg/l	--	ND	<.05	NA	--	ND	<.05	NA
Turbidity		JTU	4	0.21	1	0.15	5	1.3	0.68	0.35
Color	15	units	3	1	<.50	<3	3	4	1	<3
Odor	3	units	0	1	2	8@	0	1	2	8@
Polychlorinated Biphenyls (PCB)			--	ND	ND	NA	--	ND	ND	NA

TABLE 3-21
TRACE METALS AND MISCELLANEOUS PARAMETERS FOR WATER SUPPLY WELLS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE FOUR

Chemical Analysis Performed	Maximum Contaminant Levels Allowed	Units	5 C					UE-5C				
			1973	1977	1981	1984	1984	1973	1977	1981	1984	1984
Aluminum (Al)		mg/l	ND	ND	<0.1	NA	NA	ND	0.08	**	NA	NA
Arsenic (As)	0.05	mg/l	0.04	0.026	0.04	0.01	0.01	ND	ND	**	0.005	0.005
Lead	0.05	mg/l	ND	ND	<0.05	<0.02	<0.02	ND	ND	**	<0.02	<0.02
Selenium (Se)	0.01	mg/l	0.006	ND	<0.02	<0.01	<0.01	ND	ND	**	0.002	0.002
Barium (Ba)	1	mg/l	ND	ND	<0.05	<0.12	<0.12	ND	ND	**	0.02	0.02
Zinc (Zn)	5	mg/l	--	0.14	0.032	<0.07	<0.07	--	0.48	**	<0.07	<0.07
Copper (Cu)	1	mg/l	--	0.009	0.004	<0.07	<0.07	--	0.011	**	<0.07	<0.07
Mercury (Hg)	0.002	mg/l	--	ND	<0.002	<0.003	<0.003	--	ND	**	<0.003	<0.003
Chromium (Cr)	0.05	mg/l	ND	ND	0.001	<0.029	<0.029	ND	ND	**	<0.029	<0.029
Cadmium (Cd)	0.01	mg/l	ND	ND	0.002	<0.003	<0.003	ND	0.01	**	0.009	0.009
Suspended Solids		mg/l	1	ND	<0.1	NA	NA	ND	4	**	NA	NA
Cyanide (CN)		mg/l	--	ND	0.01	NA	NA	--	ND	**	NA	NA
Silver (Ag)	0.05	mg/l	--	ND	0.001	<0.005	<0.005	--	ND	**	0.008	0.008
Foaming Agents	0.5	mg/l	--	0.31	<0.01	NA	NA	--	0.04	**	NA	NA
Hydrogen Sulfide (H-H-S)	0.05	mg/l	--	ND	<0.05	NA	NA	ND	ND	**	NA	NA
Turbidity		JTU	3	1	0.75	0.25	0.25	3	1.8	**	1.9	1.9
Color	15	units	3	1	1	3	3	11	10	**	3	3
Odor	3	units	0	1	2	8@	8@	0	1	**	17@	17@
Polychlorinated Biphenyls (PCB)			--	ND	ND	NA	NA	--	ND	**	NA	NA

TABLE 3-21
TRACE METALS AND MISCELLANEOUS PARAMETERS FOR WATER SUPPLY WELLS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE FIVE

Chemical Analysis Performed	Maximum Contaminant Levels Allowed	Units	2					UE-15d				
			1973	1977	1981	1984		1973	1977	1981	1984	
Aluminum (Al)		mg/l	ND	ND	**	NA		ND	0.1	0.147	ND	
Arsenic (As)	0.05	mg/l	ND	ND	**	0.003		0.01	ND	0.002	0.01	
Lead	0.05	mg/l	ND	ND	**	< .002		ND	ND	< .005	0.059	
Selenium (Se)	0.01	mg/l	ND	0.001	**	0.001		0.003	0.001	< .001	< .0001	
Barium (Ba)	1	mg/l	ND	ND	**	< .012		ND	-0.7	< .01	0.12	
Zinc (Zn)	5	mg/l	--	0.018	**	0.021		--	0.032	0.03	0.072	
Copper (Cu)	1	mg/l	--	0.006	**	< .007		--	0.014	0.007	0.059	
Mercury (Hg)	0.002	mg/l	--	ND	**	0.0004		--	ND	< .001	0.002	
Chromium (Cr)	0.05	mg/l	ND	ND	**	< .029		ND	ND	0.021	< .029	
Cadmium (Cd)	0.01	mg/l	ND	ND	**	< .003		ND	ND	0.005	0.007	
Suspended Solids		mg/l	ND	ND	**	NA		1	ND	9	NA	
Cyanide (CN)		mg/l	--	ND	**	NA		--	ND	< .001	NA	
Silver (Ag)	0.05	mg/l	--	ND	**	0.014		--	ND	< .001	< .005	
Foaming Agents	0.5	mg/l	--	0.13	**	NA		--	0.02	0.015	NA	
Hydrogen Sulfide (H-H-S)	0.05	mg/l	--	ND	**	NA		--	ND	< .05	NA	
Turbidity		JTU	3	0.19	**	0.1		4	0.9	1.03	43	
Color	15	units	3	1	**	3		3	1	1	3	
Odor	3	units	0	1	**	8@		0	1	1	4@	
Polychlorinated Biphenyls (PCB)			--	ND	**	NA		--	ND	ND	NA	

TABLE 3-21
TRACE METALS AND MISCELLANEOUS PARAMETERS FOR WATER SUPPLY WELLS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE SIX

Chemical Analysis Performed	Maximum Contaminant Levels Allowed	Units	8					19c		
			1973	1977	1981	1984	1984	1973	1977	1984
Aluminum (Al)		mg/l	ND	ND	0.427	NA	NA	ND	**	NA
Arsenic (As)	0.05	mg/l	ND	ND	0.001	<.001	<.001	ND	**	0.002
Lead	0.05	mg/l	ND	ND	0.006	<.002	<.002	ND	**	<.002
Selenium (Se)	0.01	mg/l	ND	0.002	<.001	0.002	0.002	0.002	**	<.001
Barium (Ba)	1	mg/l	ND	ND	<.01	<.012	<.012	ND	**	<.012
Zinc (Zn)	5	mg/l	--	0.02	0.141	0.012	0.012	0.032	**	<.007
Copper (Cu)	1	mg/l	--	ND	0.004	<.007	<.007	ND	**	0.008
Mercury (Hg)	0.002	mg/l	--	ND	<.001	<.0003	<.0003	ND	**	<.0003
Chromium (Cr)	0.05	mg/l	ND	ND	<.002	<.029	<.029	ND	**	<.029
Cadmium (Cd)	0.01	mg/l	ND	ND	0.002	0.005	0.005	ND	**	0.004
Suspended Solids		mg/l	ND	ND	1	NA	NA	ND	**	NA
Cyanide (CN)		mg/l	--	ND	<.001	NA	NA	ND	**	NA
Silver (Ag)	0.05	mg/l	--	ND	<.001	0.010	0.010	ND	**	<.005
Foaming Agents	0.5	mg/l	--	0.09	<.001	NA	NA	0.02	**	NA
Hydrogen Sulfide (H-H-S)	0.05	mg/l	--	ND	<.05	NA	NA	ND	**	NA
Turbidity		JTU	3	0.95	0.6	0.2	0.2	1.3	**	6.8
Color	15	units	3	3	1	<3	<3	13	**	15
Odor	3	units	0	1	1	8@	8@	1	**	8@
Polychlorinated Biphenyls (PCB)			--	ND	ND	NA	NA	ND	**	NA

TABLE 3-21
TRACE METALS AND MISCELLANEOUS PARAMETERS FOR WATER SUPPLY WELLS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE SEVEN

Chemical Analysis Performed	Maximum Contaminant Levels Allowed	Units	UE-16d			UE-1r		
			1973	1977	1984	1973	1977	1984
Aluminum (Al)		mg/l	—	2.47	NA	ND	NA	NA
Arsenic (As)	0.05	mg/l	—	0.002	< .001	0.02	0.005	0.027
Lead	0.05	mg/l	—	< .005	< .002	ND	< .002	0.005
Selenium (Se)	0.01	mg/l	—	< .001	0.003	ND	0.001	0.001
Barium (Ba)	1	mg/l	—	< .01	0.11	0.018	< .012	< .012
Zinc (Zn)	5	mg/l	—	0.11	0.023	0.017	< .007	0.031
Copper (Cu)	1	mg/l	—	0.007	< .007	ND	< .007	< .007
Mercury (Hg)	0.002	mg/l	—	< .001	< .0003	NA	< .0003	< .0003
Chromium (Cr)	0.05	mg/l	—	0.019	< .029	ND	< .029	< .029
Cadmium (Cd)	0.01	mg/l	—	0.002	0.007	ND	< .003	< .003
Suspended Solids		mg/l	—	11	NA	1	NA	NA
Cyanide (CN)		mg/l	—	< .001	NA	NA	NA	NA
Silver (Ag)	0.05	mg/l	—	< .001	0.008	ND	0.007	< .005
Foaming Agents	0.5	mg/l	—	< .001	NA	NA	NA	NA
Hydrogen Sulfide (H-H-S)	0.05	mg/l	—	< .05	NA	NA	NA	NA
Turbidity		JTU	—	2.05	12.5	NA	0.65	12.7
Color	15	units	—	2	10	NA	< 3	5
Odor	3	units	—	2	17@	NA	17@	8@
Polychlorinated Biphenyls (PCB)			—	ND	NA	NA	NA	NA

TABLE 3-21
TRACE METALS AND MISCELLANEOUS PARAMETERS FOR WATER SUPPLY WELLS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE EIGHT

** Not tested in 1981 since not used as potable water
ND None Detected
NA Not Analyzed
@ Units not consistent

- (1) The "Safe Drinking Water Act" establishes maximum contaminant levels for community water systems. The second column from the left defines those limits.
(2) The bold values are those which exceed the limits.
(3) Milligrams per liter (mg/l) is approximately equal to parts per million (ppm).

Source: REECo data compilation, unpublished.

The groundwater analyses were performed in 1984 by the Oregon Health Division on samples from these water supply wells. No details on sampling methodology are available. Parameters analyzed were chloroform, dichlorobromomethane, dibromochloromethane, bromoform, and total trihalomethanes at a detection limit of 1 µg/l (ppb). Nothing was detected. No other organic analyses have been performed, and none are required as yet under the Safe Drinking Water Act. However, at the time of the on-site Survey, REECO was planning to initiate monitoring for volatile organic compounds in advance of regulatory requirements.

3.4.4 Findings

Category II findings on the lack of permits for discharges into injection wells, sumps, lagoons, or ponds are presented in Sections 3.3.4.2.2 and 3.3.4.2.3. Some of these unpermitted facilities may contain potentially hazardous or mixed wastes and thus may be subject to RCRA regulations, as described in the Category II finding in Section 4.1.3.2.1. (In general, discharges are permitted under the Clean Water Act, and facilities are permitted under RCRA.) The environmental problems with regard to potential for groundwater contamination, as distinguished from regulatory compliance aspects, are discussed in Findings 3.4.4.3.3, 3.4.4.3.5, and 3.4.4.3.6 below.

3.4.4.1 Category I

None.

3.4.4.2 Category II

None.

3.4.4.3 Category III

1. Undefined Groundwater Flow Rates and Directions. Groundwater flow rates and direction of flow cannot be defined in many areas of NTS due to the absence of monitoring wells in these areas. The consequence of data gaps in groundwater monitoring is that the location and flow of contaminants cannot be accurately predicted.

Groundwater data are available primarily from areas such as Yucca Flat and Pahute Mesa, where many holes have been drilled for nuclear testing. Information gathering from holes drilled for the testing program is subordinate to the needs and schedule of that program. However, any holes drilled in an appropriate location on the NTS for any reason, by the

national laboratories or by NVO contractors, is used on a noninterference basis to obtain whatever hydrologic information is available (NVO, 1986b).

Another source of hydrologic information is the water supply wells at the NTS. However, most wells were installed for purposes other than groundwater monitoring and are not in the most pertinent monitoring locations. Large areas both on-site and off-site have no monitoring points.

With the exception of new data from the proposed Yucca Mountain high-level waste repository (off-site), investigators have reworked old hydrologic data from the NTS over the past 20 years. Advances in understanding the flow paths and rate of movement of groundwater have been largely due to the application of evolving concepts and advances in the field of hydrology, and not to expansion of the hydrogeologic data base. More data are needed to support conceptual models of the NTS hydrologic system and to define more closely the flow paths of water leaving the site.

The scope of the need for more data goes beyond routine monitoring. Both near-source and near-receptor well locations would provide important information. Near-source wells would be used for field hydrogeologic studies, such as the pumping of wells near cavities to determine the potential for radionuclide migration. Wells farther away from sources in the direction of receptors would be used to determine whether groundwater flow paths exist from testing areas to off-site areas. Drilling and study of one well for one year is estimated to cost 1 million under NTS conditions.

An initial Five-Well Program delineating five strategic locations for installation of new hydrologic test holes on-site and off-site has been developed by the Desert Research Institute and the U.S. Geological Survey. Two of the five locations are off-site areas of particular interest. These are the Thirsty Canyon areas southwest of the Pahute Mesa in the direction of the nearest population, and the areas southeast of the site toward Indian Springs. The Indian Springs area is significant because it has been assumed that groundwater from the NTS flows only to the southwest toward Ash Meadows and the Amargosa Desert and does not enter the Las Vegas flow system to the southeast. However, the possibility exists for groundwater in the alluvium from Yucca and Frenchman Flats to enter the Paleozoic carbonate formations and flow toward Indian Springs and Las Vegas. This groundwater flow regime is in fractured rocks where rates and direction of flow are difficult to interpret and where extremely limited hydrologic and chemical data in the appropriate carbonate formations are currently available.

2. Groundwater Contamination from Underground Nuclear Testing. Underground nuclear detonations conducted near or below the water table have resulted in the radioactive contamination of the groundwater, principally with tritium, within and surrounding the test chimneys and cavities. Creation of fractures from detonations and the combination of natural and event-related hydraulic forces could result in more widespread groundwater contamination. This is shown by the fact that tritium and other radionuclides have been found in some areas not immediately adjacent to cavities and chimneys. For example, fission products were found in an emplacement hole U3kz, approximately 1,000 feet from a nuclear detonation at U7ag which is the suspected contamination source. However, for groundwater contamination in general, the possibility of off-site migration is low. This low potential is the result of cation adsorption on soil, slow groundwater flow rates, and decay of radionuclides before site boundaries are reached (see Sections 3.4.2.1 and 3.4.2.2).

3. Tunnel Ponds. Contaminated water from groundwater seepage into tunnels used for nuclear testing at Rainier Mesa on the NTS is discharged into tunnel ponds from which it may eventually infiltrate the regional carbonate aquifer. Carbonate rocks are exposed at the surface in the area, and the lowermost ponds in a tunnel system can overflow directly into fractures in the carbonate rather than seeping downward through tuff. There is an active system of tunnel ponds at both N and T tunnels. G tunnel is currently inactive and has no holding ponds. Effluent from this tunnel is contained in a 400-gallon steel holding tank. E tunnel is also inactive, but effluent is still produced from groundwater seepage into the tunnel. In a June 1986 sampling round, effluent was present at E tunnel but not at G tunnel.

The major contaminant at the tunnel ponds is tritium, but other fission products are also present. The average concentration of tritium is stated to be 1.4×10^6 pCi/l at T tunnel, 6.8×10^5 pCi/l at N tunnel, and 5.0×10^5 pCi/l at G tunnel. The average annual tritium discharge is 2.7 Ci at T tunnel, 7.2 Ci at N tunnel, and 1.0 Ci at G tunnel (NVO, 1986c). The maximum tritium activity found in a June 1986 sampling round was 8.17×10^8 pCi/l at T tunnel pond 2.

Effluent from the tunnels and water samples from two ponds at each tunnel were sampled in the June 1986 round. Methylene chloride was found in the T tunnel effluent and ponds. Methylene chloride levels were 3,450 $\mu\text{g/l}$ in T tunnel effluent, 9,300 $\mu\text{g/l}$ in T tunnel pond 1, and 1,800 $\mu\text{g/l}$ in T tunnel pond 2. It is possible that this chemical contamination resulted from an isolated, small spill rather than any continuing discharge. The presence of this solvent may create a mixed waste issue under RCRA regulations (see Section 4.1.3.2.1, a Category II Waste

Management finding). Sampling and analysis of tunnel effluent and pond water and sediments is planned by the Survey.

4. Lack of Information on Nonradioactive Constituents in Groundwater. There is a general lack of information on the nonradioactive quality of the groundwater at NTS. Groundwater samples have not been analyzed for organics other than PCBs and trihalomethanes, and are analyzed infrequently for nonradioactive inorganics. (Monitoring of water supply wells for volatile organic compounds will be required in 1991 under provisions of the 1986 amendments to the Safe Drinking Water Act.) Unidentified contaminants could potentially be present as a result of decontamination and other operations at the NTS. For example, Area 6 has several water supply wells and several potential sources of contamination. These include a decontamination pond, two steam cleaning effluent ponds, and three sewage lagoons, all of which may be receiving solvents, dilute acids and caustics, and metal-containing liquids. Water from the decontamination pond was sampled in June 1986 and found to contain 130 ppb acetone, 250 ppb chlorobenzene, 45 ppb methylene chloride, and 36 ppb total xylenes. Although the regional water table is quite deep, the potential for groundwater contamination exists from repeated recharge at such wastewater disposal sites.
5. Use of Wells for Waste and Wastewater Disposal. Groundwater contamination may result from the presence of open wells that can be used for waste disposal. The permit status of such wells is addressed in Category II findings in the Surface Water Section 3.3.4.2.2 and the Waste Management Section 4.1.3.2.1. However, the nature of the facility and the waste discharged determine whether environmental contamination occurs, not the presence or absence of a permit. Although groundwater in many on-site areas may already be contaminated from underground nuclear testing, the addition of other waste materials, including wastewater, may increase the migration potential of existing radionuclides, as well as serving as an additional source term for radioactive and nonradioactive contaminants. Additionally, while certain wastes are disposed of into test cavities and chimneys, some wastes may go into wells which were drilled as exploratory holes and may not be otherwise contaminated.

"Injection wells" of various kinds, depths, and uses exist at the NTS. Details are presented in Sections 3.4.2.4 and 3.4.2.6. Some injection wells are shallow holes, possibly abandoned emplacement holes, which are used for wastewater disposal. Discharges of wastewater into these injection wells are creating probable soil contamination and the potential for groundwater contamination. Although the depth of these wells (48-100 feet where known) is well above the regional water table (500-3,000 feet below the surface), the potential for

groundwater contamination is greater than that for discharges directly to the land surface (see Finding 3.2.4.3.2 in the soils section) because infiltration rather than evaporation is a major pathway.

A post-shot (PS1a) reentry hole at U8d has been used for disposal of liquids contaminated with radioactivity, including liquid waste from an experimental farm. Another liquid waste disposal hole, U9ITS-Y30-PS1a, was used for similar wastes (Forry, 1987). No information is available for this second deep hole. However, the U8d-PS1a hole received an estimated annual volume of 2.5×10^4 gallons during 1986. The cumulative volume since June 1984 is 8.0×10^4 gallons. Both cobalt-60 and cesium-137 were present in these wastes. No breakdown between these two nuclides is available, but the average concentration is 1.0×10^4 pCi/l and the average annual discharge is 7.0×10^{-5} Ci. It is not known if other wells, such as Pahute Mesa No. 1, have been used for waste disposal.

6. Wastewater Discharges to Surface Impoundments. Discharges of wastewater to unpermitted sumps, lagoons, and ponds are creating the potential for groundwater contamination. The permit status of such discharges is addressed in a Category II finding in the Surface Water Section 3.3.4.2.3, and the status of such facilities with respect to RCRA regulation is covered in a Category II finding in the Waste Management Section 4.1.3.2.1. Section 3.4.2.6 lists these surface impoundments. The nature of such impoundments and the wastes discharged into them determines their potential for environmental contamination, not their permit status. Although the regional water table is 500-3,000 feet below the surface, infiltration, as well as evaporation, is an important mechanism for water movement from these ponds. Thus, recharge from standing water at these point sources can occur, and such recharge creates the potential for groundwater contamination. Survey-related sampling and analysis is being conducted at several of these potential sources to determine the nature and concentration of possible contaminants.

3.4.4.4 Category IV

1. Absence of Well Purging Requirement in Sampling Procedure. The REECO and EMSL well-sampling procedures do not require that wells be purged before sampling. Therefore, analytical data may not represent concentrations of substances in the aquifer at the time of sampling. The purging of three to five well volumes is standard practice to ensure that actual formation water is being obtained.

4.0 NON-MEDIA-SPECIFIC SURVEY FINDINGS

This section discusses findings and observations pertaining to waste management, toxic and chemical materials, radiation, quality assurance, and inactive waste sites and releases. These discussions do not include a background environmental information section because the areas addressed are not necessarily tied to one medium as was the case with the discussions in Section 3.0. These discussions include an environmental monitoring program section, where appropriate and where information was available. The findings for hazardous, radioactive, mixed, and solid waste management are summarized in a section addressing waste management.

4.1 Waste Management

4.1.1 Background Information

Operations at NTS and the North Las Vegas facilities generate a variety of solid and liquid wastes, including hazardous waste, radioactive waste, mixed radioactive and hazardous waste, and nonradioactive/nonhazardous waste. Radioactive waste includes low-level waste (LLW) and transuranic (TRU) waste. No high-level radioactive waste (HLW) is generated at NTS or the North Las Vegas facilities. In addition, NTS radioactive waste management operations accept packaged radioactive wastes (i.e., LLW and TRU waste) for storage and disposal from other DOE facilities. Brief descriptions of these wastes are as follows:

- Hazardous wastes are those wastes identified as such in 40 CFR 261 (i.e., regulated under the Resource Conservation and Recovery Act [RCRA]). Such wastes are either ignitable, reactive, corrosive, or toxic, or contain materials listed in 40 CFR 261.
- Low-level radioactive waste (LLW) is described in 10 CFR 61 as radioactive waste not classified as high-level radioactive waste, transuranic waste, spent nuclear fuel, or by-product material as defined in Section 11e(2) of the Atomic Energy Act (i.e., uranium or thorium tailings and waste). At NTS, LLW consists of waste that is contaminated with low levels of radioactivity, including transuranic nuclides at concentrations less than 100 nanocuries per gram.
- Mixed (radioactive and hazardous) wastes are co-contaminated with radioactive and hazardous waste materials.

- Transuranic waste is defined in 40 CFR 191 as waste containing more than 100 nanocuries (nCi) of alpha-emitting transuranic isotopes, with half-lives greater than 20 years, per gram, except for high-level radioactive wastes.
- High-level radioactive wastes (HLW) are defined in 10 CFR 60 as (1) irradiated reactor fuel, (2) liquid wastes resulting from the operation of the first cycle solvent extraction system, or equivalent, and the concentrated wastes from subsequent extraction cycles, or equivalent, in a facility for reprocessing irradiated reactor fuel, and (3) solids into which such liquid wastes have been converted.
- Nonradioactive/nonhazardous wastes contain very little or no radioactive contamination, and no chemical contamination as defined under RCRA and the State of Nevada Regulations.

Types and quantities of wastes generated at NTS vary considerably because users of the site and levels of activity vary. Some points of generation also change because activity locations change. In addition, some of the waste is classified (i.e., the waste itself or knowledge of the nature and/or existence of a waste need to remain secure). The generation and management of all wastes and existing or potential environmental problems associated with current waste management operations at both NTS and the North Las Vegas facilities are discussed in this section.

Geologic formations at the western boundary of the NTS are being studied for possible use as a repository for the storage of commercially generated HLW. The formations consist of volcanic rocks (i.e., welded tuff) located at Yucca Mountain. This site and its suitability for the management of HLW is not addressed in this section or anywhere in this report.

The Environmental Survey procedure to identify waste-related environmental problems incorporated four types of activities: (1) inspection of waste-generating operations and waste management facilities; (2) interviews with waste management personnel; (3) review of relevant files and documents; and (4) comparison of on-site observations with site reports and procedures. Emphasis was placed on tracking waste streams that have been identified in various site documents (e.g., Clark, 1987; Frazier, 1987b; Kesler, 1987d; NVO, 1986c; REECO, 1986a; and Smith, 1987). Statutes and DOE Orders used as guidance to identify problems include the following:

- The Resource Conservation and Recovery Act (RCRA) and its amendments (specifically 40 CFR 124, 261, 262, 264, 265, and 270).
- State of Nevada Regulations governing hazardous and solid waste (e.g., Nevada Revised Statutes 459.400 through 459.600 and Nevada Administrative Code 444.8500 through 444.935).
- DOE Order 5820.2 for the management of radioactive wastes.
- DOE Orders 5480.1A and 5480.2 for the management of hazardous wastes.

The State of Nevada Division of Environmental Protection (NDEP) is responsible for regulating hazardous and solid wastes at NTS and the North Las Vegas facilities. NDEP has been granted authorization from USEPA to regulate hazardous waste and has applied to USEPA Region 9 to obtain authorization to regulate the hazardous components of mixed waste under RCRA. Therefore, NTS and the North Las Vegas facilities must submit annual hazardous waste generation reports to the State. NDEP will issue all permits for NTS facilities used to treat, store, and/or dispose of hazardous and mixed wastes. In addition, NTS must submit to the State solid waste management plans for its facilities used to dispose of nonradioactive/nonhazardous solid waste.

As of March 1988, no facility at NTS had a permit to treat, store, or dispose of hazardous or mixed wastes. RCRA Part A permit applications had been submitted to NDEP for certain facilities (i.e., the radioactive, mixed waste management sites in Areas 3 and 5, the Area 6 decontamination pond, and the Building 650 leachfield located in Area 23). These applications were submitted to obtain RCRA interim status for the storage and/or disposal of mixed waste while RCRA Part B permit applications are being prepared by NTS and processed by the State. At the time of the DOE Environmental Survey, NTS was preparing a closure/post-closure plan for the Area 23 hazardous waste landfill that was abandoned in 1982. In addition, NTS had not submitted a solid waste management plan to the State for review and approval. The Area 5 radioactive mixed waste management site was granted interim status in September 1987, and a RCRA Part B permit application for this site was being modified by NTS to reflect current situations in March 1988. All active NTS waste management facilities and sites, as well as the hazardous waste landfill, are discussed in Section 4.1.2.1. Inactive facilities and sites are discussed in Section 4.5.

The North Las Vegas facilities generate less than 1,000 kilograms of hazardous waste per month, accumulate on site no more than 6,000 kilograms in any 180-day period, and do not treat or dispose of hazardous waste on-site. Therefore, the facilities do not require any RCRA permits. Also, because

no nonhazardous wastes are disposed of on-site, the North Las Vegas facilities are not required to submit a solid waste management plan to the State. Waste management at these facilities is discussed in Section 4.1.2.2.

4.1.2 General Description of Pollution Sources/Controls

4.1.2.1 Nevada Test Site

4.1.2.1.1 Hazardous Waste

Miscellaneous hazardous wastes are generated from various locations at NTS. Routine wastes include solvents, corrosives, and expired chemicals that are generated in craft, maintenance and repair shops, and laboratories. PCB-contaminated trash is also generated during the maintenance of transformers containing PCB fluids (refer to Section 4.2.1.3). Wastes are generated on an intermittent or one-time basis at locations where there is intermittent or temporary activity (e.g., at device assembly and test sites). Hazardous wastes that were shipped off-site during 1986 and reported to the State are listed in Table 4-1. More than 8,400 gallons were shipped off-site for reclamation or incineration.

Hazardous wastes generally are collected from the generators and shipped off-site to RCRA-permitted facilities. Off-site shipments are recorded on manifests, which are kept on file by waste management personnel. Commercial waste management firms with RCRA-permitted facilities that were used by NTS during 1986 are listed below (Frazier, 1987b):

Firm	Use
Environmental Waste Enterprises Eloy, Arizona	Reclamation
OSCO Agusa, California	Reclamation
U.S. Pollution Control Grassy, Montana	Incineration

Two wastes categorized as hazardous are treated on-site. The first are explosive ordnance wastes, which are detonated in a subsidence crater in Area 11. Wastes and containers remaining after detonation are burned in the crater. Although sites used for open detonation/burning of these wastes are regulated by RCRA interim status standards (Subpart P of Part 265), NTS has not included this site in a RCRA Part A permit application. Such sites will also require Part B permits. EPA issued

TABLE 4-1

**HAZARDOUS WASTE GENERATION DURING 1986
NEVADA TEST SITE, MERCURY, NEVADA**

Waste	Quantity (gallons)	Disposition
1,1,1 Trichloroethane	220	Recycled Off-site
Trichloroethene	110	Recycled Off-site
Methylene Chloride	35	Recycled Off-site
Acetone	55	Recycled Off-site
Toluene	1,871	11 gallons recycled Off-site 1,860 gallons incinerated Off-site
Xylene & Coal Tar Mixture	4,936	Recycled Off-site
Diethylene Triamine	1,045	Incinerated Off-site
Waste Paint Related Material N.O.S.	86	Recycled Off-site
Corrosive Liquid N.O.S.	3	Recycled Off-site
Flammable Liquid N.O.S.	37	Recycled Off-site
ORM-A N.O.S.	26	Recycled Off-site

Source: Frazier, 1987b.

N.O.S. Not otherwise specified

ORM-A Other Regulated Material, Class A. An ORM-A material is a material which has an anesthetic, irritating, noxious, toxic, or other similar property and which can cause extreme annoyance or discomfort to passengers and crew in the event of leakage during transportation.

permitting standards for such sites under Subpart X of Part 264 on December 10, 1987; the final rule became effective on January 11, 1988 (52 FR 46946). The standards contain performance objectives requiring permit applicants to evaluate the potential environmental impacts of sites and demonstrate that releases will not adversely affect human health or the environment. Permitting requirements for this open burning activity are also discussed in Section 3.1.2.2, Nonradioactive Air Contaminants at the NTS.

The second hazardous waste treated on-site consists of paper wipes used to clean device components during assembly in Area 27 (i.e., the Able and Baker Sites). These wipes contain various RCRA-listed solvents added during the cleaning process. Some wipes could also be considered ignitable, as defined by 40 CFR 261. These contaminated wipes are burned along with other combustibles in an open cage in Area 27. This activity is not included in a RCRA Part A application, and thus, the cage does not possess RCRA interim status to burn the waste (i.e., RCRA regulatory approval). Nor was NTS preparing a Part B permit application for this facility at the time of the Survey. NTS does not possess an air pollution control permit for this burning (refer to Section 3.1.2.2).

The Survey team also determined that several waste streams are not being analyzed for hazardous characteristics or RCRA-listed constituents. Therefore, some wastes could be managed improperly and not reported to the State. Facilities that handle these wastes could be unsuitable or could require upgrading to meet RCRA standards (e.g., installation of liners and leak detection and collection systems) and RCRA permitting; RCRA closure and post-closure plans could also be required. Waste streams that could be hazardous and not previously identified are listed below:

- Steam-cleaning effluents from the Area 6 Machine and Welding Shop (Bldg. 6-623) and the Heavy Duty Repair Shop (Bldg. 6-800), both of which use RCRA-listed solvents, are discharged to separate unpermitted, unlined ponds at Yucca Lake (Figure 4-1). The pond that receives effluent from Building 6-800 also may overflow during storm events; at the time of the Survey, the water level of the pond was near the top of the berm. Sediments in the ponds may also be hazardous. The pond capacities are approximately 36,000 gallons.
- Wastewater from the Area 12 Construction Shops (Bldg. 12-8) and the Motor Pool Equipment Maintenance Shop (Bldg. 12-16), which use RCRA-listed solvents, is discharged to an unpermitted, unlined pond (i.e., the Area 12 industrial wastewater sump). There is evidence that this pond also overflows sometimes via a discharge pipe onto the land (i.e., soil was stained under the pipe opening outside the pond). Sediment in the pond may also be hazardous.

FIGURE 4-1

**AREA 6 WASTE MANAGEMENT FACILITIES
NEVADA TEST SITE - MERCURY, NV**

- Cleaning wastes generated at the Area 2 REEC Co Bit Cutter Rebuild Shop contain RCRA-listed solvents and are discharged down two unpermitted shallow wells (i.e., one is located inside the shop where the cutters are cleaned, and the other is located outside the shop where the rollers are cleaned; both wells are reportedly 48 feet deep with a 20-inch casing below a 52-inch casing).
- Water used to spray-clean trucks, which are used to mix epoxy-based stemming materials, is not collected and ends up on the ground. During this cleaning operation, the water could become contaminated with toluene diisocyanate, which is contained in one of the epoxy components and listed as a hazardous substance (40CFR261). These discharges are unpermitted and occur sporadically wherever there is a stemming operation using epoxy-based material.
- Cutting oils from the Area 6 Machine and Welding Shop (Bldg. 6-623; Figure 4-1) are collected in 55-gallon drums and emptied when the drums become full, on the ground (without a permit) just north of the building. Approximately three to four drums of cutting oils are used and disposed of annually. In addition, smaller quantities of cutting oils, used in Areas 23 and 27, are collected after use in vermiculite absorbent and disposed of in the Area 23 sanitary landfill. Unused oils are aqueous-based, nonhazardous cutting fluids, but could possess RCRA hazardous characteristics after use (e.g., metal concentrations could exceed RCRA toxicity limits).
- Sludges from the Area 23 sewage lagoons are disposed of in the Area 23 Sanitary Landfill (Figure 4-2) without approval from the State. The lagoons receive flows from various shops and the industrial hygiene laboratory (one of two laboratories located in Building 650), which discharge hazardous materials down building sinks (e.g., acids, bases and solvents).
- Contents of the Quonset 800 steam jenny sump located in Area 23 (Figure 4-2) are disposed of in the Area 23 solid waste trenches, also without State approval. This sump receives waters used to steam clean a 500-gallon pesticide application container.

Other waste streams that are not adequately characterized and could be radioactive mixed wastes are discussed in Section 4.1.2.1.3. Unpermitted discharges to land surfaces, discharges to unpermitted injection wells, and discharges to unpermitted sumps, lagoons, or ponds are also

FIGURE 4-2

**AREA 23 ACTIVE WASTE MANAGEMENT SITES
NEVADA TEST SITE - MERCURY, NV**

discussed in Section 3.3.4.2. Potential adverse impacts of these discharges on soils, surface waters, and groundwater are discussed in Sections 3.2.2.3, 3.3.4.2, and 3.4.2.6, respectively.

Hazardous wastes could also be generated during testing at the LGF Spill Test Facility in Frenchman Flat (Area 5). All hazardous wastes (e.g., contaminated soil) generated would be collected, manifested, and shipped off-site for disposal by the testing organization.

Hazardous Material and Waste Holding Area

Before hazardous materials are sent off-site, they are transported to the Area 23 Hazardous Material and Waste Holding Area (Figure 4-2). Each intra-site shipment is recorded on a separate manifest. Waste materials are held in the hazardous material section of the holding area for up to 30 days after arrival while site personnel attempt to identify other users of the materials. If no users are found, the materials are considered to be wastes to be sent off-site and are moved to the hazardous waste section of the holding area during the interim. It is NTS' goal to have all wastes that are consigned for off-site shipment to be removed from the holding area in less than 60 days (Fraser, 1987). However, NTS records show that hazardous wastes have been stored in the holding area longer than the 90 days allowed under RCRA (Bingham, 1987c). If storage is longer than 90 days, the area needs to be permitted as a RCRA storage area.

The holding area is a fenced, unsheltered area approximately 100 feet x 50 feet. It does not have an impervious asphalt or concrete pad, or any spill containment diking. Waste containers are stored on pallets. During a February 1987 RCRA inspection, EPA noted other problems at the holding area in addition to storage exceeding 90 days (Fitzsimmons, 1987a):

- Containers were not protected from direct sunlight to reduce the chance of pressure build-up and subsequent rupture and spillage or explosion.
- Containers of incompatible wastes were inadequately segregated.
- One container was improperly labeled.

At the time of the DOE Environmental Survey, the area was still unshaded, but sand bags had been placed as barriers between different waste types, and containers were properly labeled. No containers were being held in the hazardous waste section of the area.

Hazardous Waste Landfill

Some hazardous wastes generated at NTS in the past were disposed of in the Hazardous Waste Landfill located in Area 23 (Figure 4-2). This landfill was used mostly for disposal of uncontained liquids and was operated over a 13-year period from 1969 to 1982 (Earth Technology Corporation, 1987). Records of disposal indicate that approximately 20,000 gallons of waste were landfilled. Waste materials can be broken down into the following types: 10,000 gallons of corrosives, 5,500 gallons of ignitables, 1,000 gallons of toxics or reactives, and the remaining 3,500 gallons of miscellaneous chemicals categorized as nonhazardous.

The landfill consists of three trenches designated as "A," "B," and "C" (Earth Technology Corporation, 1987). Trenches "B" and "C" are located adjacent to each other and are 338 feet and 216 feet long, respectively. Trench "A" is 55 feet long and located approximately 130 feet east of Trench "B." The trenches were constructed using a backhoe to dig a 3-foot-wide by 4-foot-deep cut into the alluvial soils. Small volumes of liquid wastes were poured into the open portions of the trench and allowed to evaporate and infiltrate until surface materials were dry. In addition, small amounts of solid wastes were placed into these trenches. When dry, trenches were backfilled to grade with the overburden removed during the initial trenching operations.

Because the trenches were unlined and the soils are highly permeable, infiltration and contaminant migration have occurred. Investigations have determined that contaminants have infiltrated down to approximately 20 feet below the trenches in some places (Earth Technology Corporation, 1987).

Because the landfill was operated under RCRA interim status from 1980 to 1982, it is subject to RCRA closure and post-closure requirements. In addition, because wastes were disposed in the landfill after June 26, 1982, it is subject to RCRA groundwater monitoring requirements, which extend to the post-closure period. A closure/post-closure plan was being revised at the time of the DOE Environmental Survey. An earlier version included a closure alternative that involved excavation of wastes and contaminated materials. Because contamination would be removed, no groundwater monitoring or post-closure care would be required. The alternative being developed at the time of the Survey involved capping to drain water away and installation of moisture-sensor devices under the trenches and adjacent to them at various depths to track infiltration and migration.

Underground Storage Tanks

NTS has 82 underground storage tanks (USTs). Between 55 and 59 are subject to RCRA regulation (i.e., were in service during 1974 or later). However, only 49 of the regulated tanks were reported

per RCRA Subtitle I requirements (Frazier, 1986a). Twenty-two of the 82 tanks were permanently out-of-service and 10 were temporarily out-of-service. Nine of the 82 tanks contained waste, and all had been taken out of service before 1974:

- Two tanks for pre-disposal holding located at the E-MAD facility in Area 25.
- Six tanks for effluent from nuclear furnace test runs located at Test Cell C in Area 25.
- One tank for effluent from nuclear furnace test runs located at Test Cell A in Area 25.

These tanks contained radioactive or mixed wastes (REECO, undated). None of the USTs, in or out of service, contained hazardous waste, and six contained used oil. Information on these six tanks is presented below.

NTS UST Identification	Status	Content	Capacity (gallons)	Material	Age (years)	Corrosion Protection
23-750	In Service	Used Oil	2,000	Steel	22	None
23-751-1	In Service	Used Oil	2,000	Steel	22	None
23-751-2	In Service	Used Oil	2,000	Steel	22	None
6-619-4	In Service	Used Oil	2,000	Steel	15	None
12-1216	In Service	Used Oil	1,000	Steel	19	None
25-4838	In Service	Used Oil	550	Steel	22	None

It is unknown whether these six tanks leak. NTS does not have a leak detection program for USTs. Generally, steel USTs that are older than 15 years and have no corrosion protection have a high probability of leaking. However, because of the very dry environment at NTS, the probability for leaking is considerably less than more humid environments. NTS USTs are discussed in greater detail in Section 4.2.1.2.1.

4.1.2.1.2 Radioactive Waste

DOE Order 5480.2 defines radioactive waste as solid or fluid materials of no value containing radioactivity; discarded items such as clothing, containers, equipment, rubble, residues, or soils contaminated with radioactivity, or soils, rubble, equipment, or other items containing induced radioactivity, such that the levels exceed safe limits for unconditional release (DOE, 1984). Numerical limits are not specified in the DOE definition. There are various radioactive wastes at NTS, including wastes currently generated on-site, wastes remaining from discontinued site activities, and wastes received for storage or disposal from other DOE facilities. The wastes consist of source

material, special nuclear material, and by-product material (refer to Table 4-2 for definitions of terms), and include the entire spectrum of fissile and nonfissile materials.

Most of the radioactive waste generated on-site is created by the nuclear testing conducted underground in tunnels and drilled holes. This test debris is intensely radioactive and remains underground where the detonations occur. As of October 1986, there had been 557 announced underground detonations, plus unannounced detonations and nuclear device emplacements that have remained undetonated. The radioactivity associated with these detonations is discussed in Sections 3.2.2.2 and 4.3. Groundwater contamination from underground detonations is discussed in Sections 3.4.2.1 and 3.4.2.2. Other radioactive wastes currently generated on-site include:

- Samples of the radioactive detonation debris (core samples) obtained for radiochemical analysis to determine the yield and performance of the test device.
- Contaminated drilling muds generated during drill-back operations to obtain samples of detonation debris.
- Contaminated muck and debris generated during tunnel reentry and rehabilitation activities.
- Contaminated water discharged from the tunnels.
- Debris, trash, and other miscellaneous solid waste contaminated during drill back, tunnel reentry, and cleanup/rehabilitation activities.
- Contaminated water and sludge generated during decontamination of clothing, instruments, equipment, and facilities.
- Liquid wastes generated by radiochemical laboratory operations.
- Waters pumped from wells used in the radionuclide migration study program.

The management of these eight wastes is discussed in this subsection. Amounts generated are unknown (i.e., records on waste generation are not maintained), and generally the wastes are not analyzed/characterized. Some of the wastes, including tunnel discharges, decontamination wastes, and laboratory wastes, could be mixed wastes (refer to Section 4.1.2.1.3). Potential adverse impacts resulting from the management of these wastes (i.e., soil and groundwater contamination) are

TABLE 4-2

**RADIOACTIVE WASTE DEFINITIONS
NEVADA TEST SITE, MERCURY, NEVADA**

Category	Definition
Source Material	Source Material is defined in paragraph 40.4(h) of 10 CFR Part 40 as (1) uranium or thorium, or any combination thereof, in any physical or chemical form or (2) ores that contain by weight 1/20 of 1 percent (0.05 percent) or more of (a) uranium, (b) thorium, or (c) any combination thereof. Source Material does not include Special Nuclear Material.
Special Nuclear Material	Special Nuclear Material is defined in paragraph 70.4(m) of 10 CFR Part 70 as (1) plutonium, uranium-233, uranium enriched in the isotope 233 or in the isotope 235, and any other material that the Commission pursuant to the provisions of Section 541 of the Atomic Energy Act of 1954, as amended, determines to be Special Nuclear Material but does not include Source Material or (2) any material artificially enriched by any one of the foregoing but does not include Source Material.
By-product Material	By-product material is a waste produced by the extraction or concentration of uranium or thorium from any ore processed primarily for its source material content, including discrete surface waste resulting from uranium solution extraction processes (DOE, 1984). The term excludes fission products and other radioactive material covered in 10 CFR Part 20.3(3).

discussed in Sections 3.2.2.3 and 3.4.2.3 through 3.4.2.7. Active facilities and sites used to manage these wastes are listed by area in Table 4-3 and shown in Figure 4-3. Some of the facilities and sites are for classified wastes. Not all classified waste disposal facilities or sites may have been identified by the Survey team; information on some NTS activities, including associated waste management practices, may have been withheld because of the classified nature of the activities.

Discontinued activities that generated radioactive wastes include atmospheric tests; cratering tests; safety tests; tests on nuclear reactors, engines, and furnaces in Areas 25 and 26; and testing at the Area 15 EPA farm. Wastes from most of these activities were disposed of in radioactive waste dumps, tanks, and leachfields, which are now inactive. These disposal sites are discussed in Section 4.5.2. Other wastes from discontinued activities were transported to waste storage/consolidation sites until they could be decontaminated or buried (refer to Section 4.5.2.4). Wastes from these consolidation sites are now being disposed of at the Area 3 Radioactive Waste Management Site (RWMS), one of two such sites at NTS. Wastes received from other DOE facilities are stored or disposed of at the other RWMS, which is located in Area 5. Both of these sites are also discussed in this subsection. Areas of surface and near-surface contamination resulting from discontinued activities are discussed in Sections 3.2.2.1, 3.2.3.3, and 3.2.3.4. Equipment and facilities contaminated by these activities, including test reactors, test cells, and testing support facilities, are discussed in Section 4.3.2.

Core Samples

Core samples consist of mixed fission and activation products obtained from the solidified detonation debris/melt during post-shot drilling. The samples are classified, and are disposed of in deep, cased holes or returned to the drill holes from which they came. Two holes are active: Hole U3fi in Area 3 and Hole U9u in Area 9. Two other holes in Area 3, J-6 and J-11, also could be used for disposal of classified core samples. Several core holes have been closed (i.e., plugged and secured by welded or locked steel covers). In the past, some of the cores were buried a few feet beneath the surface at the site of the drill-back operation (ERDA, 1977).

Contaminated Drilling Muds

Drilling muds contaminated with radioactivity during drill-back operations are stored in return mud pits located on the ground alongside the drilling rig and are later disposed of in subsidence craters. Crater U2bu, which is located in Area 2, is currently used for disposal of contaminated muds. Craters U3ai-be and U9y were used in the past and could still be used for contaminated muds. Crater U3ai-be is currently used for disposal of excess, uncontaminated muds. The Survey team noticed evidence of recent disposal activity at Crater U9y.

TABLE 4-3

**ACTIVE RADIOACTIVE WASTE MANAGEMENT FACILITIES AND SITES
NEVADA TEST SITE, MERCURY, NEVADA**

Area	Facility/Site
2	<ul style="list-style-type: none"> ● Crater U2bu used for the disposal of contaminated drilling muds(1,2,4,5) since 1980 and decontamination liquid wastes(5); total area is 1.5 acres; average tritium concentrations discharged are 4.0×10^{-6} $\mu\text{Ci/ml}$; the average annual discharge is 1.8×10^{-4} Ci(1).
3	<ul style="list-style-type: none"> ● Hole U3fi used for disposal of classified core samples(2,4,5) and solidified decontamination wastes(5); decontamination wastes are generated from individual tests and therefore are classified; the hole is an unused emplacement hole approximately 1,300 feet deep, cased, and located above the water table; approximately 700 feet of the hole have been filled; the last 60 feet will be filled with concrete to permanently close the hole; the hole has a locked steel cover. ● Hole J-6 used for classified waste disposal(2,3,4); the cumulative volume of wash water from contaminated drilling equipment disposed of during the period June 1984-December 1986 is 6,600 gallons(3). ● Hole J-11 used for classified waste disposal(2,4) (no additional information on the hole was made available to the Survey team). ● Crater U3ai-be could be used for disposal of contaminated drilling muds and decontamination liquid wastes(4,5). ● RWMS (Crater U3ax-bl) used for disposal of bulk radioactive waste(1,2,4,5); because mixed waste is disposed of in the crater, a RCRA Part A permit application was submitted to NDEP (see text for details).
5	<ul style="list-style-type: none"> ● RWMS used for disposal of packaged, classified and unclassified, transuranic, low-level, and mixed wastes as well as storage of transuranic wastes(1,2,4,5); site was granted RCRA interim status in September 1987 (see text for details). ● Seepage/evaporation pond used for water pumped from Well RNM 25 as part of the radionuclide migration study(1,5); the pond area is 1,000 square feet; average tritium concentrations discharged are 1.5×10^{-3} $\mu\text{Ci/ml}$; the average annual discharge is 1.7×10^3 Ci(1).
6	<ul style="list-style-type: none"> ● Seepage/evaporative pond used for liquid wastes, including mixed waste, generated at the decontamination facility (1,2,3,4,5); the pond is constructed on a dry lake bed, covers a 1.0-acre area, and is unlined; the 1986 estimated annual volume discharged to the pond is 3.6 million gallons(3); average tritium concentrations are 1.1×10^{-5} $\mu\text{Ci/ml}$; the average annual discharge is 7.0×10^{-2} Ci(1); a RCRA Part A permit application was submitted to NDEP.
8	<ul style="list-style-type: none"> ● Hole U8d used for disposal of contaminated liquid wastes (1,2,3,4,5); the cumulative volume discharged during the period June 1984-December 1986 is 80,000 gallons(3); average radionuclide concentrations are 1.0×10^{-5} $\mu\text{Ci/ml}$; the average annual discharge is 7.0×10^{-5} Ci(1).

TABLE 4-3
ACTIVE RADIOACTIVE WASTE MANAGEMENT FACILITIES AND SITES
NEVADA TEST SITE, MERCURY, NEVADA
PAGE TWO

Area	Facility/Site
9	<ul style="list-style-type: none"> ● Crater U9y could be used for the disposal of contaminated drilling muds and decontamination liquid wastes⁽⁵⁾. ● Hole U9u used for disposal of classified core samples⁽⁴⁾. ● Hole U9ITS-Y30-PS1a used for disposal of contaminated liquid wastes⁽⁵⁾.
12	<ul style="list-style-type: none"> ● 4 piles for the disposal of contaminated tunnel muck and debris located at the following tunnels: U12e; U12g; U12n; and U12t; (2,4,5) the piles contain low levels of radioactivity. ● 4 series of ponds used to dispose of water discharged from the tunnels and decontamination liquid wastes at the following tunnels: U12e - 4 ponds; U12g - 1 pond; U12n - 5 ponds; and U12t - 6 ponds (1,2,3,4,5) (see text for details).
23	<ul style="list-style-type: none"> ● Leachfield at Building 650 for disposal of liquid mixed wastes from radiochemical laboratory operations with low levels of radioactivity; (2,3,4,5) the cumulative volume discharge during the period June 1984-December 1986 is 62.5 gallons; (3) a RCRA Part A permit application was submitted to NDEP.

(1) NVO, 1986a.

(2) REECa, 1986a.

(3) Clark, 1987.

(4) REECa, Undated.

(5) Interviews with NTS personnel.

FIGURE 4-3

**ACTIVE RADIOACTIVE AND MIXED
WASTE MANAGEMENT SITES
NEVADA TEST SITE - MERCURY, NV**

Contaminated Tunnel Muck and Debris

Muck and debris contaminated with low levels of radioactivity are removed during tunnel reentry and rehabilitation for additional tests. The removed material is accumulated in piles convenient to the point of mining and covered with uncontaminated soils. Some large or bulky debris is also removed and disposed of at the Area 3 RWMS. Highly contaminated waste (≥ 0.3 millirem per hour) derived from tunnel reentry operations is not brought out of the tunnels, but instead is placed in unused drifts and sealed off.

Tunnel Discharge

Groundwater accumulates in the Area 12 tunnels and either drains naturally or is pumped to manmade ponds. The ponds were constructed to allow seepage and evaporation of the tunnel waters. Additional ponds were constructed to contain overflow from existing ponds. The ponds are located downhill from the mine entrances and constructed in series if more than one was needed. Some of the tunnel water comes from the test chambers and has been contaminated with radionuclides. Typical tritium levels in the tunnel ponds are less than $0.001 \mu\text{Ci/ml}$ (ERDA 1977; also refer to Table 4-4). During weapons testing post-shot periods, reentry into a specific tunnel may require use of all the tunnel's wastewater ponds in order to handle the large amount of water accumulated behind the containment structures in the tunnel. At these times, the flow rate and the radioactivity level are normally higher due to the mass of water in the tunnel and the short-lived mixed fission products (primarily iodines) in the water. Following this initial high-flow rate, the rate subsides to that of the groundwater drainage from the tunnel (Clark, 1987). Organics have also been detected in the tunnel discharge, which indicates that the discharge may be a mixed waste (refer to Section 4.1.2.1.3).

At the time of the Survey, the N and T tunnels were active. The E and G tunnels were inactive, and the P tunnel was being developed. The U12n and U12t tunnel ponds were in use, and the U12e ponds were dry. The U12g pond contained stormwater; discharge from the U12g tunnel is disposed of on the land in a contained area (i.e., an area bounded by a 3- to 4-foot-high piece of corrugated metal 6 to 8 feet in diameter).

Contaminated Solid Waste

Contaminated solid waste is generated during various NTS activities, including drill-back operations, tunnel reentry and rehabilitation, and site cleanup and decontamination operations. This waste

TABLE 4-4

**DISCHARGES TO ACTIVE AREA 12 TUNNEL PONDS
NEVADA TEST SITE, MERCURY, NEVADA**

Tunnel Ponds	Estimated Annual Volume 1986 (gallons)(1)	Cumulative Volume Since June 1984 (gallons)(1)	Average Tritium Concentration ($\mu\text{Ci/ml}$)(2)	Average Annual Tritium Discharge (Ci)(2)
E Series (4 ponds)	1.8×10^5	4.5×10^5	--	--
G (1 pond)	dry	5.5×10^5	$5.0 \times 10^{-4}(3)$	$1.0(3)$
N Series (5 ponds)	3.3×10^6	1.5×10^7	$6.8 \times 10^{-4}(4)$	$7.2(4)$
T Series (6 ponds)	8.5×10^6	2.6×10^7	$1.4 \times 10^{-3}(5)$	$2.7(5)$

(1) Source: Clark, 1987.

(2) Source: NVO, 1986a.

(3) Sampled from a steel holding tank containing 400 gallons.

(4) Sampled from 3 ponds with an area of 0.25 acres.

(5) Sampled from 5 ponds with an area of 0.6 acres.

consists of contaminated trash and debris (e.g., rags and construction rubbish), and anything that has become contaminated and that would cost more to decontaminate than to replace (e.g., tools and rubber gloves). Large or bulky unclassified items with low levels of contamination are disposed of at the Area 3 RWMS and covered with uncontaminated soils. Smaller items are packaged and disposed of at the Area 5 RWMS. The type of disposal at the Area 5 RWMS depends on the type of contamination and whether the waste is classified (refer to the RWMS description below).

Decontamination Wastes

Water and solutions used to remove particulate radioactive contamination from various items (e.g., drilling equipment and instruments) become contaminated with radionuclides. Most of these wastes are generated at drill-back and tunnel reentry sites, the Area 12 decontamination area, and the Area 6 decontamination facility. Decontamination operations at drill-back and tunnel reentry sites generally consist of an initial washing/spraying of the contaminated items with water, and thus, the waste is only radioactively contaminated (i.e., no hazardous substances are used for decontamination and thus become part of the waste stream). Often the contaminated waters end up in the site's mud pit or on the ground. Sometimes the area is scraped over with uncontaminated soil to reduce radiation exposure. These wastes are also trucked for disposal at various sites, including tunnel ponds (e.g., U12n and t ponds), contaminated mud disposal craters (e.g., U2bu and possibly U3ai-be and U9y), liquid disposal holes (e.g., U8d, J-6, J-11, and U9ITS-Y30-PS1a), and the Area 6 decontamination facility. Some classified decontamination wastes are solidified and disposed of in core holes (e.g., U3fi and U9u).

The Area 12 decontamination area is used to decontaminate diagnostic equipment. Contaminated wash water is collected in trays that drain to a small aboveground tank. When the tank becomes full, contents are trucked for disposal to hole U8d, located in Area 8, or to the Area 6 decontamination facility.

Items that are not decontaminated on location or in Area 12, or not sufficiently decontaminated by the initial washing, are taken to the Area 6 decontamination facility. At this facility decontamination can be much more rigorous, involving the use of solvents, acids, and/or caustics. Decontamination wastes can therefore become contaminated with both radionuclides and hazardous substances (refer to Section 4.1.2.1.3). Liquid wastes from this facility are collected and piped to the Area 6 decontamination pond via two sumps. The pond is an unlined, seepage/evaporation pond. A RCRA Part A permit application was submitted for this pond in December 1987. The discharge from the facility's laundry, which is used to decontaminate masks, coveralls, gloves, and boots, is also piped to the decontamination pond. Sludges in the sumps are

removed once or twice a year, solidified in drums, and transported to the Area 3 RWMS for disposal. Contaminated solid waste, such as trash, filters, scrap metal, and wooden pallets, are disposed of at the Area 3 or Area 5 RWMS. A dry waste compactor, which compacts 40 cubic feet of dry, low-level waste into 55-gallon metal drums, is located at the loading platform of the laundry facility.

Radiochemical Laboratory Wastes

The radiochemistry laboratory, one of two laboratories located in Area 23, Building 650, generates low-level, liquid, radioactive wastes resulting from the analysis of various air, water, soil, vegetation bioassay, and other samples. The wastes usually contain less than 0.003 $\mu\text{Ci/ml}$ (ERDA, 1977) and at times may contain hazardous substances used in the laboratory (e.g., solvents, acids, and bases; refer to Section 4.1.2.1.3). The wastes are disposed of in designated sinks that are piped to an underground sump and a leachfield. This discharge is unpermitted.

RNM Well Water

Water pumped from Well RNM 25 (located in Area 5) is discharged to a ditch that flows to a seepage/evaporation pond (also located in Area 5). Other such ponds have been used in the past for waters pumped from other wells (e.g., Well UE-2ce and Well UE-7ns; refer to Section 3.4.2.1). The current discharge and the active pond do not possess any regulatory permits. In addition, these discharges are sources of soil contamination (refer to Section 3.2.2.3).

Area 3 RWMS

The radioactive waste management site (RWMS) located in Area 3 consists of an unclassified disposal area and a classified disposal area (Figure 4-4). The classified disposal area consists of an unused, cased emplacement hole, designated as U3fi, that is used for disposal of classified core samples (refer to Table 4-3 for details). The unclassified disposal area includes subsidence craters for disposal of large or bulky, unpackaged items that contain low levels of radioactivity.

Two of the craters (i.e., U3ax and U3bl) have been filled to capacity. These were made into one large crater (designated as U3ax-bl) by removing the earth in between the craters. The crater area was not lined. Materials disposed of in the crater include items collected from the consolidation sites (e.g., tower debris and military vehicles contaminated during atmospheric testing), items contaminated during drill-back and tunnel reentry operations, tunnel debris, and solidified sludges from the Area 6 decontamination facility. Because the Area 3 RWMS is only for unpackaged wastes, solidified decontamination sludges were disposed of in uncovered drums. Materials from the Johnston Atolls,

FIGURE 4-4

AREA 3 RADIOACTIVE WASTE MANAGEMENT SITE
NEVADA TEST SITE - MERCURY, NV

in cargo containers, also were disposed of in the landfill. The Area 3 RWMS does not receive compactible wastes, however, in the past, contaminated soils from the tunnels were disposed of in the crater area. Alternate layers of waste and uncontaminated soil (e.g., the soil removed to make the large crater) were placed in the crater. Wastes were first placed in Crater U3ax in January 1965. In 1985, it was estimated that the two craters contained approximately 3,000,000 cubic feet of solid LLW and that more than 90 percent of the volume consisted of contaminated debris generated during atmospheric testing (NVO, 1986a). Volumes received during the period from October 1982 through September 1986 (REECo, 1986a) are presented below:

Year (FY)	Volume (Cubic Feet)
1982	732,000
1983	1,096,000
1984	346,000
1985	963,000
1986	69,836

Because some mixed wastes (e.g., decontamination wastes, classified detonation wastes, and lead shielding) have been and will continue to be disposed of at the Area 3 RWMS, a RCRA Part A permit application for the site was submitted to the State in December 1987 (refer to Section 4.1.2.1.3). A RCRA Part B permit application also was being modified by NTS in March 1988 to reflect current situations. The RCRA Part A permit application states that the craters receive an estimated 1,700,000 pounds of hazardous lead-bearing wastes (i.e., D008) annually (Smith, 1987). In addition, NTS will submit a RCRA closure plan for Crater U3ax-bl. RCRA permits and a closure plan are required because the hazardous constituents of mixed wastes are regulated under RCRA.

Area 5 RWMS

The Area 5 RWMS consists of shallow burial grounds, waste storage pads, deep disposal boreholes (i.e., greater confinement disposal boreholes) and standby decontamination facilities with the following design capacities:

- Existing trenches and pits -- 10,000 acre-feet.
- Storage pad and boreholes -- 300,000 gallons in containers.
- Standby decontamination evaporation pond -- 100 gallons per day.

The site was first used for the disposal of low-level wastes (LLW) generated at NTS (i.e., in 1961 according to the RCRA Part A permit application; Smith, 1987). Some LLW and transuranic (TRU) wastes generated at the nation's nuclear weapons laboratories and production facilities were occasionally disposed of at the site. Beginning in 1974, wastes containing greater than 10 nCi per gram of transuranics were separated from lower-level wastes so that the transuranics could be retrieved in the future (ERDA, 1977); later that value was changed to 100 nCi. In April 1978, NTS started to routinely receive wastes from other DOE facilities. Today the existing facilities occupy 92 acres (Figure 4-5). Expansion plans include future disposal cells for LLW and mixed waste that will occupy an additional 640 acres (Figure 4-6). A revised RCRA Part A permit application for this site was submitted to NDEP, and the site was granted interim status in September 1987 (refer to Section 4.1.2.1.3). A RCRA Part B permit application was being modified by NTS in March 1988 to reflect current situations.

LLW with low specific activity (LSA) are disposed of in unlined trenches and pits and covered with at least 2 meters of uncontaminated soil. The transuranic concentration of these wastes must be less than 100 nCi per gram. Such wastes generated at NTS include contaminated trash from numerous locations (e.g., device assembly and test sites), wastes from the Area 23 laboratories, and soil decontamination testing wastes from Area 25. LSA LLW from other DOE facilities, including the North Las Vegas facilities, consist of contaminated soils, sediments and sludges, tools, filters, rubber gloves, rags, test tubes, machine cuttings, and anything else that becomes radioactively contaminated and that would cost more to decontaminate than to replace. All wastes are solid and containerized in steel drums, plywood crates, or corrugated paper boxes.

There are 14 burial trenches and pits. Five are for classified LLW; four are closed, and one is active. Nine are for unclassified LLW; seven are closed, one is active, and one is empty. Trenches and pits vary in size; lengths range from 280 to 1,133 feet, widths range from 40 to 346 feet, and depths range from 15 to 30 feet. Walls of recently constructed trenches and pits are sloped back for greater stability of waste packages. The floor is also sloped so that wastes lean back against the wall. In addition, crates and boxes are stacked in a stair-step configuration and interlaced to provide even more stability.

Thirty-five trenches for LLW and 21 trenches for mixed wastes are planned to be added to the RWMS. Each will be 650 feet long, 220 feet wide, and 20-50 feet deep (NVO, 1985a).

FIGURE 4-5

EXISTING FACILITIES AT AREA 5
RADIOACTIVE WASTE MANAGEMENT SITE
NEVADA TEST SITE - MERCURY, NV

FIGURE 4-6

AREA 5 RADIOACTIVE WASTE MANAGEMENT SITE
NEVADA TEST SITE - MERCURY, NV

Wastes stored in greater confinement disposal (GCD) boreholes are wastes that are too hazardous from a radiation standpoint for shallow burial. All GCD wastes require remote handling. Such wastes include

- LLW with high specific activity (i.e., $\geq 1,000$ Ci per drum; e.g., uranium-233).
- Wastes with transuranic nuclides (e.g., plutonium and americium) exceeding 100 nCi per gram.
- Wastes containing volatile radionuclides.
- Radiation source material that, when decayed for 100 years (institutional period), would exist in a concentration greater than 0.1 millicuries (mCi) per gram. For example:
 - Cesium-137 at concentrations greater than 1 mCi per gram.
 - Strontium-90 at concentrations greater than 1 mCi per gram.
 - Cobalt-60 at concentrations greater than 50 Ci per gram.
 - Radium-226 at concentrations greater than 0.1 mCi per gram.

The TRU wastes in GCD are classified wastes generated at the Rocky Flats Plant and the Lawrence Livermore National Laboratory. NTS will not dispose of any more of these wastes in GCD until the containment performance of the boreholes has been fully evaluated. The GCD boreholes must be capable of containing radionuclides for 300 to 500 years. (The maximum half-life of radionuclides in GCD is 30 years [Williams, 1988]).

The GCD boreholes are cased and designed to reduce the risk of inadvertent intrusion (i.e., to minimize or eliminate natural environmental intrusion processes, such as animal burrowing, rainwater percolation, and plant rootings, and to reduce the potential for inadvertent human intrusion). The boreholes are 60 to 120 feet deep. When full, the top several feet of the boreholes are backfilled with desert soil and closed. In addition, waste in GCD is located several hundred feet (approximately 800-900 feet.) above the groundwater table.

There are 13 GCD boreholes, and another is planned. The first was constructed in 1984. Five are for classified wastes; four are closed, and one is active. The planned borehole is also for classified wastes. Eight of the boreholes are for unclassified wastes; five are closed, and three are active. Nine of the boreholes are 120 feet deep, three are 90 feet deep, and one is 60 feet deep. The 120-foot deep boreholes are the newest and are 140 inches in diameter. When they are closed, they are backfilled with 60 feet or more of soil.

Wastes stored on the asphalt pad primarily consist of TRU wastes in galvanized drums that are WIPP-certified. The pad also contains some drums of TRU wastes that are not WIPP-certifiable and some drums of wastes that are not TRU (see following paragraphs for quantities). All drums are stored in cargo containers. WIPP-certified wastes are scheduled to be shipped to the WIPP site in New Mexico in 1990. Options to manage non-certifiable wastes are being evaluated.

The standby decontamination facilities consist of a decontamination pad located in Building 5-6 and a lined decontamination evaporation pond. These facilities were installed to decontaminate items that could become contaminated if a container were to rupture and release radioactive material. The facilities have never been used.

Two buildings are located at the RWMS. A 40 x 60 foot waste processing building was opened in April 1978 with the capacity to repackage containers damaged in shipping and to compact wastes from NTS operations. A second building, opened in 1984, contains office space and a laboratory.

Detailed records are kept of each package of waste, including the contents, quantities and kinds of radioactivity, and exact burial location. Wastes placed in pits and trenches are segregated by generator to enable retrieval if ever necessary. As pits and trenches are filled in, they are carefully defined with concrete markers which are located geographically and recorded by Nevada coordinates. In 1986, it was estimated that approximately 2,000,000 cubic feet of LLW had been buried in the trenches and pits (NVO, 1986a). Volumes of low-level wastes received at the Area 5 RWMS during the period from October 1982 through September 1986 (REEC0, 1986a) are presented below:

Year (FY)	Volume (Cubic Feet)
1982	285,000
1983	307,000
1984	341,000
1985	483,000
1986	549,449

These volumes represent volumes buried and in greater confinement. During the latter half of 1986, however, it was determined that some of the LLWs received from generators in the past contain hazardous constituents and are therefore mixed wastes (refer to Section 4.1.2.1.3). In addition, some TRU wastes were buried in the classified trenches before 1974 (Strickler, 1986).

In May 1986, 1,662 waste drums were being stored on the waste pad (REECO, 1986a). Out of those drums, 1,533 had been assayed and confirmed to be TRU wastes, and 129 had been assayed as not TRU. Out of the 1,533 drums, 229 had been categorized as non-WIPP-certifiable by real-time radiography. There were also 64 steel boxes containing glove boxes; 11 of the boxes were oversized and would require WIPP exemption. The volume and activity of retrievable TRU waste stored on the pad (REECO, 1986a) are shown below:

Fiscal Year	Volume (ft ³)	Activity (Ci)
1974	356	127
1975	1,080	155
1976	785	74
1977	2,197	129
1978	531	130
1979	374	227
1980	1,145	363
1981	576	123
1982	1,109	161
1983	1,635	294
1984	7,705	1,195
1985	3,414	369
TOTAL	20,907	3,347

There are approximately 22,500 cubic feet of TRU and HSA-LLW wastes in GCD boreholes (Kendall, 1988). Approximately 5,600 cubic feet consists of classified TRU wastes, which are contained in six boreholes and possess an estimated two million curies; the total estimated activity at the RWMS is five million curies.

NTS conducts some site-specific environmental monitoring associated with the RWMS operations. There are 11 air monitoring stations at the RWMS used to collect particulate and gas samples, which are analyzed weekly for radioactivity. There are also 18 thermoluminescent detectors or dosimeters (TLD) stations at the RWMS to monitor radiation exposure levels. In addition, soil, vegetation, and standing water samples are collected and analyzed whenever there is rain (NVO, 1985b). NTS, however, does not conduct any groundwater monitoring at the RWMS. Site management contends that surface runoff is generally scant (i.e., the annual average precipitation is seven inches) and seldom penetrates more than the first few inches of the vegetated desert alluvial soil. The

unsaturated zone extends approximately 800-1,000 feet below the surface. Therefore, it is unlikely that any hazardous constituents, which may be present in the landfill from past disposal of mixed wastes, will contaminate groundwater (refer to Section 3.4.2.7). Based on the site setting, NTS is seeking a waiver of RCRA landfill requirements for a liner system, a leachate collection/detection system, and a groundwater monitoring system (refer to Section 4.1.2.1.3). In addition, NTS is conducting a performance assessment to determine if the landfill can contain TRU wastes.

The existing facilities include a stormwater run-on control system that consists of a 6-foot-high, 48-foot-wide dike (refer to Figure 4-5). The dike is designed to prevent run-on from the peak discharge of a 100-year, 24-hour storm occurring in the vicinity of the site. The dike was constructed of on-site alluvial soil in 1978 and has never been breached by run-on, including the run-on from a 100-year storm that occurred in 1984.

The Area 5 RWMS is managed by REECo Environmental Services Division. The site is operated according to the Operational Radioactive Defense Waste Management Plan for the Nevada Test Site (NVO-185, Revision 4; NVO, 1985c). This document establishes procedures and criteria for the shipping, receiving, processing, disposal, and storage of radioactive defense waste. All wastes shipped to the RWMS for storage or disposal must be solid, nonhazardous defense waste and must be packaged. The following wastes are not accepted: bulk radioactive waste, liquid radioactive waste, mixed radioactive waste, nondefense radioactive waste, and nonradioactive waste. The RWMS received mixed wastes in the past but was no longer receiving mixed wastes at the time of the DOE Survey. Waste acceptance criteria are summarized in Table 4-5. Where practical, all materials should be compacted, oxidized, dehydrated, incinerated, or otherwise concentrated for the maximum possible volume reduction.

The DOE/NV Manager may approve exceptions to the criteria (NVO, 1985c). A safety analysis is required for any exceptions that will increase the fissile loading, or significantly affect other compliance criteria. All exceptions must be approved by the DOE/NV Manager prior to shipment. Radioactive wastes containing hazardous materials (i.e., mixed radioactive waste) as defined by RCRA must be identified as an exception. Acceptance and nonacceptance are considered on a case-by-case basis by the DOE/NV Manager.

All generators must be approved before they can ship their wastes to the RWMS. Approval involves annual inspections of the generator's packaging process and review of their packaging and shipping quality assurance program. At the time of the Survey, 18 generators of LLW were authorized by NTS to ship wastes to the RWMS. Generators must also provide detailed records for each waste package.

TABLE 4-5

SUMMARY OF DEFENSE WASTE ACCEPTANCE CRITERIA
NEVADA TEST SITE, MERCURY, NEVADA

1. Materials packaged as low-level radioactive waste shall not include:
 - Pyrophoric or explosive materials in reactive form
 - Compressed gases (e.g., unpunctured aerosol cans)
 - Strong oxidants (e.g., perchlorates and nitrates)
 - Oils, greases, or solvents absorbed on cellulosic material
 - Corrosive chemicals that may react with the container (e.g., acids)
 - Free liquids
 - Hazardous materials (see 40 CFR 261)
 - Other reactive materials that could cause fire, explosion, or pressure buildup
2. All shipments of radioactive waste across state or interstate highways shall comply with 49 CFR 173 and DOE 5480.1A, Chapter XI. Each radioactive waste container shall be marked as indicated in 49 CFR 172, and possess a certification label.
3. Radiation dose rates of radioactive waste packages submitted for disposal at the NTS shall not exceed:
 - 200 millirem per hour at contact with shipping container
 - 10 millirem per hour at 3 feet (1 meter) from shipping container

The generator shall certify that ingrowth of daughter products will not cause radiation levels to exceed the above limits during handling and shipping. A currently calibrated radiation survey instrument shall be used to verify radiation levels defined above.
4. Low-level waste shall be segregated for shallow land burial or greater confinement disposal. The following wastes must go into greater confinement:
 - Wastes with transuranic nuclide concentrations equal to or greater than 100 nCi per gram, unless they are WIPP-certified (these wastes can be stored on the asphalt pads)
 - Wastes with volatile radionuclides

TABLE 4-5
SUMMARY OF DEFENSE WASTE ACCEPTANCE CRITERIA
NEVADA TEST SITE, MERCURY, NEVADA
PAGE TWO

- Radiation source material that, when decayed for 100 years (institutional period), would exist in a concentration greater than 0.1 mCi per gram. For example
 - Cesium-137 at concentrations greater than 1 mCi per gram.
 - Strontium-90 at concentrations greater than 1 mCi per gram.
 - Cobalt-60 at concentrations greater than 50 Ci per gram.
 - Radium-226 at concentrations greater than 0.1 mCi per gram. (Therefore, most radium sources are unsuitable for shallow land disposal.)
- 5. TRU waste received for interim storage shall be certified for compliance with the Waste Isolation Pilot Plant waste acceptance criteria. These wastes must meet criterion 1. Packages of TRU waste must be retrievable in an intact, contamination-free condition for 20 years.
- 6. Radioactive waste shipments shall be accompanied by records that include the identities, quantities, and concentrations of the radionuclides in the waste.

Source: DOE Environmental Survey Team, 1987. Adapted from NVO, 1985c.

4.1.2.1.3 Mixed Waste

NTS generates mixed waste at various locations on-site and has received mixed waste from other DOE facilities for disposal at the Area 5 RWMS. The characteristics and volumes of mixed waste generated on-site and received from other facilities were unknown by site personnel at the time of the DOE Environmental Survey. The site had recently become aware that it may be generating mixed waste, and no formal mixed waste identification or recordkeeping system had been developed for NTS operations. In addition, the RWMS did not have waste sampling and testing capabilities and had been relying only on generator certification (Farber, 1986). However, most of the approved generators who shipped wastes to NTS had made their determination as to the absence of hazardous waste by application of administrative controls without analytical testing (i.e., generators had made determinations based on knowledge as to the hazardous characteristic of the waste in light of the materials or the processes used). Therefore, generators had controlled for RCRA-characteristic wastes (40 CFR 261, Subpart C) but not for RCRA-listed wastes (Subpart D). Some generators also had not controlled for wastes containing lead and chromium (i.e., specific wastes regulated under Subpart C; D008 and D007, respectively). This means that NTS until recently had managed mixed waste as LLW and had not been in compliance with RCRA or DOE Order 5480.2, Hazardous and Radioactive Mixed Waste Management. The hazardous constituents of mixed waste must be managed in accordance with RCRA regulations. Potential adverse impacts resulting from the management of mixed wastes (i.e., soil and groundwater contamination) are discussed in Sections 3.2.2.3, 3.4.2.3, and 3.4.2.5 through 3.4.2.7.

Many DOE generators have potentially sent mixed wastes to the Area 5 RWMS. Generators that have sent the largest waste volumes for disposal or storage as radioactive waste include the Rocky Flats Plant, Colorado, the Feed Materials Production Center, Ohio, the Mound Laboratory, Ohio, and the Lawrence Livermore National Laboratory, California. It became known that the Rocky Flats Plant had been sending mixed wastes to NTS in September 1986. NTS estimates that approximately 50 percent of the total waste buried in the Area 5 RWMS trenches and pits was received from the Rocky Flats Plant (Strickler, 1986). This waste primarily consists of process wastewater treatment sludge (nitrate salts called salt crete) and sludge from a solar evaporation pond (pond crete), both of which are solidified before being sent to NTS. Concentrations of RCRA-listed substances found in these wastes are shown below (REECo, 1986a):

- Salt Crete

Methylene Chloride	20 ppb
Acetone	380 ppb
2-Butanone	70 ppb

Benzene	26 ppb
Toluene	26 ppb

- Pond Crete

Methylene Chloride	35 ppb
Acetone	180 ppb
Tetrachloroethylene	160 ppb

At the time of the Survey, NTS was storing the final shipment of wastes sent by the Rocky Flats Plant separately outside of the operating LLW burial pit. Additionally, NTS was holding and segregating in the burial pit all wastes that it was currently receiving from generators and was not covering the wastes with soil pending further discussion between NTS and generators regarding adequacy of their waste characterization.

Wastes that are generated on-site and that are known or suspected to be mixed waste include effluent and sludge from the Area 6 decontamination facility, discharges from the Area 12 test tunnels, liquid wastes from the Area 23 radiochemistry laboratory, core samples, and solidified and unsolidified decontamination wastes disposed of in emplacement or drill-back holes. RCRA Part A permit applications have been submitted to the State for the Area 5 and Area 3 RWMS, the Area 6 decontamination pond, and the Building 650 leachfield that receives discharges from the Area 23 radiochemistry laboratory. In September 1987 the state granted interim status to the Area 5 RWMS. The wastes and the facilities used to handle them are discussed below (also refer to Figure 4.1-C for facility locations). Additional details are presented in Section 4.1.2.1.2.

Effluents from the Area 6 decontamination facility are discharged via two sumps to a 1.0-acre seepage/evaporation pond. The volume discharged to the pond during 1986 was estimated to be 3.6 million gallons (Clark, 1987). In June of 1986, NTS collected and analyzed water from the decontamination pond for radioactivity and organics (Bicker, 1986). Levels of organic contamination found are presented below:

Contaminant	Concentration (ppb)
Acetone	130
Chlorobenzene	250
Methylene chloride	45
Xylenes (total)	36

These and other chemicals have the potential to accumulate in the soil under the pond water. If the soils/sediments become contaminated, the pond could be considered by regulatory agencies to be a mixed-waste storage unit and subject to RCRA regulations (i.e., would require a double liner system, a leachate detection and collection system, and a groundwater monitoring network, or appropriate waivers; otherwise the pond would have to be closed pursuant to RCRA standards by November 1988). Analysis of pond sediment had not been conducted prior to the DOE Environmental Survey.

Sediments that accumulate in the two sumps at the Area 6 decontamination facility are solidified in drums and taken to the Area 3 RWMS for burial as low-level, radioactive waste approximately twice a year. If the sediments are hazardous as well as radioactive (i.e., mixed waste), the sumps would also have to be managed as hazardous waste storage units because they hold sediment for more than 90 days. At the time of the Survey, no data on the chemical constituents of the sediments were available that would indicate if the sediments have hazardous characteristics or contain RCRA-listed materials. At the time, it was also NTS policy not to bury any mixed waste on-site.

Because some mixed wastes (e.g., decontamination wastes and lead-bearing wastes) have been and will continue to be disposed of at the Area 3 RWMS, NTS submitted a RCRA Part A permit application for the site to the State in December 1987. According to the application, it is estimated that the Area 3 RWMS receives 1,700,000 pounds of hazardous lead-bearing waste annually. NTS was also modifying a RCRA Part B permit application for the site in March 1988 to reflect current situations. However, as of March 1988, the site had not yet been granted interim status. In addition, NTS will submit a RCRA closure plan for Crater U3ax-bl, which is being closed (refer to Section 4.1.2.1.2). Furthermore, the Area 3 RWMS does not contain liners, a leachate detection and collection system, or a groundwater monitoring network. If NTS continues to operate the site without these controls, waivers will have to be obtained.

On June 12, 1986, water samples were collected from the effluent lines at E, N, and T tunnels and the first two holding ponds at N and T tunnels (Bicker, 1986). Analysis detected both radioactivity and low concentrations of methylene chloride in the effluent water from T-tunnel and in the water from the two ponds sampled at T-tunnel. Concentrations of methylene chloride found are presented below:

Sample Location	Concentration (ppb)
T-Tunnel Pond 1	9,300
T-Tunnel Pond 2	1,800
T-Tunnel Effluent	3,450

No other organics were detected in these waters, and no hazardous contaminants were found in the other tunnel effluents or pond waters sampled. However, the sediments in all the ponds could be contaminated, and if so, these ponds would also be subject to RCRA regulations. No chemical data on pond sediments were available at the time of the Survey. In addition, the land area used for the disposal of the G-tunnel discharge also could be contaminated.

Some of the liquid waste from the Area 23/Building 650 radiochemistry laboratory is probably mixed waste. Based on laboratory activities, the waste contains some level of radioactivity and some amount of organic solvents, acids, and caustics. No chemical data were available on the effluent characteristics or constituents. Laboratory procedures dictate that, if radioactivity is detected in the waste, it is to be solidified in beakers, drummed, and shipped to the Area 5 RWMS for disposal in LLW trenches or pits. If radioactivity is not detected, the waste is disposed of in sinks that drain to the building's leachfield. It is estimated that 25 gallons of this waste were discharged to the leachfield during 1986 (Clark, 1987) and that 1,730 cubic feet of the solidified waste were shipped to the Area 5 RWMS during 1986 (from the NTS waste management data base system). NTS possesses no permit under the Clean Water Act or RCRA for this discharge to the leachfield. In addition, until late 1986, the Area 5 RWMS was managing the waste as LLW. At the time of the Survey, NTS policy was to not bury any mixed waste at the RWMSs.

Core samples and solidified and unsolidified decontamination wastes disposed of in emplacement and drill-back holes may be mixed wastes according to site personnel. The wastes are definitely radioactive (refer to Section 4.1.2.1.2), but no chemical analyses had been conducted to determine the chemical properties and constituents of the wastes. The wastes could contain metals, such as lead, and could leach enough during EPA extraction procedure testing that the wastes would be considered toxic per 40 CFR 261, Subpart C. The lead in the core samples, however, could be sealed by oxides and would not be mobile in the area soils (i.e., water is not sufficiently present in the soils to transport the lead). Holes that could receive these wastes include U3fi, J-6, J-11, U8d, U9y, and U9ITS-Y30-PS1a. None of these holes are permitted under RCRA, and only hole U3fi has been included in a RCRA Part A permit application.

The Area 5 RWMS has received both radioactive and mixed wastes for storage and disposal from on-site and other DOE facilities. The site consists of trenches and pits for LLW with low specific activity, GCD boreholes for classified TRU and LLW with high specific activity, and uncertifiable TRU wastes, and a TRU waste storage area. There are plans to construct an additional 35 trenches for LLW disposal and 21 trenches for mixed waste. RCRA Part A and Part B permit applications have been submitted to the State, and the Part B is being modified to reflect current situations. On

September 17, 1987, the State granted the RWMS interim status as a commercial, mixed-waste storage and disposal facility (Fitzsimmons, 1987b). The State also authorized DOE to proceed with storage and disposal of mixed waste without liners and groundwater monitoring. However, an alternative to groundwater monitoring and liners (e.g., monitoring soil moisture) needs to be developed before the State RCRA permit can be issued. No closure/post-closure plan has been prepared for the RWMS.

At the time of the Environmental Survey, the RWMS was not burying any mixed waste. However, until September 1986, mixed waste had been received and managed as LLW or TRU waste. Therefore, the trenches, pits, boreholes, and storage area probably will contain some amount of mixed waste. The volumes are unknown because most of the generators did not analyze their wastes for chemical constituents (i.e., RCRA-listed substances). NTS estimates that approximately half of the waste in the pits and trenches (i.e., 700,000-800,000 cubic feet) was shipped from the Rocky Flats Plant during the period from October 1980 to September 1986 (Strickler, 1986). Most of this waste is solidified nitrate salts (salt crete) and sludge from a solar evaporation pond (pond crete). Shipments of salt crete and pond crete will be authorized by NTS as soon as the Rocky Flats Plant corrects waste analysis deficiencies (Fitzsimmons, 1988). Mixed wastes will not be received from other DOE generators for disposal until the environmental assessment for the RWMS is completed (scheduled for May 30, 1988). Table 4-6 presents an estimated quantity of mixed waste to be received annually at the Area 5 RWMS (from the RCRA Part A permit application for the site; Smith, 1987).

4.1.2.1.4. Nonhazardous Wastes

NTS users generate various nonhazardous wastes throughout the site. These wastes include trash, garbage, construction rubble and debris, machining metal chips, machining cutting oils, and excess and spoiled drilling muds. NTS has various active facilities/sites to handle nonhazardous waste (Figure 4-7). These are

- Three sanitary landfills, located in Areas 6, 10, and 23.
- Two construction landfills, located in Areas 3 and 19.
- Several solid waste trenches, located in Areas 6, 12, and 23.
- At least two craters located in Area 3 that are used for the disposal of excess and spoiled drilling muds (U3ag, which is near the Area 3 mud plant, and U3ai-be).

TABLE 4-6

**ESTIMATED ANNUAL QUANTITY OF MIXED WASTE
TO BE RECEIVED AT THE AREA 5 RWMS
NEVADA TEST SITE, MERCURY, NEVADA**

Waste	Quantity (pounds)	Management
Waste Containing Organic Solvents	265,760	Disposal in trenches
Wastewater Treatment Sludges from Electroplating Operations	748,000	Disposal in trenches
Chromium-Bearing Wastes	17,600	Disposal in trenches
Waste Containing Lead, Silver, and Beryllium Dust	56,500	Disposal in trenches
Waste Containing Organic Solvents and Beryllium Dust	75	Disposal in trenches
Waste Containing Beryllium Dust	1,880	Disposal in trenches
Waste Containing Acetone, Benzene, Dichloromethane, 2-Butanone, and Methylbenzene	29,940	Disposal in trenches
Waste Containing Acetone, Bis(2-ethylhexyl) phthalate, Dichloromethane, and 1,2,2,2-Tetrachloroethane	155,580	Disposal in trenches
Lead-Bearing Waste	700	Disposal in trenches
Silver-Bearing Waste	2,760	Disposal in trenches
Waste Containing Barium	53,250	Disposal in trenches
Waste Containing Benzene and Benzo(a)pyrene	33	Disposal in trenches
Reactive Waste	1,500	Disposal in trenches
Arsenic Waste	105	Disposal in trenches
Waste Containing Organic Solvents	75	Surface treatment impoundment (i.e., decontamination sump)
Waste Containing Organic Solvents	2,200	Storage in containers

Source: DOE Environmental Survey Team, 1987. Adapted from Smith, 1987.

FIGURE 4-7

ACTIVE NONHAZARDOUS / NONRADIOACTIVE
WASTE MANAGEMENT SITES
NEVADA TEST SITE - MERCURY, NV

The sanitary landfills are used to bury most nonhazardous waste (putrescible and nonputrescible). In addition to some of the wastes listed above, the Area 23 landfill receives chlorinated sludges from Area 23 wastewater lagoons and used cutting oils from Areas 23 and 27, the Area 6 landfill receives used transformer oils (containing <50 ppm PCBs) from the Area 6 Line Yard, and the Area 3 landfill receives sediment from the Well 3 Yard truck-wash-bay sump. The solid waste trenches are used for the disposal of chemical toilet and septic tank wastes, sump wastewaters, aerosol cans, and animal carcasses. The construction landfills are to be used only for disposal of nonputrescible wastes. No records are kept to track waste types and volumes disposed of at any of the landfills, trenches, or craters.

Some nonhazardous wastes are not disposed of in landfills, trenches, or craters. For example, some paper and rags are burned in an open cage in Area 27, and spent machining cutting oils are poured onto the ground (refer to Section 4.1.2.1.1). Uncontaminated waste oils, including vehicle transmission and crankcase oils, also are sent off-site for commercial recycling.

In addition, there is an uncontaminated muck pile at the P-tunnel in Area 12. At the time of the DOE Environmental Survey, the P-tunnel was being developed and no tests had been conducted in the tunnel. The muck pile, therefore, only contained rock and earthen material tunneled out.

In Nevada, management of nonhazardous solid waste is regulated by the Division of Environmental Protection. Permits to operate facilities handling nonhazardous waste are not required; however, owners/operators must submit solid waste management plans to the State for such facilities. At the time of the DOE Environmental Survey, NTS did not possess such plans, and therefore, NTS solid waste management operations were not state-approved.

The DOE Environmental Survey team found few controls in place to assure that only nonradioactive/nonhazardous wastes were being disposed of at these disposal sites. None of the facilities are fenced or have around-the-clock access control. The disposal of wastes in the sanitary landfills is controlled during the day shift by the operators. In addition, the operators would be able to detect nighttime waste disposal the following day if they were to see uncovered waste, because all wastes are supposedly covered daily. However, there are no operators at the solid waste trenches, and wastes are not covered routinely. Operators at the Area 6 and Area 23 landfills could perhaps observe unapproved disposal into trenches in those areas because the trenches are located near the landfills. The Area 12 trenches, however, are at a more remote location, and nobody works in the area to control disposal. The construction landfills are operated by construction personnel and are only monitored by industrial hygiene personnel every two weeks. No reports of any unapproved disposals in landfills or trenches were found by the DOE Survey team, and only minor occurrences

were recalled by NTS personnel. There is less control at the mud disposal craters. Small quantities of hazardous waste (e.g., mud additive containing chromium) reportedly could have been disposed of in the Area 3 mud plant crater in the past, and radioactively contaminated drilling muds could still be disposed of in Craters U3ai-be and U9y.

Furthermore, some wastes are disposed of in landfills and trenches that have never been analyzed/characterized. Sewage sludge in the Area 23 sewage lagoons could be hazardous because some hazardous materials, such as organic solvents, acids, and caustics, are poured down sink drains in various shops and the industrial hygiene laboratory. The sludge could also have high enough levels of leachable metals to be considered RCRA-toxic (40 CFR 261). This sludge is disposed of in the Area 23 landfill. In addition, some cutting oils, which could be toxic after use, are disposed of in the Area 23 landfill. Furthermore, sump wastewaters disposed of in solid waste trenches could be hazardous at times. For example, the Quonset 800 steam jenny sump located in Area 23 receives water from steam cleaning of a 500-gallon pesticide application container; the sump contents are collected in a vacuum truck and disposed of in the Area 23 solid waste trenches. Also, wastes from chemical toilets, which are disposed of in solid waste trenches, may contain formaldehyde, which is a RCRA-listed waste (U122; 40 CFR 261).

4.1.2.2 North Las Vegas Facilities

4.1.2.2.1 Hazardous Waste

The EG&G operations at the four North Las Vegas facilities generate a variety of hazardous wastes. These wastes primarily consist of outdated or spent hazardous substances (e.g., spent plating solutions, cutting fluids contaminated with solvents, and outdated laboratory chemicals); they are not waste streams produced in an industrial process. Most of the wastes are generated at the ATLAS facility and the B Complex located on Losee Street. Very small quantities are also generated at the facilities located on Escondido Street and Sunset Street. The combined quantity of hazardous waste generated by these four facilities, however, is still small, and none of the waste is treated or disposed of on-site. Less than 1,000 kilograms per month is generated, which makes EG&G subject to regulations for small quantity generators. In addition, EG&G does not accumulate more than 6,000 kilograms of hazardous waste in any 180-day period, thereby exempting the facilities from RCRA permit requirements. All hazardous waste is shipped off-site to be disposed of or reclaimed/recycled commercially. On February 13, 1986, a hazardous waste investigation was conducted by the NDEP, and no hazardous waste management problems were noted (Coulson, 1986).

Quantities of hazardous wastes generated during 1986 were reported to the State per RCRA Section 2002 in EG&G's Hazardous Waste Generation Report for 1986 and are shown in Table 4-7. All of the wastes, except some copper-plating solutions, were sent to Casmalia Resources in Casmalia, California. The copper-plating solutions were sent to Southern California Chemical in Santa Fe Springs, California, for reclamation of copper salts. Out of the 18,137 kilograms of hazardous waste generated, 18.3 percent was sent off-site to be reclaimed/recycled (Maddox, 1987). Other wastes to be reclaimed/recycled include 1,1,1-trichloroethane, waste oils, and solder slag. Plating rinsewaters, discharge from the silver recovery unit, and small quantities of solvents, acids, and caustics are discharged to the sanitary sewer. These discharges are subject to Clean Water Act regulations (i.e., regulated under the facilities' permit(s) to discharge to the city sewer system; refer to Section 3.3.2.5), unless solvent concentrations exceed certain concentrations. If solvent concentrations exceed limits stated in 40 CFR 261.3, the discharges are regulated under RCRA.

The only PCB waste generated on-site consists of old, nonfunctioning, fluorescent light ballasts, containing small amounts of PCB fluids. These ballasts, as well as non-labeled ballasts that are assumed to contain PCB fluids to be conservative, are collected in the hazardous waste holding area until enough of a volume accumulates to warrant shipment off-site. Arrangements have been made to ship the waste to an ENSCO incinerator in Arkansas for destruction. At the time of the Environmental Survey, less than 100 ballasts were in storage awaiting shipment off-site.

Hazardous wastes to be shipped off-site are generally put into drums, collected by shipping personnel, and temporarily stored in the hazardous waste holding area, which is located behind Building B-1. Sometimes the generators take their waste to this area. The area is a covered concrete pad approximately 40 feet by 20 feet, and includes three diked areas for flammables, acids, and bases. At the time of the Survey, the pad was filled with drums (i.e., at its design capacity), and four waste drums were stored off the pad. Two of the drums contained solvent-contaminated cutting fluids, one contained waste oil, and the fourth contained a used organic solvent. In addition, labels on two of the drums on the pad did not include accumulation start dates pursuant to 40 CFR 262.34.

Hazardous wastes are not stored at the Escondido or Sunset facilities. They are trucked, usually in small containers (≤ 30 gallons), to the hazardous waste pad at the B-Complex. This shipping is not in compliance with RCRA regulations for three reasons:

1. Hazardous wastes cannot be sent to the B-Complex because it is not a RCRA-designated facility (i.e., it is not permitted for the storage of RCRA wastes; refer to 40 CFR 260.10).

TABLE 4-7

**HAZARDOUS WASTE GENERATED DURING 1986
NORTH LAS VEGAS, NEVADA, FACILITIES**

Waste Types	Amount Shipped Off-Site (lbs)
Corrosive wastes from metal etching, stripping, plating, deoxidizing, chromating, cleaning, and electropolishing operations	24,874
Corrosive laboratory and photographic chemicals (outdated and excess)	1,933
Corrosive developer from blueprint copier (i.e., ammonium hydroxide)	600
Battery acid (corrosive)	366
Ignitable laser dye solutions (containing methanol, dichloroethane, propylene carbonate, benzyl alcohol, and ethylene glycol), empty containers, and contaminated gloves and towels	1,625
Ignitable lubricating and cutting fluids (machine shop)	450
Ignitable cutting fluids and paint thinners	2,600
Ignitable photographic developers and chemicals (spent)	1,350
Ignitable, used paint rollers and outdated paints	1,075
Ignitable, empty plastic containers	860
Ignitable, copper etching solution (i.e., sodium persulfate)	300
Methanol and xylene (ignitable)	100
Vacuum pump oil contaminated with mercury (EP toxic)	600
Empty cans containing residue of spent 1,1,1-trichloroethane (toxic)	450
Machine cutting fluids contaminated with 1,1,1-trichloroethane (toxic)	2,700
Wire stripper containing methylene chloride (toxic)	25

Source: DOE Environmental Survey team, 1987. Adapted from Kesler, 1987d.

2. Hazardous wastes can be shipped only by RCRA-approved hazardous waste transporters that possess a RCRA identification number (40 CFR 263.11); at the time of the Survey, EG&G was not registered as a hazardous waste transporter.

3. Shipments of hazardous wastes must be manifested; no manifests tracking the shipment of hazardous wastes from the Escondido or Sunset facilities to the B-Complex were on file.

According to the facilities' standard operating procedures, all wastes are supposed to be inspected by shipping personnel before they are shipped off-site. Shipping personnel generally determine if the waste is hazardous or nonhazardous, and tell the generator which container type to use. Shipping personnel also complete shipping request forms and appropriate manifests. Only the facilities' environmental specialist is authorized to mix compatible wastes. He is also supposed to inspect the waste pad weekly to ensure that wastes are properly labeled and segregated and that drums are not leaking.

There is one underground storage tank at the North Las Vegas facilities (i.e., the A/B Complex). It is a 1,000-gallon steel tank that is empty and has never been used. The presence of this tank was reported to the State (Frazier, 1986a).

4.1.2.2.2 Radioactive Waste

The North Las Vegas facilities generate very little radioactive waste. The waste consists of encapsulated radiation sources that have only low levels of radioactivity. All of this waste is shipped to NTS and disposed of in the LLW trenches or pits at the Area 5 RWMS. The NTS radioactive waste data base indicates that the following volumes were disposed of over the last 3 years:

Year	Volume (Cubic Meters)
1984	0.453
1985	2.54
1986	0.637

4.1.2.2.3 Mixed Waste

No mixed radioactive/hazardous waste is generated at the North Las Vegas facilities.

4.1.2.2.4 Nonhazardous Waste

EG&G operations at the North Las Vegas facilities generate a variety of industrial nonhazardous waste, including trash, rags, machining metal chips, and depressurized aerosol cans. This waste is collected in dumpsters situated in various locations and taken to a landfill by a commercial waste hauler. Asbestos waste is infrequently generated and is segregated in plastic bags before it is hauled away and disposed of as industrial waste. A beryllium-copper-alloy machining waste, which contains 2 percent or less of beryllium, is also segregated. No wastes are disposed of on-site, and therefore, EG&G is not required to prepare and submit a solid waste management plan to the State.

4.1.3 Findings and Observations

4.1.3.1 Category I

None.

4.1.3.2 Category II

1. Potentially Hazardous or Mixed Wastes Discharged to Unpermitted Facilities. Several wastes generated at NTS could be hazardous or mixed wastes and are discharged to unpermitted facilities. NTS does not have an adequate waste characterization program in place to identify all hazardous and mixed wastes. Wastes generally have not been analyzed for RCRA characteristics or RCRA-listed constituents (refer to 40 CFR 261) but have been identified as hazardous based on knowledge of chemicals used. Therefore, wastes that have been identified as hazardous consisted of and have been limited to outdated or spent chemical products (e.g., solvents, corrosives, and laboratory chemicals). Wastes not thus identified as hazardous have been identified as either radioactive or nonradioactive/nonhazardous based on the level of radioactivity. This means that several wastes could be mismanaged, which could potentially result in the release of hazardous constituents into the environment. For example, facilities that handle the wastes could be underdesigned and unable to detect and/or contain hazardous constituents. Specifically, some surface impoundments receiving potentially hazardous or mixed-waste discharges could require upgrading to meet RCRA standards (e.g., installation of liner and leak detection and collection systems) and RCRA permitting; RCRA closure and post-closure plans could also be required. Surface impoundments containing hazardous wastes have to be upgraded or closed by November 1988. Sometimes a hazardous waste stream can be exempt from RCRA if it is regulated under a NPDES permit and solvent concentrations do not exceed specified limits

(40 CFR 261). However, none of the NTS facilities receiving liquid waste streams have NPDES permits and therefore, the wastes are all potentially subject to RCRA. Suspected wastes and the facilities used to manage the wastes are discussed below.

- Steam-cleaning effluents from the Area 6 Machine and Welding Shop (Bldg. 6-623) and the Heavy Duty Repair Shop (Bldg. 6-800), both of which use corrosives and RCRA-listed solvents, are discharged to separate unpermitted, unlined ponds at Yucca Lake (Figure 4-1). The south pond, which receives effluent from Building 6-800, also may overflow during storm events; at the time of the Survey, the water level of the pond was near the top of the berm. This pond also had an oily sheen and a reddish color. Sediments in the ponds could also be hazardous. Survey-related sampling and analysis (S&A) of the discharges to the ponds, the pond waters, and the pond sediments is planned to detect RCRA-listed substances and determine hazardous characteristics.
- Wastewater from the Area 12 Construction Shops (Bldg. 12-8) and the Motor Pool Equipment Maintenance Shop (Bldg. 12-16), which use RCRA-listed solvents, is discharged to an unpermitted, unlined pond (i.e., the Area 12 industrial wastewater sump). There is evidence that this pond also overflows sometimes via a discharge pipe onto the land (i.e., soil was stained under the pipe opening outside the pond). In addition, sediment in the pond could also be hazardous per RCRA. Survey-related S&A of the discharge to the pond, the pond water, and the pond sediment is planned to detect RCRA-listed substances and determine hazardous characteristics.
- Cleaning wastes generated at the Area 2 Cutter Rebuild Shop contain RCRA-listed solvents and are discharged down two unpermitted shallow wells (i.e., one is located inside the shop where the cutters are cleaned, and the other is located outside the shop where the rollers are cleaned; both wells are reportedly 48 feet deep with a 20-inch casing below a 52-inch casing).
- Effluents from the Area 6 Decontamination facility are discharged via 2 sumps to a 1.0-acre seepage/evaporation pond. The volume discharged to the pond during 1986 was estimated to be 3.6 million gallons (Clark, 1987). In June of 1986, NTS collected and analyzed water from the decontamination pond for radioactivity and organics (Bicker, 1986). Levels of organic contamination found are presented below:

Contaminant	Concentration (ppb)
Acetone	130
Chlorobenzene	250
Methylene chloride	45
Xylenes (total)	36

These and other chemicals have the potential to accumulate in the soil under the pond water. If the soils/sediments become contaminated, the pond would be considered by regulatory agencies to be a mixed-waste storage unit and subject to RCRA regulations (i.e., would require a double liner system, a leachate detection and collection system, and a groundwater monitoring network, or appropriate waivers). Regulations require upgrading or facility closure by November 1988. Analysis of pond sediment had not been conducted prior to the DOE Environmental Survey. Survey-related S&A of the sump water, the sump sediment, the pond influent, the pond water, and the pond sediment is planned to detect RCRA-listed substances and determine hazardous characteristics.

Sediments that accumulate in the two sumps at the Area 6 decontamination facility are solidified in drums and taken to the Area 3 RWMS landfill for burial as low-level radioactive waste approximately twice a year. If the sediments are hazardous as well as radioactive (i.e., mixed waste), the sumps would also have to be managed as hazardous waste storage units because they hold sediment for more than 90 days. At the time of the Survey, no data on the chemical constituents of the sediments were available that would indicate if the sediments have hazardous characteristics or contain RCRA-listed materials. At the time, it was also NTS policy not to bury any mixed waste on-site. A RCRA Part A permit application for the Area 3 RWMS was submitted to the State, and the State has not yet granted interim status to the RWMS. The Area 3 RWMS landfill does not contain liners, a leachate detection and collection system, or a groundwater monitoring network.

- Waters from the active Area 12 test tunnels (i.e., U12n and U12t) that discharge to the downstream ponds may be mixed waste. On June 12, 1986, water samples were collected from the effluent lines at E, N, and T tunnels and the first two holding ponds at N and T tunnels (Bicker, 1986). Analysis detected both radioactivity and low concentrations of methylene chloride in the effluent water from T-tunnel and in the waters from both

ponds at T-tunnel. Concentrations of methylene chloride (a RCRA-listed solvent) found are presented below:

Sample Location	Concentration (ppb)
T-Tunnel Pond 1	9,300
T-Tunnel Pond 2	1,800
T-Tunnel Effluent	3,450

No other organics were detected in these waters, and no hazardous contaminants were found in the other tunnel effluents or pond waters sampled. However, the sediments in all the ponds could be contaminated, and if so, these ponds would also be subject to RCRA regulations. No chemical data on pond sediments were available at the time of the Survey. In addition, the land area used for the disposal of the G-tunnel discharge also could be contaminated. Survey-related S&A of the pond influents, pond waters, and pond sediments is planned to detect RCRA-listed substances and determine hazardous characteristics.

- Some of the liquid waste from the Area 23/Building 650 radiochemistry laboratory (one of two laboratories in the building) is potentially mixed waste. Based on laboratory activities, the waste contains some level of radioactivity and some amount of organic solvents, acids, and caustics. No chemical data were available on the effluent characteristics or constituents. Laboratory procedures dictate that, if radioactivity is detected in the waste, it is to be solidified in beakers, drummed, and shipped to the Area 5 RWMS for disposal in LLW trenches or pits. If radioactivity is not detected, the waste is disposed of in sinks that drain to the building's leachfield. It is estimated that 25 gallons of this waste were discharged to the leachfield during 1986 (Clark, 1987) and that 1,730 cubic feet of the solidified waste were shipped to the Area 5 RWMS during 1986 (from the NTS waste management data base system). NTS possesses no permit under the Clean Water Act or RCRA for this discharge to the leachfield. In addition, until late 1986, the Area 5 RWMS was managing the waste as LLW. At the time of the Survey, NTS policy was to not bury any mixed waste at the RWMSs. Survey-related S&A of the discharge to the leach field is planned to detect RCRA-listed substances and determine hazardous characteristics.
- Core samples and solidified and unsolidified decontamination wastes disposed of in emplacement and drill-back holes could be mixed wastes according to site personnel. Core samples consist of mixed fission and activation products obtained from the solidified

detonation debris/melt during post-shot drilling. The samples are classified, and are disposed of in deep, cased holes or returned to the drill holes from which they came. Two holes are active: Hole U3fi in Area 3 and Hole U9u in Area 9. Two other holes in Area 3, J-6 and J-11, could be used for disposal of classified core samples. Decontamination wastes include water solutions used to remove particulate radioactive contamination from various items (e.g., drilling equipment and instruments) at drill-back and tunnel reentry sites and the Area 12 decontamination area. Decontamination operations at drill-back and tunnel-reentry sites generally consist of an initial washing/spraying of the contaminated items with water, and thus, the waste is only radioactively contaminated (i.e., no hazardous substances are used for decontamination and thus become part of the waste stream). Often the contaminated waters end up in the site's mud pit or on the ground. Sometimes the area is scraped over with uncontaminated soil to reduce radiation exposure. These wastes are also trucked for disposal at various sites, including tunnel ponds (e.g., U12n and t ponds), contaminated mud disposal craters (e.g., U2bu, U3ai-be, and U9y), liquid disposal holes (e.g., U8d, J-6, J-11, and U9ITS-Y30-PS1a), and the Area 6 decontamination facility. Some classified decontamination wastes are solidified and disposed of in core holes (e.g., U3fi and U9u). Contaminated washwater from the Area 12 decontamination area is collected in trays that drain to a small aboveground tank. When the tank becomes full, contents are trucked for disposal to hole U8d, located in Area 8, or to the Area 6 decontamination facility.

The wastes are definitely radioactive, but no chemical analyses had been conducted to determine the chemical properties and constituents of the wastes. The wastes could contain metals and could leach enough during EPA extraction procedure testing that the wastes would be considered toxic per 40 CFR 261, Subpart C. The lead in the core samples, however, could be sealed by oxides and would not be mobile in the area soils (i.e., water is not sufficiently present in the soils to transport the lead). None of the holes used for disposal of these wastes are permitted under RCRA. A RCRA Part A permit application for the Area 3 RWMS, which includes a landfill and hole U3fi, has been prepared and submitted to the State.

2. Use of Unpermitted Facilities to Destruct Hazardous Waste. Two unpermitted facilities are used to destruct hazardous wastes. Because the facilities are not designed to control the release of hazardous materials (i.e., to assure that a certain percentage of the hazardous materials are destroyed), such materials could be released into the environment, potentially posing an environmental risk.

- Explosive ordnance wastes, which are hazardous wastes, are detonated in a crater in Area 11. Wastes and containers remaining after detonation are burned in the crater. Although sites used for open detonation/burning of these wastes are regulated by RCRA interim status standards (Subpart P of Part 265), NTS has not included this site in a RCRA Part A permit application. Such sites will also require Part B permits. EPA issued permitting standards for such sites under Subpart X of Part 264 on December 10, 1987; the final rule became effective on January 11, 1988 (52 FR 46946). The standards contain performance objectives requiring permit applicants to evaluate the potential environmental impacts of sites and demonstrate that releases will not adversely affect human health or the environment. Applicable air emission permitting requirements for this open burning activity are discussed in Section 3.1.2.2, Nonradioactive Air Contaminants at the NTS; air aspects of this disposal practice are addressed in Section 3.1.4.4, Finding No. 4.

- Paper wipes used to clean device components during assembly in Area 27 (i.e., the Able and Baker Sites) are burned along with other combustibles in an open cage in Area 27. These wipes contain various RCRA-listed solvents added during the cleaning process. Some wipes could also be considered ignitable, as defined by 40 CFR 261. The burning of this waste is not included in a RCRA Part A application; and thus, the cage does not have RCRA interim status to burn the waste (i.e., RCRA regulatory approval). Nor was a Part B permit application being prepared for this facility at the time of the Survey. Furthermore, the facility did not possess a required air pollution control permit for this burning (refer to Section 3.1.2.2 and Section 3.1.4.4, Finding No. 5).

3. Unpermitted Discharges of Potentially Hazardous Wastes to the Land. Two potentially hazardous wastes are discharged onto the land without RCRA or Clean Water Act/NPDES permits. These discharges may result in localized soil contamination with hazardous waste.

- Cutting fluids from the Area 6 Machine and Welding Shop (Bldg. 6-623; Figure 4-1) are discharged onto the land in an area just north of the building (approximately three to four 55-gallon drums/year). In addition, cutting oils used in Areas 23 and 27 are collected in vermiculite absorbent after use and disposed of in the Area 23 sanitary landfill. These fluids are aqueous-based but could have RCRA hazardous characteristics after use (i.e., metal concentrations of leachates could exceed RCRA toxicity limits). Survey-related S&A was recommended on the cutting fluids. However, because of the recent resource reallocations, they were eliminated from the NTS S&A.

- Waters used to spray off the trucks that mix the epoxy-based stemming material are discharged to the land. During these cleaning operations, the waters could become contaminated with toluene diisocyanate, which is contained in one of the epoxy components and is listed as a hazardous substance (40 CFR 261). These discharges are unpermitted and occur sporadically wherever there is a stemming operation using epoxy-based material.

4. Unapproved Solid Waste Management Operations. NTS uses various facilities to handle nonhazardous waste (Figure 4-7). These are:

- Three sanitary landfills, located in Areas 6, 10, and 23.
- Two construction landfills, located in Areas 3 and 19.
- Several solid waste trenches, located in Areas 6, 12, and 23.
- At least two craters located in Area 3 that are used for the disposal of excess and spoiled drilling muds (U3ag, which is near the Area 3 mud plant, and U3ai-be).

Permits to operate these facilities in Nevada are not required; however, owners/operators must submit solid-waste management plans to the State for such facilities. These plans need to specify waste types to be disposed and operation and maintenance procedures to be used, including controls to prevent the disposal of nonapproved wastes (Nevada Administrative Code 444.850-444.935). At the time of the DOE Environmental Survey, NTS did not have such plans, and therefore, NTS solid waste management operations were not State-approved. These facilities could potentially receive hazardous materials. Because the facilities are not designed to contain hazardous materials (i.e., to meet RCRA standards), such materials could be released from the facilities into the environment, potentially resulting in soil and groundwater contamination (refer to Sections 3.2.4 and 3.4.4).

The DOE Environmental Survey team found few controls in place to assure that only nonradioactive/nonhazardous waste was being disposed of at these disposal sites. None of the facilities are fenced or have around-the-clock access control. The disposal of wastes in the sanitary landfills is controlled during the day shift by the operators. In addition, the operators would be able to detect night time waste disposal the following day if they were to see uncovered waste, because all wastes are supposedly covered daily. However, there are no operators at the solid waste trenches, and wastes are not covered routinely. Operators at the Area 6 and Area 23 landfills could, perhaps, observe unapproved disposal into trenches in those areas because the trenches are located near the landfills. The Area 12 trenches, however, are at a more remote location, and nobody works in the area to control disposal.

The construction landfills are operated by construction personnel and are only monitored by industrial hygiene personnel every two weeks. No reports of any unapproved disposal in landfills or trenches were found by the DOE Survey team, and only minor occurrences were recalled by NTS personnel. There is less control at the mud disposal craters. Small quantities of hazardous waste (e.g., mud additive containing chromium) reportedly could have been disposed of in the Area 3 mud plant crater in the past, and radioactively contaminated drilling muds could still be disposed of in Crater U3ai-be.

Furthermore, some wastes are disposed of in landfills and trenches that have never been analyzed/characterized and potentially contain hazardous constituents. Sewage sludge in the Area 23 sewage lagoons could be characterized as hazardous because some hazardous materials, such as organic solvents, acids, and caustics, are poured down sink drains in various shops and the industrial hygiene laboratory (one of two laboratories located in Building 650). The sludge could also have high enough levels of leachable metals to be considered RCRA-toxic (40 CFR 261). This sludge is disposed of in the Area 23 landfill. In addition, wastewaters disposed of in solid waste trenches could be hazardous at times. For example, the Quonset 800 steam jenny sump located in Area 23 receives water used to steam clean a 500-gallon pesticide application container; the sump contents are collected in a vacuum truck and disposed of in the Area 23 solid waste trench. Also, wastes from chemical toilets, which are disposed of in solid waste trenches, may contain formaldehyde, which is a RCRA-listed waste (U122; 40 CFR 261).

4.1.3.3 Category III

1. Area 23 Hazardous Waste Landfill. The Area 23 hazardous waste landfill was not adequately designed to contain hazardous constituents per RCRA requirements. The landfill, which is inactive, consists of three unlined trenches, designated as "A," "B," and "C." Trenches "B" and "C" are located adjacent to each other and are 338 feet and 216 feet long, respectively. Trench "A" is 55 feet long and located approximately 130 feet east of Trench "B." The trenches were constructed using a backhoe to dig a 3-foot-wide by 4-foot-deep cut into the alluvial soils. Because the trenches were unlined and the soils are highly permeable, infiltration and contaminant migration have occurred. Investigations have determined that contaminants have infiltrated down to approximately 20 feet below the trenches in some places (Earth Technology Corporation, 1987).

The trenches were used mostly for disposal of uncontained liquids and were operated over a 13-year period from 1969 to 1982 (Earth Technology Corporation, 1987). Records of disposal

indicate that approximately 20,000 gallons of waste were landfilled. Waste materials can be broken down into the following types: 10,000 gallons of corrosives, 5,500 gallons of ignitables, 1,000 gallons of toxics or reactives, and the remaining 3,500 gallons of miscellaneous nonhazardous chemicals. Small volumes of liquid wastes were poured into the open portions of the trenches and allowed to evaporate and infiltrate until surface materials were dry. In addition, small amounts of solid wastes were placed into these trenches. When dry, trenches were backfilled to grade with the overburden removed during the initial trenching operations.

Because the landfill was operated under RCRA interim status from 1980 to 1982, it is subject to RCRA closure and post-closure requirements. In addition, because wastes were disposed of in the landfill after June 26, 1982, it is subject to RCRA groundwater monitoring requirements, which extend to the post-closure period. A closure/post closure plan was being revised at the time of the DOE Environmental Survey. An earlier version included a closure alternative that involved excavation of wastes and contaminated materials. Because contamination would be removed, no groundwater monitoring or post-closure care would be required. The alternative being developed at the time of the Survey involved capping to drain water away and installation of moisture-sensor devices under the trenches and adjacent to them at various depths to track infiltration and migration.

2. Area 23 Hazardous Materials and Waste Holding Area. The Area 23 hazardous materials and waste storage holding area provides insufficient protection from the release of hazardous constituents. The area (100 feet x 50 feet) is uncovered, and containers are directly exposed to the sun. Pressure in the drums could build up sufficiently to cause the drums to rupture or explode, thereby releasing drum contents. Sand bags are also used for spill containment. However, the sand bags might be insufficient to segregate spills of incompatible materials or contain spills within the storage area. In addition, storage is not on an impervious pad; spills would contaminate the area's soil. See Section 4.1.2.1.1, Hazardous Waste, for further details on this holding area and a discussion of the 1987 RCRA inspection by EPA.
3. Hazardous Waste Holding Area – North Las Vegas. At the time of the Survey, the hazardous waste holding area at the A/B Complex appeared to have insufficient storage capacity. The holding area was filled to capacity, and four waste drums were being stored off the area's diked concrete pad. Two of the drums contained solvent-contaminated cutting fluids, one contained waste oil, and the fourth contained a used organic solvent. This situation represents a potential risk. If waste drums stored off the pad were ruptured, hazardous

materials could not be contained. Spills could flow to a nearby storm drain and toxic fumes could form if incompatible wastes were to spill and mix.

4.1.3.4 Category IV

1. Shipping of Hazardous Wastes from the Escondido and Sunset Facilities not in Compliance with RCRA. Hazardous wastes generated at the Escondido and Sunset facilities are trucked to the hazardous waste pad at the North Las Vegas B-Complex for storage. This shipping is not in strict compliance with RCRA regulations for three reasons:

- The B-Complex cannot receive outside shipments of hazardous wastes because it is not a RCRA-designated facility (i.e., it is not permitted for the storage of RCRA wastes per 40 CFR 260.10).
- Hazardous wastes can be shipped over public highways/roads only by RCRA-approved hazardous waste transporters that possess a RCRA identification number (40 CFR 263.11); at the time of the Survey, EG&G was not registered as a hazardous waste transporter.
- Shipments of hazardous wastes must be manifested; no manifests tracking the shipment of hazardous wastes from the Escondido or Sunset facilities to the B-Complex were on file.

4.2 Toxic and Chemical Materials

4.2.1 General Description of Pollutant Sources/Controls

4.2.1.1 Toxics Management

Various REECO organizations share responsibility for the transportation, storage, use, and disposal of toxic and chemical materials at NTS. These responsibilities are defined in REECO Procedure 3-2-51, "Hazardous Material Control" (REECO, 1987a). Any toxic or chemical material recognized as a hazardous material by the federal Department of Transportation (DOT) is subject to the requirements of this procedure. This includes hazardous materials used by any NTS contractor.

The REECO Procurement Department purchases all materials, including hazardous materials, from off-site vendors. The Procurement Department informs suppliers of REECO's packaging, labeling, and shipping requirements for hazardous materials, and notifies the REECO Industrial Hygiene section whenever a hazardous material is purchased.

The REECO Supply and Property Management Department is responsible for the receipt of hazardous materials at NTS from off-site suppliers. This department also reviews requisitions for the purchase or delivery of hazardous materials, arranges for the transportation of hazardous materials within the boundaries of NTS, and maintains on-site warehouses where hazardous materials are stored.

The Supply and Property Management Department must notify the Industrial Hygiene Section whenever it receives a request from an operating group at NTS to supply hazardous materials either from the on-site inventory or via an off-site supplier. Upon receipt of these hazardous materials, a Receiving Form (RE-0858) is prepared that indicates that the shipment consists of hazardous materials. A Warehouse Shuttle Bill of Lading-Hazardous Material (RE-0173) is also completed prior to releasing any hazardous material (from either Receiving or the on-site warehouses) for delivery to an on-site or off-site location. Copies of both of these forms are provided to the Industrial Hygiene Section.

The Fleet Operations Department provides trained and certified drivers to transport hazardous materials throughout NTS. These drivers are responsible for the loading, security and protection of the hazardous materials during transit, assuring that the required manifests have been completed and determining that the materials are properly labeled and packaged. Drivers have the authority to refuse shipments for deficiencies in any of these areas.

The Industrial Hygiene Section provides technical assistance regarding the transportation, use, storage, and disposal of hazardous materials to the other REEC Co departments and NTS contractors. A computerized inventory of all hazardous materials and the corresponding Material Safety Data Sheets (MSDS) in use at NTS is also maintained. The Industrial Hygiene Section reviews all requests for hazardous materials, and can reject the purchase or use of a particular hazardous material at NTS due to potential environmental or occupational health concerns.

As indicated above, the Industrial Hygiene Section is also notified when shipments of hazardous materials are delivered to NTS operating units. This information, such as date and location of delivery, product name, the DOT hazard rating, and whether the operating unit receiving the hazardous materials is a REEC Co department or other NTS contractor, is also maintained in the computerized inventory. A unique number is assigned to each product that indicates the type of hazardous material (26 different categories have been established by REEC Co) delivered to the user.

The Supply and Property Management Department maintains warehouses and other facilities at which hazardous materials are stored in Areas 6 and 23. Warehouse E in Area 23 contains supplies of hazardous materials such as paints, compressed gases, and 55-gallon containers of flammable solvents, acids, and caustics. During the Environmental Survey, the compressed gas and paint storage areas were inspected and found to be adequate. However, approximately one hundred 55-gallon drums of hazardous materials were stored out-of-doors and were not protected from adverse weather conditions. Furthermore, the drums were either placed on wooden pallets or stored directly on the desert floor, and consequently, potential spills from these drums would not be contained. Two other storage locations in Area 23 (Warehouses A and R) were also inspected during the Environmental Survey. No deficiencies with respect to storage of toxic and chemical materials were noted in Warehouse A. However, in the Acid Storage Room in Warehouse R, approximately fifty 1-gallon glass containers of acids and caustics were stored together, a situation that is not consistent with standard storage practices for acids and caustics.

Warehouse H, located in Area 6 near the Yucca Lake complex, does not provide storage for hazardous materials. However, a covered, elevated (approximately 6 feet above the desert floor) concrete pad adjacent to Warehouse H is used to store approximately two hundred 55-gallon drums of various lubricants and oils. At the time of the Environmental Survey, the concrete pad had not been equipped with curbing to contain potential spills.

A structure located behind the A-1 complex at the EG&G facilities in North Las Vegas is used to store toxic and chemical materials. During the Environmental Survey, this "chemical storage shed" was

inspected and found to be inadequate for storage of such materials. This structure was overcrowded and incompatible hazardous materials were not segregated or stored in an orderly manner.

In addition to the potential environmental contamination that could result from the improper storage of hazardous materials identified at Warehouses E and R, the oil storage pad in Area 6 and the chemical storage shed in North Las Vegas, ongoing releases of hazardous materials at other storage locations were noted during the Environmental Survey. These included racks used to store 55-gallon drums of solvents, oils, and lubricants located in Areas 2, 3, 6, 12, and 23 that were equipped with drip trays that discharged onto the ground. In addition, bags of chromium-containing mud additives stored out-of-doors at the Area 3 mud plant were damaged and releasing their contents to the environment. At the Area 12 fleet operations building, drums containing unknown oily materials were not equipped with lids, and appeared to have overflowed in the past. Finally, leaking drums of oily liquids were discovered during a tour of Test Cell C in Area 25.

At the time of the Environmental Survey, the labeling system developed by the Department of Transportation was being used to label hazardous materials at NTS. However, NTS personnel indicated that all site contractors had agreed to implement the National Paint and Coatings Association's Hazardous Materials Information System (HMIS) in the near future (Rey, 1987). The HMIS is one of several systems that have been developed for informing workers of the potential hazards associated with toxic and chemical materials.

4.2.1.2 Tank Farm Facilities

4.2.1.2.1 Underground Storage Tanks

In 1986, pursuant to the requirements of Section 9002 of the Resource Conservation and Recovery Act, NTS notified the State of Nevada that 50 underground storage tanks (USTs), used for the storage of waste and non-waste toxic and chemical materials, were present on the site (Frazier, 1986a). One UST at the EG&G facilities in Las Vegas was also reported (Kesler, 1986). These tanks are shown in Table 4-8. At the request of the state, NTS also provided information on 14 USTs at NTS with a capacity of 1,000 or more gallons that are used to store heating oil for consumptive use on the premises (such heating oil tanks, regardless of capacity, are exempt from the RCRA reporting requirements). Table 4-9 contains a listing of these latter USTs. For a discussion of USTs used to store waste materials, also see Section 4.1.2.1.1 of this report.

Forty-nine of the 64 USTs that were reported to the State of Nevada by NTS are constructed of steel and are at least 15 years old. The age of one UST (at Building 6-311) is unknown. Of these 50 USTs,

TABLE 4-8

**UNDERGROUND STORAGE TANKS USED TO STORE WASTE
AND NON-WASTE TOXIC AND CHEMICAL MATERIALS
NEVADA TEST SITE, MERCURY, NEVADA**

NTS-UST ¹ Identification Number	Age	Capacity (Gallons)	Contents	Tank Material	Corrosion Protection	Status
EG&G-1	11	1,000	Empty	Steel	Cathodic/Painted	PQOS ²
6-1	20	8,000	Diesel	Steel	Painted	In Use
6-9	10	5,000	Diesel	Steel	Unknown	In Use
6-162-1	16	3,500	Empty	Steel	None	PQOS
6-162-2	16	6,000	Binder	Steel	None	In Use
6-162-3	16	6,000	Asphalt	Steel	None	In Use
6-162-4	16	6,000	Asphalt	Steel	None	In Use
6-605	17	4,800	Diesel	Steel	Painted/Lined	In Use
6-607	16	5,000	Diesel	Steel	Painted/Lined	In Use
6-619-1	15	10,000	Gasoline	Steel	None	In Use
6-619-2	15	10,000	Gasoline	Steel	None	In Use
6-619-3	15	10,000	Diesel	Steel	None	In Use
6-619-4	15	2,000	Used Oil	Steel	None	In Use
6-619-5	15	4,000	Oil	Steel	None	In Use
6-619-6	15	4,000	Oil	Steel	None	In Use
12-1216	19	1,000	Used Oil	Steel	None	In Use
12-1226-1	19	10,000	Gasoline	Steel	None	In Use
12-1226-2	19	10,000	Gasoline	Steel	None	In Use
12-1226-3	19	10,000	Diesel	Steel	None	In Use
12-1230	16	5,000	Diesel	Steel	Painted/Lined	In Use
12-N-1	4	4380	Diesel	FRP ³	--	In Use
12-N-2	8	200	Gasoline	Steel	Painted	In Use
12-T-1	4	4,380	Diesel	FRP	--	In Use
12-T-2	4	200	Gasoline	FRP	--	In Use

TABLE 4-8
UNDERGROUND STORAGE TANKS USED TO STORE WASTE
AND NON-WASTE TOXIC AND CHEMICAL MATERIALS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE TWO

NTS-UST ¹ Identification Number	Age	Capacity (Gallons)	Contents	Tank Material	Corrosion Protection	Status
22-DRA-1	23	25,000	Aviation Gas	Steel	Painted	POOS
22-DRA-2	17	11,000	Jet-A50	Steel	Painted	In Use
22-DRA-3	7	26,000	Jet-A50	Steel	Coated	In Use
23-115-1	9	15,000	Diesel	Steel	Painted	POOS
23-115-2	9	15,000	Diesel	Steel	Painted	POOS
23-115-3	23	7,500	Diesel	Steel	Painted	POOS
23-160-1	35	10,000	Kerosene	Steel	Unknown	In Use
23-160-2	35	10,000	Diesel	Steel	Unknown	TOOS ⁴
23-160-3	35	10,000	Gasoline	Steel	Unknown	TOOS
23-160-4	35	10,000	Diesel	Steel	Unknown	TOOS
23-160-5	35	10,000	Kerosene	Steel	Unknown	In Use
23-425	21	15	Gasoline	Steel	Painted	In Use
23-600	21	555	Diesel	Steel	Painted	In Use
23-650	21	555	Diesel	Steel	Painted	In Use
23-725	21	1,500	Diesel	Steel	Painted	In Use
23-750	22	2,000	Used Oil	Steel	None	In Use
23-751-1	22	2,000	Used Oil	Steel	None	In Use
23-751-2	22	2,000	Used Oil	Steel	None	In Use
23-752-1	22	10,000	Gasoline	Steel	None	In Use
23-752-2	22	10,000	Gasoline	Steel	None	In Use
23-752-3	22	10,000	Diesel	Steel	None	In Use
23-754-1	4	12,000	Diesel	FRP	--	In Use
23-754-2	4	12,000	Diesel	FRP	--	In Use
25-4838-1	22	10,000	Gasoline	Steel	None	In Use

TABLE 4-8
UNDERGROUND STORAGE TANKS USED TO STORE WASTE
AND NON-WASTE TOXIC AND CHEMICAL MATERIALS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE THREE

NTS-UST ¹ Identification Number	Age	Capacity (Gallons)	Contents	Tank Material	Corrosion Protection	Status
25-4838-2	22	10,000	Diesel	Steel	None	In Use
25-4838-3	22	550	Used Oil	Steel	None	In Use
27-5120	28	550	Gasoline	Steel	Unknown	In Use

Source: DOE Environmental Survey Team, 1988. Adapted from NTS report to State of Nevada (Frazier, 1986b) and Kesler, 1986.

- 1 The number used by NTS to identify underground storage tanks. The number reflects the Area at NTS in which the tank is located, the facility nearest to the location of the tank, and an additional number when multiple tanks are at a location. For example, tank 6-162-2 is the second tank located near Building 162 in Area 6.
- 2 POOS = Permanently out of service.
- 3 FRP = Fiberglass reinforced plastic.
- 4 TOOS = Temporarily out of service.

TABLE 4-9

**UNDERGROUND STORAGE TANKS WITH A CAPACITY OF
GREATER THAN 1,000 GALLONS USED TO STORE HEATING OIL
NEVADA TEST SITE, MERCURY, NEVADA**

NTS-UST ¹ Identification Number	Age	Capacity (Gallons)	Contents	Tank Material	Corrosion Protection	Status
6-311	Unknown	1,200	Empty	Steel	Unknown	POOS ²
12-1216	22	3,500	Diesel	Steel	Painted	In Use
23-128	29	1,500	Diesel	Steel	Painted/Lined	In Use
23-210	34	2,000	Diesel	Steel	Unknown	TOOS ³
23-536-1	2	6,000	Diesel	FRP ⁴	---	In Use
23-536-2	2	6,000	Diesel	FRP	--	In Use
23-753-1	4	8,000	Diesel	FRP	--	In Use
23-753-2	4	8,000	Diesel	FRP	--	TOOS
25-3110	23	10,000	Diesel	Steel	Unknown	TOOS
25-4015	23	5,000	Diesel	Steel	Unknown	TOOS
25-4220	22	2,500	Diesel	Steel	Unknown	In Use
25-4222	22	2,500	Diesel	Steel	Unknown	In Use
27-5170	31	4,000	Empty	Steel	Lined	POOS
27-5310	31	4,000	Empty	Steel	Lined	POOS

Source: DOE Environmental Survey Team, 1988. Adapted from NTS report to State of Nevada (Frazier, 1986a).

¹ The number used by NTS to identify underground storage tanks. The number reflects the Area at NTS in which the tank is located, the facility nearest to the location of the tank, and an additional number when multiple tanks are at a location. For example, tank 6-162-2 is the second tank located near Building 162 in Area 6.

² POOS = Permanently out of service.

³ TOOS = Temporarily out of service.

⁴ FRP = Fiberglass reinforced plastic.

only 15 are known to have been provided with any type of corrosion protection. Therefore, a portion of these tanks may be releasing their contents to the environment, since it is generally accepted that steel USTs lacking corrosion protection and more than 15 years old have a higher probability of leaking. However, due to the dry desert climate at NTS, the rate of UST corrosion, deterioration, and leakage is presumably low compared to locations receiving more rainfall. Nevertheless, NTS has not tested any of its USTs for leakage, and relies upon a "dip stick" method for inventory control that would not detect slow UST leaks occurring over a long period of time. Sampling and analysis of a representative fraction of the oldest of these USTs is being conducted as part of the Environmental Survey.

Other USTs are present at NTS. These include 20-30 USTs (with a capacity less than 1,000 gallons) that are used to store heating oil for use at the location of the tank (Green, 1987) and, therefore, are not reportable under RCRA Section 9002. However, 19 additional USTs, at least 6 of which are subject to the RCRA reporting requirements, were identified during the Environmental Survey. Since none of these USTs were reported to the State of Nevada, little information, other than probable contents, was available to the Survey team. This information is summarized in Table 4-10.

Six of the USTs that were identified during the Environmental Survey are reportable under RCRA Section 9002. These include: the UST used to store gasoline at the Area 23 public service station (Building 109); the 3 USTs adjacent to Building 116; the UST containing diesel fuel at Baker Compound in Area 27 that supplies the emergency generator; and the UST for the saturated sodium chloride solution used to regenerate the zeolite water softener at Army Well No. 1 in Area 23. The three USTs near Building 116 have been used at different times to store both diesel fuel and gasoline. At the time of the Environmental Survey, these three USTs were empty, but they are intended for use as necessary (Minster, 1987). In contrast, the UST at the Area 23 public service station, the UST at Baker Compound, and the sodium chloride UST at Army Well No. 1 were in use during the on-site portion of the Environmental Survey. Since all six of these USTs are either currently in use or have been in use since 1974, they are reportable under RCRA Section 9002. It should also be noted that, with the exception of the Baker Compound UST installed in 1985, these USTs are probably more than 15 years old.

The dates of installation and last usage for four of the nineteen USTs identified during the Environmental Survey could not be ascertained. Since any USTs that were removed from service prior to January 1, 1974 are exempt from the RCRA reporting requirements, it is possible that none of these tanks should have been reported to the State of Nevada by NTS. The USTs in this category include 2 USTs (presumably one for diesel fuel and the other gasoline) at the inactive service station in Area 18, and one UST (most likely for gasoline) at the Area 25 inactive service station. According

TABLE 4-10

**UNDERGROUND STORAGE TANKS IDENTIFIED
DURING ENVIRONMENTAL SURVEY
NEVADA TEST SITE, MERCURY, NEVADA**

Location of Tank	Contents When Last Used	Status	Reportable Under RCRA-Section 9002
Area 7 "BJY" decontamination pad	Fuel	POOS ¹	Unknown
Area 18 inactive service station	Diesel	POOS	Unknown
Area 18 inactive service station	Gasoline	POOS	Unknown
Area 23 public service station (Building 109)	Gasoline	In Use	Yes
Area 23 near Building 116	Gasoline (3 tanks)	TOOS ²	Yes
Area 23 near Army Well No. 1	Saturated Salt Solution	In Use	Yes
Area 25 inactive service station (Building 3107)	Gasoline	POOS	Unknown
Area 25 at E-MAD under concrete pad at southwest end of building	Radioactive Wastes (2 Tanks)	POOS	No
Area 25 at Test Cell A near pumping station (Building 3116)	Unknown	POOS	No
Area 25 at Test Cell C	Radioactive Effluent from Nuclear Furnace Tests (6 Tanks)	POOS	No
Area 27 Baker Compound emergency generator	Diesel	POOS	Yes

Source: DOE Environmental Survey Team, 1988.

¹ POOS = Permanently out of service

² TOOS = Temporarily out of service

to NTS Supply Section personnel, these 3 USTs should have been drained when taken out of service, but no documentation exists to support this contention (Minster, 1987). The fourth UST that may or may not be reportable, depending upon the date that it was last used, is a 500-1,000 gallon UST for fuel at the inactive "BJY" decontamination pad (for a further discussion of this area, see Section 4.5.2.11 of this report). BJY is a term used at NTS to refer to an intersection that now is comprised of Rainier Mesa Road, Mercury Highway, and Road 7-01. No other information on the UST at this inactive decontamination pad was available.

Nine of the nineteen USTs that were identified during the Environmental Survey are not reportable under RCRA Section 9002 since they were taken out of service prior to January 1, 1974. All are located in Area 25. These nonreportable USTs include two steel USTs at the E-MAD facility that reportedly at one time provided pre-disposal storage and contained radioactive liquid wastes. The E-MAD facility was used during the 1960s and 1970s for the assembly and disassembly of nuclear rocket engines, and radioactive liquid wastes were generated as a result of these operations. Solvents, degreasers, and other chemical wastes may also have been discharged with the radioactive wastes. A steel UST was also identified at Test Cell A in Area 25. The Survey team learned that this 100,000-gallon-capacity UST was used to store water when remote testing of nuclear rocket engines was conducted at Test Cell A in the 1950s and 1960s; however, the current content of this UST is unknown. Finally, at Test Cell C six USTs were identified that received effluent from nuclear furnace tests that were conducted when this facility was in operation. No additional information with respect to the size or construction of these six USTs was available to the Survey team. It is not known whether the USTs at E-MAD, Test Cell A, or Test Cell C presently contain wastes or if they have leaked their contents to the surrounding soil. Sampling and analysis of these nine USTs has been proposed as part of the Environmental Survey.

Three USTs are located at the Desert Rock Airstrip (DRA). During the period from December 20 to 26, 1986, approximately 18,000 gallons of Jet-A50 fuel were inadvertently released from UST 22-DRA-3, resulting in subsurface soil contamination. The cause of the leak was a malfunctioning inground vertical turbine pump (Boyce, 1986). At the time of the Environmental Survey, the subsurface soil contamination that resulted from this leak had not been remediated. For an additional discussion of this release, see Section 4.5.2.9 of this report.

Surface soil contamination at several UST locations was also noted during the Environmental Survey. Extensive soil contamination was noted at the USTs used to store asphalts and binders at Building 6-162. Relatively minor surface contamination (presumably resulting from improper filling practices) was observed at the waste oil UST at Building 12-16 and the UST for the boiler at Building 6-607.

4.2.1.2.2 Above-Ground Storage Tanks

The location, contents, capacity, type of secondary containment, and status of above-ground storage tanks used to store toxic and chemical materials (and perhaps wastes) at the time of the Environmental Survey, are shown in Table 4-11. Tanks used to store water or propane gas have not been included. This listing was compiled from the Environmental Compliance Atlas furnished to the Survey team (NVO, 1987), observations of the Survey team, and interviews with NTS personnel. Most of these tanks are used for the storage of gasoline, diesel fuel, or oils.

At those locations where tanks have been provided with secondary containment by NTS, the dikes are constructed from the desert floor. However, 16 of the 26 above-ground storage tanks identified at NTS during the Environmental Survey lacked any secondary containment, including two tanks at the EG&G facilities in Las Vegas. Although not required by state or Federal regulations, secondary containment dikes for above-ground storage tanks that are constructed of impervious materials such as concrete or compacted clay will more effectively contain leaks and spills than the dikes made from sandy soil used at NTS. The most significant tanks with respect to potential environmental problems such as subsurface soil contamination that could result from leaks and spills are the two 420,000 gallon tanks used for storage of gasoline and diesel fuel in Mercury.

An above-ground storage tank not listed on the NTS inventory was identified during the Environmental Survey in Area 9 at the U9y crater. This approximately 50,000 gallon capacity tank appeared to be inactive. NTS personnel could not provide further information regarding past activities at this site. See Section 4.5.2.16 for additional discussions regarding this area.

Four inactive above-ground storage tanks are located in Area 25. At Engine Test Stand No. 1 (ETS), two tanks with a capacity of approximately 5,000 gallons were used in the past for the storage of acid and caustic. Both tanks are reportedly empty. A third tank (approximately 3,000 gallon capacity) at ETS was noted, but its past (or current) contents are unknown. At Test Cell C, radiation levels of approximately 1 mR/hour were measured at the surface of a relatively large water storage tank (capacity estimated at 250,000 gallons). NTS personnel could not explain the presence of radioactivity within this tank.

Two above-ground storage tanks at NTS were found to be leaking during the Environmental Survey. Both leaking tanks were located in Area 6. One tank, used to store diesel fuel for the emergency generator at CP-9, had a leaking drain valve. The other leaking tank was a transportable tank used to store asphalt. During the Environmental Survey, this latter tank was stored at Building 6-621.

TABLE 4-11

**ABOVE-GROUND STORAGE TANKS
NEVADA TEST SITE, MERCURY, NEVADA**

Tank	Location	Contents	Capacity (Gallons)	Type of Secondary Containment	Status
Area 1	Shaker Plant	Diesel	5,000	Earthen	In Use
Area 2	Mud Plant	Diesel	500	None	In Use
Area 3	Near Batch Plant	Diesel	3,000	None	In Use
		Diesel	5,000	None	In Use
Area 6	Yucca Lake Complex	Diesel	105,000	Earthen	In Use
		Gasoline	42,000	Earthen	In Use
		Ethylene Glycol	5,000	Earthen	In Use
		Kerosene	5,000	Earthen	In Use
		15-W-40 Oil	5,000	Earthen	In Use
		15-W-40 Oil	5,000	Earthen	In Use
		Turbine Oil	5,000	Earthen	In Use
	Building 6-621	Asphalt	Unknown	None	In Use
	Building 6-624	Kerosene	500	None	In Use
		Gasoline	300	None	In Use
	Building CP-9	Diesel	500	None	In Use
	Well 3 Yard	Gasoline	5,000	None	In Use
		Diesel	5,000	None	In Use
Area 9	Crater U9y	Unknown	50,000	None	Inactive
Area 23	Mercury	Diesel	420,000	Earthen	In Use
		Gasoline	420,000	Earthen	In Use
Area 25	Engine Test Stand No. 1	Empty (Acid)	5,000	None	Inactive
		Empty (Caustic)	5,000	None	Inactive
		Unknown	3,000	None	Inactive
	Test Cell C	Radioactive Water	250,000	None	Inactive
EG&G	Las Vegas	Lube Oil	1,000	None	In Use
		Fire-Fighting Foam	3,000	None	In Use

Source: DOE Environmental Survey Team, 1988. Adapted from NTS Environmental Compliance Atlas (NVO, 1987).

According to the EPA Oil Pollution Prevention regulations (40 CFR 112), facilities that store oils and could reasonably be expected to discharge oils into or upon the navigable waters of the United States are required to prepare a Spill Prevention, Control, and Countermeasures (SPCC) Plan. Although oils are stored at NTS, due to the absence of navigable waters, the site is not subject to the SPCC Plan requirements. Similarly, the PCB regulations (40 CFR 761) stipulate that facilities storing PCBs or PCB-contaminated liquids must prepare a SPCC Plan in accordance with CFR 112, but this requirement does not apply to NTS since releases to navigable waters are not possible. Accordingly, at the time of the Environmental Survey, NTS had not prepared a SPCC Plan or similar document. A spill response team had not been organized, and spill response procedures developed by NTS were only general in nature. Formal spill records were not maintained. According to NTS personnel, the formation of a spill response team was under consideration, but a decision to implement such measures had not been finalized (Haworth, 1987a).

4.2.1.2.3 Liquefied Gaseous Fuels (LGF) Spill Test Facility

The LGF Spill Test Facility is an operation at NTS that conducts research on the dynamics of accidental releases of various hazardous materials (Patton et al., 1986). The Spill Test Facility (STF) is designed to discharge, at a controlled rate, a measured volume of a hazardous test material. Using monitors stationed at various locations, meteorological and other data associated with the release are recorded. These functions are controlled and operated from a remote location. The STF includes separate systems for cryogenic and non-cryogenic materials. The former consists of two 28,000-gallon above-ground storage tanks whereas only one 26,000-gallon capacity tank is used to store non-cryogenic materials. Both systems share piping (500 feet in length) that leads to the spill area. Spills from both systems are pressure driven by separate nitrogen gas storage tanks. The volume of material used in these tests can vary from approximately 300 to 15,000 gallons.

The STF was originally developed to study spills of liquefied natural gas. An Environmental Assessment (EA) of the STF conducted pursuant to the requirements of the National Environmental Policy Act and issued by DOE in 1981 resulted in a Finding of No Significant Impact. In 1983, a series of spill tests for other gaseous fuels was proposed. The EA conducted at that time also concluded that no significant environmental impacts would be likely. Prior to 1986, the STF was regarded as a temporary facility. However, in 1986 it was proposed that the STF be considered a permanent facility. A further expansion of the list of materials for study was also proposed. A third EA issued in 1986 also resulted in a Finding of No Significant Impact (Patton et al., 1986). Table 4-12 lists the materials that have been approved for testing at the Spill Test Facility. As a matter of policy, NTS has concluded that no materials that accumulate and persist in the environment will be considered for

TABLE 4-12

MATERIALS APPROVED FOR TESTING AT THE SPILL TEST FACILITY
FRENCHMAN FLAT
NEVADA TEST SITE, MERCURY, NEVADA

Cryogenic	Non-Cryogenic	
Ammonia	Nitrogen tetroxide	Cyclohexane
Methane	Chlorine	Sulfur dioxide
Ethylene	Hydrazine	Carbon dioxide
Propane	Phosgene	Hydrogen fluoride
Butane	Propane	Ammonia
LNG	Butane	Hydrogen sulfide

Source: Patton et al., 1986

testing. In addition, spills tests must be less than 15 minutes in duration, and sufficient time between spills must be allowed for recovery of natural resources.

4.2.1.3 Polychlorinated Biphenyls (PCBs)

NTS uses electrical equipment that contains fluids that are contaminated with polychlorinated biphenyls (PCBs). In addition, one hydraulic system in Area 27 may be contaminated with PCBs as a result of nearby leaking electrical equipment; however, no heat transfer systems or capacitors that contain PCBs are present at NTS. The site maintains storage facilities for PCB and PCB-contaminated fluids and equipment awaiting disposal or reuse. PCBs are disposed off-site through EPA-licensed contractors.

Table 4-13 summarizes the known status of PCBs at NTS as of December 31, 1985. This information was derived from the NTS 1985 PCB Annual Report (Frazier, 1986b). However, as discussed below, NTS included in the report information only on those transformers and other equipment that had been tested for PCB content. Since there is other electrical equipment at NTS that remains to be tested for PCB content, Table 4-13 may be incomplete.

On December 31, 1985, it was known that 10 PCB transformers, 48 PCB-contaminated transformers, 9 PCB-contaminated regulators, and 1 PCB-contaminated circuit breaker were in-service at NTS. At the time of the Environmental Survey, one of the PCB transformers that had been in-service as of December 31, 1985 had been removed from service. Similarly, only 40 of the 48 PCB-contaminated transformers and 6 of the 9 PCB-contaminated regulators that had been listed in the 1985 PCB Annual Report submitted to the State of Nevada remained in-service at the time of the Environmental Survey. However, 4 additional in-service PCB-contaminated transformers had since been identified by NTS for a total of 44 in-service PCB-contaminated transformers. Table 4-14 lists the PCB and PCB-contaminated electrical equipment (in-service or stored for reuse) that had been identified by NTS at the time of the Environmental Survey (for the reasons cited above, this listing may also be incomplete). Twelve of the 44 in-service PCB-contaminated transformers were pole-mounted, and 3 of the 6 PCB-contaminated regulators were mounted on a mobile trailer that is stored in Area 2. None of the 9 PCB transformers were either pole- or trailer-mounted.

EG&G in Las Vegas does not own any PCB transformers (White, 1985). All transformers associated with the operation of these facilities are the property of the local electrical utility company (Salazar, 1987).

TABLE 4-13

**PCB AND PCB-CONTAMINATED EQUIPMENT OR FLUIDS IN SERVICE,
STORED FOR REUSE OR DISPOSED IN CY1985
NEVADA TEST SITE, MERCURY, NEVADA¹**

	In-Service		Stored for Reuse		Disposed	
	Number	Weight ²	Number	Weight	Number	Weight
PCB Transformers	10	9,601	7	1,177	----	----
PCB-Contaminated Transformers	48	72,804	20	21,002	----	----
PCB-Contaminated Regulators	9	5,168	----	----	----	----
PCB-Contaminated Circuit Breakers	1	476	----	----	----	----
PCB Liquids	----	----	----	----	12,495 (gallons)	42,483
PCB-Contaminated Liquids	----	----	----	----	5,775 (gallons)	19,635

Source: DOE Environmental Survey Team, 1987. Adapted from Frazier, 1986b.

- ¹ The listing of electrical equipment shown includes only that portion of the equipment that had been tested for PCB content as of December 31, 1985 (see Section 4.2.1.3 of this report).
- ² Total weight of PCBs, in kilograms

TABLE 4-14

**PCB AND PCB-CONTAMINATED EQUIPMENT IN-SERVICE
OR STORED FOR REUSE AT THE TIME OF THE ENVIRONMENTAL SURVEY
NEVADA TEST SITE, MERCURY, NEVADA¹**

	In-Service	Stored for Reuse
PCB Transformers	9	5
PCB-Contaminated Transformers	44	6
PCB-Contaminated Regulators	6	
PCB-Contaminated Circuit Breakers	1	

Source: DOE Environmental Survey Team, 1988 adapted from Frazier, 1986b.

1 This listing includes only that portion of the electrical equipment at NTS that had been tested for PCB content (see Section 4.2.1.3 of this report).

NTS has not tested all pole-, ground-, or trailer-mounted transformers and regulators at the site for PCB content. A procedure implemented by NTS requires the testing of transformers and other oil-filled electrical equipment for PCB content primarily when this equipment is removed from service for preventive maintenance (REECo, 1987b). Testing is also performed whenever a transformer or other equipment develops a leak or other problem requiring repair. However, this routine testing program was implemented only recently and, as a result, not all electrical equipment has been tested. The EPA PCB regulations stipulate that all transformers that have not been tested for PCB content must be classified as PCB-contaminated for purposes of the PCB Annual Report. NTS has not complied with this requirement, and therefore, the PCB annual reports that have been submitted are not accurate.

The operation, maintenance, and repair of transformers at NTS is divided among several groups depending upon the voltage of the transformer and other factors. All high voltage (greater than 69 kV) transformers, regardless of the location of the transformer, and associated lines are the responsibility of the electrical linemen stationed in Mercury. Intermediate voltage (4.1 to 34.5 kV) transformers are maintained by the Area 6 electrical linemen. Low voltage (less than 4.1 kV) transformers are handled by crews stationed in Areas 2, 3, and 12. In general, low voltage transformers are used to support nuclear tests. The Area 2 crew provides electrical service for events in Areas 2, 4, 8, 9, 10, and 20. Events in Areas 1, 3, 4, 6, and 7 are serviced by the Area 3 linemen, with both groups sharing responsibility for Area 19. Most of the equipment used by the Area 2 and Area 3 crews is easily transportable. For example, the Area 2 linemen are responsible for approximately 100 trailer-mounted transformers but only 15 stationary transformers. Since it is NTS policy that all portable transformers receive preventive maintenance after an event, most of these transformers have been tested for PCB content at least once; however, none of the stationary transformers under the jurisdiction of the Area 2 linemen had been tested for PCBs at the time of the Environmental Survey. Due to the nature of the nuclear tests conducted in Area 12, most transformers maintained by the Area 12 linemen are stationary.

The draining and refilling of all PCB and PCB-contaminated transformers, with the exception of the high voltage transformers under the control of Mercury linemen, is performed at the Area 6 Linemen's Shop. High voltage transformers are drained and refilled in place by the Mercury linemen. In general, transformer oil samples are collected and submitted for analysis for PCB content by the Area 6 linemen. However, the Area 2, 3, and 12 linemen also occasionally deliver oil samples from their transformers to the Area 6 facility for forwarding to the laboratory. Records on the PCB content of all NTS transformers that have been tested are maintained at the Area 6 Linemen's Shop.

The procedures used by the Area 6 linemen to drain, refill, and reclassify transformers with respect to PCB content are not consistent with the requirements of the PCB regulations [40 CFR 761.30(a)(2)(v)]. According to these standards, after a PCB or PCB-contaminated transformer is drained and refilled, it must be placed into service for a minimum of 3 months, under conditions that raise the temperature of the fluid to at least 50°C, prior to retesting the fluid for PCBs. Since it is known that PCBs can absorb to the coil of the transformer, the purpose of this procedure is to allow any such PCBs to be released into the new fluid and, thereby, provide a true measure of the PCB content of the refilled transformer prior to reclassification. However, NTS transformers are drained, refilled with PCB-free oil and only stored out-of-doors for a 3-month period prior to testing and reclassification. It is not known whether the procedure used by NTS would result in the leaching of PCBs absorbed to the coil to the same extent as that produced by in-service electrical loading. Therefore, it is possible that transformers that have been reclassified to non-PCB status by NTS may in fact become PCB or PCB-contaminated transformers after a period of in-service electrical loading. If these assumptions are correct, this situation would also affect the listing of transformers with respect to PCB content contained in the PCB Annual Report prepared by NTS.

The EPA regulations require the labeling of any equipment that contains PCBs at concentrations at or above 500 parts per million (ppm). A label specified by the regulations must be used for this purpose. No labeling of equipment containing fluids with less than 500 ppm PCBs is required by the Federal standards. The procedure adopted by NTS covering PCB-containing equipment at the site (REECo, 1987b) stipulates that once the PCB content of the equipment has been determined, it must be labeled as "PCB," "PCB-contaminated," or "Non-PCB." A specific label format is not prescribed by the NTS procedure. During the Environmental Survey, all of the transformers that had been classified as PCB transformers by NTS were inspected by the Survey team. Whereas all PCB transformers exhibited some type of designation that indicated that the transformer was a PCB transformer, not all of these transformers were labeled with the EPA-required label. According to NTS personnel, the harsh desert climate precluded the use of the adhesive type labels commonly used for this purpose, and as a result, the State of Nevada was in agreement that a more permanent marking (i.e., painted lettering) was acceptable (Haworth, 1987b). Approximately 25 percent of the 57 locations where PCB-contaminated transformers were in use or stored were also inspected by the Survey team. Inconsistent with the requirements of the NTS procedure, a PCB-contaminated transformer at Test Cell A was not labeled. In addition, during the Environmental Survey, 21 additional unlabeled transformers were observed at various locations. The records maintained at the Area 6 Linemen's Shop revealed that 18 of these transformers had been tested and classified as non-PCB by NTS; the remaining 3 had not been tested.

The inspection of PCB transformers at NTS is the responsibility of the departments in which they are used. These inspections are performed at the frequency required by the EPA regulations. NTS procedures indicate that a specific form (RE-1305: PCB Transformer Inspection) be completed during these inspections. Consistent with the requirements of the EPA regulations, records of these inspections, and records of the status of PCB and PCB-contaminated fluids under the custody of the department are maintained for a period of 3 years after disposal of these materials.

The EPA regulations and the NTS procedures require appropriate response to leaking PCB transformers within 48 hours of the discovery of a leak. During a tour of NTS transformer locations as part of the Environmental Survey, a leaking PCB transformer was discovered in Area 2 at the Plumber's Shop. When a subsequent tour of Area 2 was conducted two days later, it was observed that no action had been taken to remediate the leak. As described in Findings Nos. 1 and 2 in Section 4.2.2.2 below, in addition to the leaking PCB transformer discovered in Area 2, nine other leaking transformers were identified at NTS during the Environmental Survey. Discussions with NTS personnel regarding this situation indicated that response time for such incidents typically exceeds 48 hours.

Transformers and other electrical equipment containing PCBs that are awaiting reuse are stored at many locations at NTS. The Well 3 Yard in Area 6 is currently used only for the storage of large, high voltage transformers. In the past, smaller transformers were also stored at this location. Currently, however, intermediate and low voltage transformers are stored for reuse at several locations in Areas 2, 3, 6, 12, and 23. In Area 2, transformers (primarily transportable) are stored in the parking area next to the Area 2 Linemen's Shop, within the large storage area adjacent to Building 3228, and in the "Area 8 Storage Yard." Area 3 transformers are stored at the Drilling Equipment Storage Yard, and in Area 6, the transformer storage area is immediately adjacent to the Area 6 Linemen's Shop. In Area 12, transformers are stored in the "laydown" areas next to the tunnel entrances. A portion of the Excess Yard in Mercury is also utilized for this purpose. All of these locations are out-of-doors, and none of the transformer storage-for-reuse locations have been provided with a roof for protection from the elements, or an impervious flooring and curbing to contain spills. Facilities such as those described for transformers stored for reuse are not required by the EPA regulations, nevertheless, such precautions are regarded as good management practice.

Transformers are also stored for disposal at NTS in Area 6 at the Linemen's Shop and in Area 23 next to the holding facilities for hazardous materials and wastes. According to the Federal PCB regulations, PCB transformers and liquids stored for disposal must be stored in an area with an adequate roof and walls, and with an impervious floor and curbing to contain spills. Although no PCB fluids or transformers were stored in these areas at the time of the Environmental Survey,

according to NTS personnel, any PCB transformers or fluids awaiting disposal would be placed in these two areas. Consequently, these two storage-for-disposal areas do not comply with the EPA requirements for such facilities. The Survey team was informed that proper facilities may be constructed in FY1988 or FY1989.

The inactive Super Kukla Reactor Building in Area 27 contains an oil-filled hydraulic system. The hydraulic fluid "pit" for this system is in an area where there is electrical equipment. At the time of the Environmental Survey, the fluids that remain in the pit had not been tested for PCB content.

No disposal of PCB or PCB-contaminated equipment or fluids takes place at NTS; however, fluids containing less than 50 ppm PCBs are placed in on-site landfills. NTS arranges for the disposal of PCB and PCB-contaminated wastes with licensed facilities. NTS has current contracts with U.S. Ecology sites in Nevada, Arkansas, and Texas. None of these sites have been inspected by NTS personnel. PCB wastes are transported to the disposal site by the disposal contractors. Appropriate manifests are completed when the wastes are accepted for shipment. A certificate of destruction is forwarded to NTS by the disposal contractor when the wastes have been destroyed.

4.2.1.4 Pesticides

Pesticides (i.e., insecticides, herbicides, and rodenticides) are used at NTS and are applied only by site personnel. Insecticides are used for the control of roaches and ants at the NTS cafeterias. The EG&G facilities in Las Vegas also utilize insecticides, but since the site does not include a cafeteria, insecticides are used only in EG&G warehouses and offices. Herbicides are used at NTS to control vegetation for both security and aesthetic purposes, and rodenticides are placed in site warehouses, offices, and housing areas. As shown in the listing of pesticides that were approved by the NTS Environmental Health Department for use during FY1987 (Table 4-15), some restricted-use pesticides are used at NTS. Restricted-use pesticides are pesticides that, according to EPA, may be applied only by a certified pesticide applicator or persons directly supervised by a certified pesticide applicator. The approved list is updated periodically by the NTS Environmental Health Department.

Formal written procedures covering the storage, use, and disposal of pesticides have not been developed by NTS or EG&G. Training of all NTS personnel who use pesticides is conducted infrequently (at the time of the on-site survey, the last session had been held in March, 1985). However, two labor foremen at NTS have attended a State of Nevada pesticide course, and three individuals at NTS and one at EG&G are certified by the State of Nevada to apply (or supervise the application of) restricted-use pesticides. All other NTS personnel who apply any pesticides work under the direct supervision of these individuals.

TABLE 4-15

**PESTICIDES APPROVED FOR USE AT NTS IN FY 1987
NEVADA TEST SITE, MERCURY, NEVADA**

INSECTICIDES	
Product	EPA Registration Number
BP-100	11E40-9
Baygon 2% Bait	3125-121-2A
Baygon 70 WP	3125-146-AA
Bolt	4822-36-AA
Diazinon 4E	550-136-AA
Diazinon 4S	655-462
Diazinon 50W	100-460
Dursban L.O. (restricted-use pesticide)	464-571
Ficam D	45639-3
Ficam Plus	45639-66
Knox Out 2FM	4581-335
Max force	241-267
PT 515 Wasp Freeze	499-153
PT 565	499-182-ZB
Purge	9444-36-AA
Pyrenone Tossits	4735-2-4816
Pyrocide	1021-1177
Raid Ant & Roach Professional Strength	4822-84
Safrothin	11273-22
Sevin SL	264-335
797-A State Powdered Insecticide	1685-53-AA

TABLE 4-15
PESTICIDES APPROVED FOR USE AT NTS IN FY 1987
NEVADA TEST SITE, MERCURY, NEVADA
PAGE TWO

HERBICIDES	
Product	EPA Registration Number
Aquathol Plus	4581-83-AA
Diquat	239-1663-AA
Hydrothol 191	4581-174
Princep Caliber 90	100-603
Round-Up	524-308-AA
Spike 80W	1471-97-AA

RODENTICIDES	
Product	EPA Registration Number
Sewer Rat Bait Blocks	56-20
Talon-G (restricted-use pesticide)	10182-41
ZP Rodent Bait (restricted-use pesticide)	12455-18-AA

MISCELLANEOUS	
Product	EPA Registration Number
Avitrol 200 (restricted-use pesticide)	11649-7
Roost No More	7765-4-AA
Wilco Ground Squirrel Bait	36029-CA-1

Source: DOE Environmental Survey Team, 1988.

- 1 A restricted-use pesticide is a pesticide that according to EPA regulations, may be used only by a certified pesticide applicator or persons directly supervised by a certified pesticide applicator.

Personnel who apply pesticides are required to record data pertaining to each application (i.e., date, identity, and amount of pesticide applied; location treated; etc.). These records are maintained for at least a two-year period. Table 4-16 is a summary of pesticide usage at NTS during FY1986 that was derived from these records. This listing does not include any pesticides applied using spray cans available in retail stores.

A 3- to 6-month supply of the pesticides used at NTS is stored in a small, locked building in Mercury near the hazardous material and waste holding area. This location was inspected during the Environmental Survey, and was found to be in an orderly condition, with no evidence of leaks or spills. Pesticides are mixed prior to application in an area immediately adjacent to the building used to store pesticides. All empty pesticide containers, except bags, are rinsed three times and the rinse water is used to dilute the pesticide for application. Empty, rinsed pesticide containers are disposed at the Area 23 landfill.

4.2.1.5 Asbestos

The NTS Industrial Hygiene Section oversees the management of asbestos-containing materials at NTS. Any tasks requiring the actual handling of asbestos are performed by a specially-trained group of asbestos insulators stationed in Area 6. On the average, approximately two asbestos projects per year have been conducted during the last five years. None of these projects have involved amounts of asbestos that would trigger the requirements of the National Emission Standard for Hazardous Air Pollutants (NESHAPS) for asbestos, (i.e., greater than 160 square feet of surfacing materials or greater than 260 linear feet of pipe insulation).

Since most of the facilities at NTS were constructed in the 1940s and 1950s it is likely that many of the buildings contain asbestos. At the time of the Environmental Survey, NTS was compiling an inventory of the location and amount of asbestos in on-site buildings. This listing, which was reported to be 75 percent complete, was being derived from a review of "as built" drawings. Formal procedures covering asbestos abatement activities have not been developed by NTS. However, no asbestos abatement projects of a magnitude that would be subject to the NESHAPS requirements are planned.

Any asbestos wastes generated at NTS are disposed at the Area 10 or Area 23 landfills. No off-site disposal of asbestos waste has occurred. According to NTS personnel, all asbestos wastes deposited at the landfills are double-bagged, and covered with at least six inches of asbestos-free material within 24 hours. Asbestos wastes are buried with the trash and are not confined to a separate area of the landfill as recommended by EPA.

TABLE 4-16

**PESTICIDE USAGE DURING 1986
NEVADA TEST SITE, MERCURY, NEVADA**

Pesticide	Target	No. of Applications	Application Rate	Total Amount
Dursban L. O.	roaches/ants	4	0.5 percent	32 oz.
Diazinor, 4E	roaches/ants	2	0.5 percent	16 oz.
Knox Out 2FM	roaches/ants	1	1 percent	16 oz.
Ficam	roaches/ants	2	1 percent	32 oz.
Safrothin	roaches/ants	2	0.25 percent	8 oz.
Sevin SL	roaches/ants	1	1 percent	16 oz.
Oust	weeds	6	5 oz./acre	100 oz.
Spike 80W	weeds	1	2 lbs./100 gal. water	10 lbs.
Round-Up	weeds	1	1 gal./100 gal. water	8 gal.
Princep	weeds	5	45 lbs./acre	310 lbs.
Diquat	weeds	4	3 gal./acre	8 gal.
ZP Rodent Bait	rats/mice	9	1 teaspoon every 15 feet	287 locations treated
Talon-G	rats/mice	8	1/2 oz. every 10 feet	244 locations treated

Source: DOE Environmental Survey Team, 1988.

4.2.1.6 Chlorofluoroalkanes

Approximately 28,000 pounds of chlorofluoroalkanes were used at NTS in FY1986 (see Table 4-17). As a group, the chlorofluoroalkanes are relatively volatile compounds, and potential environmental problems due to vapor emissions can result if they are not properly handled and stored. Over 90 percent of the chlorofluoroalkanes purchased were CFC-12 and CFC-22. These materials are used primarily to recharge air conditioning units; over 2,800 units are in vehicles with an additional 2,400 units in buildings. Both CFC-12 and CFC-22 are gases at room temperature; and therefore, are purchased in 30-, 125- or 145-pound gas cylinders. These CFC cylinders are stored either indoors, or in a covered shelter outdoors at Warehouse E in Mercury until needed. Although, as described in Section 4.2.1.1, some deficiencies regarding the storage of other hazardous materials at Warehouse E were noted during the Environmental Survey, chlorofluoroalkanes appeared to be stored properly at NTS.

4.2.2 Findings and Observations

4.2.2.1 Category I

None.

4.2.2.2 Category II

1. Leaking PCB Transformers. PCBs are being released to the environment from leaking transformers at several locations at NTS.

Soil contamination with PCBs can occur when leaks of fluids from PCB and PCB-contaminated equipment are not repaired. From June 22 to June 24, the 14 PCB transformers (> 500 ppm) at NTS were inspected by the Survey team. In addition, approximately 25 percent of the 57 locations where PCB-contaminated transformers (50 to 500 ppm) were in use were visited. One PCB transformer and 3 PCB-contaminated transformers were found to be leaking. According to the EPA PCB regulations (40 CFR 761.3), a leak is "... any instance in which a PCB article, PCB container or PCB equipment has any PCBs on any portion of its external surface."

The location of the transformers known to contain PCBs that were observed to be leaking during the Environmental Survey is as follows:

TABLE 4-17

CHLOROFLUOROALKANE USAGE AT NTS IN FY 1986
NEVADA TEST SITE, MERCURY, NEVADA

Chlorofluorocarbon	Amount Used FY 1986 (lbs.)
CFC-11	1,400
CFC-12	16,125
CFC-22	9,750
CFC-113	635
CFC-115	150
	28,060

Source: DOE Environmental Survey Team, 1988. Adapted
from Frazier, 1987c.

Location	PCB Content	Comments
Area 2 Plumber's Shop	PCB	PCBs on external surface
Substation 25-2 (Area 25)	PCB-contaminated	PCBs on external surface
Substation 25-8 (Area 25)	PCB-contaminated	PCBs on external surface
Test Cell A (Area 25)	PCB-contaminated	PCBs on external surface

2. Leaking Transformers That May Contain PCBs. PCBs are potentially being released to the environment from leaking transformers at several locations at NTS.

Localized soil contamination with PCBs can occur when leaks of fluids from transformers that contain PCBs are not repaired. From June 22 to June 24, many of the transformers at NTS were inspected by the Survey team. A transformer stored for reuse in Jackass substation was leaking when it was inspected; the PCB content of this transformer was unknown. Five other transformers that were labeled non-PCB were also found to be leaking. According to the EPA PCB regulations (40 CFR 761.3), a leak is "any instance in which a PCB article, PCB container or PCB equipment has any PCBs on any portion of its external surface."

The location of the transformers that may potentially contain PCBs that were observed to be leaking during the Environmental Survey is as follows:

Location	PCB Content	Comments
Jackass Substation	Unknown	Oil on external surface
Well 3 Yard (3 Transformers)	Non-PCB	Oil on external surfaces and the surrounding soil
Substation 19-9	Non-PCB	Oil on external surface
Area 23 Excess Yard	Non-PCB	Oils on external surface and the surrounding soil

The leaking non-PCB transformers have been included in this list because the procedure used by NTS to reclassify transformers to non-PCB status is not in strict adherence with EPA requirements, and, if these transformers were reclassified using the NTS procedure, they may still contain regulated levels of PCBs. EPA regulations [40 CFR 761.30(a)(2)(v)] stipulate that, after a PCB or PCB-contaminated transformer is drained and refilled, it is to be placed in service for a 3-month period under conditions that raise the temperature of the dielectric fluid to at least 50°C, prior to sampling the transformer to determine the post-drain PCB concentration. Currently, NTS transformers are drained, refilled with PCB-free oil, and stored

for 3 months. The amount of PCBs leached from the transformer coil using the NTS procedure may not equal that resulting from the EPA-required method; and therefore, the actual PCB concentration in NTS transformers after being returned to service may be higher than indicated by the sampling results. According to this scenario, some of the transformers that have been classified non-PCB using the NTS procedure, including the leaking non-PCB transformers identified above, may still actually be PCB or PCB-contaminated transformers.

3. Soil Contamination by Hazardous Chemicals. Oils, fuels, and other hazardous chemicals are being released to the environment at several locations at NTS.

The locations where soil contamination was found to be occurring as a result of releases of oils, fuels, and other hazardous chemicals to the environment are as follows:

- Barrel racks with drip trays that empty onto the ground in Areas 2, 3, 6, 12, and 23. These racks are used to store 55-gallon drums of solvents, oils, and lubricants.
- Approximately fifty 50-pound bags of chromium-containing mud additives were stored out-of-doors at the Area 3 mud plant. At least five of these bags were badly damaged and releasing their contents to the environment.
- Two open drums containing unknown residuals that appeared to have overflowed in the past at the Area 12 fleet operations building.
- Two leaking drums of oily liquids at Test Cell C in Area 25.
- Leaking drain valve on an above-ground storage tank used to store diesel for the emergency generator for CP-9 (Area 6).
- Extensively-stained soils near the USTs used to store asphalts and binders at Building 6-162 (Area 6).
- A transportable tank leaking asphalt that was stored at Building 6-221 (Area 6).
- Surface-soil contamination presumably resulting from improper filling practices at the waste oil UST for Building 12-16 and the UST for the boiler for Building 6-607 (Area 6).

4.2.2.3 Category III

1. Underground Storage Tanks. Underground storage tanks (USTs) at several locations at NTS have the potential for undetected releases of hazardous liquids to the environment.

Subsurface soils underlying the underground storage tanks may be contaminated with the fuels, waste oils, and other hazardous materials stored in these tanks. An analysis of the listing of 64 underground storage tanks at NTS that was provided to the State of Nevada in 1986 indicates that 49 of these 64 USTs are constructed of steel and have been in the ground for periods ranging from 15 to 35 years, and only 15 of these are known to have been provided with any type of corrosion protection. Twenty-four of the USTs have or had capacities of at least 10,000 gallons (Table 4-8).

During the Environmental Survey, 19 additional USTs used to store fuels and other materials were identified in Areas 7, 18, 23, 25, and 27 (Table 4-10). The age, capacity, and construction of these tanks is unknown, but it is likely that the majority are also more than 15 years old and made of steel. At least 20 additional small (less than 1,000 gallon capacity) USTs that provide fuel storage for boilers used to heat various buildings (and therefore are not reportable) are also known to be in service at NTS. For the most part, these small tanks are made of steel and have been in use for more than 15 years.

It is generally accepted in the engineering and regulatory communities that steel USTs lacking corrosion protection that have been in use for more than 15 years have a relatively high probability of leaking. USTs at NTS under the control of some departments are routinely assessed for leaks by comparing daily input and output volumes (i.e., inventory control). Additionally, due to the dry desert climate at NTS, the rate of corrosion, deterioration, and subsequent leakage is presumably low relative to nondesert locations receiving more rainfall. Nevertheless, none of the USTs at NTS have been pressure-tested for leaking, and no environmental samples have been collected adjacent to the tanks and analyzed for this purpose. Such requirements have been included in the proposed EPA regulations for USTs. Sampling and analysis of a representative fraction of the oldest of these USTs is being conducted under the Environmental Survey.

2. Potential Release of PCBs to the Environment Due to Inadequate Storage Facilities for PCB Fluids and Equipment. Soils at the various facilities at NTS used to store PCB fluids and equipment may be contaminated with PCBs since these facilities are not adequate to prevent spills of PCB and PCB-contaminated fluids from being released to the environment.

The PCB storage-for-disposal facility in Mercury consists of an area approximately 30 feet by 50 feet in size. The area does not have a roof, impervious flooring, or curbing. A layer of gravel has been placed on the desert floor, and containers of PCB fluids, and PCB equipment are stored directly on the gravel. A similar but smaller area is used as a PCB storage-for-disposal area in Area 6 (at the Linemen's Shop). Facilities such as those used at NTS to store PCBs consigned for disposal do not comply with the construction standards set forth in the EPA PCB regulations (40 CFR 761.65). Specifically, PCB transformers and liquids stored for disposal must be equipped with an adequate roof and walls, and an impervious floor and curbing to contain spills. Any leakage of PCB fluids from PCB containers and PCB equipment stored in these areas would potentially result in soil contamination. The storage-for-disposal facility at the Linemen's Shop in Area 6 has been in use for approximately 6 years, whereas the Mercury facility has been used to store PCBs prior to disposal since the site began operation.

Facilities used to store PCBs for reuse are not regulated by the EPA. Hence, the facilities used by NTS to store PCB and PCB-contaminated transformers prior to reuse are not subject to the same requirements imposed on PCB storage-for-disposal facilities. Nevertheless, since the storage-for-reuse facilities at NTS are quite similar to the storage-for-disposal facilities (i.e., a sand/gravel floor, no roof, no containment curbing), it is reasonable to expect that leaks from any PCB fluid containers or PCB equipment stored in these areas would also result in a release of PCBs to the environment with some localized soil contamination. PCB storage-for-reuse facilities at NTS are located in the Area 2 support complex, Area 3 support complex, Area 6 (Linemen's Shop and Well 3 Yard), and the Excess Yard in Mercury. Of these, the Well 3 Yard in Area 6 has been used for the longest period of time. Site personnel reported that the Well 3 Yard has been used to store PCB transformers, in particular the largest transformers, since the 1950s. In the past, the Well 3 Yard was also used to store PCBs awaiting disposal. By comparison, although the Area 2 and 3 locations have been in use since operations began in these areas, only relatively small transformers have been stored in these facilities. The Area 6 Linemen's Shop and Excess Yard facilities have been in use for less than 10 years.

As described in Finding No. 2 in Section 4.2.2.2, during the Environmental Survey, three transformers that were labeled non-PCB and located in the Well 3 Yard were observed to be leaking. Due to the long history of use of the Well 3 Yard for transformer storage, it is possible that other leaks have occurred. However, no sampling and analysis of soils for PCBs from any of the transformer storage areas has been conducted to confirm the presence of any contamination. Since the Well 3 Yard has been used for the longest period of time to store the

largest transformers, sampling and analysis for PCBs in soils at the Well 3 Yard will be performed as part of the Environmental Survey.

3. Potential Release of Hazardous Materials From Inadequate Storage Facilities. Several facilities at NTS and EG&G in Las Vegas are not adequate to prevent spills of hazardous materials from being released to the environment. The reason or reasons why a particular location or facility was regarded as inadequate differs but include lack of secondary containment, ineffective secondary containment, co-storage of incompatible materials, and overcrowding of the facility (see below).

The locations and facilities where improper storage of hazardous materials could result in releases to the environment include

- Chemical storage shed behind the A-1 complex at EG&G Las Vegas. This facility is overcrowded, and incompatible hazardous materials were not segregated or stored in an orderly manner. At the time of the Environmental Survey, new containers of various solvents, oils, and inorganic acids, and waste organic acid containers were stored outside the shed on wooden pallets or directly on the ground. In the event of a spill or rupture of these containers, the materials would contaminate surrounding soils. Inside the shed, incompatible materials, such as organic acids and bases or oxidizers were stored together. The shed does not have an impervious floor and is not diked. In the event of a spill or rupture of the materials inside the shed, a violent reaction could occur and/or materials could be released into the nearby storm drain.
- Storage of 55-gallon drums of highly flammable solvents outside, exposed to the sun, on gravel surfaces lacking secondary containment at Warehouse E (Area 23). The number of such drums stored outside at Warehouse E varies with the current inventory but typically ranges between 10 and 100 drums.
- Storage of concentrated hydroxide solutions in the Acid Storage Room in Warehouse R (Area 23). The uncontrolled intermixing of acids and bases can result in a violent reaction.
- Lack of curbing to contain spills at the concrete pad adjacent to Warehouse H at the Yucca Lake complex in Area 6 that is used to store approximately two hundred 55-gallon drums of various lubricants and oils.

- Lack of secondary containment for above-ground storage tanks at the following locations (see Table 4-11 for inventory):

- Area 2 Mud Plant
- Area 3 Batch Plant (2 tanks)
- Building 6-621
- Building 6-624 (2 tanks)
- Building CP-9
- Well 3 Yard
- Crater U9y
- Engine Test Stand No. 1 (3 tanks)
- Test Cell C
- EG&G Las Vegas (2 tanks)

- Earthen containment dikes for above-ground storage tanks. Although not required by state or Federal regulations, secondary containment dikes that are constructed of impervious materials such as concrete or compacted clay will more effectively contain leaks and spills than the dikes made from sandy soil used by NTS. The above-ground storage tanks at NTS that have been provided with an earthen containment dike are as follows:

- Area 1 Shaker Plant diesel tank
- Yucca Lake bulk storage tanks
- Bulk storage tanks in Mercury

Because of the lack of containment or effective containment, any spill or leak from the above facilities can be released to the environment. The potential hazard associated with these facilities depends on the toxicity of the materials stored, the location of the facilities with respect to receptors and the condition of the above-ground tanks and drums.

4.2.2.4 Category IV

1. Noncompliance with PCB Program Requirements. The NTS PCB program does not comply with several requirements of the EPA regulations.

A review of the NTS PCB program during the Environmental Survey revealed four instances of noncompliance with the EPA regulations:

- The procedure being used by NTS to reclassify PCB and PCB-contaminated transformers to non-PCB status is not consistent with the method established by the PCB regulations (40 CFR 761.30 (a)(2)(V)). The regulation requires a minimum of 3 months of in-service use subsequent to the last servicing conducted for the purpose of reclassifying the transformer. In-service use is defined as used electrically under loaded conditions that raise the temperature of the fluid to at least 50°C. In contrast, NTS transformers are drained, refilled with PCB-free oil, and stored out-of-doors for 3 months prior to sampling.
- The NTS storage for disposal facilities do not meet the requirements of the standard (40 CFR 761.65). According to the regulation, storage for disposal facilities must have a roof which prevents rain from reaching the stored PCBs and PCB items, a smooth and impervious floor with a six-inch high curb that provides a containment volume which is the greater of twice the volume of the largest PCB item stored therein or 25 percent of the total volume of all containers and equipment, and constructed without drains or other openings. The NTS storage-for-disposal facilities consist of unprotected, out-of-door locations where containers of PCB fluids and PCB equipment are placed directly on the desert floor that has been covered with a layer of gravel (see Section 4.2.2.3, Finding No. 2).
- NTS does not respond to PCB leaks within 48 hours as specified by the regulation (40 CFR 761.30 (a)(1)(x)). During an inspection of PCB transformers during the Environmental Survey, a leaking PCB transformer was discovered by the Survey team in Area 2 at the Plumber's Shop. Two days later, during a related inspection tour, it was observed that the leak had not been repaired. Discussions with NTS personnel regarding response to transformer leaks revealed that response time typically exceeds 48 hours.
- The PCB Annual Report prepared by NTS appears to be incomplete. The EPA regulations require owners or operators of facilities where PCB transformers are used or stored to prepare an annual document which lists, along with other information, the quantities of PCBs and PCB items at the facility (40 CFR 761.180 (a)). In this regard, NTS has not tested all transformers for PCB content. Secondly, the procedures used to reclassify transformers are substandard. Therefore, it is possible that some PCB transformers may be present at NTS which have not been included in the Annual Report. Furthermore, the regulations state that all oil-filled transformers that have not been tested must be assumed to be PCB-contaminated (40 CFR 761.3). NTS has not assigned this designation to transformers that

have not been tested. As a result, the list of PCB-contaminated transformers in the Annual Report is incomplete.

2. Inaccurate Underground Storage Tank Report. The listing of underground storage tanks submitted to the State of Nevada by NTS is incomplete.

Section 9002 of the Resource Conservation and Recovery Act (RCRA) requires the owners of underground storage tanks (USTs) that were used to store waste and non-waste toxic and chemical materials after January 1, 1974 to submit a listing of such tanks to their respective states. In response to this requirement, NTS forwarded an inventory of USTs to the State of Nevada. However, during the Environmental Survey, the Survey team uncovered information which indicated the presence of 19 additional USTs at NTS that had not been previously identified by NTS (see Table 4-10). At least six (and perhaps as many as ten) of these USTs are reportable under RCRA.

PRELIMINARY

4.3 Radiation

4.3.1 Background Environmental Information

The background radiation in the vicinity of the Nevada Test Site is a consequence of both natural and man-made sources. These sources include cosmic radiation, natural radioactive materials in the soil and building materials, fallout from past world-wide atmospheric weapons detonations, and releases of radioactive materials from nuclear power plants and other facilities handling radioactive materials. Radiation doses to individuals may result from direct exposure to radiation from these sources and the intake of radioactive materials in food, drinking water, and air. The most significant exposure is that to the lungs from background levels of radon. The annual average effective dose equivalent for natural background in the United States is approximately 190 mrem/yr (FR, 1986); this dose is detailed in Table 4-18. About one-half of the dose equivalent is attributable to the inhalation of radon-222 and its decay products and the other half is direct exposure, primarily gamma radiation. The EPA reports the direct gamma radiation exposure rates for communities throughout the United States on a quarterly basis. During the period January-March, 1987, EPA reported measured gamma exposure rates that were equivalent to annual doses of between a high of 140 ± 10 mrem (exposure rate of $16 \mu\text{R/hr}$ [microroentgen/hr]) in Santa Fe, New Mexico, and a low of 56 ± 7 mrem (exposure rate of $6 \mu\text{R/hr}$) in Berkeley, California (EPA, 1987a).

Activities at the Nevada Test Site can contribute to radiation levels in the vicinity. Because of the random nature of radioactive decay and the numerous contributors to background, it is not possible to predict the exact background radiation in an area. In addition, gross-radiation measurement techniques do not allow accurate differentiation between background radiation and contributions from a localized source such as a nuclear facility. To determine whether NTS activities are contributing to the radiation levels in the vicinity, it is necessary to estimate the radiation level attributable to background sources. One approach to this is to measure the background at a location that is nearby, but sufficiently removed from the test site so that contributions from its sources would be below the detection limit for the measurement technique. Radiation levels measured at such a location may be considered to be an estimated background for the site. For the NTS, because of the distant location, radiation levels at Las Vegas, Nevada can be considered to be background and free of NTS contributions. The annual dose for Las Vegas, Nevada, based on the EPA monitoring data for the period January-March 1987, was 74 ± 5 mrem (exposure rate of $8.5 \mu\text{R/hr}$) (EPA, 1987a). The average dose, for the same time period, of 21 locations monitored throughout the United States by the EPA was 90 mrem, with a standard deviation of 24 mrem.

TABLE 4-18

AVERAGE U.S. ANNUAL EFFECTIVE DOSE EQUIVALENT TO
HUMANS FROM NATURAL BACKGROUND RADIATION

Organ	Annual Effective Dose Equivalent (mrem)
Gonads	24
Breast	14
Lung (Total)	100
Red Bone Marrow	10
Bone Surfaces	6
Thyroid	3
Other	29
Total	189

SOURCE: FR, 1986.

As part of its Annual Environmental Monitoring Report, the NTS is required to provide an assessment of the potential site contribution to the public radiation dose (Stern, 1986). In 1985, the Department of Energy (DOE) adopted an interim environmental radiation protection standard to be implemented in calendar year 1985 (Vaughan, 1985). It is DOE policy to follow the guidance of the National Council on Radiation Protection and Measurements (NCRP) to the extent practicable with respect to radiation protection standards. A comprehensive revision of previous NCRP recommendations on a basic radiation protection system is still under development. However, current NCRP guidance is available regarding protection of the public in its September 18, 1984 advice to the Environmental Protection Agency published under the title "Control of Air Emissions of Radionuclides." In this document, the NCRP endorses the recommendation of the International Commission on Radiological Protection (ICRP) to limit the continuous exposure of any member of the public from other than medical sources and natural background to 100 mrem per year whole body dose-equivalent. The previously recommended limit of 500 mrem per year is retained for non-continuous exposures. These recommendations are now adopted as interim standards for DOE environmental activities for all exposure pathways.

40 CFR 61.93 states that dose equivalent to members of the general public shall be calculated using EPA models AIRDOS-EPA and RADISK, or other procedures, including those based on environmental measurements, that EPA has determined to be suitable. DOE has adopted the requirements of 40 CFR 61.93.

4.3.2 General Description of Pollution Sources/Controls

The Nevada Test Site can contribute to the radiation dose of members of the general public through exposure to external gamma radiation, inhalation of contaminated airborne particulates, immersion in a cloud of radioactive gases, and ingestion of contaminated foodstuffs and water. The sources of radioactive materials that might lead to the latter three are discussed in the media-specific discussions of Section 3.0 (i.e., Air 3.1, Soil 3.2, Surface Water 3.3, and Groundwater 3.4). Each of these media can provide a pathway for the exposure of individuals to radiation. External gamma exposure could result from radioactive materials released through seeps, vents, and tunnel purging during or following nuclear tests; gamma emitting radionuclides stored or disposed of at the NTS; gamma-emitting materials released from past activities and deposited on on-site or off-site properties; contaminated facilities; and radiation generating equipment.

Prior to 1963, nuclear tests (both U.S. and foreign) were conducted above ground, a practice that resulted in release of large quantities of radioactive debris into the environment. Much of this material was driven into the upper atmosphere by the force of the explosions and later deposited on

the surface of earth as nuclear weapons fallout. Because much of this material has radioactive half-lives of tens to thousands of years, there remains a global inventory of radioactive fallout. The pre-1963 atmospheric weapons testing program at the NTS contributed to the fallout inventory. The Environmental Survey team did not address the issue of the NTS contributions to global fallout and it will not be discussed in this report.

The primary potential source for the release of radioactive materials from the NTS is the weapons testing program. Such releases are controlled by conducting tests in deep underground cavities or tunnels and applying various containment strategies that are designed to minimize the release risk. Containment techniques are discussed in Section 3.1.2. Test related releases are referred to as vents or seeps. Venting is a dynamic release of material through cracks or fissures in the ground, while seepage is a slow leaking of gases through tiny channels leading from the weapons test cavities or chimneys to the ground surface. While vents have occurred since the initiation of underground testing, there have been none since the BANE BERRY event in December 1970. In addition, there have been only two seeps since 1970; these were associated with the DIAGONAL LINE (1971) and RIOLA (1980) events. Radioactive noble gases were detected off-site as a consequence of both of these seeps, but the elevated activity levels persisted only for a few days and were less than 1 percent of the levels acceptable for continuous exposure of members of the public (EMSL, 1984).

Although containment during tests has been very effective since 1971, tests are conducted only if it may be concluded that allowable exposure levels will not be exceeded in any populated region, even if a massive vent should occur. Tests are conducted only when the wind direction and conditions are such that radioactive releases would not be likely to impact areas designated as uncontrollable. Uncontrollable areas are those where it is not considered feasible to assure that protective action (e.g., evacuation, keeping people indoors, or controlling access to the areas) can be taken to mitigate the effects of a release. Prior to a test, predictions are made of the fallout dispersion patterns and the maximum radiation exposure that might occur in the event of a massive venting. The test is not conducted unless exposures in both controlled and uncontrolled areas are within the dose limits of 170 mrem/yr (uncontrolled population) and 500 mrem/yr (controlled population) established by DOE for nuclear weapons testing (EMSL, 1984).

Other activities associated with underground testing that may result in the airborne release of radioactive materials include drill-back operations and tunnel purging. Following an underground nuclear detonation, a diagonal shaft may be drilled into the shot cavity or chimney to allow sampling of the debris. Steps are taken to minimize the release of radioactivity (see the discussion in Section 3.1.2) but radioactive noble gases may be released. Following a tunnel test, it is necessary to enter the tunnel to retrieve the test instrumentation. In the event of a partial containment failure,

radioactive gases will be present in the instrumentation chambers, and they must be purged prior to entry. These gases are vented to the atmosphere. The gases released in these operations are monitored and reported to EPA-EMSL (see, for example, Patzer et al., 1987) for conducting radiation dose assessments. The reported releases for the period 1982 through 1984 are presented in Table 4-19. The dose assessments are discussed in Section 4.3.3.

The radioactive waste management sites located in Areas 3 and 5 may be considered potential sources for off-site direct radiation. Because of the large accumulation of radioactive wastes, the radiation levels at these locations are typically above background, ranging (for 1985) from a low of 100 mrem/yr at the Area 5 location to a high of 259 mrem/yr at the Area 3 location (Gonzalez, 1986). The principal means of controlling exposure from the areas are maintaining access control and covering the waste materials with a soil overburden as the disposal sites are filled. Because of the shielding properties of the soil overburden and the large distances between the waste management sites and off-site residences, these sources do not contribute measurably to the radiation exposure of members of the general public. The handling of radioactive wastes at NTS is discussed in Section 4.1. In addition to active waste management sites, there are a number of inactive contaminated waste dumps (CWD) in the NTS. These are discussed in Section 4.5.2.3.

Radioactive materials and radiation generating equipment are located in various buildings within the NTS. The contributions of these facilities to the radiation levels within the boundaries of the NTS are measured by the on-site radiation monitoring network described in Section 4.3.3.1. In 1985, the monitoring network detected radiation levels above background near the Building 610 x-ray room in Area 23 (547 mrem/yr), the Building 650 sample storage room in Area 23 (628 mrem/yr), and the CP-50 calibration area in Area 6 (146 mrem/yr). Access to these areas is controlled to limit radiation exposures to individuals. The distances between these facilities and off-site residences limit their contributions to the radiation dose of members of the public to below measurable levels.

Atmospheric nuclear tests (e.g., nuclear detonations, safety experiments, nuclear rocket-engine testing, and hydrodynamics experiments), that were conducted prior to 1964, have resulted in radioactive contamination of soils in many areas within the boundaries of the NTS and on the Nellis Air Force Range. The contaminated areas are recognized by NTS personnel, and have been posted with warning signs, as appropriate. Access to the posted areas, without approval from the Radsafe Department, is prohibited. Soil contamination is discussed in more detail in Section 3.2.2 and 3.2.3.

Leach fields have been used at the NTS for the disposal of liquid radioactive wastes from laboratories and decontamination facilities. Long-lived gamma-emitting radionuclides present in the wastes are adsorbed onto the leach field medium and will remain as a potential source of external radiation.

TABLE 4-19

**REPORTED RADIONUCLIDE RELEASES FROM THE NTS 1982-1986, IN CURIES
NEVADA TEST SITE, MERCURY, NEVADA**

	1982	1983	1984	1985	1986
Tritium	165	98.2	197	116	120.7
Argon-37	-	-	9.6	9.0	-
Krypton-83m	-	-	21.3	-	-
Krypton-85m	-	-	34	-	-
Krypton-85	-	-	-	17.0	4.3
Krypton-87	-	-	0.8	-	-
Iodine-131	1×10^{-4}	1×10^{-5}	-	7×10^{-3}	2.4
Iodine-133	-	-	-	4.2×10^{-2}	-
Iodine-135	-	3×10^{-5}	-	4.2×10^{-2}	-
Xenon-133	74	26.6	160	734.9	36,000
Xenon-133m	2.5	1.5	8.5	8.3	0.058
Xenon-135	4.2	28.9	1,297	28.9	0.041
Xenon-135m	-	-	156	-	-

Source: Adapted from Black et al., 1983; Patzer et al., 1984; Potter et al., 1985; Grossman et al., 1986; Patzer et al., 1987.

Access to the leach field areas is controlled to limit the radiation exposure of NTS personnel. Because of the shielding properties of the soil covering the leach fields and the distances between the leach fields and off-site residences, these sources will not contribute measurably to the radiation exposure of individuals in off-site locations. Inactive leach fields are further discussed in Section 4.5.2.7 and 3.2.3.3. The only active radioactive waste leach field is associated with the Building 650 in Area 23; this leach field is discussed in Section 4.1.2.1.2.

There are a number of areas within the NTS where there are currently inactive buildings or equipment contaminated with radioactive materials in excess of NRC (NRC Regulatory Guide 1.86) and DOE (Barber, 1985) guidance for the unrestricted release of contaminated property. Access and use of these facilities are controlled by NTS to limit exposure to site personnel. Because of the shielding effect of buildings and the distances between the contaminated locations and off-site residences, these facilities do not contribute measurably to the radiation exposure of members of the general public. Contaminated buildings and equipment has been observed by members of the Environmental Survey team at the following locations within four NTS project areas:

- Area 25 (See Section 4.5.2.8)

- Storage areas within the E-MAD building.
- E-MAD building "hot" bay.
- E-MAD decontamination pad.
- Two outside equipment storage areas at the E-MAD complex.
- ETS-1, one small area on a metal shield with a maximum-observed-fixed-radiation-level of approximately 300 microR/hour.
- Piping and valves at Test Cell C.
- Test Cell C building.
- Two 600-gallon contaminated storage tanks near Test Cell C.
- Contaminated storage tanks (approximately 150,000 to 200,000 gallons capacity) near Test Cell C.
- Test Cell A building.
- Test Cell A equipment test laboratory.
- R-MAD "hot" bay.
- 25-CWD-3, radioactive materials storage area.

- Area 15 (See Section 4.5.2.13)
 - EPA Farm, laboratory building
 - EPA Farm, contaminated storage tank
- Area 27
 - Super Kukla reactor building
- Area 26
 - Tory reactor building
 - Disassembly building
 - Disassembly building contaminated storage tank

The locations listed above are known by NTS personnel to be contaminated. The areas are posted with warning signs and access is limited. The above list is not intended to represent a complete inventory of contaminated facilities, only those directly observed by the Survey team. There is no NTS-wide comprehensive listing of contaminated areas and facilities. However, the representative of the Radsafe Department responsible for each area maintains a listing of such locations and conducts routine radiological surveys (Shugart, 1987).

4.3.3 Environmental Monitoring Program

The on-site radiological monitoring program is administered by NTS personnel while USEPA's Environmental Monitoring Systems Laboratory (EPA-EMSL) conducts off-site radiological monitoring. This section of the report discusses on-site as well as off-site external gamma monitoring and dose assessments.

4.3.3.1 External Gamma Radiation Monitoring

Thermoluminescent dosimeters (TLD) are used to measure the external gamma radiation at locations both on and off the Nevada Test Site. In 1985, 163 TLD stations were located within the boundaries of the NTS, and 129 stations were maintained off-site at both inhabited and uninhabited locations within a 500-kilometer radius of the NTS Control Point 1 (located in Area 6).

The station locations for the on-site monitoring network were selected to serve three functions: (1) to provide a low-level exposure control-type network (i.e., a network to monitor radiation levels in locations not expected to exhibit levels above background); (2) to measure radiation levels resulting from residual activity from the atmospheric testing program; and (3) to monitor radiological conditions at locations used as radioactive waste management sites. TLDs are exchanged on a quarterly basis. Nine of the 163 locations are designated as control stations. For 1985 the observed average annual dose rates at the control stations ranged from a low of 44 to a high of 106 mrem/yr. These values are comparable to the average background gamma radiation dose of 100 mrem/yr for the United States. Of the remaining 154 dosimeters the highest average dose rates were observed at three locations: 1,817 mrem/yr at a location on Road 4-04 in Area 4; 1,746 mrem/yr at a location on Road 2-04 in Area 2 and; 1,124 mrem/yr at a location near event hole U3co in Area 3. These stations are all located near ground zero for past atmospheric nuclear tests, areas of known contamination (Gonzalez, 1986). Contaminated surface soil is discussed in Section 3.2.

At the Radioactive Waste Management Site (RWMS) in Area 5, radiation levels were measured at 16 locations in 1985. The observed dose rates varied from a low of 100 to a high of 120 mrem/yr. Observed dose rates for the four U3ax stations at the Area 3 RWMS ranged from a low of 131 to a high of 259 mrem/yr. For the remaining 134 locations, radiation levels varied from a low of 48 mrem/yr to a high of 660 mrem/yr (Gonzalez, 1986).

All of the stations that have dose rates that exceed the range of typical background values are located in areas that are used for the storage, disposal, or handling of radioactive materials; operations of radiation generating equipment (e.g., x-ray area of Building 610 in Area 23); or areas known to be contaminated from atmospheric testing.

The off-site TLD monitoring network is designed to measure environmental radiation at specific locations rather than monitoring individuals because there are many uncertainties related to personnel monitoring. However, individuals at selected locations have been monitored so that correlations between personnel and environmental monitoring could be studied. In 1986, the off-site network consisted of 129 environmental TLD stations at both inhabited and uninhabited locations within a 500 kilometer (311 mile) radius of NTS Control Point 1 (CP-1). Within the area covered by these stations, 53 off-site residents were provided with personal dosimeters during 1986. The locations of the off-site environmental TLD stations are shown in Figure 4-8 (Patzner et al., 1987).

Environmental TLDs are exchanged quarterly and personnel TLDs are exchanged monthly. The TLDs used are fabricated of crystal "chips" of dysprosium-activated calcium fluoride. Each TLD contains

FIGURE 4-8

LOCATIONS OF OFF-SITE TLD MONITORING STATIONS
NEVADA TEST SITE - MERCURY, NV

two "chips" and three TLDs are placed at each of the fixed stations. The off-site residents were each issued a single dosimeter containing two "chips." The radiation readings for each of the six "chips" at a location were averaged and the average values for each station compared with those obtained at that location for the previous four quarters to determine whether there had been a statistically significant increase in radiation levels. The results for the personnel dosimeters were compared with the average values measured at the nearest corresponding fixed station over the previous four quarters.

For the period 1982-1986, EPA-EMSL concluded (Black et al., 1983; Patzer et al., 1984; Potter et al., 1985; Grossman et al., 1986; Patzer et al., 1987) that no fixed monitoring stations exhibited radiation levels in excess of background. For 1986, the average measured dose equivalent rates for the 129 stations varied between 40 and 135 mrem/yr. These values are within the ranges observed for other areas throughout the United States. The wide variation is attributable to the varying altitudes (higher dose rates at higher altitudes) and area soil constituents for the different stations.

For the period 1982 through 1986, no personnel dosimeters exhibited any exposures to off-site residents, in excess of background, that could be attributed to NTS activities (Black et al., 1983; Patzer et al., 1984; Potter et al., 1985; Grossman et al., 1986; Patzer et al., 1987). For each year during that period, a few individuals (ranging from 3 individuals in 1983 to 12 individuals in 1984 and 1986) exhibited radiation exposures in excess of background. EPA-EMSL concluded that these exposures were attributable to either occupational exposures or higher backgrounds at the individuals' residences than at the fixed background stations and were not related to any NTS activities.

4.3.3.2 Dose Assessments

Individuals can receive radiation exposures from both external sources, as is described above, and from radionuclides taken into the body through inhalation of air or ingestion of water and foodstuffs (i.e., internal exposure). A complete assessment of the radiation dose received by members of the public as a consequence of activities at NTS must include consideration of both external and internal exposure. Because the off-site TLD monitoring network has not, over the past 5 years, detected any off-site radiation levels in excess of background, it may be concluded that current NTS activities and site conditions do not contribute measurably to the radiation dose of members of the public through direct external gamma radiation exposure pathways. However, releases of radionuclides to the air, surface water, or groundwater can lead to both external and internal exposures. This section summarizes the estimated radiation dose received by members of the public as a consequence of NTS activities.

FIGURE 4-9

**DOSE ASSESSMENT PATHWAYS
NEVADA TEST SITE - MERCURY, NV**

The principal pathways for the transport of radionuclides to humans include air, water, and food. The relationships between these is shown in Figure 4-9. The doses to the various major organs are considered for various exposure pathways. The radiation doses received by a specific organs are weighted and summed to determine the total dose. Radionuclides taken into the body will continuously irradiate the body until they are removed through either radioactive decay or metabolic processes. Consequently, internal dose estimates are calculated as "50-year dose commitments." These are obtained by integrating the total dose received by an individual's body over an assumed remaining lifetime of 50 years.

REECO personnel perform annual perimeter dose assessments based on data collected from their on-site radiological monitoring network. The details of the radiological monitoring are discussed in the media-specific sections (Air, 3.1.3; Soil, 3.2.3; Surface Water, 3.3.3; and Groundwater, 3.4.5). The dose was estimated for an individual present within the NTS during the entire calendar year 1985. This dose may be considered to be an upper-limit estimate of the dose that could be received by an individual present at the site boundary for the entire year. This estimate does not include any direct external occupational exposure that would be received by a worker while handling radioactive materials or working in a radiation exclusion (RADEX) area. For 1985, the potential exposure pathways that were considered to contribute to the radiation dose were the ingestion of radionuclides in drinking water, the inhalation of radionuclides in air, and immersion in air containing gamma emitting radionuclides.

The ingestion and inhalation dose calculations were based on the maximum average concentrations above background of tritium and plutonium-239 in potable water, and tritium, plutonium-239, and strontium-90 in air. For the purposes of the calculation, it was assumed that all of the measured gross-beta activity was strontium-90. The air immersion dose is based on the average maximum observed krypton-85 and xenon-133 concentrations. The radionuclide concentrations that were used by NTS for the dose calculations are presented in Table 4-20 (Gonzalez, 1986).

For 1985, the NTS dose assessments used monitoring data and dose assessment models and conversion factors equivalent to those of International Commission on Radiological Protection (ICRP) Publication No. 2 (ICRP 2). This approach is contrary to the current DOE guidance (Vaughan, 1985) that requires adherence to 40 CFR 61 Subpart H for the assessment of dose through the air pathway and the use of the models of ICRP 26 and ICRP 30 for the assessment of dose from all pathways. 40 CFR 61 requires the use of EPA-approved codes (AIRDOS-EPA or RADRISK), or other methods approved by EPA, to calculate the air-pathway radiation dose. EPA has not approved the use of monitoring data for the NTS dose assessments. A significant difference between the dose assessment methodology used by NTS and the current DOE guidance is that the former results in

TABLE 4-20

**RADIONUCLIDE CONCENTRATIONS USED FOR THE PERIMETER DOSE ASSESSMENT
NEVADA TEST SITE, MERCURY, NEVADA**

	Air (μCi/cc)					Potable Water (μCi/ml)	
	3H	239Pu	Gross Beta	133Xe	85Kr	239Pu	3H
On-Site Concentration	<8.0 x 10 ⁻⁹	1.5 x 10 ⁻¹⁵	1.9 x 10 ⁻¹⁴	<1.3 x 10 ⁻¹⁰	4.6 x 10 ⁻¹¹	<5.7 x 10 ⁻¹¹	<9.8 x 10 ⁻⁷
Background Concentration	2.6 x 10 ⁻¹²	2.8 x 10 ⁻¹⁷	1.4 x 10 ⁻¹⁴	0.0	2.7 x 10 ⁻¹¹	<4.3 x 10 ⁻¹¹	<7.0 x 10 ⁻⁷
Net Concentration	<8.0 x 10 ⁻⁹	1.5 x 10 ⁻¹⁵	5.0 x 10 ⁻¹⁵	<1.3 x 10 ⁻¹⁰	1.9 x 10 ⁻¹¹	<1.5 x 10 ⁻¹¹	<2.8 x 10 ⁻⁷

SOURCE: Gonzalez, 1986.

separate doses for the whole body and specific organs (e.g., lungs, bone surfaces, etc.) while the latter uses weighting factors applied to specific organ doses to obtain an effective whole body dose equivalent.

Table 4-21 presents the 1985 radiation doses as calculated by NTS personnel. In addition, the Environmental Survey team used the data of Table 4-20 to calculate the effective whole body dose equivalent. For this calculation, dose conversion factors were obtained from Vaughan, 1985, and it was assumed that an adult would consume 730 liters of water per year and would have a breathing rate of 266 ml/sec. The air immersion doses were included as calculated by NTS. The effective whole body dose equivalents for 1985 are included in Table 4-20. The 1985 air pathway dose estimates (for all radionuclides) were 14 and 45 percent, respectively, of the 40 CFR 61 Subpart H (National Emissions Standard for Radionuclide Emissions from Department of Energy Facilities) dose limits of 25 mrem/yr whole body and 75 mrem/yr critical organ (bone surfaces). The effective dose is less than 11 percent of the DOE limit of 100 mrem/yr from all pathways. Since these dose estimates are based on on-site monitoring data they are likely to be overestimates of the doses that might be received at off-site locations.

EPA-EMSL prepared dose assessments based on the results of the off-site monitoring network and modeling of releases of radionuclides reported by NTS. For calendar year 1986 (Patzner et al., 1987), EPA-EMSL identified three NTS-related sources of possible radiation exposure to individuals living near the NTS. These sources are:

- Normal seepage of radioactivity from the NTS.
- Purging of radioactive gases and contamination from tunnels following nuclear detonations.
- Radioactivity in migratory deer, received from drinking water in contaminated ponds on the NTS.

No activity of recent NTS origin was detected off-site by the EPA-EMSL air-, water-, milk-, TLD-, or biological-monitoring networks, other than on two occasions when xenon-133 was detected in air. The elevated xenon-133 levels were related to releases that occurred during venting of a tunnel (following the MIGHTY OAK test) prior to entry and during a drill-back operation. On the basis of the off-site monitoring data, it may be concluded that only airborne emissions from recent NTS activities would contribute measurably to the off-site radiation dose. Because elevated off-site activity levels were observed only on two occasions, and then, only at one station for each release,

TABLE 4-21

PERIMETER RADIATION DOSES FOR 1985
NEVADA TEST SITE, MERCURY, NEVADA

Organ	Inhalation (mrem) ⁽¹⁾			Ingestion (mrem) ⁽¹⁾		Air Immersion (mrem)		Total (mrem)
	³ H	²³⁹ Pu	⁹⁰ Sr ⁽³⁾	²³⁹ Pu	³ H	¹³³ Xe	⁸⁵ Kr	
Total Body ⁽²⁾	<2.6x10 ⁰	8.2x10 ⁻¹	1.3x10 ⁻²	<1.4x10 ⁻⁴	<4.3x10 ⁻³	<2.8x10 ⁻²	<3.6x10 ⁻⁴	<3.5x10 ⁰
Bone ⁽²⁾	0.0	3.4x10 ¹	2.2x10 ⁻¹	<5.9x10 ⁻³	0.0	<2.8x10 ⁻²	<3.6x10 ⁻⁴	<3.4x10 ¹
Lung ⁽²⁾	<2.6x10 ⁰	1.3x10 ⁰	2.1x10 ⁻²	0.0	<4.3x10 ⁻³	<3.1x10 ⁻²	<6.8x10 ⁻⁴	<4.5x10 ⁰
Skin ⁽²⁾	---	---	---	---	---	<7.9x10 ⁻²	<2.7x10 ⁻²	<1.1x10 ⁻¹
Effective Dose Equivalent ⁽⁴⁾	<4.2x10 ⁰	6.4x10 ⁰	<9.7x10 ⁻³	<4.7x10 ⁻³	<1.1x10 ⁻²	<2.8x10 ⁻²	<3.6x10 ⁻⁴	<10.7

SOURCE: Gonzalez, 1986 and DOE Environmental Survey Team, 1987.

(1) 50-year cumulative dose from inhalation and ingestion of radionuclides for one year.

(2) Calculated by NTS Personnel (Gonzalez, 1986).

(3) Assumed all of the gross beta activity was strontium-90.

(4) Calculated by DOE Environmental Survey Team.

the best estimate of the dose equivalent resulting from NTS activities is one based on the total release of radioactivity. In accordance with DOE guidance (Vaughan, 1985) and the requirements of 40 CFR 61, EPA-EMSL estimated the NTS-related dose equivalent using the computer code AIRDOS-EPA and radionuclide release data received from the NTS.

For 1986, the annual maximum individual effective dose equivalent was 2.4 microrem. This value is less than 0.01 percent of the 40 CFR 61 dose limit of 25 millirem per year (whole body) by the air pathway, and 0.0024 percent of the DOE limit of 100 millirem per year (effective whole body dose equivalent) from all pathways. For 1986, the population dose equivalent to the estimated 6,360 people living within 80 kilometers of Control Point 1 was calculated to be 7.2×10^{-3} person-rem. Table 4-22 presents the dose assessments for the 5-year period 1982 through 1986. Assuming an average background dose to these individuals, of 189 mrem/yr (see Table 4-18), the background population dose is 1.2×10^3 person rem. The 1986 NTS-related dose is 6.0×10^{-4} percent of the background population dose.

In addition to the airborne release, one potential pathway for an off-site exposure to humans is ingestion of meat from migratory deer that had been drinking water from the T-tunnel drainage pond. In 1986, deer were found to contain measurable concentrations of radionuclides. EPA-EMSL (Patzner et al., 1987) estimated that in an average year, less than one of the group of approximately 25 deer that use the T-tunnel pond would be collected by a hunter. Making some broad assumptions, it was estimated that the effective dose equivalent from eating that deer would be 7.7 mrem if all of the meat were consumed by one person or 1.9 mrem if shared equally by a family of four. These doses are, respectively, 7.7 and 1.9 percent of the DOE dose limits of 100 mrem/yr effective whole body dose equivalent from all pathways.

4.3.4 Findings and Observations

4.3.4.1 Category I

None.

4.3.4.2 Category II

None.

4.3.4.3 Category III

TABLE 4-22

**OFF-SITE RADIATION DOSE ASSESSMENTS FROM RADIOACTIVITY OF RECENT NTS ORIGIN⁽¹⁾
NEVADA TEST SITE, MERCURY, NEVADA**

Year	Maximum Individual Effective Dose (mrem)	Estimated Population within 80 km of CP-1	Population Dose Equivalent (person-rem) ⁽³⁾
1982 ⁽²⁾	3×10^{-6}	4,600	9.9×10^{-6}
1983 ⁽²⁾	1.8×10^{-8}	4,600	5×10^{-5}
1984 ⁽²⁾	2.6×10^{-4}	8,500	1×10^{-3}
1985 ⁽⁴⁾	4.2×10^{-5}	6,500	1.3×10^{-4}
1986 ⁽⁴⁾	2.4×10^{-3}	6,360	7.2×10^{-3}

SOURCE: Adapted from Black et al., 1983; Patzer et al., 1984; Potter et al., 1985; Grossman et al., 1986; Patzer et al., 1987.

- (1) Based on the NTS release estimates (Table 4-19).
 (2) Estimated using an atmospheric diffusion calculation based on a gaussian plume model.
 (3) Total effective whole body dose equivalent to persons living within 80 km of Control Point-1.
 (4) Calculated using AIRDOS EPA.

1. Radionuclide Contamination of Buildings and Equipment. Currently unused buildings and equipment on the NTS are contaminated with radioactive materials in excess of NRC, and DOE (NRC Regulatory Guide 1-86 and DOE Order 5480.11 [Barber, 1985]) guidance for the unrestricted release of contaminated property.

Unrestricted use of contaminated buildings and equipment could result in radiation exposures, through the external, inhalation, and ingestion pathways, in excess of the DOE interim standard of 100 mrem/yr for the continuous exposure of members of the public and the spread of contamination. This demands that control of access and use, and monitoring of these areas be indefinitely maintained until such time as the contamination has been removed to below the guidance limits or the radionuclides have decayed to below these limits.

Several locations within four NTS project areas have been identified by Survey team members as having contaminated buildings or equipment. The following list is provided for purposes of illustration and does not necessarily include all such contaminated locations on the NTS, or even within the project areas denoted. These locations include

- Area 25

- Storage areas within the E-MAD building.
- E-MAD building "hot" bay.
- E-MAD decontamination pad.
- Two outside equipment storage areas at the E-MAD complex.
- ETS-1, one small area on a metal shield with a maximum observed fixed radiation level of approximately 300 microR/hour.
- Piping and valves at Test Cell C.
- Test Cell C building.
- Two 600-gallon contaminated storage tanks near Test Cell C.
- Contaminated storage tanks (approximately 150,000 to 200,000 gallons capacity) near Test Cell C.
- Test Cell A building.
- Test Cell A equipment test laboratory.
- R-MAD "hot" bay.
- 25-CWD-3, radioactive materials storage area.

- Area 15
 - EPA Farm, laboratory building.
 - EPA Farm, contaminated storage tank.
- Area 27
 - Super Kukla reactor building.
- Area 26
 - Tory reactor building
 - Disassembly building
 - Disassembly building contaminated storage tank

The locations described above are posted with radiation/contamination warning signs and access is limited.

4.3.4.4 Category IV

1. Radiation Dose Assessment Methodology. The radiation dose assessment methodology used by NTS in the preparation of the "Radiological Effluent and On-site Area Monitoring Report for the Nevada Test Site" does not conform to DOE requirements.

The current DOE requirements for the development of radiation dose assessment were established in memoranda from W. A. Vaughan, dated August 5, 1985, (Vaughan, 1985) and R. J. Stern, dated February 28, 1986 (Stern, 1986). These documents stipulate that (1) dose assessments be included in annual monitoring reports, (2) ICRP 30 models and dose conversion factors be used, (3) AIRDOS-EPA or other approved models be used for the airborne pathway, (4) dose from ingestion/ inhalation pathways must be for a 50-year committed dose and, (5) assessments must be made for both individual dose and the total dose to the population within an 80 kilometer radius from the site boundaries.

The 1985 monitoring report and, the 1986 monitoring report (Gonzalez, 1987), use ICRP 2 models and dose conversion factors, use monitoring data rather than AIRDOS-EPA for the air pathway assessment (without approvals) and do not consider the 80 kilometer population dose. Since the report estimates the perimeter dose on the basis of on-site monitors, it is likely

that the reported dose is an overestimate of the actual perimeter dose. In addition, the estimated doses are well below applicable radiation protection guidelines.

In its "Off-site Environmental Monitoring Report" (Patzer et al., 1987), the EPA-EMSL reports a dose assessment consistent with the DOE guidance with one exception. The EPA-EMSL reports a population dose for the population within an 80 km radius of NTS Control Point-1 rather than 80 km from the site boundaries. This will result in an underestimate of the population dose; however, because of the low magnitude of NTS releases, the dose will remain below one percent of the background dose of that population.

PRELIMINARY

4.4 Quality Assurance

4.4.1 General Description of Data Handling Procedures

The environmental monitoring for the NTS is conducted by three organizational components: (1) the on-site radiological monitoring is conducted by the REECo Environmental Sciences Department and the Dosimetry Department; (2) the off-site radiological monitoring is the responsibility of EPA's Environmental Monitoring Systems Laboratory (EPA/EMSL); and (3) the on-site nonradiological program is the responsibility of the REECo Industrial Hygiene Department. Each of these organizations is responsible for the quality assurance applied to its aspect of the overall monitoring program.

4.4.1.1 On-site Radiological Monitoring Program

4.4.1.1.1 Media Monitoring

The Environmental Sciences Department (ESD) administers the program for the monitoring of various media (e.g. water, air) while the Dosimetry Department is responsible for the monitoring of gamma radiation levels.

Written procedures have been prepared for the collection and analysis of radiological samples (ESD, 1985). Copies of the procedures were observed in the radiological laboratories by the Environmental Survey team. The Survey team reviewed the procedures, observed laboratory practices and interviewed laboratory personnel concerning the conduct of sampling and analytical activities at the NTS. On the basis of these reviews, the written procedures were found to be consistent with current practices. No portions of the radiological monitoring program were identified that were not addressed by written procedures.

Environmental monitoring data are analyzed by computer program and reviewed by supervisory personnel in the ESD. The data are reviewed to detect deviations from expected ranges and examined for data trends (Gonzalez, 1987). If unexpected deviations are noted, a review is performed of field handling, sample preparation, analytical performance, instrument function, the results of quality control checks, and data processing. If the deviation cannot be resolved otherwise, the prepared sample is recounted or a new sample is obtained.

A portion of the laboratory quality control program includes instrument control. A logbook is maintained for each radioanalytical instrument. These logbooks are used to record instrument

quality control data, instrument repairs and preventive maintenance, malfunctions, important parameters, and analyst observations. On a regularly scheduled basis (daily or weekly, depending upon the instrument) each instrument is subjected to performance and calibration checks using radioactive sources of known activity. The data are recorded in the instrument logbooks and, for the gamma spectrometer, plotted on a control chart. Control limits for each instrument have been established (ESD, 1985). The laboratory technicians are responsible for maintaining the information from these checks and detection of any out-of-control conditions. On a weekly basis these data are collected and submitted to the Instrument Control Supervisor and the Quality Control Coordinator.

The overall laboratory quality control program also includes components designed to monitor and document the precision and accuracy of the radioanalytical work conducted in the ESD Laboratory. The analytical quality control uses spiked samples, duplicates, and blanks. The results of the quality control analyses are recorded on control charts, logbooks, and a computerized database. Blanks, and either duplicates, spiked samples, or standards are included with each batch of samples. A sample batch is defined as a set of samples that are to be analyzed together. Table 4-23 summarizes batch sizes and the frequency of quality control analyses.

The analytical quality control data are reported in the Laboratory Daily Report and submitted to the Quality Control Coordinator. Spiked sample and duplicates data are evaluated by a computer program. Completed computer-generated control charts are submitted to the Quality Control Coordinator for review. The results of the blank analyses are submitted to the Chemistry Supervisor for review and recorded in the Quality Control Logbook.

If quality control data do not meet acceptance criteria, corrective action is initiated by the Quality Control Coordinator and the appropriate laboratory supervisor. The result of the investigation of the nonconformity, and a description of the corrective action taken, are documented on the "Q.A. Corrective Action Log Sheets." If necessary, those analytical results associated with suspect quality control samples are reevaluated (ESD, 1985).

The ESD laboratory participates in interlaboratory comparison programs administered by EPA/EMSL and DOE's Environmental Measurements laboratory (EML), for external quality control. These programs consist of sets of laboratory performance evaluation samples submitted to the laboratory for analysis. The concentrations of radionuclides in the samples are known to those administering the programs but not to the participating laboratories. A laboratory's performance is measured by comparing the results of analyses on these samples with the known concentrations; acceptance criteria are based on the expected precision of a technique. The Environmental Survey team reviewed the laboratory's performance in these programs for 1986. Although there were occasions

TABLE 4-23

**SUMMARY OF QUALITY CONTROL ANALYSES FOR NTS ON-SITE RADIOLOGICAL MONITORING PROGRAM
NEVADA TEST SITE, MERCURY, NEVADA**

Type of Analysis	Type of Sample	Samples per Batch	Blanks	Background	Duplicates	Spikes/ Standard	Documentation
Gamma Spectroscopy	Air (Particulate)	16	1	1/wk		2	Logbooks and Control Charts
	Air (halogens)	16	1	1/wk		2	
	Water	16	1	1/wk		2	
Gross Beta	Air Water	Variable (10-30)	1		10%	2	Logbooks
Plutonium	Water, Urine	16	1			2	Logbook
Gross Fission Products (GFP)	Urine	30	1			2	Logbook
Strontium	Water, soil, air filter, meat vegetation, urine	10	1			2	Logbook
Tritium	Air	17	3		1	2	Logbooks
	Water, urine	Variable	3		10%	2	
Noble Gas	Air	7			10%	1	Logbook

Source: ESD, 1985

when the results of performance samples analyzed by NTS failed to meet acceptance criteria, this is not uncommon for radiochemistry laboratories and the NTS performance was generally good for air, water, and urine samples.

4.4.1.1.2 Radiation Level Monitoring

Thermoluminescent dosimeters (TLDs) are used for monitoring radiation levels throughout the NTS. TLDs are analyzed by the REECo Dosimetry Group. At the time of the Environmental Survey, NTS had recently converted their TLD-reader systems to one manufactured by Panasonic, and written procedures for the use of the system were not complete, although all operators had received training (Fauver, 1987). On a daily basis, a system response check is run. If the system fails this check, the system is recalibrated. An operational checklist must be completed for every batch of TLDs. TLD results and quality control data are stored on computer storage media (e.g. disks, or magnetic tape) for an indefinite period.

4.4.1.2 Off-site Radiological Monitoring

The off-site radiological monitoring for the NTS is conducted by the EPA/EMSL. The off-site monitoring includes the Air Surveillance Network (ASN), Noble Gas and Tritium Surveillance Network (NGTSN), Long Term Hydrological Monitoring Program (LTHMP), Milk Surveillance Network (MSN), and Dosimetry Network (DN). Each network is covered by an individual Quality Assurance Project Plan (QAPP). Each plan addresses the major aspects of the network including sampling procedures, analytical procedures, data validation, and quality control practices. Table 4-24 presents the contents of a QAPP. The Environmental Survey team reviewed the QAPPs for the ASN, DN, and LTHMP and evaluated them as complete and in conformance with accepted quality assurance practices.

The collection of samples is governed by a set of Standard Operating Procedures (SOPs). The SOPs define the frequency and method of collection, type of collection media, sample containment and transport, sample preservation, sample identification, sample tracking and control, and the operating parameters for sampling instrumentation. The SOPs also govern the selection of duplicate samples and samples for replicate analyses.

Written procedures are used for the analysis of off-site samples (Johns et al., 1979). The validity of these procedures has been verified through participation in interlaboratory comparison programs, and by participation in the semiannual Department of Energy Quality Assessment Program conducted by the Environmental Measurements Laboratory (EML). The 1986 results of the EML

TABLE 4-24

CONTENTS OF EPA/EMSL QUALITY ASSURANCE PROJECT PLAN

Section

1. Project Description
2. Project Organization and Responsibility
3. QA Objectives
4. Sampling Procedures
5. Sample Custody and Control
6. Calibration and Frequency
7. Analytical Procedures
8. Internal Quality Control
9. Data Validation
10. Precision, Accuracy and Completeness
11. Corrective Action
12. Reports

Source: Prepared by DOE Environmental Survey Team, 1987.

program indicate that the EPA/EMSL procedures produce data that meet acceptance criteria (Patzer et al., 1987).

EPA/EMSL participates in intercomparison study programs administered by DOE's EML, EPA/EMSL's Nuclear Radiation Assessment Division and the International Intercomparison of Environmental Dosimeters Program, that include environmental sample analysis, thermoluminescent dosimetry, and whole-body counting. Also, samples are spiked by adding known amounts of radionuclides and then entered into the normal chain of analysis. These samples are submitted to the analyst as blinds, (i.e., not known by the analyst to be quality control checks). A review of these data by the Environmental Survey team did not reveal unsatisfactory performance.

Data for precision are collected from duplicate and replicate analyses. At least 10 percent of all samples are collected in duplicate. At least 10 percent of all samples are resubmitted for replicate analysis.

Internal quality assurance (QA) consists of those procedures used by the analyst to assure proper sample preparation and analysis. The principal procedures used by EPA/EMSL are the following:

- Instrument background counts
- Blank and reagent analyses
- Instrument calibration with known nuclides
- Laboratory control standards analysis
- Performance check-source analysis
- Maintenance of control charts for background and check-source data
- Scheduled instrument maintenance

These procedures ensure that the instrumentation is not contaminated, that calibration is correct, and that standards carried through the total analytical procedure are accurately analyzed.

After the results are produced, supervisory personnel examine the data to determine whether or not the analysis is valid. This includes checking all procedures from sample receipt to analytical result with particular attention to the internal QA data and comparison of the results with previous data from similar samples at the same location.

Any variant result or failure to follow internal QA procedures during sample analysis will trigger an internal audit of the analytical procedures and/or a re-analysis of the sample or its duplicate.

All analytical data are reviewed by personnel of the Dose Assessment Branch for completeness and consistency. Investigations are conducted to resolve any inconsistencies and corrective actions are taken if necessary. SOPs and QA project plans are revised as needed following review of procedures and methodology. The EPA/EMSL QA Officer audits the operations periodically.

4.4.1.3 On-Site Nonradiological Monitoring Program

The Industrial Hygiene (IH) Section administers the program for sampling and analysis of nonradiological contaminants at NTS. Approximately 60 percent of the nonradiological environmental samples collected at NTS, including all of the samples from the water distribution system, are submitted to off-site contractor laboratories (Frazier, 1987d). The remainder of these samples are analyzed by the IH laboratory. Off-site contractor laboratories used by NTS include EAL Corporation and Montgomery Engineering, both of which are located in California.

Most of the nonradiological samples collected at NTS are obtained by personnel not associated with the IH section. The only samples collected on a routine basis are those from the water distribution system. The other nonradiological samples are collected on an "as needed" basis. According to NTS personnel, samples are collected from the water distribution system according to the procedures specified by State of Nevada regulations governing drinking water (Bullock, 1987b). EPA or NIOSH standard methods are utilized, where possible, for all other samples processed by the IH laboratory. Nevertheless, written procedures have not been prepared for the collection of most nonradiological samples at NTS.

Chain-of-custody procedures have not been implemented for the collection and analysis of nonradiological samples at NTS. A central sample receiving point has also not been identified, and samplers deliver samples to several different locations at the IH laboratory. Some of the samples submitted to off-site laboratories are identified only by the name of the sampling location and the date the sample was collected rather than with a unique sample identification number. Unique numbers are assigned to samples analyzed by the IH laboratory. However, procedures covering holding times and reagent shelf life have not been developed and implemented.

The IH laboratory includes a matrix spike sample and/or duplicate sample with every ten samples processed. National Bureau of Standards (NBS) standards are purchased for some analyses. In contrast, blind spike, duplicate and blank samples are rarely submitted with the samples that are forwarded to off-site contractor laboratories. A formal review of the data produced by the IH laboratory for deviations from expected ranges, data trends, etc., is not performed. Similarly, NTS

has not conducted quality assurance audits of off-site contractor laboratories, and contractor laboratories are not required to provide quality assurance data to NTS.

All analysts in the IH laboratory are required to possess a baccalaureate degree. However, formal analyst training, re-training, and cross-training programs have not been implemented; rather, "on-the-job" training is the primary method of skills development. An analyst qualification program (i.e. periodically requiring analysts to obtain results in accordance with expected precision on quality control samples of known concentration in order to be qualified to perform the analysis) has also not been established.

4.4.2 Findings and Observations

4.4.2.1 Category I

None.

4.4.2.2 Category II

1. Industrial Hygiene Laboratory Quality Assurance Program Deficiencies. The validity of the data generated by the Industrial Hygiene laboratory is suspect since many commonly-accepted quality assurance (QA) practices are not followed.

The Industrial Hygiene Laboratory QA program does not include the following essential elements:

- Written procedures covering sampling and analysis.
- Chain-of-custody procedures
- A reagent shelf life program
- Procedures covering holding times
- Blank, spike, and duplicate samples are not routinely included when samples are submitted to off-site contractor laboratories.
- A formal evaluation of QA data is not performed.
- QA audits of off-site contractor laboratories (i.e., supporting the Industrial Hygiene Laboratory) are not conducted.
- Formal analyst training and qualification programs have not been implemented.

4.4.2.3 Category III

None.

4.4.2.4 Category IV

1. Environmental Sciences Laboratory Quality Assurance Program Deficiencies. The validity of the data generated by the Environmental Sciences laboratory can not be verified since the laboratory does not fully conform to some commonly-accepted QA practices.

Overall, the QA program for the Environmental Sciences laboratory appeared sound; however, the following deficiencies were observed by the Survey team:

- Formal procedures or criteria for the trend analysis of quality control charts have not been implemented.
- Investigations or corrective actions taken in response to unacceptable performance on external QA samples (EMSL and EML) are not documented.
- The analyst training/qualification program is not formalized and does not include a provision for requalification.
- There is a break in the sample chain-of-custody. Samplers deliver samples to one of a number of locations within the laboratory. All of these locations do not have controlled access and until the samples are transferred to the sample preparation technician, they are not in the possession of a custodian.

4.5 Inactive Waste Sites and Releases

4.5.1 Background Information

This section provides a description of past releases (known and suspected) of hazardous substances into the environment. These releases have occurred as a result of past weapons test activities and from inactive waste sites, spills, and leaks at the NTS. Information on sources of releases is provided in several documents, including

- Final Environmental Impact Statement, Nevada Test Site, September 1977
- Hazardous Waste Installation Assessment Report, May 1986.
- Underground Contaminants, Nevada Test Site, August 1986.
- Phase I Installation Assessment, draft, April 1986.

Based on information available to the Survey team, there are numerous sites (primarily where underground test shots have occurred) where releases of hazardous substances (known or suspected) have occurred. The overwhelming majority of past releases has involved radionuclides. To a far lesser extent, nonradioactive hazardous substances also have been released. Section 4.5.2 lists the inactive waste sites and releases, and describes past activities that have occurred at each site.

Pursuant to the requirements of DOE Order 5480.14 (which is now undergoing a complete revision), the DOE/NV prepared a draft Phase 1 Installation Assessment (1986) for the Nevada Test Site. The objective of this assessment was to identify inactive sites at the NTS where hazardous substances may have been released to the environment. This study identified 11 inactive waste sites, which are listed below and are described in Section 4.5.2, General Description of Pollution Sources/Controls:

- CP-2 Leachfield, Area 6.
- Contaminated Waste Dump No. 1, Area 11.
- Contaminated Waste Dump No. 2, Area 11.
- Reactor Maintenance Assembly and Disassembly Facility (R-MAD) Contaminated Waste Dump - Area 25.
- R-MAD Leachfield - Area 25.

- Test Cell A Leachfield - Area 25.
- Test Cell C Leachfield - Area 25.
- Engine Maintenance Assembly and Disassembly Facility (E-MAD) Contaminated Waste Dump - Area 25.
- Tory Reactor Leachfield - Area 26.
- Tory Reactor Contaminated Waste Dump - Area 26.
- E-MAD Leachfield - Area 25.

Although the above 11 sites were known to have received radioactive substances, only six were believed to have potentially received nonradioactive hazardous substances. Sampling and analyses at these six sites indicated no significant concentration of nonradioactive hazardous wastes, although radionuclides were detected (see Section 4.5.2).

At the time the draft Phase 1 Installation Assessment was prepared, the DOE/NV understood that the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) did not pertain to radioactive substances. Barring the presence of significant concentrations of nonradioactive hazardous substances at these sites and because scores developed through the hazard ranking system were low (DOE, 1986a), the DOE/NV concluded that follow-up site characterization studies and remedial actions under CERCLA should not be required at any of the sites listed above.

Since passage of the Superfund Amendments and Reauthorization Act (SARA) of 1986, the Department of Energy has been working towards the revision of its existing CERCLA program and DOE Order 5480.14 to implement the new SARA requirements. With passage of SARA, DOE has decided to replace the five-phased approach (which included the Phase 1 Installation Assessment) and adopt the Environmental Protection Agency (EPA) program as outlined in the National Contingency Plan in its entirety, as appropriate. The adoption of EPA's program is anticipated to be completed within the next several months. DOE has issued guidance to its facilities on how to use the data collected under its old CERCLA program to meet the requirements of SARA. For example, the DOE/NV expects to complete preliminary assessments (PA) for the NTS by April 1988.

In addition, recent policy issued by the DOE/NV states that the underground nuclear testing program at NTS is subject to the Comprehensive Environmental Response, Compensation, and Liability Act

(CERCLA) regulations (Bingham, 1987b). Guidelines for implementing this policy will be forthcoming, including guidelines for reporting of hazardous releases (i.e., reportable quantities) to the National Response Center (Sparks, 1988).

4.5.2 General Description of Pollution Sources/Controls

The NTS has many sites at which past releases (known or suspected) of hazardous substances have occurred. The sites identified by the Survey team through the review of existing information are:

1. Underground Test Shots/Tunnel Tests
2. Past Atmospheric Tests
3. Inactive Contaminated Waste Dumps
4. Inactive Radioactive Waste Consolidation Sites
5. Inactive Contaminated Muck Piles
6. Inactive Storage Tanks
7. Inactive Leachfields
8. Nuclear Rocket Development Station
9. Jet Fuel Release at the Desert Rock Airstrip
10. Inactive Horn Silver Mine
11. BJY Pad
12. Catchbasin near Control Point 2
13. Experimental Farm Facility
14. Inactive Subdock Complex
15. LANL Core Handling Facility
16. U9y Storage Tanks and Adjacent Area
17. Tory Reactor
18. Super Kukla Reactor Facility
19. Other Inactive Sites where there is Potential for Hazardous Substances to be Found

4.5.2.1 Underground Test Shots/Tunnel Tests

The primary source of radioactivity at the NTS is the combination of weapons materials, fission products, and neutron-induced radioactivity generated at each underground nuclear testing location. Refer to Section 3.2.2.2, Soils, for a description of subsurface soil contamination from underground nuclear testing.

4.5.2.2 Past Atmospheric Tests

Surface soils on large portions of NTS have been contaminated by weapons tests conducted at or near the surface. Refer to Section 3.2.2.1, Soils, for a description of surface soil contamination from past atmospheric tests.

4.5.2.3 Inactive Contaminated Waste Dumps

Contaminated waste dumps (CWD) are shallow burial sites that contain solid wastes related to nuclear weapon tests and non-weapon test activity. These dumps are relatively small in size, ranging up to 5 acres in area and 10 feet in depth (Penwell, 1987a). Table 4-25 lists 10 inactive CWDs that have been identified at NTS.

Five of the inactive dumps have been sampled for radionuclides. No disposal of non-radioactive hazardous materials was suspected at these sites (DOE, 1986). The Survey team was unable to find sampling and analysis data for the other five CWDs.

The five CWDs that have been sampled are CWD #1 and #2 in Area 11, CWD #1 at the R-MAD facility in Area 25, CWD #2 at the E-MAD facility in Area 25, and CWD #2 at the Tory Reactor in Area 26. Following is a brief description of these CWDs. Table 4-26 presents environmental data for these sites (Also see Section 3.2.3.4, Soils).

- CWD #1 and #2, located in Area 11, were used for the disposal of wastes contaminated with Pu-239 that were generated from the safety shots (Project 56) during the period 1955 to 1957 (see Section 3.2.2.1, Soils).

CWD #1 does not show evidence of surface contamination or of elevated radionuclide levels at any depth. On the other hand, CWD #2 is the most contaminated inactive contaminated waste dump at NTS. Radioactivity levels are as high as 4,950 pCi/g Pu-239 and 563 pCi/g Am-241. Moreover, there is surface contamination present (282 pCi/g Am-241).

- CWD #1 at the R-MAD facility, located in Area 25, was used for the disposal of solid waste contaminated with radioactivity. The CWD was composed of three waste pits. The wastes were generated from the R-MAD operations during the period 1958 to 1979. The R-MAD facility was used for assembly and disassembly of nuclear rocket reactors (see Section 4.5.2.8, Nuclear Rocket Development Station).

TABLE 4-25

**INACTIVE CONTAMINATED WASTE DUMPS (CWD)
NEVADA TEST SITE, MERCURY, NEVADA**

Area	Name of Site
5	CWD-1 Trench at Sugar Baker CWD-2 Radioactive Waste Storage/Disposal
11	CWD-1 Project 56 Events CWD-2 Project 56 Events
12	CWD-1 Area 12 Tunnel Wastes Buried in Trench
25	CWD-1 R-MAD CWD-2 E-MAD CWD-4 Central Support Area (discarded environmental samples disposed of here)
26	CWD-1 Horn Silver Mine (Refer to Section 4.5.2.10) CWD-2 Tory Reaction Test Wastes

Source: NVO, 1987.
REECo, 1986b.
REECo, undated.

TABLE 4-26

**ENVIRONMENTAL DATA FOR INACTIVE CONTAMINATED WASTE DUMPS
NEVADA TEST SITE, MERCURY, NEVADA**

Site	Sample Location	Depth (cm)	Gamma Reading μ R/h	Isotope	Activity (pCi/gm)
Safety Shot CWDs, Area 11, CWD #1	#1 Bottom	167-183	18	K-40	25.800
				Cs-137	0.542
				Ra-226	2.350
				Th-228	2.290
				Th-232	2.150
	#1 Surface	0-15	17	K-40	22.500
				Cs-137	0.644
				Ra-226	1.460
				Th-228	1.960
	#1 Tailing	0-183	17	K-40	20.100
				Ra-226	1.920
				Th-228	2.230
	#2 Bottom	106-122	17	K-40	24.600
				Ra-226	1.690
				Th-228	2.230
	#2 Surface	0-15	17	K-40	23.000
				Cs-137	0.428
				Ra-226	1.520
				Th-228	2.060
	#2 Tailing	0-122	17	K-40	22.900
				Ra-226	1.310
				Th-228	2.090
				Th-232	1.440
Safety Shot CWDs, Area 11, CWD #2	#1 Surface	0-15	18	K-40	20.200
				Am-241	282.000
				Ra-226	1.060
				Th-228	1.490
				Th-232	1.620
	#2 Surface	0-15	19	K-40	16.800
				Am-241	563.000
				Cs-137	0.558
				Pu-239	4,950.000
				Ra-226	1.160
				Th-228	1.540

TABLE 4-26
ENVIRONMENTAL DATA FOR INACTIVE CONTAMINATED WASTE DUMPS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE TWO

Site	Sample Location	Depth (cm)	Gamma Reading μ R/h	Isotope	Activity (pCi/gm)
Safety Shot CWDs, Area 11, CWD #2 (continued)	#3 Surface	0-15	18	K-40	27.300
				Am-241	154.000
				Cs-137	1.280
				Ra-226	1.520
				Th-228	2.380
	#4 Surface	0-15	20	K-40	24.200
				Am-241	477.000
				Cs-137	0.558
				Ra-226	1.210
				Th-228	1.950
R-MAD CWD, Area 25	Pit #1 Bottom	234-249	130	Th-232	1.660
				K-40	25.100
				Co-60	7.650
				Cs-137	403.000
				Ra-226	0.818
	Pit #1 Surface	0-15	21	Th-228	1.340
				Th-232	1.590
				K-40	25.300
				Co-60	11.200
				Cs-137	53.800
	Pit #1 Tailing	0-249	42	Ra-226	25.400
				Th-228	2.030
				Th-232	1.860
				K-40	29.100
				Co-60	3.340
	Pit #2 Bottom	198-213	22	Cs-137	211.000
				Ra-226	98.200
				Th-228	2.080
				Th-232	1.860
				K-40	28.800
	Pit #2 Surface	0-15	26	Co-60	3.340
				Cs-137	1.010
				Ra-226	1.130
				Th-228	1.780
				Th-232	1.690

TABLE 4-26
ENVIRONMENTAL DATA FOR INACTIVE CONTAMINATED WASTE DUMPS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE THREE

Site	Sample Location	Depth (cm)	Gamma Reading μ R/h	Isotope	Activity (pCi/gm)
R-MAD CWD (continued)	Pit #2 Tailing	0-213	21	K-40	28.700
				Ra-226	1.170
				Th-228	1.940
				Th-232	1.640
	Pit #3 Bottom	259-274	23	K-40	28.700
				Ra-226	1.160
				Th-228	1.850
				Th-232	2.330
	Pit #3 Surface	0-15	21	K-40	30.500
				Ra-226	1.060
				Th-228	2.100
				Th-232	2.160
	Pit #3 Tailing	0-274	23	K-40	25.500
				Ra-226	1.120
				Th-228	1.830
				Th-232	1.050
E-MAD CWD, Area 25	#1 Bottom	168-183	14	K-40	31.300
				Cs-137	34.700
				Ra-226	0.927
				Th-228	1.680
				Th-232	1.650
	#1 Surface	0-15	11	K-40	29.300
				Ra-226	0.964
				Th-228	1.470
	#1 Tailing	0-183	11	K-40	30.900
				Cs-137	0.445
				Ra-226	0.815
				Th-228	1.470
				Th-232	1.360
	#2 Bottom	198-213	13	K-40	32.300
				Cs-137	17.400
				Ra-226	0.904
				Th-228	1.590
				Th-232	1.370

TABLE 4-26
ENVIRONMENTAL DATA FOR INACTIVE CONTAMINATED WASTE DUMPS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE FOUR

Site	Sample Location	Depth (cm)	Gamma Reading $\mu\text{R/h}$	Isotope	Activity (pCi/gm)
E-MAD CWD (continued)	#2 Surface	0-15	12	K-40	30.300
				Cs-137	0.184
				Ra-226	0.865
				Rh-106	0.351
				Th-228	1.510
				Th-232	1.420
	#2 Tailing	0-213	12	K-40	32.200
				Cs-137	0.114
				Ra-226	0.810
				Th-232	1.480
Tory Reactor CWD	#1 Bottom	229-244	19	K-40	28.700
				Ra-226	1.110
				Th-228	1.590
				Th-232	1.750
	#1 Surface	0-15	16	K-40	25.400
				Ra-226	1.290
				Th-228	1.780
				Th-232	1.690
	#1 Tailing	0-244	19	K-40	24.800
				Ra-226	1.490
				Th-228	1.720
	#2 Bottom	229-244	18	K-40	27.300
				Ra-226	1.300
				Th-228	1.490
				Th-232	1.630
	#2 Surface	0-15	17	K-40	27.500
				Ra-226	1.270
				Th-228	1.610
				Th-232	1.880
	#2 Tailing	0-244	22	K-40	24.800
				Ra-226	1.160
				Th-228	1.860
				Th-232	1.750

Source: REEC0, 1986b.

Pit No. 3 at the R-MAD CWD is essentially uncontaminated and Pit No. 2 has elevated radioactivity levels only at the bottom (211 pCi/g Cs-137; 98.2 pCi/g Ra-226; 3.34 pCi/g Co-60). However, Pit No. 1 at the R-MAD CWD shows elevated radioactivity both at the surface (53.8 pCi/g Cs-137; 25.4 pCi/g Ra-226; 11.2 pCi/g Co-60) and at the bottom (403 pCi/g Cs-137).

- CWD #2 at the E-MAD facility, located in Area 25, was used for the disposal of solid wastes contaminated with radioactivity. The wastes were generated from the operation of E-MAD, which operated from 1966 to 1973. The E-MAD facility was used for the assembly and disassembly of NERVA rocket engines (see Section 4.5.2.8, Nuclear Rocket Development Station).

At the E-MAD CWD, radioactivity in surface samples is not elevated. The only elevated radioactivity is found at the lower depths (approximately 6-7 feet) of the CWD, where cesium-137 was measured at a maximum radioactivity level of 34.7 pCi/g. The presence of 0.351 pCi/g of Rh-106 is considered to be an anomaly (see Section 3.2.3.3, Soils).

- CWD #2 at the Tory Reactor, located in Area 26, was used for the disposal of radioactive wastes, including fuel elements from the Tory Reactor (see Section 4.5.2.17). The reactor operated from 1959 to 1964.

The Tory Reactor CWD shows no elevated radionuclide levels at any depth.

Burial sites such as CWDs should have little or no potential for environmental contamination if no liquid phase is present to promote contaminant migration to the subsurface soil or groundwater and the buried material is covered to prevent resuspension. This appears to be the case with CWD #1 in Area 11, CWD #2 at the E-MAD facility Area 25, and CWD #2 at the Tory Reactor in Area 26.

The sites at CWD #2 in Area 11 and CWD #1 at the R-MAD facility in Area 25 do show evidence of surface radioactive contamination and, therefore, present a potential source of contamination from surface soil resuspension.

4.5.2.4 Inactive Radioactive Waste Consolidation Sites

Past atmospheric test activities conducted at the Nevada Test Site have resulted in widely distributed surface areas known to have radioactively contaminated soil and debris. Many of these areas have

been cleaned up and the radioactive solid wastes have been removed and temporarily placed at nearby consolidation sites. These radioactive waste consolidation sites (RWCS, sometimes referred to as CON for consolidation site) represent designated areas where debris and soil, including radioactively contaminated material, have been consolidated from nearby inactive atmospheric test sites. The consolidated soil and debris (e.g., concrete, steel frames, cable, lumber, wire fence, etc.) are loaded onto trucks and hauled to the Area 3 RWMS for final disposal (see Radioactive Wastes, Section 4.1.2.1.2). The cleanup of RWCSs is dependent on the availability of manpower and equipment that must be diverted from the weapons test program.

In the late 1970s, a total of 25 radioactive waste consolidation sites were designated in Areas 1, 2, 3, 4, 5, 6, 7, 9, 12, and 16. The remediation of these sites is planned to be completed by the late 1980s. To date, 20 consolidation sites have been cleaned up and 5 await remediation. These 5 sites are located in Area 2 (RWCS 2B and 2C), Area 3 (RWCS 3B), Area 5 (RWCS 5A), and Area 12 (RWCS 12A).

The objective of the remedial cleanup at an RWCS is to lower the radiation to a level that is acceptable to worker health and safety. Site remediation will reduce radiation to levels equal to those of surrounding areas, typically about 0.05 milliroentgens per hour of beta plus gamma and no measurable detection of alpha activity (REECo, 1985). Pre- and post-cleanup detection data for soil and air sampling are maintained and are available through the Radioactive Waste Management section of REECo's Environmental Services Department.

All radioactive waste consolidation sites are revegetated with indigenous plants after the remedial work has been completed.

The active waste consolidation sites are possible sources of soil contamination because of the resuspension of radioactive soil particles from the uncovered and unprotected waste piles. However, these sites are generally located in remote areas of NTS.

4.5.2.5 Inactive Contaminated Muck Piles

Muck piles are waste disposal piles which are found outside and near the entrances to Test Tunnels (see Section 3.2.2.2, Soils). Muck piles typically consist of "muck" or waste rock (from tunnel development, cutback, and reentry operations) and construction debris (e.g., framing timber, steel ribs and beams, concrete, cable, pipe, etc.).

Muck that is removed from a tunnel is placed in trucks and hauled to a nearby disposal site. Often the muck is dumped down a side of the mountain near a tunnel site. The height of a muck pile can

reach 100 feet or more. At least 10 feet of clean (i.e., uncontaminated) muck is placed on top of radioactively contaminated muck to provide adequate cover for protection (i.e., radiation, erosion). There are generally several muck piles at a tunnel site. Muck is also taken for burial at the Radioactive Waste Management Site in Area 3 (see Section 4.1.2.1.2, Radioactive Waste).

Radioactively contaminated muck is monitored for radioactivity before it leaves the tunnel. As a rule, only muck that has a radioactivity level of less than 0.3 mR/hour is allowed to be hauled away for disposal. Muck that has a level of radioactivity equal to or greater than 0.3 mR/hour is not removed from the tunnel but rather is placed in unused tunnel drifts which are later permanently sealed.

Some of the inactive muck piles are contaminated with low levels of radioactivity. The radioactive wastes probably contain low levels of fission products, including Cs-137, Sr-90, and Co-60. There are no data available on the levels of radioactivity within these piles.

Inactive contaminated muck piles (CMP) are listed in Table 4-27. Active muck piles, which are located in Area 12 (at or near tunnels U12n and U12t), are described in Section 4.1.2.1.2, Radioactive Waste.

The inactive muck piles are not likely to be sources of soil contamination. Because of the arid climate, there should be no significant liquid phase to promote contaminant migration from these piles. However, in November 1987, during a reconnaissance for S&A, a seep was observed at the base of the E tunnel muck pile. During the same time period, some sloughing from the base of the T tunnel muck pile into the first tunnel pond was observed.

4.5.2.6 Inactive Storage Tanks

NTS has well over one hundred underground and above-ground storage tanks, of which at least 12 tanks are inactive (i.e., permanently out-of-service). It is not known if any of the inactive tanks have leaked. NTS does not have a leak detection program for storage tanks. For a description of the inactive tanks at NTS, refer to Section 4.1.2.1, Waste Management, and Section 4.2.1.2.1, Toxic and Chemical Materials.

4.5.2.7 Inactive Leachfields

There are many inactive leachfields at NTS that were used in the past for the disposal of waste waters from NTS project operations. The liquid wastes disposed of included sanitary wastes, industrial hygiene chemical wastes, and radioactive decontamination wastes.

TABLE 4-27

INACTIVE CONTAMINATED MUCK PILES
NEVADA TEST SITE, MERCURY, NEVADA

Area	Name of Site
12	CMP-1 U12b Core and Drill Mud Disposal CMP-2 U12c,d,f Core and Drill Mud Disposal CMP-5 U12i,j,k Core and Drill Mud Disposal
15	CMP-1 U15e Contaminated Muck Pile
16	CMP-1 U16a Contaminated Muck Pile

Source: NVO, 1987.
REECo, 1986b.
REECo, undated.

The size of these leachfields was typically less than an acre. The exact field location of every leachfield is not known, particularly in Area 25 (i.e., NRDS). Other leachfields where contamination has been documented or suspected are well posted in the field. Table 4-28 lists 21 inactive leachfields (LFP) that, in the past, have received or could have received liquid wastes other than sanitary wastes.

For 6 of the 21 sites, preliminary soil sampling has been conducted. (The Survey team was unable to find sampling and analysis data for the other 15 sites.) These six LFPs are located at Control Point 2 in Area 6; R-MAD in Area 25; E-MAD in Area 25; Test Cell A in Area 25, Test Cell C in Area 25, and the Tory Reactor (401 MAD) in Area 26. Following is a brief description of each leachfield. Tables 4-29 and 4-30 present radioactivity and hazardous chemical data, respectively for the leachfields (also see Section 3.2.3.3, Soils).

- The leachfield at Control Point 2, located in Area 6, was operational from 1951 to 1971. It was used for the disposal of decontamination wastewaters that were generated at a nearby laundry operation and an equipment decontamination operation (see Section 4.5.2.2, Catchbasin near Control Point 2). Records indicate two leachfields (LFP-1 and 2) were operated at this site although site personnel claim that there was only one leachfield used to receive decontamination wastewaters (Penwell, 1987b). The liquid wastes contained radionuclides, as well as chemical solvents and degreasers used in conjunction with the decontamination processes. There were no water quality data recorded for these wastewaters.

The maximum level of radioactive contamination detected at the CP-2 Leachfield was 1.070 pCi/g of cesium-137 (Cs-137). The only nonradioactive hazardous substances detected at this site were cadmium (0.04 mg/l of extract) and silver (0.05 mg/l) at concentrations well below the limits for the EP toxicity test (cadmium, 1 mg/l; silver, 5 mg/l). On the basis of these results, this site is considered to be essentially uncontaminated.

- LFP-2 at R-MAD, located in Area 25, was operational between 1958 to 1973. It was used for the disposal of liquid wastes from equipment decontamination at the facility. In addition to radioactive wastes, trichloroethene was also discharged to the leachfield. Other chemical solvents and/or degreasers could have been disposed of in a similar manner.

TABLE 4-28
INACTIVE LEACHFIELDS
NEVADA TEST SITE, MERCURY, NEVADA

Area	Name of Site
3	LFP-4 Subdock Complex Leaching Bed (see Section 4.5.2.14)
6	LFP-1 Decontamination Field I LFP-2 Decontamination Field II (LFP 1 and 2 are believed to be one and the same)
7	LFP-1 BJY Pad Sump (see Section 4.5.2.11)
15	LFP-1 Experimental Farm Radsafe Waste Sump (see Section 4.5.2.13) LFP-2 Experimental Farm Leaching Field (see Section 4.5.2.13)
23	LFP-1 Building 155
25	LFP-2 R-MAD Radwaste Leachfield LFP-3 E-MAD Radwaste Leachfield LFP-5 E-MAD Decontamination Pit (see Section 4.5.2.8) LFP-6 Test Cell A LFP-7 Test Cell C
26	LFP-1 Leachfield at 401 MAD Building, used for Project Pluto which utilized the Tory Reactor LFP-2 Control Area Leachfield I LFP-3 Control Area Leachfield II LFP-4 Control Area Leachfield III LFP-5 Test Bunker Disposal Field LFP-7 MAD Building
27	LFP-1 Able Site, Process Leaching Bed LFP-3 Baker Site, Leachfield I LFP-4 Baker Site, Leachfield II

Source: NVO, 1987.
REECo, 1986b.
REECo, undated.

TABLE 4-29

**RADIOACTIVITY DATA FOR SIX INACTIVE LEACHFIELDS
NEVADA TEST SITE, MERCURY, NEVADA**

Site	Sample Location	Depth (cm)	Gamma Reading (μ R/h)	Isotope	Activity (pCi/g)	Remarks
Control Point 2 Area 6	N.W. Bottom	106-122	17	K-40	6.520	
				Ra-226	0.510	
				Th-228	0.438	
	N.W. Surface	0-15	13	K-40	10.000	
				Cs-137	1.070	
				Ra-226	0.564	
				Th-228	0.659	
				Th-232	0.672	
	N.W. Tailing	0-122	18	K-40	11.300	
				Ra-226	0.607	
				Th-228	0.853	
	N.E. Surface	0-15	17	K-40	10.800	
				Cs-137	0.749	
				Ra-226	0.521	
				Th-228	0.702	
				Th-232	0.641	
	S.E. Surface	0-15	16	K-40	9.980	
				Cs-137	0.679	
				Ra-226	0.477	
				Th-228	0.693	
				Th-232	0.633	
	S.W. Surface	0-15	16	Cs-137	0.424	
				Ra-226	0.692	
				Th-228	0.768	

TABLE 4-29
RADIOACTIVITY DATA FOR SIX INACTIVE LEACHFIELDS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE TWO

Site	Sample Location	Depth (cm)	Gamma Reading (μ R/h)	Isotope	Activity (pCi/g)	Remarks
Control Point 2 Area 6 (continued)	Center Bottom	76-91	17	K-40	5.430	
				Ra-226	0.712	
				Th-228	0.494	
	Center Surface	0-15	13	K-40	8.460	
				Cs-137	0.347	
				Ra-226	0.630	
				Th-228	0.680	
	Center Tailing	0-91	16	K-40	9.350	
				Ra-226	0.549	
				Th-228	0.563	
R-MAD Area 25	#1 Surface	0-15	410	K-40 Cs-137	22,400 493,000	PRM-6 measurement (maximum surface contact - 2,000 μ R/h)
	#2 Surface	0-15	38	K-40 Be-07 Cs-137 Ra-226 Th-228 Th-232	19,200 1,610 1,620 1,040 1,890 1,620	PRM-6 measurement (maximum surface contact - 500 μ R/h)
	Manhole Bottom	107-122	2,400	Co-60 Cs-137	632,000 21,700.0	PRM-6 measurement (maximum reading 3,500 μ R/h at 122 cm)
	Center Bottom	229-244	35	K-40 Ra-226 Th-228	30,500 1,230 1,660	PRM-6 measurement (maximum reading 42 μ R/h at all depths)

TABLE 4-29
 RADIOACTIVITY DATA FOR SIX INACTIVE LEACHFIELDS
 NEVADA TEST SITE, MERCURY, NEVADA
 PAGE THREE

Site	Sample Location	Depth (cm)	Gamma Reading ($\mu\text{R/h}$)	Isotope	Activity (pCi/g)	Remarks
R-MAD Area 25 (continued)	N. W. Bottom	107-122	40	K-40	29.800	PRM-6 measurement (maximum reading 42 $\mu\text{R/h}$ at all depths)
				Ra-226	1.160	
				Th-228	1.740	
	N. E. Bottom	107-122	41	K-40	29.400	
				Cs-137	9.410	
				Ra-226	1.110	
				Th-228	1.520	
				Th-232	1.720	
	N. E. Tailing	0-122	40	K-40	29.700	
				Cs-137	1.910	
				Ra-226	1.160	
				Rh-106	0.681	
				Th-232	1.970	
	N. E. Hot Spot	76-91	43	K-40	26.200	PRM-6 measurement (maximum reading 230 $\mu\text{R/h}$ at this depth)
				Cs-137	15.500	
				Th-228	2.180	
				Th-232	1.780	
	S. E. Bottom	107-122	42	K-40	29.300	
				Cs-137	35.400	
				Ra-226	1.100	
				Th-232	1.500	
	S. E. Tailing	0-122	45	K-40	25.000	
				Cs-137	23.700	
				Ra-226	1.060	
				Th-228	1.870	

TABLE 4-29
RADIOACTIVITY DATA FOR SIX INACTIVE LEACHFIELDS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE FOUR

Site	Sample Location	Depth (cm)	Gamma Reading (μ R/h)	Isotope	Activity (pCi/g)	Remarks
R-MAD Area 25 (continued)	S. E. Hot Spot	76-91	60	K-40	25.300	PRM-6 measurement (maximum reading 1,000 μ R/h at this depth)
				Co-60	0.739	
				Cs-137	11,900.0	
				Th-228	1.600	
E-MAD Area 25	S. W. Bottom	107-122	42	K-40	33.200	PRM-6 measurement (maximum reading 42 μ R/h at all depths)
				Ra-226	1.380	
				Th-228	2.420	
				Th-232	2.060	
	#3 Standpipe	No Soil Sample Taken				PRM-6 measurement (maximum reading 70 μ R/h at 152 cm)
	#3a Bottom	229-244	22	K-40	37.400	PRM-6 measurement (maximum reading 42 μ R/h at all depths)
				Ra-226	1.070	
				Th-228	2.170	
				Th-232	1.820	
	#3a Hot Spot	76-91	24	K-40	32.600	
				Cs-137	1.510	
				Ra-226	1.010	
				Th-228	1.830	
	#3a Tailing	0-244	24	Th-232	1.810	
				K-40	33.400	
				Ra-226	0.854	
				Th-228	1.880	
				Th-232	1.540	

TABLE 4-29
RADIOACTIVITY DATA FOR SIX INACTIVE LEACHFIELDS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE FIVE

Site	Sample Location	Depth (cm)	Gamma Reading ($\mu\text{R/h}$)	Isotope	Activity (pCi/g)	Remarks
E-MAD Area 25 (continued)	#6 Standpipe	No Soil Sample Taken				PRM-6 measurement (maximum reading 85 $\mu\text{R/h}$ at 305 cm)
	#6a Bottom	198-213	24	K-40 Ra-226 Th-228 Th-232	32.000 0.943 1.400 1.640	PRM-6 measurement (maximum reading 42 $\mu\text{R/h}$ at all depths)
	#6a Hot Spot	137-152	22	K-40 Ra-226 Th-228 Th-232	30.200 0.815 1.440 1.220	
	#6a Tailing	0-213	23	K-40 Ra-226 Th-228 Th-232	31.800 0.997 1.440 1.500	
	#9 Standpipe	No Soil Sample Taken				PRM-6 measurement (maximum reading 100 $\mu\text{R/h}$ at 305 cm)
	#9a Bottom	137-152	24	K-40 Ra-226 Th-228 Th-232	32.000 0.909 1.630 1.530	PRM-6 measurement (maximum reading 42 $\mu\text{R/h}$ at 152 cm)

TABLE 4-29
RADIOACTIVITY DATA FOR SIX INACTIVE LEACHFIELDS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE SIX

Site	Sample Location	Depth (cm)	Gamma Reading (μ R/h)	Isotope	Activity (pCi/g)	Remarks
Test Cell A Area 25	Manhole Bottom	122	38	K-40 Cs-137	109,000 1,560,000	Water Sample
	Center Bottom	107-122	41	K-40 Ra-226 Th-228	31,000 0.978 1.940	
	N. W. Bottom	107-122	40	K-40 Cs-137 Ra-226 Th-228 Th-232	31,300 0.207 1.080 1.700 1.690	
	N. E. Bottom	107-122	42	K-40 Ra-226 Th-228 Th-232	40,700 1.270 2.410 2.180	
	S. E. Bottom	107-122	42	K-40 Ra-226 Th-228 Th-232	44,000 1.280 2.600 2.800	
	S. W. Bottom	107-122	42	K-40 Ra-226 Th-228	31,500 1.160 2.170	PRM-6 measurement (maximum reading 350 μ R/h at 61 cm)
	S. W. Hot Spot	46-61	42	K-40 Ra-226 Th-228	31,900 1.310 2.300	

TABLE 4-29
RADIOACTIVITY DATA FOR SIX INACTIVE LEACHFIELDS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE SEVEN

Site	Sample Location	Depth (cm)	Gamma Reading ($\mu\text{R/h}$)	Isotope	Activity (pCi/g)	Remarks
Test Cell A Area 25 (continued)	S. W. Tailing	0-122	42	K-40	33,400	
				Co-57	0.207	
				Cs-137	0.171	
				Ra-226	1.230	
				Th-228	1.880	
Test Cell C Area 25	#1 Bottom	259-274	>5,000	Th-232	2.190	PRM-6 measurement (maximum >4,200 $\mu\text{R/h}$ at 244 cm)
				Cs-137	98,000	
	#1 Surface	0-15	37	K-40	34,100	Area background - 200 $\mu\text{R/h}$ Surface contact - 190 $\mu\text{R/h}$
				Cs-137	39,300	
				Ra-226	0.812	
				Th-232	2,310	
	#2 Bottom	290-305	95	K-40	28,900	PRM-6 measurement (maximum 150 $\mu\text{R/h}$ at 305 cm)
				Cs-137	176,000	
				Sb-125	4,220	
	#2 Surface	0-15	50	K-40	31,800	
				Cs-137	9,970	
				Ra-226	1.020	
				Th-228	1.810	
				Th-232	1.690	
	#3 Bottom	290-305	>5,000	Cs-137	735,000	PRM-6 measurement (maximum >4,200 $\mu\text{R/h}$ at 305 cm)

TABLE 4-29
RADIOACTIVITY DATA FOR SIX INACTIVE LEACHFIELDS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE EIGHT

Site	Sample Location	Depth (cm)	Gamma Reading ($\mu\text{R/h}$)	Isotope	Activity ($\mu\text{Ci/g}$)	Remarks
Test Cell C Area 25 (Continued)	#3 Surface	0-15	75	K-40	27.700	
				Cs-137	328.000	
	#4 Bottom	259-274	330	K-40	27.300	PRM-6 measurement (maximum 1,200 $\mu\text{R/h}$ at 274 cm)
				Cs-137	1,080.000	
	#4 Surface	0-15	36	K-40	27.700	
				Cs-137	6.210	
				Th-228	1.930	
				Th-232	1.87	
	#5 Bottom	290-305	42	K-40	29.000	PRM-6 measurement (maximum 50 $\mu\text{R/h}$ at 305 cm)
				Cs-137	17.200	
				Eu-155	2.270	
				Ra-226	1.310	
				Sb-125	2.480	
				Th-228	1.570	
				Th-232	1.840	
	#5 Surface	0-15	36	K-40	31.000	
				Cd-109	5.850	
				Cs-137	0.327	
				Ra-226	0.971	
				Th-228	1.620	
				Th-232	1.630	

TABLE 4-29
RADIOACTIVITY DATA FOR SIX INACTIVE LEACHFIELDS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE NINE

Site	Sample Location	Depth (cm)	Gamma Reading (μ R/h)	Isotope	Activity (pCi/g)	Remarks
Test Cell C Area 25 (Continued)	#6 Bottom	320-335	42	K-40	32.400	PRM-6 measurement (maximum 600 μ R/h at 335 cm)
				Cs-137	12.700	
				Eu-155	2.000	
				Ra-226	0.808	
				Sb-125	3.130	
				Th-228	1.980	
				Th-232	1.860	
	#6 Surface	0-15	35	K-40	32.300	
				Cs-137	1.070	
				Ra-226	0.991	
				Th-228	1.850	
				Th-232	1.450	
	#7 Bottom	229-244	2,200	Cs-137	10,700.0	PRM-6 measurement (maximum 4,200 μ R/h at 244 cm)
	#7 Tailing	0-224	85	K-40	30.200	
				Cs-137	135.000	
				Ra-226	0.188	
				Th-228	1.600	
				Th-232	1.690	
Tory Reactor (401 MAD) Area 26	#1 Surface	0-15	37	K-40	22.400	
				Cs-137	222.000	
				Th-232	1.780	
	Center Bottom	152-168	18	K-40 Ra-226 Th-232	21.400 1.040 1.300	PRM-6 measurement (maximum reading 42 μ R/h at 61 cm)

TABLE 4-29
RADIOACTIVITY DATA FOR SIX INACTIVE LEACHFIELDS
NEVADA TEST SITE, MERCURY, NEVADA
PAGE TEN

Site	Sample Location	Depth (cm)	Gamma Reading (μ R/h)	Isotope	Activity (pCi/g)	Remarks
Tory Reactor (401 MAD) Area 26	Center Surface	0-15	17	K-40	30.500	
				Cs-137	0.534	
				Ra-226	1.300	
				Th-232	1.760	
	Center Tailing	0-168	18	K-40	28.700	
				Cs-137	0.179	
				Ra-226	1.220	
				Th-232	1.700	
	N. W. Bottom	107-122	16	K-40	14.200	PRM-6 measurement (maximum reading - 38 μ R/h at 61 cm)
				Cs-137	0.214	
				Ra-226	1.310	
				Th-232	0.559	
	N. W. Surface	0-15	18	K-40	32.400	
				Cs-137	0.594	
				Ra-226	1.310	
				Th-232	0.222	
	N. W. Tailing	0-122	18	K-40	22.400	
				Cs-137	0.573	
				Ra-226	1.300	
				Th-232	1.720	
				K-40	1.400	
				Cs-137		
				Ra-226		
				Th-232		

Source: DOE, Phase 1, 1986.

TABLE 4-30

**HAZARDOUS CHEMICAL DATA FOR THREE INACTIVE LEACHFIELDS
NEVADA TEST SITE, MERCURY, NEVADA**

Site	Chemical Waste	EP Toxicity		Halocarbon	
		Detected (mg/l)	Limit(1) (mg/l)	Detected (µg/kg)	Limit(2) (µg/kg)
Control Point 2 Area 6	Cadmium Silver	0.04 0.05	1.00 5.00		
Test Cell A Area 25	Cadmium Methylene chloride	0.01	1.00	64	1,000
Test Cell C Area 25	Cadmium	0.02	1.0		

Source: DOE, 1986.

(1) EP Toxicity limit as listed in 40 CFR 261.24.

(2) As listed in 40 CFR 261.33.

No solvents (volatile organic compounds) were found at this site. None would be expected after 13 years in a desert climate. Moreover, no other nonradioactive contaminants were found. Radioactive contamination, however, is significant at this site. Cs-137 activity levels reach 493 pCi/g at the surface (0-15 cm), 11,900 pCi/g at a hot spot (76-91 cm depth), and 21,700 pCi/g at a manhole bottom. No direct measurements of strontium were made, but the cesium to strontium ratio can be assumed to be approximately 1 to 1. Therefore, equivalent amounts of strontium-90 (Sr-90) are probably also present. The manhole bottom is also contaminated with cobalt-60 (Co-60) at an activity level of 632 pCi/g. Lower levels of cobalt-60, beryllium-7 (Be-7), and rhodium-106 (Rh-106) were also reported from surface, tailings, or hot-spot samples (see Section 3.2.3.3, Soils).

- LFP-3 at E-MAD, located in Area 25, was operational between 1966 and 1973. Wastewaters from equipment decontamination operations at E-MAD were discharged to the leachfield. The wastewater contaminants were similar to those discharged to the R-MAD leachfield.

The release of radioactive material to this leachfield was documented. The type and quantity of solvents released is unknown (Fauver, 1986). No nonradioactive hazardous materials were detected here and the maximum level of radioactive contamination found was 1.51 pCi/g of Cs-137 at a hot spot 76-91 centimeters deep. The maximum radiation reading found was 100 μ R/hour at the bottom (305 cm depth) of a standpipe. No soil samples were taken at standpipes. Contamination at this site is considered to be negligible.

- LFP-6 at Test Cell A, located in Area 25, was operational from 1958 to 1966. It was used for the disposal of liquid wastes from test reactor and equipment decontamination. The facility also had a chemical laboratory that discharged liquid chemical wastes to the leachfield. Liquid wastes included radioactive contaminants and probably chemical solvents, degreasers, and various chemical laboratory wastes (type and quantity unknown).

Methylene chloride was found in a soil sample from this site, at a concentration of 64 μ g/kg (ppb). This result is probably due to laboratory analysis contamination and not to solvent actually present at the leachfield after 10 years of desert conditions (see Section 3.2.3.3, Soils). The only other nonradioactive hazardous substance detected at this

site was cadmium (0.01 mg/l of extract) at a concentration well below the 1 mg/l limit for cadmium for the EP toxicity test.

- LFP-7 at Test Cell C, located in Area 25, was operational from 1961 to 1973. Liquid wastes were discharged to the leachfield from decontamination of test reactors and related equipment. Liquid wastes included radioactive contaminants and probably chemical solvents and degreasers (type and quantity unknown).

No solvents were found at this site and none would be expected due to the effects of a desert climate on volatile organic compounds. The only nonradioactive hazardous substance detected at this leachfield was cadmium (0.02 mg/l of extract) at a concentration well below the 1 mg/l limit for cadmium for the EP toxicity test. Radioactive contamination, however, is significant. Cs-137 activity levels are as high as 328 pCi/g at the surface and 735,000 pCi/g at the bottom (290-305 cm) of this leachfield. Other radionuclides found are cadmium-109 (Cd-109) at an activity of 5.85 pCi/g, europium-155 (Eu-155) maximum 2.27 pCi/g, and antimony-125 (Sb-125) 4.22 pCi/g.

- LFP-1 at the Tory Reactor (i.e., 401 MAD, which is the 401 Maintenance, Assembly, and Disassembly facility), located in Area 26, was used from 1958 to 1964. It received liquid wastes generated from decontamination operations at the reactor. The liquid wastes contained radioactive contaminants, and possibly chemical solvents and degreasers (type and quantity unknown).

The maximum level of radioactive contamination detected at this site was 222 pCi/g of Cs-137 for a sample designated as No. 1 surface 0-15 centimeters. Another sample designated No. 1 surface 0-8 centimeters from a surface cleanup had 4.94 pCi/g of Cs-137. It is unclear whether these two samples are related. All other Cs-137 activity levels measured were less than 1 pCi/g. Other radionuclides detected were U-235 at 18.1 pCi/g and Rh-106 at 0.499 pCi/g (see Section 3.2.3.3, Soils). No nonradioactive hazardous contaminants were found. These results indicate that some hot spots (or anomalies) may exist, although the general level of contamination is negligible.

An evaluation of the preliminary soil sampling data for the above six inactive leachfields suggest that the Test Cell C and R-MAD leachfields are clearly contaminated with radionuclides. The Area 26 leachfield may have some hot spots and the Test Cell A leachfield shows anomalous radionuclide results (see Section 3.2.3.3, Soils). The E-MAD and CP-2 leachfields have no or negligible contamination. None of the six was clearly

identified as containing mixed waste at the present time, although all were suspected of receiving decontamination solvents.

The inactive leachfield at Building 155 in Area 23 (see Figure 4-10) was used for the disposal of laboratory chemical wastewater. The wastewater likely included low-level radionuclides from radiochemistry analysis and solvents, acids, and bases. Building 155 was formerly used as an industrial hygiene laboratory until the early 1960s when the laboratory was moved to Building 650 (Frazier, 1987e).

The industrial hygiene laboratory generated low-level, liquid radioactive wastes (i.e., less than $3 \times 10^{-3} \mu\text{Ci/ml}$) and nonradioactive liquid wastes. Liquid wastes were generated from the preparation and analyses of various air, water, bioassay, soil, vegetation, and other samples submitted to the laboratory for radioactivity analyses (ERDA, 1977). The Survey team could not find any environmental data regarding the specific types and quantities of liquid wastes that were produced at the laboratory.

The leachfield drain system was reportedly disconnected from Building 155 after the industrial hygiene laboratory was relocated (Frazier, 1987e). Approximately 130 feet of 4-inch-diameter cast-iron, acid-resisting drain pipe and 130 feet of 4-inch-diameter Orangeburg pipe remain in the ground. The depth and exact configuration of the leachfield is unknown. There are no detailed, as-built engineering plans for this leachfield.

Because the leachfield has been abandoned for over 20 years, volatile organic compounds would not be expected at this site given the desert climate.

There is currently a paved parking lot at the site, which serves as an impervious cap above the abandoned leachfield. It is unlikely that contaminants would have migrated from the leachfield given the arid climate (i.e., lack of rain) and the presence of this parking lot overtop the leachfield.

4.5.2.8 Nuclear Rocket Development Station

In the early 1960s, the Atomic Energy Commission and the National Aeronautics and Space Administration (NASA) negotiated an interagency agreement to establish and manage a test area known as the Nuclear Rocket Development Station (NRDS). The NRDS, located in Area 25, was used

Source: AEC, 1958

FIGURE 4-10

LOCATION OF LEACHFIELD FOR INDUSTRIAL HYGIENE LAB (Bldg. 155)
NEVADA TEST SITE - MERCURY, NV

from the 1960s to 1973 to test reactors, engines, and rocket stages as part of a project to study the feasibility of developing nuclear reactors for the U.S. space program.

Within this test area, several test installations were built, covering approximately 8,000 acres of land. These installations were the Central Support Area, Reaction Control Point, Engine Maintenance Assembly and Disassembly Building, Reactor Maintenance Assembly and Disassembly Building, Engine Test Stand, Test Cell "A," and Test Cell "C" (see Figure 4-11). Today, all of these facilities are functionally inactive and are considered to be permanently out-of-service. The Survey team discovered that there is very little documentation regarding the past activities at the NRDS. On-site personnel know very little about the operations that took place here. As-built drawings of the NRDS facilities are not available (Gayle, 1987b). Following is a brief description of each installation (DOE, 1986b).

- Central Support Area (CSA)

The CSA provided support for NRDS users through a technical shops building, an administration and engineering building, a medical facility, warehousing and storage areas, and facilities for radiographics support.

- Reactor Control Point (RCP)

The RCP provided control for and support of the reactor test programs at Test Cell "A" and Test Cell "C."

The facility included a control building, technical services building, technical operations building, administration building, cafeteria, warehouse, service station, and a weather station.

- Engine Maintenance, Assembly, and Disassembly Building (E-MAD)

The E-MAD facilities were used to assemble and prepare NERVA (Nuclear Engine for Rocket Vehicle Application) engines for testing; refurbish radioactive-hot engines for additional testing; and disassemble and conduct detailed, post-mortem inspection of tested rocket engines and components. A total of six NERVA reactors/nuclear were developed and tested.

Source: NVO, 1987.

FIGURE 4-11

NRDS INSTALLATIONS NEVADA TEST SITE - MERCURY, NV

The E-MAD building is a multi-story, reinforced-concrete structure divided into 7 areas. These areas include a cold assembly area, a hot maintenance and disassembly area, post-mortem cells, high- and low-level cells, operating galleries, and a shop and service area.

Specialized equipment used for E-MAD consisted of a railroad and transport system, which included an overhead positioning crane system (40,000 pound load capacity), wall-mounted and floor mounted handling systems, hot-bay remote cranes (80,000 and 20,000 pound capacity), cell service area remote crane (15,000 pound capacity), floor turntable (90,000 pound capacity), and a post-operative cell material transfer system.

- Reactor Maintenance, Assembly, and Disassembly Building (R-MAD)

The R-MAD Building consisted of two assembly bays where nuclear rocke reactors were assembled and installed on test cars. The assembly area consisted of a clean room and an assembly bay. Other facilities included an electrical shop, a welding shop, a control rod shop, and a vault. In recent years, the facility at R-MAD was used for MX CALTP support (see Test Cell "C" at the end of this section). The disassembly area contains upper and lower bays. The upper bay can be separated from the lower disassembly bay with a 750-ton, 5-foot-thick, concrete shielding door.

The R-MAD compound was also equipped with a 2,560-square-foot decontamination facility which was accessible via the railroad system. Railroad trackage was provided to allow remote-controlled transport of the reactor from the assembly bay to the test cell, approximately 1.5 miles away; and after testing, back to the disassembly bay. A spur led to a "graveyard" that was used to bury radioactive test hardware (see Section 4.5.2.3, Inactive Contaminated Waste Dumps).

- Engine Test Stand (ETS-1)

ETS-1 was designed for the ground developmental testing of a downward-firing, NERVA-type engine in a flight-simulated environment. The ETS-1 complex included a 160-foot-high, 100-ton aluminum structure connected by a 1,150-foot-long, underground tunnel to an underground control structure which was protected from outside radiation; a cryogenic Dewar-flask and high-pressure gas vessel tank farm; the connecting process piping; an engine compartment radiation shield; a diffuser/ejector exhaust duct; a 2.5-million-gallon demineralized-deluge and cooling-water storage tank; and a cooling-

water drainage ditch. The control systems and data acquisition and recording systems were located in rooms in the control structure.

- Test Cell "A"

Test Cell-A was designed for testing nuclear rocket reactors. During reactor operations, the enclosed areas of the test cell were made inert with nitrogen, and the entire facility was operated from the RCP. The facility was constructed with the piping and systems necessary for the storage and transfer of fluids such as liquified and gaseous hydrogen, nitrogen, helium, liquid oxygen, and demineralized cooling water. The construction included thick concrete walls to protect instrumentation and control systems from high radiation damage. The facility was equipped with a 50,000-gallon elevated water reservoir and a 100,000-gallon tank for cooling water.

- Test Cell "C"

Test Cell-C was operated in the same manner as Test Cell-A for testing nuclear rocket reactors. Test Cell-C, like Test Cell-A, was constructed with piping and systems required to handle numerous gases and liquids. The facility was equipped with a 150,000-gallon elevated water reservoir, a 250,000-gallon water tank used to store heated, borated water, and a 225,000-gallon water tank used to store 200°F water supplied to a water-hydrogen heat exchanger. In addition, a cryogenic evaluation laboratory was located in the facility.

In 1969, the reactor development, engine testing, and rocket development activities were concluded at the NRDS. When Project Rover was completed in 1973, the NRDS area was returned to NTS for close-down. Following close-down, the facilities were deactivated and decontaminated for their potential transfer to other DOE programs (see Section 4.3.2, Radiation).

In the late 1970s, the United States Air Force Ballistic Missile Office (USAF/BMO) selected Area 25 for development and testing of the Missile Experimental (MX) support systems and programs including EGRESS, the Vertical Test Shelter, and the Canister Assembly and Test Launch Program (CALTP). The Air Force concluded its activities in 1979. Since 1980, Area 25 has been primarily used for nonweapons research and development.

There are a number of areas within the NRDS where inactive buildings or equipment are contaminated with radioactive materials in excess of NRC American National Standards Institute and DOE guidance for the unrestricted release of contaminated property. Access and use of these facilities are controlled by NTS to limit exposure to site personnel. Because of the shielding effect of the buildings and the large distances between contaminated locations and off-site residences, these facilities do not contribute measurably to the radiation exposure of the general public (see Section 4.3.2, Radiation). In addition, there is virtually no liquid phase in this arid climate to promote contaminant migration to the subsurface soil and groundwater.

Contaminated inactive buildings, equipment, and surrounding areas have been observed by the Survey team at the locations that are listed below. This list is not intended to represent a complete inventory of contaminated facilities; only those observed by the Survey team.

- Central Support Area

- Contaminated waste dump (CWD-4) (discarded environmental samples disposed of here)

- E-MAD

- Two underground contaminated storage tanks (together referred to as CST-1) adjacent to the south corner of the E-MAD building (see Section 4.2.1.2.1, Toxic and Chemical Materials)
- Leachfield (LFP-3) (see Section 4.5.2.7)
- Decontamination pit (LFP-5)
- Storage areas inside E-MAD
- "Hot bay" inside E-MAD
- Two equipment storage areas outside of E-MAD
- Contaminated waste dump (CWD-2) (see Section 4.5.2.3)

- R-MAD

- Leachfield (LFP-2) (see Section 4.5.2.7)
- "Hot bay" inside R-MAD
- Contaminated waste dump (CWD-1) (see Section 4.5.2.3)

- ETS-1

- Metal shield inside building

- Test Cell "A"

- Leachfield (LFP-6) (see Section 4.5.2.7)
- Test Cell "A" building
- Test Cell "A" equipment building

- Test Cell "C"

- Leachfield (LFP-7) (see Section 4.5.2.7)
- Two aboveground 600-gallon filter tanks (LFP-8 and 9). (Survey team measured a radioactivity level of 5 millirem/hr at a distance of 3 feet from each tank surface)
- Six underground effluent storage tanks that received liquid wastes from the nuclear furnace test runs (CST-2,3,4,5,6, and 7)
- Aboveground 150,000-gallon liquid storage tank (WAT-1) (Survey team measured at the surface a radioactivity level of 1 millirem/hr)
- Radioactive waste disposal area (not actually observed by Survey team but listed on map [NVO, 1987] as located somewhere at the Test Cell "C" complex, location is unknown).
- Test Cell "C" building
- Piping and valves

4.5.2.9 Jet Fuel Release at the Desert Rock Airstrip

The Desert Rock Airstrip is located in Area 22 (see Figure 4-12). It is used by LANL and LLNL for the takeoff and landing of light aircraft. The airstrip also provides limited ground support services, including refueling.

Between December 20 and 26, 1985, the LANL underground refueling system inadvertently released approximately 18,000 gallons of Jet A-50 fuel. The jet fuel contaminated the subsurface soil around the tank. The extent of contamination is not known. The cause of the fuel leak was a malfunctioning inground vertical turbine fuel pump, which is located on top of the 23,000-gallon underground steel tank (Boyce, 1986). The fuel pump has been repaired but the contaminated subsurface soil remains.

The extent of the subsurface soil contamination is unknown. The contaminated soil has not been cleaned up or removed. Given the arid conditions, there is no liquid phase to promote contaminant migration from the subsurface soil.

Both EPA Region IX and the State of Nevada were notified of the fuel release by the Safety and Health Division, DOE/NV.

4.5.2.10 Inactive Horn Silver Mine

Around the turn of the century, mining and prospecting were common at the NTS. The Wahmonie District, which was a mining district located in the vicinity of Area 26, was prospected about 1905 for gold and silver ores. No production occurred until 1928 when a high-grade silver-gold ore was discovered at the Horn Silver Mine (see Figure 4-13). Ore production was limited and eventually the mine was abandoned in 1929 (ERDA, 1977).

During the 1960s, the Horn Silver Mine shaft was reopened and used by NTS for the disposal of solid wastes from the Tory Reactor facility (Penwell, 1987c). Information is classified regarding the nature and quantity of wastes disposed of in the mine.

The mine shaft is relatively narrow and deep. The approximate dimensions are 8 foot by 8 foot by at least 200 feet deep. Wastes were placed in the mine shaft to a level of approximately 150 feet below ground. A concrete plug was then poured on top and the remaining shaft was filled with clean soil. There is now a concrete slab covering the mine shaft entrance.

It is unlikely that there is soil contamination outside of the mine at this site. Because of the arid conditions, there is no liquid phase to promote contaminant migration. There is no environmental data for this site.

FIGURE 4-12

DESERT ROCK AIRSTRIP
NEVADA TEST SITE - MERCURY, NV

FIGURE 4-13

LOCATION OF HORN SILVER MINE
NEVADA TEST SITE - MERCURY, NV

4.5.2.11 BJY Pad

The BJY Pad is a large, flat concrete pad located near the intersection of Rainer Mesa Road and Mercury Highway in Area 3 (Figure 4-14). The rectangular pad measures several thousand square feet in area. The pad was used originally as a mooring station for large balloons that were used for atmospheric tests. When atmospheric tests were terminated in the late 1950s, the pad was no longer actively used.

Since the late 1960s, the BJY Pad has been used intermittently for washing down field equipment. (Penwell, 1987d). Drilling rigs and other vehicular equipment occasionally have been taken to the BJY Pad and washed with water to remove dirt and grime that accumulate on the equipment during field activities. In addition to water, detergents and solvents (types unknown) also could have been used in the washdown operations. No radioactively contaminated equipment was brought to this site for washing (Penwell, 1987d).

The washdown water drains to a 24-inch-diameter vertical sump, located at the northeast corner of the pad. The sump collects the water which percolates to the subsurface soil.

During recent years, the BJY Pad also has been used as a site for inspecting "off-the-road" vehicles (e.g., drill rigs) that spend the majority of the time in the forward area. These periodic inspections determine the general "roadworthiness" of the vehicles, and identify necessary repairs and maintenance that should be made. All prescribed maintenance and repairs are performed at a designated service center located elsewhere at NTS (Solaegui, 1987a).

There is no environmental data for this site. It is likely that the BJY sump is a source for subsurface soil contamination.

4.5.2.12 Catchbasin Near Control Point 2

In Area 6, there is a concrete catchbasin that formerly was used to collect wastewaters. The catchbasin discharged the wastewaters to a series of disposal ponds which were later replaced by a leachfield (See Section 4.5.2.7, Inactive Leachfields). The catchbasin has been inactive since the late 1970s. The dimensions of the below-grade structure are approximately 6 feet long by 3 feet wide by 3 feet deep.

FIGURE 4-14

LOCATIONS OF U9y CRATER, BJY PAD, AND
FORMER SUBDOCK COMPLEX
NEVADA TEST SITE - MERCURY, NV

The catchbasin received wastewaters from two sources. One source was a laundry operation located at Building CP-2. It operated until 1971 when the laundry operation was moved to Yucca Lake. Wastewater from the laundry operation reportedly was contaminated with low levels of radioactivity (Penwell, 1987b) although water-quality data were not recorded.

The catchbasin also received washdown water from an adjacent decon (i.e., decontamination) pad. This concrete pad was used until the late 1970s when decon operations were discontinued there. Designated vehicles and equipment were brought to this pad and washed down using high-pressure water. The wastewater, which was occasionally contaminated with low levels of radioactivity (Penwell, 1987b), was discharged to the adjacent catchbasin. Water-quality data were not recorded for the decon washdown water. The decon pad has been decontaminated for radioactivity (Penwell, 1987b).

Wastewaters collected in the catchbasin were discharged via an underground pipe to a series of wastewater disposal ponds located about 500 feet southwest of the catchbasin (see Figure 4-15). These ponds were later closed in the 1960s or early 1970s and the contaminants removed (Penwell, 1987b). The ponds were replaced by a newly constructed leachfield located about 250 feet east of the ponds and about 400 feet south of the catchbasin. The leachfield is inactive today although it probably continues to receive rainwater that collects in the catchbasin. The leachfield is known to have low levels of potassium (P-40), radium (Ra-226), thorium (Th-228), and cesium (Cs-137). Gadolinium and silver have also been detected but at a level below the EP toxicity limit for each metal (REECO, 1986b; also see Section 4.5.2.7, Inactive Leachfields).

During the years of inactivity, the catchbasin has become partially filled with sediment, which probably has washed in from the surrounding unvegetated soil. The Survey team noticed that the sediment had an unusual dark color (i.e., much darker than the soil from the surrounding area). The Survey team also noticed mechanical equipment parked adjacent to the catchbasin. It is not known whether waste petroleum products are emptied into this catch basin.

4.5.2.13 Experimental Farm Facility

The Experimental Farm Facility (also known as the EPA Farm Complex) was established in 1964 to investigate the air-forage-cow-milk chain for the transport of radioiodine. The complex is located in Area 15 east of Road 10-02 (see Figure 4-16).

FIGURE 4-15

LOCATION OF DECONTAMINATION PAD,
CATCHBASIN, AND WASTEWATER PONDS
NEVADA TEST SITE - MERCURY, NV

The farm complex included an irrigated agricultural area, a herd of dairy cows, milking facilities, and facilities for surgical and necropsy procedures. Metabolism stalls were later added to facilitate individual collection of urine, feces, milk, and blood from dairy cows. As the research program progressed, radioactive products of the nuclear testing program (other than radioiodine) were studied in a variety of animals that were representative of human receptors.

The experimental dairy farm was operated by EPA in the same manner as a Grade A dairy with dry-lot feeding practices, except that all milk was disposed of as waste. The facilities included up to 26 milk cows; a 15-acre farm plot for growing forage; pens for individually feeding the cows during experiments; metabolism stalls for separate collection of milk, urine, feces, and blood; and an abattoir for sacrifice of experimental animals and collection of tissue samples (EPA, 1984).

During the 18-year operation, many experiments were conducted on milk transfer and metabolism of radioiodines, other fission products, and actinides. The EPA Farm Complex also served as the base of operation for the Animal Investigation Program, which investigated the uptake and retention of radionuclides in a 100-cow beef herd maintained on the Nevada Test Site as well as in other domestic and wild animals both on and off the Nevada Test Site.

Liquid waste contaminants (other than sanitary wastes which were discharged to a leachfield) were discharged to two separate waste disposal systems. Wastewater containing low-level, short-lived radioactive contaminants was discharged to an earthen sump. Wastewater containing higher-level, long-lived radionuclides was discharged to an inground, horizontal steel tank. Nonradioactive contaminants also were discharged in the wastewater.

The earthen sump is located about 500 feet south-southeast from the experiment building. The rock-lined sump received radioactive contaminants (e.g., I-131 and 135) and nonradioactive contaminants (e.g., Hg-203) that were associated with forage experiments. Levels of radioactivity and concentrations of contaminants are unknown. The sump measures approximately 20 feet square and 8 feet deep. The wastewater was discharged into the sump and then percolated to the subsurface soil. Evaporation of liquids was likely. This sump is a probable source of soil contamination.

The inground steel tank is located about 50 feet to the east of the sump. The horizontal tank, approximately 15,000-gallon capacity, is completely surrounded by an earthen berm. This tank received wastewaters containing animal urine, blood, and other liquid wastes containing longer-lived radionuclides (e.g., Pu-239) that were associated with animal experiments. The tank was periodically emptied into a tanker truck which disposed of the liquids elsewhere at NTS (disposal site).

FIGURE 4-16

EXPERIMENTAL FARM FACILITY
NEVADA TEST SITE - MERCURY, NV

unknown). The tank contained liquid at the time the Survey team visited the EPA farm complex, and reportedly was contaminated with low-level radioactivity (level of radioactivity unknown, Penwell, 1987e).

There is also a leachfield (LFP-2) located at this site. It is unclear whether this leachfield received only sanitary wastewater.

Contaminated solid wastes (e.g., animal carcasses, feces, surgical instruments) were placed in metal boxes and drums, and transported to a radioactive waste management site (which RWMS is unclear) and/or the Horn Silver Mine in Area 26.

Since the EPA farm complex was closed in 1981, there have been no other experimental activities conducted at this facility. There are currently no plans to reopen this facility.

4.5.2.14 Inactive Subdock Complex

A subdock complex was formerly located in Area 3 immediately east of the intersection of Mercury Highway and Road R3-03 (see Figure 4-14). The subdock complex operated from the 1970s to 1985 and was used as a maintenance and repair shop for servicing worn drill bits (used by the drilling rigs) and realigning bent drilling pipe. These operations have since moved to another location.

The 10-acre site has not been used since 1985. Nearly all above-grade structures (e.g., buildings, sheds, equipment) have been removed. There remain several concrete pads (which were used for work stations), as well as drains, sumps, and several underground storage tanks.

The subdock complex reportedly did not service any equipment (e.g., drill bits, pipes) that was contaminated with radioactivity (Solaegui, 1987b). Contaminated equipment was either decontaminated in the field (at the work site) or was taken to the Area 6 decontamination facility at Yucca Flat (Solaegui, 1987b) before it was sent to the subdock complex for servicing.

Chemical solvents and degreasers were used at the subdock complex (type and quantity unknown). These chemicals were probably similar to those used at the retipping operation at the Area 2 Support Facilities (e.g., RCRA-listed solvents, see Section 4.1.2.1, Waste Management). Liquid wastes were reportedly disposed of in various drains, sumps, and tanks located around the complex. Much of the waste liquids percolated into the subsurface soil. Volatilization (e.g., chemical solvents) could have occurred as would be expected in a desert climate.

The Survey team identified at least five abandoned sumps at the site. Some of the sumps contained liquids (which the Survey team could not immediately explain because the groundwater table at this site is at least 500 feet below ground). The sumps have diameters varying from 2 to 3 feet. The depths ranged from 2 feet to over 40 feet. These sumps represent probable sources of soil contamination.

The Survey team also noted the presence of two underground storage tanks (vent pipes and fill pipes were visible). The size and depth of each tank are unknown. One tank reportedly was used as a septic tank (Solaegui, 1987b) but it is not certain if it received only sanitary wastes. There is also an inactive leachfield at this site (LFP-4) which likely operated in conjunction with this septic tank.

There is also an area at the subdock complex that has been fenced (reason unknown) and access is restricted. Within this approximate 1,000 square foot area, there are several mounds that appear to be soil. There is also an indication that liquids have been disposed of at this site (the Survey team observed a thin layer of a discolored, dried, cake-like substance on top of the ground, substance unknown). It is uncertain whether this represents a possible source of soil contamination.

The Survey team could not find any as-built engineering drawings for the complex. The plans could have provided information about the use and construction of the sumps.

4.5.2.15 LANL Core-Handling Facility

In Area 3 there is an inactive site where classified radioactively contaminated core samples were once stored and examined. The site is known as the LANL WX6 ETS facility (commonly referred to as the LANL Core-Handling Facility) and is located north of Road 3-03 and about 350 yards east of the intersection of Mercury Highway and Road 3-03. LANL maintains control of this facility although the site was last used in the early 1970s (Smale, 1987).

The 1-acre site includes a core-storage yard and building, a core-handling building, and a wastewater disposal well. There are other inactive structures at this site (see Figure 4-17).

Core samples (i.e., taken from drill backs) were stored in the core-storage yard. Vertical pipes measuring approximately 18 inches in diameter and 10 feet deep in the ground were used to store the samples. (No historical information could be obtained by the Survey team regarding the core-storage building located at this site. This building was locked at the time of the on-site Survey.)

Source: AEC, 1966.

FIGURE 4-17

LANL CORE HANDLING FACILITY
NEVADA TEST SITE - MERCURY, NV

Core samples taken from drill-back operations were radioactive. There may have been nonradioactive contaminants (e.g., heavy metals such as lead) as well. Information on specific contaminants and quantities of each is classified. In general, the core samples likely contained a wide range of fission products, including cesium, cobalt, barium, lanthanum, ruthenium-106, rhodium-106, tellurium, cerium, europium, uranium-235 and -237, americium-241, and neptunium (Smale, 1987).

From the core-storage yard, soil samples were then taken to the core-handling building for examination. LANL used this facility to "high grade" samples (i.e., concentrate analytes of interest) taken from the cores. Core samples were separated, examined and prepared for off-site shipment to LANL's laboratory in New Mexico for further analyses.

Core samples were washed at the core-handling building to remove unwanted soil and debris. Wastewater from this operation was collected and discharged (via a floor drain and an underground pipe) to a disposal well located approximately 20 feet east of the building. The well, which is no longer used, is approximately 48 inches in diameter and 100 feet deep. A security fence surrounds the well head and the fence gate is locked and signed "radioactive." (Site personnel were unable to locate the keys to unlock this gate for the Survey team.)

The wastewater discharge into this well created the potential for subsurface soil contamination and groundwater contamination. For any inactive surface facility in an arid climate where a deep water table is present, the potential for continuing groundwater contamination is very low. However, such contamination may have occurred during the life of the facility.

The Survey team was unable to find any environmental data regarding this site. The Survey team measured no surface radioactive contamination at the areas visited (excluding the well head which the Survey team did not inspect because the fence gate was locked).

4.5.2.16 U9y Storage Tank and Adjacent Area

In Area 9, there is an abandoned aboveground storage tank located about 100 yards north of crater U9y (see Figure 4-14). Adjacent to the tank is a small area of land that is roped off. The Survey team was unable to identify and interview an NTS representative who had a knowledge of past activities at this site.

The vertical storage tank is empty and appears to have been abandoned many years ago. The tank may have been used to store non-potable water for field use. The steel tank has an estimated volume of 50,000 gallons. A 1-inch-diameter pipe extends from the bottom of the tank to an adjacent area of land that has been roped off for some unknown reason. This area measures about 50 square feet. Over time, the soil inside the roped-off area appears to have subsided about 8 inches, possibly from repeated liquid discharges (undocumented). The soil appears slightly discolored. Within this area there also is a 5-gallon bucket that is partially buried in the soil. The bucket may have functioned at one time as a sump for liquid discharges. The 1-inch pipe leading from the aboveground tank terminates at this sump, suggesting that the tank discharged a liquid to the sump.

REECO Rad Safe personnel recently surveyed this site (August 1987) at the request of the Survey team and found no evidence of radiological contamination on the exterior surface of the storage tank or on the ground inside the roped-off area. The history of this site remains fragmented and incomplete.

This site represents a possible source of soil contamination.

4.5.2.17 Tory Reactor

Six experimental tests involving development of a nuclear reactor for a ramjet engine as a part of Project Pluto were conducted by LLNL in Area 26. Four tests of the so-called Tory II-A and two tests of the Tory II-C nuclear reactors were performed between 1961 and 1964. The leachfield constructed adjacent to the 401 MAD building in Area 26 handled radioactive liquids resulting from these tests (ERDA, 1977).

Nuclear fuel recovery activities for the Tory II-C fuel tubes were carried out in the E-MAD facility in Area 25. Shipment of the recovered fuel to the Idaho Nuclear Engineering Laboratory (INEL) occurred in 1978.

4.5.2.18 Super Kukla Reactor Facility

The LLNL maintains facilities in Area 27 (also known as the 410 Area) of NTS. The facilities are grouped at three sites: the Super Kukla Reactor Facility, the Able site, and the Baker site. The Super Kukla Reactor is permanently out of service; the other two sites are still active. Following is a brief description of the Super Kukla Reactor Facility (ERDA, 1977).

The Super Kukla was designed and operated to provide a source for the irradiation of a wide variety of specimens, including fissile materials. The mass of the reactor is about 5 tons. The reactor is all metal and is housed in a shielded containment bunker. A steel-frame building for experiment assembly and handling is located on top of the bunker. There are two other steel-frame buildings located adjacent to the bunker which provided support services to the reactor.

The Reactor Control Building is a steel-frame building located 930 yards from the reactor. Buried instrumentation and control cables ran from the reactor area to the Reactor Control Building in three earth-filled trenches. All control of the reactor was done remotely at the Reactor Control Building. The reactor area and the area between the control building and the Super Kukla reactor were cleared of personnel before the reactor was operated.

The Super Kukla reactor was last used in the late 1970s, and there are no plans currently to reactivate it for future operation. The Super Kukla reactor building is known by NTS personnel to be contaminated. Contaminated areas are posted with warning signs and access is limited. The contamination is totally inside and contained within the building (see Section 4.3.2, Radiation).

4.5.2.19 Other Inactive Sites Where There is Potential for Hazardous Substances to be Found

There are other sites at the NTS where hazardous wastes likely have been disposed of or where releases of hazardous substances likely have occurred. Technical drawings (NVO, 1987) and other documents (REECo, 1986b) that were reviewed by the Survey team suggest that at least 14 other sites at the NTS likely have been used for hazardous waste disposal (i.e., radionuclides and/or nonradioactive hazardous substances). These sites are listed in Table 4-31.

No determination can be made at this time whether any of these sites is contaminated. Burial sites with no liquid phase to promote contaminant migration are unlikely to produce soil or groundwater contamination in the absence of major climatic change to arid conditions that prevail at NTS.

TABLE 4-31

**OTHER INACTIVE SITES WHERE HAZARDOUS SUBSTANCES ARE LIKELY TO BE FOUND
NEVADA TEST SITE, MERCURY, NEVADA**

Area	Name of Site
3	LANL Classified Waste Disposal Hole (Ud6) CMD-2 J-11, Hole for Core Disposal CMD-3 J-6, Hole for Core Disposal CMD-4 Ud3a, Hole for Core Disposal CMD-5 Ud3b, Hole for Core Disposal CMD-6 Ud3c, Hole for Core Disposal CMD-7 Ud3d, Hole for Core Disposal CMD-8 Ud3e, Hole for Core Disposal CMD-9 Ud6, Hole for Core Disposal CMD-10 Ud6s, Hole for Core Disposal
5	BCS-1 Beryllium Contamination at Sugar Bunker BCS-2 Beryllium Contamination at Triple Point Bunker BCS-3 Beryllium Contamination at the GMX Area (All three sites are currently being investigated by BECAMP, see Section 3.2.2.1, Soils)
9	CMD-1 U9y Hole for Drill Mud Disposal

Source: NVO, 1987.
 REEC, 1986b.
 REEC, undated.

4.5.3 Findings and Observations

4.5.3.1 Category I

None

4.5.3.2 Category II

None

4.5.3.3 Category III

1. Inactive Contaminated Waste Dumps. Contaminated waste dumps (CWD) are shallow burial sites that contain solid wastes related to nuclear weapon tests and non-weapon test activity. These dumps are relatively small in size, ranging up to 5 acres in area and 10 ft in depth (see Section 4.5.2.3).

Two CWDs show evidence of surface radioactive contamination and, therefore, present a potential source of contamination from surface soil resuspension. CWD-2 in Area 11 has surface contamination of 282 pCi/g Am-241 (it is also the most contaminated CWD at NTS, see Section 4.5.2.3). Elevated radioactivity levels have been measured at the surface of CWD-1 at the R-MAD facility in Area 25. These radioactive contaminants include 53.8 pCi/g Cs-137, 25.4 pCi/g Ra-226, and 11.2 pCi/g Co-60.

There are several other inactive contaminated waste dumps that have not been fully investigated for surface radioactive contamination. These sites include the CWD-1 and CWD-2 in Area 5, the CWD-1 in Area 12, the CWD-4 in Area 25, and the CWD-1 in Area 26. No environmental data were available from these CWDs at the time of the Environmental Survey.

2. Inactive Radioactive Waste Consolidation Sites. Radioactive waste consolidation sites (RWCS, sometimes referred to as CON for consolidation site) represent designated areas where debris and soil (including radioactively contaminated material) from nearby inactive atmospheric test sites (see Section 4.5.2.4) have been consolidated and temporarily placed into waste piles.

Waste consolidation sites are possible sources of soil contamination because of the resuspension of radioactive soil particles from the waste piles that are not covered. There are currently five radioactive waste consolidation sites that are awaiting remediation and cleanup (e.g., removal of the wastes to the Area 3 RWMS). These sites are located in Area 2 (RWCS 2B and 2C), Area 3 (RWCS 3B), Area 5 (RWCS 5A), and Area 12 (RWCS 12A). Pre-cleanup data from soil and air sampling at these sites are maintained by REECO's Environmental Services Department.

3. Inactive Contaminated Muck Piles. Muck piles are waste disposal piles that are found outside and near the entrances to test tunnels. Muck piles typically consist of "muck" or waste rock (from tunnel development, cutback and reentry operations), and construction debris (e.g., framing timber, steel ribs and beams, concrete, cable, pipe, etc.) (see Section 4.5.2.5).

Some of the inactive muck piles are contaminated with low levels of radioactivity (i.e., from the disposal of contaminated muck from reentry operations). The radioactive wastes potentially contain Cs-137, Sr-90, and Co-60. The inactive contaminated muck piles are located in Area 12 (CMP-1 at U12b, CMP-2 at U12c,d,f, and CMP-5 at U12i, j and k), Area 15, (CMP-1 at U15e), and Area 16 (CMP-1 at U16a). No environmental data for the inactive contaminated muck piles were available at the time of the Environmental Survey.

Contaminated muck is generally covered with clean muck (i.e., uncontaminated tunnel waste) to provide a cover over the contamination. This prevents contaminated soil from being resuspended and contaminating surrounding soil.

The inactive muck piles are not thought to be sources of soil contamination because of the general absence of a liquid phase to promote migration. However, in November, 1987, during a reconnaissance trip for S&A, a seep was observed at the base of the E tunnel muck pile. During the same time period, some sloughing from the base of the T tunnel muck pile into the first tunnel pond was observed. Survey-related S&A has been planned for these two inactive contaminated muck piles to determine the nature and depth to contamination.

4. Inactive Leachfields. There are inactive leachfields at NTS that were used in the past for the disposal of waste waters from NTS project operations. The liquid wastes disposed of included sanitary waste, industrial hygiene chemical wastes, and radioactive decontamination wastes (see Section 4.5.2.7).

Inactive leachfields that received wastewater contaminants create probable sources for soil contamination. The frequent discharge of liquid wastes could have promoted contaminant migration from the leachfields. Radioactive contamination is known to be present at three inactive leachfields: Test Cell C (LFP-7) in Area 25, R-MAD (LFP-2) in Area 25, and at the 401 MAD building (LFP-1) in Area 26.

- Radioactive contamination at the Test Cell C LFP-7 includes 328 pCi/g of Cs-137 at the surface and 735,000 pCi/g of Cs-137 at the bottom (290-305 cm) of the leachfield. Other radionuclides found were cadmium (Cd-109) at an activity of 5.85 pCi/g, europium (Eu-155) at 2.27 pCi/g, and antimony (Sb-125) at 4.22 pCi/g.
- For the LFP-2 at the R-MAD facility, cesium (Cs-137) activity levels reach 493 pCi/g at the surface (0-15 cm), 11,900 pCi/g at a hot spot (76-91 cm depth), and 21,700 pCi/g at a manhole bottom. No direct measurements of strontium were made, but the cesium-to-strontium ratio can be assumed to be approximately 1 to 1. Therefore, equivalent amounts of strontium-90 (Sr-90) are probably also present. The manhole bottom is also contaminated with cobalt-60 (Co-60) at an activity level of 632 pCi/g. Lower levels of cobalt-60, beryllium-7 (Be-7), and rhodium-106 (Rh-106) were also reported from surface, tailings, or hot-spot samples.
- The maximum level of radioactivity found at the 401 MAD building LFP-1 was 222 pCi/g of Cs-137 at or near the surface.

None of the above listed LFPs was clearly identified as containing mixed waste at the present time, although all were suspected of receiving decontamination solvents.

There are 14 other inactive leachfields that had the potential for creating soil contamination. These inactive leachfields are referred to as LFP-4 in Area 3; LFP-1 in Area 7; LFP-1 and LFP-2 in Area 15; LFP-1 in Area 23; LFP-5 in Area 25; LFP-2, LFP-3, LFP-4, LFP-5, and LFP-7 in Area 26; and LFP-1, LFP-3, and LFP-4 in Area 27. No environmental data were available for these leachfields at the time of the Environmental Survey.

Survey-related S&A was recommended for the LFP-1 (Building 155) in Area 15. However, because of recent resource reallocations, this site has been eliminated from the NTS S&A. This facility was used as an industrial hygiene laboratory until the early 1960s when the laboratory was moved to Building 650. The laboratory generated low-level radioactive wastes (i.e., less than 3×10^{-3} μ Ci/ml) and nonradioactive liquid wastes (e.g., solvents, acids, and bases).

5. Jet Fuel Release at the Desert Rock Airstrip. The Desert Rock Airstrip is located in Area 22. It is used by LANL and LLNL for the takeoff and landing of light aircraft. The airstrip also provides limited ground support services including refueling (see Section 4.5.2.9).

Approximately 18,000 gallons of Jet A-50 fuel was inadvertently released from an underground refueling system in 1985. The release contaminated the subsurface soil. The extent of the soil contamination has not been fully characterized and remediated.

6. BJY Pad. The BJO Pad is a large (i.e., several thousand square feet), flat concrete pad located near the intersection of Rainer Mesa Road and Mercury Highway in Area 3 (see Section 4.5.2.11).

Since the late 1960s, the pad has been used intermittently for washing down field equipment. Drilling rigs and other vehicular equipment occasionally have been taken to the BJO Pad and washed with water to remove dirt and grime that accumulate on the equipment during field activities. In addition to water, detergents and solvents (types unknown) also could have been used in the washdown operations. The washdown water drains to a sump, located at the northeast corner of the pad. The sump collects the water which then percolates to the subsurface soil.

Past discharge of wastewater to the sump have probably created a source for soil contamination. No environmental data were available for this site at the time of the Environmental Survey.

Survey-related S&A is being conducted at this site.

7. Catch Basin near Control Point 2. In Area 6 near Control Point 2, there is an inground, concrete catchbasin that formerly received contaminated wastewaters from a laundry operation and an adjacent decontamination (decon) pad. The catch basin has been inactive since the late 1970s (see Section 4.5.2.12).

Wastewater from the laundry operation reportedly was contaminated with low-levels of radioactivity. Water-quality data were not recorded. The laundry operation was moved in 1971 to the Yucca Lake area.

The decon pad was used until the late 1970s. Vehicles and equipment were brought to this pad for decon operations. The wastewater was occasionally contaminated with low-levels of radioactivity. Water-quality data for this operation were not recorded.

During the years of inactivity, the catchbasin has become partially filled with sediment. The sediment has an unusual dark color (i.e., much darker than the soil from the surrounding area). At the time of the Environmental Survey, mechanical equipment was also parked adjacent to the catchbasin. It is not known whether waste petroleum products from this equipment are emptied into this catch basin. This catchbasin is a potential source of contaminated, especially if the catchbasin overflows and releases contaminated sediment to the surrounding soil.

Survey-related S&A is being conducted at this catchbasin.

8. Experimental Farm Facility. The Experimental Farm Facility (also known as the EPA Farm Complex) was operated from 1964 to 1981 to investigate the air-forage-cow-milk chain for the transport of radioiodine. The complex, which is inactive, is located in Area 15 (see Section 4.5.2.13).

Liquid waste contaminants (other than sanitary wastes which were discharged to a leachfield) were discharged to two separate waste disposal systems. Wastewater containing low-level, short-lived radioactive contaminants was discharged to an earthen sump. Wastewater containing higher-level, long-lived radionuclides was discharged to an inground, horizontal steel tank. Nonradioactive (but possibly hazardous) contaminants also were discharged in the wastewater.

The earthen sump was unlined and wastewater percolated to the subsurface soil. Past liquid discharges to this sump have potentially created a source for soil contamination. No environmental data were available for this sump at the time of the Environmental Survey.

In addition, an inactive, inground 15,000-gallon steel tank reportedly is contaminated with low-level radioactive liquid wastes (level of radioactivity is unknown, [Penwell, 1987e]). It is not known if this tank (age unknown) has even leaked (and thereby contaminated the subsurface soil).

Survey-related S&A is being conducted at the earthen sump.

9. Inactive Subdock Complex. A subdock complex was formerly located in Area 3 and was used as a maintenance and repair shop for servicing worn bits (used by drilling rigs) and for realigning bent drilling pipe. The 1-acre site has been inactive since 1985 when the subdock operations moved to another site at NTS (see Section 4.5.2.14).

Chemical solvents and degreasers were used at the subdock complex (type and quantity unknown). These chemicals were probably similar to those used at the retipping operation at the Area 2 Support Facilities. Liquid wastes were reportedly disposed of in various drains, sumps, and tanks located around the complex. Much of the waste liquids percolated into the subsurface soil. Volatilization (e.g., chemical solvents) could have occurred as would be expected in a desert climate.

The Survey team identified five abandoned sumps at the site. Some of the sumps contained liquids (which could not be immediately explained because the groundwater table at this site is at least 500 feet below ground). Some or all of these sumps represent potential sources of soil contamination because past liquid discharges could have promoted migration of contaminants from the sumps.

The Survey team also noted the presence of two underground storage tanks (vent pipes and fill pipes were visible). The size and depth of each tank are unknown and it is not known whether either tank ever leaked (and subsequently contaminated the soil). One tank reportedly was used as a septic tank (Solaegui, 1987b) but it is not certain if it received only sanitary wastes.

There is also an area at the subdock complex that has been fenced (reason unknown) and access is restricted. Within this approximate 1,000-square-foot area, there are several mounds that appear to be soil or soil covered. There is also an indication that liquids have been disposed of at this site (the Survey team observed thin layer of a discolored, dried cake-like substance on top of the ground, substance unknown). It is uncertain whether this represents a possible source of soil contamination. No environmental data were available for this site at the time of the Environmental Survey.

Survey-related S&A was recommended at this site. However, because of recent resource reallocations, this site has been eliminated from the NTS S&A.

10. LANL Core - Handling Facility. In Area 3, there is a one-acre, inactive site where classified radioactively contaminated core samples were formerly stored and examined. The site is

known as the LANL WX6 ETS facility (commonly referred to as the LANL Core-Handling Facility). LANL maintains control of this facility although the site was last used in the early 1970s (see Section 4.5.2.15).

In addition to other activities at this site, classified core samples were washed at a core-handling building to remove unwanted soil and debris. Wastewater from this operation was collected and discharged to a disposal well located approximately 20 feet east of the building. The well, which is no longer used, is approximately 48 inches in diameter and 100 feet in depth. A security fence surrounds the well head and the fence gate is locked and signed "radioactive." No environmental data were available for this site at the time of the Environmental Survey.

The wastewater discharged into this well resulted in the potential for subsurface soil contamination and groundwater contamination. For any inactive surface facility in an arid climate where a deep water table is present, the potential for continuing groundwater contamination is very low. However, such contamination may have occurred during the life of the facility.

Survey-related S&A is being conducted at the disposal well.

11. U9y Storage Tank and Adjacent Area. In Area 9, there is an abandoned aboveground 50,000-gallon steel storage tank (empty). Adjacent to this tank is a small area (approximately 50 square feet) that has been roped-off (see Section 4.5.2.16).

A 1-inch-diameter pipe extends from the bottom of the abandoned storage tank along the ground to the adjacent area of land that has been roped off. Overtime, the soil inside the roped-off area appears to have subsided about 8 inches, possibly from repeated liquid discharges (undocumented). The soil appears slightly discolored. Within this area, there also is a 5-gallon bucket that is partially buried in the soil. The bucket may have functioned at one time as a sump for liquid discharges. The 1-inch pipe leading from the storage tank terminates at this sump, suggesting that the tank discharged a liquid to the sump.

The history of this site remains incomplete. The site represents a possible source of soil contamination. No environmental data were available for this site at the time of the Environmental Survey.

Survey-related S&A was recommended for this site. However, because the recent resource reallocations, this site has been eliminated from the NTS S&A.

12. Other Inactive Sites Where There is Potential for Hazardous Substances to be Found. There are other inactive sites at the NTS where radioactive wastes and possibly hazardous wastes likely have been disposed of or where releases of hazardous substances likely have occurred. Technical drawings and other documents that were reviewed by the Survey team suggest that at least 14 other sites at the NTS likely have been used for hazardous waste disposal (i.e., radionuclides and/or nonradioactive hazardous substances). These sites are as follows:

Area 3 LANL Classified Waste Disposal Hole (Ud6)

CMD-2 J-11, Hole for Core Disposal
CMD-3 J-6, Hole for Core Disposal
CMD-4 Ud3a, Hole for Core Disposal
CMD-5 Ud3b, Hole for Core Disposal
CMD-6 Ud3c, Hole for Core Disposal
CMD-7 Ud3d, Hole for Core Disposal
CMD-8 Ud3e, Hole for Core Disposal
CMD-9 Ud6, Hole for Core Disposal
CMD-10 Ud6s, Hole for Core Disposal

Area 5

BCS-1 Beryllium Contamination at Sugar Bunker
BCS-2 Beryllium Contamination at Triple Point Bunker
BCS-3 Beryllium Contamination at the GMX Area

(All three sites are currently being investigated by BECAMP, see Section 3.2.2.1, Soils)

Area 9

CMD-1 U9y Hole for Drill Mud Disposal

No determination can be made at this time whether any of these sites is a source for soil or groundwater contamination. Burial sites with no liquid phase to promote contaminant migration are unlikely to produce soil or groundwater contamination in the absence of a major climate change to arid conditions that prevail at NTS.

Category III findings relating to past atmospheric tests, underground test shots/tunnel tests are presented in Section 3.2.4.3, Soils, Finding Nos. 1 and 2, respectively. Inactive underground storage tanks are addressed as part of a Category III Finding in Section 4.2.2, Toxic and Chemical Materials, Finding No. 1.

4.5.3.4 Category IV

1. CERCLA 103(c) Notification. Under Section 103(c) of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, NTS is required to notify the Environmental Protection Agency (EPA) of disposal sites containing hazardous substances.

No documentation could be found in the files to verify that NTS has formally notified EPA of the existence of these disposal sites.

PRELIMINARY

REFERENCES

AEC (Atomic Energy Commission), 1966. Technical Drawing, Nevada Test Site - Area 3, Station 850, Core Handling Building, Plot Plan, 003-850-C1.2, February 17.

AEC (Atomic Energy Commission), 1968. Technical Drawing, Mercury Structure 155 A or B Water and Sewer Systems, M1558-U1 and C1, July 10.

Anspaugh, L. R., J.H. Shinn, P. L. Phelps, and N. C. Kennedy, 1975. "Resuspension and Redistribution of Plutonium in Soils," Health Physics, Vol. 29, Pergamon Press, New York, New York, pp. 571-582.

Anspaugh, L. R., 1987. Personal Interview with L. R. Anspaugh, Lawrence Livermore National Laboratory, by J. D. Yesso, NUS Corporation, Subject: objectives and conclusions of NAEG and RIDP studies, July 1987.

App, F. N., 1986. Memorandum from Fred N. App, LANL, to T. T. Scolman, LANL, Subject: pre-ALEMAN investigations, Los Alamos National Laboratory, Los Alamos, New Mexico, July 23.

App, F.N., and W.L. Hawkins, 1986. Memorandum from F.N. App and W.L. Hawkins, LANL, to T. T. Scolman, LANL, Subject: "completion of RNM related activities - UE3e, U3kz," Los Alamos National Laboratory, Los Alamos, New Mexico, August 20.

Ashbaugh, L. J., 1987. Personal interview with L. J. Ashbaugh, DOD/DNA, by T. F. Eckle, NUS Corporation, Subject: containment of tunnel shots, July 8.

Barber, R. W., 1985. Letter to DOE Staff, Subject: DOE Order 5480.11, "Radiation Protection (Occupational)," U.S. Department of Energy, Washington, D.C.

Bartlett, J. W., Jr., 1985. Letter from J. W. Bartlett, Jr., Fenix & Scisson, Inc., to D. Serdoz, Nevada Division of Environmental Protection, Subject: construction of dust collection system, ADM-0376, October 29.

Bartlett, J. W., Jr., 1987. Letter from J. W. Bartlett, Jr., Fenix & Scisson, Inc., to L. H. Schifley, Jr., Nevada Division of Environmental Protection, Subject: calendar year production, January 26.

BECAMP, undated. Basic Environmental Compliance and Monitoring Program, U.S. Department of Energy, Nevada Operations Office, Las Vegas, Nevada.

Beck, M. D., 1986. Letter from M. D. Beck, McKesson Environmental Services, Inc., to J. Kesler, EG&G, Subject: transmitting water analysis results, 860998, Pleasanton, California, October 6.

Bicker, A. E., 1986. Letter from A. E. Bicker, Reynolds Electrical & Engineering Co., Inc., to P. K. Fitzsimmons, U.S. Department of Energy, Nevada Operations Office, Subject: NTS mixed waste assessment summary, October 1.

Bingham, F. E., 1987a. Personal interview with F. E. Bingham, U.S. Department of Energy, by J. D. Yesso, Subject: BECAMP activities, July.

Bingham, F. E., 1987b. Memorandum from F. E. Bingham, U.S. Department of Energy, Nevada Operations Office, to P. E. Fitzsimmons, and R. Taft, Subject: environmental regulation of nuclear weapons tests, May 29.

Bingham, F. E., 1987c. Memorandum from F. E. Bingham, U.S. Department of Energy, Nevada Operations Office, to P. K. Fitzsimmons, Subject: Resource Conservation and Recovery Act (RCRA) inspection, February 18.

Black, S. C., R. F. Grossman, A. A. Mullen, G. D. Potler, D. D. Smith., and Nuclear Radiation Assessment Division, 1983. Off-site Environmental Monitoring Report, Radiation Monitoring Around United States Nuclear Test Areas, Calendar Year 1982, EPA-6001-4-83-032, U.S. Environmental Protection Agency, Las Vegas, Nevada.

Black, S. C., A. E. Smith, and C. F. Costa, 1986. Off-Site Monitoring for the MIGHTY OAK Nuclear Test, EPA/600/4-86-030, DOE/DP/00539-057, Environmental Monitoring Systems Laboratory, U.S. Environmental Protection Agency, Las Vegas, Nevada, July, pp. 1-2.

Boughton, C. J., 1986. "Integrated Geochemical and Hydraulic Analyses of Nevada Test Site Ground Water Systems," Master's Thesis, Water Resources Center, Desert Research Institute, University of Nevada System, Reno, Nevada, May.

Boyce, D. C., 1986. Memorandum from D. C. Boyce, to S. R. Elliott, Reynolds Electrical & Engineering Co., Inc., Subject: trip report - Desert Rock Air Strip fuel tank leak, and Miles Laser Test, Mercury, Nevada, January 17.

Bruesch, G. T., 1986. Letter from G. T. Bruesch, Fenix & Scisson, Inc., to Dick Serdoz, Nevada Department of Conservation and Natural Resources, Subject: calendar year production 1985, TES-5819, March 11.

Buddemeier, R. W. and D. Isherwood, 1985. Radionuclide Migration Project, 1984 Progress Report, UCRL-53628, Lawrence Livermore National Laboratory, University of California, Livermore, California.

Bullock, D., 1987a. Personal Interview with D. Bullock, Reynolds Electrical & Engineering Co., Inc. by R. Tarbert, NUS Corporation, Subject: sewage lagoon monitoring, June 20, 1987, NTS Environmental Survey Logbook No. 3, pp. 43-51.

Bullock, D., 1987b. Personal interview with D. Bullock, Reynolds Electrical & Engineering, Co., by R. C. Gerlach, NUS Corporation, Subject: collection and analysis of samples from NTS drinking water system. July 6.

Burbey, T. J. and S. W. Wheatcraft, 1986. Tritium and Chlorine-36 Migration from a Nuclear Explosion Cavity, DOE/NW/10384-09, Water Resources Center, Desert Research Institute, University of Nevada System Publication #45050, April.

Case, C., J. Davis, R. French, and S. Raker, 1984. Site Characterization in Connection with the Low Level Defense Waste Management Site in Area 5 of the Nevada Test Site, Nye County, Nevada-Final Report, DOE/NW/10162-13, Water Resources Center, Desert Research Institute, University of Nevada System Publication #45034.

Clark, T. R., 1987. Memorandum from T. R. Clark, U.S. Department of Energy, to M. L. Walker, and S. R. Foley, Subject: Nevada Test Site Discharges to Soil Columns, Draft, April 13.

Coulson, A., 1986. Letter from A. Coulson, State of Nevada, to J. Kesler, EG&G, Subject: Generator Investigation Report, February 24.

Cross, J. A., 1986. Letter from J. Cross, Fenix & Scisson, Inc., to D. Serdoz, Nevada Division of Environmental Protection, Subject: construction of dust collection system, ADM-0535, March 21.

Crow, Neil B., 1976. First Observations of Tritium in Ground Water Outside Chimneys of Underground Nuclear Explosions, Yucca Flat, UCRL-52073, Lawrence Livermore National Laboratory, University of California, Livermore, California.

DOE (U. S. Department of Energy), 1984. DOE Order 5820.2, Radioactive Waste Management, U.S. Department of Energy, Washington, D.C., February 6.

DOE (U. S. Department of Energy), 1985. U.S. Department of Energy Guidelines for Residual Radioactivity at Formerly Utilized Sites Remedial Action Program and Remote Surplus Facilities Management Program Sites, Revision 1, U.S. Department of Energy, Washington, D.C.

DOE (U. S. Department of Energy), 1986a. Phase I Installation Assessment, Draft, April.

DOE (U. S. Department of Energy), 1986b, Nevada Site Development Plan, Part II - Appendix (Draft), May.

Earth Technology Corporation, 1987. Draft Closure Plan for the Nevada Test Site Hazardous Waste Landfill, Earth Technology Corporation, Alexandria, Virginia., pp. 4 and 5.

EG&G, 1972. Radiological Survey of the Nevada Test Site (Survey Period: 1970-1971) EGG-1183-1552, Las Vegas, Nevada.

EG&G, 1979a. An Aerial Radiological Survey for the United States Department of Energy of Area 13, Nevada Test Site, EGG-1183-1752, EG&G Energy Measurements, Las Vegas, Nevada.

EG&G, 1979b. An Aerial Radiological Survey of Areas 25 and 26, Nevada Test Site, EGG-1183-1745, EG&G Energy Measurements, Las Vegas, Nevada.

EG&G, 1982. An Aerial Radiological Survey of Areas 1, 2, 3, 4, 6, 7, 8, 9, 10, 12, 15, and 17, Nevada Test Site, EGG-1183-1808, EG&G Energy Measurements, Las Vegas, Nevada.

EG&G, 1983a. Map of Elevated Radiation Levels Identified by Aerial Surveys, January, EG&G Energy Measurements, Las Vegas, Nevada.

EG&G, 1983b. An Aerial Survey of Area 11, Nevada Test Site, EGG-10282-1004, EG&G Energy Measurements, Las Vegas, Nevada.

EG&G, 1985. An Aerial Radiological Survey of Areas 18 and 20, Nevada Test Site, EGG-10282-1093, EG&G Energy Measurements, Las Vegas, Nevada.

EG&G, 1986. An Aerial Radiological Survey of Areas 12, 15, 17, and 19, Nevada Test Site, EGG-10282-1113, EG&G Energy Measurements, Las Vegas, Nevada.

EMSL (Environmental Monitoring Systems Laboratory), 1984. Pamphlet, Public Safety for Nuclear Weapons Tests, U.S. Environmental Protection Agency, Las Vegas, Nevada, January.

EPA (U. S. Environmental Protection Agency), 1977. "Proposed Guidance on Dose Limits for Persons Exposed to Transuranium Elements in the General Environment," EPA-520/4-77-016, U.S. Environmental Protection Agency, Washington, D.C.

EPA (Environmental Protection Agency), 1984. Public Safety for Nuclear Weapons Tests, U.S. Environmental Protection Agency, Las Vegas, Nevada, January.

EPA (Environmental Protection Agency), 1987a. Environmental Radiation Data, Report 49, January 1987 - March 1987, EPA 520/5-87-018, U.S. Environmental Protection Agency, Eastern Environmental Radiation Facility, Montgomery, Alabama.

EPA (Environmental Protection Agency), 1987b. Environmental Radiation Data, Report 48, October 1986 - December 1986, EPA-520/5-87-017, U.S. Environmental Protection Agency - Eastern Environmental Radiation Facility, Montgomery, Alabama.

ERDA (Energy Research and Development Administration), 1977. Final Environmental Impact Statement, Nevada Test Site, Nye County, Nevada, ERDA-1551, Energy Research and Development Administration, Washington, D.C., September.

ESD (Environmental Sciences Department), 1985. "Radioanalytical Laboratory Procedures." Reynolds Electrical & Engineering Co., Inc. Las Vegas, NV.

Evert, W., 1987. Personal Communication (telecon) from W. Evert, USGS, to M. Robison, NUS Corporation, Subject: Pahute Mesa #1 Well, July 17,

Farber, K., 1986. Review Team Report on the Nevada Test Site Mixed Waste Issues, U.S. Department of Energy, Washington, D.C., December.

Fauver, D. N., 1986. Hazardous Waste Installation Assessment Report, DOE/NV/10327-23, Reynolds Electrical & Engineering Co., Las Vegas, Nevada.

Fauver, D. N., 1987. Personal interview with D. Fauver, REECo, by J. D. Yesso, NUS Corporation, Subject: environmental dosimetry.

Fitzsimmons, P. K., 1987a. Environmental Activity Report for the Period September-October 1987, U.S. Department of Energy, Las Vegas, Nevada, November 5.

Fitzsimmons, P. K., 1987b. Monthly Environmental Activity Report for July 1987, U. S. Department of Energy, Las Vegas, Nevada.

Fitzsimmons, P. K., 1988. Monthly Environmental Activity Report for January 1988, U.S. Department of Energy, Las Vegas, Nevada.

Fleischhauer, H. L., N. Korte, S. Sturm, S. Wagner, and J. M. Sewell, 1986. Hydrogeologic Site Characterization of the Department of Energy Kansas City Facility, Second Interim Report, GJ-40, Bendix Field Engineering Corporation, Grand Junction Operations, Grand Junction, Colorado, p. 29.

Forry, E., 1987. Personal communication from Earl "Bud" Forry, REECo, to M. Robison, NUS Corporation, Subject: Liquid Waste Disposal Hole U9ITS-Y30-Ps1a, July 9.

FR (Federal Register), 1986. "Water Pollution Control; National Primary Drinking Water Regulations; Radionuclides," 52 FR 34836, Washington, D.C., September 30.

Fraser, D. L., 1987. Memorandum from D. L. Fraser, Reynolds Electrical & Engineering Co., Inc., Subject: hazardous waste disposal, June 17.

Frazier, A. R., 1986a. Notification from A. R. Frazier, Reynolds Electrical & Engineering Co., Inc., to A. Biaggi, State of Nevada, "Notification for Underground Storage Tanks," May 9.

Frazier, A. R., 1986b. Letter from A. R. Frazier, Reynolds Electrical & Engineering Co., Inc., to Rosse, V., State of Nevada Department of Conservation and Natural Protection, Subject: 1985 Annual PCB Report, 566-06-336, June 25.

Frazier, A. R., 1987a. Letter from A. R. Frazier, Reynolds Electrical & Engineering Co., Inc., to L. H. Shifley, Nevada Department of Conservation and Natural Resources, Subject: Air Quality Permits Annual Report, CY 1986, 566-06-216, April 15.

Frazier, A. R., 1987b. Letter from A. R. Frazier, Reynolds Electrical & Engineering Co., Inc., to V. Rosse, State of Nevada, Subject: Hazardous Waste Generator Report for 1986, February 27.

Frazier, A. R., 1987c. Letter from A. R. Frazier, Reynolds Electrical & Engineering Co., to C. D. Boyce, Nevada Operations Office, Subject: halogenated hydrocarbon (CFC) usage by REECo., May 18.

Frazier, A. R., 1987d. Personal interview with A. R. Frazier, Reynolds Electrical & Engineering Co., by R. C. Gerlach, NUS Corporation, Subject: analysis of nonradiological samples by REECo Industrial Hygiene Laboratory, July 6.

Frazier, A. R., 1987e. Personal Interview with A. R. Frazier, REECo, by R. Scullin, ICF Technology, Subject: history of the industrial hygiene laboratory at Building 155.

Freeman, J., 1987. Letter from J. Freeman, Nevada Department of Conservation and Natural Resources, to O. Haworth, Reynolds Electrical & Engineering Co., Inc., Subject: Air Quality Inspection Reports, March 20.

French, R. H. and W. S. Lombardo, 1984. Assessment of Flood Hazard at the Radioactive Waste Management Site in Area 5 of the Nevada Test Site, DOE/NV/10162-15, U.S. DOE, Las Vegas, Nevada.

Frisbie, H. R., R. J. LaCamera, M. M. Rick, D. B. Wood, 1985. Water Resources Data, Nevada Water Team, 1984, USGS-WRD-NV-84-1, U.S. Geological Survey, Carson City, Nevada 62-64.

Garber, M. S., 1971. Hydraulic-Test and Quality-of-Water Data from Hole U3cn PS#2, BILBY Site, Nevada Test Site, USGS-474-105, NTS-230, U.S. Geological Survey, Federal Center, Denver, Colorado.

Gayle, H. B., 1987a. Personal Communication from H. B. Gayle, Holmes & Narver, to M. Robison, NUS Corporation, Subject: Hagestad #1 injection well, June 30.

Gayle, H., 1987b. Personal Interview with H. Gayle, Holmes & Narver, by R. Scullin, ICF Technology, Subject: as-built engineering drawings for the Nuclear Rocket Development Station facilities (Area 25).

Gilbert, R. O., L. L. Eberhardt, E. B. Fowler, E. M. Romney, E. H. Essington, and J. E. Kinnear, 1975. Statistical Analysis of $^{239-240}\text{Pu}$ and ^{241}Am Contamination of Soil and Vegetation on NAEG Study Sites, NVO-153, U.S. Energy Research and Development Administration, Nevada Operations Office, Las Vegas, Nevada, pp.339-448.

Gilbert, R. O., 1977. "Revised Total Amounts of $^{239-240}\text{Pu}$ in Surface Soil at Safety Shot Sites," Transuranics in Desert Ecosystems, NVO-181, U.S. Department of Energy, Nevada Operations Office, Las Vegas, Nevada, 423-427.

Gonzalez, D. A., 1986. Radiological Effluent and Onsite Area Monitoring Report for the Nevada Test Site (January 1985 through December 1985), DOE/NV/10327-28, Reynolds Electrical & Engineering Co., Inc., Las Vegas, Nevada, September.

Gonzalez, D., 1987. Personal Interview with D. Gonzalez, REE Co. by J. D. Yesso, NUS Corporation, Subject: NTS dose assessment methodology, July.

Green, J., 1987. Personal interview with J. Green, Reynolds Electrical & Engineering Co. by R. C. Gerlach, NUS Corporation, Subject: underground storage tanks for heating boilers, June 30.

Grossman, R. F., S. C. Black, R. E. Dye, D. D. Smith, D. J. Thome, A. A. Mullen, and Nuclear Radiation Assessment Division, 1986. Off-site Environmental Monitoring Report-Radiation Monitoring Around United States Nuclear Test Areas, Calendar Year, 1985, EPA/600/4-86/022, U.S. Environmental Protection Agency, Las Vegas, Nevada.

Haworth, O., 1987a. Personal interview with O. Haworth, Reynolds Electrical & Engineering Co. by R. C. Gerlach, NUS Corporation, Subject: spill response at NTS, July 1.

Haworth, O., 1987b. Personal interview with O. Haworth, Reynolds Electrical & Engineering Co., by R. C. Gerlach, NUS Corporation, Subject: labeling of PCB transformers at NTS, June.

Holmes & Narver, Inc., 1979. Technical Drawing, Area 6 Control Point Utilities - Sewer, p. 95, April 1.

Holmes & Narver, Inc., 1985. Nevada Test Site Sitewide Proposed and Existing Water Systems, 11-15-85, U.S. DOE, Las Vegas, Nevada.

Holmes & Narver, 1986. Nevada Test Site, Road and Facility Map, Holmes & Narver, Inc., Las Vegas, Nevada, July.

Jacobson, R. L., R. W. Buddemeier, J. L. Thompson, and C. E. Savard, Undated. Proposed Drilling and Testing at the U20n Site, Nevada Test Site, Document prepared for Nevada Joint Program and Coordinating Council, by the Desert Research Institute, Lawrence Livermore National Laboratory, Los Alamos National Laboratory, and the U.S. Geological Survey.

Jacobson, R. L., M. S. Henne, and J. W. Hess, 1986. A Reconnaissance Investigation of Hydrogeochemistry and Hydrology of Rainier Mesa, DOE/NV/10384-05, Water Resources Center, Desert Research Institute, University of Nevada System Publication #45046, June.

Jacobson, R. L., 1987a. Personal Communication from R. Jacobson, DRI, to M. S. Robison, NUS Corporation, Subject: discharge areas for NTS groundwater, June 25.

Jacobson, Roger L., 1987b. Personal Communication from R. Jacobson, DRI, to M. S. Robison and R. E. Tarbert, NUS Corporation, Subject: use of U20ac injection well, June 29.

Johns, F. B., P. B. Hahn, D. J. Thome, and E. W. Bretthauer, 1979. "Radiochemical Analytical Procedures for Analysis of Environmental Samples," EMSL-LV-0539-17, U.S. Environmental Protection Agency, Las Vegas, Nevada.

Kautsky, M., 1984. Sorption of Cesium and Strontium by Arid Region Desert Soil, DOE/NV/10162-16, Water Resources Center, Desert Research Institute, University of Nevada System Publication #45037.

Kearl, Peter M., 1982. Water Transport in Desert Alluvial Soil, DOE/NV/10162-2, Water Resources Center, Desert Research Institute, University of Nevada System Publication #45024.

Kendall, E., 1988. Personal Communication (Telephone) from E. Kendall, REECo., to G. M. Kelly, ICF Technology, Subject: radioactive waste management, March.

Kercher, J. R., and L. R. Anspaugh, 1984. Analysis of the NAEG Model of Transuranic Radionuclide Transport and Dose, UCRL-91781 Preprint, Lawrence Livermore National Laboratory, Livermore, California.

Kesler, J., 1987a. Personal Interview with J. Kesler, EG&G, by R. E. Tarbert, NUS Corporation, July 1987. DOE Survey Team Workbook No. 3, pp. 97-111.

Kesler, J., 1987b. Interoffice memorandum from J. Kesler to Pat Murphy, Re: P.C. effluent baseline monitoring March 24, 1987, EG&G Energy Measurements, Las Vegas, Nevada.

Kesler, J., 1987c. Letter to R. Tarbert, NUS Corporation, Subject: P.C. effluent sampling results for DOE Environmental Survey, dated November 4, 1987, EG&G Energy Measurements, Las Vegas, Nevada.

Kesler, J., 1987d. Letter from J. Kesler, EG&G, to A. Coulson, State of Nevada, Subject: Hazardous Waste Generator Report for 1986.

Kesler, J., 1986e. Letter from J. W. Kesler, EG&G, to A. Coulson, State of Nevada, Subject: notification of underground storage tanks, February 26.

Leavitt, V. D., and B. J. Mason, 1971. Soil Survey of Area 15, Nevada Test Site, SWRHL-106r, Western Environmental Research Laboratory, Environmental Protection Agency, Las Vegas, Nevada.

Maddox, Jackson P., 1986. Letter to City of N. Las Vegas, Subject: Industrial User Baseline Monitoring Report. October 8, 1986, EG&G Energy Measurements, Las Vegas, Nevada, October 8.

Maddox, J. P., 1987. Letter from J. P. Maddox, EG&G, to F. Bingham, U.S. Department of Energy, Nevada Operations Office, Subject: Annual Hazardous Waste Summary-1986.

Martin, W. E., and S. G. Bloom, 1980. "Nevada Applied Ecology Group Model for Estimating Plutonium Transport and Dose to Man," Transuranic Elements in the Environment, DOE/TIC-22800, Department of Energy, Washington, D.C., 459-512.

McArthur, R. D., and J. F. Kordas, 1983. Radionuclide Inventory and Distribution Program: The Galileo Area, DOE/NV/10162-14, Desert Research Institute, University of Nevada System, Las Vegas, Nevada.

McArthur, R. D., and J. F. Kordas, 1985. Nevada Test Site, Radionuclide Inventory and Distribution Program: Report No. 2, Areas 2 and 4, DOE/NV/10162-20, Desert Research Institute, University of Nevada System, Las Vegas, Nevada, September.

McArthur, R. D., and S. W. Mead, 1987a. Nevada Test Site Radionuclide Inventory and Distribution Program: Report No. 3, Areas 3, 7, 8, 9, and 10, DOE/NV/10384-15, Desert Research Institute University of Nevada System, Las Vegas, Nevada, February.

McArthur, R. D., and S. W. Mead, 1987b. Nevada Test Site Radionuclide Inventory and Distribution Program: Report No. 4, Areas 18 and 20, Draft-unnumbered, Desert Research Institute, University of Nevada System, Las Vegas, Nevada, October.

McCarthy, J. F., and Frank J. Wobber, 1986. Transport of Contaminants in the Subsurface: The Role of Organic and Inorganic Colloidal Particles (Summary Report of an ISIS Seminar, (International Series of Interactive Seminars), DOE/ER-0331, U.S. Department of Energy, Office of Energy Research, Office of Health and Environmental Research, Ecological Research Division, Washington, D.C.

McCleary, G., 1986. Permit for Open Burning, Permit No. 87-5, Department of Conservation and Natural Resources, Carson City, Nevada, August 27.

McCleary, G., 1987. Permit for Open Burning, Permit No. 87-37, Department of Conservation and Natural Resources, Carson City, Nevada, March 31.

McGrath, D.A., 1987. Memorandum from D. A. McGrath, REECO, to E. W. Kendall, REECO, Subject: Unsaturated Zone Monitoring Plan for the proposed mixed waste facility, May 28.

Metcalf, J. H., Undated. "Construction and Support Requirements, Reentry Safety and Effluent Documentation," MIDDLE NOTE, Sandia National Laboratories, Albuquerque, New Mexico.

Minster, J., 1987. Personal interview with J. Minster, Reynolds Electrical & Engineering Co., by R. C. Gerlach, NUS Corporation, Subject: underground storage tanks managed by the Supply Section of the Supply and Property Management Department). July 1.

MMES (Martin Marietta Energy Systems), 1986. Environmental Surveillance of the Oak Ridge Reservation and Surrounding Environs During 1985, ORNL-6271 Martin Marietta Energy Systems, Oak Ridge, TN.

NAEG (Nevada Applied Ecology Group), 1976. Studies of Environmental Plutonium and Other Transuranics in Desert Ecosystems, NVO-159, Energy Research and Development Administration, Nevada Operations Office, Las Vegas, Nevada.

NAEG (Nevada Applied Ecology Group), 1977. Transuranics in Natural Environments, NVO-178, U.S. Energy Research and Development Administration, Nevada Operations Office, Las Vegas, Nevada.

NAEG (Nevada Applied Ecology Group), 1978. Selected Environmental Plutonium Research Reports, NVO-192, U.S. Department of Energy, Nevada Operations Office, Las Vegas, Nevada.

NAEG (Nevada Applied Ecology Group), 1982. The Radioecology of Transuranics and Other Radionuclides in Desert Ecosystems, NVO-224, U.S. Department of Energy, Nevada Operations Office, Las Vegas, Nevada.

NAEG (Nevada Applied Ecology Group), 1987. The Dynamics of Transuranics and Other Radionuclides in Natural Environments, NVO-272, U.S. Department of Energy, Nevada Operations Office, Las Vegas, Nevada.

NVO (Nevada Operations Office), Undated. DOE's Nevada Operations Office, What It Does and Why, U.S. Department of Energy, Nevada Operations Office, Las Vegas, Nevada.

NVO (Nevada Operations Office), 1980. RIOLA-Summary of Post Seepage Radiological Activities, U.S. Department of Energy, Nevada Operations Office, Las Vegas, Nevada, November.

NVO (Nevada Operations Office), 1985a. RCRA Part B Permit Application for the Radioactive Waste Management Site Landfill, U.S. Department of Energy, Nevada Operations Office, Las Vegas, Nevada, November.

NVO (Nevada Operations Office), 1985b. NTS Low-Level Waste Management, U.S. Department of Energy, Nevada Operations Office, Las Vegas, Nevada, July.

NVO (Nevada Operations Office), 1985c. Operational Radioactive Defense Waste Management Plan for the Nevada Test Site, NVO-185 (Rev. 4), U.S. Department of Energy, Nevada Operations Office, Las Vegas, Nevada, January.

NVO (Nevada Operations Office), 1986a. The Nevada Operations Office, A Summary of Missions, Programs, Resources, Facilities, and Key Personnel, U.S. Department of Energy, Nevada Operations Office, Las Vegas, Nevada, October.

NVO (Nevada Operations Office), 1986b. Radionuclide Migration Program Strategy Document, NVO.298, Nevada Operations Office, U.S. Department of Energy, Las Vegas, Nevada.

NVO (Nevada Operations Office), 1986c. Implementation Plan for DOE Order 5820.2 Radioactive Waste Management, U.S. Department of Energy, Nevada Operations Office, Las Vegas, Nevada.

NVO (Nevada Operations Office), 1987. Nevada Test Site - Environmental Compliance Atlas, U.S. Department of Energy, Nevada Operations Office, Las Vegas, Nevada, June 15.

NWN (Nuclear Waste News), 1987. Vol. 7, No. 45, Business Publishers Inc., Silver Springs, MD, p. 327.

OCRWM (Office of Civilian Radioactive Waste Management), 1986. Environmental Assessment, Yucca Mountain Site, Nevada Research and Development Area, Nevada, DOE/RW-0073, U.S. Department of Energy, Office of Civilian Radioactive Waste Management, Washington, D.C., May.

Orcutt, J. A., 1982. Cleanup and Treatment (CAT) Test - A Land Area Decontamination Project Utilizing a Vacuum Method of Soil Removal, DOE-INV/00410-70, Reynolds Electrical & Engineering Co., Inc., Las Vegas, Nevada, August.

Oswald, K. M., 1971. Memorandum to P. E. Coyle and F. Beane, LRL, from K. M. Oswald, LRL. Subject: report of information pertinent to U9ITS-U-29, KMO-17-71, Lawrence Radiation Laboratory, Bldg. 600, NTS, March 29.

Patton, S. E., M. G. Novo, and J. H. Shinn, Lawrence Livermore National Laboratory, 1986. Environmental Assessment for the LGF Spill Test Facility at Frenchman Flat, Nevada Test Site, DOE/EA-0309, U.S. Department of Energy, Nevada Operations Office, Las Vegas, Nevada, June.

Patzer, R. G., S. C. Black, R. F. Grossman, D. D. Smith, and Nuclear Radiation Assessment Division, 1984. Off-site Environmental Monitoring Report, Radiation Monitoring Around United States Nuclear Test Areas, Calendar Year 1983, EPA-600/4-84-040, U.S. Environmental Protection Agency, Las Vegas, Nevada.

Patzer, R. G., C. A. Fontana, R. F. Grossman, S. C. Black, R. E. Dye, D. D. Smith, D. J. Thomé, A. A. Mullen, and Nuclear Radiation Assessment Division, 1987. Off-site Environmental Monitoring Report: Radiation Monitoring Around United States Nuclear Test Areas, Calendar Year 1986, EPA-600/4-87-17, U.S. Environmental Protection Agency, Las Vegas, Nevada, May.

Penwell, C., 1987a. Personal Interview with C. Penwell, REECo, by R. Scullin, ICF Technology, Subject: Size of inactive contaminated waste dumps.

Penwell, C., 1987b. Personal interview with C. Penwell, REECo, by R. Scullin, ICF Technology, Subject: History of CP-2 Catch Basin and Leachfield.

Penwell, C., 1987c. Personal interview with C. Penwell, REECo., by R. Scullin, ICF Technology, Subject: History of Horn Silver Mine.

Penwell, C., 1987d. Personal interview with C. Penwell, REECo., by R. Scullin, ICF Technology, Subject: History of BJY Pad.

Penwell, C., 1987e. Personal interview with C. Penwell, REECo, by R. Scullin, ICF Technology, Subject: EPA farm complex-contamination of the 15,000-gallon liquid waste tank.

Phillips, G. W., 1987. Personal communication between G. W. Phillips, REECo, and M. Robison, NUS Corporation, Subject: "Hagestad #1 injection well", June 29.

Porter, A., 1987. Personal Communication between Al Porter, Nevada Department of Environmental Protection, Carson City, Nevada, and R. E. Tarbert, NUS Corporation, Subject: Nevada regulations, NTS Survey Logbook No. 3, pp. 5 and 7, June 5.

Potter, G. D., S. G. Black, R. F. Grossman, R. G. Patzer, D. D. Smith, and Nuclear Radiation Assessment Division, 1985. Off-site Environmental Monitoring Report, Radiation Monitoring around United States Test Areas, Calendar Year 1984, EPA-600/4-85-035, U.S. Environmental Protection Agency, Las Vegas, Nevada.

Quiring, R. F., 1968. Technical Memorandum from R. F. Quiring, U.S. Department of Commerce, Subject: Climatological Data, Nevada Test Site and Nuclear Rocket Development Station, ERLTM-ARL7, ESSA Research Laboratories, Air Resources Laboratories, Las Vegas, Nevada, August.

REECo (Reynolds Electrical & Engineering Company, Inc.), undated. Index of Environmental Compliance Groupings.

REECo (Reynolds Electrical & Engineering Company, Inc.), 1985. Radioactive Waste Consolidation Project, FY 1985, Completion Report, December.

REECO (Reynolds Electrical & Engineering Company, Inc.), 1986a. Briefing material on radioactive defense waste management at the Nevada Test Site, May.

REECO (Reynolds Electrical & Engineering Company, Inc.), 1986b. Nevada Test Site Underground Contaminants, August.

REECO (Reynolds Electrical & Engineering Company, Inc.), 1987a. Procedure 3.2.51: "Hazardous Material Control", January 7.

REECO (Reynolds Electrical & Engineering Company, Inc.), 1987b. Company Procedure 3.2.54: "Controlling Polychlorinated Biphenyls (PCBs)", January 9.

Rey, G., 1987. Personal interview with G. Rey, Reynolds Electrical & Engineering Co., by R. C. Gerlach, NUS Corporation, Subject: labeling of hazardous materials, July 7.

Salazar, A., 1987. Personal interview with A. Salazar, EG&G Energy Measurements Group, by R. C. Gerlach, NUS Corporation, Subject: transformers at the EG&G facilities, July 8.

Sewell, Duane C., 1987. ALEMAN Radionuclide Migration Panel Final Report, Duane C. Sewell, Chairman, Private Consultant, 4265 Drake Court, Livermore, California, January 22.

Shinn, J. H., D. N. Homan, and C. B. Hofman, 1986. A Summary of Plutonium Aerosol Studies: Resuspension at the Nevada Test Site, UCRL-90746, Preprint, Lawrence Livermore National Laboratory, Livermore, California.

Shockley, V. E., 1971. Memorandum from V. E. Shockley, LRL, to P. E. Coyle and F. O. Beane, LRL, Subject: Pinex Pipe Exploration, VES-3-71, Lawrence Radiation Laboratory, April 29.

Shugart, J. W., 1987. Personal Interview with J. W. Shugart, REECO, by J. D. Yesso, NUS Corporation, Subject: Monitoring and inventory of radiation exclusion areas, July.

Sinnock, Scott, 1982. Geology of the Nevada Test Site and Nearby Areas, Southern Nevada, SAND 82-2207, Sandia National Laboratories, Albuquerque, New Mexico.

Skivers, R., 1987. Personal communication from R. Skivers, REECO., to R. Tarbert, NUS Corporation, Subject: typed list, "Septic Tanks at NTS."

Smale, D., 1987. Personal Interview with D. Smale, LANL, by R. Scullin, ICF Technology, Subject: history of LANL Core Handling Facility.

Smith, B. P., 1987. Transmittal from B. P. Smith, Reynolds Electrical & Engineering Co., Inc, to P. K. Fitzsimmons, U.S. Department of Energy, Nevada Operations Office, "Part A Applications for Radioactive Waste Management Sites in Area 3 and Area 5 at the Nevada Test Site," June 23.

Solaegui, F., 1987a. Personal Communication from F. Solaegui, REEC Co, to R. Scullin, ICF Technology, Subject: past activities at the BJY Pad.

Solaegui, F., 1987b. Personal Communication from F. Solaegui, REEC Co, to R. L. Scullin, ICF Technology, Subject: past activities at the Subdock Complex.

Sparks, L., 1988. Personal Communication with L. Sparks, Office of Environmental Compliance, DOE, by R. Scullin, ICF Technology, Subject: DOE guidelines for CERCLA and SARA compliance, March.

Stern, R. J., 1986. Preparation of Annual Site Environmental Reports for Calendar Year 1985, U.S. Department of Energy, Washington, D.C., February 28.

Strickler, R., 1986. Factsheet entitled "Nevada Operatio. Office--Nevada Test Site," U.S. Department of Energy, Washington, D.C., October.

Thalgott, R. H., and W. D. Weart, 1971. BANE BERRY Summary Report, NVO-95, U.S. Atomic Energy Commission, Nevada Operations Office, Las Vegas, Nevada.

Tuma, J., 1987. Fireman's Fund Insurance Company, Environmental Laboratories Report, 1/8/87 and 1/13/87, 864356 and 870064, Petaluma, California.

Tyler, Scott W., 1987a. Review of Soil Moisture Flux Studies at the Nevada Test Site, Nye County, Nevada, DOE/NV/10384-17, Water Resources Center, Desert Research Institute, University of Nevada System Publication #45058.

Tyler, S. W., 1987b. Personal communication from Scott Tyler, DRI, to M. S. Robison, NUS, Subject: NASH Satellite Well UE-2 ce, July 1.

Vaughan, W. A., 1985. Memorandum from W. A. Vaughan, Assistant Secretary Environment, Safety, and Health. Subject: Radiation Standards for Protection of the Public in the Vicinity of DOE Facilities, U.S. Department of Energy, Washington, D.C., August 5.

White, W. R., 1985. Memorandum from W. R. White, EG&G Energy Measurements Group, to J. Maddox, EG&G Energy Measurements Group, Subject: PCB transformers at EG&G facilities in Las Vegas.

Williams, E., 1988. Telephone interview with E. Williams, Reynolds Electrical & Engineering Co., Inc., by G. M. Kelly, ICF Technology, Subject: greater confinement disposal, March.

Winograd, I.J. and W. Thordarson, 1975. "Hydrogeologic and Hydrochemical Framework, South-central Great Basin, Nevada-California, with Special Reference to the Nevada Test Site," U.S. Geological Survey Professional Paper 712-C, U.S. Geological Survey, Washington, D.C.

PRELIMINARY

PRELIMINARY

APPENDIX A
SURVEY PARTICIPANTS

NEVADA TEST SITE SURVEY PARTICIPANTS
JUNE 22 THROUGH JULY 10, 1987

DOE

Team Leader: T. T. Traceski
Assistant Team Leader: D. A. Bergman
Operations Office Representative: F. E. Bingham

NUS

Coordinator/Surface Water: R. E. Tarbert
Toxic Materials/QA: R. C. Gerlach
Air: T. F. Eckle
Radiation: J. D. Yesso
Hydrogeology: M. S. Robison

ICF

Waste Management: G. M. Kelly
Inactive Waste Sites: R. L. Scullin

APPENDIX B
SURVEY PLAN

PRELIMINARY

ENVIRONMENTAL SURVEY PLAN

NEVADA TEST SITE

JUNE 22 - JULY 10, 1987

MERCURY, NEVADA

1.0 INTRODUCTION

The Nevada Test Site (NTS) Environmental Survey is part of the larger Department of Energy (DOE)-wide Environmental Survey effort announced by Secretary John S. Herrington on September 18, 1985. The purpose of this effort is to identify, via "no fault" baseline Surveys, existing environmental problems and areas of environmental risk at DOE facilities, and to rank them on a DOE-wide basis. This ranking will enable DOE to more effectively establish priorities for addressing environmental problems and allocate the resources necessary to correct these problems. Because the Survey is "no fault" and is not an "audit", it is not designed to identify specific isolated incidents of noncompliance, or to analyze environmental management practices. Such incidents and/or management practices will, however, be used in the Survey as a means of identifying existing and potential environmental problems.

The NTS Survey will be conducted in accordance with the protocols and procedures contained in the May 16, 1986, Environmental Survey Manual.

2.0 SURVEY IMPLEMENTATION

The Environmental Survey of the Nevada Test Site (NTS) will be managed by the DOE Team Leader, Thomas Traceski and the Assistant Team Leader, Donna Bergman. Frank Bingham will serve as the Nevada Operations Office (NVO) representative on the Environmental Survey team. Technical support is provided by NUS Corporation and ICF Corporation personnel as follows:

Richard Tarbert	NUS Coordinator/Surface Water
David Yesso	Assistant NUS Coordinator/Radiation
Richard Gerlach	QA/TSCA (Toxic Materials)
Tom Eckle	Air
Gerard Kelly	RCRA/Solid Waste
Ronald Scullin	CERCLA (Inactive Waste Sites)
Mary Robison	Hydrogeology/Soil

2.1 Pre-Survey Activities

Pre-Survey activities began in March 1987, when the DOE Team Leader and Assistant Team Leader initiated reviews of NTS environmental documents that were available at the DOE Office of Environmental Audit (OEV). This review was followed by a March 20, 1987, memorandum from OEV to the Nevada Operations Office (NVO) and the Nevada Test Site (NTS) announcing a pre-Survey site visit and requesting additional Survey-related information. The technical specialists began their review of the documents available at OEV in early May 1987. The purpose of the review of that material was to allow the Survey team members to gain familiarity with NTS and prepare themselves for the pre-Survey site visit.

The nine members of the Survey team conducted the pre-Survey site visit on May 5 and 6, 1987. The visit was scheduled to allow team members an opportunity to gain initial familiarity with the site, identify potential areas of environmental concern for purposes of the Survey, explain the objectives and methodology of the Survey, collect the documents requested in the March 20, 1987 memorandum, and coordinate plans for the upcoming Survey with NVO and NTS personnel. Mr. Kevin Flynn, Argonne National Laboratory, who will coordinate the sampling and analysis phase of the Survey, also attended the pre-Survey site visit.

During the pre-Survey site visit, team members were provided with briefings by NVO and NTS personnel on the NVO/NTS organization, operations, and activities; some of the pertinent environmental issues; plant security; safety; industrial hygiene; and the site environmental monitoring programs. Of particular value to the team were tours of the on-site waste management facilities, and operations facilities. Due to time constraints, we were not able to complete the scheduled tour of NTS during the pre-Survey site visit. (The tour is scheduled to be completed during the first day of the on-site Survey.) Prior to the tours, team members had an opportunity to review the environmental documents that had been assembled by NTS and NVO personnel. Arrangements were made to have the collected materials shipped to the NUS offices in Pittsburgh. All of the documents that were assembled in response to the memorandum of March 20, 1987 and requested during the pre-Survey site visit have been received. This Survey plan is based upon material received by the Survey team through the end of May 1987.

On May 7, 1987, Ms. Bergman, Messrs. Traceski and Yesso met with representatives of NVO, and officials of the Nevada Department of Conservation and Natural Resources and Nevada Division of Health. This meeting was

scheduled to explain the purposes of the Survey to the Regional EPA and state personnel and to allow them to express their concerns over the environmental condition of NTS. Representatives of EPA Region IX did not attend the meeting, but provided several concerns telephonically to the NVO representative on the Survey team.

The Survey was provided with a Road and Facility map which was used in the preparation of this Survey plan. The map is reproduced here as Figure 2-1.

2.2 On-Site Activities and Reports

The on-site portion of the Environmental Survey will be conducted over a three (3) week period from June 22, 1987 through July 10, 1987. A brief (about 30 minutes) introductory meeting will be held on the first day between the Survey team, NVO management and the various operating contract managers at NTS to introduce the team members and review the objectives and methodology of the Survey. A proposed agenda for the start of the on-site portion of the Survey is presented in Table 2-1. The Survey will include all facilities and areas associated with NTS operations including those located in Las Vegas. A tentative agenda is shown in Table 2-2. While members of the Survey team continue reviewing the documents prior to the Survey, and during the actual site visit, it is expected that modifications to the agenda will be made as appropriate to minimize disruption of site activities, as well as to enhance Survey efficiency and effectiveness. All modifications to the agenda will be coordinated with the site officials designated as Survey contacts. A summary of the Survey agenda is shown in Table 2-3.

The on-site activities of the Survey team will consist of interviews and consultations with, among others, environmental, industrial hygiene, safety,

Figure 2-1

**TABLE 2-1
DETAILED AGENDA FOR
MONDAY, JUNE 22, 1987**

8:00 - 8:30	Introduction <ul style="list-style-type: none"> o Survey Team o Survey Activities o Interim Briefings and Closeout Meeting 	Survey Team Leader
8:30 - 9:00	Overview and Corrective Actions Underway or Planned of Environmental Problems by NVO	NVO
9:05 - 9:45	Safety Training Film	
10:00 - 11:30	Tour Las Vegas Support Facilities	NVO/Survey Team
11:30 - 12:00	Lunch (Fast Food)	
12:00 - 1:30	Travel to NTS	
1:30 - Open	Tour Following Areas at NTS <ul style="list-style-type: none"> Area 7 - Tanks and Ponds Area 3 - Radioactive Waste Management Site Area 5 - Radionuclide Migration Study Site Spill Test Facility Area 23 - Disposal Pits and Sewage Lagoons 	

TABLE 2-2
INDIVIDUAL AGENDAS

T. ECKLE - AIR

MONDAY, JUNE 22	TUESDAY, JUNE 23	WEDNESDAY, JUNE 24	THURSDAY, JUNE 25	FRIDAY, JUNE 26
<p>AM</p> <ul style="list-style-type: none"> - Introductory Meeting at NVO - Tour Las Vegas Fac. <p>PH</p> <ul style="list-style-type: none"> - Tour NTS: - 7-Tanks & Ponds - 3-RMS - 5-RHM, Spill Test Facility - 23-Disposal Pits, Sewage Lagoons 	<ul style="list-style-type: none"> - Tour Area 22 incld. Avgas or Jet Fuel Storage - Liaison: - Tour Area 23 incld. - 925 Boiler (Bldg. 753) - 1086 & 1087 Fuel Tanks - Liaison: O. Haworth A. Frazier 	<p>AM</p> <ul style="list-style-type: none"> - Tour Area 5 incld. Spill Test Facility, OP 921 Surface Area - Disturbance, Cane Springs Test Area - Liaison: O. Haworth <p>PM</p> <ul style="list-style-type: none"> - Review Documents 	<ul style="list-style-type: none"> - Visit Facilities in Las Vegas - Liaison: Appropriate Area Operators - ENSL Off-Site Monitoring - Liaison: Appropriate Area Operators 	<ul style="list-style-type: none"> - Tour Area 6 incld. - Boiler OP 1036 - FO Tank OP 1085 - Gas Tank OP 1090 - Device Assembly RC974 (Surface Disturbance) - Concrete Batch OP 918 - Liaison: O. Haworth A. Frazier
MONDAY, JUNE 29	TUESDAY, JUNE 30	WEDNESDAY, JULY 1	THURSDAY, JULY 2	FRIDAY, JULY 3
<ul style="list-style-type: none"> - Tour Area 3 incld. - 919 Aggregate Plant - 1089 Stemming Facility - Discuss Stemming - Liaison: O. Haworth 	<p>AM</p> <ul style="list-style-type: none"> - REECO - Observe & Discuss Air Monitoring On-Site - Liaison: D. Gonzalez B. Smith <p>PH</p> <ul style="list-style-type: none"> - NVA - Discuss Met Data Acquisition & Use Before & After Test - Liaison: Appropriate Area Operators 	<p>AM</p> <ul style="list-style-type: none"> - Discuss NREG & RIDP (View Selected Sites) - Liaison: L. Anspaugh <p>PH</p> <ul style="list-style-type: none"> - Prepare for Team Meeting - Additional Document Review 	<ul style="list-style-type: none"> - Tour Area 1 incld. - 922 & 923 Shaker Plant - Coal-tar Fac. & 1287 Aggregate Plant, Pu-Con-taminated Area - 1082 Concrete Pit - 1084 Surface Dis-turbance - 1217 Crusher - Space Heating? - Liaison: O. Haworth, A. Frazier 	<ul style="list-style-type: none"> - Team Meeting
MONDAY, JULY 6	TUESDAY, JULY 7	WEDNESDAY, JULY 8	THURSDAY, JULY 9	FRIDAY, JULY 10
<ul style="list-style-type: none"> - Tour Area 2 includ. Stemming Facilities - UP 957 - OP958 - Liaison: O. Haworth - Discuss Permits incl - 1035 Superior Boiler - RC1367 Surface Disturbances (Prep Test Shots) - 87-5 Open Burning - 87-37 Open Burning 	<ul style="list-style-type: none"> - Tour Area 12 incld. - Concrete Batch Plant, OP928 - Discuss Tunnel Backfilling for Env. Control - Space Heating? - Liaison: O. Haworth - Tour Area ? incld. - Observe Drilling Activity - Liaison: O. Haworth 	<ul style="list-style-type: none"> - Technical Briefing with NVO/NTS Environmental Staff - Draft S&A Requests - Catch-up on Un-finished Items 	<ul style="list-style-type: none"> - Coordinate with S&A Team Leader - Resolution of Ques-tions from Status Meeting 	<ul style="list-style-type: none"> - Closeout Meeting

R. TARBERT - SURFACE WATER

Table 2-2 (Continued)

MONDAY, JUNE 22	TUESDAY, JUNE 23	WEDNESDAY, JUNE 24	THURSDAY, JUNE 25	FRIDAY, JUNE 26
<p>AM</p> <ul style="list-style-type: none"> - Introductory Meeting at NVO - Tour Las Vegas Facilities <p>PM</p> <ul style="list-style-type: none"> - Tour NIS: <ul style="list-style-type: none"> - 7-Tanks & Ponds - 3-RHMS - 5-RHM, Spill Test Facility - 23-Disposal Pits, Sewage Lagoons 	<p>AM</p> <ul style="list-style-type: none"> - Tour Area 12 incld. N-Tunnel & Ponds; Water & Sewer System Springs <p>Liaison: Appropriate Area Operators</p> <p>PM</p> <ul style="list-style-type: none"> - Discuss NTS Water & Sewer Systems with REECO Personnel <p>Liaison: Bullock Bolton</p>	<ul style="list-style-type: none"> - Tour Areas 6 & 11 incld. Water & Sewer Systems <p>Liaison: Appropriate Area Operators</p>	<ul style="list-style-type: none"> - Tour Ash Meadow Discharge Area, Lathrop Wells <p>Liaison: R. Jacobson</p>	<ul style="list-style-type: none"> - Tour Areas 22 and 23 incld. Water & Sewer System <p>Liaison: Appropriate Area Operators</p>
MONDAY, JUNE 29	TUESDAY, JUNE 30	WEDNESDAY, JULY 1	THURSDAY, JULY 2	FRIDAY, JULY 3
<ul style="list-style-type: none"> - Tour Areas 14,18,19, 20,29 & 30 incld. Water & Sewer Systems, Springs <p>Liaison: Appropriate Area Operators</p>	<ul style="list-style-type: none"> - Tour Areas 2,4,7,8, 9,10,15 & 17 incld. Water & Sewer System, Springs <p>Liaison: Appropriate Area Operators</p>	<ul style="list-style-type: none"> - Tour Area 25 incld. Water & Sewer System <p>Liaison: Appropriate Area Operators</p>	<ul style="list-style-type: none"> - Tour Areas 1,3, & 16 incld. Water & Sewer System, Springs <p>Liaison: Appropriate Area Operators</p>	<ul style="list-style-type: none"> - Team Meeting
MONDAY, JULY 6	TUESDAY, JULY 7	WEDNESDAY, JULY 8	THURSDAY, JULY 9	FRIDAY, JULY 10
<ul style="list-style-type: none"> - Investigate Las Vegas Facilities Water & Sewer System <p>Liaison: Appropriate Operators</p>	<ul style="list-style-type: none"> - Tour Areas 5,26 & 27 incld. Water & Sewer Facilities, Springs <p>Liaison: Appropriate Area Operators</p>	<ul style="list-style-type: none"> - Technical Briefing with NVO/NTS Environmental Staff - Coordinate with S&A Team Leader 	<ul style="list-style-type: none"> - Complete Unfinished Investigations 	<ul style="list-style-type: none"> - Closeout Meeting

M. ROBISON - HYDROGEOLOGY

Table 2-2 (Continued)

MONDAY, JUNE 22	TUESDAY, JUNE 23	WEDNESDAY, JUNE 24	THURSDAY, JUNE 25	FRIDAY, JUNE 26
<p>AN</p> <ul style="list-style-type: none"> - Introductory Meeting at NVO - Tour Las Vegas Fac. <p>PH</p> <ul style="list-style-type: none"> - Tour NTS: <ul style="list-style-type: none"> - 7-Tanks & Ponds - 3-RWMS - 5-RRM, Spill Test Facility - 23-Disposal Pits, Sewage Lagoons 	<ul style="list-style-type: none"> - Tour Area 12 incld. N-Tunnel, Tunnel Ponds & Muck Piles <p>Liaison: J. Metcalf, Sgt Wallace</p> <ul style="list-style-type: none"> - Tour Area 15 (Farm, muck pile) - Discuss Area 8 Liquid Disp. Sites & other Injection Wells - Tour Area 16 (Consolidation Site) <p>Liaison: Approp. Area Op.</p>	<ul style="list-style-type: none"> - Tour Area 25 <p>Liaison: D. McGrath or P. Dickman</p>	<ul style="list-style-type: none"> - Tour Ash Meadows Lathrop Wells <p>Liaison: R. Jacobson</p>	<ul style="list-style-type: none"> - Tour Area 5 RWMS - Tour Area 3 RWMS <p>Liaison: G. Kendall or P. Dickman</p>
MONDAY, JUNE 29	TUESDAY, JUNE 30	WEDNESDAY, JULY 1	THURSDAY, JULY 2	FRIDAY, JULY 3
<ul style="list-style-type: none"> - Tour Areas 14, 18, 19, 20, 29 & 30 incld. Springs <p>Liaison: Appropriate Area Operators</p>	<ul style="list-style-type: none"> - Tour Areas 2, 4, 7, 8, 9, 10 & 17 <p>Liaison: D. McGrath or Appropriate Area Operators</p>	<ul style="list-style-type: none"> - Meet on RWH, NAEG, RIDP <p>Liaisons: L. Anspaugh, J. Burrows</p>	<ul style="list-style-type: none"> - Observe Well Sampling <p>Liaison: D. McGrath or Sampling Team Leader</p>	<ul style="list-style-type: none"> - Team Meeting
MONDAY, JULY 6	TUESDAY, JULY 7	WEDNESDAY, JULY 8	THURSDAY, JULY 9	FRIDAY, JULY 10
<ul style="list-style-type: none"> - Tour Areas 22, 23 & 26 <p>Liaison: D. McGrath</p>	<ul style="list-style-type: none"> - Catch-up day 	<ul style="list-style-type: none"> - Technical Briefing with NVO/NTS Environmental Staff 	<ul style="list-style-type: none"> - Coordinate with S&A Team Leader 	<ul style="list-style-type: none"> - Closeout Meeting

6. KELLY - WASTE MANAGEMENT

Table 2-2 (continued)

MONDAY, JUNE 22	TUESDAY, JUNE 23	WEDNESDAY, JUNE 24	THURSDAY, JUNE 25	FRIDAY, JUNE 26
<p>AFI</p> <ul style="list-style-type: none"> - Introductory Meeting at NVO - Tour Las Vegas Fac. <p>PM</p> <ul style="list-style-type: none"> - Tour NTS: <ul style="list-style-type: none"> - 7-Tanks & Ponds - 3-RUMS - 5-RWM, Spill Test Facility - 23-Disposal Pits, Sewage Lagoons 	<ul style="list-style-type: none"> - Tour Areas 12,15,& 16 incld. Trench Ponds & Huck Piles <p>Liaison: Appropriate Area Operators</p>	<ul style="list-style-type: none"> - Tour Area 25 <p>Liaison: Appropriate Area Operators</p>	<ul style="list-style-type: none"> - Tour Las Vegas Facilities <p>Liaison: F. Bingham</p>	<ul style="list-style-type: none"> - Tour Areas 3 & 5 incld. RWM <p>Liaison: G. Kendall (Substitutes: P. Dickman, D. McGrath)</p>
MONDAY, JUNE 29	TUESDAY, JUNE 30	WEDNESDAY, JULY 1	THURSDAY, JULY 2	FRIDAY, JULY 3
<ul style="list-style-type: none"> - Tour Area 27 <p>Liaison: O. Haworth (Substitutes: D. Bullock, A. Frazier)</p>	<ul style="list-style-type: none"> - Tour Areas 7,8 & 9 <p>Liaison: O. Haworth G. Kendall</p>	<ul style="list-style-type: none"> - Tour Areas 5,6, & 11 <p>Liaison: O. Haworth G. Kendall</p>	<ul style="list-style-type: none"> - Tour Areas 1,2,3 & 4 <p>Liaison: O. Haworth G. Kendall</p>	<ul style="list-style-type: none"> - Team Meeting
MONDAY, JULY 6	TUESDAY, JULY 7	WEDNESDAY, JULY 8	THURSDAY, JULY 9	FRIDAY, JULY 10
<ul style="list-style-type: none"> - Tour Areas 22,23 & 26 <p>Liaison: O. Haworth G. Kendall</p>	<ul style="list-style-type: none"> - Tour Areas 19 & 20 <p>Liaison: O. Haworth</p> <ul style="list-style-type: none"> - Catch-up 	<ul style="list-style-type: none"> - Technical Briefing with NVO/NTS - Environmental Staff - Records Review - Preparation of S&A Needs 	<ul style="list-style-type: none"> - Records Review - Catch-up - Findings Preparation 	<ul style="list-style-type: none"> - Closeout Meeting

MONDAY, JUNE 22	TUESDAY, JUNE 23	WEDNESDAY, JUNE 24	THURSDAY, JUNE 25	FRIDAY, JUNE 26
<u>AM</u> - Introductory Meeting at NVO - Tour Las Vegas Fac. <u>PM</u> - Tour NTS: - 7-Tanks & Ponds - 3-RWMS - 5-RNM, Spill Test Facility - 23-Disposal Pits, Sewage Lagoons	<u>AM/PM</u> - Inspect PCB Electrical Equipment Liaison: J. Kim.	<u>AM</u> - Review Inspection Records for PCB Electrical Equip. Liaison: J. Kim <u>PM</u> - Inspect PCB Waste Storage Areas (e.g. Area-6) & Review Associated Records Liaison: O. Haworth	<u>AM/PM</u> - Tour EMSL - Review Monitoring Data/QA Records Liaison: S. Black	<u>AM/PM</u> - Tour Underground and Above Ground Storage Tank Areas (Areas 6,12 and Other Areas) Liaison: O. Haworth
MONDAY, JUNE 29	TUESDAY, JUNE 30	WEDNESDAY, JULY 1	THURSDAY, JULY 2	FRIDAY, JULY 3
<u>AM/PM</u> - Tour Underground & Above Ground Storage Tank Areas (Areas 22, 23, 25, 27 & Other Areas) Liaison: O. Haworth	- Tour Spill Test Facility (Area 5) Liaison: O. Haworth - Review Tank Maintenance & Spill Containment Programs Liaison: O. Haworth	<u>AM</u> - Tour Area 23 Steam Plant, Theatre Warehouse & Cafeteria regarding Asbestos - Tour Other Asbestos Areas - Tour Asbestos Disposal Sites (e.g. Area 10) <u>PM</u> - Review NTS Asbestos Control Program Liaison: Haworth, Bullock	<u>AM/PM</u> - Review NTS Pesticide Program - Inspect Pesticide Application & Storage Areas Liaison: D. Bullock	- Team Meeting
MONDAY, JULY 6	TUESDAY, JULY 7	WEDNESDAY, JULY 8	THURSDAY, JULY 9	FRIDAY, JULY 10
<u>AM</u> - Review NTS Sampling & Analysis QA Programs Liaison: R.E. Williams <u>PM</u> - Tour REECO Radioisotope & Industrial hygiene labs Liaison: R.E. Williams	<u>AM/PM</u> - Review NTS Toxic/Hazardous Materials Purchasing, Storage & Use Systems Liaison: O. Haworth S. Lopez D. Thompson	- Technical Briefing with NVO/NTS Environmental Staff	- Coordinate with S&A Team Leader	- Closeout Meeting

D. YESSO - RADIATION

Table 2-2 (continued)

MONDAY, JUNE 22	TUESDAY, JUNE 23	WEDNESDAY, JUNE 24	THURSDAY, JUNE 25	FRIDAY, JUNE 26
<p>AM</p> <ul style="list-style-type: none"> - Introductory Meeting at NVO - Tour Las Vegas Fac. <p>PM</p> <ul style="list-style-type: none"> - Tour NTS: <ul style="list-style-type: none"> - 7-Tanks & Ponds - 3-RWMS - 5-RNM, Spill Test Facility - 23-Disposal Pits, Sewage Lagoons 	<p>AM</p> <ul style="list-style-type: none"> - Tour N-Tunnel & Ponds <p>Liaison: Appropriate Area Operators</p> <p>PM</p> <ul style="list-style-type: none"> - Tour Areas 12, 15, 16 incld. Waste Consolidation Sites, DOE/EPA Farm <p>Liaison: Appropriate Area Operators</p>	<ul style="list-style-type: none"> - Area 25 incld. E-MAD, R-MAD, BREN, Reactor Test Cells <p>Liaison: Appropriate Area Operators</p>	<p>AM</p> <ul style="list-style-type: none"> - Tour EMSL - Discuss Off-Site Environmental Monitoring Program - View Off-Site Monitoring Station at Univ. Nevada - Review Monitoring Data/QA Records <p>Liaison: Stewart Black</p>	<ul style="list-style-type: none"> - Tour Area 5 - Rad-waste Management Site <p>Liaison: Appropriate Area Operators</p> <ul style="list-style-type: none"> - Tour Area 3 - Rad-waste Management Site <p>Liaison: Appropriate Area Operators</p>
MONDAY, JUNE 29	TUESDAY, JUNE 30	WEDNESDAY, JULY 1	THURSDAY, JULY 2	FRIDAY, JULY 3
<p>AM</p> <ul style="list-style-type: none"> - Tour Area 3 incld. Stemming Facility, Discuss Stemming <p>Liaison: Appropriate Area Operators</p> <p>PM</p> <ul style="list-style-type: none"> - Tour Area 26 <p>Liaison: Appropriate Area Operators</p>	<p>AM</p> <ul style="list-style-type: none"> - Observe & Discuss On-Site Air Monitoring <p>Liaison: Appropriate Area Operators</p> <p>PM</p> <ul style="list-style-type: none"> - Review Documents <p>Liaison: Appropriate Area Operators</p>	<p>AM</p> <ul style="list-style-type: none"> - On-site Meetings to discuss RNM, RIDP, NAEG (view sites selected by Liaison) <p>Liaison: L. Ansbaugh</p>	<ul style="list-style-type: none"> - Discuss BECAMP - Discuss Past-Test Drillback Activities - Tunnel Venting & Related Monitoring - Discuss Test Cavity Radionuclide Inventories <p>Liaison: F. Bingham</p>	<ul style="list-style-type: none"> - Team Meetings - Review Environmental Monitoring Records
MONDAY, JULY 6	TUESDAY, JULY 7	WEDNESDAY, JULY 8	THURSDAY, JULY 9	FRIDAY, JULY 10
<ul style="list-style-type: none"> - Review On-Site Monitoring Programs - Tour On-Site Environmental Labs - Review Monitoring Data/QA Records <p>Liaison: F.B. Johns</p>	<ul style="list-style-type: none"> - Review Records - Catch-up on Unfinished Business 	<ul style="list-style-type: none"> - Technical Briefing with NVO/NTS Environmental Staff - Coordinate with S&A Team 	<ul style="list-style-type: none"> - Catch-up on Unfinished Business - Prepare for Closeout 	<ul style="list-style-type: none"> - Closeout Meeting

R. SCULLIN - INACTIVE WASTE/SPILLS

Table 2-2 (continued)

MONDAY, JUNE 22	TUESDAY, JUNE 23	WEDNESDAY, JUNE 24	THURSDAY, JUNE 25	FRIDAY, JUNE 26
<p>AM</p> <ul style="list-style-type: none"> - Introductory Meeting at NVU - Tour Las Vegas Fac. <p>PM</p> <ul style="list-style-type: none"> - Tour NTS: <ul style="list-style-type: none"> - 7-Tanks & Ponds - 3-RWMS - 5-RWMS Spill Test Facility - 23-Disposal Pits, Sewage Lagoons 	<p>AM</p> <ul style="list-style-type: none"> - Tour N-Tunnel Liaison: <p>PM</p> <ul style="list-style-type: none"> - Tour Areas 12,15,& 16 incld. CWD, CMP, CON, CST, EPA/DOE Exp Farm, Spent Fuel Test Site, & Oak Spring/Climax Liaison: O. Haworth 	<ul style="list-style-type: none"> - Tour Area 25 incld. CST, CWD, UST, COL, LFP, E-MAD, R-MAD, Test Cells A & C, Engine Test Stand No. 1, & BREN Tower Liaison: O. Haworth 	<ul style="list-style-type: none"> - Tour Area 25 (continued) Liaison: O. Haworth (if conflict w/on-site activities, switch with 6/30 agenda) 	<ul style="list-style-type: none"> - Tour Areas 5,22,23 & 27 incld. CON, UST, LFP, WSW, Exclusion Area, Spill Test Fac, Sand Spring Test Range, Desert Rock Airstrip (fuel leak), Chemical & Medical Waste Trenches, & Hazardous Waste Land-fill "A", "B" & "C". Liaison: O. Haworth
MONDAY, JUNE 29	TUESDAY, JUNE 30	WEDNESDAY, JULY 1	THURSDAY, JULY 2	FRIDAY, JULY 3
<p>AM</p> <ul style="list-style-type: none"> - Tour Areas 6,11 incld. CON, LFP, UST, CWD, Abandoned Transmitter Site, & Explosive Ordnance Disposal Area Liaison: O. Haworth <p>PM</p> <ul style="list-style-type: none"> - Tour Area 26 incld. CST, CWD, LFP, & Horn Silver Mine Shaft Liaison: O. Haworth 	<ul style="list-style-type: none"> - Review Enviro. Records and Aerial Photos 	<ul style="list-style-type: none"> - On-Site Mtg. with DOE Area Office Counterpart - CERCLA - Continue Review of Enviro. Records & Aerial Photos 	<ul style="list-style-type: none"> - Tour Areas 1,2,3,4, 7 & 9 incld. CON, LFP, Decon. Pad Sump "BJY", & CMD. Liaison: O. Haworth 	<ul style="list-style-type: none"> - Team Meeting
MONDAY, JULY 6	TUESDAY, JULY 7	WEDNESDAY, JULY 8	THURSDAY, JULY 9	FRIDAY, JULY 10
<ul style="list-style-type: none"> - Tour Other Sites as appropriate 	<ul style="list-style-type: none"> - Review Enviro. Records - Begin S&A Plan 	<ul style="list-style-type: none"> - Technical Briefing with NVO/NTS Environmental Staff - Coordinate with S&A Team Leader 	<ul style="list-style-type: none"> - Complete Unfinished Investigations 	<ul style="list-style-type: none"> - Closeout Meeting

TABLE 2-3

NEVADA TEST SITE SURVEY
SUMMARY SITE - SURVEY AGENDA
JUNE 22 - JULY 10, 1987

	AIR	WATER	HYDROGEOLOGY SOIL	INACTIVE WASTE/ SPILLS	HAZARDOUS/ SOLID WASTE	QA/TSCA	RAD
MONDAY JUNE 22, 1987	AM - Introductory Meeting at NVO - Tour Las Vegas Fac. PM - Tour MTS: - 7-Tanks & Ponds - 3-RAMS - 5-RAM, Spill Test Facility - 23-Disposal Pits, Sewage Lagoons	AM - Introductory Meeting at NVO - Tour Las Vegas Facilities PM - Tour MTS: - 7-Tanks & Ponds - 3-RAMS - 5-RAM, Spill Test Facility - 23-Disposal Pits, Sewage Lagoons	AM - Introductory Meeting at NVO - Tour Las Vegas Fac. PM - Tour MTS: - 7-Tanks & Ponds - 3-RAMS - 5-RAM, Spill Test Facility - 23-Disposal Pits, Sewage Lagoons	AM - Introductory Meeting at NVO - Tour Las Vegas Fac. PM - Tour MTS: - 7-Tanks & Ponds - 3-RAMS - 5-RAM, Spill Test Facility - 23-Disposal Pits, Sewage Lagoons	AM - Introductory Meeting at NVO - Tour Las Vegas Fac. PM - Tour MTS: - 7-Tanks & Ponds - 3-RAMS - 5-RAM, Spill Test Facility - 23-Disposal Pits, Sewage Lagoons	AM - Introductory Meeting at NVO - Tour Las Vegas Fac. PM - Tour MTS: - 7-Tanks & Ponds - 3-RAMS - 5-RAM, Spill Test Facility - 23-Disposal Pits, Sewage Lagoons	AM - Introductory Meeting at NVO - Tour Las Vegas Fac. PM - Tour MTS: - 7-Tanks & Ponds - 3-RAMS - 5-RAM, Spill Test Facility - 23-Disposal Pits, Sewage Lagoons
TUESDAY JUNE 23, 1987	AM - Tour Area 22 incl. Avgas or Jet Fuel Storage Liaison: - Tour Area 23 incl. 925 Boiler (Bldg. 753) - 1006 & 1007 Fuel Tanks Liaison: O. Haworth A. Frazier	AM - Tour Area 12 incl. M-Tunnel & Ponds; Water & Sewer System Springs Liaison: Appropriate Area Operators PM - Discuss MTS Water & Sewer Systems with REECO Personnel Liaison: Bullock Bolton	AM - Tour Area 12 incl. M-Tunnel, Tunnel Ponds & Muck Piles Liaison: J. Metcalf, Sgt Wallace - Tour Area 15 (Farm, muck pile) - Discuss Area 8 Liquid Disp. Sites & other Injection Wells - Tour Area 16 (Con-Solidation Site) Liaison: Apporo, Area Op.	AM - Tour H-Tunnel Liaison: PM - Tour Areas 12, 15, & 16 incl. CMD, CMP, COM, CST, EPA/DOE Exp. Farm, Spent Fuel Test Site, & Oak Spring/Clinch Liaison: O. Haworth	AM - Tour Areas 12, 15, & 16 incl. Trench Ponds & Muck Piles Liaison: Appropriate Area Operators	AM/PM - Inspect PCB Electrical Equipment Liaison: J. Kim	AM - Tour H-Tunnel & Pond Liaison: Appropriate Area Operators PM - Tour Areas 12, 15, 16 incl. Waste Consolidation Sites, DOE/EPA Farm Liaison: Appropriate Area Operators
WEDNESDAY JUNE 24, 1987	AM - Tour Area 5 incl. Spill Test Facility, OP 921 Surface Area Disturbance, Cane Springs Test Area Liaison: O. Haworth PM - Review Documents	AM - Tour Areas 6 & 11 incl. Water & Sewer Systems Liaison: Appropriate Area Operators	AM - Tour Area 25 Liaison: D. McGrath or P. Dickman	AM - Tour Area 25 incl. CST, CMD, UST, COL LFP, E-MAD, R-MAD, Test Cells A & C, Engine Test Stand No. 1, & BREN Tower Liaison: O. Haworth	AM - Tour Area 25 Liaison: Appropriate Area Operators	AM - Review Inspection Records for PCB Electrical Equip. Liaison: J. Kim PM - Inspect PCB Waste Storage Areas (e.g. Area 6) & Review Associated Records Liaison: O. Haworth	AM - Area 25 incl. E-MAD R-MAD, BREN, Reactor Test Cells Liaison: Appropriate Area Operators

TABLE 2-3 (continued)

	AIR	WATER	SOIL	SPILLS	SOLID WASTE	QM/TSCA	RAD
THURSDAY JUNE 25, 1987	<ul style="list-style-type: none">- Visit Facilities in Las Vegas- Emsl Off-Site Monitoring- Liaison: Appropriate Area Operators	<ul style="list-style-type: none">- Tour Ash Meadow Discharge Area, Lathrop Mills- Liaison: R. Jacobson	<ul style="list-style-type: none">- Tour Ash Meadows Lathrop Mills- Liaison: R. Jacobson	<ul style="list-style-type: none">- Tour Area 25 (continues)- Liaison: O. Haworth(if conflict w/on-site activities, switch with 6/30 agenda)	<ul style="list-style-type: none">- Tour Las Vegas Facilities- Liaison: F. Bingham	<u>AM/PM</u> <ul style="list-style-type: none">- Review Monitoring Data/QA Records- Liaison: S. Black	<u>AM</u> <ul style="list-style-type: none">- Tour Emsl- Discuss Off-Site Environmental Monitoring Program- View Off-Site Monitoring Station at Univ. Nevada- Review Monitoring Data/QA Records- Liaison: Stewart Black
FRIDAY JUNE 26, 1987	<ul style="list-style-type: none">- Tour Area 6 incld.- Boiler OP 1036- FO Tank OP 1085- Gas Tank OP 1090- Device Assembly- MC374 (Surface Disturbance)- Concrete Batch OP 918- Liaison: U. Haworth A. Frazier	<ul style="list-style-type: none">- Tour Areas 22 and 23 incld. Water & Sewer System- Liaison: Appropriate Area Operators	<ul style="list-style-type: none">- Tour Area 5 RIMS- Tour Area 3 RIMS- Liaison: G. Kendall or P. Dickman	<ul style="list-style-type: none">- Tour Areas 5, 22, 23 & 27 incld. COM, UST, LFP, MSM, Exclusion Area, Spill, Test Fac, Sand Spring Test Ranges, Upper Rock Alkydrip (Cool Leak), Chemical & Medical Waste Trenches, & Hazardous Waste Land fill 14, 18, 19, 20, 29 & 30- Liaison: O. Haworth	<ul style="list-style-type: none">- Tour Areas 3 & 5 incld. RIM- Liaison: G. Kendall (Substitutes: P. Dickman, D. McGrath)	<u>AM/PM</u> <ul style="list-style-type: none">- Tour Underground and Above Ground Storage Tank Areas (Areas 6, 12 and Other Areas)- Liaison: O. Haworth	<ul style="list-style-type: none">- Tour Area 5 - Rad-waste Management Site- Liaison: Appropriate Area Operators- Tour Area 6- Waste Management Site- Liaison: Appropriate Area Operators
MONDAY JUNE 29, 1987	<ul style="list-style-type: none">- Tour Area 3 incld.- 919 Aggregate Plant- 1089 Stemming Facility- Discuss Stemming- Liaison: O. Haworth	<ul style="list-style-type: none">- Tour Areas 14, 18, 19, 20, 29 & 30 incld. Water & Sewer System- Springs- Liaison: Appropriate Area Operators	<ul style="list-style-type: none">- Tour Areas 14, 18, 19, 20, 29 & 30 incld. Springs- Springs- Area Operators	<u>AM</u> <ul style="list-style-type: none">- Tour Areas 6, 11 incld. COM, LFP, UST, CMO, Abandoned Transmitter Site, & Explosive Ordnance Disposal Area- Liaison: U. Haworth <u>PH</u> <ul style="list-style-type: none">- Tour Area 26 incld. CST, CMO, LFP, & Horn Silver Mine Shaft- Liaison: O. Haworth	<ul style="list-style-type: none">- Tour Area 27- Liaison: O. Haworth (Substitutes: O. Buillock, A. Frazier)	<u>AM/PM</u> <ul style="list-style-type: none">- Tour Underground & Above Ground Storage Tank Areas (Areas 22, 23, 25, 27 & Other Areas)- Liaison: O. Haworth	<u>AM</u> <ul style="list-style-type: none">- Tour Area 3 incld. Stemming Facility- Discuss Stemming- Liaison: Appropriate Area Operators <u>PH</u> <ul style="list-style-type: none">- Tour Area 26- Liaison: Appropriate Area Operators

TABLE 2-3 (continued)

	AIR	WATER	HYDROGEOLOGY SOIL	INACTIVE WASTE/ SPILLS	HAZARDOUS/ SOLID WASTE	QA/TSCA	RAD
TUESDAY JUNE 30, 1987	<p>AM</p> <ul style="list-style-type: none"> - RECO - Observe & Discuss Air Monitoring On-Site Liaison: D. Gonzalez B. Smith <p>PM</p> <ul style="list-style-type: none"> - HUA - Discuss Met Data Acquisition & Use Before & After Test Liaison: Appropriate Area Operators 	<ul style="list-style-type: none"> - Tour Areas 2, 4, 7, 8, 9, 10, 15 & 17 incld. Water & Sewer System Springs Liaison: Appropriate Area Operators 	<ul style="list-style-type: none"> - Tour Areas 2, 4, 7, 8, 9, 10, 15 & 17 incld. Water & Sewer System Springs Liaison: Appropriate Area Operators 	<ul style="list-style-type: none"> - Review Enviro. Records and Aerial Photos 	<ul style="list-style-type: none"> - Tour Areas 7, 8 & 9 Liaison: O. Haworth G. Kendall 	<ul style="list-style-type: none"> - Tour Spill Test Facility (Area 5) Liaison: O. Haworth <ul style="list-style-type: none"> - Review Tank Maintenance & Spill Containment Programs Liaison: O. Haworth 	<p>AM</p> <ul style="list-style-type: none"> - Observe & Discuss On-Site Air Monitoring Liaison: Appropriate Area Operators <p>PM</p> <ul style="list-style-type: none"> - Review Documents Liaison: Appropriate Area Operators
WEDNESDAY JULY 1, 1987	<p>AM</p> <ul style="list-style-type: none"> - Discuss MAEG & RIDP (View Selected Sites) Liaison: L. Anspaugh <p>PM</p> <ul style="list-style-type: none"> - Prepare for Team Meeting - Additional Document Review 	<ul style="list-style-type: none"> - Tour Area 25 incld. Water & Sewer System Liaison: Appropriate Area Operators 	<ul style="list-style-type: none"> - Meet on RMH, MAEG, RIDP Liaison: L. Anspaugh J. Burrows 	<ul style="list-style-type: none"> - On-Site Mtg. with DUM Area Office Counterpart EEERCLA - Continue Review of Enviro. Records & Aerial Photos 	<ul style="list-style-type: none"> - Tour Areas 5, 6, & 11 Liaison: O. Haworth G. Kendall 	<p>AM</p> <ul style="list-style-type: none"> - Tour Area 23 Steam Plant, Theatre Warehouse & Cafeteria regarding Asbestos - Tour Other Asbestos Areas - Four Asbestos Disposal Sites (a.g. Area 10) <p>PM</p> <ul style="list-style-type: none"> - Review MTS Asbestos Control Program Liaison: Haworth, Bullock 	<p>AM</p> <ul style="list-style-type: none"> - On-site Meetings to discuss RMH, RIDP, MAEG (view sites selected by liaison) Liaison: L. Anspaugh
THURSDAY JULY 2, 1987	<ul style="list-style-type: none"> - Tour Area 1 incld. 922 & 923 Shaker Plant - Coal-tar Fac. & 1287 Aggregate Plant, Pu-Com-taminated Area - 1002 Concrete Pit - 1084 Surface Disturbance - 1217 Crusher - Space Heating? Liaison: Q. Frazier 	<ul style="list-style-type: none"> - Tour Areas 1, 3, & 16 incld. Water & Sewer System, Springs Liaison: Appropriate Area Operators 	<ul style="list-style-type: none"> - Observe Well Sampling Liaison: D. McGrath or Sampling Team Leader 	<ul style="list-style-type: none"> - Tour Areas 1, 2, 3, 4, 7 & 9 incld. COM, LFP, Decon. Pad Sump "BUJ" & CND Liaison: O. Haworth 	<ul style="list-style-type: none"> - Tour Areas 1, 2, 3 & 4 Liaison: O. Haworth G. Kendall 	<p>AM/PM</p> <ul style="list-style-type: none"> - Review MTS Pesticide Program - Inspect Pesticide Application & Storage Areas Liaison: D. Bullock 	<ul style="list-style-type: none"> - Discuss BECAMP - Discuss Past-Test Drillback Activities - Turnout Testing & Related Monitoring - Discuss Test Cavity Radionuclide Inventories Liaison: F. Bingham

TABLE 2-3 (continued)

	AIR	WATER	HYDROGEOLOGY SOIL	INACTIVE WASTE/ SPILLS	HAZARDOUS/ SOLID WASTE	QA/TSCA	RAD
FRIDAY JULY 3, 1987	- Team Meeting	- Team Meeting	- Team Meeting	- Team Meeting	- Team Meeting	- Team Meeting	- Team Meetings - Review Environmental Monitoring Records
MONDAY JULY 6, 1987	- Tour Area 2 includ. Stemming Facilities UP 957 - 09954 Liaison: U. Haworth - Discuss Permits Inc: - 1035 Superior Boiler - RC1367 Surface Disturbances (Prep Test Shots) - 87-5 Open Burning - 87-37 Open Burning Tank Survivability	- Investigate Las Vegas Facilities Water & Sewer System Liaison: Appropriate Operators	- Tour Areas 22, 23 & 26 Liaison: D. McGrath	- Tour Other Sites as appropriate	- Tour Areas 22, 23 & 26 Liaison: O. Haworth G. Kendall	AM - Review MTS Sampling & Analysis QA Pro- grams Liaison: R.E. Williams PM - Tour REECO Radio- isotope & Industrial Hygiene Labs Liaison: R.E. Williams	- Review On-Site Mon- itoring Programs - Tour On-Site Environ- mental Labs - Review Monitoring Data/QA Records Liaison: F.B. Johns
TUESDAY JULY 7, 1987	- Tour Area 12 includ. - Concrete Batch Plant, 09928 - Discuss Tunnel Backfilling for Env. Control - Space Heating? Liaison: O. Haworth - Tour Area 7 includ. - Observe Drilling Activity Liaison: O. Haworth	- Tour Areas 5, 26 & 27 includ. Water & Sewer Facilities, Springs Liaison: Appropriate Area Operators	- Catch-up day	- Review Enviro. Records - Begin SBA Plan	- Tour Areas 19 & 20 Liaison: O. Haworth - Catch-up	AM/PM - Review MTS Toxic/ Hazardous Materials Purchasing, Storage & Use Systems Liaison: O. Haworth S. Lopez D. Thompson	- Review Records - Catch-up on Un- finished Business

operations, waste management, purchasing, and warehousing personnel; a review of files and documents (including classified documents) unavailable prior to the on-site portion of the Survey; and area-specific tours of the facility.

A formal closeout meeting with NVO/NTS management will be conducted on the morning of Friday, July 10, 1987 to describe the preliminary findings of the on-site activities. An informal technical briefing with NVO/NTS environmental personnel is scheduled for Wednesday July 8, 1987 at NTS to discuss tentative preliminary findings in detail. A Survey status report will be prepared within 4-6 weeks after the conclusion of on-site portion of the Survey. A Preliminary Report of the NTS Survey will be prepared within 14 to 16 weeks from the conclusion of the on-site Survey. Public distribution of the Preliminary Report will be at the discretion of the Operations Office although copies will be made available to members of Congress and EPA Headquarters, upon request. Subsequently, an Interim Report will be prepared by the Survey team within 6 to 8 weeks of the completion of sample analysis. The Interim Report will incorporate NVO/NTS technical comments to the Preliminary Report and the data from the sample analyses.

The Interim Report will be made available to the public, upon request. At the completion of the overall Environmental Survey effort, a final report will be prepared that will contain a DOE-wide list of environmental problems. The report will be used as an information base for the ranking of DOE's environmental problems.

2.3 Sampling and Analysis

Based on available site environmental information and the results of the Survey activities on-site, the NTS Survey team will identify any Survey-

related sampling and analysis needs. Preparation for the sampling and analysis (S&A) phase of the Survey process will begin approximately 2-4 weeks after the completion of the site visit, with the development of the sampling request package. The S&A effort will be conducted by Argonne National Laboratories (ANL). Kevin Flynn and Don McCown will be the ANL Team Leaders for the sampling and analysis phase of the Environmental Survey. The ANL Sampling and Analysis team will draft a Sampling and Analysis Plan based upon the needs identified by the Survey team. The Assistant Team Leader will coordinate the review of this Sampling and Analysis Plan with the Nevada Operations Office and EPA's Laboratory at Las Vegas (Environmental Monitoring Systems Laboratory), which has quality assurance and data validation responsibility for the sampling and analysis phase of the NTS Survey. The actual on-site sampling at NTS is projected to start during the fall (tentatively November) of 1987. The sampling is expected to take between 4 and 8 weeks to complete. Analysis of the Survey-related samples will be conducted by ANL following protocols provided in the Environmental Survey Manual, supplemented by the NTS Sampling and Analysis Plan. Results of the sampling and analysis will be transmitted to the Survey Team Leader for incorporation into the Interim Report.

3.0 AIR

The air-related portion of the Survey will involve an assessment of activities at the NTS that emit or have a potential to emit one or more air-contaminating materials, the emission controls or administrative procedures applied to restrict those emissions, and ambient-air monitoring equipment and procedures. The Survey will address those air contaminants for which air-quality standards (criteria pollutants) or emission standards (new source performance standards or emission standards for hazardous air pollutants) have been established by the United States Environmental Protection Agency or by Nevada Air Pollution Control Regulations. Also to be reviewed are substances being considered for listing as hazardous air pollutants. The primary NTS contact for the air specialist will be Orin L. Haworth, with other operator contacts designated by NTS to suit the plan indicated in Table 2-1.

3.1 Issue Identification

As a result of the pre-Survey site visit, it appears that radionuclides represent the air contaminant of greatest concern, and that potential sources of radionuclides exist, and will continue to be created, over much of the 1350 square miles of NTS. The criteria pollutant of major concern is total suspended particulate matter (TSP) that can be introduced into the atmosphere by a variety of activities at NTS. These materials, as well as sulfur dioxide, carbon monoxide, nitrogen dioxide, lead, hydrogen sulfide, volatile organic compounds, and any other air contaminants, will be considered as part of the Survey.

The general approach of the Survey will include a review of existing air permits, pending applications, and pertinent literature including standard

operating procedures. Processes and emission-control equipment will be inspected, with emphasis on operations and activities capable of emitting, but not limited to, radionuclides and/or particulates to the atmosphere. Of special interest will be the stemming and backfilling activities that are used to contain underground nuclear explosions. Fugitive emissions from resuspension of contaminated soils will be evaluated as a potential source of airborne contaminants. Records of operating hours, production rates, emission tests, and observations of visible emissions for permitted sources will be reviewed. Air contaminant sources that do not have air permits will be reviewed. The use and storage of solvents, including chlorofluorocarbons will be evaluated as potential sources of air contaminants.

In addition, the Survey will evaluate the air-monitoring devices and procedures used to monitor atmospheric contaminants, both on-site and off-site. Typical air-monitoring sites will be visited and the monitoring activities will be discussed with REECO and EMSL personnel. Also, the equipment and procedures used to acquire and use meteorological data before and after a test event will be observed and discussed with NOAA personnel. The Survey will also include any air-contaminant sources at NTS support facilities in Las Vegas.

Several areas of specific interest have been identified as a result of the pre-Survey site visit and a preliminary review of available documents:

- o Sources or potential sources of radionuclide emissions to the atmosphere.
 - Vents or seeps from current underground tests.
 - Drill-back into nuclear explosion cavities for sampling.

- Decontamination of equipment and facilities.
- Tailing piles and debris from postshot tunnel re-entry and rehabilitation activities.
- Resuspension of contaminated soils.
- Releases resulting from ground-fault movements.
- o Sources or potential sources of particulate dust emissions to the atmosphere.
 - Hole drilling.
 - Stemming activities, including the shaker plant, aggregator plants, coal-tan/epoxy facility, and stemming facilities.
 - Vehicular traffic on unpaved roads.
 - Subsidence.
 - Stationary diesel engines.
 - Tests of non-nuclear high explosives.
 - Oil-fired boilers.
 - Wind-blown dust (dust devils).

Throughout the Survey, emphasis will be placed on assessing available data and any future data generated by NTS within the timeframe of the overall Survey to characterize the overall environmental impact of test site operations. Where data gaps exist, recommendations for additional sampling and analysis may be developed for follow-up by the Sampling and Analysis Team.

3.2 Records Required

Additional documents will be reviewed as part of the Survey, including documents not yet received (e.g., classified documents, individual files, and documents not yet identified). Specific documents and files requested for review while on-site include, but will not be limited to, the following:

- o Most recent annual reports to the State of Nevada of information required by air operating permits, including production records, operating hours, visible opacity observations.
- o Fugitive dust control program.
- o Monthly fuel-consumption data per boiler for recent year, and annual fuel analysis data.
- o Annual throughput data for gasoline and fuel-oil tanks.
- o Annual data on organic solvent usage (including chlorofluorocarbons), and information on where and how these materials are used.
- o January 30, 1986 letter from State of Nevada regarding Air Operating Permit No. 1084.
- o Air Permits for NTS support facilities in Las Vegas.
- o Information on how classified waste paper is disposed of.

- o Data on vehicular traffic movements at NTS (especially over unpaved roads.)
- o Data on inspection and maintenance of vehicles for emission control.
- o Any other documents pertinent to air-contaminant emissions from NTS facilities.

PRELIMINARY

4.0 SURFACE WATER/DRINKING WATER

The surface water related portion of the Nevada Test Site (NTS) Environmental Survey will be concerned with the liquid discharges from industrial and sanitary waste treatment facilities at the site as well as the ponds used for collection of tunnel seepage. It will also be concerned with releases to the Publicly Owned Treatment Works (POTW) by the support facilities in Las Vegas. The six potable water systems at NTS and the potable system at the Las Vegas facilities will also be addressed in this portion of the Survey.

The Nevada Test Site is unique in that surface water discharges can not be transported to an ocean. Discharges to the north and east flow into terminal playas (i.e., Gold Flat, Kawich Valley, Groom Lake Valley, Yucca Flat and Frenchman Flat) from which there is no identified surface water drainage. The discharges to the south and west flow into various valleys (i.e., Oasis Valley, Fortymile Canyon, Topopah Wash, Rock Valley, and Mercury Valley) which lead to the Amargosa River. This is the ephemeral river that flows into Death Valley.

4.1 Issue Identification

Based on the documentation supplied by the Nevada Operations Office and the various site contractors as well as the site tour during the pre-Survey site visit it appears that there are minimal surface water issues at NTS. There are no continuous discharges from the site. However, at times of heavy rainfall and flash flooding there are off-site discharges from the valleys to the west and south of the site.

There is no NPDES permit for the site. It is our understanding that none are required under existing State of Nevada regulations. Monitoring is not conducted for parameters other than radionuclides in the surface waters on-site. The states first inspection of waste treatment facilities appears to have been on November 18-19, 1985. This inspection identified several items that needed to be improved to bring them up to state standards. The report also indicated the need for operating permits for the treatment facilities in Areas 12, 6, 23 and the C.P. Industrial Complex.

The Survey will include identification of potential discharges to surface waters, or the local sanitary authority, which may not be addressed in operating permits or other documents from NTS and the Las Vegas support facilities. The Survey will also assess the potential for nonradiological contamination (inorganic and organic) of wastewaters. Measures taken to prevent back-flow of process wastewater or sanitary sewer flows into the drinking water piping systems will be reviewed. A walk-through of the facilities will be made to observe normal routines, including maintenance activities which generate wastewaters. Various discharge and monitoring points will be reviewed, and actual sampling procedures will be observed. The adequacy of the monitoring programs and systems will be assessed. The wastewater collection, holding and treatment systems will be examined and records of operations reviewed. The capacity of sewage lagoons especially those assessed to be inadequate in the state inspection, will be reviewed. Emphasis will be placed on the major contributors to wastewater generation, such as Areas 23, 12 and 6. However, minor sources (in terms of total volume) will also be examined.

The primary contacts for the surface water specialist will be David Bullock and Paul Bolton. Interface with operations personnel in the areas indicated

in Table 2-1 will be required during tours of their areas to look at water systems and sources of liquid discharges.

4.2 Records Required

During the pre-Survey review of documents supplied by NTS, the following additional data and documents were identified as being of interest to the surface water specialist.

- o Results of the monthly analyses for the two community drinking water systems and the quarterly analyses of the four non-community drinking water systems at the site.
- o Results of nonradiological analyses conducted on the sewage and waste treatment lagoons at the site.
- o Results of analyses of effluents to the Las Vegas sewer system.
- o Copies of permits for discharges to the Las Vegas sewer system.
- o Backflow preventer inspection and maintenance records for facilities at NTS and in Las Vegas.
- o Results of sediment (soil) sampling in the bottoms of the stream channels in Oasis Valley, Forty Mile Canyon, Topapah Wash, Rock Valley and Mercury Valley if any are available.
- o Plans/Drawings of the water and sewer systems at the Las Vegas facilities.

- o Operating Permit Applications for treatment facilities in Areas 12, 6, 23 and the C.P. Industrial Complex.

PRELIMINARY

5.0 GROUNDWATER AND SOIL

The continuing generation of subsurface contamination is an inevitable result of underground nuclear testing. Residual surface soil contamination remains from above-ground nuclear testing. The use of leachfields for disposal of water, detergents, and solvents from decontamination operations and the disposal of waste liquids into various holes create further areas of contaminated soil.

The emphasis in studies of environmental conditions seems to be on purely scientific basic research or on the potential for off-site migration. On-site contamination has not been considered, historically, to be an environmental problem as long as contaminated areas are recognized, fenced, and marked, and as long as water supply wells are not affected.

The Survey effort will focus on the existence of contamination, its migration potential, and the adequacy of environmental monitoring programs. This effort will involve the evaluation of recent studies of site hydrogeology, determination of the status of on-going studies, and the review of plans for further investigations, regulatory compliance, and remedial action. Groundwater discharge areas will be examined, and the use of injection wells will be discussed.

5.1 Issue Identification

Several areas of specific interest have been identified through the pre-Survey site visit briefings and review of the data received thus far. These issues are discussed below.

Request for Waiver of RCRA Groundwater Monitoring Requirements.

The only groundwater-related compliance issue identified so far is the waiver request contained in the RCRA Part B Permit Application for the Radioactive Waste Management Landfill. This waiver request is based on a demonstration of no potential for migration of hazardous waste constituents to the uppermost aquifer. Facts cited in support of this absence of potential for migration include depth to groundwater (800-900 feet), low amount of annual precipitation (average 4.6 inches), and low moisture content of soils (3-9%). Although the Survey will not be involved in a determination of whether or not such a waiver is appropriate, the environmental situation will be reviewed.

Tunnel Ponds

Infiltration of precipitation, including snowmelt, from the surface of Rainier Mesa causes seepage of groundwater into tunnels used for underground nuclear tests. This groundwater, which represents a perched water zone above the regional water table, becomes contaminated with radionuclides, especially tritium. Contaminated water drains into, or is transferred to, a series of tunnel drainage ponds, also known as seepage basins. Typical tritium levels reported for these ponds are less than the DOE Derived Concentration Guide of 2×10^6 pCi/l (2×10^{-3} uCi/ml) for water used by members of the public, but have exceeded the EPA drinking water standard of 2×10^4 pCi/l (2×10^{-5} uCi/ml). Effluent and ponds associated with T-Tunnel are also contaminated with methylene chloride. This tritium-containing water evaporates or penetrates into the ground. The ponds also contain rinse water from grout trucks, leading to a buildup of solid material. Since seepage basins are not considered acceptable as treatment or disposal units, alternatives to the use of these ponds are under consideration. Further investigations of soil

samples from beneath the ponds have been suggested to determine if the ponds are radioactive hazardous waste sites.

Tritium in Groundwater

Tritium contamination of groundwater has occurred as a result of tests conducted below the water table. Some of this contamination is in the carbonate rocks which underlie the alluvium and form the regional aquifer in the Ash Meadows groundwater system. A review of information provided to this Survey indicates that off-site well or spring contamination is unlikely due to slow movement of groundwater in conjunction with radioactive decay.

These matters and others identified prior to, or during the on-site portion of the Survey will be discussed with appropriate contacts for the groundwater and soil specialist. These contacts include JoAnne Burrows (NVO), Roger L. Jacobson (DRI), Henry B. Gayle (Holmes and Narver), Paul Dickman and Daniel McGrath (REECO Waste Management), and Bill Scott (USGS).

5.2 Records Required

Specific documents and files to be reviewed as part of the Survey include, but will not be limited to, the following:

- o Recent data from groundwater monitoring and soil analyses.
- o Well sampling procedures. (Well sampling scheduled during the on-site portion of the Survey will be observed.)
- o Work plans for current and proposed groundwater and soil investigations.

- o Complete copies of USGS papers, including Winograd and Thordarson, 1975; USGS Prof. Paper 712-C Blankennagel and Weir, 1973; USGS Prof. Paper 712-B (Only abstracts, table of contents, and references are on hand.)

PRELIMINARY

6.0 RADIOACTIVE/HAZARDOUS/SOLID WASTE

The radioactive/hazardous/solid waste element of the Environmental Survey will identify all wastes generated at NTS and support facilities in Las Vegas; document waste treatment, storage, recycling and disposal practices; and identify any related problems that could result in the contamination of environmental media. These wastes will include hazardous, radioactive, and mixed hazardous and radioactive wastes, as well as nonhazardous/non-radioactive wastes. The procedure and facility-specific activities to accomplish these Survey objectives are presented below.

The pre-Survey visit to NTS provided an important basis for the procedure and activities outlined. It afforded an overview of site operations and wastes generated. In addition, contractor personnel responsible for waste management were met, and pertinent documents were identified. The knowledge and perspective gained also enhanced the review and analysis of material on waste generation and management provided by NVO and its contractors.

6.1 Issue Identification

The Survey procedure to identify waste-related environmental problems incorporates four types of activities: 1) inspection of waste generating operations and waste management facilities; 2) interviews with waste management personnel; 3) review of relevant records and documents; and 4) comparison of on-site observations with NVO and contractor reports and procedures. Each of these activities will be conducted daily as various areas are assessed.

Areas and wastes of interest are related to the following NVO operations:

- o Drilling and mining at NTS;
- o Underground nuclear testing at NTS;
- o Non-nuclear testing activities at NTS (MX activities, chemical spill tests, Electric Power Research Institute (EPRI) tests, tank ammo tests, RER training, etc.);
- o Support activities at NTS;
- o Waste disposal at NTS; and
- o Fabrication, assembly, and other industrial operations at NTS and in Las Vegas.

Some specific areas and wastes to be investigated are presented in Table 6-1 and 6-2, respectively. A significant amount of time will be spent investigating disposal sites used for wastes generated both on-site and off-site. Information will be collected on such features as site design and containment measures, types and volumes of waste accepted, waste containerization and retrieveability release potential and monitoring programs, and compliance status. Wastes identified in the annual hazardous waste generation reports submitted to the State and in the DOE-DP Hazardous and Mixed Waste Inventory for Nevada Operations will be carefully tracked. The Survey will also collect and review existing information on underground cavities of radioactive contamination created by underground testing, as well as undetonated devices and canisters. These activities will be conducted in conjunction with the inactive waste and spill sites element of the Survey. In addition, information on underground and above-ground storage tanks, in service and abandoned, will be collected. Underground storage tank evaluation

TABLE 6-1

Waste Management Areas To Be Investigated

Core and drill mud disposal sites (Areas 2, 3, 8 & 9)

Mining waste disposal sites

Contaminated muck piles (Areas 12, 15 & 16)

Contaminated waste dumps (Areas 11, 12, 25 & 26)

Contaminated storage tanks (Areas 15, 25 & 26)

Bermed above-ground filter tanks (Area 25)

Leach fields (Areas 6, 23, 25 & 26)

Decontamination/evaporation ponds and sump(s) (Areas 6, 7 & 12)

Trench ponds (Area 12)

Radioactive waste management sites (Areas 3 and 5)

Mercury hazardous waste landfill (Area 23)

Ordnance disposal site(s)

Waste accumulation areas located throughout NTS and the Las Vegas facilities

RCRA waste storage area in Area 23

Construction landfills

Sanitary landfills (Areas 2, 6, 10, 12, 22, 23 & 25)

Salvage yards

TABLE 6-2

Waste Types To Be Investigated

Drilling and mining wastes

Detonation wastes (in situ and removed)

Trench effluent

Contaminated materials

Decontamination wastes

Sediments in decontamination, evaporation, and trench ponds

Radioactive and mixed wastes from other DOE sites

Industrial (i.e., fabrication and assembly) wastes (e.g., solvents and thinners, corrosives, adhesives and resins, and paint wastes)

Laboratory wastes

Waste oil

Ordnances, blasting agents and explosives

Construction waste

Trash

will focus on tank material, corrosion protection, age, content, inventory control, and leak detection capabilities.

Waste management activities that could result in or avoid releases of contaminants to the environment will also be investigated. Such activities include:

- o Waste minimization and recycling;
- o Waste analysis;
- o Waste segregation and storage;
- o Waste containerization and labelling;
- o Waste tracking and recordkeeping;
- o Facility inspection and followup; and
- o Training and contingency planning.

Controls to prevent co-mingling of radioactive, hazardous and non-radioactive/non-hazardous wastes will be assessed. Adherence to established waste management procedures will be evaluated. The application of acceptance criteria for wastes received from other DOE facilities will be studied, as well as any associated analysis. Findings of previous audits and inspections will be studied.

Discussions will be held with individuals knowledgeable of current and past waste management practices. This will be accomplished during operation and facility tours and in the process of reviewing relevant documents and files. The objective is to develop an understanding of past and existing waste management activities that may serve as the basis for problem identification. Key personnel identified to date for their knowledge of waste management practices include Mr. Frank Bingham, Environmental Compliance Branch of NVO's Health Physics and Environmental Division; Gene Kendall, REECO's Radioactive Waste Management Section; and Mr. Orin Haworth, Survey Branch of REECO's Industrial Hygiene Section.

6.2 Records Required

Records on waste generation and waste management activities will be reviewed on-site to verify, expand, and update documented information studied prior to the Survey. Records include:

- o Active memorandum of understanding on waste management issues between DOE and EPA.
- o Updates to RCRA Part A and Part B permit applications.
- o Review Team Report on NTS Mixed Waste Issues (12/4/86).
- o Files on waste generation and analysis (from NTS and Las Vegas operations).
- o Files on all waste storage facilities (e.g., inventories and inspections).

- o Files on all waste disposal facilities (e.g., designs, wastes received, inspections, permits and approvals).
- o Files on all off-site treatment, storage and disposal facilities used (e.g., inspections and volumes shipped).
- o Waste manifests (i.e., for wastes coming on-site and being shipped off-site).
- o Files on waste acceptance and associated documentation.
- o Files on monitoring programs around waste disposal sites (e.g., groundwater and soil investigation data).
- o Files on underground and above-ground storage tank testing and leak detection monitoring.
- o Files or documents on the potential for seismic and flood events.
- o Waste management training records.
- o Files on internal and external waste management audit (e.g., in-house, state, local and Federal inspection records and Industrial Hygiene Appraisals) and follow-up actions to correct deficiencies.

7.0 TOXIC/HAZARDOUS SUBSTANCES

The toxic substances portion of the Survey will address raw materials and operations-related chemicals used at NTS as well as the handling, storage and disposal of specific chemicals regulated under the Toxic Substances Control Act (polychlorinated biphenyls (PCBs), chlorofluorocarbons, and asbestos) and the Federal Insecticide, Fungicide and Rodenticide Act (pesticides). The condition and environmental monitoring of underground and above ground storage tanks used for bulk chemical substances other than wastes will also be examined. Through interviews with key NTS personnel and tours of relevant facilities, the tracking, control and management of toxic/hazardous substances will be reviewed. This information and records of usage will be evaluated to determine whether or not the systems, equipment and programs established by NTS for the management of toxic/hazardous substances are adequate to minimize, to the extent feasible, potential environmental contamination.

7.1 Issue Identification

The procedures which have been implemented by NTS (e.g., Procedure 3.2.54, Controlling Polychlorinated Biphenyls) to manage electrical equipment which contains PCB and PCB-contaminated fluids will be evaluated during the Survey. The condition of, and potential for environmental contamination from, the PCB-containing electrical equipment listed in the 1985 NTS PCB Annual Report will be determined by inspecting a portion of this equipment. Obsolete, stored or used PCB equipment (such as that stored at the Area 6 Lineman's Yard) will be checked for proper containment and protection. Plant records for PCBs will be reviewed, and disposal methods and practices will also be addressed. Specifically, the compilation of completed PCB Transformer Inspection forms (RE-1305) and PCB Status Reports (RE-1304) will be requested. Records of off-

site shipments and disposal of PCB-containing materials, and any information pertaining to previous PCB spill or dump areas will be reviewed.

NTS has not provided a list of the buildings at the site which contain asbestos. This information, as well as the quantity, type and condition of any asbestos-containing materials in these buildings, and the procedures used by NTS to maintain, repair, renovate or remove such materials, is necessary to determine if potential pathways of contamination and environmental problems involving asbestos exist at NTS. Such information will be requested during the on-site Survey. Records relating to the handling and disposal of asbestos-containing materials will be reviewed. If possible, asbestos removal projects ongoing during the Survey and/or disposal of asbestos-containing materials at the landfills utilized by NTS will be observed directly. Information available to the team to date indicates that only 5 projects involving the handling of asbestos-containing material have occurred at NTS since April, 1983.

Pesticides are used at NTS. Several of these materials are restricted-use pesticides. During the Environmental Survey, the procedures used at NTS to handle, mix, apply and dispose of pesticides will be reviewed. Areas where pesticides are mixed and stored will be inspected, and pesticide purchase, use and application records will be assessed. The training program and associated records for NTS employees and/or contractor personnel who work with pesticides will also be of interest to the team.

Toxic/hazardous chemicals are stored and used in both bulk and smaller quantities at NTS. Areas where toxic/hazardous materials (e.g., solvents, acids) are used and/or stored will be visited during the Survey. Notable in this category is the Spill Test Facility in Frenchman's Flat and other

locations where above ground and underground storage tanks are present (e.g., Buildings 619, 1226 and 751-754). In addition, any locations where highly toxic substances (e.g., carcinogens) are handled will also be evaluated to determine the potential for environmental contamination. Management inventory and control of chlorofluorocarbons (freons) will also be examined. Discussions will be held with those individuals knowledgeable of toxic/hazardous substances in order to develop an understanding of current and past practices.

Contacts at NTS for the toxic/hazardous substances portion of the Survey are as follows: O. Haworth (above ground and underground storage tanks, asbestos removal, overview of toxic/hazardous substances); D. Bullock (pesticides, disposal of asbestos waste); J. Kim (inspection and maintenance of PCB equipment); S. Lopez (transportation of toxic/hazardous substances); and D. Thompson (procurement of toxic/hazardous substances).

7.2 Records Required

Files will be reviewed as part of the Survey, including documents not yet received (e.g., classified documents, individual files, documents not yet identified). Specific documents and files to be collected and reviewed during the Environmental Survey include:

- o PCB transformer inspection records and forms (RE-1305).
- o Storage and disposal records for PCB equipment and fluids.
- o Documentation that NTS personnel have conducted site visits at off-site PCB disposal locations.

- o Correspondence with the NTS Fire Department regarding PCB electrical equipment, in particular any records of fires involving PCB equipment.
- o For spills involving PCBs, records which demonstrate that affected areas (building surfaces, soil, etc.) have been adequately decontaminated.
- o Procedures established by NTS for asbestos removal work performed by NTS employees and/or contractor personnel.
- o Records of NESHAPs notifications for recent asbestos removal projects.
- o Asbestos disposal records and permits.
- o Procedures covering the purchase, handling, mixing, application and disposal of pesticides at NTS.
- o Training records of personnel who handle pesticides.
- o Pesticide annual reports.
- o Toxic/hazardous substances inventory and chemical purchase records.
- o Toxic substances labeling and tracking system overview.
- o Procedures for purchasing, handling, storing, using and disposing of toxic substances.

- o Procedures which address the handling, storage, use and disposal of chlorofluoralkanes (e.g., freons).
- o Environmental monitoring reports and procedures for underground storage tanks that contain non-waste materials.
- o Spill control and emergency preparedness plans for above ground storage tanks that contain non-waste materials.
- o Internal or external audits of any of the above programs.
- o Other records as determined on-site.

8.0 RADIOLOGICAL

The primary purpose of the NTS is to provide a continental U.S. site for the testing of nuclear weapons and conducting tests to study the effects of weapons produced radiation on weapons' systems and components. Tests have included both nuclear detonations and safety experiments. Since 1963, all tests have been conducted deep underground to limit the release of radioactive materials. Pre-1963 atmospheric nuclear detonations and safety tests have resulted in the radioactive contamination of lands both within and outside the boundaries of the NTS. Steps are taken for underground testing to minimize the risk of release of radioactive materials although there have been accidental releases through vents and seeps, as well as some planned releases of noble gases. The Environmental Survey will examine the impact of past and present nuclear tests on the current environmental condition of the site.

In addition to nuclear weapons testing, NTS has responsibility for the operation of radioactive waste disposal facilities for wastes resulting from defense-related work conducted at NTS and other locations. Special projects and facilities such as the Engine Maintenance, Assembly, and Disassembly Building (E-MAD) and the BREN tower have also presented potential environmental impacts and require some investigation.

8.1 Issue Identification

The radiological aspects of the Environmental Survey will involve an assessment of the facility-wide radioactive emissions, control and monitoring and the associated impact on the environment. The assessment will encompass four major areas: 1) airborne radionuclide releases; 2) liquid radionuclide releases; 3) radwaste management practices; and 4) soil contamination. On

the basis of reviews of available documents, it may be concluded that airborne releases of radionuclides have historically been the most significant contributors to radiation exposure to members of the general public. However, the potential of risks to the environment from the other sources must be assessed. The radiological Survey will be coordinated with the air, water, inactive sites, and hydrogeology aspects of the Survey. Specific issues requiring investigation have been identified for each of the major areas.

1) Airborne Releases of Radionuclides.

Unlike most DOE facilities, NTS has no production facilities and consequently no significant routine process-related air emissions. In addition, since all nuclear tests conducted since 1963 have been underground, and care is taken to contain the radionuclides produced in the detonation, routine releases are not expected from tests. However, there is a potential for the airborne release of materials on and off-site, from accidental vents and seeps of radionuclides associated with nuclear tests. The Survey team will examine the processes and criteria used by DOE's Containment Evaluation Panel (CEP) in its review of the containment aspects of each test. This will be accomplished through a review of documents describing the technical approach to containment, and detailing the approach and criteria used by CEP in its evaluations. To supplement the document review, the Survey team will conduct interviews with personnel on technical aspects of containment and the function of the CEP.

The air resuspension of contaminated soils is another potential pathway for further dispersion of radionuclides on-site and potential off-site release of radionuclides. This has been studied extensively by the Nevada Applied Ecology Group (NAEG) and is to be continued through the

Basic Environmental Compliance and Monitoring Program (BECAMP). The Survey team will use interviews with program personnel to supplement information gained from document reviews in its assessment of the resuspension issue.

Other specific issues to be investigated during the on-site portion of the Survey include:

- o Airborne dose calculations, inputs, assumptions, and methodology.
- o Air-related aspects of NAEG and BECAMP.
- o NAEG resuspension model.
- o NAEG plutonium dose assessment model.
- o Nuclear test radiation monitoring program.
- o Design, placement, maintenance, and calibration of on-site and off-site ambient air monitors.
- o Laboratory facilities for airborne environmental analyses.
- o Quality assurance program and records for airborne radiological sampling and analyses.
- o Radionuclide releases during drillback operations and tunnel ventilations.

2) Liquid Radionuclide Releases.

The release of radionuclides through surface water pathways is expected to be of minimal impact because of the limited number of surface-water bodies and streams. There are however, some specific issues that are of interest. In addition, radwaste disposal and nuclear tests have the potential to contaminate groundwater. Specific issues that will be investigated include:

- o Criteria for selection of surface water and groundwater sampling locations, and adequacy of sampling network.
- o Quality assurance program and records for liquid effluent sampling and analysis.
- o Adequacy of surface water and groundwater sampling and analysis procedures.
- o Radionuclide Migration Program.
- o Sediment sampling and analysis programs.
- o Radiological contamination of tunnel ponds.

3) Radwaste Handling and Disposal.

In addition to radioactive wastes that may be generated through NTS activities, NTS accepts for disposal, radioactive wastes generated at other sites involved with defense programs. There are two primary active sites at NTS for radioactive waste disposal. A 92 acre waste disposal site is located in Area 5. This site contains 10 closed pits and

trenches, 3 active pits and trenches, and 10 disposal boreholes for higher activity wastes. At Area 3, large subsidence craters are used for the disposal of bulk wastes. Specific issues that will be investigated as part of the Survey in conjunction with the Survey waste management specialist include:

- o Current site radioactive waste management practices.
- o Segregation of radioactive and mixed wastes.
- o Radioactive waste disposal practices.
- o Adequacy of disposal area monitoring.
- o Reactor test cells.
- o Disposition of BREN reactor.
- o Drillback wastes.
- o E-MAD and R-MAD area waste storage.
- o Inactive contaminated waste dumps.
- o Leach fields.

4) Soil Contamination.

Surface soils have been contaminated as a consequence of pre-1963

atmospheric nuclear detonations and safety tests (point tests). Safety tests, designed to verify that a given weapon design will not detonate accidentally, have little or no fission or fusion yield, but have resulted in plutonium contamination of soils. Since 1986, all nuclear detonations and safety tests have been conducted underground, thereby minimizing surface contamination, these tests do, however, result in a large inventory of radionuclides in underground cavities. The levels of contamination, types of radionuclides, and radionuclide inventories have been addressed as a part of the Nevada Applied Ecology Group (NAEG) studies and specifically under the Radionuclide Inventory and Distribution Program (RIDP). Beginning in 1987, similar investigations will be continued through the Basic Environmental Compliance and Monitoring Program. The results of these studies will be of particular interest to the Survey team. Specific issues to be investigated include:

- o Extent of on-site and off-site surface soil contamination.
- o Details of NAEG cleanup trial.
- o Details of soil pathway dose assessments.
- o Migration of soil contamination.
- o Characterization of underground contamination.
- o Underground weapons test cavities.

5) Miscellaneous Issues.

There remain other issues of interest that are not necessarily included

in the above categories. Such issues include:

- o Migration of radionuclides in the groundwater.
- o Adequacy of the site's overall environmental monitoring program.
- o Overall dose assessment methodology (all pathways).
- o Current status Kukla and Tory reactors.
- o Activities at E-MAD facilities.

8.2 Records Required

Records that are requested for on-site review include the following:

- o Radioanalytical QA documentation.
- o Radiological sampling procedures.
- o Environmental monitor calibration and maintenance records.
- o Radwaste management procedures.
- o Background documents for the placement and design of monitors.
- o Raw data from environmental monitoring.
- o Draft RIDP reports and data summaries.

- o Reports detailing NAEG dose prediction models.
- o Monitoring reports associated with planned ventilations of tunnels.

PRELIMINARY

9.0 QUALITY ASSURANCE

The quality assurance Survey activities will consist of an examination of the methods used to assure that the collection and analysis of environmental samples at NTS result in the generation of valid data.

9.1 Issue Identification

The Survey will focus on evaluating current sampling and analysis procedures performed at NTS or at any off-site laboratories conducting environmental analyses on samples from NTS. The intent will be to review the quality assurance procedures for collecting and environmental samples, for performing the laboratory analytical work to identify and to quantify pollutants and for evaluating and reporting the data. Aspects of the quality assurance program relating to environmental management of NTS which will be examined, if available, include: analyst training; equipment/instrument calibration and maintenance; sample collection, handling and chain-of-custody procedures; blank, replicate and spiked sample results; data reduction and reporting; and data documentation, including logbook and calculation reviews and archival data storage.

Sampling and analysis procedures will be reviewed to ensure that they conform to accepted requirements and are being appropriately implemented by NTS. An overall Survey of the NTS environmental monitoring quality assurance program will be performed.

Primary contacts at NTS are expected to be the quality assurance representative from the Laboratory Operations Section of the REECO Environmental Sciences Department (both the radioisotope and industrial

hygiene laboratories - R.E. Williams) and similar personnel from the EPA Environmental Monitoring and Support Laboratory.

9.2 Records Required

Specific documents and files to be reviewed as part of the Survey include, but will not be limited to, the following:

- o QA plans for NTS and any supporting analytical laboratories.
- o Procedure manuals and quality assurance manuals supporting the sampling and analysis aspects of NTS environmental monitoring.
- o Results of performance evaluation samples supplied to contractor laboratories by NTS.
- o Quality assurance audits of environmental sampling and analysis at NTS.
- o Quality assurance audits by NTS of contractor laboratories.
- o Studies on precision and accuracy of NTS environmental analyses.
- o Summaries of the results of interlaboratory cross-check analyses provided by contractor laboratories.
- o Summaries of results of QA sample analyses on external performance evaluation samples, such as those from DOE's Environmental Measurements Laboratory (EML) and from the EPA.

- o Training records for sample collection personnel and NTS laboratory staff.
- o Laboratory notebooks, standard data reporting forms and sampling logbooks.

PRELIMINARY

10.0 INACTIVE WASTE SITES/RELEASES

The pre-Survey visit to the DOE Nevada Test Site (NTS) provided an opportunity to become familiar with general operations and layout of the site. It also allowed for an overview of a few of the many areas known to have, or possibly have environmental contamination. The on-site Survey will attempt to identify environmental problems and potential risks associated with the historical handling, storage, and disposal of hazardous substances (including radioactive wastes) at NTS. This aspect of the survey will be coordinated with the Radiation, Waste Management, and Hydrogeology team members, and will focus on current and future risks related to the following:

- o Past waste disposal practices;
- o Past spills/releases; and
- o Potential for future spills/releases from inactive waste management sites.

10.1 Issue Identification

All past waste disposal sites and areas of past spills and releases (known or suspected) will be reviewed, inspected and assessed. These facilities include the waste management consolidation areas, construction landfills, contaminated muck piles, waste contaminated storage tanks (above and underground), contaminated waste dumps, core and mud disposal, leach fields, evaporation ponds, inactive or abandoned water supply wells, and inactive injection wells. Any sites listed in the CERCLA Phase 1 report that are not referenced above will also be addressed by the Survey. Procedures for identifying sites for

inclusion in the CERCLA Phase 1 Report will also be reviewed.

In addition, the following sites will be reviewed, inspected and assessed: Spill Test Facility - Frenchman Flat (Area 5); Sand Spring Test Range (Area 5); Abandoned Transmitter Site (Area 6); Decon Pad Sump "BJY" (Area 7); Explosive Ordance Disposal Area (Area 11); Spent Fuel Test Site (Area 15); Oak Spring/Climax and the EPA DOE Experimental Farm (Area 15); Desert Rock Airstrip (jet-A-fuel loss - Area 22); Chemical and Medical Waste Trenches, hazardous waste landfills "A", "B", and "C" (Area 23); and facilities in Area 25 including E-MAD, R-MAD, TEST CELL A,C, Engine Test Stand No. 1, and BREN tower.

The Survey team has learned that there are DOE contractor support facilities located in and around Las Vegas. These sites will also be reviewed and visited by the Survey team, as appropriate.

Other sites will also be investigated as identified by NTS personnel, and documents that will be made available during the Survey.

One important document that has not yet been received by the Survey Team is the Revised CERCLA Phase 1 report, which reportedly will be made available at the beginning of the on-site Survey. All material supporting the findings of this report also will be reviewed.

While on site, the Survey team will review environmental records pertaining to the past management, disposal and cleanup regarding hazardous wastes (both radioactive and non-radioactive substances). Inactive waste sites identified will be reviewed and assessed in terms of wastes handled and disposed of, known or suspected releases, environmental controls and monitoring, and

environmental regulatory compliance.

Sites that have undergone remedial cleanup (complete or partial) also will be addressed (e.g., 25 waste management consolidation projects). Records and analytical data in support of the site cleanup will be obtained for review. Each of these sites will be assessed in terms of residual hazardous substances (including non-radioactive contaminants such as lead) and any remaining risk to the environment.

In addition, the Survey will collect and review existing information on underground cavities of radioactive contamination created by past underground testing.

Where appropriate, the Survey team will review available engineering drawings of waste management facilities as well as aerial photographs that show the historical development of the site. Undetonated test site also will be reviewed.

Primary contacts for this portion of the Survey will include personnel from Health Physics and Environmental Division, Waste Management Project Office, and DOE Contractors (e.g., REECO)

10.2 Records Required

The following records, among others, are requested to be made available for review at the beginning of the on-site Survey. Records should be made available for at least the sites identified in Section 10.1.

- o Standard Operating Procedures regarding management of hazardous substances, disposal areas, and storage areas.
- o Hazardous substances inventories.
- o Historical files on past operations and processes, substances used, and methods of handling and disposal.
- o Records of facility expansion and building rubble disposal.
- o Records of regulatory notification pertaining to inactive waste sites and potential areas of contamination.
- o Records of regulatory compliance.
- o Description of former waste management facilities, including buried tanks and structures.
- o Revised CERCLA Phase 1 report, with map showing the location of each CERCLA site.
- o "Interview files", if relevant, for the revised CERCLA Phase 1 report.
- o Engineering drawings of waste management facilities.
- o Documents pertaining to known or suspected off-site contamination associated with NTS.
- o Documents pertaining to past remedial actions.

- o Environmental records pertaining to past facility responses to hazardous substance spills and releases.
- o Aerial photographs of NTS (historical).

PRELIMINARY

APPENDIX C
SITE-SPECIFIC SURVEY ACTIVITIES

PRELIMINARY

C.1 Pre-Survey Preparation

The DOE Office of Environmental Audit and Compliance, Assistant Secretary for Environment, Safety, and Health selected a team to conduct an Environmental Survey at the Nevada Test Site (NTS) at Mercury, Nevada, which is operated for DOE by Reynolds Electrical & Engineering Co. (REECo), Inc. Mr. Thomas Traceski was designated DOE Team Leader, and Ms. Donna Bergman, the Assistant Team Leader. Other team members included technical specialists from NUS Corporation and ICF Technology. Argonne National Laboratory (ANL) was designated to provide a sampling team for the NTS Survey and to perform the laboratory analytical services. The sampling and analysis (S&A) functions were subsequently reassigned to Battelle Columbus Division.

A pre-Survey site visit was conducted on May 5 and 6, 1987, by the Team Leaders, the NUS and ICF technical specialists, and representatives from the ANL sampling and analysis team. Following introductions, Nevada Operations Office (NVO) personnel presented an overview of activities at the facility and discussed environmental issues of concern to them. The logistics of the upcoming Survey were discussed and a facility tour was provided. In addition, a meeting was held on May 7, 1987, with officials of the Nevada Division of Health and the Nevada Environmental Protection Division to inform them of Survey activities and to hear their concerns with regard to NTS. The Environmental Protection Agency (EPA) Region IX was also invited to attend the meeting, but declined.

Subsequently, NUS and ICF technical specialists intensively reviewed the environmental documents and reports that were provided by NVO. Based on that review, a Survey plan for the NTS and the support facility in North Las Vegas was prepared, which discussed the specific approach to the Survey for each of the technical disciplines and included a proposed schedule of activities for on-site activities. The Survey plan was transmitted to the Nevada Operations Office and REECo during the week of June 5, 1987.

C.2 On-site Activities

The on-site portion of the Survey was conducted at the NTS during the period of June 22 through July 10, 1987. The opening meeting held on June 22, 1987, was attended by representatives from DOE Headquarters, the Nevada Operations Office, REECo, NUS Corporation, and ICF Technology. Discussions during this meeting centered on the purpose of the Survey, logistics at the NTS, and an introduction of the personnel involved.

During the on-site portion of the Survey, team members reviewed additional file materials including permits and applications, background studies, engineering drawings, unusual occurrence reports,

and operating logbooks. The site activities were thoroughly analyzed to identify existing and potential pollutants. Site operations and monitoring procedures were observed. Extensive interviews were conducted with site personnel regarding environmental controls, operations, monitoring and analysis, past operations, regulatory permits, and waste management.

Meetings of the Survey team members were held to report observations and compare findings. The team also coordinated daily with NVO and REECO personnel to arrange for specific site personnel and facilities to be available, as needed, on the following day. The sampling and analysis requirements identified by the Survey team members were discussed as they developed with Argonne personnel.

A site closeout briefing was held on July 10, 1987, at which the DOE Team Leader presented the preliminary observations of the Survey team. These observations were classified as preliminary, because additional research and, in some cases, additional field sampling were required to positively confirm the observations.

C.3 Sampling and Analysis

Argonne National Laboratory (ANL) prepared a Sampling and Analysis Plan which included the sampling requests made by the Survey team, a quality assurance plan, and a health and safety plan. This plan was submitted to the NVO in January 1988. Subsequent to the preparation of this plan, some sampling requests were eliminated on the basis of logistics, costs, and schedules. Sampling was initiated by Battelle Columbus Division in February 1988.

C.4 Report Preparation

A draft preliminary Survey report for the NTS was prepared to summarize the findings from the on-site Survey effort. This report will be provided to the Nevada Operations Office, and the NTS contractor for review. The findings presented in the draft report are considered preliminary until comments are received and S&A results are available. At that time, the comments and S&A results will be evaluated and an Interim Report will be prepared.

PRELIMINARY

APPENDIX D

CHEMICAL SYMBOLS, ABBREVIATIONS, AND ACRONYMS

Al	- Aluminum
Am	- Americium
AQCR	- Air Quality Control Region
ASN	- Air Surveillance Network
ATLAS	- Augmented Test Logistics Assembly System
BACT	- Best Available Control Technology
Be	- Beryllium
BECAMP	- Basic Environmental Compliance and Monitoring Program
BOD	- Biological Oxygen Demand
Btu	- British thermal unit
°C	- Degree Celcius
CAA	- Clean Air Act
Cd	- Cadmium
CEC	- Cation Exchange Capacity
CERCLA	- Comprehensive Environmental Response, Compensation, and Liability Act of 1980
CFC	- Chlorinated Fluorocarbon
CFR	- Code of Federal Regulations
Ci	- Curie
cm	- Centimeter
cm ³	- Cubic centimeter
Co	- Cobalt
CO	- Carbon Monoxide
CO ₂	- Carbon Dioxide
CP-1	- Control Point-1
cpm	- counts per minute
Cs	- Cesium
CSA	- Central Support Area
CWD	- Contaminated Waste Dump
CY	- Calendar Year
DCG	- Derived Concentration Guides
DOD	- Department of Defense
DOE	- Department of Energy
DOT	- Department of Transportation
DPP	- Drift Protection Plug
DRA	- Desert Rock Airstrip
EA	- Environmental Assessment
EERF	- Eastern Environmental Radiation Facility
EG&G/EM	- EG&G Energy Measurements, Inc.
E-MAD	- Engine Maintenance, Assembly, and Disassembly
EMSL	- Environmental Monitoring Systems Laboratory
EPA	- U.S. Environmental Protection Agency
ERDA	- Energy Research and Development Administration
ETS	- Engine Test Stand
Eu	- Europium
°F	- Degree Fahrenheit
fCi/g	- femtocurie per gram
ft	- foot
ft ²	- square foot
ft ³	- cubic foot

FR	- Federal Register
FUSRAP	- Formerly Utilized Sites Remedial Action Program
FY	- Fiscal Year
gal	- gallon
g/cm ³	- gram per cubic centimeter
GCD	- Greater Confinement Disposal
gpd	- gallon per day
GSAC	- Gas-Sealed Auxiliary Closure
GSP	- Gas-Seal Plug
³ H	- Tritium
HLW	- High Level Waste
HMIS	- Hazardous Materials Information System
HSA	- High Specific Activity
HTO	- Tritiated Water
ICRP	- International Commission on Radiation Protection
J	- Joule
K	- potassium
kg	- kilogram
km	- kilometer
⁸⁵ Kr	- krypton-85
kV	- kilovolt
lb	- pound
LFP	- Inactive Leachfield
LGF	- Liquified Gaseous Fuels
LLNL	- Lawrence Livermore National Laboratory
LLW	- Low-Level Waste
LNG	- Liquified Natural Gas
LOS	- Line-of-Sight
LPG	- Liquified Petroleum Gas
LSA	- Low Specific Activity
LTHMP	- Long-Term Hydrological Monitoring Program
LVO	- Las Vegas Operations
m ²	- square meter
m ³	- cubic meter
MAC	- Modified Auxiliary Closure
MAD	- Maintenance, Assembly, and Disassembly
MDC	- Minimum Detectable Concentration
meq	- milliequivalent
mm	- millimeter
mR	- milliroentgen
mrem/yr	- millirem per year
mCi/m ²	- millicurie per square meter
mi ²	- square mile
mg/l	- milligram per liter
MSDS	- Material Safety Data Sheets
NAAQS	- National Ambient Air Quality Standards
NAC	- Nevada Administrative Code

NAEG	- Nevada Applied Ecology Group
NASA	- National Aeronautics and Space Administration
NCRP	- National Council on Radiation Protection and Measurement
NDEP	- Nevada Division of Environmental Protection
NERVA	- Nuclear Engine for Rocket Vehicle Application
NESHAP	- National Emission Standards for Hazardous Air Pollutants
NGTSN	- Noble Gas and Tritium Sampling Network
NLVF	- North Las Vegas Facility
NO ₂	- Nitrogen Dioxide
NPDES	- National Pollutant Discharge Elimination System
NRC	- Nuclear Regulatory Commission
NRDS	- Nuclear Rocket Development Station
nCi/l	- nanocurie per liter
NTS	- Nevada Test Site
NTU	- Natural Turbidity Unit
NV	- Nevada
NVO	- Nevada Operations Office
O ₃	- Ozone
OEG	- Office of Environmental Guidance and Compliance
PCB	- Polychlorinated Biphenyl
pCi/g	- picocurie per gram
pCi/l	- picocurie per liter
pCi/m ³	- picocurie per cubic meter
POTW	- Publicly Owned Treatment Works
ppb	- part per billion
ppm	- part per million
Pu	- Plutonium
Ra	- Radium
RADEX	- Radiation Exclusion
RCP	- Reactor Control Point
RCRA	- Resource Conservation and Recovery Act
REECO	- Reynolds Electrical & Engineering Company
Rh	- Rhodium
RIDP	- Radionuclide Inventory and Distribution Program
R-MAD	- Reactor Maintenance, Assembly, and Disassembly
RNMS	- Radionuclide Migration Study
Ru	- Ruthenium
RWCS	- Radioactive Waste Consolidation Site
RWMS	- Radioactive Waste Management Site
SARA	- Superfund Amendments and Reauthorization Act of 1986
Sb	- Antimony
S&A	- Sampling and Analysis
SFMP	- Surplus Facilities Management Program
Si	- Silicon
SNL	- Sandia National Laboratory
SO ₂	- Sulfur Dioxide
SPCC	- Spill Prevention, Control, and Countermeasures
Sr	- Strontium
STF	- Spill Test Facility
TAPS	- Tunnel and Pipe Seal

TC-A
TC-C
TDS
TLD
TRU
TSP
TTR

U
USGS
UST

WIPP
WP
WSNSO

^{133}Xe

μCi
 $\mu\text{Ci}/\text{cm}^3$
 $\mu\text{Ci}/\text{m}^2$
 $\mu\text{g}/\text{kg}$
 $\mu\text{R}/\text{hr}$

- Test Cell-A
- Test Cell-C
- Total Dissolved Solids
- Thermoluminescent Dosimeter
- Transuranic
- Total Suspended Particulates
- Tonopah Test Range
- Uranium
- U.S. Geological Survey
- Underground Storage Tank
- Waste Isolation Pilot Plant
- Working Point
- Weather Service Nuclear Support Office
- Xenon-133
- microcurie
- microcurie per cubic centimeter
- microcurie per square meter
- microgram per kilogram
- microroentgen per hour

PRELIMINARY

END

DATE FILMED

11 / 16 / 90