DISTRIBUTION SHEET

To	From	Page 1 of 1
Distribution	HA, Planning and Integration	Date 11/16/94
Project Title/Work Order		EDT No. 156847
WHC-SD-W370-ER-001, REV. 0 "RECOMMENDATIONS FOR SANITARY WASTE WATER SYSTEM REPLACEMENT 222-S"		ECN No. N/A

Name	MSIN	Text With All Attach.	Text Only	Attach./ Appendix Only	EDT/ECN Only
S. L. BREY	T6-12			X	
CENTRAL FILES	L3-04	X			
J. L. DEICHMAN	H4-19			X	
B. C. HARMON	G3-08	X			
J. S. HILL	H6-25	X			
S. M. JOYCE	H4-21			X	
E. J. KOSIANSIC	T6-16			X	
R. P. MARSHALL, JR	T6-14			X	
C. B. MCVEY	H4-21	X			
C. S. MORTIMER	E6-46	X			
OTSI (2)	L8-07	X			
R. L. ROBERTSON	T6-12	X			
F. M. SIMMONS (3)	H4-21	X			
D. M. THORNTON	T6-22	X			

MASTER

NOV 16 1994
Sta. 21

21

ENGINEERING DATA TRANSMITTAL

Page 1 of 1
1. EDT 156847

2. To: (Receiving Organization) Distribution	3. From: (Originating Organization) HAS, Planning and Integration	4. Related EDT No.: 156847
5. Proj./Prog./Dept./Div.: W-370/HAS/Program Management/Planning and Integration	6. Cog. Engr.: F. M. Simmons	7. Purchase Order No.: N/A
8. Originator Remarks: Letter Report, WHC-SD-W370-ER-001, Rev. 0, for signature approval.		9. Equip./Component No.: N/A
		10. System/Bldg./Facility: 2607-W6 Septic System
11. Receiver Remarks:		12. Major Assm. Dwg. No.: N/A
		13. Permit/Permit Application No.: N/A
		14. Required Response Date: May 31, 1994

15. DATA TRANSMITTED					(F)	(G)	(H)	(I)
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	Impact Level	Reason for Transmittal	Originator Disposition	Receiver Disposition
1	WHC-SD-W370-ER-001		0	Recommendations for Sanitary Waste Water System Replacement, 222-S	E	1		

16. KEY					
Impact Level (F)		Reason for Transmittal (G)		Disposition (H) & (I)	
1, 2, 3, or 4 (see MRP 5:43)		1. Approval 2. Release 3. Information	4. Review 5. Post-Review 6. Dist. (Receipt Acknow. Required)	1. Approved 2. Approved w/comment 3. Disapproved w/comment	4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged

17. SIGNATURE/DISTRIBUTION (See Impact Level for required signatures)										(G)	(H)
Reason	Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(J) Name	(K) Signature	(L) Date	(M) MSIN	Reason	Disp.
1	1	Cog. Eng. F. M. Simmons	<i>[Signature]</i>	5/20/94		Engineering R. L. Robertson	<i>[Signature]</i>	5/20/94		1	1
1	1	Cog. Mgr. S. M. Joyce	<i>[Signature]</i>	5/20/94		Engineering L. Goodwin	<i>[Signature]</i>	5/20/94		1	1
		QA									
		Safety									
1		Env. K. A. Gioia	<i>[Signature]</i>	5/20/94							
1	1	Landlord D. Danch	<i>[Signature]</i>	5/20/94							
1	1	Operations D. M. Thornton	<i>[Signature]</i>	5/23/94							

18. Signature of EDT Originator <i>[Signature]</i> 5/20/94	19. Authorized Representative Date for Receiving Organization <i>[Signature]</i> 5/20/94	20. Cognizant/Project Engineer's Manager <i>[Signature]</i> 5/20/94	21. DOE APPROVAL (if required) Ltr. No. ☐ Approved ☐ Approved w/comments ☐ Disapproved w/comments
---	---	--	--

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

RELEASE AUTHORIZATION

Document Number: WHC-SD-W370-ER-001, REV. 0

Document Title: Recommendation for Sanitary Waste Water System Replacement, 222-S

Release Date: 11/16/94

**This document was reviewed following the
procedures described in WHC-CM-3-4 and is:**

APPROVED FOR PUBLIC RELEASE

WHC Information Release Administration Specialist:

Niki L. Solis

11/16/94

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

This report has been reproduced from the best available copy. Available in paper copy and microfiche. Printed in the United States of America. Available to the U.S. Department of Energy and its contractors from:

U.S. Department of Energy
Office of Scientific and Technical Information (OSTI)
P.O. Box 62
Oak Ridge, TN 37831
Telephone: (615) 576-8401

Available to the public from: U.S. Department of Commerce
National Technical Information Service (NTIS)
5285 Port Royal Road
Springfield, VA 22161
Telephone: (703) 487-4650

SUPPORTING DOCUMENT		1. Total Pages 54 ^{KN}
2. Title Recommendation for Sanitary Waste Water System Replacement, 222-S	3. Number WHC-SD-W370-ER-001	4. Rev No. 0
5. Key Words SEPTIC, 2607-W6, SANITARY WASTE WATER, DRAINFIELD	6. Author Name: F. M. SIMMONS Signature Organization/Charge Code 8E210/JE082	
7. Abstract <p>The 2607-W6 septic system is not approved by the Washington State Department of Health. The system is over 40 years old and is operating at greater than 200% capacity. Under these conditions the system is subject to imminent failure and is not adequately treating the septic waste. This poses a potential personnel health risk. It is recommended that this system be upgraded by installation of a new drain field similar to the modification of the 2607-W1 system.</p> <p style="text-align: center; margin: 20px 0;">DISCLAIMER</p> <p>This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.</p>		
<div style="border: 1px solid black; padding: 10px; margin: 10px auto; width: 250px;"> 8. RELEASE STAMP <div style="border: 1px solid black; padding: 5px; text-align: center;"> OFFICIAL RELEASE 21 BY WHC DATE NOV 16 1994 <i>Sta. 21</i> </div> </div>		

LETTER REPORT
WHC-SD-W370-ER-001, Rev. 0

RECOMMENDATIONS FOR SANITARY WASTEWATER SYSTEM REPLACEMENT, 222-S LABORATORIES

W-370

INTRODUCTION

This letter report addresses alternatives for upgrading the 222-S sanitary sewer. Upgrading is necessary because of the following:

The existing system (2607-W6) is not in compliance with current Washington State Department of Health (WSDOH) requirements, specifically Washington Administration Code (WAC) 246-272.

The existing drain field is operating at 200% capacity (WHC-SD-LL-ES-020).

The existing drain field is allowed to operate without upgrades as long as the headcount is not increased or new projects are not added which will increase the flow to the system (2607-W6). Additional office facilities and staff increases are planned at the 222-S complex.

The existing system is over 40 years old and subject to imminent failure.

The system is currently handling existing flows. There is no apparent subsurface failure, but very high potential for failure due to the age and capacity of the system.

SUMMARY CONCLUSIONS, AND RECOMMENDATIONS

The system flow rate is approximately 5,200 gallons per day (GPD) and the system is designed to handle 2,600 GPD. The system is subject to imminent failure as the drain field is severely undersized. It is also possible that the system is not capable of adequately treating the septic waste because the soil drains excessively, even though it is able to dispose of the large volume of flow. This poses a potential personnel health risk.

The following alternatives were considered.

Alternative 1:

Do nothing.

Alternative 1 is unacceptable because it does not meet WSDOH requirements, and the current system poses a potential public health risk. This alternative does not support an additional 30 years of continued 222-S complex operations to support the cleanup mission.

Alternative 2:

Modify the existing system with the addition of a dosing tank which can be pumped out.

Alternative 2 is not cost effective. This method is currently being done elsewhere on site, specifically 2750E, where the capacity of the system has also been exceeded. The current flowrate of 6,500 gallons per day requires 18-20 pumpout loads per week at a cost of \$110,000 per year. The pump out costs are bid per year and are a function of the number of loads (2,500 gallons per load) per week. The current daily input (WHC-SD-LL-ES-020, Rev. 0) is 5215 gallons. This equates to 15 loads per week. The cost per year would be similar to the cost for 2750E. There is also an increased risk involved with transportation for spillage and accidents. The disposal lagoon is not permitted by the state. Because approximately 400,000 gallons per year are being disposed of in the lagoon, there is concern about additional disposal to the lagoon.

Increased environmental restrictions have the potential to increase the cost of alternative 2. Therefore it is prudent to replace the existing 2607-W6 system as an interim measure versus the continual pumping of the existing system.

Alternative 3:

Install a new tile field and dosing tank. The cost would be from \$500,000 to \$700,000 as this is similar to work that has been done previously in other areas such as the upgrade to 2607-W1, Project L-169, (L169LR, ER2929).

Alternative 3 is recommended. Since this drainfield will handle the same flowrate as L-169, preliminary design calculations and estimated costs are assumed to be the same. Soil samples have already been taken and the septic tank has been inspected. The existing septic tank will be used as the primary chamber. A second tank will be required in series to provide the necessary liquid capacity and the required two compartments. A new sand bed pressure drain field will be installed adjacent to the existing drain field. A minimum imported 2-ft. thick sand bed is required when constructing soil absorption systems in Type 1 soil. These requirements are cited in WAC 246-272-080 and further detailed in "Design Guidelines for Larger On-Site Sewage Systems."

Alternative 4

Wait for Project L-116 completion. The Landlord Program is funding a FY 1996 Line Item Project L-116 to install a centralized 200 Area sanitary sewer system which includes tie-in of the 222-S facilities. The Project L-116 system will not be operational until the middle of the year 2000 at its current support level.

Alternative 4 is not viable since it does not allow any increase in manpower at the 222-S complex until FY 2000. Project L-116 is not yet funded.

REFERENCES

1. Washington State Department of Social and Health Services
 - "Guidelines for Pressure Distribution Systems," 1984
 - "Guidelines for Sand Filters," 1989
 - "Design Guidelines for Larger On-Site Sewage Systems." 1987
2. Washington Administrative Code 246-272, "On-Site Sewage System."
3. U.S. Department of Energy Order 6430.1A, "General Design Criteria"
4. Letter Report L169LR; ER2929
5. WHC-SDE-LL-ES-020, REV 0, "200 AREAS SANITARY WASTE MANAGEMENT STUDY"