2.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

**A NOVEL CARBON-BASED PROCESS
FOR FLUE GAS CLEANUP**

**Fifth Quarterly Technical Progress Report
July 1 to September 30, 1992**

**Contract No. DE-AC21-91PC91345
Ms. Diane Revay Madden: DOE COR**

Submitted to:

**U.S. Department of Energy
Pittsburgh Energy Technology Center
P.O. Box 10940, Pittsburgh, PA 15236**

**S.K. Gangwal, Project Manager
Research Triangle Institute
Research Triangle Park, NC 27709
(919) 541-8033**

**P.L. Silveston, Co-Principal Investigator
University of Waterloo
Waterloo, Ontario, Canada N2L3G1
(519) 885-1211, Ext. 2534**

October 1992

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

Se

DOE/PC/91345--T7

DE93 006488

DOE/PC/91345--T7

Received by OSTI
JAN 29 1993

TABLE OF CONTENTS

<u>Section</u>		<u>Page</u>
	List of Tables and Figures	ii
	Abstract	iii
1.0	INTRODUCTION	1
1.1	Objective	1
1.2	Process Description	1
1.3	Background	2
1.4	Project Scope/Schedule	4
1.5	Measures of Success	6
2.0	WORK COMPLETED IN PREVIOUS QUARTERS	7
3.0	WORK COMPLETED IN PRESENT QUARTER	8
3.1	Accomplishments	8
3.2	SO ₂ Removal	8
3.2.1	SO ₂ Removal Experiments at 21°C	8
3.2.2	SO ₂ Removal Experiments at Higher Temperatures	8
3.3	NO _x Removal	10
3.4	Process Economic Evaluation	12
4.0	WORK PLANNED FOR NEXT QUARTER	13
4.1	SO ₂ Removal	14
4.2	NO _x Removal	14
4.3	Process Evaluation	14
5.0	REFERENCES	15
6.0	APPENDIX	16

LIST OF TABLES

Table 1	Advantages of Process	2
Table 2	SO ₂ Removal Test Results (37.22 g of MCCI, 130°C, 1,475 scc/(cc · h) Flue-Gas Containing 2,550 ppm SO ₂ , 450 ppm NO, 10% CO ₂ , 10% H ₂ O, 5% O ₂ , and Balance N ₂ , 200 cc 4.32 N H ₂ SO ₄ flush after each cycle)	10
Table 3	Feed Gas Composition for NO Removal Test of MCCII	11
Table 4	NO Removal with MCCII at 150°C	11
Table 5	Process and Economic Assumptions	12
Table 6	RTI-Waterloo Process Economic Performance (100 MW Power Plant, 65% Capacity Factor)	13
Table 7	Cost of SO ₂ /NO _x Removal (Mid 1991 \$)	13

LIST OF FIGURES

Figure 1	Flue gas cleanup process concept	1
Figure 2	Multistage activated carbon scrubbing process with pulsed liquid flow and cooling of the feed gas and reheating of the off-gas by heat recovery	3
Figure 3	Outlet Temperature and SO ₂ Concentration Versus Run Time (MCCI Catalyst, Inlet Temperature 80°C.	9

ABSTRACT

The objective of this project is to demonstrate the preliminary technical and economic feasibility of a novel carbon-based process for removal of at least 95% SO_2 and at least 75% NO_x from coal combustion flue gas. In the process, flue gas leaving the electrostatic precipitator (ESP) is passed through a trickle bed of activated carbon catalyst employing a periodic flush of low strength sulfuric acid. The SO_2 is oxidized to SO_3 and removed as medium strength sulfuric acid. The SO_2 -free flue gas is then mixed with NH_3 , and the NO_x in the gas is subjected to selective catalytic reduction (SCR) to N_2 over a fixed bed of activated carbon catalyst.

The project is being carried out over 23 months (June 4, 1991, to April 30, 1993). The experimental work is divided between Research Triangle Institute (RTI) and the University of Waterloo (Waterloo). RTI will primarily conduct the NO_x removal studies, whereas Waterloo will conduct most of the SO_2 removal studies. The ultimate goal of the project is to demonstrate that the process can reduce the cost of electricity by 20% over conventional SCR/flue gas desulfurization (FGD) processes.

In the previous four quarters, a detailed project management plan was prepared describing the experimental setup, work plan, and test plan. The experimental system was completed for SO_2 conversion at Waterloo and for NO_x conversion at RTI. Shakedown experiments were completed. Scoping studies at Waterloo with the BPL carbon showed that periodic flushing could only achieve up to 40% SO_2 removal with one bed. The SO_2 removal factorial experiments were begun at Waterloo with the BPL carbon at 21°C. SO_2 removal was also tested at RTI on two catalysts at 80°C. It was shown that the BPL carbon could remove over 95% SO_2 at 21°C but would require several beds at a space velocity in each bed of about 1500 scc/(cc·h) to reduce SO_2 from 2,500 ppm to 100 ppm. A modified carbon catalyst (MCCI) tested at RTI showed 99% SO_2 removal at 80°C and 1,400 scc/(cc·h). The modified carbon catalyst also demonstrated removal of more than 80% NO_x at around 140°C and 1,400 scc/(cc·h).

The NO_x removal performance of two additional modified carbon catalysts (MCCII and MCCIII) was studied. MCCII showed NO_x removal efficiency which was similar to that observed for MCCI. However, MCCIII was considerably less active for NO_x removal. SO_2 removal experiments with NO present in the feed gas were performed with MCCI. SO_2 removal efficiency was consistently about 98% over each of 10 cycles and was very similar to that observed earlier with no NO present in the feed. Finally, a preliminary economic evaluation of the process was performed and a project review meeting was held. The economic evaluation showed that the RTI-Waterloo process was competitive with SCR/FGD and other combined SO_2/NO_x removal processes.

In the present quarter, further tests of MCCI were performed for SO_2 removal with NO in the feed gas, except the reactor was operated at 130°C (instead of 80°C during previous tests). Tests were also performed with MCCII for NO removal with nominally 100 ppm SO_2 in the feed gas. Papers were presented at the AIChE meeting in Minneapolis and the Contractor's Review Meeting in Pittsburgh.

1.0 INTRODUCTION

1.1 OBJECTIVE

The objective of this project is to demonstrate the preliminary technical and economic feasibility of a novel carbon-based process for removal of at least 95% SO_2 and at least 75% NO_x from coal combustion flue gas. The process is based on the demonstrated ability of activated carbons to catalyze SO_2 oxidation and NO_x reduction below 150°C .

1.2 PROCESS DESCRIPTION

The process concept is shown in Figure 1. The hot flue gas leaves the electrostatic precipitator (ESP) at $\sim 150^\circ\text{C}$ and enters a recuperative gas-gas heat exchanger, employing a bed of ceramic balls, to cool the flue gas for SO_2 removal and simultaneously heat the cold flue gas for NO_x removal. The gas leaving the exchanger enters a series of two to three activated carbon trickle-bed catalytic reactors at approximately 100°C to remove the SO_2 and convert it to medium strength sulfuric acid. The essentially SO_2 -free gas from the last trickle bed goes through the exchanger to the NO_x converter. The required amount of NH_3 (typically in an NO_x/NH_3 mol ratio of 1) is mixed with the flue gas prior to the activated carbon catalyst bed. The advantages of the proposed process concept compared to currently available SO_2/NO_x processes are summarized in Table 1.

Figure 1. Flue gas cleanup process concept.

Table 1. Advantages of Process

SO₂ Removal

● Easier retrofit	- Downstream of ESP where space is more readily available
● No waste product	- Sulfuric acid is potentially marketable
● Low temperature	- Reduced equipment stress, nonenergy intensive, no hazards including carbon combustion
● Simple regeneration	- No carbon loss
● Periodic operation	- Low pressure drop, concentrated sulfuric acid

NO_x Removal

● High catalyst life	- Low temperature operation in the absence of SO ₂ and particles significantly increases catalyst life
● Low salt/SO ₃ formation	- Due to complete SO _x removal upstream, the acid dew point of the gas is very low and salt formation is avoided
-
-

1.3 BACKGROUND

The SO₂ removal process proposed herein is based on the well-known low-temperature catalytic properties of activated carbon, but uses a novel periodically flushed trickle bed to produce a strong acid and a low level of SO₂ in the gas discharge. Hartman et al. (1971) and Hartman and Coughlin (1972) provide a detailed description of the mechanism of SO₂ oxidation [$\text{SO}_2 + (1/2)\text{O}_2 \rightarrow \text{SO}_3$ or $\text{SO}_2 + (1/2)\text{O}_2 + \text{H}_2\text{O} \rightarrow \text{H}_2\text{SO}_4$] over activated carbon. The SO₃ formed does not desorb spontaneously at low temperature. It is desorbed with water as sulfuric acid. Sulfuric acid, however, suppresses the ionization of dissolved sulfur dioxide and solubility of oxygen so that countercurrent contacting must be used to continue the reaction at an appreciable rate. Acid formation is accomplished in our process by periodic flushing, which results in a lower pressure drop and more concentrated sulfuric acid than achievable by continuous flushing.

Work in the co-principal investigator's laboratory at the University of Waterloo (Waterloo) (Haure et al., 1989) has shown the feasibility of the process. With a single bed and periodic water flushing (0.9 min water flow in every 90-min cycle), a time averaged acid concentration of nearly 0.2 molar was achieved. Based on this result, a conceptual process employing acid recycle to produce medium strength sulfuric acid is shown in Figure 2. SO_2 is absorbed from the gas phase and converted into sulfuric acid by two to three in-line periodically liquid-pulsed beds of carbon. Typically water, dilute strength acid or medium strength acid flows through them for 2 to 4 min in every 30- to 40-min cycle. The gas phase flows through the beds continuously. Co-current flow is employed so that high superficial velocities can be used without flooding. Two to three in-line, co-current trickle beds of sufficient depth should provide complete removal of SO_2 . The recycling arrangement passes the strongest acid through the bed, treating the richest gas, and thereby produces medium strength acid as a product. The gas-gas heat exchanger brings the flue gas leaving the third bed to the desired temperature for catalytic NO_x removal, which is the second part of our process, as shown previously in Figure 1.

Figure 2. Multistage activated carbon scrubbing process with pulsed liquid flow and cooling of the feed gas and reheating of the off-gas by heat recovery.

NO_x is reduced in a separate reactor at 120°C using NH_3 after the SO_2 has been removed, and the N_2 and H_2O are vented to the stack. One possible reaction is $4\text{NH}_3 + 4\text{NO} + \text{O}_2 \rightarrow 4\text{N}_2 + 6\text{H}_2\text{O}$, although many others are possible. Many catalysts for the NH_3 - NO reaction are reported in the literature (commercially practiced in selective catalytic reduction (SCR) technology using vanadium-based catalysts). However, many of these catalysts are inactive at 120°C . A comprehensive unpublished review of the literature by the principal investigators indicated that activated carbon or "coke" catalysts are the only catalysts with the potential to carry out the reaction at 120°C . Such catalysts are commercially used in the Mitsui process, which claims some 85% NO_x removal at 130°C . A number of studies (Kusakabe et al., 1988; Kuehl et al., 1986; Seki et al., 1975; U.S. Patent 4,194,373; Kareko et al., 1988) corroborate that activated carbons are active low temperature catalysts for the NO - NH_3 - O_2 and NO - NH_3 reactions. These studies further suggest that activated carbons promoted with very small quantities of group VIII transition metals (particularly platinum) should be considered.

1.4 PROJECT SCOPE/SCHEDULE

The novel carbon-based process to be studied has the potential to provide a technically sound and economically attractive solution to flue gas cleanup. The SO_2 removal experiments will be carried out in the apparatus of Haure et al. (1989) at Waterloo, modified to handle dilute to medium strength sulfuric acid and temperatures up to 100°C . The questions to be addressed in the research include:

- What acid concentrations are attainable by periodic pulsing and acid recycle?
- What is the pressure drop as a function of time during a cycle of no liquid flow to liquid flow?
- What is the optimum size of the granular activated carbon?
- What is the optimum pulse length to prevent poisoning (as occurring in steady-state operation) of the activated carbon?
- What is the optimal temperature of operation?
- What will be the effect and fate of NO_x ?

The experimental parameters investigated will include carbon type, size, bed depth, gas composition, liquid composition, gas velocity, liquid velocity, cycle time, flush time and gas temperature. To reduce the number of variables, the carbon used will be the BPL carbon (Calgon Corporation) which was found to be the most active in the previous study. Because the experiments are expected to be short, a large number of parametric experiments will be carried out to prove feasibility and obtain data to permit a process evaluation.

The NO_x removal experiments will be carried out at Research Triangle Institute (RTI). The experiments will be geared toward demonstrating >75% NO_x removal from off-gases expected from the activated carbon SO₂ conversion process. The principle variables considered will include carbon type (BPL carbon, 0.1 to 1% Pt on carbon, and three others), temperature (100 to 150°C), and space velocity [5,000 to 20,000 scf/(cf·h)]. A proper N₂ balance will be carried out in each experiment and slip of NH₃ and NO/NO_x in the reaction products will be measured. The effect of traces of SO₂ up to 250 ppmv on NO_x conversion will be examined.

Based on the experimental data, technical and economic evaluation of the process for 1 MW and 100 MW plants will be carried out. The technical evaluation shall determine the degree of SO₂ and NO_x removal that may be achieved in full-scale plants using the data collected in the controlled laboratory experiments. Economic evaluation will determine the cost of our process on unit power generation basis. The predicted cost will be compared with the cost of the conventional limestone flue gas desulfurization (FGD)/SCR system. If cost is at least 20% less for our process, our process will be considered for scaleup in future investigations.

The work to be carried out is divided into the following tasks:

<u>Task</u>	<u>Schedule</u>
Task 1: Program Definition (RTI and Waterloo)	June 4, 1991, to July 31, 1991
Task 2: Experimental 2.1: SO ₂ Removal (Waterloo) 2.2: NO _x Removal (RTI)	August 1, 1991, to February 28, 1993
Task 3: Process Evaluation (RTI)	May 1, 1992, to April 30, 1993

Task 1 (Program Definition) entails preparation of a detailed Project Management Plan describing a detailed work plan for the entire project and detailed test plans describing the experimental work. In Task 2 (Experimental), facilities will be constructed and experiments will be carried out per the approved Project Management Plan. SO₂ removal experiments will be carried out at Waterloo under the supervision of Dr. P.L. Silveston. NO_x removal experiments will be carried out at RTI under the supervision of Dr. S.K. Gangwal. In Task 3 (Process Evaluation), technical and economic evaluation of the process for 1 MW and 100 MW plants will be carried out by RTI.

It will be important to maintain a high degree of communication between Waterloo and RTI to ensure success of the project. The communication will be maintained by weekly conference calls. Also, an RTI investigator will travel to Waterloo at least twice during the

project to review their experimental progress. Similarly, a Waterloo investigator will travel to RTI at least twice during the project.

1.5 MEASURES OF SUCCESS

The targets that we hope to achieve during the course of our experiments are:

- 95% or greater removal of SO_2 ,
- Production of at least 2 molar sulfuric acid,
- Pressure drop of at most 30 in. in the SO_2 removal process,
- 75% or greater removal of NO_x , and
- 25 ppmv or less NH_3 slip.

The experimental data would also indicate how to achieve further improvements in the above targets. The project is designed to prove the technical and economic feasibility of the process and provide sufficient data to permit a preliminary process evaluation. The ultimate test of the success of the project will be whether the process can reduce the cost of electricity over conventional FGD/SCR processes by 20%.

2.0 WORK COMPLETED IN PREVIOUS QUARTERS

The accomplishments in the previous quarters were as follows:

- A paper was published and presented at the Seventh Annual Coal Preparation, Utilization, and Environmental Control Contractors' Conference sponsored by the U.S. Department of Energy/Pittsburgh Energy Technology Center (DOE/PETC);
- Task 1 was completed. A detailed Project Management Plan was prepared describing the work plan, experimental apparatus, experimental test plan/sequence, milestone schedule, cost plan, key personnel plan, project management structure, and measures of success;
- Task 2 was begun. The assembly of experimental apparatus and shakedown tests at Waterloo and RTI were completed with the exception of the installation of a continuous SO₂ analyzer.
- Sufficient catalysts were procured for the SO₂ removal experiments at Waterloo and for the NO_x removal experiments at RTI.
- A number of catalyst screening tests were completed for SO₂ and NO_x conversion. It was shown that 75% NO_x conversion was possible on selected carbon catalysts.
- A continuous SO₂ analyzer system was commissioned at Waterloo and SO₂ removal factorial experiments with BPL carbon at 21°C began.
- SO₂ removal was also tested at RTI on a modified carbon catalyst and a CarboTech carbon at a higher temperature (80°C).
- NO_x removal was tested at RTI on a number of carbon-based catalysts.
- The modified carbon catalyst (MCCI) tested at RTI consistently removed 99% SO₂ over multiple cycles at 80°C and 1,400 scc/(cc·h).
- The modified carbon catalyst also demonstrated removal of more than 80% NO_x at about 140°C and 1,400 scc/(cc·h).
- A second modified carbon catalyst (MCCII) showed NO_x removal efficiency which was similar to that observed for MCCI.
- SO₂ removal efficiency using MCCI with NO in the feed gas was consistently about 98% over 10 cycles.
- An economic evaluation showed that the RTI-Waterloo process is competitive with SCR/FGD and other combined SO₂/NO_x removal processes.

3.0 WORK COMPLETED IN PRESENT QUARTER

3.1 ACCOMPLISHMENTS

The accomplishments in the present quarter are as follows:

- Tests of MCCI at 130°C were performed for SO₂ removal with NO in the feed gas.
- Tests of MCCII were performed for NO removal with nominally 100 ppm SO₂ in the feed.
- The economic evaluation work was expanded to include cost sensitivity with respect to catalyst cost, catalyst life, acid strength, and number of beds for the SO₂ removal part of the process.

3.2 SO₂ REMOVAL

3.2.1 SO₂ Removal Experiments at 21°C

See Appendix 1.

3.2.2 SO₂ Removal Experiments at Higher Temperatures

The same modified carbon catalyst (MCCI) which had previously been used for tests of SO₂ removal at 80°C with NO present in the feed was tested at 130°C. The purpose of this test was to examine the effect of reactor temperature on SO₂ removal in the early part of a cycle. As described in the previous quarterly report, when the reactor was operated at 80°C, the SO₂ removal initially was greater than 95%, but would decrease to about 40% and then return to greater than 95% over a 1-2 hour period, before beginning to decrease again. A plot which illustrates this behavior is shown in Figure 3. It is believed that the lower reactor outlet temperature is caused by water evaporation following the cold liquid flush. This appears to reduce the SO₂ removal during the time in which the bed is heating to the inlet temperature of 80°C.

To test whether this behavior could be prevented, a 3-cycle test was performed on MCCI at 130°C. The results of this test, shown in Table 2, indicate that SO₂ removal at the beginning of exposure is greater than 97, but that breakthrough occurs in about 1/3 of the time observed previously in 80°C tests. However, the period of time in which conversion is greater than 95% is about the same as that observed at 80°C and the percent SO₂ removal does not decrease in the early part of the cycle as observed before. Operating the reactor at 130°C offers the advantage of sustained high SO₂ removal efficiency with a breakthrough time which is feasible for the periodic flush process. Since the overall breakthrough time

Figure 3. Outlet Temperature and SO₂ Concentration Versus Run Time (MCCI Catalyst, Inlet Temperature 80°C).

Table 2. SO₂ Removal Test Results (37.22 g of MCCI, 130°C, 1,475 scc/(cc·h) Flue-Gas Containing 2,550 ppm SO₂, 450 ppm NO, 10% CO₂, 10% H₂O, 5% O₂, and Balance N₂, 200 cc 4.32 N H₂SO₄ flush after each cycle)

Cycle	Breakthrough time (h) (at 5%)	Percent SO ₂ Removal	SO ₂ Converted, (g)
1	1.75	99.6	3.83
2	0.8	97.8	1.67
3	1.1	99.7	2.32

however is shorter, the results suggest that the optimum temperature may be closer to 100°C with respect to both capacity and SO₂ removal efficiency.

3.3 NO_x REMOVAL

A batch of MCCII which had been used previously for SO₂ removal tests was used to test NO removal with nominally 100 ppm SO₂ in the feed gas. The feed gas composition is summarized in Table 3.

The reactor was operated at a temperature of 150°C and a space velocity of 1480 scc/(cc·h). Results of a 24 hour deactivation test are shown in Table 4. Based on these results, there did appear to be some deactivation of the catalyst over the 24 hour period, as conversion decreased from 79% to 66% however the reason for the cycling up at 18 hours is not clear. The catalyst needs to be run longer to firm up this data.

Before SO₂ was introduced into the feed gas at the beginning of the test, the NO conversion was near 100%. When the SO₂ was added, the increase in the outlet NO concentration was equivalent to the feed gas SO₂ concentration. This suggests that ammonia preferentially reacts with SO₂, thus making it unavailable for reduction of NO. This explains the need for a higher NH₃/NO ratio in the feed (1.57) compared with what was needed previously (1.26) to achieve >75% NO reduction with no SO₂ present. However, the overall process shows capability for 100% SO₂ removal and this may need to be traded with any potential catalyst deactivation. If (NH₄)₂SO₄ formation on the catalyst is the cause of deactivation, then it may be possible to wash it off, to reactivate the catalyst. A moving-bed system might be employed in this scenario.

Table 3. Feed Gas Composition for NO Removal Test of MCCII

Component	Feed Concentration
NO	500 ppm
SO ₂	106 ppm
NH ₃	783 ppm
Steam	11.7%
CO ₂	10%
O ₂	5%

Table 4. NO Removal with MCCII at 150°C

Time On Stream, hrs.	Percent NO Conversion
2	79
4	79
6	78
8	71
10	69
12	68
14	68
16	64
18	74
20	74
22	66
24	66

3.4 Process Economic Evaluation

Based on the results to date, a preliminary engineering and economic evaluation of the RTI-Waterloo process was conducted for a 100 MW electric power plant burning a 2.8% sulfur coal. The process and economic assumptions are shown in Table 5. The Electric Power Research Institute (EPRI) technical assessment guide (TAG) method was used for the calculations. An economic sensitivity analysis of the process with respect to the SO₂ conversion reactor variables (no. of stages, catalyst cost, and catalyst life) was performed. In addition, sensitivity of the economics was performed for the acid product strength. It was assumed that the SO₂ reactors would yield 32 weight % H₂SO₄ and this was further concentrated using an external evaporator to 77.67 and 93.2 weight % H₂SO₄. The capital and levelized cost for this analysis is shown in Table 6 and compared to conventional and emerging SO₂/NO_x removal processes in Table 7. Even considering that the scale used for the RTI-Waterloo process was 100 MW as opposed to 500 MW for the other processes, the RTI-Waterloo process was competitive with the other processes.

Table 5. Process and Economic Assumptions

Power Plant Capacity	--	100 MW, 65% Capacity Factor
Coal Type	--	Illinois #6, 2.8% Sulfur
Flue-Gas Composition	--	72.6% N ₂ , 4.5% O ₂ , 12.6% CO ₂ , 10% H ₂ O, 2300 ppm SO ₂ , 530 ppm NO _x
SO ₂ Conversion	--	2 or 3 Stages, 10,000 h ⁻¹ in each stage
NO _x Conversion	--	1 Stage, 3500 h ⁻¹ , NH ₃ /NO _x = 1.35, Promoted Carbon Catalyst, \$20/lb
Acid Storage	--	24 hours
Value of 32% H ₂ SO ₄	--	\$24/ton
Value of 77.67% H ₂ SO ₄	--	\$58/ton
Value of 93% H ₂ SO ₄	--	\$70/ton
Cost of NH ₃	--	\$150/ton
Dollars	--	Mid 1991

**Table 6. RTI-Waterloo Process Economic Performance
(100 MW Power Plant, 65% Capacity Factor)**

Stages (--)	SO ₂ Conversion		Acid Product Strength (Weight %)	Capital Cost (\$/kW)	Levelized Cost (Mils/kWh)
	Catalyst Cost (\$/lb)	Catalyst Life (Yrs)			
3	20	3	32	179	8.2
2	20	3	32	162	6.8
3	20	3	77.67	188	9.0
3	20	6	77.67	188	7.3
2	20	6	77.67	171	6.4
3	20	6	93.2	188	8.3
2	20	6	93.2	171	7.4
3	3	2	77.67	169	6.3
3	3	2	93.2	169	8.0

Table 7. Cost of SO₂/NO_x Removal (Mid 1991 \$)

Process	MW	Capital Cost (\$/kW)	Levelized Cost (Mils/kWh)
Conventional SGD/SCR	500	200	8.8
Advanced FGD/SCR	500	170	7.8
NOXSO	500	215/260/300	8/11.8/17
SNOX	500	330/375/430	8.8/10.4/13
E-Beam	500	310/400/440	9/13.2/15.3
RTI/Waterloo	100	162 to 188	6.3 to 9.0

Estimates except for RTI/Waterloo process from Cichanowicz, et al., Engineering Evaluation of Combined NO_x/SO₂ Controls, 1991.

4.0 WORK PLANNED FOR NEXT QUARTER

4.1 SO₂ Removal

Tests of the unmodified carbon corresponding to MCCI will be performed. Tests of a different modified carbon catalyst (MCCIV) will also be performed.

4.2 NO_x Removal

Tests of the unmodified carbon corresponding to MCCI will be performed.

4.3 Process Evaluation

A detailed economic evaluation report will be prepared.

5.0 REFERENCES

- Hartman, M., and R.W. Coughlin. 1972. *Chem. Eng. Sci.* 127:867-880.
- Harman, M., J. Polek, and R.W. Coughlin. 1971. *Chem. Eng. Prog. Symp. Ser.*, No. 115, 67:7-22.
- Haure, P., R.R. Hudgins, and P.L. Silveston. 1989. *AIChE Journal*, 35:1437.
- Kareko, K., Y. Nakahigashi, and K. Nagata. 1988. *Carbon*, 26(3):327-333.
- Keuhl, H., E. Richter, K. Knoblauch, and H. Juentgn. 1986. *Carbon '86*, Bergan-Forschung, Essen, Germany, pp. 351-353.
- Kusakube, K., M. Karhima, S. Morook, and K. Shigeharu. 1988. *Fuel*, 67(5):714-718.
- Seki, M., Y. Sakurai, and K. Yoshida. 1975. *Am. Chem. Soc. Div. Eng. Chem. Reprints*: 15(2), Chicago Meeting, August 24-29, pp. 28-31.

APPENDIX 1
UNIVERSITY OF WATERLOO
QUARTERLY REPORT

1.0 WORK COMPLETED IN PRESENT QUARTER (July - October 1992)

1.1 ACCOMPLISHMENTS

- Completed first set of factorial experiments
- Demonstrated that 2N sulfuric acid strengths can be achieved
- Calculated bed depth and pressure drop for 95% SO₂ removal

1.2 SO₂ REMOVAL EXPERIMENTS AT 21 °C

These experiments were carried out at the University of Waterloo. The equipment was run at 21°C with a gas mixture of 2500 ppm SO₂, 5% O₂, 15% CO₂, and the balance N₂.

The factorial design method that was started last quarter to determine which of the five operating variables would most affect SO₂ removal (meaning removal of SO₂ from the gas), SO₂ conversion (meaning percentage of total SO₂ passing through the reactor converted to sulfuric acid), acid strength of product (maximum sulfuric acid, minimum sulfurous acid) and pressure drop has been completed. At this time however I can not complete an analysis for bed pressure drop (ΔP) because part way through the experiments a change was made in order to more accurately measure the bed ΔP . Table 1 shows the range and the variables studied. A total of 16 experiments were required with 8 replicates in order to estimate the experimental variance. This is a 2⁵⁻¹ factorial design of resolution V. Resolution V means that single factor interactions are confounded with four factor interactions, and two factor and three factor interactions are confounded.

It should be noted that the flushing medium (deionized water, 2.0 N sulfuric acid) is a blocked variable for convenience. The settings of the five different variables for each of the 24 experiments and the results are illustrated in Table 2. Where 2 experiments at a single set of conditions were done, in order to estimate the experimental variance, the results were averaged and are displayed as a single result.

Table 1: Levels of Variables studied in Factorial Experiments

Variables	Low Value "-"	High Value "+"
1-Space Velocity(V _l)	1000 cc•cc ⁻¹ • hr ⁻¹	2900 cc•cc ⁻¹ •hr ⁻¹
2-Liquid Velocity(V _g) (superficial)	0.2 cm•s ⁻¹	1.0 cm•s ⁻¹
3-Period(τ)	5 minutes	30 minutes
4-Flush Duration(D)	0.5 minutes	3 minutes
5-Flush Liquid(A)	Deionized Water	2.0 N H ₂ SO ₄

Table 2: Results of First Factorial Experiments

Block A - Flushing Liquid Pure Deionized Water						Acid Concentrations			
Expt#	Vg	VI	τ	A	D	Removal	Conversion	[SO ₃ ²⁻]	[SO ₄ ²⁻]
12	-1	-1	-1	-1	1	76.00	24.96	0.002480	0.001210
5,6	1	-1	-1	-1	-1	10.53	5.49	0.004600	0.005010
4,8	-1	1	-1	-1	-1	51.64	22.77	0.001685	0.001380
7	1	1	-1	-1	1	73.25	22.55	0.001390	0.000620
3,10	-1	-1	1	-1	-1	14.42	13.23	0.002095	0.023320
9	1	-1	1	-1	1	12.72	10.62	0.001780	0.009010
2,11	-1	1	1	-1	1	39.36	23.63	0.000905	0.001355
1	1	1	1	-1	-1	5.45	3.24	0.002320	0.003990
Block B - Flushing Liquid 1 Mol/L Sulfuric Acid									
5	-1	-1	-1	1	-1	14.49	10.13	0.001260	0.002920
9	1	-1	-1	1	1	15.90	7.20	0.001340	0.001110
11	-1	1	-1	1	1	53.70	25.95	0.000250	0.000230
12	1	1	-1	1	-1	13.53	9.83	0.000540	0.001450
6,8	-1	-1	1	1	1	16.29	12.55	0.001100	0.003715
2,7	1	-1	1	1	-1	4.92	4.64	0.001285	0.022130
3,4	-1	1	1	1	-1	13.76	12.12	0.000585	0.004335
1,10	1	1	1	1	1	10.80	6.59	0.000705	0.001100

The main effect of each variable was calculated by using the Yate's Algorithm. The main effect is the average of the response at the high value of the variable and the average at the low value of the variable. The significance of an effect was then determined by using a statistical significance test after calculating the estimated standard error of an effect from the replicates.

The conclusions of the initial factorial design are as follows:

Removal

Single Factor Effects

- V_g - increasing the gas velocity had a detrimental effect on the removal. The average effect of the increase in the gas velocity can be seen in Figure 1.
- V_l - increasing the superficial liquid velocity increases removal. (Figure 2)
- D - increasing the flush duration increases the removal. (Figure 3)
The effects of V_l and D indicate an increase in contact between the liquid and gas phases resulting in higher removals
- τ - increasing the period reduces the removal. (Figure 4)
This effect indicates that the catalyst surface becomes saturated with adsorbed SO_2 and can no longer remove additional SO_2 from the gas phase
- A - increasing the liquid phase acid strength reduces removal. (Figure 5)

Two Factor Effects

- τ, D - the optimum removal is obtained by using a short period with a long flush duration
- τ, A - the optimum removal is obtained with a short period and minimum acid strength of the liquid phase, however as the liquid phase acid strength increases (due to recycling of liquid phase), the period should be increased in order to maintain the removal.

Conversion

- V_g - This is the only factor affecting the conversion. Increasing the gas velocity reduces the conversion. (Figure 6)

Average Effect of Gas Velocity
on Removal

Average Effect of Superficial Liquid
Velocity on Removal

Average Effect of Liquid Flush
Duration on Removal

Average Effect of Cycle Period
on Removal

Average Effect of Acid Strength for
Catalyst Flushing on Removal

Average Effect of Gas Velocity
on Conversion

Sulfurous Acid Concentration Present in the Product

Single Factor Effects

- V_g - increasing the gas velocity increases the amount of sulfurous acid in the product. (Figure 7)
- V_l - increasing the superficial liquid velocity decreases sulfurous acid concentration in the product due to increased dilution. (Figure 8)
- τ - increasing the period reduces the sulfurous acid concentration. (Figure 9)
This is probably because the increased time without the liquid phase liquid phase increases the amount of SO_2 converted to SO_3 on the catalyst surface.
- A - increasing the liquid phase acid strength decreases sulfurous acid concentration. (Figure 10)

Two Factor Effects

- τ, A - to minimize sulfurous acid concentration a long period with high liquid phase acid strength is favoured

Sulfuric Acid Concentration in the Product

Single Factor Effects

- V_l - increasing the liquid superficial velocity reduces the sulfuric acid concentration. (Figure 11) This is due to dilution.

Two Factor Effects

- τ, V_l - to maximize the sulfuric acid concentration it will be necessary to increase the period and reduce the liquid superficial velocity.

From the above results it appears that the objectives of removal and conversion to sulfuric acid are at cross purposes. However, since marketability of the sulfuric acid product is paramount to the usefulness of this process conversion is the more significant factor. Removal however can be increased by using a deeper reactor bed. For all future experiments the a period of 30 minutes will be used. This approach will also increase the concentration of sulfuric acid in the product compared to the concentration of sulfurous acid.

Since we can increase the product acid strength over the 2N sulfuric acid used to flush the catalyst we can conclude that at least 2N acid strengths can be achieved using this process. In fact RTI has demonstrated even higher acid strengths can be achieved. As part of our future work we will also go to acid concentrations as high as 10N.

Average Effect of Gas Velocity
on Sulfurous Concentration

Average Effect of Superficial Liquid Velocity on Sulfurous Concentration

Average Effect of Cycle Period
on Sulfurous Concentration

Average Effect of Acid Strength for
Catalyst Flushing on Sulfurous Conc.

Average Effect of Superficial Liquid
Velocity on Sulfuric Concentration

Initial calculations have been completed to predict the required bed height and the reactor ΔP for 95% SO_2 removal. The average for all the experiments in the factorial design were a bed height of 134 cm and dry ΔP of 212 Pa. To achieve 95% SO_2 removal at a gas velocity of $2850 \text{ scc}\cdot\text{cc}^{-1}\cdot\text{hr}^{-1}$, period of 30 minutes, flush liquid acid strength of 1M, superficial liquid velocity of $0.2 \text{ cm}\cdot\text{s}^{-1}$ and a flush duration of 0.5 minutes the reactor bed would be 380 -611 cm high and have a dry pressure drop of 438 - 707 Pa. This was done to calculate the absolute maximum pressure drop and bed height for this process. It should be noted however that all these results are at a bed temperature of 21°C and we do not expect an industrial application at this temperature. Experiments done at RTI indicate that 95% removal can be achieved quite easily at 80°C and we will also run experiments at these conditions in a continuous mode.

1.3 WORK PROGRESS FOR THE PAST QUARTER

The major problem to note this quarter was a loss of accuracy in the total acidity determinations. The accuracy of our auto-titrator is $\pm 0.05 \text{ ml}$. When we were using deionized water as the flushing liquid and 0.1N NaOH to titrate the accuracy was excellent. This was verified by comparing the removal based on wet chemistry and the removal based on the ultra-violet SO_2 gas analyzer. However, when the flushing liquid was changed to 2N sulfuric acid we had to use 1N NaOH to titrate in order to keep the quantity of titrant at a manageable level. These two factors reduced the accuracy of our total acidity determinations. To correct for this I used the ultra-violet gas analyzer results to calculate removal. The quantity of sulfuric acid created in the product could then be determined based on the removal and subtracting the quantity of sulfurous acid present in the product. The sulfurous acid titration does not appear to have been affected by the increase in the flushing liquid acid strength.

2.0 WORK PLANNED FOR NEXT QUARTER

2.1 SO₂ REMOVAL

After completion of the current factorial design we will run experiments at higher temperatures (80°C) using the BPL activated carbon to see if there is an improvement in removal, conversion and sulfuric acid concentration. We will also test the MCCI carbon at the higher temperature for extended periods to see if there is any reduction in removal as seen in the BPL Carbon at low temperatures. Modifications to the equipment are currently underway in order that we can operate at increased temperatures. Table 3 shows the levels of the variables to be studied in the next quarter.

Table 3: Levels of Variables studied in Factorial Experiments at 80°C

Variables	Low Value "-"	High Value "+"
1-Space Velocity(V_l)	1000 cc•cc ⁻¹ •hr ⁻¹	2850 cc•cc ⁻¹ •hr ⁻¹
2-Liquid Velocity(V_g) (superficial)	0.2 cm•s ⁻¹	1.0 cm•s ⁻¹
3-Flush Duration(D)	0.5 minutes	3 minutes
4-Catalyst(C)	BPL	MCCI
5-Flush Liquid(A)	Deionized Water	2.0 N H ₂ SO ₄

END

DATE
FILMED

3 / 17 / 93