DOE/PC/89664--T5

RECEIVED
FEB 16 1993
OSTI

**ADVANCED COAL CONVERSION PROCESS
DEMONSTRATION PROJECT**

Environmental Monitoring Plan

DOE/PC/89664--T5

DE93 007623

Prepared For:

Rosebud SynCoal Partnership
Colstrip, Montana

DOE Contract
DE-FC22-90PC89664

Prepared by:

Western Energy Company
Colstrip, Montana

April 1992

For submittal to:

United States Department of Energy
Pittsburgh Energy Technology Center

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

for

LEGAL NOTICE

This report was prepared by Western Energy Company pursuant to a cooperative agreement partially funded by the U.S. Department of Energy and neither Western Energy Company nor any of its subcontractors nor the U.S. Department of Energy nor any person acting on behalf of either:

- (a) Makes any warranty or representation, express or implied with respect to the accuracy, completeness, or usefulness of the information contained in this report; or
- (b) Assumes any liabilities with respect to the use of, or for damages resulting from the use of, any information, apparatus, method or process disclosed in this report.

The process described herein is a fully patented process. In disclosing design and operating characteristics, neither Western Energy Company nor Rosebud Syncoal Partnership release any patent ownership rights.

References herein to any specific commercial product, process, or service by trades, name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the U.S. Department of Energy. The views and opinion of authors expressed herein do not necessarily state or reflect those of the U.S. Department of Energy.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

**Environmental Monitoring Plan
Rosebud SynCoal Partnership
Advanced Coal Conversion Process Demonstration
Colstrip, Montana**

TABLE OF CONTENTS

1.0 Introduction

- 1.1 EMP Purpose**
- 1.2 EMP Scope**
- 1.3 Implementation of the EMP**

2.0 Project Description

- 2.1 Background and History of the Project**
- 2.2 Site Description**
- 2.3 Existing Mine Operation**
- 2.4 Engineering Description of the Proposed Project**
 - 2.4.1 Overview**
 - 2.4.2 Process Description**
- 2.5 Emissions and Discharges**
 - 2.5.1 Atmospheric Emissions**
 - 2.5.2 Aqueous Discharges**
 - 2.5.3 Solid Waste Generation**
- 2.6 Pollution Control Systems**
 - 2.6.1 Atmospheric Emission Control**
 - 2.6.2 Aqueous Discharge Control**
 - 2.6.3 Solid Waste Control**

3.0 Existing Environment

- 3.1 Atmospheric Conditions**
- 3.2 Land Conditions**
- 3.3 Water Conditions**

4.0 Compliance Monitoring

- 4.1 Environmental Compliance Monitoring - Existing Operations**
 - 4.1.1 Air Quality**
 - 4.1.2 Water Quality**
- 4.2 Environmental Compliance Monitoring - Demonstration Project**
 - 4.2.1 Air Quality**
 - 4.2.2 Water Quality**
- 4.3 Health and Safety Compliance Monitoring - Existing Operations**
- 4.4 Health and Safety Compliance Monitoring - Demonstration Project**

5.0 Supplemental Monitoring

- 5.1 Supplemental Environmental Monitoring - Existing Operations**
- 5.2 Supplemental Environmental Monitoring - Demonstration Project -**
- 5.3 Health and Safety Supplemental Monitoring - Existing Operations**
- 5.4 Health and Safety Supplemental Monitoring - Demonstration Project**

6.0 Monitoring Activities Detailed by Process Stream

7.0 Information Management and Reporting

- 7.1 Management Responsibilities and Requirements**
 - 7.1.1 Organization and Responsibilities**
 - 7.1.2 QA/QC Plan**
 - 7.1.3 Resource Requirements**
 - 7.1.3.1 Sample Containers**
 - 7.1.3.2 Sampling Equipment**
 - 7.1.3.3 Health and Safety Equipment**
- 7.2 Compliance and Supplemental Data Flows**
- 7.3 Data Management Procedures**
- 7.4 Report Format, Content, and Frequency**
 - 7.4.1 Initial Operations Report**
 - 7.4.2 Quarterly Reports**
 - 7.4.3 Annual Report**

8.0 Appendices

- A. Additional Air Quality Information from Air Quality Permit**
- B. Additional Information on Disposal of Process Slack in Mined-out Pits.**
- C. Quality Assurance and Quality Control**

**Environmental Monitoring Plan
Rosebud SynCoal Partnership
Advanced Coal Conversion Process Demonstration
Colstrip, Montana
U.S. D.O.E. Clean Coal Technology Demonstration**

1.0 INTRODUCTION

Western Energy Company (WEC) was selected by the Department of Energy (DOE) to demonstrate the Advanced Coal Conversion Process (ACCP) which upgrades low rank coals into high Btu, low sulfur, synthetic bituminous coal. WEC has transferred the ownership of this project to Rosebud SynCoal Partnership (RSCP) and has subsequently been contracted to design, construct and operate the facility. RSCP is a general partnership between Western SynCoal Company (WSC), a subsidiary of WEC and Scoria, Inc., a subsidiary of NRG, Northern States Power's non utility group. WSC and Scoria are the ACCP technology owners. The project is located at WEC's surface coal mine at Colstrip, Montana. DOE is providing cost-sharing under a Cooperative Agreement with RSCP.

1.1 EMP Purpose

As specified in the Corporate Agreement, RSCP is required to develop an Environmental Monitoring Plan (EMP) which describes in detail the environmental monitoring activities to be performed during the project execution. The purpose of the EMP is to: 1) identify monitoring activities that will be undertaken to show compliance to applicable regulations, 2) confirm the specific environmental impacts predicted in the National Environmental Policy Act documentation, and 3) establish an information base of the assessment of the environmental performance of the technology demonstrated by the project.

1.2 EMP Scope

The EMP specifies the streams to be monitored (e.g. gaseous, aqueous, and solid waste), the parameters to be measured (e.g. temperature, pressure, flow rate), and

the species to be analyzed (e.g. sulfur compounds, nitrogen compounds, trace elements) as well as human health and safety exposure levels.

The operation and frequency of the monitoring activities is specified, as well as the timing for the monitoring activities related to project phase (e.g. preconstruction, construction, commissioning, operational, post-operational). Within the five project phases, monitoring will be broken down into two types. *Compliance* monitoring is that which is or will be required under existing and/or anticipated regulatory requirements or permit conditions. *Supplemental* monitoring will include data gathering activities deemed important to measure operational or environmental performance, but not required to be measured by permits or regulations. Identification of data to be collected was made by determining the monitoring necessity to measure compliance and by the operational necessary to determine:

- material balances around specific unit processes and the entire process, to determine performance;
- process streams as influent and effluent from specific unit processes and the entire process, and associated physical sampling locations;
- locations and information processing needs of in-stream physical property measurement, for correlation with chemical composition data to be used in mass balance calculations.

1.3 Implementation of the EMP

The EMP is designed to assess the environmental impacts and the environmental improvements resulting from construction and operation of the project. There are five distinct phases in the project schedule:

- preconstruction
- construction
- commissioning
- operational, and
- post-operational

The project schedule to implement these phases is shown in Fig. 1-1.

FIGURE 1-1
SUMMARY PROJECT SCHEDULE

OVERALL SCHEDULE FOR ACCP DEMONSTRATION PROJECT

For the EMP, baseline monitoring of the existing operations will be combined for the pre-construction, and construction, and commissioning phases. The baseline monitoring essentially consists of the environmental compliance monitoring currently required by Montana Department of State Lands and the Montana Air Quality Bureau. The various monitoring programs administered by these agencies address air emissions from point and fugitive sources, water discharges, groundwater impacts, wildlife impacts and solid waste disposal.

No additional ambient, or operational monitoring is projected for the commissioning and debugging stage of the project. The monitoring systems will be checked out and debugged at this stage as well.

Health and safety monitoring for worker exposure to noise, dust, and methane is already in place as part of the existing mine operations and will continue throughout each phase of the project.

Operational monitoring will commence after the unit has been commissioned, and WECO personnel have proven capable of operating the systems with routine guidance from vendors and contractors. It is expected that 30 to 90 days will be required after mechanical completion to initiate operational monitoring.

Since continued operation of the facility is envisioned after the demonstration, post-demonstration compliance monitoring will be required by the Montana and federal regulators. RSCP will comply with the continuing requirements of those agencies and any information reported will be available to DOE.

2.0 PROJECT AND PROCESS DESCRIPTION

2.1 Background and History of the Project

Western Energy Company (WEC) of Butte, Montana has negotiated a Cooperative Agreement with the Department of Energy (DOE) for cost sharing the construction and operation of a demonstration, advanced coal cleaning and processing facility using WEC's patented (No. 4,725,337) Advanced Coal Conversion Process. This activity responds to the DOE's solicitation offering private industry assistance in developing clean coal technologies.

WEC is a wholly-owned subsidiary of Entech, Inc., the non-utility subsidiary of the Montana Power Company. WEC has coal-mining operations in Montana, Wyoming and Texas and owns significant reserves of coal and lignite elsewhere in the United States.

The initial concept of thermally processing coal with low-pressure, super-heated recycled gas was presented to WEC by an independent consultant in 1981. Under contract to WEC, the consultant continued to develop the conceptual ideas necessary to show the potential benefits of this approach to coal upgrading technology. As those benefits were defined and explored, WEC developed an initial laboratory conceptual design. Equipment was procured, installed and operated to substantiate the theoretical concepts in a bench-scale, batchmode. The results were positive enough to warrant further development.

This led to a contract between WEC and the Montana College of Mineral Science and Technology (Montana Tech) to construct and operate a 200 lb/hr continuous pilot plant. The plant was constructed in 1984 at Montana Tech's Mineral Research Center in Butte, Montana. The primary purpose of the experimental work was to develop a method of thermally processing subbituminous and lignite coal using low pressure, superheated recycled gas derived from the feed coal to produce a clean, stable product.

Approximately 12 different coals have been tested in the pilot plant. The combined processing experience is in excess of 300 tons of coal and 4,000 operating hours. The product has been tested for storage, handling, transportation, and combustion

characteristics. Most of the testing has been performed with Rosebud subbituminous coal.

In addition to the above testing, Combustion Engineering, Inc., has performed comprehensive analytical characterizations of WEC's processed Rosebud coal. The results indicate that the processed coal improved by reduction of moisture content, ash slagging potential, coal abrasiveness, and coal sulfur content.

WEC's Advanced Coal Conversion Process produces a high-quality, cost-effective, stable synthetic fuel from low quality coal using a continuous low pressure, moderate temperature treatment. The process shrinks the moisture-holding capillaries, and thermally destroys the carboxylic acid groups in the low rank coal. As the coal particles shrink, ash and sulfur minerals (pyrites) are released from the coal and can be easily separated. Some organic sulfur is also removed. The result is a significant reduction in sulfur dioxide emission potential for the coal. These physical and chemical changes combine to produce a cleaner and drier coal product.

Design, construction and demonstration operation is expected to require five years. The demonstration plant will have a rated producing capacity of 45 tons per hour and will be located on property controlled by WEC inside an active mine area and adjacent to their existing loadout facilities. Montana Power Company operates the Colstrip generating station approximately three miles to the east. The demonstration plant's physical location, setting and facilities arrangement are discussed in Section 2.2

2.2 Site Description

The demonstration plant site is on property controlled by WEC adjacent to their existing mining and loadout activities in Rosebud County, Montana, approximately two miles southwest of the community of Colstrip as shown in Figure 2-1. The demonstration plant's physical setting and facilities arrangement is shown on the plot plan in Figure 2-2.

Several major advantages exist for locating the demonstration plant as proposed:

- 1.) Land use impacts will be negligible, as the plant will be located immediately adjacent to an existing mining and loadout facility.
- 2.) The plant will be located on the mine site, with associated truck dump, crusher, and tipping facility.
- 3.) Construction impacts will be minimal, given the existence of required ancillary facilities (e.g., coal handling facilities) and industrial infrastructure (e.g., electrical supply), plus the Colstrip community's ability to expand to meet short-term and long-term population growth requirements incurred by this project.
- 4.) Although plant-specific and cumulative environment impacts are foreseen to be minor, the present impact-monitoring network will be used to evaluate impacts. Only minimal effort will be required to modify the existing system to monitor environmental compliance by WEC's Advanced Coal Conversion Processing facility.

The downturn in eastern Montana's economy in recent years has left a sufficient pool of skilled labor available for constructing the demonstration plant. Labor schedules and the number of persons required per craft have been estimated. Similarly, the personnel required to operate the plant have been determined, and adequate labor should be available in the area.

FIGURE 2-1
SITE LOCATION

FIGURE 2-2
FACILITY PLOT PLAN

2.3 Existing Mine Operations

WECo's Rosebud Mine is an open pit surface coal mine. The mine extends over an area of approximately 48 square miles. There are currently four areas of active mining (Areas A, B, C and D) (Figure 2.1). Areas D and C supply coal to Montana Power's generating units (Colstrip 1, 2, 3 and 4). Areas A, B, and D supply coal for off-site customers. The coal is removed from under an overburden of between 40 and 200 feet. The coal seam is approximately 25 feet thick. Annual production is between 12 and 16 million tons.

2.4 Engineering Description of the Proposed Project

2.4.1 Overview

Western Energy Company's Advanced Coal Conversion Process (ACCP) produces a synthetic, high volatile, low sulfur bituminous coal fuel from subbituminous coals and lignites. Such a fuel is more competitive in the marketplace and improves the mining potential of the vast reserves of low-rank coals in Montana and throughout the world.

This section describes the design for an ACCP demonstration facility to be built in Western Energy Company's Rosebud Mine near Colstrip, Montana within the existing mining area. The demonstration plant will serve a number of purposes:

- Demonstrate a subbituminous and lignite coal upgrading concept using low-pressure, super heated gas as a heating medium in this prototypical demonstration facility.
- Confirm that the upgraded synthetic coal product retains high Btu value organic compounds for ignitability, the bulk density remains unchanged with increased heating values, and the product resists rehydration and spontaneous combustion.
- Demonstrate that coal processed in such a manner results in unique physical characteristics, allowing simple removal of pyritic sulfur and other ash forming minerals.
- Prove that the enhanced coal product is an economical and environmentally acceptable fuel.

- Provide an ample amount of the enhanced coal for commercial boiler combustion test burns to conform combustion characteristics and develop market penetration.
- Provide sufficient long-term operational experience, plant capabilities, and operating flexibility to define scale-up parameters for the proposed commercial-size facilities.

The normal throughput of the demonstration plant will be 1640 tons per day (TPD) of raw coal, providing 1098 TPD of coarse coal product and 165 TPD of coal fines (minus 20 mesh). The fines will be collected and briquetted, giving a combined product rate of 1263 TPD of high-quality, clean coal product.

The heating value of the raw coal fed to the process is 28.0 billion Btu/Day; other energy inputs to the process are from natural gas (or propane) burned in the process furnace (1.4 billion Btu/Day) and from electric power for the motors (500 million BTU/Day), for a total energy input of 29.9 billion Btu/Day. The heating value of the product coal totals 26.1 billion Btu/Day. The efficiency of the process (energy input compared to useful product) is $26.1/29.9 = 87$ percent.

The energy from the natural gas (or propane) and electricity required by the process is nine percent of the heating value of the raw coal. The waste coal discarded from the process contains 2.28 billion Btu/Day, or eight percent of the energy of the raw coal.

2.4.2 Process Description

As shown on the Plot Plan (Figure 2-2), the approximately 400 feet by 600 feet battery limits of the plant are located almost 600 feet west of the existing Western Energy Company Rosebud Mine Area A tipple, near Colstrip, Montana. The approximate coordinates of the center of the plant are 45,800 North and 46,700 East, based on the existing Colstrip grid.

The overall process is depicted by the Process Block Flow Diagram (Figure 2-3). This schematic drawing shows the major process systems and process streams.

Raw Coal Handling

Raw coal from the existing Area A stockpile is screened to provide 2 x 1/2 inch feed to the demonstration process. Coal rejected by the screening operation is conveyed back to the active Area A stockpile. Properly sized coal is conveyed to a surge bin feeding the process facility.

Coal Conversion

The drying train, which consists of dual processors, each consisting of two 5-foot wide by 30-foot long vibratory fluidized bed reactors in series, processes 2,267 pounds per minute of 2 x 1/2 inch coal followed by a 5 x 25 vibratory cooler reactor.

In the first-stage reactor, the coal is heated by hot combustion gas where primarily surface water is removed from the coal. The coal exits the first-stage reactor at a temperature slightly above that required to evaporate water. It then feeds into a second-stage reactor, which further heats the coal using a recirculating gas stream, removes water trapped in the pore structure of the coal, and promotes decarboxylation. The particle shrinkage that liberates the ash minerals and imparts the unique cleaning characteristics of this process occurs during these second stage reactions.

The hot coal from the exit of each drying train is fed to a 5 feet wide by 25-feet long vibratory fluidized bed cooler where it is cooled by contact with a gas consisting primarily of carbon dioxide and nitrogen at 100° F. The coal exits the cooler at less than 150° F and enters coal cleaning.

Included in the conversion system are particulate removal devices for each stage to dedust the circulating gas, fans to convey the gas to the reactors from the heat plant and the heat rejection system.

Figure 2-3

MSE Inc.
 ACAD#: A91M0435
 REV: A DATE: 9/16/91
 DRAFTER: DB

ROSEBUD SYNCOAL
 ADVANCED COAL CONVERSION PROCESS
 DEMONSTRATION PROJECT-PROCESS FLOW SCHEMATIC

Coal Cleaning

The coal entering the cleaning system is screened into four size fractions: plus 1/2 inch, 1/2 by 1/4 inch, 1/4 inch by 6 mesh, and minus 6 mesh. These streams are fed in parallel to four deep-bed stratifiers (stoners), where a rough specific gravity separation is made using fluidizing air and a vibratory conveying action. The light streams from the stoners are sent to the product conveyor; the heavy streams from all but the minus 6 mesh stream are sent to fluidized bed separators. The heavy fraction of the minus 6 mesh stream goes directly to the waste conveyor. The fluidized bed separators, again using air and vibration to effect a gravity separation, each split the coal into light and heavy fractions. The light stream is considered product; the heavy stream is sent to waste handling. The process waste or slack is held in an enclosed bin for transport to an off site user or alternately to an in-pit disposal site. The dry, cool, clean product from coal cleaning is sent to product storage for load out.

Heat Plant (System 4)

The heat required to process the coal is provided by burning natural gas (or propane) in a process furnace. This system is sized to provide a heat release rate of 74 MM BTU/hr. Process gas enters the furnace and is heated by radiation and convection from the burning fuel. Process makes gas from coal conversion will be incinerated in the furnace.

Heat Rejection

Most heat rejection from the ACCP will be accomplished by releasing water vapor and flue gas to the atmosphere through an exhaust stack. The stack design will allow for vapor release at an elevation great enough that, when coupled with the vertical velocity resulting from a forced draft fan, dissipation of the gases will be maximized. Additional heat rejection will be accomplished using an atmospheric induced-draft cooling tower.

Emission Control

The emission control philosophy is based on injecting dry sorbents into the ductwork to minimize the release of sulfur dioxide to the atmosphere. The sorbent, sodium bicarbonate, will be injected into the duct of the ACCP to maximize the potential for sulfur dioxide removal while minimizing reagent usage. The sorbents, having reacted with sulfur dioxide, will be removed from the gas streams in the particulate removal systems. The coal cleaning system fugitive dust is controlled by placing hoods over the sources of fugitive dust and conveying the dust laden air to fabric filter(s). The bag filters can remove 99.99 percent of the coal dust from the air before discharge. All fines will report to a briquetter and ultimately the product stream.

Utility and Ancillary Systems

Product handling, consists of the equipment necessary to convey the clean product coal to two 6,000 ton concrete silos designed to allow train loading with the existing loadout (see Figure 2.2).

The coal fines that will be collected in the conversion, cleaning and material handling systems are gathered and conveyed to a briquetting surge bin. The coal fines will then be briquetted and conveyed to the product storage area.

The common facilities include: a plant and instrument air distribution system, a fire protection water distribution system, and a fuel gas distribution system. The plant and instrument air distribution will store and deliver dry compressed air as necessary to the various plant locations. The fire protection water distribution system will meet all MSHA, Factory Mutual and NFPA codes. The fuel gas distribution system will allow safe, efficient fuel delivery.

2.5 Emissions & Discharges

2.5.1 Atmospheric Emissions

Atmospheric emissions from the ACCP fall into two categories. First, particulate from both the process and fugitive emissions. The process particulate emission is predicted to be approximately 83 ton/year. Fugitive particulate emissions are predicted to be approximately 13 ton/year.

The second category of atmospheric emissions is process combustion products. The three classes of compounds of concern are sulfur oxides, nitrogen oxides and carbon monoxide. Predicted emissions of these compounds are:

Sulfur Oxides - 35.5 Ton/yr.
Nitrogen Oxides - 34.8 Ton/yr.
Carbon Monoxide - 28.3 Ton/yr.

Appendix A contains two sections of the Rosebud Mine air quality permit describing ACCP emissions. The sections contain more detailed descriptions of the predicted emissions.

2.5.2 Aqueous Discharges

This facility is designed to have no aqueous discharges during normal operations. In the event of a water line rupture or other catastrophe the mine drainage containment plan will allow any necessary mitigating measures to be performed.

2.5.3 Solid Waste Generation

The ACCP Demonstration facility will produce approximately 41,000 tpy of cleaning circuit refuse referred to as "process slack". This material is similar to the top/bottom of seam slack coal normally wasted in the pits during coal removal operations at the Rosebud Mine.

Samples of Rosebud coal process slack produced at Western Energy's pilot coal cleaning plant in Butte, Montana, and samples of top/bottom of seam slack obtained from the Area A, B, and C pits at the Rosebud Mine were analyzed for EP toxicity and acid/base account by Northern Engineering and Testing, Inc. The results, which are contained in Appendix B, indicate that the materials are non-hazardous and non-

toxic-forming. Due to a high pyritic sulfur content, particularly for the process slack materials in which the pyrite becomes concentrated, acid/base account values indicate a potential for acid formation. However, the pyrite in these materials is a predominately massive form with a small surface area and is considered relatively non-reactive. Dr. Doug Dollhopf of the Reclamation Research Unit at Montana State University studied 12 samples of Rosebud process slack (four groups of 3 samples designated A, B, C, & D) to evaluate the potential acid producing characteristics. The 12 samples represent all four active mine areas in triplicate. Dr. Dollhopf's specific objectives were:

- determine the amount of acidity already present, if any;
- determine the potential for future acid production by analysis of sulfur forms;
- determine the potential for future acid production by laboratory weathering; and
- determine sulfide and sulfate morphology with SEM-EDAX equipment in order to assess potential for acid production.

Dr. Dollhopf's conclusions were: "Based on data presented in this report, these 12 coal cleaning samples will not cause acidification of any environmental resources. Samples designated A and B will likely yield acid upon oxidation and hydrolysis, but it will be neutralized by natural base chemistry present in these materials. Samples C and D do not contain submicron size pyrite capable of producing acid rapidly upon being oxidized. Consequently, acid produced, if any, from larger pyrite particles would be generated very slowly and be easily neutralized by base chemistry."

2.6 Pollution Control Systems

2.6.1 Atmospheric Emission Control

Fugitive particulate emissions will be controlled with a combination of stabilization and source reductions. A 91% reduction from uncontrolled fugitive particulate emissions is predicted. Process particulate emission will be controlled with baghouses. A 99.9% reduction from uncontrolled emissions is predicted.

An in-duct sorbent injection system will be used to control sulfur oxide emissions. A 60% reduction from uncontrolled emissions is predicted.

A low nitrogen oxide burner will be used in the heat plant. A 31% reduction in nitrogen oxides production is predicted.

The burner will also be of a special design to limit carbon monoxide production. A 76% reduction in carbon monoxide production is predicted.

2.6.2 Aqueous Discharge Control

No specific pollution control is planned for ACCP aqueous discharges because none are expected.

2.6.3 Solid Waste Control

Western Energy will blend the "process slack" coal with the top of seam slack coal being supplied to off site users of this refuse material when possible. The off site users will burn this material and will be obligated to dispose of the residue in compliance with their permits; therefore, there is no disposal concern with this method.

As an alternate disposal method when the normal disposal method is unavailable, Western Energy will selectively place the slack in open mine pits for burial.

Although the process slack materials are considered to be non-reactive, they will be disposed of in a manner that will minimize the potential for oxidation. As is currently done with top/bottom seam slack coal generated during normal mining activities, the process slack coal from the drying facility will be placed at the bottom of mined-out portions of the Rosebud seam in areas where it will be located below the predicted post-mine water table and where backfilling with spoil will occur within a six month period. This will provide burial with a minimum of ten feet of non-toxic, non-combustible material and will ensure that the pyritic component of the slack coal remains in a reduced or non-acid-forming state. Additional information on the method of disposal and justification of the alternate method is contained in Appendix B.

3.0 EXISTING ENVIRONMENT

3.1 Atmospheric Conditions

The proposed site is located approximately two miles southwest of the town of Colstrip and inside of an active permitted mine area. The area is typical of that for southeastern Montana and nothing exists in the area which is unique or unusual.

The semiarid climate at Colstrip is typical of the continental steppes of the northern Great Plains. Precipitation is low but variable and falls primarily during the warmer months. Daily temperature variations are large, and seasonal temperature variations are pronounced. Surface humidity is low, and the prevailing wind speeds moderate.

Mean annual precipitation is 15.8 inches; about 50 percent occurs from April through June, 20 percent in the winter, and the remainder in the fall. Precipitation falls during 95 days in an average year. The largest expected 100 year storm is 2.40 inches for a 6 hour event and 2.83 inches for a 24 hour period.

Mean annual temperature is about 45°F. Temperatures are lowest in January, averaging about 8°F, and highest in July, averaging about 90°F. High midsummer temperatures and low precipitation terminate the effective growing season. Relative humidity is lowest in July and highest in winter. The freeze-free season is about 115 days.

Winds from the northwest dominate at Colstrip. Wind from a single 22.5-degree sector persisted for 12 or more hours on only 22 occasions during 1 year of measurement, 50 percent of these occurring during the winter. Average winter wind speed ranges from 14 miles/hour (mph) at a height of 300 feet to 7 mph at ground level. Wind speeds greater than 17 mph occur less than 7 percent of the time. Vertical air movement at Colstrip is characterized by a high frequency of ground-based thermal inversions and an annual mean maximum mixing depth of 3,414 feet about ground level.

Figures 3-1 through 3-4 show the seasonal windroses for the Colstrip area for the various seasons of the year. The location of the recording instruments is south of the power plants and east of Highway 39 at an elevation of 10 meters.

At the present time, Colstrip is a primary attainment area for the U.S. EPA criteria pollutants SO₂, NO_x, ozone, CO, and total suspended particulates. The region is a secondary nonattainment area for total suspended particulates. Upon approval of the State of Montana's PM₁₀ standards by the EPA, the secondary standard for TSP will no longer exist. The state should submit their application in late 1989 or early 1990. We anticipate to be in compliance with the PM₁₀ Standards.

3.2 Land Conditions

The proposed plant site is located several miles west of Colstrip, Montana in Rosebud County. The Town of Colstrip is presently unincorporated, although its current population is approximately 4,500. The area outside of the current mine plans, both east and west of Colstrip, is mainly native range used primarily for cattle grazing. There is some dry land farming which produces small grain and alfalfa.

East Fork Armells Creek is the main drainage in the vicinity of the proposed plant. East Fork Armells Creek and its tributaries are ephemeral throughout the site vicinity. The nearest reach of channel exhibiting perennial flow begins approximately two miles downstream of the site.

The site is located outside of the 100-year flood plain of East Fork Armells Creek. This was determined by routing runoff generated from the 100-year, 24-hour design storm through a representative channel cross-section, located adjacent to the proposed plant.

FIGURE 3-1

WIND SPEED CLASS BOUNDARIES
(MILES/HOUR)

NOTES:
DIAGRAM OF THE FREQUENCY OF
OCCURRENCE FOR EACH WIND DIRECTION.
WIND DIRECTION IS THE DIRECTION
FROM WHICH THE WIND IS BLOWING.
EXAMPLE - WIND IS BLOWING FROM THE
NORTH 6.2 PERCENT OF THE TIME.

WINDROSE

ROSEBUD MINE
PERIOD: 1988
SEASON: SUMMER

FIGURE 3-2

WIND SPEED CLASS BOUNDARIES
(MILES/HOUR)

NOTES:
 DIAGRAM OF THE FREQUENCY OF
 OCCURRENCE FOR EACH WIND DIRECTION.
 WIND DIRECTION IS THE DIRECTION
 FROM WHICH THE WIND IS BLOWING.
 EXAMPLE - WIND IS BLOWING FROM THE
 NORTH 4.2 PERCENT OF THE TIME.

WINDROSE

ROSEBUD MINE
 PERIOD: 1988
 SEASON: AUTUMN

FIGURE 3-3

WIND SPEED CLASS BOUNDARIES
(MILES/HOUR)

NOTES:

DIAGRAM OF THE FREQUENCY OF
OCCURRENCE FOR EACH WIND DIRECTION.
WIND DIRECTION IS THE DIRECTION
FROM WHICH THE WIND IS BLOWING.
EXAMPLE - WIND IS BLOWING FROM THE
NORTH 6.4 PERCENT OF THE TIME.

WINDROSE

ROSEBUD MINE

PERIOD: MAY 1989

SEASON: SPRING

FIGURE 3-4

WIND SPEED CLASS BOUNDARIES
(MILES/HOUR)

NOTES:
 DIAGRAM OF THE FREQUENCY OF
 OCCURRENCE FOR EACH WIND DIRECTION.
 WIND DIRECTION IS THE DIRECTION
 FROM WHICH THE WIND IS BLOWING.
 EXAMPLE - WIND IS BLOWING FROM THE
 NORTH 5.8 PERCENT OF THE TIME.

WINDROSE

ROSEBUD MINE
 PERIOD: FEB. 1989
 SEASON: WINTER

This analysis shows that peak flow resulting from the 100-year, 24--hour storm will be contained within the channel. The site is also located outside of the "Special Flood hazard Area - Zone A", as depicted from the 1977 U.S. Department of Housing and Urban Development Flood Hazard boundary Map for Rosebud County.

The site is not located in the immediate vicinity of established wetland areas, as evidenced by the lack of native perennial surface water features. Nearby ponds (WEC0 designated PO-013 and PO-21C) are mine sedimentation ponds, whose water levels are artificially maintained, through pit-dewatering activities, in order to provide perennial water sources for wildlife use.

3.3 Water Conditions

The major aquifers in the Colstrip area include the shallow alluvium (found in major drainages), the Rosebud and McKay coal seams, and the sub-McKay sandstones. Fine-grained sandstones in the rosebud overburden and in the Rosebud-McKay interburden zones contain water on a local basis. However, these water bearing zones are of limited areal extent and generally have limited capabilities.

Colstrip area ground water is highly variable in degree and type of mineralization, but is generally a magnesium-sulfate type water with moderate concentrations of calcium, sodium, and bicarbonate. Waters from the Rosebud coal and Rosebud overburden are generally of the best quality, while waters from the spoils and alluvia aquifers generally exhibit the highest Total Dissolved Solids (TDS) levels. The greatest range in TDS values occurs within the Rosebud coal aquifer. Mean pre-mine TDS values range from 400 mg/l to over 6,000 mg/l at individual wells.

The major importance of groundwater and surface water in the Colstrip vicinity is for livestock and wildlife use.

The possibility of groundwater contamination resulting from normal plant operations is extremely limited. However in the event that a spill from the plant produced enough leachate to reach the water table, the contaminate plume produced would primarily affect the East Fork Armells Creek alluvium. This is due to horizontal permeabilities exceeding vertical permeabilities in most stream-laid

sediments in the area, together with greater hydraulic conductivities exhibited in the alluvium than those within the underlying bedrock (overburden).

In the event that significant groundwater contamination resulting from plant-related operations is suspected, a remedial-action plan would be implemented. The plan would consist of monitoring/recovery wells located and completed for the purpose of tracking, isolating and recovering product leachate. The wells would be designed and constructed specifically for the individual suspect contaminants, based on the properties of those constituents.

The proposed plant will not use any water from East Fork Armells Creek or wells, nor will any water be discharged into the creek. Make up water for domestic, fire protection and process use, will come from the Colstrip townsite water system. A service line will be installed connecting the existing water system to the facility.

4.0 COMPLIANCE MONITORING

4.1 Environmental Compliance Monitoring - Existing Operations

4.1.1 Air Quality

Currently the only air quality compliance monitoring relates to suspended particulate. WECO currently operates six sites, each site has one High Volume Air Sampler (HVAS) from which total suspended particulate data is collected on a six day EPA schedule.

Sites are located as follows:

<u>Site Number</u>	<u>Location</u>	<u>Coordinates</u>
1A & 1B	Mine Area A by Highway 39	52000 N, 53800 E
9	South of Area B	40750 N, 54700 E
10	North of Area C	51300 N, 24100 E
11	West of Area C	55800 N, 8350 W
13	South of Area C	38800 N, 12700 E
14	East of Area A	52500 N, 52250 E

Quarterly and Annual air quality reports are made to the Montana State Air Quality Bureau.

4.1.2 Water Quality

Water quality compliance monitoring at the Rosebud Mine is already extensive. At the end of the 1990 water year WECO was monitoring a total of 434 ground water wells. The wells are spread throughout the mine and draw water from various depths and geologic structures.

In addition, surface water was monitored at 13 stations.

Annual water quality reports are made to the Montana Water Quality Bureau.

4.2 Demonstration Project Environmental Compliance Monitoring

4.2.1 Air Quality

In addition to continued suspended particulate monitoring, once operational, a performance test is required by the approved air quality permit. The test will consist of an EPA Method 5 for measuring particulate emissions from the flue gas stack and the coal cleaning air discharge. The performance test will occur within 60 days after full production is attained. The air quality permit also requires monitoring and recording the flue gas temperature.

4.2.2 Water Quality

Because no water discharge is envisioned, there is no requirement for water discharge compliance monitoring. Ground water monitoring in areas at slack coal disposal will be performed if that method of slack coal disposal becomes necessary (see Appendix B).

4.3 Health and Safety Compliance Monitoring - Existing Operations

4.3.1 Noise

Existing mine operations working environment compliance monitoring is performed per 30 CFR Part 71. Personal noise level measurements are made as necessary by a qualified individual. A hearing conservation program for the coal drilling job classification is in place.

Periodic noise surveys are performed per 30 CFR 71.803.

4.3.2 Dust

Monitoring and control is done as required by 30 CFR 71.100 through 71.301. At this time there are no MSHA designated work positions that required sampling.

4.3.3 Methane

Tests for methane by a qualified person using an approved device are conducted as provided for in 30 CFR Part 787.201-1. Additionally, continuous methane monitoring is in effect at our Area C crusher/conveyor facility.

4.4 Health and Safety Compliance Monitoring - Demonstration Project

Health and safety compliance monitoring for noise and dust will continue on the same basis as current monitoring. WECO plans to install continuous methane monitors in areas where accumulations are possible.

5.0 SUPPLEMENTAL MONITORING

Supplemental monitoring is included in the EMP to demonstrate the effectiveness of the project by providing environmental and process data not available from compliance monitoring. The main objective of the supplemental monitoring program is to demonstrate the effectiveness of the combined process.

5.1 Existing Operation - Supplemental Environmental Monitoring

There are no supplemental monitoring activities related to the current mine activity.

5.2 Demonstration Project - Supplemental Environmental Monitoring

Supplemental monitoring planned for the ACCP will be used mainly for determining performance and efficiencies of unit operations, and gathering data for scale-up activities and economic evaluations. Supplemental environmental monitoring is not directed toward measuring emissions as much as measuring the process performance and efficiency.

Section 6 contains descriptions of all supplemental monitoring planned for the ACCP.

5.3 Health and Safety Supplemental Monitoring - Existing Operations

5.3.1 Noise

Periodic or spot check measurements are made when requested by employees, as machines are added or modified, during special repair or maintenance projects, during construction or as necessary for information or fact gathering projects. Personal decimeters or hand-held sound level meters may be used for this.

All new employees are given baseline audiograms. Coal drillers, dragline, shovel and highwall drill operators, and any other employee showing a shift in hearing ability or exposed to noise levels that approach allowable limits are also given annual audiograms.

5.3.2 Dust

Areas of concern are sampled as needed and private labs are used for analysis. This is done for employee and company benefit even though MSHA may not have active Designated Work Positions assigned.

5.3.3 Methane and Other Gases

These tests are on-going as needed to ensure the personal health and safety of employees. All front line supervisors have been trained to an instructor level for detection of mine gases.

Bins and tanks are tested for oxygen deficiency and explosive gases prior to work or entry.

LEL readings of explosive gases must be 0.00 prior to welding on or repairing fuel tanks.

Possible hazardous vapors are tested for as needed by using a Sensidyne Model 800 gas tester. While we are adding tubes to our inventory, we can presently test for:

- * Hydrogen Sulfide
- * Trichloroethane
- * Trichloroethylene
- * Carbon Monoxide
- * Carbon Dioxide
- * Oxygen
- * Methane
- * Methylene Chloride

5.4 Health and safety Supplemental Monitoring - Demonstration Project

The existing supplemental health and safety monitoring will be extended to encompass the demonstration project.

6.0 MONITORING ACTIVITIES

This section identifies specific monitoring activities related to the ACCP. Figure 6.1 shows the streams within the ACCP facility that will be monitored for use in the Environmental Monitoring Reports. Table 6.1 identifies the streams, parameters, and the frequency of the monitoring. Table 6.1 also designates supplemental or compliance monitoring of the stream parameter.

Table 6.2 shows monitoring related to the ACCP facility, but not within the confines of the facility itself.

Figure 6.2 shows the locations of the ambient air monitoring stations throughout the mine.

Figure 6.3 describes data types to be collected as part of test burns for the ACCP product coal. Specific streams, parameters, and frequencies will be addressed on a case-by-case basis.

Table 6.1

ACCP STREAM MONITORING - PROCESS FLOWS

STREAM ID	INSTRUMENT NUMBER	PARAMETER	UNITS	S/C	FREQUENCY	SAMPLE TYPE/ DATA SOURCE
1- NATURAL GAS	PIT-402	PRESSURE	IWC	S	HOURLY	PCS
	TE-402	TEMPERATURE	F	S	HOURLY	PCS
	FIT-402	FLOW	LB/M	S	HOURLY	PCS
2- COMBUSTION AIR	PIT-401	PRESSURE	IWC	S	HOURLY	PCS
	TE-401	TEMPERATURE	F	S	HOURLY	PCS
	FIT-401	FLOW	LB/M	S	HOURLY	PCS
3- STACK GAS	TE-700 FIT-700	TEMPERATURE	F	C	HOURLY	PCS
		FLOW	ACFM	S	HOURLY	PCS
		FUGITIVE DUST PM-10	GR/DSCF	S	ANNUALLY	
		TOTAL FUGITIVE DUST	GR/DSCF	C	NOTE 1	
		SO ₂	PPM	S	HOURLY	CONTINUOUS MONITOR
		NO _x	PPM	S	ANNUALLY	FIELD INSTRUMENT
		CO ₂	%	S	ANNUALLY	FIELD INSTRUMENT
		CO	PPM	S	ANNUALLY	FIELD INSTRUMENT
		O ₂	%	S	ANNUALLY	FIELD INSTRUMENT
		FLOW	LB/M	S	HOURLY	PCS
4- COOLING WATER SUPPLY	FIR-627 TE-614	TEMPERATURE	F	S	HOURLY	PCS
		TDS	MG/L	S	NOTE 2	GRAB SAMPLE
		TOC	MG/L	S	NOTE 2	GRAB SAMPLE
		FLOW	LB/M	S	HOURLY	PCS
5- COOLING WATER RETURN	FIR-628 TE-604	TEMPERATURE	F	S	HOURLY	PCS
		TDS	MG/L	S	NOTE 2	GRAB SAMPLE
		TOC	MG/L	S	NOTE 2	GRAB SAMPLE
		FLOW	TON/HR	S	HOURLY	PCS
6- RAW COAL INLET	FIR-108	PROXIMATE ^a		S	DAILY	GRAB SAMPLE
		ULTIMATE ^b		S	NOTE 2	GRAB SAMPLE
		TRACE ELEMENTS ^c		S	NOTE 2	GRAB SAMPLE
		TEMPERATURE	F	S	HOURLY	USE COMBUSTION AIR INLET TEMP
7- SODIUM BICARBONATE		FLOW	LB/M	S	DAILY	USAGE RATE
		COMPOSITION - NOTE 4		S	MONTHLY	GRAB SAMPLE
8- BINDER		FLOW	LB/M	S	DAILY	USAGE RATE
		COMPOSITION - NOTE 5		S	MONTHLY	GRAB SAMPLE
9- DRIED COAL		FLOW	TON/HR	S	MONTHLY	INVENTORY
		PROXIMATE ^a		S	DAILY	GRAB SAMPLE
		ULTIMATE ^b		S	NOTE 2	GRAB SAMPLE
		TRACE ELEMENTS ^c		S	NOTE 2	GRAB SAMPLE

Table 6.1 Continued

ACCP STREAM MONITORING - PROCESS FLOWS

STREAM ID	INSTRUMENT NUMBER	PARAMETER	UNITS	S/C	FREQUENCY	SAMPLE TYPE/ DATA SOURCE
10-	CLEANED COAL	FLOW PROXIMATE ^a ULTIMATE ^b TRACE ELEMENTS ^c	TON/HR	S S S S	MONTHLY DAILY NOTE 2 NOTE 2	INVENTORY GRAB SAMPLE GRAB SAMPLE GRAB SAMPLE
11-	PROCESS SLACK	FLOW PROXIMATE ^a ULTIMATE ^b TRACE ELEMENTS ^c TCLP	TON/HR	S S S S S	MONTHLY DAILY NOTE 2 NOTE 2 NOTE 2	INVENTORY GRAB SAMPLE GRAB SAMPLE GRAB SAMPLE GRAB SAMPLE
12-	COAL FINES	FLOW PROXIMATE ^a ULTIMATE ^b TRACE ELEMENTS ^c	TON/HR	S S S S	MONTHLY DAILY NOTE 2 NOTE 2	INVENTORY GRAB SAMPLE GRAB SAMPLE GRAB SAMPLE
13-	BRIQUETTED COAL	FLOW PROXIMATE ^a ULTIMATE ^b TRACE ELEMENTS ^c	TON/HR	S S S S	MONTHLY DAILY NOTE 2 NOTE 2	INVENTORY GRAB SAMPLE GRAB SAMPLE GRAB SAMPLE
14-	PRODUCT LOADOUT	FLOW PROXIMATE ^a ULTIMATE ^b TRACE ELEMENTS ^c	TON/HR	S S S S	AS REQUIRED WHEN LOADING WHEN LOADING WHEN LOADING	PCS SAMPLER SAMPLER SAMPLER
15-	COAL CLEANING AIR BAGHOUSE - NOTE 5	TOTAL FUGITIVE DUST FUGITIVE DUST PM-10	GR/DSCF GR/DSCF	C S	NOTE 1 ANNUALLY	EPA METHOD 5 EPA METHOD 5

NOTES:

- 60 DAYS AFTER ATTAINING FULL PRODUCTION.
- SAMPLING AND ANALYSIS SHALL BE CONDUCTED IN TRIPLICATE PER TEST CONDITION.
A NEW TEST CONDITION IS DEFINED AS:
WHEN TWO OR MORE PLANT CONDITIONS ARE VARIED BY MORE
THAN 20% AND MAINTAINED FOR A PERIOD OF MORE THAN 15 DAYS.
- COMPOSITION FOR SODIUM BICARBONATE AT A MINIMUM INCLUDES PERCENT NaHCO₃, PERCENT NaCl, AND SIZE DISTRIBUTION.
- BINDER TYPE IS UNKNOWN AT THIS TIME.
- NOT SHOWN ON FIGURE 6.1
 - PROXIMATE ANALYSIS DETERMINES THE MOISTURE CONTENT, VOLATILE MATTER, FIXED CARBON, AND ASH.
 - ULTIMATE ANALYSIS DETERMINES THE AMOUNT OF CARBON, HYDROGEN, OXYGEN, NITROGEN, AND SULFUR.
 - TRACE ELEMENTS INCLUDE: Sb, As, Ba, Be, Cd, Cr, Co, Pb, Mn, Hg, Ni, Se, Ag, V, Cl, F, AND P.

Table 6.2

ACCP NONPROCESS MONITORING

<u>STREAM</u>	<u>PARAMETER</u>	<u>UNITS</u>	<u>S/C</u>	<u>SAMPLE TYPE/ FREQUENCY</u>	<u>DATA SOURCE</u>
AMBIENT AIR	TOTAL SUSPENDED PARTICLES	UG/M	C	EVERY SIX DAYS	
	WATER LEVEL			MONTHLY	
WASTE COAL DISPOSAL AREA GROUND WATER	pH		C	EVERY THREE MONTHS	
	CONDUCTIVITY		C	EVERY THREE MONTHS	
	TOTAL ORGANIC CARBON		C	EVERY THREE MONTHS	
	MAJOR CATIONS		C	EVERY SIX MONTHS	
	MAJOR ANIONS		C	EVERY SIX MONTHS	
	METALS		C	EVERY SIX MONTHS

Figure 6.1

ISE Inc.

ACAD#: A91M0435
REV: A DATE: 9/16/91
DRAFTER: DB

YNCOAL
VERSION PROCESS
PROCESS FLOW SCHEMATIC

WESTERN ENERGY COMPANY

FIGURE 6.2
ROSEBUD MINE AIR MONITORING AND MONITORING WELL LOCATIONS

FIGURE 6.3

ACCP DRIED COAL TEST BURN REPORT OUTLINE

LOCATION _____

DATES OF TEST BURN _____

TONS COAL BURNED _____ TON

FIRING RATE _____ MM BTU/HR

TEST DESCRIPTION

COAL HANDLING EQUIPMENT DESCRIPTION:

COMBUSTOR DESCRIPTION:

BOILER DESCRIPTION:

EMISSIONS CONTROL EQUIPMENT DESCRIPTION:

TEST METHOD:

SPECIAL TEST EQUIPMENT:

RESULTS

BASELINE PERFORMANCE CHARACTERISTICS:

COAL HANDLING/GRINDING:
COAL INPUT RATE
TOTAL COAL INPUT

BOILER PERFORMANCE/FOULING:

ASH HANDLING:
ASH OUTPUT RATE
TOTAL ASH INPUT

EMISSIONS:
SO₂
PARTICULATE MATTER
AIR TOXICS INCLUDING Sb, As, Ba, Be,
Cd, Cr, Co, Pb, Mn, Hg, Ni, Se, Va,
Cl, F, AND P.

GENERAL:

7.0 INFORMATION MANAGEMENT AND REPORTING

7.1 Management Responsibilities and Requirements

7.1.1 Organization and Responsibilities

Figure 7-1 depicts the management organization chart for the ACCP Demonstration Project. The ACCP Project Manager is R. W. Sheldon. He is responsible for the development, implementation, and completion of the environmental monitoring plan. The Project Manager is responsible for the completion of all phases of the project, preparation and delivery of reports, and scheduling of meetings. As such, Mr. Sheldon is responsible for securing the resources necessary to complete the EMP.

The Process Engineer will report direct to Mr. Sheldon. He will have responsibility for designing, implementing, tracking, and reporting on all QA/QC aspects of the project. His responsibilities will include assurance that sampling collection, analyses, and tabulation is completed in accordance with specifications of the EMP. The Process Engineer is A. Viall.

The Compliance Monitoring responsibility will be assigned to G. W. Harbrecht who is WECO's Permitting Manager. Mr. Harbrecht will ensure that the required compliance monitoring is scheduled, performed, and reported.

Mr. Viall will also be assigned the supplemental monitoring and the process and operating conditions monitoring. Mr. Viall is also responsible for the tabulation and control of data generated by the Plant Control and Data Acquisition System.

FIGURE 7-1
ACCP Project Management Organization

7.1.2 Resource Requirements

The sampling teams will need glassware, sampling equipment, health and safety supplied, sample shipment containers, and other resources. The following list of resources are the minimum required per sampling event. Malfunction, breakage, etc. have not been included.

7.1.2.1 Sample Containers

Sample containers will be specified by the laboratory selected to perform the required analyses. Sample containers will be selected on the basis of the physical and chemical characteristics expected to be present in each stream.

7.1.2.2 Sampling Equipment

The equipment used in sampling will be determined by the sampling team such that the sample containers will be filled in a safe and accurate manner. The physical and chemical characteristics of the streams may include pressure, extreme temperature, and caustic and acidic fluids.

7.1.2.3 Health and Safety Equipment

The following equipment will be available for each member of the sampling team.

- Hard hat
- Steel toed safety shoes
- Work gloves
- Safety glasses

7.2 Compliance and Supplemental Data Flows

All phases and events which incorporate sampling and analyses of process streams will have a protocol to follow to ensure that all required samples are obtained each day.

In addition, each sample within the sampling event will be assigned a unique sample number. A log sheet with all samples identified will be maintained by the EMP Project Manager, or his designee.

The laboratory will conduct the analyses of samples received in accordance with the parameters identified in Sections 6.0 of the EMP. The required analyses will be transmitted in writing from the Process Engineer to the Laboratory, and any changes in required analyses will also be transmitted in writing. The EMP Project Manager will receive a copy of all such correspondence.

All portions of samples not consumed in analyses will be preserved and retained by the laboratory until receiving written authorization from the EMP Project Manager to either repeat analyses, conduct additional analyses, respond to questions concerning the analyses, or properly dispose of the samples.

7.3 Plant Control and Data Acquisition System

The Plant Control and Data Acquisition System (PCDAS) is the computer and associated software designed for the process. The PCDAS will monitor process variables such as temperature, pressure, flow, and other physical parameters at various time frequencies throughout unit operations. Values will be compared against set points either established within the program, or as input by the unit operators. Based upon the set point comparison, differences which lie outside a predetermined acceptable range will direct the software to initiate unit response activities at other points, such as changing steam flows to control temperature, changing set points on pneumatic actuated valves, etc. Proper operation of the entire unit is dependent upon accurate in-line measurement, signal transmission, and reliability of the software program.

The EMP is reliant upon much of its physical parameter data from the PCDAS. Points specifically identified in the EMP will be field calibrated periodically by means of high end and low end test signal transmission.

7.4 Report Format, Content, and Frequency

Reports will be issued to DOE at the completion of an initial testing and production period, quarterly and annually.

7.4.1 Initial Operations Report

The initial operations report will contain:

- results of monitoring
- dates of monitoring performed;
- contractors utilized in monitoring;
- maintenance records of relevant time frame;
- raw material usage for monitoring;
- production records for monitoring;
- laboratory contractors utilized;
- equipment operational status;
- verification of sample integrity;
- QA/QC report from analytical laboratory.

7.4.2 Quarterly Reports

Reports will be issued by the EMP Project Manager once per quarter to apprise DOE on the project status. Information to be delivered in the status reports includes:

- monitoring activities during the quarter;
- changes to the project schedule;
- activities anticipated during the next quarter.

7.4.3 Annual Reports

The Annual Reports will contain the same items as the Initial Operations Report.

APPENDIX A

Additional Air Quality Information

3.0 EMISSION SOURCES

The present emission inventory for air pollutant emissions is shown in the existing permit #1483D (Appendix A). The proposed alteration to the permit will result in increased particulate and gaseous emissions. A further increase in fugitive particulate emissions is shown on paper as a result of utilizing new emission factor equations from the Compilation of Air Pollutant Emission Factors AP-42. Appendix B and C show the fugitive total particulate and PM-10 particulate emission calculations for the annual and maximum twenty-four hour periods. Tables 1 through 4 summarize the fugitive total and PM-10 particulate emissions for the annual and maximum twenty-four hour periods. Table 5 summarizes the uncontrolled and controlled process particulate and gaseous emissions for the annual period. Table 6 lists the in-plant particulate emissions and various dust collector specifications. The present permitted ACCP demonstration facility total controlled particulate emissions are 11.69 tpy, which includes both the fugitive and process emissions. The proposed alteration would increase the total particulate emissions to a maximum of 95.32 tpy. The sulfur dioxide emissions would increase from the present permitted rate of 7.48 tpy to 35.5 tpy.

TABLE 1
 WESTERN ENERGY COMPANY
 Proposed Alteration
 FUGITIVE TOTAL PARTICULATE EMISSIONS - WORST CASE ANNUAL PERIOD

ACTIVITY	UNCONTROLLED EMISSIONS TON/YR	CONTROL MEASURES	PERCENT	CONTROLLED EMISSIONS TON/YR
Freight	36.04	Chemical Stabilizer/ Watering As Necessary	90	3.60
Commuting	13.46	Chemical Stabilizer/ Watering As Necessary	90	1.35
Waste Hauling	57.62	Chemical Stabilizer/ Watering As Necessary	90	5.76
Waste Dumping	0.55	Minimize Fall Distance	0	0.55
Coal Hopper	34.38	Enclosed Hopper W/Covered Conveyor & Baghouse	99	0.34
Reject To Pile	<u>2.28</u>	Loading Spout W/Shroud	50	<u>1.14</u>
	144.33			12.74

TABLE 2

WESTERN ENERGY COMPANY

Proposed Alteration

FUGITIVE PM-10 PARTICULATE EMISSIONS - WORST CASE ANNUAL PERIOD

ACTIVITY	UNCONTROLLED EMISSIONS TON/YR	CONTROL MEASURES	PERCENT	CONTROLLED EMISSIONS TON/YR
Freight	16.20	Chemical Stabilizer/ Watering As Necessary	90	1.62
Commuting	6.05	Chemical Stabilizer/ Watering As Necessary	90	0.61
Waste Hauling	25.95	Chemical Stabilizer/ Watering As Necessary	90	2.60
Waste Dumping	0.27	Minimize Fall Distance	0	0.27
Coal Hopper	17.19	Enclosed Hopper W/Covered Conveyor & Baghouse	99	0.17
Reject To Pile	<u>1.14</u>	Loading Spout W/Shroud	50	<u>0.57</u>
	66.80			5.84

TABLE 3
 WESTERN ENERGY COMPANY
 Proposed Alteration
 FUGITIVE TOTAL PARTICULATE EMISSIONS - MAXIMUM TWENTY-FOUR HOUR

ACTIVITY	UNCONTROLLED EMISSIONS LB/DY	CONTROL MEASURES	PERCENT	CONTROLLED EMISSIONS LB/DY
Freight	240.24	Chemical Stabilizer/ Watering As Necessary	90	24.02
Commuting	89.74	Chemical Stabilizer/ Watering As Necessary	90	8.97
Waste Hauling	384.17	Chemical Stabilizer/ Watering As Necessary	90	38.42
Waste Dumping	3.69	Minimize Fall Distance	0	3.69
Coal Hopper	188.36	Enclosed Hopper W/Covered Conveyor & Baghouse	99	1.88
Reject To Pile	<u>12.21</u>	Loading Spout W/Shroud	50	<u>6.10</u>
	918.41			83.08

TABLE 4
 WESTERN ENERGY COMPANY
 Proposed Alteration
 FUGITIVE PM-10 PARTICULATE EMISSIONS - MAXIMUM TWENTY-FOUR HOUR

ACTIVITY	UNCONTROLLED EMISSIONS LB/DY	CONTROL MEASURES	PERCENT	CONTROLLED EMISSIONS LB/DY
Freight	108.00	Chemical Stabilizer/ Watering As Necessary	90	10.80
Commuting	40.33	Chemical Stabilizer/ Watering As Necessary	90	4.03
Waste Hauling	173.02	Chemical Stabilizer/ Watering As Necessary	90	17.30
Waste Dumping	1.84	Minimize Fall Distance	0	1.84
Coal Hopper	94.18	Enclosed Hopper W/Covered Conveyor & Baghouse	99	0.94
Reject To Pile	<u>6.10</u>	Loading Spout W/Shroud	50	<u>3.05</u>
	423.47			37.96

TABLE 5
ACCP DEMONSTRATION FACILITY
PROCESS AND COMBUSTION AIR POLLUTANT EMISSIONS

ACTIVITY	UNCONTROLLED EMISSIONS TON/YR	CONTROL MEASURES	PERCENT	CONTROLLED EMISSIONS TON/YR
TOTAL PARTICULATES				
Combustion	33,690	Baghouse	99.97	11.90
In-plant	23,567	Baghouses	99.7	70.68
SULFUR OXIDES				
Combustion	88.8	Induct Sorbent Injection	60.	35.50
NITROGEN OXIDES				
Combustion	50.6	Low NOx Burner	31.3	34.80
CARBON MONOXIDE				
Combustion	119.1	Special Burner Design	76.2	28.30

1. Uncontrolled combustion total particulate emissions based on EPA AP-42 Emission Factors - Industrial Boiler (10-100 MBtu/Hr) with adjustments to account for process make gas incineration.
2. Combustion particulate control based upon equipment specifications for stage one dryer circuit.
3. Combustion NOx and CO control based upon vendor information. G. C. Broach has been selected to provide the process furnace. NOx and CO are controlled by use of a high intensity, low flame temperature burner design which approaches total combustion of all hydrocarbons while limiting NOx formation.

TABLE 6
ACCP DEMONSTRATION FACILITY
BAGHOUSE PARTICULATE CONTROL SYSTEMS

Control System	Air Volume cfm	Fan Outlet Diameter in.	Fan Outlet Velocity fpm	Grade Elevation ft.	Stack Elevation ft.	Controlled Particulates tpy
Screen Area	22,000	38	2795	3328	15	8.41
Raw Coal Bin	7,000	22	2650	3322	103	2.63
Surge Bins	3,400	15	2770	3317	106.5	1.31
Coal Clean.	88,000	3 @ 50	2690	3317	26	33.64
Waste Coal Bin	3,000	14	2805	3317	70	1.05
Dried Coal Silo	13,000	30	2685	3317	135	4.99
Dried Coal Silo	13,000	30	2685	3317	135	4.99
Dried Coal Loadout	18,000	35	2695	3317	15	6.83
Dried Coal Transfer	18,000	35	2695	3317	15	6.83
TOTAL						70.68

4.0 AIR QUALITY IMPACTS

Western Energy Company operated seven air quality monitoring stations during 1990 around the Rosebud Mine. The sampling was conducted for total suspended particulates (TSP). Table 7 summarizes the results for 1990. The Montana and Federal ambient particulate standards are now for 10 micron or smaller (PM-10) suspended particulates. However, the results in Table 7 can be compared against the old Montana TSP standard of 200 micrograms per cubic meter (ug/m^3) for the twenty-four hour period and 75 ug/m^3 for the annual average. The results from the 1990 sampling showed a maximum twenty-four hour TSP concentration of 342 ug/m^3 at Site No. 10 (located approximately three miles west of the proposed ACCP facility). The old Montana TSP standard allowed one excursion of the twenty-four hour standard per year. The second highest TSP concentration for 1990 was 256 ug/m^3 which occurred at Site No. 5. This sampler was located under the direct impact of the topsoil and overburden stripping and eventually had to be moved as the site was within the mining area. Of the sites located off the permit area, the second highest TSP concentration was 241 ug/m^3 , which occurred at Site No. 10 on November 13, 1990. This is the only TSP concentration that violated the old Montana TSP standard. The annual average TSP concentrations at all sites were within the standards.

Due to an increase in particulate emissions, an air quality dispersion modeling analysis was performed to estimate the impact on the area air quality. At the request of the Air Quality Bureau, Department of Health and Environmental Sciences, two dispersion models were used to estimate the impact of the PM-10 particulate emissions on the air quality. The gaseous emissions were not modeled as the increase in emissions for these pollutants was less than the significant level as defined in ARM Section 16.8.921 Definitions - Significant. The dispersion models used for the PM-10 modeling were the Industrial Source Complex Models for short-term and long-term averages (ISCST and ISCLT) and the Complex 1 Dispersion Model. The modeling was completed for twenty-four hour and annual periods. Emissions of annual average and maximum twenty-four hour PM-10 particulates were simulated. Actual terrain heights of receptors and stacks were input for a network surrounding the permit area (see enclosed map). The meteorological data used in the models was obtained from the Montana Power Company Site No. 1 located to the northeast of the ACCP facility. The meteorological data used was from 1989 and included hourly wind speed, wind direction, wind sigma, and temperature.

The dispersion modeling results along with input data for the ISCST and ISCLT models are included in Appendix D. The input data and dispersion modeling results from the Complex 1 modeling

are included in Appendix E. Under instructions from the Air Quality Bureau, the interpretation of the modeling was to be that the PM-10 concentrations calculated at receptor locations below the top of the stacks were to be taken from the ISC models. For PM-10 concentrations at receptor locations above the final plume rise of the stacks, the Complex 1 model results were to be used. For PM-10 concentrations at receptor locations in the area between stack gas exit elevation and the maximum plume rise elevation, the higher concentrations of the two models were to be used. Since in this modeling, emission sources with various stack heights and plume rises occur at the same time, the interpretation of the results would have been exhausting. Instead, as a first review of the results, the maximum concentrations predicted from all the models were first analyzed. The maximum annual PM-10 particulate concentration predicted by the two annual period models was 0.5 ug/m^3 . This is compared to the Montana and Federal PM-10 annual particulate standard of 50 ug/m^3 . The maximum twenty-four hour PM-10 particulate concentration predicted by the two models was 5.7 ug/m^3 . This is compared to the Montana and Federal twenty-four hour PM-10 particulate standard of 150 ug/m^3 .

TABLE 7

SUMMARY OF THE TOTAL SUSPENDED PARTICULATE DATA

January, 1990 - December, 1990

ROSEBUD MINE COLSTRIP, MONTANA

SITE	MAXIMUM	SECOND HIGH	ARITHMETIC MEAN	NO. OF SAMPLES
1A	145	132	45	60
1B	131	127	44	56
5	257	256	54	18
9	101	58	23	56
10	342	241	48	56
11	83	77	24	59
13	108	101	26	56
14	141	129	33	56

(Values in micrograms per cubic meter)

5.0 SUMMARY

Western Energy Company is proposing a change to the method of sulfur dioxide control at their coal beneficiation plant near Colstrip, Montana. The change in control will result in increased particulate and sulfur dioxide emissions. The PM-10 emissions were simulated in two dispersion models using meteorological data from the Colstrip area. The models showed the maximum impact of the coal beneficiation plant and the associated fugitive emissions would be only 0.5 ug/m^3 for the annual average and 5.7 ug/m^3 for the twenty-four hour period. The gaseous emissions were not modeled as the emissions were below the significant level as defined in the Air Quality Bureau regulations, however the impact from these emissions is estimated to very low.

APPENDIX B

Additional Information On Disposal of Process Slack in Mined-out Pits

Disposal and Monitoring

Table B-1 contains a characterization of the process slack.

The process slack coal will be handled so as to minimize the potential for oxidation. The methods employed will include interim storage in a contained bin, regular transport to the final disposal site and covering it with spoil material within 180 days after placement.

The process slack coal will not be buried in proximity of a drainage course or in any location where it would be subject to oxidation. The process slack coal disposal areas will be posted on the backfilling and regrading map in the annual reports. This will allow more accurate monitoring and assist in selection of spoil monitoring well sites.

This will ensure that disposal of these materials, according to the proposed methods, will not adversely affect public water, health, and safety. If these analyses determine that disposal in the herein described manner will adversely affect public water, health and safety, alternate disposal will be provided in a safe and legal manner or the material will be treated on-site to render it non-toxic. Depending on the nature of the problem, mitigating options might include treatment with a neutralizing agent or trucking to an EPA approved landfill.

Table B-2 contains details of a plan for monitoring groundwater quality and levels around process slack disposal areas. Process slack disposal areas will be surveyed for top and bottom elevations, as well as for areal extent (northings and eastings). The survey will be performed following placement of the process slack in the pit, and prior to backfilling. Upon completion of final grading of the overlying spoil materials. These process slack areas will be relocated. Appropriate monitoring well

Table B-1 CHARACTERIZATION OF SOLID WASTES¹

Standard	Parameter	Standard	Area A2 Process Slack	Area B2 Process Slack	Area C2 Process Slack	Area D2 Process Slack	Pit 3 Slack
EP Toxicity	As	5.0	<0.002	<0.002	<0.002	<0.002	<0.005
	Ba	100.0	0.163	0.117	0.071	0.221	0.4
	Cd	1.0	<0.005	<0.005	<0.005	<0.005	0.012
	Cr	5.0	0.050	0.020	<0.020	0.070	0.13
	Pb	5.0	<0.020	<0.020	<0.020	<0.020	<0.02
	Hg	0.2	<0.001	<0.001	<0.001	<0.001	<0.0005
	Se	1.0	<0.002	<0.002	<0.002	<0.002	<0.005
	Ag	5.0	<0.020	<0.020	<0.020	<0.020	0.02
Acid/Base Account							
	Acid Pot, tons/1000t		224	111	135	43	45
	Neut. Pot, tons/1000t		32	19	20	38	42
	Net A/B, tons/1000t	5	-192	-92	-115	20	-3
	Total Sulfur, % dry		10.33	4.07	4.75	1.75	1.8
	BTU/# , dry		8040	7117	7973	9045	---
	Ash, % dry		36	45	37	29	---
	Lime, % dry		3.67	2.54	1.80	6.57	4.22

- 1 All values in Mg/L unless otherwise noted.
- 2 Average over three samples of Rosebud process slack.
- 3 Average over Areas A, B and C pit samples.

Table B-2 GROUNDWATER QUALITY AND WATER LEVEL MONITORING PLAN

Site	pH ¹	Conductivity ¹	Total Organic Carbon ²	Major Cations ²	Major Anions ²	Metals ^{2&3}	Water Levels
Process Slack Disposal Areas							
Up-gradient Well	Quarterly	Quarterly	Quarterly	6 months	6 months	6 months	Monthly
Down-gradient Well	Quarterly	Quarterly	Quarterly	6 months	6 months	6 months	Monthly
Disposal Zone Well	Quarterly	Quarterly	Quarterly	6 months	6 months	6 months	Monthly

¹ Analyzed by WECO on site and duplicated in lab with complete analysis.

² Analyzed by commercial laboratory

³ As, B, Cd, Cr, Cu, Pb, Hg, Mo, Ni, Ag, Se, V, Zn, Fe

installations will then be constructed within and adjacent to the disposal areas. For the initial disposal area, two down gradient wells will be placed to intercept the predicted flow path providing greater confidence of obtaining representative water quality levels within the area of influence. One background monitoring well will be completed within the spoils adjacent to process slack disposal areas which have no existing spoils background wells. These wells will be completed upgradient of process slack disposal areas where possible. However, in situations where mining is proceeding upgradient in relation to groundwater flow direction (Figure B-1, Example 1), and future mine passes are intended for continued process slack disposal areas, background spoils wells will be located adjacent to disposal areas as shown. A typical monitoring well completion cross-section is also shown on Figure B-1. The plan will be integrated into the overall Groundwater Monitoring Plan (HRDV I) for the Rosebud Mine. No impacts to groundwater are likely from the plant itself, so the existing monitoring plan for adjacent wells will be adequate.

All other groundwater monitoring will follow existing schedules with reporting in the Annual and Semi-Annual Reports. These reports are placed in the Resource Volumes as they are updated.

FIGURE B-1 - TYPICAL
AND CROSS SI

WELL LAYOUT SECTION

- — PROCESSED SLACK DISPOSAL AREA
- — 1000' GRID LINES
- — POTENTIOMETRIC CONTOUR WITH FLOW DIRECTION
- — PROPOSED SPOILS MONITORING WELL
- — PROPOSED MONITORING WELLS (SPOILS & INTERBURDEN)
- — DISPOSAL ZONE WELL
- — MINE PIT

Ground Water Concerns

Since it is proposed that the process slack coal be placed at the bottom of mined-out portions of the Rosebud seam below the predicted post mine water table level, a preliminary and conservative analysis of potential ground water quality impacts was conducted. Representative samples of process slack coal, and top/bottom seam slack coal from active pits were analyzed by Northern Engineering and Testing, Inc. to determine concentrations of water soluble constituents in saturation paste extracts. Parameters evaluated were based on primary, secondary, and livestock EPA water quality standards and were compared with similar analysis data conducted on water samples from pre-mine overburden, pre-mine Rosebud coal, and post-mine spoil wells. These data were obtained from Hydrologic Resource Data Volume III.

The slack coal, ground water, and EPA standard data, which are summarized in Table B-3, verify the chemical similarities between the process slack and top/bottom seam slack coal materials in terms of water soluble constituents. As evidenced by post-mine spoil water quality data, the traditional burial of top/bottom seam slack coal in the bottom of the mined-out Rosebud seam has not degraded post-mine ground water quality beyond what is normally expected or accepted in relation to pre-mine ground water quality which tends to be marginal. The data in Table B-3 also provides evidence that there has been no impact on post-mine groundwater quality due to the oxidation of pyrites in the buried pit slack.

**TABLE B-3 SOLID WASTE
GROUND WATER QUALITY IMPACT ANALYSIS¹**

EPA Standard	Parameter	Allowable Level	Process ² Slack	Pit ³ Slack	Post-Mine ⁴ Spoils	Pre-Mine ⁵ Overburden	Pre-Mine ⁶ Rosebud Coal
Primary	As	0.05	<0.030	<0.030	---	---	---
	Ba	1.0	0.1	0.1	---	---	---
	Cd	0.010	<0.005	0.008	0.005	0.005	0.005
	Cr	0.05	<0.02	<0.02	0.01	0.0	0.024
	Pb	0.05	<0.02	<0.02	0.038	0.03	0.02
	Hg	0.002	0.0025	0.017	0.011	0.0	0.001
	NO ₃ -N	10.0	1.49	1.44	7.71	2.61	0.51
	Se	0.01	<0.015	<0.015	0.055	0.008	0.008
Secondary	Ag	0.05	<0.02	<0.02	---	---	---
	F	1.4-2.4	0.55	0.40	0.29	0.23	0.21
	Cl	250	<10.0	<10.0	22.3	10.5	9.6
	Cu	1.0	0.02	0.07	0.03	0.03	0.03
	Fe	0.3	0.06	0.14	0.19	0.29	0.23
	Mn	0.05	0.87	0.41	0.97	0.17	0.27
	SO ₄	250	600	600	1668	747	811
	Zn	5.0	0.09	0.12	0.44	0.21	0.29
	pH (st. units)	6.5-8.5	6.6	6.1	7.4	7.9	7.7
	TDS	500	1200	1200	2959	1405	1597
Livestock	B	5.0	1.5	6.0	---	---	---
	Al	5.0	<0.1	<0.1	---	---	---
	V	0.1	<0.2	<0.2	0.01	0.18	0.43
Others	Ca	NS	3.1	10.2	326	106	165
	Mg	NS	2.2	12.1	298	125	162
	Na	NS	0.5	6.1	144	107	144

1 All values in mg/l unless otherwise noted.

2 Process slack analysis from paste extract.

3 Averaged from Areas A, B, C pit samples from paste extract.

4 Averaged over 83 wells using detection limit if undetectable, Ca, Mg, Na used 66 wells.

5 Averaged over 89 wells using detection limit if undetectable, CA, Mg, Na used 75 wells

6 Averaged over 153 wells using detection limit if undetectable, Ca, Mg, Na used 130 wells

NS - No Standard

Although the Dollhopf study indicated that the process slack materials would not cause acidification, a study was conducted to determine the buffering and attenuation capacity of underlying interburdens (underburden) and overlying spoils.

In this study, samples of underburden and spoil collected from active pit areas were equilibrated with solutions designed to simulate groundwater composition as might be affected by varied levels of pyrite oxidation. The lower the pH of the attenuating solution, the higher the concentration of metals and vice versa. The results of the study provided evidence that typical spoil and underburden materials at the Rosebud Mine have the capacity to totally neutralize acidity and at the same time attenuate high concentrations of metals. This is not surprising given the abundance of carbonate compounds in these geologic materials.

The results of the attenuation study combined with the results of Dollhopf's study, in which weathered samples of process slack failed to produce acid provides strong support in favor of disposing of process slack by deep burial. It was concluded that disposal of process slack coal according to the method proposed will not adversely impact ground water flow and quality of approved post-mine land use.

Western Energy will continue to monitor and report post-mine ground water quality as currently required to ensure that disposal of process slack coal as proposed does not adversely affect ground water quality.

APPENDIX C

QUALITY ASSURANCE/QUALITY CONTROL PLAN

1.0 QUALITY ASSURANCE AND QUALITY CONTROL

Quality Assurance (QA) is a system for ensuring that all information and data gathered under a specific task are technically sound, statistically solid, and properly documented. Quality Control (QC) is the mechanism through which quality assurance achieves its goals. A quality control program defines the frequency, methods of check and audits, and reviews necessary to identify problems and dictate corrective action, thus verifying product quality.

1.1 PURPOSE AND SCOPE

A well planned QA/QC program is absolutely necessary for obtaining reliable monitoring data and method verification. Four fundamental principles must be considered: 1) responsibility for QA must extend to all areas of management; 2) specification of the quality of data must be explicit; 3) the program must have adequate steps to assure that data of needed quality is obtained; and 4) implementable and effective corrective actions must be taken when data are of unacceptable quality. The QA/QC program must address: 1) sampling; 2) analysis; 3) method and data verification; 4) sample management; and 5) data reporting.

1.2 IMPLEMENTATION OF THE QA/QC PROGRAM

Following is a detailed outline of the critical elements of the plan to be implemented for the EMP activities.

1.2.1 Organization

1. Qualifications and background of all ACCP personnel involved with the sampling and analysis will be documented.
2. Specifications of responsibilities for all personnel involved with sampling and analysis will be clearly defined and documented.
3. A chain of custody procedure for samples taken by ACCP personnel and sent to commercial laboratories will be used to ensure the integrity of the sample.

A sample will be considered to be under custody if:

- 1) It is the possession of an authorized individual; or
- 2) It is in view of, after being in the possession of an authorized individual; or
- 3) It has been secured by the authorized individual to prevent tampering; or

- 4) It has been placed in a designated secure area.

To prevent misidentification, sample request forms will be filled out at the time of collection and affixed to the sample container(s). See Figure 10-1. A field log book will also be used to record sample information such as date, time, origin, type of sample (grab or composite), preservatives, collectors identification, and general observations.

The sample request form also acts as the chain of custody record and will be signed off as the sample proceeds through the transport, preparation, and analysis process. The following information will be contained:

- Sample origin
- Sample I.D. number;
- Sample description
- Date(s) collected
- Date(s) delivered
- Signature of collector/deliverer
- Signature of receiver
- Requested analysis
- Analysis results
- Date(s) analysis is reported
- Signature of reporter

4. An alert system for unsatisfactory or unexpected results will be used. Performance charts will be generated for each determination to reflect laboratory performance on duplicates, control and spiked samples. Upper and lower control limits will be established at ± 3 standard deviations from the mean or true value. Any result falling outside these control limits will be brought to the attention of the QA/QC coordinator.

1.2.2 RECORDS

1. Records of all relevant data will be easily accessible and maintained.
2. Logbooks will be kept detailing all samples showing sample time, date obtained, source, sampler, analyst, dates analyzed and reported, etc. Sample or laboratory identification numbers will be given for those samples sent off-site.
3. All laboratory data will be written in ink in laboratory data books which will be reviewed by the QA/QA coordinator on a periodic basis.

WECO COAL ANALYSIS REQUEST/REPORT

Origin: ACCP _____ Other _____ A _____ B _____ C _____ D _____

Sample Number _____

Sample Description _____ (include coordinates for inpit samples)

Date(s) Collected _____

Date Delivered _____ By _____

Time Delivered _____ Received by _____

Analysis Requested: ☐ Short Prox ☐ Moisture Only ☐ Size Analysis
☐ Reabsorption ☐ Other _____

Gross Sample Weight _____

SHORT PROX RESULTS

Results:	<u>As Received</u>	<u>Dry Basis</u>
% Moisture	_____	----
% Ash	_____	_____
% Sulfur	_____	_____
BTU/lb	_____	_____

MAF BTU/lb _____
lb Sulfur/MM BTU _____**Screen Analysis Results**

<u>Size</u>	<u>Weight %</u>	<u>Cumulative % Passing</u>	<u>Cumulative Retained</u>

Please state screen mesh size

Date Reported _____

By _____

Comments _____

4. Records of all graphs, charts and calibrations will be kept.
5. Records of sample preparation will be kept in laboratory notebooks.
6. An inventory control system will be implemented for supply procurement, replacement and storage.

1.2.3

SAMPLING PROCEDURE

1. A procedures manual will be prepared and kept available. All samplers will be familiarized with its content which will delineate the details on sampling locations, sample type, duration of sampling, sample volume, sample collection methods and holding times, equipment to be used for the sample collection, sample containers, pretreatment of containers, type and amount of preservative to be used, blanks, duplicates, spikes, chain of custody and any other pertinent information.
2. A detailed sample schedule will be prepared for use by the samples. This will provide information on sample frequency and number of samples needed.
3. Preservation and storage protocols will be developed and made available to samples and analysts.
4. Container protocols for each parameter will be available to samplers and analysts.

1.2.4

INSTRUMENTS

1. Laboratory personnel will be properly trained in the operation and maintenance of laboratory analytical instruments.
2. Detailed operational procedures will be available.
3. Records of periodic inspection, calibration, maintenance and service will be kept on file in the laboratory.
4. Manufacturers manuals will be available to assist in installation, operation and service functions.
5. Analytical instruments will be checked periodically and maintained by WECO and trained factory service technicians as required.

1.2.5 MEASUREMENT/ANALYSIS

1. A laboratory manual detailing specified procedures (e.g., EPA, ASTM, APHA) for each parameter will be available.
2. Any modification to the above procedures will be noted either in the individual laboratory notebook or the aforementioned manual, including the reasons(s) for the change.
3. Purity of reagents and chemicals will be specified. All reagents will show date prepared and chemicals will show date of receipt.
4. Calculation of results will be clearly defined by examples or by a computer program and will include significant figures, proper units and limits of detection where appropriate.
5. An analytical result report sheet will be prepared showing identification of sample, date taken, date analyzed, analyst, notebook numbers, results, etc.

1.2.6 QA PROCEDURES

1. All calculations will be checked.
2. Spiking of samples in both the field and laboratory will be practiced for appropriate tests.
3. Blanks will be run routinely to determine interference from procedures, equipment or reagent.
4. Replicates will be run routinely to allow an evaluation of the precision of various tests.
5. Standards that can be traced back to primary standards will be used and checked routinely.
6. Recovery experiments will be conducted for appropriate tests.
7. Control charts will be prepared to document actual levels of accuracy and precision. Refer to Section 10.2.1(5).
8. The laboratory will enter a round-robin testing program for limited analyses. This is primarily directed to address coal testing procedures and techniques.
9. Samples will be split from time to time for check analyses by a secondary laboratory.

10. A record of all QA/QC data will be kept on file.
11. Method verification and matrix effects will be checked by sample spiking at various levels and analysis to document actual levels of accuracy and precision.

1.2.7 QUALITY ASSURANCE AUDITS

An independent quality assurance audit program will be conducted by the QA/QC coordinator by submitting blind samples to the laboratory for certain critical analyses. Samples may consist of spikes, samples previously analyzed, duplicates, standards, etc., to provide an independent determination of possible problem areas. Results of analyses which exceed acceptable limits (as established by NBS, EPA, APHA, etc.) will be considered out of control and immediate steps will be undertaken to correct the situation.

1.2.8 CONTRACTED ANALYTICAL WORK

It is anticipated that much of the environmental compliance and monitoring testing will be performed by contract or commercial laboratories. These laboratories will be required to demonstrate equivalency to this QA/QC program as evidenced by certification approval by the State and/or the EPA. Also besides reporting sample data, the commercial laboratories will be requested to provide chain of custody information and quality control test data such as date, time and result of most recent calibration checks, recovery data from spikes, etc.

1.2.9 USEFUL REFERENCE MATERIAL

1. United States EPA - Interim Guidelines and Specifications for preparing Quality Assurance Plans, QAMS-00-80.
2. United States EPA - Strategy for the Implementation of the EPA's Mandatory Quality Assurance Program, QAMS-001/80.
3. Standards Methods for the Examination of Water and Wastewater, 15th Edition.
4. Handbook for Sampling and Sample Preservation of Water and Wastewater, EPA-600/4-82-029.
5. Test Methods for Evaluating Solid Waste, SW-846, EPA.

END

**DATE
FILMED**

3 / 19 / 93