**DOE/PC/90544-T2
(DE92007602)**

**HEALY CLEAN COAL PROJECT, HEALY COAL FIRING AT TRW CLEVELAND
TEST FACILITY**

Final Report

**By
T. Koyama
E. Petrill
D. Sheppard**

August 1991

Work Performed Under Contract No. FC22-91PC90544

**For
U.S. Department of Energy
Pittsburgh Energy Technology Center
Pittsburgh, Pennsylvania**

**By
TRW Space & Technology Group
Redondo Beach, California**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615)576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U. S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

**Applied Technology Division
TRW Space & Technology Group
Redondo Beach, California 90278**

DOE/PC/90544--T2

DE92 007602

Healy Clean Coal Project Healy Coal Firing at TRW Cleveland Test Facility

Final Report

SN 58175

August 1991

Prepared for:

Alaska Industrial Development and Export Authority
480 West Tudor
Anchorage, Alaska

Professional Service Agreement No. HCP-003

PREPARED BY: T. Koyama E. Petrill D. Sheppard Sept 3, 1991
T. Koyama, E. Petrill, D. Sheppard DATE

APPROVAL SIGNATURES:

S. Ubhayakar
S. Ubhayakar, Area leader
Combustion and Energy Technology

September 4, '91
DATE

A. Solbes
A. Solbes, Department Manager
Combustion and Energy Technology

Sept 4, 1991
DATE

Acknowledgements

TRW acknowledges the contributions and support given by the following personnel during the course of this project:

- Steve Denton, Usibelli Coal Mine, Inc. for giving guidelines to safely store and monitor the Healy coals.
- Bob Follett, Stone & Webster Engineering Corporation, for providing temperature measurements in the furnace, and also collecting flyash and slag samples.
- Helene Bjerre-Nielson, NIRO Atomizer, for providing support at Cleveland and analysis of the FCM on a timely basis, which helped in determining the calcination of the limestone injected.

TABLE OF CONTENTS

	<u>PAGE</u>
1. ABSTRACT	1
2. EXECUTIVE SUMMARY	2
2.1 Objectives	2
2.2 Approach	2
2.3 Accomplishments	3
2.4 Results	3
2.4.1 Facility Operations	3
2.4.2 Precombustor and Main Combustor Operation and Performance	4
2.5 Conclusions	5
3. INTRODUCTION	6
3.1 Objectives	7
3.2 Approach	7
4. CLEVELAND FACILITY	9
4.1 Description of Facility	9
4.1.1 Coal Preparation and Feed Systems	9
4.1.2 Limestone Feed System	13
4.1.3 TRW Coal Combustion System	16
4.1.4 Boiler System	20
4.1.5 Auxiliary Systems	20
4.2 Facility Modifications for the Healy Test Burn	22
4.2.1 Coal Preparation System	22
4.2.1.1 System Safety	22
4.2.2 Coal Feed System	23
4.2.2.1 Pulverized Coal Surge Bin	23
4.2.2.2 Weigh Feeder/Splitter/ Transport/System	24
4.2.3 Limestone Feed System	26
4.2.4 Flue Gas/Fly Ash Systems	27
4.2.5 Combustor System	27
4.2.6 Distributed Control System	29
5. TECHNICAL DISCUSSION	30
5.1 Coal Types and Properties/Implications	30
5.2 Limestone Types and Properties	32
5.3 Test Description	32
5.3.1 Grinding Tests	34
5.3.2 Parametric Tests	34
5.3.3 FCM Collection Tests	42
5.4 Test Results and Discussion	45
5.4.1 Coal Handling, Preparation, and Feeding	45
5.4.2 Precombustor Operation	47
5.4.3 Main Combustor Operation	48
5.4.4 Furnace and Emissions	91
6. CONCLUSIONS	110

	<u>PAGE</u>
APPENDIX	113
Appendix A. Solid Sample Analyses Per Test	
Appendix B. Test Data Summaries	
Appendix C. List of Equations	
Appendix D. Damper Configurations Per Test	
Appendix E. Calcination Data	

1. ABSTRACT

A test burn of two Alaskan coals was conducted at TRW's Cleveland test facility in support of the Healy Clean Coal Project, as part of Clean Coal Technology III Program in which a new power plant will be constructed using a TRW Coal Combustion System. This system features ash slagging technology combined with NO_x and SO_x control. The tests, funded by the Alaska Industrial Development and Export Authority (AIDEA) and TRW, were conducted to verify that the candidate Healy station coals could be successfully fired in the TRW coal combustor, to provide data required for scale-up to the utility project size requirements, and to produce sufficient flash-calcined material (FCM) for spray dryer tests to be conducted by Joy/NIRO. The tests demonstrated that both coals are viable candidates for the project, provided the data required for scale-up, and produced the FCM material.

This report describes the modifications to the test facility which were required for the test burn, the tests run, and the results of the tests.

2. EXECUTIVE SUMMARY

TRW conducted a test burn of two Alaskan coals in support of the Healy Clean Coal Project, as part of a DOE Clean Coal Technology III Program in which a new power plant will be constructed using a TRW Coal Combustion System. The TRW system will meter and fire the coal under conditions which suppress NOx emissions. It will also function in conjunction with the furnace as a limestone calciner. A back-end spray dryer will utilize the calcined limestone to reduce sulfur emissions to the required limit.

The tests, funded by the Alaska Industrial Development and Export Authority (AIDEA), and TRW, were conducted between March 29 and June 7, 1991 at the TRW coal combustion test facility in Cleveland, Ohio. This test facility consists of a TRW Model 35 coal combustion system integrated with a 29,000 lb steam/hr Keeler boiler. The coal firing capacity of the facility was increased specifically for these tests to accommodate the lower heating value of the Alaskan coals. Improvements in technology and equipment were also incorporated.

The tests were designed to provide data that will form the basis of the scale-up and design of the combustor and other systems for the Healy Clean Coal Project. The tests also provided calcined material to enable Joy/NIRO to perform pilot plant tests, planned for September, for design of the spray dryer system.

2.1 Objectives

The objectives of the tests were to:

1. Evaluate combustion system operation and performance using selected Alaskan (Usibelli) coals.
2. Collect a 5-ton lot of flash-calcined baghouse catch material (FCM) from the flue gas stream and prepare for shipment to NIRO in Denmark for spray dryer tests. Limestone from Alaska was injected into the combustor/furnace interface.

2.2 Approach

The approach to this project required making necessary modifications to the test facility, then to conduct a series of tests on the Healy coals.

Facility modifications were required to handle higher coal flow rates necessitated by the low heating value of the

coals, and to address safety concerns arising from the high volatility of the coal. Modifications were also made to prevent pulverized coal agglomeration and/or accumulation during transfer. This applied to both the pulverizer sweep air system and to the coal feed transport and recycle systems. System lightoff methods and precombustor design were modified to obtain operability and performance consistent with safe boiler firing practices.

2.3 Accomplishments

The test series:

1. Established facility operations for the Healy coals (coal preparation system operation and mill capacity)
2. Evaluated the coals in terms of grinding and handling characteristics, and combustion and slagging characteristics.
3. Produced 5 tons of FCM for the Joy/NIRO spray dryer tests.

Specifically under this program, TRW accomplished the following:

1. Achieved safe and stable operation of the coal feed system.
2. Established successful coal preparation, handling, and feed systems operation on the Alaska coals.
3. Achieved successful precombustor operation.
4. Conducted 10 parametric tests using Healy Performance coal.
5. Collected 5 tons of FCM in 42 separate runs. The lot was shipped to NIRO in Copenhagen, Denmark.
6. Conducted 10 parametric tests using Healy performance coal, and Two Bull Ridge (TBR) coal.

2.4 Results

2.4.1 Facility Operations

During the test program, over 350 tons of Healy coal were handled by the Cleveland test facility without any indication of coal smoldering or fires. The coal preparation and feed systems were operated without any

adverse incidents throughout the 10-week period of using Healy coal. The CO₂ inverting system was used only when the system was idle. Use of the CO₂ deluge system to quench smoldering or burning coal was never required.

The capacity of the Kennedy Van Saun (KVS) ball mill was found to be limited to 0.8 ton/hr, necessitating that tests be of short duration and/or be conducted at reduced loads. This indicated a Hardgrove Grindability Index of 25 according to KVS. High erosion characteristics during transport were observed for the Healy coal as compared to Ohio coal.

Coal flow rates as high as 3800 lbs/hr were demonstrated using Healy performance coal. This corresponds to a heat input of 30.1 MMBtu/hr (million Btu/hr) assuming a coal HHV of 7932 Btu/lb. System steam production was near 25,300 lbs/hr which included 2,100 lbs/hr generated by the flash tank (7% heat loss). Operation during the test program demonstrated safe and stable operation of the coal feed system including:

- Safe storage of pulverized coal in the surge bin which was used as an accumulator
- Controllable coal flow rate and split
- Smooth, repeatable light-offs during all of over 80 tests
- Prevention of coal agglomeration and accumulation in the coal transport lines.

2.4.2 Precombustor and Main Combustor Operation and Performance

The tests with the Healy performance coal established the operational characteristics of the precombustor and combustor. Stable precombustor operation was achieved with a precombustor coal flow rate of up to 1500 lb/hr. Slag recovery efficiency was excellent, with most of the tests falling in the range of 80 to 90%. The slag tap remained open and free-flowing under all combustor conditions tested, down to as low as 12.5 MMBtu/hr (3 to 1 turndown). There was evidence of ash accumulations at the head end of the main combustor and in the exit of the precombustor. Although the accumulations were cleaned out after intervals of six or seven tests to reduce pressure drop, the accumulations did not appear to adversely affect combustion performance. There were also accumulations of slag in the slag recovery section exit and accumulations of ash in the furnace. These accumulations can be expected to be greatly reduced at Healy due to higher preheat temperatures, larger combustor size, and higher load operation without frequent shutdown.

Carbon losses were low (averaging 1.14% of the total input carbon), with 0.07% lost out the baghouse and 1.07% lost out the slag tap. NOx emissions ranged from 131 to 270 ppm corrected to 3% stack oxygen (0.20 - 0.41 lb/MMBtu).

Solids balances measured on the FCM collection tests were excellent and repeatable to within 10% of closure, giving increased confidence in the slag recovery efficiency and carbon loss results.

The heat absorbed by the combustor was 6 to 13% of the heat input, dependent primarily upon combustor load.

The temperature of the combustion gas exiting the furnace was measured with a high velocity thermocouple (HVT) probe. Furnace exit temperature ranged from 1900 to 2200°F over a load range of 25 to 31 MMBtu/hr.

The flash-calcined material collected for the Joy/NIRO tests was analyzed for level of calcination (percentage of calcium carbonate that oxidized to calcium oxide). Calcination ranged from 50 to 90%. Calcination for the first 11 FCM collection tests was lower (50 to 60%) than for the last 31 FCM tests (80 to 90%).

The tests with the Two Bull Ridge coal showed slightly decreased combustor performance as with the Healy Performance coal. Carbon losses were similar, as well as NOx emissions. CO levels were higher. Slag recovery was less due to the higher T_{250} of the TBR coal.

2.5 Conclusions

The Healy coal test burn demonstrated that the Healy performance coal and the Two Bull Ridge coal can be effectively burned in TRW's coal combustion system. The coal was handled, pulverized, and fed safely and reliably in the Cleveland test facility coal preparation and feed systems. Good to excellent combustion performance was achieved with both coals as inferred by carbon losses. Slag capture was excellent with the performance coal (85%). Slag capture with the TBR coal was less (45%). This is attributed directly to the higher T_{250} (2900 vs 2750°F) of the TBR coal. The larger combustor size and higher preheat temperature (650 vs 400°F) which will be present at Healy will accommodate the TBR coal. Low NOx emissions was also demonstrated. Finally, the tests demonstrated that FCM for the Joy/NIRO spray dryer SOx capture system can be produced by the TRW Coal Combustion System using Alaska coal and limestone.

3. INTRODUCTION

The Healy Clean Coal Project (HCCP) is a joint project of the Alaska Industrial Development and Export Authority (AIDEA) and of the U. S. Department of Energy (DOE). An advanced coal-fired power plant will be constructed in Healy, Alaska. In this project, TRW Coal Combustion System will interface with a Foster Wheeler boiler, and a back-end spray dryer supplied by Joy/NIRO will utilize flash-calcined limestone to control sulfur emissions.

Technical issues associated with the design and operation of the coal combustion system include:

- Effects of coal properties
- Two-phase flow cooling of the combustor shell
- Scale-up from Model 35 combustion system

An approach has been taken which mitigates the risks associated with each of these issues. In particular, for the issues which relate to the effects of coal properties and scale-up, the decision was made to conduct a series of tests at TRW's Cleveland test facility using Healy coals.

The properties of Healy coals are typically low in sulfur, high in volatiles, high moisture, high ash content, and high ash T_{250} . Coals with this combination of properties, and the ensuing low heating value, had not been tested before in the TRW Coal Combustion System. Accordingly, the first goal of the test series was to obtain operational data.

- The high volatile content is advantageous from a combustion view point, but it increases the hazards associated with handling, preparation, and feeding.
- The high ash content and high T_{250} affect primarily the slagging and slag tapping characteristics of the combustor and the heat rejection to the cooling system. The operating conditions are also affected, in particular, the required coal flow split between the precombustor and the main combustor as well as the main combustor equivalence ratio.

The second goal was to conduct a series of tests with representative Healy coals to establish a database to be used for scaling to 350 MMBtu/hr during the design phase of the Healy Clean Coal Project.

At the same time, flash-calcined material (FCM) would also be produced using an Alaskan limestone. The FCM sample would be later used by Joy/NIRO during pilot plant tests. The results of these tests would be used by Joy/NIRO during the design of the Healy back-end clean-up system.

The project team participating in the Healy Clean Coal Project includes AIDEA; DOE; Golden Valley Electric Association, the Healy power plant owner; Usibelli Coal Mine, Inc., the coal supplier; TRW, the coal combustion system supplier; Foster Wheeler Energy Corporation, the boiler supplier; Joy/NIRO, the spray dryer system supplier; and Stone and Webster Engineering Corporation, the project architect/engineer. The project team participated in the test burn by reviewing test plans and procedures, supplying coal and providing storage advice (Usibelli), being on-site during tests (Stone and Webster, Joy/NIRO), and receiving test data and solid samples.

3.1 OBJECTIVES

The objectives of the Cleveland tests were to:

1. Evaluate TRW Coal Combustion System performance at reduced scale using selected Alaskan coals. Data obtained were:
 - Coal grindability
 - Pulverized coal handling/safety
 - Coal feed system operations
 - Combustion efficiency
 - Slag removal efficiency
 - Combustor cooling loads
 - NO_x emissions
 - Furnace temperatures
 - Flyash characteristics
 - Limestone calcination
2. Collect 5 tons of flash-calcined material (FCM) from the flue gas stream by injecting limestone from Alaska into the combustion/furnace interface. The FCM collected by the baghouse would be packaged for the Joy/NIRO spray dryer test work at NIRO's test facility in Copenhagen.

3.2 APPROACH

The overall approach for the test burn was to test the selected Healy coals at TRW's Coal Combustion System Test Facility in Cleveland, Ohio.

The steps taken to conduct this test burn were to:

1. Procure the Healy coals from Usibelli Mine, Inc. in Alaska and transport to a store near the test facility.
2. Modify the Cleveland Coal Combustion System Test Facility as required to perform tests on Healy coals.
3. Perform tests designed to provide the data and the FCM sample as described in the objectives.
4. Analyze the test data and prepare the final report.

4. CLEVELAND FACILITY

4.1 Description of Cleveland Facility

The TRW Coal Combustion System Test Facility is located in the Argo-Tech manufacturing plant in Euclid, Ohio. The facility was originally owned by TRW, and then sold to Argo-Tech. The test facility is currently leased and operated by TRW. The test facility is a commercial application of the combustion system, instrumented for testing. It provides process steam to the manufacturing plant during operation.

The manufacturing plant originally received steam from three stoker-fired watertube Keeler boilers. These boilers were converted to oil and gas operation in the late 1960's, then mothballed in the 1970's. In 1985, Unit No. 3 was converted to fire pulverized coal using the TRW coal combustion system. The combustor/boiler unit, rated at 29,000 lb/hr, produces saturated steam at 100 psig. It presently operates under an Ohio EPA permit for sulfur dioxide and nitrogen oxide and has burned a wide range of coals; low, medium, and high-sulfur bituminous, low-volatile low-sulfur anthracite, and low-sulfur, high-volatile, high-ash subbituminous coal. These coals have featured a T_{250} range of 2300 to 2850°F.

The facility consists of the coal preparation and feed, limestone feed, combustor, boiler, and auxiliary systems. Figure 4-1 is a plan view of the Cleveland facility.

4.1.1 Coal Preparation and Feed Systems

Coal up to 1 1/4 inch x 0 inch size was received by the TRW test facility and pulverized to a nominal 70 to 80% through 200 mesh, transported to a surge bin, and fed to the combustor system. Figure 4-2 shows a schematic of the system.

The coal preparation system includes a KVS ball mill with gas-fired sweep air to dry and carry the coal to the surge bin. The as-received coal moisture content was 23%. The coal was dried to a level of 10-12%. The drying process was limited by the air flow capacity of the system and the maximum allowable inlet temperature of the mill. A classifier with a return leg to the mill allows control of coal particle size distribution. A baghouse separates fines from the sweep air stream; the fines are continuously added back to the coal in the surge bin. For the Healy coal tests, the existing CO₂

FIGURE 4-1. PLAN VIEW OF THE CLEVELAND TEST FACILITY

inverting system was upgraded and a deluge system installed for fire prevention and quenching. A CO monitoring system was implemented at the baghouse exit to indicate presence of coal smoldering or fires.

The coal feed system includes a surge bin with vibrating bin bottom to assure coal availability from the bin. The surge bin collects pulverized coal from the coal preparation system. It provides the capacity which allows for separate control of pulverizer output and coal feed to the combustor system. The surge bin was also used as an accumulator on the Healy coals.

The surge bin supplies coal to a drag-chain-type feeder which controls and meters the coal flow. An adjustable splitter divides the coal flow into two streams, one to the precombustor, the other to the main combustor. The coal is transported to the combustor, located 200 feet away, via carrier air at an air-to-fuel ratio ranging from 0.5 at light-off to 1.5 for the Healy tests.

4.1.2 Limestone Feed System

Pulverized limestone was used in the TRW Coal Combustion System for sulfur capture or fluxing to control the T250 of the ash. Limestone is received at the plant preground to the size required (at least 70% through 200 mesh). Limestone is stored on site in bags or in 30-ton tanker trucks. In operation, the limestone is transported pneumatically to a 4-ton storage tank with a vibrating bin-bottom which supplies the drag-chain-type weigh feeder with a smooth, steady supply of limestone (Figure 4-3). The weigh feeder monitors and controls the limestone flow rate. The flow stream can be split with an adjustable splitter. The limestone drops through the splitter into two eductors. Carrier air transports the limestone through 1-1/2 inch lines to the limestone injectors and/or the fluxing line. This system is very similar to the coal feed arrangement.

Figure 4-4 shows two injection locations available for sulfur capture: the centerline injector and/or the peripheral nozzles. The centerline injector is installed in the back wall of the combustor exit duct leading to the boiler, on the centerline of the duct. The peripheral nozzles are eight equally-spaced nozzles located around the periphery of the secondary burner. For the Healy tests, the FCM collection tests were conducted with the limestone injected through the centerline injector, except for one test in which the limestone was injected through the nozzles. Previous tests on bituminous coal with sulfur content ranging from 1 to 3% demonstrated that for high-sulfur coal, splitting the limestone flow equally between the two injection options gave the optimum sulfur capture.

Limestone was used to flux the ash in two tests on the Two Bull Ridge coal. During these tests, limestone was not used for sulfur capture. To that effect, limestone was injected into the main combustor coal feed line upstream of the coal injector. The limestone flow rate for fluxing was about 5% of the coal flow rate. No problems were encountered with the operation of the fluxing system nor the combustion system during fluxing.

FIGURE 4-3. LIMESTONE FEED SYSTEM

FIGURE 4-4. COAL AND LIMESTONE INJECTION LOCATIONS

4.1.3 TRW Coal Combustion System

The TRW Coal Combustion System includes a precombustor and a main combustor as shown in Figure 4-5. A photograph of the installation is included.

The precombustor provides high-temperature air to the main combustor for ignition by burning 25 to 50% of the coal stoichiometrically, then mixing with the remaining first stage air. Mounted tangentially on the main combustor, the precombustor is a water-cooled refractory lined cylinder approximately one-fourth the size of the main combustor. Coal is injected axially along the precombustor centerline. The remaining first stage combustion air is added to the precombustor exhaust gases. These hot gases then enter the main combustor, forming a swirling flow pattern.

With the hot gases from the precombustor, the balance of the coal is injected into the main combustor which operates in a substoichiometric, slagging mode. Combustion stoichiometries from deeply sub to complete can be used. The main combustor is a water-cooled cylinder inclined at a 15° angle towards the slag tap with a tangential air inlet and a centered exit baffle. The tangential air inlet and the baffle promote proper mixing and an internal vortex flow pattern for rapid combustion (Figure 4-6). The coal injector, located at the head end, injects coal in a conical pattern axially along the main combustor centerline. Multiport injectors have also been successfully used.

Fifty to seventy-five percent of the coal is injected into the main combustor where it is entrained by the hot, swirling combustion air from the precombustor and burned in flight. Ash contained in the coal is converted to molten slag and centrifuged to the combustor walls, forming an insulating slag layer. The fluid slag flows by gravity down the main combustor to the slag tap, and then into the water-filled slag tank where it is quenched, and fractured into pebble-sized particles. The slag is removed from the slag tank with a drag chain conveyor and dropped into a bin for disposal (Figure 4-7).

FIGURE 4-5. TRW COAL COMBUSTION SYSTEM

FIGURE 4-6. MIXING, COMBUSTION, AND INTERNAL VORTEX FLOW PATTERN IN MAIN COMBUSTOR

Combustor

Slag
Conveyor

FIGURE 4-7. SLAG REMOVAL WITH DRAG CHAIN CONVEYOR

The hot combustion gases enter the slag recovery section which provides additional residence time for combustion and additional slag recovery. When the main combustor operates at substoichiometric (fuel-rich) conditions, the combustion gas contains CO and H₂. The gases are ducted to the furnace via a water-cooled duct. Secondary air is added at the interface of the furnace so as to yield a stoichiometry in the range 1.1 to 1.4. The secondary air is introduced through an annulus in the windbox surrounding the combustor hot gas duct. Combustion is completed in the boiler's furnace.

4.1.4 Boiler System

The Keeler boiler is divided into furnace and convective sections as shown in Figure 4-8. The exit of the TRW combustor interfaces with the boiler at the front face of the furnace section. The furnace section of the boiler (only 40% water-cooled) is refractory-lined, providing a hot combustion zone. The convective passes of the boiler cool the gases to 500 to 700°F prior to entering a tubular air preheater, which preheats the combustion air to a maximum of 430°F.

The boiler is a balanced-draft system with forced and induced draft fans. The balance point is located inside the boiler. A baghouse with Gortex bags removes particulates from the gas stream before exhausting out the stack. Emissions (sulfur dioxide (SO₂), nitrogen oxide (NO), carbon monoxide (CO), and oxygen (O₂)) are monitored continuously at the stack using in-situ analyzers. SO₂ and NO_x are measured by a Lear-Siegler instrument using second derivative spectroscopy. A zirconium oxide analyzer measures O₂, and an infra-red absorption analyzer measures CO.

4.1.5 Auxiliary Systems

The combustor is cooled by pressurized sub-cooled water which is flashed to steam in a flash tank. The pressure in the cooling jackets is near 650 psig. The flow rate of the combustor cooling water and its temperature rise is measured to determine combustor heat absorption.

The operation of the combustor and boiler systems are controlled and monitored by a computerized distributed control system. The control room contains two computer modules and a printer. The system is customized for the

FIGURE 4-8. CUTAWAY VIEW OF KEELER BOILER

TRW combustor and includes alarms as well as automatic main fuel trips to shut down the combustor in the case of potentially hazardous conditions.

Three types of data can be retrieved from the system:

1. Instantaneous conditions of the system.
2. Current trends of up to six measurements.
3. Historical trends of measurements.

4.2 Facility Modifications for the Healy Test Burn

The Healy test program could not have been conducted without making a number of facility and equipment changes to the Cleveland Test Site. Many of these modifications were required to deal with the large change in Healy coal properties compared to other coals which the facility had been recently handling. Modifications were needed to:

- handle higher coal flow rates necessitated by the low heating value of the coal.
- address safety concerns arising from the high volatility of the coal.

A number of issues pertaining to system operation and performance had been carried over from previous test activities. Additional modifications were required to:

- resolve coal feed control problems.
- provide a high level of system lightoff reliability.
- improve system performance.

The installation of a new coal feed system had been undertaken prior to the implementation of the Healy test burn. Upgrading of the system was required to meet Healy requirements.

A brief description of each of the modifications at Cleveland prior to the Healy test burn and the reason for their implementation is presented in the following sections.

4.2.1 COAL PREPARATION SYSTEM

4.2.1.1 System Safety

Because of the high volatility of the Healy coals, provisions for fire prevention and fire fighting were installed in the coal preparation plant. CO₂ was used for inverting and was available for suppressing smoldering or fires if required. Water was available for use as a last resort. CO and temperature levels were monitored to determine system status. Steps taken to improve coal feed control and to control relative humidity also improved safety.

- CO₂ inverting

Additional lines for flowing CO₂ gas from the existing CO₂ dewar system were installed in strategic locations for inverting the system after shutdown.

- CO₂ deluge

An emergency high pressure CO₂ deluge system was installed for immediately backfilling the entire system. Activation required pulling a single handle outside the building in the event of an emergency.

- Water lines

Water lines with connections for attaching a flexible water hose were installed to strategic equipment in case of need for fighting a fire and/or coal smoldering.

- Sample system

Sample lines and a continuous monitoring system were installed for constant monitoring of CO and CO₂ in the system.

4.2.2 Coal Feed System

4.2.2.1 Pulverized Coal Surge Bin

Increased coal storage capacity was needed in the surge bin. A larger (3000-lb capacity) surge bin was installed. A vibrating bin-bottom (provided by Vibrascrew) was also installed to assure a stable flow of coal to the weigh feeder. The bin-bottom was enclosed inside the tank providing a unit meeting the NFPA 50-psig design pressure requirement. CO₂ inverting was continuously maintained in the dead space between the bin-bottom and tank walls. The tank interior was inverted only when the system was off for more than several hours. Coal was left in the surge bin only when necessary.

- Structure modification

The existing mounting structure was changed to contain and support the larger/heavier surge bin. Personnel access grating, etc., was modified as required.

- Indicators

A new vertical mounting arrangement for the indicators used to monitor the coal level in the surge bin was installed. The existing electrical wiring/DCS logic arrangement was used.

- Bin-bottom vibrator

A second vibrator was added to the bin bottom. The bin-bottom vibrators required removal for adjustment. Setting the new and or original vibrators at different outputs provided three available vibration levels by switching one, the other, or both units on, without the need to remove the vibrators for adjustment. The lowest available level of vibration provided the best coal flow stability and was used during the test series.

- Atmospheric vent

The existing vent to the sweep air system was removed. A new atmospheric vent to ground level outside the coal preparation building was installed. This vent was open during most of the testing.

4.2.2.2 Weigh Feeder/Splitter/Transport/System

A Vibrascrew mass weigh system enclosed in a safety vessel meeting the NFPA requirements had been installed prior to Healy. It provided sufficient output to meet Healy requirements. CO₂ inverting was continuously maintained within the safety vessel. Changes to the feeder were made to improve its performance. A new enlarged splitter assembly was required.

- Coal sample port

A pipe and valve was installed for sampling pulverized coal immediately below the isolation gate valve positioned between the surge bin and feeder.

- Exit transitions

New upper and lower feeder exit transitions were made with steeper sides to prevent coal accumulations on their surfaces. Small coal accumulations had affected the weigh feeder load cell reading. This reading provided system stability as well as coal density data.

- Feeder drag chain

Metal drags of larger cross section were installed on the drag chain to increase the area of the feed channel swept by the drags. Drag chain speeds up to 25 ft/min appeared to provide stable coal flow without this modification. Incorporating the change provided stable flow at the maximum speeds of 40 ft/min required during the Healy test program.

- Feeder inlet box
Shrouds previously employed within the feeder inlet box to help assure coal supply to the drag chain were eliminated.

- Splitter/eductor assembly
A larger splitter/eductor assembly was designed, fabricated, and installed. The assembly included new three-inch and four-inch Fox Eductor Assemblies. Three sets of different-sized nozzles were available. Changing nozzles had little effect.

- Transport Lines
New carbon steel schedule 80 three and four inch lines were installed for conveying precombustor and main combustor coal, respectively. The transport lines required about 5.5 equivalent 90 degree bends and over 200 feet of length. Approximately the last 30 feet of both lines was stainless steel. All bends were short radius flanged at both ends for quick access for line inspection and/or clean out. Coal coating in the lines never exceeded a very light dusting after relative humidity control and grounding was provided.

The end of the main combustor line was initially installed at a 45 degree angle from plant ceiling to floor. This was changed to vertical after a large deposit of coal was found at ground level in the line.

A connection was provided in the main combustor recycle line for discharging coal to a guppy storage system. A return line was installed for returning coal from the guppy to the surge tank. The need for these lines was later negated by a decision not to use the guppy system.

- Diverter Valves
Special three-way air-operated ball valves were installed to divert coal flow from recycle to firing. The valves were returned to the recycle position after shutdown. These valves retain constant flow area at all ball orientations. The air operators were modified to require only a few seconds transition time from the recycle to the firing position. This minimized coal accumulation at the valve during the transition period. The shortened time provided very smooth lightoffs.

- Fire Valves
Special two-way air-operated ball valves were installed as fire valves. Each valve was opened prior to cycling its corresponding diverter valve. This technique assured that carrier air flow was never intermittently combined with coal. This avoided intermittent flame failure at light-off which had previously been a problem.

- **Back Purge**

An enlarged back purge air supply system was required to supply sufficient flow to adequately clean the transport and recycle lines during back purging. Back purge operations were carried out first through the precombustor transport line, splitter assembly, and the main combustor recycle line. Both diverter valve positions were then reversed and the procedure performed through the main combustion transport line, splitter assembly, and precombustion recycle line.

4.2.3 Limestone Feed System

The Vibrascrew limestone feed system already installed did not require any modification for this program. Catch and weigh calibrations were run to assure the accuracy of the limestone flow at the low flow rates required (less than 1 pound per minute). This system has delivered rates as high as 25 pounds per minute.

- **Limestone centerline injector**

A new water-cooled limestone centerline injector with a thermal expansion compensation joint was installed. The previous injector, designed without compensation, had distorted and failed.

- **Limestone fluxing**

A Y-joint connection for injecting limestone into the main combustor coal transport line for fluxing was installed downstream of the fire valve. Connecting plumbing from the existing system to the fluxing line shutoff valve was added. A two-way splitter and eductor system was already available. This permitted injecting limestone into the burner throat and fluxing at the same time. Fluxing was not used while making baghouse catch product for NIRO.

4.2.4 Flue Gas/Fly Ash Systems

The fly ash from the Healy test burn was handled without making major modifications to the system. A method for dumping all the sorbent collected from each test into barrels was devised. A special attachment for conducting the material from the fly ash silo into the barrel was installed. The barrels were sealed after filling and shipped to NIRO.

The water content of the flue gas was higher than previously experienced. The coal was dried to a moisture level of 10 to 12%, not the normal operating level near 2%. No baghouse operating problems were experienced as a result of the higher moisture content of the flue gas. Problems with deposits in the stack emissions monitoring equipment did require attention. The equipment was checked out and cleaned by Spectrum Systems during the program.

At the outset of the Healy test burn, an unusually high pulse rate was accidentally imposed on the baghouse. This cleaned the bags to where some of the very fine fly ash bled through creating a stack plume. Reducing the pulse frequency by adjusting/repairing the timer control system resolved the problem. Each row of bags was pulsed at a uniform period of one minute between rows. A similar practice is also used by NIRO to maximize cake uniformity on the bags.

4.2.5 Combustor System

A number of modifications were made to the head-end of both the precombustor and main combustor in order to accommodate the larger-sized coal injectors required. Centerline coal injection was used at both locations. Provisions were incorporated to allow changing the depth of the location of coal injection relative to the head-end.

- Precombustor injector

The precombustor injector was a pipe of the same diameter as the precombustor coal transport line. Windbox equipment within the precombustor surrounding the injector had to be modified to accommodate the larger pipe. Various flame holding arrangements were tried until a system was found which could adequately attach the coal flame despite a nearly two-fold increase in cold carrier air present.

The coal flame scanner was relocated so that readjustment by the operator during lightoff was never required. Prior positioning had occasionally resulted in the generation of an erroneous coal flame signal if the

flame scanner picked up the gas ignitor flame.

The ignitor acted as an excellent source of stabilization, however, the goal was to operate with the ignitor off. Flame-holding without the ignitor was verified, however, much of the test program was conducted with the ignitor on.

The injector was mounted so that different length sleeves mounted and sealed between bolted flanges could be used to change the depth of the location of coal injection. The location of injection relative to the plane of the precombustor throat proved to be important. The coal supply pipe was extended about six feet straight out in front of the injector.

- Main combustor injector

A pintle-type injector was used for the main combustor. The existing hot sleeve was used as the outer sleeve within which the coal/carrier air flowed. The end of the sleeve required a redesign and repair of cracks which would have resulted in cooling water leakage. The hot sleeve was freed from the headend plate prior to the start of testing.

The pintle deflector, or wear ring, used to divert coal flow outward was replaceable. Replacement of this piece was necessary during the program because of the very high rate of erosion noted with the Healy coal.

The injector arrangement was also designed so that sleeve extensions mounted and sealed between bolted flanges could be used to alter the depth of the location of the coal injector. The injector was moved from a two-inch depth to as much as eight inches during the test program.

The coal entrance to the injector was changed at the start of the program from vertical down to sloped upward.

- Slag tap

A special plate containing a restrictive slag tap had been removed during earlier testing. A special dipper skirt arrangement incorporating tiles extending from below the water to the bottom side of the plate had been installed at the same time as the plate. These tiles had deteriorated and required replacement to prevent dipper skirt overheating. It was noted that the tiles contained numerous vertical cracks which allowed the tiles to crumble and fall inward.

New tiles were installed in two sections with a saw-break two inches below the normal level of water on the

dipper skirt. Retaining bands were welded in place in locations where contact with slag could be avoided. The saw cuts reduced the stress levels in the tiles. No case of dipper skirt overheating due to tile failure was noted during the program.

4.2.6 Distributed Control System

The recycle, lightoff, and back purge system changes required that logic revisions be programmed into the Westinghouse DCS. New control and data display stations were created. A ramping station was added for control of the coal feeder speed. A fully automatic system for controlling air and fuel changes over the load range from lightoff to full load was programmed but not implemented.

5. TECHNICAL DISCUSSION

5.1 Coal Types and Properties/Implications

The Healy coals are subbituminous coals with high moisture, high ash content, and high volatility. The ash also has a high T_{250} , the temperature at which the ash flows with a viscosity of 250 poise.

Coals with this combination of properties had not been tested before in a TRW coal combustion system. The high moisture was a concern for handling, drying/pulverization, and feeding the coal as well as combustor performance, baghouse operation, and emissions monitoring at the stack. The high ash and high T_{250} was a concern for slagging characteristics and slag recovery efficiency. The high volatility is beneficial for combustion, but posed safety concerns in storing and pulverizing the coals, and feeding the pulverized coals to the combustor.

Two coals were selected for this test burn series: the Healy performance blend and Two Bull Ridge coal. The coals, both candidate station coals for the utility project, were supplied by Usibelli Coal Mine, Inc.. Two other coals were also supplied to the test burn project by Usibelli but were not tested. These were waste coal and run-of-mine coal.

The Healy performance coal is a 50-50 blend of run-of-mine coal, and waste coal. The run-of-mine coal has a lower T_{250} and is currently sold to overseas customers. The waste coal has a higher T_{250} and currently has no market. The reason for blending these coals is to yield a technically viable coal at a reasonable price. The Two Bull Ridge (TBR) coal is a low-grade seam coal, from a seam from which Usibelli is not currently producing. This coal is another potentially low-priced fuel for the Healy power plant.

As fired analyses of the two coals are given in the following table. The analyses are averages of a number of samples taken after pulverizing, from a sample port in the surge bin of the coal feed system. The performance coal analysis is an average of 22 samples, the TBR analysis is an average of 8 samples. The ultimate and proximate analysis and the mineral analysis of the ash of each coal sample are presented in Appendix A, Tables A1 & A2.

The summary table shows that the performance coal was dried to about 11% moisture for these tests. The as-fired ash content was 20%, heating value about 8000 Btu/lb, and the

Table 5-1. Average Analysis of As-Fired Coal

	Average of Healy Performance Coal Analyses	Average of Two Bull Ridge Coal Analyses
PROXIMATE		
% Moisture	11.00	9.82
% Ash	20.63	27.32
% Volatile	39.24	38.20
% Fixed Carbon	29.13	24.67
Btu/lb	8047	7358
ULTIMATE		
% Moisture	11.00	9.82
% Carbon	47.81	43.50
% Hydrogen	3.62	3.41
% Nitrogen	0.77	0.76
% Sulfur	0.33	0.36
% Ash	20.61	27.32
% Oxygen	15.86	14.83
ASH		
ANALYSIS		
% SiO ₂	61.62	58.05
% Al ₂ O ₃	14.46	21.71
% TiO ₂	0.64	0.95
% Fe ₂ O ₃	4.53	3.78
% CaO	9.92	6.28
% MgO	1.76	1.62
% K ₂ O	1.74	1.96
% Na ₂ O	0.70	0.14
% SO ₃	3.31	3.16
% P ₄ O ₅	0.17	0.14
% SrO	0.10	0.07
% BaO	0.23	0.27
% MnO	0.16	0.15
Undetermined	0.64	1.73
T250	2692	2876
(Calculated)		

T₂₅₀ was about 2700°F. The TBR coal was dried with the same mill conditions to a lower moisture content at about 10%. The as-fired ash content was higher at 27%, heating value lower at about 7400 Btu/hr, and the T₂₅₀ was higher at about 2900°F, due to different constituents in the ash. The volatile content and sulfur content were comparable for both coals.

As will be discussed subsequently, the coal preparation system (mill) also imposed limitations as a result of the low grindability of the coal. Consequently, performance data as well as FCM collection data were acquired during tests of limited duration. The maximum duration for these tests was about 3 hours as limited by the capacity of the coal feed system surge bin which was used as an accumulator.

5.2 Limestone Types and Properties

Two Alaska limestones were available for use during Healy testing. They were Cantwell limestone which came from a previously unmined quarry, and Cantwell dolomite limestone which came from a previously mined quarry. Chemical and physical properties for each limestone are given in the following table. It indicates that the Cantwell limestone is much richer in calcium carbonate (90%) than the dolomite limestone (60%). For Healy testing, only the Cantwell limestone was utilized. This was because it was thought that the Cantwell limestone would generate a more suitable type flyash material for NIRO's pilot plant tests.

5.3 Test Description

The tests for the Healy test burn were conducted between March 29 and June 7, 1991 at the TRW Coal Combustion System Test Facility in Cleveland, Ohio. Over 350 tons of Alaska coal were burned during these tests.

Three types of tests were conducted: coal grindability tests, parametric tests, and FCM sample collection tests. The test series was designed to:

1. Establish facility operations (coal preparation system operation and mill capacity).
2. Evaluate the coals in terms of grinding and handling characteristics, and combustion and slagging characteristics.
3. Collect 5 tons of FCM for the Joy/NIRO spray dryer tests.

Table 5-2. Sorbent Types and Properties

o Type		Cantwell Limestone	Limestone Dolomite
o Chemical, wt. %			
	CaCO ₃	90.71	57.14
	MgCO ₃	5.04	36.69
	Insolubles	4.71	5.90
o Physical, % passing *			
	Mesh		
	50	95.16	98.71
	100	92.55	95.73
	140	89.81	93.51
	200	79.34	80.29
	270	69.85	73.97
	325	48.16	68.92
	400	N/A	61.92
	500	0.00	0.00

* - the size analysis was determined by the wet sieve process

5.3.1 Grinding Tests

Several tests were conducted using the performance coal to determine coal grindability and maximum capacity of the Cleveland facility ball mill. The following parameters were varied:

- Ball level in mill
- Classifier setting
- Mill outlet temperature

For these tests, less than one ton of coal was pulverized, then fired in the combustor. A sieve analysis on pulverized coal samples taken from the surge bin during each run was performed to determine coal particle size distribution.

With the database established for the performance coal, only a few tests were needed for the TBR coal to determine grindability and mill capacity. The results showed similar behavior for the two coals. The results are discussed in section 5.4.

5.3.2 Parametric Tests

Test Procedures

Since the minimum test load selected for parametric tests was higher than the maximum capacity of the mill, the surge bin was used as an accumulator and the test duration was limited to a few hours. The tests were performed as follows:

1. Coal was pulverized and stored in the surge bin until the surge bin level indicators read 100% full.
2. The precombustor and main combustor were started at light-off conditions, then ramped up to the selected load as quickly as possible. This ramp-up averaged 20 minutes. Once load was reached, the test began and data was recorded.
3. A set of distributed control system (DCS) diagrams were printed every 30 minutes after the test started detailing the combustor operating conditions.
4. Gas samples were monitored continuously during each test.
5. Coal samples were taken during each test for analysis. The samples were taken at the bottom of

the coal surge bin as shown in Figure 5-1. Four samples were taken for each test.

6. Slag flowing from the combustor was removed by the drag chain conveyor and dumped into buckets for temporary storage prior to being emptied into the slag dumpster. Slag samples were taken from the buckets (wet) during each test for analysis. A weigh scale was located under the dumpster.
7. Flyash material was continuously trapped in the baghouse. It was transferred to a flyash silo as shown in Figure 5-1. The flyash material was then dropped into 55 gallon drums for storage. Flyash samples were taken from the drums for analysis. Four samples were taken for each test. Total flyash weight for each test was the net weight of the filled drum.
8. The test continued until the surge bin accumulator emptied of coal and a main fuel trip (MFT) occurred. The test ended on the MFT.
9. The raw test data was copied and sent to project team members (Stone and Webster, Golden Valley Electrical Association (GVEA), and NIRO). The test data originals were sent to the TRW project office in California for analysis.
10. Samples were sent to Commercial Testing & Engineering for analysis: ultimate and proximate analyses, and mineral analysis of ash. Duplicate samples were sent to NIRO and GVEA.

Performance Coal.

Ten parametric tests were conducted using the Healy performance coal (tests H13 through H18). The conditions and results of these tests are summarized in Table 5-3. Complete data is presented for each individual test in Appendix B.

Figure 5-1. Solid Sample Locations

Table 5-3. Summary of Healy Performance
Coal Parametric Tests

HEALY TESTS	SLAG RECRY GRIND POS. S	PC DAMPER POS. S	PC INJ. DEPTH FT/S	PC INJ. IN.	PCC PHL	PC PHL	MC PHL	SB PHL	LOAD PHL	COAL PC	COAL MC	COAL SPLIC	PCCA PCPD	SECA INTR.	AIR SB STACK	O2 S	CO PPM	NOX PPM
300-H13	76 25/25	253	2	0.93	1.70	0.76	1.15	20.1	959	1558	36.1	4.30	4.45	5.07	4401	2.55	6.13	126 148
300-H13-1	70 50/50	253	2	1.02	2.11	0.92	1.22	19.7	938	1522	38.1	4.80	6.11	4.43	3481	3.55	6.21	8 213
400-H13-2	94 65/65	253	2	1.03	2.21	1.00	1.20	26.2	1013	1513	40.1	5.28	7.17	3.14	3888	3.34	6.31	0 180
401-H14	87 70/90	255	2	1.01	2.37	1.00	1.29	24.9	1200	1913	38.5	6.30	9.75	5.39	1502	4.47	5.40	189 180
402-H14-1	62 81 85/85	257	2	1.01	2.29	0.98	1.42	24.7	1200	1888	38.9	6.28	9.21	8.05	-110	5.06	5.00	65 215
404-H14-2	65/65	262	2	1.04	2.23	0.91	1.35	25.9	1290	2040	36.9	6.54	8.53	8.55	1638	5.21	6.10	8 219
405-H15	69/60	302	2	1.09	2.07	0.88	1.21	24.9	1192	1920	38.3	6.00	7.01	6.16	4491	3.45	6.25	4 183
406-H16	90/90	306	2	0.91	2.07	0.91	1.22	29.7	1492	2228	40.1	6.29	11.25	6.94	5384	3.51	6.30	15 233
407-H17	63 79 80/80	303	2	0.89	2.01	0.80	1.21	30.1	1368	2399	36.3	6.37	9.16	9.06	4795	3.37	5.90	105 239
408-H18	85 78 80/80	308	2	0.95	2.45	0.89	1.20	30.6	1272	2561	33.2	6.28	11.43	7.15	7455	3.25	5.90	2 271
AVG	80 80	283		0.98	2.15	0.90	1.25	25.1	1183	1955	37.9	5.93	8.41	6.40	3698	3.85	6.14	52 208
																		0.314

Table 5-3. Summary of Healy Performance
Coal Parametric Tests (continued)

HEALY TESTS	S02 03% PPM	S02 W/O LS	CA/S RATIO	S	S02 REHNE	PC EXIT	TOT STM	COOL LOAD	BLR EFF	FUEL /STM	HEAT LOSS	FLX 1 BLR/	FLX 2 BLR/	FLX 3 BLR/	FLX 4 BLR/	FLX 5 BLR/	FLX 6 BLR/	FLX 7 BLR/	FLX 9			
300-H13	348	405			N/A	0.34	13.9	3000	17.8	10.4	81.9	0.93	504	1.36	1.77	2.03	2.19	4.00	2.70	1.00	0.77	REGION LOAD AT PHE=0
300-H13-1	336	405			N/A	0.34	17.3	2020	17.5	9.4	81.9	0.92	511	0.87	1.33	1.63	2.01	1.63	1.27	0.96	1.50	REGION LOAD AT PHE=0, SWIRL VELOCITY AT 250 FT/S
400-H13-2	357	405			N/A	0.34	12.0	2096	18.3	11.0	81.5	0.90	617	0.83	1.26	2.64	3.32	3.12	2.27	1.42	1.36	REGION LOAD AT PHE=1, SWIRL VELOCITY AT 250 FT/S
401-H14	304	405			N/A	0.34	10.4	2545	22.4	8.4	80.9	0.90	504	3.50	0.94	3.03	3.27	2.70	2.22	1.39	0.45	MAXIMUM LOAD AT PHE=0, SWIRL VELOCITY AT 250 FT/S
402-H14-1	322	405			N/A	0.34	21.3	2597	23.2	9.6	82.4	0.87	661	0.44	0.94	3.27	4.00	4.20	2.06	1.39	1.36	MAXIMUM LOAD AT PHE=0, SWIRL VELOCITY AT 300 FT/S
404-H14-2	331	405			N/A	0.34	18.0	2631	23.5	7.9	82.3	0.91	507	0.50	1.10	2.00	3.43	2.39	1.74	1.20	0.00	MAXIMUM LOAD AT PHE=0, SWIRL VELOCITY AT 300 FT/S
405-H15	319	405			N/A	0.34	21.5	2704	20.7													MAXIMUM LOAD AT PHE=0, SWIRL VELOCITY AT 300 FT/S
406-H16	336	405			N/A	0.34	17.1	2706	23.2	7.0	82.5	1.05	501	0.22	0.77	4.26	5.72	3.00	1.82	1.49	0.23	MAXIMUM LOAD AT PHE=0, SWIRL VELOCITY AT 300 FT/S
407-H17	336	405			N/A	0.34	17.1	2070	23.6	6.5	82.7	1.05	547	0.36	0.71	2.92	3.19	2.54	1.35	1.97	0.45	MAXIMUM LOAD AT PHE=0, SWIRL VELOCITY AT 300 FT/S
408-H18	341	405			N/A	0.34	15.9	2412	22.2													MAXIMUM LOAD AT PHE=0, SWIRL VELOCITY AT 300 FT/S
AVE	339	405				0.34	16.5	2715	21.2	8.0	82.1	0.94	501	0.66	1.11	2.01	3.30	3.07	1.93	1.25	0.77	

The conditions for these tests ranged as follows:

Load	20 - 31 MMBtu/hr
Coal Grind	76 - 83% through 200 mesh
Coal Flow Split	33 - 40% to precombustor, remaining to main combustor
Main Combustor Equivalence Ratio	0.76 - 1.00
Secondary Burner Equivalence Ratio	1.20 - 1.42
Stack O ₂	5.9 - 6.9%
Combustion Air Preheat	355 - 415°F
Ca/S Ratio	0

Two Bull Ridge Coal.

Ten parametric tests were conducted using the Two Bull Ridge coal (tests TBR3 through TBR12). The conditions and results of these tests are summarized in Table 5-4. Complete data is given for each individual test in Appendix B.

The conditions for these tests ranged as follows:

Load	13 - 25 MMBtu/hr
Coal Grind	82 - 96% through 200 mesh
Coal Flow Split	39 - 47% to precombustor, remaining to main combustor
Main Combustor Equivalence Ratio	0.74 - 1.10
Secondary Burner Equivalence Ratio	0.91 - 1.43
Stack O ₂	5.5 - 8.8%
Combustion Air Preheat	249 - 393°F
Ca/S Ratio	0

Table 5-4.

YEARLY TESTS	SLUG &	COAL DAMPER RECTIFY GRIND POS.	PC EXIT FT/S	TH.	PC PRI	HC PRI	SB PRI	LOAD /HR	COAL E/HR	COAL MC SPLIT	PCCA KPPH	PCRB KPPH	SBCA INTR. AIR E/HR	OZ SO STACK	OZ CO	MOX PPH	MOX E/MINUTE			
5555-TBR1	0/50	154	6	1.33	1.96	0.94	1.05	12.8	679	1060	39.0	4.02	2.37	1.02	6167	2.12	8.00	19	193	0.292
5554-TBR2	0/50	254	6	0.98	2.05	0.91	1.05	20.0	1060	1658	39.0	4.79	6.23	2.03	6549	0.84	6.53	111	174	0.264
5555-TBR3	0/50	343	6	0.79	1.42	0.74	0.71	25.4	1600	1855	46.3	6.00	5.55	3.15	9852	-1.05	5.00	31	707	0.310
5556-TBR4	95 0/50	347	6	0.99	2.06	1.06	1.31	23.2	1400	1674	46.9	6.39	9.47	4.33	1018	4.71	5.09	82	241	0.361
5557-TBR5	54 97 0/75	313	6	0.88	2.06	1.06	1.43	23.1	1474	1666	46.9	6.16	9.40	6.45	-110	6.06	5.97	156	242	0.361
5558-TBR6	40 0/75	321	6	0.85	2.03	1.04	1.32	23.9	1523	1720	47.0	6.21	9.84	4.93	1096	4.81	5.50	138	343	0.514
5559-TBR7	43 96 100/100	100	6	0.87	2.08	1.07	1.40	23.3	1489	1683	46.9	6.22	9.91	5.78	455	5.73	6.00	126	224	0.336
5604-TBR8	82 100/100	100	6	0.91	2.09	1.06	1.42	23.2	1482	1675	46.9	6.49	9.66	6.03	-288	5.96	5.79	234	211	0.315
5611-TBR9	49 100/100	182	6	0.90	2.07	1.07	1.27	23.6	1504	1700	46.9	6.52	9.71	3.53	2358	4.16	5.70	344	253	0.390
5621-TBR10	30 0/50	279	6	1.04	1.94	1.03	1.23	18.7	1192	1367	46.9	5.87	5.91	2.79	2355	3.66	5.96	202	236	0.355
5631-TBR11	92 0/50	278	6	1.13	2.09	1.10	1.43	17.8	1155	1282	47.0	6.12	5.98	4.34	-590	6.54	6.11	186	231	0.345
5641-TBR12	73 88 0/50	274	6	1.10	2.07	1.09	1.35	17.8	1134	1281	47.0	5.95	6.01	3.47	1103	5.70	6.40	30	226	0.340
ATC	48	259		0.97	1.99	1.02	1.26	21.1	1313	1550	45.6	5.89	1.52	3.99	2527	4.11	6.23	138	232	0.340

Table 5-4. Summary of Two Bull Ridge
Parametric Tests (Continued)

HEATLY TESTS	S02 W/O PPH	S02 LS	CA/S RATIO	S	S02 REHOC	PC EXIT	TOT STH	COOL LOAD	BLR EFF	FUEL LOSS	HEAT BLU/s	FLX 1 FLX 2	FLX 3 FLX 4	FLX 5 FLX 6	FLX 7 FLX 9	COMMENTS					
				%	%	%	%	%	%	%	%	%	%	%	%	%					
553-TBR1	210	465	48.0	2.22	0.36	48.2	2000	8.8	14.9	82.7	1.21	529	0.87	1.29	2.57	3.60	2.06	1.74	2.56	0.00	TESTS TO IDENTIFY OPERATING CONDITIONS FOR TBR COAL
554-TBR2	209	466			0.36	37.7	1950	15.9	7.1	83.0	1.03	394	0.50	1.06	1.63	2.61	1.59	1.27	2.24	0.00	TESTS TO IDENTIFY OPERATING CONDITIONS FOR TBR COAL
555-TBR3	371	461	553.6	12.89	0.36	10.7	2150	16.9	6.2	82.2	1.21	435	1.02	0.82	1.17	1.00	1.74	1.59	3.20	1.36	TESTS TO IDENTIFY OPERATING CONDITIONS FOR TBR COAL
556-TBR4	331	466			0.36	29.2	1950	19.1	7.2	83.2	1.00	463	1.02	1.06	0.93	1.63	2.38	2.06	2.13	0.91	TESTS TO IDENTIFY OPERATING CONDITIONS FOR TBR COAL
557-TBR5	346	466			0.36	26.4	1950	21.1	6.0	82.7	0.89	383	0.87	0.71	1.17	2.29	1.27	1.27	2.13	0.91	TESTS TO IDENTIFY OPERATING CONDITIONS FOR TBR COAL
558-TBR6	242	466			0.36	48.4	1950	18.5	4.8	84.1	1.07	317	0.73	1.06	0.93	1.63	1.11	1.27	1.71	0.91	TESTS TO IDENTIFY OPERATING CONDITIONS FOR TBR COAL
559-TBR7	382	466			0.36	18.7	1950	19.6	5.7	82.3	0.97	370	0.44	1.06	1.37	2.61	1.43	0.95	1.92	0.00	TESTS TO IDENTIFY OPERATING CONDITIONS FOR TBR COAL
560-TBR8	340	466			0.36	25.9	1950	19.6	5.3	82.3	0.96	339	0.50	1.06	1.63	2.61	1.59	1.11	2.03	-0.45	TESTS TO IDENTIFY OPERATING CONDITIONS FOR TBR COAL
561-TBR9	313	466			0.36	33.0	1950	16.8	6.9	86.8	1.21	452	0.44	0.82	1.17	2.29	2.54	1.90	1.17	0.91	TESTS TO IDENTIFY OPERATING CONDITIONS FOR TBR COAL
562-TBR10	365	466			0.36	21.8	2000	15.1	6.6	83.9	1.02	342	0.58	0.82	0.70	1.63	1.59	1.59	1.17	1.36	TESTS TO IDENTIFY OPERATING CONDITIONS FOR TBR COAL
563-TBR11	318	465	82.0	2.73	0.36	32.3	1950	16.1	6.2	83.9	0.91	309	0.58	0.82	0.70	1.31	0.95	1.11	1.07	1.36	TESTS TO IDENTIFY OPERATING CONDITIONS FOR TBR COAL
564-TBR12	374	464	166.0	5.53	0.36	30.7	1950	14.5	4.7	83.1	0.99	230	0.29	0.82	0.93	1.31	0.79	0.43	1.07	0.45	TESTS TO IDENTIFY OPERATING CONDITIONS FOR TBR COAL
AVG	322	465	212.3	5.84	0.36	30.9	2000	16.8	6.8	83.3	1.04	388	0.67	0.95	1.22	2.11	1.59	1.37	1.87	0.44	

5.3.3 FCM Collection Tests

Forty-two tests were run using the performance coal in which the baghouse catch was collected as the FCM sample for NIRO's pilot plant tests. The tests were run at 20 MMBtu/hr, selected to promote acceptable slagging and to allow reasonable test durations for sample collection. Since these tests were run at a load higher than the maximum capacity of the mill, the test duration was limited to about three hours per test.

These tests were conducted using the same procedures as the parametric tests with the additional steps of injecting limestone in the combustor exit and collecting the FCM. The baghouse catch was collected in 55-gallon drums, marked and weighed for each test.

The conditions and results of these tests are given in Table 5-5. Complete data is given for each individual test in Appendix B.

Average test conditions for the FCM collection tests were:

Load	20 MMBtu/hr
Coal Grind	75% through 200 mesh
Coal Flow Split	45% to precombustor, remaining to main combustor
Main Combustor Equivalence Ratio	0.98
Secondary Burner Equivalence Ratio	1.04
Stack O ₂	6.15%
Combustion Air Preheat	385°F
Ca/S Ratio	1.6 (ranged from 1.02 to 2.05)

Tests

NSM 002 APRIL 1964 - 1

Table 5-5. Summary of Healy Performance Coal FCM Tests (Continued)

HEALY TESTS	S02 W/O PPM	LS	CU/S	S	REMOV	PC	TOT	COOL	BLR	FUEL	HEAT	FLX 1	FLX 2	FLX 3	FLX 4	FLX 5	FLX 6	FLX 7	FLX 8	FLX 9	COMMENTS
												BTU/HR	BTU/HR	BTU/HR	BTU/HR	BTU/HR	BTU/HR	BTU/HR	BTU/HR	BTU/HR	
500-020	259	484	68.0	2.05	0.34	38.2	2120	10.0	19.0	82.7	0.93	1052	3.19	4.06	6.07	4.74	4.76	6.02	2.31	1.36	STIRL VELOCITY AT 250 FT/S, WIND COLLECTOR
501-021	280	485	55.5	1.71	0.34	38.0	2050	10.3	9.3	82.8	1.00	572	1.82	2.12	2.57	3.27	2.54	2.22	2.56	1.36	STIRL VELOCITY AT 250 FT/S, WIND COLLECTOR
502-022		485	58.0	1.75	0.34		1970	10.0													STIRL VELOCITY AT 250 FT/S, WIND COLLECTOR
503-023	330	485	36.0	1.25	0.34	18.4	1050	10.1													STIRL VELOCITY AT 250 FT/S, WIND COLLECTOR
504-024	369	485	30.0	1.02	0.34	8.7	1050	17.0	11.4	82.6	0.94	631	1.30	1.77	2.00	2.06	2.30	1.90	1.17	1.13	STIRL VELOCITY AT 330 FT/S, WIND COLLECTOR
505-025	325	485	32.0	1.13	0.34	10.6	1070	17.1	11.0	81.6	0.92	646	0.87	1.65	2.27	3.27	2.54	3.01	1.71	0.81	STIRL VELOCITY AT 330 FT/S, WIND COLLECTOR
507-027	352	485	34.0	1.16	0.34	12.8	2200	10.7													STIRL VELOCITY AT 375 FT/S, WIND COLLECTOR
508-028	321	485	36.0	1.23	0.34	20.6	2200	10.2													STIRL VELOCITY AT 380 FT/S, WIND COLLECTOR
509-029	365	485	10.0	0.61	0.34	9.0	2150	17.0	10.2	81.7	0.95	570	0.50	1.06	2.27	3.76	3.17	2.30	1.71	0.91	STIRL VELOCITY AT 380 FT/S, WIND COLLECTOR
510-030	336	485	17.0	0.50	0.34	16.8	2150	17.0	12.7	79.9	0.90	704	0.73	1.29	3.97	4.09	4.12	2.54	2.83	1.35	STIRL VELOCITY AT 400 FT/S, WIND COLLECTOR
511-031	320	485	17.3	0.59	0.34	10.9	2200	10.4	10.1	80.2	0.87	561	0.51	1.47	3.27	3.84	3.81	2.22	1.81	0.23	STIRL VELOCITY AT 400 FT/S, WIND COLLECTOR
512-032	326	485	17.0	0.59	0.34	10.2	2250	17.0													STIRL VELOCITY AT 400 FT/S, WIND COLLECTOR
513-033	355	485	10.0	0.62	0.34	12.0	2250	10.0	10.3	80.3	0.89	570	0.44	1.10	2.33	3.10	2.38	2.06	1.71	0.91	STIRL VELOCITY AT 400 FT/S, WIND COLLECTOR
523-034	252	485	47.7	1.02	0.34	37.6	2250	17.5	9.0	81.9	0.94	547	1.25	0.92	2.29	3.24	2.83	2.70	2.54	0.82	CONTINUE WIND COLLECTION AT MEDIUM LOAD
524-035	240	485	40.0	1.02	0.34	38.3	2150	18.1	10.2	81.3	0.91	575	0.87	1.06	2.22	3.27	2.22	2.22	2.24	1.27	CONTINUE WIND COLLECTION AT MEDIUM LOAD
525-036	169	485	40.0	1.09	0.34	50.0	2200	17.0	9.0	81.4	0.95	409	0.85	1.04	2.15	2.81	2.30	2.03	2.22	0.54	CONTINUE WIND COLLECTION AT MEDIUM LOAD
526-037	182	485	50.4	1.71	0.34	54.7	2150	15.0	10.2	81.3	1.05	570	0.50	1.29	2.00	3.76	3.33	2.06	2.56	0.45	CONTINUE WIND COLLECTION AT MEDIUM LOAD
527-038	193	485	48.0	1.05	0.34	52.1	2150	15.9	10.0	81.0	0.95	550	0.32	1.00	2.92	3.60	2.85	2.06	2.51	0.00	CONTINUE WIND COLLECTION AT MEDIUM LOAD
528-039	201	485	40.0	1.05	0.34	50.3	2200	17.0	9.3	81.2	0.93	572	0.22	0.82	2.33	3.19	2.38	2.14	2.24	0.00	CONTINUE WIND COLLECTION AT MEDIUM LOAD
529-040	221	485	50.3	1.71	0.34	45.3	2200	10.0	10.4	81.4	0.90	570	0.22	0.74	2.68	4.00	2.82	2.45	2.40	-0.77	CONTINUE WIND COLLECTION AT MEDIUM LOAD
530-041	220	485	48.0	1.01	0.34	45.4	2200	17.5	10.0	82.2	0.95	609	0.44	1.10	3.03	3.92	3.61	2.06	2.24	0.45	CONTINUE WIND COLLECTION AT MEDIUM LOAD
531-042	213	485	48.0	1.36	0.34	47.1	2200	17.1	11.2	80.7	0.92	626	0.44	1.41	3.27	4.00	2.45	2.22	2.35	0.45	CONTINUE WIND COLLECTION AT MEDIUM LOAD
532-043	177	485	58.0	1.72	0.34	56.2	2150	17.2	11.1	80.6	0.93	609	0.29	1.29	2.00	4.00	2.70	2.54	2.24	0.00	CONTINUE WIND COLLECTION AT MEDIUM LOAD
533-044	195	485	42.5	1.46	0.34	51.5	2200	16.9	9.6	80.7	0.95	527	0.51	1.12	2.33	3.43	2.66	2.54	2.24	0.00	CONTINUE WIND COLLECTION AT MEDIUM LOAD
534-045	109	485	47.0	1.59	0.34	52.9	2200	17.0	9.4	80.5	0.91	525	0.44	1.06	2.57	3.27	2.22	2.20	2.24	0.45	CONTINUE WIND COLLECTION AT MEDIUM LOAD
535-046	197	485	51.0	1.73	0.34	51.0	2250	17.0	9.1	81.6	0.92	506	0.29	1.24	2.00	3.19	2.16	1.90	2.00	0.23	CONTINUE WIND COLLECTION AT MEDIUM LOAD
536-047	196	485	52.0	1.79	0.34	53.7	2150	16.7	9.0	81.4	0.96	527	0.51	0.90	2.92	3.32	3.22	1.95	2.30	0.14	CONTINUE WIND COLLECTION AT MEDIUM LOAD
537-048	196	485	51.0	1.70	0.34	51.4	2150	17.1	11.5	80.9	0.94	631	0.50	1.10	2.27	3.92	3.33	3.01	2.67	0.55	CONTINUE WIND COLLECTION AT MEDIUM LOAD
538-049	172	485	50.0	1.71	0.34	51.4	2200	16.5	9.0	83.3	1.01	547	0.57	1.17	2.70	3.91	3.47	2.60	2.61	0.41	CONTINUE WIND COLLECTION AT MEDIUM LOAD
540-051	175	485	52.5	1.70	0.34	58.4	2200	16.5	9.0	83.3	1.01	601	0.44	1.20	3.27	4.00	2.85	2.30	2.24	0.41	CONTINUE WIND COLLECTION AT MEDIUM LOAD
541-052	210	485	47.0	1.59	0.34	47.9	2200	17.5	11.4	80.6	0.93	640	0.44	1.10	3.27	4.50	3.17	2.70	3.31	-0.45	CONTINUE WIND COLLECTION AT MEDIUM LOAD
542-053	190	485	51.0	1.70	0.34	52.9	2150	10.4	12.0	80.8	0.90	605	1.02	1.20	3.50	4.90	3.81	3.01	2.89	0.00	CONTINUE WIND COLLECTION AT MEDIUM LOAD
543-054	197	485	51.0	1.77	0.34	51.1	2200	15.9	10.4	80.5	1.00	566	0.50	1.06	2.80	4.25	3.45	2.54	2.67	0.00	CONTINUE WIND COLLECTION AT MEDIUM LOAD
544-055	194	485	48.9	1.69	0.34	51.9	2150	17.9	10.5	80.9	0.89	575	0.55	1.04	3.45	4.30	3.77	2.82	2.75	-0.54	CONTINUE WIND COLLECTION AT MEDIUM LOAD
545-056	181	485	48.0	1.63	0.34	48.4	2200	17.4	9.9	81.4	0.94	614	0.73	1.47	4.03	4.09	3.96	2.54	2.45	0.00	CONTINUE WIND COLLECTION AT MEDIUM LOAD
546-057	200	485	47.0	1.61	0.34	48.4	2200	16.5	9.5	80.9	0.90	553	1.10	1.06	3.73	3.86	2.85	2.35	2.10	0.23	CONTINUE WIND COLLECTION AT MEDIUM LOAD
547-058	181	485	48.5	1.68	0.34	55.1	2150	17.0	10.7	81.4	0.94	523	0.76	1.50	2.74	3.72	2.50	2.56	2.21	1.25	CONTINUE WIND COLLECTION AT MEDIUM LOAD
548-059	166	485	50.0	1.72	0.34	53.8	2150	16.9	9.5	82.8	0.97	527	0.97	1.41	2.57	3.43	2.38	2.54	2.13	0.91	CONTINUE WIND COLLECTION AT MEDIUM LOAD
549-060	199	485	50.5	1.75	0.34	50.5	2200	16.9	9.0	81.0	0.95	490	0.80	1.26	2.45	3.35	2.62	2.46	2.10	0.00	CONTINUE WIND COLLECTION AT MEDIUM LOAD
550-061	223	485	50.0	1.70	0.34	44.7	2150	16.5	9.6	81.5	0.90	534	0.40	1.33	2.61	3.40	2.65	2.65	2.10	0.54	CONTINUE WIND COLLECTION AT MEDIUM LOAD
551-062	206	485	49.5	1.70	0.34	34.1	2150	16.0	8.0	81.0	0.96	483	0.29	1.47	2.33	2.94	2.70	2.70	2.13	0.45	CONTINUE WIND COLLECTION AT MEDIUM LOAD
552-063	183	485	48.0	1.71	0.34	54.0	2100	10.5	8.0	81.1	0.95	476	0.44	1.20	2.57	3.43	2.70	2.38	2.24	0.45	CONTINUE WIND COLLECTION AT MEDIUM LOAD
AVE	238	485	43.0	1.40	0.34	41.1	2103	17.4	10.4	81.4	0.94	577	0.70	1.34	2.87	3.69	2.92	2.53	2.31	0.46	

5.4 Test Results and Discussion

This section contains the findings of the tests and a discussion of the results.

5.4.1 Coal Handling, Preparation, and Feeding

Storage

The Healy coals were carefully stored in a local yard in 5-foot-high compacted piles instrumented with a grid of thermocouples at the bottom of the piles. Temperatures never rose above 95°F, demonstrating that attention given to coal storage was successful in avoiding problems. A temperature history record is shown in Figure 5-2.

Handling

The Healy performance coal did not present any significant handling difficulties. The coal was considerably more abrasive than other coals that have been handled in the Cleveland test facility.

The TBR coal was more difficult to handle at times than the performance coal, sticking in the transfer lines to the 25-ton silo upstream of the ball mill, as well as in the silo itself. The TBR coal varied in handling difficulty: one truckload was difficult to handle, the next was not.

Grindability

The Healy performance coal was more difficult to grind than coals previously tested in Cleveland. The maximum mill capacity was found to be 1 ton/hr, equivalent to 16 MMBtu/hr. According to KVS, the ball mill manufacturer, this corresponds to a Hardgrove Grindability Index of approximately 25.

Normal mill operation was to set mill feeder speed near 25% and to limit the mill inlet temperature to 400°F. The mill outlet temperature normally ran near 135°F. Raising the temperature to 150°F did not increase the output measurably. The ball level in the mill was 2 inches below the inner edge of the mill exit liners. The sweep air flow rate was held constant near 5300 lbs/hr.

The TBR coal exhibited similar grindability characteristics.

Coal Preparation and Feed System Operation and Safety

During the test program, over 350 tons of Healy coal were handled by the Cleveland test facility without any indication of coal smoldering or fires anywhere in the facility. CO concentrations in the sweep air never reached

Figure 5-2. Historical Temperature Record of Healy Coal Piles in Storage

a level of concern. The coal preparation and feed systems were operated without incident during the 10-week period of using Healy coal. The CO₂ inerting system was successfully used during idle periods. Use of the CO₂ deluge system to quench smoldering or burning coal was not required.

The maximum coal flows demonstrated during the test program were 3800 lb/hr and 3455 lb/hr on the Healy performance coal and the TBR coals, respectively. Safe and stable coal feed operation was obtained. Furthermore, the high moisture content of the coals did not create any coal feed problem. In conclusion, the following was demonstrated:

- Safe storage of pulverized coal in the surge bin (surge bin capacity was approximately 1 ton)
- Controllable coal flow rate and split
- Smooth, repeatable light-offs during over 80 tests
- Prevention of coal agglomeration or accumulation in coal lines

5.4.2 Precombustor Operation

Prior to the Healy tests, the precombustor internal configuration was modified to accommodate the larger diameter injector (3 inch vs. 2 inch diameter) and the higher carrier and coal mass flow rates (factor of 3 to 4). Satisfactory precombustor operation was verified using an Ohio coal. Flame holding limited the combustion air flowrate to near 7000 pounds per hour.

The precombustor was operated successfully on both Healy coals for a total of over 80 tests. Light-offs were consistent and repeatable. While normal operation was to run the precombustor with the gas ignitor on, acceptable operation without the ignitor was verified.

Using the performance coal, the precombustor coal flow rate ranged from 800 to 1500 lb/hr. Using TBR coal, the coal flow rate ranged from 679 to 1523 lb/hr. Some evidence of slag growth was found at the exit of the precombustor, but these were less frequent and less troublesome when the precombustor was run at higher temperatures (higher coal flow rates).

In conclusion:

- The precombustor provided a reliable and stable source of high-temperature ignition air to the main combustor.

- The precombustor operated successfully over a wide range of conditions.
- Precombustor exit slag growths were reduced with higher precombustor exit temperatures.
- Flame holding diminished as flow was increased.

5.4.3 Main Combustor Operation

The main combustor lit off and operated acceptably on both Healy coals for a total of over 80 tests. As with the precombustor, light-offs were consistent and repeatable. Bright, intense head end combustion was observed, especially when the dampers, which control the velocity of the precombustor exit gases, were biased toward the head end (precombustor damper settings per test are given in Appendix D). The following sections give further details on combustor performance.

Carbon Conversion

Carbon conversion was calculated from the analyses of the solid samples taken during each test, to indicate the combustion performance of the system. Table 5-6 shows average slag and FCM analyses from the FCM collection tests. FCM is defined as the material caught in the baghouse and is also referred to as flyash in this report. Slag and flyash samples were taken during each test as described in the test procedure Section 5.3.2. Carbon content of the slag averaged 2.27%. For the FCM, the average was 0.7%. The carbon in the slag is relatively low, at about the same value or slightly higher than observed in previous tests with Ohio coal. The FCM carbon content is very low, significantly lower than observed in Ohio coal tests. The reduction in the FCM carbon content indicates that the combustion of the Healy performance coal is different from that of the Ohio coal.

Carbon conversion was calculated for the performance coal and TBR tests for which slag and FCM measurements were available. Carbon conversion was determined using the following equation:

$$\text{Carbon conversion} = (1 - \text{losses} / \text{input}) * 100$$

$$\begin{aligned} \text{where} \quad \text{Losses} &= (\text{slag wt}) * (\text{slag carbon content}/100) \\ &\quad + (\text{FCM wt}) * (\text{FCM carbon content}/100) \\ \text{Input} &= (\text{coal wt}) * (\text{coal carbon content}/100) \end{aligned}$$

The inputs to the calculations and the results are shown in

Table 5-6. FCM and Slag Characteristics

Slag Characteristics

PROXIMATE		ASH ANALYSIS (dry)	
% Moisture	16.53	% SiO ₂	66.81
% Ash	80.89	% Al ₂ O ₃	13.91
% Volatile	1.09	% TiO ₂	0.63
% Fixed Carbon	1.50	% Fe ₂ O ₃	4.33
Btu/lb	367	% CaO	8.77
		% MgO	1.66
ULTIMATE		% K ₂ O	1.72
% Moisture	16.53	% Na ₂ O	0.78
% Carbon	2.27	% SO ₃	0.08
% Hydrogen	0.03	% P ₄ O ₅	0.17
% Nitrogen	0.12	% SrO	0.10
% Sulfur	0.13	% BaO	0.19
% Ash	80.89	% MnO	0.17
% Oxygen	0.03	Undetermined	0.72
		T 250	2820

FCM Characteristics

PROXIMATE		ASH ANALYSIS	
% Moisture	0.12	% SiO ₂	48.60
% Ash	98.04	% Al ₂ O ₃	17.06
% Volatile	1.75	% TiO ₂	0.72
% Fixed Carbon	0.09	% Fe ₂ O ₃	6.06
Btu/lb	16.25	% CaO	17.05
		% MgO	2.57
ULTIMATE		% K ₂ O	2.32
% Moisture	0.12	% Na ₂ O	0.65
% Carbon	0.70	% SO ₃	1.60
% Hydrogen	0.04	% P ₄ O ₅	0.10
% Nitrogen	0.21	LOI	2.49
% Sulfur	0.62	Undetermined	0.78
% Ash	98.05		
% Oxygen	0.27	% Ca	12.02
		% CO ₂	2.08
		% CaCO ₃	4.72
		% CaSO ₄	2.79

Table 5-7 for the FCM collection tests. The average chemical analysis was used for tests for which the solid samples were not analyzed. The specific analysis was used for tests where the solid samples were analyzed. Where the carbon conversion results are not given, slag or flyash data were not available. Carbon conversion for the performance coal ranged from 97.0 to 99.5%, averaging 98.9%. These results show that combustion was very good during most tests.

Carbon losses are shown graphically in Figure 5-3. It shows the separate losses to the slag and FCM for each test. Carbon losses to the slag averaged 1.07% and to the flyash only 0.07% of the total carbon input. Since carbon losses to the flyash are small, the carbon conversion numbers above are thus mainly based upon carbon losses to the slag.

The effect of coal grind on carbon content of the slag is shown in Figure 5-4 for FCM tests where solid samples were analyzed. The figure indicates that the carbon content of the slag is less for a coarser grind. However, as will be shown in the next section, slag recovery is observed to decrease significantly with a coarser grind. Low values for slag carbon content and also slag recovery for a coarser grind results in a low level of carbon loss to the slag or a high level of carbon conversion. Although a coarser grind may appear advantageous from a carbon loss view point, 70% thru 200 mesh or finer is required to obtain high levels of slag recovery (greater than 75%).

Carbon conversion for the TBR tests for which data was available is shown in Table 5-8. Again, carbon losses to the slag were greater than to the flyash. The graphic representation is given in Figure 5-5. Carbon conversion ranged from 97.5 to 99.3%, averaging 98.5%. Carbon losses to the slag averaged 1.36% and to the flyash 0.07% of the total carbon input. Carbon losses using TBR coal were slightly higher than with the performance coal, indicating that the combustion was not quite as good with the TBR coal.

In conclusion:

- Carbon conversion for the Healy performance coal was very good, averaging 98.9%, indicating acceptable combustion of the performance coal
- Carbon conversion for the TBR coal as calculated was good, averaging 98.5%.
- Carbon losses to the flyash were extremely low, a phenomenon not previously observed for other coals (e.g. Ohio, W.VA.) in the past in Cleveland.

Table 5-7. Carbon Conversion for FCM Test

Carbon Conversion																							
TESTS	R22	R23	R24	R25	R27	R28	R29	R30	R31	R32	R33	R34	R35	R36	R37	R38	R39	R40	R41	R42	R43	R44	R45
INPUTS																							
COAL FLOW (G/HR)	2436	2440	2501	2403	2401	2404	2506	2404	2509	2477	2405	2511	2533	2407	2512	2407	2525	2507	2536	2513	2402	2404	2519
BURNATION (HRS.)	200	196	134	103	142	103	141	103	159	170	105	104	151	212	105	109	133	151	209	103	194	153	100
CARBON IN COAL (G)	47.04	44.64	47.04	47.04	47.04	47.04	47.04	40.36	47.04	47.04	47.04	46.04	47.04	47.5	47.04	47.04	47.04	49.93	48.1	47.04	47.04	47.04	40.16
1. CARBON IN (G)	4001	3571	2672	3227	2920	3241	2817	3079	3101	3470	3289	3100	3050	4200	3305	3351	2670	3150	4249	3266	3039	3030	3001
TOTAL INPUT (G)		3571	2672	3227	2920	3241	2817		3101	3470	3289			4200		3351	2670	3150	4249	3266	3039	3030	3001
LOSSES																							
SLAG RECOVERED	1004	805	1355	1114	1420	1161			1220	1592	1369			2013		1413	901	1040	2020	1690	1773	1301	1635
CARBON IN SLAG (G)	2.20	1	2.20	2.20	2.20	2.20	0.5		2.20	2.20	2.20	1.65	2.20	3.23	2.20	2.20	2.20	1.04	5.92	2.20	2.20	2.20	1.70
1. SLAG CARBON LOST (G)		10	20	31	25	33	26		20	36	31			65	32	32	22	19	120	39	40	32	29
FLYASH RECOVERED	340	270	270	200	190	220	170	310	180	210	330	210	230	290	170	100	100	290	300	230	250	200	320
FLYASH CARBON (G)	0.74	0.52	0.74	0.74	0.74	0.74	0.74	1.27	0.74	0.74	0.74	0.31	0.74	0.37	0.74	0.74	0.74	0.52	0.97	0.74	0.74	0.74	0.94
2. FLYASH CARBON LOST (G)	3	1	2	2	1	2	1	4	1	2	2	1	2	1	1	1	1	2	4	2	2	1	3
TOTAL LOSSES (G)		17	22	33	27	34	28		29	30	34			66		33	24	21	123	40	42	33	32
(1-(LOSSES/INPUT))*100 (G)	99.5	99.2	99.0	99.0	99.1	99.9	99.0		99.1	99.9	99.0			98.4		99.0	99.1	99.3	97.1	98.8	98.9	98.9	99.2

Table 5-7. Carbon Conversion for FCM Test (continued)

Carbon Conversion													
TESTS	M40	M41	M40	M50	M51	M52	M53	M54	M55	M56	M57	M58	M53 AVERAGE
IMPUTS													
COAL FLOW (G/HR)	2507	2473	2469	2493	2515	2521	2497	2480	2487	2512	2525	2483	2480
PURATION (HRS.)	151	141	179	256	50	191	151	137	162	140	211	113	113
CARBON IN COAL (%)	47.84	47.84	46.86	47.84	47.84	47.84	47.84	47.84	47.84	47.84	47.84	46.66	47.84
1. CARBON IN (%)	3010	2700	3452	5000	1003	3773	3086	2987	3107	3143	4240	3472	2313
TOTAL IMPUT (%)				5000	1003	3773	3086	2987	3107	3143	4240		2313
LOSSES													
SLAG RECOVERED	2.28	2.28	1.84	2.28	2.28	1.73	2.28	2.28	2.28	0.93	1736	2.28	2.28
CARBON IN SLAG (%)													
1. SLAG CARBON LOST (%)													
FLYASH RECOVERED	150	200	220	270	80	300	230	120	360	170	350	500	230
FLYASH CARBON (%)	0.74	0.74	0.71	0.74	0.74	0.82	0.74	0.74	0.74	0.74	0.74	0.74	0.74
2. FLYASH CARBON LOST (%)	1	2	2	2	1	2	2	1	3	1	3	2	3
TOTAL LOSSES (%)				51	10	33	28	29	30	9	42		69
(1-LOSSES/IMPUT)*100 (%)				99.9	99.9	99.1	99.1	99.9	99.1	99.7	99.0		98.9

Figure 5-3. Carbon Losses to the Slag and Flyash for the FCM Performance Coal Tests

Figure 5-4. Effect of Coal Grind on Slag Carbon Content

Table 5-8. Carbon Conversion for Two Bull Ridge Tests

Carbon Conversion													
TESTS	TBR1	TBR2	TBR3	TBR4	TBR5	TBR6	TBR7	TBR8	TBR9	TBR10	TBR11	TBR12	AVERAGE
INPUTS													
COAL FLOW (L/HR)	1730	2710	3455	3154	3140	3243	3172	3157	3204	2539	2417	2415	2063
BURNATION (RTS.)	34	112	107	88	40	32	76	75	35	67	65	70	830
CARBON IN COAL (%)	43.5	43.5	43.5	43.5	43.5	43.5	43.5	43.5	43.5	43.5	43.5	43.5	43.5
1. CARBON IN (%)	429	2207	2600	2012	1115	1352	1740	1717	813	1233	1400	1226	17422
TOTAL INPUT (%)					1115	1352	1740	1717	813	1233	1400	1226	10004
LOSSES													
SLAG RECOVERED					405	304	705	593	402	593	650	767	4569
CARBON IN SLAG (%)	2.76	2.76	0.51	2.06	3.05	2.76	1.02	4.71	2.76	4.09	3.29	0.81	2.76
1. SLAG CARBON LOST (%)					19	8	14	28	11	28	21	6	137
FLYASH RECOVERED		274	600	430	210	130	200	330	170	200	240	170	2954
FLYASH CARBON (%)	0.79	0.79	0.52	0.76	0.92	0.70	0.20	0.40	0.70	1.04	1.20	1.10	0.79
2. FLYASH CARBON LOST (%)		2	3	3	2	1	0	1	1	2	3	2	22
TOTAL LOSSES (%)					21	0	14	29	12	31	24	0	160
(1-LOSSES/INPUT)*100 (%)					98.1	98.7	98.2	98.3	98.5	97.5	98.4	98.3	98.5

Figure 5-5. Carbon Losses to the slag and to the Flyash for the Two Bull Ridge Coal Tests

- Carbon losses are expected to be lower in the Healy system because the combustion air preheat will be higher, the size and hence residence time will be longer and the system will generally run at higher load. All of these will improve combustion performance.

Slagging Characteristics

A drawing of the interior of the combustor is shown in Figure 5-6 as viewed post test by the test conductor. Some build up of slag was observed in the tap, however, slag flowed out of the slag tap in every performance coal test. Ash accumulations were observed in the head end which were removed after every 6 to 8 tests. This material appeared porous and sintered rather than molten. These accumulations were reduced by feeding more coal to the precombustor to increase the gas temperature in the head end. Downstream of the air inlet from the precombustor, the slag coating on the combustor walls was shiny and uniformly covered the walls, indicating higher temperatures and molten slag flow downstream of the air inlet. Conditions improved when the main combustor injector was moved inward by 4 inches after test No. H41.

Slag tapping was also achieved with the TBR coal which had a higher T_{250} than the performance coal. Ash accumulations occurred in the head end with this coal as well as with the performance coal. In early tests on the TBR coal, the slag tap plugged, but once the proper operating conditions were determined, the slag tap remained open for the rest of the tests. Slag accumulation was observed in the slag recovery section after some tests. This did not restrict the testing, but indicated that obtaining the proper conditions to make the slag flow was more difficult with the TBR coal than the performance coal. Limestone was mixed with the main combustor coal during the last two TBR tests in the series to act as a fluxing agent. Since ash accumulations had already formed in the combustor prior to fluxing, the net effect of the limestone could not be determined within the few hours of testing.

Neither slag nor ash accumulation is expected to occur in the Healy combustor because that system will operate under conditions more suitable for the Healy coals than the Cleveland system could offer. The Cleveland system was limited by the low air preheat, the reduced load, and the small diameter of the combustor. At Healy, slag surface temperatures will be higher than at Cleveland for the following reasons:

- The air preheat will be 200 to 300°F higher
- The nominal operating load will be the design load rather than 40% of the design load

Figure 5-6. Operator's Drawing of Slag Accumulations in the Combustor During the Healy Performance Coal Test Burn

- The Healy combustor diameter will be almost three times larger, thus increasing the optical length. As optical length increases, more particles are available for radiation to the slag surface, thus increasing the heat flux available.
- Fluxing with limestone can be used to reduce the T_{250} of the slag. This should help prevent slag and/or ash accumulations as long as flux is introduced from the start with the coal. Fluxing after accumulations had formed did not cause any problems, however, little influence upon reducing the slag thickness was noted during the few hours of operation in which fluxing was used.

In conclusion:

- Slag tapping was successfully demonstrated for both the Performance blend and the Two Bull Ridge coal.
- Although ash accumulations were observed in the head end of the combustor for both performance and TBR coals, these accumulations are not expected to occur at Healy due to the higher air preheat, higher load operation, and longer optical length.

Slag Recovery

Slag recovery was determined for the Healy performance and TBR coal tests from which slag data was available. The equation used to determine the slag recovery is:

$$\text{Slag recovery} = \frac{(\text{slag wt} \text{ content} / 100) * (1 - \text{slag ash SO}_3 \text{ content} / 100)}{((\text{coal wt} \text{ content} / 100) * (1 - \text{coal ash SO}_3 \text{ content} / 100))} * 100$$

The sulfur as SO₃ is removed from the calculation because sulfur is released as a gas in the combustor zone and is not recoverable in the slag. This is clearly exhibited in the analyses of Tables 5-1 and 5-6.

Table 5-9 gives the inputs and results of the slag recovery calculations for the performance coal and TBR coal tests. Comments are given for the tests where the slag recovery could not be calculated. Figure 5-7 shows slag recovery where available for the performance coal tests along with combustor operating conditions. For the performance coal parametric tests, slag recovery ranged from 62 to 97%. The FCM tests ranged in slag recovery from 62 to 101%. Slag recovery values greater than 100% are possible due to random fluctuations in

Table 5-9. Slag Recovery Results for Healy Testing

Slag Recovery for Healy Tests

	COAL RUN TIME	COAL FLOWRATE	ASH CONTENT	SO3 CONTENT	SLAG WEIGHT	SLAG ASH	SLAG SO3	SLAG RECOVERY	COMMENTS
	(MIN)	(#/HR)	(%)	(%)	(LBS)	(%)	(%)	(%)	
HEALY PERFORMANCE COAL									
PARAMETRIC TESTS									
N13									SLAG WEIGHT NOT RECORDED
N13-1	96	2460	22.22	2.87	789	84.81	0.83	70	
N13-2	120	2526	22.22	3.19	1201	84.59	0.89	94	
N14	111	3113	20.14	3.17	1144	85.28	0.84	87	
N14-1	182	3088	17.22	3.27	865	82.81	1.15	82	
N14-2									SLAG NOT WEIGHED
N16	78	3720	18.14	2.81	985	83.74	0.12	97	SLAG NOT WEIGHED
N17	88	3767	21.45	2.74	887	81.94	0.12	83	
N18	77	3833	20.78	3.45	1017	82.18	0.13	85	
N19									DCS OUT OF ORDER
TOTALS	651	3215	20.78	3.45	6408	82.18	0.13	75	
HEALY PERFORMANCE COAL									
FCM COLLECTION TESTS									
N20									SLAG NOT WEIGHED
N21									SLAG NOT WEIGHED
N22									SLAG NOT WEIGHED
N23	196	2449	26.30	1.86	1804	81.47	0.83	63	COARSE COAL GRIND (51% THRU 200 MESH)
N24	134	2501	20.78	3.45	885	82.18	0.13	45	COARSE COAL GRIND (82% THRU 200 MESH)
N25	183	2483	20.78	3.45	1355	82.18	0.13	82	
N26									TEST ABORTED
N27	142	2491	20.78	3.45	1114	82.18	0.13	77	
N28	163	2494	20.78	3.45	1428	82.18	0.13	86	
N29	141	2506	20.78	3.45	1161	82.18	0.13	81	
N30									SLAG SCALE MALFUNCTION
N31	159	2509	20.78	3.45	1228	82.18	0.13	76	
N32	176	2477	20.78	3.45	1592	82.18	0.13	90	
N33	165	2485	20.78	3.45	1389	82.18	0.13	82	
N34									FIRST TEST IN SERIES - SLAG MAY BE ACCUMULATING
N35									POOR COMBUSTION - WATER LEAK IN HOT SLEEVE
N36	207	2497	20.60	4.21	2013	76.77	0.14	81	
N37									FINAL SLAG WEIGHT NOT RECORDED
N38	169	2487	20.78	3.45	1413	82.18	0.13	83	
N39	133	2525	20.78	3.45	981	82.18	0.13	72	
N40	151	2507	18.23	4.58	1048	84.85	0.83	81	
N41	209	2536	21.76	4.41	2020	71.77	0.17	79	
N42	183	2513	20.78	3.45	1699	82.18	0.13	101	
N43	194	2482	20.78	3.45	1773	82.18	0.13	90	
N44	153	2484	20.78	3.45	1391	82.18	0.13	90	
N45	188	2519	20.39	3.56	1635	85.91	0.07	91	
N46									SLAG NOT COLLECTED COMPLETELY
N47									OPERATOR QUESTIONS WHETHER SLAG WAS COLLECTED

Table 5-9. Slag Recovery Results for Healy Testing (cont.)

Slag Recovery for Healy Tests

	COAL RUN TIME	COAL FLOWRATE	ASH CONTENT	SO ₃ CONTENT	SLAG WEIGHT	SLAG ASH	SLAG SO ₃	SLAG RECOVERY	COMMENTS
	(MIN)	(#/HR)	(%)	(%)	(LBS)	(%)	(%)	(%)	
N48									OPERATOR QUESTIONS WHETHER SLAG WAS COLLECTED
N49									TEST ABORTED
N50									NFT DURING MIDDLE OF TEST
N51	80	2513	20.78	3.45	423	82.18	0.13	83	
N52	191	2521	21.65	2.89	1758	84.71	0.03	88	
N53	151	2497	20.78	3.45	1139	82.18	0.13	74	
N54	137	2480	20.78	3.45	1221	82.18	0.13	89	
N55	182	2467	20.78	3.45	1195	82.18	0.13	73	
N56	149	2512	16.38	3.98	993	90.78	0.20	92	
N57	211	2525	20.78	3.45	1736	82.18	0.13	80	
N58									SLAG NOT COLLECTED
N59									SLAG CARRIED OVER FROM PREVIOUS TEST
N60									SLAG CARRIED OVER FROM PREVIOUS TEST
N61	204	2512	20.78	3.45	2160	82.18	0.13	103	
N62	108	2480	20.78	3.45	1027	82.18	0.13	94	
N63	113	2440	19.93	3.4	1245	76.78	0.22	108	
TOTALS	4480	2495	20.78	3.45	38597	82.18	0.13	85	
TWO HULL RIDGE COAL									
PARAMETRIC TESTS									
TBR1									SLAG WEIGHT NOT RECORDED
TBR2									SLAG TAP PLUGGED
TBR3									SLAG TAP PLUGGED, REMOVED 7400 FROM TAP
TBR4									SLAG TAP PLUGGED
TBR5	49	3140	26.83	4.04	495	71.38	0.12	54	
TBR6	32	3243	27.32	3.16	304	80.26	0.13	40	
TBR7	76	3172	27.14	2.89	765	59.71	0.03	43	
TBR8									SLAG TAP PLUGGED, REMOVED 4750 MOSTLY FROM TAP
TBR9	35	3204	27.32	3.16	402	80.26	0.13	49	
TBR10	67	2539	27.55	2.83	593	38.57	0.34	30	
TBR11									NFT DURING MIDDLE OF TEST
TBR12	70	2415	28.15	3.6	787	68.1	0.06	73	LIMESTONE ADDED WITH COAL AS FLUXING AGENT
TOTALS	329	2952	27.32	3.16	3326	80.26	0.13	47

Slag Recovery for Performance Coal Tests.
Included are Various Test Parameters

Figure 5-7.

the slag/ash layers in the combustor. Errors in the determination process may also be a reason for slag recovery values greater than 100%. This topic will be covered later in this section.

A frequency distribution of slag recovery results for the all the Healy performance coal tests is shown in Figure 5-8. While there is scatter in the results, the distribution shows that the majority of the tests yielded 80 to 90% slag recovery.

Scatter in the slag recovery results for the performance coal parametric tests is consistent with the changing conditions of the parametric tests. Scatter in the results of the FCM collection tests was less pronounced, as would be expected since the tests were performed at similar operating conditions, except for two early tests. For these tests, the slag recovery dropped to near 65% because the coal grind was coarser. The effect of coal grind on slag recovery is shown in Figure 5-9. Slag recovery is observed to drop significantly with the coarser grind.

Figure 5-10 shows the frequency distribution of slag recovery results for the FCM collection tests only. Scatter in the FCM slag recovery is due to errors in the determination of slag recovery and/or changes in performance. Determination errors may be due to test duration or errors in either or both the coal flow measurement and the slag weight. Figure 5-11 shows cumulative slag weight with time during a typical FCM collection test. The figure shows that during the three-hour test, slag weight increased at a uniform rate beginning as soon as the load condition was reached. Thus, the duration of the test, although short, should not introduce significant errors provided that the wall coverage conditions are the same at the beginning and at the end of the test. Errors due to erroneous coal flow measurements can be compensated for by correcting the coal flow to correlate with steam flow to calculate a corrected slag recovery. This was done and the slag recovery results did not change significantly. However, by dividing slag recovery results by solids closure efficiency, which is discussed in the next section, the scatter in the slag recovery results was reduced. Figure 5-12 shows slag recovery corrected by solids closure. The majority of the slag recovery results fall between 86 and 90%, as shown in the frequency distribution for the corrected slag recovery, Figure 5-13. The solids closure correction accounts for errors in both coal flow and slag weight, and indicates that determination, not performance is believed to be main cause for the data scatter.

Figure 5-8. Slag Recovery Frequency for Performance Coal Tests

Figure 5-9. Effect of Coal Grind on Slag Recovery for Healy Performance Coal

Figure 5-10. Slag Recovery Frequency Distribution for FCM Tests Only

Figure 5-11. Slag Weight Measured at Different Times During Healy Test H32

Figure 5-12. Slag Recovery Corrected for Solids Closure - FCM Tests

Figure 5-13. Frequency Distribution for Slag Recovery Corrected for Solids Closure - FCM Tests

The TBR test slag recovery results are shown graphically in Figure 5-14. The TBR results are significantly lower than the performance coal results, ranging from 30 to 73%, with an average of 47%. The slag recovery frequency distribution in Figure 5-15 shows the scatter in the TBR results. Solids closures were also low for the TBR coal, which will be discussed in a later section. By correcting the TBR slag recovery for solids closure efficiency, shown in Figure 5-16, the scatter is reduced, as shown in Figure 5-17. However, even the corrected results are low, with the highest frequency at 51 to 60%. These results are consistent with the fact that the TBR coal has a higher T₂₅₀ than the performance coal and that the observed combustion performance was not quite as good. Improved slag recovery was observed, however, in test TBR12 where limestone was added to the coal to act as a fluxing agent. This helped to lower the high T₂₅₀ value of the slag. Slag recovery for this test was 73% (upper limit in scatter), which is a marked improvement over the other TBR tests. This slag recovery number may be artificially high, however, due to the release of some slag/ash accumulations previously existing in the combustor on the injection of limestone.

In conclusion on slag recovery:

- Slag recovery for the Healy performance coal was excellent, averaging 85% for tests at 20 MMBtu/hr, main combustor equivalence ratio of 1, coal split of 46%, and coal grinds of 70-80% thru 200 mesh.
- Slag recovery values dropped to near 65% for tests with coarser coal grinds (50-60% thru 200 mesh).
- The excellent slag recovery of 85% further corroborates that combustion performance was good with the performance coal.
- Correcting slag recovery by solids closure efficiency yields results with reduced scatter, indicating that the variations in slag recovery are primarily due to errors in slag weight measurements.
- The TBR slag recovery results were lower, as a result of the higher T₂₅₀ and slightly reduced combustion performance.
- These results indicated that the combustion could be run within the limits of the operability window with the performance coal. Combustor running conditions were slightly outside the more restrictive operating window created by the TBR coal. This window will be wider at Healy because of the higher air preheat temperature and

Figure 5-14. Slag Recovery for TBR Tests

Figure 5-15. Slag Recovery Frequency Distribution for TBR Tests

Figure 5-16. TBR Slag Recovery Results Corrected for Solids Closure

Figure 5-17. Slag Recovery Frequency Distribution for TBR Tests Corrected for Solids Closure

larger physical combustor size.

- An option with the TBR coal may be to mix limestone with the coal to act as a fluxing agent. Limestone injections with the coal lowers the high T_{250} value of the slag, which helps to facilitate slag recovery.

Solids Closures

Solids closure efficiency could be determined for the FCM collection tests and the TBR tests whenever both slag and flyash were weighed for these tests. In some of these tests, slag or flyash weights were not available, so the solids closure was not determined.

Solids Closure efficiency was calculated to determine how well the solids input (coal ash and limestone) matched the solids output (slag and flyash). The equation utilized to determine solids closure is:

$$\text{Solids Closure} = \text{Output/Input} * 100$$

$$\text{Output} = (\text{slag wt}) * (\text{slag ash content}/100) * (1 - \text{slag ash SO}_3 \text{ content}/100) + (\text{FCM wt}) * (\text{FCM ash content}/100) * (1 - \text{FCM ash SO}_3 \text{ content}/100)$$

$$\text{Input} = (\text{coal wt} * (\text{coal ash content}/100) * (1 - \text{coal ash SO}_3 \text{ content}/100) + (\text{limestone flow}) * \text{test duration}/60 * ((\text{limestone CaCO}_3 \text{ content}/100) * \text{MW}(\text{CaO})/\text{MW}(\text{CaCO}_3) + (1 - \text{limestone CaCO}_3 \text{ content}/100) * \text{MW}(\text{MgO})/\text{MW}(\text{MgCO}_3)))$$

Sulfur in the form of sulfur trioxide (SO₃) was subtracted from the coal ash, slag, and flyash calculations, since sulfur is released as a gas and not available as a solid material. The solids input from the limestone was assumed to be all calcium oxide (90%) and magnesium oxide (10%).*

The results for the applicable performance coal FCM collection tests are shown in Table 5-10. and plotted in Figure 5-18. Solids closure was found to be excellent, in the range of 74 to 137% with an overall average closure of 97%. The frequency distribution for solid balances is shown in Figure 5-19 and shows that most tests fell within 85 to 105% solids closure.

Solids balances for applicable Two Bull Ridge coal tests have been calculated and are shown in Table 5-11 and plotted in Figure 5-20. Solids closure was found to be poor, in the

* Inclusion of the actual calcination fractions, rather than the 100% value assumed here, changes the results very little.

Table 5-10. Solids Balance for FCM Tests

SOLIDS BALANCE		M22	M23	M24	M25	M27	M28	M29	M30	M31	M32	M33	M34	M35	M36	M37	M38	M39	M40	M41	M42	M43	M44	M45
TESTS																								
INPUTS																								
COAL FLOW (T/HR)		2436	2440	2501	2403	2401	2404	2506	2404	2508	2477	2405	2511	2533	2497	2512	2407	2525	2507	2536	2513	2402	2404	2519
WATER FLOW (GAL/HR)		206	198	134	103	142	163	141	103	159	176	165	164	151	207	165	165	133	151	209	163	194	153	188
WATER IN COAL (%)		20.70	26.3	20.70	20.70	20.70	20.70	20.70	19.32	20.70	20.70	20.70	22.37	20.70	20.6	20.70	20.70	20.70	20.70	21.76	20.70	20.70	20.70	
SO2 IN COAL (%)		3.45	1.06	3.45	3.45	3.45	3.45	3.45	2.74	3.45	3.45	3.45	3.33	3.45	4.21	3.45	3.45	3.45	4.50	4.41	3.45	3.45	3.45	
1. ASH IN (%)		2065	1121	1353	1103	1359	1102	1334	1334	1458	1371	1477	40	49.6	50.4	40	40	1005	1037	1037	1370	1610	1271	
LS FLOW (T/HR)		50	36	30	33	34	36	36	34	34.5	34	36	47.7	40	49.6	50.4	40	40	50.3	40	50	42.5	47	
LS FLOW (G/HR)		90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	
CO2 IN LS (%)		94.7	64.0	37.0	40.5	44.4	54.0	46.7	57.2	58.4	55.0	54.6	71.0	66.7	94.4	76.5	74.5	59.9	69.9	92.3	60.0	80.2	59.8	
2. LS ASH IN (%)																								
TOTAL INPUT (%)		2130	1150	1403	1403	1227	1413	1228	1304	1304	1513	1426			1794	1400	1400	1103	1167	1936	1430	1699	1331	1633
OUTPUTS																								
SLAG RECOVERED		1604	805	1355	1355	1116	1420	1161		1220	1592	1389			2013	1413	1413	981	1040	2020	1690	1773	1391	1635
SLAG ASH (%)		82.10	81.47	82.10	82.10	82.10	82.10	82.10	87.2	82.10	82.10	82.10	70.17	82.10	76.77	82.10	82.10	82.10	84.05	71.77	82.10	82.10	82.10	
SLAG SO2 (%)		0.13	0.03	0.13	0.13	0.13	0.13	0.13	0.03	0.13	0.13	0.13	0.15	0.13	0.14	0.13	0.13	0.13	0.03	0.17	0.13	0.13	0.13	
1. SLAG OUT (%)		1306	726	1112	1112	916	1172	953		1000	1387	1124			1503	1100	1100	805	809	1407	1307	1455	1142	
FLY ASH RECOVERED		340	270	270	200	150	220	170	310	100	210	330	210	230	290	170	160	100	90	97.27	230	250	200	
FLY ASH ASH (%)		90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	
FLY ASH SO2 (%)		1.70	1.81	1.70	1.70	1.70	1.70	1.70	1.05	1.70	1.70	1.70	1.20	1.70	1.67	1.70	1.70	1.70	1.7	1.76	1.70	1.70	1.70	
2. FLY ASH OUT (%)		327	263	260	260	164	212	164	204	173	202	310	205	221	281	164	154	173	281	363	221	241	102	
TOTAL OUTPUT (%)		1509	905	1302	1302	1059	1304	1116		1101	1500	1441			1025	1314	1314	910	1170	1810	1600	1696	1334	1712
OUTPUT/INPUT (%)		74	85	90	90	86	90	91		85	100	101			102	89	89	83	100	94	113	100	100	105

Table 5-10. Solids Balance for FCM Tests (continued)

SOLIDS BALANCE													
TESTS	M46	M47	M48	M50	M51	M52	M53	M54	M55	M56	M57	M58	AVERAGE
INPUTS													
COAL FLOW (T/HR)	2597	2473	2469	2493	2515	2521	2495.5	2459.5	2467	2511.5	2525	2469	2469
BOURNATION (RTS.)	151	141	119	256	50	191	151	137	162	149	211	175	113
ASH IN COAL (2)	20.78	20.78	21.19	20.78	20.78	21.65	20.78	20.78	20.78	16.38	20.78	20.78	20.78
SO3 IN COAL (2)	3.45	3.45	3.36	3.45	3.45	2.89	3.45	3.45	3.45	3.36	3.45	3.45	3.45
1. ASH IN (1)				2134	420	1687	1261	1127	1336	981	1782	1714	895
LS FLOW (T/HR)	51	52	51	50	52.5	47	51.6	51	48.9	40	47.6	48.5	50
CACOD IN LS (2)	90	90	90	90	90	90	90	90	90	90	90	90	90
2. LS ASH IN (1)	70.8	67.4	64.8	117.7	24.1	82.6	71.7	64.3	72.9	65.8	82.4	78.1	92.0
TOTAL INPUT (2)				2252	445	1770	1332	1191	1409	1047	1874	1807	931
OUTPUTS													
SLAG RECOVERED				2153	423	1159	1139	1221	1195	993	1736		
SLAG ASH (2)	82.10	82.10	85.82	82.10	82.10	84.71	82.10	82.10	82.10	90.78	82.10	82.10	82.10
SLAG SO3 (2)	0.13	0.13	0.03	0.13	0.13	0.03	0.13	0.13	0.13	0.13	0.13	0.13	0.13
1. SLAG OUT (1)				1167	347	1409	935	1002	981	908	1425	1773	943
FLY ASH RECOVERED	158	280	220	270	80	300	230	120	300	170	350	50	500
FLY ASH ASH (2)	90	90	88.17	90	90	97.87	90	90	90	97.77	90	90	90
FLY ASH SO3 (2)	1.79	1.79	2.06	1.79	1.79	1.47	1.79	1.79	1.79	1.94	1.79	1.79	1.79
2. FLY ASH OUT (1)	144	250	212	280	71	288	220	115	346	163	337	40	400
TOTAL OUTPUT (1)				2027	424	1777	1384	1110	1327	1063	1762	2052	1251
OUTPUT/INPUT (2)				90	95	100	87	94	94	102	94	114	132
													97

Figure 5-18. Solids Balance - FCM Tests on Performance Coal

Figure 5-19. Solids Balance Frequency Distribution for FCM Tests

Table 5-11. Solids Balance for TBR Tests

SOLIDS BALANCE													
TESTS	TBR1	TBR2	TBR3	TBR4	TBR5	TBR6	TBR7	TBR8	TBR9	TBR10	TBR11	TBR12	AVERAGE
INPUTS													
COAL FLOW (T/HR)	1739	2710	3455	3154	3140	3243	3172	3157	3204	2539	2417	2415	2653
WATER FLOW (T/HR)	34	112	107	88	49	32	75	75	35	67	85	70	839
ASH IN COAL (S)	27.32	27.32	28.03	28.35	28.93	27.32	27.14	28.82	27.32	27.55	26.46	26.35	27.32
SO3 IN COAL (S)	3.16	3.16	2.25	3.46	4.06	3.16	2.99	3.3	3.16	2.83	2.9	3.6	3.16
1. ASH IN (S)					600	450	1050	1023	494	759	807	710	8850
LS FLOW (T/HR)	40										82	165	90
CO3 IN LS (S)	90	90	90	90	90	90	90	90	90	90	90	90	90
2. LS ASH IN (S)	14	0	0	0	0	0	0	0	0	0	59	90	110
TOTAL INPUT (S)					600	450	1050	1023	494	759	916	808	6206
OUTPUTS													
SLAG RECOVERED					405	304	765	593	402	593	650	767	4500
SLAG ASH (S)	60.36	60.36	63.27	51.13	71.50	62.26	59.71	63.96	60.26	38.57	45.75	58.1	38.26
SLAG SO3 (S)	0.13	0.13	0.1	0.1	0.12	0.13	0.83	0.80	0.13	0.34	0.21	0.06	0.13
1. SLAG OUT (S)					354	103	457	379	242	228	297	522	2661
FLY ASH RECOVERED		274	600	430	210	130	200	330	170	200	240	170	2954
FLY ASH ASH (S)	97.70	97.70	98.04	97.99	96.92	97.70	98.34	97.93	97.70	98.10	97.99	97.74	97.70
FLY ASH SO3 (S)	0.83	0.83	1.35	0.96	1	0.83	0.24	0.86	0.83	0.64	0.76	0.96	0.83
2. FLY ASH OUT (S)		265	580	417	200	126	196	321	165	105	233	165	2004
TOTAL OUTPUT (S)					554	309	653	700	407	423	530	687	4252
OUTPUT/INPUT (S)					84	68	62	68	82	56	56	85	69

Figure 5-20. Solids Balance for TBR Tests

range of 56% to 85%, with an overall average of 69%. The solids closure was poor for these TBR coal tests primarily because of significant slag accumulation in the furnace section. The previous tests with the performance coal showed little slag accumulation in the furnace section. The reason why the performance coal had little slag accumulation in the furnace section is thought to be due to good combustion and an acceptable match between the active operating window and the performance coal. The combustion performance for the TBR coal tests was not quite as good as the Healy performance coal, and the higher T_{250} resulted in poorer slagging and more carryover into the furnace.

In conclusion on solids closure:

- FCM collection tests with the performance coal showed good solids closure.
- TBR tests showed poor solids closure. This was due to significant slag accumulation in the furnace section.

Calcium Balance

Calcium balances for FCM tests on performance coal have been determined with the results given in Table 5-12, and plotted in Figure 5-21. The calcium balances were found to range from 63% to 124% with an average of 78%. The calcium closure is thought to be reasonable in light of the large errors associated with the relatively small amounts of calcium present in the overall system (approximately 2% of entering solids).

Cooling Loads

Cooling load is the percentage of the higher heating value of the coal fired which is transferred to the combustor cooling water. Cooling load values were determined for the performance coal and Two Bull Ridge coal tests, and are plotted as a function of load in Figure 5-22. Also plotted in Figure 5-22 are cooling load results for Ohio coal tests performed previously under similar conditions as the Healy coal tests. The cooling loads for the Healy tests are observed to be much lower than for the Ohio coal tests. For a load of 20 MMBtu/hr, the cooling load for the Healy tests was approximately 10%, where as for the Ohio coal tests, the cooling load was 20-25%. The lower cooling loads for the Healy coal is due to the higher slag T_{250} values. The cooling loads for the Two Bull Ridge coal tests are slightly lower than those of the performance coal, consistent with the higher slag T_{250} values for the TBR coal above the performance coal.

Table 5-12. Calcium Balance for the FCM Tests on Performance Coal

Calcium Balance	Limestone deratifica 100 %															
	(x of coal deratifica)															
TESTS	M22	M23	M24	M25	M26	M27	M28	M29	M30	M31	M32	M33	M34	M35	M36	M37
INPUTS																
COAL FLOW (G/HR)	2436	2449	2501	2483	2491	2494	2506	2494	2494	2509	2477	2485	2511	2533	2497	2512
BURNATION (MINS.)	206	196	134	183	142	163	141	163	20.78	20.78	20.78	20.78	22.37	20.78	20.78	20.78
ASH IN COAL (%)	20.78	25.3	20.78	20.78	20.78	20.78	20.78	20.78	19.32	20.78	20.78	20.78	22.37	20.78	20.78	20.78
CaO IN ASH (%)	9.89	7.16	9.89	9.89	9.89	9.89	9.89	9.89	10.36	9.89	9.89	9.89	9.13	9.89	9.89	9.89
1. CALCULUM IN (%)	123	100	82	99	87	99	86	109	109	98	101	100	100	94	128	101
LS FLOW (G/HR)	50	36	30	33	34	35	36	34	34	34.5	34	36	47.7	40	45.6	50.4
CaCO3 IN LS (%)	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90
2. LS CALCULUM IN (%)	62	42	24	32	29	35	30	37	37	33	36	36	47	43	62	50
TOTAL INPUT (%)		150	106	131	118	135	117			131	143	136			180	192
OUTPUTS																
SLAG RECOVERED	1684	885	1355	1114	1429	1429	1161			1228	1592	1359			2013	1413
ASH IN SLAG (%)	82.10	81.47	82.10	82.10	82.10	82.10	82.10	81.2	81.2	82.10	82.10	82.10	78.17	82.10	76.77	82.10
CaO IN SLAG (%)	9.28	9.28	9.28	9.28	9.28	9.28	9.28	8.92	8.92	9.28	9.28	9.28	8.01	9.28	8.77	9.28
1. SLAG CALCULUM OUT (%)		75	46	74	61	70	63	310	310	180	210	75	210	230	97	170
FLYASH RECOVERED	340	278	270	200	150	220	170	96.79	96.79	90	90	90	90	90	90	90
FLYASH ASH (%)	90	90.29	90	90	90	90	90	90	90	90	90	90	90	90	90	90
CaO IN FLYASH (%)	12.97	12.97	12.97	12.97	12.97	12.97	12.97	12.97	12.97	12.97	12.97	12.97	12.97	12.97	12.97	12.97
2. FLYASH CALCULUM OUT (%)	43	32	34	36	19	20	22	36	36	23	27	42	27	29	40	22
TOTAL OUTPUT (%)		107	83	109	80	106	85			90	113	117			145	97
OUTPUT/INPUT (%)		71	78	83	69	78	73			69	80	86			76	64

Table 5-12. Calcium Balance for FCM Tests (continued)

Calcium Balance		M46	M47	M48	M50	M51	M52	M53	M54	M55	M56	M57	M58	M59	M60	M61	M62	M63 AVERAGE
TESTS																		
INPUTS																		
COAL FLOW (T/HR)		2507	2473	2469	2493	2515	2521	2497	2469	2467	2511	2525	2488	2483	2454	2512	2489	2488
WATER FLOW (GPM)		151	141	119	255	58	191	151	137	162	149	211	175	113	179	284	100	113
ASH IN COAL (G)		20.70	20.70	21.10	20.70	20.70	21.65	20.70	20.70	20.70	16.30	20.70	20.70	21.23	20.70	20.70	19.83	20.70
CaO IN ASH (G)		9.89	9.89	9.23	9.89	9.89	9.27	9.89	9.89	9.89	12.01	9.89	9.89	10.05	9.89	9.89	10.22	9.89
1. CALCIUM IN (G)		92	85	102	156	31	115	92	82	98	80	130	107	72	102	125	66	67
LS FLOW (T/HR)		51	52	51	50	52.5	47	51.5	51	49.9	48	47.6	48.5	50	50.5	50	48.5	45
CaO IN LS (G)		90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90	90
2. LS CALCIUM IN (G)		46	44	55	77	16	54	47	42	40	43	60	51	34	52	61	32	33
TOTAL INPUT (G)					233	47	169	139	124	145	131	191				167	90	4135
OUTPUTS																		
SLAG RECOVERED					2153	423	1159	1139	1221	1195	993	1136				2160	1027	1245
ASH IN SLAG (G)		82.10	82.10	85.82	82.10	82.10	84.71	82.10	82.10	82.10	90.70	82.10	82.10	82.61	82.10	82.10	76.70	82.10
CaO IN SLAG (G)		9.20	9.20	9.37	9.20	9.20	9.03	9.20	9.20	9.20	11.13	9.20	9.20	10.23	9.20	9.20	11.11	9.20
1. SLAG CALCIUM OUT (G)					117	23	96	62	67	65	72	95				110	56	76
FLYASH RECOVERED		150	260	220	210	80	300	230	120	360	170	350	50	500	290	290	424	320
FLYASH ASH (G)		90	90	90.17	90	90	97.87	90	90	90	91.77	90	90	90.19	90	90	97.54	90
Ca IN FLYASH (G)		12.97	12.97	12	12.97	12.97	15.06	12.97	12.97	12.97	14.92	12.97	12.97	12.15	12.97	12.97	14.06	12.97
2. FLYASH CALCIUM OUT (G)		10	33	26	34	10	44	30	15	46	24	44		65		37	54	40
TOTAL OUTPUT (G)					152	33	140	92	82	111	95	139				155	110	124
OUTPUT/INPUT (G)					65	71	83	66	66	76	73	73				93	113	126

Figure 5-21. Calcium Balance for the Performance Coal FCM Tests

Figure 5-22. Effect of Load on Combustor Cooling Load for Different Coals During Healy Testing

Combustor heat fluxes making up the cooling loads observed above, are shown in Figure 5-23 for the performance coal, the TBR coal, and the Ohio coal, for similar loads and equivalence ratios. The difference in heat fluxes between the Ohio coal and the Healy coal tests in the slag recovery section of the combustor is primarily due to a difference in the slag T_{250} values. This is because the slag layers in the slag recovery section were observed to be melted, where the surface of the slag must have reached the T_{250} value. Heat fluxes in the slag recovery section for the Healy coal tests were roughly half the heat flux values for the Ohio coal tests. The difference in heat fluxes between the Ohio coal and Healy coal tests in the head end section of the combustor is due to more than just the difference in the slag T_{250} values. In this region, large ash accumulations were predominant for the Healy tests causing the heat fluxes to drop to values as low as 1 Btu/s/ft². For the Healy combustor, ash accumulations are not expected because of higher air preheat temperatures and higher loadings. Heat fluxes for the head end region are thus expected to go up, but not as high as the Ohio coal, because of the higher slag T_{250} values for the Healy coal.

Calculations have been performed to show the relationship between heat flux, slag thickness, and gas temperature for the performance coal. The results of these calculations are shown in Figure 5-24. For the head end region, with heat fluxes of 1 Btu/s/ft², calculated gas temperatures are observed to be only slightly higher than the T_{250} value of the slag. Calculated slag thicknesses are thus large, 3-4 inches, and potentially unstable if the gas temperature were to drop nearer the slag T_{250} value. This is consistent with the ash accumulations observed in the head end for the performance coal. For the exit section of the main combustor, heat fluxes were approximately 5 Btu/s/ft². Calculated exit temperatures are observed to be much higher than the slag T_{250} value. This is assuming that no ash is in the gas, which is reasonable in this case for the performance coal which has good slag recovery. Calculated slag thicknesses are thus thinner and more stable, consistent with post test observations. To give more credence to the calculated results, the gas temperatures were compared against equilibrium gas temperatures determined from a thermal chemical equilibrium program, based upon stoichiometric conditions for the head end and exit regions. The equilibrium temperature results are shown in Figure 5-25, and are observed to agree well with the calculated temperatures in Figure 5-24.

Figure 5-23. Combustor Heat Fluxes for Different Coals During Healy Testing

Figure 5-24. Calculated Relationship Between Heat Flux, Slag Thickness, and Gas Temperature for Performance Coal.

Figure 5-25. Equilibrium Gas Temperatures as a Function of Combustor Equivalence Ratio for Performance Coal

In conclusion on cooling loads:

- Cooling loads and heat fluxes were observed to be lower for the Healy tests compared to previous Cleveland experience with the Ohio coal.
- The difference in exit section heat fluxes between the Healy coal and the Ohio coal is believed to be primarily due to a difference in the slag T_{250} values. This is because the slag layers were observed to be completely melted and glassy, and must have reached the slag T_{250} values. The lower heat flux for the Healy coal tests is attributed to a smaller temperature difference between the combustion gas and the higher liquid surface temperature for the slag (higher T_{250}). This result assumes that the convection-radiative heat transfer coefficient (between combustion gas and liquid slag surface) is the same for both coal types.
- The difference in head end region heat fluxes between the Healy coal and the Ohio coal is due to more than just a difference in slag T_{250} values. This is because of the large ash accumulations observed post test for the Healy coals. These accumulations created a large resistance to conduction between the slag-gas surface and the combustor wall.
- Slag accumulations are not expected to occur in the Healy combustor due to higher air preheat temperatures and higher loadings. Heat fluxes are expected to go up, but not as high as the Ohio coal tests due again to the higher slag T_{250} values of the Healy coals.

5.4.4 Furnace and Emissions

Furnace Temperatures

Temperatures were measured in the furnace during selected performance coal parametric tests using a Babcock & Wilcox high velocity thermocouple (HVT) probe. The tests for which these measurements were made were H13, H13-1, H14, H14-1, H16, H17, and H18. Traverses were made from two locations, both on a plane about 16 inches in front of the back wall of the furnace.

Figure 5-26 shows the measurement points. Access doors to the furnace were used for probe insertion. The upper measurements were taken on a diagonal traverse into the furnace. The location used to indicate furnace exit temperature was D-2. The lower measurements were taken on a horizontal traverse across the length of the furnace at a level just above the plane of the combustor exit.

Figure 5-26. HVT Probe Test Locations (High Velocity Thermocouple)

The HVT furnace temperature measurements are given by test and measurement point in Table 5-13. The furnace exit temperature ranged from 1900 to 2180°F, depending on combustor load, as shown in Figure 5-27. Temperatures from an entire traverse for two tests (H14 & H14-1) are shown in Figure 5-28 for the diagonal traverse and in Figure 5-29 for the horizontal traverse.

NOx Emissions

Nitrogen oxide (NOx) emissions were measured in the stack using a Lear-Siegler in-situ monitor for SOx and NOx emissions. Figure 5-30 shows the NOx emissions corrected to 3% oxygen in the stack for all Healy performance coal and TBR coal tests. The figure gives the NOx levels in chronological order. NOx emissions ranged from a low of 130 ppm to a high of 340 ppm, with an average value of 183 ppm for the performance coal and 232 ppm for the TBR coal. NO_x levels can be determined in lbs/MMBtu using equation 20 in Appendix C. These values are, on the average, 0.271 lbs/MMBtu for the performance coal, and 0.348 lbs/MMBtu for the TBR coal.

Figure 5-31 shows that NOx emissions are a function of stack oxygen. NOx levels increased as stack oxygen increased as expected. The excess oxygen, however, could not be controlled to lower levels because of the large amount of intrusion air in the boiler. NOx emissions are also a function of combustor load, as shown in Figure 5-32, which shows that as load increases, NOx emissions increase. This is consistent with higher temperatures at higher loads.

While NOx emissions vary as oxygen and load vary, NOx emissions are not a strong function of combustor equivalence ratio, as shown in Figure 5-33. This suggests that the combustor can be operated for optimum slagging conditions without significantly compromising NOx emissions.

In conclusion on NOx Emissions:

- Low NOx emission levels were successfully demonstrated in concert with excellent combustion and slagging characteristics.
- NOx emission trend with excess O₂ indicates the potential for further reductions NOx emissions by better control of furnace conditions as will be available at Healy.
- NOx emissions appear to be mildly dependent on combustor stoichiometry thus providing operating flexibility.

Table 5-13. Furnace Temperature Readings Using the High Velocity Thermocouple (HVT) Probe

HORIZONTAL LOCATION	TEMPERATURES (DEGREES F)	
	H13-1	H13-2
L1	2264	2289
L2	2250	2210
L3	2264	2238
L4	2305	2256
L5	2340	2265
L6	2271	2246
L7	2220	2215
L8	2175	2186
L9	2146	2156
L10	2155	2153

DIAGONAL LOCATION	TEMPERATURES (DEGREES F)				
	H14	H14-1	H16	H17	H18
D1	1821	1830	1989	2132	*
D2	1892	1874	2013	2126	2167
D3	1915	1856	2023	*	2170
D4	1957	1856	1947	*	2119
D5	1991	1909	1910	*	2049
D6	2029	1968	1961	*	*
D7	2047	2008	1997	*	*
D8	2078	2050	2024	*	*
D9	2121	2129	2053	*	*
D10	2192	2224	*	*	*
D10+1	*	2099	*	*	*

Figure 5-27. Temperatures Measured by HVT Probe Near Furnace Exit (Loc. D2) Healy Performance Coal

Figure 5-28. Temperatures Measured by HVT Probe Along Diagonal Backwall Location - Healy Performance Coal

Figure 5-29. Temperatures Measured by HVT Probe Along Horizontal Backwall Location - Healy Performance Coal

Figure 5-30. Average NOx Values During Healy Testing

Figure 5-31. Effect of Stack Oxygen on NOx Formation

Figure 5-32. Effect of Load on NOx Formations

Figure 5-33. Effect of Main Combustor Equivalence Ratio on NOx Formation

Calcination

Limestone sorbent injection into the TRW coal combustion system captures sulfur dioxide from the gas and provides a flash-calcined material (FCM) for use in a back-end sulfur removal system. The level of calcination, or the percentage of calcium carbonate in the limestone which is calcined to CaO, is an important characteristic of the FCM.

The level of calcination was calculated using the following equation

$$\text{calcination} = \frac{[\text{CaO}]/56 + [\text{CaSO}_4]/136}{[\text{CaO}]/56 + [\text{CaSO}_4]/136 + [\text{CaCO}_3]/100} * 100$$

where [CaO], [CaSO₄], and [CaCO₃] are the calcium oxide, calcium sulfate, and calcium carbonate weight percents, respectively, in the FCM after eliminating all contributions from the coal. Raw data from NIRO and their method of determination are presented in Appendix E.

The results are plotted in Figure 5-34 for available FCM tests with the performance coal. The level of calcination was observed to be moderate at 75% for test H22, but then decreased, reaching a plateau at a much lower value of 50% after test H25. For tests after H33, the level of calcination was observed to increase significantly to a level of 80 to 90%.

The variation in calcination trend appears to follow the limestone flowrate shown in Figure 5-35 fairly closely. The limestone flowrate was increased to counter the unexpectedly low levels of calcination previously achieved. As the limestone flow decreased as between tests H22 to H25, the calcination level also decreased. In addition, as the limestone flow increased as after test H33, the level of calcination also increased. The effect of limestone flowrate on calcination may be due to improved penetration and mixing of the limestone with the combustion gases.

Another factor which may have affected limestone mixing and calcination may be the slag buildup in the throat section of the secondary burner where the limestone is injected. Slag build up in the throat section is near the limestone stream and may influence contact and mixing with the combustion gases. This in turn lowers calcination, since calcination is dependent upon the temperatures in the combustion gases. Slag build up in the throat section is observed by an increase in the secondary burner throat pressures.

Figure 5-34. FCM Calcination Levels - Healy Performance Coal

Figure 5-35. Variation in Limestone Flowrate During FCM Testing

The average secondary burner throat pressures for the FCM tests are shown in Figure 5-36. The secondary burner throat pressure for test H33 is observed to be the highest in Figure 5-36 which is consistent with the significant slag build up observed post test. Furthermore, calcination for this test was observed to be the lowest at 30%, consistent with poor contact and mixing of the limestone stream with the combustion gases.

Another possible reason for increased calcination could be due to a finer limestone size distribution. This may be true even though the limestone particle size distribution was not intentionally altered during the test series. This is because the Cantwell limestone was observed to agglomerate as seen by SEM photomicrographs shown in Figure 5-37. The Ohio (Bucyrus) limestone used in earlier Cleveland tests is our previous baseline and shows much less particle agglomeration. Thus, depending upon the level of agglomeration for the Cantwell limestone, the level of calcination may also vary.

In conclusion on calcination:

- The level of calcination was observed to be low during early Healy tests (50%), followed by much better calcination (80-90%) during later Healy tests.
- The level of calcination may be due to a combination of limestone flowrate and slag build up in the throat section of the secondary burner which in turn influences the mixing and contact of limestone with the combustion gases. Limestone agglomeration which affects the particle size distribution may also be a factor in the level of calcination obtained.

SO₂ Emissions and Sulfur Balance

Sulfur dioxide emissions were monitored throughout each test and the measured values are given in the data tables. However, these values are suspect for the following reasons:

- Sulfur mass balances did not close (about 40% of the input sulfur was accounted for in the output streams) while other mass balances closed reasonably well.
- SO₂ emissions measured in tests where no sorbent was injected were lower than the expected value (calculated from sulfur in the coal). Although the Healy coal ash contains calcium, because the slag recovery efficiency was high, very little calcium was available to capture sulfur in the furnace. Thus, low sulfur capture is expected without limestone addition.

Figure 5-36. Variation in Secondary Burner Throat Pressures During FCM Testing

Figure 5-37. SEM Photomicrographs of Ohio Limestone and Cantwell Limestone (Mag. 50X)

- The flue gas contained more moisture than previous experience at Cleveland because the Healy coals contained 9 to 11% moisture as fed compared to 1 to 2% moisture for eastern bituminous coals. Moisture in the flue gas probably allowed a coating to build up on the in-situ probe, which scrubbed SO₂ from the flue gas sample as it passed through the probe to the analyzer. NO_x emissions, measured with the same analyzer, are not affected by moisture, thus the NO_x readings can be expected to be accurate.

The sulfur found in solid streams in the FCM production tests account for about 15% of the input sulfur. Thus, for a Ca/S ratio of 1.6 with the Cantwell limestone, the sulfur capture was 15% using the performance coal.

Toxicity of Solid Material Leachates

For waste management purposes, coal, slag, and flyash samples from a test on the performance coal were collected for toxicity/leachability tests. The Toxicity Characteristics Leaching Procedure (TCLP) was utilized, and performed by the Commercial Testing and Engineering Company. The procedure was limited to the following metals: arsenic, barium, cadmium, chromium, lead, selenium, silver, mercury, copper, nickel, zinc, beryllium, iron, manganese, vanadium, rubidium, strontium, and zirconium. The procedure results are given in Table 5-14.

All results were found to be well below any given TCLP regulatory limit. At this time, there should be no problems with storing or disposing of the coal, slag, or flyash in a land fill.

Table 5-14. Analysis of Metals in the TCLP Leachate

	* Coal	** Slag	** Flyash	MDL	TCLP Regulatory Limit
Paste pH	6.11	9.15	N/A		
Units	MG/L	MG/L	MG/L	MG/L	MG/L
Arsenic	ND	ND	ND	0.5	5.0
Barium	ND	ND	ND	1.0	100.0
Cadmium	ND	ND	ND	0.2	1.0
Chromium	ND	ND	1.6	0.2	5.0
Lead	ND	ND	ND	2.0	5.0
Selenium	ND	ND	ND	0.5	1.0
Silver	ND	ND	ND	0.5	5.0
Mercury	ND	ND	ND	0.1	0.2
Copper	ND	ND	ND	0.5	N/A
Nickel	ND	ND	ND	0.5	N/A
Zinc	ND	ND	0.96	0.5	N/A
Beryllium	ND	ND	ND	0.2	N/A
Iron	ND	2.2	ND	0.5	N/A
Manganese	ND	ND	1.5	0.5	N/A
Vanadium	ND	ND	ND	2.0	N/A
Rubidium	ND	ND	ND	5.0	N/A
Strontium	ND	ND	ND	10.0	N/A
Zirconium	ND	ND	ND	5.0	N/A

MDL - Method Detection Limit

ND - Not Detected at a concentration greater than or equal to the MDL

N/A - Not Available

* - Coal sample taken post test H32.

** - Slag and fly ash samples taken post test H16.

6. SUMMARY OF CONCLUSIONS

- Both the performance coal and the Two Bull Ridge (TBR) coal were handled, pulverized, and fed safely and reliably in the Cleveland test facility coal preparation, feed, and transport systems.
- Light offs of the combustor (over 80 tests) were repeatable, without any indications of problems. Flame scanners were arranged so that no interferences causing a master fuel trip (MFT) occurred.
- Precombustor flame stability was marginal near full load. The precombustor was designed for a maximum coal split of 35%, not the 47% split used for these tests. The Healy precombustor will be designed to accommodate a higher coal split thereby increasing the flame stability and eliminating any need to leave the ignitor on.
- No mechanical operation problems were induced by the use of the Healy coal except for excessive wear of the main combustor pintle tip. This problem can be eliminated by use of a multi-port pintle-less injector system.
- Combustion performance was good to excellent for both coals as measured by carbon losses in the slag and flyash. The performance coal and the TBR coal had 98.9% and 98.5% carbon conversion, respectively. Indicated CO levels at the stack were near 40 ppm for the performance coal and 140 ppm for the TBR coal. This also was indicative of good combustion with a slight preference for the performance coal.
- Slag recovery for the performance coal was excellent at 85%. The slag recovery for the TBR coal was lower at 45%. Slag recovery for the performance coal was better because the slag T_{250} value (2750 F), for the performance coal was within the combustor's operating window. Slag recovery for the TBR coal was lower because the slag T_{250} was higher at 2900 F, which was outside the combustor's operating window. Higher air preheat temperatures and larger combustor size at Healy should accommodate the TBR coal.
- Low NOx emissions were demonstrated for both performance coal and TBR coal. The performance coal tests and the TBR coal tests averaged 188 ppm, and 231 ppm of NOx, respectively. The level of NOx was found to decrease with amounts of excess oxygen in the stack. Operation at excess oxygen levels below 5% was precluded by the high amounts of intrusion air present at the furnace in Cleveland.

- Cooling loads for the performance coal and the TBR coal tests averaged 10% and 7%, respectively. The slightly lower cooling loads for the TBR coal tests is primarily due to its higher T_{250} value. These loads are much lower than in previous Cleveland tests with Ohio coal, which averaged of 20-25%. Cooling loads for the Healy tests were lower than those for the Ohio tests due primarily to higher T_{250} values for the Healy coals.
- Ash accumulations were observed in the head end region of the combustor for the Healy tests. Ash accumulations in the combustor at Healy are not anticipated because of higher air preheat temperatures and larger size. It must also be recognized that operating loads at Cleveland were only 50% of full load. Higher loads will also alleviate the ash accumulation problem.
- The slag tap remained open for all tests except during the transition from performance coal to TBR coal.
- There were also some slag accumulations in the secondary burner throat probably related to the need to continuously operate at reduced load. This is consistent with TRW's prediction for the window of operability for the Cleveland test set up.
- Furnace ash accumulation did not appear significant throughout the performance coal test phase. They increased significantly during the TBR test phase. This is believed to be due to the inability to trap the larger ash particles as slag because of the higher T_{250} of the TBR coal.
- Furnace temperatures were found to vary as expected, depending upon load and location in the furnace. For the exit of the furnace, gas temperatures ranged from 1900 F to 2180 F at loads from 24.9 MMBtu/hr to 30.6 MMBtu/hr.
- Calcination levels in the baghouse catch were found to be low for early Healy tests (50-60%) followed by much better calcination (80-90%) during later Healy performance coal tests. The increase in calcination level was found to correspond to an increase in limestone flowrate. To a lesser degree, slag buildup in the secondary burner throat may also have been a factor. Limestone agglomeration may also be another factor in determining the level of calcination.
- Useage of high moisture content Healy coals, dried to 10-11% moisture, presented little operational problems during the test series. Further testing would be required, however, to determine whether the Healy

combustor could utilize even higher moisture content
Healy coals.

Appendices

Appendix A. Solid Sample Analyses Per Test

Table A1. Healy Performance Coal Tests: Coal Analyses
Table A2. Healy Two Bull Ridge Coal Tests: Coal Analyses
Table A3. Healy Performance Coal Tests: Slag Analyses
Table A4. Healy Two Bull Ridge Coal Tests: Slag Analyses
Table A5. Healy Performance Coal Tests: Flyash Analyses
Table A6. Healy Two Bull Ridge Coal Tests: Flyash Analyses

Appendix B. Test Data Summaries

Table B1. Data Table Nomenclature
Table B2. Healy Performance Coal Parametric Test Data
Pages B5-B14. Healy Performance Coal Parametric Test
Summary Sheets
Table B3. Healy Performance Coal FCM Collection Test Data
Pages B17-B58. Healy FCM Collection Test Summary Sheets
Table B4. Two Bull Ridge Coal Parametric Test Data
Pages B61-B72. Two Bull Ridge Coal Test Summary Sheets

Appendix C. List of Equations

Appendix D. Damper Configurations Per Test

Appendix E. Calcination Data

APPENDIX A. SOLID SAMPLE ANALYSES PER TEST

Table A1. HEALY PERFORMANCE COAL ANALYSES

Test No. Sample No.	HEALY PERFORMANCE COAL TESTS: COAL ANALYSES (AS FIRED)																	
	309-H13-1 1212-16B	400-H13-2 1116-16B	401-H14 1217-16B	402-H14-1 1234-16B	406-H16 1238-16B	407-H17 1244-16B	408-H18 1243-16B	503-H23 1253-16B	510-H30 1280-16B	523-H34 1272-16B								
PROXIMATE																		
% Moisture	9.07	11.11	10.39	12.42	9.97	11.84	12.34	9.57	11.18	11.85								
% Ash	22.22	22.22	20.14	17.22	18.14	21.45	21.16	26.30	19.32	22.37								
% Volatile	39.02	36.20	39.61	40.18	40.28	38.72	38.29	37.18	39.59	38.89								
% Fixed Carbon	29.69	28.47	29.86	30.18	31.61	27.99	28.21	26.95	29.91	26.63								
Btu/lb	7950	7780	8157	8300	8337	7885	7782	7557	8183	7757								
ULTIMATE																		
% Moisture	9.07	11.11	10.39	12.42	9.97	11.84	12.34	9.57	11.18	11.85								
% Carbon	48.23	46.71	48.37	48.86	49.39	46.61	46.21	44.64	48.36	46.04								
% Hydrogen	3.62	3.53	3.72	3.73	3.86	3.51	3.56	3.40	3.69	3.41								
% Nitrogen	0.73	0.75	0.76	0.74	0.76	0.75	0.73	0.68	0.76	0.77								
% Sulfur	0.32	0.34	0.28	0.46	0.31	0.26	0.32	0.24	0.39	0.33								
% Ash	22.22	22.22	20.14	17.22	18.14	21.45	21.16	26.30	19.32	22.37								
% Oxygen	15.81	15.34	16.34	16.57	17.57	15.58	15.68	15.17	16.30	15.23								
ASH ANALYSIS																		
% SiO2	65.17	61.41	61.22	55.92	62.18	60.93	62.41	69.39	59.84	61.12								
% Al2O3	12.74	14.92	14.62	16.31	14.02	15.39	15.26	11.49	14.93	15.11								
% TiO2	0.55	0.63	0.67	0.76	0.68	0.71	0.69	0.55	0.80	0.66								
% Fe2O3	4.92	4.38	4.56	5.09	4.52	4.50	4.42	3.93	4.52	4.46								
% CaO	8.85	8.73	9.78	11.41	10.27	9.04	9.18	7.16	10.36	9.13								
% MgO	1.60	1.69	1.74	1.99	1.76	1.80	1.74	1.39	1.78	1.77								
% K2O	1.67	1.82	1.74	1.70	1.77	1.91	1.86	1.73	1.71	1.81								
% Na2O	0.77	0.77	0.75	0.69	0.71	0.77	0.81	0.83	0.75	0.69								
% SO3	2.57	3.19	3.17	3.27	2.81	2.74	2.67	1.86	2.74	3.53								
% P4O5	0.16	0.17	0.16	0.17	0.16	0.16	0.16	0.14	0.16	0.17								
% SrO	0.10	0.09	0.10	0.12	0.11	0.10	0.10	0.08	0.12	0.09								
% BaO	0.32	0.30	0.19	0.18	0.06	0.19	0.17	0.11	0.00	0.30								
% MnO	0.16	0.15	0.16	0.17	0.16	0.16	0.16	0.16	0.16	0.17								
Undetermined	0.42	1.75	1.14	2.22	0.79	1.60	0.37	1.18	2.13	0.99								
T 250	2744	2749	2683	2581	2667	2714	2732	2900	2652	2722								

Table A1. HEALY PERFORMANCE COAL ANALYSES

HEALY PERFORMANCE COAL TESTS: COAL ANALYSES (MOISTURE FREE BASIS)										
	309-H13-1	400-H13-2	401-H14	402-H14-1	406-H16	407-H17	408-H18	503-H23	510-H30	523-H34
Test No.										
Sample No.	1212-16B	1116-16B	1217-16B	1234-16B	1238-16B	1244-16B	1243-16B	1253-16B	1280-16B	1272-16B
Wt. %										
PROXIMATE										
% Moisture	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
% Ash	24.44	25.00	22.48	19.66	20.15	24.33	24.14	29.08	21.75	25.38
% Volatile	42.91	42.97	44.20	47.02	44.74	43.92	43.68	41.11	44.57	44.12
% Fixed Carbon	32.65	32.03	33.32	34.46	35.11	31.75	32.18	29.80	33.67	30.50
Btu/lb	8743	8752	9103	9477	9260	8944	8877	8357	9213	8800
ULTIMATE										
% Moisture	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
% Carbon	53.04	52.55	53.98	55.79	54.86	52.87	52.72	49.36	54.45	52.23
% Hydrogen	3.98	3.97	4.15	4.26	4.29	3.98	4.06	3.76	4.15	3.87
% Nitrogen	0.80	0.84	0.85	0.84	0.84	0.85	0.83	0.75	0.86	0.87
% Sulfur	0.35	0.38	0.31	0.53	0.34	0.29	0.37	0.27	0.44	0.37
% Ash	24.44	25.00	22.48	19.65	20.15	24.33	24.14	29.08	21.75	25.38
% Oxygen	17.39	17.26	18.23	18.92	19.52	17.67	17.89	16.78	18.35	17.28

Table A1. HEALY PERFORMANCE COAL ANALYSES

Test No.	HEALY PERFORMANCE COAL TESTS: COAL ANALYSES (AS FIRED)												FCM Tests		All Healy
	525-H36	529-H40	530-H41	534-H45	537-H48	541-H52	545-H56	548-H59	552-H63	1383-16B	Average	Perf.			
Sample No.	1296-16B	1306-16B	1309-16B	1321-16B	1337-16B	1358-16B	1365-16B	1370-16B	1383-16B	Average	Perf.	Average			
PROXIMATE															
% Moisture	11.62	11.24	10.58	11.33	11.54	10.85	11.84	12.19	7.99	10.98	11.00				
% Ash	20.60	18.23	21.76	20.39	21.19	21.65	16.38	21.33	19.83	20.78	20.63				
% Volatile	39.59	40.03	37.31	39.76	38.61	39.03	40.53	39.36	41.47	39.28	39.24				
% Fixed Carbon	28.19	30.50	30.35	28.52	28.66	28.47	31.25	27.12	30.71	28.96	29.13				
Btu/lb	8004	8258	8109	8148	7903	8022	8503	7738	8576	8063	8047				
ULTIMATE															
% Moisture	11.62	11.24	10.58	11.33	11.54	10.85	11.84	12.19	7.99	10.98	11.00				
% Carbon	47.60	49.93	48.10	48.16	46.86	47.01	50.38	46.66	50.30	47.84	47.81				
% Hydrogen	3.57	3.69	3.51	3.61	3.58	3.57	3.85	3.56	3.89	3.61	3.62				
% Nitrogen	0.84	0.83	0.82	0.77	0.75	0.88	0.79	0.76	0.78	0.79	0.77				
% Sulfur	0.34	0.36	0.38	0.34	0.33	0.31	0.30	0.32	0.29	0.33	0.33				
% Ash	20.60	18.23	21.76	20.39	21.19	21.65	16.38	21.33	19.83	20.78	20.61				
% Oxygen	15.43	15.72	14.85	15.40	15.75	15.73	16.46	15.18	16.92	15.68	15.86				
ASH ANALYSIS															
% SiO ₂	60.93	58.81	62.14	60.91	63.09	62.97	58.80	61.49	66.48	62.16	61.62				
% Al ₂ O ₃	14.64	15.17	14.89	14.25	14.56	14.98	14.55	15.35	10.98	14.24	14.46				
% TiO ₂	0.62	0.63	0.63	0.62	0.60	0.61	0.62	0.63	0.46	0.62	0.64				
% Fe ₂ O ₃	4.54	4.76	4.37	4.46	4.22	4.31	5.14	4.46	4.23	4.45	4.53				
% CaO	10.09	11.06	8.63	11.44	9.23	9.27	12.01	10.05	10.22	9.89	9.92				
% MgO	1.82	1.90	1.63	1.72	1.67	1.68	2.01	1.85	1.53	1.73	1.78				
% K ₂ O	1.73	1.68	1.82	1.70	1.79	1.78	1.52	1.82	1.48	1.71	1.74				
% Na ₂ O	0.68	0.64	0.70	0.67	0.73	0.69	0.57	0.69	0.56	0.68	0.70				
% SO ₃	4.21	4.58	4.41	3.56	3.36	2.89	3.96	2.84	3.40	3.45	3.31				
% P ₄ O ₅	0.17	0.18	0.17	0.16	0.18	0.21	0.19	0.18	0.15	0.17	0.17				
% SrO	0.10	0.11	0.10	0.11	0.10	0.10	0.12	0.10	0.01	0.10	0.10				
% BaO	0.31	0.31	0.35	0.23	0.31	0.35	0.34	0.37	0.23	0.27	0.23				
% MnO	0.16	0.17	0.16	0.17	0.16	0.16	0.17	0.17	0.17	0.17	0.16				
Undetermined	0.00	0.00	0	0.00	0.00	0.00	0.00	0.00	0.10	0.37	0.64				
T 250	2668	2614	2773	2624	2751	2750	2582	2679	2725	2703	2692				

Table A1. HEALY PERFORMANCE COAL ANALYSES

Test No.	HEALY PERFORMANCE COAL TESTS: COAL ANALYSES (MOISTURE FREE BASIS)										FCM Tests		All Healy Perf.
	525-H36	529-H40	530-H41	534-H45	537-H48	541-H52	545-H56	548-H59	552-H63	1383-16B	H20-H63	Average	
Sample No.	1296-16B	1306-16B	1309-16B	1321-16B	1337-16B	1358-16B	1365-16B	1370-16B					Average
Wt. %													
PROXIMATE													
% Moisture	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
% Ash	23.31	20.54	24.33	23.00	23.95	24.28	18.58	24.29	21.55	23.34	23.34	23.15	23.15
% Volatile	44.80	45.10	41.72	44.84	43.65	43.78	45.97	44.82	45.07	44.13	44.13	44.43	44.43
% Fixed Carbon	31.90	34.36	33.94	32.16	32.40	31.93	35.45	30.88	33.38	32.53	32.53	32.48	32.48
Btu/lb	9056	9304	9068	9189	8934	8998	9645	8812	9321	9058	9058	9042	9042
ULTIMATE													
% Moisture	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
% Carbon	53.86	56.25	53.79	54.31	52.97	52.73	57.15	53.14	54.67	53.74	53.74	53.73	53.73
% Hydrogen	4.04	4.16	3.93	4.07	4.05	4.00	4.37	4.05	4.23	4.06	4.06	4.07	4.07
% Nitrogen	0.95	0.94	0.92	0.87	0.85	0.99	0.90	0.87	0.85	0.88	0.88	0.87	0.87
% Sulfur	0.38	0.41	0.42	0.38	0.37	0.35	0.34	0.36	0.32	0.37	0.37	0.37	0.37
% Ash	23.31	20.54	24.33	23.00	23.95	24.28	18.58	24.29	21.55	23.34	23.34	23.15	23.15
% Oxygen	17.46	17.71	16.61	17.37	17.80	17.64	18.67	17.29	18.39	17.61	17.61	17.82	17.82

Table A2. HEALY TWO BULL RIDGE COAL TESTS: Coal Analyses

Test No.	HEALY TWO BULL RIDGE COAL TESTS: COAL ANALYSES (AS FIRED)																All Healy	
	555-TBR3	556-TBR4	557-TBR5	559-TBR7	560-TBR8	562-TBR10	563-TBR11	564-TBR12	TBR Coal	AVERAGE							Perf.	Average
Sample No.	1391-16B	1396-16B	1399-16B	1405-16B	1408-16B	1414-16B	1417-16B	1419-16B										
PROXIMATE																		
% Moisture	10.68	9.39	9.06	9.39	10.39	10.14	9.94	9.53	9.82	9.82	11.00							
% Ash	29.03	28.35	26.83	27.14	26.82	27.55	26.66	26.15	27.32	27.32	20.61							
% Volatile	37.17	38.05	38.82	38.21	37.86	37.47	38.94	39.05	38.20	38.20	39.53							
% Fixed Carbon	23.12	24.21	25.29	25.26	24.93	24.84	24.46	25.27	24.67	24.67	28.91							
Btu/lb	7059	7204	7498	7416	7381	7293	7447	7566	7358	7358	8047							
ULTIMATE																		
% Moisture	10.68	9.39	9.06	9.39	10.39	10.14	9.94	9.53	9.82	9.82	11.00							
% Carbon	41.62	43.01	44.26	43.96	43.83	42.89	43.99	44.47	43.50	43.50	47.81							
% Hydrogen	3.23	3.40	3.51	3.43	3.42	3.35	3.48	3.48	3.41	3.41	3.62							
% Nitrogen	0.74	0.76	0.76	0.78	0.79	0.79	0.75	0.74	0.76	0.76	0.77							
% Sulfur	0.35	0.36	0.36	0.37	0.36	0.36	0.36	0.37	0.36	0.36	0.33							
% Ash	29.03	28.35	26.83	27.14	26.82	27.55	26.66	26.15	27.32	27.32	20.61							
% Oxygen	14.35	14.73	15.22	14.93	14.39	14.92	14.82	15.26	14.83	14.83	15.86							
ASH ANALYSIS																		
% SiO2	58.41	58.05	57.93	58.45	58.23	58.49	57.33	57.54	58.05	58.05	61.62							
% Al2O3	22.19	20.94	21.89	21.72	21.89	21.66	21.98	21.37	21.71	21.71	14.46							
% TiO2	0.99	0.96	0.92	0.92	0.96	0.95	0.99	0.94	0.95	0.95	0.64							
% Fe2O3	3.59	3.63	3.83	3.81	3.62	4.03	3.75	3.97	3.78	3.78	4.53							
% CaO	5.77	5.89	6.40	6.32	6.40	6.44	6.39	6.62	6.28	6.28	9.92							
% MgO	1.53	1.48	1.59	1.55	1.62	1.98	1.58	1.61	1.62	1.62	1.78							
% K2O	2.02	1.96	1.93	1.93	2.01	1.90	1.95	1.94	1.96	1.96	1.74							
% Na2O	0.08	0.12	0.13	0.15	0.15	0.27	0.08	0.13	0.14	0.14	0.70							
% SO3	2.25	3.46	4.04	2.99	3.30	2.83	2.80	3.60	3.16	3.16	3.31							
% P4O5	0.14	0.14	0.18	0.21	0.15	0.16	0.02	0.14	0.14	0.14	0.17							
% SrO	0.06	0.07	0.07	0.08	0.06	0.06	0.07	0.07	0.07	0.07	0.10							
% BaO	0.26	0.19	0.33	0.32	0.27	0.30	0.24	0.26	0.27	0.27	0.23							
% MnO	0.15	0.15	0.15	0.14	0.15	0.15	0.15	0.15	0.15	0.15	0.16							
Undetermined	2.56	2.96	0.61	1.41	1.19	0.78	2.67	1.66	1.73	1.73	0.64							
T 250	2900	2900	2873	2888	2882	2842	2871	2848	2876	2876	2692							

Table A2. HEALY TWO BULL RIDGE COAL TESTS: Coal Analyses

	HEALY TWO BULL RIDGE COAL TESTS: (MOISTURE FREE BASIS)										All Healy	
Test No.	555-TBR3	556-TBR4	557-TBR5	559-TBR7	560-TBR8	562-TBR10	563-TBR11	564-TBR12	TBR Coal	Perf.		
Sample No.	1391-16B	1396-16B	1399-16B	1405-16B	1408-16B	1414-16B	1417-16B	1419-16B	AVERAGE	Average		
Wt. %												
PROXIMATE												
% Moisture	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
% Ash	32.50	31.29	29.50	29.95	29.93	30.66	29.60	28.90	30.29	23.15	23.15	
% Volatile	41.61	41.99	42.69	42.17	42.25	41.70	43.24	43.16	42.35	44.43	44.43	
% Fixed Carbon	25.88	26.72	27.81	27.88	27.82	27.64	27.16	27.93	27.36	32.48	32.48	
Btu/lb	7903	7951	8245	8185	8237	8116	8269	8363	8158	9042	9042	
ULTIMATE												
% Moisture	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
% Carbon	46.60	47.47	48.67	48.52	48.91	47.73	48.85	49.15	48.24	53.73	53.73	
% Hydrogen	3.62	3.75	3.86	3.79	3.82	3.73	3.86	3.85	3.78	4.07	4.07	
% Nitrogen	0.83	0.84	0.84	0.86	0.88	0.88	0.83	0.82	1.21	0.87	0.87	
% Sulfur	0.39	0.40	0.40	0.41	0.40	0.40	0.40	0.41	0.46	0.37	0.37	
% Ash	32.50	31.29	29.50	29.95	29.93	30.66	29.60	28.90	26.60	23.15	23.15	
% Oxygen	16.07	16.26	16.74	16.06	16.06	16.60	16.46	16.87	18.12	17.82	17.82	

Table A3. HEALY PERFORMANCE COAL: SLAG ANALYSES

HEALY PERFORMANCE COAL TESTS: SLAG ANALYSES (AS FIRED)																				
Test No.	309-H13-1	400-H13-2	401-H14	402-H14-1	406-H16	407-H17	408-H18	503-H23	510-H30	523-H34										
Sample No.	1211-16B	1232-16B	1230-16B	1235-16B	1240-16B	1241-16B	1246-16B	1251-16B	1281-16B	1273-16B										
Wt. %																				
PROXIMATE																				
% Moisture	15.53	13.78	13.53	15.70	15.35	17.20	12.34	17.31	12.14	19.96										
% Ash	84.01	84.59	85.28	82.61	83.74	81.94	86.81	81.47	87.20	78.17										
% Volatile	0.37	0.51	0.42	0.61	0.39	0.55	0.35	0.49	0.36	0.69										
% Fixed Carbon	0.09	1.12	0.77	1.08	0.52	0.31	0.50	0.73	0.30	1.18										
Btu/lb	0	99	99	99	99	99	99	99	99	233										
ULTIMATE																				
% Moisture	15.53	13.78	13.53	15.70	15.35	17.20	12.34	17.31	12.14	19.96										
% Carbon	0.69	1.22	0.84	1.23	0.62	0.68	0.64	1.00	0.50	1.65										
% Hydrogen	0.02	0.07	0.03	0.03	0.01	0.01	0.02	0.00	0.01	0.04										
% Nitrogen	0.13	0.22	0.23	0.32	0.19	0.12	0.11	0.12	0.10	0.08										
% Sulfur	0.13	0.11	0.09	0.10	0.08	0.04	0.07	0.09	0.04	0.10										
% Ash	84.01	84.59	85.28	82.61	83.74	81.94	86.81	81.47	87.20	78.17										
% Oxygen	-0.51	0.01	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.00										
ASH ANALYSIS																				
% SiO2	67.65	66.58	67.61	65.95	69.22	68.65	65.09	67.19	64.47	68.17										
% Al2O3	13.53	14.27	13.77	12.61	13.56	13.84	14.50	12.96	14.28	14.18										
% TiO2	0.57	0.63	0.59	1.55	0.59	0.60	0.64	0.56	0.68	0.61										
% Fe2O3	4.94	5.10	4.71	5.30	4.51	4.19	4.98	4.40	4.77	3.99										
% CaO	8.33	8.25	7.87	7.27	7.20	7.36	7.90	8.00	8.92	8.07										
% MgO	1.59	1.60	1.53	1.43	1.43	1.53	1.55	1.50	1.67	1.71										
% K2O	1.77	1.80	1.82	1.59	1.82	1.84	0.79	1.73	1.72	1.75										
% Na2O	0.93	0.85	0.88	0.90	0.89	0.95	0.77	0.85	0.74	0.79										
% SO3	0.03	0.09	0.04	1.15	0.12	0.12	0.09	0.03	0.03	0.15										
% P4O5	0.16	0.16	0.15	0.14	0.14	0.17	0.15	0.15	0.14	0.19										
% SrO	0.09	0.09	0.09	0.12	0.09	0.09	0.09	0.09	0.10	0.09										
% BaO	0.25	0.26	0.30	0.27	0.28	0.27	0.28	0.27	0.11	0.14										
% MnO	0.16	0.15	0.16	0.15	0.15	0.15	0.16	0.16	0.16	0.16										
Undetermined	0.00	0.17	0.48	1.57	0.00	0.24	2.01	2.11	2.21	0.00										
T 250	2805	2789	2860	2855	2900	2900	2821	2865	2756	2900										

Table A3. HEALY PERFORMANCE COAL: SLAG ANALYSES

		HEALY PERFORMANCE COAL TESTS: SLAG ANALYSES										(MOISTURE FREE BASIS)			
Test No.	309-H13-1	400-H13-2	401-H14	402-H14-1	406-H16	407-H17	408-H18	503-H23	510-H30	523-H34					
Sample No.	1211-16B	1232-16B	1230-16B	1235-16B	1240-16B	1241-16B	1246-16B	1251-16B	1281-16B	1273-16B					
Wt. %															
PROXIMATE															
% Moisture	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			0.00		
% Ash	99.46	98.11	98.62	98.00	98.92	98.96	99.03	98.52	99.25	97.66					
% Volatile	0.44	0.59	0.49	0.72	0.46	0.66	0.40	0.59	0.41	0.86					
% Fixed Carbon	0.11	1.30	0.89	1.28	0.61	0.37	0.57	0.88	0.34	1.47					
Btu/lb	0	115	114	117	117	120	113	120	113	291					
ULTIMATE															
% Moisture	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			0.00		
% Carbon	0.82	1.41	0.97	1.46	0.73	0.82	0.73	1.21	0.57	2.06					
% Hydrogen	0.02	0.08	0.03	0.04	0.01	0.01	0.02	0.00	0.01	0.05					
% Nitrogen	0.15	0.26	0.27	0.38	0.22	0.14	0.13	0.15	0.11	0.10					
% Sulfur	0.15	0.13	0.10	0.12	0.09	0.05	0.08	0.11	0.05	0.12					
% Ash	99.46	98.11	98.62	98.00	98.92	98.96	99.03	98.52	99.25	97.66					
% Oxygen	-0.60	0.01	0.00	0.01	0.01	0.01	0.01	0.01	0.01	0.01			0.01		

Table A4. HEALY TWO BULL RIDGE COAL TESTS: Slag Analyses

Test No.	HEALY TWO BULL RIDGE COAL TESTS: SLAG ANALYSES (AS FIRED)															All Healy	
	555-TBR3	556-TBR4	557-TBR5	559-TBR7	560-TBR8	562-TBR10	563-TBR11	564-TBR12	TBR Coal							Perf.	
Sample No.	1393-16B	1397-16B	1400-16B	1406-16B	1409-16B	1415-16B	1411-16B	1420-16B	AVERAGE							Average	
Wt. %																	
PROXIMATE																	
% Moisture	15.85	46.61	23.68	38.31	31.00	56.34	50.75	30.99	36.69							14.81	
% Ash	83.27	51.13	71.58	59.71	63.96	38.57	45.75	68.10	60.26							83.29	
% Volatile	0.63	0.88	1.44	0.73	0.68	1.00	0.98	0.20	0.82							0.77	
% Fixed Carbon	0.25	1.38	3.30	1.25	4.36	4.09	2.52	0.71	2.23							1.13	
Btu/lb	92	282	582	225	455	680	457	150	365.38							200	
ULTIMATE																	
% Moisture	15.85	46.61	23.68	38.31	31.00	56.34	50.75	30.99	36.69							14.81	
% Carbon	0.61	2.06	3.85	1.82	4.71	4.89	3.29	0.81	2.76							1.54	
% Hydrogen	0.00	0.04	0.17	0.02	0.02	0.03	0.02	0.01	0.04							0.03	
% Nitrogen	0.14	0.10	0.13	0.09	0.13	0.09	0.11	0.06	0.11							0.14	
% Sulfur	0.13	0.06	0.08	0.04	0.10	0.07	0.07	0.03	0.07							0.18	
% Ash	83.27	51.13	71.58	59.71	63.96	38.57	45.75	68.10	60.26							83.29	
% Oxygen	0.00	0.00	0.51	0.01	0.08	0.01	0.01	0.00	0.08							0.00	
ASH ANALYSIS																	
% SiO ₂	63.63	62.52	62.74	62.93	62.95	61.35	58.23	59.29	61.71							66.70	
% Al ₂ O ₃	21.62	18.00	21.41	21.59	22.03	21.18	20.65	20.77	20.93							13.92	
% TiO ₂	0.91	0.75	0.94	1.04	0.91	0.90	0.88	0.90	0.90							0.65	
% Fe ₂ O ₃	3.60	4.50	3.92	3.68	3.54	3.73	5.61	4.17	4.09							4.49	
% CaO	5.81	9.31	6.49	6.55	6.02	8.10	10.02	10.33	7.83							8.85	
% MgO	1.49	1.77	1.62	1.63	1.60	1.56	1.75	1.81	1.65							1.66	
% K ₂ O	2.03	1.79	1.97	1.99	2.03	1.97	1.79	1.86	1.93							1.68	
% Na ₂ O	0.16	0.47	0.19	0.21	0.18	0.21	0.23	0.18	0.23							0.80	
% SO ₃	0.10	0.10	0.12	0.03	0.08	0.34	0.21	0.06	0.13							0.14	
% P ₄ O ₅	0.14	0.21	0.14	0.12	0.14	0.16	0.17	0.16	0.16							0.16	
% SrO	0.06	0.09	0.07	0.08	0.06	0.07	0.07	0.08	0.07							0.10	
% BaO	0.30	0.32	0.24	0.00	0.31	0.28	0.23	0.24	0.24							0.24	
% MnO	0.15	0.17	0.15	0.15	0.15	0.15	0.16	0.15	0.15							0.16	
Undetermined	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0.00							0.39	
T 250	2900	2747	2900	2900	2900	2831	2653	2693	2816							2802	

Table A4. HEALY TWO BULL RIDGE COAL TESTS: Slag Analyses

		HEALY TWO BULL RIDGE COAL TESTS: SLAG ANALYSES (MOISTURE FREE BASIS)										All Healy	
Test No.		555-TBR3	556-TBR4	557-TBR5	559-TBR7	560-TBR8	562-TBR10	563-TBR11	564-TBR12	TBR Coal	Perf.		
Sample No.		1393-16B	1397-16B	1400-16B	1406-16B	1409-16B	1415-16B	1411-16B	1420-16B	AVERAGE	Average		
Wt. %													
PROXIMATE													
% Moisture		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
% Ash		98.95	95.77	93.79	96.79	92.70	88.34	92.89	98.68	94.74	97.73	97.73	
% Volatile		0.75	1.65	1.89	1.18	0.99	2.29	1.99	0.29	1.38	0.92	0.92	
% Fixed Carbon		0.30	2.58	4.32	2.03	6.32	9.37	5.12	1.03	3.88	1.35	1.35	
Btu/lb		109	528	763	365	659	1557	928	217	641	240	240	
ULTIMATE													
% Moisture		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
% Carbon		0.72	3.86	5.04	2.95	6.83	11.20	6.68	1.17	4.81	1.85	1.85	
% Hydrogen		0.00	0.07	0.22	0.03	0.03	0.07	0.04	0.01	0.06	0.03	0.03	
% Nitrogen		0.17	0.19	0.17	0.15	0.19	0.21	0.22	0.09	0.17	0.16	0.16	
% Sulfur		0.15	0.11	0.10	0.06	0.14	0.16	0.14	0.04	0.12	0.21	0.21	
% Ash		98.95	95.77	93.79	96.79	92.70	88.34	92.89	98.68	94.74	97.73	97.73	
% Oxygen		0.00	0.00	0.67	0.02	0.12	0.02	0.02	0.00	0.11	0.00	0.00	

Table A5. HEALY PERFORMANCE COAL: FLYASH ANALYSES

HEALY PERFORMANCE COAL TESTS: FLYASH ANALYSES (AS FIRED)												
Test No.	309-H13-1	400-H13-2	401-H14	402-H14-1	406-H16	407-H17	408-H18	503-H23	510-H30	523-H34		
Sample No.	1215-16B	1233-16B	1231-16B	1236-16B	1239-16B	1242-16B	1245-16B	1252-16B	1282-16B	1292-16B		
PROXIMATE												
% Moisture	0.09	0.08	0.04	0.07	0.16	0.02	0.02	0.01	0.42	0.02		
% Ash	98.64	98.69	98.39	98.17	98.61	98.99	99.46	98.28	96.79	98.85		
% Volatile	0.56	0.29	0.44	0.70	0.48	0.30	0.19	1.69	2.41	1.12		
% Fixed Carbon	0.71	0.94	1.13	1.06	0.75	0.69	0.33	0.02	0.38	0.01		
Btu/lb	99	99	99	99	99	99	0	0	65	99		
ULTIMATE												
% Moisture	0.09	0.08	0.04	0.07	0.16	0.02	0.02	0.01	0.42	0.02		
% Carbon	0.45	0.23	0.55	0.67	0.54	0.40	0.31	0.52	1.27	0.31		
% Hydrogen	0.06	0.06	0.08	0.05	0.04	0.04	0.04	0.02	0.03	0.09		
% Nitrogen	0.39	0.57	0.63	0.53	0.28	0.19	0.26	0.22	0.30	0.18		
% Sulfur	0.36	0.36	0.30	0.50	0.36	0.35	0.37	0.59	0.15	0.55		
% Ash	98.64	98.69	98.39	98.17	98.61	98.99	99.46	98.29	96.79	98.85		
% Oxygen	0.01	0.01	0.01	0.01	0.01	0.01	-0.46	0.36	1.04	0.00		
ASH ANALYSIS												
% SiO2	52.52	53.40	53.65	48.23	51.92	52.07	52.22	49.39	49.24	51.04		
% Al2O3	18.90	18.99	18.71	17.97	18.23	18.40	18.42	16.36	15.04	18.42		
% TiO2	0.76	0.78	0.94	0.68	0.70	0.78	0.72	0.72	0.70	0.68		
% Fe2O3	6.66	6.65	6.57	6.87	6.72	6.60	6.75	6.29	5.89	6.03		
% CaO	11.80	11.12	12.14	15.60	12.80	12.47	12.42	17.08	18.20	13.98		
% MgO	2.54	2.40	2.60	3.20	2.60	2.40	2.44	2.48	3.20	2.40		
% K2O	2.20	2.30	2.30	2.10	2.30	2.28	2.35	2.17	2.07	2.60		
% Na2O	0.65	0.72	0.72	0.66	0.70	0.70	0.69	0.66	0.60	0.70		
% SO3	0.90	0.53	0.61	1.21	0.77	0.78	0.84	1.01	1.85	1.29		
% P4O5	0.10	0.08	0.08	0.13	0.08	0.11	0.10	0.08	0.13	0.10		
LOI	1.50	1.30	1.42	2.07	1.68	1.60	1.6	2.88	2.7	1.42		
Undetermined	1.47	1.73	0.26	1.28	1.50	1.81	1.45	0.88	0.38	1.34		
% Ca	8.43	7.94	8.67	11.14	9.14	8.91	8.87	N/A	N/A	9.99		
%CO2	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	1.38		
% CaCO3	3.22	2.91	3.18	4.41	3.64	3.54	3.54	N/A	N/A	3.14		
% C2SO4	1.19	0.75	1.16	2.17	1.43	1.13	1.22	N/A	N/A	2.12		

Table A5. HEALY PERFORMANCE COAL: FLYASH ANALYSES

HEALY PERFORMANCE COAL TESTS: FLYASH ANALYSES												(MOISTURE FREE BASIS)			
Test No.	309-H13-1	400-H13-2	401-H14	402-H14-1	406-H16	407-H17	408-H18	503-H23	510-H30	523-H34					
Sample No.	1215-16B	1233-16B	1231-16B	1236-16B	1239-16B	1242-16B	1245-16B	1252-16B	1282-16B	1292-16B					
Wt. %															
PROXIMATE															
% Moisture	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00				
% Ash	98.73	98.77	98.43	98.24	98.77	99.01	99.48	98.29	97.20	98.87	98.87				
% Volatile	0.56	0.29	0.44	0.70	0.48	0.30	0.19	1.69	2.42	1.12	1.12				
% Fixed Carbon	0.71	0.94	1.13	1.06	0.75	0.69	0.33	0.02	0.38	0.01	0.01				
Btu/lb															
ULTIMATE															
% Moisture	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00				
% Carbon	0.45	0.23	0.55	0.67	0.54	0.40	0.31	0.52	1.28	0.31	0.31				
% Hydrogen	0.06	0.06	0.08	0.05	0.04	0.04	0.04	0.02	0.03	0.09	0.09				
% Nitrogen	0.39	0.57	0.63	0.53	0.28	0.19	0.26	0.22	0.30	0.18	0.18				
% Sulfur	0.36	0.36	0.30	0.50	0.36	0.35	0.37	0.59	0.15	0.55	0.55				
% Ash	98.73	98.77	98.43	98.24	98.77	99.01	99.48	98.30	97.20	98.87	98.87				
% Oxygen	0.01	0.01	0.01	0.01	0.01	0.01	-0.46	0.36	1.04	0.00	0.00				

Table A5. HEALY PERFORMANCE COAL: FLYASH ANALYSES

Test No. Sample No.	HEALY PERFORMANCE COAL TESTS: FLYASH ANALYSES (AS FIRED)												FCM Tests		All Healy Perf.
	525-H36	529-H40	530-H41	534-H45	537-H48	541-H52	545-H56	548-H59	552-H63	1385-16B	1372-16B	1361-16B	552-H63	H20-H63	Average
PROXIMATE															
% Moisture	0.04	0.04	0.19	0.09	0.14	0.11	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.10	0.36
% Ash	98.70	98.50	97.27	97.92	98.17	97.87	97.77	98.19	97.64	97.64	98.19	97.77	97.64	98.00	98.01
% Volatile	1.19	1.40	2.46	1.98	1.16	2.00	1.86	1.51	2.25	1.75	1.51	1.86	2.25	1.75	1.29
% Fixed Carbon	0.07	0.06	0.08	0.01	0.53	0.02	0.31	0.24	0.05	0.15	0.24	0.31	0.05	0.15	0.34
Btu/lb	0	99	99	0	99	99	99	99	99	71	99	99	99	71	67
ULTIMATE															
% Moisture	0.04	0.04	0.19	0.09	0.14	0.11	0.06	0.06	0.06	0.06	0.06	0.06	0.06	0.10	0.36
% Carbon	0.37	0.52	0.97	0.94	0.71	0.82	0.74	0.75	0.96	0.74	0.75	0.74	0.96	0.74	0.64
% Hydrogen	0.06	0.04	0.02	0.03	0.03	0.02	0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.04	0.05
% Nitrogen	0.16	0.19	0.23	0.18	0.15	0.06	0.19	0.15	0.26	0.19	0.15	0.19	0.26	0.19	0.26
% Sulfur	0.67	0.71	0.83	0.84	0.80	0.95	1.20	0.82	0.98	0.82	0.82	1.20	0.98	0.76	0.57
% Ash	98.70	98.50	97.27	97.92	98.17	97.87	97.77	98.19	97.64	97.64	98.19	97.77	97.64	98.00	98.01
% Oxygen	0.00	0.00	0.49	0.00	0.00	0.17	0.01	0.00	0.07	0.18	0.00	0.01	0.07	0.18	0.12
ASH ANALYSIS															
% SiO ₂	48.23	47.77	47.93	46.61	48.51	44.10	44.83	46.31	45.57	47.46	46.31	44.83	45.57	47.46	50.03
% Al ₂ O ₃	17.30	17.87	17.48	16.92	17.18	17.07	16.35	16.36	16.00	16.86	16.36	16.35	16.00	16.86	17.87
% TiO ₂	0.74	0.74	0.72	0.72	0.68	0.64	0.76	0.80	0.66	0.71	0.80	0.76	0.66	0.71	0.73
% Fe ₂ O ₃	6.01	6.17	6.03	6.03	6.29	6.10	6.46	6.06	5.87	6.10	6.06	6.46	5.87	6.10	6.28
% CaO	16.80	18.00	17.60	17.72	16.80	21.08	20.32	18.40	20.80	18.07	18.40	20.32	20.80	18.07	15.37
% MgO	2.56	2.56	2.44	2.34	2.60	2.72	2.68	2.56	2.68	2.60	2.56	2.68	2.68	2.60	2.56
% K ₂ O	2.40	2.41	2.32	2.24	2.30	2.12	2.16	2.14	2.02	2.25	2.14	2.16	2.02	2.25	2.26
% Na ₂ O	0.65	0.65	0.64	0.62	0.70	0.64	0.64	0.63	0.60	0.64	0.63	0.64	0.60	0.64	0.66
% SO ₃	1.67	1.70	1.76	1.94	2.06	1.87	1.94	2.22	2.22	1.79	2.22	1.94	2.22	1.79	1.29
% P ₄ O ₅	0.12	0.07	0.13	0.07	0.10	0.11	0.12	0.09	0.16	0.10	0.09	0.12	0.16	0.10	0.13
LOI	2.50	1.80	2.85	3.28	2.27	3.11	3.00	3.62	3.37	2.73	3.62	3.00	3.37	2.73	2.31
Undetermined	1.02	0.26	0.13	1.47	0.51	0.44	0.74	0.81	0.05	0.67	0.81	0.74	0.05	0.67	0.76
% Ca	12.00	12.86	12.58	12.69	12.00	15.06	14.52	13.15	14.86	12.97	13.15	14.52	14.86	12.97	9.20
% CO ₂	2.00	1.50	2.50	3.02	1.57	1.64	1.62	1.54	1.62	1.84	1.54	1.62	1.62	1.84	1.47
% CaCO ₃	4.54	3.40	5.68	6.86	5.00	6.86	6.77	8.18	4.98	5.54	8.18	6.77	4.98	5.54	3.84
% CaSO ₄	2.64	2.80	3.14	3.26	3.40	3.09	3.23	3.74	3.74	3.12	3.74	3.23	3.74	3.12	483.30

Table A5. HEALY PERFORMANCE COAL: FLYASH ANALYSES

Test No.	HEALY PERFORMANCE COAL TESTS: FLYASH ANALYSES										(MOISTURE FREE BASIS)				FCM Tests		All Healy Perf.
	525-H36	529-H40	530-H41	534-H45	537-H48	541-H52	545-H56	548-H59	552-H63	1385-16B	1372-16B	1361-16B	1361-16B	1372-16B	1385-16B	H20-H63 Average	0.00
Sample No.	1298-16B	1315-16B	1311-16B	1312-16B	1340-16B	1351-16B	1361-16B	1372-16B	1385-16B	1385-16B	1372-16B	1361-16B	1361-16B	1372-16B	1385-16B	1385-16B	1385-16B
Wt. %																	
PROXIMATE																	
% Moisture	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
% Ash	98.74	98.54	97.46	98.01	98.31	97.98	97.83	98.25	97.70	98.10	98.37	97.83	97.83	98.25	97.70	98.10	98.37
% Volatile	1.19	1.40	2.46	1.98	1.16	2.00	1.86	1.51	2.25	1.75	1.30	1.86	1.86	1.51	2.25	1.75	1.30
% Fixed Carbon	0.07	0.06	0.08	0.01	0.53	0.02	0.31	0.24	0.05	0.15	0.34	0.31	0.31	0.24	0.05	0.15	0.34
Btu/lb	0	99	99	0	99	99	99	99	99	77	60	99	99	99	99	77	60
ULTIMATE																	
% Moisture	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
% Carbon	0.37	0.52	0.97	0.94	0.71	0.82	0.74	0.75	0.96	0.74	0.64	0.74	0.74	0.75	0.96	0.74	0.64
% Hydrogen	0.06	0.04	0.02	0.03	0.03	0.02	0.03	0.03	0.03	0.04	0.05	0.03	0.03	0.03	0.03	0.04	0.05
% Nitrogen	0.16	0.19	0.23	0.18	0.15	0.06	0.19	0.15	0.26	0.19	0.26	0.19	0.19	0.15	0.26	0.19	0.26
% Sulfur	0.67	0.71	0.83	0.84	0.80	0.95	1.20	0.82	0.98	0.76	0.57	1.20	1.20	0.82	0.98	0.76	0.57
% Ash	98.74	98.54	97.46	98.01	98.31	97.98	97.83	98.25	97.70	98.10	98.37	97.83	97.83	98.25	97.70	98.10	98.37
% Oxygen	0.00	0.00	0.49	0.00	0.00	0.17	0.01	0.00	0.07	0.18	0.12	0.01	0.01	0.00	0.07	0.18	0.12

Table A6. HEALY TWO BULL RIDGE COAL TESTS: Flyash Analyses

		HEALY TWO BULL RIDGE COAL TESTS: FLYASH ANALYSES (AS FIRED)													
Test No.	555-TBR3	556-TBR4	557-TBR5	559-TBR7	560-TBR8	562-TBR10	563-TBR11	564-TBR12	TBR Coal			All Healy			
Sample No.	1392-16B	1398-16B	1401-16B	1407-16B	1410-16B	1416-16B	1418-16B	1421-16B	AVERAGE			Part.	Average		
PROXIMATE															
% Moisture	0.08	0.13	0.22	0.04	0.08	0.24	0.14	0.23	0.15	0.36					
% Ash	98.04	97.99	96.02	98.34	97.93	98.18	97.99	97.74	97.78	98.01					
% Volatile	1.80	1.81	3.64	1.62	1.90	1.50	1.84	1.99	2.01	1.29					
% Fixed Carbon	0.08	0.07	0.33	0.00	0.09	0.08	0.03	0.04	0.09	0.34					
Btu/lb	106	100	100	18	100	156	106	161	106	67					
ULTIMATE															
% Moisture	0.08	0.13	0.22	0.04	0.08	0.24	0.14	0.23	0.15	0.36					
% Carbon	0.52	0.76	0.92	0.20	0.40	1.04	1.28	1.18	0.79	0.64					
% Hydrogen	0.03	0.02	0.04	0.02	0.01	0.01	0.01	0.01	0.02	0.05					
% Nitrogen	0.18	0.14	0.26	0.15	0.18	0.19	0.11	0.13	0.17	0.26					
% Sulfur	0.58	0.33	0.34	0.28	0.27	0.34	0.33	0.47	0.37	0.57					
% Ash	98.04	97.99	96.02	98.34	97.93	98.18	97.99	97.74	97.78	98.01					
% Oxygen	0.57	0.63	2.42	0.97	1.13	0.00	0.14	0.24	0.76	0.12					
ASH ANALYSIS															
% SiO2	51.17	53.83	54.40	57.19	57.55	58.88	57.21	57.11	55.92	50.03					
% Al2O3	19.78	18.04	21.32	22.73	22.50	23.25	22.63	23.05	21.66	17.87					
% TiO2	0.76	0.76	0.82	1.20	0.89	0.90	0.89	0.93	0.89	0.73					
% Fe2O3	3.69	3.67	3.95	3.51	3.76	3.65	3.88	3.78	3.74	6.28					
% CaO	17.81	14.16	13.08	8.42	9.60	7.77	9.61	9.25	11.21	15.37					
% MgO	2.41	2.08	2.15	1.67	1.82	1.72	1.83	1.83	1.94	2.56					
% K2O	1.98	2.02	2.15	2.09	2.23	2.25	2.21	2.27	2.15	2.26					
% Na2O	0.28	0.24	0.24	0.14	0.16	0.17	0.17	0.15	0.19	0.66					
% SO3	1.35	0.96	1.00	0.24	0.66	0.64	0.79	0.96	0.83	1.29					
% P4O5	0.22	0.10	0.21	0.15	0.20	0.20	0.20	0.18	0.18	0.13					
%SrO	0.09	N/A	0.08	0.09	0.07	0.07	0.07	0.08	0.08	2.31					
%BaO	0.32	N/A	0.38	0.00	0.37	0.36	0.36	0.26	0.29	0.76					
%MnO	0.14	N/A	0.15	0.14	0.14	0.14	0.15	0.15	0.14	9.20					
Undetermined	0.00	1.34	0.07	2.43	0.05	0.00	0.00	0.00	0.49	1.47					
T 250	2456		2581	2771	2708	2799	2701	2716	2676	3.84					
LOI		2.80								483.30					

Table A6. HEALY TWO BULL RIDGE COAL TESTS: Flyash Analyses

Test No.	HEALY TWO BULL RIDGE COAL TESTS: FLYASH ANALYSES (MOISTURE FREE BASIS)										All Healy	
	555-TBR3	556-TBR4	557-TBR5	559-TBR7	560-TBR8	562-TBR10	563-TBR11	564-TBR12	TBR Coal	Perf.		
Sample No.	1392-16B	1398-16B	1401-16B	1407-16B	1410-16B	1416-16B	1418-16B	1421-16B	AVERAGE	Average		
Wt. %												
PROXIMATE												
% Moisture	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
% Ash	98.12	98.12	96.23	98.38	98.01	98.42	98.13	97.97	97.92	98.37	97.92	98.37
% Volatile	1.80	1.81	3.65	1.62	1.90	1.50	1.84	1.99	2.02	1.30	2.02	1.30
% Fixed Carbon	0.08	0.07	0.33	0.00	0.09	0.08	0.03	0.04	0.09	0.34	0.09	0.34
Btu/lb	106	100	100	18	100	156	106	161	106	60	106	60
ULTIMATE												
% Moisture	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
% Carbon	0.52	0.76	0.92	0.20	0.40	1.04	1.28	1.18	0.79	0.64	0.79	0.64
% Hydrogen	0.03	0.02	0.04	0.02	0.01	0.01	0.01	0.01	0.02	0.05	0.02	0.05
% Nitrogen	0.18	0.14	0.26	0.15	0.18	0.19	0.11	0.13	0.17	0.26	0.17	0.26
% Sulfur	0.58	0.33	0.34	0.28	0.27	0.34	0.33	0.47	0.37	0.57	0.37	0.57
% Ash	98.12	98.12	96.23	98.38	98.01	98.42	98.13	97.97	97.92	98.37	97.92	98.37
% Oxygen	0.57	0.63	2.43	0.97	1.13	0.00	0.14	0.24	0.76	0.12	0.76	0.12

APPENDIX B. TEST DATA SUMMARIES

Table B1. Data Table Nomenclature

Nomenclature

TESTS	First three digits indicate consecutive test number, second number indicates test condition.
SLAG RECVRY	Slag recovery numbers determined from coal ash and slag ash weights, corrected for sulfur. Equation is given in Appendix C.
COAL GRIND	Weight percent passing the 200 mesh screen (74 micron particle diameter)
DAMPER POS.	Damper position at the precombustor exit. Damper A is the downstream damper from the main combustor's headend. The values are given in terms of percent of available movement (stroke). Damper configurations are shown in Appendix D.
PC EXIT	Precombustor exit velocity in FT/S. DCS values corrected in Appendix C for coal type and PC devolatilization.
COAL INJ. DEPTH	Main combustor coal injection depth.
PCC PHI	Precombustor can equivalence ratio.
PC PHI	Equivalence ratio at exit of precombustor
MC PHI	Equivalence ratio in main combustor.
SB PHI	Equivalence ratio at secondary burner.
LOAD	Total coal flow in MMBTU/HR.
COAL PC	Precombustor coal flow in LBS/HR.
COAL MC	Main combustor coal flow in LBS/HR.
COAL SPLIT	Percent of coal going to the precombustor.
PCCA	Precombustor can air in thousands of LBS/HR.
PCMB	Precombustor mix bustle air in thousands of LBS/HR.
SBCA	Secondary burner air in thousands of LBS/HR.
INTR. AIR	Intrusion air, determined by calculating the difference in air flows attributed to measured stack oxygen and secondary burner oxygen.
O2 SB	Percent oxygen in the gas at the secondary burner.
O2 STACK	Percent oxygen in the gas measured at the stack.

Table B1. (continued)

CO @3%	Carbon monoxide emissions in stack in ppm, corrected to 3% oxygen.
NOX @3%	Nitrogen oxides emissions in stack in ppm, corrected to 3% oxygen.
SO2 @3%	Sulfur dioxide emissions in stack in ppm, corrected to 3% oxygen.
SO2 W/O LS	Calculated sulfur dioxide emissions in ppm, without limestone, corrected to 3% oxygen.
LS	Limestone flowrate in LBS/HR.
CA/S	Molar ratio of calcium in limestone to sulfur in the coal.
S	Percent sulfur in the coal.
SO2 REDUC	Sulfur dioxide reduction due to limestone addition.
PC EXIT	Precombustor exit temperature calculated assuming that only coal devolatilization occurs.
TOT STM	Total steam produced in thousands of LBS/HR - Sum of flash tank steam (combustor) plus boiler steam.
COOL LOAD	Combustor heat transfer to the cooling system relative to the thermal input, in percent.
BLR EFF	Boiler efficiency.
FUEL/STM CORR	Fuel to steam flow correlation (value of 1 indicates a match between BTU's released in the system and available BTU's in the coal fired).
HEAT LOSS	Total combustor heat loss (precombustor, main combustor, secondary burner).
HEAT FLUX	<ul style="list-style-type: none"> 1 - Headend + Air inlet 2 - Spool + Air inlet 3 - Baffle 4 - Slag recovery section front 5 - Slag recovery section right + half of back side 6 - Slag recovery section left + half of back side 7 - Precombustor + secondary burner 9 - Slag tap

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 308-H13

Date 04/12/91

PURPOSE: DEMONSTRATE SYSTEM OPERABILITY

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T2ED (calc. deg F): 2715 HHV (Btu/lb): 7988LIMESTONE: % CaCO₃: N/ANATURAL GAS: Btu/lb _____ Stoich air (# air/# NG): _____
Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 95

Section: 1 OF 1

Time of Test: 11:30

FLOW RATES:

Coal PC (#/hr) 959.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 4.380
Mix Bustle Air PC (kpph) 4.450
Coal MC (#/hr) 1558.300
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 5.873LS (#/hr) _____
LS Split (I/N) _____
Nozzles _____
Carr'r A/LS (scfh) 0.000
C.A. Press (psig) Edc Wzl Dia 0.375
Nozzles (throat): _____
Injector (tube): _____
Ca/S Ratio N/A
SCFH to #/hr 0.076Total Air (#/hr) 17316.644
Stoi Air (#/hr) 15065.656
Xcss Air SB (#/hr) 2250.988
Total Coal (#/hr) 2517.300
Total Gas (#/hr) 19303.801
% O₂ post SB Cmbn 2.547
Coal Split PC (%) 38.096
Ca Utilization, % _____

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 0.930

PC phi 1.705

MC phi 0.760

Overall phi at Sec. Brnr 1.149

Cling Calc (Btu/sec) 361.090 Cling Meas (Btu/sec) 583.555 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:FLUX (Btu/ft²-sec):#1 AI 1.365 #2 AI 1.766 #3 BAF 2.030 #4 SRS 2.190
#5 SRS 4.076 #6 SRS 2.696 #7 PC ET 1.003 #9 TAP 0.772

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
O₂ (%) 6.130
CO (ppm) 104.000 125.891 129.058
NOx (ppm) 122.000 147.680 151.395 0.223
SO₂ w/LS (ppm) 287.700 348.258 357.019 0.732
SO₂ w/o LS (ppm), calc 337.811 405.101 414.834

AIR TEMPERATURES (deg F):

Air Preheat Inlet 112.700 Preheat Outlet 362.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 579.700 FG Preheat Outlet 393.700

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.670

Flash Tank 2.080

Total Steam 17.750

Press. (psig): Boiler 103.000

Flash Tank 103.000

Temps. (deg F): Boiler 338.000

Flash Tank 338.000

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 20.108

Cooling (Coal + N Gas) - % 10.447

Cooling H₂O Inlet (deg F) 342.300

Coal + N. Gas - MMBtu/hr 20.108

RESULTS: Steam Gen Eff'cy (%) 82.986

Fuel to Steam Flow Corr. 0.929

Boiler Efficiency (%) 81.932

% SO₂ Reduction 13.937

Intrusion Air (#/hr) 4401.39

REMARKS: TEST CONDITIONS: MEDIUM LOAD AT PHI=.8

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 309-H13-1

Date 04/12/91

PURPOSE: DEMONSTRATE SYSTEM OPERABILITY

COAL: Source: HEALY PERF BLEND

Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
 Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: % CaCO₃: N/A

NATURAL GAS: Btu/lb _____
 Hydrogen (# H₂/# NG): _____

Stoich air (# air/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 59

Section: 1 OF 1

Time of Test: 16:30

FLOW RATES:

Coal PC (#/hr) 938.300
 Carrier Air PC (scfh) 12500.000
 Combustion Air PC (kpph) 4.800
 Mix Bustle Air PC (kpph) 6.110
 Coal MC (#/hr) 1522.000
 Carrier Air MC (scfh) 21710.000
 Cmbn Air Sec Brnr (kpph) 4.430

LS (#/hr) _____
 LS Split (I/N) _____
 # Nozzles _____
 Carr'r A/LS (scfh) 0.000
 C.A. Press (psig) Edc Nzl Dia 0.375
 Nozzles (throat): _____
 Injector (tube): _____
 Ca/S Ratio N/A
 SCFH to #/hr 0.076

Total Air (#/hr) 17953.644
 Stoic Air (#/hr) 14724.520
 Xcss Air SB (#/hr) 3229.124
 Total Coal (#/hr) 2460.300
 Total Gas (#/hr) 19895.805
 % O₂ post SB Cmbn 3.545
 Coal Split PC (%) 38.138
 Ca Utilization, % _____

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.025
 PC phi 2.113
 MC phi 0.918
 Overall phi at Sec. Brnr 1.219

Cing Calc (Btu/sec) 241.920 Cing Meas (Btu/sec) 510.611 Flow #/sec 28.800
 Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI 0.871 #2 AI 1.330 #3 BAF 1.633 #4 SRS 2.010
 #5 SRS 1.633 #6 SRS 1.269 #7 PC ET 0.960 #9 TAP 1.498

EMISSIONS:

At stack As meas.
 O₂ (%) 6.270
 CO (ppm) 6.210
 NOx (ppm) 174.300
 SO₂ w/LS (ppm) 274.700
 SO₂ w/o LS (ppm), calc 334.802

At 3% O₂ At Calc SB O₂ #/MMBtu
 7.589 7.359
 212.994 206.542 0.321
 335.682 325.513 0.704
 405.101 393.377

AIR TEMPERATURES (deg F):

Air Preheat Inlet 114.700 Preheat Outlet 373.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 593.300 FG Preheat Outlet 398.300

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.670
 Press. (psig): Boiler 103.000
 Temps. (deg F): Boiler 339.000

Flash Tank 1.820 Total Steam 17.490
 Flash Tank 103.000
 Flash Tank 339.000 Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 19.653 Cooling (Coal + N Gas) - % 9.353 Cooling H₂O Inlet (deg F) 344.000
 Coal + N. Gas - MMBtu/hr 19.653

RESULTS: Steam Gen Eff'cy (%) 82.760 Fuel to Steam Flow Corr. 0.919

Boiler Efficiency (%) 81.901 % SO₂ Reduction 17.252 Intrusion Air (#/hr) 3480.89

REMARKS: TEST CONDITIONS: MEDIUM LOAD AT PHI=.9
 SWIRL DAMPER SET AT VEL. OF 250 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 400-H13-2

Date 04/12/91

PURPOSE: DEMONSTRATE SYSTEM OPERABILITY

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE:

% CaCO₃: N/A

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NO): _____

Hydrogen (# H₂/# NO): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 92

Section: 1 OF 1

Time of Test: 21:16

FLOW RATES:

Coal PC (#/hr) 1013.300
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 5.280
Mix Bustle Air PC (kpph) 7.170
Coal MC (#/hr) 1513.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 3.140LS (#/hr) _____
LS Split (I/N) _____
Nozzles _____
Carr'r A/LS (scfh) 0.000
C.A. Press (psig) Edc Nzl Dia 0.375
Nozzles (throat): _____
Injector (tube): _____
Ca/S Ratio N/A
SCFH to #/hr 0.076Total Air (#/hr) 18203.644
Stoi Air (#/hr) 15119.520
Xcss Air SB (#/hr) 3084.124
Total Coal (#/hr) 2526.300
Total Gas (#/hr) 26197.905
% O₂ post SB Cmbn 3.335
Coal Split PC (%) 40.110
Ca Utilization, % _____

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.028

PC phi 2.210

MC phi 0.996

Overall phi at Sec. Brnr 1.204

Cling Calc (Btu/sec) 353.880 Cling Meas (Btu/sec) 617.222 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):#1 AI 0.827 #2 AI 1.260 #3 BAF 2.636 #4 SRS 3.317
#5 SRS 3.124 #6 SRS 2.268 #7 PC ET 1.419 #8 TAP 1.362

EMISSIONS:

At stack As meas.
O₂ (%) 6.310
CO (ppm) 0.000
NO_x (ppm) 147.300
SO₂ w/LS (ppm) 291.300
SO₂ w/o LS (ppm), calc 333.942At 3% O₂ At Calc SB O₂ #/MMBtu
0.000 0.000
180.490 177.127 0.272
356.937 350.285 0.749
405.101 397.888

AIR TEMPERATURES (deg F):

Air Preheat Inlet 109.000

Preheat Outlet 375.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 609.300

FG Preheat Outlet 400.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 16.050
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 338.700Flash Tank 2.200 Total Steam 18.250
Flash Tank 103.000
Flash Tank 338.700 Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 20.180
Coal + N. Gas - MMBtu/hr 20.180Cooling (Coal + N Gas) - % 11.011 Cooling H₂O Inlet (deg F) 343.000

RESULTS: Steam Gen Eff'cy (%) 82.682

Fuel to Steam Flow Corr. 0.903

Boiler Efficiency (%) 81.470

% SO₂ Reduction 11.964

Intrusion Air (#/hr) 3867.70

REMARKS: TEST CONDITIONS: MEDIUM LOAD AT PHI=1.
SWIRL DAMPER SET AT VEL. OF 250 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1
Date: 5/16/91TEST: 401-H14 Date 04/13/91
PURPOSE: DEMONSTRATE SYSTEM OPERABILITYCOAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988LIMESTONE: % CaCO₃: N/A NATURAL GAS: Btu/lb _____ Stoich air (# air/# NO): _____
Hydrogen (# H₂/# NO): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 77 Section: 1 OF 1 Time of Test: 12:00

FLOW RATES:

Coal PC (#/hr)	1200.000	LS (#/hr)	_____	Total Air (#/hr)	24053.644
Carrier Air PC (scfh)	12500.000	LS Split (I/N)	_____	Stoi Air (#/hr)	18630.830
Combustion Air PC (kpph)	6.300	# Nozzles	_____	Xcas Air SB (#/hr)	5422.814
Mix Bustle Air PC (kpph)	9.750	Carr'r A/LS (scfh)	0.000	Total Coal (#/hr)	3113.000
Coal MC (#/hr)	1913.000	C.A. Press (psig)	Edc M21 Dia 0.375	Total Gas (#/hr)	26511.046
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% O ₂ post SB Cmbn	4.468
Cmbn Air Sec Brnr (kpph)	5.390	Injector (tube):	_____	Coal Split PC (%)	38.548
		Ca/S Ratio	N/A	Ca Utilization, %	_____
		SCFH to #/hr	0.076		

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.010

PC phi 2.368

MC phi 1.002

Overall phi at Sec. Brnr 1.291

Cing Calc (Btu/sec) 324.000 Cing Meas (Btu/sec) 583.556 Flow #/sec 28.803

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI	0.581	#2 AI	0.942	#3 BAF	3.033	#4 SRS	3.268
#5 SRS	2.696	#6 SRS	2.220	#7 PC ET	1.387	#9 TAP	0.454

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	5.400			
CO (ppm)	163.500	188.654	173.267	
NOx (ppm)	156.000	180.000	165.319	0.270
SO ₂ w/LS (ppm)	315.700	364.269	334.559	0.762
SO ₂ w/o LS (ppm), calc	353.505	405.101	373.538	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 97.300 Preheat Outlet 417.700 Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 699.700 FG Preheat Outlet 448.700 NATURAL GAS INPUTS:

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 20.320

Press. (psig): Boiler 103.000

Temps. (deg F): Boiler 338.000

Flash Tank 2.080

Flash Tank 103.000

Flash Tank 338.000

Total Steam 22.400

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 24.867

Coal + N. Gas - MMBtu/hr 24.867

Cooling (Coal + N Gas) - % 8.448

Cooling H₂O Inlet (deg F) 342.000

RESULTS: Steam Gen Eff'cy (%) 81.710

Fuel to Steam Flow Corr. 0.896

Boiler Efficiency (%) 80.926

% SO₂ Reduction 10.435

Intrusion Air (#/hr) 1502.40

REMARKS: TEST CONDITION: MAXIMUM LOAD (30 MMBTU/HR) AT PHI=.9
COAL FEED VALVE SPEED 24.5%, SWIRL DAMPER AT V=250 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 402-H14-1

Date 04/15/91

PURPOSE: DEMONSTRATE SYSTEM OPERABILITY

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.820 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988LIMESTONE: % CaCO₃: N/A NATURAL GAS: Btu/lb _____ Stoich air (# air/# NG): _____
Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 55

Section: 1 OF 1

Time of Test: 15:00

FLOW RATES:

Coal PC (#/hr)	1200.000	LS (#/hr)	_____	Total Air (#/hr)	26153.644
Carrier Air PC (scfh)	12500.000	LS Split (I/N)	_____	Stoi Air (#/hr)	18481.209
Combustion Air PC (kpph)	6.280	# Nozzles	_____	Xcss Air SB (#/hr)	7672.435
Mix Bustle Air PC (kpph)	9.210	Carr'r A/LS (scfh)	0.000	Total Coal (#/hr)	3088.000
Coal MC (#/hr)	1888.000	C.A. Press (psig)	Edc Nz1 Dia	Total Gas (#/hr)	28591.311
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% O ₂ post SB Cmbn	5.862
Cmbn Air Sec Brnr (kpph)	8.050	Injector (tube):	_____	Coal Split PC (%)	38.860
		Ca/S Ratio	N/A	Ca Utilization, %	_____
		SCFH to #/hr	0.076		

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.007

PC phi 2.290

MC phi 0.980

Overall phi at Sec. Brnr 1.415

Cling Calc (Btu/sec) 378.000 Cling Meas (Btu/sec) 660.708 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI	0.435	#2 AI	0.942	#3 BAF	3.266	#4 SRS	4.904
#5 SRS	4.203	#6 SRS	2.062	#7 PC ET	1.387	#9 TAP	1.362

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	5.800			
CO (ppm)	54.650	64.717	54.428	
NOx (ppm)	181.500	214.934	180.763	0.321
SO ₂ w/LS (ppm)	271.500	321.513	270.397	0.669
SO ₂ w/o LS (ppm), calc	344.905	405.101	343.578	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 106.000

Preheat Outlet 363.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 630.000

FG Preheat Outlet 390.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 20.845

Flash Tank 2.355

Total Steam 23.200

Press. (psig): Boiler 103.000

Flash Tank 103.000

Temps. (deg F): Boiler 338.000

Flash Tank 338.000

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 24.667

Cooling (Coal + N Gas) - % 9.643

Cooling H₂O Inlet (deg F) 344.000

Coal + N. Gas - MMBtu/hr 24.667

RESULTS: Steam Gen Eff'cy (%) 83.282

Fuel to Steam Flow Corr. 0.874

Boiler Efficiency (%) 82.428

% SO₂ Reduction 21.300

Intrusion Air (#/hr) -110.02

REMARKS: TEST CONDITION: REPEAT OF TEST 401-H14

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 404-H14-2

Date: 04/16/91

PURPOSE: DEMONSTRATE SYSTEM OPERABILITY

COAL: Source: HEALY PERF BLEND

Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
 Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE:

% CaCO₃: N/A

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 11

Section: 1 OF 1

Time of Test: 12:20

FLOW RATES:

Coal PC (#/hr) 1200.000
 Carrier Air PC (scfh) 12500.000
 Combustion Air PC (kpph) 6.540
 Mix Bustle Air PC (kpph) 8.530
 Coal MC (#/hr) 2048.000
 Carrier Air MC (scfh) 21710.000
 Cmb. Air Sec Brnr (kpph) 8.650

LS (#/hr) _____
 LS Split (I/W) _____
 # Nozzles _____
 Carr'r A/LS (scfh) 0.000
 C.A. Press (psig) Edc Nzl Dia 0.375
 Nozzles (throat): _____
 Injector (tube): _____
 Ca/S Ratio N/A
 SCFH to #/hr 0.076

Total Air (#/hr) 26333.644
 Stoi Air (#/hr) 19438.784
 Xcas Air SB (#/hr) 6894.860
 Total Coal (#/hr) 3248.000
 Total Gas (#/hr) 28897.615
 % O₂ post SB Cmbn 5.212
 Coal Split PC (%) 36.946
 Ca Utilization, % _____

STOICHIOMETRIC AIR: (for Coal) 5.985
 STOICH. AIR: (# air/# tot fuel) 5.985
 PHI's: PCC phi 1.044
 PC phi 2.231
 MC phi 0.910
 Overall phi at Sec. Brnr 1.355

Cling Calc (Btu/sec) 306.000 Cling Meas (Btu/sec) 566.722 Flow #/sec 28.800
 Total flow assumed equal over all 8 circuits:
 FLUX (Btu/ft²-sec):
 #1 AI 0.581 #2 AI 1.177 #3 BAF 2.800 #4 SRS 3.432
 #5 SRS 2.379 #6 SRS 1.744 #7 PC ET 1.280 #8 TAP 0.000

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	6.100			
CO (ppm)	7.000	8.456	7.417	
NO _x (ppm)	181.000	218.658	191.789	0.328
SO ₂ w/LS (ppm)	274.000	331.007	290.333	0.691
SO ₂ w/o LS (ppm), calc	338.456	405.101	357.550	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 109.000

Preheat Outlet 361.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 642.000

FG Preheat Outlet 382.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH):

Boiler 21.430
 Press. (psig): Boiler 103.000
 Temps. (deg F): Boiler 339.000

Flash Tank 2.020
 Flash Tank 103.000
 Flash Tank 339.000

Total Steam 23.450

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 25.945
 Coal + N. Gas - MMBtu/hr 25.945

Cooling (Coal + N Gas) - % 7.864

Cooling H₂O Inlet (deg F) 343.000

RESULTS:

Steam Gen Eff'cy (%) 83.371

Fuel to Steam Flow Corr. 0.912

Boiler Efficiency (%) 82.869

% SO₂ Reduction 18.799

Intrusion Air (#/hr) 1630.23

REMARKS: TEST CONDITION: MAXIMUM LOAD (30 MMBTU/HR) AT PHI=.8, REPEAT OF TEST 401-H14 WITH HIGHER
 MEYERS VALVE SPEED, COAL FEED VALVE SPEED=24.5%, SWIRL DAMPER AT V=300 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 405-H15

Date 04/16/91

PURPOSE: DEMONSTRATE SYSTEM OPERABILITY

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988LIMESTONE: % CaCO₃: N/A

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 1

Section: 1 OF 1

Time of Test: 16:00

FLOW RATES:

Coal PC (#/hr) 1192.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.800
Mix Bustle Air PC (kpph) 7.010
Coal MC (#/hr) 1920.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 6.160LS (#/hr) _____
LS Split (I/W) _____
Nozzles _____
Carr'r A/LS (scfh) 0.000
C.A. Press (psig) Edc W21 Dia 0.375
Nozzles (throat): _____
Injector (tube): _____
Ca/S Ratio N/A
SCFH to #/hr 0.076Total Air (#/hr) 22583.644
Stoi Air (#/hr) 18624.845
Xcss Air SB (#/hr) 3958.799
Total Coal (#/hr) 3112.000
Total Gas (#/hr) 25040.257
% O₂ post SB Cmbn 3.453
Coal Split PC (%) 38.303
Ca Utilization, % _____

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.087

PC phi 2.070

MC phi 0.822

Overall phi at Sec. Brnr 1.213

Cling Calc (Btu/sec) 0.000 Cling Meas (Btu/sec) 0.000 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):#1 AI 0.000 #2 AI 0.000 #3 BAF 0.000 #4 SRS 0.000
#5 SRS 0.000 #6 SRS 0.000 #7 PC ET 0.000 #9 TAP 0.000

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
O₂ (%) 6.250
CO (ppm) 3.300 4.027 3.926
NO_x (ppm) 150.000 183.051 178.440 0.276
SO₂ w/LS (ppm) 261.000 318.508 310.485 0.668
SO₂ w/o LS (ppm), calc 335.231 405.101 395.351

AIR TEMPERATURES (deg F):

Air Preheat Inlet _____

Preheat Outlet _____

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet _____

FG Preheat Outlet _____

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 20.690

Flash Tank _____

Total Steam 20.690

Press. (psig): Boiler 103.000

Flash Tank 103.000

Temps. (deg F): Boiler _____

Flash Tank _____

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 24.859

Cooling (Coal + N Gas) - % 0.000

Cooling H₂O Inlet (deg F) _____

Coal + N. Gas - MMBtu/hr 24.859

RESULTS: Steam Gen Eff'cy (%) 95.425

Fuel to Steam Flow Corr. 1.135

Boiler Efficiency (%) 96.408

% SO₂ Reduction 21.466

Intrusion Air (#/hr) 4490.68

REMARKS: TEST CONDITION: MAXIMUM LOAD (30 MMBTU/HR) AT PHI=.9

COAL FEED VALVE SPEED = 24.5%, SWIRL DAMPER AT 300 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 406-H16

Date 04/17/91

PURPOSE: DEMONSTRATE SYSTEM OPERABILITY

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988LIMESTONE: % CaCO₃: N/A NATURAL GAS: Btu/lb _____ Stoich air (# air/# NG): _____
Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 31

Section: 1 OF 1

Time of Test: 10:00

FLOW RATES:

Coal PC (#/hr) 1491.500
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.290
Mix Bustle Air PC (kpph) 11.250
Coal MC (#/hr) 2228.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 6.935LS (#/hr) _____
LS Split (I/W) _____
Nozzles _____
Carr'r A/LS (scfh) 0.000
C.A. Press (psig) Edc Nzl Dia 0.375
Nozzles (throat): _____
Injector (tube): _____
Ca/S Ratio N/A
SCFH to #/hr 0.076Total Air (#/hr) 27088.644
Stoi Air (#/hr) 22260.640
Xcss Air SB (#/hr) 4828.004
Total Coal (#/hr) 3719.500
Total Gas (#/hr) 30024.817
% O₂ post SB Cmbn 3.512
Coal Split PC (%) 40.099
Ca Utilization, % _____STOICHIOMETRIC AIR: (for Coal) 5.985
STOICH. AIR: (# air/# tot fuel) 5.985
PHI's: PCC phi 0.812
PC phi 2.072
MC phi 0.905
Overall phi at Sec. Brnr 1.217Cling Calc (Btu/sec) 401.400 Cling Meas (Btu/sec) 580.750 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:
FLUX (Btu/ft²-sec):
#1 AI 0.218 #2 AI 0.765 #3 BAF 4.200 #4 SRS 5.719
#5 SRS 3.885 #6 SRS 1.824 #7 PC ET 1.494 #9 TAP 0.227

EMISSIONS:

At stark As meas.
O₂ (%) 6.300
CO (ppm) 12.000
NO_x (ppm) 190.500
SO₂ w/LS (ppm) 274.500
SO₂ w/o LS (ppm), calc 334.157At 3% O₂ At Calc SB O₂ #/MMBtu
14.694 14.276
233.265 226.624 0.351
336.122 326.553 0.705
405.101 394.082

AIR TEMPERATURES (deg F):

Air Preheat Inlet 100.500 Preheat Outlet 368.500 Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 653.500 FG Preheat Outlet 394.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 21.165
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 336.500Flash Tank 2.070 Total Steam 23.235
Flash Tank 103.000
Flash Tank 336.500 Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 29.711 Cooling (Coal + N Gas) - % 7.037 Cooling H₂O Inlet (deg F) 341.500
Coal + N. Gas - MMBtu/hr 29.711

RESULTS: Steam Gen Eff'cy (%) 82.879 Fuel to Steam Flow Corr. 1.050

Boiler Efficiency (%) 82.488 % SO₂ Reduction 17.136 Intrusion Air (#/hr) 5384.46REMARKS: TEST CONDITION: MAXIMUM LOAD (30 MMBTU/HR) AT PHI=.9
COAL VALVE SPEED = 24.5%

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 407-H17

Date 04/17/91

PURPOSE: DEMONSTRATE SYSTEM OPERABILITY

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE:

% CaCO₃: N/A

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 36

Section: 1 OF 1

Time of Test: 13:00

FLOW RATES:

Coal PC (#/hr) 1367.500

Carrier Air PC (scfh) 12500.000

Combustion Air PC (kpph) 6.365

Mix Bustle Air PC (kpph) 9.155

Coal MC (#/hr) 2399.000

Carrier Air MC (scfh) 21710.000

Cmbn Air Sec Brnr (kpph) 9.055

LS (#/hr) _____

LS Split (I/W) _____

Nozzles _____

Carr'r A/LS (scfh) 0.000

C.A. Press (psig) Edc Wzl Dia 0.375

Nozzles (throat): _____

Injector (tube): _____

Ca/S Ratio N/A

SCFH to #/hr 0.076

Total Air (#/hr) 27182.644

Stoi Air (#/hr) 22541.927

Xcss Air SB (#/hr) 4646.717

Total Coal (#/hr) 3766.500

Total Gas (#/hr) 30161.919

± O₂ post SB Cmbn 3.365

Coal Split PC (%) 36.307

Ca Utilization, % _____

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 0.894

PC phi 2.013

MC phi 0.804

Overall phi at Sec. Brnr 1.206

Cling Calc (Btu/sec) 273.600 Cling Meas (Btu/sec) 547.083 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI 0.363 #2 AI 0.706 #3 BAF 2.916 #4 SRS 3.187

#5 SRS 2.537 #6 SRS 1.348 #7 PC ET 1.067 #9 TAP 0.454

EMISSIONS:

At stack As meas.

O₂ (%) 5.900

CO (ppm) 88.000

NOx (ppm) 200.500

SO₂ w/LS (ppm) 282.000SO₂ w/o LS (ppm), calc 342.756At 3% O₂At Calc SB O₂

#/MMBtu

104.901

102.772

239.007

234.157

0.360

336.159

329.338

0.705

405.101

397.248

AIR TEMPERATURES (deg F):

Air Preheat Inlet 102.500

Preheat Outlet 377.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 662.500 FG Preheat Outlet 397.500

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 21.685

Press. (psig): Boiler 103.000

Temps. (deg F): Boiler 340.000

Flash Tank 1.950

Flash Tank 103.000

Flash Tank 340.000

Total Steam 23.635

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 30.087

Coal + N. Gas - MMBtu/hr 30.087

Cooling (Coal + N Gas) - % 6.546

Cooling H₂O Inlet (deg F) 344.500

RESULTS: Steam Gen Eff'cy (%) 82.995

Fuel to Steam Flow Corr. 1.046

Boiler Efficiency (%) 82.708

% SO₂ Reduction 17.095

Intrusion Air (#/hr) 4795.21

REMARKS: TEST CONDITION: MAXIMUM LOAD (30 MMBTU/HR) AT PHI=.8

COAL VALVE SPEED = 24.5%

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 402-H18

Date 04/17/91

PURPOSE: DEMONSTRATE SYSTEM OPERABILITY

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE:

% CaCO₃: N/A

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 14

Section: 1 OF 1

Time of Test: 17:00

FLOW RATES:

Coal PC (#/hr) 1272.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.280
Mix Bustle Air PC (kpph) 11.430
Coal MC (#/hr) 2561.000
Carrier Air MC (scfh) 21710.000
Cbn Air Sec Brnr (kpph) 7.150LS (#/hr) _____
LS Split (I/N) _____
Nozzles _____
Carr'r A/LS (scfh) 0.000
C.A. Press (psig) Edc Wzl Dia 0.375
Nozzles (throat): _____
Injector (tube): _____
Ca/S Ratio N/A
SCFH to #/hr 0.076Total Air (#/hr) 27473.644
Stoi Air (#/hr) 22939.920
Xcss Air SB (#/hr) 4533.724
Total Coal (#/hr) 3833.000
Total Gas (#/hr) 30499.414
% O₂ post: SB Cbn 3.247
Coal Split PC (%) 33.185
Ca Utilization, % _____STOICHIOMETRIC AIR: (for Coal) 5.985
STOICH. AIR: (# air/# tot fuel) 5.985
PHI's: PCC phi 0.950
PC phi 2.452
MC phi 0.886
Overall phi at Sec. Brnr 1.198Cling Calc (Btu/sec) 0.000 Cling Meas (Btu/sec) 0.000 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:
FLUX (Btu/ft²-sec):
#1 AI 0.000 #2 AI 0.000 #3 BAF 0.000 #4 SRS 0.000
#5 SRS 0.000 #6 SRS 0.000 #7 PC ET 0.000 #9 TAP 0.000

EMISSIONS:

At stack As meas.
O₂ (%) 6.900
CO (ppm) 1.300
NOx (ppm) 212.000
SO₂ w/LS (ppm) 267.000
SO₂ w/o LS (ppm), calc 321.258At 3% O₂ At Calc SB O₂ #/MMBtu
1.660 1.637
270.638 266.924 0.408
340.851 336.173 0.715
405.101 399.788

AIR TEMPERATURES (deg F):

Air Preheat Inlet _____

Preheat Outlet _____

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet _____

FG Preheat Outlet _____

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____

% of Total Load: N/A

STEAMS (KPPH): Boiler 22.210
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler _____Flash Tank _____
Flash Tank 103.000
Flash Tank _____

Total Steam 22.210

Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 30.618
Coal + N. Gas - MMBtu/hr 30.618

Cooling (Coal + N Gas) - % 0.000

Cooling H₂O Inlet (deg F) _____

RESULTS: Steam Gen Eff'cy (%) 95.520

Fuel to Steam Flow Corr. 1.303

Boiler Efficiency (%) 96.504

% SO₂ Reduction 15.912

Intrusion Air (#/hr) 7455.45

REMARKS: TEST CONDITION: MAXIMUM LOAD (35 MMBTU/HR) AT PHI=.9

COAL VALVE SPEED = 24.5%

WREATH	S02	S02	LS	CA/S	S	S02	PC	TOT	COOL	BLR	FUEL	HEAT	HEAT	FLX 1	FLX 2	FLX 3	FLX 4	FLX 5	FLX 6	FLX 7	FLX 8	COMMENTS:		
TESTS	Q33	W/O	PPM	LS	W/M	RATIO	LS	W/O	PPM	LS	W/M	RATIO	LS	W/O	PPM	LS	W/O	PPM	LS	W/O	PPM	LS	W/O	PPM
500-820	259	404	60.0	2.85	0.34	36.2	2120	10.0	19.0	82.7	0.93	1052	3.19	4.94	0.97	4.74	4.76	6.82	3.31	1.30	STIRL VELOCITY AT 250 FT/S, NIMO COLLECT			
501-821	280	405	55.5	1.71	0.34	30.0	2050	10.3	9.3	82.0	1.00	572	1.02	2.12	2.51	3.27	2.54	2.22	2.56	1.30	STIRL VELOCITY AT 250 FT/S, NIMO COLLECT			
502-822	405	405	50.0	1.75	0.34		1920	10.0													STIRL VELOCITY AT 250 FT/S, NIMO COLLECT			
503-823	330	405	36.0	1.25	0.34	18.4	1950	10.1													STIRL VELOCITY AT 250 FT/S, NIMO COLLECT			
504-824	339	405	30.0	1.02	0.34	8.7	1050	17.6	11.4	82.6	0.94	631	1.30	1.77	2.00	2.06	2.30	1.98	1.17	1.13	STIRL VELOCITY AT 300 FT/S, NIMO COLLECT			
505-825	325	405	33.0	1.13	0.34	19.6	1020	17.7	11.0	81.6	0.92	606	0.87	1.65	3.27	3.27	2.54	3.01	1.71	0.91	STIRL VELOCITY AT 300 FT/S, NIMO COLLECT			
506-826	352	405	34.0	1.16	0.34	12.0	2200	16.7													STIRL VELOCITY AT 315 FT/S, NIMO COLLECT			
507-827	321	405	36.0	1.23	0.34	28.6	2200	18.2													STIRL VELOCITY AT 300 FT/S, NIMO COLLECT			
508-828	365	405	10.0	1.22	0.34	9.6	2150	17.0	10.2	81.7	0.96	570	0.90	1.06	3.27	3.76	3.17	2.30	1.71	0.91	STIRL VELOCITY AT 300 FT/S, NIMO COLLECT			
509-829	336	405	11.0	1.16	0.34	16.0	2150	17.0	12.7	79.9	0.90	704	0.73	1.29	3.91	4.09	4.12	2.54	2.03	1.30	STIRL VELOCITY AT 400 FT/S, NIMO COLLECT			
510-830	328	405	17.3	1.17	0.34	18.9	2200	10.4	10.1	80.2	0.87	581	0.51	1.07	3.27	3.04	3.01	2.22	1.01	0.23	STIRL VELOCITY AT 400 FT/S, NIMO COLLECT			
511-831	326	405	17.0	1.17	0.34	19.2	2250	17.0													STIRL VELOCITY AT 400 FT/S, NIMO COLLECT			
512-832	355	405	10.0	1.24	0.34	12.0	2250	10.0	10.3	80.3	0.89	570	0.44	1.10	2.33	3.10	2.30	2.00	1.71	0.91	STIRL VELOCITY AT 400 FT/S, NIMO COLLECT			
513-833	282	405	47.7	1.02	0.34	37.3	2150	17.5	9.8	81.9	0.94	547	1.29	0.92	2.29	3.24	2.03	2.19	2.54	0.62	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
514-834	240	405	48.0	1.02	0.34	30.3	2150	10.1	10.2	81.3	0.91	575	0.87	1.06	2.22	3.27	2.22	2.22	2.24	1.21	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
515-835	189	405	49.0	1.09	0.34	50.0	2200	17.0	8.0	81.4	0.95	409	0.85	1.00	2.15	2.01	2.30	2.03	2.22	0.54	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
516-836	182	405	50.4	1.71	0.34	56.7	2150	15.6	10.2	81.3	1.05	510	0.50	1.29	2.00	3.76	3.33	2.06	2.36	0.45	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
517-837	193	405	48.0	1.05	0.34	52.1	2150	16.9	10.0	81.0	0.95	508	0.32	1.00	2.92	3.00	2.05	2.06	2.51	0.00	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
518-838	201	405	49.0	1.05	0.34	50.3	2200	17.0	9.3	81.2	0.93	522	0.22	0.82	3.19	2.30	2.14	2.24	0.00	CONTINUE NIMO COLLECTION AT MEDIUM LOAD				
519-839	221	405	50.3	1.71	0.34	45.3	2200	10.0	10.4	81.4	0.90	510	0.32	0.74	2.68	4.09	2.02	2.05	2.40	-0.77	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
520-840	229	405	48.0	1.01	0.34	45.4	2200	17.5	10.0	82.2	0.95	409	0.44	1.10	3.93	3.92	3.01	2.00	2.24	0.45	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
521-841	213	405	48.0	1.30	0.34	47.1	2200	17.7	11.2	80.7	0.92	625	0.44	1.41	3.27	4.09	2.05	2.22	2.35	0.45	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
522-842	177	405	50.0	1.72	0.34	56.2	2150	17.2	11.1	80.6	0.93	409	0.29	1.29	2.00	4.09	2.70	2.54	2.24	0.00	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
523-843	195	405	42.5	1.40	0.34	51.5	2200	16.9	9.6	80.7	0.95	527	0.51	1.12	2.33	3.43	2.06	2.54	2.24	0.00	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
524-844	189	405	47.0	1.39	0.34	52.9	2200	17.0	9.4	80.5	0.91	525	0.44	1.06	2.57	3.27	2.22	2.30	2.24	0.45	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
525-845	197	405	51.0	1.73	0.34	51.0	2250	17.0	9.1	81.6	0.92	508	0.29	1.24	2.00	3.19	2.14	1.90	2.00	0.23	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
526-846	186	405	52.0	1.79	0.34	53.7	2150	16.7	9.0	81.4	0.90	527	0.51	0.90	2.52	3.32	3.22	1.95	2.30	0.14	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
527-847	196	405	51.0	1.76	0.34	51.4	2150	17.1	11.5	80.9	0.94	631	0.50	1.10	3.27	3.92	3.33	3.01	2.07	0.00	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
528-848	172	405	50.0	1.71	0.34	51.4	2200	17.3	9.0	81.3	0.93	542	0.57	1.17	2.70	3.91	3.07	2.00	2.81	0.41	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
529-849	175	405	52.5	1.78	0.34	56.4	2200	16.5	8.0	83.3	1.01	409	0.44	1.29	3.27	4.09	2.05	2.30	2.24	0.00	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
530-850	210	405	47.0	1.59	0.34	47.9	2200	17.5	11.4	80.6	0.93	600	0.44	1.10	3.27	4.50	3.17	2.70	3.31	-0.45	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
531-851	189	405	51.6	1.76	0.34	52.9	2150	16.4	12.0	80.6	0.80	655	1.02	1.29	3.50	4.90	3.01	3.01	2.99	0.00	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
532-852	197	405	51.0	1.77	0.34	51.1	2200	15.9	10.4	80.5	1.00	500	0.50	1.06	2.00	4.25	3.65	2.54	2.07	0.00	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
533-853	197	405	51.0	1.77	0.34	51.1	2200	15.9	10.4	80.5	1.00	500	0.50	1.06	2.00	4.25	3.65	2.54	2.07	0.00	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
534-854	194	405	48.9	1.69	0.34	51.9	2150	17.9	10.5	80.9	0.89	575	0.55	1.04	3.45	4.30	3.77	2.82	2.75	-0.54	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
535-855	181	405	48.0	1.63	0.34	55.2	2150	19.4	11.0	81.3	0.84	614	0.73	1.41	4.42	4.09	3.96	2.54	2.45	0.00	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
536-856	208	405	47.6	1.61	0.34	48.4	2200	17.4	9.9	81.4	0.94	553	1.10	1.06	2.73	3.06	2.75	2.35	2.19	0.23	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
537-857	181	405	48.5	1.66	0.34	55.1	2150	16.5	9.5	80.9	0.90	523	0.76	1.50	2.70	3.72	2.50	2.50	2.21	1.25	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
538-858	186	405	50.0	1.72	0.34	53.0	2150	16.9	9.8	82.9	0.97	527	0.87	1.01	2.57	3.43	2.30	2.54	2.19	0.91	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
539-859	199	405	50.5	1.75	0.34	50.5	2200	16.9	9.6	81.0	0.95	400	0.80	1.24	2.45	3.35	2.62	2.46	2.19	0.00	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
540-860	223	405	50.0	1.70	0.34	44.7	2150	16.5	9.0	81.9	0.96	504	0.40	1.33	2.61	3.40	2.65	2.05	2.19	0.54	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
541-861	206	405	48.5	1.70	0.34	34.1	2150	16.0	8.0	81.9	0.96	403	0.29	1.41	2.33	2.94	2.70	2.70	2.13	0.45	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
542-862	187	405	48.0	1.71	0.34	54.0	2100	10.5	8.0	81.1	0.85	476	0.44	1.29	2.57	3.43	2.70	2.30	2.24	0.45	CONTINUE NIMO COLLECTION AT MEDIUM LOAD			
543-863																								
AVG	238	405	47.0	1.60	0.30	41.1	2143	17.4	10.4	81.4	0.94	577	0.70	1.30	2.97	3.59	2.92	2.53	2.37	0.44				

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 500-H2O

Date 04/22/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 111

Section: 1 OF 1

Time of Test: 15:00

FLOW RATES:

Coal PC (#/hr) 1000.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 5.040
Mix Bustle Air PC (kpph) 5.590
Coal MC (#/hr) 1496.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 4.180LS (#/hr) 60.000
LS Split (I/M) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Nzl Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 2.049
SCFH to #/hr 0.076Total Air (#/hr) 18152.521
Stoi Air (#/hr) 14932.179
Xcss Air SB (#/hr) 3214.342
Total Coal (#/hr) 2496.000
Total Gas (#/hr) 20149.724
% O₂ post SB Cmbn 3.485
Coal Split PC (%) 40.064
Ca Utilization, % 17.641STOICHIOMETRIC AIR: (for Coal) 5.985
STOICH. AIR: (# air/# tot fuel) 5.985
PHI's: PCC phi 1.002
PC phi 1.936
MC phi 0.887
Overall phi at Sec. Brnr 1.166Cling Calc (Btu/sec) 813.600 Cling Meas (Btu/sec) 1052.083 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:FLUX (Btu/ft²-sec):#1 AI 3.194 #2 AI 4.944 #3 BAF 6.066 #4 SRS 4.739
#5 SRS 4.758 #6 SRS 6.819 #7 PC ET 3.308 #9 TAP 1.362

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
O₂ (%) 6.450
CO (ppm) 19.450 24.062 23.414
NOx (ppm) 132.540 163.967 159.553 0.247
SO₂ w/LS (ppm) 209.000 258.557 251.596 0.543
SOx w/o LS (ppm), calc 330.407 404.458 394.056

AIR TEMPERATURES (deg F):

Air Preheat Inlet 114.000

Preheat Outlet 299.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 491.000

FG Preheat Outlet 318.000

NATURAL GAS INPUTS:

M. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 14.240
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 336.000Flash Tank 3.750 Total Steam 17.990
Flash Tank 103.000
Flash Tank 336.000 Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 19.938
Coal + N. Gas - MMBtu/hr 19.938Cooling (Coal + N Gas) - % 18.936 Cooling H₂O Inlet (deg F) 340.000

RESULTS: Steam Gen Eff'cy (%) 84.985

Fuel to Steam Flow Corr. 0.930

Boiler Efficiency (%) 82.732

% SO₂ Reduction 36.152

Intrusion Air (#/hr) 3881.60

REMARKS: TEST CONDITION: 20 MMBTU/HR, PHI=1, MAXIMUM DURATION, SWIRL DAMPER AT 250 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 501-H21

Date 04/22/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CARTWELL

% CaCO₃: 90.400NATURAL GAS: Btu/lb _____
Hydrogen (# H₂/# NG): _____

Stoich air (# air/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 141

Section: 1 OF 1

Time of Test: 19:00

FLOW RATES:

Coal PC (#/hr) 1105.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 5.340
Mix Bustle Air PC (kpph) 7.260
Coal MC (#/hr) 1667.000
Carrier Air MC (scfh) 21710.000
Comb Air Sec Brnr (kpph) 3.190LS (#/hr) 55.500
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Nzl Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.707
SCFH to #/hr 0.076Total Air (#/hr) 19132.521
Stoi Air (#/hr) 16589.997
Xcss Air SB (#/hr) 2542.524
Total Coal (#/hr) 2772.000
Total Gas (#/hr) 21345.584
% O₂ post SB Cmbn 2.602
Coal Split PC (%) 39.863
Ca Utilization, % 18.027

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 0.952

PC phi 2.050

MC phi 0.917

Overall phi at Sec. Brnr 1.109

Cling Calc (Btu/sec) 406.800 Cling Meas (Btu/sec) 572.333 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):#1 AI 1.016 #2 AI 2.119 #3 BAF 2.566 #4 SRS 3.268
#5 SRS 2.537 #6 SRS 2.220 #7 PC ET 2.561 #8 TAP 1.362

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
O₂ (%) 6.590
CO (ppm) 2.820 3.523 3.600
NOx (ppm) 123.000 153.643 157.042 0.232
SO₂ w/LS (ppm) 224.000 279.806 285.995 0.589
SOx w/o LS (ppm), calc 327.489 404.565 413.112

AIR TEMPERATURES (deg F):

Air Preheat Inlet 111.000

Preheat Outlet 349.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 533.000

FG Preheat Outlet 365.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 16.290
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 336.000Flash Tank 2.040 Total Steam 18.330
Flash Tank 103.000
Flash Tank 336.000 Feed H₂O (deg F) 212.000COMBUSTOP LOADS: Coal - MMBtu/hr 22.143
Coal + N. Gas - MMBtu/hr 22.143Cooling (Coal + N Gas) - % 9.305 Cooling H₂O Inlet (deg F) 340.000

RESULTS: Stear Gen Eff'cy (%) 83.438

Fuel to Stear Flow Corr. 0.998

Boiler Efficiency (%) 82.845

% SO₂ Reduction 30.771

Intrusion Air (#/hr) 5580.87

REMARKS: TEST CONDITION: 20 MMBTU/HR, PHI=1, MAXIMUM DURATION, SWIRL DAMPER AT 250 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 502-H22

Date 04/23/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400NATURAL GAS: Btu/lb _____
Hydrogen (# H₂/# NG): _____

Stoich air (# air/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 169

Section: 1 OF 1

Time of Test: 11:00

FLOW RATES:

Coal PC (#/hr) 970.700
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 4.793
Mix Bustle Air PC (kpph) 7.253
Coal MC (#/hr) 1464.700
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 1.373LS (#/hr) 50.000
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Nz1 Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.750
SCFH to #/hr 0.076Total Air (#/hr) 16762.121
Stoi Air (#/hr) 14575.497
Xcss Air SB (#/hr) 2186.623
Total Coal (#/hr) 2435.400
Total Gas (#/hr) 18707.009
% O₂ post SB Cmbn 2.553
Coal Split PC (%) 39.858
Ca Utilization, % 57.134STOICHIOMETRIC AIR: (for Coal) 5.985
STOICH. AIR: (# air/# tot fuel) 5.985
PHI's: PCC phi 0.989
PC phi 2.238
MC phi 1.006
Overall phi at Sec. Brnr 1.100Cling Calc (Btu/sec) 0.000 Cling Meas (Btu/sec) 0.000 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:FLUX (Btu/ft²-sec):#1 AI 0.000 #2 AI 0.000 #3 BAF 0.000 #4 SRS 0.000
#5 SRS 0.000 #6 SRS 0.000 #7 PC ET 0.000 #9 TAP 0.000

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
O₂ (%) 6.633
CO (ppm) 11.110 13.919 14.265
NOx (ppm) 0.000 0.000 0.000
SO₂ w/LS (ppm) 0.000 0.000 0.000
SOx w/o LS (ppm), calc 326.555 404.552 414.141

AIR TEMPERATURES (deg F):

Air Preheat Inlet 124.000

Preheat Outlet 326.330

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 505.330

FG Preheat Outlet 341.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 16.840
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler _____Flash Tank _____
Flash Tank 103.000
Flash Tank _____

Total Steam 16.840

Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 19.454
Coal + N. Gas - MMBtu/hr 19.454

Cooling (Coal + N Gas) - % 0.000

Cooling H₂O Inlet (deg F) _____

RESULTS: Steam Gen Eff'cy (%) 84.190

Fuel to Steam Flow Corr. 0.963

Boiler Efficiency (%) 85.232

% SO₂ Reduction 100.000

Intrusion Air (#/hr) 5017.47

REMARKS: TEST CONDITION: 20 MMBTU/HR, PHI=1, MAXIMUM DURATION, SWIRL DAMPER AT 250 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 503-H23

Date 04/23/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400NATURAL GAS: Btu/lb _____
Hydrogen (# H₂/# NG): _____

Stoich air (# air/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 178

Section: _____ Time of Test: 16:30

FLOW RATES:

Coal PC (#/hr) 976.700
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 5.250
Mix Bustle Air PC (kpph) 7.450
Coal MC (#/hr) 1472.300
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 1.000

LS (#/hr) 36.000

LS Split (I/W) 100/0

Nozzles _____

Carr'r A/LS (scfh) 9540.270

C.A. Press (psig) Edc Nz1 Dia 0.375

Nozzles (throat): _____

Injector (tube): 50.000

Ca/S Ratio 1.253

SCFH to #/hr 0.076

Total Air (#/hr) 17042.521

Stoi Air (#/hr) 14656.891

Xcss Air SB (#/hr) 2385.630

Total Coal (#/hr) 2449.000

Total Gas (#/hr) 18991.878

% O₂ post SB Cmbn 2.744

Coal Split PC (%) 39.882

Ca Utilization, % 14.701

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.062

PC phi 2.336

MC phi 1.045

Overall phi at Sec. Brnr 1.113

Cling Calc (Btu/sec) 0.000 Cling Meas (Btu/sec) 0.000 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI 0.000 #2 AI 0.000 #3 BAF 0.000 #4 SRS 0.000

#5 SRS 0.000 #6 SRS 0.000 #7 PC ET 0.000 #9 TAP 0.000

EMISSIONS:

At stack As meas.

O₂ (%) 6.270

CO (ppm) 6.700

NOx (ppm) 163.000

SO₂ w/LS (ppm) 270.000

SOx w/o LS (ppm), calc 334.477

At 3% O₂

8.187

199.185

329.939

404.708

At Calc SB O₂

8.304

202.020

334.634

410.207

#/MMBtu

0.301

0.694

AIR TEMPERATURES (deg F):

Air Preheat Inlet 124.700

Preheat Outlet 353.700

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 544.300

FG Preheat Outlet 367.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 18.140

Press. (psig): Boiler 103.000

Temps. (deg F): Boiler _____

Flash Tank _____

Flash Tank 103.000

Flash Tank _____

Total Steam 18.140

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 19.563

Coal + N. Gas - MMBtu/hr 19.563

Cooling (Coal + N Gas) - % 0.000

Cooling H₂O Inlet (deg F) _____

RESULTS: Steam Gen Eff'cy (%) 83.601

Fuel to Steam Flow Corr. 0.892

Boiler Efficiency (%) 84.588

% SO₂ Reduction 18.423

Intrusion Air (#/hr) 4300.05

REMARKS: TEST CONDITION: 20 MMBTU/HR, PHI=1, MAXIMUM DURATION, SWIRL DAMPER AT 250 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 504-H24 Date 04/24/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7986

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 117

Section: _____ Time of Test: 21:15

FLOW RATES:

Coal PC (#/hr) 953.500
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 5.100
Mix Bustle Air PC (kpph) 7.380
Coal MC (#/hr) 1546.500
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 1.015

LS (#/hr) 30.000

LS Split (I/W) 100/0

Nozzles _____

Carr'r A/LS (scfh) 9540.270

C.A. Press (psig) Edc Nzl Dia 0.375

Nozzles (throat): _____

Injector (tube): 50.000

Ca/S Ratio 1.023

SCFH to #/hr 0.076

Total Air (#/hr) 16837.521

Stoi Air (#/hr) 14962.118

Xcas Air SB (#/hr) 1875.402

Total Coal (#/hr) 2500.000

Total Gas (#/hr) 18824.451

% O₂ post SB Cmbn 2.176

Coal Split PC (%) 38.140

Ca Utilization, % 8.547

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.061

PC phi 2.354

MC phi 1.009

Overall phi at Sec. Brnr 1.077

Cling Calc (Btu/sec) 340.200 Clng Meas (Btu/sec) 631.250 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI 1.379 #2 AI 1.766 #3 BAF 2.800 #4 SRS 2.860

#5 SRS 2.300 #6 SRS 1.982 #7 PC ET 1.174 #9 TAP 1.135

EMISSIONS:

At stack As meas.

O₂ (%) 6.450

CO (ppm) 5.700

NOx (ppm) 187.500

SO₂ w/LS (ppm) 298.000

SOx w/c LS (ppm), calc 330.670

At 3% O₂

7.052

231.959

368.660

404.780

At Calc SB O₂

7.374

242.575

385.532

422.474

#/MMBtu

0.351

0.776

AIR TEMPERATURES (deg F):

Air Preheat Inlet 114.000

Preheat Outlet 334.500

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 549.000

FG Preheat Outlet 364.500

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____

% of Total Load: N/A

STEAMS (KPPH): Boiler 15.305

Flash Tank 2.250

Total Steam 17.555

Press. (psig): Boiler 103.000

Flash Tank 103.000

Temps. (deg F): Boiler 339.000

Flash Tank 339.000

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 19.970

Cooling (Coal + N Gas) - % 11.380

Cooling H₂O Inlet (deg F) 343.500

Coal + N. Gas - MMBtu/hr 19.970

RESULTS: Steam Gen Eff'cy (%) 83.614

Fuel to Steam Flow Corr. 0.940

Boiler Efficiency (%) 82.564

% SO₂ Reduction 8.744

Intrusion Air (#/hr) 5226.27

REMARKS: TEST CONDITION: 20 MMBTU/HR, PHI=1, MAXIMUM DURATION, SWIRL DAMPER AT 330 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1
Date: 5/16/91

TEST: 505-H25

Date 04/25/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR MIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 16.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400NATURAL GAS: Btu/lb _____
Hydrogen (# H₂/# NG): _____

Stoich air (# air/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 149

Section: _____ Time of Test: 1:45

FLOW RATES:

Coal PC (#/hr) 799.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 5.130
Mix Bustle Air PC (kpph) 7.480
Coal MC (#/hr) 1684.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 1.190LS (#/hr) 33.000
LS Split (I/N) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Nzl Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.133
SCFH to #/hr 0.076Total Air (#/hr) 17142.521
Stoi Air (#/hr) 14860.376
Xcss Air SB (#/hr) 2282.145
Total Coal (#/hr) 2483.000
Total Gas (#/hr) 19117.374
% O₂ post SB Cmbn 2.608
Coal Split PC (%) 32.179
Ca Utilization, % 17.295STOICHIOMETRIC AIR: (for Coal) 5.985
STOICH. AIR: (# air/# tot fuel) 5.985
PHI's: PCC phi 1.273
PC phi 2.837
MC phi 1.024
Overall phi at Sec. Brnr 1.105Cing Calc (Btu/sec) 385.200 Cing Meas (Btu/sec) 606.000 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:
FLUX (Btu/ft²-sec):
#1 AI 0.871 #2 AI 1.648 #3 BAF 3.266 #4 SRS 3.268
#5 SRS 2.537 #6 SRS 3.013 #7 PC ET 1.707 #9 TAP 0.908

EMISSIONS:

At stack As meas.
O₂ (%) 6.550
CO (ppm) 3.180
NOx (ppm) 181.000
SO₂ w/LS (ppm) 261.000
SOx w/o LS (ppm), calc 328.494At 3% O₂ At Calc SB O₂ #/MMBtu
3.861 4.048
225.467 230.382 0.340
325.121 332.209 0.684
404.745 413.172

AIR TEMPERATURES (deg F):

Air Preheat Inlet 115.000

Preheat Outlet 372.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 569.000

FG Preheat Outlet 392.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.490
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 338.000Flash Tank 2.160
Flash Tank 103.000
Flash Tank 338.000

Total Steam 17.650

Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 19.834
Coal + N. Gas - MMBtu/hr 19.834

Cooling (Coal + N Gas) - % 10.999

Cooling H₂O Inlet (deg F) 342.000

RESULTS: Steam Gen Eff'cy (%) 82.656

Fuel to Steam Flow Corr. 0.918

Boiler Efficiency (%) 81.562

% SO₂ Reduction 19.596

Intrusion Air (#/hr) 4928.04

REMARKS: TEST CONDITION: 20 MMBTU/HR, PHI=1, MAXIMUM DURATION, SWIRL DAMPER AT 330 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1
Date: 5/16/91TEST: 507-H27 Date 04/25/91
PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIROCOAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 16.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 117

Section: _____ Time of Test: 10:20

FLOW RATES:

Coal PC (#/hr) 1160.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.300
Mix Bustle Air PC (kpph) 5.450
Coal MC (#/hr) 1331.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 0.850LS (#/hr) 34.000
LS Split (I/N) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc N21 Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.164
SCFH to #/hr 0.076Total Air (#/hr) 15942.521
Stoi Air (#/hr) 14908.255
Xcss Air SB (#/hr) 1034.266
Total Coal (#/hr) 2491.000
Total Gas (#/hr) 17924.137
% O₂ post SB Cmbn 1.260
Coal Split PC (%) 46.568
Ca Utilization, % 10.998

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.045

PC phi 1.830

MC phi 0.963

Overall phi at Sec. Brnr 1.020

Cling Calc (Btu/sec) 0.000 Cling Meas (Btu/sec) 0.000 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:FLUX (Btu/ft²-sec):#1 AI 0.000 #2 AI 0.000 #3 BAF 0.000 #4 SRS 0.000
#5 SRS 0.000 #6 SRS 0.000 #7 PC ET 0.000 #9 TAP 0.000

EMISSIONS:

At stack As meas.
O₂ (%) 6.100
CO (ppm) 84.600
NOx (ppm) 182.000
SO₂ w/LS (ppm) 291.000
SOx w/o LS (ppm), calc 338.151At 3% O₂ At Calc SB O₂ #/MMBtu
78.040 85.582
219.866 241.114 0.333
351.544 385.518 0.742
404.736 442.097

AIR TEMPERATURES (deg F):

Air Preheat Inlet _____

Preheat Outlet _____

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet _____

FG Preheat Outlet _____

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 16.700
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler _____Flash Tank _____
Flash Tank 103.000
Flash Tank _____

Total Steam 16.700

Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 19.898
Coal + N. Gas - MMBtu/hr 19.898

Cooling (Coal + N Gas) - % 0.000

Cooling H₂O Inlet (deg F) _____

RESULTS: Steam Gen Eff'cy (%) 95.275 Fuel to Steam Flow Corr. 1.124

Boiler Efficiency (%) 96.385 % SO₂ Reduction 12.798 Intrusion Air (#/hr) 5509.80

REMARKS: TEST CONDITION: 20 MMBTU/HR, PHI=1, MAXIMUM DURATION, SWIRL DAMPER AT 375 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 508-H28 Date 04/25/91
 PURPOSE: GENERATE 5 TONS /F BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
 Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
 Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL % CaCO₃: 90.400 NATURAL GAS: Btu/lb _____ Stoich air (# air/# NG): _____
 Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 146

Section: _____ Time of Test: 14:30

FLOW RATES:

Coal PC (#/hr)	1162.000	LS (#/hr)	36.000	Total Air (#/hr)	16492.521
Carrier Air PC (scfh)	12500.000	LS Split (I/W)	100/0	Stoi Air (#/hr)	14928.005
Combustion Air PC (kpph)	6.120	# Nozzles	_____	Xcss Air SB (#/hr)	1564.516
Mix Bustle Air PC (kpph)	5.720	Carr'r A/LS (scfh)	9540.270	Total Coal (#/hr)	2494.300
Coal MC (#/hr)	1332.300	C.A. Press (psig)	Edc Nz1 Dia	Total Gas (#/hr)	13477.638
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% O ₂ post SB Cmbn	1.850
Cmbn Air Sec Brnr (kpph)	1.310	Injector (tube):	50.000	Coal Split PC (%)	46.586
		Ca/S Ratio	1.230	Ca Utilization, %	16.732
		SCFH to #/hr	0.076		

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.017

PC phi 1.840

MC phi 0.968

Overall phi at Sec. Brnr 1.056

Cling Calc (Btu/sec) 0.000 Clng Meas (Btu/sec) 0.000 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI	0.000	#2 AI	0.000	#3 BAF	0.000	#4 SRS	0.000
#5 SRS	0.000	#6 SRS	0.000	#7 PC ET	0.000	#9 TAP	0.000

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	5.933			
CO (ppm)	11.433	13.659	14.532	
NOx (ppm)	165.000	197.120	299.718	0.298
SO ₂ w/LS (ppm)	268.300	320.528	341.015	0.675
SOx w/o LS (ppm), calc	341.720	404.715	429.422	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 128.000 Preheat Outlet 382.330 Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 397.700 FG Preheat Outlet _____ NATURAL GAS INPUTS:

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH):

Boiler	18.210	Flash Tank	_____	Total Steam	18.210
Press. (psig):	Boiler 103.000	Flash Tank	103.000		
Temps. (deg F):	Boiler _____	Flash Tank	_____	Feed H ₂ O (deg F)	212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 19.924 Cooling (Coal + N Gas) - % 0.000 Cooling H₂O Inlet (deg F) _____
 Coal + N. Gas - MMBtu/hr 19.924

RESULTS: Steam Gen Eff'cy (%) 95.245 Fuel to Steam Flow Corr. 1.032

Boiler Efficiency (%) 96.362 % SO₂ Reduction 20.588 Intrusion Air (#/hr) 4742.26

REMARKS: TEST CONDITION: 20 MMBTU/HR, PHI=1, MAXIMUM DURATION, SWIRL DAMPER AT 388 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 509-H29

Date 04/25/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 As): 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 124

Section: _____

Time of Test: 21:20

FLOW RATES:

Coal PC (#/hr) 1168.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.450
Mix Bustle Air PC (kpph) 5.930
Coal MC (#/hr) 1338.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 1.020LS (#/hr) 12
LS Split (I/N) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc W21 Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 0.612
SCFH to #/hr 0.076Total Air (#/hr) 16742.521
Stoi Air (#/hr) 14998.027
Xcss Air SB (#/hr) 1744.493
Total Coal (#/hr) 2506.000
Total Gas (#/hr) 18736.874
% O₂ post SB Cmbn 2.034
Coal Split PC (%) 46.608
Ca Utilization, %STOICHIOMETRIC AIR: (for Coal) 5.985
STOICH. AIR: (# air/# to: fuel) 5.985
PHI's: PCC phi 1.059
PC phi 1.90E
MC phi 1.000
Overall phi at Sec. Brnr 1.068Cling Calc (Btu/sec) 370.800 Cling Meas (Btu/sec) 569.528 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:FLUX (Btu/ft²-sec):01 AI 0.581 02 AI 1.060 03 BAF 3.266 04 SRS 3.759
05 SRS 3.172 06 SRS 2.379 07 PC ET 1.707 09 TAP 0.909

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
O₂ (%) 6.410
CO (ppm) 1.000 1.234 1.300
NOx (ppm) 189.000 233.173 245.690 0.353
SO₂ w/LS (ppm) 296.000 365.182 384.785 0.769
SOx w/o LS (ppm), calc 331.477 404.717 425.468

AIR TEMPERATURES (deg F):

Air Preheat Inlet 122.000 Preheat Outlet 368.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 594.000 FG Preheat Outlet 395.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 14.980
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 338.000Flash Tank 2.030 Total Steam 17.010
Flash Tank 103.000
Flash Tank 338.000 Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 20.018
Coal + N. Gas - MMBtu/hr 20.018Cooling (Coal + N Gas) - % 10.242 Cooling H₂O Inlet (deg F) 342.000

RESULTS: Steam Gen Eff'cy (%) 82.631 Fuel to Steam Flow Corr. 0.962

Boiler Efficiency (%) 81.701 % SO₂ Reduction 9.562 Intrusion Air (#/hr) 5312.84

REMARKS: TEST CONDITION: 20 MMBTU/HR, PHI=1, MAXIMUM DURATION, SWIRL DAMPER AT 440 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 510-W30 Date 04/25/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR MERO

COAL: Source: HEALY PERF BLEND

Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
 Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 161

Section: _____ Time of Test: 1:45

FLOW RATES:

Coal PC (#/hr) 1162.000
 Carrier Air PC (scfh) 12500.000
 Combustion Air PC (kpph) 6.400
 Mix Bustle Air PC (kpph) 6.160
 Coal MC (#/hr) 1332.000
 Carrier Air MC (scfh) 21710.000
 Cmbn Air Sec Brnr (kpph) 0.940

LS (#/hr) 17
 LS Split (I/W) 100/0
 # Nozzles _____
 Carr'r A/LS (scfh) 9540.270
 C.A. Press (psig) Edc Wzl Dia 0.375
 Nozzles (throat): _____
 Injector (tube): 50.000
 Ca/S Ratio 0.501
 SCFH to #/hr 0.076

Total Air (#/hr) 16842.521
 Stoi Air (#/hr) 14926.209
 Xcss Air SB (#/hr) 1916.311
 Total Coal (#/hr) 2494.000
 Total Gas (#/hr) 18826.505
 % O₂ post SB Cmbn 2.223
 Coal Split PC (%) 46.592
 Ca Utilization, %

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.058

PC phi 1.943

MC phi 1.017

Overall phi at Sec. Brnr 1.020

Cling Calc (Btu/sec) 439.200 Cling Meas (Btu/sec) 704.194 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI 0.726 #2 AI 1.295 #3 BAF 3.966 #4 SRS 4.085
 #5 SRS 4.123 #6 SRS 2.537 #7 PC ET 2.027 #9 TAP 1.362

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
 O₂ (%) 6.600
 CO (ppm) 2.600 3.250 3.390
 NO_x (ppm) 207.000 258.750 269.913 0.391
 SO₂ w/LS (ppm) 269.000 336.250 350.757 0.708
 SO_x w/o LS (ppm), calc 327.412 404.736 421.414

AIR TEMPERATURES (deg F):

Air Preheat Inlet 125.000 Preheat Outlet 406.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 616.000 FG Preheat Outlet 426.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.320

Flash Tank 2.510

Total Steam 17.830

Press. (psig): Boiler 103.000

Flash Tank 103.000

Temps. (deg F): Boiler 338.000

Flash Tank 338.000

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 19.922

Cooling (Coal + N Gas) - % 12.725

Cooling H₂O Inlet (deg F) 343.000

Coal + N. Gas - MMBtu/hr 19.922

RESULTS: Steam Gen Eff'cy (%) 81.519 Fuel to Steam Flow Corr. 0.899

Boiler Efficiency (%) 79.673 % SO₂ Reduction 16.767 Intrusion Air (#/hr) 5405.20

REMARKS: TEST CONDITION: 20 MMBTU/HR, PHI=1, MAXIMUM DURATION, SWIRL DAMPER AT 440 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1
Date: 5/16/91

TEST: 511-H31

Date 04/26/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND

Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340

Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 141

Section: _____

Time of Test: 6:00

FLOW RATES:

Coal PC (#/hr) 1166.500

Carrier Air PC (scfh) 12500.000

Combustion Air PC (kpph) 6.060

Mix Bustle Air PC (kpph) 5.775

Coal MC (#/hr) 1342.000

Carrier Air MC (scfh) 21710.000

Cmbn Air Sec Brnr (kpph) 2.625

LS (#/hr)

17.25

LS Split (I/W)

100/0

Nozzles

Carr'r A/LS (scfh)

9540.270

C.A. Press (psig)

Edc Nzl Dia

0.375

Nozzles (throat):

50.000

Injector (tube):

50.000

Ca/S Ratio

0.586

SCFH to #/hr

0.076

Total Air (#/hr) 17802.521

Stoi Air (#/hr) 15012.990

Xcss Air SB (#/hr) 2789.531

Total Coal (#/hr) 2508.500

Total Gas (#/hr) 19798.175

% O₂ post SB Cmbn 3.078

Coal Split PC (%) 46.502

Ca Utilization, %

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.005

PC phi 1.832

MC phi 0.962

Overall phi at Sec. Brnr 1.137

Cling Calc (Btu/sec) 392.400 Cling Meas (Btu/sec) 561.111 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI 0.508

#2 AI 1.472

#3 BAF 3.266

#4 SRS 3.840

#5 SRS 3.806

#6 SRS 2.220

#7 PC 1.814

#8 TAP 0.227

EMISSIONS:

At stack

As meas.

At 3% O₂At Calc SB O₂

#/MMBtu

O₂ (%)

6.300

CO (ppm)

23.340

28.580

28.456

NOx (ppm)

206.000

252.245

251.155

0.380

SO₂ w/LS (ppm)

268.000

328.163

326.746

0.689

SOx w/o LS (ppm), calc

333.853

404.733

403.062

AIR TEMPERATURES (deg F):

Air Preheat Inlet 126.500

Preheat Outlet 417.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 639.000

FG Preheat Outlet 440.500

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____

% of Total Load: N/A

STEAMS (KPPH):

Boiler 16.400

Flash Tank 2.000

Total Steam 18.400

Press. (psig):

Boiler 103.000

Flash Tank 103.000

Temps. (deg F):

Boiler 336.500

Flash Tank 336.500

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS:

Coal - MMBtu/hr 20.038

Cooling (Coal + N Gas) - % 10.081

Cooling H₂O Inlet (deg F) 340.500

Coal + N. Gas - MMBtu/hr 20.038

RESULTS:

Steam Gen Eff'cy (%) 81.250

Fuel to Steam Flow Corr. 0.873

Boiler Efficiency (%) 80.174

% SO₂ Reduction 18.934

Intrusion Air (#/hr) 4104.20

REMARKS: TEST CONDITION: 20 MMBTU/HR, PHI=1, MAXIMUM DURATION, SWIRL DAMPER AT 440 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 512-H32

Date 04/26/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 151

Section: _____

Time of Test: 11:16

FLOW RATES:

Coal PC (#/hr) 1152.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 5.740
Mix Bustle Air PC (kpph) 5.560
Coal MC (#/hr) 1325.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 0.920LS (#/hr) 17
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Mz1 Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 0.555
SCFH to #/hr 0.076Total Air (#/hr) 15562.521
Stoi Air (#/hr) 14824.467
Xcss Air SB (#/hr) 738.054
Total Coal (#/hr) 2477.000
Total Gas (#/hr) 17533.086
% O₂ post SB Cmbn 0.820
Coal Split PC (%) 46.508
Ca Utilization, % _____STOICHIOMETRIC AIR: (for Coal) 5.985
STOICH. AIR: (# air/# tot fuel) 5.985
PHI's: PCC phi 0.971
PC phi 1.777
MC phi 0.939
Overall phi at Sec. Brnr 1.001Cling Calc (Btu/sec) 0.000 Cling Meas (Btu/sec) 0.000 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:
FLUX (Btu/ft²-sec):
#1 AI 0.000 #2 AI 0.000 #3 BAF 0.000 #4 SRS 0.000
#5 SRS 0.000 #6 SRS 0.000 #7 PC ET 0.000 #8 TAP 0.000

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
O₂ (%) 6.130
CO (ppm) 16.440 19.900 22.201
NO_x (ppm) 178.000 215.467 240.372 0.327
SO₂ w/LS (ppm) 269.000 325.622 363.258 0.687
SO_x w/o LS (ppm), calc 337.505 404.734 449.418

AIR TEMPERATURES (deg F):

Air Preheat Inlet 133.000 Preheat Outlet 417.000 Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 616.000 FG Preheat Outlet 441.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 17.760
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler _____Flash Tank _____ Total Steam 17.760
Flash Tank 103.000
Flash Tank _____ Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 19.786
Coal + N. Gas - MMBtu/hr 19.786Cooling (Coal + N Gas) - % 0.000 Cooling H₂O Inlet (deg F) _____

RESULTS: Steam Gen Eff'cy (%) 81.346 Fuel to Steam Flow Corr. 0.897

Boiler Efficiency (%) 82.301 % SO₂ Reduction 19.171 Intrusion Air (#/hr) 5213.76

REMARKS: TEST CONDITION: 20 MMBTU/HR, PHI=1, MAXIMUM DURATION, SWIRL DAMPER AT 440 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 1

Date: 5/16/91

TEST: 513-H33 Date 04/26/91
PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR MIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL % CaCO₃: 90.400 NATURAL GAS: Btu/lb _____ Stoich air (# air/# NG): _____
Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 146

Section: _____ Time of Test: 16:00

FLOW RATES:

Coal PC (#/hr) 1155.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 5.740
Mix Bustle Air PC (kpph) 5.610
Coal MC (#/hr) 1330.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 1.560

LS (#/hr) 18
LS Split (I/N) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Nzl Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 0.49
SCFH to #/hr 0.076

Total Air (#/hr) 16252.521
Stoi Air (#/hr) 14872.346
Xcss Air SB (#/hr) 1380.175
Total Coal (#/hr) 2485.000
Total Gas (#/hr) 18230.296
% O₂ post SB Cmbn 1.654
Coal Split PC (%) 46.479
Ca Utilization, %

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 0.969

PC phi 1.780

MC phi 0.939

Overall phi at Sec. Brnr 1.044

Cling Calc (Btu/sec) 316.800 Cling Meas (Btu/sec) 569.528 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI 0.435 #2 AI 1.177 #3 BAF 2.333 #4 SRS 3.105
#5 SRS 2.379 #6 SRS 2.062 #7 PC ET 1.707 #8 TAP 0.908

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	6.300			
CO (ppm)	14.000	17.143	18.425	
NOx (ppm)	178.000	217.959	234.261	0.330
SO ₂ w/LS (ppm)	290.000	355.102	381.661	0.749
SOx w/o LS (ppm), calc	333.837	404.713	433.626	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 136.000 Preheat Outlet 414.000 Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 618.000 FG Preheat Outlet 436.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.970
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 338.000

Flash Tank 2.030 Total Steam 18.000
Flash Tank 103.000
Flash Tank 338.000 Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 19.850 Cooling (Coal + N Gas) - % 10.329 Cooling H₂O Inlet (deg F) 343.000
Coal + N. Gas - MMBtu/hr 19.850

RESULTS: Steam Gen Eff'cy (%) 81.386 Fuel to Steam Flow Corr. 0.886

Boiler Efficiency (%) 80.278 % SO₂ Reduction 11.984 Intrusion Air (#/hr) 5449.31

REMARKS: TEST CONDITION: 20 MMBTU/HR, PHI=1, MAXIMUM DURATION, SWIRL DAMPER AT 440 FT/S

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision:

Date: 5/20/91

TEST: 523-H34 Date 05/14/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR MIRO

COAL: Source: HEALY PERF BLEND

Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 154

Section: _____ Time of Test: 12:24

FLOW RATES:

Coal PC (#/hr)	1167.000	LS (#/hr)	95.400	Total Air (#/hr)	17042.521
Carrier Air PC (scfh)	12500.000	LS Split (I/M)	100/0	Stoi Air (#/hr)	15027.952
Combustion Air PC (kpph)	5.940	# nozzles	_____	Xcss Air SB (#/hr)	2014.569
Mix Bustle Air PC (kpph)	5.490	Carr'r A/LS (scfh)	9540.270	Total Coal (#/hr)	2511.000
Coal MC (#/hr)	1344.000	C.A. Press (psig)	Edc Nzl Dia 0.375	Total Gas (#/hr)	19067.413
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% O ₂ post SE Cmbn	2.308
Cmbn Air Sec Brnr (kpph)	2.270	Injector (tube):	50.000	Coal Split PC (%)	46.476
		Ca/S Ratio	3.239	Ca Utilization, %	11.571
		SCFH to #/hr	0.076		

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 0.987

PC phi 1.773

MC phi 0.935

Overall phi at Sec. Brnr 1.086

Cling Calc (Btu/sec) 354.240 Cling Meas (Btu/sec) 547.083 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI	1.277	#2 AI	0.918	#3 BAF	2.286	#4 SRS	3.236
#5 SRS	2.030	#6 SRS	2.189	#7 PC ET	2.539	#9 TAP	0.817

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	6.320			
CO (ppm)	15.530	19.042	19.774	
NOx (ppm)	159.100	195.082	202.583	0.295
SO ₂ w/LS (ppm)	205.700	252.221	261.919	0.532
SOx w/o LS (ppm), calc	332.891	404.086	418.926	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 136.000

Preheat Outlet 368.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 568.600

FG Preheat Outlet 392.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.520

Flash Tank 1.950

Total Steam 17.470

Press. (psig): Boiler 103.000

Flash Tank 103.000

Temps. (deg F): Boiler 338.400

Flash Tank 338.400

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 20.058

Cooling (Coal + N Gas) - % 9.819

Cooling H₂O Inlet (deg F) 342.200

Coal + N. Gas - MMBtu/hr 20.058

RESULTS: Steam Gen Eff'cy (%) 82.529

Fuel to Steam Flow Corr. 0.937

Boiler Efficiency (%) 81.885

% SO₂ Reduction 37.479

Intrusion Air (#/hr) 4927.95

REMARKS: TEST CONDITION: 20 MMBTU/HR, DAMPER SETTINGS 0%, 50%

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision:

Date: 5/20/91

TEST: 524-H35

Date 05/14/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR WIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 146

Section: _____ Time of Test: 16:50

FLOW RATES:

Coal PC (#/hr) 1177.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.450
Mix Bustle Air PC (kpph) 5.896
Coal MC (#/hr) 1356.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 0.520LS (#/hr) 48.000
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Nzl Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.616
SCFH to #/hr 0.076Total Air (#/hr) 16208.521
Stoi Air (#/hr) 15159.618
Xcss Air SB (#/hr) 1048.902
Total Coal (#/hr) 2533.000
Total Gas (#/hr) 18229.559
% O₂ post SB Cmbn 1.257
Coal Split PC (%) 46.467
Ca Utilization, % 23.728STOICHIOMETRIC AIR: (for Coal) 5.985
STOICH. AIR: (# air/# tot fuel) 5.985
PHI's: PCC phi 1.051
PC phi 1.888
MC phi 0.987
Overall phi at Sec. Brnr 1.021Cling Calc (Btu/sec) 346.680 Cling Meas (Btu/sec) 575.139 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:
FLUX (Btu/ft²-sec):
#1 AI 0.871 #2 AI 1.060 #3 BAF 2.216 #4 SRS 3.268
#5 SRS 2.220 #6 SRS 2.220 #7 FC ET 2.241 #9 TAP 1.271

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
O₂ (%) 5.560
CO (ppm) 18.420 21.474 23.554
NO_x (ppm) 149.200 173.938 190.782 0.264
SO₂ w/LS (ppm) 213.170 248.514 272.581 0.524
SO_x w/o LS (ppm), calc 349.627 404.594 442.020

AIR TEMPERATURES (deg F):

Air Preheat Inlet 139.500

Preheat Outlet 403.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 603.500 FG Preheat Outlet 421.800

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 16.080
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 338.000Flash Tank 2.050 Total Steam 18.130
Flash Tank 103.000
Flash Tank 338.000 Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 20.234
Coal + N. Gas - MMBtu/hr 20.234Cooling (Coal + N Gas) - % 10.233 Cooling H₂O Inlet (deg F) 343.000

RESULTS: Steam Gen. Eff'cy (%) 82.233

Fuel to Steam Flow Corr. 0.906

Boiler Efficiency (%) 81.298

% SO₂ Reduction 38.333

Intrusion Air (#/hr) 4817.34

REMARKS: TEST CONDITION: 20 MMBTU/HR, DAMPER SETTINGS 0%, 50%

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 5/31/91

TEST: 525-H36

Date 05/15/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 180

Section: _____

Time of Test: 14:25

FLOW RATES:

Coal PC (#/hr) 1160.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.050
Mix Bustle Air PC (kpph) 5.820
Coal MC (#/hr) 1337.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 0.000LS (#/hr) 49.600
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Wz1 Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.693
SCFH to #/hr 0.076Total Air (#/hr) 15212.521
Stoi Air (#/hr) 14944.164
Xcss Air SB (#/hr) 269.357
Total Coal (#/hr) 2497.000
Total Gas (#/hr) 17265.857
% O₂ post SB Cmbn 0.341
Coal Split PC (%) 46.456
Ca Utilization, % 34.224STOICHIOMETRIC AIR: (for Coal) 5.985
STOICH. AIR: (# air/# tot fuel) 5.985
PHI's: PCC phi 1.009
PC phi 1.847
MC phi 0.959
Overall phi at Sec. Brnr 0.969Cling Calc (Btu/sec) 321.840 Cling Meas (Btu/sec) 489.289 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:
FLUX (Btu/ft²-sec):
#1 AI 0.653 #2 AI 1.083 #3 BAF 2.146 #4 SRS 2.811
#5 SRS 2.300 #6 SRS 2.030 #7 PC ET 2.219 #8 TAP 0.545

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
O₂ (%) 6.120
CO (ppm) 6.860 8.298 9.524
NOx (ppm) 142.300 172.137 197.569 0.261
SO₂ w/LS (ppm) 139.800 169.113 194.098 0.358
SOx w/o LS (ppm), calc 337.583 404.570 461.663

AIR TEMPERATURES (deg F):

Air Preheat Inlet 151.600

Preheat Outlet 396.300

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 596.600 FG Preheat Outlet 417.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.256
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 338.200Flash Tank 1.744 Total Steam 17.000
Flash Tank 103.000
Flash Tank 338.200 Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 19.946
Coal + N. Gas - MMBtu/hr 19.946Cooling (Coal + N Gas) - % 8.831 Cooling H₂O Inlet (deg F) 341.000

RESULTS: Steam Gen Eff'cy (%) 82.045

Fuel to Steam Flow Corr. 0.952

Boiler Efficiency (%) 81.387

% SO₂ Reduction 57.957

Intrusion Air (#/hr) 6324.06

REMARKS: TEST CONDITION: 20 MMBTU/HR, DAMPER SETTINGS 0x, 50x

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: C

Date: 5/31/91

TEST: 526-H37 Date 05/16/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 16.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 149

Section: _____ Time of Test: 20:30

FLOW RATES:

Coal PC (#/hr) 1168.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.370
Mix Bustle Air PC (kpph) 5.840
Coal MC (#/hr) 1344.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 0.000LS (#/hr) 50.400
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Mz! Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.710
SCFH to #/hr 0.076Total Air (#/hr) 15552.521
Stoi Air (#/hr) 15033.936
Xcss Air SB (#/hr) 518.584
Total Coal (#/hr) 2512.000
Total Gas (#/hr) 17558.057
% O₂ post SB Cmbn 0.645
Coal Split PC (%) 46.497
Ca Utilization, % 32.004

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tct fuel) 5.985

PHI's: PCC phi 1.048

PC phi 1.883

MC phi 0.926

Overall phi at Sec. Brnr 0.986

Cling Calc (Btu/sec) 392.400 Cling Meas (Btu/sec) 569.528 Flow #/sec 28.800
Total flow assumed equal over all 2 circuits:FLUX (Btu/ft²-sec):#1 AI 0.581 #2 AI 1.295 #3 BAF 2.800 #4 SRS 3.759
#5 SRS 3.330 #6 SRS 2.062 #7 PC ET 2.561 #9 TAP 0.454

EMISSIONS:

At stack As meas.
O₂ (%) 6.770
CO (ppm) 5.800
NOx (ppm) 159.000
SO₂ w/LS (ppm) 144.000
SOx w/o LS (ppm), calc 323.624At 3% O₂ At Calc SB O₂ #/MMBtu
7.337 8.296
201.124 227.436 0.305
182.150 205.980 0.385
404.564 455.120

AIR TEMPERATURES (deg F):

Air Preheat Inlet 143.000

Preheat Outlet 382.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 599.000

FG Preheat Outlet 399.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (kPPH):

Boiler 13.570

Flash Tank 2.030

Total Steam 15.600

Press. (psig): Boiler 103.000

Flash Tank 103.000

Temps. (deg F): Boiler 338.000

Flash Tank 338.000

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 20.066

Cooling (Coal + N Gas) - % 10.218

Cooling H₂O Inlet (deg F) 341.000

Coal + N. Gas - MMBtu/hr 20.066

RESULTS: Steam Gen Eff'cy (%) 82.223

Fuel to Steam Flow Corr. 1.048

Boiler Efficiency (%) 81.295

% SO₂ Reduction 54.742

Intrusion Air (#/hr) 7134.27

REMARKS: TEST CONDITION: 20 MMBTU/HR, DAMPER SETTINGS 0%, 50%

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 5/31/91

TEST: 521-H38 Date 05/17/91
 PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
 Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
 Moisture: 10.830 Ash: 21.000 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL % CaCO₃: 90.400 NATURAL GAS: Btu/lb _____ Stoich air (# air/# NG): _____
 Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 164

Section: _____ Time of Test: 1:35

FLOW RATES:

Coal PC (#/hr)	1156.000	LS (#/hr)	48.000	Total Air (#/hr)	15822.521
Carrier Air PC (scfh)	12500.000	LS Split (I/W)	100/0	Stoi Air (#/hr)	14884.315
Combustion Air PC (kpph)	6.380	# Nozzles	_____	Excess Air SB (#/hr)	938.206
Mix Bustle Air PC (kpph)	6.100	Carr'r A/LS (scfh)	9540.270	Total Coal (#/hr)	2487.000
Coal MC (#/hr)	1331.000	C.A. Press (psig)	Edc Mz1 Dia 0.375	Total Gas (#/hr)	17807.247
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% O ₂ post SB Cmbn	1.151
Cmbn Air Sec Brnr (kpph)	0.000	Injector (tube):	50.000	Coal Split PC (%)	46.482
		Ca/S Ratio	1.645	Ca Utilization, %	31.664
		SCFH to #/hr	0.076		
STOICHIOMETRIC AIR: (for Coal)	5.985				
STOICH. AIR: (# air/# tot fuel)	5.985				
PHI's: PCC phi	1.060	Cing Calc (Btu/sec)	358.920	Cing Meas (Btu/sec)	549.889
PC phi	1.942	Total flow assumed equal over all 8 circuits:		Flow #/sec	28.800
MC phi	1.014	FLUX (Btu/ft ² -sec):			
Overall phi at Sec. Brnr	1.014	#1 AI 0.319	#2 AI 1.001	#3 BAF 2.916	#4 SRS 3.595
		#5 SRS 2.855	#6 SRS 2.062	#7 PC ET 2.507	#8 TAP 0.003

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	5.890			
CO (ppm)	7.830	9.328	10.286	
NO _x (ppm)	141.000	167.968	185.223	0.255
SO ₂ w/LS (ppm)	162.000	192.985	212.810	0.407
SO _x w/o LS (ppm), calc	342.534	404.585	444.285	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 142.000 Preheat Outlet 401.000 Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 627.000 FG Preheat Outlet 424.500

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH):

Boiler	14.800	Flash Tank	1.960	Total Steam	16.860
Press. (psig):	Boiler 103.000	Flash Tank	103.000		
Temps. (deg F):	Boiler 338.000	Flash Tank	338.000	Feed H ₂ O (deg F)	212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 19.866 Cooling (Coal + N Gas) - % 9.965 Cooling H₂O Inlet (deg F) 342.000
 Coal + N. Gas - MMBtu/hr 19.866

RESULTS: Steam Gen Eff'cy (%) 81.954 Fuel to Steam Flow Corr. 0.955

Boiler Efficiency (%) 81.042 % SO₂ Reduction 52.101 Intrusion Air (#/hr) 5289.71

REMARKS: TEST CONDITION: 20 MMBTU/HR, DAMPER SETTINGS 0%, 50%

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0
Date: 5/31/91TEST: 528-H39 Date 05/17/91
PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIROCOAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T260 (calc. deg F): 2715 HHV (Btu/lb): 7988LIMESTONE: CANTWELL % CaCO₃: 90.400 NATURAL GAS: Btu/lb _____ Stoich air (# air/# NG): _____
Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 130 Section: _____ Time of Test: 6:46

FLOW RATES:

Coal PC (#/hr)	1173.000	LS (#/hr)	49.000	Total Air (#/hr)	16842.521
Carrier Air PC (scfh)	12500.000	LS Split (I/N)	100/0	Stoi Air (#/hr)	15111.740
Combustion Air PC (kpph)	6.190	# Nozzles	_____	Xcss Air SB (#/hr)	1730.781
Mix Bustle Air PC (kpph)	6.020	Carr'r A/LS (scfh)	9540.270	Total Coal (#/hr)	2525.000
Coal MC (#/hr)	1352.000	C.A. Press (psig)	Edc Nz1 Dia 0.375	Total Gas (#/hr)	18857.692
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% O ₂ post SB Cmbn	2.005
Cmbn Air Sec Brnr (kpph)	1.290	Injector (tube):	50.000	Coal Split PC (%)	45.455
		Ca/S Ratio	1.654	Ca Utilization, %	30.397
		SCFH to #/hr	0.076		

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.018

PC phi 1.875

MC phi 0.921

Overall phi at Sec. Brnr 1.066

Cling Calc (Btu/sec) 315.000 Cling Meas (Btu/sec) 521.833 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI 0.218 #2 AI 0.824 #3 BAF 2.333 #4 SRS 3.187

#5 SRS 2.379 #6 SRS 2.141 #7 PC ET 2.241 #9 TAP 0.000

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	5.660			
CO (ppm)	12.800	15.020	15.850	
NOx (ppm)	127.000	149.022	157.261	0.225
SO ₂ w/LS (ppm)	171.000	200.652	211.745	0.423
SOx w/o LS (ppm), calc	347.470	404.582	425.947	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 140.800 Preheat Outlet 409.000 Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 650.600 FG Preheat Outlet 429.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.740

Flash Tank 1.860

Total Steam 17.600

Press. (psig): Boiler 103.000

Flash Tank 103.000

Temps. (deg F): Boiler 337.000

Flash Tank 337.000

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 20.170

Cooling (Coal + N Gas) - % 9.314

Cooling H₂O Inlet (deg F) 342.000

Coal + N. Gas - MMBtu/hr 20.170

RESULTS: Steam Gen Eff'cy (%) 81.950

Fuel to Steam Flow Corr. 0.928

Boiler Efficiency (%) 81.177

% SO₂ Reduction 50.288

Intrusion Air (#/hr) 4259.07

REMARKS: TEST CONDITION: 20 MMBTU/HR, DAMPER SETTINGS 0%, 50%

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 5/31/91

TEST: 529-H40 Date 06/17/91
 PURPOSE: GENERATE 6 TONS OF BAGHOUSE CATCH FOR MIRO

COAL: Source: HEALY PERF BLEND
 Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
 Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____
 Hydrogen (# H₂/# NO): _____

Stoich air (# air/# NO): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 144

Section: _____ Time of Test: 10:42

FLOW RATES:

Coal PC (#/hr) 1164.500
 Carrier Air PC (scfh) 12600.000
 Combustion Air PC (kpph) 6.096
 Mix Bustle Air PC (kpph) 5.934
 Coal MC (#/hr) 1342.000
 Carrier Air MC (scfh) 21710.000
 Cmbn Air Sec Brnr (kpph) 1.085

LS (#/hr) 50.300
 LS Split (I/N) 100/0
 # Nozzles _____
 Carr'r A/LS (scfh) 9540.270
 C.A. Press (psig) Edc Nzl Dia 0.375
 Nozzles (throat): _____
 Injector (tube): 50.000
 Ca/S Ratio 1.711
 SCFH to #/hr 0.076

Total Air (#/hr) 16457.521
 Stoic Air (#/hr) 15031.020
 Xcss Air SB (#/hr) 1456.501
 Total Coal (#/hr) 2506.500
 Total Gas (#/hr) 18452.670
 % O₂ post SB Cmbn 1.724
 Coal Split PC (%) 46.459
 Ca Utilization, % 26.467

STOICHIOMETRIC AIR: (for Coal) 5.985
 STOICH. AIR: (# air/# tot fuel) 5.985
 PHI's: PCC phi 1.012
 PC phi 1.863
 MC phi 0.976
 Overall phi at Sec. Brnr 1.049

Cing Calc (Btu/sec) 361.080 Cing Meas (Btu/sec) 577.944 Flow #/sec 28.300
 Total flow assumed equal over all 8 circuits:
 FLUX (Btu/ft²-sec):
 #1 AI 0.319 #2 AI 0.742 #3 BAF 2.683 #4 SRS 4.085
 #5 SRS 2.823 #6 SRS 2.648 #7 PC ET 2.401 #8 TAP -0.772

EMISSIONS:

At stack As meas.
 O₂ (%) 5.668
 CO (ppm) 84.300
 NOx (ppm) 115.000
 SO₂ w/LS (ppm) 182.000
 SOx w/o LS (ppm), calc 347.283

At 3% O₂ At Calc SB O₂ #/MMBtu
 98.989 105.987
 135.012 144.586 0.204
 220.715 236.366 0.465
 404.584 431.966

AIR TEMPERATURES (deg F):

Air Preheat Inlet 139.500

Preheat Outlet 427.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 612.000

FG Preheat Outlet 416.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.950
 Press. (psig): Boiler 103.000
 Temps. (deg F): Boiler 338.000

Flash Tank 2.060 Total Steam 18.010
 Flash Tank 103.000
 Flash Tank 338.000 Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 20.022 Cooling (Coal + N Gas) - % 10.392 Cooling H₂O Inlet (deg F) 343.000
 Coal + N. Gas - MMBtu/hr 20.022

RESULTS: Stear. Gen Eff'cy (%) 82.338 Fuel to Steam Flow Corr. 0.904

Boiler Efficiency (%) 81.392 % SO₂ Reduction 45.281 Intrusion Air (#/hr) 4501.08

REMARKS: TEST CONDITION: 20 MMBTU/HR, DAMPER SETTINGS 0%, 50%

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 5/31/91

TEST: 530-H41 Date 05/20/91
 PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
 Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 16.980 Nitrogen: 0.730 Sulfur: 0.340
 Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL % CaCO₃: 90.400 NATURAL GAS: Btu/lb _____ Stoich air (# air/# NG): _____
 Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 202

Section: _____ Time of Test: 12:50

FLOW RATES:

Coal PC (#/hr)	1179.000	LS (#/hr)	48.000	Total Air (#/hr)	16375.521
Carrier Air PC (scfh)	12500.000	LS Split (I/W)	100/0	Stoi Air (#/hr)	15177.573
Combustion Air PC (kpph)	6.230	# Nozzles	_____	Xcss Air SB (#/hr)	1197.948
Mix Bustle Air PC (kpph)	6.000	Carr'r A/LS (scfh)	9540.270	Total Coal (#/hr)	2536.000
Coal MC (#/hr)	1357.000	C.A. Press (psig)	Edc Nz1 Dia 0.375	Total Gas (#/hr)	18398.928
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% C2 post SB Cmbn	1.422
Cmbn Air Sec Brnr (kpph)	0.803	Injector (tube):	50.000	Coal Split PC (%)	46.491
		Ca/S Ratio	1.614	Ca Utilization, %	28.127
		SCFH to #/hr	0.076		

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# to: fuel) 5.985

PHI's: PCC phi 1.018

PC phi 1.869

MC phi 0.978

Overall phi at Sec. Brnr 1.031

Cing Calc (Btu/sec) 374.400 Cing Meas (Btu/sec) 608.805 Flow #/sec 28.800
 Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI	0.435	#2 AI	1.177	#3 BAF	3.033	#4 SRS	3.922
#5 SRS	3.013	#6 SRS	2.062	#7 PC ET	2.241	#8 TAP	0.454

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	5.630			
CO (ppm)	20.420	23.914	26.010	
NO _x (ppm)	118.170	138.390	150.521	0.210
SO ₂ w/LS (ppm)	188.000	220.169	239.468	0.464
SO _x w/o LS (ppm), calc	348.125	404.595	438.469	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 133.000 Preheat Outlet 366.000 Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 580.000 FG Preheat Outlet 392.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH):	Boiler	15.280	Flash Tank	2.170	Total Steam	17.450
Press. (psig):	Boiler	103.000	Flash Tank	103.000		
Temps. (deg F):	Boiler	338.000	Flash Tank	338.000	Feed H ₂ O (deg F)	212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 20.258 Cooling (Coal + N Gas) - % 10.819 Cooling H₂O Inlet (deg F) 343.000
 Coal + N. Gas - MMBtu/hr 20.258

RESULTS: Steam Gen Eff'cy (%) 83.110 Fuel to Steam Flow Corr. 0.954

Boiler Efficiency (%) 82.168 % SO₂ Reduction 45.386 Intrusion Air (#/hr) 4774.85

REMARKS: COAL INJECTOR PUSHED IN 4". (6" total - previously 2" total) Combustor cleared prior to test.

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 531-H42

Date 05/20/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400NATURAL GAS: Btu/lb _____
Hydrogen (# H₂/# NG): _____

Stoich air (# air/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 148

Section: _____ Time of Test: 18:15

FLOW RATES:

Coal PC (#/hr) 1168.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.220
Mix Bustle Air PC (kpph) 5.880
Coal MC (#/hr) 1345.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 0.341LS (#/hr) 40.000
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Nzl Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.357
SCFH to #/hr 0.076Total Air (#/hr) 15783.521
Stoi Air (#/hr) 15039.921
Xcss Air SB (#/hr) 743.599
Total Coal (#/hr) 2513.000
Total Gas (#/hr) 17785.190
% O₂ post SB Cmbn 0.913
Coal Split PC (%) 46.478
Ca Utilization, % 34.703

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.026
PC phi 1.868
MC phi 0.978
Overall phi at Sec. Brnr 1.001Cling Calc (Btu/sec) 392.400 Cling Meas (Btu/sec) 625.639 Flow #/sec 26.800
Total flow assumed equal over all 8 circuits:FLUX (Btu/ft²-sec):#1 AI 0.435 #2 AI 1.413 #3 BAF 3.266 #4 SRS 4.085
#5 SRS 2.855 #6 SRS 2.220 #7 PC ET 2.347 #9 TAP 0.454

EMISSIONS:

At stack As meas.
O₂ (%) 6.050
CO (ppm) 34.300
NO_x (ppm) 126.000
SO₂ w/LS (ppm) 177.000
SO_x w/o LS (ppm), calc 339.174At 3% O₂ At Calc SB O₂ #/MMBtu
41.298 46.085
151.706 169.293 0.230
213.110 237.816 0.450
404.675 449.486

AIR TEMPERATURES (deg F):

Air Preheat Inlet 138.000

Preheat Outlet 405.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 625.000

FG Preheat Outlet 423.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.450
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 338.000Flash Tank 2.230
Flash Tank 103.000
Flash Tank 338.000

Total Steam 17.630

Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 20.074
Coal + N. Gas - MMBtu/hr 20.074

Cooling (Coal + N Gas) - % 11.220

Cooling H₂O Inlet (deg F) 342.000

RESULTS: Steam Gen Eff'cy (%) 81.940

Fuel to Steam Flow Corr. 0.919

Boiler Efficiency (%) 80.723

% SO₂ Reduction 47.092

Intrusion Air (#/hr) 5784.40

REMARKS: USING 8.5" LIME INJECTOR. (Nozzle ring assembly)

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 532-H43

Date 05/20/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND

Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
 Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 185

Section: _____

Time of Test: 22:48

FLOW RATES:

Coal PC (#/hr) 1154.000
 Carrier Air PC (scfh) 12500.000
 Combustion Air PC (kpph) 6.360
 Mix Bustle Air PC (kpph) 6.070
 Coal MC (#/hr) 1328.000
 Carrier Air MC (scfh) 21710.000
 Comb Air Sec Brnr (kpph) 0.175

LS (#/hr) 50.000
 LS Split (I/W) 100/0
 # Nozzles _____
 Carr'r A/LS (scfh) 9540.270
 C.A. Press (psig) Edc N21 Dia 0.375
 Nozzles (throat): _____
 Injector (tube): 50.000
 Ca/S Ratio 1.717
 SCFH to #/hr 0.076

Total Air (#/hr) 15947.521
 Stoi Air (#/hr) 14854.391
 Xcss Air SB (#/hr) 1093.130
 Total Coal (#/hr) 2482.000
 Total Gas (#/hr) 17929.195
 % O₂ post SB Cmbn 1.332
 Coal Split PC (%) 46.495
 Ca Utilization, % 32.700

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PC phi 1.059
 PC phi 1.938
 MC phi 1.013
 Over-all phi at Sec. Brnr 1.025

Cing Calc (Btu/sec) 374.400 Cing Meas (Btu/sec) 608.806 Flow #/sec 28.830
 Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI 0.290 #2 AI 1.295 #3 BAF 2.800 #4 SRS 4.085
 #5 SRS 2.696 #6 SRS 2.537 #7 PC ET 2.241 #8 TAP 0.000

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	6.330			
CO (ppm)	17.400	21.350	23.328	
NO _x (ppm)	145.000	177.914	194.403	0.270
SO ₂ w/LS (ppm)	144.000	176.687	193.062	0.373
SO _x w/c LS (ppm), calc	333.068	404.562	440.376	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 137.600

Preheat Outlet 406.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 624.000

FG Preheat Outlet 422.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.020
 Press. (psig): Boiler 103.000
 Temps. (deg F): Boiler 338.000

Flash Tank 2.170
 Flash Tank 103.000
 Flash Tank 338.000

Total Steam 17.190

Feed H₂O (deg F) 120.000

COMBUSTOR LOADS: Coal - MMBtu/hr 19.826
 Coal + N. Gas - MMBtu/hr 19.826

Cooling (Coal + N Gas) - %

11.055

Cooling H₂O Inlet (deg F) 343.000

RESULTS: Steam Gen Eff'cy (%) 81.753

Fuel to Steam Flow Corr.

0.932

Boiler Efficiency (%) 80.583

% SO₂ Reduction 56.160

Intrusion Air (#/hr) 5776.41

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 533-H44

Date 05/21/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR MIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 147

Section: _____

Time of Test: 3:46

FLOW RATES:

Coal PC (#/hr) 1154.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.080
Mix Bustle Air PC (kpph) 5.880
Coal MC (#/hr) 1330.000
Carrier Air MC (scfh) 21710.000
Comb Air Sec Brnr (kpph) 0.350LS (#/hr) 42.500
LS Split (I/N) 100/0
Nozzles _____
Carrier A/LS (scfh) 9540.270
C.A. Press (psig) Edc Nzl Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.459
SCFH to #/hr 0.076Total Air (#/hr) 15652.521
Stoi Air (#/hr) 14865.361
Xcss Air SB (#/hr) 786.150
Total Coal (#/hr) 2484.000
Total Gas (#/hr) 17632.417
% C₂ post SB Cmbn 0.974
Coal Split PC (%) 46.457
Ca Utilization, % 35.326

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PC phi 1.019

PC phi 1.870

MC phi 0.980

Overall phi at Sec. Brnr 1.004

Cling Calc (Btu/sec) 338.400 Cling Meas (Btu/sec) 527.444 Flow #/sec 28 P30

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):#1 AI 0.508 #2 AI 1.118 #3 BAF 2.333 #4 SRS 3.432
#5 SRS 2.062 #6 SRS 2.537 #7 PC ET 2.241 #9 TAP 0.000

EMISSIONS:

At stack As meas.
O₂ (%) 6.250
CO (ppm) 22.500
NO_x (ppm) 141.000
SO₂ w/LS (ppm) 160.000
SCx w/o LS (ppm), calc 334.853At 3% O₂ At Calc SB O₂ #/MMBtu
27.458 30.548
172.068 191.436 0.261
195.254 217.232 0.412
404.643 448.149

AIR TEMPERATURES (deg F):

Air Preheat Inlet 134.000

Preheat Outlet 413.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 640.000

FG Preheat Outlet 429.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH):

Boiler 15.010
Press. (psig): Boiler 103.000
Terps. (deg F): Boiler 338.000Flash Tank 1.880
Flash Tank 103.000
Flash Tank 338.000

Total Steam 16.890

Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 19.842
Coal + N. Gas - MMBtu/hr 19.842

Cooling (Coal + N Gas) - % 9.570

Cooling H₂O Inlet (deg F) 341.000

RESULTS: Steam Gen Eff'cy (%) 81.613

Fuel to Steam Flow Corr. 0.948

Boiler Efficiency (%) 80.724

% SO₂ Reduction 51.527

Intrusion Air (#/hr) 5965.85

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 534-H45 Date 05/21/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND

Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340

Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 172

Section: _____ Time of Test: 8:29

FLOW RATES:

Coal PC (#/hr) 1171.000

Carrier Air PC (scfh) 12500.000

Combustion Air PC (kpph) 6.000

Mix Rustle Air PC (kpph) 5.850

Coal MC (#/hr) 1348.000

Carrier Air MC (scfh) 21710.000

Cmbr. Air Sec Brnr (kpph) 0.224

LS (#/hr) 47.000

LS Split (I/M) 100/0

Nozzles _____

Carr'r A/LS (scfh) 9540.270

C.A. Press (psig) Edc Nzl Dia 0.375

Nozzles (throat): _____

Injector (tube): 50.000

Ca/S Ratio 1.591

SCFH to #/hr 0.076

Total Air (#/hr) 15416.521

Stci Air (#/hr) 15075.830

Xcss Air SB (#/hr) 340.630

Total Coal (#/hr) 2519.000

Total Gas (#/hr) 17426.060

% O₂ post SB Cbn 0.427

Coal Split PC (%) 46.487

Ca Utilization, % 33.269

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 0.992

PC phi 1.827

MC phi 0.959

Overall phi at Sec. Brnr 0.974

Cling Calc (Btu/sec) 338.400 Cling Meas (Btu/sec) 524.639 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI 0.435

#2 AI 1.060

#3 BAF 2.566

#4 SRS 3.268

#5 SRS 2.220

#6 SRS 2.379

#7 PC ET 2.241

#8 TAP 0.454

EMISSIONS:

At stack As meas.

O₂ (%) 6.005

CO (ppm) 30.620

NOx (ppm) 130.860

SO₂ w/LS (ppm) 157.800

SOx w/o LS (ppm), calc 340.079

At 3% O₂

36.756

157.084

189.423

404.802

At Calc SB O₂

42.010

179.538

216.500

459.845

#/MMBtu

0.238

C. 10

AIR TEMPERATURES (deg F):

Air Preheat Inlet 138.700

Preheat Outlet 423.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 647.000

FG Preheat Outlet 441.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH):

Boiler 15.940

Flash Tank 1.870

Total Steam 17.810

Press. (psig):

Boiler 103.000

Flash Tank 103.000

Temps. (deg F):

Boiler 336.000

Flash Tank 336.000

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS:

Coal - MMBtu/hr 20.122

Cooling (Coal + N Gas) - % 9.386

Cooling H₂O Inlet (deg F) 341.000

Coal + N Gas - MMBtu/hr 20.122

RESULTS:

Steam Gen Eff'cy (%) 81.373

Fuel to Steam Flow Corr. 0.908

Boiler Efficiency (%) 80.510

% SO₂ Reduction 52.919

Incrusion Air (#/hr) 6136.95

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 535-H46 Date 05/21/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR MIRO

COAL: Source: HEALY PERF BLEND

Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340

Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7982

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 149

Section: _____ Time of Test: 13:22

FLOW RATES:

Coal PC (#/hr) 1165.000

Carrier Air PC (scfh) 12500.000

Combustion Air PC (kpph) 5.750

Mix Bustle Air PC (kpph) 5.440

Coal MC (#/hr) 1342.000

Carrier Air MC (scfh) 21710.000

Cmbn Air Sec Brnr (kpph) 0.610

LS (#/hr) 51.000

LS Split (I/W) 100/0

Nozzles _____

Carr'r A/LS (scfh) 9540.270

C.A. Press (psig) Edc W21 Dia 0.375

Nozzles (throat): _____

Injector (tube): 50.000

Ca/S Ratio 1.734

SCFH to #/hr 0.076

Total Air (#/hr) 15142.521

Stoi Air (#/hr) 15004.012

Xcss Air SB (#/hr) 138.508

Total Coal (#/hr) 2507.000

Total Gas (#/hr) 17144.378

% O₂ post SB Cmbn 0.176

Coal Split PC (%) 46.470

Ca Utilization, % 29.418

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 0.962

PC phi 1.742

MC phi 0.920

Overall phi at Sec. Brnr 0.961

Cling Calc (Btu/sec) 324.000 Cling Meas (Btu/sec) 505.842 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

01 AI 0.280 02 AI 1.236 03 BAF 2.800 04 SRS 3.187

05 SRS 2.141 06 SRS 1.982 07 PC ET 2.081 09 TAP 0.227

EMISSIONS:

At stack As meas.

O₂ (%) 5.920

CO (ppm) 28.300

NOx (ppm) 118.000

SO₂ w/LS (ppm) 165.000

SOx w/o LS (ppm), calc 341.866

At 3% O₂ At Calc SB O₂

33.780 39.079

140.849 162.943

196.950 227.844

404.557 465.174

#/MMBtu

0.214

0.417

AIR TEMPERATURES (deg F):

Air Preheat Inlet 135.000

Preheat Outlet 395.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 626.000

FG Preheat Outlet 414.500

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.837

Press. (psig): Boiler 103.000

Temps. (deg F): Boiler 337.500

Flash Tank 1.803

Flash Tank 103.000

Flash Tank 337.500

Total Steam 17.640

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 20.026

Coal + N. Gas - MMBtu/hr 20.026

Cooling (Coal + N Gas) - % 9.093

Cooling H₂O Inlet (deg F) 342.500

RESULTS: Steam Gen Eff'cy (%) 82.237

Fuel to Steam Flow Corr. 0.923

Boiler Efficiency (%) 81.552

% SO₂ Reduction 51.020

Intrusion Air (#/hr) 6183.79

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 536-H47 Date 05/22/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7998

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 133

Section: _____

Time of Test: 1:30

FLOW RATES:

Coal PC (#/hr) 1150.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.170
Mix Bustle Air PC (kpph) 6.010
Coal MC (#/hr) 1323.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 0.000LS (#/hr) 52.000
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Nz1 Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.793
SCFH to #/hr 0.076Total Air (#/hr) 15522.521
Stoi Air (#/hr) 14200.527
Xcss Air SB (#/hr) 721.993
Total Coal (#/hr) 2473.000
Total Gas (#/hr) 17497.986
% O₂ post SB Cmbn 0.901
Coal Split PC (%) 46.502
Ca Utilization, % 29.963

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tct fuel) 5.985

PHI's: PCC phi 1.035

PC phi 1.908

MC phi 1.000

Overall phi at Sec. Brnr 1.000

Cling Calc (Btu/sec) 363.240 Cling Meas (Btu/sec) 527.444 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:FLUX (Btu/ft²-sec):#1 AI 0.915 #2 AI 0.977 #3 BAF 2.520 #4 SRS 3.317
#5 SRS 3.219 #6 SRS 1.951 #7 PC ET 2.379 #8 TAP 0.136

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
O₂ (%) 6.320
CO (ppm) 13.000 15.940 17.799
NOx (ppm) 123.000 150.817 168.402 0.229
SO₂ w/LS (ppm) 152.000 186.376 208.106 0.394
SOx w/o LS (ppm), calc 333.264 404.539 449.592

AIR TEMPERATURES (deg F):

Air Preheat Inlet 131.000

Preheat Outlet 378.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 624.500 FG Preheat Outlet 407.500

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 14.840
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 338.000Flash Tank 1.880
Flash Tank 103.000
Flash Tank 338.000

Total Steam 16.720

Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 19.754
Coal + N. Gas - MMBtu/hr 19.754

Cooling (Coal + N Gas) - % 9.612

Cooling H₂O Inlet (deg F) 341.700

RESULTS: Steam Gen Eff'cy (%) 82.214

Fuel to Steam Flow Corr. 0.961

Boiler Efficiency (%) 81.422

% SO₂ Reduction 53.712

Intrusion Air (#/hr) 6107.82

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 537-H48 Date 05/22/91
PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

2 00.400

NATURAL GAS: Btu/lb _____
Hydrogen (# H2/# NG): _____

Stoich air (# air/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 169

Section: _____ Time of Test: 5:53

FLOW RATES:

Coal PC (#/hr) 1147.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.340
Mix Bustle Air PC (kpph) 6.100
Coal MC (#/hr) 1322.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 0.000

LS (#/hr) 51.000
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Mzl Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.761
SCFH to #/hr 0.076

Total Air (#/hr) 15782.521
Stoi Air (#/hr) 14776.588
Xcss Air SB (#/hr) 1005.933
Total Coal (#/hr) 2469.000
Total Gas (#/hr) 17754.381
% O2 post SB Cmbn 1.238
Coal Split PC (%) 46.456
Ca Utilization, % 29.204

STUICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.063
PC phi 1.951
MC phi 1.019
Overall phi at Sec. Brnr 1.019

Cling Calc (Btu/sec) 421.200 Cling Meas (Btu/sec) 631.250 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:
FLUX (Btu/ft2-sec):
#1 AI 0.581 #2 AI 1.177 #3 BAF 3.266 #4 SRS 3.922
#5 SRS 3.330 #6 SRS 3.013 #7 PC ET 2.667 #8 TAP 0.000

EMISSIONS:

A: stack As meas.
O2 (%) 6.220
CO (ppm) 22.400
NOx (ppm) 134.800
SO2 w/LS (ppm) 160.700
SOx w/c LS (ppm), calc 335.419

At 3% O2 At Calc SB O2 #/MMBtu
27.280 29.951
164.168 180.241 0.249
195.710 214.872 0.413
404.549 442.383

AIR TEMPERATURES (deg F):

Air Preheat Inlet 138.200 Preheat Outlet 398.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 618.000 FG Preheat Outlet 413.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 14.840
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 337.000

Flash Tank 2.250
Flash Tank 103.000
Flash Tank 337.000

Total Steam 17.090
Feed H2O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 19.722
Coal + N. Gas - MMBtu/hr 19.722

Cooling (Coal + N Gas) - % 11.522 Cooling H2O Inlet (deg F) 342.000

RESULTS: Stear. Gen Eff'cy (%) 82.103 Fuel to Steam Flow Corr. 0.936

Boiler Efficiency (%) 80.884 % SO2 Reduction 51.428 Intrusion Air (#/hr) 5661.82

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 539-H50

Date 05/22/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc, deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO3: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H2/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 196

Section: _____

Time of Test: 16:45

FLOW RATES:

Coal PC (#/hr) 1159.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.260
Mix Bustle Air PC (kpph) 5.720
Coal MC (#/hr) 1334.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 0.846

LS (#/hr) 50.000

Total Air (#/hr) 16168.521

LS Split (I/W) 100/0

Stoi Air (#/hr) 14920.224

Nozzles _____

Xcss Air SB (#/hr) 1248.296

Carr'r A/LS (scfh) 9540.270

Total Coal (#/hr) 2493.000

C.A. Press (psig) Edc Nz1 Dia 0.375

Total Gas (#/hr) 18158.879

Nozzles (throat): _____

% O2 post SB Cmbn 1.502

Injector (tube): 50.000

Coal Split PC (%) 46.490

Ca/S Ratio 1.710

Ca Utilization, % 33.567

SCFH to #/hr 0.076

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.040

Cling Calc (Btu/sec) 409.680 Cling Meas (Btu/sec) 541.753 Flow #/sec 28.800

PC phi 1.865

Total flow assumed equal over all 8 circuits:

MC phi 0.978

FLUX (Btu/ft2-sec):

Overall phi at Sec. Brnr 1.035

#1 AI 0.566 #2 AI 1.165 #3 BAF 2.776 #4 SRS 3.906

#5 SRS 3.473 #6 SRS 2.680 #7 PC ET 2.614 #9 TAP 0.409

EMISSIONS:

At stack As meas.

At 3% O2

At Calc SB O2

#/MMBtu

O2 (%) 6.120

CO (ppm) 16.150

19.536

21.163

NOx (ppm) 126.000

152.415

165.107

0.231

SO2 w/LS (ppm) 142.000

171.774

186.073

0.362

SOx w/o LS (ppm), calc 337.579

404.565

436.733

AIR TEMPERATURES (deg F):

Air Preheat Inlet 139.000

Preheat Outlet 395.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 636.000

FG Preheat Outlet 415.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.399

Flash Tank 1.931

Total Steam 17.330

Press. (psig): Boiler 103.000

Flash Tank 103.000

Temps. (deg F): Boiler 336.000

Flash Tank 336.000

Feed H2O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 19.914

Cooling (Coal + N Gas) - % 9.794

Cooling H2O Inlet (deg F) 340.100

Coal + N. Gas - MMBtu/hr 19.914

RESULTS: Steam Gen Eff'cy (%) 82.106

Fuel to Steam Flow Corr. 0.933

Boiler Efficiency (%) 81.255

% SO2 Reduction 57.394

Intrusion Air (#/hr) 5333.64

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 540-H51 Date 05/23/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND

Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340

Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 44

Section: _____ Time of Test: 1:04

FLOW RATES:

Coal PC (#/hr) 1169.000

Carrier Air PC (scfh) 12500.000

Combustion Air PC (kpph) 6.105

Mix Bustle Air PC (kpph) 6.050

Coal MC (#/hr) 1346.000

Carrier Air MC (scfh) 21710.000

Cmbn Air Sec Brnr (kpph) 0.000

LS (#/hr) 52.500

LS Split (I/W) 100/0

Nozzles _____

Carr'r A/LS (scfh) 9540.270

C.A. Press (psig) Edc Wzl Dia 0.375

Nozzles (throat): _____

Injector (tube): 50.000

Ca/S Ratio 1.780

SCFH to #/hr 0.076

Total Air (#/hr) 15497.521

Stoi Air (#/hr) 15051.891

Xcss Air SB (#/hr) 445.630

Total Coal (#/hr) 2515.000

Total Gas (#/hr) 17506.365

% O₂ post SE Cmbn 0.556

Coal Split PC (%) 46.481

Ca Utilization, % 31.710

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.009

PC phi 1.874

MC phi 0.981

Overall phi at Sec. Brnr 0.981

Cling Calc (Btu/sec) 385.200 Cling Meas (Btu/sec) 490.972 Flow #/sec 29.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI 0.435 #2 AI 1.295 #3 BAF 3.266 #4 SRS 4.085

#5 SRS 2.855 #6 SRS 2.379 #7 PC ET 2.241 #9 TAP 0.000

EMISSIONS:

At stack As meas.

O₂ (%) 6.420

CO (ppm) 6.170

NOx (ppm) 121.000

SO₂ w/LS (ppm) 142.000

SOx w/o LS (ppm), calc 331.120

At 3% O₂

7.617

223.457

175.309

404.543

At Calc SB O₂

8.652

253.797

199.111

457.009

#/MMBtu

0.339

0.371

AIR TEMPERATURES (deg F):

Air Preheat Inlet 139.000

Preheat Outlet 348.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 582.000

FG Preheat Outlet 357.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 14.780

Press. (psig): Boiler 103.000

Temps. (deg F): Boiler 335.000

Flash Tank 1.750

Flash Tank 103.000

Flash Tank 335.000

Total Steam 16.530

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 20.090

Coal + N. Gas - MMBtu/hr 20.090

Cooling (Coal + N Gas) - % 8.798

Cooling H₂O Inlet (deg F) 339.000

RESULTS: Steam Gen Eff'cy (%) 83.777

Fuel to Steam Flow Corr. 1.000

Boiler Efficiency (%) 83.328

% SO₂ Reduction 50.432

Intrusion Air (#/hr) 6655.75

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0
Date: 6/10/91TEST: 541-H52 Date 05/23/91
PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIROCOAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988LIMESTONE: CANTWELL % CaCO₃: 90.400 NATURAL GAS: Btu/lb _____ Stoich air (# air/# NG): _____
Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 184

Section: _____ Time of Test: 10:02

FLOW RATES:

Coal PC (#/hr) 1171.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.110
Mix Bustle Air PC (kpph) 6.020
Coal MC (#/hr) 1350.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 0.000LS (#/hr) 47.000
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Wzl Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.589
SCFH to #/hr 0.076Total Air (#/hr) 15472.521
Stoi Air (#/hr) 15087.800
Xcss Air SB (#/hr) 384.721
Total Coal (#/hr) 2521.000
Total Gas (#/hr) 17483.639
% O₂ post SB Cmbn 0.481
Coal Split PC (%) 46.450
Ca Utilization, % 30.139STOICHIOMETRIC AIR: (for Coal) 5.985
STOICH. AIR: (# air/# tot fuel) 5.985
PHI's: PCC phi 1.003
PC phi 1.867
MC phi 0.977
Overall phi at Sec. Brnr 0.977Cling Calc (Btu/sec) 439.200 Cling Meas (Btu/sec) 639.667 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:
FLUX (Btu/ft²-sec):
#1 AI 0.435 #2 AI 1.177 #3 BAF 3.266 #4 SRS 4.576
#5 SRS 3.172 #6 SRS 2.696 #7 PC ET 3.308 #8 TAP -0.454

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
O₂ (%) 5.630
CO (ppm) 61.000 71.438 81.437
NO_x (ppm) 116.000 135.849 154.863 0.206
SO₂ w/LS (ppm) 179.000 209.629 238.970 0.443
SO_x w/o LS (ppm), calc 340.131 404.602 458.694

AIR TEMPERATURES (deg F):

Air Preheat Inlet 148.000 Preheat Outlet 410.000 Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 636.600 FG Preheat Outlet 433.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.170
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 337.000Flash Tank 2.280 Total Steam 17.450
Flash Tank 103.000
Flash Tank 337.000 Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 20.138
Coal + N. Gas - MMBtu/hr 20.138Cooling (Cra) + N Gas) - % 11.435 Cooling H₂O Inlet (deg F) 342.000

RESULTS: Steam Gen Eff'cy (%) 81.852 Fuel to Steam Flow Corr. 0.933

Boiler Efficiency (%) 80.600 % SO₂ Reduction 47.902 Intrusion Air (#/hr) 5552.64

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 542-H53 Date 05/23/91
 PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
 Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
 Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____
 Hydrogen (# H₂/# NG): _____

Stoich air (# air/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 138

Section: _____ Time of Test: 19:18

FLOW RATES:

Coal PC (#/hr) 1160.000
 Carrier Air PC (scfh) 12500.000
 Combustion Air PC (kpph) 6.380
 Mix Bustle Air PC (kpph) 6.165
 Coal MC (#/hr) 1336.500
 Carrier Air MC (scfh) 21710.000
 Cmbn Air Sec Brnr (kpph) 1.202

LS (#/hr) 51.600
 LS Split (I/W) 100/0
 # Nozzles _____
 Carr'r A/LS (scfh) 9540.270
 C.A. Press (psig) Edc Nzl Dia 0.375
 Nozzles (throat): _____
 Injector (tube): 50.000
 Ca/S Ratio 1.762
 SCFH to #/hr 0.076

Total Air (#/hr) 17089.521
 Stoic Air (#/hr) 14941.171
 Xcss Air SB (#/hr) 2148.349
 Total Coal (#/hr) 2496.500
 Total Gas (#/hr) 19083.358
 % O₂ post SB Cmbn 2.459
 Coal Split PC (%) 46.465
 Ca Utilization, % 30.015

STOICHIOMETRIC AIR: (for Coal) 5.985
 STOICH. AIR: (# air/# tot fuel) 5.985
 PHI's: PCC phi 1.057
 PC phi 1.945
 MC phi 1.015
 Overall phi at Sec. Brnr 1.095

Cling Calc (Btu/sec) 482.400 Cling Meas (Btu/sec) 664.917 Flow #/sec 28.800
 Total flow assumed equal over all 8 circuits:
 FLUX (Btu/ft²-sec):
 #1 AI 1.016 #2 AI 1.295 #3 BAF 3.500 #4 SRS 4.902
 #5 SRS 3.806 #6 SRS 3.013 #7 PC ET 2.988 #9 TAP 0.000

EMISSIONS:

At stack As meas.
 O₂ (%) 6.115
 CO (ppm) 13.692
 NOx (ppm) 115.000
 SO₂ w/LS (ppm) 157.400
 SOx w/o LS (ppm), calc 337.672

At 3% O₂ At Calc SB O₂ #/MMBtu
 16.557 17.055
 139.066 143.245 0.210
 190.339 196.059 0.401
 404.548 416.159

AIR TEMPERATURES (deg F):

Air Preheat Inlet 140.200

Preheat Outlet 393.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 639.400

FG Preheat Outlet 418.800

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 16.000
 Press. (psig): Boiler 103.000
 Temps. (deg F): Boiler 336.000

Flash Tank 2.370 Total Steam 18.370
 Flash Tank 103.000
 Flash Tank 336.000 Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 19.942
 Coal + N. Gas - MMBtu/hr 19.942

Cooling (Coal + N Gas) - % 12.003 Cooling H₂O Inlet (deg F) 340.000

RESULTS: Steam Gen Eff'cy (%) 81.982 Fuel to Steam Flow Corr. 0.878

Boiler Efficiency (%) 80.639 % SO₂ Reduction 52.888 Intrusion Air (#/hr) 4435.62

REMARKS: COMBUSTOR CLEANED PRIOR TO THIS TEST.

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 543-H54

Date 05/24/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 129

Section: _____ Time of Test: 0:17

FLOW RATES:

Coal PC (#/hr) 1143.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.150
Mix Bustle Air PC (kpph) 5.650
Coal MC (#/hr) 1316.500
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 0.080LS (#/hr) 51.000
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc H₂l Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.768
SCFH to #/hr 0.076Total Air (#/hr) 15222.521
Stoi Air (#/hr) 14719.732
Xcss Air SB (#/hr) 502.789
Total Coal (#/hr) 2459.500
Total Gas (#/hr) 17186.882
% O₂ post SB Cmbn 0.639
Coal Split PC (%) 46.473
Ca Utilization, % 28.899

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# to: fuel) 5.985

PHI's: PCC phi 1.039

PC phi 1.865

MC phi 0.979

Overall phi at Sec. Brnr 0.985

Cling Calc (Btu/sec) 414.000 Cling Meas (Btu/sec) 565.600 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FlUX (Btu/ft²-sec):#1 AI 0.581 #2 AI 1.060 #3 BAF 2.800 #4 SRS 4.249
#5 SRS 3.642 #6 SRS 2.537 #7 PC ET 2.667 #9 TAP 0.000

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
O₂ (%) 6.790
CO (ppm) 10.867 13.765 15.571
NO_x (ppm) 129.000 163.406 184.839 0.248
SO₂ w/LS (ppm) 165.400 196.847 222.667 0.416
SO₂ w/o LS (ppm), calc 323.180 404.546 455.231

AIR TEMPERATURES (deg F):

Air Preheat Inlet 135.800

Preheat Outlet 397.600

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 636.000

FG Preheat Outlet 418.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 13.904
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 337.000Flash Tank 2.016 Total Steam 15.920
Flash Tank 103.000
Flash Tank 337.000 Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 19.646
Coal + N. Gas - MMBtu/hr 19.646Cooling (Coal + N Gas) - % 10.364 Cooling H₂O Inlet (deg F) 341.000

RESULTS: Steam Gen Eff'cy (%) 81.579

Fuel to Steam Flow Corr. 0.996

Boiler Efficiency (%) 80.542

% SO₂ Reduction 51.087

Intrusion Air (#/hr) 7022.58

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 544-H55 Date 05/23/91
 PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR WIRO

COAL: Source: HEALY PERF BLEND
 Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.820 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
 Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 16C

Suction: _____ Time of Test: 4:36

FLOW RATES:

Coal PC (#/hr)	1147.000	LS (#/hr)	48.900	Total Air (#/hr)	16651.521
Carrier Air PC (scfh)	12500.000	LS Split (I/N)	100/0	Stoic Air (#/hr)	14764.618
Combustion Air PC (kpph)	6.283	# Nozzles	_____	Excess Air SB (#/hr)	1886.902
Mix Bustle Air PC (kpph)	5.978	Carr'r A/LS (scfh)	9540.270	Total Coal (#/hr)	2467.000
Coal MC (#/hr)	1323.000	C.A. Press (psig)	Edc Nz1 Dia 0.375	Total Gas (#/hr)	18620.862
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% O ₂ post SB Cmbn	2.213
Cmbn Air Sec Brnr (kpph)	1.048	Injector (tube):	50.000	Coal Split PC (%)	46.49%
		Ca/S Ratio	1.69C	Ca Utilization, %	30.739
		SCFH to #/hr	0.076		
STOICHIOMETRIC AIR: (for Coal)	5.585	Cing Calc (Btu/sec)	433.440	Cing Meas (Btu/sec)	575.139
STOICH. AIR: (# air/# tot fuel)	5.985	Total flow assumed equal over all 8 circuits:		Flow #/sec	28.800
PHI's: PCC phi	1.054	FLUX (Btu/ft ² -sec):			
PC phi	1.925	#1 AI	0.552	#2 AI	1.036
MC phi	1.007	#5 SRS	3.774	#6 SRS	2.823
Overall phi at Sec. Brnr	1.078			#7 PC ET	2.753
				#8 SRS	4.379
				#9 TAP	-0.545

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	6.270			
CO (ppm)	54.800	66.965	69.891	
NOx (ppm)	123.300	150.672	157.256	0.228
SO ₂ w/LS (ppm)	158.800	194.053	202.532	0.409
SOx w/o LS (ppm), calc	334.364	404.571	421.456	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 138.800

Preheat Outlet 401.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 642.000

FG Preheat Outlet 417.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH):

Press. (psig):

Temps. (deg F):

Boiler 15.800

Boiler 103.000

Boiler 337.000

Flash Tank

Flash Tank

Flash Tank

2.050

103.000

337.000

Total Steam 17.850

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS:

Coal - MMBtu/hr 19.706

Coal + N. Gas - MMBtu/hr 19.706

Cooling (Coal + N Gas) - %

10.507

Cooling H₂O Inlet (deg F) 340.200

RESULTS:

Steam Gen Eff'cy (%) 81.954

Fuel to Steam Flow Corr.

0.893

Boiler Efficiency (%) 80.928

% SO₂ Reduction 51.945

Intrusion Air (#/hr) 4850.20

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 545-H56

Date 05/24/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T260 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 141

Section: _____

Time of Test: 9:28

FLOW RATES:

Coal PC (#/hr) 1167.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 8.210
Mix Bustle Air PC (kpph) 8.000
Coal MC (#/hr) 1344.500
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 0.750LS (#/hr) 48.000
LS Split (I/N) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Nzl Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.629
SCFH to #/hr 0.076Total Air (#/hr) 16432.521
Stoi Air (#/hr) 15030.944
Xcess Air SB (#/hr) 1401.577
Total Coal (#/hr) 2511.500
Total Gas (#/hr) 18436.587
% O₂ post SB Cmbn 1.661
Coal Split PC (%) 46.466
Ca Utilization, % 33.895

STOICHIOMETRIC AIP: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.036
PC phi 1.904
MC phi 0.995
Overall phi at Sec. Brnr 1.045Cling Calc (Btu/sec) 450.000 Cling Meas (Btu/sec) 614.417 Flow #/sec 28.830
Total flow assumed equal over all 8 circuits:
FLUX (Btu/ft²-sec):
#1 AI 0.726 #2 AI 1.413 #3 BAF 4.433 #4 SRS 4.085
#5 SRS 3.965 #6 SRS 2.537 #7 PC ET 2.454 #9 TAP 0.000

EMISSIONS:

At stacr As meas.
O₂ (%) 5.650
CO (ppm) 25.700
NOx (ppm) 113.000
SO₂ w/LS (ppm) 154.000
SOx w/o LS (ppm), calc 347.691At 3% O₂ At Calc SB O₂ #/MMBtu
30.137 32.379
132.508 142.368 0.201
180.586 194.024 0.381
404.590 433.346

AIR TEMPERATURES (deg F):

Air Preheat Inlet 133.000

Preheat Outlet 397.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 638.000

FG Preheat Outlet 415.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 17.250
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 334.800Flash Tank 2.190 Total Steam 19.440
Flash Tank 103.000
Flash Tank 334.800 Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 20.062
Coal + N. Gas - MMBtu/hr 20.062Cooling (Coal + N Gas) - % 11.025 Cooling H₂O Inlet (deg F) 339.000

RESULTS: Steam Gen Eff'cy (%) 82.390

Fuel to Steam Flow Corr. 0.838

Boiler Efficiency (%) 81.307

% SO₂ Reduction 55.227

Intrusion Air (#/hr) 4541.94

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 546-H57 Date 06/28/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NO): _____

Hydrogen (# H₂/# NO): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): ~~224~~ 213 Section: _____ Time of Test: 12:14

FLOW RATES:

Coal PC (#/hr)	1173.000	LS (#/hr)	47.600	Total Air (#/hr)	15172.521	
Carrier Air PC (scfh)	12500.000	LS Split (I/M)	100/0	Stoi Air (#/hr)	15111.740	
Combustion Air PC (kpph)	5.980	# Nozzles	_____	Xcss Air SB (#/hr)	60.781	
Mix Bustle Air PC (kpph)	5.850	Carr'r A/LS (scfh)	9540.270	Total Coal (#/hr)	2525.000	
Coal MC (#/hr)	1352.000	C.A. Press (psig)	Ecc Nzl Dia	0.375	Total Gas (#/hr)	17187.065
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% O ₂ post SB Cmbn	0.077	
Cmbn Air Sec Brnr (kpph)	0.000	Injector (tube):	50.000	Coal Split PC (%)	46.455	
		Ca/S Ratio	1.607	Ca Utilization, %	30.097	
		SCFH to #/hr	0.076			

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 0.988

PC phi 1.821

MC phi 0.956

Overall phi at Sec. Brnr 0.956

Cling Calc (Btu/sec) 396.000 Cling Meas (Btu/sec) 552.694 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI	1.103	#2 AI	1.060	#3 BAF	3.733	#4 SRS	3.857
#5 SRS	2.855	#6 SRS	2.347	#7 PC ET	2.187	#9 TAP	0.227

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	5.600			
CO (ppm)	48.200	56.338	65.485	
NOx (ppm)	112.300	131.260	152.573	0.199
SO ₂ w/LS (ppm)	177.600	207.584	241.291	0.439
SOx w/o LS (ppm), calc	348.771	404.597	467.350	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 144.000 Preheat Outlet 398.000 Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 604.500 FG Preheat Outlet 420.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.470

Flash Tank 1.970

Total Steam 17.440

Press. (psig): Boiler 103.000

Flash Tank 103.000

Temps. (deg F): Boiler 336.000

Flash Tank 336.000

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 20.170

Cooling (Coal + N Gas) - % 9.865

Cooling H₂O Inlet (deg F) 341.000

Coal + N. Gas - MMBtu/hr 20.170

RESULTS: Steam Gen Eff'cy (%) 82.267

Fuel to Steam Flow Corr. 0.941

Boiler Efficiency (%) 81.412

% SO₂ Reduction 48.370

Intrusion Air (#/hr) 5843.47

REMARKS:

Coal Injector pushed in 2" more (8" total injector length). Combustor cleaned
Prior to test.

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0
Date: 6/10/91

TEST: 547-H58 Date 05/28/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.45C Hydrogen: 3.62O Oxygen: 15.98O Nitrogen: 0.73O Sulfur: 0.34O
Moisture: 10.83O Ash: 21.06O T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 170

Section: _____ Time of Test: 12:09

FLOW RATES:

Coal PC (#/hr)	1156.000	LS (#/hr)	48.500	Total Air (#/hr)	15592.521
Carrier Air PC (scfh)	12500.000	LS Split (I/W)	100/0	Stoi Air (#/hr)	14893.293
Combustion Air PC (kpph)	6.230	# Nozzles	_____	Xcss Air SB (#/hr)	699.228
Mix Bustle Air PC (kpph)	6.020	Carr'r A/LS (scfh)	9540.270	Total Coal (#/hr)	2488.500
Coal MC (#/hr)	1332.500	C.A. Press (psig)	Edc Nz1 Dia 0.375	Total Gas (#/hr)	17578.655
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% O ₂ post SB Cmbn	0.869
Cmbn Air Sec Brnr (kpph)	0.000	Injector (tube):	50.000	Coal Split PC (%)	46.454
		Ca/S Ratio	1.662	Ca Utilization, %	33.190
		SCFH to #/hr	0.076		
STOICHIOMETRIC AIR: (for Coal)	5.985	Cling Calc (Btu/sec)	388.800	Cling Meas (Btu/sec)	523.236
STOICH. AIR: (# air/# tot fuel)	5.985	Total flow assumed equal over all 8 circuits:		Flow #/sec	28.800
PHI's: PCC phi	1.039	FLUX (Btu/ft ² -sec):			
PC phi	1.909	#1 AI	0.762	#2 AI	1.501
MC phi	0.998	#5 SRS	2.498	#6 SRS	2.577
Overall phi at Sec. Brnr	0.998			#3 BAF	2.741
				#4 SRS	3.718
				#7 PC ET	2.214
				#8 TAP	1.248

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	6.200			
CO (ppm)	15.600	18.973	21.219	
NO _x (ppm)	137.400	167.108	186.893	0.253
SO ₂ w/LS (ppm)	148.500	180.608	201.991	0.381
SO _x w/c LS (ppm), calc	335.874	404.580	450.334	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 140.000

Preheat Outlet 407.600

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 598.800

FG Preheat Outlet 424.400

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH):	Boiler	14.595	Flash Tank	1.865	Total Steam	16.460
Press. (psig):	Boiler	103.000	Flash Tank	103.000		
Temps. (deg F):	Boiler	336.000	Flash Tank	336.000	Feed H ₂ O (deg F)	212.000

COMBUSTOR LOADS:	Coal - MMBtu/hr	19.878	Cooling (Coal + N Gas) - %	9.476	Cooling H ₂ O Inlet (deg F)	340.250
	Coal + N. Gas - MMBtu/hr	19.878				

RESULTS:	Steam Gen Eff'cy (%)	81.765	Fuel to Steam Flow Corr.	0.977		
	Boiler Efficiency (%)	80.936	% SO ₂ Reduction	55.146	Intrusion Air (#/hr)	5993.50

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 548-H59

Date 05/29/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.820 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400NATURAL GAS: Btu/lb _____
Hydrogen (# H₂/# NG): _____

Stoich air (# air/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 108

Section: _____ Time of Test: 00:18

FLOW RATES:

Coal PC (#/hr)	1154.000	LS (#/hr)	50.000	Total Air (#/hr)	15472.521
Carrier Air PC (scfh)	12500.000	LS Split (I/W)	100/0	Stoi Air (#/hr)	14860.376
Combustion Air PC (kpph)	6.200	# Nozzles	_____	Xcss Air SB (#/hr)	612.145
Mix Bustle Air PC (kpph)	5.930	Carrr'r A/LS (scfh)	9540.270	Total Coal (#/hr)	2483.000
Coal MC (#/hr)	1329.000	C.A. Press (psig)	Edc Nzl Dia 0.375	Total Gas (#/hr)	17454.985
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% O ₂ post SB Cmbn	0.766
Cmbn Air Sec Brnr (kpph)	0.000	Injector (tube):	50.000	Coal Split PC (%)	46.476
		Ca/S Ratio	1.717	Ca Utilization, %	31.318
		SCFH to #/hr	0.076		

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.036

PC phi 1.895

MC phi 0.992

Overall phi at Sec. Brnr 0.992

Cling Calc (Btu/sec) 370.800 Clng Meas (Btu/sec) 527.444 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI	0.071	#2 AI	1.413	#3 BAF	2.566	#4 SRS	3.432
#5 SRS	2.379	#6 SRS	2.537	#7 PC ET	2.134	#9 TAP	0.908

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	6.010			
CO (ppm)	9.380	11.264	12.661	
NOx (ppm)	156.000	187.325	210.573	0.284
SO ₂ w/LS (ppm)	155.000	186.124	209.224	0.393
SOx w/o LS (ppm), calc	339.939	404.562	452.522	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 141.000

Preheat Outlet 358.500

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 548.500

FG Preheat Outlet 371.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.040

Flash Tank 1.880

Total Steam 16.920

Press. (psig): Boiler 103.000

Flash Tank 103.000

Temps. (deg F): Boiler 336.000

Flash Tank 336.000

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 19.834

Cooling (Coal + N Gas) - % 9.573

Cooling H₂O Inlet (deg F) 341.000

Coal + N. Gas - MMBtu/hr 19.834

RESULTS: Steam Gen Eff'cy (%) 83.552

Fuel to Steam Flow Corr. 0.969

Boiler Efficiency (%) 82.924

% SO₂ Reduction 53.765

Intrusion Air (#/hr) 5780.87

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 549-H60 Date 05/29/91
 PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
 Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
 Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 157

Section: _____ Time of Test: 6:07

FLOW RATES:

Coal PC (#/hr) 1140.000
 Carrier Air PC (scfh) 12500.000
 Combustion Air PC (kpph) 5.964
 Mix Bustle Air PC (kpph) 5.802
 Coal MC (#/hr) 1314.000
 Carrier Air MC (scfh) 21710.000
 Comb Air Sec Brnr (kpph) 0.000

LS (#/hr) 50.500
 LS Split (I/W) 100/0
 # Nozzles _____
 Carr'r A/LS (scfh) 9540.270
 C.A. Press (psig) Edc Wz1 Dia 0.375
 Nozzles (throat): _____
 Injector (tube): 50.000
 Ca/S Ratio 1.754
 SCFH to #/hr 0.076

Total Air (#/hr) 15108.521
 Stoi Air (#/hr) 14686.815
 Xcss Air SB (#/hr) 421.705
 Total Coal (#/hr) 2454.000
 Total Gas (#/hr) 17068.316
 % O₂ post SB Cmbn 0.540
 Coal Split PC (%) 46.455
 Ca Utilization, % 28.763

STOICHIOMETRIC AIR: (for Coal) 5.985
 STOICH. AIR: (# air/# tot fuel) 5.985
 PHI's: PC phi 1.014
 PC phi 1.865
 MC phi 0.979
 Overall phi at Sec. Brnr 0.979

Cing Calc (Btu/sec) 363.600 Cing Meas (Btu/sec) 490.411 Flow #/sec 20.800
 Total flow assumed equal over all 8 circuits:
 FLUX (Btu/ft²-sec):
 #1 AI 0.798 #2 AI 1.236 #3 BAF 2.450 #4 SRS 3.350
 #5 SRS 2.617 #6 SRS 2.458 #7 PC ET 2.187 #9 TAP 0.691

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	5.739			
CO (ppm)	27.000	31.846	36.199	
NOx (ppm)	130.000	153.332	174.290	0.233
SO ₂ w/LS (ppm)	169.000	199.332	226.577	0.421
SOx w/o LS (ppm), calc	345.747	404.551	457.369	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 142.500 Preheat Outlet 390.000 Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 602.000 FG Preheat Outlet 410.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.132
 Press. (psig): Boiler 103.000
 Temps. (deg F): Boiler 336.500

Flash Tank 1.748 Total Steam 16.880
 Flash Tank 103.000
 Flash Tank 336.500 Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 19.603 Cooling (Coal + N Gas) - % 9.006 Cooling H₂O Inlet (deg F) 340.500
 Coal + N. Gas - MMBtu/hr 19.603

RESULTS: Steam Gen Eff'cy (%) 82.478 Fuel to Steam Flow Corr. 0.947

Boiler Efficiency (%) 81.841 % SO₂ Reduction 50.461 Intrusion Air (#/hr) 5510.39

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 553-H61 Date 05/29/91
 PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR MIRO

COAL: Source: HEALY PERF BLEND
 Ultimate Analysis Applied

Composition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
 Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL % CaCO₃: 90.400 NATURAL GAS: Btu/lb _____ Stoich air (# air/# NG): _____
 Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins):	196	Section:	_____	Time of Test:	11:12
FLOW RATES:					
Coal PC (#/hr)	1168.000	LS (#/hr)	50.000	Total Air (#/hr)	15902.521
Carrier Air PC (scfh)	12500.000	LS Split (I/W)	100/0	Stoi Air (#/hr)	15033.936
Combustion Air PC (kpph)	6.280	# Nozzles	_____	Xcss Air SB (#/hr)	862.584
Mix Bustle Air PC (kpph)	6.280	Carr'r A/LS (scfh)	9540.270	Total Coal (#/hr)	2512.000
Coal MC (#/hr)	1344.000	C.A. Press (psig)	Edc Nzl Dia	Total Gas (#/hr)	17907.877
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% O ₂ post SB Cmbn	1.059
Cmbn Air Sec Brnr (kpph)	0.000	Injector (tube):	50.900	Coal Split PC (%)	46.497
		Ca/S Ratio	1.697	Ca Utilization, %	26.327
STOICHIOMETRIC AIR: (for Coal)	5.985	SCFH to #/hr	0.076		
STOICH. AIR: (# air/# tot fuel)	5.985				
PHI's: PCC phi	1.035	Cing Calc (Btu/sec)	367.920	Cing Meas (Btu/sec)	533.617
PC phi	1.933	Total flow assumed equal over all 8 circuits:		Flow #/sec	28.800
MC phi	1.009	FLUX (Btu/ft ² -sec):			
Overall phi at Sec. Brnr	1.009	01 AI	0.479	02 AI	1.330
		05 SRS	2.648	06 SRS	2.648
				07 PC ET	2.187
				08 SRS	3.481
				09 TAP	0.145

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	5.920			
CO (ppm)	41.100	49.058	54.347	
NO _x (ppm)	132.000	157.560	174.546	0.239
SO ₂ w/LS (ppm)	186.700	222.851	245.876	C.470
SO _x w/c LS (ppm), calc	341.876	404.569	446.229	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 140.300 Preheat Outlet 384.500 Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 596.300 FG Preheat Outlet 401.300

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH):	Boiler	14.598	Flash Tank	1.902	Total Steam	16.500
Press. (psig):	Boiler	103.000	Flash Tank	103.000		
Temps. (deg F):	Boiler	337.000	Flash Tank	337.000	Feed H ₂ O (deg F)	212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 20.066 Cooling (Coal + N Gas) - % 9.574 Cooling H₂O Inlet (deg F) 342.000
 Coal + N. Gas - MMBtu/hr 20.066

RESULTS: Stear. Gen Eff'cy (%) 82.654 Fuel to Steam Flow Corr. 0.995
 Boiler Efficiency (%) 91.915 % SO₂ Reduction 44.675 Intrusion Air (#/hr) 5466.14

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 551-H62

Date 05/29/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7988

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 93

Section: _____ Time of Test: 18:17

FLOW RATES:

Coal PC (#/hr) 1153.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.140
Mix Bustle Air PC (kpph) 6.050
Coal MC (#/hr) 1327.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 1.690LS (#/hr) 49.500
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Wz1 Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.702
SCFH to #/hr 0.076Total Air (#/hr) 17222.521
Stoi Air (#/hr) 14842.421
Xcss Air SB (#/hr) 2380.099
Total Coal (#/hr) 2480.000
Total Gas (#/hr) 19202.393
% O₂ post SB Cmbn 2.707
Coal Split PC (%) 46.492
Ca Utilization, % 20.030STOICHIOMETRIC AIR: (for Coal) 5.985
STOICH. AIR: (# air/# tot fuel) 5.985
PHI's: PCC phi 1.028
PC phi 1.905
MC phi 0.997
Overall phi at Sec. Brnr 1.111Cing Calc (Btu/sec) 349.200 Cing Meas (Btu/sec) 482.556 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:
FLUX (Btu/ft²-sec):
#1 AI 0.280 #2 AI 1.413 #3 BAF 2.333 #4 SRS 2.941
#5 SRS 2.696 #6 SRS 2.696 #7 PC ET 2.134 #8 TAP 0.454

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
O₂ (%) 6.167
CO (ppm) 25.000 30.338 30.831
NOx (ppm) 132.000 160.183 162.786 0.242
SO₂ w/LS (ppm) 219.600 266.487 270.817 0.561
SOx w/o LS (ppm), calc 336.572 404.567 410.846

AIR TEMPERATURES (deg F):

Air Preheat Inlet 138.000 Preheat Outlet 381.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 620.500 FG Preheat Outlet 401.800

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.060
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 338.000Flash Tank 1.720 Total Steam 16.780
Flash Tank 103.000
Flash Tank 338.000 Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 19.810
Coal + N. Gas - MMBtu/hr 19.810Cooling (Coal + N Gas) - % 8.769 Cooling H₂O Inlet (deg F) 341.000

RESULTS: Steam Gen Eff'cy (%) 82.497

Fuel to Steam Flow Corr. 0.963

Boiler Efficiency (%) 81.903

% SO₂ Reduction 34.083

Intrusion Air (#/hr) 4237.54

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/10/91

TEST: 552-H63 Date 05/29/91

PURPOSE: GENERATE 5 TONS OF BAGHOUSE CATCH FOR NIRO

COAL: Source: HEALY PERF BLEND
Ultimate Analysis AppliedComposition (%) - Carbon: 47.450 Hydrogen: 3.620 Oxygen: 15.980 Nitrogen: 0.730 Sulfur: 0.340
Moisture: 10.830 Ash: 21.060 T250 (calc. deg F): 2715 HHV (Btu/lb): 7986

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 111

Section: _____

Time of Test: 22:04

FLOW RATES:

Coal PC (#/hr) 1134.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.435
Mix Bustle Air PC (kpph) 6.230
Coal MC (#/hr) 1306.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 1.780LS (#/hr) 48.800
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Nzl Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 1.705
SCFH to #/hr 0.076Total Air (#/hr) 17787.521
Stoi Air (#/hr) 14603.027
Xcss Air SB (#/hr) 3184.493
Total Coal (#/hr) 2440.000
Total Gas (#/hr) 19735.503
% O₂ post SB Cmbn 3.525
Coal Split PC (%) 46.475
Ca Utilization, % 32.145

STOICHIOMETRIC AIR: (for Coal) 5.985

STOICH. AIR: (# air/# tot fuel) 5.985

PHI's: PCC phi 1.089

PC phi 2.007

MC phi 1.046

Overall phi at Sec. Brnr 1.168

Cling Calc (Btu/sec) 360.000 Cling Meas (Btu/sec) 475.542 Flow #/sec 28.803

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

#1 AI	0.435	#2 AC	1.295	#3 BAF	2.566	#4 SRS	3.432
#5 SRS	2.696	#6 SRS	2.379	#7 PC ET	2.241	#8 TAP	0.454

EMISSIONS:

At stack As meas.
O₂ (%) 6.350
CO (ppm) 83.000
NOx (ppm) 142.500
SO₂ w/LS (ppm) 149.000
SOx w/o LS (ppm), calc 332.642At 3% O₂ At Calc SB O₂ #/MMBtu
101.980 99.007
175.085 169.982 0.264
183.072 177.735 0.384
404.566 393.300

AIR TEMPERATURES (deg F):

Air Preheat Inlet 133.800

Preheat Outlet 403.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 620.500

FG Preheat Outlet 422.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 16.775
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 335.000Flash Tank 1.695
Flash Tank 103.000
Flash Tank 335.000

Total Steam 18.470

Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 19.491
Coal + N. Gas - MMBtu/hr 19.491

Cooling (Coal + N Gas) - % 8.783

Cooling H₂O Inlet (deg F) 339.000

RESULTS: Steam Gen Eff'cy (%) 81.742

Fuel to Steam Flow Corr. 0.851

Boiler Efficiency (%) 81.061

% SO₂ Reduction 54.809

Intrusion Air (#/hr) 3598.82

REMARKS:

B59

Table B4. Two Buil Ridge Parametric Test Data

[illegible]

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/19/91

TEST: 553-TBR1

Date 05/30/90

PURPOSE: IDENTIFY SUCCESSFUL OPERATING CONDITIONS FOR TBR COAL.

COAL: Source: TWO BULL RIDGE
Ultimate Analysis AppliedComposition (%) - Carbon: 43.500 Hydrogen: 3.410 Oxygen: 14.830 Nitrogen: 0.760 Sulfur: 0.360
Moisture: 9.820 Ash: 27.320 T250 (calc. deg F): 2876 HHV (Btu/lb): 7350

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 31

Section: 1 OF 1

Time of Test: 19:57

FLOW RATES:

Coal PC (#/hr)	679.000	LS (#/hr)	48.000	Total Air (#/hr)	10752.521
Carrier Air PC (scfh)	12500.000	LS Split (I/W)	100/0	Stoic Air (#/hr)	9585.494
Combustion Air PC (kpph)	4.020	# Nozzles	_____	Xcas Air SB (#/hr)	1167.027
Mix Bustle Air PC (kpph)	2.370	Carr'r A/LS (scfh)	9540.270	Total Coal (#/hr)	1739.000
Coal MC (#/hr)	1060.000	C.A. Press (psig)	Edc Wz1 Dia	Total Gas (#/hr)	12037.914
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% O ₂ post SB Cbn	2.118
Cbn Air Sec Brnr (kpph)	1.020	Injector (tube):	50.000	Coal Split PC (%)	39.045
		Ca/S Ratio	2.222	Ca Utilization, %	21.667
		SCFH to #/hr	0.076		
STOICHIOMETRIC AIR: (for Coal)	5.512				
STOICH. AIR: (# air/# tot fuel)	5.512				
PHI's: PCC phi	1.329	Clog Calc (Btu/sec)	352.800	Clog Meas (Btu/sec)	528.847
PC phi	1.962	Total flow assumed equal over all 8 circuits:		Flow #/sec	28.800
MC phi	0.939	FLUX (Btu/ft ² -sec):			
Overall phi at Sec. Brnr	1.046	#1 AI	0.871	#2 AI	1.295
		#5 SRS	2.062	#6 SRS	1.744
				#3 BAF	2.566
				#4 SRS	3.595
				#7 PC ET	2.561
				#9 TAP	0.000

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	8.800			
CO (ppm)	13.000	19.180	20.121	
NOx (ppm)	131.000	193.279	202.753	0.292
SO ₂ w/LS (ppm)	163.000	240.492	252.280	0.507
SOx w/o LS (ppm), calc	321.817	464.918	486.580	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 146.000

Preheat Outlet 284.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 426.000

FG Preheat Outlet 289.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH):	Boiler	6.935
Press. (psig):	Boiler	103.000
Temps. (deg F):	Boiler	336.000

Flash Tank	1.885	Total Steam	6.920
Flash Tank	103.000		
Flash Tank	336.000	Feed H ₂ O (deg F)	212.000

COMBUSTOR LOADS:	Coal - MMBtu/hr	12.796	Cooling (Coal + N Gas) - %	14.879	Cooling H ₂ O Inlet (deg F)	340.000
	Coal + N. Gas - MMBtu/hr	12.796				

RESULTS:	Steam Gen Eff'cy (%)	83.767	Fuel to Steam Flow Corr.	1.210		
	Boiler Efficiency (%)	82.669	% SO ₂ Reduction	48.152	Intrusion Air (#/hr)	8167.05

REMARKS:

HEALY TESTS

TEST SUMMARY

8 Pgs: 2

Revision: 0

Date: 6/19/91

TEST: 554-TBR2

Date 05/31/91

PURPOSE: IDENTIFY SUCCESSFUL OPERATING CONDITIONS FOR TBR COAL.

COAL: Source: TWO BULL RIDGE
Ultimate Analysis AppliedComposition (%) - Carbon: 43.500 Hydrogen: 3.410 Oxygen: 14.830 Nitrogen: 0.760 Sulfur: 0.360
Moisture: 9.820 Ash: 27.320 T250 (calc. deg F): 2876 HHV (Btu/lb): 7358

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 97

Section: 1 OF 1

Time of Test: 9:54

FLOW RATES:

Coal PC (#/hr) 1060.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 4.790
Mix Bustle Air PC (kpph) 6.230
Coal MC (#/hr) 1058.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 2.030LS (#/hr) _____
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 0.000
C.A. Press (psig) Edc Nz1 Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio N/A
SCFH to #/hr 0.076Total Air (#/hr) 15663.644
Stoi Air (#/hr) 14981.813
Xcss Air SB (#/hr) 681.831
Total Coal (#/hr) 2718.000
Total Gas (#/hr) 17639.886
% O₂ post SB Cmbn 0.844
Coal Split PC (%) 38.999
Ca Utilization, % _____STOICHIOMETRIC AIR: (for Coal) 5.512
STOICH. AIR: (# air/# tot fuel) 5.512
PHI's: PCC phi 0.983
PC phi 2.050
MC phi 0.910
Overall phi at Sec. Brnr 1.046Cling Calc (Btu/sec) 270.000 Cling Meas (Btu/sec) 394.181 Flow #/sec 28.000
Total flow assumed equal over all 8 circuits:
FLUX (Btu/ft²-sec):
01 AI 0.581 02 AI 1.060 03 BAF 1.633 04 SRS 2.615
05 SRS 1.586 06 SRS 1.289 07 PC ET 2.241 08 TAP 0.000

EMISSIONS:

At stack As meas.
O₂ (%) 6.530
CO (ppm) 89.000
NOx (ppm) 140.000
SO₂ w/LS (ppm) 232.000
SOx w/o LS (ppm), calc 378.489At 3% O₂ At Calc SB O₂ #/MMBtu
110.712 123.970
174.153 195.010 0.264
288.597 323.159 0.689
445.737 519.014

AIR TEMPERATURES (deg F):

Air Preheat Inlet 137.000

Preheat Outlet 351.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 570.000

FG Preheat Outlet 370.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 14.485
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 337.000Flash Tank 1.405 Total Steam 15.890
Flash Tank 103.000
Flash Tank 337.000 Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 19.999
Coal + N. Gas - MMBtu/hr 19.999Cooling (Coal + N Gas) - % 7.996 Cooling H₂O Inlet (deg F) 340.000

RESULTS: Steam Gen Eff'cy (%) 82.901

Fuel to Steam Flow Corr. 1.033

Boiler Efficiency (%) 82.950

% SO₂ Reduction 37.736

Intrusion Air (#/hr) 6548.98

REMARKS:

NEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/18/81

TEST: 555-TBR3

Date 06/03/81

PURPOSE: IDENTIFY SUCCESSFUL OPERATING CONDITIONS FOR TBR COAL.

COAL: Source: TWO BULL RIDGE
Ultimate Analysis AppliedComposition (%) - Carbon: 43.500 Hydrogen: 3.410 Oxygen: 14.830 Nitrogen: 0.760 Sulfur: 0.360
Moisture: 9.820 Ash: 27.320 T250 (calc. deg F): 2876 HHV (Btu/lb): 7358

LIMESTONE: CANTWELL

% CaCO₃: 90.400NATURAL GAS: Btu/lb _____
Hydrogen (8 H₂/8 NG): _____

Stoich air (8 air/8 NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 70

Section: 1 OF 1

Time of Test: 18:22

FLOW RATES:

Coal PC (8/hr) 1600.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.000
Mix Bustle Air PC (kpph) 5.550
Coal MC (8/hr) 1855.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 3.150LS (8/hr) 553.000
LS Split (I/N) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc H₂l Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 12.887
SCFH to 8/hr 0.076Total Air (8/hr) 18042.521
Stoi Air (8/hr) 19044.210
Xcss Air SB (8/hr) -1001.690
Total Coal (8/hr) 3455.000
Total Gas (8/hr) 20801.182
% O₂ post SB Cmbn -1.052
Coal Split PC (%) 46.310
Ca Utilization, % 1.448

STOICHIOMETRIC AIR: (for Coal) 5.512

STOICH. AIR: (8 air/8 tot fuel) 5.512

PHI's: PCC phi 0.789

PC phi 1.418

MC phi 0.744

Overall phi at Sec. Brnr 0.909

Cling Calc (Btu/sec) 302.400 Cling Meas (Btu/sec) 434.861 Flow 8/sec 28.800
Total flow assumed equal over all 8 circuits:FLUX (Btu/ft²-sec):81 AI 1.816 82 AI 0.824 83 BAF 1.167 84 SRS 1.798
85 SRS 1.744 86 SRS 1.586 87 PC ET 3.201 88 TAP 1.362

EMISSIONS:

At stack As meas.
O₂ (%) 5.880
CO (ppm) 26.000
NOx (ppm) 174.000
SO₂ w/LS (ppm) 312.000
SOx w/o LS (ppm), calc 390.569At 3% O₂ At Calc SB O₂ 8/MMBtu
30.952 37.920
207.143 253.772 0.318
371.429 455.839 0.785
481.832 558.456

AIR TEMPERATURES (deg F):

Air Preheat Inlet 136.800

Preheat Outlet 356.800

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 648.800

FG Preheat Outlet 393.800

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.320
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 338.000Flash Tank 1.550 Total Steam 16.870
Flash Tank 103.000
Flash Tank 338.000 Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 25.422
Coal + N. Gas - MMBtu/hr 25.422Cooling (Coal + N Gas) - % 6.158 Cooling H₂O Inlet (deg F) 341.000

RESULTS: Steam Gen Eff'cy (%) 80.686

Fuel to Steam Flow Corr. 1.207

Boiler Efficiency (%) 82.227

% SO₂ Reduction 18.664

Intrusion Air (8/hr) 9032.44

REMARKS:

NEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/19/91

TEST: 556-TBR4

Date 06/04/91

PURPOSE: IDENTIFY SUCCESSFUL OPERATING CONDITIONS FOR TBR COAL.

COAL: Source: TWO BULL RIDGE
Ultimate Analysis AppliedComposition (%) - Carbon: 43.500 Hydrogen: 3.410 Oxygen: 14.830 Nitrogen: 0.760 Sulfur: 0.360
Moisture: 9.820 Ash: 27.320 T250 (calc. deg F): 2876 HHV (Btu/lb): 7358

LIMESTONE: CANTWELL

% CaCO₃: 90.400NATURAL GAS: Btu/lb _____
Hydrogen (# H₂/# NG): _____

Stoich air (# air/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 60

Section: 1 OF 1

Time of Test: 17:51

FLOW RATES:

Coal PC (#/hr)	1480.000	LS (#/hr)	_____	Total Air (#/hr)	22798.644
Carrier Air PC (scfh)	12500.000	LS Split (I/N)	100/0	Stoi Air (#/hr)	17385.077
Combustion Air PC (kpph)	6.385	# Nozzles	_____	Xcess Air SB (#/hr)	5413.567
Mix Bustle Air PC (kpph)	9.470	Carr'r A/LS (scfh)	0.000	Total Coal (#/hr)	3154.000
Coal MC (#/hr)	1674.000	C.A. Press (psig)	Edc Rzl Dia	Total Gas (#/hr)	25090.971
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% O ₂ post SB Cmbn	4.713
Cmbn Air Sec Brnr (kpph)	4.330	Injector (tube):	50.000	Coal Split PC (%)	46.925
		Ca/S Ratio	N/A	Ca Utilization, %	_____
		SCFH to #/hr	0.076		
STOICHIOMETRIC AIR: (for Coal)	5.512	Clog Calc (Btu/sec)	288.000	Clog Meas (Btu/sec)	462.917
STOICH. AIR: (# air/# tot fuel)	5.512	Total flow assumed equal over all 8 circuits:		Flow #/sec	28.800
PHI's: PCC phi	0.900	FLUX (Btu/ft ² -sec):			
PC phi	2.061	81 AI	1.916	82 AI	1.060
MC phi	1.062	85 SRS	2.370	86 SRS	2.062
Overall phi at Sec. Brnr	1.311			87 PC ET	2.134
				88 SRS	1.634
				89 TAP	0.908

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	5.888			
CO (ppm)	68.500	81.591	73.826	
NO _x (ppm)	202.000	240.603	217.707	0.361
SO ₂ w/LS (ppm)	278.000	331.128	299.616	0.692
SO _x w/o LS (ppm), calc	394.326	465.737	423.399	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 124.000

Preheat Outlet 342.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 662.000

FG Preheat Outlet 374.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH):	Boiler	17.450
Press. (psig):	Boiler	103.000
Temp. (deg F):	Boiler	338.000

Flash Tank	1.650
Flash Tank	103.000
Flash Tank	338.000

Total Steam 19.100

Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 23.207
Coal + N. Gas - MMBtu/hr 23.207

Cooling (Coal + N Gas) - % 7.181

Cooling H₂O Inlet (deg F) 342.000

RESULTS: Steam Gen Eff'cy (%) 83.115

Fuel to Steam Flow Corr. 0.999

Boiler Efficiency (%) 83.170

% SO₂ Reduction 29.236

Intrusion Air (#/hr) 1847.80

REMARKS:

NEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/19/91

TEST: 557-TBR5

Date 06/04/91

PURPOSE: IDENTIFY SUCCESSFUL OPERATING CONDITIONS FOR TBR COAL.

COAL: Source: TWO BULL RIDGE

Ultimate Analysis Applied

Composition (%) - Carbon: 43.500 Hydrogen: 3.410 Oxygen: 14.830 Nitrogen: 0.760 Sulfur: 0.360
 Moisture: 9.820 Ash: 27.320 T250 (calc. deg F): 2876 HHV (Btu/lb): 7358

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____
 Hydrogen (# H₂/# NG): _____

Stoich air (# air/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 31

Section: 1 OF 1

Time of Test: 21:18

FLOW RATES:

Coal PC (#/hr) 1474.000
 Carrier Air PC (scfh) 12500.000
 Combustion Air PC (kpph) 6.160
 Mix Bustle Air PC (kpph) 9.800
 Coal MC (#/hr) 1666.000
 Carrier Air MC (scfh) 21710.000
 Comb Air Sec Brnr (kpph) 6.450

LS (#/hr) _____
 LS Split (I/M) 100/0
 # Nozzles _____
 Carr'r A/LS (scfh) 0.000
 C.A. Press (psig) Edc H₂l Dia 0.375
 Nozzles (throat): _____
 Injector (tube): 50.000
 Ca/S Ratio N/A
 SCFH to #/hr 0.076

Total Air (#/hr) 24823.644
 Stoic Air (#/hr) 17307.908
 Xcess Air SB (#/hr) 7515.736
 Total Coal (#/hr) 3140.000
 Total Gas (#/hr) 27105.796
 % O₂ post SB Comb 6.057
 Coal Split PC (%) 46.943
 Ca Utilization, % _____

STOICHIOMETRIC AIR: (for Coal) 5.512

STOICH. AIR: (# air/# tot fuel) 5.512

PHI's: PCC phi 0.876
 PC phi 2.057
 MC phi 1.062
 Overall phi at Sec. Brnr 1.434

Cling Calc (Btu/sec) 248.400 Cling Meas (Btu/sec) 3012.958 Flow #/sec 28.800
 Total flow assumed equal over all 8 circuits:
 FLUX (Btu/ft²-sec):
 #1 AI 0.871 #2 AI 0.706 #3 BAF 1.167 #4 SRS 2.288
 #5 SRS 1.269 #6 SRS 1.269 #7 PC ET 2.134 #8 TAP 0.808

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	5.970			
CO (ppm)	130.000	155.689	129.250	
NO _x (ppm)	202.000	241.916	280.835	0.361
SO ₂ w/LS (ppm)	289.000	346.108	287.333	0.720
SO _x w/o LS (ppm), calc	392.330	465.737	390.188	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 109.500

Preheat Outlet 375.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 718.090

FG Preheat Outlet 394.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 19.725
 Press. (psig): Boiler 103.000
 Temps. (deg F): Boiler 336.000

Flash Tank 1.365 Total Steam 21.090
 Flash Tank 103.000
 Flash Tank 336.000 Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 23.104
 Coal + N. Gas - MMBtu/hr 23.104

Cooling (Coal + N Gas) - % 5.967 Cooling H₂O Inlet (deg F) 340.000

RESULTS: Steam Gen Eff'cy (%) 82.446

Fuel to Steam Flow Corr. 0.893

Boiler Efficiency (%) 82.669

% SO₂ Reduction 26.360

Intrusion Air (#/hr) -148.06

REMARKS:

NEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/19/91

TEST: 558-TBR6

Date 06/05/91

PURPOSE: IDENTIFY SUCCESSFUL OPERATING CONDITIONS FOR TBR COAL.

COAL: Source: TWO BULL RIDGE

Ultimate Analysis Applied

Composition (%) - Carbon: 43.500 Hydrogen: 3.410 Oxygen: 14.830 Nitrogen: 0.760 Sulfur: 0.360
 Moisture: 9.820 Ash: 27.320 T250 (calc. deg F): 2876 HHV (Btu/lb): 7358

LIKESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTION FIRING CONFIGURATION:

Duration (mins): 15

Section: 1 OF 1

Time of Test: 11:20

FLOW RATES:

Coal PC (#/hr) 1523.000
 Carrier Air PC (scfh) 12500.000
 Combustion Air PC (kpph) 6.205
 Mix Bustle Air PC (kpph) 9.840
 Coal NC (#/hr) 1720.000
 Carrier Air NC (scfh) 21710.000
 Comb Air Sec Brnr (kpph) 4.930

LS (#/hr) _____
 LS Flow (I/H) 100/0
 # Nozzles _____
 Carr'r A/LS (scfh) 0.000
 C.A. Press (psig) Edc H21 Dia 0.375
 Nozzles (throat): _____
 Injector (tube): 50.000
 Ca/S Ratio N/A
 SCFH to #/hr 0.076

Total Air (#/hr) 23588.644
 Sto! Air (#/hr) 17875.651
 Xcas Air SB (#/hr) 5712.993
 Total Coal (#/hr) 3243.000
 Total Gas (#/hr) 25945.656
 % O₂ post SB Comb 4.810
 Coal Split PC (%) 46.963
 Ca Utilization, % _____

STOICHIOMETRIC AIR: (for Coal) 5.512

STOICH. AIR: (# air/# tot fuel) 5.512

PHI's: PCC phi 0.863

PC phi 2.025

NC phi 1.044

Overall phi at Sec. Brnr 1.320

Cling Calc (Btu/sec) 219.800 Cling Meas (Btu/sec) 317.028 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

01 AI 0.726 02 AI 1.060 03 BAF 0.933 04 SRS 1.634
 05 SRS 1.110 06 SRS 1.269 07 PC ET 1.707 08 TAP 0.908

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	5.500			
CO (ppm)	119.000	138.194	124.299	
NO _x (ppm)	295.000	342.581	308.138	0.514
SO ₂ w/LS (ppm)	208.000	241.548	217.262	0.504
SO _x w/o LS (ppm), calc	483.046	465.737	421.006	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 114.000

Preheat Outlet 340.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 719.000

FG Preheat Outlet 364.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 17.400

Flash Tank 1.130

Total Steam 18.530

Press. (psig): Boiler 103.000

Flash Tank 103.000

Temps. (deg F): Boiler 339.000

Flash Tank 339.000

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 23.862

Cooling (Coal + N Gas) - % 4.783

Cooling H₂O Inlet (deg F) 340.000

Coal + N. Gas - MMBtu/hr 23.862

RESULTS: Steam Gen Eff'cy (%) 83.614

Fuel to Steam Flow Corr. 1.666

Boiler Efficiency (%) 84.130

% SO₂ Reduction 48.395

Intrusion Air (#/hr) 1095.70

REMARKS:

NEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/19/91

TEST: 559-TBR7

Date 06/05/91

PURPOSE: IDENTIFY SUCCESSFUL OPERATING CONDITIONS FOR TBR COAL.

COAL: Source: TWO BULL RIDGE
Ultimate Analysis AppliedComposition (%) - Carbon: 43.500 Hydrogen: 3.410 Oxygen: 14.830 Nitrogen: 0.760 Sulfur: 0.360
Moisture: 9.820 Ash: 27.320 T250 (calc. deg F): 2876 HHV (Btu/lb): 7358

LIMESTONE: CANTWELL

% CaCO₃: 90.400NATURAL GAS: Btu/lb _____
Hydrogen (# H₂/# NG): _____

Stoich air (# air/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 55

Section: 1 OF 1

Time of Test: 14:45

FLOW RATES:

Coal PC (#/hr) 1489.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.220
Mix Bustle Air PC (kpph) 9.910
Coal MC (#/hr) 1683.000
Carrier Air MC (scfh) 21710.000
Cabin Air Sec Brar (kpph) 5.780LS (#/hr) _____
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 0.000
C.A. Press (psig) Edc H2l Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio N/A
SCFH to #/hr 0.076Total Air (#/hr) 24523.644
Stoi Air (#/hr) 17484.294
Xcss Air SB (#/hr) 7259.350
Total Coal (#/hr) 3172.000
Total Gas (#/hr) 26829.054
% O₂ post SB Comb 5.731
Coal Split PC (%) 46.942
Ca Utilization, % _____

STOICHIOMETRIC AIR: (for Coal) 5.512

STOICH. AIR: (# air/# tot fuel) 5.512

PHI's: PCC phi 0.874

PC phi 2.082

MC phi 1.872

Overall phi at Sec. Brar 1.403

Cling Calc (Btu/sec) 227.600 Cling Meas (Btu/sec) 370.333 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):01 AI 0.43E 02 AI 1.060 03 BAF 1.167 04 SRS 2.615
05 SRS 1.427 06 SRS 0.952 07 PC ET 1.921 08 TAP 0.000

EMISSIONS:

At stack As meas.
O₂ (%) 6.000
CO (ppm) 105.000
NOx (ppm) 187.000
SO₂ w/LS (ppm) 318.000
SOx w/o LS (ppm), calc 391.588At 3% O₂ At Calc SB 12 #/MMBtu
126.000 106.881
224.400 190.350 0.336
381.600 323.696 0.795
445.737 398.230

AIR TEMPERATURES (deg F):

Air Preheat Inlet 120.000

Preheat Outlet 382.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 735.000

FG Preheat Outlet 407.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 18.300
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 338.000Flash Tank 1.320
Flash Tank 103.000
Flash Tank 338.000

Total Steam 19.620

Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 23.340
Coal + N. Gas - MMBtu/hr 23.340

Cooling (Coal + N Gas) - %

5.712

Cooling H₂O Inlet (deg F) 341.000

RESULTS: Steam Gen Eff'cy (%) 82.021

Fuel to Steam Flow Corr.

0.965

Boiler Efficiency (%) 82.259

% SO₂ Reduction 18.716

Intrusion Air (#/hr) 454.50

REMARKS:

NEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/19/91

TEST: 560-TBR8

Date 06/05/91

PURPOSE: IDENTIFY SUCCESSFUL OPERATING CONDITIONS FOR TBR COAL.

COAL: Source: TWO BULL RIDGE

Ultimate Analysis Applied

Composition (%) - Carbon: 43.500 Hydrogen: 3.410 Oxygen: 14.830 Nitrogen: 0.760 Sulfur: 0.360

Moisture: 9.820 Ash: 27.320 T250 (calc. deg F): 2876 HHV (Btu/lb): 7358

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 66

Section: 1 OF 1

Time of Test: 18:15

FLOW RATES:

Coal PC (#/hr) 1482.000

Carrier Air PC (scfh) 12500.000

Combustion Air PC (kpph) 6.400

Mix Bustle Air PC (kpph) 9.660

Coal MC (#/hr) 1675.000

Carrier Air MC (scfh) 21710.000

Cabin Air Sec Brnr (kpph) 6.030

LS (#/hr)

LS Split (I/M) 100/0

Nozzles

Carr'r A/LS (scfh) 0.000

C.A. Press (psig) Edc H₂ Dia 0.375

Nozzles (throat):

Injector (tube): 50.000

Ca/S Ratio N/A

SCFH to #/hr 0.076

Total Air (#/hr) 24793.644

Stoi Air (#/hr) 17401.613

Xcess Air SB (#/hr) 7392.031

Total Coal (#/hr) 3157.000

Total Gas (#/hr) 27088.152

% O₂ post SB Cabin 5.961

Coal Split PC (%) 46.943

Ca Utilization, %

STOICHIOMETRIC AIR: (for Coal) 5.512

STOICH. AIR: (# air/# tot fuel) 5.512

PHI's: PCC phi 0.911

PC phi 2.094

MC phi 1.078

Overall phi at Sec. Brnr 1.425

Cing Calc (Btu/sec) 255.890 Cing Meas (Btu/sec) 339.472 Flow #/sec 28.200

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

01 AI 0.581 02 AI 1.060 03 BAF 1.033 04 SRS 2.015

05 SRS 1.506 06 SRS 1.110 07 PC ET 2.027 09 TAP -0.454

EMISSIONS:

At stack As meas.

O₂ (%) 5.790

CO (ppm) 198.000

NOx (ppm) 178.000

SO₂ w/LS (ppm) 294.000

SOx w/o LS (ppm), calc 396.779

At 3% O₂

234.320

210.651

347.929

465.737

At Calc SB O₂

195.775

176.000

200.697

302.556

#/MMBtu

0.315

0.724

AIR TEMPERATURES (deg F):

Air Preheat Inlet 118.000

Preheat Outlet 393.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 696.000

FG Preheat Outlet 412.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 18.350

Press. (psig): Boiler 103.000

Temps. (deg F): Boiler 337.000

Flash Tank 1.210

Flash Tank 103.000

Flash Tank 337.000

Total Steam 19.560

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 23.229

Coal + N. Gas - MMBtu/hr 23.229

Cooling (Coal + N Gas) - % 5.261

Cooling H₂O Inlet (deg F) 339.000

RESULTS: Steam Gen Eff'cy (%) 81.985

Fuel to Steam Flow Corr. 0.983

Boiler Efficiency (%) 82.307

% SO₂ Reduction 25.948

Intrusion Air (#/hr) -288.36

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/19/91

TEST: 561-TBR9

Date 06/06/91

PURPOSE: IDENTIFY SUCCESSFUL OPERATING CONDITIONS FOR TBR COAL.

COAL: Source: TWO BULL RIDGE

Ultimate Analysis Applied

Composition (%) - Carbon: 43.500 Hydrogen: 3.410 Oxygen: 14.830 Nitrogen: 0.760 Sulfur: 0.360
 Moisture: 9.820 Ash: 27.320 T250 (calc. deg F): 2876 HHV (Btu/lb): 7358

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 32

Section: 1 OF 1

Time of Test: 14:15

FLOW RATES:

Coal PC (#/hr) 1504.000
 Carrier Air PC (scfh) 12500.000
 Combustion Air PC (kpph) 6.520
 Mix Bustle Air PC (kpph) 9.705
 Coal MC (#/hr) 1700.000
 Carrier Air MC (scfh) 21710.000
 Cmbn Air Sec Brnr (kpph) 3.530

LS (#/hr) _____
 LS Split (I/W) 100/0
 # Nozzles _____
 Carr'r A/LS (scfh) 0.000
 C.A. Press (psig) Edc Nzl Dia 0.375
 Nozzles (throat): _____
 Injector (tube): 50.000
 Ca/S Ratio N/A
 SCFH to #/hr 0.076

Total Air (#/hr) 22368.644
 Stoic Air (#/hr) 17660.680
 Xcas Air SB (#/hr) 4707.824
 Total Coal (#/hr) 3204.000
 Total Gas (#/hr) 24697.311
 % O₂ post SB Cmbn 4.164
 Coal Split PC (%) 46.941
 Ca Utilization, % _____

STOICHIOMETRIC AIR: (for Coal) 5.512
 STOICH. AIR: (# air/# tot fuel) 5.512
 PHI's: PCC phi 0.902
 PC phi 2.072
 MC phi 1.067
 Overall phi at Sec. Brnr 1.267

Cing Calc (Btu/sec) 252.000 Cing Meas (Btu/sec) 451.694 Flow #/sec 28.800
 Total flow assumed equal over all 8 circuits:
 FLUX (Btu/ft²-sec):
 01 AI 0.435 02 AI 0.824 03 BAF 1.167 04 SRS 2.288
 05 SRS 2.537 06 SRS 1.903 07 PC ET 1.174 09 TAP 0.908

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	5.700			
CO (ppm)	292.000	343.529	321.315	
NOx (ppm)	215.000	252.941	236.584	0.380
SO ₂ w/LS (ppm)	266.000	312.941	292.704	0.655
SOx w/o LS (ppm), calc	399.003	465.737	436.967	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 130.000

Preheat Outlet 249.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 499.000

FG Preheat Outlet 270.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.150
 Press. (psig): Boiler 103.000
 Temps. (deg F): Boiler 337.000

Flash Tank 1.610 Total Steam 16.760
 Flash Tank 103.000
 Flash Tank 337.000 Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 23.575 Cooling (Coal + N Gas) - % 6.898 Cooling H₂O Inlet (deg F) 343.000
 Coal + N. Gas - MMBtu/hr 23.575

RESULTS: Steam Gen Eff'cy (%) 86.423

Fuel to Steam Flow Corr. 1.206

Boiler Efficiency (%) 86.836

% SO₂ Reduction 33.015

Intrusion Air (#/hr) 2349.83

REMARKS:

NEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/19/91

TEST: 562-TBR10

Date 06/06/91

PURPOSE: IDENTIFY SUCCESSFUL OPERATING CONDITIONS FOR TBR COAL.

COAL: Source: TWO BULL RIDGE
Ultimate Analysis AppliedComposition (%) - Carbon: 43.500 Hydrogen: 3.410 Oxygen: 14.830 Nitrogen: 0.760 Sulfur: 0.360
Moisture: 9.820 Ash: 27.320 T250 (calc. deg F): 2876 HHV (Btu/lb): 7358

LIMESTONE: CANTWELL

% CaCO₃: 90.400NATURAL GAS: Btu/lb _____
Hydrogen (# H₂/# NG): _____

Stoich air (# air/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 59

Section: 1 OF 1

Time of Test: 16:47

FLOW RATES:

Coal PC (#/hr) 1192.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 5.870
Mix Dustle Air PC (kpph) 5.910
Coal NC (#/hr) 1347.000
Carrier Air NC (scfh) 21710.000
Cabin Air Sec Brnr (kpph) 2.700LS (#/hr) _____
LS Split (I/N) 100/0
Nozzles _____
Carr'r A/LS (scfh) 0.000
C.A. Press (psig) Edc H₂l Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio N/A
SCFH to #/hr 0.076Total Air (#/hr) 17183.644
Stoi Air (#/hr) 13995.152
Xcas Air SB (#/hr) 3188.492
Total Coal (#/hr) 2539.000
Total Gas (#/hr) 19028.989
% O₂ post SB Cabin 3.660
Coal Split PC (%) 46.948
Ca Utilization, % _____STOICHIOMETRIC AIR: (for Coal) 5.512
STOICH. AIR: (# air/# tot fuel) 5.512
PHI's: PCC phi 1.039
PC phi 1.038
NC phi 1.028
Overall phi at Sec. Brnr 1.228Cling Calc (Btu/sec) 288.800 Cling Meas (Btu/sec) 342.278 Flow #/sec 20.800
Total flow assumed equal over all 8 circuits:
FLUX (Btu/ft²-sec):
01 AI 0.581 02 AI 0.824 03 BAF 0.700 04 SRS 1.634
05 SRS 1.596 06 SRS 1.596 07 PC ET 1.174 08 TAP 1.362

EMISSIONS:

At stack As meas.
O₂ (%) 5.960
CO (ppm) 169.000
NOx (ppm) 197.000
SO₂ w/LS (ppm) 305.000
SOx w/o LS (ppm), calc 392.577At 3% O₂ At Calc SB O₂ #/MMBtu
282.261 194.843
235.771 227.125 0.355
305.827 351.640 0.765
465.736 449.421

AIR TEMPERATURES (deg F):

Air Preheat Inlet 132.000

Preheat Outlet 339.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 572.000

FG Preheat Outlet 356.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 13.910
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 338.000Flash Tank 1.220 Total Steam 15.130
Flash Tank 103.000
Flash Tank 338.000 Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 18.682
Coal + N. Gas - MMBtu/hr 18.682Cooling (Coal + N Gas) - % 6.596 Cooling H₂O Inlet (deg F) 341.000

RESULTS: Steam Gen Eff'cy (%) 83.642

Fuel to Steam Flow Corr. 1.022

Boiler Efficiency (%) 83.852

% SO₂ Reduction 21.757

Intrusion Air (#/hr) 2755.28

REMARKS:

HEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0
Date: 6/19/91TEST: 563-TBR11 Date 06/07/91
PURPOSE: IDENTIFY SUCCESSFUL OPERATING CONDITIONS FOR TBR COAL.COAL: Source: TWO BULL RIDGE
Ultimate Analysis AppliedComposition (%) - Carbon: 43.500 Hydrogen: 3.410 Oxygen: 14.830 Nitrogen: 0.760 Sulfur: 0.360
Moisture: 9.820 Ash: 27.320 T250 (calc. deg F): 2876 HHV (Btu/lb): 7358

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 94

Section: 1 OF 1

Time of Test: 9:22

FLOW RATES:

Coal PC (#/hr) 1135.000
Carrier Air PC (scfh) 12500.000
Combustion Air PC (kpph) 6.120
Mix Bustle Air PC (kpph) 5.980
Coal MC (#/hr) 1282.000
Carrier Air MC (scfh) 21710.000
Cmbn Air Sec Brnr (kpph) 4.340LS (#/hr) 82.000
LS Split (I/W) 100/0
Nozzles _____
Carr'r A/LS (scfh) 9540.270
C.A. Press (psig) Edc Wzl Dia 0.375
Nozzles (throat): _____
Injector (tube): 50.000
Ca/S Ratio 2.732
SCFH to #/hr 0.076Total Air (#/hr) 19782.521
Stoi Air (#/hr) 13322.679
Xcss Air SB (#/hr) 6459.841
Total Coal (#/hr) 2417.000
Total Gas (#/hr) 21575.906
% O₂ post SB Cmbn 6.540
Coal Split PC (%) 46.959
Ca Utilization, % 11.829STOICHIOMETRIC AIR: (for Coal) 5.512
STOICH. AIR: (# air/# tot fuel) 5.512
PHI's: PCC phi 1.131
PC phi 2.087
MC phi 1.104
Overall phi at Sec. Brnr 1.430Cling Calc (Btu/sec) 172.800 Cling Meas (Btu/sec) 308.611 Flow #/sec 28.800
Total flow assumed equal over all 8 circuits:
FLUX (Btu/ft²-sec):
01 AI 0.581 02 AI 0.824 03 BAF 0.700 04 SRS 1.307
05 SRS 0.952 06 SRS 1.110 07 PC ET 1.067 08 TAP 1.362

EMISSIONS:

At stack As meas. At 3% O₂ At Calc SB O₂ #/MMBtu
O₂ (%) 6.110
CO (ppm) 154.000 186.165 149.552
NOx (ppm) 191.000 239.893 185.484 0.345
SO₂ w/LS (ppm) 263.000 317.931 255.404 0.662
SOx w/o LS (ppm), calc 388.030 464.731 377.323

AIR TEMPERATURES (deg F):

Air Preheat Inlet 126.000 Preheat Outlet 337.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 589.800 FG Preheat Outlet 350.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 15.030
Press. (psig): Boiler 103.000
Temps. (deg F): Boiler 338.000Flash Tank 1.100
Flash Tank 103.000
Flash Tank 338.000Total Steam 16.130
Feed H₂O (deg F) 212.000COMBUSTOR LOADS: Coal - MMBtu/hr 17.784
Coal + N. Gas - MMBtu/hr 17.784

Cooling (Coal + N Gas) - % 6.247

Cooling H₂O Inlet (deg F) 342.000

RESULTS: Steam Gen Eff'cy (%) 83.372 Fuel to Steam Flow Corr. 0.909

Boiler Efficiency (%) 83.946 % SO₂ Reduction 32.312 Intrusion Air (#/hr) -589.71

REMARKS: Limestone added with coal as fluxing agent

NEALY TESTS

TEST SUMMARY

Pgs: 2

Revision: 0

Date: 6/19/91

TEST: 564-TBR12

Date 06/07/91

PURPOSE: IDENTIFY SUCCESSFUL OPERATING CONDITIONS FOR TBR COAL.

COAL: Source: TWO BULL RIDGE
Ultimate Analysis AppliedComposition (%) - Carbon: 43.500 Hydrogen: 3.410 Oxygen: 14.830 Nitrogen: 0.760 Sulfur: 0.360
Moisture: 8.820 Ash: 27.320 T250 (calc. deg F): 2876 HHV (Btu/lb): 7358

LIMESTONE: CANTWELL

% CaCO₃: 90.400

NATURAL GAS: Btu/lb _____

Stoich air (# air/# NG): _____

Hydrogen (# H₂/# NG): _____

TEST PARAMETERS - COMBUSTOR FIRING CONFIGURATION:

Duration (mins): 61

Section: 1 OF 1

Time of Test: 13:28

FLOW RATES:

Coal PC (#/hr)	1134.000	LS (#/hr)	166.000	Total Air (#/hr)	18764.521	
Carrier Air PC (scfh)	12500.000	LS Split (I/M)	100/0	Stoi Air (#/hr)	13311.655	
Combustion Air PC (kpph)	5.945	# Nozzles	_____	Xcess Air SB (#/hr)	5452.866	
Mix Bustle Air PC (kpph)	6.012	Carr'r A/LS (scfh)	9540.270	Total Coal (#/hr)	2415.000	
Coal MC (#/hr)	1281.000	C.A. Press (psig)	Edc Nzl Dia	0.375	Total Gas (#/hr)	20594.058
Carrier Air MC (scfh)	21710.000	Nozzles (throat):	_____	% O ₂ post SB Comb	5.784	
Comb Air Sec Brnr (kpph)	3.465	Injector (tube):	50.000	Coal Split PC (%)	46.957	
		Ca/S Ratio	5.534	Ca Utilization, %	5.549	
		SCFH to #/hr	0.076			

STOICHIOMETRIC AIR: (for Coal) 5.512

STOICH. AIR: (# air/# tot fuel) 5.512

PHI's: PCC phi 1.104

PC phi 2.066

MC phi 1.095

Overall phi at Sec. Brnr 1.355

Cling Calc (Btu/sec) 147.600 Cling Mass (Btu/sec) 230.056 Flow #/sec 28.800

Total flow assumed equal over all 8 circuits:

FLUX (Btu/ft²-sec):

01 AI	0.290	02 AI	0.824	03 BAF	0.933	04 SRS	1.307
05 SRS	0.793	06 SRS	0.634	07 PC ET	1.067	08 TAP	0.454

EMISSIONS:

At stack	As meas.	At 3% O ₂	At Calc SB O ₂	#/MMBtu
O ₂ (%)	6.600			
CO (ppm)	24.000	30.000	25.360	
NO _x (ppm)	181.000	226.250	191.260	0.340
SO ₂ w/LS (ppm)	259.000	323.756	273.681	0.677
SO _x w/o LS (ppm), calc	375.115	463.784	384.986	

AIR TEMPERATURES (deg F):

Air Preheat Inlet 124.000

Preheat Outlet 357.000

Ambient 77.000

FLUE GAS TEMPERATURES (deg F):

FG Air Preheat Inlet 593.000

FG Preheat Outlet 372.000

NATURAL GAS INPUTS:

N. Gas MMBtu/hr _____ % of Total Load: N/A

STEAMS (KPPH): Boiler 13.680

Flash Tank 0.820

Total Steam 14.500

Press. (psig): Boiler 103.000

Flash Tank 103.000

Temps. (deg F): Boiler 336.000

Flash Tank 336.000

Feed H₂O (deg F) 212.000

COMBUSTOR LOADS: Coal - MMBtu/hr 17.770

Cooling (Coal + N Gas) - % 4.661

Cooling H₂O Inlet (deg F) 340.000

Coal + N. Gas - MMBtu/hr 17.770

RESULTS: Steam Gen Eff'cy (%) 82.012

Fuel to Steam Flow Corr. 0.995

Boiler Efficiency (%) 83.008

% SO₂ Reduction 30.711

Intrusion Air (#/hr) 1102.73

REMARKS: Limestone added with coal as fluxing agent

APPENDIX C. LIST OF EQUATIONS

List of Equations:

1. Coal Weight = (coal flowrate)(.75*20+(duration-20))/60
(assumes 75% load for first 20 minutes)

2. Solids Balance

$$= \text{Output/Input} * 100$$

$$\text{Output} = (\text{slag wt}) * (\text{slag ash}/100) * (1 - \text{slag ash SO}_3/100) + \\ (\text{flyash wt}) * (\text{flyash ash}/100) * (1 - \text{flyash ash SO}_3/100)$$

$$\text{Input} = (\text{coal wt}) * (\text{coal ash}/100) * (1 - \text{coal ash SO}_3/100) + \\ (\text{limestone flow}) * \text{duration}/60 * ((\text{CaCO}_3/100) * \text{MW}(\text{CaO})/ \\ \text{MW}(\text{CaCO}_3) + (1 - \text{CaCO}_3/100) * \text{MW}(\text{MgO})/\text{MW}(\text{MgCO}_3))$$

3. Slag Recovery

$$= (\text{slag wt}) * (\text{slag ash}/100) * (1 - \text{slag ash SO}_3/100) / \\ (\text{coal wt}) * (\text{coal ash}/100) * (1 - \text{coal ash SO}_3/100) * 100$$

4. Carbon Conversion

$$= (1 - \text{losses}/\text{input}) * 100$$

$$\text{Losses} = (\text{slag wt}) * (\text{slag carbon}/100) + (\text{flyash wt}) * (\text{flyash carbon}/100)$$

$$\text{Input} = (\text{coal wt}) * (\text{coal carbon}/100)$$

5. Calcium Balance

$$= \text{Output/Input} * 100$$

$$\text{Output} = (\text{slag wt}) * (\text{slag CaO}/100) * \text{MW}(\text{Ca})/\text{MW}(\text{CaO}) + \\ (\text{flyash wt}) * (\text{flyash Ca}/100)$$

$$\text{Input} = (\text{coal wt}) * (\text{coal CaO}/100) * \text{MW}(\text{Ca})/\text{MW}(\text{CaO}) + \\ (\text{limestone flowrate}) * \text{duration}/60 * (\text{CaCO}_3/100) * \text{MW}(\text{Ca})/ \\ \text{MW}(\text{CaCO}_3)$$

6. PCC Phi = (PC coal carrier air + PCCA)/(PC coal * (A/F)_o)
where (A/F)_o is the stoichiometric air to fuel ratio

7. PC Phi = (PC coal carrier air + PCCA + PCMB)/(PC coal * (A/F)_o)

8. $MC \text{ Phi} = (\text{coal carrier airs} + PCCA + PCMB) / (\text{PC \& MC coals} * (A/F)_o)$
9. $SB \text{ Phi} = (\text{coal carrier airs} + PCCA + PCMB + SBCA) / (\text{PC \& MC coals} * (A/F)_o)$
10. $Ca/S = (\text{limestone flow}) * (CaCO_3/100) / MW(CaCO_3) / ((\text{PC \& MC coals}) * (S/100) / MW(S))$
11. Total Air = PC & MC coal carrier air + PCCA + PCMB + SBCA + Limestone carrier air
12. Stoichiometric air = (PC & MC coal) * (A/F)_o
13. Total gas flow = Total air + total ash free coal +
 $(ls \text{ flow}) * (CaCO_3/100) * .44$
 $+ (ls \text{ flow}) * (1 - CaCO_3/100) * .52$
 (out secondary burner)

 Total gas out stack = (stoic. air + total ash free coal +
 $(ls \text{ flow}) * (CaCO_3/100) * .44 +$
 $(ls \text{ flow}) * (1 - CaCO_3/100) * .52$
 $* (.233 / (.233 - \text{stack O}_2/100 * MW(O_2) / MW(\text{gas})))$
 (out stack)
14. Excess air = Total air - stoichiometric air
 (out secondary burner)

 Excess air out stack = (stoic. air + total ash free coal +
 $(ls \text{ flow}) * (CaCO_3/100) * .44 +$
 $(ls \text{ flow}) * (1 - CaCO_3/100) * .52$
 $* (\text{stack O}_2/100 * MW(O_2) / MW(\text{gas}) /$
 $(.233 - \text{stack O}_2/100 * MW(O_2) / MW(\text{gas})))$
 (out stack)
15. Intrusion air = Excess air out stack - Excess air (out secondary burner)
16. $\%SB \text{ O}_2 = (\text{excess air}) * .233 / MW(O_2) / ((\text{total gas}) / MW(\text{gas})) * 100$
17. $SO_2 @ 3\% \text{ O}_2 = SO_2(\text{meas.}) * (21 - 3) / (21 - \text{stack O}_2(\text{meas.}))$
18. $SO_2 @ SB \text{ O}_2 = SO_2(\text{meas.}) * (21 - SB \text{ O}_2) / (21 - \text{stack O}_2(\text{meas.}))$

$$19. \text{SO}_2 \text{ (\#/MMbtu)} = (\text{SO}_2 @ \text{SB O}_2) / 1e6 * \text{MW}(\text{SO}_2) / \text{MW}(\text{gas}) * (\text{total gas}) / \text{load}$$

$$20. \text{NO}_x \text{ (\#/MMbtu)} = (\text{NO}_x @ \text{SB O}_2) / 1e6 * \text{MW}(\text{NO}_2) / \text{MW}(\text{gas}) * (\text{total gas}) / \text{load}$$

$$21. \text{SO}_2 \text{ w/o LS} = (\text{total coal}) * (\%S / 100) / \text{MW}(S) * 1e6 / ((\text{total out stack}) / \text{MW}(\text{gas}))$$

$$22. \text{SO}_2 \text{ capture} = (\text{SO}_2 @ \text{SB(w/o ls)} - \text{SO}_2 @ \text{SB(w/ls)}) / (\text{SO}_2 @ \text{SB(w/o ls)}) * 100$$

$$23. \text{Ca utilization} = \text{SO}_2 \text{ capture} / (\text{Ca/S})$$

$$24. \text{Cooling load} = \text{flash tank steam} / \text{load} / 1e6 * 1010 * 100$$

$$25. \text{Boiler Efficiency} = \frac{A - B - D - E - F - G}{A - B - C} * 100$$

where A - $\text{hhv} * (1 - \text{cooling load} / 100)$ thermal load minus heat to cooling water

B - $\text{ash} / 100 * .75 * .2 * (T_{250} - 77)$ slag heating

C - $\text{limestone} / \text{coal} * .56 * 1385$ limestone calcination

D - $(9H + H_2O) / 100 * (1100 + 0.46 * (\text{flue gas preheat} - 77))$ sensible heat of moisture

E - $.25 * (\text{flue gas preheat} - 77) * ((21 * (A/F) * O_2 / (21 - \text{stack O}_2 / 100)) + 1 + .44 * (\text{limestone} / \text{coal}) - \text{ash} / 100)$ sensible heat of flue gas

F - $\text{ash} / 100 * (1 - .75) * .2 * (\text{flue gas preheat} - 77)$ sensible heat of in flight ash particles

G - $\text{limestone} / \text{coal} * .56 * (1385 + .2 * (\text{flue gas preheat} - 77))$ sensible heat of ls plus calcination

$$26. \text{Fuel to Steam Corr.} =$$

$$\frac{\text{total coal} * (\text{hhv} - \% \text{ash} / 100 * .75 * .2 * (T_{250} - 77) - \text{LS} / \text{total coal} * 775.6)}{(\text{boiler steam} / \text{boiler efficiency} + \text{flash tank steam}) * (1190 - 180)}$$

$$27. \text{ Calcination level} = \frac{\text{CaO} + \text{CaSO}_4 \cdot 56/136}{\text{CaO} + \text{CaSO}_4 \cdot 56/136 + \text{CaCO}_3 \cdot 56/100} * 100$$

APPENDIX D. DAMPER CONFIGURATIONS PER TEST

Explanation of Figure D1 and Table D1.

Figure D1 shows the damper configuration at the exit of the precombustor. Damper A is the damper downstream of the main combustor's head end. Dampers A and B can be adjusted independently, in terms of length or stroke. The 30 degree angle is a fixed angle in which the dampers are positioned. The fully closed position shown in Figure D1 is when the dampers are both pushed in as far as they are designed to go. The width of the flow path in this damper configuration is 5 inches (0% position). The fully open position shown in Figure D1 is when the dampers are both pulled out as far as they are designed to go. The width of the flow path in this damper configuration is 25 inches (100% position).

Table D1 shows the damper configurations used in each test with the performance coal and the Two Bull Ridge coal. The corresponding flow areas have been calculated and are also given in Table D1. Furthermore, DCS precombustor exit temperatures and velocities are also given in Table D1. These values, however, are incorrect mainly because the DCS temperatures were determined utilizing Ohio coal properties. Also, the DCS temperatures assumed 100% carbon utilization in the precombustor, which is thought to be incorrect. Oxidation of the char remaining in the precombustor after devolatilization is assumed to be delayed until reaching the main combustor. Corrections have thus been made for this as well as the utilization of Healy coal properties in the calculations. The last two columns in Table D1 gives the corrected precombustor exit velocities and temperatures for the Healy tests.

Figure D1. Damper Configurations

Table D1. Damper Configurations Per Test

NEALY TESTS	DAMPER POS. A/B, %	AREA FT ²	COAL PC #/HR	COAL MC #/HR	LOAD MMBTU /HR	COAL SPLIT %	PCCA KPPH	PCNB KPPH	PC CARR #/HR	A/F PC	DCS VEL FT/S	DCS EXIT DEG F	CALC TEMP DEG F	CALC VEL FT/S
308-H13	25/25	0.70	959	1558	20.1	38.1	4.38	4.45	950	10.2	327	3000	2300	251
309-H13-1	50/50	1.05	938	1522	19.7	38.1	4.80	6.11	950	12.6	253	2820	2000	179
400-H13-2	65/65	1.26	1013	1513	20.2	40.1	5.28	7.17	950	13.2	253	2696	1950	183
401-H14	90/90	1.60	1200	1913	24.9	38.5	6.30	9.75	950	14.2	255	2545	1820	182
402-H14-1	85/85	1.55	1200	1888	24.7	38.9	6.28	9.21	950	13.7	257	2597	1870	185
404-H14-2	65/65	1.26	1200	2048	25.9	36.9	6.54	8.53	950	13.4	262	2631	1920	191
405-H15	60/60	1.20	1192	1920	24.9	38.3	6.80	7.01	950	12.4	302	2784	2050	222
406-H16	90/90	1.60	1492	2228	29.7	40.1	6.29	11.25	950	12.4	306	2796	2050	224
407-H17	80/80	1.50	1368	2399	30.1	36.3	6.37	9.16	950	12.0	303	2870	2090	220
408-H18	80/80	1.50	1272	2561	30.6	33.2	6.28	11.43	950	14.7	308	2412	1750	223
500-H20	60/60	1.20	1000	1496	19.9	40.1	5.84	5.59	950	11.6	257	2962	2120	184
501-H21	75/75	1.40	1105	1667	22.1	39.9	5.34	7.26	950	12.3	252	2848	2050	181
502-H22	65/65	1.26	971	1465	19.5	39.9	4.79	7.25	950	13.4	251	2628	1920	183
503-H23	65/65	1.26	977	1472	19.6	39.9	5.25	7.45	950	14.0	255	2555	1850	184
504-H24	35/35	0.82	954	1547	20.0	38.1	5.10	7.38	950	14.1	332	2510	1850	244
505-H25	25/25	0.70	799	1684	19.8	32.2	5.13	7.48	950	17.0	331	2184	1620	246
507-H27	0/50	0.73	1160	1331	19.9	46.6	6.30	5.45	950	10.9	401	2980	2200	286
508-H28	0/50	0.73	1162	1332	19.9	46.6	6.12	5.72	950	11.0	421	3000	2200	309
509-H29	0/50	0.73	1168	1338	20.0	46.6	6.45	5.93	950	11.4	444	3000	2150	318
510-H30	0/50	0.73	1162	1332	19.9	46.6	6.40	6.16	950	11.6	443	2998	2150	318
511-H31	0/50	0.73	1167	1342	20.0	46.5	6.06	5.78	950	11.0	420	3000	2200	308
512-H32	0/50	0.73	1152	1325	19.8	46.5	5.74	5.56	950	10.6	403	3000	2250	302
513-H33	0/50	0.73	1155	1330	19.9	46.5	5.74	5.61	950	10.6	406	3000	2250	305
523-H34	0/50	0.73	1167	1344	20.1	46.5	5.94	5.49	950	10.6	401	3000	2250	301
524-H35	0/50	0.73	1177	1356	20.2	46.5	6.45	5.90	950	11.3	428	3000	2150	307
525-H36	0/50	0.73	1160	1337	19.9	46.5	6.05	5.82	950	11.1	422	3000	2200	309
526-H37	0/50	0.73	1168	1344	20.1	46.5	6.37	5.84	950	11.3	422	3000	2150	302
527-H38	0/50	0.73	1156	1331	19.9	46.5	6.38	6.10	950	11.6	434	2996	2150	311
528-H39	0/50	0.73	1173	1352	20.2	46.5	6.19	6.02	950	11.2	419	3000	2200	307
529-H40	40/70	1.12	1165	1342	20.0	46.5	6.10	5.93	950	11.1	326	3000	2200	239
530-H41	0/50	0.73	1179	1357	20.3	46.5	6.23	6.00	950	11.2	423	3000	2200	310
531-H42	0/50	0.73	1168	1345	20.1	46.5	6.22	5.88	950	11.2	423	3000	2200	310
532-H43	0/50	0.73	1154	1328	19.8	46.5	6.36	6.07	950	11.6	421	2976	2150	304
533-H44	0/55	0.76	1154	1330	19.8	46.5	6.08	5.88	950	11.2	415	2996	2200	304
534-H45	10/70	0.94	1171	1348	20.1	46.5	6.00	5.85	950	10.9	374	3000	2200	274
535-H46	60/100	1.47	1185	1342	20.0	46.5	5.75	5.44	950	10.4	235	3000	2250	176
536-H47	0/80	0.96	1160	1323	19.8	46.5	6.17	6.01	950	11.4	361	3000	2150	259
537-H48	0/90	1.04	1147	1322	19.7	46.5	6.34	6.10	950	11.7	346	2974	2150	250
539-H50	20/100	1.23	1159	1334	19.9	46.5	6.26	5.72	950	11.2	289	2982	2200	213
540-H51	100/100	1.74	1169	1346	20.1	46.5	6.11	6.05	950	11.2	208	3000	2200	153
541-H52	100/100	1.74	1171	1350	20.1	46.4	6.11	6.02	950	11.2	207	3000	2200	152
542-H53	60/60	1.20	1160	1337	19.9	46.5	6.38	6.17	950	11.6	298	2974	2150	215
543-H54	50/50	1.05	1143	1317	19.6	46.5	6.15	5.65	950	11.2	296	3000	2200	217
544-H55	70/70	1.34	1147	1320	19.7	46.5	6.28	5.98	950	11.5	268	3000	2150	192
545-H56	0/75	0.84	1167	1345	20.1	46.5	6.28	6.06	950	11.4	349	3000	2150	250
546-H57	0/50	0.73	1173	1352	20.2	46.5	5.96	5.85	950	10.9	422	3000	2200	309
547-H58	6/50	0.73	1156	1333	19.9	46.5	6.23	6.02	950	11.4	430	2991	2150	309
548-H59	0/50	0.73	1154	1329	19.8	46.5	6.20	5.93	950	11.3	424	3000	2150	304
549-H60	0/55	0.76	1140	1314	19.6	46.5	5.96	5.80	950	11.2	401	3000	2200	294
550-H61	0/50	0.73	1168	1344	20.1	46.5	6.28	6.28	950	11.6	447	2977	2150	323
551-H62	0/50	0.73	1153	1327	19.8	46.5	6.14	6.05	950	11.4	425	3000	2150	305
552-H63	10/50	0.78	1134	1306	19.5	46.5	5.44	6.23	950	12.0	396	2959	2160	289

HEALY TESTS	DAMPER P' . A/B, %	AREA FT2	COAL PC #/HR	COAL MC #/HR	LOAD MMBTU /HR	COAL SPLIT %	PCCA KPPH	PCMB KPPH	PC CARR #/HR	A/F PC	DCS VEL FT/S	DCS EXIT DEG F	CALC TEMP DEG F	CALC VEL FT/S
553-TBR1	0/50	0.73	679	1060	12.8	39.0	4.02	2.37	950	13.8	230	2992	2000	154
554-TBR2	0/50	0.73	1060	1658	20.0	39.0	4.79	6.23	950	11.3	373	2858	1950	254
555-TBR3	0/50	0.73	1600	1855	25.4	46.3	6.00	5.55	950	7.8	420	3000	2450	343
556-TBR4	0/50	0.73	1480	1674	23.2	46.9	6.39	9.47	950	11.4	498	2801	1950	3/7
557-TBR5	0/75	0.84	1474	1666	23.1	46.9	6.16	9.60	950	11.3	454	2824	1950	313
558-TBR6	0/75	0.84	1523	1720	23.9	47.0	6.21	9.84	950	11.2	465	2824	1950	321
559-TBR7	100/100	1.74	1489	1683	23.3	46.9	6.22	9.91	950	11.5	259	2800	1950	180
560-TBR8	100/100	1.74	1482	1675	23.2	46.9	6.49	9.66	950	11.5	259	2802	1950	180
561-TBR9	100/100	1.74	1504	1700	23.6	46.9	6.52	9.71	950	11.4	270	2900	1950	182
562-TBR10	0/50	0.73	1192	1347	18.7	46.9	5.87	5.91	950	10.7	417	2994	2000	279
563-TBR11	0/50	0.73	1135	1282	17.8	47.0	6.12	5.98	950	11.5	423	2963	1950	278
564-TBR12	0/50	0.73	1134	1281	17.8	47.0	5.95	6.01	950	11.4	419	2979	1950	274

APPENDIX E. CALCINATION DATA

Explanation of Tables E1 to E3.

The following Tables were constructed by NIRO. Their variables were defined as follows.

Ca (wt%) - is the weight percent of calcium in the FCM sample. This was determined by treatment in HCL followed by atomic absorption.

CO2 (wt%) - is the carbon dioxide released due to decomposition of carbonate in excess HCL. The CO2 is measured by absorption on Ascarite (weight difference in absorbent determines content).

SO4 (wt%) - is determined by treatment with HCL followed by ion chromatograph. The SO4 content is utilized to determine the amount of CaSO4 in the FCM.

CaO (wt%) - is the calcium oxide in the FCM. This was determined by titration with an HCL standard.

Ca-diff - tells something about how much Ca is bound as non-reactive CaO.

$$= \text{Ca} - (\text{CO}_2 * 40/44 + \text{SO}_4 * 40/96 + \text{CaO} * 40/56)$$

HCL Insol. (wt%) - is the weight percent of insolubles in the HCL solution.

Flyash (wt%) - amount of flyash in the FCM.

$$= \frac{(\text{wt\% HCL Insol. in FCM})}{(\text{wt\% HCL Insol. in avg. Flyash})} * 100$$

CaO (wt%) without flyash - amount of CaO in FCM contributed by limestone.

$$= \text{CaO in FCM} - \text{CaO in avg. Flyash} * (\text{flyash\%/100})$$

CaCO3 (wt%) without flyash - amount of CaCO3 in FCM contributed by limestone.

$$= \text{CaCO}_3 \text{ in FCM} - \text{CaCO}_3 \text{ in avg. Flyash} * (\text{flyash\%/100})$$

CaSO4 (wt%) without flyash - amount of CaSO4 in FCM contributed by limestone.

$$= \text{CaSO}_4 \text{ in FCM} - \text{CaSO}_4 \text{ in avg. Flyash} * (\text{flyash\%/100})$$

Table E-1. NIRO Data on Calcination

Sample	Ca wt%	CO ₂ wt%	SO ₄ wt%	CaSO ₄ wt%	CaCO ₃ wt%	CaO wt%	Ca diff. wt%	HCl insol. wt%	Fly ash wt%	CaO wt%	CaCO ₃ without fly ash wt%	CaSO ₄ wt%	sum
H-13-2, fly ash	4.60	0.52	1.58	2.24	1.18	0.55	3.08	74.56	100.0	0.0	0.0	0.0	100.0
H-13-1, fly ash	5.78	0.18	2.01	2.85	0.41	0.96	4.09	71.54	100.0	0.0	0.0	0.0	100.0
H-14, fly ash	6.58	0.20	2.53	3.67	0.45	1.09	4.54	67.46	100.0	0.0	0.0	0.0	100.0
H-22, FCM	9.06	1.94	2.45	3.47	4.41	6.20	1.85	64.65	90.8	5.4	3.8	0.8	100.8
H-23, FCM	8.97	2.37	2.73	3.87	5.39	4.86	2.21	62.47	87.8	4.1	4.8	1.3	98.1
H-24, FCM	10.66	3.60	3.80	5.38	8.18	6.20	1.38	67.00	94.1	5.4	7.5	2.6	109.6
H-25, FCM	8.95	3.80	3.50	4.96	8.64	4.90	0.54	65.70	92.3	4.1	8.0	1.0	105.4
H-27, FCM	9.55	3.50	3.20	4.53	7.95	4.50	1.82	63.90	89.8	3.7	7.3	1.9	102.7
H-28, FCM	9.95	4.00	3.30	4.68	9.09	4.60	1.65	60.00	84.3	3.9	8.5	2.2	98.9
H-29, FCM	9.51	3.15	3.84	5.44	7.16	4.04	2.16	59.58	83.7	3.3	6.6	3.0	96.6
H-30, FCM	9.68	2.95	3.96	5.61	6.70	3.82	2.62	67.85	95.3	3.0	6.1	2.8	107.2
H-31, FCM	8.29	2.93	3.09	4.38	6.66	3.10	2.12	67.44	94.7	2.3	6.0	1.6	104.6
H-32, FCM	8.14	2.58	3.03	4.29	5.86	3.09	2.32	65.18	91.6	2.3	5.2	1.6	100.7
H-33, FCM	12.34	7.62	5.96	8.44	17.32	2.14	1.40	57.94	81.4	1.4	16.8	6.1	105.7
H-33A, FCM	8.56	2.57	3.87	5.48	5.84	2.53	2.80	58.38	82.0	1.8	5.3	3.1	92.2
Average									89.7	3.7	6.3	2.0	101.7

Table E-2. NIRO Data on Calcination (Cont.)

Sample	Ca wt%	CO ₂ wt%	SO ₄ wt%	CaSO ₄ wt%	CaCO ₃ wt%	CaO wt%	Ca diff. wt%	RCI insol. wt%	Fly ash wt%	CaO wt%	CaCO ₃ without fly ash wt%	CaSO ₄ wt%	sum
H-44, limestone	37.78	42.25											
H-41, limestone	37.69	42.27											
H-34, FCM	7.25	0.32	3.00	4.25	0.73	2.5	3.92	64.94	91.2	1.7	0.1	1.6	94.6
H-35, FCM	9.44	1.00	3.08	4.36	2.27	3.56	4.70	59.95	84.2	2.8	1.7	1.9	90.6
H-36, FCM	9.50	1.04	3.08	4.36	2.36	4.79	3.85	59.76	83.9	4.1	1.8	1.9	91.7
H-37, FCM	9.44	1.04	3.16	4.48	2.36	4.61	3.89	62.05	87.2	3.9	1.8	1.9	94.8
H-38, FCM	9.25	0.58	3.16	4.48	1.32	4.72	4.03	63.11	88.7	4.0	0.7	1.9	95.3
H-39, FCM	9.58	1.27	2.82	3.99	2.89	4.60	3.96	59.85	84.1	3.9	2.3	1.5	91.8
H-40, FCM	10.05	0.55	3.10	4.39	1.25	5.52	4.32	54.21	76.2	4.9	0.7	2.2	83.9
H-41, FCM	9.85	0.52	3.57	5.06	1.18	5.32	4.09	59.75	83.9	4.6	0.6	2.6	91.7
H-42, FCM	9.00	0.64	3.56	5.04	1.45	4.73	3.56	57.79	81.2	4.0	0.9	2.7	88.8
H-43, FCM	8.89	0.74	3.59	5.09	1.68	4.78	3.31	64.79	91.0	4.0	1.1	2.4	98.5
H-44, FCM	9.04	0.70	3.38	4.79	1.59	4.59	3.72	56.43	79.3	3.9	1.1	2.5	86.8
H-45, FCM	10.04	0.77	3.44	4.87	1.75	5.05	4.30	58.63	82.4	4.3	1.2	2.5	90.4
Average									84.4	3.8	1.2	2.1	91.5

Table E-3. NIRO Data on Calcination (Cont.)

Sample	Ca wt%	CO ₂ wt%	SO ₄ wt%	CaSO ₄ wt%	CaCO ₃ wt%	CaO wt%	Ca diff. wt%	HCl insol. wt%	Fly ash wt%	CaO without fly ash wt%	CaCO ₃ without fly ash wt%	CaSO ₄ wt%	sum
H-46, FCM						4.92							
H-47, FCM	7.15	1.22	2.44	3.46	2.77	4.55	1.77	75.42	105.9	3.6	2.1	0.4	112.0
H-48, FCM						4.65							
H-50, FCM						6.10							
H-51, FCM	8.90	1.37	2.60	3.68	3.11	5.40	2.71	68.06	95.6	4.6	2.5	0.9	103.6
H-52, FCM						5.02							
H-53, FCM						5.62							
H-54, FCM	7.82	1.13	2.52	3.57	2.57	4.87	2.26	70.67	99.3	4.0	1.9	0.7	105.9
H-55, FCM						5.45							
H-56, FCM						5.85							
H-57, FCM	9.50	1.25	2.90	4.11	2.84	5.53	3.21	65.92	92.6	4.7	2.2	1.4	100.9
H-58, FCM						6.00							
H-59, FCM						5.57							
H-60, FCM	8.75	1.00	3.01	4.26	2.27	5.27	2.82	67.23	94.4	4.5	1.6	1.5	102.0
H-61, FCM						5.41							
H-62, FCM						5.79							
H-63, FCM	9.91	0.90	3.05	4.32	2.05	6.58	3.12	62.35	87.6	5.8	1.4	1.8	96.6
Average									95.9	4.5	2.0	1.1	103.5

END

**DATE
FILMED**

4 / 17 / 92