SDC-92-384

Final Report on Cost Estimate of Forward Superconducting Air Core Toroid*

T. Fields

ANL-HEP-TR--92-122

Argonne National Laboratory

DE93 005549

December 1992

Abstract

An independent cost-estimate for key components of the forward superconducting air core toroid (ACT) was obtained in May 1992 from an experienced manufacturer of large cryogenic vessels. This new cost estimate is summarized in this report. It implies that a suitably designed ACT may have a cost which is approximately equal to that of the presently designed SDC forward iron core toroid.

Introduction

The SDC decision to use an iron core toroid (ICT) rather than a superconducting ACT for the forward angle region was based on cost and physics benefit issues which have been described in an SDC note (ref. 1). That SDC note also emphasized the large uncertainties in the cost of the ACT. These uncertainties drove the choice toward the ICT, despite the better physics capabilities of an ACT. Main sources of these uncertainties included:

1. Two radically different ACT conceptual designs were made, and their estimated cost differed by a factor of 4.
2. The (lower cost) design made by Advanced Cryo Magnetics (ACM) (described in ref. 2) incorporated several novel design features which were designed to minimize costs. However, no independent cost estimate was available.

A logical next step to clarify these cost matters was to obtain an independent, more detailed cost estimate for the ACM design. For this purpose, a contract was let in early 1992 from ANL to Pitt-Des Moines, Inc. (PDM), a company with extensive experience in the design, cost-estimating, and fabrication of very large, aluminum (welded) cryogenic vessels. PDM was supplied with the ACM conceptual design report (with all ACM cost estimate information omitted).

In the remainder of this note, we first summarize the independent cost estimate report from PDM, then we compare that estimate to the original ACM cost estimate, and finally we give some conclusions.

PDM Report

The report from PDM, dated May 12, 1992, is a 30 page document. Copies of it can be obtained from the present author (email THF@ANLHEP).

The report first notes that the ACM conceptual design report (ref. 2) is not detailed enough to support pricing at the fabrication and welding level. Therefore, additional design work was done by PDM before they made their cost estimate. Furthermore, only 4 major components of the toroid were estimated: toroid former, helium vessel, heat shield, and vacuum vessel. These

*Work supported by U.S. Department of Energy, High Energy Physics Division under Contract No. W-31-109-ENG-38.

particular components were chosen because their design and fabrication features are well matched to PDM's capabilities and experience.

Appendix A is a spreadsheet from the PDM report. It shows that the PDM total estimate for these four components is \$2.9M. Appendix B shows the construction time schedule given in the PDM report.

Comparison with ACM Estimate

The total cost of the above-mentioned four components in the ACM estimate (ref. 2) is given as \$5.1M. Thus the cost estimating from ACM seems conservative, as was stated by ACM.

Averaging the above two estimates gives \$4.0M. To this I shall add \$5.4M, which is the cost estimate from ACM of all items (including a liquifier system) which are not included in the PDM study. This yields a new estimate of the total cost per toroid of \$9.4M. This is about 10% less than the ACM estimate.

Conclusions

My conclusions are these:

1. A more reliable cost estimate of \$9.4M per ACT is now available.
2. This can be compared to the present cost estimate of \$8.0M for each iron toroid which can be deduced from ref. 3.
3. The comparative physics advantages of the 100 ton ACT versus those of the 2400 ton ICT stand as described in ref. 1.
4. Independent cost analysis has supported the ACM claim that their design incorporates economical construction and assembly methods.
5. The ACM design also emphasizes high stability against quenches. Independent documented review of this and other fundamental design features would be desirable before more detailed engineering design work were carried out.
6. In view of the cost estimate comparisons discussed in this note, the use of superconducting toroids in the forward angle region should continue to be seriously considered for high energy collider detectors.

Acknowledgment

The help and advice of Norm Hill is much appreciated.

References

1. Report of the SDC ACT Task Force, SDC-91-00046.
2. Superconducting Toroidal Magnet Conceptual Design Report, SDC-90-130.
3. SDC Project Cost/Schedule Summary Book, SDC-000021 (Rev. B) (Oct. 1992).

APPENDIX A

YACARD VESSEL				HEAT EXCHANGER				HELIUM VESSEL				HYDRO TOWER			
EXCLUDES - Supply & Installation of Superinsulation on Heat Shield				EXCLUDES - Supply & Installation of Carbon Loops				EXCLUDES - Insulation & Wiring of Cables on Tower							
UNIT	COST	SUBTOTAL		UNIT	COST	SUBTOTAL		UNIT	COST	SUBTOTAL		UNIT	COST	SUBTOTAL	
44,756	89,512	0		64,496	128,992	0		31,145	62,290	0					
34,491	8,056	0		53,261	18,940	0		22,631	12,940	0					
1,343	281	0		3,100	3,900	0		2,158	2,158	0					
38,315	101,889	0		56,476	151,858	0		24,509	100,000	0					
500	11,400	24,340		500	12,760	24,340		300	9,940	16,416					
800	13,220	0		1,000	16,400	0		600	9,960	0					
500	15,936	30,544			19,920	38,180			11,970	22,900					
500	13,375	32,100		500	13,375	32,100		500	13,375	32,100					
2,489	28,226	0		3,134	35,440	0		6,926	78,244	0					
500	4,461	32,100			58,806	0			129,136	0					
5,000	5,000	80,097			0	0			0	0					
2,405	2,405	2,405			5,000	100,159			9,540	228,505					
					0	0			10,000	24,000					
					1,927	1,927			21,000	21,000					
					3,000	6,000			3,000	6,000					
5,439	92,508	0		9,952	163,243	0		2,332	38,254	0					
294.4	1,850	0		351.2	1,211	0		189.7	4,093	0					
17,716	17,716	0		mm / ton	26,494	0		mm / ton	6,255	0					
28,632	28,632	0		51,249	50,531	0			7,322	0					
21,710	21,710	0		38,315	38,315	0			11,841	0					
14,917	14,917	0		28,245	28,245	0			8,978	0					
28,195	28,195	0		19,944	19,944	0			4,464	0					
7,000	7,000	285,829		49,760	10,000	0			11,460	0					
480	7,874	0		15,800	5,000	441,122			1,168	117,022					
13,701	13,701	0		800	13,124	0		280	5,393	0					
		21,575			22,834	35,940			7,993	0					
		0			0	0			0	0					
		0			0	0			0	0					
		0			0	0			0	0					
		0			0	0			0	0					
		358,999				851,646									
		47,000				102,200									
		626,079				953,866									
		0				0									
		62,608				95,387									
		605,497				1,049,233									

SHORT FORM ESTIMATE SHEET											
CONTRACT NUMBER: 40120		INQUIRY NUMBER:		FILE: SECURECEST		DATE: 4/20/92		OWNER: U.S. D.O.E.			
PROJECT DESCRIPTION: SSC Reactor Vacuum Vessel		PURCHASER: Argonne National Laboratory		ESTIMATE TYPE:							
LOCATION: Madison, IL		PRODUCT C/P: 24/90									
BRANCH:											
ENGR: PLE / J.P.P.		DATE: PLE / J.P.P.		FAIR: PLE / J.P.P.		CLIVE: PLE / J.P.P.					
IC	DESCRIPTION	UNIT	COST	SUBTOTAL	DATE: PLE / J.P.P.	DATE: PLE / J.P.P.	DATE: PLE / J.P.P.	DATE: PLE / J.P.P.	DATE: PLE / J.P.P.	DATE: PLE / J.P.P.	DATE: PLE / J.P.P.
011	MATERIALS - PLATES/SHAPES		160,572	321,144							
012	MATERIALS - NET WEIGHT PLATES & SHAPES		127,237	48,200							
013	MATERIALS - WELD CONSUMABLES	64.00 / lb.	11,133	11,133							
014	MATERIALS - NET WEIGHT & COST		136,102	136,102							
015	MATERIALS - NET WEIGHT & COST		136,102	136,102							
016	MATERIALS - NET WEIGHT & COST		136,102	136,102							
017	MATERIALS - NET WEIGHT & COST		136,102	136,102							
018	MATERIALS - NET WEIGHT & COST		136,102	136,102							
019	MATERIALS - NET WEIGHT & COST		136,102	136,102							
020	MATERIALS - NET WEIGHT & COST		136,102	136,102							
021	MATERIALS - NET WEIGHT & COST		136,102	136,102							
022	MATERIALS - NET WEIGHT & COST		136,102	136,102							
023	MATERIALS - NET WEIGHT & COST		136,102	136,102							
024	MATERIALS - NET WEIGHT & COST		136,102	136,102							
025	MATERIALS - NET WEIGHT & COST		136,102	136,102							
026	MATERIALS - NET WEIGHT & COST		136,102	136,102							
027	MATERIALS - NET WEIGHT & COST		136,102	136,102							
028	MATERIALS - NET WEIGHT & COST		136,102	136,102							
029	MATERIALS - NET WEIGHT & COST		136,102	136,102							
030	MATERIALS - NET WEIGHT & COST		136,102	136,102							
031	MATERIALS - NET WEIGHT & COST		136,102	136,102							
032	MATERIALS - NET WEIGHT & COST		136,102	136,102							
033	MATERIALS - NET WEIGHT & COST		136,102	136,102							
034	MATERIALS - NET WEIGHT & COST		136,102	136,102							
035	MATERIALS - NET WEIGHT & COST		136,102	136,102							
036	MATERIALS - NET WEIGHT & COST		136,102	136,102							
037	MATERIALS - NET WEIGHT & COST		136,102	136,102							
038	MATERIALS - NET WEIGHT & COST		136,102	136,102							
039	MATERIALS - NET WEIGHT & COST		136,102	136,102							
040	MATERIALS - NET WEIGHT & COST		136,102	136,102							
041	MATERIALS - NET WEIGHT & COST		136,102	136,102							
042	MATERIALS - NET WEIGHT & COST		136,102	136,102							
043	MATERIALS - NET WEIGHT & COST		136,102	136,102							
044	MATERIALS - NET WEIGHT & COST		136,102	136,102							
045	MATERIALS - NET WEIGHT & COST		136,102	136,102							
046	MATERIALS - NET WEIGHT & COST		136,102	136,102							
047	MATERIALS - NET WEIGHT & COST		136,102	136,102							
048	MATERIALS - NET WEIGHT & COST		136,102	136,102							
049	MATERIALS - NET WEIGHT & COST		136,102	136,102							
050	MATERIALS - NET WEIGHT & COST		136,102	136,102							
051	MATERIALS - NET WEIGHT & COST		136,102	136,102							
052	MATERIALS - NET WEIGHT & COST		136,102	136,102							
053	MATERIALS - NET WEIGHT & COST		136,102	136,102							
054	MATERIALS - NET WEIGHT & COST		136,102	136,102							
055	MATERIALS - NET WEIGHT & COST		136,102	136,102							
056	MATERIALS - NET WEIGHT & COST		136,102	136,102							
057	MATERIALS - NET WEIGHT & COST		136,102	136,102							
058	MATERIALS - NET WEIGHT & COST		136,102	136,102							
059	MATERIALS - NET WEIGHT & COST		136,102	136,102							
060	MATERIALS - NET WEIGHT & COST		136,102	136,102							
061	MATERIALS - NET WEIGHT & COST		136,102	136,102							
062	MATERIALS - NET WEIGHT & COST		136,102	136,102							
063	MATERIALS - NET WEIGHT & COST		136,102	136,102							
064	MATERIALS - NET WEIGHT & COST		136,102	136,102							
065	MATERIALS - NET WEIGHT & COST		136,102	136,102							
066	MATERIALS - NET WEIGHT & COST		136,102	136,102							
067	MATERIALS - NET WEIGHT & COST		136,102	136,102							
068	MATERIALS - NET WEIGHT & COST		136,102	136,102							
069	MATERIALS - NET WEIGHT & COST		136,102	136,102							
070	MATERIALS - NET WEIGHT & COST		136,102	136,102							
071	MATERIALS - NET WEIGHT & COST		136,102	136,102							
072	MATERIALS - NET WEIGHT & COST		136,102	136,102							
073	MATERIALS - NET WEIGHT & COST		136,102	136,102							
074	MATERIALS - NET WEIGHT & COST		136,102	136,102							
075	MATERIALS - NET WEIGHT & COST		136,102	136,102							
076	MATERIALS - NET WEIGHT & COST		136,102	136,102							
077	MATERIALS - NET WEIGHT & COST		136,102	136,102							
078	MATERIALS - NET WEIGHT & COST		136,102	136,102							
079	MATERIALS - NET WEIGHT & COST		136,102	136,102							
080	MATERIALS - NET WEIGHT & COST		136,102	136,102							
081	MATERIALS - NET WEIGHT & COST		136,102	136,102							
082	MATERIALS - NET WEIGHT & COST		136,102	136,102							
083	MATERIALS - NET WEIGHT & COST		136,102	136,102							
084	MATERIALS - NET WEIGHT & COST		136,102	136,102							
085	MATERIALS - NET WEIGHT & COST		136,102	136,102							
086	MATERIALS - NET WEIGHT & COST		136,102	136,102							
087	MATERIALS - NET WEIGHT & COST		136,102	136,102							
088	MATERIALS - NET WEIGHT & COST		136,102	136,102							
089	MATERIALS - NET WEIGHT & COST		136,102	136,102							
090	MATERIALS - NET WEIGHT & COST		136,102	136,102							
091	MATERIALS - NET WEIGHT & COST		136,102	136,102							
092	MATERIALS - NET WEIGHT & COST		136,102	136,102							
093	MATERIALS - NET WEIGHT & COST		136,102	136,102							
094	MATERIALS - NET WEIGHT & COST		136,102	136,102							
095	MATERIALS - NET WEIGHT & COST		136,102	136,102							
096	MATERIALS - NET WEIGHT & COST		136,102	136,102							
097	MATERIALS - NET WEIGHT & COST		136,102	136,102							
098	MATERIALS - NET WEIGHT & COST		136,102	136,102							
099	MATERIALS - NET WEIGHT & COST		136,102	136,102							
100	MATERIALS - NET WEIGHT & COST		136,102	136,102							
101	MATERIALS - NET WEIGHT & COST		136,102	136,102							
102	MATERIALS - NET WEIGHT & COST		136,102	136,102							
103	MATERIALS - NET WEIGHT & COST		136,102	136,102							
104	MATERIALS - NET WEIGHT & COST		136,102	136,102							
105	MATERIALS - NET WEIGHT & COST		136,102	136,102							
106	MATERIALS - NET WEIGHT & COST		136,102	136,102							
107	MATERIALS - NET WEIGHT & COST		136,102	136,102							
108	MATERIALS - NET WEIGHT & COST		136,102	136,102							
109	MATERIALS - NET WEIGHT & COST		136,102	136,102							
110	MATERIALS - NET WEIGHT & COST		136,102	136,102							
111	MATERIALS - NET WEIGHT & COST		136,102	136,102							
112	MATERIALS - NET WEIGHT & COST		136,102	136,102							
113	MATERIALS - NET WEIGHT & COST		136,102	136,102							
114	MATERIALS - NET WEIGHT & COST		136,102	136,102							
115	MATERIALS - NET WEIGHT & COST		136,102	136,102							
116	MATERIALS - NET WEIGHT & COST		136,102	136,102							
117	MATERIALS - NET WEIGHT & COST		136,102	136,102							
118	MATERIALS - NET WEIGHT & COST		136,102	136,102							
119	MATERIALS - NET WEIGHT & COST		136,102	136,102							
120	MATERIALS - NET WEIGHT & COST		136,102	136,102							
121	MATERIALS - NET WEIGHT & COST		136,102	136,102							
122	MATERIALS - NET WEIGHT & COST		136,102	136,102							
123	MATERIALS - NET WEIGHT & COST		136,102	136,102							
124	MATERIALS - NET WEIGHT & COST		136,102	136,102							
125	MATERIALS - NET WEIGHT & COST		136,102	136,102							
126	MATERIALS - NET WEIGHT & COST		136,102	136,102							
127	MATERIALS - NET WEIGHT & COST		136,102	136,102							
128	MATERIALS - NET WEIGHT & COST		136,102	136,102							
129	MATERIALS - NET WEIGHT & COST		136,102	136,102							
130	MATERIALS - NET WEIGHT & COST		136,102	136,102							
131	MATERIALS - NET WEIGHT & COST		136,102	136,102							
132	MATERIALS - NET WEIGHT & COST		136,102	136,102							
133	MATERIALS - NET WEIGHT & COST		136,102	136,102							
134	MATERIALS - NET WEIGHT & COST		136,102	136,102							
135	MATERIALS - NET WEIGHT & COST		136,102	136,102							
136	MATERIALS - NET WEIGHT & COST		136,102	136,102							
137	MATERIALS - NET WEIGHT & COST		136,102	136,102							
138	MATERIALS - NET WEIGHT & COST		136,102	136,102							
139	MATERIALS - NET WEIGHT & COST		136,102	136,102							
140	MATERIALS - NET WEIGHT & COST		136,102	136,102							
141	MATERIALS - NET WEIGHT & COST		136,102	136,102							
142	MATERIALS - NET WEIGHT & COST		136,102	136,102							
143	MATERIALS - NET WEIGHT & COST		136,102	136,102							
144	MATERIALS - NET WEIGHT & COST		136,102	136,102							
145	MATERIALS - NET WEIGHT & COST		136,102	136,102							
146	MATERIALS - NET WEIGHT & COST		136,102	136,102							
147	MATERIALS - NET WEIGHT & COST		136,102	136,102							
148	MATERIALS - NET WEIGHT & COST		136,102	136,102							
149	MATERIALS - NET WEIGHT & COST		136,102	136,102							
150	MATERIALS - NET WEIGHT & COST		136,102	136,102							
151	MATERIALS - NET WEIGHT & COST		136,102	136,102							
152	MATERIALS - NET WEIGHT & COST		136,102	136,102							
153	MATERIALS - NET WEIGHT & COST		136,102	136,102							
154	MATERIALS - NET WEIGHT & COST		136,102	136,102							
155	MATERIALS - NET WEIGHT & COST		136,102	136,102							
156	MATERIALS - NET WEIGHT										

APPENDIX B

Task Name	Start Date	Duration	End Date	1992				1993				1994			
				Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3		
AWARD OF CONTRACT	1-Jun-92	0.0	1-Jun-92												
ENGINEERING	1-Jun-92	20.0 w	22-Oct-92												
DRAFTING	29-Jun-92	20.0 w	20-Nov-92												
MATERIAL PROCUREMENT	28-Jul-92	20.0 w	21-Dec-92												
FABRICATION:	22-Oct-92	35.0 w	6-Jul-93												
TOROID FORMER	22-Oct-92	15.0 w	11-Feb-93												
HELIUM VESSEL	11-Feb-93	8.0 w	9-Apr-93												
HEAT SHIELD	9-Apr-93	6.0 w	21-May-93												
VACUUM VESSEL	21-May-93	6.0 w	6-Jul-93												
CONSTRUCTION:	11-Feb-93	70.0 w	5-Jul-94												
TOROID FORMER	11-Feb-93	7.0 w	2-Apr-93												
WIND COILS (ANL)	2-Apr-93	26.0 w	6-Oct-93												
HELIUM VESSEL	24-Aug-93	20.0 w	20-Jan-94												
INSTALL CARBON TIES (ANL)	20-Jan-94	6.0 w	4-Mar-94												
HEAT SHIELD	17-Feb-94	7.0 w	8-Apr-94												
INSTALL SUPERINSULATION (ANL)	8-Apr-94	4.0 w	6-May-94												
VACUUM VESSEL	8-Apr-94	12.0 w	5-Jul-94												
PROJECT COMPLETE	5-Jul-94	0.0	5-Jul-94												

PDM CONTRACT 60120
 ARGONNE P.D. 061188
 May 13, 1992

PRELIMINARY SCHEDULE
 SSC - AIR CORE SUPERCONDUCTING TOROID
 for ARGONNE NATIONAL LABORATORY

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

END

DATE
FILMED

5/03/93