WSRC-RP-89-453

Copy No. ~~1121~~

ENVIRONMENTAL IMPLEMENTATION PLAN (U)

Volume II
Protection Programs

Derivative
Classifier

6/15/84 (Name, Title, Date) 273

Westinghouse Savannah River Company
Savannah River Site
Aiken, SC 29808

PREPARED FOR THE U.S. DEPARTMENT OF ENERGY UNDER CONTRACT NO. DE-AC09-76SR00001
(NOW CONTRACT NO. DE-AC09-88SR18035)

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

VOLUME II - PROTECTION PROGRAMS

Table of Contents

List of Tables

List of Figures

List of Acronyms

Department of Energy Orders

Applicable Laws and Administrative Requirements

1.0 INTRODUCTION

1.1 Background

1.2 Document Organization

2.0 SITE DESCRIPTION

3.0 SURFACE WATERS AND WETLANDS PROTECTION

Contents

3.1 Overview

3.1.1 Introduction

3.1.1 Summary

3.2 Policy

3.2.1 Policy Statement

3.2.2 Background for Policy Statement

3.3 Existing Conditions

3.4 Objectives

3.5 Strategy

3.6 Implementation

3.6.1 Stream Management

- 3.6.1.1 Site Program Overview**
- 3.6.1.2 Justification**
- 3.6.1.3 Organization Responsibilities Summary**
- 3.6.1.4 Stream Policies**
- 3.6.1.5 Programs**
- 3.6.1.6 Research/Studies**

3.6.2 Thermal Mitigation

- 3.6.2.1 Site Program Overview**
- 3.6.2.2 Justification/Regulatory Requirements**
- 3.6.2.3 Organizational Responsibilities Summary**
- 3.6.2.4 Facility Operations**
- 3.6.2.5 Construction Projects**
- 3.6.2.6 Research/Studies**
- 3.6.2.7 Thermal Compliance Monitoring**

3.6.3 NPDES

- 3.6.3.1 Site Program Overview**
- 3.6.3.2 Justification/Regulatory Requirements**
- 3.6.3.3 Organizational Responsibilities Summary**
- 3.6.3.4 Permit Renewal**
- 3.6.3.5 NPDES Permit Compliance Programs**
- 3.6.3.6 Research/Studies**

3.6.4 River Monitoring

- 3.6.4.1 Site Program Overview**
- 3.6.4.2 Justification**
- 3.6.4.3 Organizational Responsibilities Summary**
- 3.6.4.4 Research/Studies**
- 3.6.4.5 Reporting of Results**

3.6.5 Erosion Control

- 3.6.5.1 Site Program Overview**
- 3.6.5.2 Justification/Regulatory Requirements**
- 3.6.5.3 Organizational Responsibilities Summary**

3.6.5.4	Programs
3.6.5.5	Research/Studies
3.6.6	Waste Treatment Facilities
3.6.6.1	Site Program Overview
3.6.6.2	Justification/Regulatory Requirements
3.6.6.3	Organizational Responsibilities Summary
3.6.6.4	Permitted Facilities
3.6.6.5	Planned Facilities
3.6.6.6	Training (Operator Certification)
3.6.7	Spill Prevention/Control/Responses
3.6.7.1	Site Program Overview
3.6.7.2	Justification/Regulatory Requirements
3.6.7.3	Organizational Responsibilities Summary
3.6.7.4	Best Management Practices/Spill Prevention, Control, and Countermeasures Plans
3.6.7.5	Facilities Operations
3.6.7.6	Construction Projects
3.6.7.7	Research/Studies
3.6.7.8	Monitoring (Compliance)
3.6.8	Radiological Effluent Management
3.6.8.1	Site Program Overview
3.6.8.2	Justification/Regulatory Requirements
3.6.8.3	Organizational Responsibilities Summary
3.6.8.4	Programs
3.6.8.5	Facilities Operations
3.6.8.6	Construction Projects
3.6.8.7	Research/Studies
3.6.9.8	Release Guide Monitoring
3.6.9	Wetlands
3.6.9.1	Site Program Overview
3.6.9.2	Justification/Regulatory Requirements
3.6.9.3	Organizational Responsibilities Summary
3.6.9.4	Programs
3.6.9.5	Research/Studies
3.6.9.6	Compliance Monitoring

3.7 Resource Requirements

3.8 References

- Attachment 3.1 SRS NPDES Outfalls**
Attachment 3.2 Facility Compliance/Surveillance Procedures for BMP/SPCC Plans

4.0 SAFE DRINKING WATER AND OTHER COMPLIANCE PROGRAMS

Contents

4.1 Safe Drinking Water Act (SDWA)

- 4.1.1 Site Program Overview
- 4.1.2 Existing Conditions
- 4.1.3 Regulatory Requirements
- 4.1.4 Facilities Operations
- 4.1.5 Construction Projects
- 4.1.6 References

4.2 National Environmental Policy Act (NEPA)

- 4.2.1 Site Program Overview
- 4.2.2 Regulatory Requirements
- 4.2.3 Organizational Responsibilities
- 4.2.4 Program Activities

4.3 Toxic Substances Control Act (TSCA)

- 4.3.1 Polychlorinated Biphenyls (PCBs)
 - 4.3.1.1 Site Program Overview
 - 4.3.1.2 Regulatory Requirements
 - 4.3.1.3 Organizational/Personnel Responsibilities
 - 4.3.1.4 Auditing
 - 4.3.1.5 Compliance Actions
 - 4.3.1.6 References

4.3.2 Premanufacturing Notification (PMN)

- 4.3.2.1 Regulatory Requirements**
- 4.3.2.2 Organizational Compliance Responsibilities**
- 4.3.2.3 Compliance Actions**

4.3.3 Reporting Uses of Existing Chemicals

- 4.3.3.1 Regulatory Requirements**
- 4.3.3.2 Organizational Compliance Responsibilities**
- 4.3.3.3 Compliance Actions**
- 4.3.3.4 References**

4.3.4 Reporting of Health Effects Information

- 4.3.4.1 Regulatory Requirements**
- 4.3.4.2 Organizational/Personnel Compliance Responsibilities**
- 4.3.4.3 Compliance Actions**

4.4 Federal Insecticide, Fungicide and Rodenticide Act (FIFRA)

- 4.4.1 Site Program Overview**
- 4.4.2 Regulatory Requirements**
- 4.4.3 Organizational Responsibilities**
- 4.4.4 Compliance Actions**

4.5 Resource Requirements

5.0 LAND USE AND WILDLIFE PROTECTION PROGRAM

Contents

5.1 Overview

- 5.1.1 Introduction**
- 5.1.2 Summary**

5.2 Policy

- 5.2.1 Policy Statement**
- 5.2.2 Background for Policy Statement**

5.3 Existing Conditions

5.4 Objectives

5.5 Strategy

5.6 Implementation

5.6.1 Land Use

- 5.6.1.1 Site Program Overview**
- 5.6.1.2 Justification/Regulatory Requirements**
- 5.6.1.3 Organizational Responsibilities Summary**
- 5.6.1.4 Programs**
- 5.6.1.5 Research/Studies**

5.6.2 Endangered Species

- 5.6.2.1 Site Program Overview**
- 5.6.2.2 Justification/Regulatory Requirements**
- 5.6.2.3 Organizational Responsibilities Summary**
- 5.6.2.4 Management Programs**
- 5.6.2.5 Research/Studies**

5.6.3 Other Wildlife

- 5.6.3.1 Site Program Overview**
- 5.6.3.2 Justification/Regulatory Requirements**
- 5.6.3.3 Organizational Responsibilities Summary**
- 5.6.3.4 Management Program**
- 5.6.3.5 Research/Studies**

5.6.4 Wildlife Habitat

- 5.6.4.1 Site Program Overview**
- 5.6.4.2 Regulatory Requirements**
- 5.6.4.3 Organizational Responsibilities Summary**
- 5.6.4.4 Research/Studies**

5.6.5 Land Reclamation and Erosion Control

- 5.6.5.1 Site Program Overview**
- 5.6.5.2 Justification/Regulatory Requirements**

- 5.6.5.3 Organizational Responsibilities Summary
- 5.6.5.4 Programs

5.7 Resource Requirements

5.8 References

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

Contents

6.1 Overview

- 6.1.1 Introduction
- 6.1.2 Summary

6.2 Policy

- 6.2.1 Policy Statement
- 6.2.2 Background for Policy Statement

6.3 Existing Conditions

6.4 Objectives

6.5 Strategy

6.6 Implementation

Resource Management

- 6.6.1 Groundwater Consumption
 - 6.6.1.1 Site Program Overview
 - 6.6.1.2 Regulatory Requirements
 - 6.6.1.3 Organizational Responsibilities
 - 6.6.1.4 Programs
 - 6.6.1.5 Monitoring and Compliance

6.6.2 Hydrogeological Regime Analysis

- 6.6.2.1 Site Program Overview
- 6.6.2.2 Regulatory Requirements
- 6.6.2.3 Organizational Responsibilities
- 6.6.2.4 Programs
- 6.6.2.5 Research/Studies

6.6.3 Groundwater Monitoring

- 6.6.3.1 Site Program Overview
- 6.6.3.2 Regulating Requirements
- 6.6.3.3 Organizational Responsibilities
- 6.6.3.4 Programs

6.6.4 Water Conservation

- 6.6.4.1 Site Program Overview
- 6.6.4.2 Regulatory Requirements/Justification
- 6.6.4.3 Organizational Responsibilities
- 6.6.4.4 Programs
- 6.6.4.5 Construction Projects

Waste Management and Disposal Practices

6.6.5 Waste Management and Disposal Practices

- 6.6.5.1 Site Program Overview
- 6.6.5.2 Regulatory Requirements
- 6.6.5.3 Organizational Responsibilities
- 6.6.5.4 Waste Management Objectives and Strategy
- 6.6.5.5 Waste Generation
- 6.6.5.6 RCRA Permitting Activities
- 6.6.5.7 Current Facilities Operations
- 6.6.5.8 Construction Projects
- 6.6.5.9 Research/Studies

6.6.6 Waste Minimization

- 6.6.6.1 Site Program Overview
- 6.6.6.2 Regulatory Requirements/Justification
- 6.6.6.3 Organizational Responsibilities

- 6.6.6.4 Definitions
- 6.6.6.5 Strategy
- 6.6.6.6 Programs/Studies

6.6.7 Waste Site Closure/Remedial Action

- 6.6.7.1 Site Program Overview
- 6.6.7.2 Regulatory Requirements
- 6.6.7.3 Organizational Responsibilities
- 6.6.7.4 Closure/Remedial Action Strategy
- 6.6.7.5 RCRA Part B/RFI Activities
- 6.6.7.6 Programs
- 6.6.7.7 Research/Studies
- 6.6.7.8 Resource Requirements

Facilities Operations

6.6.8 Contamination Prevention

- 6.6.8.1 Site Program Overview
- 6.6.8.2 Regulatory Requirements
- 6.6.8.3 Organizational Responsibilities
- 6.6.8.4 Programs
- 6.6.8.5 Facility Operation
- 6.6.8.6 Construction Projects
- 6.6.8.7 Monitoring/Surveillance

6.6.9 Contamination Detection

- 6.6.9.1 Site Program Overview
- 6.6.9.2 Regulatory Requirements
- 6.6.9.3 Organizational Responsibilities Summary
- 6.6.9.4 Programs
- 6.6.9.5 Monitoring/Surveillance

6.7 Resource Requirements

6.8 References

7.0 ATMOSPHERIC PROTECTION PROGRAM

Contents

7.1 Overview

- 7.1.1 Introduction
- 7.1.2 Summary

7.2 Policy

- 7.2.1 Policy Statement
- 7.2.2 Background for Policy Statement

7.3 Existing Conditions

7.4 Objectives

7.5 Strategy

7.6 Implementation

7.6.1 Air Emissions Permitting

- 7.6.1.1 Site Program Overview
- 7.6.1.2 Regulatory Requirements
- 7.6.1.3 Organizational Responsibilities
- 7.6.1.4 Programs
- 7.6.1.5 Construction/Modification Projects
- 7.6.1.6 Research/Studies

7.6.2 Air Quality Assessments

- 7.6.2.1 Site Program Overview
- 7.6.2.2 Regulatory Requirements
- 7.6.2.3 Organizational Responsibilities
- 7.6.2.4 Programs
- 7.6.2.5 Research/Studies

7.6.3 Nonradioactive Emissions Management

- 7.6.3.1 Site Program Overview
- 7.6.3.2 Regulatory Requirements
- 7.6.3.3 Organizational Responsibilities Summary

-
-
- 7.6.3.4 Programs
 - 7.6.3.5 Facility Operations
 - 7.6.3.6 Construction/Modification Projects
 - 7.6.3.7 Research/Studies
 - 7.6.3.8 Monitoring
 - 7.6.4 Radioactive Emissions Management
 - 7.6.4.1 Site Program Overview
 - 7.6.4.2 Regulatory Requirements
 - 7.6.4.3 Organizational Responsibilities Summary
 - 7.6.4.4 Programs
 - 7.6.4.5 Facility Operations
 - 7.6.4.6 Construction/Modifications
 - 7.6.4.7 Research/Studies
 - 7.6.4.8 Monitoring
 - 7.6.5 Emergency Response
 - 7.6.5.1 Site Program Overview
 - 7.6.5.2 Regulatory Requirements
 - 7.6.5.3 Organizational Responsibilities Summary
 - 7.6.5.4 Programs
 - 7.6.5.5 Facility Operations
 - 7.6.5.6 Construction/Modifications
 - 7.6.5.7 Research/Studies
 - 7.6.5.8 Monitoring

7.7 Resource Requirements

7.8 References

Attachment 7.1--Air Quality Operating and Construction Permits

8.0 DECONTAMINATION AND DECOMMISSIONING PROGRAM

Contents

8.1 Overview

- 8.1.1 Introduction
- 8.1.2 Summary

8.2 Policy

- 8.2.1 Policy Statement
- 8.2.2 Background for Policy Statement

8.3 Existing Conditions

8.4 Objectives

8.5 Strategy

8.6 Implementation

8.6.1 Site D&D Plan

- 8.6.1.1 Site Program Overview
- 8.6.1.2 Justification/Regulatory Requirements
- 8.6.1.3 Organizational Responsibilities Summary
- 8.6.1.4 Programs

8.6.2 Tank 16 Demonstration

- 8.6.2.1 Site Program Overview
- 8.6.2.2 Justification/Regulatory Requirements
- 8.6.2.3 Organizational Responsibilities Summary
- 8.6.2.4 Programs
- 8.6.2.5 Projects
- 8.6.2.6 Research/Studies

8.6.3 Heavy Water Components Test Reactor (HWCTR)

- 8.6.3.1 Site Program Overview
- 8.6.3.2 Justification/Regulatory Requirements
- 8.6.3.3 Organizational Responsibilities Summary
- 8.6.3.4 Programs

8.6.4 HB-Line Decommissioning

- 8.6.4.1 Site Program Overview
- 8.6.4.2 Justification/Regulatory Requirements
- 8.6.4.3 Organizational Responsibilities Summary
- 8.6.4.4 Programs

8.6.5 Other Decontamination and Decommissioning

- 8.6.5.1 232-F Tritium Facility
- 8.6.5.2 284-F Powerhouse
- 8.6.5.3 412-D Heavy Water Facility
- 8.6.5.4 Decommission SRL SED I Facility
- 8.6.5.5 Decommission SRL SED II Facility
- 8.6.5.6 Decommission SRL CPF Facility
- 8.6.5.7 R Reactor Support Facilities

8.7 Resource Requirements

8.8 References

LIST OF TABLES

2.0 Site Description

Table 2.1	Summary of SRS Area Names and Letter/Number Designations
-----------	--

3.0 Surface Waters and Wetlands Protection

Table 3.7.1	Manpower Requirements Schedule
Table 3.7.2	Operating Budget Schedule
Table 3.7.3	Capital Budget Schedule
Table 3.7.4	Total Expenditure Schedule

4.0 Safe Drinking Water and Other Compliance Problems

Table 4.5.1	Manpower Requirements Schedule
Table 4.5.2	Operating Budget Schedule
Table 4.5.3	Capital Budget Schedule
Table 4.5.4	Total Expenditure Schedule

5.0 Land Use and Wildlife Protection

Table 5.7.1	Manpower Requirements Schedule
Table 5.7.2	Operating Budget Schedule
Table 5.7.3	Total Expenditure Schedule

6.0 Groundwater Protection and Waste Management

Table 6.6.5.1	Waste Generation Forecast
Table 6.6.7.1	Organizational Responsibility Summary Table
Table 6.6.9.1	Underground Storage Tanks
Table 6.7.1	Groundwater Protection Manpower Requirements Schedule
Table 6.7.2	Groundwater Protection Operating Budget Schedule
Table 6.7.3	Groundwater Protection Capital Budget Schedule
Table 6.7.4	Groundwater Protection Total Expenditure Schedule
Table 6.7.5	Waste Management Manpower Requirements Schedule
Table 6.7.6	Waste Management Operating Budget Schedule
Table 6.7.7	Waste Management Capital Budget Schedule
Table 6.7.8	Waste Management Total Expenditure Schedule

Table 6.7.9	Waste Site Closure Manpower Requirements Schedule
Table 6.7.10	Waste Site Closure Operating Budget Schedule
Table 6.7.11	Waste Site Closure Capital Budget Schedule
Table 6.7.12	Waste Site Closure Total Expenditure Schedule
Table 6.7.13	Underground Storage Tanks Manpower Requirements Schedule
Table 6.7.14	Underground Storage Tanks Operating Budget Schedule
Table 6.7.15	Underground Storage Tanks Total Expenditure Schedule

7.0 Atmospheric Protection

Table 7.7.1	Manpower Requirements Schedule
Table 7.7.2	Operating Budget Schedule
Table 7.7.3	Capital Budget Schedule
Table 7.7.4	Total Expenditure Schedule

8.0 Decontamination and Decommissioning

Table 8.7.1	Manpower Requirements Schedule
Table 8.7.2	Operating Budget Schedule
Table 8.7.3	Capital Budget Schedule
Table 8.7.4	Total Expenditure Schedule

10.0 Environmental Auditing and Appraisal

Table 10.7.1	Manpower Requirements Schedule
Table 10.7.2	Operating Budget Schedule
Table 10.7.3	Total Expenditure Schedule

11.0 Employee Education

Table 11.1	Regulations Citing Specific Training Requirements
Table 11.2	Regulations Citing No Specific Training Requirements
Table 11.3	Training Activities Cited by Federal Regulations
Table 11.4	Training Activities Cited by State Regulations
Table 11.5	Training Activities Cited by DOE Orders
Table 11.7.1	Manpower Requirements Schedule
Table 11.7.2	Operating Budget Schedule
Table 11.7.3	Total Expenditure Schedule

12.0 Community Outreach and Emergency

Table 12.7.1	Manpower Requirements Schedule
Table 12.7.2	Operating Budget Schedule
Table 12.7.3	Total Expenditure Schedule

13.0 Environmental Compliance Tracking and Data Management

Table 13.7.1	Manpower Requirements Schedule
Table 13.7.2	Operating Budget Schedule
Table 13.7.3	Capital Budget Schedule
Table 13.7.4	Total Expenditure Schedule

14.0 Resource Requirements

Table 14.1	Manpower Requirements Schedule
Table 14.2	Operating Budget Schedule
Table 14.3	Capital Budget Schedule
Table 14.4	Total Expenditure Schedule

1.0 Introduction

Figure 1-1. Structure of the Environmental Implementation Plan

2.0 Site Description

Figure 2-1. Location of the Savannah River Site

Figure 2-2. The Nuclear Fuel Cycle at the Savannah River

Figure 2-3. Savannah River Site - Location of Areas

Figure 2-4. 300-M and 700-A Areas

Figure 2-5. 100-C Area

Figure 2-6. 100-K Area

Figure 2-7. 100-L Area

Figure 2-8. 100-P Area

Figure 2-9. 200-H Area

Figure 2-10. 200-F Area

Figure 2-11. 200-F , 200-H, and Burial Ground Area

Figure 2-12. 400-D Area

Figure 2-13. Central Shops Area

Figure 2-14. 600-T Area (TNX)

Figure 2-15. 700-B/U Area

Figure 2-16. 200-S Area

Figure 2-17. 200-Z Area

3.0 Surface Waters And Wetlands Protection

Figure 3.5-1. Surface Waters and Wetlands Protection Program Strategy

5.0 Land Use and Wildlife Protection

Figure 5.5-1. Land Use and Wildlife Protection Program Strategy

6.0 Groundwater Protection and Waste Management

Figure 6.5-1. Groundwater Protection and Waste Management Program Strategy

Figure 6.6.5-1. Savannah River Site Waste management Plan (Overview)

Figure 6.6.5-2. Nonradioactive Nonhazardous Waste Management Plan

Figure 6.6.5-3. Nonradioactive Hazardous Waste Management Plan

Figure 6.6.5-4. Mixed Waste Management Plan

Figure 6.6.5-5. Low-Level and Intermediate-Level Waste Management Plan

Figure 6.6.5-6. Transuranic Waste Management Plan

Figure 6.6.5-7. High-Level Radioactive Waste Management Plan

Figure 6.6.5-8. Tritiated Waste Management Plan

Figure 6.6.5-9. Depleted Uranium Waste Management Plan.

Figure 6.6.5-10. M Area Liquid Effluent Treatment Facility Waste Management Plan

Figure 6.6.5-11. F and H Area Liquid Effluent Treatment Facility Waste Management Plan

Figure 6.6.5-12. SRS Saltstone Disposal Plan

Figure 6.6.7-1. Waste Site Closure Pathway

Figure 6.6.7-2. Waste Site Closures with RCRA Facility Investigations (RFI)

7.0 Atmospheric Protection

Figure 7.5.1. Atmospheric Protection Program Strategy

8.0 Decontamination and Decommissioning

Figure 8.5.1. Decontamination and Decommissioning Program Strategy

10.0 Environmental Auditing and Appraisal

Figure 10.5-1. Environmental Auditing and Appraisal Program Strategy

11.0 Employee Education

Figure 11.5-1. Employee Education Program Strategy

12.0 Community Outreach and Emergency Preparedness

Figure 12.5-1. Community Outreach and Emergency Preparedness Program Strategy

13.0 Environmental Compliance Tracking and Data Management

Figure 13.5-1. Environmental Compliance Tracking and Data Management Program Strategy

LIST OF ACRONYMS

AEA	Atomic Energy Act
ALARA	As Low As Reasonably Achievable
ANSP	Academy of Natural Sciences of Philadelphia
BBC	Balanced Biological Community
BGI	Beta Gamma Incinerator
BMP	Best Management Practices Plan
CAA	Clean Air Act
CCWS	Comprehensive Cooling Water Study
CEQ	Council of Environmental Quality
CERCLA	Comprehensive Environmental Response Compensation and Liability Act
CFR	Code of Federal Regulations
CI	Curie
CIF	Consolidated Incineration Facility
CWA	Clean Water Act, or Water Quality Act of 1987
D&D	Decontamination and Decommissioning
DETF	Dilute Effluent Treatment Facility (M Area)
DOE	U. S. Department of Energy
DOE-SR	Department of Energy Savannah River
DWPF	Defense Waste Processing Facility
EA	Environmental Assessment
EID	Environmental Information Document

EIP	Environmental Implementation Plan
EIS	Environmental Impact Statement
ELLT	Engineered Low-Level Trench
EOC	Emergency Operating Center
EPA	Environmental Protection Agency
ESA	Endangered Species Act
ETF	Effluent Treatment Facility (F/H Area)
ETP	Effluent Treatment Plant (TNX Area)
ETWAF	Experimental Transuranic Waste Assay Facility
FIFRA	Federal Insecticide, Fungicide, Rodenticide Act
FWS or USFWS	U. S. Fish and Wildlife Service
GCD	Greater Confinement Disposal
GMP	Groundwater Monitoring Program
HEPA Filter	High Efficiency Particulate Air Filter
HLW	High-Level Waste
HP	Health Protection or Health Physics
ILW	Intermediate-Level Waste
L	Liter
LETF	Liquid Effluent Treatment Facility (M Area)
LLW	Low-Level Waste
LR	Local Roll Wage Scale
mL	Milliliter

MPSA	Marine Protection and Sanctuaries Act
mrem	millirem
MTF	Memorandum-to-File
MWF	Mixed Waste Facilities
MWMF	Mixed Waste Management Facility
MWSB	Mixed Waste Storage Building
nCi	Nanocuri
NEPA	National Environmental Policy Act
NERP	National Environmental Research Park
NESHAP	National Emission Standards for Hazardous Air Pollutants
NHPA	National Historic Preservation Act
NMFS	National Marine Fisheries Service
NO _x	Oxides of Nitrogen
NPDES	National Pollutant Discharge Elimination System
NPR	New Production Reactor
NRC	Nuclear Regulatory Commission
ORF	Organics Removal Facility
OSHA	Occupational Safety and Health Act
PCB	Polychlorinated Biphenyl
pCi	Picocurie
RCRA	Resource Conservation and Recovery Act

rem	Roentgen
RFI	RCRA Facility Investigation
SARA	Superfund Amendments and Reauthorization Act (amending CERCLA)
SCBCESO	S. C. Board of Certification of Environmental Systems Operators
SCDHEC	S. C. Department of Health and Environmental Systems Operators
SCDWR	S. C. Drinking Water Regulations
SCHWMR	S. C. Hazardous Waste Management Regulations
SCPCA	S. C. Pollution Control Act
SCWMRD	S. C. Wildlife and Marine Resources Department
SDWA	Safe Drinking Water Act
SEFES	Southeastern Forest Experiment Station of the U. S. Forest Service
SFMP	Surplus Facilities Management Program
SGWC	Site Groundwater Coordinator
SMARTS Program	Specifications and Management Applications for Regulated Tank Systems Program
SPCC	Spill Prevention Control and Countermeasures Plan
SREL	Savannah River Ecology Laboratory
SRFS	Savannah River Forest Station of the the U. S. Forest Service
SRS	Savannah River Site
SWTP	Sanitary Waste Treatment Plant

TRC	Total Residual Chlorine
TRU	Transuranic Waste
TSCA	Toxic Substances Control Act
U.S.C.	U. S. Code of Laws
USFS	U. S. Forest Service
UTRC	Upper Three Runs Creek
WCF	Waste Certification Facility
WSCTF	Waste Site Closure Tank Force
WSRC	Westinghouse Savannah River Company

LIST OF DOE ORDERS APPLICABLE

<u>Order Number</u>	<u>Title</u>	<u>Revision Date</u>
4300.1B	Real Property and Site Development Planning	7/87
5400.1	General Environmental Protection Program	11/88
5400.3	Hazardous & Rad. Mixed Waste Program	2/22/89
5440.1C	National Environmental Policy Act	4/85
5480.1B	ES&H Program for DOE Operations	9/86
5480.2	Hazardous and Rad. Mixed Waste Mgmt.	12/82
5480.3	Safety Requirements for Packaging & Transportation of Hazardous Materials, Hazardous Substances & Hazardous Waste	7/85
5480.4	ES&H Protection Standards	5/84
5480.5	Safety of Nuclear Facilities	9/86
5480.6	Safety of DOE-Owned Nuclear Reactors	9/86
5480.7	Fire Protection	11/87
5480.11	Radiation Protection for Occupational Workers	12/88
5480.13	Aviation Safety	5/81
5480.14	CERCLA Program	4/85
5480.16	Firearms Safety	1/86
5480.17	Site Safety Representatives	10/88
5481.1B	Safety Analysis & Review System	9/86
5482.1B	ES&H Appraisal Program	9/86
5483.1A	OSHA Programs at GOCO Facilities	6/83
5484.1	ES&H Information Reporting Requirements	2/81
5500.1A	Emergency Management System	2/87
5500.3	Reactor & Nonreactor Nuclear Facility Emergency Planning, Preparedness & Response Program for DOE Operations	8/81
5700.6B	Quality Assurance	9/86
5820.2A	Radioactive Waste Management	9/88

APPLICABLE LAWS AND ADMINISTRATIVE REQUIREMENTS BY CHAPTER

SURFACE WATERS AND WETLANDS PROTECTION

DOE Order 5480.4A, SR Order 5480.4A (Radiation Standards for Protection of the Public)

Federal Water Pollution Control Act (Water Quality Act of 1987, also known as the Clean Water Act), Sections 316a & b (thermal mitigation), 402 (NPDES), 304 (control of runoff, spillage, and leakage of hazardous and toxic pollutants), 404 (Dredge and Fill)

S. C. Water Classification Standards (SCDHEC 61068)

S. C. Consent Order-84-4-W (Thermal Mitigation)

S. C. Pollution Control Act

S. C. NPDES Permit

Executive Orders 11988, 11990, and 12088 (floodplains/wetlands and pollution control)

Aiken County, SC Ordinance 74-100-37 (Sediment Control)

SAFE DRINKING WATER AND OTHER COMPLIANCE PROGRAMS

Safe Drinking Water Act of 1974, as amended

S. C. Primary Drinking Water Regulations (SCDHEC 61-58 includes
S. C. Industrial Water Supplies Regulations)

National Environmental Policy Act (NEPA)

Council on Environmental Quality (CEQ) NEPA Implementing Regulations 40
CFR 1500-1508

DOE Order 5440.1C

DOE Regulations, Compliance with NEPA (45 FR 20664, 45 FR 20694, 47 FR
7976)

Toxic Substances Control Act (TSCA) of 1977, as amended, Section 6 (PCB's), Section 5(a) (Premanufacturing Notification), Section 8(c) and 8(e) (reporting of health effects information), and Section 5(a)(2) (reporting uses of existing chemicals)

Federal Insecticide, Fungicide and Rodenticide Act (FIFRA), as amended

S. C. Pesticide Control Act (R. 27-1072 ff)

LAND USE AND WILDLIFE PROTECTION PROGRAM

DOE Order 4300.1B, Real Property and Site Development Planning (7-1-87)

SR Order SR-430X.1, Site Use Coordination and Approval (9-13-83)

Savannah River Operations Office Fish and Wildlife Management Policy for the Savannah River Plant (SR-86-35) (6-18-86)

Endangered Species Act of 1973

S. C. Nongame and Endangered Species Act

National Environmental Policy Act

S. C. Water Classification Standards (SCDHEC 61-88)

GROUNDWATER PROTECTION AND WASTE MANAGEMENT PROGRAM

Safe Drinking Water Act (requirements for installation and maintenance of wells used for potable water)

Resource Conservation and Recovery Act (RCRA) and implementing regulations (40 CFR 260-280)/Hazardous and Solid Waste Amendments of 1984 (HSWA)

Comprehensive Environmental Response Compensation and Liability Act/Super-fund Amendments and Reauthorization Act (CERCLA/SARA)

Toxic Substances Control Act (TSCA) (PCBs)

National Emission Standards for Hazardous Air Pollutants (NESHAP)

Public Law 98-181 (required discontinuance of use of the M-Area Settling Basin by 11/85, development and submittal of a groundwater protection plan to Congress)

S. C. Water Use Reporting and Coordination Act (requires quarterly reporting of use, withdrawal or diversion of surface, underground and other waters of the State to SCWRC)

S. C. Regulation R. 61-71, Well Standards and Regulations (construction of wells, including water supply, piezometers and monitoring wells)

S. C. Solid Waste Regulation, R.61-61

S. C. Industrial Solid Waste Disposal Site Regulation, R. 61-66

S. C. Landfill Regulation, R. 61-70

S. C. Hazardous Waste Management Facilities Regulation, R. 61-79.264

S. C. Consent Order 85-70-SW (11/7/85, requires additional groundwater monitoring for basins in M, F, and H Areas)

S. C. Settlement Agreement 86-52-W (11/20/86, requires periodic groundwater quality assessments at several sites and a biennial update of the Technical Summary of the Groundwater Quality Protection Program)

DOE Order 5400.3, Hazardous and Radioactive Mixed Waste Management

DOE Order 5820.2A, Radioactive Waste Management

DOE Order 5480.3, Safety Requirements for Packaging & Transportation of Hazardous Materials, Hazardous Substances & Hazardous Waste

DOE Order 5480.14, CERCLA Program

ATMOSPHERIC PROTECTION

Clean Air Act (National Primary and Secondary Ambient Air Quality Standards - 40 CFR 50, Standards of Performance of New Stationary Sources - 40 CFR 60, Prevention of Significant Deterioration Standards - 40 CFR 52, and National Emission Standards for Hazardous Air Pollutants - 40 CFR 61)

S. C. Pollution Control Act

S. C. Air Pollution Control Regulations (SCDHEC 61-62)

S. C. Ambient Air Quality Standards (SCDHEC 61-62.5)

S. C. Standards of Performance for Asbestos Removal Operations (SCDHEC 61-86.1)

DOE Order 5480.1B, ES&H Program for DOE Operations

DECONTAMINATION & DECOMMISSIONING PROGRAM

DOE Order 5820.2, Radioactive Waste Management

ENVIRONMENTAL APPRAISAL PROGRAM

DOE Order 5482.1B, ES&H Appraisal Program

EMPLOYEE EDUCATION

Employee Training requirements cited in numerous federal and state laws:

Clean Water Act

Comprehensive Environmental Response Compensation and Liability Act

Superfund Amendment and Reauthorization Act

Federal Insecticide, Fungicide, and Rodenticide Act (certification)

Hazardous Materials Transportation Act

Occupational Safety and Health Act

Resource Conservation and Recovery Act

Safe Drinking Water Act (certification)

Toxic Substances Control Act

S. C. Board of Certification of Environmental Systems Operators

S. C. Drinking Water Regulations

S. C. Hazardous Waste Management Regulations

S. C. Pollution Control Act

DOE Order 1540.2, Hazardous Materials Packaging for Transport,
Administrative Procedures

DOE Order 5400.3, Hazardous and Radioactive Mixed Waste Management

DOE Order 5480.3, Safety Requirements for Packaging and Transportation of
Hazardous Materials, Hazardous Substances and Hazardous Wastes

DOE Order 5480.3, Safety Requirements for Packaging and Transportation of
Hazardous Materials, Hazardous Substances and Hazardous Wastes
DOE Order 5500.2, Emergency Planning, Preparedness, and Response for
Operations
DOE Order 5820.2A, Radioactive Waste Management
DOE Order 5400.1, General Environmental Protection Program

COMMUNITY OUTREACH AND EMERGENCY PLANNING

DOE Order 5400.1, General Environmental Protection Program
DOE Order 5484.1, ES&H Information Reporting Requirements
Superfund Amendments and Reauthorization Act (SARA) Title III

1.0 INTRODUCTION

1.1 Background

The *Environmental Implementation Plan* (EIP) is the comprehensive environmental master plan for the operating contractor's organizations at the Savannah River Site (SRS). The EIP ensures that all environmental requirements and obligations are met by setting specific measurable objectives. The plan provides justification for site manpower and funding requests over the five-year planning period.

The EIP is the central plan for environmental activities at the SRS. All operating contractor organizations that are located on or serve the site are included and have approved the plan. The plan does not address occupational health or safety issues with the exception of drinking water systems and asbestos removal. Radiological emergency response planning is also outside the scope of the EIP as are reactor safety issues. Safety and health issues are addressed in DPSP-89-1021, *Safety and Health Long Range Plan - Savannah River Plant and Laboratory*. The EIP is not intended to be a Department of Energy Savannah River Operations Office (DOE-SR) environmental plan, but it is designed to complement environmental planning efforts of DOE-SR or the other site contractors.

The EIP is written primarily for operating contractor management and environmental professionals. It will also be useful to the DOE-SR Environmental Division and to the environmental coordinators of other site contractors. The plan is designed to be a practical and useful document. The level of detail is limited to that needed to describe activities at the project and section program level. The entire plan shall be updated annually.

1.2 Document Organization

The EIP comprises three volumes. The first volume is an Executive Summary designed for operating contractor management which identifies the significant environmental issues and the manpower and funding needed to meet the site's environmental obligations. The second volume contains the Environmental Protection Programs. These are the programs and projects that directly protect the environment from plant operations. The third volume contains the Management and Support Programs. These programs respond

to regulatory requirements in some cases, but also support good environmental practices. The overall structure of the plan is shown in Figure 1-1.

Volumes II and III, Environmental Protection Programs, and Management and Support Programs, are the key portions of the EIP. The Environmental Protection Programs volume is divided into media areas which include air, surface waters and wetlands, groundwater protection and waste management, and wildlife and land use. In addition, safe drinking water and other compliance programs, and decontamination and decommissioning are a part of this volume.

The Management and Support Programs volume is divided into program areas which include resource requirements, community outreach/emergency planning relating to Superfund Amendments and Reauthorization Act (SARA) Title III, organizational responsibility, regulatory and DOE order compliance, employee education, and auditing and appraisals.

Each of the media and program areas is designed to follow a similar format. The first section is a brief summary of the media/program area. This is followed by a media policy statement or a program purpose statement. The third section defines the existing condition of a media or state of a program. The fourth section contains the objectives that must be met to satisfy the policy/purpose statement. A brief strategy section follows which highlights the basic approach for reaching the objectives. The implementation section defines the major issue/topic within the media/program area. For each issue/topic the justification, responsible organization, major milestones, capital and operating costs, and manpower requirements are identified for the five-year planning period. The resource requirements section summarizes the cost and manpower requirements of the media/program area. The final section contains references.

2.0 SITE DESCRIPTION

The Savannah River Site (SRS) produces nuclear materials, primarily tritium and plutonium, for national defense. Constructed in the early 1950s, this installation near Aiken, South Carolina, is owned by the U.S. Department of Energy and operated by an operating contractor.

The SRS is located in south central South Carolina and occupies an almost circular area of approximately 325 square miles. The major geophysical feature is the Savannah River, which forms the southwestern boundary of the plant and is also the South Carolina-Georgia border. The SRS occupies parts of three South Carolina counties—Aiken, Barnwell, and Allendale—and is closest to the major population centers of Augusta, Georgia, and Aiken, South Carolina (see Figure 2-1). The plant is a controlled area with limited public access. The production facilities occupy less than 5 percent of the SRS area. The remainder of the site is forested (approximately 95 percent) or is wetlands.

The SRS produces nuclear materials by manufacturing fuel and target components, irradiating the components in nuclear reactors, chemically extracting the desired nuclear materials from the irradiated fuel and targets, separating radioactive waste, and solidifying the radioactive wastes in glass for final offsite geological disposal. Figure 2-2 is a simplified materials flow diagram of the site. The site also produces fuel for the U.S. Navy's nuclear fleet in a newly constructed facility.

The SRS comprises 18 production, service, and research and development areas scattered across the 325-square-mile site. Figure 2-3 shows the locations of these areas. Each area is identified by a numerical and letter designation. Table 2.1 summarizes the letter designations.

The primary facilities are the production facilities. The fuel and target components are manufactured in the 300-M Area for shipment to the site reactors. The targets and fuel are placed in heavy-water-moderated production reactors for irradiation. Originally the site operated five reactors. Currently, three of the reactors, located in the 100-P, K, and L Areas, are operational. The other two reactors, in the 100-C and R Areas, are in cold standby and shutdown status, respectively. The SRS reactors operate at relatively low temperatures and pressures, and they do not produce electricity. The reactors are cooled by a heavy-water moderator, which is then circulated through heat exchangers in a closed loop. Inside the heat exchangers, water withdrawn from the Savannah River and onsite cooling reservoirs is used to remove heat from the heavy water without contacting it. The heavy water is then recirculated through the reactor vessel, and river water is released through an outfall to onsite streams or cooling ponds before returning to the river. The irradiated fuel is

transported by shielded railroad cars to either the 200-F or H Area for the recovery of nuclear materials. The 200-F and H separations processes dissolve some of the irradiated components in acid, and extract and separate the desired nuclear materials. Other products are extracted from irradiated components in separate processes in H Area. The liquid radioactive waste generated by the separation facilities is neutralized and stored in one-million-gallon underground tanks until it can be processed in the Defense Waste Processing Facility, currently under construction in the 200-S and Z Areas. The glass wasteform will be stored onsite until a geological repository is available in the late 1990s. The nuclear material products are shipped to other Department of Energy (DOE) facilities for additional processing. The reactor, separations, and waste storage areas are at least four miles from the nearest plant boundary.

The site also contains many production support, research and development, and waste management facilities. There are five coal-fired powerhouses located in various production areas to generate electricity and steam. The largest powerhouse, which is located in the 400-D Area, produces electricity and exports process steam to C, F, H, and S Area through a seven-mile-long steam line. The heavy-water rework facility used to purify reactor moderator is also located in D Area. A semi-works facility used to study chemical and waste processing problems and to test production scale equipment is located near the Savannah River in the 600-T Area. B Area houses the site security contractor, Wackenhut Services Incorporated (WSI). The 700-A Area includes the administrative facilities for DOE and the operating contractor, the Savannah River Laboratory (SRL), and the University of Georgia Savannah River Ecology Laboratory (SREL). The Naval Reactor Fuel Material Facility, which will produce fuel for the Navy's nuclear-powered fleet, is located in F Area. In addition to the underground radioactive waste storage tanks, the SRS has a centrally located 200-acre site between F and H Areas for the disposal of solid low-level radioactive waste and the storage of transuranic (TRU) radioactive waste and mixed waste. The site also has storage buildings for nonradioactive hazardous wastes located in the Central Shops and U Areas along with a central sanitary landfill.

The SRS forests are managed by the U.S. Forest Service (USFS), which also conducts some research activities at the site. The SRS, which was designated a National Environmental Research Park (NERP) in 1972, is one of the most intensively studied environments in the country. A variety of plants (150 families and 1097 species) are located on the site. Typically scrub oak and longleaf pines cover in the drier sandy areas; and oak-hickory hardwoods and loblolly pines are prevalent on the more fertile, dry upland (Dukes, 1984). There is also an abundance of wildlife. Site species include 31 snakes, 26 frogs and toads, 17 salamanders, 10 turtles, nine lizards, and alligators (Dukes, 1984). There are over 213 species of birds, over 400 species of algae and eight species of plants in the Savannah River,

and 66 adult fish species in the Savannah River and its associated swamp and tributaries.

Some species listed as endangered by the U.S. Fish and Wildlife Service inhabit the site or the immediate vicinity include the red-cockaded woodpecker, the bald eagle, the wood stork, the shortnose sturgeon, the brother spike mussel, and the smooth coneflower. The American alligator is no longer listed as an endangered species, but it is listed as threatened. Besides research conducted by the USFS through the NERP, the Academy of Natural Sciences of Philadelphia, SRL, and SREL conduct a variety of studies related to the characteristics of the Savannah River and SRS, and the vegetation and wildlife.

The site employs more than 18,000 people. About 97 percent are employed by the operating contractor and its subcontractors. The remainder are employed by the DOE, WSI, SREL, and the USFS.

Within the operating contractor, environmental protection and regulatory compliance are line organization responsibilities. Each department is responsible for the facilities it operates.

A brief summary of department operations follows. The Raw Materials and Tritium Department is the custodian of the M Area fuel and target production facilities, the M Area Liquid Effluent Treatment Facility, and the A/M Area groundwater remediation facilities. The Separations Department is custodian of the 221-F and H Canyon buildings and associated facilities in F and H Areas. The Waste Management Department operates the high-level radioactive waste disposal facility, the TRU waste storage facilities, the hazardous and mixed waste storage buildings, the sanitary landfill, the Defense Waste Processing Facility (DWPF) under construction in S and Z Areas, and the F/H Effluent Treatment Facility in H Area. The Naval Fuel Department is custodian of the Naval Fuel Reactor Material Facility in F Area. The Power Operations Department operates the powerhouses in all areas; the sanitary treatment plants in all areas with the exception of DWPF and Naval Fuel; the drinking, process, and cooling water systems in all areas, the Savannah River and Par Pond pumphouses, Par Pond and L Lake cooling reservoirs; and the site electrical distribution system. Central Services Works Engineering is the custodian of the site roads, grounds, railroad, and rolling stock. SRL is custodian of various A Area laboratories and the T Area semi-works (TNX).

A more detailed explanation of departmental environmental responsibilities can be found in the Organizational Responsibilities section of Volume III. Area maps designating specific facilities are shown in Figures 2-4 through 2-17.

Table 2.1

SUMMARY OF SRS AREA NAMES AND LETTER/NUMBER DESIGNATIONS

Nuclear Production Reactors	100-C Area 100-K Area 100-L Area 100-P Area 100-R Area	Irradiates fuel and target elements for production of nuclear materials.
Chemical Separation Facilities	200-F Area 200-H Area	Chemically separates and processes the irradiated materials from the reactors. High-level radioactive wastes are also stored and processed in these areas.
Defense Waste Processing Facility (DWPF)	200-S Area 200-Z Area	Is under construction. The DWPF will process HLW into borosilicate glass wasteform for storage until final disposal in an as yet undesignated repository by DOE.
Fuel and Target Fabrication	300-M Area	Manufactures fuel and target elements for use in the Reactors.
Heavy Water Rework Facility D Area Powerhouse	400-D Area	Purifies Heavy Water for use as Reactor Moderator. Generates steam and electricity.

Table 2.1 (cont)

SUMMARY OF SRS AREA NAMES AND LETTER/NUMBER DESIGNATIONS

General Facilities and Services	600 Area	Contains LLW Disposal Facility. Includes all of SRS that is not within or functionally associated with a fenced area such as designated bridges, roads, parking lots, storage tanks, monitoring stations and towers, transformers, boats ramps, training areas, and repair shops.
TNX Semi-works Facilities	600-T Area	Is a facility to study chemical processing problems and test production-scale equipment and processes.
Administration, Technical, and Shops	700-A Area	<p>Includes SRL, performs R & D related to plant changes, improvements, upgrades and waste management.</p> <p>Is the administration area for DOE, SRS, SREL, medical facilities, automotive shops, warehouses, fire stations, powerhouse, coal storage, lumber and steel yards, and gas stations.</p>

Table 2.1 (cont)

**SUMMARY OF SRS AREA NAMES AND LETTER/NUMBER
DESIGNATIONS**

Security Services Area	700-B Area	Is the administration and service area for security contractor, WSI.
Components Test Area	700-U Area	Test reactor no longer in service. Contains the hazardous waste storage facility.
Central Shops	CS-Area	CS has a variety of functions, including equipment storage, painting, carpentry, automotive repairing, asphalt storage, blacksmithing, construction storage, concrete mixing, photo processing, structural iron working, coal sampling, and fire department training.
U.S. Forest Service	USFS Area	Includes administrative headquarters, storage, and maintenance sheds. Also offices for USC Institute of Archeology and Anthropology and Wildlife and Marine Resources Unit and for AT & T Southern Bell.

Figure 2-1. Location of the Savannah River Site

Figure 2-2. The nuclear fuel cycle at the Savannah River Site

Figure 2-3. Savannah River Site - Location of Areas

Figure 2-4. 300-M and 700-A Areas

Figure 2-5. 100-C Area

Figure 2-6. 100-K Area

Figure 2-7. 100-L Area

Figure 2-8. 100-P Area

Figure 2-9. 200-H Area

Figure 2-10. 200-F Area

Figure 2-11. 200-F, 200-H, and Burial Grounds Area

Figure 2-12. 400-D Area

The map shows the layout of the Naval Air Station, Alameda, with various facilities and storage areas. Key features include:

- Orientation and Scale:** A compass rose indicates North (N) and a scale bar shows distances in feet (0 to 1000).
- Facilities and Storage:**
 - HAZARDOUS WASTE STORAGE FACILITIES:** Located in the lower-left quadrant, including areas labeled 700-G and 700-1700.
 - SLAB STORAGE:** Multiple areas labeled SLAB STORAGE are distributed across the map, including one near the top right and another near the center right.
 - DRUM STORAGE:** Located in the center of the map.
 - PARKING LOT:** Located near the top center.
 - SEWAGE TREATMENT PLANT:** Located in the lower-right quadrant, including a SEWAGE TREATMENT POINT and a SANITARY SEWAGE SLODGE DISPOSAL PIT.
 - WATER TREATMENT:** Located in the upper-right quadrant, including a SANITARY WASTE WATER LAGOON and a SEEPAGE BASIN.
- Buildings and Structures:** Numerous buildings are labeled with numbers, including 81312A, 84918, 81312B, 8491C, 8310, 8312, 8318, 8319, 8320, 8321, 8322, 8323, 8324, 8325, 8326, 8327, 8328, 8329, 8330, 8331, 8332, 8333, 8334, 8335, 8336, 8337, 8338, 8339, 8340, 8341, 8342, 8343, 8344, 8345, 8346, 8347, 8348, 8349, 8350, 8351, 8352, 8353, 8354, 8355, 8356, 8357, 8358, 8359, 8360, 8361, 8362, 8363, 8364, 8365, 8366, 8367, 8368, 8369, 8370, 8371, 8372, 8373, 8374, 8375, 8376, 8377, 8378, 8379, 8380, 8381, 8382, 8383, 8384, 8385, 8386, 8387, 8388, 8389, 8390, 8391, 8392, 8393, 8394, 8395, 8396, 8397, 8398, 8399, 8400, 8401, 8402, 8403, 8404, 8405, 8406, 8407, 8408, 8409, 8410, 8411, 8412, 8413, 8414, 8415, 8416, 8417, 8418, 8419, 8420, 8421, 8422, 8423, 8424, 8425, 8426, 8427, 8428, 8429, 8430, 8431, 8432, 8433, 8434, 8435, 8436, 8437, 8438, 8439, 8440, 8441, 8442, 8443, 8444, 8445, 8446, 8447, 8448, 8449, 8450, 8451, 8452, 8453, 8454, 8455, 8456, 8457, 8458, 8459, 8460, 8461, 8462, 8463, 8464, 8465, 8466, 8467, 8468, 8469, 8470, 8471, 8472, 8473, 8474, 8475, 8476, 8477, 8478, 8479, 8480, 8481, 8482, 8483, 8484, 8485, 8486, 8487, 8488, 8489, 8490, 8491, 8492, 8493, 8494, 8495, 8496, 8497, 8498, 8499, 8500, 8501, 8502, 8503, 8504, 8505, 8506, 8507, 8508, 8509, 8510, 8511, 8512, 8513, 8514, 8515, 8516, 8517, 8518, 8519, 8520, 8521, 8522, 8523, 8524, 8525, 8526, 8527, 8528, 8529, 8530, 8531, 8532, 8533, 8534, 8535, 8536, 8537, 8538, 8539, 8540, 8541, 8542, 8543, 8544, 8545, 8546, 8547, 8548, 8549, 8550, 8551, 8552, 8553, 8554, 8555, 8556, 8557, 8558, 8559, 8560, 8561, 8562, 8563, 8564, 8565, 8566, 8567, 8568, 8569, 8570, 8571, 8572, 8573, 8574, 8575, 8576, 8577, 8578, 8579, 8580, 8581, 8582, 8583, 8584, 8585, 8586, 8587, 8588, 8589, 8590, 8591, 8592, 8593, 8594, 8595, 8596, 8597, 8598, 8599, 8600, 8601, 8602, 8603, 8604, 8605, 8606, 8607, 8608, 8609, 8610, 8611, 8612, 8613, 8614, 8615, 8616, 8617, 8618, 8619, 8620, 8621, 8622, 8623, 8624, 8625, 8626, 8627, 8628, 8629, 8630, 8631, 8632, 8633, 8634, 8635, 8636, 8637, 8638, 8639, 8640, 8641, 8642, 8643, 8644, 8645, 8646, 8647, 8648, 8649, 8650, 8651, 8652, 8653, 8654, 8655, 8656, 8657, 8658, 8659, 8660, 8661, 8662, 8663, 8664, 8665, 8666, 8667, 8668, 8669, 8670, 8671, 8672, 8673, 8674, 8675, 8676, 8677, 8678, 8679, 8680, 8681, 8682, 8683, 8684, 8685, 8686, 8687, 8688, 8689, 8690, 8691, 8692, 8693, 8694, 8695, 8696, 8697, 8698, 8699, 8700, 8701, 8702, 8703, 8704, 8705, 8706, 8707, 8708, 8709, 8710, 8711, 8712, 8713, 8714, 8715, 8716, 8717, 8718, 8719, 8720, 8721, 8722, 8723, 8724, 8725, 8726, 8727, 8728, 8729, 8730, 8731, 8732, 8733, 8734, 8735, 8736, 8737, 8738, 8739, 8740, 8741, 8742, 8743, 8744, 8745, 8746, 8747, 8748, 8749, 8750, 8751, 8752, 8753, 8754, 8755, 8756, 8757, 8758, 8759, 8760, 8761, 8762, 8763, 8764, 8765, 8766, 8767, 8768, 8769, 8770, 8771, 8772, 8773, 8774, 8775, 8776, 8777, 8778, 8779, 8780, 8781, 8782, 8783, 8784, 8785, 8786, 8787, 8788, 8789, 8790, 8791, 8792, 8793, 8794, 8795, 8796, 8797, 8798, 8799, 8800, 8801, 8802, 8803, 8804, 8805, 8806, 8807, 8808, 8809, 8810, 8811, 8812, 8813, 8814, 8815, 8816, 8817, 8818, 8819, 8820, 8821, 8822, 8823, 8824, 8825, 8826, 8827, 8828, 8829, 8830, 8831, 8832, 8833, 8834, 8835, 8836, 8837, 8838, 8839, 8840, 8841, 8842, 8843, 8844, 8845, 8846, 8847, 8848, 8849, 8850, 8851, 8852, 8853, 8854, 8855, 8856, 8857, 8858, 8859, 8860, 8861, 8862, 8863, 8864, 8865, 8866, 8867, 8868, 8869, 8870, 8871, 8872, 8873, 8874, 8875, 8876, 8877, 8878, 8879, 8880, 8881, 8882, 8883, 8884, 8885, 8886, 8887, 8888, 8889, 8890, 8891, 8892, 8893, 8894, 8895, 8896, 8897, 8898, 8899, 8900, 8901, 8902, 8903, 8904, 8905, 8906, 8907, 8908, 8909, 8910, 8911, 8912, 8913, 8914, 8915, 8916, 8917, 8918, 8919, 8920, 8921, 8922, 8923, 8924, 8925, 8926, 8927, 8928, 8929,

Figure 2-14. 600-T Area (TNX)

Figure 2-15. 700-B/U Area

Figure 2-16. 200-S Area

Figure 2-17. 200-Z Area

References

- Dukes, E. K., 1984. *The Savannah River Plant Environment*, USDOE Report DP-1642, E. I. du Pont de Nemours & Co., Savannah River Laboratory, Aiken, SC.
- Du Pont, 1989. *Safety and Health Long Range Plan - Savannah River Plant and Laboratory, DPSP-89-1021*, E. I. du Pont de Nemours & Co., Savannah River Laboratory, Aiken, SC.

3.0 SURFACE WATERS AND WETLANDS PROTECTION

CONTENTS

3.1 Overview

- 3.1.1 Introduction
- 3.1.2 Summary

3.2 Policy

- 3.2.1 Policy Statement
- 3.2.2 Background for Policy Statement

3.3 Existing Conditions

3.4 Objectives

3.5 Strategy

3.6 Implementation

3.6.1 Stream Management

- 3.6.1.1 Site Program Overview
- 3.6.1.2 Justification
- 3.6.1.3 Organization Responsibilities Summary
- 3.6.1.4 Stream Policies
- 3.6.1.5 Programs
- 3.6.1.6 Research/Studies

3.6.2 Thermal Mitigation

- 3.6.2.1 Site Program Overview
- 3.6.2.2 Justification/Regulatory Requirements
- 3.6.2.3 Organizational Responsibilities Summary
- 3.6.2.4 Facility Operations
- 3.6.2.5 Construction Projects
- 3.6.2.6 Research/Studies
- 3.6.2.7 Thermal Compliance Monitoring

3.6.3 NPDES

- 3.6.3.1 Site Program Overview**
- 3.6.3.2 Justification/Regulatory Requirements**
- 3.6.3.3 Organizational Responsibilities Summary**
- 3.6.3.4 Permit Renewal**
- 3.6.3.5 NPDES Permit Compliance Programs**
- 3.6.3.6 Research/Studies**

3.6.4 River Monitoring

- 3.6.4.1 Site Program Overview**
- 3.6.4.2 Justification**
- 3.6.4.3 Organizational Responsibilities Summary**
- 3.6.4.4 Research/Studies**
- 3.6.4.5 Reporting of Results**

3.6.5 Erosion Control

- 3.6.5.1 Site Program Overview**
- 3.6.5.2 Justification/Regulatory Requirements**
- 3.6.5.3 Organizational Responsibilities Summary**
- 3.6.5.4 Programs**
- 3.6.5.5 Research/Studies**

3.6.6 Waste Treatment Facilities

- 3.6.6.1 Site Program Overview**
- 3.6.6.2 Justification/Regulatory Requirements**
- 3.6.6.3 Organizational Responsibilities Summary**
- 3.6.6.4 Permitted Facilities**
- 3.6.6.5 Planned Facilities**
- 3.6.6.6 Training (Operator Certification)**

3.6.7 Spill Prevention/Control/Responses

- 3.6.7.1 Site Program Overview**
- 3.6.7.2 Justification/Regulatory Requirements**
- 3.6.7.3 Organizational Responsibilities Summary**
- 3.6.7.4 Best Management Practices/Spill Prevention, Control, and Countermeasures Plans**
- 3.6.7.5 Facilities Operations**
- 3.6.7.6 Construction Projects**

- 3.6.7.7 Research/Studies
- 3.6.7.8 Monitoring (Compliance)

3.6.8 Radiological Effluent Management

- 3.6.8.1 Site Program Overview
- 3.6.8.2 Justification/Regulatory Requirements
- 3.6.8.3 Organizational Responsibilities Summary
- 3.6.8.4 Programs
- 3.6.8.5 Facilities Operations
- 3.6.8.6 Construction Projects
- 3.6.8.7 Research/Studies
- 3.6.8.8 Release Guide Monitoring

3.6.9 Wetlands

- 3.6.9.1 Site Program Overview
- 3.6.9.2 Justification/Regulatory Requirements
- 3.6.9.3 Organizational Responsibilities Summary
- 3.6.9.4 Programs
- 3.6.9.5 Research/Studies
- 3.6.9.6 Compliance Monitoring

3.7 Resource Requirements

3.8 References

Attachment 3.1 SRS NPDES Outfalls

**Attachment 3.2 Facility Compliance/Surveillance Procedures for
BMP/SPCC Plans**

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.1 Overview

3.1.1 Introduction

Large quantities of water, primarily noncontact cooling water, are pumped from the Savannah River, PAR Pond, and wells to support Savannah River Site (SRS) operations and are subsequently discharged to onsite streams and tributaries after use. Industrial and urban growth along the Savannah River above and below the SRS is expected to expand and use more Savannah River water. The increasing demand for water will require continued exemplary stewardship of the river, wetlands, and onsite streams. The Surface Waters and Wetlands Protection Program establishes the overall management framework for the protection of this resource.

3.1.2 Summary

SRS operations meet environmental regulations and site policies related to the protection of surface waters and wetlands except for the thermal discharges from K Reactor and the D Area Powerhouse which are presently regulated by a Consent Order with the State of South Carolina. Extensive river monitoring shows that the Savannah River is generally unaffected by plant operations.

The site is required by a South Carolina Department of Health and Environmental Control (SCDHEC) Consent Order to mitigate the heated water discharges from K Reactor and the D Area Powerhouse. An Environmental Impact Statement has been prepared for alternative cooling water systems. Extensive environmental information packages were developed through research and studies on the effects of heated water from the L, K, and C Reactors and the D Area Powerhouse on water quality and aquatic ecology in the receiving bodies of water. The installation of a once-through, natural-draft cooling tower for K Reactor and increased Savannah River flow to the D Area Powerhouse were the preferred alternatives. The Record of Decision issued February 12, 1988, however, selected a recirculating cooling system as the alternative most likely to be successfully permitted. Funding issues must be resolved before design, construction, and

startup of the selected system can begin. The heated water discharges are received from P Reactor into PAR Pond and from L Reactor into L Lake. Studies show that PAR Pond, the cooling pond for P Reactor effluent heated water which was built in the early 1950s support a balanced biological community, and researchers are monitoring the developing balanced biological community in L Lake completed in 1985.

Nonradiological discharges are regulated by the site National Pollutant Discharge Elimination System (NPDES) permit. The site has an effective NPDES program with greater than 99 percent compliance over the last three years. The permit is expected to be issued in late 1989. Several issues may be associated with the new permit including, ceasing disinfections at selected outfalls, other thermal sources, toxicity testing requirements, combining/eliminating outfalls, and using effluent treatment facilities (ETFs) for treating additional waste streams. Limits on residual chlorine could require the installation of dechlorination facilities at all sanitary waste treatment plants and possibly other facilities, if included in the new permit. Estimated funding required to comply with the proposed requirement is \$9.4 million and will depend on conditions specified in the new permit.

Tritium is the only radiological discharge to the river that is expected to increase. Although the concentrations are expected to be within the drinking water standards, the startup of the F/H ETF will double Savannah River tritium concentrations. Alternatives to reduce tritium discharges by segregation within the H Area Separations process will be explored should river concentrations be significantly higher than expected after the F/H ETF startup.

The Savannah River is monitored extensively for radiological and nonradiological constituents. Small measurable concentrations of low-level radioactive (alpha- and beta-gamma emitting radionuclides and tritium) and nonradioactive effluents reach the river from process discharges to the onsite streams, but these do not have an impact on the aquatic biota or human health. Tritium composes 97 percent of the existing radiological releases to the river. The downriver tritium concentration averages 20 percent or less of the Environmental Protection Agency (EPA) drinking water standard.

The sitewide stream management program will provide a comprehensive and long-term approach to ensure that the quality of surface waters and wetlands is protected. A management policy will be developed for each onsite stream similar to the existing Upper Three Runs Stream Policy. These policies will be the basis for decisions related to installing and operating wastewater treatment facilities and to siting and operating other facilities.

Costs for the surface water and wetlands protection program during the five-year planning period from FY89 through FY93 are expected to total about \$385 million which includes nearly 1017 man-years of effort. Operating costs account for about \$94 million. Capital expenditures are projected to be about \$242 million. The major capital items are the K Reactor cooling tower and potential dechlorination facilities for the sanitary waste treatment plants which are estimated at \$127 million and \$9.4 million, respectively.

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.2 Policy

3.2.1 Policy Statement

The Savannah River Site (SRS) Surface Waters and Wetlands Policy requires that site operations be conducted in a manner that protects public health, preserves and maintains the quality of the site surface waters and associated wetlands, meets regulatory effluent limits, and complies with applicable Department of Energy (DOE) and operating contractor requirements.

3.2.2 Background for Policy Statement

The DOE and operating contractor are committed to protecting the public health and safety and the environment. A statement of these convictions is in DOE Order 5400.1, General Environmental Protection Program, and in the SRS *Strategic Environmental Plan* (Du Pont 1986a). Compliance with applicable environmental regulations, DOE orders, and operating contractor policies form the basis for the SRS Surface Waters and Wetlands Policy.

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.3 Existing Conditions

Large quantities of water are pumped from the Savannah River and site production wells for use as cooling and process water in Savannah River Site (SRS) reactors and other processing facilities. The water is then returned to the surface streams that flow across the site to the Savannah River. The SRS is crossed by six principal tributaries of the Savannah River: Beaver Dam Creek, Four Mile Creek, Pen Branch, Steel Creek, Upper Three Runs Creek, and Lower Three Runs Creek. In addition, surface water is held in more than 50 artificial impoundments with areas totaling over 4000 acres. Par Pond is the largest, with an area of about 2700 acres, followed by L Lake, which has an area of about 1000 acres. Water is retained intermittently in wetlands and in more than 200 natural basins, including some Carolina bays. A large swamp (about 10,000 acres) borders the Savannah River and is crossed by several streams.

Some of the site streams, as well as L Lake and PAR Pond receive treated wastewater effluents containing typical industrial chemicals, small concentrations of radionuclides, and heated water as a result of SRS operations. Concentrations of radiological and nonradiological constituents are monitored to verify that permitted discharge limits are not exceeded.

The Savannah River, the principal tributaries, PAR Pond, and L Lake are monitored extensively for radioactivity. Measurable concentrations of alpha- and beta-gamma-emitting radionuclides and tritium are released to these waters, but the concentrations do not have an impact on aquatic biota or human health. Dilution renders the alpha- and beta-gamma-emitting radionuclide contaminants essentially indistinguishable from background levels in the Savannah River. Tritium releases, which make up 97 percent of the total radioactivity releases to the Savannah River from SRS operations, are detectable downriver of the SRS. Tritium concentrations downriver of the SRS average 3-4 pCi/mL. These average tritium concentrations are well within EPA standards and are less than one percent of DOE guidelines. Concentrations of all radionuclides in the Savannah River are within the EPA drinking water standards.

The SRS complies with the Clean Water Act (CWA) and the South Carolina Department of Health and Environmental Control (SCDHEC) wastewater regulations for Class B streams except for thermal effluents. Thermal discharges are currently regulated by a Consent Order with the State of South Carolina. Nonradioactive industrial effluents are monitored through a system of 76 currently permitted National Pollutant Discharge Elimination System (NPDES) outfalls. Effluent discharge limits are set to allow plant operation without significant adverse impact on aquatic biota or water quality. The 20 existing site wastewater treatment facilities are permitted by SCDHEC. Compliance performance for the last four years was as follows: 1985-98.8 percent; 1986-99.4 percent; 1987-99.7 percent; and 1988-99.8 percent.

During reactor operation, reactor cooling water is discharged at greater than 70°C (175°F) to several of the site streams. Although substantial cooling occurs during passage downstream and through the swamp, elevated temperatures are detectable in the Savannah River. Also, the large volume of cooling water discharged (about 175,000 gallons per minute per reactor) relative to the natural flow of the receiving stream results in water chemistries that are more similar to the high-nutrient Savannah River water than to coastal plain stream water. Additionally, flow-induced erosion results in elevated suspended solids loads that are transported across the stream deltas and to the Savannah River swamp. The site constructed Par Pond and L Lake to mitigate heated water discharges from P Reactor and L Reactor, respectively. In addition, the Department of Energy entered into a Consent Order with the SCDHEC to mitigate the heated water discharges from K Reactor and the D Area Powerhouse.

The majority of the Savannah River swamp exhibits little visible change as a result of heated water discharges. Some cypress-tupelo forest canopy in a portion of the river swamp is being eliminated due to elevated water temperatures, increased sedimentation, and flooding while at the same time, aquatic habitat has increased. The loss of some tree canopy results in increased growth of herbaceous vegetation and algae.

The Savannah River is generally unaffected by SRS operations. The low levels of radionuclides have no demonstrated affect on the aquatic biota or human health. The concentrations of nonradioactive materials in the river are the same upriver and downriver of the SRS. Fish in the Savannah River are attracted to thermal plumes in winter, but there is no evidence that river populations are adversely affected. There is no evidence that thermal plumes in the Savannah River affect migration patterns of anadromous fish that spawn in the river. The thermal plume does not affect the entire cross-section of the river, leaving a zone of passage along the Georgia side.

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.4 Objectives

The objectives to support the Surface Waters and Wetlands Protection Program are shown below. The strategy to achieve these objectives is illustrated in Section 3.5 followed by programmatic details in Sections 3.6 and 3.7.

- **Requirements**—Comply with the Clean Water Act, the National Environmental Policy Act (NEPA), South Carolina Department of Health and Environmental Control (SCDHEC) Wastewater Treatment Regulation 61-76, applicable federal and state regulations and orders, DOE orders, and operating contractor requirements related to allowable discharge limits, NEPA review, wetlands assessments, and accident risk minimization.
- **Operational Guidelines**—Operate within discharge limits based on applicable effluent guidelines or site-specific water quality criteria for selected radiological and nonradiological species that may pose an environmental hazard.
- **Radiological Effluents**—Control radionuclide discharges so that the Savannah River remains below the primary drinking water standards for radioactivity.
- **River Monitoring and Reporting**—Monitor the quality of the Savannah River and inform the public and regulatory agencies of the results regularly.
- **Spill Control/Response**—Maintain a spill response capability and a real-time emergency tracking system that can rapidly respond to accidental releases to surface waters.
- **Wetlands Protection**—Minimize the loss of wetlands from existing operations and prevent any significant losses from future operations.

-
-
- **Resource Management**—Develop a long range land use plan which adequately protects the site's surface water resources.

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.5 Strategy

The strategy for reaching the Surface Waters and Wetlands Protection objectives includes:

- Identifying regulatory and other protection requirements
- Promoting innovative and cost-effective means of meeting the requirements through research and development
- Developing physical and administrative controls to protect surface waters and wetlands utilizing the knowledge gained from the research and development efforts
- Implementing physical and administrative controls
- Evaluating the controls to ensure protection requirements are met.

The strategy is illustrated in Figure 3.5-1. Programmatic details are presented in Section 3.6.

Figure 3.5-1: Surface Waters and Wetlands Protection Program Strategy

FIGURE 3.5-1 SURFACE WATERS AND WETLANDS PROTECTION PROGRAM STRATEGY

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.6 Implementation

The implementation section identifies issues and those responsible for actions to achieve defined objectives. Each environmental effort will require funding for one or more of the following: research and development, operations, programs, and construction/modification projects. The resource requirements span a five-year period from FY89 through FY93.

The operating costs used throughout the text are expressed in FY89 dollars and are not escalated. Costs include subcontractor, manpower, and other operating expenses. Capital projects, such as construction and large modification projects, are expressed in escalated dollars and include manpower costs. Total costs include cost of research and development, operations, manpower, subcontractors, and capital costs. Detailed cost tables are presented in Section 3.7.

Annual manpower costs are calculated using these factors: SRS Monthly Salary (MS) at \$59,500, and all Local Roll (LR) at \$40,000.

3.6.1 Stream Management

3.6.1.1 Program Overview

The Savannah River Site (SRS) stream management policy is designed to protect human health, safety, and the environment by adhering to water quality standards for Class B streams in the State of South Carolina. The water quality of each stream will continue to be determined through studies, modeling, and research to determine if the cumulative impacts of site operations have significant short or long-term impacts on stream water quality and ecology. The results of this work are being used to develop stream management policies for each of the onsite streams. Decisions related to the installation and operation of wastewater treatment facilities and other routine releases will be made by utilizing the stream management policies to ensure that adverse environmental impacts are minimized.

The Nonradiological Site-Specific Stream Guides program is a portion of the SRS stream management effort to assess if point source discharges are having any adverse impact on receiving-stream biota. Mathematical stream flow models will be developed along with biological toxicity studies to assess the impacts from present and future SRS discharges of priority pollutants.

Preliminary studies have shown that disinfection of sanitary waste treatment plant effluents may not be necessary. A National Pollutant Discharge Elimination System (NPDES) permit modification was requested to cease disinfection and denied. Further studies of wastewater plant effluents and their impact on streams are being designed. Studies on the effects of chlorination from other sources such as discharges from cooling towers, noncontact cooling water, domestic water systems, and sanitary wastewater treatment facilities will continue. Total residual chlorine (TRC) concentrations in onsite streams are being evaluated in anticipation that TRC limits may be imposed in the 1989 NPDES permit. Additional nonradiological constituents for assessment will be selected.

Total costs for the stream management program are estimated to be \$1.4 million for the five-year planning period including 18 man-years of effort.

3.6.1.2 Justification

To preserve the quality and character of the SRS streams, the site must be concerned with the entire stream system rather than just regulatory compliance at point source discharges. Although this approach requires a comprehensive knowledge of the site's surface waters, it is the only prudent manner in which to ensure proper utilization and protection of site streams.

The stream management program supports each objective stated in Section 3.4.

3.6.1.3 Organizational Responsibilities Summary

The Department of Energy (DOE) has final approval on all stream management issues and programs. The Environmental Protection Section (EPS) has the lead role in developing the stream management program at the SRS. The Savannah River Laboratory (SRL) and Savannah River Ecology Laboratory (SREL) conduct basic research and provide expertise and assistance in making decisions regarding stream management.

Operating departments assess their operational impacts on the streams and provide data from special studies related to surface water concerns.

3.6.1.4 Stream Policies

The EPS, in cooperation with SRL, SREL, and operating departments, will develop stream management policies for each of the major SRS streams. These policies will provide guidelines for the release of effluents into each stream and will establish a mechanism by which onsite approval for release of effluents is obtained. The goal of these policies is to ensure that plant operations are conducted in a manner that maintains the water quality of each stream and the associated aquatic community.

The Upper Three Runs Creek (UTRC) stream management policy allows continued discharge of properly treated effluents from facility operations to the stream as long as: (1) the research studies in the upper third of the stream are not disturbed; and (2) the middle portion of the creek does not exceed the historical levels of contaminants. Low-impact effluents may be discharged to the lower region of UTRC only if regulatory limits are not exceeded and aquatic biota or water quality are not significantly affected.

A stream management policy for UTRC was submitted to the DOE for review and approval in October 1987. This policy has been given to the DOE with the recommendation that it be adopted for sitewide use by all SRS contractors. Prior to any new discharge to UTRC, the EPS must approve the discharge through committee action that includes input from the EPS, the custodial department proposing the discharge, and ecologists from the SRL and SREL. If the committee approves, a program to assess the impact to the stream is developed. The DOE-Environmental Division reviews the committee recommendations and makes the final decision. This mechanism was used to obtain approval of the projected discharge of the F/H Area Effluent Treatment Facility (ETF) effluent into UTRC near F Area.

3.6.1.5 Programs

Stream Management Program

•**Environmental Protection Section (EPS)**—The EPS is responsible for coordinating the stream management program with the operating departments and the SRL. The SRS Stream Management Program supports an overall policy of using onsite streams while maintaining water quality and ecological resources. Goals of the program are:

- Define existing stream quality and uses
- Develop a management plan for each onsite stream considering existing and desired uses
- Develop guidelines for assessing stream quality (chemical and biological)
- Assess effects of point source discharges on streams and the Savannah River
- Optimize effluent discharges and associated processes to minimize impact on streams and the Savannah River and to protect desired uses
- Develop basis for negotiating NPDES permit limits (monitoring, modeling, etc.).

To meet these goals, available monitoring data to establish existing water quality in SRS streams has been surveyed. Further work will include developing guidelines for aquatic quality toxicity testing at the SRS and developing dilution and transport models for predicting outfall impacts on SRS streams.

The total five-year cost for EPS is estimated to be \$595,000.

•**SRL - Environmental Sciences Section (ESS)**—The ESS will continue to assist in decision-making on all proposed changes to the stream management program. The ESS also provides continued technical guidance and assessment on environmental-specific issues associated with onsite streams. Programmatic support of ESS in stream management will be provided in the future as required.

The total five-year cost is estimated to be \$199,000.

Chlorine/Bromide Assessment

•**Environmental Protection Section (EPS)**—The EPS has the lead role in the completion of a chlorine/bromide data assessment of effluent wastewater from domestic water systems, reactor effluent cooling water, cooling towers, sanitary waste treatment plants, and other noncontact

cooling water. Program needs are being assessed and will be defined and implemented to address conditions in the renewed NPDES permit.

3.6.1.6 Research/Studies

•**Environmental Protection Section (EPS)**—The EPS has subcontracted the development of mathematical models for SRS streams to track constituents of current and future steady-state discharges. The EPS has also initiated the development of site-specific biological toxicity testing. This work is being done with a Request for Technical Assistance to the SRL and by a subcontractor (see Section 3.5.4, NPDES). Tracking capabilities, coupled with realistic toxicity testing and data, will provide a solid foundation for SRS stream management.

The total five-year cost is estimated to be \$375,000.

•**SRL - Environmental Sciences Section (ESS)**—The ESS has completed a study on the concentrations of residual chlorine in SRS streams related to the chlorination of effluents from the sanitary waste treatment plants. Results from these studies indicate that chlorinating these effluents is not necessary and could be discontinued if proposed fecal coliform monitoring instream is approved by the SCDHEC. These results were transmitted to the SCDHEC for review. Considerations for residual chlorine will be incorporated into the proposed recirculating cooling tower design. Additional studies include the effects of residual chlorine from existing site cooling towers and domestic water discharges. The estimated completion date for the studies is the first quarter, FY89.

The total five-year cost is estimated to be \$148,750.

•**SRL - Environmental Technology Section (ETS)**—The ETS will continue to develop special equipment for sampling SRS streams and the river. Samplers that are controlled by water height are used in special studies, and radiotelemetry is being investigated for remote sampler control. Data loggers that record data on water level and water quality have been used in site streams. The ETS can provide near real-time flow in streams monitored by the U. S. Geological Survey (USGS), and additional data can be obtained from the wire services of the National Weather Service and the USGS.

The total five-year cost is estimated to be \$59,500.

The ETS develops and uses stream/river transport models for estimating downstream/river concentrations of pollutants, both radiological and nonradiological, resulting from accidental releases. The same models have been used for assessments to determine if certain planned releases will exceed stream/river concentration guides. The models are a one-dimensional description of conservative stream transport and are verified using tracers in the streams. Stream transport coefficients were remeasured in 1988, and in the near future a new stream/river transport model will be developed.

The total five-year cost is estimated to be \$29,750.

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.6.2 Thermal Mitigation

3.6.2.1 Site Program Overview

Heated water discharges from K Reactor and the C Area Powerhouse currently cause exceptions to thermal limits for discharges to Class B streams as set forth in South Carolina Water Quality Stream Standards. A consent order between the Department of Energy (DOE) and South Carolina Department of Health and Environmental Control (SCDHEC) allows the two facilities to operate outside the temperature limits until mitigation facilities are placed in operation. An Environmental Impact Statement (EIS) was prepared on Alternative Cooling Water Systems for K Reactor and the D Area Powerhouse. The installation of a recirculating cooling tower at K Area is the alternative chosen by the DOE in the Record of Decision (ROD) published February 12, 1988. Increasing Savannah River flow to the D Area power facility heated effluent cooling water was chosen as well in the ROD.

Federal Water Pollution Control Act (also known as the Clean Water Act) Section 316(a) demonstration studies are being or will be conducted to evaluate if potential exceptions to thermal discharge limits will have adverse effects on the water quality and the aquatic ecology of the receiving body of water.

Heated water discharges from P and L Reactors are cooled by PAR Pond and L Lake, respectively. The SCDHEC has provisionally accepted the 316(a) and (b) demonstration that PAR Pond has a balanced community, contingent upon implementing a plan to mitigate fish kills in Pond C. At L Lake, an extensive monitoring program of biological and chemical constituents of the L Lake and Steel Creek ecosystems is in progress. A 316(a) biological monitoring program for L Lake is in progress to determine whether a balanced biological community is developing in the lake as required by the permit.

The 316(a) study must demonstrate that the recently established aquatic community in L Lake is progressing toward a balanced biological community or an alternative action plan addressing the L Lake biological concerns must be submitted.

Use of remote sensing techniques for surface water monitoring and regulatory compliance will continue. Systems are being developed to predict thermal effects from reactor operations on L Lake. Modeling of these effects is expected to result in increased reactor power levels while maintaining compliance with National Pollutant Discharges Elimination System (NPDES) thermal limits.

The total cost for the five-year planning period for the thermal mitigation program is estimated to be \$147 million which includes 48 man-years of effort.

3.6.2.2 Justification/Regulatory Requirements

Federal Laws

•**Federal Water Pollution Control Act (Water Quality Act of 1987)**—The Water Quality Act of 1987 reauthorized and strengthened the Federal Water Pollution Control Act (commonly known as the Clean Water Act). The Water Pollution Control Act requires that discharges to navigable waters meet applicable thermal limitations or demonstrate a balanced indigenous, population.

•**Executive Order 12088**—This executive order requires federal agencies to comply with applicable administrative and procedural pollution control standards established by federal laws.

South Carolina Standards

•**South Carolina Water Classification Standards (SCDHEC 61-68)**—These standards require that all Savannah River Site (SRS) navigable waters meet Class B Water Quality Standards. The standards require Class B stream temperatures to be 90°F or less, or not to cause ambient temperatures to increase by more than by 5°F.

State Consent Orders/Memorandum of Understanding

•**CO-84-4-W (Thermal Mitigation)**—In a Consent Order dated January 3, 1984, the DOE and SCDHEC mutually agreed and subsequently amended in 1985, 1987, and 1988, temporarily supersede the NPDES temperature requirements. The Consent Order also required the DOE to assess the impact of SRS thermal discharges on site streams, lakes, and the Savannah River and to install facilities to mitigate thermal discharges from the D Area Powerhouse and the C and K Reactors. The

Consent Order was amended in August 1987 to exclude the shutdown C Reactor and to establish a new compliance schedule.

The thermal mitigation program supports the requirements objective stated in Section 3.4.

3.6.2.3 Organizational Responsibilities Summary

•**Environmental Protection Section (EPS)**—The EPS is responsible for coordinating compliance activities at the SRS for the DOE. The EPS stays abreast of thermal mitigation studies and regulatory concerns, and facilitates communication between the SCDHEC, DOE, and research and operating groups. The EPS is also working with the operating groups to negotiate permits and achieve compliance for minor thermal (non-reactor) discharges.

The total five-year cost is estimated to be \$148,750.

•**SRL - Environmental Sciences Section (ESS)**—The ESS is responsible for assessing the environmental effects of the intake and release of reactor and D Area Powerhouse cooling water on onsite stream systems and the Savannah River. A Comprehensive Cooling Water Study (CCWS) assessing the impacts of thermal effluents to site waters was completed in early 1988. An L Lake 316(a) demonstration study has been completed and is being compiled to submit to SCDHEC to satisfy terms of the NPDES permit for L Reactor thermal discharge. Predictive 316(a) information on the C and K Reactor cooling water systems and powerhouse discharges was included in the EIS ROD. The ESS is also conducting an extensive monitoring program of biological and chemical constituents of L Lake and Steel Creek ecosystems. The ESS is the lead technical organization at the SRS in the development and use of remote sensing techniques.

•**SRL - Environmental Technical Section (ETS)**—The ETS is developing systems capable of predicting the thermal effects of reactor cooling water effluents on site surface waters.

3.6.2.4 Facilities Operations

Power Operations

An NPDES permit for powerhouse condenser effluent limits the temperature of the water discharged to Beaver Dam Creek to 90°F and the temperature rise to 5°F. The temperature limit is exceeded by a few degrees during the summer months at the specified NPDES monitoring location. A consent order between the DOE and SCDHEC has allowed the continued operation of the D Area powerhouse. An Environmental Impact Statement (EIS) has been prepared and a mitigation alternative selected.

The temperature of the discharge water can be maintained below 90°F by selectively increasing the river water flow pumped from the 681-5G pumphouse. This method of thermal mitigation has been approved by the SCDHEC. No additional manpower requirements are needed to implement this thermal mitigation procedure. No initial capital costs are involved. The operational costs associated with the additional pumping are estimated at \$30,000/year.

A 316(a) demonstration study is being conducted in Beaver Dam Creek to verify that a temperature differential between the Savannah River and outfall D-001 in excess of 5°F will not jeopardize the biological balance in the Beaver Dam wetlands. The study, which was started in September 1988, is scheduled to last for 18 months.

PAR Pond currently is the primary source of cooling water for P Reactor. P Reactor discharged effluent cooling water into Steel Creek until 1963. Beginning in 1963, all cooling water from P Reactor has been discharged to the middle arm of PAR Pond after passing through a series of pre-cooler ponds. The lower arm of PAR Pond serves as the intake to the PAR Pond pumphouse. Currently P Reactor receives 85-90 percent of its cooling water from PAR Pond. The remaining 10-15 percent is from the Savannah River and replaces loss by evaporation and seepage through the earthen dam to Lower Three Runs Creek. The water level at the pond is maintained and the pond supports a balanced biological community showing few signs of reactor effluent cooling water thermal effects.

The formation of a 1000-acre cooling pond in 1985 for L Reactor startup was a condition of the Final Environmental Impact Statement, L Reactor Startup. L Lake receives the heated effluent cooling water during reactor operation. The overflow from the L Lake dam follows the Steel Creek

channel to the Savannah River. The temperature limit of 90°F for Class B waters applies to 50 percent of the lake surface area. This criterion cannot be met during summer months in a cost-effective manner considering the constraints the temperature limit places on reactor power levels. During reactor operation, the reactor power levels are lowered to prevent temperature noncompliances at L Lake. Production schedules are being proposed so that annual tests requiring reactor shutdown are scheduled for summer months.

The current NPDES permit specifies that the temperature limit is enforceable in stream after mixing. Currently, temperatures are measured at the NPDES sample points, which are often far upstream of the mixing zones. Five Power Department outfalls with minor thermal influence have had problems in the past meeting the NPDES temperature limit of 90°F at their NPDES sample points. These outfalls are currently being monitored at both the official sample points and downstream locations. With data obtained from this monitoring, alternative methods or locations for NPDES temperature sampling will be proposed to SCDHEC. In cases where there is insufficient data, additional time will be requested to study the outfall behavior.

Reactors

Reactors supplies P and L Reactor operating data to the SRL for inclusion in thermal studies relating to L Lake and PAR Pond.

The total five-year cost is estimated to be \$11,900.

3.6.2.5 Construction Projects

Reactors

•**Reactor Effluent Cooling Thermal Mitigation**—Reactors, and the SRL will implement a thermal mitigation plan to maintain the K Reactor heated water discharge temperatures below the 90°F NPDES permit requirements. The preferred alternative was a once-through, gravity fed, natural draft hyperbolic cooling tower. However, the final selection in the ROD is a recirculating cooling tower which will be constructed near Pen Branch to treat the K Area heated water discharge. The total capital cost for the cooling tower is estimated to be \$127 million; the FY90 cost is \$10 million.

Milestones: Project Engineering and Design
Construction Start
Construction End

First Quarter 89
Fourth Quarter 89
First Quarter 93

•**L Lake Secondary Supply**—This project will provide a supply of water to L Lake independent of flow through the 105-L Building. This secondary supply to enter L Lake separate from the normal flow from 105-L with capacity to meet SCDHEC minimum seasonal flow criteria for Steel Creek below L Lake and to maintain L Lake level criteria during cooling water outage in L Area. This is a FY93 line-item project with a total estimated cost of \$5 million.

3.6.2.6 Research/Studies

K and D Area Studies

•**SRL - Environmental Sciences Section (ESS)**—The ESS developed environmental information packages which include predictive 316(a) information to support the Alternative Cooling Water Systems EIS. The EIS addressed the thermal discharges from K Reactor and the D Area Powerhouse. This information is useful for determining the effects potential temperature exceptions will have on water quality and aquatic ecology of the receiving water. Simulated temperature models of onsite streams are being used to determine the effluent discharge temperatures following mitigation of the reactor and powerhouse heated effluent water. The EIS related to Beaver Dam Creek, Four Mile Creek, and Pen Branch has been completed. Predictive 316(a) data on the preferred alternative are included in the EIS. A complete predictive 316(a) demonstration for the K Reactor recirculating cooling tower was submitted in 1989.

The total five-year cost for the Section 316(a) is estimated to be \$6.8 million.

PAR Pond Studies

•**SRL - Environmental Sciences Section (ESS)**—Section 316(a) and (b) demonstrations were completed in 1986 for PAR Pond. The documented results of this study were approved by SCDHEC with the stipulation that a plan for mitigating future fish kills in Pond C of the PAR Pond system be implemented. A mitigation plan was developed by the ESS and sent to the SCDHEC for approval in 1987. The plan recommended elevating the outlet crib in PAR Pond to prevent fish from

entering Pond C. Further studies on the mitigation of fish kills in Pond C and L Lake are being conducted.

The total five-year cost is estimated to be \$17,850.

L Lake Studies

•**SRL - Environmental Sciences Section (ESS)**—An extensive monitoring program of biological communities of L Lake and Steel Creek is being performed by the ESS. The biomonitoring program will determine if balanced biological communities will exist in the L Lake/Steel Creek ecosystems as required by Section 316(a) of the Clean Water Act and requirements of the SRS NPDES permit. The existence of balanced biological communities would permit L Reactor operation to continue without further thermal mitigation. Study results are expected to provide the basis for L Reactor to operate at higher power levels during some months without significant adverse effects on the L Lake ecosystem.

The L Lake 316(a) study was initiated in 1985 and the report documenting the development of the balanced biological community was submitted in June 1988. Studies are continuing pending a response from the SCDHEC. Specific studies concerning the mitigation of fish kills in L Lake and the operation of L Reactor to produce tritium are underway.

The total five-year cost is estimated to be \$5.1 million.

New Production Reactor Support

•**SRL - Environmental Sciences Section (ESS)**—Siting of a new production reactor (NPR) at the SRS is being considered to meet national defense nuclear materials requirements into the 21st century. An extensive Environmental Information Document (EID) will be developed by the SRL to support the National Environmental Policy Act (NEPA) process. The EID will provide the technical basis for developing an EIS prepared by an independent DOE contractor. The ESS will contribute to the EID by coordinating preparation of the document and undertaking a predictive 316(a) study for the NPR cooling water effluent. Assessment of site geology, hydrology, and wetlands protection issues associated with the NPR EID will also be undertaken by the ESS.

Current plans call for the preparation of an EIS in the 1989 through 1991 time frame. An NPR Environmental Task Team has been formed to develop schedules and resource requirements for EID preparation. The

SRL-New Production Reactor Development (NPRD) group has primary responsibility for the task team, which has members from the ESS, ETS, and EPS. Work has been initiated on site selection and EID preparation. Field studies in support of this project will be required to access the impact on selected sites and streams that will receive effluents.

The total five-year cost is estimated to be \$704,750.

Thermal Transport in Streams

•**SRL - Environmental Sciences Section (ESS)**—The ESS is the lead site organization for development and use of remote sensing techniques. The ESS is continuing studies to use remote sensing technologies in support of site environmental monitoring, assessment, and regulatory compliance. Projected applications of remote sensing to SRS research and monitoring activities will include water quality monitoring of the L Lake/Steel Creek ecosystem, waste site characterization, reactor restart EIS, and NPR siting and support. The major parts of these applications consist of thermal infrared and multispectral scanner surveys, aerial photography, gamma radiation surveys and analysis, data processing and analysis, and Geographic Information Systems (GIS) data base development.

Additional studies will continue in FY89 and FY90. Study results will be reviewed annually to assess the scope and needs for the coming fiscal years.

The total five-year cost is estimated to be \$81,550.

Continued Reactor Operations

•**SRL - Environmental Sciences Section (ESS)**—The DOE will prepare an EIS to support the operation of P, K, and L R. actors. The ESS will coordinate the preparation of an EID which contains the technical data necessary for an independent DOE contractor to prepare the EIS. These studies and document preparation will primarily occur during FY89 and FY90, but additional studies and documentation are anticipated in subsequent years.

The total five-year cost is estimated to be \$172,550.

Thermal Modeling of L Lake

•**SRL - Environmental Technology Section (ETS)**—The ETS is currently developing systems capable of predicting the thermal effects from reactor operations on the site surface waters. L Lake modeling is expected to result in increased reactor power levels while maintaining the lake temperature below the limits in the NPDES permit.

The ETS is responsible for developing transport/thermal models for surface water systems at the SRS, for analysis of thermal data (field and remote sensing data), field studies that support the modeling effort, and for providing thermal compliance data for L Lake. The ETS maintains thermal databases for L Lake, SRS streams, and the Savannah River. Future areas of investigation include developing methods to automate stream and river temperature compliance reporting, developing quality assurance methods for the temperature data that are now being collected, and performing thermal impact analyses.

The total five-year cost for the current thermal transport program is estimated to be \$148,750.

3.6.2.7 Thermal Compliance Monitoring

Compliance monitoring for thermal and additional water quality parameters is routinely undertaken and administered by a variety of SRS departments. Production department custodians are responsible for ensuring that surface water effluents from their facilities permitted under the NPDES program meet permit requirements. Administration of the site NPDES program is the responsibility of the EPS.

Thermal compliance monitoring of L Lake cooling waters is jointly undertaken and administered by the ETS and Power Operations. The ETS and Power Operations total five-year costs for L Lake thermal monitoring are estimated to be \$26,825 and \$198,425, respectively.

ETS maintains the real-time temperature data collected from the satellite data platforms on the Savannah River and the confluences of the site streams with the Savannah River. Programs are being developed to ensure data quality and to make the compliance reports available automatically.

The total five-year cost is estimated to be \$148,750.

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.6.3 NPDES

3.6.3.1 Site Program Overview

All operational effluents from Savannah River Site (SRS) facilities discharge through point source outfalls. Discharges from the outfalls are regulated by the South Carolina Department of Health and Environmental Control (SCDHEC) under the National Pollutant Discharge Elimination System (NPDES). Currently there are 76 permitted outfalls at the SRS under NPDES Permit SC0000175 (see Attachment 3.1). The permit was issued on January 1, 1984, and a renewal application was submitted in June 1988. Permit renewal is pending action by the SCDHEC. Compliance performance for the last four years was as follows: 1985 - 98.8 percent; 1986 - 99.4 percent; 1987 - 99.7 percent; and 1988 - 99.8 percent.

The NPDES self-monitoring program is administered by SRS personnel with analytical work done by a subcontractor lab. To reduce costs, the Environmental Monitoring Section (EMS) plans to take on some of the analytical work. They plan to develop resources and capabilities in-house in order to request certification of a laboratory in Building 735-11A by the State of South Carolina.

Total cost for the NPDES program is estimated to be \$13.5 million for the five-year planning period and includes 105 man-years of effort.

3.6.3.2 Justification/Regulatory Requirement

Federal Laws

•**Federal Water Pollution Control Act (Water Quality Act of 1987)**—The Water Pollution Control Act requires the Department of Energy (DOE) to obtain applicable permits before treating wastes and discharging them to navigable waters. Under Section 402, a National Pollutant Discharge Elimination System (NPDES) permit is required. The Environmental Protection Agency (EPA) has granted this regulatory authority to the State of South Carolina.

In complying with the provisions of the NPDES permit, the site achieves the following objectives stated in Section 3.4: compliance with SCDHEC Permit SC0000175 and thus with the Federal Water Pollution Control Act; and compliance with the maintenance of site stream water quality criteria and/or stream-specific guides.

•**Executive Order 12088**—See description in Section 3.6.2.2.

3.6.3.3 Organizational Responsibilities Summary

The NPDES permit is administered on a sitewide basis by Environmental Protection Section (EPS), Environmental Monitoring Section (EMS), and the Power Section. The EPS provides support for permit application, modifications, and compliance. The EMS and Power Section oversee compliance sampling and analysis. Each outfall has an assigned custodian who is responsible for ensuring that the outfall meets permit parameters. The EMS is responsible for scheduling compliance sampling of outfalls. State and EPA audit samples are taken on a less frequent basis. The EMS takes parallel samples for comparison. The EMS also oversees compliance sampling and analysis during NPDES permit renewal. Outfall custodians are responsible for supplying the EPS with information needed for permitting support.

3.6.3.4 Permit Renewal

A permit renewal application was submitted to the SCDHEC in June 1988. The new NPDES permit is expected to be issued in late 1989.

3.6.3.5 NPDES Permit Compliance Programs

Construction Management

Construction Management has four outfalls, S-002 and S-008 in Central Shops and DW-001 and DW-002 in S Area. Construction Management plans to stop processing construction liquid wastes through the oil/water separator and its subsequent discharge to DW-002 when Defense Waste Processing Facility (DWPF) construction work is completed. SRS management will have to designate a custodian for the operation at that time. These outfalls are sampled by the EMS and analyzed for compliance parameters. Other surveillance is carried out by construction at the following costs:

The total five-year monitoring, analysis and implementation cost is estimated to be \$697,500.

Central Services Works Engineering (CSWE)

CSWE has a program to monitor the A-005 outfall in accordance with DPSOL 7-1005.

The total five-year cost is estimated to be \$148,750.

Defense Waste Processing Facility (DWPF)

The DW-003 and DW-004 outfalls will be inspected daily, and effluent will be sampled as needed beginning March 1989. Nonroutine samples will be analyzed in-house. Compliance sampling and analysis will be done by the EMS.

Beginning in FY89, the total five-year cost is estimated to be \$71,950.

Environmental Monitoring Section (EMS)

The EMS is responsible for the collection and analysis of monthly compliance samples from site NPDES outfalls. Collection procedures are outlined in DPSOL 271-1. Currently, samples are collected by the EMS and analyzed by an offsite certified subcontractor and onsite laboratories. The EMS maintains the site NPDES database and reports results to the EPS in the format required by the SCDHEC.

In addition to routine compliance sampling, the EMS collects parallel samples during SCDHEC compliance audits and has them analyzed.

Total five-year manpower requirements are as follows:

Sample Collection	\$200,000
Sample Analysis	\$600,000
Database Maintenance	\$50,000

To consolidate NPDES activities onsite, the EMS has recently equipped laboratories in the newly constructed Building 735-11A. DPSOP 271-6 will document the analytical procedures for NPDES samples. A stepwise approach to state certification and onsite analysis is planned. The first phase, certification and testing for metals and solids, is planned for 1989. One additional analyst will be required for this effort.

The manpower cost is estimated to be \$297,500.

The next phase will be certification and testing for parameters such as nitrate, sulfate, and oil and grease. This effort is planned for 1990 and will require additional personnel and funding. The final phase will be certification and testing for organic constituents. This phase is also planned for 1990 and will require additional personnel and funding.

The additional five-year manpower cost is estimated to be \$654,000.

Environmental Protection Section (EPS)

The EPS has the administrative oversight responsibility for the NPDES permit. The EPS monitors site performance under the permit, prepares required regulatory reports, assists the custodial departments with permit modifications, and is the operating contractor contact with the DOE and SCDHEC.

The total five-year NPDES permit administration cost is estimated to be \$297,500.

Naval Fuel (NF)

The Naval Fuel Facility is responsible for ensuring that outfall F-003 complies with NPDES permit effluent limits. Extensive sampling was conducted during 1986 to characterize the water quality of Naval Fuel effluent. Monthly monitoring is conducted for process control and ongoing effluent characterization. Process control analyses are made by in-house or other onsite labs.

The total five-year cost is estimated to be \$8925.

Power Operations

Process control sampling is performed to provide trend analysis data for all Power Operations outfalls. A minimum of two samples per week are taken from each permitted outfall. Data is then provided to outfall custodians on a monthly and bi-annual basis in order to perform trend analysis and characterize each discharge stream relative to area processes and discharge limits. Power Operations coordinates with the EPS on the preparation of information for new permit applications and the justification for revisions to existing limits.

The total five-year technical oversight and report preparation cost is estimated to be \$535,500.

•**New NPDES Permit**—The new NPDES permit, is expected to be issued in late 1989, will probably have limitations on total residual chlorine (TRC) concentrations. The EPA is promoting the elimination of chlorine discharges to surface streams. TRC limits as low as 10 - 15 ppb may be imposed. Several water or wastewater systems are chlorinated and will discharge TRC concentrations in excess of permit limitations. Some of these systems include drinking water systems, clearwells, storage tank overflows, sanitary wastewater treatment plant effluents and cooling tower overflows. Once the new permit is received, many overflow streams may have to be eliminated. Dechlorination facilities may be required for some processes.

The total five-year cost is estimated to be \$128,520. Capital cost estimates are not available, pending issuance of the SCDHEC requirements.

•**Removal of 784-A Powerhouse Waste Streams from A-008 Outfall**—The existing 784-A powerhouse waste stream effluents which flow to Outfall A-008 consist of discharges from the wet ash scrubber, process cooling water, service and domestic water tank overflows, well blowoff, boiler blowdown, washdown water, and the coal unloading sump. The wet ash scrubber discharge and the washdown water contain high levels of suspended solids. These effluents will be diverted to and treated in a sedimentation basin provided by this project. After completion of this project, no powerhouse effluents will discharge through Outfall A-008. The total estimated cost is \$6 million.

Raw Materials (RM)

The Raw Materials Department releases effluent from the Dilute Effluent Treatment Facility (DETF) to outfall M-004 and from the Project Air Stripper (PAS) to outfall M-005. Both of these outfalls flow to outfall A-014. Each process batch from the DETF is sampled by RM and analyzed by the SRS Laboratories prior to release to ensure compliance with the NPDES permit limits. The outfalls (M-004, M-005, and A-014) are also sampled and analyzed weekly by the EMS. Total mass for many of the constituents at the M-004 outfall are specified in the NPDES permit and are calculated based on the concentration analyses and measured flow rate. The PAS influent and effluent are monitored quarterly for all priority pollutants as a condition of the NPDES permit. The analytical results and mass

calculations are compiled by RM and the EPS and issued as a portion of the monthly NPDES Discharge Monitoring Report.

The total five-year sampling, analysis, technical oversight and report preparation cost is estimated to be \$548,750.

•**Upgrade Storm Sewer**—The existing storm sewer will be modified to enable handling current and potential future volumes of noncontact cooling water. The modification will include contamination monitors to comply with monitoring regulations. This is a FY93 line-item with a total estimated cost of \$2,000,000. This project is required by EPA and state regulations.

Reactors

Reactors Department NPDES outfalls consist of stormwater runoff and in some cases heat exchanger cooling water flow. Therefore, only monthly EMS compliance samples are routinely analyzed. Non-routine discharges to the outfalls are analyzed prior to release. Records and trends of all sample data are maintained in each reactor facility. Reactors Department personnel provide a visual inspection of the following items at each outfall at least monthly: grass cutting, headwall grating, flow weir, platform safety, and current signs.

The total five-year cost is estimated to be \$50,575.

Separations

The current Separations program includes daily monitoring for process control purposes and sample analyses for permit parameters by a subcontractor for Separations at the five Separations outfalls. The EMS samples monthly for NPDES compliance. Separations maintains continuous monitors at the outfalls. Data is analyzed for trends and process control records are maintained by Separations.

The total five-year routine daily monitoring, data management and trend analysis cost is estimated to be \$119,500.

•**Divert East Side Rainwater, 221-H**—This project will provide a design and scope of work to install a drainage system to divert rainwater draining down the east side of 221-H into the area storm water system. The roof of 221-H has an area of approximately 100,000 sq ft.

Rainwater drains off either the west or the east side of the building. The west side is equipped with drain pipes which are connected to the area storm sewer system, but since there are no drainage lines on the east side, the roof water collects on the ground causing slipping hazards on freezing days and poor housekeeping conditions. This is a FY92 project with a total estimated cost of \$100,000.

•**Segregated Water Auto Count System, 221-H**—This project will purchase an automatic low background Alpha/Beta/Gamma counting system and provide the design for the installation of this system in the 221-H EMS counting room. The present method and instrumentation is inadequate to determine the activity in the segregated cooling water prior to discharging it to the creek. Purchase and installation of a more sensitive counting device will eliminate this problem. This is a FY90 project with a total estimated cost of \$100,000.

SRL - Tech Area

The Laboratory Services Section's effort to ensure compliance with outfall A-001 NPDES permit limitations includes maintaining administrative controls on releases via written procedures, evaluating unusual discharges and submitting new permit applications to the SCDHEC through the EPS and DOE. The EMS samples monthly for NPDES compliance.

The total five-year cost is estimated to be \$39,750.

SRL-TNX

TNX activities for ensuring compliance with the site NPDES permit currently consist of maintaining administrative controls on releases to the five active permitted outfalls (one from the sanitary treatment plant is under Power Section custodianship), evaluating unusual discharges, and submitting new permits and modifications to existing permits to the SCDHEC via the EPS and DOE. Most sampling of TNX outfalls is performed by the EMS.

Process control samples are taken at the facility which generates the effluent to verify compliance. TNX is responsible for coordinating with the EMS and EPS to ensure that testing is performed and analytical results are reviewed.

The total five-year cost is estimated to be \$79,500.

Tritium

The Tritium Department is responsible for ensuring that monthly compliance samples taken from NPDES outfall H-002 (by the EMS) comply with permit limits. A subcontractor takes biweekly process control samples for the Tritium Department and analyzes the samples for permit parameters. The process control sampling program is a means of detecting trends leading to potential problems with the effluent waters from Tritium facilities.

The total five-year cost is estimated to be \$24,500.

Waste Management (WM)

The WM Department has custodianship of seven outfalls. WM obtains periodic process control samples for pH, chlorine, and other parameters. Outfall H-006 receives stormwater and Outfall H-007 receives cooling tower water and stormwater. The outfalls are sampled monthly by the EMS for NPDES compliance. The F/H ETF added five outfalls at the end of 1988 from:

- F Area retention basin/cooling water basin (F-012, F-013)
- H Area retention basin/cooling water basin (H-017, H-018)
- F/H ETF process water outfall to Upper Three Runs Creek (H-016).

The total five-year cost for process control samples is estimated to be \$28,000.

3.6.3.6 Research/Studies

Outfall Characterization

•**SRL - Environmental Sciences Section (ESS)**—ESS will assist the EPS in developing a long-term study for nonpoint discharges. The Water Quality Act of 1987 authorizes a new state-federal program to control nonpoint source pollution such as oil and grease run off from city streets, pesticide run off from land and run off from construction areas. The effects of nonpoint sources of water pollution are expected to be an important environmental and regulatory issue in the next few years.

The total five-year cost is estimated to be \$53,550.

Biological Monitoring and Assessment

•**Environmental Protection Section (EPS)**—The SCDHEC has indicated that aquatic toxicity testing will be imposed in the new NPDES permit. The EPS will coordinate biotoxicity studies with the SRL and individual departments in advance of permit requirements in order to determine if there are toxicity problems at any SRS outfalls. Specific outfalls of most pertinent interest are being tested.

•**SRL - Environmental Sciences Section (ESS)**—The ESS has completed a study to determine the toxicological characteristics of surface water effluents discharged from site NPDES outfalls. Fifty-two of the 64 outfalls were surveyed at least once between March and October 1985. The results of these tests and analyses were used to predict the possible impact of each effluent on the organisms inhabiting the receiving stream. Specific toxicity tests have also been conducted on the new M Area effluent treatment facility discharges. Similarly, a biotoxicity testing program has been implemented by ESS for the effluent from the planned F/H Area Effluent Treatment Facility (F/H ETF).

The total five-year cost is estimated to be \$667,900.

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.6.4 River Monitoring

3.6.4.1 Site Program Overview

Water quality and the associated aquatic community of the Savannah River and site streams are currently being monitored. These continuing assessments stem from the Savannah River Site's (SRS) ongoing commitment to protecting the water quality of the Savannah River. In 1951, baseline river quality data was collected prior to site operation and long before statutory/regulatory requirements were in place. Routine water quality monitoring by the Environmental Monitoring Section (EMS) for nonradiological parameters (temperature, pH, dissolved oxygen, nutrients, major ions, metals) in the Savannah River was initiated in 1959. This program was expanded to include a number of site stream locations in 1971. Continual refinements and expansion of the program were undertaken in 1973, 1982, and 1985.

The EMS conducts extensive radiological surveys of the river upstream and downstream of the SRS. Annual summaries of the data are presented in Volumes I and II of DPSPU-88-30-1, *U.S. Department of Energy Annual Savannah River Site Environmental Report for 1987* (DOE 1988), and prior issues.

Additional nonroutine, special water quality surveys have been historically undertaken, in response to requests by the Department of Energy (DOE) or South Carolina Department of Health and Environmental Control (SCDHEC), to address short-term special water quality concerns or to further long-term research in the field of water quality. These surveys are conducted by SRS organizations. Special water quality surveys conducted over the years include studies of: Mercury in onsite streams/Savannah River from 1973 to 1975; and volatile acid and acid-base-neutral organics in onsite streams/Savannah River during 1984. Additional information is being collected by the Limnology Department of the Academy of Natural Sciences of Philadelphia (ANSP) for the SRS. Parameters that are being measured include temperature, concentrations of herbicides, pesticides, polychlorinated biphenyls (PCBs), and mercury in fish and drinking water. cursory surveys are also being made of the

protozoa, insects, macroinvertebrates, fish, and algae in the aquatic community.

The SRL-Environmental Technology Section (ETS) performs special studies on the Savannah River to determine the transport and concentration of radionuclides. These studies are used to support EMS findings when a release reaches the river.

Total cost for the river monitoring program is \$1.6 million for the five-year planning period and includes about 11 man-years of effort.

3.6.4.2 Justification

The operating contractor's policy to protect health and environmental quality, coupled with the increased use of Savannah River water for human and industrial purposes, requires that the SRS be able to identify and minimize site impacts on the river. The detailed, ongoing river studies initiated prior to site startup provide the only means of accurately assessing river impacts from the site.

The River Monitoring Program, through scheduled periodic sampling of the biota and the water by plant and subcontractor personnel achieve the objectives set forth in Section 3.4: compliance with operating contractor policy and an EPA limit of 20 pCi/mL of tritium in the Savannah River; compliance with routine monitoring of the river and reporting the findings to the public through the annual environmental report.

3.6.4.3 Organizational Responsibilities Summary

The Environmental Monitoring Section (EMS) has the lead responsibility for routine and scheduled river monitoring with participation by the Environmental Protection Section (EPS) and Savannah River Laboratory (SRL). The participation by the EPS will continue to increase in coming years as expanded stream management programs are implemented.

3.6.4.4 Research/Studies

Environmental Monitoring Section (EMS)

The EMS administers a subcontract with the ANSP for a continuing survey of aquatic environment and water quality of the Savannah River upriver and downriver from the SRS. Diatometers are positioned in the river to provide a continuous monitor of the potential effects of SRS effluents on

one major group of river diatoms. The diatometer substrates are sent to the ANSP for analysis on a biweekly basis. Quarterly surveys of other biota are made by an interdisciplinary team from the ANSP. These surveys are designed to detect any gross changes of water quality in the river at a control station located upstream from all SRS discharges and at impact and recovery stations which are below plant outfalls. Comprehensive surveys of water quality and biological species are also performed. These surveys look at trends in all major aspects of river conditions at three to five-year intervals. The original surveys were conducted in 1951.

The total five-year EMS cost is estimated to be \$750,000.

The EMS subcontracts with the ANSP to conduct comprehensive baseline limnology studies as needed. The ANSP completed a two-year comprehensive survey on the Savannah River in the vicinity of Plant Vogtle to obtain a pre-operational baseline characterization of the biological and chemical parameters. These baseline studies will be archived and used in post-operational studies. The studies will differentiate between the impacts on the river by Plant Vogtle operations from those attributable to SRS operations.

The EMS conducts routine monitoring for radioactivity at specific locations in the Savannah River. The EMS collects samples according to DPSOL 271-1 and performs analyses as outlined in DPSOLs 271-5 and 271-2. Data are reviewed and reported annually in the SRS environmental monitoring report. The EMS has instituted management reporting guidelines for increases in radionuclide concentrations at two sampling locations, River-2 (upriver) and River-10 (downriver). For the River-2 location, a concentration of any radionuclide measured in a weekly sample that is greater than two times the maximum concentration measured at this location during the previous calendar year is highlighted in the monthly releases report. For the River-10 location, a concentration of any radionuclide measured in a weekly sample that is greater than the average concentration at this location for the previous calendar year is highlighted in the monthly releases report.

The EMS also initiates special monitoring programs of the Savannah River whenever unexpected radioactive release occurs to a plant stream.

The EMS conducts a routine Savannah River water quality monitoring program. Mercury analysis of Savannah River fish and river temperature measurements are also included. Quarterly temperature profiles are

performed to show compliance with the Consent Order between the DOE and SCDHEC (see Thermal Mitigation, Section 3.6.2). Savannah River water and sediments are analyzed for pesticides, herbicides and PCBs. The EMS collects the samples and sends them to an offsite laboratory for analysis. Data are evaluated and reported in the annual environmental report.

In addition to the routine program, the EMS performs special nonradiological monitoring whenever releases occur which could impact the Savannah River.

The total five-year cost for river monitoring is estimated to be \$500,000.

SRL - Environmental Technology Section (ETS)

The ETS performs special studies in the Savannah River to determine the transport and concentration of radionuclides, primarily Cs-137, Tc-99, and I-129. The results of the special studies are used to support EMS findings following a release to the river. In addition, special topic reports are made (e.g., April 1986 tritium release from the 400 Area and L Reactor restart Cs-137 concentrations in the river). These studies will continue with an assessment of Np-237 transport in the river.

The total five-year cost is estimated to be \$297,500.

An environmental survey was made in 1986-87 to provide baseline radionuclide data of the Savannah River in the vicinity of the Plant Vogtle nuclear power plant outfall. In-situ measurements were made and were found to be valuable as a means of surveying following accidental releases of radioactivity both from Plant Vogtle and the Savannah River Site. The surveys will continue at a much lower level of effort.

The total five-year cost is estimated to be \$79,750.

3.6.4.5 Reporting of Results

The results of the river monitoring programs are published annually in the DOE annual environmental monitoring report. Reports on special studies or impact of unplanned releases are published as necessary.

Unusual monitoring data and information related to unplanned releases are communicated to state and federal regulatory agencies as soon as practical.

Costs for the annual report can be found in Community Outreach and Emergency Planning chapter (see Section 12.6.1).

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.6.5 Erosion Control

3.6.5.1 Site Program Overview

Soil erosion to the Savannah River, site streams, Carolina Bays, ponds, and lakes on the site can occur from stormwater runoff, improper maintenance of stormwater systems, and improperly maintained secondary roads. The major erosion effects outside the site operating areas occur along stream banks, secondary roads, and right-of-ways. Operating areas generally experience some soil erosion during periods of heavy construction. On major construction projects, money is allocated for preventing the siltation/sedimentation of nearby streams. The preventative measures have included sedimentation basins, diversion of runoff water away from storm sewers to open fields, and filtration devices such as hay bales and cloth screening.

The U.S. Forest Service (USFS) annually surveys erosion conditions along paved roads, wood roads (used in site logging activities), and powerlines. Recommendations are submitted to Central Service Works Engineering (CSWE) personnel who prepare site specifications for secondary roads.

Total cost for the erosion control program is \$3.6 million for the five year planning period and includes about 43 man-years of effort.

3.6.5.2 Justification/Regulatory Requirements

Executive Orders

•**Executive Orders 11988, 11990, and 12088**—These Executive Orders obligate the Department of Energy (DOE) to avoid, or minimize to the extent practicable, any short- and long-term adverse impacts to floodplains and wetlands. Even though the site is exempted from the provisions of Aiken County Ordinance 74-10-37, Sediment Control Ordinance, erosion control plans use the ordinance as a model.

The Erosion Control Program, through inspections, surveillance, maintenance, and provisions made in projects is achieving these objectives set forth in Section 3.4: the requirements of Executive Orders 11988 and 11990; and the NPDES limits for total suspended solids at permitted point sources and the protection of wetlands.

3.6.5.3 Organizational Responsibilities Summary

Each Savannah River Site (SRS) area or facility custodian is responsible for controlling or minimizing soil erosion caused by stormwater runoff or heavy construction. The immediate reporting of significant erosion in the contiguous vicinity of the area or facility falls within the domain of the area or facility custodian. The contiguous area in many instances is the secure area devoid of trees outside the perimeter fences.

The U.S. Forest Service (USFS) conducts an annual road condition survey of all general use and secondary roads in addition to powerline and wood roads used in timber sales. The USFS prepares maintenance lists for road repairs or new wood roads for pulp wood sales. Requests for road maintenance are routed through the DOE and reviewed by CSWE for materials and cost. Road specifications, maintenance, and erosion control are the responsibility of CSWE. Soil erosion and land reclamation in all forested areas are the responsibility of the USFS.

Any erosion of the banks of the Savannah River that threatens SRS facilities, such as the river pumphouses, is referred to the site office of the United States Army Corps of Engineers (COE) for site-specific action by the Charleston District COE.

3.6.5.4 Programs

Central Services Works Engineering (CSWE)

The CSWE Erosion Control Program includes the use of straw or rip-rap for filler materials and the reseeding of areas of recent construction or excavation. This includes work such as building road shoulders, cutting deerhunt trails, etc. CSWE provides the manpower and equipment for erosion control areas throughout the plantsite. The CSWE and USFS have agreed to consider USFS specifications for secondary roads when constructing roadways other than roads for the USFS. CSWE has responsibility for developing site secondary road specifications. There are also coordination activities with the U.S. Soil Conservation Service.

The total five-year cost for this program is estimated to be \$2.8 million.

CSWE will annually survey the site's secondary roads and utility right-of-way for erosion problems. The erosion areas will be prioritized for corrective action.

The total five-year survey update cost is estimated to be \$29,750.

Construction Management

Construction Management conducts erosion control measures as developed by the operating departments for specific projects.

The total five-year monitoring and implementation cost is estimated to be \$548,750.

Environmental Protection Section (EPS)

The EPS currently reviews control plans which must be prepared for all major projects involving earth moving or land clearing. The EPS proposes, as manpower becomes available, to take an active role in erosion control by providing followup to ensure that all aspects of erosion control plans are implemented. The total five-year cost is estimated to be \$178,500.

3.6.5.5 Research/Studies

SRL - Environmental Sciences Section (ESS)

A limited assessment was made by the ESS in FY88 on the effects of erosion, sedimentation, and siltation of Upper Three Runs Creek from construction activities in F, H, S, and Z Areas. Other erosion assessment studies will be developed in future years as warranted by plant construction activities. The ESS may assist in developing long-term studies for addressing erosion control at the site (beyond current National Environmental Policy Act (NEPA) requirements).

The total five-year cost is estimated to be \$29,750.

SRL - Environmental Technology Section (ETS)

The ETS makes special studies on stream sediment transport to support stream/river transport model development, because many pollutants are

transported by sediment particles. These results will assist in determining the fate of stream-transported sediments. A study was completed in 1987 on the transport of Cs-137 to Creek Plantation while the Savannah River was in flood stage. This study includes detailed measurements on sediment transport in the Savannah River floodplain.

The total five-year cost is estimated to be \$59,500.

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.6.6 Waste Treatment Facilities

3.6.6.1 Site Program Overview

The Savannah River Site (SRS) has 30 permitted wastewater treatment facilities currently operating. These are predominantly Sanitary Waste Treatment Plants (SWTPs). As plant operations expand and environmental regulations become more strict, additional wastewater facilities will be required. Increased treatment capacity has been installed in A, H, and F Area SWTPs and will be installed in A and D Areas. SWTPs in all areas will have equalization tanks installed to permit deferring the treatment of peak waste liquid input to periods of reduced flow. Recently completed treatment facilities include the F/H Effluent Treatment Facility (ETF) which permitted the closing of F and H Area seepage basins, Savannah River Laboratory (SRL) ETF to remove low-level radioactivity; TNX Area ETP to process nonradioactive aqueous effluents, and TNX Area Organics Removal Facility (ORF) to remove Environmental Protection Agency (EPA) priority pollutants (e.g., phenols, benzene, nitrobenzene) from TNX wastewater. ETFS that are planned include the TNX ion-exchange facilities (one is experimental, the other is full scale) to remove mercury from wastewater generated by a Defense Waste Processing Facility (DWPF) process. These new wastewater treatment facilities will require certified operators of the proper level.

Facility custodians are in the process of qualifying additional personnel to operate SWTPs and effluent treatment facilities as required by South Carolina law.

Over the next five years, costs for constructing and operating wastewater facilities will increase. About \$44.7 million is forecasted for the construction of additional facilities and capacity. Total five-year operating costs are estimated to be \$63.6 million.

Total cost for the Waste Treatment Facilities program for the five-year planning period is about \$133 million including 532 man-years of effort.

3.6.6.2 Justification/Regulatory Requirements

Federal Laws

- Federal Water Pollution Control Act (Water Quality Act of 1987)**—The Water Pollution Control Act requires the Department of Energy (DOE) to obtain applicable permits before treating wastes and discharging them to navigable waters.

- Executive Order 12088**—See description in 3.6.2.2.

Code of Laws of South Carolina

- South Carolina Pollution Control Act (Title 48, Chapter 1)**—This act requires the DOE to comply with applicable South Carolina environmental regulations.

Under the South Carolina Pollution Control Act, the U. S. Department of Energy - Savannah River Operations Office (DOE-SR) is required to obtain Wastewater Treatment Facility Construction Permits for the construction of any wastewater treatment facilities and sewers (South Carolina Wastewater Regulations 61-9, Section 2). After construction is completed, an operating permit must be obtained.

The Wastewater Treatment Facilities program achieves these objectives set forth in Section 3.4: compliance with regulatory requirements in the Clean Water Act and the South Carolina Pollution Control Act which require permitting prior to the release of wastewater to state navigable waters; compliance with SRS release guidelines and the EPA standard for tritium in the Savannah River; and compliance requiring the reporting of findings in the annual environmental report.

3.6.6.3 Organizational Responsibilities Summary

Custodians of permitted wastewater facilities are required to meet the permit limits for facility effluents and to operate the plants in accordance with all NPDES permit conditions. Each custodian of an SWTP or an effluent treatment facility is required to have characterized the effluent from the facility and to have trained and licensed operators for SWTPs. Each facility custodian is to determine in advance with Power Section personnel the impact a large influx of operating or construction personnel would have on the SWTP.

Environmental Protection Section (EPS)

The EPS helps custodians apply for permits and permit modifications, and with general compliance issues related to wastewater treatment. The EPS facilitates information exchange between the regulatory groups and the SRS operating groups. The EPS also coordinates operator training and certification activities for the site. In the future, the EPS plans to provide the services of an experienced wastewater engineer for the site.

The total five-year cost is estimated to be \$416,500.

3.6.6.4 Permitted Facilities

Construction Management

Construction Management currently has two permitted wastewater facilities. The oil/ water separator facility in S Area is permitted to separate oil from water liquids generated by construction work on the DWPF installations. The concrete batch plant was installed and permitted to facilitate the movement of concrete to the DWPF construction site. Construction intends to stop operation at the concrete batch plant when the DWPF facilities are completed. The effluent water from truck washing is clarified and its pH adjusted in the batch plant's treatment facility prior to release to onsite streams.

The manpower requirements and costs are listed in Section 3.6.3.5.

Navel (NF)

The Naval Fuel Facility treats all process wastewater by volume reduction in an evaporator and solidification in cement to produce NF saltcrete. The saltcrete is currently being temporarily stored on storage pads at the Burial Ground with plans for ultimate disposal in Z Area vaults beginning in 1990.

The total five-year operating cost is estimated to be \$7.1 million. The total 1990-1993 cost for NF saltcrete Z Area disposal is estimated to be \$1.34 million.

Due to the increased plant population and age of current facilities, additional capital expenditures for new plants and equipment are planned for FY89 through FY93 (see Section 3.6.6.5).

Raw Materials (RM)

- **Liquid Effluent Treatment Facility**—RM operates one effluent treatment facility. This facility provides treatment for all M Area process wastewater and is operated under SCDHEC Permit No. 10287 for the Liquid Effluent Treatment Facility (LETF). Raw Materials also operates a Process Waste Interim Storage Facility under SCHDEC permit No. 10696. The waste from the LETF is currently an F-006 RCRA-listed hazardous waste (wastes from electroplating processes) when Building 313-M is in operation.

The total five-year cost is estimated to be \$5.8 million.

- **LEFT Renovations**—The LETF process uses nitric acid, which has a potential for causing an undesirable nitrate burden at the M-004 outfall and in the storage tanks. A proposed initiative to replace nitric acid with sulfuric acid will be pursued for feasibility, not only in M Area but also for its effects to the Y Area facility. Extensive LETF renovations would be required if it is acceptable. Approximately 84 percent of nitric acid use is directly attributable to Building 313-M operations. Priority to determine the feasibility of replacing nitric acid with sulfuric acid will be impacted by Building 313-M schedules.

The total costs are estimated to be \$238,000.

Milestones:	Determine Sulfuric Acid Compatibility	12/90
	Determine Design Changes	12/91
	Establish Justification	03/91
	Permit Application	06/91
	Start Construction	06/92

The effluent waste streams from M Area to the LETF are to be characterized in order to make continual improvements in the LETF operation. The area material balance will also be improved by the potential reduction in wastes.

Further improvements in the LETF discharges will be needed to comply with the expected future permit limits. A significant modification to the Dilute Effluent Treatment Facility (DETF) is expected.

The five-year program will start in FY 90. The total five-year cost will be \$298,000 for manpower and subcontracts. Capital expenditures are expected.

Numerous small and large modification projects are scheduled for the LETF to improve efficiency and production of its polymer, chemical transfer, and dilute effluent treatment operations and associated piping. The improvements will eliminate most of the drum handling, equipment unreliability, and high maintenance requirements. In addition, the LETF control panel will be redesigned to provide graphic controllers and a better visual display of alarms and process status.

The total five-year cost is estimated to be \$11.8 million.

Milestones:

Filter Cake Slurry System

Project Authorization	06/89
Design Start	11/88
Permit Application	07/89
Construction Start	01/90
Construction End	10/90

Oberlin Filter Redesign

Project Authorization	12/89
Design Start	09/89
Construction Start	02/90
Construction End	05/90

Replace Process Sewer

Project Authorization	09/87
Design Start	09/87
Permit Application	03/89
Construction Start	01/90
Construction End	04/91

Improved Filtration

Project Authorization	09/89
Design Start	06/89
Permit Application	09/89
Construction Start	03/90
Construction End	12/90

Slurry Treatment Interim
Fixation Facility (STIFF)

Project Authorization	06/89
Design Start	08/89
Permit Application	03/90
Construction Start	11/90
Construction End	12/91

Wastewater Feed Improvements

Project Authorization	03/90
Design Start	12/89
Permit Application	03/90
Construction Start	12/90
Construction End	06/91

Graphic Controllers

Design Start	06/88
Construction Start	10/88
Construction End	06/88

Supernate Transfer & Polymer
System

Design Start	02/88
Construction Start	06/88
Construction End	06/89

SRL - TNX

TNX Operations operates one permitted wastewater treatment facility.

•**Effluent Treatment Plant**—The TNX Effluent Treatment Plant (ETP) provides treatment for all nonradioactive aqueous process effluents to ensure compliance with current regulations. The facility provides treatment by pH neutralization and effluent clarification, and includes equipment tankage, instrumentation, and extended area utilities. Startup for the plant was achieved in August 1988.

The total five-year cost is estimated to be \$919,000.

SRL - Tech Area

Tech Area currently operates a waste neutralization facility at Building 607-17A, serving the Environmental Lab 735-11A. In this facility wastewater pH is adjusted before release to Outfall A-001.

The total five-year cost is estimated to be \$89,250.

Waste Management (WM)

•**F/H Effluent Treatment Facility**—An effluent treatment facility for the F and H Separations Areas (F/H ETF) began operation in October 1988. The F/H ETF is a replacement facility for the F and H Area seepage basins, which received process wastewater from F and H Areas. The F/H ETF adjusts the process stream pH, then removes chemical and radiochemical contaminants by ion-exchange, microfiltration, reverse osmosis, and evaporation. The treated effluent is discharged through a permitted NPDES outfall to Upper Three Runs Creek.

Tank 50, which receives effluent from the ETF, is permitted separately. Operating costs are included in Tank Farm operations in Section 6.6.5, Waste Management and Disposal Practices.

The total five-year operating cost is estimated at \$48.5 million.

3.6.6.5 Planned Facilities

Defense Waste Processing Facility (DWPF)

Final disposition of DWPF process wastewater has yet to be determined.

- **Saltstone Facility (Z Area)**—Discussion and costs for this facility are found in Section 6.6.5, Waste Management and Disposal Practices.

Power Operations

- **A Area Sanitary Wastewater Treatment Facility**—All sanitary upgrades require a construction permit from the SCDHEC. The length of time which the SCDHEC spends reviewing facility design varies greatly. Therefore, schedules are based on the time required to reach milestones after receipt of the permit.

A 97,500 gallon equalization basin became operational in December 1987. The discharge to the sprayfield was diverted to outfall A-015 (January 1988) and the spray field was closed per a SCDHEC approved closure plan. A new 65,000 GPD treatment plant is in the design phase. The treatment system capacity expansion cost is \$520,000.

The total cost is estimated to be \$870,000.

Milestones:	Project Authorization	10/87
	Design Start	10/87
	Construction Start	05/89
	Construction End	10/89

- **F Area Sanitary Wastewater Treatment Facility**—The F Area treatment facility previously consisted of a 45,000 gallon equalization basin and a 60,000 GPD treatment plant. An additional 30,000 GPD treatment plant has been constructed and is in operation. This is an FY90 project with a total estimated cost of \$1 million.

- **D Area Sanitary Wastewater Treatment Facility Upgrade**—Enlarged flow capacity is needed to handle sewage flows which often exceed current design capacity. Hydraulic overloading has caused several NPDES noncompliances. Flow equalization is also needed to level out intermittent low and high flows. The existing 12,000 GPD plant will be abandoned and a new 20,000 GPD plant and 10,000 GPD equalization basin installed.

The total cost is estimated to be \$380,000.

Milestones:	Project Authorization	08/87
	Design Start	08/87
	Construction Start	12/88
	Construction End	09/89

•**Equalization Basins for CS, P, K, C, L, NF Sanitary Wastewater Treatment Facilities**—Installation of equalization basins is needed to even out low and high sewage flows which can adversely affect the performance of these facilities, resulting in NPDES exceptions. The Central Shops (CS) equalization basin will be installed first on a separate project, followed by the P, K and L Area, and Naval Fuel installations. C Area equalization basin will be installed last as a separate project.

The total cost is estimated to be \$1.9 million. CS costs are \$420,000; the others are \$300,000 per area. C Area is scheduled as a FY89 project.

Central Shops

P, L, K, C, NF Area

Milestones:

Project Authorization	10/87	Project Authorization	05/89
Design Start	10/87	Design Start	05/89
Construction Start	09/88	Construction Start	3 months after permit receipt
Construction End	01/89	Construction End	8 months after permit receipt

•**Portable Sanitary Wastewater Treatment Facility**—A portable sanitary wastewater treatment plant will be purchased to handle sudden localized increases in sewage flow due to the influx of construction or operating personnel. During reactor shutdowns, the number of people utilizing sanitary facilities can increase dramatically, causing hydraulic overloading of the sanitary waste treatment plant. This project has not yet been approved for funding and no schedule is available.

The total five-year cost is estimated to be \$750,000.

•**Upgrade D Area Neutralization/Demonstration**—This project increases the capacity of the existing neutralization system. The existing neutralization and regeneration systems are filled to capacity with the existing steam load. The increase of the steam demands on the powerhouse by the existing and planned steam lines will increase the number of regenerations of H & S units and thus exceed the capacity of the neutralization system. The neutralization system was designed to support the boiler load before the D to F steam line was built. Now a second steam line is to be built from D Area to H Area. This second line will place additional load on the existing system. If this project is not funded, there could be production outages due to the lack of steam. After the second steam line is built, there most likely will be production outages because the neutralization system cannot process the waste at the required rate, and because the storage capacity is not sufficient. If the capacity is not sufficient, this may result in violation of the site's NPDES permit limitations. This project is estimated to cost \$4 million.

•**Install Sodium Hypochlorite and Dechlorination Facilities**—These four projects will install permanent disinfection and dechlorination facilities at the sanitary treatment plants. Disinfection is required at all the effluents of the sanitary treatment plants in order to meet SCDHEC regulations. At the present time, there are temporary drip feeders being used to disinfect the waste stream with the addition of sodium hypochlorite. These drip feeders required frequent monitoring and manual adjustment to prevent the effluent from being out of limits. In addition, indications from the SCDHEC are that new limits will be imposed on the sanitary treatment plant effluents for residual chlorine. If imposed, these limits would require dechlorination of the effluent. The present system does not provide for any dechlorination. This project would install permanent, self-monitoring and self-controlling systems for disinfection and dechlorination. This project is needed for state regulatory compliance. This is a FY91 project with a total estimated cost of \$9.4 million.

SRL - Tech Area

•**SRL Low-Level Radioactive Waste Treatment Facility**—A low-level radioactive waste effluent treatment facility is planned in Tech Area for FY93. In this facility, low levels of radioactivity would be removed from the waste stream prior to their release to Outfall A-001. Costs for this facility are described in Section 6.6.5.8.

•**SRL Increase Capacity of Tech Area Sewage Lift**—This project will increase the capacity of technical area sewage lift stations and

connecting pipe systems. The existing lift stations were installed in original construction (1952) and the present volume of sewage is in excess of original design. This is a FY92 project with a total estimated cost of \$500,000.

•**Laundry Effluent Treatment Facility - F Area**—Facilities must be provided to deal with potentially contaminated laundry wastewater which handles clothing from regulated areas. This is a FY91 through FY93 project with a total estimated cost of \$10 million.

There are several facilities that will be operational in the near future:

SRL - TNX

•**Organic Removal Facility**—The Organic Removal Facility (ORF) will remove EPA priority pollutants (e.g., phenols, benzene, nitrobenzene) from wastewater generated from experimental facilities at TNX. The ORF contains feed and hold tanks, dual absorbers filled with activated carbon, filters, and sample locations for process control. This facility became operational in June 1989.

The total five-year cost is estimated to be \$319,000.

•**Process Sewer Upgrade, SRL**—This activity will replace existing aging sewer lines and bring the T Area in compliance. This is a FY 93 project with a total estimated cost of \$300,000.

•**Ion-Exchange System**—The TNX Ion-Exchange Facilities (one facility is experimental, the other is full scale) are designed to treat wastewater by ion-exchange. Its first use will be to remove mercury from wastewater generated by the Integrated DWPF Melter System (IDMS). The facility may eventually be used for other specialized water treatment. The facility receives alkaline, filtered wastewater from IDMS. It removes mercury by ion-exchange, neutralizes the water, tests for removal of mercury, and then sends the water to the ORF for removal of any organic compounds. From the ORF, the water is sent to the ETP.

The full scale facility is scheduled for a FY92 line item project with a total estimated cost of \$18.2 million. Operating costs for FY89 through FY93 are estimated to be \$2 million.

3.6.6.6 Training (Operator Certification)

The 1976 Code of Laws of South Carolina, Chapter 23, Section 40-23-140, paragraph B, requires that all employees in the operation of state-permitted water or wastewater treatment facilities must obtain State certification as a water or wastewater operator. The South Carolina Board of Certification of Environmental Systems Operators (SCBCESO) established rules and regulations for certification of operators. On July 1, 1987, SCBCESO reclassified wastewater treatment plants and operations requiring separate certifications for physical and chemical (P/C), and biological (sanitary) wastewater treatment facilities. Each grade level of certification requires successful completion of an examination and at least one year of operating experience at each of the four levels. Higher levels of certification can be obtained only in sequential order beginning with level D and followed by levels C, B, and A. All operators are also required to receive continuing education in the pertinent field in an educational institute, seminars, programs, workshops, inhouse training, correspondence courses, or any combination of the above. Further details can be found in DPSP-86-1078, *SRP Program for Certification of Water and Wastewater Operators*, in the Training/Awareness section.

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.6.7 Spill Prevention/Control/Responses

3.6.7.1 Site Program Overview

To mitigate the consequences of pollutants reaching the environment and contaminating the surface waters of the State of South Carolina, the Savannah River Site (SRS) has implemented a comprehensive spill prevention, control, and response program. Key elements of this program are as follows:

- Spill Prevention Control and Countermeasures (SPCC) Plan**—Establishes the procedures, methods, equipment, and other requirements for equipment to prevent the discharge of petroleum products from site facilities into or upon the navigable waters of the United States.

- Best Management Practices (BMP) Plan**—Establishes actions or procedures to prevent or minimize the potential for the release of toxic or hazardous pollutants in significant amounts to surface waters. The discharges controlled by BMPs are site runoff, spillage or leaks, sludge or waste disposal, and drainage from raw material storage areas. The BMP Plan is an integral part of the SRS National Pollutant Discharge Elimination System (NPDES) permit.

- SRS Procedures Manual, Item 201**—Provides sitewide specific guidance to ensure the timely and accurate reporting of spills to the Environmental Protection Section (EPS) and/or the Department of Energy (DOE), the Environmental Protection Agency, and the South Carolina Department of Health and Environmental Control (SCDHEC), as appropriate.

The SRS Hazardous Material Response Team is on duty 24 hours a day to assist facility custodians whenever a spill or release of nonradioactive liquids occurs and the facility custodian cannot cope with the spill/release. Most of the facility custodians have determined flow paths of sewer manholes or other liquid effluent drainage paths to final destinations. The remaining custodians are currently updating the flow path information on

new or old facility systems. The SRL Environmental Technology Section (ETS) is developing a model to assist in determining the consequences of a spill, whether into the ground or to a surface runoff.

Facility custodians have initiated projects for upgrading of containment systems that enhance spill control and prevention of hazardous, toxic, oil, or oil-related products.

The total cost of the Spill Prevention/Control/Responses program for the five-year planning period is estimated to be \$36 million including 31 man-years of effort.

3.6.7.2 Justification/Regulatory Requirements

Executive Orders

•**Executive Orders 11988 and 11990**—These Executive Orders obligate the DOE to avoid, or minimize to the extent practicable, any short- and long-term adverse impacts to floodplains and wetlands.

Federal Laws

•**Federal Water Pollution Control Act (Clean Water Act of 1977)**—The Code of Federal Regulations (CFR), as authorized by Section 304 of the Clean Water Act, specifically address the control of runoff, spillage, and leakage of hazardous and toxic pollutants (40 CFR 125.100). Industries handling or discharging any toxic or hazardous pollutants are subject to requirements relative to all activities which may result in significant amounts of pollutants reaching surface waters in the United States. In addition, 40 CFR 125.103 states that BMP shall be incorporated into a NPDES permit.

40 CFR 112.3 requires a Spill Prevention Control and Countermeasure (SPCC) Plan to address oil pollution prevention.

State Permits

•**SCDHEC NPDES Permit (SC0000175)**—Item 2, Part III, of the SRS NPDES permit issued January 1, 1984, directed the SRS to prepare a Best Management Practices Plan to identify and control the discharge of hazardous and toxic substances listed in 40 CFR Part 117 and Tables II and III of Appendix D to 40 CFR Part 22.

The comprehensive spill prevention, control, and response program, utilizing the site BMP/SPCC Plans and the area/facility-specific documents and procedures, achieves the following objectives set forth in Section 3.4: compliance with the items listed above, maintenance of Class B stream quality, and maintenance of spill prevention/control/response capability with facility and Spill Response personnel.

3.6.7.3 Organizational Responsibilities Summary

In response to the regulatory requirements and NPDES Permit SC0000175, the site has prepared documentation that satisfies the requirements of a BMP and a SPCC Plan. Construction Management adheres to the facility custodians documents affecting the area in which their personnel are working or stationed.

Each facility custodian is responsible for implementing the requirements of the plant through documented administrative controls or via the BMP/SPCC plans and projects. Facility custodians must upgrade or add containment systems for certain areas handling hazardous, toxic, oil, or oil-related products. Each facility custodian is responsible for achieving immediate interim spill response by storing spill containment materials in strategic locations for timely capability. Each facility custodian has assigned personnel to summon the Hazardous Material Response Team as needed. Each facility custodian has the responsibility to provide spill/reporting training to pertinent personnel. Each facility custodian ensures that immediate reporting of spills occurs via facility administrative procedures, SRS Procedures Manual-Item 201, or through the use of the SPCC/BMP Plans. The Spill Coordinator in the EPS has the responsibility to interface with the custodians and DOE; the coordinator reports reportable spills to the DOE. SRS Fire Department and Central Services Works Engineering Response Teams have the responsibility to provide assistance for spill control and cleanup 24 hours a day as needed. The team leaders have the responsibility of maintaining trained units while drawing on Safety, Environmental Monitoring Section, and EPS for technical expertise.

3.6.7.4 Best Management Practices/Spill Prevention, Control, and Countermeasures Plans

The Savannah River Site responded to the regulatory requirements and Part III of SRS NPDES Permit SC0000175 and prepared SPCC Plans.

Construction Management follows the plans in the areas where their personnel are located. The SRS SPCC Plans were reissued as an official document, DPSP-87-1083. The BMP Plans will be reproduced and updated by a subcontractor for the EPS on an annual basis. The facility custodians will provide data to the EPS coordinator for transmittal to the subcontractor for inclusion in the revised BMP Plan. It is anticipated the next revision of the BMP Plan will be available by August 1989.

3.6.7.5 Facilities Operations

Spill Control

Facility custodians have surveyed their areas for additional operations or equipment requiring enhanced spill control systems. Those operations or equipment requiring modifications have been listed in the SPCC/BMP Plans and will be included in current and future SRS budgets. Typical environmental projects affecting spill control include diking diesel fuel storage areas, diking hazardous waste staging and satellite staging areas and truck unloading pads. For additional information refer to the SPCC/BMP Plans and Section 3.6.7.6, Construction Projects. Spill control procedures and other allied procedures are listed in Attachment 3.2, Facility Compliance/Surveillance Procedures for BMP/SPCC Plans.

Spill/Release Reporting

All facility custodians report spills or releases to the EPS Spill Coordinator as soon as possible after a spill/release occurs (usually within 1 hour). The designated Emergency Coordinator or facility custodian makes the initial verbal report to the EPS Spill Coordinator as outlined in the SPCC/BMP Plans or facility procedures and provides the requested information. The site Hazardous Materials Response Team is activated upon request of the facility, Technical Support Center (TSC), or EPS Spill Coordinator. The EPS Spill Coordinator reports the reportable spills to the SCDHEC via DOE concerning the spill/release. A more detailed formal report of the spill/release is forwarded to the EPS Spill Coordinator by the SRS facility custodian. Reporting of spill/releases are processed similarly within the SRL complex in compliance with the SRL Procedures Manual. Spill/release reporting procedures with other allied procedures are listed in Attachment 3.2, Facility Compliance/Surveillance Procedures for BMP/SPCC Plans.

•**Environmental Protection Section (EPS)**—The EPS Spill Coordinator's role is to receive and document all spills at the SRS and

immediately notify management and the DOE as required. If necessary, the Spill Coordinator inspects the spill site and assists the custodian in determining the proper cleanup procedure. The Coordinator with other environmental experts will assess the spill and determine if the spill is reportable to the DOE, SCDHEC and Environmental Protection Agency (EPA) under the reporting guidelines. The Coordinator will also escort DOE, SCDHEC and EPA personnel on initial and followup inspections of the spill site and provide written reports as appropriate. Reporting criteria for the EPS are based on three established rules:

- South Carolina Hazardous Waste Management Regulations
- Section 311 of the Clean Water Act
- Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) proposed reportable quantities.

All reportable spills at the SRS are reported to the DOE, which determines if other regulatory agencies are to be notified. The EPS Spill Coordinator will immediately notify the DOE of any Superfund reportable spills occurring on plant property. The DOE will notify the EPA and National Response Center.

The SRS experienced two Superfund spills in 1985, two in 1986, and no spills in 1987 and 1988. The charter of an elite Spill Response Team in 1985 has enhanced the ability of SRS custodians to mitigate environmental impacts at the SRS.

The EPS is also responsible for ensuring sitewide compliance with the SRS SPCC Plan.

The total five-year cost is estimated to be \$148,750.

•Environmental Monitoring Section (EMS)—In the case of a radioactive release or spill, the EMS collects and analyzes samples as soon as possible and notifies the EMS to perform additional sampling. The EMS emergency procedures are in DPSOL 179-1. The EMS also assists production in locating the source of the release and terminating the release. In the case of a nonradioactive spill such as oil, the EMS has a member on the Spill Response Team who serves primarily as a technical advisor.

The EMS collects samples for analysis to determine the extent of the spill and reports the data to the EPS.

Spill Response Capability

Custodians are responsible for containing spills in their respective facilities. Each SRS facility custodian has established stores of supplies and/or hand tools in strategic locations near potential sources of spills/releases to minimize, control, and contain the release. These strategic supplies can include such items as shovels, buckets, sandbags, absorbent materials, and other materials necessary to effectively contain any spill at that location. Some facility custodians are increasing their capabilities by purchasing additional supplies. Facility custodians use the BMP/SPCC Plans, SRS Procedures Manual Item 201, or documented departmental/ facility procedures to augment their spill response capability. The BMP/SPCC Plans have sketches and flow diagrams indicating the direction of storm sewer flows. Area storm sewer, sanitary, process, chemical, domestic water, etc., lines are also shown for all SRS facilities in DPSP 81-1045, Rev. 8/82, *Savannah River Plant Area Drainage Maps*, as an aid to spill response capability. The drainage maps have been updated by the facility custodians and are currently being revised. Facility spill response procedures and other allied procedures are listed in Attachment 3.2, Facility Compliance/Surveillance Procedures for BMP/SPCC Plans.

•Spill Response Personnel Fire Department and Central Services Works Engineering (CSWE)—The SRS has two completely trained and equipped teams to respond to environmental spills, Fire Department's Hazardous Material Response Team and the CSWE Spill Busters. Their role is to contain and cleanup accidental spills which have the potential to result in a significant impact on the environment. SRS custodians are responsible for cleanup of minor spills that occur within their respective areas.

On November 14, 1988, the Fire Department assumed responsibility for responding to environmental spills on all shifts. This service was previously provided by CSWE on day shifts and Fire Department on off shifts. This change is being made to streamline site spill notification and response assignments.

The emergency response personnel have received training as required by applicable federal regulations. Thirty-seven CSWE and thirty-three Fire Department employees have completed a 24-hour Emergency Response Course. In addition, twenty-five CSWE employees have completed a 40-hour Health and Safety for Hazardous Waste Operations course. Six Fire Department supervisors have completed an additional 8-hours of specialized training on hazardous waste containment and cleanup.

The CSWE Spill Busters are equipped with a trailer that contains oil booms, absorbant pads, Scott Air-Packs, rope, handtools, Class A response protective clothing, and various other specialized equipment. They also have boats for access to spills that reach waterways, and backup heavy equipment such as backhoes and dump trucks.

The Fire Department has support from their fire trucks and a special response van and trailer that is equipped with the same type of gear that the Spill Busters have. Additionally, the Fire Department is supported by a high technology computer system that will give them on the spot guidance for any type of chemical spill.

The Spill Response Van Trailers are available to go to the scene of the spill, setup a barricaded safe area for work, monitor for radioactivity, provide lighting, and protect participating personnel. Larger amounts of supplies are stored and available as well as four boats, motors and trailers, and a four-wheel-drive vehicle. Greater detail on the Spill Team equipment and supplies can be found in DPSP-87-1083, *Spill Prevention Control and Countermeasures Plan*. Construction is committed to providing any of their equipment for their own spill/release use or to augment SRS requests for additional equipment.

The Spill Team personnel must be certified by meeting the training requirements set forth in OSHA Standard 1910.120 (e). Minimum requirements are:

- Receive 40 hours of training
- Experience three days of actual field cleanup experience under the supervision of trained experienced supervision
- Receive special training for unique hazards
- Obtain certificate of training
- Undergo eight hours of annual refresher training.

Site management and supervisors coordinating spill cleanup activities receive the preceding training and at least eight hours of specialized training on managing such operations. The Spill Team is currently able to participate in the field cleanup experience training. Detailed descriptions of the training are provided in the manual *Oil and Chemical Response Guidelines for SRS Spill Team* and DPSP-87-1083.

The total five-year cost is estimated to be \$430,000. The team plans to purchase a new trailer, boat, and vehicle within the five-year period. The

annual replacement cost for absorbents and containment booms is \$30,000.

Construction Management—Construction Management does not have any formal spill response procedures. Various memoranda and training materials have been issued to Construction personnel explaining their responsibilities.

The total five-year implementation and monitoring cost is estimated to be \$446,250.

SRL - Equipment Engineering Section - Robotics (EES)—An emergency response capability based on flexible and diverse fleet of mobile robotics and associated equipment such as video, sensors and manipulator arms is being developed within the Robotics Development Group of EES. The capability now exists to respond on short notice with various sized wheeled and tracked vehicles and appropriate mission modules to fit the task. The group has its own transporting vehicle and a facility to stage the equipment and maintain it. A new versatile tracked vehicle and manipulator arm were acquired in 1988. Additional mission modules and refined capabilities will be added in 1989 and efforts to increase survivability in a radiation environment are progressing. The group will be working to integrate equipment into the site emergency response system this year so that those trained in these activities will be aware of and ready to use the remote capability provided.

The total five-year cost is estimated to be \$1.7 million. No capital funds are anticipated for FY89.

3.6.7.6 Construction Projects

The projects in this section were initiated as a result of the SPCC/BMP Plans or through recommendations from internal environmental audits. The projects are an integral part of the SRS effort to reduce the potential for environmental pollution and to abide by the intent of environmental regulations. With the installation of the following and similar facilities, the plant will meet the commitments of the Best Management Practices Plan required by the South Carolina NPDES Permit SC0000175.

Power Operations—The following Power Operations projects will provide improved spill containment:

- Upgrade Softener Building and Spill Containment, Bldg 483-D, FY92, \$440,000. This project will provide spill containment diking for the H&S Tanks at the water treatment facility.

Milestones: Project Authorization	01/92
Design Start	09/91
Construction Start	01/93
Construction End	06/94

- Upgrade Softener Building and Spill Control, PKH, FY91, \$600,000. This project will provide spill containment diking for the demineralization systems in P, K and H Areas.

Milestones: Project Authorization	06/90
Design Start	01/90
Construction Start	01/91
Construction End	01/92

Reactors—Future projects include the following:

- An \$800,000 project in FY90 that provides state-of-the-art secondary containment for aboveground fuel oil storage tanks.

Milestones: Project Authorization	06/90
Design Start	08/90
Construction Start	02/91
Construction End	08/92

- A \$250,000 project in FY91 for fuel oil unloading pads near the aboveground fuel oil storage tanks.

Milestones: Project Authorization	06/91
Design Start	08/91
Construction Start	01/92
Construction End	06/93

- Environmentally safe underground diesel fuel storage tanks as a FY90 line-item, Extended Diesel Engine Operation. The cost is \$20 million.

Milestones:	Project Authorization	02/90
	Design Start	02/90
	Construction Start	08/90
	Construction End	09/92

- A 25,000-gallon storage tank in each area to temporarily store sodium polyborate during long reactor outages. This is an FY91 project with a cost of \$1.5 million.
- Diking around the Heavy Water Department's wastewater storage tanks and the D₂O storage facilities.

Cost for the storage facility diking in D Area and R Area is \$103,000 (operating).

Milestones:	Project Authorization	01/90
	Design Start	01/90
	Construction Start	06/90
	Construction End	12/90

- A part of the FY87 line-item, Environmental Protection Plantwide, titled Waste Liquid Collection and Drum Storage will provide a facility at each of the 105 Buildings for temporary storage and handling of contaminated waste liquid. The total estimated cost is \$1.4 million.

Milestones:	Construction Start	1988
	Construction End	1989

- A Contaminated Water Handling Installation within each 105 Building will provide a means of reducing the waste water drum handling and temporary storage of the waste liquid. The cost of this project is \$990,000.

Milestones:	Construction Start	1988
	Construction End	1989

Separations—Future projects include the following:

- An FY83 line-item, Nonradioactive Waste Management, provided enhanced spill containment (dikes) at Separations facilities. Part III for the project was \$580,000.

- An FY87 line-item project, Environmental Protection Plantwide, will provide spill control for regulated areas of 211-F/H. The project total estimated cost (TEC) is \$2.0 million in FY87 funding.

Milestones:	Project Authorization	09/87
	Design Start	07/87
	Construction Start	03/88
	Construction End	06/89

- An FY90 line-item project, Improved Segregated Water Delaying Basin, will provide positive control over high-level tank cooling water effluent after a radiation alarm sounds by diverting the effluent to one of two delaying basins for sampling analysis.

The total capital cost is \$6 million.

Milestones:	Project Authorization	12/90
	Design Start	09/90
	Construction Start	09/91
	Construction End	12/93

- A capital project will provide dike and sump at Slurry Receipt Tank unloading station.

The capital project cost is \$75,000.

Milestones:	Project Authorization	01/89
	Design Start	10/88
	Construction Start	03/89
	Construction End	05/89

- The Bulk Storage Facility, 222-F, project will provide a design for a bulk storage tank facility to hold a 16 percent solution of hydroxylamine nitrate (HAN). An unloading pump and associated piping is required for receipt of material from a vendor's tractor trailer. A transfer pump and piping is required for receipt of material from vendor's tractor trailer. A transfer pump and piping is required for moving material to tanks 221 and 271. A capacity of 150,000 lb is required. HAN is used as a chemical additive for 221-F first and second cycle operations. Currently HAN is received in 55 gallon drums (495 net lb) and an inventory of 125 to 150 drums is required to ensure uninterrupted operation of 221-F. The drums cause a handling and storage problem. A more efficient and safe method would be to meter the HAN into tanks 221

and 271 from a bulk storage tank as are all other liquid chemicals presently use at 222-F. This is a FY93 project with a total estimated cost of \$250,000.

SRL-TNX—Future projects include the following:

- The SRL Chemical Storage Expansion, Building 674-T, will provide additional indoor storage space for raw chemicals to be used for research purposes. Currently, space is limited, and much of this material must be stored outdoors, increasing the likelihood of damage to the drums which could lead to a spill to the environment. This is a FY91 project with a total estimated cost of \$250,000.

Milestones:	Basic Data	FY91
	Basic Data Routing	FY91
	Project Authorization	FY91

3.6.7.7 Research/Studies

SRL - Environmental Technology Section (ETS)

The ETS is developing a model to assist in determining the consequences of a spill at the SRS. Initially, the model will be able to determine the primary pathway of a pollutant (down into the ground or surface runoff) and to which surface stream. The model development was delayed until the summer of 1988.

The total five-year cost is estimated to be \$89,250.

3.6.7.8 Monitoring (Compliance)

The facility custodians, using documented procedures, inspect their storage areas and tanks at least on a weekly basis to ensure their compliance with federal and state regulations and operating contractor directives; some facilities are inspected more frequently. Compliance and surveillance procedures and other allied procedures are listed in Attachment 3.2, Facility Compliance/Surveillance Procedures for BMP/SPCC Plans. This is generally accomplished by recording of deficiencies (if any), followup corrective action, and documenting and archiving the procedure for three years. The documented procedures are kept available for the SCDHEC and regulatory review. Several of the site safety audits have been expanded to include environmental concerns

such as spill control. The audits enforce management directives that facility custodians comply with the regulations.

In addition to internal audits of compliance, audits are conducted by the DOE, SCDHEC, and EPA on a less frequent basis. Audits range from documentation checks down to and including field inspections. The response capability of the Spill Response Team has also been tested by an unannounced mock run for a regulatory group.

Routine inspections are conducted by operating personnel. Procedural training is provided annually. Records are maintained for three years in each facility. Physical controls are also used to ensure compliance.

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.6.8 Radiological Effluent Management

3.6.8.1 Site Program Overview

To keep annual radioactive releases as low as reasonably achievable (ALARA), the Savannah River Site (SRS) adopts annual radiological release guides for the site and for each facility with radioactive releases. The Environmental Monitoring Section (EMS) has primary responsibility for establishing the annual site release guides. Operating departments assist in the development of facility release guides. Radioactive release guides are based on operating experience and are set at low levels so that any significant increase from normal releases are brought to the attention of SRS management. Development of release guides are based on forecasted production schedules, new facility installations, and past performance. The new facilities, as they come online, may have adjustments made to the guides based on actual operating data. Since these ALARA Guides are a mechanism to alert management, 6-12 percent of the guides are expected to be exceeded if they are set correctly. The release guides are set well below any regulatory limits.

Tritium is the primary radionuclide of concern, although cesium-137, strontium-90, and other radionuclides are released in small amounts. One objective for the site is to keep tritium releases from SRS operations in Savannah River water below the EPA drinking water standard of 20 pCi/mL. The two drinking water treatment plants downriver from SRS in 1988 had a high of 4.0 pCi/mL, which is only 20 percent of the EPA standard.

The amount of tritium in the F/H ETF effluent will vary with the type of irradiated fuel being processed in the canyon buildings. The F/H ETF waste stream will be an undecayed addition to the Savannah River tritium level concentration. The waste stream is expected to add several pCi/mL to the average concentration in the river. It is anticipated the waste stream would add an additional average low of 2.2 pCi/mL and a high of 11.0 pCi/mL to normal river flows; or an additional average low of 3.1 pCi/mL and a high of 15.3 pCi/mL at a 7Q10 river flow (7Q10 means the lowest consecutive 7-day flow in 10 years). A study on concentrating tritiated

high-activity waste evaporator overheads in Separations Canyon buildings will continue to determine the feasibility of making process changes should river tritium concentrations be higher than expected from the F/H Effluent Treatment Facility.

Total cost for the Radiological Effluent Management program is \$48 million for the five-year planning period including 217 man-years of effort.

3.6.8.2 Justification/Regulatory Requirements and Site Policy

The site policy is to control radiological releases to ALARA. The plant goal is to provide ALARA guides which are about one percent of the Department of Energy (DOE) dose limit of 100 mrem/year on an annual basis and are lower than DOE limits. The radiological effluent management program meets the following objectives set forth in Section 3.4: the EPA limit for tritium concentration for drinking water in the Savannah River, the SRS annual guides for releases, and the reporting of findings to the public via the annual environmental monitoring report.

DOE Orders (HQ/SR)

•**DOE ORDER 5480.4; SR ORDER 5480.4**—The radiation standards for the protection of the public in the vicinity of the SRS are given in DOE Order 5480.4.

3.6.8.3 Organizational Responsibilities Summary

The Manager, Environmental Monitoring Section (EMS), heads the Plant Release Practices, Guides, and Monitoring Committee, which annually reviews draft copies of the facility custodian's proposed radioactive release guides and sets them for the following year. Each facility custodian will review monthly data for trends and take corrective action where necessary. Each facility custodian reviews the release guides during the year whenever production schedules change or a new facility is preparing to start operations.

3.6.8.4 Programs

Annual Release Guides

•**Environmental Monitoring Section (EMS)**—The EMS has primary responsibility for establishing the annual radiological release guides for the site. The Manager, EMS, is chairman of the Site Release Practices, Guides, and Monitoring Committee, which reviews guides and sets new guides annually. These guides are documented in DPSOP 40, *Savannah River Site Radiation and Contamination Control*.

Calculated releases derived from sample analyses are compared to the guides on a monthly basis. Releases that exceed the prorated guides are investigated and reported to management. The EMS reviews the data to assess trends in releases from site facilities.

The total five-year cost for the development and administration of the release guides is estimated to be \$720,000.

•**Raw Materials (RM)**—RM currently has radiological release guidelines for uranium at NPDES Outfall M-004. The release guidelines are based on a uranium toxicity study conducted in 1985. The release guidelines will be reviewed prior to the reissuance of the NPDES permit in 1989 to ensure the concentration guidelines protect human health and the environment.

The total five-year cost is estimated to be \$5950.

•**Reactors**—An *ad hoc* committee within Reactors develops the annual release guides for reactor operation. The committee recommendations are reviewed by the 100-Area Environmental Committee and are submitted to the Site Release Practices, Guides, and Monitoring Committee for final review and inclusion in DPSOP 40. Notifications are issued for all radioactive releases in excess of annual guides.

The total five-year cost for developing and monitoring surface water release guides is estimated to be \$5950.

•**Separations**—Separations chairs a committee that develops facility radioactive release guides for the 200 Areas. The committee consists of representatives from departments that have facilities in F or H Areas. The committee recommendations are submitted to the Site Release Practices, Guides, and Monitoring Committee for final approval. Data is reviewed monthly to assess trends.

The total five-year cost is estimated to be \$5950.

•**SRL - Tech Area**—Annual release guides for SRL facilities are developed by the SRL Environmental Subcommittee. The committee recommendations are submitted to the Site Release, Practices, and Monitoring Committee for final approval. Data from samples are reviewed monthly to assess trends.

The total five-year cost is estimated to be \$5950.

•**SRL - TNX**—TNX has radiological release guidelines for the new TNX seepage basin. The release guideline is established annually by the SRL Environmental Subcommittee. The committee recommendations are submitted to the Site Release, Practices, and Monitoring Committee for final approval. Samples are analyzed monthly and calculated releases are determined by the EMS. The data are reviewed monthly to assess trends. The total five-year cost is estimated to be \$2975.

•**Tritium**—Investigations are implemented as needed to ensure that radiological release guides are being met by Tritium facilities. Tritium facilities contribution to the tritium content in effluent surface waters is very small, so action is normally not necessary.

The Tritium Department works to comply with annual release guides, developed by the Separations Department, for wastewater to the H Area seepage basins and plant streams.

The total five-year cost is estimated to be \$5950.

3.6.8.5 Facilities Operations

WM controls the amount of radiological effluent to surface water by using the following procedures:

DPSOL 241-FH-706	<i>Regulating Water Level in Retention Basins, Building 281-8 F&H</i>
DPSOL 241-FH-720	<i>Pumping Retention Basin Water to Seepage or to Four Mile Creek</i>
DPSOL 241-FH-740-Q	<i>In-Line Storm Water Monitors</i>
DPSOL 241-FH-741	<i>Diversion of Storm Water</i>

The F/H ETF contributes an average tritium concentration of 64,000 pCi/mL to Upper Three Runs Creek. See Section 3.6.6.4 for additional information.

3.6.8.6 Construction Projects

Reactor

•**Heat Exchanger Replacement**—In each reactor facility, cooling water is pumped through 12 heat exchangers at the total rate of approximately 175,000 gallons per minute. The effluent is pumped to either plant streams, PAR Pond, or L Lake depending on the facility. Minor leakage within the heat exchangers results in very low levels of tritium released to the effluent streams. Leakage rates are specified which require increased sample frequency and/or heat exchanger replacements. Older heat exchangers are being replaced at the rate of one to two per year on an as-needed basis.

The capital cost for each heat exchanger is \$1.2 million. Reactor manpower cost for the heat exchanger replacement is \$33,850 per heat exchanger.

The replacement schedule and associated costs for the next five years are predicated on the failure rate of the heat exchangers, which is indeterminate. It is expected, however, that five heat exchangers would be replaced by 1993, averaging one per year. The average cost for installation of a new heat exchanger would be \$1.23 million.

Each reactor area and the Heavy Water Rework Facility discharge approximately 1.6×10^9 and 6.1×10^8 gallons of water per year, respectively, into a process sewer. The effluents are monitored under the site radioactive release guide program. The process sewer instrumentation includes a continuous sampler that provides total effluent radioactive release data. ALARA release guides, when exceeded, are investigated and corrective actions taken.

Radiological effluents which do not meet the requirements for discharge to the process sewer or the reactor seepage basins are shipped to the Separations Area evaporators.

Separations

•**Detritiation of Effluent Streams 200-F/H**—Tritium in effluent streams in F & H Area result in tritium releases to the environment. The ETF does not have tritium removal capabilities. The project may be required in the future by the regulatory agencies. This is a FY93 line-item project with a total estimated cost of \$25 million.

Waste Management

•**Stormwater Runoff**—The WM Tank Farm Stormwater runoff is monitored for radiological activity and diverted to retention basins if activity is detected. Two WM employees are assigned to this work. The stormwater is also directed to the retention basins as a precaution during transfers. This is an FY90 capital project with a total estimated cost of \$1 million.

•**Retention Basin Liners, F**—This project is to install new liners in F Area Retention Basins to improve integrity and reliability and minimize risk of releases to the environment. This project is necessary for environmental compliance. This is a FY92 project with a total estimated cost of \$1.2 million.

•**Retention Basin Liners, H**—This project is to install new liners in H Area retention basins to improve integrity and reliability and minimize risk of releases to the environment. This project is necessary for environmental compliance. This is a FY91 project with a total estimated cost of \$1.2 million.

3.6.8.7 Research/Studies

DOE Interim Stream Ecology Radiation Dose Limit

•**Environmental Monitoring Section**—The EMS is currently performing analyses to demonstrate compliance with the DOE interim dose standard of one rad per day to aquatic biota present in onsite effluent streams. The EMS also needs to show compliance for the radioactivity analyses of surface water and sediments which are routinely performed by the EMS.

The EMS supplies these data to the SRL - Environmental Technology Section for calculation of dose to the onsite aquatic biota.

The total five-year cost is estimated to be \$148,750.

•**SRL - Environmental Technology Section (ETS)**—The ETS will continue the studies related to the transport of radionuclides in the site streams and surface impoundments into the Savannah River. Studies related to the remobilization of radionuclides from the Steel Creek corridor will also be continued.

The total five-year cost is estimated to be \$11,900.

After data are collected for approximately one year and compliance is demonstrated and documented, it is expected that the number of analyses currently performed can be reduced.

•**SRL-Analytical Development Section (ADS)**—The ADS developed an improved online alpha monitor (OLAM) during 1988. The improved monitor was developed for use in the cooling water streams discharged from the separations areas. The new low-level alpha monitor has been undergoing testing in the segregated water system in F Area since April and proved its superiority to the existing monitor system. The new OLAM gave more reproducible response to repeated source checking over the extended test period and, due to almost trouble/maintenance free operations, provided more online time than the existing system.

The ADS will provide an engineered package in 1989 to replace the existing alpha monitors in the F & H Area cooling water systems with the new OLAM. The OLAM will be tested in a canyon building evaporator overheads monitoring application. Assistance will be provided to the USF team for the design and procurement of five OLAM systems; assistance may include fabrication and assembly of the systems. Tests of the OLAM for use in stack monitoring will be performed.

The total five-year cost is estimated to be \$611,900.

•**Separations**—A proposed test program to concentrate tritiated High-Activity Waste (HAW) evaporator overheads in H Area canyon building has been deferred until the F/H ETF has been started. The program would be to make beneficial use of the concentrate, such as in the canyon dissolver. Alternatively, the concentrate will be immobilized in saltcrete. Baseline data are currently being accumulated on canyon streams and tritium leaching from saltcrete. If the program is successful, the tritium being released to the river would be decreased.

Manpower costs for FY89 are \$19,900.

3.6.8.8 Release Guide Monitoring

Environmental Monitoring Section (EMS)

The EMS conducts an extensive radiological environmental monitoring program. Environmental samples are submitted to the EMS facilities in 735-A. Data generated are used to determine radioactive releases to plant streams and the Savannah River. Data are published in monthly radioactive releases reports and in the annual environmental report (WSRC-RP-Year-59-1).

Liquid effluents analyzed by the EMS include site streams and facility effluents.

An inventory of tritium released to the Savannah River is calculated and included in the annual environmental monitoring report.

Samples are routinely collected and analyzed from two water treatment plants located downriver of the SRS. Doses to persons consuming the water are calculated and reported by letter to the water treatment plant management on a quarterly basis as well as included in the annual environmental monitoring report.

Additional environmental monitoring programs are initiated by the EMS for special studies of unplanned radioactive releases.

The total five-year cost is estimated to be \$11.6 million for environmental monitoring programs.

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.6.9 Wetlands

3.6.9.1 Site Program Overview

The sitewide program to address onsite wetlands protection is the Environmental Evaluation Checklist System. All Savannah River Site (SRS) departments are required to submit a Checklist (OSR Form 14-347) for any project that meets the site criteria. The Savannah River Ecology Laboratory (SREL) and other onsite contractors are required to initiate similar documentation to the Department of Energy (DOE) for any project that meets the site criteria. The National Environmental Policy Act (NEPA) Activities group reviews each SRS-generated checklist and determines the significance of the environmental impact, including the impact on wetlands. If the impact on wetlands is not clearly insignificant, it may be determined that a wetlands assessment is necessary. The NEPA Activities group coordinates the assessment and uses the results in preparing the required NEPA documentation.

The total cost of the Wetlands Protection program for the five-year planning period is \$764,000 which includes about 13 man-years of effort.

3.6.9.2 Justification/Regulatory Requirements

Executive Orders

•**Executive Order 12088**—This Executive Order requires federal agencies to comply with applicable administrative and procedural pollution control standards established by federal laws.

•**Executive Orders 11988 and 11990**—These Executive Orders obligate the DOE to avoid, or minimize to the extent practicable, any short and long-term adverse impacts to floodplains and wetlands.

The sitewide wetlands protection program meets the following objectives set forth in Section 3.4: compliance with regulatory requirements, informing the public, and minimizing wetland losses from SRS operations.

3.6.9.3 Organizational Responsibilities Summary

The EPS has administrative oversight responsibility for the Wetlands Protection Program. The SRS facility custodians are responsible for using the Environmental Evaluation Checklist System if any of their research, studies, new installation waste streams, or significant changes in established waste streams have the potential to impact wetlands. Site Use Permits are required by all SRS facilities that are enlarging their activities to include more land use. Prior to any dredging or filling at navigable streams, a Section 404 Permit must be attached. The EMS is responsible for performing periodic radioactivity surveys in the Savannah River swamp on the South Carolina side. The EMS also schedules comprehensive surveys of the swamp by the Academy of Natural Sciences of Philadelphia (ANSP) on a five-year frequency.

3.6.9.4 Programs

404 Permit Dredging and Filling

•**Construction**—Construction will depend on the appropriate operating department to obtain the 404 Permit for dredging and filling construction work authorized by the department.

The total five-year cost is estimated to be \$595,000.

•**Environmental Protection Section (EPS)**—The EPS assists custodians with 404 Permits as needed. In the future, the EPS proposes to have a more active roll in Wetlands Protection. The total five-year cost is estimated to be \$59,500.

3.6.9.5 Research/Studies

SRL - Environmental Sciences Section (ESS)

The release of heated effluents from SRS production reactors and D Area powerhouse eliminates some cypress-tupelo swamp forest canopy in the onsite swamp. The relative roles of temperature, sedimentation, and flooding, though not known completely, continue to be researched and assessed by the ESS. The commitment to undertake wetlands protection investigations originated with the Environmental Impact Statement for the restart of L Reactor and associated support documents. Although no additional studies are currently planned, the

ESS will provide the technical support for future 404 Dredge and Fill investigations as deemed necessary.

The total five-year cost is estimated to be \$59,500.

3.6.9.6 Compliance Monitoring

Environmental Monitoring Section (EMS)

The EMS performs annual surveys of the swamp to determine if radioactivity in the swamp is migrating. A comprehensive survey is made of the swamp every five years by the ANSP. Data are reported in the annual environmental report.

The total five-year cost is estimated to be \$50,000.

3.0 SURFACE WATERS AND WETLANDS PROTECTION

3.7 Resource Requirements

The manpower and operating funding requirements for the Surface Waters and Wetlands Protection program are shown in this section for FY89 through FY93. Capital costs are escalated and include manpower requirements. The manpower, operating, capital, and total cost schedules for each issue are presented in Tables 3.7.1 through 3.7.4. Similar cost schedules are presented for each department in Appendix Tables 3.7.1A through 3.7.4A.

Total funding requirements over the five-year planning period are \$385 million. Manpower requirements (Monthly Salary and Local Roll) are about 431 man-years and 585 man-years, respectively. The Power Department capital requirements include an estimated \$9.4 million expenditure for dechlorination facilities that may be required. The Reactors Department requirements included an estimated \$127 million for a recirculating cooling tower for K Reactor effluent water.

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
3.0 SURFACE WATERS AND WETLANDS
3.7 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 2 of 5

SURFACE WATERS/WETLANDS PROTECTION PROGRAM

3.7 RESOURCE REQUIREMENTS

ISSUE	FY 89		FY 90		FY 91		FY 92		FY 93		TOTAL	
	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR
3.6.1 STREAM MANAGEMENT	122	10	152	10	226	20	226	20	226	20	952	80
3.6.2 THERMAL MITIGATION	550	70	484	52	456	72	431	72	431	72	2350	336
3.6.3 NPDES	408	397	652	417	691	417	691	417	691	417	3133	2066
3.6.4 RIVER MONITORING	80	32	80	32	80	32	80	32	80	32	402	160
3.6.5 EROSION CONTROL	113	240	158	240	158	240	158	240	158	240	744	1200
3.6.6 WASTEWATER TREATMENT	2297	2870	2505	2870	2416	2870	2358	2870	2207	2870	11781	13350
3.6.7 SPILL PREVENTION/CONTROL	226	96	226	96	226	96	226	96	226	96	1131	480
3.6.8 RADIOLOGICAL EFF. ASSESSMENT	923	1144	887	1136	887	1136	887	1136	887	1136	4471	5688
3.6.9 WETLANDS	131	10	148	10	148	10	148	10	148	10	714	50
TOTAL	4848	4869	5290	4663	5245	4693	5201	4623	5053	4693	25676	23410

* VALUES ARE THOUSANDS OF FY88 DOLLARS.

**ANNUAL MANPOWER COSTS BASED ON: MS = \$59.5M (SR5); LR = \$40M (SR5).

TABLE 3.7.1 MANPOWER REQUIREMENTS SCHEDULE (\$M)*,**

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
3.0 SURFACE WATERS AND WETLANDS
3.7 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 3 of 5

SURFACE WATERS/WETLANDS PROTECTION PROGRAM

3.7 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
36.1 STREAM MANAGEMENT	100	150	125	0	0	375
36.2 THERMAL MITIGATION	4149	3321	2351	1871	861	12353
36.3 NPDES	10	3010	3010	10	10	6052
36.4 RIVER MONITORING	213	213	213	213	213	1066
36.5 EROSION CONTROL	281	281	281	281	281	1403
36.6 WASTEWATER TREATMENT	10418	11713	12813	14813	14013	63572
36.7 SPILL PREVENTION/CONTROL	180	1083	1280	820	700	3863
36.8 RADIOLOGICAL EFF. ASSESSMENT	1111	511	1711	1711	511	5555
36.9 WETLANDS	0	0	0	0	0	0
TOTAL	16463	20282	21584	19318	16589	94238

* COST ITEMS FOR PROGRAMS, OPERATING COSTS, RTA'S, SAMPLING, ETC., ARE EXPRESSED AS THOUSANDS OF FY89 DOLLARS. THESE COSTS DO NOT INCLUDE MANPOWER COSTS.

TABLE 3.7.2 OPERATING BUDGET SCHEDULE (\$M)*

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
3.0 SURFACE WATERS AND WETLANDS
3.7 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 4 of 5

SURFACE WATERS/WETLANDS PROTECTION PROGRAM

3.7 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
3.6.1 STREAM MANAGEMENT	0	0	0	0	0	0
3.6.2 THERMAL MITIGATION	0	10000	89500	23500	9000	132000
3.6.3 NPDES	0	100	0	100	2000	2200
3.6.4 RIVER MONITORING	0	0	0	0	0	0
3.6.5 EROSION CONTROL	60	60	60	60	60	300
3.6.6 WASTEWATER TREATMENT	8530	7170	9600	18402	300	44002
3.6.7 SPILL PREVENTION/CONTROL	2840	26040	1540	40	400	30860
3.6.8 RADIOLOGICAL EFF. ASSESSMENT	1230	2230	1230	1230	26230	32150
3.6.9 WETLANDS	0	0	0	0	0	0
TOTAL	12660	45600	101930	43332	37990	241512

* CAPITAL ESTIMATES INCLUDE MANPOWER REQUIRED TO SUPPORT CAPITAL PROJECTS:
THESE VALUES, EXPRESSED AS THOUSANDS OF DOLLARS, ARE ESCALATED THROUGH FY93.

TABLE 3.7.3 CAPITAL BUDGET SCHEDULE (\$M)*

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
3.0 SURFACE WATERS AND WETLANDS
3.7 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 5 of 5

SURFACE WATERS/WETLANDS PROTECTION PROGRAM

3.7 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
3.6.1 STREAM MANAGEMENT	232	312	371	246	246	1407
3.6.2 THERMAL MITIGATION	4788	13857	92377	25873	10363	147039
3.6.3 NPDES	815	4179	4119	1219	3119	13451
3.6.4 RIVER MONITORING	325	325	325	325	325	1627
3.6.5 EROSION CONTROL	894	738	738	738	738	3646
3.6.6 WASTEWATER TREATMENT	23915	24058	27299	38242	19191	132705
3.6.7 SPILL PREVENTION/CONTROL	3342	27445	3142	982	1422	38339
3.6.8 RADIOLOGICAL EFF. ASSESSMENT	4408	4764	4984	4984	28764	47864
3.6.9 WETLANDS	141	158	158	158	158	764
TOTAL	38841	75835	133482	72546	64324	384838

* INCLUDES MANPOWER COST (3.7.1), OPERATING COST (3.7.2) AND CAPITAL COST (3.7.3)
EXPRESSED AS THOUSANDS OF FY89 DOLLARS.

TABLE 3.7.4 TOTAL EXPENDITURE SCHEDULE (\$M)*

3.0 SURFACE WATER AND WETLANDS PROTECTION PROGRAM

3.8 References

- DOE, 1987. *Final Environmental Impact Statement, Alternative Cooling Water Systems*, Savannah River Plant, Aiken, SC, DOE/EIS-0121, US DOE, Washington, DC.
- DOE, 1988. *US Department of Energy Savannah River Plant Environmental Report for 1986*, DPSPU-88-30-1, US DOE, Aiken, SC.
- Du Pont, 1987. *Savannah River Plant, Spill Prevention Control and Countermeasures Plan*, DPSP-87-1083, E. I. du Pont de Nemours and Company, Aiken, SC.
- Du Pont, 1986a. *Strategic Environmental Plan*, DPW-86-102, E. I. du Pont de Nemours and Company, Wilmington, DE.
- Du Pont, 1986b. *Environmental Quality, Corporate Policies and Guidelines*, E. I. du Pont de Nemours and Company, Wilmington, DE.
- Du Pont, 1985. *Savannah River Plant, Best Management Practices (BMP) Plan*, E. I. du Pont de Nemours and Company, Aiken, SC.

ATTACHMENT 3.1 -- SRS/SREL NPDES OUTFALLS

	<u>Outfall</u>	<u>Area</u>	<u>Department</u>	<u>Facility</u>
1.	A-001	A	SRL	773-A, SRL
2.	A-003		Power	781-A, Cooling tower overflow
3.	A-005		CSWE	717-A , Maintenance central shop
4.	A-011		Power	716-A , Auto repair shop
5.	A-014		Raw Materials	341-A , Liquid effluent treatment
6.	A-015	C	Power	607-7A , Sanitary treatment
7.	C-001		Reactor	108-1C, Engine house
8.	C-003		Reactor	108-2C, Engine house
9.	C-004		Reactor	105-C, Reactor building
10.	C-004A		Power	607-20C, Sanitary treatment
11.	D-001	D	Power	484-D, Power house
12.	D-001A		Power	607-7D, Sanitary treatment
13.	D-001B		Power	Coal pile runoff
14.	D-001C		Power	488-1D, Ash basin discharge
15.	D-003		Power	484-D, External runoff
16.	D-005	S	Power	483-D, Large basin outflow
17.	D-006		Power	421, Building process sewer
18.	DW-001		Construction	Wash down rack, trucks
19.	DW-002		Construction	Steam cleaning, equipment wash
20.	DW-003		Power	Sanitary treatment
21.	DW-004	F	DWPF	
22.	F-001		Separations	221-F, Canyon building
23.	F-002		Separations	221-1F, Canyon building
24.	F-003		Naval Fuel	247-F, Fuel Facility
25.	F-003A		Power	607-17F, Sanitary treatment
26.	F-005		Separations	235-F, Metallurgical building
27.	F-007		Power	284-F, Powerhouse (standby)
28.	F-008		Power	284-F, Coal pile runoff
29.	F-008A		Power	607-7F, Sanitary treatment
30.	F-012		Waste Manage.	Stormwater runoff
31.	F-013	G	Waste Manage.	Cooling water retention basin
32.	FS-001		SREL	739-G, Thermal lab greenhouse
33.	FS-002		SREL	739-G, Thermal lab greenhouse
34.	H-002	H	Tritium	234-H, Manufacturing building
35.	H-004		Separations	221-H, Canyon building

DPSP-87-121-2-2
ENVIRONMENTAL IMPLEMENTATION PLAN
3.0 SURFACE WATERS AND WETLANDS
NPDES Outfalls

Rev 0, 6/15/89
Effective 6/15/89
Page 2 of 2

36.	H-006		Waste Manage.	Stormwater
37.	H-007		Waste Manage.	Cooling Tower Blowdown and Compressor Cooling Water
38.	H-008		Power	285-H, Cooling tower
39.	H-008A		Power	607-7S, Sanitary treatment
40.	H-012		Separations	232-, 234H, Manufacturing buildings
41.	H-013		Power	H Area, Sanitary Treatment
42.	H-015		Fuel Production Fac.	Fuel production facility
43.	H-016		Waste Manage.	F/H Area ETF
44.	H-017		Waste Manage.	Stormwater runoff
45.	H-018		Waste Manage.	Cooling water retention
46.	K-001	K	Reactor	704-K, Office building
47.	K-006		Power	184-K, Powerhouse
48.	K-008		Reactor	108-2K, Engine house
49.	K-010		Reactor	108-1K, Engine house
50.	K-011		Reactor	105-K, Reactor building
51.	K-012		Power	607-17K, Sanitary treatment
52.	L-007	L	Reactor	105-L, Reactor building
53.	L-007A		Power	607-16L, Sanitary treatment
54.	L-008		Reactor	108-1L, Engine houses 108-2L
55.	L-010		Reactor	704-L, Office building
56.	M-004	M	Raw Material	341-M, Liquid effluent treatment
57.	M-005		Raw Material	906-1M, Air stripper
58.	P-005	P	Power	188-P, Ash disposal basin
59.	P-007		Power	184-P, Powerhouse
60.	P-013		Reactor	105-P, Reactor building
61.	P-014		Power	607-7G, Sanitary treatment
62.	P-019		Reactor	105-P, Reactor building
63.	PP-001	PP	SRL	737-5G, Env. support laboratory
64.	S-002	C.	Construction	8303, Auto repair shop
65.	S-008		Construction	690-G, Process HX repair
66.	S-011		Power	Sanitary treatment
67.	S-014		CSWE	8491-11, Vehicle wash rack
68.	T-001	TC&U	SREL	Artificial streams laboratory
69.	T-005		SRL	704-U, Office building & laboratory
70.	T-007		Power	Sanitary treatment
71.	X-004		CMX-SRL	677-G, Pilot plant building
72.	X-008		TNX SRL	679-G, Test facility & laboratory
73.	X-011		SRL	675-G, Glass melter building
74.	X-013		Power	607-37G, Sanitary treatment
75.	X-014		TNX SRL	TNX ETP
76.	Y-001	Y	CSWE	618-G, Locomotive shop

Attachment 3.2 – Facility Compliance Surveillance Procedures for BMP/SPCC Plans

The following procedures and manuals are used by SRS facilities for meeting SCDHEC and SRS requirements generated by SPCC/BMP Plans. Some of the listed procedures and manuals encompass all three activities such as spill control, spill response, and spill/release reporting in a single procedure. In addition to the following list of broad-ranging procedures, there are many more that are specific for small and large equipment and unit operations in all plant areas.

Central Services Works Engineering (CSWE)

DPSOP 301 Section 6	Spills
DPSOP 301 Section 10, Item (4)	Spill Prevention Control and Countermeasure Plan 3/700 Area Project No. 2533 Oil and Chemical Spill Response Guidelines Manual for SRS Spill Teams

Construction Management

(They use the procedures or directives of the area where they are stationed.)

Defense Waste Processing Facility (DWPF)

Environmental Protection Section (EPS)

SRS Procedures Manual, Item 201

Environmental Monitoring Section (EMS)

Chemical spill control for HP Laboratories in 735-A and 734-11A is governed by SRS procedures.

Naval Fuel (NF)

DPSOL 247-MC-87	Inspection of the Emergency Diesel Fuel Tank
DPSOL 247-SA-025	Response to Chemical or Oil Spills Outside the FMF Building

Power Operations

DPSOP 210	Power Department Safety Rules - Section F - Handling Chemical Spills - Section Y - Laboratory Chemical Spills
DPSOP 10-OSP-1	Oil Spill Prevention Control and Countermeasure Plan

Raw Materials (RM)

DPSOL 300-655	Reporting Spills/Leaks on Process Chemicals or Petroleum
DPSOL 300-125	Maintaining Log of Inventory Inspections and Disposal of Hazardous Waste Drums at Hazardous Waste Storage Areas
DPSOL 300-126	Weekly Inspection of Chemical Storage Pad
DPSOL 320-733	Preparation and Shutdown Procedure for the 2,750-ton Extrusion Press
DPSOL 321-823	Maintaining Log Inventory Inspection of the Extrusion Press Staging Area
DPSOL 313-7048	Disposing Non-Radioactive Waste Oil
DPSOL 313-2625	Operating the Serfilco Filter
DPSOL 313-2630	Operating the Oberlin Filter

Reactors

DPSOP 105-2328	Oil Pollution Prevention and Control, provides for daily inspections of all potential spill locations and staging areas
DPSOL 105-ME-611	Spills Reporting and Control, details the emergency spill control, reporting, and cleanup actions required in the event of an unauthorized release.

DPSOL 421-2D-166

Wastewater Disposal

Separations

DPSOL 200-H-9563
DPSOL 200-H-9564-Q

Inspecting Building 211-H Solvent Handling
Inspecting Hazardous Chemical Storage
Area 211-H

DPSOL 244-H-8005

Inspection of A-Line, 222-F, 211-F Chemical
Storage Areas

DPSOL 211-F-1902

Inspections of Hazardous Chemical Storage
Areas - 244/245-H

DPSOL 221-F-JB-9561

Chemical or Oil Spill - Area Emergency
Coordinator Response

DPSOL 200-H-9561

Area Emergency Coordinator Response
Chemical or Oil Spill

DPSOL 244-H-8006
DPSOP 246-F-TF-1050

RBOF Response to Chemical or Oil Spills
Chemical or Oil Spill Emergency
Coordinator Response

DPSOL 221-F-9561

Chemical or Oil Spill Emergency
Coordinator Response

DPSOL 221-HB-4724

Chemical Spill Containment for Scrap
Recovery Facilities

SRL - Tech Area

SRL Procedures Manual, Item 1.10
SRL Procedures Manual, Item 4.18

Nonradioactive Spills
Unusual Occurrences - Notification and
Reporting to DOE

LSD Operating Proc., SPCC Plan

Loading Caustic Reagent in 607-17A, dated
2-26-87

SRL - TNX

DPSTOM-47

TNX Emergency and Disaster Plan, Section
VIII, Spill Control

TNXOP-3-1.20

SRL/TNX Semiworks HOW Manual, Spill
Prevention from SPCC/BMP Facilities

Tritium

DPSOL TF-H-5193

Spill Reporting, Spill Prevention, and
Inspection within the Tritium Facilities

Waste Management (WM)

DPSOL 241-FH-9562
DPSOL 709-G-8

Waste Management Response to Spills
Overpacking and Redrumming Leaking
NRHW Drums

DPSOL 709-G-9

Emptying Building 709-G 1709-4G/709-2G
Sumps

DPSOL 241-FGH-2004

Emergency Actions Following a Leak in Spent
Solvent Storage Tanks, Building 643-G

DPSOL 643-29G-2

Emptying Building 643-29G Sump

4.0 SAFE DRINKING WATER AND OTHER COMPLIANCE PROGRAMS

CONTENTS

4.1 Safe Drinking Water Act (SDWA)

- 4.1.1 Site Program Overview
- 4.1.2 Existing Conditions
- 4.1.3 Regulatory Requirements
- 4.1.4 Facilities Operations
- 4.1.5 Construction Projects
- 4.1.6 References

4.2 National Environmental Policy Act (NEPA)

- 4.2.1 Site Program Overview
- 4.2.2 Regulatory Requirements
- 4.2.3 Organizational Responsibilities
- 4.2.4 Program Activities

4.3 Toxic Substances Control Act (TSCA)

4.3.1 Polychlorinated Biphenyls (PCBs)

- 4.3.1.1 Site Program Overview
- 4.3.1.2 Regulatory Requirements
- 4.3.1.3 Organizational/Personnel Responsibilities
- 4.3.1.4 Auditing
- 4.3.1.5 Compliance Actions
- 4.3.1.6 References

4.3.2 Premanufacturing Notification (PMN)

- 4.3.2.1 Regulatory Requirements
- 4.3.2.2 Organizational Compliance Responsibilities
- 4.3.2.3 Compliance Actions

4.3.3 Reporting Uses of Existing Chemicals

- 4.3.3.1 Regulatory Requirements**
- 4.3.3.2 Organizational Compliance Responsibilities**
- 4.3.3.3 Compliance Actions**
- 4.3.3.4 References**

4.3.4 Reporting of Health Effects Information

- 4.3.4.1 Regulatory Requirements**
- 4.3.4.2 Organizational/Personnel Compliance Responsibilities**
- 4.3.4.3 Compliance Actions**

4.4 Federal Insecticide, Fungicide and Rodenticide Act (FIFRA)

- 4.4.1 Site Program Overview**
- 4.4.2 Regulatory Requirements**
- 4.4.3 Organizational Responsibilities**
- 4.4.4 Compliance Actions**

4.5 Resource Requirements

4.0 SAFE DRINKING WATER AND OTHER COMPLIANCE PROGRAMS

4.1 Safe Drinking Water Act (SDWA)

4.1.1 Site Program Overview and Summary

The Savannah River Site (SRS) has domestic water treatment facilities which are independent of the water systems in surrounding communities. The construction, modification, and operation of the site's domestic water supplies and wells are regulated by the South Carolina Department of Health and Environmental Control (SCDHEC) under the State Primary Drinking Water Regulations. The SCDHEC has regulatory authority from the Environmental Protection Agency (EPA), and the state regulations meet federal requirements established under the Safe Drinking Water Act of 1974 (amended 1986). The regulations require:

- Construction and operating permits for new systems or modifications to existing systems
- Operation of existing facilities by certified operators of the proper grade
- Periodic sampling of finished water to verify proper treatment and potability.

In many cases, the SRS goes beyond the requirements of the SCDHEC regulations to ensure the quality of the domestic water supplies. More bacteriological samples are taken than are required, and SRS limits for bacteriological samples are more restrictive. Annual chemical analyses are performed to verify compliance with SCDHEC contaminant limits for community water systems, even though the SRS's systems qualify as less regulated non-transient, non-community systems.

Total cost for the Safe Drinking Water Act Protection Program during the five-year planning period is expected to be nearly \$58.3 million which includes about 130 man-years of effort. Capital expenditures are expected to exceed \$45.7 million. The major capital project item is the replacement of the fire/domestic water distribution systems in the 100 areas at a cost of \$50 million (FY90 through FY95).

4.1.2 Existing Conditions

The SRS has 27 separate domestic water systems which supply drinking water to plant personnel. These systems supply water to facilities that range in size from the security barricades, with a small number of users, to the 300-M/700-A Area system, which supplies water to over 5000 users. Treated well water supplies 26 of these systems. In D Area, treated water from the Savannah River is used. All domestic water supplies are chlorinated for bacteriological control. In the larger systems, the finished water is pH adjusted, and polyphosphate may be added to control water discoloration and piping corrosion.

In 1981, trace quantities (10 parts per billion) of chlorocarbons were detected in two of the domestic water wells in the 300-M/700-A Areas. As a precautionary measure, carbon bed filters were installed on-line until two new wells, 1.5 miles northeast of A Area, were placed in service in 1986. The old wells were converted to process water use.

4.1.3 Regulatory Requirements

Federal and State Laws and Regulations

•Safe Drinking Water Act of 1974, as amended (42 U.S.C. 300f et seq.), the South Carolina Primary Drinking Water Regulations (SCDHEC 61-58) (which includes the South Carolina Industrial Water Supplies Regulation)—These acts and regulations require the Department of Energy (DOE) to obtain applicable permits and satisfactorily complete required sample analyses and site inspections of public/industrial water supplies and sources of drinking water. The EPA has authorized South Carolina to regulate both public/industrial water supplies and sources of drinking water.

4.1.4 Facilities Operations

Environmental Protection Section (EPS)

The EPS evaluates regulatory requirements and compliance issues, reviews projects, assists with facility permitting and provides assistance with regulatory agency facility audits. The EPS also coordinates the sitewide program for operator certification. The estimated total five-year cost is \$297,500.

Power Operations and Power Engineering

Power Operations has 33 supervisors and operators that are certified by the South Carolina Board of Certification to operate domestic water facilities. Employees complete 32 hours of classroom training in preparation for the Board examination. While on the job, certified operators adjust chemical feed rates, analyze water samples to verify proper pH and chlorine residuals, and collect bacteriological samples which are analyzed at the 772-D laboratory. Operators visit each facility at least once each day to perform the above duties.

Power Engineering prepares a monthly report which is submitted to the SCDHEC through the DOE. This report includes water quality data relating to operation of the D Area surface water (Savannah River) treatment plant. Any positive bacteriological samples exceeding SCDHEC criteria are also detailed in this report.

The estimated total Power Operations and Power Engineering five-year cost is \$10.9 million.

Defense Waste Processing Facility (DWPF)

All DWPF Production Specialists are being SCDHEC certified to operate the DWPF Domestic Water System. This includes two domestic water wells and treatment by chlorination and neutralization. Operators will be required to adjust feed rates, sample water quality, and verify proper equipment operation daily. Facility operation on a temporary domestic water well began in March 1987. Operation of the primary domestic water deepwells is scheduled for June 1989 pending final approval of the SCDHEC.

The estimated total DWPF five-year operating cost is \$441,000.

SRL - TNX Operations

The TNX Domestic Water Facility is jointly operated by TNX Operations and Power. TNX Operations take water samples every shift to check pH and residual chlorine. If the readings are outside the appropriate range, Power is called to make the necessary chemical adjustments. Power also takes daily samples to check pH and residual chlorine and makes chemical adjustments based on their results.

The estimated total TNX five-year cost is \$84,000.

4.1.5 Construction Projects

Power Operations and Power Engineering

•**Replace Water Wells, All Areas**—Sitewide domestic/service/fire water wells will be replaced on an as needed basis for the five-year period. No milestones are available since it is an ongoing program. The estimated cost of this project for the five-year period is \$3.75 million. Costs for FY89 are \$900,000. Additional non-liaison manpower costs for the five-year period are \$133,875.

•**Install Domestic Water Instruments, All Areas**—SCDHEC is requiring installation of flow meters on well water and domestic water headers. Chemical feeds will be flow paced, and existing chemical feeders will be modified to provide automatic proportioning with manual overrides. The cost of this project is \$1.95 million with initial funding beginning in FY89. Costs are \$876,000 for FY89. Additional non-liaison manpower costs for FY89 through FY91 are \$74,375. Milestones are as follows:

Project Authorized	06/88
Design End	03/90
Construction Start	06/90
Construction End	12/91

•**Replace Service Domestic Water Degasifiers, 284-H**—The degasifiers are deteriorating and require replacement. Degasifiers remove any CO₂ and H₂S gases present from domestic and service well water prior to chemical treatment.

The cost of this project is \$300,000 with initial funding beginning in FY92. Additional non-liaison manpower costs for FY91 through FY93 are \$90,250. Milestones are as follows:

Project Authorized	06/92
Design End	02/93
Construction Start	03/93
Construction End	12/93

•**Provide Deepwell Water Pumps, F, H, and A Areas**—Spare pumps are necessary to ensure rapid repair and to minimize downtime.

The cost of this project is \$300,000 with initial funding beginning in FY91. Additional FY91 through FY93 non-liaison manpower costs are \$89,250. Milestones are as follows:

Project Authorized	06/91
Design End	03/92
Construction Start	09/92
Construction End	03/93

•**Replace Domestic Water Storage Tanks 282-F and H**—The existing original equipment tanks have cracks which result in slow leaks.

The cost of this project is \$1.0 million with initial funding beginning in FY90. Additional non-liaison manpower for FY90 through FY93 are \$119,000. Milestones are as follows:

Project Authorized	06/90
Design End	03/91
Construction Start	09/91
Construction End	09/92

•**Install Domestic Waterline Flush Valves, Sitewide**—The SCDHEC is requiring that all major SRS drinking water systems be routinely flushed to remove sediment and stagnant water. Many of the existing systems are not equipped with flushing hydrants.

The cost of this project is \$750,000 and is being funded in FY90. Additional FY90 through FY93 non-liaison manpower costs are \$119,000. Milestones are as follows:

Project Authorized	06/90
Design End	06/91
Construction Start	12/91
Construction End	12/93

•**Replace Fire/Domestic Water Distribution Piping, 100 Areas**—Corroded cast iron piping will be replaced with new corrosion-resistant piping. New storage tanks, pumps, and some fire suppression systems will also be installed. Polyphosphate treatment systems will be installed or upgraded in P, K, C, L, D and CS Areas.

The cost of this project is \$50 million (FY90 through FY95) and is being funded beginning in FY90. Additional non-liaison manpower costs (FY89 through FY93) are \$208,250. Milestones are as follows:

Project Authorized	06/90
Design End	07/91
Construction Start	01/92
Construction End	12/94

•**Conversion of D Area Domestic System to Groundwater**—D Area's domestic water system is supplied with surface clarified water from the 483-D Water Treatment Plant. Building 483-D also supplies boiler feedwater and service water for Area uses. New federal and state drinking water regulations may require extensive design modifications. Tighter regulatory limits and sampling requirements will make operation and compliance with water quality limits more difficult. Domestic water production wells and a storage tank will be installed to convert the existing system from surface water to groundwater.

The cost of this project is \$4.0 million. Additional FY90 through FY92 non-liaison manpower costs are \$89,250.

Project Authorized	09/89
Start Design	10/89
Design Complete	06/90
Start Construction	03/91
Complete Construction	06/92

•**Replace Water Storage Tanks, C-Shops**—This project will replace present water storage tanks in Central Shops with an altitude tank having a storage capacity of 200,000 gallons. The 120,000 gallon tank has been in service from more than 34 years and is in very poor condition. The 60,000 gallon tank is in marginal condition, and a new roof is needed. It alone does not have the capacity to supply fire protection and domestic needs, due to expansion in the Central Shops area. This project is necessary to maintain domestic water needs. The impact of no funding will be the risk of losing the 120,000 gallon tank and not having the capability to supply fire protection and domestic needs. This is a FY92 project with a total estimated cost of \$250,000.

•**Replace Deepwell**—This project will provide a new 400 gpm deepwell with pump, motor and piping for an additional source of domestic and fire protection water for B Area. At the present time, there are two 500 gpm wells

that supply domestic and fire protection water to B Area, 905-59B and 905-67B. Well 905-59B was constructed in 1951 and has greatly exceeded the normal life span of a deepwell at the SRS. Failure of this well would regularly lead to a loss of domestic water to the area whenever well 905-67B is down for maintenance. In addition, well 905-67B could not meet the demand for fire protection water during an emergency. Construction of a replacement well for 905-59B will ensure a reliable source of domestic water and meet the potential fire protection system demand. No funding could result in a lack of domestic water for the area on a periodic basis. Possible increase in fire damage due to insufficient amount of fire protection water could also result. This is a FY91 project with a total estimated cost of \$900,000.

•**Domestic Water Pumps, F/H Areas, Part 2**—This FY89 project is to complete the replacement of obsolete domestic water pumps in 200-F and -H Areas at a cost of \$700,000.

•**Replace Flow Controls and Backwash Valves, 483-D**—This project will replace the backwash control and filter backwash valves. The existing backwash valves leak, reducing efficiency in cleaning the filters. The flow control system is obsolete and repair parts are not readily available. This FY92 project will cost \$800,000.

The following projects were identified during the Environmental Implementation Plan review process, but cost information was not available.

•**Isolation Valves for Domestic and Well Water Headers**—Most of the domestic and well water piping systems on plant were not installed with an adequate number of isolation valves. Line breaks often result in disruption of flows to large portions of the distribution systems. The SCDHEC requested installation of additional valves in a 1986 audit, and recommendations for additional valve installations were developed for each system. Some of the Areas have installed the necessary valves, others have written requests for engineering assistance (REAs). An overall project is needed to accomplish the remaining installations.

•**Polyphosphate Treatment Systems, F and H Areas**—Polyphosphate treatment systems are needed in F and H Areas for redwater and corrosion control. An REA was written in 1984, but this project has not proceeded beyond completion of the initial Scope of Work. The SCDHEC now requires a corrosion control system before they will approve construction permits for new wells.

•**Upgrade Underground Water System, B Area**—An REA was written in 1986 to replace the B-Area domestic and fire water piping system. The carbon steel piping system has corroded to the point that line breaks and leaks are common. The domestic water supply is discolored from the presence of iron, resulting from piping corrosion.

SRL-TNX

•**New Water Well, TNX Area**—This activity will replace the existing wells on a needed schedule to keep up with the forecasted growth of TNX Area. This is a FY93 capital project with a total estimated cost of \$200,000.

4.1.6 References

DPSP-86-1026 titled *South Carolina Department of Health and Environmental Control Permit Procedures HOW Manual*.

Area Power Section DPSOPs specify the proper procedures for disinfection of domestic water lines, operation of equipment, sampling, etc. DPSOL 10-PAR-1 incorporated in each of the Power Section DPSOPs summarizes water sampling and reporting requirements.

SRS Safety Manual Item Number 29 gives specific requirements for protecting domestic systems from cross contamination with nonpotable supplies.

4.0 SAFE DRINKING WATER AND OTHER COMPLIANCE PROGRAMS

4.2 National Environmental Policy Act (NEPA)

4.2.1 Site Program Overview and Summary

The Savannah River Site (SRS) NEPA Program was initiated in August 1982 at the request of the Department of Energy Savannah River (DOE-SR) to ensure that the requirements of the NEPA were met. This program is administered and coordinated for the SRS by the NEPA Activities Group within the Environmental Protection Section (EPS) of the Environmental and Health Protection Department. The program reflects the Council on Environmental Quality (CEQ) regulations and DOE guidelines which require consideration of environmental factors during the planning process for all major federal activities that significantly affect the quality of the environment.

The NEPA Activities Group works with various SRS organizations in gathering the information and preparing the documentation necessary for NEPA compliance. The Group also has an active NEPA training program to inform employees of their obligations under the Act.

The total five-year NEPA cost is \$2.4 million which includes 25 (MS) and five (LR) man-years of effort.

4.2.2 Regulatory Requirements

Federal Law

•**National Environmental Policy Act (42 USC 4321-4347)**—The purpose of the NEPA is to establish a national policy to protect the environment and to promote a better understanding of the ecological systems and natural resources important to the nation. NEPA and CEQ regulations implementing the NEPA (40 CFR 1500-1508) contain action-forcing provisions to ensure that federal agencies consider environmental information prior to making decisions on proposed actions. The NEPA process includes decision points at which the significance of environmental effects is considered, project alternatives are evaluated, and public input is

obtained as necessary and a Record of Decision prepared publicly stating the alternative selected.

DOE Orders/Regulations

- Implementation of the National Environmental Policy Act (DOE Order 5440.1C)**—This order established a DOE policy of complying fully with the NEPA and describes the roles of various DOE offices in implementing the Act.

- DOE Regulations, Compliance with the National Environmental Policy Act, as amended (45 FR 20664, 45 FR 20694, 47 FR 7976)**—These guidelines provide procedures which the DOE will apply to implement the CEQ regulations for compliance with the NEPA. The SRS is required to integrate the NEPA process with other planning at the earliest possible time to ensure that planning and decisions reflect environmental values.

4.2.3 Organizational Responsibilities

The NEPA Activities Group within the Environment Protection Section has the responsibility to prepare and/or manage all appropriate NEPA documentation for transmittal to the DOE. The primary responsibility of the group is to coordinate all activities of SRS organizations related to NEPA documentation for specific projects.

The Savannah River Laboratory (SRL), acting in an oversight capacity, reviews NEPA documentation prepared for the DOE to ensure technical accuracy and approves all formal transmittal of NEPA documentation to DOE-SR.

4.2.4 Program Activities

Environmental Protection Section (EPS)

The NEPA Activities Group administers an active program involving receipt of approximately 20-25 Environmental Evaluation Checklists for projects and Test Authorizations per month. Approximately 10 percent of these require documentation such as a Memorandum-To-File (MTF), Environmental Assessment (EA), or Environmental Impact Statement (EIS). Two EISs have recently been completed: *Waste Management Activities for the Protection of Groundwater* and *Alternative Cooling Water Systems*. The DOE-SR and its environmental contractors prepared the EISs for which the operating

contractor provided technical information. The EA for Management Activities for Retrieved and Newly Generated Transuranic Waste is in DOE-HQ for issue. An MTF is being prepared to show that changes since the Defense Waste Processing Facility EIS was completed have not changed the Record of Decision. Under review are the Consolidated Incineration Facility (EA) and the Hazardous Waste/Mixed Waste Disposal Facility (potential supplement to groundwater EIS). New major activities include such projects as the New Production Reactor(EIS) and continued Reactor Operations (EIS). Others may include Fuel Cycle Facilities (potential EIS), and New/Replacement Plutonium Facility (FB Line).

The estimated total five-year cost is \$2.4 million for EPS management.

4.0 SAFE DRINKING WATER AND OTHER COMPLIANCE PROGRAMS

4.3 Toxic Substances Control Act (TSCA)

The purpose of the Toxic Substances Control Act (TSCA) is to protect human health and the environment by requiring the reporting of and necessary use restrictions on certain chemical substances. The TSCA has two main regulatory objectives: first, the development of a baseline chemical inventory and evaluation of potential hazards of all chemicals manufactured in or imported into the United States; second, the regulation of production (including new chemicals), use, distribution, and disposal of such chemical substances. The Environmental Protection Agency (EPA) administers the act. Polychlorinated Biphenyls (PCBs) are the chemicals under the TSCA that are given particular attention in the Environmental Implementation Plan (EIP).

4.3.1 Polychlorinated Biphenyls (PCBs)

4.3.1.1 Site Program Overview

Since 1980, the Savannah River Site (SRS) has had an active program to remove and properly dispose of PCBs. In the past, the primary use of PCBs was in closed or semi-closed systems in electrical transformers, capacitors, heat transfer systems, and hydraulic systems. At the present time, PCBs onsite are found in small capacitors (less than 3 pounds) used to raise and lower reactor control rods, and in ballasts in fluorescent light fixtures. New purchases of hydraulic fluids, heat transfer systems, electrical transformers, capacitors, and other dielectric fluid-containing materials are certified by the vendor to contain no PCBs.

Operations continue to be conducted to remove all PCB fluids and materials from the site. The SRS is going beyond regulations by shipping some PCB-containing materials offsite for disposal at an approved EPA facility. At the present time, there are two onsite locations for the storage of PCB-containing materials: Building 741-1A for non-radiological PCB containing materials and Building 643-29G for radioactively contaminated PCB-containing materials. Both of these facilities meet the federal regulations for the storage of PCBs. Currently there is no approved facility for disposal of radioactively contaminated PCBs.

The total five-year period TSCA cost is \$857,725 which includes seven (MS) and one (LR) man-years of effort.

4.3.1.2 Regulatory Requirements

Federal Law and Regulations

• **Toxic Substances Control Act (TSCA) of 1977, as amended (15 U.S.C. 2601 et seq.), Section 6 (40 CFR 761)**—The use of polychlorinated biphenyls (PCBs) are prohibited except in a totally enclosed manner. The DOE is also required to comply with listed procedures in handling, storing, and disposing of regulated PCBs and PCB-containing materials.

4.3.1.3 Organizational Responsibilities

Site Engineering and Services is responsible for:

- Maintaining storage facilities at Building 741-1G in compliance with regulatory requirements
- Ensuring proper packaging and labeling of PCB-containing material in Building 741-1G
- Obtaining a contract for offsite disposal of PCBs
- Insuring PCBs are shipped offsite within the time limitations set by regulations.

Waste Management Operations is responsible for:

- Maintaining the storage facilities at Building 643-29G in compliance with regulatory requirements
- Ensuring proper packaging and labeling of PCB-containing material in Building 643-29G.

The Environmental Protection Section (EPS) is responsible for:

- Serving as an onsite PCB consultant

- Coordinating the PCB removal program
- Interfacing with regulatory agencies on audits.

Health Protection (HP) responsibilities are outlined in DPSOL 158-2-161.

Laboratories is responsible for:

- Analyzing samples for PCBs.

Custodial Departments are responsible for:

- Determining, by conducting a Health Protection (HP) survey, if the potential for occupational exposure to PCBs exists
- Instituting a program of personal monitoring to determine potential exposures if the potential for occupational exposure to PCBs exists
- Notifying HP and the EPS Spill Coordinator in the event of a spill
- Notifying area HP when working on PCB-containing equipment
- Identifying any PCB-containing materials in the area
- Ensuring proper labeling of PCB-containing materials
- Transporting PCB-containing materials to the proper storage facilities
- Ensuring that employees are trained in handling of PCBs and that training is documented.

4.3.1.4 Auditing

The following audits are to be performed at the SRS for PCB-containing materials:

- DOE appraisal every three years
- EPA audit at infrequent intervals (PCB survey optional)
- SRS self audit at infrequent intervals (see Chapter 10.0, Environmental Auditing and Appraisal Program.)

4.3.1.5 Compliance Actions

Site Engineering and Services (SES)

SES manages the offsite disposal of all PCBs at the 741-G Salvage Yard. This is done by storing the PCBs and making periodic shipments per EPA regulations to an approved offsite disposal vendor. The size of these shipments will continue to decrease as PCBs are eventually eliminated at the SRS. The current storage facilities should be adequate for the next five years.

The estimated total five-year operating cost is \$99,750.

Waste Management Operations (WMO)

WMO is presently storing in the mixed waste storage building, 643-29G, one 85-gallon drum and eight 55-gallon drums of floor sweepings contaminated with PCBs and radioactivity. WMO is developing a plan for disposal of these PCBs, which may include shipment to the incinerator at the Oak Ridge National Laboratory capable of handling radioactive feeds. The schedule for this activity is not known at this time. The cost to dispose of these materials is estimated at \$15,000 to \$20,000.

The estimated total five-year operating cost is \$204,375.

Environmental Protection Section (EPS)

The EPS coordinates PCB activities for the site and consults with the custodians on PCB related issues. EPS also prepares the annual inventory report and interfaces with the regulatory agencies on audits. EPS is subcontracting the computerization of the electrical and hydraulic equipment database in 1989. EPS is also consulting with the PCB task force as part of a 1989 effort to sample/analyze selected transformers onsite and re-verify that they are nonPCB.

The estimated total five-year cost is \$198,750.

Laboratories

The 320-M Lab is planning to perform all PCB analyses at the site once sample/waste disposal issues are resolved with the assistance of Power,

Waste Management, and EPS. As part of a program to upgrade their analytical methods, lab equipment will be replaced and upgraded in 1989.

The estimated total five-year cost is \$305,100.

Health Protection (HP)

HP assists all of the other departments through the implementation of DPSOL 158-2-161.

The estimated total five-year cost is \$9,950.

4.3.1.6 References

DPSOL 158-2-4161. Polychlorinated Biphenyls (Biphenyls)--PCBs.

DPSOP 83. Polychlorinated Biphenyl Analysis in Transformer Oils.

DPSOL S-9549, DPSOP 326. Control and Disposal of Polychlorinated Biphenyls (PCBs).

4.3.2 Premanufacturing Notification (PMN)

4.3.2.1 Regulatory Requirements

Federal Law and Regulations

•**Toxic Substance Control Act (TSCA) of 1977, as amended (15 U.S.C. 2601 et seq.) Section 5[a] (40 CFR 761)**—Chemicals not listed on the TSCA Inventory are considered new chemicals and must undergo premanufacture notification to the EPA 90 days prior to commercial manufacture or importation. The normal review period is 90 days, extendable by EPA for cause to 180 days.

4.3.2.2 Organizational Compliance Responsibilities

Any employee, group or department who intends to manufacture or import a new chemical substance for commercial purposes must submit a PMN notice to the SRS TSCA Site Coordinator, Environmental Protection Section. The requirement for PMN review also includes certain bioengineered microorganisms which EPA regards as new chemical substances.

The TSCA site coordinator has on file the appropriate EPA forms (EPA Form 7710-25) to meet PMN compliance. The person or group planning to make or import the new chemical must complete the PMN forms and submit them to the TSCA Site Coordinator. Completed PMN forms will be filed by the TSCA Site Coordinator with DOE-SR.

The EPA may determine that the chemical substance is not subject to PMN requirements and will notify the submitter.

4.3.2.3 Compliance Actions

Environmental Protection Section (EPS)

The EPS coordinates PMN activities. The EPS and custodial resource requirements are nominal.

4.3.3 Reporting Uses of Existing Chemicals

4.3.3.1 Regulatory Requirements

Federal Law and Regulations

• **Toxic Substances Control Act (TSCA) of 1977, as amended (15 U.S.C. 2601 et seq.) Section 5[a] [2] (40 CFR 721)—** Reporting is required for significant new uses of existing chemicals or an appreciable increase in their utilization for an existing purpose.

4.3.3.2 Organizational Compliance Responsibilities

Health Protection (HP) is responsible for:

- Maintaining the inventory of chemicals used by the site
- Approving the purchase of new chemicals by the site
- Approving new uses of existing onsite chemicals by the site .

4.3.3.3 Compliance Actions

Health Protection (HP)

HP administers the reporting of new chemical uses. HP resource requirements are nominal.

4.3.3.4 References

DPSOL 40-5-105 Purchase Approval Program: Chemical and Physical Agents

4.3.4 Reporting of Health Effects Information

4.3.4.1 Regulatory Requirements

Federal Law and Regulations

• **Toxic Substances Control Act (TSCA) of 1977, as amended (15 U.S.C. 2601 seq.) Section 8[c] and 8[e] (40 CFR 761)**—The operating contractor is required to maintain certain records and reporting on chemical substances products or processes and are required to notify the EPA under certain circumstances.

4.3.4.2 Organizational/Personnel Compliance Responsibilities

The Human Resources Division is responsible for informing new employees during their initial orientation about their TSCA responsibilities including reporting via TSCA 8(c), and 8(e) forms.

Employees shall:

- Notify Supervision/Health Protection if adverse health effects appear
- Report to Medical for observation
- File TSCA 8(c) forms with the assistance of Supervision/Health Protection/Medical.

Supervision shall be responsible for:

- Reporting verbal allegations to Health Protection
- Assisting as necessary in completing the form: Allegation of Significant Adverse Reaction Toxic Substances Control Act TSCA Section 8(c)
- Receiving verbal allegations from families of employees or site neighbors and seeing that the allegations are recorded on TSCA 8(c)

- Filling out and processing TSCA 8(c) form if an employee, family member, or site neighbor declines to fill out the forms
- Informing the employee of the disposition of his allegation.

Health Protection shall be responsible for:

- Keeping TSCA 8(c), and 8(e) reporting forms on file
- Assisting employees and supervision in completing TSCA 8(e) forms
- Receiving and processing completed forms
- Requesting the Medical Department to review completed forms
- Ensuring that all employees through line organization are given appropriate responses on their allegations
- Annually reminding all employees of their TSCA responsibilities
- Maintaining completed site TSCA 8(c), and 8(e) records for 30 years.

The Medical Department shall be is responsible for:

- Providing appropriate medical consultation with employees reporting for observation
- Assisting employees and Health Protection in completing TSCA 8(c), and 8(e) forms.

The EPS is responsible for:

- Reviewing and assisting in completing TSCA 8(c), and 8(e) forms relating to environmental allegations
- Maintaining completed site TSCA 8(c), and 8(e) forms on environmental matters for 5 years.

The EPA may conduct inspections of TSCA 8(c), and 8(e) records.

4.3.4.3 Compliance Actions

Costs for compliance with health effects reporting are difficult to determine within each of the site organizations. Actual costs are not excessive and are part of the organizational base costs.

4.0 SAFE DRINKING WATER AND OTHER COMPLIANCE PROGRAMS

4.4 Federal Insecticide, Fungicide, & Rodenticide Act (FIFRA)

4.4.1 Site Program Overview and Summary

The primary objective of the Savannah River Site (SRS) Pesticide Program is to select and use pesticides that are safe and effective. To accomplish this goal, there is a formalized process for the selection of pesticides according to objectives for use, optimum effectiveness and economy, and relative safety of use. The use and potential effect on the environment is also an important consideration.

The program defines responsibilities regarding pesticide selection, approval, procurement, formulation for use, application, cleanup, disposal of empty containers or unused supplies, and contractor services and liaison. Standard procedures are established covering individual application programs. These procedures include the proper reporting of pesticide activities and stress personal safety factors. Training programs are also instituted to ensure proper application of pesticides by pesticide applicators and their supervisors.

The total five-year FIFRA (pesticide program) cost is \$464,875, which includes nine man-years of effort.

4.4.2 Regulatory Requirements

•Federal Insecticide, Fungicide and Rodenticide Act, as amended (7 U.S.C. 136, et seq.) and the South Carolina Pesticide Control Act (R. 27-1072 ff)—These statutes require The Department of Energy (DOE) to comply with established procedures in handling, storing, applying and disposing of pesticides (e.g., insecticides, herbicides, termiticides, etc.). The SRS uses licensed pest control contractors for many of these services.

4.4.3 Organizational Responsibilities

The SRS Pesticide Control Committee (PCC) is responsible for the analysis and standardization of all current and new pesticide programs at the SRS. The group also responds to all questions and communications concerning pesticide use at the SRS and prepares any statistical reports or responses concerning pesticide activities. The PCC is composed of the Environmental Protection Section (EPS) Pesticide Coordinator as Chairman, Central Services Works Engineering (CSWE) Pesticide Activity Supervisor, and a Health Protection Industrial Hygienist.

Health Protection is responsible for contractor orientation with the SRS Pesticide Program. When applicable the orientation is performed by the building or facility custodian.

CSWE is responsible for the receipt, verification, storage, and issuance of all pesticides purchased for use at the SRS. The CSWE is responsible for the disposal of all pesticide containers and unused pesticides.

The Program Originator, the representative of the SRS Department that needs a pesticide application program, is responsible for preparing the DPSOL and forwarding it to the PCC for review and approval. The Program Originator must ensure that the applicators and supervisors are properly trained to apply the pesticides specified.

It is the responsibility of the custodian, or designate, to inform applicators of safety and environmental rules or special conditions in effect in his building or facility at the time of application.

The United States Forest Service (USFS) administers a separate SRS pesticide program. Subcontractors may be used to apply pesticides. All pesticide application is reviewed with the Department of Energy (DOE) prior to deployment. Procedural controls are specified in USFS Manuals.

The Savannah River Ecology Laboratory (SREL) does not use any pesticides.

4.4.4 Compliance Actions

Contractor Orientation

•**Health Protection (HP)**—HP reviews all pesticides used by Site contractors. Contractors supply product labels and material safety data sheets. Specific applications are also reviewed to ensure that applicable regulations and site policies are followed. Site orientations with contractor personnel are conducted as needed.

The total estimated five-year HP cost is \$14,875.

Pesticide Control

•**Central Services Works Engineering (CSWE)**

CSWE DPSOP 329 titled *Pesticide Control*, provides the primary guidance for the site. Oversight for the program is provided by the PCC. CSWE is responsible for the receipt, storage, and issuance of pesticides. Additional responsibilities include disposal of empty containers and unused pesticides.

The total estimated five-year cost is \$628,500.

4.0 SAFE DRINKING WATER AND OTHER COMPLIANCE PROGRAMS

4.5 Resource Requirements

The manpower and operating requirements for the Safe Drinking Water and Other Compliance Programs section are shown for FY89 through FY93. Capital costs are escalated and include manpower requirements. Manpower requirements (Monthly Salary and Local Roll) over the next five years are 81 man-years and 98 man-years, respectively. The manpower, operating, capital, and total cost schedules for each issue are presented in Tables 4.5.1 through 4.5.4. Total funding requirements over the five-year planning period are about \$62.2 million.

Similar schedules of manpower and cost requirements for each department are presented in Appendix Tables 4.5.1A through 4.5.4A.

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
4.0 SAFE DRINKING WATER AND OTHER PROGRAMS
4.5 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 2 of 5

SAFE DRINKING WATER AND OTHER PROTECTION PROGRAMS

4.5 RESOURCE REQUIREMENTS

ISSUE	FY 89		FY 90		FY 91		FY 92		FY 93		TOTAL	
	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR
4.1 SAFE DRINKING WATER ACT	424	668	543	668	602	668	602	668	572	668	2743	3340
4.2 NATIONAL ENVIRON. POLICY ACT	298	40	298	40	298	40	298	40	298	40	1488	200
4.3 TOXIC SUBSTANCES CONTROL ACT	73	6	73	6	73	6	73	6	73	6	366	32
4.4 FED. INSECT., FUNG. & RODENT. ACT	39	72	39	72	39	72	39	72	39	72	193	360
TOTAL	833	786	852	786	1012	786	1012	786	882	786	4700	3932

* VALUES ARE THOUSANDS OF FY88 DOLLARS.

**ANNUAL MANPOWER COSTS BASED ON: MS = \$59.5M (SR8); LR = \$40M (SR8).

TABLE 4.5.1 MANPOWER REQUIREMENTS SCHEDULE (\$M):**

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
4.0 SAFE DRINKING WATER AND OTHER PROGRAMS
4.5 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 3 of 5

SAFE DRINKING WATER AND OTHER PROTECTION PROGRAMS

4.5 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
4.1 SAFE DRINKING WATER ACT	1312	1312	1312	1312	1312	6559
4.2 NATIONAL ENVIRON POLICY ACT	150	150	150	150	150	750
4.3 TOXIC SUBSTANCES CONTROL ACT	84	84	84	84	84	420
4.4 FED. INSECT., FLNG. & RODENT. ACT	18	18	18	18	18	90
TOTAL	1564	1564	1564	1564	1564	7819

* COST ITEMS FOR PROGRAMS, OPERATING COSTS, RTA'S, SAMPLING, ETC., ARE EXPRESSED AS THOUSANDS OF FY89 DOLLARS. THESE COSTS DO NOT INCLUDE MANPOWER COSTS.

TABLE 4.5.2 OPERATING BUDGET SCHEDULE (\$M)*

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
4.0 SAFE DRINKING WATER AND OTHER PROGRAMS
4.5 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 4 of 5

SAFE DRINKING WATER AND OTHER PROTECTION PROGRAMS

4.5 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
4.1 SAFE DRINKING WATER ACT	2476	4716	11306	14225	12925	45650
4.2 NATIONAL ENVIRON. POLICY ACT	0	0	0	0	0	0
4.3 TOXIC SUBSTANCES CONTROL ACT	0	0	0	0	0	0
4.4 FED. INSECT., FUNG. & RODENT. ACT	0	0	0	0	0	0
TOTAL	2476	4716	11306	14225	12925	45650

* CAPITAL ESTIMATES INCLUDE MANPOWER REQUIRED TO SUPPORT CAPITAL PROJECTS.
THESE VALUES, EXPRESSED AS THOUSANDS OF DOLLARS, ARE ESCALATED THROUGH FY93.

TABLE 4.5.3 CAPITAL BUDGET SCHEDULE (\$M)*

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
4.0 SAFE DRINKING WATER AND OTHER PROGRAMS
4.5 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 5 of 5

SAFE DRINKING WATER AND OTHER PROTECTION PROGRAMS

4.5 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
4.1 SAFE DRINKING WATER ACT	4880	7241	13888	18807	15477	58292
4.2 NATIONAL ENVIRON. POLICY ACT	488	488	488	488	488	2438
4.3 TOXIC SUBSTANCES CONTROL ACT	164	164	164	164	164	818
4.4 FED. INSECT., FUNG. & RODENT. ACT	129	129	129	129	129	643
TOTAL	5659	8020	14668	17587	16257	62191

* INCLUDES MANPOWER COST (4.5.1), OPERATING COST (4.5.2) AND CAPITAL COST (4.5.3)
RTA'S, SAMPLING, ETC., FOR THE RESPONDING DEPARTMENT OR UNIT.

TABLE 4.5.4 TOTAL EXPENDITURE SCHEDULE (\$M)*

5.0 LAND USE AND WILDLIFE PROTECTION PROGRAM

CONTENTS

5.1 Overview

- 5.1.1 Introduction
- 5.1.2 Summary

5.2 Policy

- 5.2.1 Policy Statement
- 5.2.2 Background for Policy Statement

5.3 Existing Conditions

5.4 Objectives

5.5 Strategy

5.6 Implementation

5.6.1 Land Use

- 5.6.1.1 Site Program Overview
- 5.6.1.2 Justification/Regulatory Requirements
- 5.6.1.3 Organizational Responsibilities Summary
- 5.6.1.4 Programs
- 5.6.1.5 Research/Studies

5.6.2 Endangered Species

- 5.6.2.1 Site Program Overview
- 5.6.2.2 Justification/Regulatory Requirements
- 5.6.2.3 Organizational Responsibilities Summary
- 5.6.2.4 Management Programs
- 5.6.2.5 Research/Studies

5.6.3 Other Wildlife

- 5.6.3.1 Site Program Overview**
- 5.6.3.2 Justification/Regulatory Requirements**
- 5.6.3.3 Organizational Responsibilities Summary**
- 5.6.3.4 Management Program**
- 5.6.3.5 Research/Studies**

5.6.4 Wildlife Habitat

- 5.6.4.1 Site Program Overview**
- 5.6.4.2 Regulatory Requirements**
- 5.6.4.3 Organizational Responsibilities Summary**
- 5.6.4.4 Research /Studies**

5.6.5 Land Reclamation and Erosion Control

- 5.6.5.1 Site Program Overview**
- 5.6.5.2 Justification/Regulatory Requirements**
- 5.6.5.3 Organizational Responsibilities Summary**
- 5.6.5.4 Programs**

5.7 Resource Requirements

5.8 References

LAND USE AND WILDLIFE PROTECTION PROGRAM

5.1 Overview

5.1.1 Introduction

Less than 5 percent of the Savannah River Site (SRS) land area is used for industrial purposes (buildings, roads, etc.). The majority of the remaining land is managed as a forest. Other components of the SRS natural resource management program include soil, water, and plant conservation; fish and wildlife management; preservation and study of historical and cultural sites; and land use activities associated with the site's designation as a National Environmental Research Park (NERP). Although other organizations on the site are involved in natural resource management, this section of the Environmental Implementation Plan (EIP) focuses on operating contractor activities for managing and protecting wildlife and land use.

5.1.2 Summary

The SRS meets environmental regulations and site policies related to land use and wildlife protection. The operating contractor participates with other onsite contractors in a Site Use Coordination System to meet land use requirements and to promote beneficial uses of site lands. The SRS also participates in studies and management programs for protection of animal species that are classified as endangered under the Endangered Species Act. Principal activities involving other wildlife on the site include biological monitoring and population control. Land reclamation and erosion control activities are underway to revegetate bare or altered areas.

The Site Use Coordination System established by the United States Department of Energy Savannah River Office (DOE-SR) ensures that land use at the SRS is managed in a way that meets mandated preservation requirements for endangered species and historical and cultural resources, promotes multiple, beneficial uses of the site, and does not interfere substantially with the prime mission of the SRS. This system coordinates the review and approval of site use requests for land not dedicated to production activities.

The SRS provides a wide range of habitats for animal populations: over 400 species of mammals, birds, fish, reptiles, and amphibians have been documented on the site. Four endangered animal species have been sighted at the SRS.

The SRS was designated the nation's first NERP in 1972 and has become one of the most extensively studied environments in this country. The NERP designation recognized the value of the environmental databases developed by previous Savannah River Laboratory (SRL) and Savannah River Ecology Laboratory (SREL) research, and also the protection provided to field research sites located at the site. Scientific investigators from universities and other research organizations are encouraged to use the NERP as an outdoor laboratory for environmental impact studies.

Natural resource management (e.g., land and timber management) is conducted principally by the U.S. Forest Service Savannah River Forest Station (SRFS) with support provided by the operating contractor. Approximately one-half of the budget for land use activities is expended in providing services such as maintenance of equipment, buildings, and roads.

The principal activities involving other wildlife on the SRS are research studies and population control. The studies consist of biological monitoring and are described in Section 3.6.2 of the Surface Waters and Wetlands Protection Program. Public deer hunts are managed by the operating contractor with assistance from other onsite and offsite contractors. Beaver and other nuisance animals are controlled by trapping.

On-site land reclamation activities began in 1974 with revegetation efforts by SRFS. Currently, both SRFS and the operating contractor have programs to revegetate bare or altered areas. Erosion control activities and resource requirements are given in Subsection 6.6.5 of the Surface Waters and Wetlands Protection Program.

Total cost for the land use and wildlife protection program during the five-year planning period is expected to be \$17.1 million, which includes 238 man-years of effort.

5.0 LAND USE AND WILDLIFE PROTECTION PROGRAM

5.2 Policy

5.2.1 Policy Statement

The Savannah River Site (SRS) land use and wildlife protection policy is to develop the site to meet operational requirements, restore impacted lands where appropriate, and manage site lands and wildlife in a manner that satisfies regulatory and operating contractor requirements while supporting DOE and other contractor programs.

5.2.2 Background for Policy Statement

The United States Department of Energy (DOE) and the operating contractor, are committed to operating the SRS in a manner that protects the public health and safety, and the environment. This philosophy is contained in DOE Order 5400.1, General Environmental Protection Program, and in the SRS *Strategic Environmental Plan* (1986). Additional guidance for land use and wildlife protection at the SRS are given in the following documents:

- Savannah River Operations Office (DOE-SR) Fish and Wildlife Management Policy for the Savannah River Plant (6-18-86)
- DOE Order 4300.1B, Real Property and Site Development Planning, (7-1-87)
- SR Order SR-430X.1, Site Use Coordination and Approval, (9-13-83).

5.0 LAND USE AND WILDLIFE PROTECTION PROGRAM

5.3 Existing Conditions

Current land use on the Savannah River Site (SRS) reflects the activities of the multiple site users. About five percent of the area composing the site is developed. Approximately 13 square kilometers are occupied by production, support, and waste packaging facilities and 29 square kilometers by transportation arteries and right-of-ways.

In 1951 when the 780-square-kilometer site was acquired, the land was approximately two-thirds forested and one-third cropland and pasture. Subsequently, the abandoned fields were planted with various species of pine trees or were allowed to pass through vegetational succession. Today, approximately 95 percent of the site is forested. Wetlands, creeks, floodplains, lakes, and the Savannah River Swamp account for approximately 160 square kilometers. The extensive wetlands and the prevalence of forest acreage gives the site a markedly different character than the surrounding agricultural and urban areas.

During the construction of facilities, roads, and dams, about eight square kilometers of spoil piles and borrow pits were created. Initial attempts to revegetate these areas were not successful and, in many cases, severe soil erosion has resulted. More recently, the Savannah River Forest Station (SRFS) has reclaimed approximately two square kilometers through revegetation.

The Department of Energy (DOE) Site Use Coordination System established under Savannah River (SR) Order 430X.1 ensures that land use at the SRS is managed in a way that meets mandated preservation requirements for endangered species (e.g., the Endangered Species Act of 1973) and historical and cultural resources (e.g., the National Historic Preservation Act of 1966), promotes multiple, beneficial uses of the site (e.g., environmental/ecological research and forest management), and does not interfere substantially with the prime mission of the SRS.

In 1972, the SRS was designated the first National Environmental Research Park (NERP) and has become one of the most extensively studied

environments in the country. The NERP designation recognized the value of the environmental databases developed by previous Savannah River Laboratory (SRL) and Savannah River Ecology Laboratory (SREL) research and also the protection provided to field research sites located at the SRS. Scientific investigators from universities and other research organizations are encouraged to use the NERP as an outdoor laboratory for studies of the environmental impact of man's activities. In 1986, ten research projects were conducted at the site under the NERP Program.

The SRS provides a wide range of habitats for animal populations; over 400 species of mammals, birds, fish, reptiles, and amphibians have been documented on the site. Many of these species were present onsite at the time of government acquisition and closure to the public. Subsequent changes in the vegetation cover and an intensive pine planting program by the SRFS have brought about changes in the numbers of some species.

The ecosystems at the SRS support many commercially and recreationally valuable game populations; however, the DOE restricts recreational use to controlled hunts for white-tailed deer and feral hogs. Some species, such as the wood duck, bullfrog, and various species of turtles, are mobile and migrate offsite where activities such as hunting are allowed.

In addition to the NERP designation, ten reserve sites within the boundaries of the SRS were selected by the SREL as representative of major site vegetational communities and were formally set aside in 1967 by the DOE to promote ecological research. Two additional natural research areas are registered with the Society of American Foresters and are also protected from development. At the DOE's request, the operating contractor and other contractors have identified examples of additional habitats appropriate for reserve status which are being considered for future designation by the DOE.

Several endangered species inhabit the site. A nesting pair of bald eagles was located near PAR Pond and raised two young in 1986 and two in 1987. From a recent census, the red-cockaded woodpecker was found in three colonies distributed in mature pine stands. In the Savannah River, larvae of the shortnose sturgeon were found. Evidence also indicates sturgeon spawning both upriver and downriver from the site. In swamps on and around the site, the wood stork has been observed feeding during the summer months. The American alligator, another species protected under the Endangered Species Act, has a wide distribution in wetlands on the site. On June 4, 1987, the status of the alligator under the Act was changed from

threatened, to threatened on the basis of similarity of appearance. Under this new classification, approval from the U.S. Fish and Wildlife Service (FWS) must be obtained before taking, moving, or killing alligators or destroying their nests.

The FWS has additional plants, invertebrates, and vertebrates that are considered candidate species for the list of endangered and threatened wildlife and plants. Of these candidate species, two insects, the American sand-burrowing mayfly and the blackwater sand-filtering mayfly and approximately eight species of plants are found on the SRS. The latter are as follows: cypress stump sedge, Elliot's croton, smooth purple coneflower, bog-spice bush, swamp lobelia, loose water milfoil, *Nestronia*, and the awned meadow-beauty.

South Carolina also has a listing of species considered to be endangered within the state and protected by state law. Over 50 plants and animals on the South Carolina list are found onsite.

The site is in compliance with the requirements of the Endangered Species Act of 1973.

More than 800 prehistoric and historic archaeological sites are within the boundaries of the SRS. New sites are being located as intensive surveys by the University of South Carolina Institute of Archaeology and Anthropology (USCIAA) continue. The operating contractor cooperates with the USCIAA in implementation of the National Preservation Act of 1966.

5.0 LAND USE AND WILDLIFE PROTECTION PROGRAM

5.4 Objectives

The objectives to support the Land Use and Wildlife Protection Program are shown below. The strategy to achieve these objectives is illustrated in Section 5.5 followed by programmatic details in Sections 5.6 and 5.7.

- **Land Regulations**—Comply with all applicable federal and state land preservation/management laws and regulations.
- **Land Use Coordination**—Coordinate land development plans with DOE and other contractor programs.
- **Land Reclamation**—Continue land reclamation programs where practical.
- **Wildlife Regulations**—Comply with all applicable federal and state wildlife laws and regulations.
- **Understanding Impacts**—Understand the effects of plant operations by quantifying the impacts to site lands and wildlife.
- **Manage Wildlife Populations**—Manage wildlife populations to ensure employee safety and to protect Savannah River Site facilities.

5.0 LAND USE AND WILDLIFE PROTECTION PROGRAM

5.5 Strategy

The strategy for reaching the Land Use and Wildlife Protection Program objectives is to:

- Identify regulatory and other protection requirements
- Promote innovative and cost-effective means of meeting the requirements through research and development
- Develop physical and administrative controls to protect wildlife and land by utilizing the knowledge gained from the research and development efforts
- Implement physical and administrative controls
- Evaluate the controls to ensure that protection requirements are met.

The strategy is illustrated in Figure 5.5-1. Programmatic details are presented in Section 5.6.

FIGURE 5.5-1 LAND USE AND WILDLIFE PROTECTION PROGRAM STRATEGY

LAND USE AND WILDLIFE PROTECTION PROGRAM

5.6 Implementation

The implementation section identifies issues and those responsible for actions to achieve defined objectives. Each environmental effort will require funding for one or more of the following: research and development, operations, programs, and construction/modification projects. The resource requirements span a five-year period from FY89 through FY93.

The operating costs used throughout the text are expressed in FY89 dollars and are not escalated. Costs include subcontractor, manpower, and other operations expenses. Total costs include cost of research and development, operations, manpower, and subcontractors. Detailed cost tables are presented in Section 5.7.

Annual manpower costs are calculated using these factors: SRS Monthly Salary (MS) at \$59,500 and all Local Roll (LR) at \$40,000.

5.6.1 Land Use

5.6.1.1 Site Program Overview

Activities to improve land use at the Savannah River Site (SRS) include research, site use coordination, natural resource management, and required supporting services. Ongoing research focuses on developing remote sensing technologies, evaluating databases to enhance the knowledge of natural processes and the effects of man's activities on them, and to comply with regulatory requirements and commitments. About 20 percent of the National Environmental Research Park (NERP) budget for the site is managed by the operating contractor. These funds are currently used to support onsite research by university scientists.

Land use activities outside of production area fences are coordinated under the Department of Energy Savannah River (DOE-SR) Site Use Coordination System. The operating contractor and other onsite contractors participate through a site use permit system.

Natural resource management (e.g., land and timber management) is conducted principally by Savannah River Forest Stations (SRFS). The SRFS is supported in this activity by the operating contractor. Approximately 80 percent of the budget for land use activities is expended in providing services such as maintenance of equipment, buildings, and roads.

The total cost for the land use program over the five-year planning period is \$14.8 million which includes 24 man-years (MS) and 191 man-years (LR).

5.6.1.2 Justification/Regulatory Requirements

The SRS is managed by the DOE-SR to meet the requirements of DOE Order 4300.1B, Real Property and Site Development Planning (7-1-87), and the objectives of the NERP Program. Environmental objectives established for NERP sites include a search for new techniques to measure environmental changes, development of better tools to predict environmental response to human activities, and demonstration of methods to minimize adverse impacts.

The land use program supports the land regulations, land use coordination, and understanding impacts of objectives described in Section 5.4.

5.6.1.3 Organizational Responsibilities Summary

Land use management is administered by the DOE-SR and the onsite contractors. The DOE-SR Site Use Coordination System governs the approval of land use not previously approved. Site contractors have land use management responsibilities in the approved areas under the guidelines established in the initial land use approval. In addition, custodial departments of the operating contractor manage land use within the boundaries of the production areas and in cleared areas associated with various right-of-ways.

The major organizations conducting environmental research on the site are the Savannah River Laboratory (SRL, primarily the Environmental Sciences and Environmental Technology Sections), Savannah River Ecology Laboratory (SREL), and Savannah River Forest Service (SRFS). These organizations conduct programs to provide information essential to achieving environmental goals and for evaluating the effects of operating nuclear production facilities.

Natural resource management activities (e.g., forestry management) are conducted principally by the SRFS under an interagency agreement with DOE.

5.6.1.4 Programs

Site Development and Facility Utilization Plan

•**Long Range Planning (LRP)**—The Site Development and Facility Utilization Plan for the SRS was issued April 1, 1987. The plan will be maintained and kept current. Revisions will be distributed to plan holders at least annually and the plan will be totally revised every five years.

The estimated total five-year program cost \$1,409,500.

Site Use Coordination System

Site coordination outside the boundaries of the existing production areas is governed by SR Order 430X.1, Site Use Coordination and Approval. The operating contractor manages land use within the boundaries of the production areas and for cleared areas associated with various right-of-ways in accordance with Projects Management Procedure 5.3 (formerly Memorandum B-23).

•**Environmental Protection Section (EPS)**—The EPS currently coordinates the review of site use permits with regard to potential impacts on the environment. The estimated total five-year cost is \$148,750.

•**Projects Management**—Requests for changes to the site initiated within the operating contractor and necessitating site clearance, removal of trees, or issuance of land use permits are submitted to the Projects Management for authorization, as detailed in SRS Procedures Manual Item 1201. Other requests initiated by SRS are submitted directly to the DOE-SR for approval. Plant service groups are kept informed to ensure that their day-to-day activities do not jeopardize environmental and ecological research projects.

The estimated total five-year program cost is \$859,875.

Support to Land and Timber Management

•**Central Services Works Engineering (CSWE)**—The CSWE provides support services such as building maintenance, contracting outside vehicle and equipment maintenance with local vendors, furnishing fuel, issuing supplies, radio maintenance, and implementing road management plans.

The estimated total five-year cost is \$12,265,000.

Programs by Other Onsite Contractors

Forest management is performed almost exclusively by the SRFS and includes such activities as timber harvesting, site preparation, reforestation, timber stand improvement, prescribed burning, wildlife management, soil reclamation, management of secondary roads, and research support.

Soil classification and mapping of the SRS is a current project of the Soil Conservation Service. This information will be used in planning, managing, and harvesting woodland crops; locating and designing research plots; locating sources of soil materials of high density and low permeability; locating and designing roads, parking areas, buildings, and spray fields; and managing wildlife resources.

5.6.1.5 Research/Studies

Remote Sensing

SRL Environmental Sciences Section (ESS)

Data is being gathered from satellite and airborne sensor systems during overflights of the SRS to provide a database of those areas of the site that are difficult to study on the ground. Evaluating these data will provide both a temporal and spatial assessment of the effects of SRS operations on terrestrial and aquatic environments of the site. Additional information on the remote sensing studies, including funding, manpower, and milestones, can be found in Section 3.6.2 (Surface Waters and Wetlands Protection Program) and Section 6.6.7 (Waste Site Closure).

National Environmental Research Park (NERP)

The SRS is designated a NERP. This site is an outdoor laboratory set aside for ecological research on the environmental impacts of SRS operations and to aid in informing the public of available environmental and land use options. However, the research at the park is regional in approach, and activities are not limited to those environmental concerns and species native to the SRS. In this regard, SRS lands are viewed as a national resource with potential for contributing to a wide variety of environmental research issues.

The NERP program is conducted by the SRL, SREL, SRFS, and their contractors, and by scientists with outside funding cooperating with one of these organizations. The SRL uses NERP program resources to support university research. At the SREL, NERP program resources are used to support and facilitate applied research activities rather than to actually conduct such work. Support is provided for basic ecological studies and long-term baseline assessments of the flora, fauna, and other important environmental factors.

SRL - Environmental Sciences Section (ESS)

In 1988 and 1989, the NERP provided seed support for studies on the microbiological components of the subsurface environment. In 1987 in excess of 1000 different organisms were found to a depth of 800 feet. This finding has potentially great significance to the fate of groundwater pollutants. Certain of these organisms are new to science and may be very useful in biotechnology applications. The program is a cooperative one with universities and national laboratories (Florida State, Cornell, Oklahoma, Penn State, Tennessee, PNL, and ORNL). The program provides essential information about the influence of the subsurface community on nutrients and wastes. It will provide important insight into the longevity of containers used to retain hazardous wastes.

The NERP also supports a travel fund to permit well-known scientists to visit the Savannah River National Environmental Research Park. On their visits, they provide seminars to keep SRL employees up-to-date with the latest approaches to environmental research. This program is extremely productive, providing our staff with insights that result in cost-effective

alterations in our program areas and informing the visiting scientist of research opportunities at the NERP.

The estimated total five-year cost is \$147,000. No manpower costs are expected.

5.0 LAND USE AND WILDLIFE PROTECTION PROGRAM

5.6.2 Endangered Species

5.6.2.1 Site Program Overview

Most of the current activities in direct support of threatened and endangered species are conducted by the Savannah River Ecology Laboratory (SREL) and Savannah River Forest Station (SRFS). Aside from biological monitoring described in Section 3.6.2 (Surface Waters and Wetlands Protection Program), the operating contractor's involvement is limited to participation in a technical working group. This group follows the status of the wood stork in the vicinity of the Savannah River Site (SRS) and recommends research and management needs. Potential impacts on endangered species from new activities are identified in the planning stage of each activity through use of a National Environmental Protection Act (NEPA) checklist and are addressed through consultations with the appropriate governmental organizations.

5.6.2.2 Justification/Regulatory Requirements

Federal Law

•Endangered Species Act of 1973 (16 USC 1531-1543)—The Endangered Species Act requires every federal agency to ensure that its actions and those of its contractors are not likely to jeopardize the continued existence of any endangered or threatened species or result in the destruction or adverse modification of a critical habitat, unless an exemption as defined in Sections 1536(a)(2) and (h), has been granted by the Endangered Species Committee.

No permits are required to comply with the Act. However, in the case of anadromous species consultation with the U.S. Fish and Wildlife Service (FWS), or the National Marine Fisheries Service (NMFS), is required for a proposed project. A biological assessment may be required if the FWS or NMFS indicates that a threatened or endangered species might be found.

State Law

• **South Carolina Nongame and Endangered Species Act (Code of Laws of South Carolina, Title 50, Chapter 15)**—The South Carolina Nongame and Endangered Species Act protects state nongame species in need of management and species listed by the State as endangered. Consultation with the South Carolina Wildlife and Marine Resources Commission (WMRC) is required if a listed species is present in an area to be disturbed by construction or ongoing operation of a new facility.

The endangered species program supports the Wildlife Regulations objective in Section 5.4.

5.6.2.3 Organizational Responsibilities Summary

When planning begins on an activity with a high potential for environmental impact, on a test authorization, or on any activity (other than direct work/repair orders) that costs \$250,000 or more, it is the responsibility of the operating contractor department or division initiating the activity to complete a NEPA Safety Analysis and Environmental Permit Checklist (OSR 14-347) that identifies whether or not an endangered species might be impacted by the proposal activity. If an endangered species might be impacted, the Department of Energy Savannah River (DOE-SR) initiates contact with the Regional Field Station of the FWS. If there is a potential for affecting endangered marine species, the regional office of the NMFS is also contacted. If it is found that an endangered species could potentially be affected, the DOE-SR will supervise the information-gathering necessary for a biological assessment of the impact on the species.

5.6.2.4 Management Programs

Two Savannah River Forest Station (SRFS) programs for the protection of endangered species are of sufficient importance to be noted:

- The Southern Bald Eagle Management Plan includes designation of a Territory Management Zone to provide additional protection for the species. Highly regarded offsite, this program serves as a model for USFS projects elsewhere.
- The Red-Cockaded Woodpecker Management Plan includes management of over 400 square kilometers (100,000 acres) of forest, mostly pine, for the benefit of the woodpecker. Conditions favorable to the

species are being established through longer rotation, to allow pines to attain older age before harvest, and by controlled burning to remove understory species and maintain a more open pine forest.

5.6.2.5 Research/Studies

Wood Stork Technical Working Group

• **SRL - Environmental Sciences Section (ESS)**—The ESS is a member of a technical working group which is recommending research and management for the wood stork on the SRS. Other members of the group include the DOE, SREL, FWS, and the National Audubon Society (NAS). The group meets annually to discuss the current status of the species on the site and management of the NAS Kathwood Lake foraging site. The ESS has consulting agreements with scientists specializing in endangered species. These scientists review and make recommendations on the management of the species. The estimated total five-year manpower cost is \$5950.

Research/Studies by Other Onsite Contractors

The SREL is currently conducting several research projects on threatened or endangered species under their Stress and Wildlife Ecology Program. Among these projects are:

- A study to assess the effects of cooling water discharges on the American alligator and shortnose sturgeon and their associated habitats.
- A telemetric study of the American alligator to provide predictive information regarding the fate of other species in a thermally altered area.
- A population genetics study of the red-cockaded woodpecker to aid in the introduction of red-cockaded woodpeckers from other areas to the SRS.
- A study to evaluate the importance of the Savannah River Swamp System to the wood stork to determine its foraging requirements.

- A survey of rare and endangered plant species onsite to determine their presence, distribution, and abundance.

The U.S. Forest Service-Southeastern Forest Experiment Station (SEFES) currently has a program for the re-establishment of the red-cockaded woodpecker at the SRS. The objectives of this program include recommending modifications to existing habitat, reintroducing red-cockaded woodpeckers to the SRS from other offsite populations, and monitoring the reproductive and adaptive success of the existing and relocated populations.

5.0 LAND USE AND WILDLIFE PROTECTION PROGRAM

5.6.3 Other Wildlife

5.6.3.1 Site Program Overview

The principal activities involving other wildlife on the site are research/studies and population control. The operating contractor's studies consist of biological monitoring and are described in Section 3.6.2 of the Surface Waters and Wetlands Protection Program. Public deer hunts are managed by the operating contractor with assistance from other on-site and off-site contractors. These hunts are significant operations as measured by the site area involved and extent of funding required. Beaver and other nuisance animals are controlled by trapping. Funding for beaver and other nuisance animal control is relatively small.

The total cost for the other wildlife program over the five-year planning period (FY89 through FY93) is \$1.6 million which includes 10 (MS) and 11 (LR) man-years of effort.

5.6.3.2 Justification

DOE Order

•**Real Property and Site Development Planning (DOE 4300.1B)**—Chapter VIII, Management of Natural Resources, of this order states that all installations having suitable land and water areas will have programs for the harvesting of fish and wildlife by the public, provided it does not interfere with site missions.

DOE-SR Site Policy

•**Fish and Wildlife Management Policy for the Savannah River Plant (SR Announcement No. SR-86-35)**—It is the policy of the Department of Energy Savannah River (DOE-SR) to effectively manage fish and wildlife resources of the Savannah River Site (SRS) to maintain their biological productivity and diversity. In addition, animals are hunted and trapped only to control safety hazards or excessive property damage.

Ongoing activities involving other wildlife support and manage the wildlife populations objective as stated in Section 5.4.

5.6.3.3 Organizational Responsibilities Summary

The main organizations conducting environmental research at the SRS are the Savannah River Laboratory (SRL, primarily the Environmental Sciences and Environmental Technology Sections), Savannah River Ecology Laboratory (SREL), and Savannah River Forest Station (SRFS). These programs provide information essential to achieving environmental goals and for evaluating the effects of operating nuclear production facilities.

The Safeguards and Security Section, with support from the Environmental Monitoring Section (EMS) and Central Services Works Engineering (CSWE) Section, manages public hunts for deer and feral hogs at the SRS. Nuisance beaver are controlled under a contract with a local vendor that is funded, as necessary, by the SRFS, SREL, EMS, and CSWE and administered by the Environmental Protection Section (EPS) with assistance from the SRFS.

5.6.3.4 Management Program

Management of Deer Hunting

Animal hunts are conducted at the SRS to control the resident deer and hog populations and to reduce animal-automobile accidents. The 1988 hunts yielded 855 deer and 146 hogs (roughly the same as the number of deer and hogs collected in 1985). The hunts are expected to be conducted and managed in the current manner for the next five years.

•**Central Services Works Engineering (CSWE)**—The CSWE provides transportation for hunters from the security gate entrances of the plant to designated hunting areas and back. The CSWE also plans and coordinates the deer hunts.

The estimated total five-year cost is \$735,500.

•**Environmental Monitoring Section (EMS)**—All animals are monitored for radioactivity before they are released to the hunters. The maximum ^{137}Cs concentration in muscle tissue of deer collected in the 1988 hunts was 60 pCi/g. The average concentration of ^{137}Cs was 10.2 ± 11 pCi/g. Measurements of ^{137}Cs in hogs were somewhat lower with a

maximum of 16 pCi/g and an average of 6 ± 7.4 pCi/g. The estimated total five-year cost is \$674,500.

•**Safeguards and Security (SG&SEC).** Security and safety briefings are provided to the hunters before each hunt.

The estimated total five-year cost is \$29,750.

Control of Nuisance Animals

Beaver activity (e.g., blocking culverts) frequently impounds surface water, which can kill valuable trees, undercut roadbed embankments, and inundate or prevent access to monitoring stations and research facilities. Other nuisance animals include dogs, cats, skunks, snakes, rabbits, etc., that stray into operating areas of the SRS.

•**Environmental Protection Section (EPS)**—EPS administers the contract for beaver control which is funded by USFS, SREL, EMS, and CSWE. The EPS resource requirements for administering this contract are minimal.

•**Central Services Works Engineering (CSWE)**—The estimated total five-year cost to CSWE for beaver control is \$69,750.

•**Environmental Monitoring Section (EMS)**—The estimated total five-year cost to EMS for control of other nuisance animals is \$41,475.

Management by Other Onsite Contractors

Under an interagency agreement with the DOE, wild turkeys were formerly netted onsite by the South Carolina Wildlife and Marine Resources Department (SCWMRD) for purposes of stocking offsite areas. Although the need for transplanted birds does not currently exist, a new cooperative agreement between the two agencies provides for resumption of the activity should the need arise.

5.6.3.5 Research/Studies

Plans to Mitigate Fish Kills in Pond C

•**SRL - Environmental Sciences Section (ESS)**—A plan of action has been developed and proposed to, the South Carolina Department of Health and Environmental Control (SCDHEC) to address their concerns over fish kills in Pond C, a body of water in the PAR Pond system that receives heated effluent from P Reactor. Major fish kills have been related to restarts of P Reactor after extended shutdowns. The plan involves raising the outlet crib where Pond C water flows into PAR Pond to approximately one foot above the normal water level of Par Pond. This would provide mitigation by two mechanisms. First, migration of fish from PAR Pond into Pond C would be stopped and secondly, the water level of Pond C would be raised, providing more cool water refuge space for native fish. Studies are also being conducted to mitigate fish kills on L Lake following L Reactor startup.

Cost and manpower requirements are shown in Section 3.6.2 (Surface Waters and Wetlands Protection Program).

Biological Monitoring

•**SRL - Environmental Sciences Section (ESS)**—Several ongoing studies are assessing the cumulative effects of thermal discharges to on-site surface waters from SRS facilities. These studies are being done to ensure that waters which receive thermal discharges maintain a balanced indigenous biological community. The studies include 316(a) studies of the K Reactor cooling water system, the D Area powerhouse discharge, and the biological monitoring of L Lake and Steel Creek. A 316(a) demonstration was initiated in Beaver Dam Creek to determine if the stream supports a balanced biological community, following implementation of thermal mitigation in D Area. The ESS initiated a biological monitoring program in Par Branch and Indian Grave Branch to document recovery of these ecosystems subsequent to the shutdown of K Reactor in April 1988.

Additional information including funding, manpower, and milestones for these thermal mitigation studies can be found in Section 3.6.2 (Surface Waters and Wetlands Protection Program).

The ESS is participating in the SRS Biodiversity Program. This program is organized around a Steering Committee with representation from the DOE-

SR, SRFS, Westinghouse Savannah River Company (WSRC), and SREL. The objectives are to assess the biodiversity of habitats on the site, and develop programs to enhance biodiversity. The estimated total five-year cost is \$29,750.

Research/Studies by Other Onsite Contractors

The SREL, operated by the University of Georgia Institute of Ecology, has several programs to develop an understanding of the impact of various energy technologies and management practices on the ecosystems of the southeastern United States. The SREL research is conducted by interdisciplinary research teams organized under three major divisions: (1) Biogeochemical Ecology; (2) Stress and Wildlife Ecology; and (3) Wetlands Ecology. Wildlife studies are included in the following SREL programs: Radioecology, Environmental Operations Support, Foraging and Breeding Ecology of the Wood Stork, L Lake and Steel Creek Corridor, and Environmental Stresses from the SRS Operations.

5.0 LAND USE AND WILDLIFE PROTECTION PROGRAM

5.6.4 Wildlife Habitat

5.6.4.1 Site Program Overview

The effect of some Savannah River Site (SRS) activities on wildlife habitat is assessed in support of the National Environmental Policy Act (NEPA) documentation. This has included the completion of two Environmental Impact Statements (EISs): *Waste Management Activities for Groundwater Protection at the Savannah River Plant*, and *Alternative Cooling Water Systems—Savannah River Plant*. In addition, the Savannah River Ecology Laboratory (SREL) conducts wildlife habitat studies under several ongoing programs.

Funding and manpower for studies of wildlife habitat, which support the NEPA reviews, are included in Section 3.6.2 of the Surface Waters and Wetlands Protection Program and Sections 6.6.6 and 6.6.7 of the Groundwater Protection Program.

5.6.4.2 Justification/Regulatory Requirements

National Environmental Policy Act (42 USC 4321-4347)—The NEPA directs federal agencies who propose actions significantly affecting the quality of the environment to evaluate the impact of the action on the environment. The preparation of an EIS is required for major federal actions.

Ongoing activities involving wildlife habitats support the wildlife regulations and understanding impacts objectives which are discussed in Section 5.4.

5.6.4.3 Organizational Responsibilities Summary

The major organizations conducting environmental research on the site are Savannah River Laboratory (SRL, primarily the Environmental Sciences and Environmental Technology Sections), SREL, and Savannah River Forest Station (SRFS). The programs conducted by these organizations provide information essential to achieving environmental goals and for evaluating the effects of operating nuclear production facilities. The SRFS

uses forest management as a tool for providing open areas and a diversity of forest habitats for wildlife.

Potential impacts on wildlife habitat from proposed new activities are identified in the planning stage by the operating contractor department/division initiating the activity (see NEPA Checklist, Subsection 5.6.2.3). Potential impacts are assessed in a NEPA review and in a Site Use Permit review (see Subsection 5.6.1.3), and mitigated as needed.

5.6.4.4 Research/Studies

Waste Management Activities for Groundwater Protection EIS Alternative Cooling Water Systems EIS

•**SRL-Environmental Sciences Section (ESS)**—The effect of certain SRS activities on wildlife habitat is described in two EISs. In the EIS on waste management activities for groundwater protection, the closure of existing waste disposal sites, the construction of new waste management facilities for low-level radioactive and hazardous materials, and the disposal of tritiated wastewater from reactor disassembly basins are discussed. The analysis considered the effect of hazardous substances reaching terrestrial and aquatic habitats by surface water runoff and the uptake by terrestrial vegetation or surface water by the passage of hazardous substances through the groundwater. The EIS on alternative cooling water systems evaluated the potential effects on receiving stream systems from the proposed cooling tower alternatives for C and K Reactors and D Powerhouse. For additional information on the NEPA Activities Group see Section 4.2.

Research/Studies by Other Onsite Contractors

The SREL, operated by the University of Georgia Institute of Ecology, conducts research that will develop an understanding of the impact of various energy technologies and management practices on the ecosystems of the southeastern United States. The titles of SREL wildlife habitat studies currently underway on the site include: Wetland Ecosystem Processes, Environmental Operations Support, Defense Waste Processing Facility-Ecological Effects of Construction, the L Lake and Steel Creek Corridor, Ecosystem Alteration by Chemical Pollutants, Systems Ecology, and L Lake Shoreline Vegetation Establishment.

5.0 LAND USE AND WILDLIFE PROTECTION PROGRAM

5.6.5 Land Reclamation and Erosion Control

5.6.5.1 Site Program Overview

Onsite land reclamation activities began in 1974 with revegetation efforts by the Savannah River Forest Station (SRFS). Currently, both the SRFS and operating contractor have programs to revegetate bare or altered areas.

The total cost for the land reclamation program over the five-year planning period is \$648,750 which includes 2.5 man-years of effort.

5.6.5.2 Justification/Regulatory Requirements

South Carolina Standards

•**South Carolina Water Classification Standards (SCDHEC 61-88)**—These standards require that all Savannah River Site (SRS) navigable waters meet Class B Water Quality Standards, which include limits on total suspended solids and pH.

Ongoing and planned land reclamation activities support the land reclamation objective described in Section 5.4.

DOE Order

•**DOE Order 4300.1B, Real Property and Site Development Planning (7-1-87)**—The order states that the Department of Energy (DOE) will manage its real properties in a way that conserves soil, water, and plants.

5.6.5.3 Organizational Responsibilities Summary

Plans for the rehabilitation of disturbed onsite lands are being developed by the Power and Power Engineering Sections. Implementation of these plans will extend the useful life of SRS waste disposal facilities while converting bare areas into more useful habitat for wildlife. The SRFS has conducted soil stabilization activities in forested areas of the site since 1974.

Erosion control measures are the responsibility of Construction for construction projects, custodial departments for fenced areas, and Central Services Works Engineering for all areas outside the fences which are not controlled by other onsite contractors. Additional information on organizational responsibilities is given in Subsection 3.6.6.3.

5.6.5.4 Programs

Land Reclamation

•**Power Operations and Power Engineering**—Sanitary sludge from SRS wastewater treatment facilities is now being applied to a SCDHEC permitted borrow pit land reclamation site in F Area. An additional pit is available in H Area for future use. Borrow pits are sites where sand or gravel was removed during construction of plant facilities. These sites will benefit from application of sludge, which acts as a soil conditioner and promotes revegetation.

A similar program has been established for disposal of powerhouse ash. Ash is being removed from existing ash basins to extend the useful life of the basins. This ash is being placed in borrow pit land reclamation sites, which are then filled in and revegetated. In addition, the ash will also be used as a fill material to reclaim abandoned ash basins.

The estimated total five-year cost is \$648,750.

Erosion Control

Erosion control activities and resource requirements for operating contractor organizations are given in Section 3.6.6.5.

Programs by Other Onsite Contractors

Soil stabilization activities by the SRFS to control soil erosion began in 1974. Since then, more than two square kilometers of bare area has been revegetated. In 1986 approximately 0.25 square kilometers were reshaped, subsoiled, and planted with legumes to provide wildlife food while controlling erosion.

5.0 LAND USE AND WILDLIFE PROTECTION PROGRAM

5.6.5 Land Reclamation and Erosion Control

5.6.5.1 Site Program Overview

Onsite land reclamation activities began in 1974 with revegetation efforts by the Savannah River Forest Station (SRFS). Currently, both the SRFS and operating contractor have programs to revegetate bare or altered areas.

The total cost for the land reclamation program over the five-year planning period is \$648,750 which includes 2.5 man-years of effort.

5.6.5.2 Justification/Regulatory Requirements

South Carolina Standards

•**South Carolina Water Classification Standards (SCDHEC 61-88)**—These standards require that all Savannah River Site (SRS) navigable waters meet Class B Water Quality Standards, which include limits on total suspended solids and pH.

Ongoing and planned land reclamation activities support the land reclamation objective described in Section 5.4.

DOE Order

•**DOE Order 4300.1B, Real Property and Site Development Planning (7-1-87)**—The order states that the Department of Energy (DOE) will manage its real properties in a way that conserves soil, water, and plants.

5.6.5.3 Organizational Responsibilities Summary

Plans for the rehabilitation of disturbed onsite lands are being developed by the Power and Power Engineering Sections. Implementation of these plans will extend the useful life of SRS waste disposal facilities while converting bare areas into more useful habitat for wildlife. The SRFS has conducted soil stabilization activities in forested areas of the site since 1974.

Erosion control measures are the responsibility of Construction for construction projects, custodial departments for fenced areas, and Central Services Works Engineering for all areas outside the fences which are not controlled by other onsite contractors. Additional information on organizational responsibilities is given in Subsection 3.6.6.3.

5.6.5.4 Programs

Land Reclamation

•**Power Operations and Power Engineering**—Sanitary sludge from SRS wastewater treatment facilities is now being applied to a SCDHEC permitted borrow pit land reclamation site in F Area. An additional pit is available in H Area for future use. Borrow pits are sites where sand or gravel was removed during construction of plant facilities. These sites will benefit from application of sludge, which acts as a soil conditioner and promotes revegetation.

A similar program has been established for disposal of powerhouse ash. Ash is being removed from existing ash basins to extend the useful life of the basins. This ash is being placed in borrow pit land reclamation sites, which are then filled in and revegetated. In addition, the ash will also be used as a fill material to reclaim abandoned ash basins.

The estimated total five-year cost is \$648,750.

Erosion Control

Erosion control activities and resource requirements for operating contractor organizations are given in Section 3.6.6.5.

Programs by Other Onsite Contractors

Soil stabilization activities by the SRFS to control soil erosion began in 1974. Since then, more than two square kilometers of bare area has been revegetated. In 1986 approximately 0.25 square kilometers were reshaped, subsoiled, and planted with legumes to provide wildlife food while controlling erosion.

5.0 LAND USE AND WILDLIFE PROTECTION PROGRAM

5.7 Resource Requirements

The manpower and funding requirements are shown on the following tables for the five-year planning period FY89 through FY93 for the Land Use and Wildlife Protection Program. Manpower requirements (Monthly Salary and Local Roll) over the next five years are 36 and 202 man-years, respectively. The manpower, operating and total cost schedules for each issue are presented in Table 5.5.1 through 5.5.3. No requirements for capital funds were identified in this planning period. Total funding required over the five-year planning period is \$17.1 million. Approximately 87 percent of the total budget is required for land use activities (primarily to support land and timber management).

Similar schedules of manpower and cost requirements for each department are presented in Appendix Tables 5.5.1A through 5.5.3A.

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
5.0 LAND USE AND WILDLIFE PROTECTION
5.7 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 2 of 4

LANDUSE AND WILDLIFE PROTECTION PROGRAM

5.7 RESOURCE REQUIREMENTS

ISSUE	FY 89		FY 90		FY 91		FY 92		FY 93		TOTAL	
	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR
5.6.1 LAND USE	283	1524	283	1524	283	1524	283	1524	283	1524	1413	7620
5.6.2 ENDANGERED SPECIES	3	0	3	0	0	0	0	0	0	0	0	0
5.6.3 OTHER WILDLIFE	114	88	114	88	114	88	114	88	114	88	558	410
5.6.4 WILDLIFE HABITAT	0	0	0	0	0	0	0	0	0	0	0	0
5.6.5 LAND RECLAM. & EROSION CONTROL	30	0	30	0	30	0	30	0	30	0	149	0
TOTAL	428	1612	428	1612	426	1612	426	1612	426	1612	2130	8060

* VALUES ARE THOUSANDS OF FY88 DOLLARS.

**ANNUAL MANPOWER COSTS BASED ON: MS = \$69.5M (SR5); LR = \$40M (SR5).

TABLE 5.7.1 MANPOWER REQUIREMENTS SCHEDULE (\$M)**

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
5.0 LAND USE AND WILDLIFE PROTECTION
5.7 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 3 of 4

LANDUSE AND WILDLIFE PROTECTION PROGRAM

5.7 RESOURCE REQUIREMENTS

ISSUE	FY 88	FY89	FY81	FY82	FY83	TOTAL
5.6.1 LAND USE	1137	1090	1090	1390	1090	5797
5.6.2 ENDANGERED SPECIES	0	0	0	0	0	0
5.6.3 OTHER WILDLIFE	115	115	115	115	115	574
5.6.4 WILDLIFE HABITAT	0	0	0	0	0	0
5.6.5 LAND RECLAM & EROSION CONTROL	100	100	100	100	100	500
TOTAL	1352	1305	1305	1605	1305	6871

* COST ITEMS FOR PROGRAMS, OPERATING COSTS, RTA'S, SAMPLING, ETC., ARE EXPRESSED AS THOUSANDS OF FY88 DOLLARS. THESE COSTS DO NOT INCLUDE MANPOWER COSTS.

TABLE 5.7.2 OPERATING BUDGET SCHEDULE (\$M)*

WSRC-RP-89-453
 ENVIRONMENTAL IMPLEMENTATION PLAN
 5.0 LAND USE AND WILDLIFE PROTECTION
 5.7 Resource Requirements

Rev 0, 8/1/89
 Effective 8/1/89
 Page 4 of 4

LANDUSE AND WILDLIFE PROTECTION PROGRAM

5.7 RESOURCE REQUIREMENTS

ISSUE	FY 80	FY80	FY81	FY82	FY83	TOTAL
5.6.1 LAND USE	2844	2897	2897	3187	2897	14830
5.6.2 ENDANGERED SPECIES	3	3	0	0	0	6
5.6.3 OTHER WILDLIFE	318	318	318	318	318	1582
5.6.4 WILDLIFE HABITAT	0	0	0	0	0	0
5.6.5 LAND RECLAM & EROSION CONTROL	130	130	130	130	130	649
TOTAL	3393	3346	3345	3643	3343	17067

* INCLUDES MANPOWER COST (5.7.1) AND OPERATING COST (5.7.2)
 EXPRESSED AS THOUSANDS OF FY80 DOLLARS.

TABLE 5.7.3 TOTAL EXPENDITURE SCHEDULE (\$M)*

5.0 LAND USE AND WILDLIFE PROTECTION PROGRAM

5.8 References

Du Pont, 1986. *Strategic Environmental Plan*, DPW-86-102, E.I. du Pont de Nemours and Company, Wilmington, DE.

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

CONTENTS

6.1 Overview

- 6.1.1 Introduction
- 6.1.2 Summary

6.2 Policy

- 6.2.1 Policy Statement
- 6.2.2 Background for Policy Statement

6.3 Existing Conditions

6.4 Objectives

6.5 Strategy

6.6 Implementation

Resource Management

6.6.1 Groundwater Consumption

- 6.6.1.1 Site Program Overview
- 6.6.1.2 Regulatory Requirements
- 6.6.1.3 Organizational Responsibilities
- 6.6.1.4 Programs
- 6.6.1.5 Monitoring and Compliance

6.6.2 Hydrogeological Regime Analysis

- 6.6.2.1 Site Program Overview
- 6.6.2.2 Regulatory Requirements
- 6.6.2.3 Organizational Responsibilities
- 6.6.2.4 Programs

6.6.2.5 Research/Studies

6.6.3 Groundwater Monitoring

- 6.6.3.1 Site Program Overview
- 6.6.3.2 Regulatory Requirements
- 6.6.3.3 Organizational Responsibilities
- 6.6.3.4 Programs
- 6.6.3.5 Research Studies

6.6.4 Water Conservation

- 6.6.4.1 Site Program Overview
- 6.6.4.2 Regulatory Requirements/Justification
- 6.6.4.3 Organizational Responsibilities
- 6.6.4.4 Programs
- 6.6.4.5 Construction Projects

Waste Management and Disposal Practices

6.6.5 Waste Management and Disposal Practices

- 6.6.5.1 Site Program Overview
- 6.6.5.2 Regulatory Requirements
- 6.6.5.3 Organizational Responsibilities
- 6.6.5.4 Waste Management Objectives and Strategy
- 6.6.5.5 Waste Generation
- 6.6.5.6 RCRA Permitting Activities
- 6.6.5.7 Current Facilities Operations
- 6.6.5.8 Construction Projects
- 6.6.5.9 Research/Studies

6.6.6 Waste Minimization

- 6.6.6.1 Site Program Overview
- 6.6.6.2 Regulatory Requirements/Justification
- 6.6.6.3 Organizational Responsibilities
- 6.6.6.4 Definitions
- 6.6.6.5 Strategy
- 6.6.6.6 Programs/Studies

6.6.7 Waste Site Closure/Remedial Action

- 6.6.7.1 Site Program Overview
- 6.6.7.2 Regulatory Requirements
- 6.6.7.3 Organizational Responsibilities
- 6.6.7.4 Closure/Remedial Action Strategy
- 6.6.7.5 RCRA Part B/RFI Activities
- 6.6.7.6 Programs
- 6.6.7.7 Research/Studies
- 6.6.7.8 Resource Requirements

Facilities Operations

6.6.8 Contamination Prevention

- 6.6.8.1 Site Program Overview
- 6.6.8.2 Regulatory Requirements
- 6.6.8.3 Organizational Responsibilities
- 6.6.8.4 Programs
- 6.6.8.5 Facility Operations
- 6.6.8.6 Construction Projects
- 6.6.8.7 Monitoring/Surveillance

6.6.9 Contamination Detection

- 6.6.9.1 Site Program Overview
- 6.6.9.2 Regulatory Requirements
- 6.6.9.3 Organizational Responsibilities
- 6.6.9.4 Programs
- 6.6.9.5 Monitoring/Surveillance

6.7 Resource Requirements

6.8 References

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.1 Overview

6.1.1 Introduction

The Savannah River Site (SRS) uses large quantities of groundwater as drinking water, process water, and noncontact cooling water. Continued industrial and residential growth along with additional agricultural irrigation in areas adjacent to the SRS will increase the demand for groundwater. This increasing demand will require a comprehensive management system to ensure the needed quality and quantity of groundwater is available for all users. The Groundwater Protection and Waste Management Program establishes the overall framework for the protection of this resource.

6.1.2 Summary

Groundwater under the SRS is monitored extensively for radiological and nonradiological constituents. The groundwater has been impacted at 33 locations on the site, but none of the contaminants have moved offsite. Onsite and offsite drinking water supplies are monitored to ensure they are not impacted. The site has over 1000 monitoring wells from which groundwater samples are analyzed for radiological and nonradiological constituents. Approximately 100 additional monitoring wells per year will be added over the next five years.

The SRS is complying with all regulations and consent orders related to groundwater protection, waste treatment, and waste disposal. Consent order requirements related to M Area groundwater monitoring, F and H Area Seepage Basin point-of-compliance monitoring wells, and quarterly groundwater reports are being met. The existing waste storage facilities are permitted or are being permitted. Existing hazardous and mixed waste storage facilities are being included in the site Resource Conservation and Recovery Act (RCRA) Part B permit. Part B permitting has been started for many of the planned hazardous and mixed waste treatment and disposal facilities.

The Savannah River Laboratory (SRL) has an extensive effort underway to define the regional hydrogeological system. Current programs include

geological sampling, groundwater monitoring, and aquifer modeling efforts to further understand the SRS hydrogeological system. The SRL will also conduct studies on the quantities of water the SRS removes from aquifers relative to the production capability of the formation.

To protect the groundwater from SRS generated wastes, the site has a comprehensive waste management program. The SRS strategy requires that all wastes be treated and disposed onsite whenever practical. Facilities for the treatment and disposal of radioactive, hazardous, mixed (radioactive and hazardous), and nonradioactive, nonhazardous wastes either currently exist, are under construction, or are planned for the near future. The \$905 million Defense Waste Processing Facility will convert the liquid high-level waste into a permanent solid glass waste form for offsite geological disposal. Low-level radioactive waste will be disposed in the new Low-Level Waste Disposal Facility which will feature stabilization and containment of the radionuclides. The \$49 million Consolidated Incineration Facility will be constructed to volume reduce radioactive waste and detoxify hazardous waste. Treatment and disposal facilities for non-incinerable hazardous and mixed waste are planned. New facilities for the retrieval and packaging of stored TRU waste for shipment to offsite geological storage are also planned.

Increased waste minimization activities began during FY88. These activities focused on improved process efficiency to reduce the amount of waste generated. The strategy was to conduct a site inventory of waste streams, identify candidate streams for cost effective reductions, and implement facility specific reduction measures. The site will continue the efforts to reduce the amount and volume of low-level radioactive waste going to the Low-Level Waste Disposal Facility. Efforts to delist the M Area sludge from a hazardous waste to a nonhazardous waste will continue.

Activities toward closing the many SRS waste sites will continue to increase. The SRS waste site closure strategy is to close regulatory required sites first, sites near the plant boundaries second, and finally sites interior to the plant. RCRA closure activities have begun on the M Area settling basin, Mixed Waste Management Facility, and the F and H Area Seepage Basins. In addition to waste closures, remediation activities are underway in M Area to remove chlorocarbons from the groundwater to prevent the existing plume from spreading.

Systems to prevent and detect groundwater impacts from existing and future facilities are in place. Site specifications for underground storage tanks,

diking systems, well installation, and well abandonment have been developed.

Costs for the groundwater protection and waste management program during the five-year planning period are expected to total \$2 billion. Capital expenditures are projected to be \$424 million. Waste site closure costs at \$245 million account for 12 percent of the groundwater protection and waste management costs. Waste management and disposal costs account for 84 percent of the total cost.

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.2 Policy

6.2.1 Policy Statement

The Savannah River Site (SRS) groundwater protection and waste management policy requires that plant operations be conducted in a manner that protects the quantity and quality of the site groundwater, meets regulatory requirements, restores the resource where degradation has occurred when practical, and complies with applicable Department of Energy (DOE) and operating contractor requirements.

6.2.2 Background for Policy Statement

The DOE and operating contractor are committed to protecting the public health and safety and the environment. A statement of these convictions is in DOE Order 5400.1, General Environmental Protection Program, and in the SRS *Strategic Environmental Plan*. Compliance with applicable environmental regulations, DOE orders, and operating contractor policies form the basis for the SRS Groundwater Protection and Waste Management Policy.

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.3 Existing Conditions

The Savannah River Site (SRS) operations have not affected offsite groundwater supplies. The SRS uses large quantities of groundwater as drinking water, process water, and noncontact cooling water. After use the groundwater is released to surface streams or to seepage basins. Although plant operations have impacted groundwater quality at several locations, no offsite drinking water supplies have been affected. The impacts on groundwater quality generally have been the result of the use of seepage basins for the disposal of wastewater and the non-contained disposal of wastes at various sites. Programs are underway to eliminate the use of seepage basins and to close all existing waste sites. SRS operations have not affected the quantity of groundwater available to users adjacent to the site.

The increasing regional demand will require a comprehensive management system to ensure the needed quality and quantity of groundwater is available for all users. The SRS has several programs and studies underway to define and understand the regional hydrogeological cycle. The site will continue current geologic sampling, groundwater monitoring, and aquifer modeling efforts to further understand the SRS hydrogeological system.

The SRS is in compliance with or has entered into compliance agreements related to groundwater protection, waste treatment, and waste disposal regulations. The SRS is meeting the requirements of Consent Orders related to groundwater monitoring and cleanup at various sites. Waste treatment and disposal facilities are in compliance with federal and South Carolina regulations.

The site has a comprehensive waste management and disposal strategy. The strategy requires that all wastes be treated and disposed onsite whenever practical. Facilities for the treatment and disposal of radioactive, hazardous, mixed (radioactive and hazardous), and nonradioactive, nonhazardous wastes either currently exist, are under construction, or are planned for the near future. The \$905 million Defense Waste Processing

planned for the near future. The \$905 million Defense Waste Processing Facility, currently under construction, will convert the 34 million gallons of liquid high-level waste into a permanent solid glass waste form for offsite geological disposal. Low-level radioactive waste, currently disposed by shallow land burial, will be disposed in the new Low-Level Waste Disposal Facility which will feature stabilization and containment of the radionuclides. The site currently has permitted storage facilities for hazardous and mixed wastes. An incinerator to volume reduce radioactive waste and detoxify hazardous waste is planned. Treatment and disposal facilities for hazardous and mixed waste are also planned for non-incinerable wastes.

The 202 waste sites are currently being closed or are scheduled to be closed by the mid-1990s. Resource Conservation and Recovery Act (RCRA) closure activities have begun on the M Area settling basin, Mixed Waste Management Facility and the F and H-Area Seepage Basins. Other waste site closure activities are focused on the characterization of the remaining waste sites and the development of the RCRA Facilities Investigation (RFI) plan required by the site RCRA permit.

Although operations have impacted the groundwater at 33 locations, remediation activities have been deemed necessary at only one site. Groundwater remediation activities are being conducted in the A/M Area to remove chlorocarbons. The chlorocarbons, used as degreasing agents in the M Area fuel fabrication facility, entered the groundwater principally through the M Area settling basin and associated underground piping. The basin is out of service and all other sources have been stopped. The chlorocarbons are confined primarily in a shallow aquifer, but there are some isolated locations where the chlorocarbons have reached the deeper aquifer. The chlorocarbons are being removed from the shallow aquifer by a series of recovery wells that contain the plume onsite by removing water from the formation. The water is pumped to an air stripper column which removes the chlorocarbons from the water. The water is then discharged to a permitted National Pollutant Discharge Elimination System (NPDES) outfall. The chlorocarbons are vented to the atmosphere via a permitted stack. Approximately 200,000 pounds of an estimated 500,000 pounds of chlorocarbons in the formation have been removed. The small amounts of chlorocarbons in the deeper aquifer currently pose no threat to offsite drinking water systems. The SRS continues to monitor the aquifers under A and M Areas to track existing plumes and to detect other sources. Groundwater monitoring at the other impacted locations does not presently indicate a need for remedial action.

Volatile Organic Compounds (VOCs) have also entered the groundwater from operations near the SRL complex. Remediation in this area will begin in 1990 using an air stripper column to cleanup the groundwater.

To protect the groundwater from current and future operations the site has developed special designs and procedures. All new underground storage tanks must be of double wall construction. New and existing underground tanks must have a rigorous inventory reconciliation procedure capable of detecting leaks. Existing above ground tanks are being retrofitted with diking systems to contain leaks. New facilities are constructed with dikes as part of the design. Site specifications for production and monitoring wells were revised to ensure the wells are properly constructed so as not to act as conduits for contaminants. In addition, the site well abandonment program is closing all wells not needed for production or monitoring purposes to remove any additional potential conduits for contamination. Monitoring wells are retrofitted to existing facilities where there is a potential for groundwater impact. New facilities are required to install monitoring wells prior to construction and startup.

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.4 Objectives

The objectives to support the Groundwater Protection and Waste Management Program are shown below. The strategy to achieve these objectives is illustrated in Section 6.5 followed by programmatic details in Sections 6.6 and 6.7.

- Groundwater Consumption**—Protect the quantity and quality of groundwater resources by managing consumption for best resource utilization.

- Hydrogeologic Understanding**—To understand the natural conditions of hydrology and geology that exist in the vicinity of the site.

- Groundwater Monitoring**—To assess groundwater quality in an effort to determine any impacts that have occurred as a result of site operations.

- Groundwater Conservation**—Protect water resources by managing the quantity of water being used in comparison to the resources available.

- Waste Disposal Requirements**—Comply with applicable federal and state regulations, Department of Energy (DOE) orders, and operating contractor policies related to groundwater protection, waste treatment, and waste disposal activities.

- Waste Disposal Strategy**—Provide a waste disposal strategy consistent with applicable laws, DOE orders, and operating contractor policies for each waste stream, including a comprehensive waste minimization strategy.

- Waste Site Closure**—Close all inactive waste sites in accordance with applicable laws and regulations, DOE orders, and operating contractor policies.

•**Groundwater Remedial Actions**—Improve the quality of Savannah River Site (SRS) degraded groundwater to limits agreed to with regulatory agencies.

•**Operational Guidelines**—Operate SRS facilities utilizing site groundwater protection designs and procedures.

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.5 Strategy

The strategy for reaching the Groundwater Protection and Waste Management objectives includes:

- Identifying regulatory and other protection requirements.
- Understanding the hydrogeological system and promoting innovative, cost-effective means of meeting the requirements through research and development.
- Developing physical and administrative controls to protect groundwater utilizing the knowledge gained from the research and development efforts.
- Implementing physical and administrative controls.
- Evaluating the controls to ensure protection requirements are met.

The strategy is illustrated in Figure 6.5-1. Programmatic details are presented in Section 6.6.

FIGURE 6.5-1 GROUNDWATER PROTECTION AND WASTE MANAGEMENT STRATEGY

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.6 Implementation

The implementation section identifies issues and those responsible for actions to achieve defined objectives. Each environmental effort will require funding for one or more of the following: research and development, operations, programs, and construction/modification projects. The resource requirements span a five-year period from FY89 through FY93.

The operating costs used throughout the text are expressed in FY89 dollars and are not escalated. Costs include subcontractor, manpower, and other operations expenses. Capital projects such as construction and large modification projects are expressed in escalated dollars and include manpower costs. Total costs include the costs of research and development, operations, manpower, subcontractors, and capital costs.

Annual manpower costs are calculated using these factors: Savannah River Site (SRS) Monthly Salary (MS) at \$59,500 and Local Roll (LR) at \$40,000.

6.6.1 Groundwater Consumption

6.6.1.1 Site Program Overview

The management of groundwater consumption and understanding the effects of SRS groundwater consumption on the regional hydrogeological regime are essential components of the SRS groundwater protection program. A primary goal of the SRS groundwater protection effort is to ensure that SRS groundwater consumption does not irreparably stress the yield of the underlying regional hydrogeological system.

Environmentally sound management of groundwater consumption practices is being optimized through various SRS efforts. Considerable evaluation of site hydrogeology through past and ongoing projects lead by the Savannah River Laboratory (SRL) is allowing for refined delineation and predictive modeling of the regional hydrogeological regime. The Environmental Protection Section (EPS) is leading the

development of a Water Resource Management Plan for the SRS which will ensure the protection of water quality and quantity; the management of water quantity; and the monitoring of water quality and quantity. Efforts lead by the Power Engineering Section are enhancing the monitoring of groundwater consumption, through the installation of flow meters on all new production wells and the retrofitting of existing production wells.

Over \$482,625 will be required during the five-year planning period which includes six man-years of effort.

6.6.1.2 Regulatory Requirements

The South Carolina Water Use Reporting and Coordination Act authorizes the South Carolina Water Resources Commission (WRC) to require reporting of information relative to substantial use, withdrawal, or diversion of surface, underground, or other waters of the state. Required information includes identifications of the locations of wells or facilities where water is used, withdrawn, or diverted; the source and location of the water; and the total amount of water used, withdrawn, or diverted.

The Safe Drinking Water Act (SDWA) imposes requirements on the installation and maintenance of drinking water wells.

South Carolina regulation R.61-71, Well Standards and Regulations, is applicable to most newly constructed wells, including water supply wells, monitoring wells, and piezometers. To satisfy this regulation, a water well record form (HDI-977) for each well must be submitted to South Carolina Department of Health and Environmental Control (SCDHEC) within thirty days after the completion of the well.

Management of groundwater consumption supports the Groundwater Consumption objective set forth in Section 6.4.

6.6.1.3 Organizational Responsibilities

Discussed below are those groups responsible for groundwater consumption management.

The Groundwater Task Force

The SRS Groundwater Task Force is chaired by the Manager of the Groundwater Group in the Environmental Protection Section (EPS) and is composed of individuals from various custodial and technical departments

that are involved in groundwater-related activities. The task force is responsible for planning and communicating new groundwater protection and management policies.

Environmental Protection Section (EPS)

The Groundwater Group in the EPS is responsible for coordinating all activities relating to the SRS groundwater protection program. The group coordinates the technical and reporting aspects of groundwater consumption, preservation, remediation, and contaminant monitoring activities. The group monitors the status of all ongoing groundwater projects, and maintains comprehensive documentation of project activities. All groundwater projects require approval from the Manager of the EPS Groundwater Group. The Manager of the Groundwater Group interacts with all custodial departments and environmental coordinators, and works with or is a member of all groundwater related task forces.

The EPS is responsible for the technical and regulatory review of all activities affecting groundwater consumption. The EPS also reviews groundwater consumption activities to determine if site policies, objectives, and commitments are being met. The Groundwater Group in the EPS is responsible for coordinating all reporting activities relating to SRS groundwater consumption, e.g., the EPS compiles and reports sitewide water use data. The EPS supports custodial efforts with regulatory expertise.

The total five-year cost is estimated to be \$482,625.

6.6.1.4 Programs

Power Engineering Section

Installation of metering devices for all production wells (i.e., greater than 10 gpm) is necessary to comply with the reporting requirements of the South Carolina Water Use and Coordination Act and to provide precise baseline information for the SRS Water Conservation Program. Flow meters are being provided for all new production water wells.

6.6.1.5 Monitoring and Compliance

The South Carolina Water Use and Coordination Act requires the SRS to report substantial use, withdrawal or diversion of surface, underground and other waters of the state to the South Carolina Water Resources Commission. Specifically, this Act requires all users of 100,000 gallons or more of water a day to report water usage for each quarter and the maximum amount of water withdrawn in a single day for each month of the quarter. The EPS presently completes the sitewide quarterly Water Use Reports from data collected from SRS custodians.

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.6.2 Hydrogeological Regime Analysis

6.6.2.1 Site Program Overview

Description of the hydrogeological regime at the Savannah River Site (SRS) is an integral planning component of the groundwater protection program. Analysis of both the natural systems and the effects of large-volume pumping centers are the two primary tasks of this effort. The Environmental Sciences Section (ESS) of the Savannah River Laboratory is the lead organization responsible for this effort. Much of the funding comes from the Waste Management Department, especially for numerical modeling of the effects of large-volume pumping in the Separations Areas.

Numerous wells have been installed onsite. Many of the deeper wells have been both cored and geophysically logged, which provides information on the vertical distribution of bulk physical parameters affecting groundwater flow. Aquifer tests provide field estimates of groundwater flow rates and directions, as well as the degree of confinement of an aquifer beneath a small part of the site. Special core sections have been acquired that are suitable for measurement of both porosity and permeability.

Analysis of the field data includes correlation of logs into stratigraphic cross-sections, comparison of well logs with seismic cross-sections, potentiometric surface maps, calculation of groundwater flow rates and directions, calculation of vertical and lateral gradients, assessment of leakance coefficients of regional aquitards, and many other efforts.

Numerical modeling of the aquifer system beneath the SRS assesses both short- and long-term consequences of water withdrawals. The impact of regional droughts has been considered, but the primary modeling emphasis is on particle tracking to assess pathways of contaminant migration and assessing the impact of large-volume pumping centers on groundwater flow rates and directions.

Head reversal studies assess both the lateral extent of and changes in the area beneath the SRS in which there is an upward flow gradient between the uppermost Cretaceous aquifer and the overlying uppermost aquifer.

Additional data have added many control points for contouring the lateral extent of head reversal. The local influence of pumping centers in the Separations Areas has been the subject of several numerical modeling studies.

Over \$9.7 million will be required over the five-year planning period which includes 40 man-years of effort.

6.6.2.2 Regulatory Requirements

Federal Laws

•**Resource Conservation and Recovery Act (RCRA)**—These regulations include requirements for groundwater monitoring (40 CFR 264 and 265). Many of these requirements imply a thorough description of the hydrogeological regime; particularly, the definition of the uppermost aquifer and the determination of groundwater flow rates and directions.

State Regulations

•**R.61-61-Solid Waste Regulation**—Postclosure monitoring requirements include the use of a monitoring well, which implies an assessment of the location of the water table and the downgradient direction.

•**R.61-66-Industrial Solid Waste Disposal Site Regulation**—If hazardous waste is present, groundwater monitoring requirements imply an assessment of the location of the water table and the downgradient direction.

•**R.61-70-South Carolina Landfill Regulation**—The requirement for monitoring wells implies an assessment of the location of the water table and the downgradient direction.

•**R.61-79.264 and 265 Hazardous Waste Management Regulations**—This is South Carolina's promulgation of RCRA regulations, enforced under authority of the Environmental Protection Agency (EPA). Groundwater monitoring requirements require extensive knowledge of the hydrogeological regime.

Consent Orders

ACO 85-70-SW—The Department of Energy (DOE) agreed to additional groundwater assessment activities at the M Area Settling Basin and

vicinity and the F and H Area Seepage Basins, under the terms of an Administrative Consent Order signed 11/7/85 and amended 1988. These assessment activities require a detailed understanding of the hydrogeological regime at each site.

SA 86-52-W—A Settlement Agreement signed 6/20/86 also requires groundwater quality assessments at several sites along with a biennial update of the Technical Summary of the Groundwater Quality Protection Program.

DOE Orders

•5400.1-General Environmental Protection Program—This DOE order requires the development of groundwater protection management and groundwater monitoring programs for the site.

•5480.2-Hazardous and Radioactive Mixed Waste Management—This DOE order requires groundwater monitoring at all solid, hazardous and mixed waste management facilities to ensure that groundwater quality is not degraded. The assessment of groundwater degradation requires knowledge of the hydrogeological regime.

•5820.2A-Radioactive Waste Management—This DOE order requires that the waste management plan for each facility describe groundwater monitoring programs for both radioactive and nonradioactive constituents.

The Hydrogeological Regime Analysis supports the Hydrogeologic Understanding objective set forth in Section 6.4.

6.6.2.3 Organizational Responsibilities

Groups responsible for hydrogeological regime analysis are described below.

Savannah River Laboratory - Environmental Sciences Section, (SRL-ESS)

ESS research staff take the leading role in interpreting the results from projects requiring hydrogeological regime analysis. ESS staff ordinarily determine the best method of analysis. Subcontractors perform most of the following tasks: numerical modeling, soil boring, offsite well drilling, water level measurements, and core characterizations, including porosity/permeability measurements.

Environmental Monitoring Section (EMS)

EMS hydrologists and geologists administer subcontracts for geophysical logging, monitor well drilling, pump and aquifer tests, and coring projects. Technical staff help characterize site aquifers and assist in interpretation of groundwater flow directions.

Environmental Protection Section (EPS)

In its oversight role, the EPS may suggest projects to the SRL or custodians, fund special studies, prepare policy and guidance statements, such as a water resource management plan, or request acquisition of particular data.

Custodians

Custodians of facilities that have affected or are likely to affect groundwater are responsible for assessment of the groundwater impact. This includes a significant effort to describe the site hydrogeology. These projects are performed by the ESS, EPS, consultants, EMS, and occasionally by custodial staff.

Raw Materials Engineering and Technology plans and oversees the program to address the volatile organic chlorocarbon plume in groundwater beneath the M Area Settling Basin and vicinity. This program's characterization and assessment phases yielded significant data regarding the hydrogeology of the A/M Area. Costs associated with this program are presented in Section 6.6.7.

Waste Management Technology plans and oversees the program to address the nitrate/tritium plume in groundwater beneath the F and H Area Seepage Basins, as well as monitoring possible groundwater impacts from the Burial Grounds and other waste management facilities. Characterization and assessment phases of these projects yield significant data regarding the hydrogeology of the Separations Area. Costs associated with this program are presented in Section 6.6.7. Groups responsible for projects that incidentally provide hydrogeological data are described below:

Power Engineering's analyses geophysical logs, cuttings, and cores acquired during the installation of deep, high-volume production wells to contribute to the understanding of the site's lithostratigraphy and aquifer properties.

Construction Management's soil borings performed during foundation studies, road building, trenching, and other construction activities often provide useful hydrogeological information, such as the depth to water table. Piezometers and dewatering wells are often installed as part of the construction of large buildings.

6.6.2.4 Programs

EPS—The Groundwater Group's responsibilities include coordination of all groundwater-related activities at the SRS. The EPS encourages the fundamental understanding of the hydrogeologic regime in the region of the Atlantic Coastal Plain that includes the SRS. The EPS at times recommends particular studies and may supply portions of necessary funding for particular projects.

The total five-year cost for EPS is estimated to be \$648,750.

SRL-ESS—All hydrogeologic regime analysis performed for research purposes is directed by ESS staff. These projects include the Baseline Hydrogeological Investigation, regional aquifer studies, head reversal studies, and others. In addition, the hydrogeologic regime analysis portions of custodian projects are often directed by ESS staff. Examples include particle tracking studies and groundwater flow modeling in the Separations Areas and groundwater flow patterns near coal piles.

Custodial Departments—Some custodial staff can perform hydrogeological regime analysis. In these cases the projects ordinarily involve groundwater monitoring of a waste site or operating facility. Examples include the Raw Materials Engineering and Technology group responsible for groundwater activities at the M Area Settling Basin and vicinity and the Waste Management Technology (WMT) group responsible for groundwater activities at WMT waste disposal sites, particularly those in the Separations Areas.

6.6.2.5 Research/Studies

SRL - Environmental Sciences Section (ESS)

•Understanding the SRS Hydrologic Cycle

Groundwater Resources Management Plan—The objective of this study is to develop a sitewide groundwater resources management plan. A major

program element is consultation on general geology and hydrology issues at SRS. The total five-year cost is estimated to be \$239,250.

Seismology of SRS—This study maintains and upgrades four vertical and two horizontal sensing seismometers of the SRS Seismological Network. The total five-year cost is estimated to be \$948,750.

Stratigraphic Definition of the SRS—This study will document the geology, hydrology, and geohydrology of the SRS. This is a geological study of the entire sedimentary column, with a goal of defining aquifers underlying SRS, the interconnections, and the hydraulic properties. A dedicated computer with specialized geological software will be purchased in FY90 to manage and display the geologic data. The total five-year cost is estimated to be \$1.5 million.

Detailed Characterization of SRS Aquifer Systems—This program will include pumping tests, detailed analysis of groundwater and sediments, and age dating of groundwater to develop a hydrologic data base for SRS aquifer systems. The total five-year cost is estimated to be \$978,500.

Calcareous Zone Project—This study will define the extent, continuity and lithology of calcareous units underlying the SRS that might contain of units with high permeability. Interpretive techniques will be used to integrate the information collected using various subdisciplines (e.g., geophysics, hydrology, paleontology, stratigraphy). The calcareous zones will ultimately be described in terms of detailed depositional models. The total five-year cost is estimated to be \$515,200.

SRS Baseline Hydrogeological Investigation—This is a three-phase study involving drilling and installation of clustered monitoring wells at 18 sites. The study encompasses core drilling, geophysical logging, stratigraphic interpretation, and detailed lithologic interpretation of the entire coastal plain sedimentary sequence. Laboratory testing of physical properties of the sediments is also included. The total five-year cost is estimated to be \$498,750.

•Development of a Regional Hydrological Model

Sitewide Groundwater Model—This study will develop a mathematical model of groundwater flow to be used as a groundwater management tool over a 3,000 square mile area with SRS at the center. The study will include information from onsite wells and offsite wells. The interrelationships and cumulative effects of well pumping will be evaluated. The total five-year cost is estimated to be \$748,750.

Site Geological Model—This study will develop a regional geological model in support of the regional groundwater flow model. The study will use cores collected during the SRS Baseline Hydrogeological Investigation and perform core descriptions, stratigraphic research, paleontology, and analysis of depositional environments. Aquifers will be delineated in both the regional and site specific geological framework by using cores from the well installation program of the South Carolina Water Resources Commission. The total five-year cost is estimated to be \$619,000.

Offsite Geological Investigations:

•South Carolina—SRS is coordinating a project with the South Carolina Water Resources Commission (SCWRC) to establish a permanent network of clustered wells offsite. The data from these wells (geology, water levels, etc.) will be included in SRS modeling studies.

•Georgia—At this time there are no piezometers across the Savannah River in Georgia with a design that is comparable to the South Carolina's well clusters. It is expected that a cooperative program with a state or federal agency (e.g., Georgia State University) will be developed.

The total five-year cost is \$1.6 million.

Geophysical Studies—This study will develop an understanding of the three-dimensional geologic structure beneath the plant site. Techniques used will be geomagnetic surveys, seismic surveys, gravity surveys and testing of electrical methods. The total five-year cost is estimated to be \$1.4 million.

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.6.3 Groundwater Monitoring

6.6.3.1 Site Program Overview

Protection of the aquifers underlying the Savannah River Site (SRS) is a major component of the groundwater protection and waste management program. The Environmental Protection Section (EPS), the Environmental Monitoring Section (EMS), and the Power Engineering Section are the lead organizations responsible for aquifer protection through a comprehensive monitoring effort. Many groundwater monitoring wells have been installed onsite. The data is being examined to monitor existing plumes and to identify any additional impacted locations.

Over \$18 million will be required over the five-year planning period which includes 41 man-years of effort.

6.6.3.2 Regulatory Requirements

Federal Laws

- **Resource Conservation and Recovery Act (RCRA)**—RCRA regulations include explicit specifications for groundwater monitoring requirements (40 CFR 264 and 265).

- **Public Law 98-181**—This law passed in 1983, specified discontinuance of the settling basin in M Area by November 1985 and required that the Department of Energy Savannah River (DOE-SR) develop a plan for groundwater protection and submit it to the U.S. Congress. Included in the law was the authorization to design and construct the 300-M Area effluent treatment facility (ETF). The SRS met the requirements of Public Law 98-181 by closing the M Area Settling Basin in July 1985 and by submitting to Congress a groundwater protection plan in May 1984). The provisions in the plan represent ongoing commitments.

State Regulations

•**R.61-61-Solid Waste Regulation**—This regulation specifies procedures to be followed for closing or abandoning solid waste disposal sites. Stipulated requirements include postclosure monitoring by at least one monitoring well with readings taken every three months for submittal to the Solid Waste Division, State Board of Health.

•**R.61-66-Industrial Solid Waste Disposal Site Regulation**—This regulation requires a permit for operating any industrial solid waste system. If the industrial waste system involves hazardous waste, then a groundwater monitoring system must be developed into the site plan.

•**R.61-70-South Carolina Landfill Regulation**—The South Carolina Landfill regulation requires an owner or operator of a solid waste disposal facility to obtain a permit to operate a sanitary waste landfill. In addition, observation test wells that provide reliable data on groundwater contamination must be included in the site design.

•**R.61-71-Well Standards and Regulations**—The South Carolina Well Standards and Regulations apply to any newly constructed well, including water supply and monitoring wells. These regulations establish certain minimum standards for well construction and well locations. They require that a water well record form (HDI 9-77) be submitted to the South Carolina Department of Health and Environmental Control (SCDHEC) within thirty days after the completion of any well or the abandonment of a well.

•**R.61-79.264-Hazardous Waste Management Facilities Regulation**—The hazardous waste management regulation establishes minimum standards on the management of hazardous waste for owners or operators of permitted hazardous waste treatment, storage, and disposal facilities. The groundwater protection standards required by this regulation will be met once the SRS obtains its complete permit.

Consent Orders

The DOE agreed to additional groundwater monitoring for basins in M, F, and H Areas under a Consent Order (CO #85-70-SW) signed November 7, 1985. Settlement Agreement (SA #86-52-W) signed on June 20, 1986, requires periodic groundwater quality assessments at several sites and a biennial update of the Technical Summary of the Groundwater Quality Protection Program.

DOE Orders

•**5400.1-General Environmental Protection Programs**—This DOE order requires the development of groundwater monitoring programs at the site.

•**5480.2-Hazardous and Radioactive Mixed Waste Management**—DOE Order 5480.2 establishes hazardous waste management procedures for DOE facilities that generate, transport, treat, store, and/or dispose of hazardous waste. This order requires groundwater monitoring to be conducted at all solid, hazardous, and mixed waste management facilities to ensure that groundwater quality is not degraded.

•**5820.2A-Radioactive Waste Management**—DOE Order 5820.2A establishes policies and guidelines by which the DOE manages its radioactive waste, waste by-products, and radioactively-contaminated surplus facilities. Under this order, the waste management plan required for each radioactive waste-management facility must include a section on the radioactive and nonradioactive monitoring programs, including groundwater monitoring, of these sites.

The Groundwater Monitoring Program supports the Hydrogeological Regime objective set forth in Section 6.4.

6.6.3.3 Organizational Responsibilities

Discussed below are those groups with responsibility for the groundwater monitoring activities.

Groundwater Task Force

The Groundwater Task Force is chaired by the Manager of the Groundwater Group in Environmental Protection Section (EPS), and is composed of individuals from various custodial or technical departments that are involved in groundwater-related activities. The task force is responsible for planning and communicating new groundwater protection and management policies.

Environmental Protection Section (EPS)

The Groundwater Group in the EPS is responsible for coordinating all activities relating to the SRS groundwater protection program. The group coordinates the technical and reporting aspects of groundwater

consumption, preservation, remediation, and contaminant monitoring activities. The group monitors the status of all ongoing groundwater projects, and maintains comprehensive documentation of project activities. All groundwater projects require approval from the Manager of the EPS Groundwater Group. The Manager of the Groundwater Group interacts with all custodial departments and environmental coordinators, and works with or is a member of all groundwater related task forces.

The EPS is responsible for the technical and regulatory review of all activities affecting groundwater consumption. The EPS also reviews groundwater consumption activities to determine if site policies, objectives, and commitments are being met. The Groundwater Group in the EPS is responsible for coordinating all reporting activities relating to SRS groundwater consumption, e.g., the EPS compiles and reports sitewide water use data.

Custodial Departments

Groundwater projects are carried out by the department with custodial responsibility for the geographical area where the project will occur. The departments designate coordinators for their environmental issues or projects. Well drilling, soil boring and monitoring activities are centralized in the Environmental Monitoring Section (EMS). The custodians are responsible for budgeting and planning groundwater projects, managing the projects, conducting data evaluation and preparing reports. The EMS administers most of the well drilling contracts.

Environmental Monitoring Section (EMS)

The EMS is responsible for soliciting, selecting, and administering subcontracts for groundwater well drilling, sampling, and analysis. The EMS assures that quality assurance and quality control requirements for sampling and analytical programs are met. Analytical results are transmitted directly to the appropriate custodian or through the EPS. The EMS maintains a computerized data base containing well construction records, well logs, cores, and analytical data.

Power Engineering Section

The Power Engineering Section is responsible for the operation of most onsite production water wells, and for coordinating well construction, maintenance and abandonment activities.

6.6.3.4 Programs

Oversight

•**Environmental Protection Section (EPS)**—Custodial departments proposing hydrogeological related efforts must complete and submit to the EPS a general program plan for hydrogeologic work at the SRS. Prior to commencing the project the EPS must approve the plan. The EPS is responsible for coordinating all activities relating to the quantity and quality of groundwater, including program completeness, consistency, uniformity, and progress, and for reviewing data and reports prior to transmittal to the regulatory agencies. The total five-year cost is estimated to be \$1 million.

In an effort to establish a single set of procedural methods of acceptable hydrogeological investigation data collection and selected environmental testing protocols, DPSOP 254 - *Hydrogeologic Data Collection Methods*, (Du Pont 1987), was developed. The manual is organized so that updates require minimal effort. New sections may be added as additional activities requiring standardized procedures are identified. Annual updates and revisions are expected to require \$324,375 over the five-year planning period.

Groundwater Monitoring Program

The SRS has established an extensive and comprehensive Groundwater Monitoring Program (GMP). The purpose of the GMP is to determine if any SRS facilities have influenced groundwater quality, and if they have, to quantify the influence. Facilities monitored include waste disposal sites, spill sites, chemical storage areas, process sewers, and certain process buildings. The EMS conducts all compliance groundwater monitoring at the SRS except the monitoring done to define the chlorocarbon contamination in the M Area vicinity. The GMP is composed of four subprograms:

- Well Drilling, Maintenance, and Abandonment
- Water Sampling
- Sample Analyses
- Data Management and Reporting.

•**Environmental Monitoring Section (EMS)**—Projects that support the GMP are described below. For planning purposes, it is estimated that the EMS will require \$1.8 million to support SRS groundwater activities.

Well Drilling, Maintenance and Abandonment—Monitoring wells are drilled and installed in accordance with the procedures and specifications described in DPSOP 254 - *Hydrogeologic Data Collection*. (Du Pont 1987) A detailed protocol is mandated to assure continuity of construction. Such specifications conform to recently published SCDHEC guidelines. A monitoring well installation report is completed and submitted with the general program plan for review and approval of the EPS. Upon completion of the well installation process a final report is submitted to the EPS. The maintenance of the monitoring wells is done on a quarterly inspection of all monitoring wells by the sample collection contractor. An effort is in progress to identify and locate all monitoring wells within SRS that serve no present use and can therefore be abandoned. DPSOP 254 provides the procedures and specifications followed in abandoning groundwater monitoring wells. The intent of these procedures and specifications is to return each aquifer and overlying sediments to as near the original state as possible. An abandonment program plan is prepared for each well or group of wells to be abandoned. All proposed abandonment program plans are reviewed and approved by the EPS.

Monitoring Well Surveying—This task involves subcontracts awarded to surveying firms so that new wells and soil cores are accurately placed and existing wells and soil cores may be accurately located, even after a long period of abandonment. Typically, surveying teams gather the well number, SRS Grid Coordinates, casing elevation, and ground elevation information. The total five-year cost is estimated to be \$350,000.

Monitoring Well Drilling and Soil Coring—This task includes all monitoring well and soil core drilling, installation, and abandonment activities conducted by the EMS. Actual well drilling and soil coring is subcontracted. Waste site custodians are responsible for transferring funds to the EMS to pay for well installations. The total five-year cost is estimated to be \$4.5 million.

Individual Oversight of the EMS GMP—This task provides for the oversight of the EMS GMP. A single individual from a contractor is responsible for assisting the EMS in site selection and program review and assessment. This individual supplements the EMS by providing additional oversight of the EMS and subcontractor activities. The total five-year cost is estimated to be \$375,000.

Technical Oversight of the GMP—Qualified support is provided to oversee contractors working in the EMS GMP. An independent contractor provides an individual to oversee another contractor's activities. Additional support is

provided as needed. This task supplements the EMS by providing additional oversight of subcontractors. Activities that receive oversight from this project are well drilling and installation, soil coring, and well maintenance. The total five-year cost is estimated to be \$1 million.

Monitoring Well Maintenance—Well maintenance is the repair or replacement of malfunctioning electrical and mechanical equipment, in addition to routine maintenance. The objective of this task is to maintain the monitoring wells to minimize well contamination and failure and to comply with all state and federal regulatory requirements. Well maintenance activities are conducted by a subcontractor. The total five-year cost is estimated to be \$350,000.

•**Environmental Protection Section (EPS)**

Independent Oversight—In order to ensure that state and federal standards are met, the EPS provides for an independent contractor to oversee the drilling, installation and abandonment of all monitoring and production wells. It is the contractor's responsibility to: (1) conduct formal written audits of the drilling subcontractor and technical oversight performance on individual well installation/abandonments; (2) ensure that SRS well installation/abandonment specifications are being followed by the drilling subcontractor; (3) monitor the overall performance of the drilling subcontractor; and (4) monitor the quality of installation/abandonment. The total five-year cost is estimated to be \$1.7 million.

Water Sampling

The proper collection of groundwater samples is of prime importance in conducting a complete and defensible hydrogeologic investigation. The protocol to be used in assuring representative groundwater samples is: (1) obtaining a sample that is representative of subsurface conditions; (2) minimizing the potential for contamination of samples from sampling equipment, jars, etc.; (3) proper logging, field testing, filtering, and preservation of samples; and (4) proper documentation including chain of custody records. Prior to initiating a new groundwater sampling program, a Sampling Program Description Form (DPSOP 254-XI-1) must be completed and submitted along with the General Program Plan to the EPS for review and approval. The sampling program must be developed using the specific field procedures described in DPSOP 254.

•Environmental Monitoring Section (EMS)

Well Sampling—The well sampling task ensures that well water samples are collected on schedule and are not subjected to outside contamination. Therefore, quality control is a very important part of the well sampling task. The total five-year cost is estimated to be \$875,000.

Sample Analyses

The analytical laboratories contracted to perform sample analyses adhere to the analytical methods and detection limits prescribed by the Environmental Protection Agency (EPA). The chemical constituents identified and measured include volatile organics, acid extractable and base neutral organics, pesticides and polychlorinated biphenyls (PCBs), inorganics, and radiological constituents. The accuracy and precision of the data generated by the contractor is determined through analysis of replicates, spiked samples, synthetic reference samples, field or laboratory blanks along with each set of samples.

•Environmental Monitoring Section (EMS)

Well Sample Analysis (Laboratory No. 1)—This task purpose is to perform analyses on samples collected in the groundwater monitoring program. These samples are primarily well water samples, but may include soil samples obtained through soil coring operations. The primary analytical laboratory is responsible for performing most of the analyses and can handle the needs of the entire SRS groundwater monitoring program. This includes ensuring the quality of analytical results by rigorous quality assurance procedures. The total five-year cost is estimated to be \$4.1 million.

Well Sample Analysis (Laboratory No. 2)—This task purpose is to provide a backup laboratory for any problems with the primary lab. Although the primary analytical laboratory has the responsibility of performing most of the analyses, circumstances may arise due to equipment malfunction or sample load where one laboratory may not be able to handle the entire suite of analyses. Therefore, a secondary laboratory will be named that has the capacity to handle the sample analysis and data management needs of the entire groundwater monitoring program. This would include ensuring the quality of analytical results by rigorous quality assurance procedures. The total five-year cost is estimated to be \$200,000.

Well Sample Analysis (Laboratory No. 3)—This task purpose is for a third laboratory to perform QA/QC work in order to check the results provided by the primary and secondary laboratories. The tertiary analytical laboratory is responsible for performing check analyses such as split sample analyses. The results yielded by the check analyses are compared to the results obtained in the initial analyses by way of a simple statistical procedure. This comparison is the fundamental unit of the quality assurance procedure. The tertiary laboratory does not have to perform all sample analyses and data management work for the entire SRS groundwater monitoring program. The total five-year cost is estimated to be \$100,000.

In addition to the above contracts performing water analyses on a routine basis, it is expected that at least 80 wells (considering current regulations) will require Appendix 9 analyses, which cost \$3,000 per analysis. The total five-year cost is estimated to be \$1.2 million.

Data Management and Reporting

The GMP provides a Data Management Unit which (1) receives, collates and reviews data from various sources (laboratory, field personnel, drilling documentation, etc.) and (2) organizes this data into a report ready database. Data can be extracted from the database by personal computers that are connected to the SRS Local Area Network. Monthly printouts highlighting flagged analyses are forwarded to the custodians and the EPS. The flagged values have no regulatory significance; they are intended to assist with data interpretation and scheduling. This printout provides the custodians and the EPS preliminary data allowing them to assist in the review process at the earliest possible point. Analyses from each calendar quarter are compiled in quarterly reports which are issued to the custodians and the EPS. The custodians have the responsibility for data interpretation. The data management element of the GMP is described in detail in DP-MS-87-109, *The Organization and Operation of the Savannah River Site's Groundwater Monitoring Program*.

•Environmental Protection Section (EPS)

Well Construction Data (WCD)—Well construction data for approximately 1000 site wells are being centralized in an Oracle relational database. The data provides information on well construction details such as location,

coring, drilling, geophysical logging, maintenance and abandonment. It provides the use with menu driven searches by:

1. Well ID
2. Well coordinate
3. Distance (radius) from SRS coordinates

The well construction data system is part of an ongoing effort to centralize data associated with the site groundwater activities.

The cost for maintaining the data index is approximately \$75,000 for the five-year planning period.

•**Environmental Monitoring Section (EMS)**

Groundwater Monitoring Data Management and Report Preparation—This task responsibility is to manage sample analyses data received from the analytical laboratory, sample scheduling, and report preparation. Data management is composed of (1) receiving laboratory results on a floppy disk; (2) entering the information into the computer; (3) comparing the analytical results with flagging criteria; and (4) formatting the data for report preparation. Report production includes monthly, quarterly, and annual nonradioactive groundwater monitoring reports. The total five-year cost is estimated to be \$350,000.

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.6.4 Water Conservation

6.6.4.1 Site Program Overview

Protecting the water resources (groundwater and surface water) by managing the quantity of water being used versus the amounts available represents an important part of the Savannah River Site (SRS) Groundwater Protection and Waste Management Program. Additionally, responsible use of SRS water resources provides secondary benefits resulting in lower energy and waste treatment costs and ensures adequate water supplies for future SRS and neighboring activities.

Regional groundwater assessment programs have documented the availability of adequate water supplies (DOE, 1987a). SRS operations for over 35 years in conjunction with other industrial, agricultural and municipal users in the region have not adversely affected groundwater availability. The abundance of groundwater results in little direct economic benefits with regard to water conservation and therefore few formal water conservation programs have been implemented. However, water conservation has indirectly resulted from other environmentally regulatory or economically driven programs.

Over \$1 million will be required over the five-year planning period which includes 14 man-years of effort.

6.6.4.2 Regulatory Requirements/Justification

State Laws

•**South Carolina Water Use and Coordination Act**—This regulation requires SRS to report substantial use, withdrawal or diversion of surface underground and other waters of the State of South Carolina to the State of South Carolina Water Resources Commission.

In addition, the state of South Carolina has drought response regulations that can require consumption reductions at times.

The Water Conservation Program supports the Groundwater Conservation Regime objective set forth in Section 6.4.

6.6.4.3 Organizational Responsibilities

Discussed below are those groups with responsibility for the Water Conservation Program.

Groundwater Task Force

The SRS Groundwater Task Force is chaired by the Manager of the Groundwater Group in the Environmental Protection Section (EPS), and is composed of individuals from various technical departments that are involved in groundwater related activities. The task force is responsible for reviewing and approving new water conservation programs.

Environmental Protection Section (EPS)

The EPS is responsible for the technical and regulatory review of all activities affecting groundwater. The EPS provides the lead support for initiation of water conservation programs. The EPS will conduct periodic surveys of water use activities and provide recommendations for specific conservation programs. Additionally, the EPS will address water conservation in conjunction with related environmental audits and assessments in which they participate.

Custodial Departments

Reactors, Raw Materials and Tritium Operations, Separations, Waste Management and Naval Fuel have personnel responsible for reviewing all water use activities to ensure responsible use of water resources. The personnel are also responsible for submitting appropriate water conservation information as required to the EPS and Groundwater Task Force for review and/or approval.

6.6.4.4 Programs

Custodial Departments

The Custodial Departments will submit an Annual Water Conservation Assessment Report to the EPS beginning in Fiscal Year (FY) 1990. The Annual Water Conservation Assessment Report will address the following subjects:

-
-
- Present fiscal year water use
 - Previous two fiscal years water use
 - Percentage increase or decrease
 - Reason for increase or decrease
 - Proposed water conservation projects for next three fiscal years; including:
 - Project description
 - Water savings as a percentage of total use
 - Affect on groundwater head reversal if any
 - Project cost.

As discussed in Section 6.6.6, the SRS has implemented a broad based waste management program which includes significant waste minimization activities. Although specifically designed to minimize waste stream quantity, many of these programs significantly reduce the quantity of process water use. A recent example of this secondary benefit type of water conservation program is the M Area wastewater reduction in metal fabrication operations program. Through careful analysis of existing processes, waste water from 87 process effluents was reduced from 528 gallons per minute (gpm) to 20 gpm (Martin et al., 1987), representing a dramatic reduction in process water consumption. As similar analyses are performed, the water conservation benefits should be evaluated and emphasized as additional justification for such programs.

The total five-year cost is estimated to be \$398,000.

Environmental Protection Section (EPS)

The EPS provides the technical and regulatory review of all activities affecting groundwater and the lead support for initiation of water conservation programs. Periodic surveys of water use activities, recommendations for specific conservation programs, and water conservation in conjunction with related environmental audits and assessments are ongoing activities.

The total five-year cost is estimated to be \$473,125.

Separations

A groundwater usage study will be completed for the F and H Areas by the subcontractor Camp, Dresser, and McKee (CDM). Methods and potential areas of water usage reductions will be identified through the study. There will be two phases of the project. They are as follows:

- Developing a detailed scope from the general objectives and determining additional instrumentation requirements to achieve desired goals.
- Conducting data collection and analyzing results after instrumentation installation by Works Engineering groups.

A report will be issued containing the data and resulting recommendations. The total FY89 cost of the study will be approximately \$80,000.

6.6.4.5 Construction Projects

Power Engineering Section

Installation of metering devices for all production wells (i.e., greater than ten gpm) is necessary to comply with the reporting requirements of the South Carolina Water Use and Coordination Act and to provide precise baseline information for the SRS Water Conservation Program. Flow meters are being provided for all new production water wells. Existing production wells will be retrofitted.

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.6.5 Waste Management and Disposal Practices

6.6.5.1 Site Program Overview

The Savannah River Site (SRS) waste management plan provides a strategy to comply with applicable federal and state regulations, Department of Energy (DOE) orders, and operating contractor policies related to groundwater protection, waste treatment, storage, and waste activities. The plan covers disposal of all nonhazardous, hazardous (as defined by the Resource Conservation and Recovery Acts (RCRA), radioactive and RCRA hazardous radioactive (mixed) wastes.

The SRS waste management plan has been updated. Some of the needed facilities for treating, storing or disposing of the wastes are currently operating; others are in active design or construction; still others are in the conceptual planning stage.

Over the next five years, the cost of waste treatment, storage and disposal will increase significantly. Waste disposal activities will cost \$1.7 billion during the five-year planning period from FY89 through FY93. Approximately \$422 million is forecasted for the construction of additional facilities. Total five-year manpower requirements are estimated at 1412 man-years.

6.6.5.2 Regulatory Requirements

SRS waste management practices are regulated by The DOE, Environmental Protection Agency (EPA), and the South Carolina Department of Health and Environmental Control (SCDHEC). The applicable regulations are described below:

Resource Conservation and Recovery Act (RCRA)

The Resource Conservation and Recovery Act of 1976, also known as the Solid Waste Disposal Act, as amended, provides a comprehensive federal EPA regulatory program for hazardous waste management and a state regulatory program for nonhazardous wastes. The SCDHEC has been

granted authority by the EPA to conduct the RCRA hazardous waste program in South Carolina. The basic framework for the management of hazardous waste, from its generation to its final disposal, is presented in 40 CFR 260-265.

All hazardous waste treatment, storage and disposal facilities at the SRS are either (1) fully permitted, (2) have interim status, or (3) have entered into settlement agreements or consent orders with the SCDHEC. The SRS is in compliance with or has entered into compliance agreements related to groundwater protection, waste treatment, and waste disposal regulations. There have been several RCRA settlement agreements and consent orders signed from 1985 to March 1988.

<u>Date</u>	<u>Agreement/Order</u>	<u>Description</u>
07/1985	Consent Order	Spills
11/07/85	Consent Order	Groundwater Monitoring (Hazardous Waste Sites)
10/06/86	Settlement Agreement	M Area Drums
05/02/87	Settlement Agreement	Part B Deficiencies
11/12/87	Settlement Agreement	EPA Multimedia Inspections Resulting in RCRA Violations
11/12/87	Settlement Agreement	Mixed Waste Management Facility (MWMF) Part B Deficiencies
12/29/87	Settlement Agreement	L Tank Hazardous Waste Storage (National Resources
05/26/88	Consent Decree	National Resources Defense Council (NRDC) Lawsuit
11/23/88	Settlement Agreement	Transuranic (TRU) Pads
02/16/89	Settlement Agreement	Interim Status Closure Plan Navel Fuel Drums

Toxic Substances Control Act (TSCA)

The objective of the TSCA is to ensure that the manufacture and sale of chemical substances and mixtures do not present an unreasonable risk of injury to health or the environment. The principle applicability of the TSCA to SRS operations is in the management and disposal of polychlorinated biphenyls (PCBs). The EPA implementing regulation for the handling, storing and disposal of PCBs and PCB-containing material is found in 40 CFR Part 761.

National Emission Standards for Hazardous Air Pollutants (NESHAP)

The NESHAP establishes the guidelines for the atmospheric release of radioactive and certain hazardous pollutants. The primary pollutants of concern for SRS operations are radionuclides, asbestos and benzene. The SRS complies with all NESHAP guidelines.

Federal Solid Waste Management Guidelines and Regulations, 40 CFR 240-257

The regulations presented in 40 CFR 240-257 describe the guidelines for the management of nonhazardous solid wastes. Specifically, 40 CFR 241, Guidelines for the Land Disposal of Solid Waste, and 40 CFR 257, Criteria for Classification of Solid Waste Disposal Facilities and Practices, are applicable to SRS operations.

SCDHEC R.61-79.124 through R.61-79.270

A major goal of the RCRA is to authorize state agencies operate hazardous waste programs based on minimum standards set by the EPA. The requirements of the hazardous waste management program administered by the state are described in the South Carolina Hazardous Waste Management Regulations (R.61-79.124 through R.61-79.270). Hazardous waste management in the Hazardous Waste Storage Buildings (except 643-29G, Mixed Waste Storage Building (MWSB) are operated under a Part B permit issued in September 1987. All other hazardous waste management activities at the SRS are currently being conducted under Interim Status Standards. As such, facilities must comply with the Interim Status Standards (R.61-79.265) and must not engage in hazardous waste activities or processes not specified in the RCRA Part A application.

DOE Order 5480.3

This order establishes the requirements for the packaging and transportation of hazardous (including radioactive) materials, substances, and wastes.

DOE Order 5820.1

This order establishes administrative controls and requirements for the generation, treatment, packaging, storage, transportation, and disposal of transuranic (TRU) contaminated material and TRU waste. These requirements include segregation and certification programs for TRU

generated material, reduction of TRU waste, and preparation for offsite disposal of TRU material that meet offsite disposal acceptance criteria.

DOE ORDER 5820.2A

This order establishes policies and guidelines by which the DOE manages its radioactive waste, waste byproducts, and radioactively-contaminated surplus facilities. Under this order, a waste management plan for each radioactive waste-management facility must be prepared and updated annually. These plans must include a section on the radioactive and nonradioactive monitoring programs, including groundwater monitoring.

The Waste Disposal program satisfies the Waste Disposal Requirements and the Waste Disposal Strategy objectives in Section. 6.4.

6.6.5.3 Organization Responsibilities

Waste Management (WM)

The Waste Management Department has the primary responsibility for selecting, permitting, constructing and operating waste disposal facilities.

Environmental Protection Section (EPS)

The EPS is responsible for coordinating and organizing the permitting for the waste disposal facilities. The EPS is also responsible for reporting the status of waste disposal compliance to the DOE and SCDHEC.

Custodial Departments

The Custodial Departments are responsible for proper identification and packaging of wastes according to regulatory, DOE and Department of Transportation (DOT) requirements.

Savannah River Laboratory (SRL)

The SRL is responsible for research and development (R&D) in support of waste disposal.

6.6.5.4 Waste Management Objectives and Strategy

The SRS waste management objectives are to comply with applicable regulations, to minimize effects on the environment and, to the extent

possible, contain waste handling, treatment, storage, and disposal within the site. Exceptions to onsite final disposal are: PCBs, which must go to EPA-approved PCB disposal facilities; high-level wastes and TRU wastes, for which federal repositories are to be designated; some types of nonradioactive hazardous waste, which are sent offsite for incineration and disposal until onsite facilities are available; chlorinated hydrocarbons, lead batteries and scrap metal, which are sold to commercial recyclers.

The strategy for achieving these objectives is to:

- Ensure waste can be disposed of before it is generated.
- Reduce/minimize waste generation.
- Recycle or consume wastes in processes as much as practical.
- Segregate wastes at the generating location for temporary storage in permitted facilities.
- Incinerate to destroy hazardous wastes and reduce waste volume.
- Treat wastes to minimize mobility before final disposal.
- Dispose of newly generated wastes ultimately in monitored repositories.
- Maintain integrity of existing disposal sites to assure performance objectives are met.

The major categories of wastes generated at the SRS are nonradioactive nonhazardous, nonradioactive hazardous, mixed (hazardous and radioactive), low- and intermediate-level radioactive, high-level radioactive and transuranic. Figure 6.6.5-1 provides an overview summary of the site waste management plan. Within each of these six categories there are a multitude of waste streams requiring numerous storage and disposal techniques. Five of the waste streams, the waste slurry from M Area Liquid Effluent Treatment Facility (LETFF), the waste slurry from F/H Area ETF, waste streams requiring mixing and disposal as saltstone, tritiated wastewater, and depleted uranium, are discussed in detail.

The following descriptions provide an overview of the storage and disposal practices, both current and future, for the six waste categories and the five highlighted waste streams.

Nonradioactive Nonhazardous Waste

For nonhazardous solid waste, the SRS complies with RCRA Subtitle D requirements which is a South Carolina regulated program. Programs are in place for managing SRS waste streams which include land reclamation, sanitary landfilling, salvage/recycle, wood burning and erosion control. A detailed flow chart of the current and recommended programs for the

management of the nonradioactive nonhazardous waste streams generated is shown in Figure 6.6.5-2.

Land reclamation involves disposal of land enhancing materials in ash basins and piles and areas designed for sanitary sludge disposal. The ash basins and piles have been used primarily for the disposal of coal ash from powerhouse operations located throughout the SRS. Land reclamation is also used for the disposal of sludge generated at SRS sanitary wastewater treatment plants (refer to Section 5.6.5).

A sanitary landfill is currently used at the SRS for disposal of general garbage and paper waste, rubble and construction waste, and asbestos enclosed in bags. Refuse from regulated areas that is not contaminated will be surveyed for radioactivity, certified as nonradioactive waste and sent to the sanitary landfill. A 70-acre site is being used for the sanitary landfill. Operation of this site began in 1973, and it is expected to be filled by 1991.

A program aimed at reducing the volume of waste disposed of in the sanitary landfill using incinerators and/or compactors will be considered (refer to Section 6.6.6). Discussions are ongoing with regulatory agencies concerning the expansion of this site to meet future waste disposal needs and the construction of a new nonhazardous solid waste disposal facility.

Salvage activities at the SRS involve the sale of empty drums, scrap metal, batteries, and excess equipment to commercial recyclers.

Several wood burning pits and scrap lumber piles are located on the site for burning and stockpiling excess wood. The SCDHEC has approved sites for wood burning activities and is notified before each burning.

Erosion control sites include four approved areas in which inert construction debris such as asphalt, roofing materials, stump and concrete rubble are placed to reclaim eroded areas. An application to the SCDHEC for four additional sites has been submitted.

Disposal options for the more than 200,000 scrap railroad ties are currently being investigated. Since a few of the railroad ties have the potential to be slightly radioactively contaminated, offsite disposal is not an option. The SRS is unable to obtain a permit to burn the ties due to opacity restrictions. The railroad ties are currently piled near the wood burning pit north of F Area until an appropriate disposal method can be determined and implemented.

RCRA Permitting

RCRA permit application, modification, and implementation is an ongoing process for treatment, storage or disposal facilities. Several examples of RCRA permitting activities at the SRS are as follows:

Permitted

- Hazardous Waste Storage Buildings 709-G,-2G,-4G, and 710-U
- M Area Basin Post Closure Care

Permits Pending Regulatory Approval

- Consolidated Incineration Facility (08/88)
- Benzene Storage Tank at DWPF (12/88)
- M Area Process Interim Treatment/Storage Facility (07/88)
- Mixed Waste Management Facility (MWMF) Post Closure Care (07/88)
- Mixed Waste Storage Building 643-29G (08/86)
- Hazardous Waste/Mixed Waste Disposal Facility (11/88)
- Solid Waste Storage Pad, Building 709-G,-2G-4G (12/88)

Interim Status (Operating Facilities)

- SRL Waste Storage Tanks
- 643-29G Mixed Waste Storage Building
- Transuranic (TRU) Pads (6-13)
- M Areas Process Waste Interim Treatment/Storage Tanks
- High-Level Waste Tank Farms
- Solid Waste Storage Pad, Building 709-G,-2G,-4G

Permit Applications to be Submitted

- Transuranic Waste Facility (08/89)
- Y Area Saltstone (09/89)
- M Area Tanks Closure Plan (06/89)
- TRU Pads 1-5 RCRA Storage Subpart X (09/89)
- TRU Pads 6-13 RCRA Storage (09/89)
- SRL Waste Storage Tanks (12/89)
- F/H Area Seepage Basin Closure Care (12/90)
- M Area Interim Storage Pad (12/89)
- Metallurgical Laboratory Basin Post Closure Care (08/89)
- Acid/Caustic Basins Post Closure Care (08/89)
- DWPF Vitrification Facility (date pending)

Tank Farm Permitting

On May 1, 1987, DOE issued a final interpretive rulemaking for the purpose of clarifying DOE's obligations under RCRA. The effect of the rule was that all DOE radioactive waste which is hazardous under the RCRA definition is subject to regulation under both RCRA and AEA. Since the time of this interpretation, SRS has had ongoing discussions with EPA and SCDHEC concerning regulation of the tank farms as either RCRA or wastewater facilities. DOE requested that SRS pursue the path of preparing a RCRA permit application while the discussions continued. On June 30, 1989, a letter was received from SCDHEC stating that the F and H Area High Level Waste Tanks should be permitted pursuant to the South Carolina Pollution Control Act. This requires that the tank farms be permitted as wastewater facilities. Waste Management is preparing the wastewater permit for the tank farms. Also, a Federal Facilities Agreement (formerly Interagency Agreement) which is being negotiated by EPA, SCDHEC, and DOE will specify requirements for secondary containment and leak detection for the tank farms. These requirements will be similar, but not identical to, the RCRA tanks standards specified in 40 CFR 264.

Nonradioactive Hazardous Waste

Current, planned and proposed programs for the treatment and disposal of nonradioactive hazardous waste streams are shown in Figure 6.6.5-3. Nonradioactive hazardous waste is generated sitewide, predominately from Construction, Raw Materials, Central Services Works Engineering (CSWE), and the SRL-TNX. This waste includes paint solvents, extrusion press oil, halogenerated degreasing solvents, and machine coolant. Current onsite programs for the management of nonradioactive hazardous waste are storage of the waste in permitted hazardous waste storage buildings (Buildings 709-G, 709-4G, and 710-U), and the use (burning) of waste oil in SRS powerhouses for energy recovery.

Various hazardous wastes (e.g., solvents and pesticides) and contaminated soil from the Chemicals, Metals and Pesticides (CMP) pits are stored in RCRA permitted hazardous waste storage facilities. All buildings used as hazardous waste storage facilities are operated in accordance with a RCRA Part B permit issued in September 1987.

Storage of incinerable hazardous waste or shipment for incineration offsite, except land ban solvent wastes, will continue at permitted facilities until the Consolidated Incineration Facility (CIF) begins operations. Ash from the CIF will be stabilized as ashcrete at the CIF and then disposed in a proposed

Hazardous Waste/Mixed Waste Disposal Facility, except for a small fraction that may be hazardous which will be disposed of in the Y Area Waste Solidification and Disposal Facility. Currently, the nonincinerable hazardous waste, such as corrosive, heavy metals and reactive metals, are stored in RCRA permitted hazardous waste storage buildings/pads. A proposed facility stabilizing the nonincinerable hazardous waste would allow the portion rendered nonhazardous to be disposed of in the sanitary landfill, thereby reducing the volume of waste to be disposed of in the Hazardous Waste/Mixed Waste Disposal Facility.

It is planned that the drums that have been emptied of their hazardous contents will be sent to a drum crusher before being disposed of in the Hazardous Waste/Mixed Waste Disposal Facility. Residuals from the drums will be treated and stabilized before disposal. Rinsing will be conducted if required.

Nonradioactive waste oil is being burned as a fuel supplement in two powerhouse boilers. This energy recovery is not considered as a disposal method under RCRA, and therefore the boilers do not require a RCRA permit. Once operating, the CIF will provide a second alternative for use of the waste oil.

Lead batteries are sold to commercial firms and the federal government for salvage. Silver recovery is conducted on photographic wastes.

PCBs are not classified as hazardous waste by RCRA standards, but do require special handling and disposal under TSCA. Equipment containing PCBs such as transforms and capacitors have been replaced. Final disposal of PCB material offsite is at an EPA-approved facility.

Mixed Waste

Current and planned programs for the management of mixed waste (radioactively contaminated hazardous waste) are presented in Figure 6.6.5-4. Examples of mixed waste are tritiated oil, F006 sludge, mercury, lead, cadmium, silver, benzene and scintillation fluids. Most of the mixed waste is being stored until the CIF and the Hazardous Waste/Mixed Waste Disposal Facility begin operation.

Currently, tritiated oil is stored in sealed DOT 17-E drums placed inside concrete culverts in one of the Mixed Waste Storage Buildings if contamination is >50 nCi/ml. The latter approach is also used for spent scintillation fluid. Radioactive PCB-material is stored in enclosed concrete

culverts in 643-29G until an offsite TSCA-approved mixed waste disposal facility becomes available.

Mixed waste is also stored at some of the generator facilities for a period up to ninety days, after which the waste must be transferred to a RCRA permitted or interim status facility. There are currently two permitted mixed-waste storage buildings: one for low activity mixed waste, high activity mixed waste. The mixed waste managed by this storage method includes tritiated mercury from the tritium facilities, tritiated oil (>50 nCi/ml) from the reactor areas and Tritium facilities, solvents from various area facilities, lead, and lead-containing equipment. Mercury pumps in the tritium facilities are being replaced with nonmercury pumps, which will reduce the amount of contaminated mercury generated for storage. In addition, the SRL is currently demonstrating a mercury decontamination process for DWPF mercury.

Low-Level and Intermediate-Level Solid Radioactive Waste

Figure 6.6.5-5 shows current, planned and proposed programs for the management of low-level and intermediate-level waste. Low-level waste (LLW) and intermediate-level waste (ILW) are generated sitewide. These waste streams consist of contaminated operating and laboratory wastes such as small equipment, plastic sheeting, protective clothing, soil, used equipment from production facilities, and other job control waste.

LLW is defined as waste that radiates 300 mR/hr or less at three inches from an unshielded container. It also must contain less than 100 nCi of transuranic nuclides per gram of waste. The LLW is buried in engineered low-level trenches (ELLTs) in the Radioactive Waste Burial Ground, 643-7G. Refuse from regulated areas but known to be free of radioactivity is surveyed for radioactivity, certified as clean waste, and sent to the sanitary landfill for disposal.

Intermediate-level waste (ILW) radiates more than 300 mR/hr at three inches from an unshielded container. An improved disposal technique, Greater Confinement Disposal (GCD) is used for some ILW. The objective of GCD is to provide a near zero release facility that will provide improved containment of radionuclides and require minimum maintenance after closure. The two GCD concepts are the GCD boreholes and the GCD engineered trench. Oversize ILW waste that cannot be packaged for GCD is placed in shallow land burial trenches.

Planned programs for the disposal of LLW and ILW include the opening of new Low-Level Waste Storage/Disposal Facilities, and treatment of both liquid and solid LLW by the Consolidated Incineration Facility (CIF). Size reduction and stabilization processes are planned for LLW and possibly ILW going to the new Low-Level Waste Disposal Facilities.

The planned New Low-Level Waste Disposal Facility will have an above-ground facility for future interim storage of wastes contaminated with long-buried radioisotope (i.e. C-14, I-129) until an appropriate disposal facility is determined.

Tritium containing waste will be placed in storage vaults to allow for decay. After 120 years the remaining waste will be disposed of as LLW or ILW, depending on the residual activity level.

Transuranic Waste

The current and planned programs for the management of transuranic (TRU) waste are shown in Figure 6.6.5-6. TRU waste is material which is contaminated with alpha-emitting radionuclides of atomic numbers greater than 92 having a half-life greater than 20 years and in concentrations greater than 100 nCi/g. Since 1974, all TRU waste has been retrievably stored on above-ground concrete pads in the Low-Level Waste Disposal Facility. The programs developed by the SRS include facilities to process and evaluate TRU waste for management by onsite disposal at the Waste Isolation Pilot Plant (WIPP) in New Mexico. Two facilities included in these programs are the Waste Certification Facility (WCF) and the TRU Waste Facility (TWF). The first phase of the WCF was completed in 1986 and includes facilities to assay, x-ray and weigh 55-gallon drums of suspect TRU-contaminated waste material. The second phase of this facility will be completed in 1989 and will include facilities to prepare drums for shipment and to load drums into the Transuranic Package Transporter (TRUPACT) for shipment to the WIPP. The TWF will include facilities and equipment to retrieve TRU waste from retrievable storage in the Low-Level Waste Disposal Facility; vent, purge, shred and repackage drums; reduce sizes and repackage bulky waste; and solidify waste. The proposed startup for this facility is 1995.

The processes and methods used to certify newly generated TRU waste for disposal at WIPP are described in the *Savannah River Certification Plan for Newly Generated, Contact Handled Transuranic Waste*, DPSP 84-17-1. For purposes of the certification program, newly generated drummed TRU waste is divided into five categories: job control waste, resin, high efficiency

particulate air (HEPA) filters, sludges and miscellaneous waste. With existing facilities, only job control drummed waste can be packaged to meet the comprehensive waste packaging requirements for WIPP. Under this program, the five TRU waste generating facilities segregate and package the drummed waste as certifiable or noncertifiable. The certifiable waste is sent to the WCF for final nondestructive examination to verify that all waste packaging requirements for WIPP have been met. This waste is then placed in temporary storage to await shipment to WIPP. The noncertifiable drummed waste and waste in all other containers is placed in interim storage for eventual processing in the TWF.

After evaluation at the WCF, the waste certified <100 nCi/g is placed back in storage for future disposal and the waste >100 nCi/g is placed in interim storage pending shipment to the WIPP. Onsite disposal is managed by shipping the TRU waste to the Low-Level Waste Disposal Facility, with that waste contaminated at 10 to 100 nCi/g going to the GCD trench. The WIPP facility under construction will be a development facility for demonstrating the safe disposal of TRU waste in an underground repository. Shipments to WIPP are scheduled to begin when a review by the National Academy of Sciences is complete, Land withdrawal Legislation is passed by Congress, and RCRA permitting is completed for WIPP.

High-Level Radioactive Waste (Mixed Waste)

High-level radioactive waste (HLW) disposal methods are shown in Figure 6.6.5-7. HWL is generated in the chemical separations facilities and at the SRL.

Currently, the HLW is in tanks designed to receive high-level radioactive process effluents. The processing of the liquid HLW begins by separating sludge and aqueous fractions. The sludge is allowed to settle in a tank. The aqueous fraction is evaporated, forming a damp salt cake. Both fractions are then aged to allow decay of short-lived radionuclides before further processing. The salt waste is treated for disposal by an in-tank precipitation process to remove the radioactive components from salt wastes. In this process, over 99.9 percent of the radioactivity in the salt portion of the waste is precipitated and removed from solution by filtration. The resulting decontaminated salt solution, which represents about 90 percent of the HLW volume, will be piped to an onsite disposal area where it will be mixed with cement, and fly ash, to form a nonhazardous grout called saltstone. The saltstone will be placed in near-surface concrete vaults for disposal (see Saltstone Disposal discussion).

The HLW sludges, which contain about 70 percent of the radioactivity, and the precipitate from the salt decontamination process will be piped as slurries to the DWPF vitrification facilities, which are scheduled to begin operation in 1990. Before being fed to the glass melter, the sludges and precipitate will go through several treatment steps. Treatment of the precipitate results in the formation of benzene and other organics which will be collected in a RCRA permitted tank and incinerated in the CIF. The treated precipitate stream, with about 90 percent of the organic removed, is combined with the treated sludge and glass-making material and fed to the glass melter, where the waste solids actually dissolve in and become part of the glass. The glass will be poured into stainless steel canisters where it will solidify. The glass containers will be placed in temporary onsite storage until a federal repository is available. It is anticipated that additional onsite storage will be needed prior to the availability of a federal repository.

Tritiated Wastewater

The current, planned and proposed programs for the management of tritiated waste water are shown in Figure 6.6.5-8.

Tritiated water from D Area is discharged directly to Beaver Dam Creek where it flows to the Savannah River. The disassembly-basin purge-water from K, P, and L Areas is discharged to the respective area seepage and containment basins, where atmospheric exchange and radioactive decay occur prior to and during subsurface flow to onsite streams. Usage of the basins could be discontinued if a proposed Engineered Basin serving P, L, K, and D Areas were selected.

Currently the evaporator overheads and untreated effluents from F and H Areas are sent to the F/H Effluent Treatment Facility (F/H ETF). Effluents from the F/H ETF are discharged directly to Upper Three Runs Creek. While the discontinued use of seepage basins will eliminate the discharge of hazardous waste, it will eliminate the tritium decay mechanisms afforded by seepage basins. Discharges to the Savannah River from the F/H ETF will elevate tritium concentrations relative to current contributions. Although tritium concentrations will be below EPA drinking water standards, the development of methods to reduce tritium concentrations at the source will continue to be investigated (see Section 3.6.9).

Wastewater (i.e., building condensate and sumps) from the buildings in the reactor areas is trucked to the F Area Separations evaporators for processing. Evaporator overheads are currently discharged to the F Area seepage basins. None of the tritium is removed via the evaporation process.

Depleted Uranium

The storage and disposal scheme for Depleted Uranium is shown in Figure 6.6.5-9.

Uranyl nitrate solution is generated as a byproduct of plutonium production in the F-Canyon Purex process. The solution is processed in the FA-Line facility to produce a uranium oxide powder (yellow cake). Several methods of reprocessing and/or recovery of this material have been studied and have shown that it is not cost effective to recover the depleted uranium. The material is stored onsite awaiting possible future reprocessing.

Drums of uranium oxide are stored in several areas onsite: F, R, and B Areas. Construction of two large buildings in F Area is underway to consolidate storage of the uranium oxide powder drums.

Visual inspections are performed periodically for accountability and environmental purposes. Repackaging of old or corroded drums is done when required to prevent breach of containment.

Waste Slurry from M Area Liquid Effluent Treatment Facility (Mixed Waste)

Current and planned programs for waste management in M Area are presented in Figure 6.6.5-10. The M Area Liquid Effluent Treatment Facility (LETf) was designed and constructed to treat liquid effluents from the fuel and target fabrication facility. The LETf includes a Chemical Transfer Facility (CTF), a Dilute Effluent Treatment Facility (DETF), and the Process Waste Interim Treatment/Storage Facility (PWIT/SF).

Concentrated uranium waste, acid waste and caustic waste from M Area are blended and neutralized in the CTF. The resulting precipitate is concentrated and stored in interim status waste tanks for eventual disposal as a saltstone waste form. Because the sludge comes from an electroplating facility it is a listed waste (F006). Efforts to delist the waste are underway. If delisting is accomplished, disposal in a RCRA permitted facility would not be necessary.

The DETF provides for the neutralization and filtration of M Area dilute wastes. The filtered solids are sent to the CTF for processing. The remaining effluents (filtrate) meet NPDES discharge limits and are released to Tim's Branch through NPDES outfalls M-004 and A-014.

6.6.5 Waste Management and Disposal Practices

Further processing of this waste will include sending the supernate from the stored sludge to the DETF for processing. This will reduce the volume of sludge requiring final disposal as saltstone.

Waste Slurry from the F/H Effluent Treatment Facility

The F/H Effluent Treatment Facility (F/H ETF) treats wastewater generated in the Separations Areas and possibly liquid waste streams from the Naval Fuel Manufacturing Facility and the proposed Fuel Production Facility. The F and H Area waste streams are classified as hazardous because of corrosivity, and EP toxicity. Usage of the F/H Area seepage basins was discontinued by October 8, 1988, as required by RCRA. Operation of the F/H ETF began in 1988.

The waste treatment scheme for the F/H ETF is presented in Figure 6.6.5-11. The process consists of filtration, organic removal, reverse osmosis and ion exchange. Concentrated liquid waste streams from these processes are evaporated. The reverse osmosis permeate and condensate from the evaporator overheads are discharged in compliance with an NPDES permit. The evaporator bottoms will be sent to Tank 50, before being disposed of in Z Area as saltstone, unless the activity is too high, in which case, the slurry will be stored in the HLW tanks for eventual processing in the DWPF.

Saltstone Disposal

The disposal program for two planned saltstone disposal facilities is presented in Figure 6.6.5-12.

The Z Area mixing and disposal facility is designed to solidify decontaminated salt solution rendering it nonhazardous. This solution contains sodium chromate and has a high pH, both of which cause the solution to be characterized as hazardous under SCDHEC regulations. Concentrated slurry from the F/H ETF will also be processed in Z Area. The salt solution will be mixed with a slag based cement and fly ash to form a nonhazardous grout called saltstone, which is suitable for long-term disposal in above grade concrete vaults.

It is planned that the slurry from CIF off-gas treatment will be mixed with the sludge from the M Area LETF and then stabilized in a RCRA designed Saltstone Mixer. If the saltstone is determined to be nonhazardous it will be sent to Z Area for final disposal. If the resulting saltstone is determined to be hazardous it will be disposed of in Y Area, which will have been permitted as a RCRA disposal site.

The effluents from the Naval Fuel Facility and Fuel Production Facilities will also eventually go to a saltstone facility.

6.6.5.5 Waste Generation

Table 6.6.5.1 provides the 1989 SRS waste generation forecast.

Nonradioactive hazardous waste is generated sitewide. Approximately 718 cubic feet per year is generated by all departments.

Mixed waste is generated primarily by Raw Materials, Reactors, Separations and Tritium. It is estimated that the departments collectively generate approximately 1934 cubic feet per year. Raw Materials is the largest contributor, generating approximately 900 cubic feet per year.

Low-level and intermediate-level radioactive waste is generated sitewide. Approximately 1,076,400 cubic feet of low-level waste and 53,840 cubic feet of intermediate-level waste is generated annually. The largest contributors are Separations, Naval Fuel, Reactors, Raw Materials and Waste Management.

Separations is the primary producer of transuranic waste, generating 55,617 cubic feet per year.

6.6.5.6 RCRA Permitting Requirements

This section summarizes the RCRA permitting activities related to existing and planned hazardous and mixed waste treatment and disposal facilities. RCRA Facility Investigation (RFI) studies and permitting activities related to waste site closures are discussed in Section 6.6.7.

Environmental Protection Section (EPS)

The EPS coordinates the site RCRA permitting efforts. Currently the EPS is assisting the custodial departments revise the site RCRA Part B permit to include additional existing and planned facilities. The total five-year cost is estimated to be \$1.4 million.

Waste Management (WM)

Waste Management has prepared the RCRA Part B submittals for the Hazardous Waste/Mixed Waste Disposal Facility and the Consolidated Incineration Facility, and is preparing the RCRA Part B submittal for Y Area

and the TRU pads. A RCRA Closure Plan was submitted for the F and H Seepage Basins after the operating permit was denied. Revisions for the Mixed Waste Management Facility submittals are made as needed. A Part B permit application for the HLW Tank Farms which may be submitted to the SCDHEC depending on the outcome of discussions among the DOE, SCDHEC and EPA. Revisions will be needed to the Tank Farm permit application for two new facilities: The New Waste Evaporator and the Hazardous Low-Level Waste Processing Tanks. The total five-year cost is estimated to be \$6 million.

DWPF

DWPF is responsible for preparing the RCRA Part B submittal for the DWPF Organics Storage Tank and the DWPF vitrification process should these facilities become classified as Mixed Waste facilities. The total five-year cost is estimated to be \$583,250.

SRL - Technical Area (Tech)

Tech is responsible for preparing the RCRA Part B submittal for the Metallurgical Laboratory Basin and the SRL Mixed Waste Storage Tanks. The total five-year cost is estimated to be \$253,750.

6.6.5.7 Current Facilities Operations

The facilities currently operating for the treatment, storage and disposal of waste at the SRS are described below. Costs and manpower requirements for operation of the facilities until 1993 are provided.

Waste Management

●**Hazardous Waste Storage**—Hazardous waste is stored in facilities that are permitted by the SCDHEC. These facilities will continue to operate until the CIF and similar facilities are available to process waste. The total five-year cost is estimated to be \$3.4 million.

●**High-Level Waste Tanks**—Approximately 34 million gallons of high-level radioactive liquid wastes are stored in 51 subsurface carbon steel waste tanks encased in concrete vaults (one tank is an emergency spare and has never held waste). The majority of waste tanks are 1.3 million gallon double-wall steel tanks. The annular space between the tank walls is monitored and inspected for leaks. Surveillance instrumentation includes

conductivity probes to detect leakage and monitors for temperature, benzene, hydrogen and radiation. Of the remaining tanks, most have partial secondary containment, sufficient to contain leakage but not capable of holding the full volume of the primary tank. Some tanks are only single wall, although they have leak detection and are encased in concrete vaults. In the event leakage is detected, the waste is transferred out of the leaking system. It is expected that the use of single-wall tanks will be discontinued by the mid to late 1990s. Type IV tanks (single wall) have had most of the HLW removed. The total cost are as follows:

- Salt Removal - New Tanks Cost Projects - \$77 million
- Tank Farms (New Waste Transfer Facilities Operations) - \$15.7 million
- Tank Farms (Non-Routine Maintenance and Upgrades) - \$101 million
- Waste Transfer - Old Tanks Operation - \$9.5 million
- Waste Transfer - Old Tanks Cost Project - \$34 million

●**Low-Level Waste Disposal Facility**—The present Low-Level Waste Disposal Facility (also referred to as the Radioactive Waste Burial Ground) is located between F and H Separations Areas. This facility is an area of approximately 61 acres consisting of trenches, greater confinement disposal boreholes, and pads used for the storage or disposal of low-level, intermediate-level, and TRU solid waste. The MWMF is completely within the boundaries of the active radioactive waste burial ground. The total combined area of the burial ground and MWMF is 119 acres. The total five-year cost of the Low-Level Waste Disposal Facility is estimated to be \$16 million.

●**Mixed Waste Storage**—The Mixed Waste Facilities (MWFs) consist of an inactive landfill (the Mixed Waste Management Facility, MWMF) and two active container storage buildings (Mixed Waste Storage Buildings (MWSB) 709-2G and 643-29G). The MWMF and one MWSB are within the boundaries of the Low-Level Waste Disposal Facility. The second MWSB has been constructed at the Central Shops Area. Covering an area of approximately 58 acres, the MWMF consists of a number of individual shallow land burial trenches that were used for the disposal of candidate mixed wastes. Closure plans are under review by SCDHEC. The total five-year cost is estimated to be \$6.6 million, which does not include closure costs.

●**Nonradioactive Hazardous Waste Storage**—Nonradioactive hazardous waste is stored on site in three RCRA Part B Permitted hazardous waste storage buildings (Buildings 709-G, 709-4G, and 710-U). The buildings are constructed with sloped floors, dikes, and sumps to provide adequate containment in the event of a spill. Effective separation of incompatible chemicals is provided. Ignitable waste is separated from other waste by a fire wall in 709-2G. The buildings contain more than 2000 55-gallon drums and 82 five-gallon drums. The total five-years cost is estimated to be \$8 million.

●**Radiation Survey**—The Landfill Monitoring Facility, located across from the burial ground, performs a final survey on clean waste to certify that the waste meets the criteria (<10 nCi/box) for disposal in the sanitary landfill. State-of-the-art radiation detection monitors are used. Operating costs for this facility are incorporated into the Sanitary Landfill operations.

●**Sanitary Landfill**—The sanitary landfill is a 70 acre fenced, controlled access waste site for nonhazardous wastes (from offices and lunchroom/cafeterias) and clean (nonradioactive) waste. The waste trenches are 12 to 18 feet deep and 20 feet wide with a sloped vehicle approach to the bottom. The trenches are backfilled daily with a one-foot overburden by lengthening the trench. The full trenches are backfilled to the original ground level with three to five feet of overburden. The current site is projected to be filled in FY91. The total five-year cost is estimated to be \$3.8 million. A FY93 line-item project will provide a new 80-acre sanitary landfill at an estimated cost of \$68 million (see Section 6.6.5.8).

●**TRU Waste Certification Facility (WCF)**—The WCF was constructed in two phases. The first phase, called the Experimental Transuranic Waste Assay Facility (ETWAF), was constructed in 1985 for \$1.1 million and includes equipment to assay, x-ray and weigh the 55-gallon drums of waste to verify they have been packaged to meet the WIPP waste acceptance criteria. No waste packages are opened in the facility. The second phase, completed in 1987 at a cost of \$970,000 provides facilities to prepare drums for shipment and to load the drums into the TRUPACT transport container. The total estimated operating cost for the five-year period is \$17.3 million.

Power Operations

●**Ash Basins**—Ash sluice water or dry ash from the numerous powerhouses onsite is discharged to ash basins or ash piles in the vicinity of each powerhouse. Currently, there are six active ash basins/piles with the following inventories: A Area (3000 cubic yards per year), D Area (65,000

cubic yards per year), H Area (12,000 cubic yards per year), K Area (18,000 cubic yards per year), and P Area (18,000 cubic yards per year). The total five-year cost is estimated to be \$308,250.

However, periodic cleanings of the ash basins are required to allow adequate settling time for ash so that total suspended solids levels do not exceed NPDES limits at the basin outfalls. Presently, inactive ash basins are targeted as receptacles for ash removed from operating basins.

Basin 488-1D is to be dredged in FY89 and the spoil ash placed in the inactive 488-D basins once the dike heights have been increased. The cost of the project is \$3.2 million.

Basin 288-H is to be cleaned in FY89 and the spoil ash placed in the inactive 288-F and 288-1F basins. The 288-1F basin will be closed as a waste site and the ash will serve as an inert fill material. The cost of the project is \$1.6 million.

Ash pile 788-2A will be taken out of service in FY89. Ash from the powerhouse 784-A will be trucked and placed into inactive basin 288-F. Cost for the project will be \$120,000.

No remediation is necessary in basin 188-P (cleaned in FY87) or basin 188-K (adequate capacity for four years of operation) at this time.

•**Powerhouse Boiler**—The powerhouse boilers in D Area are used to burn waste oil for heat recovery. The manpower and costs requirements for this procedure are absorbed by the routine steam and electrical generation cost.

•**Sanitary Treatment Plants**—There are 19 Sanitary Wastewater Treatment Plants (SWTPs) currently permitted at 13 SRS facilities. Increased treatment capacity has been implemented in F Area SWTPs and will be installed in A and D Areas. SWTPs in all areas will have equalization tanks installed to permit deferring the treatment of peak waste input to periods of minimal input. Section 3.6.6 chapter discusses in detail the current and planned programs for the SWTPs. Costs and manpower requirements for operating and modifying the SWTPs are figured into the Surface Waters and Wetlands resource requirements (Section 3.7).

Raw Materials

●**Liquid Effluent Treatment Facility**—The M Area liquid effluent treatment facility (LETF) was designed and constructed to treat liquid effluents from the fuel and target fabrication facility. Operation of the facility began in the spring of 1985. The facility eliminates the use of M Area settling basin. The LETF includes a chemical transfer facility, a dilute effluent treatment facility, process modifications for rinse water reduction, and temporary storage tanks. The treated liquid effluents from this treatment facility, which meets NPDES discharge limits, is discharged to Tim's Branch. Solids are being stored for further processing which will include plans for solidification as saltstone and disposal in Y or Z Areas. Operating costs are provided in Section 3.6.6.

Reactors

●**K Area Containment Basin**— An unlined 50-million-gallon containment basin, located outside the K Area perimeter fence is used for low-level radioactive (primarily tritium) purge water from the K Reactor disassembly basin. The containment basin is rectangular in shape, measuring 559 feet by 616 feet. It has been in use since 1966, receiving fission and activation products. Operating costs are minimal and are included in K Reactor costs.

●**P and L Area Seepage Basins**—The P and L Area Seepage Basins receive low-level radioactive (primarily tritium) purge water from the respective reactor disassembly basins. There are three P Area seepage basins located just outside of the P Area perimeter fence. Overflow from Basin Number 1 is discharged into Basin Number 2, which in turn overflows to Basin Number 3. The L Area seepage basin is located outside the L Area perimeter fence. The basins were constructed by excavating below grade and building dikes around the sides at grade level. Operating costs are minimal and are included in P and L Reactor costs.

●**Reactors Waste Handling**—Normal waste management in the Reactors facilities is an on-going activity. Waste management activities include boxing and shipping reactor waste and shipping wastewater and waste oil. The total five-year cost is estimated to be \$4.5 million.

Separations

●**Onsite Storage for Depleted Uranium**—Construction of three large buildings in F Area has recently been completed at a cost of \$825,000. These buildings provide consolidated storage for uranium oxide powder

drums. One building has a capacity of 10,000 drums. The two larger buildings have capacities of 20,000 drums each. Annual operating costs are minimal.

•**Separations Low- and Intermediate-Level Waste Handling**—This activity involves the handling and packaging of low and intermediate-level solid waste. Costs include material and manpower for operators to handle and load the waste, and supervisors to ensure proper disposal. The total five-year cost is estimated to be \$23.9 million.

•**Separations TRU Waste Handling**—This activity involves the handling and packaging of TRU Waste. Costs include materials for packaging (drums, plastic bags and tape), the cost of manpower for operators to handle and load the waste, and for supervisors to ensure proper disposal. The total five-year cost is estimated to be \$5.5 million.

Tritium

•**Tritium Waste Management**—Normal waste management in the Tritium facilities is an on-going activity. Waste management activities include the identification, handling, packaging, short-term storage, and shipment of job-control, mixed and hazardous waste. Most waste management activities involve solid waste, but there are some liquid waste drums that require disposal. The total five-year cost is estimated to be \$1.3 million.

6.6.5.8 Construction Projects

The SRS waste management plan includes many planned and proposed projects. Those projects that are anticipated to be constructed by 1992 are described below. Cost requirements for the construction of the facilities are provided.

Waste Management

•**Consolidated Incineration Facility (CIF)**—This project will provide a process facility to incinerate solid and liquid wastes. These include wastes considered hazardous under RCRA, LLW, and mixed wastes. The resulting solid waste products from the incineration process will be solidified in a cement matrix in drums, with drumming facilities provided by this project. Solidified drums will be disposed of in the Hazardous/Mixed Waste Disposal Facility. Liquid waste from the off-gas treatment incineration process will be solidified for permanent disposal. The CIF will incinerate wastes from

storage as well as newly generated wastes. The total estimated cost for this project is \$49 million. The five-year operating cost for the CIF (including manpower, utilities and maintenance) is expected to be \$27.5 million.

●**ETF Spare Parts Storage Building, 200-F/H**—A prefabricated building at the ETF site for storage of spare parts and instruments. The building will be 3,400 sq ft with a 20 ft wall height. Air conditioning is required. This building is needed for successful operation of the F/H ETF. The ETF utility requirement of 99.5 percent requires that adequate spare parts and equipment be on hand for repair or replacement. This is a FY 91 project with a total estimated cost of \$180,000.

●**ETF Storage Building, 200-H**—A prefabricated building at the ETF site for storage of raw materials. This building is needed for successful start-up and operation of the F/H ETF. The ETF utility requirement of 99.5 percent requires that raw materials be readily available. This building is needed to provide storage for raw materials ordered for startup. This is a FY91 project with a total estimated cost of \$180,000.

●**Evaporation**—This project includes both the operation of the current tank farm evaporators, and the design and construction of replacement evaporators. Two of the evaporators are approaching 30 years of service and are becoming increasingly unreliable. The new evaporator will replace these evaporators and will provide capacity needed to process the DWPF recycle steam. The new evaporator will offer enhanced contamination control. The total five-year cost is estimated to be \$81 million.

●**F/H Effluent Treatment Facility (F/H ETF)**—This facility is a wastewater storage and treatment facility which processes routine wastewater and spills from the chemical separations facilities in F and H Areas. The facility include a 235 gpm capacity treatment plant; a 6,600 square foot building to house a control room and associated change room and office facilities; 50,000 square feet of regulated areas to contain treatment plant process equipment; two 2.5 million gallon, one 200,000 gallon and one 50,000 gallon agitated wastewater storage basins; and other support facilities. The F and H ETF started up in October 1988. Funding, manpower, and milestones for the F/H ETF are provided in the Surface Water and Wetlands Chapter, Section 3.6.6.

●**Hazardous Waste/Mixed Waste Disposal Facility**—This project provides a RCRA disposal facility for hazardous waste and mixed waste that cannot be otherwise disposed of in existing or planned facilities. Forecasts

indicate that approximately 40,000 cubic feet/year of waste (after treatment) in addition to an inventory of 170,000 cubic feet will require disposal. The total estimated cost for this project is \$19 million. The five-year operating cost is estimated to be \$4.4 million.

•**Incineration and Compaction Facilities**—In order to reduce the volume of refuse and paper disposed of in the sanitary landfill, compaction and incineration programs for nonradioactive nonhazardous wastes have been proposed. This facility, if constructed, would most likely be built after completion of the CIF and would not be available before FY 92. Costs and manpower requirements have not yet been estimated for this project.

•**Low-Level Waste Processing Tanks**—This project will provide a facility in H Area to receive and transfer hazardous low-level liquid waste streams generated by Extended Sludge Processing, ETF, In-Tank Precipitation and the Receiving Basin of Offsite Fuels. It will manage six million gallons of waste annually which will be distributed to salt and sludge removal facilities, the Tank 32 cesium removal column, and In-Tank Precipitation. The total five-year cost is estimated to be \$1 million.

•**New Low-Level Waste Disposal/Storage Facility**—A new facility for the disposal and storage of solid low-level radioactive waste is being planned. The new facility is required because the present LLW Disposal Facility is expected to be filled in late 1990. This project will provide for the site development of an additional 100 acres and the initial disposal/storage units. The site for the facility is north of and contiguous with the present LLW Disposal Facility (643-7G). The new facility will consist of concrete vaults for the disposal/storage of LLW. Tritium waste will be stored in above ground concrete vaults to permit the tritium to decay. Waste containing long lived nuclides will be stored in an above-ground building for eventual disposal in a suitable repository. The new facility is projected to meet SRS needs through the year 2008. Phased turnover is scheduled for the first quarter FY 91. The total estimated five-year cost for this facility is \$51 million.

•**New Sanitary Landfill**—This is a newly identified project. The State of South Carolina and EPA are in the process of developing new guidance and regulations concerning sanitary landfills and have indicated that the SRS use for its new Sanitary Landfill a liner/leachate collection technology. This project for the new landfill will be for 80 acres. The total five-year cost is estimated to be \$6.8 million.

•**TRU Waste Facility (TWF)**—The TWF will consist of a new building, a ventilation system with high efficiency filtration, and additional equipment necessary to retrieve and process TRU waste for disposal at WIPP. The waste will be retrieved from storage and transported to the TWF. The TWF will vent, purge, x-ray, and assay the storage containers; size-reduce the large waste not suitable for shipment; solidify free liquids, resins and sludge; and repackage the waste for shipment and permanent disposal at WIPP. The total estimated five-year cost for the construction and operation of this facility is \$55 million.

•**Waste Preparation Facility**—This is an FY93 line-item project with a total estimated cost of \$95 million. It will provide facilities to prepare low and intermediate-level solid waste for disposal. This preparation will consist of volume reduction of the waste via shedding and compaction and the containment of the waste in drums by filling the void spaces with concrete. It will reduce the volume of waste packed in the burial ground trenches, thus increasing trench life and decreasing storage/disposal costs. It will also provide facilities to contain the waste creating a more stable waste form. The total FY89 through FY95 operating cost is estimated to be \$7.8 million. Capital costs are estimated to be \$95 million.

•**Waste Solidification and Disposal Facility (also known as Y Area Solidification and Disposal Facility)**—This project is for construction of a facility in Y Area to dispose of waste generated by the 300-M Fuel Fabrication Facility. Radioactive aqueous waste solutions from various cleaning and chemical milling operations in M Area are treated in a Liquid Effluent Treatment Facility (LETf), with the concentrate stored in tanks until permanent disposal is provided. The sludge from the LETf is classified as an F006 hazardous waste (because it is wastewater treatment sludge from an electroplating process) but can be solidified and disposed as nonhazardous waste, if successfully delisted. The waste will be shipped to Y Area by truck and transferred to a storage silo. The waste will be mixed in a modified cement mixer with slag based cement, fly ash, and a grout admixture. The grout will be pumped via pipeline into engineered vault and allowed to solidify into saltstone. The total estimated cost for the project is \$22.7 million. The total five-year operating cost is estimated to be \$11.3 million.

●**Y Area Vaults**—Funding for this project provides RCRA approved vaults in Y Area for the disposal of saltstone. One vault is required each year to adequately accommodate saltstone production. The total FY93 and FY95 line-item cost is \$6 million.

SRL - TNX

●**Effluent Treatment Plant**—The TNX Effluent Treatment Plant (ETP) treats process wastewater generated in the TNX Area for discharge to an NPDES permitted outfall. The facility allows closure of the 904-102G New TNX Seepage Basin. The ETP provides flow equalization, neutralization, clarification, and solids removal. Facility startup occurred on August 16, 1988. Funding requirements for the ETP are provided in the Section 3.6.6.

●**Ion-Exchange System (Hg Removal)**—Effluents from the Integrated DWPF Melter System (IDMS), a research project in support of the DWPF, will contain low-levels of soluble mercury. An ion exchange facility will be installed to remove mercury from this waste, as well as from mercury-contaminated wastes generated in other facilities at TNX. Filtered alkaline wastewater is processed through two ion exchange columns loaded with cation exchange resin and neutralized within the facility. Funding requirements are provided in Section 3.6.6.

●**Organics Removal Facility**—Effluents from several research projects of the DWPF will contain significant quantities of soluble organic compounds. An Organics Removal Facility (ORF), consisting of dual activated carbon columns, a filtration system, and associated tanks and pumps, will be used to treat these effluents. The ORF will receive and treat effluents from four separate processes. The cleansed effluent will be discharged to Outfall X-014. Funding requirements for the ORF are provided in Section 3.6.6.

●**Satellite Storage Area, 677-T**—The new satellite area will allow for accumulation of hazardous material into one 55-gallon drum located adjacent to Building 677-T. This facility is necessary for continued compliance with SCDHEC regulations. This is a FY91 project with a total estimated cost of \$100,000.

SRL - TECH

●**Replace/Upgrade 776-A Waste Handling Facility**—This project will provide a new facility that will replace and upgrade the 776-A radioactive liquid waste handling facility.

The existing 776-A radioactive liquid waste handling facility collects and temporarily stores radioactive and nonradioactive aqueous waste generated by research activities at the SRL Technical Area, and transports these wastes to the 200 Area for final disposal. Wastes are stored in underground storage tanks protected by reinforced concrete secondary containment structures. Wastes are transported over plant roads by tanker trucks to the 200 Area. The existing facilities and equipment are over 30 years old and are nearing the end of their useful life. Layout of the facility makes inspections of the system components difficult. This facility does not provide waste treatment capability and does not have the flexibility to respond to rapidly changing environmental regulations.

The replacement/upgrade project will utilize and install state-of-the-art technology and equipment treat radioactive and nonradioactive liquid waste streams resulting from research at the SRL Technical Area. The new facilities will operate within current environmental regulations, and will provide the flexibility to address anticipated environmental regulations.

New facilities will treat the clear, nonradioactive liquid waste streams to meet NPDES guidelines and discharge effluent to the A-001 outfall. Radioactive liquid waste streams will be treated to reduce the activity of the effluent. The project will provide new equipment to shipment to ship treated effluent from the radioactive waste streams and solid radioactive secondary waste generated by the wastewater treatment process to the 200 Area for final disposal. This shipment of the solid waste will meet environmental and DOT regulations. This is an FY93 line-item. The total five-year cost is estimated to be \$7.9 million.

Reactors

●**Engineered Basin for P, L, K, and D Areas**—This proposed project would provide an engineered basin for disposal of tritiated waste water from P, L, K, and D Areas. The siting and design of the basin would provide optimum conditions for tritium decay. This project is in the preliminary

planning stages. If the engineered basin is opted for as a future alternative, construction would commence beyond the five-year planning period.

Defense Waste Processing Facility (DWPF)

•**DWPF**—The DWPF is being constructed to process high-level radioactive liquid wastes currently stored as insoluble sludges, precipitated salt, and supernatant liquid in single or double-walled tanks in the F and H Area tank farms. The process includes the removal of wastes from tank storage; pretreatment of sludge to remove most of the alumina and soluble salts; treatment of the salt to remove cesium, strontium, and plutonium, and plutonium in borosilicate glass; encapsulation of the waste glass mixture in steel canisters; storage of the canisters in a surface facility until shipment to a repository. The construction began in 1983. The total estimated cost is \$905 million. The total five-year cost is estimated to be \$640 million.

•**Z Area Mixing and Saltstone Disposal Facility** —The Z Area disposal facility is designed for disposal of decontaminated salt solution resulting from processing of high-level radioactive liquid wastes in the DWPF and ETF concentrate. The solution contains sodium chromate and has a high pH, both of which cause the solution to be characterized as hazardous under SCDHEC regulations. The salt solution will be mixed with a slag based cement and fly ash to form nonhazardous saltstone. Total five-year costs are estimated to be \$78 million.

Raw Materials

•**Waste Volume Reduction and Solidification, and Interim Storage**—The M Area Wastewater Slurry Treatment Interim Fixation Facility (STIFF) will remove dilute wastewater for treatment and discharge to Tim's Branch, treat the concentrated sludge for interim fixation in saltstone, and provide storage on a RCRA pad. This facility must be completed for M Area to produce target uranium slugs or to process supernate from waste storage tanks after the May 1990 land ban. Priority for this project will be determined by production forecasts. The total five-year cost is estimated to be \$8 million.

6.6.5.9 Research/Studies

Research supporting the waste management plan is primarily conducted by the Interim Waste Technology Section (IWTS) and Defense Waste

Processing Technology Section (DWPTS). In addition, studies addressing specific issues may be initiated by the various departments. The following summaries provide an overview of the on-going Research/Studies addressing waste disposal at the SRS. Costs and manpower requirements for conducting the research and studies until 1993 are provided.

Environmental Protection Section (EPS)

●**Railroad Ties**—The EPS is coordinating efforts to find an adequate disposal method for the used railroad ties which have been accumulated over the years at SRS. This has involved searching for ways to allow them to be salvaged, burned, or used in some other capacity on plant. The EPS will put together a research/feasibility study for this program during 1989.

●**Sanitary Landfill Waste Incinerator and Compactor**—The EPS has proposed a program for the nonradioactive nonhazardous waste currently disposed of in the sanitary landfill. This program would most likely involve using an incinerator and/or compactor. The EPS will initiate a research/feasibility study for this program during 1989.

SRL - Interim Waste Technology Section (IWTS)

●**Consolidated Incineration Support**—The IWTS continues to provide technical support for the CIF. This includes fundamental studies on incineration, safety analyses, immobilization of materials removed from off-gases by HEPA filters, and related studies. Also included are ashcrete studies for disposal of the solid residues from incineration and a study to upgrade the BGI. Milestones are as follows:

Complete burner testing	03/88
Complete off-gas studies	03/89
Complete solidification of ash demonstration	03/90

The total five-year cost is estimated to be \$7.5 million.

●**Effluent Treatment Facility Support Studies**—The IWTS is actively involved in research to support and improve the F/H Effluent Treatment Facility. This includes development and optimization of systems and processes for ion exchange, organic removal, reverse osmosis, filtration, and heavy metal removal.

The ETF began operating in October 1988. The SRL support will continue, but decrease slowly. The total five-year cost is estimated to be \$3.5 million.

●**ETF Chemical Studies**—The project provides process technology support for the F/H Area Effluent Treatment Facility. These studies are needed to ensure that ETF Operation is maintained and system availability assured. The total five-year cost is estimated to be \$2.8 million.

●**Hazardous Waste/Mixed Waste Disposal Technology Development**—Hazardous and mixed waste are generated at the SRS as a result of operations at the site. Some materials are treated by incineration. Other materials are treated by chemical fixation.

This activity will provide development and demonstration of technologies for treatment and disposal of hazardous and mixed wastes that require treatment/stabilization.

This activity will support the FY89 line-item for a new facility at the SRS for disposal of hazardous and mixed waste. Included in this task will be the evaluation and development of treatment steps for waste prior to disposal.

This will also provide support for the Y Area disposal facility. The total five-year cost is estimated to be \$5.4 million.

●**HLW Evaporator**—Evaporation processes are used to reduce the volume and mobility of stored HLW at the SRS.

This activity provides technical support to HLW evaporation activities and is aimed toward improving overall tank farm evaporator operations by increasing utility.

It will also support an FY89 line-item for a new replacement HLW evaporator. Primary focus of this activity is to improve evaporator system utility. This activity will provide support for programs to improve existing evaporator feed pumps and the newer above tank pump units. The total five-year cost is estimated to be \$2.7 million.

●**HLW Process Development**—HLW are stored in carbon steel tanks at SRS until feed preparation activities are completed that allow transfer to

DWPF (HLW) or saltstone (LLW). Several programs require analytical support for evaluation process operations and conditions.

This activity provides technology support for HLW storage/processing activities including analytical support for tank chemistry studies and operation of high-level waste facilities for waste handling and small scale testing.

These support capabilities are needed for other HLW programs including in-tank precipitation, salt removal, evaporation and sludge processing. The total five-year cost is estimated to be \$11 million.

●**HLW Storage Support**—HLW is stored at the SRS in 51 large carbon steel tanks. Understanding the composition of the waste materials and chemistry is necessary for on-going operations. This activity supports the study to the chemistry of HLW to ensure corrosion data, corrosion mechanisms and waste chemistry data bases are maintained. This activity provides for process technology to ensure waste storage conditions are assured. The activity is necessary for the continued safe storage of HLW and control of corrosion. The total five-year cost is estimated to be \$5.4 million.

●**LLW Technology**—This activity provides for continued investigations of radionuclide migration on the SRS Burial Ground and or laboratory and field tests of mechanisms associated with migration. The SRS Burial Ground and or laboratory and field tests of mechanisms associated with migration. The SRS Burial Ground is representative of conditions at commercial, shallow land burial (SLB) sites that are operating in a humid, coastal plain area. Experience from operating this site will provide information necessary to develop disposal facilities at other humid sites. Included in this will be field investigation of landfill stabilization by grout injection, dynamic compaction and chemical fixation. The total five-year cost is estimated to be \$361,000.

●**Low-Level Waste Disposal Support**—The IWTs research activities for LLW disposal includes developing new disposal concepts and techniques, assisting in the planning and design of new facilities, and characterizing the geology and hydrology of new disposal sites. Milestones are as follows:

Define packaging requirements for LLW	08/89
Complete demonstration of crucible disposal	08/89
Complete development of soil container	09/90

The total five-year cost is estimated to be \$5.9 million.

•**Naval Fuel Support Studies**—Development of improved methods to treat and solidify naval fuel wastes into a saltstone material with the existing system have been completed. These included solving heat generation problems, and improving mixing of the grout. An improved saltstone preparation facility has been identified, procured and installed. Final check out and startup is scheduled for early 1989. FY89 and FY90 funding is estimated to be \$350,500.

•**New Development HLW Processing and Waste Handling**—This program is directed at improving operations of the HLW Tank Farm by providing technology for enhancing current operations.

This activity will include development concepts for improving operation of the in-tank precipitation and resulting operation of the ITP process. In addition, this includes the demonstration of an ion exchange process as an improved method for salt decontamination.

Also, this activity will address the demonstration of additional remote equipment for use in tank farm operations. Remote equipment will be utilized for task operations such as jumper change out and maintenance. Remote equipment will be used to improve Tank Farm Operations by further reducing personnel exposure and increasing equipment repair capabilities. The total five-year cost is estimated to be \$11.2 million.

•**Nonradioactive Hazardous Waste Support**—Nonradioactive hazardous waste are generated due to several operation at the SRS. Methods to treat various waste streams require development/testing to ensure waste disposal criteria are fulfilled.

This task is to provide analytical studies for nonradioactive hazardous waste (NRHW) programs. This task will provide for development of techniques for waste analysis, waste characterization, that is necessary for the evaluation of newly developed treatment technology. In addition, this will allow enhanced methods to segregate hazardous and nonhazardous waste to be

pursued as a way to reduce final treatment and disposal costs. This will also provide for analysis of treated waste to demonstrate proof-of-concept for supporting waste facility permitting and improved waste disposal technology programs. The total five-year cost is estimated to be \$3.4 million.

●**Recovery Incineration**—TRU wastes are generated as the result of producing strategic nuclear materials. Waste contaminated with transuranics (TRU) are packaged and stored retrievably onsite awaiting transportation of the Waste Isolation Pilot Plant (WIPP) for disposal. To reduce future waste generation, methods of recovery are being developed.

This activity support the utilization of existing incineration technology for recovery of fissile material from TRU waste. Process demonstration is aimed at reducing the volume of TRU waste generated while producing incinerator residues compatible with technologies for metal recovery. The goal is to reduce the ultimate volume of waste generated. The total five-year cost is estimated to be \$1.7 million.

●**SRL ETF Support Work**—The IWTS is supporting the characterization of liquid wastes generated at SRL to provide the necessary data to enable design of an effluent treatment facility for the SRL. This program is also insuring that the liquid wastes being generated at the SRS are not hazardous. The total five-year cost is estimated to be \$2.6 million.

●**Tank Farms (NWTF) Operations Support**—This activity provides for the development of remote equipment to improve tank farm operation and reduce exposure. Includes development of remote equipment to disassemble components and reduce waste volume. This includes slurry pump testing, improved containment by new seal development and studies to improve and increase pump life.

Also, the program will address improvement of waste transfer programs by conducting slurry transfer experiments. The total five-year cost is estimated to be \$1 million.

●**Tritium Reduction In ETF Feeds**—The treatment of F and H Area waste waters in the ETF, rather than disposing of the waters into seepage basins, will result in an increase of the tritium releases to the Savannah River. A program is needed to evaluate the tritium from the major sources and investigate methods to reduce these tritium levels. Such a program will

require input from the SRL, Separations, Waste Management, and EPS. The total estimated five-year costs are \$2.5 million.

•**TRU Waste Compliance Activities**—The IWTS is developing a computer model to determine the amount of radiolytic gas generated from TRU waste drums in preparation for and during shipment to WIPP. This will allow determination of the optimum amounts of TRU to be shipped in TRUPACT shipments. Milestones are as follows:

Complete gas generation testing	05/88
Complete characterization studies	05/89
Complete data base studies	06/90
Develop packaging criteria	06/91

The total estimated costs for the five-year period are \$2.9 million.

•**TRU Waste Incineration**—The IWTS is developing incineration technology for the efficient disposal of combustible solid TRU waste. This includes both experimental incineration facilities and a mathematical modeling effort to find optimal incineration conditions. The program emphasis is to create an ash that will allow for plutonium recovery. Also included is design work for a prototype incinerator for FB line to allow plutonium recovery. Milestones are as follows:

Cold testing complete	06/88
Hot startup to begin	06/89
Process Improvements	06/90
Recovery process steps complete	06/91

Total estimated costs for the five-year period are \$1.7 million.

•**TRU Waste Processing Technology**—The IWTS has built and is operating a test facility in which components, equipment and processes can be evaluated and tested for the TRU Waste Facility. Components planned for testing include shredders, plasma arch torch, and other size reduction techniques. Equipment for opening culverts which are presently in storage has been tested in this facility as well. Milestones are as follows:

Remote drum lifter developed	06/88
Vent purge machine demonstration to begin	10/88

Operational testing complete	01/89
Remote maintenance testing complete	01/90

Total estimated costs for the five-year period are \$14 million.

•**Z Area Technical Support**—The IWTS is continuing to optimize the saltstone formulation, perform modeling studies to predict performance of saltstone and provide technical support in permitting activities. Milestones are as follows:

Complete technical data for decommissioning	06/89
Complete final decommissioning plan	12/91

The total five-year cost is estimated to be \$4.7 million.

SRL - Defense Waste Processing Technology Section (DWPTS)

•**DWPF Demonstration Facilities**—DWPTS has constructed and maintains demonstration facilities for all of the major unit operations of the DWPF. These include precipitate hydrolysis facilities, scale melters, sludge decontamination, and sealing. Besides demonstration the operations, these facilities are used to optimize operating conditions. In many instances the facilities serve as actual full scale mock-up equipment for the DWPF. Milestones are as follows:

Demonstrate operation with mercury	06/89
SAR Final available	11/89
Technical documentation	09/89
Technical support continuation	

The total five-year cost is estimated to be \$93 million.

•**DWPF Waste Compliance Technology**—This activity funds SRL support of DWPF product acceptance technology and also confirmation of product acceptability. Specific near-term goals are gaining approval of the DWPF Waste Form Compliance Plan (WCP), preparation of a preliminary Waste Form Qualification Report (WQR), assistance in including data from Integrated Cold Run in WQR, and development and implementation of QA programs for DWPF product qualification and production. The total five-year cost is estimated to be \$28 million.

M707049

Figure 6.6.5-1. Savannah River Site Waste Management (Overview)

Figure 6.6.5-2, Nonradioactive Hazardous Waste Management Plan

Figure 6.6.5-3. Nonradioactive Hazardous Waste Management Plan

Figure 6.6.5-4. Mixed Waste Management Plan

Figure 6.6.5-5. Low-Level and Intermediate-Level Waste Management Plan

* May also be mixed waste; handling is the same.

Figure 6.6.5-6. Transuranic Waste Management Plan

M707041

M707043

Figure 6.6.5-7. High-Level Radioactive Waste Management Plan

M709061

Figure 6.6.5-8. Tritiated Waste Water Management Plan

* One of the three storage buildings is complete and in use for storage of newly generated depleted uranium.

M708062

Figure 6.6.5-9. Depleted Uranium Waste Management Plan

M707040

Figure 6.6.5-10. M Area Liquid Effluent Treatment Facility Waste
 Management Plan

M707045

Figure 6.6.5-11. F and H Area Effluent Treatment Facility Waste Management Plan

* These effluents will go to 2nd saltstone mixer when it comes online (see F & H Area Effluent Treatment for current disposal practice).

M707042A

Figure 6.6.5-12. SRS Saltstone Disposal Plan

Table 6.6.5.1 1989 Waste Generation Forecast (Volumes in Cubic Feet)

<u>Organization</u>	<u>Waste Type</u>				
	<u>Low-Level</u>	<u>Intermediate-Level</u>	<u>TRU</u>	<u>Mixed</u>	<u>Nonradioactive Hazardous</u>
Laboratories	86,100	270	838	28	0
Naval Fuel	127,500	0	0	14	7
Raw Materials	82,400	0	0	900	420
Reactors	157,000	9420	0	300	0
Separations	421,000	8450	55,617	400	0
Site Services	5,000	0	0	0	0
SRL	37,600	300	992	12	250
Tritium	54,000	6,000	0	270	10
Waste Mgmt.	101,800	29,400	0	25	16
Other	4,000	0	0	0	0
Totals	1,076,400	53,840	57,447	1934	718

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.6.6 Waste Minimization

6.6.6.1 Site Program Overview

The SRS Waste Minimization Program is designed to reduce the volume and toxicity of hazardous, mixed, low-level radioactive and nonhazardous waste generated at the site in order to minimize any present or future threat to human health and the environment. The program meets regulatory and operating contractor requirements and supports the waste minimization objectives of the Environmental Implementation Plan (EIP). The program is being jointly developed by the Environmental Protection Section (EPS), Waste Management, and Savannah River Laboratory (SRL) Interim Waste Technology Section through a Waste Action Team.

The site strategy is to; 1) identify and inventory all site waste streams; 2) select candidate streams for source reduction, recycling, or treatment based on regulatory or operating contractor requirements and cost effectiveness considerations; 3) implement facility specific waste minimization programs; and 4) monitor progress on unit production basis, where appropriate. The site has already started or planned many waste reduction or recycling activities.

Over the five-year planning period over \$3.8 million is expected to be invested to implement waste minimization activities. Total five-year manpower requirements are estimated at 20 man-years of effort.

6.6.6.2 Regulatory Requirements/Justification

Federal Laws

•**1984 Resource Conservation and Recovery Act (RCRA) Amendments**—The Act requires the generator of hazardous waste to have a program to reduce the volume or quantity and toxicity of waste to the degree economically practicable and use treatment, storage, or disposal methods which minimize the present and future threat to human health and the environment.

DOE Orders

DOE Order 5400.1 —This order establishes requirements for waste minimization plans as required by the RCRA, including the establishment of a Pollution Awareness program for the site.

Policy

• **Waste Minimization Policy**—The operating contractor shall treat, dispose of, and store radioactive and other hazardous materials in a manner that minimizes waste volumes and provides the maximum protection for the environment and human health.

Divisions will reduce or modify to the extent practicable, material, procedures, or processes which produce hazardous waste. Waste Minimization programs should consider:

- Use of alternate raw materials to reduce or eliminate waste
- Recovery, recycle or sale
- Process and operational changes to eliminate or reduce the volume, quantity and toxicity of the waste.

• **Strategic Environmental Plan**—The SRS *Strategic Environmental plan* (Dupont, 1986b) contains the following waste minimization objectives:

- Reduce radionuclide releases on a per unit production basis, where it is cost effective to do so.
- Minimize the generation of low-level radioactive and hazardous waste from operating SRL facilities on a per unit production basis.
- Destroy and immobilize unavoidable hazardous wastes and residues to the maximum possible extent onsite for permanent disposal.
- Evaluate potential environmental impacts early in the development of new processes and facilities to influence design in a way that reduces waste generation and environmental impacts.

• **Waste Minimization**—Waste specific minimization goals will be set by individual operating departments and facilities as their waste minimization programs are developed through the overall site program.

The Waste Minimization program satisfies the Waste Disposal Requirements objective set forth in Section 6.4.

6.6.6.3 Organizational Responsibilities

The Environmental Protection Section (EPS) is the lead organization for the coordination of a comprehensive sitewide waste minimization program. The EPS will monitor the program progress to ensure regulatory requirements for minimizing waste are met. Waste Management is the lead organization for developing waste operations to support the site Waste Minimization Program.

A central Waste Action Team (WAT) has been established to coordinate the site's Waste Minimization Program activities. Representatives have been assigned from each site waste-generating group to participate on this team. A draft Waste Minimization Plan has been developed and is being reviewed for approval.

The custodial departments are responsible for the implementation of facility and process specific waste minimization programs.

The Savannah River Laboratory (SRL) is responsible for research and development activities needed to support the site waste minimization goals. Within the SRL, the Actinide Technology Section will review the Separations flow sheets for waste reduction opportunities, while the Interim Waste Technology Section will be the lead organization for proposing and developing waste minimization technologies for site waste streams.

6.6.6.4 Definitions

The following definitions will be used in the SRS Waste Minimization Program.

Waste Minimization—The reduction of the amount of waste that is generated or that must be subsequently treated, stored, or disposed. It includes any source reduction or recycling activity that results in the reduction of the total volume or quantity of a waste and/or the reduction of the toxicity or the toxicity classification of a waste. The reduction must be consistent with the goal of minimizing present and future threats to human health and the environment. Methods of waste minimization include waste

reduction, substitution, volume reduction, waste treatment and stabilization, delisting, and reclassification.

Waste Reduction—Any activity or treatment that reduces or eliminates the generation of a waste at the source. Waste recycling or treatment of wastes after initial generation, is not considered waste reduction. An action that concentrates the hazardous content of a waste to reduce waste volume or dilutes it to reduce the degree of hazard is not considered waste reduction. Waste reduction is measured in terms of weight per unit production.

Substitution—The use of an alternative chemical in a process which results in the production of a less toxic or nontoxic waste product.

Volume Reduction—Any treatment, storage, or disposal method which reduces the volume of waste after it is generated.

Waste Treatment and Stabilization—The processing of a waste after initial generation to produce a less toxic and/or inert substance for storage or disposal.

Delisting—The removal of a chemical from the RCRA hazardous chemical list by the Environmental Protection Agency (EPA). Delisting reclassifies a waste by demonstrating that the waste is nonhazardous.

Reclassification—The certification of waste generated in regulated areas as non-radioactive waste.

6.6.6.5 Strategy

The SRS waste minimization strategy is to identify and inventory all site waste streams, select candidate streams for reductions based on regulatory/operating contractor requirements and cost effectiveness considerations, implement facility specific waste minimization programs, and monitor progress on unit production basis. The strategy also includes development and tracking of cumulative cost savings for waste minimization efforts.

Conceptually, a facility specific waste minimization team will conduct an inventory to identify all waste streams generated by their operating facilities, review process flow sheets to determine the expected volumes of

waste produced, and determine the methods and costs associated with disposing the waste. Once these data are obtained, waste minimization technologies are reviewed and proposed to reduce or eliminate the waste generation rate.

Waste minimization approaches which are currently being followed include:

- Process Changes—Nonhazardous (or less hazardous) materials are substituted for hazardous materials where possible. Processes are also reviewed for modifications that would eliminate or drastically reduce the waste generation rate.
- Process Optimization—Process procedures are strictly followed or modified as necessary so that the existing processes/facilities will operate more efficiently.
- Segregation—Nontoxic substances are separated out from waste mixtures when feasible.
- Waste Reuse and Recycling—After treatment, some waste is recycled either in the process that produced it, or by another onsite facility.
- Detoxification Techniques—After generation, select the most cost-effective method of reducing the waste toxicity that adequately protects human health and the environment. Methods such as biological, chemical, or physical treatment and incineration are currently being utilized.
- Delisting and Reclassification—Lower the toxicity category of a waste stream by delisting applicable hazardous waste streams and reclassifying clean waste from regulated areas to nonhazardous and nonradioactive categories, respectively.
- Awareness and Training—Independent reviews of both new and existing processes by site waste minimization committees help identify ways in which waste generation rates can be reduced. Ongoing programs educate and train employees in waste generation opportunities. Additional awareness activities are planned to support the site Waste Minimization Program.

6.6.6.6 Programs/Studies

Site Waste Minimization Program

• **Environmental Protection Section (EPS)**—The EPS is coordinating the development of a SRS Waste Minimization Program with a source reduction and recycling focus to reduce the site waste generation rate. The EPS will work with generator departments through the site Waste Action Team to establish minimization goals, methods, and timetables. A computerized waste stream tracking system will be developed to monitor generation rate reductions. During FY89, Waste Management will develop a financial charge back system that would charge generating departments for waste storage and disposal.

The EPS is also responsible for compiling and submitting the quarterly SRS Hazardous Waste Report and Annual Waste Minimization Report to the Department of Energy (DOE) for transmittal to the South Carolina Department of Health and Environmental Control (SCDHEC).

The total five-year cost is estimated to be \$810,500.

• **Waste Management Operations**—Waste Management is the lead organization for developing waste operations to support the site Waste Minimization Program. This includes waste handling practices, treatment and disposal strategies, and development and implementation of a financial charge back system for waste generators. Waste Management is also responsible for advising on waste forecasting and radioactive waste operations.

Facility Specific Programs

The following are examples of existing or planned activities conducted by the generating departments and the SRL.

Process Changes

• **Raw Materials**—A nonhazardous alternative degreaser is being evaluated as an alternative to freon.

The waste stream generated by the new degreaser could be disposed as a non-hazardous waste instead of a hazardous waste stream.

The lead-oil waste previously generated in M Area extrusion operations is now recognized to be included on the EPA California List ban. The ban which was effective July 8, 1987 affects only leaded wastes generated after this date which limits the storage period prior to treatment and disposal to one year. Tin-oil is now being used as a lubricant in the M Area extrusion processes. The use of a substitute lubricant, molybdenum sulfide, is being investigated. Also under investigation is a treatment method that would separate the lead and oil by centrifugation. The oil could then be burned for heat recovery and the lead sold to a salvage vendor.

This is an FY91 capital project with an estimated cost of \$400,000.

●**SRL - Interim Waste Technology Section (IWTS).** IWTS has a program to reduce hazardous wastes by evaluating substitute process and developing alternative, nonhazardous materials for existing processes. The research evaluates and tests the new materials which are then proposed as substitutes to plant operating groups. The IWTS is also supporting the SRL Model Waste Program in an effort to establish SRL as a model waste handling facility. Milestones are as follows:

Identify alternate degreaser for M Area	12/89
Complete evaluation of solvent recycling by	06/89
Complete HP evaluation of alternate scintillation fluid	12/89

The total five-year cost is estimated to be \$2.6 million.

Process Optimization

●**Raw Materials**—The Raw Materials plans to decant the supernate from the M Area interim sludge storage and treat the decanted liquid in the M-Area liquid effluent treatment facility (LETf) to reduce the amount of hazardous waste that must be processed into saltstone.

The costs associated with the supernate processing are included as part of the LETf costs.

●**SRL - TNX**—TNX has instituted procedures to limit the purchases of hazardous materials used for research and development activities to

reduce and eliminate the large quantities of unused raw materials that must be stored and disposed as hazardous waste.

The costs associated with administering this program are minimal.

•**All Custodial Departments**—The site procedures have been revised to unpack and uncrate materials and equipment prior to moving the materials into a regulated area. This change has reduced the amount of low-level radioactive and suspect low-level radioactive waste that must be disposed in the Low-Level Waste Management Facility.

The costs associated with administering this program are minimal.

Segregation

•**Central Services Works Engineering (CSWE)**—CSWE provides separate collection dumpsters at waste generation points to segregate low-level radioactive wastes, nonhazardous wastes, glass and lumber, and inert construction rubble. This enables the site to treat these wastes properly in the most cost-effective manner.

A program has also been established to remove, clean, and send obsolete underground storage tanks offsite for resale as scrap metal.

The costs associated with waste segregation are part of the CSWE operating budget.

Waste Reuse and Recycling

•**Power Operations**—Power Operations burns waste oil from rolling stock crankcases, diesel generators and other sources for heat recovery in site powerhouse boilers.

The costs for this activity are included in the Power Operations and other custodial organization operating budgets.

•**Construction Management**—A study is underway to remove the associated solids from paint solvents, so that the solvents can be burned for their fuel value. A centrifugation technique with possible filtration is planned for this waste stream in order to remove lead and other solid contaminants.

The costs associated with this program are minimal.

•**SRL - Interim Waste Technology Section (IWTS)**—Coating and decontamination of lead to determine if lead shielding can be recycled on plant rather than being disposed as a mixed waste is being investigated. Promising coating/decontamination techniques will be tested in actual plant conditions to determine if any of the techniques are practical. Milestones are as follows:

Develop coating technology by	03/89
Install decontamination test facility	12/89

The total five-year cost is estimated to be \$

Detoxification Techniques

•**Waste Management**—The Beta/Gamma Incinerator had been used to burn radioactively contaminated canyon solvent and other contaminated solid incinerable wastes to reduce the volume of material that must be disposed in the Low-Level Waste Disposal Facility. Tritiated oil was also burned as supplemental fuel. Currently the facility is presently not operating. The Beta/Gamma Incinerator is discussed in Section 6.6.5.

The Consolidated Incineration Facility (CIF) will be built to detoxify and volume reduce mixed and hazardous wastes. The CIF will also reduce the volume of low-level wastes prior to disposal. This \$49 million facility will be available in FY92. Additional CIF cost information is in Section 6.6.5.

Deisting and Reclassification

•**Waste Management**—Waste Management has implemented a major reclassification program to reduce solid waste currently going to the Low-Level Waste Disposal Facility. This has been accomplished by the separation of solid radioactive waste from clean waste generated in regulated areas. This allows disposal of the clean waste in the sanitary landfill reserving the remaining available Low-Level Waste Disposal Facility space for radioactive waste. A Landfill Monitoring Facility, using highly sensitive equipment, certifies that the clean waste is not

radioactively contaminated prior to disposal in the Sanitary Landfill. The annual cost for operating this facility is \$200,000.

●**Raw Materials**—The Raw Materials Department is planning to delist the sludge generated from the M Area Liquid Effluent Treatment Facility (LETf). The sludge is a listed mixed hazardous waste because the waste treated by the LETf originates from an electroplating line in the fuel fabrication process. The sludge is currently stored as a hazardous waste and if not delisted will have to be treated in a RCRA permitted hazardous waste facility prior to disposal. The regulatory agencies will soon be petitioned to delist the sludge to allow disposal as a nonhazardous waste.

Raw Materials generates lithium/aluminum dross generated in the fuel fabrication process. The dross, which consists of the oxides that form at the surface of molten aluminum during the induction melting and alloying with lithium metal, has been determined to be nonhazardous per independent testing results.

The costs associated with the delisting activities is included as part of the Raw Materials operating budget. The SCDHEC has recently concurred with this assessment.

Awareness and Training

●**Environmental Protection Section (EPS)**—Waste minimization awareness and training will be developed under the Pollution Prevention Awareness Program as required by DOE Order 5400.1. This program will promote employee leadership and participation in site waste minimization activities (see Section 11.6.1), and will include employee training incentives and awards.

●**Waste Management**—Waste Management recently conducted a sitewide awareness and training program to extend the useful life of the existing Low-Level Waste Disposal Facility. The program educated employees on the importance of placing only low level waste in the B-25 disposal boxes. Generating departments were requested to implement procedures to ensure the B-25 boxes were completely filled prior to shipment to the disposal facility.

The costs associated with the administration of this program are included in the Waste Management operating budget.

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.6.7 Waste Site Closure/Remedial Actions

6.6.7.1 Sitewide Program Overview

The Savannah River Site (SRS) Waste Site Closure and Environmental Restoration Program provides a consistent strategy for compliance with applicable federal and state regulations, Department of Energy (DOE) orders, and operating contractor policies related to waste site closure, groundwater protection and remedial activities. A total of 202 active and inactive waste sites have been identified at the SRS. A waste site may be listed under more than one program due to overlapping regulatory jurisdiction. At this time, there are 14 Resource Conservation and Recovery Act (RCRA), 65 RCRA Facility Investigation (RFI) sites, 11 potential RFI sites, and 66 potential Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) sites. Eighty-seven sites are regulated under the South Carolina Solid Waste Regulations. The RCRA sites are included in the SRS RCRA Part A and Part B permit program, and written closure plans for each site have been or are being developed. Preliminary Assessments were submitted for the 66 potential CERCLA sites. The procedures established in the Waste Site Closure Manual are applied to the closure of all waste sites, both hazardous and nonhazardous. The majority of the SRS waste sites are scheduled for closure by the mid-1990s.

Over \$285 million will be required over the five-year planning period. Manpower requirements are included in the site closure and remedial action cost estimates.

6.6.7.2 Regulatory Requirements

The basic framework for assessing all waste sites and developing closure, post-closure, and remedial action plans is based on the hazardous waste requirements of the Resource Conservation and Recovery Act (RCRA), Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) as amended, South Carolina Solid Waste Regulations (nonhazardous sites), and South Carolina Hazardous Waste Management Regulation (SCHWMR). Closure and remedial activities are also regulated

by the DOE. The RCRA has been the primary regulatory driver at the SRS. A large number of waste sites will either undergo RCRA closures or are in the RFI Program. However, the SRS is currently in the process of negotiating an Interagency Agreement (IAG) with the State and Environmental Protection Agency (EPA) Region IV. It is expected that the agreement will be finalized by the end of the fiscal year. As a result of this agreement, many of the waste sites will be regulated under the CERCLA. However, it is important to note that it is still unclear how RCRA/CERCLA activities will be integrated. A summary of applicable state and federal regulations and DOE orders is provided in the Waste Site Closure Manual, DPSPM-GEN-57.

Federal Requirements

•**Resource Conservation and Recovery Act (RCRA)**—The State of South Carolina is authorized by the EPA to administer the RCRA. Permitting under RCRA is a two part process. The first part involves the submittal of a Part A Permit application that contains certain basic facility information. A Part A application was filed with the EPA for the SRS that addresses the F and H Area Seepage Basins, the M Area Settling Basin and Lost Lake, and the Mixed Waste Management Facility. The second part involves the submittal of a Part B Permit application that contains detailed information about the individual interim-status waste-management units, including closure activities. The Site Part B Permit application was filed in February 1985 and has been revised to incorporate additional facilities. The permit was issued in September 1987.

•**CERCLA/Superfund Amendments and Reauthorization Act (SARA) (Superfund)**—CERCLA is administered by EPA. According to Section 107(g) of CERCLA, agencies of the federal government are procedurally and substantively subject to compliance with CERCLA. This provision mandates the DOE to undertake remedial actions for CERCLA-equivalent sites at all DOE facilities once that facility is listed on the National Priorities List (NPL). Preliminary Assessments have been submitted to the EPA for 66 potential CERCLA sites.

DOE Orders

The Waste Site Closure Environmental Restoration program meets the Waste Closure and Groundwater Remedial Actions objectives set forth in Section 6.4.

•**DOE Order 5480.14**—This order establishes instructions for implementing the DOE CERCLA program, and defines actions to identify and evaluate inactive hazardous waste sites at DOE installations, and directs the custodian to take remedial action where necessary to improve control of hazardous substance migration from such sites. (This order is currently being revised.)

•**DOE Order 5480.2**—This order establishes hazardous waste management procedures for facilities operated under the authority of the Atomic Energy Act, and provides instruction for implementing the RCRA, to the extent practicable.

State Requirements

•**R.61-61**—Solid Waste Regulation

•**R.61.66**—Industrial Solid Waste Disposal Site Regulation

•**R.61-70**—South Carolina Landfill Regulation

•**R.61-71**—Well Standards and Regulations

•**R.61-79.264**—Hazardous Waste Management (SCHWMP) Regulation

6.6.7.3 Organizational Responsibilities***Waste Site Remediation Task Force***

A Waste Site Remediation Task Force (WSRTF) was established in January 1984 to assist SRS waste site custodians in developing closure plans and carrying out cleanup projects. The WSRTF objectives include developing closure criteria, advising custodians on closure plans and environmental documentation, achieving consistency in approach, and providing coordination of overall site cleanup activities (DPSPM-GEN-57). The implementing arm of the WSRTF is the seven-member executive committee, chaired by the Manager of the Waste Site Group, and includes

the SRS WSRTF Coordinator and representatives from The Savannah River Laboratory (SRL) and Environmental Protection Section (EPS). This committee reviews and approves the waste site closure plans prior to submittal to the DOE or regulatory agencies.

Environmental Protection Section (EPS)

The EPS is the lead organization responsible for overall coordination of the waste site closure and environmental restoration program. The EPS is responsible for ensuring that all waste site custodians are aware of and in compliance with the appropriate requirements, and interfaces with the DOE and South Carolina Department of Health and Environmental Control (SCDHEC) on topics associated with the RCRA, CERCLA/SARA, and SCHWMR. The SRS WSRTF Coordinator maintains a full-time point-of-contact to centralize and coordinate waste site closure activities.

Custodial Organizations

The custodial organizations are responsible for the identification, characterization, assessment, closure, and groundwater remediation, if necessary, of each of their waste sites. This includes performing and documenting all activities necessary for waste site closure. Each organization must acquire the funding for closure activities and provide oversight for the work performed by contractors. The custodial organizations for each waste site are shown in Table 6.6.7.1.

Savannah River Laboratory (SRL)

The SRL assists the EPS and the custodial organizations with the technical aspects of waste site closure, and remediation. The SRL develops the technical data necessary to design closure plans for solid waste sites. This includes mathematical modeling, laboratory and field experimentation, site characterization, and performance assessments as required for closure.

6.6.7.4 Closure/Environmental Restoration Strategy

The SRS waste site closure and environmental restoration program is designed to comply with all applicable regulations to minimize or mitigate effects on the environment to the extent possible. Currently there are 202 active and inactive nonhazardous-nonradioactive, hazardous, low-level radioactive, and hazardous-radioactive waste sites that may require some degree of closure activity. Material disposed at these sites has not contaminated offsite groundwater supplies. The 15 RCRA sites are the

priority sites for closure. *The Waste Site Closure Manual* (Du Pont, 1986c) establishes procedures to be followed throughout the various phases of closure.

The Waste Site Closure Manual (Du Pont, 1986c) devotes a section to each of the major phases of closure establishing the basic procedures to be used. A flowchart depicting the major phases of closure is shown in Figure 6.6.7-1. A short description of the major phases are:

- Characterization**—A determination through document review, first hand knowledge, and/or preliminary soil/groundwater analyses, of the waste (contamination) located at the site. The result of this phase should dictate what, if any, action should be taken to further define the impact of the waste deposited at the site.

- Site Assessment**—An evaluation of all information gathered during the initial and extended characterization. The result of this phase should include a confirmation of the applicable regulatory status, environmental impacts and a proposal for necessary closure action.

- Closure Plan**—A detailed plan describing every action to be taken to decontaminate and/or close the waste site. The result of this phase should mitigate current, or prevent future, adverse environmental impacts on the soil, surface water, and groundwater surrounding the waste site to the extent economically and technically feasible.

- Closure**—The implementation of the above described closure plan.

- Remedial Action**—An action taken in addition to closure to prevent contaminant migration that could prove harmful to human health or the environment.

The SRS strategy for waste site closure and remedial groundwater actions is to: (1) meet regulatory requirements; (2) address sites close to the boundary; and (3) address the remaining sites according to the type of waste disposed at the site.

Closure options for the waste sites are varied and will be determined on a site specific basis. Options for remediation include waste stabilization, site capping, waste removal, and grading. No action may be required at some waste sites, in which case, documentation supporting this option will be provided in a report. Based on preliminary analyses presented in the Environmental Impact Statement (EIS), *Waste Management Activities for Groundwater Protection at the Savannah River Plant*, DOE/EIS-0120D

(DOE 1987b), the current plans propose waste removal at the old F Area seepage basin and the six R Area seepage basins. Closure for most other waste sites would entail the waste being left in place with closure techniques, such as capping, applied. The final closure strategy for all waste sites will, however, depend on the information developed during characterization and assessment.

Groundwater remedial actions will be performed as needed to conform to groundwater protection requirements resulting from negotiated agreements with regulatory agencies. Corrective actions are complex and depend on many variables, which are often site-specific. Remedial actions include *in situ* treatment, groundwater pumping and treatment, and containment or diversion. An effective design often combines two or more actions. The removal of chlorocarbons from the shallow groundwater and vadose zone in M Area is currently the only groundwater remedial action underway at SRS.

6.6.7.5 RCRA Part B/RFI Activities

There are 14 waste sites that are currently subject to RCRA permitting and compliance action by the SCDHEC under the authorized state hazardous waste program.

The SRS RCRA Part B permit identifies 65 sites for which RCRA Facility Investigations (RFIs) are required. The more detailed assessments necessary for these 65 sites will determine the nature, extent and potential pathways of contaminant releases to the air, land, surface water and groundwater. Eleven sites are also potential candidates for the RFI program.

In FY88 the Manager of the Waste Site Group established a RFI Program Team to ensure timely completion of the RFI program mandated by the RCRA Part B Permit.

6.6.7.6 Programs

Sitewide Activities

Waste site closure activities include many steps as described in Section 6.6.7.4, such as characterization, assessment, closure plan development, site closure, and remedial activities.

The following is an overview of the sitewide closure activities. In this same section the departmental closure activities and their allocated resources will be outlined.

•**Waste Site Investigation and Remediation Manual**—The SRS WSRTF Coordinator is responsible for updating the Waste Site Closure Manual as new specifications and requirements are set forth.

•**Characterization**—Characterization of SRS waste sites includes the various data gathering activities necessary to determine the rate and extent of contaminant migration resulting from the waste site, if applicable, and the concentration of any contaminants that may be present. Characterization addresses:

- The compilation of all available data
- Identification of data gaps
- Gathering of additional information through soil-gas and soil boring analyses, preliminary well drilling, and groundwater analyses.

Characterization details are provided in the Waste Site Closure Manual, with an outline of what a characterization plan and final report should include. DPSOP 254, *Hydrogeologic Data Collection Methods, Procedures and Specifications* (Du Pont 1987) establishes the accepted procedural methods for the various characterization activities, such as monitoring well installation and sample analysis procedures.

•**Assessment**—All SRS waste sites are assessed as follows:

- Compile and interpret the data collected during the characterization phase
- Identify applicable regulations
- Discuss closure alternatives.

Site specific assessments include:

- The properties of the known contaminants, if any
- The sources
- The rate and extent of contamination
- The groundwater flow directions and elevations.

Based on this information a closure option is recommended.

Guidance for completing a waste site assessment is given in the *Waste Site Closure Manual* (Du Pont, 1986c), along with an outline of what a site assessment final report should include.

The assessment of all SRS waste sites is scheduled for completion by 1993.

•**Site Closure Criteria**—Procedures and criteria for characterizing, remediating and closing of the inactive waste sites are set by applicable federal and state regulations and DOE orders. There is a minimum amount of information that must be developed for each site. A different level of activity is required at each waste site due to the type of waste deposited and the requirements of different regulations. The definition of the site-specific closure criteria is developed during the characterization and assessment phases of closure for each site.

•**Closure Plan Development and Approval**—The closure plans for all SRS waste sites will be developed to minimize or eliminate the postclosure migration of wastes, and to keep future maintenance at a minimum. Closure plans address:

- Closure performance standards
- A detailed waste inventory
- Waste removal, treatment, and disposal requirements
- Sampling and analyses needs
- Backfill requirements
- Cover systems
- Equipment decontamination
- Surface water controls
- Closure schedules
- Closure costs.

Guidance for the completion of a waste site closure plan is provided in the *Waste Site Closure Manual*.

The development and approval of all SRS closure plans is expected to be completed by 1995.

•**Postclosure/Remedial Action Plan Development**—An integral part of each waste site closure plan is the postclosure maintenance and monitoring activities to assure integrity and security of the closed waste site. Postclosure plans include:

-
- Inspection checklist
 - Inspection frequency
 - Facility custodian
 - Monitoring and compliance (if necessary)
 - Postclosure costs.

Remedial action plans are required if residual contamination remains in the closed site and the characterization analysis requires it. Remedial action plans include:

- Predetermined groundwater protection standard
- Hazardous constituents present
- Compliance point and duration of monitoring requirements
- Remedial action and monitoring program.

Guidance on how to prepare postclosure plans and/or remedial action plans is provided in the *Waste Site Closure Manual* (Du Pont, 1986c) along with an outline of what a site postclosure/remedial action plan should include. Postclosure/remedial action plans for specific waste sites must be reviewed and approved by the appropriate regulatory agencies.

The development and approval of all required postclosure/remedial action plans, is scheduled to be completed in the mid-1990s as part of each Waste Site Closure Plan.

•**Closure**—The major portion of work outlined in the closure plan will be performed by contractors. The waste site custodian is responsible for managing the contractor(s) and ensuring that the contractor is following the approved closure plan.

The closure of all SRS waste sites is expected to be completed by the mid-1990s.

•**Postclosure Activities/Remedial Action**—The waste site custodians are responsible for ensuring the implementation of the activities specified in the approved Postclosure/Remedial Action Plan. Postclosure inspection, maintenance and monitoring may be required following closure in order to assure the integrity and security of the closed waste site. The effectiveness of any required remedial actions is verified through postclosure monitoring. The scope of these activities will vary from site to site depending on the type and amount of waste, waste residue, or residual contamination remaining in place following site closure.

The following sections present Organizational Activities and Waste Area Group (WAG). The Organizational Activities section presents waste site summaries for each SRS organization and remediation activities are presented in the WAG Section. WAGs are programmatic groups of tasks and waste units in the Environmental Restoration Program.

Organizational Activities

•Central Services Works Engineering (CSWE)

CSWE has 60 inactive waste sites. Twelve are burning/rubble pits, three are seepage basins, and there are numerous rubble piles or pits. Twenty-four inactive waste sites are in the RFI program.

The closure scheme for these waste sites may combine some aspects of: waste removal, waste capping, waste stabilization, grading or abandonment. Closure options will be determined on a site specific basis. All closure activities for the remaining CSWE sites should be completed by the mid 1990s.

CSWE has two active waste sites which are erosion control sites regulated by South Carolina solid waste regulations. A total of eleven sites have been closed.

•Construction Management

Construction Management has seven active waste sites; six are erosion control sites regulated by South Carolina solid waste regulations and one site (scrap lumber pit) is a potential CERCLA site.

•Environmental Protection Section (EPS)

The EPS program has responsibility for coordinating the sitewide waste site closure program and RFI activities.

If the site enters into a CERCLA Interagency Agreement (IAG), the Savannah River Operations Office may be required to reimburse the SCDHEC for its involvement in CERCLA activities. The Savannah River Operations Office may also be required by the regulators to support studies conducted at the SRS by the Agency for Toxic Substances and Disease Registry (ATSDR). The Interagency Agreement is still in the draft stages. The final form may be complete by the end of this fiscal year.

•Power Operations

Power Operations has 21 inactive waste sites. Six sites are basins which have received acidic or caustic waste associated with generation of steam and electricity, one basin is an overflow in the event of an underground storage tank rupture and one lagoon was used to retrieve sanitary plant sludge. Twelve of the inactive sites are currently involved in the SRS RFI program.

Four of the six Acid/Caustic Basins are RCRA sites requiring closure activities to be developed in accordance with SCDHEC regulations. The current closure options include minor excavation, placement of clean fill and capping of the facility. A clean closure option is being pursued which will eliminate the need for post closure monitoring. The closure activities are expected to be completed during 1990.

The closure scheme for the remainder of the waste sites may combine some aspects of waste removal, waste capping, waste stabilization, grading or abandonment. Closure options will be determined on a site specific basis. All closure activities for the remaining Power sites should be completed by the mid 1990s.

Power has 14 active waste sites; one is a potential CERCLA site, five are RFI sites, and the remainder are regulated by South Carolina solid waste regulations. The sites include ash piles and basins, coal pile runoff basins, rubble piles, and sewage sludge disposal areas.

•Raw Materials

Raw Materials Engineering and Technology Department has five inactive waste sites. These include the M Area Hazardous Waste Management Facility (a basin, sewer line, overflow ditch, seepage area, and a natural depression known as Lost Lake), two chemicals basins, and a metals burning pit.

The M Area Hazardous Waste Management Facility (HWMF) includes the M Area settling basin, process sewer line, basin overflow ditch, seepage area and Lost Lake. The HWMF is undergoing closure in accordance with the RCRA, SCHWMR, and an approved closure plan. To date the closure is 80 percent complete. The basin liquid and sludge have been removed. The liquid was treated through a permitted temporary waste water facility, and released to a permitted NPDES discharge point upstream of the A-014 Outfall. The sludge was removed from the basin, dewatered, mixed with cement, and placed back in the basin. All contaminated soils from the

excavated areas (sewer line, overflow ditch, seepage area and Lost Lake) are being placed in the basin. The facility will be RCRA capped and post closure monitoring will be initiated. The closure activities are expected to be completed during 1989.

The closure scheme for the remainder of the waste sites will combine some aspects of: waste removal, waste capping, waste stabilization, grading or abandonment. Closure options will be determined on a site specific basis as a part of the RFI. All closure activities for the remaining Raw Materials sites should be completed by the mid 1990s.

Raw Materials Engineering and Technology is also responsible for the A/M Area Groundwater Remediation Program. The remediation activities are expected to continue through the 1990s. A description of the A/M Area Groundwater Remediation Program is provided in Section 6.3, Existing Conditions.

•Reactors

The Reactors Department has 16 inactive waste sites. Nine are seepage basins and seven are Bingham pump outage pits which received construction debris. These sites are scheduled for closure under CERCLA; remediation will begin in FY92 after completion of the Remedial Investigation/Feasibility Study (RI/FS).

The closure scheme for these waste sites may combine some aspects of: waste removal, waste capping, waste stabilization, grading or abandonment.

Reactors has eight active waste sites which include a containment basin and seven seepage basins. These sites are CERCLA sites.

•Separations

The Separations Department has two inactive waste sites. The closure schemes for the old F Area seepage basin and F Area seepage basin and F Area clay boards may combine some aspects of waste removal, waste capping, waste stabilization, grading or abandonment. All closure activities for these sites should be completed by the mid 1990s.

•Fire Department

Fire Department has one inactive seepage basin. The closure scheme for this waste site may combine some aspects of waste removal, waste capping, waste stabilization, grading or abandonment.

•Savannah River Laboratory

The SRL Seepage Basins (four) are being closed under the Natural Resources Defense Council (NRDC) Consent Decree. The closure

scheme for these basins may combine some aspects of backfilling, waste site capping and erosion control.

TNX has four inactive sites. They are the Old TNX Seepage Basin, the new TNX Seepage Basin, the TNX burying ground and the TNX rubble pile. The Old TNX Seepage Basin is being closed under the RFI/CERCLA program. The New TNX Seepage Basin is being closed under the NRDC Consent Decree. The closure schemes may combine some aspects of waste removal, waste capping, waste stabilization, grading or abandonment. Closure options will be determined on a site specific basis.

The SRL has nine additional waste sites; five have been closed in accordance with the South Carolina solid waste regulations and four are inactive sites subject to RCRA or South Carolina requirements.

•Waste Management

The Waste Management Department is custodian for 23 inactive waste sites. Seven of these waste sites are the F and H Seepage Basins. Four of the sites are Burning Rubble Pits near the Central Shops area. Also included are Rubble pits in near L Area (1) and at Burma Road (1). The remaining inactive waste sites are the Mixed Waste Management Facility (1), the Old Radioactive Waste Burial Ground (1), the CMP pits (7), and the Silverton Road Waste Site (1).

The F and H Seepage Basins consist of six RCRA regulated basins and one non-RCRA basin. Closure activities for all seven of the basins are being developed in accordance with SCDHEC regulations. The current closure options include basin dewatering, sludge stabilization, backfilling, capping with a RCRA type cap, and post closure monitoring. The closure activities are expected to be complete by the mid 1990s. A corrective action program is being developed for the seepage basins to remediate groundwater contamination.

The Mixed Waste Management Facility (MWMF) is a RCRA/SCHWMR unit being closed in accordance with a closure plan approved in December 1987. Closure activities are underway. The first major work element to be accomplished is the process of Dynamic Compaction of selected portions of this 58 acre waste site. The Dynamic Compaction process is 25 percent complete. Following this first major element will be backfilling to contour design grades, installing a RCRA type cap and post closure groundwater monitoring.

The chemical, metal, and pesticide (CMP) pits consist of seven trenches which have been excavated, backfilled, capped, and are being monitored for groundwater contamination.

The closure plans for the remainder of the inactive waste sites will include some aspect of waste removal, waste capping, waste stabilization, grading or abandonment. Closure options will be determined on a site specific basis utilizing information formulated by the RCRA Facility Investigation for these sites.

Waste Management operates three active waste sites: the Active Radioactive Waste Burial Ground, Sanitary Landfill, and the F Area Scrap Lumber Pile. Closure details for the burial ground and landfill for these sites will largely depend on information gathered through the RCRA Facility Investigation of these sites.

Waste Management is also responsible for the decommissioning of Tank 16 and numerous solvent tanks in the Old Radioactive Waste Burial Ground. These closure activities are expected to be complete by the early 1990s.

Waste sites under Waste Management custodianship involved in the RFI program include both the Active and Old Radioactive Waste Burial Grounds, Tank 16, the CMP pits, Sanitary Landfill, and all WM burning rubble and rubble pits. This program will characterize and assess the extent (if any) of any hazardous waste migration at these sites.

Waste Area Groups (WAGs)

•M Area Settling Basin/Lost Lake

The M Area Settling Basin/Lost Lake is in the northwest portion of the SRS. The basin received electroplating waste from the M Area operations. A RCRA Part B Permit was issued by the SCDHEC. Closure of the basin has

been initiated and is approximately 80 percent complete. Closure of the M Area Basin/Lost Lake is expected to be complete by the end of FY89.

The total five-year cost is estimated to be \$3.7 million.

•A/M Area Groundwater Remediation

The groundwater under the A/M Area is being pumped through an air Stripper to remove halogenated hydrocarbons to a residual concentration acceptable to the SCDHEC. This remediation program is now in its fourth year and it is currently estimated that the program will continue through the year 2017. An average of 15-17 million gallons of water are treated per month. Plans to increase the rate of flow to the air stripper are being implemented. It is anticipated that the flow to the air stripper will increase by 50 percent.

A separate area of groundwater contamination has been identified under the SRL. The first step toward implementing a remedial action program in this northern sector of the A/M Area is the relocation of a prototype air stripper from the Raw Materials Engineering Technology Department.

A groundwater remediation system will also be installed in the southern sector of the A/M Area. The plan includes installing recovery wells and stripper units.

This task also includes the vadose zone project. The objective of this task is to remove the residual contaminate from the vadose zone before it reaches the groundwater.

The total five-year cost is estimated to be \$6.8 million.

•Met Lab Basin Closure

The Met Lab Basin received wastewater effluent from the Metallurgical Laboratory. The waste generally consists of degreasing, cleaning and etching compounds. The basin is being closed in accordance with consent decree resulting from the NRDC settlement. Current proposed closure consists of removal and treatment of basin water followed by backfill and capping of the basin. Plans for the characterization of both the influent piping and the Carolina Bay associated with the basin discharge are being developed. A closure plan has been prepared and will be submitted to SCDHEC by June 30, 1989.

The total five-year cost is estimated to be \$4 million.

•Acid/Caustic Basin Closure

The Acid/Caustic Basins at F, H, K, and P Areas were the subject of a lawsuit filed against the DOE by the NRDC. A formal closure plan has been prepared which includes an assessment plan for the underground process sewer lines which fed the four basins. This plan will be submitted to the appropriate control agencies in FY89 for review and approval. The four Acid/Caustic Basins should be closed in FY90. Additional funds have been allocated for FY91 through FY94 to address any remediation work that may be required at the underground process sewer lines.

The total five-year cost is estimated to be \$2.9 million.

•Mixed Waste Management Facility Closure

Closure of the Mixed Waste Management Facility (MWMF) consists of compacting and capping a 58 acre section of the Radioactive Waste Burial Ground (RWBG) as required by the RCRA. The unit has both hazardous and radioactive waste buried in it. The first phase of construction, clay cap and dynamic compaction tests, began in October 1987 and March 1988 respectively. Dynamic compaction began in February 1989. The project is presently estimated to be ten percent complete.

The total five-year cost is estimated to be \$45 million.

•RFI Program Investigations

The RFI Program was developed to provide a framework for the completion of the RCRA facilities investigation and is mandated by the RCRA Part B permit. The SRS RFI Program provides the basis for the development of site-specific RFI Work Plans for the units currently in the program. This will provide determination of the extent of contamination in relation to background levels indicative to each RFI unit. At the Site Investigation Phase, a detailed soils assessment is made and can include studies of the surface water, groundwater and ambient air. Upon completion of the investigation, a RFI report will be submitted to the control agencies and a choice for corrective action will be determined. For the purposes of budgeting, the costs through Fiscal Year 1991 include the RFI investigations. A separate Waste Area Grouping was established to reflect the costs associated with corrective actions for the units in the RFI Program.

The total five-year cost is estimated to be \$32 million.

•Environmental (ER) Program Support

Support is required to satisfy DOE management requirements of the ER Program. The objectives are to assure adequate program documentation and submission of required reports. It is necessary to secure the support of consultants in the implementation and continuation of this program to ensure achievement of the objectives.

The total five-year cost is estimated to be 3.9 million.

•Trichloroethylene (TCE) Biodegradation Demonstration

A number of waste sites at the SRS and across the U.S. are known to have contaminated the groundwater with volatile organic compounds, such as trichloroethylene. The TCE Biodegradation Demonstration provides direct application of biotechnology for remediation of wastes and waste sites at the SRS. *In-situ* bioremediation is recognized as an acceptable RCRA cleanup technique and offers the potential to save millions of dollars in closure activities at waste sites. It can also be used to cleanup petroleum spills and to reduce the volume of waste materials. The first portion of the project involves design of an above-ground bioreactor to remediate trichloroethylene-contaminated groundwater. A micro-organism that degrades trichloroethylene has been discovered and a patent has been submitted. This micro-organism will be utilized during the design of the bioreactor. A successful demonstration is highly likely because of successful laboratory tests already conducted.

The total five-year cost is estimated to be 3.8 million.

•SRL Seepage Basin Closure

The SRL Seepage Basins are located in the northwestern section of the SRS in the 700 Area. The basins received low-level radioactive wastewater from the Savannah River Lab. These basins are being closed in a RCRA-like manner per a consent decree resulting from the NRDC settlement. The current proposed closure method consists of stabilization of basin liquids followed by backfill and capping of the basin. A program for characterization of the influent piping is being developed. A feasibility study of several closure options has been prepared in the Waste Management EIS.

The total five-year cost is estimated to be \$3.1 million.

•New TNX Seepage Basin Closure

The new TNX Seepage Basin received neutralized waste from TNX Pilot Scale Testing Programs. The objective is to close the basin in a RCRA-like fashion per a consent decree resulting from the NRDC settlement. The proposed method for closure consists of removal and treatment of basin liquids followed by backfill and capping of the basin. A program for the characterization of the influent piping is being developed. A feasibility study of several closure options has been prepared in the Waste Management EIS.

The total five-year cost is estimated to be \$2.9 million.

•Solvent Tank Decommissioning

There are 22 underground storage tanks which have been used for the storage of spent canyon solvent. The tanks are located within the Old Radioactive Burial Ground (RWBG). The tanks have been emptied of all but the unpumpable heel. This heel is known to be radioactive. Therefore, these tanks must be decommissioned before the Old RWBG can be restored. This has to be done as an interim measure at an RFI Unit because the Old RWBG is the RFI Program under RCRA.

The total five-year cost is estimated to be \$2.7 million.

•RI/FS (CERCLA) Investigation

The Savannah River Operations Office (DOE-SR) is currently in the process of negotiating an Interagency Agreement with USEPA Region IV and the SCDHEC. The SRS may then be required to conduct Remedial Investigations and Feasibility Studies (RI/FS) at some waste sites.

CERCLA Section 120 requires federal facilities placed on the National Priority List (NPL) to enter into an Interagency Agreement. The SRS has not been proposed for inclusion to the NPL. The EPA has indicated, however, that the SRS will likely be proposed for inclusion within the year. The DOE-SR and EPA agree it is beneficial for the site to enter into the agreement voluntarily. Two informal meetings and one formal negotiation meeting have been held between the EPA, SCDHEC, and DOE-SR since November 7, 1988.

If the site enters into a CERCLA Interagency Agreement (IAG) the DOE-SR may be required to reimburse the SDHEC for its involvement in CERCLA activities.

The DOE-SR may also be required by the regulators, to support studies conducted at the SR by the Agency for Toxic Substances and Disease Registry (ATSDR).

The total five-year cost is estimated to be \$14 million.

•Underground Storage Tanks

This task covers the activities involved with the underground tank abandonment process and associated corrective action activities. The objective is to comply with the EPA and SCDHEC regulations. Tanks will be evaluated for leaks by means of inventory records, and if found to be leaking, remedial action will be taken for the tank, contaminated soil and/or groundwater. Inactive tanks will be removed and the necessary remedial action will be taken.

The total five-year cost is estimated to be \$2.1 million.

•Miscellaneous Waste Sites

The nonhazardous/nonradioactive waste units will be closed in accordance with the South Carolina Solid Waste Regulations. Newly discovered waste units will be placed in this WAG until the waste has been characterized and the unit assigned to a specific program such as the RFI Program.

The total five-year cost is estimated to be \$2.3 million.

•F/H Area Seepage Basin Closure

The F/H Area Seepage Basins received wastewater containing radionuclides and other chemicals from the F/H Separations Areas. Influent to the basins stopped in November 1988. The F/H Effluent Treatment Facility (ETF) was brought on line at that time and now treats the wastewater from the Separations Areas. Pre-closure activities at the basins, including clearing, grubbing, vegetation burning and materials staging, are underway. Current projections are that a Request for Proposal be used shortly and a contract for capping awarded before the end of 1989.

The total fix-year cost is estimated to be \$39 million.

•Inactive Reactor Seepage Basins Investigations (RI/FS)

The five reactor areas at the SRS use earthen seepage basins to dispose of low-level radioactive purge waters from the reactor disassembly basins. There are 14 reactor seepage basins sitewide of which seven (six in R Area and one in K Area) are inactive. The K Area Reactor Seepage Basin (Building Number 904-56G) has been open but inactive since 1960. R Area Reactor Seepage Basin 1 (Building No. 904-103G) was placed into service in June 1957. Basins 2 through 6 (Building Numbers 904-104G, -57G, -58G, -59G, -60G, respectively) were placed into service near the end of 1957. Basin 1 was backfilled in January 1958 and Basins 2 through 5 were deactivated and backfilled in 1960. The ground surface above the five basins was treated with herbicide and covered with asphalt. In addition, a kaolinite dike was constructed down to the clay layer around Basin 1 and the northwest end of Basin 3 to contain any lateral movement of radioactive contamination. Basin 6 was last used in 1964 and was backfilled in 1977.

The total five-year cost is estimated to be \$1.2 million.

•**Inactive Reactor Seepage Basins Remediation**

As noted above, the Reactor Seepage basins received low-level radioactive waste from the reactor disassembly basins. The basins may be addressed in the IAG. Therefore, this grouping was established to reflect the estimated CERCLA remediation costs for these basins. The total five-year cost is established to be \$28 million.

•**Bingham Pump Outage Pits Investigation (RI/FS)**

In 1957 and 1958 the SRS reactors underwent major modifications to their primary and secondary cooling water systems. The reactor shutdowns necessitated by these upgrade activities became known as the Bingham Pump Outages. Low-level radioactive refuse generated during pump outages at the K, L, P, and R reactors, was disposed of in pits excavated in each of the respective areas. Waste materials deposited include pipes, cables, ladders, drums, wooden boxes, and miscellaneous hardware. The radiation level these materials was <25 mRad/hr and 7.6 cm when buried, with no detectable alpha activity. A total of approximately one Ci of activity (primarily Cesium 137 and Strontium 90) is estimated to remain at the seven sites. Following construction activities, the outage pits were backfilled with clean soil, graded and seeded.

The total five-year cost is estimated to be \$1 million.

•RFI Program Corrective Actions

The RFI Program was developed to provide a framework for the completion of the RCRA facilities investigation and is mandated by the SRS RCRA Part B permit. Upon completion of the investigation, a RFI report will be submitted to the control agencies and a choice for corrective action determined. The units in the RFI Program follow a staggered schedule. In Fiscal Year 1992 some of the sites will begin corrective action while other sites in the program will be ending the investigation stage. However, by FY93, all of the sites in the RFI Program will be undergoing corrective action measures.

The total five-year cost is estimated to be \$38 million.

•Bingham Pump Outage Pits Remediation

The Bingham Pump Outage Pits received very low-level solid waste when modifications of cooling water systems at the reactors were made in 1957 and 1958. The waste included miscellaneous construction equipment such as pipes, cables, ladders, drums and boxes of hardware.

The DOE-SR is in the process of negotiating an Interagency Agreement with the state and EPA. The Bingham Pump Outage Pits may be addressed in the IAG. Therefore, this Waste Area Grouping was established to reflect estimated costs for CERCLA remediation of these outage pits.

The total five-year cost is estimated to be \$5 million.

•CERCLA Remediations

The DOE-SR is currently negotiating an Interagency Agreement with the EPA Region IV and SCDHEC. The SRS may be required to conduct RI/FS programs at some waste sites followed by remediation. This WAG is for CERCLA remediation activities. A schedule for addressing these sites will be provided in the agreement.

The total five-year cost is estimated to be \$18 million.

6.6.7.7 Research/Studies

Savannah River Laboratory

Subsurface environmental research at the SRS is primarily conducted by the Environmental Sciences Section (ESS) and Interim Waste Technology Section (IWTS) with field support from the plant technology and production departments.

The programs related to the subsurface can roughly be divided into the following four categories: waste constituent transport rate/mechanisms, engineered cleanup technologies, biotechnology, and geology/geohydrology. The overall objectives of the transport rate/mechanism studies are to define the rate of waste constituent migration (using field techniques such as soil gas surveys, groundwater analyses, and lysimeters, and lab studies such as column and batch sorption experiments) and to elucidate the mechanisms of transport. These activities will facilitate accurate modeling and help identify new treatment technologies. The overall objective of the engineered cleanup technology studies is to determine the applicability of emerging remediation technologies for waste constituents at the SRS. The overall objectives of the subsurface biotechnology program at SRS are to identify the number, type and characteristics of the microorganisms in the subsurface, and to determine the potential applicability of these organisms (or engineered organisms) to the remediation of waste constituents. The overall objective of the geology/geohydrology programs is to develop a fundamental understanding of the SRS strata (depositional environments, stratigraphy, seismic environment, etc.) and to develop new mathematical analysis methods to describe subsurface processes.

Total estimated costs for all studies are \$15 million for the five year planning period.

A listing of subsurface research programs follows:

Transport Rates and Mechanisms

<u>Title</u>	<u>Description</u>
Facilitated Transport Study	Evaluate the detailed mechanisms for waste transport through porous media using laboratory column studies, geochemical models and field studies. Initial results suggest that association of waste constituents

with mobile colloids and various ligands can play a significant role in the distribution of these materials. The feasibility of minimizing transport of waste constituents by modification of the geochemical environment will be evaluated.

SRS Waste Lysimeters

Provide technical support for improved management of shallow buried waste through the use of lysimeters. This project uses 42 lysimeters to test different SRS wastes, representing the type buried in the SRS burial ground from 1953 to 1984. These lysimeters were installed in the burial ground and sampled monthly to monitor the release and migration of radionuclides.

Tenth Scale Saltcrete Lysimeters

Evaluate economical shallow land disposal of low level waste by testing a 1982 formulation of nonradioactive saltstone. The lysimeter is sampled monthly to evaluate the retention of soluble constituents.

Groundwater Modeling

Provide technical support for site-specific groundwater modeling such as support of remedial action programs. Current projects involve modeling of: (1) the A/M Area groundwater remediation program, (2) the degradation of groundwater from coal piles, (3) the effects of air injection from a horizontal on groundwater flow paths; and (4) assessment of the effect of capping waste sites on groundwater flow.

Tank 24 Saltstone Lysimeters

Evaluate on a larger scale with actual waste. Three lysimeters sampled monthly to determine retention of soluble constituents.

Alpha Source Mini Lysimeters

Evaluate leaching from five chemical forms of plutonium and americium, and from alpha containing glass, ash and sludge. The 11 lysimeters are in the burial grounds and are sampled quarterly.

6.6.7 Waste Site Closure/Remedial Actions

Environmental Saltstone
Lysimeters

Measure radioactive releases from saltstone that are a potential path for transport to the surface by vegetation.

Special Waste Form

Evaluate five different types of commercial Lysimeters with nuclear power plant wastes. These ten lysimeters are located in the burial ground and are sampled monthly. The lysimeters allow the option of horizontal coring.

SRL Tree Plots

Determine uptake of radionuclides from a burial ground low-level alpha waste trench by vegetation.

TRU Waste Assessment

Review procedures for management of transuranic wastes at the SRS, including historical monitoring data, isotopes in the groundwater, and modeling projections on potential effects of the wastes in the biosphere.

Ground Penetrating Radar

Evaluate ground penetrating radar an assessment technique to locate buried objects at SRS waste sites.

Organic and Inorganic Coal Pile
Constituents

Collect and analyze groundwater data from the coal piles and coal pile runoff basins at the SRS. The objective is to protect groundwater through improved management and utilization strategies for coal piles.

Engineered Cleanup Technologies

Vacuum Recovery

Evaluate the feasibility of using vacuum technology to remediate organic solvents at SRS. A pilot study was performed with one extraction well and two pressure measurement wells. A tracer test to measure transport velocities at the pilot location is planned. Ultimately, the program will combine vacuum extraction with injection of gases in the saturated zone (*in-situ* air stripping).

Air Stripping

Evaluate effectiveness of an *in-situ* air stripper to remove organics from the groundwater. The *in-situ* air stripping will be tested in combination with vacuum extraction in the vadose zone. The test will be performed in horizontal wells. Modeling of the field tests will be undertaken.

Waste Disposal Cover

Develop new technologies for closing waste disposal facilities. Currently, this involves development of new materials and implementation techniques for geomembranes, currently required for closure of waste sites.

***In-Situ* Vitrification**

Assess feasibility and cost effectiveness of applying *in-situ* vitrification (ISV) technology to closure of selected waste sites at the SRS. A test program using SRS soil is scheduled to begin at the Pacific Northwest Laboratories about mid-1989 and is expected to lead to a full scale demonstration of ISV at an existing SRS waste site in FY92.

Biotechnology**Biotechnology at the SRS**

From a basic understanding of biotechnology, develop applications related to product recovery, waste disposal, and process replacement. Product recovery and process replacement are in the early development stage. Evaluation of waste disposal applications and *in-situ* biological degradation are research endeavors for which the SRL is the lead laboratory in the DOE for technology development. An above ground bioreactor to remediate contaminated groundwater and a study of a potential *in-situ* biodegradation site are the first two proposed applied biotechnology projects.

Microbiology of the Deep Subsurface

Determine the presence and activity of microorganisms with depth (down to the bedrock) and use that information to assist in understanding the basic science associated

with this system. Many types of organisms (aerobic, anaerobic, protozoa, viruses) have been found to date and many unusual characteristics have been identified. Most of the organisms are new to science (i.e., they have never been previously isolated).

Biobarriers for Sites

Field test a system of an encapsulated slow release herbicide bonded to a geo-fabric. When the system is placed below the soil zone, over a closed waste facility, the system is designed to eliminate root penetration for >100 years.

Waste Site Microorganisms

Determine type, density, and activity of microorganisms in waste sites, and develop bioremediation and biorestitution techniques for returning the sites to pristine conditions.

Environmental Radionuclide Assessment

The Environmental Technology and Environmental Sciences Sections have initiated a long-term study to assess the status of radionuclides released from in-stream, wetland and terrestrial areas on and near the SRS. The studies are a joint effort with Environmental Monitoring and Environmental Protection Sections and are oriented toward evaluating the long-term risks associated with radionuclides released by aquatic and atmospheric pathways, and deposited beyond SRS facility boundaries.

Waste Site Remediation Studies

The Environmental Sciences Section has initiated projects in conjunction with Interim Waste Technology Section and plant custodial organizations to examine the biological effects of historical waste disposal practices. These studies are oriented toward determining what, if any, biological effects are detectable, and developing methodologies for remediation of effects to above ground biological communities.

M905094

Figure 6.6.7-1. Waste Site Closure Pathway

M710833

Figure 6.6.7-2. Waste Site Closures with RCRA Facility Investigations (RFI)

Table 6.6.7.1. Organizational Responsibility Summary Table

<u>Organization</u>	<u>Site Description</u>
CSWE	RUBBLE PITS/PILES (37) HYDROFLUORIC ACID SPILL AREA (1) FORD BUILDING WASTE SITE (1) BURNING/RUBBLE PITS (12) D AREA WASTE OIL BASIN (1) 716-A MOTOR SHOP SEEPAGE BASIN (1) G AREA OIL SEEPAGE BASIN (1) EROSION CONTROL SITE (3) GAS CYLINDER DISPOSAL FACILITY (1) ASBESTOS DISPOSAL FACILITIES (2) OPEN METAL PILE (1) SCRAP METAL PIT (1) MISCELLANEOUS SITES (9)
CONSTRUCTION MANAGEMENT	ACTIVE & INACTIVE EROSION CONTROL SITES (6) CS SCRAP LUMBER PIT(1)
POWER OPERATIONS	F, H, P, K ACID-CAUSTIC BASINS (4) L & R ACID CAUSTIC BASINS (2) ACTIVE & INACTIVE ASH BASINS/PILE (15) ACTIVE & INACTIVE COAL PILE RUNOFF BASINS (7) EARTHEN OIL BASINS (2) SANITARY SEWAGE SLUDGE LAND APPLICATION (1) SANITARY SEWAGE SLUDGE PIT SANITARY TREATMENT PLANT RUBBLE (1) IMHOFF TANK (RUBBLE PILE (1) BARROW PITS (2)
RAW MATERIALS	M AREA SETTLING BASIN (1) LOST LAKE (1) MISCELLANEOUS CHEMICAL BASIN (1) METALS BURNING PIT (1) ROAD A CHEMICAL BASIN (1)
REACTOR	FORD BUILDING SEEPAGE BASIN (1) L AREA OIL & CHEMICAL BASIN (1) ACTIVE & INACTIVE SEEPAGE BASINS (14) BINGHAM PLUMP OUTAGE PITS (7) K AREA CONTAINMENT BASIN (1)
FIRE DEPARTMENT	FIRE DEPARTMENT HOSE TRAINING FACILITY (1)
SREL	GEORGIAFIELDS SITE (1)

Table 6.6.7.1. Organizational Responsibility Summary Table (Contd)

<u>Organization</u>	<u>Site Description</u>
SRL	40 ACRE HARDWOOD SITE (1) 723-A MET. LAB. BASIN (1) SRL OIL TEST SITE (1) MISCELLANEOUS SITES (6)
SRL - TNX	SRL SEEPAGE BASINS (4) TNX SEEPAGE BASINS (2) TNX BURYING GROUND (1) TNX RUBBLE PILE (1)
SEPARATIONS	OLD F AREA SEEPAGE BASIN WASTE SITE (1) F AREA CLAY LATERALS (1)
WASTE MANAGEMENT	F&H AREA SEEPAGE BASINS (7) MIXED WASTE MANAGEMENT FACILITY(1) SILVERTON ROAD WASTE SITE(1) SILVERTON ROAD WASTE TANK PLUGS (1) ACTIVE & INACTIVE RETENTION BASIN (4) SANITARY LANDFILL(1) F AREA SCRAP LUMBER PILE(1) RADIOACTIVE BURIAL GROUNDS (2) CMP PITS (7) ASBESTOS PITS (2) BURNING/RUBBLE PITS (3) HIGH LEVEL TANK 016 (1) RUBBLE PITS (4)
SAVANNAH RIVER FOREST STATION	FOREST RUBBLE PIT (11) SRFS RUBBLE PILE (1)

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.6.8 Contamination Prevention

6.6.8.1 Site Program Overview

Systems to prevent groundwater contamination include all site diking systems and procedures, well design and installation specifications, and new underground storage tanks, associated equipment and piping systems. Diking systems prevent groundwater contamination by containing small leaks from above ground facilities in addition to protecting surface waters from run-off from spills. Well specifications and procedures in DPSOP 254 prevent contamination by ensuring all wells are properly installed to prevent cross contamination of aquifers in addition to meeting regulatory construction requirements. All new tank systems containing hazardous substances as defined in Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), petroleum products, or hazardous wastes provide groundwater protection with double-walled steel construction with interstitial monitoring and cathodic protection.

Since the site diking program and well specifications are discussed in other sections of the plan, this section deals almost exclusively with the Savannah River Site (SRS) underground storage tank program.

Over \$9.7 million will be required during the five-year planning period which includes 16 man-years of effort.

6.6.8.2 Regulatory Requirements

The Hazardous and Solid Waste Amendments of 1984 (HSWA) expanded the Resource Conservation and Recovery Act (RCRA) in Subtitle I to include underground storage tanks. The final underground storage tank regulations (Subtitle I) were promulgated in 1988. The Department of Energy (DOE) entered into negotiations with the South Carolina Department of Health and Environmental Control (SCDHEC) to include underground storage tanks in the existing Memorandum of Agreement (MOA). This gave the SCDHEC control over tanks containing petroleum products at the SRS under the existing SCDHEC underground storage tank regulations.

Federal Law

•**Resource Conservation and Recovery Act (RCRA)**—Permitting tanks regulated under RCRA Subtitle C is a two part process. The first part involves the submittal of a Part A application, containing basic information describing the tank system. The second part involves the submittal of a Part B application, containing more detailed information of the tank system and a certified tank assessment. The hazardous waste tank regulations require that all new tank systems have secondary containment with release detection, be built of a material which is compatible with the waste type, and be protected from corrosion.

Regulations resulting from Subtitle I require Environmental Protection Agency (EPA) notification of all underground storage tanks in operation which contain petroleum products or a hazardous substance as defined in the CERCLA. The SCDHEC was notified of all applicable tanks at the SRS on May 8, 1986. All new tanks must have a release detection system, corrosion protection, spill and overfill prevention devices, and be constructed of a material which is compatible with the substance to be stored.

State Regulations

•**Underground Storage Tank Control Regulations (R.61-92)**—These regulations require that all tanks installed after January 1, 1986 prevent releases due to corrosion, have a release detection system, and maintain an inventory recordkeeping system. The regulations also include requirements for notifications, permitting, installation, general operations, corrective actions, and abandonment activities.

Policy

•**SRS Policy**—The SRS policy is to handle hazardous materials in pipelines and vessels above ground to the extent it is safe, technically and economically feasible. In those instances where underground installations are appropriate, measures are to be taken to ensure that such installations are environmentally sound. SRS Presidential approval is required to install a tank system underground. A comparative risk analysis must be performed to determine if the system may be installed underground. All new underground storage tanks which will contain a hazardous substance as defined in the CERCLA or a petroleum product will be double-walled steel with interstitial monitoring and cathodic protection.

The systems to prevent contamination support the Waste Disposal Requirements and the Operational Guidelines objectives in Section 6.4.

6.6.8.3 Organizational Responsibilities

Underground Tank Committee

An Underground Tank Committee was established in November 1984 to develop the site policy for underground tank management. The committee authored the SRS SMARTS (Specifications and Management Applications for Regulated Tank Systems) Program, DPSP 85-1126 (Du Pont, 1985). The committee members included representatives from the custodial departments and technical support departments.

Environmental Protection Section (EPS)

The EPS is responsible for communicating applicable hazardous waste and underground storage tank regulation requirements to the Custodial Departments. The EPS is also the interface with the DOE and SCDHEC, including permit transmittals.

Custodians

The custodians are also responsible for identifying the new tank systems required to meet the facility needs and for acquiring the funding for tank design, construction, and installation. The custodian is also responsible for providing the information required for the applicable permits.

A listing of the SRS underground tanks by custodian is provided in Table 6.6.9.1.

6.6.8.4 Programs

Diking Systems

The SRS program is to retrofit existing above ground storage areas with impervious diking systems to contain leaks and spills. All new site facilities are required to include containment structures as part of the original design. Although the primary justification for these systems is to protect surface waters from run-off from spills and leaks, totally contained dikes also provide groundwater protection by containing small leaks. The cost and manpower requirements for this program are included in Section 3.6.7.

Well Specifications

The SRS has standard well specifications for the design, construction, and operation of monitoring and production wells. These specifications ensure all new monitoring wells are installed in accordance with RCRA requirements. Site procedures ensure these wells are sampled and analyzed according to EPA protocol standards. The monitoring well specifications and sampling procedures are contained in DPSOP 254. Although these specifications and sampling procedures were designed primarily to comply with rigid regulatory sampling requirements and health standards, these strict standards protect the groundwater by lowering the potential for a improperly installed well to cross contaminate aquifers. The cost and manpower requirements for this program are included in Section 3.6.2.

•**Environmental Protection Section (EPS)**—EPS is responsible for the oversight of the SMARTS Program as it applies to underground tank systems. This includes reviewing the comparative risk analysis, obtaining plant manager approval for tank installation, coordinating permitting of new facilities, ensuring all departments have an active inventory program, and updating the SMARTS Program when new regulations are promulgated. The SMARTS Program also requires that all tanks subject to regulation under Subtitle I have an inventory recordkeeping system. The program also provides plant policy on operating requirements, corrective action responsibilities and abandonment practices.

EPS is also responsible for sitewide consistency in the information included in the hazardous waste tank assessments.

The total five-year cost is estimated to be \$297,500.

6.6.8.5 Facility Operations

Underground and Hazardous Waste Tanks

•**Central Services Works Engineering (CSWE)**—CSWE is planning to abandon two underground fuel storage tanks. In addition, all heating fuel tanks on the site are to be abandoned. The program is estimated to cost \$219,500.

•**Construction Management**—Construction Management will abandon eight underground fuel storage tanks in FY89 and FY90. The estimated cost of the abandonment is \$63,800.

•**Waste Management**—Closure of tritiated waste oil tank S-32, which is located in the 643-7G burial ground, was completed in July 1988. Tank S-32 was closed in accordance with the SCDHEC approved closure plan, and it was the first hazardous waste unit closed at the SRS. The sludge was removed from the tank, and the tank and service piping were filled with grout. All pipes were cut off below grade, capped, and covered with soil. The closure cost was approximately \$100,000.

Waste Management also plans to abandon and decommission thirty-one underground holding tanks which contain radioactive wastes. The total cost is estimated to be \$3.4 million.

6.6.8.6 Construction Projects

Construction Management

Construction Management plans to replace two underground fuel storage tanks at Central Shops. The proposed project would require \$147,600 in FY91 funding.

Central Service Works Engineering

CSWE plans to replace the underground waste oil tank in FY90. The cost of the proposed project is \$31,900.

Power Operations

Power Operations plans to replace all existing underground storage tanks. The proposed project is scheduled as a \$6.5 million FY89 capital line-item. FY90 and FY91 spendout is \$2 million and \$4.5 million, respectively.

Reactors

Reactors plan to install 12 new underground fuel storage tanks to replace the existing tanks feeding the emergency generators in 100-P, K, L. The proposed project is estimated to cost \$36.5 million. Spendout during the planning period is \$7.1 million in FY90, \$7.5 million in FY91, \$18.4 million in FY92, and \$3.5 million in FY93. Since the primary purpose of replacing these tanks is to install additional storage capacity for reactor safety considerations, the capital cost is not included as an environmental cost in the plan. The new tanks will meet all the standards for underground tanks.

Safeguards and Security

Safeguards and Security plans to replace two underground fuel storage tanks. The proposed project would require \$118,600 in FY91 funding.

Waste Management

Waste Management plans to install two new low-level waste tanks to support continued operations of the Extended Sludge Processing (ESP), In-Tank Precipitation (ITP), and the Receiving Basin for Offsite Fuels (RBOF). These tanks will also meet future regulatory requirements. This project scope includes a reduction from four proposed tanks to two. This scope re-evaluation was done at the DOE's request and was based upon potential SCDHEC acceptance of Type IV tanks as equivalent device and changes in the tank farm schedule and services which has eliminated the need to use Tank 50 as a high heat waste receiver. This project will be funded as a FY91 capital line-item project. Costs for this project are included in Section 6.6.5.7.

6.6.8.7 Monitoring/Surveillance

Custodial Departments

The Custodial Departments monitoring and surveillance systems are detailed in Section 6.6.9.5, Contamination Detection.

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.6.9 Contamination Detection

6.6.9.1 Site Program Overview

Contamination detection includes the site monitoring well program and the underground storage tanks inventory systems. Monitoring wells are installed around existing facilities if there are indications of impacted groundwater or if there is a high potential for future impacts. All major new facilities have monitoring wells installed during construction prior to startup. All underground storage tanks containing hazardous materials, petroleum products, or hazardous wastes have an inventory and/or leak detection system. These inventory systems are designed to meet regulatory requirements as well as to protect the groundwater.

Since the monitoring well program is discussed in another section of the plan, this section deals almost exclusively with the Savannah River Site (SRS) underground storage tank inventory program.

Nearly \$6.8 million will be required during the five-year planning period which includes 41 man-years of effort.

6.6.9.2 Regulatory Requirements

The Hazardous and Solid Waste Amendments of 1984 (HSWA) expanded the Resource Conservation and Recovery Act (RCRA) in Subtitle I to include underground storage tanks. The final underground storage tank regulations (Subtitle I) were promulgated in 1988. The Department of Energy (DOE) entered into negotiations with the South Carolina Department of Health and Environmental Control (SCDHEC) to include underground storage tanks in the existing Memorandum of Agreement (MOA). This gave SCDHEC control over tanks containing petroleum products at the SRS under the existing SCDHEC underground storage tank regulations.

Federal Law

•**Resource Conservation and Recovery Act**—Permitting tanks regulated under RCRA Subtitle C is a two part process. The first part

involves the submittal of a Part A application, containing basic information describing the tank system. The second part involves the submittal of a Part B application, containing more detailed information of the tank system and a certified tank assessment. The hazardous waste tank regulations require that all new tank systems have secondary containment with release detection, be built of a material which is compatible with the waste type, and be protected from corrosion. These regulations also require performing a tank assessment for all existing tanks which do not have a secondary containment system meeting the regulatory requirements. If a tank does not have a secondary containment system which meets the requirements, it must be retrofitted with a secondary containment system which does or be closed.

Regulations resulting from Subtitle I require Environmental Protection Agency (EPA) notification of all underground storage tanks in operation which contain petroleum products or a hazardous substance as defined in CERCLA. SCDHEC was notified of all applicable tanks at the SRS on May 8, 1986.

All existing tanks must be retrofitted with leak detection corrosion protection and spill and overfill prevention devices within a ten year period.

State Regulations

•Underground Storage Tank Control Regulations (R.61-92)—These regulations require that all tanks installed after January 1, 1986, to prevent releases due to corrosion, have a release detection system, and maintain an inventory recordkeeping system. Under these regulations, each tank must have an inventory recordkeeping system. The regulations also include requirements for notifications, permitting, installation, general operations, corrective actions, and abandonment activities.

The systems to detect contamination support the Waste Disposal Requirements and the Operational Guidelines objectives in Section 6.4.

6.6.9.3 Organizational Responsibilities

Underground Tank Committee

An Underground Tank Committee was established in November 1984 to develop the site policy for underground tank management. The committee authored the SRS SMARTS (Specifications and Management

Applications for Regulated Tank Systems) Program, DPSP 85-1126 (Du Pont, 1985). The committee members included representatives from the custodial departments and technical support departments.

Environmental Protection Section (EPS)

The EPS is responsible for communicating applicable underground tank regulation requirements to the Custodial Departments. The EPS is also the interface with the DOE and SCDHEC, including permit transmittals.

Custodians

The custodians are responsible for the proper operation of the underground tanks. The custodians are also responsible for the development and implementation of the regulatory required inventory systems. It is the responsibility of the Custodial Departments to determine which tanks need to be replaced or upgraded and to acquire the funding necessary to meet the requirements of the applicable regulations.

6.6.9.4 Programs

A listing of SRS underground tanks by custodial department is provided in Table 6.6.9.1.

Soil Gas and Geophysical Surveys

•**SRL - Environmental Sciences Section**—Soil gas analysis is a tool used at SRS to identify contaminant areas and to track shallow groundwater plumes. The technique has been successful in detecting chlorocarbon, oil, and mercury in groundwater at disposal and spill sites. Soil gas surveys are used as a screening technique in the preliminary characterization of a waste site. Shallow geophysical techniques such as ground-penetrating radar and electrical resistivity are also being used to characterize waste sites. The total five-year cost is estimated to be \$4.6 million.

Monitoring Well Requirements

•**Environmental Protection Section (EPS)**—The SRS has criteria for the installation of monitoring wells for early indications of groundwater impacts. Monitoring wells are installed around existing facilities if there are indications of impacted groundwater or if there is a high potential for future impacts. All major new facilities, such as the Defense Waste

Processing Facility, have monitoring wells installed during construction to obtain pre-startup data and to detect any impacts from operations.

Costs for administering this program are included in the EPS costs shown in Section 6.6.3.

Underground and Hazardous Waste Tanks

•**Environmental Protection Section (EPS)**—EPS is responsible for the oversight of the SMARTS Program. The SMARTS Program requires that all tanks subject to regulation under Subtitle I have an inventory recordkeeping system. The program also provides plant policy on operating requirements, corrective action responsibilities and abandonment practices.

The EPS is responsible for sitewide consistency in the information included in the hazardous waste tank assessments.

Cost and manpower requirements are included in Section 6.6.8, Contamination Prevention.

A total of 126 underground storage tanks subject to regulation under Subtitle I of RCRA and 54 underground hazardous waste tanks subject to regulation under Subtitle C of RCRA have been identified at the SRS. In addition to these tanks are numerous tank systems which are exempt from Subtitle I regulations (heating oil tanks, flow-through process tanks, septic tanks, surface impoundments, stormwater or wastewater collection systems, et al.) and tank systems which Subtitle I regulations has been deferred until a later date (i.e., waste-water treatment tanks, oil/water separators, sumps, hydraulic lift tanks, underground electrical equipment, etc.).

6.6.9.5 Monitoring/Surveillance/Testing

All custodial departments are required to inventory and maintain inventory records on all underground storage tanks containing hazardous materials, petroleum products, or hazardous waste.

Central Services Works Engineering

CSWE has implemented use of both a constant level monitoring device and computerized automated fuel pump dispensers at the service station tanks as part of the required inventory program. The level monitoring

device provides information on the number of inches of fuel in the tank, gallons of fuel remaining in the tank, number of inches of water in the tank, and the temperature of the fuel. The automated fuel device provides information on the fuel transactions from a given tank.

CSWE manually obtains the liquid level reading for the underground waste oil tank two times per day. The liquid level reading obtained each morning is then compared to the liquid level reading obtained the previous afternoon to determine if any leakage has occurred.

The CSWE inventory program total five-year requirement is \$297,500.

Tank integrity tests for underground fuel storage tanks is estimated to cost \$24,150. The testing is scheduled to be completed in FY91.

DWPF

Two underground fuel storage tanks were installed at DWPF in 1985. The tanks are a double-walled steel design with continuous interstitial monitoring and sacrificial anodes for corrosion protection.

Costs of the DWPF inventory program are included as part of the DWPF operating costs in Section 6.6.5.

Construction Management

Construction Management uses manual monitoring devices to obtain in-tank liquid and water levels and metering devices to determine fuel transactions from a given tank. The net gains/losses are computed on a daily basis for high usage tanks. Low usage tanks are inventoried on a semi-monthly basis with the net gains/losses computed on a semi-monthly basis.

The inventory system for Construction tanks total five-year requirement is \$119,000.

The tank integrity tests for underground storage tanks is estimated to cost \$24,950 in FY91.

Power Operations

Power Operations uses manual monitoring devices to obtain in-tank liquid and water levels and metering devices to determine fuel transactions from

a given tank. The net gains/losses are computed on a daily basis for high usage tanks. Low usage tanks are inventoried on a semi-monthly basis with the net gains/losses computed on a semi-monthly basis.

The Power Operations inventory system total five-year requirement is \$297,500.

Four tanks will require tank integrity tests estimated to cost \$222,835. The testing is scheduled to be conducted in FY90 and FY91.

Raw Materials

Raw Materials has installed a new underground leaded oil sump which has full secondary containment and interstitial monitoring for leak detection.

The inventory costs are minimal and are included as part of the Fuel Fabrication production costs.

Reactors

Reactors uses manual monitoring devices to obtain in-tank liquid and water levels and metering devices to determine fuel transactions from a given tank. The net gains/losses are computed on a daily basis for high usage tanks. Low usage tanks are inventoried on a semi-monthly basis with the net gains/losses computed on a semi-monthly basis.

The Reactors inventory program total five-year requirement is \$59,500.

Safeguards and Security

Safeguards and Security uses manual monitoring devices to obtain in-tank liquid and water levels and metering devices to determine fuel transactions from a given tank. The net gains/losses are computed on a daily basis for high usage tanks. Low usage tanks are inventoried on a semi-monthly basis with the net gains/losses computed on a semi-monthly basis.

The Safeguards and Security inventory system total five-year requirement is \$29,750.

SRL-Technical Area

The Savannah River Laboratory uses in-tank monitoring devices to obtain liquid levels and to determine fuel transactions from a given tank. Sump alarms located within the secondary containment serve as release detection.

The SRL inventory system total five-year requirement is \$33,750.

Waste Management

As a result of the DOE interpretation of the byproduct material definition, Waste Management has prepared a RCRA Part B permit application for high-level waste tank farms. Tank assessments were included in the permitting activities. Modifications to procedures to ensure compliance with the permit application and with other RCRA requirements is estimated to cost \$171,500 in FY89 (see Section 6.6.5 for further discussion of tank farm permitting).

The total five-year cost of complying with RCRA requirements is estimated at \$799,325.

Tank integrity testing for underground fuel storage tanks is estimated to cost \$18,000 in FY91.

Waste Management underground high level radioactive waste storage tanks each have an electrical reel tape to monitor liquid level. The reel tape is read three times per day in the field. Each reel tape is calibrated once per month by comparing readings between a steel tape manually lowered into the tank and the reel tape. Each tank also has a high level conductivity probe.

Detailed procedures are in place to make material balances when waste is transferred between tanks. Tank level readings are recorded each hour and a balance is made every four hours during the transfer. All transfer lines are jacketed with stainless steel pipe. Each jacket is sloped to a low point where leak detection equipment (conductivity probe) is located.

Of the 51 tanks, 43 have an annulus. Each annulus has three conductivity probes and one pneumatic liquid level bubbler. The other eight tanks are single walled tanks that have been emptied of radioactive waste and contain low-level contaminated water, cleaning solution and solids that cannot be removed.

Costs associated with the inventory of the high-level waste tanks are included as part of the high level waste management costs in Section 6.6.5.

Waste Management uses manual monitoring devices to obtain in-tank liquid and water levels in the nonradioactive underground tanks. The net gains/losses are computed on a daily basis for high usage tanks. Low usage tanks are inventoried on a semi-monthly basis with the net gains/losses computed on a semi-monthly basis.

The Waste Management inventory system total five-year requirement is \$100,000.

Table 6.6.9.1. Underground Storage Tanks

<u>Organization</u>	<u>Tank Description</u>
CSWE CONSTRUCTON MANAGEMENT	SERVICE STATION TANKS (16) BULK STORAGE TANKS (8) HEATING FUEL TANKS (4) SERVICE STATION TANKS (2)
DWPF POWER OPERATIONS REACTOR	EMERGENCY GENERATOR FEED TANKS (2) EMERGENCY GENERATOR FEED TANKS (25) EMERGENCY GENERATOR FEED TANKS (16) RADIOACTIVE WASTE HOLDING TANKS (2) SAFEGUARDS & SECURITY EMERGENCY GENERATOR FEED TANKS (2)
SRL	FUELING TANK (1) CHEMICAL WASTE STORAGE TANKS (2) RADIOACTIVE WASTE HOLDING TANKS (10)
FOREST STATION WACKENHUT SECURITY WASTE MANAGEMENT	HEATING FUEL TANK (1) FUELING TANK (1) STAND-BY GENERATOR FEED TANK (1) HEATING FUEL TANK (1) RADIOACTIVE WASTE HOLDING TANKS (31)

Underground Hazardous Waste Tanks

<u>ORGANIZATION</u>	<u>Tank Description</u>
CSWE RAW MATERIALS WASTE MANAGEMENT	WASTE OIL (1)* LEADED OIL SUMP (1)* RADIOACTIVE WASTE STORAGE TANKS (52)

* 90-DAY ACCUMULATION TANK

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.7 Resource Requirements

The manpower and funding requirements for the Groundwater Protection and Waste Management program are shown in this section for FY89 through FY93. The manpower, operating, capital, and total cost schedules for each issue are presented in Tables 6.7.1 through 6.7.15. Similar schedules of manpower and cost requirements for each department are presented in Appendix Tables 6.7.1A through 6.7.15A.

The total funding required over the five-year planning period is estimated to be \$2 billion. Manpower requirements are 1850 man-years. Approximately 84 percent of program costs are associated with waste management and minimization activities. Total waste management costs including High-Level Waste (HLW) and TRU Waste activities are \$1.7 billion. The total five-year waste site closure costs are estimated at \$285 million.

GROUNDWATER PROTECTION PROGRAMS

6.7 RESOURCE REQUIREMENTS

ISSUE	FY 89		FY 90		FY 91		FY 92		FY 93		TOTAL	
	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR
6.6.1 GROUNDWATER CONSUMP.	57	10	57	10	57	10	57	10	57	10	283	50
6.6.2 HYDROLOGICAL REGIME	315	98	345	118	303	118	303	110	303	106	1571	550
6.6.3 GROUNDWATER MONITORING	494	0	494	0	494	0	494	0	494	0	2469	0
6.6.4 WATER CONSERVATION	115	32	110	32	110	32	125	32	125	32	585	160
TOTAL	981	140	1006	160	964	160	979	152	979	148	4908	760

* VALUES ARE THOUSANDS OF FY89 DOLLARS.

**ANNUAL MANPOWER COSTS BASED ON: MS = \$59.5M (SRS); LR = \$40M (SRS).

6.7.1 MANPOWER REQUIREMENTS SCHEDULE (\$M):**

GROUNDWATER PROTECTION PROGRAMS

6.7 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
6.6.1 GROUNDWATER CONSUMP.	30	30	30	30	30	150
6.6.2 HYDROLOGICAL REGIME	1665	1915	1390	1040	810	6920
6.6.3 GROUNDWATER MONITORING	3185	3185	3185	3185	3185	15925
6.6.4 WATER CONSERVATION	125	50	50	50	50	325
TOTAL	5005	5180	4655	4305	4175	23321

* COST ITEMS FOR PROGRAMS, OPERATING COSTS, RTA'S, SAMPLING, ETC., ARE EXPRESSED AS THOUSANDS OF FY89 DOLLARS. THESE COSTS DO NOT INCLUDE MANPOWER COSTS.

6.7.2 OPERATING BUDGET SCHEDULE (\$M)*

GROUNDWATER PROTECTION PROGRAMS

6.7 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
6.6.1 GROUNDWATER CONSUMP.	0	0	0	0	0	0
6.6.2 HYDROLOGICAL REGIME	120	320	70	70	70	650
6.6.3 GROUNDWATER MONITORING	0	0	0	0	0	0
6.6.4 WATER CONSERVATION	0	0	0	0	0	0
TOTAL	120	320	70	70	70	650

* CAPITAL ESTIMATES INCLUDE MANPOWER REQUIRED TO SUPPORT CAPITAL PROJECTS; THESE VALUES, EXPRESSED AS THOUSANDS OF DOLLARS, ARE ESCALATED THROUGH FY93.

6.7.3 CAPITAL BUDGET SCHEDULE (\$M)*

ENVIRONMENTAL IMPLEMENTATION PLAN

Effective 8/1/89

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

Page 5 of 16

6.7 Resource Requirements

GROUNDWATER PROTECTION PROGRAMS

6.7 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
6.6.1 GROUNDWATER CONSUMP.	97	97	97	97	97	483
6.6.2 HYDROLOGICAL REGIME	2198	2698	1881	1523	1390	9691
6.6.3 GROUNDWATER MONITORING	3679	3679	3679	3679	3679	18394
6.6.4 WATER CONSERVATION	272	192	192	207	207	1070
TOTAL	6246	6866	5849	5506	5372	29638

* INCLUDES MANPOWER COST (6.7.1), OPERATING COST (6.7.2) AND CAPITAL COST (6.7.3) EXPRESSED AS THOUSANDS OF FY89 DOLLARS.

6.7.4 TOTAL EXPENDITURE SCHEDULE (\$M)*

WASTE MANAGEMENT/DISPOSAL PRACTICES/MINIMIZATION

6.7 RESOURCE REQUIREMENTS

ISSUE	FY 89		FY 90		FY 91		FY 92		FY 93		TOTAL	
	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR
6.6.5 WASTE MANAGEMENT	7634	5660	7652	5860	7592	5860	8199	6000	8056	6000	39132	29380
6.6.6 WASTE MINIMIZATION	179	40	179	40	179	40	179	40	179	40	893	200
TOTAL	7812	5700	7830	5900	7771	5900	8377	6040	8234	6040	40024	29580

* VALUES ARE THOUSANDS OF FY89 DOLLARS.

**ANNUAL MANPOWER COSTS BASED ON: MS = \$59.5M (SRS); LR = \$40M (SRS).

6.7.5 MANPOWER REQUIREMENTS SCHEDULE (\$M)**

WASTE MANAGEMENT/DISPOSAL PRACTICES/MINIMIZATION

6.7 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
6.6.5 WASTE MANAGEMENT	192488	204984	258389	272203	262950	1191025
6.6.6 WASTE MINIMIZATION	204	341	541	541	641	2268
TOTAL	192692	205325	258940	272744	263591	1193293

* COST ITEMS FOR PROGRAMS, OPERATING COSTS, RTA'S, SAMPLING, ETC., ARE EXPRESSED AS THOUSANDS OF FY89 DOLLARS. THESE COSTS DO NOT INCLUDE MANPOWER COSTS.

6.7.6 OPERATING BUDGET SCHEDULE (\$M)*

WASTE MANAGEMENT/DISPOSAL PRACTICES/MINIMIZATION

6.7 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
6.6.5 WASTE MANAGEMENT	131461	60886	76590	88860	63850	421647
6.6.6 WASTE MINIMIZATION	0	0	400	0	0	400
TOTAL	131461	60886	76990	88860	63850	422047

* CAPITAL ESTIMATES INCLUDE MANPOWER REQUIRED TO SUPPORT CAPITAL PROJECTS; THESE VALUES, EXPRESSED AS THOUSANDS OF DOLLARS, ARE ESCALATED THROUGH FY93.

6.7.7 CAPITAL BUDGET SCHEDULE (\$M)*

WASTE MANAGEMENT/DISPOSAL PRACTICES/MINIMIZATION

6.7 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
6.6.5 WASTE MINIMIZATION	337243	279381	348441	375262	340856	1681184
6.6.6 WASTE MANAGEMENT	423	560	1160	760	860	3761
TOTAL	337666	279941	349601	376021	341715	1684944

* INCLUDES MANPOWER COST (6.7.5), OPERATING COST (6.7.6) AND CAPITAL COST (6.7.7) EXPRESSED AS THOUSANDS OF FY89 DOLLARS.

6.7.8 TOTAL EXPENDITURE SCHEDULE (\$M)*

6.7 Resource Requirements

WASTE SITE CLOSURE/REMEDIAL ACTION

6.7 RESOURCE REQUIREMENTS

ISSUE	FY 89		FY 90		FY 91		FY 92		FY 93		TOTAL	
	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR
6.6.7 WASTE SITE CLOSURE	2194	478	2506	498	2654	570	2597	638	2632	426	12583	2611
TOTAL	2194	478	2506	498	2654	570	2597	638	2632	426	12583	2611

* VALUES ARE THOUSANDS OF FY89 DOLLARS.

**ANNUAL MANPOWER COSTS BASED ON: MS = \$58.5M (SRs); LR = \$40M (SRs).

6.7.9 MANPOWER REQUIREMENTS SCHEDULE (\$M):**

6.7 Resource Requirements

WASTE SITE CLOSURE/REMEDIAL ACTION

6.7 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
6.6.7 WASTE SITE CLOSURE	38053	58258	57750	54755	60380	269196
TOTAL	38053	58258	57750	54755	60380	269196

* COST ITEMS FOR PROGRAMS, OPERATING COSTS, RTA'S, SAMPLING, ETC., ARE EXPRESSED AS THOUSANDS OF FY88 DOLLARS. THESE COSTS DO NOT INCLUDE MANPOWER COSTS.

6.7.10 OPERATING BUDGET SCHEDULE (\$M)*

WASTE SITE CLOSURE/REMEDIAL ACTION

6.7 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
6.6.7 WASTE SITE CLOSURE	100	150	300	200	250	1000
TOTAL	100	150	300	200	250	1000

* CAPITAL ESTIMATES INCLUDE MANPOWER REQUIRED TO SUPPORT CAPITAL PROJECTS; THESE VALUES, EXPRESSED AS THOUSANDS OF DOLLARS, ARE ESCALATED THROUGH FY93.

6.7.11 CAPITAL BUDGET SCHEDULE (\$M)*

6.7 Resource Requirements

WASTE SITE CLOSURE/REMEDIAL ACTION

6.7 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
6.7.7 WASTE SITE CLOSURE	40826	61412	61275	58190	63688	285390
TOTAL	40826	61412	61275	58190	63688	285390

* INCLUDES MANPOWER COST (6.7.9), OPERATING COST (6.7.10) AND CAPITAL COST (6.7.11)
EXPRESSED AS THOUSANDS OF FY89 DOLLARS.

6.7.12 TOTAL EXPENDITURE SCHEDULE (\$M):*

6.7 Resource Requirements

UNDERGROUND STORAGE TANKS

6.7 RESOURCE REQUIREMENTS

ISSUE	FY 89		FY 90		FY 91		FY 92		FY 93		TOTAL	
	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR
6.6.8 CONTAMINATION PREVENTION	222	0	202	0	274	0	131	0	131	0	969	0
6.6.9 CONTAMINATION DETECTION	315	153	290	153	308	153	242	153	242	153	1397	764
TOTAL	537	153	492	153	581	153	373	153	373	153	2357	764

* VALUES ARE THOUSANDS OF FY89 DOLLARS.

**ANNUAL MANPOWER COSTS BASED ON: MS = \$50.5M (SRS); LR = \$40M (SRS).

TABLE 6.7.13 MANPOWER REQUIREMENTS SCHEDULE (\$M)**

6.7 Resource Requirements

UNDERGROUND STORAGE TANKS

6.7 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
6.8.8 CONTAMINATION PREVENTION	963	4117	2658	523	523	8782
6.8.9 CONTAMINATION DETECTION	512	1054	1103	1000	1000	4669
TOTAL	1475	5171	3761	1523	1523	13452

* COST ITEMS FOR PROGRAMS, OPERATING COSTS, RTA'S, SAMPLING, ETC., ARE EXPRESSED AS THOUSANDS OF FY89 DOLLARS. THESE COSTS DO NOT INCLUDE MANPOWER COSTS.

TABLE 6.7.14 OPERATING BUDGET SCHEDULE (\$M)*

6.7 Resource Requirements

UNDERGROUND STORAGE TANKS

6.7 RESOURCE REQUIREMENTS

ISSUE	FY89	FY90	FY91	FY92	FY93	TOTAL
6.6.8 CONTAMINATION PREVENTION	1185	4319	2932	653	653	9742
6.6.9 CONTAMINATION DETECTION	980	1497	1564	1395	1395	6830
TOTAL	2165	5816	4495	2048	2048	16572

* INCLUDES MANPOWER COST (6.7.13) AND OPERATING COST (6.7.14)
EXPRESSED AS THOUSANDS OF FY89 DOLLARS.

TABLE 6.7.15 TOTAL EXPENDITURE SCHEDULE (\$M)*

6.0 GROUNDWATER PROTECTION AND WASTE MANAGEMENT

6.8 References

- DOE, 1987a. US Department of Energy, *Savannah River Plant Environmental Report for 1986*, DPSPU-87-30-1, US DOE, Aiken, SC.
- DOE, 1987b. *Final Environmental Impact Statement, Waste Management Activities for Groundwater Protection*, Savannah River Plant, Aiken, SC, DOE/EIS-0120, US DOE, Washington, DC.
- DOE, 1987c. *Geohydrology Program Report*, US DOE, Prepared for the Environmental Division, Savannah River Operations Office by NUS Corporation, Aiken, SC.
- Du Pont, 1987, *Hydrogeologic Data Collection*, DPSOP 254, E. I. du Pont de Nemours and Company, Aiken, SC.
- Du Pont, 1986a. *Environmental Quality, Corporate Policies and Guidelines*, E. I. du Pont de Nemours and Company, Wilmington, DE.
- Du Pont, 1986b. *Strategic Environmental Plan*, DPW-86-102, E. I. du Pont de Nemours and Company, Wilmington, DE.
- Du Pont, 1986c *Waste Site Closure Manual*, DPSP-86-1184, E. I. du Pont de Nemours and Company, Aiken, SC.
- Du Pont, 1985. *Specifications and Management Applications for Regulated Tank Systems*, DPSP-85-1126, E. I. du Pont de Nemours and Company, Aiken, SC.
- Martin, H. L., P. K. Gurney, and L.P. Fernandez, 1987, *Wastewater Reduction in Metal Fabrication Operations*, E. I. du Pont de Nemours and Company, Inc., Savannah River Plant, Aiken SC.

7.0 ATMOSPHERIC PROTECTION PROGRAM

CONTENTS

7.1 Overview

- 7.1.1 Introduction
- 7.1.2 Summary

7.2 Policy

- 7.2.1 Policy Statement
- 7.2.2 Background for Policy Statement

7.3 Existing Conditions

7.4 Objectives

7.5 Strategy

7.6 Implementation

- 7.6.1 Air Emissions Permitting
 - 7.6.1.1 Site Program Overview
 - 7.6.1.2 Regulatory Requirements
 - 7.6.1.3 Organizational Responsibilities
 - 7.6.1.4 Programs
 - 7.6.1.5 Construction/Modification Projects
 - 7.6.1.6 Research/Studies
- 7.6.2 Air Quality Assessments
 - 7.6.2.1 Site Program Overview
 - 7.6.2.2 Regulatory Requirements
 - 7.6.2.3 Organizational Responsibilities
 - 7.6.2.4 Programs
 - 7.6.2.5 Research/Studies

7.6.3 Nonradioactive Emissions Management

- 7.6.3.1 Site Program Overview
- 7.6.3.2 Regulatory Requirements
- 7.6.3.3 Organizational Responsibilities Summary
- 7.6.3.4 Programs
- 7.6.3.5 Facility Operations
- 7.6.3.6 Construction/Modification Projects
- 7.6.3.7 Research/Studies
- 7.6.3.8 Monitoring

7.6.4 Radioactive Emissions Management

- 7.6.4.1 Site Program Overview
- 7.6.4.2 Regulatory Requirements
- 7.6.4.3 Organizational Responsibilities Summary
- 7.6.4.4 Programs
- 7.6.4.5 Facility Operations
- 7.6.4.6 Construction/Modifications
- 7.6.4.7 Research/Studies
- 7.6.4.8 Monitoring

7.6.5 Emergency Response

- 7.6.5.1 Site Program Overview
- 7.6.5.2 Regulatory Requirements
- 7.6.5.3 Organizational Responsibilities
- 7.6.5.4 Programs
- 7.6.5.5 Facility Operations
- 7.6.5.6 Construction/Modifications
- 7.6.5.7 Research/Studies
- 7.6.5.8 Monitoring

7.7 Resource Requirements

7.8 References

Attachment

7.1 Air Quality Operating and Construction Permits

7.0 ATMOSPHERIC PROTECTION PROGRAM

7.1 Overview

7.1.1 Introduction

The Savannah River Site (SRS) Atmospheric Protection Program includes a comprehensive air monitoring program to evaluate air quality and potential impacts of emissions from plant operations. Data show that air quality near the SRS is within applicable federal and state limits, confirming that impact of SRS operations on air quality has been minimal. Industrial and urban growth along the Savannah River above and below the SRS is expected to expand; thus, continued exemplary stewardship of this resource is required. The Atmospheric Protection Program describes the overall management framework for protecting air quality.

7.1.2 Summary

SRS operations meet applicable federal and state standards and site policies related to protecting air quality, except for occasional high-opacity results from the F Area process stack during process upset conditions. Following renovation of the nitric acid absorption column for the process stack, the opacity requirement will be met. Atmospheric emissions of sulfur dioxide from powerhouse stacks are determined from analysis of burned coal.

Limited amounts of radioactivity are released from SRS facilities in the normal course of operations. This radioactivity is monitored at the source of release for atmospheric emissions. Radioactivity is also monitored throughout the site, the site boundary, and at various locations offsite.

Costs for the atmospheric protection program during the five-year planning period from FY89 through FY93 are expected to total over \$111 million which includes over 530 man-years of effort. Operating costs account for \$35 million. Capital expenditures are projected to be over \$45 million.

7.0 ATMOSPHERIC PROTECTION PROGRAM

7.2 Policy

7.2.1 Policy Statement

The SRS atmospheric protection policy is to conduct plant operations in a manner that protects human health and safety, meets regulatory emissions requirements, reduces emissions below regulatory limits, and complies with applicable Department of Energy (DOE) and operating contractor requirements.

7.2.2 Background for Policy Statement

The DOE and operating contractor are committed to protecting the public health and safety and the environment. This commitment is stated in DOE Order 5400.1, General Environmental Protection Program, and in the SRS *Strategic Environmental Plan*. (Du Pont, 1986a). Compliance with applicable environmental regulations, DOE orders, and operating contractor policies forms the basis for the SRS Atmospheric Protection Policy.

7.0 ATMOSPHERIC PROTECTION PROGRAM

7.3 Existing Conditions

The Savannah River Site (SRS) atmospheric protection program includes a comprehensive air monitoring program to evaluate air quality and potential impacts resulting from plant operations. Long-term activities include monitoring for criteria pollutants and radionuclides at onsite and offsite locations. In addition, special air surveys are initiated to understand specific impacts to air quality during normal and abnormal conditions, (i.e., fallout from Chernobyl).

Ambient air quality standards are being met onsite; however, improvements have been identified which would result in reduced emissions from some process areas, (i.e., nitrogen oxides (NO_x) from F-Canyon stack).

Criteria Pollutants

Although not required by the Clean Air Act, Environmental Protection Agency (EPA), or South Carolina Department of Health and Environmental Control (SCDHEC) regulations, a network of four onsite ambient air quality monitoring stations has been established to measure criteria pollutants. Data are collected and analyzed using EPA approved methods. Results are compiled quarterly and compared to state standards and National Ambient Air Quality Standards (NAAQS).

The nonradiological ambient air monitoring program has shown that SRS operations have not contributed to violations of any NAAQS. Maximum onsite levels of sulfur dioxide (SO₂) and nitrogen dioxide (NO₂) are about five percent of the standard; total suspended particulates are about 60 percent; and ozone is about 80 percent. A comparison of air quality data measured during 1986 at onsite locations to data from nearby offsite monitoring stations operated by SCDHEC and the Georgia Department of Natural Resources (GDNR) showed that offsite upper levels of criteria pollutants exceed those measured onsite (Zeigler et al., 1987; GDNR 1987; SCDHEC 1987). This indicates that the impact of operations at the SRS is minimal. The EPA has designated the area as attainment for all NAAQS.

Toxic Air Pollutants

Ambient levels of toxic and other non-criteria pollutants are not routinely measured at the SRS except for asbestos which is monitored during building renovation and/or demolition. Concentrations of toxic and other non-criteria pollutants can be calculated from emission source estimates using a dispersion model which predicts downwind concentrations.

Monitoring programs for toxic air pollutants could become a requirement for two SRS operations if proposed revisions to SCDHEC regulations are promulgated. It may become necessary to monitor volatile organic compounds near the M Area air stripper. Hazardous and toxic emissions data will probably be required to permit the proposed Consolidated Incineration Facility for onsite disposal of hazardous waste.

Radionuclide Emissions

The long-term SRS monitoring program, which conforms with DOE Order 5480.1B, has shown that ambient air concentrations of radionuclides around the SRS are within guides set by the DOE and EPA (40 CFR 61, Subpart H) to limit the radiation dose to the whole body and critical organs.

The radiation dose from SRS operations is small in comparison to the background from natural radioactivity, (cosmic, terrestrial, radon in homes), which averages 288 mrem per year for the area within 80 km of the SRS. The maximum onsite and offsite dose commitments from the SRS operations are 0.3 and 0.2 percent of the annual average, respectively. (Zeigler et al., 1987). In 1986 the calculated concentration of each radionuclide released to air from the SRS was less than one percent of the appropriate Derived Concentration Guide (DCG) recommended by the DOE for continuous, annual inhalation exposure for persons located beyond the site boundary.

The maximum committed effective dose equivalent at the SRS boundary from atmospheric releases during 1986 was 0.6 mrem, which is less than three percent of the EPA radionuclide National Emission Standards for Hazardous Air Pollutants (NESHAP) standard of 25 mrem/yr for the whole body. The critical organ dose commitment was 3.14 mrem to the thyroid which is about four percent of the EPA standard of 75 mrem/yr.

Tritium from SRS operations is the only airborne radionuclide routinely detected at the plant boundary. The average value in CY 1986 decreased in comparison to previous years, and represents less than one percent of the

DCG (Zeigler et al., 1987). The maximum onsite values, which occurred in F and H Separations Areas, were approximately 5.5 percent of the DCG.

Site-Specific Air Contaminant Problems

Emissions from some SRS operations can be reduced. Improvements are either planned or under study for the following operations.

F-Canyon Process Stack—In February 1986, a 40 percent opacity limit was imposed on the process stacks in F and H Areas by the SCDHEC. The H Area stack meets this limit; however, prior to July 1986, the F Area stack opacity was routinely 50 to 60 percent. The contaminant of most concern, NO_x, is extracted in an absorber column from the process offgases to make 50 percent nitric acid which is recycled. In July 1986, a rebuilt absorber column was installed and the average opacity dropped to 30 to 45 percent. Presently facility personnel are working to gather data and improve the process to further reduce stack opacity.

M Area—M Area emissions of 1,1,1-trichloroethane (TCE) from metal degreasing operations have been about 200 tons per year. Workplace sampling shows air concentrations about one percent of the threshold limit value (TLV®) for TCE. Degreasers in 321-M were recently switched to Freon®113. An evaluation of a detergent degreasing system to replace the solvent degreasers is under way.

7.0 ATMOSPHERIC PROTECTION PROGRAM

7.4 Objectives

The objectives to support the Atmospheric Protection Program are shown below. The strategy to achieve these objectives is illustrated in Section 7.5, followed by programmatic details in Sections 7.6 and 7.7.

- **Requirements**—Comply with the Federal Clean Air Act, South Carolina Department of Health and Environmental Control (SCDHEC) Regulation 61-62, and other applicable federal and state regulations, DOE orders, and operating contractor policies related to accident risk minimization and allowable emissions rates.
- **Operational Guidelines**—Strive to maintain emissions of radioactive, nonradiological, and toxic air pollutants per unit of production at or below current levels.
- **Impact Assessment**—Quantify sitewide air pollutant emission levels, understand the transport and interaction mechanisms of pollutants, and evaluate the impacts on human health and the environment.
- **Release Response**—Maintain a real time emergency response system at the SRS that has both onsite and two-state offsite capabilities.
- **Cost Benefit**—Utilize a cost/benefit methodology for evaluating air emission initiatives.

7.0 ATMOSPHERIC PROTECTION PROGRAM

7.5 Strategy

The strategy for reaching the Atmospheric Protection Program objectives includes:

- Identifying regulatory and other protection requirements.
- Promoting innovative and more cost-effective means of meeting requirements through research and development.
- Developing physical and administrative controls to protect the atmosphere utilizing the knowledge gained from the research and development efforts.
- Implementing physical and administrative controls.
- Evaluating and upgrade controls, as needed, to meet protection requirements.

This strategy is illustrated in Figure 7.5-1. Programmatic details are presented in Section 7.6.

Figure 7.5-1 Atmospheric Protection Program Strategy

7.0 ATMOSPHERIC PROTECTION PROGRAM

7.6 Implementation

The implementation section identifies issues and those responsible for actions to achieve defined objectives. Each environmental effort will require funding for one or more of the following: research and development, operations, construction/modification projects and manpower requirements. The resource requirements span a five-year period from FY89 through FY93.

The operating cost funds used throughout the text are expressed in FY89 dollars and are not escalated. Cost dollars include subcontractor, manpower, and other expenses drawn by facility operations from their operating funds. Capital cost projects, such as construction and large modification projects, are expressed in escalated dollars and include factored manpower costs. Total costs include cost of research and development, operations, manpower, subcontractors, and capital costs.

Annual manpower costs are calculated using these factors: SRS Monthly Salary (MS) at \$59,500 and all Local Roll (LR) at \$40,000.

7.0 ATMOSPHERIC PROTECTION PROGRAM

7.6.1 Air Emissions Permitting

The Savannah River Site (SRS) air emissions permitting program is designed to ensure that radiological, nonradiological, and toxic air pollutants emitted from SRS facilities are within levels that have been determined to be nondetrimental to human health and welfare, and that all federal and state regulatory requirements are met.

Air emission permits may be required from one or more governmental agencies for both the construction or modification, and operation of a facility. This section summarizes the types of permits, approvals and notifications which are required by the Environmental Protection Agency (EPA) and South Carolina Department of Health and Environmental Control (SCDHEC).

7.6.1.1 Site Program Overview

Currently, the SRS holds operating permits from the SCDHEC which regulate nonradioactive emissions from approximately 100 point sources (Attachment 1), about 20 of which have specific emission limitations. The SRS also holds construction permits for several new facilities.

Facility custodians are required to notify the Environmental Protection Section (EPS) before starting any activity which requires the removal of asbestos. If the quantity removed requires a National Emission Standards for Hazardous Air Pollutants (NESHAP) permit, the EPS then notifies the Department of Energy (DOE) who obtains approval from the SCDHEC for the asbestos removal as required by EPA (40 CFR 61, Subpart M) and SCDHEC (61-86.1) regulations. Similarly, the operating contractor notifies the DOE prior to burning scrap wood or conducting a fire training exercise. The DOE notifies the SCDHEC as appropriate. The SR Forestry Station is responsible for obtaining permits for prescribed burning used in forest management.

Total cost for air emission permitting is \$416,500 for the five-year planning period which includes seven man-years of effort.

7.6.1.2 Regulatory Requirements

Air emissions from SRS facilities are regulated by the EPA and SCDHEC. SRS operations must also be conducted in a manner which complies with DOE orders and operating contractor policy.

Clean Air Act—DOE facilities are required to comply with regulations issued by the EPA under the Clean Air Act (Title 42 U.S.C. 7401, et seq.) which include:

- National Primary and Secondary Ambient Air Quality Standards (NAAQS, 40 CFR 50) set primary and secondary standards for criteria pollutants, and reference methods for the determination of criteria pollutants in ambient air.
- Standards of Performance for New Stationary Sources (NSPS, 40CFR 60) set allowable emission limitations for new sources:
- Prevention of Significant Deterioration rules (PSD, 40 CFR 52) require preconstruction monitoring and permits for the construction of major, new stationary sources of air pollutants.
- National Emission Standards For Hazardous Air Pollutants (NESHAP, 40 CFR 61) require approval from EPA prior to the construction or modification of a source which will release hazardous air pollutants.

The State of South Carolina has an approved State Implementation Plan (SIP). Authority to regulate air programs for sources within the State is delegated to the SCDHEC. One exception involves regulation of radionuclides under the NESHAP which will be regulated by EPA until revisions to the South Carolina SIP are approved by EPA.

South Carolina Pollution Control Act—DOE facilities are required to comply with regulations issued by the SCDHEC under the South Carolina Pollution Control Act (SC Code of Laws, Title 48, Chapter 1), which include:

- South Carolina Air Pollution Control Regulations (SCDHEC 61-62) set standard requirements for construction and operating permits and for renewing permits, require the compilation and annual updating of an emissions inventory, regulate open burning, and require emergency action plans to deal with releases of hazardous air pollutants.

- South Carolina Ambient Air Quality Standards (SCDHEC 61-62.5) set standards for visible emissions and requirements for opacity monitoring, and source tests. This regulation also sets emission limitations for certain source types and PSD requirements.
- South Carolina Standards of Performance for Asbestos Removal Operations (SCDHEC 61-86.1) set requirements for the removal and handling of asbestos when a facility is either renovated or dismantled.

South Carolina has proposed two regulations which may impact permitting of SRS facilities. The state has released a draft Toxic Air Pollution Standard which could apply to new or proposed source modifications after July 1, 1989. This regulation may require an operator to provide information on air toxics, and dispersion modeling to show that ambient air concentrations will not exceed specified limits at the plant boundary. Proposed revisions to the Air Pollution Control Regulations to regulate emissions from boilers, furnaces and incinerators may impact the permitting of the proposed Consolidated Incineration Facility.

DOE Orders—The following DOE order applies to permitting activities at the SRS:

5480.1B—Environment, Safety, and Health Program for Department of Energy Operations, adopted 9-23-86. This order sets environment, safety, and health (ES&H) requirements for all DOE or DOE-controlled operations.

7.6.1.3 Organizational Responsibilities

The Environmental Protection Section (EPS) is responsible for administrative oversight of air permitting. The EPS monitors site performance required by permits, assists custodians in preparing permit applications, transmits permit applications and regulatory reports to the DOE for submission to the SCDHEC, and is the operating contractor contact with the DOE for all interactions with the SCDHEC.

Each facility custodian is responsible for completing a National Environmental Policy Act (NEPA) checklist and preparing required permit applications prior to any construction or facility modification. The custodians are responsible for ensuring that facilities are constructed and operated in accordance with permit requirements.

SRL is responsible for conducting air modeling that may be required to support permit applications.

7.6.1.4 Programs

Asbestos Removal Control

•**Environmental Protection Section (EPS)**—Custodians are to notify the EPS 30 to 40 days prior to any major asbestos removal job (160 square feet or 260 linear feet or more) for the EPS to obtain DOE and SCDHEC approval. The EPS notifies the custodian when the job can start, coordinates SCHDEC inspections, and signs the Construction Asbestos Removal form. Custodians must also notify the EPS of minor removals 24 hours in advance. The minor removal is recorded in the site asbestos removal log maintained by the EPS. This log may be inspected by the SCDHEC at any time. A quarterly report summarizing minor asbestos removals is prepared for the DOE to submit to the SCDHEC.

The estimated total five-year cost is \$148,750.

Increase Capacity of Groundwater Air Stripper

•**Raw Materials**—The capacity of the M-Area air stripper column is limited by a 400 gpm NPDES discharge rate and an air emissions limit of 34.6 tons of chlorocarbons per year. Following tests to increase the groundwater feed rate, an application to modify the air and wastewater permit for the stripper will be submitted to SCDHEC.

Cost requirements other than permitting are listed in Section 7.6.3.4. The total five-year cost for permitting activities is estimated to be \$14,875. Milestones include:

Complete capacity tests	08/89
Submit wastewater permit to SCDHEC	04/90

NEPA Checklist Review

•**Environmental Protection Section (EPS)**—The EPS reviews all Environmental Evaluation (formerly NEPA, Safety Analysis and Permits) Checklist prepared by facility custodians for test authorizations, new construction or renovation projects costing more than \$250,000 to identify potential environmental and health impacts and to determine permit requirements. The EPS advises facility custodians of permit requirements and timing needed to obtain permits. Custodians then complete permit applications with EPS assistance. The EPS submits permit applications to

the DOE, arranges any necessary meetings with the SCDHEC through the DOE, and notifies custodians when permits are issued.

The estimated total five-year cost is \$74,375.

Permitting Support

•**Environmental Protection Section (EPS)**—The EPS provides permitting support to custodial departments as needed. In FY88, the EPS developed detailed NESHAP permitting instructions to assist custodial departments in completing the data needed for NESHAP approval.

The total five-year cost for permitting support is estimated to be \$148,750.

•**Custodial Departments**—It is the responsibility of each custodial department to prepare a Environmental Evaluation Checklist, complete permit applications and compile supporting information. The custodial departments must ensure that facilities are constructed and operated in accordance with permit requirements and that any Change of Design modifications will not violate permit conditions.

Custodial departments are responsible for submitting to the EPS information required for permit renewal or modification. SRS operating permits are shown on Attachment 7.1. The attachment also identifies construction permits for which operating permits are required before operating these facilities.

Costs to complete the Environmental Evaluation Checklist and to prepare permit applications are included in the cost of each project.

7.6.1.5 Construction/Modification Projects

Burial Ground Equipment Support

•**Waste Management (WM)**—WM will install a mobile concrete mixer and storage silo at the Burial Ground which will be used in the solidification of selected radioactive wastes. This facility will require air quality and NESHAP permits.

Consolidated Incineration Facility

•**Waste Management (WM)**—A Consolidated Incineration Facility (CIF) will be installed in H-Area to burn low-level, hazardous, and mixed wastes

to meet Resource Conservation and Recovery Act (RCRA) waste minimization disposal, the land ban, and SRS volume/cost reduction goals. The facility will include design provisions to minimize chemical and radiological air emissions, using such techniques as offgas scrubbers and HEPA filters. Milestones include:

Obtain air and RCRA permits	12/89
Construction start	02/90
Mechanical completion	11/91
Trial burn	1st quarter 1992
Operating permit and startup	May 1992

7.6.1.6 Research/Studies

NESHAP Impact Modeling

•**SRL - Environmental Technology Section (ETS)**—The ETS has obtained and developed the capability to use the AIRDOS-EPA code to calculate the impact of air emissions. AIRDOS will be used to evaluate compliance with radionuclide NESHAP standards.

The estimated total five-year cost is \$29,750.

7.0 ATMOSPHERIC PROTECTION PROGRAM

7.6.2 Air Quality Assessments

The Savannah River Site (SRS) air quality assessment program is conducted to achieve the objectives stated in Section 7.4. It is designed to improve understanding of transport and interactions of pollutants in the atmosphere, evaluate impacts to human health and the environment and to comply with regulatory requirements.

7.6.2.1 Site Program Overview

Air quality assessments are included in the annual SRS Environmental Report required by Department of Energy (DOE) Orders 5400.1 and 5484.1. Assessments are also frequently required to support permit applications, hazard reviews and to show compliance with applicable environmental regulations.

The Environmental Technology Section of SRL (ETS) operates and maintains the site meteorological data gathering network and validates the computer codes used to calculate dose assessments. The Environmental Sciences Section of SRL (ESS) conducts research on the transport of tritium and other pollutants, and their interactions with vegetation and soils. This research will provide data to estimate the dose to man from radionuclides incorporated into plant matter. The Environmental Monitoring Section (EMS) measures beta fallout from nuclear weapons testing and prepares the annual SRS Environmental Monitoring Report.

Total cost for air quality assessments is \$109 million for the five-year planning period, FY89 through FY93, which includes 28 (MS) and 25 (LR) man-years of effort.

7.6.2.2 Regulatory Requirements

Most of the regulatory requirements set forth in Section 7.6.1.2 require air quality data to support permit applications or to show compliance with permits issued under those regulations. The following DOE orders also apply to air quality assessments:

5400.1—General Environmental Protection Program, 11-09-88—This order sets the requirements for reporting and notification including compilation of an annual site environmental report.

5480.12—Environmental Pollution Control—This order requires that releases of radionuclides be characterized and their impact on the public and the environment be assessed. This order is currently under revision.

5484.1—Environmental Protection, Safety, and Health Protection Information Reporting Requirements—This order establishes requirements and procedures for reporting and investigating matters of environmental, safety, and health protection significance to DOE operations. This includes the annual environmental monitoring report.

7.6.2.3 Organizational Responsibilities

The Environmental Monitoring Section is responsible for routine monitoring for airborne radioactive and nonradioactive pollutants.

The Savannah River Laboratory (SRL-ETS) collects meteorological data from nine onsite and offsite towers and conducts or administers contracts to study and model atmospheric transport and pollutant interactions with the environment.

7.6.2.4 Programs

Environmental Monitoring Section (EMS)

•Ambient Air Quality Monitoring

Ambient air monitoring for NO_x, Ozone (O₃), SO₂ and total suspended particulates (TSP) was initiated by EMS. The EMS operates a five station air quality monitoring network. This program provides data for assessing air quality and supporting any Prevention of Significant Deterioration (PSD) permit application that may be submitted to the EPA for a major new facility.

The total five-year cost is estimated to be \$1 million.

•Fallout From Nuclear Weapons Tests

The EMS routinely collects and analyzes samples of nonvolatile particulate matter for beta activity from atmospheric weapons tests. Monthly values are

plotted to determine background radiation levels, seasonal variability and long-term trends in beta activity from weapons testing.

The estimated total five-year cost is \$168,750.

•Savannah River Site Environmental Report

The EMS is responsible for preparing the annual SRS Environmental Report required by DOE Orders 5480.12, 5484.1 and 5400.1 for release to the public. The report, which covers all environmental media, is issued in two volumes. The first volume describes the SRS environmental monitoring program and analyzes the data collected for the subject year. Air quality assessments for criteria pollutants and radionuclides are an integral part of this volume. The second volume presents the environmental monitoring data and figures.

The resources needed to prepare the annual report are summarized in the Community Outreach Section of the EIP (Section 12.0).

SRL-Environmental Technology Section (ETS)

•SRS Meteorological Database

A system of nine onsite and one offsite instrumented towers to collect real-time meteorological data are operated by ETS. Up to 125 data points are collected every 1.5 seconds and compiled using a quality control algorithm. Data summaries are printed hourly to check instrumentation and assess local conditions. The data are stored to provide a permanent climatology record for SRS. The five year meteorological data base used for dispersion and transport calculations is periodically updated from these records.

The estimated total five-year cost is \$4.4 million.

•Standard Methodology for Routine and Accidental Release Calculations

A technical manual giving a standard set of analytical methodologies and computer codes to calculate pollutant transport and to assess doses from routine and postulated accidental releases was developed by ETS. Recent work to revise the atmospheric transport and dose assessment codes along with associated costs and manpower requirements are included with the Mesoscale Atmospheric Transport Study (MATs) discussed in Section 7.6.5.7.

•Environmental Dose Calculations

The ETS maintains a set of environmental dosimetry codes that provide state-of-the-art methodology that is accurate and consistent for assessing doses from normal plant operations and hypothetical incidents. These codes are used to prepare dose estimates required for safety analyses, permit applications and the annual environmental report. The codes were recently modified to use ICRP 30 dose factors and the 1982 through 1986 SRS meteorological data base update.

The estimated total five-year cost is \$2.3 million.

7.6.2.5 Research/Studies

Research/studies are conducted to assess air quality impacts of SRS operations and to understand pollutant transport and atmospheric interactions. Some of these studies are not directly related to environmental compliance activities, but have broad environmental protection goals.

SRL-Environmental Technology Section (ETS)

•Modeling of Reactor Stacks

Reactor stacks are being studied to determine the effect of stack height on radiation doses from postulated accidents. ETS contracted with Colorado State University in FY87 to model the P- and L-Reactor complexes with the existing 62 meter stack, a 107 meter stack and a 152 meter stack in a wind tunnel capable of simulating different atmospheric stabilities. The wind tunnel data will be compared to data from the mathematical dispersion model used by ETS.

If the results of this study demonstrate a higher stack is justified, SRL will have addressed potential concerns about the Gaussian Model, a dispersion model used in dose calculations, determining stack design, and reassessing emergency planning conditions.

The estimated FY89 operating cost is \$77,575.

•Stable Boundary Layer Experiment - STABLE

The ETS will participate in STABLE which is a study being conducted by two universities and several DOE sponsored laboratories to measure

turbulence and pollutant dispersion in the nocturnal boundary layer. The goal of the study is to improve dispersion modeling of atmospheric releases under nocturnal conditions which are expected to cause the most severe impact. The study will run four years.

The estimated FY89 and FY90 operating cost is \$309,500. Milestones include:

Publish preliminary study results	FY89
Complete field measurements	FY89
Publish study results	FY90

•Transport and Cycling of Tritium and Other Pollutants

This study measures the transport and exchange of gases and particles with forested land surfaces using micro-meteorological methods. Air/earth pollutant exchange data have been collected for water vapor (tritium oxide), carbon dioxide, sulfur dioxide, and particulates. Field and laboratory experiments involving exposure of vegetation and soils to selected pollutants are also conducted. Models of these processes are used to provide more accurate estimates of downwind pollutant concentrations and their impact on terrestrial ecosystems.

Other study elements are designed to: (1) determine the uptake rates of elemental tritium by terrestrial ecosystems, (2) determine the partitioning of absorbed elemental tritium into plant organic matter, (3) estimate the dose to man from tritium incorporated into organic matter, and (4) determine the rate of incorporation of tritium into aquatic organic compartments for streams receiving periodic tritium releases.

The total estimated cost is \$3.4 million. The estimated cost for the five-year planning period is \$2.4 million. Milestones include:

Complete collection and measurement of organic tritium content of Upper Three Runs Creek.

Collect biota from tritium contaminated areas to look at food chain transfer of tritium.

•Validation of Pollutant Transport Models

Atmospheric meteorological data from nine onsite and one offsite instrumented towers are used by ETS to annually verify the atmospheric dispersion models used to calculate radiological dose assessments.

The estimated total five-year cost is \$148,750.

7.0 ATMOSPHERIC PROTECTION PROGRAM

7.6.3 Nonradioactive Emissions Management

The Savannah River Site (SRS) nonradioactive emissions management program is conducted to achieve the objectives stated in Section 7.4, to meet all South Carolina Department of Health and Environmental Control (SCDHEC) permit conditions, and to further reduce emissions per unit of production.

7.6.3.1 Site Program Overview

Each operating department is responsible for ensuring that air emissions from their facilities comply with SCHDEC permits and all applicable State and Federal air standards. The Environmental Protection Section (EPS) provides regulatory oversight and assistance to the operating departments.

The EPS has initiated a three year program to compile a comprehensive inventory of point and fugitive air emission sources. The sources will be systematically numbered and characterized as to location, physical dimensions, and design maximum and actual emission rates. The Environmental Technology Section (ETS) of the Savannah River Laboratory (SRL) has initiated a long term program to identify and characterize trace level emissions of organic compounds that may be hazardous.

Several operating departments have proposed projects to either install new or to upgrade existing air emission control equipment to reduce emissions and potential health hazards. The Power and Power Engineering Sections have projects for coal dust abatement, improved soot blowing, new induced draft/forced draft (ID/FD) fans for the A Area boiler and boiler controls optimization. Raw Materials and Separations have projects to improve control of NO_x emissions.

The total estimated five-year cost for nonradioactive emissions management is about \$38.3 million which includes 85 (MS) and 114 (LR) man-years of effort.

7.6.3.2 Regulatory Requirements

Air emissions from SRS operations must comply with applicable regulations, Department of Energy (DOE) orders (see Sections 7.6.1.2 and 7.6.2.2) and all conditions specified in SCDHEC permits.

7.6.3.3 Organizational Responsibilities Summary

Operating departments are responsible for controlling air emissions from their facilities. Facilities must be operated to control air emissions and to meet all permit conditions. Programmatic regulatory support is provided by the EPS. Routine monitoring of air emissions and ambient criteria pollutant concentrations is conducted by the Environmental Monitoring Section. The SRL is responsible for special studies and predictive air quality assessments.

7.6.3.4 Programs

The following programs have either been proposed or undertaken to better understand processes and their environmental impacts. These programs have specific immediate or near-term objectives.

Environmental Protection Section (EPS)

- **Air Emissions Inventory**—The EPS has initiated a program to identify and characterize all point and fugitive emission sources at the SRS. The work will be performed by a contractor under EPS direction. Field surveys will be carried out with the assistance of building custodians to locate sources and to define source operation. This study, which is expected to identify a number of sources, will provide the comprehensive inventory to develop the data base to comply with projected new regulations. Custodians will review their sources annually and notify the EPS to update the inventory as appropriate.

The total five-year cost is estimated to be \$1.2 million.

For planning purposes, custodial effort was allotted as follows: Reactors and Separations-20 percent, Construction, Power, SRL-ETS and Waste Management-10 percent; CSWE, Heavy Water (Reactors), Raw Materials and TNX-5 percent. Milestones include:

Develop field protocols	08/89
Complete sitewide inventory	12/93

Power Engineering (PE)

- **Boiler Control Optimization and Performance Testing**—PE is conducting studies to optimize boiler combustion control systems, and performance testing. This study should improve boiler efficiency and reduce carbon monoxide and particulate emissions.

The estimated total five-year cost is \$478,650. Milestones are:

Start optimization study	08/89
Complete optimization study	12/91

Conduct performance testing every two to three years

Raw Materials (RM)

- **Elimination of Solvent Degreasers**—RM has initiated a project to eliminate the use of solvent degreasers in M Area. It is anticipated that that the solvent units will be replaced with detergent degreasers.

M Area has replaced 1,1,1-trichloroethane with Freon® TF, a more environmentally suitable substitute. However, SRL has conducted tests to identify suitable alternatives to Freon® TF with only limited success. The ability to meet the outlined milestones is dependent on the results of additional testing and whether identified alternatives can feasibly be implemented into M Area processes.

The estimated total five-year cost is \$471,400. Milestones include:

Develop control strategy	02/89
Request Engineering Dept. assistance	10/89
Begin installation	04/91
Complete installation	10/91

- **Emissions from Etching Tank**—RM has proposed to study emissions of ammonia and sodium hydroxide from the aluminum etching tanks used in M Area to determine if these emissions pose any threat to employee health or the environment. Scrubbers will be installed if the study indicates that they are needed.

The estimated total five-year cost is \$148,155. Milestones are:

Develop program strategy	06/90
Initiate tank monitoring	04/91
Develop control strategy	10/91

• **Increase Capacity of Groundwater Air Stripper**—The capacity of the M Area air stripper column is limited by a 400 gpm NPDES discharge rate and an air emissions rate of 34.6 tons of chlorocarbons per year. Following tests to increase the groundwater feed rate, an application to modify the air permit for the stripper will be prepared for submittal to the SCDHEC.

The estimated FY89 operating cost is \$38,675. Milestones include:

Complete capacity tests	08/89
Submit permit modification to SCDHEC	04/89

7.6.3.5 Facility Operations

Power Operations

• **Control of Boiler Emissions**—The coal fired boilers at the SRS are equipped with mechanical dust collectors or electrostatic precipitators to meet SCDHEC permit conditions and ambient air quality standards. Opacity meters are installed in the boiler stacks to continuously measure emissions. Routine operations include maintenance of the dust collectors, calibration and repair of the opacity meters, coal quality analyses and generation of required environmental operating records.

The estimated total five-year cost is \$1.2 million.

Raw Materials (RM)

• **Control of M Area Emissions**—The SCDHEC air permit limits chlorinated solvent emissions from the M Area groundwater stripper and NO_x (opacity) emissions from two metal cleaning processes. Routine operations include determining and recording the amount of solvents emitted from the stripper from analyses of inlet and outlet water. NO_x from the cleaning processes can be controlled, as needed, using scrubbers or tank controls. Costs to calculate emissions rates are minimal.

Custodial Departments

• **Emergency Diesel Generator Operations**—SCDHEC air permits for emergency power diesel generators (Attachment 7.1) contain specified emission levels and limitations on the number of operating hours. Custodians must keep operation records and make them available to the SCDHEC on request.

The estimated total five-year cost to keep the required records is \$64,000. For planning purposes, the cost is divided equally between Power, Reactors, Separations, and Waste Management.

SRL - TNX

• **TNX Pilot Operations Emissions**—The SCDHEC air permit for TNX sets emission limits for the Precipitate Hydrolysis Experimental Facility (PHEF) and the Plutonium Waste Research Incinerator (PWRI). The Integrated DWPF Melter System (IDWPF) is exempt from SCDHEC regulation. Air emissions from these facilities must be controlled to meet permit and exemption limits.

Benzene emissions from the PHEF are controlled with a refrigerated condenser. The SCDHEC requires a temperature gauge which has been connected to an audible alarm. If a temperature excursion occurs, the facility is shutdown. In addition, a benzene vapor monitor is used to detect and correct fugitive emissions from flanges, seals and valves.

Opacity levels from the PWRI are controlled with an offgas treatment system that uses dilution air cooling, a sintered metal filter and a high efficiency particulate air (HEPA) filter.

Emissions from the IDWPF are controlled using several systems including a refrigerated formic acid condenser to remove mercury vapor, an offgas quencher, an ejector venturi gas scrubber for particulates, high efficiency mist eliminators, and HEPA filters.

The total five-year cost specific to routine air emissions management for these facilities is estimated to be \$22,500.

7.6.3.6 Construction/Modification Projects

Power Operations

- **Dust Abatement Systems - A, H, K and P Areas**—Significant quantities of dust are generated in handling coal at the power houses. This FY 91 project to control fugitive coal dust emissions will reduce a potential employee health hazard and improve SRS air quality.

The total estimated capital cost is \$10 million. The estimated total five-year cost is \$10.4. Milestones include:

Project authorization	06/91
Project completion	12/94

- **Install Emissions Monitors, A, H, K, and P Areas**—Indications are that the EPA will require additional monitoring of emissions from powerhouses and have tighter limits on potential pollutants such as sulphur dioxide. This project will install the required monitoring equipment and replace obsolete monitoring equipment for opacity. This is a FY93 capital project with a total estimated cost of \$3.5 million.

- **Improved Soot Blowing Equipment - 484-D**—The soot blowing equipment at the 484-D powerhouse has been in service for over 30 years. New equipment will increase boiler efficiency and reduce stack opacity.

The total FY90 estimated capital cost is \$2.0 million. The estimated total five-year cost is \$2.1 million. Milestones are:

Project authorization	06/90
Project completion	12/92

Raw Materials (RM)

- **Install NO_x Scrubber - 321-M**—NO_x emissions from two metal cleaning processes in 321-M are released directly to the atmosphere. This proposed FY94 project will install a scrubber to reduce NO_x emissions.

The total estimated capital cost is \$300,000. The estimated total five-year cost is \$328,500. Milestones are:

Develop basic data	10/93
Project authorization	04/94
Project completion	06/95

- **Replace Nitric Acid Scrubber - 313-M**—The existing nitric acid scrubber in 313-M will be replaced with a more efficient unit that will reduce the liquid effluent stream to about one gpm. Atmospheric emissions of NO_x will also be reduced. Priority for replacement of the acid scrubber will be impacted by Building 313-M schedules.

The estimated capital cost is 150,000. The estimated total five-year cost is \$201,700. Milestones include:

Request Engineering Department assistance	06/87
Develop basic data	09/87
Project authorization	06/89
Project completion	05/90

- **Monitor NO_x Emissions**—After the nitric acid scrubber in 313-M becomes operational, it will be necessary to monitor NO_x emissions. The FY90 project to replace the acid scrubber will include both radioactive air monitoring and NO_x monitoring in the basic data.

The estimated total five-year cost is \$59,500. Milestones are:

Conduct monitoring tests	FY90/91
--------------------------	---------

- **Upgrade Filtered Exhaust System - 322-M**—The filtered exhaust system in the Metallurgical Laboratory (322-M) will be upgraded to reduce chemical emissions and ground level employee exposures.

The total estimated capital cost is \$500,000. The estimated total five-year cost is \$567,700. Milestones include:

Develop basic data	10/87
Complete design and CAC estimate	06/88
Project authorization	08/88
Project completion	09/90

Separations

● **Improved NO_x Absorption - F Canyon**—A rebuilt NO_x absorption column was installed in July 1986 when SCHDEC imposed a 40 percent opacity limit on the F Canyon stack. The rebuilt column resulted in a reduced opacity but not consistently below the 40 percent limit. Separations has initiated an FY89 project to install automatic controls on the F-8 absorption column that will improve control of NO_x emissions.

The estimated total five-year cost is \$2.5 million.

SRL - Analytical Development Section (ADS)—During FY88, the ADS specified and worked with Separations to install analyzers on the F-8 absorption column inputs and outputs. Data from these analyzers were used to develop a model of the column operation and a control scheme.

In FY89, a control scheme recommendation will be made to the plant and the analyzers (with ADS developed operating manuals) will be turned to the plant for their continued use. The ADS will assist Separations with a plant test of the recommended control scheme. The model will be refined further and general assistance will be provided for the column control project.

The estimated FY89 operating cost is \$130,000.

7.6.3.7 Research/Studies

SRL - Environmental Technology Section (ETS)

● **Identification of Trace Level Organic Emissions**—The ETS has initiated a research study to identify and characterize trace level emissions of organic compounds used in production processes or formed as radiation degradation products. Air emissions from SRS facilities will be sampled and analyzed by a contract laboratory using ultra sensitive mass spectrometry until the SRL develops in-house analytical capability.

The estimated total five-year cost is \$3.6 million. Milestones are:

Initiate research program	1st quarter 89
Complete feasibility study	4th quarter 89

Future milestones are to be determined.

7.6.3.8 Monitoring

Health Protection Technology Section (HPTS)

- **Asbestos Monitoring**—The Health Protection Technology Section monitors asbestos levels according to DPSOL 40-5-102 during all building renovations or demolitions involving asbestos.

The estimated total five-year cost is \$9.4 million.

Power Operations

- **Boiler Compliance Testing**—SCDHEC air permits require that the 13 coal fired boilers at the SRS be tested every two years to verify compliance with particulate emission limits. The tests are conducted by a certified vendor with a SCHDEC observer present. Power Operations conducts internal testing, equipment testing and repairs in preparation for the certified tests.

The estimated total five-year cost is \$1.1 million.

Separations

- **Canyon Stack Testing for NO_x**—SCDHEC air permits for the F and H Area canyon stacks require that compliance testing for NO_x be conducted as part of the permit renewal process. Stack testing may be required in 1989 and in 1992.

The estimated total five-year cost is \$250,000.

Defense Waste Processing Facility (DWPF)

- **DWPF Stack Monitoring**—A continuous stack monitoring program will be initiated when DWPF starts up. Benzene, mercury and NO_x will be monitored in the S-Zone 1 and mercury in S-Zone 2. Opacity will be monitored in the Z-Zone. This program will provide essential operating data and information on air emissions.

The estimated total five-year cost is \$81,750. Milestones include:

Start S-Zone monitoring

09/89

7.0 ATMOSPHERIC PROTECTION PROGRAM

7.6.4 Radioactive Emissions Management

The Savannah River Site (SRS) radioactive emissions management program is conducted to achieve the objectives stated in Section 7.4, to meet the as low as reasonably achievable (ALARA) goals, and to identify ways to further reduce emissions per unit of production.

7.6.4.1 Site Program Overview

The SRS radioactive emissions management program is based on the ALARA principle. To achieve the lowest emission rates, annual radiological release guides are set for the site and each operating facility. These guides are based on past performance, projected production rates and planned improvements in emission control. Progress is measured against these guides monthly and appropriate action is initiated if emissions approach or exceed prorated goals.

The Environmental Monitoring Section (EMS) conducts extensive routine monitoring programs to measure emissions of radioactivity from individual facilities and operating areas, and to measure impacts at selected onsite, perimeter, and offsite locations. These data are used to measure success in meeting release guides and to calculate radiation doses. The Environmental Technology Section (ETS) of the Savannah River Laboratory (SRL) conducts special monitoring of F- and H-Canyon stacks to determine emissions of radionuclides that are difficult to measure. Monitoring results are included in the annual SRS environmental monitoring report.

Several operating departments have proposed projects to either install new or to upgrade existing equipment to improve monitoring capabilities and accuracy, and to reduce emissions of radioactive emissions. The EMS is in the process of expanding the perimeter monitoring network from 12 to 27 locations; Separations has recently installed a new sand filter for the Plutonium Fabrication Facility (PuFF) and plans to upgrade the A-Line ventilation system; Waste Management has proposed to construct containment buildings for diversion boxes and pump pits.

The total estimated five-year cost for radioactive emissions management is \$59.1 million which includes about 105 (MS) and 239 (LR) man-years of effort.

7.6.4.2 Regulatory Requirements

Construction of new facilities and modification of existing facilities are subject to National Emission Standards for Hazardous Air Pollutants (NESHAP) regulations promulgated by the Environmental Protection Agency (EPA) under Section 112 of the Clean Air Act. Routine emissions will be subject to the NESHAP emission standards and the requirements of Department of Energy (DOE) Order 5480.12 which is under revision. These requirements include emission levels and dose limits as established by International Committee on Radiation Protection (ICRP). These are the same standards accepted by the Nuclear Regulatory Commission (NRC). They include:

- National Emission Standards for Hazardous Air Pollutants, 40 CFR 61, Subpart H, National Emission Standard for Radionuclide Emissions from DOE Facilities.

7.6.4.3 Organizational Responsibilities Summary

Operating departments are responsible for the radioactive air emissions from their facilities. Facilities must be operated to maintain radioactive emissions based on the ALARA principle and meet applicable Radiological Release Guides. Raw Materials, Reactors and Separations set guides for their operating areas based on planned improvements, past performance and projected production rates. Site guides are set annually by the EMS. Routine monitoring for radionuclides is carried out by the EMS.

7.6.4.4 Programs

Operating departments at the SRS have either proposed or undertaken the following programs to better understand processes and their environmental impacts. These programs have specific immediate or near-term objectives.

Air Emissions Inventory

Environmental Protection Section (EPS)—The EPS has initiated a program to identify and characterize all point and fugitive emissions sources at the SRS. The program, which includes both radioactive and nonradioactive emissions, is discussed in Section 7.6.3.4.

Annual Radiological Release Guides

Environmental and Health Protection—Annual site release guides for radionuclides are authorized by the Vice President, Environmental, Safety, Health and Quality Assurance (ESH & QA) based on recommendations by the Site Release Practices ALARA Guides, and Monitoring Committee. Approved guides are documented in DPSOP 40. The guides are based on operations and production experience and are set to the lowest practical level. The EMS is responsible for a comprehensive monitoring program to measure releases of radionuclides to all media. Any abnormal condition or guide exception is reported to the appropriate operating department which will initiate appropriate action to reduce emissions.

The estimated total five-year cost is \$597,500.

Raw Materials (RM)—RM evaluates the type and quantity of reactor components to be produced and their impact on radionuclide releases in developing annual release guides. Recommended guides are sent to the EMS for final review and inclusion in DPSOP 40. RM is responsible for issuing notifications for all radioactive releases in excess of their annual guides.

The estimated total five-year cost is \$5,950.

Reactors—A Reactors *ad hoc* committee develops annual ALARA release guides based on production rates, production subcycles and fuel cycles. The recommended guides are reviewed by the 100 Area Environmental Committee before submission to the EMS for final review and inclusion in DPSOP 40. Reactors is responsible for issuing notifications for all radioactive releases in excess of their annual ALARA guides.

The estimated total five-year cost is \$32,250.

Separations—The Separations Environmental Coordinator chairs the 200-Area release guide committee which develops annual radioactive release guides based on production rates, irradiation time and age of targets or fuel elements processed, and past experiences. The recommended release guides are submitted to the EMS for final review and inclusion in DPSOP 40. Separations is responsible for getting responsible departments to issue notifications for radioactive releases in excess of their annual guides in the 200 areas.

The estimated total five-year cost is \$13,400.

Reduction of M Area Emissions

Raw Materials (RM)—A program to identify and implement improved control of radioactive emissions to the atmosphere from Buildings 313-M and 321-M has been proposed by RM.

The estimated capital cost is \$60,000. The estimated total five-year cost is \$256,350. Milestones are:

Initiate monitoring review program	10/89
Develop upgrade program	10/90
Complete program	10/91

7.6.4.5 Facility Operations

Raw Materials (RM)

• **M Area Emission Control**—Atmospheric emissions of radionuclides from 321-M are controlled with high efficiency particulate air (HEPA) filters. Most process air emissions are monitored daily using continuous filter paper samplers and process conditions are adjusted if releases increase. Particulate filters are not used on vents from 313-M because of the low potential for releases.

The estimated total five-year cost is \$860,030.

Naval Fuel (NF).

● **Naval Fuel Emission Control**—A total containment concept is used in NF to minimize employee exposure and radioactive emissions. Process equipment is contained in wet or dry cabinets, fume hoods or other enclosures. Individual processes have either HEPA or sintered metal filters to remove particulate radionuclides. Building 247-F is divided into three areas that are interconnected through air locks and have separate ventilation systems with high efficiency particulate air (HEPA) filters which are vented to the atmosphere through a 108 foot stack. Maintenance activities include changing HEPA and sintered metal filters, inspecting air locks and measuring pressure drops across ventilation systems.

The estimated total five-year cost is \$12,975.

Reactors

● **Reactors Emission Control - 105-K, L, and P**—Employee exposure and radioactive emissions from SRS reactors are controlled by using a once through negative ventilation system (100,000 cfm) designed to move air from employee occupied areas to radiation zones and through a filter system before being discharged to the atmosphere from 200 foot stacks. The filter system consists of: moisture separators to remove water containing tritium, HEPA filters to remove particulates, and activated carbon filters impregnated with potassium iodide and ethylenediaminetetraacetic (EDTA) to remove halogens. Noble gas isotopes, Carbon-14 (C-14) contained in carbon dioxide and some tritium are not removed. Online Kanne chambers, which monitor tritium in various parts of the 105 buildings, will alert personnel to possible equipment malfunctions or leakage of tritiated heavy water from the reactor cooling system. The filter system and Kanne monitors are maintained on frequencies specified in written procedures.

Estimated total five-year cost is \$982,500.

Separations

● **Separations Areas Emission Control**—Employee exposure and radioactive emissions from the F and H Area Canyons are controlled by using a once through negative ventilation system designed to move air from employee occupied areas to radiation zones and through a filter system before being discharged to the atmosphere from 200 foot stacks.

Dissolver offgases are passed through an iodine absorber, a fiberglass filter, and in 221-F an acid recovery column before being discharged to the stack. Exhausts from other Separations facilities are passed through either a sand or HEPA filter before being released. Maintenance activities include changing HEPA filters and silver iodine absorbers, inspection and repair of sand filters, and measuring pressure drops across ventilation systems.

The estimated total five-year cost is \$382,000.

Separations monitors emission trends for process areas, and assist facility personnel in determining the cause of any abnormal condition or guide exceptions and proper corrective actions.

Estimated total five-year cost is \$32,250.

SRL - Laboratory Services Section (Tech)

● **SRL Ventilation Systems**—The SRL conducts bench and small scale manufacturing activities, process development and chemical research involving radionuclides. Engineering controls and air flow filtration are used to control atmospheric emissions of radionuclides. Ventilation air from hoods in the B and C wings of 773-A is exhausted through single stage HEPA filters to 100 ft. stacks. Ventilation air flows through a HEPA filter to glove boxes, manipulator cells, and other hot process enclosures, then through a two stage HEPA filter to a sand filter before discharge to a 160 ft. stack. Routine maintenance activities include changing HEPA filters, inspection and repair of sand filters, and measuring pressure drops across ventilation systems. These three stacks are also continuously monitored for tritium releases.

The estimated total five-year cost is \$816,500.

7.6.4.6 Construction/Modifications

Heavy Water (HW) - Reactors

● **Replace Rework Pumps - 420-D**—The current Heavy Water Rework Unit pumps will be replaced with sealless pumps to reduce losses of tritiated heavy water from seal leaks and seal replacements. This project will reduce losses of heavy water and emissions of tritium to the atmosphere.

The estimated FY90 capital cost is \$150,000. The estimated FY90 total cost is \$155,950.

Raw Materials (RM)

- **Install Air Monitoring System - 321-M**—A system of central air monitors and alarms will be installed to improve the accuracy and effectiveness of the exhaust air monitoring system in building 321-M. This project will improve control of building ventilation and provide better estimates of radionuclides released to the atmosphere.

The estimated FY88 and FY89 capital costs are \$350,000. The estimated FY89 total cost is \$362,925. Milestones include:

Develop basic data	10/87
Design and CAC estimate	08/89
Project authorization	09/89
Project completion	12/90

Reactors

- **Install Berthold Monitors - 105-K, L, and P**—This project was expanded to provide three Berthold tritium monitors (BTM) for each reactor area to improve the accuracy of tritium release estimates and to comply with DOE Order 5480.6.

The additional FY89 capital cost is \$60,000. The estimated total five-year cost is \$274,000. Milestones are:

Project authorization	06/88
Project completion	FY89

- **Upgrade Noble Gas Monitors - 105-K, L and P**—Each reactor stack is equipped with a noble gas monitor to detect and monitor noble gas releases. This project will upgrade the monitors to eliminate problems which have resulted in variations between reactors. The new systems will consist of computer controlled, multi-channel analyzers and high purity germanium detectors. These systems will be used to isotopically monitor noble gas releases.

The estimated FY89 capital cost is \$500,000.

Separations

- **Upgrade A-Line Exhaust System - 221-1F**—The A-line process system is being upgraded to conform with DOE and industry standards. The major emphasis is to replace the HEPA filter housings.

The estimated FY88 and FY89 capital costs are \$1.3 million. The estimated total five-year cost is \$729,450. Milestones are:

Project authorization	09/87
Design	09/87 to 09/87
Procurement	03/88 to 08/88
Construction	11/88 to 09/89
Project completion	09/89

- **Airborne Radiation Removal, Phase I and Phase II**—Airborne Radiation Removal, Part 1. Provide two stages of HEPA filtration for 772-F and the associated fans, motors, ducts, and support facilities. This first phase will permit 50 percent utilization of 772-F (90,000 cfm). The current single stage of HEPA filtration has not prevented stack releases of radioactive material. It is a FY89 line-item project with a total estimated cost of \$7 million. It will only be for procurement and installation of the HEPA filter.

Milestones:

Procurement	FY89
Installation	3rd quarter 89

Airborne Radiation Removal, Part 2. Provide additional HEPA filtration for 772-F to increase air flow to 100 percent (150,000 cfm) and enclose filters inside a building. 100 percent of 772-F utilization is needed for support of the Separations processes. The current single stage of HEPA filtration has not prevented stack releases of radioactive material. This is an FY93 line-item with a total estimated cost of \$3.25 million. It will only be for procurement and installation of the HEPA filter.

Milestones:

Procurement	3rd quarter 92
Installation	3rd quarter 93

• **Improved Waste Handling, 211-F**—The project will provide a new truck unloading building in the 211-F Waste Handling Facility. The proposed building will be designed to completely enclose high- and low-level waste trailers during unloading operations. A ventilation system including HEPA filters and sampling and monitoring capabilities are part of the project. The project will also replace the existing ventilation system on the storage tanks that the waste is transferred to prior to processing. This project is for NESHAP compliance. This is a FY92 through FY95 line-item project with a total estimated cost of \$14.5 million.

• **Upgrade Stack Monitoring Systems - 292-F and H**—The obsolete stack monitoring instrumentation will be replaced with new solid state instrumentation which will require minimum maintenance and provide a higher level of reliability. It is also planned to install sample boxes, piping and equipment to continuously monitor the sand filter for breakthroughs.

The estimated FY 89 through FY 92 capital costs are \$2.0 million.

SRL - Laboratory Services Section (Tech)

• **Expand SRL Sand Filter - 794-A**—The Technical Area radioactive exhaust system is operating at or near capacity. Additional exhaust capacity will be necessary for expansion of radioactive loads in this area.

The estimated total five-year cost is \$106,000. The total estimated capital cost is \$6 million. Milestones are:

Begin planning/design	FY93
Project authorization	FY94
Project completion	FY96

• **Upgrade SRL Radionuclide Air Monitoring System**—The reporting and recording instrumentation in the current monitoring system is obsolete and spare parts are difficult to obtain. A computer based reporting system with instant display is proposed to update the SRL monitoring system to provide complete and dependable data to estimate radionuclide emissions.

The estimated FY92 capital cost is \$1.0 million. The estimated total five-year cost is \$1.5 million. Milestones include:

Start planning/design	FY91
Project authorization	FY92
Project completion	FY93

- **Replace Shielded Area Exhaust System**—The exhaust filtration system for the SRL Mixed Waste Tank facility will be upgraded to conform with DOE and industry standards. The existing HEPA filter housings will be replaced with new double stage bag-in/bag-out filter housings. This is a FY 90 budget item with an estimated cost of \$500,000.

Tritium

- **Improve Tritium Area Stack Monitoring**—Project S-3751, Tritium Stack Samplers, will improve sampling capability and provide real time flow meters for three Tritium Area stacks. It will result in faster and more accurate estimates of tritium releases.

The estimated FY88 and FY91 capital costs are \$350,000. Milestones are:

Project authorization	09/88
Design complete	09/89
Construction	01/90
Project completion	03/91

Waste Management (WM)

- **Diversion Box and Pump Pit Containment - F and H Areas**—This project will provide three buildings to contain radionuclide releases from FDB 4 and FPP 2 & 3 (241-21F), HPP 5 & 6 (241-70H) and HPP 7 (241-21H). The buildings will have HEPA filtered HVAC systems. These facilities are used in the management of high level waste.

7.6.4.7 Research/Studies

SRL - Environmental Technology Section (ETS)

- **Noble Gas and Tritium Forms Study**—The Tracking Radioactive Atmospheric Contamination (TRAC) mobile laboratory is used to study and plot the distribution of tritium and Argon-41 (Ar-41) plumes downwind

of SRS facilities. Routine sampling and analysis for Ar-41 is difficult because of its short half-life (1.83 hours); however with the TRAC laboratory Ar-41 can be measured at distances up to 50 km. Results are used to verify dispersion modeling and dose estimates.

Cost and manpower requirements for this study are included with emergency response use of the TRAC mobile laboratory in Section 7.6.5.8.

7.6.4.8 Monitoring

A number of radioactivity monitoring programs are conducted by various custodial departments in addition to the sitewide monitoring carried out by the EMS. To ensure the quality of measurements, all departments follow guidelines for internal quality control. Accuracy of radioactivity measurements is verified using standards from the National Bureau of Standards or their equivalent. Most counting instruments are calibrated monthly, but may be calibrated at any time if daily background or source counts do not fall within an acceptable range. Performance and calibration histories of each instrument are maintained in logbooks and/or computer files.

In addition to the internal quality control program, SRS participates in two interlaboratory quality assurance programs: the Quality Assurance Division (QAD) program of EPA's Cincinnati Laboratory and the Environmental Measurements Laboratory program of the DOE.

Environmental Monitoring Section (EMS)

• **Ambient Radiological Monitoring Program**—The EMS is responsible for complying with the radiological monitoring and reporting requirements of DOE Orders 5400.1 and 5484.1. An extensive radiological monitoring network has been established with measurements taken at six onsite locations and an additional 12 stations at the site perimeter and 13 stations at a 25-mile radius from the SRS. The stations at the site perimeter and 25 mile radius are located to permit continuing sampling within each 30 degree sector around the SRS. The system is currently being expanded by the addition of 15 more perimeter monitors (see Section 7.6.4.6). An additional four monitoring locations have been established 100 miles from the SRS near high population centers. Sampling procedures are covered by DPSOP 271-1.

Tritium, which accounts for approximately 75 percent of the offsite population dose from atmospheric releases, is the only radionuclide of SRS origin that can be routinely detected offsite. Ambient levels of particulate alpha and beta/gamma emitters are determined by direct count of filter paper samples using a high purity germanium detector. The filter papers and other samples are further analyzed for strontium-89 (Sr-89), strontium-90 (Sr-90), iodine-131 (I-131), plutonium-238 (Pu-238), and plutonium-239 (Pu-239). Analytical requirements are set forth in DPSOP 271-5.

Gross gamma radiation is continuously measured on and offsite using thermoluminescent dosimeters at approximately 340 locations covering an area of 800 square miles. This network will be used to distinguish between SRS emissions and future emissions from Plant Vogtle which is directly across the Savannah River from the SRS.

The estimated five-year capital equipment cost is \$895,000. With expanded perimeter monitoring, the estimated total five-year cost is \$6.5 million.

- **D Area Release Monitoring**—Tritium from leaks of tritiated heavy water in the pump room and the drum handling facility at the Rework Unit are released to the atmosphere through a 70 foot stack with a 13,000 cfm flow. Water vapor is removed by refrigerated condensers to minimize tritium releases. The stack is continuously monitored with a Kanne chamber and dehumidifier water samples are collected for analysis to estimate tritium releases. Continuous filter paper samples are analyzed weekly by the EMS for alpha and gamma emitters.

Monitoring costs are minimal and are included as part of the Heavy Water Rework Facility Costs.

- **M Area Emission Monitoring**—The stacks of the fuel fabrication facility (321-M) are continuously sampled for particulate activity with fiberglass filters. Filters are collected and analyzed weekly by M Area Health Protection personnel. The Metallurgical Laboratory Stack (322-M) is continuously monitored for tritium with a Kanne chamber. Tritium measurements have been negligible.

The estimated five-year capital equipment costs are \$125,000. The estimated total five-year cost is \$864,000.

-
- **Monitoring of Separations Stacks - F and H Areas**—The 200 foot canyon stacks are continuously monitored for alpha and beta/gamma activity, and sampled using fiberglass and charcoal filters. All monitoring systems include alarms for high activity, low and high sampling flow, and counting system failures. The stack monitors for alpha emitters, fission products and radioiodine are source checked weekly to ensure proper response. The alpha monitors are calibrated monthly. The radioiodine and fission product monitors are calibrated annually.

Filter paper samples are changed daily and counted in a local facility for gross alpha and beta/gamma. Charcoal filters are changed weekly. Samples are isotopically analyzed by the EMS using alpha spectrometry, gamma pulse height analysis, and wet chemistry. Iodine-129 is measured by low energy photon counting.

The estimated five-year capital equipment cost is \$364,200. The estimated total five-year cost is \$9 million.

- **Naval Fuel Stack Monitoring**—Atmospheric emissions of radionuclides from the main process stack are controlled with HEPA filters while individual processes use either HEPA or sintered metal filters. Process air emissions are monitored either weekly or monthly using continuous filter paper samplers. The main process stack is continuously monitored with an in-line scintillation detector.

Estimated five-year capital equipment cost is \$137,000. The estimated total five-year cost is \$876,000.

- **Over-Range Protection for F and H Area Stacks**—This program is to provide and maintain over-range protection and alarms for the key stack monitors on 291-F, 291-H and 772-F.

The estimated total five-year cost is \$114,625.

- **Reactor Stack Emissions - 105-K, L, and P**—The 200 foot stacks from each of the reactor buildings are sampled continuously using a dual fiberglass filter to trap particulate matter, followed by an activated charcoal bed to adsorb gases. The stacks are also equipped with a noble gas detector and tritium monitor. All stack sampling systems are calibrated annually using an approved procedure. Response checks are run on the noble gas detector daily.

Noble gas levels are recorded hourly with a remote readout. The fiberglass filters and charcoal samples are surveyed daily for gross alpha and beta/gamma counts in a local counting facility and changed weekly. They are then forwarded to the EMS laboratory for more detailed analyses using gas flow proportional counters and high purity germanium detectors.

The estimated five-year capital cost is \$277,000. The estimated total five-year cost is \$3.4 million.

• **RBOF Emissions Monitoring - 224-H**—Both stacks of the Receiving Basin for Offsite Fuels (RBOF) are continuously monitored and sampled. The Kanne chamber used to monitor tritium is source checked each shift with an external gamma source. The fiberglass filter paper samples are monitored continuously for fission products with a scintillator. Fiberglass and activated charcoal filter samples are changed weekly and counted by the EMS.

The estimated total five-year capital equipment cost is \$8,600. The estimated total five-year cost is \$116,575.

SRL - Environmental Technology Section (ETS)

• **SRL Monitoring of Separations Stacks**—The SRL monitors certain radionuclide emissions from process stacks in the F and H Areas that can not be monitored by on-line equipment or routine laboratory procedures. The ETS uses special collection and analytical procedures to measure carbon-14 (C-14), technetium-99 (Tc-99), iodine-129 (I-129), neptunium-237 (Np-237) and other isotopes. Weekly samples are collected from the canyon stacks and radioassayed using the Ultra-Low Level Counting Facility for C-14 and I-129 concentrations. In FY88 the program was expanded to routinely measure Tc-99 and Np-237 in canyon emissions and I-129 and C-14 in reactor emissions.

The estimated total five-year cost is \$2 million.

• **Tritium Forms Monitoring**—Biological uptake of tritium is dependent on its chemical form. To determine the different forms of tritium that the SRS releases, the SRS continuously samples releases from two Tritium Area stacks to determine emissions of elemental tritium, tritium oxide and tritiated methane. Data from the ETS stack monitoring program are used by the EMS to determine population dose assessments. During

FY89, a similar monitoring system will be installed on the remaining Tritium Area stack (see Section 7.6.4.6).

The estimated total five-year cost is \$359,750.

Laboratories (Lab)

The 772-D Laboratory analyzes samples containing tritium and other nuclides from the heavy water rework unit and the reactor areas. The laboratory stack is sampled continuously to determine releases of tritium and other nuclides from laboratory operations.

Monitoring costs are minimal and are included as part of the laboratory costs.

Defense Waste Processing Facility (DWPF)

- **DWPF Emission Monitoring**—A continuous stack monitoring program will be initiated with the startup of DWPF. Beta/gamma particles, Iodine-129 (I-129) and tritium will be measured on samples from the pump pits, S-Zone 1 and 2, and Z-Area.

The estimated total five-year cost is \$388,750.

SRL - Laboratory Services Section (Tech)

- **SRL Stack Monitoring**—The three Technical Area stacks have continuous on-line sampling and monitoring systems for alpha and beta/gamma emitters including photomultiplier detectors for low levels of alpha and beta radioactivity. Filter paper samples are changed daily, counted locally and forwarded to the Environmental Monitoring Section for more detailed analyses. Activated charcoal filters are changed weekly.

The estimated total five-year cost is \$490,000.

Reactors

- **Tritium Releases from Reactor Operations - 105-K, L, and P**—Each reactor stack is continuously monitored for tritium with a Kanne chamber and a Stack Tritium Monitor (STM) and a Berthold Tritium Monitor (BTM). The Kanne chamber is calibrated monthly with an external gamma source. Tritium releases are calculated daily using results obtained from the electronic stack monitors and four liquid dehumidifier

samples, and data on stack flows and moisture levels. The monitoring systems are maintained by the Reactor Works Engineering Department (see Section 6.4.5).

The estimated total five-year cost is \$229,750.

Separations

- **Isokinetic Stack Samplers, 772-F**—This project will install an isokinetic stack sampling and monitoring system for the 772-F exhaust stack. The system will include the collection device, blower, piping and monitor electronics. This project will bring the 772-F stack monitoring into compliance with DOE Order 5480.1A and ANSI N13.1-1969. This is a FY93 capital equipment project with a total cost of \$2 million.

Milestone: Capital Equipment purchase FY93

Waste Management

- **Constant Air Monitors**—Constant air monitors to be installed at approximately 40 locations on waste storage tanks in F and H Areas. Monitors will be installed on tank purge and annulus exhaust systems that presently do not have constant air monitor systems. There are six capital equipment projects necessary to complete this work of \$1 million each. The first one is funded for FY89. The others are scheduled for FY91 through FY93. The modifications are required by law. This is a FY89 through FY93 capital project with a total estimated cost of \$6 million.

7.0 ATMOSPHERIC PROTECTION PROGRAM

7.6.5 Emergency Response

Emergency response planning must be an integral part of any atmospheric protection plan because of the rapidity with which an atmospheric release can be spread over a large area. The ability to respond to an unplanned atmospheric release of radiation or other pollutant requires rapid recognition that a release is occurring or has occurred, timely characterization of the release, an established monitoring network, real time meteorological data, accurate prediction of plume movement with time, and well thought out and rehearsed response plans.

The Savannah River Site (SRS) emergency response program is designed to meet the objective of Section 7.4 to maintain a real time emergency response system that has both onsite and offsite capabilities. Most aspects of the emergency response program, such as response planning and drills, are beyond the scope of this section of the *Environmental Implementation Plan* (EIP) and are covered in DPSP-89-121-1, *Safety and Health Long Range Plan Savannah River Plant and Laboratory*. This section only covers those emergency response activities that involve detection, characterization and tracking of atmospheric releases which are also applicable to routine emissions.

7.6.5.1 Site Program Overview

The SRS has developed monitoring and predictive systems to detect and track atmospheric releases in near real time. These systems are frequently reviewed and modified to improve their capabilities. The Remote Environmental Monitoring System (REMS) is being expanded to connect most process stack sensors to the meteorological laboratory of the Environmental Technology Section (ETS) so that realtime emission data can be directly used by the various models used to predict plume movements, and pollutant dispersion, interactions and concentrations with time. These models also receive realtime meteorological data from ten instrumented towers and long-term historical data from the Weather Information and Display (WIND) system. A computerized process control system (VANTAGE) is being installed to monitor the various data collection systems.

If the release is significant, the Tracking Radioactive Atmospheric Contamination (TRAC) mobile laboratory may be directed to the predicted plume location to measure radionuclide levels. The TRAC was equipped with a gamma ray terrain monitor in FY88 so that it can measure ground surface contamination. The Savannah River Laboratory (SRL) is also developing a gamma ray detection array which can be quickly mounted on a helicopter to supplement the TRAC laboratory.

While these systems were developed to respond to emergency conditions, they are regularly used in research programs to track and monitor routine releases from SRS facilities. The data obtained from these programs are used to verify and update the various models used to predict plume movements and interactions. This also serves to keep the equipment and operators in a ready state should an emergency occur.

Total estimated five-year cost for emergency response is \$7.9 million which includes 20 (MS) and 21 (LR) man-years of effort valued.

7.6.5.2 Regulatory Requirements

Emergency planning and the ability to respond to releases of radionuclides or other pollutants is required by Title III of the Superfund Amendments and Reauthorization Act of 1986 (SARA) and Department of Energy (DOE) Order 5500.3:

- Title III, EPA Emergency Planning and Notification Rules (40 CFR 355), require all industries in Standard Industry Codes (SIC) 20-39 to participate in local emergency planning and report all releases of hazardous materials to local emergency planning committees. The SRS is in SIC Code 2819.

- DOE Order 5500.3, Reactor and Nonreactor Nuclear Facility Emergency Planning Preparedness and Response Program for Department of Energy Operations, adopted 8-13-81. This order requires the SRS to develop and improve monitoring and meteorological systems to detect, track and assess radiological or other effluent plumes.

7.6.5.3 Organizational Responsibilities

When a release occurs, the area emergency coordinator notifies the Emergency Operating Center (EOC) of the release who in turn notifies the Environmental Monitoring Section (EMS), EPS, operating contractor

management, and DOE, as appropriate. The EMS has the responsibility for defining radiation and toxic material exposure potential to onsite and offsite populations and for advising emergency coordinators and staff of appropriate actions to control exposures. The EPS has the responsibility of ensuring that the DOE and SCDHEC are notified of releases subject to Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) and SARA reporting requirements.

The ETS has the responsibility for prompt characterization of the release and to predict plume movements. The aim is to provide critical information to the proper decision makers at each stage of the emergency and to sampling teams.

7.6.5.4 Programs

Defense Waste Processing Facility (DWPF)

DWPF Emergency Response Training—DWPF is initiating annual, computer-assisted emergency response training aimed at responding to atmospheric releases. The indicated cost includes acquisition of a computer and development of the training program.

The estimated total five-year cost is \$139,500.

7.6.5.5 Facility Operations

Custodial Departments

Departmental Emergency Response—Each department has written procedures that require the EOC to be notified if a significant release occurs. The EOC will notify the EMS, EPS, operating contractor management and DOE as appropriate. The EMS has the responsibility for determining the probability of exposure to onsite and offsite populations and assisting emergency coordinators and staff in controlling exposures. The EPS has the responsibility of ensuring that the DOE and SCDHEC are notified of releases subject to CERCLA and SARA reporting requirements. Training is conducted for personnel in responding to emergency situations.

Cost and manpower requirements for writing procedures are minimal.

SRL - Environmental Technology Section (ETS)

SRS Meteorological Data Base—The ETS operates a system of nine onsite and one offsite instrumented towers to collect real-time meteorological data. Up to 125 data points are collected every 1.5 seconds and compiled using a quality control algorithm. Data summaries are printed hourly to check instrumentation and assess local conditions. The data are stored to provide a permanent climatology record for the SRS. The system is used to support training exercises and is available for possible offsite emergencies. The large online database allows personnel to go back in time as well as predict future conditions when assessing release consequences.

Estimated cost and manpower requirements for operating this system are given in Section 7.6.2.4.

7.6.5.6 Construction Modifications

SRL - Environmental Technology Section (ETS)

Expand Remote Environmental Monitoring System—The Remote Environmental Monitoring System (REMS) is designed to transmit site environmental data to the SRL. Real-time meteorological data from ten instrumented towers, emission data from stack monitors, and monitoring data from site and perimeter monitors are transmitted to the SRS. These data are available for rapidly assessing release consequences. The system is currently being upgraded to improve data interpretation and to add the Tritium Area stack monitors.

The estimated total five-year cost is \$963,750. Milestones include:

Link Tritium Area and L Lake monitors to system	FY87
Link 100 & 200 Areas stack monitors to system	02/88
Project completion	09/92

7.6.5.7 Research/Studies

Research/studies are conducted to improve the ability of the SRS to track releases and to determine their impact on human health and the environment. While these programs are primarily directed towards

emergency response, they help to measure and determine the impact of routine emissions from SRS facilities.

SRL - Environmental Technology Section (ETS)

•Airborne Gamma Ray Monitor

The ETS is designing an airborne gamma ray monitor which will consist of an array of sodium iodide detectors coupled with a simple data logging system that can be easily mounted on a helicopter. If successful this monitor will allow rapid location and plotting of a fission product plume without the terrain restrictions that limit the tracking radioactive atmospheric contamination (TRAC) mobile laboratory. This will allow TRAC to proceed to population centers and begin earlier monitoring and provide more accurate population dose estimates.

The estimated total five-year cost to develop and evaluate the system is \$96,875.

•Mesoscale Atmospheric Transport Study

The Mesoscale Atmospheric Transport Study (MATS) is being conducted to verify and validate atmospheric transport models which will improve early dose consequence, concentration and deposition estimates. The TRAC mobile laboratory and stationary time sequence samplers are being used to trace controlled releases of sulfur hexafluoride from a 60 meter stack. MATS results are also being used to improve environmental sampling programs.

The estimated total five-year cost is \$455,500. Milestones are:

Complete day time tests	FY87
Complete one-half of night time tests	FY88
Complete study	FY90

•Revise WIND Emergency Response Codes

The WIND system is an emergency response system designed to provide real time, predictive, and analytic information on a release to the atmosphere, and to aid in determining protection action for the public. WIND uses stack emission data, real-time meteorological data and either one, two or three dimensional transport and dispersion models to predict

and analyze release consequences. The computer codes are being rewritten using a systems engineering approach to produce a modularized system consisting of independent, many well-documented modules.

A multiple sequential puff release code, 2DPUF, is being developed and will be fully implemented by 1989. The code will utilize both the SRS and National Weather Service Meteorological data from the entire Southeastern United States to improve model accuracy. The Geographic Information System (GIS) will also be integrated into WIND in 1989. The GIS system will superimpose multiple layers of geographic data, such as, population, towns, roads, buildings, to use in calculating doses.

The estimated total five-year cost to maintain and upgrade, as needed, the WIND System is \$3.3 million.

7.6.5.8 Monitoring

•Environmental Monitoring Section

Link Stack Monitors to EOC—The main process stacks in the Reactor and Separations Areas are continuously monitored for radiological releases. In 1988 the EOC was connected to the Remote Environmental Monitoring System (REMS) linking the monitors in C, F, H, K, L, and P Areas to the WIND computer in the SRL. The software interface and system check-out will be completed in early 1989. This will allow the EOC to respond to releases more rapidly.

The estimated total five-year cost is \$99,750.

SRL - Environmental Technology Section (ETS)

•TRAC Mobile Laboratory

The ETS uses the TRAC mobile laboratory to provide near real time measurements of radionuclides that may be routinely or accidentally releases from SRS facilities. The TRAC has been used to monitor controlled releases, determine plume movements and measure downwind concentrations. These data are used to validate dispersion, meteorological, pollutant exchange and transport models.

The TRAC is equipped with tritium and noble gas monitors; airborne particulate and activated carbon canister samplers; high resolution germanium, sodium iodide and solid state surface barrier detectors; a Loran C navigational position system; and radio communication equipment. Improvements completed during FY88 included enhanced computer driven automation of sample collection and analysis and the installation of a gamma ray terrain monitor to measure deposition of radioactivity on ground surfaces.

The estimated five-year cost is \$2 million.

• **VANTAGE System**

VANTAGE is a computerized process control system used to monitor environmental data collection systems. VANTAGE displays real time output from sensors, archives data and triggers alarms when preset levels are exceeded. Various sensors are being added to the systems as REMS connections becomes available.

The estimated total cost is \$888,750. Milestones are:

Link Tritium Area monitors to system	08/87
Link 100 & 200 Areas stack monitors to system	02/88
Program completion	09/92

7.0 ATMOSPHERIC PROTECTION PROGRAM

7.7 Resource Requirements

The manpower and funding requirements for the Atmospheric Protection Program are shown in this section for FY89 through FY93. Manpower requirements (Monthly Salary and Local Roll) over the next five years are 231 man-years and 400 man-years, respectively. The manpower, operating, capital and total cost schedules are presented for each issue in Tables 7.7.1 through 7.7.4. Total funding requirements over the five-year planning period are \$111 million.

Similar schedules of manpower and cost requirements are presented for each department in Appendix Tables 7.7.1A through 7.7.4A.

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
7.0 ATMOSPHERIC PROTECTION
7.7 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 2 of 5

ATMOSPHERIC PROTECTION PROGRAM
7.7 RESOURCE REQUIREMENTS

ISSUE	FY 89		FY 90		FY 91		FY 92		FY 93		TOTAL	
	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR
7.7.1 AIR EMISSIONS PERMITTING	82	0	83	0	83	0	83	0	83	0	417	0
7.7.2 AIR QUALITY ASSESSMENTS	360	202	345	202	315	202	315	202	315	202	1851	1010
7.7.3 NONRAD EMISSIONS MGMT.	1081	921	910	928	921	905	1084	905	1075	905	5050	4554
7.7.4 RADIOACTIVE EMISSIONS MGMT.	1324	1846	1226	1892	1262	1904	1208	1908	1208	1908	6230	9556
7.7.5 EMERGENCY RESPONSE	271	190	259	180	228	160	228	160	226	160	1205	850
TOTAL	3118	3258	2820	3202	2808	3170	2898	3174	2908	3174	14553	15980

* VALUES ARE THOUSANDS OF FY88 DOLLARS.

**ANNUAL MANPOWER COSTS BASED ON: MS = \$59.5M (SR8); LR = \$40M (SR8).

TABLE 7.7.1 MANPOWER REQUIREMENTS SCHEDULE (\$M)*,**

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
7.0 ATMOSPHERIC PROTECTION
7.7 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 3 of 5

ATMOSPHERIC PROTECTION PROGRAM

7.7 RESOURCE REQUIREMENTS

ISSUE	FY 89	FY90	FY91	FY92	FY93	TOTAL
7.7.1 AIR EMISSIONS PERMITTING	0	0	0	0	0	0
7.7.2 AIR QUALITY ASSESSMENTS	1718	1670	1570	1570	1570	8098
7.7.3 NONRAD EMISSIONS MGMT.	2273	1799	1799	1799	1799	9469
7.7.4 RADIOACTIVE EMISSIONS MGMT.	2295	2228	2341	2378	2378	11619
7.7.5 EMERGENCY RESPONSE	1340	1268	1090	1090	1090	5878
TOTAL	7626	6964	6801	6838	6838	35063

* COST ITEMS FOR PROGRAMS, OPERATING COSTS, RTA'S, SAMPLING, ETC., ARE EXPRESSED AS THOUSANDS OF FY89 DOLLARS. THESE COSTS DO NOT INCLUDE MANPOWER COSTS.

TABLE 7.7.2 OPERATING BUDGET SCHEDULE (\$M)*

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
7.0 ATMOSPHERIC PROTECTION
7.7 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 4 of 5

ATMOSPHERIC PROTECTION PROGRAM
7.7 RESOURCE REQUIREMENTS

ISSUE	FY 88	FY 89	FY 90	FY 91	FY 92	FY 93	TOTAL
7.6.1 AIR EMISSIONS PERMITTING	0	0	0	0	0	0	0
7.6.2 AIR QUALITY ASSESSMENTS	23	23	23	23	23	23	115
7.6.3 NONRAD EMISSIONS MGMT.	1655	2155	3580	5855	6155	6155	19200
7.6.4 RADIOACTIVE EMISSIONS MGMT.	7492	4581	2781	3911	7111	7111	25877
7.6.5 EMERGENCY RESPONSE	0	0	0	0	0	0	0
TOTAL	9170	6759	6384	9589	13289	45192	

* CAPITAL ESTIMATES INCLUDE MANPOWER REQUIRED TO SUPPORT CAPITAL PROJECTS;
THESE VALUES, EXPRESSED AS THOUSANDS OF DOLLARS, ARE ESCALATED THROUGH FY 93.

TABLE 7.7.3 CAPITAL BUDGET SCHEDULE (\$M)*

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
7.0 ATMOSPHERIC PROTECTION
7.7 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 5 of 5

ATMOSPHERIC PROTECTION PROGRAM

7.7 RESOURCE REQUIREMENTS

ISSUE	FY 89	FY 90	FY 91	FY 92	FY 93	TOTAL
7.7.1 AIR EMISSIONS PERMITTING	83	83	83	83	83	417
7.7.2 AIR QUALITY ASSESSMENTS	2303	2240	2111	2111	2111	10875
7.7.3 NONRAD EMISSIONS MGMT	5930	5783	7205	9423	9933	38284
7.7.4 RADIOACTIVE EMISSIONS MGMT	13056	9926	8288	9406	12606	53282
7.7.5 EMERGENCY RESPONSE	1801	1704	1478	1478	1476	7933
TOTAL	23173	19746	19183	22499	28209	110790

* INCLUDES MANPOWER COST (7.7.1), OPERATING COST (7.7.2) AND CAPITAL COST (7.7.3)
EXPRESSED AS THOUSANDS OF FY88 DOLLARS.

TABLE 7.7.4 TOTAL EXPENDITURE SCHEDULE (\$M)*

7.0 ATMOSPHERIC PROTECTION PROGRAM

7.8 REFERENCES

- Du Pont ,1986. *Strategic Environmental Plan*. Atomic Energy Division, E. I. du Pont de Nemours and Company, Inc., Wilmington, DE.
- GDNR,1987. *1986 Condensed Statistical Summary for Augusta, Georgia* , Air Quality Evaluation Section, Georgia Department of Natural Resources, Atlanta, GA.
- NUS,1986. *Annual Overview and Status Summary*, Report prepared by NUS Corporation for Department of Energy, Savannah River Operations Office, Aiken, SC.
- SCHDEC,1987. *1986 Ambient Air Quality Data for South Carolina*, Bureau of Air Quality Control, South Carolina Department of Health and Environmental Control, Columbia, SC.
- Zeigler, C.C., I. B. Lawrimore, E. M. Heath and J. E. Till,1986. *Savannah River Plant Environmental Report For 1985*, Report DPSPU-86-30-1, Health Protection Department, E. I. du Pont de Nemours and Company, Inc., Aiken, SC.
- Zeigler, C.C., E. M. Heath, L. B. Taus and J. L. Todd,1987. *Savannah River Plant Environmental Report For 1986*, Report DPSPU-87-30-1, Health Protection Department, E. I. du Pont de Nemours and Company, Inc., Aiken, SC.

7.0 ATMOSPHERIC PROTECTION PROGRAM

ATTACHMENT 7.1 Air Quality Operating and Construction Permits

A Area (permit effective 5/14/87)

AREA/PERMIT ID.	PREVIOUS ID.	DESCRIPTION	BUILDING	ORGANIZATION
0080-0042-01	O/P-02-263	71.7 MBTU Boiler	784-A	Power
0080-0042-02	O/P-02-264	71.7 MBTU Boiler	784-A	Power
0080-0042-03		600 KW Diesel Generator	794-A	SRL
0080-0042-04		400 KW Diesel Generator	773-A	Power
0080-0042-05	0080-0042-CA	200 KW Diesel Generator	703-A	Power
0080-0042-06	0080-0042-CA	400 KW Diesel Generator	503-2A	Power
0080-0042-07	0080-0042-CA	150 KW Diesel Generator	751-A	Power
CONSTRUCTION	0080-0042-CB	250 KW Diesel Generator	754-4A	Power
CONSTRUCTION	0080-0042-CC	455 KW Diesel Generator	720-2A	Wackenhut

ATTA Area

AREA/PERMIT ID.	PREVIOUS ID.	DESCRIPTION	BUILDING	ORGANIZATION
0080-0079-01	0080-0079-CA	180 KW Diesel Generator		

C Area (permit effective 7/28/86)

AREA/PERMIT ID.	PREVIOUS ID.	DESCRIPTION	BUILDING	ORGANIZATION
0080-0043-01	O/P-02-265	43.8x10x6 Boiler		Power
0080-0043-02	O/P-02-266	43.8x10x6 Boiler		Power
0080-0043-03		150 KW Diesel Generator	108-4C	Reactors
0080-0043-04		150 KW Diesel Generator	108-4C	Reactors
0080-0043-05		1000 KW Diesel Generator	108-1C	Reactors
0080-0043-06		1000 KW Diesel Generator	108-2C	Reactors
0080-0043-07	0080-0043-CA	225 KW Diesel Generator	105-C	Power
0080-0043-08	0080-0043-CA	365 KW Diesel Generator	183-2C	Power

D Area (permit effective 8/19/87)

AREA/PERMIT ID.	PREVIOUS ID.	DESCRIPTION	BUILDING	ORGANIZATION
0080-0044-01	O/P-02-267	396 MBTU Boiler	484-D	Power
0080-0044-02	O/P-02-268	396 MBTU Boiler	484-D	Power
0080-0044-03	O/P-02-269	396 MBTU Boiler	484-D	Power
0080-0044-04	O/P-02-270	396 MBTU Boiler	484-D	Power
0080-0044-05		150 KW Diesel Generator	501-D	Power
0080-0044-06		1.1 Ton/hr Rejects System	484-D	Power
0080-0044-07		300 Ton/hr Coal Crusher	484-D	Power

ATTACHMENT 7.1 Air Quality Operating and Construction Permits (Contd)

F Area (permit effective 9/29/88)

AREA/PERMIT ID.	PREVIOUS ID.	DESCRIPTION	BUILDING	ORGANIZATION
0080-0045-01	O/P-02-271	71.7 MBTU Boiler	784-F	Power
0080-0045-02	O/P-02-272	71.7 MBTU Boiler	784-F	Power
0080-0045-03	O/P-02-273	71.7 MBTU Boiler	784-F	Power
0080-0045-04	O/P-02-274	71.7 MBTU Boiler	784-F	Power
0080-0045-05	O/P-02-247 and -248	Uranium Dissolution	221-F	Separations
0080-0045-06	0080-0045-CA	200 KW Diesel Generator	254-5F #1	Power
0080-0045-07	O/P-02-285	200 KW Diesel Generator	254-5F #2	Power
0080-0045-08	0080-0045-CA	175 KW Diesel Generator	772-F #1	Lab
0080-0045-09	0080-0045-CB	175 KW Diesel Generator	772-F #2	Lab
0080-0045-10	0080-0045-CH	350 KW Diesel Generator	241-19F	WM
0080-0045-11	0080-0045-CE	350 KW Diesel Generator	235-F	Separations
0080-0045-12		350 KW Diesel Generator	254-4F	WM
0080-0045-13		250 KW Diesel Generator	254-1F	WM
0080-0045-14		200 KW Diesel Generator	241-74F	WM
0080-0045-15		600 KW Diesel Generator	292-F	Power
0080-0045-16		665 KW Diesel Generator	271-4F	NF
0080-0045-17	0080-0045-CD	315 KW Diesel Generator	221-FB	Separations
0080-0045-18	0080-0045-CC	415 KW Diesel Generator	772-1F	Lab
0080-0045-19		300 KW Diesel Generator	292-2F	Separations
0080-0045-20	0080-0045-CF	300 KW Diesel Generator	254-9F	Lab
0080-0045-21	0080-0045-CD	1000 KW Diesel Generator	221-F	Separations
0080-0045-22		600 KW Diesel Generator	254-10F	Separations
0080-0045-23	0080-0045-CH	350 KW Diesel Generator	254-8F	WM ETF
CONSTRUCTION	0080-0045-CJ	455 KW Diesel Generator	720-F	Wackenhut
CONSTRUCTION	0080-0045-CI	Cement and Fly Ash Silo		

ATTACHMENT 7.1 Air Quality Operating and Construction Permits (Contd)

H Area (permit effective 9/29/88)

AREA/PERMIT ID.	PREVIOUS ID.	DESCRIPTION	BUILDING	ORGANIZATION
0080-0046-01	O/P-02-275	71.7 MBTU Boiler	784-H	Power
0080-0046-02	O/P-02-276	71.7 MBTU Boiler	784-H	Power
0080-0046-03	O/P-02-277	71.7 MBTU Boiler	784-H	Power
0080-0046-04		"O" Waste Incinerator		WM
0080-0046-05	O/P-02-284	Separation Process	221-H	Separations
0080-0046-06		200 KW Diesel Generator	234-4H	Power
0080-0046-07		200 KW Diesel Generator	299-1H	WM
0080-0046-08		200 KW Diesel Generator	241-74H	WM
0080-0046-09		250 KW Diesel Generator	254-1H	WM
0080-0046-10		275 KW Diesel Generator	254-3H	WM
0080-0046-11	0080-0046-CA	300 KW Diesel Generator	221-HB	Separations
0080-0046-12		300 KW Diesel Generator	254-5H #1	Power
0080-0046-13		300 KW Diesel Generator	254-5H #2	Power
0080-0046-14		300 KW Diesel Generator	232-H	Power
0080-0046-15		300 KW Diesel Generator	234-H	Power
0080-0046-16	0080-0046-CB	500 KW Diesel Generator	232-H #2	Tritium
0080-0046-17		500 KW Diesel Generator	254-H	WM
0080-0046-18		600 KW Diesel Generator	292-H	Power
0080-0046-19	0080-0046-CC	000 KW Diesel Generator	221-H	Power
0080-0046-20	0080-0046-CI	500 KW Diesel Generator	254-8H	WM ETF
0080-0046-21	0080-0046-CI	400 KW Diesel Generator	254-9H	WM ETF
CONSTRUCTION	0080-0046-CJ	455 KW Diesel Generator	720-H	Power
CONSTRUCTION	0080-0046-CE	150 KW Diesel Generator	241-96-H	
CONSTRUCTION	0080-0046-CF	1000 KW Diesel Generator		
CONSTRUCTION	0080-0046-CG	765 KW Diesel Generator	233H	
CONSTRUCTION	0080-0046-CH	Fuel Processing Facility		
CONSTRUCTION	0080-0046-CD	Alt. Tanks 48H & 49H		

K Area (permit effective 7/29/87)

AREA/PERMIT ID.	PREVIOUS ID.	DESCRIPTION	BUILDING	ORGANIZATION
0080-0047-01	O/P-02-278	194.5 MBTU Boiler	184-K	Power
0080-0047-02	O/P-02-279	194.5 MBTU Boiler	184-K	Power
0080-0047-03		1000 KW Diesel Generator	108-1K	Reactors
0080-0047-04		1000 KW Diesel Generator	108-2K	Reactors
0080-0047-05		150 KW Diesel Generator	108-4K #1	Reactors
0080-0047-06		150 KW Diesel Generator	108-4K #2	Reactors
0080-0047-07	0080-0047-CA	225 KW Diesel Generator	152-7K	Power
CONSTRUCTION	0080-0047-CA	365 KW Diesel Generator	183-K	Power
CONSTRUCTION	0080-0047-CB	800 KW Diesel Generator	107-A	
CONSTRUCTION	0080-0047-CB	800 KW Diesel Generator	107-B	

L Area (permit effective 7/29/87)

AREA/PERMIT ID.	PREVIOUS ID.	DESCRIPTION	BUILDING	ORGANIZATION
0080-0049-01	O/P-02-355	1000 KW Diesel Generator	108-1L	Reactors
0080-0049-02	O/P-02-355	1000 KW Diesel Generator	108-2L	Reactors
0080-0049-03	O/P-02-354	400 KW Diesel Generator	191-L	Reactors
0080-0049-04		150 KW Diesel Generator	108-4L #1	Reactors
0080-0049-05		150 KW Diesel Generator	108-4L #2	Reactors
0080-0049-06	0080-0049-CA	225 KW Diesel Generator	152-7L	Power
CONSTRUCTION	0080-0049-CA	365 KW Diesel Generator	183-2P	Power

ATTACHMENT 7.1 Air Quality Operating and Construction Permits (Contd)

M Area (permit effective 4/9/86)

AREA/PERMIT ID.	PREVIOUS ID.	DESCRIPTION	BUILDING	ORGANIZATION
0080-0055-01	O/P-02-282	Uranium Metal Cleaning	313-M	Raw Materials
0080-0055-02	O/P-02-283	Aluminum Tube Cleaning	321-M	Raw Materials
0080-0055-04	0080-0055-CB	400GPM Air Stripper		Raw Materials
0080-0055-05	0080-0055-CC	200 KW Diesel Generator	320-M	
CONSTRUCTION	0080-0055-CA	70 GPM Air Stripper	SRL	Raw Materials

P Area (permit effective 7/29/87)

AREA/PERMIT ID.	PREVIOUS ID.	DESCRIPTION	BUILDING	ORGANIZATION
0080-0048-01	O/P-02-280	194.5 MBTU Boiler	184-P	Power
0080-0048-02	O/P-02-281	194.5 MBTU Boiler	184-P	Power
0080-0048-03		1000 KW Diesel Generator	108-1P	Reactors
0080-0048-04		1000 KW Diesel Generator	108-2P	Reactors
0080-0048-05		150 KW Diesel Generator	108-4P	Reactors
0080-0048-06		150 KW Diesel Generator	108-4P	Reactors
0080-0048-07	0080-0048-CA	225 KW Diesel Generator	152-7P	Power
CONSTRUCTION	0080-0048-CA	365 KW Diesel Generator	183-2P	Power

S Area (permit effective 9/29/88)

AREA/PERMIT ID.	PREVIOUS ID.	DESCRIPTION	BUILDING	ORGANIZATION
0080-0066-01	0080-0066-CA	540 Ton Cement Silo		Construction
0080-0066-02	0080-0066-CA	540 Ton Flyash Silo		Construction
0080-0066-03	0080-0066-CA	540 Ton Mixer		Construction
0080-0066-04	0080-0066-CD	84 Ton New Cement Silo		Construction
0080-0066-05	0080-0066-CA	2000 KW Diesel Generator	292-S #1	DWPF
0080-0066-06	0080-0066-CA	2000 KW Diesel Generator	292-S #2	DWPF
CONSTRUCTION	0080-0066-CB	DWPF Vitrification Process	221-S	DWPF
CONSTRUCTION	0080-0066-CC	187 KW Diesel Generator	980-S	DWPF

T Area (permit effective 9/21/88)

AREA/PERMIT ID.	PREVIOUS ID.	DESCRIPTION	BUILDING	ORGANIZATION
0080-0060-01		750 KW Diesel Generator	673-T	SRL
0080-0060-02	0080-0060-CA	300 KW Diesel Generator	673-T	SRL
0080-0060-03	0080-0060-CC	300 KW Diesel Generator	672-T	SRL
0080-0060-04	0080-0060-CB	20 lb Incinerator	677-T	SRL
0080-0060-05	0080-0060-CD	PHEF	682-T	SRL
0080-0060-06	0080-0060-CF	1000 KW Diesel Generator	654-1T	
0080-0060-07	0080-0060-CE	300 KW Diesel Generator	654-T	

Z Area

AREA/PERMIT ID.	PREVIOUS ID.	DESCRIPTION	BUILDING	ORGANIZATION
0080-0080-01	0080-0080-CG	Cement Storage Silo		DWPF
0080-0080-02	0080-0080-CB	Fly Ash Storage Silo		DWPF
0080-0080-03	0080-0080-CC	Weight Hopper		DWPF
0080-0080-04	0080-0080-CD	Two Premix Air Blender		DWPF
0080-0080-05	0080-0080-CE	Premix Feed Storage Bin		DWPF
0080-0080-06	0080-0080-CF	Grout Mixer		DWPF
0080-0080-07	0080-0080-CA	425 KW Diesel Generator		DWPF

8.0 DECONTAMINATION AND DECOMMISSIONING PROGRAM

CONTENTS

8.1 Overview

- 8.1.1 Introduction
- 8.1.2 Summary

8.2 Policy

- 8.2.1 Policy Statement
- 8.2.2 Background for Policy Statement

8.3 Existing Conditions

8.4 Objectives

8.5 Strategy

8.6 Implementation

- 8.6.1 Site Decontamination and Decommissioning Plan
 - 8.6.1.1 Site Program Overview
 - 8.6.1.2 Justification/Regulatory Requirements
 - 8.6.1.3 Organizational Responsibilities Summary
 - 8.6.1.4 Programs
- 8.6.2 Tank 16 Demonstration
 - 8.6.2.1 Site Program Overview
 - 8.6.2.2 Justification/Regulatory Requirements
 - 8.6.2.3 Organizational Responsibilities Summary
 - 8.6.2.4 Programs
 - 8.6.2.5 Projects

8.6.2.6 Research/Studies

8.6.3 Heavy Water Components Test Reactor (HWCTR)

8.6.3.1 Site Program Overview

8.6.3.2 Justification/Regulatory Requirements

8.6.3.3 Organizational Responsibilities Summary

8.6.3.4 Programs

8.6.4 Old HB-Line Decommissioning

8.6.4.1 Site Program Overview

8.6.4.2 Justification/Regulatory Requirements

8.6.4.3 Organizational Responsibilities Summary

8.6.4.4 Programs

8.6.5 Other Decontamination and Decommissioning Projects

8.6.5.1 232-F Tritium Facility

8.6.5.2 284-F Powerhouse

8.6.5.3 412-D Heavy Water Facility

8.6.5.4 Decommission SRL SED I Facility

8.6.5.5 Decommission SRL SED II Facility

8.6.5.6 Decommission SRL CPF Facility

8.6.5.7 R Reactor Support Facilities

8.7 Resource Requirements

8.8 References

8.0 DECONTAMINATION AND DECOMMISSIONING PROGRAM

8.1 Overview

8.1.1 Introduction

Decontamination and Decommissioning (D&D) is defined as actions taken to reduce the potential health and safety impacts of surplus facilities, including actions to remove, reduce, or stabilize radioactive contamination. Of the approximately 3000 site facilities identified by a unique building number, 496 were judged to be radioactively contaminated in a scoping study (Martin, 1986) and will require decommissioning in the future.

D&D as defined does not include waste sites. Waste site closure issues and activities are not addressed in the D&D Program but are addressed in Section 6.6.7 of the Groundwater Protection Program.

8.1.2 Summary

The site D&D activities include the development of a site program plan, compliance with regulatory, Department of Energy (DOE), and operating contractor requirements, and the development of technologies needed to carry out major decommissioning activities. Historically, Savannah River Site (SRS) D&D activities have been directed toward providing space for new facilities in existing buildings. However, the age of the site facilities may require major D&D activities in the near future.

The SRS will develop a site D&D program plan as resources become available. The Environmental Protection Section (EPS) will take the lead in determining D&D organizational responsibilities for a site program plan. The SRS Long-Range Planning Group and the Operational Planning Section will continue to provide long-range planning support until the site program plan is developed.

The site participates in the DOE Surplus Facilities Management Program (UNC Nuclear Industries, 1985). The Heavy Water Components Test Reactor (HWCTR), which has been inactive since 1964, is included in this program. As part of the program, HWCTR is currently monitored and maintained to ensure that radionuclides are contained.

The SRS is actively developing the technologies needed to decontaminate and decommission major site facilities. The Tank 16 stabilization will demonstrate the techniques needed to decommission the other high-level waste tanks. The old HB-Line D&D activities are providing experience in the decommissioning of plutonium processing facilities. Development of a decommissioning plan for HWCTR will begin in FY90.

The total cost for the D&D program during the five-year planning period is estimated at \$50 million. This includes 27 (MS) and 29 (LR) man-years of effort and capital expenditures for the Tank 16 stabilization project of \$7.2 million.

8.0 DECONTAMINATION AND DECOMMISSIONING PROGRAM

8.2 Policy

8.2.1 Policy Statement

The Savannah River Site (SRS) Decontamination and Decommissioning (D&D) policy is to manage surplus facilities in a safe, cost-effective manner that ensures protection of human health and the environment from radiation and hazardous chemicals.

8.2.2 Background for Policy Statement

The United States Department of Energy (DOE) and the operating contractor are committed to operating the SRS in a manner that protects the public health and safety, and the environment. This is documented in DOE Order 5400.1, General Environmental Protection Program, and in the SRS *Strategic Environmental Plan* (Du Pont, 1986). Specific guidance for D&D of surplus facilities is given by DOE Order 5820.2A, Radioactive Waste Management (2-6-84), and the *Surplus Facilities Management Program, Program Plan* (UNI-3560, Office of Surplus Facilities Management, UNC Nuclear Industries, October 1985).

8.0 DECONTAMINATION AND DECOMMISSIONING PROGRAM

8.3 Existing Conditions

Historically, the Savannah River Site (SRS) Decontamination and Decommissioning (D&D) activities have been directed toward providing space for new facilities in existing buildings. Included in the facilities requiring decontamination and decommissioning are the five production reactors, the two chemical separations plants, the fuel fabrication facilities, and the 51 underground high-level waste tanks. Some D&D activity has been or is being conducted on site facilities such as the Building 305-M Test Pile Reactor and the old HB-Line, but little has been done toward the decommissioning of one of the major production facilities.

A long-range D&D scope was transmitted to the Department of Energy (DOE) in June 1986 (Martin, 1986). This scope addressed the decommissioning needs for 496 SRP facilities and projected a FY2045 completion date for all site D&D activities. During 1987, a review of the 735 buildings listed in the DOE Real Property Inventory System (RPIS), as well as buildings not yet added to RPIS, identified 84 buildings as not strategically important to the SRS mission. The review also recommended a disposition action for these buildings (Du Pont, 1987).

The Surplus Facilities Management Program (UNC Nuclear Industries, 1985) is the DOE departmental D&D effort. The Heavy Water Components Test Reactor (HWCTR) is the only SRS facility currently included in this program. HWCTR is currently monitored and maintained to ensure that any radionuclides are contained. A D&D plan was developed in 1975 (Field, 1976) but has not been updated.

The SRS is actively developing and/or demonstrating the technologies needed to decontaminate and decommission major site facilities. The Tank 16 sludge removal demonstration in the late 1970s, the planned decontamination activities of Tank 16, the 1984 removal of the Building 305-M Test Pile, and the old HB-Line D&D activities are examples of recent activities.

8.0 DECONTAMINATION AND DECOMMISSIONING PROGRAM

8.4 Objectives

The objectives listed below are required to meet the Decontamination and Decommissioning (D&D) Program Policy and to meet the intent of the *Strategic Environmental Plan*. The strategy to achieve these objectives is presented in Section 8.5, and the programmatic details are presented in Section 8.6.

- **Requirements**—Comply with federal and state regulations, Department of Energy (DOE) D&D policies, and the operating contractor's environmental philosophy.
- **Long-Range Planning**—Perform the necessary long-term planning for decommissioning surplus facilities to ensure optimum use of site resources.
- **Develop Technology**—Develop new technologies when existing technologies are not applicable or cost-effective for Savannah River Site (SRS) D&D activities.

8.0 DECONTAMINATION AND DECOMMISSIONING PROGRAM

8.5 Strategy

The strategy for reaching the Decontamination and Decommissioning (D&D) Program objectives is to:

- Identify decommissioning needs and the appropriate protection requirements
- Promote innovative and cost-effective means of meeting the requirements through research and development
- Develop decommissioning plans that use the knowledge gained from research and development efforts
- Implement the plans
- Evaluate the effectiveness of the decommissioning activities to ensure that protection requirements are met.

The strategy is illustrated in Figure 8.5-1. Programmatic details are presented in Section 8.6.

FIGURE 8.5-1 DECONTAMINATION AND DECOMMISSIONING PROGRAM STRATEGY

8.0 DECONTAMINATION AND DECOMMISSIONING PROGRAM

8.6 Implementation

This section identifies the issues and those organizations responsible for achieving the defined objectives. Each environmental effort will require funding for one or more of the following: research and development, operations, or construction/modification projects. The resource requirements span a five-year period from FY89 through FY93.

The operating costs used throughout the text are expressed in FY89 dollars and are not escalated. Costs include subcontractor, site manpower, and other expenses drawn by facility operations from operating funds. Capital costs, such as construction and large modification projects, include manpower costs. Total costs include manpower, operating, research and development, subcontractor, and capital costs.

Annual incremental manpower costs are calculated using the following: Savannah River Site (SRS) Monthly Salary (MS) at \$59,500 and all Local Roll (LR) at \$40,000.

8.6.1 Site Decontamination and Decommissioning (D&D) Program

8.6.1.1 Site Program Overview

The SRS has no coordinated sitewide decommissioning plan although the SRS Long-Range Planning Group and the Operational Planning Section have done recent work in this area. Preparation of a sitewide D&D plan will be facilitated by an ad hoc task group, led by the Environmental Protection Section (EPS) in FY89.

8.6.1.2 Justification/Regulatory Requirements

A sitewide program plan for D&D of SRS facilities is needed to provide a structured program to accomplish disposition of all surplus facilities in accordance with site land use policy. The D&D program plan would be supplemented by individual decommissioning project plans as required by DOE Order 5820.2A.

A sitewide D&D program plan supports the long-range planning objective in Section 8.4.

8.6.1.3 Organizational Responsibilities Summary

The SRS has not assigned an organization responsibility for preparing a long-range sitewide decommissioning program. The SRS Long-Range Planning Group has recently done work in this area. The EPS will take the lead in assigning responsibility for a sitewide decommissioning program.

8.6.1.4 Programs

Long-Range Oversight

- **Long-Range Planning (LRP) and Operational Planning Section (OPS)**—Both LRP and OPS will continue to provide long-term planning oversight for D&D of SRS facilities. Additional studies will be undertaken as necessary. Only nominal manpower is required for the oversight function.

Program Plan

- **Environmental Protection Section (EPS)**—During FY89, EPS will chair an ad hoc task team which will develop a comprehensive D&D program plan. The task team will designate the responsible organization for the implementation of the program plan. The team will consider the results of on-site decommissioning demonstrations, the status of robotic development, the compatibility with the waste closure program, and the options for disposal of hazardous, mixed, and low-level waste generated by D&D activities. The program plan will identify effected facilities and provide projected cost estimates and schedules.

The FY89 cost is estimated to be \$129,750.

Nominal manpower for SRS departmental participation in the task team is forecasted for FY89.

8.0 DECONTAMINATION AND DECOMMISSIONING PROGRAM

8.6.2 Tank 16 Demonstration

8.6.2.1 Site Program Overview

Preparations are underway for demonstrating steps to decommission the 51 waste tanks used for interim storage and processing of high-level radioactive waste at the Savannah River Site (SRS). The demonstration involves stabilization of Tank 16 against collapse, accidental release, inadvertent intrusion, etc., (i.e., decommissioning by entombment). The demonstration will be preceded by steps to clean the tank as well as is reasonably achievable and at least to levels which meet criteria for classifying the tank and its contents as low-level radioactive waste. Waste has been removed from the tank itself, but some waste remains in the annulus. Tank cleanup operations are expected to be completed by FY91, and construction activities to stabilize Tank 16 are expected to begin in FY92 if funding is available. The decommissioning schedule is dependent upon the Tank 16 Resource Conservation and Recovery Act (RCRA) Facility Investigation.

8.6.2.2 Justification/Regulatory Requirements

Of the 51 underground tanks for storing high-level waste at SRS, 24 are of early designs (Types I, II, and IV) and have been in service for up to 34 years. During this time, nine of the tanks (including Tank 16) have leaked waste through the primary tank wall. Under current plans the waste will be removed from these tanks and at least 21 of them will be decommissioned before the year 2010. The decommissioning of Tank 16 will provide a demonstration of proposed techniques for decommissioning all 51 waste tanks.

After cleanup, Tank 16 must meet the criteria for low-level radioactive waste because Environmental Protection Agency (EPA) and Nuclear Regulatory Commission (NRC) regulations (i.e., 40 CFR 191 and 10 CFR 60) prohibit disposal of high-level waste except in a licensed geologic repository. All radioactive waste generated during decommissioning will be managed according to the requirements of Department of Energy

(DOE) Order 5820.2A. The Tank 16 decommissioning supports the Requirements and the Technology Development objectives in Section 8.4.

8.6.2.3 Organizational Responsibilities Summary

Previous work has removed most of the waste from the Tank 16 primary vessel and developed plans for further cleanup of the tank annulus and stabilization of the tank prior to final closure. Currently, a project is being prepared for a decommissioning demonstration of Tank 16.

Waste Management will continue to be the lead organization in implementing and assessing the annulus cleanup and the decommissioning demonstration. Other organizations, including the Environmental Monitoring Section (EMS), the Environmental Protection Section (EPS), and the Interim Waste Technology and Environmental Sciences Sections of (IWTS, ESS), will continue to provide support to these activities.

8.6.2.4 Programs

Annulus Cleanup

•**Waste Management (WM)**—As part of ongoing operations, WM will remove leachable waste from the annulus and other hard-to-reach locations with appropriate washes such as oxalic acid followed by water rinses. This activity is expected to take place following removal of waste (sludge) from Tank 15. The Tank 16 annulus is scheduled to be cleaned by the first quarter FY92.

The total five-year operating costs are approximately \$135,975.

8.6.2.5 Projects

Tank 16 Decommissioning Demonstration

•**Waste Management (WM)**—A FY91 cost project is being prepared for the decommissioning demonstration of Tank 16. The project scope focuses on stabilization of Tank 16 and assumes that ongoing WM operations will reduce residual waste in the tank to acceptable levels. The project scope is being re-evaluated. Three alternatives are being studied, with the most costly option being \$15 to \$20 million. The project further assumes that final closure, including covering with topsoil, seeding, etc., will take place following stabilization of the other three tanks (Tanks 13, 14,

and 15) which are located on the same construction pad. Major project actions leading to stabilization of Tank 16 include:

- Cut and cap all lines to Tank 16.
- Remove equipment from the tank top (disposal method is being evaluated).
- Fill both primary and secondary tank vessels with grout/concrete.

Milestones are as follows:

VGA	06/89
CAB	12/90
Project Authorization	04/91

The estimated annual cost to prepare, follow, and implement the project is approximately \$1,580,800.

8.6.2.6 Research/Studies

Tank 16 Demonstration Support

•**SRL-Interim Waste Technology Section (IWTS)**—IWTS reviews proposals and makes recommendations for further cleanup and stabilization of Tank 16. IWTS has prepared a Technical Data Summary (TDS) on Tank 16 which will provide input into the Tank 16 Decommissioning Demonstration Project. IWTS will be responsible for the modeling of groundwater around Tank 16 and other studies as needed to support the decommissioning demonstration.

Key IWTS funding and manpower for support of the Tank 16 demonstration which were completed are:

Issue draft TDS on Tank 16	12/87
Issue final TDS	02/88
Issue subcontractor for modeling studies	10/88

The total five-year cost is \$145,700.

•**SRL-Environmental Sciences Section (ESS)**—A member of ESS provides consultation and technical support to the investigation of groundwater in the vicinity of Tank 16.

The total five-year support cost is \$23,800.

8.0 DECONTAMINATION AND DECOMMISSIONING PROGRAM

8.6.3 Heavy Water Components Test Reactor

8.6.3.1 Site Program Overview

The Heavy Water Components Test Reactor (HWCTR) is the only Savannah River Site (SRS) facility in the DOE Surplus Facilities Management Program (SFMP). The HWCTR has been inactive since 1964 and is currently monitored and maintained to protect human health and the environment. A study is expected to begin in FY90 which will lead to a decommissioning plan for the HWCTR by FY92.

8.6.3.2 Justification/Regulatory Requirements

No regulatory or other legal requirements exist which establish a schedule for decommissioning the HWCTR. However, one of the purposes of the SFMP is to develop programs leading to the ultimate disposition of surplus facilities included in the SFMP. DOE Order 5820.2A and the first priority of the SFMP requires that the HWCTR be monitored and maintained to ensure protection of human health and the environment until final disposition can be implemented.

The HWCTR monitoring program supports the requirements objective in Section 8.4.

8.6.3.3 Organizational Responsibilities Summary

Three SRS organizations are currently involved in the care of the HWCTR:

- Site Engineering and Services Department is the assigned custodian.
- Long-Range Planning (LRP) provides liaison with the SFMP and carries out an oversight role.
- The Reactors Department provides surveillance and maintenance as needed.

The Waste Management Department will involve the above organizations and others as needed when the HWCTR Decommissioning Study is initiated in FY91.

8.6.3.4 Programs

Surveillance and Maintenance

•**Reactors**—Reactors provides ongoing care of the HWCTR to ensure that public health and the environment are protected.

Currently the SFMP provides \$10,000 annually for surveillance and maintenance of the HWCTR in a safe storage mode.

Decommissioning Study

•**Waste Management**—The Waste Management Department plans to begin a three-year study in FY91 leading to a decommissioning plan for the HWCTR. Other departments/divisions will be involved as needed. Decommissioning activities are projected to begin in FY93.

The five-year cost to support the HWCTR Decommissioning Study is \$5.9 million.

8.0 DECONTAMINATION AND DECOMMISSIONING PROGRAM

8.6.4 Old HB-Line Decommissioning

8.6.4.1 Site Program Overview

Decontamination and decommissioning (D&D) of the old HB-Line began in 1984 and was approximately 20 percent complete. Work on the project was temporarily suspended until 1989. The project will resume in FY89 and is projected to be completed in FY94.

Resources which were expended in FY84 through FY86 were \$5 million.

8.6.4.2 Justification/Regulatory Requirements

No regulatory or other legal requirements exist which mandate a schedule for D&D of the old HB-Line. One of the primary purposes of the project is the replacement of old equipment and facilities, and to do so in accordance with Department of Energy (DOE) Order 5820.2A. This order requires proper monitoring and maintenance to ensure protection of human health and the environment until final disposition can be implemented.

The old HB-Line project supports the requirements objective in Section 8.4 as well as the long-range planning objective.

8.6.4.3 Organizational Responsibilities Summary

There are a number of organizations currently involved in the HB-Line project:

- Design is the project management organization.
- Separations is the site custodian.
- Separations Project Department provides liaison with Design.

- Separations Technology Department conducted development work on decontamination agents and procedures with the Savannah River Laboratory (SRL).
- Environmental Monitoring Section provides training and assistance in worker health and safety protection.
- Separations Engineering Department assisted Construction to ensure systems were de-energized prior to the construction.
- Construction performs actual construction work on the project.
- Long-Range Planning provides liaison and oversight to the project.

8.6.4.4 Programs

The old HB-Line project will resume in FY89. The organizations previously listed will again be involved in the necessary activities for decontamination/decommissioning work.

D&D of the old HB-Line is a cost project. The total cost is \$15.5 million; for FY89 through FY93 the project costs are \$8.4 million.

8.0 DECONTAMINATION AND DECOMMISSIONING PROGRAM

8.6.5 Other Decontamination and Decommissioning Projects

8.6.5.1 232-F Tritium Facility

The 232-F Tritium Facility is presently abandoned in place. It was shutdown in 1958. The facility is contaminated and contains asbestos used in steam lines, etc. Although the facility presently does not present a hazard to personnel or the environment, in time it will become a problem as it continues to deteriorate. Also, the facility occupies space in a congested area which could be used for new facilities and programs. The project is proposed for FY92 authorization. The total FY89 through FY95 operating and line-item cost is estimated to be \$10 million.

8.6.5.2 284-F Powerhouse

The 284-F Powerhouse was shutdown in 1954 and is not need. There is no contamination present, however, asbestos is present as insulation.

The plan is to begin definitive design in FY92. The total FY90 through FY91 operating and line-item cost is estimated to be \$4 million.

8.6.5.3 412-D Heavy Water Facility

Building 412-D and associated facilities are the last of the heavy water production facilities; 412-D and 413-D were dismantled several years ago. The facility has no alternative use. As deterioration progresses, there is an increasing potential hazard due to asbestos. Conceptual design work and basic data development should begin in FY92 or sooner. The total FY92 through FY95 operating and line-item cost is estimated to be \$2.4 million.

8.6.5.4 Decommission SRL SED I Facility

This activity covers the decommissioning and removal of classified experimental equipment from the SRL Technical Area. A more detailed explanation of the activity cannot be provided because of the classified nature of the job. The facility will be returned to service after decommissioning.

The plan is to begin decommissioning in FY90. The total FY90 through FY91 operating cost is estimated to be \$1.5 million.

8.6.5.5 Decommission SRL SED II Facility

This activity cover the decommissioning and removal of classified experimental equipment from the SRL Technical Area. A more detailed explanation of the activity cannot be provided because of the classified nature of the job. The facility will be returned to service after decommissioning.

The plan is to begin decommissioning in FY92. The total FY92 through FY94 operating cost is estimated to be \$3 million.

8.6.5.6 Decommission SRL CPF Facility

This activity covers the decommissioning and removal of equipment used in the californium industrial source packaging facility. The californium program was moved to Oak Ridge. The facility will become usable space after decommissioning.

The plan is to begin work in FY93 and complete by FY96. The total FY93 through FY95 operating cost is estimated to be \$3 million.

8.6.5.7 R Reactor Support Facilities

R Reactor and associated support facilities were shutdown in 1964 and are candidates for D&D. Plans are to D&D these reactors by entombment. Currently the reactor does not present a contamination hazard to personnel or the environment. However, it will eventually have to be decontaminated and decommissioned.

The plan is to begin design and basic data development in FY92. The total FY92 through FY94 operating and line-item cost is estimated to be \$10.1 million.

8.0 DECONTAMINATION AND DECOMMISSIONING PROGRAM

8.7 Resource Requirements

The manpower and funding requirements for the Decontamination and Decommissioning Protection program are shown in this section for FY89 through FY93. Manpower requirements over the next five years are 27 (MS) and 29 (LR) man-years. The manpower, operating, capital and total cost schedules for each issue are presented in Tables 9.7.1 through 9.7.4. Total funding over the five-year planning period is \$50 million.

Similar schedules of manpower and cost requirements are presented for each department in Appendix Tables 9.7.1A through 9.7.4A. About 30 percent of the total budget is required for the Tank 16 decommissioning demonstration.

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
8.0 DECONTAMINATION AND DECOMMISSIONING
8.7 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 2 of 5

DECONTAMINATION & DECOMMISSIONING PROGRAM

8.7 RESOURCE REQUIREMENTS

ISSUE	FY 89		FY 90		FY 91		FY 92		FY 93		TOTAL	
	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR	MS	LR
8.6.1 SITE D&D PLAN	30	0	0	0	0	0	0	0	0	0	30	0
8.6.2 TANK 16 DEMONSTRATION	161	16	155	16	158	56	155	56	152	16	779	160
8.6.3 HMCIR	0	0	0	0	0	0	0	0	0	0	0	0
8.6.4 HB-LINE DECOMMISSIONING	155	200	155	200	155	200	155	200	155	200	774	1000
8.6.5 OTHER D&D PROJECTS	0	0	0	0	0	0	0	0	0	0	0	0
TOTAL	345	216	309	216	312	256	309	256	306	216	1583	1160

*VALUES ARE THOUSANDS OF FY89 DOLLARS.

**ANNUAL MANPOWER COSTS BASED ON: MS = \$59.5M (SRS); L.R. = \$40M (SRS).

TABLE 8.7.1 MANPOWER REQUIREMENTS SCHEDULE (\$M)**

WSRC-RP-89-453
 ENVIRONMENTAL IMPLEMENTATION PLAN
 8.0 DECONTAMINATION AND DECOMMISSIONING
 8.7 Resource Requirements

Rev 0, 8/1/89
 Effective 8/1/89
 Page 3 of 5

DECONTAMINATION & DECOMMISSIONING PROGRAM

8.7 RESOURCE REQUIREMENTS

ISSUE	FY 89	FY90	FY91	FY92	FY93	TOTAL
8.6.1 SITE D&D PLAN	100	0	0	0	0	100
8.6.2 TANK 16 DEMONSTRATION	1472	1497	1447	1422	1422	7260
8.6.3 HWCTR	20	20	120	10	10	180
8.6.4 HB-LINE DECOMMISSIONING	0	0	0	0	0	0
8.6.5 OTHER D&D PROJECTS	760	770	10	1702	3312	6554
TOTAL	2352	2287	1577	3134	4744	14094

* COST ITEMS FOR PROGRAMS, OPERATING COSTS, RTA'S, SAMPLING, ETC., ARE EXPRESSED AS THOUSANDS OF FY89 DOLLARS. THESE COSTS DO NOT INCLUDE MANPOWER COSTS.

8.7.2 OPERATING BUDGET SCHEDULE (\$M)*

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
8.0 DECONTAMINATION AND DECOMMISSIONING
8.7 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 4 of 5

DECONTAMINATION & DECOMMISSIONING PROGRAM

8.7 RESOURCE REQUIREMENTS

ISSUE	FY 89	FY90	FY91	FY92	FY93	TOTAL
8.6.1 SITE D&D PLAN	0	0	0	0	0	0
8.6.2 TANK 16 DEMONSTRATION	0	0	2000	2000	3000	7000
8.6.3 HWCTR	0	0	0	2500	3300	5800
8.6.4 HB-LINE DECOMMISSIONING	3500	2500	2500	2500	400	11400
8.6.5 OTHER D&D PROJECTS	0	0	0	3000	6000	9000
TOTAL	3500	2500	4500	10000	12700	33200

* CAPITAL ESTIMATES INCLUDE MANPOWER REQUIRED TO SUPPORT CAPITAL PROJECTS;
THESE VALUES, EXPRESSED AS THOUSANDS OF DOLLARS, ARE ESCALATED THROUGH FY93.

TABLE 8.7.3 CAPITAL BUDGET SCHEDULE (\$M)*

WSRC-RP-89-453
ENVIRONMENTAL IMPLEMENTATION PLAN
8.0 DECONTAMINATION AND DECOMMISSIONING
8.7 Resource Requirements

Rev 0, 8/1/89
Effective 8/1/89
Page 5 of 5

DECONTAMINATION & DECOMMISSIONING PROGRAM

8.7 RESOURCE REQUIREMENTS

ISSUE	FY 89	FY90	FY91	FY92	FY93	TOTAL
8.6.1 SITE D. PLAN	130	0	0	0	0	130
8.6.2 TANK 16 DEMONSTRATION	1649	1668	3661	3633	4590	15199
8.6.3 HWC:TR	20	20	120	2510	3310	5980
8.6.4 HB-LINE DECOMMISSIONING	3853	2853	2853	2853	753	13174
8.6.5 OTHER DAD PROJECTS	760	770	10	4702	9312	15554
TOTAL	8413	5312	8645	13699	17966	50037

* INCLUDES MANPOWER COST (8.7.1), OPERATING COST (8.7.2) AND CAPITAL COST (8.7.3)
EXPRESSED AS THOUSANDS OF FY89 DOLLARS.

TABLE 8.7.4 TOTAL EXPENDITURE SCHEDULE (\$M)*

8.0 DECONTAMINATION AND DECOMMISSIONING PROGRAM

8.8 References

- Du Pont, 1986. *Strategic Environmental Plan*, DPW-86-102, E. I. du Pont de Nemours and Company, Wilmington, DE.
- Du Pont, 1987. *Savannah River Site Strategic Facilities Plan*, DPSP- LRP-87-5-23, E. I. du Pont de Nemours and Company, Savannah River Plant, Aiken, SC.
- Du Pont, 1989. *Savannah River Site Decontamination and Decommissioning Forecast*, DPSP-89-1055, E. I. du Pont de Nemours and Company, Savannah River Plant, Aiken, SC.
- Field, F. R., 1976. *A Decommissioning Plan for the Heavy Water Components Test Reactor*, DPST-75-417, E. I. du Pont de Nemours and Company, Savannah River Laboratory, Aiken, SC.
- Martin, W. P., 1986. *SRP Decontamination and Decommissioning Scoping Study*, DPST-85-793, E. I. du Pont de Nemours and Company, Savannah River Laboratory, Aiken, SC.
- UNC Nuclear Industries, 1985. *Surplus Facilities Management Program - Program Plan*, UNI-3560, Office of Surplus Facilities Management, UNC Nuclear Industries, Richland, WA.

END

DATE
FILMED

3 / 22 / 93