ORNL/CON-323

**OAK RIDGE
NATIONAL
LABORATORY**

MARTIN MARIETTA

**Evaluation of Bonneville's 1988
and 1989 Residential
Weatherization Program: A
Northwest Study of Program
Dynamics**

Marilyn A. Brown
Dennis L. White

**MANAGED BY
MARTIN MARIETTA ENERGY SYSTEMS, INC.
FOR THE UNITED STATES
DEPARTMENT OF ENERGY**

REPRODUCTION OF THIS DOCUMENT IS UNLIMITED

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

ORNL/CON--323

DE93 005500

ENERGY DIVISION

EVALUATION OF BONNEVILLE'S 1988 AND 1989
RESIDENTIAL WEATHERIZATION PROGRAM:
A NORTHWEST STUDY OF PROGRAM DYNAMICS

Marilyn A. Brown
Dennis L. White

Received by OSTI

JAN 26 1993

December 1992

Prepared for
Pam Brandis
Program Evaluation
Office of Energy Resources
Bonneville Power Administration

Prepared by the
Oak Ridge National Laboratory
Oak Ridge, Tennessee 37831-6285
managed by
MARTIN MARIETTA ENERGY SYSTEMS, INC.
for the
U.S. DEPARTMENT OF ENERGY
under contract DE-AC05-84OR21400

MASTER

yp

TABLE OF CONTENTS

LIST OF FIGURES	v
LIST OF TABLES	vi
ABSTRACT	vii
EXECUTIVE SUMMARY	ix
PART I: INTRODUCTION AND RESEARCH PLAN	
1. INTRODUCTION	1.1
1.1 PURPOSE AND OUTLINE OF REPORT	1.1
1.2 BACKGROUND	1.2
2. RESEARCH PLAN	2.1
2.1 SAMPLING	2.1
2.2 DATA COLLECTION	2.2
2.3 WEATHER NORMALIZATION	2.3
2.4 SCREENING CRITERIA	2.5
2.5 UTILITY WEIGHTS	2.8
2.6 ESTIMATION OF ELECTRICITY SAVINGS	2.10
2.7 CALCULATION OF LEVELIZED COSTS	2.11
PART II: THE 1988 PROGRAM	
3. MEASURES RECOMMENDED AND INSTALLED	3.1
3.1 WEATHERIZATION MEASURES	3.1
3.2 WEATHERIZATION COSTS AND ESTIMATED SAVINGS	3.3
4. ENERGY SAVINGS	4.1
4.1 HOUSEHOLD SAVINGS	4.1
4.2 UTILITY-LEVEL SAVINGS	4.5
4.3 OVERALL PROGRAM SAVINGS	4.8
4.4 LEVELIZED COSTS	4.11
PART III: THE 1989 PROGRAM	
5. MEASURES RECOMMENDED AND INSTALLED	5.1
5.1 WEATHERIZATION MEASURES	5.1
5.2 WEATHERIZATION COSTS AND ESTIMATED SAVINGS	5.3
6. ENERGY SAVINGS	6.1
6.1 HOUSEHOLD SAVINGS	6.1
6.2 UTILITY-LEVEL SAVINGS	6.4
6.3 OVERALL PROGRAM SAVINGS	6.6
6.4 LEVELIZED COSTS	6.9

PART IV: DISCUSSION AND CONCLUSIONS

7. COMPARISONS WITH PRIOR BONNEVILLE WEATHERIZATION EVALUATIONS	7.1
7.1 WEATHERIZATION MEASURES	7.1
7.2 WEATHERIZATION COSTS	7.2
7.3 PRERETROFIT ENERGY CONSUMPTION	7.5
7.4 ENERGY SAVINGS	7.6
7.5 LEVELIZED COSTS	7.9
8. CONCLUSIONS AND RECOMMENDATIONS	8.1
8.1 CONCLUSIONS	8.1
8.2 PROGRAMMATIC AND EVALUATION RECOMMENDATIONS	8.2
9. REFERENCES	9.1
10. ACKNOWLEDGMENTS	10.1

APPENDIX A

Comparisons of Estimated, Unweighted Consumption, Based on Smaller vs. Larger Samples

LIST OF FIGURES

Fig. 1.1	Overview of Bonneville's Residential Weatherization Program	1.4
Fig. 2.1.	Map of the Pacific Northwest and the utilities participating in Bonneville's Data Gathering Project	2.2
Fig. 2.2	Consumption profile of a 1988 RWP participant.	2.7
Fig. 4.1.	Annual gross electricity savings for 1988 program participants and nonparticipants one year after weatherization (unweighted)	4.3
Fig. 4.2.	Comparison of audit-estimated savings with actual gross electricity savings one year after weatherization in 1988 (unweighted).	4.4
Fig. 4.3.	Weighted NAC components for 1988 program participants and comparison group	4.9
Fig. 4.4.	Average programwide gross and net energy savings for 1988 program participants and comparison group.	4.10
Fig. 6.1.	Annual gross electricity savings for 1989 program participants and nonparticipants one year after weatherization (unweighted).	6.3
Fig. 6.2.	Comparison of audit-estimated savings with actual gross electricity savings one year after weatherization in 1989 (unweighted).	6.4
Fig. 6.3	Weighted NAC components for 1989 program participants and comparison group	6.7
Fig. 6.4.	Average programwide gross energy savings for 1989 program participants and comparison group	6.8
Fig. 7.1.	Comparisons of regional weatherization costs across Bonneville's weatherization programs.	7.4
Fig. 7.2.	Preretrofit energy consumption of participants, non participants, and comparison groups.	7.7
Fig. 7.3.	Comparison of net electricity savings by participants in Bonneville's weatherization programs.	7.8
Fig. 7.4.	Historic levelized costs of Bonneville's weatherization programs.	7.11

LIST OF TABLES

Table 2.1	Data attrition and sample sizes	2.4
Table 2.2	Utility weights for the 1988 long-term RWP	2.9
Table 2.3	Utility weights for the 1989 long-term RWP	2.9
Table 3.1	Measures installed in the 1988 Residential Weatherization Program	3.2
Table 3.2	Weatherization costs for the 1988 Residential Weatherization Program	3.4
Table 4.1	Comparisons of weighted preretrofit normalized annual consumption for 1988 program participants, nonparticipants	4.1
Table 4.2	Average weather-adjusted electricity consumption and gross electricity savings one year after weatherization, by utility, for the 1988 program	4.5
Table 4.3	Average weather-adjusted electricity consumption and gross electricity savings two years after weatherization, by utility, for the 1988 program	4.6
Table 4.4	Average net electricity savings by utility	4.7
Table 4.5	Weighted average electricity savings for 1988 participants and comparison group	4.11
Table 5.1	Measures installed in the 1989 Residential Weatherization Program	5.2
Table 5.2	Weatherization costs for the 1989 Residential Weatherization Program	5.4
Table 6.1	Comparisons of weighted preretrofit normalized annual consumption for 1989 program participants, nonparticipants, and comparison group	6.2
Table 6.2	Average weather-adjusted electricity consumption and gross electricity savings one year after weatherization, by utility, for the 1989 program	6.5
Table 6.3	Average net electricity savings by utility	6.6
Table 6.4	Weighted average electricity savings for 1989 participants and comparison group	6.7
Table 7.1	Installation rates for categories of RWP measures (weighted)	7.2
Table 7.2	Comparisons of weatherization costs for long-term RWP participants and participants in earlier Bonneville weatherization programs	7.3
Table 7.3	Weatherization costs by source of contribution (in percentages)	7.4
Table 7.4	Preretrofit energy consumption for RWP participants and nonparticipants	7.5
Table 7.5	Average annual electricity savings during postretrofit years	7.7
Table 7.6	Historic Costs and Net Savings of Bonneville's Weatherization Programs	7.10
Table A.1	Unweighted average electricity consumption for 1988 participants and nonparticipants: Larger vs. smaller samples	A.1
Table A.2	Unweighted average electricity consumption for 1989 participants and nonparticipants: Larger vs smaller samples	A.1

ABSTRACT

This study continues the series of evaluations of the Bonneville Power Administration's long-term Residential Weatherization Program (RWP) by examining the energy saved by its 1988 and 1989 participants. The sample of participants for this study was drawn from 10 utilities covering the region's three climate zones. Six of these utilities were included in the 1988 RWP evaluation, and eight of them were included in the 1989 RWP evaluation. This study analyzes data on 356 participating households in 1988, 433 participants in 1989, and a comparison group of 1,170 nonparticipants in 1988 and 1,466 in 1989. Previous evaluations of Bonneville's earlier weatherization programs provide an historic context for analyzing program dynamics.

Selected findings are summarized below:

- The 1988 and 1989 Programs continued Bonneville's historic emphasis on the installation of ceiling and floor insulation and storm windows. In 1988, weatherization costs per home averaged \$2,310 (in 1989-\$), and in 1989 they averaged \$2,320 (including administrative costs of \$400/job). These statistics indicate a reduction in the resources devoted to the typical weatherization job, particularly since the 1986 RWP which averaged \$3,130 (in 1989-\$).
- Between 1981 and 1989, the preretrofit Normalized Annual Consumption of program participants and nonparticipants decreased markedly: (1) from 29,350 kWh/year for 1981 participants to 23,520 and 23,130 for 1988 and 1989 participants and (2) from 25,410 kWh/year for 1981 nonparticipants to 18,830 and 18,300 for 1988 and 1989 nonparticipants. In both 1988 and 1989, RWP participants consumed approximately 20% more electricity prior to weatherization than eligible nonparticipants. This finding is consistent with the results of previous RWP evaluations.
- Estimated net energy savings are 2,180 kWh for the first year after retrofit in 1988. This represents 9.3% of the preretrofit level of Normalized Annual Consumption. Net energy savings of 1,330 kWh (or 6.0%) are estimated for the initial year after weatherization in 1989. These findings indicate a continued downward trend in the savings achieved by Bonneville's weatherization programs; the first-year savings of the 1988 and 1989 Programs are lower than any previously evaluated weatherization program operated by Bonneville.
- Regional levelized costs are 50 and 83 mills/kWh for the 1988 and 1989 programs, respectively. Thus, Bonneville's 1989 Residential Weatherization Program exceeds the Northwest Power Planning Council's cost-effectiveness ceiling of 56 mills/kWh. Bonneville's levelized costs for both programs (33 and 52 mills/year) are considerably lower than the regional costs, reflecting the substantial cost sharing by utilities and consumers.

EXECUTIVE SUMMARY

Over the past decade, the Bonneville Power Administration (Bonneville) has supported one of the largest residential weatherization programs in the United States. In addition to providing free on-site home energy audits to its residential consumers, Bonneville's Residential Weatherization Program (RWP) has offered financial incentives to encourage the installation of cost-effective energy conservation measures. Since 1980, Bonneville has examined the energy saved by its weatherization programs. This report examines the energy impacts of the 1988 and 1989 RWP.

The sample of participants for this study was selected by Bonneville from its Data Gathering Project (DGP) database, which included 10 utilities from the region's three climate zones and three of its four states. Six of these DGP utilities were included in the 1988 RWP evaluation, and eight of them were included in the 1989 RWP evaluation. This update analyzes data on 466 participants in 1988, 610 participants in 1989, and a comparison group of 1,500 nonparticipants. After screening and weather normalizing the electricity consumption data, sample sizes were reduced to 356 and 433 for the two participating groups, and to 1,170 and 1,466 for the corresponding control households, respectively.

Electricity bills were weather-adjusted using the Princeton Scorekeeping Method (PRISM). Normalized Annual Consumption (NAC) was calculated for each participant and comparison group household for which data were available. Gross energy savings were calculated by subtracting a household's NAC for each postretrofit year from its preretrofit NAC. Next, household level data were aggregated and examined at the utility level allowing the calculation of average net savings, which is the difference between gross savings by nonparticipants and participants. Utility-level data were then weighted, based on the extent of each utility's participation in the 1988 and 1989 RWP, resulting in estimates of overall program savings.

Previous evaluations of Bonneville's earlier weatherization programs provide an historic context for analyzing program dynamics. Specific findings are summarized below:

- In both 1988 and 1989, more than 80% of the audit-recommended measures were installed by the RWP. Where there was a considerable disparity between rates of recommendation and installation, the non-installed weatherization measures tended to offer lower-than-average audit-estimated energy savings and greater-than-average costs per kWh of estimated savings (e.g., clock thermostats, sash-mounted windows, and weatherstripping). These findings also characterized previous years of the RWP.
- The 1988 and 1989 Programs continued Bonneville's historic emphasis on the installation of ceiling and floor insulation and storm windows.
- In 1988, weatherization costs per home averaged \$2,310 (in 1989-\$), and in 1989 they averaged \$2,320 (including administrative costs of \$400/job). These statistics indicate a

reduction in the resources devoted to the typical weatherization job, when compared to earlier (pre-1988) years. Resources have declined particularly since the 1986 RWP, which averaged \$3,130 (in 1989-\$). Some of this decrease is undoubtedly due to cost-reduction measures implemented in 1988.

- The utility contribution to RWP costs averaged 3% in both 1988 and 1989, continuing the pattern of utility financial involvement initiated in 1986. The average consumer contribution has increased steadily from 6% in 1982 to 27% and 31% in 1988 and 1989.
- Between 1981 and 1989, the preretrofit Normalized Annual Consumption of program participants and nonparticipants decreased markedly: (1) from 29,350 kWh/year for 1981 participants to 23,520 and 23,130 for 1988 and 1989 participants and (2) from 25,410 kWh/year for 1981 nonparticipants to 18,830 and 18,300 for 1988 and 1989 nonparticipants. In both 1988 and 1989, RWP participants consumed approximately 20% more electricity prior to weatherization than eligible nonparticipants. This finding is consistent with the results of previous RWP evaluations.
- When the nonparticipant group is weighted to mirror the utility-by-utility distribution of participants, the differences in preretrofit consumption levels are reduced, reflecting the fact that program participation tends to be higher in utilities with higher levels of residential consumption. This bias would appear to favor greater program energy savings.
- Estimated gross energy savings are 1,773 kWh (± 288 kWh) for the first year after weatherization in 1988 and 1,274 kWh (± 163 kWh) for the first year after weatherization in 1989¹. Audit-estimated savings were 4,240 and 4,100 kWh/year for the 1988 and 1989 programs. Thus, as is typical of weatherization programs nationwide, only a portion of anticipated savings were realized (42% for the 1988 program and 31% for the 1989 program). On a household-by-household basis, there is little correspondence between audit-estimated savings and actual savings.
- Estimated net energy savings are 2,180 kWh for the first year after retrofit in 1988. This represents 9.3% of the preretrofit level of Normalized Annual Consumption. Net energy savings of 1,330 kWh (or 6.0%) are estimated for the initial year after weatherization in 1989. These findings indicate a continued downward trend in the savings achieved by Bonneville's weatherization programs; the first-year savings of the 1988 and 1989 Programs are lower than any previously evaluated weatherization program operated by Bonneville.
- The net energy savings of 1988 Program participants declined by only 180 kWh (or 8%) from the first to the second year after weatherization. The average year-to-year decline by RWP participants who have been tracked for two or three years after participation beginning with the Pilot Program has been 15%.
- Regional levelized costs are 50 and 83 mills/kWh for the 1988 and 1989 programs, respectively. Thus, Bonneville's 1989 Residential Weatherization Program exceeds the Northwest Power Planning Council's cost-effectiveness ceiling of 56 mills/kWh. Bonneville's

¹ Ranges in parentheses represent the 95% confidence interval.

levelized costs for both programs (33 and 52 mills/year) are considerably lower than the regional costs, reflecting the substantial cost sharing by utilities and consumers.

The report ends with a discussion of three recommendations:

- Bonneville should conduct a comprehensive review of state-of-the-art weatherization technologies and procedures to assess their applicability to its own Residential Weatherization Program.
- Bonneville should improve the audit procedure used in its Residential Weatherization Program.
- Bonneville should continue to evaluate the persistence of RWP energy savings; it should also initiate on-site engineering analysis and household surveying to identify the factors influencing RWP savings decay.

PART I: INTRODUCTION
AND
RESEARCH PLAN

1. INTRODUCTION

Over the past decade, the Bonneville Power Administration (Bonneville) has supported one of the largest residential weatherization programs in the United States. In addition to providing free on-site home energy audits to its residential consumers, Bonneville has offered financial incentives to encourage the installation of cost-effective energy conservation measures. The underlying assumption of Bonneville's weatherization efforts is that installation of retrofit measures will lead to substantial reductions in residential energy use, and that the value of these savings will justify the Bonneville, utility, and household costs of implementation.

To ensure proper assessment of its weatherization program activities, Bonneville has examined several cohorts of program participants, beginning in 1980, and has looked at energy savings one, two, and three years after participation. When conservation resources are being purchased to offset supply resources over an extended planning period, it is important to analyze the durability of program performance and the ability of programs to evolve in response to changing needs. This study represents the latest addition to Bonneville's continuing series of weatherization evaluations by examining the energy saved by its 1988 and 1989 programs (Goeltz, Hirst, and Trumble, 1986; Haeri, 1988; Hirst, et al., 1983a; Hirst, White, and Goeltz, 1985; Hirst, et al., 1985; Horowitz, Bronfman, and Lerman, 1987; Schweitzer, Brown, and White, 1989; White and Brown, 1990).

1.1 PURPOSE AND OUTLINE OF REPORT

The purpose of this study is to provide an impact evaluation of Bonneville's 1988 and 1989 long-term Residential Weatherization Program (RWP). The evaluation reviews the measures installed by the program, weatherization costs, and the actual electricity saved by participants. The results of prior evaluations provide a context and a comparison within which the present results are analyzed, enabling the identification of trends in the program, its participants, and its cost effectiveness.

This report is divided into four parts. Part I provides a history and brief description of Bonneville's RWP (Chapter 1). It also describes the research methodology used here, including data collection and screening techniques, and data analysis methods (Chapter 2). Part II focuses on the 1988 program. It describes the energy conservation measures that were recommended to participants in 1988, and compares these with the measures that were actually installed (Chapter 3). It also presents the results of an analysis of energy savings for the 1988 program, beginning with household-level savings, moving to utility-level savings, and ending with a discussion of overall program costs, savings, and cost effectiveness (Chapter 4). Part III is modeled after part II, only its two chapters describe the 1989

program (Chapters 5 and 6). Part IV compares the findings of this report with the results of prior RWP evaluations (Chapter 7), provides conclusions, and offers recommendations for future programmatic and evaluation activities (Chapter 8).

1.2 BACKGROUND

1.2.1 Program History

Bonneville's residential weatherization efforts were initiated in response to a 1980 federal law that greatly expanded Bonneville's responsibilities for energy planning in the Pacific Northwest (U.S. Congress, 1980). At the time of the Pacific Northwest Electric Power Planning and Conservation Act, Bonneville was projecting a power deficit by the late 1980s. By improving the energy efficiency of the existing stock of electrically heated homes, Bonneville hoped to acquire a significant energy resource to help meet the region's energy needs. The original intent of the program was to retrofit 300,000 homes and generate an annual energy savings of 1.5 million MWh during its 10-year lifetime at a cost of \$480 million (Bonneville, 1982a and b).

Bonneville launched the Residential Weatherization Pilot Program in 1980 (Bonneville, 1980). The Pilot Program was operated through 11 small public utilities located in Idaho, western Montana, Oregon, and Washington, and was a precursor to the subsequent, larger regionwide programs. During its two and a half years of operation, the Pilot Program provided free home energy audits to 7,200 electrically heated households and zero-interest weatherization loans to 4,100 of these participants (Hirst et al. 1983a; Bonneville, 1984).

An Interim Program was offered to the region's private and public utilities in November 1981. It operated for almost two years. In response to owner preferences, the Interim Program encouraged the installation of retrofit measures by offering cash rebates that averaged \$1,330 (or 85% of the total costs) for installation of recommended retrofit measures. Two sets of retrofit measures were included in the Interim Program. All eligible houses could have any of the following measures installed: ceiling insulation, wall insulation, cold- and hot-water pipe insulation, duct insulation, dehumidifiers, and clock thermostats. Only houses meeting the Interim Program's indoor air-quality criteria qualified for the "house-tightening" measures: storm windows, storm doors, caulking, weatherstripping, and outlet and switchplate gaskets. Although all housing types (other than mobile homes) built before 1981 with electric space-heat were eligible, the vast majority of the Interim Program's participants lived in single-family homes and were homeowners. By the time the Interim Program was completed, 96 of 135 eligible utilities had signed up (Eissler, 1984), and the Program had retrofitted 104,000 homes at a total cost to Bonneville of \$157 million.

Having demonstrated that residential weatherization was a significant, steady, and reliable energy resource that could be purchased by Bonneville, a long-term weatherization program was designed to operate through 1990. Bonneville offered the long-term RWP to its contracting utilities in July 1983. The program consisted of a free energy audit and an incentive payment based on the estimated kWh savings. Incentives to non-low-income consumers were initially set at \$0.292 per kWh of estimated first-year energy savings; they were subsequently raised to \$0.32 in late 1985. At the same time, "house-tightening" measures were made available to all program participants, not just those meeting indoor air-quality standards.

In the mid-1980's, program expenditures for weatherizing the homes of non-low-income households declined significantly from \$142 million in FY 1983 to \$40 million in FY 1984, \$41 million in FY 1985, and \$36 million in FY 1986. By 1986 Bonneville forecast an unanticipated power surplus, and its surplus power situation was projected to extend through 2005 or 2010. The value of operating conservation programs through to the end of the decade was therefore questioned.

After a series of public meetings, Bonneville decided to operate the Residential Weatherization Program at a reduced level through FY 1990. Each participating utility was asked to propose the contractual amendments or cost-reduction method that it would use to reduce Bonneville's RWP costs beginning with the 1988 program. (These cost-reduction methods and other features of the 1988 and 1989 programs are described below.) More recently, Bonneville's resource acquisition program has become increasingly decentralized, offering utilities the opportunity to operate DSM programs that are responsive to the particular needs of their customer base.

1.2.2 The 1988 and 1989 Programs

Bonneville developed several options that utilities could implement to reduce programmatic costs in 1988 and 1989. These could be adopted individually or in combination. Two of the options involved contract amendments. The others could be instituted under the existing contract.

The **Dipstick Amendment** included a simplified audit that reduced administrative costs by reducing audit costs and shifting the responsibility for identifying conservation measures to weatherization installers. The amendment also required that homeowners have all of the recommended measures installed, and it reduced the incentive to about 50 percent of the job cost for non-low-income homes.

The **Window Separation Amendment** allowed utilities to remove windows and doors from the list of eligible measures. Windows and doors tend to be costly measures with lengthy payback periods.

The **Reduced Incentive** option enables costs to be reduced by decreasing the average Bonneville incentive per house. This could be achieved by reducing the total dollar amount of the incentive, by

reducing the payment maximum from the current 85 percent of the actual weatherization cost, or by reducing the incentive amount to below the previous level of 32 cents per estimated kWh of savings.

Increased Utility Funds is a cost-reduction method that offsets Bonneville costs by increasing utility expenditures. This can involve utility-operated zero- or low-interest loan programs, increased utility incentives, or the use of utility funds to weatherize additional homes.

Other options and various possible combinations are described by Doyle, Lorberau, and Skumatz (1991). Based on their survey of 16 utilities participating in Bonneville's RWP, the cost-reduction methods can be ordered from most to least frequent as follows: the Window Separation Amendment, Reduced Incentives, Increased Utility Funds, and the Dipstick Amendment.

The 1988 and 1989 programs are perhaps best described in terms of the steps that they typically involve (see Fig. 1.1).

Fig. 1.1 Overview of Bonneville's Residential Weatherization Program

In the case of the Dipstick Amendment, installers perform the simplified audit and inform the homeowner of the total cost of the job and the incentive payment. The utility reviews and approves the bid, the work is completed by the installer, and the utility inspects the job and makes the incentive payment.

With the exception of the various cost-reduction measures described earlier, the long-term RWP as implemented in 1988 and 1989 is similar to the long-term program first implemented in 1983.

2. RESEARCH PLAN

2.1 SAMPLING

The sample of participants for this study was selected by Bonneville from its Data Gathering Project (DGP) database. The DGP was developed and implemented in 1985 to track the cost of weatherization measures and to facilitate evaluation of long-term RWP impacts. The DGP database for evaluating the 1988 program was composed of 7 utilities; in 1989 the database contained information from 10 utilities. Participating DGP utilities were located across the region's three climate zones and in three of its four states -- they were intended to be representative of the entire RWP.

Participating utilities were required to provide worksheet forms to Bonneville, containing data on the types and numbers of recommended and installed measures; the actual costs of the installed measures to the consumer, utility, and Bonneville; and the corresponding audit-estimated savings for each installed measure. If less than 20 residential consumers had retrofit work done in any one month, the utility was required to submit worksheets on each consumer. In the event that more than 20 consumers participated in any one month, a random sample of 20 of those participants was drawn and worksheets were submitted for those selected.

Each utility applied the same random sampling plan (developed by Bonneville) in order to identify a comparison group of eligible, but nonparticipating households. The random sample of nonparticipants was not matched by consumption level or other characteristics to resemble the sample of participants. Nevertheless, by examining the energy consumption of this comparison group over the same study period, it is possible to identify and take into account the effects of regionwide trends in income, energy prices, do-it-yourself retrofitting, and other determinants of energy use. The Princeton Scorekeeping Method (PRISM) is used in this study to control for changes in weather between the pre- and post-weatherization years, as described in Section 2.3.

The present analysis excludes one utility of the 7 DGP members in 1988 (Ravalli), and two utilities of the 10 members in 1989 (Ravalli and Grays Harbor). Due to a major upgrade in the way that Ravalli County Electric Cooperative maintained its consumers' historical billing records, Ravalli was unable to provide any history that occurred before July 1990, without incurring extraordinary costs. Ravalli was therefore removed from the present analysis for both 1988 and 1989. Grays Harbor County PUD was removed from the 1989 analysis due to a lack of billing history information for the preretrofit year.

The 6 members of the DGP in 1988 that were retained for the present analysis were Seattle City Light, Tacoma Public Utilities, the City of Richland, Benton County PUD, Eugene Water & Electric

Board, and Missoula Electric Cooperative. The 8 members of the DGP in 1989 that were retained for the present analysis included these same 6 utilities plus Port Angeles City Light and Clallam County PUD. Figure 2.1 shows the approximate locations of each of these utilities.

Fig. 2.1. Map of the Pacific Northwest and the utilities participating in Bonneville's Data Gathering Project.

2.2 DATA COLLECTION

Utility billing records were obtained from the utilities for the period July 1987 through June 1990, for participants and nonparticipants. Average daily temperature data, for the same period as the billing records, were obtained from the National Oceanic and Atmospheric Administration (NOAA) for weather stations that were located in closest proximity to the utilities.

Since the present study was designed to focus on single-family, non-low-income residential electricity consumers, households not meeting these criteria were removed from the study sample. Furthermore, consumers that had participated in other demand-side management programs or at other times in the RWP were excluded from the study sample. Finally, households were excluded that had received weatherization treatment under the 1988 or 1989 long-term RWP either early (before April 1) or late (after September 30) in the program year. This ensured that both the pre- and postretrofit period contained a complete heating season. Previous research has indicated that no bias is introduced by removing winter retrofits from the analysis (Brandis and Bronfman, 1987), because costs and implementation rates are similar between summer and winter of the same program year.

The pre- and postretrofit periods were defined individually for each participant, based on the date of weatherization. This allows more households to be retained in the analysis than would be the case with the use of a standard pre and post year. For nonparticipants, on the other hand, standard years are used. July 1987 through June 1988, for instance, is the preretrofit year for nonparticipants in the 1988 program. Later July through June years are used for subsequent cohorts. We required that at least two years of billing history (the preretrofit and postretrofit years) be available for each participant and nonparticipant house to be analyzed.

The resulting sample sizes of households with complete bills, by utility, are shown in columns 2, 5, 8, and 11 in Table 2.1. Also shown in this table is the primary cost-reduction method used by each utility.

2.3 WEATHER NORMALIZATION

Weather-normalization via PRISM was applied to the billing records of both participant and nonparticipant households in order to obtain an estimate of electricity use under normal weather conditions. See Fels, 1986, for a detailed discussion of PRISM. The basic assumption of PRISM is that residential energy consumption and outdoor temperature are linearly related. PRISM uses average daily energy consumption and average daily outdoor temperature to fit the following linear model for each housing unit:

$$F_i = a + bH_i(t) + e_i .$$

where,

- F_i = the average daily consumption (kWh) in time interval i ,
- a = the fixed amount of daily consumption (baseload),
- b = the proportional constant amount of daily consumption (space heating),
- H_i = the heating-degree days per day computed to reference temperature t in time interval i ,
- e_i = the random error term.

Table 2.1 Data attrition and sample sizes

Cost-Reduction Method and Utility	Participants					
	Program Year 1988			Program Year 1989		
	Sample (1)	Bills (2)	NACs (3)	Sample (4)	Bills (5)	NACs (6)
Increased Utility Funds: Seattle City Light Tacoma Public Utilities	48 108	46 106	41 79	49 101	49 100	39 88
Reduced Incentives: Grays Harbor County PUD Port Angeles, City of Richland Energy Services	- - 63	- - 61	- - 53	44* 61 64	0 59 62	0 50 52
Dipstick Amendment: Benton County PUD Clallam County PUD	69 -	65 -	59 -	75 45	71 37	69 30
Window Separation Amendment: Missoula Electric Cooperative Ravalli Co. Elec. Cooperative	34 39*	26 0	25 0	43 38*	39 0	21 0
None: Eugene Water & Electric Board	105	101	99	90	87	84
Subtotal	466	406	356	610	500	433
*Data not available.						

Cost-Reduction Method and Utility	Nonparticipants					
	Program Year 1988			Program Year 1989		
	Sample (7)	Bills (8)	NACs (9)	Sample (10)	Bills (11)	NACs (12)
Increased Utility Funds: Seattle City Light Tacoma Public Utilities	575 300	575 486	525 335	575 300	575 486	538 399
Reduced Incentives: Grays Harbor County PUD Port Angeles, City of Richland Energy Services	125* 75 100	0 77 99	0 0 81	125* 75 100	0 77 99	0 56 80
Dipstick Amendment: Benton County PUD Clallam County PUD	125 100	127 104	6 0	125 100	127 104	117 101
Window Separation Amendment: Missoula Electric Cooperative Ravalli Co. Elec. Cooperative	75 75*	82 0	80 0	75 75*	82 0	29 0
None: Eugene Water & Electric Board	150	147	143	150	147	146
Subtotal	1700	1697	1170	1700	1697	1466
*Data not available for these utilities.						

Normalized Annual Consumption (NAC) is then calculated as follows:

$$\text{NAC} = 365a + bH_0(t),$$

where,

365a = the fixed amount of base load electricity consumed by a household in one year,

$H_0(t)$ = the heating-degree days (base t) in a typical year, so that

$bH_0(t)$ = the amount of electricity consumed for space heating, adjusted for long-term outdoor temperatures.

Nearly all of the 26 retrofit measures that could be installed under the 1988 and 1989 long-term RWP were developed to save space-heating electricity use. Hot-water pipe wrap and domestic hot-water heater insulation were eligible retrofit measures that could reduce the baseload, but they were installed infrequently. Thus, one would expect most of the program's impacts to be reflected in the PRISM estimates of space-heating electricity use and savings. The PRISM estimates of space-heating consumption, however, are not as robust as the estimates of weather-adjusted total consumption (NAC) (Fels, Rachlin, and Socolow, 1986). In particular, it has been shown that *nonheating factors* such as the weather-sensitive portion of water heating and seasonal variations in lighting cause PRISM to overestimate space heating (Hwang, 1989). As a result, this report emphasizes NAC as a basis for assessing the impacts of weatherization on electricity use.

2.4 SCREENING CRITERIA

Two different screening criteria were used. The first was quite restrictive, requiring good-fitting PRISM models and resulting in relatively small samples. The screening criteria are similar to those used in previous RWP evaluations. The second screening approach was less restrictive and therefore more inclusive, resulting in larger samples. These criteria deviate somewhat from those used previously, but they are believed to be superior. The specifics are described below.

In the more restrictive, smaller sample, the following three screens were used. First, we removed from analysis any house that used an unusually low amount of electricity (i.e., less than 2,000 kWh in any one year) for whole-house electricity needs including lighting, water heating, and space heating. This criterion is expected to eliminate supplemental or multiple fuel users from the sample. Second, houses whose PRISM estimates of electric space heating were 1,000 kWh or less were removed from the analysis. Their low electric space-heating consumption may be due to factors such as supplemental fuel use, extended vacant periods during the winter season, or changes in occupancy that may have been overlooked. Finally, we removed houses whose model R-squares from PRISM were less than 0.2, thus excluding from the analysis houses whose energy-use patterns are not typical of all-electric residential energy users.

The second, less restrictive and larger sample contains all of the households that are part of the smaller sample, but is expanded by including those households where the covariance of NAC (i.e., the standard error of NAC divided by the NAC estimate) is less than 0.2. According to M. Fels (personal communication), the PRISM model provides a valid estimate of NAC when its covariance is low, even if the R^2 of the model is not statistically significant. Low covariances of NAC characterize households that have relatively flat profiles of electricity consumption; that is, their consumption of electricity does not vary markedly with heating degree days. The following types of households tend to have flat profiles: (1) households that reside in fairly moderate climates; (2) households that have high baseloads of electricity consumption; and (3) households that rely on supplemental heating fuels.

The inclusion of households with low covariances of NAC expands the samples of participants from 324 to 356 in 1988 (or 9.9%) and from 382 to 433 in 1989 (or 13.4%). The samples of nonparticipants are expanded even more, from 1,009 to 1,170 in 1988 (16.0%) and from 1,238 to 1,466 in 1989 (18.4%). These increases suggest that flat profiles are more characteristic of nonparticipants than participants.

The average preretrofit electricity consumption of the larger samples is consistently lower than that of the small samples. (Tables A.1 and A.2 in Appendix A provide these mean values.) Thus, households with low covariances of NAC also tend to have low levels of pre-weatherization electricity consumption. This explains the greater expansion of the nonparticipant samples, compared to the participant samples, when households with low covariances of NAC are included. As illustrated in Appendix A, nonparticipants tend to consume less electricity than RWP participants.

Figure 2.2 provides consumption profiles and PRISM statistics for a program participant from the Missoula Electric Cooperative that failed to be included in the smaller sample, but was retained in the larger sample. The household's first postretrofit year was the problem -- the PRISM model has an R^2 of only 0.06. There is no relationship between heating degree days per day, and daily electricity consumption. The low covariance (9%) reflects the fact that there is little difference in daily electricity consumption across meter-reading periods. Every meter reading period except one ("M") has an average daily electricity consumption that is greater than 32 kWh and less than 42 kWh. The covariance of NAC for the pre-weatherization period is even lower (1%), with consumption values ranging narrowly between 43 and 52 kWh/day. These values suggest a reliable reduction of electricity consumption of approximately 20 to 25%. The estimated preretrofit NAC is 16,953, and the estimated postretrofit NAC is 13,074, a 23% decrease.

The postretrofit consumption profile shown in Fig. 2.2 is typical of the households that were added to the larger sample. Their NAC's appear to adequately reflect their level of usage, even though their

Fig. 2.2 Consumption profile of a 1988 RWP participant.

heating slopes are suspect, and their R^2 's are not statistically significant. Thus, the larger sample is employed in the remaining sections of this report.

The final sample sizes are shown in Columns 3, 6, 9, and 12 of Table 2.1. The total number of 1988 participant households for which savings one year after weatherization could be calculated was 356 (based on six utilities); the total number of 1989 participant households for which savings one year after weatherization could be calculated was 433 (based on eight utilities). The nonparticipant samples are much larger: 1,170 households from six utilities for the 1988 program year, and 1,466 households from eight utilities for the 1989 program year.

As can be seen in Table 2.1, one of the largest causes of attrition was the loss of two utilities that failed to provide any data. The data screening described above resulted in minimal decreases in sample sizes: 12% and 13% losses for the 1988 and 1989 participants, and 31% and 14% losses for the 1988 and 1989 samples of nonparticipants.

2.5 UTILITY WEIGHTS

For a variety of reasons, rates of participation in conservation programs typically vary across utilities, and this is true of Bonneville's Residential Weatherization Program. Among the utilities studied here, participation rates in the 1988 long-term RWP ranged from less than 0.1% for Seattle City Light to 6% for the Eugene Water & Electric Board. As a result, Eugene participants represent 81% of the RWP participants served by the DGP utilities in 1988 (Table 2.2). Eugene's participation rate in 1989 was less than half its 1988 rate, while the other DGP utilities' rates remained fairly constant. While still dominant, Eugene's share of the RWP participants in 1989 declined to 62%.

The distribution of eligible nonparticipants, by utility, differs significantly from the distribution of participants. In the present analysis, more than 56% of the approximately 500,000 households among the DGP-member utilities that were eligible to participate in the 1988 long-term RWP were served by one utility: Seattle City Light. At the other extreme, Missoula Electric Cooperative served less than 2% of the eligible households.

Weights were developed for each utility's participant and nonparticipant groups to reflect the proportionate representation of each group among all the 1988 (and 1989) participants and nonparticipants served by the DGP utilities. For participants, the weighting factor was calculated for each utility based upon the total number of houses retrofit by the utility during calendar year 1988 (or 1989) relative to the total number of houses weatherized by all DGP-member utilities (see Tables 2.2 and 2.3).

Two types of weighting schemes were used for nonparticipants, reflecting the two different purposes of the nonparticipant samples: (1) to characterize the customer base of all households eligible

Table 2.2 Utility weights for the 1988 long-term RWP

Cost-Reduction Method and Utility	Participants		Nonparticipants	
	Total Number of Houses Weatherized	Utility Weight ¹	Total Number of Eligible Households	Utility Weight
Increased Utility Funds: Seattle City Light Tacoma Public Utilities	214 561	0.0437 0.1145	278,724 112,488	0.5623 0.2269
Reduced Incentives: Grays Harbor County PUD Port Angeles, City of Richland Energy Services	- - 18	- - 0.0036	- - 13,259	- - 0.0267
Dipstick Amendment: Benton County PUD Clallam County PUD	63 -	0.0128 -	26,985 -	0.0544 -
Window Separation Amendment: Missoula Electric Cooperative Ravalli Co. Elec. Cooperative	71 x	0.0145 x	6,689 x	0.0135 x
None: Eugene Water & Electric Board	3971	0.8107	57,556	0.1161
Totals	4898	0.9998	495,701	1.0000
"X" = data not provided by utility. "-" = utility did not participate in the Data Gathering Project for the year indicated.				
¹ These same utility weights are used to create a comparison group from the sample of nonparticipants.				

Table 2.3 Utility weights for the 1989 long-term RWP

Cost-Reduction Method and Utility	Participants		Nonparticipants	
	Total Number of Houses Weatherized	Utility Weight ¹	Total Number of Eligible Households	Utility Weight
Increased Utility Funds: Seattle City Light Tacoma Public Utilities	204 623	0.0694 0.2120	284,924 114,119	0.5389 0.2159
Reduced Incentives: Grays Harbor Co. PUD Port Angeles, City of Richland Energy Services	x 105 21	x 0.0357 0.0071	x 7,454 13,200	x 0.0141 0.0250
Dipstick Amendment: Benton County PUD Clallam County PUD	29 77	0.0100 0.0262	26,987 17,139	0.0509 0.0324
Window Separation Amendment: Missoula Electric Cooperative Ravalli Co. Elec. Cooperative	53 x	0.0180 x	6,828 x	0.0130 x
None: Eugene Water & Electric Board	1827	0.6216	58,126	0.1100
Totals	2939	1.0000	528,687	1.0000
"X" = data not provided by utility.				
¹ These same utility weights are used to create a comparison group from the sample of nonparticipants.				

for participation in the RWP (the standard use of weighting found in most RWP studies); and (2) to provide a comparison group for estimating the electricity consumption of program participants (a unique and appropriate application for this study not found in other RWP studies).

To characterize the eligible customer base, a new set of weights were calculated for each utility and each of the two years (Tables 2.2 and 2.3). For the 1988 nonparticipants, the weighting factor for each utility was the utility's share of all eligible nonparticipants, relative to the total number of 1988 nonparticipants among the DGP-member utilities. Because Seattle City Light dominates the population of eligible households, its weight is high (0.56). Weights were calculated in a similar fashion for 1989 nonparticipants, and Seattle's weight is similarly high.

To provide a comparison group for the RWP participants, the nonparticipants are weighted, by specific utility area, using the same weights as the participants. This weighting scheme provides the best estimate of how much electricity the participants would have consumed if they had not had the benefit of participating in the RWP. Thus, for the comparison group, the 1988 nonparticipants in Eugene are weighted heavily (by a weight of 0.51), just like the 1988 Eugene participants. Since most of the RWP participants among the DGP-member utilities are served by Eugene Water and Electric Board, it seems reasonable that nonparticipants in the same utility service area should dominate the estimation of the baseline. The alternative weighing scheme (described in the previous paragraph) would have provided a baseline dominated by Seattle households, to act as a comparison group for participants located primarily in Eugene.

2.6 ESTIMATION OF ELECTRICITY SAVINGS

NACs were calculated for each participant and nonparticipant household for each of the household-years that data were available. Gross energy savings (DNAC or change in NAC) were estimated for each household by subtracting NAC of the first or second postretrofit year (post-NAC) from NAC of the preretrofit year (pre-NAC), where

$$\text{DNAC} = \text{pre-NAC} - \text{post-NAC}.$$

Thus, a positive value for DNAC indicates a reduction in energy use (i.e., energy savings).

Net energy savings — the portion of the savings that can be attributed to the program — were estimated at the utility and program levels. Average DNACs were calculated for each utility for participant and nonparticipant groups, and not on a house-by-house basis. The nonparticipant group average DNACs were then subtracted from the average DNACs for participants. The difference is the average net energy savings per participating household for the specific utility.

At the program level, the average DNAC for participants was calculated by weighting each utility's DNACs using the utility-specific participant weights shown in Tables 2.2 and 2.3. The average DNAC for the comparison group was calculated by weighting each utility's nonparticipant DNAC by the same participant weights. The difference is the average net energy savings per participating household.

2.7 CALCULATION OF LEVELIZED COSTS

In addition to identifying energy savings over time, we also calculate levelized costs for the 1988 and 1989 RWP. Cost levelization is a technique that puts costs on a common basis, allowing comparisons across different retrofits, different markets, and different supply options. Consistent with Bonneville procedures, the following equation was used to calculate the levelized costs of the RWP to the Bonneville region:

$$\text{Levelized costs (mills/kWh)} = \left[\frac{1000 \times (\text{first costs}) \times (\text{composite multiplier})}{(\text{line loss credit}) \times (\text{annual energy savings})} \right]$$

where,

$$\text{composite multiplier} = \frac{[(\text{financing factor}) \times (\text{real levelizing factor})]}{(\text{nominal discount factor})},$$

$$\text{annual energy savings} = \text{first year net savings}.$$

Two types of first costs are considered: (1) regional costs and (2) Bonneville costs. Regional costs are the weighted average costs of weatherization installation (including Bonneville, utility, and consumer contributions) plus \$400 (per participating household) in administration costs. Bonneville costs are the weighted average costs of weatherization installation that were covered by Bonneville incentive funds (i.e., excluding utility and consumer contributions) plus \$400 in administration. Regional levelized costs result from the former, and Bonneville levelized costs result from the latter. The Council recommends a regional cost-effectiveness ceiling of 56 mills (real 1990\$) per kWh. Thus, regional levelized costs will be compared to this ceiling.

The lifetime of the measures is assumed to be 31 years, to be consistent with prior RWP evaluations. The real discount rate is assumed to be 3 percent, the inflation rate is assumed to be 5 percent, the long-term financing rate is assumed to be 8.35 percent, and the levelizing rate is assumed to be 3 percent. The annual energy savings are the net savings achieved one year after weatherization. (Bonneville has recently adopted the assumption of a 20% energy-savings decay over time; however, prior

evaluations have assumed 100% of the first year savings will persist. Thus, 100% of the net savings will be used in the calculations here.) This savings is multiplied by a line loss credit of 1.075, which reflects a 7.5% credit given to conservation programs due to electricity transmission and distribution savings.

PART II: THE 1988 PROGRAM

3. MEASURES RECOMMENDED AND INSTALLED

This chapter reviews the retrofit measures that were recommended and installed by Bonneville's 1988 long-term Residential Weatherization Program. Recommended and installed measures are examined here primarily as a means of understanding the 1988 Program's costs and savings. Comparisons with the 1989 program and previous RWP evaluations are presented in Chapter 7.

3.1 WEATHERIZATION MEASURES

Altogether, the RWP enables the installation of 27 different types of energy conservation measures. A total of 17 of these measures were recommended for installation in at least 1% of the sample of homes weatherized in 1988. Statistics on these 17 measures are provided in Table 3.1. On average, the audits recommended the installation of 5.2 measures per house. An average of 4.3 measures were installed per house, representing almost one measure fewer than was recommended. This is a full 82% of all recommended measures installed in 1988 residences.

There was considerable variation in installation rates across retrofit measures. At one extreme are the 10 types of measures that were installed in fewer than 1% of the homes or not at all (for which statistics are not provided in Table 3.1). These include hydronic piping insulation, crawl space perimeter insulation, exterior perimeter insulation, exterior surface wall insulation, interior- and exterior-surface roof insulation, air-to-air heat exchangers, French doors, floor insulation (exposed), and dehumidifiers. Another five types of measures were installed in fewer than 5% of the homes: vent conversion windows, electrical water heater wraps, floor insulation (basement), water heater pipe insulation, and basement wall insulation (interior).

At the other extreme, ceiling insulation under attics was recommended to 86% of the 1988 RWP participants and was installed in 78% of their homes, representing the measure that was installed most often. The next four most recommended and installed measures were floor insulation (over the crawl space), weatherstripping, caulking, and multiglazed windows.

Some measures were installed in almost all of the homes which needed them, based on audit results. Ceiling, floor, wall, and duct insulation are examples. Other measures were installed in a much smaller proportion of the recommended homes. Examples include clock thermostats, sash-mounted windows, and weatherstripping, where less than 80% of the recommended installations were completed.

Table 3.1 Measures installed in the 1988 Residential Weatherization Program

Measure*	Percent recommended	Percent installed	Amount installed
Ceiling insulation under attic	86	78	1,120
Floor insulation (over crawl space)	74	71	1,150
Weatherstripping	67	52	1.7
Caulking	62	54	1.0
Multiglazed windows	49	43	113
Storm windows	35	29	111
Sliding glass doors	32	29	64
Duct insulation	21	18	133
Sash-mounted storm window	21	10	24
Clock thermostat	20	5	1.0
Wall insulation (exterior cavity)	16	16	604
Wall insulation (unfinished walls)	11	8	193
Floor insulation (basement)	4	2	406
Vent conversion windows	4	4	144
Electrical water heater wrap	3	3	1.0
Basement wall insulation (interior)	2	1	473
Water heater pipe insulation	2	2	56.5
Measure*	Cost per installation (in 1988-\$)	Audit-estimated savings (kWh/year)	Cost per kWh of estimated savings (in 1988-\$)
Ceiling insulation under attic	533	1,176	0.45
Floor insulation (over crawl space)	800	2,158	0.37
Weatherstripping	52	31	1.68
Caulking	59	110	0.54
Multiglazed windows	1,217	1,233	0.99
Storm windows	798	1,303	0.61
Sliding glass doors	483	653	0.74
Duct insulation	286	1,053	0.27
Sash-mounted storm window	172	237	0.73
Clock thermostat	135	237	0.57
Wall insulation (exterior cavity)	454	1,487	0.31
Wall insulation (unfinished walls)	58	586	0.10
Floor insulation (basement)	169	709	0.24
Vent conversion windows	1,145	1,476	0.78
Electrical water heater wrap	32	n/a	n/a
Basement wall insulation (interior)	542	1,642	0.33
Water heater pipe insulation	46	n/a	n/a
*The following measures were installed in fewer than 1% of the homes, if at all: interior- or exterior-surface roof insulation, crawl space perimeter insulation, exterior perimeter insulation, exterior surface wall insulation, hydronic piping insulation, air-to-air heat exchangers, french doors, floor insulation (exposed), or dehumidifiers.			
Source: Sample of 406 homes weatherized in 1988.			

3.2 WEATHERIZATION COSTS AND ESTIMATED SAVINGS

Overall, the average audit-estimated energy savings per house for all recommended measures were 4,680 kWh/year, and audit-estimated savings for installed measures were 4,240 kWh/year. These estimates are based on engineering calculations involving a heat loss model. They will be compared with measured savings based on consumption data in Chapter 4.

One way of analyzing these audit estimates is to compute the percent of potential audit-estimated savings that are associated with installed measures by dividing the audit-estimated savings from installed measures by the audit-estimated savings from recommended measures, and multiplying by 100. The result (91%) indicates two findings: (1) that the installed measures account for a majority of the audit-estimated energy savings, and (2) that households are more likely to install measures that are estimated to achieve greater energy conservation, since overall only 82% of the recommended measures were installed.

Based on actual costs and audit-estimated savings, the energy conservation measures installed by the RWP vary significantly in cost effectiveness. The cost per kWh of estimated savings (in 1988-\$) is lowest for wall insulation (unfinished walls), floor insulation (basement), duct insulation, and wall insulation (exterior cavity). Each of these cost less than \$0.32 per kWh of estimated savings in the first year. At the other extreme, each of the following measures is expected to cost more than \$0.70 per kWh: weatherstripping, windows (multiglazed, vent conversion, and sash-mounted), and sliding glass doors. Recall that windows and doors are excluded from utility programs that elected to reduce costs through the Window Separation Amendment; however, none of the five utilities included in this 1988 RWP evaluation used this cost reduction method.

Table 3.2 presents the average weatherization costs for the 1988 Program and for each of the utilities. For the entire sample, the average, regionally-weighted job cost (excluding administrative costs) was \$1,799 (in 1988-\$). Of these 1988 costs, 70% was reimbursed by Bonneville, 3% was paid by the utility, and the consumer contribution averaged 27%. The \$400 of administrative costs per participant is split approximately equally between Bonneville and participating utilities. Inclusion of these costs raises the utility share to 12% and decreases the Bonneville and consumer contributions to 66% and 22%, respectively.

Average retrofit costs vary greatly across the utilities, as does the distribution of costs across the three contributors: Bonneville, the utility, and the consumer. The utility contributions are greatest for those utilities that elected to decrease Bonneville's RWP costs by increasing utility funds. Total retrofit costs are least for Missoula Electric Cooperative, the only DGP utility employing the Window Separation Amendment to reduce costs.

Table 3.2 Weatherization costs for the 1988 Residential Weatherization Program

Utility (by Cost-Reduction Method)	Average Retrofit Cost (in 1988-\$) ^a	Contributions (in 1988-\$) by:		
		Utility	Consumer	Bonneville
Increased Utility Funds:				
Seattle City Light (46)	874	434	0	439
Tacoma Public Utilities (106)	2,509	67	597	1,846
Reduced Incentives:				
Richland, City of (61)	1,314	0	358	956
Dipstick Amendment:				
Benton County PUD (66)	1,752	0	337	1,415
Window Separation Amendment:				
Missoula Electric Cooperative (26)	555	0	78	477
None:				
Eugene Water & Electric Board (101)	1,725	41	487	1,197
Program Summary^b	1,799	52 (3%)	487 (27%)	1,260 (70%)
^a Excludes administrative costs of \$400. ^b The numbers in this row are weighted by utility. Numbers in parentheses are percentages of the total retrofit cost. Source: 406 participant homes weatherized in 1988.				

4. ENERGY SAVINGS

Based on billing histories provided by the six utilities described in Chapter 2, annual weather-adjusted energy use and savings were estimated. There were 356 participant households in 1988 for which at least two complete years of data were available, allowing the calculation of energy use for one year prior to weatherization and one year afterwards. Two years of complete data also were available for 1,170 nonparticipants. Three years of complete data (one pre- and two postretrofit) were available for smaller numbers of participants (N=315) and nonparticipants (N=1,084).

Once household energy use and gross savings were calculated for the sample of participants and nonparticipants described above, these data were then aggregated and examined at the utility level. Finally, utility savings were weighted, using the participant weights shown in Table 2.2, to allow the identification of *overall* 1988 program savings. Each of these different levels of analysis will be discussed in the following sections, beginning with energy use and savings by individual households.

4.1 HOUSEHOLD SAVINGS

We began by comparing the average weather-adjusted annual electricity consumption of RWP participants and nonparticipants for the year prior to their weatherization (Table 4.1). As with earlier

Table 4.1 Comparisons of weighted preretrofit normalized annual consumption for 1988 program participants, nonparticipants, and comparison group¹

	Participants' mean pre-retrofit NAC	Nonparticipants' mean pre-retrofit NAC	Participants' preretrofit NAC minus nonparticipants' preretrofit NAC	Comparison group's mean preretrofit NAC	Participant's preretrofit NAC minus comparison group's preretrofit NAC
Normalized annual consumption (NAC)	23,521 kWh (4,505)	18,833 kWh (5,425)	4,688 kWh***	20,737 kWh (3,929)	2,784 kWh***
Reference temp. (°F)	60.2 (4.3)	59.8 (5.4)	---	59.8 (3.7)	---
PRISM R ²	0.89 (0.09)	0.86 (0.11)	---	0.86 (0.08)	---
Number of households in sample	356	1,170	---	1,170	---
¹ Participants and nonparticipants shown here are all those households for which at least two complete years of billing data were obtained: the pre-weatherization year and the first year after weatherization. Numbers in parentheses are standard deviations. *** indicates that the difference is significant at the 0.001 level.					

analyses, we found that those households in this sample that participated in the program in 1988 used more electricity prior to weatherization than did the nonparticipants. Table 4.1 shows that the sample of 1988 participants used nearly 4,700 kWh (i.e., 20%) more than the sample of nonparticipants, and that the preretrofit NAC of the two groups is different at the 0.001 significance level.

The average preretrofit NAC of the comparison group is also significantly smaller than that of the average participating household. (Recall that the comparison group is comprised of nonparticipants whose consumption is weighted to reflect the utility-by-utility distribution of participants.) As a result of the weighting scheme, the comparison group's pre-weatherization consumption is greater than that of nonparticipants. This increase over nonparticipants is due to the fact that the comparison group is dominated by nonparticipants located in the Eugene Water and Electric Board's service territory, who consume considerably more electricity than nonparticipating households from the utility that dominates the nonparticipant group -- Seattle City Light. Thus, within the DGP utilities, program participants are drawn at a higher rate from the utilities with higher levels of preretrofit electricity consumption. This bias favors greater energy savings, since preretrofit energy use is a strong positive predictor of savings.

The distribution of gross electricity savings achieved by participating households one year after weatherization is shown in Fig. 4.1. Gross savings are calculated by subtracting postretrofit NAC from preretrofit NAC. If the amount of energy consumed after a home is weatherized is less than was used before, gross savings are positive; if energy use goes up following weatherization, gross savings are negative. The participants' unweighted gross savings for the first year following weatherization have a mean of 2,200 kWh and a standard deviation of 5,039 kWh. These numbers and the accompanying figure indicate that there was a broad range of savings. Indeed, many program participants (30%) used more energy following weatherization than before weatherization. This finding is common to many other evaluations of conservation programs, including earlier assessment of the RWP (Hirst, et al., 1983a).

As shown in Fig. 4.1, nonparticipants also experienced a broad range of energy savings (i.e., changes in consumption), even in the absence of participation in the RWP. In this case, however, the average amount saved was only 317 kWh. The standard deviation was high, at 4,707 kWh, and many households experienced substantial savings (39% reduced energy use), even without being weatherized through the RWP.

Household energy savings are difficult to predict using audit estimates, as shown by Fig. 4.2. Each point on the scatter plot represents an estimate of savings made by the RWP energy audit and actual gross energy savings (based on billing records) achieved one year after the same home was weatherized. The simple Pearson correlation coefficient between the audit estimates and gross savings is only 0.11. Although this is statistically significant at a 0.04 level of significance, the scattered "swarm" of points

Fig. 4.1. Annual gross electricity savings for 1988 program participants and nonparticipants one year after weatherization (unweighted). (Univariate nonparametric kernel density estimator used for smoothing.)

shown in Fig. 4.2 illustrates that on a household-by-household basis, there is little correspondence between audit-estimated and gross energy savings.

In general, audit-estimated savings were much higher than the gross savings. This is frequently experienced by other conservation programs, as well (Hirst, Goeltz, and Trumble, 1989; Nadel and Keating, 1991). In this study, average audit-estimated savings (unweighted) were 3,840 kWh (with a standard deviation of 2,650 kWh). Mean (unweighted) gross savings, however, were only 2,200 kWh

Fig. 4.2. Comparison of audit-estimated savings with actual gross electricity savings one year after weatherization in 1988 (unweighted).

(with a standard deviation of 5,040) for the first year after weatherization. Thus, only 57% of the estimated savings was realized as gross savings during the first postretrofit year. This shortfall decreases somewhat when (unweighted) audit-estimated savings are compared to (unweighted) net savings (which average 2,280 kWh). However, the improvement is modest.

4.2 UTILITY-LEVEL SAVINGS

This section discusses energy use and savings, by utility. Table 4.2 shows preretrofit NAC, as well as NAC and gross energy savings for the first year after weatherization, for each of the six utilities in our sample. This table shows that participants used more energy prior to weatherization than did nonparticipants for five of the six utilities. The exception is Benton County PUD, where there is a small sample of only six nonparticipants available for analysis. The table also shows substantial differences among utilities in average preretrofit consumption for participants and nonparticipants alike; preretrofit

Table 4.2 Average weather-adjusted electricity consumption and gross electricity savings one year after weatherization, by utility, for the 1988 program

Cost-Reduction Method and Utility		Preretrofit NAC ^a	First year postretrofit NAC ^a	First year postretrofit gross electricity savings ^a
Increased Utility Funds:				
Seattle City Light	Participants (41) Nonparticipants (525)	20,305 19,381	17,470 18,942	2,835*** 439*
Tacoma Public Utilities	Participants (79) Nonparticipants (335)	24,260 15,794	22,286 15,161	1,974*** 633*
Reduced Incentives:				
Richland Energy Services	Participants (53) Nonparticipants (81)	23,877 20,467	20,457 19,650	3,420*** 817
Dipstick Amendment:				
Benton County PUD	Participants (59) Nonparticipants (6)	24,315 25,386	22,645 26,224	1,670*** -838
Window Separation Amendment:				
Missoula Electric Cooperative	Participants (25) Nonparticipants (80)	19,684 19,222	17,251 19,235	2,433* -13
None:				
Eugene Water & Electric Board	Participants (99) Nonparticipants (143)	23,519 22,653	21,798 23,573	1,720** -920**
^a Electricity consumption and savings are reported in units of kWh. Gross savings are significantly different from zero at * = 0.1, ** = 0.01, and *** = 0.001 levels of significance.				

NACs vary from 15,800 (for the Tacoma Public Utilities nonparticipants) to 25,400 kWh (for the Benton County PUD nonparticipants).

In aggregate, participants in each of the six utilities experienced positive gross savings during the first year following weatherization. The average gross savings range from 1,700 kWh in Benton County PUD to 3,400 kWh in Richland Energy Services. In three of the six utilities, nonparticipants experienced negative savings (i.e., greater energy use in 1988/89 than in 1987/88). These values range from -920 kWh for the Eugene Water and Electric Board to 817 kWh for Richland Energy Services.

Table 4.3 provides preretrofit NAC plus NAC and gross savings for the *second* year following weatherization, by utility. Savings were calculated by subtracting second-year postretrofit NAC from preretrofit NAC. During this second postretrofit year, average gross savings by participants were positive

Table 4.3 Average weather-adjusted electricity consumption and gross electricity savings two years after weatherization, by utility, for the 1988 program

Cost-Reduction Method and Utility		Preretrofit NAC ^a	Second year postretrofit NAC ^a	Second year postretrofit gross energy savings ^a
Increased Utility Funds:				
Seattle City Light	Participants (24) Nonparticipants (511)	21,938 19,415	18,524 19,594	3,413* -179
Tacoma Public Utilities	Participants (76) Nonparticipants (323)	24,210 16,061	22,981 15,803	1,229* 258
Reduced Incentives:				
Richland Energy Services	Participants (50) Nonparticipants (75)	23,769 20,781	21,684 21,859	2,084** -1,078*
Dipstick Amendment:				
Benton County PUD	Participants (56) Nonparticipants (5)	24,220 28,163	24,485 25,052	-265 3,110*
Window Separation Amendment:				
Missoula Electric Cooperative	Participants (12) Non participants (28)	21,500 20,233	22,995 17,592	-1,495 2,642
None:				
Eugene Water & Electric Board	Participants (97) Nonparticipants (142)	23,534 22,691	22,266 23,857	1,269* -1,166*
^a Electricity consumption and savings are reported in units of kWh. Gross savings are significantly different from zero at * = 0.1, ** = 0.01, and *** = 0.001 levels of significance.				

for four of the six utilities, but were negative for Benton County PUD and Missoula Electric Cooperative (which had a small sample of only 12 participants). Average gross savings by nonparticipants were negative for consumers in three utilities and positive for the other three. Once more, there was considerable variation in gross savings across utilities.

Net energy savings for individual utilities are calculated by subtracting gross savings experienced by nonparticipants from gross savings achieved by participants. Taking the difference between gross savings for these two groups helps control for exogenous influences (such as higher energy prices) that might affect energy behavior by all consumers, in order to isolate the effect of the RWP on participants' energy use. Net savings by utility for all postretrofit years, along with the size of these savings in relation to preretrofit NAC, are given in Table 4.4. All six utilities experienced net savings during the first postretrofit year, and for each utility, net savings are significant at a .10 level or less (often much less). They range from 1,340 kWh (6% of previous energy use) for Tacoma Public Utilities to 2,640 kWh (11% of prior use) for Eugene Water and Electric Board.

Table 4.4 Average net electricity savings by utility

Cost Reduction Method and Utility	First year postretrofit net energy savings	Second year postretrofit net energy savings
Increased Utility Funds:		
Seattle City Light	2,396 (11.8%)	3,592 (16.4%)
Tacoma Public Utilities	1,341 (5.5%)	971 (5.0%)
Reduced Incentives:		
Richland, City of	2,603 (10.9%)	3,162 (13.3%)
Dipstick Amendment:		
Benton County PUD	2,508 (10.3%)	-3,375 (-13.9%)
Window Separation Amendment:		
Missoula Electric Cooperative	2,446 (12.4%)	-4,137 (-19.2%)
None:		
Eugene Water & Electric Board	2,640 (11.2%)	2,435 (10.3%)
Using two-tail t-tests comparing gross savings for participants and nonparticipants, net savings are statistically different from zero at * = 0.1, ** = 0.01, and *** = 0.001 levels of significance, respectively. Parentheses are percentage savings.		

Net energy savings for the second postretrofit year are quite similar to the first year net savings for four of the six utilities. The greatest changes in net savings between the first and second postretrofit years are experienced by Missoula Electric Cooperative (with only 12 participants) and Benton County PUD (with only 5 nonparticipants), where the results are least reliable due to small sample sizes. For the remaining four utilities, net savings during the second year following weatherization range from 5% to 16% of preretrofit NAC.

4.3 OVERALL PROGRAM SAVINGS

After household energy use was aggregated by utility and net savings were calculated, utility-level data were weighted and aggregated to produce estimates of programwide savings. Weighted average electricity consumption for the preretrofit year and the two postretrofit years are shown in Table 4.5, along with their standard deviations.

Programwide gross energy savings are estimated to be 1,773 kWh during the first postretrofit year (or 7.5% of preretrofit energy use) and 1,274 kWh during the second postretrofit year (representing 5.4% of preretrofit energy use). In contrast, the comparison group increased its consumption by 1.9% during the first year after weatherization, and by 3.5% during the second year. This increase is consistent with national trends in electricity consumption per household. Over the past decade, an increasing proportion of consumers are using electricity for cooling and various appliances (e.g., microwave ovens and electronic equipment), thereby raising electricity consumption (Response Analysis, 1991).

The estimate of gross savings for the first year after weatherization is quite precise. Using the standard deviation and sample size shown in Table 4.5, the standard error for participants is estimated to be 147 kWh. This translates into a relative error (i.e., the standard error as a percent of the mean gross savings) of only 8.3% and a 95% confidence interval around the mean gross savings, ranging from 1,485 to 2,061 kWh. The estimate of gross savings for the second postretrofit year, however, is considerably less precise. Its standard error is 200 kWh, which is 15.7% of the estimate of gross savings. Its 95% confidence interval ranges from 882 to 1,666 kWh.

Relative to the audit-estimated savings of 4,240 kWh/year, the actual gross savings are modest. During the first year after weatherization, only 42% of the predicted savings were achieved, and during the second year only 30% were achieved.

Figure 4.3 provides estimates of end-use electricity consumption (i.e., space heat and base load), based on outputs of PRISM. It illustrates that both the total Normalized Annual Consumption and space-heat energy use were relatively constant over the three-year period for the comparison group. For RWP participants, however, both consumption values declined significantly after weatherization. Interestingly,

one and two years after weatherization, the participants' levels of total and space heat consumption approximated that of the comparison group. This suggests that the program has succeeded in transforming the relatively energy-intensive homes of participants into homes with lower and more typical levels of electricity use. One difference between the two groups is that the variation in the energy consumption levels across households in the comparison group appears to be greater than the variation in the post-retrofit consumption of participants.

Fig. 4.3. Weighted NAC components for 1988 program participants and comparison group.

Figure 4.4 illustrates the programwide weighted gross and net savings for the first and second years after weatherization. Programwide total net savings were 2,177 kWh (in 1988/89) and 2,003 kWh (1989/90), one and two years following weatherization. For both years, these net savings represent 9% of preretrofit energy use (Table 4.5).

Fig. 4.4. Average programwide gross and net energy savings for 1988 program participants and comparison group.

Table 4.5 Weighted average electricity savings for 1988 participants and comparison group

		Pre-weatherization energy use	Total gross savings ¹	Total gross savings as % of pre-weatherization energy use	Total net savings	Total net savings as % of pre-weatherization energy use
One year after weatherization	Participants (N=356)	23,521 (4,505)	1,773*** (2,773)	7.5%	2,177	9.3%
	Comparison group ² (N=1,170)	20,737 (3,929)	-404*** (1,740)	-1.9%		
Two years after weatherization	Participants (N=315)	23,583 (4,739)	1,274*** (3,553)	5.4%	2,003	8.5%
	Comparison group ² (N=1,084)	20,867 (4,046)	-729*** (2,289)	-3.5%		
¹ Numbers in parentheses are standard deviations. Gross savings are statistically different from zero at * = 0.1, ** = 0.01, and *** = 0.001 levels of significance. ² The comparison group is comprised of a sample of nonparticipants weighted to match the utility-by-utility distribution of RWP participants.						

4.4 LEVELIZED COSTS

Levelized costs are calculated in 1989 dollars, to facilitate direct comparison with the levelized costs of the 1989 RWP. The 1988 costs shown in Table 3.2 are inflated to 1989 dollars by using a multiplier of 1.051 based on the Consumer Price Index (CPI) for the Seattle-Tacoma, Washington area. Total retrofit costs in 1989 dollars are \$2,310 and Bonneville's costs in 1989 dollars are \$1,530. Both of these cost estimates include administrative costs.

Based on the formula described in Section 2.7, Bonneville's levelized cost for the 1988 RWP is 33 mills/kWh (1989-\$). This exceeds the BPA cost target of 30 mills/kWh in 1990-\$ that Bonneville has set for its portfolio of conservation programs for all sectors and areas. However, it is within the sector payment target (of 20 to 35 mills/kWh in 1990-\$) established to guide the acquisition of future conservation resources through residential DSM programs operated by utilities (Bonneville Power Administration, 1992).

Regional levelized costs are higher (50 mills/kWh), since they reflect all of the direct program costs of Bonneville, participating utilities, and participating households. These regionwide costs are less than the Council's ceiling of 56 mills/kWh.

PART III: THE 1989 PROGRAM

5. MEASURES RECOMMENDED AND INSTALLED

This chapter reviews the retrofit measures that were recommended and installed by Bonneville's 1989 long-term Residential Weatherization Program. Recommended and installed measures are examined here primarily as a means of understanding program costs and predicted and actual savings. We focus on the sample of participants in the 1989 RWP with one year of pre- and postretrofit billing data in order to maintain comparability with the energy savings analysis presented in Chapter 6. Comparisons with previous RWP evaluations (including the results presented in Chapter 3 of the 1988 RWP) are the focus of Chapter 7.

5.1 WEATHERIZATION MEASURES

A total of 17 different types of energy conservation measures were recommended for installation in at least 1% of the sample of homes weatherized in 1989. Statistics on these 17 measures are provided in Table 5.1. On average, the audits recommended the installation of 5.0 measures per house. An average of 4.1 measures were installed per house, representing almost one measure fewer than was recommended. As in the 1988 Program, a total of 82% of all recommended measures were installed.

There was considerable variation in installation rates across retrofit measures. At one extreme, many types of measures were installed in fewer than 1% of the homes or not at all, for which statistics are not provided in Table 5.1. These include hydronic piping insulation, crawl space perimeter insulation, exterior perimeter insulation, exterior surface wall insulation, interior- and exterior-surface roof insulation, air-to-air heat exchangers, French doors, floor insulation (exposed), and dehumidifiers. Another four measures were installed in fewer than 5% of the homes: floor insulation (basement), basement wall insulation (interior), electrical water heater wraps, and water heater pipe insulation.

At the other extreme, ceiling insulation under attics was recommended to 83% of the 1989 RWP participants and was installed in 71% of their homes, representing the measure that was installed most often. The next four most recommended and installed measures were floor insulation (over crawl space), multiglazed windows, weatherstripping, and caulking.

Some measures were installed in almost all of the homes which needed them, based on audit results. Ceiling, floor, wall, and duct insulation are examples. Other measures were installed in a much smaller proportion of the recommended homes. Examples include sash-mounted windows, clock thermostats, storm windows, and weatherstripping, where less than 80% of the recommended installations were completed.

Table 5.1 Measures installed in the 1989 Residential Weatherization Program

Measure ^a	Percent recommended	Percent installed	Amount installed
Ceiling insulation under attic	83	71	1,088
Floor insulation (over crawl space)	67	64	1,105
Weatherstripping	61	45	2
Caulking	55	44	1.0
Multiglazed windows	56	48	128
Storm windows	30	22	107
Sliding glass doors	25	22	50
Duct insulation	25	23	196
Sash-mounted storm window	16	8	46
Clock thermostat	22	12	1.0
Wall insulation (exterior cavity)	20	19	773
Wall insulation (unfinished walls)	14	13	222
Floor insulation (basement)	4	3	675
Vent Conversion windows	5	5	157
Electrical water heater wrap	1	1	1.0
Basement wall insulation (interior)	3	2	662
Water pipe insulation	1	1	60
Measure ^a	Cost per installation (in 1989-\$)	Audit-estimated savings (kWh/year)	Cost per kWh of estimated savings (in 1989-\$)
Ceiling insulation under attic	567	1,032	.55
Floor insulation (over crawl space)	798	1,923	.41
Weatherstripping	70	41	1.71
Caulking	63	100	.63
Multiglazed windows	1,429	1,404	1.02
Storm windows	832	1,142	.72
Sliding glass doors	543	546	.99
Duct insulation	340	988	.34
Sash-mounted storm window	421	330	1.28
Clock thermostat	145	215	.67
Wall insulation (exterior cavity)	559	1,967	.28
Wall insulation (unfinished)	130	1,171	.11
Floor insulation (basement)	539	1,070	.50
Vent Conversion windows	1,117	1,610	.69
Electrical water heater wrap	30	n/a	n/a
Basement wall insulation (interior)	537	1,432	.38
Water pipe insulation	47	n/a	n/a
^a The following measures were installed in fewer than 1% of the homes, if at all: interior- or exterior-surface roof insulation, crawl space perimeter insulation, exterior perimeter insulation, exterior surface wall insulation, hydronic piping insulation, air-to-air heat exchangers, french doors, floor insulation (exposed), or dehumidifiers.			
Source: Sample of 507 homes weatherized in 1989.			

5.2 WEATHERIZATION COSTS AND ESTIMATED SAVINGS

Overall, the average audit-estimated (weighted) energy savings per house for all recommended measures were 4,640 kWh/year, and audit-estimated (weighted) savings for installed measures were 4,100 kWh/year. These estimates are based on engineering calculations and will be compared with measured savings based on consumption data in Chapter 6.

As with the 1988 program evaluation, we computed the percent of potential audit-estimated savings that are actually captured by dividing the audit-estimated savings from installed measures by the audit-estimated savings from recommended measures, and multiplying by 100. The result (88%) indicates: (1) that the installed measures account for a majority of the audit-estimated energy savings and (2) that households are more likely to install measures that are estimated to achieve greater energy conservation, since overall only 82% of the recommended measures were installed.

Based on actual costs and audit-estimated savings, the energy conservation measures installed by the RWP vary significantly in cost effectiveness. The cost per kWh of estimated savings (in 1989-\$) is lowest for wall insulation (unfinished walls and exterior cavity) the only two measures that cost less than \$0.32 per kWh of estimated savings in the first year. Other measures with relatively low costs per estimated energy saved include duct insulation, basement wall insulation (interior), and floor insulation (over crawl space). At the other extreme, each of the five following measures is expected to cost more than \$0.70 per kWh: weatherstripping, windows (sash-mounted, storm, and multiglazed), and sliding glass doors.

Table 5.2 presents the average weatherization costs for each utility and for the 1989 Program as a whole, based on the sample of 507 participants in 1989. For the entire sample, the average, regionally-weighted job cost (excluding administrative costs of \$400) was \$1,918 (in 1989-\$). The average, programwide Bonneville costs (excluding administrative costs) were \$1,266. Including half of the administrative costs, Bonneville's contribution averages \$1,466. Of the average job cost in 1989 (excluding administrative costs), 66% was reimbursed by Bonneville, 3% was paid by the utility, and the consumer contribution averaged 31%.

Total retrofit costs vary greatly across the utilities, as does the distribution of costs across the three contributors: Bonneville, the utility, and the consumer. Costs are least for Missoula Electric Cooperative, the only DGP utility operating under the Window Separation Amendment. No other cost-reduction method results in notably low or high overall costs. However, the utility contribution is greatest for those utilities that elected to reduce Bonneville's RWP costs by increasing the utility cost-share: Seattle City Light and Tacoma Public Utilities.

Table 5.2 Weatherization costs for the 1989 Residential Weatherization Program

Utility (by Cost-Reduction Method)	Total Retrofit Cost (in 1989-\$) ^a	Contributions (in 1989\$) by:		
		Utility	Consumer	Bonneville
Increased Utility Funds:				
Seattle City Light (49)	976	84	0	891
Tacoma Public Utilities (100)	2,316	80	796	1,440
Reduced Incentives:				
Richland Energy Services (63)	1,411	0	227	1,184
Port Angeles, City of (59)	2,736	0	1,200	1,536
Dipstick Amendment:				
Benton County PUD (71)	1,450	0	692	759
Clallam County PUD (36)	1,848	0	1,450	398
Window Separation Amendment:				
Missoula Electric Cooperative (41)	412	0	177	234
None:				
Eugene Water & Electric Board (88)	1,823	43	537	1,243
Program Summary^b	1,918	51 (3%)	604 (31%)	1,266 (66%)
^a Excludes administrative costs of \$400. ^b The numbers in this row are weighted by utility. Numbers in parentheses are percentages of the total retrofit cost. Source: 507 participant homes weatherized in 1989.				

6. ENERGY SAVINGS

Based on billing histories provided by the eight utilities described in Chapter 2, annual weather-adjusted energy use and savings were estimated. There were 433 participant households in 1989 for which at least two complete years of data were available, allowing the calculation of energy use for one year prior to weatherization and one year afterwards. Two years of complete data also were available for 1,466 nonparticipants.

Once household energy use and gross savings were calculated for the sample of participants and nonparticipants described above, these data were then aggregated and examined at the utility level. Finally, utility savings were weighted, using the participant weights shown in Table 2.3, to allow the identification of *overall* 1989 program savings. Each of these different levels of analysis will be discussed in the following sections, beginning with energy use and savings by individual households.

6.1 HOUSEHOLD SAVINGS

We began by comparing the average weather-adjusted annual electricity consumption of RWP participants and nonparticipants for the year prior to their weatherization. As with the 1988 program, we found that those households in this sample that participated in the program in 1989 used more electricity prior to weatherization than did the nonparticipants. Table 6.1 shows that the sample of 1989 participants used 3,830 kWh (i.e., 21%) more electricity during the preretrofit year (1988/89) than the sample of nonparticipants. This difference in preretrofit NAC is significant at the 0.001 level.

The average preretrofit NAC of the comparison group is also significantly smaller than that of the average participating household (Table 6.1). However, as was the case in the 1988 Program, the comparison group consumes more than the nonparticipants. This increase is due to the fact that the comparison group is dominated by Eugene nonparticipants, who consume considerably more electricity than nonparticipating households from the utility that dominates the nonparticipant group -- Seattle City Light. Thus, within the DGP utilities, program participants are drawn at a higher rate from the utilities with higher levels of preretrofit electricity consumption. This bias favors greater energy savings, since preretrofit energy use is a strong positive predictor of savings.

The distribution of gross electricity savings achieved by participating households one year after weatherization are shown in Fig. 6.1. The participants' unweighted average gross savings is 1,085 kWh with a standard deviation of 5,848 kWh. These numbers and the accompanying figure indicate that there was a broad range of savings. Indeed, many program participants (25%) used more energy following weatherization than before weatherization. This finding is common to many other studies of conservation programs, including earlier assessments of the RWP (Hirst, et al., 1983a).

Table 6.1 Comparisons of weighted preretrofit normalized annual consumption for 1989 program participants, nonparticipants, and comparison group¹

	Participants' mean pre-retrofit NAC	Nonparticipants' mean pre-retrofit NAC	Participants' preretrofit NAC minus nonparticipants' preretrofit NAC	Comparison group's mean preretrofit NAC	Participants' preretrofit NAC minus comparison group's preretrofit NAC
Normalized annual consumption (NAC)	22,134 kWh (3,597)	18,303 kWh (4,528)	3,831 kWh***	19,383 (3,733)	2,741***
Reference temp. (°F)	60.6 (4.1)	59.2 (5.3)	---	60.3 (3.9)	---
PRISM R ²	0.87 (0.08)	0.89 (0.14)	---	0.87 (0.13)	---
Number of households in sample	433	1,466	---	1,466	---
¹ Participants and nonparticipants shown here are all those households for which at least two complete years of billing data were obtained: the pre-weatherization year and the first year after weatherization. Numbers in parentheses are standard deviations. *** Indicates that the difference is significant at the 0.001 level.					

As shown in Fig. 6.1, nonparticipants also experienced a broad range of energy savings (i.e., changes in consumption), even in the absence of participation in the RWP. In this case, however, the mean amount saved was -630 kWh, meaning that the average comparison household used 630 kWh more during 1989/90 than 1988/89. The standard deviation was high, at 4,294 kWh, and many households experienced substantial savings (42% reduced energy use), even without being weatherized through the RWP.

Household energy savings are difficult to predict using audit estimates, as shown by Fig. 6.2. Each point on the scatter plot represents an estimate of savings made by the RWP energy audit and the actual energy savings achieved (based on billing histories) one year after the same home was weatherized. In general, audit-estimated savings were much higher than the savings actually realized. This is frequently found in other conservation programs, as well (Hirst, Goeltz, and Trumble, 1989; Nadel and Keating, 1991). In this study, average audit-estimated savings (unweighted) were approximately 3,180 kWh (with a standard deviation of 3,250 kWh). Mean (unweighted) gross savings, however, were only 1,085 kWh for the first year after weatherization. Thus, 34% of the estimated savings was realized during the first postretrofit year. On a household-by-household basis, Fig. 6.2 illustrates that there is little correspondence between audit-estimated and actual gross energy savings. As with the 1988 RWP, the Pearson correlation coefficient between audit-estimated and gross savings is significant, but small ($r=0.10$, $p=0.03$).

Fig. 6.1. Annual gross electricity savings for 1989 program participants and nonparticipants one year after weatherization (unweighted). (Univariate nonparametric kernel density estimator used for smoothing.)

Fig. 6.2. Comparison of audit-estimated savings with actual gross electricity savings one year after weatherization in 1989 (unweighted).

6.2 UTILITY-LEVEL SAVINGS

Table 6.2 shows preretrofit NAC, NAC for the first year following weatherization, and gross energy savings (the difference between these two numbers) for the first year after weatherization for each of the eight utilities in our sample. This table shows that participants used more energy prior to weatherization than did nonparticipants for five of the eight utilities. The table shows substantial differences among utilities in average preretrofit consumption for participants and nonparticipants alike.

Preretrofit NACs range from 15,231 kWh for Tacoma Public Utilities nonparticipants to 25,680 kWh for Benton County PUD participants.

Table 6.2 Average weather-adjusted electricity consumption and gross electricity savings one year after weatherization, by utility, for the 1989 program

Cost-Reduction Method and Utility		Preretrofit NAC ^a	First year postretrofit NAC ^a	First year postretrofit gross electricity savings ^a
Increased Utility Funds:				
Seattle City Light	Participants (39) Nonparticipants (538)	16,990 18,788	16,110 19,390	880 -602***
Tacoma Public Utilities	Participants (88) Nonparticipants (399)	23,716 15,231	22,108 15,589	1,609*** -358*
Reduced Incentives:				
Port Angeles, City of	Participants (50) Nonparticipants (56)	19,983 18,092	17,539 17,652	2,444*** 440
Richland Energy Services	Participants (52) Nonparticipants (80)	21,996 19,643	23,865 21,234	-1,869 -1,591***
Dipstick Amendment:				
Benton County PUD	Participants (69) Nonparticipants (117)	25,680 23,609	25,281 25,369	399 -1,760***
Clallam County PUD	Participants (30) Nonparticipants (101)	21,173 29,514	18,481 20,808	2,693*** -294
Window Separation Amendment:				
Missoula Electric Cooperative	Participants (21) Nonparticipants (29)	20,324 19,411	15,477 18,017	4,847*** 1,395
None:				
Eugene Water & Electric Board	Participants (84) Nonparticipants (146)	21,890 23,438	21,191 23,650	699 -212
*Electricity consumption and savings are reported in units of kWh. Gross savings are significantly different from zero at * = 0.1, ** = 0.01, and *** = 0.001 levels of significance.				

Participants in seven of the eight utilities experienced positive gross savings in the first year after retrofit. The exception is Richland Energy Services, where participants on average consumed more electricity after weatherization than before. Nonparticipants generally experienced small positive or small negative savings (i.e., greater energy use in 1989/90 than in 1988/89). The exception is Missoula Electric Cooperative, where the sample of nonparticipating households consumed 1,395 kWh of NAC more in 1988/89 than in 1989/90.

There was substantial variation among utilities in the magnitude of gross savings achieved. Gross savings range from -1,869 in Richland Energy Services to 4,847 in Missoula Electric Cooperative. The

reliability of the estimate for Missoula is questionable because it is based on a sample of only 21 participants.

Net savings by utility for the initial postretrofit year, along with the size of these savings as a percent of preretrofit NAC, are given in Table 6.3. Seven of the eight utilities experienced positive net savings during the first postretrofit year. They ranged from 911 kWh (4% of previous energy use) for Eugene Water & Electric Board to 3,452 kWh (17% of prior use) for Missoula Electric Cooperative.

Table 6.3 Average net electricity savings by utility, for the 1989 Program

Cost-Reduction Method and Utility	First year postretrofit net energy savings
Increased Utility Funds: Seattle City Light Tacoma Public Utilities	1,482 (8.7%) 1,967 (8.3%)
Reduced Incentives: Port Angeles, City of Richland Energy Services	2,004 (10.0%) -278 (-1.3%)
Dipstick Amendment: Benton County PUD Clallam County PUD	2,159 (8.4%) 2,987 (14.1%)
Window Separation Amendment: Missoula Electric Cooperative	3,452 (17.0%)
None: Eugene Water & Electric Board	911 (4.2%)

6.3 OVERALL PROGRAM SAVINGS

After household energy use was aggregated by utility and net savings were calculated, utility-level data were further aggregated to allow the calculation of programwide savings. Weighted average electricity consumption and PRISM-generated end-use estimates for the preretrofit and postretrofit years are shown in Fig. 6.3 and Table 6.4, along with their standard deviations.

Programwide gross energy savings for 1989 participants are estimated to be 990 kWh during the first postretrofit year, or 4.5% of preretrofit energy use. In contrast, the comparison group increased its consumption by 337 kWh or 1.7% during the first year after weatherization. This increase is consistent with national trends in electricity consumption per household (Response Analysis, 1991).

Based on the standard deviation (1,727 kWh) of the participants' gross savings and the sample size of 433, the estimate of gross savings is quite precise. Its standard error is 83 kWh, which is only 8% of the estimated gross savings, and its 95% confidence interval ranges from 827 to 1,153 kWh.

Fig. 6.3 Weighted NAC components for 1989 program participants and comparison group.

Table 6.4 Weighted average electricity savings for 1989 participants and comparison group

		Pre-weatherization energy use	Total gross savings ¹	Total gross savings as % of pre-weatherization energy use	Total net savings ¹	Total net savings as % of pre-weatherization energy use
One year after weatherization	Participants (N=433)	22,134 (3,597)	990*** (1,727)	4.5%	1,327	6.0%
	Comparison Group ² (N=1,466)	19,721 (3,759)	-337*** (1,543)	-1.7%		

¹ Numbers in parentheses are standard deviations. Gross savings are statistically different from zero at * = 0.1, ** = 0.01, and *** = 0.001.

² The comparison group is comprised of a sample of nonparticipants weighted to match the utility-by-utility distribution of RWP participants.

Relative to the audit-estimated savings of 4,100 kWh/year, the actual savings are modest. Only 32% of the estimated savings were realized during the first year after weatherization.

Figure 6.3 suggests that the slight increase in the comparison group's Normalized Annual Consumption is due to the group's increased base load consumption. The participants also appear to have increased their base load consumption, which offsets some of the large decrease (2,700 kWh) in their space heat use between their preretrofit and postretrofit years. During the postretrofit year, the participant group's space heat use (10,162 kWh) approximates that of the comparison group (9,449 kWh), but its base load is somewhat larger (10,982 vs. 10,272 kWh). The same pattern was observed with the 1988 participants.

Figure 6.4 graphically illustrates how net savings is a function of the gross savings of participants and the comparison group one year after weatherization. In Table 6.4, *weighted* gross savings and

Fig. 6.4. Average programwide gross energy savings for 1989 program participants and comparison group.

weighted net savings for the postretrofit year are shown. Programwide total net savings were 1,327 kWh for the first year following weatherization. This represents 6.0% of preretrofit energy use (Table 6.4).

6.4 LEVELIZED COSTS

Using the formula described in Section 2.7, Bonneville's levelized costs for the 1989 RWP are 52 mills/kWh, based on Bonneville's expenditure of \$1,470 per weatherized unit (including \$200 in administrative costs). This levelized cost is 19 mills more than in 1988. It also exceeds the BPA cost target for Bonneville's portfolio of conservation programs, and it exceeds Bonneville's residential sector payment target of 20 to 35 mills/kWh (Bonneville Power Administration, 1992).

Regional levelized costs are 83 mills/kWh, nearly 33 mills more than in 1988 and 27 mills more than the Council's 56 mill ceiling. The difference is due to lower 1989 net energy savings (2,180 kWh in 1988 vs. 1,330 kWh in 1989), combined with slightly higher regional costs (\$2,310 in 1988 vs. \$2,320 in 1989).

PART IV: DISCUSSION AND CONCLUSIONS

7. COMPARISONS WITH PRIOR BONNEVILLE WEATHERIZATION EVALUATIONS

This chapter compares the results of the 1988 and 1989 RWP evaluation with the findings of previous evaluations of Bonneville's weatherization efforts.

When comparisons are being made with the findings from previous evaluation research, dollars are inflated to 1989 values using 1981 through 1989 Consumer Price Indexes for the Seattle, Washington area.

7.1 WEATHERIZATION MEASURES

In 1988 and 1989, the installation rates for particular weatherization measures were quite similar. In both years, the most commonly installed measures were:

- ceiling or attic insulation
- floor insulation over crawl spaces
- weatherstripping
- caulking
- multiglazed windows

These same measures were also commonly installed by Bonneville in its prior weatherization programs.

Table 7.1 provides an historic profile of the installation rates for categories of weatherization measures, dating back to 1982. There has been a sustained emphasis on the installation of ceiling and floor insulation since the inception of the program. Interestingly, the Program insulates heating ducts, as per the audit recommendation, in only about 20% of the weatherized dwellings. Given the recent information by Proctor and Pemick (1992) and Coyne (1992), there may be an opportunity to increase the cost effectiveness of the Program by decreasing the air leakage in distribution systems, in a greater number of dwellings.

The statistics indicate a decline in installation rates for setback thermostats and an increased emphasis on storm windows, storm doors, caulking, and weatherstripping since the onset of the long-term RWP. The high rate of installation of storm windows since 1985 has been sustained despite the growing recognition that storm windows are not typically cost effective (Cohen and Goldman, 1992; CSR, Inc. and Meridian Corporation, 1989).

In both 1988 and 1989, 82% of the audit-recommended measures were installed. This rate is comparable to the rates identified by previous evaluations of Bonneville's weatherization programs. In 1982 and 1983, 70% of the recommended measures were installed by the Bonneville program (Hirst, et al., 1985), in 1985 the measure installation rate was 78% (Horowitz, et al., 1987), and in 1986 it was 83% (White and Brown, 1990).

Table 7.1 Installation rates for categories of RWP measures (weighted)

Measures	Percent Installed ¹					
	1982	1983	1985	1986	1988	1989
Insulation						
Outside Wall ²	16	9	46	34	21	31
Roof/Ceiling ³	90	80	61	77	78	71
Floor ⁴	73	73	39	64	72	66
Heating Ducts	17	15	15	27	18	23
Storm						
Windows ⁵	37	46	63	68	62	62
Doors ⁶	15	7	15	28	29	22
Infiltration						
Caulking	} 20	} 17	37	38	54	44
Weatherstripping			42	44	52	45
Setback Thermostat	29	14	16	14	5	12

¹Evaluation of the 1980-82 Pilot Program relied upon a telephone survey to estimate installation rates for individual conservation measures (Hirst, et al., 1983a). The results were judged to be too unreliable for inclusion here.

²Includes crawl space perimeter (interior and exterior), basement wall, unfinished wall, exterior wall and exterior wall cavities insulation.

³Includes ceiling and roof (interior and exterior) insulation.

⁴Includes crawl space, basement and exposed floor insulation.

⁵Includes storm windows, sash-mounted storms and multiple glazing.

⁶Includes sliding glass doors and French doors.

Source for 1982-83 data is Hirst, et al. (1985), Table 13. Source for 1985 data is Horowitz, et al. (1987), Tables 3 and 7. Source for 1986 data is Schweitzer, White, and Brown (1989), Table 3.6.

Where there was a considerable disparity between rates of recommendation and installation, the non-installed measures tend to offer lower-than-average audit-estimated energy savings and greater-than-average costs per kWh of estimated savings (e.g., clock thermostats, sash-mounted windows, and weatherstripping). In contrast, ceiling, floor, wall, and duct insulation were installed in almost all of the homes where the audit indicated a need. These measures tend to offer higher-than-average audit-estimated energy savings at a relatively low cost per energy saved. This same pattern was identified in the evaluation of 1986 program participants (Schweitzer, White, and Brown, 1989).

7.2 WEATHERIZATION COSTS

The cost of the average Bonneville-supported weatherization job (in nominal dollars) has remained fairly steady since 1981 (Table 7.2). When these costs are inflated to 1989 dollars, the results indicate

a discernable reduction in the real resources devoted to the typical job, particularly since the 1986 RWP (Figure 7.1). Some of this decrease is undoubtedly due to the cost-reduction measures implemented in 1988.

Table 7.2 Comparisons of weatherization costs for long-term RWP participants and participants in earlier Bonneville weatherization programs

Program	Regional Costs/Unit (nominal \$) ¹	Regional Costs/Unit (1989-\$) ²
Pilot (1980-82)	2,630	3,220
Interim (1982-83)	2,100	2,540
Long-Term RWP (1985)	2,280	2,580
Long-Term RWP (1986)	2,790	3,130
Long-Term RWP (1988)	2,200	2,310
Long-Term RWP (1989)	2,320	2,320
¹ Costs are figured with nominal dollars and include administrative costs as described below. Pilot Program - (Hirst, White, and Goeltz, 1985, Table 2, p. 18; and Hirst et al., 1983, p. 89, assuming \$360 in administration costs). Interim Program - (Hirst et. al., 1985, Table 18, p. 71, and Ch. 7, assuming \$370 in administrative costs). Long-Term Program, 1985 Cohort - (Haeri, 1988, Table 10 and p. 23, assuming \$400 in administrative costs), 1986 Cohort - (Schweitzer, White, and Brown, 1989, assuming \$400 in administrative costs), 1988 and 1989--this report, assuming \$400 in administrative costs. ² Inflated to 1989 dollars using CPI-U (all items) for the Seattle-Everett and Seattle-Tacoma, Washington areas. Index stood at 297.8 for 1982, 304.0 for 1983, 321.9 for 1985, 325.2 for 1986, 346.9 for 1988, and 364.5 for 1989 where 1967 = 100. Inflating 1982 costs to 1989 level uses the calculation: $(\text{Cost}_{82} / \text{CPI}_{82}) \times \text{CPI}_{89}$.		

The increase over time in the average consumer contribution is vividly illustrated in Table 7.3. In 1985 and 1986, consumers contributed 27% and 31% of the average RWP costs, respectively, as did the 1988 and 1989 consumers. In the early years of the Program, the consumer contribution was less: it was 20% in 1983, and 6% in 1982. Utilities became stakeholders in Bonneville's long-term RWP in 1986, and their financial support (although modest) has continued through to the present.

Fig. 7.1. Comparisons of regional weatherization costs across Bonneville's weatherization programs.

Table 7.3 Weatherization costs by source of contribution (in percentages)¹

Source	1982	1983	1985	1986	1988	1989
Bonneville						
Excluding administrative costs ²	94	80 ³	73	57	70	66
Including administrative costs	88	75	69	56	66	63
Utility						
Excluding administrative costs ²	0	0	0	12	3	3
Including administrative costs	7	9	9	17	11	11
Consumer						
Excluding administrative costs ²	6	20	27	31	27	31
Including administrative costs	5	16	22	27	22	26

¹ Source for 1982-83 data is Hirst, et al. (1985), Table 5 and footnote (a), Table 11. Source for 1985 data is Horowitz, et al. (1987). Source for 1986 data is Schweitzer, White, and Brown (1990), Table 3.4.

² These percentages do not include the Program's administrative costs, which are split equally between Bonneville and its utilities.

³ This includes an average payment of \$289 by one utility, in addition to the financial incentive provided by Bonneville.

7.3 PRERETROFIT ENERGY CONSUMPTION

In both the 1988 and 1989 program evaluation, participants were found to consume more electricity prior to weatherization than eligible nonparticipants. This finding is consistent with the results of previous evaluations of Bonneville's Residential Weatherization Program (Table 7.4) and studies of other residential conservation programs (Hirst et al., 1983b; Goldberg, 1986; Brown and White, 1988).

This characteristic difference in preprogram electricity consumption between RWP participant and comparison group households has persisted over time (Fig. 7.2). In the Pilot Program, administered between 1980 and 1982, participating households included in the evaluation used 29,350 kWh/year in the preweatherization year while nonparticipants used 25,410 kWh/year. Thus, participants used 16% more electricity than nonparticipants. In the 1986 long-term RWP, participants used 24,310 kWh (weighted) in the preretrofit year while the comparison group households used an average of 22,270 kWh (weighted). Thus, participants used 9% more electricity than nonparticipants.

Table 7.4 Preretrofit energy consumption for RWP participants and nonparticipants

Program	Normalized Annual Consumption (NAC) for Participants (kWh/year)	Normalized Annual Consumption (NAC) for Nonparticipants (kWh/year)	Percent Difference
Pilot (1980-82)	29,350	25,410	16
Interim (1982-83)	26,100	24,800	5
Long-Term RWP (1985)	23,900	22,100	8
Long-Term RWP (1986)	24,310	22,270	9
Long-Term RWP (1988)	23,520	18,830	20
Long-Term RWP (1989)	23,130	18,300	21
Source for 1980-82 data is Hirst, White, and Goeltz (1985), Table 2. Source for 1982-83 data is Goeltz, Hirst, and Trumble (1986), Table 3. Source for 1985 RWP data is Horowitz, Bronfman, and Lerman (1987), Table 8. Source for 1986 RWP data is White and Brown (1990), Table 4.1.			

As discussed in Section 2.5, in evaluating the 1988 and 1989 Programs, we estimated the electricity consumption of two different nonparticipant groups created through two distinct weighting schemes. When nonparticipants are weighted to mirror the utility-by-utility distribution of eligible nonparticipants (the traditional use of weights for Bonneville RWP evaluations), the difference in preretrofit electricity consumption between participants and nonparticipants is large: 20% in 1988 and 21% in 1989. When nonparticipants are weighted to reflect the utility-by-utility levels of program participation (the unique use of weights developed for this evaluation), the differences in preretrofit consumption levels are reduced. This reflects the fact that within the DGP utilities, rates of program participation tend to be higher in utilities with higher levels of residential electricity consumption, a bias that favors greater energy savings.

Another pattern shown in Table 7.4 (and Fig. 7.2) is the decreased levels of preretrofit Normalized Annual Consumption experienced both by program participants and nonparticipants between 1981 and 1989. Since preretrofit NAC has been found in numerous studies to be the single greatest predictor of weatherization energy savings, we would also expect to see diminished programmatic savings over the same period. This is, in fact, documented below in Table 7.5.

7.4 ENERGY SAVINGS

A sense of the relative decline in electricity savings achieved by 1988 and 1989 RWP participants can be attained by comparing the amount of energy saved by this group with the savings experienced by previous participants in this and similar Bonneville weatherization programs. Table 7.5 and Figure 7.3 show net savings for participants in the RWP Pilot, Interim, and long-term programs, whose homes were weatherized between 1981 and 1989. For the Pilot Program, the savings presented are for the first three years following weatherization. For 1982 and 1983 participants in the Interim Program, savings estimates are available for three and two years after participation, respectively. For the long-term RWP, the savings experienced by 1985 and 1986 participants are tracked for three postweatherization years. For 1988 and 1989 participants, savings are estimated for two and one year postretrofit, respectively.

There has been a downward trend over the years in the net savings achieved during the first postretrofit year by successive cohorts of participants, declining from high values of 3,840 kWh in 1981 and 4,200 kWh in 1982-83 to 2,180 kWh in 1988 and 1,330 kWh in 1989. The one exception to this trend is the 1986 group, which had higher savings than the 1985 group in its first postretrofit year. Recall that average weatherization costs per job were also higher in 1986 than in 1985 (Table 7.2). Recall, too, that RWP costs per weatherized dwelling were considerably lower in 1988 and 1989, when constant (1989) dollars are considered.

Fig. 7.2. Preretrofit energy consumption of participants, non participants, and comparison groups.

Table 7.5 Average annual electricity savings during postretrofit years

	Net Energy Savings (kWh/Year) ¹		
	Year 1	Year 2	Year 3
Pilot (1980-82)	3,840	3,790 (1.3%)	3,410 (11.2%)
Interim (1982-83) ²	4,200	3,600 (14.3%)	2,500 (40.5%)
Long-Term RWP (1985)	2,610	2,565 (1.7%)	2,600 (0.4%)
Long-Term RWP (1986)	3,060	2,112 (31.0%)	2,140 (30.1%)
Long-Term RWP (1988)	2,180	2,000 (8.3%)	
Long-Term RWP (1989)	1,330		

¹ Does not include 7.5% credit for reduced transmission and distribution losses. Numbers in parentheses are percentages of the year 1 net savings.

² Net energy savings of the Interim Program is the weighted average of the 1982 and 1983 cohort savings. (Goeltz, Hirst, and Trumble, 1985, Table 3, p. 14). In particular:

Year 1 = $483 (4,100) + .517 (4,300) = 4,200$

Year 2 = $483 (3,300) + .517 (3,800) = 3,600$

The 1982 cohort is the only cohort in the Interim Program with a third year of savings (2,500).

Fig. 7.3. Comparison of net electricity savings by participants in Bonneville's weatherization programs.

Two of the five cohorts with multiple postretrofit years of consumption data exhibit marked decay in savings over time. For instance, net savings for the Interim Program (1982-83) declined by 40% between the first and third postretrofit years. Similarly, the amount of energy saved by the 1986 group fell by nearly 30% from the first to the third postretrofit year. Net savings by the other cohorts (including 1988) remained relatively constant.

While the causes of inconsistency in conservation over time are still unclear, there is a growing body of empirical evidence documenting the magnitude of conservation decay. Longitudinal evaluations of Seattle City Light's Home Energy Loan Program (HELP) and two Wisconsin weatherization programs are particularly noteworthy.

Sumi and Coates (1988) examined HELP to determine the persistence of energy savings over the 1982-87 period. The analysis was restricted to 1,030 single-family households who had received a loan, performed a home weatherization, and who had lived in the same home for the duration of the study period. A nonparticipant sample of 229 homes was studied for comparison purposes. All energy consumption data were weather-normalized using PRISM. On average it was found that the energy saved by participating households during their first preretrofit year declined 5.9% per year, or 27% over the six-year period for each of the six program cohorts (that is, participants weatherized in 1981, 1982, . . . , 1986). There was much less decay in energy savings when each cohort was tracked over time. For instance, annual energy savings in 1982 for 1981 participants was 2,805 kWh. Subsequent years of savings for the same 1981 cohort fluctuated slightly up and down between 1983 (when savings were 2,932 kWh) and 1987 (when savings were 2,759 kWh) (Sumi and Coates, 1988, p. 32). Thus, as with this study, most of the degradation in savings over time was due to the reduced savings associated with each new program cohort.

Narum, Pigg, and Schlegel (1992) examined two Wisconsin weatherization programs to assess the persistence of gas savings. Consumption histories for Wisconsin Gas Company participants spanned six years, and for Madison Gas & Electric Company, the histories covered five years. Altogether, more than 6,000 customers were included in the study. Untreated buildings were used to produce an estimate of net savings. Gas consumption increased over the period of analysis for both weatherized and untreated buildings in both of the utility programs. While gross consumption of weatherized buildings increased over the period of analysis, that of the untreated buildings increased during this period at a greater rate. As a result, it was concluded that net savings do not decay over the first six years following weatherization.

The overall experience with Bonneville's weatherization efforts suggests a comparable conservation decay as for the Seattle and Utah programs discussed above. The average decline in net savings for the nine one-year segments shown in Figure 7.3 is 543 kWh/year. When *each* annual decline is calculated as a percent of the savings during the first postretrofit year -- and averaged -- the average percent decline in net savings is 15%.

7.5 LEVELIZED COSTS

Regional and Bonneville levelized costs of Bonneville's weatherization programs are shown in Table 7.6 and Fig. 7.4. Costs are inflated to 1989 mills/kWh to facilitate comparison.

None of the long-term RWP cohorts (1985 through 1989) have been as cost effective for the region as Bonneville's two earlier weatherization programs. The levelized costs of the electricity saved

in the 1989 program (83 kWh/year) are notably more expensive than previous years of weatherization activities, and are also the first to exceed the Council's 56 mills/kWh limit.

Utility and consumer contributions to the program's costs have also increased over time. As a result, Bonneville's levelized have not increased as dramatically as the regional costs. Nevertheless, the 1989 RWP is estimated to have cost Bonneville 52 mills for every kWh saved, which is approximately twice the cost of the 1985 and 1986 Programs.

Table 7.6 Historic Costs and Net Savings of Bonneville's Weatherization Programs

Program Year	First Year Net Savings ¹	Regional Levelized Costs (1989-\$)		Bonneville Levelized Costs (1989-\$)	
		Per Unit ²	Mills/kWh	Per Unit ³	Mills/kWh
Pilot (1980-82)	3,840	3,220	40	(Loan Prg.)	<40
Interim (1982-83)	4,200	2,540	29	1,900	21
RWP 1985	2,610	2,580	47	1,780	32
RWP 1986	3,060	3,130	48	1,750	27
RWP 1988	2,180	2,310	50	1,530	33
RWP 1989	1,330	2,320	83	1,470	52

¹ See Table 7.5 for a list of sources for these estimates of savings. Weighted savings do not include the 7.5% credit for reduced transmission and distribution line losses.

² See Table 7.2 for a list of sources for these estimates of weatherization costs, including administrative costs.

³ Bonneville costs are based on the percentage contribution listed in CON-323, Table 7.3, which include administrative costs.

Fig. 7.4. Historic levelized costs of Bonneville's weatherization programs.

8. CONCLUSIONS AND RECOMMENDATIONS

8.1 CONCLUSIONS

This section summarizes the results of the 1988 and 1989 RWP evaluation. Our major findings are described below:

- In both 1988 and 1989, more than 80% of the audit-recommended measures were installed by the RWP. Where there was a considerable disparity between rates of recommendation and installation, the non-installed weatherization measures tended to offer lower-than-average audit-estimated energy savings and greater-than-average costs per kWh of estimated savings (e.g., clock thermostats, sash-mounted windows, and weatherstripping). These findings also characterized previous years of the RWP.
- The 1988 and 1989 Programs continued Bonneville's historic emphasis on the installation of ceiling and floor insulation and storm windows.
- In 1988, weatherization costs per home averaged \$2,310 (in 1989-\$), and in 1989 they averaged \$2,320 (including administrative costs of \$400/job). Compared to earlier years, these statistics indicate a reduction in the resources devoted to the typical weatherization job, particularly since the 1986 RWP which averaged \$3,130 (in 1989-\$). Some of this decrease is undoubtedly due to the cost-reduction measures implemented in 1988.
- The utility contribution to the costs of the RWP averaged 3% in both 1988 and 1989, continuing the pattern of utility financial involvement initiated in 1986. The average consumer contribution has increased steadily from 6% in 1982 to 27% and 31% in 1988 and 1989.
- Between 1981 and 1989, the preretrofit Normalized Annual Consumption of program participants and nonparticipants decreased markedly: (1) from 29,350 kWh/year for 1981 participants to 23,520 and 23,130 for 1988 and 1989 participants and (2) from 25,410 kWh/year for 1981 nonparticipants to 18,830 and 18,300 for 1988 and 1989 nonparticipants. In both 1988 and 1989, RWP participants consumed approximately 20% more electricity prior to weatherization than eligible nonparticipants. This finding is consistent with the results of previous RWP evaluations.
- When the nonparticipant group is weighted to mirror the utility-by-utility distribution of participants, the differences in preretrofit consumption levels are reduced, reflecting the fact that program participation tends to be higher in utilities with higher levels of residential consumption. This bias would appear to favor greater energy savings.
- Estimated gross energy savings are 1,773 kWh (± 288 kWh) for the first year after weatherization in 1988 and 1,274 kWh (± 163 kWh) for the first year after weatherization in 1989. Audit-estimated savings were 4,240 and 4,100 kWh/year for the 1988 and 1989 programs¹. Thus, as is typical of weatherization programs nationwide, only a portion of anticipated savings were realized (42% for the 1988 program and 31% for the 1989 program).

¹ Ranges in parentheses represent the 95% confidence interval.

On a household-by-household basis, there is little correspondence between audit-estimated savings and actual savings.

- Estimated net energy savings are 2,180 kWh for the first year after retrofit in 1988. This represents 9.3% of the preretrofit level of Normalized Annual Consumption. Net energy savings of 1,330 kWh (or 6.0%) are estimated for the initial year after weatherization in 1989. These findings indicate a continued downward trend in the savings achieved by Bonneville's weatherization programs; the first-year savings of the 1988 and 1989 Programs are lower than any previously evaluated weatherization program operated by Bonneville.
- The net energy savings of 1988 Program participants declined by 180 kWh (or 8%) from the first to the second year after weatherization. The average year-to-year decline by RWP participants who have been tracked for two or three years after participation beginning with the Pilot Program is 15%.
- Regional levelized costs are 50 and 83 mills/kWh for the 1988 and 1989 programs, respectively. Thus, Bonneville's 1989 Residential Weatherization Program exceeds the Northwest Power Planning Council's cost-effectiveness ceiling of 56 mills/kWh. Bonneville's levelized costs for both programs (33 and 52 Mills/year) are considerably lower than the regional costs, reflecting the substantial cost sharing by utilities and consumers.

8.2 PROGRAMMATIC AND EVALUATION RECOMMENDATIONS

Several recommendations emerge from this evaluation that pertain to the operation and evaluation of Bonneville's Residential Weatherization Program.

Recommendation 1: Bonneville should conduct a comprehensive review of state-of-the-art weatherization technologies and procedures to assess their applicability to its own Residential Weatherization Program.

Over the past decade, weatherization program managers across the country have learned a great deal about how to improve the cost effectiveness of their programs. Recent innovations include:

- targeted outreach activities, client screening, and investment protocols that result in higher participation rates and greater investment levels for high-energy users;
- increasingly accurate audit and diagnostic techniques (e.g., integrated shell and equipment audits, integrated heating and cooling audits, blower doors, and infrared photography);
- new and improved weatherization measures (e.g., high-density wall insulation, compact fluorescent light bulbs, and low-emissivity windows);
- on-site client education (e.g., involving real-time feedback of consumption data via smart thermostats, household commitments to take specific conservation actions, and utility follow-up activities); and

It is important to continually consider programmatic changes based on evolving regional, utility, and customer needs and continuing developments in weatherization technologies. A comprehensive review of state-of-the-art weatherization procedures to assess their applicability to the Residential Weatherization Program would be particularly timely now because of the questionable cost effectiveness of the current program, as indicated by this evaluation.

Recommendation 2: Bonneville should improve the audit procedure used in its Residential Weatherization Program.

The residential energy audit used in the RWP does not accurately estimate the energy to be saved by weatherization measures, and it may not be directing weatherization crews to install the most cost-effective measures. The audit significantly overestimates the program's aggregate energy savings, perhaps because it is overvaluing such measures as storm windows and storm doors. The program's audit procedures have changed very little over the duration of the long-term RWP, in part because of the burden such changes place upon the utilities and contractors that are familiar with the current audit procedures. However, it is time to consider adoption and implementation of a superior audit. DOE's low-income Weatherization Assistance Program has developed a national audit for use by its 1,000+ local weatherization agencies. This audit should be among the first to be reviewed for possible application to Bonneville's program. Adoption of an improved audit could significantly increase the cost effectiveness of the RWP.

Recommendation 3: Bonneville should continue to evaluate the persistence of RWP energy savings; it should also initiate on-site engineering analysis and household surveying to identify the factors influencing RWP savings decay.

The evaluations of Bonneville's weatherization programs have indicated that energy savings degrade somewhat as time elapses from when a household was first weatherized. It is unclear, however, how much energy savings can be expected to persist, and for how long. Further, we do not know how much of the degradation in savings is due to technological, behavioral, and other factors. Continued monitoring of postretrofit weatherization is needed to arrive at a robust estimate of conservation decay, for use in integrated resource planning and to help optimize the investment in weatherization. Field work is required to identify the causes of conservation persistence and decay.

9. REFERENCES

- Amir, E. and M. Ringer, 1987, *Relative Cost of Electricity Production*, California Energy Commission, Sacramento, California.
- Bonneville Power Administration, 1980, *Residential Weatherization Pilot Program*, Portland, Oregon.
- Bonneville Power Administration, 1982a, *BPA Home Energy Efficiency Program, Residential Weatherization*, Portland, Oregon, January.
- Bonneville Power Administration, 1982b, *Conservation Program Fact Sheet Residential Weatherization*, Portland, Oregon, October.
- Bonneville Power Administration, 1984, *Results of the BPA Residential Weatherization Pilot Program Evaluation*, Office of Conservation, DE-2, Portland, Oregon, August.
- Bonneville Power Administration, 1986, *Office of Conservation 1986 Yearbook*, Portland, Oregon.
- Bonneville Power Administration, 1992, *Conservation Acquisition Guidelines*, Portland, Oregon, September.
- Brandis, P. and B. Bronfman, 1987, "Captured Conservation: One Year of a Decade," *Proceedings of the 1987 Conference, Energy Conservation Program Evaluation: Practical Methods, Useful Results*, Volume 2, Argonne, Illinois: Argonne National Laboratory, pp. 435-444.
- Brown, M. A. and D. L. White, 1988, "Stimulating Energy Conservation by Sharing the Savings: A Community-Based Approach," *Environment and Planning A*, 20, pp. 517-534.
- Cohen, S. D. and C. A. Goldman, 1992, "Measured Energy Savings and Economics of Low-Income Weatherization Programs," *Summer Study on Energy Efficiency in Buildings, Proceedings*, American Council for an Energy Efficient Economy, Washington, D.C.
- Coyne, B., 1992, "A Million Miles of Ducts: Duct Sealing Update," *Home Energy*, 9(2), pp. 14-20.
- CSR, Inc. and Meridian Corporation, 1989, *Weatherization Evaluation Findings: A Comparative Analysis*, Alexandria, Virginia.
- Doyle, M. C., K. M. Lorberau, and L. A. Skumatz, 1991, *Process Evaluation of the Bonneville Long-Term Residential Weatherization Program: 1987-1989*, SRC Report No. 7582-R3, Synergic Resources Corporation, Seattle, Washington, April.
- Eissler, A., 1984, personal communication, Bonneville Power Administration, Office of Conservation, Portland, Oregon, January.
- Fels, M. F., 1986, "PRISM: An Introduction," *Energy and Buildings*, 9, pp. 5-18.
- Fels, M. F., J. Rachlin, and R. H. Socolow, 1986, "Seasonability of Non-heating Consumption and Its Effect on PRISM Results," *Energy and Buildings*, 9, pp. 139-148.

Goeltz, R., E. Hirst, and D. Trumble, 1986, *Electricity Savings One to Three Years After Participation in the BPA Residential Weatherization Program*, ORNL/CON-194, Oak Ridge National Laboratory, Oak Ridge, Tennessee, April.

Goldberg, M. L., 1986, "A Midwest Low-Income Weatherization Program Seen Through PRISM," *Energy and Buildings*, 9, pp. 37-44.

Haeri, M. Hossein, 1988, *Electricity Savings Three Years After Participation in the Bonneville Power Administration Regionwide Weatherization Program*, ERC/PO-34, ERC International, Portland, Oregon.

Hirst, E., B. Bronfman, R. Goeltz, J. Trimble, and D. Lerman, 1983a, *Evaluation of the BPA Residential Weatherization Pilot Program*, ORNL/CON-124, Oak Ridge National Laboratory, Oak Ridge, Tennessee, June.

Hirst, E., R. Goeltz, M. Thomsjo, and D. Sundin, 1983b, *Evaluation of the Home Energy Audit Retrofit Loan Programs in Minnesota: the Northern States Power Experience*, ORNL/CON-136, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Hirst, E., D. White, and R. Goeltz, 1985, *Three Years After Participation: Electricity Savings Due to the BPA Residential Weatherization Program*, ORNL/CON-166, Oak Ridge National Laboratory, Oak Ridge, Tennessee, January.

Hirst, E., R. Goeltz, D. White, B. Bronfman, D. Lerman, and K. Keating, 1985a, *Evaluation of the BPA Residential Weatherization Program*, ORNL/CON-180, Oak Ridge National Laboratory, Oak Ridge, Tennessee, June.

Hirst, E. and R. Goeltz, 1986, *Electricity Use for Residential Space Heating: Comparison of the Princeton Scorekeeping Method with End-Use Load Data*, ORNL/CON-203, Oak Ridge National Laboratory, Oak Ridge, Tennessee, April.

Hirst, E. and K. Keating, 1987, "Dynamics of Energy Savings Due to Conservation Programs," *Energy Systems and Policy*, 10(3), pp. 257-273.

Hirst, E., R. Goeltz, and D. Trumble, 1989, "Effects of the Hood River Conservation Project on Electricity Use," *Energy and Buildings* 13 (1), pp. 19-30.

Horowitz, M. J., B. H. Bronfman, and D. I. Lerman, 1987, *Evaluation of the Bonneville Power Administration Long-Term Residential Weatherization Program: The Data Gathering Report*, IEAL/PO-16, International Energy Associates Limited, Portland, Oregon.

Hwang, H. L., 1989, *Analysis of the Princeton Scorekeeping Method Using End-Use Data From the Hood River Conservation Project Submetered Houses*, ORNL/CON-270, Oak Ridge National Laboratory, Oak Ridge, Tennessee, March.

Nadel, S. M. and K. M. Keating, 1991, "Engineering Estimates vs. Impact Evaluation Results: How do they Compare and Why?" *Energy Program Evaluation: Uses, Methods, and Results*, Proceedings of the Fifth International Energy Program Evaluation Conference, pp. 24-33.

Narum, D., S. Pigg, and J. Schlegel, 1992, *Looking Past the First Year: Do the Savings Last?* Wisconsin Energy Conservation Corporation, Madison, Wisconsin, September.

Pratt, F., 1984, "Standard Heat Loss Methodology Energy Savings Estimates," Bonneville Power Administration White Paper, April.

Proctor, J. P. and R. K. Pemick, 1992, "Getting it Right the Second Time: Measured Savings and Peak Reduction from Duct and Appliance Repairs," *Summer Study on Energy Efficiency in Buildings, Proceedings*, American Council for an Energy-Efficient Economy, Washington, DC.

Response Analysis, 1991, *Low Income Home Energy Trends 1979 to 1989*, technical report, Response Analysis, Princeton, New Jersey, 1991.

Schweitzer, M., M. A. Brown, and D. L. White, 1989, *Electricity Savings One and Two Years After Weatherization: A Study of 1986 Participants in Bonneville's Residential Weatherization Program*, ORNL/CON-289, Oak Ridge National Laboratory, Oak Ridge, Tennessee, September.

Sumi, D. and B. Coates, 1988, *Longitudinal Evaluation of Energy Savings from Seattle City Light's Home Energy Loan Program*, Seattle, Washington: Seattle City Light.

U.S. Congress, 1978, *National Energy Conservation Policy Act*, Public Law 95-619, November 9.

U.S. Congress, 1980, *Pacific Northwest Electric Power Planning and Conservation Act*, Public Law 96-501, December.

White, D. L. and M. A. Brown, 1990. *Electricity Savings Among Participants Three Years After Weatherization in Bonneville's 1986 Residential Weatherization Program*, ORNL/CON-305, Oak Ridge National Laboratory, Oak Ridge, Tennessee, September

10. ACKNOWLEDGMENTS

This research was funded by the Office of Energy Resources, Bonneville Power Administration under the capable and helpful direction of Pam Brandis. Pam Brandis and Ken Keating (Bonneville Power Administration), Mark Thompson (Portland General Electric Company), Jeff Schlegel, Scott Pigg, and David Narum (Wisconsin Energy Conservation Corporation), Linda Berry, Jim Kolb, Martin Schweitzer, and Bruce Tonn (ORNL) provided comments on an earlier version of this report. Sherry Surdam and Ethel Schorn were responsible for keyboarding the report, and Mark Beyer and Ed Lapsa prepared the graphics. The input of each of these people is greatly appreciated.

APPENDIX A

Comparisons of Estimated, Unweighted Consumption, Based on Smaller vs. Larger Samples

**Table A.1 Unweighted average electricity consumption
for 1988 participants and nonparticipants:
Larger vs. smaller samples**

	Larger Sample		Smaller Sample	
	Sample size	Preretrofit energy use ¹	Sample size	Preretrofit energy use ¹
One year after weatherization	Participants (N=356)	23,230 (8,960)	Participants (N=324)	23,504 (7,911)
	Nonparticipants (N=1,170)	18,849 (9,598)	Nonparticipants (N=1,009)	19,969 (8,827)
Two years after weatherization	Participants (N=315)	23,657 (8,744)	Participants (N=277)	23,967 (7,859)
	Nonparticipants (N=1,084)	19,001 (9,598)	Nonparticipants (N=917)	20,107 (8,859)
¹ Numbers in parentheses are standard deviations.				

**Table A.2 Unweighted average electricity consumption
for 1989 participants and nonparticipants:
Larger vs smaller samples**

	Larger Sample		Smaller Sample	
	Sample size	Preretrofit energy use ¹	Sample size	Preretrofit energy use ¹
One year after weatherization	Participants (N=433)	22,091 (8,395)	Participants (N=382)	22,489 (7,978)
	Nonparticipants (N=1,466)	18,819 (8,974)	Nonparticipants (N=1,238)	19,816 (8,424)
¹ Numbers in parentheses are standard deviations.				

INTERNAL DISTRIBUTION

1 R.A. Balzer, 4500N, MS 6206	23 H.A. McLain, 3147, MS 6070
2 D. Bauer, 4500N, MS 6206	24 J.M. MacDonald, 3147, MS 6070
3 L.G. Berry, 4500N, MS 6206	25 W.R. Mixon, 3147, MS 6070
4 M.A. Brown, 4500N, MS 6206	26 D.E. Reichle, 4500N, MS 6253
5 R.S. Carlsmith, 4500N, MS 6188	27 M. Schweitzer, 4500N, MS 6206
6 C.V. Chester, 4500N, MS 6190	28 T.R. Sharp, 3147, MS 6070
7 S.M. Cohn, 4500N, MS 6205	29 R.B. Shelton, 4500N, MS 6187
8 G.E. Courville, 3147, MS 6070	30 B.M. Sorensen, 4500N, MS 6190
9 S. Das, 4500N, MS 6205	31-280 S.A. Surdam, 4500N, Room H11-D
10 W. Fulkerson, 4500N, MS 6247	281 M.P. Ternes, 3147, MS 6070
11 E. Hirst, 4500N, MS 6206	282 B.E. Tonn, 4500N, MS 6207
12 R.B. Honea, 4500N, MS 6179	283 D.L. White, 4500N, MS 6206
13 M.B. Gettings, 3147, MS 6070	284 T.J. Wilbanks, 4500N, MS 6184
14 S.W. Hadley, 4500N, MS 6206	285 ORNL Patent Office
15 L.J. Hill, 4500N, MS 6205	286 Central Research Library
16 E.L. Hillsman, 4500N, MS 6206	287 Document Reference Section
17 P.J. Hughes, 3147, MS 6070	288-290 Laboratory Records
18 M.A. Karnitz, 4515, MS 6065	291 Laboratory Records - RC
19 C.R. Kerley, 4500N, MS 6205	
20 J.O. Kolb, 3147, MS 6070	
21 M.A. Kuliasha, 4500N, MS 6189	
22 W.P. Levins, 3147, MS 6070	

EXTERNAL DISTRIBUTION

- 292 D.A. Beschen, U.S. Department of Energy, 5G-023, CE-70,
1000 Independence Ave., S.W., Washington, DC 20585
- 293-302 P. Brandis, Office of Energy Resources, Bonneville Power Administration,
P.O. Box 3621, Portland, OR 97208
- 303 B.G. Buchanan, Computer Science Department, University of Pittsburgh,
206 Mineral Industries Building, Pittsburgh, PA 15260
- 304 J.W. Cooke, DOE Oak Ridge Field Office, P.O. Box 2008,
Oak Ridge, TN 37831-6269
- 305 M.A. Fowler, U.S. Department of Energy, 5G-023, CE-532,
1000 Independence Avenue, S.W., Washington, DC 20585
- 306 A. Hirsch, Washington DC Office, 5109 Leesburg Pike, Falls Church, VA 22041
- 307 H.M. Ingram, Director, Udall Center for Studies in Public Policy,
The University of Arizona, 803/811 East First Street, Tucson, AZ 85719
- 308 C.D. MacCracken, President, Calmac Manufacturing Corporation,
101 West Sheffield Ave., P.O. Box 710, Englewood, NJ 07631
- 309 Ralph Nader, Post Office Box 19367, Washington, DC 20036
- 310 Office of Assistant Manager for Energy Research and Development,
DOE Oak Ridge Field Office, P.O. Box 2008, Oak Ridge, TN 37831-6269
- 311 OSTI, U.S. Department of Energy, P.O. Box 62, Oak Ridge, TN 37831
- 312 J.B. Shrager, Director, Office of Technology Transfer,
Vanderbilt University, 405 Kirkland Hall, Nashville, TN 37240
- 313 J. VanVlandren, U.S. Department of Energy, CE-532,
1000 Independence Ave., S.W., Washington, DC 20585
- 314 M. Williams, Professor, Department of Economics,
Northern Illinois University, Dekalb, IL 60115

END

DATE
FILMED
3 / 5 / 93