**Cover Sheet for a Hanford
Historical Document
Released for Public Availability**

Released 1994

**Prepared for the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830**

**Pacific Northwest Laboratory
Operated for the U.S. Department of Energy
by Battelle Memorial Institute**

C-57, 265
DECLASSIFIED

RL-7-B

RICHLAND

02 R&D PROGRAM

Classification Cancelled and Changed To

DECLASSIFIED

By Authority of RM-Hen
CG-NMP-1, 8-10-94
By J.E. Savely 8-18-94
Verified By Jerry Maley,
10-19-94.

ANNUAL SUMMARY REPORT

RICHLAND OPERATIONS OFFICE

ATLANTIC RICHFIELD HANFORD COMPANY

June 30, 1971

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DECLASSIFIED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, make any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

TABLE OF CONTENTS

	<u>PAGE</u>
INTRODUCTION	3
PROCESS DEVELOPMENT COST SUMMARY	4
PROGRAM DISCUSSION	
I. <u>BASIC PRODUCTION</u>	
A. Process Development - Extraction	5
B. Process Development - Plutonium	6
C. Equipment, Instrumentation and Materials	6
II. <u>ENVIRONMENTAL AND REGULATORY TECHNOLOGY</u>	
A. Atmospheric Dispersion of Radioactive Particles	9
B. Radionuclides in Soils	9
C. Seismic Investigations	11
III. <u>WASTE MANAGEMENT</u>	
A. Low- and Intermediate-Level Wastes	12
B. Salt Waste Processing	15
C. Waste Solidification in Tanks (ITS)	18
D. Waste Packaging	18
E. Salt Waste Volume Reduction	21
F. Alternative Solidification Methods	22
G. Solid Wastes	23
H. Gaseous Effluents	25
J. Waste Immobilization	25
DISTRIBUTION	27

UNCLASSIFIED

RICHLAND 02 R&D PROGRAM

ANNUAL SUMMARY REPORT

INTRODUCTION

This summary report was prepared by RL Production Planning and Development Branch. It presents the status as of June 30, 1971 of 02 Process Development activities performed and sponsored by the Atlantic Richfield Hanford Company for the AEC Division of Production.

Prior work, current accomplishments (during last half of FY 1971), and future work are covered. A summary of the Process Development costs is given on Page 4. A more detailed description of these activities is contained in ARHCO Annual Report - Process Development, ARH-1968-B, June 30, 1971.

UNCLASSIFIED

Page 3

[REDACTED]

PROCESS DEVELOPMENT COST SUMMARY

(\$ X 10³)

	<u>EXPENDITURES</u>	<u>BUDGET</u>	
	<u>FY 71</u>	<u>FY 72</u>	<u>FY 73</u>
<u>I. Basic Production</u>			
Process Development - Extraction	65	-	-
Process Development - Plutonium	50	39	42
Equipment, Instrumentation & Materials	28	11	15
Subtotal	143	50	57
<u>II. Environmental & Regulatory Technology</u>			
Atmospheric Dispersion of Radioactive Particles	90	75	110
Radionuclides in Soils	252	290	100
Seismic Investigations	10	5	65
**Biological Process	-	30	100
Subtotal	352	400	375
<u>III. Waste Management</u>			
Low and Intermediate Level Waste	196	136	213
Salt Waste Processing	145	65	30
Waste Solidification in Tanks	40	30	30
Waste Packaging	224	66	60
Salt Waste Volume Reduction	79	3	15
Alternative Solidification Methods	101	108	-
Solid Wastes	132	412	1020
Gaseous Effluents	13	-	-
*Waste Immobilization	19	230	600
Subtotal	949	1050	1968
Grand Total	1444	1500	2400

FY 71 expenditures were approximately 99.6 percent of the R&D budget (\$1,450,000).

* Related to long-term applications

** New Program

[REDACTED]

DECLASSIFIED

UNCLASSIFIED

BASIC PRODUCTION PROGRAM

This program is aimed at improving product quality and operating safety, and reducing product losses and operating costs while maintaining Hanford's capability to isolate and purify selected radioactive products.

A. Process Development - Extraction

1. Zirflex Tonic Effect

Studies have shown that the improved zirconium decontamination observed in the Purex Plant when processing zircaloy-clad fuel elements (declad in ammonium fluoride solutions - The Zirflex Process) was due to the presence of fluoride in the feed solutions.

Efforts during the report period were limited to issuance of a final report. ("Improved Zirconium Decontamination in the Purex Process", BNWL-1573, May 1971).

No further Process Development work is planned.

2. Computer Simulations of Solvent Extraction Flowsheets

The digital computer program, SEPHIS, which was developed at ORNL, was debugged, tested and utilized, with minor modifications, to simulate the Purex solvent extraction process.

Efforts during the report period were limited to issuance of a final report. ("Computer Program for Solvent Extraction Calculations", Letter Report, G. Jansen to G. Benedict, January 14, 1971).

Any future work will be carried out with Process Technology funds.

3. Dissolver Hydrogen Evolution

No quantitative work has been done on this project which is concerned initially with hydrogen evolution during the processing of canned plutonium-uranium scrap in the Purex dissolvers.

Work has been postponed in deference to higher priority projects.

This project will be held in abeyance until a specific need is identified.

UNCLASSIFIED

B. Process Development - Plutonium

1. Neptunium Chemistry HA Column

Development work has been planned to maximize neptunium recovery in the Purex HA Column while maintaining adequate decontamination from fission products.

The importance of acid concentration to neptunium recovery was verified and re-emphasized, e.g., the distribution of neptunium at equilibrium would be about three times greater from 3M HNO₃ than from 2M HNO₃. A decrease in zirconium DF can be avoided by the addition of fluoride. Experimental results were documented in a report. ("Neptunium and Zirconium Extraction under Purex HA Column Scrub Section Conditions", BNWL-1588, June 1971).

Future work will involve additional experiments to resolve some inconsistencies in the data.

2. Improved CC Column Cartridge

Development work is planned to study various plate and packing configurations for optimum mixing in the Plutonium Reclamation Facility's CC Column which has been adapted to a plutonium-uranium partitioning column by using a portion of the column scrub section to remove uranium from the plutonium product.

No work was performed on this project during the report period.

Future work will include building a CC Column mock-up to study the performance characteristics of various plate and packing configurations in this system.

C. Equipment, Instrumentation, and Materials

1. Neutron Interface Controller

Initial development studies have shown that an interface detection system (e.g., air-to-aqueous or aqueous-to-organic) which does not require penetration into the process vessel is feasible. A 105 gm Pu (as PuF₄) line source (sealed in a 1/2-inch pipe 20 inches long) was fabricated as the neutron flux source.

During the report period, studies were undertaken to minimize background effects and to optimize the moderation around the detector for maximum difference between organic and aqueous counts/min. A final unit, including all electronics and control valve, is being assembled for plant installation.

UNCLASSIFIED

The complete prototype interface control system will be installed on the CX Column in the Plutonium Reclamation Facility. If tests are successful, a similar unit may be installed on the CO Column. A final report will be issued.

2. Dispersed Phase Hold-Up

A 4-foot high by 4-inch diameter pulse column with replaceable cartridges, and a 100 gm Pu source (as PuF_4) were devised to determine if neutron or gamma attenuation can adequately detect a change in dispersed phase hold-ups, thus anticipating a potential flood.

No work was undertaken during the report period due to higher priorities.

Future work will include investigation of percent dispersed phase versus count rate using the 20-inch line source (100 gm Pu as PuF_4) and the 24-inch BF_3 detector. Other types of attenuation systems will be studied if this appears unsatisfactory. Should none of these prove feasible, newly developed solid state transducers will be investigated for possible application in the Plutonium Reclamation Facility CA extraction and CC stripping columns.

3. Nitric Acid Measurement in Slag and Crucible Dissolvers

A prototype unit consisting of a combined specific gravity-conductivity sensor assembly has been developed to measure and control the nitric acid strength in slag and crucible dissolvers which in turn controls both the hydrogen evolution and dissolution rates.

Due to higher priority items no work was performed on this project during the report period.

Future tests of the instrumentation in an experimental glass dissolver will be directed toward simplifying the system.

4. Instrumentation - General Application

Work has been pursued to develop new designs and to adapt existing materials, equipment, and instruments for application where no commercially available alternative exists.

During the report period, a digital circuit for the Pulse Frequency Controller was designed to replace the time delay relay which was the cause of previous malfunctions. Operation has proven successful and all controllers will be modified to the new circuitry. For Level

UNCLASSIFIED

Detection In Bowling Ball Cask, a capacitance probe using a quartz tube with a combination metal-electrolyte center conductor has been fabricated and laboratory tests are currently in progress.

Development efforts will be directed to the improvement of equipment wherever new and better concepts can be conceived.

UNCLASSIFIED

Page 8

UNCLASSIFIED

ENVIRONMENTAL AND REGULATORY TECHNOLOGY PROGRAM

This program is designed to provide the technical backup necessary to evaluate the effects of present and/or proposed waste management practices as well as evaluating potential accident situations.

A. Atmospheric Dispersion of Radioactive Particles

Small scale laboratory experiments have been conducted to provide order-of-magnitude estimates of the quantities of plutonium and its compounds made airborne in situations involving differing thermal and aerodynamic environments which might accompany accidents.

During the report period, the Radioactive Aerosol Release Test Facility was placed in service. Two tests were completed in which gasoline was burned on a soil surface containing uranium compounds as a stand-in for plutonium. One test utilized uranium oxide powder and the other uranyl nitrate solution which was allowed to dry prior to ignition of the gasoline. Air samples collected downwind from the burning source are currently undergoing analysis in the radiochemical laboratory. Alpha emitting particles in the 234-5 Building air exhaust system are being characterized to allow prediction of the areal distribution of these particles as a function of airborne concentration.

Future work will continue toward evaluating potential atmospheric release of plutonium and its compounds for the several postulated credible accident situations. The chemical and physical properties of the radioactive particulates will be studied as well as the atmospheric parameters which control their transport, diffusion, deposition, and resuspension.

B. Radionuclides in Soils

1. Radionuclide Transport Model

Mathematical models have been written to describe subsurface water movement and radionuclide transport in both the saturated and unsaturated sediments of the Hanford Reservation. The Variable Thickness Transient (VTT) flow model is operational and has been applied to several groundwater flow problems. Significant progress has been made toward resolving numerical instabilities in the Partially Saturated Transient (PST) flow model. The Transport Model (TM) was formulated for the special case of two-dimensional horizontal transport through an aquifer of varying thickness.

During the report period, a stable solution algorithm for the PST Model was successfully demonstrated. A new numerical scheme was formulated for solution of the transport equation, and the transmissivity iterative sequence which allows rapid computer-graphical interpretation of groundwater field data was completed.

UNCLASSIFIED

Future work will include historical verification of the VTT Model, laboratory verification of the ionic portions of the transport model, and laboratory and field verification of the PST Model. Integration of the PST, VTT, macro-ion and micro-ion models into an operational radionuclide transport model will undergo field verification.

2. Soil-Waste Reactions

Five parameters - initial solution in concentration, solid phase calcium carbonate in sediments, cation exchange capacity of the sediments, ion exchange constants, and the soluble components in the sediments - have been identified as principal factors which control reactions of radionuclides with Hanford sediments. Laboratory studies directed at measuring the sorption of Sr-85 on sediments as a function of pH, Na^+ , K^+ and Ca^{++} were completed.

During the report period, a study was undertaken to measure the variation of strontium movement as a function of depth for unsaturated soils of the Hanford Reservation. Another study was initiated to assess the areal variation of strontium movement in the saturated zone of the Hanford groundwater system for correlation with the transmissivity or permeability distribution.

Future work will define the characteristics of soil-waste reactions of all significant soil types underlying the Hanford Reservation with respect to the Hanford reference soil and the radionuclides of concern.

3. Field Measurement Methods

Development work has been underway to economically obtain hydrologic data for managing the Hanford groundwater system. Thermocouple psychrometers and soil temperature sensors were installed between the ground surface and the water table to measure the water content of vadose zone soils.

During the report period, a manual scanner for monitoring the moisture content and temperature in wells was installed and is operational. Analysis of field data indicates that the soil psychrometers in the wells are now at equilibrium and are reflecting field conditions.

Future work will include continued monitoring of in situ soil psychrometers and temperature sensors and a refinement of procedures for installing the system at other locations. Consideration will be given to measuring climatological parameters in the vicinity of well data collection points.

UNCLASSIFIED

C. Seismic Investigations

A number of studies related to assessing earthquake risks at Hanford have been made. Although the results have generally indicated that Hanford process facilities would probably withstand any likely experienced earthquake, additional factual data on the seismic characteristics of the area are needed. A five-year program of systematic data collection and analysis has been scoped and documented to utilize available national expertise.

During the report period, the 16 geophone array operated by the U. S. Geological Survey remained in operation measuring natural ground motion for seismic activity in the region. A short period seismograph system was received from the National Ocean Survey and installed on the south side of Gable Mountain.

Future work will include installation of a prototype system for measuring coupling characteristics between bedrock and structures in the 200-W Area. Eight more geophones will be installed. Consultants will be retained to evaluate previous seismic studies and to identify the investigation needed to provide the data required for an authoritative assessment of earthquake risk and protection to Hanford's radioactive waste storage system.

UNCLASSIFIED

Page 11

UNCLASSIFIED

WASTE MANAGEMENT PROGRAM

This program is directed toward eliminating trace amounts of radioactivity from effluents that are discharged; reducing wastes to the smallest possible volume and converting them to an immobile form for storage; and increasing the integrity of the containment facilities used for storage.

A. Low and Intermediate Level Wastes

1. Organic Phase Separations

The capabilities of two commercial decanters - needed to make an adequate phase separation of the Purex solvent wash wastes - were reviewed.

No work was performed on this project during the report period.

No further Process Development work is planned since the results of this project are not needed for the Purex Plant to complete its identified tasks.

2. Low-Level Radiation Monitoring Systems

Electropolishing and metal plating techniques have been developed for gross gamma monitor sample cells.

During the report period, two prototype sample cell assemblies were fabricated for evaluation in existing low-level effluent monitors. These cells are designed so that the beaker may be replaced, either to provide a new cell with a lower background or to evaluate a different plastic material.

In the future various plastic, electropolished metal, and electroplated metal sample cells will be evaluated under field conditions.

3. Alternative Treatment Methods

A process for the treatment of B Plant process condensate (BCP) by stream stripping followed by ion exchange to remove radioactive contaminants has been successfully demonstrated in the laboratory and the results have been formally reported. ("Ion Exchange Treatment of B Plant Process Condensate", BNWL-1544, November 1970).

UNCLASSIFIED

Page 12

UNCLASSIFIED

During the report period, three ion exchange column runs were conducted to determine the DF's and breakthrough after regeneration of the resin columns used for treating BCP. Laboratory results show that 98 and 100 percent of the cesium and strontium, respectively, are removed with 6 column volumes of 4M HNO₃. A laboratory study was initiated to evaluate the use of a two-layered ion exchange bed for decontaminating A-AX farm condensate. Zeolon was found to be effective for removing Cs-137, and Amberlite IR 200 is recommended for Sr-90 removal.

Future laboratory experiments are planned to evaluate performance of Amberlite IR 200 for removing strontium from A-AX farm condensate.

4. Subsurface Storage

The feasibility of using subterranean air injection to retard the flow of groundwater and to laterally expand the flow from a near surface liquid discharge facility has been studied.

During the report period, a bench scale plastic model was constructed to study the air-curtain technique. Although the air does interfere with saturated flow through porous media, attempts to "seal" against water flow at the air-solid interface were unsuccessful.

No further Process Development work is planned.

5. Fixation of Radioactive Wastes in Soils

Organic polymers (thermosetting resin type) have been evaluated for use in the fixation of radionuclides contained in the soil beneath crib disposal sites and in the salt wastes stored in underground tanks. These resins produced high-strength soil and salt mixtures with low leachability. Disadvantages include high cost, low tolerance to moisture, and high viscosity which limits the injection rate.

During the report period, laboratory studies were initiated on the use of Geoseal MQ-4N, a chemical grout, for the fixation of radionuclides in soil and salt cakes. The advantages of Geoseal MQ-4N are lower cost, lower viscosity and greater compatibility with salt wastes.

Future work will include steady-state, leach rate determinations on Geoseal-soil and Geoseal-salt mixtures. Other chemical grouts, "AM-9", "Cyanoloc-62", and "Siroc" will also be evaluated in the laboratory.

UNCLASSIFIED

6. Gamma Cell Development

Improved techniques for fabricating plastic sample cells have been developed. Electropolishing techniques were developed for stainless steel sample cells for use as gross gamma monitors.

During the report period, two stainless steel sample cells were fabricated. Both cells - one formed from a "U" shaped piece of tubing and the other from machined parts - were compatible with the existing process stream gamma monitoring systems. Results have shown that radioactive material retention was least on the electropolished surfaces and highest on machine-polished surfaces.

Future work will include the investigation of electroplated surfaces for contamination retention characteristics. Various forms of stainless steel will be evaluated for optimum electropolishing properties.

7. Nondestructive Plutonium Assay

Development work was undertaken to develop the technology and instrumentation to monitor scrap packages for plutonium without sampling.

During the report period, a counting system consisting of a Ge(Li) detector, a turntable for the package, and a Ba-133 self-absorption source was demonstrated. Anticipated measurement goals were exceeded, and the system should provide a strong contribution to the Safeguards program. A final report ("The Ge(Li)IV Plutonium-239 Package Counter", ARH-1993, March 1971) was issued.

No further Process Development work is planned.

8. Purex Process Solvent Treatment

The ability of Amberlyst macroreticular A-26 anion exchange resin to cleanup Purex process solvent (ICW) has been demonstrated in cyclic load-elution column tests.

During the report period, the application of A-26 resin to the cleanup of the 20 percent tributyl phosphate-carbon tetrachloride solvent from the Plutonium Reclamation Facility was demonstrated.

Future work will include column runs with PRF solvent under optimum flow and residence times to establish resin capacity and performance. Additional batch and column studies will be undertaken to investigate the use of A-26 resin for removing hydrazoic acid and iodine from used solvent.

UNCLASSIFIED

B. Salt Waste Processing

1. Strontium Purification

a. Ion Exchange

Laboratory studies to demonstrate the feasibility of purifying strontium from the B Plant first cycle solvent extraction product, using Linde 13-X inorganic exchanger, have been completed.

No work was performed on this project during the report period.

No further Process Development work is planned as strontium purification via a sulfate precipitation process has been successfully implemented in B Plant. A final report will be issued.

b. Multiple Sulfate Precipitation

Studies have been initiated to purify crude strontium by sulfate precipitation to provide the encapsulation plant with a feed that will meet specifications.

During the report period, laboratory studies were completed to define the flowsheets for strontium purification using sulfate precipitation. Plant testing of these flowsheets verified the reliability of this process and equations have been developed to predict flowsheet conditions. Utilizing solvent extraction or rare earth carrier precipitation processes on the sulfate wastes minimizes strontium losses.

Additional process optimization is planned to obtain greater product purity.

2. Continuous Centrifuge

The encouraging results of studies using batch-type centrifuges on prototype scale equipment to remove insoluble material from dissolver solutions for the Plutonium Reclamation Facility led to the evaluation of a continuous centrifuge.

During the report period, a commercial continuous centrifuge (Bird) was evaluated for both concentration of solids and clarification of liquid for a synthetic PAS slurry. Studies show that a continuous centrifuge could be used to clarify the PAS stream.

Selection of a specific model for plant use will depend on future requirements.

3. Corrosion Studies

Cathodic protection tests of carbon steel model waste storage tanks showed that an applied current of 10 ma/ft² prevented nitrate stress corrosion cracking during a two-year exposure under boiling conditions. Following the evaluation of several alloys for use in cesium chloride equipment, Hastelloy C-276 was recommended for construction of the CsCO₃ reaction vessel. Soil corrosion test data have indicated that the short-term corrosiveness of 200-W burial ground soil to mild steel is essentially independent of depth between 5 and 15 feet.

During the report period, an ASTM ferric-sulfate-sulfuric acid acceptance test for nickel base alloys was evaluated and accepted. Corrosion testing of candidate materials for the cesium chloride melter under process conditions showed that 18-18-2 stainless steel has adequate corrosion resistance. Resistance of carbon steel and 304L stainless steel to general corrosion by simulated concentrated alkaline waste solutions was found to be adequate.

Future work will include a study to determine the form of corrosive attack observed at the solution-air interface of the liner in several waste tanks. Investigation of the inhibiting effect of sulfate on the stress corrosion cracking of mild steel will continue to define the mechanisms involved. Corrosivity of process solutions associated with the isolation and packaging of Sr-90 and Cs-137 will continue to be evaluated.

4. Strontium Quality from Current Waste

Laboratory work has been performed to determine the path of cation constituents in CAW solvent extraction processing to enable prediction of strontium product quality. Distribution ratios have been determined for a typical B Plant process solution as a function of pH using various complexants.

During the report period, mercury distribution ratios were obtained as a function of pH and complexant. The distribution ratios of minor cations found in B Plant aqueous solution has been valuable in predicting the route of cations through solvent extraction processing.

Future studies will be performed to determine distribution ratios of Ni and Zr as a function of pH and complexant. The impact of these cations as well as anions (SiO₃⁻², SO₄⁻², PO₄⁻³) on strontium distribution ratios will be determined.

UNCLASSIFIED

5. Strontium Recovery from Stored Sludge

Development work has been undertaken to identify the reasons for the high strontium losses and material unaccounted for in the lead-carrier sulfate precipitation process.

During the report period, a second cycle solvent extraction for up-grading PASEX (PAS after one cycle of solvent extraction) prior to final multiple sulfate precipitation was tested with synthetic and a actual B Plant feeds. Results show that the direct purification of strontium from second cycle PASEX feeds will not provide a suitable feed for the encapsulation plant, but it will provide feed to the sulfate purification process which in turn produces a suitable product.

No further Process Development work is planned.

6. Cesium Recovery from Current Waste

The investigation of cesium recovery from acid wastes using a synthetic titanium base ion exchanger as an alternative to the PTA precipitation process was undertaken. Laboratory testing of "ABEDEM, Ti-A" with synthetic PAW-ZAW feed stocks has indicated good loading performance at relatively high feed rates.

No work was performed on this project during the report period.

Future work will only be undertaken if justified by production requirements.

7. Cesium Recovery from Sludge Sluicing Wastes

No work has been started on this project due to higher priority items.

If logistics make it desirable to blend these wastes with Redox supernatant (RSN), the necessary investigations for such blending will be undertaken.

8. Cesium Purification

This is a new program.

During the report period, investigation was started to evaluate the performances of Zeolon, an inorganic exchanger, and Duolite ARC-359, an organic exchanger, for cesium recovery and purification. Equilibrium ion exchange isotherms are being determined with these ion exchangers by the "progressive batch" method for $\text{Cs}^+\text{-M}^+$ ($\text{M} = \text{Na}, \text{K}, \text{or Rb}$) combinations in solution.

UNCLASSIFIED

Future work will continue to develop additional data needed to evaluate the results in terms of distribution coefficients and separation factors for cesium and the other alkali metals.

C. Waste Solidification in Tanks (ITS)

1. Waste Tank Thermal Analysis

Development work has been pursued to evaluate the effects of steady-state and transient heat losses from underground waste storage tanks to the surrounding soil. A computer program, SLUCE, was developed and used to estimate the steady-state temperatures for a wide range of tank operating conditions.

During the report period, a technique was developed for estimating the maximum temperatures in rectangular blocks of sludge as a function of the dimensions and thermal properties of the sludge. A computer program, THRAKE, was written to allow rapid temperature calculations.

Future work will include comparisons of the calculated results versus operating conditions for tank 108 SX and the AY tank farm. A report describing the program, SLUCE, will be written.

2. Waste Characterization

A thermal conductivity probe has been fabricated for making thermal conductivity measurements of sludge over a wide temperature range. Measurements were completed on a sample of sludge from tank 108 SX.

Thermal conductivity measurements of sludge from tanks 116 TX and 117 TX were completed during the report period. Values generally ranged from 0.22 to 0.28 BTU-ft/hr-ft²-°F.

Additional thermal conductivity measurements will be made on sludge samples as they become available.

D. Waste Packaging

1. Flowsheet Development

Both flowsheets for preparing CsCl and SrF₂ were confirmed using simulated and radioactive feeds. Methods for decontaminating ¹³⁷CsCl and ⁹⁰SrF₂ from metal surfaces were developed. Physical properties of CsCl-alkali metal chloride systems were evaluated as a function of alkali metal chloride content. Work to evaluate various candidate materials for containing SrF₂ during sintering was initiated.

UNCLASSIFIED

During the report period, the CsCl-alkali metal chloride systems, physical properties work was completed and a topical report was issued. ("Physical Property Measurements on CsCl and CsCl-Alkali Metal Chloride Systems", BNWL-B-74, March 1971). Inconel 600 was recommended as the material for furnace boats following the completion of testing of container materials for firing SrF_2 at 1100°C . Testing was begun to demonstrate that the strontium product from the purification process is suitable for conversion to SrF_2 and encapsulation.

Future work will complete the radioactive demonstrations of the compatibility of the B Plant strontium product with the SrF_2 flowsheet.

2. Compatibility Studies

Testing of both radioactive and nonradioactive SrF_2 and CsCl was initiated to evaluate their compatibility with containment materials.

During the report period, the two-year nonradioactive tests were completed and analyzed. Test results confirm those previously obtained, i.e., 316L SS is the best cladding material for CsCl and Haynes 25 is the best for SrF_2 . Double encapsulation (~ 200 mils total wall thickness) appears quite adequate.

The compatibility and radiolysis testing programs will be continued as scheduled.

3. Engineering Development

Determination of parameters for the precipitation, digestion, filtering, drying, and sintering of SrF_2 was completed. The melt-cast process was evaluated and selected for production of CsCl. Computer modeling of the cesium ion exchange purification process was started.

During the report period, design information and operating parameters were obtained for the production of CsCl. The process involves evaporating the CsCl solution, melting the cake, and casting the melt into a container which is welded shut. The CsCl melter is being fabricated. Computer programming was continued for a simulated inorganic cation exchange of cesium from potassium and sodium.

Equipment for SrF_2 production will remain operable for future work to evaluate alternative flowsheets. The CsCl evaporator-melter and casting machine will be tested to evaluate problems associated with the self-heating properties of $^{137}\text{CsCl}$. The cesium ion exchange computer program will be debugged.

UNCLASSIFIED

4. Encapsulation Development

Various methods of compacting SrF_2 were evaluated and impact consolidation was chosen for continued development work. Two prototype units were designed and built.

During the report period, a process was developed for densifying SrF_2 to >80 percent theoretical density.

Future work will be conducted with Process Technology funds. A final report will be issued.

5. Thermal Studies

Steady-state thermal calculations on SrF_2 and CsCl waste packages and the CsCl melter were made and preliminary analysis of thermal behavior of the capsule storage basins was completed.

During the report period, the computer program TIESOC was altered to permit temperature profile determinations of capsules in water as well as in air. Equations were developed which rapidly determine the effects of design changes on the thermal conditions of waste packages in air and water.

Future work will evaluate the time required for cooling CsCl capsules in the melt transfer mechanism. Thermal analysis of process equipment will continue as required.

6. Nondestructive Testing Support and Development

Prior work resulted in preliminary design of the electronic circuitry associated with the ultrasonic test system.

During the report period, the general design and development of the ultrasonic inspection system was essentially completed with the exception of the final detailed design of the local and remote test tanks. Testing of the prototype circuitry and scanning techniques has proven the system's capability for the satisfactory examination of waste capsules.

Development work on the NDT system will be documented and further weld development support will be performed as requested. Final design and fabrication of the NDT system will be funded by the Waste Encapsulation Facility project.

UNCLASSIFIED

7. Equipment Design and Procurement

Testing of empty and loaded (inert salts) CsCl and SrF₂ capsules for thermal cycling, thermal shock, internal and external pressurization, shear puncture, and impact resistance have been started.

Results of the capsule integrity testing completed during the report period show that the waste capsule design is mechanically and thermally sound.

Future work will test the capsule integrity of Hastelloy C-276.

8. Welding Development

Investigation has been conducted to develop welding techniques and equipment to satisfactorily make high integrity, full penetration welds on waste capsules by remote control operation.

Fabrication of the remote welding stations for in-cell use was started during the report period. Two automatic gas-tungsten-arc welding systems will be used for the capsule welding. A progress report was issued. ("Welding Development for the Waste Encapsulation Program, Interim Report No. 4", ARH-2029, April 1971).

Future work will be limited to adding final improvements on weld parameters for actual capsule material which should arrive onsite about December 1971.

9. Cell Mock-Up Facility

Plywood structures simulating B and D cells were constructed and three manipulators were purchased and installed in the mock-ups. A suitable arrangement of the cell equipment was obtained and incorporated in the final facility design.

During the report period, evaluation of the bag sealer confirmed the feasibility of sealing the waste drum plastic liner.

Future Process Development work with the mock-ups is not anticipated.

E. Salt Waste Volume Reduction

1. Platinum Catalyzed Hydrazine

The reductions of plutonium (IV) and uranium (VI) by hydrazine were found to be catalyzed by platinum.

UNCLASSIFIED

During the report period, copper, thallium, bismuth, and lead were found to be catalyst poisons. Catalyst poisoning problems make it highly unlikely that a continuous process employing platinum-catalyzed hydrazine reduction of uranium (VI) could be developed. A final report was issued. ("Platinum-Catalyzed Hydrazine Reductions of Plutonium (IV) and Uranium (VI)", BNWL-1584, June 1971).

No further Process Development will be undertaken.

2. Hydroxylamine Nitrate-Hydrazine

Prior work on the kinetics and stoichiometry of the reduction of plutonium (IV) with hydroxylamine nitrate shows that the reduction is complex and involves a number of stages.

During the report period, reaction rates were determined for various initial concentrations of reactants using stopped-flow techniques. Experimental data has been documented. ("Hydroxylamine Nitrate Reduction of Plutonium (IV): Iron Catalysis", ARH-1920, January 1971).

Rate constants for the postulated rate law will be calculated in the future, and their temperature dependence will be determined.

3. Alternative Reductant for Neptunium Recovery Cycle

The use of uranium (IV) as an alternate plutonium reductant in the Purex first partition cycle has been demonstrated.

During the report period, flowsheet studies were continued to test alternate reductants in the Purex IBX column. Plutonium and neptunium were successfully co-extracted using a proposed HNO_2 neptunium recovery flowsheet.

Laboratory work has been cancelled due to the limited life expectancy of the Purex Plant. Flowsheet tests to lower use of iron in J Cell Package will be demonstrated in the plant using Process Technology funds.

F. Alternative Solidification Methods

1. Fluidized Bed Calciner

A 4-inch diameter model fluid bed calciner has been designed and constructed.

A number of runs were made on the unit during the report period to optimize process conditions and improve process hardware. Efforts have been directed toward optimizing nozzle performance to assure continuous process operation. Experimental work has shown that a

UNCLASSIFIED

synthetic mixture of the radioactive aqueous waste can be successfully calcined to form a granular solid product with a 6:1 volume reduction.

Future work will include a third run campaign to investigate a fuel mixture of kerosene and synthetic liquid organic wastes. A fourth campaign will use actual radioactive salt wastes combined with a synthetic fuel mixture followed by a fifth campaign using synthetic feeds in a 12-inch diameter unit.

G. Solid Wastes

1. Instrumentation for Sorting

This is a new program.

The techniques of applying semiconductor detector and computer technology to automated radioactive waste segregation and inventory system needs developing. An accurate inventory of all long-lived beta-gamma and alpha-gamma emitting isotopes in packaged waste appears feasible.

Future work will establish automated sorting criteria from both NaI(Tl) and Ge(Li) detector data. A technique of equalizing activity emission from all parts of a package that is rotated or laterally scanned will be developed as well as a versatile data format for computer output.

2. Process Equipment Decontamination

This is a new development program.

Work during the report period has determined the fission product composition on the surface of metallic equipment from B Plant using gamma energy analysis. The nature of the surface and the effect of decontaminating solutions is being studied using microprobe analysis.

Future work will complete the economic evaluations of applicable equipment decontamination flowsheets. Contaminated equipment typical of 200 Area processes will be studied.

3. Process Equipment Disposal

This is a new development program.

Experimental work to date has been directed at finding crucible materials to contain molten stainless steel and various slag systems

UNCLASSIFIED

at 1500°C. Preliminary results indicate that metal can be decontaminated by melting it down in contact with a slag phase, i.e., the radioactive contaminants dissolve in the slag leaving a relatively clean metal phase.

Further testing will continue to develop slags which will remove a greater percentage of the radioactive species present in the contaminated metal.

4. Salt Cake Volume Reduction

This is a new project.

A program outline was established to determine the feasibility of reducing the volume of salt cake wastes. The six potential processes to be evaluated are: Electrolytic Reduction, Membrane Separation, Precipitation, Metallic Reduction, Solvent Extraction/Ion Exchange, Calcination and Fusion.

The most promising processes for further development will be selected and in-depth studies will be made to develop the necessary technology.

5. Alternatives to Incineration

This is a new project.

Small laboratory equipment has been set up, and future experimental work will determine the technical and economic feasibility of using a molten salt system to decompose or oxidize radioactivity contaminated combustibles.

6. Automated Radioactive Waste Inventory System

This is a new project.

Considerable experience with semiconductor detector technology and recent successful experience with the Ge(Li)IV Plutonium-239 Package Counting System indicates that an automated radioactive waste inventory system using existing radiation detector technology is feasible.

Future work will be directed toward establishing an automated sorting criteria from Ge(Li) detector data which will permit routing of a given package to storage, to Pu-239 recovery, or to additional compaction.

UNCLASSIFIED

7. Solid Waste Decay Calculations

Development work has been undertaken to determine the influence of the daughters of the parent actinide on long-term hazard considerations.

During the report period, a Hazard Index (sum of the radioactive nuclides, in curies, divided by the respective MPC_w) was calculated for several actinides for periods of up to a million years. Results show that the daughters must be considered in formulating any long-term storage or disposal plans.

No further Process Development work is anticipated. A final report is being written.

H. Gaseous Effluents

1. Tritium Disposal

A program was established to define the technology for containing tritium in the Purex Plant.

During the report period, evaluation of process requirements, methods for process comparison, and conceptual plant designs were started in order to select processes that would be practical for removing tritium from aqueous wastes.

This program is being discontinued due to the limited life of the Purex Plant. A final report will be issued.

J. Waste Immobilization

1. STOPPER: Stone Process for Permanent Encapsulation of Radionuclides

Development work has been undertaken to explore the system of complex silicate solids produced hydrothermally for the long-term storage of radioactive wastes.

During the report period, samples of synthetic pollucite (cesium aluminum silicate) were prepared and preliminary leaching and thermal stability tests were made. Autoclaves for hydrothermal crystallization studies are being installed. A report was issued. ("Guidelines to Radioactive Waste Management", ARH-2080, May 1971).

Additional study of the conditions most favorable for the production of complex cesium, strontium, and plutonium silicates is planned.

UNCLASSIFIED

2. Thermalt Waste Immobilization

Investigation of the system of complex silicate solids produced by liquid melts and exothermic chemical reactions for long-term storage of radioactive wastes has been undertaken.

During the report period, simulated wastes (35 percent nitrates) were reacted with 13 percent aluminum granules using 52 percent basalt and silica sand for control. The silicious rock-like products had lower leach rates than previously reported for other types of solidified wastes. Hanford surface soil was substituted for the basalt and silica in some tests and produced a similar product but with greater crystallinity. A report was issued. ("Thermalt Process for Immobilization of Radioactive Wastes", ARH-2059, May 1971).

Future work will be directed toward solving the problem of sublimate formation during these high temperature reactions.

3. Basalt Melt Process

Melting a mixture of solid waste and basalt is another high-temperature disposal concept that is being studied.

Preliminary studies of this process were performed during the report period. A mixture of crushed 85 w/o basalt, and an inert 15 w/o cesium compound was melted. Fusion of pollucite and basalt occurred without evolution of cesium. A report was issued. ("Laboratory Studies of Methods for Permanent Disposal of Hanford Radioactive Wastes", ARH-2064, April 1971).

Future work will be directed toward melt experiments with synthetic wastes for thorough characterization of melt products. Such characterization will include water leachability, thermal shock treatments, X-ray diffraction analysis, chemical composition determination, and thermal (DTA and TGA) analysis.

UNCLASSIFIED

DISTRIBUTION

OFFSITE

- 1-5. F. P. Baranowski, AEC-HQ
- 6. W. L. Ginkel, AEC-ID
- 7. S. R. Sapirie, AEC-OR
- 8. N. Stetson, AEC-SR

RICHLAND OPERATIONS OFFICE

9. J. T. Christy	15. T. A. Nemzek
10. O. J. Elgert	16. H. E. Parker
11. E. B. Jackson	17. R. L. Plum
12. R. H. Lindsey	18. M. R. Schneller
13. W. E. Lotz	19. D. G. Williams
14. J. E. McDonald	20. Record Copy

ATLANTIC RICHFIELD HANFORD COMPANY

21. R. P. Corlew	24. L. M. Richards
22. R. E. Isaacson	25. R. E. Tomlinson
23. E. T. McIntyre	26. J. H. Warren

BATTELLE-NORTHWEST

27. E. L. Alpen	31. R. S. Paul
28. J. M. Batch	32. W. D. Richmond
29. R. E. Burns	33. J. R. Young
30. D. E. Olesen	

DOUGLAS UNITED NUCLEAR, INC.

34. C. W. Kihlman	35. R. K. Robinson