DISTRIBUTION SHEET

To Distribution	From 7FD10	Page 1 of 1			
		Date 11/4/94			
Project Title/Work Order Application of the Department of Energy Prescribed Guides to the Evaluation of the Hanford Site Mixed Low-Level Solid Waste Treatment Options		EDT No. 157033			
		ECN No. n/a			

Name	MSIN	Text With All Attach.	Text Only	Attach./ Appendix Only	EDT/ECN Only
D. E. Ball	G6-46	x			
B. F. Campbell	G3-15	x			
O. L. Kruger	H5-33	x			
M. M. McCarthy	N3-13	x			
C. R. Nash	G3-15	x			
T. R. Pauly	G6-47	x			
C. A. Petersen	G6-47	x			
J. A. Swenson	G6-45	x			
T. L. Yount	G6-47	x			
Central Files (2)	L8-04	x			
SWOC/DMC	G6-51	x			
OSTI (2)	L8-07	x			

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

Sta # 10

NOV 15 1994

23

ENGINEERING DATA TRANSMITTAL

Page 1 of 1

1. EDT 157033

2. To: (Receiving Organization) Solid Waste Operations		3. From: (Originating Organization) WRAP & Solid Waste Projects		4. Related EDT No.: n/a	
5. Proj./Prog./Dept./Div.: W100/WRAP		6. Cog. Engr.: BF Campbell/CR Nash		7. Purchase Order No.: n/a	
8. Originator Remarks: Application of DOE Prescribed Guides to the Evaluation of Hanford's Mixed Low Level Solid Waste Treatment Options				9. Equip./Component No.: n/a	
				10. System/Bldg./Facility: n/a	
11. Receiver Remarks:				12. Major Assm. Dwg. No.: n/a	
				13. Permit/Permit Application No.: n/a	
				14. Required Response Date: n/a	

15. DATA TRANSMITTED					(F)	(G)	(H)	(I)
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	Approval Designator	Reason for Transmittal	Originator Disposition	Receiver Disposition
1	WHC-SD-W100-ES-009		0	Application of DOE Prescribed Guides to the Evaluation of Hanford's Mixed Low Level Solid Waste Treatment Options	n/a	1		

16. KEY					
Approval Designator (F)		Reason for Transmittal (G)		Disposition (H) & (I)	
E, S, Q, D or N/A (see WHC-CM-3-5, Sec.12.7)		1. Approval	4. Review	1. Approved	4. Reviewed no/comment
		2. Release	5. Post-Review	2. Approved w/comment	5. Reviewed w/comment
		3. Information	6. Dist. (Receipt Acknow. Required)	3. Disapproved w/comment	6. Receipt acknowledged

17. SIGNATURE/DISTRIBUTION (See Approval Designator for required signatures)										(G)	(H)
Reason	Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(J) Name	(K) Signature	(L) Date	(M) MSIN	Reason	Disp.
1		Cog.Eng. BF Campbell/CR Nash	<i>[Signature]</i>	11/1/94	G3-15	TL Erickson	<i>[Signature]</i>	11/1/94	H5-33	1	1
1		Cog. Mgr. CA Petersen	<i>[Signature]</i>	11/1/94	G6-47	OL Kruger	<i>[Signature]</i>	11/1/94	H5-33	1	1
		QA				MM McCarthy			N3-13		
		Safety				CR Nash	<i>[Signature]</i>	11/1/94	G3-15	1	
		Env.				JA Swenson	<i>[Signature]</i>	11/1/94	G6-45	1	
1	1	DA Burbank	<i>[Signature]</i>	11/7/94	G6-47	TL Yount	<i>[Signature]</i>	11/1/94	G6-47		
		DE Ball			G6-46						

18. Signature of EDT Originator <i>[Signature]</i> BF Campbell/CR Nash Date: 11/1/94		19. Authorized Representative Date for Receiving Organization <i>[Signature]</i> CA Petersen Date: 11/4/94		20. Cognizant Manager Date <i>[Signature]</i> CA Petersen Date: 11/4/94		21. DOE APPROVAL (if required) Ctrl. No. ☐ Approved ☐ Approved w/comments ☐ Disapproved w/comments	

RELEASE AUTHORIZATION

Document Number: WHC-SD-W100-ES-009, Rev. 0

Document Title: Application of DOE Prescribed Guides to the
Evaluation of Hanford's Mixed Low Level Solid Waste
Treatment Options

Release Date: 11/10/94

**This document was reviewed following the
procedures described in WHC-CM-3-4 and is:**

APPROVED FOR PUBLIC RELEASE

WHC Information Release Administration Specialist:

Chris Willingham
C. Willingham

11/10/94

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

This report has been reproduced from the best available copy. Available in paper copy and microfiche. Printed in the United States of America. Available to the U.S. Department of Energy and its contractors from:

U.S. Department of Energy
Office of Scientific and Technical Information (OSTI)
P.O. Box 62
Oak Ridge, TN 37831
Telephone: (615) 576-8401

Available to the public from: U.S. Department of Commerce
National Technical Information Service (NTIS)
5285 Port Royal Road
Springfield, VA 22161
Telephone: (703) 487-4650

SUPPORTING DOCUMENT		1. Total Pages 19
2. Title Application of DOE Prescribed Guides to the Evaluation of Hanford's Mixed Low Level Solid Waste Treatment Options	3. Number WHC-SD-W100-ES-009	4. Rev No. 0
5. Key Words Application of DOE prescribed guides to the evaluation of Hanford's mixed low level solid waste treatment options	6. Author Name: BF Campbell/CR Nash Signature: <i>[Handwritten Signature]</i> Organization/Charge Code 7FD10/A5211	
7. Abstract A recent Westinghouse Hanford Company report (WHC-SD-W100-ES-008, February, 1994), compared a Vitrification process to the WRAP-2A Grout/PE process for the treatment of Mixed Low Level Waste (MLLW). This comparison applied a limited scope numerical evaluation to compare technology complexity of the two processes, but focused primarily on capital and operating costs. The work reported here is supplementary to WHC-SD-W100-ES-008. It provides a record of the application of the more formal DOE-prescribed criteria (Treatment Selection Guides for Federal Facility Compliance Act Draft Site Treatment Plans) to the Vittrification and Grout/PE processes previously evaluated. Results of the evaluation favored the Grout/PE process by a weighted score of 83 to 78 over the Plasma arc vitrification process.		
		8. RELEASE STAMP OFFICIAL RELEASE BY WHC DATE NOV 15 1994 <i>[Handwritten: 62-#10]</i>

**APPLICATION OF
THE DEPARTMENT OF ENERGY
PRESCRIBED GUIDES TO
THE EVALUATION OF
THE HANFORD SITE
MIXED LOW-LEVEL
SOLID WASTE TREATMENT
OPTIONS**

OCTOBER 1994

B. F. CAMPBELL
C. R. NASH

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

Westinghouse Hanford Company
Richland, Washington

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

CONTENTS

1.0	INTRODUCTION	1
2.0	SUMMARY	1
3.0	DISCUSSION	2
3.1	Definitions of Guides	2
3.2	Prioritization of Guide Elements	2
3.3	Scoring Guide	2
3.4	Determination of Scores	2
3.5	Summary Results	2
4.0	REFERENCES	3
	APPENDIX A: SELECTION GUIDE DEFINITIONS	4

APPLICATION OF DOE PRESCRIBED GUIDES TO THE EVALUATION OF HANFORD'S MIXED LOW LEVEL SOLID WASTE TREATMENT OPTIONS

1.0 Introduction

A recent Westinghouse Hanford Company report (WHC-SD-W100-ES-008, February, 1994), compared a Vitrification process to the WRAP-2A Grout/PE process for the treatment of Mixed Low Level Waste (MLLW). This comparison applied a numerical evaluation, based on engineering judgement, to technology complexity, but focused primarily on capital and operating costs. The report favored the Grout/PE process over the Vitrification process.

The DOE Federal Facility Compliance (FFC) Act Task Force issued, in March, 1994, a broader set of treatment selection guides than were used in the above WHC analysis. These DOE guides, or criteria, are in part a distillation of similar guides used throughout the DOE nuclear complex. They have been prescribed for use in comparing candidate treatment options and in selecting the preferred option in the development of Draft Site Treatment Plans.

The work reported here is supplementary to WHC-SD-W100-ES-008. It provides a record of the application of the DOE-prescribed criteria to the Vitrification and Grout/PE processes previously evaluated. This was accomplished by adapting the DOE guides, where necessary, to conditions unique to the Hanford Site, establishing priorities (weighting) for guide elements and numerically evaluating the process options against each guide element, thus establishing a weighted score for comparison of the treatment technologies.

2.0 Summary

Results of the evaluation favored the Grout/PE process by a weighted score of 83 to 78 over the Plasma Arc Vitrification process. The major elements of difference in scoring are:

- ♦ Permitting and development of the EIS for the Vitrification process, particularly the offgas system, is seen as significantly more time consuming than for the Grout/PE process.
- ♦ Achieving and maintaining regulatory compliance of the offgas system is a further difficulty with the Vitrification process.
- ♦ The Vitrification process is perceived as more complex, and operates at much higher temperatures than Grout/PE, drawing a penalty in the areas of availability and safety.
- ♦ On the other hand, Vitrification has significant advantages in volume reduction, destruction and immobilization efficiency (e.g. organics) and is perceived by the public as a superior waste form.

The results of this evaluation are consistent with the conclusions drawn in February, 1994 (WHC-SD-W100-ES-008).

3.0 Discussion

3.1 Definition of Guides

The definition of the evaluation guides (Appendix A) is excerpted from the FFCAct Task Force report. These definitions were used to establish a common perspective during the actual scoring phase. Exception was taken to the definition of "Lifecycle Cost", which was modified to contain two elements: 1) true lifecycle costs - capital, operating and D&D and 2) the present worth summation of lifecycle costs. The DOE definition included only capital costs.

3.2 Prioritization of Guide Elements

Each guide element was prioritized, or weighted, in accordance with its significance to the Solid Waste Disposal Program and to conditions specific to the Hanford Site. Weighting factors ranging from 1 to 5 were applied, with 5 representing the highest degree of importance to the evaluation. The weightings and the reasoning or justification behind them are shown in table 1. As indicated, the highest priorities were given to safety-related criteria, and the lowest to Hanford-unique transportation considerations.

3.3 Scoring Guide

The FFCAct Task Force report provided a scoring guide which established criteria for applying a "low", "medium" or "high" score for an option against an evaluation criteria sub-element. This guide was adapted to allow for scoring from 1 to 5 (similar to the weighting factors) and was modified, where possible, to provide quantifying bases for scoring. It also adjusts some of the quantifying values provided by DOE to reflect Hanford conditions. See Table 2.

3.4 Determination of Scores

The scoring of each process against the criteria of the Guides is summarized in Table 3. This table records the principal analysis effort performed to evaluate the process options. It provides either a quantified basis, where possible, or an engineering judgement basis to assign a particular score.

The actual scoring was determined in an interactive meeting of seven engineering personnel, with a consensus obtained on each score. Cost information for the process comparison was obtained from the February Vitrification Study (WHC-SD-W100-ES-008). The scores ascribed to each Guide sub-element were multiplied by the respective weighting factor to obtain a weighted score for the sub-element as applied to each process.

3.5 Scoring Results

The final scoring is summarized in Table 4, which shows the weighted scores established for each of the treatment options against the major guide categories. For each category the score represents the average of the weighted scores of each sub-element within the category. The total score of 83 for grout/PE and 78 for vitrification supports the selections of grout/PE as the most favorable treatment process for MLLW at Hanford (Tables 1, 2, 3, 4).

TABLE 1

PRIORITIZATION OF TREATMENT SELECTION GUIDES
(score of 1-5, in order of priority, identified as weighting factor [wf])

1. Regulatory Response (wf-3)

This reflects an average priority in concern over the regulatory maturity of a technology. The nominal level of importance placed on this factor avoids over-weighting a process having a track record of permitting success in favor of promising, but newer and less proven technologies.

2. Environment, Health and Safety (average wf-4)

This is the average of the weighting applied to the sub-guides of this category, discussed below:

- **Environment/Public H & S (wf-5):** High public awareness, stakeholder energy level and the sensitivity of the viability of a technology to this factor warrants the highest weighting of 5 to be applied.
- **Non-Operational Worker Health and Safety (wf-4):** Consequences of non-operational events would negatively impact facility, programmatic or construction management, but would not likely result in severe facility or technological penalties. A moderately high weighting of 4 is considered warranted.
- **Operational Worker Health and Safety (wf-5):** This represents risks more intimately connected to the technology, design and operational continuity of the facility than the above non-operational concerns. Accordingly, and in keeping with the generally high priority accorded worker safety, a weighting of 5, comparable to that applied to environmental and public safety, is considered justified.
- **Transportation Risk (wf-2):** Off-site shipment of treated/immobilized mixed low level waste is not planned at Hanford. On-site delivery of final waste forms to RCRA approved landfills is not considered to pose a significant risk. The low weighting of 2 appropriately reflects this finite but low risk intrinsic to Hanford's situation.

3. Treatment Effectiveness (wf-3)

- **Volume Reduction (wf-3):** This factor is moderately significant at Hanford as it relates to the cost of disposal in RCRA landfills. The quantity of public land committed to this purpose is also significant, but to a lesser degree at Hanford than for many other treatment/disposal sites. An average weighting of 3 is an appropriate priority to assign to this sub-element.
- **Secondary Waste Reduction (wf-3):** This is of significance as an element of cost and time in the development/design phase of a program. If not resolvable with the initial technology selected, this approach is abandoned and a new technology pursued. It is of average priority (wf-3) in comparison to other technical aspects of a treatment system.

- **Destruction, Removal, and/or Demobilization Efficiency (wf-3):** A weighting of 3 is assigned this factor for the same reasons as for Secondary Waste Reduction.

- **Flexibility (wf-4):** This sub-element, which relates to adaptability to uncertainties and variability in feed stock, is considered to have more significance at Hanford than other treatment effectiveness factors. A generally higher weighting (4), but less than maximum (considered primarily for safety related elements), is considered appropriate.

- **Final Waste Form Performance (wf-3):** No question of the importance of this element, but the priority to be placed on it, following the rational applied to other sub-elements, above, is appropriately represented by an average weighting of 3.

- **Ability to be Shipped (wf-2):** Rational for applying a weighting factor of 2 is the same as above for Transportation Risk.

4. Implementability (wf-4)

All sub-elements of Implementability are assigned a weighting factor of 4. These elements all relate to the reliability of the treatment process to come on line and achieve the mission objective, with flexibility and capacity to meet demand contingencies. This reasonably high priority is responsive to the consensus desire to resolve this waste legacy problem.

5. Stakeholder Concerns (wf-4)

Stakeholder involvement and influence on the course of waste programs is a highly significant factor at Hanford and warrants substantial priority. Since most of the considerations of the sub-elements, Equity Concerns and Public Acceptance, relate to Treatment Effectiveness and Health and Safety, a weighting of 4 -- the average of the later two major guides -- is appropriate.

6. Lifecycle Costs (wf-4)

The efficient use of resources and judicious commitment of future federal funds is a major stewardship responsibility of waste program management. A moderately high weighting of 4 for this very significant guide element is assigned.

7. Technology Development (wf-2)

The two sub-elements of this guide, Marketing for Technology and Private Sector Involvement are significant factors to the long term economic health of the general Hanford area. However, although there is a growing trend toward privatization, the technology selection drivers are similar whether there is governmental or commercial control of the final system. Therefore, in relationship to other waste treatment selection guides, Technology Development cannot be considered a high priority, nor is it to be ignored. The assigned weighting of 2 carries with it some, but not a distracting significance.

TABLE 2

SCORING GUIDE

SELECTION GUIDES/CRITERIA	HIGH SCORE (5-4)	MIDDLE SCORE (3)	LOW SCORE (2-1)
REGULATORY COMPLIANCE:			
Regulatory Compliance (weight = 3)	All process-related regulations are met through standard processes	Most regulations are met, with the balance possibly met through requests for variance	Majority of regulations cannot be met without variances or other extensive measures
ENVIRONMENT, HEALTH, SAFETY:			
Environment/Public Health (weight = 5)	Little of no facility emissions for routine operations or under all but the most catastrophic accidents	Little or no facility emissions for routine operations but significant releases under most accident conditions	Marginally acceptable releases under routine operations and/or extensive releases under most accident conditions
Non-Operational Worker Health and Safety (weight = 4)	Significantly fewer construction/decommissioning workers and less routine maintenance required	Average number of workers and non-routine maintenance required (relative to other technologies)	More complex than average facility construction, non-routine maintenance and decommissioning
Operational Worker Health and Safety (weight = 5)	Significantly fewer workers potentially exposed or potential exposure much lower than average	Average number of workers and potential exposure levels	Greater than average number of workers required or greater than average potential exposure to the work force
Transportation Risk (weight = 2)	No off-site transportation of treated or untreated waste required	Limited additional characterization required to support transportation, no new packaging/certification facilities required, and limited waste transports required	Significant additional waste characterization required for transportation, new packaging/certification facilities required, large number of waste transports needed, or large number of miles required for each waste shipment
TREATMENT EFFECTIVENESS:			
Volume Reduction (weight = 3)	Reduction 20-50% = 4 > 50% = 5	Volume after processing is between 80 to 120% of feed volume	Volume change: 120-200% = 2 > 200% = 1
Secondary Waste Generation (weight = 3)	Secondary waste is easily treated using existing technologies	Treatment of secondary wastes requires modification of existing technologies	Secondary waste has no known technology for treatment
Destruction, Removal, & Demobilization Efficiency (weight = 3)	All of the applicable LDR standards are met	Additional LDR Treatment is required for some of the constituents and technology exists	Additional treatment is required to meet requirements & technology does not exist or requires modification
Flexibility (weight = 4)	Minimal system inefficiencies are experienced for off-design input	Off-design inputs are acceptable but cause reduced efficiency	Special precautions must be taken to avoid off-design input
Final Waste Form (weight = 3)	Meets the expected disposal WAC	Residues require additional treatment to meet disposal WAC and technologies exist	Significant additional treatment is required prior to disposal and/or technology does not exist
Ability to be Shipped (weight = 2)	Treatment residuals meet shipping requirements without any additional treatment	Treatment residuals only require simple physical treatment to meet shipping requirements	Treatment residuals require extensive treatment to meet shipping requirements

TABLE 2

IMPLEMENTATBILITY:			
System Implementability (weight = 4)	Most of the system elements and process previously demonstrated. Prototype = 4 Production = 5	50 - 25% of the elements have been previously demonstrated at production or prototype levels	Few or no elements demonstrated < 25% = 2 < 10% = 1
Availability (weight = 4)	Facility or system exhibits superior reliability Downtime 40 - 30 % = 4 < 30% = 5	Availability expected to be 60 - 50%	Availability expected to be <50% - 40% = 2 <40% = 1
Scalability (weight = 4)	Process can be easily expanded for economies of scale	Process can accept a range of input but has limitations for expansion	Process is limited and cannot be expanded for economies of scale
Schedule for Waste Treatment (weight = 4)	Waste can be processed within short time frame, schedule allows for some slippage	Waste can be processed within required time frame but allows for no slippage	Critical path approaches of exceeds milestones for designated waste
STAKEHOLDER CONCERNS:			
Equity Concerns (weight = 3)	Regulators accept facility plans With few concerns = 4 With no concerns = 5	Some concerns of the regulators could affect schedule and design	Significant regulator concerns: Serious impact to schedule and design = 2 Jeopardize program = 1
Public Acceptance (weight = 3)	Stakeholders accept the process and risks	Some stakeholder concerns that could affect the successful utilization of the technology	Significant stakeholder concerns about process
LIFECYCLE COSTS:			
Lifecycle Costs (weight = 4)	Lifecycle costs significantly less than other alternative 10 - 20% = 4 > 20% = 5	Lifecycle costs of alternatives within 10%	Lifecycle costs significantly greater than other alternative 10 - 20% = 2 > 20% = 1
TECHNOLOGY DEVELOPMENT:			
Market for Technology (weight = 2)	Numerous markets are identified within and outside DOE	More than one market is identified within and outside DOE	Few or no markets or needs are identified
Private Sector Involvement (weight = 2)	Private sector technology company is identified with experience and interest and has experience in permitting activities	A private sector party has expressed an interest; however, has little or no experience in this type of activity or permitting processes	No private sector companies have expressed and interest or a need for the technology

TABLE 3

EVALUATION SCORES
VITRIFICATION VERSUS GROUT/PE

Criteria Element	Score	VITRIFICATION Discussion	Score	GROUT/PE Discussion
<u>Regulatory Compliance</u> [3] ♦ Permitting # Air Quality	2/6	♦ Tech demo more extensive ♦ Lifetime Contin Monitoring ♦ Active delisting effort nationally	5/15	♦ No offgas problem
# Product form	4/12		3/9	♦ Meets LDR; less potential for delisting
<u>Environment, Health & Safety</u> ♦ Public Health #Emissions[5]	4/20	♦ High energy, potentially greater accident consequences ♦ Offgas & solids handling systems more complex (D&D)	5/25	♦ Low energy process; PE storage low risk explosion hazard ♦ D&D not as complex
♦ Non-operational worker safety [4]	3/12		4/16	
♦ Operation worker safety [5]	3/15	♦ VIT & Grout/PE = same process worker staff size.	3/15	♦ Same, neither has unusual work activities
♦ Transfer Risk [2]	5/10	♦ Not an issue at Hanford	5/10	♦ Same

[n] = weighting factor
n/n = score/weighted score

TABLE 3

Criteria Element	Score	VITRIFICATION Discussion	Score	GROUT/PE Discussion
<u>Treatment Effectiveness</u>				
♦ Volume Reduct'n [3]	4/12	♦ Volume reduces by 30%	2/6	♦ Volume increase of 150%
♦ Sec'y Waste Generation[3]	4/12	♦ Cu; Hg; Nox; S= attit'l treatment	5/15	♦ No secondary wastes, side streams recycled
♦ Destruct'n-Immobilizat'n Efficiency[3]	5/15	♦ Organics oxidized, salts decomposed	3/9	♦ Immobilization only of salts and organics
♦ Flexibility [4]	4/16	♦ Less flex for debris, non-glass formers	3/12	♦ Less flex for particulate content variation
♦ Final Waste Form [3]	4/12	♦ PA does not take credit for final waste form; VIT creates residuals requiring further treatment, e.g.Hg	4/12	♦ No residuals; narrower range of treatability groups
♦ Ability to be Shipped[2]	5/10	♦ Not a Hanford issue	5/10	♦ Same
<u>Implementability</u> [4]				
♦ System [4]	4/16	♦ Butte and Swiss have operating facilities.	4.5/18	♦ Grout=5 (BNFL + Commercial Ops)
♦ Availability [4]	3/12	♦ More complex process, high temp, more unit operations, unique torch changeout	4/16	♦ PE=4 (RF Prototype, Brookhaven)
♦ Scalability [4]	5/20	♦ Fully scalable to meet expected range of thruput	5/20	♦ Robust and relatively simple
♦ Schedule of Implement'n [4]	1/4	♦ EIS + Potential permitting probs	3/12	♦ Same
		♦ Design/Constr not at issue.		♦ Can meet Sched Reqts, but not room for slippage
				♦ Design/Constr not at issue

[n] = weighting factor
n/n = score/weighted score

TABLE 3

Criteria Element	Score	VITRIFICATION Discussion	Score	GROUT/PE Discussion
<u>Stakeholder Equity Concerns</u> [3] ♦ Regulators ♦ Public Acceptance	4/12 4/12	♦ Not aware of blocks to regulatory app'l ♦ Glass perceived as stable & benign	4/12 3/9	♦ Same ♦ Concrete known to crumble
<u>Lifecycle Costs</u> [4]	3/12	♦ Life cycle costs are within the 10% guideline ♦ Present worth also with the 10% guideline (at 3% interest)	3/12	♦ Same ♦ Same
<u>Develop't</u> [2] ♦ Marketing of Technology ♦ Private Sector Involvement	1/2 4/8	♦ Tech transfer issues of minor impact; the mkt is within DOE complex ♦ RETECH performing development at Butte	1/2 4/8	♦ Process used primarily commercial grade equipment ♦ BNFL providing grout sample testing; PE work at Brookhaven

[n] = weighting factor
n/n = score/weighted score

TABLE 4
SUMMARY SCORES
EVALUATION OF
VITRIFICATION VERSUS GROUT/PE

Criteria Element	Vitrification	Grout/PE
Regulatory Compliance	9	12
Environment, Health and Safety	14.3	16.5
Treatment Effectiveness	12.8	10.6
Implementability	13	16.5
Stakeholder Concerns	12	10.5
Lifecycle Costs	12	12
Development	5	5
Grand Total Scores	78	83

4.0 References

1. Comparison of a Vitrification Process against the baseline Grout/PE Processes in the Waste Receiving and Processing Facility, Module 2A, WHC-SD-W100-ES-008, Rev 0, December 1993.
2. Memorandum, Patrice Bubar, Director, Federal Facility Compliance Task Force, Office of Waste Management Environmental Restoration and Waste Management, DOE, Treatment Selection Guides for Federal Facility Compliance Act Draft Site Treatment Plans, March 17, 1994.

APPENDIX A SELECTION GUIDE DEFINITIONS

Most of the selection guides can be applied to the treatment options under consideration by consideration of applicable sub-elements which contribute to the primary guide. For instance, an assessment of a treatment option's "treatment effectiveness" is evaluated by considering the following:

- The system's ability to reduce the volume of waste, or waste minimization
- The difficulty encountered in managing or treating any secondary waste that is generated during the treatment process
- The system's ability to remove, destroy, or demobilize any unwanted hazardous constituents
- The system's ability to treat a broad range of waste, or to minimize the amount of pretreatment required to make the waste meet the facility's acceptance criteria
- The ability to ship and dispose of treatment residuals or to minimize post treatment required to meet shipping and disposal requirements

The sub-elements have been identified to ensure that treatment effectiveness and other guides are evaluated in a comparable manner from one site to another. Some of the guides, such as regulatory compliance and life-cycle cost, are considered adequately self-contained and have no separate sub-elements identified. The definitions of the guides and their sub-elements are identified below.

Regulatory Compliance

This guide assesses the ease with which process-specific regulations (e.g., federal, state, and local) and commitments in compliance agreements or orders are satisfied. The regulatory requirements include state and local laws, EPA and Department of Transportation (DOT) laws, and other laws that specify requirements or milestones. Treatment systems under consideration should be developed to ensure that, at a minimum, the waste meets the LDR standards. (It is anticipated that options which do not meet regulatory requirements, either through standard application of regulatory requirements or established variance procedures, will not pass a basic viability screening as described in Section V of the FFCAct Task Force Report) This parameter gives high scores to treatment technologies or options that have been previously permitted and are relatively straightforward, and lower scores to technologies or options that require regulatory exemptions or demonstrations of equivalency that may pose additional permitting difficulties.

Environmental, Health, and Safety

The environmental, health, and safety guide gives high marks to processes providing little or no additional risk to the industry workers, the public, or the environment in general. This included all occupational safety and health issues, pollution issues, and legally driven issues.

Environment/Public Health and Safety: This sub-element assesses risk to all off-site populations due to routine operations and potential accidents at a facility with the proposed process. This assessment includes routine emissions (radiological and hazardous) from the facility under normal operating conditions, under less than ideal conditions (e.g., waste streams marginally characterized or overly aggressive production schedules), and all accident scenarios (both high probability/low consequence and low probability/high consequence).

Non-Operational Worker Health and Safety: This sub-element assesses occupational risks to all on-site workers due to activities exclusive of facility operations using the proposed process. Risks include those from construction of the facility, non-routine maintenance (e.g., substitution of technologies, equipment replacement, etc.), and decontamination/decommissioning of the facility.

Operational Worker Health and Safety: This sub-element assesses the radiological and hazardous risks to all on-site workers during operations at a facility with the proposed process, including both routine operations and accidents. Risks due to routine operations include radiological and hazardous exposure during drum handling, waste sorting, primary and/or secondary treatment, packaging of the treatment residuals, and routine equipment maintenance. Risks due to accidents include radiological and hazardous exposure resulting from equipment failure (with possible associated fires or explosions) or worker error.

Transportation Risk: This sub-element assesses the radiological and hazardous risks to workers and the public posed by off-site transportation of mixed waste. Risks include those from additional waste characterization required for transportation, handling of waste containers during certification and loading/unloading, fatalities and injuries due to traffic accidents, and chronic and acute effects of exposure to radiological and hazardous constituents of the waste during both routine operations and as the result of an accident.

Treatment Effectiveness

The treatment effectiveness guide assesses how well the proposed process performs technically and what the anticipated advantages are compared to alternatives.

Volume Reduction: This sub-element assesses the ability of the treatment technology or option to reduce volume of the original waste (i.e., waste minimization). Net volume of residuals divided by net input volume provides a way to measure this factor as compared to other alternatives under consideration. The determination of volume reduction should include volumes of secondary waste generated during the process.

Secondary Waste Generation: This sub-element assesses the difficulty of managing contaminated material generated during the treatment of primary waste. Secondary waste may have additional chemical or other characteristics providing new problems relating to treatment and disposal, including contaminated filters, contaminated protective equipment, swipes, used oil, and off gases. The difficulty of meeting any additional treatment requirements for treatment residuals would be accounted for by ranking the sub-element of destruction and removal efficiency. The relative value of this assessment should be determined according to the level of difficulty associated with managing the secondary waste.

Destruction, Removal, and/or Demobilization Efficiency: This sub-element assesses the ability of the treatment option to destroy or remove unwanted contaminants from the waste stream or to reduce the potential hazard by isolating or rendering the hazardous constituents immobilized.

Flexibility: This sub-element assesses the system's ability to process a range of inputs with minimal effect on system operations. This includes accommodating the expected waste stream changes and daily variations as well as unanticipated spikes in the waste stream rate and composition. A treatment system that can accept a broad range of treatability groups would be given a high flexibility rating.

Final Waste Form Performance: The treatment systems posed as options for evaluation should, at a minimum, be able to meet the LDR treatment standards. This sub-element assesses the long-term stability of the treatment residuals, or the difficulty encountered in meeting post-treatment acceptance criteria required to comply with disposal requirements. Although disposal WACs have not been developed, the evaluation of this sub-element should represent a first order approximation of the closeness of the treatment residuals to the anticipated disposal requirements. This evaluation may need to include consideration of factors such as:

- Compressive strength
- Biological stability
- Radiation stability
- Resistance to thermal cycling
- TCLP analysis results
- Radionuclide leachability
- Solubility

Ability to be Shipped: This sub-element assesses the amount of additional treatment required to make the treatment residuals meet shipping requirements.

Implementability

The implementability guide assesses the ease and likelihood of bringing a treatment facility or technology into operation within the proposed schedule and estimated cost. This guide should be used to assess the availability of capacity at existing facilities to meet specific treatment requirements. The implementability guide gives high scores to technologies that can be designed, built, demonstrated, and put into production within specified schedules while exhibiting high levels of maturity, development, and availability.

System Implementability: This sub-element assesses the ability to build, construct, or implement the treatment option on the site. The demonstrability of the system is assessed by the ratio of the number of process sub-elements previously demonstrated and validated in both actual and similar environments to the total number of sub-elements in the treatment system. The technical analysis of alternatives should not be based on the presumed performance of untested methods. An estimate of the probability of failure, in either qualitative or quantitative terms, should be made for each component technology and for the complete alternative process. Consideration of this sub-element should give preference to technologies proven effective under conditions similar to those anticipated.

Availability: This sub-element assesses the fraction of time the system is available, considering labor and materials as well as the frequency and complexity of necessary maintenance. Availability is decreased by technologies requiring frequent or complex operation and maintenance activities as opposed to technologies requiring straightforward operation and less maintenance.

Scalability: This sub-element assesses the ability to transfer the technology from bench scale or demonstration testing to full scale operation or vice versa. It also addresses the ease with which a treatment system or technology can be scaled up to a larger capacity or down to a smaller capacity.

Waste Management Schedule: This sub-element assesses the time required to process the waste, including special studies, design, demonstrations, construction, permitting, and any other steps that may be required to complete waste treatment. This sub-element is also affected by facility capacity limitations; for instance, when a waste stream may not be able to be treated for a lengthy period of time.

Stakeholder Concerns

The stakeholder concerns guide assesses the ability of the treatment option to satisfy concerns of the stakeholders. Recognition of stakeholders' concerns is important to the progress of DOE's waste management program and successful achievement of milestones. Stakeholders may include the local public, public near the intermediate and final destinations of the waste, state and local governments, Native Americans, Congress, and industry.

Equity Concerns: This sub-element assesses the likelihood that equity concerns on the part of the sites' regulators will affect the plans for the facility.

Public Acceptance: This sub-element assesses the acceptability of the plan and schedules by stakeholders, as well as the adequacy of stakeholder involvement. A potential for political controversy may affect public acceptance and the public's perceptions of a process could affect its use, as could tribal rights and future land uses associated with technology demonstration, deployment, and socioeconomic interests.

Life-Cycle Cost

Life-cycle cost includes the total of the direct, indirect, recurring, nonrecurring and other related costs incurred or estimated to be incurred in the design, development, production, operation, maintenance, support, and final disposition of a major system over its anticipated useful life span. Where system or project planning anticipates use of existing sites or facilities, restoration and refurbishment costs should be included.

Factors included in the life-cycle cost estimate are detailed in guidance (Draft Site Treatment Plan Cost Information Guidance, Revision 0, March 1994) currently being developed by DOE Headquarters. Capital and operating cost estimates should be developed using the Waste Management Facilities Cost Information Report (EGG-WTD-10443, Oct. 92). unless better system-specific or site-specific information is available. To ensure that the life-cycle costs from one facility to another are comparable, a facility should include all of the treatment systems necessary to meet LDR treatment standards for the primary waste, treatment residuals, and all secondary waste generated during the treatment process(es). The cost estimates must be developed in consideration of the particular radionuclides present by incorporating the containment, accountability, and special handling requirements posed.

Technology Development

The technology development guide encompasses privatization concerns to be considered when evaluating technology development options. This guide assesses the value of a technology development activity or program to the commercial sector.

Market for Technology: This sub-element assesses the market inside and outside of the DOE complex for the option under consideration. This assessment includes determination of whether the development would be beneficial to others or whether there is a potential for commercialization of the technology or facility.

Private Sector Involvement: This sub-element assesses the potential for private sector involvement in the development and marketing of the proposed process in a teaming arrangement with DOE. The desire of a private company to develop or assist in the development of a process increases the desirability for the development of that process. Technologies and facilities may be developed and privatized by DOE to be operated by the private sector.