**Cover Sheet for a Hanford
Historical Document
Released for Public Availability**

Released 1994

**Prepared for the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830**

**Pacific Northwest Laboratory
Operated for the U.S. Department of Energy
by Battelle Memorial Institute**

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, make any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

DECLASSIFIED

HDC-2534

EDC-2534

RECORD CENTER FILE

Richland, Washington
March 14, 1952

Classification Cancelled and Changed To

DECLASSIFIED

By Authority of D. S. LewisCG-NMP-1 6-27-94By J. E. Savely 7-1-94Verified By Jessie Mally7-27-94

-1-

Copy #1 - J. M. Fox, Jr.
 #2 - W. A. Blanton
 #3 - R. J. O'Neil
 #4 - J. M. Frame
 #5 - V. W. Wood
 #6 - Yellow File
 #7 - Pink File
 #8 - 760 File

15
6

J. M. Fox, Jr.
 Design Planning Unit
 761 BUILDING, 700 AREA

300 AREA "X" PROGRAM, BASIS "B"

Page 15 is unclassified.

Attached is a secret draft of 300 Area expansion for the proposed "X" Program (600 MMD level for indefinite period) made up of the following:

- a. Assumptions
- ⊙ b. Present Facilities and to What Extent Inadequate
- ⊙ c. Description of Proposed Work
- d. Advantages to Be Gained and Justification for Proposed Work
- e. Why Existing or Alternate Facilities Cannot Be Used
- ⊙ f. Estimate of Cost
- g. Attachments
 1. Production Equipment Requirements - 600 MMD
 2. Instrument and Machinery List
 3. Production Schedule
 4. 8½" x 11" area plot plan photostat

RECEIVED

JUL 1952

⊙ 300 AREA
 CLASSIFIED FILES

Design and construction bar charts for the major items are being made up and will be submitted under separate cover later with the estimate.

- ⊙ Expansion of the Metal Preparation facilities must be undertaken as soon as the "X" Program is approved. This is true whether Basis "A" or Basis "B" of "X" Program is used, the only major differences being the extent of expansion to 313 Building and the size of the 303 change house. This is the equivalent of 33 months lead time on the completion of "X" Program date.

To differentiate the major items needed in the 300 Area whether the "X" Program is executed or not, we are giving the following explanation: To satisfy the present needs of the 300 Area the added change house, administration building, railroad spur, parking lot and stores warehouse should be accomplished, the priority being in the order given with the change house having the highest and the stores warehouse the least. It should be

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

GA

MASTER
DECLASSIFIED

-2-

J. M. Fox, Jr.

March 14, 1952

understood that the size of the change house might be reduced if there were no sizable expansion plans for the 300 Area in the foreseeable future.

It should be further pointed out that considerable process engineering is needed in the 300 Area to arrive at the most satisfactory equipment arrangement for the efficient streamlined flow of materials should the 313 Building addition be built.

The location shown on the photostat of the area for the acid and caustic unloading station, the new stores warehouse, administration building and parking lot is tentative. It is possible that an engineering study might disclose that a more economical arrangement could be had if the new technical center badge house were used as access to the 300 Area and the west gate house closed.

This write-up was prepared through joint effort of the Project Engineering Unit and the Process Engineering Unit, with the cooperation of the Plant Engineering Services Unit of the Metal Preparation Section, Manufacturing Department.

PROCESS ENGINEERING UNIT

VW Wood:jvw

Attachment

DECLASSIFIED

-3-

③ 300 AREA "X" PROGRAM, BASIS "B"

For the purposes of a 300 Area expansion to accommodate the 600 MSD "X" Program as outlined March 10, 1952, the following assumptions are made:

1. The triple dip canning process will be used. ③
2. New metal will be available in the quantities required. 100% of the slugs required for process will be received from off-site in the bare machined surface condition by January 1, 1953, but deliveries will start July 1, 1953 to meet forecast schedules. ③
3. Two months (production) bare finished slugs, one-half month slugs in process and one month finished canned slugs will be required for satisfactory operating inventories at the 300 Area. ③
4. The 305 Building will have sufficient capacity for graphite and other testing. ③
5. The quantity of enriched alloy slug canning will remain approximately the same as the present schedule with all alloying being accomplished off-site and will continue to be dry canned at 300 Area. ③
6. A production yield of 75% of acceptable finished canned slugs. See Document HW-23255.
7. The 300 Area will operate continuously on three shifts a day, seven days a week. ③
8. The 100 Areas will have reached an equilibrium demand of 270 tons of canned slugs per month beginning approximately six months after start-up of the "Y" unit. ③
9. The 100 Areas will be able to satisfactorily store initial charges of approximately 970 tons of canned slugs for "X" and "Y" piles. ③
10. North Richland will maintain a minimum of 85 pounds per square inch pressure on the existing 300 Area export lines and with the line proposed under another project will be considered an adequate source of water supply for the 300 Area.
11. An 80% - 20% ratio of eight-inch to four-inch slugs will be considered as normal production. ③
12. The existing rod straightening, extrusion press, slug machining, chip recovery, melt plant and oxide roasting facilities will remain undisturbed.
13. The 314 Building will not be available for storage of machined slugs.
14. The design and construction of a 303 Area change house and a combination 300 Area administration building will be expedited and completed

DECLASSIFIED

by July 1, 1953. Added change house facilities for 100 more men must be available by April 1, 1953 in order to meet 1953 commitments for 300 Area under the "X" Program.

15. The present 303 Buildings will have storage capacity for only 150 tons of slugs under manufacturing arrangements which are necessary for the "X" Program production.
16. The Metal Preparation Plant will not provide operating personnel to the Reactor plants for Program "X".

I. Present Facilities and to What Extent Inadequate

Present production in the 300 Area is approximately 140 tons per month on a two-shift, six-day week basis. The swing shift is essentially only a partial shift. However, because of process time cycle, high maintenance of furnaces, equipment out of regular production for special materials coming (necessary to avoid contamination) and space limitations (including production line offices and change house facilities), production can not be stepped up in direct proportion to the extension of operating time and added production personnel without additional equipment and space. The estimated maximum production to be obtained from existing facilities and proposed production equipment shown on the attached list is 280 tons per month on a three-shift, seven-day week basis.

Sufficient, suitable space is not available in the 300 Area for storage of bare slugs, essential materials and miscellaneous materials for the 600 MWD level. Only 3810 square feet of existing storage space including 2650 square feet of essential materials storage will be available for this 600 MWD "X" Program. A total of 9000 square feet of additional storage space will be required. The existing 313 Building is not adequate to accommodate the additional production facilities and a 7,000 square foot addition to the building will be required. This plus the 9,000 square feet additional storage makes a total addition required for 313 Building of 16,000 square feet. Existing building ventilation facilities are inadequate for even the present loads, and a substantial addition is necessary to supplement existing facilities and the addition.

The present facilities for receiving raw material for the 300 Area are improvised, hazardous and inadequate. The necessity for adequate round-the-clock material handling facilities will be materially accentuated by the doubling of present production.

During the past few years there has been a real need for adequate 303 Area change house accommodations for the operating personnel. The existing facility is the limiting factor in increasing present production in this area. The existing change house has suitable accommodations for approximately 150 operating personnel. However, 190 have been crowded into the present facilities resulting in lowering morale and potential labor grievances. Suitable new change house space is needed for handling 375 people. At the present time the power and maintenance forces in the 300 Area have no change house or lunch room facilities and are required to change clothes and eat their lunches in makeshift areas which leave much to be desired. The existing change house

~~SECRET~~

DECLASSIFIED

-5-

facilities will be diverted to the use of these people. The present change house is not properly located or adequate for either contamination control or for accommodating production personnel. The 300 Area has no air raid shelter. Because of the 303 Area operating limitations, it would be farsighted and highly desirable to incorporate an air raid shelter in the 303 Area change house. It would facilitate making maximum use of the limited space available at the strategic location for a shelter.

There has been an urgent need for a railroad spur in the 300 Area for efficient handling of railroad freight in the area. The increased volume of traffic required under the 600 MWD "X" Program, plus the need for acid and caustic tank car unloading spot, dictates the need for the spur at this time. Associated with this facility is the need for a truck and rail (loading - unloading) dock and ramp. The existing truck ramp is recessed in the ground, in the proposed location for the new change house, and is not in the proper location for maximum use. Because of the increased shipping traffic necessitated by the "X" Program the present truck loading facilities become highly undesirable.

The existing 300 Area parking lot on the east side of the main highway is divided into two areas, neither of which is of acceptable standard or conducive to efficient, safe channeling of pedestrian and motor vehicle traffic. It has been progressively enlarged from time to time to meet the urgent needs of increased personnel. The present facility because of limited space creates congestion which hampers security operations at the 300 Area main entrance gate, delays traffic and leads to inefficient and hazardous operation of traffic flow in and out of the area. In addition, it has been observed recently that each day more than 100 employee cars have been parked on the west side of the main thoroughfare in front of 300 Area. This necessitates pedestrian traffic for the drivers and riders across four-lane traffic during rush hours going both to and from work. At shift change, passengers enter the main highway from both sides, pedestrians cross the highway, traffic from the highway enters 300 Area main entrance, other traffic leaves the area through the main gate, shift buses arrive and leave twice during the change and the shuttle bus arrives and departs--all of which does not contribute to safe and adequate channeling of vehicle traffic. True, although a sizable portion of the present parking area customers will shift to the Technical Center parking lot and entrance gate in the near future, an improved parking lot is necessary for the balance of the employees who will continue to work in the metal preparation plant.

Expansion of technical laboratories in the 300 Area during 1946 and the continued expansion in the 300 Area during the last five years have brought about maximum utilization of office space in permanent type buildings. In addition, a sizable number of administrative personnel have been forced to set up offices in eleven temporary Quonset type huts that had been received in a used, knocked down condition in the 300 Area at the time the need arose. Some of these huts were erected hurriedly on an urgent basis as early as 1946 with a designed life of two years. Now these huts have been in service more than five years and have begun to show excessive weathering, structural weakness and dry rot conditions in the sub-structures. The hutments were pressed into service until suitable permanent type quarters could be provided. At present they require exorbitant maintenance, can not be maintained at a comfortable temperature, do not conform to the minimum requirements of the Uniform Building Code (Pacific

Coast Building) and do not contribute to maximum operating efficiency of administrative personnel as compared to results to be obtained in a well planned, centralized permanent type administrative building. The consolidation of first aid, patrol headquarters, badge house, fire, safety, manufacturing and administrative offices and rest room facilities under a common roof has been highly desirable for a considerable period of time. No space exists in the present huts to house additional administrative personnel required for the "X" Program. The following is a tabulated list of the present hutment facilities being used, number of occupants, floor space and type of work performed:

Buildings or Offices Being Replaced	No. of Occupants		Floor Space	Type of Work
	Male	Female		
3704-B	3	2	600 Sq.'	Administrative and supporting clerical personnel for the Operations and Process Units.
3704-C			600 Sq.'	General conference room, serving approximately 450 employees in the Metal Preparation Section.
3704-D			600 Sq.'	Ladies [®] and men's restrooms for administrative employees. [®]
3704-E	4	3	600 Sq.'	S.F. Accountability.
3704-F	2	1	600 Sq.'	General administrative and supporting clerical personnel for the Metal Preparation Section.
3704-G [®]	5	2	600 Sq.'	Fire and Safety Engineers and Administrative personnel for the Operations and Process Units.
TS-153	2	1	450 Sq.'	S.F. Accountability
3713 (½ Office)	0	1	72 Sq.'	Administrative clerical personnel [®] for the Power and Maintenance Unit
3717 (1½ Offices)	1	2	252 Sq.'	Administrative and supporting clerical personnel for the Power and Maintenance Unit.
3717-B (2 Offices)	2	2	265 Sq.'	Administrative and supporting clerical personnel for the Plant Engineering Services Unit.
3717-B (1 Office)	1	2	132 Sq.'	General administrative and supporting clerical personnel for the Metal Preparation Section.

No air raid shelters exist in the 300 Area and it is considered logical and good planning to incorporate an air raid shelter in the proposed administrative building. This shelter would be of sufficient capacity to house the area personnel not accommodated by the proposed 303 Area change house.

-7-

The needed 10,000 square feet of space for stores warehouse to service the Metal Preparation Plant and other facilities in the 300 Area does not exist.

There is no reserve transformer capacity in the 352 "A" Substation. The existing 3750 KVA transformer will be loaded to 4275 KVA upon completion of the Hanford Laboratory. This is the maximum permissible loading even with forced air cooling. Therefore, it is mandatory to add the new transformer to supply the service required for the expansion program.

II. Description of Proposed Work

A full scale engineering, design and construction program is proposed to cover the following work:

1. Construct a 16,000 square foot addition to the east side of the existing 313 Building to accommodate the increased production and storage facilities. The building is to be of similar construction to the existing building but with a higher ceiling. This addition will be furnished with lights; heavy floors; large service doors; heating; ventilation; office space; toilets; smoke room; air, water and steam services; and sanitary and process sewers including tie-ins. Site preparation, re-location of electrical lines, re-location of existing obstructions, site drainage, grading, ramps, roads, truck and rail loading and unloading docks are to be included. Associated with the building addition and included as part of the work is the rearrangement of existing equipment in the 313 Building as required for complete integration of the new facilities with the present. The 20 autoclaves in 314 Building are to be moved to the new addition and properly arranged with the eight new autoclaves. As part of this expansion item the following will be included: design, layout, procurement and installation of equipment as shown on attached lists ("Instrument and Machinery List" and "Production Equipment Requirements - 600 MWD"). See attached photostat of 300 Area for approximate building addition location.
2. Provide railroad spur track or siding plus acid and caustic tank car unloading facilities (including pumps) and storage tanks. Spur to be so arranged to permit unloading of process materials on the existing track while coal cars are being shuttled in and out of the power house unloading station.
3. A 303 Area change house for three hundred seventy-five, a maximum of one hundred thirty persons per shift, 303 Area operating personnel (on the basis of 80% men and 20% women) with air raid shelter. This item will include heating, ventilation, lighting, lunch room, lockers, showers, toilets, rest rooms and the necessary changes to the exclusion area fence, roads, walkways, surface drainage at building site, patrol stations, access walkways, surface drainage at building site, patrol stations, access gates and overhead lines as are necessary for maximum utilization of manpower and the proposed facilities. See attached photostat of the 300 Area for location of change house. Included with this facility is the added septic tank capacity for 300 Area sanitary utilities required for the additional personnel necessitated by the "X" Program.
4. Build a 300 square foot addition to Building 382 for installation of one electric driven 1500 GPM pump. Procurement and installation of this pump

are included as part of the work to be accomplished under this project proposal.

5. Construct 300 Area asphalt surfaced parking facilities for Manufacturing[®] and supporting personnel. ©
6. Erect a 300 Area combination administration, first aid, patrol headquarters, badge house, fire, safety, H.I. service building and air raid shelter with a total square footage of approximately 14,000 square feet. The building will have fluorescent lighting, movable interior panel partitions, steel window sash, standard steam heating (with steam supplied from central power house), evaporative cooling, standard type ventilation system and rest rooms. The building will have fire detection system connected to the 300 Area fire detection loop, adequate rest room facilities which meet minimum requirements of the Uniform Building Code and Washington state laws. See attached photostat for approximate location of administration building.
7. Provide 10,000 square feet permanent type truck height stores warehouse of fire resistant materials with fire detector system, lights, truck loading and unloading dock, shelving, one office, toilet-lavatory, limited heating and ventilation. See attached photostat for tentative location of warehouse.
8. Upon completion of the permanent type office building, dismantle Quonset huts 3704-B, 3704-C, 3704-D, 3704-E, 3704-F and T-153 and dispose through excess. The site is to be left adequately cleared with a neat, smooth rolled surface over the entire hut area. ©
9. Add 3750 KVA transformer to 352 "A" substation. ©
10. Provide added transformer bank for combination administration building, transformer bank for 303 change house building, and transformer bank at stores warehouse.
11. Added outside telephone service to cover the necessitated expansion by "X" Program.

III. Advantages to Be Gained and Justification for Proposed Work

The established operating storage capacities in the stated assumption for this proposal are very real but would be too low in case of an extended railroad strike or an adversity which would interrupt the flow of materials much beyond thirty days. This added storage will provide reasonable storage for raw materials, essential materials and miscellaneous materials (pallets, containers, etc.) which are needed to maintain continuity of operations in the metal preparation plant with the 600 MWD "X" Program.

The present facilities in the 313 Building are not adequate to meet the equilibrium demand, 270 tons per month, of acceptable finished canned slugs. The proposed 313 expansion will provide a plant with adequate production capacity to maintain the equilibrium level as defined in the assumptions. The shifting of existing autoclaves will have to be strategically scheduled, but when accomplished it will eliminate excessive extra handling of production materials which is now required to transfer the slugs from the 313 Building to 314. ©

DECLASSIFIED

~~SECRET~~

HDC #2534

-9-

building to inspection building and then to storage. It will permit the use of more efficient mechanical handling equipment to service the old and the new autoclaves. The added office space will provide reasonable facilities for the added operating supervisory personnel and service supervision required by the proposed "X" Program and will alleviate the deficiency which now exists under present operating levels.

The proposed mechanization of the canning assembly furnace is designed to take advantage of the mechanical development study now under way on this phase of operation at the General Electric Engineering Laboratories at Schenectady and Hanford Works. It is expected that this will improve the uniformity of canned slug quality and result in a small reduction of operating personnel.

The interference caused while unloading raw material from railroad cars during the switching of coal cars to the 384 Building will be materially reduced by the addition of the spur track. This added facility will reduce the potentials for paying demurrage on railroad cars not unloaded in the required time, and a suitable rail spot will be available for unloading caustic and acid tank cars. This facility does not now exist in the area. Installing of acid and caustic tank car unloading and storage facilities in the area to meet the increased demands for caustic and acid will eliminate the present undesirable method and permit taking advantage of the low cost bulk handling features of the proposed facilities.

The proposed power and maintenance shop equipment will permit reasonable servicing of the production lines operating on the three-shift, seven-day week basis, and will permit expansion of the centralized electronic shop for servicing the entire Hanford Works.

The construction of a new 303 Area change house will permit the full utilization of more manpower for training and metal preparation purposes. The Power and Maintenance forces will be provided with rest room--lunch room facilities which they do not now have, and the existing overcrowded operation change house condition will be relieved. The contamination control problem will be eased and the morale of the 303 Area personnel will be enhanced.

The proposed new 300 Area parking lot will reduce security and traffic hazards in front of the main entrance gate.

Administration of the Metal Preparation Plant (300 Area) until the latter part of 1951 was carried on largely from the 700 Area Administration Building. With reorganization of the Manufacturing Department, the 300 Area management and staff personnel are now located in the Metal Preparation Area, and personnel are temporarily occupying makeshift office space in widely separated buildings throughout the area, which has resulted in overcrowded conditions in many buildings.

The activities of the Metal Preparation Plant are numerous and varied. To give proper consideration to the special problems relative to these activities, it is desirable to have responsible administrative and engineering personnel at a central location near the work site.

The construction of the proposed office building will provide adequate centralized

~~SECRET~~

DECLASSIFIED

facilities for administrative, accountability, staff, engineering, clerical, fire, safety, first aid and patrol personnel. It will alleviate over-crowded conditions, improve working conditions and provide facilities comparable to other plant areas. Consolidation of offices to the one building on the plant location will improve office efficiency and permit groups with closely related functions to be housed under one roof. It will reduce duplication of office records, facilitate coordination of efforts between groups and improve employee morale.

- The erection of the stores warehouse will reduce handling of stores stock items, improve stores service to the Metal Preparation Plant and Technical Center, supplement the central warehouse space, reduce the traffic between the area and the main central stores, and provide an area stores comparable to those in the other areas.

The resulting removal of the hutments will eliminate continued application of maintenance funds to structures of disproportionately low dollar value and will retire these structures from service since they have passed their economical service life.

IV. Why Existing or Alternate Facilities Cannot Be Used

There are no other existing or alternate facilities available in the 300 Area at the present time or in the immediate future.

V. Estimate of Cost

The estimate was arrived at by the representatives of the estimating group meeting with the engineers working up this report and going over the items listed to be done in the 300 Area for the "X" Program. The estimators took this information and reviewed it for approximately two days before submitting their estimate. In addition, the outside electrical work including the transformer for the sub-station was estimated by discussions between the engineers preparing this proposal and the Electrical Design Group (outside distribution electrical), Design Section.

PRODUCTION EQUIPMENT REQUIREMENTS - 600 MSP

1. Recovery Furnaces	85,000
2. Replace furnaces.	30,000
3. Rearrangement of Furnaces and Auxiliary Equipment	40,000
4. Bronze Bath Agitators and Lockout Equipment	1,000
5. Metal Drying Facilities	7,500
6. Miscellaneous Canning Equipment	15,000
7. 2 Fluoroscopes	10,000
8. Facing Lathes	30,000
9. Welders, Auxiliary Equipment and Space	7,000
10. Increase Pickle Dryer Capacity	5,000
11. Degreaser for Pickle Line	3,000
12. Hoists (larger capacity)	3,000
13. Increase capacity or replace component parts preparation facilities.	20,000
14. Methanol Still - Budget Item B-1970	6,000
15. Replace press.	7,500
16. Increase capacity of air bath and frost test facilities.	33,000
17. 8 Additional Autoclaves	45,000
18. Slug Boxes and Pallets for Shipping and Storage	30,000
19. Design and Construction of Improved Canning and Finishing Facilities	750,000

Acid Station

20. 1 - 12,000 gallon stainless steel storage tank complete with footings, valves and piping for storage of tank car lots of nitric acid.
21. 1 - 12,000 gallon storage tank complete with footings, valves, steam coils, and supporting piping for storage of tank car lots of caustic.
22. 1 Nitric acid pump, 200 GPM, with electric motor drive, controls, etc.
23. 1 Caustic pump, 200 GPM, with electric motor drive, controls, etc.

Water Works

24. 1 - 1500 GPM pump with 40 HP electric drive and controls.

DECLASSIFIED

-12-

INSTRUMENT AND MACHINERY LISTQuantityDescription

2	300 ampere electric driven welding machines
2	10" x 48" South Bend lathes
6	10" x 36" Monarch tool room lathes
1	16" x 10'0" engine lathe, 6" hollow spindle
3	Universal milling machine
1	Gorton engraver and tool grinder
1	Universal shaper, 20" Cincinnati
1	Hellogg welder, model #201
1	Spot welder, 50 ampere sheet metal
2	1/2 HP pedestal grinders, 8" & 3/4"
1	2 - 1/2 HP pedestal grinders, 12" x 2"
1	Bench grinder
2	Bench drill presses
1	Oakley or Cincinnati Universal tool grinder
1	Vacuum pump and tube filling manifold
-	Electrical test equipment
6	Instrument equipment
-	Oscilloscope

DECLASSIFIED

~~SECRET~~

PRODUCTION SCHEDULE

Metal Preparation Section
600 MWD Forecast

	Reactor Requirements Tons/M	Production Tons/M	Month End Inventory Tons	Personnel	
				Technical	All Others
<u>1952</u>					
Jan.	100			30	378
Feb.	100				
Mar.	100				
Apr. (C)	100	145	324	82	410
May (C)	350	145	119		
June	100	145	164		
July	100	145	209	56	425
Aug.	100	145	254		
Sept.	100	145	299		
Oct.	100	145	344	92	438
Nov.	100	145	389		
Dec.	100	145	434		
<u>1953</u>					
Jan.	100	145	479	92	449
Feb.	116	145	524		
Mar.	150	145	553		
Apr. (C)	158	145	543	93	465
May (C)	160	145	535		
June	160	145	520		
July	160	181	541	96	517
Aug.	160	181	562		
Sept.	160	181	583		
Oct.	160	181	604	96	507
Nov. (C)	160	181	625		
Dec. (C)	160	181	646		
<u>1954</u>					
Jan.	160	217	703	96	484
Feb.	160	217	760		
Mar.	160	217	817		
Apr.	160	217	874	96	484
May	160	217	931		
June	160	217	988		
July	160	217	1045	96	484
Aug.	160	217	1102		
Sept.	160	217	1159		
Oct.	160	217	1216	96	484
Nov. (C)	169	217	1273		
Dec. (C)	169	217	1330		

DECLASSIFIED

~~SECRET~~

HDC-253A

-2-

	Reactor Requirements Tons/M	Production Tons/M	Month End Inventory Tons	Personnel	
				Technical	All Others
1955					
Jan.	164	217	396	100	517
Feb.	233	217	380		
Mar.	259	217	338		
Apr.	264	253	327	105	550
May	202	253	378		
June	221	253	410		
July	221	253	442	106	561
Aug.	286	253	409		
Sept.	310	253	352		
Oct.	315	270	307	106	573
Nov.	270	270	307		
Dec.	270	270	307		
1956					
Jan.	270	270	307	106	573

~~SECRET~~

DECLASSIFIED

DECLASSIFIED

EMC-2534