February 1992

DOE/CE/27504--7-Pt.2

DE93 005613

HYDRAULIC WASTE ENERGY RECOVERY

A Technical Report

Energy Task Force
of the Urban Consortium

CITY OF DETROIT
Coleman A. Young, Mayor

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Conducted by:

Creighton C. Lederer, P.E.

Albert H. Thomas

Joseph L. McGuire, P.E.

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

PREFACE

1991 URBAN CONSORTIUM ENERGY TASK FORCE RESEARCH

THE URBAN CONSORTIUM (UC) is a special network of the Nation's largest cities and urban counties brought together by PTI to find new solutions to their common concerns. The UC provides a creative forum where elected and appointed officials can identify, test, and validate practical ways to improve the provision of public services while generating new revenue opportunities. With staff, management, and business services provided by PTI, the UC addresses the critical needs of large local governments through its three task forces: Energy, Environment, and Telecommunications and Information.

The Urban Consortium Energy Task (UCETF) has 20 members and was established to improve urban energy management and decision-making through applied research and technology transfer. The UCETF focuses on developing and sharing new approaches and innovative solutions to energy management problems with local governments. Projects are organized in thematic units and co-managed by a member of the Task Force.

A description of the 1991 program Units and projects are:

ALTERNATIVE VEHICLE FUELS AND TECHNOLOGIES (AVF)

Alternative vehicle fuels offer a very strong potential to aid in the reduction of U.S. dependence on foreign oil supplies, with the resulting benefits of decreased air pollution in urban areas. Local governments can play an instrumental role in realizing this potential through practical applied research and highly visible demonstrations of alternative fuels and technologies. Issues addressed this year include identifying (a) intensive and credible market development efforts based on an applied research and demonstration program that combines reliable technology with experience-tested applications, (b) environmental and energy diversity benefits, and (c) institutional and infrastructure barriers. The 1991 AVF unit consists of:

Broward County, FL -- *Dual-Fuel Conversion Demonstration and Technology Transfer Project*

New York City, NY -- *Alternative Fuel Vehicle: Financing Issues*

Denver, CO -- *Technical and Market Comparison Between H₂/CNG (Hythane), Electric Hybrid, and CNG Fueled Vehicles*

Denver, CO -- *An Alternative Fuels Fleet Evaluation System -- A Transfer Project*

Detroit, MI -- *Analysis of Institutional and International Limitations for Alternative Fuel Vehicles*

Washington, DC -- *Comparison of Energy Consumption, Energy Savings, and Environmental Effects of EV/PV vs. Conventional Gasoline Vehicle*

ELECTRICITY MANAGEMENT

Urban interests for electricity management focus on means to maintain stable, secure and reasonably priced supplies of electric energy. Approaches include procedures for better demand management, application of "least cost" planning concepts, appropriate use of decentralized and/or small power production facilities, improved end-use efficiency, and developing sound structures for cooperative action among municipalities and energy utilities. Urban strategies include support for decentralized "small" power production, along with better demand management and improved end-use energy efficiency. The successful development and implementation of such strategies will require close cooperation with the utility industry and will address topics in areas of institutional relations, source flexibility, and demand-side management. The 1991 Electricity Management Unit consists of:

Albuquerque, NM -- *Alternatives to Traditional Rate Setting*

Chicago, IL -- *Integrating Innovative Supply and Efficiency Techniques*

Chicago, IL -- *The Chicago Energy Management Cooperative*

Dade County, FL -- *Energy Cost Reduction Through Resource Recovery*

Detroit, MI -- Hydraulic Waste Energy Recovery (Phase II) City of Detroit Water Distribution System

San Jose, CA -- Utility/Local Government Partnership to Increase Energy Conservation in New Construction

ENERGY EFFICIENT FACILITIES

Activities involving energy efficient facilities are at present, part of a national effort to achieve maximum cost-effective energy productivity in the building sector. There exists a need for collaboration between local government officials responsible for energy and environmental programs and other local government officials responsible for facilities, as well as the Federal officials and private sector groups, e.g. utilities. New technologies and management/administration practices to advance energy efficiency in facilities require major partnership efforts and transfer programs. Multi-family housing that has a large concentration of low-income families presents a unique challenge to lowering energy costs and maintaining energy efficient facilities. Projects in this unit are:

Boston, MA -- Neighborhood Energy Efficiency Outreach Partnership

Columbus, OH -- Energy Efficiency and Indoor Air Quality: Solutions for Fire Stations

Louisville, KY -- Partnership Approach to Energy Efficiency in Non-Profit Facilities

Montgomery County, MD -- Technology Transfer of Building Energy Design Guidelines

New Orleans, LA -- Residential Utility Costs Comparative Study

Phoenix, AZ -- Variable Frequency Drive Applications Guide

Portland, OR -- Energy Savings Through Operation and Maintenance Training in the Low-Income Multi-Family Sector

Washington, DC -- Comparison of Two Techniques for Identifying Energy Conservation Measures in Low Income Homes

ENERGY, ENVIRONMENT and ECONOMIC DEVELOPMENT

This an area that has both visionary and immediate practical emphases on the definition and evaluation of realistic strategies and actions to support energy-sustainable and

environmentally responsible communities. Emphases include uses for renewable energy, practical domestic supply and conservation alternatives, and the synthesis of energy concerns with wider local government interests in economic development, environmental quality, and internal cost control. Urban strategies to improve energy-sustainability require attention to both broad based institutional changes, as well as specific projects designed to encourage the application of appropriate technology and community development practices. The "Sustainable Communities" project has involved three municipalities with State agency, Lawrence Berkeley National Laboratory, and a formal advisory committee with broad national representation. Projects under this unit are:

Austin, TX -- Energy Star Sustainable Rating Program

Phoenix, AZ -- Impact of Heat Island on Cooling and Environment: A Demonstration Project

Pima County, AZ -- Tucson Solar Village - Project Management

Portland, OR -- Sustainable City Transfer Project

San Francisco, CA -- Neighborhood Energy/Economic Development at South Bayshore

San Francisco, CA -- Sustainable City Transfer Project

San Jose, CA -- Sustainable City Transfer Project

Seattle, WA -- Coordination of Energy and Air Quality (CEAM)

Seattle, WA -- Bicycle Program -- Urban Trails System

Tucson, AZ -- Local Government Involvement in Long Term Resource Planning for Community Energy Services

Reports from each of these research projects, including this report, are specifically designed to aid the transfer of proven experience to other local governments. Readers interested in obtaining any additional reports or further information about the Urban Consortium Energy Task Force and the Urban Consortium should contact:

**Energy R&D Program
Public Technology, Inc.
1301 Pennsylvania Avenue, NW
Washington, DC 20004
1-800-852-4934**

ACKNOWLEDGEMENTS

Sincere appreciation is extended to the members of the City of Detroit's Energy Task Force team for their assistance and cooperation during the preparation of the Hydraulic Waste Energy Recovery Report: Creighton C. Lederer, P.E., Director of the Buildings and Safety Engineering Department, and Energy Task Force member; Albert H. Thomas, Project Director and Assistant Director for the Buildings and Safety Engineering Department; Joseph L. McGuire, P.E., Project Manager, and Head Engineer of the Detroit Water and Sewerage Department; Charlie J. Williams, Director of the Detroit Water and Sewerage Department; Remedios del Rosario, Assistant Director of the Detroit Water and Sewerage Department; Marilyn Gazadag, Administrative Assistant of the Buildings and Safety Engineering Department; Linda Miller, Contracts Section of the Detroit Water and Sewerage Department, Michelle Williams, Contracts Section of the Detroit Water and Sewerage Department.

Special mention of our consultant for their assistance in the investigation and for report delineation. The firm responsible for the project was Tucker, Young, Jackson, Tull, Inc.; Consulting Engineers; Detroit, Michigan. Those staff members directly involved included David K. Yang, P.E. and Edward Young, P.E.

Special thanks are given to the U.S. Department of Energy for providing the grant to the Urban Consortium Energy Task Force, and to the staff of Public Technology, Inc. for their assistance and critiques.

TABLE OF CONTENTS

Page

Preface

Acknowledgments

Table of Contents

Chapter 1 - Overview

1.1 Abstract	1
1.2 Project Purpose	3
1.3 Report Organization	3

Chapter 2 - General Background and Descriptions

2.1 Introduction	5
2.2 General Background and Descriptions	6
2.2.1 Site Selection	6
2.2.2 North Service Center Booster Station	6
2.2.3 Selection of In-Line Turbine Generator Unit	11
2.2.4 Interconnection with Local Electrical Utility	16
2.2.5 Power and Control Interface	16
2.2.6 Payback Assessment	19

Chapter 3 - Project Description

3.1 Introduction	23
3.2 Project Development and Application	23
3.2.1 In-line Turbine Connection with the Existing System	24
3.2.2 Turbine Building	26
3.2.3 Impacts of Future Turbine Operation and Construction	26
3.2.4 Operational and Control Philosophies	30
3.2.5 Construction Sequence	32
3.3 Results	33
3.4 Future Plans	34

Chapter 4 - Summary and Suggestions for Application

4.1 Lessons Learned	35
4.2 Suggestions for Application	36

Appendices

A -- Proposed In-Line Turbine Manufacturer's Information	37
B -- Study of Flow and Pressure at the North Service Center	47
C -- Economic Analyses	51

Table

Cost Estimate for Turbine Generators and Installation	20
---	----

Figures

1. Lake Huron System Water Transmission Mains	8
2. Daily Average Pressure at the North Service Center - 1989	9
3. North Service Center Booster Station	10
4. Turbine Generator Profile	12
5a. Headloss versus Flow Rate Across Reducing Valves - Existing Operating System	14
5b. Headloss versus Flow Rate Across Reducing Valves - Future Operating System	15
6. Single Line Diagram	18
7. North Service Center Site Plan	25
8. Base Plan Turbine Building	27
9. Section Turbine Building	28
10. North Service Center Booster Station - Construction Phases - Operation	29
B1. Energy Gradient in Existing Transmission Mains	50

CHAPTER 1

OVERVIEW

1.1 Abstract

One of the largest expenditures a municipality endures is the energy cost to run the pumps of its water distribution system. In 1988 the City of Detroit spent \$14 million on electricity to operate these supply pumps. In recent years, this cost has increased as the result of the need for additional pumping energy to supply an expanding service area. In order to offset these escalating energy costs, the City of Detroit is investigating the use of in-line turbine generators to recover waste hydraulic energy in the transmission system and convert it to electricity. The electricity produced will in turn be used to drive the pumps of the distribution system, thereby reducing the total amount of electricity purchased from the utility company.

Hydraulic turbine generators are the machines used to capture the energy of flowing water in the transmission system and convert it to electricity. These machines are composed of two components; a turbine and an induction generator. The turbine unit is placed in the stream of water in the transmission main. As water passes through the turbine, a force is imparted to the blades of a propeller causing them to rotate. An induction generator is mounted above the turbine and connected to the propeller by a shaft. The rotation of the propeller turns the induction generator yielding electricity. The electricity produced is then fed to the water distribution pumps reducing the kilowatt-hours of electricity required from the local utility.

The Hydraulic Waste Energy Recovery study was conducted in two phases, each having a duration of one year. The efforts of the first year, Phase I, were concerned with establishing the technical and economic feasibility of in-line turbine generation, while the research of Phase II focused on the tasks related to the operation and installation of in-line turbines.

The Interim Report¹ published at the conclusion of Phase I documents the results of the first year research. The conclusions of Phase I indicated that hydraulic energy recovery using turbine generators is technically feasible and will provide a cost effective way to slow increasing electricity costs.

1 Detroit Water and Sewerage Department. Hydraulic Waste Energy Recovery - Publication No. DG/90-331. Washington, D.C.: Public Technology, Inc., 1990.

The research objectives of Phase II were to determine the materials and procedures required for installation and operation of the turbine generation system. The results of this phase of the study provide the information necessary for the construction and implementation of the project.

The research performed during Phase II of this project consisted of four primary tasks.

- Determine additional equipment, materials, and structures necessary for turbine operation and connection with existing transmission system.
- Determine the impact of turbine generators on the existing transmission system during its construction and future operation.
- Determine sequencing between pressure reducing control valves and turbine generator to operate under the full range of flow conditions. The function of the pressure reducing control valves and their relation to the turbine generator is discussed in a subsequent section.
- Establish a sequence for construction.

Although this document provides a comprehensive review of the entire project, special attention is given to the research tasks undertaken during the final phase of the study. The results of Phase I are summarized in this report to provide background for the discussions of the Phase II studies. The results of the Phase II investigation are covered in Chapter 3.

The lessons learned from the hydraulic waste energy recovery study can help other communities implement similar systems. Although this study focused on installing turbine units upstream of booster pumping stations, many potential sites exist in a water transmission network where the flow and pressure conditions will support such energy recovery systems.

The flow and pressure characteristics in the water transmission line determines the amount of electricity which can be produced by the turbine generator, and ultimately the economic feasibility of the project. To maximize the electrical energy produced by the generator, careful study must be made of present and future flow and pressure conditions at a site. Special consideration must also be given to sizing the turbine to select the unit which will operate most efficiently in the given pressure and flow conditions. If the turbine generator project will involve

interconnection with lines of an electrical utility, early coordination is recommended to determine costs and guidelines for this procedure.

The constraint to the widespread application of in-line turbine generation has been that technical information regarding equipment, installation procedures, instrumentation and control as well as costs and potential savings of such systems is not readily available to every interested community. It is hoped that construction of the recommended turbine generators at the proposed pilot site will provide the operating data needed to remove the current constraints on the widespread use of this innovative technological application.

1.2 Project Purpose

The study completed for the Phase I Interim Report established that in-line turbine generation was technically and economically feasible at the North Service Center Booster Station, the site selected for the pilot installation. The research objectives of Phase II were to determine the materials and equipment necessary for turbine operation, the construction and future operation impacts of the turbine generators on the existing system, a plan for sequencing the operation of the turbines and pressure reducing valves of the existing transmission system and establishing a sequence for turbine construction.

At the installation site selected by this study, the turbine generators will provide two benefits. First, electricity generated by the turbines will reduce the kilowatt-hours of energy purchased from the local utility. Also, the turbines will act as flow rate control devices, regulating the pressure of flow as it enters the suction of the distribution pumps of the North Service Center Booster Station located immediately downstream.

Although this study focused on potential installation sites upstream of booster pump stations, turbine installations are not restricted to this specific application in a transmission system. The necessary flow and pressure required for turbine installations can be created by a number of circumstances which are common to every transmission system. Similarly, the technical information contained in this report regarding installation and operation of the turbine generators can be applied by any community wishing to implement such a system.

1.3 Report Organization

The following provides a brief description of the information contained in each of the major headings of this report:

CHAPTER 1: Overview

Provides a brief summary of the project, methodology, and results. Includes a statement of the project purpose and the potential benefit to local governments. This chapter also contains a description of the report organization.

CHAPTER 2: General Background and Descriptions

States the potential benefits of in-line turbine systems and describes how the research accomplished during this project can aid other communities in implementing similar projects. Also, summarizes the results of the technical and economic investigations of Phase I to provide background for the discussions of Phase II studies presented in Chapter 3.

CHAPTER 3: Project Description

Details the plans and processes developed during the research efforts of Phase II. It describes the connections with the existing system and the structure to house the turbine units, explains the plan to interconnect with the existing transmission and electric systems, defines the operation and control philosophies which will allow turbines to function through fluctuations in pressures and flow, and provides the anticipated construction sequence. It also summarizes the results of Phase II and discusses future plans for the project.

CHAPTER 4: Summary and Suggestions for Application

This chapter provides short descriptions of the major problems and successes encountered during the overall project and makes suggestions for municipalities considering similar projects. It also describes an alternative application for in-line turbine generators.

APPENDICES Include manufacturer's information regarding turbine generators, a study of the pressure and flow occurring at the selected installation site, and an economic analysis of the turbine generation system.

CHAPTER 2

GENERAL BACKGROUND AND DESCRIPTIONS

2.1 Introduction

Whenever a pressure change is required in any water distribution system, it requires adding or removing energy. A booster pumping station increases the energy of the water in a transmission system. On the other hand, a pressure reducing station or valve removes the energy from the system.

The energy required for booster station operation is supplied by the electrical utility company and has an associated cost. Energy removed by pressure reducing valves in the system is lost or wasted.

The objective of this project is to capture the wasted hydraulic energy with in-line turbines. In this application, the in-line turbines act as pressure reducing valves while removing energy from the water distribution system and converting it to electrical energy. The North Service Center pumping station was selected for the pilot program due to the availability of a wide range in pressure drop and flow, which are necessary for hydraulic energy recovery.

Although the use of turbines to capture the power of flowing water is not uncommon, the application of turbines in transmission systems represents a relatively innovative technology. Consequently, the technical information regarding the turbine equipment, controls, instrumentation, as well as installation procedures, guidelines for coordinating interconnection with electrical utilities, and costs of turbine systems are not available to all interested communities.

Pressure and flow conditions required to support a reliable cost effective source of electricity from turbine generation are common to nearly every municipalities' transmission system. The research performed during this project resulted in documentation of technical, economic, installation, and operational information necessary for local government officials to make an informed judgement as it relates to in-line turbine generation.

2.2 General Background and Descriptions

2.2.1 Site Selection

The initial task in this investigation was to identify potential sites for a pilot installation. The hydraulic characteristic necessary for turbine installation is a sudden reduction in water pressure within the transmission line. A drop in pressure is often created intentionally by placing a device such as a valve in the main. The pressure reduction is a result of the energy expended by the flowing water crossing the constriction created by the valve. The reason for placing a valve in the line is to control the pressure of the water downstream of the device.

Many reasons exist to control the pressure of the flow in a transmission system. One example in the Detroit system where valves are used to control pressure is immediately upstream of booster pumping stations. Booster pumping stations are located along the transmission line to increase the pressure of water in order to deliver it to distant reaches of the service area. To operate efficiently, the water pressure on the suction side of the pumps must be held within a certain range. To accomplish this, valves are placed upstream of the booster station to impede the incoming flow causing the reduction in the water pressure to the desired suction pressure of the booster pumps. In this project, the turbine generators replace the pressure regulating function of the existing valves, while using the energy of the flowing water to generate electricity.

The existing service agreements with the local electrical utility also affected site selection. The existing service agreements did not allow for purchase of power generated, but permitted interconnection between the in-line turbine and the existing electrical power transmission system. Hence, close proximity of the turbines and the booster pumps increased the project's cost effectiveness by reducing costs associated with installation of power lines.

2.2.2 North Service Center Booster Station

The North Service Center (NSC) is a booster pumping station located in the northern suburbs of the Detroit distribution system service area. This location became a potential pilot installation site because a pressure reducing valve station is located on the property. What made this site more attractive is the large pressure reduction at the reducing station. After examination of historic flow and pressure data for the transmission system, it was determined that hydraulic conditions at the North Service Center could support the operation of a hydraulic turbine generator.

The North Service Center booster pumping station operates within the Lake Huron Treatment Plant water transmission system and under the jurisdiction of the Detroit Water and Sewerage Department (DWSD). A map showing the relative locations of the Lake Huron Treatment Plant and the NSC booster station is shown in Figure No. 1. Water from the Lake Huron plant is pumped west through a 120-inch transmission main to the Imlay station. The Imlay facility is a booster station which is currently out-of-service. At this site, the flow is split between a 72-inch main which supplies the city of Flint, Michigan, further to the west and a 96-inch main which travels south to the North Service Center. Future operation of the Imlay pumping station is a critical variable in the hydraulic analysis of the system. Repumping the flow at Imlay station to either Flint or the North Service Center affects the energy and volume of the incoming flow to the North Service Center and consequently the performance of the turbine generator.

The Imlay station was designed to re-pump flow to the city of Flint and the North Service Center; however, the demand for water in this transmission system has not developed as expected. Because the demands for higher flow rates have not materialized, it remains more economical to continue to pump directly from the Lake Huron plant.

Current flow rates from the Lake Huron Water Treatment Plant are approximately 50 percent of the 120-inch transmission main capacity. At this discharge rate, friction losses occurring between the wall of the pipe and flowing water do not reduce the pressure of the water as they would at higher rates. Consequently, the water is at an average pressure of 120 pounds per square inch (psi) when it reaches the North Service Center. The chart shown in Figure No. 2 represents the daily average pressures of the incoming flow at NSC in 1989. These pressures are consistent with historical records of pressure at the NSC.

To operate efficiently, the water pressure on the suction side of the booster pumps must remain at approximately 35 psi. A pressure reducing valve station (PRV) accomplishes the required reduction in the incoming water pressure. The PRV station is located upstream of the booster pumps at the NSC site as shown in Figure No. 3. The PRV station is equipped with four cone valves. Cone valves are designed for pressure reducing applications and remain durable under the pressures applied. The pressure reducing

DAILY AVERAGE PRESSURE DISTRIBUTION FOR 1989

HYDRAULIC ENERGY RECOVERY		WATER AND SEWERAGE DEPARTMENT		DAILY AVERAGE PRESSURE AT NSC - 1989	
DATE: JANUARY 15, 1992.		CITY OF DETROIT		FIGURE 2	
COP. ENG. DIV.		TUCKER YOUNG JACKSON TULL, INC.		SCALE: NONE	
TJ/T - P122		CONSULTING ENGINEERS			
		300 E. LIVING ST. DETROIT, MI 48201			
		(313) 860-0912			

DETROIT WATER & SEWERAGE DEPARTMENT NORTH SERVICE CENTER

LEGEND

- ⊗ PRESSURE REDUCING VALVE
- ⊠ BUTTERFLY OR GATE VALVE
- PUMP
- FLOW DIRECTION

EXISTING (NORMAL) FLOW OPERATION

HYDRAULIC ENERGY RECOVERY

DATE: JANUARY 15, 1992.

DET. DIV. 5
TJ/JT-9012-015

CITY OF DETROIT
WATER AND SEWERAGE DEPARTMENT

NORTH SERVICE CENTER
BOOSTER STATION

SY TUCKER YOUNG JACKSON TALL, INC.
CONSULTING ENGINEERS
605 E. LOMBARD AVE. 2ND FLOOR, MI 48202 (313) 963-0915

FIGURE 3

SCALE: NONE

valve station is designed with two parallel pipes, each with two cone valves in series. Cone valves in series are required to split the large pressure drop between two valves to avoid damage from the high pressure.

The proposed turbine installation will be located on site and operate in conjunction with the pressure reducing valve station. Under normal service conditions, the majority of the flow will bypass the PRV station. This flow will be directed to the turbine installation to recover the energy presently being dissipated by the cone valves. Turbine control will be designed to regulate the turbines and maintain 35 psi downstream duplicating the function of the pressure reducing station. Turbine and pressure reducing valve control will be integrated to provide for flow outside the turbine range as well as turbine start-up and shut down.

2.2.3 Selection of In-line Turbine Generator Unit

The machines selected to operate under the hydraulic conditions of incoming flow at the North Service Center are semi-axial flow propeller type turbines. Figure No. 4 shows a profile of this turbine generator. Propeller type turbines are commonly used in similar high speed and relatively low pressure applications.

A series of moveable vanes called "wicket gates" at the propeller or inlet regulate flow through the turbine. The pitch of the propeller blades is fixed. Two 500 kW turbine units were specified for this project to better accommodate the wide range of flow conditions the NSC station experiences.

The induction generator is synchronized by the power grid it is connected to and does not require precise speed control like a synchronous generator. It is an induction motor turning faster than synchronous speed so that energy flows into rather than out of the electrical power supply system. Manufacturers' information pertaining to the turbine unit selected is shown in Appendix A. A listing of turbine manufacturers is contained in the Interim Report referenced in Chapter 1.

Estimated flows and pressures at the North Service Center were calculated for two system operating scenarios; the current mode of operation with flows to the NSC and Flint bypassing the Imlay booster station or a possible future scenario which involves repumping the flow to Flint at the Imlay station. Because the economy of Flint is closely tied to the auto industry, a resurgence in car manufacturing would influence the city's water demand making the latter pumping scenario probable.

BELOW GRADE PULL-OUT DESIGN

HYDRAULIC ENERGY RECOVERY	CITY OF DETROIT WATER AND SEWERAGE DEPARTMENT	TURBINE PROFILE
DATE: JANUARY 15, 1992.	TUCKER YOUNG JACKSON TULL, INC. CONSULTING ENGINEERS	FIGURE 4
<small>GAS FILED: 1/21/92</small> TYJT-9012-043	<small>ONE E. LAFAYETTE STREET 3RD FLOOR, DETROIT, MI 48226 (313) 963-6913</small>	SCALE: NONE

The performance range for the two turbines operating in parallel is plotted on Figure Nos. 5a and 5b. These figures show the pressure reduction presently accomplished by the pressure reducing valves, plotted against varying incoming flow rates at the North Service Center. The incoming flow rates are a function of the number of pumps operating at the Lake Huron Treatment Plant and the percentage of the total flow going to the city of Flint. These hydraulic variables are represented by the pumping curves in the figures.

The turbines performance range are overlayed on these drawings to show their capacity for reduction under the incoming flow and pressure variations. Figure No. 5a represents the current operation strategy of pumping directly from the Lake Huron Treatment Plant. Figure no. 5b shows how the NSC incoming hydraulic conditions are altered when the operating strategy changes by repumping a percentage of the flow from the Lake Huron Treatment Plant to the city of Flint at the Imlay Booster Station.

Both figures show the potential impact of operating the turbines, which can be highlighted as follows:

1. Under average system demand conditions, the turbines will operate with good efficiency.
2. Increase in future demand to Flint will increase the electricity generated by the turbines provided average pressure at NSC is increased due to lower friction losses in the 96-inch transmission main.
3. Repumping to North Service Center from Imlay Booster Station would preclude the turbines use. However, the time and level of effort required to increase the Lake Huron Water Treatment Plant and the Imlay station capacities to allow repumping to the North Service Center is longer than the turbine payback period.
4. In the event repumping to North Service Center is possible, it is unlikely that the Imlay station would re-pump flow to the NSC in the winter months because of a reduction in demand. Hence, turbine operation would be possible during this low flow period.

Further explanation of the hydraulic analysis is contained in Appendix B.

<p>HYDRAULIC ENERGY RECOVERY</p>	<p>CITY OF DETROIT WATER AND SEWERAGE DEPARTMENT</p>	<p>HEADLOSS VS FLOW RATE ACROSS PRESSURE REDUCING VALVES</p>
<p>DATE: JANUARY 15, 1992.</p>	<p>TYJ TUCKER YOUNG JACKSON TULL, INC. CONSULTING ENGINEERS</p>	<p>FIGURE 5A</p>
<p>DET. DES. No. TYJT-8012-017</p>	<p>600 E. LANSING AVE. 2ND FLOOR, DETROIT, MI 48226 (313) 963-0912</p>	<p>SCALE: NONE</p>

HYDRAULIC ENERGY RECOVERY	CITY OF DETROIT WATER AND SEWERAGE DEPARTMENT	HEADLOSS VS FLOW RATE ACROSS PRESSURE REDUCING VALVES
DATE: JANUARY 15, 1992.	TUCKER YOUNG JACKSON TULL, INC. CONSULTING ENGINEERS	FIGURE 5B
<small>END SHEET</small> TYJ-8012-017	<small>800 E. LAFAYETTE BLVD. 2ND FLOOR, DETROIT, MI 48226 (313) 843-0012</small>	SCALE: NONE

2.2.4 Interconnection with Local Electrical Utility

The Public Utility Regulatory Policies Act of 1978 (PURPA) and the Federal Energy Regulatory Commission (FERC) regulations are legislation that required electric utilities to interconnect and operate in parallel with cogenerators and small power producers which meet FERC requirements. They also require electric utilities to purchase power from qualifying utilities if requested to do so. The local electric utility is the Detroit Edison Co. (DE Co.). For this project, the Detroit Edison Company has waived the FERC pre-qualification requirement because the Detroit Water and Sewerage Department has agreed the utility would not be required to purchase the electricity produced by the generators.

Since the electricity generated by the hydraulic turbine feeds into the local utility line, certain standards and requirements had to be met by the "Independently Owned Generator" (IOG); in this case, DWSD. Early coordination with the local utility is a key to the success of a cogeneration project such as this. It is important that an IOG contact the utility early in the planning process to determine the interconnection requirements and costs for their specific project. Further discussion of the interconnection process and agreements can be found in the Year Eleven Interim Report.

The electrical system protective measures required to accommodate operation of an independently owned generator are influenced by many factors. Therefore, it is impossible for a utility to standardize protection requirements. The specific protective measures for each proposed interconnection is determined from individual analysis.

2.2.5 Power and Control Interface

Power supplied to the hydraulic turbine facility will be sufficient for lighting and operation of auxiliary equipment. The control interface will incorporate the following:

1. Generator controls, sequencing, and interlocks.
2. Turbine wicket gate controls and actuator.
3. Isolation valve controls and actuators.
4. Fuses, contactor, and load break switch for line connection.
5. All monitoring, protective, and alarm instruments.
6. All interconnecting power and control wiring between new and existing devices.

7. All necessary metering, protective relaying, and modifications to existing circuits.

The control system will be based on existing modular control and switchgear packages incorporating the items above. The control in this application will be based on maintaining a constant pressure in the line downstream of the pressure reducing valve station and hydraulic turbine generators regardless of flow conditions. This will require a computer controlled closed loop system with control outputs to the wicket gates. A programmable logic controller will be used for this purpose as well as for the generator as shown in Figure No. 6.

The standard control functions that will be specified are as follows:

1. Continuous monitoring of all auxiliary systems (cooling water, hydraulic pressure, and lube oil.)
2. Annunciation of all unit faults.
3. Automatic sequencing during start-up and shut down operations.
4. All auxiliary systems will be verified as to proper operation and appropriate pressures or flows. Any malfunction of an auxiliary system will prevent the start-up sequence from proceeding, annunciate the cause, and leave the turbine in a safe condition.
5. Continuous monitoring of output pressure in comparison with a predetermined set point.
6. Through closed loop control, the programmable logic controller will maintain the appropriate downstream pressure through adjustment of the turbine wicket gates within the range of the unit. When the limits of the turbine are approached, the programmable logic controller will either shutdown the turbines and turn control over to the pressure reducing valves or open the wicket gates to 100 percent and call upon the pressure reducing valves to assist in passing more flow.
7. Automatic restart of the generating units following a power outage on the part of the utility.
8. The control system will sense the utility outage, disconnect itself from the line, turn control over to the pressure reducing valves, and await the return of the utility. Upon restoration of voltage on the line for a predetermined length

FIGURE 6

CITY OF DETROIT WATER AND SEWERAGE DEPARTMENT ENGINEERING DIVISION NORTH SERVICE CENTER		2 0 0 4 0 2 1 0 1 9		E-2	
HYDRAULIC ENERGY RECOVERY		PARTIAL SINGLE LINE DIAGRAM		SCALE: AS SHOWN	
DESIGNED BY: TUCKER, YOUNG, JACKSON, FULL CHECKED BY: [] DATE: [] PROJECT NO.: [] DRAWING NO.: []		DESIGNED BY: [] CHECKED BY: [] DATE: [] PROJECT NO.: [] DRAWING NO.: []		DESIGNED BY: [] CHECKED BY: [] DATE: [] PROJECT NO.: [] DRAWING NO.: []	

of time, the control system will begin the sequencing necessary to bring the first unit up to speed, then place it on line. Should the first attempt fail, the controls will retry for a total of three times before issuing a lockout command and an alarm.

9. The programmable logic controller will be integrated into the system such that state changes, switch status, and relay status are known to it. Further, as part of the standard design, remote control points such as start/stop will be incorporated. This will permit the future addition of a remote Supervisory Control and Data Acquisition (SCADA) option with a minimum of field work and installation time.

Design criteria and standards for equipment, materials, and systems specified will be in accordance with the specifications of the following institutions:

ANSI	American National Standards Institute
ASTM	American Society for Testing and Materials
DWSD	Detroit Water and Sewerage Department, Control System Design Standards
IEEE	Institute of Electrical and Electronics Engineers
ISA	Instrument Society of America
MIOSHA	Michigan Occupational Safety and Health Administration
NEC	National Electric Code
NEMA	Nation Electrical Manufacturers Association
NFPA	National Fire Protection Association
OSHA	Occupational Safety and Health Administration of the U.S. Department of Labor
UL	Underwriters Laboratories

2.2.6 Payback Assessment

In determining the cost effectiveness of a project, the concept of "payback" year is often employed. The payback year is the time elapsed before the amount invested is recovered in actual dollars. Although this method is simplistic, it indicates whether a project is feasible from a capital management point of view. If a quick return on the investment is necessary for cash flow purposes, a long payback period is not desirable. The basic payback formula is payback period equals first cost divided by net annual savings.

1. First Cost

The first cost includes the estimated cost of two 500 kilowatts (kW) turbines, appurtenances, and installation. The first cost of the project is shown in the table below:

Table
Cost Estimate for Turbine Generators and Installation
=====

Turbine Generators (2 units - 500 KW each)	\$ 820,000
Structure	282,000
Switchgear	43,900
Instrumentation	28,600
Yard Piping	59,800
Valves	257,000
Mechanical Work	90,000
HVAC	10,500
Electrical Work	<u>28,600</u>
	\$1,620,400
15% Contingency	<u>243,060</u>
Total	\$1,863,460
SAY,	<u>\$1,864,000</u>
	=====

Source: Tucker, Young, Jackson, Tull, Inc.; October 1991;
Detroit, Michigan.

2. Net Annual Savings

The net annual savings is the difference between the cost of the power recovered by generating electricity and the annual maintenance expenditure. The energy saved is determined from the Detroit Edison Co. service rates developed by the utility for municipal customers requiring "primary voltage" (>24 kilovolts). The billing formula is shown in Appendix C. In addition to the charges for primary service, there is also a "standby service" charge. Standby service applies to customers who desire the util-

ity to serve load which is normally served by another source of energy such as a generator. Standby service capacity at NSC will be equal to the maximum output of the new turbine generators. Standby service rates are also shown in Appendix C.

Due to changes in pressure and flow, the power output of the turbine generators is expected to vary from 750 kilowatts to 1,000 kilowatts. A primary pumping rate savings and a standby service charge were calculated for the cases of 750 kW and 1,000 kW turbine generator output on a per month basis. The standby service charge was then subtracted from the primary pump savings. The result of this calculation is the total electric bill savings per month. These numbers were then pro-rated to determine a total annual savings. The annual savings for the cases of 750 kW and 1,000 kW turbine generator output are \$330,244 and \$452,568 respectively. The calculations appear in Appendix C.

3. Payback Period

Considering each case of generator productivity, the payback period varies 4.1 years - 5.7 years. Although these numbers are only a rough measure of the time the investment takes to pay for itself, the relatively short capital turnover time is desirable from a cash flow management point of view.

CHAPTER 3

PROJECT DESCRIPTION

3.1 Introduction

The city of Detroit Water Distribution System is supplied by five water plants and 20 booster pumping stations. The system serves 116 communities in the metropolitan area with a combined service population of approximately four (4) million.

Based on the most recent figures, the city of Detroit spends between \$15 to \$17 million per year for electrical power associated with pumping water into the distribution system. The city of Detroit system as a whole consumed approximately 300 million kilowatt-hours (kWh) during fiscal year 1987 - 1988. Of this total, over 80 percent is attributable to the five large water treatment plants associated with the system. The remaining 19 - 20 percent is consumed by the 20 booster stations located throughout the distribution network.

The North Service Center is one of the city's largest of the booster pumping stations. It consumes approximately 1.8 million kWh at a cost of \$1.2 million annually. This facility handles an average flow of approximately 20 to more than 100 million gallons per day depending upon the amount of water generated at the Lake Huron Water Treatment Plant.

3.2 Project Development and Application

In-line turbine generation is an innovative approach to energy recovery. Because it is a relatively unexplored technology, little documentation is available to serve as a guide in selecting installation sites, turbine equipment, and turbine control systems and instrumentation.

The objectives of Phase I of the Hydraulic Waste Energy Recovery Project were to determine if in-line turbine generation could be accomplished technically and if the project would be economically viable. Research tasks included investigation of flow demand characteristics at potential installation sites, review of applicable turbine equipment and suppliers, design of power control and interface with local utility system, and determination of economic feasibility. The results of the Phase I effort confirmed that the technology existed and that the project would prove to be economically desirable.

Since the flow and pressure conditions necessary for a successful in-line turbine generation project are common to nearly every transmission system, the results of the Phase I analyses would be beneficial to any community planning a feasibility study for a similar project.

The research objectives of the Phase II study were to determine the additional equipment, materials and structures necessary for operation and connection with the existing transmission system, the impacts of the turbine on the North Service Center's operation during construction and in the future, the sequencing between pressure reducing control valves and turbine generator, and the expected sequence of construction. Each of the research tasks are discussed below.

3.2.1 In-line Turbine Connection with the Existing System

To determine the location for the in-line turbine generator installation on site of the North Service Center Booster Station (NSC), the following items were considered: 1) minimize the length of the new water pipe; 2) require no relocation of existing water pipe; 3) require no relocation of utility line or equipment, and 4) require minimal or no disruption of existing North Service Center operation during construction. The location selected is shown on the plan of the North Service Center site in Figure No. 7.

This in-line turbine location will require two connections to the existing yard piping. One connection will be to an existing tee and the other to the existing 84-inch diameter water main. Once the new water pipe is constructed, tested, and approved, connecting to the tee and 84-inch water main will not inordinately disrupt the North Service Center's normal operation. It is proposed that NSC be supplied from another treatment plant during these operations.

Electrically actuated butterfly valves will be installed near the connections to the existing yard piping to isolate the new section of pipe. Two 36-inch electrically actuated cone valves located at the turbine building will regulate flow entering the turbines. Two 36-inch manually operated butterfly valves will isolate the turbine units.

LOCATION PLAN
NO SCALE

HYDRAULIC ENERGY RECOVERY

DATE: JANUARY 15, 1992.

END SHEET
TWT - P01

CITY OF DETROIT
WATER AND SEWERAGE DEPARTMENT

NORTH SERVICE CENTER SITE PLAN

BY TUCKER YOUNG JACKSON TULL, INC.
CONSULTING ENGINEERS
600 E. LANSING AVE. 3RD FLOOR, DETROIT, MI 48202 (313) 860-0300

FIGURE 7

SCALE: NONE

3.2.2 Turbine Building

Both turbines will be enclosed by a turbine vault. This two-level building measures 30 feet by 30 feet by 14 feet high, as shown in the layout and section of Figure Nos. 8 and 9. The concrete masonry block superstructure is supported on reinforced concrete walls and base slab.

The built up roof with metal deck and the steel grating floor at grade level are supported by structural steel members. Two roof hatches, which function as skylights, also provide access to the facility for removal of the turbines for maintenance or repair. Two 8-foot by 6-foot louvers are provided for air intake and the provision for exhaust fans is made at roof level.

The turbine building will be electrically heated to maintain temperatures and lower the relative humidity. Dual sump pumps will be specified. Power ventilation will be provided to control heat dissipated by the induction generators. Exhaust fans, louvers, and dampers will be controlled by thermostat.

3.2.3 Impacts of Future Turbine Operation and Construction

Turbine installation will be provided with automatic controls so that the turbines will be relatively transparent to normal operations at the North Service Center. Additional control and interconnections with the existing pressure reducing valve station will be installed so that the turbines and pressure reducing valves function together as required to match flow conditions outside the range of the turbines and when the turbines are out-of-service. Interruptions to the normal North Service Center operation during construction are discussed below:

1. Yard Piping Connection

Making the supply and the discharge connections for the turbine piping will each require operating shutdowns as can be seen in the proposed yard piping shown in Figure 10.

The turbine supply connection at the existing tee east of the pressure reducing valve well will require shutting off flow in the 96-inch main from Lake Huron long enough to remove the existing 60-inch blind flange and install a valve. It is estimated that this connection would require approximately eight to ten hours. The tees can be isolated between existing valves to minimize dewatering.

HYDRAULIC ENERGY RECOVERY	CITY OF DETROIT WATER AND SEWERAGE DEPARTMENT	BASE PLAN TURBINE BUILDING
DATE: JANUARY 15, 1992.	TUCKER YOUNG JACKSON TULL, INC. CONSULTING ENGINEERS 200 E. LAMAR STREET 2ND FLOOR DETROIT, MI 48202	FIGURE 8
TJ/T - F08		SCALE: NONE

DETROIT WATER & SEWERAGE DEPARTMENT NORTH SERVICE CENTER

OPERATION CHANGES:

- 1) CLOSE 96" DIA VALVE
- 2) FEED NSC FROM NORTHEAST OR ON SITE RESERVOIR
- 3) FEED FLINT & 96" CUSTOMERS FROM LHP AND DIRECT EXCESSIVE FLOW INTO IMLAY RESERVOIR

CONSTRUCTION ACTIVITIES:

- 1) REMOVE 60" DIA BLIND FLANGE AND INSTALL A VALVE
- 2) MAKE A TAP TO 84" DIA PIPE AND INSTALL A VALVE
- 3) INSTALL PIPING AND TURBINE WHICH WILL NOT HAVE IMPACT ON OPERATION

LEGEND

- ⊗ PRESSURE REDUCING VALVE
- ⊠ BUTTERFLY OR GATE VALVE
- PUMP
- FLOW DIRECTION

CONSTRUCTION PHASE OPERATION

HYDRAULIC ENERGY RECOVERY

DATE: OCTOBER 9, 1991

CAD DES. NO.: TYJT-9012-084

CITY OF DETROIT
WATER AND SEWERAGE DEPARTMENT

NORTH SERVICE CENTER
BOOSTER STATION

TYJT
TUCKER YOUNG JACKSON TULL, INC.
CONSULTING ENGINEERS
840 E. LARNED BLVD. 300 DETROIT, MI 48226 (313) 963-0812

FIGURE 10

SCALE: NONE

The turbine discharge connection will require installing an 84-inch by 60-inch tee and isolation valve. Shutting down this 84-inch main will prevent using the pressure reducing valve station.

It is estimated that this installation will take between 16 to 24 hours with careful planning and preparation. It is assumed that these two shutdowns must be scheduled to occur during a period of low demand. Considerable assessment and preplanning will be required as well as careful coordination with the Detroit Water and Sewerage Department. A flexible schedule and detailed preparation will be required of the contractor to allow appropriate timing of these operations. Work will be required to continue nonstop once a shutdown has begun. During shutdown periods, the North Service Center will be supplied from another municipal treatment plant as well as the on-site reservoirs.

2. Electrical Interconnection

Installation of the Detroit Edison Company metering devices will require shutdowns of approximately one to two weeks on each bus to install new metering equipment and making appropriate interconnections to the existing switchgear.

The tie-in of generation to existing switchgear will require a shutdown of one bus for approximately two to three weeks to make necessary switchgear modifications and the connections. The work can be done concurrently with the metering work on the affected bus.

During each of the shutdowns, the North Service Center can continue to operate on the remaining bus.

3.2.4 Operational and Control Philosophies

The turbine generator station will be controlled through a programmable logic controller which will govern the turbines and the existing pressure reducing valves. The basic function will be to maintain a downstream pressure. A great deal of flexibility is available in the programming and operational details must be worked out with the Detroit Water Sewerage Department. It is felt that the design goal must be minimizing the impact of the turbine installation on day-to-day operation of North Service Center. With the turbine station out-of-service, control of the pressure reducing valves will revert to the current method.

Automatic controls will be provided such that the turbines and pressure reducing valves will function together to cover the full range of operating conditions.

1. Turbine Start-up: As water is admitted to the turbine and as flow through the turbine is increased, the pressure reducing valves will close as required to maintain the downstream pressure.
2. Normal Operation: During normal operation, the turbine wicket gates will be modulated to maintain the downstream pressure; i.e., they will perform the pressure reducing function.
3. Excess Flow: When the required flow becomes high enough that the turbine reaches its full capacity (particularly if one turbine is out-of-service), the pressure reducing valves will open to bypass additional water and modulate to control the downstream pressure. Controls will be interlocked to provide for a minimum valve opening in order to avoid potential damage to the valves (which could occur if trying to regulate very near a closed position).
4. Electrical Failure: If the electrical load on the generator is lost, the turbine and the induction generator are designed to withstand a 200 percent overspeed for a minimum of 30 minutes. In that event, the turbine wicket gates and the turbine inlet valve would begin to close as the pressure reducing valves would begin to open taking the turbine off-line and putting the pressure reducing valves on-line. Valve operating speeds would be controlled to avoid water hammer or excessive pressure at the pump station.
5. Station Power Failure: The emergency power system at the North Service Center is designed to put the station valves in a safe condition if the incoming electrical power is lost. As a purely secondary system, it is proposed that the turbine valves be closed using emergency power and the turbines remain off-line until power is fully restored and any emergency conditions are over.

(Note: The induction generators cannot produce power unless connected to an external power source to magnetize the stator coils and establish the magnetic field and thus the frequency. Therefore, they could provide no emergency power.)

6. Turbine Shutdown: The turbine wicket gates will close to minimum position, and the pressure reducing valves will begin to open to maintain the North Service Center suction pressure. When the electrical output reaches a minimum and the generator goes off-line, the inlet valve will begin closing and the pressure reducing valve will continue opening. Valve operating speed will be regulated to prevent water hammer or significant pressure variation.

The turbines could also be placed on-line manually at a fixed wicket gate position and the cone valves regulated to control suction pressure. Wicket gate position as well as inlet valve position could be controlled from a remote location. Further study during design will select an optimum control configuration with minimum dependence upon automation.

3.2.5 Construction Sequence

Following award of a construction contract and subsequent start work order, construction of the proposed turbine installation will follow the approximate sequence shown below.

1. Order long lead time items: Turbine generators, valves, and electrical switch gear.
2. Schedule and plan construction in detail: Based upon valve deliveries and close coordination with Detroit Water and Sewerage Department (DWSD) operations. Preliminary operation changes due to construction activity is shown in Figure 10.
3. Install and test inlet and outlet yard piping.
4. Install conduit and wire.
5. Construct turbine vault.
6. Confirm shutdown plan and schedule. Coordinate as directed by DWSD.
7. Make inlet and outlet connections.
8. Complete and backfill yard piping.
9. Install turbine equipment and complete wiring.
10. Complete hydrostatic testing and disinfect piping.
11. Submit O&M and training materials for DWSD approval.

12. Schedule start-up based upon DWSD operation.
13. Start up without load: Verify correct operation of valves and turbine gate controls.
14. Start up underload: Assume load under manufacturer's supervision.
15. Operational testing and training: Place in closely supervised operation for a 30-day period. Train DWSD personnel.
16. Complete punch list work.
17. Final inspection and contract closeout.
18. Warranty period.

3.3 Results

Efforts of the final year of the Hydraulic Energy Recovery Project concentrated on remaining tasks required for construction. Having established the economic and technical feasibility of the project during Phase I, Phase II was concerned with the implementation of the project. The results of Phase II provide a location and layout of the turbine installation, a plan for interconnection with the existing yard piping and electrical systems, an operation and control strategy for the in-line turbines, and a sequence for construction.

The on-site location selected for the installation of the in-line turbines was based on several criterion. The location selected minimizes the length of new water pipe, requires no relocation of the existing pipe or utility lines, and requires little disruption of the existing system.

Determining valves and piping required for the turbine operation was necessary so that their detailed design could be completed. The turbine building will provide shelter for the electrical and mechanical equipment. The structure was designed with ample space and access to the turbines for maintenance. The turbine building will be heated to control temperatures and humidity.

Connections of new piping to existing yard piping will require two shutdowns. The upstream connection will require 8 to 10 hours; the downstream installation may require 16 to 24 hours. The shutdowns must be scheduled to occur during periods of low system demand. Considerable assessment and preplanning will be required

as well as careful coordination with the Detroit Water and Sewerage Department. A flexible schedule and detailed preparation will be required of the contractor to allow appropriate timing of these operations. During shutdown periods, water will be supplied from another treatment plant. The interconnection of electrical equipment will require shutdown of the incoming power lines. The work to be completed during this shutdown includes installation of Detroit Edison metering equipment and tie-in of the generators to the existing switchgear. The work will proceed on one bus while the other will continue to feed the North Service Center. Each shutdown is expected to last one to three weeks.

The turbine generator station will be controlled through a programmable logic controller which will govern the operation of the turbines and existing pressure reducing valves. The basic function will be to maintain a downstream pressure. A great deal of flexibility is available in the programming and operational details must be worked out with the Detroit Water and Sewerage Department. The design objective is to minimize the impacts of the turbine installation on day-to-day operation of the North Service Center.

3.4 Future Plans

The efforts of Phase II of the Hydraulic Energy Recovery study will result in the construction of a pilot installation located at the North Service Center site. The goal of this phase of the project was to provide documentation for the installation and operation of the in-line turbines so that detailed drawings and specifications could be prepared for construction. The North Service Center pumping station was selected for the pilot project because of its unique flow and pressure characteristics. If this installation is successful, the Detroit Water and Sewerage Department will consider other sites for future installations.

CHAPTER 4

SUMMARY AND SUGGESTIONS FOR APPLICATION

4.1 Lessons Learned

The decision to install a turbine generation unit should be based on the economic feasibility of the project. The economic feasibility of the project is strongly dependent on the flow characteristics at the proposed installation site. In the investigation of potential installation sites, flow metering studies would be encouraged if such studies have not been performed previously. Flow metering facilities were not available at the North Service Center or the Lake Huron Treatment Plant. This required relying on the Lake Huron High Lift pump curves and iterative calculations to estimate flow at North Service Center. Fortunately, pressure and flow data for the 76-inch main traveling to Flint was available to confirm these calculations.

Flow characteristics are critical when sizing a turbine unit. The equipment selected must make the best use of the energy available. If the turbine generators selected were sized to make best use of the energy available during the peak demand months, they would be idle several months of the year with an insufficient volume of water. Selecting larger turbine units to handle a greater volume of water is also more costly. An energy cost analysis indicated the most productive use for turbines would be to design them for the average flow conditions which remain relatively constant through the non-peak months of the year.

In addition to making use of historical flow and pressure data, a study of the projected demands is also imperative. The expected demand in the service area of the Lake Huron Treatment Plant never developed as predicted. The present demand does not require water from the Lake Huron Plant be repumped to the city of Flint or the North Service Center at the Imlay Booster Station. Should future demands require that flows to the North Service Center be increased by repumping at Imlay Station, the turbines would become obsolete because of the reduction in pressure head this creates. An increase in water demand could be triggered by a rebound in the auto industry; however, the duration of the projects required at the Imlay Station and Lake Huron Treatment Plant to increase their flow capacities is much longer than the turbine payback period.

One of the keys to success in this project has been the relationship developed with the Detroit Edison Company, the local electrical utility. Early in the study phase of the project, the utility company was contacted. The information supplied by the Detroit Edison Company on their power cost structure was critical in determining the economic feasibility of the project. The utility also provided a set of guidelines distributed to all independently owned generators that wish to operate in parallel with the electric utility. The guidelines outline all requirements and responsibilities of the independently owned generator for interconnection with the utility. The guidelines and information provided were essential in the planning for the eventual interconnection. The Detroit Edison Company was eager to participate in this project as they could better predict their future load requirements knowing the electrical needs of the City of Detroit.

4.2 Suggestions for Application

The technology necessary to install and operate an in-line turbine generator is transferrable to any community wishing to implement such a project. The primary consideration in planning such a system is whether the pressure and flow characteristics are available to sustain the turbines efficient operation and what payback period is desired. Potential energy savings at the NSC will allow a payback period of approximately four years. The annual cost savings will amount to nearly half a million dollars.

The turbine generator technology used for this project could also be applied to in-line wastewater systems which undergo similar forced reductions in pressure.

The final step in this project will be its construction which is scheduled for 1992. If this pilot program proves successful, other sites will be considered for similar installations.

Appendix A
Proposed In-Line Turbine Manufacturer's Information

SPECIFICALLY DESIGNED FOR SMALL HYDROELECTRIC SITES.

Byron Jackson has used the hydraulic design experience gained through more than a century of leadership in centrifugal pumps to develop the TKW. TKW is not a pump but a semi-axial flow hydraulic turbine designed for small hydroelectric sites.

MANUFACTURING EXPERTISE

Byron Jackson has developed an unmatched manufacturing expertise that encompasses precision machining, extensive testing and stringent quality control. The latest computer-aided design and manufacturing techniques and metallurgical controls are employed in producing the TKW.

PRODUCT TESTING

We maintain an on-going turbine test program in our

THE NEW TKW DELIVERS

- Higher Return on Investment
- Shorter Payback Period

HERE'S HOW:

- *More Efficient* than Kaplan and Francis style turbines in the design ranges shown.
- *Wider Operating Range* than a reverse running pump
- *Lowest* total capital investment per kilowatt output
- *Reduced* installation costs
- *Flexible* payment options
- *Complete* water-to-wire systems

own hydraulic laboratories. The TKW has been thoroughly tested for KW output, efficiency, runner setting and, runaway speed flow.

SIMPLE INSTALLATION

The TKW has been designed to maximize standardization and avoid complex controls. The result is reduced maintenance and prompt delivery. The simplified, compact design reduces site preparation and cost. Complete factory assembly of the turbine achieves further cuts in installation time and cost.

WORLDWIDE SERVICE

Our service capabilities are second to none. Byron Jackson Service Centers and warehouses are strategically located worldwide to provide quick turnaround on repairs, and responsive parts delivery. Technicians are available to handle installation, repair, start up, and field service.

PUT THE TKW IN YOUR APPLICATION PLANS

- For sites of 50 KW to 3000 KW
- 50 KW to 1000 KW per Unit
- 40 to 150 feet of head per stage

RANGE CHART—TKW TURBINES

**THESE FEATURES GIVE YOU THE MOST
COST-EFFECTIVE TURBINE ON THE MARKET.**

LESS FLOOR SPACE

Vertical configuration requires only 30% to 40% of the floor space needed with conventional turbine designs. Reduces site preparation and civil engineering costs.

THE RIGHT MATERIALS FOR YOUR SITE

Stainless steel shaft. Nickel aluminum bronze wicket gates, runner, and runner case. Other metallurgies are available as required.

CHOICE OF CONTROLS

Controls can be automatic or manual. Alternative mechanisms can be provided to meet specific site requirements.

YOUR CHOICE OF BEARING CONSTRUCTION

Self-lube, oil-lube, or grease-lube bearings can be specified to meet your site conditions and prolong bearing life.

EASE OF MAINTENANCE

Inspection-Port above turbine case allows easy access. Runner and bottom bearing are replaced by removing draft tube. Simpler design and fewer components than either a Kaplan or Francis style turbine.

**ADJUSTABLE WICKET GATES TO
OPTIMIZE GENERATOR CAPACITY**

Wicket gates can be adjusted during operation to exactly match the site conditions. This ensures that you can maximize power recovery and optimize power generation over a wide operating range.

NO CHOKE-FLOW PROBLEMS

Water hammer problems are eliminated since the runaway speed flow curve approximates the turbine design flow. Valve response time to stop total flow is no longer critical — a significant advantage over most other types of turbines, and is an inherent safeguard not available in reverse running pumps.

LESS DOWNTIME

In the event of wear, the runner can be axially adjusted at the operating floor level to restore original operating clearances without disassembly.

DRAFT TUBE FOR ENERGY RECOVERY

Designed for maximum energy recovery of velocity head, the fabricated steel draft tube is flanged for connection to the runner casing.

Available in
Vertical or
Horizontal
Configuration

BW/IP International, Inc.
Tulsa Operations

14
TOTAL HEAD IN FEET

A MINIMUM GATE OPENING
B/C INTERMEDIATE OPENINGS
D MAXIMUM GATE OPENING

CUBIC FEET PER SECOND

15 H TKW 720 RPM NPEH = 30.00
2 STAGES

18-OCT-91

CUBIC FEET PER SECOND

15 H TKW 720 RPM NPEH = 30.00
2 STAGES TURBINES IN PARALLEL

BYRON JACKSON TYPE TKW STYLE DB PULLOUT PRELIMINARY OUTLINE DIMENSIONS

BASIC OUTLINE

TYPICAL METHODS OF BARREL INSTALLATION

NOZZLE ORIENTATION

OPTIONAL PIPING/NOZZLE ADAPTATION

OPTIONAL BASEPLATE/MOUNTING FLANGE

OUTLINE DIMENSIONS - INCHES

TURBINE SIZE	A	B	C	D	E	F ¹	G ¹		J ²	L	M	N ⁵	P	Q	V	W	X	Y	H ⁶			
							1-STG COMP.	ADD PER STG.											K-DEGREES			
																			0	45	90	135
6 PL	35	31	33	1		30	40	14	12	24	30	16	16	32	34	1	1 1/8	1	24	17	12	5
8 M	41	37	39	1		30	65	19	12	28	36	16	19	38	40	1	1 1/2	1	24	19	12	5
8 H	41	37	39	1	1	30	70	19	14	29	36	20	21	38	40	1	1 1/8	1 1/8	28	23	16	5
10 H	66	66	54	1 1/2		30	84	24	17 1/2	37	48	26	25	52	54	1 1/4	1 1/8	1 1/8	35	27	17	6
12 H	72	72	60	1 1/2		30	101	29	20	40	54	30	30	58	60	1 1/4	1 1/8	1 1/8	40	34	22	7
15 M	72	72	60	1 1/2		30	115	33	20	40	54	30	30	58	60	1 1/4	1 1/8	1 1/8	40	34	22	7
15 H	79	79	70	1	1 1/2	30	120	33	23 1/2	44	60	36	35	64	66	1 1/4	1 1/8	1 1/8	47	38	26	9
18 H	91	84	83	1 1/2	1 1/2	36	142	42	27	53	72	42	42	76	80	1	1 1/2	1 1/2	54	46	31	11
21 H	106	106	97	1	1 1/2	36	165	47	31 1/2	60	84	50	49	90	92	1	1 1/2	1 1/2	63	55	38	15
24 H	124	124	110	2	1 1/2	36	198	56	37 1/2	67	96	60	59	102	104	1	2 1/4	1 1/2	74	66	46	17

TABLE ADAPTATION DIMENSIONS

6 M PL 6 IN-CA
10 M PL 10 IN-DA
15 M PL 6 IN-CA
18 M PL 4 IN-DA

NOTES:

1. Barrel length may be increased if necessary for extra-deep nozzle setting.
2. H dimension is the typical minimum generator stand height. Applications requiring oversize turbine shafting or special wicket gate operators may require additional height.
3. Standard barrel nozzles are sized for moderate fluid approach velocity to provide efficient and quiet operation. Where required, separate nozzle adaptors or integral welded adaptors may be specified.
4. Specify "Byron Jackson To Supply" or "By Others".
5. Standard nozzles have 150 lb. or 125 lb. standard A S A. raised face flanges.
6. Nozzle water greater than 150 lb. may require greater elevation difference. Inlet nozzle elevation is always equal to or above discharge elevation.
7. 150 lb. or 300 lb. nozzle flanges require additional base-to-nozzle clearance.
8. Contact B.J. Engineering Department for special installation/mounting design.

BARREL INSTALLATION AND MOUNTING CONSIDERATIONS

Pullout barrels can be permanently embedded in concrete, or they can be bolted to a baseplate. Each means of installation has certain advantages over the other. The embedded barrel will result in quieter operation due to the sound damping effect of the concrete and soil. For speed or ease of installation, the flange-mount barrel can be provided. A separate baseplate, anchor bolts, and flange mounting hardware will also be furnished. Installation of the baseplate will be performed by others. The baseplate and mounting flange mating surfaces are machined flat and after the baseplate has been properly levelled and grouted, the turbine barrel is simply lowered into place. With either type of pullout barrel installation, the barrel may be left in place, leaving the connected piping undisturbed, should it become necessary to remove the turbine for maintenance.

BYRON JACKSON TKW HYDRO TURBINE

PRELIMINARY OUTLINE-BELOW GRADE PULL-OUT DESIGN

USER:	DRAWN BY	DATE	PROP. NO.
LOCATION:			
DRAWING TITLE:

BYRON JACKSON HYDRO TURBINE SYLE DB
BELOW GRADE PULL-OUT DESIGN

Appendix B

Study of Flow and Pressure at the North Service Center

The pressure and rate of the incoming flow to the North Service Center site is controlled by the number of pumps operating at the Lake Huron Treatment Plant. This facility has five pumps, each is rated at a discharge capacity of 60 million gallons per day (MGD). The number of pumps operating is a reflection of the demand created by the system. To supply the average day demand for treated water in this system, two (2) pumps with a combined discharge of 120 MGD are required. During extreme hot or dry periods of the summer months, three (3) or four (4) pumps may operate. The pressure downstream of the pumps is maintained between 170 and 190 pounds per square inch (psi).

On an average day, (2 pump operation) the demand from the city of Flint will be approximately 35 MGD with the balance of the flow travelling to the North Service Center (NSC). Under these normal operating conditions, the pressure of the flow arriving at NSC in the 96-inch transmission main will be approximately 120 psi. Figure No. 2 presents the range of pressures occurring at NSC in 1989.

Several factors effect the pressure of the incoming flow at NSC. Increasing the flow through the 96-inch transmission main to the NSC also causes a pressure reduction in the flow by increasing the energy required to overcome the effects of friction against the moving water. Therefore, as additional pumps are placed in service at the Lake Huron Plant, a corresponding reduction in pressure occurs at the North Service Center due to the increase in losses attributed to friction. Figure B-1 shows the pressure reduction occurring in the system, measured in units of feet, for multiple pump operation at the Lake Huron Plant.

As mentioned earlier, the operation of the Imlay Booster Station will effect the flow and pressure arriving at the NSC. This station was designed with the capacity to pump to the city of Flint as well as to the NSC. Currently, the station is only equipped with pumps to service the city of Flint. Increasing the flow to Flint to some degree will increase pressures arriving at the NSC by reducing the pressure required necessary at the Lake Huron Treatment to pump to Flint. If future demands at NSC require pumping from Imlay Station, the use of the turbines would be precluded due to the pressure drop created by friction forces acting on the increased flow rate.

DETROIT WATER & SEWERAGE DEPARTMENT

ENERGY GRADIENT - 120", 96" AND 60" WATER MAIN

LEGEND

- 2 PUMPS OPERATING
- 3 PUMPS OPERATING
- 4 PUMPS OPERATING
- EL. 994.4' ELEVATION OF HEAD (PRESSURE) IN FEET

HYDRAULIC ENERGY RECOVERY		CITY OF DETROIT WATER AND SEWERAGE DEPARTMENT	PROPOSED IN-LINE TURBINE
DATE: JANUARY 15, 1992.			
600 ENG. PROJ. TWT-FID A-1		TY TUCKER YOUNG JACKSON TULL, INC. CONSULTING ENGINEERS 600 E. LECHE BLVD. SUITE 300 DETROIT, MI 48226 (313) 960-0913	FIGURE B - 1
			SCALE: NONE

Appendix C
Economic Analyses

HYDRAULIC ENERGY RECOVERY
AT
NORTH SERVICE CENTER
PREPARED BY TUCKER, YOUNG, JACKSON, TULL, INC.

DEFINITION:

1. DAILY ON-PEAK DEMAND:

The highest 30-minute integrated reading of the demand meter in each day from 11 a.m. to 7 p.m., weekdays only.

2. DAILY DEMAND:

The daily on-peak demand plus one third of the amount by which it is exceeded by the highest single demand occurring during the off-peak hours on the same calendar day.

Daily Demand = Daily On-peak Demand + $1/3$ (Daily Off-peak Demand - Daily On-peak Demand)

3. WEEKLY BILLING DEMAND:

The highest of the Daily Demand established on seven-day intervals.

4. MONTHLY BILLING DEMAND (DEMAND CHARGE = AVERAGED DEMAND):

The average of the four weekly demands (period after 21 days of the month is considered as the fourth week). The monthly billing demand should be not less than 50 percent of contract capacity; otherwise, it is set equal to 50 percent of the contract capacity and it is called ratchet.

Monthly Billing Demand = $(WK1 + WK2 + WK3 + WK4) \text{ Weekly Billing Demand} / 4$

5. MAXIMUM DEMAND:

The highest 30-minute demand created during the previous 12 billing months, including the current month. Maximum demand should be not less than 50 percent of contract capacity.

6. STANDBY CONTRACT CAPACITY (SCC):

Standby contract capacity (SCC) in KW will be established for electric capacity sufficient to meet the customer's standby load.

E4, 1991 MONTHLY RATE:

1. SERVICE CHARGE:	\$269.00
2. MONTHLY BILLING DEMAND:	\$13.23 /KW
3. MAXIMUM DEMAND:	\$2.65 /KW
4. ENERGY CHARGE:	\$0.0393 /KWH
5. OFF PEAK DISCOUNT:	\$0.007 /KWH
6. ENERGY DISCOUNT:	\$0.001 /KWH
7. NUCLEAR DECOMMISSIONING SURCHARGE:	\$0.0000455 /KWH
8. SURCHARGES (RCS+ESS):	\$0.0015 /KWH

TOTAL CHARGE = SERVICE CHARGE + MONTHLY DEMAND + MAXIMUM DEMAND + ENERGY CHARGE
+ (OFF-PEAK DISCOUNT + ENERGY DISCOUNT)
+ NUCLEAR DECOMMISSIONING SURCHARGE + SURCHARGES

R3, STANDBY SERVICE RATE:

1. SERVICE CHARGE:	\$210.00
2. MONTHLY RESERVATION GENERATION FEE:	\$0.85 /SCC IN KW
3. NON-GENERATION CHARGE:	\$2.36 /SCC IN KW
4. DAILY ON-PEAK DEMAND CHARGE FOR BACKUP POWER:	\$0.82 /KW/DAY
5. ENERGY CHARGE FOR BACKUP POWER:	\$0.0399 /KWH
6. OFF PEAK DISCOUNT:	\$0.007 /KWH
7. ENERGY DISCOUNT:	\$0.001 /KWH
8. NUCLEAR DECOMMISSIONING SURCHARGE:	\$0.0000622 /KWH
9. SURCHARGES (RCS+ESS):	\$0.0015 /KWH

WAIVERS AND LIMITS FOR DEMAND/ENERGY RATE

- (a) If the total of Daily Demand charges for the month is less than the monthly generation reservation fee, then the daily demand charges will be waived for that month.
- (b) If the total of daily demand charges for the month is greater than the monthly generation reservation fee, then the generation reservation fee will be waived for that month.

TOTAL SAVING IN ELECTRIC BILL:

EXAMPLE 1: OUTPUT OF THE TURBINES = 1,000 KW

ASSUMPTIONS: 9 DAYS/MONTH HOLIDAY OR WEEKEND.

OUTPUT OF THE TURBINES IS CONSTANT/MONTH.

NO MAINTENANCE CHARGES.

POWER CONSUMPTION EXCEEDS POWER GENERATED BY THE TURBINES.

TOTAL SAVING IN ELECTRIC BILL = SAVING IN E4 + R3 CHARGE
--

STANDBY CONTRACT CAPACITY (SCC) @ N.S.C. =	1000 KW
OUTPUT OF THE TURBINES =	1000 KW
TOTAL ON-PEAK DEMAND HOURS/MONTH = 8 HRS * (31-9) DAYS	176 HRS
TOTAL OFF-PEAK DEMAND HOURS/MONTH = 16 HRS * 31 DAYS + 8 HRS * 9 DAYS	568 HRS

1) E4, PRIMARY PUMPING RATE SAVING:

SCC KWH = SCC (KW) * (ON-PEAK HOURS + OFF-PEAK HOURS)/MONTH	744000 KWH
MONTHLY BILLING DEMAND:	\$13,230
MAXIMUM DEMAND:	\$2,650
ENERGY CHARGE:	\$29,239
OFF-PEAK DISCOUNT:	\$3,976
ENERGY DISCOUNT:	\$744
NUCLEAR DECOMMISSIONING SURCHARGE:	\$34
SURCHARGES (RCS+ESS):	\$1,116
 TOTAL PRIMARY PUMPING RATE SAVINGS/MONTH =	 \$41,549

2) R3, STANDBY SERVICE CHARGE:

SERVICE CHARGE:	\$210
MONTHLY RESERVATION GENERATION FEE:	\$850
NON-GENERATION CHARGE:	\$2,360
DAILY ON-PEAK DEMAND CHARGE FOR BACKUP POWER: (31-9) DAYS *	\$0.82
ENERGY CHARGE FOR BACKUP POWER:	\$0
OFF PEAK DISCOUNT:	\$0
ENERGY DISCOUNT:	\$0
NUCLEAR DECOMMISSIONING SURCHARGE:	\$0
SURCHARGES (RCS+ESS):	\$0
 TOTAL STANDBY CHARGE =	 \$3,420

TOTAL ELECTRIC BILL SAVING =	\$38,129 /MONTH
------------------------------	-----------------

(NOTE: THE NUMBER IS THE SAME FOR EACH 31 DAY MONTH IF THE TURBINES GENERATE 1000 KW)

ECONOMIC ANALYSIS:

PRICE FOR A TWO 500 KW TURBINE:	\$820,000
CONSTRUCTION COST:	\$1,033,000
FIRST COST:	\$1,853,000
MAINTENANCE FEE =	\$5,000 /YEAR
INSTALLING TURBINE WOULD SAVE:	\$38,129 /MONTH
NET ANNUAL SAVING	\$452,549 /YEAR
PAY BACK PERIOD =	$\frac{\text{FIRST COST}}{\text{NET ANNUAL SAVING}}$
PAY BACK PERIOD =	4.1 YEARS

EXAMPLE 2: OUTPUT OF THE TURBINES < 1,000 KW

ASSUMPTIONS: 9 DAYS/MONTH HOLIDAY OR WEEKEND.

OUTPUT OF THE TURBINES IS CONSTANT/MONTH.

NO MAINTENANCE CHARGES.

POWER CONSUMPTION EXCEEDS POWER GENERATED BY THE TURBINES.

TOTAL SAVING IN ELECTRIC BILL = SAVING IN E4 + R3 CHARGE
--

STANDBY CONTRACT CAPACITY (SCC) @ N.S.C. =	1000 KW
OUTPUT OF THE TURBINES =	750 KW
TOTAL ON-PEAK DEMAND HOURS/MONTH = 8 HRS * (31-9) DAYS	176 HRS
TOTAL OFF-PEAK DEMAND HOURS/MONTH = 16 HRS * 31 DAYS + 8 HRS * 9 DAYS	568 HRS

1) E4, PRIMARY PUMPING RATE SAVING:

SCC KWH = SCC (KW) * (ON-PEAK HOURS + OFF-PEAK HOURS)/MONTH	744000 KWH
MONTHLY BILLING DEMAND:	\$13,230
MAXIMUM DEMAND:	\$2,650
ENERGY CHARGE:	\$29,239
OFF-PEAK DISCOUNT:	\$3,976
ENERGY DISCOUNT:	\$744
NUCLEAR DECOMMISSIONING SURCHARGE:	\$34
SURCHARGES (RCS+ESS):	\$1,116
 TOTAL PRIMARY PUMPING RATE SAVINGS/MONTH =	 \$41,549

2) R3, STANDBY SERVICE CHARGE:

SERVICE CHARGE:	\$210
MONTHLY RESERVATION GENERATION FEE:	\$0
NON-GENERATION CHARGE:	\$2,360
DAILY ON-PEAK DEMAND CHARGE FOR BACKUP POWER: = (31-9 DAYS)*	\$0.82
	\$4,510
ENERGY CHARGE FOR BACKUP POWER:	\$7,421
OFF PEAK DISCOUNT:	\$994
ENERGY DISCOUNT:	\$186
NUCLEAR DECOMMISSIONING SURCHARGE:	\$12
SURCHARGES (RCS+ESS):	\$279
 TOTAL STANDBY CHARGE =	 \$13,612

TOTAL ELECTRIC BILL SAVING =	\$27,937 /MONTH
------------------------------	-----------------

(NOTE: THE NUMBER IS THE SAME FOR EACH 31 DAY MONTH IF THE TURBINES GENERATE 1000 KW)

ECONOMIC ANALYSIS:

PRICE FOR A TWO 500 KW TURBINE:	\$820,000
CONSTRUCTION COST:	\$1,033,000
FIRST COST:	\$1,853,000
MAINTENANCE FEE =	\$5,000 /YEAR
INSTALLING TURBINE WOULD SAVE:	\$27,937 /MONTH
NET ANNUAL SAVING	\$330,245 /YEAR
PAY BACK PERIOD =	$\frac{\text{FIRST COST}}{\text{NET ANNUAL SAVING}}$
PAY BACK PERIOD =	5.6 YEARS

SUMMARY:

ASSUME STANDBY CONTRACT CAPACITY 1,000 KW
MAINTENANCE FEE = \$5000 /YEAR
NET ANNUAL SAVING = ELECTRIC BILL SAVING - MAINTENANCE FEE
FIRST COST = \$1,853,000

OUTPUT OF THE TUR (KW)	MONTHLY ELECTRIC BILL SAVING	NET ANNUAL SAVING	PAY BACK PERIOD (YEAR)
1,000	\$38,129	\$452,548	4.1
875	\$33,458	\$396,496	4.7
750	\$27,937	\$330,244	5.6
625	\$22,416	\$263,992	7.0
500	\$16,895	\$197,740	9.4

REPORT AND INFORMATION SOURCES

Additional copies of the Final Report, "Hydraulic Waste Energy Recovery," are available from:

Publications

Public Technology, Inc.

1301 Pennsylvania Avenue, NW

Washington, DC 20004-1793

Additional information on the structure, operation, and results of this study as well as information on other energy management activities in the city of Detroit are available from:

Crieghton C. Lederer, Energy Coordinator

Buildings and Safety Engineering Department

401 City-County Building

Detroit, Michigan 48226

(313) 224-3252

Publication No. DG/91-311

CITY OF DETROIT

MAYOR

Coleman A. Young

CITY COUNCIL

Maryann Mahaffey, President

Gill Hill, President, Pro Tem.

Keith A. Butler

Clyde Cleveland

David Eberhard

Kay Everett

Nicholas Hood

Jack Kelley

Mel Ravitz

Publications Price List--UCETF Reports

ITEM #	TITLE	PRICE
90-331	Hydraulic Waste Energy Recovery: A Technical Report	15.00
90-318	A Regulatory Framework for Alternative Fuels and Transportation Management Services	15.00
90-316	Alternative Vehicle Fuels: A Demonstration Project	15.00
90-314	Energy Efficiency in Public Housing	15.00
89-330	Analysis of Programmatic Fleet Conversion to Ethanol Blends	15.00
89-325	An Alternative Fuels Evaluation System for Fleet Vehicles	15.00
89-323	Dual Fuel Conversion Demonstration and Technology Transfer Project	10.00
89-321	Summary of Low and Moderate Income Residential Energy Conservation Programs	15.00
89-315	A Case Study in the Pursuit of Urban Energy Efficiency	15.00
89-314	Communicating with the Public About Environmental Health Risks: A Case Study	13.00
89-313	Evaluation and Comparison of Selected Household Hazardous Waste Collection Facilities	15.00
89-311	Yard Waste Recycling Study: A Pilot Study	15.00
89-310	Sludge Storage Lagoon Biogas Recovery and Use, Volume 1	15.00
89-307	Proceeding: 1989 Electric Utility Franchise Conference	20.00
89-306	Reducing Electricity Demand Through Energy-Related Efficient Construction	15.00
89-304	Modernization of Lighting in Municipal Auditoriums	15.00
89-303	Wastewater Treatment Process Energy Optimization	13.00
89-301	Implementation of Alternative Technologies through the Assessment of Energy Markets	14.00
88-322	Marketing Energy Efficiency Programs to Commercial and Industrial Firms: Lighting Incentives and	15.00
88-321	Urban Energy Management Today: Ten Year Compendium of UCETF Programs	10.00
88-319	Integrating Energy Efficiency Into Municipal Purchasing Decisions: Computerizing Procurement	15.00
88-318	Household Hazardous Waste: Implementation of a Permanent Collection Facility	20.00
88-317	Hazardous Waste as an Energy Manager's Issue	15.00
88-316	Household Hazardous Waste Management Planning	15.00
88-312	Summary of Small Business Energy Conservation Programs	15.00
88-310	The Earth-Coupled Heat Pump: Utilizing Innovative Technology in Single Family Rehabilitation	15.00
88-309	Energy Planning for Economic Development	18.00
88-308	Conversion of Resource Recovery Steam to Hot and Chilled Water Systems	10.00
88-306	HVAC Equipment Replacement for Best Size and Efficiency, Transfer Report	15.00
88-305	Cogeneration and Cooling in Small Scale Applications	15.00
88-304	Energy Master Planning: Innovative Design and Energy Analysis Services for New Commercial	22.00
88-303	Energy Efficient Building Design: Guidelines for Local Government	15.00
88-302	Direct Digital Control of Air Washer Cooling System	15.00
88-301	Feasibility Study of Transportation Management Strategies in the Poplar Corridor, Memphis, Tennessee	18.00
87-327	Energy Efficient Urban Cooling Technologies: 1st National Conf.	20.00
87-324	Memphis Area Rideshare	15.00
87-317	Joint City Government/Utility Partnerships to Reduce Business Costs	15.00
87-314	The Impact of Budgetary Incentives on Energy Management	15.00

Publications Price List--UCETF Reports

ITEM #	TITLE	PRICE
87-313	Computer Assisted Control for Municipal Water Systems, Phase II	20.00
87-312	Economic Development Through Energy Technology Transfer	15.00
87-311	Electric Utility Franchise Guide	20.00
87-310	Hidden Link: The Energy and Economic Development, Phase II	15.00
87-307	Municipal Underground Storage Tanks: An Energy Manager's Guide	18.00
87-306	Integrating Energy Efficiency into Mun. Purchasing Decisions	20.00
87-305	Energy Enhancement in New Residential Construction	40.00
87-302	Thermal Energy Storage: Application Guide for Local Governments	20.00
87-301	HVAC Equipment Replacement for Best Size & Efficiency	20.00
86-315	Balancing Single Pipe Steam Heating Systems	20.00
86-314	Inhibition of Respiration in Activated Sludge by High Carbon Dioxide Concentration	7.50
86-313	Water Supply System Energy Conservation Through Computer Control	18.00
86-312	Energy Cost Reduction Through Wastewater Flow Equalization	20.00
86-311	High Efficiency Gas Furnace Modification in Low Income Housing	15.00
86-310	Hidden Link: Energy and Economic Development, Phase I	15.00
86-307	Disposal Techniques with Energy Recovery for Scrapped Vehicle Tires	20.00
86-306	District Heating Marketing: Analysis of a Twelve City Survey	20.00
86-305	Technology Transfer for Residential Energy Programs in New Construction and Existing Housing	15.00
86-304	Technology Transfer for Residential Energy Efficiency	15.00
86-302	Neighborhood Energy Efficiency & Reinvestment	15.00
86-301	On-Site Municipal Fuel Cell Power Plant: Feasibility and Application Guide	15.00
85-326	Resource Recovery for Urban Yard Waste	18.00
85-323	Energy Monitoring and Controlling in Municipal Facilities	10.00
85-320	Transportation Management for Business Relocation	15.00
85-319	District Heating in Denmark	10.00
85-318	Computer-Assisted Control for Municipal Water Systems, Phase I	18.00
85-317	Financing Energy Efficient Housing as a Community Economic Development Tool	15.00
85-316	Modular District Heating Planning as a Development Tool	15.00
85-314	Alternative Techniques for Dev. of Energy Efficient Residences	15.00
85-312	Shared Savings and Low Income Homeowners	18.00
85-311	Measures and Investment Options for Community Energy Conservation	18.00
85-310	Planning for Energy Efficiency in New Commercial Buildings	15.00
85-308	Residential Space Heating with Wood	15.00
85-307	Thermal Storage Strategies for Energy Cost Reduction	18.00
84-325	Shared Savings in the Residential Market	
84-324	Methanol Use in Vehicle Fleet Operations: Barriers	20.00
84-322	Energy Management and Technology for Urban Governments	15.00
84-321	Hydrate Process for Waste Water Treatment Plant Sludge Dewatering	15.00

Publications Price List--UCETF Reports

ITEM #	TITLE	PRICE
84-320	Development of Computerized Inventory and Maintenance System for Municipal Street Lights	15.00
84-315	Facilities Energy Monitoring System	15.00
84-314	Application of Mini-Van Technology to Vanpool Services	18.00
84-312	Implementation Methods for an Integrated Energy System	10.00
84-311	Feasibility of Water-Based District Heating and Cooling	15.00
84-310	Budgetary Incentives for Municipal Energy Management	22.00
84-309	Central Energy Systems Applications to Economic Development	20.00
84-308	On-Site Cogeneration for Office Buildings	15.00
84-306	Analysis of Municipal Bus Operations for the Advancement of Fuel Cell Technology	15.00
84-305	Computer Based Maintenance	15.00
84-304	Innovative Finance Plans for Privately Owned Waste/Vol. 2	15.00
84-303	Innovative Finance Plans for Privately Owned Waste/ Vol. 1	15.00
84-301	Coordinating Preventive Maintenance with Energy Management	15.00
83-319	The Rehabilitation and Retrofit of Older Houses to Superinsulated Standards	15.00
83-318	Developing Sources and Techniques for Alternative Financing of Energy Conservation	20.00
83-316	Hydrate Process for Dewatering Sewage Sludge	10.00
83-315	Financial Planning for District Heating: Brooklyn Navy Yard	15.00
83-314	Memphis Area Rideshare On-Line Information System	18.00
83-313	Renovation Opportunities for Steam District Heating Systems	18.00
83-312	Initial Assessment of District Heating and Cooling	20.00
83-311	Energy Conservation Through Computerized Automation	18.00
83-309	Development of an Energy Park: Issues and Implementation Options	15.00
83-308	Alternative Uses for Digester Methane Gas	25.00
83-307	Innovative Financing and Incentive Package to Reduce Energy	15.00
83-305	Multi-Jurisdictional Planning for District Heating and Cooling	10.00
83-303	Improving Energy Management and Accountability in Municipal Operations	15.00
82-320	Utilization of Felled City Trees as Supplemental Boiler Fuel	7.50
82-319	Methanol Use in Vehicle Fleet Operations: Comparisons	15.00
82-317	Microcomputer Tools for Trans. and Residential Energy Conservation	20.00
82-316	Reduction of Impediments to Alternative Energy Use	20.00
82-315	Reducing Regulatory and Financial Impediments to Energy Conservation	20.00
82-314	Integrating Energy Management with Economic Development	20.00
82-313	Energy Conservation and Economic Development	10.00
82-310	Municipal Technologies	20.00
82-307	Strategies to Improve Community Energy Use Practices	10.00
82-306	Energy Conservation In Water Treatment	
82-305	Development of an Energy Action Plan: Participating Approach	15.00
82-303	Energy Economic Development	20.00

Publications Price List--UCETF Reports

ITEM #	TITLE	PRICE
82-302	Public Housing Energy Efficiency Through Private Financing	10.00
82-300	Developing an Energy Management Tracking System	
81-328	Matching End Use Energy Needs to Source Possibilities	20.00
81-327	Development of a Hydrogen-Fueled Mass Transit Vehicle s	15.00
81-326	Operational and Maintenance Guidelines for Reducing Energy Consumption	
81-324	Energy Management for Small Business	10.00
81-320	Energy Data Gathering, Analysis, and Review System	20.00
81-318	Fuel Management and Planning System for Local Government	25.00
81-316	Production of Ethanol from Cellulosic Fraction	
81-313	Metro-Dade County Comprehensive Energy Emergency Plan	
81-311	Developing Energy Emergency Preparedness	15.00
81-310	Simplified Methodology for Community Energy Management	20.00
81-309	Energy Management: The Public Sector	15.00
81-307	Municipal Technical Assistance-Energy Monitoring	6.00
81-306	New Technology Demonstration	10.00
81-305	Technology Transfer: Unit Report from the Energy Task Force	15.00
81-304	Development of Local Energy Management Preparedness	10.00
81-303	Municipal Energy Management	10.00
80-314	Methodology for Energy Impact Analysis of Urban Development Projects	15.00
80-313	Evaluation of Landfill Gas as an Energy Source	15.00
80-309	Decision Process for the Retrofit of Municipal Buildings	20.00
80-308	Primary Urban Energy Management Planning Methodology	7.50
80-306	Local Government Use of Thermography for Energy	15.00
79-300	Planning for and Purchasing Computer Technology	6.50

END

**DATE
FILMED**

2 / 17 / 93