1 of 1

DECLASSIFIED

RECORD CENTER FILE

SECURITY INFORMATION

DECLASSIFIED

HW-27968

DEL

DECLASSIFIED

WITH DELETIONS

CA 300 Area per 10-1374

By G. S. Schutte 11/1/53

Verified By R. E. Schutte 11/1/53

1. A.B. Greninger
2. R.H. Beaton
3. J.S. McMahon
4. H.A. Carlberg
5. W.K. MacCreedy
6. W.K. Woods
7. W.M. Harty
8. V.D. Nixon
9. T.W. Hauff
10. R.S. Bell
11. C.P. Cabell
12. P.D. Lee
13. O.F. Hill

14. C.E. Reed
15. V.R. Chapman
16. J.L. Boyd/C.E. Kent
17. F.W. Woodfield/R.J. Soat
18. F.A. Hollenbach
19. W.H. Mobley/R.G. Barnes
20. R.E. Smith
21. G.C. Gabler/H.E. Hanthorn
22. V.R. Cooper
23. R.E. Tomlinson
24. C.A. Rohrmann
25. Yellow
26. 700 File

This document consists of
15 pages, ~~MA~~
Series ~~MA~~

May 5, 1953

TO: V.D. Nixon

COPY 1 OF 1, SERIES MA

FROM: C.A. Rohrmann/J.O. Ludlow

Chas. A. Rohrmann
PROCESS W/IFICATIONS 202-S BUILDING

Ref: HW-26030 "Program "X" - Separations Cost", C.A. Rohrmann, 10/23/52.

HW-27010 "Back-Cycling of 2DW-10W to Earlier Cycles as Scrub - 202-S Building", R.G. Barnes/O.C. Schroeder, 2/9/53.

Introduction:

Document HW-26030 presented annual operating costs for a 200 TU/Mo Redox plant. Document HW-27010 proposed a scheme whereby the third and second uranium cycle salt wastes in the Redox plant are combined, stripped, evaporated, and then returned as scrub to the first (and possibly second) cycles as scrub, operating as a dual scrub column.

Purpose:

It is the purpose of this report to study this proposed method of back-cycling, and to investigate other methods of reducing chemical and waste storage costs. The method which appears most desirable will be recommended for inclusion in the Phase II Redox alterations.

RECEIVED
This document contains restricted data as defined in the Atomic Energy Act of 1946. Its transmission outside the scope of its control in any manner is unauthorized. Persons are prohibited from unauthorized disclosure.

SECURITY INFORMATION

300 AREA
CLASSIFIED FILES

DISTRIBUTION RESTRICTED TO U.S. ONLY

DECLASSIFIED

HW-27968

DEL

V.D. Nixon

- 2 -

May 5, 1953

Summary & Conclusions:

COMPARISON OF ALTERNATES

<u>Alternates</u>	<u>Manufacturing Costs Per Year.</u>	<u>Dollar Value over Basic Redox of U and Pu Recovered</u>
Basic 200 TU/Mo Redox.	\$8,080,900	0
Basic Redox / 2 Stage Back-Cycle.	5,811,400	\$243,200
Basic Redox / Pre-Cycle / 2 Stage Back-Cycle.	5,275,100	404,400
Basic 200 TU/Mo Redox - Cribbable.	7,453,900	0
Basic Redox / 2 Stage Back-Cycle - Cribbable.	5,185,500	343,200
Basic Redox / Pre-Cycle / 2 Stage Back-Cycle - Cribbable.	4,615,500	392,200
Basic 200 TU/Mo Redox with Self Concentration.	7,017,900	0
Basic Redox / 2 Stage Back-Cycle with Self Concentration.	4,635,400	343,200
Basic Redox / Pre-Cycle / 2 Stage Back-Cycle with Self Concentration.	4,342,000	404,400
Basic 200 TU/Mo Redox - Cribbable with Self Concentration.	6,140,200	0
Basic Redox / 2 Stage Back-Cycle - Cribbable with Self Concentration.	4,426,400	\$343,200
Basic Redox / Pre-Cycle / 2 Stage Back-Cycle - Cribbable with Self Concentration	4,121,500	392,200

In view of the considerable savings and improved operation achieved by the use of pre-cycle, combined with two stage back-cycling of the uranium salt wastes and cribbing of coating wastes and final plutonium cycle wastes, it is proposed that Phase II Redox alterations be revised in accordance with Figure 4. Provisions should be provided for segregating coating wastes and final plutonium cycle waste for cribbing.

DECLASSIFIED

HW-27968

DEL

V.D. Nixon

- 3 -

May 5, 1953

Discussion:

After receiving HW-27010, consultations by the Separations Section and the Design Section resulted in a decision to modify the back-cycle proposal to provide for 2 stage back-cycling of uranium salt wastes - third cycle returned to second cycle and second cycle returned to the first cycle.

During the preliminary scope design of the Purex plant, the process consisted of one combined decontamination and partition cycle, followed by a separate decontamination cycle each for uranium and plutonium. Further study by the Technical Section resulted in the conclusion that sufficient decontamination to produce specification uranium and plutonium could not be assured using two cycles. As a result, the Technical Section requested that the scope be revised to include a third uranium decontamination cycle and a third plutonium cycle. Study and evaluation by the Design Section resulted in an alternative proposal to install a single complete decontamination cycle for uranium together with plutonium, at the start of the extraction battery, and thus as a result to provide the third cycle for both uranium and plutonium. This was the so-called pre-cycle flowsheet. This proposal accomplished the desires of the Technical Section using only two additional columns instead of the four necessary for separate third cycles. A further saving was realized in that chemicals and waste storage for only one additional cycle were required. This was true, since the chemicals and waste facilities necessary for 16,600# of metal are not increased by including the plutonium along with this mass of uranium in the pre-cycle.

Since it was realized that considerable piping and equipment revisions would have to be made in order to provide facilities for Phase II Redox and ANN back-cycling it was decided to investigate the possibility of making further piping changes in order to gain the benefits of pre-cycle operation.

Basic Redox layout consists of head-end treatment, feed tanks, concentrators, and auxiliaries located in cells in the canyon section of the building. The extraction columns are all located in the silo section of the building. Piping connecting these two sections of the building are via a hot pipe trench. Therefore, a given feed tank can be connected to a different column by making relatively minor changes in piping in the silo.

Investigation of silo lay-out, correlated with the desired process pattern led to the following revised flow pattern.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

~~CONFIDENTIAL~~

HW-27968 DEL

V.D. Nixon

May 5, 1953

The 1AF tank feeds the 1A-1S combination as at present. Organic from the 1A-1S column top is jumpered to the feed point of 2E column. The line from the 2E column is jumpered to the 1CU concentrator. Organic from the 2D column is jumpered to the 1B feed. Aqueous from the 1C column is jumpered to the 2EU concentrator. The 2BP is jumpered to the 3BP receiver with a diversion valve so it can be routed to the 3AF tank if desired. The existing third plutonium cycle thus will not be required for normal processing, but can be used for off-standard operation, thus giving four cycles available for plutonium.

Two stage back-cycling can be provided by routing the III DW to the 1CU concentrator, and routing the II DW and possibly the II AW via the proposed ANN concentrator to the feed to the 1A-1S units.

Figure 1 shows in brief outline form the Basic Redox flow pattern.

Figure II shows the changes in pattern to achieve 2 stage back-cycling.

Figure III shows the changes in pattern to achieve 2 stage back-cycling and operated with pre-cycle.

Figure IV is a rearrangement of Figure III, deleting lines not used, and re-grouping the equipment to clarify the flow pattern.

Other than raw material and waste storage costs, advantages gained include:

- 1) Improved decontamination since two acid deficient cycles and one acid cycle are better than one acid deficient cycle followed by two acid cycles.
- 2) Improved recovery, since all fission products leave from one column. This column can be run for maximum recovery at slight expense of decontamination, and the other "A" type columns run for maximum decontamination at the expense of waste "loss", since these bottoms are recycle and the plutonium and uranium there-in thus automatically recovered.
- 3) Minimization of the effect of minor column upsets, since all except first "A" type column provide for automatic recovery of wastes.
- 4) Liberation of an existing Pu decontamination cycle which can be used in line to provide four cycles for processing off-standard (Pu containing) wastes. Plant practice has indicated that three cycles are not sufficient in some cases to produce specification product. This final cycle can also be available for receiving and processing off specification plutonium through an additional cycle without interruption of plant operation.
- 5) Since this method reduces the waste volume/TU processed, less interruption in plant capacity is occasioned by having to rework production of non-standard wastes.

DECLASSIFIED

HW-27968 DEL

V.D. Nixon

- 5 -

May 5, 1953

Table I, column I, lists manufacturing costs for the basic 200 TU/Mo Redox plant, wherein raw material costs and waste volumes are based on information secured from the Separations Section, labor costs are based on the best estimate available by consultation with Separations Section, and the balance of the costs as given in HW-26030. Values used for labor and other fixed charges are constant for all alternates studied, and thus do not effect the savings possible. They are included so that savings may be evaluated as per cent of basic Redox costs.

Column 2 lists the costs for the basic 200 TU/Mo Redox plant as revised for two stage back-cycle.

Column 3 lists the cost for the basic 200 TU/Mo Redox plant as revised for pre-cycle and two stage back-cycle.

Consultation with the Separations Section and with Radiological Sciences has indicated the possibility that coating waste can be cribbed, since it has negligible content of long lived fission products. Study by the Design Section has resulted in the conclusion that, if coating waste can be cribbed, final Plutonium Cycle salt waste can probably also be cribbed. Radiological Sciences is currently conducting tests to verify these possibilities. Final Plutonium Cycle wastes can be segregated and routed to crib by utilization of the spare sump drain header.

Table II lists costs of the three alternate methods of operation if the coating waste and the final Plutonium Cycle wastes are cribbed.

Experiences in operation of the Redox Plant and numerous calculations indicate that the waste storage tanks will boil for a considerable period of time. In order to provide storage for wastes at Phase II rates, 241-SX tank farm has been authorized and is in process of detailed design. The flow pattern as designed will allow the condensate collected from the boiling tanks to be cribbed, thus providing self concentration of the wastes.

Document HW-23477 "Heat Generation in Stored Redox Wastes" by J.S. Kane and R.E. Burns gives the heat liberation from fission product activity/TU as a function of time after discharge from the reactor.

These figures were used to provide plots of heat liberation versus time in a 750,000 Gal. tank for several methods of operation of the Redox Plant. These plots were then integrated to provide gallons evaporated. Test data indicating that Redox Wastes of present concentration can still be handled satisfactorily if reduced to $\frac{1}{4}$ volume are also given.

The tank heat evolution curves plotted in HW-23477 are not directly applicable to the costs now being studied in the following aspects:

- 1) Plant operation rate is different.
- 2) Quantity of waste/TU is different.
- 3) 241-SX tanks are 1,000,000 Gal. each, tanks used in document were 750,000 Gal. each.

DECLASSIFIED

HW-27968 DEL

V.D. Nixon

- 6 -

May 5, 1953

In view of the above it was decided to use the basic heat content for sixty day old wastes as given in HW-23477, and apply their method in determining heat evolution, but to use 1,000,000 Gal. storage tanks, 200 TU/Mo processing rate, and the waste volumes/TU as calculated for the three alternates used in Table I, and as revised for use in Table II. As a limiting case in volume reduction, 1/3 the volume before concentration was used. This is conservative since test experiments quoted in HW-23477 indicate that a reduction to $\frac{1}{3}$ volume is feasible, if heat is available.

Table III lists the waste volume in gallons/TU processed used in Table I and II (without concentration) and also lists the volume following concentration. Those cases where more heat is available than is required to concentrated to 1/3 volume are marked with an asterisk and the volumes shown is 1/3 the original volume.

Table III also gives the time in months before the 15,000,000 Gal. of storage provided by 241-SX tank farm will be filled for each case.

Tables IV and V list the costs of the alternates shown in Tables I and II, but allow for self concentration of wastes to the degree shown in Table III.

DECLASSIFIED

HW-27968

DEL

V.D. Nixon

- 7 -

May 5, 1953

Table I

ANNUAL COSTS OF REDOX SEPARATIONS

	<u>Basic 200 TU/Mo Redox</u>	<u>Basic Redox / 2 Stage Pack-Cycle</u>	<u>Basic Redox / Pre- Cycle / 2 Stage Back- Cycle.</u>
Direct Material	\$1,797,400	\$1,065,400	\$ 893,000
Labor	890,000	890,000	890,000
IME	150,000	150,000	150,000
Waste Storage (@ 40¢/gal)	<u>3,302,000</u>	<u>1,764,500</u>	<u>1,400,600</u>
Total Within Division	6,139,400	3,869,900	3,333,600
Outside Division Costs	1,941,500	1,941,500	1,941,500
Manufacturing Costs for processing 200 TU/Mo	8,080,900	5,811,400	5,275,100
Reduction in Manuf. Cost below Basic Redox Cost for processing 200 TU/Mo	0	<u>8,080,900</u> <u>5,811,400</u> 2,269,500	<u>8,080,900</u> <u>5,275,100</u> 2,805,800
Dollar Value over Basic Redox Cost for processing 200 TU/Mo	0	<u>343,200</u>	<u>104,400</u>
Total Net Reduction		\$2,612,700	\$3,211,200

V.D. Nixon

- 11 -

May 5, 1953

HW-27968

DEL

DECLASSIFIED

Table V

WITH DELETIONS

ANNUAL COSTS OF REDOX SEPARATIONS

	Basic 200 TU/Mo Redox - Cribbable with Self Concentra- tion.	Basic Redox / 2 Stage Back-Cycle - Cribbable with Self Concentration	Basic Redox / Pre- Cycle / 2 Stage Back- Cycle - Cribbable with Self Concentration.
Direct Material	\$1,797,400	\$1,065,400	\$ 893,000
Labor	890,000	890,000	890,000
IME	150,000	150,000	150,000
Waste Storage (@ 40¢/gal)	<u>1,361,300</u>	<u>379,500</u>	<u>247,000</u>
Total Within Division	4,198,700	2,484,900	2,180,000
Outside Division Costs	1,941,500	1,941,500	1,941,500
Manufacturing Costs for processing 200 TU/Mo	6,140,200	4,426,400	4,121,500
Reduction in Manuf. Cost below Basic Redox Cost	8,080,900	8,080,900	8,080,900
	<u>6,140,200</u>	<u>4,426,400</u>	<u>4,121,500</u>
for processing 200 TU/Mo	1,940,700	3,654,500	3,959,400

V.D. Nixon

- 10 -

May 5, 1953

HM-27968

DEL.

DECLASSIFIED
WITH DELETIONS

Table IV

ANNUAL COSTS OF REDOX SEPARATIONS

	Basic 200 TU/Mo Redox with Self Concentration	Basic Redox / 2 Stage Back-Cycle with Self Concen.	Basic Redox / Pre- Cycle / 2 Stage Back- Cycle with Self Concen.
Direct Material	\$1,797,400	\$1,065,400	\$ 893,000
Labor	890,000	890,000	890,000
IME	150,000	150,000	150,000
Waste Storage (@ 40¢/gal)	<u>2,239,000</u>	<u>588,500</u>	<u>467,500</u>
Total Within Division	5,075,400	2,693,900	2,391,500
Outside Division Costs	<u>1,941,500</u>	<u>1,941,500</u>	<u>1,941,500</u>
Manufacturing Costs for processing 200 TU/Mo	7,017,900	4,635,400	4,342,000
Reduction in Manuf. Cost below Basic Redox Cost for processing 200 TU/Mo	8,080,900 <u>7,017,900</u> 963,000	8,080,900 <u>4,635,400</u> 3,445,500	8,080,900 <u>4,342,000</u> 3,738,900

DECLASSIFIED

HW-27968

DEL

V.D. Nixon

- 8 -

May 5, 1953

DECLASSIFIED
WITH DELETIONS

Table II

ANNUAL COSTS OF REDOX SEPARATIONS

	Basic 200 TU/Mo Redox - Cribbable	Basic Redox / 2 Stage Back-Cycle - Cribbable	Basic Redox / Pre- Cycle / 2 Stage Back- Cycle - Cribbable
Direct Material	\$1,797,400	\$1,065,400	\$ 893,000
Labor	890,000	890,000	890,000
IME	150,000	150,000	150,000
Waste Storage (@ 40¢/gal)	<u>2,675,000</u>	<u>1,138,600</u>	<u>771,000</u>
Total Within Division	\$5,512,400	3,244,000	2,574,000
Outside Division Costs	1,941,500	1,941,500	1,941,500
Manufacturing Costs for processing 200 TU/Mo	7,453,900	5,185,500	4,615,500
Reduction in Manuf. Cost below Basic Redox Cost for processing 200 TU/Mo	<u>8,080,900</u> <u>7,453,900</u> 627,000	<u>8,080,900</u> <u>5,185,500</u> 2,895,400	<u>8,080,900</u> <u>4,615,500</u> 3,465,500

FIGURE 1

PHASE II
REDOX
SAIC FLOW SHEET

44-27762

DECLASSIFIED

TWO-STAGE
BACK CYCLE

2
11
11
11
11
11

Ed-27-903

DEL

DECLASSIFIED

DATE

FILMED

1 / 6 / 94

END