ORNL/M--1851

X-OE-554

**OAK RIDGE
NATIONAL
LABORATORY**

MARTIN MARIETTA

**Functional Requirements for the
Liquid Waste Transfer and
Distribution Station at Waste Area
Grouping 6 at Oak Ridge National
Laboratory, Oak Ridge, Tennessee**

**MANAGED BY
MARTIN MARIETTA ENERGY SYSTEMS, INC.
FOR THE UNITED STATES
DEPARTMENT OF ENERGY**

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

**Gilbert/Commonwealth, Inc.
Knoxville, Tennessee**

contributed to the preparation of this document and should not be considered an eligible contractor for its review.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from 615-576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

MARTIN MARIETTA ENERGY SYSTEMS, INC.

OAK RIDGE, TN - PADUCAH, KY

ENGINEERING TRANSMITTAL

PAGE 2 of 2

PROJECT TITLE	PROJECT NO.	E.S.O. (W.O.) NO.
Waste Area Grouping 6 Closure		PKX823
JOB TITLE	BUILDING	
	SWSA 6	

ORNL/M--1851

DE92 005309

Well Plugging & Abandonment

D. D. Huff	3504	6317
J. A. Greene	70788	6402
W. K. McMaster	1503	6352
A. S. Will	TriCity	7606
C. K. Valentine	6026C	6395
E. D. Wright	6026	6395
T. L. Ashwood	1505	6036
R. O. Kennard	3504	6317
T. O. Early	1505	6038
T. Grizzard	1506	6034
F. E. Meyer	4500S	6102
C. S. Haase	1503	6353
M. Wilson	DOE	
G. Bodenastein	DOE	
A. J. Kuhaida	TriCity	7606

Monitoring Sta. No. 3 Upgrade

P. M. Craig	ECE	
R. B. Clapp	1505	6036
C. K. Valentine	6026C	6395
J. L. Gray	3001	6029
D. D. Huff	3504	6317

WAG 6 Leachate Transfer & Distribution Station

M. Tulay	Gilbert/Commonwealth	
C. K. Valentine	6026C	6395
T. E. Kent	3017	6044
S. M. Robinson	3017	6044
D. J. Peterson	3130	6058
C. B. Scott	3130	6058
S. T. Rudell	3042	6060
J. L. Steller	1000	6338
W. E. Miller	K1550E	7233
P. Craig	ECE	
R. B. Clapp	1505	6036

Well P&A Support Facilities

M. Tulay	Gilbert/Commonwealth	
J. F. Alexander	3546	6011
D. D. Huff	3504	6317
J. A. Greene	70788	6402
W. K. McMaster	1503	6352
A. S. Will	TriCity	7606
C. K. Valentine	6026C	6395
E. D. Wright	6026	6395
T. L. Ashwood	1505	6036
R. O. Kennard	3504	6317
T. O. Early	1505	6038
T. Grizzard	1506	6034
F. E. Meyer	4500S	6102
C. S. Haase	1503	6353
M. Wilson	DOE	
G. Bodenastein	DOE	
A. J. Kuhaida	TriCity	7606

WAG 6 Borrow Site Development
Add TVA Powerline Relocation

C. B. Scott	3130	6058
C. Oaks	Gilbert/Commonwealth	
J. G. Rogers	1001	7155
J. M. Loar	1505	6036
P. D. Parr	1505	6038
R. C. Kroodama	1505	6038
R. P. Nicholson	FOB	
S. V. Keye	4500S	6124
B. A. Berven	7509	6383
J. B. Richard	7962	6391
S. R. McNeary	4500N	6252
W. W. Teer	9711-1	MS1
R. L. Stover	7947	6393
D. Kendall	MTI	
R. Roop	Labot	
S. Sarter	Labot	
J. Hughie	K1550E	7233
L. Degenhardt	1000	6334

Tumulus Cover

T. J. Pierce	K1550E	7234
T. A. Fontaine	1505	6038
R. B. Clapp	1505	6038

Technical Review Team

L. H. Stinson	1000	6342
W. D. Barton	1550	7233
T. B. Hale	1035	7209
B. P. Spalding	1505	6036
S. Garland	70788	6402
S. D. Van Hoesen	1000	6338
J. Frost	Lee Wan	
D. Allen	Lee Wan	
D. Roop	Labot	

Originated By	Section (Group)	Division (Department)	Principal Engineer	Project Engr. (Manager)
S. L. Laman	S. D. Van Hoesen	E. H. Krieg, Jr.	A. G. Oaks	S. L. Laman

UCN-1201 (12358C 1-88)

MARTIN MARIETTA ENERGY SYSTEMS, INC.

OAK RIDGE, TN - PADUCAH, KY

ENGINEERING TRANSMITTAL

AM/L NO.

WAG-6 057

ISSUE DATE

11/18/91

PROCUREMENT BY

FIELD WORK BY

PROJECT TITLE

Waste Area Grouping 6 Closure

PROJECT NO.

E.S.O. (W.O.) NO.

PKX823

JOB TITLE

BUILDING

SWSA 6

PLANT

ORNL

DISTRIBUTION

QUANTITIES

FUNCTION	NAME	BLDG.	Mail Stop	Xmtl	Dwg. Red/Full	B/M	D/S Spec	*	ISSUE FOR:		
									☐ Info/Record	☐ Comment	☐ Approval
Project Manager (PM)	S. D. Van Hoesen	1000	6338	1					☐ Approved	☐ CFC	☐ Design Comp.
Principal Engr. (PE)	A. G. Oaks	1550C	7233	1					Return Comments To _____ By (Date) _____		
Project Engr. (PJ)	S. L. Laman	1000	6338	1					LIST OF ATTACHMENTS & INFORMATION ☒ RC ☐ NoRC		
Plant Div. Rep.	S. B. Garland	7078A	6402	1							
	R. W. Morrow	1000	6338	1					PAGE 1 OF 2		
Constr. Engr. (CE)	R. B. Knott	2647	6319	1					Functional Requirements for the Liquid Waste Transfer and Distribution Station at Oak Ridge National Laboratory Oak Ridge, Tennessee		
	J. R. Lawson	1000	6338	1							
Est./Sch. Engr. (ES)	K. P. Rice	K1550J	7234	1							
	W. W. Thompson	1330	7298								
	D. W. Swindle	1330	7298								
	W. E. Manrod	K1550E	7233	1							
QA Specialist	M. A. Woody	1000	6338	1							
	K. W. Cook	3001	6029								
	N. W. Durfee	1330	7298								
Struct. & Architect.	R. M. Collins	K1550B	7231	1							
System Eng.	D. G. Miller	1000	6337	1							
System Safety Eng.	C. K. Ford	1000	6333	1							
Electrical Engrg.	M. V. Shamblin	1000	6334	1							
Engrg. Mechanics	B. G. Shockley	9733-2	8031	1							
Environ. Control	S. O. Santich	9733-1	8029	1							
	H. Clem	3550	6291	1							
Instrument Engrg.	J. R. Mathis	1000	6334	1							
	S. Yeung	EBASCO		1							
	A. N. Wylie	K1550E	7233	1							
	J. A. Hall	3550	6291	1							
	L. C. Cox	1000	6338	1							
	J. Kubarewicz	CH2MHILL		1							
	D. L. Garrett	1000	6338	1							
	R. Wilson	CH2MHILL		1							
	J. Frost	Lee Van		1							
Environ. Protection	F. C. Kornegay	4500N	6198	1							
Fire Protection	R. L. Atchley	2500	6307	1							
Health Physics	R. L. Jeffers	2652B	6290	1							
Industrial Hygiene	K. F. Edwards	3550	6292	1							
Utilities	G. W. Oliphant	2518	6323	1							
	T. F. Scanlan	3047	6023	1							
Safety	M. W. Kohring	4500N	6256	1							
Security	F. J. Graziano	3037	6016	1							
Test & Inspection	P. B. Burn	2000	6053	1							
Maintenance	S. R. Larkins	2518	6328	1							
	K. G. Greer	6026	6395	1							
	B. Piper	3001	6029	1							
	B. Bartenbus	4500N	6200	1							
DOE - ORO	S. Riddle	FOB	2116	1							
	G. Hudson	FOB	2219	1							
	M. Belvin	4500N	6269	1							
Retain PUF	S. L. Laman	1000	6338	1							
Engineering Services	D. K. Stair	1000	6331	2							
TOTALS				57							

RECEIVING INSPECTION REQUIRED

☐ (1) Routine ☐ (2) Special

Refer Technical Questions

To:

Phone:

If company, list responsible group, e.g., Engineering, Maintenance, others. Explain above.

Return originals to _____

☐ Add disclaimer and substitute clauses.

Originated By

S. L. Laman

Section (Group)

S. D. Van Hoesen

Division (Department)

E. H. Krieg, Jr.

Principal Engineer

A. G. Oaks

Project Engr. (Manager)

S. L. Laman *SL*

UCN-1201 (12356C 1-88)

Environmental Restoration Division
ORNL Environmental Restoration Program

**Functional Requirements for the Liquid Waste Transfer and
Distribution Station at Waste Area Grouping 6
at Oak Ridge National Laboratory,
Oak Ridge, Tennessee**

Date Issued—August 1991

Prepared by
Engineering Division
Martin Martin Energy Systems, Inc.

Prepared for
U.S. Department of Energy
Office of Environmental Restoration and Waste Management
under budget and reporting code EW 20

OAK RIDGE NATIONAL LABORATORY
Oak Ridge, Tennessee 37831-6285
managed by
MARTIN MARIETTA ENERGY SYSTEMS, INC.
for the
U.S. DEPARTMENT OF ENERGY
under contract DE-AC05-84OR21400

MASTER

APPROVALS

Functional Requirements for the Liquid Waste Transfer and Distribution Station
at Waste Area Grouping 6 at Oak Ridge National Laboratory,
Oak Ridge, Tennessee

M. P. Tulay (Preparer)

8-27-91

Date

S. L. Laman (Reviewer)

8/30/91

Date

M. W. Kohring (Reviewer)

8-10-14-91

Date

R. L. Mlekodaj (Reviewer)

10/24/91

Date

D. L. Kirby (Reviewer)

9-3-91

Date

F. C. Kornegay (Reviewer)

10/15/91

Date

T. F. Scanlan (Reviewer)

11/15/91

Date

M. A. Woody (Reviewer)

10/24/91

Date

S. D. Van Hoesen

11/18/91

Date

S. B. Garland II

11/15/91

Date

CONTENTS

EXECUTIVE SUMMARY	v
1. INTRODUCTION AND PURPOSE	1
1.1 BACKGROUND	1
1.2 PURPOSE	1
2. PROJECT DEFINITION	2
3. MISSION	4
4. REQUIREMENTS AND SPECIAL ISSUES	6
4.1 REQUIREMENTS AND SPECIAL CONSTRAINTS	6
4.1.1 General Functional Requirements	6
4.1.2 WAG 6 Liquid Waste Transfer and Distribution Station	7
4.2 UNCERTAINTIES	8
4.2.1 Location	8
4.2.2 Waste Generation	8
4.2.3 Other Types of Wastes	9
4.3 INTERFACES AND INTERFACE REQUIREMENTS	9
4.4 SPECIAL ANALYSES	9
4.5 HUMAN FACTORS	10
4.6 MAINTENANCE ISSUES	10
4.7 CRITICAL SYSTEMS	10
4.8 TESTING REQUIREMENTS	10
5. CONFIGURATION CONTROL PLAN	11
BIBLIOGRAPHY	12

EXECUTIVE SUMMARY

A new facility will be constructed near the Bethel Valley storage tanks to receive process waste liquids generated by Oak Ridge National Laboratory during closure activities at Waste Area Grouping 6. The facility will unload trucks and distribute the liquid waste to other treatment facilities. It will be able to handle eight 5000-gal transfers per 8-h shift. No waste categorized as Resource Conservation and Recovery Act or liquid low-level is expected, but if such waste is encountered, it will cause transfer rate restrictions.

1. INTRODUCTION AND PURPOSE

1.1 BACKGROUND

In 1969 Oak Ridge National Laboratory (ORNL) began placing solid waste in Solid Waste Storage Area (SWSA) 6. The waste included radioactive, suspect radioactive, and hazardous waste materials. SWSA 6 has now been incorporated into Waste Area Grouping (WAG) 6, which includes the nearby Emergency Waste Basin and Explosives Detonation Trench. Currently, the Environmental Protection Agency Region IV (hereafter referred to as EPA), the Tennessee Department of Environment and Conservation (TDEC), the Department of Energy (DOE), and Martin Marietta Energy Systems (Energy Systems) are developing a Closure Plan with a target date of 1997 to complete closure activities. Because of the nature of the waste products at SWSA 6, regulations promulgated by the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA), the Resource Conservation and Recovery Act (RCRA), and others must be integrated into the Closure Plan.

To date, several likely closure scenarios have been identified. Closure is expected to include plugging and abandonment (P&A) of unneeded research wells and boreholes. Liquids will likely need to be removed from trenches prior to stabilization by grout injection and/or dynamic compaction. Additionally, interceptor ditches (french drains) may be installed upgradient of the WAG 6 burial trenches to divert surface water around the trenches, thus minimizing leaching of contaminated fluids through them.

It is recognized that contaminated solid and liquid waste will be generated during P&A, installation of interceptor ditches, and other activities. Both solid and liquid waste materials will likely be collected in storage drums and tanks and analyzed. Once characterized, the liquid waste will be transferred to appropriate ORNL facilities for treatment. Several MC312 tanker trucks will be needed to transport the liquid waste to these facilities. A WAG 6 Liquid Waste Transfer and Distribution Station (hereafter referred to as the facility) will be needed to provide a means to transfer and distribute liquid waste from the tankers to the appropriate facilities, including the Nonradiological Wastewater Treatment Plant (NRWTP) and the Process Waste Treatment Plant (PWTP).

1.2 PURPOSE

The purpose of this project is to construct a liquid wastewater receiving station to transfer and distribute the liquids generated during well P&A and other closure activities. During P&A activities, waste in the form of soil, grout, water, and well casings will be generated. The wastewater, equipment cleaning solutions, and/or leachate will be held in SWSA 6 and analyzed for contamination prior to being transferred by MC312 tanker trucks for treatment. A transfer and unloading station is required so that these trucks can be unloaded and the wastewater distributed to the appropriate treatment facility. In general, the facility must provide for the safe and contained unloading of liquid waste from MC312 tanker trucks, ensuring no runoff to adjacent areas.

2. PROJECT DEFINITION

This project consists of one new facility. Figure 1 is a plot plan depicting the general location of the new facility, the tanker truck route from SWSA 6, and the NRWTP. The selection of a potential construction site is discussed in Sect. 4.2.1.

3. MISSION

The mission of the project is to provide a facility to safely and efficiently transfer and distribute liquids generated during closure activities to the appropriate treatment facility. The facility will be designed to provide long-range support in connection with the closure of WAG 6. The organization of the Project Team is provided in Fig. 2.

FIGURE 2
WAG #6
PROJECT IMPLEMENTATION ORGANIZATION

4. REQUIREMENTS AND SPECIAL ISSUES

4.1 REQUIREMENTS AND SPECIAL CONSTRAINTS

4.1.1 General Functional Requirements

The facility must be capable of safely unloading liquids already designated as process waste from MC312 tanker trucks. During P&A and other closure activities, the wastewater generated is anticipated to be suitable for distribution to either the PWTP or the NRWTP. Tanker trucks transporting nonradiological wastewater are anticipated to unload at the NRWTP.

It is highly unlikely that any wastewater would be classified as liquid low-level waste (LLW). It is, however, possible that analysis of the wastewater could reveal the presence of toluene, a RCRA-listed waste. If this occurs, the flow rate and concentration limits discussed in Sect. 4.2.3 will be applied.

Provisions will be incorporated into the procedures, design, and operation of this and other SWSA 6 facilities to ensure that the liquids encountered are transferred to the correct station for unloading and distribution.

The facility will be designed to unload one tanker truck at a time. Based on the rate at which liquid waste is anticipated to be generated during P&A and closure activities in SWSA 6, along with the holding capacity anticipated within SWSA 6, the facility should be capable of performing a maximum of eight transfers in an 8-h shift. It should be noted that this rate of transfer may exceed the capacity of the overall waste treatment system, but this facility should not limit transfers.

The site targeted for the facility (see Fig. 1) is near the existing Bethel Valley Collection Tanks (BVCT), which may contain low-level radioactive contamination. The possible presence of buried organics may have decreased the strength of the soil. Therefore, depending on the results of soil analysis, the architect-engineer will decide if a turn-down slab or a deep foundation (piles) will be necessary. In either case, extraordinary efforts will be taken during the design and planning phases to ensure that minimal solid waste (i.e., soil) is generated during the construction of the proposed facility.

The design will ensure that the facility can readily be cleaned daily to remove contamination. Provisions to ensure that no residual material becomes airborne will be incorporated into the design.

The facility will be furnished with the services and utilities (e.g., electrical power, water, and sewer) needed to support operations on a continuous basis. The facility will be designed to provide 20 years of continuous service. The presence of hazardous materials will be communicated to personnel by means of signs, training, etc., in accordance with the requirements of 29 CFR 1926.59. The ventilation and illumination of the facility will be adequate for expected operations.

4.1.2 WAG 6 Liquid Waste Transfer and Distribution Station

The facility will be capable of safely unloading process liquid waste from the bottom valving on the MC312 tanker trucks. The facility must contain the spillage of all liquids by means of a diked pad that complies with current Energy Systems diking requirements. The pad will be coated to prevent the seepage of liquid waste into the concrete, and the coating will be contamination resistant. The pad will also be sloped to direct any spilled leachate into a sump, the contents of which will be pumped to the ORNL process waste stream. The pad will be capable of supporting a fully loaded 5000-gal MC312 tanker truck along with the mechanical equipment described herein. The sump will be equipped with a conductivity probe with local and remote alarms.

A centrifugal pump (with redundant system) will be provided to pump the liquid waste from both the tanker trucks and the sump through transfer piping into either of the existing BVCTs. The pumps' control will be equipped with pump on/off push button switches and pilot lights. An interlock will be provided to insure no transfer with can occur with a high level alarm.

A roof over the facility will prevent the entry of rainwater onto the diked pad. To allow for the dispersion of exhaust fumes from the trucks and for ventilation, the facility will not be totally enclosed.

Potable water will be supplied at a rate of 50 gal/min. The water will be needed for rinsing the inside of the tanks after each transfer of liquid waste, for hosing the surface of the diked pad, for cleaning general equipment, and for use by personnel.

The flow of personnel entering and leaving the area will be controlled, and the facility will be enclosed with a security fence. An estimated maximum of three people will occupy the facility at any given time.

The facility must have the capability of identifying badges of all personnel entering and leaving the facility at the maximum rate of one badge every 15 sec. The badge identification system need only be capable of reading one badge at a time. Telecommunications will be available to personnel within or near the enclosed area.

The facility must also be capable of securely controlling the approach, access, and egress of each MC312 tanker truck. The vehicle gate will be large enough to allow passage of fire-fighting equipment. An adequate supply of water for fire protection will be provided.

The facility must be capable of ensuring that all personnel and the exterior surfaces of vehicles entering and leaving the enclosed area meet acceptable levels of radioactive contamination. To that end, the facility will have portable instruments capable of detecting any contamination. The facility will also have an emergency shower and eyewash station in case someone becomes contaminated. Acceptable radiation limits will be in accordance with DOE Order 5480.1A, and measures for personnel will be in accordance with applicable ORNL Health Physics procedures.

Provisions for a local toilet facility or for transporting personnel to an existing toilet facility will be included.

Pneumatic valves will be used operable from a local control system panel. The pump motor starters should be installed in a local control system panel.

A new fire hydrant will be installed near the station.

4.2 UNCERTAINTIES

4.2.1 Location

The preferred location for the WAG 6 Liquid Waste Transfer and Distribution Station is in the vicinity of the Bethel Valley storage tanks. This facility will transfer only liquids already identified as ORNL process waste for future distribution to the PWTP. Thus, if this location is selected, the facility need not be capable of transferring nonradiological leachate because such wastewater would be unloaded at the existing transfer station at the NRWTP.

The merit of building the facility at the proposed location was evaluated along with a number of alternatives during the initial stages of this project. The alternatives evaluated, but not chosen, are listed here.

1. Integrate the WAG 6 Liquid Waste Transfer and Distribution Station into the proposed Leachate Treatment Facility to be constructed near the NRWTP.
2. Modify, if necessary, the existing NRWTP pump unloading station to allow distribution of both nonradiological and process wastes to either the NRWTP or the PWTP, respectively.
3. Build a new transfer station only for process waste. This would entail a small facility for pumping into an existing manhole for ORNL process piping. Nonradiological waste would be transferred through use of the existing station.
4. Use existing Bethel Valley storage tanks for holding process waste transferred from tanker trucks. Nonradiological waste would be transferred through use of the existing station.

4.2.2 Waste Generation

The amount and rate of liquid waste generation can only be approximated at this time. An estimated 25 linear ft/day of well per rig can be expected to be removed, requiring about 600–700 gal of water. An additional 150 gal of water already in each well will also be removed. Examination of P&A activities at the Oak Ridge Y-12 Plant will provide additional information regarding the amount of liquid waste and its rate of generation during well P&A activities.

With an estimated four rigs plugging wells each day, approximately 3400 gal of liquid waste would be generated daily in WAG 6. An additional 200–300 gal of drill rig wash water will also contribute to the total amount of liquid waste being generated daily.

A final contributor to the WAG 6 liquid waste stream may be leachate from trenches, which could add up to another 700 gal per 8-h shift. The results of liquid waste analysis, WAG 6 holding capacity, and the management of waste concentrations will determine the rate at which tanker trucks are dispensed from WAG 6 to transfer, unload, and distribute the

liquids. The capability to unload eight trucks per day at the new facility was conservatively based on these expected generation rates.

4.2.3 Other Types of Wastes

As discussed previously, it is uncertain to what extent RCRA wastes or low-level wastes will be encountered once analysis commences on the liquid waste generated from P&A activities. RCRA 261.3 regulations stipulate that if the feed to the treatment facility contains less than 1 ppm and 25 ppm of the spent solvents specified in exemptions A and B, respectively, then the wastewater is non-RCRA and the resulting sludge would not be a liquid waste. Analysis of SWSA 6 data reveals that the *maximum* concentration of exemption A spent solvents was 0.04 ppm. Toluene is the only spent solvent that would significantly contribute to the level of exemption B spent solvents. The maximum concentration of toluene is 150 ppm, and the average concentration is 11 ppm.

Calculations have been performed to determine the rate at which WAG 6 liquid waste could be transferred to the system to stay within the RCRA regulations. Based on the most conservative assumptions of a minimum flowrate into the PWTP of 145,000 gal/day and the maximum concentration of spent solvents (160 ppm) observed in the WAG 6 data, 3000 gal/day could be discharged to the PWTP without exceeding 10 ppm in the headwaters. If 3000 gal/day of WAG 6 wastewater containing the average concentration of contaminants were discharged to the PWTP under average PWTP operating conditions, the headwaters would contain only 0.5 ppm of spent solvents.

A small number of samples (9 of 46) exceeded the PWTP waste acceptance criteria for alpha and/or beta contamination. However, at 3000 gal/day or less, these concentrations should not cause a violation of DOE Order 5400.5 derived concentration guide limits at the NRWTP discharge point.

4.3 INTERFACES AND INTERFACE REQUIREMENTS

The electrical power, potable water, alarms, and telecommunications requirements necessary to support operation of the facility are discussed in Sect. 4.1.

The sump high level alarm will be tied into the distributed control system at the Non Rad Waste Treatment Facility.

An interface exists between this task and the overall Environmental Restoration (ER) Program. This task will support the ER Program. Interfaces also exist between the task and the ORNL Ground Water Manager and ORNL Waste Operations.

4.4 SPECIAL ANALYSES

A safety assessment, a risk assessment plan, a quality assurance plan, and an internal environmental assessment will be prepared by Energy Systems for this project.

4.5 HUMAN FACTORS

Standard design practice for facilities of this type will be adequate. Electrical outlets near the diked pad, sump, eyewash station, emergency shower, and other water sources will be furnished with ground-fault interrupters.

4.6 MAINTENANCE ISSUES

Equipment requiring operator actions or maintenance will be accessible within the enclosed area for those purposes. Equipment requiring maintenance outside the facility will be cleaned before it is removed from the enclosed area.

4.7 CRITICAL SYSTEMS

No critical systems are associated with this project.

4.8 TESTING REQUIREMENTS

Before the facility is operated or occupied, Engineering will test the function of the following systems according to the current functional testing requirements: pumps; telecommunications; electrical power; heating, ventilation, and air conditioning; lighting; alarms; and potable water (including the emergency shower and the eyewash station). All testing and test results will be documented and provided to the ER Division for review. All problems and deficiencies encountered during testing will be corrected by Engineering. Retesting will be performed and documented by Engineering to verify correction.

5. CONFIGURATION CONTROL PLAN

All changes to the approved design will be reviewed and approved by the ER Program Project Manager and reviewed by ER Division to ensure that the proposed changes do not conflict with the requirements of this document as reflected in the design basis of the facility.

7. BIBLIOGRAPHY

Oak Ridge National Laboratory. 1988. Closure Plan for Solid Waste Storage Area 6 ORNL/RAP/Sub-87/99053/9TV1/R1 Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Oak Ridge National Laboratory. 1988. Health, Safety, and Environmental Protection Procedure for Excavated Operations. ORNL/M-116/R1. Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Oak Ridge National Laboratory. 1990. Corrective Action Plan in Response to Tiger Team Assessment. ORNL-6657 Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Oak Ridge National Laboratory, 1991. Functional Requirements for the Support Facilities to Plug and Abandon Wells at SWSA 6, ORNL. FRD-92-(later). Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Oak Ridge National Laboratory, 1991. Summary of Chemical Analysis of WAG 6 Groundwater Samples (Draft). Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Mortimore, J. 1988. Groundwater Quality Monitoring Well Installation - WAG 6. ORNL/RAP-44. Oak Ridge National Laboratory, Oak Ridge, Tennessee.

END

**DATE
FILMED**

2 / 26 / 92