TEST AREA FOR REMEDIAL ACTIONS (TARA)
SITE CHARACTERIZATION AND DYNAMIC COMPACTION
OF LOW-LEVEL RADIOACTIVE WASTE TRENCHES
FY 1988 PROGRESS REPORT

E. C. Davis
B. P. Spalding
S. Y. Lee
L. K. Hyder

Environmental Sciences Division
Oak Ridge National Laboratory

Date of Issue - January 1989

Prepared for the
Office of Defense Waste and Transportation Management

Prepared by the
OAK RIDGE NATIONAL LABORATORY
Oak Ridge, Tennessee 37831-6285
operated by
MARTIN MARIETTA ENERGY SYSTEMS, INC.
for the
U.S. Department of Energy
under contract DE-AC05-84OR21400

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615) 576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

NTIS price codes—Printed Copy: A10 Microfiche A01

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

TEST AREA FOR REMEDIAL ACTIONS (TARA)
SITE CHARACTERIZATION AND DYNAMIC COMPACTION
OF LOW-LEVEL RADIOACTIVE WASTE TRENCHES
FY 1988 PROGRESS REPORT

E. C. Davis
B. P. Spalding
S. Y. Lee
L. K. Hyder

Environmental Sciences Division
Oak Ridge National Laboratory

Date of Issue - January 1989

Prepared for the
Office of Defense Waste and Transportation Management

Prepared by the
OAK RIDGE NATIONAL LABORATORY
Oak Ridge, Tennessee 37831-6285
operated by
MARTIN MARIETTA ENERGY SYSTEMS, INC.
for the
U.S. Department of Energy
under contract DE-AC05-84OR21400

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

CONTENTS

	<u>Page</u>
LIST OF TABLES.....	iii
LIST OF FIGURES.....	vii
SUMMARY.....	1
I. INTRODUCTION.....	3
Background.....	3
Purpose and Objectives.....	5
Site Selection.....	5
Project Documentation.....	8
II. SITE CHARACTERIZATION.....	9
Waste Records Search.....	9
Monitoring Well Installation.....	11
Water Level Measurements.....	14
Groundwater Sampling.....	22
Precompaction Nonstandard Trench Penetration Tests.....	36
Standard Soil Penetration Tests and Soil Core Retrieval.....	39
Measurement of Trench Void Volumes.....	54
Trench Cover Moisture and Bulk Density.....	69
Trench Contents and Grout Compatibility.....	74
Degradation Rates for ¹⁴ C-Labeled Polyacrylate and Polyacrylamide Grouts in Soil.....	86
Field Monitoring of SWSA 4 Grouted Trenches.....	102
III. DYNAMIC COMPACTION.....	110
Method of Dynamic Compaction.....	110
Results of Dynamic Compaction.....	110
Site Grading and Drainage.....	131
Time and Personnel.....	132
IV. REFERENCES.....	134
APPENDIX I - Examples of Types of Waste Placed in SWSA 6 Trenches 2, 3, 4, and 5.....	I-1
APPENDIX II - Drill Logs and Construction Information for TARA Wells 1 through 13.....	II-1
APPENDIX III - TARA Well Water Level Data, Hydrographs, and Area Rainfall.....	III-1

CONTENTS

	<u>Page</u>
APPENDIX IV - Nonstandard Soil Penetration Tests Over Waste Trenches.....	IV-1
APPENDIX V - Nonstandard Soil Penetration Tests in Conasauga Shale.....	V-1
APPENDIX VI - Standard Soil Penetration Resistance, Soil Moisture, and Bulk Density Data.....	VI-1
APPENDIX VII - Summary of the Number of Weight Drops Required During Trench Compaction.....	VII-1
APPENDIX VIII- Task Plan for Site Stabilization and Closure Technology Demonstration.....	VIII-1
APPENDIX IX - Final Plan for the Demonstration and Evaluation of Stabilization and Closure Techniques for Low-Level Waste Burial Trenches at Oak Ridge National Laboratory.....	IX-1
APPENDIX X - Correspondence with The State of Tennessee Department of Health and Environment.....	X-1

LIST OF TABLES

<u>Table</u>	<u>Page</u>
1 Summary of TARA trench open and close dates, waste shipment records, and estimated waste volumes according to ORNL Environmental Protection and Compliance Division waste records.....	10
2 Summary of TARA well construction parameters.....	13
3 Comparison of water elevations taken by the OMNIDATA logging system with manual measurements.....	17
4 Results of groundwater analysis from 15 TARA wells.....	23
5 Listing of semivolatile compounds that were analyzed but not detected in TARA groundwater samples.....	28
6 Comparison of measured groundwater TDS with calculated TDS and measured groundwater hardness with calculated hardness.....	31
7 Water quality characteristics of monitoring well samples.....	34
8 Organic vapor analyzer results for the undisturbed soil samples around the TARA burial trenches.....	46
9 Volatile organic compounds analyzed for in the TARA soil samples.....	52
10 Organic compounds and radionuclides detected in TARA soil samples selected from organic vapor analyzer responses.....	53
11 Radionuclides in soil samples from around the TARA burial trenches.....	55
12 Summary of calculations of water accessible void space derived from trench water pump-in tests.....	67
13 Changes in trench cap moisture and bulk density after trench compaction.....	72
14 Bulk density and moisture contents of surface (0-15 cm) soils of trench caps after dynamic compaction.....	73
15 Gross chemical and radiochemical characteristics of burial trench leachate and groundwater samples.....	79

LIST OF TABLES

<u>Table</u>	<u>Page</u>
16 Radionuclide and moisture contents of burial trench soil samples.....	80
17 Settling times for acrylamide grout in the presence of burial trench leachates and soils.....	82
18 Residual concentrations of acrylamide and methylenabisacrylamide in specimens of grout prepared in the presence and absence of burial trench soil and leachate.....	83
19 Hydraulic conductivities of burial trench soil columns before and after grouting with polyacrylamide.....	84
20 Water retention characteristics of acrylate and acrylamide polymers at various pressures.....	89
21 Loss of ^{14}C activity from 10% polyacrylate grout by degradation.....	90
22 Degradation rate constants and half-lives of 10% polyacrylate grout in soil.....	91
23 Loss of ^{14}C activity from 20% polyacrylate grout in soil.....	97
24 Degradation rate constants and half-lives of 20% polyacrylate grout in soil.....	97
25 Loss of ^{14}C activity from 10% polyacrylamide grout in soil.....	98
26 Degradation rate constants and half-lives of 10% polyacrylamide grout in soil.....	99
27 Loss of ^{14}C activity from 20% polyacrylamide grout in soil.....	100
28 Degradation rate constants and half-lives of 20% polyacrylamide grout in soil.....	100
29 Organic analyzates in groundwater samples from SWSA 4 monitoring wells around the polyacrylamide-grouted demonstration trenches.....	105
30 Water quality characteristics of SWSA 4 monitoring wells around the in situ grouting demonstration trenches.....	107

LIST OF TABLES

<u>Table</u>	<u>Page</u>
31 Elemental analyses of groundwater samples from SWSA 4 monitoring wells around the in situ grouting demonstration trenches.....	108
32 Summary of the number of weight drops required for each foot of trench compaction.....	115
33 Elevation of TARA trench 2 before and after trench compaction.....	117
34 Elevation of TARA trench 3 before and after trench compaction.....	120
35 Elevation of TARA trench 4 before and after trench compaction.....	123
36 Elevation of TARA trench 5 before and after trench compaction.....	125
37 Elevation of TARA trench 6 before and after trench compaction.....	127
38 Percentage reduction in trench water accessible void space achieved by dynamic compaction.....	131

LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
1 Problems encountered in the shallow-land burial of low-level and transuranic solid waste.....	4
2 Plan view of SWSA 6 showing the TARA site.....	6
3 Aerial view of the TARA site.....	7
4 Location of TARA site groundwater monitoring wells.....	12
5 Location of the four water elevation data logging systems at the TARA site.....	15
6 Topographic contour of the TARA site water table on March 18, 1988.....	18
7 Topographic contour of the TARA site water table on August 22, 1988.....	19
8 North-South cross section of the TARA site.....	20
9 East-West cross section of the TARA site.....	21
10 Quality control chart for anion-cation balance.....	30
11 Tritium contours at the TARA site approximated using Golden Graphics contouring software.....	32
12 Location of standard and nonstandard penetration test sites.....	37
13 Comparison of within trench and out of trench nonstandard penetration tests.....	38
14 Relationship between soil penetration resistance and percentage soil moisture at the TARA site.....	41
15 Relationship between soil penetration resistance and soil bulk density at the TARA site.....	42
16 Relationship between soil moisture and soil bulk density at the TARA site.....	43
17 Positions for undisturbed soil sampling during standard penetration tests around five TARA burial trenches.....	45
18 Frequency distribution of adjusted organic vapor analyzer readings for TARA soil samples.....	51

LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
19 Water pump-in test hydrograph for TARA trench 2.....	61
20 Water pump-in test hydrograph for TARA trench 3.....	62
21 Water pump-in test hydrograph for TARA trench 4.....	63
22 Water pump-in test hydrograph for TARA trench 5.....	64
23 Water pump-in test hydrograph for TARA trench 6.....	65
24 TARA site soil moisture as a function of depth.....	70
25 TARA site soil bulk density as a function of depth.....	71
26 Degradation of 10% ^{14}C -polyacrylate grout in soil plotted according to Equation 1 (k represents rate constants shown in Table 2).....	92
27 Degradation of 20% ^{14}C -polyacrylate grout in soil plotted according to Equation 1 (k represents rate constants shown in Table 4).....	94
28 Degradation of 10% ^{14}C -polyacrylamide grout in soil plotted according to Equation 1 (k represents rate constants shown in Table 6).....	95
29 Degradation of 20% ^{14}C -polyacrylamide grout in soil plotted according to Equation 1 (k represents rate constants shown in Table 8).....	96
30 Map of Solid Waste Storage Area 4, ORNL, showing area selected for demonstration of in situ grouting of buried transuranic waste.....	103
31 Plan view of trench caps and monitoring well locations in the study area for buried transuranic waste in situ grouting demonstration.....	104
32 Dynamic compaction of TARA burial trenches using a 4 Mg weight dropped from height of 7 m.....	111
33 Dynamic compaction of a control area at TARA site using a 4 Mg weight.....	112
34 Dynamic compaction crater over a TARA burial trench being surveyed for surface radioactivity.....	113

LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
35	Location of the compaction positions on the TARA trenches.....	114
36	Location of the control trench surface elevation points before and after trench compaction.....	129
37	Location of drainage berm showing finished grade at the TARA site.....	133

SUMMARY

As part of a low-level radioactive waste burial ground stabilization and closure technology demonstration project, a group of five burial trenches in Oak Ridge National Laboratory (ORNL) Solid Waste Storage Area (SWSA) 6 was selected as a demonstration site for testing trench compaction, trench grouting, and trench cap installation and performance. This report focuses on site characterization, trench compaction, and grout-trench leachate compatibility. Trench grouting and cap design and construction will be the subject of future reports.

The five trenches, known as the Test Area for Remedial Actions (TARA) site, are contained within a hydrologically isolated area of SWSA 6; for that reason, any effects of stabilization activities on site performance and groundwater quality will be separable from the influence of other waste disposal units in SWSA 6. To obviate the chronic problem of burial trench subsidence and to provide support for an infiltration barrier cap, these five trenches were dynamically compacted by repeated dropping of a 4-ton weight onto each trench from heights of approximately 7 m. Such a procedure was found to be effective in collapsing trench voids in a previous demonstration using one trench in SWSA 6 (Spalding 1986). However, experience with more than one trench is desirable to substantiate the technique's effectiveness.

Prior to trench dynamic compaction, a group of 13 groundwater monitoring wells was installed at the TARA site for purposes of collecting background information on site water quality and for monitoring water table elevation fluctuations. Sampling has shown that the groundwater contains tritium in concentrations as high as 270,000 Bq/L and is dominated by the sulfate, bicarbonate, and chloride anions, and the potassium, calcium, magnesium, and sodium cations. Water table fluctuations are monitored using an automated data logging system and appear to be similar to other areas within SWSA 6 (on the order of 1 to 2 m between winter high and summer low). The water table at the site has not been observed to intersect the trench bottoms as is the case with waste trenches located in lower topographic areas of SWSA 6.

Soil penetration resistance tests carried out at the site prior to compaction show that there is a significant difference between the stability of the existing trench covers and the native Conasauga Shale in which the waste trenches were placed. Trench void space, which causes this lack of stability, was measured prior to compaction by means of water pump-in tests. Results indicated that from 26 to 61 m³ of water-accessible voids existed in the trenches, accounting for between 8 and 23% of the total trench volume.

From July 27 to August 4, 1988, the five TARA trenches were compacted to a maximum depth of 1.2 m and the site was graded to facilitate surface runoff. A total of 2141 7-m drops of the 4-ton weight were required, or approximately 5.5 drops/m² of trench. Measurement of the volume reduction achieved through compaction was made by determining the volume of the resulting trench crater. Results indicate that an average water-accessible-void volume reduction of 77% was achieved. As further tests at the TARA site evaluate the effectiveness of trench grouting and cap performance, ORNL will be in a better position to select effective stabilization techniques for closure of

its existing radioactive waste disposal sites.

To ensure good control of future in situ grouting of the five compacted trenches, samples of leachate and bottom soil were collected from each trench and tested for compatibility with the polyacrylamide grout. Addition of trench soil or leachate did not significantly retard the set time of the grout, and it was determined that the percent polymerization of the acrylamide in the presence of soil or leachate was identical to that achieved with unamended or neat grout (i.e., 99.5%). In addition, specimens of the burial trench soil were converted from high to unmeasurably low hydraulic conductivity by percolation with reacting grout. Thus, it appears that these burial trenches pose no interference with polyacrylamide grout set.

Laboratory degradation studies using ^{14}C -labeled acrylate and acrylamide grouts have been monitored for periods up to two years. The microbiological half-lives of polyacrylate grouts, under steady-state conditions, range between 50 and 60 years while polyacrylamide grouts have half-lives greater than 300 years. Specimens of 10 and 20% polyacrylamide failed to lose detectable water even when equilibrated against 15 bars of moisture tension. Thus, desiccation in the subsurface soil environment will probably not be a significant problem for polyacrylamide grout performance.

Performance monitoring of groundwater around two small transuranic waste burial trenches in SWSA 4, grouted with polyacrylamide in 1986, has not revealed any contamination by grout constituents. Background water quality in the area has not been perturbed by either the grouting operations or by the buried waste except for occasional elevated levels of ^3H and gross beta activities.

I. INTRODUCTION

BACKGROUND

The Oak Ridge National Laboratory (ORNL) has been directed by the Department of Energy (DOE), the Tennessee Department of Health and Environment (TDHE), and the Environmental Protection Agency (EPA) to initiate closure of its current operational solid low-level radioactive waste disposal area (SWSA 6) by November of 1988. Anticipating the need for an extensive evaluation of the feasibility and effectiveness of waste trench closure techniques likely to be used on a large scale within SWSA 6 beyond the November 1988 closure initiation date, the ORNL Remedial Action Program (RAP) began an investigation in 1987 designed to evaluate several candidate remedial actions likely to be employed at the ORNL site.

The need for remedial actions originates in the many problems with shallow-land burial which have been experienced through the years. Figure 1 depicts a hypothetical burial trench in a humid climate which illustrates these performance problems in need of correction. The problem of trench cap permeability can lead to excessive leaching or inundation of buried waste either from direct infiltration of precipitation or from trapping of surface runoff which originates in adjacent areas. When the trench cap is much more permeable than the surrounding soil formation, the burial trench can actually fill with water to the point where radioactive leachate can overflow to the surface and flow offsite. If disposal area covers are made more impermeable, then a relatively large proportion of incoming precipitation will be converted to surface runoff; such runoff must be managed carefully so that soil erosion does not create new pathways to the waste or, in extreme cases, expose waste at the soil surface. In arid regions, wind erosion of cover material can result in similar waste exposure problems.

Regardless of trench cap construction or surface runoff management design, trench subsidence can result in surface depressions or cavities which will compromise performance. Trench subsidence is caused by the gradual consolidation of backfill or cover soil, by sedimentation of soil within buried waste voids, or by waste container degradation creating new trench voids. Surface subsidence depressions can then function to direct runoff and precipitation into contact with buried waste. Groundwater can also intrude into the trench through, for example, the seasonal fluctuation of the water table. Although the water-table elevation at the site may be below burial depth when measured before vegetation clearing or during seasonally dry periods, it may subsequently rise and intercept buried waste. A shortening of groundwater migration pathways may also be facilitated by trench construction. For example, a trench may connect previously separated groundwater flow paths or conductive geologic features for transient saturated flow.

In addition to these direct water management problems, the comparatively easy penetrability of cover soil and trench backfill may attract burrowing animals and/or facilitate plant root intrusion into buried waste. Such intrusion problems can be potentially serious even in arid regions where access to trench-stored moisture by plant roots can be obtained during normal

PROBLEMS ENCOUNTERED IN THE SHALLOW LAND BURIAL OF LOW-LEVEL WASTE

Fig. 1. Problems encountered in the shallow-land burial of low-level and transuranic solid waste.

seasonal moisture stresses. In addition, the animal burrows and the relict channels of plant roots can be conduits bringing surface runoff and precipitation directly into contact with buried waste. Plants growing on burial trenches can translocate radionuclides to their aboveground parts, creating a possibly significant mechanism for offsite dispersal via consumption by grazing animals, leaching of senescent plant material by surface water, or wind suspension or erosion of plant remains.

Many of the problems with burial trench performance stem from the inherent instability of the buried waste and backfill. Dynamic compaction was selected for demonstration as a remedial technique to address this primary fault. If dynamic compaction can establish a structurally sound ground surface, then various caps and moisture barriers can be constructed over burial trenches with assurance that they will not subside. In addition, in situ grouting was selected as a potential technique to provide hydrologic isolation of buried waste from either groundwater intrusion or infiltration of precipitation. Its use in combination with dynamic compaction will also be attempted. Only the first of these activities, dynamic compaction, was scheduled for FY 1988 and is the subject of this progress report. Chemical grouting and cover design and installation will be performed in FY 1989 and will be addressed in future reports.

PURPOSE AND OBJECTIVES

The purpose of this investigation, known as the Test Area for Remedial Actions (TARA) project, is to (1) identify promising trench stabilization and closure techniques applicable to the ORNL setting, (2) carry out these stabilization and closure techniques on a field scale using actual low-level waste trenches, and (3) collect the necessary data to evaluate each technique as to its feasibility, effectiveness, and cost. In this manner, the RAP will be in a position to select trench stabilization and closure alternatives which have been proven to be successful at the ORNL site.

SITE SELECTION

The site chosen for the TARA project lies on a small hillock in the northeast corner of SWSA 6 (Fig. 2). The site was selected based primarily on the following two criteria (1) it was away from operational areas within SWSA 6 and would, therefore, not interfere with daily waste management activities or vice versa; and (2) it was located on high ground and is thus isolated hydrologically from any peripheral recharge areas which would complicate performing a site water budget and performance monitoring as part of the stabilization and closure evaluation. In addition, the water table at the site is well below the bottoms of the trenches (see section on water level measurements) and, according to Davis et al. (1987), the trenches in the area are classified as unsaturated throughout the majority of the year, as opposed to being inundated or bathtubbing, as is the case with other trench areas within SWSA 6. The site also contains some of the first burial trenches used in SWSA 6 which contain higher-level (>200mrem/h) low-level solid waste. Figure 3 shows an aerial view of the TARA site illustrating the steep topography surrounding the waste trenches.

Fig. 2. Plan view of Solid Waste Storage Area 6 showing the Test Area for Remedial Actions (TARA) site.

Fig. 3. Areal View of the TARA site.

Initially, plans were made to compact 19 waste trenches located at the TARA site. As planning progressed and cost estimates were made for quantities of grout and construction of a cover that included the entire hillock, the idea of compacting 19 trenches was abandoned and the easternmost 5 of the 19 trenches were selected for compaction, grouting, and covering (ASGI 1987). By considering only the five easternmost trenches (trenches 2 through 6), the volume of grout needed was cut by 75% and the need for an expensive and possibly unbuildable retaining wall to support the final site cover in areas of steep slope was eliminated. Thus, the TARA project considered only 5 of the more than 500 waste trenches located in SWSA 6.

PROJECT DOCUMENTATION

Planning for the field activities to be conducted at the TARA site began in FY 1986 with the preparation of a draft task plan proposal of work to be carried out. This plan outlined the task as one which would focus on developing a closure strategy for the TARA site acceptable both to regulatory government agencies (EPA, TDHE, and DOE) and to ORNL environmental management.

The first task performed in FY 1987 was to conceptualize a plan for trench stabilization that had the necessary input of all groups concerned. This task was accomplished through subcontract with Automated Sciences Group, Inc., of Oak Ridge and the preparation of a final plan for trench stabilization and closure (See Appendix VIII). In this final plan, the field demonstration was broken down into four separate activities: (1) trench compaction, (2) trench grouting, (3) trench cover construction, and (4) site monitoring. Each activity was described, a cost estimate was prepared, and a list of potential contractors was compiled. Plans were made to proceed with the first activity (dynamic compaction) using Rust Engineering Company as the contractor.

Before any field activities could begin, an Action Description Memorandum (ADM) (Valentine 1986) had to be prepared, followed by an Environmental ALARA Memorandum (EAM) (Bly 1988). Additional documents, called for in the ADM and the EAM, were prepared next and included a construction excavation permit, a project Waste Management Plan, a project Safety Assessment (Doyle 1988), and finally a project Quality Assurance Plan. Several oral briefings for regulatory agency personnel were conducted through the regular DOE Waste Management Interface meetings. Several design and site monitoring changes were incorporated into project planning as a result of these meetings and resulting written correspondence with TDHE and EPA is contained in Appendix VIII. Although these extramural interactions, as well as the intramural documentation requirements, resulted in many extensions of the original project schedule, the project has been improved by them. Copies of the original ORNL task plan, the ASG, Inc., task plan, which was submitted to TDHE and EPA for comment, and the resulting exchange of comments are attached as Appendix VIII. Dynamic compaction activities finally began in July 1988.

II. SITE CHARACTERIZATION

WASTE RECORDS SEARCH

One of the first tasks to be performed in planning for the dynamic compaction demonstration was to identify the trench contents. This was seen as an important step in the event that the trenches contained significant quantities of hazardous liquids, such as waste oils that had been stored in drums prior to disposal in trenches. In addition, wastes likely to contain large quantities of small particulates, which would be of concern for potential airborne release during dynamic compaction, would need to be noted. To investigate trench contents, a search of the Environmental and Health Protection Division's waste records was made. The search consisted of manually going through files containing UCN 2822 forms (forms documenting each waste shipment to the ORNL burial grounds) and photocopying those forms that indicated disposal in SWSA 6 trenches 2, 3, 4, 5, or 6. Table 1 summarizes the trench open and close dates, the number of waste shipments made to each trench according to the computer data base known as MOD 1, the number of UCN 2822 forms that could be retrieved and photocopied, the percentage of UCN 2822 forms missing from the records, and an estimate of the total volume of waste according to the MOD 1 data base.

In addition to the data presented in Table 1, Duguid and Sealand (1975) reported that a total of 3415 ft^3 (97 m^3) of contaminated soil (weathered Conasauga shale) was removed from the vicinity of a liquid waste transfer line leak at ORNL and was placed in SWSA 6 trenches 3 and 4. A total of 875 ft^3 (25 m^3) of contaminated soil was placed in trench 3 and 2540 ft^3 (72 m^3) was placed in trench 4. Analysis of soil samples taken from the leak site prior to disposal in SWSA 6 are summarized by Duguid and Sealand (1975) and indicate that the soil contained the alpha emitters ^{244}Cm , ^{241}Am , ^{238}Pu , and ^{239}Pu ; the beta emitters ^{90}Sr , ^{60}Co , $^{95}\text{ZrNb}$, ^{106}Ru , ^{125}Sb , ^{134}Cs , and ^{137}Cs ; and unknown gamma emitters. The MOD 1 computer data base confirms these volumes of contaminated soil as originating from Pit Number 7, and lists 3375 ft^3 (95.6 m^3) as containing "low" alpha and "high" beta activity, while 40 ft^3 (1 m^3) contained "high" alpha and "low" beta activity.

As seen in Table 1, there are no waste shipment records describing wastes reported to have gone to trench 6. This was not understood until the burial ground operators' log book was consulted and it was found that trench 6 was opened for only one day and was filled with the contents of parts of trenches 2, 3, and 4 that were exposed while attempting to recover a piece of missing equipment that had been thrown away inadvertently. Thus, trenches 2, 3, 4, and 6 probably contain more soil backfill than would normally be expected in typical SWSA 6 trenches because of the nature of the waste (contaminated soil) and the additional excavation and reburial that took place.

While reviewing the individual UCN 2822 forms, selected documents containing a more descriptive account of the waste type were compiled into a summary table (Appendix I). In reviewing Appendix I, it can be seen that the trench number, date, volume, and radiation level of individual waste

Table 1. Summary of TARA trench open and close dates, waste shipment records, and estimated waste volumes according to ORNL Environmental Protection and Compliance Division waste records

	SWSA 6 Trench				
	2	3	4	5	6
Open Date	11-2-72	4-12-73	7-30-73	8-28-73	10-10-73
Close Date	5-30-73	7-30-73	8-28-73	10-10-73	10-11-73
Time Open	6 mo	3 mo	1 mo	2 mo	1 day
Number of Waste Shipments According to MOD 1 Data Base	49	41	77	26	0
Number of UCN 2822 Forms Retrieved	14	20	28	18	0
Percentage of UCN 2822 Forms Missing (%)	71	51	64	31	0
Total Volume of Waste (m^3) Reported in MOD 1 Data Base ¹	63.2	95.3	195.4	86.5	0

¹These estimated waste volumes are taken directly from the MOD 1 waste disposal data base and include volumes of waste for all recorded shipments, not just the volumes from retrieved 2822 forms.

shipments are summarized, along with the isotopes and a brief written description of the waste. These records are only estimates made by the original waste generators, and their accuracy would be expected to vary widely. The description contains such entries as "misc. cell waste in lead dumpster, junk from cell A, and contaminated waste on hot truck wrapped in plastic," which make it impossible to quantify the contents or total activity within the five trenches of interest. Because there was no thorough listing of trench contents, dynamic compaction proceeded with contingency plans in the event that liquids, dust, or high radiation levels were encountered during the process.

MONITORING WELL INSTALLATION

To facilitate groundwater sampling, establish background water quality conditions, and monitor changes in the water-table elevation at the TARA site, a group of 13 wells was planned and constructed in 1987. Criteria for siting the wells included (1) distributing them across the site so that the waste trenches would be completely surrounded, (2) locating wells in the near field (close to the waste trenches) as well as farther away from the waste in a down-gradient direction (far field), (3) establishing both east-west and north-south transects for future graphical representations of the cross-sectional water table in the vicinity of the waste trenches, and (4) making use of existing SWSA 6 piezometers and water quality wells constructed during the summers of 1986 and 1987, respectively. Figure 4 shows the 13 well locations in plan view along with existing piezometers (369, 367, 646, and 655) and water quality monitoring wells (843 and 844).

Well construction began in March 1987 at TARA well 5 located in the southwestern corner of the TARA site. A track-mounted drill rig was used by ORNL's Plant and Equipment Division with field assistance from personnel in the Environmental Sciences Division. A 15-cm (6-in.) diam auger with a rock bit head was used to auger each of the 13 holes. Drilling records were kept at each 30.5-cm (1-ft) depth interval describing the presence or absence of rock (inferred from drilling resistance), cuttings color, presence of water, and general drilling conditions. Appendix II summarizes the drilling logs and well construction data in pictorial form. As expected, many hard limestone layers interbedded with softer shale layers were encountered during the drilling process.

As drilling of each of the 13 holes was completed, cleaning was accomplished by repeated rapid revolution of the auger combined with vertical movement of the auger sections to bring cuttings to the surface. The auger was then broken down in 1.5-m (5-ft) sections and removed from the hole. Prepackaged 7.6-cm (3-in.)-diam threaded PVC casing material was then lowered down each hole beginning with a 6.1-m (20-ft) length of 0.51-mm (0.02-in.) slot opening screen followed by enough solid riser pipe to protrude approximately 1 m above the ground surface. Prewashed, coarse silica sand was then added to the annular space to cover the 6.1-m length of well screen by approximately 1 m. Continuous health physics coverage was provided throughout the drilling operation, and no radioactivity was detected in cuttings from any of the 13 wells.

Fig. 4. Location of TARA site groundwater monitoring wells.

After sampling and radioactivity analyses in April 1987, each of the TARA wells, along with existing piezometer 367, was flushed (cleaned out) using water from a nearby pond (emergency liquid waste storage basin shown in Figs. 3 and 4). Flow-rates used were approximately 7.4 L/min (28 gal/min) delivered to each well using a trailer-mounted diesel water pump and 5-cm (2-in.) rubber delivery hose run to the bottom of each well. Each well, in turn, was repeatedly flushed by water surges until fines were lifted from the casing and the stream of wash water became clear (approximately 30 min to 1 h). After flushing was completed, excess water remaining in the casing was siphoned out via the rubber hose water delivery line. Bentonite clay pellets were added to the annular volume outside the casing above the sand to form an approximate 1-m-thick impermeable barrier to vertical water movement, and the remainder of the annular space was backfilled with soil cuttings. At this point the wells were considered completed and were labeled with metal tags and surveyed for exact location, top of casing elevation, and ground elevation (Table 2).

Table 2. Summary of TARA well construction parameters

TARA Well	ORNLN	ORNLE	TOC Elev. (m)	Ground Elev. (m)	Well Depth (m)	Screen Length (m)	Depth to Sand (m)	Depth to Volclay (m)
1	17806.99	25192.38	254.47	253.58	19.15	6.10	9.30	7.16
2	17816.12	25102.46	256.08	255.14	19.32	6.10	12.19	10.97
3	17752.28	25062.08	256.00	255.43	16.40	6.10	9.27	8.02
4	17654.24	25002.46	255.34	254.38	17.83	6.10	10.85	9.75
5	17549.76	24928.23	255.65	254.87	19.27	6.10	9.07	7.64
6	17608.96	25086.38	255.46	254.74	19.23	6.10	8.23	7.16
7	17689.47	25141.24	256.04	255.76	19.32	6.10	5.03	3.81
8	17814.50	24993.14	246.59	245.75	11.89	6.10	2.32	1.43
9	17879.49	25041.76	245.99	245.39	11.89	6.10	5.79	4.57
10	17697.16	24945.94	246.57	245.90	11.89	6.10	5.03	3.96
11	17709.84	25256.02	248.09	247.45	14.87	6.10	9.14	7.92
12	17645.69	25295.15	239.17	238.63	9.14	6.10	2.44	0.73
13	17895.08	25151.41	245.36	245.01	11.89	6.10	4.57	3.35
367	17723	25091	257.39	256.61	22.17	3.05	--	--
369	17476	24805	256.32	255.48	14.63	3.05	--	--
646	17550.78	25167.05	239.84	239.31	11.89	3.05	7.31	7.01
655	17469.72	24815.30	255.91	255.50	38.10	7.62	28.95	28.35

WATER LEVEL MEASUREMENTS

Manual water level measurements have been made on 15 of the TARA wells (wells 1 through 13, 367, and 646) since the time of well construction (April 1987). These manual measurements were taken at approximate 1-week time intervals and consisted of lowering an electronic tape down the well to the depth of the water surface and recording this distance from the top of the casing to the water surface. The depths to water were then converted to absolute elevation above National Geodetic Vertical Datum (by subtracting them from the top of the well casing elevation) and are summarized in Appendix III. Along with the tabular water elevation data, well hydrographs have been constructed for each well for the period April 1987 to August 1988 along with rainfall for the period January 1987 to August 1988 (Appendix III). Responses of monitoring wells to trench water pump-in tests conducted in July and October 1987 are annotated on each hydrograph.

To ease the task of measuring water levels by the manual method described above, and to facilitate taking water elevations at shorter time steps through particular storm events, an automatic water level monitoring system was installed at the TARA site. The system consisted of 15 Druck, Inc., pressure transducers (one for each of the 15 TARA wells) connected to four OMNIDATA, Inc., Easy Logger data logging devices located at four stations across the TARA site. Data logging stations 1 through 4, and the wells they serve, are shown in plan view in Fig. 5.

After laboratory calibration, the pressure transducers were taken to the site and installed in each well at a depth of 1.5 to 3 m below the water surface. The lead wires running to the data loggers were secured to the well casing so the transducer could not accidentally be moved, thus changing elevation. The transducer leads were then run along the ground and connected to the logging devices which were set to record (daily) the pressure due to the height of the column of water above the transducer. The pressure, recorded by the data logger as a millivolt signal, is converted to a water head using the equation

$$Y = SX + O$$

where, Y = water head (m)
 S = slope (m/mV)
 X = probe signal (mV)
 O = probe offset (m).

Values of S and O were determined for each probe during laboratory calibration prior to field use and were programmed into the individual data loggers.

The loggers were programmed to scan the pressure transducers each day at 1200 h EST and to record the instantaneous water level in each of the 15 wells. Water elevation data collected by the data loggers have been combined with manual measurements and are summarized in tabular and graphical form in Appendix III.

Fig. 5. Location of the four water elevation data logging systems at the TARA site.

To ensure that the pressure transducers are functioning properly, manual water level readings have been compared to the instantaneous pressure transducer readings on a monthly basis. Table 3 summarizes the results of two such comparisons made on April 4 and May 18, 1988. An insignificant difference, on the order of centimeters, is typically found between manual readings and pressure transducer readings indicating that the pressure transducers have been quite accurate in measuring the site water table elevation.

The water elevation data collected at the TARA site can be used to construct a topographic map of the water surface as well as hydrologic cross sections of the site. The groundwater topography was mapped on two separate dates: March 18, 1988, which represents relatively high water table conditions, and August 22, 1988, which represents a lower water table condition (Figs. 6 and 7) resulting from a regional drought. Both maps show that there is a gradient from west to east across the site with a localized high in the vicinity of TARA 3. The reason for this localized high is not understood at this time and is under investigation. Assuming the groundwater flow direction to be perpendicular to the contours of Figs. 6 and 7, infiltration from the vicinity of TARA trenches 2 through 6 should move in a southeasterly direction toward wells 7, 11, and 12. Future groundwater sampling of these and the other TARA wells will determine if this inference is correct.

In addition to the topographic contour maps, two cross sections of the site have been constructed along the two dotted lines shown in Fig. 4 (see Figs. 8 and 9). Again, the water levels for March 18 and August 22, 1988, were used. The slight mounding of water around well 3 is apparent in these drawings also and could be caused by perched water near well 3 or by well 367 acting as a drain or discharge point. Again, this is the subject of further investigation.

Table 3. Comparison of water elevations taken by the OMNIDATA logging system with manual measurements

TARA Well	Measured Water Elevation (m)	Logger Water Elevation (m)	Difference (m)
April 4, 1988			
1	241.24	241.19	-0.05
2	240.53	240.53	0.00
3	243.71	243.69	-0.02
4	242.26	242.26	0.01
5	242.84	242.84	0.00
6	240.88	240.84	-0.04
7	240.92	240.86	-0.06
8	240.72	240.67	-0.04
9	239.96	239.94	-0.02
10	242.21	242.25	0.04
11	238.08	238.05	-0.03
12	235.65	235.65	0.01
13	237.83	237.83	0.00
367	240.15	240.08	-0.07
646	235.74	235.71	-0.03
May 18, 1988			
1	240.73	240.68	-0.05
2	240.41	240.41	0.00
3	243.32	243.32	0.00
4	241.54	241.54	0.01
5	242.48	242.48	0.00
6	240.44	240.44	0.00
7	240.61	240.57	-0.04
8	240.57	240.53	-0.04
9	239.81	239.79	-0.02
10	241.88	241.90	0.01
11	237.78	237.74	-0.03
12	235.23	235.19	-0.04
13	238.34	238.34	-0.01
367	239.77	239.72	-0.05
646	235.52	235.51	-0.01

Fig. 6. Topographic contour of the TARA site water table on March 18, 1988.

Fig. 7. Topographic contour of the TARA site water table on August 22, 1988.

Fig. 8. North-South cross section of the TARA site.

Fig. 9. East-West cross section of the TARA site.

GROUNDWATER SAMPLING

To establish baseline water quality at the TARA site (before compaction activities were initiated), water samples were collected from each of the 15 wells listed in Table 4. Sampling was conducted between November 18 and 23, 1987, and consisted of repeatedly evacuating each well casing using a stainless steel, compressed air driven, submersible pump lowered by reel and cable to within approximately 0.5 m of the well bottom. Pumping rates varying between 75 and 230 L/h were maintained in each well until the water was completely pumped from the well casing. Only well 12, which is located in a gully to the southeast of the trenches, was able to recover at a rate greater than the 230-L/h maximum pumping rate such that it could not be completely evacuated. All water withdrawn from each well as part of the evacuation procedure was collected in plastic carboys until chemical and radiochemical analysis confirmed it was safe to discard.

The water evacuation procedure was repeated two or three times on each well, often over several days, before a representative sample was collected for chemical analysis. Total volumes of water removed from each well prior to sampling are summarized in Table 4.

As water was being pumped from each well and into a plastic carboy, flow was directed through a Hydrolab Corporation Surveyor II water analyzer connected in series with the pump. The analyzer was set up to measure water temperature, pH, dissolved oxygen (DO), and electrical conductivity (EC). At the desired sampling time, water was pumped directly into prewashed sample bottles which were capped, labeled, and stored directly on ice for transport to the laboratory. This method avoided splitting samples into individual sample bottles in the laboratory. Table 4 summarizes each of these four parameters measured at the time groundwater samples were collected.

In addition to the four parameters measured in the field, samples were analyzed for a number of elements using inductively coupled plasma (ICP) emission spectroscopy techniques (APHA 1980), hardness, alkalinity, total organic carbon (TOC), total dissolved solids (TDS), 91 semivolatile organic compounds (EPA Method 624, Table 5), radionuclides, Hg and K via atomic adsorption (AA) spectroscopy, and major anions via high-pressure liquid chromatography (HPLC). None of the 91 organic compounds listed in Table 5 was detected in any of the TARA groundwater samples. In the laboratory, electrical conductivity, pH, dissolved solids (after filtration through 0.45 μ m nitrocellulose membranes), and gross alpha and beta activities were measured (APHA 1980). Tritium was measured without distillation using a 2-mL aliquot with 18 mL of Ecolume (ICN Radiochemicals, Inc.) scintillation cocktail; the near background levels of gross alpha and beta activities in the samples justified this abridged ^3H assay technique. The values for ^3H and other radionuclides reported in Table 4 were performed by standard (not abridged) procedures and, therefore, are not subject to ambiguity.

To determine how complete the groundwater analysis was, an anion-cation charge balance was performed on each water sample. Major anions considered were bicarbonate (measured by alkalinity titration), chloride, and sulfate. The additional anions nitrite and phosphate were below detection limits while

Table 4. Results of groundwater analysis from 15 TARA wells

TARA Well	Sample Date	Water Removed Before Sampling (L)	Field Temp. (°C)	Field pH (units)	Lab pH (units)	Field DO (mg/L)	Field EC (mmhos/cm)
1	11/20/87	125	14.5	5.8	6.6	4.4	0.24
2	11/20/87	46	13.8	6.3	6.8	3.5	0.28
3	11/20/87	71	11.9	6.3	6.4	2.5	0.47
4	11/20/87	152	13.1	6.5	6.6	0.5	0.46
5	11/20/87	92	13.2	6.8	6.8	3.5	0.27
6	11/20/87	37	13.0	6.5	6.8	1.1	0.29
7	11/20/87	92	12.9	6.2	6.9	0.6	0.36
8	11/23/87	100	14.4	6.6	7.2	0.5	0.35
9	11/23/87	62	14.0	6.8	7.2	5.0	0.24
10	11/23/87	112	15.0	6.9	6.4	6.0	0.23
11	11/20/87	144	13.2	6.4	6.5	6.5	0.46
12	11/18/87	200	14.9	6.4	6.8	2.5	0.35
13	11/23/87	42	13.7	6.5	7.1	3.3	0.21
367	11/20/87	78	13.1	6.3	6.9	3.3	0.55
646	11/23/87	20	15.8	6.4	7.3	1.2	0.23

Table 4. (Continued)

TARA Well	Lab EC (mmhos/cm)	TOC (mg/L)	TDS (mg/L)	Hardness (mg CaCO ₃ per L)	Alkalinity (mg CaCO ₃ per L)	Cl (mg/L)	SO ₄ (mg/L)
1	0.49	2.9	440	454	340	2.5	59
2	0.51	3.1	420	416	382	2.4	45
3	0.91	3.5	840	718	506	10	290
4	0.49	4.4	380	400	366	9.6	31
5	0.45	1.5	420	398	292	3.1	81
6	0.66	9.6	600	568	492	11	65
7	0.67	10.1	2560	550	532	21	24
8	0.38	9.1	240	278	258	4.5	35
9	0.45	9.0	200	356	306	1.8	50
10	0.35	7.7	260	286	244	4.6	38
11	0.89	1.6	920	758	512	21	250
12	0.60	2.2	2420	470	466	14	59
13	0.42	0.8	1120	314	292	1.5	42
367	1.10	1.7	1020	900	554	240	390
646	0.48	1.6	200	352	316	2.9	41

Table 4. (Continued)

TARA Well	NO ₂ (mg/L)	NO ₃ (mg/L)	PO ₄ (mg/L)	K (mg/L)	Ca (mg/L)	Mg (mg/L)	Na (mg/L)
1	<5	<5	<5	2.91	150	28	13
2	<5	<5	<5	3.40	160	35	9.1
3	<5	<5	<5	4.82	180	70	39
4	<5	5.9	<5	1.69	140	20	9.1
5	<5	<5	<5	3.36	120	35	13
6	<5	<5	<5	6.40	190	40	17
7	<5	32	<5	2.30	220	31	20
8	<5	<5	<5	2.00	96	16	6.1
9	<5	<5	<5	2.51	120	19	18
10	<5	<5	<5	2.75	110	14	6.5
11	<5	<5	<5	3.18	230	60	38
12	<5	8.7	<5	1.50	180	26	18
13	<5	<5	<5	1.66	140	15	9.6
367	<5	<5	<5	3.37	240	80	34
646	<5	<5	<5	11.6	120	37	16

Table 4. (Continued)

TARA Well	Fe (mg/L)	Hg (mg/L)	Br (mg/L)	F (mg/L)	Ag (mg/L)	Al (mg/L)	As (mg/L)
1	0.88	0.0002	<5	1.0	<0.05	0.44	<0.10
2	1.40	0.0001	<5	1.0	<0.05	0.51	<0.10
3	0.09	0.0001	<5	1.0	<0.05	0.22	<0.10
4	0.08	0.0002	<5	<1	<0.05	0.20	<0.10
5	0.28	0.0001	<5	<1	<0.05	0.28	<0.10
6	1.50	<0.0001	<5	1.0	<0.05	0.56	<0.10
7	0.78	0.0002	<5	1.0	<0.05	0.56	<0.10
8	0.19	0.0001	<5	<1	<0.05	0.22	<0.10
9	0.85	0.0002	<5	<1	<0.05	0.41	<0.10
10	0.64	0.0001	<5	<1	<0.05	0.34	<0.10
11	1.50	0.0001	5.0	1.0	<0.05	0.61	<0.10
12	0.28	0.0001	<5	1.0	<0.05	0.31	<0.10
13	0.97	0.0001	<5	<1	<0.05	0.63	<0.10
367	0.76	0.0003	<5	1.0	<0.05	0.37	<0.10
646	1.70	0.0002	<5	<1	<0.05	0.43	<0.10

Table 4. (Continued)

TARA Well	B (mg/L)	Ba (mg/L)	Be (mg/L)	Cd (mg/L)	Co (mg/L)	Cr (mg/L)	Cu (mg/L)
1	<0.08	0.13	<0.002	<0.005	<0.01	<0.04	<0.02
2	<0.08	0.13	<0.002	<0.005	<0.01	<0.04	<0.02
3	<0.08	0.07	<0.002	<0.005	<0.01	<0.04	<0.02
4	<0.08	0.13	<0.002	<0.005	<0.01	<0.04	<0.02
5	<0.08	0.06	<0.002	<0.005	<0.01	<0.04	<0.02
6	<0.08	0.34	<0.002	<0.005	<0.01	<0.04	<0.02
7	<0.08	0.16	<0.002	<0.005	<0.01	<0.04	<0.02
8	<0.08	0.14	<0.002	<0.005	<0.01	<0.04	<0.02
9	<0.08	0.11	<0.002	<0.005	<0.01	<0.04	<0.02
10	<0.08	0.19	<0.002	<0.005	<0.01	<0.04	<0.02
11	<0.08	0.04	<0.002	<0.005	<0.01	<0.04	<0.02
12	<0.08	0.19	<0.002	<0.005	<0.01	<0.04	<0.02
13	<0.08	0.21	<0.002	<0.005	<0.01	<0.04	<0.02
367	<0.08	0.03	<0.002	<0.005	<0.01	<0.04	<0.02
646	<0.08	0.20	<0.002	<0.005	<0.01	<0.04	<0.02

Table 4. (Continued)

TARA Well	Ga (mg/L)	Li (mg/L)	Mn (mg/L)	Mo (mg/L)	Ni (mg/L)	P (mg/L)	Pb (mg/L)
1	<0.3	<0.2	0.27	<.04	<0.06	<0.3	<0.2
2	<0.3	<0.2	0.40	<.04	<0.06	<0.3	<0.2
3	<0.3	<0.2	0.47	<.04	<0.06	<0.3	<0.2
4	<0.3	<0.2	0.03	<.04	<0.06	<0.3	<0.2
5	<0.3	<0.2	0.06	<.04	<0.06	<0.3	<0.2
6	<0.3	<0.2	0.26	<.04	<0.06	<0.3	<0.2
7	<0.3	<0.2	0.24	<.04	<0.06	<0.3	<0.2
8	<0.3	<0.2	0.09	<.04	<0.06	<0.3	<0.2
9	<0.3	<0.2	0.25	<.04	<0.06	<0.3	<0.2
10	<0.3	<0.2	0.20	<.04	<0.06	<0.3	<0.2
11	<0.3	<0.2	0.25	<.04	<0.06	<0.3	<0.2
12	<0.3	<0.2	0.07	<.04	<0.06	<0.3	<0.2
13	<0.3	<0.2	0.55	<.04	<0.06	<0.3	<0.2
367	<0.3	<0.2	0.07	<.04	<0.06	<0.3	<0.2
646	<0.3	<0.2	0.68	<.04	<0.06	<0.3	<0.2

Table 4. (Continued)

TARA Well	Sb (mg/L)	Se (mg/L)	Si (mg/L)	Sn (mg/L)	Sr (mg/L)	Ti (mg/L)	V (mg/L)
1	<0.2	<0.2	7.1	<0.05	0.31	<0.02	<0.02
2	<0.2	<0.2	7.5	<0.05	0.34	<0.02	<0.02
3	<0.2	<0.2	8.9	<0.05	0.42	<0.02	<0.02
4	<0.2	<0.2	6.7	<0.05	0.26	<0.02	<0.02
5	<0.2	<0.2	11	<0.05	0.31	<0.02	<0.02
6	<0.2	<0.2	11	<0.05	0.45	<0.02	<0.02
7	<0.2	<0.2	11	<0.05	0.34	<0.02	<0.02
8	<0.2	<0.2	5.2	<0.05	0.22	<0.02	<0.02
9	<0.2	<0.2	8.3	<0.05	0.21	<0.02	<0.02
10	<0.2	<0.2	6.4	<0.05	0.26	<0.02	<0.02
11	<0.2	<0.2	8.8	<0.05	0.46	<0.02	<0.02
12	<0.2	<0.2	9.6	<0.05	0.29	<0.02	<0.02
13	<0.2	<0.2	6.0	<0.05	0.20	<0.02	<0.02
367	<0.2	<0.2	8.9	<0.05	0.43	<0.02	<0.02
646	<0.2	<0.2	14	<0.05	1.5	<0.02	<0.02

Table 4. (Continued)

TARA Well	Zn (mg/L)	Zr (mg/L)	Co 60 (Bq/L)	Cs 137 (Bq/L)	Total Sr (Bq/L)	Tritium (Bq/L)	Major Anions (me/L) ¹
1	0.034	<0.02	<0.2	<0.2	0.23	74	8.10
2	0.050	<0.02	<0.1	<0.1	0.85	1100	8.65
3	0.046	<0.02	0.89	0.31	1.4	4400	16.44
4	0.026	<0.02	0.43	<0.1	0	270000	8.33
5	0.032	<0.02	<0.1	<0.1	0.39	390	7.61
6	0.053	<0.02	0.51	<0.1	2.9	7500	11.50
7	0.039	<0.02	<0.2	<0.2	0.78	1700	12.25
8	0.020	<0.02	<0.2	<0.1	0	7000	6.02
9	0.037	<0.02	<0.1	<0.1	0.49	450	7.21
10	0.022	<0.02	<0.2	<0.2	0.046	13000	5.80
11	0.054	<0.02	1.3	<0.1	0.17	3300	16.04
12	0.022	<0.02	0.24	<0.1	0.07	8200	11.08
13	0.032	<0.02	<0.2	0.15	0.28	34000	6.76
367	0.058	<0.02	0.19	<0.1	0.65	280	25.97
646	0.034	<0.02	<0.1	<0.1	0.75	0	7.26

¹Milliequivalents/liter.

Table 4. (Continued)

TARA Well	Major Cations (me/L)	Anion-Cation Ratio
1	10.43	0.78
2	11.35	0.76
3	16.56	0.99
4	9.07	0.92
5	9.52	0.80
6	13.67	0.84
7	14.46	0.85
8	6.42	0.94
9	8.40	0.86
10	6.99	0.83
11	18.15	0.88
12	11.94	0.93
13	8.68	0.78
367	20.12	1.29
646	10.02	0.72

Table 5. Listing of semivolatile compounds that were analyzed but not detected in TARA groundwater samples

phenol	hexachlorobenzene
bis (2-chloroethyl) ether	pentachlorophenol
2-chlorophenol	phenanthrene
1,3-dichlorobenzene	anthracene
1,4-dichlorobenzene	di-n-butylphthalate
benzyl alcohol	fluoranthene
1,2-dichlorobenzene	pyrene
2-methylphenol	butylbenzylphthalate
bis(2-chloroisopropyl) ether	3,3'-dichlorobenzidine
n-nitroso-di-n-propylamine	benzo(a)anthracene
hexachloroethane	chrysene
nitrobenzene	bis(2-ethylhexyl)phthalate
isophorone	di-n-octylphthalate
2-nitrophenol	benzo(b)fluoranthene
2,4-dimethylphenol	benzo(k)fluoranthene
benzoic acid	benzo(a)pyrene
bis(2-chloroethoxy)methane	indeno(1,2,3-cd)pyrene
2,4-dichlorophenol	dibenz(a,h)anthracene
1,2,4-trichlorobenzene	benzo(g,h,i)perylene
naphthalene	alpha-BHC
4-chloroaniline	beta-BHC
hexachlorobutadiene	delta-BHC
4-chloro-3-methylphenol	gamma-BHC (Lindane)
2-methylnaphthalene	heptachlor
hexachlorocyclopentadiene	aldrin
2,4,6-trichlorophenol	heptachlor epoxide
2,4,5-trichlorophenol	endosulfan I
2-chloronaphthalene	dieldrin
2-nitroaniline	4,4'-DDE
dimethylphthalate	endrin
acenaphthylene	endosulfan II
2,6-dinitrotoluene	4,4'-DDD
3-nitroaniline	endosulfan sulfate
acenaphthene	4,4'-DDT
2,4-dinitrophenol	methoxychlor
4-nitrophenol	endrin ketone
dibenzofuran	alpha-chlordane
2,4-dinitrotoluene	gamma-chlordane
diethylphthalate	toxaphene
4-chlorophenyl-phenylether	Aroclor-1016
fluorene	Aroclor-1221
4-nitroaniline	Aroclor-1232
4,6-dinitro-2-methylphenol	Aroclor-1242
n-nitrosodiphenylamine (1)	Aroclor-1248
4-bromophenyl-phenylether	Aroclor-1254
	Aroclor-1260

nitrate was detected in measurable amounts in wells 4 and 12 only. Major cations considered were potassium, calcium, magnesium, and sodium. Concentrations of each of these major anions and cations were expressed in milliequivalents per liter (me/L) and summed in Table 4. The charge ratio of anions to cations (expected to be 1 if analytical work is precise and all ions are considered) is summarized as the last column of Table 4 and shows that there was generally a low anion concentration (ratio <1) except for well 367, which had an anion to cation ratio of 1.29. Most of the ratios range from 0.76 to 0.99, indicating that the three major anions and four major cations being considered adequately account for charged species present in the TARA groundwater.

A procedure recommended in Standard Methods for the Examination of Water and Wastewater (APHA 1980) for checking the correctness of anion and cation analyses was used and consisted of plotting the difference in anions and cations expressed as me/L against the sum of the anions (Fig. 10). Lines representing plus or minus one standard deviation, the acceptable error limit, are also shown in this figure and were derived from the equation

$$\text{Sum Anions} - \text{Sum Cations} = \pm(0.1065 + 0.0155 * \text{Sum Anions}).$$

Points lying outside the two acceptable limits indicate possible problems with the chemical analyses. The deficiency of anions could have resulted from a loss of alkalinity in the samples due to outgassing of CO₂ between the time of sampling and analysis; such an outgassing would be accompanied by a slight rise in pH, which was observed in the laboratory-measured pH versus field-measured pH. Alternately, an excess of cations, particularly Ca and Mg, could result from dissolution of colloidal CaCO₃ on addition of the HNO₃ preservative after sample filtration. Regardless of its source, the discrepancy between anions and cations probably results from differences in Ca, Mg, and alkalinity and would have little consequence in the interpretation of groundwater quality for these background samples.

Another check was made of the TDS values by a "rough calculation" method suggested in Standard Methods. Electrical conductivity (μmhos/cm) values multiplied by a factor in the range of 0.55 to 0.7 should approximate TDS in mg/L. Results, along with the percentage differences between measured and approximated values of TDS, are summarized in Table 6.

A final check of the hardness by calculation was made using the equation

$$H = 2.497[Ca] + 4.118[Mg]$$

where: H = hardness, mg/L as CaCO₃

Ca = calcium, mg/L

Mg = magnesium, mg/L.

Results of the calculated values of hardness are compared to the measured values in Table 6. The calculated hardnesses were all greater than the measured hardnesses, and this systematic difference could arise from the causes discussed above.

Fig. 10. Quality control chart for anion-cation balance.

Table 6. Comparison of measured groundwater total dissolved solids (TDS) with calculated TDS (calculated TDS = EC x 0.7) and measured groundwater hardness with calculated hardness (calculated hardness = $2.497 \times [\text{Ca, mg/L}] + 4.118 \times [\text{Mg, mg/L}]$)

TARA Well	Measured TDS (mg/L)	Calculated TDS (mg/L)	Percent Diff.	Measured Hardness (mg CaCO ₃ /L)	Calculated Hardness (mg CaCO ₃ /L)	Percent Diff.
1	440	343	22	454	490	8
2	420	357	15	416	544	31
3	840	637	24	718	738	3
4	380	343	10	400	432	8
5	420	315	25	398	444	11
6	600	462	23	568	639	13
7	2560	469	82	550	677	23
8	240	266	11	278	306	10
9	200	315	58	356	378	6
10	260	245	6	286	332	16
11	920	623	32	758	821	8
12	2420	420	83	470	557	18
13	1120	294	74	314	411	31
367	1020	770	25	900	929	3
646	200	336	68	352	452	28

Tritium concentrations measured in the groundwater were contoured using the SURFER (Golden Software, Inc.) GRID and TOPO contouring programs. Tritium was selected from the list of parameters in Table 4 because it was detected in all but one well (646), it is mobile and would tend to follow the water flow, and its source is likely to be waste placed in the upgradient waste trenches. Because of the large range in tritium concentrations that was measured (0 Bq/L in well 646 to 270,000 Bq/L in well 4), only selected contour lines are shown in Fig. 11. It is seen that the highest tritium concentrations are in the vicinity of wells 4 (270,000 Bq/L), 10 (13,000 Bq/L), and 13 (34,000 Bq/L), which lie to the north and west of the trenches. The remaining wells contained approximately two-orders-of-magnitude-lower concentrations, in the range of 100 to 8000 Bq/L. The distribution of tritium at the TARA site points out that, although the water contours indicate primarily a southwest flow direction, drainage from the trench area is moving down gradient in all directions and is being intercepted by both the near and far field TARA wells.

It is important to realize that the contours shown in Fig. 11 are computer generated from observations at irregularly spaced well locations and can only be used to approximate the actual distribution of tritium at the site. The interpolation methods employed by SURFER for computing concentrations between wells may or may not be valid and would certainly be inappropriate if water flow at the site is dominated by fractures or other flow conduits

Fig. 11. Tritium contours at the TARA site approximated using Golden Graphics contouring software.

existing between trenches and wells.

To determine how the groundwater quality changes with time, additional samples were collected from these 15 wells on April 8, 1987; November 11, 1987; June 24, 1988; and August 29, 1988, for analysis of radionuclides and macroscopic chemical characteristics. Grab samples of water were collected from each well using a dedicated PVC bailer attached to a nylon string that could be lowered down each well. Results are presented in Table 7. No significant trends in either the chemical or radiochemical characteristics are apparent. There was no immediate change between precompaction (June 24, 1988) and the first postcompaction (August 29, 1988) sampling dates. Because the compacted trenches are at least 10 m above the seasonally high water table in the area, possible contamination of groundwater via mass transport of dissolved constituents from the compacted trenches would not be expected immediately after the completion of trench compaction. Interpretation of temporal trends in water quality characteristics at TARA will be attempted in 1989 when hydrologic models of the site are developed.

Table 7. Water quality characteristics of monitoring well samples

Well Number	pH	E.C. (dS/m)	Hardness (....mg CaCO ₃ /L..)	Alkalinity (mg/L)	Dissolved Solids (mg/L)	³ H (dpm/mL)	Gross Beta (Bq/L)	Gross Alpha (Bq/L)
Sampling Date - 8-29-88								
TARA-1	6.9	628	222	162	540	1	nd	nd
TARA-2	6.9	635	220	175	580	23	16	4
TARA-3	6.8	1098	385	214	1340	189	nd	nd
TARA-4	6.8	535	185	145	520	208	3	nd
TARA-5	7.1	625	208	153	540	1	nd	6
TARA-6	6.7	883	277	212	780	392	nd	11
TARA-7	6.7	817	300	244	940	38	4	nd
TARA-8	7	448	156	123	480	389	nd	2
TARA-9	7.2	580	153	136	460	13	nd	nd
TARA-10	7.1	469	150	110	420	2591	nd	nd
TARA-11	6.8	1203	401	227	1560	208	19	15
TARA-12	6.8	668	214	182	640	2285	nd	nd
TARA-13	7.3	358	94	86	320	33	nd	nd
TARA-367	7	921	267	182	1200	11	nd	nd
Sampling Date - 6-24-88								
TARA-1	7.5	588	286	210	340	4	nd	nd
TARA-2	7.5	708	362	340	460	32	nd	27
TARA-3	7.4	1120	626	440	900	214	4	4
TARA-4	7.5	550	260	250	340	179	12	6
TARA-5	7.7	664	310	220	460	7	nd	4
TARA-6	7.4	817	406	370	560	515	nd	9
TARA-7	7.2	857	388	360	580	58	nd	15
TARA-8	7.7	545	264	220	340	419	nd	6
TARA-9	7.8	555	238	240	280	14	nd	13
TARA-10	7.8	464	234	210	280	1173	nd	9
TARA-11	7.4	1176	606	330	960	180	15	9
TARA-12	7.5	663	334	310	440	1462	nd	4
TARA-13	7.8	365	162	160	240	21	nd	6
TARA-367	7.3	1295	722	420	1200	18	nd	13
Sampling Date - 11-18-87 through 11-23-87								
TARA-1	6.6	490	454	340	440	4.44	nd	nd
TARA-2	6.8	510	416	382	420	66	nd	nd
TARA-3	6.4	900	718	506	840	264	12	nd
TARA-4	6.7	495	400	366	380	16200	nd	nd
TARA-5	6.8	450	398	308	420	23.4	nd	nd
TARA-6	6.8	660	568	492	600	450	11	nd
TARA-7	6.9	670	550	532	560	102	9	nd

Table 7. (Continued)

Well Number	pH	E.C. (dS/m)	Hardness (....mg CaCO ₃ /L..)	Alkalinity (mg/L)	Dissolved Solids (mg/L)	³ H (dpm/mL)	Gross Beta (Bq/L)	Gross Alpha (Bq/L)
TARA-8	7.2	380	278	258	240	420	2	nd
TARA-9	7.2	455	356	306	200	27	nd	2
TARA-10	6.4	355	286	244	260	780	nd	nd
TARA-11	6.6	890	758	512	940	198	24	6
TARA-12	6.8	600	470	466	1180	492	4	nd
TARA-13	7.1	425	314	292	320	2040	3	nd
TARA-367	6.9	1180	900	554	1020	16.8	nd	nd
TARA-646	7.3	480	352	316	200	0	nd	nd
Sampling Date - 11-4-87								
TARA-1	6.2	650	190	190	380	14	4	nd
TARA-2	6.2	740	262	188	440	158	29	nd
TARA-3	6.4	1100	362	282	640	73	12	nd
TARA-4	6.2	710	226	162	340	1066	nd	nd
TARA-5	6.5	730	256	172	380	9	nd	nd
TARA-6	6.4	900	272	178	440	402	nd	4
TARA-7	6.3	980	302	180	100	278	nd	nd
TARA-8	6.5	560	198	142	920	471	nd	nd
TARA-9	6.5	600	214	152	280	31	nd	nd
TARA-10	6.1	550	212	158	640	660	nd	nd
TARA-11	6.2	1500	702	166	300	272	5	nd
TARA-12	6.2	890	280	182	620	244	nd	nd
TARA-13	5.3	500	180	122	200	9	1	nd
TARA-367	5.9	1600	542	260	840	19	12	nd
POND	6.2	240	136	78	280	na	6	nd
TARA-646	6.1	540	180	154	280	7	61	9
Sampling date - 4-8-87								
TARA-1	6.2	195	200	60	0	5	nd	nd
TARA-2	6.1	325	156	50	220	2	nd	nd
TARA-3	6.2	660	306	76	560	242	nd	nd
TARA-4	6.3	340	114	96	220	552	nd	nd
TARA-5	6.5	470	236	126	440	4	nd	nd
TARA-6	6	495	240	152	200	765	nd	nd
TARA-7	6.1	440	168	98	280	253	nd	nd
TARA-8	6.4	155	106	42	100	38	nd	nd
TARA-9	5.9	340	162	110	1460	1	nd	nd
TARA-10	6	370	132	106	220	75	nd	nd
TARA-11	6.1	1050	552	92	920	292	nd	nd
TARA-12	6.4	850	428	54	640	529	nd	nd
TARA-13	6.5	620	212	94	400	1	nd	nd
TARA-367	7.1	530	302	120	580	8	nd	nd

PRECOMPACTION NONSTANDARD TRENCH PENETRATION TESTS

The rationale for compacting the TARA trenches as a part of the closure demonstration was to reduce trench void volume and stabilize the ground surface prior to constructing a permanent cover. Water-induced trench cover subsidence, which takes place with time, would be undesirable and could cause differential settling, resulting in shear forces that could compromise the performance of an impermeable membrane or other cover components. To quantify the benefits resulting from trench dynamic compaction, soil penetration tests were carried out at 5 positions over each of the 19 waste trenches, as well as at 34 locations over the surrounding soil and saprolite weathered from the Conasauga formation (Fig. 12). A nonstandard test was developed for use over the trenches in order to avoid augering, which is required in the standard soil penetration test (ASTM TEST D 1586 - 67 Penetration test and split barrel sampling of soils), and to prevent bringing contaminated waste to the surface.

The nonstandard test consisted of using a 63.5-kg (140-lb) drill-rig-mounted drop hammer to drive a 4.4-cm diam AW-size drill rod into the soil. The end of the drill rod was fitted with a 5.1-cm diam 60° cone point, and the rod was marked off in 30-cm lengths. At each nonstandard penetration site shown in Fig. 12, the rod was hammered into the soil and the hammer blows for each 30-cm depth were recorded. The deepest penetration hole in each trench was used for installation of a monitoring well. A 5.1-cm-diam stainless steel wire-wound well screen section (1.5 m long) with a tapered well point was hammered into the hole and coupled with threaded flush-joint casing (Johnson Company). Appendices IV (data obtained within trenches) and V (data obtained in Conasauga Shale) summarize the nonstandard trench penetration data by tabulating the number of hammer blows required to drive the drill rod each 30-cm increment of depth. This nonstandard penetration is similar to the Dutch cone penetration test (DCPT) except that the test borehole was not augered out every 46 cm (18 in.) to relieve drill stem friction. Blow count values (penetration resistance) obtained by the DCPT have often been found equivalent to blow count values obtained with the standard penetration test (SPT) (Solymar and Reed 1986). The DCPT, like the herein reported nonstandard penetration test, is not employed frequently in geotechnical work because it does not produce a soil sample for subsequent geotechnical or chemical tests.

An examination of the nonstandard penetration data shows that there is a significantly lower resistance to penetration within the trenches as compared to the resistance to penetration in the undisturbed Conasauga Shale. In some cases, large voids were encountered and one or two blows with the hammer would send the drill rod to the bottom of the trench. This difference, which was expected, is graphically displayed in Fig. 13 by showing the number of drop hammer blows required to achieve each 30 cm (1 ft) of penetration as a function of depth. A marked increase in the number of blows per foot of penetration occurred as a function of depth for setups outside the trenches, whereas within the trenches, this increase was not as apparent. The large voids within trenches apparently resulted in little frictional resistance to drill rod penetration in comparison to the relatively dense soil formation.

Fig. 12. Location of standard and nonstandard penetration test sites.

Fig. 13. Comparison of within-trench and out-of-trench nonstandard penetration tests.

Similar penetration tests conducted within the compacted trenches in FY 1989 will be compared to data shown in Fig. 13 to determine to what extent compaction has stabilized the trenches relative to the undisturbed soil formation.

Figure 13 also provides some useful statistical information for planning the installation of monitoring wells in ORNL burial trenches. More than half of the test penetrations (48 of 93) achieved a depth equal to the nominal bottom of the burial trench (i.e., 14 ft). In the other test penetrations, refusal was encountered at shallower depths due, presumably, to hard waste components such as concrete or steel. In the deeper holes, well casing can be inserted after drill rod removal resulting in a facile installation of an intratrench monitoring well. This installation technique avoids the problem of augering boreholes and exposing drill operators to trench contents. In addition, because the penetration point remained in the hole and the drill rod was cleaned somewhat in the process of removal from the hole, little residual contamination was found on the drill rod even in these >200-mrem/h waste burial trenches. Decontamination of the lower section of drill rod was achieved by wiping the rod with a towel. Only 7 instances of rod contamination were encountered during the 93 intratrench penetration tests. No contamination level was greater than 10 mrem/h at contact, and no drill rod failed decontamination. One penetrometer point housing could not be decontaminated in the field. The waste generated in producing 48 potential intratrench monitoring wells amounted to four cotton towels and one penetrometer point housing. Thus, the penetration well installation technique looks to be a safe and economical method.

STANDARD SOIL PENETRATION TESTS AND SOIL CORE RETRIEVAL

In addition to the nonstandard penetration tests discussed above, standard engineering methods (ASTM TEST 1586-67) of determining soil penetration resistance and collecting undisturbed soil cores were used at the locations shown as circles in Fig. 12. Those 15 locations shown as being above the waste trenches were sites where shallow cores into the trench covers were collected (to 91.4 cm only), whereas the 34 locations shown outside the trenches were sites where cores were collected to a maximum depth of 4.6 m (15 ft).

The standard soil penetration test consisted of driving a 69-cm-long, 0.54-cm-diam, split spoon soil sampler into the ground to a depth of 46 cm (18 in.) using a 63.5-kg drop hammer. The length of the extracted soil core was then measured and scanned with a Geiger-Mueller meter for the presence of radioactivity. The core was immediately removed from the sampler and placed in a prewashed sample bottle for later determination of volatile and semivolatile organics, moisture content, and weight (bulk density). A 15-cm hollow stem auger was then used to drill down to the elevation of the bottom of the soil core and another 46 cm soil core was collected using the split spoon sampler inserted into the hollow center of the auger. As the spoon was being driven into the ground, the blow counts to achieve each 15 cm of depth were recorded in an identical manner to that used in the nonstandard penetration tests. Alternate augering and soil core sampling were repeated in 46-cm increments until either a depth of 4.6 m was reached or the auger

met refusal (no progress with approximately 10 min of drilling) due to hard rock layers.

The standard penetration tests and core retrieval served three purposes (1) to collect standard penetration resistance data that can be correlated to the nonstandard data of Appendices IV and V, (2) to retrieve soil cores from between and around the five TARA trenches for chemical and radiochemical analyses prior to trench compaction, and (3) to obtain a rough picture of the depth to auger refusal at the TARA site. Specifically, core retrieval allowed for determining if there was radioactivity and/or organic contamination present around the trenches prior to compaction, as well as to provide a means of determining soil moisture and bulk density as a function of depth. Appendix VI summarizes the penetration test data obtained from the standard penetration tests, along with the core moisture and bulk density values. Figures 14, 15, and 16 show the relationship between penetration resistance and soil moisture, penetration resistance and bulk density, and moisture and bulk density, respectively. There was an expected positive correlation ($r=0.66$) between penetration resistance and soil bulk density; the denser the material, the more resistance to penetration would be expected. The negative correlation between penetration resistance and moisture content probably results from the inverse correlation between soil moisture content and bulk density; the less dense a soil or saprolite layer, the more water it would be expected to hold against a given moisture tension or drying stress. Additional soil and saprolite variables, such as texture, structure, and lithologic properties, likely contribute to the additional variation in penetration resistance.

The undisturbed soil samples from the standard penetration tests were collected between February 29 and April 8, 1988, and all samples were stored at 4°C until laboratory analyses for organic vapor and radionuclides were initiated. Organic vapor analysis was attempted as a screening tool to select a small group of samples for detailed organic analyses. An organic vapor analyzer, using a photoionization detector (Photovac Tip-II Analyzer), was employed for all measurements. The instrument was turned on until a stable reading was attained. Calibration was carried out using a 32 ppm ethanol standard prepared by injecting 500 μ L of an ethanol saturated atmosphere (48.8-mm partial pressure at 22.0°C) into a 1-L glass bottle fitted with Teflon tubing connectors using a glass-barrel, gas-tight syringe with Teflon plunger. The bottle was shaken for several seconds, was allowed to stand for 30 s, and the intake tubing of the Tip-II analyzer was connected to one of the tube fittings. The readings of the analyzer were recorded after 10, 30, and 60 s from attachment of the analyzer as well as the reading immediately before attachment. The intake tubing of the analyzer was then disconnected from the standardization chamber (bottle) and the standardization repeated twice more. Soil samples in the 1-L bottles were run identically to the standards after being allowed to warm to room temperature (22.0°C). Standards were run at the beginning, middle, and end of each day's group of soil samples. Rather than adjust the span and zero setting controls on the Tip-II analyzer, all readings were linearly adjusted to an equivalent reading for the 32-ppm ethanol standard for the standardization closest to the time of sample analysis. The 30-s reading was

Fig. 14. Relationship between soil penetration resistance and percentage soil moisture at the TARA site.

Fig. 15. Relationship between soil penetration resistance and soil bulk density at the TARA site.

Fig. 16. Relationship between soil moisture and soil bulk density at the TARA site.

found to be the most reproducible of the three time intervals; therefore, this reading was used for sample comparison (Table 8). The location of the sampling positions relative to the five burial trenches is depicted in Fig. 17. A frequency distribution of the adjusted organic vapor analyzer readings over the range of soil samples is depicted in Fig. 18. The range of response was over four orders of magnitude. Subsamples of ten of the high reading samples were prepared by sieving about 100 g of fresh core material to <2 mm; these samples were submitted to the ORNL Analytical Chemistry Division for analysis of volatile (Table 9) and semivolatile (Table 5) organic compounds via EPA method 624.

The selected samples are listed in Table 10 along with the identified and quantified organic species determined. The only unqualified identification in all samples was methylene chloride in the 10- to 100- $\mu\text{g/kg}$ range; all other identified species were either below the quantitation limit or appeared in background blanks also. Clearly, the identified organic species account for only a trivial fraction of the volatile species causing the high organic vapor analyzer readings, e.g., up to 12,800 mg/L of soil atmosphere. It should be pointed out that most of the volatile and semivolatile species analyzed for are not natural products of organic matter decay in soil. The majority of the organic species causing the organic vapor analyzer readings are probably simple decomposition products from plant roots and waste packages (e.g. wood) and do not constitute hazardous materials. Similarly, the utility of the nonspecific organic vapor analyzer as either a screening tool or a field monitoring device must be questioned given the high "background" of natural organic vapors present within the SWSA 6 soils. Also in Table 10, the measured radionuclide activities in these ten soil samples are listed; most of these were near the detection limit for the radionuclide assay, although occasional low levels of ^{137}Cs and/or ^{90}Sr were detected. Obviously, the radionuclides originate from the burial trenches, and it might be expected that if the sources of high organic vapor also originated from the burial trenches, some degree of correlation or ranking similarity might be expected. However, this obviously did not hold true for either the trench perimeter or trench cap samples.

After completion of the organic vapor screening, all soil samples were dried at 105°C for 48 h in their original glass bottles. Samples were reweighed to determine their oven dry weights and moisture contents. A representative subsample of about 100 cm^3 was removed and sieved to <2 mm. All residual soil samples were transferred to seal-lock polyethylene bags for archiving. Into plastic 25-mL scintillation vials, 10.00 g of the sieved soil was weighed and used for assay of ^{137}Cs , ^{60}Co , and ^{90}Sr . These samples were counted for 10 min each using a NaI detector for gamma ray spectroscopy (Cerling and Spalding 1981). The activity of ^{90}Sr was estimated from bremsstrahlung radiation detection in the lower-energy region of the gamma ray spectrum below the ^{137}Cs photopeak region. Crosstalk into this bremsstrahlung window was subtracted using factors determined from ^{137}Cs and ^{60}Co standards in 10-g soil samples and the measured samples activities of ^{137}Cs and ^{60}Co . Other background counts in the bremsstrahlung window were subtracted using soil blanks without added isotopes. Standards of ^{90}Sr in soil were prepared to measure the bremsstrahlung counting efficiency, which generally averaged about 4.4%. The bremsstrahlung method for ^{90}Sr assay is

Fig. 17. Positions for undisturbed soil sampling during standard penetration tests around five TARA burial trenches.

Table 8. Organic vapor analyzer results for the undisturbed soil samples around the TARA burial trenches

Sample Hole	Depth Section Top (in.)	Start Reading (units)	30 Sec. Reading (units)	Standard Reading (units)	Adjusted Reading (units)	Sample Ranking	Log of Adj. Reading
1	0	-4.7	-1.6	18.4	3.8	53	0.579783
1	18	-5.9	-2.6	18.4	4	59	0.602059
1	36	-6	-3	18.4	3.7	50	0.568201
1	54	-5.2	-2.6	18.4	3.2	42	0.505149
1	72	-5.1	-1.9	18.4	3.9	55	0.591064
1	90	-4.8	-1.1	18.4	4.5	72	0.653212
1	108	-3.9	-3.6	3.9	1.7	19	0.230448
2	0	-4.2	-4	3.9	1.1	12	0.041392
2	18	-4.1	-3.8	3.9	1.7	20	0.230448
2	36	-4.1	-4	3.9	0.6	8	-0.22184
2	54	-4.1	-3.9	3.9	1.1	11	0.041392
2	72	-4.2	-4.1	3.9	0.6	7	-0.22184
2	90	-4.2	-4.1	3.9	0.6	5	-0.22184
2	108	-4.2	-4.1	3.9	0.6	6	-0.22184
2	126	-4	-3.3	3.9	4	60	0.602059
2	144	-4.1	-4	3.9	0.6	4	-0.22184
2	162	-4.1	-3.8	3.9	1.7	21	0.230448
3	0	-12.7	-10.8	13.1	3.2	43	0.505149
3	18	-12.4	-10.7	13.1	2.9	39	0.462397
3	36	-12.6	-9.9	13.1	4.6	74	0.662757
3	54	-11.4	-10.4	13.1	1.7	22	0.230448
3	72	-11.4	-10.3	13.1	1.9	24	0.278753
3	90	-11.8	-10.4	13.1	2.4	30	0.380211
3	108	-11.4	-10.5	13.1	1.5	17	0.176091
3	126	-11.6	-10.4	13.1	2.1	28	0.322219
3	144	-11.8	-10.3	13.1	2.6	31	0.414973
3	162	-11.4	-8.5	13.1	5	85	0.698970
4	0	-14.5	-11.5	13.1	5.1	89	0.707570
4	18	-14.3	-11.6	13.1	4.6	75	0.662757
4	36	-12	-9.7	13.1	3.9	56	0.591064
4	54	-13.7	-11.1	13.1	4.4	70	0.643452
4	72	-12.1	-9.9	13.1	3.8	54	0.579783
5	0	-10.3	-8.6	8.7	4.4	71	0.643452
5	18	-10.6	-8.6	8.7	5.1	91	0.707570
5	36	-10.2	-7.8	8.7	6.2	113	0.792391
5	54	-10.6	-8.5	8.7	5.4	95	0.732393
5	72	-8	-4.5	8.7	9	141	0.954242
5	90	-10.3	-7.9	8.7	6.2	112	0.792391
5	108	-10.1	-8.1	8.7	5.1	90	0.707570
6	0	-9.4	-7.5	8.7	4.9	83	0.690196
6	18	-8.5	-5.4	8.7	8	136	0.903089
6	36	-9.1	-3.1	8.7	15.4	171	1.187520
6	54	-10.1	-7.4	8.7	7	126	0.845098
6	72	-8.9	-1.2	8.7	19.8	190	1.296665
6	90	-5.6	-2.3	3.3	22.4	195	1.350248

Table 8. (Continued)

Sample Hole	Depth Section Top (in.)	Start Reading (units)	30 Sec. Reading (units)	Standard Reading (units)	Adjusted Reading (units)	Sample Ranking	Log of Adj. Reading
6	108	-9.2	-6.4	8.7	7.2	129	0.857332
6	126	1.5	325	3.3	2195.9	256	3.341612
6	144	-8.9	0.1	8.7	23.2	199	1.365487
6	162	-9.6	0.7	8.7	26.5	210	1.423245
7	0	-10.5	-7.6	4.3	15.1	170	1.178976
7	18	-10.6	-5.8	13.1	8.2	137	0.913813
7	36	-10.5	-7.9	4.3	13.5	161	1.130333
7	54	-12	-9.8	4.3	11.5	152	1.060697
7	72	-12.3	-9.6	4.3	14.1	165	1.149219
7	90	-9.7	-6.3	4.3	17.7	184	1.247973
7	108	-11.8	-10	4.3	9.4	143	0.973127
8	0	-11.4	-9.3	13.1	3.6	49	0.556302
8	18	-11.4	-9.4	13.1	3.4	46	0.531478
8	36	-9.7	-5.4	8.7	11.1	150	1.045322
8	54	-3	1884	3.3	12808.7	259	4.107505
8	72	-13	-9.5	13.1	6	111	0.778151
9	0	-1.3	0.4	13.8	2.8	33	0.447158
9	18	-0.8	0	13.8	1.3	15	0.113943
9	36	-5.2	0	13.8	8.4	139	0.924279
9	54	-19.6	-5.1	12.3	26.4	209	1.421603
9	72	-9.3	-2.8	13.1	11.1	151	1.045322
9	90	-5.5	-3.8	13.8	2.8	34	0.447158
9	108	1.2	5.6	13.8	7.1	127	0.851258
9	126	-10.2	-4.3	13.1	10.1	147	1.004321
9	144	-6.8	-4.4	13.8	3.9	57	0.591064
9	162	-4.8	-0.1	13.8	7.6	134	0.880813
10	0	-7.4	-6.3	13.8	1.8	23	0.255272
10	18	-2.8	-1.1	13.8	2.8	35	0.447158
10	36	-10.3	-8.1	8.7	5.7	102	0.755874
10	54	-5.6	-1.9	3.3	25.1	204	1.399673
10	72	-5.7	-2.3	3.3	23.1	198	1.363611
10	90	-11	4.1	13.1	25.8	207	1.411619
10	108	-5.7	-2.4	3.3	22.4	196	1.350248
10	126	-5.5	-2.4	3.3	21	193	1.322219
10	144	-5.4	-2.1	3.3	22.4	197	1.350248
10	162	-6	-2.2	3.3	25.8	206	1.411619
11	0	-11.6	-10.9	13.1	1.2	13	0.079181
11	18	-10.7	-8.9	13.1	3.1	41	0.491361
11	36	-11.9	-10.6	13.1	2.2	29	0.342422
11	54	-7.3	-3.9	10.5	7.3	130	0.863322
11	72	-10.6	-8.4	4.3	11.5	153	1.060697
11	90	-12	-9.9	4.3	10.9	149	1.037426
11	108	-11.9	-9.9	4.3	10.4	148	1.017033
11	126	-8.4	-5.1	4.3	17.2	183	1.235528
11	144	-8.5	-0.9	4.3	39.6	221	1.597695
11	162	-11.9	-10.1	4.3	9.4	144	0.973127

Table 8. (Continued)

Sample Hole	Depth Section Top (in.)	Start Reading (units)	30 Sec. Reading (units)	Standard Reading (units)	Adjusted Reading (units)	Sample Ranking	Log of Adj. Reading
12	0	-10.6	-9.3	5.2	5.6	97	0.748188
12	18	-10.6	-9.1	5.2	6.5	115	0.812913
12	36	-10.9	-8.9	5.2	8.6	140	0.934498
12	54	-10.6	-9	5.2	6.9	120	0.838849
12	72	-10.9	-9.2	5.2	7.3	131	0.863322
12	90	-19.4	-4.4	12.3	27.3	213	1.436162
12	108	-20.2	-2.5	12.3	32.2	219	1.507855
12	126	-12.1	-9.3	13.1	4.8	82	0.681241
13	0	-4	145.7	6.6	508.1	250	2.705949
13	18	-6.5	19.6	1.8	324.8	247	2.511616
13	36	-3.3	3.6	6.6	23.4	200	1.369215
13	54	-4.5	8	6.6	42.4	224	1.627365
13	72	-6.4	-2.3	1.8	51	225	1.707570
13	90	-4.1	7.5	6.6	39.4	220	1.595496
13	108	-6.7	-3.4	1.8	41.1	223	1.613841
13	126	-3.6	3.5	6.6	24.1	202	1.382017
13	144	-3.6	3.4	6.6	23.8	201	1.376576
13	162	-1.2	7.5	6.6	29.5	216	1.469822
14	18	-7.2	-2	1.8	64.7	229	1.810904
14	36	-7.2	-4.6	3.9	14.9	169	1.173186
14	54	-2.6	5.3	6.6	26.8	211	1.428134
14	72	-7.1	-4.8	3.9	13.2	156	1.120573
14	90	-7.1	-4.6	3.9	14.4	166	1.158362
14	108	-7.1	-4.8	3.9	13.2	158	1.120573
14	126	-7.2	-4.5	3.9	15.5	172	1.190331
14	144	-7	-4.7	3.9	13.2	157	1.120573
14	162	-7.1	-4.5	3.9	14.9	168	1.173186
15	0	-11.6	-8.4	13.1	5.5	96	0.740362
15	18	-10.7	-6.9	13.1	6.5	116	0.812913
15	36	-11.9	-9	13.1	5	86	0.698970
15	54	-11.3	-6.7	13.1	7.9	135	0.897627
15	72	-11.5	-8.6	13.1	5	88	0.698970
15	90	-12.4	-9.1	13.1	5.6	98	0.748188
15	108	-11.8	-8.9	13.1	5	87	0.698970
15	126	-12.7	-8.8	13.1	6.7	117	0.826074
15	144	-10.4	-7.9	13.1	4.3	67	0.633468
15	162	-11	-7.6	13.1	5.8	110	0.763427
16	0	-10.7	-9.4	5.2	5.6	100	0.748188
16	18	-10.4	-9.1	5.2	5.6	99	0.748188
16	36	-2.9	-2.8	10.5	0.2	1	-0.69897
16	54	-2.6	-1.9	10.5	1.5	18	0.176091
16	72	-1.8	2.8	10.5	9.8	145	0.991226
16	90	-6.4	-4.5	10.5	4.1	64	0.612783
16	108	-10.4	-9.3	5.2	4.7	79	0.672097
16	126	-10.5	-8.2	5.2	9.9	146	0.995635
17	0	-4.9	-3.9	18.4	1.2	14	0.079181

Table 8. (Continued)

Sample Hole	Depth Section Top (in.)	Start Reading (units)	30 Sec. Reading (units)	Standard Reading (units)	Adjusted Reading (units)	Sample Ranking	Log of Adj. Reading
17	18	-0.6	3.9	13.8	7.3	132	0.863322
17	36	-6.1	-3.1	18.4	3.7	51	0.568201
17	54	-6.4	-2.6	18.4	4.6	76	0.662757
17	72	1.5	2.3	13.8	1.3	16	0.113943
17	90	0.7	2.4	13.8	2.8	36	0.447158
17	108	0.9	3.9	13.8	4.9	84	0.690196
17	126	-6	-3.1	18.4	3.5	48	0.544068
17	144	1.4	3.9	13.8	4.1	65	0.612783
17	162	1.4	5.8	13.8	7.1	128	0.851258
18	0	-7	-4.6	3.9	13.8	162	1.139879
18	18	-5.9	-2.6	18.4	4	62	0.602059
18	36	-3.6	3.3	6.4	24.2	203	1.383815
18	54	-5.2	-3	18.4	2.7	32	0.431363
18	72	-2.4	4.3	18.4	8.2	138	0.913813
18	90	-2.8	0.2	18.4	3.7	52	0.568201
18	108	-1.4	1.9	18.4	4	61	0.602059
18	126	-2.2	0.6	18.4	3.4	47	0.531478
18	144	-0.6	3.3	18.4	4.7	80	0.672097
18	162	-2.5	0.2	18.4	3.3	45	0.518513
19	0	-6.2	-4.9	10.5	2.8	37	0.447158
19	18	-3.2	-3.1	10.5	0.2	2	-0.69897
19	36	-2.4	-1.5	10.5	1.9	25	0.278753
19	54	-0.1	0.2	10.5	0.6	9	-0.22184
19	72	-6.7	-4.7	10.5	4.3	68	0.633468
19	90	-1.6	-0.7	10.5	1.9	26	0.278753
19	108	-1.1	-0.2	10.5	1.9	27	0.278753
19	126	-10.7	-9.1	5.2	6.9	121	0.838849
19	144	-10.3	-9	5.2	5.6	101	0.748188
19	162	-12.1	-9.3	5.2	12.1	154	1.082785
20	0	-5.3	-0.9	3.3	29.9	217	1.475671
20	18	-5.6	-0.9	6.6	16	175	1.204119
20	36	-5.5	-0.7	6.6	16.3	179	1.212187
20	54	-5.9	-1.3	3.3	31.2	218	1.494154
20	72	-5.5	-0.9	6.6	15.6	174	1.193124
20	90	-5.6	-0.9	6.6	16	176	1.204119
20	108	-5.2	-1.1	6.6	13.9	164	1.143014
20	126	-0.5	-0.4	6.6	0.3	3	-0.52287
20	144	-3.7	1.3	6.6	17	181	1.230448
20	162	-5.3	-0.5	6.6	16.3	178	1.212187
21	0	-6.8	-5.8	3.9	5.7	105	0.755874
21	18	-7	-6	3.9	5.7	103	0.755874
21	36	-5.7	-4.6	3.9	6.3	114	0.799340
21	54	-3.2	-0.8	3.9	13.8	163	1.139879
21	72	-7.3	-4.5	3.9	16.1	177	1.206825
21	90	-6.8	-5.8	3.9	5.7	104	0.755874
21	108	-5.8	-5.1	3.9	4	63	0.602059

Table 8. (Continued)

Sample Hole	Depth Section Top (in.)	Start Reading (units)	30 Sec. Reading (units)	Standard Reading (units)	Adjusted Reading (units)	Sample Ranking	Log of Adj. Reading
21	126	-5	-3.8	3.9	6.9	122	0.838849
22	0	-7.3	-5	3.9	13.2	159	1.120573
22	18	-7.1	-4.6	3.9	14.4	167	1.158362
22	36	-6.2	-5	3.9	6.9	124	0.838849
22	54	-7.5	-4.8	3.9	15.5	173	1.190331
22	72	-19.6	-4.3	12.3	27.9	214	1.445604
22	90	-6	-2.5	18.4	4.3	69	0.633468
22	108	-3.8	-1.5	18.4	2.8	38	0.447158
22	126	-6	-0.5	18.4	6.7	118	0.826074
22	144	-5.2	-1.8	18.4	4.1	66	0.612783
22	162	-3.7	0	18.4	4.5	73	0.653212
2A	0	-5.8	7.2	1.8	161.8	239	2.208978
2A	18	-6.1	3.3	1.8	117	237	2.068185
2B	0	-11.9	-9.3	8.7	6.7	119	0.826074
2B	18	-10	-7.9	5.2	9	142	0.954242
2C	0	-7.1	-3.3	18.4	4.6	77	0.662757
2C	18	-5.6	-3	18.4	3.2	44	0.505149
3A	0	-0.1	211	3.3	1432.9	255	3.156215
3A	18	-0.2	132.5	3.3	900.8	253	2.954628
3B	0	-10.8	-8.6	8.7	5.7	106	0.755874
3B	18	-10.3	-8.6	5.2	7.3	133	0.863322
3C	0	-9.9	-8.4	8.7	3.9	58	0.591064
3C	18	-11	-8.8	8.7	5.7	107	0.755874
4A	0	-5.9	5.7	1.8	144.4	238	2.159567
4A	18	-4	184	1.8	2339.6	257	3.369141
4B	0	-4.5	64.9	1.8	863.6	252	2.936312
4B	18	-2.3	2	18.4	5.2	94	0.716003
4C	0	-10	-8.4	5.2	6.9	125	0.838849
4C	18	-10.6	-8.6	8.7	5.1	92	0.707570
5A	0	-3.5	105.6	1.8	1357.7	254	3.132803
5A	18	-5.3	44	1.8	613.5	251	2.787814
5B	0	-5.8	7.8	1.8	169.2	240	2.228400
5C	0	-10	-8.9	5.2	4.7	81	0.672097
5C	18	-11	-8.8	8.7	5.7	108	0.755874
6A	0	-3.7	0.1	18.4	4.6	78	0.662757
6A	18	-1.4	1	18.4	2.9	40	0.462397
6B	0	-5.4	324	1.8	4099.2	258	3.612699
6B	18	-6.1	2.9	1.8	112	235	2.049218
6C	0	-10.6	-8.6	8.7	5.1	93	0.707570
6C	18	-11.4	-9.2	8.7	5.7	109	0.755874

Relative Organic Vapor Analyzer Readings for TARA Soil Samples

Fig. 18. Frequency distribution of adjusted organic vapor analyzer readings for TARA soil samples.

Table 9. Volatile organic compounds analyzed for in TARA soil samples

Compound	CAS No.	Detection Limit ($\mu\text{g}/\text{kg}$)
Chloromethane	74-87-3	10
Bromomethane	74-83-9	10
Vinyl chloride	75-01-4	10
Chloroethane	75-00-3	10
Methylene chloride	75-09-2	10
Acetone	67-64-1	10
Carbon disulfide	75-15-0	5
1,1-Dichloroethene	75-35-4	5
1,1-Dichloroethane	75-34-3	5
1,2-Dichloroethene	540-59-0	5
Chloroform	67-66-3	5
1,2-Dichloroethane	107-06-2	5
2-Butanone	78-93-3	10
1,1,1-Trichloroethane	71-55-6	5
Carbon tetrachloride	56-23-5	5
Vinyl acetate	108-05-4	10
Bromodichloromethane	75-27-4	5
1,2-Dichloropropane	78-87-5	5
cis-1,3-Dichloropropene	10061-01-5	5
Trichloroethene	79-01-6	5
Dibromochloromethane	124-48-1	5
1,1,2-Trichloroethane	79-00-5	5
Benzene	71-43-2	5
trans-1,3-Dichloropropene	10061-02-06	5
Bromoform	75-25-2	5
4-Methyl-2-pentanone	108-10-1	10
2-Hexanone	591-78-6	10
Tetrachloroethene	127-18-4	5
1,1,2,2-Tetrachloroethane	79-34-5	5
Toluene	108-88-3	5
Chlorobenzene	108-90-7	5
Ethylbenzene	100-41-4	5
Styrene	100-42-5	5
Xylene (total)	1330-20-7	5

Table 10. Organic compounds detected in TARA soil samples selected from organic vapor analyzer responses

Sample Position	12	8	6B	6	5A
Depth Section	108-126"	54-72"	0-18"	126-144"	18-36"
Vapor Analyzer Rank of 259 soil samples	40	1	2	4	8
Relative Vapor Analyzer Reading	32	12800	4100	2200	614
Organic Compound (ug/kg):					
Methylenechloride	17	53	82	97	107
Acetone	22B	38B	24B	103B	66B
Diethylphthalate	83J	nd	nd	130J	82J
Di-n-butylphthalate	39J	28J	nd	28J	nd
bis-(2-Ethylhexyl)-phthalate	930B	840B	1050B	87B	82B
Radionuclides (dpm/g):					
¹³⁷ Cs	<0.5	<0.5	28.3	<0.5	<0.5
⁹⁰ Sr	59.9	<1.0	92.2	<1.0	<1.0
⁶⁰ Co	<0.5	<0.5	<0.5	<0.5	<0.5

(cont.)					
Sample Position	22	9	13	3A	4A
Depth Section	72-90"	54-72"	18-36"	18-36"	18-36"
Vapor Analyzer Rank of 259 soil samples	45	50	12	6	3
Relative Vapor Analyzer Reading	28	26	325	901	2340
Organic Compound (ug/kg):					
Methylenechloride	74	65	96	78	81
Acetone	64B	44B	27B	44B	48B
Diethylphthalate	130J	145J	161J	172J	126J
Di-n-butylphthalate	26J	26J	nd	21J	nd
bis-(2-Ethylhexyl)-phthalate	500B	600B	1050B	1530B	4025B
Radionuclides (dpm/g):					
¹³⁷ Cs	5.0	8.5	<0.5	<0.5	<0.5
⁹⁰ Sr	<1.0	60.3	<1.0	<1.0	<1.0
⁶⁰ Co	<0.5	<0.5	<0.5	<0.5	<0.5

NOTES:

nd - not detected.

B - This data qualifier appears for a compound which was detected in both the sample and its associated blank.

J - Indicates that the quantitative value is estimated. It appears after a value which is below the quantitation limit but above the detection limit.

known to be highly dependent on counting geometry and sample material characteristics, but these were held constant for all samples and standards. The reported ^{90}Sr activities would also include other hard-beta emitters, other than ^{137}Cs and ^{60}Co , which might also produce bremsstrahlung emission. Unambiguous methods for the determination of ^{90}Sr in soil involve complete sample dissolution and radiochemical fractionation with final beta counting. The savings in cost and time were judged adequate compensation for the increase in ease and speed of sample assay. It is reassuring that the technique does not produce false negatives; if ^{90}Sr is present in a soil sample above the detection limit of 1.0 dpm/g, then it is detected.

Results of these radionuclide assays are presented in Table 11. Two general observations about this group of samples are worthy of mention. First, although all these samples were taken within a few feet of trench boundaries, relatively few showed significant levels of contamination particularly at depth; only the bottom section of position 9 (between trenches 3 and 4) exhibited a high level (186,000 dpm/g) of ^{90}Sr at the 162- to 180-in. interval. Lower levels of contamination by several isotopes were found in the samples just below the surface (i.e., >18 in. and <54 in.) in samples both off and over the trenches. The presence of radioactivity at shallow depth at positions not directly over the trenches indicates that the radioactivity may have been spread to these positions during either the attempted package retrieval in 1973 or during the installation of the shallow bentonite seal in 1976. It would seem unlikely that this contamination would have resulted from the water filling tests in July and October 1987 because most of the contamination is associated with ^{137}Cs . Not only is ^{137}Cs strongly adsorbed to soil and, hence, immobile in these soils (Cerling and Spalding 1981), but samples of the trench leachate, collected from the trenches during the water filling tests, showed mostly hard-beta activity associated with ^{90}Sr (Table 15, next section), not ^{137}Cs . It should also be noted that only one sample, with the highest level of ^{90}Sr contamination, was detected using the field Geiger-Mueller counter as a screening tool.

MEASUREMENT OF TRENCH VOID VOLUMES

An important quantitative indicator of the benefits of trench compaction is the reduction of trench voids which is achieved. The method selected to measure these voids prior to trench compaction was the filling of the five trenches with a known volume of water, taking into consideration the losses due to seepage into the surrounding soil that takes place during filling. Water was pumped from the emergency waste holding basin to the north of the TARA site into one of the five trenches. Trench 2 was filled between October 26 and 28, 1987, and received 55 m^3 (14,555 gal) of water. Trench 3 was filled between October 19 and 20, 1987, and received 53 m^3 (14,071 gal) of water. Trench 4 was filled between July 27 and August 3, 1987, and received 100 m^3 (26,422 gal) of water. Trench 5 was filled between October 22 and 23, 1987, and received 77 m^3 (20,367 gal) of water. Trench 6 was filled between October 28 and November 2, 1987, and received 55 m^3 (14,440 gal) of water.

Water was delivered to the trenches via a 5-cm (2-in.) rubber hose run to the bottom of one of the intratrench wells. The water delivery was allowed

Table 11. Radionuclides in soil samples from around the TARA burial trenches

Sample Position	Section		^{137}Cs (dpm/g)	^{60}Co (dpm/g)	^{90}Sr (dpm/g)
	Top (in.)	Bottom (in.)			
1	0	18	30.5	<0.5	192.1
1	18	36	<0.5	<0.5	76.3
1	36	54	<0.5	<0.5	<1.0
1	54	72	<0.5	<0.5	<1.0
1	72	90	<0.5	<0.5	<1.0
1	90	108	<0.5	<0.5	<1.0
1	108	126	<0.5	<0.5	<1.0
2	0	18	121.9	<0.5	<1.0
2	18	36	<0.5	<0.5	<1.0
2	36	54	<0.5	<0.5	133.5
2	54	72	<0.5	<0.5	<1.0
2	72	90	<0.5	<0.5	<1.0
2	90	108	<0.5	<0.5	16.3
2	108	126	<0.5	<0.5	<1.0
2	126	144	<0.5	<0.5	<1.0
2	144	162	<0.5	<0.5	<1.0
2	162	180	<0.5	<0.5	<1.0
3	0	18	<0.5	<0.5	117.2
3	18	36	<0.5	<0.5	<1.0
3	36	54	29.8	<0.5	7.8
3	54	72	<0.5	<0.5	<1.0
3	72	90	2.8	<0.5	<1.0
3	90	108	<0.5	<0.5	<1.0
3	108	126	<0.5	<0.5	<1.0
3	126	144	<0.5	<0.5	<1.0
3	144	162	<0.5	<0.5	<1.0
3	162	180	<0.5	<0.5	<1.0
4	0	18	<0.5	<0.5	<1.0
4	18	36	<0.5	<0.5	46.3
4	36	54	<0.5	9.5	<1.0
4	54	72	<0.5	<0.5	<1.0
4	72	90	<0.5	<0.5	122.6
5	0	18	<0.5	<0.5	<1.0
5	18	36	3604.5	<0.5	1481.4
5	36	54	<0.5	<0.5	359.7
5	54	72	4.3	<0.5	39.4
5	72	90	<0.5	<0.5	<1.0
5	90	108	<0.5	<0.5	<1.0
5	108	126	425.9	<0.5	<1.0
6	0	18	<0.5	<0.5	32.7
6	18	36	58.8	<0.5	3.7
6	36	54	<0.5	<0.5	<1.0
6	54	72	<0.5	<0.5	<1.0
6	72	90	<0.5	<0.5	<1.0
6	90	108	43.2	<0.5	<1.0

Table 11. (Continued)

Sample Position	Section		^{137}Cs (dpm/g)	^{60}Co (dpm/g)	^{90}Sr (dpm/g)
	Top (in.)	Bottom (in.)			
6	108	126	<0.5	<0.5	<1.0
6	126	144	<0.5	<0.5	<1.0
6	144	162	<0.5	<0.5	<1.0
6	162	180	3.5	<0.5	<1.0
7	0	18	<0.5	<0.5	<1.0
7	18	36	<0.5	<0.5	<1.0
7	36	54	<0.5	<0.5	2.7
7	54	72	<0.5	<0.5	40.9
7	72	90	<0.5	<0.5	<1.0
7	90	108	<0.5	<0.5	<1.0
7	108	126	<0.5	<0.5	<1.0
8	0	18	<0.5	<0.5	<1.0
8	18	36	<0.5	<0.5	<1.0
8	36	54	<0.5	<0.5	<1.0
8	54	72	<0.5	<0.5	<1.0
8	72	90	<0.5	<0.5	<1.0
9	0	18	60.2	<0.5	<1.0
9	18	36	<0.5	<0.5	<1.0
9	36	54	<0.5	<0.5	<1.0
9	54	72	8.5	<0.5	60.3
9	72	90	<0.5	<0.5	<1.0
9	90	108	9.9	<0.5	<1.0
9	108	126	<0.5	<0.5	<1.0
9	126	144	<0.5	9.5	<1.0
9	144	162	<0.5	<0.5	<1.0
9	162	180	<0.5	7846.2	186501.4
10	0	18	<0.5	<0.5	392.4
10	18	36	17	<0.5	<1.0
10	36	54	<0.5	<0.5	57.2
10	54	72	1.4	<0.5	112.3
10	72	90	31.2	<0.5	112
10	90	108	2.8	<0.5	<1.0
10	108	126	<0.5	<0.5	<1.0
10	126	144	<0.5	<0.5	<1.0
10	144	162	<0.5	<0.5	<1.0
10	162	180	<0.5	<0.5	<1.0
11	0	18	<0.5	<0.5	<1.0
11	18	36	53.2	<0.5	<1.0
11	36	54	<0.5	<0.5	<1.0
11	54	72	4.3	<0.5	<1.0
11	72	90	<0.5	<0.5	<1.0
11	90	108	<0.5	<0.5	<1.0
11	108	126	<0.5	<0.5	<1.0
11	126	144	<0.5	<0.5	<1.0
11	144	162	<0.5	<0.5	<1.0
11	162	180	<0.5	<0.5	<1.0

Table 11. (Continued)

Sample Position	Section		^{137}Cs (dpm/g)	^{60}Co (dpm/g)	^{90}Sr (dpm/g)
	Top (in.)	Bottom (in.)			
12	0	18	<0.5	<0.5	<1.0
12	18	36	23.4	<0.5	<1.0
12	36	54	<0.5	<0.5	<1.0
12	54	72	<0.5	<0.5	68.1
12	72	90	<0.5	<0.5	<1.0
12	90	108	<0.5	<0.5	<1.0
12	108	126	<0.5	<0.5	59.9
12	90	108	<0.5	<0.5	<1.0
12	108	126	<0.5	<0.5	59.9
12	126	144	<0.5	<0.5	<1.0
13	0	18	2.1	<0.5	7.7
13	18	36	<0.5	<0.5	<1.0
13	36	54	<0.5	<0.5	<1.0
13	54	72	<0.5	<0.5	19.1
13	72	90	<0.5	<0.5	<1.0
13	90	108	31.2	<0.5	<1.0
13	108	126	20.6	<0.5	<1.0
13	126	144	<0.5	<0.5	<1.0
13	144	162	<0.5	<0.5	<1.0
13	162	180	<0.5	<0.5	<1.0
14	0	18	<0.5	<0.5	<1.0
14	18	36	15.6	<0.5	<1.0
14	36	54	<0.5	<0.5	<1.0
14	54	72	<0.5	<0.5	<1.0
14	72	90	<0.5	<0.5	<1.0
14	90	108	<0.5	<0.5	<1.0
14	108	126	<0.5	<0.5	<1.0
14	126	144	<0.5	<0.5	<1.0
14	144	162	14.2	<0.5	<1.0
14	162	180	<0.5	<0.5	<1.0
15	0	18	<0.5	<0.5	<1.0
15	18	36	<0.5	<0.5	<1.0
15	36	54	<0.5	<0.5	<1.0
15	54	72	<0.5	<0.5	<1.0
15	72	90	<0.5	<0.5	<1.0
15	90	108	<0.5	<0.5	<1.0
15	108	126	<0.5	<0.5	<1.0
15	126	144	<0.5	<0.5	<1.0
15	144	162	<0.5	<0.5	<1.0
15	162	180	<0.5	<0.5	<1.0
16	0	18	474.1	530.2	1210.9
16	18	36	134.7	111.2	410.8
16	36	54	107	<0.5	290.8
16	54	72	<0.5	<0.5	<1.0
16	72	90	<0.5	<0.5	<1.0
16	90	108	<0.5	<0.5	<1.0

Table 11. (Continued)

Sample Position	Section		^{137}Cs (dpm/g)	^{60}Co (dpm/g)	^{90}Sr (dpm/g)
	Top (in.)	Bottom (in.)			
16	108	126	<0.5	<0.5	<1.0
16	126	144	<0.5	<0.5	<1.0
17	0	18	<0.5	<0.5	<1.0
17	18	36	59.5	<0.5	76.2
17	36	54	14.9	<0.5	<1.0
17	54	72	<0.5	<0.5	<1.0
17	72	90	<0.5	<0.5	<1.0
17	90	108	<0.5	<0.5	<1.0
17	108	126	<0.5	16.6	<1.0
17	126	144	<0.5	<0.5	<1.0
17	144	162	2.1	<0.5	<1.0
17	162	180	<0.5	<0.5	<1.0
18	0	18	<0.5	<0.5	<1.0
18	18	36	<0.5	<0.5	<1.0
18	36	54	775.3	42.6	220.2
18	54	72	82.2	<0.5	16.1
18	72	90	<0.5	<0.5	<1.0
18	90	108	<0.5	<0.5	<1.0
18	108	126	<0.5	<0.5	<1.0
18	126	144	<0.5	<0.5	<1.0
18	144	162	<0.5	33.1	147.1
18	162	180	<0.5	<0.5	<1.0
19	0	18	<0.5	<0.5	<1.0
19	18	36	38.3	<0.5	<1.0
19	36	54	<0.5	<0.5	<1.0
19	54	72	1.4	<0.5	<1.0
19	72	90	<0.5	<0.5	<1.0
19	90	108	<0.5	<0.5	<1.0
19	108	126	<0.5	<0.5	<1.0
19	126	144	<0.5	<0.5	<1.0
19	144	162	<0.5	<0.5	<1.0
19	162	180	<0.5	<0.5	<1.0
20	0	18	19.1	<0.5	<1.0
20	18	36	<0.5	<0.5	<1.0
20	36	54	<0.5	<0.5	<1.0
20	54	72	<0.5	<0.5	<1.0
20	72	90	<0.5	<0.5	<1.0
20	90	108	<0.5	<0.5	<1.0
20	108	126	<0.5	<0.5	<1.0
20	126	144	<0.5	<0.5	261.6
20	144	162	22	<0.5	1
20	162	180	<0.5	<0.5	<1.0
21	0	18	<0.5	<0.5	<1.0
21	18	36	<0.5	<0.5	<1.0
21	36	54	<0.5	<0.5	<1.0
21	54	72	<0.5	<0.5	<1.0

Table 11. (Continued)

Sample Position	Section		^{137}Cs (dpm/g)	^{60}Co (dpm/g)	^{90}Sr (dpm/g)
	Top (in.)	Bottom (in.)			
21	72	90	<0.5	14.2	<1.0
21	90	108	<0.5	<0.5	<1.0
21	108	126	<0.5	<0.5	<1.0
21	126	144	<0.5	<0.5	<1.0
22	0	18	<0.5	<0.5	<1.0
22	18	36	92.1	<0.5	<1.0
22	36	54	<0.5	20.1	<1.0
22	54	72	<0.5	<0.5	<1.0
22	72	90	5	<0.5	<1.0
22	90	108	<0.5	<0.5	<1.0
22	108	126	<0.5	<0.5	<1.0
22	126	144	<0.5	<0.5	<1.0
22	144	162	<0.5	<0.5	<1.0
22	162	180	<0.5	<0.5	<1.0
2A	0	18	50.3	<0.5	19.6
2A	18	36	7779.6	<0.5	<1.0
2B	0	18	<0.5	<0.5	<1.0
2B	18	36	644.9	<0.5	<1.0
2C	0	18	39	<0.5	<1.0
2C	18	36	0.7	<0.5	<1.0
3A	0	18	<0.5	<0.5	<1.0
3A	18	36	<0.5	<0.5	<1.0
3B	0	18	11.3	<0.5	<1.0
3B	18	36	856.1	<0.5	<1.0
3C	0	18	<0.5	<0.5	<1.0
3C	18	36	<0.5	<0.5	<1.0
4A	0	18	7.8	<0.5	<1.0
4A	18	36	<0.5	<0.5	<1.0
4B	0	18	12	<0.5	90.4
4B	18	36	10.6	<0.5	<1.0
4C	0	18	15.6	<0.5	125.5
4C	18	36	107	<0.5	<1.0
5A	0	18	<0.5	<0.5	<1.0
5A	18	36	110.6	<0.5	562.9
5B	0	18	<0.5	<0.5	<1.0
5B	18	36	1255.1	<0.5	<1.0
5C	0	18	<0.5	<0.5	<1.0
5C	18	36	854	34.3	<1.0
6A	0	18	<0.5	<0.5	<1.0
6A	18	36	<0.5	<0.5	<1.0
6B	0	18	28.3	<0.5	92.2
6B	18	36	322.5	29.6	529
6C	0	18	<0.5	<0.5	<1.0
6C	18	36	2679.7	<0.5	<1.0

to continue overnight under continuous surveillance until water level monitoring in additional intratrench wells indicated that the water was within approximately 0.5 m of the ground surface. At this point, the flow rate was either adjusted downward to determine the minimum flow required to maintain the existing head or turned off. When the pump was turned off, the head in the observation wells was monitored periodically until the trench was completely drained. This made possible the determination of seepage rates required to correct for seepage during the water delivery interval and indicated when it would be possible to begin the next water pump-in test in the adjacent trench. Water levels, or more frequently the lack of standing water, in neighboring trenches were also monitored during the filling and draining intervals to identify any hydrologic connection among the burial trenches. Among the five trenches at the eastern end of the TARA site, no interconnection of burial trenches was observed during the filling tests. Figures 19 through 23 summarize the intratrench well hydrographs during the water pump-in tests for trenches 2 through 6, respectively. Water levels in the 15 groundwater monitoring wells were measured periodically during the trench-filling process to determine which, if any, of the wells would respond to trench filling. Results are included in the well hydrographs of Appendix III.

Fig. 19. Water pump-in test hydrograph for TARA trench 2.

Fig. 20. Water pump-in test hydrograph for TARA trench 3.

Fig. 21. Water pump-in test hydrograph for TARA trench 4.

Fig. 22. Water pump-in test hydrograph for TARA trench 5.

Fig. 23. Water pump-in test hydrograph for TARA trench 6.

To determine the trench voids from the water pump-in test data, each trench was divided into several regions (horizontal cross sections of varying but defined thickness) starting at the trench bottom and moving upward until the last trench region was immediately below the trench soil cover. The area and thickness of each region was recorded along with the flow rate maintained while filling that region as well as the region's filling and emptying times. A seepage rate for each region was calculated as

$$X_0 = (X_1 * T_1) / (T_0 + T_1)$$

where, X_0 - seepage rate, m^3/h
 X_1 - water delivery rate, m^3/h
 T_1 - region's filling time, h
 T_0 - region's emptying time, h.

A net filling rate for each region was then calculated as

$$N = X_1 - X_0$$

where, N - net filling rate, m^3/h
 X_1 - water delivery rate, m^3/h
 X_0 - seepage rate, m^3/h .

Finally, the region void volume was calculated as

$$V_r = (X_1 * T_1) - (X_0 * T_1)$$

where, V_r - void volume of the region, m^3
 X_1 , X_0 , T_1 - previously defined.

The regional void volumes could then be summed to yield the total water-accessible trench void volume, and this, in turn, could be expressed as a percentage of the total trench volume. Table 12 summarizes the calculations of water-accessible trench void volumes made for TARA trenches 2 through 6 using this method. The calculated fractional void volumes were between 8 and 23%. These values are similar to the 20% values found for trenches in SWSA 4 (Spalding et al. 1987) but smaller than the 30% value found for trench 271 in SWSA 6 (Spalding 1986). There now appears to be a sufficient sample of burial trench fractional void volumes from this and previous work for assessing stabilization and closure needs for ORNL SWSAs. The measurement of the residual void volumes in these trenches, after dynamic compaction, will be repeated using the grout filling volumes. Thus, a direct quantifiable comparison of trench voids can be obtained before and after compaction.

Table 12. Summary of calculations of water-accessible void volume derived from trench water pump-in tests.

Region	Bottom Elev. (m)	Top Elev. (m)	Region Height (m)	Region Flow Rate (m ³ /h) (X ₁)	Region Fill Time (T ₁)	Region Empty Time (T ₀)	Seep Rate (m ³ /h) (X ₀)	Net Fill Rate (m ³ /h)	Void Volume (m ³)	Void Volume (%)
Trench 2, Area = 84.5 m ²										
1	252.87	253.83	0.96	4.18	5.50	89.00	0.24	3.94	21.65	26.69
2	253.83	254.12	0.29	3.45	1.00	9.50	0.33	3.12	3.12	12.74
3	254.12	254.66	0.54	2.75	2.50	11.50	0.49	2.26	5.65	12.38
			<u>1.79</u>						<u>30.42</u>	<u>20.11</u>
Trench 3, Area = 77.2 m ²										
1	251.61	253.00	1.39	4.25	1.25	480.00	0.01	4.24	5.30	4.94
2	253.00	254.00	1.00	4.25	2.25	78.75	0.12	4.13	9.30	12.04
3	254.00	255.00	1.00	4.25	2.75	18.75	0.54	3.71	10.19	13.20
4	255.00	255.56	0.56	4.25	1.75	0.25	3.72	0.53	0.93	2.15
			<u>3.95</u>						<u>25.72</u>	<u>8.43</u>
Trench 4, Area = 63.5 m ²										
1	251.55	253.00	1.45	5.45	6.09	51.07	0.58	4.87	29.65	32.21
2	253.00	254.00	1.00	5.45	3.38	17.05	0.90	4.55	15.37	24.21
3	254.00	255.13	1.13	3.91	6.83	7.33	1.89	2.02	13.82	19.27
4	255.13	255.70	0.57	4.20	1.42	0.83	2.65	1.55	2.20	6.08
			<u>4.15</u>						<u>61.04</u>	<u>23.17</u>

Table 12. (Continued)

Region	Bottom Elev. (m)	Top Elev. (m)	Region Height (m)	Region Flow Rate (m ³ /h) (X ₁)	Region Fill Time (T ₁)	Region Empty Time (T ₀)	Seep Rate (m ³ /h) (X ₀)	Net Fill Rate (m ³ /h)	Void Volume (m ³)	Void Volume (%)
Trench 5, Area = 64.1 m ²										
1	252.20	253.00	0.80	4.27	6.25	172.61	0.15	4.12	25.75	50.22
2	253.00	254.00	1.00	4.27	3.50	57.25	0.25	4.02	14.08	21.97
3	254.00	255.00	1.00	4.27	3.00	16.25	0.67	3.60	10.81	16.87
4	255.00	256.20	1.20	4.27	5.25	3.00	2.72	1.55	8.15	10.60
			<u>4.00</u>						<u>58.79</u>	<u>22.93</u>
Trench 6, Area = 56.9 m ²										
1	252.00	253.00	1.00	3.13	2.25	41.25	0.16	2.97	6.68	11.74
2	253.00	254.00	1.00	3.13	4.25	20.75	0.53	2.60	11.04	19.40
3	254.00	255.00	1.00	3.13	5.00	13.65	0.84	2.29	11.45	20.13
4	255.00	256.11	1.11	3.13	4.25	3.50	1.72	1.41	6.01	9.51
			<u>4.11</u>						<u>35.18</u>	<u>15.04</u>

TRENCH COVER MOISTURE AND BULK DENSITY

The soil cores collected by the standard split spoon sampling technique described above were taken to the laboratory and, after preliminary screening for volatile organics, were weighed, dried at 104°C until all moisture was driven off, and reweighed to determine the percentage moisture. The lengths of the cores had already been measured in the field and could be used to calculate the mass of dry soil per unit volume (bulk density) of each core. Figures 24 and 25 illustrate soil moisture and bulk density as a function of depth, respectively. No significant variation in moisture content with soil depth was apparent. Bulk density, however, did tend to increase with soil depth as might be expected for soil weathered in place. It should be pointed out that all sampling was carried out between February and mid-April, 1987, when soil moisture conditions would normally be expected to be at seasonal maxima. Drier soil moisture contents would be expected, particularly in the surface samples, if sampling were carried out in summer or early fall.

After the compaction of each trench was completed, a hand-held soil coring device of 944-cm³ volume was used to obtain a shallow soil core from three positions along each trench for moisture and bulk density measurements (Blake and Hartge 1986). The core reached only to a depth of 11 cm and was thus compared to the 0- to 46-cm sections of core taken before compaction to access the changes that occurred in bulk density. Table 13 summarizes the changes in trench cap moisture and bulk density before and after trench compaction. Table 14 presents all the moisture and bulk density measurements made on the five trenches after compaction. No significant change in the bulk density of the soil cap resulted from the dynamic compaction. This result leads to the conclusion that the consolidation of the trench occurred largely in the subsurface.

Fig. 24. Tara site soil moisture as a function of depth.

Fig. 25. TARA site soil bulk density as a function of depth.

Table 13. Changes in trench cap moisture and bulk density after trench compaction

Soil Depth (cm)	Before Compaction			
	Average Moisture		Average Bulk Density	
	Trench Cap Area		Trench Cap Area	
	Trench Cap	Area	Trench Cap	Area
0 - 46	21.8	20.8	1.56	1.53
46 - 92	22.5	24.0	1.62	1.57
	After Compaction			
	Average Moisture		Average Bulk Density	
	Trench Cap Area		Trench Cap Area	
	Trench Cap	Area	Trench Cap	Area
0 - 15	18.8		1.45	

Table 14. Bulk density and moisture contents of surface (0-11 cm) soils of trench caps after dynamic compaction

<u>Trench Number</u>	<u>Position</u>	<u>Moisture</u> (% dry wt.)	<u>Bulk Density</u> (g/cm ³)
2	North	17.8	1.31
2	Center	19.2	1.26
2	South	19.3	1.41
3	North	16.4	1.39
3	Center	18.8	1.56
3	South	20.1	1.39
4	North	18.8	1.31
4	Center	20.1	1.47
4	South	22.3	1.57
5	North	18.5	1.52
5	Center	17.9	1.36
5	South	17.2	1.61
6	North	16.8	1.58
6	Center	18.6	1.62
6	South	18.9	1.37
Control	Center	19.3	1.54
Average		18.7	1.45
Standard Deviation		±1.4	±0.12

TRENCH CONTENTS AND GROUT COMPATIBILITY

Because of the large inventory of radioactivity in some burial trenches in SWSA 6, assurance of hydrologic isolation of trench contents from groundwater intrusion and/or percolation, beyond that provided by an infiltration barrier, may be warranted for particular trenches. In situ grouting is a technique for providing assurance of hydrologic isolation of burial trench contents, regardless of assurance of infiltration barrier integrity or performance. Two in situ grouting field demonstrations have been completed at ORNL (Spalding et al. 1985 and 1987). Both of these demonstrations involved placing acrylamide grout into uncompacted burial trenches. Both were successful in changing the burial trenches from a condition of extreme permeability and facile water intrusion to a condition of unmeasurable permeability. However, based on these demonstrations, it became apparent that the costs of in situ grouting were quite high (i.e. about \$50,000 per typical burial trench, due to the large amount of voids per trench). Dynamic compaction, on the other hand, is a relatively inexpensive method to eliminate many of the large voids within a trench, leaving a potentially much smaller residual void volume to be grouted. One of the major goals of the proposed in situ grouting demonstration is to demonstrate that dynamically compacted trenches can be grouted with acrylamide and achieve the same degree of hydrologic isolation that has been demonstrated on unperturbed burial trenches. If this compatibility of in situ grouting with dynamic compaction can be demonstrated, then not only will in situ grouting costs be considerably lower (probably 80% due to the trench void reduction by dynamic compaction) but an effective and safe method for stabilizing the burial trench ground surface to support an infiltration barrier cap will be established to a degree that acrylamide grouting alone cannot achieve.

In seeking advice from environmental regulatory agencies and other scientists and engineers, a number of questions were raised concerning the hazards and risks of using acrylamide in the proposed demonstration. Acrylamide is a toxic substance and, therefore, poses certain risks not only for those who prepare and inject the grout but also for potential groundwater contamination in the area where the grout is being injected. Once the acrylamide polymerizes (sets), it becomes nontoxic and nonhazardous like the majority of polymers in the materials of commerce. Most of the concerns raised center on the ability to control the polymerization process during injection into burial trenches and provide assurance that the grout will set to an impermeable state and not result in any contamination of groundwater at the demonstration site. The setting of polyacrylamide is known to be inhibited by strong acids, bases, and concentrated (10%) solutions of reducing agents (Larson and May 1983). What assurances exist that similar substances are not present in the five proposed trenches which may potentially inhibit the grout set? How is it known that a grout formulation of a given design set time will not reach the water table below the trenches before it sets?

One approach to test compatibility of acrylamide grout with the burial trench contents would be to perform chemical analyses of the inorganic and organic constituents in each of the burial trenches and, then, perform grout compatibility tests with each component at the measured concentrations. This

approach is enormously costly and technically difficult. Characterization of trench contents is quite difficult due to the heterogeneous nature of the buried waste. As an alternative, samples of trench leachate, where available, and trench bottom soil could be obtained and tested for compatibility with the acrylamide grout. The samples of leachate and trench bottom soil would be characterized in a screening method for gross chemical and radiochemical properties without a detailed examination and analysis for specific hazardous constituents. Not only could grout set time be measured in the presence of trench leachate and soil, but quantitative measurements of the degree of polymerization could be determined by assaying the set grouts for residual concentrations of the acrylamide monomer. In addition, the hydraulic conductivity of trench soil specimens could be determined before and after grouting to verify the degree of permeability expected during actual trench grouting. If it can be demonstrated that grout set time is not affected adversely by the trench leachates or trench soils, that the degree of polymerization achieved in the presence of trench leachate or trench soil is equivalent to what can be achieved with a neat grout, and that trench soil can be converted to an impermeable state by the grout, then high confidence can be attained that grout set control can be ensured in the field demonstration.

Samples of trench bottom soil were collected on July 1, 1988, from the five burial trenches (SWSA 6 trench numbers 2, 3, 4, 5, and 6) by inserting a hand auger into uncased residual penetration testing holes and/or existing bottomless well casings that were placed in each trench during filling. The penetration test holes were made in February and March 1987 during stability (nonstandard soil penetration) tests on the burial trenches prior to dynamic compaction. Composites of all samples from an individual trench were made in the field in seal-lock polyethylene bags. Typically, about 100-200 g of field-moist soil could be obtained from each trench. Samples were screened as collected for gross beta/gamma radioactivity with a field survey Geiger-Mueller meter; several read about 10 mR/h at contact with the sample bag. To reduce the soil moisture content to a level where the samples could be sieved and homogenized, the samples were dried in the opened bags at 80 °C for 2 h. Care was taken that the samples did not completely dry. Samples were then sieved to <2 mm by hand, and the coarse fragments (mostly gravels) were discarded as radioactive waste. Moisture contents of the sieved and homogenized soil were determined by drying subsamples at 105 °C for 2 h. These samples of oven-dried soil were used for determination of ^{137}Cs , ^{60}Co , and ^{90}Sr via gamma-ray spectroscopy and bremsstrahlung detection using an NaI detector with a multiple channel analyzer.

Samples of trench leachate were collected between October 27 and November 20, 1987, during trench water filling for void determination. Since January 1987, when the first access wells were placed during initial penetration tests on these five trenches, a seasonally ephemeral level of standing water has been observed in only one of these trenches following a sustained rainy period in February 1987. Thus, "natural" trench leachate samples were not available for this grout compatibility study. However, the induced leachate samples were collected at the time near the emptying of the trench and, therefore, likely represent types of leachate with maximal exposure to trench waste contents. These leachate samples were characterized

for their gross chemical and radiochemical properties by measuring pH, electrical conductivity, dissolved solids, hardness, alkalinity, gross alpha, and gross beta activities (APHA 1980). In addition, a sample of the emergency waste holding pond water (used as the source of water for the trench filling tests) was included in this characterization as a point of reference for water quality before contacting the buried waste trenches. Also included, for comparison, are the mean values for these same water characteristics for samples of groundwater collected three weeks after the completion of the last trench-filling test from the 15 groundwater monitoring wells within and around the test area.

To measure grout set time in the presence of trench leachate, 10.0 mL of a 20% (weight/volume) solution of Q-1 (Cues, Inc., Orlando, Fla.) grout in water was placed in a 50-mL capacity polypropylene beaker. The Q-1 grout is a mixture of 95% acrylamide and 5% methylenebisacrylamide. The 20% grout solution also contained 1% (volume/volume) triethanolamine, the grout-free radical transfer agent, and 0.02% (weight/volume) potassium ferricyanide, the grout set retarder. After adding the grout to the beaker, 5 mL of either trench leachate or water were added. Then, 5 mL of a 4% (weight/volume) solution of ammonium persulfate, the grout catalyst, was added and swirled gently to mix the beaker contents. Time of grout set was measured from the time of catalyst addition until grout would no longer flow within the beaker. The setting of acrylamide grout is a relatively abrupt change in viscosity occurring within a few seconds. Thus, unlike set time measurement with cements or silicate grouts, no elaborate test methods or apparatuses are required. Insufficient amounts of the leachate of trench 4 were available for study.

To measure grout set in the presence of soil, the procedure was identical to that described above except that 5.00 g of fresh (undried) sieved soil was used instead of the 5 mL of leachate or water. The beaker contents were swirled at frequent intervals to keep the soil in suspension to maintain an intimate contact between soil and grout. This method maximizes the potential for observing possible interference of grout set by the soil or its contaminants. Otherwise, the soil would settle to the bottom of the beaker and the overlying grout could set without interference from the burial trench soil or its possible adsorbed constituents. The observed set times of the grout were recorded to the nearest minute.

After storing the 20-mL grouted soil and leachate specimens in a sealed container overnight (16 h), the samples were extracted with water to determine concentrations of residual monomer and, hence, to calculate the degree of polymerization achieved in the presence and absence of burial trench soil and leachate. The grouted specimen was placed in a 250-mL stainless steel container with 100 mL of distilled water and macerated for 15 s with a commercial rotating knife blender at 21,000 rpm. The resulting viscous homogenate was filtered through a borosilicate glass microfiber filter (1 μ m particle size retention) overlain by a 1-cm-thick sand layer as a prefilter to prevent clogging by the filtrate. The sand was acid-washed and ignited quartz. The resulting clear filtrate was stored in capped polyethylene containers at 4 C until analysis. Four samples of the unpolymerized grout were also prepared by substituting 5 mL of water for the

ammonium persulfate catalyst solution or 5 mL of a 4% ammonium sulfate solution.

Analysis for acrylamide, methylenebisacrylamide, and acrylic acid was carried out using a direct injection on a high-pressure liquid chromatograph (HPLC). A 4.6 mm x 25 cm long stainless steel column was employed containing octadecylsilane reversed-phase spherical silica absorbent (10 μ m particle size) with 20% methanol:water (v:v) as the eluant. An injection volume of 0.25 mL was employed using a fixed-volume sample loop attached to the injection valve of a Perkin-Elmer 15B Liquid Chromatograph equipped with an ultraviolet detector and a flow rate of 1 mL/min. Good separation between the three components was achieved, and a detection limit of about 1 mg/L of acrylamide was attained. Standards for acrylamide in the range of 20 to 100 mg/L were prepared, and dilutions of the grout extracts were made to be within this range. Elution peak height was used as a measure of acrylamide concentration and was found to be linearly correlated ($r = .9982$) with acrylamide concentration within the range of standards. Percent of polymerization was calculated from the difference between the amount of acrylamide in the unpolymerized specimens and that measured in the grouted specimens.

The effect of grouting of burial trench soil on its permeability was determined by measuring the hydraulic conductivity of small columns of burial trench soil before and after permeating them with grout. Five grams of moist soil, overlying 3 g of quartz sand, was placed into a 1.0 cm diam x 10 cm long glass column equipped with polypropylene fittings to regulate flow. A 20-mL aliquot of grout solution, prepared identically to that described above, was carefully poured onto the top of the column. A constant head was maintained manually by keeping the level of grout fixed above the column. From the measured volume of excess grout eluting from the soil column in a measured time interval, a hydraulic conductivity for the soil sample was calculated for the geometric configuration of liquid level and length of soil column (Klute 1965). The bulk density of the soil in the columns was calculated from the known fresh weights of soil added, their measured moisture contents, and the volume occupied by the soil in the column. Several columns required that their flow be interrupted to prevent grout from running out of the soil, while others attained grout set before grout solution had percolated the soil. After grout set, any set grout on top of the column was removed with a spatula. The glass surface near the column bottom was scored and broken off to allow for the removal of any grouted sand from the column. Otherwise, grouted sand at the column bottom may have reduced hydraulic conductivity of the sample, the effect of which could not be determined independently of any grouting of the soil. The postgrouting permeability measurements were, therefore, performed on columns containing only soil. A head of water was placed on top of each column, and a collecting tube, with only a pinhole opening to the atmosphere to prevent evaporation of any eluant, was placed on each column. The collection tubes were observed periodically over the following 48 h for the presence of eluant, but none was observed. A minimum postgrouting hydraulic conductivity was calculated for each column based on the minimum detectable amount of eluant (1 drop or 0.1 mL) in 48 h and the column geometry as in the pregrouting hydraulic conductivity calculation.

The chemical and radiochemical characteristics of the five samples of burial trench leachate are presented in Table 15 along with the characteristics of the pond water used to fill these trenches and the average characteristics of groundwater beneath and surrounding the five burial trenches.

Several conclusions about the characteristics of waste buried in the five trenches can be deduced from the information about these leachates. First, the trenches do not contain readily leachable contaminants such as acids, bases, or soluble ionic species. The placement of pond water into the trenches did not significantly alter the pH, alkalinity, hardness, dissolved solids, or electrical conductivity of the water. Nor are there significant amounts of nonvolatile organic species which would have perturbed the dissolved solids level in the water. Most of the modest increases in the chemical properties of the pond water as it evolved into trench leachate can be explained as an interaction between the limestone-containing soil at the site. Due to this interaction, groundwaters tend to be rather hard, with readily measurable levels of dissolved constituents. The average level of dissolved solids in the 15 samples of groundwater was greater than that of the dissolved solids in any of the trench leachates. Thus, the chemical environment, which the grout will encounter when placed into the burial trenches at the site, will not be much different than that anticipated for areas unperturbed by waste burial. Thus, the reported interferences in acrylamide grout setting by strong acids, bases, and reducing agent (Larson and May 1983) would not occur in these trenches.

Evidence that the pond water, which filled the trenches, did have significant interaction with the buried waste contents can be seen in the dramatic increase in dissolved radioactivity, particularly the gross beta activity. The significant level of gross alpha activity in the sample from trench 5 is due to the presence of ^{233}U , which has been identified following alpha spectroscopic assay of this sample. It should be emphasized that this area was used for disposal of higher-level (>200 mR/h at package surface) low-level radioactive solid waste. Thus, it is less likely to contain the directly handled laboratory waste which is the likely source of hazardous organic materials (e.g., scintillation vials) probably contained in other areas of SWSA 6 used for disposal of lower-level low-level solid waste.

The moisture content and radionuclide content of the six burial trench soil samples are listed in Table 16. The presence of such significant activities of radionuclides in these trench bottom soils indicates that they have experienced significant interaction with the buried contents of the trenches through the years. Thus, trace levels of inorganic and organic contaminants may also be present in these samples, and represent a good material for testing compatibility with acrylamide grouts. It should be noted that the sample of cap material from trench 3 was taken from a depth of 2-3 ft below the ground surface and does not represent surface contamination at the site. It represents a soil which would potentially interact with grout at the last stages of trench filling.

Table 15. Gross chemical and radiochemical characteristics of burial trench leachate and groundwater samples

Sample	Date Collected	pH	Electrical		Alkalinity	Dissolved	Gross	
			Conductivity	Hardness		Solids	Alpha	Beta
			(dS/m)	(...mg CaCO ₃ /L....)		mg/L	(...dpm/mL...)	
T-2	10-30-87	6.2	170	86	54	60	7	12
T-3	10-27-87	7.2	760	242	166	480	<1	103
T-4	11-03-87	6.4	1100	168	446	200	3	20800
T-5	10-27-87	6.7	510	184	68	440	187	43
T-6	10-30-87	6.1	740	298	158	420	nd ²	257
Pond	11-03-87	6.2	240	136	78	120	nd	nd
Ground								
Water ¹	11-20-87	6.8	590	481	381	544	nd	0.3
Std. Dev. ¹		0.2	217	185	124	324	-	0.4

¹ Groundwater characteristics are the average and standard deviation for 15 samples collected from the monitoring wells in and surrounding the test area.

² not detected.

Table 16. Radionuclide and moisture contents of burial trench soil samples

Sample	Moisture (%)	^{137}Cs (.....dpm/g.....)	^{60}Co	^{90}Sr
Trench 2	17.9	1060	nd ¹	3590
Trench 3	18.3	3350	nd	72800
Trench 4	16.4	128	nd	410
Trench 5	5.9	622	995	nd
Trench 6	13.7	9580	nd	15800
Trench 3 Cap	15.2	17	nd	nd

¹ not detected. Detection limits were 1.4 dpm/g, 2 dpm/g, and 6 dpm/g for ^{137}Cs , ^{60}Co , and ^{90}Sr , respectively.

None of the trench leachate samples posed any interference with the setting time of the acrylamide grout formulation (Table 17). None of the six soils samples caused any delay or inhibition of grout setting time either. Soil samples from trenches 3 and 4 did, however, cause a detectable acceleration of grout setting time. The causes of this effect are not known, but even if the same effect were manifested in actual field operations, no increase in hazard risk would result.

As discussed previously, grout set alone is not a quantitative indication of the degree of polymerization achieved by the grout. The HPLC analyses of the extracts of the grouted specimens for residual monomer, acrylamide, and cross-linking agent, methylenebisacrylamide, does provide a quantitative method to calculate the degree of polymerization and, thus, to observe any interference with the polymerization reaction by either soil or leachate. Table 18 summarizes the measured residual acrylamide concentrations within the grout specimens produced for the setting time determinations above. Also included are samples of the unpolymerized grout, prepared with either water or ammonium sulfate to replace the ammonium persulfate catalyst, which function to provide the concentration of monomer expected without any polymerization.

None of the samples of burial trench soil or leachate showed any effect on the degree of polymerization of the acrylamide, as all samples exhibited 99+% polymerization. The uncatalyzed grout samples were formulated to contain 10% acrylamide, and it is very reassuring that 100,800 mg/L were found by analysis. This verified that this bulk grout solution had not deteriorated in over 2 years of storage in the laboratory. All grout specimens contained a residual concentration of about 500 mg/L of acrylamide within their polymerized volume. The extremely low permeability of the set grout provides the mechanism to retain this residual level within the grouted mass preventing it from leaching and possibly contaminating groundwater. This would be true not only for this application for radioactive waste stabilization but also for the more common non-waste engineering applications such as dam seepage sealing or ground stabilization for improving bearing strength. In addition, low levels of acrylamide are readily biodegradable in soil (Lande et al. 1979). Thus, both the hydrologic isolation afforded by the polymer and the facile biodegradation of small amounts of residual acrylamide, which might leach from the surface of the grouted mass, provide adequate assurance that acrylamide will not reach groundwater at the proposed demonstration site.

In addition to the assurance of predictable set times and a high degree of polymerization in the presence of burial trench soil and leachate, the acrylamide also resulted in unmeasurable hydraulic conductivities in columns of burial trench soil after percolation and grout set (Table 19). The post-grouting hydraulic conductivities, listed in Table 19, may be quite lower than the calculated detection limit based on the minimum detectable volume of water at the small gravity head maintained on the columns. Thus, the burial

Table 17. Setting times for acrylamide grout in the presence of burial trench leachates and soils

Sample	Type	Setting Time (min)
Water	Water	9
Trench 2	Leachate	9
Trench 3	Leachate	9
Trench 5	Leachate	9
Trench 6	Leachate	9
Trench 2	Soil	11
Trench 3	Soil	7
Trench 4	Soil	5
Trench 5	Soil	10
Trench 6	Soil	10
Trench 3	Soil-Cap	11

Table 18. Residual concentrations of acrylamide and methylenebisacrylamide in specimens of grout prepared in the presence and absence of burial trench soil and leachate

Sample	Acrylamide (.....mg/L.....)	Methylenebis- acrylamide	Degree of Polymerization (%) ¹
Uncatalyzed Grout (4 samples)	100,800	5360	None
Neat Grout A (no soil)	450	0.7	99.55
Neat Grout B (no soil)	516	0.6	99.56
Neat Grout C (no soil)	462	0.9	99.49
Trench 2 Leachate	480	0.9	99.52
Trench 3 Leachate	462	0.7	99.54
Trench 5 Leachate	486	0.7	99.51
Trench 6 Leachate	510	0.9	99.49
Trench 2 Soil	498	3.0	99.50
Trench 3 Soil	342	2.1	99.66
Trench 4 Soil	348	<10.0	99.65
Trench 5 Soil	570	3.4	99.43
Trench 6 Soil	516	2.8	99.49
Trench 3 Cap Soil	456	2.4	99.54

¹ Degree of polymerization = (starting concentration of acrylamide - sample residual concentration of acrylamide) / starting concentration of acrylamide, where the starting concentration of acrylamide = 100,800 mg/L.

Table 19. Hydraulic conductivities of burial trench soil columns before and after grouting with polyacrylamide

Soil Column	Bulk Density (g/cm ³)	Hydraulic Conductivity	
		Before	After
		(.....cm/s.....)	
Trench 2	0.83	1.2×10^{-2}	$<2.4 \times 10^{-7}$
Trench 3	0.80	4.8×10^{-2}	$<2.5 \times 10^{-7}$
Trench 4	0.78	4.0×10^{-2}	$<2.6 \times 10^{-7}$
Trench 6	0.95	3.2×10^{-3}	$<2.2 \times 10^{-7}$
Trench 3 Cap	0.80	2.5×10^{-2}	$<2.5 \times 10^{-7}$

trench soil is not expected to pose any deleterious effect on the permeability of the grout. Neat acrylamide grouts have measured hydraulic conductivities of about 10^{-10} cm/s (Avanti International 1985). This extremely low permeability is adequate to retain the low residual concentrations of monomeric acrylamide within the polymeric grout to a diffusion-controlled level.

In summary, the proposed in situ grouting of five burial trenches with polyacrylamide had raised several concerns about potential environmental contamination by acrylamide. To establish the compatibility of the acrylamide grout set reaction with potential interference by buried waste constituents, several tests were performed to verify the ability to predict and control the polymerization or set of the acrylamide grout. Samples of soil from the bottom of five trenches and samples of burial trench leachate were collected and added to grout solutions before set. No soil or leachate significantly retarded the grout set time. By chemical analysis of extracts of grout/soil specimens, it was determined that the percent polymerization in the presence of soil or leachate was identical to that achieved with unamended grout, i.e., 99.5%. In addition, specimens of burial trench soil were converted from high to unmeasurably low hydraulic conductivities by percolation with reacting grout. Thus, it appears that these burial trench soils and leachate pose no interference with acrylamide grout set. Both the degree of polymerization and the impermeable nature of the resulting polyacrylamide grout lead to the assurance that environmental contamination of groundwater by grout injection into these burial trenches is extremely improbable.

DEGRADATION RATES FOR ^{14}C -LABELED POLYACRYLATE AND POLYACRYLAMIDE GROUTS IN SOIL

Chemical and microbial stability is one of the critical issues to be resolved for performance evaluation of organic-based grouts. Laboratory experiments have been conducted for the determination of degradation rates for ^{14}C -tagged polyacrylate and polyacrylamide grouts. This subtask reports results of degradation experiments conducted on grouts of 10% polyacrylate, 20% polyacrylate, 10% polyacrylamide, and 20% polyacrylamide, over periods of 757 days, 153 days, 153 days, and 440 days, respectively.

The soil used in this experiment was obtained from the C horizon (1 to 2 m from surface) of a Typic Dystrochrept; loamy-skeletal, mixed, thermic (Berks variant series) soil profile, developed on residuum of Maryville Limestone (Conasauga Group), located in Solid Waste Storage Area 6 of the Oak Ridge Reservation. Detailed characterization of the soil sample (<2 mm in diam) showed a clay loam texture (28% sand, 35% silt, and 37% clay), low organic matter content (0.17% carbon), moderate cation exchange capacity (11 meq/100 g), and acidic pH (5.4). Vermiculite and illite were the major clay minerals.

The 10% polyacrylate grout components were prepared in two flasks: the first contained 50 μl of ^{14}C -tagged acrylic acid (98% by wt., 9.43 μCi total activity) supplied by Pathfinder Laboratories, Inc., to which was added 125 mL of AC400 magnesium acrylate monomer (40% solids by weight), 4.5 mL triethanolamine (99% by weight), and 68 mg potassium ferricyanide. The second flask contained 250 mL of 0.1 M ammonium persulfate. The 20% polyacrylate grout was prepared by combining 250 mL of AC400, 100 mg potassium ferricyanide, and 50 μL of ^{14}C -tag with a 250 mL 0.1 M ammonium persulfate solution containing 9.0 mL triethanolamine.

In the case of the polyacrylamide grouts, a ^{14}C -acrylamide solution was first prepared by transferring 10 mg of dry acrylamide-UL- ^{14}C (94.2 μCi total activity) supplied by Pathfinder Laboratories, Inc., to a tared bottle and dissolving it in 10 mL distilled deionized water. To prepare the 10% polyacrylamide grout, 1 mL (9.42 μCi) of the tag solution was transferred to a flask which also contained 50 g of Q Seal acrylamide monomer (92% by weight), 47 mg potassium ferricyanide, 4.2 mL triethanolamine (99% by weight), and 190 mL distilled deionized water. A second flask contained 250 mL of 0.1 M ammonium persulfate. The 20% polyacrylamide grout was prepared using 100 g Q Seal, 92 mg potassium ferricyanide, 8.2 mL triethanolamine, and 1 mL of ^{14}C -tag in the first flask, and 250 mL of 0.1 M ammonium persulfate in the second flask.

Water retention characteristics of untagged 10 and 20% polyacrylamide and 10% polyacrylate prepared in the same manner as for the other experiments were measured at 1/3, 3, 8, and 15 bars on a soil moisture 5-bar and 15-bar pressure plate extractor.

For each experiment, six successive 40 mL aliquots of grout were prepared by mixing equal volumes (20 mL) from the two flasks. Each of the four grout compositions were added to a set of six 450-mL jars containing 50 g each of air-dried soil which had been sieved to <2-mm grain size, making 24 jars

altogether. Based on scintillation counting of 1-mL aliquots of the unpolymerized ^{14}C -acrylate and -acrylamide solutions, the ^{14}C activities added to the soil jars were calculated to be 0.620 μCi in the case of the 10% polyacrylate, 0.645 μCi for the 20% polyacrylate, 0.652 μCi for the 10% polyacrylamide, and 0.626 μCi for the 20% polyacrylamide. After the grouts had set thoroughly, the soil/grout mixtures in three of the jars (designated 4, 5, and 6) in each experiment were macerated using a spatula. Jars 1, 2, and 3 in each experiment were left undisturbed. An open scintillation vial containing 1 mL of 1.0 N NaOH was placed in each jar; the jars were then sealed and stored in an incubator at 25°C. The scintillation vials were replaced at 3- to 5-d intervals initially, later at weekly intervals, and in some cases monthly intervals. $^{14}\text{CO}_2$ collected in the vials was determined by adding 1 mL distilled water and 18 mL ACS scintillation cocktail to each vial, mixing, then measuring radioactivity with a Packard TriCarb Model 3255 liquid scintillation spectrometer.

In the course of the experiments, it was observed that as the carbonate contents of some of the vials increased, precipitation of Na_2CO_3 began to occur upon addition of the scintillation cocktail. To prevent this, two methods for dilution were used. Initially, a 0.5-mL aliquot of 1.0 N NaOH solution was transferred from a "problem" vial to a new vial and diluted with 1.5 mL distilled water before addition of scintillation cocktail. When this became insufficient, an alternate method was used: 2 mL of 1.0 N NaOH was added to the vials before CO_2 collection, then 0.5 mL was transferred after collection and diluted as before. This prevented precipitation and made for a fourfold dilution of the ^{14}C -bearing NaOH solution.

Later, when activity levels in the jars declined sufficiently, dilutions were reduced to twofold by transfer of 1 mL of NaOH from the sampling vial, with addition of 1 mL of distilled water. As the experiments continued, it was possible to eliminate the dilutions altogether and return to the original sampling procedures.

A first-order rate law for grout degradation was calculated by plotting concentration (radioactivity) versus time

$$C = C_0 e^{-kt}, \quad (\text{Equation 1})$$

where, C_0 = initial radioactivity of carbon- 14
 C = remaining activity
 t = time (days)
 and k = reaction rate constant.

The half-life (t) of the reaction was calculated using the equation

$$t = 0.6931/k. \quad (\text{Equation 2})$$

Thus, the half-life of the grout is independent of its initial quantity.

Several factors could affect the degradation of added grout materials. The biological degradation rate of a given organic substrate will depend upon its composition and the physicochemical conditions in the surrounding

environment. Temperature, O₂ supply, moisture, pH, available nutrients, C:N ratio of soil organics, and the indigenous microbial population are the main environmental influences. In these laboratory experiments, incubation temperature was 25°C, under moist but unsaturated conditions, and aerobic conditions were maintained by periodic opening of the jars for sampling.

Water contents of acrylamide and acrylate polymers depend on the amount of monomers and catalysts used initially. Understanding the behavior of water in the polymers is important because the water molecules control their stability. The polymers will shrink when they lose water, resulting in the formation of undesirable voids between the polymer block and trench wall and cap. Therefore, water retention characteristics of the polymers were investigated under various tension pressures (1/3, 3, and 15 bars) that have been widely used in other studies. The field water capacity of a soil is determined in the laboratory by measuring the water content of a soil sample under 1/3 bar tension. Under these conditions, most large pores have drained free of water. The water associated with the tension zone between field capacity and about 3 bars is easily extracted by plants with minimal expenditure of energy. Soil water under tension between 3 and 15 bars becomes more difficult to extract by plants. As water tension increases in this range, plants undergo drought stress. Finally, a tension is reached under which a plant can no longer extract water. This tension is commonly termed the permanent wilting point and is observed at 15 bars in the laboratory.

The average water contents measured under 0 bars pressure after oven drying at 105°C for 24 h, were 86.4% for 10% polyacrylate, 84.6% for 10% polyacrylamide, and 74.2% for 20% polyacrylamide (Table 20). The water contents after equilibration at 1/3, 3, 8, and 15 bars tension were not significantly different. The ability of both polyacrylamide and polyacrylate to retain water at 15 bars tension indicates that plants should not be able to extract any of this bound water. The only movement of polymer-bound water to the surrounding medium should be by diffusion, a slow process that would occur only if there were a large differential in moisture content. Conversely, when the surrounding medium is saturated, diffusion should be in the reverse direction. Subsurface soils could remain in an unsaturated condition for a significant period, but in a humid region, the soil water tension should remain close to field capacity. Therefore, void formation between the injected polymers and trench walls due to shrinkage of the polymers is not expected and is not considered a limiting factor for their application in this region.

Degradation of 10% ¹⁴C-polyacrylate: When the results from scintillation counting of the CO₂ collection vials exposed to the polyacrylate-grouted soil were plotted in terms of evolved ¹⁴C activity versus time, the three undisturbed soil/grout replicates (1, 2, and 3) showed an initially high activity, followed by a gradual decline. Replicates 1 and 2 appear to have "bottomed out" by approximately day 40, but replicate 3 underwent a sharp increase in activity, beginning around day 30, peaking near day 48, and declining gradually thereafter. Near day 60, replicate 2 began a similar pattern, peaking near day 75 at half again the activity of replicate 3.

Table 20. Water retention characteristics of acrylate and acrylamide polymers at various pressures

	Water Retention, %				
	0 bar	1/3 bar	3 bars	8 bars	15 bars
10% polyacrylate	86.4	86.3	85.1	85.5	85.9
10% polyacrylamide	86.6	86.8	86.2	86.4	85.9
20% polyacrylamide	74.2	73.8	73.3	72.2	72.9

About that date, replicate 1 also increased sharply and peaked around day 90 at well over twice the maximum level of replicate 3. In each case, the increase in ^{14}C activity measured in the scintillation vials was directly correlated with visual observation of fungal mycelia in the undisturbed soil/grout jars.

The three macerated soil/grout replicates (4, 5, and 6) displayed a similar pattern, only later. All had a sharp but relatively low ^{14}C peak within the first week after grouting, followed by a rapid decline and gradual leveling off of activity. This was succeeded in each case by a period of rapid degradation accompanied by the appearance of fungal mycelia, beginning with replicate 6 on day 150, then replicate 4 around day 210, and replicate 5 after day 250. Activities released from the macerated grout forms during these periods of rapid fungal growth, though occurring later, were nearly twice as great ($0.063 \mu\text{Ci}$ average, as compared with $0.034 \mu\text{Ci}$ for the undisturbed grouts) (Table 21).

To calculate the grout degradation rates, the data were plotted as concentration versus time, i.e. $\ln(C_0/C)$ versus t , assuming the degradation processes to be first-order reactions (Fig. 26). The slopes of these curves represent different degradation rate constants, from which grout half-lives can be calculated. "Steady degradation" rate constants (k_1 - k_7) were determined for the 10% polyacrylate grout replicates (Table 22).

Although "steady degradation" constituted an average of 75.7% of the time-period measured, it generated an average of only 14.2% of the total ^{14}C activity released from the 10% polyacrylate grouts (18.4% for undisturbed, 10.0% for macerated forms). Of the tagged carbon given off as CO_2 during the monitoring period, 85.2% was released during short bursts of rapid degradation by soil microorganisms. However, there has been no renewal of this sort of activity since approximately day 355, and it appears that the rate constants from the latter portion of the plot (k_2 - k_7) reflect long-term grout behavior.

Table 21. Loss of ^{14}C activity from 10% polyacrylate grout, by degradation stages

Undisturbed				Macerated			
Replicate	Day	μCi	% loss	Replicate	Day	μCi	% loss
1	0-74	0.0078	1.26	4	0-60	0.0059	0.95
	74-161	0.0361	5.82		60-208	0.0031	0.50
	161-757	0.0092	1.48		208-355	0.0569	9.18
	Total	0.0531	8.56		355-757	0.0051	0.82
					Total	0.0717	11.56
2	0-60	0.0075	1.21	5	0-60	0.0059	0.95
	60-147	0.0394	6.35		60-249	0.0043	0.69
	147-757	0.0089	1.43		249-355	0.0687	11.08
	Total	0.0558	9.00		355-757	0.0040	0.65
					Total	0.0837	13.50
3	0-28	0.0051	0.82	6	0-60	0.0059	0.95
	28-161	0.0263	4.24		60-147	0.0021	0.34
	61-757	0.0089	1.43		147-347	0.0632	10.20
	Total	0.0403	6.50		347-757	0.0046	0.74
					Total	0.0767	12.37

Table 22. Degradation rate constants and half-lives of 10% polyacrylate grout in soil

Rate Constant (day ⁻¹)		Half-life (years)	Remarks		
k ₁	3.5 x 10 ⁻⁵	53.7	1st	steady	degradation
k ₂	3.4 x 10 ⁻⁵	55.0	2nd	steady	degradation
k ₃	3.8 x 10 ⁻⁵	49.8	2nd	steady	degradation
k ₄	4.1 x 10 ⁻⁵	46.8	2nd	steady	degradation
k ₅	3.4 x 10 ⁻⁵	55.0	2nd	steady	degradation
k ₆	3.5 x 10 ⁻⁵	54.8	2nd	steady	degradation
k ₇	3.2 x 10 ⁻⁵	60.0	2nd	steady	degradation

Figure 26. Degradation of 10% ^{14}C -polyacrylate grout in soil, plotted according Equation 1 (k represents rate constants shown in Table 21).

Degradation of 20% ^{14}C -polyacrylate: After 153 days of monitoring, it appears that only since Day 139 has the 20% polyacrylate grout degradation begun to pass from an "initial" to a "steady" phase (Fig. 27, Table 24). Comparison of 10% and 20% polyacrylate grout half-lives may therefore not be especially useful at this time. However, activity released from the 20% polyacrylate grout composition has been significantly less than from the 10% polyacrylate composition (nearly an order of magnitude less, when measured over the same time period as percent of initially added activity), and the six replicates have shown remarkable consistency in rate and timing of degradation stages. The combination of low released ^{14}C -activity, relatively high degradation rate constants, and virtually identical behavior of macerated and undisturbed 20% polyacrylate grout forms, in contrast with the relatively erratic behavior of the 10% polyacrylate forms, may represent a toxicity effect which is delaying achievement of a "steady-state" microbial population.

Degradation of 10% ^{14}C -polyacrylamide: The plot of $\ln(C_0/C)$ versus t for the 10% polyacrylamide grout (Fig. 28) shows a distinct resemblance to that for 10% polyacrylate, with the various grout forms degrading at different rates. The macerated replicates display a consistently lower degradation rate (k_{11} and k_{12} , Table 26), while the undisturbed replicates have degraded more rapidly and erratically. It is unclear why the undisturbed samples should degrade more rapidly; however, a slight downturn in $\ln(C_0/C)$ for the last pair of samples from jars 1-3 may be the beginning of a "steady" phase with rate constants similar to those for jars 4-6. Perhaps the 10% polyacrylamide degradation will follow a path similar to that of the 10% polyacrylate - the undisturbed forms undergoing rapid degradation earlier, but releasing less activity overall, while rapid degradation of the macerated forms is delayed but ultimately releases more activity due to increased surface area available for microbial attack.

Degradation of 20% ^{14}C -polyacrylamide: Data for the first 440 days of the 20% ^{14}C -polyacrylamide experiment have been plotted as $\ln(C_0/C)$ versus t (Fig. 29). Two major phases of grout degradation based on ^{14}C -activity have appeared so far: an initial, very rapid phase (k_{17}) lasting approximately 20 days, and a slower phase observed from day 21 onward. This latter phase probably does not represent "steady" degradation, however; it may represent a long-term toxicity effect like that of the 20% polyacrylate grout, impeding microbial growth toward a stable population level. During the initial rapid phase, average ^{14}C loss among the replicates was 0.048% of the total activity applied for each jar (Table 27). The percent activity losses between days 21 and 440 were 0.159% for undisturbed and 0.277% for macerated replicates. A feature of this latter phase has been the divergence of degradation rates for the undisturbed (k_{18-20}) versus macerated (k_{21-23}) grout replicates. The consistently higher rate of ^{14}C -release from the macerated replicates may indicate that a larger surface area facilitates microbial activity and/or diffusion of unreacted monomer into the atmosphere (Table 28), though this leaves unresolved the question of why the 10% polyacrylamide composition should behave in the opposite manner, with undisturbed forms degrading faster than macerated.

Fig. 27. Degradation of 20% ^{14}C -polyacrylate grout in soil, plotted according to Equation 1 (k represents rate constants shown in Table 23).

Fig. 28. Degradation of 10% ^{14}C -polyacrylamide grout in soil, plotted according to Equation 1 (k represents rate constants shown in Table 25).

Fig. 29. Degradation of 20% ^{14}C -polyacrylamide grout in soil, plotted according to Equation 1 (k represents rate constants shown in Table 27).

Table 23. Loss of ^{14}C activity from 20% polyacrylate grout in soil

Replicate	Day	^{14}C loss, μCi	% loss
1-6 (averaged)	0-97	0.0059	0.915
	97-139	0.0037	0.574
	139-153	0.0035	0.054
	Total	0.0131	1.543

Table 24. Degradation rate constants and half-lives of 20% polyacrylate grout in soil

Rate Constant (day^{-1})	Half-Life (years)	Remarks
$k_8 \ 8.8 \times 10^{-5}$	21.6	Initial degradation
$k_9 \ 1.4 \times 10^{-4}$	13.5	Accelerated degradation
$k_{10} \ 6.4 \times 10^{-5}$	29.6	Steady degradation?

Table 25. Loss of ^{14}C activity from 10% polyacrylamide grout in soil

Replicate	Day	^{14}C loss, μCi	% loss
1	0-9	0.0004	0.06
	9-30	0.0004	0.06
	30-153	0.0061	0.94
	Total	0.0069	1.07
2	0-9	0.0004	0.07
	9-48	0.0006	0.09
	48-153	0.0045	0.68
	Total	0.0055	0.85
3	0-9	0.0005	0.07
	9-48	0.0006	0.10
	48-83	0.0013	0.20
	83-153	0.0020	0.31
	Total	0.0044	0.68
4	0-9	0.0003	0.05
	9-62	0.0006	0.09
	62-153	0.0005	0.08
	Total	0.0014	0.22
5	0-9	0.0004	0.06
	9-62	0.0006	0.09
	62-153	0.0004	0.06
	Total	0.0014	0.21
6	0-9	0.0003	0.05
	9-62	0.0006	0.09
	62-153	0.0006	0.09
	Total	0.0015	0.23

Table 26. Degradation rate constants and half-lives of 10% polyacrylamide grout in soil

Rate Constant (day ⁻¹)	Half-Life (years)	Remarks
k ₁₁ 1.76 x 10 ⁻⁵	107.8	Initial degradation
k ₁₂ 7.99 x 10 ⁻⁶	237.5	1st Steady degradation
k ₁₃ 2.48 x 10 ⁻⁵	76.5	Initial degradation
k ₁₄ 7.22 x 10 ⁻⁵	26.3	Accelerated degradation
k ₁₅ 4.28 x 10 ⁻⁵	44.3	Accelerated degradation
k ₁₆ 7.43 x 10 ⁻⁵	25.5	Accelerated degradation

Table 27. Loss of ^{14}C activity from 20% polyacrylamide grout in soil

Replicate	Treatment	Day	^{14}C loss, μCi	% loss
1 - 3	Undisturbed	0-21	0.0003	0.048
		21-124	0.0003	0.048
		124-321	0.0003	0.056
		321-440	0.0003	0.055
		Total	0.0012	0.207
4 - 6	Macerated	0-21	0.0003	0.048
		21-230	0.0008	0.133
		230-307	0.0002	0.036
		307-440	0.0007	0.108
		Total	0.0020	0.325

Table 28. Degradation rate constants and half-lives of 20% polyacrylamide grout in soil

Rate Constant (day^{-1})		Half-life (years)	Remarks
k ₁₇	2.6×10^{-5}	73.0	Initial degradation
k ₁₈	4.3×10^{-6}	441.3	1st Steady degradation
k ₁₉	3.0×10^{-6}	632.5	2nd Steady degradation
k ₂₀	4.9×10^{-6}	388.1	Accelerated degradation
k ₂₁	6.7×10^{-6}	283.2	1st Steady degradation
k ₂₂	4.5×10^{-6}	421.7	2nd Steady degradation
k ₂₃	7.8×10^{-6}	243.3	Accelerated degradation

Based on the results to date, the 10% polyacrylate grout has an average "steady" decomposition rate constant of $3.6 \times 10^{-5} \text{ day}^{-1}$ and an average half-life of 53 years. Although the other three grout compositions may not yet have achieved a "steady" rate, due to toxicity or other effects, there is a clear pattern of superior resistance to decomposition by the polyacrylamide forms. The smallest 20% polyacrylate rate constant obtained to date is $6.4 \times 10^{-5} \text{ day}^{-1}$, corresponding to a half-life of 29.6 years (Table 24), while average degradation rates for the 10% and 20% polyacrylamide grouts are respectively $4.0 \times 10^{-5} \text{ day}^{-1}$ and $5.2 \times 10^{-6} \text{ day}^{-1}$ (excluding k_{17}) (Tables 26 and 28). These correspond to 47- and 365-year half-lives, respectively. The 10% polyacrylate experiment is now over 2 years old, with an apparently stable microbial population, while the other experiments can only look forward to decreased decomposition rates in the long term. The data thus suggest that half-lives of 50-60 years for polyacrylate grouts, versus greater than 300 years for polyacrylamide grout compositions, are quite likely.

FIELD MONITORING OF SWSA 4 GROUTED TRENCHES

In 1986, a demonstration and evaluation of hydrologic isolation of buried transuranic waste via in situ grouting was carried out in SWSA 4. Two small trenches in the central region of SWSA 4 (Fig. 30) were filled with 34,000 L of polyacrylamide grout. These trenches were not dynamically compacted prior to the grouting, and their water accessible voids were completely filled by the grout (Spalding et al. 1987). Intratrench hydraulic conductivity was reduced to below field-measurable values after grout set. A group of monitoring wells (Fig. 31) for the shallow groundwater in the area were installed prior to grouting to establish water quality characteristics in the area and to monitor for potential leaching of grout constituents through time.

The HPLC analysis for grout constituents was used to assay samples from wells on two occasions (Table 29). In the initial sampling on September 21, 1987, no acrylic acid, acrylamide, methylene-bis-acrylamide, or ethylene glycol was found in any of the groundwater monitoring well samples nor was any found in the one intratrench well (number 4) which yielded a water sample. All samples were at or below the detection limit of the technique. However, for samples taken on June 27, 1988, several wells indicated apparent detectable concentrations of either acrylamide, acrylic acid, or methylene-bis-acrylamide. First, the detection limit for this sampling date was considerably higher (10 versus 0.5 mg/L) due to the smaller injection volumes employed. More importantly, several of these apparent concentrations of grout monomers are inconsistent with the total organic carbon (TOC) concentrations. For example, acrylamide contains 50.69% carbon and, therefore, each mg/L of acrylamide would require 0.5 mg/L of TOC. The inconsistency of the reported acrylamide concentration of 16 mg/L in well 17 with a TOC of 1.9 mg/L is apparent; if acrylamide concentration was in reality 16 mg/L, then the TOC must be at least 8 mg/L and probably greater if there were any other organic species present in the sample. Similarly, the well 5 acrylic acid concentration of 24 mg/L is inconsistent with a TOC of only 0.8 mg/L. The TOC measurements are more accurate for these field samples. The HPLC analysis is based on the measurement of an elution peak from the chromatographic column with a retention time equivalent to a standard, e.g. acrylamide. Other organic or inorganic species, which may be present in the sample, should they elute with the same retention time, would be measured as the standard. In the HPLC analysis of laboratory-prepared grouts, alternate species are not present because of the known additions made in the preparation of the grouts. Thus, the residual monomer analyses, reported previously, are quite accurately measured by the HPLC technique. In field samples, however, unknowns may be present that yield apparent concentrations greater than those actually present. It should be emphasized that if grout monomers are present above the detection limit, they will be detected by the technique; thus, a less-than number in Table 29 is accurate and false negatives are not possible. A refinement of the HPLC technique will be attempted next year to avoid the obvious false positives for grout constituents in the SWSA 4 monitoring wells.

The intratrench monitoring wells (Numbers 1, 2, 4, 8, and 10) all showed significantly elevated TOC values. These are probably associated with the

Fig. 30. Map of Solid Waste Storage Area 4, ORNL, showing area selected for demonstration of in situ grouting of buried transuranic waste.

Fig. 31. Plan view of trench caps and monitoring well locations in the study area for buried transuranic waste in situ grouting demonstration.

Table 29. Organic analyzates in groundwater samples from the SWSA 4 monitoring wells around the polyacrylamide grouting demonstration trenches

Well	Total Organic Carbon (.....mg/L.....)	Acrylamide	Acrylic Acid	Methylene-bis-acrylamide	Ethylene Glycol
Sampling Date - 9-21-87:					
3	na ¹	<0.5	<0.5	<0.5	<3
4	na	<0.5	<0.5	<0.5	<3
5	na	<0.5	<0.5	<0.5	<3
6	na	<0.5	<0.5	<0.5	<3
11	na	<0.5	<0.5	<0.5	<3
12	na	<0.5	<0.5	<0.5	<3
13	na	<0.5	<0.5	<0.5	<3
14	na	<0.5	<0.5	<0.5	<3
15	na	<0.5	<0.5	<0.5	<3
16	na	<0.5	<0.5	<0.5	<3
17	na	<0.5	<0.5	<0.5	<3
18	na	<0.5	<0.5	<0.5	<3
19	na	<0.5	<0.5	<0.5	<3
Sampling Date - 6-27-88:					
1	126	<10	<10	<10	na
2	34	<10	<10	<10	na
3	3.0	<10	<10	<10	na
4	12.2	<10	<10	23	na
5	0.8	<10	24	<10	na
6	1.0	<10	<10	<10	na
8	324	<10	<10	<10	na
10	269	<10	<10	<10	na
11	7.4	<10	<10	<10	na
12	3.9	<10	<10	<10	na
13	9.2	<10	<10	<10	na
14	1.4	<10	<10	<10	na
15	23	<10	<10	<10	na
16	4.9	<10	<10	<10	na
17	1.9	16	<10	<10	na
18	1.4	<10	<10	<10	na
19	8.3	<10	<10	<10	na

¹ not analyzed for.

hydrocarbon oil which was found floating on the standing water in these two trenches when they were characterized prior to grouting. A sample of the oil was skimmed from the trench and submitted for analysis; it contained no PCBs and was composed of aliphatic hydrocarbons typical of a machining oil. Many metallic turnings and shavings were augered from these trenches during the placement of intratrench monitoring wells, and the presence of machining oil would be consistent with the nature of the waste. The high TOCs are probably associated with the residuals of this hydrocarbon oil which adheres to the surfaces of all the intratrench well casings. It should also be noted that this oil is immiscible with the aqueous acrylamide grout and that encapsulation of hydrophobic species or water-immiscible fluids by acrylamide grout would not be expected without the addition of some surfactant or soap.

Values for the gross chemical and radiochemical characteristics of these monitoring well samples are presented in Table 30. No consistent or significant changes in these characteristics is observable between these recent values and those reported previously for samples taken before and immediately after grouting (Spalding et al. 1987). Additionally, the samples taken on September 21, 1987, were submitted for ICP elements as a documentation of water quality in the area (Table 31). No particularly anomalous values for heavy metals were apparent, and the major cations (Ca, Mg, Na, Al, and Fe) and Si were typical for shallow groundwaters in the Conasauga formation.

Table 30. Water quality characteristics of SWSA 4 monitoring wells around the in situ grouting demonstration trenches

Well Number	pH	E.C. (dS/m)	Hardness (...mg CaCO ₃ /L....)	Alkalinity (mg/L)	Dissolved Solids (mg/L)	³ H (dpm/mL)	Gross Beta (Bq/L)	Gross Alpha (Bq/L)
Sampling Date - 6-27-88								
SWSA4-3	6.4	696	258	40	700	5	nd ¹	nd
SWSA4-4	6.9	1278	560	220	1000	7	1	15
SWSA4-5	7.6	290	184	140	160	1	nd	2
SWSA4-6	7.4	301	188	140	200	4	nd	6
SWSA4-11	7	1001	488	510	620	7	nd	9
SWSA4-12	7	922	366	540	620	5	10	nd
SWSA4-13	6.8	692	368	370	480	7	nd	13
SWSA4-14	7.5	469	240	220	280	7	2	9
SWSA4-15	8.8	1822	50	480	2220	7	18	25
SWSA4-16	6.2	642	232	170	600	10	nd	13
SWSA4-17	6.9	631	312	320	400	8	nd	nd
SWSA4-18	7.6	438	184	180	280	5	nd	13
SWSA4-19	7.1	907	372	280	920	7	nd	11
SWSA4-1	8	2350	122	1120	520	9	5	4
SWSA4-2	7.9	559	124	180	340	28	8	6
SWSA4-8	6.7	508	168	0	1220	24	12	11
SWSA4-10	8.1	3050	96	1620	960	10	7	13
Sampling Date - 9-21-87								
SWSA4-3	6.4	1300	237	na ²	300	na	3	nd
SWSA4-4	6.9	1450	368	na	740	na	16	56
SWSA4-5	7.5	280	83	na	0	na	1	6
SWSA4-6	7.5	295	93	na	20	na	nd	nd
SWSA4-11	6.4	720	218	na	380	na	nd	nd
SWSA4-12	6.3	740	212	na	460	na	1	nd
SWSA4-13	6.4	590	174	na	2040	na	nd	nd
SWSA4-14	7.3	460	126	na	80	na	nd	nd
SWSA4-15	7.1	1700	126	na	1540	na	2	9
SWSA4-16	6.2	840	181	na	460	na	nd	nd
SWSA4-17	6.8	810	255	na	300	na	nd	nd
SWSA4-18	7.3	420	124	na	0	na	nd	18
SWSA4-19	7.2	910	235	na	1000	na	7	nd

¹ not detected.² not analyzed.

Table 31. Elemental analyses of groundwater samples from SWSA 4 monitoring wells around the in situ grouting demonstration trenches (sampling date 9-21-87)

Well	Ag (mg/L)	Al (mg/L)	As (mg/L)	B (mg/L)	Ba (mg/L)	Be (mg/L)	Ca (mg/L)
SWSA4-5	<5.0E-02	1.6	<1.0E-01	<8.0E-02	0.21	<2.0E-03	48
SWSA4-6	<5.0E-02	6.9	<1.0E-01	<8.0E-02	0.24	<2.0E-03	51
SWSA4-11	<5.0E-02	0.3	<1.0E-01	<8.0E-02	0.46	<2.0E-03	140
SWSA4-12	<5.0E-02	1.6	<1.0E-01	<8.0E-02	0.49	<2.0E-03	100
SWSA4-13	<5.0E-02	42	<1.0E-01	<8.0E-02	0.95	0.0029	100
SWSA4-14	<5.0E-02	<0.2	<1.0E-01	<8.0E-02	0.17	<2.0E-03	75
SWSA4-15	<5.0E-02	1.4	<1.0E-01	<8.0E-02	0.27	<2.0E-03	81
SWSA4-16	<5.0E-02	1.4	<1.0E-01	<8.0E-02	0.98	<2.0E-03	59
SWSA4-17	<5.0E-02	3.2	<1.0E-01	<8.0E-02	0.85	<2.0E-03	110
SWSA4-18	<5.0E-02	0.3	<1.0E-01	<8.0E-02	0.26	2.0E-03	66
SWSA4-19	<5.0E-02	5.7	<1.0E-01	<8.0E-02	2	<2.0E-03	150

Well	Cd (mg/L)	Co (mg/L)	Cr (mg/L)	Cu (mg/L)	Fe (mg/L)	Ga (mg/L)	Li (mg/L)
SWSA4-5	<5.0E-03	<0.01	<4.0E-02	<2.0E-02	2.4	<0.3	<0.2
SWSA4-6	<5.0E-03	<0.01	<4.0E-02	<2.0E-02	10	<0.3	<0.2
SWSA4-11	<5.0E-03	0.012	<4.0E-02	<2.0E-02	1.8	<0.3	0.4
SWSA4-12	<5.0E-03	<0.01	<4.0E-02	<2.0E-02	2.6	<0.3	0.79
SWSA4-13	<5.0E-03	0.071	0.13	0.054	69	<0.3	<0.2
SWSA4-14	<5.0E-03	<0.01	<4.0E-02	<2.0E-02	0.21	<0.3	<0.2
SWSA4-15	<5.0E-03	0.01	<4.0E-02	<2.0E-02	2.3	<0.3	75
SWSA4-16	<5.0E-03	0.037	<4.0E-02	<2.0E-02	5.5	<0.3	7.9
SWSA4-17	<5.0E-03	0.013	<4.0E-02	<2.0E-02	6.7	<0.3	<0.2
SWSA4-18	<5.0E-03	<0.01	<4.0E-02	<2.0E-02	0.3	<0.3	<0.2
SWSA4-19	<5.0E-03	0.013	<4.0E-02	<2.0E-02	16	<0.3	<0.2

Well	Mg (mg/L)	Mn (mg/L)	Mo (mg/L)	Na (mg/L)	Ni (mg/L)	P (mg/L)	Pb (mg/L)
SWSA4-5	9.5	0.42	<4.0E-02	9.3	<6.0E-02	<0.3	<0.2
SWSA4-6	12	0.97	<4.0E-02	9.3	<6.0E-02	<0.3	<0.2
SWSA4-11	20	3.2	<4.0E-02	22	0.1	<0.3	<0.2
SWSA4-12	23	2.7	<4.0E-02	<10	<6.0E-02	<0.3	<0.2
SWSA4-13	36	11	<4.0E-02	18	0.2	0.61	<0.2
SWSA4-14	21	0.79	<4.0E-02	14	<6.0E-02	<0.3	<0.2
SWSA4-15	17	0.84	<4.0E-02	14	<6.0E-02	<0.3	<0.2
SWSA4-16	21	5.4	<4.0E-02	10	0.063	<0.3	<0.2
SWSA4-17	28	2.9	<4.0E-02	14	<6.0E-02	<0.3	<0.2
SWSA4-18	15	0.66	<4.0E-02	10	<6.0E-02	<0.3	<0.2
SWSA4-19	38	5.6	<4.0E-02	12	<6.0E-02	<0.3	<0.2

Table. 31 (Continued)

Well	Sb (mg/L)	Se (mg/L)	Si (mg/L)	Sn (mg/L)	Sr (mg/L)	Ti (mg/L)	V (mg/L)
SWSA4-5	<0.2	<0.2	15	<0.05	0.23	<0.02	<0.02
SWSA4-6	<0.2	<0.2	22	<0.05	0.18	0.039	0.058
SWSA4-11	<0.2	<0.2	13	<0.05	0.19	<0.02	<0.02
SWSA4-12	<0.2	<0.2	12	<0.05	0.18	<0.02	<0.02
SWSA4-13	<0.2	<0.2	43	<0.05	0.23	0.58	<0.02
SWSA4-14	<0.2	<0.2	8.5	<0.05	0.17	<0.02	<0.02
SWSA4-15	<0.2	<0.2	11	<0.05	0.17	<0.02	0.077
SWSA4-16	<0.2	<0.2	13	<0.05	0.15	<0.02	<0.02
SWSA4-17	<0.2	<0.2	16	<0.05	0.25	<0.02	<0.02
SWSA4-18	<0.2	<0.2	11	<0.05	0.18	<0.02	<0.02
SWSA4-19	<0.2	<0.2	23	<0.05	0.79	0.037	0.058

Well	Zn (mg/L)	Zr (mg/L)
SWSA4-5	<0.02	<0.02
SWSA4-6	0.13	<0.02
SWSA4-11	<0.02	<0.02
SWSA4-12	0.053	<0.02
SWSA4-13	0.25	<0.02
SWSA4-14	<0.02	<0.02
SWSA4-15	0.035	<0.02
SWSA4-16	0.095	<0.02
SWSA4-17	0.059	<0.02
SWSA4-18	<0.02	<0.02
SWSA4-19	0.2	<0.02

III. DYNAMIC COMPACTION

METHOD OF DYNAMIC COMPACTION

The method selected for compacting the contents of TARA trenches 2 through 6 was the repeated dropping of a 4-metric-ton, cylindrical, concrete weight at positions or settings along the trench cover. The method had been previously tested and been found to be successful during the 1985 experimental compaction of SWSA 6 trench 271 (Spalding 1986). A track-mounted crane with a maximum lifting capacity of 60 tons was used to straddle the trench and drop the weight from a height of approximately 7 m. As the weight was lifted and positioned over the trench cap, the break on the cable holding the weight was released and the weight was allowed to fall. Upon impact, the cable break was quickly engaged to prevent excess cable from unrolling from the drum due to the downward momentum of the cable. A steel-belted truck tire was used as a connection between the crane cable and weight to act as a shock absorber. On several occasions during the trench compaction operation, the tire was replaced due to excessive wear. Figures 32 through 34 show the weight being dropped over the cover of one of the TARA trenches.

The method found to be most successful in compacting the trenches involved beginning at one end of the trench and laying out an approximate 3 m x 3 m square section. The four corners of this section were compacted first to a depth of 1.2 m (4 ft), followed by compaction of the center portion of the section to the same depth. After the entire trench section had been lowered to a depth of 1.2 m, the bottom of the resulting crater was leveled by numerous short drops of the weight. When leveling of the section was completed, the crane was repositioned and an adjoining 3 m x 3 m section of the trench was compacted. Figure 35 summarizes the compaction method by showing the locations of the trench sections and the compaction positions within each section. In total, 39 trench sections were laid out over the five TARA trenches, and 211 compaction positions were used.

RESULTS OF DYNAMIC COMPACTION

As a part of the compaction evaluation, the number of drops of the weight required for each 30 cm (1 ft) of depth at each compaction position was counted, along with the number of short drops to level out each section, and the radiation reading in mR/h at each compaction position. Table 32 summarizes the average drop counts per foot of compaction for the five TARA trenches and a 3 m by 3 m control trench that was laid out immediately to the southeast of trench 3. Appendix VII contains the entire trench compaction data set, including the location of the settings found to register radioactivity at the soil surface.

As expected, the average number of drops increased with each 30 cm of depth; 1.2 drops were required for the first 30 cm, 2 drops for the next 30 cm, 2.8 drops for the next 30 cm, and 3.8 drops for the last 30 cm. This increase was due to the compaction of soil and waste that was taking place immediately below the point of impact. Also summarized in Table 32 are the corresponding number of drops required for the 3 m x 3 m control section.

Fig. 32. Dynamic compaction of TARA burial trenches using a 4-Mg weight dropped from height of 7 m.

Fig. 33. Dynamic compaction of a control area at TARA site using a 4-Mg weight.

Fig. 34. Dynamic compaction crater over a TARA burial trench being surveyed for surface radioactivity.

Fig. 35. Location of the compaction positions on the TARA trenches.

Table 32. Summary of the number of weight drops required for each foot of trench compaction

Depth (ft)		Trench 2	Trench 3	Trench 4	Trench 5	Trench 6	Total	Control Trench
1	N -	47	44	39	41	40	211	6
	AVG -	1.79	1.11	0.85	1.02	1.13	1.20	3.17
	STD -	1.27	0.80	0.58	0.84	0.93	0.98	2.11
	MAX -	8	3	2	3	4	8	6
	MIN -	0	0	0	0	0	0	0
	SUM -	84	49	33	42	45	253	19
2	N -	47	44	39	41	39	210	6
	AVG -	2.51	1.98	1.72	1.68	2.03	2.00	5.50
	STD -	1.50	1.12	0.78	1.00	1.19	1.20	2.75
	MAX -	7	5	3	4	5	7	10
	MIN -	1	0	0	0	0	0	2
	SUM -	118	87	67	69	79	420	33
3	N -	47	44	39	41	40	211	6
	AVG -	3.53	3.36	2.23	2.29	2.48	2.82	7.33
	STD -	2.18	1.58	0.95	1.17	1.40	1.64	3.40
	MAX -	13	8	4	5	8	13	13
	MIN -	1	1	1	1	1	1	2
	SUM -	166	148	87	94	99	594	44
4	N -	46	44	39	41	40	210	4
	AVG -	4.74	3.86	3.26	2.93	3.88	3.76	6.75
	STD -	2.46	2.04	1.50	1.47	2.03	2.05	2.68
	MAX -	12	8	6	7	11	12	11
	MIN -	1	1	1	1	1	1	4
	SUM -	218	170	127	120	155	790	27
5	N -	6	9				15	
	AVG -	6.00	2.89				4.13	
	STD -	2.65	1.66				2.60	
	MAX -	10	6				10	
	MIN -	3	1				1	
	SUM -	36	26				62	
6	N -	5	3				8	
	AVG -	3.60	1.33				2.75	
	STD -	1.02	0.47				1.39	
	MAX -	5	2				5	
	MIN -	2	1				1	
	SUM -	18	4				22	

This section, which is similar in all respects to the trenches except that there was no underlying waste trench, required an average of 3.2 drops for the first 30 cm, 5.5 drops for the second 30 cm, 7.3 drops for the third 30 cm, and 6.7 drops for the fourth 30 cm. In addition to the greater number of drops required to achieve a desired depth, a considerable amount of soil upheaval was noted around the control trench, extending to a distance of approximately 2 m from the trench. This upheaved soil volume was estimated using pre- and postcompaction elevation surveys which allowed an actual (corrected for upheaved soil) depth of compaction to be determined for the control section.

In summary, the dynamic compaction of the five TARA trenches required 2141 drops of the weight from a height of 7 m and approximately 2445 drops of the weight from a lower height (1-2 m) for leveling purposes. Knowing that the total area of the five trenches is 387 m², these total drop numbers can be expressed as 5.5 drops/m² of trench for compaction and 6.3 drops/m² for leveling purposes.

The depth of compaction of each trench was determined by comparison of a trench surface elevation survey made before compaction with that of a post-compaction elevation survey. In contrast to the control section, an insignificant amount of soil upheaval was noticed adjacent to each of the five trenches; thus, depth corrections for upheaval did not have to be made for the waste trenches as they were for the control section. Tables 33 through 37 summarize the pre- and postcompaction elevation surveys and indicate that an average depth of compaction of 0.46 m, 0.49 m, 0.60 m, 0.63 m, and 0.54 m was achieved for trenches 2, 3, 4, 5, and 6, respectively. Knowing the length and width of each trench allows one to calculate the total volume of compaction that took place for each trench. These uncorrected volumes (uncorrected for compaction that took place in the control section) are summarized for each trench in Tables 33 through 37.

The depths and volumes of trench compaction reported in the previous paragraph are uncorrected [i.e. the values have not been corrected for the degree of compaction that could be achieved in the trench cover alone (without an underlying trench)]. To obtain this correction value, a 3 m x 3 m control section was laid out adjacent to trench 3 (Fig. 35) and compacted with the concrete weight in a manner identical to the waste trench compaction. Elevation survey points were established at 41 locations around the perimeter of the trench out to a distance of 1.5 m (Fig. 36). By comparing the elevations at the survey points before and after compaction, the depth of the control section crater could be determined (0.75 m) and the total volume of soil upheaval that occurred could be estimated. Dividing the perimeter of the control section into a set of concentric octagonal elements (shown as dotted lines in Fig. 36), and summing element volumes, resulted in a total upheaved soil volume of 4.44 m³. The corrected control crater volume (i.e. the actual volume reduction achieved at the control section had the soil not been able to be pushed up) was calculated using the following equation

Table 33. Elevation of TARA trench 2 before and after trench compaction

Before Compaction		After Compaction		Change in Elev. (m)	Trench Width (m)	Unit Width (m)	Unit Volume (m ³)
Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)						
0.3	255.21	0.3	254.95	0.26	3.05	0.305	0.24
	255.21	0.6	254.68	0.53	3.06	0.305	0.49
	255.21	0.9	254.68	0.53	3.07	0.305	0.49
	255.21	1.2	254.64	0.57	3.07	0.305	0.54
	255.21	1.5	254.64	0.57	3.08	0.305	0.54
	255.21	1.8	254.65	0.56	3.09	0.305	0.53
	255.21	2.1	254.69	0.52	3.10	0.305	0.49
	255.21	2.4	254.64	0.57	3.11	0.305	0.54
	255.21	2.7	254.63	0.58	3.12	0.305	0.55
	255.21	3.0	254.63	0.58	3.12	0.305	0.55
	255.20	3.4	254.69	0.51	3.13	0.305	0.49
	255.20	3.7	254.76	0.44	3.14	0.305	0.42
	255.20	4.0	254.79	0.41	3.15	0.305	0.39
	255.20	4.3	254.80	0.40	3.16	0.305	0.38
	255.20	4.6	254.78	0.42	3.16	0.305	0.40
	255.20	4.9	254.78	0.42	3.17	0.305	0.41
	255.20	5.2	254.95	0.25	3.18	0.305	0.25
	255.20	5.5	255.04	0.16	3.19	0.305	0.16
	255.20	5.8	255.11	0.09	3.20	0.305	0.09
6.1	255.20	6.1	255.08	0.12	3.21	0.305	0.12
	255.21	6.4	254.86	0.35	3.21	0.305	0.34
	255.23	6.7	254.82	0.41	3.22	0.305	0.40
	255.24	7.0	254.79	0.45	3.23	0.305	0.44
	255.25	7.3	255.00	0.25	3.24	0.305	0.25
	255.27	7.6	255.08	0.19	3.25	0.305	0.19
	255.28	7.9	255.10	0.18	3.25	0.305	0.18
	255.29	8.2	254.98	0.32	3.26	0.305	0.31
	255.31	8.5	254.95	0.36	3.27	0.305	0.36
	255.32	8.8	254.96	0.35	3.28	0.305	0.35
	255.33	9.1	254.97	0.36	3.29	0.305	0.37
	255.35	9.4	254.95	0.39	3.30	0.305	0.40
	255.36	9.8	254.93	0.42	3.30	0.305	0.43
	255.37	10.1	254.91	0.46	3.31	0.305	0.46
	255.39	10.4	254.95	0.44	3.32	0.305	0.44
10.7	255.40	10.7	254.97	0.43	3.33	0.305	0.44
	255.41	11.0	254.93	0.48	3.34	0.305	0.49
	255.42	11.3	254.97	0.45	3.35	0.305	0.46
	255.43	11.6	255.03	0.40	3.35	0.305	0.41
	255.44	11.9	255.06	0.38	3.36	0.305	0.39
	255.45	12.2	255.02	0.44	3.37	0.305	0.45
	255.47	12.5	255.04	0.42	3.38	0.305	0.44
	255.48	12.8	255.08	0.39	3.39	0.305	0.41
	255.49	13.1	255.09	0.40	3.39	0.305	0.41
	255.50	13.4	255.00	0.50	3.40	0.305	0.52

Table 33. (Continued)

Before Compaction		After Compaction		Change in Elev. (m)	Trench Width (m)	Unit Width (m)	Unit Volume (m ³)
Dist. from Elev. Trench North (m)	End (m)	Dist. from Elev. Trench North (m)	End (m)				
14.6	255.51	13.7	255.01	0.50	3.41	0.305	0.52
	255.52	14.0	255.03	0.49	3.42	0.305	0.51
	255.53	14.3	255.09	0.44	3.43	0.305	0.46
	255.54	14.6	255.10	0.44	3.44	0.305	0.46
	255.55	14.9	255.17	0.37	3.44	0.305	0.39
	255.55	15.2	255.18	0.37	3.45	0.305	0.39
	255.55	15.5	255.01	0.54	3.46	0.305	0.57
	255.55	15.8	255.03	0.53	3.47	0.305	0.56
	255.56	16.2	255.11	0.45	3.48	0.305	0.48
	255.56	16.5	255.25	0.31	3.48	0.305	0.33
	255.56	16.8	255.22	0.34	3.49	0.305	0.36
	255.56	17.1	255.18	0.38	3.50	0.305	0.41
	255.57	17.4	255.14	0.42	3.51	0.305	0.45
	255.57	17.7	255.10	0.47	3.52	0.305	0.51
18.3	255.57	18.0	255.03	0.55	3.53	0.305	0.59
	255.57	18.3	255.11	0.47	3.53	0.305	0.50
	255.57	18.6	255.14	0.43	3.54	0.305	0.47
	255.57	18.9	255.14	0.43	3.55	0.305	0.46
	255.57	19.2	255.12	0.45	3.56	0.305	0.49
	255.57	19.5	255.13	0.44	3.57	0.305	0.48
	255.57	19.8	255.11	0.46	3.57	0.305	0.51
	255.57	20.1	255.13	0.44	3.58	0.305	0.48
	255.57	20.4	255.04	0.53	3.59	0.305	0.58
	255.57	20.7	255.06	0.51	3.60	0.305	0.56
	255.58	21.0	255.04	0.54	3.61	0.305	0.59
	255.58	21.3	254.93	0.65	3.62	0.305	0.72
	255.58	21.6	255.02	0.56	3.62	0.305	0.62
	255.58	21.9	255.03	0.55	3.63	0.305	0.61
23.2	255.58	22.2	255.06	0.52	3.64	0.305	0.58
	255.58	22.6	254.95	0.63	3.65	0.305	0.70
	255.58	22.9	255.03	0.55	3.66	0.305	0.61
	255.58	23.2	255.07	0.51	3.66	0.305	0.57
	255.57	23.5	255.01	0.57	3.67	0.305	0.63
	255.57	23.8	255.12	0.45	3.68	0.305	0.50
	255.56	24.1	255.06	0.49	3.69	0.305	0.56
	255.55	24.4	255.05	0.50	3.70	0.305	0.57
	255.54	24.7	255.02	0.52	3.71	0.305	0.59
	255.53	25.0	255.02	0.51	3.71	0.305	0.58
	255.53	25.3	255.06	0.47	3.72	0.305	0.53
	255.52	25.6	255.10	0.42	3.73	0.305	0.48
	255.51	25.9	255.13	0.38	3.74	0.305	0.44
	255.50	26.2	254.96	0.54	3.75	0.305	0.61
	255.50	26.5	254.95	0.54	3.76	0.305	0.62
	255.49	26.8	254.93	0.55	3.76	0.305	0.63

Table 33. (Continued)

Before Compaction		After Compaction		Change in Elev. (m)	Trench Width (m)	Unit Width (m)	Unit Volume (m ³)
Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)				
	255.48	27.1	254.69	0.79	3.77	0.305	0.91
	255.47	27.4	254.93	0.54	3.78	0.305	0.62
	255.46	27.7	254.85	0.62	3.79	0.305	0.71
	255.46	28.0	254.80	0.66	3.80	0.305	0.76
	255.45	28.3	254.74	0.71	3.80	0.305	0.83
28.6	255.44	28.6	254.74	0.70	3.81	0.305	0.81
SW CORNER	255.60	SW CORNER	255.65	-----	-----		-----
SE CORNER	255.28	SE CORNER	255.29				
NE CORNER	255.17	NE CORNER	255.26	AVG	AVG		SUM
NW CORNER	255.26	NW CORNER	255.43	0.46	3.43		45.32

Table 34. Elevation of TARA trench 3 before and after trench compaction

Before Compaction		After Compaction		Change Trench		Unit	Unit
Dist. from Elev.	Trench North (m)	Dist. from Elev.	Trench North (m)	in Elev. (m)	Width (m)	Width (m)	Volume (m ³)
End (m)		End (m)					
0.30	255.33	0.30	255.02	0.31	3.69	0.305	0.35
	255.35	0.61	254.85	0.50	3.68	0.305	0.57
	255.38	0.91	254.86	0.51	3.67	0.305	0.57
	255.40	1.22	254.89	0.51	3.66	0.305	0.57
	255.43	1.52	254.93	0.50	3.65	0.305	0.55
	255.45	1.83	255.05	0.40	3.64	0.305	0.44
	255.47	2.13	255.15	0.33	3.63	0.305	0.36
	255.50	2.44	255.10	0.40	3.62	0.305	0.44
	255.52	2.74	255.18	0.34	3.61	0.305	0.37
	255.55	3.05	255.12	0.43	3.60	0.305	0.47
	255.57	3.35	255.19	0.38	3.59	0.305	0.41
3.66	255.60	3.66	255.33	0.27	3.57	0.305	0.29
	255.62	3.96	255.37	0.25	3.56	0.305	0.27
	255.65	4.27	255.32	0.32	3.55	0.305	0.35
	255.67	4.57	255.31	0.36	3.54	0.305	0.39
	255.70	4.88	255.36	0.34	3.53	0.305	0.36
	255.72	5.18	255.36	0.36	3.52	0.305	0.38
	255.74	5.49	255.27	0.47	3.51	0.305	0.51
	255.77	5.79	255.27	0.50	3.50	0.305	0.53
	255.79	6.10	255.27	0.52	3.49	0.305	0.56
	255.82	6.40	255.32	0.50	3.48	0.305	0.53
	255.84	6.71	255.32	0.52	3.47	0.305	0.55
	255.86	7.01	255.34	0.52	3.46	0.305	0.55
7.31	255.87	7.31	255.42	0.47	3.45	0.305	0.50
	255.90	7.62	255.48	0.42	3.44	0.305	0.44
	255.92	7.92	255.42	0.50	3.43	0.305	0.53
	255.93	8.23	255.41	0.53	3.42	0.305	0.55
	255.95	8.53	255.40	0.55	3.41	0.305	0.57
	255.96	8.84	255.41	0.56	3.40	0.305	0.57
	255.98	9.14	255.46	0.52	3.39	0.305	0.54
	255.99	9.45	255.48	0.52	3.38	0.305	0.53
	256.01	9.75	255.54	0.47	3.36	0.305	0.48
	256.02	10.06	255.60	0.43	3.35	0.305	0.44
	256.04	10.36	255.57	0.47	3.34	0.305	0.47
	256.05	10.67	255.56	0.50	3.33	0.305	0.51
	256.07	10.97	255.56	0.51	3.32	0.305	0.52
	256.08	11.28	255.58	0.51	3.31	0.305	0.51
	256.10	11.58	255.60	0.50	3.30	0.305	0.50
	256.11	11.89	255.61	0.50	3.29	0.305	0.50
12.19	256.13	12.19	255.50	0.63	3.28	0.305	0.63
	256.13	12.50	255.51	0.62	3.27	0.305	0.62
	256.14	12.80	255.70	0.43	3.26	0.305	0.43
	256.14	13.11	255.66	0.48	3.25	0.305	0.48
	256.14	13.41	255.54	0.60	3.24	0.305	0.59

Table 34. (Continued)

Before Compaction		After Compaction		Change in Elev. (m)	Trench Width (m)	Unit Width (m)	Unit Volume (m ³)
Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)				
16.15	256.15	13.72	255.55	0.60	3.23	0.305	0.59
	256.15	14.02	255.58	0.57	3.22	0.305	0.56
	256.16	14.32	255.56	0.59	3.21	0.305	0.58
	256.16	14.63	255.45	0.71	3.20	0.305	0.69
	256.16	14.93	255.54	0.62	3.19	0.305	0.60
	256.17	15.24	255.60	0.56	3.18	0.305	0.54
	256.17	15.54	255.57	0.60	3.17	0.305	0.58
	256.17	15.85	255.62	0.55	3.15	0.305	0.53
	256.18	16.15	255.65	0.53	3.14	0.305	0.50
	256.18	16.46	255.59	0.59	3.13	0.305	0.56
	256.18	16.76	255.58	0.60	3.12	0.305	0.57
	256.18	17.07	255.62	0.56	3.11	0.305	0.53
	256.18	17.37	255.64	0.54	3.10	0.305	0.52
	256.18	17.68	255.59	0.59	3.09	0.305	0.56
	256.18	17.98	255.58	0.60	3.08	0.305	0.56
	256.18	18.29	255.65	0.53	3.07	0.305	0.50
	256.19	18.59	255.73	0.46	3.06	0.305	0.43
	256.19	18.90	255.64	0.55	3.05	0.305	0.51
	256.19	19.20	255.63	0.56	3.04	0.305	0.52
	256.19	19.51	255.69	0.50	3.03	0.305	0.46
21.03	256.19	19.81	255.76	0.43	3.02	0.305	0.40
	256.19	20.12	255.64	0.55	3.01	0.305	0.50
	256.19	20.42	255.58	0.61	3.00	0.305	0.56
	256.19	20.73	255.60	0.59	2.99	0.305	0.54
	256.19	21.03	255.62	0.57	2.98	0.305	0.51
	256.18	21.33	255.69	0.49	2.97	0.305	0.44
	256.17	21.64	255.72	0.45	2.96	0.305	0.40
	256.15	21.94	255.76	0.39	2.94	0.305	0.35
	256.14	22.25	255.72	0.43	2.93	0.305	0.38
	256.13	22.55	255.70	0.43	2.92	0.305	0.38
	256.12	22.86	255.61	0.51	2.91	0.305	0.45
	256.11	23.16	255.53	0.57	2.90	0.305	0.51
	256.10	23.47	255.57	0.52	2.89	0.305	0.46
	256.08	23.77	255.58	0.50	2.88	0.305	0.44
	256.07	24.08	255.62	0.45	2.87	0.305	0.40
	256.06	24.38	255.63	0.43	2.86	0.305	0.38
	256.05	24.69	255.51	0.54	2.85	0.305	0.47
	256.04	24.99	255.50	0.54	2.84	0.305	0.47
	256.02	25.30	255.48	0.54	2.83	0.305	0.47
	256.01	25.60	255.51	0.50	2.82	0.305	0.43
	256.00	25.91	255.46	0.54	2.81	0.305	0.46
	255.99	26.21	255.46	0.52	2.80	0.305	0.45
	255.98	26.52	255.39	0.59	2.79	0.305	0.50
	255.97	26.82	255.42	0.55	2.78	0.305	0.47

Table 34. (Continued)

Before Compaction		After Compaction		Change in Elev. (m)	Trench Width (m)	Unit Width (m)	Unit Volume (m ³)
Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)				
	255.95	27.13	255.57	0.39	2.77	0.305	0.33
	255.94	27.43	255.64	0.30	2.76	0.305	0.26
27.74	255.93	27.74	256.03	-0.10	2.74	0.305	-0.08
SW CORNER	256.01	SW CORNER	256.06	-----	-----		-----
SE CORNER	255.85	SE CORNER	255.96				
NE CORNER	255.28	NE CORNER	255.48	AVG	AVG		SUM
NW CORNER	255.37	NW CORNER	255.52	0.49	3.22		43.52

Table 35. Elevation of TARA trench 4 before and after trench compaction

Before Compaction		After Compaction		Change in Elev. (m)	Trench Width (m)	Unit Width (m)	Unit Volume (m ³)
Dist. from Elev. Trench North (m) End (m)		Dist. from Elev. Trench North (m) End (m)					
0.30	255.88	0.30	255.57	0.31	2.74	0.305	0.26
	255.91	0.61	255.46	0.45	2.74	0.305	0.37
	255.94	0.91	255.51	0.43	2.74	0.305	0.36
	255.97	1.22	255.56	0.41	2.74	0.305	0.35
	256.00	1.52	255.53	0.47	2.74	0.305	0.39
	256.03	1.83	255.57	0.46	2.74	0.305	0.38
2.13	256.06	2.13	255.60	0.46	2.75	0.305	0.38
	256.06	2.44	255.63	0.43	2.75	0.305	0.36
	256.07	2.74	255.58	0.49	2.75	0.305	0.41
	256.08	3.05	255.56	0.51	2.75	0.305	0.43
	256.08	3.35	255.53	0.56	2.75	0.305	0.47
	256.09	3.66	255.53	0.56	2.75	0.305	0.47
	256.10	3.96	255.45	0.65	2.75	0.305	0.54
	256.11	4.27	255.50	0.60	2.75	0.305	0.50
	256.11	4.57	255.50	0.62	2.75	0.305	0.52
	256.12	4.88	255.50	0.62	2.75	0.305	0.52
	256.13	5.18	255.56	0.56	2.76	0.305	0.47
	256.13	5.49	255.45	0.68	2.76	0.305	0.57
	256.14	5.79	255.43	0.71	2.76	0.305	0.60
	256.15	6.10	255.48	0.67	2.76	0.305	0.57
6.10	256.17	6.40	255.57	0.59	2.76	0.305	0.50
	256.18	6.71	255.58	0.59	2.76	0.305	0.50
	256.19	7.01	255.57	0.62	2.76	0.305	0.53
	256.20	7.31	255.55	0.65	2.76	0.305	0.55
	256.21	7.62	255.58	0.63	2.76	0.305	0.53
	256.23	7.92	255.58	0.64	2.76	0.305	0.54
	256.24	8.23	255.60	0.64	2.77	0.305	0.54
	256.25	8.53	255.57	0.68	2.77	0.305	0.57
	256.26	8.84	255.60	0.66	2.77	0.305	0.55
	256.27	9.14	255.57	0.71	2.77	0.305	0.60
	256.29	9.45	255.59	0.70	2.77	0.305	0.59
	256.30	9.75	255.61	0.69	2.77	0.305	0.58
	256.31	10.06	255.68	0.63	2.77	0.305	0.53
	256.31	10.36	255.57	0.74	2.77	0.305	0.63
10.06	256.32	10.67	255.61	0.71	2.77	0.305	0.60
	256.32	10.97	255.62	0.70	2.77	0.305	0.59
	256.32	11.28	255.69	0.63	2.78	0.305	0.53
	256.32	11.58	255.68	0.65	2.78	0.305	0.55
	256.32	11.89	255.66	0.66	2.78	0.305	0.56
	256.32	12.19	255.67	0.65	2.78	0.305	0.55
	256.33	12.50	255.69	0.64	2.78	0.305	0.54
	256.33	12.80	255.70	0.63	2.78	0.305	0.54
	256.33	13.11	255.66	0.67	2.78	0.305	0.57
	256.33	13.41	255.69	0.64	2.78	0.305	0.55

Table 35. (Continued)

Before Compaction		After Compaction		Change in Elev. (m)	Trench Width (m)	Unit Width (m)	Unit Volume (m ³)
Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)				
14.32	256.33	13.72	255.69	0.64	2.78	0.305	0.55
	256.33	14.02	255.70	0.64	2.78	0.305	0.54
	256.34	14.32	255.71	0.63	2.79	0.305	0.54
	256.33	14.63	255.74	0.59	2.79	0.305	0.50
	256.33	14.93	255.73	0.60	2.79	0.305	0.51
	256.33	15.24	255.72	0.61	2.79	0.305	0.52
	256.33	15.54	255.74	0.59	2.79	0.305	0.50
	256.33	15.85	255.73	0.60	2.79	0.305	0.51
	256.33	16.15	255.74	0.59	2.79	0.305	0.51
	256.33	16.46	255.74	0.59	2.79	0.305	0.50
	256.33	16.76	255.72	0.61	2.79	0.305	0.52
	256.33	17.07	255.74	0.59	2.79	0.305	0.50
	256.33	17.37	255.75	0.58	2.80	0.305	0.49
	256.33	17.68	255.73	0.60	2.80	0.305	0.51
19.81	256.33	17.98	255.75	0.58	2.80	0.305	0.49
	256.33	18.29	255.77	0.56	2.80	0.305	0.48
	256.33	18.59	255.78	0.55	2.80	0.305	0.47
	256.33	18.90	255.74	0.59	2.80	0.305	0.50
	256.33	19.20	255.68	0.65	2.80	0.305	0.56
	256.33	19.51	255.64	0.69	2.80	0.305	0.59
	256.34	19.81	255.69	0.65	2.80	0.305	0.55
	256.33	20.12	255.71	0.61	2.80	0.305	0.53
	256.32	20.42	255.71	0.60	2.81	0.305	0.52
	256.31	20.73	255.69	0.62	2.81	0.305	0.53
	256.30	21.03	255.73	0.57	2.81	0.305	0.49
	256.29	21.33	255.72	0.57	2.81	0.305	0.48
	256.28	21.64	255.74	0.54	2.81	0.305	0.46
	256.27	21.94	255.74	0.53	2.81	0.305	0.45
24.08	256.26	22.25	255.65	0.61	2.81	0.305	0.52
	256.25	22.55	255.61	0.64	2.81	0.305	0.55
	256.24	22.86	255.60	0.64	2.81	0.305	0.55
	256.23	23.16	255.69	0.54	2.81	0.305	0.47
	256.22	23.47	255.63	0.59	2.82	0.305	0.51
	256.21	23.77	255.63	0.58	2.82	0.305	0.50
	256.20	24.08	255.71	0.49	2.83	0.305	0.42
	SW CORNER	256.25	SW CORNER	256.28	-----	-----	-----
	SE CORNER	256.14	SE CORNER	256.07			
	NE CORNER	255.85	NE CORNER	256.06	AVG	AVG	SUM
	NW CORNER	255.92	NW CORNER	256.00	0.60	2.78	40.07

Table 36. Elevation of TARA trench 5 before and after trench compaction

Before Compaction		After Compaction		Change in Elev. (m)	Trench Width (m)	Unit Width (m)	Unit Volume (m ³)
Dist. from Trench North End (m)	Elev. (m)	Dist. from Trench North End (m)	Elev. (m)				
0.30	255.81	0.30	255.29	0.52	2.93	0.305	0.47
	255.85	0.61	255.35	0.50	2.93	0.305	0.45
	255.88	0.91	255.39	0.49	2.93	0.305	0.44
	255.92	1.22	255.50	0.41	2.93	0.305	0.37
	255.95	1.52	255.56	0.40	2.94	0.305	0.36
	255.99	1.83	255.49	0.50	2.94	0.305	0.45
2.44	256.03	2.13	255.49	0.54	2.94	0.305	0.48
	256.07	2.44	255.51	0.56	2.94	0.305	0.50
	256.08	2.74	255.54	0.54	2.94	0.305	0.48
	256.09	3.05	255.53	0.56	2.94	0.305	0.50
	256.11	3.35	255.56	0.55	2.95	0.305	0.50
	256.12	3.66	255.55	0.57	2.95	0.305	0.52
	256.14	3.96	255.53	0.60	2.95	0.305	0.54
	256.15	4.27	255.57	0.58	2.95	0.305	0.52
	256.16	4.57	255.60	0.57	2.95	0.305	0.51
	256.18	4.88	255.63	0.54	2.95	0.305	0.49
	256.19	5.18	255.70	0.49	2.95	0.305	0.44
	256.21	5.49	255.57	0.63	2.96	0.305	0.57
	256.22	5.79	255.58	0.64	2.96	0.305	0.58
	256.23	6.10	255.62	0.61	2.96	0.305	0.55
6.71	256.25	6.40	255.64	0.61	2.96	0.305	0.55
	256.26	6.71	255.65	0.61	2.96	0.305	0.55
	256.27	7.01	255.65	0.62	2.96	0.305	0.56
	256.28	7.31	255.63	0.65	2.97	0.305	0.59
	256.29	7.62	255.60	0.69	2.97	0.305	0.62
	256.30	7.92	255.62	0.67	2.97	0.305	0.61
	256.31	8.23	255.64	0.67	2.97	0.305	0.61
	256.32	8.53	255.64	0.68	2.97	0.305	0.62
	256.33	8.84	255.71	0.62	2.97	0.305	0.56
	256.34	9.14	255.73	0.61	2.98	0.305	0.55
	256.35	9.45	255.78	0.57	2.98	0.305	0.52
	256.36	9.75	255.78	0.58	2.98	0.305	0.53
	256.37	10.06	255.79	0.57	2.98	0.305	0.52
	256.38	10.36	255.84	0.54	2.98	0.305	0.49
12.19	256.39	10.67	255.84	0.55	2.98	0.305	0.50
	256.40	10.97	255.84	0.55	2.98	0.305	0.50
	256.41	11.28	255.82	0.59	2.99	0.305	0.54
	256.42	11.58	255.73	0.69	2.99	0.305	0.63
	256.43	11.89	255.79	0.63	2.99	0.305	0.58
	256.44	12.19	255.84	0.60	2.99	0.305	0.54
	256.45	12.50	255.86	0.58	2.99	0.305	0.53
	256.45	12.80	255.82	0.64	2.99	0.305	0.58
	256.46	13.11	255.83	0.63	3.00	0.305	0.58
	256.47	13.41	255.82	0.65	3.00	0.305	0.59

Table 36. (Continued)

Before Compaction		After Compaction		Change in Elev. (m)	Trench Width (m)	Unit Width (m)	Unit Volume (m ³)
Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)				
	256.48	13.72	255.84	0.64	3.00	0.305	0.59
	256.49	14.02	255.88	0.61	3.00	0.305	0.56
	256.50	14.32	255.84	0.66	3.00	0.305	0.60
	256.51	14.63	255.89	0.61	3.00	0.305	0.56
	256.51	14.93	255.94	0.57	3.00	0.305	0.53
	256.52	15.24	255.96	0.56	3.01	0.305	0.51
	256.53	15.54	255.90	0.63	3.01	0.305	0.58
15.85	256.54	15.85	255.84	0.70	3.01	0.305	0.64
	256.54	16.15	255.86	0.68	3.01	0.305	0.63
	256.54	16.46	255.88	0.66	3.01	0.305	0.60
	256.54	16.76	255.88	0.66	3.01	0.305	0.60
	256.54	17.07	255.93	0.61	3.02	0.305	0.56
	256.54	17.37	255.89	0.65	3.02	0.305	0.60
	256.54	17.68	255.88	0.66	3.02	0.305	0.61
	256.54	17.98	255.92	0.62	3.02	0.305	0.57
	256.54	18.29	255.87	0.67	3.02	0.305	0.62
	256.54	18.59	255.83	0.71	3.02	0.305	0.65
	256.54	18.90	255.85	0.69	3.03	0.305	0.63
	256.54	19.20	255.85	0.69	3.03	0.305	0.64
	256.54	19.51	255.77	0.77	3.03	0.305	0.71
	256.54	19.81	255.75	0.79	3.03	0.305	0.73
	256.54	20.12	255.74	0.80	3.03	0.305	0.74
20.42	256.55	20.42	255.81	0.74	3.03	0.305	0.69
	256.54	20.73	255.80	0.74	3.03	0.305	0.68
	256.52	21.03	255.81	0.72	3.04	0.305	0.67
	256.51	21.33	255.76	0.75	3.04	0.305	0.70
	256.50	21.64	255.75	0.75	3.04	0.305	0.69
	256.49	21.94	255.68	0.81	3.04	0.305	0.75
	256.48	22.25	255.68	0.80	3.04	0.305	0.74
	256.47	22.55	255.70	0.77	3.04	0.305	0.72
	256.46	22.86	255.72	0.74	3.05	0.305	0.69
	256.45	23.16	255.81	0.64	3.05	0.305	0.60
	256.44	23.47	255.85	0.59	3.05	0.305	0.55
23.77	256.43	23.77	255.94	0.49	3.05	0.305	0.46
SW CORNER	256.47	SW CORNER	256.50	-----	-----	-----	-----
SE CORNER	256.38	SE CORNER	256.42				
NE CORNER	255.88	NE CORNER	255.89	AVG	AVG		SUM
NW CORNER	277.74	NW CORNER	255.72	0.63	2.99		44.53

Table 37. Elevation of TARA trench 6 before and after trench compaction

Before Compaction		After Compaction		Change in Elev. (m)	Trench Width (m)	Unit Width (m)	Unit Volume (m ³)
Dist. from Elev. Trench North (m) End (m)		Dist. from Elev. Trench North (m) End (m)					
0.30	255.55	0.30	255.27	0.28	2.53	0.305	0.22
	255.61	0.61	255.27	0.34	2.53	0.305	0.26
	255.68	0.91	255.32	0.35	2.53	0.305	0.27
	255.74	1.22	255.32	0.42	2.54	0.305	0.32
	255.80	1.52	255.35	0.45	2.54	0.305	0.35
	255.86	1.83	255.48	0.38	2.54	0.305	0.30
	255.93	2.13	255.43	0.50	2.54	0.305	0.39
	255.99	2.44	255.51	0.48	2.54	0.305	0.37
2.74	256.05	2.74	255.55	0.50	2.55	0.305	0.39
	256.07	3.05	255.46	0.60	2.55	0.305	0.47
	256.09	3.35	255.58	0.51	2.55	0.305	0.40
	256.10	3.66	255.68	0.42	2.55	0.305	0.33
	256.12	3.96	255.64	0.48	2.55	0.305	0.37
	256.14	4.27	255.64	0.50	2.56	0.305	0.39
	256.16	4.57	255.63	0.53	2.56	0.305	0.41
	256.18	4.88	255.65	0.52	2.56	0.305	0.41
	256.19	5.18	255.76	0.43	2.56	0.305	0.34
	256.21	5.49	255.76	0.45	2.56	0.305	0.35
	256.23	5.79	255.75	0.48	2.57	0.305	0.38
	256.25	6.10	255.79	0.46	2.57	0.305	0.36
	256.27	6.40	255.77	0.49	2.57	0.305	0.39
	256.28	6.71	255.81	0.47	2.57	0.305	0.37
	256.30	7.01	255.83	0.47	2.57	0.305	0.37
	256.32	7.31	255.80	0.52	2.58	0.305	0.41
7.62	256.34	7.62	255.81	0.53	2.58	0.305	0.42
	256.35	7.92	255.80	0.55	2.58	0.305	0.43
	256.36	8.23	255.85	0.52	2.58	0.305	0.41
	256.38	8.53	255.90	0.48	2.58	0.305	0.37
	256.39	8.84	255.93	0.46	2.59	0.305	0.37
	256.40	9.14	255.95	0.45	2.59	0.305	0.36
	256.41	9.45	255.94	0.47	2.59	0.305	0.38
	256.42	9.75	255.97	0.45	2.59	0.305	0.36
	256.44	10.06	255.99	0.45	2.59	0.305	0.36
	256.45	10.36	255.95	0.50	2.60	0.305	0.39
	256.46	10.67	255.99	0.47	2.60	0.305	0.37
	256.47	10.97	256.00	0.47	2.60	0.305	0.37
	256.48	11.28	256.00	0.48	2.60	0.305	0.38
	256.50	11.58	255.85	0.64	2.60	0.305	0.51
	256.51	11.89	255.79	0.72	2.61	0.305	0.57
	256.52	12.19	255.90	0.62	2.61	0.305	0.49
12.50	256.53	12.50	255.93	0.60	2.61	0.305	0.48
	256.54	12.80	255.90	0.64	2.61	0.305	0.51
	256.54	13.11	255.92	0.63	2.61	0.305	0.50
	256.55	13.41	255.96	0.59	2.62	0.305	0.47

Table 37. (Continued)

Before Compaction		After Compaction		Change in Elev. (m)	Trench Width (m)	Unit Width (m)	Unit Volume (m ³)
Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)	Dist. from Elev. Trench North (m) End (m)				
	256.55	13.72	255.98	0.57	2.62	0.305	0.46
	256.56	14.02	255.99	0.57	2.62	0.305	0.46
	256.57	14.32	255.98	0.59	2.62	0.305	0.47
	256.57	14.63	255.97	0.60	2.62	0.305	0.48
	256.58	14.93	255.98	0.60	2.63	0.305	0.48
	256.58	15.24	256.01	0.57	2.63	0.305	0.46
	256.59	15.54	256.05	0.54	2.63	0.305	0.44
	256.60	15.85	256.00	0.59	2.63	0.305	0.48
	256.60	16.15	256.00	0.60	2.63	0.305	0.48
	256.61	16.46	255.95	0.66	2.64	0.305	0.53
	256.61	16.76	255.94	0.68	2.64	0.305	0.54
	256.62	17.07	255.93	0.69	2.64	0.305	0.56
17.37	256.63	17.37	255.95	0.68	2.64	0.305	0.55
	256.63	17.68	256.01	0.62	2.64	0.305	0.50
	256.62	17.98	256.03	0.60	2.65	0.305	0.48
	256.62	18.29	256.03	0.60	2.65	0.305	0.48
	256.62	18.59	256.05	0.57	2.65	0.305	0.46
	256.62	18.90	256.05	0.57	2.65	0.305	0.46
	256.61	19.20	256.04	0.57	2.65	0.305	0.46
	256.61	19.51	256.07	0.53	2.66	0.305	0.43
	256.61	19.81	256.00	0.61	2.66	0.305	0.49
	256.60	20.12	256.02	0.58	2.66	0.305	0.47
	256.60	20.42	256.03	0.57	2.66	0.305	0.47
	256.60	20.73	256.03	0.56	2.66	0.305	0.46
	256.59	21.03	256.05	0.54	2.67	0.305	0.44
21.33	256.59	21.33	256.04	0.55	2.67	0.305	0.45
	256.58	21.64	256.05	0.53	2.67	0.305	0.43
	256.57	21.94	256.00	0.57	2.67	0.305	0.47
	256.56	22.25	255.94	0.62	2.67	0.305	0.50
	256.55	22.55	255.84	0.71	2.68	0.305	0.58
	256.54	22.86	255.89	0.65	2.68	0.305	0.53
	256.53	23.16	255.96	0.57	2.68	0.305	0.47
23.47	256.52	23.47	256.04	0.48	2.68	0.305	0.39
SW CORNER	256.54	SW CORNER	256.67	-----	-----		-----
SE CORNER	256.50	SE CORNER	256.55				
NE CORNER	255.66	NE CORNER	255.82	AVG	AVG		SUM
NW CORNER	255.44	NW CORNER	255.69	0.54	2.61		32.89

Fig. 36. Location of the control trench surface elevation points before and after trench compaction.

$$CV_{cc} = (L \times W \times D) - 4.44 \text{ m}^3$$

where, CV_{cc} = corrected control crater volume, m^3
 L = control section length, 2.74 m
 W = control section width, 2.74 m
 D = control section depth, 0.75 m.

Solving the above equation yields a corrected control crater volume of 1.21 m^3 and, therefore, a corrected control crater depth of 0.16 m. In other words, the approximate 3 m x 3 m control section could actually be compacted to a depth of 0.16 m, yielding a total compacted volume of 1.21 m^3 .

The control section depth of 0.16 m was then subtracted from the average trench crater depths, resulting in corrected trench crater depths. These depths are summarized in Table 38 and range from a minimum of 0.30 m in trench 2 to a maximum of 0.47 m in trench 5. The corrected trench crater volume was then calculated as

$$CV_{tc} = (D_t - 0.16) \times W \times L$$

where, CV_{tc} = corrected trench crater volume, m^3
 D_t = trench depth, m
 W = trench width, m
 L = trench length, m.

The corrected trench crater volumes were then compared to the volume of water-accessible void space (measured via the water pump-in tests described above) and expressed as a percentage of this value. For example, Table 38 shows that a compaction volume of 29.48 m^3 was achieved over trench 2, accounting for 96.9% of the measured water-accessible void space of 30.42 m^3 . These water-accessible void space reductions ranged from a low of 48.2% to a high of 115%, with an average value of 77%.

Several sources of error could account for the variations in trench void reduction that were observed. First, the water pump-in tests could underestimate the actual trench void volume if all observation wells along the trench did not maintain equal elevations during the filling process. In other words, only one side of the trench would have actually been filled with water while the other side of the trench would have been partially filled. This would lead to an overestimate in the trench void reduction such as was the case with trench 3 (115% reduction). Another source of error could be void volume within waste packages themselves that was not measured in the water pump-in tests but was accounted for in the trench crater volume after the waste packages were smashed by dynamic compaction. This would again lead to an overestimate of the trench void reduction such as was the case for trench 3. One last point to consider is that the actual void volume (volume of air) of the TARA trenches was not measured by the water pump-in tests, only the water-accessible void volume, which is smaller. This is because the trenches contain a certain volume that cannot be saturated during the relatively short water pump-in tests and also because of the formation of air pockets in and around the waste and soil backfill.

Table 38. Percentage reduction in trench water-accessible void space achieved by dynamic compaction

Trench Number	Average Crater Width (m)	Average Crater Length (m)	Average Crater Depth (m)	Corrected Crater Depth (m)	Corrected Crater Volume (m ³)	Water Void (m ³)	Void Redu. (%)
2	3.43	28.65	0.46	0.30	29.48	30.42	96.9
3	3.22	27.74	0.49	0.33	29.48	25.72	115
4	2.78	24.08	0.60	0.44	29.45	61.04	48.2
5	2.99	23.77	0.63	0.47	33.40	58.79	56.8
6	2.61	23.47	0.54	0.38	23.28	35.18	66.2
Control	2.74	2.74	0.16	-	-	-	-

This results in a somewhat lower reduction of total trench void space than of water-accessible void space depending on the actual ratio of total void space to water-accessible voids. Considering these sources of error, the best estimate of water-accessible void reduction achieved by compaction of the five TARA trenches is the average of the five calculated values, or 77%. This estimate will be verified next year by the independent measurement of residual void volume in the trenches as determined by the volumes of grout accepted by the compacted trenches.

SITE GRADING AND DRAINAGE

After compaction of the five trenches was completed, a thorough walkover radiation survey of the craters was carried out by ORNL Health Physics personnel. A maximum activity of 2000 cpm (background = 50 to 100 cpm) was noted in the center of trench 6, with lower activity "hot spots" found scattered over all five trenches. In all cases, activity was due to the reduction in shielding that had occurred as a result of compacting the trench cover and was not the result of contaminated soil. This was verified by removing shovelfuls of soil from "hot spots" to background areas and then failing to detect radiation in the removed soil.

Shortly after the radiation survey was completed, a bulldozer was used to cut the walls between the trench craters and move this excess dirt to the northwest edge of the trenches to lessen the existing slope in this region. The intertrench walls were carefully removed in approximate 15-cm cuts to an elevation approximately 15 cm above the trench crater floors. Every pass of the dozer was followed by an area survey by the site health physicist looking for possible contamination. The elevations of the trench crater floors were determined before and after site grading to ensure that at least 15 cm of cover was left over the craters and that the dozer did not accidentally cut into the compacted trench which could possibly spread contamination. Final site grading was done with a small rubber-tired road grader.

When site grading was completed, a soil berm was constructed around the perimeter of the site to direct surface runoff away from the trenches to the north. The berm will be an important component of the eventual trench cap and will allow for infiltrating water to be trapped by an impermeable membrane and directed to a flow measuring station where its quantity can be measured. Figure 37 illustrates the berm construction and the finished site grade.

Under routine operation, a group of compacted trenches would immediately be covered with some type of impermeable cap to prevent rainfall infiltration. At the TARA site, however, this step would prevent the planned postcompaction penetration testing as well as the use of solution grouting in further stabilizing these compacted trenches with high radioisotope inventories. For these reasons, the site was seeded and mulched after grading and the construction of a cap was delayed until testing and grouting are completed.

TIME AND PERSONNEL

Compaction of the five trenches began the morning of July 27, 1988, at the north end of trench 2. Trench 6 was completed at 1012 on August 4, 1988. Of the 7 working days during this time period, a total of 48 h was spent actually dropping the weight over the 5 trenches. An additional 1 h was spent compacting the control section. During the 7-day working period, the cable break mechanism of the crane had to be adjusted periodically, as well as crane lubrication, fueling, and cable inspection. In total, the crane was operating 85% of the time (48 h), with the additional 15% downtime due to maintenance activities.

The Rust Engineering Company personnel assigned full time to the compaction project consisted of 1 heavy equipment operator, one machine oiler, two laborers, and one metal worker. Additional truck drivers, mechanics, metal workers, and laborers were used on an as-needed basis. Personnel from ORNL consisted of one health physicist, one site supervisor, and two field technicians recording data and filming the drops on videotape as part of the overall project documentation. Excluding the part-time RUST personnel, it was estimated that approximately 504 employee hours were spent during the 7-day working period compacting the trenches. Site grading, seeding, and mulching, which followed compaction, required 2 days to complete. Additional time was spent in relocating a section of the SWSA 6 fence which was required for future cap construction purposes.

Fig. 37. Location of drainage berm showing finished grade at the TARA site.

IV. REFERENCES

- APHA (American Public Health Association). 1980. Standard Methods for the Examination of Water and Wastewater. Am. Pub. Health Assoc., Washington, D. C.
- ASGI (Automated Sciences Group Inc.). 1987. Final Plan for the Demonstration and Evaluation of Stabilization and Closure Techniques for Low-Level Waste Burial Trenches at Oak Ridge National Laboratory. Oak Ridge National Laboratory. Oak Ridge, TN ORNL/RAP-42.
- Avanti International. 1985. AV-100 Chemical Grout Technical Manual. Avanti International, Webster, Texas.
- Blake, G. R. and K. H. Hartge. 1986. "Bulk Density." pp. 363-375 in, Methods of Soil Analysis. Part 1. Amer. Soc. of Agronomy, Madison, Wisconsin.
- Bly, S. G. 1988. Dynamic Compaction Demonstration SWSA-6. Oak Ridge National Laboratory. Oak Ridge, TN EAM 0640X.
- Cerling, T. E. and B. P. Spalding. 1981. Areal Distribution of ⁶⁰Co, ¹³⁷Cs, and ⁹⁰Sr in Streambed Gravels of White Oak Creek Watershed, Oak Ridge, Tennessee. Oak Ridge National Laboratory, Oak Ridge, TN ORNL/TM-7318.
- Davis, E. C., D. K. Solomon, R. B. Dreier, S. Y. Lee, P. M. Craig, A. D. Kelmers, and D. A. Lietzke. 1987. Summary of Environmental Characterization Activities at the Oak Ridge National Laboratory Solid Waste Storage Area Six FY 1986 through 1987. Oak Ridge National Laboratory. Oak Ridge, TN ORNL/RAP/LTR-87/68.
- Doyle, G. M. 1988. Solid Waste Storage Area 6 Closure Demonstration - Dynamic Compaction Phase. Oak Ridge National Laboratory. Oak Ridge, TN ORNL/ENG/SA-2027.
- Duguid, J. O., and O. M. Sealand. 1975. Reconnaissance Survey of the Intermediate-Level Liquid Waste Transfer Line Between X-10 and the Hydrofracture Site. Oak Ridge National Laboratory. Oak Ridge, TN ORNL-TM-4743.
- Klute, A. 1965. "Laboratory Measurement of Hydraulic Conductivity of Saturated Soil." C. A. Black (ed.), Methods of Soil Analysis. Part 1. Agronomy 9:210-221.
- Lande, S. S., S. J. Bosch, and P. H. Howard. 1979. "Degradation and Leaching of Acrylamide in Soil." J. Environ. Qual. 8:133-137.
- Larson, R. J., and J. H. May. 1983. "Geotechnical Aspects of Bottom Sealing Existing Hazardous Waste Landfills by Injection Grouting (Phase I - Compatibility Studies)." pp. 513-529 in, Proceedings of the First Annual Hazardous Materials Management Conference. Tower Conference Management Company, Wheaton, Illinois.

Solymar, Z. V., and D. J. Reed. 1986. "Comparison Between in-situ Test Methods." pp. 1236-1248. in, Use of In Situ Tests in Geotechnical Engineering. S. P. Clemence (ed.). Amer. Soc. Civil Engineers. New York, New York.

Spalding, B. P., L. K. Hyder, and I. L. Munro. 1985. "Grouting as a Remedial Technique for Buried Low-Level Radioactive Wastes." J. Environ. Qual. 14:389-396.

Spalding, B. P. 1986. Burial Trench Dynamic Compaction at a Humid Site. CONF-8509121. pp. 676-698. EG&G Idaho, Inc., Idaho Falls, Idaho.

Spalding, B. P., S. Y. Lee, C. D. Farmer, L. K. Hyder, and P. Supaokit. 1987. "In Situ Grouting of Buried Transuranic Waste with Polyacrylamide." in, Oak Ridge Model Conference Proceedings, pp. 39-76. CONF-871075, Volume I, Part 3. Martin Marietta Energy Systems, Inc., Oak Ridge, TN.

Valentine, C. K. 1986. Closure Technology Demonstration 19 Trench Section. Oak Ridge National Laboratory. Oak Ridge, TN ADM 0363X.

APPENDIX I

Examples of Types of Waste Placed in SWSA 6 Trenches 2, 3, 4, and 5.

APPENDIX I

Document	Trench	Date	Volume	Radiation	Isotopes
31168	2	1-30-73	20ft ³	50mrem	Co, Ir, Ra, Sb
[lead pig and metal can]					
30652	2	10-10-72	12	250	?
[HB-6 beam hole plug wrapped in plastic]					
30698	2	10-20-72	18	none	none
[28 containers of electrolyte (battery acid) in GI cans and plastic bags]					
30879	2	11-13-72	24	500	mixed
[misc cell waste in lead dumpster]					
30886	2	11-13-72	24	3000	mixed f.p.
[misc waste from cells in lead dumpster]					
30839	2	11-02-72	24	2000	?
[waste blotting paper, gloves, shoe covers, etc. double bagged in lead pan]					
30840	2	11-02-72	24	200	?
[waste paper, rubber gloves, trash from behind cell 5, HRLAF in double bags in lead pan]					
30909	2	11-16-72	18	8000	mixed f.p.
[three manipulator boots from SLFP cells 3028 in metal container]					
30838	2	11-02-72	20	1000	mixed f.p.
[three filters (two CWS and one charcoal) in cardboard and plywood]					
30910	2	11-16-72	6	<2	mixed f.p.
[heater wrapped in plastic]					
30921	2	11-21-72	6	1500	Sr90
[junk from room 105 of building 3047 in G.I. can]					
31028	2	12-14-72	15	3000	mixed f.p.
[two garbage cans - CWS- filters plus charcoal in metal containers]					
31039	2	12-19-72	60	2000	Cs137
[CWS filters in plywood container]					
30849	2	11-03-72	150	750	mixed f.p.
[roughing filters from cell ventilation pit at stack area in plywood container]					

APPENDIX I

Document	Trench	Date	Volume	Radiation	Isotopes
32124	3	6-22-73	20	6.5	U, Cs
[8 glass beakers of reactor ash in lead pigs and 2 other shielded containers]					
32123	3	6-22-73	40	140	?
[2-1/2 ton cylinder wrapped in plastic and traps]					
32121	3	6-22-73	50	0.6	U, Pu, Np
[3 cobaltous fluoride traps and transfer line in plastic]					
32170	3	07-03-73	24	400	mixed f.p.
[3 drums contaminated resin - water slurry in SS drums]					
32162	3	07-02-73	24	100	?
[hot can in lead pan]					
32174	3	07-06-73	6	4000	?
[2 Be NO ₃ pellets in hot can]					
32179	3	07-09-73	24	400	Cl ¹⁴ , Be
[unspecified in lead pan]					
32189	3	07-11-73	8	<5	Ca
[1 SS drum]					
32209	3	07-17-73	20	2000	Eu
[SS Table in clean plastic]					
32233	3	07-25-73	6	2000	Eu
[junk from cell A]					
32169	3	07-03-73	125	1000	f.p. + alpha
[HEPA filters in plastic and wood box]					
32181	3	07-09-73	24	1000	Cs ¹³⁷ , Be, Co
[can in lead pan]					
32180	3	07-09-73	10	10000	Co, Eu
[waste in 2 pierce containers]					
32208	3	07-16-73	50	50	Cs ¹³⁷ , Sr ⁹⁰
[blotter paper and plywood box on hot truck]					
32211	3	07-18-73	250	800	Sr ⁹⁰
[furnace from cell - 11 in armor plate shield bottom in plastic]					

APPENDIX I

Document	Trench	Date	Volume	Radiation	Isotopes
32212	3	07-18-73	100	10	Sr90, Cs137
[bags of debris on hot truck]					
32238	3	07-27-73	20	1	C14
[refrigerator taped closed]					
32239	3	07-27-73	8	2	mixed f.p.
[55 gal drum of radiation waste]					
32344	3	07-30-73	60	<10	Cs137, Sr90
[misc. waste on hot truck triple plastic wrap]					
32241	3	07-27-73	50	20000	Sr90, Cs137
[CV filter in plywood box plastic wrapped]					
32309	4	8-15-73	21	50	Th
[3 - 20 gal cans and 1 - 5 gal can]					
32296	4	8-10-73	150	6000	Sr90
[contaminated waste on hot truck wrapped in plastic]					
32268	4	08-02-73	10	15	Ag110
[three 1-gallon bottles of EDM dielectric oil, small holding tank, waste rags and approximately 1-pint of waste acetone in plastic bag]					
32303	4	08-14-73	100	10	U233
[old resin clo. 2 plus trash from pent house + cell V plutonium in black iron drums and in plastic]					
32334	4	08-09-73	8	<.5	H3
[aluminum drum]					
32344	4	08-20-73	5	10	?
[scrap from cell A, various Alum. S.S., + debris. Class A scrap in bucket]					
32305	4	08-14-73	60	10	Cm244
[Waste from charging area - wipes, hoses, clothing, etc. 8 - GI cans, 1 cardboard box, 1 SS 55 gal drum]					
32319	4	08-16-73	24	3	mixed f.p.
[used oil in 3 55 gal drums from 3039 stack]					
32306	4	08-14-73	12	2000	?
[spent filter from ORR pool primary water system in 30 gal drum]					

APPENDIX I

Document	Trench	Date	Volume	Radiation	Isotopes
32267	4	08-02-73	25	4000	?
[junk from cell A - 2 - GI cans and 1- 55 gal drum]					
32285	4	08-08-73	8	1200	?
[junk from cell A in 55 gal drum]					
32355	4	08-21-73	20	3000	?
[junk from cell A in two hot cans + table]					
32304	4	08-14-73	12	1200	?
[spent filters from ORR primary water system in drums and plastic]					
32369	4	08-24-73	50	100	mixed f.p.
[absolute filters from 3092 off gas scrubber in plywood box]					
32269	4	08-02-73	120	10	mixed f.p. +alpha
[wood, paper, and plastic in plastic bags]					
32343	4	08-20-73	3	5	?
[used pump oil in can]					
32339	4	08-20-73	30	none	none
[approx. 10 bags (90#) CaO lime)]					
32266	4	08-02-73	15	40	Cs137
[90,000 Ci Cs137 in 8" lead tucson container, sources doubly encapsulated and carried welded closed]					
32247	4	07-31-73	20	<.5	?
[sample preparation stage for EM-100 microscope (obsolete), 4D file cabinet]					
32261	4	08-01-73	20	<.5	?
[misc lab ware]					
32290	4	08-09-73	18	<.2	U234
[glovebox X-44735 in plywood box]					
32323	4	08-16-73	12	<.2	H3
[used oil]					
32258	4	08-01-73	36	20	?
[broken glass (some mercury) + radiation waste in yellow cans]					

APPENDIX I

Document	Trench	Date	Volume	Radiation	Isotopes
32348	4	08-21-73	30	20	?
[radiation waste in 5 yellow GI cans]					
32321	4	08-16-73	40	15	Sr90, Cs137, Cm244
[used plywood and boards]					
32302	4	08-14-73	6	6	?
[1 - empty acid carboy with busted bottom]					
32359	4	08-22-73	16	<.1	Pu
[2 - 55 gal drums containing Kinney Pump oil adsorbed in vermiculite]					
32360	4	08-22-73	78	7	Pu
[misc. Pu salvage in cardboard boxes]					
?????	4	08-07-73	12	300	mixed f.p.
[alpha, beta, + gamma contaminated equipment from hot cell operations sealed in metal drum in yellow dumpster]					
32504	5	09-28-73	24	200	mixed
[misc cell waste in lead pan]					
32476	5	09-20-73	16	<10	Cm244
[plastic suits, plastic booties, surgeons gloves + other debris in cardboard boxes]					
32492	5	09-25-73	8	850	mixed f.p.
[one charcoal roughing filter in plywood box]					
32425	5	09-05-73	24	20	Ir192
[cell waste in 3 hot cans in lead pan]					
32426	5	09-05-73	24	1200	Eu, Gd
[3 GI cans and 1 gal bucket waste in lined dumpster]					
32375	5	08-28-73	6	400	K43, Au199, Au197
[waste from lab #207 in hot can]					
32451	5	09-12-73	50	1000	Co, Sr
[2 S. S. trays]					
32459	5	09-14-73	36	2000	Co60
[junk from cell C]					

APPENDIX I

Document	Trench	Date	Volume	Radiation	Isotopes
32506	5	09-28-73	5	10	Eu, Sr, Co
[waste in Pierce carrier]					
32481	5	09-20-73	30	5000	mixed f.p.
[junk from cell C, stainless steel ductwork and 2 GI cans]					
32498	5	09-27-73	6	500	Co60, Sr90
[misc solid waste + debris from floor of cell A in garbage can]					
32500	5	09-27-73	50	800	Co60, Sr90
[SSt duct - contaminated in plywood box]					
32480	5	09-20-73	60	<2	none
[HEPA filters, blotter paper, plastic bags in cardboard + plastic]					
32442	5	09-10-73	77	<1	none
[HEPA filters, blotter paper, plastic, cardboard in cardboard and plastic]					
32443	5	09-10-73	42	20	?
[waste material from ORIC (radiation waste) in 7 yellow cans]					
32460	5	09-14-73	375	500	mixed f.p.
[misc contaminated scrap in plastic]					
32470	5	09-19-73	200	180	Transuranic
[transuranium contaminated filters + equipment in double bagged wooden box]					
32548	5	10-03-73	18	2000	mixed
[misc waste from cell in 3 GI cans]					
32557	5	10-05-73	450	10	Cs137, Co60, other
[excavated dirt, shrubs, and grass in plastic lined truck]					
32558	5	10-05-73	925	10	Cs137, Co60, other
[excavated dirt, shrubs, and grass in plastic lined truck]					
32527	5	10-01-73	20	20	alpha
[contaminated HEPA filters in metal container]					
?????	5	09-13-73	200	6000	Cm244
[VOG filter in concrete container]					
?????	5	09-20-73	60	0.1	none
[HEPA filters, blotter paper, plastic bags in cardboard and plastic]					

APPENDIX II

Drill Logs and Construction Information for TARA Wells 1 - 13

WELL TARA-1

WELL TARA-2

WELL TARA-3

WELL TARA-4

WELL TARA-5

WELL TARA-6

WELL TARA-7

WELL TARA-8

WELL TARA-9

WELL TARA-10

WELL TARA-11

WELL TARA-12

WELL TARA-13

APPENDIX III

TARA Well Water Level Data, Well Hydrographs, and Rainfall

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
1	05/22/87	01:34 PM	242.48
1	06/15/87	01:30 PM	241.28
1	07/13/87	12:00 PM	240.87
1	07/27/87	10:55 AM	240.62
1	07/27/87	01:31 PM	240.62
1	07/27/87	04:00 PM	240.63
1	07/27/87	08:40 PM	240.62
1	07/28/87	06:39 AM	240.61
1	07/28/87	10:21 AM	240.62
1	07/28/87	01:15 PM	240.62
1	07/28/87	03:00 PM	240.63
1	07/29/87	09:14 AM	240.62
1	07/29/87	02:53 PM	240.61
1	07/30/87	09:08 AM	240.60
1	07/30/87	04:24 PM	240.59
1	07/31/87	08:48 AM	240.57
1	08/03/87	08:57 AM	240.56
1	08/04/87	08:51 AM	240.55
1	08/05/87	07:33 AM	240.55
1	08/05/87	03:04 PM	240.56
1	08/06/87	08:56 AM	240.54
1	08/07/87	09:13 AM	240.55
1	08/10/87	09:17 AM	240.52
1	08/12/87	09:58 AM	240.50
1	08/14/87	07:57 AM	240.48
1	08/17/87	07:31 AM	240.45
1	08/21/87	03:23 PM	240.40
1	09/04/87	08:27 AM	240.17
1	09/11/87	01:30 PM	240.07
1	09/18/87	01:30 PM	240.07
1	09/25/87	01:30 PM	240.01
1	10/01/87	01:30 PM	239.96
1	10/08/87	01:30 PM	239.89
1	10/15/87	01:30 PM	239.82
1	10/19/87	02:07 PM	239.79
1	10/20/87	09:01 AM	239.79
1	10/20/87	03:56 PM	239.78
1	10/21/87	09:04 AM	239.76
1	10/22/87	09:29 AM	239.76
1	10/23/87	09:14 AM	239.78
1	10/26/87	09:09 AM	239.91
1	10/27/87	08:56 AM	239.96
1	10/28/87	08:59 AM	239.99
1	10/29/87	09:21 AM	240.06
1	10/30/87	09:40 AM	240.41

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
1	11/02/87	02:45 PM	241.31
1	11/04/87	09:36 AM	241.36
1	11/05/87	01:30 PM	241.34
1	11/10/87	01:30 PM	241.16
1	11/12/87	01:00 PM	241.03
1	11/17/87	08:15 AM	240.89
1	11/17/87	11:08 AM	240.89
1	12/03/87	01:30 PM	240.41
1	12/11/87	01:30 PM	240.24
1	12/16/87	01:30 PM	240.20
1	12/21/87	02:30 PM	240.07
1	12/28/87	10:15 AM	240.28
1	12/31/87	01:00 PM	240.10
1	01/04/88	02:00 PM	240.10
1	01/08/88	10:40 AM	240.05
1	01/14/88	08:50 AM	240.00
1	01/21/88	10:00 AM	240.44
1	01/22/88	01:00 PM	240.31
1	01/25/88	10:00 AM	240.28
1	01/28/88	10:00 AM	240.25
1	02/01/88	10:15 AM	240.28
1	02/11/88	10:30 AM	240.60
1	02/18/88	01:50 PM	240.71
1	02/26/88	12:15 PM	240.68
1	03/03/88	10:00 AM	240.67
1	03/09/88	08:30 AM	240.63
1	03/16/88	10:00 AM	241.70
1	03/16/88	12:00 PM	241.64
1	03/17/88	12:00 PM	241.59
1	03/18/88	12:00 PM	241.58
1	03/19/88	12:00 PM	241.53
1	03/20/88	12:00 PM	241.48
1	03/21/88	12:00 PM	241.43
1	03/22/88	12:00 PM	241.37
1	03/23/88	12:00 PM	241.32
1	03/24/88	12:00 PM	241.29
1	03/25/88	12:00 PM	241.26
1	03/26/88	12:00 PM	241.25
1	03/27/88	12:00 PM	241.18
1	03/28/88	10:00 AM	241.18
1	03/28/88	12:00 PM	241.13
1	03/29/88	12:00 PM	241.11
1	03/30/88	12:00 PM	241.08
1	03/31/88	12:00 PM	241.04
1	04/01/88	12:00 PM	241.03
1	04/02/88	12:00 PM	241.01

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
1	04/03/88	12:00 PM	241.00
1	04/04/88	10:00 AM	241.24
1	04/04/88	12:00 PM	241.20
1	04/05/88	12:00 PM	241.01
1	04/06/88	12:00 PM	241.26
1	04/07/88	12:00 PM	241.28
1	04/08/88	12:00 PM	241.12
1	04/09/88	12:00 PM	241.12
1	04/10/88	12:00 PM	241.12
1	04/11/88	12:00 PM	241.15
1	04/12/88	12:00 PM	241.13
1	04/13/88	12:00 PM	241.09
1	04/14/88	12:00 PM	241.06
1	04/15/88	12:00 PM	241.04
1	04/16/88	12:00 PM	241.01
1	04/17/88	12:00 PM	241.00
1	04/18/88	12:00 PM	241.22
1	04/19/88	12:00 PM	241.67
1	04/20/88	12:00 PM	241.33
1	04/21/88	12:00 PM	241.29
1	04/22/88	12:00 PM	241.30
1	04/23/88	12:00 PM	241.28
1	04/24/88	12:00 PM	241.25
1	04/25/88	12:00 PM	241.20
1	04/26/88	12:00 PM	241.18
1	04/27/88	12:00 PM	241.14
1	04/28/88	12:00 PM	241.08
1	04/29/88	12:00 PM	241.05
1	04/30/88	12:00 PM	241.03
1	05/01/88	12:00 PM	241.00
1	05/02/88	12:00 PM	240.98
1	05/03/88	10:00 AM	241.00
1	05/03/88	12:00 PM	240.95
1	05/04/88	12:00 PM	240.95
1	05/05/88	12:00 PM	240.93
1	05/06/88	12:00 PM	240.91
1	05/07/88	12:00 PM	240.87
1	05/08/88	12:00 PM	240.85
1	05/09/88	12:00 PM	240.84
1	05/10/88	12:00 PM	240.82
1	05/11/88	12:00 PM	240.82
1	05/12/88	10:00 AM	240.82
1	05/12/88	12:00 PM	240.77
1	05/13/88	12:00 PM	240.75
1	05/14/88	12:00 PM	240.74
1	05/15/88	12:00 PM	240.72

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
1	05/16/88	12:00 PM	240.71
1	05/17/88	12:00 PM	240.70
1	05/18/88	12:00 PM	240.69
1	05/19/88	12:00 PM	240.67
1	05/20/88	12:00 PM	240.64
1	05/20/88	01:30 PM	240.69
1	05/21/88	12:00 PM	240.62
1	05/22/88	12:00 PM	240.60
1	05/23/88	12:00 PM	240.59
1	05/24/88	12:00 PM	240.58
1	05/25/88	12:00 PM	240.57
1	05/26/88	12:00 PM	240.56
1	05/26/88	02:15 PM	240.61
1	05/27/88	12:00 PM	240.54
1	05/28/88	12:00 PM	240.52
1	05/29/88	12:00 PM	240.51
1	05/30/88	12:00 PM	240.49
1	05/31/88	12:00 PM	240.48
1	06/01/88	12:00 PM	240.47
1	06/02/88	09:30 AM	240.50
1	06/02/88	12:00 PM	240.46
1	06/03/88	12:00 PM	240.45
1	06/04/88	12:00 PM	240.41
1	06/05/88	12:00 PM	240.39
1	06/06/88	12:00 PM	240.37
1	06/07/88	12:00 PM	240.37
1	06/08/88	12:00 PM	240.36
1	06/09/88	10:30 AM	240.38
1	06/09/88	12:00 PM	240.35
1	06/10/88	12:00 PM	240.30
1	06/11/88	12:00 PM	240.29
1	06/12/88	12:00 PM	240.27
1	06/13/88	12:00 PM	240.26
1	06/14/88	12:00 PM	240.24
1	06/15/88	12:00 PM	240.22
1	06/16/88	12:00 PM	240.22
1	06/17/88	12:00 PM	240.21
1	06/18/88	12:00 PM	240.19
1	06/19/88	12:00 PM	240.16
1	06/20/88	12:00 PM	240.15
1	06/21/88	12:00 PM	240.14
1	06/21/88	12:00 PM	240.17
1	06/22/88	12:00 PM	240.13
1	06/23/88	12:00 PM	240.12
1	06/24/88	12:00 PM	240.10
1	06/25/88	12:00 PM	240.08

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
1	06/26/88	12:00 PM	240.10
1	06/27/88	12:00 PM	240.10
1	06/28/88	12:00 PM	240.09
1	06/29/88	12:00 PM	240.09
1	06/30/88	12:00 PM	240.08
1	07/01/88	12:00 PM	240.09
1	07/01/88	12:00 PM	240.06
1	07/02/88	12:00 PM	240.05
1	07/03/88	12:00 PM	240.03
1	07/04/88	12:00 PM	240.02
1	07/05/88	12:00 PM	240.00
1	07/06/88	12:00 PM	239.99
1	07/07/88	12:00 PM	239.98
1	07/08/88	12:00 PM	239.97
1	07/09/88	12:00 PM	239.96
1	07/10/88	12:00 PM	239.94
1	07/11/88	12:00 PM	239.92
1	07/12/88	12:00 PM	239.93
1	07/13/88	12:00 PM	239.95
1	07/14/88	12:00 PM	240.15
1	07/15/88	12:00 PM	240.05
1	07/16/88	12:00 PM	240.01
1	07/17/88	12:00 PM	240.00
1	07/18/88	12:00 PM	239.98
1	07/19/88	12:00 PM	239.99
1	07/20/88	12:00 PM	239.98
1	07/21/88	12:00 PM	239.96
1	07/22/88	12:00 PM	239.98
1	07/23/88	12:00 PM	240.00
1	07/24/88	12:00 PM	239.98
1	07/25/88	12:00 PM	239.97
1	07/26/88	12:00 PM	239.97
1	07/26/88	12:00 PM	240
1	07/27/88	12:00 PM	239.99
1	07/28/88	12:00 PM	240.01
1	07/29/88	12:00 PM	240.01
1	07/30/88	12:00 PM	240.01
1	07/31/88	12:00 PM	240.01
1	08/01/88	12:00 PM	240.00
1	08/02/88	12:00 PM	239.99
1	08/03/88	12:00 PM	239.98
1	08/04/88	12:00 PM	239.98
1	08/05/88	12:00 PM	239.96
1	08/06/88	12:00 PM	239.95
1	08/07/88	12:00 PM	239.95
1	08/08/88	12:00 PM	239.94

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
1	08/09/88	12:00 PM	239.93
1	08/10/88	12:00 PM	239.91
1	08/11/88	12:00 PM	239.91
1	08/12/88	12:00 PM	239.91
1	08/13/88	12:00 PM	239.91
1	08/14/88	12:00 PM	239.91
1	08/15/88	12:00 PM	239.91
1	08/16/88	12:00 PM	239.90
1	08/17/88	12:00 PM	239.89
1	08/18/88	12:00 PM	239.88
1	08/19/88	12:00 PM	239.88
1	08/20/88	12:00 PM	239.87
1	08/21/88	12:00 PM	239.86
1	08/22/88	12:00 PM	239.85
1	08/23/88	12:00 PM	239.87

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
2	06/15/87	01:30 PM	240.57
2	07/13/87	12:00 PM	240.46
2	07/27/87	10:54 AM	240.17
2	07/27/87	01:30 PM	240.17
2	07/27/87	03:58 PM	240.18
2	07/27/87	08:41 PM	240.16
2	07/28/87	06:37 AM	240.16
2	07/28/87	10:20 AM	240.16
2	07/28/87	01:14 PM	240.16
2	07/28/87	02:59 PM	240.17
2	07/29/87	09:13 AM	240.15
2	07/29/87	02:51 PM	240.15
2	07/30/87	09:07 AM	240.13
2	07/30/87	04:23 PM	240.13
2	07/31/87	08:46 AM	240.11
2	08/03/87	08:56 AM	240.07
2	08/04/87	08:50 AM	240.04
2	08/05/87	07:31 AM	240.03
2	08/05/87	03:02 PM	240.04
2	08/06/87	08:55 AM	240.02
2	08/07/87	09:12 AM	240.01
2	08/10/87	09:16 AM	239.99
2	08/12/87	09:57 AM	239.97
2	08/14/87	07:55 AM	239.96
2	08/17/87	07:30 AM	239.97
2	08/21/87	03:22 PM	239.94
2	09/04/87	08:25 AM	239.77
2	09/11/87	01:30 PM	239.70
2	09/18/87	01:30 PM	239.84
2	09/25/87	01:30 PM	239.80
2	10/01/87	01:30 PM	239.77
2	10/08/87	01:30 PM	239.74
2	10/15/87	01:30 PM	239.68
2	10/19/87	02:06 PM	239.66
2	10/20/87	08:59 AM	239.65
2	10/20/87	03:55 PM	239.66
2	10/21/87	09:00 AM	239.64
2	10/22/87	09:25 AM	239.64
2	10/23/87	09:03 AM	239.64
2	10/26/87	09:13 AM	239.66
2	10/27/87	09:11 AM	239.67
2	10/28/87	09:14 AM	239.67
2	10/29/87	09:19 AM	239.65
2	10/30/87	09:35 AM	239.66
2	11/02/87	02:40 PM	239.69
2	11/04/87	09:33 AM	239.73

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
2	11/05/87	01:30 PM	239.75
2	11/10/87	01:30 PM	239.80
2	11/12/87	01:00 PM	239.84
2	11/17/87	08:15 AM	239.89
2	11/18/87	09:05 AM	239.88
2	12/03/87	01:30 PM	239.86
2	12/11/87	01:30 PM	239.83
2	12/16/87	01:30 PM	239.76
2	12/21/87	02:30 PM	239.83
2	12/28/87	10:13 AM	239.94
2	12/31/87	01:00 PM	239.91
2	01/04/88	02:00 PM	239.97
2	01/08/88	10:40 AM	239.97
2	01/14/88	08:50 AM	239.94
2	01/21/88	10:00 AM	240.37
2	01/22/88	01:00 PM	240.26
2	01/25/88	10:00 AM	240.22
2	01/28/88	10:00 AM	240.14
2	02/01/88	10:15 AM	240.15
2	02/11/88	10:30 AM	240.40
2	02/18/88	01:50 PM	240.43
2	02/26/88	12:15 PM	240.40
2	03/03/88	10:00 AM	240.38
2	03/04/88	12:00 PM	240.38
2	03/05/88	12:00 PM	240.34
2	03/06/88	12:00 PM	240.34
2	03/07/88	12:00 PM	240.33
2	03/08/88	12:00 PM	240.33
2	03/09/88	08:30 AM	240.35
2	03/09/88	12:00 PM	240.35
2	03/10/88	12:00 PM	240.48
2	03/11/88	12:00 PM	241.35
2	03/12/88	12:00 PM	241.06
2	03/13/88	12:00 PM	241.38
2	03/14/88	12:00 PM	241.55
2	03/15/88	12:00 PM	241.20
2	03/16/88	10:00 AM	241.09
2	03/16/88	12:00 PM	241.12
2	03/17/88	12:00 PM	240.96
2	03/18/88	12:00 PM	240.94
2	03/19/88	12:00 PM	240.89
2	03/20/88	12:00 PM	240.84
2	03/21/88	12:00 PM	240.80
2	03/22/88	12:00 PM	240.74
2	03/23/88	12:00 PM	240.71
2	03/24/88	12:00 PM	240.69

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
2	03/25/88	12:00 PM	240.68
2	03/26/88	12:00 PM	240.67
2	03/27/88	12:00 PM	240.62
2	03/28/88	10:00 AM	240.60
2	03/28/88	12:00 PM	240.59
2	03/29/88	12:00 PM	240.59
2	03/30/88	12:00 PM	240.57
2	03/31/88	12:00 PM	240.55
2	04/01/88	12:00 PM	240.54
2	04/02/88	12:00 PM	240.53
2	04/03/88	12:00 PM	240.54
2	04/04/88	10:00 AM	240.53
2	04/04/88	12:00 PM	240.54
2	04/05/88	12:00 PM	240.53
2	04/06/88	12:00 PM	240.57
2	04/07/88	12:00 PM	240.62
2	04/08/88	12:00 PM	240.65
2	04/09/88	12:00 PM	240.66
2	04/10/88	12:00 PM	240.68
2	04/11/88	12:00 PM	240.70
2	04/12/88	12:00 PM	240.69
2	04/13/88	12:00 PM	240.66
2	04/14/88	12:00 PM	240.65
2	04/15/88	12:00 PM	240.62
2	04/16/88	12:00 PM	240.60
2	04/17/88	12:00 PM	240.60
2	04/18/88	12:00 PM	240.64
2	04/19/88	12:00 PM	240.68
2	04/20/88	12:00 PM	240.82
2	04/21/88	12:00 PM	240.85
2	04/22/88	12:00 PM	240.86
2	04/23/88	12:00 PM	240.84
2	04/24/88	12:00 PM	240.81
2	04/25/88	12:00 PM	240.78
2	04/26/88	12:00 PM	240.77
2	04/27/88	12:00 PM	240.73
2	04/28/88	12:00 PM	240.69
2	04/29/88	12:00 PM	240.67
2	04/30/88	12:00 PM	240.65
2	05/01/88	12:00 PM	240.62
2	05/02/88	12:00 PM	240.61
2	05/03/88	10:00 AM	240.60
2	05/03/88	12:00 PM	240.59
2	05/04/88	12:00 PM	240.59
2	05/05/88	12:00 PM	240.57
2	05/06/88	12:00 PM	240.56

APPENDIX III

PARA Well	Date	Time	Water Elevation (m)
2	05/07/88	12:00 PM	240.54
2	05/08/88	12:00 PM	240.52
2	05/09/88	12:00 PM	240.51
2	05/10/88	12:00 PM	240.52
2	05/11/88	12:00 PM	240.50
2	05/12/88	10:00 AM	240.48
2	05/12/88	12:00 PM	240.47
2	05/13/88	12:00 PM	240.46
2	05/14/88	12:00 PM	240.45
2	05/15/88	12:00 PM	240.44
2	05/16/88	12:00 PM	240.44
2	05/17/88	12:00 PM	240.43
2	05/18/88	12:00 PM	240.41
2	05/19/88	12:00 PM	240.40
2	05/20/88	12:00 PM	240.37
2	05/20/88	01:30 PM	240.38
2	05/21/88	12:00 PM	240.35
2	05/22/88	12:00 PM	240.34
2	05/23/88	12:00 PM	240.34
2	05/24/88	12:00 PM	240.32
2	05/25/88	12:00 PM	240.32
2	05/26/88	12:00 PM	240.30
2	05/26/88	02:15 PM	240.30
2	05/27/88	12:00 PM	240.30
2	05/28/88	12:00 PM	240.30
2	05/29/88	12:00 PM	240.29
2	05/30/88	12:00 PM	240.28
2	05/31/88	12:00 PM	240.26
2	06/01/88	12:00 PM	240.25
2	06/02/88	09:30 AM	240.24
2	06/02/88	12:00 PM	240.25
2	06/03/88	12:00 PM	240.24
2	06/04/88	12:00 PM	240.20
2	06/05/88	12:00 PM	240.17
2	06/06/88	12:00 PM	240.15
2	06/07/88	12:00 PM	240.15
2	06/08/88	12:00 PM	240.14
2	06/09/88	10:30 AM	240.12
2	06/09/88	12:00 PM	240.12
2	06/10/88	12:00 PM	240.09
2	06/11/88	12:00 PM	240.08
2	06/12/88	12:00 PM	240.07
2	06/13/88	12:00 PM	240.06
2	06/14/88	12:00 PM	240.05
2	06/15/88	12:00 PM	240.03
2	06/16/88	12:00 PM	240.03

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
2	06/17/88	12:00 PM	240.02
2	06/18/88	12:00 PM	240.00
2	06/19/88	12:00 PM	239.97
2	06/20/88	12:00 PM	239.96
2	06/21/88	12:00 PM	239.95
2	06/21/88	12:00 PM	239.93
2	06/23/88	12:00 PM	239.93
2	06/24/88	12:00 PM	239.91
2	06/25/88	12:00 PM	239.88
2	06/26/88	12:00 PM	240.27
2	06/27/88	12:00 PM	240.29
2	06/28/88	12:00 PM	240.28
2	06/29/88	12:00 PM	240.29
2	06/30/88	12:00 PM	240.28
2	07/01/88	12:00 PM	239.89
2	07/01/88	12:00 PM	240.27
2	07/03/88	12:00 PM	240.24
2	07/04/88	12:00 PM	240.23
2	07/05/88	12:00 PM	240.21
2	07/06/88	12:00 PM	240.20
2	07/07/88	12:00 PM	240.20
2	07/09/88	12:00 PM	239.79
2	07/10/88	12:00 PM	239.77
2	07/11/88	12:00 PM	239.76
2	07/12/88	12:00 PM	239.76
2	07/13/88	12:00 PM	239.80
2	07/14/88	12:00 PM	239.88
2	07/15/88	12:00 PM	239.91
2	07/16/88	12:00 PM	239.92
2	07/17/88	12:00 PM	239.92
2	07/18/88	12:00 PM	239.91
2	07/19/88	12:00 PM	239.91
2	07/20/88	12:00 PM	239.89
2	07/21/88	12:00 PM	239.88
2	07/22/88	12:00 PM	239.92
2	07/23/88	12:00 PM	239.94
2	07/24/88	12:00 PM	239.93
2	07/25/88	12:00 PM	239.93
2	07/26/88	12:00 PM	239.93
2	07/26/88	12:00 PM	239.94
2	07/27/88	12:00 PM	239.95
2	07/28/88	12:00 PM	239.97
2	07/29/88	12:00 PM	239.97
2	07/30/88	12:00 PM	239.97
2	07/31/88	12:00 PM	239.97
2	08/01/88	12:00 PM	239.95

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
2	08/02/88	12:00 PM	239.93
2	08/23/88	12:00 PM	239.73

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
3	06/03/87	09:11 AM	243.29
3	06/15/87	01:30 PM	243.16
3	07/13/87	12:00 PM	242.84
3	07/27/87	10:53 AM	242.66
3	07/27/87	01:29 PM	242.65
3	07/27/87	03:57 PM	242.66
3	07/27/87	08:43 PM	242.66
3	07/28/87	06:35 AM	242.65
3	07/28/87	10:18 AM	242.65
3	07/28/87	01:13 PM	242.78
3	07/28/87	02:58 PM	242.96
3	07/29/87	09:11 AM	245.13
3	07/29/87	02:49 PM	245.59
3	07/30/87	09:07 AM	245.96
3	07/30/87	04:21 PM	245.99
3	07/31/87	08:45 AM	246.09
3	08/03/87	08:55 AM	245.57
3	08/04/87	08:49 AM	245.18
3	08/05/87	07:30 AM	244.95
3	08/05/87	03:01 PM	244.88
3	08/06/87	08:54 AM	244.71
3	08/07/87	09:11 AM	244.51
3	08/10/87	09:15 AM	244.07
3	08/12/87	09:55 AM	243.90
3	08/14/87	07:54 AM	243.74
3	08/17/87	07:28 AM	243.54
3	08/21/87	03:21 PM	243.32
3	09/04/87	08:24 AM	242.80
3	09/11/87	01:30 PM	242.63
3	09/18/87	01:30 PM	242.50
3	09/25/87	01:30 PM	242.37
3	10/01/87	01:30 PM	242.30
3	10/08/87	01:30 PM	242.21
3	10/15/87	01:30 PM	242.14
3	10/19/87	02:04 PM	242.12
3	10/20/87	08:54 AM	242.11
3	10/20/87	03:54 PM	242.10
3	10/21/87	09:14 AM	242.12
3	10/22/87	09:19 AM	243.71
3	10/23/87	09:04 AM	244.78
3	10/26/87	09:14 AM	245.65
3	10/27/87	09:02 AM	245.62
3	10/28/87	09:05 AM	245.78
3	10/29/87	09:10 AM	246.13
3	10/30/87	09:28 AM	246.53
3	11/02/87	02:23 PM	246.23

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
3	11/04/87	09:23 AM	245.89
3	11/05/87	01:30 PM	245.67
3	11/10/87	01:30 PM	244.45
3	11/12/87	01:00 PM	244.55
3	11/17/87	08:15 AM	244.16
3	11/18/87	09:53 AM	243.94
3	12/03/87	01:30 PM	243.37
3	12/11/87	01:30 PM	243.12
3	12/16/87	01:30 PM	242.91
3	12/21/87	02:30 PM	242.77
3	12/28/87	10:15 AM	242.61
3	12/31/87	01:00 PM	242.56
3	01/04/88	02:00 PM	242.63
3	01/08/88	10:40 AM	242.74
3	01/14/88	08:50 AM	243.09
3	01/21/88	10:00 AM	243.86
3	01/22/88	01:00 PM	243.87
3	01/25/88	10:00 AM	244.41
3	01/28/88	10:00 AM	244.33
3	02/01/88	10:15 AM	244.18
3	02/11/88	10:30 AM	244.04
3	02/18/88	01:50 PM	243.90
3	02/26/88	12:15 PM	243.67
3	03/03/88	10:00 AM	243.62
3	03/04/88	12:00 PM	243.65
3	03/05/88	12:00 PM	243.59
3	03/06/88	12:00 PM	243.59
3	03/07/88	12:00 PM	243.56
3	03/08/88	12:00 PM	243.55
3	03/09/88	08:30 AM	243.55
3	03/09/88	12:00 PM	243.58
3	03/10/88	12:00 PM	245.25
3	03/11/88	12:00 PM	243.90
3	03/12/88	12:00 PM	243.67
3	03/13/88	12:00 PM	243.83
3	03/14/88	12:00 PM	243.70
3	03/15/88	12:00 PM	243.72
3	03/16/88	10:00 AM	243.75
3	03/16/88	12:00 PM	243.74
3	03/17/88	12:00 PM	243.85
3	03/18/88	12:00 PM	243.96
3	03/19/88	12:00 PM	244.02
3	03/20/88	12:00 PM	244.05
3	03/21/88	12:00 PM	244.07
3	03/22/88	12:00 PM	244.04
3	03/23/88	12:00 PM	244.03

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
3	03/24/88	12:00 PM	243.99
3	03/25/88	12:00 PM	244.04
3	03/26/88	12:00 PM	244.01
3	03/27/88	12:00 PM	243.97
3	03/28/88	10:00 AM	243.92
3	03/28/88	12:00 PM	243.93
3	03/29/88	12:00 PM	243.91
3	03/30/88	12:00 PM	243.87
3	03/31/88	12:00 PM	243.83
3	04/01/88	12:00 PM	243.81
3	04/02/88	12:00 PM	243.77
3	04/03/88	12:00 PM	243.75
3	04/04/88	10:00 AM	243.71
3	04/04/88	12:00 PM	243.74
3	04/05/88	12:00 PM	243.68
3	04/06/88	12:00 PM	243.70
3	04/07/88	12:00 PM	243.66
3	04/08/88	12:00 PM	243.61
3	04/09/88	12:00 PM	243.57
3	04/10/88	12:00 PM	243.55
3	04/11/88	12:00 PM	243.56
3	04/12/88	12:00 PM	243.54
3	04/13/88	12:00 PM	243.50
3	04/14/88	12:00 PM	243.47
3	04/15/88	12:00 PM	243.45
3	04/16/88	12:00 PM	243.43
3	04/17/88	12:00 PM	243.42
3	04/18/88	12:00 PM	243.46
3	04/19/88	12:00 PM	243.44
3	04/20/88	12:00 PM	243.41
3	04/21/88	12:00 PM	243.42
3	04/22/88	12:00 PM	243.42
3	04/23/88	12:00 PM	243.41
3	04/24/88	12:00 PM	243.40
3	04/25/88	12:00 PM	243.40
3	04/26/88	12:00 PM	243.42
3	04/27/88	12:00 PM	243.42
3	04/28/88	12:00 PM	243.40
3	04/29/88	12:00 PM	243.42
3	04/30/88	12:00 PM	243.43
3	05/01/88	12:00 PM	243.43
3	05/02/88	12:00 PM	243.45
3	05/03/88	10:00 AM	243.45
3	05/03/88	12:00 PM	243.46
3	05/04/88	12:00 PM	243.49
3	05/05/88	12:00 PM	243.46

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
3	05/06/88	12:00 PM	243.46
3	05/07/88	12:00 PM	243.44
3	05/08/88	12:00 PM	243.43
3	05/09/88	12:00 PM	243.43
3	05/10/88	12:00 PM	243.42
3	05/11/88	12:00 PM	243.43
3	05/12/88	10:00 AM	243.37
3	05/12/88	12:00 PM	243.38
3	05/13/88	12:00 PM	243.37
3	05/14/88	12:00 PM	243.36
3	05/15/88	12:00 PM	243.36
3	05/16/88	12:00 PM	243.36
3	05/17/88	12:00 PM	243.35
3	05/18/88	12:00 PM	243.33
3	05/19/88	12:00 PM	243.32
3	05/20/88	12:00 PM	243.29
3	05/20/88	01:30 PM	243.28
3	05/21/88	12:00 PM	243.26
3	05/22/88	12:00 PM	243.25
3	05/23/88	12:00 PM	243.24
3	05/24/88	12:00 PM	243.22
3	05/25/88	12:00 PM	243.20
3	05/26/88	12:00 PM	243.15
3	05/26/88	02:15 PM	243.14
3	05/27/88	12:00 PM	243.13
3	05/28/88	12:00 PM	243.12
3	05/29/88	12:00 PM	243.10
3	05/30/88	12:00 PM	243.08
3	05/31/88	12:00 PM	243.06
3	06/01/88	12:00 PM	243.05
3	06/02/88	09:30 AM	243.04
3	06/02/88	12:00 PM	243.05
3	06/03/88	12:00 PM	243.04
3	06/04/88	12:00 PM	243.00
3	06/05/88	12:00 PM	242.96
3	06/06/88	12:00 PM	242.94
3	06/07/88	12:00 PM	242.94
3	06/08/88	12:00 PM	242.95
3	06/09/88	10:30 AM	242.91
3	06/09/88	12:00 PM	242.93
3	06/10/88	12:00 PM	242.86
3	06/11/88	12:00 PM	242.81
3	06/12/88	12:00 PM	242.80
3	06/13/88	12:00 PM	242.78
3	06/14/88	12:00 PM	242.76
3	06/15/88	12:00 PM	242.75

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
3	06/16/88	12:00 PM	242.75
3	06/17/88	12:00 PM	242.75
3	06/18/88	12:00 PM	242.72
3	06/19/88	12:00 PM	242.69
3	06/20/88	12:00 PM	242.66
3	06/21/88	12:00 PM	242.66
3	06/21/88	12:00 PM	242.64
3	06/23/88	12:00 PM	242.63
3	06/24/88	12:00 PM	242.61
3	06/25/88	12:00 PM	242.54
3	06/26/88	12:00 PM	242.56
3	06/27/88	12:00 PM	242.55
3	06/28/88	12:00 PM	242.53
3	06/29/88	12:00 PM	242.52
3	06/30/88	12:00 PM	242.51
3	07/01/88	12:00 PM	242.49
3	07/01/88	12:00 PM	242.50
3	07/03/88	12:00 PM	242.46
3	07/04/88	12:00 PM	242.43
3	07/05/88	12:00 PM	242.41
3	07/06/88	12:00 PM	242.39
3	07/07/88	12:00 PM	242.38
3	07/09/88	12:00 PM	242.37
3	07/10/88	12:00 PM	242.36
3	07/11/88	12:00 PM	242.34
3	07/12/88	12:00 PM	242.50
3	07/13/88	12:00 PM	242.38
3	07/14/88	12:00 PM	242.68
3	07/15/88	12:00 PM	242.48
3	07/16/88	12:00 PM	242.40
3	07/17/88	12:00 PM	242.39
3	07/18/88	12:00 PM	242.41
3	07/19/88	12:00 PM	242.46
3	07/20/88	12:00 PM	242.49
3	07/21/88	12:00 PM	242.53
3	07/22/88	12:00 PM	242.56
3	07/23/88	12:00 PM	242.60
3	07/24/88	12:00 PM	242.60
3	07/25/88	12:00 PM	242.63
3	07/26/88	12:00 PM	242.66
3	07/26/88	12:00 PM	242.65
3	07/27/88	12:00 PM	242.81
3	07/28/88	12:00 PM	242.74
3	07/29/88	12:00 PM	242.71
3	07/30/88	12:00 PM	242.72
3	07/31/88	12:00 PM	242.74

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
3	08/01/88	12:00 PM	242.76
3	08/02/88	12:00 PM	242.77
3	08/23/88	12:00 PM	242.83

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
4	06/03/87	01:50 PM	242.25
4	06/15/87	01:30 PM	241.50
4	07/13/87	12:00 PM	241.40
4	08/04/87	08:43 AM	243.34
4	08/04/87	01:29 PM	243.81
4	08/05/87	07:10 AM	244.83
4	08/05/87	02:49 PM	245.04
4	08/06/87	08:44 AM	245.39
4	08/06/87	01:10 PM	245.53
4	08/06/87	03:20 PM	245.60
4	08/07/87	09:00 AM	247.14
4	08/07/87	02:18 PM	245.70
4	08/10/87	09:08 AM	245.14
4	08/11/87	03:27 PM	244.83
4	08/12/87	09:46 AM	244.64
4	08/13/87	08:55 AM	244.43
4	08/14/87	07:44 AM	244.25
4	08/17/87	07:17 AM	243.80
4	08/21/87	03:16 PM	243.28
4	09/04/87	08:17 AM	242.06
4	09/11/87	01:30 PM	241.69
4	09/18/87	01:30 PM	241.57
4	09/25/87	01:30 PM	241.41
4	10/01/87	01:30 PM	241.34
4	10/08/87	01:30 PM	241.23
4	10/15/87	01:30 PM	241.14
4	11/04/87	09:17 AM	241.82
4	11/05/87	01:30 PM	241.75
4	11/10/87	01:30 PM	241.47
4	11/12/87	01:00 PM	241.40
4	11/17/87	08:15 AM	241.24
4	11/18/87	10:30 AM	241.23
4	12/03/87	01:30 PM	240.96
4	12/11/87	01:30 PM	240.90
4	12/16/87	01:30 PM	240.92
4	12/21/87	02:30 PM	240.92
4	12/28/87	10:15 AM	241.07
4	12/31/87	01:00 PM	241.07
4	01/04/88	02:00 PM	241.11
4	01/08/88	10:40 AM	241.08
4	01/14/88	08:50 AM	241.00
4	01/21/88	10:00 AM	241.54
4	01/22/88	01:00 PM	241.81
4	01/25/88	10:00 AM	242.15
4	01/28/88	10:00 AM	242.16
4	02/01/88	10:15 AM	242.18

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
4	02/11/88	10:30 AM	242.52
4	02/18/88	01:50 PM	242.38
4	02/26/88	12:15 PM	242.18
4	03/03/88	10:00 AM	242.03
4	03/04/88	12:00 PM	242.01
4	03/05/88	12:00 PM	241.97
4	03/06/88	12:00 PM	241.96
4	03/07/88	12:00 PM	241.92
4	03/08/88	12:00 PM	241.90
4	03/09/88	08:30 AM	241.90
4	03/09/88	12:00 PM	241.90
4	03/10/88	12:00 PM	241.96
4	03/11/88	12:00 PM	242.22
4	03/12/88	12:00 PM	242.45
4	03/13/88	12:00 PM	242.62
4	03/14/88	12:00 PM	242.77
4	03/16/88	10:00 AM	242.89
4	03/16/88	12:00 PM	242.86
4	03/17/88	12:00 PM	242.89
4	03/18/88	12:00 PM	242.94
4	03/19/88	12:00 PM	242.92
4	03/20/88	12:00 PM	242.89
4	03/21/88	12:00 PM	242.86
4	03/22/88	12:00 PM	242.82
4	03/23/88	12:00 PM	242.78
4	03/24/88	12:00 PM	242.74
4	03/25/88	12:00 PM	242.71
4	03/26/88	12:00 PM	242.68
4	03/27/88	12:00 PM	242.60
4	03/28/88	10:00 AM	242.55
4	03/28/88	12:00 PM	242.54
4	03/29/88	12:00 PM	242.50
4	03/30/88	12:00 PM	242.44
4	03/31/88	12:00 PM	242.39
4	04/01/88	12:00 PM	242.34
4	04/02/88	12:00 PM	242.31
4	04/03/88	12:00 PM	242.28
4	04/04/88	10:00 AM	242.26
4	04/04/88	12:00 PM	242.24
4	04/05/88	12:00 PM	242.21
4	04/06/88	12:00 PM	242.21
4	04/07/88	12:00 PM	242.24
4	04/08/88	12:00 PM	242.24
4	04/09/88	12:00 PM	242.25
4	04/10/88	12:00 PM	242.25
4	04/11/88	12:00 PM	242.24

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
4	04/12/88	12:00 PM	242.21
4	04/13/88	12:00 PM	242.16
4	04/14/88	12:00 PM	242.13
4	04/15/88	12:00 PM	242.07
4	04/16/88	12:00 PM	242.03
4	04/17/88	12:00 PM	242.01
4	04/18/88	12:00 PM	242.02
4	04/19/88	12:00 PM	242.05
4	04/20/88	12:00 PM	242.12
4	04/21/88	12:00 PM	242.19
4	04/22/88	12:00 PM	242.23
4	04/23/88	12:00 PM	242.22
4	04/24/88	12:00 PM	242.19
4	04/25/88	12:00 PM	242.14
4	04/26/88	12:00 PM	242.11
4	04/27/88	12:00 PM	242.05
4	04/28/88	12:00 PM	242.00
4	04/29/88	12:00 PM	241.95
4	04/30/88	12:00 PM	241.91
4	05/01/88	12:00 PM	241.87
4	05/02/88	12:00 PM	241.84
4	05/03/88	10:00 AM	241.81
4	05/03/88	12:00 PM	241.81
4	05/04/88	12:00 PM	241.80
4	05/05/88	12:00 PM	241.79
4	05/06/88	12:00 PM	241.77
4	05/07/88	12:00 PM	241.73
4	05/08/88	12:00 PM	241.71
4	05/09/88	12:00 PM	241.69
4	05/10/88	12:00 PM	241.68
4	05/11/88	12:00 PM	241.67
4	05/12/88	10:00 AM	241.64
4	05/12/88	12:00 PM	241.64
4	05/13/88	12:00 PM	241.62
4	05/14/88	12:00 PM	241.61
4	05/15/88	12:00 PM	241.59
4	05/16/88	12:00 PM	241.57
4	05/17/88	12:00 PM	241.56
4	05/18/88	12:00 PM	241.56
4	05/19/88	12:00 PM	241.53
4	05/20/88	12:00 PM	241.51
4	05/20/88	01:30 PM	241.52
4	05/21/88	12:00 PM	241.50
4	05/22/88	12:00 PM	241.48
4	05/23/88	12:00 PM	241.47
4	05/24/88	12:00 PM	241.46

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
4	05/25/88	12:00 PM	241.45
4	05/26/88	12:00 PM	241.45
4	05/26/88	02:15 PM	241.45
4	05/27/88	12:00 PM	241.44
4	05/28/88	12:00 PM	241.43
4	05/29/88	12:00 PM	241.41
4	05/30/88	12:00 PM	241.41
4	05/31/88	12:00 PM	241.39
4	06/01/88	12:00 PM	241.38
4	06/02/88	09:30 AM	241.36
4	06/02/88	12:00 PM	241.37
4	06/03/88	12:00 PM	241.35
4	06/04/88	12:00 PM	241.33
4	06/05/88	12:00 PM	241.31
4	06/06/88	12:00 PM	241.30
4	06/07/88	12:00 PM	241.29
4	06/08/88	12:00 PM	241.28
4	06/09/88	10:30 AM	241.26
4	06/09/88	12:00 PM	241.27
4	06/10/88	12:00 PM	241.25
4	06/11/88	12:00 PM	241.25
4	06/12/88	12:00 PM	241.24
4	06/13/88	12:00 PM	241.23
4	06/14/88	12:00 PM	241.21
4	06/15/88	12:00 PM	241.20
4	06/16/88	12:00 PM	241.19
4	06/17/88	12:00 PM	241.17
4	06/18/88	12:00 PM	241.16
4	06/19/88	12:00 PM	241.14
4	06/20/88	12:00 PM	241.13
4	06/21/88	12:00 PM	241.10
4	06/21/88	12:00 PM	241.11
4	06/22/88	12:00 PM	241.10
4	06/23/88	12:00 PM	241.09
4	06/24/88	12:00 PM	241.08
4	06/25/88	12:00 PM	241.08
4	06/26/88	12:00 PM	241.09
4	06/27/88	12:00 PM	241.10
4	06/28/88	12:00 PM	241.09
4	06/29/88	12:00 PM	241.09
4	06/30/88	12:00 PM	241.09
4	07/01/88	12:00 PM	241.06
4	07/01/88	12:00 PM	241.07
4	07/02/88	12:00 PM	241.07
4	07/03/88	12:00 PM	241.05
4	07/04/88	12:00 PM	241.05

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
4	07/05/88	12:00 PM	241.03
4	07/06/88	12:00 PM	241.02
4	07/07/88	12:00 PM	241.02
4	07/08/88	12:00 PM	241.01
4	07/09/88	12:00 PM	241.00
4	07/10/88	12:00 PM	241.00
4	07/11/88	12:00 PM	240.99
4	07/12/88	12:00 PM	241.03
4	07/13/88	12:00 PM	241.05
4	07/14/88	12:00 PM	241.12
4	07/15/88	12:00 PM	241.15
4	07/16/88	12:00 PM	241.14
4	07/17/88	12:00 PM	241.13
4	07/18/88	12:00 PM	241.13
4	07/19/88	12:00 PM	241.11
4	07/20/88	12:00 PM	241.10
4	07/21/88	12:00 PM	241.09
4	07/22/88	12:00 PM	241.14
4	07/23/88	12:00 PM	241.14
4	07/24/88	12:00 PM	241.13
4	07/25/88	12:00 PM	241.12
4	07/26/88	12:00 PM	241.1
4	07/26/88	12:00 PM	241.11
4	07/27/88	12:00 PM	241.15
4	07/28/88	12:00 PM	241.16
4	07/29/88	12:00 PM	241.16
4	07/30/88	12:00 PM	241.15
4	07/31/88	12:00 PM	241.13
4	08/01/88	12:00 PM	241.12
4	08/02/88	12:00 PM	241.11
4	08/03/88	12:00 PM	241.09
4	08/04/88	12:00 PM	241.08
4	08/05/88	12:00 PM	241.07
4	08/06/88	12:00 PM	241.05
4	08/07/88	12:00 PM	241.05
4	08/08/88	12:00 PM	241.04
4	08/09/88	12:00 PM	241.03
4	08/10/88	12:00 PM	241.02
4	08/11/88	12:00 PM	241.01
4	08/12/88	12:00 PM	241.01
4	08/13/88	12:00 PM	241.01
4	08/14/88	12:00 PM	241.01
4	08/15/88	12:00 PM	241.00
4	08/16/88	12:00 PM	240.99
4	08/17/88	12:00 PM	240.98
4	08/18/88	12:00 PM	240.98

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
4	08/19/88	12:00 PM	240.98
4	08/20/88	12:00 PM	240.98
4	08/21/88	12:00 PM	240.99
4	08/22/88	12:00 PM	240.98
4	08/23/88	12:00 PM	240.96

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
5	06/03/87	01:25 PM	242.55
5	06/15/87	01:30 PM	242.38
5	07/13/87	12:00 PM	242.23
5	08/04/87	08:44 AM	242.10
5	08/04/87	01:28 PM	242.11
5	08/05/87	07:12 AM	242.15
5	08/05/87	02:54 PM	242.21
5	08/06/87	08:50 AM	242.28
5	08/07/87	09:07 AM	242.69
5	08/07/87	02:30 PM	242.78
5	08/10/87	09:11 AM	243.30
5	08/11/87	03:30 PM	243.29
5	08/12/87	09:48 AM	243.23
5	08/13/87	08:59 AM	243.15
5	08/14/87	07:49 AM	243.11
5	08/17/87	07:18 AM	242.96
5	08/21/87	03:17 PM	242.74
5	09/04/87	08:15 AM	242.26
5	09/11/87	01:30 PM	242.08
5	09/18/87	01:30 PM	241.99
5	09/25/87	01:30 PM	241.88
5	10/01/87	01:30 PM	241.82
5	10/08/87	01:30 PM	241.73
5	10/15/87	01:30 PM	241.67
5	11/04/87	09:13 AM	241.88
5	11/05/87	01:30 PM	241.89
5	11/10/87	01:30 PM	241.86
5	11/12/87	01:00 PM	241.80
5	11/16/87	03:42 PM	241.76
5	11/17/87	08:15 AM	242.09
5	12/03/87	01:30 PM	241.61
5	12/11/87	01:30 PM	241.56
5	12/16/87	01:30 PM	241.47
5	12/21/87	02:30 PM	241.48
5	12/28/87	10:15 AM	241.54
5	12/31/87	01:00 PM	241.55
5	01/04/88	02:00 PM	241.63
5	01/08/88	10:40 AM	241.70
5	01/14/88	08:50 AM	241.69
5	01/21/88	10:00 AM	242.06
5	01/22/88	01:00 PM	241.97
5	01/25/88	10:00 AM	242.05
5	01/28/88	10:00 AM	242.05
5	02/01/88	10:15 AM	242.20
5	02/11/88	10:30 AM	242.59
5	02/18/88	01:50 PM	242.68

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
5	02/26/88	12:15 PM	242.68
5	03/03/88	10:00 AM	242.68
5	03/04/88	12:00 PM	242.69
5	03/05/88	12:00 PM	242.62
5	03/06/88	12:00 PM	242.63
5	03/07/88	12:00 PM	242.60
5	03/08/88	12:00 PM	242.58
5	03/09/88	08:30 AM	242.61
5	03/09/88	12:00 PM	242.62
5	03/10/88	12:00 PM	242.65
5	03/11/88	12:00 PM	242.69
5	03/12/88	12:00 PM	242.74
5	03/13/88	12:00 PM	242.81
5	03/14/88	12:00 PM	242.88
5	03/16/88	10:00 AM	242.94
5	03/16/88	12:00 PM	242.94
5	03/17/88	12:00 PM	242.97
5	03/18/88	12:00 PM	243.05
5	03/19/88	12:00 PM	243.07
5	03/20/88	12:00 PM	243.06
5	03/21/88	12:00 PM	243.05
5	03/22/88	12:00 PM	243.01
5	03/23/88	12:00 PM	243.00
5	03/24/88	12:00 PM	242.99
5	03/25/88	12:00 PM	243.01
5	03/26/88	12:00 PM	243.03
5	03/27/88	12:00 PM	242.96
5	03/28/88	10:00 AM	242.93
5	03/28/88	12:00 PM	242.92
5	03/29/88	12:00 PM	242.93
5	03/30/88	12:00 PM	242.90
5	03/31/88	12:00 PM	242.88
5	04/01/88	12:00 PM	242.87
5	04/02/88	12:00 PM	242.85
5	04/03/88	12:00 PM	242.85
5	04/04/88	10:00 AM	242.84
5	04/04/88	12:00 PM	242.83
5	04/05/88	12:00 PM	242.81
5	04/06/88	12:00 PM	242.84
5	04/07/88	12:00 PM	242.83
5	04/08/88	12:00 PM	242.80
5	04/09/88	12:00 PM	242.79
5	04/10/88	12:00 PM	242.82
5	04/11/88	12:00 PM	242.86
5	04/12/88	12:00 PM	242.85
5	04/13/88	12:00 PM	242.81

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
5	04/14/88	12:00 PM	242.79
5	04/15/88	12:00 PM	242.76
5	04/16/88	12:00 PM	242.75
5	04/17/88	12:00 PM	242.75
5	04/18/88	12:00 PM	242.80
5	04/19/88	12:00 PM	242.79
5	04/20/88	12:00 PM	242.78
5	04/21/88	12:00 PM	242.82
5	04/22/88	12:00 PM	242.86
5	04/23/88	12:00 PM	242.86
5	04/24/88	12:00 PM	242.86
5	04/25/88	12:00 PM	242.84
5	04/26/88	12:00 PM	242.86
5	04/27/88	12:00 PM	242.85
5	04/28/88	12:00 PM	242.82
5	04/29/88	12:00 PM	242.81
5	04/30/88	12:00 PM	242.79
5	05/01/88	12:00 PM	242.78
5	05/02/88	12:00 PM	242.77
5	05/03/88	10:00 AM	242.76
5	05/03/88	12:00 PM	242.76
5	05/04/88	12:00 PM	242.77
5	05/05/88	12:00 PM	242.74
5	05/06/88	12:00 PM	242.72
5	05/07/88	12:00 PM	242.69
5	05/08/88	12:00 PM	242.66
5	05/09/88	12:00 PM	242.65
5	05/10/88	12:00 PM	242.64
5	05/11/88	12:00 PM	242.61
5	05/12/88	10:00 AM	242.57
5	05/12/88	12:00 PM	242.57
5	05/13/88	12:00 PM	242.55
5	05/14/88	12:00 PM	242.54
5	05/15/88	12:00 PM	242.54
5	05/16/88	12:00 PM	242.53
5	05/17/88	12:00 PM	242.52
5	05/18/88	12:00 PM	242.50
5	05/19/88	12:00 PM	242.47
5	05/20/88	12:00 PM	242.44
5	05/20/88	01:30 PM	242.44
5	05/21/88	12:00 PM	242.41
5	05/22/88	12:00 PM	242.39
5	05/23/88	12:00 PM	242.39
5	05/24/88	12:00 PM	242.37
5	05/25/88	12:00 PM	242.35
5	05/26/88	12:00 PM	242.29

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
5	05/26/88	02:15 PM	242.29
5	05/27/88	12:00 PM	242.28
5	05/28/88	12:00 PM	242.28
5	05/29/88	12:00 PM	242.27
5	05/30/88	12:00 PM	242.26
5	05/31/88	12:00 PM	242.24
5	06/01/88	12:00 PM	242.23
5	06/02/88	09:30 AM	242.25
5	06/02/88	12:00 PM	242.25
5	06/03/88	12:00 PM	242.25
5	06/04/88	12:00 PM	242.20
5	06/05/88	12:00 PM	242.16
5	06/06/88	12:00 PM	242.15
5	06/07/88	12:00 PM	242.15
5	06/08/88	12:00 PM	242.17
5	06/09/88	10:30 AM	242.15
5	06/09/88	12:00 PM	242.16
5	06/10/88	12:00 PM	242.08
5	06/11/88	12:00 PM	242.06
5	06/12/88	12:00 PM	242.05
5	06/13/88	12:00 PM	242.03
5	06/14/88	12:00 PM	242.01
5	06/15/88	12:00 PM	242.01
5	06/16/88	12:00 PM	242.02
5	06/17/88	12:00 PM	242.02
5	06/18/88	12:00 PM	242.00
5	06/19/88	12:00 PM	241.97
5	06/20/88	12:00 PM	241.95
5	06/21/88	12:00 PM	241.93
5	06/21/88	12:00 PM	241.95
5	06/22/88	12:00 PM	241.94
5	06/23/88	12:00 PM	241.94
5	06/24/88	12:00 PM	241.92
5	06/25/88	12:00 PM	241.89
5	06/26/88	12:00 PM	241.91
5	06/27/88	12:00 PM	241.90
5	06/28/88	12:00 PM	241.88
5	06/29/88	12:00 PM	241.88
5	06/30/88	12:00 PM	241.88
5	07/01/88	12:00 PM	241.85
5	07/01/88	12:00 PM	241.85
5	07/02/88	12:00 PM	241.84
5	07/03/88	12:00 PM	241.82
5	07/04/88	12:00 PM	241.80
5	07/05/88	12:00 PM	241.77
5	07/06/88	12:00 PM	241.76

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
5	07/07/88	12:00 PM	241.76
5	07/08/88	12:00 PM	241.75
5	07/09/88	12:00 PM	241.75
5	07/10/88	12:00 PM	241.73
5	07/11/88	12:00 PM	241.72
5	07/12/88	12:00 PM	241.72
5	07/13/88	12:00 PM	241.71
5	07/14/88	12:00 PM	241.73
5	07/15/88	12:00 PM	241.75
5	07/16/88	12:00 PM	241.74
5	07/17/88	12:00 PM	241.75
5	07/18/88	12:00 PM	241.76
5	07/19/88	12:00 PM	241.76
5	07/20/88	12:00 PM	241.76
5	07/21/88	12:00 PM	241.75
5	07/22/88	12:00 PM	241.76
5	07/23/88	12:00 PM	241.77
5	07/24/88	12:00 PM	241.76
5	07/25/88	12:00 PM	241.77
5	07/26/88	12:00 PM	241.77
5	07/26/88	12:00 PM	241.76
5	07/27/88	12:00 PM	241.77
5	07/28/88	12:00 PM	241.77
5	07/29/88	12:00 PM	241.77
5	07/30/88	12:00 PM	241.79
5	07/31/88	12:00 PM	241.80
5	08/01/88	12:00 PM	241.81
5	08/02/88	12:00 PM	241.80
5	08/03/88	12:00 PM	241.80
5	08/04/88	12:00 PM	241.80
5	08/05/88	12:00 PM	241.80
5	08/06/88	12:00 PM	241.80
5	08/07/88	12:00 PM	241.79
5	08/08/88	12:00 PM	241.79
5	08/09/88	12:00 PM	241.78
5	08/10/88	12:00 PM	241.76
5	08/11/88	12:00 PM	241.76
5	08/12/88	12:00 PM	241.74
5	08/13/88	12:00 PM	241.75
5	08/14/88	12:00 PM	241.75
5	08/15/88	12:00 PM	241.75
5	08/16/88	12:00 PM	241.74
5	08/17/88	12:00 PM	241.73
5	08/18/88	12:00 PM	241.74
5	08/19/88	12:00 PM	241.74
5	08/20/88	12:00 PM	241.73

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
5	08/21/88	12:00 PM	241.73
5	08/22/88	12:00 PM	241.70
5	08/23/88	12:00 PM	241.69

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
6	06/04/87	09:00 AM	240.54
6	06/15/87	01:30 PM	240.41
6	07/13/87	12:00 PM	240.38
6	08/04/87	08:41 AM	243.99
6	08/04/87	01:30 PM	245.42
6	08/05/87	07:09 AM	246.24
6	08/05/87	02:51 PM	246.56
6	08/06/87	08:41 AM	247.30
6	08/06/87	01:11 PM	247.68
6	08/06/87	03:15 PM	247.74
6	08/07/87	09:03 AM	245.81
6	08/07/87	02:24 PM	247.62
6	08/10/87	09:02 AM	247.94
6	08/11/87	03:18 PM	245.86
6	08/12/87	09:50 AM	244.91
6	08/13/87	08:48 AM	243.46
6	08/14/87	07:47 AM	242.88
6	08/17/87	07:15 AM	242.16
6	08/21/87	03:14 PM	241.63
6	09/04/87	08:19 AM	240.83
6	09/11/87	01:30 PM	240.59
6	09/18/87	01:30 PM	240.52
6	09/25/87	01:30 PM	240.44
6	10/01/87	01:30 PM	240.36
6	10/08/87	01:30 PM	240.25
6	10/15/87	01:30 PM	240.14
6	11/04/87	09:51 AM	241.17
6	11/05/87	01:30 PM	241.06
6	11/10/87	01:30 PM	240.74
6	11/12/87	01:00 PM	240.61
6	11/17/87	08:15 AM	240.43
6	11/18/87	11:11 AM	240.37
6	12/03/87	01:30 PM	239.94
6	12/11/87	01:30 PM	239.86
6	12/16/87	01:30 PM	239.76
6	12/21/87	02:30 PM	239.76
6	12/28/87	10:15 AM	239.79
6	12/31/87	01:00 PM	239.77
6	01/04/88	02:00 PM	239.86
6	01/08/88	10:40 AM	239.91
6	01/14/88	08:50 AM	239.95
6	01/21/88	10:00 AM	240.39
6	01/22/88	01:00 PM	240.62
6	01/25/88	10:00 AM	240.84
6	01/28/88	10:00 AM	240.85
6	02/01/88	10:15 AM	240.94

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
6	02/11/88	10:30 AM	241.09
6	02/18/88	01:50 PM	240.98
6	02/26/88	12:15 PM	240.86
6	03/03/88	09:50 AM	240.83
6	03/04/88	12:00 PM	240.84
6	03/05/88	12:00 PM	240.78
6	03/06/88	12:00 PM	240.76
6	03/07/88	12:00 PM	240.74
6	03/08/88	12:00 PM	240.72
6	03/09/88	08:30 AM	240.75
6	03/09/88	12:00 PM	240.75
6	03/10/88	12:00 PM	240.76
6	03/11/88	12:00 PM	240.77
6	03/12/88	12:00 PM	240.82
6	03/13/88	12:00 PM	240.91
6	03/14/88	12:00 PM	241.04
6	03/15/88	12:00 PM	241.10
6	03/16/88	11:45 AM	241.13
6	03/16/88	12:00 PM	241.13
6	03/17/88	12:00 PM	241.16
6	03/18/88	12:00 PM	241.23
6	03/19/88	12:00 PM	241.23
6	03/20/88	12:00 PM	241.23
6	03/21/88	12:00 PM	241.21
6	03/22/88	12:00 PM	241.19
6	03/23/88	12:00 PM	241.16
6	03/24/88	12:00 PM	241.13
6	03/25/88	12:00 PM	241.14
6	03/26/88	12:00 PM	241.12
6	03/27/88	12:00 PM	241.08
6	03/28/88	10:00 AM	241.04
6	03/28/88	12:00 PM	241.03
6	03/29/88	12:00 PM	241.02
6	03/30/88	12:00 PM	240.98
6	03/31/88	12:00 PM	240.95
6	04/01/88	12:00 PM	240.93
6	04/02/88	12:00 PM	240.91
6	04/03/88	12:00 PM	240.89
6	04/04/88	10:00 AM	240.88
6	04/04/88	12:00 PM	240.90
6	04/05/88	12:00 PM	240.84
6	04/06/88	12:00 PM	240.85
6	04/07/88	12:00 PM	240.84
6	04/08/88	12:00 PM	240.80
6	04/09/88	12:00 PM	240.78
6	04/10/88	12:00 PM	240.79

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
6	04/11/88	12:00 PM	240.82
6	04/12/88	12:00 PM	240.82
6	04/13/88	12:00 PM	240.77
6	04/14/88	12:00 PM	240.74
6	04/15/88	12:00 PM	240.73
6	04/16/88	12:00 PM	240.70
6	04/17/88	12:00 PM	240.70
6	04/18/88	12:00 PM	240.73
6	04/19/88	12:00 PM	240.73
6	04/20/88	12:00 PM	240.70
6	04/21/88	12:00 PM	240.73
6	04/22/88	12:00 PM	240.75
6	04/23/88	12:00 PM	240.76
6	04/24/88	12:00 PM	240.75
6	04/25/88	12:00 PM	240.73
6	04/26/88	12:00 PM	240.75
6	04/27/88	12:00 PM	240.73
6	04/28/88	12:00 PM	240.70
6	04/29/88	12:00 PM	240.69
6	04/30/88	12:00 PM	240.69
6	05/01/88	12:00 PM	240.67
6	05/02/88	12:00 PM	240.66
6	05/03/88	10:00 AM	240.66
6	05/03/88	12:00 PM	240.65
6	05/04/88	12:00 PM	240.66
6	05/05/88	12:00 PM	240.63
6	05/06/88	12:00 PM	240.61
6	05/07/88	12:00 PM	240.59
6	05/08/88	12:00 PM	240.57
6	05/09/88	12:00 PM	240.56
6	05/10/88	12:00 PM	240.55
6	05/11/88	12:00 PM	240.52
6	05/12/88	10:00 AM	240.55
6	05/12/88	12:00 PM	240.50
6	05/13/88	12:00 PM	240.49
6	05/14/88	12:00 PM	240.48
6	05/15/88	12:00 PM	240.48
6	05/16/88	12:00 PM	240.47
6	05/17/88	12:00 PM	240.46
6	05/18/88	12:00 PM	240.44
6	05/19/88	12:00 PM	240.42
6	05/20/88	12:00 PM	240.40
6	05/20/88	01:30 PM	240.41
6	05/21/88	12:00 PM	240.38
6	05/22/88	12:00 PM	240.37
6	05/23/88	12:00 PM	240.36

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
6	05/24/88	12:00 PM	240.36
6	05/25/88	12:00 PM	240.33
6	05/26/88	12:00 PM	240.30
6	05/26/88	02:15 PM	240.29
6	05/27/88	12:00 PM	240.28
6	05/28/88	12:00 PM	240.28
6	05/29/88	12:00 PM	240.27
6	05/30/88	12:00 PM	240.26
6	05/31/88	12:00 PM	240.24
6	06/01/88	12:00 PM	240.24
6	06/02/88	09:30 AM	240.24
6	06/02/88	12:00 PM	240.24
6	06/03/88	12:00 PM	240.25
6	06/04/88	12:00 PM	240.20
6	06/05/88	12:00 PM	240.17
6	06/06/88	12:00 PM	240.16
6	06/07/88	12:00 PM	240.16
6	06/08/88	12:00 PM	240.17
6	06/09/88	10:30 AM	240.17
6	06/09/88	12:00 PM	240.18
6	06/10/88	12:00 PM	240.12
6	06/11/88	12:00 PM	240.08
6	06/12/88	12:00 PM	240.07
6	06/13/88	12:00 PM	240.05
6	06/14/88	12:00 PM	240.04
6	06/15/88	12:00 PM	240.03
6	06/16/88	12:00 PM	240.04
6	06/17/88	12:00 PM	240.04
6	06/18/88	12:00 PM	240.02
6	06/19/88	12:00 PM	239.99
6	06/20/88	12:00 PM	239.98
6	06/21/88	12:00 PM	239.96
6	06/21/88	12:00 PM	239.97
6	06/22/88	12:00 PM	239.97
6	06/23/88	12:00 PM	239.96
6	06/24/88	12:00 PM	239.95
6	06/25/88	12:00 PM	239.86
6	06/26/88	12:00 PM	239.90
6	06/27/88	12:00 PM	239.91
6	06/28/88	12:00 PM	239.90
6	06/29/88	12:00 PM	239.90
6	06/30/88	12:00 PM	239.91
6	07/01/88	12:00 PM	239.49
6	07/01/88	12:00 PM	239.89
6	07/02/88	12:00 PM	239.88
6	07/03/88	12:00 PM	239.87

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
6	07/04/88	12:00 PM	239.85
6	07/05/88	12:00 PM	239.83
6	07/06/88	12:00 PM	239.82
6	07/07/88	12:00 PM	239.81
6	07/08/88	12:00 PM	239.81
6	07/09/88	12:00 PM	239.83
6	07/10/88	12:00 PM	239.82
6	07/11/88	12:00 PM	239.80
6	07/12/88	12:00 PM	239.80
6	07/13/88	12:00 PM	239.80
6	07/14/88	12:00 PM	239.81
6	07/15/88	12:00 PM	239.82
6	07/16/88	12:00 PM	239.84
6	07/17/88	12:00 PM	239.84
6	07/18/88	12:00 PM	239.84
6	07/19/88	12:00 PM	239.86
6	07/20/88	12:00 PM	239.89
6	07/21/88	12:00 PM	239.92
6	07/22/88	12:00 PM	239.95
6	07/23/88	12:00 PM	240.00
6	07/24/88	12:00 PM	240.00
6	07/25/88	12:00 PM	240.03
6	07/26/88	12:00 PM	240.03
6	07/27/88	12:00 PM	240.01
6	07/28/88	12:00 PM	239.94
6	07/29/88	12:00 PM	239.86
6	07/30/88	12:00 PM	239.83
6	07/31/88	12:00 PM	239.77
6	08/01/88	12:00 PM	239.58
6	08/02/88	12:00 PM	239.53
6	08/03/88	12:00 PM	239.52
6	08/04/88	12:00 PM	239.54
6	08/05/88	12:00 PM	239.52
6	08/06/88	12:00 PM	239.49
6	08/07/88	12:00 PM	239.47
6	08/08/88	12:00 PM	239.43
6	08/09/88	12:00 PM	239.39
6	08/10/88	12:00 PM	239.35
6	08/11/88	12:00 PM	239.32
6	08/12/88	12:00 PM	239.30
6	08/13/88	12:00 PM	239.27
6	08/14/88	12:00 PM	239.25
6	08/15/88	12:00 PM	239.23
6	08/16/88	12:00 PM	239.20
6	08/17/88	12:00 PM	239.17
6	08/18/88	12:00 PM	239.15

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
6	08/19/88	12:00 PM	239.13
6	08/20/88	12:00 PM	239.11
6	08/21/88	12:00 PM	239.07
6	08/22/88	12:00 PM	239.02
6	08/23/88	12:00 PM	239.9

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
7	06/04/87	09:25 AM	240.73
7	06/15/87	01:30 PM	240.68
7	07/13/87	12:00 PM	240.59
7	07/27/87	10:51 AM	240.51
7	07/27/87	01:32 PM	240.51
7	07/27/87	04:01 PM	240.52
7	07/27/87	08:37 PM	240.51
7	07/28/87	06:31 AM	240.51
7	07/28/87	10:16 AM	240.52
7	07/28/87	01:10 PM	240.54
7	07/28/87	03:01 PM	240.55
7	07/29/87	09:15 AM	241.32
7	07/29/87	02:54 PM	241.55
7	07/30/87	09:10 AM	241.92
7	07/30/87	04:18 PM	241.99
7	07/31/87	08:42 AM	242.07
7	08/03/87	08:58 AM	241.87
7	08/04/87	08:48 AM	241.67
7	08/05/87	07:26 AM	241.74
7	08/05/87	03:03 PM	241.81
7	08/06/87	08:53 AM	242.03
7	08/07/87	09:09 AM	242.38
7	08/10/87	09:13 AM	242.61
7	08/12/87	09:53 AM	242.43
7	08/14/87	07:51 AM	242.22
7	08/17/87	07:26 AM	241.91
7	08/21/87	03:19 PM	241.55
7	09/04/87	08:21 AM	240.78
7	09/11/87	01:30 PM	240.61
7	09/18/87	01:30 PM	240.54
7	09/25/87	01:30 PM	240.49
7	10/01/87	01:30 PM	240.46
7	10/08/87	01:30 PM	240.43
7	10/15/87	01:30 PM	240.41
7	10/19/87	02:02 PM	240.41
7	10/20/87	08:48 AM	240.39
7	10/20/87	03:51 PM	240.40
7	10/21/87	09:17 AM	240.39
7	10/22/87	09:15 AM	240.40
7	10/23/87	09:08 AM	240.42
7	10/26/87	09:18 AM	242.34
7	10/27/87	09:00 AM	242.33
7	10/28/87	09:03 AM	242.23
7	10/29/87	09:29 AM	243.03
7	10/30/87	09:43 AM	243.81
7	11/02/87	02:15 PM	243.10

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
7	11/04/87	09:48 AM	242.57
7	11/05/87	01:30 PM	242.30
7	11/10/87	01:30 PM	241.53
7	11/12/87	01:00 PM	241.34
7	11/17/87	08:15 AM	241.05
7	11/19/87	02:55 PM	240.94
7	12/03/87	01:30 PM	240.62
7	12/11/87	01:30 PM	240.52
7	12/16/87	01:30 PM	240.48
7	12/21/87	02:30 PM	240.46
7	12/28/87	10:15 AM	240.45
7	12/31/87	01:00 PM	240.45
7	01/04/88	02:00 PM	240.45
7	01/08/88	10:40 AM	240.45
7	01/14/88	08:50 AM	240.47
7	01/21/88	10:00 AM	240.56
7	01/22/88	01:00 PM	240.70
7	01/25/88	10:00 AM	241.02
7	01/28/88	10:00 AM	241.07
7	02/01/88	10:15 AM	241.06
7	02/11/88	10:30 AM	241.08
7	02/18/88	01:50 PM	241.05
7	02/26/88	12:15 PM	241.03
7	03/03/88	10:00 AM	240.87
7	03/04/88	12:00 PM	240.84
7	03/05/88	12:00 PM	240.82
7	03/06/88	12:00 PM	240.80
7	03/07/88	12:00 PM	240.79
7	03/08/88	12:00 PM	240.78
7	03/09/88	08:30 AM	240.80
7	03/09/88	12:00 PM	240.79
7	03/10/88	12:00 PM	240.78
7	03/11/88	12:00 PM	240.80
7	03/12/88	12:00 PM	240.86
7	03/13/88	12:00 PM	240.91
7	03/14/88	12:00 PM	240.99
7	03/15/88	12:00 PM	241.03
7	03/16/88	11:45 AM	241.08
7	03/16/88	12:00 PM	241.04
7	03/17/88	12:00 PM	241.08
7	03/18/88	12:00 PM	241.11
7	03/19/88	12:00 PM	241.12
7	03/20/88	12:00 PM	241.14
7	03/21/88	12:00 PM	241.14
7	03/22/88	12:00 PM	241.13
7	03/23/88	12:00 PM	241.12

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
7	03/24/88	12:00 PM	241.10
7	03/25/88	12:00 PM	241.10
7	03/26/88	12:00 PM	241.09
7	03/27/88	12:00 PM	241.05
7	03/28/88	10:00 AM	241.06
7	03/28/88	12:00 PM	241.03
7	03/29/88	12:00 PM	241.02
7	03/30/88	12:00 PM	240.98
7	03/31/88	12:00 PM	240.96
7	04/01/88	12:00 PM	240.94
7	04/02/88	12:00 PM	240.92
7	04/03/88	12:00 PM	240.91
7	04/04/88	10:00 AM	240.92
7	04/04/88	12:00 PM	240.90
7	04/05/88	12:00 PM	240.87
7	04/06/88	12:00 PM	240.86
7	04/07/88	12:00 PM	240.86
7	04/08/88	12:00 PM	240.86
7	04/09/88	12:00 PM	240.85
7	04/10/88	12:00 PM	240.86
7	04/11/88	12:00 PM	240.87
7	04/12/88	12:00 PM	240.85
7	04/13/88	12:00 PM	240.82
7	04/14/88	12:00 PM	240.80
7	04/15/88	12:00 PM	240.79
7	04/16/88	12:00 PM	240.77
7	04/17/88	12:00 PM	240.76
7	04/18/88	12:00 PM	240.76
7	04/19/88	12:00 PM	240.76
7	04/20/88	12:00 PM	240.77
7	04/21/88	12:00 PM	240.80
7	04/22/88	12:00 PM	240.81
7	04/23/88	12:00 PM	240.81
7	04/24/88	12:00 PM	240.80
7	04/25/88	12:00 PM	240.79
7	04/26/88	12:00 PM	240.78
7	04/27/88	12:00 PM	240.77
7	04/28/88	12:00 PM	240.74
7	04/29/88	12:00 PM	240.73
7	04/30/88	12:00 PM	240.72
7	05/01/88	12:00 PM	240.71
7	05/02/88	12:00 PM	240.70
7	05/03/88	10:00 AM	240.73
7	05/03/88	12:00 PM	240.69
7	05/04/88	12:00 PM	240.69
7	05/05/88	12:00 PM	240.68

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
7	05/06/88	12:00 PM	240.67
7	05/07/88	12:00 PM	240.66
7	05/08/88	12:00 PM	240.65
7	05/09/88	12:00 PM	240.64
7	05/10/88	12:00 PM	240.63
7	05/11/88	12:00 PM	240.62
7	05/12/88	10:00 AM	240.66
7	05/12/88	12:00 PM	240.61
7	05/13/88	12:00 PM	240.60
7	05/14/88	12:00 PM	240.60
7	05/15/88	12:00 PM	240.59
7	05/16/88	12:00 PM	240.59
7	05/17/88	12:00 PM	240.58
7	05/18/88	12:00 PM	240.57
7	05/19/88	12:00 PM	240.56
7	05/20/88	12:00 PM	240.55
7	05/20/88	01:30 PM	240.60
7	05/21/88	12:00 PM	240.55
7	05/22/88	12:00 PM	240.54
7	05/23/88	12:00 PM	240.53
7	05/24/88	12:00 PM	240.53
7	05/25/88	12:00 PM	240.52
7	05/26/88	12:00 PM	240.51
7	05/26/88	02:15 PM	240.56
7	05/27/88	12:00 PM	240.50
7	05/28/88	12:00 PM	240.50
7	05/29/88	12:00 PM	240.49
7	05/30/88	12:00 PM	240.49
7	05/31/88	12:00 PM	240.48
7	06/01/88	12:00 PM	240.48
7	06/02/88	09:30 AM	240.52
7	06/02/88	12:00 PM	240.48
7	06/03/88	12:00 PM	240.47
7	06/04/88	12:00 PM	240.46
7	06/05/88	12:00 PM	240.46
7	06/06/88	12:00 PM	240.45
7	06/07/88	12:00 PM	240.45
7	06/08/88	12:00 PM	240.45
7	06/09/88	10:30 AM	240.49
7	06/09/88	12:00 PM	240.45
7	06/10/88	12:00 PM	240.44
7	06/11/88	12:00 PM	240.43
7	06/12/88	12:00 PM	240.43
7	06/13/88	12:00 PM	240.42
7	06/14/88	12:00 PM	240.42
7	06/15/88	12:00 PM	240.42

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
7	06/16/88	12:00 PM	240.41
7	06/17/88	12:00 PM	240.41
7	06/18/88	12:00 PM	240.41
7	06/19/88	12:00 PM	240.40
7	06/20/88	12:00 PM	240.40
7	06/21/88	12:00 PM	240.40
7	06/21/88	12:00 PM	240.44
7	06/22/88	12:00 PM	240.39
7	06/23/88	12:00 PM	240.39
7	06/24/88	12:00 PM	240.38
7	06/25/88	12:00 PM	240.38
7	06/26/88	12:00 PM	240.38
7	06/27/88	12:00 PM	240.38
7	06/28/88	12:00 PM	240.38
7	06/29/88	12:00 PM	240.38
7	06/30/88	12:00 PM	240.38
7	07/01/88	12:00 PM	240.37
7	07/01/88	12:00 PM	240.42
7	07/02/88	12:00 PM	240.37
7	07/03/88	12:00 PM	240.37
7	07/04/88	12:00 PM	240.36
7	07/05/88	12:00 PM	240.36
7	07/06/88	12:00 PM	240.36
7	07/07/88	12:00 PM	240.35
7	07/08/88	12:00 PM	240.35
7	07/09/88	12:00 PM	240.35
7	07/10/88	12:00 PM	240.35
7	07/11/88	12:00 PM	240.34
7	07/12/88	12:00 PM	240.34
7	07/13/88	12:00 PM	240.34
7	07/14/88	12:00 PM	240.35
7	07/15/88	12:00 PM	240.36
7	07/16/88	12:00 PM	240.36
7	07/17/88	12:00 PM	240.36
7	07/18/88	12:00 PM	240.37
7	07/19/88	12:00 PM	240.36
7	07/20/88	12:00 PM	240.36
7	07/21/88	12:00 PM	240.36
7	07/22/88	12:00 PM	240.36
7	07/23/88	12:00 PM	240.37
7	07/24/88	12:00 PM	240.36
7	07/25/88	12:00 PM	240.34
7	07/26/88	12:00 PM	240.32
7	07/26/88	12:00 PM	240.41
7	07/27/88	12:00 PM	240.30
7	07/28/88	12:00 PM	240.28

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
7	07/29/88	12:00 PM	240.28
7	07/30/88	12:00 PM	240.28
7	07/31/88	12:00 PM	240.28
7	08/01/88	12:00 PM	240.28
7	08/02/88	12:00 PM	240.27
7	08/03/88	12:00 PM	240.27
7	08/04/88	12:00 PM	240.27
7	08/05/88	12:00 PM	240.27
7	08/06/88	12:00 PM	240.27
7	08/07/88	12:00 PM	240.27
7	08/08/88	12:00 PM	240.27
7	08/09/88	12:00 PM	240.26
7	08/10/88	12:00 PM	240.26
7	08/11/88	12:00 PM	240.25
7	08/12/88	12:00 PM	240.23
7	08/13/88	12:00 PM	240.23
7	08/14/88	12:00 PM	240.24
7	08/15/88	12:00 PM	240.23
7	08/16/88	12:00 PM	240.23
7	08/17/88	12:00 PM	240.23
7	08/18/88	12:00 PM	240.24
7	08/19/88	12:00 PM	240.24
7	08/20/88	12:00 PM	240.24
7	08/21/88	12:00 PM	240.23
7	08/22/88	12:00 PM	240.23
7	08/23/88	12:00 PM	240.34

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
8	05/21/87	01:27 PM	240.77
8	06/15/87	01:30 PM	240.58
8	07/13/87	12:00 PM	240.65
8	07/31/87	09:12 AM	240.14
8	08/03/87	09:52 AM	240.11
8	08/04/87	10:05 AM	240.10
8	08/04/87	02:27 PM	240.10
8	08/05/87	07:49 AM	240.09
8	08/05/87	03:22 PM	240.10
8	08/06/87	10:20 AM	240.09
8	08/07/87	09:28 AM	240.09
8	08/10/87	09:41 AM	240.08
8	08/12/87	10:14 AM	240.07
8	08/14/87	08:12 AM	240.21
8	08/17/87	07:00 AM	240.20
8	08/21/87	03:35 PM	240.17
8	09/04/87	08:48 AM	239.92
8	09/11/87	01:30 PM	239.86
8	09/18/87	01:30 PM	240.29
8	09/25/87	01:30 PM	240.21
8	10/01/87	01:30 PM	240.26
8	10/08/87	01:30 PM	240.16
8	10/15/87	01:30 PM	240.09
8	10/19/87	02:37 PM	240.07
8	10/20/87	09:28 AM	240.06
8	10/21/87	09:31 AM	240.06
8	10/22/87	09:50 AM	240.07
8	10/23/87	09:30 AM	240.08
8	10/26/87	09:53 AM	240.11
8	10/27/87	09:24 AM	240.11
8	10/28/87	09:30 AM	240.12
8	10/29/87	09:39 AM	240.13
8	10/30/87	09:56 AM	240.14
8	11/02/87	01:49 PM	240.17
8	11/04/87	10:03 AM	240.20
8	11/05/87	01:30 PM	240.21
8	11/10/87	01:30 PM	240.45
8	11/12/87	01:00 PM	240.44
8	11/17/87	08:15 AM	240.59
8	11/19/87	04:10 PM	240.44
8	12/03/87	01:30 PM	240.44
8	12/11/87	01:30 PM	240.39
8	12/16/87	01:30 PM	240.53
8	12/21/87	02:30 PM	240.49
8	12/28/87	10:15 AM	240.67
8	12/31/87	01:00 PM	240.57

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
8	01/04/88	02:00 AM	240.70
8	01/08/88	10:40 AM	240.57
8	01/14/88	08:50 AM	240.62
8	01/21/88	10:00 AM	240.81
8	01/22/88	01:00 PM	240.70
8	01/25/88	10:00 AM	240.63
8	01/28/88	10:00 AM	240.59
8	02/01/88	10:15 AM	240.59
8	02/11/88	10:30 AM	240.64
8	02/18/88	01:50 PM	240.71
8	02/26/88	12:15 PM	240.64
8	03/03/88	10:00 AM	240.62
8	03/09/88	08:30 AM	240.64
8	03/16/88	10:00 AM	240.76
8	03/17/88	12:00 PM	240.73
8	03/18/88	12:00 PM	240.72
8	03/19/88	12:00 PM	240.70
8	03/20/88	12:00 PM	240.69
8	03/21/88	12:00 PM	240.68
8	03/22/88	12:00 PM	240.67
8	03/23/88	12:00 PM	240.66
8	03/24/88	12:00 PM	240.66
8	03/25/88	12:00 PM	240.66
8	03/26/88	12:00 PM	240.67
8	03/27/88	12:00 PM	240.65
8	03/28/88	10:00 AM	240.64
8	03/28/88	12:00 PM	240.64
8	03/29/88	12:00 PM	240.63
8	03/30/88	12:00 PM	240.62
8	03/31/88	12:00 PM	240.62
8	04/01/88	12:00 PM	240.61
8	04/02/88	12:00 PM	240.65
8	04/03/88	12:00 PM	240.64
8	04/04/88	10:00 AM	240.72
8	04/04/88	12:00 PM	240.68
8	04/05/88	12:00 PM	240.68
8	04/06/88	12:00 PM	240.91
8	04/07/88	12:00 PM	240.81
8	04/08/88	12:00 PM	240.74
8	04/09/88	12:00 PM	240.70
8	04/10/88	12:00 PM	240.69
8	04/11/88	12:00 PM	240.67
8	04/12/88	12:00 PM	240.69
8	04/13/88	12:00 PM	240.66
8	04/14/88	12:00 PM	240.64
8	04/15/88	12:00 PM	240.63

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
8	04/16/88	12:00 PM	240.66
8	04/17/88	12:00 PM	240.64
8	04/18/88	12:00 PM	240.82
8	04/19/88	12:00 PM	240.89
8	04/20/88	12:00 PM	240.84
8	04/21/88	12:00 PM	240.78
8	04/22/88	12:00 PM	240.73
8	04/23/88	12:00 PM	240.71
8	04/24/88	12:00 PM	240.69
8	04/25/88	12:00 PM	240.67
8	04/26/88	12:00 PM	240.65
8	04/27/88	12:00 PM	240.64
8	04/28/88	12:00 PM	240.63
8	04/29/88	12:00 PM	240.62
8	04/30/88	12:00 PM	240.62
8	05/01/88	12:00 PM	240.61
8	05/02/88	12:00 PM	240.60
8	05/03/88	10:00 AM	240.65
8	05/03/88	12:00 PM	240.60
8	05/04/88	12:00 PM	240.70
8	05/05/88	12:00 PM	240.67
8	05/06/88	12:00 PM	240.64
8	05/07/88	12:00 PM	240.62
8	05/08/88	12:00 PM	240.60
8	05/09/88	12:00 PM	240.67
8	05/10/88	12:00 PM	240.65
8	05/11/88	12:00 PM	240.63
8	05/12/88	10:00 AM	240.65
8	05/12/88	12:00 PM	240.61
8	05/13/88	12:00 PM	240.59
8	05/14/88	12:00 PM	240.58
8	05/15/88	12:00 PM	240.57
8	05/16/88	12:00 PM	240.56
8	05/17/88	12:00 PM	240.55
8	05/18/88	12:00 PM	240.53
8	05/19/88	12:00 PM	240.52
8	05/20/88	12:00 PM	240.51
8	05/20/88	01:30 PM	240.61
8	05/21/88	12:00 PM	240.50
8	05/22/88	12:00 PM	240.49
8	05/23/88	12:00 PM	240.48
8	05/24/88	12:00 PM	240.52
8	05/25/88	12:00 PM	240.65
8	05/26/88	12:00 PM	240.62
8	05/26/88	02:15 PM	240.66
8	05/27/88	12:00 PM	240.59

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
8	05/28/88	12:00 PM	240.56
8	05/29/88	12:00 PM	240.53
8	05/30/88	12:00 PM	240.50
8	05/31/88	12:00 PM	240.47
8	06/01/88	12:00 PM	240.44
8	06/02/88	09:30 AM	240.46
8	06/02/88	12:00 PM	240.42
8	06/03/88	12:00 PM	240.39
8	06/04/88	12:00 PM	240.36
8	06/05/88	12:00 PM	240.33
8	06/06/88	12:00 PM	240.31
8	06/07/88	12:00 PM	240.29
8	06/08/88	12:00 PM	240.27
8	06/09/88	10:30 AM	240.32
8	06/09/88	12:00 PM	240.27
8	06/10/88	12:00 PM	240.37
8	06/11/88	12:00 PM	240.37
8	06/12/88	12:00 PM	240.34
8	06/13/88	12:00 PM	240.30
8	06/14/88	12:00 PM	240.26
8	06/15/88	12:00 PM	240.23
8	06/16/88	12:00 PM	240.20
8	06/17/88	12:00 PM	240.18
8	06/18/88	12:00 PM	240.16
8	06/19/88	12:00 PM	240.13
8	06/20/88	12:00 PM	240.12
8	06/21/88	12:00 PM	240.11
8	06/21/88	12:00 PM	240.13
8	06/23/88	12:00 PM	240.08
8	06/24/88	12:00 PM	240.06
8	06/25/88	12:00 PM	240.05
8	06/26/88	12:00 PM	240.34
8	06/27/88	12:00 PM	240.31
8	06/28/88	12:00 PM	240.28
8	06/29/88	12:00 PM	240.25
8	06/30/88	12:00 PM	240.22
8	07/01/88	12:00 PM	240.21
8	07/01/88	12:00 PM	240.23
8	07/03/88	12:00 PM	240.17
8	07/04/88	12:00 PM	240.17
8	07/05/88	12:00 PM	240.15
8	07/06/88	12:00 PM	240.13
8	07/07/88	12:00 PM	240.09
8	07/09/88	12:00 PM	240.03
8	07/10/88	12:00 PM	240.01
8	07/11/88	12:00 PM	239.98

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
8	07/12/88	12:00 PM	240.52
8	07/13/88	12:00 PM	240.63
8	07/14/88	12:00 PM	240.68
8	07/15/88	12:00 PM	240.56
8	07/16/88	12:00 PM	240.50
8	07/17/88	12:00 PM	240.45
8	07/18/88	12:00 PM	240.41
8	07/19/88	12:00 PM	240.37
8	07/20/88	12:00 PM	240.34
8	07/21/88	12:00 PM	240.44
8	07/22/88	12:00 PM	240.60
8	07/23/88	12:00 PM	240.54
8	07/24/88	12:00 PM	240.49
8	07/25/88	12:00 PM	240.45
8	07/26/88	12:00 PM	240.41
8	07/26/88	12:00 PM	240.43
8	07/27/88	12:00 PM	240.88
8	07/28/88	12:00 PM	240.80
8	07/29/88	12:00 PM	240.75
8	07/30/88	12:00 PM	240.71
8	07/31/88	12:00 PM	240.64
8	08/01/88	12:00 PM	240.60
8	08/02/88	12:00 PM	240.56
8	08/23/88	12:00 PM	240.17

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
9	05/21/87	10:38 AM	239.84
9	06/15/87	01:30 PM	239.78
9	07/13/87	12:00 PM	239.89
9	07/31/87	09:11 AM	239.46
9	08/03/87	09:51 AM	239.42
9	08/04/87	10:06 AM	239.40
9	08/04/87	02:26 PM	239.41
9	08/05/87	07:47 AM	239.39
9	08/05/87	03:21 PM	239.40
9	08/06/87	10:19 AM	239.38
9	08/07/87	09:26 AM	239.37
9	08/10/87	09:40 AM	239.34
9	08/12/87	10:12 AM	239.32
9	08/14/87	08:11 AM	239.40
9	08/17/87	06:59 AM	239.39
9	08/21/87	03:34 PM	239.35
9	09/04/87	08:47 AM	239.18
9	09/11/87	01:30 PM	239.12
9	09/18/87	01:30 PM	239.52
9	09/25/87	01:30 PM	239.44
9	10/01/87	01:30 PM	239.46
9	10/08/87	01:30 PM	239.38
9	10/15/87	01:30 PM	239.32
9	10/19/87	02:36 PM	239.30
9	10/20/87	09:26 AM	239.30
9	10/21/87	09:30 AM	239.29
9	10/22/87	09:49 AM	239.27
9	10/23/87	09:29 AM	239.27
9	10/26/87	09:52 AM	239.29
9	10/27/87	09:23 AM	239.29
9	10/28/87	09:29 AM	239.28
9	10/29/87	09:37 AM	239.27
9	10/30/87	09:56 AM	239.27
9	11/02/87	01:47 PM	239.28
9	11/04/87	10:06 AM	239.29
9	11/05/87	01:30 PM	239.29
9	11/10/87	01:30 PM	239.44
9	11/12/87	01:00 PM	239.60
9	11/17/87	08:15 AM	239.64
9	11/19/87	03:56 PM	239.51
9	12/03/87	01:30 PM	239.63
9	12/11/87	01:30 PM	239.57
9	12/16/87	01:30 PM	239.73
9	12/21/87	02:30 PM	239.68
9	12/28/87	10:15 AM	239.92
9	12/31/87	01:00 PM	239.82

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
9	01/04/88	02:00 PM	239.94
9	01/08/88	10:40 AM	239.81
9	01/14/88	08:50 AM	239.84
9	01/21/88	10:00 AM	240.12
9	01/22/88	01:00 PM	240.05
9	01/25/88	10:00 AM	240.00
9	01/28/88	10:00 AM	239.90
9	02/01/88	10:15 AM	239.92
9	02/11/88	10:30 AM	240.06
9	02/18/88	01:50 PM	240.12
9	02/26/88	12:15 PM	240.14
9	03/03/88	10:00 AM	240.02
9	03/04/88	12:00 PM	240.05
9	03/05/88	12:00 PM	240.04
9	03/06/88	12:00 PM	240.04
9	03/07/88	12:00 PM	240.02
9	03/08/88	12:00 PM	240.02
9	03/09/88	08:30 AM	240.17
9	03/09/88	12:00 PM	240.06
9	03/10/88	12:00 PM	240.23
9	03/11/88	12:00 PM	240.21
9	03/12/88	12:00 PM	240.17
9	03/13/88	12:00 PM	240.20
9	03/14/88	12:00 PM	240.17
9	03/15/88	12:00 PM	240.10
9	03/16/88	10:00 AM	239.87
9	03/16/88	12:00 PM	240.07
9	03/17/88	12:00 PM	240.02
9	03/18/88	12:00 PM	240.02
9	03/19/88	12:00 PM	240.00
9	03/20/88	12:00 PM	239.97
9	03/21/88	12:00 PM	239.95
9	03/22/88	12:00 PM	239.92
9	03/23/88	12:00 PM	239.91
9	03/24/88	12:00 PM	239.91
9	03/25/88	12:00 PM	239.92
9	03/26/88	12:00 PM	239.93
9	03/27/88	12:00 PM	239.90
9	03/28/88	10:00 AM	239.88
9	03/28/88	12:00 PM	239.88
9	03/29/88	12:00 PM	239.88
9	03/30/88	12:00 PM	239.86
9	03/31/88	12:00 PM	239.86
9	04/01/88	12:00 PM	239.86
9	04/02/88	12:00 PM	239.93
9	04/03/88	12:00 PM	239.92

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
9	04/04/88	10:00 AM	239.96
9	04/04/88	12:00 PM	239.95
9	04/05/88	12:00 PM	239.94
9	04/06/88	12:00 PM	239.99
9	04/07/88	12:00 PM	240.03
9	04/08/88	12:00 PM	240.00
9	04/09/88	12:00 PM	239.98
9	04/10/88	12:00 PM	239.98
9	04/11/88	12:00 PM	239.98
9	04/12/88	12:00 PM	239.96
9	04/13/88	12:00 PM	239.95
9	04/14/88	12:00 PM	239.93
9	04/15/88	12:00 PM	239.91
9	04/16/88	12:00 PM	239.93
9	04/17/88	12:00 PM	239.93
9	04/18/88	12:00 PM	240.00
9	04/19/88	12:00 PM	240.06
9	04/20/88	12:00 PM	240.06
9	04/21/88	12:00 PM	240.06
9	04/22/88	12:00 PM	240.04
9	04/23/88	12:00 PM	240.01
9	04/24/88	12:00 PM	239.99
9	04/25/88	12:00 PM	239.98
9	04/26/88	12:00 PM	239.96
9	04/27/88	12:00 PM	239.94
9	04/28/88	12:00 PM	239.91
9	04/29/88	12:00 PM	239.91
9	04/30/88	12:00 PM	239.89
9	05/01/88	12:00 PM	239.88
9	05/02/88	12:00 PM	239.87
9	05/03/88	10:00 AM	239.90
9	05/03/88	12:00 PM	239.86
9	05/04/88	12:00 PM	239.94
9	05/05/88	12:00 PM	239.96
9	05/06/88	12:00 PM	239.94
9	05/07/88	12:00 PM	239.91
9	05/08/88	12:00 PM	239.88
9	05/09/88	12:00 PM	239.92
9	05/10/88	12:00 PM	239.95
9	05/11/88	12:00 PM	239.92
9	05/12/88	10:00 AM	239.91
9	05/12/88	12:00 PM	239.89
9	05/13/88	12:00 PM	239.87
9	05/14/88	12:00 PM	239.85
9	05/15/88	12:00 PM	239.84
9	05/16/88	12:00 PM	239.82

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
9	05/17/88	12:00 PM	239.81
9	05/18/88	12:00 PM	239.79
9	05/19/88	12:00 PM	239.78
9	05/20/88	12:00 PM	239.76
9	05/20/88	01:30 PM	239.85
9	05/21/88	12:00 PM	239.74
9	05/22/88	12:00 PM	239.73
9	05/23/88	12:00 PM	239.73
9	05/24/88	12:00 PM	239.74
9	05/25/88	12:00 PM	239.84
9	05/26/88	12:00 PM	239.85
9	05/26/88	02:15 PM	239.88
9	05/27/88	12:00 PM	239.84
9	05/28/88	12:00 PM	239.82
9	05/29/88	12:00 PM	239.79
9	05/30/88	12:00 PM	239.75
9	05/31/88	12:00 PM	239.72
9	06/01/88	12:00 PM	239.70
9	06/02/88	09:30 AM	239.72
9	06/02/88	12 00 PM	239.68
9	06/03/88	12:00 PM	239.66
9	06/04/88	12:00 PM	239.62
9	06/05/88	12:00 PM	239.60
9	06/06/88	12:00 PM	239.59
9	06/07/88	12:00 PM	239.58
9	06/08/88	12:00 PM	239.57
9	06/09/88	10:30 AM	239.58
9	06/09/88	12:00 PM	239.55
9	06/10/88	12:00 PM	239.57
9	06/11/88	12:00 PM	239.57
9	06/12/88	12:00 PM	239.56
9	06/13/88	12:00 PM	239.54
9	06/14/88	12:00 PM	239.52
9	06/15/88	12:00 PM	239.50
9	06/16/88	12:00 PM	239.49
9	06/17/88	12:00 PM	239.48
9	06/18/88	12:00 PM	239.45
9	06/19/88	12:00 PM	239.43
9	06/20/88	12:00 PM	239.42
9	06/21/88	12:00 PM	239.43
9	06/21/88	12:00 PM	239.42
9	07/01/88	12:00 PM	239.48
9	07/09/88	12:00 PM	239.36
9	07/10/88	12:00 PM	239.34
9	07/11/88	12:00 PM	239.32
9	07/12/88	12:00 PM	239.59

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
9	07/13/88	12:00 PM	239.71
9	07/14/88	12:00 PM	239.88
9	07/15/88	12:00 PM	239.85
9	07/16/88	12:00 PM	239.79
9	07/17/88	12:00 PM	239.74
9	07/18/88	12:00 PM	239.70
9	07/19/88	12:00 PM	239.66
9	07/20/88	12:00 PM	239.62
9	07/21/88	12:00 PM	239.63
9	07/22/88	12:00 PM	239.85
9	07/23/88	12:00 PM	239.83
9	07/24/88	12:00 PM	239.78
9	07/25/88	12:00 PM	239.74
9	07/26/88	12:00 PM	239.70
9	07/26/88	12:00 PM	239.72
9	07/27/88	12:00 PM	239.92
9	07/28/88	12:00 PM	239.89
9	07/29/88	12:00 PM	239.85
9	07/30/88	12:00 PM	239.80
9	07/31/88	12:00 PM	239.76
9	08/01/88	12:00 PM	239.72
9	08/02/88	12:00 PM	239.68
9	08/23/88	12:00 PM	239.48

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
10	05/21/87	03:13 PM	242.04
10	06/15/87	01:30 PM	241.88
10	07/13/87	12:00 PM	241.90
10	07/31/87	09:14 AM	242.12
10	08/03/87	09:53 AM	242.23
10	08/04/87	10:08 AM	242.17
10	08/04/87	02:28 PM	242.18
10	08/05/87	07:50 AM	242.15
10	08/05/87	03:23 PM	242.15
10	08/06/87	10:21 AM	242.13
10	08/07/87	09:29 AM	242.15
10	08/10/87	09:42 AM	242.25
10	08/12/87	10:15 AM	242.26
10	08/14/87	08:14 AM	242.24
10	08/17/87	07:02 AM	242.16
10	08/21/87	03:36 PM	242.05
10	09/04/87	08:49 AM	241.67
10	09/11/87	01:30 PM	241.58
10	09/18/87	01:30 PM	241.72
10	09/25/87	01:30 PM	241.62
10	10/01/87	01:30 PM	241.65
10	10/08/87	01:30 PM	241.54
10	10/15/87	01:30 PM	241.46
10	10/19/87	02:38 PM	241.43
10	10/20/87	09:29 AM	241.42
10	10/21/87	09:32 AM	241.42
10	10/22/87	09:54 AM	241.43
10	10/23/87	09:31 AM	241.45
10	10/26/87	09:54 AM	241.78
10	10/27/87	09:25 AM	241.84
10	10/28/87	09:32 AM	241.87
10	10/29/87	09:40 AM	241.93
10	10/30/87	09:58 AM	242.09
10	11/02/87	01:52 PM	242.33
10	11/04/87	10:00 AM	242.29
10	11/05/87	01:30 PM	242.24
10	11/10/87	01:30 PM	242.11
10	11/12/87	01:00 PM	242.05
10	11/17/87	08:15 AM	241.92
10	11/19/87	04:30 PM	241.71
10	12/03/87	01:30 PM	241.63
10	12/11/87	01:30 PM	241.54
10	12/16/87	01:30 PM	241.75
10	12/21/87	02:30 PM	241.67
10	12/28/87	10:15 AM	241.98
10	12/31/87	01:00 PM	241.87

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
10	01/04/88	02:00 PM	242.03
10	01/08/88	10:40 AM	241.86
10	01/14/88	08:50 AM	241.83
10	01/21/88	10:00 AM	242.58
10	01/22/88	01:00 PM	242.39
10	01/25/88	10:00 AM	242.20
10	01/28/88	10:00 AM	242.09
10	02/01/88	10:15 AM	242.08
10	02/11/88	10:30 AM	242.22
10	02/18/88	01:50 PM	242.36
10	02/26/88	12:15 PM	242.14
10	03/09/88	08:30 AM	242.04
10	03/16/88	10:00 AM	242.49
10	03/16/88	12:00 PM	242.50
10	03/17/88	12:00 PM	242.42
10	03/18/88	12:00 PM	242.39
10	03/19/88	12:00 PM	242.34
10	03/20/88	12:00 PM	242.30
10	03/21/88	12:00 PM	242.28
10	03/22/88	12:00 PM	242.25
10	03/23/88	12:00 PM	242.23
10	03/24/88	12:00 PM	242.22
10	03/25/88	12:00 PM	242.22
10	03/26/88	12:00 PM	242.23
10	03/27/88	12:00 PM	242.18
10	03/28/88	10:00 AM	242.13
10	03/28/88	12:00 PM	242.15
10	03/29/88	12:00 PM	242.15
10	03/30/88	12:00 PM	242.12
10	03/31/88	12:00 PM	242.11
10	04/01/88	12:00 PM	242.10
10	04/02/88	12:00 PM	242.15
10	04/03/88	12:00 PM	242.15
10	04/04/88	10:00 AM	242.21
10	04/04/88	12:00 PM	242.20
10	04/05/88	12:00 PM	242.26
10	04/06/88	12:00 PM	242.40
10	04/07/88	12:00 PM	242.58
10	04/08/88	12:00 PM	242.47
10	04/09/88	12:00 PM	242.40
10	04/10/88	12:00 PM	242.34
10	04/11/88	12:00 PM	242.29
10	04/12/88	12:00 PM	242.24
10	04/13/88	12:00 PM	242.19
10	04/14/88	12:00 PM	242.16
10	04/15/88	12:00 PM	242.12

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
10	04/16/88	12:00 PM	242.12
10	04/17/88	12:00 PM	242.10
10	04/18/88	12:00 PM	242.30
10	04/19/88	12:00 PM	242.64
10	04/20/88	12:00 PM	242.61
10	04/21/88	12:00 PM	242.51
10	04/22/88	12:00 PM	242.42
10	04/23/88	12:00 PM	242.31
10	04/24/88	12:00 PM	242.25
10	04/25/88	12:00 PM	242.21
10	04/26/88	12:00 PM	242.18
10	04/27/88	12:00 PM	242.13
10	04/28/88	12:00 PM	242.11
10	04/29/88	12:00 PM	242.08
10	04/30/88	12:00 PM	242.06
10	05/01/88	12:00 PM	242.05
10	05/02/88	12:00 PM	242.03
10	05/03/88	10:00 AM	242.02
10	05/03/88	12:00 PM	242.02
10	05/04/88	12:00 PM	242.08
10	05/05/88	12:00 PM	242.08
10	05/06/88	12:00 PM	242.05
10	05/07/88	12:00 PM	242.02
10	05/08/88	12:00 PM	241.99
10	05/09/88	12:00 PM	242.05
10	05/10/88	12:00 PM	242.04
10	05/11/88	12:00 PM	242.01
10	05/12/88	10:00 AM	241.97
10	05/12/88	12:00 PM	241.98
10	05/13/88	12:00 PM	241.96
10	05/14/88	12:00 PM	241.94
10	05/15/88	12:00 PM	241.93
10	05/16/88	12:00 PM	241.92
10	05/17/88	12:00 PM	241.91
10	05/18/88	12:00 PM	241.91
10	05/19/88	12:00 PM	241.89
10	05/20/88	12:00 PM	241.87
10	05/20/88	01:30 PM	241.88
10	05/21/88	12:00 PM	241.86
10	05/22/88	12:00 PM	241.86
10	05/23/88	12:00 PM	241.85
10	05/24/88	12:00 PM	241.86
10	05/25/88	12:00 PM	241.97
10	05/26/88	12:00 PM	241.94
10	05/26/88	02:15 PM	241.94
10	05/27/88	12:00 PM	241.92

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
10	05/28/88	12:00 PM	241.89
10	05/29/88	12:00 PM	241.87
10	05/30/88	12:00 PM	241.84
10	05/31/88	12:00 PM	241.82
10	06/01/88	12:00 PM	241.81
10	06/02/88	09:30 AM	241.79
10	06/02/88	12:00 PM	241.80
10	06/03/88	12:00 PM	241.79
10	06/04/88	12:00 PM	241.76
10	06/05/88	12:00 PM	241.74
10	06/06/88	12:00 PM	241.73
10	06/07/88	12:00 PM	241.73
10	06/08/88	12:00 PM	241.72
10	06/09/88	10:30 AM	241.69
10	06/09/88	12:00 PM	241.70
10	06/10/88	12:00 PM	241.73
10	06/11/88	12:00 PM	241.74
10	06/12/88	12:00 PM	241.73
10	06/13/88	12:00 PM	241.70
10	06/14/88	12:00 PM	241.69
10	06/15/88	12:00 PM	241.67
10	06/16/88	12:00 PM	241.66
10	06/17/88	12:00 PM	241.64
10	06/18/88	12:00 PM	241.62
10	06/19/88	12:00 PM	241.60
10	06/20/88	12:00 PM	241.59
10	06/21/88	12:00 PM	241.56
10	06/21/88	12:00 PM	241.58
10	06/22/88	12:00 PM	241.57
10	06/23/88	12:00 PM	241.56
10	06/24/88	12:00 PM	241.55
10	06/25/88	12:00 PM	241.53
10	06/26/88	12:00 PM	241.66
10	06/27/88	12:00 PM	241.68
10	06/28/88	12:00 PM	241.67
10	06/29/88	12:00 PM	241.65
10	06/30/88	12:00 PM	241.63
10	07/01/88	12:00 PM	241.61
10	07/01/88	12:00 PM	241.6
10	07/02/88	12:00 PM	241.60
10	07/03/88	12:00 PM	241.58
10	07/04/88	12:00 PM	241.57
10	07/05/88	12:00 PM	241.56
10	07/06/88	12:00 PM	241.55
10	07/07/88	12:00 PM	241.53
10	07/08/88	12:00 PM	241.51

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
10	07/09/88	12:00 PM	241.49
10	07/10/88	12:00 PM	241.47
10	07/11/88	12:00 PM	241.45
10	07/12/88	12:00 PM	241.65
10	07/13/88	12:00 PM	241.74
10	07/14/88	12:00 PM	241.96
10	07/15/88	12:00 PM	241.90
10	07/16/88	12:00 PM	241.84
10	07/17/88	12:00 PM	241.80
10	07/18/88	12:00 PM	241.78
10	07/19/88	12:00 PM	241.75
10	07/20/88	12:00 PM	241.73
10	07/21/88	12:00 PM	241.73
10	07/22/88	12:00 PM	241.90
10	07/23/88	12:00 PM	241.87
10	07/24/88	12:00 PM	241.83
10	07/25/88	12:00 PM	241.81
10	07/26/88	12:00 PM	241.76
10	07/26/88	12:00 PM	241.78
10	07/27/88	12:00 PM	241.96
10	07/28/88	12:00 PM	241.91
10	07/29/88	12:00 PM	241.87
10	07/30/88	12:00 PM	241.84
10	07/31/88	12:00 PM	241.81
10	08/01/88	12:00 PM	241.78
10	08/02/88	12:00 PM	241.76
10	08/03/88	12:00 PM	241.73
10	08/04/88	12:00 PM	241.72
10	08/05/88	12:00 PM	241.70
10	08/06/88	12:00 PM	241.69
10	08/07/88	12:00 PM	241.70
10	08/08/88	12:00 PM	241.69
10	08/09/88	12:00 PM	241.67
10	08/10/88	12:00 PM	241.65
10	08/11/88	12:00 PM	241.63
10	08/12/88	12:00 PM	241.67
10	08/13/88	12:00 PM	241.67
10	08/14/88	12:00 PM	241.66
10	08/15/88	12:00 PM	241.64
10	08/16/88	12:00 PM	241.62
10	08/17/88	12:00 PM	241.60
10	08/18/88	12:00 PM	241.58
10	08/19/88	12:00 PM	241.56
10	08/20/88	12:00 PM	241.58
10	08/21/88	12:00 PM	241.65
10	08/22/88	12:00 PM	241.65

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
10	08/23/88	12:00 PM	241.61

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
11	05/22/87	01:01 PM	238.02
11	06/15/87	01:30 PM	237.83
11	07/13/87	12:00 PM	237.77
11	07/31/87	09:03 AM	241.06
11	08/03/87	09:12 AM	241.10
11	08/04/87	08:53 AM	240.83
11	08/05/87	07:35 AM	240.55
11	08/05/87	03:05 PM	240.47
11	08/06/87	08:59 AM	240.24
11	08/07/87	09:15 AM	240.00
11	08/10/87	09:19 AM	239.47
11	08/11/87	03:37 PM	239.30
11	08/12/87	10:00 AM	239.21
11	08/14/87	07:58 AM	238.98
11	08/17/87	07:33 AM	238.71
11	08/21/87	03:34 PM	238.41
11	09/04/87	08:28 AM	237.90
11	09/11/87	01:30 PM	237.80
11	09/18/87	01:30 PM	237.92
11	09/25/87	01:30 PM	237.71
11	10/01/87	01:30 PM	237.69
11	10/08/87	01:30 PM	237.63
11	10/15/87	01:30 PM	237.65
11	10/19/87	02:09 PM	237.65
11	10/20/87	09:03 AM	237.65
11	10/21/87	09:06 AM	237.65
11	10/22/87	09:30 AM	237.92
11	10/23/87	09:16 AM	238.24
11	10/26/87	09:10 AM	239.52
11	10/27/87	08:57 AM	239.66
11	10/28/87	09:01 AM	239.79
11	10/29/87	09:22 AM	240.13
11	10/30/87	09:41 AM	240.64
11	11/02/87	02:48 PM	241.01
11	11/04/87	09:40 AM	240.90
11	11/05/87	01:30 PM	240.75
11	11/10/87	01:30 PM	239.99
11	11/12/87	01:00 PM	239.68
11	11/17/87	08:15 AM	239.12
11	11/18/87	02:03 PM	238.89
11	12/03/87	01:30 PM	238.20
11	12/11/87	01:30 PM	238.00
11	12/16/87	01:30 PM	237.92
11	12/21/87	02:30 PM	237.82
11	12/28/87	10:15 AM	237.91
11	12/31/87	01:00 PM	237.75

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
11	01/04/88	02:00 PM	237.73
11	01/08/88	10:40 AM	237.73
11	01/14/88	08:50 AM	237.76
11	01/21/88	10:00 AM	238.00
11	01/22/88	01:00 PM	238.27
11	01/25/88	10:00 AM	238.21
11	01/28/88	10:00 AM	238.55
11	02/01/88	10:15 AM	238.51
11	02/11/88	10:30 AM	238.34
11	02/18/88	01:50 PM	238.29
11	02/26/88	12:15 PM	238.25
11	03/03/88	10:00 AM	238.07
11	03/09/88	08:30 AM	238.02
11	03/16/88	11:45 AM	238.18
11	03/16/88	12:00 PM	238.15
11	03/17/88	12:00 PM	238.18
11	03/18/88	12:00 PM	238.22
11	03/19/88	12:00 PM	238.24
11	03/20/88	12:00 PM	238.25
11	03/21/88	12:00 PM	238.26
11	03/22/88	12:00 PM	238.25
11	03/23/88	12:00 PM	238.24
11	03/24/88	12:00 PM	238.23
11	03/25/88	12:00 PM	238.23
11	03/26/88	12:00 PM	238.23
11	03/27/88	12:00 PM	238.19
11	03/28/88	10:00 AM	238.19
11	03/28/88	12:00 PM	238.17
11	03/29/88	12:00 PM	238.15
11	03/30/88	12:00 PM	238.13
11	03/31/88	12:00 PM	238.11
11	04/01/88	12:00 PM	238.09
11	04/02/88	12:00 PM	238.07
11	04/03/88	12:00 PM	238.07
11	04/04/88	10:00 AM	238.08
11	04/04/88	12:00 PM	238.05
11	04/05/88	12:00 PM	238.03
11	04/06/88	12:00 PM	238.02
11	04/07/88	12:00 PM	238.02
11	04/08/88	12:00 PM	237.99
11	04/09/88	12:00 PM	237.98
11	04/10/88	12:00 PM	237.97
11	04/11/88	12:00 PM	237.98
11	04/12/88	12:00 PM	237.95
11	04/13/88	12:00 PM	237.93
11	04/14/88	12:00 PM	237.91

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
11	04/15/88	12:00 PM	237.89
11	04/16/88	12:00 PM	237.87
11	04/17/88	12:00 PM	237.87
11	04/18/88	12:00 PM	237.88
11	04/19/88	12:00 PM	237.87
11	04/20/88	12:00 PM	237.87
11	04/21/88	12:00 PM	237.87
11	04/22/88	12:00 PM	237.88
11	04/23/88	12:00 PM	237.86
11	04/24/88	12:00 PM	237.85
11	04/25/88	12:00 PM	237.85
11	04/26/88	12:00 PM	237.84
11	04/27/88	12:00 PM	237.83
11	04/28/88	12:00 PM	237.82
11	04/29/88	12:00 PM	237.81
11	04/30/88	12:00 PM	237.80
11	05/01/88	12:00 PM	237.80
11	05/02/88	12:00 PM	237.79
11	05/03/88	10:00 AM	237.83
11	05/03/88	12:00 PM	237.79
11	05/04/88	12:00 PM	237.80
11	05/05/88	12:00 PM	237.79
11	05/06/88	12:00 PM	237.79
11	05/07/88	12:00 PM	237.78
11	05/08/88	12:00 PM	237.78
11	05/09/88	12:00 PM	237.78
11	05/10/88	12:00 PM	237.77
11	05/11/88	12:00 PM	237.77
11	05/12/88	10:00 AM	237.80
11	05/12/88	12:00 PM	237.76
11	05/13/88	12:00 PM	237.76
11	05/14/88	12:00 PM	237.75
11	05/15/88	12:00 PM	237.75
11	05/16/88	12:00 PM	237.75
11	05/17/88	12:00 PM	237.75
11	05/18/88	12:00 PM	237.76
11	05/19/88	12:00 PM	237.74
11	05/20/88	12:00 PM	237.74
11	05/20/88	01:30 PM	237.78
11	05/21/88	12:00 PM	237.74
11	05/22/88	12:00 PM	237.74
11	05/23/88	12:00 PM	237.73
11	05/24/88	12:00 PM	237.73
11	05/25/88	12:00 PM	237.72
11	05/26/88	12:00 PM	237.71
11	05/26/88	02:15 PM	237.75

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
11	05/27/88	12:00 PM	237.71
11	05/28/88	12:00 PM	237.71
11	05/29/88	12:00 PM	237.71
11	05/30/88	12:00 PM	237.70
11	05/31/88	12:00 PM	237.70
11	06/01/88	12:00 PM	237.70
11	06/02/88	09:30 AM	237.73
11	06/02/88	12:00 PM	237.70
11	06/03/88	12:00 PM	237.70
11	06/04/88	12:00 PM	237.69
11	06/05/88	12:00 PM	237.69
11	06/06/88	12:00 PM	237.69
11	06/07/88	12:00 PM	237.69
11	06/08/88	12:00 PM	237.69
11	06/09/88	10:30 AM	237.65
11	06/09/88	12:00 PM	237.69
11	06/10/88	12:00 PM	237.67
11	06/11/88	12:00 PM	237.67
11	06/12/88	12:00 PM	237.67
11	06/13/88	12:00 PM	237.67
11	06/14/88	12:00 PM	237.66
11	06/15/88	12:00 PM	237.66
11	06/16/88	12:00 PM	237.66
11	06/17/88	12:00 PM	237.66
11	06/18/88	12:00 PM	237.66
11	06/19/88	12:00 PM	237.65
11	06/20/88	12:00 PM	237.65
11	06/21/88	12:00 PM	237.68
11	06/21/88	12:00 PM	237.65
11	06/22/88	12:00 PM	237.65
11	06/23/88	12:00 PM	237.65
11	06/24/88	12:00 PM	237.64
11	06/25/88	12:00 PM	237.64
11	06/26/88	12:00 PM	237.64
11	06/27/88	12:00 PM	237.64
11	06/28/88	12:00 PM	237.64
11	06/29/88	12:00 PM	237.64
11	06/30/88	12:00 PM	237.64
11	07/01/88	12:00 PM	237.66
11	07/01/88	12:00 PM	237.63
11	07/02/88	12:00 PM	237.63
11	07/03/88	12:00 PM	237.63
11	07/04/88	12:00 PM	237.63
11	07/05/88	12:00 PM	237.63
11	07/06/88	12:00 PM	237.63
11	07/07/88	12:00 PM	237.63

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
11	07/08/88	12:00 PM	237.63
11	07/09/88	12:00 PM	237.63
11	07/10/88	12:00 PM	237.62
11	07/11/88	12:00 PM	237.62
11	07/12/88	12:00 PM	237.62
11	07/13/88	12:00 PM	237.62
11	07/14/88	12:00 PM	237.62
11	07/15/88	12:00 PM	237.62
11	07/16/88	12:00 PM	237.62
11	07/17/88	12:00 PM	237.62
11	07/18/88	12:00 PM	237.62
11	07/19/88	12:00 PM	237.62
11	07/20/88	12:00 PM	237.63
11	07/21/88	12:00 PM	237.63
11	07/22/88	12:00 PM	237.63
11	07/23/88	12:00 PM	237.64
11	07/24/88	12:00 PM	237.64
11	07/25/88	12:00 PM	237.65
11	07/26/88	12:00 PM	237.65
11	07/26/88	12:00 PM	237.68
11	07/27/88	12:00 PM	237.65
11	07/28/88	12:00 PM	237.65
11	07/29/88	12:00 PM	237.65
11	07/30/88	12:00 PM	237.66
11	07/31/88	12:00 PM	237.66
11	08/01/88	12:00 PM	237.66
11	08/02/88	12:00 PM	237.66
11	08/03/88	12:00 PM	237.66
11	08/04/88	12:00 PM	237.66
11	08/05/88	12:00 PM	237.66
11	08/06/88	12:00 PM	237.67
11	08/07/88	12:00 PM	237.67
11	08/08/88	12:00 PM	237.67
11	08/09/88	12:00 PM	237.67
11	08/10/88	12:00 PM	237.67
11	08/11/88	12:00 PM	237.68
11	08/12/88	12:00 PM	237.68
11	08/13/88	12:00 PM	237.68
11	08/14/88	12:00 PM	237.69
11	08/15/88	12:00 PM	237.69
11	08/16/88	12:00 PM	237.69
11	08/17/88	12:00 PM	237.69
11	08/18/88	12:00 PM	237.70
11	08/19/88	12:00 PM	237.70
11	08/20/88	12:00 PM	237.70
11	08/21/88	12:00 PM	237.70

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
11	08/22/88	12:00 PM	237.70
11	08/23/88	12:00 PM	237.72

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
12	05/22/87	08:50 AM	235.60
12	06/15/87	01:30 PM	235.34
12	07/13/87	12:00 PM	235.20
12	08/04/87	08:55 AM	236.22
12	08/04/87	01:43 PM	236.22
12	08/05/87	07:36 AM	236.20
12	08/05/87	03:06 PM	236.23
12	08/06/87	09:01 AM	236.23
12	08/07/87	09:16 AM	236.32
12	08/10/87	09:20 AM	236.52
12	08/11/87	03:38 PM	236.54
12	08/12/87	10:02 AM	236.51
12	08/14/87	08:00 AM	236.46
12	08/17/87	07:35 AM	236.35
12	08/21/87	03:25 PM	236.14
12	09/04/87	08:30 AM	235.46
12	09/11/87	01:30 PM	235.24
12	09/18/87	01:30 PM	235.15
12	09/25/87	01:30 PM	235.03
12	10/01/87	01:30 PM	234.94
12	10/08/87	01:30 PM	234.90
12	10/15/87	01:30 PM	234.83
12	10/19/87	02:11 PM	234.78
12	10/20/87	09:05 AM	234.77
12	10/21/87	09:21 AM	234.78
12	10/22/87	09:38 AM	234.83
12	10/23/87	09:17 AM	234.92
12	10/26/87	09:43 AM	235.48
12	10/27/87	09:17 AM	235.60
12	10/28/87	09:20 AM	235.66
12	10/29/87	09:28 AM	235.73
12	10/30/87	09:47 AM	235.92
12	11/02/87	02:10 PM	236.31
12	11/04/87	09:43 AM	236.31
12	11/05/87	01:30 PM	236.27
12	11/10/87	01:30 PM	236.07
12	11/12/87	01:00 PM	235.89
12	11/17/87	08:15 AM	235.67
12	11/18/87	02:54 PM	235.57
12	12/03/87	01:30 PM	235.06
12	12/11/87	01:30 PM	234.89
12	12/16/87	01:30 PM	234.86
12	12/21/87	02:30 PM	234.82
12	12/28/87	10:15 AM	235.10
12	12/31/87	01:00 PM	235.00
12	01/04/88	02:00 PM	235.13

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
12	01/08/88	10:40 AM	234.97
12	01/14/88	08:50 AM	234.93
12	01/21/88	10:00 AM	235.61
12	01/22/88	01:00 PM	235.50
12	01/25/88	10:00 AM	235.51
12	01/28/88	10:00 AM	235.50
12	02/01/88	10:15 AM	235.46
12	02/11/88	10:30 AM	235.67
12	02/18/88	01:50 PM	235.69
12	02/26/88	12:15 PM	235.52
12	03/03/88	09:50 AM	235.42
12	03/09/88	08:30 AM	235.38
12	03/16/88	11:45 AM	235.89
12	03/16/88	12:00 PM	235.86
12	03/17/88	12:00 PM	235.84
12	03/18/88	12:00 PM	235.85
12	03/19/88	12:00 PM	235.81
12	03/20/88	12:00 PM	235.80
12	03/21/88	12:00 PM	235.79
12	03/22/88	12:00 PM	235.75
12	03/23/88	12:00 PM	235.75
12	03/24/88	12:00 PM	235.73
12	03/25/88	12:00 PM	235.73
12	03/26/88	12:00 PM	235.77
12	03/27/88	12:00 PM	235.68
12	03/28/88	10:00 AM	235.68
12	03/28/88	12:00 PM	235.67
12	03/29/88	12:00 PM	235.66
12	03/30/88	12:00 PM	235.60
12	03/31/88	12:00 PM	235.59
12	04/01/88	12:00 PM	235.56
12	04/02/88	12:00 PM	235.60
12	04/03/88	12:00 PM	235.59
12	04/04/88	10:00 AM	235.65
12	04/04/88	12:00 PM	235.61
12	04/05/88	12:00 PM	235.57
12	04/06/88	12:00 PM	235.72
12	04/07/88	12:00 PM	235.80
12	04/08/88	12:00 PM	235.74
12	04/09/88	12:00 PM	235.73
12	04/10/88	12:00 PM	235.69
12	04/11/88	12:00 PM	235.69
12	04/12/88	12:00 PM	235.63
12	04/13/88	12:00 PM	235.60
12	04/14/88	12:00 PM	235.58
12	04/15/88	12:00 PM	235.53

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
12	04/16/88	12:00 PM	235.52
12	04/17/88	12:00 PM	235.51
12	04/18/88	12:00 PM	235.62
12	04/19/88	12:00 PM	235.81
12	04/20/88	12:00 PM	235.82
12	04/21/88	12:00 PM	235.80
12	04/22/88	12:00 PM	235.76
12	04/23/88	12:00 PM	235.71
12	04/24/88	12:00 PM	235.66
12	04/25/88	12:00 PM	235.65
12	04/26/88	12:00 PM	235.59
12	04/27/88	12:00 PM	235.55
12	04/28/88	12:00 PM	235.51
12	04/29/88	12:00 PM	235.48
12	04/30/88	12:00 PM	235.46
12	05/01/88	12:00 PM	235.44
12	05/02/88	12:00 PM	235.43
12	05/03/88	10:00 AM	235.46
12	05/03/88	12:00 PM	235.39
12	05/04/88	12:00 PM	235.45
12	05/05/88	12:00 PM	235.43
12	05/06/88	12:00 PM	235.39
12	05/07/88	12:00 PM	235.34
12	05/08/88	12:00 PM	235.34
12	05/09/88	12:00 PM	235.36
12	05/10/88	12:00 PM	235.33
12	05/11/88	12:00 PM	235.36
12	05/12/88	10:00 AM	235.34
12	05/12/88	12:00 PM	235.28
12	05/13/88	12:00 PM	235.27
12	05/14/88	12:00 PM	235.27
12	05/15/88	12:00 PM	235.24
12	05/16/88	12:00 PM	235.22
12	05/17/88	12:00 PM	235.21
12	05/18/88	12:00 PM	235.26
12	05/19/88	12:00 PM	235.22
12	05/20/88	12:00 PM	235.18
12	05/20/88	01:30 PM	235.22
12	05/21/88	12:00 PM	235.15
12	05/22/88	12:00 PM	235.14
12	05/23/88	12:00 PM	235.13
12	05/24/88	12:00 PM	235.14
12	05/25/88	12:00 PM	235.19
12	05/26/88	12:00 PM	235.16
12	05/26/88	02:15 PM	235.20
12	05/27/88	12:00 PM	235.13

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
12	05/28/88	12:00 PM	235.11
12	05/29/88	12:00 PM	235.10
12	05/30/88	12:00 PM	235.08
12	05/31/88	12:00 PM	235.07
12	06/01/88	12:00 PM	235.07
12	06/02/88	09:30 AM	235.11
12	06/02/88	12:00 PM	235.06
12	06/03/88	12:00 PM	235.05
12	06/04/88	12:00 PM	235.03
12	06/05/88	12:00 PM	235.02
12	06/06/88	12:00 PM	235.02
12	06/07/88	12:00 PM	235.01
12	06/08/88	12:00 PM	235.00
12	06/09/88	10:30 AM	235.05
12	06/09/88	12:00 PM	235.00
12	06/10/88	12:00 PM	234.99
12	06/11/88	12:00 PM	234.98
12	06/12/88	12:00 PM	234.98
12	06/13/88	12:00 PM	234.97
12	06/14/88	12:00 PM	234.96
12	06/15/88	12:00 PM	234.94
12	06/16/88	12:00 PM	234.93
12	06/17/88	12:00 PM	234.92
12	06/18/88	12:00 PM	234.91
12	06/19/88	12:00 PM	234.89
12	06/20/88	12:00 PM	234.88
12	06/21/88	12:00 PM	234.94
12	06/21/88	12:00 PM	234.90
12	06/22/88	12:00 PM	234.89
12	06/23/88	12:00 PM	234.88
12	06/24/88	12:00 PM	234.86
12	06/25/88	12:00 PM	234.86
12	06/26/88	12:00 PM	234.94
12	06/27/88	12:00 PM	234.90
12	06/28/88	12:00 PM	234.87
12	06/29/88	12:00 PM	234.86
12	06/30/88	12:00 PM	234.85
12	07/01/88	12:00 PM	234.85
12	07/01/88	12:00 PM	234.88
12	07/02/88	12:00 PM	234.84
12	07/03/88	12:00 PM	234.84
12	07/04/88	12:00 PM	234.84
12	07/05/88	12:00 PM	234.81
12	07/06/88	12:00 PM	234.80
12	07/07/88	12:00 PM	234.80
12	07/08/88	12:00 PM	234.79

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
12	07/09/88	12:00 PM	234.79
12	07/10/88	12:00 PM	234.76
12	07/11/88	12:00 PM	234.73
12	07/12/88	12:00 PM	234.89
12	07/13/88	12:00 PM	234.90
12	07/14/88	12:00 PM	235.06
12	07/15/88	12:00 PM	235.01
12	07/16/88	12:00 PM	234.91
12	07/17/88	12:00 PM	234.89
12	07/18/88	12:00 PM	234.87
12	07/19/88	12:00 PM	234.88
12	07/20/88	12:00 PM	234.89
12	07/21/88	12:00 PM	234.89
12	07/22/88	12:00 PM	234.98
12	07/23/88	12:00 PM	234.94
12	07/24/88	12:00 PM	234.86
12	07/25/88	12:00 PM	234.87
12	07/26/88	12:00 PM	234.85
12	07/26/88	12:00 PM	234.88
12	07/27/88	12:00 PM	235.02
12	07/28/88	12:00 PM	234.95
12	07/29/88	12:00 PM	234.91
12	07/30/88	12:00 PM	234.90
12	07/31/88	12:00 PM	234.89
12	08/01/88	12:00 PM	234.87
12	08/02/88	12:00 PM	234.86
12	08/03/88	12:00 PM	234.85
12	08/04/88	12:00 PM	234.83
12	08/05/88	12:00 PM	234.84
12	08/06/88	12:00 PM	234.84
12	08/07/88	12:00 PM	234.84
12	08/08/88	12:00 PM	234.83
12	08/09/88	12:00 PM	234.82
12	08/10/88	12:00 PM	234.79
12	08/11/88	12:00 PM	234.79
12	08/12/88	12:00 PM	234.86
12	08/13/88	12:00 PM	234.82
12	08/14/88	12:00 PM	234.80
12	08/15/88	12:00 PM	234.79
12	08/16/88	12:00 PM	234.78
12	08/17/88	12:00 PM	234.75
12	08/18/88	12:00 PM	234.75
12	08/19/88	12:00 PM	234.75
12	08/20/88	12:00 PM	234.80
12	08/21/88	12:00 PM	234.82
12	08/22/88	12:00 PM	234.79

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
12	08/23/88	12:00 PM	234.79

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
13	05/21/87	09:20 AM	238.75
13	06/15/87	01:30 PM	237.62
13	07/13/87	12:00 PM	237.96
13	07/31/87	09:09 AM	237.74
13	08/03/87	09:50 AM	237.70
13	08/04/87	10:04 AM	237.67
13	08/04/87	02:25 PM	237.67
13	08/05/87	07:46 AM	237.62
13	08/05/87	03:20 PM	237.62
13	08/06/87	10:19 AM	237.54
13	08/07/87	09:25 AM	237.49
13	08/10/87	09:39 AM	237.45
13	08/12/87	10:11 AM	237.44
13	08/14/87	08:10 AM	237.46
13	08/17/87	06:58 AM	237.43
13	08/21/87	03:33 PM	237.42
13	09/04/87	08:45 AM	237.33
13	09/11/87	01:30 PM	237.31
13	09/18/87	01:30 PM	237.48
13	09/25/87	01:30 PM	237.45
13	10/01/87	01:30 PM	237.48
13	10/08/87	01:30 PM	237.44
13	10/15/87	01:30 PM	237.42
13	10/19/87	02:35 PM	237.43
13	10/20/87	09:24 AM	237.39
13	10/21/87	09:29 AM	237.37
13	10/22/87	09:47 AM	237.35
13	10/23/87	09:27 AM	237.32
13	10/26/87	09:51 AM	237.31
13	10/27/87	09:22 AM	237.29
13	10/28/87	09:28 AM	237.25
13	10/29/87	09:36 AM	237.22
13	10/30/87	09:54 AM	237.18
13	11/02/87	01:45 PM	237.15
13	11/04/87	10:08 AM	237.15
13	11/05/87	01:30 PM	237.14
13	11/10/87	01:30 PM	237.26
13	11/12/87	01:00 PM	237.23
13	11/17/87	08:15 AM	237.31
13	11/19/87	03:45 PM	237.19
13	12/03/87	01:30 PM	237.37
13	12/11/87	01:30 PM	237.38
13	12/16/87	01:30 PM	237.43
13	12/21/87	02:30 PM	237.46
13	12/28/87	10:15 AM	237.90
13	12/31/87	01:00 PM	237.91

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
13	01/04/88	02:00 PM	238.10
13	01/21/88	10:00 AM	239.04
13	01/22/88	01:00 PM	239.05
13	01/25/88	10:00 AM	239.07
13	01/28/88	10:00 AM	239.04
13	02/01/88	10:15 AM	239.06
13	02/11/88	10:30 AM	239.38
13	02/18/88	01:50 PM	239.47
13	02/26/88	12:15 PM	239.51
13	03/03/88	10:00 AM	239.51
13	03/09/88	08:30 AM	239.54
13	03/16/88	10:00 AM	239.24
13	03/17/88	12:00 PM	237.85
13	03/18/88	12:00 PM	237.86
13	03/19/88	12:00 PM	237.83
13	03/20/88	12:00 PM	237.81
13	03/21/88	12:00 PM	237.78
13	03/22/88	12:00 PM	237.76
13	03/23/88	12:00 PM	237.74
13	03/24/88	12:00 PM	237.74
13	03/25/88	12:00 PM	237.75
13	03/26/88	12:00 PM	237.76
13	03/27/88	12:00 PM	237.72
13	03/28/88	10:00 AM	237.71
13	03/28/88	12:00 PM	237.73
13	03/29/88	12:00 PM	237.73
13	03/30/88	12:00 PM	237.71
13	03/31/88	12:00 PM	237.71
13	04/01/88	12:00 PM	237.72
13	04/02/88	12:00 PM	237.75
13	04/03/88	12:00 PM	237.80
13	04/04/88	10:00 AM	237.83
13	04/04/88	12:00 PM	237.84
13	04/05/88	12:00 PM	237.85
13	04/06/88	12:00 PM	237.99
13	04/07/88	12:00 PM	238.06
13	04/08/88	12:00 PM	238.10
13	04/09/88	12:00 PM	238.13
13	04/10/88	12:00 PM	238.14
13	04/11/88	12:00 PM	238.14
13	04/12/88	12:00 PM	238.11
13	04/13/88	12:00 PM	238.10
13	04/14/88	12:00 PM	238.11
13	04/15/88	12:00 PM	238.10
13	04/16/88	12:00 PM	238.11
13	04/17/88	12:00 PM	238.15

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
13	04/18/88	12:00 PM	238.19
13	04/19/88	12:00 PM	238.31
13	04/20/88	12:00 PM	238.40
13	04/21/88	12:00 PM	238.44
13	04/22/88	12:00 PM	238.44
13	04/23/88	12:00 PM	238.43
13	04/24/88	12:00 PM	238.42
13	04/25/88	12:00 PM	238.43
13	04/26/88	12:00 PM	238.42
13	04/27/88	12:00 PM	238.40
13	04/28/88	12:00 PM	238.37
13	04/29/88	12:00 PM	238.37
13	04/30/88	12:00 PM	238.36
13	05/01/88	12:00 PM	238.35
13	05/02/88	12:00 PM	238.35
13	05/03/88	10:00 AM	238.36
13	05/03/88	12:00 PM	238.35
13	05/04/88	12:00 PM	238.36
13	05/05/88	12:00 PM	238.38
13	05/06/88	12:00 PM	238.37
13	05/07/88	12:00 PM	238.35
13	05/08/88	12:00 PM	238.35
13	05/09/88	12:00 PM	238.35
13	05/10/88	12:00 PM	238.38
13	05/11/88	12:00 PM	238.36
13	05/12/88	10:00 AM	238.35
13	05/12/88	12:00 PM	238.35
13	05/13/88	12:00 PM	238.36
13	05/14/88	12:00 PM	238.35
13	05/15/88	12:00 PM	238.35
13	05/16/88	12:00 PM	238.35
13	05/17/88	12:00 PM	238.34
13	05/18/88	12:00 PM	238.34
13	05/19/88	12:00 PM	238.34
13	05/20/88	12:00 PM	238.33
13	05/20/88	01:30 PM	238.24
13	05/21/88	12:00 PM	238.32
13	05/22/88	12:00 PM	238.33
13	05/23/88	12:00 PM	238.32
13	05/24/88	12:00 PM	238.32
13	05/25/88	12:00 PM	238.33
13	05/26/88	12:00 PM	238.32
13	05/26/88	02:15 PM	238.34
13	05/27/88	12:00 PM	238.32
13	05/28/88	12:00 PM	238.32
13	05/29/88	12:00 PM	238.31

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
13	05/30/88	12:00 PM	238.30
13	05/31/88	12:00 PM	238.30
13	06/01/88	12:00 PM	238.31
13	06/02/88	09:30 AM	238.31
13	06/02/88	12:00 PM	238.30
13	06/03/88	12:00 PM	238.29
13	06/04/88	12:00 PM	238.27
13	06/05/88	12:00 PM	238.26
13	06/06/88	12:00 PM	238.27
13	06/07/88	12:00 PM	238.27
13	06/08/88	12:00 PM	238.27
13	06/09/88	10:30 AM	238.26
13	06/09/88	12:00 PM	238.25
13	06/10/88	12:00 PM	238.24
13	06/11/88	12:00 PM	238.24
13	06/12/88	12:00 PM	238.24
13	06/13/88	12:00 PM	238.22
13	06/14/88	12:00 PM	238.22
13	06/15/88	12:00 PM	238.22
13	06/16/88	12:00 PM	238.23
13	06/17/88	12:00 PM	238.22
13	06/18/88	12:00 PM	238.20
13	06/19/88	12:00 PM	238.19
13	06/20/88	12:00 PM	238.19
13	06/21/88	12:00 PM	238.20
13	06/21/88	12:00 PM	238.20
13	06/23/88	12:00 PM	238.18
13	06/24/88	12:00 PM	238.17
13	06/25/88	12:00 PM	238.17
13	07/01/88	12:00 PM	238.17
13	07/26/88	12:00 PM	238.43
13	08/23/88	12:00 PM	238.45

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
367	06/03/87	10:19 AM	240.19
367	06/15/87	01:30 PM	239.80
367	07/13/87	12:00 PM	239.69
367	07/27/87	10:52 AM	239.58
367	07/27/87	01:28 PM	239.58
367	07/27/87	04:02 PM	239.58
367	07/27/87	08:45 PM	239.58
367	07/28/87	06:33 AM	242.29
367	07/28/87	09:51 AM	243.14
367	07/28/87	10:17 AM	243.24
367	07/28/87	11:37 AM	243.55
367	07/28/87	01:12 PM	243.85
367	07/28/87	02:42 PM	244.18
367	07/28/87	02:56 PM	244.25
367	07/29/87	09:10 AM	245.94
367	07/29/87	02:48 PM	246.03
367	07/30/87	09:06 AM	245.97
367	07/30/87	04:19 PM	245.94
367	07/31/87	08:44 AM	245.99
367	08/03/87	08:54 AM	244.37
367	08/04/87	08:48 AM	243.62
367	08/05/87	07:28 AM	243.00
367	08/05/87	03:03 PM	242.82
367	08/06/87	08:53 AM	242.44
367	08/07/87	09:10 AM	242.01
367	08/10/87	09:14 AM	241.25
367	08/12/87	09:54 AM	240.91
367	08/14/87	07:53 AM	240.62
367	08/17/87	07:27 AM	240.28
367	08/21/87	03:20 PM	239.99
367	09/04/87	08:23 AM	239.63
367	09/11/87	01:30 PM	239.49
367	09/18/87	01:30 PM	239.41
367	09/25/87	01:30 PM	239.34
367	10/01/87	01:30 PM	239.29
367	10/08/87	01:30 PM	239.24
367	10/15/87	01:30 PM	239.19
367	10/19/87	02:03 PM	239.17
367	10/20/87	08:51 AM	239.16
367	10/20/87	03:52 PM	239.16
367	10/21/87	09:15 AM	239.32
367	10/22/87	09:22 AM	240.58
367	10/23/87	09:05 AM	241.65
367	10/26/87	09:15 AM	243.64
367	10/28/87	09:06 AM	243.58
367	10/29/87	09:07 AM	245.09

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
367	10/30/87	09:30 AM	245.79
367	11/02/87	02:26 PM	244.60
367	11/04/87	09:27 AM	243.96
367	11/05/87	01:30 PM	243.54
367	11/10/87	01:30 PM	242.06
367	11/12/87	01:00 PM	241.62
367	11/17/87	08:15 AM	240.94
367	11/18/87	01:28 PM	240.68
367	12/03/87	01:30 PM	239.93
367	12/11/87	01:30 PM	239.79
367	12/16/87	01:30 PM	239.69
367	12/21/87	02:30 PM	239.61
367	12/28/87	10:15 AM	239.54
367	12/31/87	01:00 PM	239.51
367	01/04/88	02:00 PM	239.51
367	01/08/88	10:40 AM	239.59
367	01/14/88	08:50 AM	239.77
367	01/21/88	10:00 AM	240.63
367	01/22/88	01:00 PM	241.01
367	01/25/88	10:00 AM	241.33
367	01/28/88	10:00 AM	241.21
367	02/01/88	10:15 AM	240.95
367	02/11/88	10:30 AM	240.68
367	02/18/88	01:50 PM	240.52
367	02/26/88	12:15 PM	240.24
367	03/03/88	10:00 AM	240.17
367	03/09/88	08:30 AM	240.09
367	03/16/88	10:00 AM	240.51
367	03/17/88	12:00 PM	240.44
367	03/18/88	12:00 PM	240.52
367	03/19/88	12:00 PM	240.55
367	03/20/88	12:00 PM	240.57
367	03/21/88	12:00 PM	240.56
367	03/22/88	12:00 PM	240.53
367	03/23/88	12:00 PM	240.51
367	03/24/88	12:00 PM	240.48
367	03/25/88	12:00 PM	240.48
367	03/26/88	12:00 PM	240.44
367	03/27/88	12:00 PM	240.40
367	03/28/88	10:00 AM	240.47
367	03/28/88	12:00 PM	240.34
367	03/29/88	12:00 PM	240.32
367	03/30/88	12:00 PM	240.26
367	03/31/88	12:00 PM	240.23
367	04/01/88	12:00 PM	240.20
367	04/02/88	12:00 PM	240.17

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
367	04/03/88	12:00 PM	240.15
367	04/04/88	10:00 AM	240.24
367	04/04/88	12:00 PM	240.15
367	04/05/88	12:00 PM	240.08
367	04/06/88	12:00 PM	240.10
367	04/07/88	12:00 PM	240.07
367	04/08/88	12:00 PM	240.04
367	04/09/88	12:00 PM	240.02
367	04/10/88	12:00 PM	240.01
367	04/11/88	12:00 PM	240.01
367	04/12/88	12:00 PM	239.98
367	04/13/88	12:00 PM	239.95
367	04/14/88	12:00 PM	239.92
367	04/15/88	12:00 PM	239.91
367	04/16/88	12:00 PM	239.89
367	04/17/88	12:00 PM	239.89
367	04/18/88	12:00 PM	239.89
367	04/19/88	12:00 PM	239.90
367	04/20/88	12:00 PM	239.91
367	04/21/88	12:00 PM	239.93
367	04/22/88	12:00 PM	239.94
367	04/23/88	12:00 PM	239.93
367	04/24/88	12:00 PM	239.91
367	04/25/88	12:00 PM	239.91
367	04/26/88	12:00 PM	239.89
367	04/27/88	12:00 PM	239.89
367	04/28/88	12:00 PM	239.85
367	04/29/88	12:00 PM	239.86
367	04/30/88	12:00 PM	239.85
367	05/01/88	12:00 PM	239.84
367	05/02/88	12:00 PM	239.84
367	05/03/88	10:00 AM	239.96
367	05/03/88	12:00 PM	239.83
367	05/04/88	12:00 PM	239.85
367	05/05/88	12:00 PM	239.84
367	05/06/88	12:00 PM	239.84
367	05/07/88	12:00 PM	239.82
367	05/08/88	12:00 PM	239.81
367	05/09/88	12:00 PM	239.81
367	05/10/88	12:00 PM	239.80
367	05/11/88	12:00 PM	239.83
367	05/12/88	10:00 AM	239.90
367	05/12/88	12:00 PM	239.77
367	05/13/88	12:00 PM	239.77
367	05/14/88	12:00 PM	239.76
367	05/15/88	12:00 PM	239.75

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
367	05/16/88	12:00 PM	239.75
367	05/17/88	12:00 PM	239.74
367	05/18/88	12:00 PM	239.73
367	05/19/88	12:00 PM	239.77
367	05/20/88	12:00 PM	239.72
367	05/20/88	01:30 PM	239.84
367	05/21/88	12:00 PM	239.68
367	05/22/88	12:00 PM	239.68
367	05/23/88	12:00 PM	239.67
367	05/24/88	12:00 PM	239.67
367	05/25/88	12:00 PM	239.65
367	05/26/88	12:00 PM	239.62
367	05/26/88	02:15 PM	239.75
367	05/27/88	12:00 PM	239.62
367	05/28/88	12:00 PM	239.62
367	05/29/88	12:00 PM	239.60
367	05/30/88	12:00 PM	239.59
367	05/31/88	12:00 PM	239.58
367	06/01/88	12:00 PM	239.58
367	06/02/88	09:30 AM	239.71
367	06/02/88	12:00 PM	239.58
367	06/03/88	12:00 PM	239.58
367	06/04/88	12:00 PM	239.55
367	06/05/88	12:00 PM	239.53
367	06/06/88	12:00 PM	239.52
367	06/07/88	12:00 PM	239.52
367	06/08/88	12:00 PM	239.52
367	06/09/88	10:30 AM	239.65
367	06/09/88	12:00 PM	239.52
367	06/10/88	12:00 PM	239.48
367	06/11/88	12:00 PM	239.47
367	06/12/88	12:00 PM	239.46
367	06/13/88	12:00 PM	239.45
367	06/14/88	12:00 PM	239.44
367	06/15/88	12:00 PM	239.44
367	06/16/88	12:00 PM	239.44
367	06/17/88	12:00 PM	239.44
367	06/18/88	12:00 PM	239.42
367	06/19/88	12:00 PM	239.41
367	06/20/88	12:00 PM	239.40
367	06/21/88	12:00 PM	239.40
367	06/21/88	12:00 PM	239.52
367	06/23/88	12:00 PM	239.39
367	06/24/88	12:00 PM	239.38
367	06/25/88	12:00 PM	239.36
367	06/26/88	12:00 PM	239.38

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
367	06/27/88	12:00 PM	239.37
367	06/28/88	12:00 PM	239.37
367	06/29/88	12:00 PM	239.36
367	06/30/88	12:00 PM	239.37
367	07/01/88	12:00 PM	239.49
367	07/01/88	12:00 PM	239.35
367	07/03/88	12:00 PM	239.34
367	07/04/88	12:00 PM	239.33
367	07/05/88	12:00 PM	239.31
367	07/06/88	12:00 PM	239.31
367	07/07/88	12:00 PM	239.31
367	07/09/88	12:00 PM	239.31
367	07/10/88	12:00 PM	239.30
367	07/11/88	12:00 PM	239.27
367	07/12/88	12:00 PM	239.29
367	07/13/88	12:00 PM	239.29
367	07/14/88	12:00 PM	239.28
367	07/15/88	12:00 PM	239.31
367	07/16/88	12:00 PM	239.30
367	07/17/88	12:00 PM	239.31
367	07/18/88	12:00 PM	239.31
367	07/19/88	12:00 PM	239.35
367	07/20/88	12:00 PM	239.37
367	07/21/88	12:00 PM	239.38
367	07/22/88	12:00 PM	239.38
367	07/23/88	12:00 PM	239.41
367	07/24/88	12:00 PM	239.38
367	07/25/88	12:00 PM	239.40
367	07/26/88	12:00 PM	239.34
367	07/26/88	12:00 PM	239.54
367	07/27/88	12:00 PM	239.40
367	07/28/88	12:00 PM	239.40
367	07/29/88	12:00 PM	239.39
367	07/30/88	12:00 PM	239.40
367	07/31/88	12:00 PM	239.41
367	08/01/88	12:00 PM	239.41
367	08/02/88	12:00 PM	239.41
367	08/23/88	12:00 PM	239.59

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
646	06/15/87	01:30 PM	235.40
646	07/13/87	12:00 PM	235.34
646	08/04/87	08:57 AM	235.18
646	08/04/87	01:44 PM	235.18
646	08/05/87	07:37 AM	235.21
646	08/05/87	03:07 PM	235.22
646	08/06/87	09:02 AM	235.29
646	08/07/87	09:17 AM	235.42
646	08/10/87	09:21 AM	235.67
646	08/11/87	03:40 PM	235.69
646	08/12/87	10:03 AM	235.70
646	08/14/87	08:01 AM	235.71
646	08/17/87	07:36 AM	235.68
646	08/21/87	03:26 PM	235.59
646	09/04/87	08:31 AM	235.29
646	10/19/87	02:12 PM	234.86
646	10/20/87	09:08 AM	234.85
646	10/21/87	09:23 AM	234.89
646	10/22/87	09:40 AM	234.86
646	10/23/87	09:19 AM	234.87
646	10/26/87	09:44 AM	234.92
646	10/28/87	09:22 AM	234.98
646	10/29/87	09:30 AM	235.02
646	10/30/87	09:49 AM	235.03
646	11/02/87	02:07 PM	235.15
646	11/04/87	10:37 AM	235.24
646	11/12/87	01:00 PM	235.32
646	11/17/87	08:15 AM	235.26
646	11/19/87	02:36 PM	235.26
646	12/03/87	01:30 PM	234.69
646	12/11/87	01:30 PM	234.63
646	12/16/87	01:30 PM	234.60
646	12/21/87	02:30 PM	234.68
646	12/28/87	10:15 AM	235.18
646	12/31/87	01:00 PM	235.03
646	01/04/88	02:00 PM	235.25
646	01/08/88	10:40 AM	235.11
646	01/14/88	08:50 AM	234.99
646	01/21/88	10:00 AM	235.61
646	01/22/88	01:00 PM	235.54
646	01/25/88	10:00 AM	235.48
646	01/28/88	10:00 AM	235.36
646	02/01/88	10:15 AM	235.31
646	02/11/88	10:30 AM	235.51
646	02/18/88	01:50 PM	235.55
646	02/26/88	12:15 PM	235.44

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
646	03/03/88	09:50 AM	235.38
646	03/04/88	12:00 PM	235.39
646	03/05/88	12:00 PM	235.37
646	03/06/88	12:00 PM	235.36
646	03/07/88	12:00 PM	235.34
646	03/08/88	12:00 PM	235.36
646	03/09/88	08:30 AM	235.35
646	03/09/88	12:00 PM	235.38
646	03/10/88	12:00 PM	235.65
646	03/11/88	12:00 PM	235.74
646	03/12/88	12:00 PM	235.70
646	03/13/88	12:00 PM	235.73
646	03/14/88	12:00 PM	235.76
646	03/15/88	12:00 PM	235.69
646	03/16/88	11:45 AM	235.67
646	03/16/88	12:00 PM	235.65
646	03/17/88	12:00 PM	235.64
646	03/18/88	12:00 PM	235.62
646	03/19/88	12:00 PM	235.60
646	03/20/88	12:00 PM	235.58
646	03/21/88	12:00 PM	235.56
646	03/22/88	12:00 PM	235.54
646	03/23/88	12:00 PM	235.53
646	03/24/88	12:00 PM	235.52
646	03/25/88	12:00 PM	235.61
646	03/26/88	12:00 PM	235.64
646	03/27/88	12:00 PM	235.65
646	03/28/88	10:00 AM	235.66
646	03/28/88	12:00 PM	235.64
646	03/29/88	12:00 PM	235.67
646	03/30/88	12:00 PM	235.64
646	03/31/88	12:00 PM	235.65
646	04/01/88	12:00 PM	235.63
646	04/02/88	12:00 PM	235.71
646	04/03/88	12:00 PM	235.67
646	04/04/88	10:00 AM	235.74
646	04/04/88	12:00 PM	235.75
646	04/05/88	12:00 PM	235.73
646	04/06/88	12:00 PM	235.82
646	04/07/88	12:00 PM	235.89
646	04/08/88	12:00 PM	235.86
646	04/09/88	12:00 PM	235.84
646	04/10/88	12:00 PM	235.86
646	04/11/88	12:00 PM	235.86
646	04/12/88	12:00 PM	235.86
646	04/13/88	12:00 PM	235.85

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
646	04/14/88	12:00 PM	235.83
646	04/15/88	12:00 PM	235.80
646	04/16/88	12:00 PM	235.80
646	04/17/88	12:00 PM	235.79
646	04/18/88	12:00 PM	235.86
646	04/19/88	12:00 PM	235.97
646	04/20/88	12:00 PM	235.99
646	04/21/88	12:00 PM	236.01
646	04/22/88	12:00 PM	235.99
646	04/23/88	12:00 PM	235.96
646	04/24/88	12:00 PM	235.93
646	04/25/88	12:00 PM	235.91
646	04/26/88	12:00 PM	235.89
646	04/27/88	12:00 PM	235.86
646	04/28/88	12:00 PM	235.82
646	04/29/88	12:00 PM	235.81
646	04/30/88	12:00 PM	235.78
646	05/01/88	12:00 PM	235.76
646	05/02/88	12:00 PM	235.74
646	05/03/88	10:00 AM	235.74
646	05/03/88	12:00 PM	235.72
646	05/04/88	12:00 PM	235.76
646	05/05/88	12:00 PM	235.73
646	05/06/88	12:00 PM	235.69
646	05/07/88	12:00 PM	235.67
646	05/08/88	12:00 PM	235.68
646	05/09/88	12:00 PM	235.74
646	05/10/88	12:00 PM	235.74
646	05/11/88	12:00 PM	235.68
646	05/12/88	10:00 AM	235.70
646	05/12/88	12:00 PM	235.64
646	05/13/88	12:00 PM	235.62
646	05/14/88	12:00 PM	235.60
646	05/15/88	12:00 PM	235.58
646	05/16/88	12:00 PM	235.57
646	05/17/88	12:00 PM	235.53
646	05/18/88	12:00 PM	235.51
646	05/19/88	12:00 PM	235.51
646	05/20/88	12:00 PM	235.47
646	05/20/88	01:30 PM	235.49
646	05/21/88	12:00 PM	235.44
646	05/22/88	12:00 PM	235.43
646	05/23/88	12:00 PM	235.41
646	05/24/88	12:00 PM	235.43
646	05/25/88	12:00 PM	235.56
646	05/26/88	12:00 PM	235.38

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
646	05/26/88	02:15 PM	235.40
646	05/27/88	12:00 PM	235.35
646	05/28/88	12:00 PM	235.33
646	05/29/88	12:00 PM	235.32
646	05/30/88	12:00 PM	235.30
646	05/31/88	12:00 PM	235.30
646	06/01/88	12:00 PM	235.29
646	06/02/88	09:30 AM	235.34
646	06/02/88	12:00 PM	235.28
646	06/03/88	12:00 PM	235.27
646	06/04/88	12:00 PM	235.25
646	06/05/88	12:00 PM	235.23
646	06/06/88	12:00 PM	235.22
646	06/07/88	12:00 PM	235.21
646	06/08/88	12:00 PM	235.20
646	06/09/88	10:30 AM	235.24
646	06/09/88	12:00 PM	235.21
646	06/10/88	12:00 PM	235.27
646	06/11/88	12:00 PM	235.21
646	06/12/88	12:00 PM	235.20
646	06/13/88	12:00 PM	235.18
646	06/14/88	12:00 PM	235.15
646	06/15/88	12:00 PM	235.13
646	06/16/88	12:00 PM	235.12
646	06/17/88	12:00 PM	235.11
646	06/18/88	12:00 PM	235.02
646	06/19/88	12:00 PM	235.01
646	06/20/88	12:00 PM	235.02
646	06/21/88	12:00 PM	235.06
646	06/21/88	12:00 PM	235.07
646	06/22/88	12:00 PM	235.05
646	06/23/88	12:00 PM	235.02
646	06/24/88	12:00 PM	235.01
646	06/25/88	12:00 PM	235.02
646	06/26/88	12:00 PM	235.19
646	06/27/88	12:00 PM	235.12
646	06/28/88	12:00 PM	235.09
646	06/29/88	12:00 PM	235.06
646	06/30/88	12:00 PM	235.08
646	07/01/88	12:00 PM	235.07
646	07/01/88	12:00 PM	235.05
646	07/02/88	12:00 PM	235.04
646	07/03/88	12:00 PM	235.04
646	07/04/88	12:00 PM	235.03
646	07/05/88	12:00 PM	235.00
646	07/06/88	12:00 PM	234.98

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
646	07/07/88	12:00 PM	234.96
646	07/08/88	12:00 PM	234.96
646	07/09/88	12:00 PM	234.96
646	07/10/88	12:00 PM	234.94
646	07/11/88	12:00 PM	234.93
646	07/12/88	12:00 PM	235.18
646	07/13/88	12:00 PM	235.17
646	07/14/88	12:00 PM	235.44
646	07/15/88	12:00 PM	235.24
646	07/16/88	12:00 PM	235.18
646	07/17/88	12:00 PM	235.14
646	07/18/88	12:00 PM	235.11
646	07/19/88	12:00 PM	235.10
646	07/20/88	12:00 PM	235.10
646	07/21/88	12:00 PM	235.18
646	07/22/88	12:00 PM	235.37
646	07/23/88	12:00 PM	235.25
646	07/24/88	12:00 PM	235.16
646	07/25/88	12:00 PM	235.14
646	07/26/88	12:00 PM	235.12
646	07/26/88	12:00 PM	235.14
646	07/27/88	12:00 PM	235.48
646	07/28/88	12:00 PM	235.32
646	07/29/88	12:00 PM	235.33
646	07/30/88	12:00 PM	235.29
646	07/31/88	12:00 PM	235.25
646	08/01/88	12:00 PM	235.22
646	08/02/88	12:00 PM	235.20
646	08/03/88	12:00 PM	235.17
646	08/04/88	12:00 PM	235.15
646	08/05/88	12:00 PM	235.15
646	08/06/88	12:00 PM	235.14
646	08/07/88	12:00 PM	235.17
646	08/08/88	12:00 PM	235.13
646	08/09/88	12:00 PM	235.10
646	08/10/88	12:00 PM	235.07
646	08/11/88	12:00 PM	235.05
646	08/12/88	12:00 PM	235.19
646	08/13/88	12:00 PM	235.13
646	08/14/88	12:00 PM	235.09
646	08/15/88	12:00 PM	235.07
646	08/16/88	12:00 PM	235.04
646	08/17/88	12:00 PM	235.03
646	08/18/88	12:00 PM	235.03
646	08/19/88	12:00 PM	235.02
646	08/20/88	12:00 PM	235.18

APPENDIX III

TARA Well	Date	Time	Water Elevation (m)
646	08/21/88	12:00 PM	235.21
646	08/22/88	12:00 PM	235.13
646	08/23/88	12:00 PM	235.12

TARA WELL 1

1987 AND 1988 WATER ELEVATIONS

HYDROGRAPH FOR TARA WELL 1

TARA WELL 2 1987 AND 1988 WATER ELEVATIONS

HYDROGRAPH FOR TARA WELL 2

TARA WELL 3 1987 AND 1988 WATER ELEVATIONS

HYDROGRAPH FOR TARA WELL 3

TARA WELL 4 1987 AND 1988 WATER ELEVATIONS

HYDROGRAPH FOR TARA WELL 4

TARA WELL 5 1987 AND 1988 WATER ELEVATIONS

HYDROGRAPH FOR TARA WELL 5

TARA WELL 5

WATER ELEVATION (m ABOVE MSL)

HYDROGRAPH FOR TARA WELL 6

TARA WELL 7 1987 AND 1988 WATER ELEVATIONS

HYDROGRAPH FOR TARA WELL 7

TARA WELL 8 1987 AND 1988 WATER ELEVATIONS

HYDROGRAPH FOR TARA WELL 8

TARA WELL 9 1987 AND 1988 WATER ELEVATIONS

HYDROGRAPH FOR TARA WELL 9

TARA WELL 10 1987 AND 1988 WATER ELEVATIONS

HYDROGRAPH FOR TARA WELL 10

TARA WELL 11
1987 AND 1988 WATER ELEVATIONS

HYDROGRAPH FOR TARA WELL 11

TARA WELL 12 1987 AND 1988 WATER ELEVATIONS

HYDROGRAPH FOR TARA WELL 12

TARA WELL 13 1987 AND 1988 WATER ELEVATIONS

HYDROGRAPH FOR TARA WELL 13

TARA WELL 367

1987 AND 1988 WATER ELEVATIONS

HYDROGRAPH FOR TARA WELL 367

TARA WELL 646 1987 AND 1988 WATER ELEVATIONS

HYDROGRAPH FOR TARA WELL 646

SWSA 6 PRECIPITATION

Date	TARA Precip. (mm)	SWSA 6 Precip. Gauge 1 (mm)	SWSA 6 Precip. Gauge 2 (mm)	SWSA 6 Average Precip. (mm)
01/01/87		2.78	3.04	2.91
01/02/87		0.00	0.00	0.00
01/03/87		0.00	0.00	0.00
01/04/87		0.00	0.00	0.00
01/05/87		0.00	0.00	0.00
01/06/87		0.00	0.00	0.00
01/07/87		0.00	0.00	0.00
01/08/87		0.00	0.00	0.00
01/09/87		3.06	3.06	3.06
01/10/87		2.02	1.90	1.96
01/11/87		0.00	0.00	0.00
01/12/87		0.00	0.00	0.00
01/13/87		0.00	0.00	0.00
01/14/87		4.33	4.60	4.47
01/15/87		2.52	1.71	2.12
01/16/87		0.00	0.00	0.00
01/17/87		3.59	3.69	3.64
01/18/87		52.15	51.79	51.97
01/19/87		17.17	15.63	16.40
01/20/87		0.00	0.00	0.00
01/21/87		0.00	0.00	0.00
01/22/87		11.18	10.93	11.06
01/23/87		0.00	0.00	0.00
01/24/87		0.51	0.51	0.51
01/25/87		22.50	21.84	22.17
01/26/87		0.00	0.00	0.00
01/27/87		2.29	2.03	2.16
01/28/87		0.00	0.00	0.00
01/29/87		0.00	0.00	0.00
01/30/87		0.00	0.00	0.00
01/31/87		0.76	0.00	0.38
02/01/87		0.00	0.00	0.00
02/02/87		9.88	9.92	9.90
02/03/87		0.00	0.00	0.00
02/04/87		0.00	0.00	0.00
02/05/87		0.00	0.00	0.00
02/06/87		0.00	0.00	0.00
02/07/87		0.00	0.00	0.00
02/08/87		0.00	0.00	0.00
02/09/87		0.00	0.00	0.00
02/10/87		0.00	0.00	0.00
02/11/87		0.00	0.00	0.00
02/12/87		0.00	0.00	0.00
02/13/87		0.00	0.00	0.00
02/14/87		4.84	4.57	4.71

SWSA 6 PRECIPITATION

Date	TARA Precip. (mm)	SWSA 6 Precip. Gauge 1 (mm)	SWSA 6 Precip. Gauge 2 (mm)	SWSA 6 Average Precip. (mm)
02/15/87		3.19	3.20	3.20
02/16/87		20.05	21.18	20.62
02/17/87		3.79	2.54	3.17
02/18/87		1.26	2.55	1.91
02/19/87		0.00	0.00	0.00
02/20/87		3.05	3.05	3.05
02/21/87		0.76	0.89	0.83
02/22/87		20.57	20.93	20.75
02/23/87		0.00	0.00	0.00
02/24/87		0.00	0.00	0.00
02/25/87		0.00	0.00	0.00
02/26/87		11.97	13.40	12.69
02/27/87		27.92	25.20	26.56
02/28/87		21.08	21.34	21.21
03/01/87		0.76	0.25	0.51
03/02/87		0.00	0.00	0.00
03/03/87		0.00	0.00	0.00
03/04/87		0.00	0.00	0.00
03/05/87		0.00	0.00	0.00
03/06/87		0.00	0.00	0.00
03/07/87		0.00	0.00	0.00
03/08/87		2.55	2.16	2.36
03/09/87		9.65	9.15	9.40
03/10/87		0.00	0.00	0.00
03/11/87		4.84	4.06	4.45
03/12/87		0.62	1.01	0.82
03/13/87		0.00	0.00	0.00
03/14/87		0.00	0.00	0.00
03/15/87		0.00	0.00	0.00
03/16/87		2.79	3.43	3.11
03/17/87		0.00	0.00	0.00
03/18/87		17.55	16.26	16.91
03/19/87		9.90	12.19	11.05
03/20/87		0.00	0.00	0.00
03/21/87		0.00	0.00	0.00
03/22/87		0.00	0.00	0.00
03/23/87		0.00	0.00	0.00
03/24/87		7.38	7.38	7.38
03/25/87		0.76	0.76	0.76
03/26/87		0.00	0.00	0.00
03/27/87		2.79	2.79	2.79
03/28/87		0.00	0.00	0.00
03/29/87		0.00	0.00	0.00
03/30/87		15.76	15.76	15.76
03/31/87		0.00	0.00	0.00

SWSA 6 PRECIPITATION

Date	TARA Precip. (mm)	SWSA 6 Precip. Gauge 1 (mm)	SWSA 6 Precip. Gauge 2 (mm)	SWSA 6 Average Precip. (mm)
04/01/87		0.00	0.00	0.00
04/02/87		6.49	6.12	6.31
04/03/87		15.10	13.20	14.15
04/04/87		0.00	0.00	0.00
04/05/87		0.00	0.00	0.00
04/06/87		0.00	0.00	0.00
04/07/87		0.00	0.00	0.00
04/08/87		0.00	0.00	0.00
04/09/87		0.00	0.00	0.00
04/10/87		0.00	0.00	0.00
04/11/87		5.34	5.08	5.21
04/12/87		3.05	3.04	3.05
04/13/87		0.00	0.00	0.00
04/14/87		8.01	7.61	7.81
04/15/87		21.08	19.68	20.38
04/16/87		9.41	8.63	9.02
04/17/87		0.89	0.50	0.70
04/18/87		0.00	0.00	0.00
04/19/87		0.00	0.00	0.00
04/20/87		0.00	0.00	0.00
04/21/87		0.00	0.00	0.00
04/22/87		0.00	0.00	0.00
04/23/87		0.00	0.00	0.00
04/24/87		3.56	3.30	3.43
04/25/87		0.00	0.00	0.00
04/26/87		0.00	0.00	0.00
04/27/87		0.76	0.64	0.70
04/28/87		0.00	0.00	0.00
04/29/87		0.00	0.00	0.00
04/30/87		1.52	1.27	1.40
05/01/87		0.00	0.00	0.00
05/02/87		0.00	0.00	0.00
05/03/87		18.39	16.96	17.68
05/04/87		4.21	5.13	4.67
05/05/87		0.00	0.00	0.00
05/06/87		0.00	0.00	0.00
05/07/87		0.00	0.00	0.00
05/08/87		0.00	0.00	0.00
05/09/87		0.00	0.00	0.00
05/10/87		0.00	0.00	0.00
05/11/87		0.00	0.00	0.00
05/12/87		0.76	0.38	0.57
05/13/87		0.00	0.00	0.00
05/14/87		0.00	0.00	0.00
05/15/87		0.00	0.00	0.00

SWSA 6 PRECIPITATION

Date	TARA Precip. (mm)	SWSA 6 Precip. Gauge 1 (mm)	SWSA 6 Precip. Gauge 2 (mm)	SWSA 6 Average Precip. (mm)
05/16/87		2.79	1.77	2.28
05/17/87		23.12	23.62	23.37
05/18/87		0.00	0.00	0.00
05/19/87		0.00	0.00	0.00
05/20/87		3.31	3.05	3.18
05/21/87		9.51	9.65	9.58
05/22/87		0.00	0.00	0.00
05/23/87		0.00	0.00	0.00
05/24/87		1.27	1.52	1.40
05/25/87		3.31	5.59	4.45
05/26/87		0.00	0.00	0.00
05/27/87		0.00	0.00	0.00
05/28/87		0.00	0.00	0.00
05/29/87		19.69	21.58	20.64
05/30/87		14.73	13.97	14.35
05/31/87		0.00	0.00	0.00
06/01/87		0.00	0.00	0.00
06/02/87		0.00	0.00	0.00
06/03/87		1.27	0.64	0.96
06/04/87		0.00	0.00	0.00
06/05/87		0.00	0.00	0.00
06/06/87		0.00	0.00	0.00
06/07/87		0.00	0.00	0.00
06/08/87		0.00	0.00	0.00
06/09/87		0.00	0.00	0.00
06/10/87		0.00	0.00	0.00
06/11/87		0.00	0.00	0.00
06/12/87		8.89	8.89	8.89
06/13/87		1.27	1.27	1.27
06/14/87		0.00	0.00	0.00
06/15/87		0.64	0.64	0.64
06/16/87		0.00	0.64	0.32
06/17/87		3.17	2.54	2.86
06/18/87		5.08	5.71	5.40
06/19/87		3.17	3.81	3.49
06/20/87		2.54	2.54	2.54
06/21/87		13.33	12.95	13.14
06/22/87		40.64	41.27	40.96
06/23/87		0.64	0.64	0.64
06/24/87		0.00	0.00	0.00
06/25/87		0.00	0.00	0.00
06/26/87		0.64	1.27	0.96
06/27/87		0.00	0.00	0.00
06/28/87		0.00	0.00	0.00
06/29/87		0.00	0.00	0.00

SWSA 6 PRECIPITATION

Date	TARA Precip. (mm)	SWSA 6 Precip. Gauge 1. (mm)	SWSA 6 Precip. Gauge 2 (mm)	SWSA 6 Average Precip. (mm)
06/30/87		0.00	0.00	0.00
07/01/87		6.86	6.86	6.86
07/02/87		0.25	0.25	0.25
07/03/87		14.47	13.71	14.09
07/04/87		7.88	8.00	7.94
07/05/87		8.26	8.76	8.51
07/06/87		0.25	0.51	0.38
07/07/87		8.38	7.87	8.13
07/08/87		0.00	0.00	0.00
07/09/87		0.00	0.00	0.00
07/10/87		0.00	0.00	0.00
07/11/87		7.37	6.73	7.05
07/12/87		0.00	0.00	0.00
07/13/87		1.15	0.77	0.96
07/14/87		0.00	0.00	0.00
07/15/87		0.00	0.00	0.00
07/16/87		0.00	0.00	0.00
07/17/87		0.00	0.00	0.00
07/18/87		0.00	0.00	0.00
07/19/87		0.00	0.00	0.00
07/20/87		0.00	0.00	0.00
07/21/87		0.00	0.00	0.00
07/22/87		0.00	0.00	0.00
07/23/87		0.00	0.00	0.00
07/24/87		0.00	0.00	0.00
07/25/87		0.00	0.00	0.00
07/26/87		0.00	0.00	0.00
07/27/87		0.00	0.00	0.00
07/28/87		0.00	0.00	0.00
07/29/87		0.00	0.00	0.00
07/30/87		0.00	0.00	0.00
07/31/87		0.00	0.00	0.00
08/01/87		0.00	0.00	0.00
08/02/87		0.00	0.00	0.00
08/03/87		0.38	0.50	0.44
08/04/87		0.00	0.00	0.00
08/05/87		2.03	1.52	1.78
08/06/87		9.65	9.40	9.53
08/07/87		0.00	0.00	0.00
08/08/87		0.00	0.00	0.00
08/09/87		4.06	3.30	3.68
08/10/87		2.79	3.31	3.05
08/11/87		0.00	0.00	0.00
08/12/87		24.77	21.46	23.12
08/13/87		0.00	0.00	0.00

SWSA 6 PRECIPITATION

Date	TARA Precip. (mm)	SWSA 6 Precip. Gauge 1 (mm)	SWSA 6 Precip. Gauge 2 (mm)	SWSA 6 Average Precip. (mm)
08/14/87		0.00	0.00	0.00
08/15/87		0.00	0.00	0.00
08/16/87		0.00	0.00	0.00
08/17/87		5.09	5.08	5.09
08/18/87		0.00	0.00	0.00
08/19/87		0.00	0.00	0.00
08/20/87		0.00	0.00	0.00
08/21/87		0.00	0.00	0.00
08/22/87		0.00	0.00	0.00
08/23/87		0.00	0.00	0.00
08/24/87		0.00	0.00	0.00
08/25/87		0.00	0.00	0.00
08/26/87		0.00	0.00	0.00
08/27/87		0.00	0.00	0.00
08/28/87		3.05	2.41	2.73
08/29/87		0.00	0.00	0.00
08/30/87		0.00	0.00	0.00
08/31/87		0.00	0.00	0.00
09/01/87		0.00	0.00	0.00
09/02/87		0.00	0.00	0.00
09/03/87		0.00	0.00	0.00
09/04/87		0.00	0.00	0.00
09/05/87		0.00	0.00	0.00
09/06/87		1.26	1.27	1.27
09/07/87		0.00	0.00	0.00
09/08/87		5.08	3.55	4.32
09/09/87		0.00	0.00	0.00
09/10/87		0.00	0.00	0.00
09/11/87		0.38	0.38	0.38
09/12/87		62.24	60.95	61.60
09/13/87		0.00	0.00	0.00
09/14/87		0.00	0.00	0.00
09/15/87		0.00	0.00	0.00
09/16/87		0.00	0.00	0.00
09/17/87		0.00	0.00	0.00
09/18/87		0.00	0.00	0.00
09/19/87		8.12	7.88	8.00
09/20/87		0.00	0.00	0.00
09/21/87		0.00	0.00	0.00
09/22/87		0.00	0.00	0.00
09/23/87		0.00	0.00	0.00
09/24/87		0.00	0.00	0.00
09/25/87		0.00	0.00	0.00
09/26/87		0.00	0.00	0.00
09/27/87		0.00	0.00	0.00

SWSA 6 PRECIPITATION

Date	TARA Precip. (mm)	SWSA 6 Precip. Gauge 1 (mm)	SWSA 6 Precip. Gauge 2 (mm)	SWSA 6 Average Precip. (mm)
09/28/87		0.00	0.00	0.00
09/29/87		16.51	17.26	16.89
09/30/87		0.00	0.00	0.00
10/01/87		0.00	0.00	0.00
10/02/87		0.00	0.00	0.00
10/03/87		0.00	0.00	0.00
10/04/87		0.00	0.00	0.00
10/05/87		0.00	0.00	0.00
10/06/87		0.76	1.02	0.89
10/07/87		0.00	0.00	0.00
10/08/87		0.00	0.00	0.00
10/09/87		0.00	0.00	0.00
10/10/87		0.00	0.00	0.00
10/11/87		0.00	0.00	0.00
10/12/87		0.00	0.00	0.00
10/13/87		0.00	0.00	0.00
10/14/87		0.00	0.00	0.00
10/15/87		0.00	0.00	0.00
10/16/87		0.00	0.00	0.00
10/17/87		0.00	0.00	0.00
10/18/87		0.00	0.00	0.00
10/19/87		0.51	0.37	0.44
10/20/87		7.12	7.36	7.24
10/21/87		0.00	0.00	0.00
10/22/87		0.00	0.00	0.00
10/23/87		0.00	0.00	0.00
10/24/87		0.00	0.00	0.00
10/25/87		0.76	0.64	0.70
10/26/87		1.53	1.29	1.41
10/27/87		2.03	2.03	2.03
10/28/87		0.00	0.00	0.00
10/29/87		2.54	2.03	2.29
10/30/87		0.00	0.00	0.00
10/31/87		0.00	0.00	0.00
11/01/87		0.00	0.00	0.00
11/02/87		0.00	0.00	0.00
11/03/87		0.00	0.00	0.00
11/04/87		0.00	0.00	0.00
11/05/87		0.00	0.00	0.00
11/06/87		0.00	0.00	0.00
11/07/87		0.00	0.00	0.00
11/08/87		0.00	0.00	0.00
11/09/87		7.02	8.70	7.86
11/10/87		20.55	19.50	20.03
11/11/87		0.00	0.00	0.00

SWSA 6 PRECIPITATION

Date	TARA Precip. (mm)	SWSA 6 Precip. Gauge 1 (mm)	SWSA 6 Precip. Gauge 2 (mm)	SWSA 6 Average Precip. (mm)
11/12/87		0.00	0.00	0.00
11/13/87		0.00	0.00	0.00
11/14/87		0.00	0.00	0.00
11/15/87		0.00	0.00	0.00
11/16/87		0.00	0.00	0.00
11/17/87		18.28	18.53	18.41
11/18/87		0.00	0.00	0.00
11/19/87		0.00	0.00	0.00
11/20/87		0.00	0.00	0.00
11/21/87		0.00	0.00	0.00
11/22/87		0.00	0.00	0.00
11/23/87		0.00	0.00	0.00
11/24/87		0.00	0.00	0.00
11/25/87		0.00	0.00	0.00
11/26/87		0.25	0.38	0.32
11/27/87		0.00	0.00	0.00
11/28/87		6.35	6.09	6.22
11/29/87		0.00	0.00	0.00
11/30/87		0.00	0.00	0.00
12/01/87		0.63	0.63	0.63
12/02/87		0.00	0.00	0.00
12/03/87		0.76	0.89	0.83
12/04/87		0.00	0.00	0.00
12/05/87		0.00	0.00	0.00
12/06/87		0.00	0.00	0.00
12/07/87		0.00	0.00	0.00
12/08/87		0.00	0.00	0.00
12/09/87		0.00	0.00	0.00
12/10/87		0.00	0.00	0.00
12/11/87		0.25	0.63	0.44
12/12/87		0.00	0.00	0.00
12/13/87		0.00	0.00	0.00
12/14/87		5.08	4.77	4.93
12/15/87		17.03	17.59	17.31
12/16/87		0.00	0.00	0.00
12/17/87		0.00	0.00	0.00
12/18/87		0.00	0.00	0.00
12/19/87		0.00	0.00	0.00
12/20/87		3.80	3.55	3.68
12/21/87		0.00	0.00	0.00
12/22/87		0.00	0.00	0.00
12/23/87		0.00	0.00	0.00
12/24/87		18.10	17.81	17.96
12/25/87		7.28	7.18	7.23
12/26/87		9.91	8.77	9.34

SWSA 6 PRECIPITATION

Date	TARA Precip. (mm)	SWSA 6 Precip. Gauge 1 (mm)	SWSA 6 Precip. Gauge 2 (mm)	SWSA 6 Average Precip. (mm)
12/27/87		7.12	7.37	7.25
12/28/87		9.89	9.64	9.77
12/29/87		0.00	0.00	0.00
12/30/87		0.00	0.00	0.00
12/31/87		2.67	2.92	2.80
01/01/88		12.57	11.93	12.25
01/02/88		0.00	0.00	0.00
01/03/88		8.38	8.26	8.32
01/04/88		0.00	0.26	0.13
01/05/88		0.00	0.00	0.00
01/06/88		0.00	0.00	0.00
01/07/88		14.45	14.23	14.34
01/08/88		0.76	0.90	0.83
01/09/88		0.00	0.00	0.00
01/10/88		0.00	0.00	0.00
01/11/88		0.00	0.00	0.00
01/12/88		0.51	0.63	0.57
01/13/88		1.53	1.01	1.27
01/14/88		0.00	0.00	0.00
01/15/88		0.00	0.00	0.00
01/16/88		0.00	0.00	0.00
01/17/88		14.84	15.75	15.30
01/18/88		0.00	0.00	0.00
01/19/88		75.44	72.52	73.98
01/20/88		0.00	0.00	0.00
01/21/88		0.00	0.00	0.00
01/22/88		0.00	0.00	0.00
01/23/88		0.00	0.00	0.00
01/24/88		0.26	0.51	0.39
01/25/88		1.28	1.28	1.28
01/26/88		0.00	0.00	0.00
01/27/88		0.00	0.00	0.00
01/28/88		0.00	0.00	0.00
01/29/88		0.00	0.00	0.00
01/30/88		0.00	0.00	0.00
01/31/88		0.76	0.77	0.77
02/01/88		0.00	0.00	0.00
02/02/88		13.71	12.72	13.22
02/03/88		14.73	14.73	14.73
02/04/88		14.99	13.71	14.35
02/05/88		0.00	0.00	0.00
02/06/88		0.00	0.00	0.00
02/07/88		0.00	0.00	0.00
02/08/88		0.00	0.00	0.00
02/09/88		0.00	0.00	0.00

SWSA 6 PRECIPITATION

Date	TARA Precip. (mm)	SWSA 6 Precip. Gauge 1 (mm)	SWSA 6 Precip. Gauge 2 (mm)	SWSA 6 Average Precip. (mm)
02/10/88		0.00	0.00	0.00
02/11/88		5.09	4.32	4.71
02/12/88		0.00	0.00	0.00
02/13/88		0.00	0.00	0.00
02/14/88		0.00	0.00	0.00
02/15/88		14.98	13.96	14.47
02/16/88		0.00	0.00	0.00
02/17/88		0.00	0.00	0.00
02/18/88		0.00	0.00	0.00
02/19/88		4.83	4.32	4.58
02/20/88		0.00	0.00	0.00
02/21/88		0.00	0.00	0.00
02/22/88		0.00	0.00	0.00
02/23/88		4.44	4.56	4.50
02/24/88		0.00	0.00	0.00
02/25/88		0.00	0.00	0.00
02/26/88		0.00	0.00	0.00
02/27/88		0.00	0.00	0.00
02/28/88		0.00	0.00	0.00
02/29/88		0.00	0.00	0.00
03/01/88		0.00	0.00	0.00
03/02/88		0.00	0.00	0.00
03/03/88		1.40	1.27	1.34
03/04/88	7.37	8.50	6.61	7.49
03/05/88	0.00	0.00	0.00	0.00
03/06/88	0.00	0.00	0.00	0.00
03/07/88	0.00	0.00	0.00	0.00
03/08/88	0.00	0.00	0.00	0.00
03/09/88	4.06	3.30	2.04	3.13
03/10/88	55.12	54.09	54.75	54.65
03/11/88	0.00	0.00	0.00	0.00
03/12/88	14.48	14.21	13.08	13.92
03/13/88	0.25	0.76	0.76	0.59
03/14/88	0.00	0.00	0.00	0.00
03/15/88	0.00	0.00	0.00	0.00
03/16/88	0.00	0.00	0.00	0.00
03/17/88	0.00	0.00	0.00	0.00
03/18/88	3.56	3.30	2.91	3.26
03/19/88	0.00	0.00	0.00	0.00
03/20/88	0.00	0.00	0.00	0.00
03/21/88	0.25	0.00	0.00	0.08
03/22/88	0.00	0.00	0.00	0.00
03/23/88	0.00	0.00	0.00	0.00
03/24/88	0.00	0.00	0.00	0.00
03/25/88	2.79	2.54	2.29	2.54

SWSA 6 PRECIPITATION

Date	TARA Precip. (mm)	SWSA 6 Precip. Gauge 1 (mm)	SWSA 6 Precip. Gauge 2 (mm)	SWSA 6 Average Precip. (mm)
03/26/88	2.54	3.56	2.54	2.88
03/27/88	0.00	0.00	0.00	0.00
03/28/88	0.00	0.00	0.00	0.00
03/29/88	0.00	0.00	0.00	0.00
03/30/88	0.25	0.25	0.38	0.29
03/31/88	1.02	1.01	0.77	0.93
04/01/88	10.67	9.53	9.13	9.78
04/02/88	0.25	0.00	0.00	0.08
04/03/88	7.11	5.96	5.70	6.26
04/04/88	0.00	0.00	0.00	0.00
04/05/88	0.00	0.00	0.00	0.00
04/06/88	18.29	17.02	16.52	17.28
04/07/88	0.00	0.00	0.00	0.00
04/08/88	0.00	0.00	0.00	0.00
04/09/88	0.00	0.00	0.00	0.00
04/10/88	0.00	0.00	0.00	0.00
04/11/88	2.03	1.53	1.53	1.70
04/12/88	5.84	4.70	4.83	5.12
04/13/88	0.00	0.00	0.00	0.00
04/14/88	0.00	0.00	0.00	0.00
04/15/88	6.35	6.35	5.47	6.06
04/16/88	0.00	0.00	0.00	0.00
04/17/88	0.00	0.00	0.00	0.00
04/18/88	20.83	18.30	17.91	19.01
04/19/88	5.33	5.20	4.95	5.16
04/20/88	0.00	0.00	0.00	0.00
04/21/88	0.00	0.00	0.00	0.00
04/22/88	0.00	0.00	0.00	0.00
04/23/88	3.05	3.17	2.54	2.92
04/24/88	1.27	1.27	1.02	1.19
04/25/88	0.00	0.00	0.00	0.00
04/26/88	0.00	0.00	0.00	0.00
04/27/88	0.00	0.00	0.00	0.00
04/28/88	0.00	0.00	0.00	0.00
04/29/88	0.00	0.00	0.00	0.00
04/30/88	0.00	0.00	0.00	0.00
05/01/88	0.00	0.00	0.00	0.00
05/02/88	0.00	0.00	0.00	0.00
05/03/88	7.62	7.62	7.11	7.45
05/04/88	9.14	8.37	8.64	8.72
05/05/88	0.00	0.00	0.00	0.00
05/06/88	0.00	0.00	0.00	0.00
05/07/88	0.00	0.00	0.00	0.00
05/08/88	0.00	0.00	0.00	0.00
05/09/88	10.92	10.67	9.78	10.46

SWSA 6 PRECIPITATION

Date	TARA Precip. (mm)	SWSA 6 Precip. Gauge 1 (mm)	SWSA 6 Precip. Gauge 2 (mm)	SWSA 6 Average Precip. (mm)
05/10/88	0.76	0.64	0.76	0.72
05/11/88	0.00	0.00	0.00	0.00
05/12/88	0.00	0.00	0.00	0.00
05/13/88	0.00	0.00	0.00	0.00
05/14/88	0.51	0.63	0.51	0.55
05/15/88	0.00	0.00	0.00	0.00
05/16/88	0.00	0.00	0.00	0.00
05/17/88	0.00	0.00	0.00	0.00
05/18/88	0.00	0.00	0.00	0.00
05/19/88	0.00	0.00	0.00	0.00
05/20/88	0.00	0.00	0.00	0.00
05/21/88	0.00	0.00	0.00	0.00
05/22/88	0.51	0.76	0.63	0.63
05/23/88	0.00	0.00	0.00	0.00
05/24/88	20.57	23.11	21.84	21.84
05/25/88	1.78	1.78	1.65	1.74
05/26/88	0.00	0.00	0.00	0.00
05/27/88	0.00	0.00	0.00	0.00
05/28/88	0.00	0.00	0.00	0.00
05/29/88	0.00	0.00	0.00	0.00
05/30/88	0.00	0.00	0.00	0.00
05/31/88	0.00	0.00	0.00	0.00
06/01/88	0.00	0.00	0.00	0.00
06/02/88	0.00	0.00	0.00	0.00
06/03/88	0.00	0.00	0.00	0.00
06/04/88	0.00	0.00	0.00	0.00
06/05/88	0.00	0.00	0.00	0.00
06/06/88	0.00	0.00	0.00	0.00
06/07/88	0.00	0.00	0.00	0.00
06/08/88	0.00	0.00	0.00	0.00
06/09/88	14.48	11.69	11.93	12.70
06/10/88	0.00	0.00	0.00	0.00
06/11/88	0.00	0.00	0.00	0.00
06/12/88	0.00	0.00	0.00	0.00
06/13/88	0.00	0.00	0.00	0.00
06/14/88	0.00	0.00	0.00	0.00
06/15/88	0.00	0.00	0.00	0.00
06/16/88	0.00	0.00	0.00	0.00
06/17/88	0.00	0.00	0.00	0.00
06/18/88	0.00	0.00	0.00	0.00
06/19/88	0.00	0.00	0.00	0.00
06/20/88	4.57	3.94	5.21	4.57
06/21/88	0.00	0.00	0.00	0.00
06/22/88	0.00	0.00	0.00	0.00
06/23/88	0.00	0.00	0.00	0.00

SWSA 6 PRECIPITATION

Date	TARA Precip. (mm)	SWSA 6 Precip. Gauge 1 (mm)	SWSA 6 Precip. Gauge 2 (mm)	SWSA 6 Average Precip. (mm)
06/24/88	5.84	5.72	5.33	5.63
06/25/88	16.76	27.81	24.89	23.15
06/26/88	0.00	0.00	0.00	0.00
06/27/88	0.00	0.00	0.00	0.00
06/28/88	0.00	0.00	0.00	0.00
06/29/88	0.00	0.00	0.00	0.00
06/30/88	3.81	3.19	3.05	3.35
07/01/88	0.00	0.00	0.00	0.00
07/02/88	0.00	0.00	0.00	0.00
07/03/88	4.83	5.08	4.83	4.91
07/04/88	0.00	0.00	0.00	0.00
07/05/88	0.00	0.00	0.00	0.00
07/06/88	0.00	0.00	0.00	0.00
07/07/88	0.00	0.00	0.00	0.00
07/08/88	0.00	0.00	0.00	0.00
07/09/88	0.00	0.00	0.00	0.00
07/10/88	0.00	0.00	0.00	0.00
07/11/88	25.91	16.67	16.86	19.81
07/12/88	14.22	30.45	28.22	24.30
07/13/88	54.10	58.92	56.65	56.56
07/14/88	0.25	0.00	0.26	0.17
07/15/88	0.00	0.00	0.00	0.00
07/16/88	0.51	0.00	0.51	0.34
07/17/88	0.00	0.00	0.00	0.00
07/18/88	1.52	1.27	2.03	1.61
07/19/88	0.00	0.00	0.00	0.00
07/20/88	0.00	0.00	0.00	0.00
07/21/88	32.51	31.23	29.46	31.07
07/22/88	1.02	0.00	0.00	0.34
07/23/88	1.02	1.52	1.14	1.23
07/24/88	0.00	0.00	0.00	0.00
07/25/88	0.00	0.00	0.00	0.00
07/26/88	32.00	30.48	31.88	31.45
07/27/88	0.00	0.00	0.00	0.00
07/28/88	0.00	0.00	0.00	0.00
07/29/88	0.00	0.51	0.00	0.17
07/30/88	0.00	0.00	0.00	0.00
07/31/88	0.00	0.00	0.00	0.00
08/01/88	0.00			
08/02/88	0.00			
08/03/88	0.00			

SWSA 6 1987 AND 1988 PRECIPITATION

SUMMARY OF SWSA-6 PRECIPITATION

APPENDIX IV

Nonstandard Soil Penetration Tests Over Waste Trenches

APPENDIX IV

Trench Number	Hole Number	Date	ft from N End	Contam.	1-ft Blows	2-ft Blows	3-ft Blows	4-ft Blows	5-ft Blows
2	1	02/03/87	20 N	NO	4	5	3	1	1
2	2	02/03/87	35 N	NO	4	3	3	1	1
2	3	02/03/87	48.5 N	NO	3	5	6	6	5
2	4	02/03/87	60.5 N	NO	5	4	7	4	4
2	5	02/03/87	18 S	NO	3	4	10	8	7
3	1	02/03/87	12.5 N	NO	3	4	3	2	1
3	2	02/03/87	24.5 N	NO	4	6	7	3	3
3	3	02/03/87	40.5 N	NO	5	3	5	7	8
3	4	02/03/87	53.5 N	YES	4	5	6	4	4
3	5	02/04/87	22 S	YES	4	5	7	6	5
4	1	02/04/87	7 N	NO	3	3	6	4	3
4	2	02/04/87	20 N	YES	4	5	8	5	3
4	3	02/04/87	33.5 N	NO	4	4	8	9	8
4	4	02/04/87	47 N	NO	4	4	7	9	12
4	5	02/04/87	65.5 N	NO	4	4	5	3	3
5	1	02/04/87	8.5 N	NO	3	5	7	6	5
5	2	02/04/87	22.5 N	NO	4	4	8	10	11
5	3	02/05/87	40 N	NO	4	5	7	8	7
5	4	02/05/87	52.5 N	NO	5	6	6	5	4
5	5	02/05/87	67.5 N	NO	4	3	3	5	5
6	1	02/05/87	9 N	NO	4	4	8	7	4
6	2	02/05/87	25 N	NO	4	4	8	3	3
6	3	02/05/87	41 N	NO	5	7	8	3	3
6	4	02/05/87	57 N	NO	6	7	8	4	4
6	5	02/05/87	70 N	NO	4	4	8	5	3
7	1	02/05/87	9 N	NO	4	5	10	7	4
7	2	02/05/87	25 N	NO	5	3	7	7	7
7	3	02/05/87	36 N	NO	5	4	9	3	3
7	4	02/06/87	51 N	NO	5	6	13	8	6
7	5	02/06/87	64 N	NO	7	5	7	5	4
8	1	02/06/87	10 N	NO	4	6	10	12	13
8	2	02/06/87	21.5 N	YES	4	5	6	7	4
8	3	02/06/87	36.5 N	NO	5	4	9	7	6
8	4	02/06/87	49.5 N	NO	5	7	11	9	4
8	5	02/06/87	60.5 N	NO	4	4	10	6	5
9	1	02/06/87	11 N	NO	5	5	8	4	4
9	2	02/06/87	20 N	NO	4	5	7	7	5
9	3	02/09/87	30.5 N	NO	6	6	9	12	8
9	4	02/09/87	42 N	NO	6	5	7	11	9
9	5	02/09/87	53 N	NO	6	5	12	9	6
126	1	02/09/87	8 N	NO	4	3	6	8	5
126	2	02/09/87	18.5 N	NO	5	4	3	3	5
126	3	02/09/87	30 N	NO	5	5	5	8	9
126	4	02/09/87	41 N	NO	5	4	7	8	10
126	5	02/09/87	53.5 N	NO	4	1	8	11	12
142	1	02/11/87	7.5 N	NO	4	2	6	6	8
142	2	02/11/87	19 N	NO	5	4	8	8	8

APPENDIX IV

Trench Number	Hole Number	Date	ft from N End	Contam.	1-ft Blows	2-ft Blows	3-ft Blows	4-ft Blows	5-ft Blows
142	3	02/11/87	31.5 N	NO	5	6	7	8	8
142	4	02/11/87	41 N	NO	5	5	7	7	8
142	5	02/11/87	52.5 N	NO	6	6	8	21	8
159	1	02/11/87	6.5 N	NO	3	2	6	3	4
159	2	02/11/87	17 N	NO	6	5	7	11	9
159	3	02/11/87	28 N	NO	5	3	6	25	12
159	4	02/11/87	37 N	NO	5	5	7	6	6
159	5	02/11/87	47.5 N	NO	4	4	7	10	10
165	1	02/11/87	6.5 N	NO	3	2	5	6	4
165	2	02/12/87	15.5 N	NO	4	4	5	8	6
165	3	02/12/87	23.5 N	YES	3	5	7	8	7
165	4	02/12/87	32.5 N	NO	4	5	5	10	8
170	1	02/12/87	4 N	NO	5	2	5	7	4
170	2	02/17/87	12.5 N	YES	3	4	5	8	10
170	3	02/17/87	23.5 N	NO	4	4	6	11	
170	4	02/17/87	30.5 N	NO	4	6	7	7	4
170	5	02/17/87	40 N	NO	2	4	6	10	10
192	1	02/17/87	7 N	NO	5	2	2	5	4
192	2	02/17/87	11.5 N	NO	3	4	6		
192	3	02/17/87	18.5 N	NO	4	5	7	8	6
192	4	02/17/87	28 N	NO	4	5	8	5	3
199	1	02/17/87	4 E	NO	3	4	2	1	4
199	2	02/17/87	13.5 E	NO	3	2	2	2	2
199	3	02/17/87	21 E	NO	3	3	3	2	3
199	4	02/18/87	26.5 E	NO	2	4	5	2	3
199	5	02/18/87	38.5 E	NO	2	3	6	4	3
148	1	02/18/87	4 E	NO	2	4	9	4	5
148	2	02/18/87	14 E	NO	4	3	7	9	9
148	3	02/18/87	23 E	NO	5	5	10	8	9
148	4	02/18/87	33.5 E	NO	3	3	11	9	7
148	5	02/18/87	45 E	NO	3	3	9	6	4
155	1	02/18/87	4.5 E	NO	3	5	12	7	5
155	2	02/18/87	22 E	YES	5	6	11	6	4
155	3	02/18/87	32 E	NO	5	6	7	3	4
155	4	02/19/87	43 E	NO	4	3	7	5	9
155	5	02/19/87	54.5 E	NO	6	5	7	3	12
151	1	02/19/87	4 E	NO	4	5	7	12	14
151	2	02/19/87	13 E	NO	3	3	11	11	7
151	3	02/19/87	22 E	NO	4	5	9	12	11
151	4	02/19/87	25 E	NO	5	4	10	17	
151	5	02/19/87	41.5 E	NO	3	3	10	6	4
178	1	02/02/87	6 W	NO	4	9	31	17	9
178	2	02/02/87	26 W	NO	6	5	10	8	12
178	3	02/19/87	4.5 E	NO	3	5	14	12	9
178	4	02/19/87	14 E	NO	4	5	14	14	8
178	5	02/19/87	25 E	NO	4	4	12	9	6
Average -					4.2	4.4	7.6	7.2	6.2

APPENDIX IV

Trench Number	Hole Number	6-ft Blows	7-ft Blows	8-ft Blows	9-ft Blows	10-ft Blows	11-ft Blows	12-ft Blows	13-ft Blows	14-ft Blows
2	1	3	3	2	4	10	39			
2	2	6	10	3	5	11	7	9	32	
2	3	15								
2	4	4	5	19	18	17	13	20	42	24
2	5	8	4	3	7	6	8	6	5	8
3	1	2	1	4						
3	2	4	1	3	2	1	3	3	10	
3	3	10	6	7	4	4	6	2	10	20
3	4	4	4	4	3	3	5			
3	5	4	2	4	3	3	13	7	7	14
4	1	1	2	4	3	10	3	3	3	20
4	2	2	1	1	7	2	3	3	3	3
4	3	6	5	6	10					
4	4	11	39							
4	5	1	1	1	1	1	2	1	1	0
5	1	4	4	4	4	7	11	11	19	
5	2	11	9	9	12	11	13	24	24	24
5	3	5	6	6	11	7	9	11	11	10
5	4	2	3	2	6	1	4	7	5	8
5	5	5	6	6	6	5	5	5	6	6
6	1	4	3	4	3	4	2	2	2	3
6	2	2	1	1	2	3	1	3	2	2
6	3	1	2	2	1	3	1	3	2	2
6	4	2	4	3	2	3	1	2	3	4
6	5	2	3	2	1	3	1	5	10	15
7	1	2	3	2	1	1	2			
7	2	7	6	7	5	6	7	13		
7	3	3	3	4	2	4	3	5	9	5
7	4	4	5	17	9	4	6	10	18	9
7	5	2	2	2	1	1	11			
8	1	13	18	17	18	21	24	44	25	
8	2	4	7	6	6	5	6	7	8	6
8	3	2	2	2	2	2	4	6	8	6
8	4	2	4	2	6					
8	5	3	2	4	6	7	8	7	8	8
9	1	6	4	4	3	3	8	9	7	5
9	2	5	5	5	4	7	4	6	4	8
9	3	7	10	18	13	10	12			
9	4	8	9	8	6	6	5	5	4	5
9	5	3	3	2	2	2	13	2	1	1
126	1	5	4	4	2					
126	2	3	1	2	1	12	5	3	3	
126	3	6	10	14	10	8	8	11	11	9
126	4	14	15	13	14	11	15	15	15	16
126	5	6	6	4	3	7	10	15	10	11
142	1	6	6	4	4	3				
142	2	7	8	9	8	7	7	8	8	7

APPENDIX IV

Trench Number	Hole Number	6-ft Blows	7-ft Blows	8-ft Blows	9-ft Blows	10-ft Blows	11-ft Blows	12-ft Blows	13-ft Blows	14-ft Blows
142	3	7	10	29						
142	4	7	6	7	7	6	7	12	13	11
142	5	5	5	3	7	8	8	5	4	4
159	1	2	2	2	3	3	1	1	2	22
159	2	9	5	11	3	11	4	6	15	
159	3	9	11	8	8	7	8	8		
159	4	5	6	5	7	10				
159	5	6	12	12	14	13	16	12		
165	1	4	4	4	4	3	4	3	4	4
165	2	5	3	3	3	3	3	8		
165	3	7	6	6	7	8	7	8	7	8
165	4	7	7	7	6	10	7	14	13	14
170	1	7	13	21	14	13	14	27	30	29
170	2	12	11	12	10	9	18	15	19	26
170	3									
170	4	4	3	4	4	2	1	2	4	
170	5	8	7	6	3	6	11			
192	1	2	3	2	2	8				
192	2									
192	3	3	4	5	3	4	3	4	4	6
192	4	2	1	2	2	4	3	1	13	
199	1	3	4	3	4	4	5	5	11	27
199	2									
199	3	0	0	0	1	3	10	1	3	9
199	4	6								
199	5	3	3	4	27					
148	1	5	6	5	5	5	4	5	5	22
148	2	9	7	6	8					
148	3	14	11	10	7	10	9	12	10	25
148	4	5	6	5	3	8	4	2	15	
148	5	4	4	15	6					
155	1	3	9	3	5	6	5	8	26	
155	2	5	3	4	4	4	3	4	16	
155	3	2	2	1	2	1	1	2	1	12
155	4	14	13	6	7	23	9	8	9	29
155	5									
151	1	11	14	15	13	14	15	15	17	21
151	2	6	6	18	22	11	9	11	14	19
151	3	9	9	13	17	7	14			
151	4									
151	5	3	3	2	5	3	2	3	2	16
178	1	8	7	8	3	7	19	32	25	16
178	2	60	29	12	22	14	17			
178	3	6	16							
178	4	6	6	5	2	10	8	18	45	
178	5	2	2	5	5	7	10	25		
Average =		6	6.2	6.4	6.3	6.7	7.8	8.8	11	12.1

APPENDIX IV

Trench Number	Hole Number	15-ft Blows	Total Depth	Well Installed
2	1		11	NO
2	2		13	NO
2	3		6	NO
2	4	30	15	NO
2	5	9	15	YES
3	1		8	NO
3	2		13	NO
3	3	23	15	YES
3	4		11.5	NO
3	5	13	15	NO
4	1		14	YES
4	2	7	15	YES
4	3		9	NO
4	4		7	NO
4	5	2	15	NO
5	1		13	NO
5	2		14	NO
5	3		14.5	NO
5	4	8	15	YES
5	5	6	15	NO
6	1	5	15	NO
6	2	3	15	YES
6	3	13	15	NO
6	4	4	15	NO
6	5	22	15	NO
7	1		11.5	NO
7	2		12	NO
7	3	7	15	YES
7	4	10	15	NO
7	5		11	NO
8	1		13	NO
8	2	6	15	YES
8	3	5	15	NO
8	4		9	NO
8	5	13	15	NO
9	1	6	15	YES
9	2	8	15	NO
9	3		11.5	NO
9	4	4	15	NO
9	5	2	15	NO
126	1		9.5	NO
126	2		13.5	NO
126	3	12	15	YES
126	4	16	15	NO
126	5	13	15	NO
142	1		10.5	NO
142	2	5	15	YES

APPENDIX IV

Trench Number	Hole Number	15-ft Blows	Total Depth	Well Installed
142	3		8	NO
142	4	7	15	NO
142	5	9	15	NO
159	1	41	15	NO
159	2		13	NO
159	3		12	NO
159	4		10.5	NO
159	5		12.5	NO
165	1	13	15	NO
165	2		12	NO
165	3	9	15	YES
165	4	8	15	NO
170	1	26	15	NO
170	2		14	NO
170	3		4	NO
170	4		13	NO
170	5		11	NO
192	1		10	NO
192	2		3	NO
192	3	13	15	YES
192	4		13	NO
199	1		14	NO
199	2		5.5	NO
199	3	20	15	YES
199	4		6	NO
199	5		9	NO
148	1	44	15	YES
148	2		9	NO
148	3		14	NO
148	4		13	NO
148	5		9	NO
155	1		13	NO
155	2		13	NO
155	3	46	15	YES
155	4		14	NO
155	5		5	NO
151	1	58	15	YES
151	2	31	15	NO
151	3		11	NO
151	4		4	NO
151	5		14	YES
178	1	28	15	NO
178	2		11.5	NO
178	3		7	NO
178	4		13	NO
178	5		12	NO

Average = 15.1

APPENDIX V

Nonstandard Soil Penetration Tests in Conasauga Shale

APPENDIX V

Control Hole	Date	Contam. Found	1-ft Blows	2-ft Blows	3-ft Blows	4-ft Blows	5-ft Blows	6-ft Blows	7-ft Blows	8-ft Blows
1	2/29/88	NO	6	12	17	36	52	52	75	
2	2/29/88	NO	5	6	6	10	14	25	40	41
3	2/29/88	NO	6	4	5	6	10	10	22	27
4	2/29/88	NO	2	1	2	1	1	24	50	95
5	2/29/88	NO	6	4	2	8	18	21	27	31
6	3/1/88	NO	5	4	7	13	27	33	36	50
7	3/1/88	NO	6	5	8	9	11	23	43	76
8	3/1/88	NO	5	11	16	30	43	57	81	57
9	3/1/88	NO	5	4	6	9	20	30	48	53
10	3/1/88	NO	5	4	12	21	42	42	52	51
11	3/1/88	NO	7	6	7	11	15	18	21	30
12	3/1/88	NO	4	3	8	12	24	41	119	
13	3/1/88	NO	6	5	5	8	15	25	36	44
14	3/2/88	NO	6	5	18	32	55	43	43	63
15	3/2/88	NO	8	4	7	11	16	19	24	29
16	3/2/88	NO	5	4	8	17	18	22	19	34
17	3/2/88	NO	5	3	4	9	10	14	22	33
18	3/2/88	NO	6	4	6	9	19	29	36	45
19	3/2/88	NO	8	7	8	17	26	37	82	115
20	3/3/88	NO	7	7	14	14	15	19	25	37
21	3/3/88	NO	6	6	37	37	36	39	38	52
22	3/3/88	NO	4	4	5	11	15	31	52	78
1	2/2/87	NO	5	12	31	20	17	18	14	28
2	2/2/87	NO	5	4	10	14	14	14	27	26
3	2/24/87	NO	3	5	4	6	10	13	16	22
4	2/24/87	NO	3	10	5	3	7	12	16	21
5	2/24/87	NO	4	4	4	3	8	13	23	28
6	2/24/87	NO	5	4	9	4	5	7	16	23
7	2/24/87	NO	4	3	9	7	15	24	23	28
8	2/24/87	NO	3	4	10	19	30	134		
9	2/25/87	NO	4	5	7	6	11	33	51	44
10	2/25/87	NO	5	4	26					
11	2/25/87	NO	5	4	12	6	20	45	58	
12	2/25/87	NO	4	8	19	21	16	19	17	10
Average =			5.1	5.3	10.4	13.3	19.8	29.9	39.1	43.8

APPENDIX V

Control Hole	9-ft Blows	10-ft Blows	11-ft Blows	12-ft Blows	13-ft Blows	14-ft Blows	15-ft Blows	Total Depth
1								7
2	32	28	28	32	47			13
3	41	44	55	62				12
4								8
5	62	112						10
6	51	52						10
7	62	57						10
8								7.5
9	54	41	57					11
10	39	32						10
11	26	24	31	29	45	30		14
12								6.5
13	52	60	44					11
14	35							8.5
15	42	43	58	50	53			13
16	106							9
17	40	46	45	69				12
18	44	34	31	67				12
19								8
20	40	42	34	28	49	48		14
21	49							9
22								8
1	38	58						10
2	31	26	41	63	75			13
3	36	42	51	37				12
4	28	38	48	62	82			13
5	33	35	45					11
6	32	24	26	31	34			13
7	35	52						10.5
8								6.5
9	45							9
10								3.5
11								7
12	46							9
Average -	44	44.5	42.4	48.2	55	39		

APPENDIX VI

Standard Soil Penetration Resistance, Soil Moisture,
and Bulk Density Data

APPENDIX VI

TARA Core Number	Date	Core Length (In.)	Soil Moist. (% of Dry Wt)	Core Bulk Density (g/cm ³)	Blows Per 6 In.	Blows Per 12 In.	Blows Per 18 In.	Penetrate Resist. (Blows/Ft)
1	03/09/88	14.50	23.42	1.57	3	3	3	6
1	03/09/88	15.25	18.55	1.67	3	5	5	10
1	03/09/88	17.00	16.20	1.72	5	10	20	30
1	03/09/88	15.00	11.46	2.15	14	17	21	38
1	03/09/88	14.50	12.59	2.03	11	27	88	115
1	03/09/88	8.50	6.58	1.84	36	100	DRILL	
1	03/10/88	7.00	6.94	2.11	35	100/STOP		
2	03/10/88	13.50	22.52	1.69	2	2	4	6
2	03/10/88	15.00	27.19	1.56	3	6	9	15
2	03/10/88	16.00	23.08	1.67	4	9	13	22
2	03/10/88	17.50	23.74	1.63	5	12	15	27
2	03/10/88	15.00	21.26	1.74	7	12	13	25
2	03/10/88	16.00	24.26	1.75	6	10	15	25
2	03/10/88	17.00	25.55	1.66	6	7	12	19
2	03/11/88	15.00	21.09	1.75	9	9	8	17
2	03/11/88	17.00	21.53	1.74	6	13	15	28
2	03/11/88	12.25	21.10	1.83	7	15	14/STOP	
3	03/11/88	14.25	24.07	1.56	2	2	2	4
3	03/11/88	13.00	31.91	1.49	2	3	4	7
3	03/11/88	14.50	25.64	1.66	2	3	3	6
3	03/11/88	15.00	29.46	1.53	2	3	3	6
3	03/11/88	15.25	25.83	1.62	3	8	11	19
3	03/11/88	13.25	19.83	1.88	8	14	15	29
3	03/11/88	15.00	20.30	1.82	12	18	27	45
3	03/11/88	14.25	20.63	1.82	9	13	18	31
3	03/11/88	13.75	19.08	1.96	8	14	14	28
3	03/11/88	14.50	23.44	1.81	6	10	14	24
4	03/24/88	10.00	16.46	1.62	1	1	1	2
4	03/24/88	10.00	13.85	1.34	1	1	1	2
4	03/24/88	10.75	19.44	1.38	1	1	1	2
4	03/24/88	17.50	16.88	1.88	5	10	19	29
4	03/24/88	12.50	11.97	1.92	14	100/STOP		
5	03/25/88	11.75	20.93	1.50	3	3	3	6
5	03/25/88	16.00	26.09	1.48	2	1	2	3
5	03/25/88	17.00	27.87	1.47	4	5	10	15
5	03/25/88	16.00	22.31	1.67	6	10	10	20
5	03/25/88	17.25	24.06	1.58	4	8	10	18
5	03/25/88	17.75	16.67	1.67	6	16	19	35
5	03/25/88	15.00	9.77	1.82	40	77	100/STOP	

APPENDIX VI

TARA Core Number	Date	Core Length (In.)	Soil Moist. (% of Dry Wt)	Core Bulk Density (g/cm ³)	Blows Per 6 In.	Blows Per 12 In.	Blows Per 18 In.	Penetrate Resist. (Blows/Ft)
6	03/28/88	15.00	21.82	1.51	3	3	2	5
6	03/28/88	16.25	30.25	1.50	2	3	5	8
6	03/28/88	17.00	23.48	1.60	4	7	14	21
6	03/28/88	17.50	21.23	1.71	8	14	15	29
6	03/28/88	16.50	21.23	1.82	6	12	17	29
6	03/28/88	13.25	18.49	1.85	7	10	10	20
6	03/28/88	17.00	13.22	2.10	10	50	29	79
6	03/28/88	17.25	23.73	1.69	3	10	18	28
6	03/28/88	14.50	22.31	1.71	8	9	9	18
6	03/28/88	15.00	25.00	1.86	3	13	17	30
7	03/16/88	13.75	22.64	1.58	3	3	2	5
7	03/16/88	13.50	25.00	1.40	3	6	7	13
7	03/16/88	13.75	21.90	1.57	3	4	5	9
7	03/16/88	15.00	22.41	1.59	5	5	8	13
7	03/16/88	15.50	23.39	1.64	4	9	11	20
7	03/16/88	14.50	26.09	1.63	5	9	15	24
7	03/16/88	14.25	20.87	1.66	5	11	16	27
8	03/24/88	14.75			3	4	6	10
8	03/24/88	15.25	16.42	1.81	6	8	10	18
8	03/24/88	15.75	14.29	1.83	8	14	21	35
8	03/24/88	15.50	14.16	1.83	9	12	46	58
8	03/24/88	8.25	9.59	1.82	35	101/STOP		
9	03/29/88	14.25	21.10	1.57	3	3	2	5
9	03/29/88	16.50	21.05	1.66	4	6	7	13
9	03/29/88	15.25	22.05	1.71	4	8	11	19
9	03/29/88	16.00	22.31	1.84	7	10	11	21
9	03/29/88	15.50	23.66	1.74	3	10	13	23
9	03/29/88	14.75	21.60	1.74	7	14	15	29
9	03/29/88	16.50	25.17	1.78	3	11	18	29
9	03/29/88	15.50	21.74	1.83	9	12	19	31
9	03/29/88	8.50	17.72	1.91	14	35/STOP	DRILL	
9	03/29/88	16.25	13.82	1.92	32	29	13	42

APPENDIX VI

TARA Core Number	Date	Core Length (In.)	Soil Moist. (% of Dry Wt)	Core Bulk Density (g/cm ³)	Blows Per 6 In.	Blows Per 12 In.	Blows Per 18 In.	Penetrate Resist. (Blows/Ft)
10	03/29/88	12.25	20.65	1.54	3	2	2	4
10	03/29/88	16.50	28.46	1.53	2	2	7	9
10	03/29/88	17.00	25.93	1.63	5	10	11	21
10	03/30/88	15.75	20.29	1.80	6	14	17	31
10	03/30/88	16.50	31.20	1.56	6	7	9	16
10	03/30/88	15.50			6	10	19	29
10	03/30/88	17.50	15.48	1.82	10	15	23	38
10	03/30/88	14.00	13.97	2.00	13	23	32	55
10	03/30/88	16.00	15.86	1.86	10	17	22	39
10	03/30/88	14.00	14.00	2.20	11	25	40/STOP	
11	03/14/88	13.50	25.49	1.55	3	3	3	6
11	03/14/88	15.50			3	4	5	9
11	03/14/88	15.50	32.67	1.34	3	4	5	9
11	03/14/88	15.75	31.13	1.38	3	7	7	14
11	03/14/88	14.50	31.68	1.43	3	4	8	12
11	03/14/88	10.50	29.33	1.47	3	5	6	11
11	03/14/88	13.00	25.77	1.53	4	6	9	15
11	03/15/88	16.00	29.31	1.49	2	8	12	20
11	03/15/88	16.50	29.36	1.36	5	4	5	9
11	03/15/88	15.00	20.16	1.77	6	10	13	23
12	03/21/88	8.00	21.43	1.44	2	2	2	4
12	03/21/88	16.25	26.61	1.57	2	4	6	10
12	03/21/88	15.50	18.80	1.76	4	11	16	27
12	03/21/88	16.00	20.47	1.63	6	10	14	24
12	03/21/88	14.00	14.04	1.67	8	16	21	37
12	03/23/88	10.75	12.50	1.99	19	42	93	135
12	03/23/88	13.50	9.91	2.10	26	54	65	119
12	03/23/88	15.50	8.67	1.99	28	96	101/STOP	
13	04/04/88	14.75	20.54	1.56	2	3	4	7
13	04/04/88	16.00	31.46	1.43	2	3	4	7
13	04/04/88	18.00	35.71	1.44	2	3	6	9
13	04/04/88	17.00	31.71	1.49	4	6	11	17
13	04/04/88	15.00	32.23	1.66	7	12	14	26
13	04/04/88	14.00	21.37	1.72	6	10	10	20
13	04/04/88	15.25	18.42	1.54	5	9	7	16
13	04/04/88	16.50	22.39	1.67	5	9	13	22
13	04/04/88	17.75	23.08	1.50	8	9	10	19
13	04/04/88	17.50	13.79	1.70	19	19	24	43

APPENDIX VI

TARA Core Number	Date	Core Length (In.)	Soil Moist. (% of Dry Wt)	Core Bulk Density (g/cm ³)	Blows Per 6 In.	Blows Per 12 In.	Blows Per 18 In.	Penetrate Resist. (Blows/Ft)
14	04/05/88	13.50	21.59	1.34	2	3	4	7
14	04/05/88	16.75	30.08	1.51	3	3	6	9
14	04/05/88	16.50	21.26	1.58	6	10	16	26
14	04/05/88	17.50	17.12	1.71	7	14	22	36
14	04/05/88	16.00	14.97	1.89	11	16	24	40
14	04/05/88	17.00	17.02	1.70	11	14	18	32
14	04/05/88	16.00	15.17	1.86	11	18	26	44
14	04/05/88	14.50	17.05	1.83	12	19	22	41
14	04/05/88	18.00	16.99	1.75	8	15	24	39
14	04/05/88	16.50	9.93	1.88	24	39	100/STOP	
15	03/17/88	11.50	20.43	1.66	4	3	3	6
15	03/17/88	15.00	29.09	1.51	3	5	6	11
15	03/17/88	15.00	26.85	1.48	3	7	8	15
15	03/17/88	14.75	25.00	1.45	5	7	8	15
15	03/17/88	15.50	14.93	1.78	3	8	10	18
15	03/17/88	13.50	28.71	1.54	3	6	10	16
15	03/17/88	15.00	29.41	1.40	3	6	8	14
15	03/17/88	12.50	27.78	1.48	3	5	6	11
15	03/17/88	15.75	31.78	1.40	3	7	8	15
15	03/17/88	16.75	28.21	1.44	4	7	7	14
16	03/21/88	13.75	23.23	1.48	2	2	2	4
16	03/21/88	15.50	28.95	1.51	2	3	5	8
16	03/21/88	16.75	23.88	1.64	4	9	11	20
16	03/21/88	17.00	23.91	1.67	7	9	11	20
16	03/21/88	17.00	29.27	1.49	5	6	7	13
16	03/21/88	14.75	17.60	1.74	6	11	16	27
16	03/21/88	11.50	8.65	1.86	29	84/STOP	DRILL	
16	03/21/88	10.00	8.05	1.79	47	58/STOP		
17	04/06/88	13.75	22.33	1.54	3	3	3	6
17	04/06/88	16.50	24.81	1.66	3	4	5	9
17	04/06/88	18.00	35.65	1.31	3	4	4	8
17	04/06/88	14.25	32.67	1.46	4	4	4	8
17	04/06/88	17.75			3	4	9	13
17	04/06/88	16.25	24.43	1.66	5	9	14	23
17	04/07/88	15.50	20.00	1.79	7	13	15	28
17	04/07/88	16.00			10	22	26	48
17	04/07/88	16.25	15.75	1.85	8	13	46/STOP	
17	04/07/88	11.00	8.94	2.30	40	50/STOP		

APPENDIX VI

TARA Core Number	Date	Core Length (In.)	Soil Moist. (% of Dry Wt)	Core Bulk Density (g/cm ³)	Blows Per 6 In.	Blows Per 12 In.	Blows Per 18 In.	Penetrate Resist. (Blows/Ft)
18	04/07/88	15.00	15.32	1.70	2	3	2	5
18	04/07/88	13.75	26.47	1.52	3	3	2	5
18	04/07/88	11.25	17.95	1.42	4	5	8	13
18	04/07/88	12.50	18.95	1.56	5	6	6	12
18	04/08/88	14.50	20.49	1.73	5	10	12	22
18	04/08/88	15.75	20.90	1.75	8	9	14	23
18	04/08/88	15.25	22.05	1.71	7	8	10	18
18	04/08/88	16.00	20.59	1.75	6	6	9	15
18	04/08/88	15.25	20.74	1.82	7	10	12	22
18	04/08/88	15.50	16.55	1.92	9	15	20	35
19	03/18/88	14.00	20.69	1.70	4	3	4	7
19	03/18/88	15.00	27.83	1.58	3	4	7	11
19	03/18/88	15.50	27.68	1.48	4	6	8	14
19	03/18/88	16.25	21.09	1.62	6	10	13	23
19	03/18/88	14.75	21.67	1.67	8	15	19	34
19	03/18/88	14.50			10	19	24	43
19	03/18/88	17.00			6	3	4	7
19	03/18/88	18.00	40.17	1.34	2	3	5	8
19	03/18/88	17.00	26.40	1.51	6	7	8	15
19	03/18/88	15.00	29.36	1.49	6	5	8	13
20	03/03/88	6.50	17.95	1.23	3	3	3	6
20	03/03/88	16.00	26.19	1.62	4	6	9	15
20	03/03/88	17.75			4	6	7	13
20	03/03/88	16.50	26.89	1.48	4	8	9	17
20	03/03/88	16.75	30.97	1.39	4	5	5	10
20	03/07/88	16.50	39.25	1.33	2	3	6	9
20	03/07/88	13.50	32.56	1.31	2	5	5	10
20	03/07/88	17.50	31.75	1.48	3	6	9	15
20	03/07/88	15.75	27.73	1.55	4	6	7	13
20	03/07/88	15.25	22.50	1.62	5	8	12	20
21	03/07/88	15.00			2	3	3	6
21	03/07/88	17.50	29.46	1.51	4	4	7	11
21	03/07/88	14.75	18.55	1.73	6	9	12	21
21	03/07/88	18.00	15.69	1.75	8	15	22	37
21	03/07/88	15.75	12.70	1.64	12	26	28	54
21	03/07/88	15.00	16.26	1.68	8	12	14	26
21	03/08/88	17.25	13.77	1.64	10	15	22	37
21	03/08/88	8.50	16.95	1.43	12	8/STOP		

APPENDIX VI

TARA Core Number	Date	Core Length (In.)	Soil Moist. (% of Dry Wt)	Core Bulk Density (g/cm ³)	Blows Per 6 In.	Blows Per 12 In.	Blows Per 18 In.	Penetrate Resist. (Blows/Ft)
22	03/08/88	13.50	21.65	1.48	2	2	2	4
22	03/08/88	15.25	33.01	1.39	1	2	4	6
22	03/08/88	15.75	32.35	1.33	3	4	4	8
22	03/08/88	17.00	33.33	1.38	4	5	9	14
22	03/08/88	16.50	21.50	1.60	4	12	16	28
22	03/08/88	17.50	20.71	1.64	7	14	15	29
22	03/08/88	17.50	18.25	1.61	9	17	17	34
22	03/08/88	18.00	19.61	1.75	7	11	9	20
22	03/08/88	16.75	19.58	1.75	8	9	13	22
22	03/09/88	16.00	25.47	1.36	3	5	12	17
2A	04/11/88	14.75			3	3	2	5
2A	04/11/88	12.00	24.72	1.52	2	3	5	8
2B	04/12/88	12.00	22.83	1.58	2	2	2	4
2B	04/12/88	11.50	21.65	1.73	4	3	5	8
2C	04/12/88	12.00	21.28	1.61	2	4	2	6
2C	04/12/88	7.00	21.57	1.50	2	1	1	2
3A	04/11/88	11.50	22.35	1.52	3	2	2	4
3A	04/11/88	13.00	23.17	1.67	3	4	4	8
3B	04/12/88	12.00	22.99	1.49	3	2	3	5
3B	04/12/88	11.25	23.33	1.64	3	3	5	8
3C	04/12/88	15.00	23.28	1.59	2	2	3	5
3C	04/12/88	8.50	19.35	1.50	3	3	3	6
4A	04/11/88	12.00	22.35	1.46	2	2	2	4
4A	04/11/88	11.00	22.86	1.72	2	3	5	8
4B	04/11/88	10.50	18.99	1.55	4	3	3	6
4B	04/11/88	13.25	22.12	1.61	3	2	6	8
4C	04/12/88	13.00	23.71	1.53	3	3	2	5
4C	04/12/88	11.50	22.83	1.64	3	4	5	9
5A	04/11/88	12.50	21.65	1.59	2	3	3	6
5A	04/11/88	11.50	23.88	1.54	2	3	3	6
5B	04/11/88	11.00	20.00	1.59	3	3	2	5
5B	04/11/88	11.50	24.47	1.68	3	4	5	9

APPENDIX VI

TARA Core Number	Date	Core Length (In.)	Soil Moist. (% of Dry Wt)	Core Bulk Density (g/cm ³)	Blows Per 6 In.	Blows Per 12 In.	Blows Per 18 In.	Penetrate Resist. (Blows/Ft)
5C	04/12/88	12.75	22.22	1.60	2	3	2	5
5C	04/12/88		23.64		2	3	5	8
6A	04/08/88	11.75	21.35	1.56	3	2	2	4
6A	04/08/88	15.00	21.31	1.67	3	3	3	6
6B	04/11/88	12.00	20.00	1.56	3	3	2	5
6B	04/11/88	10.50	21.69	1.62	3	5	4	9
6C	04/12/88	12.50	22.22	1.63	2	3	2	5
6C	04/12/88	14.25	21.37	1.69	3	6	6	12
1	03/06/87	16	24.23	1.44	2	2	4	6
1	03/06/87	14	10.18	2.02	14	10	9	19
1	03/06/87	16	20.07	1.49	5	5	11	16
1	03/06/87	17	9.24	1.74	10	28	22	50
2	03/03/87	16	19.06	1.59	2	3	2	5
2	03/03/87	13	21.93	1.39	2	2	2	4
2	03/03/87	15	19.04	1.62	2	3	4	7
2	03/03/87	14.5	25.02	1.63	2	4	7	11
2	03/03/87	15	30.56	1.51	3	6	6	12
2	03/03/87	15	15.99	1.69	5	11	17	28
2	03/03/87	14	14.45	1.76	9	16	19	35
2	03/03/87	15	11.08	1.73	11	26	22	48
2	03/03/87	13.5	20.56	1.64	6	8	6	14
3	02/25/87	10	22.65	1.35	1	1	2	3
3	02/25/87	13	25.87	1.43	3	4	3	7
3	02/25/87	15	28.43	1.42	1	2	2	4
3	02/25/87	16	24.04	1.48	4	5	4	9
3	02/25/87	15	26.91	1.58	3	6	8	14
3	02/25/87	18	27.35	1.53	3	7	9	16
3	02/25/87	18	21.11	1.72	3	11	14	25
3	02/25/87	15	18.75	1.59	4	13	16	29
3	02/25/87	17	18.96	1.62	10	13	14	27
3	02/26/87	13	19.93	1.65	6	13	12	25

APPENDIX VI

TARA Core Number	Date	Core Length (In.)	Soil Moist. (% of Dry Wt)	Core Bulk Density (g/cm ³)	Blows Per 6 In.	Blows Per 12 In.	Blows Per 18 In.	Penetrate Resist. (Blows/Ft)
4	02/26/87	14	23.49	1.60	1	2	2	4
4	02/26/87	13	25.18	1.46	3	3	3	6
4	02/26/87	17	29.42	1.48	1	2	3	5
4	02/26/87	14	30.92	1.45	2	3	4	7
4	02/26/87	15	35.60	1.33	2	5	3	8
4	02/26/87	17	15.42	1.36	2	3	5	8
4	02/26/87	16	25.81	1.55	3	5	9	14
4	02/26/87	15	15.67	1.48	6	13	19	32
4	02/26/87	14	16.82	1.64	8	14	15	29
4	02/27/87	13	20.64	1.58	5	9	9	18
5	02/27/87	12	22.47	1.49	2	2	2	4
5	02/27/87	14	25.87	1.54	3	2	3	5
5	02/27/87	12	31.11	1.28	1	4	3	7
5	02/27/87	13	25.57	1.43	2	5	6	11
5	02/27/87	15	19.05	1.62	4	10	15	25
5	02/27/87	12	16.16	1.63	6	12	10	22
5	02/27/87	14	28.00	1.57	3	8	10	18
5	02/27/87	15	25.67	1.52	4	8	8	16
5	02/27/87	17.5	28.86	1.44	5	6	6	12
6	03/03/87	14	18.71	1.54	2	2	2	4
6	03/03/87	14	19.20	1.61	1	3	3	6
6	03/03/87	15	23.58	1.42	1	1	1	2
6	03/03/87	15.5	19.78	1.59	2	3	4	7
6	03/03/87	15	15.42	1.74	4	9	11	20
6	03/03/87	15	17.18	1.76	6	8	10	18
6	03/03/87	14.5	21.94	1.61	5	6	8	14
6	03/03/87	17	29.87	1.41	4	4	5	9
6	03/04/87	19	30.49	1.39	3	4	5	9
7	03/04/87	14	16.73	1.49	2	3	3	6
7	03/04/87	14.5	19.81	1.57	1	5	5	10
7	03/04/87	14	20.78	1.54	2	4	5	9
7	03/04/87	13	17.17	1.62	3	8	6	14
7	03/04/87	15	21.93	1.63	5	7	7	14
7	03/04/87	14	19.98	1.71	3	8	6	14
7	03/04/87	15.5	13.13	1.97	5	14	27	41
7	03/04/87		5.81		23	51/STOP		
8	03/04/87	12	21.37	1.51	2	4	3	7
8	03/04/87	15	19.89	1.73	2	5	6	11

APPENDIX VI

TARA Core Number	Date	Core Length (In.)	Soil Moist. (% of Dry Wt)	Core Bulk Density (g/cm ³)	Blows Per 6 In.	Blows Per 12 In.	Blows Per 18 In.	Penetrate Resist. (Blows/Ft)
9	03/04/87	12.5	17.74	1.52	3	3	3	6
9	03/04/87	13	21.61	1.81	2	4	6	10
9	03/04/87	13	28.07	1.58	3	3	3	6
9	03/04/87	15	16.86	1.82	3	7	12	19
9	03/04/87	14.5	13.34	1.89	6	12	12	24
9	03/04/87	16	21.58	1.73	4	5	10	15
9	03/04/87	14.5	15.81	1.63	5	7	5	12
9	03/04/87	17	13.94	1.81	7	13	16	29
9	03/04/87	14	12.14	1.95	9	12	15	27
10	03/05/87	9	13.39	1.60	4	3	1	4
10	03/05/87	16	19.15	1.69	4	6	6	12
11	03/05/87	13	16.60	1.46	3	4	4	8
11	03/05/87	18.5	16.77	1.56	3	7	5	12
11	03/05/87	16	25.78	1.43	2	2	3	5
11	03/05/87	17	34.51	1.34	1	2	3	5
11	03/05/87	17.5	18.33	1.53	3	8	14	22
11	03/05/87	13.5	13.62	1.72	8	10	8	18
11	03/05/87	15	13.67	1.78	5	9	17	26
12	03/05/87	13	23.85	1.63	3	2	2	4
12	03/05/87	17	14.80	1.76	11	7	8	15
12	03/05/87	15	16.39	1.70	5	7	8	15
12	03/05/87	14.5	18.67	1.75	5	7	7	14
12	03/05/87	13	24.38	1.53	4	2	2	4
12	03/06/87	16.5	22.37	1.57	1	3	9	12
12	03/06/87	16	10.04	1.98	11	20	24	44
12	03/06/87	8	11.39	1.98	8	STOP		

APPENDIX VII

Summary of the Number of Weight Drops Required
During Trench Compaction
Blows to Level - Leveling of Entire Section

APPENDIX VII

Trench	Date	Sect.	Blows Per 1-ft	Blows Per 2-ft	Blows Per 3-ft	Blows Per 4-ft	Blows Per 5-ft	Blows Per 6-ft	Total Blows	Blows Cont. to (mR/h) Level	
2	07/27/88	A 1	8	7	13				28		
2	07/27/88	A 2	2	3	7	8			20		
2	07/27/88	A 3	2	4	4	10			20		
2	07/27/88	A 4	2	1	3	4	10		20	0.1	
2	07/27/88	B 1	2	3	3	4	3	5	20	53	50
2	07/27/88	B 2	3	2	1	3			9	53	
2	07/27/88	C 1	2	2	2	3	9	4	22	61	
2	07/27/88	C 2	2	2	2	2	6	4	18	61	
2	07/27/88	C 3	2	2	2	3	4	3	16	61	
2	07/27/88	C 4	1	2	3	4	4	2	16	61	
2	07/27/88	C 5	1	2	3	6			12	61	
2	07/27/88	D 1	2	2	1	5			10	69	
2	07/27/88	D 2	2	1	4	8			15	69	
2	07/27/88	D 3	2	4	1	3			10	69	
2	07/27/88	D 4	1	2	2	2			7	69	
2	07/27/88	D 5	0	1	3	4			8	69	
2	07/27/88	D 6	1	1	2	2			6	69	
2	07/27/88	E 1	3	3	4	2			12	89	
2	07/27/88	E 2	2	2	4	6			14	89	
2	07/27/88	E 3	2	2	3	3			10	89	
2	07/27/88	E 4	2	4	3	3			12	89	
2	07/27/88	E 5	0	1	2	7			10	89	
2	07/27/88	E 6	0	1	2	7			10	89	
2	07/28/88	F 1	2	5	4	12			23	69	
2	07/28/88	F 2	1	4	2	5			12	69	2
2	07/28/88	F 3	3	5	2	4			14	69	
2	07/28/88	F 4	2	7	7	4			20	69	
2	07/28/88	F 5	1	2	2	1			6	69	
2	07/28/88	F 6	1	1	1	8			11	69	0.2
2	07/28/88	G 1	1	3	4	4			12	51	
2	07/28/88	G 2	2	4	4	10			20	51	0.1
2	07/28/88	G 3	2	3	4	4			13	51	
2	07/28/88	G 4	3	3	5	5			16	51	
2	07/28/88	G 5	1	1	2	6			10	51	
2	07/28/88	G 6	0	1	3	3			7	51	

APPENDIX VII

Trench	Date	Sect.	Blows Per 1-ft	Blows Per 2-ft	Blows Per 3-ft	Blows Per 4-ft	Blows Per 5-ft	Blows Per 6-ft	Total Blows	Blows to Level	Cont. (mR/h)
2	07/28/88	H 1	3	1	3	4			11	56	
2	07/28/88	H 2	3	5	8	10			26	56	
2	07/28/88	H 3	1	2	5	2			10	56	
2	07/28/88	H 4	2	2	7	5			16	56	
2	07/28/88	H 5	2	2	5	2			11	56	
2	07/28/88	H 6	1	1	3	4			9	56	
2	07/28/88	I 1	3	2	5	6			16	58	
2	07/28/88	I 2	2	2	3	5			12	58	
2	07/28/88	I 3	2	3	6	4			15	58	
2	07/28/88	I 4	2	3	3	2			10	58	0.5
2	07/28/88	I 5	0	1	3	5			9	58	
2	07/28/88	I 6	0	1	1	4			6	58	
3	07/28/88	A 1	2	4	4	8			18	26	
3	07/28/88	A 2	1	2	7	7			17	26	
3	07/28/88	A 3	1	2	2	3	3	1	12	26	
3	07/28/88	A 4	2	1	2	2	2	1	10	26	
3	07/28/88	A 5	0	1	7	4			12	26	
3	07/28/88	A 6	0	1	2	5	2		10	26	
3	07/28/88	B 1	1	2	2	1	5		11	69	
3	07/28/88	B 2	1	1	2	2	6		12	69	
3	07/28/88	B 3	1	2	3	3	1	2	12	69	
3	07/28/88	B 4	1	1	2	1	4		9	69	
3	07/28/88	B 5	0	0	2	3			5	69	
3	07/28/88	B 6	0	1	1	1	1		4	69	
3	07/28/88	C 1	1	1	3	6			11	68	
3	07/28/88	C 2	1	2	4	2			9	68	
3	07/28/88	C 3	1	2	3	1			7	68	
3	07/28/88	C 4	1	2	2	3			8	68	
3	07/28/88	C 5	1	2	2	2			7	68	
3	07/28/88	C 6	0	1	1	1	2		5	68	
3	07/29/88	D 1	2	1	4	7			14	54	
3	07/29/88	D 2	1	2	4	5			12	54	
3	07/29/88	D 3	3	5	4	4			16	54	0.5
3	07/29/88	D 4	2	3	5	6			16	54	0.2
3	07/29/88	D 5	0	1	2	3			6	54	
3	07/29/88	D 6	0	1	2	4			7	54	1

APPENDIX VII

Trench	Date	Sect.	Blows Per 1-ft	Blows Per 2-ft	Blows Per 3-ft	Blows Per 4-ft	Blows Per 5-ft	Blows Per 6-ft	Total Blows	Blows Cont. to (mR/h) Level
3	07/29/88	E 1	2	2	3	3			10	62 5
3	07/29/88	E 2	1	3	4	2			10	62
3	07/29/88	E 3	2	2	3	5			12	62
3	07/29/88	E 4	2	2	4	4			12	62 0.5
3	07/29/88	E 5	0	1	1	2			4	62
3	07/29/88	E 6	0	1	2	1			4	62
3	07/29/88	F 1	2	2	5	4			13	57
3	07/29/88	F 2	1	4	8	6			19	57
3	07/29/88	F 3	1	3	5	2			11	57
3	07/29/88	F 4	1	3	5	4			13	57
3	07/29/88	G 1	2	5	5	5			17	57
3	07/29/88	G 2	1	3	3	6			13	57
3	07/29/88	G 3	3	2	2	6			13	57
3	07/29/88	G 4	2	2	3	2			9	57
3	07/29/88	G 5	1	2	4	6			13	57
3	07/29/88	G 6	0	1	3	3			7	57 0.2
3	07/29/88	H 1	2	4	5	7			18	60
3	07/29/88	H 2	1	1	4	8			14	60
3	07/29/88	H 3	1	2	3	4			10	60
3	07/29/88	H 4	1	1	4	6			12	60
4	07/29/88	A 1	2	2	3	4			11	26
4	07/29/88	A 2	1	3	3	6			13	26
4	07/29/88	A 3	1	1	4	2			8	26
4	07/29/88	A 4	1	1	3	3			8	26
4	07/29/88	B 1	1	2	3	4			10	32
4	07/29/88	B 2	1	1	3	4			9	32
4	07/29/88	B 3	1	2	2	4			9	32
4	07/29/88	B 4	1	1	2	5			9	32
4	07/29/88	B 5	0	1	1	1			3	32
4	07/29/88	B 6	0	0	1	1			2	32
4	07/29/88	C 1	1	2	3	6			12	24
4	07/29/88	C 2	1	1	3	2			7	24
4	08/01/88	D 1	2	2	2	6			12	70
4	08/01/88	D 2	2	2	4	4			12	70
4	08/01/88	D 3	2	2	3	4			11	70
4	08/01/88	D 4	1	2	3	3			9	70
4	08/01/88	D 5	0	1	1	2			4	70
4	08/01/88	D 6	0	1	1	3			5	70

APPENDIX VII

Trench	Date	Sect.	Blows Per 1-ft	Blows Per 2-ft	Blows Per 3-ft	Blows Per 4-ft	Blows Per 5-ft	Blows Per 6-ft	Total Blows	Blows Cont. to (mR/h) Level
4	08/01/88	E 1	1	3	4	2			10	59
4	08/01/88	E 2	1	3	3	4			11	59
4	08/01/88	E 3	1	2	3	2			8	59
4	08/01/88	E 4	1	2	3	2			8	59
4	08/01/88	E 5	1	1	2	2			6	59
4	08/01/88	E 6	0	1	1	2			4	59
4	08/01/88	F 1	1	3	3	6			13	62
4	08/01/88	F 2	1	3	2	6			12	62
4	08/01/88	F 3	1	3	2	6			12	62
4	08/02/88	F 4	1	2	2	4			9	62
4	08/02/88	F 5	0	1	1	3			5	62
4	08/02/88	F 6	0	1	1	3			5	62
4	08/02/88	G 1	1	2	2	2			7	77
4	08/02/88	G 2	1	1	2	3			7	77
4	08/02/88	G 3	1	3	1	2			7	77
4	08/02/88	G 4	1	2	2	3			8	77
4	08/02/88	G 5	0	1	1	3			5	77
4	08/02/88	G 6	0	1	1	1			3	77
4	08/02/88	H 1	1	2	3	2			8	
4	08/02/88	H 2	1	2	2	2			7	
4	03/02/88	H 3	0	1	1	3			5	
5	08/02/88	A 1	2	2	2	2			8	31
5	08/02/88	A 2	1	2	2	4			9	31
5	08/02/88	A 3	1	1	1	2			5	31
5	08/02/88	A 4	0	1	1	3			5	31
5	08/02/88	A 5	0	0	1	1			2	31
5	08/02/88	A 6	0	0	1	2			3	31
5	08/02/88	B 1	1	2	1	3			7	69
5	08/02/88	B 2	1	1	1	3			6	69
5	08/02/88	B 3	2	2	3	2			9	69 0.5
5	08/02/88	B 4	1	1	3	3			8	69
5	08/02/88	B 5	0	0	1	2			3	69
5	08/02/88	B 6	0	1	1	1			3	69
5	08/02/88	C 1	2	2	3	2			9	87
5	08/02/88	C 2	1	2	3	3			9	87 0.1
5	08/02/88	C 3	1	2	4	3			10	87 0.2
5	08/02/88	C 4	1	4	4	3			12	87
5	08/02/88	C 5	0	1	3	5			9	87
5	08/02/88	C 6	0	1	2	7			10	87

APPENDIX VII

Trench	Date	Sect.	Blows Per 1-ft	Blows Per 2-ft	Blows Per 3-ft	Blows Per 4-ft	Blows Per 5-ft	Blows Per 6-ft	Total Blows	Blows Cont. to (mR/h) Level
5	08/02/88	D 1	1	3	2	7			13	70
5	08/02/88	D 2	1	2	3	4			10	70
5	08/02/88	D 3	2	2	2	5			11	70
5	08/02/88	D 4	1	3	3	2			9	70
5	08/02/88	D 5	1	1	1	2			5	70
5	08/02/88	D 6	0	1	2	1			4	70
5	08/02/88	E 1	2	2	4	2			10	81
5	08/02/88	E 2	2	2	4	5			13	81
5	08/02/88	E 3	3	3	2	5			13	81
5	08/02/88	E 4	2	2	5	2			11	81
5	08/02/88	E 5	0	1	2	3			6	81
5	08/02/88	E 6	0	1	1	2			4	81
5	08/02/88	F 1	2	3	4	4			13	58
5	08/02/88	F 2	1	2	1	2			6	58
5	08/02/88	F 3	2	3	4	2			11	58
5	08/02/88	F 4	2	3	4	4			13	58
5	08/03/88	F 5	0	1	1	1			3	58
5	08/03/88	F 6	0	0	1	1			2	58
5	08/03/88	G 1	1	4	3	3			11	65
5	08/03/88	G 2	2	2	3	4			11	65
5	08/03/88	G 3	1	1	1	2			5	65
5	08/03/88	G 4	2	1	2	2			7	65
5	08/03/88	G 5	0	1	2	4			7	65
6	08/03/88	A 1	2	4	3	5			14	44
6	08/03/88	A 2	1	2	3	3			9	44
6	08/03/88	A 3	1	2	2	9			14	44
6	08/03/88	A 4	1	2	1	3			7	44
6	08/03/88	A 5	0	1	2	3			6	44
6	08/03/88	A 6	0	0	1	1			2	44
6	08/03/88	B 1	1	2	2	4			9	90
6	08/03/88	B 2	1	2	4	2			9	90
6	08/03/88	B 3	1	2	4	2			9	90
6	08/03/88	B 4	2	2	1	3			8	90
6	08/03/88	B 5	0	0	1	3			4	90
6	08/03/88	B 6	0	0	1	1			2	90

0.3

APPENDIX VII

Trench	Date	Sect.	Blows Per 1-ft	Blows Per 2-ft	Blows Per 3-ft	Blows Per 4-ft	Blows Per 5-ft	Blows Per 6-ft	Total Blows	Blows to Level	Cont. (mR/h)
6 08/03/88	C	1	2	2	3	4			11	83	0.2
6 08/03/88	C	2	1	2	3	2			8	83	1
6 08/03/88	C	3	2	4	3	6			15	83	0.2
6 08/03/88	C	4	1	2	2	4			9	83	0.3
6 08/03/88	C	5	0	1	1	2			4	83	0.5
6 08/03/88	C	6	0	0	1	2			3	83	0.5
6 08/03/88	D	1	1	5	5	11			22	44	
6 08/03/88	D	2	3	2	3	4			12	44	2
6 08/03/88	D	3	2	2	3	5			12	44	
6 08/03/88	D	4	1	2	2	4			9	44	
6 08/03/88	D	5	0	1	2	3			6	44	5
6 08/03/88	D	6	1		1	5			7	44	0.5
6 08/03/88	E	1	1	2	2	6			11	34	
6 08/03/88	E	2	1	2	1	2			6	34	
6 08/03/88	E	3	1	2	3	3			9	34	
6 08/03/88	E	4	1	2	2	4			9	34	
6 08/04/88	F	1	2	2	3	4			11	39	
6 08/04/88	F	2	2	3	3	4			12	39	
6 08/04/88	F	3	2	4	3	4			13	39	
6 08/04/88	F	4	1	2	3	3			9	39	
6 08/04/88	F	5	0	1	1	2			4	39	
6 08/04/88	F	6	0	1	1	1			3	39	
6 08/04/88	G	1	2	4	4	5			15	51	
6 08/04/88	G	2	2	3	4	6			15	51	
6 08/04/88	G	3	4	4	8	7			23	51	
6 08/04/88	G	4	2	3	3	5			13	51	
6 08/04/88	G	5	0	1	3	5			9	51	
6 08/04/88	G	6	0	1	1	3			5	51	
C 08/04/88	A	1	5	7	13				25	35	
C 08/04/88	A	2	6	10	9				25	35	
C 08/04/88	A	3	3	4	5	5			17	35	
C 08/04/88	A	4	4	7	7	7			25	35	
C 08/04/88	A	5	0	2	2	4			8	35	
C 08/04/88	A	6	1	3	8	11			23	35	

APPENDIX VIII

Task Plan for
Site Stabilization and Closure Technology Demonstration

Task Plan Proposal for
Site Stabilization and Closure Technology Demonstration

Brian P. Spalding

Ed C. Davis

Gour-Tsyh Yeh

October 31, 1986

SUMMARY

The basic objective of this task is to carry out a demonstration and evaluation of the stabilization and closure of a waste disposal site at ORNL. A provisional plan for the stabilization and closure of a one acre section of Solid Waste Storage Area (SWSA) 6 is presented. The selected area contains 19 burial trenches of higher activity (>200 mR/hr at package surface) low-level waste and has the advantage, for this demonstration, of being situated in a hydrologically isolable unit on the eastern side of SWSA 6. The provisional stabilization plan will be finalized during the initial twelve months of this task through negotiation and information exchange with U. S. Environmental Protection Agency, Tennessee Department of Health and Environment, the

DOE Low-Level Waste Management Program personnel as well as representatives of Martin Marietta Energy Systems Central Engineering and the ORNL Department of Environmental Management. The provisional plan contains components including trench dynamic compaction, trench grouting, percolation barriers of reinforced chlorosulfonated polyethylene and bentonite, a biointrusion barrier of gravel and cobble, and a graded and vegetationally-stabilized soil cap. Materials and installation costs for this provisional design are estimated to be \$336,000 to be spent in FY 1988. Each component, as well as the system as a whole, will be tested and evaluated during and after completion to verify and, where possible, quantify the degree of hydrologic isolation actually achieved and its long-term stability. By establishing the effectiveness of each component and the integrated system, future planning for corrective actions and stabilization of many ORNL contaminated sites can proceed with the empirical assurance that the various techniques will achieve a performance adequate for site closure and passive long-term stability.

Evaluation of each system component will consist of a combination of geotechnical tests and environmental monitoring. Stability of each of the nineteen trenches will be tested with standard penetrometers before and after their dynamic consolidation. Grouted trenches will be tested for hydrologic isolation by water acceptance tests carried out

at selected wells before and after grouting. The long-term performance of the percolation barrier will be ascertained by placing groundwater tracers in each trench to monitor any downward movement to the water table. Shorter-term evaluation will be based on a site water budget calculated from measurements of runoff, precipitation, and moisture storage in the soil cap. Additional tracers (stable cesium and strontium salts) will be placed directly below the percolation barrier so that any translocation to the forest cover will indicate areas of failure. Water and sediment yields from the soil cap will be monitored to establish erosion rates for estimates of long-term stability. Comparison of these geotechnical parameters with those from a geomorphically stable 'control' area will be included in the task. Additional tests are described within this task plan and will be performed at varying frequencies within a four year period of intensive monitoring following completion of the construction phase.

1. OBJECTIVES

The major objective of this task is to perform a demonstration and evaluation of a stabilization and closure of a portion of a waste disposal area at ORNL. The final stabilization design will incorporate input and comments on a provisional plan by regulatory authorities (USEPA, TDHE, DOE, and NRC) and other MMES suborganizations with a direct

interest in waste site stabilization planning. An ancillary objective is to establish regulatory involvement in the design and planning phases in order to develop a mutual understanding of, and an identification with, the goals and objectives of site stabilization and closure. The field verification of the effectiveness of the proposed stabilization techniques, as well as that of their integrated system, will be the major product of this task. The detailed chronology of the problems encountered and their attempted solutions in the implementation of these techniques should prove quite valuable in the design and planning of future stabilizations and closures of the many ORNL contaminated sites. Obviously, the experience of these techniques on an actual field scale will lead to a great improvement in the estimation of costs for future activities. The continued involvement of and information exchange with regulatory authorities could establish many operational precedents and procedures for future site remediation activities at ORNL. The communal experience gained could translate directly into an organizational confidence in the design and effectiveness of future stabilization projects at all ORNL contaminated sites.

2. BACKGROUND

The ORNL Site Corrective Measures Program is addressing the

problems of corrective actions for many contaminated sites. Although the program is presently in a phase of inventory, characterization, and ranking of these sites, the longer range plan calls for the actual planning and implementation of corrective actions to begin in FY 1989 for some of the higher priority sites. Exactly what will be done, when this implementation stage is arrived at, is presently defined as a consideration and comparison of alternatives. There are several technology development tasks underway considering such techniques as drainage modification, grouting, and in situ vitrification. But practical, operational experience with an integrated system employing these techniques, which will presumably be necessary for any site stabilization and closure, is notably lacking. If more is to be accomplished in FY 1989 than extensive analysis and design activities, then experience in the implementation of these techniques will need to be acquired.

There is considerable experience at ORNL in addressing short-term corrective actions. These activities include subsurface drainage modification in SWSA 6 (Davis and Stansfield 1984), surface runoff diversion in SWSA 4 (Melroy and Huff 1985), in situ grouting of burial trenches (Spalding et. al. 1985), dynamic compaction of burial trenches (Spalding 1986), bentonite surface seal evaluation (Arora et al. 1981), and trench lining with chlorosulfonated polyethylene fabric (Davis and Spalding

1986). Additional corrective action projects, employing in situ grout curtains and asphaltic caps as infiltration barriers at liquid LLW Trench 7, are presently underway. None of these actions, however, has attempted to address long-term stabilization and closure. The implicit objective of site stabilization and closure is a design which yields reasonable assurance of hydrological and biological isolation of interred waste and which requires minimum or, preferably, no maintenance. Thus, system passivity is an implicit performance objective for site stabilization and closure.

3. DESCRIPTION OF WORK

The first phase of this task is to present the provisional design for stabilization and closure to the group of regulatory authorities and advisors which is presently reviewing the entire ERFU program plan in early FY 1987. The area presently considered for this stabilization and closure demonstration is an approximately one acre hillock on the northeastern side of SWSA 6. The area contains 19 low-level waste burial trenches (Figure 1) and, because of its topography, represents a hydrologically isolable and monitorable unit. The provisional stabilization and closure plan was prepared in such detail primarily for an initial estimate of construction costs (Table 1) although the final plan will probably contain many

ORNL-DWG 79- 20420AR5

Figure 1. Map of Solid Waste Storage Area 6, ORNL, showing the location and topographic setting of the 19 trench section for the site stabilization and closure demonstration.

Table 1. Summary of Construction Costs for
Stabilization and Closure of 19 Trench Area, SWSA 6.

Component or Operation	Total Units	Unit Cost	Total Cost
1. Dynamic Compaction (labor P+E)	20,000 ft ²	\$1.86/ft ²	37,200
2. Grouting Trenches			
a. Sodium silicate (materials)	40,000 ft ³	\$2.91/ft ³	116,400
b. Labor (P+E)	40,000 ft ³	\$2.00/ft ³	80,000
3. Backfill/Grading	2,300 yd ³	\$2.50/yd ³	5,750
Compaction (labor)	2,300 yd ³	\$2.17/yd ³	5,000
4. Percolation Barrier			
a. Hypalon (materials)	40,000 ft ²	\$0.25/ft ²	10,000
b. Bentonite mat (materials)	40,000 ft ²	\$0.13/ft ²	5,200
c. Installation labor (subcontract)			30,000
5. Biointrusion Barrier (gravel and spreading)	5,000 yd ³	\$6.00/yd ³	30,000
6. Geotextile Filter Fabric	40,000 ft ²	\$0.10/ft ²	4,000
7. Soil Cap/Cover (labor, free soil)	5,000 yd ³	\$2.50/yd ²	12,500
Total	40,000 ft ² (site area)	\$8.40/ft ²	\$336,050
	200,200 ft ³ (trench volume)	\$1.68/ft ³	

modifications. A subcontract with a project engineering firm, with experience with hazardous waste site remedial actions, will be established in FY 1987 to support ORNL in producing the final design. The provisional design encompasses the deep dynamic compaction of all the trenches, in situ grouting of the resulting compacted trench volumes, and filling the compaction craters and grading to the original land surface. A percolation and biological intrusion barrier will then be constructed as a unit over the entire area of these stabilized trenches (Figure 2). This subsurface percolation barrier is designed to prevent movement of water down the soil profile and contact with buried waste or contamination within the surrounding soil formation. This percolation barrier is protected from burrowing animals and plant roots by a layer of coarse gravel and cobble (nominally 1 m thick). The size of the cobble will preclude its transport or movement by burrowing animals. Above this biobarrier, will be a soil cap or cover which will be planted to grass for immediate erosion control but, ultimately, to trees for a maintenance-free vegetation cover. Its actual thickness and slope will be designed to manage site precipitation between runoff and infiltration. The objective will be to provide adequate soil moisture storage to support the needs of the incipient forest while facilitating site runoff without significant erosion. Rather than wait many years for natural succession to establish the forest, trees of

Figure 2. Drill-top view section of a stabilized landfill cap system showing for

construction from one side only.

about ten-year-old size will be transplanted on the site and species composition will be maintained similar to that of the climax successional stage for the region.

Each component of the system will be tested extensively both during its construction and subsequently in a nondestructive manner by various site monitoring activities. These testing and evaluation methods are summarized in Table 2. Most of the geotechnical tests will be replicated at least four times on each trench. Considerable drilling, augering, and temporary well installing is envisioned in most of these activities. To avoid the compromising protrusion of many well casings from the ground surface and through the various barriers, angle well placement will be used for monitoring and sampling the water table beneath the site. Horizontal neutron probe access tubes will be employed beneath the percolation barrier to detect any moisture variation indicative of barrier failure. Access to these tubes could be gained from either the hillslopes around the site or from a centrally situated deep manhole. Additional moisture monitoring will be achieved by placing neutron probe access tubes into the soil cap but these will not penetrate the percolation barrier. Surface runoff monitoring stations will be constructed around the site to monitor both water and sediment flux from the site in response to individual precipitation events and as an annual flux. Groundwater at the site will be systematically

Table 2. Summary of Testing and Evaluation of
Provisional Site Stabilization and Closure Installation

Component or Process	Testing and Evaluation Methods
1. Dynamic compaction of waste and backfill	1a. Standard penetrometer tests 1b. Bulk density measurements 1c. Ground surface depression surveys
2. Grouting of compacted waste and backfill	2a. Hydraulic conductivity, before and after 2b. Volumetric void filling calculation
3. Dynamic compaction of new soil fill	3a. Bulk density measurements 3b. Standard compaction tests to high limit
4. Chlorosulfonated polyethylene liner	4a. Moisture monitoring via buried neutron probe access tube (horizontal) 4b. Biointrusion via translocation of stable cesium and strontium tracers 4c. Shear strength and puncture testing
5. Bentonite mat	5a. In situ permeability tests 5b. Biointrusion tests as in 4b.
6. Gravel and Cobble	6a. Size distribution testing 6b. Depth profile survey
7. Soil cover	7a. Runoff and sediment yields for erosion measurements 7b. Stored moisture measurement via neutron probe (vertical) 7c. Evapotranspiration via moisture balance 7d. Depth profile survey
8. Vegetation (trees)	8a. Survival + moisture stress of tree species 8b. Above ground biomass and growth measurements
9. Whole system	9a. Groundwater recharge via water table monitoring, before and after 9b. Migration of trench tracers (Na and Li) placed in penetrometer holes 9c. Water budget analysis and hydrologic performance model

monitored by analyses for the tracers placed in the trenches and for the tracers placed directly beneath the cap. Growth of trees will be measured and samples of the tree leaves will be taken on an annual basis from various areas and analyzed for the stable cesium and strontium tracers. These elements are not toxic to the trees and have extremely low ambient background levels in vegetation. Burrowing animal activity will be monitored at the site and nondestructive probing and surveying of the burrows will be attempted to ascertain the effectiveness of the biobarrier.

Hydrologic modeling will play an integrating role in both the design of the final stabilization and closure plan and in performance assessment of the system as determined from the field monitoring. The consequences of various failure scenarios will be simulated with these hydrologic models. Water budgeting of the site will be compared with long-term predictions of forest moisture needs and growth. Soil erosion will be simulated with some models which will be verified by the empirical site erosion measurements.

The working relationship with the advisory group, which hopefully will be developed during the planning stages for the final stabilization and closure design, will be maintained throughout the construction and postconstruction monitoring phases of the project. Continued improvements in the evaluation phase will undoubtedly be needed and the

continued briefing of this group regarding problems and interpretations should prove useful to all parties.

Periodic formal and informal reporting of results will be maintained. The major report on the design, construction, and installation evaluation will be produced at the end of the first quarter of FY 1989.

A breakdown of the various subtask activity costs by fiscal year is presented in Table 3. A schedule for the project is presented in Figure 3.

Table 3.
Subtask Activity Costs by Fiscal Year

Activity	Fiscal Year					
	1987	1988	1989	1990	1991	1992
1. Design, Planning, + Advisory Interactions	120	50	50	50	50	50
2. Field Construction and Support	0	400	0	0	0	0
3. Installation tests and evaluations	120	100	100	0	0	0
4. Monitoring and assessments	60	100	150	175	75	25
5. Hydrologic modeling	0	50	50	25	25	25
TOTAL	300	700	350	200	150	100

TITLE: Site Stabilization and Closure
Technology Demonstration

ACTIVITY NO. _____
189A NO. _____
or
FTP/A NO. _____

4. REFERENCES

Arora, H. S., D. D. Huff, D. S. Ward, and O. M. Sealand. 1981. An assessment of the effect of a bentonite seal on groundwater storage in underlying waste disposal trenches at Oak Ridge National Laboratory. ORNL/TM-7416.

Davis, E. C. and B. P. Spalding. 1986. Field evaluation of a cement-bentonite grout and a chlorosulfonated polyethylene fabric liner in hydrologically isolating low-level radioactive solid waste. ORNL/TM-9742.

Davis, E. C. and R. G. Stansfield. 1984. Design and construction of a French drain for groundwater diversion in Solid Waste Storage Area 6 at the Oak Ridge National Laboratory. ORNL/TM-9014.

Melroy, L. A. and D. D. Huff. 1985. Evaluation of a flow diversion system for reducing ^{90}Sr migration from SWSA 4 to White Oak Creek. ORNL/TM-9374.

Spalding, B. P., L. K. Hyder, and I. L. Munro. 1985. Grouting as a remedial technique for buried low-level radioactive wastes. J. Environ. Qual. 14:389-396.

Spalding, B. P. 1986. Burial trench dynamic compaction demonstration at a humid site. In, Seventh Annual DOE LLWMP Participants' Information Meeting. CONF-8509121. EG&G Idaho, Inc. Idaho Falls, Idaho, pp. 676-698.

APPENDIX IX

Final Plan
for
The Demonstration and Evaluation
of
Stabilization and Closure Techniques
for
Low-Level Waste Burial Trenches
at
Oak Ridge National Laboratory

FINAL PLAN
FOR
THE DEMONSTRATION AND EVALUATION
OF
STABILIZATION AND CLOSURE TECHNIQUES
FOR
LOW-LEVEL WASTE BURIAL TRENCHES
AT
OAK RIDGE NATIONAL LABORATORY

Access to the information in this report is limited to those indicated on the distribution list, to the U.S. Department of Energy and its contractors, to other Government Agencies and their contractors, and to Tennessee Government Agencies.

PREPARED BY:
AUTOMATED SCIENCES GROUP, INC.
800 OAK RIDGE TURNPIKE, SUITE C-102
OAK RIDGE, TN 37830

SEPTEMBER 24, 1987

CAUTION

This document has not been given final patent clearance and is for internal use only. If this document is to be given public release, it must be cleared through the site Technical Information Office which will see that the proper patent and technical information reviews are completed in accordance with Energy Systems Policy.

TABLE OF CONTENTS

IX-3

	<u>PAGE</u>
1.0 INTRODUCTION	1-1
1.1 BACKGROUND	1-1
1.2 OBJECTIVES	1-2
2.0 DESIGN DESCRIPTION	2-1
2.1 DYNAMIC COMPACTION	2-1
2.2 EARTHWORK	2-4
2.3 TRENCH GROUTING	2-4
2.4 NEUTRON PROBE ACCESS TUBES	2-5
2.5 PERCOLATION BARRIER	2-5
2.5.1 Liner	2-6
2.5.2 Environmat	2-6
2.5.3 Bentonite Mat	2-6
2.6 GEO-TEXTILE FABRIC	2-6
2.7 BIO-BARRIER	2-6
2.7.1 Drainage System	2-7
2.8 SOIL CAP	2-7
2.9 SEEDING	2-7
2.10 TREES	2-7
3.0 RATIONALE	3-1
4.0 TRACERS	4-1
5.0 TESTING/MONITORING	5-1
6.0 SCHEDULE	6-1
7.0 COST ESTIMATE	7-1

TABLE OF CONTENTS (Continued)

IX-4

	<u>PAGE</u>
8.0 POTENTIAL SUBCONTRACTORS	8-1
9.0 REFERENCES	9-1
10.0 APPENDICES	10-1

LIST OF FIGURES

Figure 1 Map of SWSA-6	2-2
Figure 2 Stabilization & Closure Demonstration Components . .	2-3

1.1 BACKGROUND

The ORNL Site Corrective Measures Program is currently addressing problems of corrective actions for many contaminated sites. Although the program is presently in a phase of inventory, characterization, and ranking of these sites, the longer range plan calls for the actual planning and implementation of corrective actions to begin in FY-1989 for some of the higher priority sites. There are several technology demonstration tasks underway considering such techniques as drainage modification, dynamic compacting, grouting, and in situ vitrification. Practical, operational experience with an integrated system employing these techniques, which will presumably be necessary for site stabilization and closure, is notably lacking. If more is to be accomplished in FY-1989 than extensive analysis and design activities, experience in the implementation and evaluation of these techniques needs to be acquired. This demonstration and evaluation of stabilization and closure techniques also constitutes the initial closure activities in Solid Waste Storage Area 6 (SWSA-6) as presented in its closure plan (ORNL, 1986). The evaluation of these techniques should aid in planning the closure of additional areas in SWSA-6.

The area chosen for this stabilization and closure demonstration is an approximately one acre hillock on the northeastern side of Solid Waste Storage Area (SWSA) No. 6 and contains 19 trenches. The rationale for choosing this site is as follows:

1. The area is hydrologically isolated from other burial sites in SWSA-6.
2. the area is easy to monitor through a suite of perimeter monitoring wells.
3. Since the most significant vector for water contacting buried waste is by direct infiltration of precipitation, the topographical setting does not necessitate the construction of diversion or cut-off structures to prevent lateral groundwater intrusion. This allows cover evaluation independent of the performance of any drainage modification structure.

4. This area was used for burial of higher-activity low-level waste and represents a significant waste inventory.
5. Stabilization and closure activities in this area will not interfere with, or be compromised, by ongoing waste disposal operations, or traffic, in SWSA-6.
6. Water is available in a nearby impoundment for hydrologic testing and possible cover stress testing via irrigation.
7. The area has been characterized for about a year for prestabilization and closure attributes.

The Resource Conservation and Recovery Act (RCRA) does not provide closure formats and requirements, however, it does impose this responsibility on owners and generators, subject to the approval of the Environmental Protection Agency (EPA) regional administrator. In this case the owner is the Department of Energy (DOE) and the generator is Martin Marietta Energy Systems (MMES). It is anticipated that the evaluation of the techniques employed in this demonstration will provide the rationale for what will work in most of the SWSA's at ORNL. Although this demonstration will stabilize and close a small section of SWSA-6 it will not necessarily dictate the degree of stabilization and closure required for most waste trenches.

1.2 OBJECTIVES

The major objective of this project is to perform a demonstration and evaluation of stabilization and closure techniques on a portion of a waste disposal area at ORNL. An objective of this activity is to establish regulatory involvement in the design and planning phases in order to develop a mutual understanding of, and an identification with, the goals and objectives of site stabilization and closure. The field verification of the effectiveness of the proposed stabilization techniques, as well as that of their integrated system, will be the major product of this project.

The implicit objective of site stabilization and closure is a design which yields reasonable assurance of hydrological and biological isolation of interred waste and which requires no maintenance.

The area chosen for this stabilization and closure demonstration is an approximately one acre hillock on the northeastern side of Solid Waste Storage Area (SWSA) No. 6. The area contains 19 low-level waste burial trenches (Figure 1) and, because of its topography, represents a hydrologically isolable and monitorable unit.

The Final Plan encompasses the dynamic compaction of all 19 trenches, grading the 5 most easterly trenches to a specific shape and slope, backfilling and compacting the remaining 14 trench craters, in situ grouting of the 5 easterly trenches, construction of a percolation and biological intrusion barrier over the 5 grouted trenches, and covering the 14 trench area with a surface plastic sheet to prevent recharge of the 5 trench area during the 4 year monitoring period. Figure 2 depicts the components, and the order in which they are placed, of the closure design.

2.1 DYNAMIC COMPACTION

Dynamic compaction of waste contained in each trench will be accomplished by dropping a 4 ton cylindrical weight, from a crane, on the trench from a height of 25 to 50 feet. The trench corners will be located and staked by the Company. The drop pattern will be in the form of a square approximately 10 feet by 10 feet. The corners of the square will be compacted first, followed by the center, by dropping the weight in one place until penetration is negligible as determined by the company field engineer. He also determines the height, from which the weight is dropped, by the amount of penetration achieved by the weight on each drop. Each trench is approximately 10 feet wide by 50 feet long and 15 feet deep. There is approximately 10 feet of waste at the bottom of each trench with 3 to 5 feet of cover soil over the waste. From past dynamic compaction operations reduction of waste volume has been as great as 64%. (Ref. 1)

ORNL-DWG 79-20470A05

Figure 1. Map of Solid Waste Storage Area 6, ORNL, showing the location and topographic setting of the 19 trench section for the site stabilization and closure demonstration.

Figure 2

STABILIZATION and CLOSURE DEMONSTRATION COMPONENTS

IX-9

For Design purposes, reduced waste volume was assumed to be 50% and is considered conservative. Therefore, it is expected that the average reduction in top-of-trench elevation will be 5 feet.

2.2 EARTHWORK

Upon completion of the dynamic compaction operation the noncompacted soil surrounding the 5 most easterly trenches will be cut to the level of the top-of-trench elevations, shaped and sloped to provide drainage. The soil removed in this operation will be used to backfill the trench craters of the other 14 trenches. This backfill will be compacted to maximum density and the whole site will be seeded and mulched. Clearing and fence removal will be required in the vicinity of the 5 trench area so as to achieve non-eroding slopes. Silt fencing will be installed in this area also. The site will remain in this condition for approximately 12 months while in situ grouting and subsequent testing of the 5 trenches is performed, primarily by MMES.

The next earthwork activity will occur after selected trenches have been grouted and the grout verification testing is complete. The site will be cut/filled/compacted in accordance with the plans and specifications.

The soil placed over the percolation and intrusion barrier will be applied in 8 inch lifts with each lift compacted. Soil from a SWSA-6 or nearby borrow pit will be used as required.

2.3 TRENCH GROUTING

Further stabilization of the 5 most easterly trenches will be accomplished by in situ grouting. The grout specified is AV-100 Chemical Grout, or equivalent, as distributed by Avanti International. This is an acrylamide base grout which allows a wide range of gel set time and has excellent dispersion capability. (Ref. 2) The approximate void volume within each of the 5 selected trenches will be determined by water injections. The

grout will be injected in such a manner as to completely fill all voids within and surrounding the compacted waste. Intra trench observation wells will be monitored during grout injection to verify dispersion of grout within each of the 5 trenches.

2.4 NEUTRON PROBE ACCESS TUBES

Neutron probe access tubes will be placed beneath the percolation barrier horizontally to detect any moisture variation indicative of barrier failure. These tubes will be placed horizontally and surface on the northerly and southerly sideslopes. When not in use they will be plugged with end caps. The tubes will be 1.55" I.D. aluminum and be placed approximately 12 inches below the liner.

2.5 PERCOLATION BARRIER

The percolation barrier is comprised of three materials; 1) a High Density Polyethylene (HDPE) membrane liner, 2) a bentonite mat (Enviromat), and 3) a layer of high swelling Wyoming bentonite. This system is designed to provide a primary and secondary barrier to percolating surface water. The HDPE liner will be placed on a 6" sand bed which covers the compacted soil over the trenches. The Enviromat will be placed directly on the liner with a 6" layer of bentonite placed directly on the Enviromat. The bentonite will be sprayed with a commercially available root inhibitor and immediately covered with a geo-textile fabric. Another 6" layer of sand will then be placed over the geo-textile fabric. The bentonite is confined between the liner and the geo-textile fabric thereby creating a watertight seal upon wetting of the bentonite. Any expansion of the bentonite layer will be absorbed by the sand bed overlaying the bentonite due to sand upsurging into void spaces created by the rip-rap bio-barrier which is placed on the sand.

2.5.1 Liner

IX-12

The liner specified is 60 mil thick HDPE, equivalent to "Gundline HD" as manufactured and installed by Gundle Lining System, Inc. See specifications for details on the liner, its installation and verification.

2.5.2 Enviromat

Enviromat is a bentonite-impregnated non-woven geotextile manufactured by International Minerals and Chemical Corporation. See specifications for details.

2.5.3 Bentonite

The bentonite specified is a high swelling Wyoming bentonite.

2.6 GEO-TEXTILE FABRIC

The geo-textile fabric specified is a non-bio-degradable and nonwoven fabric such as Construction Fabric 4561 as manufactured by Amoco. This fabric will be installed in two places; 1) over the bentonite layer, and 2) over the bio-barrier. This fabric is permeable and performs a material separation function only.

2.7 BIO-BARRIER

The bio-barrier will consist of 3 feet of 6" diameter, and larger, cobble stones and gravel placed directly on the sand layer which covers the bentonite. Gravel will be placed on top of the cobble to fill voids and provide a smoother surface on which to place a geo-textile fabric. The bio-barrier is designed to prevent intrusion of burrowing animals. Because of its negligible water-holding capacity, it will also aid as a barrier to plant root intrusion.

2.7.1 Drainage System

IX-13

The bio-barrier serves a secondary purpose in providing the necessary voids to drain percolating water to a perimeter drainage pipe and then to a catch basin for quantification and qualification during the 4 year monitoring period succeeding construction.

2.8 SOIL CAP

The soil cap will consist of 3' or more of spoil left over from previous earthwork and make-up soil from a borrow pit located at, or near, SWSA-6. The cap will be placed in 8" lifts with each lift compacted to a density specified by the soil consultant. A ditch, as shown on the plans shall be cut around the perimeter of the site to catch and transport rain water run-off to a catch basin to allow monitoring.

2.9 SEEDING

Immediately upon Company approval of the soil cap, the site will be seeded and mulched so as to minimize erosion. Seed will be Kentucky 31 Fescue applied at a rate of 100 pounds per acre. All disturbed areas shall be seeded. Mulch shall be applied immediately after seeding and wetting.

2.10 TREES

Rather than wait many years for natural succession to establish a forest cover, trees of various ages will be transplanted to the site. Species composition will be maintained similar to that of the climax successional stage for the region.

The purpose of this section of the plan is to provide the rationale for those design items which differ significantly from an earlier provisional plan. Some of the differences are a result of the lack of detail in the provisional conceptual plan and some are the result of recent research exposing a wider choice of material and methods.

Briefly, the major differences are as follows:

- o Cutting surrounding natural ground to top-of-trench elevations after dynamic compacting is being done to minimize the effects of trench subsidence on the HDPE liner.

Past reports indicate the major cause of liner failure is trench subsidence which allows excessive tensile forces to exceed the liner capability. With fill soil surrounding and covering the trenches, compacted to optimum density, the potential for liner failure due to trench subsidence is minimized. This surface grading will also facilitate grout and drilling equipment placement during grouting operations. The provisional plan proposed backfilling and compacting the trenches to the original elevations and then adding the percolation and bio-barriers and soil cap.

- o HDPE Liner - The provisional plan proposed Hypalon for the membrane liner. The Gundle HDPE liner has greater elongation and puncture resistance properties.
- o Enviromat - The Enviromat was added as a protective cover to the HDPE liner during construction. It will also function as an independent percolation barrier to the HDPE liner below and the loose bentonite above.

- o Root Inhibitor - Since the site will eventually be allowed to re-vegetate and large trees will be part of the vegetation, a means of preventing root intrusion into the waste layers was investigated. Copper sulfate is the foremost ingredient in all effective root inhibitors. Ideally, an ion exchange will occur between the copper sulfate and elements in bentonite such that the resultant compound will be a long-term deterrent to root growth, should roots penetrate to the bentonite layer. At this writing it is not known if an ion exchange will occur between copper sulfate and bentonite. Laboratory experiments will be conducted during the regulatory review period to determine the feasibility of this approach. Solution concentration and dosage rate will also be determined by laboratory analysis.
- o Grout - The provisional plan proposed using sodium silicate as the waste stabilization agent. After evaluation of recent grouting experience at ORNL, it was determined that an acrylamide agent would be considerably more effective. The primary characteristic which makes acrylamide advantageous is its low viscosity which is very near that of water. This will allow a much higher confidence in the grout performance because of the hydrodynamic dispersibility of the acrylamide agent. Its disadvantage is in its cost.

4.0 TRACERS

IX-16

The long-term performance of the percolation barrier will be ascertained by placing groundwater tracers in selected trenches to monitor any downward movement to the water table. A total of 13 water table wells have been recently installed on site to facilitate groundwater monitoring. Additional tracers (stable cesium and strontium salts) will be placed directly below the percolation barrier so that any translocation to the forest cover will indicate areas of failure. All tracer placement and monitoring will be performed by the Company.

The specifications, included in this plan, dictate the testing of materials and/or installations required to verify each stage of the construction activities. This section describes additional testing and monitoring not included in the specifications. This additional testing, for the most part, will be performed by the Company.

Each component of the system will be tested extensively both during its construction and subsequently in a nondestructive manner by various site monitoring activities. These testing and evaluation methods are summarized in Table 1. Most of the geotechnical tests will be replicated at least four times on each trench. Considerable drilling, augering, and temporary well installing is envisioned in most of these activities. To avoid the compromising protrusion of many well casings from the ground surface and through the various barriers, angle well placement will be used for monitoring and sampling the water table beneath the site. Pressure transducers and sampling tubes will be fitted in existing monitoring wells and routed to the sides of the site. This will allow continued monitoring without potentially compromising the area cap. Horizontal neutron probe access tubes will be employed beneath the percolation barrier to detect any moisture variation indicative of barrier failure. Additional moisture monitoring will be achieved by placing vertical neutron probe access tubes into the soil cap, but these shallow tubes will not penetrate the percolation barrier. Surface runoff monitoring stations will be constructed around the site to monitor both water and sediment flux from the site in response to individual precipitation events and as an annual flux. Groundwater at the site will be systematically monitored for tracers placed in the trenches and for the tracers placed directly beneath the cap. Growth of trees will be measured and samples of the tree leaves will be taken on an annual basis from various areas and analyzed for stable cesium and strontium tracers. These

Table 1. Summary of Testing and Evaluation of
Site Stabilization and Closure Installation

IX-18

Component or Process	Testing and Evaluation Methods
1. Dynamic compaction of waste and backfill	1a. Standard penetrometer tests 1b. Bulk density measurements 1c. Ground surface depression surveys
2. Grouting of compacted waste and backfill	2a. Hydraulic conductivity, before and after 2b. Volumetric void filling calculation
3. Dynamic compaction of new soil fill	3a. Bulk density measurements 3b. Standard compaction tests to high limits
4. HDPE liner	4a. Moisture monitoring via buried neutron probe access tube (horizontal) 4b. Biointrusion via translocation of stable cesium and strontium tracers 4c. Shear strength and puncture testing
5. Bentonite mat	5a. In-situ permeability tests 5b. Biointrusion tests as in 4b
6. Gravel and Cobble	6a. Size distribution testing 6b. Depth profile survey
7. Soil cover	7a. Runoff and sediment yields for erosion measurements 7b. Stored moisture measurement via neutron probe (vertical) 7c. Evapotranspiration via moisture balance
8. Vegetation (trees)	8a. Survival + moisture stress of tree species 8b. Above ground biomass and growth measurements
9. Whole system	9a. Groundwater recharge via water table monitoring, before and after 9b. Migration of trench tracers (Na and Li) placed in penetrometer holes 9c. Water budget analysis and hydrologic performance model

elements are not toxic to the trees and have extremely low ambient background levels in vegetation. Burrowing animal activity will be monitored at the site and nondestructive probing and surveying of the burrows will be attempted to ascertain the effectiveness of the bio-barrier.

Hydrologic modeling will play an integrating role in both the design of the final stabilization and closure plan and in performance assessment of the system as determined from the field monitoring. The consequences of various failure scenarios will be simulated with these hydrologic models. Water budgeting of the site will be compared with long-term predictions of forest moisture needs and growth. Soil erosion will be simulated with some models which will be verified by the empirical site erosion measurements.

6.0 SCHEDULE

IX-20

6.1 FISCAL YEAR 1988

	'87 O N D	'88 J F M A M J J A S
Dynamic Compaction	^-----^	
Cut & Grade		^-----^
Pentetration Testing (Trenches)	^-----^	
Trench Grouting		^-----^
Hydraulic Testing		^-----^

STABILIZATION & CLOSURE DEMONSTRATION PROPOSED CONSTRUCTION SCHEDULE

	'88			'89								
	O	N	D	J	F	M	A	M	J	J	A	S
Neutron Tubes, Fill & Grade, Compact Liner Instl.	^-----^											
Bentonite/Bio-Barrier												
Soil Cap/Seeding												
Clean Up/Move Out												

STABILAZATION AND CLOSURE
DEMONSTRATION

PROPOSED CONSTRUCTION SCHEDULE

7.0 COST ESTIMATE

IX-22

<u>ACTIVITY</u>	<u>UNITS</u>	<u>QUANTITY</u>	<u>UNIT COST</u>	<u>TOTAL COST</u>
1. Dynamic Compaction	Sq. Ft.	13,100	\$1.86	\$24,366
2. Grouting (5 trenches)	Cu. Ft.	6,700	42.50	284,750
3. Earthwork				
a. Cut	Cu. Yd.	980	2.50	2,450
b. Fill (Incl. soil cap)	Cu. Yd.	2,861	2.50	7,153
c. Compaction	Cu. Yd.	2,861	2.17	6,208
4. Percolation Barrier				
a. HDPE Liner	Sq. Ft.	13,800	1.23	16,974
b. Enviromat	Sq. Ft.	13,800	.60	8,280
c. Bentonite	Ton	242	189.00	45,738
d. Sand	Cu. Yd.	511	10.00	5,110
e. Root Inhibitor	Gal.			2,500
5. Bio-Barrier				
a. Rip-rap	Cu. Yd.	1,227	7.50	9,203
b. Gravel	Cu. Yd.	307	10.00	3,070
6. Geo-textile Fabric	Sq. Ft.	27,600	0.19	5,244
7. Seeding/Mulch	SY.	5,555	1.53	8,500

<u>ACTIVITY</u>	<u>UNITS</u>	<u>QUANTITY</u>	<u>UNIT COST</u>	<u>TOTAL COST</u>
8. Drainage System	L.S.	---	---	7,500
A. 6" perforated pipe				
b. 6" solid pipe				
c. 1 1/2" river gravel				
d. Surface ditching				
e. Catch Basin				
f. 10" solid pipe				
g. Rip rap pad				
TOTAL ESTIMATED COST				<hr/> \$437,046

8.0 POTENTIAL SUBCONTRACTORS

IX-24

8.1 Earthwork/General

- a. Gaiter Construction Co.
P. O. Box 14005
Knoxville, TN
(615) 524-4944
- b. Blaine-Hays Construction Co.
9047 Executive Park, Suite 206
Knoxville, TN
(615) 693-0575
- c. A. B. Long Construction Co.
6416 Deane Hill Dr.
Knoxville, TN
(615) 588-0661

8.2 Grouting

- a. Northwest Specialities
33 Yorkshire Dr.
Oak Brook, IL 60521
(312) 533-6644
- b. Hayward Baker Co.
1875 Mayfield Rd.
Odenton, MD 21113
(301) 551-8200
- c. W. G. Jaques Construction Co.
2183 N.W. 86th St.
Des Moines, IA 50322
(515) 276-5464

8.3 HDPE Liner

IX-25

- a. Gundle Lining Systems, Inc.
1340 E. Richey Rd.
Houston, TX 77073
(713) 443-8564
- b. Rouse Construction Co.
9050-B Executive Park Dr.
Knoxville, TN
(615) 690-4312
- c. Geo-Con, Inc.
P. O. Box 17380
Pittsburgh, PA 15235
(412) 244-8200

9.0 REFERENCES

IX-26

1. B. P. Spalding, "Proceedings of the Seventh Annual Participants' Information Meeting", DOE Low-Level Waste Management Program, CONF-8509121, pp. 676-698.
2. B. P. Spalding, S. Y. Lee, C. D. Farmer, L. K. Hyder, "Demonstration of In situ Immobilization of Buried Transuranic Waste using Acrylamide Grout", September 1986, RAP 86-69.
3. B. P. Spalding, L. K. Hyder, I. L. Munro, "Grouting as a Remedial Technique for Buried Low-Level Radioactive Wastes, Journal of Environmental Quality", Vol. 14, No. 3, July-September 1985.
4. ORNL/TM-9877, "Characterization Plan for Solid Waste Storage Area 6", Pub. No. 2638, December 19, 1985.
5. "Draft Closure Plan for Solid Waste Storage Area Six," Oak Ridge National Laboratory, Oak Ridge, Tennessee, ORNL/SUB/86-72127/1, 1986.

10.0 APPENDICES

10.1 APPENDIX 1
DRAWINGS

APPENDIX X

Correspondence with
The State of Tennessee
Department of Health and Environment
and
The United States
Environmental Protection Agency

STATE OF TENNESSEE
DEPARTMENT OF HEALTH AND ENVIRONMENT
1605 PROSSER ROAD
KNOXVILLE, TENNESSEE 37914-3434

February 1, 1988

Mr. W. Nelson Lingle
Department of Energy
Research and Waste Management Division
Waste Management Branch
P. O. Box E
Oak Ridge, TN 37831

RE: Tennessee Department of Health and Environment (TDHE) Review of Draft
Plan for the Test Area Remedial Action (TARA) at ORNL. ORNL/RAP-42

Dear Mr. Lingle:

The Tennessee Department of Health and Environment (TDHE) has appreciated the opportunity to review the above referenced document. Associated with the TARA project were the review of the additional documents: (1) Environmental ALARA Memorandum for the Core Sampling, Trench 150, Solid Waste Storage Area (SWSA) 6; (2) Closure Technology Demonstration, 19 Trench Section, SWSA 6 - Action Description Memorandum, and (3) Brian P. Spalding's November 2, 1987 White Paper on questions concerning the filling of selected trenches with water at the SWSA 6 Test Area for Remedial Actions (TARA).

As previously noted in my letter to you of December 29, 1987, the Division of Solid Waste Management has determined that the activities outlined in the Draft TARA Plan are not approved as meeting initial RCRA closure in SWSA 6 and the Department of Energy (DOE) will need to modify the RCRA closure plan for SWSA 6. It is important that DOE and ORNL give the SWSA 6 Closure Plan and schedule a high priority.

DOE and Martin Marietta is advised to discontinue the injection of water or other fluids into waste trenches for hydraulic conductivity and volumetric void filling calculations. This practice represents the potential for "flushing" of radioactive and/or hazardous materials from the trenches into the surrounding environment including groundwater. TDHE will be available to assist DOE and Martin Marietta Energy Systems in selecting acceptable alternatives for making void filling calculations.

TDHE recognizes the importance of selecting the best available technologies for the effective closure of SWSA 6. The TARA project as a demonstration could with some modification help to serve that purpose. General and specific comments are enclosed for DOE's review and consideration.

RECEIVED

FEB 04 1988

L. POBLES

ID

FILE TIC

Mr. W. Nelson Lingle

Page 2

February 1, 1988

X-3

If you have questions or need clarification please feel free to contact
Gay Hashbarger or me.

Sincerely,

Earl C. Leming

ECL:GIH:pjm DWM3C

Attachment

cc: Wayne Hibbitts
Mike Mitchell
✓ Lanny Bates
Dave Hopkins

General comments and questions concerning the TARA Plan include:

- (1) Page 1-1: How were the priorities determined for corrective actions?
- (2) Page 1-1: It is unclear how the initial TARA activities will mesh with the closure plan for SWSA 6.
- (3) Page 1-1: Does data collected to date assure hydrologic isolation from the other burial sites, or merely indicate that such a condition is likely to exist?
- (4) Page 1-1: The fact that the most significant vector for infiltration is vertical does not preclude a horizontal influence. Please address this possibility.
- (5) Page 2-1: The liquid content in the trench or in the waste in the trenches is not documented. It appears that dynamic compaction has the potential to release liquids that may exist in some of the containers. Address this issue.
- (6) Page 2-1: Why cap only 5 of the trenches? How will the 5 trenches be hydrologically (both surface and ground) separated from the remaining 14 trenches? Why was the retaining wall deleted?
- (7) Page 2-4: The injection of fluids during grouting may constitute an injection under State or Federal UIC regulations. Has this been considered as a permitting requirement?
- (8) Page 2-4: Reference paragraph 3 regarding the measurement of void volumes by water injection. This method is unacceptable to TDHE.
- (9) Page 2-4: Has the soil over the 5 trenches, that is to be used to backfill the craters of the remaining 14 trenches been sampled for hazardous or radioactive contamination?
- (10) Page 2-4:
Page 2-5,
and Page 3-2 Does the acrylamide base grout contain a monomer which is toxic? Given the proximity to the Emergency Waste Basin and a creek which flows into White Oak Lake, what measures will be taken to prevent possible

release of contaminants to surface or ground water? Does the grout contain any other toxic constituents which might be released to surface or ground waters? X-5

(11) Page 2-4:

Provide specifics regarding, "grout verification testing" method(s).

(12) Page 2-5:

Given that numerous wells are to be installed, i.e. intra trench observation wells, etc..., will membrane of plastic be placed beneath and around drilling rigs to minimize any dispersion of liquids and facilitate site clean-up?

(13) Page 2-5:

Should the removal of any liquids or contaminated soil from the trench occur during drilling or other operations, how will these be handled?

(14) Page 2-5:

Why was 6 inches of bentonite selected instead of clay?

(15) Page 2-5:

When the swelling of the 6 inches of bentonite occurs will adequate expansion of the geo-textile fabric be available to prevent tearing or ripping? How would this be monitored or detected?

(16) Page 2-5:

Why not use the neutron probes at different levels?

(17) Page 2-7:

Re: 2.8 Soil Cap, where in the plans is the drainage ditch illustrated? To what plans does this sentence refer?

(18) Page 2-7:

What will be the final slope of the cap? What will be the stability of the cap, given the steepness of the current outcrops? Will the cap remain in place permanently? If not, how long is it expected to remain in place? What is the final fate of the cap?

(19) Page 2-7:

What parameters will be monitored for the surface waters carried by the ditch?

(20) Page 2-7:

Kentucky 31 Fescue alone is inadequate. A quickly establishing annual rye and a legume should be included, species dependent upon season of seeding. Annual evaluation of vegetative success and annual fertilization should be included in the plan.

(21) Page 2-7 and Page 3-2:

The establishment of trees on this cap is unacceptable. If trees are to be evaluated it should occur on a "cold" demonstration site where the consequences will not potentially be environmentally harmful.

- (22) Page 4-1: Additional information is needed regarding the specifications of the monitoring system. This is particularly important for the angled monitoring wells.
- (23) Page CV-1.3:
7 of 12 The mulch rates are inadequate at 100 lb/1000 ft². They should be 3 to 4 times the suggested rate.
- (24) General Has EPA commented on the 3004(u) impact of this project?
- (25) General An alternative cap-cover that provides high run-off and low infiltration is suggested in NUREG/CR-4918 Vol. 1, Control of Water Infiltration into Near Surface LLW Disposal Units, by R. K. Schulz, R. W. Ridky, and E. O'Donnell. How does the proposed TARA cap compare?

GIH:pjm DWM3C

OAK RIDGE NATIONAL LABORATORY

OPERATED BY MARTIN MARIETTA ENERGY SYSTEMS, INC.

POST OFFICE BOX X
OAK RIDGE, TENNESSEE 37831

March 10, 1988

Mr. Rodger A. Jump
Waste Management Branch
Department of Energy, Oak Ridge Operations
Post Office Box E
Oak Ridge, Tennessee 37831

Dear Mr. Jump:

Response to TDHE Comments on the TARA Plan

Enclosed are individual responses to the comments from the Tennessee Department of Health and Environment (TDHE) on the Test Area for Remedial Actions (TARA) Plan as contained in the letter from Earl C. Leming to Mr. W. Nelson Lingle dated February 1, 1988. Please forward this response to TDHE as appropriate.

Major issues identified in the TDHE comments will be discussed during the March 16, 1988, meeting with TDHE and Environmental Protection Agency in Chattanooga, Tennessee. Therefore, the enclosed material provides information regarding the content of those discussions. If you have questions or concerns, please let us know as soon as possible. Other comments addressing minor technical details can be handled sufficiently through transmission of this response.

If you have any questions, please do not hesitate to call either myself (6-4438) or Brian Spalding (4-7265).

Sincerely,

L. D. Bates, Manager
Remedial Action Program

LDB:mse (E031088)

Enclosure

cc/enc: H. M. Braunstein
K. W. Cook
H. R. Gaddis
R. A. Jump
J. R. Lawson
L. W. Long

L. E. McNeese
T. E. Myrick
C. E. Nix
T. P. Perry
P. S. Rohwer
B. P. Spalding
F-TARA Demo

TDHE Comments and Replies 1

March 9, 1988

To: L. D. Bates

From: B. P. Spalding

Reply to TDHE Review of the TARA Plan

The TARA closure techniques demonstration project is a phased approach to testing trench stabilization techniques. The project involves three distinct phases in sequence: dynamic compaction, grouting, and covering. By the very nature of the activity, the task does not lend itself to either a rigid schedule or extreme procedural detail as might be expected in an actual closure plan for a waste site. Each phase has a flexible schedule for its implementation imposed by the necessity to evaluate the effectiveness of that phase before planning details of a subsequent phase. Each phase will generate information that will be needed to plan the subsequent phase. For instance, we cannot provide final design of the area cap until we know the final elevation of the graded site which will depend on how deep our dynamic compaction proceeds. Nor can we be specific about the volume of grout, which will be required, until we determine the residual voids within the compacted trenches. Because the project is, in essence, an evaluation of stabilization and closure techniques and not a closure demonstration, the task plan will remain a living document with only as much detail as reasonable given that we will not know the effectiveness of the various techniques until they are completed.

Getting a consensus or approval for all issues and concerns, which we do not believe is required, from the regulators will take considerable time. We still have not heard from EPA although they were sent copies of the plan on October 21, 1987. For now, we can address in depth only the TDHE comments. We sincerely appreciate the time and effort on their part in providing these comments. They have identified a number of regulatory and institutional concerns with the proposed actions, all of which we will be facing in the larger venture of actual site closures in the near future. We believe that all of these issues and concerns have been addressed herein and we should be allowed to proceed with these critical activities. As pointed out in detail in some these replies, we must assume some risk in proceeding with these activities to gain the benefit of learning their effectiveness. Otherwise, we will have to face the same issues when we propose actual closure methods for our waste sites and still have no data or experience from which to answer them.

TDHE Comments and Replies 2

I have grouped the TDHE comments by phase and suggest that we proceed with the planned activities when we have satisfied ourselves as to their resolution. The specific TDHE comments have been quoted below, prior to each reply, so that an interested reader does not have to divide his/her attention between two documents.

Dynamic Compaction Phase

(5) "The liquid content in the trench or in the waste in the trenches is not documented. It appears that dynamic compaction has the potential to release liquids that may exist in some of the containers. Address this issue."

I will address the easiest part of this comment first. We have placed a monitoring well into each trench about a year ago. At that time (February 1987), we observed standing water in only three trenches but only of nominal depth (less than 1 foot). During the following spring and summer, this standing water disappeared in all these trenches. Water filling measurements later that year inundated seven trenches with water. This water seeped away within two weeks of filling and the trenches returned to their unsaturated condition. Thus, at the time we had originally planned to initiate compaction (October 1987), the trenches would have been free of standing water. When we finally initiate compaction, we anticipate similar unsaturated conditions.

The more difficult part of this comment centers on potential release of liquids in the waste within the trenches due to dynamic compaction. I believe that we will all agree that any containers, for liquids or solids, will be destroyed by dynamic compaction. Thus, any contained liquids will no longer be contained after dynamic compaction. Thus, the issue reduces to assessing just how much contained liquid might be in these trenches and, if present, what the consequences of loss of containment might be. Let's go at these questions in order.

How much liquid is likely to be in containers in these trenches? Probably, there is not much! The reason I reach this conclusion is based largely on the operation of ORNL radioactive solid waste disposal system at the time these trenches were being used. The first trench (No. 2) was opened on November 2, 1972 and the last trench (199) was closed June 16, 1976 at the TARA site. During this interval ORNL's radioactive liquid waste disposal system was operational and accessible through a cost-free (to the user) drain system. Not only were potential generators provided with free bulk liquid disposal in their labs, but disposal of bulk liquids was prohibited for solid waste disposal as described in waste management practices at that time (ORNL-CF-72-9-1). We are reviewing the 602 disposal records (UCC Form 2822) of waste shipments to these 19 trenches in an effort to identify how many might have contained aqueous or nonaqueous

TDHE Comments and Replies 3

liquids. At best, this exercise will probably yield qualitative confirmation of the 'not much' liquid character of its contained waste. These records lack much detail with many entries reading 'miscellaneous junk'. In addition, bulk quantities of contaminated solvent were disposed into auger holes in other areas of SWSA 6. Thus, it is extremely likely that this area does not contain bulk quantities of aqueous or nonaqueous liquids. However, that does leave open the possibility that these trenches may contain small or incidental quantities of both aqueous or nonaqueous liquids within small containers or vials. But again, there is probably not much of this in the area either.

The area was reserved for higher level low-level (>200 mrem/hr at the package surface) solid waste. The area was, and still is, high and dry; it is generally over thirty feet to the water table at most places at the TARA site. Thus, the higher-level waste was disposed there in an effort to keep it out of groundwater. Thus, the bulk of lower level waste (e.g., scintillation vials which are contact handled) would likely end up in other areas of SWSA 6 used for disposal of <200 mrem/hr waste. Sampling of trench leachate (i.e., standing water) in low-level trenches in other areas of SWSA 6 in 1986 by Solomon et al. (RAP/LTR-87/37) detected the presence of dissolved organics in the mg/L range for several but not all trenches. Notably, all were at least an order of magnitude below their solubility limit indicating that no large amount of these liquids was present in these trenches. Detected compounds were often characteristic of scintillation fluids (naphthalene, toluene, ethylbenzene, etc.). As pointed out above, scintillation vials would not be an expected component of higher-level waste in the TARA trenches. Nevertheless, residual fluids and solvent may be present in the TARA trenches in small quantities in disposed labware from hotcell operations and other waste.

What might be the consequences of releasing these minor amounts of aqueous fluids or solvents during dynamic compaction? An instantaneous release of fluid at the trench floor during compaction is likely to be adsorbed by the soil backfill within the trench which would likely be in an unsaturated condition. However, the adsorbed fluid is free to mix and move via advection with percolating water subsequent to compaction. How long would it take for a dissolved fluid to reach the watertable approximately 20 feet below the trench floor? Probably several years even if compaction were the sole step in stabilizing these trenches. But we plan to grout these trenches and cap all the trenches within one year of completing compaction. In theory, therefore, fluid movement to the watertable would then be solely by diffusion because the cover would prevent further advection of water through the trench. In addition, the grouting would encapsulate residual material within the trench. In the brief time between the compaction phase and the grouting plus capping phases, released fluids could move under unsaturated conditions. Unsaturated conditions means hydraulic conductivities very much

TDHE Comments and Replies 4

lower than saturated (about 10^{-5} cm/sec) and extremely small hydraulic gradients, i.e., little movement.

It is also important to realize that we would not be taking the small risk of fluid releases blindly. There is a suite of 15 groundwater monitoring wells within and around the TARA site. These wells have been sampled for hazardous constituents but analyses have not yet been completed. Radiochemical analyses have indicated that they contain low levels of tritium as do just about all groundwater samples in SWSA 6. We will have a good understanding of groundwater contamination before dynamic compaction. We plan to sample these wells periodically during the life of the project to observe how water quality may change. Hopefully, we will observe no deterioration but, if any is observed, we can collect groundwater as needed. Wells in this area are extremely low yield (i.e., less than 50 liters per day) so collection would not be a significant expense were it required.

Thus, based on available disposal records and disposal practices in use in SWSA 6 at the time the trenches at TARA were filled, it is unlikely that significant amounts of liquids were disposed there in any type of container. Although the risks may be greater in other areas of SWSA 6, the risk of container destruction releasing detectable amounts of fluids would appear to be very small at TARA. The benefit from taking such a risk is substantial. We will gain the technical evidence that dynamic compaction can or cannot obviate trench subsidence. In addition we will determine the compatibility of grouting with dynamic compaction so that we can save enormous amounts of money by not having to purchase grout to fill large trench voids which can be cheaply and effectively eliminated by dynamic compaction. If the combination of dynamic compaction and grouting proves successful in this low-risk area of SWSA 6, then we will have a good position to evaluate whether to apply the technique to higher risk areas of SWSA 6.

(8) "Reference paragraph 3 regarding the measurement of void volumes by water injection. This method is unacceptable to TDHE."

The comment is moot because we do not have to, nor do we plan to, carry out any more water injections into the TARA trenches. (See the addendum "White Paper" on the benefits and risks of trench water filling.) If we need to inject water into trenches or wells, we may have to obtain an Underground Injection Permit.

(9) "Has the soil over the 5 trenches, that is to be used to backfill the craters of the remaining 14 trenches been sampled for hazardous or radioactive contamination?"

It should be emphasized that the soil directly over the

TDHE Comments and Replies 5

trenches to be compacted will be pushed down into the compacted mass and there are no plans to move or disturb this soil. The soil around these five trenches will be pushed over to the other 14 trenches to level their grade to the original land surface. In the area not directly over trenches, twelve undisturbed soil cores were obtained to a depth of 15 feet during standard penetration tests in 1987. Each 18-inch long section of core was scanned for radioactivity with a Geiger-Muller detector. None was observed. In addition, during construction of the 13 new monitoring wells at the TARA site in 1987, drill cuttings were continuously monitored for radioactive contamination by our Health physics personnel. Again, none was detected. Hazardous substances were not analyzed in either the soil cores or drill cuttings although the former have been archived.

It is quite unlikely that any of this soil, which we propose to move, would contain hazardous or radioactive contamination. First, all of this soil lies above the depth of waste burial and any possible waste contamination migration would have been down or lateral with the flux of water. Second, it is extremely unlikely that hazardous substances would be present without co-contamination by radioactive substances. This is probable because the TARA trenches were used for disposal of higher-level low-level waste. We have very specific radiologic safety procedures which must be followed during all excavations to protect workers and the environment. As a contingency, if we do encounter radioactive contamination during either dynamic compaction or site grading, we plan to dispose of it in situ by covering with clean fill and dynamically compacting. It is extremely unlikely that this contingency will arise but we plan the health physics coverage to deal with it. A third observation, which supports our planning that radioactive contamination will not be encountered, is the fact that this site has been graded before. In 1976 the site had the top two feet of cover removed and a bentonite seal emplaced at that depth by mixing into the soil. The cover soil was then replaced and seeded to grass. No reports of radioactive contamination during that operation were made during continuous health physics coverage.

(24) "Has EPA commented on the 3004(u) impact of this Project?"

No, not to my knowledge. Because the TARA site trenches were used prior to 1980, the area is currently not classified as a RCRA waste area. However, the trenches contain the same physical types of waste and the trenches were constructed and closed by procedures identical to the RCRA area trenches. Thus, the stabilization evaluations gained on this site will be directly applicable to RCRA areas of SWSA 6 and other SWSAs.

Comments Related to Trench Grouting

TDHE Comments and Replies 6

(7) "The injection of fluids during grouting may constitute an injection under State or Federal UIC regulations. Has this been considered as a permitting requirement?"

The Action Description Memorandum (ADM), which was prepared for this project, is a formal review of proposed actions by ORNL's Environmental Compliance Department for conformity to environmental laws and regulations. This issue was not raised at the time the ADM was prepared, at which time the State regulations had been in effect for one year, so it was presumed that the proposed grouting was in compliance with those regulations (as were the proposed trench water fillings). Although the UIC regulations do not prohibit this grouting, we may need to apply for a permit to perform the grouting of the trenches.

A reading of the Tennessee Rules for Underground Injection Control (Chapter 1200-4-6 effective June 7, 1985), seems to indicate that grout injection into trenches is not prohibited. We do not propose to place the grout into ground water. The grout will be confined strictly to trenches whose floors lie about 20 feet above the water table. When the grout sets, about an hour after injection, it is no longer a fluid and there is no possibility of its migration to the water table.

(10) "Does the acrylamide base grout contain a monomer which is toxic? Given the proximity to the Emergency Waste Basin and a creek which flows into White Oak Lake, what measures will be taken to prevent possible release of contaminants to surface or ground water? Does the grout contain any other toxic constituents which might be released to surface or ground waters?"

Yes, the major component of the grout, acrylamide, is toxic as defined by EPA regulations. We plan double containment of the grout during its preparation and mixing and pouring into the trenches. The portable liquid mixing and storage tanks will be contained within a "Port-a-Berm" which is a self-supporting liquid containment pond of sufficient capacity that should all tanks break simultaneously, the fluids could be contained. The polymerization catalyst, ammonium persulfate, will be on site so that detoxification of any spilled acrylamide can be performed by initiating polymerization. The polymer is neither toxic nor hazardous. Subsequent biodegradation of the polymer is extremely slow and produces no toxic or hazardous products. Possible release to ground water is protected by the same double containment system. Possible release to ground water as a result of injection is controlled by the set time of the grout. As when we performed trench grouting in 1986, each batch of grout and catalyst is tested before injection to verify that the set time is less than one hour. Thus, there would be inadequate time for

TDHE Comments and Replies 7

the grout to reach the water table before set even at maximum ground water velocities of meters per day which have been observed in fractures in the soil formation within SWSA 6.

The grout also contains methylenabisacrylamide (a polymer cross-linking agent) whose toxicity would be similar to the acrylamide. The other constituents of the grout are not classified as hazardous or toxic. These include the ammonium persulfate (the catalyst), triethanolamine (the radical transfer agent), potassium ferricyanide (the set retardant). Unlike our previous uses of this grout, we do not plan to use a triethanolamine grade which contains ethylene glycol as a freezing point depressant.

(11) "Provide specifics regarding, "grout verification testing" method(s)."

This was meant to refer to Table 1 which lists the grouting verification and evaluation methods. These methods include measurements of trench hydraulic conductivity before and after grouting and volumetric void filling calculations. We have already performed trench void measurements, as discussed in item (8) above. After compaction, we will determine what fraction of these voids have been collapsed via elevation surveys of the land surface depression. The difference between these two measurements will be a measure of the remaining voids in the trench. From our measurements of the volumes of grout actually placed into each trench, we should be able to evaluate the degree of filling of these residual voids.

Because we have been specifically proscribed from putting even small amounts of water into burial trenches, the measurement of hydraulic conductivities before and after will be difficult. Hopefully, the injection of the grout itself can be used as a measure of the before hydraulic conductivities. It would be quite advantageous to know what the injection well fluid acceptance rates will be before we inject because that would allow us to plan our work schedule and regulate set times of the grout accordingly. We could also measure the post grouting hydraulic conductivity with grout but that is a one-shot evaluation, since once the additional grout sets, further measurements over time are meaningless to interpret any change in grout performance. However, if we are fortunate as we have been in previous grouting demonstrations, post grouting hydraulic conductivities approach zero (unmeasurable). In that case, we may be able to put water into the well casing, demonstrate that it does not flow out into the trench, and remove the same volume of water so that there is no net injection.

Cover Construction Phase

(14) "Why was 6 inches of bentonite selected instead of clay?"

TDHE Comments and Replies 8

We selected bentonite, which is a clay, over local deposits because we do not have geotechnical information on the hydraulic properties of local clays. Bentonite would be the premium grade of clay for cover construction and, without an extensive program of hydraulic testing, its use would present no compromise in the assurance of the quality of materials. Obviously, it is more expensive than local clays. But the cost of geotechnical testing for use in such a small-scale demonstration exceeds the extra costs associated with procuring the premium bentonite.

(15) "When the swelling of the 6 inches of bentonite occurs will adequate expansion of the geo-textile fabric be available to prevent tearing or ripping? How will this be monitoring or detected?"

The sole function of the geo-textile fabric is to provide a materials separation and, in the case referred to, this in between the bentonite and sand layers. This materials separation is required mainly during the construction phase where we will be placing a specific thickness of sand over a potentially moist and slippery bentonite. The technical specifications of the fabric are given in the Appendix of the plan. Its tensile strength, elongation, and puncture resistance are quite large and would be able to endure the swelling pressures of the bentonite. One of its major commercial uses is in distributing loads over unstable ground, i.e., roadbed support. It is extremely permeable and is not designed for percolation protection. During construction of our proposed cap, it will function to distribute the load of cobble so that penetration of the bentonite does not occur resulting in a nonuniform thickness.

(16) "Why not use the neutron probes at different levels?"

The position of the neutron probe access tubes is directly below the percolation barrier. Their sole purpose is to detect possible moisture fluctuations in this region (i.e., barrier failure). Putting them at different levels would not supply additional information. It would, however, raise an additional hazard in their construction. Putting the tubes just below the cap requires a 'ditch witch' trench, about 6 inches deep, to be placed across the site. To go any deeper, would entail digging down into the depth interval of the buried waste which we would prefer to avoid. We have additional vertical access tubes planned for the soil and cobble levels of the cap. But tubes should not penetrate the percolation barrier because that might compromise its function.

(17) "Re: 2.8 Soil Cap, where in the plans is the drainage ditch illustrated? To what plans does this sentence refer?"

This sentence refers to the plan drawings (See Sheet 3 of 3)

TDHE Comments and Replies 9

which should have been received with the text of the plan. The ditch is a small ditch to collect and route surface runoff from the cap to our monitoring point.

(18) "What will be the final slope of the cap? What will be the stability of the cap, given the steepness of the current outslopes? Will the cap remain in place permanently? If not, how long is it expected to remain in place? What is the final fate of the cap?"

As depicted on the drawing (Sheet 3 of 3) the cap will slope 1% in both the northwest and southeast direction peaking in the middle. The cap will also slope 1% toward the northeast over about 3/4 of its length and increase to 7% at the extreme northeast. This sloping pattern was designed to route all surface runoff to a single monitoring point for gaging. The proposed cap is over the five trenches in the extreme northeast section of the TARA site where the hillock widens out noticeably. The outslopes in this area are not particularly steep and no ground instability is anticipated. This is contrasted with an earlier version of the plan, which encompassed all 19 trenches at the site being capped, where the steep and narrow part of the hillock to the southwest would present stability problems.

Unless there is a gross failure in performance, the cap is designed to be permanent. It is planned to monitor its performance through site water balances and dynamics for at least five years. At that time, presuming it is still performing well, its continued monitoring would be integrated with the total SWSA 6 post-closure monitoring.

(19) "What parameters will be monitored for the surface waters carried by the ditch?"

It is planned to monitor regularly only flow and suspended sediment in the surface runoff. On a quarterly basis, we plan to screen runoff samples for gross alpha, beta, and tritium and gross quality characteristics (i.e., pH, e.c., d.o., hardness, alkalinity, and acidity). Since all cap materials will be clean, no contamination in its surface runoff would be expected. The main reason for measuring flow of this runoff is to construct a water balance for the cap and to determine its rate of erosion from the amount of suspended solids carried off.

(20) "Kentucky 31 Fescue alone is inadequate. A quickly establishing annual rye and a legume should be included, species dependent upon season of seeding. Annual evaluation of vegetative success and annual fertilization should be included in the plan."

The plan can accommodate whatever type of quick vegetative cover is preferred. We can include some annual rye and a legume, such

TDHE Comments and Replies 10

as white clover or alfalfa, with the fescue. Its main purpose was to prevent erosion of the soil cap while the trees are getting established in the first few years. (See item 21 below). The plan does include an annual evaluation as implied by the evaluation methods in Table 1. This evaluation includes above ground biomass and growth measurement, inspection of survival and moisture stress status and vegetation sampling for analysis of strontium and cesium tracers placed beneath the percolation barrier. This latter analysis will be performed to establish whether or not root intrusion has occurred through the percolation barrier. The cesium and strontium are neither toxic nor hazardous and are present only at trace background levels in vegetation. Thus, such sampling offers a facile and safe method to assess possible barrier failure. Annual fertilization will not compromise any project goals and will be included in the plan.

(21) "The establishment of trees on this cap is unacceptable. If trees are to be evaluated it should occur on a "cold" demonstration site where the consequences will not potentially be environmentally harmful."

We will concede to this prescription and modify the plan so that soil cover contains only grasses and legumes and no woody species. We believe that the basis for this objection to trees lies in the common misconception that trees are deep rooted and pasture species (grasses and legumes) are not. Both trees and forage species can be either deep or shallow rooted depending on soil horizon characteristics much more than species characteristics. We feel that the cobble, bentonite, and liner layers would offer sufficient resistance to root penetration by trees. But forage species on the soil cap will offer the same potential stresses to the performance of the percolation barrier. Thus, the experimental goals of the project will not be compromised by the use of forage vegetation on the cap instead of trees.

It should be noted that, at some point in time, all of the caps on all of our hazardous and radioactive waste sites will be covered with trees. This will occur whenever we abandon these sites. Our goal in originally proposing to use trees on this cover was to disprove the common misconception about trees so that we do not have to go about continually maintaining these caps under the prejudice that keeping trees out is doing some good. Whatever cap is finally placed over our hazardous and radioactive waste sites will have to resist root penetration whether by trees or grasses. Our desire to perform the tree vegetation on a 'real' site was motivated by the common reaction of so many people that, when a 'cold' test is performed, significant skepticism always remains because "you haven't done it on a real site." Obviously, had the TARA trees become radioactively contaminated, we would eradicate them similarly to

TDHE Comments and Replies 11

what we would have to do if any vegetative cover over a capped area became contaminated. A change to tree cover on the TARA cap can be made at any time in the future whenever the times will allow it. So, for the present, we will plan to establish only forage species on the TARA cap.

(23) "The mulch rates are inadequate at 100 lb/1000 ft². They need to be 3 to 4 times the suggested rate."

The proposed mulch rates were simply taken from standard engineering specifications for finishing earthwork. The suggestion to increase the mulch rate will be followed. We will use 10 bales of straw instead of 2 on the cap and on interim covering before final cap construction. We will be watching during all phases of construction and, should insufficient mulching have occurred due to an arbitrary specification, we would have modified it as necessary.

(25) "An alternative cap-cover that provides high run-off and low infiltration is suggested in NUREG/CR-4918 Vol. 1, Control of Water Infiltration into Near Surface LLW Disposal Units, by R. K. Schulz, R. W. Ridky, and E. O'Donnell. How does the proposed TARA cap compare?"

The referenced NRC 'cap' offers no protection to either root or burrowing animal intrusion and has no subsurface percolation barrier. It is essentially a roof over the ground with trees (Junipers) planted in holes in the roof to dry up any moisture that might leak through the roof. The concept implies active roof maintenance. [The liners depicted in sketches within the subject report are not part of the cap concept but are there solely to collect and estimate of any water which may penetrate the cap.] No protection for intrusion into the waste by the Juniper roots is presented. It should also be noted that this NRC cap is a high runoff cap while the TARA cap is designed for low runoff. We believe that caps over large areas of ORNL disposal areas will need to be low or delayed runoff types. Otherwise the increased runoff for a large area, e.g. ten acres, will represent a significant erosion hazard for adjoining areas. We believe that the TARA cap is superior in concept and design to the referenced cap.

Comments Related to All Phases

(1) "How were the priorities determined for corrective actions?"

There has been no determination of priorities for corrective action. We will not know what corrective actions may be required for the TARA site until the RI/FS for SWSA 6 is completed. In other words, we have little idea what the inherent hazard of doing nothing to the TARA site is. But we are reasonably sure

TDHE Comments and Replies 12

that whatever corrective actions may prove to be required at TARA will encompass stabilization and closure techniques less than or equal to, but not greater than, what we have proposed in this demonstration. Our goal is to determine the effectiveness of each component of stabilization and closure so that any benefits for large-scale closure can be pursued with confidence rather than discarded due to lack of proven effectiveness. We need to know which components of a cover or cap work and why, not that a multicomponent system succeeds or fails without knowing why. This is an experimental closure to help us do the real thing right. We may make mistakes on a little area like TARA but that is a risk we believe we must take so that we do not make mistakes on our larger problems.

(2) "It is unclear how the initial TARA activities will mesh with the closure plan for SWSA 6."

As of the date of this writing, we do not have a closure plan for SWSA 6. At the time the TARA plan was prepared, we believed that we had one but that was judged to be unacceptable by EPA. The TARA activities will mesh with whatever the SWSA 6 closure plan turns out to be. The technical information of the effectiveness of dynamic compaction, grouting, and their combination, as well as cover performance data, should be valuable to planning the stabilization and closure of SWSA 6 and all the other SWSAs which will eventually have to be closed. If the motivation for this question centers on how physically the demonstration site will mesh with the rest of the site, we do not know specifically. Presumably, the five trench cap will remain because there are probably many ways to integrate it with whatever must be done over the rest of the site. Physically, it poses no more of an obstacle than a building, road, power line, or drainage ditch. The technical information will be the most valuable product we gain by testing techniques on less than 1% of the burial trenches in SWSA 6.

(3) "Does data collected to date assure hydrologic isolation from the other burial sites, or merely indicate that such a condition is likely to exist?"

The data collected to date do assure hydrologic isolation of the five trenches to be covered from other trenches in the area. When trench 6 (i.e., the western most trench to be covered) was filled with water, no water was observed in trench 7 just to the west. This observation provides excellent evidence of hydrologic isolation and could not be attained without water filling tests. The water table in this region also is isolated from the western region. Pump-in tests at the five trenches to be covered did not produce a response in wells on the western side of the TARA site and did produce a response in wells on geologic strike (i.e., the direction roughly parallel to trench orientation). Therefore, it

TDHE Comments and Replies 13

seems assured that percolation on the western side of the proposed five-trench cap will not influence moisture within the five covered trenches or the water table below them.

(4) "The fact that the most significant vector for infiltration is vertical does not preclude a horizontal influence. Please address this possibility."

We agree strongly with this statement. We believed that we had to establish this hydrologic isolation of the trenches to be covered particularly from possible lateral recharge. Our water pump in tests, as discussed above, clearly eliminate such a possibility for the trench area to be covered.

(5) "Why cap only 5 of the trenches? How will the 5 trenches be hydrologically (both surface and ground) separated from the remaining 14 trenches? Why was the retaining wall deleted?"

Perhaps a brief history of the evolution of this project would explain this issue. Initially, it was planned to carry out this demonstration of stabilization and closure techniques on all 19 trenches at the TARA site. However, in order to contain a cap over the western half of the site, lateral support would be required to prevent it from slipping down the steep slopes on the northwest and southeast sides. The instability of the present slope is quite apparent from the leaning of the perimeter fence on the northwest side of the site. However, in order to produce sufficient 'toe' for a possible retaining wall in this area, the height of the wall became large (i.e., 26 feet). With no feasible means of supporting the hillside during the construction of such a wall, it became apparent that the wall was not buildable. It became a moot issue that the wall, were it buildable, would cost over a million dollars (labor and materials). However, on the eastern side of the site, the hillock widens noticeably and, we concluded that the cap was possible without any additional lateral support in this region. Thus, we scaled down the project to what was possible. We believe that we can gather sufficient information on the stabilization and closure of these five trenches to attain the project goals.

The original scope of the project called for stabilizing all 19 trenches at the TARA site. Such a scope was necessary because, at that stage of the project, we had no evidence for the hydrologic isolation of any subunits at the TARA site. Thus, the compaction, grouting, and covering of all trenches would have been necessary. However, our site characterization efforts, particularly the water pump-in tests last fall, have established the isolation of the five trenches on the eastern side. Thus, the project was scoped down to these five trenches. The remaining 14 trenches, like the other hundreds of trenches in

TDHE Comments and Replies 14

SWSA 6, will have to await the completion of the RI/FS before their stabilization and closure can be attempted.

(12) "Given that numerous wells are to be installed, i.e. intra trench observation wells, etc..., will membrane of plastic be placed beneath and around drilling rigs to minimize any dispersion of liquids and facilitate site/clean-up?"

Yes, during drilling, plastic sheeting was used under both the drill stem of the rig and the engine section to contain possible hydraulic fluid leaks. These procedures are detailed in the project Activities Description Memorandum (ADM). The procedures for waste handling from drilling operations are also described in the ADM. For intratrench wells, we have employed a technique of driving well points with stainless steel casing. This technique produces no drill cuttings and was devised to avoid the hazards of bringing unknown and radioactive trench contents to the surface.

(13) "Should the removal of any liquids or contaminated soil from the trench occur during drilling or other operations, how will these be handled?"

The only fluids, which have been removed from the trenches, have been a few samples (approximately 100 mL each) during and after trench filling experiments. We have no plans to sample trench contents. See item (9) for a discussion of soil contamination probable during site grading operations and contingency plans.

(22) "Additional information is needed regarding the specifications of the monitoring system. This is particularly important for the angled monitoring wells."

At the time the original draft of this plan was produced (September 1986), no new monitoring wells had been installed at the site. The 13 new wells were installed in the Spring of 1987. Construction details, locations, development procedures, and sampling procedures are now available but were not available in the original the plan. When the scope of the project encompassed all 19 trenches, almost all of these monitoring wells would have been sacrificed so that none would protrude through, and potentially compromise, the area cap. Thus, after cap construction, new angled wells were envisioned which would give access to the water table under the cap from the surrounding hillslopes. However, with the smaller area to be capped, most monitoring wells will now not need to be sacrificed. We have also devised a method to continue use of the two existing wells which will be under the soil cap. These wells will be cut at the grade below the percolation barrier. Sampling tubes and pressure transducers (for water table monitoring) will be placed into the

TDHE Comments and Replies 15

casings and routed laterally, under the percolation barrier layer, to points outside the cap. We have just installed the automatic water level monitoring system at the TARA site in February 1988 and should have approximately a year of established performance before cap installation.

The 13 monitoring wells were positioned to provide perimeter sampling points as well as points on linear transects for water table mapping purposes. We can provide details in a revised plan.

TDHE Comments and Replies 16

Addendum

November 2, 1987

Questions concerning the filling of selected trenches with water at the Solid Waste Storage Area (SWSA) 6 Test Area for Remedial Actions (TARA).

B. P. Spalding

Please excuse the dialogue format but I thought it would be the most straight forward approach to document how we have addressed the many obvious concerns about filling burial trenches with water.

Why is it necessary to fill radioactive waste burial trenches with water? There is a consensus that the goal of remedial actions is to keep water out of the trenches. So why do you deliberately put water into trenches?

The purpose of filling selected trenches with water is to obtain a direct measure of the void volume within these trenches. When the seven selected trenches (out of a total of 508 in SWSA 6) are dynamically compacted later this fiscal year, surface depressions will result whose volume can be determined by surveying techniques. By comparing the depression volumes to the trench void volumes from the water filling, a quantitative measure of the effectiveness of dynamic compaction will be obtained. It is also planned to grout these compacted trenches later in the fiscal year. The effectiveness of grouting will also be evaluated using the water filling volumes. The difference between the total trench void volume and the compaction crater volume will be a direct measure of the volume of grout which the trench should require to fill its remaining voids. The volume of grout, which can actually be placed into the trench, can then be compared with the grout holding capacity of the trench.

Has not the effectiveness of dynamic compaction been evaluated previously? Why is it necessary to repeat these water filling experiments?

Yes, dynamic compaction was evaluated by the above procedure on one trench in SWSA 6 in 1985. It was found that 64% of the total trench void volume could be collapsed by dynamic compaction. This degree of trench compaction made the trench similar to the unperturbed soil formation and represented a very promising result. However, we are not sure how representative this one sample of 508 trenches really is. In addition, the 1985 trench was not grouted and we have no quantitative information on just how compatible dynamic compaction and grouting might be. In the various SWSAs, we have approximately 2,000 burial trenches for which dynamic compaction and selected grouting will probably play an important role in final stabilization. Without additional

Trench Water Filling 17

evaluation on the effectiveness of these techniques, we could fall into two possibly undesirable situations. We could be misleading ourselves, based on our limited experience, as to the effectiveness of dynamic compaction. If in actual practice, dynamic compaction proves less effective, we could waste considerable money implementing trench stabilization which is not effective. Without evaluation, we would not know about our lack of effectiveness for many years when the trenches would begin to manifest additional subsidence. Alternately, if dynamic compaction is more effective than our experience to date, then grouting may prove to be unnecessary for most burial trenches. The only way to proceed is to build more experience and quantify it.

What would be the consequences of not performing these water filling tests?

From a limited perspective, the question is moot. We have completed all the filling tests planned at the TARA site. Post-compaction evaluation will involve water acceptance tests, not complete filling, of the dynamically compacted trenches. Such tests will involve pumping in a few gallons of water to measure the acceptance rate of the trenches in order to evaluate the possible hydrologic effects and to plan the grouting procedures. In a larger perspective, it may be necessary to perform such tests in other SWSAs so that the question is not moot. If we do not have the quantitative evaluation of the effectiveness of these techniques, the RI/FS process will be affected. When performing a feasibility study, techniques with unknown effectiveness get poor marks when compared to alternatives (e.g., exhumation, treatment, and redisposal) regardless of costs. In situ stabilization and isolation techniques are infrequently chosen in feasibility studies of both hazardous and radioactive waste sites because of poor documentation of effectiveness. We believe that they may prove equally effective to exhumation and redisposal and pose considerably less risk of contaminant dispersal. Without such qualitative analysis, however, we are left only with our favorable dispositions and intuitive judgments.

What are the risks of filling these trenches with water? Do you not exacerbate leaching of radionuclides? How bad have you made the situation just to get some information on how to improve it?

Typically, it has required about 15,000 gallons of water to fill an average TARA trench of about 700 square feet. In terms of equivalent rainfall or infiltration, this would amount to 344 inches of rain. This amount of water is probably more than these TARA trenches would see in 10 years. Although this impact seems dramatic, it should be pointed out that many trenches in other areas of SWSA 6 routinely flood and receive an amount of water equivalent to our filling volume several times per year. The

Trench Water Filling 18

TARA site is unique in that all of its trenches are well above the seasonally high water table. However, several of the TARA trenches did have perched water within them when wells were first installed last year. From another perspective, the total water applied to the site (105,000 gallons, i.e. 7 x 15,000 gallons) is equivalent to 1.8 inches of infiltrated rainfall on the two acre site.

We monitor the water table elevation at the site and occasionally have seen an upward response of some of the near-field wells to filling tests. However, we did not see a response in the perimeter monitoring wells. We collect samples of the standing water in each trench after filling although no analyses are yet available for the present tests. We are not, however, proceeding blindly to the possibility of accelerated leaching of radionuclides. In two previous tests of trench filling, we observed no impact on leaching from the trench. In 1986, two small trenches in SWSA 4 we filled with water as part of a grout evaluation. In twelve wells within three feet of these trenches, we observed no radioactivity (hard beta and/or alpha) either before, after, or during the filling. Nor did we observe any increase in the dissolved radioactivity within the trench. In 1985, during the filling of the trench in SWSA 6 prior to its dynamic compaction, leachate concentrations within the trench were not changed. Radioactivity in groundwater outside the trench was not affected. Given the high distribution coefficient of most radionuclides between SWSA soil and groundwater, these results are not too surprising. It is our common observation that radionuclides, other than tritium, move quite slowly in soil. Where SWSAs are discharging Sr-90 or Cs-137, it is usually due to trench overflow and resulting surface runoff not groundwater leaching. We are particularly careful to avoid overfilling the trenches during a test for just this reason. In summary, we believe the risks to be low and the benefits to be high. But we are strongly aware of the risks.

Are there not other ways to make these measurements and evaluations?

No, none that we are aware of. We have other methods to evaluate dynamic compaction (e.g., penetration resistance testing). Unfortunately, these do not, even indirectly, measure void collapse. We could conceivably increase penetration resistance without a collapse of the majority of voids although this would seem unlikely. The penetration resistance hopefully will be correlated with the measured void reductions. We need that information so that penetration resistance can be employed for routine evaluation of dynamic compaction during actual SWSA-wide application. Hopefully, penetration resistance will become an effective and inexpensive evaluation technique but only after the correlation has been established.

Alternately, we have considered gas permeation but have not found a viable technique. Gas permeabilities in soil are usually

Trench Water Filling 19

several orders of magnitude greater than those for water. It is unlikely that the trenches would be tight enough to determine volumes by pressure testing such as is done with underground tanks. Filling with a fluid, which subsequently can be removed or allowed to drain away, seems to be the only approach to make this determination.

Is anything else learned from water filling besides void volume?

Yes. We determine void volume as a function of trench depth. This documents where voids are located. In the previous test in SWSA 6, the greatest void volume was located just beneath the three foot thick soil cap. We also determine the hydraulic conductivity of the soil formation in which the trench was placed. The variability of hydraulic conductivity with depth is also determined. These measurements are valuable in modeling the hydrology of the site. We also learn the directional effects on water table response which usually correlates with the geologic structure. Such tests aid in the placement and monitoring frequency of groundwater wells. The response of adjacent trenches to a trench filling also provides us with information on the hydrologic connection between trenches. In one case, we filled an adjacent trench simultaneously which is why we filled seven instead of the planned six trenches at the site. In other work, not related to TARA, groundwater tracers have been introduced into trenches during water filling.

OAK RIDGE NATIONAL LABORATORY

OPERATED BY MARTIN MARIETTA ENERGY SYSTEMS, INC.

POST OFFICE BOX X
OAK RIDGE, TENNESSEE 37831

May 17, 1988

Mr. Rodger A. Jump, Manager
Waste Management Branch
Department of Energy, Oak Ridge Operations
Post Office Box 2001
Oak Ridge, Tennessee 37831

Dear Mr. Jump:

Notification of Federal and State Regulators of Initiation of Dynamic
Compaction in Solid Waste Storage Area 6

The draft Task Plan for the Shallow Land Burial Stabilization and Closure Demonstration at the Test Area for Remedial Actions (TARA) in Solid Waste Storage Area (SWSA) 6 was submitted to the Tennessee Department of Health and Environment (TDHE) and the U.S. Environmental Protection Agency (EPA)-Region IV on September 30, 1987. Comments on this plan were received from TDHE on February 1, 1988, and modifications to the plan were made in a formal reply (enclosed) on February 22, 1988. To date, we have received no comments from EPA and have received no response to our comments from TDHE.

In order to initiate this activity this year to gain the critical information we need to plan stabilization and closure of SWSA 6 and other areas, we propose to initiate the first phase of this stabilization demonstration, the dynamic compaction of five shallow land burial trenches at TARA. Because we cannot control the schedule for commenting by either EPA or TDHE and because formal written approval for these activities could probably never be obtained, we propose that you notify these agencies of our intent to start the dynamic compaction phase on June 20, 1988, invite them to come watch this activity, and notify us if they do not want us to perform this activity. Such notification and offer of "right of refusal" is the only method that we perceive to get approval by default.

Enclosed is a suggested text for such a transmittal to TDHE and EPA-Region IV. Early transmittal should afford them adequate time (30 days) in which to respond to you if they decide that our planned dynamic compaction activities are objectionable. If you have questions, please feel free to contact me (6-4438).

Sincerely,

L. D. Bates, Manager
Remedial Action Program

LDB:bps

Rodger A. Jump, DOE/ORO

2

May 17, 1988

Enclosures (3)

1. Suggested Text
2. Draft Final Plan for the Demonstration and Evaluation of Stabilization and Closure Techniques for Low-Level Waste Burial Trenches at Oak Ridge National Laboratory, ORNL/RAP-42
3. TDHE Comments and Replies

cc/enc:	E. C. Davis	R. C. Sleeman
	J. R. Lawson	B. P. Spalding
	L. W. Long	J. E. Van Cleve
	L. E. McNeese	File - LDB (2)
	T. H. Row

STATE OF TENNESSEE
DEPARTMENT OF HEALTH AND ENVIRONMENT
1605 PROSSER ROAD
KNOXVILLE, TENNESSEE 37914-3434

June 30, 1988

Mr. Rodger A. Jump
Waste Management Branch
Department of Energy
Post Office Box E
Oak Ridge, Tennessee 37831

RE: Test Area Remedial Action (TARA) Demonstration
Demonstration at Solid Waste
Storage Area (SWSA) 6

Dear Mr. Jump:

The Tennessee Department of Health and Environment (TDHE) received Oak Ridge National Laboratories (ORNL) response to our comments of February 1, 1988 on March 25, 1988. I received a letter on May 31, 1988 from Mr. Brian Spalding of ORNL advising TDHE that compaction of the five (5) trenches at the TARA site in Solid Waste Storage Area (SWSA) 6 would occur the week of June 20, 1988. The attached comments represent TDHE's reply to ORNL's response of March 25, 1988 and outline unresolved concerns. We recognize the activities as outlined are ongoing, however we anticipate ORNL's acknowledgement and response to our concerns and that activities on site will accommodate, as appropriate, the following TDHE comments:

- (1) Concurrence is provided by TDHE on the value of this project as a demonstration to assess the desirability of compaction and grouting relative to trench stabilization and avoidance of subsidence. However, this technology should not be adopted on a larger scale until a thorough assessment of the results of the demonstration has been performed and concurrence provided by TDHE.
- (2) Additional characterization of the leachate is necessary. Quantities of dissolved organics in the mg/l range are considered to be significant, as most RMCL's for these compounds fall in the low ppb range.
- (3) An assessment of the effect of the dynamic compaction on the integrity of the subsurface strata is recommended. The possibility of creating fractures which might provide new pathways through the substrata into groundwater must be assessed.

RECEIVED

JUL 8 1988

L. D. BATES

ID 01685

FILE TIC

HOLD

- (4) Because this technology may be used in closure activities, it is important to determine the fate of liquids in the trenches, not only as protective measures in this demonstration but as a predictive measure in later demonstrations. The focus of this demonstration should be to provide evidence that the technology is useful or applicable to a wide variety of trench conditions. The results should be assessed as applicable not only in this narrowly defined situation, but for a broader range of considerations reflecting the most common conditions of trenches in SWSA 6.
- (5) It appears additional clarification of State UIC regulations is needed. The use of these fluids may constitute a Class V injection well under Chapter 1200-4-6-.06(5)(J). Class V injection wells are only authorized by rule, if the operator can meet the conditions specified in 1200-4-6-.14(2)(a)&(b). The Division will require a permit if the Class V well has the potential to violate water quality criteria as specified in 1200-4-6-.14(4).
- (6) Were the bulk quantities of solvents poured into auger holes or are they suitably contained and stored in these auger holes? (Page 3)
- (7) Scanning a core section with a GM tube could, at best, give an indication of a very gross radioactive material contamination. The inclusion of this, as a measure of radioactive material contamination, indicates a lack of understanding of good health physics or radiation detection. (Page 5)
- (8) The risk associated with additional sampling is worth the effort to collect additional information. It would be of great benefit to understand what is happening in the trench and under it. Why can't access tubes be laid in longitudinal to the cap? (Page 8)
- (9) Are the cesium and strontium radioactive? DOE should do analyses on fertilizers, otherwise U, Th, or other materials may show up from that source. (Page 10)
- (10) The discussion on Page 12 supports the Division of Radiological Health's comments and ideas for more extensive monitoring for any and all demonstration projects. (Page 12)
- (11) "No radioactivity" is defined as no "hard beta and/or alpha." What about soft beta, e.g., H-3 or gamma? (Page 18)

Your response to our previously noted concerns is appreciated. We anticipate continuing to assess the desirability of these technologies.

Sincerely,

Earl C. Leming
DOE Project Coordinator

ECL/GIH:arb/DWM#1B2

cc: W.E. Hibbitts
✓ L.D. Bates, ORNL
W.E. Cantrell
Dave Hopkins

OAK RIDGE NATIONAL LABORATORY

OPERATED BY MARTIN MARIETTA ENERGY SYSTEMS, INC.

POST OFFICE BOX 2008

OAK RIDGE, TENNESSEE 37831

December 14, 1988

Mr. Tom J. Wheeler
Waste Management Branch
Department of Energy, Oak Ridge Operations
Post Office Box 2001
Oak Ridge, Tennessee 37831-8621

Dear Mr. Wheeler:

**Reply to Regulatory Comments on Task Plan for Test Area for Remedial
Actions, Solid Waste Storage Area 6**

Reference: State of Tennessee, Department of Health and Environment,
Comments of June 30, 1988, on Test Area for Remedial Actions
(TARA) at Solid Waste Storage Area 6

We are grateful for the comments of the Tennessee Department of Health and Environment (TDHE) on the subject project. We believe that we have accommodated these comments and concerns as described in the following specific replies. We would appreciate your forwarding of these replies to them. To facilitate comparison of our replies with their comments, we have repeated their numbered comments, in bold letters, prior to our reply and discussion of each.

1. **Concurrence is provided by TDHE on the value of this project as a demonstration to assess the desirability of compaction and grouting relative to trench stabilization and avoidance of subsidence. However, this technology should not be adopted on a larger scale until a thorough assessment of the results of the demonstration has been performed and concurrence provided by TDHE.**

We appreciate the concurrence of TDHE on the value of this project. We do not plan to adopt either the in situ grouting or dynamic compaction on any scale larger than the originally proposed scale of the TARA. We too are anxious to perform an assessment of the demonstration results and will seek the concurrence of TDHE in that assessment before including this technology in any stabilization or closure plans at ORNL remedial action sites. The TARA Project plan is considered amended by any of the changes which we acknowledge in our replies to TDHE comments.

We would like, at this time, to modify the original proposed activities included under the in situ grouting phase. We had originally planned to perform the in situ grouting of the five TARA trenches which had been compacted the week of August 1, 1988. As discussed in comment (5), we will not initiate this planned grouting

Mr. Tom J. Wheeler, DOE/ORO

2

December 14, 1988

until concerns over underground injection control (UIC) regulations are resolved and TDHE and EPA concur on our assessment of the grout compatibility testing information. Assuming resolution of the technical concerns about in situ grouting, we would like to perform in situ grouting on, at most, three additional uncompacted trenches (No. 7, 8, and 9) at TARA. This additional grouting will provide us with data for a direct comparison of the effectiveness of in situ grouting on both compacted and uncompacted trenches. This information on grouting of uncompacted trenches would be most useful for application to other areas of SWSA 6 where the breaking of any ambient liquid containment in burial trench waste packages might pose a significant impact on groundwater quality following dynamic compaction. If such areas are identified during the remedial investigation of SWSA 6, then in situ grouting, without dynamic compaction, may be more desirable for selected trenches or auger holes. Thus, a direct comparison of in situ grouting effectiveness, via a measurement of degree of hydrologic isolation, for compacted versus undisturbed burial trenches will be necessary. Our proposed modification of the TARA in situ grouting phase would provide this information. We see no new technical issues raised by this modification which have not already been addressed in the present proposed in situ grouting activities.

We would also like to grout one additional trench (No. 150) in SWSA 6, but not at TARA, to demonstrate an additional capability of the acrylamide grout. In August 1986, this trench was grouted by injection of a blend of Portland cement (39%), fly ash (55.5%), and bentonite (5.5%). The grout take on this trench was excellent and accounted for all of the measured voids as determined by a water-filling test performed prior to grouting (T. Tamura, et al., In Situ Waste Grouting of an ORNL Trench Using a Particulate-Type Grout, 1987, ORNL/RAP-23). Good postgrouting penetration resistance was also exhibited by this trench indicating that good geotechnical stability had been achieved. However, water acceptance rates by monitoring wells within the trench were still significant although reduced from pregrouting values. It is concluded that the particulate-based grout filled all of the large voids but failed to penetrate into smaller voids which provided the residual features to conduct water through the trench. We believe that with a minimal amount of acrylamide grout (probably less than 500 gallons), these residual voids could be sealed and hydrologic isolation of the buried waste demonstrated. The demonstration of the effectiveness of combining a cheap particulate grout to fill most trench voids with an expensive acrylamide grout to fill residuals may represent an extremely low cost stabilization technique for ORNL burial trenches. We propose to test compatibility of the acrylamide polymerization with both the grout and waste from this trench before attempting the acrylamide field demonstration. Samples from the trench were taken as part of the postgrouting evaluation and are available for testing. Compatibility of acrylamide with both cement

Mr. Tom J. Wheeler, DOE/ORO

3

December 14, 1988

and bentonite is well documented as these substances have been used as additives for acrylamide grouts to increase viscosity and strength. Thus, this small additional grouting could provide valuable information on potential stabilization techniques for selected trenches which, for whatever reason, may pose too much risk for the very cheap dynamic compaction technique.

2. Additional characterization of the leachate is necessary. Quantities of dissolved organics in the mg/l range are considered to be significant, as most RMCL's for these compounds fall in the low ppb range.

We will have difficulty performing additional characterization of trench "leachate" as recommended. The samples of trench "leachate", which we collected, are somewhat artificial in that they were not "natural" standing water within the trenches. They were collected from the perched water in the trenches following the water filling tests. We have used these samples for radiochemical (gross alpha and beta and tritium) and gross chemical (pH, electrical conductivity, alkalinity, hardness, and total dissolved solids) analyses as well as for testing their compatibility with acrylamide grout (Item 5 below). We have only limited amounts remaining (<50 mL) for the analyses of possible organic contamination. We will attempt to analyze our residual samples for volatile and semivolatile organics (EPA method 624) but the detection limits will be quite high because of the limited sample size. We will continue to monitor the trenches for transient standing water and will sample any "natural" leachate if possible. Only 3 of the 19 TARA trenches to date have exhibited transient standing water following sustained wet weather periods. We will also continue to monitor and analyze groundwater at the TARA site.

3. An assessment of the effect of the dynamic compaction on the integrity of the subsurface strata is recommended. The possibility of creating fractures which might provide new pathways through the substrata into groundwater must be assessed.

We cannot, at present, provide any direct measurements to support an assessment of the effect of dynamic compaction on the integrity of subsurface strata. We anticipate no adverse effect on the shallow subsurface due to two generalized experiences with dynamic compaction. First, an evaluation of dynamic compaction for construction engineering planning (P. W. Mayne, J. S. Jones, and J. C. Dumas, 1984. "Ground Response to Dynamic Compaction" J. Geotechnical Engineering, 110:757-774) has led to the general conclusion that the maximum depth of influence of dynamic compaction (Di) is:

Mr. Tom J. Wheeler, DOE/ORO

4

December 14, 1988

$$D_i = (M \cdot H)^{1/2} / 2$$

where M = drop weight in tonnes
and H = drop height in meters

For the TARA dynamic compaction, we designed a drop weight of 4 tonne (Mg) which was dropped from a maximum height of 8 meters. Thus, our D_i would be only 9.3 feet which, following an average of 4 feet of ground subsidence at the point of dropping in response to the dynamic compaction, would give a total depth of influence of just over 13 feet (approximately the burial trench depth). This would put the depth of influence well above the water table at TARA which is a minimum of 35 feet below the ground surface in the burial trench area.

Second, the material in the zone of influence of dynamic compaction at TARA is soil or saprolite and not rock. In response to compression, the soil would be expected to deform plastically not brittly. Thus, we anticipate that whatever hydrologically conductive features may be in the depth of influence of dynamic compaction, will be deformed plastically and result in a decreased hydraulic conductivity after dynamic compaction. This effect is exactly the same as the decreased hydraulic conductivity of clay during its compaction in the construction of a RCRA-type cover over a hazardous waste site. The difference, of course, is in the depth of influence of dynamic compaction versus the relatively shallow depth of influence of conventional surface compaction machinery. If dynamic compaction were used in an attempt to compact hard or brittle material, such as unweathered shale or limestone, fracturing would be expected; and the resulting new fractures would be expected to provide new conduits for fluid movement.

During the initial stages of the in situ grouting of the five compacted trenches at TARA, we will be able to calculate whole-trench hydraulic conductivities and compare these values to those determined during precompaction water-filling tests. Most likely, any subtle differences between pre- and postcompaction hydraulic conductivities will not be discernible. However, if this issue remains a significant concern, we could devise methods to test the influence of dynamic compaction on soil and saprolite hydraulic conductivity. Because of the destructive sampling methods involved, i.e., excavations to sequential depths under a region of compacted surface, and the necessity to measure water intake rates into the subsurface, this activity would probably have to be performed in areas of SWSA 6 which did not contain buried waste. However, we would anticipate that a significant effect, either positive or negative, would not be detectable because of the inherent large variability in hydraulic conductivity from point-to-point in the Conasuaga formation (R. J. Luxmoore, B. P. Spalding, and I. L.

Mr. Tom J. Wheeler, DOE/ORO

5

December 14, 1988

Munro. 1981. "Areal Variation and Chemical Modification of Weathered Shale Infiltration Characteristics. Soil Sci. Soc. Amer. J. 45:687-691).

4. Because this technology may be used in closure activities, it is important to determine the fate of liquids in the trenches, not only as protective measures in this demonstration but as a predictive measure in later demonstrations. The focus of this demonstration should be to provide evidence that the technology is useful or applicable to a wide variety of trench conditions. The results should be assessed as applicable not only in this narrowly defined situation, but for a broader range of considerations reflecting the most common conditions of trenches in SWSA 6.

We agree completely with this comment and believe that the results of the TARA demonstration will be applicable to most of the trench conditions in SWSA 6 and other ORNL areas without too much ambiguity. We see only two general areas of concern in extrapolating the TARA results to the rest of SWSA 6 and other ORNL remedial action sites. First is the concern over the impact of the loss of any ambient liquid containment in buried waste packages following dynamic compaction. As we have emphasized previously, it seems unlikely that significant amounts of fluids were disposed at the TARA site. Nevertheless, we will verify the extent of radioactive contamination around all the trenches following dynamic compaction through extensive soil sampling following the sampling strategy employed for the precompaction characterization. (The precompaction characterization data is contained in a draft manuscript which should be released in final form by November 31, 1988.) As discussed in our previous correspondence, we plan to gather the geotechnical data at TARA to quantify the benefits of dynamic compaction. These data will be applicable to all ORNL burial trenches. They will clearly define the benefits to be achieved in taking the risks of breach of liquid containment. Once, or if, the benefits of dynamic compaction are established, a TARA Phase II demonstration is planned to demonstrate and assess the environmental consequences of a breach of liquid containment during dynamic compaction. At this point, the planning for Phase II is only conceptual as outlined in the SWSA 6 Closure Plan. We would emphasize that whatever ambient liquid containment exists in SWSA 6 burial trenches for the unknown amounts of liquids disposed was not designed for any containment during disposal but only to get the material to the site. Thus, whatever containment of whatever fluids may exist in SWSA 6 will disappear sooner or later. Ambient containment will provide no environmental protection in the long term, and the protection of ground and surface water will depend entirely on the performance of infiltration and groundwater intrusion barriers. The performance of these barriers, in turn, depends heavily on the stability of their foundation which is the fundamental problem addressed by dynamic compaction.

Mr. Tom J. Wheeler, DOE/ORO

6

December 14, 1988

The second issue of concern regarding liquids in burial trenches centers on the applicability of dynamic compaction to inundated or partially inundated burial trenches. Obviously, water in burial trenches is not compressible and would have to be removed prior to dynamic compaction. We are looking into methods of groundwater treatment, as part of the SWSA 6 Closure Plan, as a technique of addressing inundated trenches prior to dynamic compaction and possible groundwater collection and treatment if contamination were to occur during dynamic compaction. Once water has been removed from a trench, its suitability for dynamic compaction would be equivalent to a burial trench in an unsaturated condition like those at TARA.

5. It appears additional clarification of State UIC regulations is needed. The use of fluids may constitute a Class V injection well under Chapter 1200-4-6-.06(5)(J). Class V injection wells are only authorized by rule, if the operator can meet the conditions specified in 1200-4-6-.14(2)(a)&(b). The Division will require a permit if the Class V well has the potential to violate water quality criteria as specified in 1200-4-6-.14(4).

Our interpretation of this comment is that we must provide enough information to TDHE to show that our proposed in situ grouting at TARA "does not present a hazard to any existing or future use of a ground water classified pursuant to Rule 1200-4-6.05(1)." We have provided, under separate transmittal, detailed testing results of acrylamide grout reaction with samples of TARA burial trench soil and "leachate." In summary, we found that no burial trench bottom soil or leachate retarded grout set time nor was the degree of acrylamide polymerization affected in the presence of soil or leachate. The resulting hydraulic conductivity of polyacrylamide grouted trench soil was too low to be measured in the laboratory tests. We believe that we have demonstrated our ability to control the polymerization of the acrylamide grout and that no potentially interfering substances are present in the TARA trenches. It should also be emphasized that the proposed in situ grouting at TARA will be carried out at shallow depth well above the water table. The trenches at TARA were dug to a maximum depth of 15 feet below the surface, and the water table at the site is an additional 20±3 feet below the trench bottoms. Grout injection will be limited to depths above the trench bottoms. Thus, because our proposed grouting will be in a zone not containing groundwater and because of our ability to control acrylamide grout polymerization, we believe that there is no hazard to the existing or future use of groundwater at SWSA 6.

Mr. Tom J. Wheeler, DOE/ORO

7

December 14, 1988

6. Were the bulk quantities of solvents poured into auger holes or are they suitably contained and stored in these auger holes? (Page 3)

The contaminated solvents, which were disposed in SWSA 6 auger holes, were always contained prior to burial according to our conversations with former disposal operators. However, this containment was not designed for groundwater protection or suitability against environmental release. The containers were minimal, i.e., whatever was necessary to safely transport the solvents to the site. The integrity of any of these containers should be regarded as suspect.

7. Scanning a core section with a GM tube could, at best, give an indication of a very gross radioactive material contamination. The inclusion of this, as a measure of radioactive material contamination, indicates a lack of understanding of good health physics or radiation detection. (Page 5).

We agree that GM surveys provide only a gross estimation of radioactive contamination. However, the GM survey, along with alpha detection survey, provides our primary assurance for the health and safety of our field workers. Even when we observe no beta-gamma or alpha emissions in the field, we treat the soil samples as contaminated until low-level beta and gamma counting has been completed in the laboratory. Our reply in the March 25, 1988, comments was meant only to inform TDHE of what information we had about site contamination. At that time, we had just completed the field soil sampling but had not initiated the sample preparation for low-level counting. Since then, we have completed the low-level counting for ^{137}Cs , ^{60}Co , and ^{90}Sr . We have reported these activities in the draft TARA Project report which will be available in final form by November 30, 1988.

8. The risk associated with additional sampling is worth the effort to collect additional information. It would be a great benefit to understand what is happening in the trench and under it. Why can't access tubes be laid in longitudinal to the cap? (Page 8)

We do plan to put neutron probe access tubes longitudinal to the cap, i.e., horizontal, to the ground surface. We also plan to use tubes at different depths within the cap. The tubes above the infiltration barrier will be vertical and situated at many positions within the cap area. The tubes under (within six inches) of the infiltration barrier will be horizontal and are designed to detect liner leakage or, to phrase it more optimistically, to verify the lack of leakage. What we found difficult in the original TDHE comment was what we interpreted as a suggestion to place additional horizontal tubes at greater depths which we envision would require excavation into the burial trenches. To avoid this hazard, we plan to construct at least one vertical well and neutron access tube into

Mr. Tom J. Wheeler, DOE/ORO

8

December 14, 1988

each of the five trenches. Of necessity these will penetrate the various infiltration barriers to provide access from the surface. These vertical wells will allow us to verify the moisture condition of the trenches through time.

Assuming that the trenches are grouted with acrylamide, it is anticipated that neutron probe readings will indicate saturated conditions at all times after grouting. The polyacrylamide grout is 90% water and the neutron probe cannot distinguish between this bound water and free liquid water. However, the neutron probe readings should allow us to verify that the grout does not desiccate under field conditions through time. The access wells, however, will allow us to verify that no free standing water is present in the grouted trenches and to sample any water which might be present.

9. Are the cesium and strontium radioactive? DOE should do analyses on fertilizers, otherwise U, Th, or other materials may show up from that source. (Page 10)

The cesium and strontium will not be radioactive. We will employ the stable isotopes of the elements, i.e., just the routine chemical grade forms. Because Cs and Sr are present naturally at only trace levels in plants (i.e., <1 and <10 mg/kg, respectively), they represent a safe way to detect any root penetration of the infiltration and biointrusion barriers via vegetation sampling. Neither element is toxic to plant growth and neither is classified as a hazardous or toxic element. They are also ideal tracers for ^{137}Cs and ^{90}Sr which are the radionuclides of greatest concern for the performance of SWSA 6.

We will also analyze whatever fertilizer we use for trace amounts of U and Th. We will also provide, in annual summaries of site performance, an assessment of what these small additions of natural radionuclides mean in terms of site performance and environmental monitoring.

10. The discussion on Page 12 supports the Division of Radiological Health's comments and ideas for more extensive monitoring for any and all demonstration projects. (Page 12)

We will continue our extensive monitoring of the TARA demonstration and will continue to modify our monitoring strategy to accommodate additional concerns as appropriate.

11. "No radioactivity" is defined as no "hard beta and/or alpha." What about soft beta, e.g., H-3 or gamma? (Page 18)

We have analyzed samples from the monitoring wells at the SWSA 4 in situ grouting demonstration site for tritium and, surprisingly, detected none unlike samples from the TARA site. Our low-level

Mr. Tom J. Wheeler, DOE/ORO

9

December 14, 1988

alpha-beta counter has a gamma detector which is used for coincident counting event rejection; but we do not report gamma activity per se. Our gamma-emitting isotopes of greatest concern, ^{137}Cs and ^{60}Co , are also hard beta emitters. Because no hard beta was detected in these samples, we did not proceed to the next level of identification, gamma spectroscopy. This tiered sample analysis protocol, saves us from doing a lot of unnecessary radiochemical analyses. It was not our intention in the discussion on p. 18 to present details of our methods but only to point out that in past water-filling tests, we were in a position to detect any adverse environmental effect of these tests. Because no contamination was found in the surrounding groundwater monitoring wells before, after, or during the tests, we offered this information to support our assessment of the safety of the water-filling tests.

Sincerely,

L. D. Bates, Manager
Remedial Action Program

LDB:msc (E121488)

cc: H. M. Braunstein
K. W. Cook
E. C. Davis
C. E. Nix
B. P. Spalding
C. L. Stair
file - LDB

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION IV

345 COURTLAND STREET
ATLANTA, GEORGIA 30365

JUL 11 1988

REF: 4WM-GP

Mr. Joseph A. Lenhard
Assistant Manager for
Energy Research and Development
Department of Energy
Oak Ridge Operations
P. O. Box E
Oak Ridge, Tennessee 37831

Dear Mr. Lenhard:

The Underground Injection Control (UIC) Permits Unit of the U.S. Environmental Protection Agency (EPA), Region IV has reviewed the information submitted on May 19, 1988, on the proposed demonstration project grout injection wells. Based on this review and the meeting between EPA and the Department of Energy (DOE) on June 24, 1988, we feel that significant concerns with the project exist.

In order to further assess the need for a UIC permit for this project, we ask that you submit existing information or prepare a written report on the following:

- Characterization of waste in trenches to be grouted;
- Characterization of surficial geologic conditions including soils, depth to the water table, and the uppermost aquifer;
- Compatibility of the grout with various waste materials and fluids including the results of any bench or pilot tests;
- Results of past on-site demonstration activities;
- Past testing procedures and future testing procedures to demonstrate (1) successful polymerization of injected grout and (2) non-migration of grout outside of trench; and
- Long term stability of the grout including the effects of biodegradation and dehydration.

-2-

After our review of this information we would like to meet with DOE to discuss any concerns we may have. If you have any questions, please call Ms. Annie Godfrey, of my staff at 404/347-3866.

Sincerely yours,

William J. Taylor
William J. Taylor, Chief
Underground Injection Control Section
Ground-Water Protection Branch

cc: Art Linton, Environmental Assessment Branch

Lewing
H. B. H.
Stecman

Stabilization of Waste Trenches by Grout Injection

October 6, 1988

revised edition

This document is to supplement information formerly submitted by P. S. Rohwer on April 22, 1988 which addressed requirements of the TDHE Rule 1200-4-6, concerning Class V wells. Some questions about this demonstration project were raised by the EPA and are addressed in this document.

The proposed demonstration is part of the Test Area Remedial Action (TARA) project in ORNL's Solid Waste Storage Area (SWSA) 6. The project involves the installation of a group of Class V well. The wells will be used to inject grout into the trenches, solidifying and stabilizing the waste. Figures 1-3 present the location of SWSA 6 and the trench locations.

1. Characterization of surficial geologic conditions including the uppermost aquifer, depth to the water table and soils:

UPPERMOST AQUIFER:

Solid Waste Storage Area (SWSA) 6 is underlain by the Nolichucky shale and Maryville Limestone formations of the Conasauga Group. The formations strike northwesterly at 56 degrees and dip is to the southeast at angles between 30 and 40 degrees (Tucci, 1986). The Conasauga is heavily fractured, providing microscale conduits. The aquifer system is anisotropic; the original bedrock was impermeable, but subsequent folding and weathering has created a secondary fracture system which permits the movement of water in all directions. In the topographic high regions the unconsolidated zone is as deep as 12 m (39 ft), and the water table aquifer may extend 61 m (198 ft) below the ground surface (Davis et al., 1987 p. 91).

The hydraulic conductivity for the unconsolidated zone varies from less than 0.1 ft/day (3.5×10^{-5} cm/s) to 1.0 ft/day (3.5×10^{-4} cm/s). The anisotropy likely ranges between 1:1 to 0.333:1 (strike normal/strike parallel) (Davis et al., 1987, p. 92).

DEPTH TO WATER TABLE

Water table measurements have been taken by the U. S. Geological Survey since 1975. Well number 367, 256.55 m (841.7 ft) above mean sea level, is located in the trench area proposed for the grouting demonstration. According to the ORNL Remedial Action Database, the water level reading taken on January 8, 1988, (during the wet season of the year when groundwater levels are the highest) in well 367 was 239.50 m (785.79 ft) making the depth to groundwater 17.05 m (55.93 ft). The hydrograph showing the seasonal fluctuation in groundwater levels for 1977-1979 is presented in Figure 4 (Webster et al., 1980). The highest level recorded was approximately 14.5 m (47.6 ft) below ground

surface. Data taken on January 8, 1988, from other wells located among the trenches yielded the following information:

<u>well#</u>	<u>water elevation</u>	<u>land elevation</u>	<u>depth to water</u>
1	787.61 ft	832.29 ft	44.88 ft
2	787.33	837.27	49.94
3	796.42	838.13	41.71
7	788.91	839.38	50.47

The grout will only be injected to the bottom of the trenches. The trenches are 5 m (16.4 ft) in depth. During the highest groundwater level recorded, the bottom of the trench was still 9.5 m (31.2 ft) above the water table.

SOIL CHARACTERISTICS

The five trenches are located in ruptic ultic dystrochrepts: young soils with high silt content, intermittent clay enriched horizons and organic content. These soils are derived from the Maryville limestone. The slope ranges from 12-25% and is weathered (Davis et al., 1987, pp. 31, 47-49). The soil map is presented in Figure 5. The following tables are attached to provide additional information about the soils (Davis et al., 1987):

- Table 1 Physical properties
- Table 2 Engineering properties
- Table 3 Chemical properties

2. Compatibility of the grout with various waste materials and fluids including the results of any bench or pilot tests:

Larson and May (1983) performed experiments to test the compatibility of various types of hazardous waste with grout. First, the effect of the various wastes on set time were tested. Adverse effects on set time were noted when the acrylamide was mixed with HCl solution (acid), ammonium and sodium hydroxide solutions (bases), and cupric sulfate (salt). All were 10% solutions. No adverse effects were noted with ammonium chloride (salt) or several hydrocarbons: benzene, trichloroethylene, unleaded gas or oil (SAE 30).

Secondly, Larson and May tested the effect of various wastes on grout that had already set. After twenty days, the wastes caused either shrinking or swelling of the grout:

SHRINKING

Hydrochloric acid
Cupric sulfate

SWELLING

Potassium Chromate
Ammonium hydroxide
Sodium hydroxide
Toluene
Ammonium chloride
Benzene
Trichloroethylene
Phenol
Gas (unleaded)
Oil (SAE 30)

Because the trenches proposed for the grouting demonstration were used specifically for low-level radioactive waste, it is highly unlikely that any strong acids, bases or salt solutions are present.

To test the compatibility of the acrylamide with the types of waste that are found in the five SWSA 6 trenches, samples of trench leachate and bottom soil were taken from each of the trenches for laboratory testing. Not only was the "set" time for the grout tested, but the percentage of grout that polymerized was measured by assaying for the residual acrylamide monomer as well. The results of the study are shown in the following table taken from written correspondence with B. Spalding on July 25, 1988, pp. 9-11:

<u>SAMPLE</u>	<u>TYPE</u>	<u>SETTING TIME(MIN)</u>	<u>% POLYMERIZATION</u>	<u>POST-GROUTING CONDUCTIVITY</u>
water	water	9		
Trench 2	leachate	9	99.52	
Trench 3	leachate	9	99.56	
Trench 5	leachate	9	99.49	
Trench 6	leachate	9	99.49	
Trench 2	soil	11	99.50	<2.4 x 10 ⁻⁷
Trench 3	soil	7	99.66	<2.5 x 10 ⁻⁷
Trench 4	soil	5	99.65	<2.6 x 10 ⁻⁷
Trench 5	soil	10	99.43	<2.2 x 10 ⁻⁷
Trench 6	soil	10	99.49	<2.5 x 10 ⁻⁷

na=data is not available

None of the samples posed any interference with the set time of the grout, nor were there any adverse effects on the percent of grout that polymerized. The proposed demonstration project will use 190,000 liters of grout which will contain 0.5% residual free acrylamide monomer in an impermeable matrix. Most likely, the monomer would be permanently trapped within the polymerized grout. If any monomer leached from the grout, it is expected that

it would be easily degraded by the soil microorganisms (Lande et al., 1979).

3. Characterization of the waste in the trenches to be grouted:

The waste in the trenches is primarily solid low-level radioactive waste. Because this is a solid low-level waste trench, only minimal amounts of liquid waste may be present. The following table lists examples of the waste found in each trench, and the isotopes present. The radioactive waste is either encased in lead shielding or bagged in plastic.

<u>Trench</u>	<u>Waste</u>	<u>Radionuclides</u>
2	Cell waste, paper, shoe covers, gloves, filters	Co, Ir, Ra, Sb, Cs
3	reactor ash, NO3 pellets, cell furnace, CV filters	U, Pu, Np, C, Sr, Cs Be, Ca, Eu, Co
4	EDM dielectric oil, scrap from cell A hoses, clothing, CaO lime	Pu, Cs, U, Sr, Ag, H, Cm
5	Cell waste, plastic suits, shoe covers, gloves, filters	Ir, Eu, Gd, K, Au, Co, Sr,
6	No shipment papers are available for this trench, but the type of waste is similar to that of the other four trenches.	

This information was taken from an incomplete set of waste shipment records. The list should be regarded as examples of the typical types of waste found in the trenches.

Samples of trench leachate and groundwater were used to characterize the waste in the absence of thorough records. The following characteristics are presented in Tables 4 and 5 from written correspondence with B. Spalding, July 25, 1988: pH, conductivity, hardness, alkalinity, dissolved solids, gross alpha and beta activity levels, moisture and radionuclide concentration.

4. Results of past on-site demonstration activities:

A 1985 study tested seven grout formulations using soils from Oak Ridge, TN, and Maxey Flats, KY. for ability to reduce hydraulic conductivity and ability to penetrate backfilled soils. Three small, pilot-scale trenches were grouted; two were grouted with sodium silicate and one with acrylamide. Acrylamide grout was more effective than particulate grouts in soil penetration

(Table 2, p. 392) and performed more consistently than the other soluble grouts (p. 392) (Spalding et al., 1985 pp. 389-396). The polyacrylamide-filled trench exhibited essentially immeasurable hydraulic conductivity.

Another field study was conducted at ORNL in SWSA 4 in 1987. Two small waste trenches were filled with 34,000 L of polyacrylamide grout. The grout significantly reduced hydraulic conductivity; in four wells conductivity in the trenches was below detection limits (Spalding et al., 1987).

No detectable amounts of acrylamide or grout by-products have been detected in the monitoring wells surrounding either of the test sites (personal communication with B. Spalding, August 9, 1988).

5. Long term stability of the grout including the effects of biodegradation and dehydration:

The acrylamide gels are subject to mechanical deterioration as a result of freezing and dehydration. However, in temperate, humid climates deterioration is minimal. Under moist soil conditions, the polymer is resistant to microorganisms, dilute acids and bases, as well as the salts and gases ordinarily found in soils (Lande et al., 1979).

The acrylamide monomer that is released into the environment is degraded by microorganisms found naturally in soils and water. Because it is easily degraded, the toxic monomer would only persist a few days and does not bioaccumulate. Soil microorganisms degrade the acrylamide monomers in only six days after a lag time of two days (Lande et al., 1979). Although acrylamide monomers are leachable, it is unlikely that any will reach either wells used for drinking water or surface water before degradation occurs.

A microbial degradation study of the set polymer resulted in calculations that estimate the grout to have an average half-life of 362 years with a decomposition rate constant of 5.5×10^{-6} /day (Spalding et al., 1987, p. 47. Tables p. 49). The degradation is a first-order rate reaction (ie. after two half-lives, 25% of the grout is remaining).

6. Past testing procedures and future testing procedures to demonstrate (1) successful polymerization of injected grout and (2) non-migration of grout outside the trench:

The bench test analyzing grout compatibility with the trench leachate samples involved adding 10 mL of grout solution to 5 mL of leachate. The grout solution was made of acrylamide, methylenebisacrylamide, triethanolamine and potassium ferricyanide. Time of grout set was measured when grout would no longer flow in the beaker. To test the soil compatibility the same procedure was used with 5.00 g of soil.

After overnight storage, the samples were extracted with water to determine the amount of residual monomer. Samples were placed in a blender with 100 mL of water and macerated. The homogenate was filtered. The filtrate was analyzed for acrylamide and methylenebisacrylamide using a direct injection on a high pressure liquid chromatograph (HPLC). The following table lists the residual concentrations of acrylamide and methylenebisacrylamide from grout prepared in trench leachate:

<u>Sample</u>	<u>Acrylamide(mg/L)</u>	<u>methylenebis- acrylamide (mg/L)</u>
uncatalyzed grout (no polymerization)	100,800	5360
Trench 2	480	0.9
Trench 3	462	0.7
Trench 5	486	0.7
Trench 6	510	0.9

For specific details of the procedure, please refer to the attached document Compatibility of Acrylamide Grout with Burial Trench Contents in Test Area for Remedial Actions at Oak Ridge National Laboratory Solid Waste Storage Area 6, pp 4-6.

Field procedures for testing polymerization of the acrylamide grout are less quantitative, but offer a high degree of confidence in the control of grout set. First, each batch of grout and catalyst is tested before injection into the trench by mixing equal volume samples and determining set time. This procedure verifies that the batch (normally 3000 gallons) was prepared and blended correctly. This also confirms that the reactivity of the catalyst, ammonium persulfate, is within the desired range of set times, from 20 to 60 minutes. After a batch is pumped into a trench, the liquid level in the trench is measured at the injection wells and intratrench monitoring wells. Probing of the liquid with a steel weight on a measuring tape is continued until the grout has set in all wells. Both set time and depth to set grout are recorded before the injection of another batch. Water levels in surrounding water monitoring wells are recorded. Water samples from monitoring wells are taken daily during the grouting campaign and at exponentially decreasing intervals after completion for laboratory analysis.

Citations:

Avanti International AV-100 Chemical Grout Technical Manual.

Davis, E.C., D.K. Solomon, R.B. Dreier, S.Y. Lee, P.M. Craig, A.D. Kelmers, and D.A. Leitzke. 1987. Summary of Environmental Characterization Activities at the Oak Ridge National Laboratory Solid Waste Storage Area Six FY 1986 through FY 1987. ORNL/RAP/LTR-87/68.

Karol, R.H., Chemical Grouts and their properties. In Proceedings of the Conference on Grouting in Geotechnical Engineering. ed. W.H. Baker.

Lande, S.S, S.J. Bosch and P.H. Howard. 1979. Degradation and Leaching of Acrylamide in Soil. J. Environ. Vol. 8, no.1.

Larson, R.J. and J.H. May. 1983. Geotechnical Aspects of Bottom Sealing Existing Hazardous Waste Landfills by Injection Grouting (Phase I - Compatibility Studies). pp. 513-529 In Proceedings of the First Annual Hazardous Materials Management Conference. Tower Conference Management Company, Wheaton, Illinois.

Spalding, Brian (Environmental Sciences Division) Personal communication to Susan Michaud (Environmental and Health Protection) 9 August 1988.

Spalding, Brian (Environmental Sciences Division). Written communication: Compatibility of Acrylamide Grout with Burial Trench Contents in Area of Remedial Actions at Oak Ridge National Laboratory Solid Waste Storage Area 6. to Susan Michaud (Environmental and Health Protection) 25 July, 1988.

Spalding, B.P., L.K. Hyder and I.L. Munro. 1985. Grouting as a Remedial Technique for Buried Low-Level Radioactive Wastes. J. Environ. Qual. 14:389-396.

Spalding, B.P., S.Y. Lee, C.D. Farmer, L.K. Hyder and P. Supaokit. 1987. In situ Grouting of Buried Transuranic Waste with Polyacrylamide. in Oak Ridge Conference Proceedings. pp. 39-76. Conf-871075, Vol. I, Part 3. Martin Marietta Energy Systems, Inc. Oak Ridge, TN.

Spooner, P.A., G.E. Hunt, V.E. Hodge, P.M. Wagner and I.R. Melnyk. 1984. Compatibility of Grouts with Hazardous Wastes. United States Environmental Protection Agency EPA-600/S2-84-015 Mar.

Tucci, P. 1986. Groundwater Flow in Melton Valley, Oak Ridge Reservation, Roane County, Tennessee - Preliminary Model Analysis. U.S. Geological Survey. Nashville, Tennessee. WRI 85-4221.

Webster, D.A., J.S. Beatty, P.M. Benjamin, and W.M. Trnum. 1980. Water Level Data for Wells in Burial Ground 6, Oak Ridge National Laboratory, Tennessee, 1975-1977 U.S. Geological Survey Open-file Report 81-57.

Figure 1. Location of the solid waste storage areas (SWSAs) at ORNL.

Fig. 2. Location of TARA site groundwater monitoring wells.

Figure 3. TARA site grout injection locations. The longitude and latitude are measured from the center of the five trench area.

Figure 4. Hydrograph from well 367 from April 1977 to July 1979.

Figure 5. Soil map with locations of soil profiles, trenches and core drillings.

Table 2 Particle size (in mm) distribution, including rock fragments, and USDA soil textures of six soils at Skwa-6.

Pit Horizon	Depth (cm)	VCS 2-1	CS 1-.5	MS .5-2.5	FS .25-.1	VFS .1-.05	CSI .05-.02	FSI .02-.002	Sand 2-0.05	Silt .05-.002	Clay <0.002	Fragment >2mm	Texture with Modifier
1 ARA Site	A-Bw 0 - 8	10.6	3.6	0.9	1.5	2.9	29.0	40.9	19.5	69.9	10.6	24.50	shaly silt loam
	C-Cr1 8 - 40	19.0	8.6	1.3	3.3	11.1	12.2	28.1	32.9	40.3	26.8	71.12	ext. shaly loam
	Cr2 40 - 110	16.8	9.6	1.3	1.6	0.3	5.2	24.7	29.6	29.9	40.5	85.99	ext. shaly clay
	Cr3 110 - 145	28.0	16.5	4.6	5.9	3.6	8.3	12.2	58.6	20.5	20.9	78.27	ext. shaly scl**
	Cr4 145 - 205	26.0	11.7	2.9	4.0	4.6	12.6	19.4	49.2	32.0	18.8	94.00	ext. shaly loam
3	A-E 0 - 18	8.0	3.2	1.1	3.4	10.4	43.6	27.0	26.1	70.6	3.3	9.39	silt loam
	BE 18 - 25	6.7	3.1	1.3	3.3	11.1	22.5	28.8	25.5	51.3	23.2	8.67	silt loam
	Bt-C 25 - 105	9.7	7.0	0.5	1.0	3.2	4.6	15.8	21.4	20.4	58.2	57.19	very shaly clay
	C1 105 - 132	11.5	4.5	0.9	2.4	8.5	17.4	17.4	27.8	34.8	37.4	67.00	ext. shaly clay loam
	C2 132 - 150	6.1	2.1	0.4	1.6	13.8	16.1	13.9	24.0	30.0	46.0	66.76	ext. shaly clay
4	CrMn 175 - 260	23.8	9.1	1.2	3.8	6.5	10.9	17.5	44.4	28.4	27.2	78.93	ext. shaly clay loam
	Cr 201 - 213	11.6	3.0	0.5	3.1	13.4	14.5	17.9	31.6	32.4	36.0	58.61	very shaly clay loam
	A-E 0 - 27	3.5	1.7	0.3	0.5	2.1	54.4	30.8	8.1	85.2	6.7	10.45	silt
	Bt1-Bt2 27 - 70	12.3	6.7	1.7	3.9	9.8	19.5	27.1	10.1	46.6	43.3	14.59	shaly clay
	Bt3-Cbt 70 - 110	1.3	1.1	0.2	0.5	1.9	10.8	23.9	34.4	26.8	38.8	25.52	shaly clay loam
9	C1 110 - 170	0.8	0.5	0.3	0.9	5.0	14.3	23.1	7.5	37.4	58.9	46.69	very shaly clay
	C2 170 - 190	13.0	9.7	1.2	2.0	3.4	17.2	18.5	29.3	35.7	55.1	37.75	very shaly clay
	Cr1 190 - 230	2.2	2.1	0.3	2.1	9.6	14.4	21.6	16.3	36.0	35.0	86.14	ext. shaly clay
	Cr2 205 - 300	31.4	7.3	0.4	1.8	2.4	10.4	19.1	43.3	29.2	27.2	94.03	ext. shaly clay loam
	Cr3 230 - 300	19.0	10.1	1.7	2.8	3.9	8.4	14.8	37.5	23.2	39.3	92.18	ext. shaly clay loam
10	Cr4 290 - 310	9.6	6.0	0.8	0.8	2.0	12.3	29.8	19.2	42.1	38.7	44.08	very shaly clay loam
	Cr5 310 - 366	16.3	8.3	1.6	4.3	9.6	12.8	8.6	40.1	21.4	38.5	49.84	very shaly clay loam
	Cr6 366 - 396	2.6	1.6	2.4	8.4	7.5	38.9	34.9	22.5	73.8	3.7	4.44	silt loam
	Ap-E 0 - 20	1.5	1.3	2.1	8.7	9.1	17.1	31.6	22.7	48.7	28.6	1.59	clay loam
	Bt1-Bt2 20 - 53	1.7	1.5	1.9	8.6	9.2	26.8	30.6	22.9	47.4	29.7	17.42	gravelly clay loam
10	2Bt3 53 - 80	0.4	0.3	1.0	6.4	12.4	18.7	21.7	20.5	40.4	39.1	10.10	gravelly clay loam
	2Bt5 119 - 190	2.8	2.9	1.0	2.2	2.5	21.2	34.5	11.4	55.7	32.9	12.73	silty clay loam
	Ap 0 - 14	5.2	4.2	1.7	3.1	3.8	6.1	31.2	18.0	37.3	44.7	16.30	shaly clay
	Btg 23 - 50	4.7	3.3	0.9	1.5	1.6	7.2	57.2	12.0	64.4	23.6	54.33	very shaly silt loam
	Cr 50 - 74	12.8	8.0	1.6	1.8	0.7	3.2	24.1	24.9	27.3	47.8	86.96	ext. shaly clay loam
SI	Cr 74 - 84	6.2	4.5	2.2	4.8	2.9	4.5	25.3	20.6	29.8	49.6	75.71	ext. shaly clay
	3Cr 84 - 120	20.4	9.6	2.2	2.4	2.2	6.1	27.2	36.8	33.3	29.9	88.66	ext. shaly clay loam
	4Cr 120 - 123	7.3	5.0	3.2	10.4	7.0	3.9	18.3	32.8	22.2	45.0	67.85	ext. shaly clay
	5Cr 123 - 150	13.1	9.1	2.9	6.6	14.8	10.5	16.4	46.5	26.9	26.6	91.21	ext. shaly scl**
	APZ 100	0.5	0.5	0.9	6.3	9.2	15.1	19.0	17.4	34.1	48.5	1.22	clay
BPZ	PZ 200	5.2	6.7	29.7	28.5	2.1	2.2	1.1	72.2	3.3	24.5	43.52	v. gravelly clay loam
	BPZ 300	3.3	3.6	1.7	3.4	5.4	1.1	37.4	17.4	38.5	44.1	93.71	ext. shaly clay

SI=shallow trench, APZ=above pebble zone, PZ=pebble zone, BPZ=below pebble zone. * ext. = Extremely. ** scl = sandy clay loam.

Table 2. Atterburg limits of five soils at SWSA-6

TARA
Site

Pit	Horizon	Depth (cm)	Liquid limit	Plastic limit	Plasticity index	Flow index	Shrinkage limit	Activity ratio
1	A-Bw	0 - 8	50.5	32.2	18.3	14.4	24.0	1.73
	C-Cr1	8 - 40	29.3	20.5	8.8	10.0	18.0	0.33
	Cr2	40 - 110	-	-	-	-	-	-
	Cr3	110 - 145	-	-	-	-	-	-
	Cr4	145 - 205	-	-	-	-	-	-
3	A-E	0 - 18	43.3	29.6	13.7	7.2	23.3	4.15
	BE	18 - 25	27.1	19.8	7.3	9.8	17.9	0.31
	Bt-C	25 - 105	49.0	25.2	23.9	14.2	17.4	0.41
	C1	105 - 132	49.6	33.7	15.9	8.8	25.7	0.43
	C2	132 - 150	-	-	-	-	-	-
	Cr-Mn	175 - 260	-	-	-	-	-	-
	Cr	201 - 213	-	-	-	-	-	-
4	A-E	0 - 27	22.4	15.6	6.8	1.4	15.0	1.01
	Bt1-Bt2	27 - 70	-	-	-	-	-	-
	Bt3-Cbt	70 - 110	43.1	28.7	14.4	7.9	22.5	0.37
	C1	110 - 170	-	-	-	-	-	-
	C2	170 - 190	61.8	45.9	15.9	26.8	34.6	0.29
	Cr1	190 - 230	-	-	-	-	-	-
	Cr2	230 - 310	-	-	-	-	-	-
	Cr5	310 - 366	-	-	-	-	-	-
9	Ap-E	0 - 20	27.2	16.4	10.7	4.2	14.5	2.89
	Bt1-Bt2	20 - 53	31.2	17.8	13.4	4.9	14.8	0.47
	2Bt3	53 - 80	47.2	29.3	17.9	3.1	22.0	0.60
	2Bt5	119 - 190	49.4	33.4	16.0	17.0	25.5	0.41
10	Ap	0 - 14	35.6	23.1	12.5	8.1	18.9	0.38
	Bt	14 - 23	46.5	23.6	22.9	8.9	16.4	0.51
	Btg	23 - 50	-	-	-	-	-	-
	Cr	50 - 74	-	-	-	-	-	-
	2Cr	74 - 84	51.5	28.3	23.2	9.7	19.8	0.47
	3Cr	84 - 120	-	-	-	-	-	-
	4Cr	120 - 123	-	-	-	-	-	-
	5Cr	123 - 150	-	-	-	-	-	-

Table 3. The distribution of pH, ammonium acetate extractable bases, sodium dithionite extractable (CBD) iron and manganese, and hydroxylamine reducible (HA) manganese for five soil profiles at SWSA-6

Pit	Horizon	Depth	pH (1:1)		NH ₄ OAc		Fe	Mn	HA
			Water	KCl	Ca	Mg			
			-----ppm-----						
TARA Site	1 A-Bw	0 - 8	6.57	5.75	3507	226	826	399	297
	C-Cr1	8 - 40	6.73	4.93	2261	171	1611	627	49
	Cr2	40 - 110	4.82	3.48	1658	544	1927	229	7
	Cr3	110 - 145	4.96	3.30	1924	343	1642	908	150
	Cr4	145 - 205	5.00	3.38	2688	361	1305	1534	95
3	A-E	0 - 18	6.45	5.79	2987	137	765	918	40
	BE	18 - 25	6.11	5.18	1537	138	1550	752	4
	Bt-C	25 - 105	5.38	4.31	2492	142	3626	207	2
	C1	105 - 132	4.60	3.46	238	166	3326	100	12
	C2	132 - 150	4.90	3.52	44	196	3886	1368	167
	CrMn	175 - 260	5.02	3.48	77	159	2172	874	156
	Cr	201 - 213	5.20	3.61	33	192	2723	161	48
4	A-E	0 - 27	4.81	3.75	150	9	1255	620	39
	Bt1-Bt2	27 - 70	5.09	3.59	157	129	2855	34	56
	Bt3-Cbt	70 - 110	5.31	3.60	14	57	3580	114	13
	C1	110 - 170	5.47	3.51	9	73	5467	117	17
	C2	170 - 190	5.11	3.55	10	79	2315	126	211
	Cr1	190 - 230	4.84	3.55	27	186	3480	988	125
	Cr2	205 - 300	5.21	3.61	33	217	3264	2834	609
	Cr3	230 - 300	4.84	3.55	11	327	1876	1820	209
	Cr4	290 - 310	5.28	3.69	24	395	2850	1950	117
	Cr5	305 - 366	5.11	3.51	34	477	1872	1628	182
	Cr6	366 - 396	4.90	3.54	50	491	1443	2215	324
9	Ap-E	0 - 20	5.91	5.55	1401	114	2683	13	29
	Bt1-Bt2	20 - 53	4.49	3.79	270	3	1948	11	6
	2Bt3	53 - 80	5.00	3.69	150	90	2203	182	1
	2Bt5	119 - 190	4.90	3.48	61	40	2683	11	1
10	Ap	0 - 14	4.68	3.55	912	325	2087	592	47
	Bt	14 - 23	4.80	3.15	556	246	2652	1552	164
	Btg	23 - 50	4.81	3.48	406	256	2642	521	45
	Cr	50 - 74	4.81	3.42	722	629	2244	932	62
	2Cr	74 - 84	5.05	3.45	600	488	4279	259	22
	3Cr	84 - 120	6.50	5.09	3,488	1305	2539	103	208
	4Cr	120 - 123	6.95	6.19	10,056	1468	2855	200	25
	5Cr	123 - 150	7.25	6.25	17,643	1305	2297	165	224
	APZ	100	4.88	3.55	29	118	4029	52	1
	PZ	200	4.71	3.50	50	49	2127	155	1
	BPZ	300	4.59	3.48	32	255	3723	81	1

Note: ST=shallow trench, APZ=above pebble zone, PZ=pebble zone, BPZ=below pebble zone.

Table 3 Summation of mineralogical analyses from x-ray diffraction and differential scanning calorimetry determinations.

Minerals present in clay fraction (<.002 mm)										
Pit	Horizon	Depth	Smectite	Vermiculite	HIV*	Chlorite**	Kaolinite	Illite	Oxides	Gibbsite
ARA ite {	A-Bw	0-10	NO	H	Tr	NO	Tr	M	Tr	NO
	Cr4	145-205	NO	M	NO	NO	Tr	H	Tr	NO
	3									
	A-E	0-18	NO	M	M	NO	Tr	M	Tr	NO
	Bt-C	84-105	NO	H	M	NO	Tr	M	Tr	NO
	C2	132-150	NO	H	L	NO	Tr	H	Tr	NO
	Cr	201-213	NO	M	Tr	NO	Tr	H	Tr	NO
	4									
	A-E	0-27	NO	Tr	H	Tr	Tr	L	Tr	NO
	Bt1-Bt2	27-70	NO	L	H	Tr	Tr	L	Tr	NO
	Cr1	190-230	NO	M	M	NO	Tr	M	Tr	NO
	Cr4	290-310	NO	M	L	NO	Tr	H	Tr	NO
9	Ap-E	0-20	NO	L	H	Tr	Tr	L	Tr	NO
	Bt1-Bt2	20-53	NO	Tr	H	L	L	L	Tr	NO
	2Bt3	53-85	NO	Tr	H	L	L	L	Tr	NO
	2Bt5	119-190	NO	L	H	Tr	L	L	Tr	Tr
10	Ap	0-14	Tr	M	Tr	NO	Tr	M	Tr	NO
	Btg	23-50	Tr	H	Tr	NO	Tr	H	Tr	NO
	Cr	50-74	Tr	H	Tr	NO	Tr	H	Tr	NO
	5Cr	123-150	Tr	M	Tr	NO	Tr	H	Tr	NO
ST	APZ	100	NO	L	H	NO	L	M	Tr	NO
	PZ	200	NO	L	M	NO	L	M	Tr	NO
	BPZ	300	NO	L	M	NO	Tr	M	Tr	NO

Notes: NO=not detected, Tr=trace(<10%), L=low(10-20%), M=medium(20-30%), H=high(>30%).

* HIV=hydroxy interlayered vermiculite. **Chlorite=pedogenic chlorite. ST=shallow trench, APZ=above pebble zone, PZ=pebble zone, BPZ=below pebble zone.

Table 3. Organic carbon distributions in six soils at SWSA-6.

TARA
Site {

Pit	Horizon	Depth (cm)	Carbon (%)
1	A-Bw	0 - 8	4.33
	C-Cr1	8 - 40	0.59
	Cr2	40 - 110	0.24
	Cr3	110 - 145	0.12
	Cr4	145 - 205	0.12
3	A-E	0 - 18	4.10
	BE	18 - 25	0.65
	Bt-C	84 - 105	0.61
	C1	105 - 132	0.17
	C2	132 - 150	0.13
	CrMn	175 - 260	0.05
	Cr	201 - 213	0.11
4	A-E	0 - 27	0.74
	Bt1-Bt2	27 - 70	0.28
	Bt3-CBt	70 - 110	0.40
	C1	110 - 170	0.10
	C2	170 - 190	0.09
	Cr1	190 - 230	0.08
	Cr2	205 - 300	0.05
	Cr3	230 - 300	0.01
	Cr4	290 - 310	0.03
	Cr5	310 - 366	0.02
	Cr6	366 - 396	<0.01
9	Ap-E	0 - 20	1.80
	Bt1-Bt2	20 - 53	0.48
	2Bt3	53 - 80	0.09
	2Bt5	119 - 190	0.09
10	Ap	0 - 14	0.73
	Bt	14 - 23	0.45
	Btg	23 - 50	0.39
	Cr	50 - 74	0.12
	2Cr	74 - 84	0.14
	3Cr	84 - 120	0.44
	4Cr	120 - 123	0.72
	5Cr	123 - 150	0.47
ST	APZ	100 cm	0.17
	PZ	200 cm	0.08
	BP	300 cm	0.06

ST = shallow trench, APZ = above pebble zone, PZ = pebble zone, BPZ = below pebble zone

Table 4 - Gross chemical and radiochemical characteristics of burial trench leachate and groundwater samples.

Sample	Date Collected	pH	Electrical		Alkalinity	Dissolved Solids	Gross	
			Conductivity	Hardness			Alpha	Beta
			(dS/m)	(mg CaCO ₃ /L)		mg/L	(dpm/mL)	
T-2	10-30-87	6.2	170	86	54	60	7	12
T-3	10-27-87	7.2	760	242	166	480	<1	103
T-4	11-03-87	6.4	1100	168	446	200	3	20800
T-5	10-27-87	6.7	510	184	68	440	187	43
T-6	10-30-87	6.1	740	298	158	420	nd	257
Pond	11-03-87	6.2	240	136	78	120	nd	nd
Ground								
Water*	11-20-87	6.8	590	481	381	544	nd	0.3
Std. Dev.*		0.2	217	185	124	324	-	0.4

* Groundwater characteristics are the average and standard deviation for 15 samples collected from the monitoring wells in and surrounding the test area.

nd = not detected.

Table 5 - Radionuclide and moisture contents of burial trench soil samples.

Sample	Moisture	^{137}Cs	^{60}Co	^{90}Sr
	(%)	(	dpm/g	)
Trench 2	17.9	1060	nd	3590
Trench 3	18.3	3350	nd	72800
Trench 4	16.4	128	nd	410
Trench 5	5.9	622	995	nd
Trench 6	13.7	9580	nd	15800
Trench 3 Cap	15.2	17	nd	nd

nd - not detected. Detection limits were 1.4 dpm/g, 2 dpm/g, and 6 dpm/g for ^{137}Cs , ^{60}Co , and ^{90}Sr , respectively.

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION IV

345 COURTLAND STREET
ATLANTA, GEORGIA 30365

DEC 16 1988

Mr. Joseph A. Lenhard
Assistant Manager for Energy Research and Development
Department of Energy
Oak Ridge Operations
P.O. Box 2001
Oak Ridge, Tennessee 37831

Dear Mr. Lenhard:

The Underground Injection Control (UIC) Program of the U.S. Environmental Protection Agency (EPA) Region IV has received your letter and the attached documents dated October 25, 1988, concerning the proposed stabilization of waste trenches in Waste Area Grouping (WAG) 6 by grout injection. Your letter stated that the information submitted was intended to be a Class V UIC permit application; however, the submittal appears to be a response to my July 11, 1988, letter where I requested additional technical information regarding the stabilization proposal. For clarification purposes, the submittal was not reviewed or considered to be a permit application, but was reviewed only as an informational package.

After reviewing the information submitted, the UIC Program continues to have technical concerns with the proposed grout injection project. We are concerned that the trenches have not been adequately characterized such that grout compatibility with the waste is assured. We also have other concerns including questions about the long term effectiveness of the acrylamide grout, especially in trenches located above the water table.

To help us resolve these concerns, we have requested that the EPA Risk Reduction Engineering Laboratory (RREL) in Cincinnati, Ohio review your injection/stabilization proposal in order to help us assess if the proposed demonstration project is appropriate. We have a meeting scheduled with RREL in Cincinnati in mid January. We will be providing you with comments and recommendations developed from this meeting as soon as possible. We will also notify you at that time concerning our decision of the need for ORNL to obtain a UIC permit for the demonstration project.

-2-

We are coordinating the UIC review with the RCRA and CERCLA programs since the demonstration project is part of a RCRA/CERCLA remedial investigation and feasibility study. It is our understanding that grout stabilization is one of several remediation alternatives being considered for the trenches in WAG 6. From our discussions with staff of the RCRA and CERCLA programs, it is important that information generated from the test demonstration project be useful in assessing the feasibility of this remediation alternative for remediation of other trenches in the WAG 6 area. We will be taking the RCRA and CERCLA program needs into consideration as we make our decision regarding the UIC issues.

If you have any questions, please phone me at FTS 257-3866.

Sincerely Yours,

William D. Taylor, Chief
Underground Injection Control Section
Ground-Water Protection Branch

1. T. L. Ashwood
2. J. S. Baldwin
- 3-5. L. D. Bates
6. W. J. Boegly
7. H. M. Braunstein
8. T. W. Burwinkle
- 9-10. K. W. Cook
- 11-16. E. C. Davis
17. H. R. Gaddis
18. S. B. Garland
19. D. D. Huff
20. L. D. Hyde
21. L. K. Hyder
22. R. H. Ketelle
23. D. G. Jernigan
24. S. Y. Lee
25. L. W. Long
26. L. E. McNeese
27. L. J. Mezga
28. M. E. Mitchell
29. T. E. Myrick
30. C. E. Nix
- 31-34. P. T. Owen
35. R. K. Owenby
36. T. A. Perry
37. D. E. Reichle
38. P. S. Rohwer
39. T. H. Row
- 40-49. B. P. Spalding
50. S. H. Stow
51. L. E. Stratton
52. J. R. Trabalka
53. R. I. Van Hook
54. L. D. Voorhees
- 55-57. Laboratory Records-RC
58. ORNL Patent Section

EXTERNAL DISTRIBUTION

59. R. D. Glenn, Bechtel National Inc., P.O. Box 350, Oak Ridge,
TN 37831-0350
60. OFFICE OF ASSISTANT MANAGER, ENERGY RESEARCH AND DEVELOPMENT,
U.S. DEPARTMENT OF ENERGY, DOE FIELD OFFICE, OAK RIDGE
P.O. BOX 2001, OAK RIDGE, TN 37831-8600
- 61-62. OFFICE OF SCIENTIFIC AND TECHNICAL INFORMATION, P.O. BOX 62,
OAK RIDGE, TENNESSEE 37831

END

**DATE
FILMED**

4 / 30 / 92