DOE/MC/28162-3184

University of Kentucky
**CENTER FOR
APPLIED ENERGY
RESEARCH**

3572 Iron Works Pike
Lexington, KY 40511-8433
FAX: 606-257-0220

DOE/MC/28162--3184

DE93 006358

Coolside Waste Management Research

Project No. DE-AC21-MC91MC28162

Quarterly Technical Report

October 1 to December 31, 1991

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

UK

An Equal Opportunity/
Affirmative Action University

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

COOLSIDE WASTE MANAGEMENT RESEARCH

Technical Progress Report

Contract No: DE-AC21-91-MC8162

Report Period: October 1, 1991 to October 31, 1991

Statement of Project Objectives

Produce sufficient information on the physical and chemical nature of Coolside waste to design and construct physically stable and environmentally safe landfills.

Summary of Progress for Period

Progress for the period was primarily centered on development of analytical methods elemental and mineralogical analysis of the samples, and on preparation of the field facilities to receive the lysimeter fill. Subsamples were selected for laboratory lysimeter testing and analytical method development.

Two subsamples of material (approximately 350 kg each) were selected from Coolside No. 1 and Coolside No. 3 for geotechnical testing (Subtask 2.3), chemical and mineralogic analysis (Subtask 2.2), and laboratory column tests (Task 4). The subsamples chosen are representative of waste material produced during effective operation of the Coolside system at Edgewater Plant.

Considerable progress has been made concerning analytical methods and protocols for chemical determination of the Coolside solids. Sample preparation techniques for thick target PIXE/PIGE have been investigated. Good agreement between measured and actual values for NBS 1633a fly ash standard sample were obtained for all elements except Fe, Ba, and K using PIXE analysis. Li, O, F, Na, Mg, Al, Si, P, Ca, Ti, V, and Mn appeared in the PIGE spectra but have not yet been quantitatively determined.

Design of the field lysimeters is nearly completed. Contracts for cleaning the lysimeters and building the concrete mixing pad have been finalized. Work will commence during the first week of November, and all necessary construction and support work should be finished later that month.

Technical Progress

Introduction

Progress on the Coolside Project during the month of October is summarized below by Task and Subtask.

Task 2. Materials Characterization

Subtask 2.1 - Sample Collection

Two subsamples of material (approximately 350 kg each) were selected from Coolside No. 1 and Coolside No. 3 for geotechnical testing (Subtask 2.3), chemical and mineralogic analysis (Subtask 2.2), and laboratory column tests (Task 4). The samples chosen should be representative of the materials produced during the two runs when the Coolside system was operating effectively at Edgewater Power Plant. Each subsample was thoroughly mixed in a V blender to assure homogeneity. Geotechnical and geochemical tests will be performed on the same subsamples; preliminary results should be completed in early November. These materials will also be used to fill the laboratory leaching columns.

Subtask 2.2 Chemical and Mineralogic Analysis of the Materials

PIXE/PIGE Analysis. A series of experiments were performed to establish an analytical protocol for the thick-target PIXE/PIGE analyses. As noted in the last report, spectroscopic grade graphite powder (Johnson Mathey Ultra F) has been chosen as the binder/dilution material. A series of graphite blanks were prepared and irradiated with an external 2 MeV proton beam. The results of this analysis is shown in Table 1.

Table 1. PIXE Analysis of Blank Graphite Pellets

<u>Preparation Procedure</u>	<u>Observed Contaminants (ppm)</u>
Pressed pellet in s.s. die at 11 MPa	Fe (4.0)
Mixed in s.s. mixer mill and pressed into pellet in s.s. die.	Cr (441), Fe (2700), Ni (5), Cu (7) Zn (9)
Mixed in polystyrene mixer mill with methacrylate beads and pressed into pellet in s.s. die	Fe (11), Cu (1.0), Zn (0.5)

In order to minimize sample contamination, the thick-target PIXE/PIGE samples will be prepared by mixing with spectroscopic grade graphite powder in the polystyrene vials with methacrylate beads.

Three NBS 1633a fly ash standard samples were prepared by mixing approximately 50 mg of the dried fly ash with 500 mg of graphite powder and pressing 300 mg of the mixture into a pellet. These samples were then analyzed by bombarding each sample for five minutes with an external proton beam at 2 and 4 MeV. The preliminary results of the 2 MeV PIXE analysis with a 700 μm thick mylar filter are given in Table 2.

Table 2. PIXE Analysis of NBS 1633a Mixed with Graphite

<u>Element</u>	<u>Average</u>	<u>Stdev</u>	<u>R Stdev</u>	<u>Actual</u>	<u>Observed/Actual</u>
As	141.8	21.4	15.1%	145.0	0.98
Ba %	0.30	0.02	7.1%	0.15	1.98
Ca %	0.96	0.08	8.7%	1.11	0.87
Cr	211.4	10.4	4.9%	196.0	1.08
Cu	97.1	9.0	9.3%	118.0	0.82
Ga	45.9	9.9	21.6%	58.0	0.79
Ge	25.5	8.3	32.5%		
Fe %	5.6	0.4	7.8%	9.4	0.60
Mn	176.3	19.0	10.8%	179.0	0.98
K %	0.91	0.1	6.5%	1.9	0.48
Rb	98.9	0.9	0.9%	131.0	0.75
Sr	660.3	69.6	10.5%	830.0	0.80
Ti %	0.72	0.04	6.1%	0.80	0.90
Zn	183.3	31.5	17.2%	220.0	0.83
Y	105.9	31.3	29.5%		
Zr	190.5	49.3	25.9%		

Good agreement is observed for every element except Ba, Fe, and K. The poor result for K has been traced to an error in the K standard used in these tests. The large error in the Ba and Fe results are due to the poor detector lineshape parameters used in the PIXE calculations. New values are being remeasured in our lab. It should be stressed that these are PRELIMINARY results from an experiment on 11/2. The PIGE results and the 4 MeV data have not yet been analyzed. The elements observed in the PIGE spectra whose concentrations can be obtained with this technique are: Li, O, F, Na, Mg, Al, Si, P, Ca, Ti, V, and Mn. Finally, we would point out that the elements that are masked by the strong Fe signal in the PIXE spectra (Co, Ni, and Cu) will be obtained when the selective Cr filter is added to the X-ray detector. This filter is scheduled to arrive on 11/15.

Ultimate, Proximate, Major, and Trace Element Analysis. Ultimate and proximate analysis of the solid waste material will be performed in accordance with the American Society for Testing and Materials, procedures D 3172 and D 3176. The proximate analysis will include moisture, ash, volatile and fixed carbon. The ultimate analysis will include carbon, hydrogen, nitrogen, sulfur, oxygen, and ash.

The major elements as oxides (SiO_2 , Al_2O_3 , TiO_2 , Fe_2O_3 , CaO , MgO , K_2O , Na_2O , and P_2O_5) will be determined using a variety of analytical techniques. The analytical techniques include (PIXE and PIGE) x-ray fluorescence, ICP, and AA (FIAS).

The trace elements (Ag, As, B, Ba, Be, Cl, Co, Cd, Cr, Cu, F, Hg, Mn, Ni, Pb, Se, V, and Zn) will be determined using the same techniques used in major elements with the addition of an Ion Chromatograph.

The total elemental analysis of the solid waste material will require the conversion of insoluble material to soluble forms by special digestion techniques. Several procedures will be evaluated in this study to assess the efficiency of dissolution. These procedures will include heating in the presence of boiling acid solutions, lithium tetraborate fusion, and dissolution using a CEM microwave digestion oven.

The following tables contain analytical data obtained from a homogenous mixture of Coolside material of the 300 series. Proximate and ultimate analysis were performed in accordance with ASTM procedures. The trace elements were performed using a Spectrametric III ICP spectrometer equipped with a CETAC 5100 Ultrasonic Nebulizer. The major elements were performed using the Spectrametric III DCP. 0.1 gram of Coolside sample was placed into a teflon PFA vessel with a pressure relief valve. Three mls each of HNO_3 , HCL , and HF was added to the material then the samples were heated in the microwave at a pressure of 100 PSI for 20 mins. 50 mls of saturated boric acid was added to the samples and reheated in the microwave then analyzed.

Table 3. Proximate and Ultimate Analysis of Coolside Material.

Proximate Analysis			
<u>Moist.</u>	<u>Volatile Matter</u>	<u>Ash</u>	<u>Fixed Carbon</u>
0.84%	11.99%	85.48%	1.68%
Ultimate Analysis			
<u>Carbon</u>	<u>Hydrogen</u>	<u>Nitrogen</u>	<u>Sulfur</u>
6.66%	0.39%	0.58%	2.02%

Table 4. Major and Trace Elemental Analysis - 3 Replicates of Coolside Material

<u>Major Elements</u>			
<u>Element</u>	<u>CS-1</u>	<u>CS-2</u>	<u>CS-3</u>
Al ₂ O ₃	15.80%	15.30%	15.30%
CaO	13.70%	13.60%	13.20%
Fe ₂ O ₃	10.20%	9.78%	10.00%
K ₂ O	1.10%	1.14%	1.12%
MgO	0.98	0.95%	0.96%
Na ₂ O	1.98%	1.89%	1.98%
SiO ₂	40.60%	39.90%	40.60%

<u>Trace Elements</u>			
<u>Element</u>	<u>CS-1</u>	<u>CS-2</u>	<u>CS-3</u>
Ag	<0.010	<0.010	<0.010
Be	0.016	0.015	0.014
Cd	0.003	0.002	0.003
Co	0.047	0.045	0.045
Cr	0.060	0.062	0.064
Cu	0.100	0.109	0.105
Mn	0.147	0.153	0.155
Ni	0.162	0.160	0.164
Pb	0.055	0.059	0.055
V	0.109	0.101	0.107

Subtask 2.3 Index Testing and Structural Properties Testing

Several samples of Coolside materials 1 and 3 were remolded near ninety five percent of maximum standard dry density and optimum water content. Target densities and moisture contents, as determined by standard compaction tests, were:

	Density	Moisture Content
Sample 1	69.5 lbs/ft ³	35.5%
Sample 3	69.9 lbs/ft ³	36.5%

The remolded samples were sealed and allowed to cure at room temperature. Permeability and unconfined compressive strength tests were performed on samples after curing for 1 day and seven days. Results of the tests are (Table 5):

Table 5. Permeability and Compressive Strength Tests.

1 day

Sample ID	Coefficient of Permeability (cm/sec)	Dry Density (lbs. /ft ³)	Moisture Content (%)	Moisture Content after Test (%)
Sample 1	1.45 X 10 ⁻⁵	66.3	35.53	54.38
Sample 2	4.91 X 10 ⁻⁶	66.5	35.56	54.90

Sample ID	Unconfined Compress. Strength (lbs./in. ²)	Dry Density (lbs. /ft ³)	Moisture Content (%)	Moisture Content after Test (%)
Sample 1	17.90	66.3	35.51	
Sample 3	44.23	66.7	34.87	

7 days

Sample ID	Coefficient of Permeability (cm/sec)	Dry Density (lbs. /ft ³)	Moisture Content (%)	Moisture Content after Test (%)
Sample 1	4.05 X 10 ⁻⁵	65.5	36.63	58.03
Sample 3	1.10 X 10 ⁻⁵	66.1	37.07	54.60

Sample ID	Unconfined Compress. Strength (lbs./in. ²)	Dry Density (lbs. /ft ³)	Moisture Content (%)	Moisture Content after Test (%)
Sample 1	37.02	65.9	34.31	
Sample 3	56.13	66.9	34.46	

Unconfined compressive strengths were greater at seven days curing time for both samples. Coefficients of permeability values were approximately the same for one and seven days curing periods for both samples. Moisture content increased about nineteen percent during permeability tests in all of the samples. Future tests will be performed at extended levels of curing time, to develop a relationship between permeability and unconfined strength, and curing time.

Task 3. Field Lysimeter Tests

Contracts for site preparation were completed with Walker Construction Co. and work will begin during the first week of November. Owing to the isolation of the field station and its location at the top of a steep hill, considerable road maintenance must be performed before heavy equipment or the Coolside materials can be moved to the lysimeter site. Once the road repairs are finished, construction of the concrete mixing pad and emptying of the lysimeters should proceed quickly.

The field lysimeter station has been inspected and various repairs effected. Design of the field lysimeter configuration is nearly completed and lysimeter monitoring configurations are being investigated. Preliminary plans include 7' to 8' of Coolside waste capped with 2' to 3' of natural soil. Each lysimeter will include aluminum or PVC tubes for monitoring moisture and density of the lysimeter fill with a Troxler density/moisture instrument. Thermocouples to monitor lysimeter temperatures are also being considered. The weather monitoring equipment has been prepared and supplies for collecting the leachate samples have been ordered.

Task 4. Laboratory Lysimeter Tests.

Several laboratory column configurations are being considered. Objectives in column design include duplication of field lysimeter configurations, testing of natural liner materials, and testing of other flue-gas desulfurization byproducts to be furnished by Consolidation Coal Co. The laboratory which will house the columns is being prepared. Equipment and supplies necessary to operate the column leachate collection and analysis system are being assembled or ordered as needed.

Plans for the Next Month.

Two cells of the field lysimeters will be emptied and filled with Coolside solid waste. One lysimeter will be filled with compacted material and the other will be filled with uncompacted material.

We will begin preparing the 300+ thick target samples for PIXE/PIGE analysis using the procedure developed. A select set of samples will be analyzed with NBS 1633a standards to examine and refine the accuracy of the thick-target measurements. The most important test will be the addition of the selective Cr filter for reducing the Fe signal and the construction of a "funny" filter for measuring Si, P, and S.

We will begin preparing thin target samples for IBA using the microwave digestion procedure developed by Mr. Thomas. The PIXE/PIGE measurements of the digested material will be compared with the ICP

Unconfined and permeability tests will continue on the samples 1 and 3 remolded near ninety five percent of standard maximum dry density.

Index properties and compaction tests will be performed on large Coolside composite samples. Specimens will be remolded from these samples for future curing and testing.

Figure 1. Dry unit weight as a function of moisture content for different levels of compactive energy - Sample 1.

Figure 2. Dry unit weight as a function of moisture content for different levels of compactive energy - Sample 3.

COOLSIDE WASTE MANAGEMENT RESEARCH

Technical Progress Report

Contract No: DE-AC21-91-MC8162

Report Period: November 1, 1991 to November 31, 1991

Statement of Project Objectives

Produce sufficient information on the physical and chemical nature of Coolside waste to design and construct physically stable and environmentally safe landfills.

Summary of Progress for Period

Progress for the period centered on preparation of the field and laboratory facilities to receive the lysimeter material, and on continued geotechnical testing of the two Coolside subsamples. The road to the field station was improved to allow transport of equipment and Coolside materials to the remote location. The field lysimeters will be cleaned and ready for filling by January 1, 1992. Construction of the laboratory which will house the laboratory lysimeters was completed and several laboratory lysimeter configurations are being considered.

Mineralogic analysis of the bulk Coolside wastes indicate the material is composed principally of unreacted $\text{Ca}(\text{OH})_2$, quartz, mullite, X-ray amorphous Al-Si-Fe oxide or oxyhydroxide, and gypsum(?). A preliminary experiment, which consisted of simply aging a mixture of Coolside material and water for two days at room temperature, indicates the Coolside waste is quite reactive and forms new phases after a short reaction time. Development of analytical methods continued for both the solid material and the leachate samples.

Geotechnical testing indicates the Coolside materials increase noticeably in compressive strength after 27 days of curing at optimum moisture compared with 14 days of curing. Permeability of the materials decreases during the first fourteen days of curing, but a slight increase in permeability was noted after 27 days of curing.

Technical Progress

Introduction

Progress on the Coolside Project during the month of October is summarized below by Task and Subtask.

Task 2. Materials Characterization

Subtask 2.1 - Sample Collection

Preliminary tests were initiated on the two subsamples which will be used for laboratory lysimeter and aging studies

Subtask 2.2 Chemical and Mineralogic Analysis of the Materials

X-ray diffraction analysis of fresh Coolside material indicates it is composed principally of common fly-ash compounds and portlandite. The XRD results and chemical analysis of the bulk material suggest there is considerable unreacted $\text{Ca}(\text{OH})_2$ in the Coolside samples. The only crystalline sulfate tentatively identified was gypsum $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$. In addition to portlandite, the sample contained mullite, quartz, hematite, pyrite(?), and ankerite(?). X-ray amorphous Al-Si-Fe oxides and oxyhydroxides commonly observed in fly-ash are likely also present.

A simple experiment was performed to assess the reactivity of the Coolside material. A sample consisting of 65% Coolside waste was mixed with 35% H_2O and aged for two days at room temperature. The sample was dried in an oven at 65°C overnight and pulverized for X-ray diffraction analysis. Preliminary results indicate considerable change in the crystalline components even after a reaction time of two days.

Microwave digestion and metal analysis will be performed on the Coolside Subsample II. The results will be compared to Coolside Subsample I with little or no variation in analytical results expected.

Four leaching characteristic studies will be performed on the Coolside Subsamples I and II. Two of the extraction procedures will follow ASTM guidelines. ASTM-A leachate procedure dictates a distilled water extraction while ASTM-B utilizes a buffered acetic acid/sodium acetate medium. The third and fourth extractions will follow EPA guidelines for potential toxic leaching characteristics of solid waste. EP toxicity is a procedure that prescribes a solid : liquid ratio of 1 : 16 with dilute acetic acid added to maintain a pH of 4.8 to 5.2. The TCLP (Toxic Characteristic Leachate Procedure) is the current test used by the EPA to determine toxicity of solid waste. The major differences between the TCLP and EP toxicity are the liquid/solid separation, extraction vessels, agitation, extraction time, extraction fluid, and quality control (QC) requirements. All the leachate results will be compared to the TCLP procedure because it is the current guideline of potential toxic leachate for solid waste. The field and column leachate results during and after the current Coolside project will be compared to the TCLP results. (The TCLP results will not be completed by the end of December owing to delay in purchasing the required materials.)

Figure 1. Unconfined compressive strength versus time, samples 1 and 3.

Figure 2. Coefficient of permeability versus time, samples 1 and 3.

Figure 3. Unconfined compressive strength after permeability test, samples 1 and 3.

Four bulk samples of Coolside solid waste were delivered in November. Preliminary index testing has begun on these samples.

Task 3. Field Lysimeter Tests

Road improvements to the field lysimeter station have been completed. The road improvements were necessary in order to transport equipment and the Coolside materials to the remote field station. The lysimeter pit has been emptied, but recent heavy rains may require further pumping to remove excess water. The lysimeters will be cleaned by Walker Construction Co. as soon as they have free equipment and the field station is accessible. The lysimeters will be filled as soon as practical after they are emptied and cleaned.

Task 4. Laboratory Lysimeter Tests.

The laboratory which will house the columns has been prepared. Between 12 and 20 columns will be constructed to adequately test the objectives established for column testing. Samples of various liner materials and soils (particularly Ohio soils) are being collected for column construction. Various column designs and constituent materials are being evaluated. Construction of the laboratory columns should begin in January.

Plans for the Next Month.

The field lysimeters will be emptied and two cells filled with Coolside solid waste if the weather permits. Filling of the lysimeters may be delayed if inclement winter sets in before the lysimeters are emptied. One lysimeter will be filled with compacted material and the other will be filled with uncompacted material.

A set of samples will be analyzed by PIXE/PIGE analysis using NBS 1633a standards to examine and refine the accuracy of the thick-target measurements. The selective Cr filter for reducing the Fe signal and the filter for measuring Si, P, and S will be tested.

Mineralogic and chemical changes produced during aging of the Coolside materials will continue to be investigated.

PIXE/PIGE measurements of the Coolside material will be compared with ICP analysis.

Unconfined and permeability tests will continue on the samples 1 and 3 remolded near ninety five percent of standard maximum dry density.

Index property testing will continue and compaction tests will be performed on the four bulk samples delivered. After completion of the compaction tests specimens will be remolded for curing and testing.

COOLSIDE WASTE MANAGEMENT RESEARCH

Technical Progress Report

Contract No: DE-AC21-91-MC8162

Report Period: December 1, 1991 to December 31, 1991

Statement of Project Objectives

Produce sufficient information on the physical and chemical nature of Coolside waste to design and construct physically stable and environmentally safe landfills.

Summary of Progress for Period

Technical progress for December centered on developing the analytical methods that will be employed for chemical determination of the Coolside waste materials and leachates collected from the Coolside wastes. Quality control and other protocols for chemical analysis have been established from the relevant EPA methods.

The ultrasonic nebulizer has enhanced the detection power of ICP analysis. The ultrasonic unit minimizes the loss of analyte and increases the emission intensity for trace metal analysis. Detection limits are substantially lowered by use of this nebulizer.

Comparison between preparation methods for solid Coolside waste indicates that no single method best for all elements of interest. The recovery of elements from a standard fly ash sample (1633 A) varied widely between the various methods. Microwave digestion showed the most uniform recovery of elements from the fly ash, ranging from 89% to 110%. X-ray fluorescence also displayed good results for many elements, including those which were inconsistent for microwave digestion. A combination of the two methods might be considered.

Permeability and unconfined compressive strength tests were performed on Coolside solid waste samples 1 and 3. The specimens tested for compressive strength were cured for 55 days at room temperature. The strengths were 652.6 and 852.7 psi, respectively. Sample 1 has increased from 17.9 psi at 1 day curing time to 652.6 psi at 55 days. Sample 3 has increased from 44.2 to 852.7 psi. The coefficient of permeability for sample 1 was 8.61×10^{-6} cm/sec after 53 curing days. Sample 3 had a coefficient of permeability value of 6.70×10^{-6} cm/sec after curing for 67 days.

Preparations are underway to fill the field lysimeters and the laboratory lysimeters. Configurations for the field lysimeters were discussed at the Quarterly Coolside Advisory Board Meeting on January 7, 1992. The preliminary intent is to fill three of the lysimeters with Coolside waste at different degrees of compaction and with different soil fills. The fourth lysimeter would be filled with Ohio fly ash.

A preliminary list of laboratory lysimeters has been prepared. Three areas of investigation will be emphasized: 1) comparison and contrast between laboratory lysimeters and field lysimeters, 2) interaction between liner materials and leachate, and 3) leaching characteristics of other Coolside materials supplied by Consolidation Coal Company.

Technical Progress

Introduction

Preparations are nearing completion to begin the field lysimeter and laboratory lysimeter studies. Approval has not yet been received to place the Coolside wastes in the lysimeter. Winter will likely delay emplacement of the waste until the weather moderates. Geotechnical testing indicates the Coolside material continues to increase in compressive strength with continued aging. However, these measurements were made on Coolside material that has been in contact with the original added water for the duration of the aging tests. Laboratory lysimeter tests with percolating water should help define the leaching characteristics of the Coolside waste with continual water flow.

Task 2. Materials Characterization

Subtask 2.1 - Sample Collection

Soils and clay liners will be collected from Ohio waste disposal operations. If possible, different soils from different portions of the state will be used. All the Coolside samples in storage from series 1 and series 3 will be combined into one sample to fill the lysimeters and for use in the laboratory columns.

The Coolside materials in storage are comprised of three sampling series of which two (No. 1 and No. 3) are considered representative of the Coolside process. The two combined samples are bimodal with respect to sulfur distribution. The majority of the samples (259 barrels) are normally distributed around 1.90% sulfur with a standard deviation of 0.22% (Figure 1). The remaining samples (23 barrels) contain approximately 2.65% sulfur. The field lysimeters will be filled with material from both distributions. A few barrels of Coolside material will be retained at CAER for reference, further testing, and to fill laboratory lysimeters in the second phase of lysimeter testing.

Subtask 2.2 Chemical and Mineralogic Analysis of the Materials

The following report contains the analytical methods and protocol that will be a routine operation during analysis of the Coolside leachate samples. All methods were obtained from EPA analytical procedures. The guidelines will be strictly followed in the analysis of metals, anions, and cations. The EPA methods of analysis contain many quality control procedures that will always be on record for anyone to view at any time during the course of the project. The following report contains two quality control data sheets that will be logged and on file routinely.

Analysis of the metals will be performed by ICP-DCP. Trace metal analysis will be performed using the CETAC U-5000 Ultrasonic Nebulizer in conjunction with the ICP. A brief description of the nebulizer and its accuracy is contained in the report.

Figure 1- Distribution of sulfur in Coolside Samples 1 and 3.

Various digestions have been performed on a coal fly ash quality control sample (1633 A). The results of the digestions are contained in the report. The purpose of the digestions was to establish the best method to be used on the Coolside solid waste.

Analytical Protocol Of Metals: CAER Coolside Waste Leachate Project

1) Method and Application

Procedures and applications described by EPA Method 1620 will be the source followed by the CAER analytical staff. Method 1620 was developed by the Industrial Technology Division (ITD) within the United States Environmental Protection Agency (USEPA) Office of Water Regulations and Standards (WORS) to provide improved precision and accuracy of analysis of pollutants in aqueous and solid matrices.

The following will be the routine method of analysis.

- a) Calibration of instrument
- b) Initial Calibration Verification (ICV)
- c) Continuing Calibration Verification (CCV)
(midpoints of their respective calibration curves)
- d) Interference Check Sample A (ICS A)
(interferents- Ca,Al,Mg 500 PPM- Fe 200 PPM)
- e) Interference Check Sample AB (ICS AB)
(analytes mixed with the interferents)
control limit + 20%
- f) Reagent Blank (RB)
(must follow steps as samples)
- g) Quality Control (QC)
(Spex QC-19, QC-7 Quality Control Standards)

2) Sample Preparation

Dissolved metals will be analyzed on the Coolside Leachate samples. Dissolved elements (those which will pass through a .45micron membrane filter) are determined in samples that have been filtered and acidified to <2 PH.

3) Metals To Be Determined

ICP-Ultrasonic Nebulizer

(Ag,Ba,B,Cd,Cr,Cu,K,Mn,Mo,Ni,P,Pb,Ti,V,Zn,)

DCP (Al,Ca,Fe,Mg,Na.)

FIAS AA Hydride (As,Se,Hg)

EPA-TCLP,EPTOX Metals (As,Se,Hg,Ba,Cd,Cr,Pb)

Parameters	Containers	Coolside Parameters			Volume
		Preservative	Holding time		
1 Sulfate	P,G	COOL, 4C	28 DAYS		250ml
2 Chloride	P	COOL, 4C	28 DAYS		100ml
3 Fluoride	P	NR	28 DAYS		100ml
4 Nitrate	P,G	COOL, 4C	48 HRS		100ml
5 Ammonium	P,G	COOL, 4C	28 DAYS		100ml
6 Alkalinity	P,G	COOL, 4C	14 DAYS		100ml

(P) Polyethylene (G) Glass (NR) None Required
(Obtained from EPA 40 CFR 136 & SW-846)

Field Analysis

Fisher Scientific Accumet 02 portable laboratory will generate PH data. Other field data to be acquired include precipitation (volume), Coolside leachate (volume), moisture content of material by Troxler neutron probe.

Analytical Protocol

All the parameters above will follow the EPA guidelines specified by the EPA methods manual Methods of Chemical Analysis of Water and Waste Water. The cations and anions will follow the 300 series guidelines while others will follow the 100 series of analytical protocol.

CETAC U-5000 Ultrasonic Nebulizer

Trace metal analysis of the Coolside material will be determined by using the Spectrametrics III ICP spectrometer in conjunction with the CETAC U-5000 Ultrasonic Nebulizer (Figure 2). The purpose of the Ultrasonic Nebulizer is to enhance the detecting power (lower the detection limits) and is 5 to 25 times better than the normal pneumatic nebulizer. A dry aerosol is introduced into the torch eliminating clogging (a routine problem associated with pneumatic nebulizers). An aqueous sample is introduced onto a piezoelectric transducer plate at a frequency of 1.4Mhz. The transducer oscillates and the resulting vibration breaks the liquid film into a heavy aerosol. The aerosol is carried by the argon gas first through a temperature controlled heating tube and then into a temperature controlled condenser. The dry aerosol is carried to the torch of the ICP with minimum loss of analyte. Approximately 70% to 80% of the solution is atomized which simultaneously increases the emission intensity and lowers detection limits and standard concentrations.

Normal Operating Conditions - CETAC Technologies Ultrasonic Nebulizer

Model	U-5000
Transducer Type	Air-cooled
Frequency	1.4 Mhz
Current	6A
Heating Temp.	140°C
Cooling Temp.	0°C

Figure 2.- The Ultrasonic Nebulizer - CETAC U-5000

Figure 2 Air-cooled Transducer and Aerosol Chamber.

QC Data ICP-Ultrasonic Nebulizer: EPA QC-8 EPA QC-20

Element	Average	Actual	Observed/Actual
Ag	0.0060	0.0055	109 %
Be	0.0600	0.0591	102 %
Cd	0.0290	0.0290	100 %
Co	0.0360	0.0382	95 %
Cr	0.0930	0.0892	104 %
Cu	0.0105	0.0100	105 %
Mn	0.0900	0.0860	105 %
Mo	0.0254	0.0264	96 %
Ni	0.0179	0.0171	105 %
Pb	0.0960	0.0914	105 %
Ti	0.2750	0.2780	99 %
V	0.0371	0.0360	103 %
Zn	0.1330	0.1270	105 %

Quality Control Data for DCP - 1633A Digestion Method Results
Results in % of Known Concentration

Element	Hot Plate	LTB Fusion	Microwave	XRF
Al	77	76	94	105
Ca	73	90	97	84
Fe	99	129	93	103
K	94	107	89	88
Mg	89	141	91	98
Mn	97	170	97	NA
Na	124	176	100	NA
Si	*	67	110	100
Ti	85	88	99	110

(NA) - Analysis not performed.

* - Si volatilized as SiF₄.

Subtask 2.3 Index Testing and Structural Properties Testing

Permeability and unconfined compressive strength tests were performed on Coolside solid waste samples 1 and 3. The specimens tested for compressive strength were cured for 55 days at room temperature. The strengths were 652.6 and 852.7 psi, respectively. Sample 1 has increased from 17.9 psi at 1 day curing time to 652.6 psi at 55 days. Sample 3 has increased from 44.2 to 852.7 psi (Figure 3). The coefficient of permeability for sample 1 was 8.61×10^{-6} cm/sec after 53 curing days. Sample 3 had a coefficient of permeability value of 6.70×10^{-6} cm/sec after curing for 67 days (Figure 4).

Unconfined compressive strength tests were performed on the specimens upon completion of permeability tests. Strength is remaining high even though the samples were saturated for permeability testing. Results of unconfined compressive strength after permeability testing are shown in Figure 5.

Unconfined Compressive Strength 55 days

Sample ID	Unconfined Compressive Strength (lbs.\in. ²)	Dry Density (lbs.\ft ³)	Moisture Content (%)
Sample 1	652.60	66.2	35.89
Sample 3	852.70	67.2	34.86

Permeability

Sample ID	Coefficient of Perm. (cm/sec)	Dry Density (lbs.\ft ³)	Moisture Content (%)	Moisture Content after Test (%)
Sample 1 53 Days	8.61×10^{-6}	67.49	34.47	57.48
Sample 3 67 Days	6.70×10^{-6}	67.08	35.62	55.16

Unconfined Compressive Strength After Permeability

Sample ID	Unconfined Compressive Strength (lbs.\in. ²)	Dry Density (lbs.\ft ³)	Moisture Content (%)
Sample 1 53 days	617.01	67.5	57.48
Sample 3 67 days	794.99	67.1	55.16

Figure 3. Unconfined compressive strength, samples 1 and 3.

Figure 4. Coefficient of permeability versus time, samples 1 and 3.

UNCONFINED COMPRESSIVE STRENGTH AFTER PERMEABILITY TEST

Figure 5. Unconfined compressive strength after permeability test, samples 1 and 3.

Task 3. Field Lysimeter Tests

Approval has not yet been received to place the Coolside material in the field lysimeters. Filling of the lysimeters will likely be delayed until March owing to anticipated inclement weather and difficulty of access to the remote site during the winter. All of the lysimeters in the group of four will be emptied and available for filling.

Three of the lysimeters can be filled with the present quantity of Coolside waste if a soil cap and quartz sand base are included in each design. The fourth lysimeter may be filled with fly ash collected from an Ohio power plant which is a candidate for Coolside technology retrofit. The fly ash would provide an basis for comparison with conventional power plant waste. The preliminary configurations of the three lysimeters receiving Coolside waste include: 1) Coolside waste compacted to 95% of optimum density; 2) loose Coolside waste which is not mechanically compacted; 3) Coolside waste compacted to 95% of optimum density which contains an Ohio soil liner at the base. A fourth lysimeter containing fly ash collected from an Ohio power plant burning Ohio coal will be used as the control if sufficient material can be obtained.

Index property testing was completed for samples 388, 397, 1040, and 1050. All four samples classified as A-4 and CL by the AASHTO and Unified Classification systems, respectively. Standard moisture-density relations tests were performed on samples 388 and 1040. Grain size distribution and moisture-density curves are located in Appendix A.

Task 4. Laboratory Lysimeter Tests.

A preliminary list of lysimeter configurations during the first phase of laboratory lysimeter testing is presented in Table &. These configurations will allow comparison between the field lysimeters and the laboratory columns, test the response of clay liners to Coolside waste leachate, and permit comparison of several types of Coolside waste.

Plans for the Next Month.

Unconfined and permeability tests will continue on the samples 1 and 3 remolded near ninety five percent of standard maximum dry density. Standard, modified, and low-energy moisture-density tests will continue on the four bulk samples. Bearing ratio and triaxial shear testing will begin. Samples will be remolded and allowed to cure for future testing.

The digestion and analysis of the Coolside solid material will be performed. Analytical methods include ICP-DCP and X-ray fluorescence. A quality control sample (1633A) will be digested and analyzed along with the solid material. The rotary extractors have been ordered and TCLP extraction and analysis will begin thus completing the regulatory and Standard Methods leachate experiments.

Preliminary leaching tests of the Coolside materials will begin in January with and study of major and trace elements release from Coolside/water mixtures. The element release patterns with and without replacement of the initial water will provide information concerning the factors controlling dissolution of Coolside materials. This information will help in design of the laboratory and field lysimeters.

Appendix A

1050

1040

397

388

12-18-91

COOLSIDE 1040 STANDARD

OPTIMUM MOISTURE CONTENT (%) = 35.8

OPTIMUM DRY DENSITY = 71.1 PCF

12-17-91

COOLSIDE 388 STANDARD

OPTIMUM MOISTURE CONTENT (%) = 39.4

OPTIMUM DRY DENSITY = 70.8 PCF

Q.C. Report # _____

Quality Control Data

Date
Sample Collected _____

Date
Sample Analyzed _____

Sample ID _____

Element	Control Limit	True Value	Actual Value	%R
Al				
Ba				
B				
Ca				
Cd				
Cr				
Cu				
Fe				
K				
Mg				
Mn				
Mo				
Na				
Ni				
P				
Pb				
Ti				
V				
Zn				
As				
Se				
Hg				

Q.C. Report # _____

Spike Sample Recovery

Date
Sample Collected _____

Date
Sample Analyzed _____

Sample ID _____

Element	Control Limit	Spiked Sample	Sample Result	Spike Added	%R
Al					
Ba					
B					
Ca					
Cd					
Cr					
Cu					
Fe					
K					
Mg					
Mn					
Mo					
Na					
Ni					
P					
Pb					
Ti					
V					
Zn					
As					
Se					
Hg					

END

DATE
FILMED
318193