**Recovery Efficiency Test Project
Phase I - Activity Report
Volume I: Site Selection, Drill Plan Preparation,
Drilling, Logging, and Coring Operations**

Topical Report

**W.K. Overbey, Jr.
R.S. Carden
J.N. Kirr**

April 1987

Work Performed Under Contract No.: DE-AC21-85MC22002

For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
Morgantown, West Virginia

By
The BDM Corporation
Morgantown, West Virginia

MASTER

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615)576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

**Recovery Efficiency Test Project
Phase I - Activity Report
Volume I: Site Selection, Drill Plan Preparation,
Drilling, Logging, and Coring Operations**

Topical Report

**W.K. Overbey, Jr.
R.S. Carden
J.N. Kirr**

Work Performed Under Contract No.: DE-AC21-85MC22002

**For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
P.O. Box 880
Morgantown, West Virginia 26507-0880**

**By
The BDM Corporation
1199 Van Voorhis Road
Morgantown, West Virginia 26505**

April 1987

RECOVERY EFFICIENCY TEST PROJECT
PHASE I - ACTIVITY REPORT

TABLE OF CONTENTS

	<u>PAGE</u>
1.0 EXECUTIVE SUMMARY	1-1
1.1 Site Selection	1-3
1.2 Reservoir Evaluation and Modeling	1-7
1.3 Drilling Plan	1-9
1.4 Drilling, Logging, and Coring Operations	1-11
1.5 Discussion	1-19
1.6 Results	1-23
1.7 Recommendations for Future Studies	1-23
2.0 INTRODUCTION	2-1
2.1 Project Objective	2-1
2.2 Objective of Site Selection Activities	2-1
2.3 Objective of Drilling Operations Activities	2-1
2.4 Objective of Well Testing Operations	2-2
3.0 SITE SELECTION ACTIVITIES	3-1
3.1 Site Selection Rationale/Criteria	3-1
3.2 Data Collection, Screening, and Analysis	3-2
3.3 Prioritization of Geographic Sites	3-2
3.4 Specific Site Selection Criteria	3-5
4.0 DRILL PLAN DEVELOPMENT ACTIVITIES	4-1
4.1 Review of Literature	4-1
4.2 Review of Key Topics Researched	4-2
4.3 Rationale for Technical Approach	4-5
4.4 Review of Optional Scenarios	4-6
4.5 Directional Well Drilling Plan	4-9
5.0 SITE DEVELOPMENT PLAN	5-1
5.1 Wellsite Layout	5-1
5.2 Waste Management	5-1
5.3 Site Reclamation Plan	5-1

TABLE OF CONTENTS (continued)

	<u>PAGE</u>
6.0 DRILLING OPERATIONS	6-1
6.1 Selection of the Operations Team	6-1
6.2 Vertical Hole Drilling Operations	6-4
6.3 Angle Building Drilling Operations	6-7
6.4 Horizontal Drilling Operations	6-24
6.5 Casing	6-50
6.6 Road and Site Work	6-51
7.0 DISCUSSION	7-1
8.0 CONCLUSIONS	8-1
9.0 REFERENCES	9-1
10.0 APPENDICES	10-1

RECOVERY EFFICIENCY TEST PROJECT
PHASE I - ACTIVITY REPORT

LIST OF FIGURES

<u>FIGURE</u>	<u>TITLE</u>	<u>PAGE</u>
1.1.1	Partitioned Areas Accepted for Analysis	1-4
1.1.2	Location of Selected Partition Area for Detailed Site Selection Studies	1-6
1.1.3	Location of Site Selected Relative to Fracture and Production Trends	1-8
1.4.1	Drilling Schedule for Devonian Shale Horizontal Well	1-12
1.4.2	Wellbore Diagram	1-13
1.4.3	Vertical View of Sidetracks	1-15
1.4.4	Vertical (Elevation) View of RET #1 Well	1-17
1.4.5	Plan View of Horizontal Displacement of RET #1	1-18
1.5.1	Rose Diagram of Oriented Core Fractures from RET #1	1-21
1.5.2	Schematic Diagram of RET #1 Well Showing Fractures Indicated by Gas Shows while Drilling	1-22
3.2.1	Flow Diagram for Geographic Area and Specific Site Selection Process	3-3
3.3.1	Partitioned Areas Accepted for Analysis	3-4
3.3.2	Location of Selected Partition Area for Detailed Site Selection Studies	3-8
3.4.1	Structure Contoured on Pre-Cambrian Rocks	3-9
3.4.2	Relationship of Basement Faulting to Structure on the Base of Huron Shale	3-10
3.4.3	Berea Structure with Interrupted Faults and Fracture Zone	3-11
3.4.4	Correlation of Geologic Structure and Production	3-13
3.4.5	Proposed Locations in Lincoln County, WV	3-14

LIST OF FIGURES (continued)

<u>FIGURE</u>	<u>TITLE</u>	<u>PAGE</u>
3.4.6	Structure with Interpreted Faults and Fracture Zones	3-15
3.4.7	Relationship of Berea Structure to High Cumulative Production Areas and Proposed Well Locations	3-16
3.4.8	Iso-Cumulative Production Contours of Wilsondale Pool, Wayne County, WV Location	3-17
3.4.9	Relationship of Current Reservoir Pressure to Location of Proposed Directional Well	3-18
3.4.10	Location of Site Relative to Fracture and Production Trends	3-20
4.5.1	Conceptual Design of Horizontal Well	4-10
4.5.2	Scenario #5 Wellbore Schematic Diagram	4-11
4.5.3	Vertical View of Scenario #5	4-20
5.0.1	Proposed Location and Roads	5-2
5.1.1	Wellsite Layout	5-3
5.3.1	Wellsite Reclamation Plan	5-4
6.0.1	Drilling Operations Schedule	6-2
6.0.2	Wellbore Diagram Showing Final Status of RET #1 Well	6-3
6.3.1	Photo of 10-5/8" Wellbore from Video Log of Hole	6-10
6.3.2	Photo of 7-7/8" Wellbore Where Dust is Seen in the Hole	6-21
6.3.3	Photo of 7-7/8" Hole Drilled on Air. Note Cleanness.	6-22
6.4.1	Vertical View of Planned versus Actual Drilling Operations	6-26
6.4.2	Plan View of Planned versus Actual Drilling Operations	6-27
6.4.3	Diagram of Fractures in Core Run #3	6-33
6.4.4	Rose Diagram of Core Fractures	6-34

LIST OF FIGURES (continued)

<u>FIGURE</u>	<u>TITLE</u>	<u>PAGE</u>
6.4.5	Schematic of Wellbore Showing Location of Fractures and Gas Shows	6-37
6.4.6	Plot of Calculated Gas Flow Rates versus Horizontal Hole Length	6-38
6.4.7	Schematic Diagram of Logging Tools and Wet Connect System Used to Log the Well	6-40
6.4.8	Schematic of Side Entry Sub System Used to Facilitate Logging of the Horizontal Hole	6-42
6.4.9	Induction, Density and Gamma Ray Logs of the Horizontal Borehole in the High Frequency Gas Show Zone	6-43
6.4.10	Temperature and Differential Temperature Curves for the High Frequency Gas Show Zone	6-44
6.4.11	Compensation, Density, Induction, and Gamma Ray Curves for Cored Section of the Borehole	6-45
6.4.12	Temperature and Differential Temperature Curves for the Cored Section of the Borehole	6-47
6.4.13	Observed Natural Fractures from Downhole Camera in the Horizontal Section of the Borehole	6-48
6.4.14	Natural Fracture Spacing from Downhole Camera in the Horizontal Section of the Borehole	6-49

RECOVERY EFFICIENCY TEST PROJECT
PHASE I - ACTIVITY REPORT

LIST OF TABLES

<u>NUMBER</u>	<u>TITLE</u>	<u>PAGE</u>
3.3.1	Row Data for Ranking of Partition Areas	3-6
3.3.2	Normalizing of Data for Ranking	3-7
3.4.1	Comparison of Geologic, Engineering, and Other Criteria and Final Ranking for the Sites Evaluated	3-19
4.4.1	Drilling Scenario Directional Programs	4-7
4.4.2	Comparison of Drilling Scenarios	4-8
4.5.1	Proposed Target Information Output	4-19
6.4.1	Calculated Coefficient of Friction for Drilling Operations	6-30
6.4.2	Core Fracture Data	6-32
6.4.3	Compilation of Mud Logger Gas Shows	6-36
6.4.4	Spacing Between Mud Logger Shows for ECP Zone 4	6-39

1.0 EXECUTIVE SUMMARY

The Recovery Efficiency Test well project addressed a number of technical issues. The primary objective was to determine the increased efficiency of gas recovery of a long horizontal wellbore over that of a vertical wellbore and, more specifically, what improvements can be expected from inducing multiple hydraulic fractures from such a wellbore. To accomplish the objective, the following tasks were performed:

- o Select a suitable area and drill site;
- o Evaluate the reservoir;
- o Formulate a drill plan;
- o Drill the well;
- o Test and analyze the reservoir;
- o Hydraulically fracture multiple intervals; and
- o Evaluate the recovery efficiency.

The BDM Corporation spent four months locating the optimum geologic area and the specific site to conduct the drilling phase of the Recovery Efficiency Test (RET). An additional four months was spent researching and planning the drilling program. Three months were spent in negotiating a lease (farmout) on which to drill the test well. Drilling operations were planned to take 45 days; however, a broken bit in the shallow hole and lost tools in the inclined section of the borehole extended drilling time to 58 days. The well encountered two gas shows in the inclined portion of the wellbore and thirty gas shows during the drilling of the horizontal section of the well. One 200-foot section from 5040 to 5240 feet had calculated gas shows totaling 5263 mcf. Gas shows calculated from chromatograph data from both the inclined and horizontal portions of the wellbore through the Devonian shale formation totaled 5846 mcf. The well was projected to have a shut-in pressure of 250 psig; however, a seven-day shut-in test recorded only 135 psig.

The well was open flow tested at a rate of 260 mcf for more than six hours after the seven-day shut-in, but the well blew down to a rate of 3 mcf through a 1/2-inch orifice plate at 0 psig. Plans are to conduct

individual zone (eight isolated zones) gas flow and pressure build-up and drawdown tests before beginning Phase II operations. In Phase II, four to eight multiple hydraulic fracture stimulations of the well will be conducted and the improved recovery efficiency of the stimulated versus natural producing well will be determined.

The U.S. Department of Interior, Bureau of Mines, Morgantown Energy Research Center, initiated studies of fractured oil and gas reservoirs in the Appalachian region in 1964. Results of these early studies pointed out that the earth's natural fracture system plays a major role in the flow of fluids from oil and gas reservoirs. A Bureau of Mines project titled "Earth Fracture Systems and Their Effect on Fossil Fuel Recovery Processes" was initiated in 1966. Some of the results and recommendations were published in an SPE paper, "Natural and Induced Fracture Systems and Their Application to Petroleum Production", presented to the SPE in Denver, Colorado, in May 1969. This paper, written by J. Pasini III and W.K. Overbey, Jr., pointed out that directional wells could be drilled to intercept natural fractures as a means of improving recovery efficiency, and that multiple hydraulic fractures could be induced from such horizontal or near-horizontal wells to further improve recovery efficiency.

In 1976, the Energy Research and Development Administration's (ERDA) Morgantown Energy Research Laboratory (successor to U.S. Bureau of Mines) initiated the Eastern Gas Shales Project. This project was designed to characterize the Devonian-age shales in the eastern United States, determine the total gas resource in place, and to investigate new techniques for improving recovery of the gas in place. The U.S. Department of Energy (successor to ERDA) has completed the tasks of resource characterization and presently pursues research directed to improving the efficiency of recovery of gas from the shales. The present project is a continuation of studies initiated in 1968. The first directional test well was drilled in September and October 1972 in Harvey District, Mingo County, West Virginia, in a cooperative project with Columbia Gas. The well was targeted to reach an inclination of 60 degrees, but obtained a deviation of only 42 degrees. The second test well was drilled in 1976 in cooperation with Consolidated Natural Gas (CNG) in Jackson County, West Virginia, and obtained an inclination of 52 degrees. The third

well was drilled in Meigs County, Ohio, in 1982. The target inclination was 60 degrees but a deviation of only 25 degrees was obtained.

1.1 Site Selection

Site selection began with a review of the geographic sites where directional drilling had the most potential for successful completion of the Recovery Efficiency Test in the Devonian shales of the Appalachian Basin.

Various structural and tectonic elements of fourteen (14) different geographic areas were examined in light of the site selection rationale and criteria developed for the project. These geographic areas (partitions) are shown in Figure 1.1.1 and are labeled one (1) through six (6) with a letter prefix designating the state.

Areas WV-5 and WV-6 are characterized primarily by horizontal tectonic control, although there may be some vertical tectonic effects in certain areas. The structures are all shallow, detached structures with evidence of fracturing. However, because the areas produce oil as well as gas from the Devonian shales, thus presenting the problems of two phase flow analyses, they were given a low priority.

Areas WV-4 and OH-3 are characterized more by vertical tectonic effects (basement faulting), but because of mixed oil and gas production from the shales in these areas, they also were given low priority for final site selection consideration.

Areas KY-1, 2, 3, and WV-1 and 2 were given the highest priority because they met most of the rationale elements and criteria requirements. They are located in areas characterized by vertical tectonism (basement faulting) which has produced extensive tensile fracturing. There are indications of minor horizontal tectonic activity in areas KY-1 and 3, or the results of episodic rejuvenation of basement faulting has produced surface or near-surface faulting which resembles thrust faulting (strike slip faulting in Martin County, Kentucky, interpreted by Lee, 1980, and in Mingo and Lincoln County, W.K. Overbey, 1985). An evaluation of original rock pressure for areas KY-1 and WV-1 indicates that the Martin County, Kentucky, section is likely to be more extensively fractured

Figure 1.1.1

than the Wayne-Lincoln County, West Virginia, area. Martin County, Kentucky, has an original pressure gradient of .195, while Wayne-Lincoln County, West Virginia, area has an original gas pressure gradient of .260. BDM's interpretation of this data is that a higher frequency of fractures is the cause of lower rock pressure in that area, since the thickness, depth and content of the shales is virtually the same.

The southeastern part of KY-2 area and adjacent areas of Virginia are characterized by horizontal tectonism and are situated on the northern end of the Pine Mountain thrust sheet. There are zones of extensive fracturing in the shales, but production developed to this point in time has been scattered and generally not as good as that further north in the tensile fractured area of geographic sites KY-1 and WV-1. For this reason, area KY-2 was given a lower priority.

The final ranking of the geographic areas (see Figure 1.1.2) is as follows:

<u>RANKING</u>	<u>GEOGRAPHIC AREA</u>
First	WV-1
Second	KY-3
Third	WV-4
Fourth	KY-2
Fifth	KY-1

The final ranking of the partitioned areas was accomplished by normalizing data published in DOE reports on West Virginia, Kentucky, and Ohio, compiled by Lewin and Associates. Normalizing the data for thickness and reservoir pressure gave a ranking based on fracture permeability or flow capacity, which can be more readily tested by the horizontal borehole and multiple hydraulic fracture approach.

The BDM Corporation recommended that final site selection studies be conducted in geographic partition WV-1, which includes Cabell, Wayne, and Lincoln Counties, West Virginia. This area is identified as the hatchured area in Figure 1.1.2 with the final ranking of partitioned areas.

BDM reviewed the published data available that would be useful in specific site selection studies and selected five specific sites for

FIGURE 1.1.2
LOCATION OF SELECTED PARTITION AREA
FOR DETAILED SITE SELECTION STUDIES

evaluation. Two sites are located in Harts Creek District of Lincoln County, and three sites are located in Lincoln District of Wayne County.

BDM recommended drilling the directional well at Site No. 3 in Wayne County. The well site is shown with the projected well path trajectory in Figure 1.1.3. Site No. 3 will intercept one, possibly two, high cumulative production trends postulated to exist in the area. The bearing of the well path trajectory is S37°E. This is nearly normal to the principal stress direction for the area, estimated to be N52°E based on correlation of structural and lineament trends.

1.2 Reservoir Evaluation and Modeling

BDM collected data on more than 40 wells drilled in the Wilsondale Devonian shale gas pool during the past 50 years. These wells now belong to Cabot Oil and Gas Corporation. The data included cumulative gas production by horizon, reservoir pressure (initial and current), initial open flow gas production rates and current production rates. The data was used to prepare initial and current reservoir pressure maps and initial and current production rate maps and cumulative production trend maps.

The data was utilized by the DOE reservoir modeling group to generate a reservoir model of the field using the SUGAR-MD model developed by METC. The model is a dual porosity model that accounts for desorption flow from the matrix into fractures followed by fracture flow. The model was constructed using production data provided by Cabot Oil and Gas Corporation. History matching the data provided helped establish permeability trends and flow rates into horizontal and vertical wells drilled in the sites proposed by BDM. Using this technique, interference of the planned well with currently producing wells could be predicted along with the relative improvement ratio between the proposed locations and drilling directions. The model was used by DOE to select Site No. 2 as the preferred direction for drilling the well based on improvement ratio. The model was also used to project 20-year cumulative production from a horizontal well drilled at Site No. 2 versus a vertical well drilled at Site No. 2.

1.3 Drilling Plan

BDM reviewed the state-of-the-art literature relative to directional drilling and investigated a number of scenarios which might be used and, based on such key elements as well as trajectory design, drag, hook load, rig size, risk factor, and cost, have determined the best well design to accomplish the requirements set forth in the Statement of Work for the Recovery Efficiency Test Project.

BDM initially proposed to drill a small diameter hole, ream it to the required size to set casing, and conduct the required production tests. Literature research and special topics research revealed that the state-of-the-art of directional drilling has decidedly improved in the past two years, specifically during the past six months. Strong consideration was given to large diameter holes due to recent successful operations (completed in October and December 1985).

BDM determined through discussions with drilling consultants, directional engineers and the results of cost and risk analysis that the probability of success is higher when a larger diameter hole is drilled. Computer modeling of wellbore shape based upon rate of build was performed. The analysis included long radius turns, medium radius turns, and catenary type curves along with several hole sizes. Results indicated that for 2000 feet of horizontal hole there was little difference between the scenarios (based upon the drill pipe stress level as a percentage of yield strength). Therefore, a build rate was selected that would minimize the amount of directional drilling and still be easily obtainable, especially in view of the previous angle building problems in the DOE-sponsored wells.

Each of the scenarios was evaluated for potential risks. The risk analysis compared potential problems, cost, and the proven use of the technology. By using larger diameter drill pipe and bits, the risk of twist-offs and other typical directional drilling problems is considerably reduced.

The low fracture gradients in the area required the use of an air-mist system as the circulating medium. The use of air-mist considerably reduces the directional drilling technology available.

BDM proposed to drill the required "Recovery Efficiency Test" directional well in the following manner:

1. On the selected and approved drill site, drill 630 feet of 17-1/2-inch hole;
2. Cement 630 feet of 16-inch conductor casing (fresh water protection string);
3. Drill 2000 feet of 14-3/4-inch hole to a point just below the Big Injun sand;
4. Set and cement to surface 2000 feet of 11-3/4-inch casing;
5. Kick well off at 2080 feet using a bent sub and downhole motor with a 10-5/8-inch drill bit and using an electromagnetic MWD unit for directional control;
6. Build angle at a constant rate of 4.25 degrees per 100 feet until an inclination of 85 degrees or more is reached in the top of the Lower Huron shale;
7. Run conventional wireline logs to maximum obtainable depth;
8. Set 4080 feet of 8-5/8-inch casing, cementing the lower 500 and upper 150 feet in place;
9. Drill out with a 7-7/8-inch bit for 100 feet, then rig up and take 90 feet of 3-1/2-inch oriented core;
10. Depending upon surveys while coring, run an angle building assembly with a conventional bit and the electromagnetic MWD unit, increase angle to 90 degrees and attempt to drill a total of 2000 feet horizontally (85 - 90 degrees) to 6080 feet measured depth;
11. Inspect the wellbore with a TV camera attached to the drill pipe or coiled tubing;
12. Log the horizontal section of the wellbore with a gamma, temperature, and dual induction tool conveyed by drill pipe;
13. Set 6080 feet of 4-1/2-inch casing and inflate external packers to isolate four zones for testing; ported collars will eliminate the need for perforating the intervals;
14. Open the ported collars and test the isolated zones separately.

BDM examined the costs and risks of a number of drilling methods. This proposal was submitted as the best possible scenario for accomplishing the items in the Statement of Work at the costs projected in the contract.

1.4 Drilling, Logging and Coring Operations

Drilling operations were conducted at the selected site between October 21 and December 18, 1986. The actual drilling time for 2000 feet of horizontal wellbore was 58 days, compared to the planned time of 45 days, a difference of 13 days. Figure 1.4.1 shows a plot of actual and planned depth versus days.

Most of the additional drilling time was consumed by HLH Drilling Company in drilling the vertical portion of the hole. HLH Drilling Company drilled this portion on footage. The estimated drilling time was three days and it actually took 15 days. The directional portion of the hole was expected to take 42 days, but required 43 days. The building portion of the well took longer than expected because of the two sidetracks; however, the horizontal section went faster than expected because no motor corrections were required.

The primary objective of the drilling plan was to drill and evaluate a 2000-foot horizontal wellbore. The objective was accomplished by drilling Recovery Efficiency Test Well No. 1. The well has more than 2000 feet of wellbore with an inclination of more than 85 degrees that can be tested and evaluated. Both the coring and logging programs were successful and will aid in the evaluation of the well. Logging was not completely successful because the density tool did not work properly. However, the fractures were identified with the TV camera and the temperature logs. Well testing is currently being conducted.

Figure 1.4.2 is a wellbore diagram showing the final status of the well along with casing sizes and setting points. The 16-inch casing is set deeper than planned because it was required by the West Virginia Department of Energy to isolate a coal zone and protect shallow aquifers. They also required the 11-3/4-inch casing to be cemented to the surface instead of the planned 1300 feet.

While drilling the surface hole at 161 feet, two bit shanks broke away from the 18-1/2-inch bit and could not be recovered. The contractor skidded the rig and began drilling a new well.

The 16-inch surface casing was set at 650 feet in a 17-1/2-inch hole and cemented to the surface. On the first attempt, the 16-

Figure 1.4.1 -- Drilling Schedule for Devonian Shale Horizontal Well

Figure 1.4.2 -- Configuration of Wellbore at Completion

inch casing would not go into the hole. The 17-1/2-inch hole was reamed, then the casing went to bottom.

A 14-3/4-inch hole was drilled to 2113 feet without incident. The 11-3/4-inch casing was run and set at 2025 feet. The casing was cemented back to the surface. Directional drilling operations began at 2113 feet in the 10-5/8-inch hole. The highest inclination was 92 degrees at a measured depth of 4043 feet. The entire angle building section was built using downhole motors as planned.

There were three major problems encountered in the 10-5/8-inch (angle building) hole. The first problem was a stuck drill string, resulting in a subsequent sidetrack operation. While reaming the hole out at 3509 feet, the drill string became stuck in the hole. The drill string was backed off leaving two monel collars, two steel collars, and two reamers in the hole (Figure 1.4.3). The fish (lost tools) were jarred for more than eight hours with no significant movement of tools when the jars failed to function. Jarring loads as much as 130,000 pounds over the string weight were observed.

The well was successfully sidetracked at 3239 feet and directionally drilled to 3666 feet. Because of problems getting the motor oriented during the sidetrack, the inclination was behind schedule and the target could not be hit.

The well was sidetracked a second time at 3362 feet and drilled to 3827 feet. At this point, hole cleaning became a significant problem. The drill string had to be pumped in and out of the well. To alleviate the hole cleaning problem, the 8-5/8-inch casing was run and cemented at 3803 feet. The inclination at this point was 74 degrees. The drilling plan called for setting the 8-5/8-inch casing at 85 degrees.

The remainder of the well drilling operation went very well. The angle was built from 74 to 92 degrees with a 7-7/8-inch bit at a depth of 4043 feet. At this point coring operations were initiated. A total of 75 feet of core was obtained at an inclination of 92 degrees. The core showed natural fractures and faulting in the interval. Core recovery was 50 percent on one run and 100 percent on two runs.

The remainder of the horizontal section was drilled with a rotary assembly using air as the circulating medium, as planned. The assembly dropped inclination from 92 degrees to approximately 87 degrees

— Vertical View of Sidetracks —

Figure 1.4.3

at a total measured depth of 6020 feet. The wellbore stayed within the target interval in the Lower Huron shale. The bottom of the Lower Huron shale was at a vertical depth of 3450 feet. The maximum total vertical depth (TVD) reached by the wellbore was 3427 feet. Figures 1.4.4 and 1.4.5 show the planned versus actual wellbore paths.

A 4-1/2-inch production casing string was run incorporating external casing packers to isolate individual zones for testing. At the present time, an initial flow test over the entire horizontal wellbore is being conducted.

The 7-7/8-inch hole was logged with an open hole logging suite and a TV camera. A Dresser Atlas drill pipe conveyed logging system was used for both logs.

The first logging run was made with Density, Gamma Ray, Caliper and Dual Induction resistivity tools. The Density and Caliper tools did not function properly because the pad was on the low side of the hole and could not be deployed to contact the sidewall properly. After logging from 6020 feet to 4137 feet, the wet connect pulled loose from the logging tools. Dresser personnel speculated there was some rust scale from the pipe in the wet connect, causing it not to seat properly. The wet connect was re-established and the logging run completed.

The second logging run consisted of Temperature and Gamma Ray logs. The temperature was logged down while tripping in the hole. The correlation Gamma Ray tool failed, so the 8-5/8-inch casing seat was used for depth correlation.

The TV camera was attached to the drill string using a special housing and the wellbore observed (logged) going into the hole. This tool proved to be very useful in identifying the fractures in the wellbore. This is the first time a TV camera has been run using a drill pipe conveyed logging method, and it was very successful. The TV camera was invaluable in providing fracture identification and hole condition information. The most notable information observed was the production of liquid condensate from several of the wellbore fractures.

Vertical View

Figure 1.4.4 -- Elevation (Vertical) View of RET #1 Well

Plan View

Figure 1.4.5 -- Plan View of Horizontal Displacement of RET #1 Well

1.5 Discussion

The strategy selected by BDM, which was to use downhole motors to build the entire inclined portion of the well, was a complete success. The major problem overcome during this part of the drilling operation was hole cleaning. Another problem was motor starting, which was later addressed by picking up a double stand (62 feet) with each connection. BDM tried (unsuccessfully) to determine the potential detrimental effects of various chemicals used in the mist fluid. Evaluation of BDM data by Drilling Resources Development Corporation indicates that a higher fluid injection rate of 15 to 20 barrels per hour should have been more successful in hole cleaning than the 10 to 12 barrel per hour rate used by BDM. This probably would have been more successful in wetting the cuttings and preventing agglomeration of the cuttings to form mud balls which could not be removed from the wellbore.

Testing of the ElectroMagnetic Measurement While Drilling system (EM-MWD) to provide tool face orientation, wellbore inclination and trajectory azimuth, was disappointing. The tool worked reasonably well but needs additional hardening and software configuration to obtain required data in a timely fashion. Future development of horizontal drilling as an efficient and economic method of producing petroleum and natural gas depends largely upon reducing the time required to make these measurements.

The use of 3100 cfm of air for the circulating medium with the rotating bottomhole assembly (BHA) was very effective in removing cuttings during drilling of the horizontal section of the hole. The use of an on-site computer to examine the drilling tendencies of several BHAs allowed BDM engineers to select the best assembly for the operation. The assembly selected worked so well that a motor run to correct for dropping angle or walking was not required.

There were no major difficulties encountered during coring operations. The modified core barrel worked very well, recovering 100 percent of the core cut on two of the three runs made. Examination of the core material revealed the presence of 15 natural fractures, six faults, and 59 coring-induced fractures. The natural fractures had a

mean orientation of N37°E, 87°NW, while the faults (normal) had a mean orientation of N22°E, 56°NW. Mean spacing between fractures was eight feet. Mean orientation of the coring-induced fractures was N52°E (Figure 1.5.1). This orientation is interpreted to be the direction of induced hydraulic fracturing and confirms the N53°E orientation postulated by this author. The S37°E planned trajectory is only one degree off from being exactly normal to the direction of induced fracturing. Surface joint studies, aerial photography, landsat imagery and core fracture data from wells nearby in Lincoln County, West Virginia, and Martin County, Kentucky, were studied to determine the wellbore orientation which would be optimum for hydraulic fracturing operations.

The 15 degree difference in orientation of the well developed natural fractures found in the oriented core with the interpreted principal horizontal stress orientation, should be ideal for the planned attempt to incorporate natural fractures in the hydraulic fracture stimulation operation. The author has postulated that in areas where tensile fracturing is dominant, natural fractures oriented within 22 degrees of the principal stress orientation can be inflated under the right circumstances and used to augment the fracturing process.

Chromatographic analysis of the air stream monitored while drilling the horizontal hole indicated 30 fractures were encountered which produced measurable volumes of natural gas (Figure 1.5.2). The largest of these had a calculated open flow of 2168 mcf/d. Examination of the borehole with a video camera revealed circular and elliptical features which were interpreted to be fractures, since many of them were bleeding gas and condensate into the wellbore. The presence of condensate indicates that two-phase flow conditions may exist at different periods of time in the life of a well or field. Some Devonian shale producers have suspected this was the case, but lacked proof to explain oddities in production.

The well was cased with 4-1/2-inch J-55, 10.5 pounds per foot casing equipped with eight external casing packers, one cement packer, and 14 full opening ported cementing collars. Presently the external casing packers have not been inflated to produce eight isolated zones for testing, but will be inflated when the initial open flow testing

Rose Diagram of Core Fractures

Figure 1.5.1 -- Rose Diagram of Oriented Core Fractures

Recovery Efficiency Test

Figure 1.5.2

Schematic Diagram of RET #1 Well Showing
Fractures Indicated by Gas Shows While Drilling

has been completed. The well is currently producing 1299 bbl gas at rates varying between 24 and 45 mcf/d depending upon orifice size and choke settings being tested. The well had a seven-day shut-in pressure measurement of 135 psig. This is about one-half of the pressure predicted by mapping of seven-day fieldwide shut-in pressure measurements. The low pressures encountered could be related to the presence of fluid (condensate) in the fractures, thus pressure will increase with time as the fluid is removed, or a low pressure fracture system could be storing gas during the entire well production test phase. Zone isolation testing will help to resolve some of these questions.

1.6 Results

In conducting the Recovery Efficiency Test Project, BDM successfully located, planned, and drilled a long radius turn horizontal well in the Devonian shale Lower Huron section in Wayne County, West Virginia; successfully tested drilling, coring, and logging in a horizontal well using air as the circulating medium (possibly the world's first); conducted reservoir modeling studies to project flow rates and reserves in advance of drilling operations; observed two-phase flow conditions not observed previously in the wellbore; cored a fracture zone which produced gas; observed that fractures in the core and the wellbore were not systematically spaced (varied from 5 to 68 feet in different parts of the wellbore); and observed that highest gas show rates reported by the mud logger corresponded to zone with lowest fracture spacing (5 feet) or high fracture frequency.

1.7 Recommendations for Future Studies

Future R & D efforts should be directed toward first conducting a similar confirmatory project to determine if all aspects can be duplicated in another area, then testing medium radius turn technology (400 to 600-foot radius) in the same area where two long radius turn wells were tested. Since reservoir modeling has been completed, regional and site geologic and reservoir engineering studies would be minimal.

Directional control technology should continue to be developed and tested, especially the electromagnetic MWD system, which can be used in air drilling. Horizontal well stimulation technology will need additional development and testing.

Additional studies and tests on more efficient operation of downhole motors should be conducted. Fluids and chemicals, along with mixing and injection rates, should be more closely monitored to prevent rubber swelling in the stator, which eventually stalls the motor and prevents restarting until the rubber has returned to near-normal conditions.

A more concerted effort should be made to obtain additional core (for example, 1000 feet of core in a 2000-foot horizontal hole) to examine fracture spacing more thoroughly. When large shows of gas are encountered in future wells, drilling should be halted temporarily to make flow measurements.

2.0 INTRODUCTION

The drilling of directional wells and even horizontal wells to augment oil and gas production goes back to at least 1944 in the Appalachian Basin, when a horizontal well was drilled from a 500-foot-deep shaft in the Franklin Heavy Oil Field in Venango County, Pennsylvania, to improve oil recovery. Several hundred feet of horizontal core was taken during the drilling operations in the Venango Sand.

Attempts were made to drill directional wells in the Devonian shales in 1972, 1976, and 1982 by the U.S. Department of Energy (Cottageville, Mingo County, and E.C. Newell 10056-D). Reports have been circulated that Columbia Gas and Consolidated Gas Supply Corporation each have drilled directional wells in the shale, with few details available.

2.1 Project Objective

The overall objective of this project was to test the increase in recovery efficiency of multiple hydraulic fractures induced in the gas-bearing Devonian shales from a wellbore deviated 60 to 90 degrees from vertical in a particular azimuthal direction selected to enhance the hydraulic fracturing process.

2.2 Objective of the Site Selection Activities

The objective of the site selection activities was to select the proper geographic area where geologic conditions are such that the well drilled to test the conceptual objective of the project would have the greatest chance of being successful.

2.3 Objective of the Drilling Operations Activities

The objective of the drilling operations activities was to drill a usable horizontal wellbore in order to test and hydraulically fracture individual zones in the Devonian shale.

2.4 Objective of the Well Testing Operations

Initial testing will be conducted to provide the information necessary to adequately test and subsequently hydraulically fracture the identified zones.

3.0 SITE SELECTION ACTIVITIES

The objective of this task was to select the proper geographic area and specific drill site that would provide the greatest chance for successfully attaining the project's objectives of drilling, coring, logging, testing and producing a horizontal wellbore in the Devonian age shales.

3.1 Development of Site Selection Rationale

The area and site selected must have sufficient thickness of gas-bearing Devonian age shales to sustain commercial gas production. The area and site must have a well-developed natural fracture system consisting of micro fractures, bedding plane fractures, joints and faults, all interconnected to form a permeable production path to the wellbore.

Results of numerous studies have pointed out that tensile fracture regimes are better conduits for hydrocarbon fluids than compressive or shear fracture systems. Based on previous studies by Leonard Harris of the U.S. Geological Survey, the pre-Cambrian rift system which developed the Rome Trough in eastern Kentucky and southwestern West Virginia would have generated the extensive fracture systems needed to promote gas production from the Devonian age shales.

Advani and Lee (1983) investigated the development of finite element models which calculated the stress ratios of sedimentary units across the Rome Trough complex. The model projected the lowest stress ratios over and near the basement faults, thus providing a target area and a target geo-tectonic condition to search for as part of an overall site selection rationale. The key features of the site selection rationale are as follows:

- o Sufficient thickness (more than 100 feet) of organic rich gas bearing shales;
- o Established gas production in the area;
- o Low stress ratio (.3 to .5) to ensure presence of fractures in the shale;

Sufficient remaining reservoir pressure to allow for measuring the beneficial results of drilling through fracture zones and to quantify the results of hydraulic fracturing operations;

- o Sufficient geologic and engineering data is available to determine and verify the orientation of the fracture system and the orientation of hydraulically induced fractures.

3.2 Data Collection, Screening and Analysis

A large volume of published data was reviewed to determine the usefulness of the data for site selection analysis. The data types and general technical approach are presented in the flow diagram in Figure 3.2.1.

Geologic and engineering data were collected for specific areas in the basin which were defined several years ago as areas of similar geologic conditions and gas production relative to the Devonian shales. These areas or partitions were further defined and published by Lewin and Associates, who compiled data generated by other investigators to obtain representative figures for thickness, gas content, rock pressure, production decline rates and cumulative production for each partitioned area.

3.3 Prioritization of Geographic Sites

The partitioned areas in each of the primary gas producing states in the Appalachian Basin were screened against the criteria listed below for analysis and ranking. The area accepted for analysis is shown in Figure 3.3.1.

Site Selection Criteria:

- o The area has wells currently producing from the Devonian shales;
- o Productive intervals are between the depths of 1500 and 4000 feet;
and
- o Production data is available for analysis.

Figure 3.2.1
 FLOW DIAGRAM FOR GEOGRAPHIC AREA
 AND SPECIFIC SITE SELECTION PROCESSES

Figure 3.3.1 -- Basin Areas Examined

The data collected and screened is shown in Table 3.3.1. The data was normalized as shown in Table 3.3.2 and the area given a final ranking. The ranking of the partitioned areas is shown in Figure 3.3.2. The selected geographic area is WV-1, which consists of Cabell, Wayne, and Lincoln Counties, West Virginia.

3.4 Specific Site Selection

The BDM Corporation systematically considered organic richness, thermal maturation, thickness, and production potential in selecting the best geographic area in which to conduct the studies. BDM then conducted more detailed examination of tectonic history, geologic structure, specific occurrence of natural gas production, and reservoir properties within the selected partition area.

The basement structure map shown in Figure 3.4.1, contoured on pre-Cambrian age rocks, indicates several faults are present in the selected partition area (WV-1) which comprises most of Wayne, Lincoln, and Cabell Counties. The faulting in the basement rocks produced effects in the thickness and structural configuration of the overlying rocks. Such a relationship is readily discernible on Figure 3.4.2 which shows the position of the basement faults in relationship to geologic structure on the base of Upper Devonian age Huron shales. Synclines and anticlines have been developed in close proximity to fault scarps. Episodic rejuvenation of these faults has produced fracture zones in overlying sediments such as the Devonian age shales.

Structure mapped on the Berea sandstone by Columbia Gas (for Gas Research Institute) was used as a base for re-interpretation considering the effects of the Rome Trough basement faulting on the shallower formations over geologic time. Figure 3.4.3 depicts the location of several logical faults which help to explain present Berea structure in Lincoln County, West Virginia.

The same procedure was used on a structure map prepared on the base of the Huron shale member of the Ohio shale formation. Correlation of high cumulative production areas (striped areas had more than 500 mmcf cumulative gas production) with interpreted faults and

TABLE 3.3.1

RAW DATA FOR RANKING

PARTITION AREA	GAS CONTENT mcf/AF	ROCK PRESSURE INITIAL, psi	NET THICKNESS-ft	DEPTH ft
WV I	64	330	91	3487
II	50	450	226	3414
III	55	960	120	5736
IV	80	625	67	3723
V	50	340	160	4283
VI	60	450	100	4051
KY I	74	375	380	3038
II	81	590	114	3878
III	108	520	123	3350
IV	79	550	120	3000
OH I	100	690	119	2320
II	96	240	60	1590
III	20	525	120	3560
IV	140	215	105	1660
V	200	90	10	365
VI	50	135	100	2135
AVERAGE VALUE	81	450	115	3123

TABLE 3.3.2
NORMALIZING OF DATA FOR RANKING

PARTITION AREA	10 YEAR CUMULATIVE PRODUCTION	RANK	**NORMALIZED BY THICKNESS		***NORMALIZED BY THICKNESS AND I.R.P.		NORMALIZED RANK	FINAL RANK
				THICKNESS		AND I.R.P.		
WV								
I	285	5	364		495		2	1
II	376	4	191		191		9	7
III	221	because	108	is too	92	deep	13	---
IV	277	6	475		342		4	3
V	155	because	111	is too	79	deep	14	---
VI	167	10	192		192		8	6
KY								
I	815	1	246		295		6	5
II	405	3	408		311		5	4
III	435	2	406		351		3	2
IV	243	8	232		189		10	8
OH								
I	276	7	266		180		11	9
II	121	because	231	is too	226	deep	7	---
III	85	13	81		69		15	11
IV	49	14	53		110		12	10
V	14	because	161	is too	805	deep	1	---
VI	7	16	8		29		16	12

* Projected for well with 150' Hyd. Frac.

** Avg. Thk./Thk. x 10 year cumulation projected for 150' Hyd. Frac.
= normalized for thickness.

*** Avg. Init. Rock Pres./Init. Rock Pres. x normalized thickness value
= normalized thickness x pressure.

FIGURE 3.3.2
LOCATION OF SELECTED PARTITION AREA
FOR DETAILED SITE SELECTION STUDIES

Figure 3.4.1 -- Structure Contoured on Pre-Cambrian Rocks Contoured in Thousands of Feet

RELATIONSHIP OF BASEMENT FAULTING
TO STRUCTURE ON THE BASE OF HURON SHALE

FIGURE 3.4.2

STRUCTURE MAP ON BEREA SANDSTONE
SOUTHWEST WEST VIRGINIA STUDY AREA

Figure 3.4.3 -- Berea Structure with Interpreted Faults and Fracture Zones

fracture zones is shown in Figure 3.4.4. Two potential sites were identified in this map area; Site No. 1, located on the southeastern corner of the Ranger 7-1/2 minute quadrangle, was selected to cross a fracture believed to be partly responsible for the production of 2 bcf of gas during the past 40 years (Figure 3.4.5); Site No. 2 is located in the northwestern corner of the Trace 7-1/2 minute quadrangle near the axis of a small anticline and crossing a postulated fracture zone.

Adjacent to this area in Lincoln District, Wayne County, West Virginia, a structure map of the Berea sandstone (prepared by Mammoth Geo, Barrackville, West Virginia) was given a similar re-interpretation to define postulated faults and fracture zones as shown in Figure 3.4.6. Three potential locations were defined on the northwestern section of the Wilsondale 7-1/2 minute quadrangle. Site No. 1 is located in the vicinity of several producing wells and crosses a projected fault (see Figure 3.4.7). Site No. 2 is surrounded on three sides by fractures or faults and is oriented away from any major projected fracture zone. Site No. 3 is located and designed so as to cross a major fracture zone believed to be responsible for producing nearly 2 bcf of gas during the past 40 years. Figure 3.4.8 depicts the Wilsondale gas pool well locations and iso-cumulative gas production contours which seem to confirm the orientation of the postulated fracture zones in Figure 3.4.6.

The positions of the proposed wells in relationship to current reservoir iso-pressure contour values help to rank the proposed locations as depicted on Figure 3.4.9. Table 3.4.1 compares geologic and engineering criteria for the sites in the two areas and the final ranking of the sites as proposed by BDM. Site No. 1 in Wayne County, West Virginia, received the highest ranking in keeping with the site selection criteria. DOE reviewed the data presented in the site selection report and initiated a series of reservoir modeling simulations of the field using production data from 38 wells and a history matching technique. DOE-METC personnel concluded that the final location should be Site No. 2 in Wayne County, West Virginia, based on less interference with currently producing wells and a higher ratio of recovery efficiency projected for a horizontal well in this location over a vertical well drilled on the same spot. The final location of the site selected is shown in Figure 3.4.10.

Figure 3.4.4 -- Correlation of Geologic Structure and Production

Figure 3.4.5 -- Proposed Locations in Lincoln County, West Virginia

WEBB 7.6' WILSONDALE 7.6'

BDM CORPORATION

Structure with Interpreted
Faults and Fracture Zones

PREPARED IN PART BY
MAMMOTH GEO

Figure 3.4.6

Figure 3.4.7

Relationship of Berea Structure
To High Cumulative Production Areas
and Proposed Well Locations

0 2000 4000

ELEVATIONS BELOW SEA LEVEL

CONTOUR INTERVAL 20'

WEBB 7.5' WILSONDALE 7.5'

BDM CORPORATION

PREPARED IN PART BY
MAMMOTH GEO

ISO-CUMULATIVE PRODUCTION CONTOURS

Contours in Millions of Cubic Feet of Gas

Figure 3.4.8

Figure 3.4.9 -- Relationship of Current Reservoir Pressure to Location of Proposed Directional Well

Geologic Criteria	200 Feet of Huron Shale	50 Feet of > 200 APIGR Units Response	Faults or Fractures Nearby	Remote Sensing Line. Corr. with Geologic Trends	High Fracture Density Area	Stress Ratio .3 to .5	Joints Make Acute Ang. w/Max. Hor. Stress	Engineering Criteria	Single Phase Prod. (Gas Only) Nearby	Present Rock Pressure > 50 Original Pressure	Nearby Wells Completed by Hyd. Frac. (5mi)	Good Fracture Permeability (High Cumulative Production)	Other Criteria	Gas Contract - 2 Yrs. Cont. Prod. GTD.	Cost Sharing by Lease Holder	Numerical Total	Final Rank
Wayne Co. W.V. Area																	
Site No. 1	X	X	X	X	X	X	X		X		X	X		X	X	12	2
Site No. 2	X	X		X			X			X	X			X	X	8	4
Site No. 3	X	X	X	X	X	X	X		X	X	X	X		X	X	13	1
Lincoln Co. W.V. Area																	
Site No. 1	X	X	X	X	X	X	X		X			X				10	3
Site No. 2	X	X		X			X			X						5	5

TABLE 3.4.1
Comparison of Geologic, Engineering, and Other Criteria
and Final Ranking for the Sites Evaluated

4.0 DRILL PLAN DEVELOPMENT ACTIVITIES

Considerable time and effort went into the planning of Recovery Efficiency Test Well No. 1. A literature search was conducted to find all the information available on high inclination wells. Computer programs were used to simulate torque, drag, and bottomhole assembly reactions. Several scenarios for drilling the well were explored. The scenarios were evaluated for risk and the final drilling plan was formulated.

4.1 Review of Literature

The literature relating to directional wells, with emphasis being placed upon high-angle wells, was reviewed. The literature was examined to determine the state-of-the-art of directional drilling. The findings have been summarized.

The most common build rates for high inclination wellbores were found to be from four to six degrees per 100 feet. Higher rates are generally avoided because of the larger bending stresses and resultant reduction in fatigue life.

Friction (torque and drag) is an inherent component in trajectory planning. Deviated well paths frequently experience limiting frictional forces.

Hole sizes vary and are primarily dependent upon casing diameter. Generally, additional casing clearances are designed into the casing programs.

The rotating bottomhole assembly is used whenever possible because of the cost differential versus the downhole motor. Bit walk is a constant problem with rotating BHAs and is incorporated into the directional plan whenever possible. Generally, low build rates of about two degrees per 100 feet are obtained with the rotary assembly.

Motors are used to build at higher rates and to make corrections in rotary drilled holes. Motors have a more predictable rate of build and result in a smoother wellbore path.

All the high inclination wells employ the use of an MWD system or at least a steering tool. The advent of the MWD system has cut drilling and surveying time considerably and is one reason for the increased amount of high inclination drilling being performed.

Wireline logging tools will not fall past an inclination of 60 degrees. The majority of the high angle wells mentioned in the literature do not have wireline open hole logs. Those that do use drill pipe conveyed logging tools, where the hole is logged one stand at a time.

There is practically no mention of coring high angle holes in the literature reviewed. Some coring has been done using downhole motors.

There is also very little mention about cementing casing in high inclination wellbores. Some are completed open hole and others are completed with slotted liners without cementing.

4.2 Review of Key Topics Researched

Downhole motors were researched to determine what is available and the advantages and disadvantages of each. Motors can be obtained in a wide range of sizes from 1-3/4 to 9-1/2 inches and speeds from 70 to 800 rpm.

The small diameter motors (2-7/8 inches and smaller) have low torque values and turn at high rpm. No slow speed motors are available in the small diameters. The larger diameter, slower speed motors (6-1/2 inches or larger) are more applicable to air drilling. All motors run on air must have a mist for lubrication. The slower the motor speed, the less likely it is to "tear itself up".

Motor deflection is accomplished with a bent sub or bent housing. This tilts the axis of the bit compared to the rest of the drill string. The motor will tend to drill along a constant radius arc in the direction of the tilted bit. The expected dogleg severity of the arc is determined by hole size, degree of the bent sub or housing, and motor diameter.

The closer the bend is to the bit, the greater the dogleg severity produced.

The rotating bottomhole assembly is usually used in the hold section of the hole in combination with motor corrections or is used to build or drop angle at lower rates. The deviation tendency in a rotary assembly is a result of the flexibility of the drill collars and the forces acting on the assembly causing the collars to bend.

Building assemblies use the bend in the collars and a fulcrum (stabilizer) near the bit to apply a positive building force at the bit. Holding assemblies limit the bending of the collars by several points of stabilization along the drill collars, attempting to achieve a neutral side force at the bit. A dropping assembly will use the weight of the drill collars below a stabilizer to cause a negative dropping force at the bit. This is often referred to as the pendulum effect.

Most MWD tools use mud pulse telemetry to send signals to the surface. They have proven accuracy and reliability. MWD tools can be used while rotary drilling or for orienting downhole motors.

The electromagnetic MWD tool uses electromagnetic waves to send signals up to the surface. In the Geoscience tool, the drill string is used as the primary signal transmitter. The more conductive the formation, the greater the signal loss will be. This tool can be used in air drilling, but its reliability is unknown.

The MWD will save time and money in a horizontal wellbore. Wireline tools and singleshots will have to be pumped down if possible. Scientific's EYE tool has been proven to work in an air environment.

The vast majority of high inclination wellbores are drilled using mud as a circulating medium. Hole cleaning is routinely accomplished in horizontal holes with higher plastic viscosities in laminar flow or lower plastic viscosities in turbulent flow. Also, mud will yield lower torque and drag values. Oil base muds provide even more lubricity.

Air can and has been used in directional drilling applications. An air-mist mixture must be used with downhole motors to provide cooling and lubrication. The air or air-mist system has problems cleaning the

hole at high inclinations. Hole cleaning will certainly be one of the major problems associated with the drilling of the RET No. 1 well.

The wellbore can be drilled full size, or it can be drilled with a smaller bit and opened later to full size. No directional drilling firms recommended drilling a smaller hole and opening it up to full size. The failure frequency of hole openers in a hard formation is high, and problems can be expected during hole opening operations.

Almost all operators who have experience with horizontal drilling recommend a top drive rig. With top drive (or power swivel), the string can be rotated while being raised or lowered, thus alleviating some of the drag problems.

If most of the heavier bottomhole assembly components are left out of the hole, a smaller rig can be used. This is possible because it takes more than 25,000 pounds of compression to buckle 4-1/2-inch drill pipe and 15,000 pounds to buckle 3-1/2-inch drill pipe in a 90 degree hole. BHAs can be rotated with low enough weights to keep the drill pipe from buckling. This would be easier with 4-1/2-inch drill pipe.

Specialty systems allow building angle at high rates (15 to 20 degrees per 100 feet), but are in the development stage. Reliability of these systems are questionable.

Build rates of 10 degrees per 100 feet are obtainable with conventional directional drilling equipment. Because of the potential problems with building inclination in the area, maximum build rates should not be planned. A moderate build rate should be used in the planning so there will be flexibility to increase the building tendency if the assemblies do not perform as expected.

There were two types of coring techniques available: conventional and wireline retrievable. The conventional approach requires that the drill string be tripped from the hole when the inner core barrel is filled. With the wireline retrievable system, a drill string remains in the hole and the inner barrel is tripped with a wireline, which saves time.

The wireline system is more reliable in the 1" to 2" sizes commonly used for mineral exploration. Wireline experience with the larger sizes is limited and will be further complicated by the high angle requirements. The experience with the smaller diameters far exceeds that for the larger diameters in the high angle wellbores.

The cost of obtaining electric logs in high angle wellbores is higher because they require mechanical placement (with drill pipe or coiled tubing) and specialty hardware and personnel. Open hole logs such as gamma ray, temperature, induction, formation density, flow meter, video inspection, and acoustic may be of use in the RET No. 1 well.

The three previous DOE-supported directional wells (Cottageville, Mingo County, and E.C. Newell) were analyzed to determine the feasibility of drilling a horizontal well. The analysis indicated that directional drilling should not be a problem in the area. E.C. Newell had the most problems and was the furthest away from RET No. 1. The other two wells (and the first 1600 feet of E.C. Newell) performed very much as expected. Motors tend to give smooth radial curves and BHAs are less predictable. Also, the best success was obtained in the larger hole sizes. Bit walk was always to the left and associated with bottomhole assemblies.

4.3 Rationale for Technical Approach

After an extensive literature review, computer modeling, risk analysis, and discussions with directional drilling experts, the final technical approach was determined. The best technical approach is to drill a large diameter hole, build at a moderate constant rate using motors to avoid problems with bit walk, and employ an MWD system. The hole should be drilled on air-mist to avoid lost circulation problems and to increase penetration rate. To achieve a non-invading fluid, the horizontal portion of the hole will have to be drilled with air-mist.

The 7-7/8-inch horizontal hole will allow use of more reliable, larger diameter motors, and 4-1/2-inch drill pipe. Many more twist-off problems are associated with 3-1/2-inch drill pipe than with 4-1/2-inch. The chances of success are higher in the 7-7/8-inch hole.

It is anticipated that the technical approach will provide the desired wellbore configuration at minimum expense and provide enough information to evaluate the potential for horizontal wells in the Devonian shale.

There are potential problems with the proposed well. The most significant problem will be hole cleaning. The ability to clean a high angle well with air has not been established. As much as 1.5 times and 3 times the minimum air requirements will be available for the 10-5/8-inch and 7-7/8-inch holes, respectively. There is no way to determine whether this will be adequate without actually drilling the well. The problem will be compounded if the shale sloughs significantly.

Another potential problem is the MWD system. If the system fails, it will be much more difficult to drill the well using steering tools and singleshots.

Torque and drag may be a problem if it exceeds the rig capabilities. According to the computer modeling, this should not be a problem. If it does become a problem, it will probably be due more to hole cleaning than friction.

4.4 Review of Optional Scenarios

Several scenarios were developed to determine the best method to drill the recovery efficiency well. The analysis required three steps. The first step was to model the shape of the hole to determine which hole shape would yield the least amount of torque and drag. Second, the best scenarios were costed. Then each scenario was rated for risk. The lowest risk well would have the highest probability of success.

Six wellbore configurations were developed to determine the effect of wellbore shape on torque and drag. The shapes included everything from kicking off shallow and building slowly, to kicking off deep and building rapidly. Five of the six scenarios assumed a final hole size of 6-1/4 inches and one assumed a final hole size of 7-7/8 inches. The scenarios were designed to build angle with rotating assemblies, motors, and medium radius turn technology.

Table 4.4.1 shows the drilling data for each of the scenarios. Table 4.4.2 shows the results of the computer simulation.

SCENARIO #	KICK-OFF POINT	BUILD RATE	METHOD OF BUILD
1	1000'	4°/100' to 45° Drill 1100' at 45° 5°/100' to 85°	MOTOR BHA MOTOR
2	1700'	4°/100' to 85°	MOTOR
3	2300'	7°/100' to 85°	MOTOR
4	800'	3°/100' to 12° 2°/100' to 53° 5°/100' to 85°	MOTOR BHA MOTOR
5	1700'	4°/100' to 85°	MOTOR
6	2850'	20°/100' to 90°	MOTOR

TABLE 4.4.1
DRILLING SCENARIO DIRECTIONAL PROGRAMS

As can be seen from Table 4.4.2, the torque and drag for each scenario, except No. 5, are very similar. Scenario No. 5 shows significantly higher torque and drag values; however, as a percent of tubular yield strength, the values are very similar. The difference in the torque and drag values is not enough to pinpoint the best scenario.

HOLE CONDITIONS	SCENARIO											
	#1	#2	#3	#4	#5	#6						
COEF. FRIC=0.45 HORIZ. HOLE = 2000'	RTT = 8,901 HLD = 1,338 HLU = 79,133	RTT = 8,786 HLD = 2,543 HLU = 67,835	RTT = 8,568 HLD = 4,835 HLU = 69,929	RTT = 8,849 HLD = 2,266 HLU = 68,062	RTT = 14,786 HLD = -4,783 HLU = 91,064	RTT = 8,377 HLD = 6,777 HLU = 73,067						
COEF. FRIC=0.30 HORIZ. HOLE = 2000'	RTT = 6,434 HLD = 20,145 HLU = 63,576	RTT = 6,358 HLD = 21,176 HLU = 57,837	RTT = 6,212 HLD = 22,373 HLU = 56,996	RTT = 6,399 HLD = 20,321 HLU = 58,128	RTT = 10,524 HLD = 22,100 HLU = 75,128	RTT = 6,085 HLD = 23,311 HLU = 58,283						
COEF. FRIC=0.55 HORIZ. HOLE = 2000'	RTT = 10,515 HLD = -15,834 HLU = 92,407	RTT = 10,405 HLD = -14,346 HLU = 77,129	RTT = 10,138 HLD = -11,156 HLU = 81,373	RTT = 10,482 HLD = -14,670 HLU = 77,259	RTT = 17,627 HLD = -29,503 HLU = 106,634	RTT = 9,905 HLD = -8,233 HLU = 86,561						
COEF. FRIC=0.75 HORIZ. HOLE = 2000'	RTT = 13,834 HLD = -65,210 HLU = 129,050	RTT = 13,644 HLD = -62,887 HLU = 105,286	RTT = 13,280 HLD = -57,328 HLU = 113,386	RTT = 13,748 HLD = -63,117 HLU = 104,725	RTT = 23,310 HLD = -99,813 HLU = 149,940	RTT = 12,962 HLD = -51,410 HLU = 125,480						
COEF. FRIC=0.45 HORIZ. HOLE = 1000'	RTT = 7,715 HLD = 13,584 HLU = 69,931	RTT = 7,599 HLD = 14,765 HLU = 60,223	RTT = 7,381 HLD = 17,150 HLU = 58,722	RTT = 7,662 HLD = 14,350 HLU = 60,271	RTT = 12,884 HLD = 10,259 HLU = 79,929	RTT = 7,196 HLD = 18,889 HLU = 61,115						
ANGLE BUILD PT. f.e., 85° COEF. FRIC=0.45	RTT = 14,087 HLD = 34,457 HLU = 114,134	RTT = 12,180 HLD = 35,998 HLU = 97,763	RTT = 11,076 HLD = 49,348 HLU = 94,281	RTT = 12,811 HLD = 35,207 HLU = 101,890	RTT = 12,180 HLD = 35,998 HLU = 97,763	RTT = 13,005 HLD = 52,574 HLU = 82,508						

TABLE 4.4.2 - COMPARISON OF DRILLING SCENARIOS

RTT = Rotary Table Torque while drilling

HLD = Hook Load Down while tripping

HLU = Hook Load Up while tripping

(A negative value is a compressive force)

All of the advantages, disadvantages, and risks of each scenario were weighed and assigned a ranking. The costs for each scenario were determined and assigned a ranking along with the hole drag values. The scenario with the best ranking was scenario No. 5 because of the lower risk value. Therefore, scenario No. 5 was chosen as the optimum drilling plan.

4.5 Directional Drilling Well Plan

The conceptual design of the well as envisioned by BDM is shown in Figure 4.5.1. The proposed well program is summarized as follows:

- o Drill a 17-1/2 or 18-inch hole to 630 feet and set a 16-inch fresh water protection string.
- o Drill a 14-1/2-inch hole vertically to below the Big Injun at 2000 feet and set 11-3/4-inch casing.
- o Kick off at 2080 feet and build to 85 degrees (4.25 degrees per 100 feet) using downhole motors and a 10-5/8-inch bit.
- o Log the 10-5/8-inch hole.
- o Run 8-5/8-inch casing.
- o Drill out and core 60 feet of horizontal hole.
- o Drill 2000 feet of horizontal hole using BHAs and downhole motors as required.
- o Log the 7-7/8-inch hole.
- o Run 4-1/2-inch casing and isolate the potential producing zones using ECPs.
- o Test the well through the port collars.

A wellbore schematic is shown in Figure 4.5.2. The Recovery Efficiency Test well, beyond a doubt, prove or disprove the system. The ultimate objective of the Recovery Efficiency Test well is to determine the productivity increase of a horizontal well in the Devonian shale. To accomplish this, multiple completions in the horizontal section are required. The technology of isolating, stimulating, and testing individual zones will be tested.

Devonian Shale Horizontal Well

— Conceptual Design —

Figure 4.5.1

Figure 4.5.2 -- Scenario #5 Wellbore Schematic

Though coring at high inclinations has been accomplished, little data is available. The ability to core while maintaining inclination will be determined.

4.5.1 Well Prognosis

The optimum scenario is No. 5 revised for the actual location and budget constraints. The well builds angle at 4.25 degrees per 100 feet and provides a 7-7/8-inch horizontal hole. The rate of angle build should be easy to obtain and the larger 7-7/8-inch hole allows a larger selection of downhole tools. Also, the risk of fishing with 4-1/2-inch drill pipe will be less.

The vertical section of the hole will be from 0 to 2000 feet. This portion will be drilled on footage. The procedure will be as follows:

- o Drill a 17-1/2-inch (or 18-inch) hole to 630 feet.
 - o Run and set 630 feet of 16-inch conductor pipe.
 - o Cement to surface. Waiting on cement 8 hours.
 - o Nipple up air head.
 - o Drill a 14-3/4-inch hole to 2000 feet using air and mist (approximately 3500 scfm).
 - o Run and set 11-3/4-inch, 47 pound, J-55, ST&C casing as follows:
 - Guide shoe
 - 1 joint 11-3/4-inch casing
 - Insert float valve
 - Remaining 11-3/4-inch casing.
- Place one centralizer in the center of the first joint. Place one centralizer on each coupling for 200 feet. Total six centralizers.
- o Cement back to 1300 feet using 200 sacks of Class "A" cement containing 2 percent CaCl_2 and 100 sacks of Halliburton light containing 3 percent CaCl_2 (20 percent excess). WOC 8 hours.
 - o Nipple up wellhead and rotating head.
 - o Drill out with a 10-5/8-inch bit.

Directional Requirements: In the vertical portion of the hole, the maximum dogleg severity will be 1 degree per 100 feet. Maximum angle will be 3 degrees.

Since this portion of the well is to be drilled on footage, it will be up to the drilling contractor to drill the hole, following the directional requirements and casing specifications. Inclination will be built at an average rate of 4.25 degrees per 100 feet using downhole motors.

1. At 2080 feet, run a 10-5/8-inch air bit, 7-3/4-inch Baker motor, 2-1/2-inch bent sub (BS), 8-inch Monel drill collar, MWD (Geoscience), 2-8-inch steel drill collars, and 4-1/2-inch drill pipe.
2. Directionally drill at 4.25 degrees per 100 feet. If the 2-1/2 degrees BS does not give 4.25 degrees per 100 feet, use a 3 degree BS or a bent housing motor in combination with a bent sub. A 2-1/2 degree BS should give 5-1/2 degrees per 100 feet.
3. Drill to 85-90 degrees at a TVD of 3423 feet (50 feet from bottom of Lower Huron) which should be approximately 4080 feet measured depth (MD).

NOTE: If inclination will not build at approximately 4.25 degrees per 100 feet, use a 2 degree bent housing Baker motor (6-3/4-inch). If problems persist, use a bent sub with the bent housing motor. A standoff ring can be added if required (see contingency plan).

4. Circulation rate should be 2500 cfm with <10 bbls/hr mist. As hole cleaning becomes a problem, the air rate should be increased gradually to 4000 cfm. Use a bypass orifice in the motor as recommended by Baker for higher flow rates. If hole cleaning is still a problem, add polymer to the mist to stiffen the foam. Start out at 1 qt/20 bbls and increase as needed (see contingency plan).
5. At times it may be necessary to make reaming runs to bring the hole into gauge. If this is necessary, run a bit, 3 point reamer, 8-inch Monel, 3 point reamer and two 8-inch DCs. Ream this assembly through the portion of the hole that is causing problems.

6. Log the well according to Section 4.5.5.
7. Run and set 8-5/8-inch, 24 pounds per foot and 28 pounds per foot, J-55, ST&C casing at ± 4080 feet as follows:
 - Guide shoe
 - 1 joint 28 pound per foot casing
 - Float collar
 - Total of 1800 feet 28 pound per foot casing
 - Remaining 24 pound per foot casingPlace one centralizer in the middle of the first joint and one centralizer on each coupling for the next 300 feet (9 centralizers). Place two cementing baskets 150 feet from surface.
8. Cement with 50 sacks bentonite preflush followed by 250 sacks Class A cement. Place 10 feet of sand in annulus and fill annulus with Class A cement. WOC 8 hours.
9. Nipple up wellhead, bag preventer and rotating head.

The horizontal section will be drilled in the bottom 50 feet of the Lower Huron.

1. Drill out of 8-5/8-inch casing with a 7-7/8-inch bit, 3-point and Monel drill collar.
2. Core 60 feet of the Lower Huron at 85 to 90 degrees.
3. Ream out core hole with 7-7/8-inch bit, 3-point reamer and Monel with MWD. Drill ahead until a motor correction is required or TD is reached.
4. Run a 7-7/8-inch air bit, 6-3/4-inch motor with bent housing, 6-1/4-inch Monel, and 4-1/2-inch drill pipe. The setting for the motor will be determined from data gained while building angle. The setting should be around 3/8 degree.
5. Drill 2000 feet of horizontal hole in the Lower Huron. Circulation rate should be 2400 cfm with <10 bbls mist/hr containing 1 qt/20 bbls polymer. Air rates should be increased to as much as 4000 cfm if hole cleaning is a problem. Then, polymer should be increased in volume if required. Rotating the motor while drilling some of the hole may help. (See contingencies.)

6. At TD, log and test the well.
7. Run and set 4-1/2-inch, 10.5 pounds per foot J-55, ST&C at TD as follows:
 - Bull plug
 - 1 joint 4-1/2-inch casing
 - External casing packers and port collars as required.
 - Remaining 4-1/2-inch casing.
8. Cement as shown in the cementing program.

4.5.2 Contingency Plans

Inclination will not build: In the 10-5/8-inch section of the hole, inclination will be built primarily using a 7-3/4-inch Baker motor and a bent sub. A 2-1/2 degree bent sub should build more than 5 degrees per 100 feet and a 3 degree bent sub should build at least 6 degrees per 100 feet. If the angle won't build at 4.25 degrees per 100 feet, use a 6-3/4-inch bent housing motor at 2 degrees which should give 5-1/2 degrees per 100 feet. A bent sub can be used in combination with the bent housing to obtain more building tendency. A 2 degree sub and 2 degree housing should give approximately 10 degrees per 100 feet. A standoff ring can be welded onto the bent sub or stabilizer placed just above the bent sub if necessary to give more inclination tendency.

If all the above fails, convert the hole to mud and use the previous methods of bent sub and housing to increase inclination. If the angle still won't increase, nothing else can be done. At this point, a decision can be made to drill ahead with a building assembly or to run casing and employ a short radius turn system.

In the first scenario, a radical building assembly could be run to continue drilling. The assembly may consist of a bit, 3 point reamer, two joints drill pipe, 3 point reamer, monel, MWD and drill collars. The assembly would be used to drill ahead to the 8-5/8-inch casing point. After the 8-5/8-inch casing is set, the Lower Huron would be cored. Drilling would continue with a rotating assembly until the entire Lower Huron section had been drilled.

In the second scenario, a short radius turn system would be used to build inclination and drill the horizontal section. A string of 7-inch casing will have to be run since the short radius systems use small diameter equipment. The exact setting depth of the 7-inch casing would depend upon the inclination of the hole. The greater the inclination, the deeper the casing can be set. Additional funding would be required to use the short radius turn scenario.

Sloughing Shale: A mist system is required when using downhole motors to provide cooling and lubrication. The motors cannot be run dry. The Devonian shale is noted for sloughing when it gets wet. The shale may slough enough to prevent further drilling with downhole motors. Three options are available. They are: (1) dry the hole up and drill ahead with a building assembly; (2) run 8-5/8-inch casing; or (3) convert the well to a mud system.

Option 1 would be very similar to the first scenario stated above where a building assembly is run to drill to the 8-5/8-inch casing point. Option 2 could be used if the well is already close to the 8-5/8-inch casing point. After setting casing, the remaining inclination can be built in the 7-7/8-inch hole.

Option 3 involves converting the well to a mud system. A mud system will provide better hole cleaning; however, it slows down drilling operations. Converting to a mud system will require additional funding because of the increased time on location and the potential for severe lost circulation.

4.5.3 Hole Cleaning and Conditioning (Reaming)

Hole Cleaning: If hole cleaning becomes a problem, increase the air rate to as much as 4000 cfm. Beyond this, the polymer rate should be increased to stiffen the foam which will help transport cuttings. Pipe rotation will help cleaning if possible.

In the horizontal hole, it may be necessary to do some rotating with the bent housing motor. This should be limited as much as possible because rotating in a hard formation may damage the motor bearings.

If the horizontal hole cannot be cleaned with a downhole motor, two alternatives are available: (1) Switch the drilling fluid to a high viscosity mud system; (2) Use a rotary building assembly and drill with 20,000 to 25,000 pounds bit weight. The assembly should consist of:

- 7-7/8-inch journal bearing bit (J-44)
- 1 - 2 foot long 6-1/4-inch float sub
- 1 - 7-7/8-inch bottomhole 3 point reamer
- 1 - 6-1/4-inch Monel
- 1 - 6-1/4-inch MWD
- 4-1/2-inch drill pipe

Hole Reaming: Hole reaming will probably be necessary behind long motor runs. When the used bit comes out of the hole slightly undergauge, a new bit will not go to bottom. A reaming assembly can be run to bring the hole back in gauge. This may also help to smooth out the rugosity of the wellbore and enhance the probability of being able to get the casing to bottom. Generally, if the DCs and full gauge reamers will go in the hole, the casing will go in the hole. The reaming assembly should consist of the following:

- Bit
- Full gauge 3 point reamer
- 1 drill collar (8-inch in 10-5/8-inch hole and
6-1/4-inch in 7-7/8-inch hole)
- Full gauge 3 point reamer
- 1 drill collar (as above)
- 4-1/2-inch drill pipe.

Care should be taken not to force the reaming assembly into an undergauge hole. It may not come back out.

4.5.4 Directional Control

The directional program is designed to allow a relatively easy build rate of 4.25 degrees per 100 feet. Based on the data from the Cottageville well, it should not be that difficult to obtain. The biggest problem in the Cottageville well came from bit walk. By building with a downhole motor, bit walk will be avoided.

The directional program is shown in Table 4.5.1. The well will be drilled vertically to 2080 feet. At 2080 feet, the inclination will be built at a rate of 4.25 degrees per 100 feet in a S37°E direction. Total horizontal displacement will be 2230 feet. The motor in conjunction with Geoscience's MWD unit should provide fast, accurate directional drilling.

The horizontal hole will be drilled without a downhole motor. This is more desirable from a hole cleaning standpoint. If required, a bent housing motor could be adjusted to just offset the natural dropping tendency of the slick assembly. If the motor builds too much, the motor could be cycled so that it will turn left and then right. This will allow it to maintain inclination without pulling the motor for adjustments. The MWD will be used for precise control.

If hole cleaning is a problem, a BHA can be used to maintain inclination. The bit, lift sub, and reamer will provide a maximum building assembly. Weight will be adjusted to maintain inclination. Based on the reaction of the assemblies in the Cottageville well, 25,000-pound bit weight should increase inclination by about 1 to 2 degrees per 100 feet. The resultant force inclination is 4 degrees greater than hole inclination. In the Cottageville well, the 60-foot building assembly had a resultant force inclination 4 degrees greater than hole inclination and built 2 degrees per 100 feet. Unfortunately, bit walk may be a problem. A ± 10 degree bit walk should be allowed before a motor correction is made. The vertical view can be seen in Figure 4.5.3.

Table 4.5.1

PROPOSED TARGET INFORMATION OUTPUT

PROPOSED DIRECTION S 37.00 E

SURVEY STATION PARAMETERS OUTPUT

NO.	M.D. (FT)	INC. (DEG)	DIRECTION			<-----		LOCATION (FT)	-----	
			N/S	AZM (DEG)	E/W	+N / -S		+E / -W		TVD
1	.00	.00	S	37.00	E	.0		.0		.0
2	2113.00	.00	S	37.00	E	.0		.0		2113.0
3	2213.00	4.48	S	37.00	E	-3.1		2.4		2212.9
4	2313.00	8.96	S	37.00	E	-12.5		9.4		2312.2
5	2413.00	13.44	S	37.00	E	-28.0		21.1		2410.3
6	2513.00	17.92	S	37.00	E	-49.6		37.3		2506.5
7	2613.00	22.40	S	37.00	E	-77.1		58.1		2600.4
8	2713.00	26.88	S	37.00	E	-110.4		83.2		2691.2
9	2813.00	31.36	S	37.00	E	-149.2		112.4		2778.6
10	2913.00	35.84	S	37.00	E	-193.4		145.7		2861.8
11	3013.00	40.32	S	37.00	E	-242.6		182.8		2940.5
12	3113.00	44.80	S	37.00	E	-296.6		223.5		3014.2
13	3213.00	49.28	S	37.00	E	-355.1		267.6		3082.3
14	3313.00	53.76	S	37.00	E	-417.6		314.7		3144.5
15	3413.00	58.24	S	37.00	E	-483.8		364.5		3200.4
16	3513.00	62.72	S	37.00	E	-553.2		416.9		3249.7
17	3613.00	67.20	S	37.00	E	-625.6		471.4		3292.0
18	3713.00	71.68	S	37.00	E	-700.3		527.7		3327.1
19	3813.00	76.16	S	37.00	E	-777.1		585.6		3354.8
20	3913.00	80.64	S	37.00	E	-855.3		644.5		3374.9
21	4013.00	85.12	S	37.00	E	-934.5		704.2		3387.3
22	4113.00	89.60	S	37.00	E	-1014.3		764.3		3391.9
23	4122.00	90.00	S	37.00	E	-1021.5		769.7		3391.9
24	4213.00	90.00	S	37.00	E	-1094.1		824.5		3391.9
25	4313.00	90.00	S	37.00	E	-1174.0		884.7		3391.9
26	4413.00	90.00	S	37.00	E	-1253.9		944.8		3391.9
27	4513.00	90.00	S	37.00	E	-1333.7		1005.0		3391.9
28	4613.00	90.00	S	37.00	E	-1413.6		1065.2		3391.9
29	4713.00	90.00	S	37.00	E	-1493.4		1125.4		3391.9
30	4813.00	90.00	S	37.00	E	-1573.3		1185.6		3391.9
31	4913.00	90.00	S	37.00	E	-1653.2		1245.8		3391.9
32	5013.00	90.00	S	37.00	E	-1733.0		1305.9		3391.9
33	5113.00	90.00	S	37.00	E	-1812.9		1366.1		3391.9
34	5213.00	90.00	S	37.00	E	-1892.8		1426.3		3391.9
35	5313.00	90.00	S	37.00	E	-1972.6		1486.5		3391.9
36	5413.00	90.00	S	37.00	E	-2052.5		1546.7		3391.9
37	5513.00	90.00	S	37.00	E	-2132.4		1606.8		3391.8
38	5613.00	90.00	S	37.00	E	-2212.2		1667.0		3391.8
39	5713.00	90.00	S	37.00	E	-2292.1		1727.2		3391.8
40	5813.00	90.00	S	37.00	E	-2371.9		1787.4		3391.8
41	5913.00	90.00	S	37.00	E	-2451.8		1847.6		3391.8
42	6010.00	90.00	S	37.00	E	-2529.3		1905.9		3391.8
43	6010.00	90.00	S	37.00	E	-2529.3		1905.9		3391.8

PLANNED VERTICAL VIEW

RBT #1

Figure 4.5.3 -- Vertical View of Scenario #5

4.5.5 Coring

The plan is to obtain an oriented core in the high angle portion of the hole upon drilling out of the 8-5/8-inch intermediate casing at 85 degrees. Additional stabilization is required for the inner barrel at angles above 65 degrees; otherwise, the inner barrel may rub the outer barrel, resulting in core breakage. Maximum barrel lengths of 30 feet should be used in deviated well sections. The barrels will have to be manufactured specifically for this project. A 6-1/4 inch core barrel will be required in the 7-7/8 inch hole, and a 3-1/2 inch core will be cut.

1. After setting the 8-5/8-inch casing, drill out with a 7-7/8-inch bit and three point reamer. Drill approximately 75 feet of hole so that the orienting equipment will be out of the casing while coring.
2. Pick up coring equipment. Install the angle unit assembly and engage the mule shoe. Install the multishot camera set at ten minute intervals.
3. Core using the air-mist system.
4. After coring 30 feet, pull out of the hole and lay down the core.
5. Repeat the above steps until 60 feet of core has been obtained.
6. Run in the hole with a bit and three point reamer to ream out the core hole. Drill ahead until a motor correction is required.

4.5.6 Logging Plan

The electric logging program involves two separate trips to the well. The first is at the 8-5/8-inch intermediate casing point when the inclination is 85 degrees at approximately 4080 feet. Conventional logging operations are to be performed to the maximum attainable depth under the force of gravity. The tools are expected to fall to a limiting inclination angle of approximately 55 degrees. The second logging operation will be performed when drilling is finished on the

high angle segment and will employ drill pipe conveyed logging tools. The tools will be limited to those that will aid in fracture identification and depth control only. This is because of the additional expense associated with conveyed wireline logging tools. The logging sondes will be placed with 4-1/2-inch drill pipe using a technique developed for offshore wells by a major wireline service company.

The originally-planned logging suite (LDT-NGT, SNP, DIL, TEMP, AUDIO, LITHO ANALYSIS) may be reduced to an FDC-GR, DIL and a temperature if the natural production above an inclination angle of 55 degrees is greater than 50 mcfd.

The subsequent high angle (60 to 90 degrees) logging operations employs only those tools that will aid in fracture identification. The program includes a drill string or coiled tubing conveyed television survey and concurrent or subsequent gamma ray-temperature log in the high angle hole segment to identify fracture locations to enable completion operations to straddle these intervals. The gamma ray can be pulled the entire way out and checked with the conventional logging activities performed previously. This will enable any depth measurement system differences to be identified and allow them to be scaled out.

The current practice is to use the drill string to convey the logging tools. The practice of utilizing coiled tubing to convey wireline electric logging tools in high angle holes is presently under development by Dresser Atlas and shows promise. The television survey requires a coaxial cable to be installed inside the coiled tubing. The combination of a gamma ray signal on the coaxial cable is under review. Preliminary indications are not promising. In any event, the television survey will be attempted with either drill string conveyance or coiled tubing conveyance. The system used will be that which has the highest probability of success with reasonable costs.

4.5.7 Casing Program

The casing program is as follows:

630 feet - 16-inch conductor

2000 feet - 11-3/4-inch, 47 pounds per foot, J-55,
ST&C

4080 feet - 8-5/8-inch, 24 pounds per foot, J-55,
ST&C

6080 feet - 4-1/2-inch, 10.5 pounds per foot, J-55,
ST&C.

The 2000 feet of 11-3/4-inch surface casing will be run to isolate the salt water zones from the fresh water zones to satisfy state regulatory requirements and to isolate potential production from the Big Lime and Big Injun. The pipe will be cemented to the surface. The Berea Formation is tight in this area and is not expected to be a problem.

The 8-5/8-inch casing will be run to protect the build portion of the hole. There is concern that the Devonian shale will become unstable after a period of time. The 8-5/8-inch casing will alleviate this problem. The bottom 500 to 600 feet of casing will be cemented.

The 4-1/2-inch casing will be the production casing and will be set at total depth (TD). The production interval will be isolated with external casing packers to allow testing of individual zones.

the low dogleg severity of 4.25 degrees per 100 feet should not present a problem for running any casing string. Hole rugosity may cause a problem, but reaming the hole should alleviate this problem.

the high angle segment of the hole is to be drilled with a "non-invading" fluid, and the completion involves casing and creating zonal isolation between fracture intervals. The plan is to utilize hydraulically inflatable packer elements on the outside of the casing on either side of the fracture intervals identified by the logging/coring operations. An attempt will be made to isolate the zones

to be tested by inflating the packers. If the packers hold, cementing operations will be bypassed; if they do not hold, cement will be squeezed between the zones using ported collars between the packers. Additionally, ported collars will also be placed across the fractures themselves to eliminate the need for perforating later. These ported collars could be used for cement squeezing across the fractured intervals in the event of a packer or primary cementing failure.

For casing, the manufacturer's inspection will be sufficient. Threads will be cleaned and visually inspected at the site.

The 4-1/2-inch drill pipe will be inspected prior to drilling. A sonoscope (or equivalent) standard rack inspection will be performed on the drill pipe. Only pipe that meets the minimum requirements for API premium used drill pipe will be accepted.

5.0 SITE DEVELOPMENT PLAN

The location of the Recovery Efficiency Test Well No. 1 is on the western flank of the Tick Ridge in the Cabwaylingo State Forest. Figure 5.0.1 shows the location of the well and the access roads.

5.1 Wellsite Layout

Figure 5.1.1 shows the proposed layout of the drill site along with a generic equipment layout. The road and site construction will conform to West Virginia's Oil and Gas Regulations. After the site has been surveyed and staked, the actual layout may change slightly depending upon terrain.

5.2 Waste Management

The drilling fluids will be contained within the reserve pit. Prior to site reclamation, the water in the pit will be neutralized. Then, the water will be disposed of using the land disposal method in which the water is sprinkled over an area and allowed to soak in. The method will be approved by the state in the drilling permitting process.

A portable toilet will be on location to contend with human waste. The waste will be hauled off and disposed of at the nearest state-approved disposal site in the Cabwaylingo State Forest. A refuse barrel will contain other waste material and will be disposed of at the nearest approved dump.

5.3 Site Reclamation Plan

The site will be reclaimed by draining and back-filling the pits, disposing of pit fluids, and restoring the site as nearly as possible to its original condition. See the West Virginia State Construction and Reclamation Plan (Figure 5.3.1).

Figure 5.1.1 -- WELLSITE LAYOUT

ATTACH OR PHOTOCOPY SECTION OF
INVOLVED TOPOGRAPHIC MAP.
QUADRANGLE Wilsondale/Webb

Sketch to include well location, existing access road, roads to be constructed, well site, drilling pits and necessary structures numbered or lettered to correspond with the first part of this plan. Include all natural drainage.

COMMENTS:

1. Length of Access Road 300'
2. Brush to be Cut and Piled at Site.
3. Trees to be Cut and Stacked at Site.
4. Location Located Approximately 250' West of County Road.
5. Access Road Will Be Sloped 2-3% Towards The Open Ditch.
6. All Outlets of Drainage Structures and Ditches Will Be In A Stable Area.
7. All Cuts Will Be 2:1 Slope Or Less.

Figure 5.3.1

6.0 DRILLING OPERATIONS

Drilling operations were conducted at the selected site between October 21 and December 18, 1986. Figure 6.0.1 shows a plot of depth versus days for the actual and planned drilling program. It actually took 58 days to drill 2000 feet of horizontal wellbore. The planned drilling time was 45 days.

The major difference in drilling time occurred in the vertical portion of the hole, which HLH Drilling Company drilled on footage. The estimated drilling time was three days and it actually took 15 days. The directional portion of the hole was planned at 42 days and required 43 days. The building portion of the well took longer than expected because of the two sidetracks; however, the horizontal went faster than expected because no motor corrections were required.

The primary objective of the drilling plan was to drill and evaluate a 2000-foot horizontal wellbore. The objective was accomplished by drilling the Recovery Efficiency Test Well No. 1. The well has more than 2000 feet of wellbore over 85 degrees that can be tested and evaluated. Both the coring and logging programs were successful and will aid in the evaluation of the well. Logging was not completely successful because the density tool did not work properly. However, the fractures were identified with the TV camera and the temperature logs. Well testing is still being conducted.

Figure 6.0.2 is a wellbore diagram showing the final status of the well along with casing sizes and setting points. The 16-inch casing is set deeper than planned to satisfy West Virginia Department of Energy requirements. They also required the 11-3/4-inch casing to be cemented to the surface instead of 1300 feet as planned.

6.1 Selection of the Operations Team

All of the equipment and services at the site were selected by competitive bid. The drilling contractor, HLH Drilling, was selected because their rig met or exceeded all the minimum requirements, and the owners of the company took an active role in the operations of the drilling

Schedule Devonian Shale Horizontal Well

Figure 6.0.1

BDM CORPORATION

RECOVERY EFFICIENCY TEST WELL #1

WELLBORE DIAGRAM

Figure 6.0.2 -- Wellbore Diagram Showing Final Status of Casing, Port Collars, and External Casing Packers

rig. As it turned out, the rig and personnel performed well. The downtime required for repairs was much less than expected considering the rough drilling conditions encountered. The 250,000-pound hook load capability was required during the fishing operations. A smaller rig could have been used but would not have been as effective. The drilling rig and crew were well-suited for the operations.

The directional drilling contractor, Eastman Christensen, was selected because of their experience in the Appalachian Basin. The MWD system was provided by Geoscience Electronics because it was the only system available that would work in an air-filled hole. Scientific Drilling was chosen as the backup to the MWD because of their proven ability to work in an air environment. Grace, Shursen, Moore, and Associates was chosen to help manage drilling operations because of their previous experience in drilling high inclination air holes; also, they had helped formulate the drilling plan.

6.2 Vertical Hole Drilling Operations

The vertical hole was drilled on a footage contract by HLH Drilling to a measured depth of 2124 feet. The drilling plan called for drilling the vertical portion of the hole in three days; however, drilling required 15 days. There are two reasons the surface hole took longer than expected. One was a fishing job that required the contractor to skid the rig and start over. The other was that the formations were harder than anticipated and the penetration rates were low, especially with the larger bits.

The well was spudded at 6:41 p.m. on October 21, 1986. A 22-inch bit and air hammer was used to drill the conductor hole to 48 feet KB. The 20-inch conductor casing was set at 48 feet with no problems.

The surface hole was drilled with an 18-1/2-inch bit and air hammer to 160 feet KB when two shanks broke off the bit. The bit was originally a 17-1/2-inch bit that had been enlarged to 18-1/2-inches by cutting the bit and spreading the shanks. The method used, along with the stress caused by the air hammer, could have contributed to the failure.

HLH built a finger basket in order to retrieve the lost shanks, but were unsuccessful. Because of the size and shape of the "fish" (lost tools), it would have been very difficult to retrieve, so the decision was made to skid the rig and start over. The rig was skidded 15 feet to the east and drilling began again. Approximately three days were lost.

The conductor hole was again spudded at 7:00 p.m. on October 24, 1986. The conductor hole was drilled to 30 feet KB using a 22-inch bit and air hammer. The 20-inch conductor was set at 30 feet.

The surface hole was again drilled with an 18-1/2-inch bit and air hammer to 161 feet. HLH pulled the bit periodically to check for cracks in the bit shanks. After drilling to 161 feet, cracks were found in the bit at the nozzle. Closer inspection of the 22-inch bit revealed cracks in that bit also. HLH decided to lay down the air hammer and continue drilling without it. The 18-1/2-inch bits are not a common size and are not easily located. Therefore, drilling continued to the 16-inch casing point with a 17-1/2-inch bit.

An attempt was made to run the 16-inch casing but the first joint would not go past the bottom of the conductor pipe. The conductor was pulled and had a slight bend on the bottom of it. The casing was again run but would not go past 60 feet. The hole had to be offset to cause the casing to bind in the 18-1/2-inch hole.

A 17-1/2-inch, bottomhole, three point reamer was run above the bit and the hole was reamed out to TD. Several spots in the upper portion of the hole reamed hard.

The 16-inch casing was again run. The casing went in with no problem to about 350 feet, where it hung up again. The casing was worked up and down several times, which reduced the drag. Casing was then run to bottom without further problems.

The casing was 16-inch, 65 pound per foot, H-40, Buttress and was set at 649.53 feet KB. The casing was cemented to surface with 270 sacks of Class A cement containing 3 percent calcium chloride. No float equipment, guide shoe or centralizers were run on the casing. Casing was set deeper than planned because it was requested by the State Department of Energy (DOE) for aquifer protection.

The 14-3/4-inch hole was drilled to 2124 feet. The biggest problem in this portion of the hole was the rough drilling. HLH was running low bit weight and rpms because the bit was torquing and drilling rough. At 1760 feet, the rpms were increased to 150 and the penetration rate went from 10 to 25 feet per hour. The torque and rough drilling also smoothed out.

The well was logged by Young Wireline. The log indicated that the 11-3/4-inch casing only had to be set at about 2025, feet which places one joint below the Big Injun formation. The intent was to isolate potential production from the zones above and in the Big Injun.

A string of 11-3/4-inch, 47 pound per foot, K-55, ST&C casing was run to 2024 feet KB. The casing was cemented to the surface with 350 sacks of Halliburton light containing 3 percent calcium chloride followed by 425 sacks of Class A containing 2 percent calcium chloride. The drilling plan had called for cementing the casing up above the salt water zones to 1300 feet, but the State DOE required cementing back to surface to isolate coal seams and aquifers. Therefore, the casing was cemented to the surface.

After waiting on cement for 12 hours (state requirement), the casing was nipped up with a bag preventer and the shoe joint drilled out. When the well was cleaned out to TD, the drill pipe was strapped out of the hole. The depth of the well was changed to 2113 feet to correspond to the strap. Directional drilling began.

HLH had run five deviation surveys in the vertical portion of the hole. The initial surveys were run close together to make sure the hole was not increasing inclination. Once the deviation tendency was established, the surveys were run further apart to save time. The deviation surveys run by HLH are as follows:

- .50 degree at 295 feet
- .25 degree at 439 feet
- 1.25 degrees at 931 feet
- 1.50 degrees at 1276 feet
- .50 degree at 1870 feet.

The drilling contractor met the minimum deviation requirements of less than 3 degrees maximum deviation and a maximum dogleg severity of 1 degree per 100 feet.

A significant gas and oil show calculated to be 1814 mcf/d was encountered at 1834 feet in the Big Lime interval. Shows of oil were found at 1900-1910 feet and 1940-1950 feet. Oil was estimated at 3 barrels of oil per day (also in the Big Lime section). If there were any gas shows in the Big Injun sand section (mostly a siltstone in this well), it was not detected because of the heavy gas from the Big Lime section. There were no other gas shows in the shallow vertical section of the wellbore.

6.3 Angle Building Drilling Operations

The inclination of the hole was built from vertical to 92 degrees in the section of the hole from 2113 feet to 4043 feet. The drilling plan had called for drilling this section of the hole with a 10-5/8-inch bit and running 8-5/8-inch casing all the way to bottom. Hole cleaning problems, which will be discussed later, caused the casing to be set earlier than anticipated. Also, the well was sidetracked twice in this section of the hole.

The directional program was changed to reflect the actual conditions at the well site. Based upon the logs and the actual kickoff point of 2113 feet, the rate of build was changed from 4.25 degrees per 100 feet to 4.48 degrees per 100 feet. (See Appendix A-1 for projected surveys.) The TVD to be horizontal was changed from 3420 feet to 3390 feet based upon the logs and the actual KB elevation. The target was defined as a TVD of 3390 feet $\pm$ 10 feet. The reason for being 90 degrees instead of 85 degrees was because of the potential of dropping inclination with the coring operations.

Directional drilling began using a Baker 7-3/4-inch motor, a 2.5 degree bent sub, and Geoscience's MWD system along with a conventional air drilling bit. Progress was slow at first because of problems associated with motor plugging and the MWD system. (See the Daily Log in Appendix B for more details.) The initial build rate averaged

4.75 degrees per 100 feet to 2800 feet. The dogleg severity averaged 5.25 degrees per 100 feet. After 2800 feet, the rate of build started to decrease from a dogleg severity of 5 degrees per 100 feet to a dogleg severity of 3.5 degrees per 100 feet at 3182 feet. (See surveys in Appendix A-2.) The inclination in the same interval changed from 35 to 48 degrees. Above 48 degrees, the build rate started to increase again. The motor failed to start after stopping to obtain the survey at 3246 feet. Since the inclination was beginning to lag the planned trajectory, a 3 degree bent sub was run with the next motor.

The 3 degree bent sub was run at a depth of 3309 feet. This assembly had an average dogleg severity of 7.4 degrees per 100 feet. After only two surveys with the 3 degree assembly and a projected inclination of greater than 68 degrees, the assembly was pulled out of the hole because the inclination was building too fast. The measured depth at this point was 3509 feet. The hole became tight while tripping out and reamers were run to ream the hole out.

The hole required reaming from 2230 feet to TD. While making the connection on bottom, the drill pipe became plugged and stuck. (Fishing operations are discussed later.) Attempts to fish the bottomhole assembly were unsuccessful and the well had to be sidetracked. The well was plugged back to 3175 feet with cement and the cement was dressed off to 3239 feet.

A 7-3/4-inch Baker motor with 2.5 degree bent sub was run to sidetrack out the right side of the hole. Because of problems associated with the steering tool and with getting the downhole motor oriented, the well dropped inclination and then did not build fast enough. The well had actually sidetracked while dressing off the cement plug because the inclination dropped from 51.6 to 48 degrees at 3240 feet. The cuttings were almost all shale when drilling with the downhole motor began. At 3421 feet, a 3 degree bent sub was run to build inclination faster. At this point the inclination would have to be built at about 7 degrees per 100 feet in order to be 90 degrees within the target TVD. The assembly built erratically ranging from 4.4 to 6.9 degrees per 100 feet. At 3666 feet, the target could not be hit without building over 10 degrees per

100 feet. Also, the areas of slow build rate were correlated to the brown shale zones. Since all brown shale would be drilled below 3666 feet, it was not likely that the inclination could be built faster than 10 degrees per 100 feet. The decision was made to plug back and sidetrack again.

The well was plugged back to 3330 feet with cement. The cement was dressed off to 3362 feet where the second sidetrack was initiated. In order to kick off on the high side of the hole, a strong building assembly was run. The assembly consisted of a 2 degree bent housing (6-3/4 inches OD) Baker motor and a 1.5 degree bent sub. The assembly had no problem sidetracking out the top side of the hole.

Directional drilling continued to 3827 feet when hole cleaning problems dictated running the 8-5/8-inch casing. Several days were spent trying to clean the 10-5/8-inch hole with as much as 4000 scfm of air and 30 bbls/hr of mist. During one of the reaming runs, a singleshot survey was run indicating that the inclination was 74 degrees rather than the 76 degrees the steering tool was reading. The survey at 3787 feet was changed to 74 degrees from 76.3 degrees to reflect the singleshot data.

A TV camera was run in the well as part of the logging operations. The camera fell to 3142 feet and stopped. The hole was very dirty with about 2 to 3 inches of balled-up cuttings accumulated on the low side of the wellbore as shown in Figure 6.3.1. The camera could not get through to the part of the hole where pipe movement was a problem. Dresser ran open hole logs on rollers to 3620 feet before the logs stopped. The caliper on the logs showed portions of the hole had very small diameters. The Dresser log also indicated the average hole diameter was 11.5 to 12 inches. The largest washouts occurred in the grey shales whereas the brown shale had very little washout. This is exactly opposite of what was anticipated.

A string of 8-5/8-inch, 24 and 32 pound per foot, K-55, ST&C casing was run and set at 3803 feet Kelly bushing (KB). The casing ran without incident to a depth of 3543 feet. At 3543 feet the casing stopped and had to be washed down several places thereafter. (See the Daily Log in Appendix B for further details.) The 32 pound per foot casing

Figure 6.3.1

Photo of 10-5/8" Hole From TV Camera

was run instead of the 28 pound per foot in the drilling plan because of a mix-up in the purchase order. The latter had not been ordered by the supplier and was replaced by the 32 pound per foot casing which had been special drifted to 7.875 inches. API drift is 7.796 inches. No problems were encountered in running tools through the heavy-walled casing.

The 8-5/8-inch casing was cemented in place with 150 sacks of Class A cement containing 10 percent salt. Displacement of the cement was seven barrels short of the calculated volume, and there was a possibility that the plug did not bump. The top of the casing could not be cemented as planned because the foam in the annulus (caused by having to wash the casing to bottom) would not let the cement fall in the 11-3/4-inch by 8-5/8-inch annulus. The annulus would have to be cemented after the foam broke and fell back.

The 8-5/8-inch casing was cut off and welded to the 11-3/4-inch casing. An orbit valve and rotating head were nipped up on the 8-5/8-inch casing. While blowing the water out of the casing, the weld broke loose between the 8-5/8-inch and 11-3/4-inch casing. The internal pressure, relieved by blowing out the water, caused the casing to grow in length, breaking the weld. The casing had only grown by 4 inches; however, this was enough to cause interference between the rotating head and the rotary table. The casing had to be cut off and the BOP stack nipped up again. By this time, the annulus started flowing water and gas. The 8-5/8-inch casing could not be completely welded to the 11-3/4-inch casing because of the hazard of welding around the gas.

The 8-5/8-inch casing was drilled out. The float collar and plug were encountered at the depth they should have been; therefore, the plug had bumped during displacement. There was no cement in the shoe joint. The guide shoe was drilled out and the open hole below the casing was filled with cement. Because of an error in the drill pipe tally, an extra 33 feet of hole was drilled to 3860 feet. The error made the difference between having to build 7.8 degrees per 100 feet and having to build 11.3 degrees per 100 feet to hit the specified target.

The 6-3/4-inch bent housing motors were used in the 7-7/8-inch hole. The next building assembly consisted of a Baker bent housing motor. The bend in the motor was set between 1-3/4 and 1-7/8 degrees. This

is the maximum bend that could be put into the 8-5/8-inch casing without having to push it with the drill collars. A 2 degree bend probably could have been run in the 8-5/8-inch casing, but was not required since the smaller bend built adequately.

The average dogleg severity for the bent housing motor was 10.1 degrees per 100 feet. At a measured depth of 4043 feet the extrapolated inclination was 92 degrees. The angle build portion of the hole was complete. The actual survey at 4043 feet (obtained from the multishot while coring) was 92 degrees. The true vertical depth of the well at this point was 3402.5 feet, which is 2.5 feet below the specified target.

6.3.1 Bottomhole Assemblies

The bottomhole assemblies are tabularized in Appendixes C-1 and C-2. The bottomhole assemblies (BHAs) used in the vertical hole were slick assemblies. They did not contain any stabilizers. The only exception is the BHA used to ream the 17-1/2-inch hole prior to running the casing. This assembly was not used to drill.

The inclined (curving) section of the borehole was built with Baker slow speed, high torque downhole motors. Both 7-3/4-inch motors and 6-3/4-inch bent housing motors were used. The by-pass valve was blanked for use with air; otherwise, the motors were not modified for use in air drilling.

The well was kicked off using the 7-3/4-inch motor and a 2.5 degree bent sub. The average dogleg severity obtained with the 2.5 degree bent sub while drilling the 10-5/8-inch hole was 5.6 degrees per 100 feet. At first the inclination built faster than expected, but as inclination angle increased, the build rate slowed until the inclination reached 50 degrees. At this point, the rate of build started to increase again. A 3 degree bent sub was put in the hole at 3309 feet because the inclination was starting to get behind the planned program. The 3 degree bent sub built at an average of 7.36 degrees per 100 feet.

The expected dogleg severity for the 2.5 degree and 3 degree bent sub were 5.5 degrees per 100 feet and 7 degrees per 100 feet, respectively. The actuals were very close to the expected.

After the first sidetrack operation was performed at 3509 feet, the 2.5 degree and 3 degree bent subs did not perform as well. There were a lot of problems getting the motor oriented while sidetracking which caused a low dogleg severity with the 2.5 degree bent sub. Survey points closer together would show a much higher dogleg severity. The 3 degree bent sub run from 3421 feet to 3666 feet showed markedly different build rates ranging from 4.4 degrees to 6.9 degrees per 100 feet. At least the initial portion of the motor run can be correlated to the brown shale. The build rate in the brown shale was 4.4 degrees per 100 feet, and the build rate in the grey shale was over 6 degrees per 100 feet. However, the last surveyed interval between 3589 feet and 3615 feet showed a build rate of over 6 degrees per 100 feet and, when the logs were reviewed, was found to be in the brown shale.

The second sidetrack was accomplished with a 2 degree bent housing motor (6-3/4-inch OD) and a 1.5 degree bent sub. The 1.5 degree bent sub was selected because it made up with the same tool face as the motor. The align-a-sub had not arrived on location and could not be used. The 2 degree bent sub would have been used if the align-a-sub was available. A 2 degree bent housing in a 10-5/8-inch hole should yield an angle building rate of about 5.5 degrees per 100 feet. A 1.5 degree bent sub should yield 2.5 degrees per 100 feet. If the values are additive, the expected dogleg severity should be 8 degrees per 100 feet. Adding a float sub between the bit and motor decreases the expected rate of build, because the bend is moved farther away from the bit. Therefore, the rate of build should be slightly less than 8 degrees per 100 feet. The actual dogleg severity was 7.72 degrees per 100 feet for the first motor run. The dogleg severity for the second motor run was 4.25 degrees per 100 feet. The survey at 3787 feet was adjusted to reflect the singleshot data which reduced the dogleg severity. Also, the align-a-sub was added to this assembly; moving the bent sub farther away from the bit causing a lower angle building tendency. At 3827 feet (74 degree inclination), the hole was reamed and the 8-5/8-inch hole protection casing set.

After the 8-5/8-inch casing was run, a 6-3/4-inch bent housing motor with a 1.8 degree (between the 1-7/8 degree and 1-3/4 degree

marks on the motors) bend of the housing was used. The expected dogleg severity in a 7-7/8-inch hole for the motors used are not published or available from the manufacturer. However, a 1.5 degree bent housing should yield a 5 degree per 100 foot dogleg in an 8-3/4-inch hole. Extrapolating, a 1.8 degree bent housing should yield about 7 degrees per 100 feet. Reducing the hole size makes a significant difference in the expected dogleg severity and should add at least 1 or 2 more degrees. The actual dogleg severity for the last two motor runs was 9.8 degrees per 100 feet. This value could be close to the expected value.

A total of 14 motor runs were made using 11 downhole motors (see Appendix C-3 and C-4). The average footage drilled per motor run was 176 feet in 7.8 drilling hours. The average footage drilled per motor was 223 feet in 9.93 drilling hours. Seven 7-3/4-inch and four 6-3/4-inch motors were used. Time spent restarting the motors averaged 2.71 hours per run and 3.45 hours per motor. This is the time it took to restart the motor after it stalled or after a connection. The motor stalled only a few times while drilling. Most of the problems associated with restarting the motors occurred after a connection. The eventual procedure that worked best for restarting the motors was to pump a few barrels of water (containing mist chemicals) down the drill pipe prior to turning air into the drill pipe. This restarting procedure increased motor life by 1.5 to 2 times. Eventually, this method failed to restart the motors.

Attempts were made to determine the cause of the poor motor performance. The air rate was varied between 2000 and 3000 scfm, the mist rate was varied between 5 and 35 barrels per hour, and each chemical in the mist except soap and polymer was dropped out of the mist one at a time. Nothing seemed to have any effect on the motor performance. One interesting thing to note is that the motor would often restart after no fluid went through the motor for more than two hours. Several times after working on the steering tool, the motor would restart with no

difficulty. The downtime was generally two to three hours with no fluid being pumped through the motor. The evidence indicates that the mist somehow caused the motor problem, perhaps by swelling the rubber in the motor. After a period of time the swelling went down and the motor restarted.

The same thing could happen if the motor got hot. However, the bottomhole temperature never exceeded 120° F. If the motor heated up due to rotation, then it should have cooled down in a short period of time. Also, in attempts to get the motor running, air and mist were pumped through the motor for up to one hour in hopes the motor would restart. The motor was not rotating during this period of time because the stand pipe pressure was between 400 and 500 psi. When the motor ran, the stand pipe pressure was always between 150 and 300 psi depending upon the air rate and the bit torque. Since the motor was not rotating, the fluid and air should have quickly cooled the rubber and the motor should have started. However, it did not start.

When the motors were sent back to Baker for repairs, no mechanical damage was found. No explanation was found for the stalling and restarting problems of the motors.

6.3.2 MWD and Steering Tool

The Geoscience Electronic's measurement while drilling (MWD) unit was the first tool used to steer the downhole motors. It was run in the hole on motor runs number 1 and 2. The unit sent the survey information to the service as electromagnetic radiation. The radiation was picked up by antennas and transmitted by wire to a central computer. The computer decoded the signals and printed the data. While air was not being circulated down the hole, the MWD unit could transmit and receive information from the subsurface but it could not receive down-linking commands when air was being circulated. This turned out to be a significant problem because the tool was set up to automatically send survey information to the surface every 15 minutes, which it did.

Unfortunately, tool face data was also received only once every 15 minutes, which was not frequently enough. Tool face information was needed once every two or three minutes.

If the electromagnetic MWD unit had been able to receive commands from the surface with the air circulating in the hole, then tool face data could have been sent more often. The only tool face data obtained by this method involved pulling the motor off bottom and turning off the air. Essentially this is the same method as using a singleshot to orient the downhole motor, only faster. The reactive torque of the motor on the bottom of the hole is not known and must be guessed, therefore the accuracy of the data is in question. As discussed previously, the motors were hard to restart after a connection or taking a survey, causing shorter motor runs. After the second motor run it became obvious that the MWD unit was not going to be able to supply the data required to accurately drill the well.

The first MWD probe failed at the end of the first motor run after only four hours of drilling time. The motor was shut down to take a survey and get a tool face orientation. After the information was obtained, the motor would not restart. The stand pipe pressure went up to 500 psi and failed the MWD probe. Pressure had gotten inside the pressure barrel causing the electronics to fail. Geoscience Electronics had left off the secondary o-ring seals because they thought they weren't necessary at the pressures expected during drilling operations.

The second motor run was terminated when the MWD unit quit working after drilling and surveying for four hours. The electronics package had failed. The motor was tripped out and the electronics package replaced with the last backup package. The motor drilled another 10 feet, when it became plugged after the air was shut off to get a tool face reading. At this time the MWD unit was laid down because it could not give the necessary information to accurately drill the well and was causing the associated operating problems.

Geoscience informed BDM that the tool can be reprogrammed to give tool face data automatically every minute, but it would take about one week in the lab to reprogram. If that is the case, the tool can be used as a steering tool. However, the reliability of the tool has not been proven and it may have to be hardened further to work in an air drilling environment. The maximum flow rate through the electromagnetic MWD unit was 2100 scfm with 10 bbls of mist fluid per hour. More frequent failures would be anticipated at higher flow rates as experienced with Scientific Drilling's tool.

Scientific Drilling, Incorporated's (SDI) steering tool was used from 2277 feet to the completed angle build point at 4043 feet. The steering tool operated very well at air rates of 2100 scfm, but experienced failures at air rates above 2100 scfm. The intention was to change to a different steering tool manufactured by Sharewell after obtaining an inclination of 65 degrees. Scientific's tool does not give accurate inclination and direction data above 65 degrees; however, it does give accurate tool face data.

The Sharewell tool was run at the beginning of the first sidetrack. The first tool lasted two hours, and the second tool lasted three hours. The air rate was 2100 scfm while running the Sharewell tool. Prior to running the Sharewell tool, Scientific's tool had not experienced a failure, although two failures were experienced in the wireline. The wireline had kinked twice at the side entry sub during attempts to restart the motor and when working the pipe in tight hole.

The Scientific tool was used to 90 degrees and singleshot surveys were run with the steering tool to monitor inclination and direction. All work with the steering tool employed the use of a side entry sub which saved considerable time when making connections. The biggest problem with the side entry sub was kinking the wireline, which was to be expected. The wireline had kinked three times while drilling with the downhole motors. Two of the three times, the kink was caused by working the pipe up and down to restart a motor or to work tight hole.

From then on, the pipe was not worked up and down to restart a motor and the air was put back on the hole to pull the drill string out of tight hole.

The steering tool would not fall past about 3900 feet, which was about 75 degrees. An unsuccessful attempt was made to pump the steering tool down. Beyond this point in drilling operations, the steering tool was seated at about 3800 feet and then tripped to bottom with the drill string. It took a little more time but was the only way to operate without an MWD unit.

The steering tool experienced only one failure at an air rate of 2100 scfm. At an air rate of 3100 scfm, four failures occurred. The 3100 scfm was required to clean the hole at inclinations above 60 degrees but the steering tool would not run. After the inclination reached 80 degrees, only one probe failure occurred. There were a total of four wireline failures in the steering tool head and kinked wireline.

6.3.3 Hole Cleaning

As expected, hole cleaning was one of the major problems in drilling the well. The intent was to start out at a minimum air rate of about 2100 scfm with as little mist as possible. The minimum rate the mist pump would pump was a little less than 10 barrels per hour. The first two motor runs ended with the bit plugged with cuttings even though there was a float immediately above the motor. A float left by the hammer drill company was used on top of the bit in conjunction with the motor. The float would sit on top of the pin similar to a baffle plate and did not require a sub.

At the end of motor run number six (3309 feet), a problem was experienced in pulling the drill string out of the hole. The hole was tight after pulling one stand (60 feet). The air was circulated for 1-1/2 hours to clean the hole. The inclination at 3300 feet was 54 degrees. On the next motor run, there were a lot of problems getting

out of the hole at 3509 feet. The inclination was 65 degrees. The hole could not be circulated clean, but the pipe could be pulled out of the hole with little or no drag as long as the air was circulating. The air stream made a fluidized bed of the agglomerated cuttings and allowed the drill string to move freely.

At 3509 feet, a reaming run was made to clean the hole out. The reaming assembly became stuck during a connection at 3509 feet. While making a connection, the pipe became plugged and would not come out of the hole. The bit float had worn out on the previous motor run and was not on the bit allowing the drill string to become plugged. It was not known at this time, but the inclination between 60 degrees and 70 degrees is where the majority of the hole cleaning problems were encountered. The air rate was 3150 scfm while reaming near the bottom. No mist was being pumped while reaming.

The well was plugged back to 3200 feet in order to sidetrack the fish. The cement was drilled out with 2100 scfm and 20 barrels per hour mist. Then the well was sidetracked with the same air and mist rate. There was no problem getting out of the hole. The inclination was around 47 degrees.

At 3300 feet the air rate was increased to 3150 scfm with 20 barrels per hour mist. The higher air rate contributed to four steering tool and wireline failures in the next 100 feet. The air rate was reduced to 2100 scfm at 3421 feet because only one probe was still functioning. If it failed, downtime would be experienced waiting on another probe. There was no problem tripping out of the hole at this depth but the motor had to be washed back in the hole indicating that hole cleaning was not adequate. The inclination at this point was about 57 degrees. Drilling continued with 2100 scfm to 3666 feet. The drill pipe had to be pumped out of the hole on the trip at 3666 feet. The inclination was a little over 60 degrees at this point. A reaming run was made to clean the hole out. After reaming the hole and circulating for 1-1/2 hours with 3150 scfm and 20 to 25 barrels per hour mist, the drill string still had to be pumped out of the hole.

The well was again plugged back because the inclination wasn't building fast enough. The well was sidetracked and drilled to 3827 feet. An air rate of 2100 scfm was used to drill from 3360 to 3700 feet because of the problems with the steering tool. On the trip out of the hole at 3634 feet, there was a little drag and there was 60 feet of fill on bottom on the trip in. At 3700 feet, the air rate was increased to 3150 scfm. On the trip out of the hole at 3827 feet, the pipe had to be pumped out of the hole. The inclination at 3800 feet was 74 degrees.

A reaming assembly was run in the hole to clean it out while running 4200 scfm with 30 barrels per hour mist. Even after circulating and working the pipe for two hours, the pipe still had to be pumped out of the hole. The mist came out of the hole clean and white.

A TV camera was run in the well and made it to 3148 feet, which was about 47 degrees. There were two to three inches of balled-up cuttings on the low side of the borehole even after circulating with over 4000 scfm. Figure 6.3.2 is a picture of what the hole looked like with the TV camera. Because of the hole cleaning problem, the decision was made to run the 8-5/8-inch casing. Two more days were spent trying to clean the hole and the casing still had to be circulated into the hole.

Drilling continued in the 7-7/8-inch hole. The 8-5/8-inch casing was drilled out with 2100 scfm and 10 barrels per hour mist. The slick assembly still experienced problems being pulled out of the hole. The cuttings were falling to about 3700 feet inside the casing. The inclination at 3700 feet was about 70 degrees.

From then on the motors were run with 3150 scfm and 25 barrels per hour mist. The pipe still had to be pumped out of the hole inside the casing at 3600 to 3700 feet. The 7-7/8-inch hole could not be completely cleaned with mist.

After the coring operations were concluded at 4156 feet, the well was dried up and dusted to TD. An air rate of 3150 scfm was run and no further problems with hole cleaning were encountered. Figure 6.3.3 is a picture of what the dusted hole looked like.

Figure 6.3.2

**PHOTOGRAPH OF 10-5/8" HOLE WITH MUD BALLS
ON BOTTOM OF HOLE BLOCKING CAMERA**

FIGURE 6.3.3
PHOTOGRAPH OF 7-7/8" HOLE DRILLED ON AIR.
NOTE CLEANNESS OF HOLE

The hole could not be effectively cleaned with mist, but could be cleaned with air. Mist has a greater carrying capacity than air and should have cleaned the hole better. Even pipe rotation with mist did not clean the hole. Drilling Resources Development Corporation, using a computer program just developed for analyzing air requirements, analyzed our data and projected that a higher injection rate of 30 barrels per hour should have wet the cuttings more effectively, thus preventing the agglomeration and fluidized bed problems that were experienced.

6.3.4 Fishing

There was one fishing job during the drilling of RET #1. After directional drilling to 3509 feet, the assembly became difficult to pull out of the hole. A reaming assembly was run to ream and clean the hole out. The assembly consisted of a bottomhole three point reamer, two 8-inch monels, a three point reamer, and two 6-1/4-inch drill collars. The intention was to drill ahead with this assembly after reaming. The inclination in the well was ahead of schedule; therefore, some hole could be drilled with the rotary building assembly.

The hole was reamed from 2230 feet to 3509 feet with 2100 to 3150 scfm of air. No mist was used since the intention was to dry up the hole and drill ahead with the BHA. On the connection at 3509 feet, the drill string stuck and the pipe became plugged. A small float valve that sat on top of the bit like a baffle plate (no float sub was needed) was not immediately above the bit. On the previous bit run, the float had worn out and no longer functioned. Cuttings had fallen back down around the drill string and in the bit. Without circulation, the drill string could not be freed.

Initially, the pipe could be moved up and down with two feet of free movement and could be rotated in that interval. As much as 230,000 pounds was pulled on the pipe but no progress was made. After four hours of working the pipe, there was no longer any free movement and the pipe could not be rotated.

A freepoint was run and the drill string was found to be free at least to the top of the upper three point reamer. The free-

point tool would not fall any further in the hole than 10 feet into the monels. The pipe was backed off at the top of the 6-1/4-inch drill collars so that the collars would be laying on the low side of the hole, making it easier to screw back into the collars with a jarring assembly.

A jarring assembly was run in the hole and the fish screwed into with no problem. The jars hit twice and failed. While trying to get the jars working, the screw-in sub pulled out of the fish. The fishing assembly was pulled out of the hole to pick up a new set of jars. The second set of jars was run and screwed into the fish. The fish was jarred with as much as 200,000 pounds (130,000 pounds over string weight). After eight hours of jarring, the jars failed and the fish had only moved two feet with no progress in the last three hours. It was not likely the fish could be jarred out of the hole.

The options considered were to wash over the fish, clean out the inside of the fish to try and circulate, or sidetrack the well. Washing over the fish at that inclination would have been very difficult and the odds of leaving some wash pipe in the hole were good. The fish could only be cleaned out to the top of the bottomhole three point and would probably not be successful. The sidetrack option was chosen.

6.4 Horizontal Drilling Operations

The last motor run was finished at 4043 feet with an inclination of 92 degrees. The wellbore had reached 90 degrees at 4020 feet. The well was cored and drilled to 4156 feet using mist and 2100 scfm of air.

After coring operations were complete, the wellbore was dried up and the rest of the well was dusted with no further problems associated with hole cleaning. The assembly run was a bit, float sub, bottomhole three point reamer and two 6-1/4-inch monel drill collars with a monel crossover sub in between the monels. The assembly turned out to be perfect for the drilling of the horizontal section of the hole. It dropped inclination at an average rate of 1/4 degree per 100 feet and walked to the right at 1/2 degree per 100 feet. The final TVD reached was 3427 feet, which was 25 feet from the bottom of the Lower Huron shale. A

little more dropping tendency (an additional 0.1 degree per 100 feet) could have dropped the wellbore to the bottom of the Lower Huron. Considering the ability to control BHA's, the assembly did an excellent job. From the plots of the vertical and plan view (Figures 6.4.1 and 6.4.2), the wellbore course was on target better than could be expected considering no motor corrections were made.

The weight of the BHA was adjusted from 25,000 to 15,000 pounds in an attempt to make the assembly drop a little faster; however, bit weight had no effect on the dropping tendency of the assembly. Subsequently, the bit weight was maintained at 20,000 pounds with a penetration rate of 25 feet per hour including connections.

The bottomhole assembly analysis program had also indicated that weight would have no effect on the inclination tendency. The program gave a bit side force of 1584 pounds build and a bit tilt of 0.08 degree up. Both indicate the assembly should have built inclination when in fact it dropped inclination. Therefore, the formation had a drop tendency equivalent to the building tendency of the assembly plus about 0.3 degree per 100 feet. The computer printout of the analysis is in Appendix C-5.

After reaching a TD of 6020 feet, open hole logs and a TV camera were run in the hole on drill pipe. Though operations were slow, there were no problems encountered (see logging detail).

The 4-1/2-inch casing was run to total depth without any problem. A total of 14 port collars, eight external casing packers, and one cement packer were run on the 4.5-inch casing. The placement of the packers and port collars can be seen on the tally sheet in Appendix D. One centralizer was placed immediately above and below each external casing packer to prevent damage while being run in the hole.

The Baker external casing packers (Lynes model "RTS") will be used to isolate the individual producing zones. The cement packer (manufactured by Completion Tool Company) is a backup to the Baker packers and is inflated with cement. The port collars (Halliburton F O Cementers) are located between the packers and will be used to selectively produce and stimulate the individual producing zones.

Vertical View

Figure 6.4.1

Plan View

Figure 6.4.2

Surveying was one of the most time-consuming aspects of drilling the 7-7/8-inch hole. A total of 39 hours were spent obtaining six surveys. Fortunately, the inclination and direction were not changing fast and the surveys could be spread out once confidence had been gained. Initially, the surveys were taken in 90-foot intervals and then extended to 300 feet. The last survey was at 5599 feet. The survey at 6020 is an extrapolated value.

A single conductor wireline attached to the singleshot instrument was used to survey through the side entry sub. The survey instrument would only fall to about 3800 feet under the influence of gravity. The wireline was used because of the accurate weight indicator and hydraulic hoist.

An attempt was made to pump the singleshot down while drilling at 4221 feet. The singleshot would fall to 4000 feet while pumping 3150 scfm down the drill pipe. By shaking the drill pipe, the singleshot would fall to the top of the collars but would not go in.

Therefore, a side entry sub had to be used to survey. The survey tool was placed in the monel drill collars at about 3700 feet and tripped the rest of the way in the hole with the drill pipe. After the timer went off, the pipe was pulled out of the hole to the side entry sub, and the survey instrument was removed. The last survey at 5628 feet took seven hours to complete. The 2000 feet of wireline above the side entry sub was too heavy to hold and almost always kinked. The kinked line was reused as much as possible because the electrical connection was not destroyed.

The use of an MWD tool would make surveying much easier in the horizontal portion of the hole. If the reaction of the BHA had not been so predictable, surveying would have had to be much more frequent. Over half the time spent in the horizontal hole would have been spent surveying. Surveying every 100 feet would have taken four hours of drilling and six hours of surveying.

6.4.1 Hole Drag

The most significant problem in the horizontal section of the hole was hole drag. Hole drag did not become a problem until the depth of 5400 feet. The problem occurred when running the pipe back in the hole after a connection. All the weight could be slacked off and the pipe would not go down but could be pulled up and rotated easily. To solve the problem, six 6-1/4-inch drill collars were placed in the vertical hole at 1500 feet on the next bit trip.

The excess down drag was not caused by poor hole cleaning because circulating and reaming made little difference. The collars in the vertical portion of the hole allowed the drill string to be lowered in the hole until the connection at 5693 feet, when the pipe would no longer fall in the hole. If the pipe was slowly lowered in the hole, it would stop with all the weight stacked out. In order to make the pipe go in the hole, it had to be run quickly. Once the entire string was moving, it would continue to slide down the hole.

All the data indicates that an initial coefficient of static friction had to be overcome before the pipe would start moving. Once the pipe was moving, then only the lower coefficient of kinetic friction had to be exceeded. By using the momentum of the drill pipe (dropping the drill string from maximum hook load), the higher friction coefficient could be overcome.

Below 5400 feet, the variables for drill string drag going down had to have changed. As can be seen in Table 6.4.1, the coefficient of kinetic friction while lowering the drill string changed significantly while the hoisting and rotating coefficient changed very little. Drilling Resources Development's computer model was used to calculate the coefficient of friction. The friction coefficient was varied until the drag value equaled the drag measured in the field.

When the bottomhole assembly was left out of the drill string while running logs, there was no problem getting the drill pipe in and out of the hole. The excessive down drag in the bottom of the

hole had something to do with the BHA. The excessive drag could have been caused by drill pipe buckling while lowering. Buckling may have caused the drill pipe to bind in the hole. Without the bottom two drill collars, the pipe may not have buckled; therefore, the drag was reduced. This is speculation only, and not based upon any calculations. The DRD computer model does not take buckling into account. There is no reason for the down drag coefficient to have changed drastically.

TABLE 6.4.1
CALCULATED COEFFICIENT OF FRICTION FOR DRILLING OPERATIONS

<u>MEASURED DEPTH</u>	<u>ROTATING COEFFICIENT</u>	<u>LOWERING COEFFICIENT</u>	<u>HOISTING COEFFICIENT</u>
2595	motor	0.45	0.60
3309	motor	0.30	0.30
3803	8-5/8-inch csg	0.50	0.50
3509	0.30	0.40	0.60
3827	motor	0.15	0.35
3997	motor	0.10	0.20
4412	0.35	0.10	0.45
4854	0.35	0.25	0.50
5077	0.40	0.25	0.40
5569	0.35	0.55	0.50
5693	0.35	0.55	0.50
6020	0.35	0.60	0.45
6020	4.5-inch csg	0.15	0.15

The computer modeling done prior to drilling the well gave similar results. For the expected coefficient of friction of 0.45, the program indicated that there would be some trouble getting the drill pipe in the hole, but there would be no real problem hoisting or rotating the pipe.

6.4.2 Coring

The 7-7/8-inch hole was cored after building to an inclination of 92 degrees. The first core was taken from 4043 feet to 4057 feet. Coring operations stopped after 14 feet and it appeared that the core barrel was jammed. When the core barrel was pulled it was discovered that the barrel was half full of cuttings. To alleviate the problem on the next core run, the ball that prevents circulation through the core barrel was removed. When the core barrel was washed to bottom, the cuttings were flushed from the inner barrel.

The second core run was made from 4057 feet to 4086 feet with no problems. The third core was taken from 4126 feet to 4156 feet with no problems. Core recovery for runs 2 and 3 was 100 percent.

A standard 30-foot, 6-1/4-inch diameter core barrel modified with an inner tube stabilizer in the center was used to core the well. The core bit was a 7-7/8-inch by 4-inch compact bit (RC-444). An aluminum inner barrel cut in 15-foot lengths was used because of the center stabilizer. All the cores were oriented so the direction of the natural fractures could be determined.

When the first core barrel came to the surface, the two 15-foot sections of aluminum inner barrel were removed and inspected, and the cuttings filling the second 15-foot section were discovered.

The shale cored was dark gray (N₃ on GSA color chart) with practically no significant color or textural variations along its length. The core was in excellent condition and was very hard. It did not break easily even when struck by a hammer and a cold steel chisel. Pyrite is common and was found scattered throughout the core length.

Fossil kelp and algae Tasmanites were noted in the core. Some of the pyrite noted in the core appeared to be replacement of fossil material.

Of the 113 fractures and faults observed in the core, fifteen were natural extension joints with a mean orientation of N37°E, 87°NW. The frequency of jointing (spacing) in the first 44 feet of core was irregular, but had a mean spacing of 6.2 feet. Spacing between

fractures in the second core was 12 feet. However, the second fracture was actually a fracture zone consisting of six joints and six faults (see interval 4139 to 4142 feet in Table 6.4.2).

TABLE 6.4.2 -- CORE FRACTURES

DEPTH	SPACING BETWEEN FRACTURES	FRACTURE TYPE	ORIENTATION	DIP
1. 4045.7	17'	JOINT	S39°E	80°NW
2. 4062.3	5'	JOINT	N38°E	78°NW
3. 4067.8	4'	JOINT	N38°E	84°NW
4. 4071.0	4'	JOINT	N38°E	78°NW
5. 4075.7	1'	JOINT	N38°E	78°NW
6. 4076.2		JOINT	N37°E	77°NW
First 44' of core S39°E 92° inclination.				
7. 4128.1	12'	JOINT	N40°E	77°SE
8. 4139.9	0.2'	JOINT	N39°E	VERTICAL
9. 4140.1	0.4'	JOINT	N40°E	85°SE
10. 4140.4	0.4'	JOINT	N38°E	85°SE
11. 4140.8	0.4'	FAULT (normal)	N22°E	60°NW
12. 4141.08	0.4'	JOINT	N34°E	85°NW
13. 4141.4		FAULT	N17°E	54°NW
14. 4141.10	0.02'	FAULT	N17°E	54°NW
15. 4141.12	0.08'	FAULT	N17°E	54°NW
16. 4141.2	0.6'	FAULT (normal)	N32°E	42°NW
17. 4141.8	0.1'	FAULT (reverse)	N32°E	76°NW
18. 4141.9	0.1'	JOINT	N31°E	77°NW
19. 4142.0		JOINT	N31°E	78°NW

The frequency of fracturing in the fracture zone (4139.9 to 4142) is 0.2 foot (see Figure 6.4.3). The faults were mostly normal faults with a mean orientation of N22°E dipping 56°NW (see Figure 6.4.5). The core also contained a total of 59 sub-vertical irregular fractures which are interpreted to be coring induced fractures which should be oriented by the in-situ stress field. As shown on Figure 6.0.2, the

DIAGRAM OF FRACTURES IN CORE RUN #3

Figure 6.4.3

Rose Diagram of Core Fractures

Figure 6.4.4

induced fractures have a mean orientation of N52°E. This is the direction in which hydraulic fractures induced from the horizontal well will be oriented. BDM also projects the possibility of inflating the natural joint set and possibly the faults from the wellbore because the di-hedral angle measured between the induced fractures and the faults is 30 degrees and less than the average shear fracture di-hedral angle of 32 degrees. A complete report detailing the fractographic analysis of the core material prepared by Kulander and Dean is found in Appendix E.

Analysis of the core fracture orientation with respect to the orientation of fractures from other cores taken within 50 miles of the location shows good correspondence with the identified regional systematic fracture (joint) trends. The orientation of the wellbore along a S37°E trajectory was in a direction nearly orthogonal to the principal horizontal stress orientation in the area.

6.4.3 Logging

During drilling operations, the drilling fluid (air or air/mist) was continuously monitored by a gas chromatograph system operated by Hydrocarbon Mud Logging, Inc. Hydrocarbon operators also collected, examined, described, and prepared a log of the samples recovered from the well on a 10 foot per sample basis. Sample logging began at 700 feet after the shallow water protection string had been set at 650 feet. The log was available for examination as a completed product (prepared by a computer printer) every day and was very useful in making decisions about drilling operations.

Perhaps the most useful aspect of the "mud logging" operations was the gas shows detected by the chromatographic unit. Table 6.4.3 lists the depth at which a gas show was recorded, the percent of the air stream in parts per million (ppm) detected, and the calculated rate of flow of gas detected. Figure 6.4.5 is a schematic diagram showing the relative position of gas shows encountered in the horizontal section of the wellbore. Figure 6.4.6 illustrates the relative magnitude of flow rates encountered at 200-foot intervals along the wellbore.

The high flow rates found between 5000 and 5200 feet along the wellbore are obviously associated with a highly fractured zone in the Devonian shale section.

TABLE 6.4.3 -- COMPILATION OF MUD LOGGER GAS SHOWS

DEPTH OF SHOW (ft)	GAS DETECTED (ppm)	CALCULATED ¹ RATE (mcfpd)	DEPTH OF SHOW (ft)	GAS DETECTED (ppm)	CALCULATED ¹ RATE (mcfpd)
1835	10,000	30	4882	7,500	34
1844	600,000	1,814	4896	1,000	4
2507	5,000	15	4908	1,000	4
2516	4,000	12	4923	6,200	28
2583	8,500	25	4932	8,600	39
2600	5,000	15	4960	8,400	38
3092	6,500	19	4970	9,700	44
3152	5,000	15	4976	15,000	68
3219	36,000	108	5032	5,000	22*
3422	3,500	10	5036	5,000	22*
3506	4,000	12	5046	478,000	2,168*
3586 ²	34,000	102	5056	151,000	684*
3598	74,000	223	5068	142,000	644*
3896	65,000	196	5090	110,000	499*
3972	3,500	10	5096	139,000	630*
4056	6,500	20	5118	131,000	594*
4140	77,000	233	5218	48,000	217
4430	6,500	29	5320	50,000	226
4452	3,500	16	5450	23,000	104
4480	5,000	22	5514	42,000	190
4666	2,000	9	5842	6,000	27
4690	3,000	13	5858	7,000	31
4728	4,000	18	5878	12,000	54
4738	4,000	18			

¹ (ppm gas vol. % of air stream) x (cubic feet per min. of air**) x 60 min/hr x 24 hr/day = cubic feet of gas per day.
(** air rate was either 2100 or 3150 cubic feet per minute)

² Sidetrack #2

* Total for high fracture density zone = 5,263.

FIGURE 6.4.5

Figure 6.4.6

Spacing between the gas shows in the interval was 10.75 feet as shown in Table 6.4.4 below.

TABLE 6.4.4

SPACING BETWEEN MUD LOGGER GAS SHOWS
FOR INTERVAL 5,000 TO 5,200 FEET
(ECP ISOLATION ZONE 4)

<u>MUD LOGGER GAS SHOWS</u>	<u>SPACING BETWEEN SHOWS</u>
5032'	
5036'	4'
5046'	10'
5056'	10'
5068'	12'
5090'	22'
5096'	6'
5118'	22'

MEAN SPACING BETWEEN MUD LOGGER SHOWS = 10.75'.

After a total depth of 6020 feet was reached, the hole was blown for an additional hour to remove cuttings and clean up the wellbore for logging operations. The 7-7/8-inch hole was logged with an open hole logging suite and a downhole television camera. Dresser Atlas used a drill pipe conveyed logging system to log the hole in two logging runs. Strata Vision utilized the same hardware system to run their video log of the open hole.

The drill pipe conveyed system utilizes the drill pipe to transport the logs to the bottom of the hole because they will not fall under the influence of gravity. The logging tools are encased in a housing which attaches to the bottom of the drill pipe. The logs and drill pipe are then tripped into the hole to a point where the wireline is attached using a wet connect (see Figure 6.4.7). In the RET #1 well, the side entry sub was installed after the logging tools had reached 3200 feet where the hole inclination is 48 degrees. The rope socket is lowered into the drill pipe through the side entry sub and is latched onto the logging sondes. The connection is called a wet connect. Once electrical communication is established with the logging tools, the drill

DOE/BDM R.E.T. #1

Figure 6.4.7

pipe is tripped all the way in the hole as shown in Figure 6.4.8. The well is then logged while pulling the drill string out of the hole (temperature was logged going in the hole). When the logging has been completed, the wireline is pulled out of the rope socket and pulled from the hole. The drill pipe is tripped out and the logging sondes removed.

The first logging run was a Gamma Ray, Density, Caliper and Dual Induction suite. The Density and Caliper tools did not work properly because the pad was located on the low side of the hole and did not position the tool to contact the hole properly. After logging to 4137 feet, the wet connect pulled loose from the logging tools (which it is not supposed to do). Dresser speculated that there was some scale from the pipe in the wet connect causing it not to seat properly. The wet connect was made again and the logging run completed.

The second logging run was with a Temperature and Gamma Ray tool. The temperature was logged while tripping in the hole. The Gamma Ray tool (which was being run for correlation purposes) failed, so the 8-5/8-inch casing seat was used for depth correlation for the temperature tool.

On logging run 1, which began at 6008 feet, the density pad (not being fully deployed to contact the wellbore) gave no compensation curve presentation and erroneous density values. As shown on Figure 6.4.9, there were no responses on either the density curve or the induction resistivity curve which would indicate the fracture porosity, and thus production potential at the points indicated where gas production was encountered according to the mud logger.

The temperature curve presented in Figure 6.4.10 does indicate where production was coming into the wellbore. The differential temperature curve points out the total interval contributing to the production.

After the wet connect came loose, and then was re-established, the moving of the tools in and out changed the tool position and the density pad deployed enough to start generating a compensation curve. In Figure 6.4.11 the compensation and density curves indicate the presence of fractures (joints) in the same area where joints

DOE/BDM R.E.T. #1

Figure 6.4.8

Figure 6.4.9

Figure 6.4.10

Figure 6.4.11

were found in the cores in core runs 1 and 2. The tools were not functioning properly when core run 3 area was logged. In Figure 6.4.12, the temperature curve presentation shows that the fault zone had been completely depleted by the time the log was run.

From examination of the logs, there appears to be no relationship between lithology as indicated by the gamma ray curve and the occurrence of gas shows indicating fractures. The occurrence of fractures would seem to be related more to tectonic stress conditions than lithology. The temperature log should be the best log for detecting fractures and/or production in the horizontal wellbore of a Devonian shale well.

The TV camera logged going in the hole and proved to be very useful in identifying the fractures in the wellbore. This is the first time a TV camera had been run using the drill pipe conveyed logging method and it was very successful. The TV camera was invaluable in providing fracture identification and hole condition information.

Video log analysis of Zone 4 (4994 to 5170 feet) detected 50 features interpreted to be fractures. Six of those features contained stains indicating condensate bleeding into the wellbore at that point. In the interval 5042 to 5055 feet, a distance of 13 feet, fourteen fractures were detected giving an average spacing of 0.9 foot between fractures. This same zone also produced a gas show calculated to be 2168 mcf/d. Based on comparative examination of the same interval on the video log as that cored in core run 3 where the fracture spacing in a two-foot interval was 0.2 foot, it is likely that there are at least 65 fractures in this zone and only 20 percent (14) were detected by the video log.

The number of observed features interpreted to be natural fractures varied from a low of five for a 200-foot interval (4500 to 4700 feet) to a high of 50 (5100 to 5300 feet as shown in Figure 6.4.13). The frequency of fracture occurrence increased in the back section of the borehole from 5100 to 6020 feet. The spacing between fractures (see Figure 6.4.14) varied from a few inches to 70 feet. The mean spacing for fractures over the 2200-foot length surveyed was 8.8 feet. Mean spacing as indicated by the mud log record was 65 feet.

Table 6.4.12

**Observed Natural Fractures From Downhole Camera
Devonian Shale Horizontal Well -- Wayne Co., W.V.**

Figure 6.4.13

**Natural Fracture Spacing From Downhole Camera
Devonian Shale Horizontal Well -- Wayne Co., W.V.**

Figure 6.4.14

6.5 Casing

Six thousand thirteen (6013) feet of J55, 10.5 pounds per foot ST&C casing was installed in the wellbore. Included in the casing string were eight (8) external casing packers (ECPs), which were used to isolate zones with similar fracture or production characteristics for future stimulation operations. Also included was one cement packer placed near the center of the horizontal section to be used in the event the other packers did not function properly.

Prior to beginning casing operations, each piece of casing was measured and numbered so that the exact location of the packers and port collars could be determined. Fourteen full opening (FO) multiple stage cementer units were also installed in the casing. The FO cementers were used to serve as ports for access to the isolated zones primarily, and as ports for cementing to isolate if necessary. The casing tally and location of ECPs and ported (sliding sleeve cementers) collars is presented in Appendix D. Drag, hookload up, and hookload down are also presented in the table.

Conventional bow-spring centralizers were placed on either end of the ECPs to provide support and keep the rubber on the packers from being dislodged or torn while being run in the wellbore.

6.6 Road and Site Work

The drilling site actually constructed was slightly smaller than the planned size because of the rough terrain. The reserve pits had to be built in two sections because of the slope of the hill. The second section of the pit was built at an elevation approximately 20 feet below the upper reserve pit. Each section of the reserve pit was 10 x 30 x 8 feet deep. Fluid from the top pit spilled over into the lower pit. The water was pumped from the lower pit into the soap tanks for reuse.

Because of the heavy rains during the drilling of RET No. 1, the pits filled up. A lot of the drill site drained into the pits and

filled them. A third reserve pit had to be constructed on the east side of the location behind the compressors. Otherwise, the pits would have overflowed. All the reserve pits were lined with pit liners.

The rain also caused significant problems with the road to the location. Considerably more money had to be spent on the road than had been planned. For the last 20 days, the only way a truck with equipment could get into the location was to be pulled by a dozer. Initially, only the access road from the Tick Ridge road was causing problems. As the rain continued to keep the roads wet, the last two miles of the Tick Ridge road itself became impassable by the end of the well. Even four-wheel-drive vehicles could not get in or out. The road had to be repaired before the testing phase could be completed.

7.0 DISCUSSION

The strategy selected by BDM, which was to use downhole motors to build the entire inclined portion of the well, was obviously the correct one. The major problem overcome during this part of the drilling operation was hole cleaning. Motor starting was another problem which was later addressed by picking up a double stand (62 feet) with each connection. BDM tried unsuccessfully to determine the potential detrimental effects of various chemicals used in the mist fluid. Evaluation of BDM data by Drilling Resources Development Corporation indicates that a higher fluid injection rate of 15 to 20 barrels per hour should have been more successful in hole cleaning than the 10-12 barrel per hour rate used by BDM. This probably would have been more successful in wetting the cuttings and preventing agglomeration of the cuttings to form mud balls which could not be removed from the wellbore.

Testing of the electromagnetic measurement while drilling system (EM-MWD) to provide tool face orientation, wellbore inclination and trajectory azimuth was disappointing. The tool worked reasonably well but needs additional hardening and software configuration to obtain required data in a timely fashion. Future development of horizontal drilling as an efficient and economic method of producing petroleum and natural gas depends largely upon reducing the time required to make these measurements.

The use of 310 cfm of air for the circulating medium with the rotating bottomhole assembly was very effective in removing cuttings during drilling of the horizontal section of the hole. The use of an on-site computer to examine the drilling tendencies of several BHAs allowed BDM engineers to select the best assembly for the operation. The assembly selected worked so well that a motor run to correct for dropping angle or walking was not required.

There were no major difficulties encountered during coring operations. The modified core barrel worked very well, recovering 100 percent of the core cut on two of the three runs made. Examination of the core

material revealed the presence of 15 natural fractures, six faults, and 59 coring-induced fractures. The natural fractures had a mean orientation of N37°E, 87°NW, while the faults (normal) had a mean orientation of N22°E, 56°NW. Mean spacing between fractures was eight feet. Mean orientation of the coring-induced fractures was N52°E (Figure 6.1). This orientation is interpreted to be the direction of induced hydraulic fracturing and confirms the N53°E orientation postulated by this author. The S37°E planned trajectory is only one degree off from being exactly normal to the direction of induced fracturing. Surface joint studies, aerial photography, landsat imagery and core fracture data from wells nearby in Lincoln County, West Virginia, and Martin County, Kentucky, were studied to determine the orientation of the wellbore which would be optimum for hydraulic fracturing operations.

The 15 degree difference in orientation of the well developed natural fractures found in the oriented core with the interpreted principal horizontal stress orientation, should be ideal for the planned attempt to incorporate natural fractures in the hydraulic fracture stimulation operation. The author has postulated that in areas where tensile fracturing is dominant, natural fractures oriented within 22 degrees of the principal stress orientation can be inflated under the right circumstances and used to augment the fracturing process.

Chromatographic analysis of the air stream monitored while drilling the horizontal hole indicated 34 fractures were encountered which produced measurable volumes of natural gas. The largest of these had a calculated open flow of 2168 mcfd. Examination of the borehole with a video camera revealed circular and elliptical features which were interpreted to be fractures since many of them were bleeding gas and condensate into the wellbore. The presence of condensate indicates two-phase flow conditions may exist at different periods of time in the life of a well or field. Some Devonian shale producers have suspected this was the case, but lacked proof to explain oddities in production.

The well was cased with 4-1/2-inch J55, 10.5 pounds per foot casing equipped with eight external casing packers, one cement packer, and 14 full opening ported cementing collars. Presently the external casing packers have not been inflated to produce eight isolated zones for testing,

but will be inflated when the initial open flow testing has been completed. The well is currently producing 1299-btu gas at rates varying between 24 and 45 mcfpd depending upon orifice size and choke settings being tested. The well had a seven day shut-in pressure measurement of 135 psig. This is about one-half of the pressure predicted by mapping of seven day fieldwide shut-in pressure measurements. The low pressures encountered could be related to the presence of fluid (condensate) in the fractures and will increase with time as the fluid is removed, or a low pressure fracture system may have been encountered, which is storing gas during this whole well production test phase. Zone isolation testing will help to resolve some of these questions.

The use of an on-site computer with programs which could analyze bottomhole assemblies and rates of angle build, and determine true vertical depth was a factor which was extremely important to the successful completion of the well. The computer was also used to keep a daily log of operations (see Appendix D), and to keep a daily record of expenditures.

8.0 CONCLUSIONS

BDM successfully located, planned, and drilled a long radius turn horizontal well in the Devonian shale Lower Huron section in Wayne County, West Virginia, demonstrating that state-of-the-art technology is capable of drilling such wells.

BDM successfully tested drilling, coring, and logging in a horizontal well using air as the circulating medium (possibly the world's first); conducted reservoir modeling studies to protect flow rates and reserves in advance of drilling operations; observed two phase flow conditions in the wellbore not observed previously; cored a fracture zone which produced gas; observed that fractures in the core and the wellbore were not systematically spaced (varied from 5 to 68 feet in different parts of the wellbore); observed that highest gas show rates reported by the mud logger corresponded to zones with lowest fracture spacing (five feet) or high fracture frequency. Four and one-half inch casing was successfully installed in the borehole and was equipped to isolate the horizontal section into eight (8) zones for future testing and stimulation operations.

9.0 REFERENCES

1. Pasini, J.P. III and W.K. Overbey, Jr. Natural and Induced Fracture Systems and Their Application to Petroleum Production, Soc. of Pet. Eng., SPE 2565, Presented in Denver, Colorado, May, 1969.
2. Overbey, W.K., Jr. and W.M. Ryam. Drilling a Directionally Deviated Well to Stimulate Gas Production from a Marginal Reservoir in Southern West Virginia, ERDA Tech. Prog. Rpt., METC/TPR7613, July, 1976.
3. McManus, G. Report on Directionally Drilled Well - Consolidated Gas Supply Corporation Well #12501, Jackson County, WV, ERDA Internal Report.
4. Rodgers, J.A. Drilling of a Deviated Well - E.C. Newell 10056-D, Meigs County, OH. Report Submitted to DOE/METC by Gruy Petroleum Tehcnology, September 30, 1982.
5. Lee, K.D. Subsurface Structure of the Eastern Kentucky Gas Field: Morgantown, WV, West Virginia University, Department of Geology Masters Thesis, 1980.
6. Technically Recoverable Devonian Shale Gas in West Virginia, (Lewin and Associates, Inc.) 1984, (DOE/MC/19239-1750); Technically Recoverable Devonian Shale Gas in Ohio, 1983, (DOE/MC/19239-1525); Technically Recoverable Devonian Shale Gas in Kentucky, 1985 (DOE/MC/19239-1834).

10.0 APPENDICES

A-I	Planned Wellpath Trajectory and Survey Data
A-II	Survey Data to Point of Sidetrack No. 1
A-III	Survey Data to Point of Sidetrack No. 2
A-IV	Final Survey Data for Completed Well
B	Daily Log of Operations on Location
C-I	Bottomhole Assemblies Utilized in Drilling RET #1 Well
C-II	Analysis of Bottomhole Assemblies used for Inclined Hole Drilling Operations
C-III	Downhole Motor Angle Building Performance Data
C-IV	Downhole Motor Drilling Performance Data
C-V	Analysis of Bottomhole Assembly used for Horizontal Drilling Operations
D	Casing Tally, ECP and Port Collar Location, Hookload and Drag Data
E	Core Fractographic Analysis and Discussion of Tectonic Setting
F	Daily Report on Well Drilling Operations

APPENDIX A-I
PLANNED WELLPATH TRAJECTORY AND SURVEY DATA

WELLPLAN (Version 3.0)

Drilling Resources Development Corporation

Operator : BDM

Contractor : HLH DRILLING

Lease : ENEGER/CABOT

Field : WILSONDALE

Well Name : BDM/DOE ENEGER RET#1

Analyst : RSC

Date : 11-6-86

ANALYSIS : 3 - BDM/DOE ENEGER RET#1 PLAN

SUBMODULE : 1 - Radius of Curvature Method

UNITS : ENGLISH

PROPOSED TARGET INFORMATION OUTPUT

PROPOSED DIRECTION S 37.00 E

SURVEY STATION PARAMETERS OUTPUT

NO.	M.D. (FT)	INC. (DEG)	DIRECTION			<----- LOCATION (FT) ----->		TVD
			N/S	AZM (DEG)	E/W	+N / -S	+E / -W	
1	.00	.00	S	37.00	E	.0	.0	.0
2	2113.00	.00	S	37.00	E	.0	.0	2113.0
3	2213.00	4.48	S	37.00	E	-3.1	2.4	2212.9
4	2313.00	8.96	S	37.00	E	-12.5	9.4	2312.2
5	2413.00	13.44	S	37.00	E	-28.0	21.1	2410.3
6	2513.00	17.92	S	37.00	E	-49.6	37.3	2506.5
7	2613.00	22.40	S	37.00	E	-77.1	58.1	2600.4
8	2713.00	26.88	S	37.00	E	-110.4	83.2	2691.2
9	2813.00	31.36	S	37.00	E	-149.2	112.4	2778.6
10	2913.00	35.84	S	37.00	E	-193.4	145.7	2861.8
11	3013.00	40.32	S	37.00	E	-242.6	182.8	2940.5
12	3113.00	44.80	S	37.00	E	-296.6	223.5	3014.2
13	3213.00	49.28	S	37.00	E	-355.1	267.6	3082.3
14	3313.00	53.76	S	37.00	E	-417.6	314.7	3144.5
15	3413.00	58.24	S	37.00	E	-483.8	364.5	3200.4
16	3513.00	62.72	S	37.00	E	-553.2	416.9	3249.7
17	3613.00	67.20	S	37.00	E	-625.6	471.4	3292.0
18	3713.00	71.68	S	37.00	E	-700.3	527.7	3327.1
19	3813.00	76.16	S	37.00	E	-777.1	585.6	3354.8
20	3913.00	80.64	S	37.00	E	-855.3	644.5	3374.9
21	4013.00	85.12	S	37.00	E	-934.5	704.2	3387.3
22	4113.00	89.60	S	37.00	E	-1014.3	764.3	3391.9
23	4122.00	90.00	S	37.00	E	-1021.5	769.7	3391.9
24	4213.00	90.00	S	37.00	E	-1094.1	824.5	3391.9
25	4313.00	90.00	S	37.00	E	-1174.0	884.7	3391.9
26	4413.00	90.00	S	37.00	E	-1253.9	944.8	3391.9
27	4513.00	90.00	S	37.00	E	-1333.7	1005.0	3391.9
28	4613.00	90.00	S	37.00	E	-1413.6	1065.2	3391.9
29	4713.00	90.00	S	37.00	E	-1493.4	1125.4	3391.9
30	4813.00	90.00	S	37.00	E	-1573.3	1185.6	3391.9
31	4913.00	90.00	S	37.00	E	-1653.2	1245.8	3391.9
32	5013.00	90.00	S	37.00	E	-1733.0	1305.9	3391.9
33	5113.00	90.00	S	37.00	E	-1812.9	1366.1	3391.9
34	5213.00	90.00	S	37.00	E	-1892.8	1426.3	3391.9
35	5313.00	90.00	S	37.00	E	-1972.6	1486.5	3391.9
36	5413.00	90.00	S	37.00	E	-2052.5	1546.7	3391.9
37	5513.00	90.00	S	37.00	E	-2132.4	1606.8	3391.8
38	5613.00	90.00	S	37.00	E	-2212.2	1667.0	3391.8
39	5713.00	90.00	S	37.00	E	-2292.1	1727.2	3391.8
40	5813.00	90.00	S	37.00	E	-2371.9	1787.4	3391.8
41	5913.00	90.00	S	37.00	E	-2451.8	1847.6	3391.8
42	6010.00	90.00	S	37.00	E	-2529.3	1905.9	3391.8
43	6010.00	90.00	S	37.00	E	-2529.3	1905.9	3391.8

BUILD, WALK, AND DOGLEG SEVERITY OUTPUT

NO.	M.D. (FT)	BUILD (D/100')	WALK (D/100')	DOGLEG SEVERITY (D/100')
2	2113.00	.000	.000	.000
3	2213.00	4.480	.000	4.480
4	2313.00	4.480	.000	4.480
5	2413.00	4.480	.000	4.480
6	2513.00	4.480	.000	4.480
7	2613.00	4.480	.000	4.480
8	2713.00	4.480	.000	4.480
9	2813.00	4.480	.000	4.480
10	2913.00	4.480	.000	4.480
11	3013.00	4.480	.000	4.480
12	3113.00	4.480	.000	4.480
13	3213.00	4.480	.000	4.480
14	3313.00	4.480	.000	4.480
15	3413.00	4.480	.000	4.480
16	3513.00	4.480	.000	4.480
17	3613.00	4.480	.000	4.480
18	3713.00	4.480	.000	4.480
19	3813.00	4.480	.000	4.480
20	3913.00	4.480	.000	4.480
21	4013.00	4.480	.000	4.480
22	4113.00	4.480	.000	4.480
23	4122.00	4.480	.000	4.480
24	4213.00	.000	.000	.000
25	4313.00	.000	.000	.000
26	4413.00	.000	.000	.000
27	4513.00	.000	.000	.000
28	4613.00	.000	.000	.000
29	4713.00	.000	.000	.000
30	4813.00	.000	.000	.000
31	4913.00	.000	.000	.000
32	5013.00	.000	.000	.000
33	5113.00	.000	.000	.000
34	5213.00	.000	.000	.000
35	5313.00	.000	.000	.000
36	5413.00	.000	.000	.000
37	5513.00	.000	.000	.000
38	5613.00	.000	.000	.000
39	5713.00	.000	.000	.000
40	5813.00	.000	.000	.000
41	5913.00	.000	.000	.000
42	6010.00	.000	.000	.000
43	6010.00	.000	.000	.000

HORIZONTAL DISPLACEMENT AND VERTICAL SECTION OUTPUT

NO.	M.D. (FT)	HORIZONTAL DISPLACEMENT (FT)	VERTICAL SECTION (FT)
1	.00	.0	.0
2	2113.00	.0	.0
3	2213.00	3.9	3.9
4	2313.00	15.6	15.6
5	2413.00	35.0	35.0
6	2513.00	62.0	62.0
7	2613.00	96.5	96.5
8	2713.00	138.2	138.2
9	2813.00	186.8	186.8
10	2913.00	242.2	242.2
11	3013.00	303.8	303.8
12	3113.00	371.4	371.4
13	3213.00	444.6	444.6
14	3313.00	522.9	522.9
15	3413.00	605.7	605.7
16	3513.00	692.7	692.7
17	3613.00	783.3	783.3
18	3713.00	876.9	876.9
19	3813.00	973.0	973.0
20	3913.00	1070.9	1070.9
21	4013.00	1170.1	1170.1
22	4113.00	1270.0	1270.0
23	4122.00	1279.0	1279.0
24	4213.00	1370.0	1370.0
25	4313.00	1470.0	1470.0
26	4413.00	1570.0	1570.0
27	4513.00	1670.0	1670.0
28	4613.00	1770.0	1770.0
29	4713.00	1870.0	1870.0
30	4813.00	1970.0	1970.0
31	4913.00	2070.0	2070.0
32	5013.00	2170.0	2170.0
33	5113.00	2270.0	2270.0
34	5213.00	2370.0	2370.0
35	5313.00	2470.0	2470.0
36	5413.00	2570.0	2570.0
37	5513.00	2670.0	2670.0
38	5613.00	2770.0	2770.0
39	5713.00	2870.0	2870.0
40	5813.00	2970.0	2970.0
41	5913.00	3070.0	3070.0
42	6010.00	3167.0	3167.0
43	6010.00	3167.0	3167.0

APPENDIX A-II
SURVEY DATA TO POINT OF SIDETRACK #1

WELLPLAN (Version 3.0)

Drilling Resources Development Corporation

Operator : BDM

Contractor : HLH DRILLING

Lease : ENEGER/CABOT

Field : WILSONDALE

Well Name : BDM/DOE ENEGER RET#1

Analyst : RSC

Date : 11-15-86

ANALYSIS : 2 - BDM/DOE ENEGER RET#1 SIDETRAC

SUBMODULE : 1 - Radius of Curvature Method

UNITS : ENGLISH

PROPOSED TARGET INFORMATION OUTPUT

PROPOSED DIRECTION S 37.00 E

SURVEY STATION PARAMETERS OUTPUT

NO.	M.D. (FT)	INC. (DEG)	DIRECTION			<----- LOCATION (FT) ----->		TVD
			N/S	AZM (DEG)	E/W	+N / -S	+E / -W	
1	.00	.00	N	.00	E	.0	.0	.0
2	2000.00	.00	S	1.00	E	.0	.0	2000.0
3	2083.00	.50	S	.01	E	-.4	.0	2083.0
4	2101.71	.87	S	3.49	E	-.6	.0	2101.7
5	2133.76	2.62	S	3.35	E	-1.6	.1	2133.7
6	2165.58	4.52	S	9.00	E	-3.5	.3	2165.5
7	2197.00	5.59	S	26.24	E	-6.2	1.1	2196.8
8	2229.00	6.50	S	41.00	E	-9.0	3.0	2228.6
9	2271.00	9.80	S	51.60	E	-13.1	7.3	2270.2
10	2340.00	12.50	S	49.00	E	-21.6	17.5	2337.9
11	2403.00	15.50	S	47.00	E	-31.8	28.9	2399.0
12	2465.00	18.00	S	42.00	E	-44.5	41.4	2458.4
13	2528.00	20.80	S	40.40	E	-60.3	55.2	2517.8
14	2591.00	24.50	S	40.00	E	-78.8	70.8	2575.9
15	2655.00	27.50	S	39.00	E	-100.4	88.7	2633.4
16	2718.00	30.00	S	37.00	E	-124.3	107.3	2688.7
17	2781.00	32.75	S	38.00	E	-150.3	127.3	2742.4
18	2844.00	35.80	S	39.00	E	-178.1	149.4	2794.5
19	2931.00	39.20	S	40.00	E	-219.0	183.0	2863.5
20	2993.00	41.60	S	40.00	E	-249.7	208.9	2910.7
21	3057.00	44.00	S	39.00	E	-283.3	236.5	2957.7
22	3120.00	46.20	S	37.80	E	-318.3	264.2	3002.1
23	3182.00	48.40	S	38.00	E	-354.2	292.2	3044.2
24	3246.00	51.60	S	37.00	E	-393.1	322.1	3085.3
25	3343.00	56.60	S	34.00	E	-457.0	367.7	3142.2
26	3405.00	60.80	S	33.50	E	-501.1	397.1	3174.4
27	3467.00	65.70	S	33.50	E	-547.2	427.7	3202.3
28	3509.00	68.00	S	34.00	E	-579.3	449.1	3218.8

BUILD, WALK, AND DOGLEG SEVERITY OUTPUT

NO.	M.D. (FT)	BUILD (D/100')	WALK (D/100')	DOGLEG SEVERITY (D/100')
2	2000.00	.000	.000	.000
3	2083.00	.602	.000	.602
4	2101.71	1.978	-18.600	1.990
5	2133.76	5.460	.437	5.460
6	2165.58	5.971	-17.756	6.073
7	2197.00	3.405	-54.870	5.914
8	2229.00	2.844	-46.125	5.629
9	2271.00	7.857	-25.238	8.633
10	2340.00	3.913	3.768	3.980
11	2403.00	4.762	3.175	4.823
12	2465.00	4.032	8.065	4.654
13	2528.00	4.444	2.540	4.524
14	2591.00	5.873	.635	5.878
15	2655.00	4.688	1.562	4.737
16	2718.00	3.968	3.175	4.252
17	2781.00	4.365	-1.587	4.443
18	2844.00	4.841	-1.587	4.923
19	2931.00	3.908	-1.149	3.970
20	2993.00	3.871	.000	3.871
21	3057.00	3.750	1.562	3.897
22	3120.00	3.492	1.905	3.744
23	3182.00	3.548	-.323	3.556
24	3246.00	5.000	1.562	5.141
25	3343.00	5.155	3.093	5.731
26	3405.00	6.774	.806	6.809
27	3467.00	7.903	.000	7.903
28	3509.00	5.476	-1.191	5.585

HORIZONTAL DISPLACEMENT AND VERTICAL SECTION OUTPUT

NO.	M.D. (FT)	HORIZONTAL DISPLACEMENT (FT)	VERTICAL SECTION (FT)
1	.00	.0	.0
2	2000.00	.0	.0
3	2083.00	.4	.3
4	2101.71	.6	.5
5	2133.76	1.6	1.3
6	2165.58	3.5	3.0
7	2197.00	6.3	5.6
8	2229.00	9.4	8.9
9	2271.00	15.0	14.8
10	2340.00	27.8	27.8
11	2403.00	42.9	42.8
12	2465.00	60.8	60.5
13	2528.00	81.7	81.3
14	2591.00	105.9	105.5
15	2655.00	134.0	133.6
16	2718.00	164.2	163.9
17	2781.00	197.0	196.7
18	2844.00	232.4	232.1
19	2931.00	285.4	285.0
20	2993.00	325.6	325.2
21	3057.00	369.0	368.6
22	3120.00	413.7	413.2
23	3182.00	459.2	458.8
24	3246.00	508.2	507.8
25	3343.00	586.6	586.3
26	3405.00	639.4	639.2
27	3467.00	694.5	694.4
28	3509.00	733.0	733.0

APPENDIX A-III
SURVEY DATA TO POINT OF SIDETRACK #1

WELLPLAN (Version 3.0)

Drilling Resources Development Corporation

Operator : BDM

Contractor : HLH DRILLING

Lease : ENEGER/CABOT

Field : WILSONDALE

Well Name : BDM/DOE ENEGER RET#1

Analyst : RSC

Date : 11-23-86

ANALYSIS : 4 - BDM/DOE ENEGER RET#1 SIDETRAC

SUBMODULE : 1 - Radius of Curvature Method

UNITS : ENGLISH

PROPOSED TARGET INFORMATION OUTPUT

PROPOSED DIRECTION S 37.00 E

SURVEY STATION PARAMETERS OUTPUT

NO.	M.D. (FT)	INC. (DEG)	DIRECTION			<-----		LOCATION (FT)	----->	
			N/S	AZM (DEG)	E/W	+N / -S			+E / -W	TVD
1	.00	.00	N	.00	E	.0		.0	.0	.0
2	2000.00	.00	S	1.00	E	.0		.0	.0	2000.0
3	2083.00	.50	S	.01	E	-.4		.0	.0	2083.0
4	2101.71	.87	S	3.49	E	-.6		.0	.0	2101.7
5	2133.76	2.62	S	3.35	E	-1.6		.1	.1	2133.7
6	2165.58	4.52	S	9.00	E	-3.5		.3	.3	2165.5
7	2197.00	5.59	S	26.24	E	-6.2		1.1	1.1	2196.8
8	2229.00	6.50	S	41.00	E	-9.0		3.0	3.0	2228.6
9	2271.00	9.80	S	51.60	E	-13.1		7.3	7.3	2270.2
10	2340.00	12.50	S	49.00	E	-21.6		17.5	17.5	2337.9
11	2403.00	15.50	S	47.00	E	-31.8		28.9	28.9	2399.0
12	2465.00	18.00	S	42.00	E	-44.5		41.4	41.4	2458.4
13	2528.00	20.80	S	40.40	E	-60.3		55.2	55.2	2517.8
14	2591.00	24.50	S	40.00	E	-78.8		70.8	70.8	2575.9
15	2655.00	27.50	S	39.00	E	-100.4		88.7	88.7	2633.4
16	2718.00	30.00	S	37.00	E	-124.3		107.3	107.3	2688.7
17	2781.00	32.75	S	38.00	E	-150.3		127.3	127.3	2742.4
18	2844.00	35.80	S	39.00	E	-178.1		149.4	149.4	2794.5
19	2931.00	39.20	S	40.00	E	-219.0		183.0	183.0	2863.5
20	2993.00	41.60	S	40.00	E	-249.7		208.9	208.9	2910.7
21	3057.00	44.00	S	39.00	E	-283.3		236.5	236.5	2957.7
22	3120.00	46.20	S	37.80	E	-318.3		264.2	264.2	3002.1
23	3182.00	48.40	S	38.00	E	-354.2		292.2	292.2	3044.2
24	3240.00	48.00	S	35.00	E	-389.0		318.0	318.0	3082.8
25	3272.00	46.00	S	34.00	E	-408.2		331.2	331.2	3104.7
26	3385.00	47.36	S	34.00	E	-476.4		377.2	377.2	3182.2
27	3397.00	47.50	S	34.00	E	-483.7		382.1	382.1	3190.3
28	3463.00	50.40	S	34.00	E	-525.0		409.9	409.9	3233.6
29	3509.00	53.17	S	34.73	E	-554.8		430.3	430.3	3262.1
30	3526.00	54.20	S	35.00	E	-566.1		438.2	438.2	3272.2
31	3589.00	57.00	S	35.00	E	-608.6		468.0	468.0	3307.8
32	3615.00	58.80	S	33.00	E	-626.9		480.3	480.3	3321.6
33	3665.00	61.50	S	34.00	E	-663.1		504.2	504.2	3346.5

BUILD, WALK, AND DOGLEG SEVERITY OUTPUT

NO.	M.D. (FT)	BUILD (D/100')	WALK (D/100')	DOGLEG SEVERITY (D/100')
2	2000.00	.000	.000	.000
3	2083.00	.602	.000	.602
4	2101.71	1.978	-18.600	1.990
5	2133.76	5.460	.437	5.460
6	2165.58	5.971	-17.756	6.073
7	2197.00	3.405	-54.870	5.914
8	2229.00	2.844	-46.125	5.629
9	2271.00	7.857	-25.238	8.633
10	2340.00	3.913	3.768	3.980
11	2403.00	4.762	3.175	4.823
12	2465.00	4.032	8.065	4.654
13	2528.00	4.444	2.540	4.524
14	2591.00	5.873	.635	5.878
15	2655.00	4.688	1.562	4.737
16	2718.00	3.968	3.175	4.252
17	2781.00	4.365	-1.577	4.443
18	2844.00	4.841	-1.587	4.923
19	2931.00	3.908	-1.149	3.970
20	2993.00	3.871	.000	3.871
21	3057.00	3.750	1.562	3.897
22	3120.00	3.492	1.905	3.744
23	3182.00	3.548	-.323	3.556
24	3240.00	-.690	5.172	3.917
25	3272.00	-6.250	3.125	6.655
26	3385.00	1.204	.000	1.204
27	3397.00	1.167	.000	1.167
28	3463.00	4.394	.000	4.394
29	3509.00	6.022	-1.587	6.149
30	3526.00	6.059	-1.588	6.193
31	3589.00	4.444	.000	4.444
32	3615.00	6.923	7.692	9.507
33	3665.00	5.400	-2.000	5.672

HORIZONTAL DISPLACEMENT AND VERTICAL SECTION OUTPUT

NO.	M.D. (FT)	HORIZONTAL DISPLACEMENT (FT)	VERTICAL SECTION (FT)
1	.00	.0	.0
2	2000.00	.0	.0
3	2083.00	.4	.3
4	2101.71	.6	.5
5	2133.76	1.6	1.3
6	2165.58	3.5	3.0
7	2197.00	6.3	5.6
8	2229.00	9.4	8.9
9	2271.00	15.0	14.8
10	2340.00	27.8	27.8
11	2403.00	42.9	42.8
12	2465.00	60.8	60.5
13	2528.00	81.7	81.3
14	2591.00	105.9	105.5
15	2655.00	134.0	133.6
16	2718.00	164.2	163.9
17	2781.00	197.0	196.7
18	2844.00	232.4	232.1
19	2931.00	285.4	285.0
20	2993.00	325.6	325.2
21	3057.00	369.0	368.6
22	3120.00	413.7	413.2
23	3182.00	459.2	458.8
24	3240.00	502.4	502.0
25	3272.00	525.7	525.4
26	3385.00	607.6	607.5
27	3397.00	616.4	616.3
28	3463.00	666.1	666.0
29	3509.00	702.2	702.1
30	3526.00	715.8	715.8
31	3589.00	767.8	767.7
32	3615.00	789.7	789.7
33	3665.00	833.0	833.0

APPENDIX A-IV
FINAL SURVEY DATA FOR COMPLETED WELL

WELLPLAN (Version 3.0)

Drilling Resources Development Corporation

Operator : BDM

Contractor : HLH DRILLING

Lease : ENEGER/CABOT

Field : WILSONDALE

Well Name : BDM/DOE ENEGER RET#1

Analyst : RSC

Date : 12-14-86

ANALYSIS : 7 - BDM/DOE ENEGER RET#1

SUBMODULE : 1 - Radius of Curvature Method

UNITS : ENGLISH

PROPOSED TARGET INFORMATION OUTPUT

PROPOSED DIRECTION S 37.00 E

SURVEY STATION PARAMETERS OUTPUT

NO.	M.D. (FT)	INC. (DEG)	DIRECTION			<----- LOCATION (FT) ----->		TVD
			N/S	AZM (DEG)	E/W	+N / -S	+E / -W	
1	.00	.00	N	.00	E	.0	.0	.0
2	2000.00	.00	S	1.00	E	.0	.0	2000.0
3	2083.00	.50	S	.01	E	-.4	.0	2083.0
4	2101.71	.87	S	3.49	E	-.6	.0	2101.7
5	2133.76	2.62	S	3.35	E	-1.6	.1	2133.7
6	2165.58	4.52	S	9.00	E	-3.5	.3	2165.5
7	2197.00	5.59	S	26.24	E	-6.2	1.1	2196.8
8	2229.00	6.50	S	41.00	E	-9.0	3.0	2228.6
9	2271.00	9.80	S	51.60	E	-13.1	7.3	2270.2
10	2340.00	12.50	S	49.00	E	-21.6	17.5	2337.9
11	2403.00	15.50	S	47.00	E	-31.8	28.9	2399.0
12	2465.00	18.00	S	42.00	E	-44.5	41.4	2458.4
13	2528.00	20.80	S	40.40	E	-60.3	55.2	2517.8
14	2591.00	24.50	S	40.00	E	-78.8	70.8	2575.9
15	2655.00	27.50	S	39.00	E	-100.4	88.7	2633.4
16	2718.00	30.00	S	37.00	E	-124.3	107.3	2688.7
17	2781.00	32.75	S	38.00	E	-150.3	127.3	2742.4
18	2844.00	35.80	S	39.00	E	-178.1	149.4	2794.5
19	2931.00	39.20	S	40.00	E	-219.0	183.0	2863.5
20	2993.00	41.60	S	40.00	E	-249.7	208.9	2910.7
21	3057.00	44.00	S	39.00	E	-283.3	236.5	2957.7
22	3120.00	46.20	S	37.80	E	-318.3	264.2	3002.1
23	3182.00	48.40	S	38.00	E	-354.2	292.2	3044.2
24	3240.00	48.00	S	35.00	E	-389.0	318.0	3082.8
25	3272.00	46.00	S	34.00	E	-408.2	331.2	3104.7
26	3345.00	47.00	S	34.00	E	-452.1	360.8	3154.9
27	3373.00	49.60	S	33.60	E	-469.5	372.4	3173.5
28	3437.00	53.50	S	30.00	E	-512.1	398.8	3213.3
29	3468.00	55.50	S	30.00	E	-534.0	411.5	3231.3
30	3500.00	57.60	S	31.00	E	-557.0	425.0	3249.0
31	3532.00	59.90	S	33.00	E	-580.2	439.5	3265.6
32	3563.00	62.20	S	32.00	E	-603.0	454.1	3280.6
33	3594.00	64.50	S	34.00	E	-626.3	469.2	3294.5
34	3661.00	69.00	S	34.00	E	-677.3	503.6	3320.9
35	3725.00	72.20	S	35.00	E	-727.0	537.8	3342.2
36	3787.00	74.00	S	34.00	E	-775.9	571.4	3360.2
37	3869.00	74.50	S	37.00	E	-840.2	617.2	3382.5
38	3935.00	81.00	S	37.00	E	-891.6	656.0	3396.5
39	3998.00	88.00	S	39.00	E	-941.0	694.6	3402.5
40	4043.00	92.00	S	39.00	E	-976.0	722.9	3402.5
41	4191.00	92.00	S	39.00	E	-1090.9	816.0	3397.3
42	4382.00	91.00	S	38.00	E	-1240.4	934.8	3392.3
43	4666.00	90.00	S	37.00	E	-1465.7	1107.7	3389.8
44	4983.00	89.00	S	35.00	E	-1722.1	1294.0	3392.6
45	5298.00	88.50	S	34.00	E	-1981.6	1472.4	3399.5
46	5599.00	88.00	S	31.00	E	-2235.3	1634.0	3408.7
47	6020.00	87.00	S	29.00	E	-2599.6	1844.3	3427.0

HORIZONTAL DISPLACEMENT AND VERTICAL SECTION OUTPUT

NO.	M.D. (FT)	HORIZONTAL DISPLACEMENT (FT)	VERTICAL SECTION (FT)
1	.00	.0	.0
2	2000.00	.0	.0
3	2083.00	.4	.3
4	2101.71	.6	.5
5	2133.76	1.6	1.3
6	2165.58	3.5	3.0
7	2197.00	6.3	5.6
8	2229.00	9.4	8.9
9	2271.00	15.0	14.8
10	2340.00	27.8	27.8
11	2403.00	42.9	42.8
12	2465.00	60.8	60.5
13	2528.00	81.7	81.3
14	2591.00	105.9	105.5
15	2655.00	134.0	133.6
16	2718.00	164.2	163.9
17	2781.00	197.0	196.7
18	2844.00	232.4	232.1
19	2931.00	285.4	285.0
20	2993.00	325.6	325.2
21	3057.00	369.0	368.6
22	3120.00	413.7	413.2
23	3182.00	459.2	458.8
24	3240.00	502.4	502.0
25	3272.00	525.7	525.4
26	3345.00	578.5	578.2
27	3373.00	599.3	599.1
28	3437.00	649.1	649.0
29	3468.00	674.1	674.1
30	3500.00	700.6	700.6
31	3532.00	727.8	727.8
32	3563.00	754.9	754.9
33	3594.00	782.5	782.5
34	3661.00	844.0	844.0
35	3725.00	904.3	904.3
36	3787.00	963.6	963.5
37	3869.00	1042.5	1042.4
38	3935.00	1107.0	1106.9
39	3998.00	1169.6	1169.5
40	4043.00	1214.5	1214.5
41	4191.00	1362.3	1362.3
42	4382.00	1553.2	1553.2
43	4666.00	1837.2	1837.2
44	4983.00	2154.1	2154.1
45	5298.00	2468.8	2468.7
46	5599.00	2768.9	2768.6
47	6020.00	3187.3	3186.0

BUILD, WALK, AND DOGLEG SEVERITY OUTPUT

NO.	M.D. (FT)	BUILD (D/100')	WALK (D/100')	DOGLEG SEVERITY (D/100')
2	2000.00	.000	.000	.000
3	2083.00	.602	.000	.602
4	2101.71	1.978	-18.600	1.990
5	2133.76	5.460	.437	5.460
6	2165.58	5.971	-17.756	6.073
7	2197.00	3.405	-54.870	5.914
8	2229.00	2.844	-46.125	5.629
9	2271.00	7.857	-25.238	8.633
10	2340.00	3.913	3.768	3.980
11	2403.00	4.762	3.175	4.823
12	2465.00	4.032	8.065	4.654
13	2528.00	4.444	2.540	4.524
14	2591.00	5.873	.635	5.878
15	2655.00	4.688	1.562	4.737
16	2718.00	3.968	3.175	4.252
17	2781.00	4.365	-1.587	4.443
18	2844.00	4.841	-1.587	4.923
19	2931.00	3.908	-1.149	3.970
20	2993.00	3.871	.000	3.871
21	3057.00	3.750	1.562	3.897
22	3120.00	3.492	1.905	3.744
23	3182.00	3.548	-.323	3.556
24	3240.00	-.690	5.172	3.917
25	3272.00	-6.250	3.125	6.655
26	3345.00	1.370	.000	1.370
27	3373.00	9.286	1.429	9.347
28	3437.00	6.094	5.625	7.519
29	3468.00	6.452	.000	6.452
30	3500.00	6.562	-3.125	7.061
31	3532.00	7.188	-6.250	8.956
32	3563.00	7.419	3.226	7.938
33	3594.00	7.419	-6.452	9.397
34	3661.00	6.716	.000	6.716
35	3725.00	5.000	-1.562	5.213
36	3787.00	2.903	1.613	3.288
37	3869.00	.610	-3.659	3.574
38	3935.00	9.848	.000	9.848
39	3998.00	11.111	-3.175	11.552
40	4043.00	8.889	.000	8.889
41	4191.00	.000	.000	.000
42	4382.00	-.524	.524	.740
43	4666.00	-.352	.352	.498
44	4983.00	-.315	.631	.705
45	5298.00	-.159	.317	.355
46	5599.00	-.166	.997	1.010
47	6020.00	-.238	.475	.531

APPENDIX B

DAILY LOG OF OPERATIONS ON LOCATION

BDM/DOE ENERGER DAILY LOG STARTING 10-19-86

10-19

RIGGING UP. HAVE SUBSTRUCTURE AND DRAWWORKS SET.

10-20

RIGGING UP. HAVE MOST OF RIG ASSEMBLED.

10-21

FINISHED RIGGING UP.

2:00PM: DRILLING RAT HOLE AND MOUSE HOLE.

6:42PM: STARTED DRILLING THE CONDUCTOR HOLE WITH A 22" BIT AND 2100SCFM OF AIR.

10-22

12:30AM: FINISHED DRILLING CONDUCTOR HOLE. DEPTH IS 48'.

RAN 20" CONDUCTOR TO 48' KB. NIPPLING UP CONDUCTOR PIPE.

3:00PM: DOE TRAILER ARRIVED ON LOCATION. THE TRAILER WAS PULLED TO THE LOCATION BY STOWERS TRUCKING. PO# MOR 000296 WAS ISSUED. THE DOE REPRESENTATIVES FINISHED HOOKING UP BOTH TRAILER TO THE GENERATOR.

5:00PM: STARTED DRILLING THE SURFACE HOLE WITH BIT #1 WHICH IS A 17 1/2" BIT THAT HAS BEEN ENLARGED TO APPROXIMATELY 18 1/2" INCHES. RUNNING 2100SCFM AIR (TWO COMPRESSORS).

10-23

12:30AM: MAKE CONNECTION. WOULD NOT DRILL AFTER CONNECTION. DEPTH 160'.

2:00AM: PULLED OUT OF HOLE. TWO SHANKS OF BIT LEFT IN HOLE. CALLED FOR FISHING TOOLS.

3:00AM: WAITING ON FISHING TOOLS.

9:00AM: DAN DEVOS AND AL YOST ON LOCATION TO REVIEW WELL STATUS. RIG CREW FABRICATING TOOLS TO RECOVER BIT SHANKS. FISHING TOOLS WERE DETERMINED TO BE TOO EXPENSIVE.

3:00PM: FISHING TOOLS ON BOTTOM, BUT FINGERS TOO LONG, CAME BACK OUT TO SHORTEN. FORTY TONS OF LIMESTONE PLACED ON ROAD BY KEN-MOR STONE, INC.

5:00PM: BACK ON BOTTOM WITH TOOLS, FOUND 15' OF FILLUP. COULDN'T GET TOOLS DOWN TO FISH. CAME OUT OF HOLE TO PUT ON 17.5" TRI-CONE BIT TO DRILL DOWN TO TOP OF BIT SHANKS. CALLED GEOSCIENCE ELECTRONICS TO DELAY ARRIVAL UNTIL WED. 29TH.

10:00PM: RERAN FABRICATED FINGER BASKET TO GET FISH. FINGERS TOO STIFF WILL MODIFY AND TRY AGAIN.

10-24

12:30AM: RUN FINGER BASKET AGAIN TO FISH BIT SHANKS. PULLED OUT OF THE HOLE WITH NO RECOVERY.

2:00AM: MODIFY FINGER BASKET BY MAKING THE FINGERS LESS STIFF.
2:30AM: RUN FINGER BASKET IN THE HOLE AGAIN. FISH. PULLED PIPE FROM HOLE WITH NO RECOVERY.
4:00AM: MODIFY FINGERS ON BASKET.
5:30AM: RUN BASKET. PULL OUT OF HOLE WITH NO RECOVERY.
6:30AM: MODIFY BASKET FINGERS AGAIN.
7:30AM: RUN BASKET AGAIN. PULL OUT OF HOLE WITH NO RECOVERY.
9:00AM: DECIDED TO SKID THE RIG. ODDS ARE THAT THE BIT SHANKS CANNOT BE RECOVERED ECONOMICALLY. PREPARING TO SKID THE RIG.
1:00PM: SKIDDED DRILLING RIG 15 FEET TO THE WEST. THE 16" CASING ARRIVED ON LOCATION. HAULED BY INTRACOSTAL TRUCKING INC. UNLOADED THE 16 JOINTS ON TO THE RACKS.
2:00PM: RIGGING UP DRILLING RIG. LAST PIPE TUB AND THE SPARE MUD PUMP ARRIVED ON LOCATION. BROUGHT IN BY HLH DRILLING.
2:30PM: DRILLING MOUSE HOLE.
3:00PM: DRILLING RAT HOLE. HLH HAS LOCATED A 22" BIT AND 20" CONDUCTOR.
4:00PM: PREPARING BHA FOR DRILLING CONDUCTOR HOLE. WAITING ON 22" BIT AND CONDUCTOR PIPE.
6:00PM: BIT ARRIVED ON LOCATION. RUN BIT. START DRILLING CONDUCTOR HOLE AT 6:30 PM. AIR RATE 2100SCFM WITH 100 PSI DRILL PIPE PRESSURE. BHA CONSIST OF BIT, AIR HAMMER, AND X-O SUB.
9:00PM: 20" INCH CONDUCTOR ARRIVED ON LOCATION. CONDUCTOR HAS A WRINKLE IN IT APPROXIMATELY 12 FEET FROM BOTTOM. WILL ONLY BE ABLE TO RUN ABOUT 30 FEET OF IT.

10-25

7:00AM: FINISHED DRILLING 30 FEET OF CONDUCTOR PIPE. PULL OUT OF HOLE AND LAY DOWN THE BIT AND AIR HAMMER. PREPARE TO RUN THE 20" CONDUCTOR. RAINED ALL NIGHT. ROAD INTO LOCATION IS VERY SLIPERY AND LOCATION IS MUDDY. 18 1/2" BIT ARRIVED ON LOCATION AT 8:30 AM.
9:00AM: PICKING UP CONDUCTOR PIPE. HAD TO DRIVE APPROXIMATELY 10 FEET.
1:00PM: NIPPLING UP CONDUCTOR. MAKE UP BHA. WELD STRAPS ON BIT TO STRENGTHEN IT.
4:00PM: RUN PIPE IN HOLE AND PREPARE TO DRILL.
4:30PM: DRILL TO 40 FEET.
5:30PM: MAKE CONNECTION. THE CONNECTION TAKES A LONG TIME BECAUSE THE CONDUCTOR MUST BE NIPPLED DOWN AND THE AIR HAMMER HAS TO BE CHANGED AROUND.
9:00PM: HAVING PROBLEMS WITH THE AIR HEAD. IT WILL NOT GO BACK TOGETHER. STILL WORKING ON IT.

10-26

2:00AM: STARTED DRILLING. DRILLED TO 52 FEET IN 2 HOURS. CHANGED TO STANDARD TIME. AIR HEAD IS STILL LEAKING.

3:00AM: MAKE CONNECTION. PULL BIT AND CHECK IT FOR CRACKS.
4:30AM: DRILLING TO 70 FEET. AIR HEAD STILL LEAKING.
7:00AM: STOPPED DRILLING TO REPAIR AIR HEAD. REPAIRED AIR HEAD BY CUTTING NEW BOLT HOLES AND CENTERING IT UNDER THE ROTARY TABLE.
9:30AM: DRILLING TO 120 FEET. RUNNING 2100 SCFM AT 150 PSI.
1:00PM: PULL PIPE FROM HOLE TO CHECK BIT. PART OF ONE OF THE STRAPS HAD FALLEN OFF. BIT OK.
2:30PM: DRILLING TO 132 FEET.
4:00PM: SERVICE RIG.
4:30PM: DRILLING TO 161 FEET. HLH RECEIVED A LOAD OF DIESEL. HAD TO BLADE OFF ROAD TO GET IT IN.
6:30PM: PULL PIPE TO CHECK BIT. THE BIT HAD A HAIR LINE CRACK AT THE JET HOLE.
7:30PM: LAY DOWN AIR HAMMER. PICK UP NEW BIT. MAKE UP BIT AND TRIP IN THE HOLE.
11:30PM: STARTED DRILLING. HOLE IS A LITTLE TIGHT EVERY ONCE IN A WHILE AND THE PIPE HAS TO BE WORKED. SOME FILL ON BOTTOM ON CONNECTIONS.

10-27

8:00AM: DRILLING AT 224 FEET. EASTMAN WHIPSTOCK WILL SEND OUT THE DIRECTIONAL DRILLING EQUIPMENT TODAY. HLH SAID THE SURVEY WIRELINE WILL BE HERE TODAY. WELL GOT WET AT 225 FEET. STARTED MISTING. SERVICE RIG.
8:30AM: MAKE CONNECTION AND START DRILLING.
9:00AM: NIS ON LOCATION. SET UP PIPE RACKS TO INSPECT PIPE.
12:00PM: NIS HAS STARTED INSPECTING PIPE. NIS SAYS THAT PIPE HAS BEEN IN SOME HYDROGEN SULFIDE RECENTLY BECAUSE OF THE BLACK SCALE. DRILLING AT 250 FEET. NO LONGER MISTING. NOT DRILLING EXTREMELY FAST. HALLIBURTON BROUGHT OUT WIRELINE UNIT AT 11:00AM. HLH BROUGHT IN OTHER COMPRESSOR AT THE SAME TIME.
3:30PM: DEPTH 295 FEET. RING UP AND SURVEY. SURVEY WAS 1/2 DEGREE AT 595 FEET. NIS HAS INSPECTED 80 JOINTS OF PIPE. HAVE TWO REJECTS. ONE IS BENT AND ONE HAS AN INTERNAL DEFECT.
4:00PM: START DRILLING WITH 30000 LBS BIT WEIGHT.
7:00PM: DRILLING AT 328 FEET. NIS HAS 126 JOINTS INSPECTED. STILL RAINING.
9:00PM: NIS FINISHED INSPECTING THE DRILL PIPE. FOUND 3 BAD JOINTS OUT OF 173 JOINTS. 42 JOINTS WERE BENT.
11:30PM: DRILLING AT 408 FEET. STRING WEIGHT IS 50,000 LBS WITH NO HOLE DRAG.

10-28

1:00AM: BIT TORQUED UP. PULL BIT. IT HAD A LOCKED CONE. PUT ON A NEW BIT AND TRIP IN THE HOLE.
7:00AM: BACK ON BOTTOM AND STARTING TO DRILL. DEPTH AT TRIP WAS 426 FEET. HAD NO DRAG OR TIGHT SPOTS WHILE TRIPPING. HOLE APPEARS TO BE IN GOOD SHAPE.
8:00AM: RUN SURVEY AT 439 FEET WAS 1/2 DEGREE.

8:30AM: DRILLING.

11:00AM: LEVELED DOE TRAILER. DRILLING AT 486 FEET.

1:00PM: DEPTH IS 499 FEET. BOLTS WORKED OUT ON AIR HEAD. REPAIR SAME.

1:30PM: FINISHED REPAIRS AND STARTED DRILLING. BIT WEIGHT IS 35000 TO 40000 LBS. RPM 60. PRESSURE IS 140 PSI. MISTING.

2:00PM: DIRECTIONAL DRILLER SMITH, FROM EASTMAN CHRISTENSEN VISITED LOCATION TO CHECK SCHEDULE.

5:30PM: DRILLING AT 550 FEET. GOING TO DRILL TO 660 FEET. HAVE 649.53 FEET OF 16" CASING ON LOCATION. THE MIST RATE IS APPROXIMATELY 6 BARRELS PER HOUR.

8:00PM: NIPPLE BROKE ON THE MIST INJECTION PUMP. REPAIRED SAME. DEPTH IS 589 FEET.

9:00PM: FINISHED REPAIRS AND ARE BACK TO DRILLING.

10:00PM: BIT TORQUING UP. PULL OUT OF HOLE TO CHECK BIT. DEPTH IS 602 FEET.

10-29

12:30AM: OUT OF HOLE. BIT HAS A LOCKED UP CONE. MAKE UP NEW BIT AND TRIP IN HOLE. THE LAST TWO BITS HAVE BEEN USED BITS.

2:00AM: ESTABLISH CIRCULATION.

2:30AM: START DRILLING. DRILL TO 660 FEET WHICH IS WHERE THE 16 INCH CASING WILL BE RUN.

6:30AM: TD AT 660 FEET. CIRCULATE TO CLEAN THE HOLE BEFORE RUNNING CASING.

7:30AM: START OUT OF HOLE. STOWERS AND SONS HAVE BEEN HAULING WATER MOST OF THE NIGHT.

9:00AM: START TO PICK UP 16 INCH CASING. FIRST JOINT WOULD NOT GO PAST THE BOTTOM OF THE CONDUCTOR PIPE. GOING TO PULL THE CONDUCTOR PIPE.

9:30AM: HALLIBURTON REPRESENTATIVE ARRIVED ON LOCATION. FULL ROTARY TABLE TO REMOVE CONDUCTOR PIPE. CONDUCTOR WAS SLIGHTLY BENT ON THE BOTTOM.

10:30AM: START RUNNING 16 INCH CASING AGAIN. TOOK TWO HOURS TO MAKE UP FIRST JOINT. WOULD NOT GO PAST 60 FEET. TRIED DRIVING ON CASING WITH NO RESULTS. TOOK 80,000 LBS TO PULL IT BACK OUT. HAVE AN OFFSET HOLE AT APPROXIMATELY 60 FEET.

12:00PM: STOWERS AND SONS FINALLY ARRIVED WITH THE DIRECTIONAL DRILLING EQUIPMENT. WAITING TO BE UNLOADED. RIG CREW IS BUSY RUNNING CASING.

1:00PM: LAY CASING BACK DOWN.

2:00PM: WAITING FOR DRILCO TO BRING OUT A 17 1/2 INCH 3PT REAMER. LAY DOWN COLLARS OUT OF DERRICK TO BE USED FOR REAMING.

4:00PM: FINISHED UNLOADING STOWERS TRUCK. THE HALLIBURTON PUMP TRUCKS ARRIVED ON LOCATION. LEFT THE CEMENT TRUCK AT THE LOCATION.

8:00PM: DRILCO ARRIVED WITH THE REAMER. MAKE UP REAMER ON THE BOTTOMHOLE ASSEMBLY. REAMED HARD BETWEEN 60 AND 70 FEET. TACKED BIT TO THE REAMER.

11:30PM: REAMING AT 90 FEET.

10-30-86

8:00AM: REAMING AT 475 FEET. HAVE HAD A FEW TIGHT SPOTS. DISCUSSED RUNNING A PACKED HOLE ASSEMBLY IF THE SINGLE REAMER DOES NOT DO THE JOB. HLH WILL BE LOOKING FOR ADDITIONAL REAMERS AND/OR STABILIZERS.

9:00AM: REAMING AT 550 FEET. NOT REAMING HARD NOW.

10:30AM: FINISHED REAMING TO 660 FEET. CIRCULATE TO CLEAN HOLE.

11:00AM: START PULLING OUT OF THE HOLE.

11:30AM: RIG UP AND START RUNNING CASING. HAD VERY LITTLE DRAG GOING THROUGH THE SPOT AT 60 FEET.

1:30PM: HAVE 200 FEET IN THE HOLE (5 JOINTS). DRAG IS 2000 POUNDS. OTTO OF EASTMAN ARRIVED ON LOCATION IS CHECKING THE INVENTORY OF THE EQUIPMENT THAT EASTMAN SENT TO THE LOCATION.

2:30PM: THE FIRST 7 JOINTS WENT IN WITHOUT ANY PROBLEM. HUNG UP ON THE 8TH AND 9TH JOINTS. (300 TO 400 FEET). WORKED PIPE UP AND DOWN SEVERAL TIMES AND IT REDUCED THE DRAG CONSIDERABLY. ENOUGH TO BE ABLE TO RUN MORE CASING. CASING IS 16", 65 #/FT, H-40, BUTTRESS.

4:00PM: FINISHED RUNNING CASING. TIGHT ON LAST JOINT BUT IT WENT INTO THE HOLE. CALLED HALLIBURTON AND THE STATE INSPECTOR. WAITING ON HALLIBURTON.

PIPE TALLY ON 16 INCH CASING BOTTOM TO TOP.

40.25

41.15

43.15

42.10

38.25

40.50

33.75

39.60

38.15

46.02

39.60

42.60

42.50

40.40

37.55

43.96

649.53

DID NOT RUN SHOE, FLOAT EQUIPMENT, OR CENTRALIZERS.

8:00PM: HALLIBURTON ARRIVED AND STARTED RIGGING UP.

10:00PM: FILLED PIPE AND ESTABLISHED CIRCULATION.

TRANSFERRING WATER BETWEEN TANKS.

11:00PM: START CEMENTING OPERATIONS. PUMPED 5 BARRELS OF WATER FOLLOWED BY 270 SACKS OF CLASS A CEMENT CONTAINING 3% CALCIUM CHLORIDE (57 BARRELS). DISPLACED WITH 142 BARRELS WATER. LEFT 20 FEET OF CEMENT INSIDE CASING. CIRCULATED 10 BARRELS OF GOOD CEMENT TO SURFACE. MIXED CEMENT AT 15.6 LBS PER GALLON WITH A YIELD OF 1.18 CUBIC FEET PER SACK.

10-31

12:00PM: RIG DOWN HALLIBURTON AND WAIT ON CEMENT.

6:00AM: TRISTATE ARRIVED ON LOCATION WITH THE 11 3/4 INCH CASING ELEVATORS AND THE COLLAR CLAMP.

8:00AM: CUT OFF 16 INCH CASING AND NIPPLE UP. TRISTATE LEFT WITH THE 16 INCH CASING ELEVATORS.

10:00AM: MAKE UP BHA. BIT, X-O, 2-8" MONELS, X-O, X-O, 6 3/4 INCH DRILL COLLARS. NIPPLE UP AIR HEAD ON TOP OF THE BIT.

1:30PM: TRIP IN HOLE. UNLOAD WATER FROM HOLE.

3:00PM: RESET ROTARY TABLE. SERVICE DRILLING RIG AND DRILL OUT THE CEMENT PLUG. CLEAN UP HOLE. MILLER SUPPLY BROUGHT OUT THE WELLHEAD EQUIPMENT AND MCJUNKIN BROUGHT OUT THE AIR METERING EQUIPMENT.

5:30PM: STOWERS AND SONS ARRIVED ON LOCATION AND STARTED HAULING WATER. STARTED DRILLING. DRILL TO 700 FEET.

7:00PM: DRYING UP HOLE AND WORKING ON MIST PUMP.

8:00PM: DRILL TO 743 FEET WITH 35,000 LBS BIT WEIGHT. DRILLING ONE TO TWO MINUTES PER FOOT. TRYING TO DRY UP HOLE.

9:30PM: FOAM HOLE TO MAKE SURE IT IS UNLOADED. WELL IS NOT MAKING WATER.

10:00PM: DRILLING TO 769 FEET. BIT APPEARS TO BE TORQUING. HLH WILL PULL IT TO SEE IF IT IS OK.

10:30PM: TRIP OUT OF HOLE TO INSPECT BIT. THE BIT IS A RECONDITIONED BIT.

11-1

12:00AM: OUT OF THE HOLE. BIT APPEARS TO BE OK. PROBABLY ROUGH DRILLING CONDITIONS. TRIP IN HOLE AND ESTABLISH CIRCULATION.

2:00AM: DRILLING WITH 2100 SCFM AIR AND MIST.

8:00AM: DEPTH IS 896 FEET. NOT HAVING MUCH LUCK DRYING UP WELL BUT IT IS NOT MAKING WATER.

9:30AM: SURVEY AT 931 FEET WAS 1 1/4 DEGREES. CHANGED OIL IN THE DOE GENERATOR AT 762 HOURS. ALSO CHANGED FUEL AND OIL FILTERS.

2:00PM: DRILLING AT 992 FEET WITH 20000 LBS BIT WEIGHT, 40 RPM, AND 180 PSI. AIR RATE IS 2100 SCFM. MAGCOBAR ARRIVED ON LOCATION WITH MUD PRODUCTS AT 1:00 PM. THE 11 3/4" CASING ARRIVED ON LOCATION AT 2:30 PM. RECIEVED 51 JOINTS (2129.30') OF 11 3/4", 47#/FT, K-55, ST&C CASING.

11-2

12:00AM: BIT IS DRILLING ROUGH AND IRRATIC. DRILLER DECIDED TO PULL THE BIT. DEPTH IS 1197 FEET. TRIP OUT OF HOLE. BIT LOOKS OK. ROUGH DRILLING IS DUE TO FORMATION. RUN ANOTHER BIT WHICH IS ALSO A RERUN BIT. TRIP IN HOLE. ESTABLISH CIRCULATION.

6:00AM: ON BOTTOM AND STARTED DRILLING. STILL DRILLING VERY ROUGH.

8:00AM: DRILLING AT 1216 FEET WITH 30000 LBS AND 45 RPM.
10:30AM: RUN DEVIATION SURVEY AT 1276 FEET. DEVIATION IS 1.5 DEGREES.
11:00AM: DRILLING.
3:30PM: PENETRATION RATE IS SLOWING DOWN STARTING AT 1385 FEET. DRILLING ROUGH. ONLY RUNNING 20000 LBS ON THE BIT BECAUSE OF THE TORQUE. DEPTH IS 1390 FEET.
4:30PM: SERVICE DRILLING RIG AND AIR PACKAGE.
5:00PM: DRILLING SLOW. MUD LOGGER SAYS THE FORMATION IS SANDSTONE. BIT WEIGHT IS ONLY 15000 LBS BECAUSE OF TORQUING PROBLEMS.
8:00PM: CONNECTION AT 1431 FEET. TOOK 3 HOURS TO DRILL 30 FEET. DRILLED ONLY 6 FEET IN LAST HOUR.

11-3

12:00AM: DRILLING AT 1510 FEET.
8:00AM: DRILLING AT 1625 FEET. DRILLING ROUGH. RUNNING 23,000 LBS BIT WEIGHT, 55 RPM, 2100 SCFM AIR, 5 TO 10 BBL'S PER HOUR MIST, AND 180 PSI STANDPIPE PRESSURE. PUTTING MF-1 IN THE SOAP TANKS TO CLEAN UP PIT WATER. REUSING PIT WATER FOR MIST.
9:30AM: BIT IS TORQUING RADICALLY. WILL TRIP TO CHECK BIT. DEPTH IS 1650 FEET.
11:00AM: OUT OF HOLE. BEARINGS ON BIT ARE BAD BUT THE CUTTING STRUCTURE IS STILL IN GOOD SHAPE. BIT IS TIGHT. COULD NOT BREAK THE BIT OFF UNDER THE ROTARY TABLE EVEN USING THE DOZER TO HOLE IT. HAD TO CUT THE SHOULDER ON THE BIT IN ORDER TO GET IT TO BREAK.
4:00PM: RUN NEW BIT WHICH IS A HUGHES TOOL COMPANY HH73 AND IS A NEW BIT. HUGHES TOOL DELIVERED THREE 10 5/8" AND TWO 7 7/8" BITS AT 12:30 PM. HALLIBURTON ARRIVED AT 1:00 PM TO CHECK ON THE DRILLING OPERATIONS. SAID THEY WOULD SEND OUT THE FLOAT EQUIPMENT TOMORROW. CLARK CAME OUT TO SEVICE THE PORTA-JOHN'S AT 1:30 PM. ASHLAND PETROLEUM COULD NOT DILEVER DIESEL TODAY SO CALLED UP ORVILLE MARKUM TO BRING SOME OUT OTHERWISE WE WOULD RUN OUT.
6:00PM: IN THE HOLE AND WORKING ON THE AIR HEAD. BLOW HOLE.
6:30PM: DRILLING. WELL IS DRILLING VERY ROUGH. IT STALLS OUT THE ROTARY TABLE. RUNNING 25,000 LBS ON THE BIT WITH 55 RPM. AIR, MIST AND PRESSURE ARE THE SAME.
9:00PM: BRIDGE MART BROUGHT OUT 4500 GALS OF DIESEL AND PUT IT IN THE TANKER OND THE RIG TANK.
11:00PM: DRILLING AT 1730 FEET. THE DRILLING RATE HAS SLOWED DOWN CONSIDERABLY.

11-4

3:30AM: DRILLING RATE PICKED UP AT 1760 FEET AFTER INCREASING THE RPM'S TO 150. RUNNING THE LOWER RPM, IT TOOK 4 HOURS TO DRILL 30 FEET. NOW DRILLING ABOUT 25 FEET PER HOUR.
7:00AM: GOT A GOOD GAS SHOW AT 1825 FEET OF 6,000 PPM. HAD A GAS SHOW OF 500,000 PPM IN THE BIG LIME AT 1836 FEET.

8:00AM: DRILLING AT 1870 FEET. BACKGROUND GAS IS DOWN TO 300,000 PPM. CIRCULATING TO TAKE A SURVEY. HOLE HAS NOT UNLOADED IN THE LAST HOUR. PUMPING FOAM TO UNLOAD HOLE. MAY HAVE PICKED UP MORE FLUID.

9:00AM: GEOSCIENCE ARRIVED WITH THEIR TOOLS AND STARTED TO UNLOAD THEM. BOB HENNIGER ARRIVED AT ABOUT 9:30 AM. SURVEY AT 1870 FEET WAS 0.5 DEGREES. BACKGROUND GAS HAS DROPPED TO ABOUT 250,000 PPM.

12:00PM: CONNECTION AT 1932 FEET. HAVING TROUBLE UNLOADING THE HOLE SO HLH IS GOING TO PUT 3 COMPRESSORS ON THE HOLE (3150 SCFM). BILL OVERBY CALLED AND SAID THE BASE OF THE BIG INJUN SHOULD BE ABOUT 2055 FEET AND WE WOULD HAVE TO SET CASING AT 2080 FEET. WILL HAVE TO DRILL TO ABOUT 2100 FEET. EASTMAN REPRESENTATIVE ARRIVED AND IS COORDINATING WITH GEOSCIENCE.

2:00PM: HALLIBURTON ARRIVED WITH THE GUIDE SHOE, INSERT FLOAT VALVE, AND 6 CENTRALIZERS.

2:45PM: REACHED 2000 FEET. DRILLED INTO THE RED INJUN AT ABOUT 1975 FEET. STRAPPED THE 11 3/4" CASING. HAVE 2111.04 FEET ON LOCATION. GEOSCIENCE LEFT THE LOCATION.

7:00PM: REACHED A TD OF 2124 FEET. HAD SILTSTONE AND SHALE IN THE LAST TWO KELLYS DOWN. CIRCULATED THE HOLE CLEAN. HAD TO CIRCULATE ABOUT 1/2 HOUR AFTER EACH KELLY DOWN SINCE 8:00AM BECAUSE THE HOLE WAS NOT UNLOADING WHILE DRILLING THE KELLY DOWN. PENETRATION RATE WAS ABOUT 1 MINUTE PER FOOT.

8:00PM: CALLED HALLIBURTON, CORDER POWER TONGS, AND JERRY HOLCOMB WITH THE STATE. HALLIBURTON SHOULD BE HERE AT 7:00 AM AND CORDER SHOULD BE HERE AT 3:00AM. YOUNG WIRELINE SHOULD BE HER AT 9:00PM.

8:30PM: START OUT OF THE HOLE. HUNG UP FOR A WHILE AFTER PULLING 130 FEET OF PIPE AND KELLY. WORKED FREE. RAN BACK THROUGH THE SPOT WITH NO PROBLEM. CONTINUED OUT OF THE HOLE.

9:30PM: YOUNG WIRELINE IS ON LOCATION.

10:00PM: STARTED LAYING DOWN THE 6 1/4" DRILL COLLARS.

11-5

12:30AM: FINISH LAYING DOWN DRILL COLLARS. BREAK OUT BIT UNDER ROTARY TABLE.

2:30AM: RIG UP YOUNG WIRELINE AND RUN OPEN HOLE LOGS.

3:30AM: FINISHED THE NEUTRON, DENSITY AND GAMMA RAY. HAD TO RUN THE GAMMA RAY SEPARATE BECAUSE THE SOURCE SATURATED THE GAMMA RAY IN THE LARGER AIR FILLED HOLE. DEPTH WAS 2102 FEET. FOUND 300 FEET OF FLUID IN THE HOLE. FLUID LEVEL HAD COME UP THE HOLE 50 FEET IN ABOUT ONE HOUR.

7:00AM: FINISHED LOGGING AND RIG DOWN THE LOGGER. RIG UP TO RUN CASING. WILL SET CASING AT ABOUT 2020 FEET.

8:00AM: START RUNNING CASING. MADE UP GUIDE SHOE ON BOTTOM JOINT. PLACED INSERT FLOAT VALVE IN THE TOP OF THE FIRST JOINT. PLACED ONE CENTRALIZER ON THE FIRST THROUGH SIXTH COLLARS. TOTAL 6 CENTRALIZERS. USED WELD A ON THE GUIDE SHOE.

11:30AM: THE STATE INSPECTOR, JERRY HOLCOMB, ARRIVED ON LOCATION. HE SAID THAT WE HAD TO CEMENT THE 11 3/4" CASING ALL THE WAY BACK TO THE SURFACE. HE ALSO SAID THAT WE MUST WAIT ON CEMENT FOR 12 HOURS SINCE THE TOP SLURRY IS HALLIBURTON LIGHT. CANNOT TAKE THE HEAD OFF FOR 12 HOURS.

INCLUDING THE CEMENT TO PLUG THE OLD HOLE THERE IS 350 SACKS OF HALLIBURTON LIGHT (1.54 CU FT/SACK) AND 425 SACKS OF NEAT CEMENT (1.18 CU FT/SACK). TOTAL CEMENT VOLUME IS 185.31 BARRELS. HOLE VOLUME FROM THE CALIPER LOG IS 172.27 BARRELS. THE SHOE JOINT TAKES 5 BARRELS WHICH LEAVES 8 BARRELS EXCESS.

2020-2006	13 3/4"	.0495BBL/FT	0.69BBLS
2006-1998	14"	.0563BBL/FT	0.45BBLS
1998-1800	13 3/4"	.0495BBL/FT	9.80BBLS
1800-1690	14"	.0495BBL/FT	6.19BBLS
1690-0	15 1/4"	.0918BBL/FT	155.14BBLS
TOTAL			172.27BBLS

1:00PM: FINISHED RUNNING PIPE. RAN 2024.46 FEET OF CASING.

CASING TALLY FOR 11 3/4", 47#, K-55, ST&C CASING IS AS FOLLOWS:

44.04
42.67
42.96
43.98
41.48
43.92
44.00
44.12
41.28
42.98
44.19
43.95
41.50
43.70
43.40
44.18
43.95
43.40
43.12
38.25
41.70
44.14
36.68
42.99
34.99
37.95
34.96
42.85
43.83
43.02
36.49
35.05
43.11
43.35
43.41

41.61
38.72
42.96
37.92
36.18
42.04
43.77
39.82
43.50
42.23
43.98
37.78
33.42
34.95

TOTAL LENGTH 2024.46 FEET. LANDED AT 2024 FEET KB.

CEMENT WITH 11 3/4" CASING WITH 10 BBLs WATER, 25 SACKS OF GEL MIXED IN 125 BBLs OF WATER, 350 SACKS OF HALLIBURTON LIGHT (MIXED AT 12.6PPG AND 1.54 CU FT PER SACK) CONTAINING 3% CALCIUM CHLORIDE FOLLOWED BY 425 SACKS OF CLASS A (MIXED AT 15.6PPG AND 1.18 CU FT PER SACK) CONTAINING 2% CALCIUM CHLORIDE. DISPLACED WITH 232 BARRELS OF WATER. PLUG DID NOT BUMP. FLOAT HELD OK. PLUG DOWN AT 3:10 PM.

CIRCULATED GOOD CEMENT TO SURFACE. WAITING ON CEMENT.

PULLED ALL THE HALLIBURTON TRUCKS OFF THE LOCATION WITH THE DOZER.

6:00PM: PUT 150 FEET OF 2 INCH PLASTIC LINE IN THE OLD HOLE.

7:00PM: RIGGING UP FLOW METER FOR COMPRESSORS. PLACE 15 JOINTS OF DRILL PIPE ON RACK AND STRAP.

11:00PM: EASTMAN ARRIVED AND BROUGHT OUT A UBHO SUB AND SOME MOTOR PARTS.

11-6

3:30AM: RIG DOWN CEMENTING HEAD AND NIPPLE UP ON 11 3/4" CASING.

5:30AM: LOCAL WELDER ARRIVED BUT REFUSED TO WELD FLANGE IN THE CELLAR. WAITING ON WELDER.

6:30AM: HLH WELDER ARRIVED AND STARTED NIPPLING UP.

11:00AM: EASTMAN AND BAKER REPRESENTATIVE ARRIVED TO GO OVER MOTOR OPERATIONS.

12:00PM: HAVE BOP ON. INSTALLING ROTATING HEAD.

2:30PM: FINISHED NIPPLING UP. PICK UP BHA. STRAP AND CALIPER ALL OF BHA. WITH THE 8 1/2 HOUR CREDIT, DAYWORK STARTED AT 6:00AM ON 11-6-86. (4.5 HOURS LOGGING AND 4 HOURS EXTRA WOC). MAGCOBAR SENT OUT 50 BAGS OF GRAPHITE.

5:00PM: RUN DRILL PIPE IN HOLE. TRI-STATE ARRIVED ON LOCATION TO PICK UP THE CASING ELEVATORS AND 7 5/8 BY 6 5/8 CROSSOVER. LOADED TRUCK. EASTMAN IS ON LOCATION AND WORKING.

7:00PM: INSTALL ROTATING HEAD RUBBER. BLOW WATER OUT OF PIPE. COMPRESSORS WENT DOWN. FUEL VALVE HAD BEEN SHUT OFF. RESTART COMPRESSORS. LOST ABOUT 1 HOURS TIME. STOWERS AND SONS IS HAULING WATER.

8:00PM: UNLOADED THE HOLE AND THE FLOWLINE BLEW OFF.
REPLACE FLOWLINE. THE HOLE DIRECTION WAS CHANGED TO S37E
IN ORDER TO ALLOW ADEQUATE DRILLED LENGHT AND STILL STAY
WITHIN THE ENEGER LEASE. This will also help compensate for
any left hand walk

8:30PM: CONTINUE TO TRIP IN HOLE. BLOW WATER OUT OF CASING.
10:30PM: TAG CEMENT AT 1923 FEET. SERVICE RIG.
11:00PM: DRILL CEMENT TO FLOAT VALVE.

11-7

12:30AM: DRILLING ON FLOAT. NOT MAKING MUCH PROGRESS. HAD
TO PUT 40000 LBS ON BIT TO DRILL THROUGH IT.
4:00AM: DRILL SHOE JOINT AND WASH TO BOTTOM. HAD 10 FEET OF
CEMENT BELOW THE SHOE. HAD 20 FOOT OF FILL ON THE BOTTOM.
6:00AM: CIRCULATE TO SURVEY. MEASURED DEPTH OF BOTTOM WAS
2113 FEET.
6:30AM: SURVEY. SURVEY WAS .5 DEGREES SOW AT 2083 FEET.
THE HALLIBURTON WIRELINE WOULD NOT PULL THE TOOL BACK OUT
OF THE HOLE. TOOK 1.5 HOURS TO RUN THE SURVEY.
8:00AM: START OUT OF HOLE WITH DRILL PIPE. REPLACE LINE ON
THE MAKEUP TONGS.
10:00AM: BILL ORISON OF MAGCOBAR ARRIVED TO WORK THE FOAM
SYSTEM. BROUGHT OUT 4 1/2 XH CORROSION RINGS.
10:30AM: OUT OF HOLE. BIT IS IN GOOD SHAPE. REPLACE SNUB
LINES ON TONG LINES.
11:30AM: PICK UP MOTOR AND MWD EQUIPMENT.
2:00PM: START IN THE HOLE WITH COLLARS AND DRILL PIPE.
5:00PM: ON BOTTOM WITH ANGLE BUILDING ASSEMBLY. EASTMAN
WIRELINE UNIT ARRIVED ON LOCATION. WAIT ON GEOSCIENCE.
6:00PM: BEGIN TO ORIENT TOOL FACE. TEST MISTING UNIT.
6:40PM: START MOTOR, BEGIN DRILLING.
8:30PM: FIRST KELLEY DOWN. DRILLING AT RATE OF 20 ' /HR. LAST
15 FEET. GEOSCIENCE SURVEY SAYS .87DEGREE INCLINATION,
ORIENTATION S4E.
11:00PM: DRILLING WITH DOWNHOLE MOTOR AT 2194 FEET. THE
LAST SURVEY WAS 4.52 DEGREES S9E AT 2166 FEET. HAVE ABOUT
10 FEET OF FILL ON CONNECTIONS WHICH IS NOT BAD. THE ACTUAL
ON BOTTOM DRILL RATE IS ABOUT 45 FEET PER HOUR. BIT WEIGHT
IS 7000 LBS, PRESSURE IS 200 PSI, AND THE MIST RATE IS 10
BBL'S PER HOUR.
11:10PM: MOTOR STALLED AND CAN'T GET IT RUNNING AGAIN. WILL
HAVE TO TRIP.

11-8

12:30AM: TRIP OUT OF HOLE. THE MWD TOOL IS NOT WORKING
EITHER.
2:00AM: FINISHED TRIP OUT OF THE HOLE. BREAK DOWN THE
TOOLS. THE MOTOR IS PLUGGED WITH CUTTINGS. BIT OK. CHANGE
MOTOR.
4:00AM: REPAIR MWD. CAN'T GET INSIDE OF THE TOOL BECAUSE
THE LOCKING SCREWS WON'T COME OUT. PICKED UP THE STANDBY
TOOL AND ASSEMBLED THE BHA.

7:00AM: TRIP IN THE HOLE WITH NEW MOTOR AND MWD SYSTEM.
9:00AM: FINISH TRIP IN HOLE. RIG UP, ORIENT AND SURVEY.
10:00AM: START DRILLING. SURVEY AT FIRST KELLY DOWN WAS 5.59 DEGREES S26.24E AT 2197 FEET. NOT GETTING AUTOMATIC 15 MINUTE SIGNALS AFTER 11:00 AM.
12:00PM: HAVING TROUBLE KEEPING MOTOR ORIENTED AND NOT GETTING ENOUGH SIGNALS FROM THE MWD TO KNOW EXACTLY WHAT THE MOTOR IS DOING.
1:00PM: DRILLED TO 2267 FEET. COULD NOT GET THE MWD TOOL TO SURVEY AT THE KELLY DOWN. GET NO SIGNAL FROM THE TOOL. WAITING FOR JIM OF GEOSCIENCE TO ARRIVE ON LOCATION.
3:30PM: DECIDED TO CALL SCIENTIFIC DRILLING FOR ORIENTATION SERVICE.
4:00PM: HARRISON BACK ON LOCATION. PULLED UP HOLE 1 STAND AND TRIED TO SURVEY. NO RESULTS
4:40PM: STARTED OUT OF THE HOLE TO REMOVE THE SPARE TOOL AND EVALUATE FOR REPAIRS.
5:15PM: USED DRILL AND TAP TO REMOVE SCREWS TO OPEN TOOL FOR INSPECTION. WHEN LAST SET SCREW WAS ALMOST OUT, THE TOOL BLEW APART BECAUSE PRESSURE WAS TRAPPED INSIDE. JIM HARRISON SPECULATED THAT THE PRESSURE INSIDE THE TOOL PROBABLY CAUSED A CHIP OR OTHER ELECTRONIC COMPONENT FAILURE. THIS MAY OR MAY NOT BE THE REASON FOR FAILURE OF THE BACKUP TOOL.
7:45PM: SECOND TOOL OUT OF DRILL STRING. FAILURE IN THE ELECTRONICS PACKAGE NOT RELATED TO THE FIRST FAILURE. THE BACKUP TOOL WILL BE REPAIRED AND PLACED BACK IN THE DRILL STRING FOR ADDITIONAL EVALUATION.
10:30PM: HAVE THE SECOND TOOL REPAIRED WITH NEW ELECTRONICS PACKAGE. TWO ELECTRONICS PACKAGES HAVE ALREADY FAILED. INSTALL TOOL IN THE DRILL STRING.
11:30PM: TRIP IN HOLE.

11-9

1:30AM: ON BOTTOM. HAD 20 FEET OF FILL OR TIGHT HOLE. WASHED MOTOR DOWN THROUGH IT. SURVEY AND ORIENT. SURVEY WAS 6.5 DEGREES S41E AT 2229 FEET.
2:30AM: DRILLING. GEOSCIENCE STATED THAT THE DIFFERENCE BETWEEN THEIR TOOL FACE AND THE MOTOR TOOL FACE WAS NOT PUT INTO THE COMPUTER. THE DIFFERENCE IS 40 DEGREES TO THE LEFT. THEREFORE, INSTEAD OF BUILDING INCLINATION DURING THE LAST MOTOR RUN, THE HOLE WAS BEING TURNED LEFT. THE HOLE DIRECTION ON BOTTOM IS PROBABLY DUE EAST. TURNING MOTOR TO THE RIGHT. CANNOT GET IT TO TURN TO THE RIGHT IMMEDIATELY. WILL HAVE TO TURN A LITTLE, DRILL, TURN AND DRILL UNTIL THE MOTOR IS POINTED TO THE RIGHT. DRILL 10 FEET TO 2277 FEET.
3:00AM: SHUT PUMP DOWN TO GET A SURVEY AND TOOL FACE. MOTOR WOULD NOT RESTART. IT IS PLUGGED. STANDPIPE PRESSURE WAS 500 PSI. ATTEMPT TO UNPLUG MOTOR.
4:00AM: TRIP OUT OF HOLE TO LAY DOWN MWD SYSTEM AND UNPLUG THE MOTOR. THE MWD SYSTEM IS NOT SET UP TO GIVE ENOUGH TOOL FACE INFORMATION TO MAKE IT REALISTIC ENOUGH TO USE FOR A STEERING TOOL. SINCE THE MWD CANNOT RECEIVE DATA WITH THE AIR ON, DRILLING MUST BE STOPPED TO SEND A SIGNAL AND RECEIVE A TOOL FACE. THEN THERE ARE PROBLEMS GETTING THE MOTOR RESTARTED.

6:00AM: LAY DOWN MWD SYSTEM.
8:00AM: TRY MOTOR AT THE SURFACE. MOTOR TURNS AT 120 PSI.
ESTIMATE THE MOTOR IS TURNING BETWEEN 120 AND 200 RPM WHICH
SHOULD NOT HURT THE MOTOR. REMOVE 24/32" JETS FROM BIT.
WILL TRY TO BUILD A FLOAT TO STICK ON TOP OF THE BIT.
9:00AM: MAINTAINING RIG WHILE WAITING ON SCIENTIFIC.
SERVICED THE GENERATOR AT 880 HOURS.
6:30PM: SCIENTIFIC DRILLING ARRIVED ON LOCATION. GO OVER
PLANS.
7:00PM: UNLOAD SCIENTIFIC'S EQUIPMENT.
8:00PM: MAKE UP BHA. MAKE SURE STEERING TOOL WILL GO
THROUGH ALL OF BHA. SEAT TOOL IN MULE SHOE SUB.
9:30PM: TRIP IN HOLE. ASSEMBLE STEERING TOOL.
11:00PM: WAITING ON GEARHEART TO ARRIVE WITH WIRELINE UNIT.

11-10

12:45AM: GEARHEART ARRIVED ON LOCATION. BEGIN TO RIG
WIRELINE. HAVE TO MAKE HEAD CONNECTION. HANG SHIEVES.
4:00AM: RUN STEERING TOOL INTO WELL. HAD TROUBLE GETTING
INTO THE 6 1/4" DRILL COLLARS WHICH HAVE A 2 3/8 INCH ID.
PULL STEERING TOOL AND GRIND DOWN FINS. RUN STEERING TOOL
AND SEAT IN BENT SUB.
6:00AM: START AIR MOTORS AND ORIENT DOWNHOLE MOTOR.
6:30AM: START DRILLING AT HIGH SIDE TO 20 DEGREES RIGHT.
11:30AM: CONNECTION AT 2385 IS A LITTLE TIGHT. WORKED PIPE
UP AND DOWN SEVERAL TIMES.
12:30PM: CONNECTION AT 2416 FEET. PULLING 72000 LBS UP AND
68000 LBS DOWN. BLOCKS AND KELLY WEIGH 10000 LBS.
4:30PM: STARTED DRILLING SLOWER AT 2510 FEET. POSSIBLE TOP
OF THE BEREA SANDSTONE. SURVEY WAS 18 DEGREES S42E AT 2465
FEET.
8:30PM: HAVING TROUBLE KEEPING MOTOR RUNNING.
9:00PM: TRIP OUT TO SIDE ENTRY SUB. WIRELINE DOES NOT
APPEAR TO HAVE LEAKED AT THE SUB. PULL WIRELINE. FINISH
TRIP OUT OF HOLE.

11-11

12:00AM: LAY DOWN MOTOR AND BIT. BIT STILL LOOKS IN FAIRLY
GOOD SHAPE. HAD A PIECE OF THE MOTOR RUBBER ON TOP OF THE
BIT. MOTOR IS PROBABLY WORE OUT. PICK UP AND TEST THE
FIRST MOTOR TO SEE IF IT IS STILL WORKING OR PLUGGED.
1:00AM: MOTOR TESTED OK. TOOK 135 PSI TO START IT.
TRIP IN HOLE.
3:30AM: ENCOUNTERED A TIGHT SPOT AT 2400 FEET. PICKED UP
KELLY AND WORKED THROUGH IT.
4:00AM: RUN STEERING TOOL.
4:30AM: ORIENT AND START DRILLING.
5:30AM: CONNECTION AT 2573 FEET. PULLED 76000 LBS UP AND
68000 LBS DOWN. SURVEY AT 2528 FEET WAS 20.8 DEGREES
S40.4E. STILL DRILLING FAIRLY HARD.
6:00AM: DRILLING AHEAD BUT MOTOR IS STALLING A LOT.

8:00AM: MOTOR WILL NOT RESTART AFTER A CONNECTION. DRILLED ERRATIC.

8:30AM: START OUT OF HOLE TO PICK UP A NEW MOTOR. PULLED THE STEERING TOOL OUT OF THE HOLE.

11:00AM: OUT OF HOLE. LAID DOWN THE MOTOR AND PICKED UP A NEW MOTOR. THE ONE WITHOUT THE BY-PASS. TRIPPED IN THE HOLE. HAD NO FILL OR TIGHT SPOTS.

2:30AM: FINISHED TRIP IN THE HOLE. SERVICED RIG. ADJUST BRAKES.

DAILY LOG PART 2, STARTING AT 3:00PM ON 11-11-86.

3:00PM: RUN STEERING TOOL AND SEAT.

3:30PM: DRILLING WITH DOWNHOLE MOTOR. UP DRAG IS 80000 AND DOWN DRAG IS 70000. RUNNING 5 TO 10000 LBS ON THE MOTOR WITH 2100SCFM AT 200 TO 250 PSI.

7:00PM: CONNECTION AT 2700 FEET. HAVING TROUBLE GETTING THE MOTOR RESTARTED AFTER CONNECTIONS. TRIED WORKING UP AND DOWN. BLEEDING AIR OFF AND PUTTING IT BACK ON. MOTOR STARTED AFTER ABOUT ONE HOUR.

10:00PM: DRILLED TO 2763 FEET AND MAKE A CONNECTION.

SURVEY AT 2718' IS 30 DEGREES S37E. COULD NOT GET MOTOR TO RESTART AFTER THE CONNECTION. TRIED FOR ONE HOUR. TRIED 3150SCFM ON THE HOLE WITH NO LUCK.

11:30PM: PULL OUT OF HOLE TO MAKE SURE THE SIDE ENTRY SUB IS NOT LEAKING. CALLED PRESTON DOMINIQUE OF BAKER ABOUT MOTOR. HE SAID THAT SOMETIMES THE MOTOR WILL DRY OUT AND WILL NOT RESTART. TRY DUMPING 5 GALS OF SOAP DOWN THE PIPE ON THE CONNECTION OR ROTATING IT ON THE BOTTOM FOR A FEW TURNS. CAN'T ROTATE WITH A WIRELINE IN THE HOLE.

11-12

1:00AM: DUMPED 5 GALS SOAP IN PIPE AND TRIP BACK TO BOTTOM.

2:00AM: PUT MOTOR ON BOTTOM AND IT STARTED RUNNING. DRILLED 5 FEET TO MAKE SURE IT WOULD CONTINUE TO DRILL.

2:30AM: RUN WIRELINE. DUMP 5 GALS SOAP IN PIPE.

3:00AM: START DRILLING WITH MOTOR.

3:30AM: MAKE A CONNECTION. PUT SOAP IN PIPE. MOTOR WOULD NOT START. DUMPED OIL IN THE MOTOR WITH NO LUCK. PUMPED ABOUT 5 BARRELS WITH MIST PUMP. THE MOTOR STARTED.

5:00AM: DRILLED TWO JOINTS DOWN TO 2857 FEET. SURVEY AT 2781 IS 32.75 DEGREES S38E. STILL HAVE 10000LBS DRAG.

7:30AM: MOTOR WOULD NOT RESTART ON THE CONNECTION. PUMPED MIST WATER INTO IT AND FINALLY GOT IT STARTED.

9:00AM: MOTOR WOULD NOT RESTART AFTER THE NEXT CONNECTION. PUMPED MIST WATER INTO IT TWICE BEFORE IT STARTED.

10:30AM STARTED MOTOR AND DRILLED 31'. MADE CONNECTION AND MOTOR WOULDN'T START.

11:30AM DEPTH 2920' TRYING TO START MOTOR. RIGGED TO DRILL 2 JOINTS AT A TIME. LAYED KELLEY DOWN.

2:30PM STARTED MOTOR DRILLED 16'. WIRELINE GOING INTO THE SIDEDOOR SUB GOT KINKED WHILE WE MADE COURSE CORRECTIONS, AND WOULD NOT FEED. HAVE TO CUT LINE AND REHEAD TO CONTINUE

5:30PM WIRELINE REPAIRED. TRYING TO START MOTOR

8:00PM STARTED MOTOR, DRILLED 62'.

9:30PM PUMPED WATER DOWN DRILL PIPE TO LUBRICATE MOTOR STILL WON'T START.

11:30PM STARTED MOTOR, DRILLED 11' AND MOTOR STALLED. 2985'.

11-13-96

12:00AM DECIDED TO PULL STRING AND REPLACE MOTOR. TRIP OUT OF HOLE.

4:00AM: OUT OF THE HOLE. TOOK THE BLANKED BY-PASS OUT OF THE OLD MOTOR AND INSTALLED IT IN THE NEW MOTOR.
5:00AM: STARTED IN THE HOLE. RERAN THE LAST BIT BECAUSE IT WAS STILL IN GOOD SHAPE.
8:00AM: ON BOTTOM WITH THE MOTOR. RUN WIRELINE STEERING TOOL. START UP COMPRESSORS.
9:00AM: STARTED DRILLING THE FIRST CONNECTION. THE MOTOR STARTED RIGHT UP. SURVEY AT 2993 FEET WAS 41.6 DEGREES S40E. MADE A CONNECTION AND THE MOTOR RESTARTED.
10:30AM: MAKE CONNECTION. HAD 17 FEET OF FILL ON CONNECTION. NO PROBLEM STARTING MOTOR.
11:00AM: DRILLING. WILL SLOW THE PENETRATION RATE A LITTLE TO GIVE THE HOLE A BETTER CHANCE TO CLEAN.
11:30AM: DRILLING. HAD NO PROBLEM RESTARTING THE MOTOR.
1:30PM: CONNECTION. DID NOT HAVE ANY FILL. MOTOR STARTED FIRST TIME. THE MOTOR IS NOW ONLY BUILDING AT A RATE OF 3.5 TO 4.0 DEGREES PER 100 FEET WHICH IS NOT ENOUGH. HAVE TO BUILD 4 DEGREES PER 100 FEET. WILL PULL THE MOTOR WHEN THE INCLINATION GETS CLOSE TO THE PLANNED INCLINATION.
2:00PM: DRILLING. LEASE ROAD IS BEING REPAIRED TODAY BY HLH AND BOB RICHARDS OF ENERGER. DEPTH AT CONNECTION IS 3102 FEET. SURVEY AT 3057 IS 44 DEGREES S39E.
3:30PM: CONNECTION AT 3165 FEET. NO FILL. HAD TO PUT ABOUT 1 BARREL OF WATER IN THE DRILL PIPE TO GET THE MOTOR RESTARTED.
4:15PM: STARTED DRILLING.
6:00PM: MOTOR STALLED AT 3220 FEET. HAD A GAS SHOW OF 35,000 PPM AT THE SAME TIME. PROBABLY A FRACTURE.
6:30PM: CONNECTION AT 3227 FEET. THE SURVEY AT 3182 FEET READ 48.4 DEGREES S40E. DIRECTION WAS JUMPING AROUND A LITTLE ON SCIENTIFIC'S PANEL. MAY NOT BE ACCURATE. DID NOT GET THE SURVEY UNTIL THE PUMP HAD BEEN TURNED BACK ON. INCLINATION IS BUILDING AT ONLY 3.5 DEGREES PER 100 FEET. NOW ONLY 1.5 DEGREES AHEAD OF SCHEDULE. WILL HAVE TO TRIP FOR THE 3 DEGREE BENT SUB. HAVING TO PUT WATER IN THE DRILL PIPE ON EACH CONNECTION NOW TO GET THE MOTOR STARTED.
7:30PM: MOTOR STALLED AT 3240 FEET. STARTED RIGHT UP. NO GAS SHOW.
10:30PM: CONNECTION. SURVEY IS 51.6 DEGREES S37E AT 3246 FEET. BUILD RATE IS 5.0 DEGREES PER 100 FEET. WILL DRILL ANOTHER 60 FEET AS LONG AS THE MOTOR WILL RUN. CHANGED PREVIOUS SURVEY TO S38E.
11:00PM: MOTOR STALLED AFTER DRILLING 10 FEET. PUMPING WATER TO GET IT RUNNING AGAIN.

11-14

12:00AM: GOT MOTOR RUNNING. DRILLED ANOTHER 8 FEET AND STALLED AGAIN. WILL CIRCULATE A LITTLE WHILE AND THEN TRIP OUT. THE NEW BAKER MOTORS ARRIVED AND PRESTON WITH BAKER ALSO ARRIVED.
1:00AM: HOLE IS TIGHT. PULLING 50000 LBS OVER THE STRING WEIGHT TO GET THE PIPE OUT. WILL HAVE TO RUN 3000 SCFM NEXT TIME TO GET THE HOLE CLEAN.

2:00AM: GOT FIRST STAND OUT. CIRCULATE TO CLEAN UP THE HOLE. UNLOAD THE NEW MOTORS FROM THE TRUCK AND LOAD THE OLD MOTORS (3) TO SEND BACK TO LOUISIANA.

3:30AM: PULL OUT OF HOLE. STILL A LITTLE TIGHT.

7:30AM: LAY DOWN DOWNHOLE MOTOR. BIT IS STILL IN GOOD SHAPE. CHANGED THE BENT SUB TO 3 DEGREES. FOUND A 2 INCH DIAMETER PIECE OF RUBBER ON TOP OF THE FLOAT VALVE. PRESTON THINKS THAT IT MAY BE THE CAUSE FOR ALL THE MOTOR PROBLEMS. AT LEAST IT WOULD EXPLAIN WHY THERE IS A 200 PSI INCREASE IN PRESSURE WHEN THE MOTOR IS NOT RUNNING. THE STALL PRESSURE SHOULD ONLY BE ABOUT 25 TO 50 PSI.

8:30AM: SERVICE RIG. UNLOAD SOAP AND SODA ASH FROM THE MAGCOBAR TRUCK.

9:30AM: MAKE UP AIR BODY AND TRIP IN THE HOLE. RUN STEERING TOOL.

12:00PM: ON BOTTOM AND ORIENTING DOWNHOLE MOTOR. STEERING TOOL FAILED. THIS IS THE FIRST PROBLEM WITH THE STEERING TOOL. PULL WIRE LINE AND CHANGE PROBES.

2:00PM: RUN STEERING TOOL.

2:30PM: TRIP TO BOTTOM AND ORIENT MOTOR.

3:00PM: ON BOTTOM DRILLING WITH MOTOR. MOTOR IS RUNNING FINE.

5:30PM: CONNECTION. SURVEY IS 56.6 DEGREES S34E AT 3343 FEET. BUILDING 5.155 FEET PER HUNDRED. THE DIRECTION ON THE EYE TOOL IS NOW GOING TO BE LESS ACCURATE BECAUSE THE INCLINATION IS NOW REACHING THE LIMITS OF THE TOOL.

6:00PM: BACK TO DRILLING. NO PROBLEM STARTING THE MOTOR.

8:00PM: MAKE A CONNECTION AT 3450 FEET. SURVEY IS 60.8 DEGREES S33.5E AT 3405 FEET. BUILDING 6.7 DEGREES PER HUNDRED.

8:30PM: DRILLING. NO PROBLEM RESTARTING MOTOR.

11:00PM: CONNECTION AT 3509 FEET. SURVEY IS 65.7 DEGREES WHICH IS A 7.9 DEGREE PER 100 FEET BUILD RATE. WILL HAVE TO RUN A MUCH SMALLER BENT SUB. CIRCULATE PRIOR TO PULLING OUT OF THE HOLE.

11-15

12:00AM: HOLE IS TIGHT. HAD ONLY BEEN RUNNING 2100 SCFM BECAUSE 3000 SCFM CAUSED THE STEERING TOOL TO JUMP AROUND. HAD CUT MIST BACK TO 10 BBLs PER HOUR TO LESSEN THE WETTING OF THE HURON SHALES. WAS NOT ENOUGH TO CLEAN THE HOLE. PULLING 60,000 LBS OVER STRING WEIGHT.

12:30AM: CIRCULATE FOR 1/2 HOUR TO CLEAN HOLE. STILL COULD NOT GET PIPE OUT OF THE HOLE.

1:30AM: CIRCULATE HOLE FOR ANOTHER HOUR.

2:30AM: HOLE IS STILL TIGHT. PULLING ONE JOINT AT A TIME WHILE CIRCULATING THE HOLE. THE BUILD RATE REQUIRED NOW TO HIT A TVD OF 3390 FEET AT 85 DEGREES IS 2.6 DEGREES PER 100 FEET. WILL HAVE TO DRILL OVER 700 FEET TO DRILL IT. AL AND BILL LOOKED AT THE LOGS AND WOULD LIKE TO BE AT 90 DEGREES AT 3400 FEET TVD BECAUSE THAT IS WHERE THE AVERAGE PAY IS IN THE SURROUNDING WELLS. TO OBTAIN THIS OBJECTIVE, THE WELL HAS TO BE AT 85 DEGREES AT A TVD OF 3380 FEET.

5:00AM: PULL STEERING TOOL. THE HOLE IS FULL OF FLUID BECAUSE THE PRESSURE EXCEEDS 500 PSI. WHILE WORKING THE PIPE TO GET IT OUT OF THE HOLE, THE WIRELINE WAS KINKED AT THE SIDE ENTRY SUB AND IS SHORTED OUT. THERE IS NOT ENOUGH WIRE ON THE TRUCK TO CUT IT AGAIN. RELEASE THE GEARHART TRUCK.

5:30AM: PULLING ONE JOINT AT A TIME WITH AIR ON.

7:00AM: HAVE 300 FEET OF PIPE OUT OF THE HOLE WHEN THE PIPE STARTED COMING FREE. TRIP OUT OF HOLE.

8:30AM: RIG UP TO LAY DOWN DRILL PIPE FOR REAMING.

9:00AM: LAY DOWN 80 JOINTS OF DRILL PIPE. WILL PICK UP THE PIPE IN THE TUBS TO REAM WITH. THE DRILL PIPE HAS A LOT OF RUST AND SCALE IN IT WHICH COULD BE CAUSING PROBLEMS WITH THE DOWNHOLE MOTORS. BY REAMING WITH THIS PIPE, THE MAJORITY OF THE SCALE CAN BE REMOVED BEFORE RUNNING A MOTOR. THE DRILL PIPE THAT WAS LAID DOWN CAN BE PICKED UP WHILE MOTOR DRILLING SINCE THE SCALE HAS ALREADY BEEN CLEANED OUT OF THE PIPE.

11:30AM: FINISHED LAYING DOWN THE DRILL PIPE. TRIP THE REST OF THE WAY OUT OF THE HOLE. TO THE COLLARS.

1:00PM: CUT DRILLING LINE.

2:00PM: PULL DRILL COLLARS AND LAY DOWN THE MOTOR AND BENT SUB.

4:00PM: PICK UP BHA AND CALIPER AND STRAP IT. BHA CONSIST OF BIT, 3 FT, 2-8" MONELS, 3 FT, X-O, X-O, 2 6 1/4" DC'S.

CHANGED OIL IN THE ONAN AT 1014 HOURS.

6:00PM: STAP STANDS IN THE HOLE.

7:00PM: PICK UP AND STRAP DRILL PIPE OUT OF TUBS.

9:00PM: STARTED TAKING WEIGHT AT 2230 FEET. ONLY 100 FEET INTO THE DIRECTIONAL HOLE. START COMPRESSORS AND PICK UP KELLY.

9:30PM: START REAMING WITH 5000 LBS WEIGHT. RUNNING 2100 SCFM WITH NO SOAP.

11-16

12:00AM: REAMING AT 2400 FEET. WELL IS DUSTING NICELY.

8:00AM: REAMING AT 3176 FEET. NO PROBLEMS. THE STRING WEIGHT IS 80000. DRAG IS 100000 UP AND 70000 DOWN.

9:00AM: HOLE IS REAMING MUCH TOUGHER NOW. RUNNING 10000 TO 20000 LBS REAMING. HAVING PROBLEMS CLEANING THE HOLE. PUT 3000 SCFM ON THE WELL. CIRCULATING AND WORKING THE PIPE AFTER EACH KELLY DOWN.

1:00PM: GEARHART ARRIVED ON LOCATION. REAMING AT 3459 FEET. STILL REAMING ROUGH. WORKING PIPE AND CIRCULATING TO CLEAN HOLE AFTER EACH CONNECTION. RIG UP GEARHART.

3:30PM: DRILL STRING BECAME STUCK WHILE MAKING A CONNECTION. DRILL PIPE IS PLUGGED AND CANNOT CIRCULATE. STUCK APPROXIMATELY 5 FEET OFF BOTTOM. CAN MOVE THE PIPE 2 FEET AND CAN ROTATE IN THAT 2 FOOT INTERVAL. TRIED PULLING AND WORKING THE PIPE OUT OF THE HOLE. PULLED 230000 LBS WITH NO PROGRESS. PUMPED ABOUT 50 BBLS DOWN THE ANNULUS TO TRY FLUSHING THE HOLE OUT WITH NO SUCCESS.

7:00PM: HOLE IS SLOWLY GETTING TIGHTER. HAVE NOT MADE ANY PROGRESS. DO NOT HAVE ANY FREE MOVEMENT IN THE PIPE ANY MORE. CALLED MCCULLOUGH TO BACK OFF THE DRILL PIPE AND DOTCO TO FISH IT OUT. WAITING ON FISHING TOOLS AND WIRELINE TRUCK. WORKING STUCK PIPE.

11:30PM: MCCULLOUGH ARRIVED ON LOCATION. RIGGING UP.

11-17

12:00AM: RUNNING FREEPOINT. THE 6 1/4" DRILL COLLARS ARE FREE. CANNOT GET MORE THAN 10 FEET INTO THE MONELS.

1:30AM: RUN BACKOFF SHOT TO BACKOFF AT THE TOP OF THE 6 1/4" DRILL COLLARS. PUT 3.5 ROUNDS OF TORQUE IN THE DRILL STRING AND FIRE BACKOFF SHOT. BACKOFF WAS SUCCESSFUL.

2:00AM: RIG DOWN MCCULLOUGH. DOTCO ARRIVED ON THE LOCATION.

2:30AM: TRIP OUT OF THE HOLE.

5:00AM: OUT OF THE HOLE. PICK UP THE FISHING ASSEMBLY. SCREW IN SUB, X-O, BUMPER SUB, JARS, X-O, 4-6 1/4" DC'S.

8:00AM: FINISHED PICKING UP THE BHA. STRAP IN THE HOLE.

10:00AM: TAG THE FISH AND START THE COMPRESSORS. CIRCULATE ON TOP OF THE FISH FOR 30 MINUTES. SCREW INTO THE FISH. JARRED TWICE AND THE JARS FAILED. SCREW IN SUB CAME OUT.

11:00AM: TRIP OUT OF HOLE FOR NEW SET OF JARS. JARS WILL HAVE TO COME FROM RIPLEY, BELIEVE IT OR NOT.

3:00PM: JARS ARRIVED. MAKE UP JARS IN BHA.

4:00PM: TRIP IN THE HOLE WITH FISHING ASSEMBLY.

6:00PM: ON BOTTOM WITH JARS. CIRCULATE. SCREW INTO FISH WITH 3.5 ROUNDS OF TORQUE.

6:30PM: JARRING ON FISH WITH 190000 LBS. BUMPER SUB MOVES WITH 70,000 LBS. FISH IS MOVING SLIGHTLY.

10:00PM: FISH HAS MOVED ABOUT 1.5 FEET. STARTED JARRING WITH 200000 LBS AND PULLED 220000 LBS. DOE GENERATOR FAILED.

11-18

3:00AM: JARS FAILED. ONLY MOVED THE FISH A TOTAL OF 2 FEET. CALL FOR A BACKOFF TRUCK.

4:00AM: MANUALLY BACKED OFF THE DRILL STRING AT THE SCREW IN SUB TO REMOVE THE KELLY. STARTED BACKING OFF WITH ONLY 1 ROUND OF TORQUE. COULD NOT SCREW BACK INTO THE FISH. YOUNG WIRELINE CALLED BACK AND AND SAID THEY COULD NOT MAKE IT.

7:00AM: TRIP OUT OF THE HOLE. THE DECISION TO SIDETRACK HAS BEEN MADE. HALLIBURTON WILL SET A 200 FOOT PLUG. WILL ATTEMPT A SIDETRACK ABOUT 100 FEET ABOVE THE FISH.

9:00AM: LAY DOWN THE FISHING TOOLS. THE SCREW IN SUB LOOKED LIKE IT HAD GONE DOWN ALONG SIDE OF THE FISH BECAUSE OF THE MARKS ON THE PIN.

10:00AM: TRIP IN THE HOLE WITH DRILL PIPE OPEN ENDED. HALLIBURTON ARRIVED ON THE LOCATION..

12:00PM: RIG UP HALLIBURTON TO SET A BALANCED PLUG. PUMPED 46 BARRELS OF WATER FOLLOWED BY 125 SACKS OF NEAT CEMENT CONTAINING 3% CALCIUM CHLORIDE (MIXED AT 15.6 PPG WITH A YEILD OF 1.18 CUBIC FEET PER SACK). DISPLACED CEMENT WITH 6.5 BARRELS OF WATER.

1:00PM: RIG DOWN HALLIBURTON.

1:30PM: TRIP OUT OF THE HOLE. LAY DOWN 5 STANDS.

3:30PM: WAITING ON CEMENT. PERFORM MAINTENANCE ON THE RIG. GO THROUGH THE COMPRESSORS AND MIST PUMP. PULL BLANK BY-PASS VALVES OUT OF THE USED MOTORS.

11-19

11:00AM: PICK UP A NEW BIT, X-O, FLOAT SUB, AND 4-6 1/4" DC'S. TRIP IN THE HOLE TO DRESS OFF THE CEMENT PLUG. SCIENTIFIC ARRIVED ON THE LOCATION AT NOON. CALLED OUT GEARHART.

1:00PM: START COMPRESSORS AND BLOW THE WATER OUT OF THE HOLE. TAG CEMENT AT 3176 FEET. DRILLED CEMENT TO 3239 FEET. CEMENT IS HARD AND DRILLED ABOUT 2 MINUTES TO THE FOOT WITH 20,000 LBS BIT WEIGHT.

4:00PM: THE NEW 8" MONELS AND REAMERS ARRIVED ON THE LOCATION. CIRCULATED TO CLEAN THE HOLE AND UNLOADED THE TRUCK. GEARHART ARRIVED ON THE LOCATION.

5:00PM: THE HOLE WAS A LITTLE TIGHT WHEN FIRST PICKED UP OFF BOTTOM. PICKED UP THE KELLY AND REAMED THROUGH IT A COUPLE TIMES.

6:00PM: PULL OUT OF HOLE. LAID DOWN ALL THE 6 1/4" DRILL COLLARS.

9:00PM: PICK UP NEW MOTOR, FLOAT SUB, 2 1/2 DEGREE BENT SUB, 2-8" MONELS, AND X-O.

10:00PM: TRIP IN HOLE WITH MOTOR. RIG UP THE WIRELINE TRUCK.

11-20

12:00AM: RUN SHAREWELL STEERING TOOL.

12:30AM: TIME DRILL TO SIDETRACK. HAVING TROUBLE ORIENTING THE DOWNHOLE MOTOR. TRYING TO DRILL OFF TO THE RIGHT (90 DEGREES). SLOWLY GETTING MOTOR ORIENTED.

2:30AM: SHAREWELL TOOL FAILED. WILL NO LONGER GIVE READINGS. PULL SHAREWELL TOOL AND CHANGE PROBES.

4:30AM: TIME DRILLING WITH MOTOR. DRILLED 8 FEET BETWEEN 6 AND 7 AM. MUD LOGGER SAYS SAMPLES ARE MOSTLY SHALE. WELL APPEARS TO BE SIDETRACKED.

7:30AM: THE SECOND SHAREWELL TOOL FAILED. PULL WIRELINE AND RIG UP SCIENTIFIC TOOL.

9:30AM: BACK TO TIME DRILLING. HAVING PROBLEMS ORIENTING THE MOTOR. WILL HAVE TO DRILL A LITTLE AND WORK IT AROUND. NOW FACING 120 DEGREES TO THE RIGHT.

12:30PM: TRYING TO RESTART MOTOR. WILL NOT RESTART. DECIDED TO TRIP OUT OF HOLE TO EXAMINE MOTOR.

4:00PM: TRIP OUT OF THE HOLE.

5:00PM: RIG REPAIR

6:00PM: CONTINUE TRIP OUT OF HOLE.

7:00PM: CHANGE MOTOR.

9:00PM: START IN THE HOLE WITH NEW MOTOR AND 2 1/2 DEGREE BENT SUB.

11:30PM: ON BOTTOM. RUN WIRELINE STEERING TOOL. START DRILLING WITH MOTOR. RUNNING 2100 SCFM OF AIR ON THE FIRST 30 FEET. THEN STARTED RUNNING 3150 SCFM. PRESSURE IS 250 PSI.

11-21

3:30AM: THE STEERING TOOL FAILED. DRILLED THE REMAINING 15 FEET OF KELLY DOWN. PULL THE STEERING TOOL. PROBE HAD FAILED. CHANGE PROBE.

5:30AM: STEERING TOOL IS BACK ON BOTTOM. HAD 30 FEET OF FILL. BEFORE THE MOTOR COULD BE REAMED TO BOTTOM, THE STEERING TOOL FAILED AGAIN. PULL STEERING TOOL.

6:30AM: WIRELINE CONNECTION HAD FAILED. REHEAD STEERING TOOL. THE GEARHART WIRELINE IS SLIGHTLY UNDER GAUGE AND DOES NOT FIT INTO THE SCIENTIFIC EQUIPMENT PERFECTLY. THE UNDER GAUGE PROBLEM CONTRIBUTED TO THE FAILURE. RUN STEERING TOOL WITH A GEARHART CONNECTION.

8:00AM: RIG WIRELINE AND TRY TO DRILL. PROBE FAILED BEFORE TOOL FACE COULD BE ORIENTED. CHECKED PROBE AND HEAD CONNECTION. HEAD CONNECTION APPEARS TO BE THE PROBLEM. WILL SWITCH BACK TO THE SCIENTIFIC HEAD.

10:30AM: A. SHANE CO. ON LOCATION TO REPAIR THE ONAN GENERATOR. SHAFT IN THE FUEL INJECTOR PUMP WAS BROKEN. REPLACE THE FUEL INJECTOR PUMP.

11:00AM: ON BOTTOM WITH THE STEERING TOOL. HAVING PROBLEMS ORIENTING THE DOWNHOLE MOTOR. IT WANTS TO GO TO THE LEFT. FINALLY HAD TO LET IT DRILL OFF TO THE RIGHT. WERE TWISTING UP BLOCKS TRYING TO GET ENOUGH TORQUE IN THE DRILL STRING.

12:00PM: STARTED DRILLING. DRILLED TO 3421 FEET AND THE SCIENTIFIC TOOL FAILED AGAIN. PULL WIRELINE AND START OUT OF THE HOLE TO PICK UP A 3 DEGREE BENT SUB. LAST INCLINATION WAS 48.8 DEGREES WHICH IS ABOUT 5 DEGREES BEHIND SCHEDULE. NEED TO BUILD ALMOST 6 DEGREES PER 100 TO REACH THE TARGET.

1:00PM: THE PROBE ON THE STEERING TOOL HAD FAILED AGAIN. 3000 SCFM IS TOO MUCH AIR TO RUN WITH THE PROBE. WILL HAVE TO CUT IT BACK TO 2100 SCFM AND RUN ENOUGH MIST TO CLEAN THE HOLE.

3:30PM: THE CROSSOVER SUB AND FLOAT SUB ARRIVED FROM TRI-STATE.

4:00PM: OUT OF THE HOLE. SCIENTIFIC PUT A NEW STABILIZER ONB THE STEERING TOOL. CUT IT TO JUST BARELY FIT INSIDE THE CROSSOVER SUB ABOVE THE MONELS. THE X-O IS ABOUT 1/8" SMALLER THAN THE MONELS. CHANGE BENT SUB TO 3 DEGREES. PUT FLOAT SUB ON THE BIT AND REMOVE THE FLOAT SUB ON TOP OF THE MOTOR.

5:30PM: START IN THE HOLE.

7:30PM: RAN IN TO WITHIN 2 STANDS OF BOTTOM (120 FEET) AND THE STRING TOOK WEIGHT. PICK UP KELLY JOINT AND WASH 60 FEET. RAN THE NEXT JOINT WITHOUT ANY TROUBLE.

8:30PM: RUN WIRELINE STEERING TOOL.

9:00PM: WASH 40 FEET TO BOTTOM AND ORIENT THE MOTOR. STARTED DRILLING AGAIN. HOLE IS UNLOADING IN SLUGS.

10:00PM: DRILLED KELLY DOWN. MAKE A CONNECTION AT 3442 FEET. SURVEY IS 57 DEGREES. ONLY BUILT 4.4 PER 100 FEET WHICH IS NOT ENOUGH.

8:00AM: DRILLING AT 3657 FEET. MOTOR BUILT 6 DEGREES PER 100 FEET THEN 4.4 DEGREES PER 100 FEET. CANNOT REACH TARGET OF 3400 TVD WITH THE PRESENT ASSEMBLY. WILL HAVE TO BUILD 10 DEGREES PER 100 FEET.

8:30AM: TRIP BECAUSE THE WELL IS NOT BUILDING FAST ENOUGH. CONSIDERING OPTIONS WITH AL YOST. DEPTH IS 3666 FEET. WILL RUN A SURVEY.

9:00AM: HOLE IS TIGHT. CAN PULL 140000 LBS WITHOUT THE PIPE MOVING. PUT AIR ON THE DRILL STRING AND THE STRING COMES UP AT 80000 WITHOUT ANY TROUBLE. PUMPED A TOTAL OF 12 JOINTS OUT OF THE HOLE, THEN THE PIPE CAME FREE.

12:30PM: RUN SINGLES BACK IN THE HOLE TO SURVEY WITH SCIENTIFIC'S SINGLESOT. NO HOLE DRAG AT ALL GOING IN. HAD 40 FEET OF FILL ON BOTTOM.

2:00PM: CIRCULATE THE HOLE WITH 3150 SCFM AND DOUBLE THE SOAP CONCENTRATION IN THE MIST.

3:00PM: SURVEY. STEERING TOOL SAYS 58.8 DEGREES AND THE SINGLESOT SAYS 57.5 DEGREES. DEFINITELY CANNOT HIT THE TARGET UNLESS BUILDING MORE THAN 10 DEGREES PER 100 FEET. THAT WOULD REQUIRE A BENT HOUSING AND BENT MOTOR COMBINATION. STILL GOING OVER THE OPTIONS.

4:00PM: PULL OUT OF THE HOLE. HAD TO PUMP OUT 10 STANDS. SAME PROBLEM AS BEFORE. CIRCULATING DIDN'T HELP. THE CUTTINGS ARE PROBABLY TOO BIG TO BE LIFTED OUT OF THE HOLE WITH AIR. THE BROWN SHALE MAY BE SLOUGHING. SAMPLES DO NOT INDICATE EXCESSIVE CONTAMINATION, BUT SOME CONTAMINATION

5:00PM: HAVE DECIDED TO PLUG BACK AND REDRILL THE HOLE. IT SEEMS THE SLOW BUILD RATE OF THE MOTORS CORRELATES WITH THE BROWN SHALE ACCORDING TO OFFSET LOGS AND THE MUD LOGGERS REPORT. SPECULATE THAT WE WILL NOT BE ABLE TO BUILD 10 DEGREES PER 100 FEET IN THE HURON SHALE AT 3666 FEET AND THEREFORE WOULD MISS THE TARGET BY QUITE A BIT BUT WOULD STILL BE IN THE LOWER HURON. WILL SIDETRACK AT ABOUT 3300 FEET AND GO OUT THE HIGH SIDE OF THE HOLE. NEED THE BENT HOUSING AND BENT SUB COMBINATION TO ACCOMPLISH THIS. ORDER OUT THE ALIGN-A-SUB FROM EASTMAN. HAVE TRI-STATE MAKE A FLOAT SUB CROSSOVER FOR THE BOTTOM OF THE MOTOR. ORDER OUT 210 SACKS OF NEAT CEMENT FROM HALLIBURTON.

9:00PM: OUT OF THE HOLE. LAY DOWN THE BHA. RUN PIPE IN OPEN ENDED TO THE BOTTOM OF THE HOLE.

10:00PM: WAITING ON HALLIBURTON TO ARRIVE ON LOCATION. PIPE IS AT THE BOTTOM OF THE CASING.

11:00PM: HALLIBURTON ARRIVED ON LOCATION. TRIP PIPE TO BOTTOM. RIG UP HALLIBURTON.

11-23

1:00AM: PLUG BACK WITH 36 BARRELS OF WATER FOLLOWED BY 210 SACKS OF CLASS "A" CEMENT CONTAINING 3% CALCIUM CHLORIDE (MIXED AT 1.18 CUBIC FEET PER SACK AND 15.6 PPG). DISPLACED WITH 5 BARRELS OF WATER. VOLUME IS 10% EXCEEDS OVER CALCULATED HOLE SIZE. PULLED PIPE OUT OF THE HOLE. NO PROBLEM GETTING IN OR OUT OF THE HOLE WITH THE OPEN ENDED DRILL PIPE. HAD ABOUT 20 FOOT OF FILL ON BOTTOM.

4:00AM: PICK UP BIT, FLOAT SUB, 3 PT, 2-8" MONELS, 3PT AND X-O. TRIP IN THE HOLE.

8:00AM: REAM A TIGHT SPOT AT 2500 FEET. ONLY REAMED 30 FEET AND IT DIDN'T REAM HARD.

RAN PIPE TO 3250 FEET. PICK UP KELLY AND START REAMING. REAMED PRETTY HARD. RUNNING A LOT OF WEIGHT TO MAKE SURE WE STAY IN THE SIDETRACKED HOLE. TAGGED UP ON CEMENT AT 3270 FEET. DRILLED RATTY CEMENT TO 3300 FEET. THE LAST 10 FEET SEEMED LIKE PRETTY GOOD CEMENT.

12:00PM: CIRCULATE TO CLEAN HOLE WITH 3150 SCFM. FOAM IS COMPLETELY WHITE AFTER CIRCULATING 1 HOUR.

1:00PM: RUN SINGLE SHOT SURVEY TO MAKE SURE OF WHICH HOLE THE PIPE IS IN. REAMED PRETTY HARD FROM THE KICKOFF POINT DOWN. SINGLESOT READ 47 DEGREES S34E AT 2380 FEET. NO FILL ON BOTTOM WHILE TAKING A SURVEY.

3:00PM: TRIP OUT OF THE HOLE. NO EXCESS HOLE DRAG. HOLE IS CLEAN.

5:30PM: WAITING ON EASTMAN ALIGN-A-SUB. TRI-STATE SAID THAT THEY HAD TO WAIT FOR EASTMAN TO SEND THE TRUCK WITH THE EQUIPMENT. TRUCK LEFT TRI-STATE AT 1:30 PM.

7:00PM: TRUCK ARRIVED WITH THE EQUIPMENT EXCEPT THE TORQUE GAUGE AND THE ALIGN-A-SUB. NOTE SAID THAT THE SUB WILL BE IN CHARLESTON AT 10:30 PM ON PIEDMONT AIRLINES. WAYNE WITH SCIENTIFIC WENT AFTER IT. WAITING ON EASTMAN ALIGN-A-SUB. DOING RIG MAINTAINANCE WORK.

11-24

12:00AM: WAYNE CALLED AND SAID THE SUB NEVER ARRIVED. CALL AND TALK TO EASTMAN WHIPSTOCK. THEY DON'T KNOW WHERE IT IS. GOING TO TRY ALL THE BENT SUBS AND SEE IF ANY OF THEM WILL LINE UP WITH THE MOTOR TOOL FACE WHEN MADE UP. WANTED TO RUN THE 2 DEGREE SUB BUT IT LINED UP ABOUT 120 DEGREES OFF. TRIED THE 1.5 DEGREE SUB AND IT LINED UP ALMOST PERFECT. IT IS ONLY ABOUT 10 DEGREES OFF OF THE MOTOR TOOL FACE AND OTTO CAN'T DRAW THE LINE UP THE MOTOR THAT STRAIGHT. LUCKED OUT.

2:00AM: TRIP IN THE HOLE. RUN WIRELINE STEERING TOOL.

4:00AM: ORIENTING THE DOWNHOLE MOTOR. THE STRAP ON THE REAMING RUN WAS OFF BY ONE STAND. DEPTH IS 3362 FEET. TAGGED CEMENT AT 3330 FEET. THE SURVEY DEPTH WAS 3340 FEET WITH THE SINGLESOT.

6:30AM: DRILLING WITH THE DOWNHOLE MOTOR. WOULD LIKE TO GET ABOUT 10 DEGREES PER 100 FEET OUT OF THE MOTOR SO THAT THE INCLINATION WILL BE AHEAD OF SCHEDULE. RIGHT NOW A LITTLE OVER 6 DEGREES PER 100 FEET IS REQUIRED.

9:00AM: THE STEERING TOOL SAYS 47.3 DEGREES AT THE KICK OFF POINT OF 3362 FEET.

9:30AM: CONNECTION AT 3413 FEET. SURVEY SAYS 49.6 DEGREES AT 3373 FEET. BUILD RATE CALCULATES OUT TO BE 20 DEGREES PER 100 FEET. SURVEYS ARE TOO CLOSE TOGETHER. NOTE THAT THE CREW WAS NOT RUNNING KCL IN THE MIST. HAD THEM START ADDING IT TO THE SYSTEM AT 8:00 AM. THERE WAS A MISCOMMUNICATION WITH THE DRILLING CREW.

11:00AM: MOTOR STALLED AT 3426 FEET. SURVEYED AND THE SURVEY INDICATED BUILDING AT 14 DEGREES PER 100 FEET. SURVEYS ARE STILL TOO CLOSE TOGETHER TO COMPLETELY BELIEVE THE RESULTS. BROOKS WITH EASTMAN CALLED AND SAID THAT THE SUB WOULD BE IN CHARLESTON AT 3:30 PM. HE IS MAKING

ARRANGEMENTS TO HAVE IT SHIPPED TO THE LOCATION.
KCL MAY BE WHY THE MOTORS ARE STALLING (NOT COMPLETELY
DISSOLVED). WILL LEAVE OUT KCL FOR A WHILE AND SEE IF IT
HELPS.

1:00PM: SURVEY INDICATES THE MOTOR IS BUILDING AT 6.1
DEGREES PER 100 FEET. WILL TAKE SURVEYS EVERY 30 FEET TO
CHECK PERFORMANCE. INCREASED FREQUENCY JUST CAUSES
ERRONEOUS RESULTS. NEED TO BUILD 6.3 PER 100 FEET TO HIT THE
TARGET.

5:00PM: CONNECTION AT 3508 FEET. WELL IS BUILDING ABOUT 6.5
DEGREES PER 100 FEET. NEED JUST OVER 6 PER 100 TO HIT
TARGET. EVERYTHING IS ON COURSE. SCIENTIFIC'S TOOL
INDICATES THAT WE ARE GETTING SOME MAGNETIC INTERFERENCE
POSSIBLY FROM THE FISH SINCE THE HOLE IS DIRECTLY UNDER IT.

7:00PM: THE ALIGN-A-SUB ARRIVED ON LOCATION. SURVEY AT
3500 FEET INDICATES STILL BUILDING AT 6.5 DEGREES PER 100
FEET.

11-25

12:00AM: CONNECTION AT 3603 FEET. INCLINATION IS 62.2
DEGREES AT 3563 FEET. BUILT 7.4 PER 100 ON LAST 30 FEET.
NOW NEED JUST LESS THAN 6 PER 100 TO HIT THE TARGET. HAD A
GOOD GAS SHOW AT ABOUT 3600 FEET. THE UNITS CAME UP TO
75000 PPM.

3:00AM: SURVEY AT 3594 FEET IS 64.5 DEGREES. DEPTH IS 3634
FEET. MOTOR WOULD NOT RESTART. BUILD RATE IS STILL 7.4
PER 100 FEET. NOW ONLY NEED 5.6 PER 100 TO HIT THE TARGET.
HAVE BEEN RUNNING 2100 SCFM AND 25 TO 30 BBLs PER HOUR MIST
TO CLEAN THE HOLE. HOLE FOAMS PRETTY GOOD. KCL MAY NOT BE
THE PROBLEM WITH THE MOTORS SINCE THIS ONE HAS HAD TO BE
RESTARTED WITH WATER ALMOST EVERY TIME SINCE 7:00 PM
YESTERDAY. GAS FLARES WHILE MAKING A CONNECTION. THE
MOTOR HAS BEEN BUILDING AT A VERY CONSTANT RATE OF 6.5 TO
7.5 PER 100 FEET EVEN IN THE FRIABLE SHALE SECTIONS.
FORMATION DOESN'T SEEM TO MAKE AS MUCH OF A DIFFERENCE.

4:00AM: PULL OUT OF THE HOLE. THE HOLE WAS A SLIGHT BIT
TIGHT IN A COUPLE OF SPOTS DURING THE FIRST 3 STANDS. NEVER
HAD TO PUT THE AIR ON IT AND NEVER PULLED MORE THAN 20000
LBS OVER THE UP DRAG WEIGHT OF 80000 LBS.

8:00AM: OUT OF THE HOLE. THE BIT IS NOT IN VERY GOOD SHAPE.
WILL RUN BIT #9 BACK IN THE HOLE. CHANGE OUT MOTORS.

3:00PM: BACK IN HOLE NEAR BOTTOM WITH 1.5 BENT SUB,
ALIGN-A-SUB, 2 DEG. BENT HOUSING MOTOR, X-O FLOAT SUB AND
BIT NO. 9. STEERING TOOL WONT WORK. STOWERS MOTORS
DELIVERED 4109' OF 24# 8 5/8 CASING FROM APPAL. PIPE.
JENNIFER FAILED TO SEND THE PROPER PD TO APPAL. PIPE.
WILL SEND 1823 BACK AND ASK DAVE FOX TO FIND THAT MUCH 28#
PIPE.

4:30PM: REWORKED HEAD ON STEERING TOOL, FUNCTIONING
OK. BACK ON BOTTOM, START MOTOR. FOUND 60' OF FILL-UP FROM
SLOUGHING HOLE CONDITIONS. CLEANING HOLE

5:00PM: START DRILLING. DRILLED 3 FEET AND MAKE A
CONNECTION.

5:30PM: MOTOR DRILLED 10 FEET AND STALLED. HAD TO RESTART WITH WATER. DRILLED 2 FEET AND STALLED. HAD TO RESTART WITH WATER. DRILLED 5 FEET AND STALLED. THE MOTOR IS NOT WORKING RIGHT. THE TORQUE IS IRRATIC WHEN ON BOTTOM. CAN'T RUN ANY WEIGHT ON THE MOTOR.

10:00PM: DRILLED A TOTAL OF 33 FEET WITH THE MOTOR. STILL CAN'T RUN ANY WEIGHT. STARTED A THIRD COMPRESSOR AND THE MOTOR TOOK OFF DRILLING. NOW DRILLING OK.

11-26

12:30AM: FINISHED SURVEY. SURVEY AT 3661 FEET IS 69 DEGREES. NEED TO BUILD 5.2 PER 100 TO HIT TARGET. BUILT 6.7 ON THE LAST 60 FEET.

3:00AM: SURVEY IS 72.2 DEGREES AT 3725 FEET. BUILT 5 PER 100 IN LAST 60 FEET. NEED TO BUILD 5.3 PER 100 TO HIT TARGET.

8:00AM: DEPTH IS 3827 FEET. SURVEY IS 76.3 DEGREES AT 3787 FEET. BUILD RATE WAS 6.6 PER 100 FEET IN THE LAST 60 FEET. NOW NEED 4.5 PER 100 TO HIT THE TARGET. MOTOR WOULD NOT RESTART. PULLED ONE STAND AND THE KELLY JOINT WHEN THE HOLE GOT TIGHT. HAVING TO PUMP OUT SINGLES. AS LONG AS THE AIR IS ON THERE IS NO DRAG.

12:30PM: HAD TO PULL 11 JOINTS OUT WITH AIR ON. PULLED ONE STAND AND IT GOT TIGHT AGAIN. PUMP OUT ONE MORE JOINT. THE REST IS COMING OUT OK. THE MAJOR PROBLEM THIS TIME IS THAT THE PIPE WON'T GO BACK DOWN AFTER PICKING IT UP PAST THE TIGHT SPOTS.

3:00PM: OUT OF THE HOLE. PICKING UP REAMING ASSEMBLY WHICH INCLUDES A BIT, MONEL, REAMER, MONEL. WILL REAM THE SIDETRACK WITH A PILOT.

4:30PM: TRIP IN THE HOLE. START REAMING AT 3300 FEET.

6:30PM: STARTED AIR PACKAGE. THE ASSEMBLY IS NOT TORQUING AT ALL GOING TO BOTTOM. REAMING EACH JOINT DOWN AND CIRCULATING 15 TO 20 MINUTES AFTER EACH CONNECTION.

11-27

12:00AM: CIRCULATE FOR ONE HOUR TO CLEAN HOLE.

1:00AM: SURVEY WITH THE STEERING TOOL. STEERING TOOL FELL TO 3600 FEET AND READ 67.7 DEGREES. PUMPED TOOL TO BOTTOM. STEERING TOOL READ 77 DEGREES. TAKE SURVEY. SURVEY SAID 74 DEGREES S36E AT 3807 FEET.

2:30AM: CIRCULATE DRY AIR FOR 1.5 HOURS TO GET THE FOAM OUT OF THE HOLE BEFORE LOGGING WITH THE TV CAMERA.

4:00AM: START OUT OF THE HOLE. PULLED 1.5 STANDS AND THE HOLE GOT TIGHT. COULD NOT PULL OUT OF THE HOLE WITHOUT THE AIR ON. COULD NOT GO BACK DOWN AFTER CIRCULATING. HAD A LOT OF TROUBLE GETTING OUT OF THE HOLE. PULLED 8 STANDS BEFORE THE PIPE CAME FREE.

8:00AM: FINISH TRIP OUT OF THE HOLE.

10:00AM: OUT OF THE HOLE. RIG UP TO RUN THE TV CAMERA.

5:00PM: FINISHED RUNNING THE TV CAMERA. GOT TO 3142 FEET BEFORE THE CAMERA STOPPED. THE LOW SIDE OF THE HOLE HAD ABOUT 2 TO 3 INCHES OF BALLED UP CUTTINGS ON THE BOTTOM OF THE INCLINED WELLBORE. HOLE IS EXTREMELY DIRTY. CAN'T CLEAN THE HOLE WHEN DRILLING WITH DOWNHOLE MOTORS. RIG DOWN THE LOGGERS.

6:00PM: LAY DOWN THE 8" MONELS.

7:00PM: START IN THE HOLE WITH A BIT, X-O, FS AND DRILL PIPE TO CLEAN THE HOLE. WILL RUN 8 5/8" CASING. CONTINUING TO DRILL WILL ONLY LOAD THE HOLE FURTHER WITH CUTTINGS AND COMPOUND THE PROBLEM.

8:30PM: GOT TO 3380 FEET AND SET DOWN. PICK UP KELLY AND START WASHING TO BOTTOM. COULD NOT PUSH DOWN THROUGH THE HOLE WITH THE AIR ON. HAD TO ROTATE AND DRILL THROUGH IT. CIRCULATING BEFORE EACH CONNECTION.

12-28

1:00AM: CIRCULATE TO CLEAN HOLE. HAVE BEEN RUNNING 4200 SCFM AND 30 BBLs MIST. CIRCULATED FOR 1.5 HOURS AND WORKED THE PIPE.

2:30AM: MAKE A 10 STAND SHORT TRIP (600 FEET) TO CHECK HOLE CONDITIONS. HAD NO TROUBLE PULLING THE PIPE OUT OF THE HOLE. PIPE STOPPED AT 3600 FEET ON THE WAY IN.

DAILYLOG PART 3, STARTING AT 3:00 AM ON 11-28-86.

3:00AM: REAM BACK TO BOTTOM FROM 3600 FEET. RUNNING 4200 SCFM OF AIR.
5:00AM: BACK ON BOTTOM. CIRCULATE TO CLEAN THE HOLE.
7:00AM: START OUT OF THE HOLE. PULLED 2 1/2 STANDS AND HAD TO PUMP THE PIPE OUT OF THE HOLE.
10:00AM: OUT OF THE HOLE. RIG UP DRESSER AND RUN LOGS. LOGS WENT TO 3620 FEET BEFORE THEY STOPPED. HOLE GAUGE AVERAGES 11.5 TO 12 INCHES. THE GREY SHALES HAVE THE LARGEST WASHOUTS OF ABOUT 14 INCHES. THE BROWN SHALES SHOW MOSTLY IN GAUGE. THE LOG INDICATES A FEW TIGHT SPOTS IN THE HOLE AROUND 3385 AND 3285 WHERE THE CALIPER READS LESS THAN 4 INCHES. WILL MAKE ONE MORE CLEANING RUN.
1:30PM: RIG DOWN DRESSER.
2:30PM: TRIP IN THE HOLE TO THE END OF THE CASING.
4:30PM: BLOW HOLE WITH AIR ONLY. STAGE IN THE HOLE TO 3200 FEET.
7:30PM: START RUNNING SINGLES AND REAMING EACH JOINT. RUNNING 3100 SCFM OF AIR. CIRCULATE 30 MINUTES ON EACH CONNECTION.

11-29

3:30AM: STARTED HITTING TIGHT SPOTS AT 3600 FEET. REAMED THROUGH THEM.
4:30AM: PIPE DEPTH IS 3650 FEET. SHORT TRIP 6 STANDS (360 FEET) TO CHECK HOLE. HOLE WAS TIGHT IN PLACES ON THE FIRST 2 STANDS OUT. WORKED PIPE THROUGH ALL BUT ONE SPOT AT 3550 FEET WITHOUT PUTTING THE AIR ON THE HOLE. RUN PIPE BACK TO 3650 FEET. REAMED FROM 3500 FEET DOWN. DID NOT TRY TO GO DOWN WITHOUT REAMING.
5:30AM: REAMING TO BOTTOM ONE JOINT AT A TIME.
8:30AM: HIT FLUID 60 FEET OFF BOTTOM. WASH THROUGH AND CIRCULATE 30 MINUTES.
9:00AM: TAG BOTTOM. CIRCULATE TO CLEAN AND DRY HOLE.
11:00AM: TRIP OUT OF HOLE. HIT ONE TIGHT SPOT AT 3550 FEET. WAS ABLE TO WORK UP THROUGH IT PULLING 120,000 LBS. DID NOT HAVE TO PUT AIR ON THE HOLE. FINISH TRIP OUT OF THE HOLE.
1:00PM: OUT OF THE HOLE. BREAK OFF BIT AND SUBS. THE BOTTOM OF THE PIPE WAS COATED WITH CUTTINGS. NIPPLE DOWN WELLHEAD EQUIPMENT.
3:30PM: RIG UP POWER TONGS AND PREPARE TO RUN CASING.
4:00PM: PICK UP MOTOR AND ADJUST HOUSING TO 2 DEGREES. MAKE UP BIT AND TRY TO RUN IT INSIDE THE 8 5/8" CASING. WOULD NOT GO. CHANGED THE BEND TO 1.75 DEGREES. STILL WOULD NOT GO, BUT CLOSE. A STAND OF COLLARS PUSHING IT WOULD PROBABLY MAKE IT GO.
5:30PM: PICKUP AND RUN 8 5/8" CASING. INSTALLED 2 CENTRALIZERS ON THE FIRST JOINT AND ONE CENTRALIZER ON EACH COUPLING THEREAFTER FOR A TOTAL OF 9 CENTRALIZERS. RAN CASING WITH GUIDE SHOE AND FLOAT COLLAR ON TOP OF THE FIRST JOINT.
10:00PM: CASING SET DOWN AT 3543 FEET. PICK UP KELLY AND SWEDGE. CIRCULATE THROUGH THE BRIDGE. THE JOINT OF CASING CRUSHED IN THE SLIPS WHEN THE BRAKES SLIPPED BECAUSE THEY WERE WET. LAID DOWN THE JOINT AFTER WASHING THROUGH THE BRIDGE. HIT A SECOND BRIDGE AT 3582 FEET. WASHED THROUGH

IT ALSO.

11-30

1:00AM: THE NEXT TWO JOINTS RAN WITH NO PROBLEM. PIPE STOPPED AGAIN AT 3710 FEET. HAD TO WASH DOWN 50 FEET OF PIPE.

4:00AM: RAN THE LAST JOINT IN THE HOLE. CASING IS SET AT 3803 FEET KB. RIG DOWN THE POWER TONGS AND RIG UP HALLIBURTON. THE BOTTOM 1616 FEET IS 8 5/8", 32#, K-55, ST&C CASING (40 JOINTS) WITH 8 5/8", 24#, K-55, ST&C ON TOP. RAN ONE JOINT OF 32# CASING ON TOP.

5:30AM: CEMENT CASING WITH 5 BARRELS OF WATER, 75 BARRELS OF GELLED WATER, AND 5 BARRELS OF WATER FOLLOWED BY 150 SACKS OF CLASS "A" CEMENT CONTAINING 10 % SALT (MIXED AT 15.8 PPG AND 1.2 FT CUBED PER SACK). DISPLACED WITH 227 BARRELS OF WATER WHEN THE CASING PRESSURED UP 1500 PSI. DISPLACEMENT SHOULD HAVE BEEN 234 BARRELS. MAY HAVE LEFT CEMENT IN THE CASING. PLUG DOWN AT 6:30 AM.

7:00AM: TRIED TO CEMENT THE TOP 150 FEET OF CASING DOWN THE ANNULUS. THERE WAS TOO MUCH FOAM AND WATER IN THE ANNULUS AFTER CIRCULATING TO GET THE CEMENT TO FALL. WILL HAVE TO WELD IT TO THE 11 3/4" CASING. WAIT ON CEMENT.

1:00PM: CUT OFF 8 5/8" CASING. WELD ON A COLLAR. WELD 8 5/8" CASING TO THE 11 3/4" CASING.

4:00PM: FINISHED WELDING. START NIPPLING UP COMPANION FLANGE, ORBIT VALVE AND ROTATING HEAD. UNLOAD BAKER 2 6 3/4" BAKER MOTORS. LOAD 7 USED BAKER MOTORS AND RETURN TO LAFAYETTE.

6:00PM: NIPPLE UP THE WELLHEAD EQUIPMENT.

12-1

12:00AM: PICK UP THE BHA. BIT, FLOAT SUB, 6 1/4" MONEL, X-O, 6 1/4" MONEL. HAD TO CLEAN MUD OUT OF THE X-O SUB AND THE MONELS.

2:00AM: GO IN THE HOLE WITH THE BHA. HAD A LITTLE TROUBLE GETTING INTO THE WELLHEAD WHERE IT WAS WELDED. BLOW WATER OUT OF THE HOLE EVERY 500 FEET.

7:00AM: THE WELD BETWEEN THE 8 5/8" CASING AND THE 11 3/4" CASING BROKE AND THE 8 5/8" CASING MOVED UP THE HOLE 4 INCHES. THAT WAS JUST ENOUGH FOR THE AIR BODY TO OBSTRUCT OPERATIONS OF THE ROTARY TABLE. WILL HAVE TO CUT OFF THE CASING AND LOWER THE PREVENTER STACK. PULL ROTATING HEAD RUBBER AND TRIP OUT OF THE HOLE.

10:00AM: OUT OF THE HOLE. PULL ROTARY TABLE AND NIPPLE DOWN THE BOP STACK.

1:00PM: FINISHED NIPPLING DOWN. THE LOCAL WELDER ARRIVED BUT AFTER SEEING HIM CUT OFF A COUPLING FROM 8 5/8" CASING, IT'S NOT LIKELY HE CAN DO THE JOB. FIND MORE QUALIFIED WELDER. THE WELDER WE HAD LINED OUT BEFORE HAND WAS NOT HOME. HAVE A WELDER COMING FROM CHARLESTON. WAITING ON WELDER. GAS IS STARTING TO COME OUT OF THE 8 5/8" ANNULUS ALONG WITH WATER. TRIED DUMPING DIRT AND STUFFING RAGS IN THE ANNULUS TO STOP THE GAS FROM LEAKING. DID NOT WORK. CANNOT WELD WITH THE GAS COMING OUT. THERE IS NOT MUCH BUT ENOUGH TO PREVENT WELDING. PUT A RUBBER HOSE IN THE ANNULUS AND PACKED OFF THE ANNULUS WITH MUD. THE GAS IS NOW GOING

OUT THE HOSE AND NO LONGER PRESENTS A PROBLEM.

6:00PM: CUT OFF THE CASING AND WELD ON A COLLAR. CUT OFF APPROXIMATELY 6 INCHES.

10:00PM: NIPPLE UP ON THE CASING COLLAR AND INSTALL THE FLOW LINE.

12-2

1:00AM: RIG REPAIR. BUSHINGS.

2:30AM: TRIP IN THE HOLE. TAG FLOAT COLLAR AT THE RIGHT DEPTH.

4:30AM: DRILLED FLOAT COLLAR AND PLUG. HAD NO CEMENT IN THE SHOE JOINT. DRILLED GUIDE SHOE AND CEMENT IN THE OPEN HOLE SECTION.

7:00AM: DRILLER MAY HAVE SCREWED UP ON THE TALLY AND IS DEFINITELY DRILLING FORMATION. PROBABLY DRILLED 30 FEET OF NEW HOLE. CIRCULATE TO CLEAN THE HOLE.

8:00AM: START TRIP OUT OF THE HOLE. PULLED 2 STANDS AND THE HOLE BECAME TIGHT. HAD TO PICK UP THE KELLY. PULLED 2 MORE STANDS AND THE HOLE GOT TIGHT AGAIN. PICK UP KELLY. NO PROBLEM MOVING PIPE WIT AIR ON. HERE WE GO AGAIN. PULLED 2 MORE STANDS AND GOT TIGHT. PICK UP KELLY. PULLED ONE STAND AND IT PULLED TIGHT. PULLED AS MUCH AS 150,000 LBS. PICK UP KELLY.

11:00AM: FINISH TRIP OUT OF THE HOLE.

1:00PM: STRAP OUT OF THE HOLE IS 3860 FEET. DRILLED OVER 30 FEET OF FORMATION. WILL NOT HIT THE CENTER OF THE TARGET NOW. IT DEPENDS UPON HOW MUCH INCLINATION WAS LOST AS TO WHERE THE HOLE WILL END UP. THE ONLY THING TO DO IS DRILL THE HOLE AND FIND OUT WHAT THE SURVEY IS AT 3860 FEET.

3:00PM: PICKED UP MOTOR AND PUT A BEND IN IT BETWEEN 1 3/4 AND 1 7/8 DEGREES. BHA IS MOTOR, FLOAT SUB, MSS, MONEL, X-O, MONEL. TRIP IN THE HOLE.

5:30PM: HAD TO PICK UP THE KELLY 2 STANDS OFF BOTTOM AND REAM THROUGH THE AREA OF THE FLOAT COLLAR. WOULD NOT FALL THROUGH. RIGGED UP THE KELLY HOSE TO THE KELLY JOINT.

6:30PM: RIG UP AND RUN THE WIRELINE STEERING TOOL. WOULD NOT FALL TO BOTTOM. COULD NOT PUMP THE STEERING TOOL INTO THE MULE SHOE SUB. PULL WIRELINE AND CHANGE TO SMALLER MULE SHOE. STILL WOULD NOT GO.

8:30PM: PULL THREE STANDS TO RUN WIRELINE. RUN AND SEATED THE WIRELINE. HAD TO PUT THE KELLY ON TO GET THROUGH THE GUIDE SHOE. MAKE UP 60 FOOT KELLY.

10:30PM: START DRILLING WITH THE DOWNHOLE MOTOR.

12-3

2:00AM: THE MOTOR STALLED. COULD NOT RESTART IT. TRIED PUMPING WATER THREE TIMES.

3:30AM: DECIDED TO SURVEY BEFORE TRIPPING. PULL TO SIDE ENTRY SUB AND TRIP THE WIRELINE. RUN SCIENTIFIC'S SINGLESOT. TRIP TO BOTTOM. SURVEY. TRIP TO THE SIDE ENTRY SUB. PULL WIRELINE. NO SURVEY. THE TOOL HAD PARTIALLY BACKED OFF AND THE BULBS SHORTED OUT. RERUN SURVEY. SURVEY WAS 74.5 DEGREES S37E AT 3869 FEET. HAD LOST ONLY 1/2 DEGREE DRILLING WITH SLICK ASSEMBLY. NOW NEED TO BUILD 10 DEGREES PER 100 TO HIT BOTTOM OF THE TARGET. SIX DEGREES PER 100 WILL GIVE A TVD OF 3415 AT 90 DEGREES.

7:00AM: CIRCULATED AFTER THE SURVEY. THE MOTOR RESTARTED. RUN STEERING TOOL IN THE HOLE TO DRILL SOME MORE IF THE MOTOR WILL DRILL.

9:00AM: ON BOTTOM AND STARTED DRILLING. DRILLING SLOWLY TO BUILD ANGLE FASTER. RUNNING 3150 SCFM AND 25 BARRELS PER HOUR MIST.

1:30PM: KELLY DOWN AT 3980 FEET. PULL TO WIRELINE ENTRY SUB TO SURVEY. RAN THE SINGLESOT WITH THE STEERING TOOL TO SAVE SURVEY TIME. THE SURVEY WAS 81 DEGREES WHICH MEANS THE WELL IS BUILDING ABOUT 10 DEGREES PER 100 FEET. SIXTY MORE FEET SHOULD MAKE THE WELL OVER 90 DEGREES. WILL TRY TO GET MOTOR RUNNING ON BOTTOM.

4:00PM: RESTARTING MOTOR. HAD TO PUMP WATER THREE TIMES BEFORE THE MOTOR RESTARTED.

5:30PM: DRILLING WITH MOTOR. THE MOTOR DRILLED TO 3997 FEET WHEN IT STOPPED. THE STEERING TOOL FAILED AT THE SAME TIME.

6:30PM: PULL TO THE WIRELINE ENTRY SUB. HAD NO PROBLEM GETTING TO THAT POINT. COULD NOT RESTART THE MOTOR. TRIP OUT OF THE HOLE. PIPE DRUG ON THE 6TH STAND OUT. HAD TO PUT THE KELLY ON THE HOLE ON THE 7TH STAND OUT WHICH IS APPROXIMATELY 3600 FEET BIT DEPTH. THAT IS THE POINT WHERE THE CUTTINGS WILL FALL TO AND THEN BUILD UP. THE STEERING TOOL HAD THE SINGLESOT INSTRUMENT FAIL AND CAUSED IT TO SHUT OUT.

11:30PM: OUT OF THE HOLE. CHANGE MOTORS. HAD TO CHANGE THE BY-PASS IN THE MOTOR TO A BLANK. THE NEW MOTOR IS SET SLIGHTLY LESS THAN THE 1 7/8 DEGREE MARK.

12-4

4:00AM: START BACK IN THE HOLE. TRIP IN TO THREE STANDS OFF BOTTOM.

6:30AM: RUN STEERING TOOL. HAD TO PICK UP THE KELLY TWICE TO GET THE LAST THREE STANDS IN THE HOLE. ONCE THE AIR WAS ON, THE PIPE RAN DOWN THE HOLE WITH NO PROBLEM. HAD PROBLEMS GETTING THE THIRD AIR COMPRESSOR RUNNING.

8:00AM: START STANDBY COMPRESSOR. RUN PIPE TO BOTTOM.

9:30AM: START DRILLING. THE PEOPLE ARE HERE TO LAY THE PIPELINE.

11:30AM: KELLY DOWN AT 4043 FEET. SURVEY. PULL TO WIRELINE ENTRY SUB TO GET TOOL OUT. SURVEY DID NOT TAKE. TOO MUCH VIBRATION WHILE DRILLING.

1:00PM: RERUN SURVEY. TRIP TO BOTTOM. TRIP TO SIDE ENTRY SUB. PULL WIRELINE. SURVEY IS 88 DEGREES. SHOULD BE 92 DEGREES ON BOTTOM. TIME TO CORE. YEAH!!

4:00PM: RIG DOWN THE WIRELINE AND SHEAVES.

4:30PM: PULL OUT OF THE HOLE. DID NOT HAVE TO PICK UP KELLY.

6:30PM: OUT OF THE HOLE. BREAK DOWN THE BHA. PICK UP THE CORE BARREL. EASTMAN HAD FAILED TO SEND OUT ALL THE NECESSARY EQUIPMENT.

8:00PM: WAITING ON EASTMAN TO BRING OUT THE REST OF THE EQUIPMENT.

12-5

3:00AM: EQUIPMENT ARRIVED. PUT CORE BARREL TOGETHER.

5:00AM: TRIP IN THE HOLE. HAD TO START WASHING 200 FEET OFF BOTTOM.

8:30AM: ON BOTTOM. CIRCULATED ONE HOUR BEFORE STARTING TO CORE.

9:30AM: STARTED CORING. CORED 13 FEET REAL EASY. COULD NOT CORE ANY MORE THAN 14 FEET. CORE BARREL IS JAMMED.

11:00AM: STARTED OUT OF THE HOLE. PULLED TIGHT 7 STANDS OUT BUT WERE ABLE TO WORK IT FREE WITHOUT PICKING UP THE KELLY.

1:30PM: OUT OF THE HOLE. LAY DOWN CORE. HAD 13 FEET OF CORE IN THE BARREL. THE REST WAS CUTTINGS. STOPPED CORING BECAUSE THERE WAS NO MORE ROOM IN THE CORE BARREL. REMOVED BALL FROM CORE BARREL. THE AIR WILL NOW RUN THROUGH THE BARREL AND WASH OUT ANY CUTTINGS PRIOR TO STARTING TO CORE.

4:30PM: TRIP IN THE HOLE WITH THE CORE BARREL. HAD NO PROBLEMS GETTING TO BOTTOM.

7:00PM: ON BOTTOM. CIRCULATE ONE HOUR BEFORE STARTING TO CORE. THE AIR RATE WHILE CORING IS 2100 SCFM WITH ABOUT 256 BBLs OF MIST PER HOUR.

8:00PM: CORING. CORED FROM 4057 FEET TO 4086 FEET. ORIENTED CORE.

9:30PM: FINISHED CORING 30 FEET. STOPPED EVERY 2 FEET FOR MULTISHOT SURVEY. TRIP OUT OF THE HOLE. HAD A LOT OF TROUBLE GETTING OUT OF THE HOLE AT ABOUT 3600 FEET. HAD TO LAY DOWN 3 JOINTS WHILE CIRCULATING OUT OF THE HOLE. TOOK ABOUT 2 HOURS.

12-6

2:00AM: OUT OF THE HOLE WITH THE CORE BBL. RECOVERED 30 FEET OF CORE. CORE HAD NATURAL VERTICAL FRACTURES SPACED AT ABOUT 5 FOOT INTERVALS. PREVIOUS 13 FEET DID NOT HAVE ANY APPEARANT NATURAL FRACTURES. LAY DOWN THE CORE BARREL. THE MULTISHOT DATA SHOWS THE HOLE INCLINATION TO BE 92 DEGREES AT THE END OF THE MOTOR RUN AT 4043 FEET. WILL RUN A BUILDING ASSEMBLY TO CHECK AND SEE IF THE CORE BARREL HAS DROPPED INCLINATION.

5:00AM: PICK UP BUILDING ASSEMBLY CONSISTING OF BIT, FLOAT SUB, 3 POINT, AND THE MONELS. (DID NOT RUN THE MONELS WITH THE 30 FOOT CORE BARREL.)

6:00AM: TRIP IN THE HOLE.

8:30AM: STARTED TAKING WEIGHT 200 FEET OFF BOTTOM. PICKED UP KELLY AND STARTED REAMING TO BOTTOM. RUNNING 3150 SCFM AND 25 BBLs OF MIST PER HOUR.

11:00AM: STARTED DRILLING. DRILLED TO 4126 FEET.

12:30PM: CIRCULATING TO SURVEY.

1:30PM: TRIED TO SURVEY WITH THE SMALL WIRELINE UNIT BY PUMPING THE TOOL DOWN THE HOLE. THE FIRST TRIP IN DID NOT MAKE IT INTO THE MONELS. NO SURVEY. TRIED HARDER THE NEXT TIME. PULLED THE WIRELINE TO 3600 FEET AND IT WOULD NOT COME UP ANY MORE. HAD TO PULL THE WIRELINE IN TWO WITH THE RIG. PROBABLY PUMPED THE GEOGRAPH LINE BY THE SURVEY TOOL AND THEN IT HUNG COMING OUT OF THE HOLE. LEFT ABOUT 1500 FEET OF GEOGRAPH LINE IN THE HOLE.

4:00PM: TRIP OUT OF THE HOLE TO RECOVER THE SURVEY TOOL. PUMPED ONE HOUR TO CLEAN THE HOLE BEFORE PULLING OUT.
5:00PM: START OUT OF THE HOLE.
8:00PM: OUT OF THE HOLE. LAY DOWN THE BHA AND AND PICK UP THE CORE BARREL. RECOVERED THE SURVEY TOOL. IT WAS STUCK IN THE FLOAT SUB. HAD TO BEAT IT OUT. THE SURVEY SAID 2 1/4 DEGREES. TOOL FELL INTO THE MONELS AFTER GETTING INTO THE VERTICAL PORTION OF THE HOLE, THEN THE MONEL SENSOR WENT OFF.
10:00PM: TRIP IN THE HOLE WITH THE CORE BARREL.

12-7

12:30AM: ON BOTTOM WITH THE CORE BARREL. HAD NO PROBLEM GETTING TO BOTTOM. CIRCULATE ONE HOUR TO CLEAN THE HOLE.
1:30AM: STARTED CORING. CORED 30 FEET. MULTISHOT EVERY 2 FEET.
2:30AM: PULL OUT OF THE HOLE WITH THE CORE. HUNG UP A LITTLE WHILE PULLING OUT OF THE HOLE BUT WERE ABLE TO WORK PAST IT.
5:30AM: LAY DOWN THE CORE. CUT A FAULT AT 4140 FEET. HAD A GAS INCREASE TO 77,000 PPM WHEN IT WAS CUT BUT DIED RIGHT OFF. LAY DOWN THE CORE BARREL. GOT 100% RECOVERY. THERE WERE NOT MANY OTHER NATURAL FRACTURES EXCEPT RIGHT AT THE FAULT. THE MULTISHOT STILL READS 92 DEGREES ALL THROUGH THE DRILLED INTERVAL.
8:00AM: PICK UP THE BHA. BIT, FLOAT SUB, 3FT, 6 1/4" MONEL, X-O, 6 1/4" MONEL. TRIP IN THE HOLE.
11:00AM: HAD NOT PROBLEM GETTING IN THE HOLE. REAMED THE CORE HOLE AND TAGGED BOTTOM. THE CORE HOLE HAS ALWAYS REAMED EASY BUT DID HAVE TO BE REAMED.
12:00PM: START DRILLING. DRILLED 60 FEET TO 4221 FEET. DRIED THE HOLE OUT. CIRCULATED AND DRILLED 10 FEET AT A TIME FOR THE FIRST 30 FEET TO DRY THE HOLE. HOLE STARTED DUSTING AFTER THE FIRST 10 FEET. HOLE UNLOADED AFTER THE FIRST 30 FEET.
2:00PM: CIRCULATE 1/2 HOUR BEFORE SURVEYING.
2:30PM: TRYING TO SURVEY BY PUMPING THE SURVEY TOOL DOWN THE HOLE. USING THE GEARHART TRUCK SO THE WEIGHT INDICATOR CAN BE WATCHED. WELDED A ROPE SOCKET TO THE EASTMAN SINGLESLOT. PLACED A THICK RUBBER GASKET 3" IN DIAMETER ABOVE THE SURVEY TOOL TO HELP IT BE PUMPED DOWN. TOOL FEEL TO 4000 FEET FIRST TIME IN WITH 2100 SCFM. WOULD NOT FALL ANY FARTHER. PICKED UP AND TRIED WITH 3150 SCFM BUT WOULD NOT FALL FARTHER THAN 4000 FEET. WERE ABLE TO GET THE TOOL FARTHER DOWN THE HOLE BY SHAKING THE DRILL PIPE. WIRELINE DEPTH WAS 4200 FEET WHEN THE TOOL WOULD NOT FALL ANY FARTHER. PULL SINGLESLOT. HAD NO SURVEY. THE TOOL WAS NOT IN THE MONELS BECAUSE THE MONEL SENSOR NEVER TRIGGERED. TIME FOR PLAN 02.
5:30PM: TRIP OUT OF THE HOLE 10 STANDS TO 3600 FEET. NO TIGHT HOLE AT ALL WHILE PULLING THE PIPE. RUN SURVEY TOOL IN THE SIDE ENTRY SUB. CLAMP IT OFF AND TRIP TO BOTTOM. TAKE SURVEY. PULL 10 STANDS TO THE SIDE ENTRY SUB. PULL WIRELINE. THE SURVEY SAID 92 DEGREES S39E AT 4191 FEET. HOLDING ANGLE VERY WELL. TRIP TO BOTTOM. KINKED THE WIRELINE.

9:30PM: START DRILLING. WILL DRILL ABOUT 200 FEET BEFORE SURVEYING AGAIN. CIRCULATING 10 MINUTES BETWEEN EACH CONNECTION. DROPPED BIT WEIGHT FROM 25 TO 20,000 LBS TO SEE IF IT WILL DROP ANGLE A LITTLE.

12-8

4:30AM: DEPTH IS 4412 FEET. TIME TO SURVEY. CIRCULATE 1/2 HOUR.

5:00AM: SURVEY THROUGH SIDE ENTRY SUB. SURVEY READ 91 DEGREES S38E AT 4382 FEET. STILL HOLDING INCLINATION VERY WELL. NO TIGHT HOLE WHILE TRIPPING AT ANY TIME. THE DRY HOLE CLEANS BETTER.

9:00AM: BACK ON BOTTOM AND DRILLING. HLU 72000, HLD 54000, ROTATING 57000, TORQUE 1 ROUND. DEPTH IS 4412 FEET.

11:30AM: DECREASED DRILLING WEIGHT TO 15000 LBS TO SEE IF THE WELL WILL DROP INCLINATION A LITTLE FASTER. DEPTH IS 4482 FEET.

6:00PM: DRAG IS INCREASING. COMING UP OVER 80000 AND GOING DOWN AT 40000. WILL STOP AND CLEAN THE HOLE FOR A WHILE TO SEE IF THE DRAG CHANGES. EASTMAN TRUCK ARRIVED. LOADED OUT THE CORING EQUIPMENT AND 8" MONELS.

8:00PM: BACK TO DRILLING. DEPTH IS 4634 FEET.

9:30PM: ONE COMPRESSOR WENT DOWN. THE CREW TRIED TO RESTART IT AND USED UP ALL THE RIG AIR SO THERE WERE NO CONTROLS. DOWN FOR 1/2 HOUR.

11:00PM: STOPPED AT 4697 TO TAKE A SURVEY. 284 FEET FROM LAST SURVEY. CIRCULATE 1/2 HOUR.

11:30PM: PULL 17 STANDS TO SURVEY THROUGH SIDE ENTRY SUB. DRILLER SAID THE BIT WAS TORQUING A LOT MORE ON THE LAST CONNECTION. WILL TRIP FOR A BIT ON NEXT SURVEY.

12-9

4:00AM: FINISHED SURVEY. THE SEARHART LINE BIRD CAGED UNDER THE SIDE ENTRY SUB. WILL HAVE TO PULL AN EXTRA STAND ON THE NEXT SURVEY. DO NOT WANT TO CUT THE LINE SINCE IT WILL PROBABLY BE KINKED AGAIN. SURVEY WAS 90 DEGREES S37E AT 4666 FEET. JUST RIGHT. IF THE WELL CONTINUES TO DROP 1/3 DEGREE PER 100 FEET, IT WILL BE AT THE BOTTOM OF THE SHALE AT 6000 FEET. RIGHT NOW THE WELL IS TO THE LEFT OF THE S37E LINE SO RIGHT HAND WALK WILL BRING IT BACK IN LINE. START TRIP OUT OF THE HOLE.

7:00AM: OUT OF THE HOLE. THE BIT IS NOT IN BAD SHAPE. COULD HAVE GONE A LOT FARTHER. BOTTOMHOLE REAMER WAS ONLY SLIGHTLY OUT OF GAUGE. RERAN SAME ASSEMBLY. CHANGED AIR HEAD RUBBER.

8:00AM: START IN THE HOLE. THE DRESSER LOGGING EQUIPMENT ARRIVED. HAD TO TOW THE TRUCK IN BECAUSE IT IS RAINING AGAIN. IMAGINE THAT! FORTUNATELY THE ARK IS ALMOST FINISHED.

10:00AM: FINISHED TRIP IN THE HOLE. NO PROBLEM GOING RIGHT TO BOTTOM. STARTED DRILLING.

7:00PM: HLU: 82000, HLD: 49000, ROTATING: 53000, 1.5 ROUNDS AT 4854 FEET.

12-10

3:00AM: SURVEY AT 5013 FEET. PULLED 23 STANDS TO PUT THE SIDE ENTRY SUB IN THE HOLE.

7:00AM: OUT OF THE HOLE WITH THE FIRST SURVEY. THE PICTURE WAS BLANK. WILL HAVE TO RERUN IT. TRIP BACK IN WITH THE SURVEY.

10:00AM: SURVEY WAS GOOD. READS 89 DEGREES S35E AT 4983'. STILL DROPPING ABOUT 1/3 DEGREE PER 100 FEET AND WALKING TO THE RIGHT.

11:00AM: BACK ON BOTTOM AND DRILLING. NOW RUNNING 20000 LBS ON THE BIT BECAUSE WEIGHT SEEMS TO MAKE NO DIFFERENCE. DRILLS FASTER. THE DRD PROGRAM INDICATES THAT WEIGHT SHOULD MAKE NO DIFFERENCE EITHER.

1:30PM: HLU: 79000, HLD: 46000, ROTATING: 54000, TORQUE 2 RDS, AT 5077 FEET.

11:00PM: DRILLING SOME HARD STREAKS BUT THE MUD LOGGER SAYS THE FORMATION HASN'T CHANGED. SOME OF IT DRILLS 5 TO 10 MINUTES PER FOOT.

12-11

4:00AM: TIME FOR ANOTHER SURVEY. BLOW HOLE FOR 1/2 HOUR. TRIP 28 STANDS TO INSTALL SIDE ENTRY SUB. THE WIRELINE IS GETTING VERY HEAVY AND HARD TO PULL BACK WHEN MAKING UP STANDS. CAN'T KEEP GOOD TENSION ON THE WIRE.

9:00AM: OUT OF THE HOLE WITH THE SURVEY. READS 88.5 DEGREES S34E AT 5298 FEET. JUST WHAT ONE WOULD EXPECT. KINKED THE WIRELINE SO THAT IT WILL HAVE TO BE CUT. THERE IS NO WAY TO KEEP ENOUGH TENSION ON IT AND PULL IT OUT OF THE WAY TO MAKE UP OR BREAK OUT A STAND. IT IS TOO HEAVY. WILL PROBABLY KINK THE WIRELINE ON EACH SURVEY. SURVEYING IS GOING TO GET VERY EXPENSIVE. WILL SURVEY AS LITTLE AS POSSIBLE. SERVICE RIG.

9:30AM: START BACK IN THE HOLE.

10:30AM: ON BOTTOM. HAVE TO REPAIR THE RIG. THE ROTARY HOSE BROKE.

11:30AM: STARTED DRILLING. WITH 20000 LBS.

4:00PM: WENT TO MAKE A CONNECTION AT 5452 FEET. THE PIPE WOULD NOT GO BACK IN THE GROUND. THE MUD LOGGER SAID WE JUST CUT A FRACTURED INTERVAL. COULD BE SLOUGHING IN. HAD TO PULL 3 JOINTS BEFORE IT WOULD FALL BACK IN THE HOLE. REAMED THE 3 JOINTS BACK TO BOTTOM. STILL RUNNING ABOUT 20000 COMING DOWN.

6:30PM: BACK TO DRILLING. CUT DRILLING WEIGHT BACK TO 15000 JUST IN CASE HOLE CLEANING IS THE PROBLEM.

7:30PM: DRILLED TO 5484 FEET AND PICKED UP THE KELLY TO SEE IF IT WOULD FALL. IT WOULD NOT. REAMED THE KELLY BACK DOWN. TOOK 10 MINUTES AND 25000 LBS TO REAM THROUGH A SPOT NEAR 5475 FEET. BUT THERE IS NO MORE TORQUE. TORQUE IS STILL 1.5 TO 2 ROUNDS. PULLING 100000 AND GOING DOWN AT 20000 IF IT GOES DOWN. EACH TIME THE KELLY GOES THROUGH THE SAME SPOT, IT TAKES A LOT OF WEIGHT TO REAM THROUGH IT.

SET KELLY BACK TO PULL A FEW JOINTS. PULLED THE FIRST JOINT AND THE PIPE WOULD GO BACK IN THE HOLE. PICKED UP THE KELLY AND IT WENT IN WITHOUT ROTATING. PUT AIR ON THE HOLE AND IT WENT IN BUT A LITTLE HARDER. STRANGE. SOMETHING IS NOT RIGHT. HAVE A PROBLEM SOMEWHERE. WILL DRILL ANOTHER JOINT.
10:00PM: STARTED DRILLING. DRILLING THREE TO SIX MINUTES PER FOOT WITH 20000 TO 25000 LBS PER FOOT. MAY HAVE TO PULL THE ASSEMBLY.

10:30PM: STARTED DRILLING RIGHT. ABOUT 2 MINUTES PER FOOT.

11:30PM: SLOWED WAY DOWN TO ABOUT 30 MINUTES PER FOOT AT 5507 FEET. MUD LOGGER SAYS THE SAMPLES HAVE NOT CHANGED ENOUGH TO CAUSE IT. KICKED OUT ROTARY TABLE AND THE WEIGHT INDICATOR JUMPED FROM 20000 LBS TO 40000 LBS. THE KELLY IS HANGING UP IN THE BUSHINGS AND TAKING THE WEIGHT. THE WEIGHT IS NOT MAKING IT TO THE BIT. THAT IS WHY IT WON'T DRILL. THE PROBLEM IS NOT RELATED TO THE BOTTOM OF THE HOLE AT ALL. WILL HAVE TO DRILL BY PENETRATION RATE THROUGH THAT PORTION OF THE KELLY.

12-12

12:00AM: DRILLING PROBLEM IS SOLVED BUT THE PIPE STILL WILL NOT FALL BACK IN THE HOLE. PULLED 5 JOINTS BEFORE IT WOULD RUN BACK IN. REAMED THE 5 JOINTS BACK IN THE HOLE. STILL HAVING PROBLEMS MAKING THE CONNECTIONS. JUST GETTING TOO MUCH PIPE IN THE HORIZONTAL PORTION OF THE HOLE TO BE ABLE TO PUSH WITH JUST THE DRILL STRING. DRILLED ONLY 10 FEET IN THE LAST HOUR ON THE PREVIOUS KELLY. HOLE SHOULD HAVE BEEN PRETTY CLEAN. THERE WERE NO CUTTINGS COMING OUT OF THE HOLE.

5:00AM: DRILL FROM 5515 FEET TO 5546 FEET IN ONE HOUR. TRIED TO MAKE A CONNECTION. COULD DO IT BUT HAD TO RUN INTO THE DRILL STRING. WILL TRIP OUT TO PICK UP SOME COLLARS FOR THE VERTICAL SECTION OF THE HOLE AND CHANGE THE BIT.

6:30AM: START OUT OF THE HOLE. NO PROBLEM GETTING OUT OF THE HOLE. STILL DRAGGING ABOUT 100000 ON BOTTOM BUT IS NOT TIGHT.

9:30AM: OUT OF THE HOLE. REPAIR THE KELLY BUSHING SLIDES SO THE KELLY WOULD NOT HANG UP ANY MORE.

11:30AM: FINISH PULLING THE BHA. CHANGE THE BIT.

12:30PM: START IN THE HOLE. TRIP IN TO 24 STANDS OUT OF THE HOLE.

2:30PM: PICK UP SIX 6 1/4" DRILL COLLARS TO PUSH THE PIPE IN THE HOLE.

4:00PM: TRIP THE REST OF THE PIPE IN THE HOLE. LAY DOWN 6 JOINTS OF DRILL PIPE.

5:00PM: REPAIRING THE AIR HOSES ON THE ROTARY TABLE CLUTCH.

7:00PM: RUN THE LAST 3 STANDS IN THE HOLE AND START THE AIR COMPRESSORS.

7:30PM: START DRILLING AGAIN. HAD NO PROBLEM GETTING IN THE HOLE. WENT RIGHT TO BOTTOM OR SHOULD I SAY THE SIDE.

8:30PM: PULLING 98000 LBS UP AND GOING DOWN AT 40000 LBS. WHEN THE PIPE FIRST STARTS DOWN, THE WEIGHT INDICATOR COMES DOWN TO ABOUT 20000 LBS. THE BLOCKS AND KELLY WEIGH 10000 LBS. CONNECTION WAS AT 5569 FEET.

11:00PM: TIME FOR A SURVEY. DEPTH IS 5628 FEET. BLOW HOLE 1/2 HOUR BEFORE STARTING OUT. TRIPPED 32 STANDS AND INSTALLED THE SIDE ENTRY SUB.

12-13

1:00AM: INSTALLED A 2" NIPPLE ON THE FLOW LINE TO TEST THE WELL. WELL IS MAKING 119 MCF PER DAY. USED A MONOMETER TO DETERMINE THE FLOW RATE.

2:00AM: START IN WITH THE SURVEY TOOL.

5:00AM: OUT OF THE HOLE WITH THE SURVEY TOOL. THE SURVEY IS 88 DEGREES S31E AT 5598 FEET. JUST RIGHT.

5:30AM: RIG DOWN THE WIRELINE TRUCK AND RELEASE GEARHART.

6:00AM: TRIP TO BOTTOM. STILL NO TROUBLE GETTING IN THE HOLE.

7:00AM: IN THE HOLE. START AIR COMPRESSORS.

7:30AM: SERVICE RIG AND AIR PACKAGE.

8:00AM: START DRILLING.

10:30AM: CONNECTION AT 5693 FEET. HAVING TROUBLE GOING DOWN. BLOW HOLE AND WORK PIPE. HLU: 105000, HLD: 20-50000, ROTATING: 64000, TORQUE 2.25 ROUNDS.

12:00PM: START DRILLING AGAIN. STILL HAVING TROUBLE MAKING THE PIPE GO DOWN. ONCE THE PIPE IS MOVING DOWN THE HOLE IT CONTINUES TO GO DOWN AT 30 TO 40000 LBS.

6:00PM: THE KELLY IS STILL HANGING UP IN THE BUSHINGS AND SLOWING DOWN THE PENETRATION RATE. MAKING THE CONNECTIONS BY DROPPING THE PIPE IN THE HOLE. WORKS AND IT IS STILL DRILLING.

11:00PM: SERVICE THE RIG AND BLOW THE HOLE FOR ONE HOUR TO MAKE SURE IT IS CLEAN.

12:14

3:50am: REACHED T.D. OF 6020 MEASURED DEPTH, 3427 T.V.D. HORIZONTAL DEPARTURE OF 3187'. THE AZIMUTH OF THE BOTTOM OF THE HOLE IS S 35 DEGREES AND 20 MINUTES EAST. THE TARGET AZIMUTH WAS S 37 E. BLOW HOLE FOR 1 HOUR. THE PIPE IS STILL HARD TO GET DOWN. COMES UP AT 110000LBS AND IS SMOOTH BUT GOING DOWN TAKES ALL THE WEIGHT AND IS NOT SMOOTH AT ALL.

4:50AM: START OUT OF THE HOLE TO GET READY TO LOG HOLE.

9:30AM: OUT OF HOLE. WAITING ON DRESSER ATLAS.

2:45PM: DRESSER ARRIVED ON LOCATION. RIGGING UP TO GO IN THE HOLE. STARTED RIGGING UP THE LOGGING TOOLS IN THE ROTARY TABLE.

7:00PM: FINISHED RIGGING UP LOGGING TOOLS. START TRIPPING THE TOOLS IN THE HOLE ON THE END OF THE DRILL STRING. RUNNING COMPENSATED DENSITY, GAMMA RAY, DUAL INDUCTION, AND CALIPER. TRIP IN TO 3200 FEET.

11:00PM: INSTALL SIDE ENTRY SUB AND TRY TO RUN THE CABLE HEAD IN THE DRILL PIPE. CABLE HEAD WOULD NOT GO PAST 6 STANDS DOWN. THE OD OF THE CABLE HEAD IS 3" AND THE ID OF THE DRILL PIPE TOOL JOINT IS 3.25" ACCORDING TO THE API. PULL 6 STANDS AND REMOVE THE STAND. RAN CABLE HEAD THREE MORE STANDS AND IT STOPPED AGAIN. REMOVED THE STAND THAT WAS STOPPING THE CABLE HEAD. RAN CABLE HEAD TO THE TOP OF THE LOGGING TOOLS. PLACE 2 MORE STANDS IN THE DRILL STRING BELOW THE SIDE ENTRY SUB. CONNECT INTO THE LOGGING TOOLS.

12-15

6:00AM: TRIP THE LOGGING TOOLS AND SIDE ENTRY SUB TO BOTTOM. WIRELINE DEPTH IS 6002'. DRILL PIPE STRAP DEPTH IS 6020 FEET. EXACTLY THE SAME AS THE TALLY BOARD.

8:00AM: START LOGGING BY PULLING DRILL PIPE. THE DENSITY AND CALIPER TOOLS WOULD NOT WORK PROPERLY BECAUSE THEY WERE NOT ORIENTED WITH RESPECT TO THE HIGH SIDE OF THE BOREHOLE. THE WEIGHT OF THE TOOL KEPT THE CALIPER CLOSED. ONLY ONE INEFFECTIVE ATTEMPT WAS MADE TO REALIGN THE TOOL BY ROTATING THE DRILL STRING. DRESSER DID NOT WANT TO ROTATE THE ROTARY TABLE BECAUSE THEY WERE AFRAID THEY WOULD KINK OR CUT THE WIRELINE.

12:00PM: THE WET CONNECT PULLED OFF THE LOGGING TOOLS. TRIPPED OUT TO THE SIDE ENTRY SUB. CABLE HEAD WAS STILL OK. RUN WIRELINE AND CONNECT BACK INTO THE WET CONNECT. ONCE SET, THE WET CONNECT IS NOT SUPPOSED TO COME OFF. THE LINE IS SUPPOSED TO BE PULLED OUT OF THE ROPE SOCKET. DID NOT HAVE IT ON GOOD ENOUGH. TRIPPED BACK INTO THE HOLE TO 4137 FEET WHERE LOGGING HAD STOPPED.

3:30PM: LOG THE REMAINDER OF THE 7 7/8" HOLE.

4:30PM: PULLED THE WIRELINE OUT OF THE ROPE SOCKET AND TRIPPED IT OUT OF THE HOLE. PULL DRILL STRING WITH THE LOGGING TOOLS.

7:00PM: LAY DOWN THE LOGGING TOOLS AND PICK UP THE TEMPERATURE TOOLS. CUT SLOTS IN THE TEMPERATURE HOUSING TO MAKE IT WORK. DRESSER HAD MADE A MISTAKE AND DID NOT MAKE THE HOUSING TO THE RIGHT LENGTH.

11:00PM: TRIP IN THE HOLE WITH THE TEMPERATURE LOG, AND GAMMA RAY TO 3200 FEET.

12-16

1:00AM: INSTALL SIDE ENTRY SUB AND MAKE WET CONNECT. THE GAMMA RAY WOULD NOT WORK. DID NOT RETURN TO THE SURFACE TO CHANGE TOOL BECAUSE THE PROBLEM MAY HAVE CURED ITSELF AND IT WOULD BE TOO EXPENSIVE.

3:00AM: LOG TEMPERATURE LOG INTO THE WELL TO TD. TEMPERATURE WORK FINE. THE DEPTHS WERE CORRELATED WITH THE BOTTOM OF THE 8 5/8" CASING.

6:00AM: PULL WIRELINE OUT OF THE ROPE SOCKET AND TRIP OUT OF THE HOLE. THERE HAS BEEN NO PROBLEM GETTING IN AND OUT OF THE HOLE.

11:30AM: RIG DOWN THE DRESSER LOGS AND RIG UP TO RUN STRATAVISION TV CAMERA.

2:00PM: TRIP INTO 3200 FEET WITH TV CAMERA.

5:00PM: INSTALL SIDE ENTRY SUB AND MAKE WET CONNECT. THE FIRST ATTEMPT FAILED BUT THE SECOND ATTEMPT WAS SUCCESSFUL. THE WET CONNECT PULLED OFF THE FIRST TIME.

6:00PM: LOG TO TD WITH THE TV CAMERA. THE CAMERA SHOWED THE FRACTURES VERY WELL, AND SHOWED MANY MORE THAN THE ONES RECORDED BY THE MUD LOGGERS. HOLE WAS DUSTY BUT OTHERWISE IN GOOD SHAPE. DID NOT LOOK MUCH OUT OF GAUGE.

12-17

1:00AM: STARTED LOGGING BACK UP THE HOLE.

4:00AM: PULLED LOOSE FROM THE WET CONNECT AND START WIRELINE OUT OF THE HOLE. WIRELINE BECAME STUCK. TRIPPED PIPE TO THE SIDE ENTRY SUB.

6:00AM: THE WIRELINE DEPTH IS 3218 FEET AND THERE IS STILL A CONNECTION TO THE TV CAMERA. DID NOT PULL OUT BEFORE. PULLED OUT OF THE WET CONNECT AND PULL WIRELINE.

7:00AM: RIG UP AND START LAYING DOWN DRILL PIPE WHILE PULLING THE TV CAMERA.

10:30AM: LAID DOWN 3200 FEET OF PIPE. LAY DOWN LOGGING TOOLS.

11:30AM: RUN THE REST OF THE DRILL PIPE IN THE HOLE AND THEN LAID IT DOWN.

4:30PM: FINISHED LAYING DOWN DRILL PIPE. NIPPLE DOWN AND RIG UP TO RUN 4 1/2" CASING.

7:00PM: START RUNNING CASING. RUNNING 4 1/2", 10.5#/FT, J-55, ST&C CASING. RAN 14 F O CEMENTERS, 8 BAKER ECP'S, AND ONE CTC PACKER. PLACED CENTRALIZERS ON BOTH SIDES OF THE PACKERS.

DAILYLOG PART 4, STARTING AT 11:30 PM ON 12-17-86.

11:30PM: HAVE ALL THE ECP'S AND PORT COLLARS IN THE HOLE.
RUN REMAINDER OF THE CASING.

12-18

2:00AM: ALL THE CASING IS IN THE HOLE. LANDED THE CASING AT
6013.92 FEET KB. THE DOWN DRAG WAS 31000 LBS AND THE UP
DRAG WAS 42000 WHEN THE CASING WAS ON BOTTOM. THE BLOCKS
WEIGH 5000 LBS. THE PLACEMENT OF THE PACKERS AND PORT
COLLARS CAN BE FOUND ON THE CASING TALLY. RIG DOWN THE
POWER TONGS AND SET THE SLIPS ON THE 4 1/2" CASING.

3:00AM: START RIGGING DOWN THE RIG.

6:00AM: RELEASED THE DRILLING RIG.

LOADED OUT STOWERS TRUCK WITH MAGCOBAR DRILLING PRODUCTS.
LOADED ANOTHER STOWERS TRUCK WITH THE DIRECTIONAL DRILLING
EQUIPMENT AND THE TRI-STATE EQUIPMENT AND SENT IT TO
MORGANTOWN. LOADED THE EASTMAN TRUCK WITH THE DRESSER
EQUIPMENT AND SENT IT TO HOUSTON. WELDED A BASE PLATE ON
TO THE 8 5/8" CASING AND PLACED A RUBBER GASKET BETWEEN THE
11" AND 8 5/8" CASING TO STOP THE ANNULUS FROM LEAKING.
LEFT LOCATION AT 8:00 PM.

APPENDIX C-I

**BOTTOMHOLE ASSEMBLIES UTILIZED
IN DRILLING RET #1 WELL**

.

BHA #	DEPTH IN	DEPTH OUT	BOTTOMHOLE ASSEMBLY	REMARKS
1	0	161	22" & 18 1/2" BIT, X-O, AIR HAMMER, X-O, 17-6 1/4" DC'S	
2	161	660	17 1/2" BIT, X-O, 17-6 1/4" DC'S	16" CASING POINT
3	660	660	17 1/2" BIT, 3 POINT REAMER, X-O, X-O, 17-6 1/4" DC'S	REAM
4	660	1651	14 3/4" BIT, X-O, 2-8" MONELS, X-O, X-O, 17-6 1/4" DC'S	
5	1651	2113	13 3/4" BIT, X-O, 2-8" MONELS, X-O, X-O, 17-6 1/4" DC'S	11 3/4" CASING POINT
6	2113	2113	10 5/8" BIT, 2 8" MONELS, X-O, X-O, 2-6 1/4" DC'S	DRILL CEMENT
7	2113	2277	MOTOR RUN NUMBER 1 AND 2	
8	2277	3309	MOTOR RUN NUMBER 3 THRU 6	
9	3309	3509	MOTOR RUN NUMBER 7	
10	3509	----	10 5/8" BIT, 3 POINT REAMER, 2-8" MONELS, 3 POINT REAMER, X-O, X-O, 2-6 1/4" DC'S	LOST IN HOLE
11	3176	3239	10 5/8" BIT, FS, 2-8" MONELS, X-O	DRILL CEMENT
12	3239	3421	MOTOR RUN NUMBER 8 AND 9	
13	3421	3666	MOTOR RUN NUMBER 10	
14	3330	3362	10 5/8" BIT, FS, 3 POINT REAMER, 2-8" MONELS, 3 POINT REAMER, X-O	REAM AND DRILL CEMENT
15	3362	3634	MOTOR RUN NUMBER 11	
16	3634	3827	MOTOR RUN NUMBER 12	8 5/8" CASING POINT
17	3827	3827	10 5/8" BIT, FS, 8" MONEL, 3 POINT REAMER, 8" MONEL, X-O	REAM AND CLEAN HOLE
18	3827	3827	10 5/8" BIT, X-O, FS	CLEAN HOLE
19	3827	3862	7 7/8" BIT, FS, 3 1/4" MONEL, X-O, 6 1/4" MONEL	DRILL OUT

BHA #	DEPTH IN	DEPTH OUT	BOTTOMHOLE ASSEMBLY	REMARKS

20	3862	4043	MOTOR RUN NUMBER 13 AND 14	
21	4043	4086	7 7/8" CORE BIT, 30' CORE BARREL, X-O, X-O	
22	4086	4126	7 7/8" BIT, FS, 6 1/4" MONEL, X-O, 6 1/4" MONEL	
23	4126	4156	7 7/8" CORE BIT, 30' CORE BARREL, X-O, X-O	
24	4156	6020	7 7/8" BIT, FS, 6 1/4" MONEL, X-O, 6 1/4" MONEL	TOTAL DEPTH

DC = DRILL COLLAR
FS = FLOAT SUB

APPENDIX C-II

**ANALYSIS OF BOTTOMHOLE ASSEMBLY
USED FOR HORIZONTAL DRILLING OPERATIONS**

RUN	MOTOR	
#	#	BOTTOMHOLE ASSEMBLY
1	1	10 5/8" BIT, 7 3/4" MOTOR, FS, 2 1/2" BS, 8" MONEL, MWD, UBHO SUB, 8" MONEL, 2 6 1/4" DRILL COLLARS
2	2	10 5/8" BIT, 7 3/4" MOTOR, FS, 2 1/2" BS, 8" MONEL, MWD, UBHO SUB, 8" MONEL, 2 6 1/4" DRILL COLLARS
3	2	10 5/8" BIT, 7 3/4" MOTOR, FS, 2 1/2" BS, 2-8" MONELS, X-O, X-O, 2-6 1/4" DRILL COLLARS
4	1	10 5/8" BIT, 7 3/4" MOTOR, FS, 2 1/2" BS, 2-8" MONELS, X-O, X-O, 2-6 1/4" DRILL COLLARS
5	3	10 5/8" BIT, 7 3/4" MOTOR, FS, 2 1/2" BS, 2-8" MONELS, X-O, X-O, 2-6 1/4" DRILL COLLARS
6	4	10 5/8" BIT, 7 3/4" MOTOR, FS, 2 1/2" BS, 2-8" MONELS, X-O, X-O, 2-6 1/4" DRILL COLLARS
7	5	10 5/8" BIT, 7 3/4" MOTOR, FS, 3" BS, 2-8" MONELS, X-O, X-O, 2-6 1/4" DRILL COLLARS
8	6	10 5/8" BIT, 7 3/4" MOTOR, FS, 2 1/2" BS, 2-8" MONELS, X-O
9	7	10 5/8" BIT, 7 3/4" MOTOR, FS, 2 1/2" BS, 2-8" MONELS, X-O
10	7	10 5/8" BIT, 7 3/4" MOTOR, FS, 3" BS, 2-8" MONELS, X-O
11	8	10 5/8" BIT, FS, 6 3/4"-2" BENT HOUSING MOTOR, 1.5" BS, X-O, 2-8" MONELS, X-O
12	9	10 5/8" BIT, FS, 6 3/4"-2" BENT HOUSING MOTOR, ALIGN-A-SUB, 1.5" BS, X-O, 2-8" MONELS, X-O
13	10	7 7/8" BIT, 6 3/4"-1 7/8" BENT HOUSING MOTOR, FS, MSS, 6 1/4" MONEL, X-O, 6 1/4" MONEL
14	11	7 7/8" BIT, 6 3/4"-1 7/8" BENT HOUSING MOTOR, FS, MSS, 6 1/4" MONEL, X-O, 6 1/4" MONEL

FS= FLOAT SUB

BS= BENT SUB

X-O= CROSS OVER SUB

MSS= MULE SHOE SUB

APPENDIX C-III

DOWNHOLE MOTOR ANGLE BUILDING PERFORMANCE DATA

RUN #	MOTOR #	DEPTH IN	DEPTH OUT	BUILD RATE DEG/100	WALK RATE DEG/100	DLS DEG/100	BENT SUB BENT HSG
1	1	2113	2215	4.42	29.58	5.77	BS 2.5
2	2	2215	2277	7.86	25.24	8.63	BS 2.5
3	2	2277	2559	4.29	4.39	4.50	BS 2.5
4	1	2559	2604	5.87	0.64	5.89	BS 2.5
5	3	2604	2985	4.27	1.51	4.37	BS 2.5
6	4	2985	3309	4.19	1.69	4.41	BS 2.5
7	5	3309	3509	7.34	0.40	7.36	BS 3.0
8	6	3239	3285	-6.25	3.13	6.67	BS 2.5
9	7	3285	3421	1.19	0.00	1.19	BS 2.5
10	7	3421	3666	5.57	2.17	6.14	BS 3.0
11	8	3362	3634	6.84	3.53	7.72	BH 2.0, BS 1.5
12	9	3634	3827	3.95	1.59	4.25	BH 2.0, BS 1.5
13	10	3862	3997	10.48	1.59	10.70	BH 1.8
14	11	3997	4043	8.89	0.00	8.89	BH 1.8

* The MWD and steering tool were used to survey and the high dogleg severity may be due to the difference in the instruments.

** Had trouble orienting the downhole motor.

*** The survey at 3787 was decreased to reflect the singleshot data and reduces the dogleg severity.

C-IV

DOWNHOLE MOTOR DRILLING PERFORMANCE DATA

C-4

RUN #	MOTOR #	DEPTH IN	DEPTH OUT	FEET	DRILLING HOURS	FT/HR	HOURS TO RESTART	COMMENTS

1	1	2113	2215	102	3.00	34.0	0.00	PLUGGED WITH CUTTINGS
2	2	2215	2277	62	2.50	24.8	0.00	PLUGGED WITH CUTTINGS
3	2	2277	2559	282	11.00	25.6	0.50	MOTOR FAILED
4	1	2559	2604	45	3.50	12.9	0.50	MOTOR FAILED
5	3	2604	2985	381	12.75	29.9	14.00	MOTOR FAILED
6	4	2985	3309	324	11.00	29.5	1.50	MOTOR FAILED
7	5	3309	3509	200	7.00	28.6	0.00	PULLED TO CHANGE BHA
8	6	3239	3285	46	9.50	4.8	3.50	TIME DRILL TO SIDETRACK
9	7	3285	3421	136	4.50	30.2	0.00	PULLED TO CHANGE BHA
10	7	3421	3666	245	10.00	24.5	0.00	PULLED TO PLUG BACK
11	8	3362	3634	272	14.50	18.8	5.00	MOTOR FAILED
12	9	3634	3827	193	9.00	21.4	10.00	MOTOR FAILED
13	10	3862	3997	135	9.00	15.0	3.00	MOTOR FAILED
14	11	3997	4043	46	2.00	23.0	0.00	FINISHED BUILD
AVERAGE PER RUN				176	7.80	22.6	2.71	
AVERAGE PER MOTOR				224	9.93	22.6	3.45	

APPENDIX C-V

ANALYSIS OF BOTTOMHOLE ASSEMBLY USED FOR HORIZONTAL DRILLING OPERATIONS

WELLPLAN (Version 3.0)

Drilling Resources Development Corporation

Operator : BDM

Contractor : HLH DRILLING

Lease : CABOT ENEGER

Field : WILSONDALE

Well Name : BDM/DOE ENEGER RET#1

Analyst : RSC

Date : 12-13-86

ANALYSIS : 2 - BDM ENEGER RET#1

SUBMODULE : 1 - BHA Analysis

UNITS : ENGLISH

DRILLING PARAMETERS OUTPUT

WEIGHT ON BIT (LBf)		20000.0
MUD WEIGHT (PPG)		.00
TORQUE AT BIT (FT-LB)		.00
MEASURED DEPTH OF BIT (FT)		4600.0
DRILL STRING (RPM)		0.

BOTTOM HOLE ASSEMBLY OUTPUT

NO.	TYPE	<----- COMPONENT ----->				<- STABILIZER/TOOL JOINT ->				
		LENGTH (FT)	ID (in)	OD (in)	MATL	LENGTH (FT)	ID (in)	OD (in)	FSHNCK (FT)	WEIGHT (PPF)
1	BIT	1.0		7.88						
2	COLLAR	2.1	2.50	5.75	STL					--
3	STABILIZER	3.6	2.00	7.00	STL	.50		7.75	2.00	--
4	COLLAR	2.0	2.00	6.00	STL					--
5	COLLAR	60.7	2.75	6.50	MNL					--
6	DRILL PIPE	5355.6	3.83	4.50	STL		3.20	6.25		18.51

WELLBORE DEPTH/DIAMETER OUTPUT

LOC. NO.	WELLBORE DEPTH (FT)	EFFECTIVE DIAMETER (in)
1	4983.0	7.875

WELLBORE DEPTH/COEFFICIENT OF FRICTION OUTPUT

LOC. NO.	MEASURED DEPTH (FT)	COEFFICIENT OF FRICTION
1	3803.0	.300
2	6020.0	.450

SURVEY STATION PARAMETERS OUTPUT

STATION NO.	MEAS. DEPTH (FT)	INCLINATION (DEG)	DIRECTION AZM (DEG)	TVD (FT)
1	.0	.00	N .00 E	.0
2	2000.0	.00	S .1.00 E	2000.0
3	2083.0	.50	S .01 E	2083.0
4	2101.7	.87	S 3.49 E	2101.7
5	2133.8	2.62	S 3.35 E	2133.7
6	2165.6	4.52	S 9.00 E	2165.5
7	2197.0	5.59	S 26.24 E	2196.8
8	2229.0	6.50	S 41.00 E	2228.6
9	2271.0	9.80	S 51.60 E	2270.2
10	2340.0	12.50	S 49.00 E	2337.9
11	2403.0	15.50	S 47.00 E	2399.0
12	2465.0	18.00	S 42.00 E	2458.4
13	2528.0	20.80	S 40.40 E	2517.8
14	2591.0	24.50	S 40.00 E	2575.9
15	2655.0	27.50	S 39.00 E	2633.4
16	2718.0	30.00	S 37.00 E	2688.7
17	2781.0	32.75	S 38.00 E	2742.4
18	2844.0	35.80	S 39.00 E	2794.5
19	2931.0	39.20	S 40.00 E	2863.5
20	2993.0	41.60	S 40.00 E	2910.7
21	3057.0	44.00	S 39.00 E	2957.7
22	3120.0	46.20	S 37.80 E	3002.1
23	3182.0	48.40	S 38.00 E	3044.2
24	3240.0	48.00	S 35.00 E	3082.8
25	3272.0	46.00	S 34.00 E	3104.7
26	3345.0	47.00	S 34.00 E	3154.9
27	3373.0	49.60	S 33.60 E	3173.5
28	3437.0	53.50	S 30.00 E	3213.3
29	3468.0	55.50	S 30.00 E	3231.3
30	3500.0	57.60	S 31.00 E	3249.0
31	3532.0	59.90	S 33.00 E	3265.6
32	3563.0	62.20	S 32.00 E	3280.6
33	3594.0	64.50	S 34.00 E	3294.5
34	3661.0	69.00	S 34.00 E	3320.9
35	3725.0	72.20	S 35.00 E	3342.2
36	3787.0	74.00	S 34.00 E	3360.2
37	3869.0	74.50	S 37.00 E	3382.5
38	3935.0	81.00	S 37.00 E	3396.5
39	3998.0	88.00	S 39.00 E	3402.5
40	4043.0	92.00	S 39.00 E	3402.5
41	4191.0	92.00	S 39.00 E	3397.3
42	4382.0	91.00	S 38.00 E	3392.3
43	4666.0	90.00	S 37.00 E	3389.8
44	4983.0	89.00	S 35.00 E	3392.6
45	5298.0	88.50	S 34.00 E	3399.5
46	5599.0	88.00	S 31.00 E	3408.7
47	6020.0	87.00	S 29.00 E	3427.0

BHA NODAL INFORMATION

NODE NUMBER	NODE TYPE	DISTANCE FROM BIT (FT)	MEASURED DEPTH (FT)
-----	-----	-----	-----
1	BIT	.0	4600.0
2	COLLAR	3.1	4596.9
3	STABILIZER	4.2	4595.8
4	STABILIZER	4.7	4595.3
5	COLLAR	6.7	4593.3
6	COLLAR	8.7	4591.3
7	COLLAR	18.8	4581.2
8	COLLAR	28.9	4571.1
9	COLLAR	39.1	4560.9
10	COLLAR	49.2	4550.8
11	COLLAR	59.3	4540.7
12	COLLAR	69.4	4530.6
13	PIPE	76.9	4523.1
14	PIPE	84.4	4515.6
15	PIPE	91.9	4508.1
16	PIPE	99.4	4500.6
17	PIPE	106.8	4493.2
18	PIPE	114.3	4485.7
19	PIPE	121.8	4478.2
20	PIPE	129.3	4470.7
21	PIPE	136.8	4463.2
22	PIPE	144.3	4455.7
23	PIPE	151.8	4448.2
24	PIPE	159.3	4440.7
25	PIPE	166.8	4433.2
26	PIPE	174.3	4425.7
27	PIPE	181.7	4418.3
28	PIPE	189.2	4410.8
29	PIPE	196.7	4403.3
30	PIPE	204.2	4395.8
31	PIPE	211.7	4388.3
32	PIPE	219.2	4380.8
33	PIPE	226.7	4373.3
34	PIPE	234.2	4365.8
35	PIPE	241.7	4358.3
36	PIPE	249.2	4350.8
37	PIPE	256.6	4343.4
38	PIPE	264.1	4335.9
39	PIPE	271.6	4328.4
40	PIPE	279.1	4320.9

BHA NODAL INFORMATION

*** USER WARNING MESSAGE ***

DRILL STRING INPUT EXCEEDS PROGRAM SIZE LIMITS
MODEL TRUNCATED AFTER FIRST 209.7 (FT) OF SECTION 6
TOTAL LENGTH ANALYZED IS 279.1 (FT)
TOTAL STRING LENGTH INPUT IS 5425.0 (FT)

*** END USER MESSAGE ***

BHA BIT RESULTS DATA

WELLBORE ORIENTATION AT BIT

INCLINATION 90.23 (DEG)
DIRECTION S 37.23 E
MEASURED DEPTH (FT) 4600.00

DRILL STRING ORIENTATION AT BIT

INCLINATION 90.31 (DEG)
DIRECTION S 37.24 E

RELATIVE ANGULAR POSITION OF BIT TO WELLBORE

INCLINATION DIFFERENCE08 (DEG) (TILT UP)
DIRECTION DIFFERENCE01 (DEG) (POINT LEFT)

BIT LOAD ON FORMATION

INCLINATION FORCE 1584. (LBf) (BUILD)
DIRECTION FORCE 200. (LBf) (LEFT)
WOB 20000. (LBf)

RESULTANT FORCE AT BIT

LOAD 20064. (LBf)
INCLINATION 94.76 (DEG)
DIRECTION S 37.81 E

BHA NODAL FORCES

NODE NUMBER	NODE TYPE	CONTACT	X INCLINATION FORCE (LB+)	Y DIRECTIONAL FORCE (LB+)	RESULTANT FORCE (LB+)
1	BIT	YES	-1584.	-200.	1597.
2	COLLAR	NO	0.	0.	0.
3	STABILIZER	YES	1004.	163.	1018.
4	STABILIZER	YES	2549.	33.	2550.
5	COLLAR	NO	0.	0.	0.
6	COLLAR	NO	0.	0.	0.
7	COLLAR	NO	0.	0.	0.
8	COLLAR	YES	1254.	1.	1254.
9	COLLAR	YES	1164.	18.	1164.
10	COLLAR	YES	1004.	15.	1004.
11	COLLAR	YES	844.	7.	844.
12	COLLAR	YES	1009.	-34.	1010.
13	PIPE	NO	0.	0.	0.
14	PIPE	NO	0.	0.	0.
15	PIPE	YES	162.	-5.	162.
16	PIPE	YES	390.	-8.	390.
17	PIPE	YES	179.	-2.	179.
18	PIPE	YES	158.	-2.	158.
19	PIPE	YES	139.	-1.	139.
20	PIPE	YES	132.	-1.	132.
21	PIPE	YES	146.	0.	146.
22	PIPE	YES	144.	0.	144.
23	PIPE	YES	135.	0.	135.
24	PIPE	YES	118.	0.	118.
25	PIPE	YES	177.	0.	177.
26	PIPE	YES	114.	0.	114.
27	PIPE	YES	132.	0.	132.
28	PIPE	YES	162.	-1.	162.
29	PIPE	YES	118.	0.	118.
30	PIPE	YES	151.	-1.	151.
31	PIPE	YES	123.	-1.	123.
32	PIPE	YES	161.	0.	161.
33	PIPE	YES	108.	0.	108.
34	PIPE	YES	175.	1.	175.
35	PIPE	YES	113.	0.	113.
36	PIPE	YES	149.	0.	149.
37	PIPE	YES	134.	0.	134.
38	PIPE	YES	151.	0.	151.
39	PIPE	YES	111.	0.	111.
40	PIPE	YES	88.	0.	88.

BHA ELEMENT AXIAL FORCES AND TORQUES

ELEMENT NODAL IDENTIFICATION	DISTANCE FROM BIT TO ELEMENT CENTER (FT)	ELEMENT AXIAL FORCE (LBf)	ELEMENT TORQUE (FT-LB)
1 - 2	2.	-20000.	0.
2 - 3	4.	-20001.	0.
3 - 4	4.	-20002.	148.
4 - 5	6.	-20002.	518.
5 - 6	8.	-20003.	518.
6 - 7	14.	-20005.	518.
7 - 8	24.	-20010.	518.
8 - 9	34.	-20014.	671.
9 - 10	44.	-20018.	813.
10 - 11	54.	-20022.	936.
11 - 12	64.	-20026.	1038.
12 - 13	73.	-20028.	1161.
13 - 14	81.	-20029.	1161.
14 - 15	88.	-20029.	1161.
15 - 16	96.	-20030.	1175.
16 - 17	103.	-20031.	1208.
17 - 18	111.	-20031.	1223.
18 - 19	118.	-20032.	1237.
19 - 20	126.	-20032.	1248.
20 - 21	133.	-20033.	1259.
21 - 22	141.	-20033.	1272.
22 - 23	148.	-20034.	1284.
23 - 24	156.	-20034.	1295.
24 - 25	163.	-20035.	1305.
25 - 26	171.	-20036.	1320.
26 - 27	178.	-20036.	1330.
27 - 28	185.	-20037.	1341.
28 - 29	193.	-20037.	1355.
29 - 30	200.	-20038.	1365.
30 - 31	208.	-20038.	1377.
31 - 32	215.	-20039.	1388.
32 - 33	223.	-20040.	1401.
33 - 34	230.	-20040.	1410.
34 - 35	238.	-20041.	1425.
35 - 36	245.	-20041.	1435.
36 - 37	253.	-20042.	1447.
37 - 38	260.	-20042.	1459.
38 - 39	268.	-20043.	1471.
39 - 40	275.	-20043.	1481.

BHA NODAL RELATIVE DISPLACEMENTS

NODE NUMBER	NODE TYPE	X INCLINATION (in)	Y DIRECTIONAL (in)	RESULTANT (in)
1	BIT	.016	.002	.016
2	COLLAR	-.044	-.003	.044
3	STABILIZER	-.072	-.012	.073
4	STABILIZER	-.088	-.001	.088
5	COLLAR	-.142	-.002	.143
6	COLLAR	-.219	-.010	.219
7	COLLAR	-.586	-.009	.586
8	COLLAR	-.700	.000	.700
9	COLLAR	-.699	-.011	.699
10	COLLAR	-.697	-.011	.698
11	COLLAR	-.696	-.006	.696
12	COLLAR	-.697	.023	.698
13	PIPE	-1.005	.047	1.006
14	PIPE	-1.457	.048	1.458
15	PIPE	-1.687	.048	1.688
16	PIPE	-1.690	.023	1.690
17	PIPE	-1.689	.008	1.689
18	PIPE	-1.689	.007	1.689
19	PIPE	-1.689	.001	1.689
20	PIPE	-1.689	.005	1.689
21	PIPE	-1.689	-.005	1.689
22	PIPE	-1.689	-.002	1.689
23	PIPE	-1.689	-.003	1.689
24	PIPE	-1.689	-.004	1.689
25	PIPE	-1.689	.002	1.689
26	PIPE	-1.689	.005	1.689
27	PIPE	-1.689	-.003	1.689
28	PIPE	-1.689	.006	1.689
29	PIPE	-1.689	.000	1.689
30	PIPE	-1.689	.008	1.689
31	PIPE	-1.689	.007	1.689
32	PIPE	-1.689	.001	1.689
33	PIPE	-1.689	-.005	1.689
34	PIPE	-1.689	-.011	1.689
35	PIPE	-1.689	-.003	1.689
36	PIPE	-1.689	-.001	1.689
37	PIPE	-1.689	-.002	1.689
38	PIPE	-1.689	-.002	1.689
39	PIPE	-1.689	-.004	1.689
40	PIPE	-1.687	-.001	1.687

BHA NODAL RELATIVE CLOSURE DISTANCE

NODE UMBER	NODE TYPE	X INCLINATION (in)	Y DIRECTIONAL (in)	RESULTANT (in)
1	BIT	-.016	-.002	.016
2	COLLAR	-.392	-.031	.394
3	STABILIZER	.010	.002	.010
4	STABILIZER	.025	.000	.026
5	COLLAR	-.295	-.005	.295
6	COLLAR	-.468	-.022	.469
7	COLLAR	-.102	-.002	.102
8	COLLAR	.013	.000	.013
9	COLLAR	.012	.000	.012
10	COLLAR	.010	.000	.010
11	COLLAR	.008	.000	.008
12	COLLAR	.010	.000	.010
13	PIPE	-.680	.032	.681
14	PIPE	-.229	.008	.229
15	PIPE	.000	.000	.000
16	PIPE	.003	.000	.003
17	PIPE	.001	.000	.001
18	PIPE	.001	.000	.001
19	PIPE	.001	.000	.001
20	PIPE	.001	.000	.001
21	PIPE	.001	.000	.001
22	PIPE	.001	.000	.001
23	PIPE	.001	.000	.001
24	PIPE	.001	.000	.001
25	PIPE	.002	.000	.002
26	PIPE	.001	.000	.001
27	PIPE	.001	.000	.001
28	PIPE	.002	.000	.002
29	PIPE	.001	.000	.001
30	PIPE	.002	.000	.002
31	PIPE	.001	.000	.001
32	PIPE	.002	.000	.002
33	PIPE	.001	.000	.001
34	PIPE	.002	.000	.002
35	PIPE	.001	.000	.001
36	PIPE	.001	.000	.001
37	PIPE	.001	.000	.001
38	PIPE	.002	.000	.002
39	PIPE	.001	.000	.001
40	PIPE	.000	.000	.000

APPENDIX D

CASING TALLEY, ECP & PORT COLLAR LOCATION HOOKLOAD AND DRAG DATA

4 1/2" CASING TALLY ON 12-13-86 RUN ON 12-17-86
 INFLATE PORT IS 13" BELOW THE TOP OF ECP
 INFLATE VALVE IS 9.7' BELOW TOP OF CTC PACKER

JOINT NUMBER	LENGTH	COLLAR DEPTH	COMMENTS

BOTTOM		6013.92	
	0.80	6013.12	
71	43.81	5969.31	
72	43.84	5925.47	
73	43.58	5881.89	
74	43.83	5838.06	
75	43.85	5794.21	
76	45.30	5748.91	
	2.88	5746.03	PORT COLLAR
77	45.16	5700.87	
78	45.41	5655.46	
79	44.97	5610.49	
	8.83	5601.66	PACKER 1
80	43.85	5557.81	
	2.88	5554.93	PORT COLLAR
81	44.97	5509.96	
82	43.55	5466.41	
	2.88	5463.53	PORT COLLAR
83	43.64	5419.89	
	8.83	5411.06	PACKER 2
84	45.50	5365.56	
85	43.81	5321.75	
	2.88	5318.87	PORT COLLAR
86	43.83	5275.04	
87	43.64	5231.40	
	2.88	5228.52	PORT COLLAR
88	43.84	5184.68	
	8.83	5175.85	PACKER 3
89	43.84	5132.01	
	2.88	5129.13	PORT COLLAR
90	43.55	5085.58	
91	44.63	5040.95	
	2.88	5038.07	PORT COLLAR
92	43.60	4994.47	
	8.83	4985.64	PACKER 4
93	43.82	4941.82	
94	45.14	4896.68	
	2.88	4893.80	PORT COLLAR
95	45.58	4848.22	
	37.25	4810.97	CTC PACKER
96	43.82	4767.15	
97	43.85	4723.30	
98	39.00	4684.30	
99	43.01	4641.29	
100	43.82	4597.47	
	2.88	4594.59	PORT COLLAR
101	38.18	4556.41	
102	43.61	4512.80	
103	43.56	4469.24	
104	43.85	4425.39	
105	39.20	4386.19	
	2.88	4383.31	PORT COLLAR
106	37.53	4345.78	

	8.83	4336.95	PACKER 5
107	43.56	4293.39	
	2.88	4290.51	PORT COLLAR
108	43.81	4246.70	
109	43.83	4202.87	
	8.83	4194.04	PACKER 6
110	43.80	4150.24	
	2.88	4147.36	PORT COLLAR
111	43.81	4103.55	
	8.83	4094.72	PACKER 7
112	43.85	4050.87	
113	43.80	4007.07	
114	43.82	3963.25	
	2.88	3960.37	PORT COLLAR
115	37.51	3922.86	
116	43.85	3879.01	
117	43.83	3835.18	
	2.88	3832.30	PORT COLLAR
118	43.83	3788.47	
119	43.85	3744.62	
	8.83	3735.79	PACKER 8
120	43.83	3691.96	
121	42.94	3649.02	
122	45.10	3603.92	
123	43.80	3560.12	
124	43.60	3516.52	
125	43.82	3472.70	
126	43.60	3429.10	
127	42.15	3386.95	
128	43.58	3343.37	
129	43.81	3299.56	
130	38.97	3260.59	
131	43.83	3216.76	
132	39.15	3177.61	
133	38.23	3139.38	
134	44.48	3094.90	
135	43.55	3051.35	
136	42.10	3009.25	
137	43.85	2965.40	
138	43.83	2921.57	
1	43.64	2877.93	
2	43.68	2834.25	
3	45.35	2788.90	
4	43.90	2745.00	
5	43.61	2701.39	
6	43.64	2657.75	
7	43.87	2613.88	
8	44.75	2569.13	
9	43.64	2525.49	
10	43.89	2481.60	
11	43.69	2437.91	
12	43.89	2394.02	
13	43.69	2350.33	
14	43.67	2306.66	
15	43.60	2263.06	
16	43.89	2219.17	
17	43.61	2175.56	DRAG 1-2000LBS
18	43.63	2131.93	
19	43.88	2088.05	
20	43.89	2044.16	DRAG 2000 LBS

21	43.62	2000.54	
22	43.87	1956.67	
23	45.28	1911.39	
24	43.68	1867.71	
25	43.86	1823.85	
26	45.12	1778.73	
27	45.34	1733.39	
28	43.62	1689.77	
29	45.81	1643.96	
30	43.65	1600.31	
31	43.65	1556.66	
32	43.87	1512.79	UP 40000 DOWN 35000
33	45.88	1466.91	
34	43.60	1423.31	
35	41.91	1381.40	
36	43.85	1337.55	
37	38.85	1298.70	
38	43.86	1254.84	
39	43.84	1211.00	
40	42.25	1168.75	
41	43.59	1125.16	
42	38.57	1086.59	
43	43.64	1042.95	
44	37.24	1005.71	UP 40000 DOWN 32000
45	43.86	961.85	
46	43.60	918.25	
47	43.84	874.41	
48	43.86	830.55	
49	42.43	788.12	
50	37.36	750.76	
51	43.84	706.92	
52	43.85	663.07	
53	44.59	618.48	
54	43.60	574.88	
55	43.82	531.06	
56	43.62	487.44	42000 LBS DOWN 31000
57	43.89	443.55	
58	43.88	399.67	
59	43.87	355.80	
60	43.85	311.95	
61	43.85	268.10	
62	43.85	224.25	
63	45.13	179.12	
64	43.85	135.27	
65	44.76	90.51	
66	43.87	46.64	UP 42000 DOWN 31000
67	43.64	3.00	
68	43.62	OUT	
69	43.87	OUT	
70	43.65	OUT	

6142.06			

APPENDIX E

CORE FRACTOGRAPHIC ANALYSIS AND DISCUSSION OF TECTONIC SETTING

FRACTOGRAPHIC LOGGING FOR DETERMINATION OF
NATURAL AND CORING-INDUCED FRACTURES
IN THE RET #1 WELL, WAYNE COUNTY, WEST VIRGINIA

INTRODUCTION

Fracture logging of 73 feet of oriented core taken from the RET #1 well in Wayne County, West Virginia, was completed during January 2-4, 1987. The core was deviated into the Middle Devonian black shales and drilled two horizontal lengths from 4043 to 4087 feet and 4126 to 4155 feet. All core footage measurements signify core length instead of drilling depth and are keyed to a zero length at ground surface. This procedure is necessary because of the extreme deviation (vertical to horizontal) of the hole. The horizontal core sections were drilled toward S39°E which was the downhole direction, and all angular measurements during the fractographic investigation were made from a S39°E trending line marking the top of the core. Fractographic logging, a procedure developed by Kulander, Barton and Dean (1979), was applied to all core samples to determine:

- (1) coring-induced fractures and their type, frequency, orientation and extent;
- (2) natural fractures and their frequency, orientation and extent;
- (3) tectonic indicators such as faults, slickenlines, stylolites and mineralization trends;
- (4) possible in-situ stresses and/or rock anisotropies indicated by coring-induced fractures.

All fracture and tectonic data (faults, slickenlines) were recorded on core fracture logging information sheets. In addition, Figure 1-a, 1-b, and 1-c are continuous core fracture logs compiled for easy visualization of spatial relationships between all coring-induced fractures, natural joints and faults. Figures are also included that depict regional in-situ stresses, basement Rome Trough structure, fracture and lineament trends found in the well, adjoining wells and outcrop, as well as sketches and photos showing coring-induced and natural joint characteristics.

OBSERVED CORE FRACTURES AND TECTONIC FEATURES

A total of 113 fractures and faults, as well as three rubble zones cutting the core, are described on the included core fracture log. The 113 logged fractures include 15 natural joints and 6 faults as well as coring-induced breaks including 59 subvertical irregular fractures (SVIF), 26 bedding partings (BP), and 4 torsion fractures. In addition, one drilled surface and two handling-induced fractures were described in the fracture logging information sheets that were not included on the core log (Figures 1-a, 1-b, 1-c).

Natural Extension Joints

Fifteen (15) natural extension joints cut the examined core sections. Joint strikes were remarkably consistent ranging from N31°E to N40°E. Joint dips ranged from 77°NW to 83°SE. The mean joint orientation was N37°E, 87°NW. No secondary mineralization was evident by visual examination on any joint face. Natural joint orientations are given in Table 1, and a rose diagram of joint trends is shown in Figure 2.

TABLE 1

NATURAL JOINT ORIENTATIONS AND DRILLING LENGTHS

<u>ORIENTATION</u>	<u>DRILLING LENGTH</u>	<u>ORIENTATION</u>	<u>DRILLING LENGTH</u>
N37°E, 80°NW	4045.7 feet	N39°E, vertical*	4139.9 feet
N38°E, 78°NW	4062.2 feet	N39°E, 83°SE*	4139.9 feet
N38°E, 84°NW*	4067.9 feet	N40°E, 85°SE	4140.1 feet
N38°E, 84°NW*	4067.9 feet	N38°E, 85°SE	4140.4 feet
N38°E, 78°NW	4071.0 feet	N34°E, 85°NW	4141.1 feet
N38°E, 78°NW	4075.7 feet	N31°E, 77°NW	4142.0 feet
N37°E, 77°NW	4076.2 feet	N31°E, 78°NW	4142.6 feet
N40°E, 77°SE	4128.2 feet		

* Overlapping joints at same drilling length.

All joints exhibited well-developed surface structures including hackle plumes, arrest lines, and twist hackle bands. These structures mandate Mode I fracture with the principal effective tension at the crack tip perpendicular to the propagating fracture front (Kulander and Dean, 1985). Partial plume geometries on the segments of joint faces captured

by the horizontal core show that the joints were penetrated at different positions within each individual plume (Figure 3). In fact, twist hackle bands were penetrated at cored lengths of 4045.7 and 4142.6 feet. These twist hackle bands are local areas of increased fracture surface area and corresponding fracture permeability. Such zones may enhance hydrocarbon production.

A statistical fracture spacing could not be determined reliably from the drilled natural joints. However, spacing between joints in cores 1 and 2 is 12-6-3 and 5 feet in a downcore direction, giving a mean spacing of 6.5 feet. In core 3, a distance of 12 feet separated a single natural joint from the inception of a joint and fault zone. The mean joint spacing for the entire cored section equals 8 feet. A spacing of 3 to 5 feet for megascopic joints is not uncommon in outcropping Devonian shales to the west in Rowan County, Kentucky.

A joint face within the joint-fault zone, at a drilled distance of 4141.8 feet, contained hackle plume components overprinted by slickenlines. Here, sequential development of joint surface structures, including slickenlines, suggests fault movement within this zone may have occurred along pre-existing joints. However, lower dips on all normal faults, as compared to steeper joint inclinations, serve to weaken this argument, unless faulting occurred along joints of a different and unrelated set.

Four oriented Devonian shale cores have previously been taken in conjunction with the Eastern Gas Shales Project (EGSP) within a 50 mile radius of the RET #1 well. These adjacent wells are the WV #3 and WV #4 in Lincoln County, and the KY #3 and KY #4 in Martin and Johnson Counties, respectively. Devonian shales in all these wells are within the Rome Trough. Table 2 lists statistically significant natural joint trends within these wells. Figure 4 shows rose diagrams for these tabulated trends as well as the N37°E trend evident in the deviated RET #1 core.

Table 2 and Figure 4 shows that in three of the adjacent cores, statistically significant joint trends were within 10° of the N37°E mean trend for the RET #1 core. The N37°E trend in the KY #3 core, even though it matched the mean joint trend in the deviated core, was not deemed by Evans to be statistically significant.

TABLE 2
SIGNIFICANT NATURAL JOINT AND SLICKENLINE TRENDS
FROM ADJACENT DEVONIAN SHALE CORES (after Evans, 1979)

<u>EGSP WELL NO.</u>	<u>STATE WELL NO.</u>	<u>SIGNIFICANT JOINT TRENDS</u>	<u>SIGNIFICANT SLICKENLINE TRENDS</u>
WV #3	LIN-1637	N65°E, N27°E, N83°E	N77°E, N13°W
WV #4	LIN-1636	N27°E	N40°W, N45°W
KY #3	PERMIT NO. 31020	N37°E (Insignificant)	N03°W, N75°E N17°W, N47°E, N83°E
KY #4	?	N65°E, N47°E	Numerous directions; none significant.

Long (1979) mapped surface joints in outcropping Devonian shales approximately 70 miles to the east and found that throughout the shale belt, first-formed joint trends N25° to 55°E (Figure 5). Long also found that the predominant trend of first-formed joints in overlying Mississippian and Pennsylvanian age shales was N30° to 55°E (Figure 6). In all cases, systematic fractures were clearly linked by orthogonal nonsystematic fractures.

Kulander and Dean (unpublished information) investigated outcrop joint trends in the Devonian shales of Rowan County, Kentucky, approximately 50 miles to the west of Wayne County. They found that the first-formed and most pervasive fracture set trends N40° to 55°E. Here, outcrop frequency averaged 1 joint per 3 to 5 feet. A nonsystematic joint set striking N40° to 50°W abutted the N40°-55°E set orthogonally. Another less persistent, systematic fracture set trended North to N10°E and was not clearly related to any nonsystematic joint set. In addition, a 240 foot shale core drilled by Mound Laboratories in Rowan County was examined by Kulander and Dean. The core contained only four natural fractures trending N12°E vertical; N62°E vertical; N70°E, 87°NW; N75°W, vertical.

Colton, et al (1981) investigated regional joint patterns in the central and northeastern Appalachian Basin. In Rowan County, Kentucky, they found that in gray units of the Devonian Ohio shale, the predominant

joint direction was N50°-60°E, whereas in black units of the Ohio shale, the predominant joint direction was N45°E. In both cases, each systematic joint set was related to well-developed orthogonal nonsystematic sets (Figure 7).

Wise, et al (1980) in a study of brittle fracture patterns in the Big Sandy gas field of eastern Kentucky (Jenkins, KY, 2° quadrangle), found pronounced landsat lineament trends of N45°E and N65°E (Figure 8). Wise also investigated topographic lineaments from one by two degree relief maps (Figure 9). In this case, pronounced lineament trends in the Huntington 2° quadrangle showed similar lineament trends of N03°E, N34°E, and N60°-70°E. The N45°E landsat and N34°E relief map trends are in accord with the N37°E joint trend cutting the RET #1 core. However, this correlation does not imply that fractures cutting the buried Devonian shale section are persistent to the surface, only that subsurface fractures and surface topography may in some way be related to Rome Trough development.

The northeast joint trend common to the RET #1 well and adjacent EGSP wells, as well as the Devonian shale outcrops to the west, is approximately parallel to the strike direction of the western flank of the Rome Trough (Figure 10). In Wayne and adjacent counties in West Virginia and Kentucky, basement contours strike regionally N40°-50°E. In addition, Middle Devonian shales thicken toward the east over the Rome Trough (Patchen, 1977). However, Devonian basin contours do not necessarily parallel Rome Trough basement contours. If the first-formed joints with northeast trend found in outcrop are comparable to those found in the RET #1 and adjacent wells, they all may reflect tensile stresses present during Devonian basin development. In this case, the least effective fracturing stress would have been regionally perpendicular to Devonian shale thickening direction. A modern analog would be the stresses responsible for the basin faults in the Gulf Coast.

Maximum horizontal compressive stresses measured by impression packer surveys in adjacent Lincoln County, West Virginia, trend N37°E (Overbey, 1976), and N40°-50°E (Evans, 1979). These directions, if valid, are approximately parallel to the natural joint strike within the deviated well. This geometrical relationship may be fortuitous, especially if

the drilled joint system developed early in response to stresses within the subsiding Devonian basin, as suggested in the previous paragraph. However, artificial stimulation of the well may be enhanced by parallelism between natural joint and in-situ stress directions. Here, induced fracture growth would be greatest in the maximum stress direction that, in this case, may coincide with the direction of natural joints and any related microcracks, both of which are nearly perpendicular to the wellbore.

No nonsystematic joints were apparent cutting the cored section. This is somewhat surprising because in outcrops within the Allegheny plateau, nonsystematic joints commonly show an orthogonal abutting relationship to first-formed systematic joints (Kulander and Dean, 1979; Long, 1979; Colton, 1981). However, in the RET #1 well, the deviated core was drilled almost perpendicular to the interpreted systematic joint set. It follows that any orthogonal, nonsystematic fracture would be approximately parallel to the drilled direction of S39°E. If this geometry is correct, perhaps a future deviation direction of 45 degrees to the estimated systematic trend would also penetrate any orthogonal nonsystematic joint set. However, such fracture-core geometry (i.e., fractures not perpendicular to wellbore) may complicate subsequent stimulation procedures. Photos showing natural joint surface and trace characteristics are shown in Figure 11.

Faults

Six faults cut the core within a shear zone extending from 4140.8 to 4141.8 feet. Fault strikes ranged from N17°E to N32°E and fault dips ranged from 54°NW to 76°NW. Mean fault orientation is N22°E, 56°NW. Slickenlines trended down-dip and slickenline steps indicated that last movement in five faults was in a normal sense, whereas slickenline steps on the fault at 4141.8 feet indicated reverse movement. Fault type, attitude and drilled location are given in Table 3, and an equal area diagram of joint trends is shown in Figure 12.

All faults were smooth and planar. In every case, well-developed slickenlines on fault surfaces trended parallel to the dip direction.

TABLE 3
FAULT ORIENTATIONS, FAULT TYPES, AND DRILLING LENGTHS

<u>FAULT ORIENTATION</u>	<u>FAULT TYPE</u>	<u>DRILLING LENGTH</u>
N22°E, 60°NW	Normal	4140.8 feet
N17°E, 54°NW*	Normal	4141.1 feet
N17°E, 54°NW*	Normal	4141.1 feet
N17°E, 54°NW*	Normal	4141.1 feet
N32°E, 76°NW	Reverse	4141.8 feet

* Small overlapping faults at approximately same drilling length.

The mean fault trend is approximately 15 degrees east of the mean trend for penetrated joints. The difference in mean orientation suggests that if fault movement occurred along preexisting joints, these joints may not have been related to the cored N37°E set. The supposition that movement was along preexisting joints is bolstered by the fact that one of the faults contained slickenlines that overprinted hackle plume components. Also, this reverse fault dipped steeply (76°) and was sub-parallel in strike (N32°E) to the N37°E joints. However, the normal fault at 4141.1 feet cuts and offsets a N37°E natural joint, suggesting that faulting was not aided by the pervasive cored joint set.

Finally, the preponderance of normal faults suggests that faulting occurred after jointing in further response to tensional stresses related to basin development and increased differential compaction towards the Rome Trough axis. Another structural possibility exists that would explain the northwest fault dip with respect to the northeastward thickening direction of Middle Devonian shales as well as the northeastward direction of Rome Trough deepening. Here the penetrated faults may be antithetic to a larger normal fault system that dips toward the northeast. Photos showing fault surface and trace characteristics are shown in Figure 13.

Coring-Induced Sub-Vertical Irregular Fractures

A total of 59 sub-vertical irregular fractures (SVIF) cut the logged core sections. These coring-induced fractures were commonly rough and

curviplanar to the degree that 19 of them could not be used even for average orientation values. However, a mean strike and dip of N52°E, vertical was determined for the remaining 40, and a rose diagram (Figure 14) shows the orientation spread. SVIF fractures could be separated into two types based upon overall shape.

SVIF fracture traces and surface structures of both types possessed an overall uniform geometry with the core even though they were not planar and smooth. For example, in the first type, the top 0.08 inch sections of a great majority of these core fractures were inclined at an average 77 degrees upcore toward the northwest. The central portion curved back to vertical, or slightly inclined, toward the southeast. The bottom section broke vertically to the core boundary, cut sharply downcore to form a small lip, or again became inclined back toward the northwest. Furthermore, the SVIF fracture type generally originated within the top section of the core towards the core periphery. However, an origin within the core was not always apparent. Thirty-five of this type SVIF fractures were well-formed and possessed the above described geometry (Figures 15-a and 16-a).

The second type of SVIF fracture is barbed in appearance and does not show the pronounced northwest dipping upper section. In addition, these fractures turn abruptly in the bottom one-third to one-quarter of the core to become parallel or subparallel to bedding. This bottom fracture section, approximately paralleling bedding, propagates downcore for one to three inches before cutting abruptly to meet the core margin at 90 degrees (Figures 15-b and 16-b). Overall fracture propagation directions on the barbed SVIF fractures are ambiguous. For example, in most cases, arrest lines on the barbed section at core bottom show an upcore overall propagation direction for fracture. In contrast, the nearly vertical section of these fractures contain origins in the upper core section, occasionally spatially related to the scribe groove. This central and upper section of the barbed fracture propagates in an overall downcore direction to joint the subhorizontal barb. The resulting two propagation directions indicate that several barbed fractures may actually be a composite of two breaks.

The above-described two directional scenario of development for barbed fractures can be altered. For example, several of these breaks propagated from the bottom to top of the core, while others propagated continually from core top to core bottom. Again, a distinct fracture origin was not always apparent, especially when surface structures were obscure.

In every case, both types of SVIF fractures possessed an overall uniform geometry and constant average orientation perpendicular to the core axis. In addition, hackle plume geometry reflected the geometry of the core. These observations show that the development of SVIF fractures was controlled by drilling-induced stresses, a pervasive rock anisotropy or a combination of both. In any case, the explanation of why SVIF fractures did not favor a pervasive anisotropy suggested by the natural joints is not clear. The small (15 degree) variance between the mean strike of SVIF fractures and natural joints indicates that any anisotropy related to microfracturing in the natural joint direction was ineffective in controlling induced SVIF fracture growth. However, Evans (1979) does show coring-induced (petal-centerline) fractures in the WV #3 and #4 wells trending N60°E and N35°E respectively. Photos showing SVIF fracture surface and trace characteristics are shown in Figures 16-a and 16-b.

Coring-Induced Bedding Parting Fractures

A total of 26 horizontal to subhorizontal bedding parting (BP) fractures were observed in the core section. Coring-induced BP fractures were generally smooth and planar to slightly curvilinear. In addition, BP fractures were bedding-parallel or cut across bedding at a low angle, suggesting a resistance of the core at these locations to part along bedding.

BP fractures could be separated into two sub-types based upon plume geometry where fracture surface structures were well-developed (Figures 17 and 18). The prevalent fractures each displayed a hackle plume axis at the center of the fracture face. The overall fracture propagation direction was downcore in every case except one, where the plume indicated

an upcore propagation direction. Abutting relationships with SVIF fractures were ambiguous and suggested that BP fractures could pre or postdate SVIF fractures. Here, the latter case was predominant. In addition, several BP fractures of this type hooked sharply toward the core margin, suggesting these fractures developed after coring.

The lack of a discernible origin and the downcore propagation direction suggests that this type of BP fracture may be analogous to petal-centerline fractures in vertical cores (Kulander and Dean, 1979). However, no distinct petals or concentric arrest lines were observed.

The second type BP fracture always originated at the scribe knife groove and propagated in an overall downcore direction (Figures 17 and 18). These fractures parted parallel to bedding, had a continuous origin at the advancing scribe knife, and hooked abruptly toward the opposite core margin. Primary control for development of these fractures are stresses induced by the scribe knife in conjunction with a weak bedding plane.

Coring-Induced Torsion Fractures

Only four fractures possessed the spiral hackle plume geometry indicative of torsion fractures. All of these were within the first two continuous core sections and none were related to zones of excessive core damage. Figure 19 is a photo showing the spiral hackle geometry characteristic of torsion fractures within the RET #1 core. These four torsion fractures were the only coring-induced breaks cutting this horizontal core that possessed clear similarities to identical fractures found in vertical cores drilled perpendicular to bedding in adjacent locations within the Allegheny plateau.

THE ROME TROUGH-TECTONIC SETTING FOR THE RET #1 WELL

The Rome Trough forms an integral part of a pronounced rift system that extends southwestward from the Olin Basin in Pennsylvania (Wagner, 1976), through West Virginia where it turns to a west-southwest trend into Kentucky (Kulander and Dean, 1980a,b, 1986; Schrantz, 1984; Webb, 1980). The rift system continues westward into southeast Missouri to

the New Madrid rift (Ervin and McGinnis, 1975). Figures 20 and 21 show the major structural components and basement depths within the trough proposed by the previously mentioned investigators.

In eastern Kentucky, Webb (1980) suggests that the Kentucky River fault, forming the northern boundary of the Rome Trough, has a much greater displacement than the Rockcastle River fault that marks the trough's southern boundary. These faults are extended into West Virginia by Schrantz (1984). However, Schrantz places the Irvine-Paint Creek and Martha faults within the trough at different locations based upon gravity modelling techniques similar to those of Ammerman and Keller (1978). The northern boundary of the Rome Trough as shown by Kulander and Dean (1986) also reflects the possible extension of the fault into West Virginia by the steepened gradient shown by basement contours (Figure 10). In addition, Kulander and Dean suggest that the southernmost-bounding Rockcastle fault has the greatest displacement in West Virginia. Proprietary seismic profiles across this feature in West Virginia indicate that the Rockcastle fault is a normal fault zone, and not a single fault, as depicted on the small scale basement map.

Ammerman and Keller (1978) believe that the Lexington and other major trough faults were initially developed during Keweenawan time and were rejuvenated during the Middle Cambrian. Their conclusion is based upon increasing thickness of Middle Cambrian units within the trough. Webb (1980) concurs with this developmental plan and further suggests that the bounding faults had periodic movement throughout the Paleozoic. Webb also states that major intra-basin fault-bounded blocks were tilted during Middle Cambrian time.

Overbey (1976), in a study of in-situ stresses, suggests that maximum compressive stress trajectories in the horizontal plane are regionally deviated within the Rome Trough (Figure 22). Kulander and Dean (1980a) concur, and show coal cleat trends changing abruptly within sections of the Rome Trough. Here, changing cleat trends reflect deviated stress direction during Pennsylvanian time that are related spatially to major Rome Trough structures. Furthermore, Kulander and Dean (1980b) postulate that cover movement towards the southeast into the trough may have occurred

during middle and late Paleozoic time. This observation is based upon the southeastward asymmetry of a number of supra-Martinsburg folds within the trough.

The Rome Trough in West Virginia has undoubtedly affected the regional tectonics, as well as intra-trough in-situ and paleostresses. The north-east trending joints cut by the RET #1 well comply with a regional joint pattern shown by surrounding well and outcrop data. Furthermore, these joints are approximately parallel to the northeast trending Rome Trough bounding faults in West Virginia. In addition, joint directions are roughly parallel to Devonian basin contours. These geometrical relationships suggest that these first-formed joints developed early in a subsiding basin in which the principal fracturing tension (least effective stress) was perpendicular to basin contours. In contrast, the single northwest dipping reverse fault may have developed later in response to cover movement towards the southeast into the deeper sections of the Rome Trough. This movement may have occurred primarily over a detachment seated within the Ordovician Martinsburg formation, an incompetent unit throughout the central Appalachians. Such southeastward movement may have been partially due to increased differential compaction of the sedimentary section within the deepest sections of the Rome Trough. In addition, thrust faults cutting Devonian shale cores within the trough may be related to such movement.

In summary, documented joint, fault, and fold trends within the Rome Trough may differ from the trend of these structural features outside the trough. In addition, structural trends within the trough may change subtly or abruptly over intra-trough basement structures. These changes are reflected in the fact that in-situ and paleostresses seem to have been affected by the presence of Rome Trough structure (Kulander and Dean, 1983, and Figure 23).

SUMMARY

1. Fifteen (15) natural joints cut by the RET #1 well trended from N30°E to N40°E, with dips ranging from 77°NW to 83°SE. Mean natural joint orientation was N37°E, 87°NW.

2. Six (6) faults, distinguished by slickenline development, had a mean trend of N22°E, 56°NW. Slickenline steps indicated final movement in a normal sense for five faults and a reverse sense for one fault. All faults were located in a shear zone from a drilled length of 4140.8 to 4142.0 feet.
3. Coring-induced SVIF fractures had a mean trend of N52°E, vertical, and were perpendicular to the core axis. Development of these fractures was most likely controlled by drilling-induced stresses, a rock anisotropy not reflected by natural joint development, or a combination of both of these factors.
4. Natural joint and fault trends paralleled those found in Devonian shale outcrops to the west and in adjacent Devonian shale cores. In outcrop, these northeast trending joints were generally first-formed and pervasive.
5. Natural joint and fault geometrical relationships to Rome Trough basement contours and shale isopach geometry suggest that these structures are related to Devonian basin history and Rome Trough related stresses.
6. No nonsystematic joints orthogonal to the N37°E trending cored joints were observed in the RET #1 well. Therefore, to maximize joint penetration, perhaps future deviated wells should be drilled at 45 degrees to the perceived systematic joint trend. However, this procedure would place joint trends at a lower angle to the core axis and could cause problems during subsequent stimulation.

REFERENCES CITED

- Ammerman, M.L. and Keller, G.E., 1978. Delineation of Rome Trough in Eastern Kentucky by Gravity and Deep Drilling Data. American Association of Petroleum Geologists Bulletin, V. 63/3, p. 341-353.
- Colton, G.W., Perry, W.J. and MacKenzie, J.D., 1981. Joint Patterns in the Central and Northeastern Appalachian Basin. United States Geological Survey Open File Report 81-873 and 81-838.
- Ervin, C.P. and McGinnis, L.O., 1975. Reelfoot Rift; Reactivated Precursor of the Mississippi Embayment. Geological Society of America Bulletin, V. 86, p. 1287-1395.
- Evans, M.A., 1979. Fractures in Oriented Devonian Shale Cores from the Appalachian Basin. Unpublished M.S. Thesis, West Virginia University, Morgantown, WV, 278 p.
- Kulander, B.R., Barton, C.C., and Dean, S.L., 1979. The Application of Fractography to Core and Outcrop Fracture Investigations. United States Department of Energy, METC/SP-79/3, available from National Technical Information Service, Springfield, VA, 174 p.
- Kulander, B.R., Dean, S.L., and Williams, R.E., 1980a. Fracture Trends in the Allegheny Plateau of West Virginia. West Virginia Geological and Economic Survey Map WV-11, Scale 1:250,000.
- Kulander, B.R. and Dean, S.L., 1980b. Rome Trough Relationship to Fracture Domains, Regional Stress History, and Decollement Structures. In R. Wheeler and C.S. Dean, eds., Western Limits of Detachment and Related Structures in the Appalachian Foreland, 1978, DOE/METC/SP-80/23, available from National Technical Information Services, U.S. Department of Commerce, Springfield, VA, V. 22161, p. 64-73.
- Kulander, B.R. and Dean, S.L., 1983. Fracture Domains in the Allegheny Plateau of West Virginia; in the Fourteenth Annual Appalachian Petroleum Geology Symposium, West Virginia Geological and Economic Survey, Circular No. C-31, p. 34-38.
- Kulander, B.R. and Dean, S.L., 1985. Hackle Plume Geometry and Joint Propagation Dynamics. In O. Stephansson, ed., Fundamentals of Rock Joints, Centek Publishers, Lulea, Sweden, p. 85-94.
- Kulander, B.R. and Dean, S.L., 1986. Structure and Tectonics of Central and Southern Appalachian Valley and Ridge and Plateau Provinces, West Virginia and Virginia. American Association of Petroleum Geologists Bulletin, V. 70/11, p. 1674-1684.
- Long, B.R., 1979. Regional Survey of Surface Fractures in Eastern Kentucky. Unpublished M.S. Thesis, West Virginia University, 66 p.

- Overbey, W.K., 1976. Effect of In-Situ Stresses on Induced Fractures. In Devonian Shale Production and Potential. Proc. Seventh Appalachian Petroleum Geology Symposium, US/ERDA, Morgantown Energy Research Center, MERC/SP-76/2, p. 1822-211.
- Patchen, D.G., 1977. Subsurface Stratigraphy and Gas Production of the Devonian Shales in West Virginia. MERC/CR-77/5, Department of Energy, Morgantown Energy Technology Center, Morgantown, WV, 35 p.
- Schranz, J.K., 1984. Regional Gravity Survey and Modeling of the Rome Trough in Southwest West Virginia, unpublished M.S. Thesis, Wright State University, 87 p.
- Wagner, W.R., 1976. Growth Faults in Cambrian and Lower Ordovician Rocks of Western Pennsylvania: American Association of Petroleum Geologists Bulletin, V. 60/3, p. 414-427.
- Webb, E.J., 1980. Cambrian Sedimentation and Structural Evolution of the Rome Trough in Kentucky. Unpublished Ph.D. Dissertation, University of Cincinnati, 95 p.
- Wise, D.V., Micelli, L.J., and Baginski, P., 1980. Brittle Fracture Patterns on a Traverse of the Big Sandy Gas Field, Kentucky. In R. Wheeler and C.S. Dean, eds., Western Limits of Detachments and Related Structures in the Appalachian Foreland; 1978, DOE/METC/SP-80/23. Available from National Technical Information Service, U.S. Department of Commerce, Springfield, VA, V. 22161, p. 133-148.

FIGURE 2 - ROSE DIAGRAM
SHOWING NATURAL JOINT
TRENDS

FIGURE 3 LINE DRAWING OF VERTICAL NATURAL JOINT WITH HACKLE PLUME - CIRCLES SHOW POSSIBLE PENETRATION LOCATIONS WITH PLUME - ARROWS SHOW FRACTURE PROPAGATION DIRECTIONS WITHIN CORED JOINT SEGMENTS, NOTE THAT DRILLING DIRECTION 45° TO SYSTEMATIC JOINT TREND COULD POSSIBLY PENETRATE MORE JOINTS

ROWAN CO. KY

48 MILES

WAYNE
CO.
WV

FIGURE 5

DEVONIAN SHALE JOINTS IN OUTCROP

from Long 1979

Joints Formed First

10 0 10 20
MILES

WHITLEY
CO.

VA

KY
TN

GENERAL SHALE
COMPOSITE

N=1622

10 0 10 20
MILES

MISS.-PENN.
SHALE JOINTS
B. LONG (1979)
First
Joints Formed Second

FIGURE 6

WAYNE
CO.

KENTUCKY
WEST VIRGINIA

ROWAN CO. KY. — 48 MILES —> WAYNE CO. WV

FIGURE 7

NATURAL FRACTURE DIRECTIONS IN OUTCROP
ROWAN CO. KY
COLTON ET. AL. 1980

415 LANDSAT LINEAMENTS
JENKINS, KY. 2° QUAD

IMAGE = 2386 , FEB. 12 , 1976
SUN ELEVATION = 28° , SUN AZIMUTH = 141°
AVG. LINEAR LENGTH = 9.99 KM

FIGURE 8

WISE ET. AL., 1980

Wise ET AL., 1980

FIGURE 9

FIGURE 10
KULANDER & DEAN (1986)

FIGURE 11. Two natural joints 4075.7 and 4076.2 feet. These joints were smooth and planar and sub-orthogonal to the core axis.

} Twist
Hackle

FIGURE 11. Surface structures on natural joint faces. Note twist hackle fringe or band on natural fracture immediately above. Arrows show local fracture propagation directions indicated by plumes.

FIGURE 13. Fault and joint zone cutting the core at 4140.8 to 4142 feet. Note two smooth and planar joints immediately to the right of the scale (shown by arrows). These two joints are shown close-up in figure 11.

FIGURE 13. Photos showing slickensided fault surfaces. Photo to left shows slickenlines superposed on plume structure. Such a sequence suggests brittle failure preceded fault movement. Photo to right shows faint slickenlines that upon close examination showed steps indicating a normal sense of movement. Steps are not evident on the photo.

FIGURE 14-ROSE DIAGRAM
SHOWING CORING-INDUCED
SVIF FRACTURE TRENDS

FIGURE 15a LINE DRAWING DEPICTING VARIOUS MORPHOLOGIES AND
 HACKLE PLUME GEOMETRIES FOR CORING-INDUCED SVIF FRACTURES
 OF THE FIRST TYPE AS DESCRIBED IN THE TEXT

FIGURE 15b LINE DRAWINGS DEPICTING VARIOUS MORPHOLOGIES
AND HACKLE PLUME GEOMETRIES FOR CORING-INDUCED SVIF
FRACTURES OF THE SECOND OR BARBED TYPE

FIGURE 16. Panorama of SVIF fractures of the first type described in text. Note regular spacing for SVIF fractures in this core section. Also note SVIF fracture of the second type described in text -- BP fracture -- natural joint.

FIGURE 16. Close-up of two SVIF fractures of the first type described in text. Note natural joint (arrow) in foreground.

FIGURE 16. SVIF fractures of the second type described in text. Note basal barbs. Generally these fractures showed a regular spacing as shown in figure 1.

FIGURE 16. A sub-vertical irregular fracture (SVIF) of the second type described in text. Note abrupt barb at core bottom.

FIGURE 17 LINE DRAWING DEPICTING VARIOUS TYPES OF
MORPHOLOGIES FOR CORING-INDUCED BP FRACTURES

FIGURE 18. Bedding parting (BP) fractures. Top photo shows BP fracture cutting to core margin at low angle to bedding. Note sharp hook to core margin. This fracture was not related to scribe knife.

Photo to side shows BP fracture with continuous origin at scribe knife. Note arrest lines

FIGURE 19. Typical spiral plume on helical fracture face of torsion fracture. Arrows show local propagation directions radiating from origin.

FIGURE 20 - Rome
TROUGH STRUCTURE
from Webb (1980)

FIGURE 21 - ROME
TROUGH STRUCTURE
from Schrantz (1984)
.. see figure 10 for
basement depths

POSTULATED
MAXIMUM COMPRESSIVE
STRESS TRAJECTORIES

SCALE

FIGURE 22
from Overbey (1976)
Evans (1980)

Characteristic Coal Fracture Trends of the Allegheny Plateau.
(from Kulander, Dean, and Williams, 1980)

FIGURE 23
COAL FRACTURE DOMAINS
AND IN SITU STRESS
DOMAINS - WEST VIRGINIA
KULANDER AND DEAN (1983)

APPENDIX F

DAILY REPORT OF WELL DRILLING OPERATIONS

BDM DAILY REPORT

WELL NAME: BDM/DDE ENEGER RET#1 DATE: 10-20-86 REPORT TIME: 8:00 A.M.
DEPTH: 0 FOOTAGE: 0 ACTIVITY: RIGGING UP
FORMATION: HLU: HLD: TORQUE:
ROTATING WEIGHT:

BIT RECORD:

BIT	SERIAL			DEPTH		FOOT--	FT/				
#	SIZE	TYPE	MANUF	#	IN	OUT	AGE	HR	WT	RPM	CONDITION

AIR RATE: MIST RATE: BBLs/HR PRESSURE:
ADDITIVES:

BHA:

[illegible]

```
GAS:  C1:      "  C2:      ,  C3:      ,  C4:      ,  C5:      ,  C5+:      ,  TOT:
SHOWS:
```

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS
------	----	-----

RIGGING UP. HAVE SUBSTRUCTURE AND DRAWWORKS SET

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGET RET#1 DATE: 10-21-86 REPORT TIME: 8:00 A.M.
 DEPTH: 0 FOOTAGE: 0 ACTIVITY: RIGGING UP
 FORMATION: HLU: HLD: TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
-------	------	------	-------	----------	----------	-----------	----------	-------	----	-----	-----------

AIR RATE: MIST RATE: BBLS/HR PRESSURE:
 ADDITIVES:

BHA:

SURVEYS: 0, 0, @ / 0, 0, @ / 0, 0, @ / 0, 0, @ /

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM TO HRS
 RIGGING UP. HAVE MOST OF THE RIG ASSEMBLED.

BIT RECORD: 00

AIR RATE: 2100 MIST RATE: BBLs/HR PRESSURE: 100
ADDITIVES:

SURVEYS: 0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-2:00	6	RIGGING UP DRILLING RIG.	
2:00PM-4:00	2	DRILLING RAT HOLE AND MOUSE HOLE.	
4:00PM-6:30	2.5	RIGGING UP TO DRILL CONDUCTOR HOLE.	
6:30PM-12:30	6	DRILLING CONDUCTOR HOLE TO 48 FEET.	
12:30AM-8:00	7.5	RIG UP AND RUN 20 INCH CONDUCTOR TO 48' KB. NIPPLING UP CONDUCTOR PIPE.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 10-23-86 REPORT TIME: 8:00 A.M.
 DEPTH: 160 FOOTAGE: 112 ACTIVITY: WAITING ON FISHING TOOLS
 FORMATION: HLU: HLD: TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
1	18.5				48	160	112	14.9	5	60	LOST SHAN

AIR RATE: 2100 MIST RATE: BBL S/HR PRESSURE: 100
 ADDITIVES:

BHA: BIT, AIR HAMMER, X-0, 2-6 1/4 DC15

SURVEYS: 0, 0, @ 0, @ 0, @ 0, @ 0, @ 0, @

GAS: C1: C2: C3: C4: C5: C5+: TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM	5:00	7	NIPPLE UP CONDUCTOR PIPE AND MAKE UP BHA.
5:00PM	12:30	7.5	DRILL SURFACE HOLE FROM 48' TO 160'
12:30AM	2:00	1.5	BIT WOULD NOT DRILL AFTER MAKING A CONNECTION AND WAS TORQUING UP. TRIP OUT. LOST 2 SHANKS OFF OF BIT.
2:00AM	8:00	6	WAITING ON FISHING TOOLS.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 10-24-86 REPORT TIME: 8:00 A.M.
 DEPTH: 160' FOOTAGE: 0' ACTIVITY: FISHING
 FORMATION: _____ HLU: _____ HLD: _____ TORQUE: _____
 ROTATING WEIGHT: _____

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN OUT	FOOT- AGE	FT/ HR	WT	RPM	CONDITION
----------	------	------	-------	-------------	-----------------	--------------	-----------	----	-----	-----------

AIR RATE: _____ MIST RATE: _____ BBLs/HR _____ PRESSURE: _____
 ADDITIVES: _____

BHA:

SURVEYS: _____

GAS: C1: _____, C2: _____, C3: _____, C4: _____, C5: _____, C5+: _____, TOT: _____
 SHOWS: _____

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-3:00	7	FABRICATING FINGER BASKET AT THE RIG TO FISH FOR LOST BIT SHANKS.	
3:00PM-4:00	1	RUN FINGER BASKET. NO LUCK CATCHING FISH. MODIFY BASKET.	
4:00PM-5:00	1	RUN BASKET. HAD 15 FEET OF FILL ON BOTTOM. DID NOT GET 10 FISH.	
5:00PM-8:00	3	RUN 17 1/2" BIT AND CLEAN OUT FILL.	
8:00PM-8:00	12	RUNNING FABRICATED FINGER BASKET TO FISH FOR LOST BIT SHANKS. RAN THE BASKET FIVE TIMES WITH NO RECOVERY. MODIFIED THE THE FINGERS ON THE BASKET EACH TRIP.	

RDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 10-25-86 REPORT TIME: 8:00 A.M.
DEPTH: 30 FOOTAGE: 30 ACTIVITY: PREPARE TO RUN CONDUCTOR
FORMATION: HLU: HLD: TORQUE:
ROTATING WEIGHT:

BIT RECORD:

BIT				SERIAL	DEPTH		FOOT--	FT/			
#	SIZE	TYPE	MANUF	#	IN	OUT	AGE	HR	WT	RPM	CONDITION

AIR RATE: 2100SCFM MIST RATE: BBL5/HR PRESSURE: 100PSI
ADDITIVE5:

BHA: 22" BIT, AIR HAMMER, X-O, KELLY

SURVEYS: O " O , @ O " O , @
O " O , @ O " O , @

```
GAS:  C1:      , C2:      , C3:      , C4:      , C5:      , C5+:      , TOT:
SHOWS:
```

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-9:00	1	FISHING	
9:00AM-1:00	4	DECIDED TO SKID THE RIG. PREPARING TO SKID.	
1:00PM-2:30	1.5	SKID RIG 15 FEET TO THE WEST. RIG UP.	
2:30PM-4:00	1.5	DRILL RAT HOLE AND MOUSE HOLE.	
4:00PM-6:00	2	WAIT FOR 22" BIT TO ARRIVE ON LOCATION.	
6:00PM-7:00	1	MAKE UP BIT AND BHA.	
7:00PM-7:00	12	DRILL THE CONDUCTOR HOLE TO 30 FEET.	
7:00AM-8:00	1	TRIP OUT OF THE HOLE AND LAY DOWN THE BHA.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 10-26-86 REPORT TIME: 8:00 A.M.
 DEPTH: 70 FOOTAGE: 40 ACTIVITY: REPAIRING AIR HEAD
 FORMATION: _____ HLU: _____ HLD: _____ TORQUE: _____
 ROTATING WEIGHT: _____

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
2	18.5		HTC		30		40	7.27	5	60	

AIR RATE: 2100 MIST RATE: _____ BBLs/HR _____ PRESSURE: 150
 ADDITIVES: _____

BHA: BIT, AIR HAMMER, X-0, 6 1/4" DRILL COLLAR

SURVEYS: _____

GAS: C1: _____, C2: _____, C3: _____, C4: _____, C5: _____, C5+: _____, TOT: _____
 SHOWS: _____

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-4:30	8.5		RUN 20" CONDUCTOR PIPE TO 30 FEET KB. NIPPLE UP ON CONDUCTOR AND MAKE UP BHA. WELD STRAPS ONTO THE 18 1/2" BIT TO MAKE IT STRONGER.
4:30PM-5:30	1		DRILLING TO 40 FEET.
5:30PM-2:00	8.5		MAKE CONNECTION. AIR HEAD WILL NOT GO BACK INTO BOWL. REPAIRING AIR HEAD.
2:00AM-3:00	2		DRILLING TO 52 FEET. CHANGED TO STANDARD TIME.
3:00AM-4:30	1.5		MAKE CONNECTION AND CHECK BIT FOR CRACKS.
4:30AM-7:00	2.5		DRILLING TO 70 FEET.
7:00AM-8:00	1		REPAIRING AIR HEAD.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 10-27-86 REPORT TIME: 8:00 A.M.
 DEPTH: 224 FOOTAGE: 154 ACTIVITY: DRILLING
 FORMATION: HLU: HLD: TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
2	18.5	F4R	HTC		30	161	131	10.48	10	50	CRACKED
3	17.5	HH88	SEC		161		63	7.41	20	60	

AIR RATE: 2100 SCFM MIST RATE: BBLs/HR PRESSURE: 100 PSI
 ADDITIVES:

BHA: BIT, X-O, 6-6 1/4" COLLARS

SURVEYS: 0, 0, @ 0, @ 0, @ 0, @ 0, @
0, 0, @ 0, 0, @ 0, @

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-9:30	1.5	WORK ON AIR HEAD. CUT NEW BOLT HOLES AND RECENTER AIR HEAD UNDER THE ROTARY TABLE.	
9:30AM-1:00	3.5	DRILLING TO 120 FEET.	
1:00PM-2:30	1.5	PULL BIT AND CHECK FOR CRACKS. NO CRACKS	
2:30PM-4:00	1.5	DRILLING TO 132 FEET.	
4:00PM-4:30	.5	SERVICE RIG.	
4:30PM-6:30	2	DRILLING TO 161 FEET.	
6:30PM-7:30	1	PULL OUT OF HOLE TO CHECK BIT. BIT SHANK IS CRACKED BY THE NOZZLE.	
7:30PM-11:30	4	LAY DOWN AIR HAMMER. PICK UP NEW BIT. MAKE UP BIT AND TRIP IN HOLE.	
11:30PM-8:00	8.5	DRILLING TO 224 FEET WITHOUT AIR HAMMER.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 10-28-86 REPORT TIME: 8:00 A.M.
 DEPTH: 433 FOOTAGE: 209 ACTIVITY: DRILLING
 FORMATION: SANDSTONE HLU: 50000 HLD: 50000 TORQUE:
 ROTATING WEIGHT: 50000

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
3	17.5	HH88	SEC		161	426	265	10.6	35	60	CONE LOCK
4	17.5	HH88	SEC		426			7.0	40	60	

AIR RATE: 2100 SCFM MIST RATE: BBLs/HR PRESSURE: 120 PSI
 ADDITIVES:

BHA: BIT, X-O, 6 1/4 INCH DRILL COLLARS.

SURVEYS: 1/2 °, °, @ 295' °, °, @
°, °, @ °, °, @

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-3:30	7.5		DRILLING TO 295 FEET. MISTED FOR A SHORT PERIOD OF TIME AT 225 FEET BECAUSE THE WELL WAS MAKING A LITTLE WATER.
3:30PM-4:00	.5		SURVEY AT 295 FEET. SURVEY WAS 1/2 DEGREE.
4:00PM-1:00	9		DRILLING TO 426 FEET.
1:00AM-7:00	6		BIT TORQUED UP. TRIP OUT. HAD ONE CONE LOCKED UP. RUN NEW BIT AND TRIP IN HOLE.
7:00AM-8:00	1		DRILLING TO 433 FEET.

INSPECTED 173 JOINTS OF DRILL PIPE. FOUND THREE JOINTS WITH DEFECTS AND 42 JOINTS BENT. THE INSPECTION COMPANY SAID THE PIPE HAD BEEN IN HYDROGEN SULFIDE SERVICE BECAUSE OF THE BLACK SCALE ON THE PIPE.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 10-29-86 REPORT TIME: 8:00 A.M.
DEPTH: 660 FOOTAGE: 227 ACTIVITY: TRIP OUT TO RUN CASING
FORMATION: SANDSTONE HLU: 60000 HLD: 60000 TORQUE:
ROTATING WEIGHT: 60000

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
4	17.5	HH88	SEC		426	602	176	13.54	40	60	LOCK CONE
5	17.5	HH88	SEC		602	660	58	14.5	40	60	

AIR RATE: 2100 SCFM MIST RATE: 5 BBLS/HR PRESSURE: 150 PSI
ADDITIVES:

BHA: SAME

SURVEYS: 1/2", 1", 2", 3", 4", 5", 6", 7", 8", 9", 10", 11", 12", 13", 14", 15", 16", 17", 18", 19", 20", 21", 22", 23", 24", 25", 26", 27", 28", 29", 30", 31", 32", 33", 34", 35", 36", 37", 38", 39", 40", 41", 42", 43", 44", 45", 46", 47", 48", 49", 50", 51", 52", 53", 54", 55", 56", 57", 58", 59", 60", 61", 62", 63", 64", 65", 66", 67", 68", 69", 70", 71", 72", 73", 74", 75", 76", 77", 78", 79", 80", 81", 82", 83", 84", 85", 86", 87", 88", 89", 90", 91", 92", 93", 94", 95", 96", 97", 98", 99", 100", 101", 102", 103", 104", 105", 106", 107", 108", 109", 110", 111", 112", 113", 114", 115", 116", 117", 118", 119", 120", 121", 122", 123", 124", 125", 126", 127", 128", 129, 130, 131, 132, 133, 134, 135, 136, 137, 138, 139, 140, 141, 142, 143, 144, 145, 146, 147, 148, 149, 150, 151, 152, 153, 154, 155, 156, 157, 158, 159, 160, 161, 162, 163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 83

```
GAS: C1:      , C2:      , C3:      , C4:      , C5:      , C5+:      , TOT:
SHOWS:
```

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-8:30	.5	SURVEY AT 439 FEET.	
8:30AM-1:00	4.5	DRILLING TO 499 FEET.	
1:00PM-1:30	.5	BOLTS WORKED LOSE ON THE AIR HEAD. TIGHTENED SAME.	
1:30PM-8:00	6.5	DRILLING TO 589 FEET.	
8:00PM-9:00	1	NIPPLE BROKE ON MIST PUMP. REPAIR THE NIPPLE.	
9:00PM-10:00	1	DRILLING TO 602 FEET.	
10:00PM-12:30	2.5	BIT TORQUING UP. BLOW HOLE AND TRIP OUT TO CHECK BIT. CONE LOCKED UP.	
12:30AM-2:00	1.5	TRIP IN HOLE.	
2:00AM-2:30	.5	UNLOAD HOLE.	
2:30AM-6:30	4	DRILLING TO 660 FEET.	
6:30AM-7:30	1	CIRCULATE TO CLEAN HOLE.	
7:30AM-8:00	.5	TRIP OUT OF HOLE.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 10-30-86 REPORT TIME: 8:00 A.M.
DEPTH: 660 FOOTAGE: 0 ACTIVITY: REAMING
FORMATION: SANDSTONE HLU: HLD: TORQUE:
ROTATING WEIGHT:

BIT RECORD:

BIT	SIZE	TYPE	MANUF	SERIAL	DEPTH	FOOT-	FT/	WT	RPM	CONDITION
#				#	IN	OUT	AGE	HR		
RR5	17.5	HH88	SEC							REAMING

AIR RATE: 1100 SCFM MIST RATE: BBLs/HR PRESSURE: 50 PSI
ADDITIVES:

BHA: BIT, 17.5" REAMER, X-O, X-O, 6 1/4" DRILL COLLARS

SURVEYS: ☐ " ☐ " ☒ " ☐ " ☐ " ☐ " ☐ "

☐ " ☐ " ☒ " ☐ " ☐ " ☐ " ☐ "

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-9:00	1		FINISH TRIP OUT OF HOLE.
9:00AM-10:30	1.5		TRY TO RUN 16 INCH CASING BUT IT WOULD NOT GO. PULL CONDUCTOR PIPE. CONDUCTOR WAS SLIGHTLY BENT ON BOTTOM.
10:30AM-1:00	2.5		RUN TWO JOINTS OF 16 INCH CASING. HAD APPROXIMATELY 60 FEET IN HOLE AND WOULD NOT GO ANY FARTHER EVEN AFTER DRIVING ON IT. TOOK 80,000 POUNDS TO PULL IT BACK OUT.
1:00PM-2:00	1		LAY DOWN CASING.
2:00PM-8:00	6		WAIT FOR 17 1/2 INCH THREE POINT REAMER TO ARRIVE ON LOCATION IN ORDER TO REAM THE HOLE.
8:00PM-9:30	1.5		PICK UP THREE POINT REAMER.
9:30PM-8:00	10.5		REAMING. REAMED HARD AT 60 FEET. REAMING AT 475 FEET.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 10-31-86 REPORT TIME: 8:00 A.M.
DEPTH: 660 FOOTAGE: 0 ACTIVITY: WAITING ON CEMENT
FORMATION: HLU: HLD: TORQUE:
ROTATING WEIGHT:

BIT RECORD:

BIT	SIZE	TYPE	MANUF	SERIAL	DEPTH	FOOT--	FT/	WT	RPM	CONDITION
#				#	IN	OUT	AGE	HR		

AIR RATE: MIST RATE: BBLs/HR PRESSURE:

ADDITIVES:

BHA:

[illegible]

```
GAS:  C1:      , C2:      , C3:      , C4:      , C5:      , C5+:      , TOT:
SHOWS:
```

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-10:30	2.5		REAMING FROM 475 FEET TO 660 FEET. NOT REAMING HARD.
10:30AM-11:00	.5		CIRCULATE TO CLEAN HOLE.
11:00AM-11:30	.5		TRIP OUT OF HOLE.
11:30AM-4:00	4.5		RUN 649.43 FEET OF 16 INCH CASING. CASING SET AT 649.43 FEET KB. HOLE WAS TIGHT BETWEEN 300 AND 400 FEET AND ON THE LAST JOINT. CASING IS 16", 65#/FT, H-40, BUTTRESS.
4:00PM-8:00	4		WAIT ON HALLIBURTON TO ARRIVE ON LOCATION.
8:00PM-11:00	3		RIG UP HALLIBURTON. FILL CASING WITH WATER AND CIRCULATE.
11:00PM-12:00	1		CEMENT CASING WITH 5 BARRELS OF GELLED WATER FOLLOWED BY 270 SACKS OF CLASS A CEMENT CONTAINING 3% CALCIUM CHLORIDE AND DISPLACED WITH 142 BARRELS OF WATER. LEFT 20 FEET OF CEMENT INSIDE OF CASING. CIRCULATED 10 BARRELS OF GOOD CEMENT BACK TO SURFACE. MIXED CEMENT AT 15.6 PPG WITH A YEILD OF 1.18 CUBIC FEET PER SACK.
12:00AM-8:00	8		WAIT ON CEMENT.

 
18-29	~65%
30-49	~75%
50-69	~80%
70+	~85%

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 11-1-86 REPORT TIME: 8:00 A.M.
DEPTH: 896 FOOTAGE: 236 ACTIVITY: DRILLING
FORMATION: SHALE HLU: 70000 HLD: 70000 TORQUE:
ROTATING WEIGHT: 70000

BIT RECORD:

BIT				SERIAL	DEPTH		FOOT-	FT/			
#	SIZE	TYPE	MANUF	#	IN	OUT	AGE	HR	WT	RPM	CONDITION
6	14.75	J44	HTC		660		236	24.8	35	60	

AIR RATE: 2100 SCFM MIST RATE: BBLs/HR PRESSURE: 120 PSI
ADDITIVES:

BHA: BIT, X-0, 2-8" DC'S, X-0, X-0, 17-6 1/4" DC'S

SURVEYS: ☐ 1 ☐ 2 ☐ 3 ☐ 4 ☐ 5 ☐ 6 ☐ 7 ☐ 8 ☐ 9 ☐ 10 ☐ 11 ☐ 12 ☐ 13 ☐ 14 ☐ 15 ☐ 16 ☐ 17 ☐ 18 ☐ 19 ☐ 20 ☐ 21 ☐ 22 ☐ 23 ☐ 24 ☐ 25 ☐ 26 ☐ 27 ☐ 28 ☐ 29 ☐ 30 ☐ 31 ☐ 32 ☐ 33 ☐ 34 ☐ 35 ☐ 36 ☐ 37 ☐ 38 ☐ 39 ☐ 40 ☐ 41 ☐ 42 ☐ 43 ☐ 44 ☐ 45 ☐ 46 ☐ 47 ☐ 48 ☐ 49 ☐ 50 ☐ 51 ☐ 52 ☐ 53 ☐ 54 ☐ 55 ☐ 56 ☐ 57 ☐ 58 ☐ 59 ☐ 60 ☐ 61 ☐ 62 ☐ 63 ☐ 64 ☐ 65 ☐ 66 ☐ 67 ☐ 68 ☐ 69 ☐ 70 ☐ 71 ☐ 72 ☐ 73 ☐ 74 ☐ 75 ☐ 76 ☐ 77 ☐ 78 ☐ 79 ☐ 80 ☐ 81 ☐ 82 ☐ 83 ☐ 84 ☐ 85 ☐ 86 ☐ 87 ☐ 88 ☐ 89 ☐ 90 ☐ 91 ☐ 92 ☐ 93 ☐ 94 ☐ 95 ☐ 96 ☐ 97 ☐ 98 ☐ 99 ☐ 100 ☐ 101 ☐ 102 ☐ 103 ☐ 104 ☐ 105 ☐ 106 ☐ 107 ☐ 108 ☐ 109 ☐ 110 ☐ 111 ☐ 112 ☐ 113 ☐ 114 ☐ 115 ☐ 116 ☐ 117 ☐ 118 ☐ 119 ☐ 120 ☐ 121 ☐ 122 ☐ 123 ☐ 124 ☐ 125 ☐ 126 ☐ 127 ☐ 128 ☐ 129 ☐ 130 ☐ 131 ☐ 132 ☐ 133 ☐ 134 ☐ 135 ☐ 136 ☐ 137 ☐ 138 ☐ 139 ☐ 140 ☐ 141 ☐ 142 ☐ 143 ☐ 144 ☐ 145 ☐ 146 ☐ 147 ☐ 148 ☐ 149 ☐ 150 ☐ 151 ☐ 152 ☐ 153 ☐ 154 ☐ 155 ☐ 156 ☐ 157 ☐ 158 ☐ 159 ☐ 160 ☐ 161 ☐ 162 ☐ 163 ☐ 164 ☐ 165 ☐ 166 ☐ 167 ☐ 168 ☐ 169 ☐ 170 ☐ 171 ☐ 172 ☐ 173 ☐ 174 ☐ 175 ☐ 176 ☐ 177 ☐ 178 ☐ 179 ☐ 180 ☐ 181 ☐ 182 ☐ 183 ☐ 184 ☐ 185 ☐ 186 ☐ 187 ☐ 188 ☐ 189 ☐ 190 ☐ 191 ☐ 192 ☐ 193 ☐ 194 ☐ 195 ☐ 196 ☐ 197 ☐ 198 ☐ 199 ☐ 200 ☐ 201 ☐ 202 ☐ 203 ☐ 204 ☐ 205 ☐ 206 ☐ 207 ☐ 208 ☐ 209 ☐ 210 ☐ 211 ☐ 212 ☐ 213 ☐ 214 ☐ 215 ☐ 216 ☐ 217 ☐ 218 ☐ 219 ☐ 220 ☐ 221 ☐ 222 ☐ 223 ☐ 224 ☐ 225 ☐ 226 ☐ 227 ☐ 228 ☐ 229 ☐ 230 ☐ 231 ☐ 232 ☐ 233 ☐ 234 ☐ 235 ☐ 236 ☐ 237 ☐ 238 ☐ 239 ☐ 240 ☐ 241 ☐ 242 ☐ 243 ☐ 244 ☐ 245 ☐ 246 ☐ 247 ☐ 248 ☐ 249 ☐ 250 ☐ 251 ☐ 252 ☐ 253 ☐ 254 ☐ 255 ☐ 256 ☐ 257 ☐ 258 ☐ 259 ☐ 260 ☐ 261 ☐ 262 ☐ 263 ☐ 264 ☐ 265 ☐ 266 ☐ 267 ☐ 268 ☐ 269 ☐ 270 ☐ 271 ☐ 272 ☐ 273 ☐ 274 ☐ 275 ☐ 276 ☐ 277 ☐ 278 ☐ 279 ☐ 280 ☐ 281 ☐ 282 ☐ 283 ☐ 284 ☐ 285 ☐ 286 ☐ 287 ☐ 288 ☐ 289 ☐ 290 ☐ 291 ☐ 292 ☐ 293 ☐ 294 ☐ 295 ☐ 296 ☐ 297 ☐ 298 ☐ 299 ☐ 300 ☐ 301 ☐ 302 ☐ 303 ☐ 304 ☐ 305 ☐ 306 ☐ 307 ☐ 308 ☐ 309 ☐ 310 ☐ 311 ☐ 312 ☐ 313 ☐ 314 ☐ 315 ☐ 316 ☐ 317 ☐ 318 ☐ 319 ☐ 320 ☐ 321 ☐ 322 ☐ 323 ☐ 324 ☐ 325 ☐ 326 ☐ 327 ☐ 328 ☐ 329 ☐ 330 ☐ 331 ☐ 332 ☐ 333 ☐ 334 ☐ 335 ☐ 336 ☐ 337 ☐ 338 ☐ 339 ☐ 340 ☐ 341 ☐ 342 ☐ 343 ☐ 344 ☐ 345 ☐ 346 ☐ 347 ☐ 348 ☐ 349 ☐ 350 ☐ 351 ☐ 352 ☐ 353 ☐ 354 ☐ 355 ☐ 356 ☐ 357 ☐ 358 ☐ 359 ☐ 360 ☐ 361 ☐ 362 ☐ 363 ☐ 364 ☐ 365 ☐ 366 ☐ 367 ☐ 368 ☐ 369 ☐ 370 ☐ 371 ☐ 372 ☐ 373 ☐ 374 ☐ 375 ☐ 376 ☐ 377 ☐ 378 ☐ 379 ☐ 380 ☐ 381 ☐ 382 ☐ 383 ☐ 384 ☐ 385 ☐ 386 ☐ 387 ☐ 388 ☐ 389 ☐ 390 ☐ 391 ☐ 392 ☐ 393 ☐ 394 ☐ 395 ☐ 396 ☐ 397 ☐ 398 ☐ 399 ☐ 400 ☐ 401 ☐ 402 ☐ 403 ☐ 404 ☐ 405 ☐ 406 ☐ 407 ☐ 408 ☐ 409 ☐ 410 ☐ 411 ☐ 412 ☐ 413 ☐ 414 ☐ 415 ☐ 416 ☐ 417 ☐ 418 ☐ 419 ☐ 4

```
GAS: C1:      , C2:      , C3:      , C4:      , C5:      , C5+:      , TOT: 0_UNITS
SHOWS: NONE
```

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-10:00	2		CUT OFF AND NIPPLE UP ON 16 INCH.
10:00AM-1:30	3.5		MAKE UP BHA AND NIPPLE UP AIR HEAD ON TOP OF BIT.
1:30PM-3:00	1.5		TRIP IN HOLE AND BLOW WATER OUT.
3:00PM-5:30	1.5		RESET ROTARY TABLE. SERVICE RIG AND AIR PACKAGE. DRILL OUT CEMENT.
5:30PM-7:00	1.5		DRILLING TO 700 FEET.
7:00PM-8:00	1		DRYING UP HOLE AND WORKING ON MIST PUMP.
8:00PM-9:30	1.5		DRILL TO 743 FEET.
9:30PM-10:00	.5		FOAM HOLE TO MAKE SURE IT IS UNLOADED. HOLE IS NOT MAKING ANY WATER.
10:00PM-10:30	.5		DRILLING TO 789 FEET. BIT IS TORQUING SLIGHTLY.
10:30PM-12:00	1.5		TRIP OUT OF HOLE TO CHECK BIT. BIT LOOKS OK. RERUN BIT.
12:00AM-2:00	2		TRIP IN HOLE AND ESTABLISH CIRCULATION.
2:00AM-8:00	6		DRILLING TO 896 FEET.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-2-86 REPORT TIME: 8:00 A.M.
DEPTH: 1216 FOOTAGE: 320 ACTIVITY: DRILLING
FORMATION: SHALE HLU: 78000 HLD: 78000 TORQUE:
ROTATING WEIGHT: 78000

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN	DEPTH OUT	FOOT- AGE	FT/ HR	WT	RPM	CONDITION
6	14.75	J44	HTC	Z5813	660	1197	537	21.48	30	50	2-5-1
7	14.75	X33	HTC	LX363	1197		19	9.5	30	45	

2
AIR RATE: 2100 SCFM MIST RATE: 10 BBLs/HR PRESSURE: 160
ADDITIVES:

BHA: SAME

SURVEYS: 0, 1.250 @ 931' 0, 0, @

```
GAS: C1:      , C2:      , C3:      , C4:      , C5:      , C5+:      , TOT: 0
TRIP GAS: 10,000 FPM  SHOWS: NONE
```

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-9:30	1.5	DRILLING	
9:30AM-10:00	.5	SURVEY AT 931 FEET IS 1.25 DEGREES	
10:00AM-12:00	14	DRILLING TO 1197 FEET. DRILLING ROUGH.	
12:00AM-6:00	6	TRIP FOR BIT. BIT HAD ONE LOOSE BEARING OTHERWISE IT WAS IN GOOD SHAPE.	
6:00AM-8:00	2	DRILLING. BIT IS TORQUING AND DRILLING VERY ROUGH.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 11-3-86 REPORT TIME: 13:00 A.M.
DEPTH: 1625 FOOTAGE: 409 ACTIVITY: DRILLING
FORMATION: SHALE HLD: 80000 HLD: 80000 TORQUE: 11000
ROTATING WEIGHT: 80000

BIT RECORD:

BIT	SIZE	TYPE	MANUF	SERIAL	DEPTH	FOOT--	FT/	WT	RPM	CONDITION
#				#	IN	OUT	AGE	HR		
7	14.75	X-33	HTC	LX363	1197		428	17.12	15	55

AIR RATE: 2100 SCFM MIST RATE: 10 BLS/HR PRESSURE: 150-200 PSI
ADDITIVES: MF-1 TO FLOCCULATE OUT SOLIDS

BHA: SAME

SURVEYS: 1.50, 0, @ 1276, 0, 0, @

GAS: C1: 100, C2: , C3: , C4: , C5: , C5+: , TOT: 100PPM
SHOWS: CONNECTION GAS 130 PPM

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-10:30	2.5	DRILLING TO 1276 FEET	
10:30AM-11:00	.5	SURVEY, 1.5 DEGREES AT 1276 FEET	
11:00AM-4:30	5.5	DRILLING TO 1400 FEET.	
4:30PM-5:00	.5	SERVICE RIG AND AIR PACKAGE	
5:00PM-8:00	15	DRILLING ROUGH.	

BPM DAILY REPORT

WELL NAME: BDM/DOE ENERGY RETAIL DATE: 11-5-86 REPORT TIME: 8:00 A.M.
 DEPTH: 2124 SURFACE: 254 ACTIVITY: RIGGING UP TO RUN CASING
 ADDITION: SHT LIME AND SHALE HIT: 38000 HIT: 38000 TORQUE:
 TOTALING DEPTH: 38000

BIT RECORD:

BIT	SERIAL	DEPTH	FOOT-	FT/						
#	SIZE	TYPE	MANUF	#	IN	OUT	AGE	HR	WT	RPM
3	13.75	H11/2	HTC		1651	2124	473	24.25	40	150

AIR RATE: 3150 SCFM MIST RATE: 10 BBL/HR PRESSURE: 230 PSI
 ADDITIVES: MF-1

BHP: 38MF

SURVEYS: 0, 0.50, @ 1870' 0, 0, 0, @
 0, 0, @ 0, 0, @

GAS: C1:50000, C2:6500, C3:5500, C4:1000, C5:300, C5+: , TOT:65000
 SHOWS:NONE

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-9:00	1		CIRCULATE TO CLEAN HOLE BEFORE SURVEY.
9:00AM-9:30	.5		SURVEY AT 1870 FEET.
9:30AM-7:00	6		DRILLING.
	3.5		CIRCULATING BEFORE CONNECTION. HAD PROBLEMS CLEANING THE HOLE AFTER GOING THROUGH THE GAS ZONE. HAD TO CIRCULATE AFTER EACH KELLY DOWN. PUT 3150 SCFM ON THE HOLE AT 1933 FEET.
7:00PM-8:30	1.5		CIRCULATE TO CLEAN HOLE.
8:30PM-12:30	4		TRIP OUT OF HOLE TO RUN OPEN HOLE LOGS. LAYED DOWN ALL BUT 2-6 1/4 INCH COLLARS.
12:30AM-2:30	2		BREAK OFF BIT UNDER THE ROTARY TABLE.
2:30AM-7:00	4.5		RIG UP AND RUN OPEN HOLE LOGS. LOG TD WAS 2102 FEET. HAD 300 FEET OF WATER IN THE HOLE.
7:00AM-8:00	1		RIG UP TO RUN CASING.

LOG TOPS: BIG LIME 1682-1950

BIG INJUN 1954-1981

POROSITY ZONES: 1762-64 15% NO SHOW

1766-74 17% NO SHOW

1812-15 12% GAS SHOW 10,000PPM TG

1824-34 15% GAS SHOW 600,000PPM TG

1873-79 15% PROBABLY WATER

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-6-86 REPORT TIME: 8:00 A.M.
DEPTH: 2124 FOOTAGE: 0 ACTIVITY: NIPPLE UP
FORMATION: HLU: HLD: TORQUE:
ROTATING WEIGHT:

BIT RECORD:

BIT				SERIAL	DEPTH		FOOT-	FT/				
#	SIZE	TYPE	MANUF	#	IN	OUT	AGE	HR	WT	RPM	CONDITION	

AIR RATE: MIST RATE: BBLs/HR PRESSURE:
ADDITIVES:

BHA:

[illegible]

```
GAS:  C1:      , C2:      , C3:      , C4:      , C5:      , C5+:      , TOT:
SHOWS:
```

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-1:00	5		RUN 11 3/4", 47#, K-55, ST&C CASING AND SET AT 2024 FEET. RAN A GUIDE SHOE AND AN INSERT FLOAT VALVE ONE JOINT ABOVE THE SHOE. PLACED ONE CENTRALIZER ON THE BOTTOM 6 COLLARS.
1:00PM-3:00	2		CEMENT TO SURFACE WITH 350 SACKS OF HALLIBURTON LIGHT CONTAINING 3% CALCIUM CHLORIDE FOLLOWED BY 425 SACKS OF CLASS A CONTAINING 2% CALCIUM CHLORIDE. RAN 125 BBLs OF GEL FLUSH AHEAD OF CEMENT. DISPLACED WITH 232 BBLs OF WATER. PLUG DID NOT BUMP. FLOAT HELD OK. CIRCULATED GOOD CEMENT TO SURFACE.
3:00PM-4:00	1		RIG DOWN HALLIBURTON.
4:00PM-3:30	11.5		WAIT ON CEMENT.
3:30AM-4:30	1		NIPPLE DOWN HALLIBURTON HEAD AND CUT OFF CASING.
4:30AM-7:00	2.5		WAITING ON WELDER.
7:00AM-8:00	1		NIPPLING UP.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-7-86 REPORT TIME: 8:00 A.M.
 DEPTH: 2124 FOOTAGE: 0 ACTIVITY: TRIP
 FORMATION: HLU: 60000 HLD: 60000 TORQUE: 0
 ROTATING WEIGHT: 60000

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
9	10	5/8	HH44	HTC							DRILL CMT

AIR RATE: 2100 SCFM MIST RATE: 5 BBLs/HR PRESSURE: 160 PSI
 ADDITIVES:

BHA: BIT, 2-8" MONELS, X-0, X-0, 2-6 14" DC/S

SURVEYS: 0.50, 500W, @ 2083' 0, 0, @
 0, 0, @ 0, 0, @

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT: 0 PPM
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-2:30	6.5	NIPPLE UP ON 11 3/4" CASING.	
2:30PM-5:00	2.5	PICK UP, STRAP AND CALIPER THE BHA.	
5:00PM-7:00	2	RUN DRILL PIPE. INSTALL ROTATING HEAD RUBBER.	
7:00PM-8:00	1	BLOW WATER OUT OF HOLE. COMPRESSORS WENT DOWN BECAUSE THE FUEL LINE VALVES WERE CLOSED. RESTART COMPRESSORS.	
8:00PM-8:30	.5	FLOWLINE BLEW OFF WHILE CIRCULATING. REPLACE FLOWLINE.	
8:30PM-10:30	2	TRIP IN HOLE AND BLOW WATER OUT.	
10:30PM-11:00	.5	TAG CEMENT AT 1923 FEET. SERVICE DRILLING RIG.	
11:00PM-12:30	1.5	DRILL CEMENT AND PLUG TO THE FLOAT VALVE.	
12:30AM-4:00	3.5	DRILL FLOAT VALVE.	
4:00AM-6:00	2	DRILL OUT SHOE JOINT AND WASH TO BOTTOM.	
6:00AM-6:30	.5	CIRCULATE TO CLEAN HOLE.	
6:30AM-8:00	1.5	RUN DIRECTIONAL SURVEY. SURVEY MACHINE HAD TROUBLE PULLING THE SURVEY BACK OUT OF THE HOLE.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-8-86 REPORT TIME: 8:00 A.M.
 DEPTH: 2215 FOOTAGE: 102 ACTIVITY: TRIP
 FORMATION: SILT AND SHALE HLD: 63000 HLD: 62000 TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
9	10 5/8	HH44	HTC		2113	2215	102	34.0	5	300	GOOD
RR9	10 5/8	HH44	HTC		2215						

3

AIR RATE: 2100 SCFM MIST RATE: 10 BBLs/HR PRESSURE: 200
 ADDITIVES: SODA ASH, KCL, RAPID MUD, GRAPHITE, MF-1, AND FOAMER 80

BHA: BIT, BAKER MOTOR, FLOAT SUB, 2 1/2° BENT SUB, 8" MONEL, MWD, UBHO
 SUB, 8" MONEL, 2 6 1/4" DC'S

SURVEYS: .87°, 53.49°E, @2101.7' 2.62°, 53.35°E, @2133.8'
 4.52°, 59°E, @2165.6' 0, 0, @

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT: 866 1500
 SHOWS: HAD GAS AFTER DRILLING OUT SHOE AND BEFORE DRILLING ANY NEW HOLE.

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM	10:30	2.5	PULL OUT OF THE HOLE.
10:30AM	11:30	1	REPLACE SNUB LINES ON THE TONGS.
11:30AM	2:00	2.5	MAKE UP BHA AND MWD SYSTEM.
2:00PM	5:00	3	TRIP IN HOLE WITH MOTOR.
5:00PM	6:00	1	WAIT FOR GEOSCIENCE TO ARRIVE ON LOCATION.
6:00PM	7:00	1	ORIENT AND SURVEY.
7:00PM	11:30	3	DRILLING WITH DOWNHOLE MOTOR.
		1.5	SURVEYING AND ORIENTING WITH THE MWD SYSTEM.
11:30PM	12:00	.5	MOTOR STOPPED. TRYING TO RESTART MOTOR.
12:00AM	2:00	2	TRIP OUT OF HOLE.
2:00AM	7:00	5	BROKE DOWN THE MWD TOOLS AND INSTALLED THE BACKUP SENSOR PACKAGE BECAUSE THE FIRST PACKAGE FAILED. LAY DOWN MOTOR AND PICK UP NEW MOTOR.
7:00AM	8:00	1	TRIP IN HOLE.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-9-86 REPORT TIME: 8:00 A.M.
 DEPTH: 2277 FOOTAGE: 62 ACTIVITY: LAY DOWN MWD SYSTEM
 FORMATION: HLU: 70000 HLD: 64000 TORQUE:
 ROTATING WEIGHT: 65000

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN	DEPTH OUT	FEET-AGE	FT/HR	WT	RPM	CONDITION
RR9	10	5/8	HH44	HTC	2215	2277	62	24.80	5-7		2-4-I

AIR RATE: 2100 SCFM MIST RATE: 10 BBLs/HR PRESSURE: 200 PSI
 ADDITIVES: SAME

BHA: SAME

SURVEYS: 5.59°, 526.24°E, @ 2197' 6.5°, 541°E, @ 2229'
 °, °, @ ' °, °, @ '

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-9:00	1	TRIP IN HOLE.	
9:00AM-10:00	1	SURVEY AND ORIENT THE DOWNHOLE MOTOR.	
10:00AM-1:00	2	DRILLING WITH DOWNHOLE MOTOR.	
	1	SURVEYING AND ORIENTING DOWNHOLE MOTOR. MWD QUIT WORKING. TD IS 2267 FEET. GEOSCIENCE NEGLECTED TO ENTER THE PROBE TOOL FACE AND MOTOR TOOL FACE DIFFERENCE IN THE COMPUTER. DRILLED THE LAST 52 FEET WITH THE MOTOR AT 40 TO 60 DEGREES TO THE LEFT INSTEAD OF STRAIGHT UP. WILL BE TOO FAR TO THE LEFT.	
1:00PM-5:00	4	WAIT FOR GEOSCIENCE TECHNICIAN TO ARRIVE ON LOCATION.	
5:00PM-10:30	5.5	REPAIR MWD EQUIPMENT. ONE PROBE WAS RUINED BY PRESSURE AND THE OTHER HAD A LOOSE WIRE.	
10:30PM-11:30	1	INSTALL MWD PROBE IN THE BHA.	
11:30PM-1:30	2	TRIP IN HOLE.	
1:30AM-2:30	1	WASH 20 FEET TO BOTTOM AND SURVEY. ORIENT MOTOR.	
2:30AM-3:00	.5	DRILL TO 2277 FEET.	
3:00AM-4:00	1	TURN OFF AIR IN ORDER TO SURVEY. COULD NOT RESTART MOTOR.	
4:00AM-6:00	2	TRIP OUT OF HOLE.	
6:00AM-8:00	2	LAY DOWN MWD EQUIPMENT. THE MWD SYSTEM DOES NOT GIVE ENOUGH TOOL FACE DATA TO BE RELIABLE.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-10-86 REPORT TIME: 8:00 A.M.
DEPTH: 2304 FOOTAGE: 27 ACTIVITY: DRILLING
FORMATION: HLU: HLD: TORQUE:
ROTATING WEIGHT:

BIT RECORD:

BIT	SERIAL				DEPTH		FOOT--	FT/			
#	SIZE	TYPE	MANUF	#	IN	OUT	AGE	HR	WT	RPM	CONDITION
RR9	10	5/8	HH44	HTC	2277		27	18			

AIR RATE: 2100 SCFM MIST RATE: 10 BBLs/HR PRESSURE: 200 PSI
ADDITIVES:

BHA: BIT, MOTOR, FLOAT SUB, 2 1/2" BENT SUB, 2 8" MONELS, X-O, X-O, 2 6 1/4" DC'S

SURVEYS: ☐ 1 ☐ 2 ☐ 3 ☐ 4 ☐ 5 ☐ 6 ☐ 7 ☐ 8 ☐ 9 ☐ 10 ☐ 11 ☐ 12 ☐ 13 ☐ 14 ☐ 15 ☐ 16 ☐ 17 ☐ 18 ☐ 19 ☐ 20 ☐ 21 ☐ 22 ☐ 23 ☐ 24 ☐ 25 ☐ 26 ☐ 27 ☐ 28 ☐ 29 ☐ 30 ☐ 31 ☐ 32 ☐ 33 ☐ 34 ☐ 35 ☐ 36 ☐ 37 ☐ 38 ☐ 39 ☐ 40 ☐ 41 ☐ 42 ☐ 43 ☐ 44 ☐ 45 ☐ 46 ☐ 47 ☐ 48 ☐ 49 ☐ 50 ☐ 51 ☐ 52 ☐ 53 ☐ 54 ☐ 55 ☐ 56 ☐ 57 ☐ 58 ☐ 59 ☐ 60 ☐ 61 ☐ 62 ☐ 63 ☐ 64 ☐ 65 ☐ 66 ☐ 67 ☐ 68 ☐ 69 ☐ 70 ☐ 71 ☐ 72 ☐ 73 ☐ 74 ☐ 75 ☐ 76 ☐ 77 ☐ 78 ☐ 79 ☐ 80 ☐ 81 ☐ 82 ☐ 83 ☐ 84 ☐ 85 ☐ 86 ☐ 87 ☐ 88 ☐ 89 ☐ 90 ☐ 91 ☐ 92 ☐ 93 ☐ 94 ☐ 95 ☐ 96 ☐ 97 ☐ 98 ☐ 99 ☐ 100 ☐ 101 ☐ 102 ☐ 103 ☐ 104 ☐ 105 ☐ 106 ☐ 107 ☐ 108 ☐ 109 ☐ 110 ☐ 111 ☐ 112 ☐ 113 ☐ 114 ☐ 115 ☐ 116 ☐ 117 ☐ 118 ☐ 119 ☐ 120 ☐ 121 ☐ 122 ☐ 123 ☐ 124 ☐ 125 ☐ 126 ☐ 127 ☐ 128 ☐ 129 ☐ 130 ☐ 131 ☐ 132 ☐ 133 ☐ 134 ☐ 135 ☐ 136 ☐ 137 ☐ 138 ☐ 139 ☐ 140 ☐ 141 ☐ 142 ☐ 143 ☐ 144 ☐ 145 ☐ 146 ☐ 147 ☐ 148 ☐ 149 ☐ 150 ☐ 151 ☐ 152 ☐ 153 ☐ 154 ☐ 155 ☐ 156 ☐ 157 ☐ 158 ☐ 159 ☐ 160 ☐ 161 ☐ 162 ☐ 163 ☐ 164 ☐ 165 ☐ 166 ☐ 167 ☐ 168 ☐ 169 ☐ 170 ☐ 171 ☐ 172 ☐ 173 ☐ 174 ☐ 175 ☐ 176 ☐ 177 ☐ 178 ☐ 179 ☐ 180 ☐ 181 ☐ 182 ☐ 183 ☐ 184 ☐ 185 ☐ 186 ☐ 187 ☐ 188 ☐ 189 ☐ 190 ☐ 191 ☐ 192 ☐ 193 ☐ 194 ☐ 195 ☐ 196 ☐ 197 ☐ 198 ☐ 199 ☐ 200 ☐ 201 ☐ 202 ☐ 203 ☐ 204 ☐ 205 ☐ 206 ☐ 207 ☐ 208 ☐ 209 ☐ 210 ☐ 211 ☐ 212 ☐ 213 ☐ 214 ☐ 215 ☐ 216 ☐ 217 ☐ 218 ☐ 219 ☐ 220 ☐ 221 ☐ 222 ☐ 223 ☐ 224 ☐ 225 ☐ 226 ☐ 227 ☐ 228 ☐ 229 ☐ 230 ☐ 231 ☐ 232 ☐ 233 ☐ 234 ☐ 235 ☐ 236 ☐ 237 ☐ 238 ☐ 239 ☐ 240 ☐ 241 ☐ 242 ☐ 243 ☐ 244 ☐ 245 ☐ 246 ☐ 247 ☐ 248 ☐ 249 ☐ 250 ☐ 251 ☐ 252 ☐ 253 ☐ 254 ☐ 255 ☐ 256 ☐ 257 ☐ 258 ☐ 259 ☐ 260 ☐ 261 ☐ 262 ☐ 263 ☐ 264 ☐ 265 ☐ 266 ☐ 267 ☐ 268 ☐ 269 ☐ 270 ☐ 271 ☐ 272 ☐ 273 ☐ 274 ☐ 275 ☐ 276 ☐ 277 ☐ 278 ☐ 279 ☐ 280 ☐ 281 ☐ 282 ☐ 283 ☐ 284 ☐ 285 ☐ 286 ☐ 287 ☐ 288 ☐ 289 ☐ 290 ☐ 291 ☐ 292 ☐ 293 ☐ 294 ☐ 295 ☐ 296 ☐ 297 ☐ 298 ☐ 299 ☐ 300 ☐ 301 ☐ 302 ☐ 303 ☐ 304 ☐ 305 ☐ 306 ☐ 307 ☐ 308 ☐ 309 ☐ 310 ☐ 311 ☐ 312 ☐ 313 ☐ 314 ☐ 315 ☐ 316 ☐ 317 ☐ 318 ☐ 319 ☐ 320 ☐ 321 ☐ 322 ☐ 323 ☐ 324 ☐ 325 ☐ 326 ☐ 327 ☐ 328 ☐ 329 ☐ 330 ☐ 331 ☐ 332 ☐ 333 ☐ 334 ☐ 335 ☐ 336 ☐ 337 ☐ 338 ☐ 339 ☐ 340 ☐ 341 ☐ 342 ☐ 343 ☐ 344 ☐ 345 ☐ 346 ☐ 347 ☐ 348 ☐ 349 ☐ 350 ☐ 351 ☐ 352 ☐ 353 ☐ 354 ☐ 355 ☐ 356 ☐ 357 ☐ 358 ☐ 359 ☐ 360 ☐ 361 ☐ 362 ☐ 363 ☐ 364 ☐ 365 ☐ 366 ☐ 367 ☐ 368 ☐ 369 ☐ 370 ☐ 371 ☐ 372 ☐ 373 ☐ 374 ☐ 375 ☐ 376 ☐ 377 ☐ 378 ☐ 379 ☐ 380 ☐ 381 ☐ 382 ☐ 383 ☐ 384 ☐ 385 ☐ 386 ☐ 387 ☐ 388 ☐ 389 ☐ 390 ☐ 391 ☐ 392 ☐ 393 ☐ 394 ☐ 395 ☐ 396 ☐ 397 ☐ 398 ☐ 399 ☐ 400 ☐ 401 ☐ 402 ☐ 403 ☐ 404 ☐ 405 ☐ 406 ☐ 407 ☐ 408 ☐ 409 ☐ 410 ☐ 411 ☐ 412 ☐ 413 ☐ 414 ☐ 415 ☐ 416 ☐ 417 ☐ 418 ☐ 419 ☐ 4

```
GAS:  C1:      , C2:      , C3:      , C4:      , C5:      , C5+:      , TOT:
SHOWS:
```

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-9:00	1		BIT WAS PLUGGED WITH CUTTINGS. TEST MOTOR AT THE SURFACE. MOTOR RUN OK.
9:00AM-6:30	9.5		WAIT ON SCIENTIFIC DRILLING AND WIRELINE TRUCK.
6:30PM-9:30	3		UNLOAD SCIENTIFIC'S TOOLS AND MAKE UP BHA.
9:30PM-12:00	2.5		TRIP IN HOLE WITH MOTOR.
12:00AM-4:00	4		RIG UP WIRELINE SHEAVES, REHEAD STEERING TOOL ONTO WIRELINE TRUCK, INSTALL SPLIT ROTARY BUSHING, AND INSTALL WIRELINE IN THE SIDE ENTRY SUB. TRIP IN THE LAST 5 STANDS.
4:00AM-6:00	2		RUN STEERING TOOL IN THE HOLE. WOULD NOT GO THROUGH THE 6 1/4" DC'S. PULL WIRELINE AND GRIND DOWN THE STABILIZER FINS.
6:00AM-6:30	.5		START AIR PACKAGE AND ORIENT MOTOR.
6:30AM-8:00	1.5		DRILLING WITH MOTOR.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-11-86 REPORT TIME: 8:00 A.M.
 DEPTH: 2595 FOOTAGE: 291 ACTIVITY: DRILLING
 FORMATION: BEREA HLU: 78000 HLD: 66000 TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
RR9	10	5/8	HH44	HTC	2277	2559	282	25.64	5-10		5-6-I
10	10	5/8	HH44	HTC	2559		36	10.29	5-10		

AIR RATE: 2100SCFM MIST RATE: 10 BBL/S/HR PRESSURE: 250-300
 ADDITIVES: SAME

BHA: SAME

SURVEYS: 9.8°, S51.6°E, @ 2271' 12.5°, S49°E, @ 2340'
 15.5°, S47°E, @ 2403' 18°, S42°E, @ 2465' 20.8°, S40.4°E,
 @2528'

GAS: C1:1000, C2:200, C3: , C4: , C5: , C5+: , TOT: 2000 PPM
 SHOWS: GOOD OIL STAINING IN TOP OF BEREA AT 2520-2535, FAIR STAINING FROM
 2535-2600. NO GAS SHOW ASSOCIATED WITH IT. GAS SHOW AT 2585 WAS 10,000PPM

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-8:30	9.5	DRILLING WITH DOWNHOLE MOTOR.	
	3	CONNECTIONS AND STEERING TOOL.	
8:30PM-9:00	.5	TRYING TO MAKE MOTOR RUN.	
9:00PM-12:00	3	TRIP OUT OF HOLE. PULL STEERING TOOL.	
12:00AM-1:00	1	PICK UP FIRST MOTOR AND TEST IN THE ROTARY TABLE. RUNS OK.	
1:00AM-3:30	2.5	TRIP IN HOLE.	
3:30AM-4:00	.5	PICK UP KELLY AND WORK OUT TIGHT SPOT AT 2400 FEET.	
4:00AM-4:30	.5	RUN STEERING TOOL.	
4:30AM-8:00	3.5	DRILLING WITH DOWNHOLE MOTOR.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-12-86 REPORT TIME: 8:00 A.M.
 DEPTH: 2857 FOOTAGE: 262 ACTIVITY: DRILLING
 FORMATION: SHALE HLU: 80000 HLD: 70000 TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
10	10	5/8	HH44	HTC	2559	2604	45	12.86	5-10		2-2-1
RR10	10	5/8	HH44	HTC	2604		253	33.73	5-10		

7.5

AIR RATE: 2100SCFM MIST RATE: 20 BBLS/HR PRESSURE: 200-300
 ADDITIVES: SAME

BHA: SAME

SURVEYS: 24.5°, S40°E, @ 2591' 27.5°, S39°E, @ 2655'
 30°, S37°E, @ 2718' 32.75°, S38°E, @ 2781'

GAS: C1: 2000, C2: 200, C3: , C4: , C5: , C5+: , TOT: BGG 3000
 PPM
 SHOWS: NONE

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM	8:30	.5	TRYING TO START DOWNHOLE MOTOR.
8:30AM	11:00	2.5	PULL STEERING TOOL AND TRIP OUT OF THE HOLE FOR A DOWNHOLE MOTOR.
11:00AM	12:30	1.5	LAY DOWN DOWNHOLE MOTOR AND PICK UP NEW MOTOR. CHECK BY-PASS VALVE.
12:30PM	2:30	2	TRIP IN HOLE.
2:30PM	3:00	.5	SERVICE RIG.
3:00PM	3:30	.5	RUN STEERING TOOL.
3:30PM	10:00	5	DRILLING WITH DOWNHOLE MOTOR.
		1.5	CONNECTIONS AND ORIENT MOTOR.
10:00PM	3:00	5	TRYING TO RESTART MOTOR. PULLED OUT OF HOLE TO THE SIDE ENTRY SUB. SUB NOT LEAKING. DUMP 5 GALS SOAP IN PIPE. TRIP TO BOTTOM. MOTOR STARTED WORKING. RUN STEERING TOOL.
3:00AM	3:30	.5	DRILLING.
3:30AM	5:00	1.5	TRYING TO RESTART MOTOR AFTER CONNECTION. PUMPED WATER INTO THE DRILL PIPE AND IT STARTED. SOAP DID NOT START IT THIS TIME.
5:00AM	8:00	2	DRILLING.
		1	RESTARTING MOTOR AFTER CONNECTIONS.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-13-86 REPORT TIME: 8:00 A.M.
 DEPTH: 2985 FOOTAGE: 128 ACTIVITY: TRIP
 FORMATION: SHALE HLU: 80000 HLD: 70000 TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
RR10	10	5/8	HH44	HTC	2604	2985	381	31.75	5-10		2-3-1

AIR RATE: 2100 MIST RATE: 20 BBLs/HR PRESSURE: 250 PSI
 ADDITIVES: SAME

BHA: SAME

SURVEYS: 35.8°, S39°E, @ 2844' 39.2°, S40°E, @ 2931'
 °, °, @ °, °, @

GAS: C1: 2000, C2: 300, C3: 150, C4: , C5: , C5+: , TOT: 3000 PPM
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM	9:00	1	DRILLING WITH DOWNHOLE MOTOR.
9:00AM	10:30	1.5	CONNECTION AND RESTARTING MOTOR.
10:30AM	11:30	1	DRILLED TO 2920 WITH DOWNHOLE MOTOR.
11:30AM	2:30	3	RIG UP TO MAKE 60 FOOT CONNECTIONS. TRYING TO RESTART MOTOR.
2:30PM	3:15	.75	DRILLED 15 FEET. STEERING TOOL WENT OUT. THE WIRELINE HAD KINKED.
3:15PM	5:30	2.25	REPAIR WIRELINE AND REHEAD STEERING TOOL.
5:30PM	8:00	2.5	RESTARTING MOTOR.
8:00PM	9:30	1.5	DRILLED TO 2977 FEET.
9:30PM	11:30	2	TRYING TO RESTART THE MOTOR.
11:30PM	12:00	1	DRILLED TO 2985 FEET.
12:00PM	12:30	.5	MOTOR HAD STALLED. TRIED TO RESTART.
12:30AM	4:00	3.5	PULL STEERING TOOL AND TRIP OUT OF THE HOLE.
4:00AM	5:00	1	PULL BLANK OUT OF THE OLD MOTOR AND INSTALL IT IN THE NEW MOTOR.
5:00AM	8:00	3	TRIP IN HOLE WITH NEW MOTOR.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-14-86 REPORT TIME: 8:00 A.M.
 DEPTH: 3309 FOOTAGE: 324 ACTIVITY: TRIP
 FORMATION: HURON SHALE HLU: 80000 HLD: 68000 TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	SERIAL #	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
RR10	10	5/8	HH44	HTC	2604	3309	329	29.91	5-10		2-4-1/8

AIR RATE: 2100SCFM MIST RATE: 20 BBLS/HR PRESSURE: 200-300
 ADDITIVES: SAME

BHA: SAME

SURVEYS: 41.6°, S40°E, @ 2993' 44.0°, S39°E, @ 3057'
 46.2°, S37.8°E, @ 3120' 48.4°, S38°E, @ 3182' 51.6°, S37°E, @ 3246'

GAS: C1: 10000, C2: 4000, C3: 1200, C4: 200, C5: 0, C5+: 0, TOT: 24000 PPM
 SHOWS: 3094' 6500PPM, 3141' 5000PPM, 3224' 36,000PPM. AT 3224' THE
 BREAKDOWN IS AS FOLLOWS: C1: 11000, C2: 6000, C3: 2400, C4: 400, C5: 0.

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-9:00	1	START COMPRESSORS AND RUN STEERING TOOL.	
9:00AM-11:00	10.5	DRILLING WITH DOWNHOLE MOTOR.	
	3.5	CONNECTIONS.	
11:00PM-1:00	.5	DRILLING.	
	1.5	MOTOR STARTED STALLING ON BOTTOM. STALLED TWICE AND WOULD NOT RESTART THE SECOND TIME.	
1:00AM-2:00	1	STARTED OUT OF THE HOLE. HOLE TIGHT AFTER PULLING ONE STAND.	
2:00AM-3:30	1.5	CIRCULATE TO CLEAN HOLE. UNLOAD NEW BAKER MOTORS AND LOAD OLD BAKER MOTORS ON A HOTSHOT TRUCK.	
3:30AM-8:00	4.5	PULL OUT OF THE HOLE AND LAY DOWN THE MOTOR.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-15-86 REPORT TIME: 8:00 A.M.
 DEPTH: 3509 FOOTAGE: 200 ACTIVITY: TRIP
 FORMATION: _____ HLU: _____ HLD: _____ TORQUE: _____
 ROTATING WEIGHT: _____

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
RR10	10 5/8	HH44	HTC	3309	3509	200	28.57	5-10		3-5-1/8

AIR RATE: 2100 SCFM MIST RATE: 10 BBLs/HR PRESSURE: 250 PSI
 ADDITIVES: SAME

BHA: BIT, MOTOR, FS, 3° BENT SUB, 2-8" MONELS, X-O, X-O, 2-6 1/4" DC'S
 SURVEYS: 56.6°, S34°E, @ 3343' 60.8°, S33.5°E, @ 3405'
65.7°, S34°E, @ 3467' °, °, @

GAS: C1: 12000, C2: 2700, C3: 1300, C4: 260, C5: 0, C5+: 0, TOT: 20000 PPM
 SHOWS: NONE

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-8:30	.5	LAY DOWN MOTOR AND CHANGE BENT SUB.	
8:30AM-9:00	.5	SERVICE DRILLING RIG.	
9:00AM-12:00	3	TRIP IN HOLE WITH 3° BENT SUB. RUN STEERING TOOL.	
12:00PM-2:00	2	STEERING TOOL FAILED. PULL WIRELINE AND CHANGE OUT STEERING TOOL PROBE.	
2:00PM-3:00	1	RUN WIRELINE. TRIP TO BOTTOM AND ORIENT MOTOR.	
3:00PM-11:00	7	DRILLING WITH DOWNHOLE MOTOR.	
	1	CONNECTIONS.	
11:00PM-12:00	1	SURVEY AND CIRCULATE BEFORE TRIP. HOLE IS BUILDING ANGLE TOO FAST.	
12:00AM-12:30	.5	TRIED TO PULL PIPE BUT HOLE IS TIGHT. PULLING 60000 LBS OVER THE STRING WEIGHT.	
12:30AM-2:30	2	CIRCULATE TO CLEAN THE HOLE.	
2:30AM-5:00	2.5	PULL PIPE ONE JOINT AT TIME WHILE CIRCULATING. CANNOT PULL PIPE WITHOUT CIRCULATING.	
5:00AM-5:30	.5	PULL STEERING TOOL. WIRELINE HAD KINKED WHILE WORKING PIPE OUT OF THE HOLE.	
5:30AM-7:00	1.5	PULLING PIPE ONE JOINT AT A TIME WITH AIR ON THE HOLE.	
7:00AM-8:00	1	PIPE CAME FREE AFTER PULLING 300 FEET OUT OF THE HOLE. TRIP OUT OF HOLE.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGET RET#1 DATE: 11-16-86 REPORT TIME: 8:00 A.M.
DEPTH: 3509 FOOTAGE: 0 ACTIVITY: REAMING
FORMATION: HURON SHALE HLU: 95000 HLD: 70000 TORQUE: 1/2 RD
ROTATING WEIGHT: 80000

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT- AGE	FT/ HR	WT	RPM	CONDITION
RR10	10 5/8	HH44	HTC							REAMING

AIR RATE: 2100 SCFM MIST RATE: 0 BBLS/HR PRESSURE: 150 PSI
ADDITIVES:

BHA: BIT, 3 FT, 2-8" MONELS, 3 FT, X-O, X-O, 2-6 1/4" DC'S

[illegible]

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
SHOWS:

TIME BREAKDOWN AND COMMENTS:

<u>FROM</u>	<u>TO</u>	<u>HRS</u>	
<u>8:00AM-8:30</u>	<u>.5</u>		<u>TRIP OUT OF HOLE.</u>
<u>8:30AM-11:30</u>	<u>3</u>		<u>RIG UP AND LAY DOWN 80 JOINTS OF DRILL PIPE FOR</u> <u>REAMING.</u>
<u>11:30AM-1:00</u>	<u>1.5</u>		<u>FINISHED LAYING DOWN DRILL PIPE. TRIP OUT TO COLLARS.</u>
<u>1:00PM-2:00</u>	<u>1</u>		<u>CUT DRILLING LINE.</u>
<u>2:00PM-4:00</u>	<u>2</u>		<u>PULL COLLARS AND LAY DOWN MOTOR AND BENT SUB.</u>
<u>4:00PM-6:00</u>	<u>2</u>		<u>PICK UP REAMING ASSEMBLY.</u>
<u>6:00PM-9:00</u>	<u>3</u>		<u>STRAP IN THE HOLE. PICK UP SINGLES OUT OF THE PIPE</u> <u>TUBS.</u>
<u>9:00PM-9:30</u>	<u>.5</u>		<u>START AIR COMPRESSORS AND PICK UP KELLY.</u>
<u>9:30AM-8:00</u>	<u>10.5</u>		<u>REAMING THE HOLE ' FROM 2230 FEET TO 3176 FEET. DUSTING</u> <u>THE HOLE.</u>

DOWNTIME GAS IS AS FOLLOWS:

```
C1: 620000
C2: 133000
C3: 85280
C4: 18386
C5: 6000
C6: 2000
TOTAL 850000 PPM
```

BDM DAILY REPORT

WELL NAME: BDM/DOE ENAGER RET#1 DATE: 11-17-86 REPORT TIME: 8:00 A.M.
DEPTH: 3509 FOOTAGE: 0 ACTIVITY: FISHING
FORMATION: _____ HLU: _____ HLD: _____ TORQUE: _____
ROTATING WEIGHT: _____

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT- AGE	FT/ HR	WT	RPM	CONDITION
----------	------	------	-------	-------------	--------------	--------------	-----------	----	-----	-----------

AIR RATE: 3000 SCFM MIST RATE: 0 BBLS/HR PRESSURE: 150 PSI
ADDITIVES:

BHA: SCREW IN SUB, X-O, BUMPER SUB, JARS, X-O, 4 6 1/4" DC'S
SURVEYS: , , , ,
 , , , ,

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-3:30	7.5		REAM TO 3509 FEET. REAMED HARD FROM 3100 FEET TO BOTTOM. TRYING TO DRY UP HOLE. CIRCULATING 15 MINUTES AFTER EACH KELLY DOWN.
3:30PM-7:30	4		PIPE BECAME STUCK WHILE MAKING A CONNECTION. WORKED STUCK PIPE FOR 4 HOURS WITHOUT MAKING ANY PROGRESS.
7:30PM-11:30	4		WAIT ON FISHING TOOLS AND WORK STUCK PIPE.
11:30PM-2:30	3		RIG UP MCCULLOUGH AND RUN A FREEPOINT. PIPE IS FREE TO THE TOP REAMER. RUN BACKOFF SHOT AND BACKOFF AT THE TOP OF THE 6 1/4" DC'S. LEFT BIT, 3 FT, 2-8" MONELS, 3 FT, X-O, X-O, 2 6 1/4" DC'S IN THE HOLE.
2:30AM-5:00	2.5		RIG DOWN MCCULLOUGH AND TRIP OUT OF THE HOLE.
5:00AM-8:00	3		PICK UP FISHING TOOLS.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 11-18-86 REPORT TIME: 8:00 A.M.
 DEPTH: 3509 FOOTAGE: 0 ACTIVITY: TRIP
 FORMATION: _____ HLU: _____ HLD: _____ TORQUE: _____
 ROTATING WEIGHT: _____

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT- AGE	FT/ HR	WT	RPM	CONDITION

AIR RATE: _____ SCFM MIST RATE: _____ BBLs/HR PRESSURE: _____ PSI
 ADDITIVES: _____

BHA:

SURVEYS: _____

GAS: C1: _____, C2: _____, C3: _____, C4: _____, C5: _____, C5+: _____, TOT: _____
 SHOWS: _____

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-10:00	2	TRIP IN THE HOLE WITH FISHING TOOLS.	
10:00AM-11:00	1	START COMPRESSORS, CIRCULATE AND SCREW INTO THE FISH.	
11:00AM-11:30	.5	JAR ON FISH. THE JARS HIT TWICE AND FAILED. THE SCREW IN SUB PULLED OUT OF THE FISH.	
11:30AM-1:30	2	TRIP OUT OF THE HOLE.	
1:30PM-3:00	1.5	LAY DOWN JARS AND WAIT ON NEW JARS.	
3:00PM-3:30	.5	PICK UP NEW JARS.	
3:30PM-6:00	2.5	TRIP IN THE HOLE.	
6:00PM-6:30	.5	CIRCULATE AND SCREW INTO THE FISH.	
6:30PM-3:00	8.5	JARRING ON THE FISH WITH 120,000 LBS OVER THE STRING WEIGHT. JARS FAILED.	
3:00AM-4:00	1	WAIT ON BACKOFF TRUCK.	
4:00AM-7:00	3	MANUALLY BACK OFF THE PIPE AT THE SCREW IN SUB TO REMOVE THE KELLY. COULD NOT SCREW BACK INTO THE FISH.	
7:00AM-8:00	1	PULL OUT OF THE HOLE.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 11-19-86 REPORT TIME: 8:00 A.M.
DEPTH: 3509 FOOTAGE: 0 ACTIVITY: WAIT ON CEMENT
FORMATION: HLU: HLD: TORQUE:
ROTATING WEIGHT:

BIT RECORD:

BIT				DEPTH		FOOT-	FT/			
#	SIZE	TYPE	MANUF	IN	OUT	AGE	HR	WT	RPM	CONDITION

AIR RATE: SCFM MIST RATE: BBLS/HR PRESSURE: PSI
ADDITIVES:

EHA:

SURVEYS: 0, 0, @ - 0, 0, @ -
 0, 0, @ - 0, 0, @ -

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:

SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-9:00	1		PULL OUT OF THE HOLE.
9:00AM-10:00	1		LAY DOWN THE FISHING TOOLS.
10:00AM-12:00	2		TRIP IN THE HOLE WITH OPEN ENDED DRILL PIPE.
12:00PM-1:00	1		PLUG BACK 200 FEET WITH 125 SACKS OF CLASS "A" CEMENT CONTAINING 3% CALCIUM CHLORIDE. PLUG SET FROM 3385' TO 3185'.
1:00PM-1:30	.5		RIG DOWN HALLIBURTON.
1:30PM-3:30	2		TRIP OUT OF THE HOLE. LAY DOWN 5 STANDS OF DRILL PIPE.
3:30PM-8:00	17.5		WAIT ON CEMENT.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 11-20-86 REPORT TIME: 8:00 A.M.
DEPTH: 3259 FOOTAGE: 20 ACTIVITY: CHANGING STEERING TOOL
FORMATION: _____ HLU: _____ HLD: _____ TORQUE: _____
ROTATING WEIGHT: _____

RIT RECORD:

BIT		SIZE		TYPE	MANUF	DEPTH		FOOT- AGE	FT/ HR	WT	RPM	CONDITION
#						IN	OUT					
11	10	5/8	HH44	HTC	3239			20	4.0	1		

AIR RATE: 2100 SCFM MIST RATE: 20 BBLS/HR PRESSURE: 200 PSI
ADDITIVES:

BHA: BIT, MOTOR, FLOAT SUB, 2 1/2" BENT SUB, 2-8" MONELS, X-0

SURVEYS: 0, 0, @ 0, 0, @

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:

SHOWS:

TIME BREAKDOWN AND COMMENTS:

<u>FROM</u>	<u>TO</u>	<u>HRS</u>	
<u>8:00AM-11:00</u>	<u>3</u>		<u>WAITING ON CEMENT.</u>
<u>11:00AM-1:00</u>	<u>2</u>		<u>TRIP IN HOLE TO DRESS OFF THE CEMENT PLUG.</u>
<u>1:00PM-4:00</u>	<u>3</u>		<u>START COMPRESSORS. TAG CEMENT AT 3176 FEET. DRILL</u> <u>FROM 3176 FEET TO 3239 FEET. CEMENT DRILLED HARD AT</u> <u>ABOUT 2 MINUTES PER FOOT WITH 20000 LBS BIT WEIGHT.</u>
<u>4:00PM-5:30</u>	<u>1.5</u>		<u>CIRCULATE TO CLEAN HOLE AND UNLOAD MONEL DRILL COLLARS.</u>
<u>5:30PM-7:30</u>	<u>2</u>		<u>PULL OUT OF THE HOLE.</u>
<u>7:30PM-10:00</u>	<u>2.5</u>		<u>LAY DOWN THE 6 1/4" DRILL COLLARS. PICK UP MOTOR AND</u> <u>MONELS.</u>
<u>10:00PM-12:00</u>	<u>2</u>		<u>TRIP IN HOLE WITH MOTOR.</u>
<u>12:00AM-12:30</u>	<u>.5</u>		<u>RUN SHAREWELL STEERING TOOL.</u>
<u>12:30AM-2:30</u>	<u>2</u>		<u>TIME DRILLING AND ORIENTING THE DOWNHOLE MOTOR.</u> <u>SHAREWELL TOOL FAILED.</u>
<u>2:30AM-4:30</u>	<u>2</u>		<u>FULL SHAREWELL TOOL AND CHANGE PROBES. RUN TOOL.</u>
<u>4:30AM-7:30</u>	<u>3</u>		<u>ORIENT MOTOR AND TIME DRILL TO 3259 FEET. SAMPLES ARE</u> <u>MOSTLY SHALE. WELL APPEARS TO BE SIDETRACKED. THE</u> <u>SECOND SHAREWELL TOOL FAILED.</u>
<u>7:30AM-8:00</u>	<u>.5</u>		<u>PULL STEERING TOOL. WILL RUN SCIENTIFIC TOOL.</u>

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGETIC RET#1 DATE: 11-21-86 REPORT TIME: 8:00 A.M.
 DEPTH: 3382 FOOTAGE: 123 ACTIVITY: REPAIRING STEERING TOOL
 FORMATION: HURON SHALE HLU: 70000 HLD: 60000 TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
11	10 5/8	HH44	HTC	3239		143	11.44	5		

12.5

AIR RATE: 3150 SCFM MIST RATE: 20 BBL/S/HR PRESSURE: 240 PSI
 ADDITIVES:

BHA: SAME

SURVEYS: 48°, S35°E, @ 3240' 46°, S34°E, @ 3272'
°, °, @ °, °, @ °

GAS: C1: 5000, C2: 900, C3: 400, C4: 100, C5: 0, C5+: 0, TOT: 8500 PPM
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-12:30	4.5	TIME DRILLING TO SIDETRACK THE WELL. MOTOR STALLED.	
12:30PM-4:00	3.5	TRYING TO RESTART MOTOR. WOULD NOT RESTART.	
4:00PM-5:00	1	TRIP OUT OF HOLE.	
5:00PM-6:00	1	RIG REPAIR.	
6:00PM-7:00	1	TRIP OUT OF THE HOLE.	
7:00PM-9:00	2	CHANGE MOTORS.	
9:00PM-11:30	2.5	TRIP IN THE HOLE.	
11:30PM-12:30	1	RUN WIRELINE STEERING TOOL.	
12:30AM-3:30	3	DRILLING WITH DOWNHOLE MOTOR.	
3:30AM-8:00	4.5	PROBE FAILED ON THE STEERING TOOL. PULL WIRELINE. CHANGE PROBES. RUN WIRELINE. TOOL FAILED AGAIN. PULL WIRELINE. WIRELINE CONNECTION FAILED. REHEAD WIRELINE.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-22-86 REPORT TIME: 8:00 A.M.
 DEPTH: 3657 FOOTAGE: 275 ACTIVITY: DRILLING
 FORMATION: HURON SHALE HLU: HLD: TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
11	10 5/8	HH44	HTC	3239		418	17.79	5		

23.5

AIR RATE: 2100 SCFM MIST RATE: 20 BBLs/HR PRESSURE: 250 PSI
 ADDITIVES:

BHA: BIT, FLOAT SUB, MOTOR, 3° BENT SUB, 2-8" MONELS, X-0

SURVEYS: 47.5°, S34°E, @ 3397' 50.4°, S34°E, @ 3463'
54.2°, S35°E, @ 3526' 57°, S35°E, @ 3589'

GAS: C1: 15000, C2: 7000, C3: 1000, C4: 600, C5: 0, C5+: 0, TOT: 23000 PPM
 SHOWS: AT 3628 29500 PPM

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-11:00	3		STEERING TOOL FAILURE. REHEAD WIRELINE.
11:00AM-12:00	1		TRYING TO ORIENT MOTOR. CAN NOT GET IT SET FOR STRAIGHT BUILD.
12:00PM-1:30	1.5		DRILLING WITH MOTOR. WORKING THE ORIENTATION AROUND TO STRAIGHT BUILD. TOOK ABOUT 30 FEET OF HOLE.
1:30PM-2:30	1		STEERING TOOL FAILED. 3000 SCFM CAUSES TOO MUCH VIBRATION FOR THE STEERING TOOL.
2:30PM-4:30	2		TRIP OUT OF HOLE TO PICK UP 3° BENT SUB.
4:30PM-5:30	1		CHANGE BENT SUB.
5:30PM-7:30	2		TRIP IN HOLE.
7:30PM-9:00	1.5		REAM 40 FEET TO BOTTOM. RUN STEERING TOOL.
9:00PM-8:00	9.5		DRILLING WITH DOWNHOLE MOTOR.
	1.5		CONNECTIONS.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-23-86 REPORT TIME: 8:00 A.M.
 DEPTH: 3666 FOOTAGE: 9 ACTIVITY: REAMING
 FORMATION: _____ HLU: _____ HLD: _____ TORQUE: _____
 ROTATING WEIGHT: _____

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
11	10 5/8	HH44	HTC	3239	3666	427	17.79	5		2-7-1/8

24

AIR RATE: 2100 SCFM MIST RATE: 20 BBLs/HR PRESSURE: 250 PSI
 ADDITIVES: _____

BHA: BIT, FLOAT SUB, 3PT, 2-8" MONELS, 3PT, X-0

SURVEYS: 58.8°, S33°E, @ 3615' _____
 _____, _____, @ _____, _____, @ _____

GAS: C1: _____, C2: _____, C3: _____, C4: _____, C5: _____, C5+: _____, TOT: _____
 SHOWS: _____

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-8:30		.5	DRILLING TO 3666 FEET. NOT BUILDING ENOUGH INCLINATION.
8:30AM-12:30		4	FULL PIPE OUT OF THE HOLE. HOLE TIGHT. HAD TO PUMP OUT 12 JOINTS BEFORE PIPE CAME FREE.
12:30PM-2:00		1.5	RUN SINGLES BACK IN HOLE TO SURVEY. NO HOLE DRAG. HAD 40 FOOT OF FILL.
2:00PM-3:00		1	CIRCULATE TO CLEAN HOLE. FOAM IS NOT COMING OUT DIRTY.
3:00PM-4:00		1	RUN SURVEY.
4:00PM-7:00		3	TRIP OUT. HOLE IS STILL TIGHT. HAD TO PUMP OUT 10 JOINTS OF DRILL PIPE. FOAM IS CLEAN COMING OUT OF THE HOLE. MAY BE A FEW LARGE ROCKS CAUSING THE DRAG. THERE IS NO DRAG WITH THE AIR ON. WILL NOT COME OUT WITH THE AIR OFF.
7:00PM-9:00		2	TRIP OUT OF HOLE. LAY DOWN BHA.
9:00PM-10:00		1	RUN DRILL PIPE OPEN ENDED TO 2000 FEET.
10:00PM-11:00		1	WAIT ON HALLIBURTON.
11:00PM-1:30		2.5	HALLIBURTON ARRIVED. TRIPPED PIPE TO BOTTOM. RIG UP HALLIBURTON. PLUG BACK TO 3300 FEET WITH 210 SACKS OF CLASS "A" CEMENT CONTAINING 2% CALCIUM CHLORIDE.
1:30AM-4:00		2.5	TRIP OUT OF THE HOLE. LAY DOWN 12 JOINTS OF DRILL PIPE.
4:00AM-6:00		2	PICK UP REAMING BHA.
6:00AM-8:00		2	TRIP IN HOLE.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-24-86 REPORT TIME: 8:00 A.M.
 DEPTH: 3390 FOOTAGE: 28 ACTIVITY: DRILLING
 FORMATION: SHALE HLU: HLD: TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH		FOOT-AGE	FT/HR	WT	RPM	CONDITION
				IN	OUT					
12	10 5/8	HH44	HTC	3362		28	18.67	5		

1.5

AIR RATE: 2100 SCFM MIST RATE: 25 BBLs/HR PRESSURE: 250 PSI
 ADDITIVES:

BHA: BIT, FLOAT SUB, 2° BENT HOUSING MOTOR, 1.5° BENT SUB, X-0, 2-8"

MONELS, X-0

SURVEYS: 47°, S34°E, @ 3345' 0, 0, @ '
0, 0, @ ' 0, 0, @ '

GAS: C1: 7500, C2: 1500, C3: 800, C4: 85, C5: , C5+: , TOT: 10000 FPM
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-12:00	4		REAM A TIGHT SPOT AT 2500 FEET. RAN PIPE TO 3250 FEET. REAM 3250 TO 3330 FEET. DRILL CEMENT FROM 3330 FEET TO 3362 FEET.
12:00PM-1:00	1		CIRCULATE TO CLEAN HOLE WITH 3150 SCFM.
1:00PM-3:00	2		RUN SINGLE SHOT SURVEY AT 3345 FEET.
3:00PM-5:30	2.5		TRIP OUT OF HOLE. LAY DOWN THE BHA.
5:30PM-1:00	7.5		WAIT ON EASTMAN ALIGN-A-SUB. NEVER ARRIVED.
1:00AM-2:00	1		MAKE UP MOTOR WITH 1.5° BENT SUB. THE BENT SUB LINES UP WITH THE MOTOR WHEN MADE UP.
2:00AM-4:00	2		TRIP IN THE HOLE.
4:00AM-6:30	2.5		RUN WIRELINE AND ORIENT MOTOR.
6:30AM-8:00	1.5		DRILLING WITH DOWNHOLE MOTOR.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 11-25-86 REPORT TIME: 8:00 A.M.
 DEPTH: 3634 FOOTAGE: 244 ACTIVITY: TRIP
 FORMATION: HURON SHALE HLU: 75000 HLD: 65000 TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
<u>12</u>	<u>10 5/8</u>	<u>HH44</u>	<u>HTC</u>	<u>3362</u>	<u>3634</u>	<u>272</u>	<u>18.76</u>	<u>2-3</u>		

AIR RATE: 2100 SCFM MIST RATE: 25 BBLS/HR PRESSURE: 220 PSI
 ADDITIVES:

BHA: SAME

SURVEYS: 49.6°, S33.6°E, @ 3373' 53.5°, S30°E, @ 3437'
57.6°, S31°E, @ 3500' 62.2°, S32°E, @ 3563' 64.5°,
S34°E, @ 3594'

GAS: C1: 12000, C2: 2600, C3: 1200, C4: 500 , C5: 0 , C5+: 0 , TOT: 25000 PPM
 SHOWS: 3585' WENT FROM 10000 TO 34000 PPM, AT 3600' WENT FROM 30000 TO 74500 PPM.

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
<u>8:00AM-3:00</u>	<u>13</u>	<u>6</u>	<u>DRILLING WITH DOWNHOLE MOTOR.</u>
		<u>1</u>	<u>CONNECTIONS AND RESTARTING MOTOR.</u>
<u>3:00AM-4:00</u>	<u>1</u>		<u>TRYING TO RESTART MOTOR. WOULD NOT RESTART.</u>
<u>4:00AM-8:00</u>	<u>4</u>		<u>TRIP OUT OF THE HOLE. PULL WIRELINE STEERING TOOL.</u>

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 11-26-86 REPORT TIME: 8:00 A.M.
 DEPTH: 3827 FOOTAGE: 193 ACTIVITY: DRILLING
 FORMATION: HLU: 80000 HLD: 65000 TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
RR9	10 5/8	HH44	HTC	3634		193	21.44	2-5		

AIR RATE: 3150 SCFM MIST RATE: 25 BBLs/HR PRESSURE: 290 PSI
 ADDITIVES:

BHA: BIT, FLOAT SUB, 2° BENT MOTOR, ALIGN-A-SUB, 1.5° BENT SUB, X-O, 2-8" MONELS, X-O
 SURVEYS: 69°, S34°E, @ 3661' 72.2°, S35°E, @ 3725'
76.3°, S34°E, @ 3787' °, °, @

GAS: C1: 6500, C2: 2200, C3: 1000, C4: 250, C5: 0, C5+: 0, TOT: 10000 PPM
 SHOWS: NONE

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM	11:00	3	CHANGE BHA. REMOVE SHIMS FROM OLD MOTOR AND INSTALL IN NEW MOTOR. PLACE ALIGN-A-SUB BETWEEN THE BENT SUB AND MOTOR.
11:00AM	1:30	2.5	TRIP IN THE HOLE. HAVE 60 FEET OF FILL.
1:30PM	4:30	3	STEERING TOOL FAILED. HAD TO REHEAD. RUN WIRELINE.
4:30PM	5:00	.5	WASH 60 FEET TO BOTTOM.
5:00PM	10:00	2	TRYING TO DRILL WITH DOWNHOLE MOTOR. MOTOR KEEPS STALLING AND TORQUING WITH VERY LITTLE BIT WEIGHT. DRILLED 33 FEET TO 3667 FEET.
		3	RESTARTING MOTOR AND ORIENTING.
10:00PM	8:00	7	INCREASED THE AIR RATE FROM 2100 SCFM TO 3150 SCFM. MOTOR STARTED DRILLING.
		3	SURVEYS AND CONNECTIONS.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 11-27-86 REPORT TIME: 8:00 A.M.
 DEPTH: 3827 FOOTAGE: 0 ACTIVITY: TRIP
 FORMATION: HLU: HLD: TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
RR9	10 5/8	HH44	HTC	3634	3827	193	21.44	2-5		

AIR RATE: 3150 SCFM MIST RATE: 20 BBLS/HR PRESSURE: 280 PSI
 ADDITIVES:

BHA: BIT, FLOAT SUB, MONEL, 3 FT, MONEL, X-0
 SURVEYS: 74°, S36°E, @ 3807' SINGLE SHOT SURVEY
°, °, @ °, °, @ °

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SPOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-9:00	1	TRYING TO RESTART MOTOR.	
9:00AM-3:00	6	PULLED 100 FEET OUT OF THE HOLE AND THE HOLE BECAME TIGHT. HAD TO PUMP OUT 12 JOINTS OF PIPE BEFORE THE PIPE CAME FREE. WOULD NOT COME OUT OF THE HOLE WITHOUT THE AIR ON.	
3:00PM-4:30	1.5	LAY DOWN THE MOTOR AND PICK UP A REAMING ASSEMBLY.	
4:30PM-6:30	2	TRIP IN THE HOLE.	
6:30PM-12:00	5.5	REAMED FROM 3300 FEET TO THE BOTTOM OF THE HOLE. NO PROBLEM REAMING THE HOLE. THE HOLE WAS NOT TIGHT AT ALL.	
12:00AM-1:00	1	CIRCULATE TO CLEAN THE HOLE.	
1:00AM-2:30	1.5	SURVEY AT 3807 FEET. THE STEERING TOOL READ 77 DEGREES AND THE SINGLESOT WITH THE STEERING TOOL SAID 74 DEGREES. STEERING TOOL IS READING 3 DEGREES HIGH.	
2:30AM-4:00	1.5	CIRCULATE TO CLEAN HOLE BEFORE RUNNING THE TV CAMERA.	
4:00AM-8:00	4	START OUT OF THE HOLE. PULLED 100 FEET AND THE HOLE GOT TIGHT. HAD TO PUMP OUT AND PULL 8 STANDS BEFORE THE PIPE CAME FREE.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 11-28-86 REPORT TIME: 8:00 A.M.
DEPTH: 3827 FOOTAGE: 0 ACTIVITY: TRIP
FORMATION: HLU: HLD: TORQUE:
ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH		FOOT--	FT/ HR	WT	RPM	CONDITION
				IN	OUT	AGE				
1										
2										
3										
4										
5										
6										
7										
8										
9										
10										
11										
12										
13										
14										
15										
16										
17										
18										
19										
20										
21										
22										
23										
24										
25										
26										
27										
28										
29										
30										
31										
32										
33										
34										
35										
36										
37										
38										
39										
40										
41										
42										
43										
44										
45										
46										
47										
48										
49										
50										
51										
52										
53										
54										
55										
56										
57										
58										
59										
60										
61										

AIR RATE: 4200 SCFM MIST RATE: 30 BBLs/HR PRESSURE: 320 PSI
ADDITIVES:

BHA: BIT, X-0, FLOAT SUB

SURVEYS: 0, 0, @ - 0, 0, @ - 0, 0, @

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:

SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-10:00	2	TRIP OUT OF THE HOLE.	
10:00AM-3:00	5	RUN TV CAMERA. GOT TO 3142 FEET BEFORE THE CAMERA STOPPED. HAVE 2 TO 3" OF BALLED UP CUTTINGS ON THE LOW SIDE OF THE HOLE. SHOW OF GAS IN THE BEREA AT 2527 FEET. SMALL FRACTURE AND GAS BUBBLE AT 2967 FEET.	
3:00PM-5:00	2	UNLOAD REMAINING 8 5/8" CASING.	
5:00PM-6:00	1	RIG DOWN LOGGING TRUCK.	
6:00PM-7:00	1	LAY DOWN THE 8" MONELS.	
7:00PM-8:30	1.5	TRIP IN THE HOLE TO 3380 FEET WHEN THE PIPE STOPPED.	
8:30PM-1:00	4.5	REAM TO BOTTOM. HAD TO ROTATE TO GET THE PIPE TO BOTTOM EVEN WITH THE AIR ON. RUNNING 4200 SCFM.	
1:00AM-2:30	1.5	CIRCULATE TO CLEAN THE HOLE. WORKED PIPE WHILE CIRCULATING.	
2:30AM-3:30	1	SHORT TRIP 10 STANDS TO CHECK HOLE CLEANING. HAD NO TROUBLE PULLING THE 10 STANDS. TRIPPED IN TO 3600 FEET WHEN THE PIPE STOPPED. COULD NOT PUSH IT TO BOTTOM.	
3:30AM-5:00	1.5	REAM TO BOTTOM.	
5:00AM-7:00	2	CIRCULATE TO CLEAN THE HOLE. WORK THE PIPE WHILE CIRCULATING.	
7:00AM-8:00	1	PULL PIPE. PULLED TIGHT AFTER PULLING 150 FEET. COULD NOT GO UP OR DOWN. PUMP THE AIR ON THE HOLE AND CIRCULATE.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENGER RET#1 DATE: 11-29-86 REPORT TIME: 8:00 A.M.
DEPTH: 3827 FOOTAGE: 0 ACTIVITY: REAM AND CIRC TO CLEAN HOLE
FORMATION: HLU: 75000 HLD: 60000 TORQUE:
ROTATING WEIGHT: 62000

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH		FOOT- AGE	FT/ HR	WT	RPM	CONDITION
				IN	OUT					
1	1 1/2	1	1	1	1	1	1	1	1	1
2	1 1/2	1	1	1	1	1	1	1	1	1
3	1 1/2	1	1	1	1	1	1	1	1	1
4	1 1/2	1	1	1	1	1	1	1	1	1
5	1 1/2	1	1	1	1	1	1	1	1	1
6	1 1/2	1	1	1	1	1	1	1	1	1
7	1 1/2	1	1	1	1	1	1	1	1	1
8	1 1/2	1	1	1	1	1	1	1	1	1
9	1 1/2	1	1	1	1	1	1	1	1	1
10	1 1/2	1	1	1	1	1	1	1	1	1
11	1 1/2	1	1	1	1	1	1	1	1	1
12	1 1/2	1	1	1	1	1	1	1	1	1
13	1 1/2	1	1	1	1	1	1	1	1	1
14	1 1/2	1	1	1	1	1	1	1	1	1
15	1 1/2	1	1	1	1	1	1	1	1	1
16	1 1/2	1	1	1	1	1	1	1	1	1
17	1 1/2	1	1	1	1	1	1	1	1	1
18	1 1/2	1	1	1	1	1	1	1	1	1
19	1 1/2	1	1	1	1	1	1	1	1	1
20	1 1/2	1	1	1	1	1	1	1	1	1
21	1 1/2	1	1	1	1	1	1	1	1	1
22	1 1/2	1	1	1	1	1	1	1	1	1
23	1 1/2	1	1	1	1	1	1	1	1	1
24	1 1/2	1	1	1	1	1	1	1	1	1
25	1 1/2	1	1	1	1	1	1	1	1	1
26	1 1/2	1	1	1	1	1	1	1	1	1
27	1 1/2	1	1	1	1	1	1	1	1	1
28	1 1/2	1	1	1	1	1	1	1	1	1
29	1 1/2	1	1	1	1	1	1	1	1	1
30	1 1/2	1	1	1	1	1	1	1	1	1
31	1 1/2	1	1	1	1	1	1	1	1	1
32	1 1/2	1	1	1	1	1	1	1	1	1
33	1 1/2	1	1	1	1	1	1	1	1	1
34	1 1/2	1	1	1	1	1	1	1	1	1
35	1 1/2	1	1	1	1	1	1	1	1	1
36	1 1/2	1	1	1	1	1	1	1	1	1
37	1 1/2	1	1	1	1	1	1	1	1	1
38	1 1/2	1	1	1	1	1	1	1	1	1
39	1 1/2	1	1	1	1	1	1	1	1	1
40	1 1/2	1	1	1	1	1	1	1	1	1
41	1 1/2	1	1	1	1	1	1	1	1	1
42	1 1/2	1	1	1	1	1	1	1	1	1
43	1 1/2	1	1	1	1	1	1	1	1	1
44	1 1/2	1	1	1	1	1	1	1	1	1
45	1 1/2	1								

AIR RATE: 3150 SCFM MIST RATE: 0 BELS/HR PRESSURE: 130 PSI
ADDITIVES:

BHA: SAME

SURVEYS:

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
SHOWS:

TIME BREAKDOWN AND COMMENTS:

<u>FROM</u>	<u>TO</u>	<u>HRS</u>	
<u>8:00AM-10:00</u>	<u>2</u>		<u>TRIP OUT OF THE HOLE AFTER WORKING THROUGH A TIGHT SPOT AT 3650 FEET.</u>
<u>10:00AM-1:30</u>	<u>3.5</u>		<u>RIG UP DRESSER AND LOG THE HOLE. BOTTOM OF THE LOGGED INTERVAL WAS 3620 FEET. HOLE WAS MOSTLY 11.5 TO 12 INCHES IN DIAMETER. THE GREY SHALES WASHED OUT THE MOST TO ABOUT 14 INCHES IN A FEW SPOTS. CALIPER SHOWED TIGHT SPOTS AT 3280 AND 3380 FEET. CALIPER WAS LESS THAN 4 INCHES.</u>
<u>1:30PM-2:30</u>	<u>1</u>		<u>RIG DOWN DRESSER.</u>
<u>2:30PM-4:30</u>	<u>2</u>		<u>TRIP IN TO THE BOTTOM OF THE 11 3/4" CASING. BLOW AIR IN HOLE TO DRY IT UP.</u>
<u>4:30PM-7:30</u>	<u>3</u>		<u>STAGE INTO THE HOLE TO 3200 FEET.</u>
<u>7:30PM-4:30</u>	<u>9</u>		<u>REAM HOLE TO 3650 FEET. STARTED HITTING TIGHT SPOTS AT ABOUT 3600 FEET.</u>
<u>4:30AM-5:30</u>	<u>1</u>		<u>SHORT TRIP 6 STANDS. HOLE WAS TIGHT ON THE FIRST 2 STANDS. HAD TO PUT THE AIR ON THE HOLE TO WORK UP PAST 3550 FEET. TRIP IN AND REAM PAST THE TIGHT SPOT.</u>
<u>5:30AM-8:00</u>	<u>2.5</u>		<u>REAMING AND BLOWING THE HOLE TO 3760 FEET.</u>

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGET RET#1 DATE: 11-30-86 REPORT TIME: 8:00 A.M.
 DEPTH: 3827 FOOTAGE: 0 ACTIVITY: WAITING ON CEMENT
 FORMATION: _____ HLU: _____ HLD: _____ TORQUE: _____
 ROTATING WEIGHT: _____

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION

AIR RATE: _____ SCFM MIST RATE: _____ BBLs/HR PRESSURE: _____ PSI
 ADDITIVES: _____

BHA:

SURVEYS: _____

GAS: C1: _____, C2: _____, C3: _____, C4: _____, C5: _____, C5+: _____, TOT: _____
 SHOWS: _____

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-9:00	1	REAM TO BOTTOM.	
9:00AM-11:00	2	CIRCULATE TO CLEAN THE HOLE.	
11:00AM-1:00	2	TRIP OUT OF THE HOLE. HAD TWO TIGHT SPOTS AT 3550 FEET. HAD TO PULL 120,000 LBS TO GET PAST IT BUT DID NOT HAVE TO PICK UP THE KELLY.	
1:00PM-3:30	2.5	NIPPLE DOWN.	
3:30PM-4:00	.5	RIG UP POWER TONGS AND EQUIPMENT TO RUN THE CASING.	
4:00PM-5:30	1.5	PICK UP ONE JOINT OF CASING AND TRY TO RUN 2 ND BENT HOUSING MOTOR IN THE CASING. WOULD NOT GO UNDER ITS OWN WEIGHT. MAY BE ABLE TO PUSH IT IN WITH COLLARS.	
5:30PM-10:00	4.5	RUN 8 5/8" 24# AND 32# CASING TO 3543' AND HIT A BRIDGE.	
10:00PM-4:00	6	HAD TO WASH THE LAST 6 JOINTS TO BOTTOM. LANDED THE CASING AT 3803 FEET.	
4:00AM-5:30	1.5	RIG UP HALLIBURTON.	
5:30AM-7:00	1.5	CEMENT WITH 120 SACKS OF CLASS "A" CEMENT AND DISPLACED WITH 227 BARRELS OF WATER. DISPLACEMENT SHOULD HAVE BEEN 234 BARRELS. MAY HAVE LEFT SOME CEMENT IN THE CASING.	
7:00AM-8:00	1	WAITING ON CEMENT.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 12-1-86 REPORT TIME: 8:00 A.M.
DEPTH: 3827 FOOTAGE: 0 ACTIVITY: TRIP
FORMATION: LOWER HURON HLU: HLD: TORQUE:
ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH		FOOT- AGE	FT/ HR	WT	RPM	CONDITION
				IN	OUT					
13	7.875	HH-44	HTC	3827		0				DRL CMT.

AIR RATE: SCFM MIST RATE: BBLS/HR PRESSURE: PSI
ADDITIVES:

BHA:BIT,FLOAT SUB, MONEL, X-O, MONEL

SURVEYS: , , @ ' , , @ '
 , , @ , , @

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
SHOWS:

TIME BREAKDOWN AND COMMENTS:

<u>FROM</u>	<u>TO</u>	<u>HRS</u>	
<u>8:00AM-1:00PM</u>	<u>5</u>	<u>WAITING ON CEMENT</u>	
<u>1:00PM-4:00PM</u>	<u>3</u>	<u>CUT OFF CASING , WELDED 8 5/8 CASING TO 11 3/4 CASING</u>	
<u>4:00PM-6:00PM</u>	<u>2</u>	<u>UNLOADING BAKER MOTORS, SEND OLD MOTORS BACK</u>	
<u>6:00PM-12:00</u>	<u>6</u>	<u>NIPPLE UP</u>	
<u>12:00-2:00AM</u>	<u>2</u>	<u>PICK UP BHA</u>	
<u>2:00AM-7:00AM</u>	<u>5</u>	<u>GO IN HOLE, BLOW WATER OUT EVERY 500 FT.</u>	
<u>7:00AM-8:00AM</u>	<u>1</u>	<u>WELD BROKE, WILL HAVE TO NIPPLE DOWN AND REWELD</u>	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 12-2-86 REPORT TIME: 8:00 A.M.
DEPTH: 3827 FOOTAGE: 0 ACTIVITY: CIRCULATE
FORMATION: _____ HLU: _____ HLD: _____ TORQUE: _____
ROTATING WEIGHT: _____

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH		FOOT- AGE	FT/ HR	WT	RPM	CONDITION
				IN	OUT					DRL CMT
13	7 7/8	HH44	HTC	3827						

AIR RATE: 2100 SCFM MIST RATE: 10 BBLs/HR PRESSURE: 200 PSI
ADDITIVES:

BHA: SAME

SURVEYS: , , @ ' , , @ ' ,
 , , @ ' , , @ ' ,

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
SHOWS:

TIME BREAKDOWN AND COMMENTS:

<u>FROM</u>	<u>TO</u>	<u>HRS</u>	
<u>8:00AM-10:00</u>	<u>2</u>	<u>TRIP OUT OF THE HOLE.</u>	
<u>10:00AM-1:00</u>	<u>3</u>	<u>NIPPLE DOWN.</u>	
<u>1:00PM-6:00</u>	<u>5</u>	<u>WAIT ON WELDER.</u>	
<u>6:00PM-10:00</u>	<u>4</u>	<u>CUT OFF CASING AND WELD ON A COLLAR.</u>	
<u>10:00PM-1:00</u>	<u>3</u>	<u>NIPPLE UP.</u>	
<u>1:00AM-2:30</u>	<u>1.5</u>	<u>RIG REPAIR.</u>	
<u>2:30AM-4:30</u>	<u>2</u>	<u>TRIP IN HOLE.</u>	
<u>4:30AM-8:00</u>	<u>3.5</u>	<u>DRILL OUT CEMENT TO TD.</u>	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 12-3-86 REPORT TIME: 8:00 A.M.
 DEPTH: 3914 FOOTAGE: 87 ACTIVITY: RUN STEERING TOOL
 FORMATION: LOWER HURON HLU: HLD: TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
13	7 7/8	HH44	HTC	3827		87	19.3	2-5		

4.5

AIR RATE: 3150 SCFM MIST RATE: 25 BBLs/HR PRESSURE: 200-300 PSI
 ADDITIVES:

BHA: BIT, 1 7/8" BENT MOTOR, FLOAT SUB, MSS, 6 1/4" MONEL, X-O, 6 1/4" MONEL

SURVEYS: 74.5°, S37°E, @ 3869' °, @ °, @ °, @ °, @

GAS: C1: 1000, C2: 500, C3: 100, C4: , C5: , C5+: , TOT: 2500 PPM
 SHOWS: AT 3895 FEET TOTAL WAS 65000 PPM AND DIED QUICKLY

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-11:00	3	TRIP OUT OF THE HOLE. PULLED TIGHT 4 TIMES AND HAD TO PICK UP THE KELLY. TOTAL 9 STANDS OUT.	
11:00AM-1:00	2	TRIP OUT OF THE HOLE. STRAP SHOWS TOTAL DEPTH IS 3860 FEET. DRILLED 33 FEET OF FORMATION BECAUSE OF ERROR IN THE TALLY.	
1:00PM-3:00	2	PICK UP MOTOR AND SET BENT HOUSING TO 1 7/8". MAKE UP BHA.	
3:00PM-5:30	2.5	TRIP IN THE HOLE.	
5:30PM-6:30	1	STOPPED AT THE FLOAT COLLAR. PICKED UP THE KELLY AND REAMED THROUGH THE FLOAT COLLAR.	
6:30PM-8:00	1.5	RUN WIRELINE STEERING TOOL. WOULD NOT FALL TO BOTTOM. TRIED PUMPING IT TO BOTTOM WITH NO LUCK.	
8:00PM-10:30	2.5	PULLED THREE STANDS AND RUN STEERING TOOL. TRIP IN THREE STANDS WITH STEERING TOOL AND MAKE UP 60 FOOT KELLY.	
10:30PM-2:00	3.5	DRILLING WITH DOWNHOLE MOTOR.	
2:00AM-3:30	1.5	MOTOR STALLED. COULD NOT RESTART.	
3:30AM-7:00	3.5	PULL 3 STANDS AND WIRELINE TO TAKE A SURVEY. FIRST SURVEY FAILED. SECOND SURVEY WAS GOOD.	
7:00AM-8:00	1	MOTOR STARTED RUNNING. RUN STEERING TOOL.	

EDM DAILY REPORT

WELL NAME: BDM/DOE ENERGETIC RET#1 DATE: 12-4-86 REPORT TIME: 8:00 A.M.
 DEPTH: 3997 FOOTAGE: 83 ACTIVITY: TRIP
 FORMATION: LOWER HURON HLU: 65000 HLD: 58000 TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
13	7 7/8	HH44	HTC	3827	3997	170	17.0	2-5		2-5-I

AIR RATE: 3150 SCFM MIST RATE: 25 BBLS/HR PRESSURE: 300 PSI
 ADDITIVES:

BHA: SAME

SURVEYS: 81°, S37°E, @ 3935' 0°, 0°, @ '
0°, 0°, @ ' 0°, 0°, @ '

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-9:00		1	RUN WIRELINE AND TRIP TO BOTTOM.
9:00AM-1:30		4.5	DRILLING WITH DOWNHOLE MOTOR TO 3980 FEET.
1:30PM-4:00		2.5	SURVEY.
4:00PM-5:30		1.5	RESTARTING MOTOR.
5:30PM-6:30		1	DRILLING WITH DOWNHOLE MOTOR TO 3997 FEET. MOTOR STALLED. STEERING TOOL FAILED WHILE TRYING TO RESTART THE MOTOR.
6:30PM-8:00		1.5	PULL WIRELINE AND TRY TO RESTART MOTOR. MOTOR WOULD NOT RESTART.
8:00PM-11:30		4.5	TRIP OUT OF THE HOLE. HAD TO PUT AIR ON THE HOLE ON THE 7TH STAND OUT (3600').
11:30PM-4:00		4.5	CHANGE DOWNHOLE MOTORS. CHANGE BY-PASS VALVE.
4:00AM-6:30		2.5	TRIP IN THE HOLE.
6:30AM-7:30		1	RUN STEERING TOOL 3 STANDS OFF BOTTOM.
7:30AM-8:00		.5	START AIR COMPRESSORS. ONE COMPRESSOR WILL NOT START.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 12-5-86 REPORT TIME: 8:00 A.M.
 DEPTH: 4043 FOOTAGE: 46 ACTIVITY: TRIP IN HOLE
 FORMATION: LOWER HURON HLU: 65000 HLD: 58000 TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
RR13	7 7/8	HH44	HTC	3997	4043	46	23	2-5		

AIR RATE: 3150 SCFM MIST RATE: 25 BBLs/HR PRESSURE: 250 PSI
 ADDITIVES:

BHA:

SURVEYS: 88°, S39°E, @ 3998' °, °, @ '
°, °, @ ' °, °, @ '

GAS: C1: 7000 , C2: 400, C3: 100, C4: 0 , C5: 0 , C5+: 0 , TOT: 13000 PPM
 SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-9:30	1.5	WASH TO BOTTOM.	
9:30AM-11:30	2	DRILL WITH DOWNHOLE MOTOR TO 4043 FEET.	
11:30AM-3:30	4	SURVEY.	
3:30PM-4:30	1	RIG DOWN WIRELINE.	
4:30PM-6:30	1	TRIP OUT OF THE HOLE.	
6:30PM-7:30	1	LAY DOWN BHA.	
7:30PM-8:00	.5	PICK UP CORE BARREL. EASTMAN DID NOT SEND OUT ALL THE EQUIPMENT.	
8:00PM-3:00	7	WAITING ON CORING EQUIPMENT FROM EASTMAN.	
3:00AM-5:00	2	MAKE UP CORE BARREL.	
5:00AM-8:00	3	TRIP IN THE HOLE. HAD TO PICK UP KELLY 200 FEET OFF BOTTOM TO WASH THROUGH A BRIDGE.	

EDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 12-6-86 REPORT TIME: 8:00 A.M.
DEPTH: 4086 FOOTAGE: 43 ACTIVITY: TRIP
FORMATION: LOWER HURON HLU: HLD: TORQUE:
ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT- AGE	FT/ HR	WT	RPM	CONDITION
CORE	7 7/8			4043	4086	43	14.3			
14	7 7/8	HH44	HTC	4086						

AIR RATE: 2100 SCFM MIST RATE: 25 BBLS/HR PRESSURE: 320 PSI
ADDITIVES:

BHA:BIT. FLOAT SUB. 3 PT. MONEL. X-O. MONEL

SURVEYS: 0, 0, @ — 0, 0, @

 0, 0, @ — 0, 0, @

GAS: C1: 1100 , C2: 600, C3: 100, C4: 0 , C5: 0 , C5+: 0, TOT: 2600 PPM
SHOWS: 4054 FEET, 6000 PPM

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-9:30	1.5	WASH TO BOTTOM.	
9:30AM-11:00	1.5	CORE 14 FEET. CORE JAMMED. DEPTH 4057 FEET.	
11:00AM-1:30	2.5	TRIP OUT OF THE HOLE.	
1:30PM-4:30	3	LAY DOWN CORE. RECOVERED 13 FEET. CUTTINGS HAD FILLED THE TOP HALF OF THE BARREL AND PREVENTED FURTHER CORING. REMOVED CIRCULATING BALL FROM BARREL.	
4:30PM-7:00	2.5	TRIP IN THE HOLE WITH CORE BARREL.	
7:00PM-8:00	1	CIRCULATE BEFORE CORING.	
8:00PM-9:30	1.5	CORE FROM 4057' TO 4086'.	
9:30PM-2:00	4.5	TRIP OUT OF THE HOLE. HOLE TIGHT AT 3600 FEET. HAD TO PICK UP THE KELLY.	
2:00AM-5:00	3	LAY DOWN CORE AND CORE BBL. HAD 100% RECOVERY.	
5:00AM-6:00	1	MAKE UP THE BHA.	
6:00AM-8:00	2	TRIP IN THE HOLE.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGETIC RET#1 DATE: 12-7-86 REPORT TIME: 8:00 A.M.
 DEPTH: 4156 FOOTAGE: 70 ACTIVITY: LAY DOWN CORE.
 FORMATION: LOWER HURON HLU: HLD: TORQUE:
 ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
14	7 7/8	HH44	HTC	4086	4126	40	26.7	25	60	1-1-I
CORE	7 7/8			4126	4156	30	30.0			

AIR RATE: 2100 SCFM MIST RATE: 25 BBLs/HR PRESSURE: 320 PSI
 ADDITIVES:

BHA: COR BIT, 30' CORE BBL, X-0, X-0

SURVEYS: 92°, S39°E, @ 4043'
0, 0, @ 0, 0, @ 0, 0, @ 0

GAS: C1: 5000, C2: 1100, C3: 500, C4: 0, C5: 0, C5+: 0, TOT: 17,000
 SHOWS: 4140 FEET, 77,000 PPM

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM	8:30	.5	TRIP IN THE HOLE.
8:30AM	11:00	2.5	WASH AND REAM 200 FEET TO BOTTOM.
11:00AM	12:30	1.5	DRILLING TO 4126 FEET.
12:30PM	1:30	1	CIRCULATE BEFORE SURVEYING.
1:30PM	4:00	2.5	TRYING TO RUN SURVEY. COULD NOT PUMP TOOL INTO THE MONELS. LOST SURVEY TOOL IN THE PIPE.
4:00PM	5:00	1	CIRCULATE TO CLEAN THE HOLE.
5:00PM	8:00	3	TRIP OUT OF THE HOLE. TIGHT AT 3600 FEET BUT DID NOT HAVE TO PICK UP THE KELLY.
8:00PM	10:00	2	LAY DOWN BHA. PICK UP CORE BARREL.
10:00PM	12:30	2.5	TRIP IN THE HOLE.
12:30AM	1:30	1	CIRCULATE BEFORE CORING.
1:30AM	2:30	1	CORE 4126' TO 4156'.
2:30AM	5:30	3	TRIP OUT OF THE HOLE.
5:30AM	8:00	2.5	LAY DOWN CORE AND CORE BARREL. HAD 100% RECOVERY.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGET RET#1 DATE: 12-8-86 REPORT TIME: 8:00 A.M.
 DEPTH: 4412 FOOTAGE: 256 ACTIVITY: SURVEY
 FORMATION: LOWER HURON HLU: 72,000 HLD: 54,000 TORQUE: 1 RD
 ROTATING WEIGHT: 57,000

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
RR14	7 7/8	HH44	HTC	4156		256	28.4	20-25	60	

AIR RATE: 3150 SCFM MIST RATE: 0 BBLs/HR PRESSURE: 190 PSI
 ADDITIVES:

BHA: BIT, FLOAT SUB, 3 FT, MONEL, X-O, MONEL
 SURVEYS: 92°, S39°E, @ 4191' 91°, S38°E, @ 4382'
0°, 0°, @ 0' 0°, 0°, @ 0'
 COORDINATES @ 4382' TVD: 3392.3 DEP: 1553.2
 GAS: C1: 600, C2: 200, C3: 0, C4: 0, C5: 0, C5+: 0, TOT: 900 PPM
 SHOWS: 4216' 1300 PPM

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
<u>8:00AM-11:00</u>	<u>3</u>		<u>TRIP IN THE HOLE WITH BHA.</u>
<u>11:00AM-12:00</u>	<u>1</u>		<u>REAM CORE HOLE.</u>
<u>12:00PM-2:00</u>	<u>2</u>		<u>DRILLING TO 4221'.</u>
<u>2:00PM-2:30</u>	<u>.5</u>		<u>CIRCULATE BEFORE SURVEYING.</u>
<u>2:30PM-5:30</u>	<u>3</u>		<u>TRY TO SURVEY BY PUMPING SINGLES HOT DOWN DRILL PIPE USING 5/16" WIRELINE. COULD NOT GET SURVEY TOOL INTO THE MONELS.</u>
<u>5:30PM-9:30</u>	<u>4</u>		<u>PULL 10STDs. RUN SURVEY TOOL THROUGH SIDE ENTRY SUB. TRIP TO BOTTOM AND TAKE SURVEY. PULL 10STDs TO REMOVE SURVEY TOOL. TRIP BACK TO BOTTOM.</u>
<u>9:30PM-4:30</u>	<u>7</u>		<u>DRILLING TO 4412'. CIRCULATING 10 MINUTES BETWEEN CONNECTIONS.</u>
<u>4:30AM-8:00</u>	<u>3.5</u>		<u>SURVEY THROUGH SIDE ENTRY SUB.</u>

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 12-9-86 REPORT TIME: 8:00 A.M.
 DEPTH: 4696 FOOTAGE: 284 ACTIVITY: TRIP
 FORMATION: LOWER HURON HLU: 78000 HLD: 46000 TORQUE: 1.5 RD
 ROTATING WEIGHT: 56000

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH		FOOT-AGE	FT/HR	WT	RPM	CONDITION
				IN	OUT					
RR14	7 7/8	HH44	HTC	4156	4696	540	26.3	15-25	60	1-4-I

AIR RATE: 3150 SCFM MIST RATE: 0 BBLS/HR PRESSURE: 190 PSI
 ADDITIVES:

BHA: SAME

SURVEYS: 90°, S38°E, @ 4666' 0, 0, @ '
0, 0, @ ' 0, 0, @ '

COORDINATES AT 4666' TVD 3389.8' DEP 1837.2'

GAS: C1: ', C2: ', C3: ', C4: ', C5: ', C5+: ', TOT: 5200 PPM
 SHOWS: AT 4480' 8500 PPM, AT 4502' 3200 PPM, AT 4566' 4500 PPM, AT 4667
3500 PPM, AT 4690' 5100 PPM

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-9:00		1	SURVEY.
9:00AM-6:00		9	DRILLING TO 4635'.
6:00PM-8:00		2	CIRCULATE TO CLEAN THE HOLE AND LOAD EASTMAN TRUCK.
8:00PM-9:00		1	DRILLING.
9:00PM-9:30		.5	RIG REPAIR.
9:30PM-11:00		1.5	DRILLING TO 4696'.
11:00PM-4:00		5	SURVEY.
4:00AM-8:00		4	TRIP OUT OF THE HOLE TO CHANGE BIT. CHANGE AIR HEAD RUBBER.

EDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 12-10-86 REPORT TIME: 8:00 A.M.
DEPTH: 5013 FOOTAGE: 317 ACTIVITY: SURVEY
FORMATION: LOWER HURON HLU: HLD: TORQUE:
ROTATING WEIGHT:

HIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
15	7 7/8	HH44	HTC	4696		317	18.65	15	60	

17

AIR RATE: 3150 SCFM MIST RATE: 0 BBLS/HR PRESSURE: 160 PSI
ADDITIVES:

BHA: SAME

SURVEYS:

GAS: C1:2000, C2:900, C3:550, C4:150, C5: 0 , C5+: 0 , TOT: 4500 PPM
SHOWS: AT 4882 7500, AT 4924 6200, AT 4933 8600, AT 4960 8400, AT 4970
9700, AT 4975 15000, AT 4680 6000, AT 4728 9000, AT 4740 9000.

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM	10:00	2	TRIP IN THE HOLE.
10:00AM	3:00	17	DRILLING TO 5013.
3:00AM	8:00	5	SURVEY. DID NOT GET A PICTURE. HAD TO RERUN THE SURVEY.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 12-11-86 REPORT TIME: 8:00 A.M.
DEPTH: 5328 FOOTAGE: 315 ACTIVITY: SURVEY
FORMATION: LOWER HURON HLU: 79000 HLD: 46000 TORQUE: 2 RD
ROTATING WEIGHT: 56000

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH		FOOT- AGE	FT/ HR	WT	RPM	CONDITION
15	7 7/8	HH44	HTC	4696		632	22.6	15-20	60	

AIR RATE: 3150 SCFM MIST RATE: 0 BBLS/HR PRESSURE: 160 PSI
ADDITIVES:

BHA: SAME

SURVEYS: 0, 0, @ 0, 0, @ 0, 0, @

GAS: C1:24000, C2:4800, C3:1800, C4: 600, C5: 0 , C5+: 0 , TOT:48000 PPM
SHOWS: AT 5047' FROM 7000 TO 478000, AT 5068' FROM 65000 TO 142000, AT
5096' FROM 70000 TO 139000, AT 5118' FROM 80000 TO 131000, AT 5220' FROM
18000 TO 48000

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM	11:00	3	SURVEY AT 5013 FEET.
11:00AM	4:00	17	DRILLING TO 5328'.
4:00AM	4:30	.5	CIRCULATE BEFORE SURVEYING.
4:30AM	8:00	3.5	SURVEY. TRIPPING 28 STANDS TO SIDE ENTRY SUB.

NO DRILLING BREAK ASSOCIATED WITH GAS SHOWS

BDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 12-12-86 REPORT TIME: 8:00 A.M.
 DEPTH: 5546 FOOTAGE: 218 ACTIVITY: TRIP
 FORMATION: LOWER HURON HLU: 100000 HLD: 20000 TORQUE: 2 RD
 ROTATING WEIGHT: 54000

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
15	7 7/8	HH44	HTC	4696	5546	850	23.2	15-20	60	2-5-I

AIR RATE: 3150 SCFM MIST RATE: 0 BBLS/HR PRESSURE: 180 PSI
 ADDITIVES:

BHA: SAME

SURVEYS: 88.5°, S34°E, @ 5298' 0, 0, 0, @ 0
0, 0, @ 0, 0, @ 0

GAS: C1: 6000 , C2: 2500, C3: 800 , C4: 200 , C5: 0 , C5+: 0 , TOT: 11000 PPM
 SHOWS: NONE

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM	9:00	1	SURVEY.
9:00AM	9:30	.5	SERVICE RIG.
9:30AM	11:30	2	TRIP IN THE HOLE.
11:30AM	4:00	4.5	DRILLING TO 5452'.
4:00PM	6:30	2.5	PIPE WOULD NOT GO IN THE HOLE AFTER MAKING A CONNECTION. PULLED 3 JTS BEFOR PIPE WOULD FALL. REAMED 3 JOINTS BACK TO BOTTOM.
6:30PM	7:30	1	DRILLED 30 FEET.
7:30PM	10:00	2.5	PIPE WILL NOT FALL BACK IN THE HOLE. REAMED LAST 30 FEET DRILLED. TAKES MORE WEIGHT TO REAM THAN IT DID TO DRILL. FOUND OUT LATER THAT THE KELLY WAS HANGING UP IN THE BUSHINGS AND TAKING THE WEIGHT.
10:00PM	12:00	2	DRILLED 30 FEET.
12:00AM	5:00	5	PIPE WOULD NOT FALL BACK IN THE HOLE. PULLED 5 JOINTS BEFORE IT WOULD. REAMED 5 JOINTS TO BOTTOM.
5:00AM	6:00	1	DRILLED 30 FEET.
6:00AM	6:30	.5	TRIED TO MAKE A CONNECTION. WOULD NOT GO DOWN.
6:30AM	8:00	1.5	TRIP OUT OF THE HOLE TO CHANGE BIT AND INSTALL COLLARS IN THE VERTICAL PORTION OF THE HOLE.

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGER RET#1 DATE: 12-13-86 REPORT TIME: 8:00 A.M.
DEPTH: 5630 FOOTAGE: 84 ACTIVITY: SERVICE RIG
FORMATION: LOWER HURON HLU: 98000 HLD: 40000 TORQUE:
ROTATING WEIGHT:

BIT RECORD:

BIT				DEPTH		FOOT-	FT/			
#	SIZE	TYPE	MANUF	IN	OUT	AGE	HR	WT	RPM	CONDITION
13	7 7/8	HH44	HTC	5546		84	24.0	20	60	

3.5

AIR RATE: 3150 SCFM MIST RATE: 0 BBLS/HR PRESSURE: 180 PSI
ADDITIVES:

RHA: SAME

SURVEYS: 880, S310E, @ 5598' 0, 0, @

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-9:30	1.5	TRIP OUT OF THE HOLE.	
9:30AM-11:30	2	REPAIR THE KELLY BUSHINGS. THE KELLY HAD BEEN HANGING UP IN THE BUSHINGS AND THE WEIGHT WAS NOT BEING TRANSMITTED TO THE BIT.	
11:30AM-12:30	1	PULLED BHA AND CHANGED THE BIT.	
12:30PM-3:00	2.5	TRIP IN THE HOLE.	
3:00PM-4:00	1	PICK UP SIX 6 1/4" DRILL COLLARS. WILL BE AT 1500 FEET WHEN THE PIPE IS ON BOTTOM.	
4:00PM-5:30	1.5	FINISH TRIP IN HOLE.	
5:30PM-7:30	2	REPAIR AIR LINES TO ROTARY TABLE.	
7:30PM-11:00	3.5	DRILLING TO 5628 FEET.	
11:00PM-11:30	.5	CIRCULATE BEFORE SURVEY.	
11:30PM-1:00	1.5	PULL 32 STANDS TO INSTALL SIDE ENTRY SUB.	
1:00AM-2:00	1	RIG UP FLOW LINE TO TEST WELL. WELL IS MAKING 119 MCFPD.	
2:00AM-5:00	3	SURVEY.	
5:00AM-6:00	1	RIG DOWN WIRELINE TRUCK AND FLOWLINE TESTING EQUIPMENT.	
6:00AM-7:30	1.5	TRIP IN HOLE.	
7:30AM-8:00	.5	SERVICE RIG.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGET RET#1 DATE: 12-14-86 REPORT TIME: 8:00 A.M.
 DEPTH: 6020 FOOTAGE: 392 ACTIVITY: TRIP OUT OF THE HOLE
 FORMATION: LOWER HURON HLU: 110000 HLD: 10000 TORQUE: 2.5 RDS
 ROTATING WEIGHT: 64000 WEIGHT OF BLOCKS AND KELLY: 10000

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT-AGE	FT/HR	WT	RPM	CONDITION
16	7 7/8	HH44	HTC	5546	6020	474	24.9	20	60	1-3-I

AIR RATE: 3150 SCFM MIST RATE: 0 BBL/HR PRESSURE: 220 PSI
 ADDITIVES:

BHA: SAME

SURVEYS: 87°, S29°E, @ 6020' EXTRAPOLATED SURVEY

0, 0, @ 0, 0, @ 0

COORDINATES: 3427' TVD, 3187.3' DEPARTURE

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:

SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	COMMENTS
8:00AM-10:30	2.5	DRILLING TO 5693 FEET.	
10:30AM-12:00	1.5	COULD NOT GO DOWN ON THE CONNECTION. CIRCULATE AND WORK THE PIPE.	
12:00PM-2:00	2	DRILLING TO 5756 FEET.	
2:00PM-3:00	1	PIPE HAVING TROUBLE GOING DOWN. CIRCULATE HOLE AND WORK PIPE.	
3:00PM-4:00	1	DRILLING TO 5787 FEET.	
4:00PM-5:00	1	WORK PIPE AND CIRCULATE. SEEMS TO MAKE LITTLE DIFFERENCE.	
5:00PM-11:00	6	DRILLING TO 5911 FEET.	
11:00PM-12:00	1	CIRCULATE TO MAKE SURE HOLE IS CLEAN. SERVICE RIG.	
12:00AM-4:00	4	DRILLING TO 6020 FEET WHICH IS TD. STILL HAVING TROUBLE GETTING PIPE TO GO DOWN.	
4:00AM-5:00	1	CIRCULATE TO CLEAN HOLE.	
5:00AM-8:00	3	TRIP OUT OF THE HOLE.	

EDM DAILY REPORT

WELL NAME: BDM/DOE ENAGER RET#1 DATE: 12-15-86 REPORT TIME: 8:00 A.M.
DEPTH: 6020 FOOTAGE: 0 ACTIVITY: LOGGING
FORMATION: LOWER HURON HLU: HLD: TORQUE:
ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN OUT		FOOT- AGE	FT/ HR	WT	RPM	CONDITION
----------	------	------	-------	-----------------	--	--------------	-----------	----	-----	-----------

AIR RATE: SCFM MIST RATE: BBLS/HR PRESSURE: PSI
ADDITIVES:

BHA:

[illegible]

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-9:30	1.5	TRIP OUT OF THE HOLE.	
9:30AM-3:00	5.5	WAIT FOR DRESSER TO ARRIVE ON LOCATION.	
3:00PM-7:00	5	RIG UP TOOLS IN ROTARY TABLE.	
7:00PM-11:00	4	TRIP IN 3200 FEET OF PIPE. RIG UP SIDE ENTRY SUB.	
		THE WIRELINE HEAD WOULD NOT GO THROUGH THE DRILL PIPE.	
11:00PM-6:00	7	REMOVE JOINTS OF DRILL PIPE THAT WOULD NOT ALLOW THE	
		WIRELINE HEAD TO PASS THE TOOL JOINT. RIG UP AND	
		CONNECT INTO THE LOGGING TOOLS.	
6:00AM-8:00	2	RUN PIPE WITH LOGGING TOOLS AND SIDE ENTRY SUB.	

EDM DAILY REPORT

WELL NAME: BDM/DOE ENEGER RET#1 DATE: 12-16-86 REPORT TIME: 8:00 A.M.
DEPTH: 6020 FOOTAGE: 0 ACTIVITY: LOGGING
FORMATION: LOWER HURON HLU: HLD: TORQUE:
ROTATING WEIGHT:

BIT RECORD:

BIT #	SIZE	TYPE	MANUF	DEPTH IN	DEPTH OUT	FOOT- AGE	FT/ HR	WT	RPM	CONDITION
----------	------	------	-------	-------------	--------------	--------------	-----------	----	-----	-----------

AIR RATE: SCFM MIST RATE: BBLs/HR PRESSURE: PSI
ADDITIVES:

BHA:

SURVEYS: 0, 0, 0 1, 0, 0, 0 0, 0

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-12:00	4		RUNNING DENSITY, GAMMA RAY, DUAL INDUCTION LOG. CALIPER AND DENSITY LOG DID NOT WORK BECAUSE THE PAD WAS ON THE LOW SIDE OF THE HOLE AND DID NOT CONTACT THE HOLE PROPERLY.
12:00PM-3:30	3.5		THE WET CONNECT PULLED OUT OF THE LOGGING TOOLS AT 4137 FEET. PULLED PIPE TO THE SIDE ENTRY SUB AND PULLED THE WIRELINE. SERVICE WET CONNECT AND RUN BACK IN THE HOLE. TRIP TO 4137 FEET.
3:30PM-4:30	1		FINISHED RUNNING THE DENSITY LOGS TO THE 8 5/8" CASING POINT.
4:30PM-7:00	2.5		PULL WIRELINE AND TRIP LOGGING TOOLS OUT OF THE HOLE.
7:00PM-11:00	5		LAID DOWN THE DENSITY LOGGING SUITE AND PICK UP THE TEMPERATURE LOGGING TOOL.
11:00PM-1:00	2		TRIP IN THE HOLE TO 3200 FEET.
1:00AM-3:00	2		INSTALL SIDE ENTRY SUB AND MAKE WET CONNECT.
3:00AM-6:00	3		RUN TEMPERATURE LOG TO TD. GAMMA RAY DID NOT WORK. CORRELATED WITH THE BOTTOM OF THE 8 5/8" CASING.
6:00AM-8:00	2		PULL WIRELINE AND TRIP OUT OF THE HOLE WITH THE LOGGING TOOLS.

RDM DAILY REPORT

WELL NAME: BDM/DOE ENERGET RET#1 DATE: 12-17-86 REPORT TIME: 8:00 A.M.
DEPTH: 6020 FOOTAGE: 0 ACTIVITY: LAY DOWN DRILL PIPE
FORMATION: LOWER HURON HLU: HLD: TORQUE:
ROTATING WEIGHT:

BIT RECORD:

[illegible]

AIR RATE: SCFM MIST RATE: BBLS/HR PRESSURE: PSI
ADDITIVES:

BHA:

SURVEYS: 0, 0, @ ' 0, 0, @ '
 0, 0, @ ' 0, 0, @ '

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-11:30	3.5	PULL DRILL PIPE WITH TEMPERATURE TOOL.	
11:30AM-2:00	2.5	RIG DOWN DRESSER LOGS AND RIG UP TO RUN STRATAVISION.	
2:00PM-5:00	3	TRIP IN TO 3200 FEET WITH THE CAMERA.	
5:00PM-6:00	1	MAKE WET CONNECT AND TRIP TO THE BOTTOM OF THE 8 5/8" CASING.	
6:00PM-1:00	7	LOG TO TD WITH THE TV CAMERA.	
1:00AM-4:00	3	RUN THE TV CAMERA OUT OF THE HOLE. DISCONNECT FROM THE WET CONNECT.	
4:00AM-6:00	2	PULL WIRELINE AND WIRE BACAME STUCK. TRIP OUT TO SIDE ENTRY SUB.	
6:00AM-7:00	1	THE WET CONNECT HAD NOT PULLED OUT. PULL OUT OF THE WET CONNECT.	
7:00AM-8:00	1	RIG UP AND LAY DOWN DRILL PIPE WHILE PULLING OUT OF THE HOLE WITH THE TV CAMERA.	

BDM DAILY REPORT

WELL NAME: BDM/DOE ENERGET RET#1 DATE: 12-18-86 REPORT TIME: 8:00 A.M.
DEPTH: 6020 FOOTAGE: 0 ACTIVITY: RIG RELEASED
FORMATION: LOWER HURON HLU: 42000 HLD: 31000 TORQUE:
WHILE RUNNING CASING. WEIGHT OF THE BLOCK IS 5000 LBS.

BIT RECORD:

[illegible]

AIR RATE: SCFM MIST RATE: BBLS/HR PRESSURE: PSI
ADDITIVES:

BHA:

SURVEYS: , , @ , , @ , @
 , , @ , , @ , @

GAS: C1: , C2: , C3: , C4: , C5: , C5+: , TOT:
SHOWS:

TIME BREAKDOWN AND COMMENTS:

FROM	TO	HRS	
8:00AM-10:30	2.5	LAY DOWN DRILL PIPE.	
10:30AM-11:30	1	LAY DOWN THE TV CAMERA AND RIG DOWN STRATAVISION.	
11:30AM-4:30	5	RUN REMAINING DRILL PIPE AND COLLARS OUT OF THE DERRICK. LAY DOWN DRILL PIPE.	
4:30PM-7:00	2.5	NIPPLE DOWN WELLHEAD AND RIG UP TO RUN 4 1/2" CASING.	
7:00PM-2:00	7	RUN 4 1/2", 10.5#/FT, J-55, ST&C CASING AND SET AT 6013.92 FEET. RAN 8 ECP'S, ONE CTC PACKER, AND 14 PORT COLLARS. PLACED THEM ACROSS VARIOUS INTERVALS IN THE OPEN HOLE. HAD NOT PROBLEM RUNNING THE CASING.	
2:00AM-3:00	1	RIG DOWN POWER TONGS AND SET WELLHEAD.	
3:00AM-6:00	3	RIGGING DOWN. RIG RELEASED AT 6:00 AM ON 12-18-86.	

Recovery Efficiency Test Project, Phase I - Activity Report
Volume I: Site Selection, Drill Plan Preparation,
Drilling, Logging, and Coring Operations

END

**DATE
FILMED**

3 / 25 / 92