PNL--8458

DE93 006606

INSPECTION AND ASSESSMENT OF ENERGY
CONSERVATION OPPORTUNITIES AT
ELLIS ISLAND NATIONAL PARK
ELLIS ISLAND, NEW YORK

P. R. Armstrong
G. B. Parker
E. E. Richman

December 1992

Prepared for
the U.S. Department of Energy
Federal Energy Management Program
under Contract DE-AC06-76RLO 1830

Pacific Northwest Laboratory
Richland, Washington 99352

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

JP

Preface

The goal of the U.S. Department of Energy (DOE) Federal Energy Management Program (FEMP) is to facilitate energy-efficiency improvements at federal facilities. This is accomplished by a balanced program of technology development, facility assessment, and use of cost-sharing procurement mechanisms. Technology development focuses upon the tools and procedures used to identify and evaluate energy-efficiency improvements, such as the ASEAM simulation model and the Federal Life Cycle Costing procedures. For facility assessment, FEMP provides metering equipment and trained analysts to federal agencies exhibiting a commitment to improve energy use efficiency. To assist in procurement of energy-efficiency measures, FEMP helps federal agencies devise and implement shared energy savings and utility demand-side management projects.

Pacific Northwest Laboratory (PNL)^(a) supports the FEMP mission as the lead laboratory for energy systems modernization. Under this charter, the Laboratory and its contractors work with federal facility energy managers to assess and implement energy-efficiency improvements at federal facilities nationwide.

(a) Pacific Northwest Laboratory is operated by Battelle Memorial Institute for the U.S. Department of Energy under Contract DE-AC06-76RLO 1830.

Executive Summary

Ellis Island is a National Park Service (NPS) facility located in New York Harbor that hosts nearly two million visitors per year. The main building houses exhibits and artifacts, food and gift concessions, and staff work and office spaces in a 200,000-square-foot floor area. Heating and cooling of the main building are provided by a central heating and cooling plant, housed in an adjacent 20,000-square-foot building, with distribution by nine main fan systems and perimeter radiators.

Energy end-use estimates were obtained by reconciling connected load characteristics (including operating hours) with billing data. The energy-use intensities (EUIs) are about 40 kWh/ft²-yr for electricity and 170,000 Btu/ft²-yr for natural gas. Energy use is higher than expected for facilities of this type in this region--even with the lighting, envelope characteristics, and heating, ventilating and air conditioning (HVAC) reheat and re-humidify configuration taken into account.

This high energy use is likely due to a number of factors. A large fraction of the lighting is provided by incandescent lamps. Constant-volume air-handlers and reheat coils are used in most of the exhibit spaces. Tight temperature and humidity control is achieved in these spaces at the expense of substantial energy use for simultaneous heating and cooling. The large window area of the main hall is made up entirely of single-glazed units. Ventilation is controlled by time schedules, not occupant load. Most motors and pumps are single-speed rather than the more efficient variable speed drive (VSD) type.

A preliminary assessment of the potential for energy conservation has been made after a site inspection and analysis of utility bills, building plans, and other information. The electric savings potential at the site is over 30% using available, generally cost-effective technologies. The fossil fuel savings potential is over 1,500 million British thermal units (MBtu) per year and could be much higher because 10,000 MBtu/yr of natural gas consumption could not be accounted for in our analyses. An effort should be made to check for and correct operational deficiencies, such as excess outside air, excessive reheat and re-humidification, and unnecessary operation of lights and other loads, before pursuing more elaborate energy conservation opportunities (ECOs).

Cost-effective ECOs were identified in the areas of lighting, HVAC, central plant, envelope, motors, and other equipment and loads. These are summarized in the following table showing the estimated annual energy (electrical or fossil fuel) and cost savings.

Measure	Estimated Savings		
	kWh/year	MBtu/year	\$K/year
Chilled Water System VSD Pumps/Fans	562,000	40	40.5
HVAC VSD Fans/Efficient Motors	621,000	--	44.7
Efficient Fluorescent Fixtures	819,000	--	55.6
Efficient Incandescent/Metal Halide	221,000	--	14.7
Light-Emitting Diode Exit Signs	10,800	--	0.7
Occupancy Sensors	200,000	--	14.4
Glazing Upgrade/Ventilation Control		1,600	8.3
High-Efficiency Transformers	200,000	--	14.4
Total	2,633,800	1,340	193.3

Specific ECOs that are the most promising to improve energy efficiency at Ellis Island include the following:

- **Central Plant and Thermal Distribution Systems** - The central plant and distribution opportunities identified in the preliminary assessment include two-speed or variable-speed pumps for chilled and condenser water, reducing steam pressure to 15 psi, replacing lead condensate return pumps with downsized, efficient pumps, providing a small local boiler for summer constant volume (CV) system loads, and providing thermostatic control of (or removing) the heat tape system associated with distribution of domestic hot water (DHW). Electrical energy savings can also be obtained by replacing single-speed feedwater and combustion air motors with two-speed motors or installing VSD.
- **Lighting** - The lighting retrofit measures identified in the preliminary assessment include replacing incandescents with compact fluorescents, replacing incandescents with dimmable fluorescents, replacing mercury vapor with high-pressure sodium lamps, replacing existing fluorescents with high-efficiency units and replacing fluorescent exit signs with light-emitting diode (LED) exit signs. Occupancy sensors are also recommended for rooms where fixture retrofit is not feasible.
- **HVAC Systems** - The ECOs identified for heating, ventilating and air conditioning (HVAC) equipment include converting the four CV systems to two-speed fan operation, replacing inlet-vane with VSD control of variable air volume (VAV) flow rate, replacing pump and fan motors with properly sized, efficient motors, modifying outside air control and installing low-leak dampers in the CV systems to provide zero outside air in

unoccupied periods, providing CO₂ control of outside air in all zones, improving control and balance to minimize H/C coil loads, and implementing (or fine-tuning) optimal start/stop control. Replacement of the existing cooling/dehumidification coil configuration in the four CV units with a face-and-bypass configuration should also be explored.

- **Envelope and Ventilation** - It is estimated that control of ventilation air by CO₂ sensors would save at least 1000 MBtu/yr in natural gas and 30,000 MBtu/yr in electricity. Kitchen and other special ventilation loads have not been considered in this assessment but may represent further energy savings potential. In addition, the central portion (main hall) of the building still retains single-pane windows. These could be retrofitted with double glazing to reduce heat loss.
- **Electrical Distribution and Generation Systems** - Electrical distribution opportunities include examining the use of existing 750-kVA diesel generator for peak shaving (not quantified) and replacing transformers (on failure) with high-efficiency models.
- **Other Systems** - Though not quantified in this assessment, other energy conservation opportunities include providing two-speed, variable-speed, or downsized-efficient ejector pumps, incinerator heat recovery, an efficient motor retrofit for the trash holding room refrigeration compressor, and reducing heat tape temperature.

The servicing utility, New Jersey Public Service Electric and Gas (PSE&G), may be able to provide support and incentives for electric energy efficiency projects at the site. The utility is about to launch a multi-year conservation acquisition program that covers a greater variety of conservation measures than the PSE&G standard rebate program. The current incentive caps (e.g., \$5,000 for fluorescent tubes and \$5,000 for all other measures) of the standard rebate program are also being eliminated. The initial two-year (1992-93) acquisition is limited to 150,000 kW in 400 kW (average summer on-peak) minimum blocks. PSE&G's acquisition differs from many other utilities' demand-side management programs in making the customer responsible for 1) verifying the energy savings over the life of the project and 2) determining the cost effectiveness of measures. The willingness of PSE&G to up-front finance the initial capital cost of the retrofits for federal customers and go considerably beyond their standard incentive program is a significant unknown that should be explored.

FEMP can make PNL available on a cost-recovery basis to assist the Ellis Island NPS in short-term testing and monitoring to measure energy end-use and to assist in procuring energy-efficiency improvements through internal, utility, or shared energy savings projects.

Lighting retrofit, HVAC load-reducing measures, pump and fan downsizing and motor retrofits, and peak-shaving implementation are projects that can benefit from a better

Contents

Preface	iii
Executive Summary	v
1.0 Introduction	1.1
2.0 Facility Description	2.1
2.1 Energy Sources	2.1
2.2 Other Utilities	2.2
2.3 Central Plant	2.2
2.4 HVAC Equipment	2.3
2.5 Lighting	2.4
2.6 Other Equipment and Loads	2.5
2.7 Envelope	2.5
2.8 Operation	2.6
3.0 Energy Usage and Rates	3.1
3.1 Electrical Energy	3.1
3.1.1 Utility Demand-Side Management Program Offerings	3.1
3.2 Natural Gas	3.3
3.3 Fuel Oil	3.5
3.4 Weather and Population Effects	3.5
3.5 Energy-Use Intensities by Electrical End-Use	3.7
3.6 Energy-Use Intensities by Fossil Fuel End-Use	3.8
4.0 Energy Conservation Opportunities	4.1
4.1 Central Plant	4.1

4.2 HVAC Equipment	4.2
4.3 Lighting	4.3
4.4 Other Equipment and Loads	4.5
4.5 Envelope and HVAC Distribution	4.5
5.0 Findings and Recommendations	5.1
5.1 Findings	5.1
5.2 Recommendations	5.1
5.2.1 Lighting	5.1
5.2.2 HVAC Systems and Envelope	5.1
5.2.3 Central Plant and Thermal Distribution Systems	5.2
5.2.4 Electrical Distribution and Generation Systems	5.2
5.2.5 Other Systems	5.2
5.3 Savings Potential	5.2
5.4 Utility Incentives	5.4
5.5 Technical Assistance	5.4
Appendix A - Documentation	A.1
Appendix B - Preliminary Measurement Plan	B.1

Figures

3.1	Monthly Electrical Demand and Consumption by Time of Use	3.2
3.2	Monthly Electrical Consumption and Cost Expressed in \$/kWh	3.2
3.3	Monthly Natural Gas Consumption and Cost in \$/MBtu	3.4
3.4	Average Monthly Concession Electrical Consumption vs. Visitor Count . . .	3.6

Tables

3.1	Gas And Electricity Billing History	3.4
3.2	Monthly Visitor Counts	3.5

1.0 Introduction

A request was made by Department of Interior and the DOE Field Office in Manhattan to DOE-FEMP for a preliminary energy assessment at Ellis Island National Park. FEMP tasked the Energy Systems Modernization Office (ESMO) at PNL to undertake this assessment.

A one-day site inspection was conducted on October 22, 1991. Energy bills, building drawings, relamping schedules and similar material were subsequently provided by the site. These are documented in Appendix A.

A preliminary assessment was made based on the site visit and supplementary documentation. This report describes energy saving projects and opportunities for heating, ventilating and air conditioning (HVAC) equipment, lighting, and other major energy-using equipment at Ellis Island. A project to modify the emergency generator power interface and controls to enable peak shaving is also discussed.

Following this introduction, the facility description is presented in Section 2.0. Energy usage and rates at Ellis Island are provided in Section 3.0. Section 4.0 contains a discussion on energy conservation opportunities at Ellis Island, and Section 5.0 presents the study findings and recommendations. Appendix A contains the study documentation as listed above, and Appendix B provides the Preliminary Measurement Plan that was used in the assessment.

2.0 Facility Description

Ellis Island comprises 22 acres and many, mostly uninhabitable, buildings. The site was abandoned by its most recent past tenant, the U.S. Coast Guard, in the early 1950s, and restoration of the main building and powerhouse was begun by NPS around 1985. Renovation of some basement (non-public) areas and service tunnels was also undertaken at this time.

The existing restored and renovated spaces consist of the entry hall, the railroad ticket office, the main hall, exhibit spaces, a 125-seat theater, administrative offices, exhibit and facilities shops and offices, and concessions. The main building, including sub-basement utility areas, has a floor area of about 200,000 square feet, and the powerhouse and facilities shops and offices comprise almost 20,000 square feet of floor area. The restoration was executed on a relatively short schedule with an evident concern for quality but no special consideration for energy efficiency and conservation.

The exhibit spaces present a challenging energy-efficiency problem because they must be maintained at 70 to 72°F and 50% relative humidity.

Plans for future development include a convention center and hotel. The development would involve both new buildings and restoration of existing buildings. There is excess capacity in the existing central plant plus room for one additional 17-MBtu/h boiler and one additional 500-ton chiller.

2.1 Energy Sources

Gas and electricity are supplied to Ellis Island by New Jersey Public Service Electric and Gas (PSE&G) through submarine lines. (Water and sewer also connect to the New Jersey side, service being provided by the Jersey City utility department.) The annual electrical consumption is about 8,000 MWh/yr, or 40 kWh/ft²-yr. Gas consumption is about 34,000 MBtu (higher heating value) per year, which corresponds to 170,000 Btu/ft²-yr. There are two new 20,000-gallon #2 fuel oil tanks for operating three diesel launches, one 750-kVA standby (emergency) generator, and three dual-fuel boilers. An 80,000-gallon tank predating the preservation project operates in parallel with the new tanks. Fuel oil is delivered by tanker about three times per year. There are no meters for monitoring day-to-day fuel oil consumption.

An electrical substation is situated at basement level between the powerhouse and the east end of the main building. Three-phase power enters at 13.2 kV. There are four

750-kVA, 480-V, 3-phase oil-filled transformers serving the east and west electric load centers and two 750-kVA, 3-phase, 480-V dry transformers serving the powerhouse. A 750-kVA Cummins diesel generator is located in a room in the northeast corner of the sub-station. Fuel is pumped from the main storage tanks into a day tank. The generator serves five emergency load centers.

2.2 Other Utilities

Water is delivered at night and flows, under delivery pressure, into a replica of the original 120-foot-high 250,000-gallon water tower. Booster pumps are in place to pump water up the tower when delivery pressure is inadequate (< 50 psig at grade) but it has not been necessary to use them. The servicing utility (Jersey City) has not taken meter readings since early 1991 due to a previous overpayment from which a net credit for the site still exists. Historical water flows are therefore unknown. The site is considering installation of a water meter on the island so that leaks can be detected by comparison with meter readings from the New Jersey side.

Sewage is pumped to the New Jersey side by one of two 15-hp pumps operated in a lead-lag configuration. These pumps do not have cumulative operating-hour meters.

2.3 Central Plant

There are two 500-ton (480-V, 3-phase) Trane 3-stage centrifugal chillers feeding a common chilled water loop. A two-cell cooling tower, each cell of which contains a 40-hp two-speed fan, provides heat rejection. The fans operate in the following sequence with increasing load: one fan at low speed, both fans at low speed, one fan at low and the other at high speed, both fans at high speed. Provision has been made to add a third cell in the future. There are two 50-hp and one 60-hp condenser water pumps. Condenser water temperature is held to an operator-selectable set point by control of a modulating water bypass valve. The control module also has auxiliary contacts for selecting high fan speed. The cooling tower sump is heated by steam in winter and the exposed pipes are protected from freezing by electric heat tracing.

There are two 60-hp and two 75-hp chilled water pumps. Chilled water temperature is held to an operator-selectable set point by another controller. The set point is typically 45°F in summer and 55°F in winter. The controller has a reset-on-load feature that will probably be put to use in the future. A plate heat exchanger manually valved into the condenser and chilled water loops provides "free" chilled water in winter. There is currently no provision for load reset of chilled water temperature in this mode of operation.

Steam is provided by two 500-hp (16.7 MBtu/h) Cleaver-Brooks package boilers and one 200-hp (6.7 MBtu/h) package boiler for use in summer. Each 500-hp boiler has a 15-hp combustion air fan, a 5-hp feedwater pump and a $\frac{3}{4}$ -hp fuel oil pump. A combustion air fan discharge damper and a ten-pin cam control the fuel-air ratio. There is also a stack damper and controller to maintain the windbox at a pressure close to atmospheric. The boilers can be fired by gas or #2 fuel oil atomized by 15 psi air, but there is no intention of routinely using the oil-fired mode. Make-up water and condensate return are not metered but steam flow is metered through an orifice plate. Feedwater is preheated in a heat exchanger at the stack end of the boiler. There is no combustion air preheat. Blowdown is automatic and continuous. Steam is generated at 80 psi in winter and 50 psi in summer. There are two pressure-reducing stations at the east and west ends of the main hall basement. Steam pressure is reduced at each station to 15 psi for use in air-handlers, terminal dry steam humidifiers and domestic water heaters and to 5 psi for use in radiators. A number of steam radiators have been removed from service (leaving the minimum needed for adequate heat) because of a perceived risk (to older people and toddlers especially) of inflicting minor burns. The removal of radiators may have the adverse effect of encouraging electric heater use.

2.4 HVAC Equipment

There are four variable air volume (VAV) air-handlers for the main hall and theater with a connected load, including return fans, of 240 hp. One constant volume (CV), return-air reset system representing a 20-hp connected load serves the concession area. Four CV terminal reheat systems, with a total connected load of 210 hp, serve the museum spaces.

The VAV units have full outside-return air enthalpy economizer controls. A few zones (e.g., conference rooms) have terminal reheat. The supply fans are controlled to maintain about 2" static pressure at the air-handling unit (AHU) outlet by inlet (pre-rotation) vane modulation. The return fans are axial fans in which propeller pitch is modulated by the same signal that modulates supply fan inlet vane position. The return fans are currently set to provide about 80% of the supply fan volume at full (cooling) load conditions. The VAV discharge temperature is set by the operator. The setpoint is typically 55°F in summer, 65°F in winter, and 60°F in swing seasons.

The museum CV air-handlers are designed to maintain the exhibit spaces at 70 to 72°F, 50% relative humidity, 8,760 hours per year. Minimum outside air is used to avoid outside air pollutants. Damper actuators exist at the outside air and exhaust dampers, but it is not clear that they are (or can be) programmed to admit zero outside air during unoccupied periods. The air-handler discharge temperature and maximum humidity are set

by the operator. Steam must be available to the reheat coils at all times of the year because of the humidity and temperature control requirements.

The concession area air-handler has its discharge temperature modulated inversely with return air temperature. Reheat at each zone's terminal unit(s) is controlled by a room thermostat. This scheme gives rapid response to load changes without the stability problems of derivative control. A single thermostat in a location representative of all concession area zones is used at night to turn the air-handler on when area temperature drops to the night setpoint (55°F). The aggregate connected load of kitchen fans, toilet fans and other exhaust fans is 19 hp.

The aggregate connected load of powerhouse air-handlers is 42 hp. The aggregate connected load of fractional unit heater fans is 4 hp, and the aggregate connected load of large exhaust and return fans is 20 hp.

2.5 Lighting

There are approximately two-hundred 60-W exposed incandescent bulbs in decorative fixtures that circumnavigate the main hall at the lip of the balcony floor, 84 exposed 150-W bulbs in 14 small chandeliers, eighty 60-W bulbs in frosted globes of the four central chandeliers and one-hundred-sixty 60-W bulbs in valence fixtures below the arched windows of the main hall clerestory windows. Each of the foregoing classes of light fixtures is divided into zones with separate dimming controls. A Lutron control panel provides four dimming level configurations or "scenes"; the currently active scene is determined by logic signals from the building automation system. Three scenes are currently programmed by time schedule: "night," "staff" (starting at 7 a.m.), and "visitor" (starting at 9 a.m.). The fourth scene is used for special functions, so that the lighting levels of the three regular scenes never have to be disturbed. The time schedule also turns the lights (except for security lights) completely off nightly from midnight to 7 a.m. The valance fixtures can be replaced by dimmable fluorescents.

Most of the lighting in the exhibit areas is provided by 900 incandescent track fixtures. There are also some incandescent and halogen plug-in fixtures powered from convenience outlets in the floor.

Much of the lighting in hallways is provided by incandescent fixtures that have frosted globes (or other shapes that provide a functionally equivalent light-diffusing envelope); replacement of these incandescent bulbs by compact fluorescents appears straightforward.

Lighting in other areas is controlled by the building automation system via relay panels. Operator override is typically invoked about once a week for the cleaning crew to do special cleaning of a specified area.

The staff areas are illuminated by fluorescent fixtures with low-glare reflectors. The high bay area of the heat plant is illuminated by high-pressure sodium lamps.

There are approximately fifty PL7 fixtures (frosted hemispherical cover) along the sea wall. The main walkway is illuminated by approximately twenty 175-W mercury vapor pole lamps with frosted globes. There are approximately forty high-intensity discharge (HID) fixtures under the entry canopy. There are two 1-kW spotlights illuminating the flag pole. The valence lighting, mentioned earlier, illuminates the windows of the great hall and provides the primary architectural lighting effect. There are no floods or spots directed at the exterior of the building.

2.6 Other Equipment and Loads

There are two incinerators that consume paper and plastic waste from office activity and concessions. Each unit has a 75-hp induced draft fan and 5- and 10-hp pumps for scrubber water circulation. There is currently no provision for heat recovery or combustion air preheat. A 10- x 20- x 8-foot refrigerated trash-holding room, cooled by a 5-hp refrigeration machine, is provided for operational flexibility.

Hot water (DHW) is used in bathrooms and for food preparation in the concession area. Heat tape is used to provide a hot water recirculation loop or "instant hot water" effect. Some sections are thermostatically controlled; some use self-regulating (setpoint not adjustable) heat tape.

Cooking and warming appliances in the concession area are all-electric.

2.7 Envelope

The east and west wings were reportedly insulated and fitted with insulating windows during the restoration. The walls in the east and west wings and parts of the central hall have been framed on the inside and insulated with 1- to 1 ½-inch polyurethane foam. The roof was insulated with 1- to 2-inch rigid foam between the decking and tiles. The railroad ticket office roof was insulated with similar material between the decking and the standing-seam finish material.

The central portion of the building was subject to more rigorous restoration criteria and retains its original single-pane windows. It was reported that most of the plaster-finished wall areas in the central hall have been insulated, but the percent of tile-finished wall areas (presumably uninsulated) was not determined. The roof insulation is reported to be similar to that on the east and west wings.

2.8 Operation

Utilities (electrical distribution, water and sewer) and central plant (boilers, chillers, emergency generator, incinerators) are operated and maintained by a contractor under the direction of the park engineer. The contractor also takes care of HVAC distribution operations and maintenance (O&M) and custodial (cleaning, changing light bulbs, etc.) work. Routine plumbing and electrical maintenance is taken care of by NPS personnel. The NPS also oversees operation of concessions (food, gift shop, visitor ferry service). The food and gift shop concession facilities are owned by NPS and leased to concessionaires. The O&M/custodial contractor operates and maintains building systems in the concession areas. Electricity, central steam and chilled water are supposed to be metered, but the central steam and chilled water Btu-meters are not currently operational.

3.0 Energy Usage and Rates

The loads served by different forms of energy and the rate structures associated with each form are described in this section. The effects of seasonal weather and occupancy on energy consumption are also discussed.

3.1 Electrical Energy

PSE&G provides 13.2 kV power that is billed at three different rates, depending on the time of use. The rate schedule is as follows:

<u>Period</u>	<u>Schedule</u>	<u>Use Rate (\$/kWh)</u>	<u>Demand Rate (\$/kW-mo)</u>
On-peak	10 am - 10 pm M-F	0.08141	9.04
Mid-peak	8 am - 10 pm Sat	0.07012	0.92
Off-peak	All other	0.06000	0.92

There are no power factor or reactive demand charges. The average blended rate paid by the site during calendar year 1991 was \$0.72/kWh.

The electric billing history is plotted in Figures 3.1 and 3.2. Figure 3.1 shows monthly energy and demand by billing period. Figure 3.2 shows monthly total energy and apparent (total kWh/total dollars) price of electricity. The history indicates a summer peak that is moderate (due to the relatively efficient three-stage centrifugal cooling plant and its relatively small share in total electric energy use) and an annual use of 8,000 MWh per year. The average monthly load factor (15-minute peak to average load ratio) is about 1.5.

3.1.1 Utility Demand-Side Management Program Offerings

PSE&G offers several demand-side management program offerings for its commercial/industrial customers. These range from "technical assistance" to cash incentives for load management and conservation strategies. They include:

Figure 3.1. Monthly Electrical Demand and Consumption by Time of Use

Figure 3.2. Monthly Electrical Consumption and Cost Expressed in \$/kWh

- **Energy Efficiency Evaluation** which includes checking customer's facility and providing a detailed report on "energy trouble spots." A list of recommendations will be provided to show the customer how to lower operating costs. The recommendations include energy conservation measures with cost and payback as well as specific operating and maintenance procedures.
- **Cash Rebates** for replacing standard fluorescent lamps with high-efficiency lamps. The maximum currently available rebate is \$5,000/customer.
- **Thermal Storage System** cash rebates of \$250/kW of summer peak demand reduction for the first 500 kW and \$125/kW for load reductions greater than 500 kW.
- **Gas Absorption and Gas-Fired Engine-Driven Chillers** cash rebates to replace electric chillers (minimum of 100 ton). Rebates are \$125/ton for new and \$75/ton for retrofit absorption chillers, and \$50/ton for new or replacement gas-fired engine-driven chillers.
- **Load Management Assessment** to shift and/or minimize the time and amount of use of electrical load (both demand and energy). This would be implemented either directly by the utility (e.g., through load controllers) or indirectly by the customer (e.g., through use of backup generation during peak load periods).

3.2 Natural Gas

The natural gas billing history is plotted in Figure 3.3. Natural gas consumption is expressed in millions of British thermal units (MBtu) of *higher heating value* heat content represented by the volume of gas delivered. The minimum monthly average consumption is 1.8 MBtu/hr (9 Btuh/ft²) in August 1991 and the maximum is 6.5 MBtu/hr (32 Btuh/ft²) in February 1992. Total consumption between 3 April 1991 and 31 March 1992 was 33,920 MBtu (170,000 Btu/ft²-yr) at a cost of \$175,215. The price of natural gas fluctuates with supplier costs and averaged \$5.17/MBtu in this period.

The electric and gas billing histories are documented in Table 3.1.

Figure 3.3. Monthly Natural Gas Consumption and Cost in \$/MBtu

Table 3.1. Gas And Electricity Billing History

Period Ending	Natural Gas		Electrical Energy (kWh)			Demand (kW)			\$
	Therms	\$	On-Peak	Mid-Peak	Off-Peak	On-Peak	Mid-Peak	Off-Peak	
01/31			299,600	64,400	296,800	1176	1064	1148	45,065
03/05			252,000	47,600	271,600	980	952	952	38,903
04/03	37,341	20,220	282,800	64,400	316,400	1148	1204	1204	45,707
05/02	39,735	21,511	271,600	50,400	252,000	1176	1008	1036	41,511
06/03	26,331	12,109	288,400	56,000	288,400	1400	1232	1260	46,524
07/02	19,397	9,018	366,000	75,600	352,800	1568	1316	1260	56,450
08/01	14,824	6,980	333,200	64,400	316,400	1316	1316	1568	52,201
08/30	14,825	6,980	364,000	70,000	322,000	1624	1540	1568	57,642
10/01	13,124	6,223	344,400	64,400	310,800	1596	1624	1540	55,461
10/30	18,755	8,732	338,800	75,600	333,200	1344	1288	1288	52,179
12/02	26,704	14,482	305,200	61,600	280,000	1288	1288	1260	46,691
01/02	36,305	19,661	282,800	64,400	277,200	1232	1260	1232	44,825
01/31	42,923	23,222	285,600	53,200	252,000	1232	1204	980	43,109
03/03	41,189	22,104	252,000	44,800	235,200	1008	896	924	37,972
03/31	45,093	24,193	260,400	58,800	263,200	980	924	952	40,293

3.3 Fuel Oil

Fuel oil has not been used in the dual-fuel boilers and there are no plans to use fuel oil except in the event of a loss of natural gas service. Fuel oil is used to operate the emergency generator but this use has not been a significant fraction of the site's total energy use.

3.4 Weather and Population Effects

The seasonal dependence of heating load is clear from the monthly gas consumption history plotted in Figure 3.3. A more detailed analysis of weather effects was not carried out for the preliminary assessment. The visitor counts from October 1990 through April 1992 are documented in Table 3.2. Electrical consumption (Figure 3.1) appears to be only weakly correlated with visitor count.

Table 3.2. Monthly Visitor Counts

<u>Year</u>	<u>Month</u>	<u>Visitor Count</u>
1990	October	172,426
	November	167,094
	December	82,661
1991	January	50,481
	February	54,109
	March	102,380
	April	183,172
	May	257,025
	June	228,857
	July	221,014
	August	214,697
	September	171,426
	October	176,197
	November	112,819
	December	82,226
1992	January	42,425
	February	50,694
	March	79,369
	April	145,680

The use of electricity in the concessions, on the other hand, is reasonably well correlated with visitor count. The data are plotted in Figure 3.4. The electrical end-uses represented by the data include cooking and refrigeration but not air conditioning. Air conditioning is provided by chilled water from the central plant. Note that the 4Q90 and 1Q91 points are averages taken over the two quarters because the total kWh for both quarters was the only available kWh number.

Figure 3.4. Average Monthly Concession Electrical Consumption vs. Visitor Count

3.5 Energy-Use Intensities by Electrical End-Use

Estimates of annual energy consumption by electrical end-use have been developed from the inventory of connected loads and estimates of annual operating hours for each load or class of loads. These estimates had to be adjusted upwards somewhat to reconcile the resulting engineering estimate with measured aggregate energy use as reported in the billing history. The resulting estimated energy baseline is tabulated below. The "Other" category includes plug loads, cooking, refrigeration, incinerator pumps and fans, elevators, and unaccounted for lighting loads.

End-Use	Annual Energy Consumption	
	(kWh/yr)	(%)
Chiller Compressor	850,000	10.6
Chiller Auxiliaries	1,050,000	13.0
Boiler Auxiliaries	150,000	1.9
HVAC Fans	1,700,000	21.1
Lighting (feasible ECOs)	2,034,000	25.3
Lighting (unfeasible)	884,000	11.0
Distribution Loss	480,000	6.0
Other	900,000	11.2
Total	8,048,000	100.0

The chiller compressor load can be further disaggregated by cooling load component. Such a disaggregation can be useful in determining reductions in cooling loads that will occur when other energy conservation measures (e.g., efficient lighting) are implemented. The components of the cooling load met by the plate heat exchanger have not been estimated because the data

needed to estimate the total load on the plate heat exchanger are not available or have not been logged. Estimates of the main components of the chiller cooling load are tabulated below:

Cooling Load Component	Chiller Compressor Energy	
	(kWh/yr)	(%)
Electrical gains	350,000	41.2
Metabolic-sensible	30,000	3.5
Metabolic-latent	25,000	3.0
Outside air-sensible	22,000	2.6
Outside air-latent	78,000	9.2
Solar	160,000	18.8
Envelope	35,000	4.1
Other	<u>150,000</u>	<u>17.6</u>
Total	850,000	100.0

3.6 Energy-Use Intensities by Fossil Fuel End-Use

The primary end-uses of natural gas on the site are space and domestic water heating. Space heating can be further divided into latent and sensible ventilation loads and envelope loads. Conservative engineering estimates were developed to help identify ECOs associated with these loads.

Estimates of annual energy consumed by each steam load were developed based on 24-hour per day ventilation and the lowest plausible R-values (R-2 average) and highest plausible hot water use (0.5 gallon per visitor at 80°F rise) that could be reasonably assumed. In addition, the highest possible balance point (70°F) was assumed. The resulting estimates, tabulated on the next page, still are nearly 50% of actual consumption. Some possible explanations for the discrepancy are excessive ventilation loads, excessive energy use for the reheat systems, poor boiler efficiency, large steam distribution loss, excessive use by the incinerators, natural gas leaks, or gas meter error. Based on the field experience at other federal and commercial facilities, excessive ventilation and reheat operation are the most likely explanations for the discrepancy. This can be confirmed by field measurements.

Thermal end-use:	MBtu/yr
Envelope, conduction	7,000
Ventilation-sensible	5,000
Ventilation-latent	3,000
Domestic water heating	1,000
Distribution loss (est.)	1,000
Stack loss	5,000
Incinerator (est.)	1,000
Unknown	10,000
Total from PSE&G billings	33,000

4.0 Energy Conservation Opportunities

The energy saving potential of an energy conservation opportunity (ECO) is determined from the percent savings that is realized when a given piece of end-use equipment is replaced by a life-cycle cost-effective, energy-efficient fixture or system that provides the same or comparable service. The savings potential for each end-use and the aggregate savings for all end-uses can then be estimated. These estimates are presented below with a description of each ECO considered appropriate for the site.

4.1 Central Plant

The chiller compressors use about 850,000 kWh/yr. An internal combustion engine powered chiller is a possible ECO; however, the year-round heating load is required to be in the form of steam, which complicates the utilization of engine waste heat. The facts that the existing three-stage chiller is relatively efficient and provision for free cooling via a plate heat exchanger already exists are likely to make the economics of this ECO unattractive based on cost of operation alone. The electric utility's \$50/ton rebate (\$75/ton for absorption chillers) may provide a sufficient incentive, but this has not been evaluated for this assessment. Other promising avenues for chiller energy savings are the measures that reduce coil loads and increase free cooling opportunities. These measures are described below.

The chilled and condenser water pumps and cooling tower fans use about 1,050,000 kWh/yr. The 40-hp cooling tower fans are two-speed units. A variable-speed or energy-efficient motor retrofit is therefore not likely to be cost-effective except as a replace-on-failure measure. Conversion of the 50- and 60-hp condenser water pumps to variable-speed drive can save about 200,000 kWh/yr. Condenser water flow rate will be controlled by the condenser heat rate and the modulating valve will be fixed in the zero bypass position after the retrofit. Two other cooling tower-related measures are a thermostat for the trace heater (so it will operate only when the pipe surface temperature drops below 45°F to provide freeze protection) and improved control of the sump freeze protection that is provided by direct steam. The current energy use and potential savings for these cannot be estimated without field measurements.

Conversion of one 75-hp and two 60-hp chilled water pumps to variable-speed pumps will save about 250,000 kWh/yr. The chilled water supply temperature control will have to be modified if it is currently reset on supply-return temperature difference; it should be reset on the heat rate (i.e., the product of flow rate and supply-return temperature difference).

The boilers currently use 33,900 MBtu/yr (higher heating value) of natural gas. The combustion air fans and feedwater pumps use about 145,000 kWh/yr. Conversion of the combustion air fans to variable-speed fans will save about 90,000 kWh/yr. Conversion of the feedwater pumps and reducing steam supply pressure will save at least 20,000 kWh/yr, with proper controls, in feedwater pump energy. Reducing steam pressure will save about 1000 MBtu/yr in natural gas by reducing boiler stack temperature. Reduced steam pressure will also save an additional 40 MBtu/yr due to reduced steam distribution loss and 2,000 kWh/yr due to reduced chiller operation for removing the heat due to internal steam distribution system losses.

4.2 HVAC Equipment

The four variable air volume (VAV) air-handlers use about 275,000 kWh/yr. Average fan power can be reduced by changing from static pressure control to most-needy-zone control. Note that fan power and chiller power can be traded by varying chilled water set point. A control algorithm that determines the optimal chilled water temperature should be used if the control vendor can provide it.

The CV air-handler that serves the concession area uses about 33,000 kWh per year. The unit can be converted to VSD with flow rate controlled by occupant load as measured by CO₂ concentration and humidity in the return air. Calibration requirements for the CO₂ sensors will be more stringent than usual because the control must maintain a lower than normal value of excess CO₂ in order to maintain sufficient air flow to control odors and other airborne products of food production, distribution and consumption in the concession area. This scheme will modulate outside air as well as supply and return air flow rates and is preferred to a control that modulates only outside air. The former saves significant fan energy as well as primary heating and cooling energy needed to condition the outside air. Savings of about 20,000 kWh and 200 MBtu per year can be expected.

The four CV terminal reheat/re-humidify systems serving the museum spaces use about 770,000 kWh/yr. An estimated 315,000 kWh/yr can be saved by operating at two-thirds of the nominal airflow rate during unoccupied hours (14 hours per day). The temperature and humidity distributions in exhibit spaces should not be adversely affected by the reduced flow because local heat and humidity loads are relatively small during unoccupied periods. An additional 200,000 kWh/yr might be saved by converting the fans to VSD and modulating airflow on the humidity and heat loads of the highest load zones. Coil valve and humidifier control gains may have to be reduced modestly to maintain stability with the reduced air flows.

Efficient motor and CO₂ sensor EROs are applicable to air-handlers AHU-1 through AHU-9 and Powerhouse air-handlers AHU-1 and AHU-2. CO₂ sensors can save from 1,000 to 5,000 MBtu/yr (and possibly more) depending on the existing ventilation rate and control scheme.

The aggregate connected load of kitchen fans, toilet fans and other exhaust fans is 19 hp. These units have 1/25 to 1/2 hp motors which should be considered for replacement by energy-efficient motors when they fail. Permanent magnet or other efficient motor technologies may make replacement prior to failure cost-effective at some future time.

Conversion of kitchen exhaust hoods to combined supply-return heat recovery units should be considered.

4.3 Lighting

Lighting uses an estimated 3,000,000 kWh/yr (37% of the total) at the site. An inventory of lighting equipment by fixture type and function appears in Table 4.1. A recommended retrofit is given, where feasible and cost-effective, for each existing fixture type, and the resulting savings is indicated. The initial cost numbers, from the PNL Lighting Matrix, include labor, materials, overhead and profit, but no credit for utility rebates. The total potential savings is estimated to be approximately 1,051,000 kWh/yr (37%). (Note that the changes in the heating/cooling load requirement from a lighting retrofit are not quantified nor included in this savings estimate. It is however estimated that the heating load will increase less than 2% to make up for heat lost through a lighting retrofit.) Of this estimated total, 531,000 kWh/yr is due to replacing incandescents with compact fluorescents (CFL), 75,000 kWh/yr results from replacing incandescents with dimmable fluorescents, 14,000 kWh/yr is due to replacing mercury vapor with metal halide and CFL fixtures, 206,200 kWh/yr is due to replacing existing fluorescents with high-efficiency fluorescent (T-8) systems, 214,000 kWh/yr results from replacing existing incandescents with metal halide or high-efficiency incandescents, and 10,800 kWh/yr is due to replacing fluorescent exit signs with light-emitting diode (LED) exit signs.

The lighting retrofit table indicates that 50% of the energy used by fixtures considered for retrofit can be saved with cost-effective retrofits. However, one-third of the lighting energy is used in fixtures where retrofits are not technically feasible due to architectural constraints. Occupancy sensors may be an acceptable and cost-effective conservation measure in the exhibit and other public areas where fixture retrofits are not feasible. The installation of more accessible or automated (occupancy-sensing) light switches in the

Table 4.1. Conservation Potential of Lighting For Selected Retrofits

Use or Code ^(a)	Operation (h/yr) ^(b)	Description, existing fixture	Qty (#)	Size (W)	Description, efficient fixture	Output (%) ^(c)	Size (W)	Energy Use (Existing) (kWh/yr)	Energy Savings (kWh/yr)	Energy Savings (\$/yr) ^(d)	Demand Savings (\$/yr) ^(d)
FV-FAK1	6570	INC hanging glb (most)	438	100	26-28 W CFLquad 7.6"	85	35	287,766	187,048	9,352	3074
FX-FAO	6570	INC in hanging globe	272	200	26-28 W CFLquad 7.6" ^(e)	43	35	357,408	294,862	14,743	4847
FY-FK	6570	INC in down sconce	35	60	11 W CFL twin 5.75"	83	15	13,797	10,348	517	170
FAX	6570	INC "saucer" wall light	10	60	13-15 W CFL twin 6.5"	99	19	3,942	2,694	135	44
FAJ	6570	INC (3) in hanging globe	45	60	13-15 W CFL twin 6.5"	99	19	17,739	12,122	606	199
FW,FD	6570	INC in up wall light	80	60	11 W CFL twin 5.75" ^(e)	83	15	31,536	23,652	1,183	389
EXIT	8760	Fluorescent	63	26	LED	NA	6.5	14,349	10,762	538	133
FO,FAN	6570	PAR38 flood/Watt-miser ^(f)	104	120	60PAR/FL/HIR(halogen) ^(g)	NA	60	81,994	40,997	2,050	674
FL	6570	PAR38 spot	208	75	65R/SP Watt-miser	NA	65	102,492	13,666	683	225
FF	6570	50-R20 spot	254	50	(44) T8 w/dimBist & para ref.	NA	29	83,439	75,056	3,753	1234
FAM	6570	INC	104	300	Met. Hal. (bist in dlg cover)	79	95	204,984	140,072	7,004	2303
FM,FB	6570	INC	195	150	Watt-miser	91	135	192,173	19,217	961	316
Office	5000	1X4 2-tube F40WW	1250	98	T-8 System	74	65	612,500	206,250	10,313	4455
Sidewalk	4380	175 W mercury vapor	20	210	100 W Metal Halide	105	130	18,396	7,008	350	173
Canopy	4380	40 W mercury vapor	48	60	20 W CFL	96	25	12,614	7,358	368	181
FAZ	6570	300 W quartz	16	300	No Retrofit	NA	NA	31,536	0	0	0
FAZ1	6570	500 W quartz	12	500	No Retrofit	NA	NA	39,420	0	0	0
FAN1	4380	PAR38 "pink" spot	8	85	No Retrofit	NA	NA	2,978	0	0	0
FA	4380	KYP-GO INC	876	60	No Retrofit	NA	NA	230,213	0	0	0
Track	6570	INC spot(?)	900	80	No Retrofit	NA	NA	473,040	0	0	0
HPS	8760	250 W HPS	4	305	No Retrofit	NA	NA	10,687	0	0	0
HPS	8760	400 W HPS	13	465	No Retrofit	NA	NA	52,954	0	0	0
Seawall	4380	PL7/27	50	11	No Retrofit	NA	NA	2,409	0	0	0
Exhibit	4380	100W halogen	93	100	No Retrofit	NA	NA	40,734	0	0	0
Flagpole	4380	Incandescent spot	2	1000	No Retrofit	NA	NA	8,760	0	0	0
Totals:								2,927,860	1,051,110	52,556	18,417
Total for fixtures with feasible retrofit(s)								2,035,128			
Total for fixtures with no feasible retrofit								892,732			

Notes:

- Fixture codes from construction drawings; short description appears in cases where a code was not assigned in a drawing.
- Hours of operation per year as indicated by the site O&M contractor.
- Light output of efficient fixture as a percent of existing light output.
- Based on approximate average rates of \$0.05 kWh and \$9.00 kW/mo.
- FAO dimming will not be possible.
- Will no longer be dimmable.
- Some units use side prong bulbs; side prong may not be available in halogen retrofit bulbs.

office areas may also be cost-effective. An additional 200,000 kWh/year savings is estimated from the installation of occupancy sensors (not shown in Table 4.1).

4.4 Other Equipment and Loads

The trash incinerators probably do not have sufficient operating hours to justify motor ECMs. It may be feasible to recover stack heat via the scrubber water to heat the fuel oil storage tanks or to install a boiler make-up water storage tank and heat it. Alternatively, a heat wheel could be used to preheat combustion air and thus reduce natural gas consumption. More data on incinerator operation and gas consumption are needed to assess such measures.

An efficient motor retrofit of the trash holding room refrigeration machine will save approximately 100 kWh/yr.

Energy used by heat tape to keep domestic hot water (DHW) warm for "instant hot water" effect has not been estimated. Energy savings potential of better control should be investigated. If there is a freeze potential, a lower setpoint thermostat can be used instead of completely disabling the heat tape; a dual setpoint thermostat can be used in conjunction with schedule control to retain the instant hot water feature during occupied hours.

Electrical distribution losses amount to about 480,000 kWh/yr and are primarily transformer losses. Transformer losses can be reduced by about 200,000 kWh/yr by replacing the transformers with properly sized high-efficiency transformers. A significant peak shaving opportunity exists because the monthly demand is typically over 1.5 times the average load. The existing generator has more than enough capacity (over 50% of base-load) and can be adapted to provide peak shaving with the addition of switchgear and controls.

4.5 Envelope and HVAC Distribution

Estimates of the envelope loads have been made to assess the need for further study of insulation and weatherization measures and to estimate the magnitudes of HVAC losses due to non-ideal distribution and control. However, field confirmation of insulation was not possible within the scope of the preliminary assessment. Based on the reported levels of insulation there may be opportunities to reduce window heat loss in the main hall and infiltration losses through attic spaces, exhaust ducts and other envelope penetrations.

The walls of the east and west wings were reportedly insulated and fitted with insulating windows during the restoration; however, the high annual gas use documented in Section 3.0 is inconsistent with the reported insulation levels. A thorough inspection should be initiated to confirm the insulation levels, and a series of blower door tests should be run to identify infiltration sites.

The energy consumption due to ventilation was more amenable to analysis. The aggregate nominal make-up air flow for air-handlers 1 through 8 is 25,000 cubic feet per minute (cfm), and the flow for air-handler 9 is over 6000 cfm. This represents about 1,500 MBtu/yr raw heating energy for 10 h/day of daytime ventilation, or 4,800 MBtu/yr for 24 h/day ventilation. The latent and sensible cooling load to condition this ventilation air is about 2,100 MBtu/yr (115,000 kWh/yr in chiller compressor energy). It is estimated that control of ventilation air by CO₂ sensors would save at least 1,000 MBtu/yr in natural gas and 30,000 kWh/yr in electricity. Kitchen and other special ventilation loads have not been considered in this assessment but may represent further energy savings potential.

5.0 Findings and Recommendations

5.1 Findings

Electrical energy use at Ellis Island is higher than expected based on the installed equipment and its reported operation. Natural gas use is also higher than expected. The energy use intensities (EUIs) of the site are 40 kWh/ft²-yr for electricity and 170,000 Btu/ft²-yr for natural gas.

5.2 Recommendations

There are a number of technically feasible and cost-effective energy conservation opportunities (ECOs) for the site to consider. These are given below.

5.2.1 Lighting

The lighting ECOs identified in Table 4.1 should be considered for immediate implementation. These retrofits comply with the federal life-cycle cost-effectiveness criteria and include replacing incandescents with compact fluorescents, replacing incandescents with dimmable fluorescents, replacing mercury vapor with high-pressure sodium lamps, replacing existing fluorescents with high-efficiency units, and replacing fluorescent exit signs with light-emitting diode (LED) exit signs.

Though the retrofits are primarily for "one-for-one" replacement, the design of these retrofits will require skills of an experienced lighting design expert to ensure that the site's image as an historic monument is not compromised. Occupancy sensors or better zoning should be considered in rooms where fixture retrofits are not feasible.

5.2.2 HVAC Systems and Envelope

The ECOs identified for HVAC equipment include converting the four CV systems to two-speed fan operation; replacing inlet-vane with VSD control of VAV flow rate; replacing pump and fan motors with properly sized, efficient motors; modifying outside air control and installing low-leak dampers in the CV systems to provide zero outside air in unoccupied periods; providing CO₂ control of outside air in all zones; improving control and balance to minimize H/C coil loads; and implementing (or fine-tuning) optimal start/stop control. Replacement of the existing cooling/dehumidification coil configuration in the four CV units with a face-and-bypass configuration should also be explored.

5.2.3 Central Plant and Thermal Distribution Systems

Central plant and distribution ECOs identified include two-speed or variable-speed pumps for chilled and condenser water; reducing steam pressure to 15 psi; replacing lead condensate return pumps with downsized, efficient pumps; providing a small local boiler for summer CV system loads; implementing incinerator heat recovery for combustion air or other use; and providing thermostatic control of (or remove) the DHW heat tape system. Electrical energy savings can also be obtained by replacing single-speed feedwater and combustion air motors with two-speed motors or installing variable-speed drives. The feasibility of these measures, however, will depend to large extent on the boiler manufacturer's technical support.

5.2.4 Electrical Distribution and Generation Systems

Electrical distribution ECOs include using the existing 750-kVA diesel generator for peak shaving and replacing transformers (on failure) with high-efficiency models.

5.2.5 Other Systems

Other ECOs include providing two-speed, variable-speed, or downsized-efficient ejector pumps; incinerator heat recovery; an efficient motor retrofit for the trash holding room refrigeration compressor; and reducing heat tape temperatures. Use of the existing generator for peak shaving will not reduce energy consumption but can reduce the site's electric bill significantly.

5.3 Savings Potential

The savings that can be expected for the ECOs outlined above have been estimated in Table 5.1. For this preliminary assessment, the accuracy of the individual electrical savings is $\pm 30\%$; the accuracy of the total savings in Table 5.1 is $\pm 15\%$. The total estimated electric savings potential is over 32%.

The annual consumption of natural gas is at least 30% higher than can be accounted for by the engineering estimates. The potential to save more than half of the 33,000 MBtu/yr in current gas consumption appears to exist, but further investigation of thermal energy end-uses is needed to determine what operational changes and retrofit measures are needed to accomplish this. The natural gas savings estimates in Table 5.1 reflect the lowest savings estimates for the two ECOs that could be identified with the available information.

Table 5.1. Estimated Energy Use and Savings Potential Enumerated By ECO

	Electrical Energy		Fossil Energy	
	Current (kWh/yr)	Savings (kWh/yr)	Current (MBtu/yr)	Savings (MBtu/yr)
Chilled Water System				
VSD ChW & CndW pumps	1,050,000	200,000		
VSD ChW & CndW pumps		250,000		
VSD combustion air fans	145,000	90,000		
VSD feed pumps		20,000		
Reduce steam pressure	5,000	2,000	100	40
HVAC Fan and Distribution Systems				
2-speed CV fans	770,000	315,000		
Alternate: VSD	(a)	200,000		
Most needy zone ctrl of 4 VAC fans	275,000	75,000		
VSD concession area fan	33,000	20,000		
Energy efficient motors	(a)	10,000		
Energy efficient KX&TX motors	50,000	1,000		
Lighting				
Replace inc. w/compact fluorescent	712,000	531,000		
Replace inc. w/dimmable fluorescent	83,000	75,000		
Replace Hg vpr w/metal halide or CF	31,000	14,000		
Fluorescent upgrade	613,000	206,200		
Replace inc. with metal halide	205,000	140,000		
LED exit signs	13,000	10,800		
Replace std inc. w/high effic.	295,000	74,000		
Occupancy sensors	881,000	200,000		
Envelope and Ventilation Loads				
CO ₂ sensors			7,000	1,000
Double glazing			1,200	600
Transmission & Distribution				
Efficient transformers	480,000	200,000		
Other Loads	2,407,000		24,700	
Total	8,048,000	2,634,000	33,000	1,640
(a) End-use accounted for in previous line(s).				

5.4 Utility Incentives

The utility, PSE&G, is about to launch a multiyear conservation acquisition program that covers a greater variety of conservation measures than the PSE&G standard rebate program. The current incentive caps (e.g., \$5,000 for fluorescent tubes and \$5,000 for all other measures) of the standard rebate program are also being eliminated. The initial two-year (1992-93) acquisition is limited to 150,000 kW in 400 kW (average summer on-peak) minimum blocks. PSE&G's acquisition differs from many other utilities' demand-side management programs in making the customer responsible for 1) verifying the energy savings over the life of the project and 2) determining the cost-effectiveness of measures. The willingness of PSE&G to up-front finance the initial capital cost of the retrofits for federal customers and go considerably beyond its standard incentive program is a significant unknown that should be explored.

5.5 Technical Assistance

FEMP can make PNL available on a cost-recovery basis to assist the Ellis Island National Park Service in short-term testing and monitoring to measure energy end-use and to assist in procuring energy-efficiency improvements through internal, utility, or shared energy savings projects.

Lighting retrofit, HVAC load-reducing measures, pump and fan downsizing and motor retrofits, and peak-shaving implementation are projects that can benefit from a better understanding of energy use and related existing conditions prior to proceeding with detailed design work. Sample measurement plans for such projects are presented in Appendix B.

Appendix A

Documentation

Appendix A

Documentation

Drawings

Mechanical:	M7, M12, M13, M19-M26, M30, M31, M34-M36
Electrical:	E8-E10
Reflected Ceiling Plans	
Powerhouse:	A35-A36
Main Building:	A127-A136
Building Automation System	
Lighting Power Relays:	BAS15-BAS21
Lighting Zones:	BAS22
Lighting FPU Schematics:	BAS23-BAS31
Lighting Fixture Details:	L1.0-L1.15

Historical Bills: Gas
 Electric
 Water and sewer

Chiller Logs: typical summer week--2-hour logs
 typical winter week--2-hour logs

Boiler Logs: typical summer week--2-hour logs
 typical winter week--2-hour logs

Monthly visitor counts.

Appendix B

Preliminary Measurement Plan

Appendix B

Preliminary Measurement Plan

Objectives:

- Confirm utility meter accuracy;**
- Identify energy waste;**
- Quantify energy use by end-use;**
- Provide basis for accurate estimates of conservation potential.**

1. Substation

- Revenue meter pulse output**
- Individual measurement of power to the six distribution transformers**

2. Powerhouse monitoring

- Main gas meter pulse output**
- Boiler gas valve positions**
- Steam flow (rehabilitate existing meter)**
- Feedwater flow rate**
- Make-up water flow rate**
- Incinerator gas valve positions**
- Incinerator scrubber fan and pump status**
- Outdoor wet and dry bulb temperatures and barometric pressure**
- Insolation and wind speed**
- Condenser and chilled water temperatures**
- Aggregate power of chiller compressors**
- Aggregate power of chilled water pumps**
- Aggregate power of condenser water pumps**
- Aggregate power of cooling tower fans**
- Aggregate power of combustion air fans**

3. HVAC monitoring (by AHU; three AHUs per logger)

- Supply, return, and mixed-air temperatures**
- Cooling coil condensate drain flow rate**
- Aggregate reheat coil condensate return flow**
- Air stream temperature rise across dry steam humidifiers**
- Aggregate lighting power to zones served by AHU**
- Supply and return fan power (2 CTs per fan)**

Distribution

No. of
Copies

No. of
Copies

OFFSITE

- 12 DOE/Office of Scientific and
Technical Information

M. Ginsberg
Federal Energy Management Program
U.S. Department of Energy
CE-44
1000 Independence Avenue, S.W.
Washington, DC 20585

- 2 L. Harris
Federal Energy Management Program
U.S. Department of Energy
CE-44
1000 Independence Avenue, S.W.
Washington, DC 20585

- 5 National Park Service
Ellis Island
Liberty Island
New York, NY 10004
ATTN: T. Bradley
M. Conklin
J. Culkin
R. Wells (2)

- 2 New York Support Office
U.S. Department of Energy
26 Federal Plaza
New York, NY 10278
ATTN: C. Baxter
W. Belgrave

- 2 J. Duran
National Parks Service
800 N. Capitol St. NW
Suite 580/Code 610
Washington, DC 20003

- 2 New Jersey Public Service
Electric and Gas
P.O. Box 570
Newark, NJ 07101
ATTN: F. Link
J. Polaski

ONSITE

DOE Richland Field Office

D. R. Segna

- 22 Pacific Northwest Laboratory

R. Bartlett
P. R. Armstrong (3)
J. W. Currie
B. L. Mohler
G. B. Parker (5)
D. R. Payson
W. F. Sandusky
J. L. Stoops
Project File (2)
Publishing Coordination
Technical Report Files (5)

END

**DATE
FILMED**

3 / 15 / 93