AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

1 of 1

**Environmental Restoration Program Pollution Prevention
Performance Measures for FY 1993 and 1994
Remedial Investigations**

Environmental Restoration Program
P.O. Box 2003
Oak Ridge, Tennessee 37831-7298

Date Issued—March 1993

Prepared by
Roy F. Weston, Inc.
704 South Illinois Avenue Suite C-102
Oak Ridge, Tennessee
under General Order Subcontract 91B-99927C

Prepared for
U.S. Department of Energy
Office of Environmental Restoration and Waste Management
under budget and reporting code EW 20

MARTIN MARIETTA ENERGY SYSTEMS, INC.
managing the

Oak Ridge K-25 Site
Oak Ridge Y-12 Plant
Oak Ridge National Laboratory
under contract DE-AC05-84OR21400

Paducah Gaseous Diffusion Plant
Portsmouth Gaseous Diffusion Plant
under contract DE-AC05-76OR00001

for the
U.S. DEPARTMENT OF ENERGY

MASTER

CONTENTS

CONTENTS	iii
FIGURES	v
TABLES	vii
ACKNOWLEDGMENTS	ix
EXECUTIVE SUMMARY	xi
1. INTRODUCTION	1
1.1 PURPOSE	1
1.2 SCOPE	1
1.2 DRIVERS	2
2. METHODOLOGY	5
3. DATA SUMMARY	13
4. PERFORMANCE MEASURE	26
4.1 OVERALL PERFORMANCE MEASURE	26
4.1.1 Training	26
4.1.2 Self-Assessment Audit	27
4.1.3 Field Implementation	27
4.1.4 Documentation	28
4.1.5 Technology Transfer	28
4.1.6 Planning	28
4.2 PERFORMANCE MEASURES FOR EACH ER PROGRAM	28
4.2.1 K-25 Site ER Program	29
4.2.2 Y-12 Plant ER Program	29
4.2.3 Clinch River/Off-Site ER Program	30
4.2.4 Paducah ER Program	31
4.2.5 Portsmouth ER Program	31
5. CONCLUSIONS/RECOMMENDATIONS	33

FIGURES

1	Logic diagram for scoring RI projects	6
2	A graphical representation of the response to a yes/no question	14
3	An example of the distribution of the answers	14
4	Training scores by facility	26
5	Self-assessment scores by facility	27
6	Field implementation scores by facility	27
7	Documentation scores by facility	28
8	Technology transfer scores by facility	29
9	Planning scores by facility	29
10	ORNL scores by category	30
11	K-25 scores by category	30
12	Y-12 Plant scores by category	31
13	Clinch River/Off-Site scores by category	31
14	Paducah scores by category	32
15	Portsmouth scores by category	32

TABLES

1	Regulatory guidance	3
2	Percentages of yes/no responses to training question 1	15
3	Percentages of yes/no responses to self-assessment audits question 1	15
4	Percentages of yes/no responses to self-assessment audits question 2	16
5	Percentages of yes/no responses to self-assessment audits question 3	16
6	Percentages of yes/no responses to self-assessment audits question 4	16
7	Percentages of yes/no responses to self-assessment audits question 5	17
8	Response expressed in percentages for multiple choice question 4 pertaining to self-assessment audits	17
9	Percentages of yes/no responses to field implementation question 1	17
10	Responses expressed in percentages for the multiple choice portion of field implementation question 1	18
11	Responses expressed in percentages for multiple choice question 2 pertaining to field implementation	18
12	Percentages of yes/no responses to documentation question 1	19
13	Percentages of yes/no responses to documentation question 2	19
14	Percentages of yes/no responses to documentation question 3	20
15	Percentages of yes/no responses to documentation question 4	20
16	Percentages of yes/no responses to documentation question 5	21
17	Percentages of yes/no responses to documentation question 6	22
18	Percentages of yes/no responses to question 1 pertaining to technology transfer for soils	22
19	Percentages of yes/no responses questions 2, 3, and 4 pertaining to technology transfer for sediments/sludges	22
20	Percentages of yes/no responses pertaining to planning for soils questions 2, 4, 5, 7, 9, and 11	23
21	Percentages of yes/no responses pertaining to planning for sediments/sludges questions 13, 15, 16, 18, 20, and 21	23
22	Percentages of yes/no responses pertaining to planning for surface water, groundwater, and drilling fluids questions 24, 26, and 29	23
23	Percentages of yes/no responses to question 31 pertaining to planning for decontamination liquids	24
24	Percentages of yes/no responses to questions 33 and 34 pertaining to planning for personal protective equipment (PPE)	24
25	Percentages of yes/no responses to questions 35 and 36 pertaining to planning for soils	24
26	Percentages of yes/no responses to questions 37 and 38 pertaining to planning for sediments/sludges	25
27	Percentages of yes/no responses to question 40 pertaining to planning for surface water, groundwater, and drilling fluids	25

ACKNOWLEDGMENTSS

The Environmental Restoration Pollution Prevention Program acknowledges the following project managers for their dedication and contributions to this report.

S. C. Bieniek
H. Boston
J. E. Carter
R. B. Cook
F. Haywood
J. A. Hodgins
C. Hudson
S. J. Kondracki

E. Krispin
C. J. Marshall
T. Newsom
T. E. Post
M. L. Solienberger
D. M. Ulrich
A. S. Will

EXECUTIVE SUMMARY

The Martin Marietta Energy Systems, Inc., Environmental Restoration (ER) Program adopted a Pollution Prevention Program in March 1991. The program's mission is to minimize waste and prevent pollution in remedial investigations (RI), feasibility studies (FS), decontamination and decommissioning (D&D), and surveillance and maintenance (S&M) site program activities. Mission success will result in volume and/or toxicity reduction of generated waste.

The ER Program waste generation rates are projected to steadily increase through the year 2005 for all waste categories. Standard production units utilized to measure waste minimization apply to production/manufacturing facilities. Since ER inherited contaminated waste from previous production processes, no historical production data can be applied. Therefore, a more accurate measure for pollution prevention was identified as a need for the ER Program. The Energy Systems ER Program adopted the concept of numerically scoring their waste generators to measure the effectiveness of pollution prevention/waste minimization (PP/WM) programs and elected to develop a numerical scoring system (NSS) to accomplish these measurements.

The prototype NSS, a computerized, user-friendly information management database system, was designed to be utilized in each phase of the ER Program. The NSS was designed to measure a generator's success in incorporating pollution prevention in their work plans and reducing investigation derived waste (IDW) during RIs.

Energy Systems is producing a fully developed NSS and actually scoring the generators of IDW at six ER sites: Oak Ridge National Laboratory (ORNL), the Oak Ridge Y-12 Plant, the Oak Ridge K-25 site, Paducah Gaseous Diffusion Plant (Paducah), and Portsmouth Uranium Enrichment Complex (Portsmouth). This report summarizes the findings of this initial numerical scoring evaluation and shows where improvements in the overall ER Pollution Prevention program may be required.

This initial Pollution Prevention Program RI evaluation indicated a need for improvement in each performance category. This conclusion was based on the average composite of all of the combined performance measures for the ER site programs at ORNL, the Oak Ridge Y-12 Plant, K-25, Paducah, and Portsmouth.

This report identifies a number of recommendations that, if implemented, would help to improve site-performance measures. The continued development of the NSS will support generators in maximizing their PP/WM efforts. Further refinements of the NSS, as applicable to RI projects, will be made as the generators become more familiar with the program and suggest comments and/or recommendations for improvement.

1. INTRODUCTION

The Department of Energy (DOE) has established a Pollution Prevention/Waste Minimization (PP/WM) Policy in response to the Pollution Prevention Act (PPA) of 1990. DOE also prepared a Waste Minimization Crosscut Plan to provide a DOE-wide planning framework for effective coordination of all DOE PP/WM activities. Martin Marietta Energy Systems, Inc., has prepared a PP/WM Awareness Program based on the 1990 PPA, DOE's PP/WM Policy, and DOE Crosscut Plan. As a part of its program, Energy Systems has initiated development of a numerical scoring system (NSS) to aid in evaluation of the effectiveness of PP/WM activities.

This report identifies the purpose, scope, and drivers for completing the scoring of ongoing and near-term PP/WM activities for remedial investigation (RI) projects at facilities managed for DOE by Energy Systems.

1.1 PURPOSE

The central purpose of the DOE and Energy Systems pollution prevention efforts is to reduce waste generated by the DOE facilities managed and maintained by Energy Systems. This should be accomplished through acceptable programmatic and regulatory standards within the constraints of available public funding. The creation of drilling cuttings, decontamination fluids, residual samples, and other investigation-derived waste (IDW) is the result of the investigations of previous contamination. A key objective of the Environmental Restoration (ER) Pollution Prevention Program is to establish performance measures to be implemented by the generator by means of a numerical score. As generators improve their scores, waste generation rates will be tracked to determine correlations in performance measurement and waste reduction.

1.2 SCOPE

Four basic steps are required for developing an RI scoring system:

- Identify ongoing and near-term RI activities and the wastes generated during these activities.
- Identify key steps and documentation in the RI phase.
- Produce checklist for generations for scoring.
- Develop objective scoring algorithms for RI waste-stream questions developed in the first phase of the NSS project. The algorithm will be unique for each question relative to the volume of waste reduced. Scores will be computed for generators identified during the initial phase of development at the Oak Ridge National Laboratory (ORNL), the Oak Ridge K-25 Site, the Oak Ridge Y-12 Plant, the Portsmouth Uranium Enrichment

Complex (Portsmouth), the Paducah Gaseous Diffusion Plant (Paducah), and Clinch River/Off-Site.

1.2 DRIVERS

The major regulatory drivers that impact PP/WM are discussed in Table 1.1, Regulatory guidance.

Table 1. Regulatory guidance

Key driver	Key provisions	Applicable regulatory agency
Pollution Prevention Act	<ul style="list-style-type: none"> combines the requirements of several acts with the aim of coordinating activities to minimize the generation and disposal of hazardous wastes into the environment. ensures efforts are undertaken to reduce the impact on public health and all environmental media. plans to conduct multimedia inspections to determine whether generators are considering multimedia impacts in the implementation of PP/WM programs. requires that hazardous waste generators establish a program to reduce the volume and toxicity of waste to the degree determined, by the generator, to be "economically practicable." requires submittal of biennial reports to EPA identifying efforts to reduce the volume and toxicity of wastes generated and the changes in volume and toxicity actually achieved during the year. submit waste minimization results with their annual toxic chemical release inventories. incorporates the Clean Air Act, Clean Water Act, Toxic Substance Control Act, Hazardous and Solid Waste Amendments. determines cleanup standards, schedules, and evaluates remedies for response to cleanup of releases to hazardous substances. PP will be facilitated through the application of IDW management options that target areas of concern in RI phases. document all PP plans aimed at reducing waste at the source whenever feasible. This applies to hazardous and mixed waste. 	Environmental Protection Agency (EPA)
Resource Conservation and Recovery Act (RCRA)		EPA
Comprehensive Environmental Response, Compensation and Liability Act and the Superfund Amendments and Reauthorization Act		EPA
Land Disposal Restrictions Federal Facilities Compliance Act		EPA

Table 1. (continued)

Key driver	Key provisions	Applicable regulatory agency
Tennessee Hazardous Waste Reduction Act	<ul style="list-style-type: none"> document all PP plans aimed at reducing waste at the source whenever feasible. This applies to hazardous and mixed waste. 	State of Tennessee
DOE Waste Reduction Policy	<ul style="list-style-type: none"> consolidates DOE Order 5400.1, 5400.3, 5820.2A. requires all DOE program offices and field offices to "institute a waste reduction policy to the total amount of waste that is generated and disposed of by DOE operating facilities through waste minimization." requires waste reduction to be a "prime consideration" in research activities, process design, and facility design and operation. 	DOE

2. METHODOLOGY

The methodology for scoring the pollution prevention activities for the RI projects from all six ER program sites (ORNL, the K-25 Site, the Oak Ridge Y-12 Plant, Paducah, Portsmouth, and Clinch River/Off-Site) are presented in Fig. 1. The diagram is divided into the following three main steps:

1. Development of questionnaire and scoring mechanism.
2. Listing and selecting RI projects to be scored.
3. Application of questionnaire and scoring selected RI projects.

Using the developed RI checklist and the fully developed NSS, each site generator with a scheduled RI in FY 1993 or FY 1994 was asked to complete the questionnaires. The RI questions were grouped into six performance measures: training, self assessment, field implementation, documentation, technology transfer, and planning. The answers obtained from the generators were scored using the algorithms developed in the NSS.

The generators numerical scores were based on a composite of general questions and waste stream questions. The general questions were made up of yes/no and multiple choice questions. The waste stream questions were made up of yes/no and fill in the blank questions. More details of the scoring methodology are presented in note number 16 of Fig. 1.

Fig. 1. Logic diagram

Notes pertaining to Fig. 1 (Logic diagrams for scoring RI projects):

1. Quality Assurance Standards for Nuclear Facilities (NQA-1) elements are as follows:

- organization
- quality assurance program
- design control
- procurement document control
- instructions, procedures, and drawings
- document control
- control of purchased items and services
- identification and control of items
- control of process
- inspection
- test control
- control of measuring and test equipment
- handling, storage, and shipping
- inspection, test, and operating status
- control of nonconforming items
- corrective action
- quality assurance records
- audits

2. EPA pollution prevention elements are as follows:

- top management support
- waste minimization and pollution prevention awareness
- explicit program scope, objectives, and numerical goals
- periodic waste minimization assessments/audits
- accurate cost accounting
- accurate waste accounting
- technology transfer
- program evaluation

3. The Generator Evaluation Score questionnaire consists of general questions that apply to every phase of the program and every waste stream that has been generated. These questions were developed from the combination of elements in the EPA pollution prevention program with the elements of NQA-1.

4. The volume reduction index is designed to measure the reduction in volume achieved by a given waste minimization technique applied to a subject waste stream. This index will be used in a future RI iteration. The volume reduction index r_{ij} for a waste-stream j and reduction technique i is represented mathematically below:

$$r_{ij} = \frac{e_{ij} \times P_{ij}}{10}$$

where

r_{ij} = reduction index for waste stream j using the reduction technique i ; it has a maximum value of 10,

e_{ij} = effectiveness of reduction technique i on waste stream j ; it has a maximum value of 10,

P_{ij} = probability index of reduction technique i being implemented for waste stream j ; it has a value range from 0 to 10,

i = reduction technique,

j = waste stream.

5. The relative ranking index is a measure of the desirability of the implemented minimization efforts relative to the pollution prevention hierarchy:

- source control,
- recycling, and
- "end of pipe" treatment.

This index was used in the generator numerical scores. The relative ranking index for a given technique and waste stream may be defined by the product of the pollution prevention hierarchy (Z_{ij}) factor times its effectiveness (e_{ij}). This is represented by the following equation.

$$h_{ij} = \frac{e_{ij} Z_{ij}}{10}$$

where

e_{ij} = effectiveness of reduction technique i on waste stream j ; it has a maximum value of 10,

Z_i = pollution prevention hierarchy index of reduction technique i ; it does not depend on waste stream and has a maximum value of 10,

h_{ij} = relative ranking index of the reduction technique i on waste stream j ; it has a maximum value of 10.

The following are examples for calculating the relative ranking index h_{ij}

- a. To calculate the relative ranking index for
Reduction technique: reduce number of borings ($i=1$)
Waste stream: soil cutting ($j=1$)

Using best engineering judgment, the value of e_{ii} (effectiveness in volume reduction) and Z_i (hierarchy index) are 10 and 10, respectively.

Calculate:

$$\begin{aligned} h_{ii} &= \frac{e_{ii} Z_i}{10} \\ &= \frac{(10)(10)}{10} \\ &= 10 \end{aligned}$$

so the relative ranking index is 10.

- b. To calculate the relative ranking index for
Reduction technique: limit changes of PPE ($i=5$)
Waste stream: PPE ($j=2$)

Using best engineering judgment, the value of e_{52} and Z_5 are 5 and 10, respectively.

Calculate:

$$\begin{aligned} h_{52} &= \frac{e_{52} Z_5}{10} \\ &= \frac{(5)(10)}{10} \\ &= 5 \end{aligned}$$

so the relative ranking index is 5.

6. The cost benefit index is the index that provides a cost/benefit factor that will enable the waste generator to assess the economic effectiveness of a particular waste minimization technique. This index will be used in the future iteration of RI projects. The cost benefit index is the ratio of overall cost saving from implementation of waste minimization to the overall cost of managing the waste without minimization efforts. This cost benefit index for a waste stream j can be represented as follows:

$$C_{js} = \frac{C_j - C_{jm}}{C_j}$$

where

C_{js} = cost benefit index for waste stream j ; it has a maximum value of 1,

C_j = overall cost of managing the waste without minimization for waste stream j ,

C_{jm} = cost of managing the waste with minimization for waste stream j .

7. Data quality objectives (DQOs) are qualitative and quantitative statements that specify the quality of the data required to support the decision during remedial response activities. DQOs are determined based on the end uses of the data to be collected. The level of detail and data quality needed will vary based on the intended use of the data.

8. The ORNL ER Program consists of the following projects:

Waste area group (WAG) 2
WAG 4
WAG 5
WAG 10

9. The K-25 Site ER Program consists of the following projects:

K-1070-C/D Burial Ground Phase 2 RI
K-1220-NE Underground Storage Tank

10. The Oak Ridge Y-12 Plant ER Program consists of the following projects:

Chestnut Ridge Operable Unit (OU) 2 Filled Coal Ash
OU 3/Bldg. 81-10
Bear Creek OU 2
Bear Creek OU 4 Groundwater
Upper East Fork Poplar Creek (UEFPC) OU 2
UEFPC RCRA Closure
Study Area
Chestnut Ridge OU 1 Security Pits/Groundwater

11. The Paducah ER Program consists of the following projects:

WAGs 1, 7
WAGs 2, 3, 4
WAGs 5, 11
WAGs 8, 9
WAGs 10, 16
WAGs 12, 15
WAGs 13
WAGs 17
WAGs 18
WAGs 21

12. The Portsmouth ER Program consists of the following project:

Quadrant IV RCRA facility investigation (RFI)

13. The Clinch River/Off-Site ER Program consists of the following projects:

Clinch River/Off-Site

South Campus, Oak Ridge Associated Universities (ORAU)

14. The six performance measurements categories are as follows:

Training

Self-assessment audits

Field implementation

Documentation

Technology transfer

Planning

15. The report has the following format:

Executive Summary

1. Introduction
2. Methodology
3. Data Summary
4. Performance Measure
5. Conclusions/Recommendation

16. Methodology for scoring the questionnaires:

Questionnaires are designed for each category of performance measures. Answers from the waste generators are compiled and analyzed to produce scores for each measure.

For each performance measure category, the questionnaire is composed of either one or both of the following parts:

- a. The general questions, which are designed for the program level's activities, are scored based on the following:

For yes/no questions,

1. any answer with yes will receive a score of one point;
2. any answer with no or without an answer will receive zero points.

For multiple choice questions,

1. an assigned score from zero to four points will be given depending on the specific answer;
2. an unanswered multiple choice question will be assigned zero points.

b. The waste stream questions, which include project pollution prevention activities associated with the waste reduction techniques for each applicable waste stream, are scored based on the following:

1. Only yes/no questions will be scored in this section. The fill-in-the-blank questions are not scored at this time.
2. Positive answers that apply to any reduction technique will result in an assigned relative ranking index. The relative ranking index, as indicated in Fig. 1, note 4, calculates the score of the waste stream questions. Engineering judgment is used to preassign effectiveness value and pollution prevention hierarchy index for every waste stream and every waste reduction technique. The product of the effectiveness value times the hierarchy index is the relative ranking index of each individual waste reduction technique within each waste stream.

The composite relative ranking index for each target waste stream is calculated based on the average of all the relative ranking indices for each reduction technique. The overall relative ranking index for all the waste streams is calculated based on the average of all the relative ranking indices for each waste stream.

3. If there is no positive answer to any reduction technique in an applicable waste stream, the relative ranking index for that particular waste stream will be zero.

All the scores and indices are converted to a 100-point system for performance measures that have only the general questions or the waste stream questions; the score will be reflected only on one type of question. For performance measures that have both general questions and waste stream questions, the score will reflect 50% from general questions and 50% from the waste stream questions.

3. DATA SUMMARY

As described in the preceding sections, the pollution prevention activities of several projects in the RI phase were evaluated using the fully developed questionnaire. Not all of the questions in the checklist are used to score the pollution prevention programs of the projects. The majority of the questions used to evaluate the performance of the waste generators are yes/no questions. A graphical representation of the response to one of the questions is shown for illustration purposes, in Fig. 2. Note that the question in Fig. 3 can be answered in three different ways: yes, no, or the question can be left blank.

A second type of question used to evaluate the generators is a multiple choice question. As in the previous example, the distribution of answers is given in Fig. 3 for illustration purposes only. Again, the list of possible answers is augmented by leaving the question blank.

The responses to the yes/no questions and multiple choice questions, expressed in percentages, are given in Tables 2 through 27. The tables are arranged according to the following distribution:

• Training	Table 2
• Self-assessment audits	Tables 3 through 8
• Field implementation	Table 9 through 11
• Documentation	Tables 12 through 17
• Technology transfer	Tables 18 and 19
• Planning	Tables 20 through 27

All of the questions are not presented in the tables. Specifically, questions that could have multiple answers and fill-in-the-blank questions were not included.

Fig. 2 A graphical representation of the response to a yes/no question.

Fig. 3 An example of the distribution of the answers.

Table 2. Percentages of yes/no responses to training question 1

Question	Yes (%)	No (%)	Blank (%)
Have you or those that report to you been trained for the following items?			
Site general employee and radiation	100	0	0
24 h minimum initial Hazardous Waste Operations and Emergency Response with 8 h refresher annually	100	0	0
RCRA hazardous waste generator	89	11	0
PP/WM	46	54	0

Table 3. Percentages of yes/no responses to self-assessment audits question 1

Question	Yes (%)	No (%)	Blank (%)
Did you or those that report to you have your pollution prevention program audited in the last 12 months?	0	100	0
Did you or those that report to you have your pollution prevention program audited in the following manner?			
A periodic schedule for audit of activities	0	100	0
The audit is performed by those who have the direct responsibility for performing the activities being audited	0	100	0
The audit is performed by those who do not have the direct responsibility for performing the activities being audited	0	100	0
The audit is always reviewed by responsible management	0	100	0
Follow-up action is always taken as a result of the audit	0	100	0

Table 4. Percentages of yes/no responses to self-assessment audits question 2

Question	Yes (%)	No (%)	Blank (%)
Have you or those that report to you initiated an assessment of your waste streams to reduce or prevent waste generation?	50	46	4
Have the following project waste assessment elements been performed?			
The review of Environmental Restoration Waste Management (ERWM) operations and waste management issues and targeted work sites that should be assessed	43	50	7
The development of flow diagrams and material balances for each targeted work site	32	64	4
The identification of pollution prevention opportunities and projects that address those opportunities	46	50	4
The evaluation and ranking of projects into a coordinated facility long-range plan	43	50	7

Table 5. Percentages of yes/no responses to self-assessment audits question 3

Question	Yes (%)	No (%)	Blank (%)
Have you or those that report to you evaluated your pollution prevention program to your numerical goal criteria in the last 12 months?	0	57	43
Are the following criteria used to evaluate your pollution prevention program?	0	57	43
The number of numerical goals achieved	0	57	43
The number of cost reductions achieved	0	57	43
The number of noncompliances cited	0	57	43
The number of new technologies integrated	0	57	43

Table 6. Percentages of yes/no responses to self-assessment audits question 4

Question	Yes (%)	No (%)	Blank (%)
Do you or those that report to you implement mechanisms for quality improvement in pollution prevention to prevent noncompliance?	75	21	4

Table 7. Percentages of yes/no responses to self-assessment audits question 5

Question	Yes (%)	No (%)	Blank (%)
Is technology information available for comparison from other sites for pollution prevention assessment?			
Parameters and results of a material or RI/feasibility studies (FS) activity	46	54	0
The impact of the project of implementing a new technology	11	89	0
The RI/FS activities and materials currently used	82	18	0
RI/FS activities and materials under consideration	43	57	0

Table 8. Response expressed in percentages for multiple choice question 4 pertaining to self-assessment audits

Question	A (%)	B (%)	C (%)	D (%)	E (%)	Blank (%)
How often does management assess the Pollution Prevention Program to quality assure that it is adequate and is effectively implemented?	36	36	0	0	0	29

A = Never

B = No regular schedule for assessing the Pollution Prevention Program, maybe every once in a while.

C = Has regular schedule for assessing the Pollution Prevention Program and is done every 2 years.

D = Has regular schedule for assessing the Pollution Prevention Program and is done every year.

E = Has regular schedule for assessing the Pollution Prevention Program and is done at least every 6 months.

Table 9. Percentages of yes/no responses to field implementation question 1

Question	Yes (%)	No (%)	Blank (%)
Have you or those that report to you labeled your waste containers and keep records of each container done on-site?	57	36	7

Table 10. Responses expressed in percentages for the multiple choice portion of field implementation question 1

Question	A (%)	B (%)	C (%)	D (%)	E (%)	Blank (%)
How are labeling of containers and recording of waste in each container done on-site?	0	0	0	18	39	43

A = Containers are not always marked and no recording of waste type, amount, or constituent of waste is done.

B = Containers are always marked according to the judgment of site workers. Records of waste type, amount, and constituent of waste do not always exist.

C = Containers are always marked according to the judgment of site workers. Records of waste type, amounts, and constituent of waste always match the container.

D = Containers are always marked according to the instruction or procedure for labeling. Recording information contains waste type, amounts, and constituent of waste and always match each container.

E = Containers are always marked according to instruction or procedure for labeling. Recorded information contains waste type, amount, and constituent of waste and always match each container. All recorded information can be tied directly to a database.

Table 11. Responses expressed in percentages for multiple choice question 2 pertaining to field implementation

Question	A (%)	B (%)	C (%)	D (%)	E (%)	Blank (%)
Do you or those that report to you know who handles the waste you generate?	21	11	4	0	50	14

A = It is not known who handles your waste.

B = Your site waste management organization handles your waste.

C = Your site waste management organization handles your waste and provides a methodology to track it.

D = Your site management organization handles your waste and provides you some of the data to meet your reporting requirements.

E = Your site waste management organization handles your waste and provides you all of the data to meet your reporting requirements.

Table 12. Percentages of yes/no responses to documentation question 1

Question	Yes (%)	No (%)	Blank (%)
Do you have an ERWM PP/WM Program Plan on site?	89	11	0
Does pollution prevention at your site have full management support including the following?			
A written ERWM policy statement from top management	82	14	4
A written ERWM PP/WM program plan to ensure program objectives and goals are met	11	86	4
Budgeted line items that are dedicated to pollution prevention programs	43	54	4
An ERWM organization chart	82	11	7

Table 13. Percentages of yes/no responses to documentation question 2

Question	Yes (%)	No (%)	Blank (%)
Does your pollution prevention program have a statement of scope and objectives distributed to project personnel?	11	86	4
Does your pollution prevention program have explicit scope, objectives, and numerical goals as follows?			
It has a statement of pollution prevention scope and objectives developed and distributed to project personnel	11	86	4
It has a statement of pollution prevention scope and objectives developed and distributed to all contractor personnel	11	86	4
Specific numerical goals for pollution prevention for each project waste stream are set and distributed/displayed to all project personnel	0	96	4
Specific numerical goals for pollution prevention for each project waste stream are set and distributed/displayed to all contractor personnel	0	96	4

Table 14. Percentages of yes/no responses to documentation question 3

Question	Yes (%)	No (%)	Blank (%)
Do you or those that report to you initiate work/waste management plan(s) for your projects that are scheduled to start within 180 days or less?	89	7	4
Have you or those that report to you incorporated PP/WM in your work/waste management plans for projects scheduled to start within 180 days or less?			
PP/WM is not incorporated in any of the project work/waste management plan(s)	0	86	14
There is a section on PP/WM incorporated in at minimum one of the project work/waste management plans	75	14	11
There is a section on PP/WM in all of the project work/waste management plans	43	43	14
There is a section on PP/WM in all project work/waste management plans. Each section discusses at minimum of three techniques to reduce or prevent waste generation	36	54	11

Table 15. Percentages of yes/no responses to documentation question 4

Question	Yes (%)	No (%)	Blank (%)
Do you or those that report to you have the following data relating to your site operations and waste streams so that pollution prevention opportunities can be identified?			
Supply/distribution records (i.e., chemical inventory, chain of custody, and waste drum tracking)	61	43	6
Maintenance records (i.e., inspection and equipment)	50	43	7
Supervision records (i.e., Quality Assurance/Quality Control audits, noncompliance, and personnel training)	89	7	4
Required permits and records (i.e., Clean Air Act of 1990, National Pollutant Discharge Elimination System, and RCRA monitoring; RCRA accumulation facility/inventories and manifests; Comprehensive Environmental Response, Compensation, and Liability Act of 1980 reportable quantity releases; and sample/waste analyses)	79	11	11
ERWM Program documentation (i.e., all work/waste management plans for projects scheduled to begin within 180 days)	54	39	7
Design information (i.e., process flow diagrams and material balances)	79	11	11

Table 15 (continued)

Question	Yes (%)	No (%)	Blank (%)
Environmental information and reporting (i.e., sample/waste analyses, RCRA/Tennessee/annual report, EPA biannual report, and PPA report)	96	0	4
Raw material/site information (i.e., material safety data sheets, contractor data logs, site operating procedures, and project schedules and milestones)	100	0	0
Economic information (i.e., waste treatment, disposal, operating, maintenance, and departmental and pollution prevention implementation costs)	71	25	4

Table 16. Percentages of yes/no responses to documentation question 5

Question	Yes (%)	No (%)	Blank (%)
Do you or those that report to you have cost, schedule, and program controls specific to your ERWM program activities?	57	36	7
What kind of waste accounting is performed?			
Are operating cost records kept?	50	43	7
Are treatment cost records kept?	39	54	7
Are disposal cost records kept?	39	54	7
Are maintenance cost records kept?	46	46	7
Are life-cycle cost records kept?	46	46	7
Are costs to implement pollution prevention activities kept?	0	61	39

Table 17. Percentages of yes/no responses to documentation question 6

Question	Yes (%)	No (%)	Blank (%)
Do you or those that report to you keep and organize records from pollution prevention activities for quality assurance purposes?	7	89	4
Are your records from pollution prevention activities retained and organized in the following manner?			
Records that furnish documentary evidence from all pollution prevention activities retained and organized	7	89	4
Records are well organized and are easy to assess	7	89	4
Records are protected against damage, deterioration, or loss	7	89	4
Requirements and responsibilities for record transmittal, distribution, retention, maintenance, and disposition are established and documented	7	89	4

Table 18. Percentages of yes/no responses to question 1 pertaining to technology transfer for soils

Questions	Yes (%)	No (%)	Blank (%)
Could some exploratory borings be substituted by direct push technology?	16	40	44

Table 19. Percentages of yes/no responses questions 2, 3, and 4 pertaining to technology transfer for sediments/sludges

Questions	Yes (%)	No (%)	Blank (%)
Could some exploratory borings be substituted by direct push technology?	16	40	44
Could decon liquid be minimized by using evaporate tanks?	39	30	30
Could decon liquid be treated and re-used?	65	13	22

Table 20. Percentages of yes/no responses pertaining to planning for soils questions 2, 4, 5, 7, 9, and 11

Question	Yes (%)	No (%)	Blank (%)
Could the diameter of the exploratory boring be reduced?	24	44	28
Could the number of exploratory borings be decreased?	0	64	36
Could some exploratory borings be substituted by direct push technology?	16	40	44
Can the total depth of the borings be decreased?	4	56	40
Can the size and number of pits be reduced?	0	4	96
Can the number of soil samples be reduced?	4	40	56

Table 21. Percentages of yes/no responses pertaining to planning for sediments/sludges questions 13, 15, 16, 18, 20, and 21

Question	Yes (%)	No (%)	Blank (%)
Could the diameter of the exploratory boring be reduced?	0	43	57
Could the number of exploratory borings be decreased?	0	71	29
Could some exploratory borings be substituted by direct push technology?	43	14	43
Can the total depth of the borings be decreased?	0	57	43
Can the size and number of pits be reduced?	0	0	100
Can the number of soil samples be reduced?	0	57	43

Table 22. Percentages of yes/no responses pertaining to planning for surface water, groundwater, and drilling fluids questions 24, 26, and 29

Question	Yes (%)	No (%)	Blank (%)
Could the number of location points/monitoring wells be reduced?	7	60	33
Could the diameter of the monitoring wells be reduced?	17	57	26
Could the number and/or frequency of surface water and/or groundwater samples be reduced?	6	39	56

**Table 23. Percentages of yes/no responses to question 31
pertaining to planning for decontamination liquids**

Question	Yes (%)	No (%)	Blank (%)
Could a substantial amount of decon liquid be prevented by:			
Cleaning only augers and tools instead of the complete rig?	57	22	22
Using dedicated pumps/bailers that are left in place?	41	30	30
Using disposable sampling equipment?	65	13	22
Cleaning rig parts, augers, split spoons, bailers, hand augers, spoons, bowls, shovels, etc., by cleaning with a low-volume sprayer (after removal of the larger pieces of material) instead of buckets and brushes?	74	9	17

**Table 24. Percentages of yes/no responses to questions 33 and 34
pertaining to planning for personal protective equipment (PPE)**

Question	Yes (%)	No (%)	Blank (%)
Could a substantial percentage of PPE be prevented if the level of protection was reduced?	61	30	9
Could a percentage of PPE be prevented by keeping changes to a minimum?	70	22	9

Table 25. Percentages of yes/no responses to questions 35 and 36 pertaining to planning for soils

Question	Yes (%)	No (%)	Blank (%)
Could a percentage be returned to the boring, pit, or source?	64	8	28
Can a percentage be spread around the boring, pit, or source?	48	20	32

**Table 26. Percentages of yes/no responses to questions 37 and 38
pertaining to planning for sediments/sludges**

Question	Yes (%)	No (%)	Blank (%)
Could a percentage be returned to the boring, pit, or source?	43	29	29
Can a percentage be spread around the boring, pit, or source?	43	29	29

**Table 27. Percentages of yes/no responses to question 40 pertaining to planning
for surface water, groundwater, and drilling fluids**

Question	Yes (%)	No (%)	Blank (%)
Can a percentage be spread around the boring, pit, or source?	22	57	22

4. PERFORMANCE MEASURE

4.1 OVERALL PERFORMANCE MEASURE

Each of the ER programs has been scored based on six categories of performance measures. These six categories are training, self-assessment auditing, field implementation, documentation, technology transfer, and planning.

Six ER programs and 28 projects were included in this RI NSS scoring. The lists of programs and associated projects were presented in Sect. 2.

The following is a summary of ER Program findings based on each performance measure category. The maximum score for any category is 100.

The performance measure rating ranges are:

100	perfect score
90-99	excellent
70-89	exceed the requirements
50-69	meet the requirements
25-49	need improvement
0-24	corrective action necessary

4.1.1 Training

All of the ER programs did well in this performance category with an overall rating exceeding the requirements (Fig. 4). It should be noted that the Y-12 and Portsmouth site programs received the best performance score ratings.

Fig. 4. Training scores by facility.

4.1.2 Self-Assessment Audit

All ER site programs did poorly in this category, with an overall rating corrective action needed (Fig. 5). The Oak Ridge Y-12 Plant was the only exception with a need improvement performance rating. This reflects the fact that self-assessment audits in the ER Pollution Prevention Program have not yet been addressed.

Fig. 5. Self-assessment scores by facility.

4.1.3 Field Implementation

All ER programs received a need improvement rating for this performance category (Fig. 6). This is primarily attributed to program managers not being intimately involved with the details of waste handling and waste management.

Fig. 6. Field implementation scores by facility.

4.1.4 Documentation

Most of the ER site programs received a need improvement rating for this performance category (Fig. 7). Only the Y-12 and K-25 ER programs met the numerical performance requirements for this category. Documentation related to pollution prevention activities in the ER Program is weak. It was discovered that there is little or no flow of waste minimization documentation in the RI work plans.

Fig. 7. Documentation scores by facility.

4.1.5 Technology Transfer

The majority of ER site programs received a need improvement or corrective action necessary rating in this performance category (Fig. 8). Only the K-25 and Portsmouth sites met the performance requirements. The ORNL ER Program received a need improvement rating. The Oak Ridge Y-12 Plant and Paducah sites received corrective action necessary ratings. At the time of this survey, RIs were still in the early stages when minimal characterization information, which is critical in prescribing proper technology, is available.

4.1.6 Planning

The majority of ER site programs received need improvement ratings in this performance category (Fig. 9). Only the Paducah site met the performance requirements. The performance rating in this category will improve when the data from fill-in-the-blank questions have been further analyzed.

4.2 PERFORMANCE MEASURES FOR EACH ER PROGRAM

The following sections provide a summary of the findings from performance measure categories based on each ER program.

Fig. 8. Technology transfer scores by facility.

Fig. 9. Planning scores by facility.

4.2.1 ORNL ER Program

The ORNL ER Program exceeded the requirements in the training category (Fig. 10). This program needs moderate improvement in the field implementation, documentation, planning, and technology transfer categories. The program needs corrective action in the self-assessment audit category.

4.2.2 K-25 Site ER Program

The K-25 Site ER Program exceeded the requirements in the training category (Fig. 11). This program needs improvement in the field implementation and planning categories. The program needs corrective action in the self-assessment audit category.

Fig. 10. ORNL scores by category.

Fig. 11. K-25 scores by category.

4.2.3 Y-12 Plant ER Program

The Oak Ridge Y-12 Plant ER Program achieved a perfect score in the training category (Fig. 12). This program needs improvement in the field implementation and self-assessment audit categories. The program needs corrective action in the technology transfer and planning categories. However, four of nine projects from the Oak Ridge Y-12 Plant ER Program did not supply any waste stream and waste reduction information because these RI projects are at the very early stage and their work plans are not available. It is very likely that the Oak Ridge Y-12 Plant ER Program will score higher in the field implementation, technology transfer, and planning categories when waste stream and waste reduction information for the four projects are developed and become available.

Fig. 12. Y-12 Plant scores by category.

4.2.4 Clinch River/Off-Site ER Program

The Clinch River/Off-Site ER Program exceeded the requirements in the training category (Fig. 13). This program needs improvement in the documentation and field implementation categories. The program needs corrective action in the self-assessment audit, technology transfer, and planning categories.

Fig. 13. Clinch River/Off-Site scores by category.

4.2.5 Paducah ER Program

The Paducah ER Program exceeded the requirements in the training category (Fig. 14). This program needs improvement in the documentation category. The program needs corrective action in the self-assessment audit, technology, and field implementation categories.

Fig. 14. Paducah scores by category.

4.2.6 Portsmouth ER Program

The Portsmouth ER Program achieved perfect scores in the training category (Fig. 15). The program needs improvement in the field implementation, documentation, and planning categories. The program needs corrective action in the self-assessment audit category.

Fig. 15. Portsmouth scores by category.

5. CONCLUSIONS/RECOMMENDATIONS

In conclusion, the numerical scoring of pollution prevention initiatives for RI projects establishes a baseline for future quantitative performance measurement. The performance measurement categories of training, self-assessment audits, field implementation, documentation, technology transfer, and planning have been determined to accurately reflect the status of pollution prevention for the ER Program. This numerical scoring system, if executed properly, will not only reduce IDW generation but will also minimize multimedia transfers to the environment. Other benefits include ease of implementation, establishment of performance indicators, and cost savings resulting as waste generators train and assess themselves.

In summary, the ER Program received an overall need improvement performance rating. This rating was based on an average composite of all the combined performance measures for the ER site programs at ORNL, the Y-12 Plant, the K-25 Site, Paducah, Portsmouth, and Clinch River/Off-Site.

The ER Pollution Prevention Program has identified a number of recommendations to improve the performance measures for the ER Program sites. The overall key strategy for planning and implementing the PP/WM is the continued development of the NSS to support generators in conducting process waste assessments (PWA), PP/WM planning, identifying and correcting deficiencies, and setting quantitative goals to measure performance.

The recommendations for improvement for each ER program are as follows:

- A follow up on the NSS of RI projects is recommended in the next 12-18 months. The purpose for this iteration is to assess the level of improvement on each program when all the pollution prevention elements have been fully implemented. Also other parameters that can be quantitatively measured, such as the volume reduction index, should be included in the next RI NSS scoring.
- Each ER Program site should set a minimum numerical score as a target for each performance measure within a certain suitable time frame as part of their site Performance Evaluation Criteria milestones.
- Lesson learned from this iteration should be used in future numerical scoring of waste generators.
- Improvement is needed for the performance measures of the training and technology transfer categories of the questionnaire. These categories will need to have an adequate number of questions, which includes all the activities, to ensure that scores in these categories will be represented more accurately. Conversely, some categories such as self assessment need fewer questions.
- PWA methodology and documentation should be incorporated into the NSS to train and assist generators in reducing waste and multimedia transfers. A good starting point would be performing a source reduction/zero discharge pilot study in targeting RI IDW projects. All waste assessment opportunity projects should be prioritized by ease of implementation and potential cost-benefit analysis.

- In an effort to get better cooperation from all ER Program and project personnel, the following items are recommended:
 - Seek input from the waste generators in the early planning stage. Let the waste generators review the questionnaire, follow up on any comment received from them, and answer any question that they may have before actually scoring them.
 - Emphasize that the NSS RI scoring is important for the ER pollution prevention program and will be able to assist them improving their work performance.
 - Improve communication between ER personnel and plant management personnel to better facilitate pollution prevention activities.
- It is imperative that the proper incentives be in place for the ER Program sites to provide the proper motivation for generators to complete the numerical scoring, process waste assessments, and self audits.
- Show how performance measures are tracked with project and actual waste generation.
- In the future, consideration will be given to the waste generators who have done all the minimization up front before scoring the NSS, so the scoring mechanism will not penalize them.
- All the indices not addressed in this scoring will be used in a future iteration.

DISTRIBUTION

1. B. D. Barkenbus	25. S. J. Kondracki
2. D. T. Bell	26. E. A. Krispin
3. S. C. Bieniek	27. C. J. Marshall
4. H. Boston	28-30. D. M. Matteo
5. K. M. Cash	31. S. R. Michaud
6. B. J. Clayton	32. J. R. Michel
7. J. S. Colley	33. B. H. Miller
8. A. L. Cook	34. T. J. Newsom
9. K. W. Cook	35-36. P. T. Owen
10. R. B. Cook	37. B. E. Phifer
11. D. G. Cope	38. T. E. Post
12. M. F. P. DeLozier	39. G. E. Rymer
13. C. H. Estes	40. E. M. Schilling
14. D. J. Fennell	41. M. L. Solenbenger
15. T. Fletcher	42. T. D. Taylor
16. C. D. Goins	43. D. M. Ulrich
17. J. T. Grumski	44. A. E. Walzer
18. P. J. Halsey	45. D. R. Watkins
19. C. J. Hammonds	46. R. K. White
20. E. S. Harrington	47. A. S. Will
21. J. A. Hodgins	48. Central Research Library
22. C. G. Hudson	49-53. ER Document Management Center
23. T. W. Joseph	54. ORNL Laboratory Records
24. B. L. Kimmel	
55. E. J. Powell, DOE Oak Ridge Field Office, P. O. Box 2001, Oak Ridge, TN 37831-8541	
56-57. R. L. Nace, Branch Chief, Nonenrichment Facilities, Oak Ridge Program Division, Office of Eastern Area Programs, Office of Environmental Restoration, EM-423, Trevion 2, U.S. Department of Energy, Washington, DC 20585	
58-67. L. K. Price, DOE Oak Ridge Field Office, P.O. Box 2001, Oak Ridge, TN 37831-8541	
68. Fred Haywood, Radian Corporation, 120 South Jefferson Circle, Oak Ridge, TN 37830	
69. D. W. Swindle, Radian Corporation, 120 South Jefferson Circle, Oak Ridge, TN 37830	
70-71. H. M. Thron, Chief, Enrichment Facilities, Oak Ridge Program Division, Office of Eastern Area Programs, Office of Environmental Restoration, EM-423, Trevion 2, U.S. Department of Energy, Washington, DC 20585	
72. Ray Bogardus, Roy F. Weston, 704 S. Illinois Avenue, Oak Ridge, TN 37830	
73-74. Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831	

**DATE
FILMED**

8 / 2 / 93

END