AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910

301/587-8202

1 of 1

DECLASSIFIED

DOCUMENT NO.

HW-68499

SERIES AND COPY NO.

DATE _____

February 20, 1961

GENERAL ELECTRIC

HANFORD ATOMIC PRODUCTS OPERATION - RICHLAND, WASHINGTON

TITLE

100-C WATER PLANT

AUTHOR

J. D. AGAR

ISSUING FILE

**COPY
AREA**

100

OTHER OFFICIAL CLASSIFIED INFORMATION

THIS MATERIAL CONTAINS INFORMATION AFFECTING THE NATIONAL DEFENSE OF THE UNITED STATES WITHIN THE MEANING OF THE ESPIONAGE LAWS, TITLE 18, U.S.C., SECS. 793 AND 794, THE TRANSMISSION OR REVELATION OF WHICH IN ANY MANNER TO AN UNAUTHORIZED PERSON IS PROHIBITED BY LAW.

TO IT WHEN NOT IN IT MUST BE STORED IN AN UNLOCKED LOCKER WHEN NOT IN USE TRANS AUTO AND STORAGE AT AIR PLG

ROUTE TO:

PAYROLL NO.

LOCATION

FILE	ROUTE	DATE
100-443888-100	100-443888-100	100-443888-100

SIGNATURE AND DATE

15681	27102		
15681	27102		

Back side Plate	53011	703
-----------------	-------	-----

(Rh Plum)

105

 ME

~~_____~~
Zulf

DECLASSIFIED
MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

54-3000-340 (3-57) AEC-GE RICHLAND, WASH

(CLASSIFICATION)

DECLASSIFIED

HW-68499

This document classified by

D. L. Condotta

This document consists of
10 pages.

100-C WATER PLANT

J. D. Agar

February 20, 1961

Classification Cancelled and Changed To

DECLASSIFIED

By Authority of CG-PR-2

L. A. Snyder, 2-23-94

By Jesse Miley, 3-9-94

Verified By J. K. Hanson, 3-21-94

DISTRIBUTION

1. J. D. Agar
2. L. S. Cave
3. D. L. Condotta
4. N. F. Fifer
5. P. J. Hollifield
6. D. L. Renberger
7. E. R. Rudock
8. D. F. Watson
- 9-14. Extra
15. 300 Area Files
16. Record Center

DECLASSIFIED

DECLASSIFIED

-2-

HW-68499

February 20, 1961

E. R. Rudock
Reactor Modification Design
FACILITIES ENGINEERING SECTION

100-C WATER PLANT

The following report is in answer to your letter, dated October 5, 1960, in which you requested the following items:

1. Separate system curves for each portion of the C Reactor water plant between the river pump house to the top of riser.
2. The existing supply pump performance curves for each station to be plotted with the corresponding system curves.
3. The C Area filter plant capacity be determined and/or verified as to the B-C Area 183 intertie requirements.

SUMMARY

System curves for each portion of the C Area Water Plant were obtained from referenced work and are presented in Figures I, II, and III. Field test data, corroborating the calculated curves, are presented as singular points on the same graphs.

The present maximum capacity of the C Area Filter Plant is about 121,000 gpm with about 118,000 gpm available for use as primary reactor coolant. Proper modifications to the filter effluent piping would increase this available flow to about 180,000 gpm.

Of the 118,000 gpm available for C Reactor use, 10,000 to 12,000 gpm is presently demanded by B Area through the 183 BC intertie. The maximum flow that the intertie line could handle, without reducing the filter capacity of the C Area filters, is about 21,000 gpm.

DISCUSSION

System Pressure Curves

Calculated pressure curves and corresponding field test data are included in Figures I, II and III. The field test data are shown as singular points. The pump supply curves and system demand curves were obtained from reference work as noted.

The field data were obtained during flow conditions corresponding to equilibrium reactor operation. All available pressure and flow instrumentation were used with the exception of the conventional 183 pump discharge pressure gauges. These gauges were replaced with 0-100 psi Heise pressure gauges. It was found that a 10 per cent error was inherent in reading the former pressure gauges because of the low head existing in that portion of the system.

DECLASSIFIED

HW-68499

E. R. Rudock

-3-

February 20, 1961

The test data, as taken, are presented in Tables I, II and III.

During Test I (Table I) various combinations of 181-C pumps were used. The C reactor water system was completely isolated from the B reactor system. This test, therein, does not depict the situation in which water is supplied to the 182-B export system with any pump other than C-14, which is reserved for export flow only.

Only four 183-C pumps could be used during Test II without overflowing the 190-D clearwells. Further test data with the use of five 183-C pumps could be taken during a reactor outage by first dropping the water level in the 190 clearwells prior to the start of the test. It was felt that for the purpose of demonstrating the reliability of the calculated system demand curve, a four pump test would be sufficient.

C-Area Filter Plant

At the present time, with 12 filters in use, the maximum net flow through the C Area filters is about 121,000 gpm. This figure is based upon the following items:

1. An average flow per filter of 10,500 gpm during a filter run.
2. A filter run of 12 hours in length. (The length of a filter run varies between 10 hours and 22 hours depending upon the time of the year or on the condition of the raw water. This time is not necessarily optimum for a filter run⁽³⁾).
3. A backwash flow rate of 17,000 gpm per filter.
4. A backwash run of 10 minutes in length. (This again is not necessarily an optimum time limit and depends somewhat on filter bed consistency and air inclusion in the bed.

A miscellaneous loss of 3 1/2 per cent to 4 per cent of the net filter flow reduces the maximum net flow available to C Reactor to 118,000 gpm. This miscellaneous loss includes such items as filtered water flow to the power house, flow to the 190 and 105 Buildings for bearing coolant, cooling flow for the HCRS, and general area requirements in the form of fire and sanitary water, etc.

The primary limiting factor of filter flow is the filter reservoir effluent piping. The consistency of the filter bed is a potential secondary flow limiting factor. In 1955, prior to the completion of Project CG-558, the depths of the sand and anthrafil portions of the filter bed were changed at all old reactors except C Reactor. The depth of the sand was reduced to 5 inches and the depth of the anthrafil was increased to 25 inches.⁽²⁾⁽⁶⁾ The sand portion of the bed at C reactor was retained at 20 inches and the anthrafil at 7 to 9 inches. It follows that the fine sand layer between the anthrafil and the sand portions of the filter bed at C reactor is of greater thickness than that at the other old reactors. This results in a shorter allowable filter cycle at C reactor and a greater pressure drop across the bed.

DECLASSIFIED

HW-68499

E. R. Rudock

-4-

February 20, 1961

A major revision of the C reactor water plant must include both a revision to the filter effluent piping and to the filter bed consistency. The money for such a revision has not been included in the processing budget and, therefore, must be included in any proposed project such as the C overbore project, which presupposes a major increase in bulk coolant.

The C area filter beds can be revised with the aid of an existing sludge pump. The anthrafil can be pumped from one side of the filter to the other and the excess sand transferred from the exposed side to the ground outside of the 183 building. The anthrafil can then be replaced and additional anthrafil added as needed⁽⁶⁾. The majority of the cost would be labor.

A test was run recently at F reactor in an attempt to establish the maximum filter bed flow capacity. The resulting net flow through the 105 building was 90,000 gpm. The total filtered water flow was larger because of the backwashing, bearing cool- and flow, etc., that was necessary. The corresponding net flow that would be possible through the C area filters, based on comparable cross-section area, is 180,000 gpm.

183-BC Intertie

At the present time, the average filtered water flow rate to 183-B through the 183-BC intertie line is 10,000 to 12,000 gpm. The installation of the intertie line was originally justified by anticipating a reduction of 1,000 gpm through each of the 12 B area filters.

The maximum flow that could be realized through the 1,208 foot long, 30" O.D. intertie line is about 24,000 gpm⁽²⁾. This flow is based on a driving force of 21.5 feet of water corresponding to the difference in height of the filter reservoirs. Since the flow from 183-C to 183-B is by gravity, the maximum flow rate would be reduced by about 3,000 gpm if based on the normal water surface height difference of 17 feet.

For future reference, the flow from 183-C to 183-B could be increased from 12,000 to 21,000 gpm without seriously affecting the 183 C filter capacity. However, increasing the flow above 21,000 gpm would necessitate increasing the normal water surface height in the 183 C filter reservoir. This increase would correspond to a decrease in the filter flow driving force and seriously reduce the filtering efficiency. It is suggested here that for the purpose of assessing future C area water plant demands that the flow to 183-B through the presently installed intertie line be limited to 21,000 gpm.

The cost of enlarging 183-B filter area, in contrast to using the intertie line, was estimated by L. B. Brinkman at over \$1,000,000.⁽²⁾

J. D. Agar

Reactor Design Analysis
Process Design Operation
NPR PROJECT SECTION

JD Agar: cab

DECLASSIFIED

HW-68499

E. R. Rudock

- 5 -

February 20, 1961

BIBLIOGRAPHY

1. HW-40287, "Pressure Flow Characteristics of the 190-105 Systems after Completion of Projects CG-558 and CG-600," L. E. Foster, E. R. Rudock, December 7, 1955.
2. HW-53683, "183-B-C Cross-Tie Justification and Scope," L. B. Brinkman, December 2, 1957.
3. HW-58580, "Existing Reactor Water Plant Study B, C, D, DR, F & H Reactors Interim Report," D. F. Watson, January 19, 1959.
4. HW-65814, "Technical Aspects of 105-C Conversion to Zircaloy-2 Process Tubes and Self-Supported Fuel Elements," C. A. Mansius and D. D. Stepnewski, July 15, 1960.
5. HW-67173, "C Reactor Overbore Study - Interim Report," W. L. Bunch, November 7, 1960.
6. Personal contact with L. Cave and R. W. Pitman, January 27, 1961.

DECLASSIFIED

- 6 -

HW- 68499

February 20, 1961

TABLE I
CAPACITY FLOW CHECK
181-C to 183-C

RIVER ELEVATION: 387.9'

PUMP ROOM ELEVATION: 429'

TEST DATE: 12-16-60

RUN NO.	NUMBER OF PUMPS ***	PUMP(S) DELETED	DISCHARGE PRESSURE			FLOW(1,000 GPM)			HEADER PRESSURE			BASIN HEIGHT
			#3	#8	#13	NORTH	SOUTH	TOTAL	#1	#2	#3	
				(PSIG)						(PSIG)		
1.	10 / (2) Large	#2	46.5	47.0	46.0	60.5	59.2	119.7	14.0	15.0	15.0	16'-8"
2.	11 / (2) Large	None	48.0	48.0	47.0	63.0	62.2	125.2	14.5	15.0	15.0	16'-9"
3.	11 / (1) Large	#10	44.5	45.5	45.0	58.0	57.0	115.0	14.0	14.5	15.0	16'-10"
4.	11 / (0) Large	#1,10	42.0	43.0	42.0	52.5	51.5	104.0	13.5	14.0	14.5	16'-9"

TABLE II
CAPACITY FLOW CHECK
183-C to 190-C

NO. 183 PUMPS: 4

hs*: 6'

NET TOTAL FLOW: 89,670 gpm

TEST DATE: 1-25-61

TIME (HRS.)	183-PUMP DISCHARGE PRESSURE PSIG			
	2	3	5	6
9A	18.5	18.8	17.6	15.3**
10A	18.3	18.5	17.3	17.0
11A	18.5	18.8	17.3	17.4
12N	18.5	18.7	17.2	17.3
1P	18.3	18.5	17.0	17.0

190 CLEARWELL TANK LEVELS (FEET)			
2	3	4	5
30	30	30	30
29.0	30	30	29
28.5	29.7	29.8	28.5
28.0	29.3	29.5	28
27.5	29.0	29.0	27.5

* hs = static suction head

** Obviously an erroneous reading

*** Designates 10 old pumps plus 2 new pumps (See reference 3).

DECLASSIFIED

- 7 **DECLASSIFIED**

HW-68499

February 20, 1961

TABLE III

CAPACITY FLOW CHECK

190-C to 105-C

CORRECTED * REACTOR FLOW: 95,500 gpm

TEST DATE: 10-17-60

<u>190 PUMP DISCHARGE PRESSURE</u>		<u>TORP</u>	
1.	465 psig	A	396 psig
2.	470 psig	B	398 psig
3.	470 psig	C	390 psig
4.	465 psig	D	392 psig
5.	460 psig		
9.	440 psig		
10.	455 psig		
11.	455 psig		
12	450 psig		

* Correction factor determined by recent Draw Down Test.

FIGURE I

181-C to 183-C

Pump Curves
(HW-58580)

System Curves
(HW-58580)

NOTE:

- 1) 11 / 2 denotes 11 old pumps / 2 new pumps
- 2) X, etc. --- test data

DECLASSIFIED

HW-68499

-9-

FIGURE II
183-C to 190-C CLEARWELL

DECLASSIFIED

HW-68499

FIGURE III

190 to 105-C (TOR)

FRICTION PRESSURE DROP ONLY

DATE

FILMED

8/19/94

END