DRAFT

DOE/PC/79654--T5

DE93 011510

**Development of a Retrofit Coal Combustor for
Industrial Applications**

**TECHNICAL PROGRESS REPORT
OCTOBER - DECEMBER 1987**

Prepared For:

**U.S. Department of Energy
Pittsburgh Energy Technology Center**

DOE Contract DE-AC22-87PC79654

By:

MANAGEMENT AND TECHNICAL CONSULTANTS, INC.

P.O. Box 21, Columbia, MD 21045 (301)982-1292 Telex 292354 / MTCI UR

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

PREFACE

A detailed description of the background, technology and application for the development of a Retrofit Coal Combustor for Industrial Applications was provided in the first quarterly report, December 1986 - March 1987, MTCI 79654-101. This material is omitted in this technical progress report.

During this quarter the tandem design configuration unit was tested on a low ash pulverized coal. The test results confirmed operation with strong peak-to-peak pressures and high carbon burn-out efficiencies. These configuration units were dismantled after testing with micronized coal (see third quarterly) and pulverized coal during this period. The refractory material in one of the chambers failed, probably due to improper curing during installation. Design modifications based on performance were incorporated into both the combustors and the facility. The tandem unit was modified and evaluation testing initiated. Performance on 100 percent pulverized coal was similar to performance on micronized coal indicating that the unit has a high degree of tolerance and flexibility for a spectrum of fuel types.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

TABLE OF CONTENTS

	<u>Page</u>
1.0 <u>PROGRAM DESCRIPTION AND WORK STATUS.</u>	1
1.1 PROGRAM DESCRIPTION.	1
1.2 TASK DESCRIPTIONS.	1
1.3 STATUS	3
2.0 <u>TECHNICAL DISCUSSION OF WORK COMPLETED</u> <u>DURING THE REPORTING PERIOD.</u>	5
3.0 <u>PLANNED ACTIVITY FOR THE NEXT PERIOD</u>	24

LIST OF FIGURES

1 PROGRAM LOGIC FOR DEVELOPMENT OF A PULSE COAL COMBUSTOR FOR RETROFIT APPLICATIONS	2
2 PULSE COMBUSTOR CHAMBER A	6
3 PULSE COMBUSTOR CHAMBER B	7
4 OPTIMIZED CONFIGURATION OF INDUSTRIAL TANDEM UNIT	9
5 CARBON BURN-OUT VERSUS CUMULATIVE COAL FEED TIMELINE	17
6 CARBON RETENTION IN SLAGGED COMBUSTOR	18
7 SAMPLE LOCATIONS FOR COMBUSTION SYSTEM	20
8 SCHEMATIC OF CARBON & ASH DISTRIBUTION IN PULSE COMBUSTOR APPARATUS	22

LIST OF TABLES

1 PULVERIZED COAL FUEL ANALYSIS	11
2 PULVERIZED COAL TEST RUN	13
3 SUMMARY OF TEST DATA	14
4 COMPARISON OF CARBON BURN-OUT VALUES FOR DIFFERENT SAMPLE LOCATION AND SLAG REJECTION ASSUMPTIONS	21

SECTION 1.0

PROGRAM DESCRIPTION AND WORK STATUS

1.1 PROGRAM DESCRIPTION

The objective of this phase of the program for the development of a retrofit pulse coal combustor for industrial applications is to design, fabricate, test and evaluate advanced chamber designs at the laboratory scale utilizing several fuels (Task 1). The activities are structured to provide design criteria for scaling up to the pilot-scale level for the demonstration of a pulse combustor fired with coal-water mixtures for industrial boiler and process heater retrofit applications. The program logic is depicted in Figure 1.

The design data and information acquired during Task 1 of the initial phase will be used to develop scale-up design criteria for scaling the laboratory-scale design to pilot-scale including interface requirements for the field demonstration. The scale-up pilot unit design will be sufficiently developed to allow fabrication of the unit for testing in the existing test facility upon DOE exercising its option for the follow-on activities of this program. These follow-on activities will include the fabrication, test and engineering evaluation of the pilot-scale combustor and include technical and laboratory test support activities for reducing the technical risks and costs of development at the pilot-scale. Based on the information, test, data and technical support activities, a retrofit combustor system will be designed for field demonstration as shown on the left in Figure 1.

At the end of this phase of the program, a design for a retrofit combustor system for field demonstration will be completed with the exception of site-specific design details which will be provided after approval for the field demonstration at the subcontractor test site.

1.2 TASK DESCRIPTIONS

Task 1: Optimization of the Laboratory-Scale Combustor

The specific objectives of this task are to optimize the chamber design of the feasibility units developed under Contract No. DE-AC22-83PC60419 for optimized performance with coal and coal-water slurry fuels and to reduce performance sensitivity to variations in fuel specifications.

To meet these objectives, two advanced combustion chamber configurations will be designed and fabricated at the laboratory-scale (1 - 2 MMBtu/hr) size. Design options will include both bare metal and refractory-lined units to permit both air-cooled and adiabatic operation. These advanced designs will be fabricated and then tested to evaluate the performance with respect to the following parameters:

FIGURE 1:
PROGRAM LOGIC FOR DEVELOPMENT OF A PULSE
COAL COMBUSTOR FOR RETROFIT APPLICATIONS

- o Combustion intensity and heat release rates,
- o Staging capability,
- o Dry sulfur capture and ash rejection performance,
- o Carbon burnout efficiency,
- o NO_x emissions performance, and
- o Sensitivity to changes in fuel specifications.

Refractory-lined combustor tests will be conducted employing both the feasibility unit chamber design and one of the advanced chamber designs selected on the basis of the evaluation tests.

Task 2: Scale-Up Pilot Unit Design

The specific objective of Task 2 is to design a pilot-scale test unit for evaluation in the existing MTCI facility. To meet this objective, the data acquired under Task 1 will be utilized to develop design scale-up criteria for scaling the laboratory-scale design to pilot-scale. These criteria include consideration of the effect of scale-up on combustor operating frequency, firing intensity (in MMBtu/hr cu.ft.), and the intensity of pressure fluctuation with increased firing rate. The scale-up design also considers all the interface requirements of the pilot-scale development activities at the subcontractor test site. The design developed will be sufficiently detailed to permit the fabrication of the unit when approved by DOE.

1.3 STATUS

The tandem design configuration unit was tested with a low ash pulverized coal during this period. The unit operated with strong peak-to-peak pressure. Carbon burn-out efficiencies greater than 99 percent were achieved but small quantities of support gas were required to maintain stability. The tandem unit was dismantled and inspected after the series of test runs on pulverized coal. In one of the combustor chambers (B), large chunks of refractory were dislodged from the lining, whereas in chamber (A) a fairly uniform penetrating layer of slag approximately 1/2 inch wide had been deposited. The basic geometry of this chamber remained unchanged. The refractory failure in chamber B was later traced to improper handling and curing during installation.

The test results on the configuration design unit clearly indicated that the tandem combustor had the ability to meet the intended target performance goals for dry micronized coal. In preparation for optimization testing on pulverized coal and slurry, some modifications were incorporated into the system to increase residence time, reduce heat losses in the chamber and tailpipe and to improve slag handling for higher ash fuels. The quench tank and scrubber column were also modified to handle the higher firing rates of the tandem unit and to reduce back-pressure on the system. Some additional modifications were incorporated into the optimized system design to provide for preheating the fuel feed lift air; the introduction of secondary air into the cyclone combustor for staged combustion and; finally, for reducing acoustic emissions from the unit.

The modifications were completed and the optimized tandem unit was fired first on natural gas for tuning in preparation for evaluation testing on pulverized coal and slurry. The unit was fairly well-behaved, achieving stable operation, high carbon burn-out rates and low NO_x and CO emissions. The issue of carbon burn-out was evaluated to assure ourselves that the methodology developed was indicative of the burn-out performance of the unit.

Preliminary activities have also been initiated for the design of the scale-up combustor with emphasis on concepts for improving efficiency of ash collection, acoustic insulation, combustor control and interface requirements for retrofitting the unit to a small industrial boiler.

During the last period, a series of tests were conducted on the tandem design configuration employing a direct tangential cyclone. The test runs were performed using a low ash micronized coal. Testing continued during this period on a low ash pulverized coal. The test results were quite significant, confirming the ability of the combustor to operate with strong peak-to-peak combustor pressures while utilizing coal fuels only. In several cases, carbon burn-out efficiencies of greater than 99 percent were achieved on micronized coal. Carbon burn-out efficiencies on pulverized coal were typically a couple of percent lower than for the micronized fuels. The maximum feed rate for the pulverized coal was somewhat less than for the micronized coal, requiring small quantities of support gas.

The test results clearly demonstrated the ability of the tandem pulse combustor to achieve many of the intended target performance goals for operation on dry micronized fuels. The initial configuration tests on pulverized coal indicated that further system modifications were necessary to optimize performance on these higher ash containing pulverized fuels and slurry fuels. These modifications included: 1) increasing the combustor chamber volume to increase residence time, 2) increasing the thickness of refractory lining in the chamber and tailpipes to reduce heat losses and thus increase combustion temperature, and 3) redesign the cyclone to allow improved slag handling for higher ash content fuels.

SECTION 2.0

TECHNICAL DISCUSSION OF WORK COMPLETED DURING THE REPORTING PERIOD

The work during this reporting period focused upon the following tasks:

- 1.0 Lab Scale Optimization
- 1.2 Configuration Optimization
- 1.3 Evaluation Testing
- 1.4 Data Reduction and Analysis, and
- 3.0 Management and Reporting

Task 1.2: Configuration Optimization of Configuration Unit

Tests performed in September and October were made on the tandem unit employing two coupled combustors designated as Chamber A and Chamber B. It was evident during the course of these runs that the performance in Chamber B was progressively diminishing. In fact, on several occasions, Chamber B would phase out while Chamber A would continue to operate in a normal manner.

Post Mortem Inspection

Following tests in October on pulverized coals, the tandem unit was dismantled and inspected in order to prepare for construction of the optimized design. The inspection revealed several important results.

Chamber A, which had exhibited good performance throughout September, was coated with a penetrating slag layer approximately 1/2" thick. In contrast, only small quantities of slag were evident in Chamber B. More importantly, large chunks of refractory were dislodged from the lining in Chamber B, whereas the basic geometric contours in Chamber A were unchanged. Figures 2 and 3 show the two chambers after disassembly. The deep pitting in Chamber B is easily seen in Figure 3.

Based on these results, it was evident that the diminished performance in Chamber B was a direct result of the deteriorated chamber surfaces. Since the carbon burn-out efficiencies measured at the cyclone exit included contributions from both Chamber A and Chamber B, it is projected that actual performance levels in the uncompromised chamber were significantly higher than the reported average values.

Both chambers were originally poured with Pyrotab refractory which is a high alumina based material rated to 3400°F. While this refractory has good high-temperature capability, it suffers from attack by acidic slag constituents. As a result, the slag has a tendency to react and fuse with the

FIGURE 2:
PULSE COMBUSTOR CHAMBER A

FIGURE 3:
PULSE COMBUSTOR CHAMBER B

refractory material. While this phenomena does not appear to result in catastrophic failure of the refractory, it does seem to roughen and texture the smooth surface of the lining as observed in Chamber A. The catastrophic failure observed in Chamber B is now thought to be due to improper curing and handling procedures and is not believed to be indicative of normal wear behavior within the combustor.

The reaction of slag with the combustor lining is somewhat problematic. Although more acidic refractory materials having a lower reaction potential are available, their high temperature capabilities are limited. One possible solution involves neutralization of the slag constituents. This can be accomplished by the addition of basic components such as limestone. Since limestone injection for sulfur capture is envisioned for many applications, the problem of slag erosion may be naturally ameliorated under these conditions.

Construction of an optimized configuration was undertaken during this period to improve those features specifically related to the optimal combustion of high ash pulverized coal and slurry fuels. Test runs focused on the use of pulverized and slurry fuels.

The residence time in the combustion chambers was increased by adding a 4" insert at the maximum diameter of the chamber. This insert does not change the basic geometry of the chamber but increases the volume from 345 cubic inches to 610 cubic inches. In order to decrease the heat losses, the refractory wall thickness has been increased to 2 inches in both the chambers and tailpipes.

The cyclone has also been redesigned to improve slag rejection characteristics. The cyclone chamber was poured with a sloping surface to allow slag collection at a newly installed slag tap. Figure 4 depicts the new design features. The 4" combustor insert is also identified in this figure.

The new configuration also employs a modified fuel injection system; one that is believed to be suitable for both dry and slurry fuels. Slurry fuel injection will involve the use of a phase chamber to provide capabilities for preheating and vaporizing before direct injection into the combustor.

A common observation throughout many of the tests conducted in the last several months has been the tendency for the tandem pulse combustors to "hunt" during normal operation. Combustor hunting is characterized by an instability which forces the unit to wander in and out of an intense combustion phase. During the intense combustion phase, the unit appears to lock into a robust resonant mode. This condition is evidenced by increased peak and mean pressure boosts as well as a noticeable increase in combustor sound intensity. Shortly thereafter, however, the intense combustion phase degenerates into a less robust operating condition as a result of some undefined system instability.

Up until recently, the source of this combustion instability was thought to be related primarily to non-uniformities in the feed rate of fuel to the combustor. However, it is now evident that some of these instabilities were

FIGURE 4: OPTIMIZED CONFIGURATION OF INDUSTRIAL TANDEM UNIT

also associated with back pressure fluctuations in the quench tank and scrubber column.

The quench tank and scrubber column were initially designed to handle flue gas flow rates from combustors sized in the 1.0 to 1.5 MMBtu/hr firing range. However, with the increased capacity of the tandem units, the quench/scrubber is now required to handle firing rates of 2.0 to 3.0 MM Btu/hr. Design calculations were made which indicated that the scrubber column was undersized for the intended service, resulting in a phenomena known as "flooding" caused by the high velocity of flue gases in the scrubber column.

During normal scrubber operation, the contact liquid should flow in an unrestricted manner through the packing contained within the scrubber column. However, as the velocity of flue gases increased, a point is reached where the pressure drop through the column restricts the uniform flow of liquid down the packing. During this flooding condition, the liquid in the column builds up until the pressure head is sufficient to force it through the packing. This phenomena imposes an unstable back-pressure on the combustor resulting in the hunting effect previously mentioned.

Design calculations showed the 14" scrubber column to be limiting the system throughput. In contrast, the 2' diameter scrubber tank is sufficiently large to handle the higher capacities. Thus, in order to overcome the capacity limitations of the scrubber column, the raschig packing rings were removed from this unit. Instead, contact liquid is now directly sprayed into the top of the empty column. Due to the absence of packing, flooding no longer occurs and the contact of flue gases and liquid within the empty scrubber column appears to be sufficient for the intended service.

It is believed that stabilization of the back pressure on the tandem combustors may result in significantly improved performance, particularly with regard to combustor hunting.

In addition to the major system changes described earlier, some minor modifications were made to the air intake plenum and the lift air system. Due to excessive temperature exposures near the face of the combustors, the 1/8" thick plate forming the air plenum became distorted beyond repair. Therefore, a new plenum was fashioned from 1/4" thick plate and amply braced. Also, the plenum door was refitted with high temperature stainless steel gaskets, and the entire housing was insulated with a sound proofing blanket. The increased stiffness of the housing and the added insulation substantially reduced the acoustic emissions from the unit.

Appropriate modifications were also made to allow for preheating of the coal lift air prior to the eductor. The air passes through a 20 foot length of 3/8" tubing. Current is passed through the metal tubing from a temperature controlled relay in order to allow regulation of the lift air preheat temperature.

Finally, provisions were made to introduce secondary air into the cyclone combustor for staged air combustion operation. In this configuration, a branch line from the forced draft fan transports secondary air to an annular jacket which surrounds the cyclone exit line. Here, the air is preheated prior to introduction into the cyclone decoupler which now additionally serves as a secondary combustion chamber.

Emphasis should be placed on breaking in the refractory chamber surface by depositing a thin slag layer which has been found to be essential for the attainment of repeatable steady-state combustion performance data.

Deposition of a slag layer was accomplished by operation of the combustors on both micronized and pulverized coal for extended periods. The enhancement of combustion performance as a function of break in time (i.e., cumulative coal feed) was clearly demonstrated over the course of the test runs conducted this period.

Task 1.3 Evaluation Testing:

Prior to disassembling the tandem unit, a test run was conducted using a low ash pulverized coal fuel. The sample analysis for this coal fuel is given in Table 1.

TABLE 1:
PULVERIZED COAL FUEL ANALYSIS

COAL I.D. UE3-135-PCO-C

DESCRIPTION: Upper Elkhorn #3 Seam - Deep Cleaned Coal Dry Pulverized for
MTG

PROXIMATE:

MOISTURE 2.82%
VOLATILE MATTER 37.00%
FIXED CARBON 61.60%
ASH 1.40%
SULFUR 0.65%
BTU/LB 15235

ASH CHEMISTRY:

SiO₂ 38.35%
Al₂O₃ 29.44%
TiO₂ 2.79%
Fe₂O₃ 18.98%
CaO 3.64%
MgO 1.03%
K₂O 0.98%
Na₂O 1.23%
SO₃ 2.50
P₂O₅ 0.56% Est.
SrO 0.42%
BaO 0.45% Est.
Mn₃O₄ 0.03% Est.
BASE ACID RATIO 0.37%
T-250 TEMP. 2450°F

ULTIMATE:

CARBON 84.37%
HYDROGEN 5.36%
NITROGEN 1.52%

ASH FUSION: REDUCING

INITIAL 2090°F
SOFTENING 2230°F
FLUID 2370°F

FREE SWELLING INDEX:

6.5

HARDGROVE GRINDABILITY:

NA

SULFUR FORMS:

PYRITIC 0.05%
SULFATE 0.02%
ORGANIC (DIFF) 0.58%

The results of the test run are shown in Table 2. The unit operated with a low oxygen content of 1.1% in the flue gas. Note that all flue gas sampling was made at the cyclone exit. Also note that the reported gas analysis is for the uncorrected dry gas.

It can be seen from Table 2 that the carbon monoxide level at the exit of the cyclone is quite low (50 ppm). In comparison to the testing during the previous period, the carbon monoxide levels at the tailpipe exit can be greater than 10,000 ppm. It is evident that the additional residence time in the cyclone is sufficient to complete CO burn-out.

The NO_x concentration was measured as 750 ppm (actual) or approximately 675 ppm corrected to 3% O₂. The SO₂ level was measured as 500 ppm or approximately 450 ppm corrected.

The carbon burn-out value calculated based on fly ash measurements was only 91%. As discussed in the previous quarterly report, the bulk of the ash is rejected as slag. Using a 95% and 80% slag rejection efficiency assumption, the actual carbon burn-out values are calculated as 99.55% and 98.2% (see Table 2).

The optimized unit was assembled and initial natural gas tests were conducted. These tests were initially performed on the new chamber prior to making alterations to the scrubber unit. The unit was fired up to a peak rate of 2.6 MM Btu/hr and the unit was observed to operate in an optimal manner at firing rates somewhat greater than 2.0 MM Btu/hr. The typical mean boost pressure in the combustor at these conditions was approximately 15 to 16 inches water column.

Additional tests on natural gas were performed following modification of the scrubber system as described above. Preliminary results appear to confirm the hypothesis that the scrubber may have limited pulse combustor performance. Mean boost pressures of over 20 inches water column were recorded after the scrubber unit was modified. The combustor sound intensity and quality appeared to improve considerably. Combustion instability and hunting appeared to be greatly minimized. Furthermore, the waveforms from the combustors monitored by oscilloscope were among the cleanest and most pure sine waves recorded to date. The 180° phase lag between the combustors was quite stable, with little evidence of wandering as observed in the past.

These results provided a level of confidence that the new system is well tuned. Preparations for testing on pulverized coal and slurry fuels were initiated and evaluation testing on pulverized coal was conducted during this period. Measurements were performed for six separate runs as summarized in Table 3.

The unit was fired on 100% pulverized coal at a rate of 2.59 MM Btu/hr. The volumetric heat release rate and residence times in the pulse combustor and tailpipe were 1.33 MM Btu/ft³/hr and 46 msec, respectively.

TABLE 2:
PULVERIZED COAL TEST RUN

TEST DATE	10/20/1987
Firing Rate Natural Gas	425,250
Firing Rate Coal	1,008,000
Coal Type	Low Ash Pulverized
Total Firing Rate	1,433,250
<u>GAS ANALYSIS (1)</u>	
O ₂ %	1.1
CO ₂ %	14.0
CO ppm	50
NO _x ppm	750
SO ₂ ppm	500
% CARBON BURN-OUT (2):	91.0
ADJUSTED % BURN-OUT (3):	
95% Slag	99.55
80% Slag	98.20

- (1) At Cyclone Exit
- (2) Based on Fly Ash Only (at cyclone exit)
- (3) Adjusted for Slagging (at cyclone exit)

TABLE 3: SUMMARY OF TEST DATA

<u>Test Date</u>	<u>12/02/87</u>	<u>12/23/87</u>	<u>1/4/88</u>	<u>1/13/88</u>
Natural Gas, MM Btu/h	1.51	1.01	0.00	1.83
Coal, MM Btu/h	.69	1.75	2.59	.32
Coal Type	pulv.	micro	pulv.	pulv.
Total Fuel, MM Btu/h	2.20	2.76	2.59	2.15
<u>Gas Analysis</u>				
O ₂ %	3.50	3.0	(1)	7.8
CO ppm	1000+	1000+	(1)	10
NO _x ppm	800	630	(1)	100
<u>% Carbon Burn-out</u>				
Cyclone Exit:				
0% slag	83.0	86.0	95.0	88.0
80% slag	96.6	97.2	99.0	97.6
95% slag	99.2	99.3	99.8	99.4
Scrubber Bottoms (0% slag)	NA	NA	NA	99.4
<u>Test Date</u>	<u>1/14/88</u>	<u>1/15/88</u>		
Natural Gas, MM Btu/h	0.00	0.00		
Coal, MM Btu/h	2.59	2.59		
Coal Type	pulv.	pulv.		
Total Fuel, MM Btu/h	2.59	2.59		
<u>Gas Analysis</u>				
O ₂ %	2.6	6.8		
CO ppm	1000+	620		
NO _x ppm	430	NA		
<u>% Carbon Burn-out</u>				
Cyclone Exit:				
0% slag	92.6	92.0		
80% slag	98.5	98.4		
95% slag	99.6	99.6		
Scrubber Bottoms (0% slag)	NA	98.6		
(1) sample line air leak				

Stable operation on 100% pulverized coal was demonstrated for the modified tandem unit. The performance on pulverized coal was shown to be similar to that on micronized fuels indicating a low sensitivity to fuel type.

Carbon burn-out levels of greater than 99% were achieved as measured from scrubber bottoms samples. These values were calculated assuming 0% slag rejection in the cyclone and thus are conservative.

The carbon burn-out values from the quench probe located at the cyclone exit were typically in the range of 90% using a 0% slag assumption. As will be discussed in the following section, only a small portion of the ash agglomerates are effectively collected in the quench probe. Additional sample measurements indicated that only approximately 10% of the ash is collected in the sample probe, the remaining portion being excluded due to their large size. As seen in Table 1, by adjusting for this effect, the carbon burn-out values at a 80 to 95% slag rejection assumption gives values similar to that obtained from the quench solids. A more complete discussion of this issue follows.

Carbon monoxide values for coal runs typically exceeded 1000 ppm, however lower values were obtained for high excess air rates. These values are not considered to be an issue since complete burn-out is expected during the residence times provided in an actual boiler retrofit application. NO_x emission values as low as 430 ppm were obtained on 100% pulverized coal.

Task 1.4 Data Reduction and Analysis:

The series of test runs to characterize the performance of the modified tandem pulse combustors operating on pulverized coal fuels have provided a new body of evidence having significant bearing on the interpretation of the overall performance of the pulse combustors, particularly with respect to carbon burn-out and the nature of ash or slag rejection.

The experimental test results indicated that the combustor system is characterized by a transient state involving the deposition of a thin slag deposit layer on the combustor walls. During this break-in period, the fate of ash and unburned carbon particles within a "fresh" combustor was found to be markedly different from that in a fully slag-coated combustor under steady-state conditions.

The experimental test results also indicated that once the combustor is fully slagged, a substantial portion of the ash is rejected from the system in the form of relatively large particle agglomerates. While some of these agglomerates are retained within the cyclone, a large portion are entrained in the flue gas stream. Due to the apparent size of these agglomerates, it is believed that an improved cyclone design would allow their capture at high efficiencies.

In the following paragraphs, these conclusions will be discussed in light of the recent experimental data.

Transient Behavior and Combustor Break-in

Based on experimental data collected over the six week period, it has become evident that measured combustion efficiency initially improved in direct relation to the cumulative quantity of coal fuel fed to the combustors. This "breaking in" period and its effect on the measured combustion efficiency is now thought to be due to the influence of slag deposition processes on either: 1) the relative balance of carbon and ash in the flue gas due to selective deposition of ash on the refractory sink surfaces, or 2) the ability of a thin wet slag layer to capture and retain large coal particles, thereby increasing their effective residence times within the combustion chamber and thus enhancing carbon burn-out.

The first effect is an experimental ambiguity which results from the particular methodology and assumptions used to calculate the carbon burn-out efficiency. In a commonly practiced method, a flue gas sample containing particulate matter (ash and unburned carbon) is collected through an isokinetic probe. The particulate matter is filtered from the gas stream and then ashed to measure its relative carbon content. If all of the ash is assumed to be entrained within the flue gas stream, then the ratio of carbon to ash in the sample can be compared with that of the initial coal fuel, and a simple algorithm can be employed to calculate the percent carbon burn-out.

However, in the case of a combustor operating in a slagging mode, a significant portion of the coal ash may be rejected as a molten slag or may adhere to refractory surfaces within the combustion system. Under these conditions, the flue gas particulate matter does not contain ash in a quantity which is truly representative of the initial coal feed. Therefore, if the appropriate corrections for ash rejection by slag formation are not made, the described method of calculation will yield artificially low carbon burn-out values.

Results of recent tests appear to indicate that an uncharacteristically large portion of coal ash may be rejected as slag during the initial break-in period of the combustor. In this case, slag rejection is probably occurring in the form of deposition on the fresh refractory surfaces of the combustor, tailpipe, and cyclone. As the cumulative quantity of coal fuel fed to the combustors increases, a steady-state slag layer is established. Once this slag layer is established, additional deposition on the surface does not occur and increasing quantities of fly ash, or fine slag agglomerates are entrained within the flue gas stream. This phenomena leads to carbon burn-out values which tend to increase with time when no corrections for slag rejection are made.

The results of tests conducted this month are consistent with the aforementioned interpretation. Figure 5 shows a plot of the calculated carbon burn-out values, assuming no slag rejection (0% slag), as a function of the cumulative coal feed timeline. The general tendency toward increasing carbon burn-out values is clearly evident in this plot. Note that the assumption of 0% slag rejection is highly conservative giving rise to erroneously low combustion efficiency.

FIGURE 5: CARBON BURNOUT VERSUS CUMULATIVE COAL FEED TIMELINE

A second explanation based on a more fundamental mechanism may also be considered. As thin slag deposit layer builds up on the surface of the combustor, large coal particles which impinge by inertial forces on the combustor walls are temporarily retained there. This assists in enhancing carbon burn-out by increasing the residence time of the largest particles which are in need of the longest burn-out times. Figure 6 depicts the hypothetical process within the combustor as a slag layer accumulates.

Differentiation between these two interpretations can only be made by obtaining a more thorough understanding of the partition and disposition of coal ash within the combustion system. Unfortunately, the measurements needed to quantify the precise nature and extent of ash rejection within a hot combustion zone are quite difficult. This is particularly true for a small experimental apparatus which is operated for only relatively short durations.

Despite these difficulties, techniques do exist for quantifying carbon and ash loadings within hot flue gas streams. Generally, these methods employ isokinetic probes which sample a defined volume of flue gas over a defined period. These slip streams can then be related to the total system flows in order to estimate the overall material balance. However, these methods are often prone to a considerable degree of error when the sample which is

..... LARGE PARTICLE TRAJECTORY
——— FLOW STREAM LINES

FIGURE 6:
CARBON RETENTION IN SLAGGED COMBUSTOR

withdrawn is not completely representative of the actual flue gas stream. This can occur, for instance, when small particles are preferentially withdrawn in the slip stream relative to large particles.

In recognition of these issues, a combination of sampling techniques have been applied to better define the fate of carbon and ash within the slagging tandem pulse combustor. These techniques have included sampling from the exit of the hot cyclone using an isokinetic probe and sampling of the particulate knock-down product (scrubber bottoms) within the quench scrubber. The results from these measurements have been analyzed to develop a consistent interpretation and reliable calculations regarding the performance of the pulse combustors.

Carbon Burn-out and Ash Sampling

Figure 7 depicts the pulse combustion apparatus and primary sample locations. During the course of this experimental program, samples have been withdrawn from each of the locations noted. The first sample point is located at the tailpipe exit. The second point is located after the hot cyclone at the transfer line leading to the quench scrubber. And finally, sample is also withdrawn from the particulate knock-down drum which is integral to the quench scrubber.

Previously, the carbon burn-out values were calculated based on samples withdrawn from sample location No. 2. The carbon burn-out values were reported for three separate parametric assumptions concerning slag rejection efficiency; 0%, 80% and 95%. The first parametric level (0%) reflects the case where no slag is rejected in the cyclone and the sample probe uniformly withdraws a fly ash quantity in proportion to the total quantity of ash contained in the initial coal. The 80% and 95% parametric levels reflect increasing quantities of "apparent" slag rejection. Note that apparent slag rejection refers not only to ash which is physically rejected in the cyclone, but also ash which is incapable of being withdrawn by the sample probe due to its large agglomerated size. Thus, the parametric slag rejection level can be considered as the quantity of ash which can theoretically be collected through the use of a high efficiency physical separation device.

The values of 80% and 95% slag rejection were selected based on experimental estimates of the total ash loading in the flue gas as reported in the last quarterly. This calculation was made by measuring the volume of flue gas drawn over a defined time, measuring the quantity of ash deposited on a filter, and then relating these quantities to the overall system material balance. Using this procedure, measured slag rejection values of greater than 90% were recorded.

However, during the course of more extended testing, it soon became evident that this large quantity of slag was not collecting in the cyclone. Furthermore, total mass balances on the particulate knock-down solids collected from the scrubber system indicated that relatively large quantities of mass were being accumulated therein.

FIGURE 7:
SAMPLE LOCATIONS FOR COMBUSTION SYSTEM

These results seemed to suggest that the pulse combustors were generating ash agglomerates which were not captured in the cyclone with high efficiency, but were agglomerated to a sufficient extent that they were effectively excluded from capture in the fly ash sample probe.

In order to test this hypothesis ash samples were taken from the scrubber bottoms. These samples consistently yielded carbon conversion levels which were significantly higher than those obtained using the gas probe based on a 0% slag assumption. This result is entirely consistent with the hypothesis that the bulk of the ash is too large to be collected in the fly ash probe. Of course, the quench scrubber system is capable of collecting virtually all of the ash including both fly ash and agglomerates, and thus the ratio of ash to carbon is higher for scrubber bottom samples than for gas probe samples. This in turn explains the higher carbon burn-out values measured for samples withdrawn from the scrubber bottoms using a 0% slag assumption.

Table 4 summarizes the test results for several runs and compares the calculated carbon burn-out values for samples taken from the scrubber bottoms and from the gas probe using the three different slag rejection parameters. It can be seen that the carbon burn-out values calculated from the scrubber bottoms samples are in the range of 99% for the 0% slag assumption (i.e., assuming all of the ash is collected in the scrubber.) In contrast, the 0% slag assumption for the gas probe sample only yields values in the range of 90%. Since the carbon burn-out values for each of these samples should be equivalent (due to negligible differences in residence time between these sample point and the spray quench downstream of the sample location #2) the correct slag assumption for the gas probe must be found which allows a consistent interpretation of the data. By inspection of Table 4, it can be seen that for a slag rejection assumption in the range of 80% to 95%, a consistent interpretation of the data can be achieved (i.e., the two sample points yield equivalent conversions). Furthermore, this range of slag rejection values is consistent with the estimated values calculated based on gas volume and solids withdraw consideration as previously reported. It is thus concluded that the gas sample probe is capable of collecting only 5 to 20% of the initial coal ash, indicating that the balance of ash is either deposited in the cyclone or entrained as relatively large size agglomerates within the flue gas stream. Figure 8 depicts the hypothetical distribution of ash and carbon within the combustion system.

**TABLE 4: COMPARISON OF CARBON BURN-OUT VALUES FOR DIFFERENT
SAMPLE LOCATION AND SLAG REJECTION ASSUMPTIONS**

<u>Run Date</u>	Scrubber Bottoms	Gas Probe Sample		
	<u>0% Slag</u>	<u>0%</u>	<u>80%</u>	<u>95%</u>
12-02-87	NA	83.0	96.6	99.2
12-23-87	NA	86.0	97.2	99.3
01-04-88	NA	95.0	99.0	99.9
01-13-88	99.4	88.0	97.6	99.4
01-14-88	NA	92.6	98.5	99.6
01-15-88	98.6	92.0	98.4	99.6

FIGURE 8:
SCHEMATIC OF CARBON AND ASH DISTRIBUTION IN PULSE COMBUSTION APPARATUS

Conclusions

The following conclusions can be drawn from the experimental data to date.

1. Carbon burn-out efficiencies of greater than 99% can be achieved using both dry micronized and dry pulverized coal fuels.
2. The pulse combustor generates slag ash agglomerates of relatively large sizes. Due to their large sizes, these agglomerates are not detected by the fly ash probe. It can be inferred that the agglomerates are of sufficiently large size to be collected in a more efficient cyclone or by addition of ash screens as presented in the MTCI original design (Final Report Contract No. DE-AC22-83PC60419).
3. The combustion efficiency in the pulse combustors should only be calculated after the initial break-in period particularly on low ash coal firing.

Task 2.0: Scale-up Pilot Unit Design

Preliminary efforts have been initiated for the design of a scale-up combustor at the 3.5 to 5.0 MMBtu/hr range. Particular emphasis is being given to the development of concepts for more efficient collection of ash agglomerates. Methods of acoustic insulation and combustor control are also being considered as well as issues relating to interface of the combustor with a small industrial boiler.

Task 3.0: Technical Management and Reporting

This task is progressing as per plan. In early October, MTCI presented the results of both the residential and industrial pulse combustion programs at the DOE/PETC facilities. The requirements for follow-on work in Phase II were also discussed at this time.

SECTION 3.0

PLANNED ACTIVITY FOR THE NEXT PERIOD

Evaluation testing on coal slurries will be initiated during the next period and a final Phase I report will be prepared. It is anticipated that the Phase I effort will be successfully concluded early in the next quarter. There will, therefore, be no further quarterly progress reports for this phase of the program.

END

**DATE
FILMED
5/13/93**