Draft Office of Engineering 10 Year Plan 1992-2001

Approved by the Board of Directors

JUN 17 1992

Bonneville
POWER ADMINISTRATION

May 1992

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DOE/BP--1557

DE92 015690

DRAFT

**BONNEVILLE POWER ADMINISTRATION
OFFICE OF ENGINEERING
10-YEAR PLAN
1992 - 2001**

MAY 1992

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

**OFFICE OF ENGINEERING
10-YEAR PLAN
1992-2001**

Table of Contents

	<u>Page</u>
ENGINEERING MISSION STATEMENT	4
I. INTRODUCTION	4
II. LONG RANGE PLANNING CONTINUUM.....	6
A. Regional Perspective.....	6
B. Reliability.....	7
C. Loads	8
D. Resource Integration	8
E. Environment.....	9
F. Public Involvement.....	9
G. Cost Effectiveness.....	10
H. Human Resources	10
I. Safety	11
III. OFFICE OF ENGINEERING WORKLOAD	12
A. Transmission System Development.....	12
B. System Replacement, Operation & Maintenance.....	13
i. Capital Replacement Program	13
ii. System O&M	14
C. Support for Other Programs	15
i. Fish and Wildlife	15
ii. Energy Resources.....	15
iii. Power Sales	16
iv. Environment	16

IV.	STRATEGIES.....	18
A.	West Coast Vision/BPA Transmission Strategy	18
B.	Transmission System Reliability	19
C.	System Loads in the Next Decade	20
D.	Integration of New Generation Resources	21
E.	Environmental Stewardship.....	21
F.	Public Involvement.....	22
G.	Cost Competitiveness.....	22
H.	Management of Human Resources	23
I.	Safety	24

V.	CONCLUSION	24
----	------------------	----

VI. APPENDICES

Appendix A

- Transmission System Development Program, Major Construction Items and Justification
- Summary, 10 Year Transmission System Development Program

Appendix B

- Tables 1,2,3 - Office of Engineering Program Dollars and Personnel Data

ENGINEERING MISSION STATEMENT

BPA Engineering will provide the engineering leadership that assures a reliable and economical Northwest Transmission System. We are committed to excellence and responsiveness in providing engineering services of high value and quality to our customers.

I. INTRODUCTION

For over 50 years, the Bonneville Power Administration (BPA) has evolved to supply electric power to more than 170 customer utilities and direct service industries across 14,800 miles of high voltage transmission lines. BPA's Office of Engineering provides the planning, development, and engineering for the required expansion, upgrade, and replacement of the transmission system.

As BPA's principal engineering organization, the Office of Engineering serves BPA by (a) exercising leadership and primary responsibility for long-range and program planning of transmission facilities to serve loads, integrate resources, and maintain system reliability in a technical, economical, and environmentally acceptable manner; (b) planning, designing and specifying equipment and construction requirements for BPA's substation, transmission, control, communication, and non-electric facilities; (c) providing project related National Environmental Policy Act (NEPA) documentation; (d) managing the overall BPA Research and Development (R&D) program and implementing the transmission system R&D program elements; and (e) providing engineering and laboratory services to other Offices in BPA.

Engineering's activities support a number of BPA programs that are planned in a variety of public processes. Transmission facilities are planned to meet the "BPA Reliability Criteria for System Planning" which was reviewed and updated in a 1989 public "Technical Review Group" process. This criteria is the basis for identifying major new transmission facilities in the Transmission System Development Plan and for longer range transmission system development forecasts, the most recent being the "Transmission Facilities 10 Year Development for 1991-2000." Engineering also supports other BPA programs that are planned in the following processes: 1) "Operations, Maintenance, and Replacement 10 Year Plan 1990-1999;" 2) "Northwest Power Planning Council - Columbia River Basin Fish and Wildlife Program of 1987" and subsequent amendments; and 3) the "1990 Resource Program" with biennial revisions. The "Northwest Power Planning Council - Regional Power Plan" is a basis for specific BPA office programs. Each year the resulting programs are presented, discussed, and refined in BPA's Programs in Perspective (PIP) public process.

The purpose of this 10-Year Plan is to present strategies to maintain a reliable energy delivery system within changing public, business, technological, and environmental climates. The issues and trends discussed in this document and our strategies for addressing them provide the backround for the Office of Engineering programs and projects. With a budget in the hundreds of millions annually and increasing public concern, we welcome the opportunity to communicate with our customers.

In addition to the factors, trends and issues described in this document are two appendices containing project costs and program and staffing levels. These figures are preliminary with estimates cuurent as of May 13, 1992.

Appendix A contains: 1) a listing of the major projects which are planned over the 10 year period, along with justifications and total project costs; and 2) a summary of these projects showing costs over 10 years. Future transmission system requirements can usually be met by a number of functionally acceptable alternatives. Technical, economical, environmental, and other pertinent aspects of each of the alternatives are analyzed and evaluated prior to the selection of a final plan-of-service. The environmental work has been completed for most of the 1993 and earlier projects shown in Appendix A , and a final plan-of-service has been selected. The 1994 and later projects are presently under study and the environmental work is not completed. The plan for these projects represents one possible alternative and is used at this time for budget forecasts. While some of the larger future projects may have financial participation by others, the entire costs are shown for planning purposes.

Appendix B contains three tables: Table 1, which shows staffing levels and program dollars for the Transmission System Development program; Table 2, showing the staffing levels and program dollars for the System Replacement Program; and Table 3, a 20-year history of Engineering program dollars and Engineering staffing levels from 1987-2001.

You may send written comments on the Draft Office of Engineering 10-Year Plan by COB June 29, 1992, to:

Public Involvement Manager
Bonneville Power Administration
P.O. Box 12999
Portland, OR 97212

II. PLANNING CONTINUUM

In the 1990's, BPA will operate in a climate of increased public awareness of environmental conditions and rising costs, while trying to maintain a reliable and cost effective transmission system. Technological changes in electrical transmission allow BPA engineers to incorporate new and more efficient technologies into the transmission system. BPA's engineers are carefully examining the capacity of the system, planning facilities, and designing and testing equipment additions and replacements during the next 10 years to continue to provide reliable service to the Pacific Northwest.

The system must be upgraded to maintain reliability while accommodating load growth. Load growth spurs demand for new generation resources which can be located in remote areas, requiring more transmission to bring the power to the load centers. The public has become increasingly concerned about transmission facilities because of visual considerations, impact on the environment, and possible health effects from electric and magnetic fields (E/MF). As a result, transmission line rights-of-way are becoming more difficult to obtain. Concerns over declining Columbia River fish runs may change the way the river can be used to produce power, causing BPA engineers to find new ways to maximize the use of the existing system.

Following is a summary of the primary factors that influence BPA's future transmission system development.

A. Regional Perspective

The BPA transmission system is linked directly with almost all other Pacific Northwest utilities, and other regions including British Columbia and California through AC and DC Intertie systems. In addition, all the western states and western Canada operate as an interconnected system. The utilities in this interconnected system depend on each other for mutual back-up of generation resources and transmission. Also, because the systems are interconnected, problems on one system can cause problems on another system. Thus, it is important that utilities coordinate their system plans.

BPA and other utilities in the Pacific Northwest, Pacific Southwest, western Canada and other western states are members of the Western Systems Coordinating Council (WSCC). WSCC was formed in 1967 to coordinate the operation and planning activities of its members and to promote the reliability and adequacy of the western interconnected transmission and generation facilities.

The common difficulties the power industry faces such as the reduced availability of rights-of-way, require even greater planning and cooperation between utilities. To meet these concerns, BPA and other Northwest utilities are committed to the concept of single utility transmission planning. This concept goes beyond coordinating plans to ensure they work together. It means planners look at the whole Northwest transmission system as one system, independent of ownership, and develop the most efficient system to serve all loads reliably, to integrate all new generation, and to accommodate the Northwest's transactions with other regions. Single utility planning will ultimately reduce the number of new facilities needed. This will benefit all the region's power customers by minimizing construction, cost and environmental impacts.

BPA engineers were recently involved in the formation of the Northwest Power Pool's Transmission Engineering Committee. This committee is composed of 12 Northwest utilities and was established to facilitate joint regional transmission planning. Several other forums, including the WSCC, are being examined for coordination on a broader scale.

B. Reliability

The BPA transmission system is planned, designed, constructed, and operated to insure cost-effective, reliable service. Engineering is responsible for the planning and design of the system. The system is planned and designed for sufficient strength and capacity to maintain continuity and quality of service to electrical loads during certain more common contingencies or system disturbances. For other less common contingencies, it may not be cost-effective to provide enough capacity to maintain full service, so interruption of service or some reduction of quality of service is allowed.

The BPA Reliability Criteria for system planning set the performance requirements for planning the BPA system and are the basis for determining when transmission system reinforcements are needed. BPA has actively sought regional involvement and commentary in development of its planning criteria from the public, other utilities, and its customers. The region wants and expects service at a high reliability level. The BPA Reliability Criteria for transmission lines, substations, and control set the standards for design of these transmission system facilities. Like the planning criteria, the design criteria are intended to achieve cost-effective system reliability.

The BPA system is planned to satisfy both BPA and WSCC reliability criteria. The WSCC Reliability Criteria set the limits that disturbance(s) on one system can have on another system. BPA and other WSCC utilities are required to meet these

standards through coordinated planning of their present and future transmission systems.

C. Loads

Load growth is a combination of a projected trend over some period, usually 20 years, punctuated with unplanned new loads spurred by some commercial opportunity, like a new industrial plant. Forecasts of loads for each utility and point of delivery are prepared by BPA's Area Offices and compiled by the Office of Energy Resources, which also adds adjustments to the forecasts to reflect extreme weather assumptions. Engineering is responsible to provide transmission facilities to reliably serve BPA's existing and new load growth. New or unexpected load growth often demands a quick response. A major effort is currently being undertaken to provide for unexpected growth in the Puget Sound Area. BPA system planners are learning from the Puget Sound situation and are establishing new levels of coordination with planners from the other area utilities. This will result in a better understanding of future growth and transmission requirements in Portland and other expanding urban areas.

D. Resource Integration

The Pacific Northwest faces resource uncertainties in the next decade with the growing northwest loads, the endangered salmon species listing, and other competing uses of the hydro system. BPA has initiated a Competitive Acquisition Program, intended to acquire 300 MW of new resources.

BPA would provide for interconnection of new facilities to the BPA system, insuring that reliability requirements are met. Design issues, costs, system reinforcement requirements, and interconnections with other utilities must be part of each proposer's plan. Many of these resource providers, while able to originate proposals that meet Engineering's screening criteria, will have no experience with a complex system like BPA's. Creative interaction with each provider will be required, to make sure all important engineering details are adequately communicated.

Engineering will analyze the transmission and interconnection requirements for these proposals. The location of resources is also important in determining whether additional main grid system reinforcement will be needed. Engineering will provide oversight to ensure reliability and sound engineering practices are adhered to in integrating new resources.

It is estimated that resource acquisition programs will provide in excess of 300 MW of new generation over the next 4 years, and as much as 1000 MW over the next

decade. It will continue to involve considerable effort for engineering to decide how these resources can be integrated into the transmission system. The BPA Reliability Criteria and the Small Generation Integration Standards provide BPA engineers with standards for transmission, controls, relaying, metering, and other critical requirements for integrating generation facilities.

E. Environment

The National Environmental Policy Act (NEPA) was enacted in 1970. NEPA established a system of evaluating the effects a project will have on the environment. In the years since NEPA, environmental sensitivity has increased to a point where the public is reluctant to accept new alternatives with a high environmental impact. The Department of Energy is currently in the process of developing additional regulations governing the procedures used to implement NEPA.

BPA has responded to environmental concerns in a direct and open manner. During project development and planning, public meetings with BPA engineering staff are held to obtain feedback on alternative designs. In most situations, there are environmental considerations which will influence the design of a project. These environmental issues are addressed and mitigation measures are integrated into the technical design and planning. The environmental process can add time to the schedule of a project, but the result is an improvement in the overall design of a project both from an environmental and public perspective.

Public and industry concern about possible health effects from electric and magnetic fields (E/MF) is an issue that is being addressed within BPA. Scientists are continuing research to determine if there is a link between magnetic fields from AC power lines and certain types of cancer.

F. Public Involvement

Prior to the 1970's, transmission system planning was done with limited public input to the process. When the transmission system needed reinforcement to perform reliably, action was taken to build new transmission lines and substations.

In order to satisfy regional needs and develop the most efficient transmission system, BPA has entered into an era of regional problem solving. Information is gathered from all interested and affected parties. In addition to transmission, other solutions such as conservation, load management, and local generation are considered in the planning process.

The Puget Sound Area Electric Reliability Plan exemplifies an open planning process. Engineering has worked with representatives from the four Puget Sound utilities, conservation and resource personnel within BPA, and the public to develop a 10-year plan for serving the growing load in the Seattle area. BPA personnel met with the public to gather information used in the decision process. This has resulted in alternative solutions to solve the reliability problem in the region.

Communicating with the customer is a regular part of the planning process. Technical requirements must be explained in a way the public can understand. BPA engineers then examine all the alternatives before making a decision.

Engineering personnel are active in the public involvement process at the earliest stages in a project. These investments of engineering resources are in addition to BPA's annual PIP presentations, where BPA managers describe their programs and budget to the public and invite the public to discuss issues with BPA.

G. Competitiveness/Cost Effectiveness

It is critical for BPA and our customers to be competitive in the future. To meet that goal, Engineering will continue to concentrate on providing a cost effective, reliable transmission system that will serve our customers' needs. Engineering will continue to seek cost effective methods to optimize the existing system. This will require technically innovative applications such as sophisticated remedial action schemes, static var compensators, and the use of Flexible AC Transmission Systems (FACTS).

H. Human Resources

The electric utility industry is dependent on and employs almost all of the areas of advanced technology available today. Many utility projects combine these areas and include socio-economic factors in addressing the increasingly complex and interdisciplinary issues surrounding planning, design, engineering, construction, operations and maintenance of electrical energy systems.

The technical human resource challenges facing utility management can be analyzed by addressing three questions: 1) where are the future technologists coming from given the low interest in science, math, and engineering at the pre-college level; 2) how to identify and bring new college hires to full performance with full orientation on current utility practices and issues; and 3) how to maintain and update the skills of our current technical workforce so that they can fully perform.

The human resource concerns become even more pressing with analysis of BPA's current workforce in the Office of Engineering. Among Engineering's current 475 permanent employees, approximately 10 percent are eligible for retirement during 1992. During the period of 1993-1996 an additional 13 percent become eligible. By the end of the decade, 43 percent of the current Engineering workforce will be eligible to retire. The continuing high workload levels forecast for the same period and the growing complexity of the work suggests that almost half of the Engineering workforce will be renewed in the next 10 years. Engineering is pursuing some and considering other innovative activities to direct more students to science, math and engineering careers. To increase the technical skills of our current workforce, Engineering developed accelerated orientation for new technical workers, and is studying advanced degree programs and continuing training for the technical staff.

I. Safety

Safety will continue to be a priority in the planning, engineering, design, and testing of all BPA facilities. This will include the engineering effort required to ensure compliance with changing codes and regulations.

III. OFFICE OF ENGINEERING WORKLOAD

A. Transmission System Development

BPA's Transmission System Development (TSD) program provides for all additions and upgrades to the federal transmission system in the Pacific Northwest, allowing reliable service to be provided to Northwest industrial users and utility customers. The program also provides for the sale and exchange of power to and from the region.

There are five basic kinds of BPA facilities: 1) main grid, for bulk power transmission, mostly 230 kV and above; 2) interties, the 500 kV and 230 kV interconnections with other regions; 3) area service networks, the local load carriers, 230 kV and below; 4) customer service, the substations and links between BPA and its customers; and 5) system control and communication facilities required to operate the system.

BPA has 14,800 miles of high-voltage transmission lines and approximately 400 substations. This investment requires annual budgets to meet and sustain the growing demands on the power system. Engineering develops a budget summary that provides a general, five-to-ten-year forecast of system activities; at three years out, the specific budget, with a close approximation of budget dollars is issued; at two years out, those figures are refined, and then finalized for authorization. The Appendix to this document lists the main grid and area projects planned for the next 10 years, including basic justifications, cost estimates, and year of estimated energization. It also provides a listing and estimated costs of system controls projects through 1995. The list shows a schedule of capacity and control-improving additions such as transformers and breakers in existing substations, and modernizing safety-enhancing and reliability-improving elements in those facilities.

A number of new building facilities are planned for the next 10 years to replace and upgrade aging and inadequate existing structures. The most significant of these will be a new training and support services building and new chemistry and electronics laboratories at Ross Substation in Vancouver, Washington. These new facilities will accommodate BPA's increased operation and maintenance training needs and the increased emphasis on environmental and low voltage electronic equipment testing. The laboratories already provide major support to the Offices of Engineering and Operations, Maintenance and Construction (OM&C) and for the R&D program. This workload will be growing in future years. Also planned for completion within the next five years is a new facility (Alternate Control Center) to replace the Eastern Control Center at Moses Lake, Washington. This new facility will provide redundancy and backup for the Dittmer Control Center in Vancouver. In the event

of a catastrophic failure at Dittmer, the Alternate Control Center will also be capable of providing complete power generation control and scheduling.

Increasing load growth, maintenance and replacement needs, coupled with environmental and public concerns will pose a challenging resource allocation problem. Table 1 (Appendix B) shows proposed TSD expenditures from 1989 through 2001. The upsurge in TSD expenditure is clearly reflected, with primary increases in main grid and area reinforcements. The emphasis will be on strengthening the current system, and improving system operating efficiencies.

How the system evolves over the next decade is primarily based on load growth, the system's physical condition, and new generation sources. The TSD program emphasizes the pursuit of the most cost effective and technically sound equipment, including a continued emphasis on Research and Development. Increased customer communication and inter-utility cooperation are seen as the best ways to anticipate and meet future system needs.

B. System Replacement, Operation, and Maintenance

i. Capital Replacement Program

Achieving an improved physical condition for the aging transmission system will be accomplished through an Engineering commitment to BPA's 10-year Replacement plan. Up to 30 percent of Engineering's resources will be dedicated to this effort over the next decade. OM&C and the Areas have identified a multitude of system components and facilities that, either by regulation, duration of service, or failure history, need replacing over the next 10 years. Engineering will plan and design the replacement of an average of 50 power circuit breakers per year, which may also include the upgrade or replacement of related substation facilities. These are technically demanding installations which require cooperation between Engineering, OM&C, and the Areas. Table 2 (Appendix B) shows the extensive Engineering commitment of budget and staff to the Replacement Program.

In many instances, replacement will involve not just a single piece of equipment but a whole, or a substantial part of a whole system. Replacements must also be integrated with other systems of varying age and resilience. An example of this is the Celilo HVDC Terminal work, where aging main circuit equipment and analog controls will be incrementally replaced over the next 10 years to provide additional life for the 1960's vintage mercury arc converters. In contrast, the recent Celilo Expansion Project added 1100 Megawatts of additional capacity by utilizing new thyristor and microprocessor technologies. More frequently engineers are

challenged to compatibly integrate the operation of the old and new systems without interruption of service.

Engineering will also be involved in the design of oil spill containment facilities, roof replacements, and heating, ventilating, and air conditioning systems over the next decade, and is assisting with Level I Hazardous Material Assessments, Spill Prevention Control and Countermeasures (SPCC) Plan development, dry well inventories and closures and National Pollution Discharge Elimination System (NPDES) surveys.

Replacement will not necessarily be in kind, but will incorporate changes in technology and system requirements. Equipment chosen will be cost effective and have the capacity to handle BPA's future system needs. BPA Engineering will help to choose the technology which will integrate best with existing technology, write the specifications and develop the interfaces to make both technologies operate harmoniously. BPA Engineers and technicians will be trained thoroughly in the application of new technologies.

Several maintenance headquarters, such as Longview, Kalispell, and Covington, are scheduled for replacement or upgrade due to their age or expanded needs. Completion of these major facilities improves the capability, safety and productivity of construction and maintenance personnel. These new facilities increase the usefulness of existing facilities by making available additional storage and work areas needed to construct, maintain and service the increasingly complex electrical system.

ii. System O&M

At least three different federal requirements -- the Toxic Substances Control Act (TOSCA), the Resource Conservation Recovery Act (RCRA), and the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) -- can be in effect on any given hazardous waste clean-up assignment. These requirements are, and will be, changing during the next 10 years, making it difficult to plan appropriate long term responses. As the science of measurement becomes more precise, some wastes will become more detectable at much lower levels, provoking increasingly stringent standards.

BPA's laboratories maintain oversight on the effects of these regulations, as it does with a multitude of standards and specifications. Major areas of cleanup activity for the laboratories include solvents and other industrial chemicals and polychlorinated biphenals (PCBs). Cleanup of PCBs occurs when an old PCB-laden capacitor is changed out for a newer, non-PCB version. Most of BPA's older capacitors have

already been replaced, but clean-up of contaminated soils may increase with more stringent government regulations. In addition, the laboratory has embarked on a program to find a substitute for the pervasive industrial solvent tri-chloroethylene, which makes up a large percentage of BPA's hazardous waste.

C. Support for Other Programs

i. Fish & Wildlife

BPA Engineering provides a wide range of engineering, architectural, surveying, and mapping services in support of the Fish and Wildlife program. Engineering helps protect wildlife in transmission corridors by working with state and Federal Fish and Wildlife services to insure minimum disturbances. Technical solutions such as tiered line stacking have been designed to make BPA lines less of a navigational hazard for migrating birds, and towers have been raised to preserve habitat for elk.

Engineering has completed the design for the first two fish hatcheries at Roosevelt Lake, with others being considered. The technology in this area is rapidly changing. BPA is looking at the use of "natural" hatcheries that try to enhance the natural runs in selected rivers. Engineers are also involved in the design and installation of innovative new fish screens that keep migrating fish out of irrigation ditches. Designs to aid fish survival will be a major ingredient of the '90's for BPA Engineering.

ii. Energy Resources

BPA has recently undertaken an aggressive program to reach and maintain a load-resource balance through the 1990's. This will be accomplished by several actions which impact the Office of Engineering workload. A competitive bidding process has resulted in a list of 27 conservation and generation projects for potential acquisition by BPA. Of these, 300 average megawatts will be selected for integration into the transmission system. An additional 800 average megawatts of resource options will be optioned through the Resource Contingency Program in the near future. There is also a geothermal pilot program and a billings credit program which are designed to add new generating resources or provide energy savings. Finally, BPA is looking at exchanges of power or capacity with utilities in California or elsewhere as a source of energy. All of these acquisitions require evaluation by planning engineers to determine the effects on the transmission system and the best plan for integrating them into the system. Engineering may also be involved in analyzing environmental impacts or equipment changes that would be required because of the cumulative effects of new resources on the main grid system. Even

when other utilities acquire a project, BPA will ultimately be involved in assessing the impact to our system.

The Columbia River Treaty with Canada requires that the Canadian Entitlement to downstream power benefits be returned to British Columbia. In 1998, the U.S. is obligated to return as much as 126 MW to Canada, increasing to as much as 1400 MW in 2003. BPA and B.C. Hydro are studying various alternatives for returning this power to Canada. Any of these alternatives will likely have an effect on the transmission system and will require additional facilities.

iii. Power Sales

Engineering supports the Office of Power Sales in a variety of ways. Power contract negotiations and rate development require significant technical content which requires engineering analysis. Transmission system impacts of marketing capacity or energy to utilities outside the region, possibly in exchange for energy, must be determined. A key objective of BPA in the next few years is finding a way to respond to the demands for open transmission access which will have implications for the TSD program as well as power and wheeling contract terms and conditions.

iv. Environment

On February 2, 1990, the Secretary of Energy issued a notice in which he called for significant changes in the way elements of the Department of Energy (DOE) were to fulfill their responsibilities under NEPA. As part of this effort, the Department has been developing regulations governing the procedures that must be used to properly implement NEPA. Previously, the Department had relied on guidance that did not carry the force of formal regulations. It is expected that the regulations will be finalized and become effective during the spring of 1992.

Adapting to the requirements of the DOE regulations will require some adjustment by BPA. One emphasis involves closer coordination with state agencies. Another new requirement is that implementation plans for environmental impact statements must be made available for public review. Also, there is now a requirement to prepare a formal plan for accomplishing and monitoring the effectiveness of mitigation features discussed in environmental documents. The results of this monitoring must be reported to the Department annually.

Accordingly, much of the environmental effort in the Office will now be directed toward implementing the new DOE regulations, strengthening our efforts for involving the states and the public in planning our activities in an environmentally sound manner, and directing significant attention to the challenges of improving our

ability to mitigate environmental impacts that cannot be fully avoided. We will also be going through a period of adjusting to new environmental requirements and will be seeking ways in which to improve our efficiency in accomplishing our environmental goals. This will include efforts to find ways in which the amount of time required to complete procedural requirements can be shortened without compromising the quality of our decision making.

Environmental issues likely to be of particular concern in the future include: 1) the question of potential human health effects of electric and magnetic fields (E/MF) associated with transmission lines; and 2) the protection of wetlands. Public concern over the former have created significant challenges for BPA in siting transmission facilities even in relatively sparsely populated areas. We are currently considering the development of an E/MF Research and Demonstration Center. The center is intended to help the public and utility representatives to better understand a complex variety of E/MF issues ranging from effects on property values to potential health concerns. We are also addressing this public concern by developing appropriate brochures, fact sheets and an update of BPA's "Green Book" (a review of the literature on E/MF). In addition, we have an ongoing research program to assess potential health effects. We are continuing to explore and apply ways to better limit E/MF exposure through both project siting and project design decisions.

In the area of wetland protection we are currently initiating the preparation of a wetlands inventory on property owned by BPA. The Office's computerized Geographic Information System is at the heart of this effort. The data collected on this system will enhance our ability to avoid wetland areas. In those instances where impacts cannot be fully avoided, we are developing improved means for minimizing and mitigating impacts.

We will address other environmental issues during the coming decade in response to both public concerns and our increased understanding of how our actions impact the environment. Our goal will be to recognize these issues as early as possible and to respond to them effectively and responsibly in a spirit of cooperation and trust with the public and our customers. To create the opportunity for this type of partnership, we will make every effort to communicate effectively and frequently with our customer and public planning partners. We recognize this means we must effectively receive and consider, as well as provide, relevant information.

IV. STRATEGIES

A. West Coast Vision/BPA Transmission Strategy

The West Coast Vision was developed through meetings over the last few years between utilities, regulators, and environmental groups in British Columbia, California, and the Northwest. While a final statement of the Vision has not been published, the concept is summarized as follows: Cooperating for mutual economic and environmental benefits, West Coast electric utilities will work together to provide least-cost energy services.

Following the 1991 BPA Strategic Planning Session, BPA management expressed a Business Goal for Transmission which states: BPA and the NW utilities will cooperatively develop and achieve the operation of a reliable, low cost, environmentally sound NW transmission system which facilitates a competitive and efficient wholesale power supply market.

Implications of the West Coast Vision and BPA's Business Goal for Transmission include: 1) additional network and intertie transmission to allow for the economic and sound development of resources; 2) completion of mutually beneficial arrangements for exchanges of capacity or power for energy; and 3) additional time and workload required for open, cooperative regional planning.

To meet BPA's Vision and Goals, Engineering will actively promote the planning, construction and operation of a more integrated west coast power system. This includes conducting all transmission systems planning from a "one-utility" perspective. We will participate with our customers and the public to develop plans in the best interest of BPA, and also in the best interests of the West Coast as an integrated power system. Maximizing opportunities to share in the planning of transmission facilities will avoid unnecessary duplication. Cooperation will include designing facilities, sharing technology, and utilizing the experience of others when possible. We will promote: 1) transmission access to allow the most efficient use of the region's transmission facilities and seek ways to craft ownership and operating agreements that accomplish this; 2) maximum sharing of operational information between utilities through interutility data exchanges; and 3) opportunities to share in the research and development of power system technologies including use of our BPA Laboratories as a regional R&D center.

Engineering will utilize technical expertise to maximize use of the existing transmission system before building new facilities. This includes the use of new technologies such as Flexible AC Transmission Systems, system reactive construction to provide voltage support in lieu of new transmission, and more

sophisticated controls to allow operation of the power system at higher capacities. We are seeking ways to upgrade the capacity of existing transmission facilities and transmission corridors.

Engineering is committed to effectively utilizing research and development with direct applicability to the power system. These research projects will be conducted with the view towards maximizing system efficiencies and promoting cost effectiveness.

Lastly, BPA and Engineering will continue to utilize its technical expertise for the best interests of the power industry by promoting the participation by BPA professionals in appropriate technical societies and standards committees.

B. Transmission System Reliability

Engineering develops efficient methods to provide the appropriate level of transmission system reliability. These will include the construction of new cost-effective transmission, as well as maximizing the use of existing transmission through the use of new technologies and system controls.

There are a number of major new 500 kV transmission projects identified for construction in the next 10 years as shown in Appendix A. These projects are necessary to maintain reliable service to loads, provide for the integration of new resources, and to facilitate the sharing of resources between regions. As a result, Engineering is examining the major design parameters which influence our line design. This will include looking at tower design, life-cycle economics, maintainability, reliability, and overall efficiency of designs.

Engineering will continue to promote the development and use of digital computers as a means of increasing the sophistication of power system controls. This includes the increased use of computers at the control centers, at the substations and in the equipment itself. We will make the maximum use of our regional control centers to promote system efficiency and system reliability by: 1) enhancing the capabilities of control center systems; 2) providing backup of critical functions between control centers; and 3) integrating these systems to avoid duplication of control equipment.

Engineering will foster the development and use of computer-based systems and operational data networks that gather data, as well as expert systems that utilize specific decision models to analyze the data.

As the transmission system becomes more reliant on sophisticated controls for its operation, the importance of highly reliable control equipment becomes more

critical. We will use fault tolerant systems where prudent to increase the reliability of critical control systems. A fault tolerant system is designed to prevent a single component from causing the entire system to fail or misoperate. They provide maximum control equipment reliability with a minimum of additional investment.

We will continue to use advanced system protection technologies and remedial action control schemes to improve the reliability and capability of the existing transmission system and forego the construction of new transmission if possible. We are increasing our funding in the systems controls portion of the Transmission System Development program in the upcoming planning period to foster these technologies.

Engineering will support development and use of Reliability Centered Maintenance systems by OM&C and the Areas. These systems continuously monitor the usage of power system high voltage equipment to determine appropriate maintenance intervals, and key equipment parameters to detect and predict equipment problems. These methods will significantly reduce costly equipment failures and will allow maximum use of high voltage equipment since preventative maintenance will only be performed when necessary.

We will continue to seek better ways to design our buildings for maximum efficiency, using solar energy, waste heat recovery, and other technologies to meet or exceed the Model Conservation Standard.

C. System Loads in the Next Decade

Engineering will continue to develop, refine and test its power system models to assure that they reflect the changing operating conditions associated with diverse new resources, more complex grid interconnection/interaction and increased loads.

Engineering will develop long range load models that provide adequate planning lead time for the development and budgeting of new transmission to meet projected new growth.

Engineering will develop research and development programs in collaboration with the Department of Energy and other institutions for the rapid development, demonstration and implementation of new technologies. These projects will focus on maximizing use of existing rights-of-way and transmission and distribution facilities. Examples include accelerating R&D in control and operation technologies. Target areas include measurement (sensing), communications, information processing, including advanced computation and visual presentation, advanced components, and new power system methodologies. Another example is

the high capacity transmission embodied in high voltage direct current (HVDC) technology. The purpose of this research is to identify short term and long term research and development issues, activities and priorities to reduce the cost of construction and operation of HVDC transmission. A specific objective of this research is to reduce HVDC terminal cost by as much as 40% of current costs so that it can be used to increase transmission capacity over existing corridors and be considered as an alternative to AC over shorter intra-regional routes. Engineering will continue to actively pursue these as well as other technologies over the next decade that allow greater use of the existing transmission systems and increase the cost effectiveness of new technologies.

D. Integration of New Generation Resources

Engineering will actively promote and develop ways to integrate new generation sources in a cost effective and environmentally sound manner. In the past, Bonneville has had to integrate large generation sources, such as hydroelectric and thermal plants. Now Bonneville must position itself to integrate smaller generation sources, often with characteristics different than the larger hydroelectric or thermal plants. These can include wind, geothermal, cogeneration, etc. Each of these may have their own characteristics and requirements for control and protection. Engineering will refine planning models to accurately project impacts to the power system for these varying size and types of generation. Engineering will actively investigate, jointly develop, and conduct necessary technical studies to efficiently integrate new resources.

E. Environmental Stewardship

Engineering will continue to act as a responsible environmental steward. Power transmission facilities and the technologies they employ will impact the environment. Engineering will utilize responsible design for these facilities to insure that high voltage equipment is applied in an environmentally acceptable manner. This will include planning and siting of transmission facilities to factor in the impact on any endangered species and other factors such as historical sites and wetland areas.

Engineering will continue to investigate the effects of electric and magnetic fields (E/MF). Facilities will be designed to minimize exposure to magnetic fields where possible. In all cases, Engineering will strive to promote full consideration of the impacts of electrical technology. We will seek to design our facilities to minimize other impacts such as radio and television interference.

Other areas of environmental consideration include replacement of underground fuel tanks, development of oil spill containment around high voltage equipment, use of alternatives to treated wood poles, and performing hazardous waste cleanup. Also, we will continue to purchase equipment that is environmentally safe, such as non-PCB filled high voltage equipment. Finally, where practical, we will minimize the visual and audible impacts of our facilities.

In summary, we will engineer our systems to provide reliable, high quality energy to the region, while being sensitive to minimize all impacts to the environment and people of the northwest.

F. Public Involvement

We will engineer a transmission system to meet the future needs of the region, while endeavoring to promote awareness and involve the public in our process. Specifically, we will continue to inform and involve the public in our planning decisions. Examples include recent planning projects in the Puget Sound and Eugene areas. We are committed to balancing demands for electricity with other public interests. We will utilize the PIP process and other vehicles to discuss our plans with the public in a timely manner. Feedback from this process will be considered in our planning and designs.

G. Cost Competitiveness

Engineering realizes that the cost effectiveness of our energy will directly affect the ability of our customers to be cost competitive in a regional as well as global market. We will strive to make our energy services as competitive as possible by establishing a flexible engineering program that insures a predictable and competitive long term power supply.

High technology computer-based systems such as expert systems, advanced technologies such as data networks, fiber optics and satellites, and increased levels of control integration will be used on an increasing scale. Use of advanced control and measurement technologies will maximize power delivery capacity. These initiatives are intended to increase the effective control of the power system in a competitive manner.

We will maximize the use of our transmission system load characteristics unique to the region by planning and engineering the transmission system to take advantage of these features. For example, because seasonal peak loads vary between the Pacific Northwest and Pacific Southwest, the transmission system is used to facilitate the exchange of power between the regions to minimize duplicate generation facilities.

By designing maintainability into the systems, the overall life cycle costs can be reduced. This includes the use of Reliability Centered Maintenance techniques described earlier.

We will refine standards to improve cost effective design of transmission facilities, resulting in more efficient structures, lower construction costs, and greater integration of controls.

Multi-year material contracts will be used where possible, allowing the development of more standardized designs that will be used for several years. This will reduce the overall acquisition time and associated costs. It will also allow us to buy in greater volume, achieving more consistent quality and developing longer term relationships with our suppliers.

In all aspects of planning, engineering, and designing we will seek to continuously improve the quality of our product. This continuous incremental improvement will ultimately result in a more cost effective system.

H. Management of Human Resources

Human resources are Engineering's most valuable asset. Thus, we will seek ways to maximize the quality and efficiency of our technical staff. We will continue to use Architectural and Engineering contract services and other engineering consultants to accomplish peak workload while maintaining a core of highly qualified technical staff with specialized expertise. The continued development of our technical staff will assure that we have the necessary expertise to meet future Engineering demands. There is a significant level of attrition expected over the next few years as a segment of the staff nears retirement. We are developing understudies to assure the transfer of this expertise so that it will not be lost.

We will continue to use advanced tools that leverage the talent of our technical staff. This includes the increased use of ADP and the use of sophisticated engineering workstations, computer aided design (CAD) terminals, and artificial intelligence. These systems will enable engineering personnel to achieve even greater efficiency and to further develop their skills.

Realizing that it is no longer sufficient to wait for the new college graduates, we will continue to seek innovative ways to attract and train new talent. We are developing long term relationships with promising students to insure a pool of highly qualified people to select from in the future. Current examples include the Saturday Academy Apprenticeship and Cooperative programs for high school students and

the Junior Fellowship and Cooperative Programs for college students. Using Universities on joint projects provides valuable work-related experience to them as well as useful results for BPA. We will continue to pursue these and other programs to insure a quality, diverse workforce for the future. We will also utilize local universities where possible to attract and train students within the local community.

We will continue to promote the use of other outside specialty technical resources where prudent, including organizations like the Electric Power Research Institute (EPRI).

I. Safety

Engineering is committed to insure the safety of our employees and the public. We will pursue research and development projects that will improve the safety of our system. Examples are the use of safer technologies such as explosion proof 500 kV equipment. We will continue to investigate and monitor high voltage equipment failures to better specify and engineer high voltage systems.

Safety efforts continue in the areas of: 1) measurement and improvement of substation grounding systems to minimize the localized impacts of system disturbance and the risk to personnel in our facilities; 2) the handling of hazardous waste and the design of substation facilities that will minimize the exposure to any hazardous materials; and 3) active participation in and promotion of industry standards that insure greater safety.

V. CONCLUSION

This document describes the issues and trends that affect the Office of Engineering in accomplishing its program. This background is intended to give perspective to the various projects listed in Appendix A and to convey strategies to address these issues and trends.

The projects and their costs as listed in Appendix A are preliminary. There will be opportunities to discuss these projects as well as the issues raised in this document with Office of Engineering management in preparatory sessions for BPA's Programs in Perspective (PIP) meetings scheduled in June 1992. This Draft Plan will be modified and a final document released following any program level changes after the PIP process.

**TSD PROGRAM
MAIN GRID PROJECTS
MAJOR CONSTRUCTION ITEMS AND JUSTIFICATION**

<u>LOCATION</u>	<u>CONSTRUCTION</u>	<u>JUSTIFICATION</u>	<u>ON- LINE</u>	<u>BUDGET</u> ¹ (\$ million)
PORT ANGELES SYSTEM ADDITIONS	At Fairmount, development of 230-kV yard to breaker-and-a-half bus arrangement with 7 power circuit breakers to loop in existing lines; reconnect transformer Bank 2 to 115-kV Bay 4 with new 115-kV low side breaker. At Olympia, upgrade 230-kV capacitors from 105 to 336 MVARs by replacing existing PCB-contaminated caps.	Prevent overloading and improve system reliability in Upper Olympic Peninsula. Provides voltage support for existing loads.	1992	7.2
3RD AC SYSTEM REINFORCEMENT, HANFORD	Reterminate Vantage 500-kV line from Bay 2 to Bay 1; removal and replacement of WPPSS-owned 500-kV circuit breakers in Bay 1; removal of central circuit breaker in Bay 2.	Prevent system instability in case Grand Coulee and Vantage lines are lost from mid-breaker failure. Allow Intertie transfers up to 4000 MW.	1992	1.4
3RD AC SERIES COMPENSATION AND TRANSMISSION	500-kV series capacitor installations at Sand Spring, Fort Rock, & Sycan.	Compensation stations up-rated to support higher Intertie power transfers. In conjunction with PGE construction.	1992	10.9 BPA, 17.7 PGE
EUGENE- MEDFORD	New Alvey 500-kV switchyard with three 500-kV PCBs & replacement of three 230-kV PCBs.	To meet PP&L load requirements.	1992	66.9 ²
	500 KV PCBs, shunt reactors, and series capacitors at Dixonville and Meridian substations. 500-kV line from Alvey to Dixonville, 60 miles.		1993	

¹Total Projected Cost. (Direct cost including escalation and inflation)

² This represents BPA's 50% share of the joint BPA/PP&L project cost.

EUGENE-MEDFORD 500-KV INTER-CONNECTION	A 500-kV single-circuit, Dixonville-Meridian line, 76 miles.	Adds 500-kV line from Dixonville to Meridian to serve the 3rd AC & Southern Oregon loads. Increase of 1600 MW in Intertie transferability.	1993	66.9(Additional PPL construction)
3RD AC INTERTIE REINFORCEMENT	Marion-Alvey series compensation; expand Grizzly, Malin & Slatt Substations; construct new Captain Jack Substation & transmission line.	The Interim Interconnection Agreement between BPA, PacifiCorp, PGE TANC and Western has a December 1992, date for interconnection and operating the AC Intertie at 4000 MW.	1992	
		Increase to 4800 MW in Intertie transferability between the Pacific Northwest and Northern California. Joint project with California utilities.	1993	70.1
LONGVIEW SYSTEM REINFORCEMENT	Adds one 500/230-kV transformer, four 500-kV PCBs & three 230-kV PCBs; replacement of nine over-stressed 230-kV PCBs; re-termination of a Longview and a Clatsop line at Allston.	Increase transformer capacity in Longview Area to serve growing loads; prevent overloading Chehalis-Longview 230-kV line in event of existing Allston transformer outage prevents overloads in case of Allston-Keeler outage.	1993	16.1
ECHO LAKE SWITCHING STATION	New switching station with four 500-kV breakers and two 500-kV shunt capacitor groups; loop in Monroe-Raver 500-kV line and Maple Valley section.	Puget Sound voltage support,, more reliable switching of Monroe-Maple Valley Tap-Raver lines; provide reactive margin in Puget Sound.	1993	18.9
MAPLE VALLEY STATIC VAR--SYSTEM REACTIVE	A complete 300 MVAR SVS, turnkey; a 230-kV terminal with PCB.	Dynamic voltage support of Seattle area, reduces exposure to load loss in case of generator or line losses during peak loads, even with additional cross-Cascade transmission.	1993	26.1
SLATT THYRISTOR-CONTROLLED SERIES CAPACITORS (TCSC)	Install TCSC in Slatt-Buckley No.1 500-kV line; field test and evaluate.	BPA hosting EPRI FACTS project, to evaluate Subsynchronous Resonance (SSR) control, enhance power system transient stability, damping, control of power flow, & stability margin for DC outages	1993	BPA, 3.2 EPRI-GE, 10.0

KEELER STATIC VAR--SYSTEM REACTIVE	A complete 300 MVAR SVS, turnkey; a 230-kV terminal with PCB.	Dynamic voltage support of Portland area, reduces exposure to load loss in case of Trojan loss coupled with Centralia off-line or other failure.	1993	23.9
TRANSMISSION SYSTEM EFFICIENCY	Develop 1.5 Avg MW per year of the most cost effective transmission system upgrades including reconductoring projects.	Efficiencies gained reduce the need for equivalent new generation.	1993-1997	20.0
SCHULTZ SUBSTATION	New 500-kV switchyard with twelve 500 kV circuit breakers; loop Grand Coulee-Raver 500-kV double-circuit lines 1 & 2, Vantage-Raver & Sickler-Raver 500-kV lines into new station; add series compensation to Grand Coulee-Raver lines; retire Naneum switchyard.	Support for Puget Sound voltage instability, in conjunction with Puget Sound Area Electric Reliability Plan, helping to defer a cross-Cascade transmission line. Reduces transmission system losses.	1994	52.4
NORTHWEST MONTANA-NORTH IDAHO SUPPORT	Six 115-kV PCB additions; new 230/115-kV, 200 MVA Sand Creek Substation; double-circuit, 230-kV line, 58 miles, from Libby to Bonners Ferry, 230-kV PCB at Libby.	Satisfies System Reliability Criteria by preventing overload of TWWP's Cabinet Gorge-Bronx line and loss of load in event of Albeni Falls-Priest River outage.	1996	35.4
BELLINGHAM AREA REINFORCEMENT	Rebuild 12 miles of 230-kV to double-circuit between Bellingham and Custer; install 230-kV PCB at Custer & three 230-kV PCBs at Bellingham. Rebuild 25-mile Bellingham-Sedro-Woolley 230-kV tap to double circuit & install 230/115-kV transformer, two 230-kV PCBs and five 115-kV PCBs at Bellingham at PSP&L expense.	Reinforce 230-kV system between Custer, Bellingham & Sedro Woolley & improve reliability of local loads. Improve reliability of north to south imports from Canada. Increase capacity for imports and proposed future cogeneration. In consort with PSP&L.	1996	BPA, 28.6 PSP&L, 33.4
SEATTLE-OLYMPIA SYSTEM REINFORCEMENT	Construct a second 70 mile Paul-Raver single circuit 500kv line; add two 500kv PCB's at Raver and Paul.	Reinforce the 500 KV system between Raver and Paul to prevent overload of BPA's S. Tacoma-Olympia 230-kV line, and PSP&L's underlying 115kv system for a Raver-Paul outage.	1998	49.4

E. WASHINGTON REINFORCEMENT	Rebuild 15 miles at Bell end of Grand Coulee-Bell 115-kV lines 1&2 to single-pole double circuit;. Construct 15 miles of 500-kV double circuit on vacated Grand Coulee-Bell right-of-way; construct 150 miles of 500-kV single-circuit line from double circuit section to Ashe; 500-kV switchyard at Bell with three 500-kV PCBs; terminate new 500-kV line at Ashe with two 500-kV PCBs.	Increase BPA's east-to-west transfer capability. Reduce need to curtail eastern hydro & Colstrip generation. Essential for proposed BC Hydro Eastern Intertie.	1998	132.7
KING COUNTY SYSTEM REINFORCEMENT	Construct 500-kV single-circuit line between Monroe and Echo Lake along existing 32-mile line; add 500-kV PCB at Monroe; add two 500-kV PCBs at Echo Lake.	Prevent overloads on 230-kV system in case of Monroe-Echo Lake outage.	1999	30.6
EASTERN CANADA INTERTIE	94 miles of 500-kV transmission from Bell to Canadian border near Boundary; two 500-kV PCBs at Bell. BC Hydro will connect at border from Selkirk station. Other alternatives being considered are WWP's 230kv circuit option from Selkirk to Beacon, and BPA's 500kv line option from Oliver to Grand Coulee.	Provide capacity for Canadian Entitlement return. Increase transfer capability between BPA and BC Hydro by 1000 MW. Back-up for Custer-Ingledow 500-kV lines or cross-mountain lines.	1999	62.5
CHIEF JOSEPH TRANSFORMER ADDITION	Add 1300-MVA, 500/230-kV transformer, 500-kV breaker, 230-kV terminal & 230-kV breaker.	Eliminate possibility of Grand Coulee 500/230-kV transformer overload.	2000	13.0
NORTH SEATTLE TRANSFORMER REINFORCEMENT	Convert 12.8 miles of Sno-King 230-kV line to 500 kV; add 500/230 transformer & four 230-kV PCBs at Sno-King; loop Bothel-Sno-King-Maple Valley line into Sno-King. Add one 230-kV PCB at Maple Valley.	Support winter peak loads in North Seattle. Prevent overload of Monroe transformer, Monroe-Sedro tap & Monroe-Sno-King tap.	2000	16.8

PUGET SOUND
AREA
REINFORCEMENT

Replace Chief Jo-Snohomish 345-kV lines 3&4 with double-circuit 500-kV line, 133 miles; retire two 345/230 transformers and low-side switching each at Chief Jo & Snohomish; add four 500-kV PCBs at Chief Jo, five 500-kV PCBs and one 230-kV PCB at Monroe, & one 500/230-kV transformer & two 230-kV PCBs at Snohomish.

To prevent regional voltage instability during peak loads from line or generator losses. Reduction of system losses by 20 MW Avg or 60 MW peak.

2000 275.5

OLYMPIC
PENINSULA
REINFORCEMENT

Two 230-kV PCBs at Shelton; double-circuit, 500-kV, 15-mile line from Shelton intercept to Shelton Substation to be operated at 230 KV; construction of 6-mile section for new Olympia-Shelton 230-kV line; convert Olympia-Shelton section of Olympia-Kitsap 230-kV line to 115-kV; terminals, system controls, and protective equipment for Olympia and Shelton Substations.

Increases transmission capacity to Olympic & Kitsap Peninsulas. Prevents voltage collapse and loss of service in event of Olympia 500/230-kV outage.

2001 26.5

TSD PROGRAM
AREA AND CUSTOMER SERVICE PROJECTS
MAJOR CONSTRUCTION ITEMS AND JUSTIFICATION

<u>LOCATION</u>	<u>CONSTRUCTION</u>	<u>JUSTIFICATION</u>	<u>ON- LINE</u>	<u>BUDGET</u> ¹ (\$millions)
HEYBURN-HAY MILL SUPPORT	Construct 138-kV Heyburn-Hay Mill line, 4.6 miles; add two 138-kV terminals & breakers at Heyburn, & a 12.5-kV PCB at Hay Mill.	Improve reliability of radial loads to Hay Mill, & eliminates outage when single line is out of service. Reinforces Heyburn, eliminating need for Heyburn PCB-contaminated capacitors & breaker replacement.	1992	1.7
SNO-KING TRANSFORMER ADDITION	Add a 300-MVA, 230/115-kV transformer, a 230-kV PCB and a 115-kV PCB at Sno-King.	Prevent transformer overloading & increase reliability in Sno-King-Snohomish area.	1992	2.7
ALBANY TRANSFORMER SUPPORT	Replace existing three single phase transformers with new three phase 300-MVA transformer; replace PCBs in Bays 3 & 7.	Provide Albany area transformer support and solve Albany Substation noise problems. Upgrade breaker ratings	1993	3.6
MINIDOKA AREA SERVICE	Construct 138kv tap line, 3.2 miles, to East End Substation and 1.8 miles to Jackson Substation. Rebuild East End Substation to 138kv and temporarily install 138-34.5kv transformer at Jackson Substation.	Upgrades 34.5kv transmission system in the Minidoka area to 138kv. The Bureau of Reclamation is upgrading their Minidoka switchyard from 34.5kv to 138kv.	1994	2.0
CENTRAL SNOHOMISH COUNTY TRANSFORMER SUPPORT	Add 230/115 kV, 300 MVA transformer; add 115 KV and 230-kV transformer terminals with PCBs & switches; replace two 230-kV PCBs	Satisfy Reliability Criteria to prevent overloading existing transformer for single contingency outage. Correct PCBs for excessive fault values. BPA cost could be reduced with Snohomish PUD participation.	1994	4.7
HUNGRY HORSE- COLUMBIA FALLS LINE REBUILD	Rebuild 8.5 miles of Hungry Horse-Columbia Falls 115-kV line to 230 kV.	Integrate upgraded generation at Hungry Horse. Prevents overloads & reduces line losses. In conjunction with USBR.	1994	2.2

GIG HARBOR REINFORCEMENT	Remove Narrows Crossing; remove Cushman 2-Allyn sections of Cushman 2-Pearl 115-kV lines 1&2; install 300-MVA, 230/115 kV transformer, two 230-kV PCBs & two 115-kV PCB terminals at Shelton; construct 230-kV, double-circuit Shelton-Allyn line, 18 miles; acquire & repole Allyn-Narrows section of Cushman 2-Pearl line; add 10 MVAR of shunt capacitors at Narrows; construct new four-bay 115-kV Potlatch switching station & four 115-kV PCBs.	Tacoma City Light area lines are ending structural life. BPA will pick up the load from these upgraded lines. Joint TCL project.	1995	12.3
WELLS AREA SERVICE	230-kV lines from Midpoint to Carlin Area via Wells, in conjunction with Wells Area Electric, Sierra Pacific & Idaho Power.	Support increased load in Carlin /Quarry area, estimated to rise from 45 to 85 MW by 1999. This could become a joint project with SWIP and Sierra Pacific.	1996	40.4
COLUMBIA FALLS TRANSFORMER ADDITION	One 3-phase 230/115-kV, 100 MVA transformer bank; Five 230-kV PCBs; convert Hungry Horse - Columbia Falls line to 230-kV operation.	Provide sufficient transformer capacity needed with line upgrade.	1996	4.3
TRI-CITIES AREA REINFORCEMENT	Reconductor Horn Rapids tap-Ledbeder-Richland 115-kV line, 6 miles & reconductor Stevens Drive-Thayer Drive 115-kV line, 1.6 miles.	Prevents overloads for certain line outages during summer peak load periods.	1996	1.9
CHEHALIS TRANSFORMER SUPPORT	Replace existing 100 MVA 230/69kV transformer at Chehalis with a 250MVA transformer.	Reinforce 230/69-kV transformer at Chehalis	1996	3.8
MOSSYROCK GENERATION SUPPORT	Rebuild 17 miles of the Chehalis-Silver Creek line to double circuit; rebuild 4 miles of Chehalis-Mossyrock line to 230-kV double circuit; add 230-kV terminal and sectionalizing breaker at Chehalis.	Prevent overloading between Chehalis and Mayfield under outage conditions. Upgrade capacity and reduce transmission losses.	1997	9.3

SALEM-GRANDE
RONDE LINE
RECONDUCTOR-
ING

Reconductor Salem-
Grande Ronde 115-kV
line section, 28 miles.

Increase line capacity &
prevent winter peak
voltage problems.

1996 4.0

OKANOGAN
VALLEY
TRANSFORMER
SUPPORT

Add one 200-kVA,
230/115 transformer at
East Omak & one 230-kV
PCB at Chief Joseph

Service to Okanogan
Valley & prevents area
overloads.

1998 3.1

TSD PROGRAM

POWER SYSTEM CONTROL PROJECTS

MAJOR CONSTRUCTION ITEMS AND JUSTIFICATION

LOCATION	CONSTRUCTION	JUSTIFICATION	ON-LINE	BUDGET ¹ (\$millions)
BPA System	Operational Data Network, Phase 1.	Simplifies interconnection of control center data systems, reduces incremental communication costs, provides for data systems growth, improves field crew efficiency for restoring the power system after an outage.	1995	1.9
BPA System	Upgrade Remedial Action Scheme for Intertie loss during Import.	Import RAS schemes are "band aided" on RAS controllers which do not meet WSCC reliability standards.	1995	1.0
BPA System	Breaker Failure Protection Retrofit, Phase 8.	Mitigate explosive failures of 500 kV circuit breakers.	1995	1.6
BPA System	System Events Monitor, Phase 5.	Continuing program to provide diagnostic tools for analyzing the causes of control scheme responses to system disturbances.	1995	1.2
BPA System	Power System Database Maintenance System.	Consolidates three different data bases which currently duplicate common data.	1995	1.2
BPA System	Dittmer Control Center, Transient Energy Function.	Provides system data for dispatcher training and to enable dispatchers to operate the power system at increased transmission and intertie capability.	1995	2.6
BPA System	Alternate Route Comm. for Garrison-Colestrip	Complies with BPA and WSCC reliability requirements for alternate routing of communications for Remedial Action Schemes.	1995	4.3

¹ Total Projected Cost. (Direct cost including escalation and inflation)

BPA System	Toledo-Wendson Comm. Upgrade.	Existing communication circuits are marginal and most equipment in service is obsolete and no longer supported by the manufacturer.	1995	1.8
BPA System	Fiber Optic System Phase 1: Dittmer-Big Eddy.	Upgrades the existing "A" microwave system to provide required channel capacity to serve increasing BPA system requirements for communications.	1996	4.9
BPA System	Microwave RF Replacement Phase 10.	Existing equipment in service is nearing the end of its service life and is no longer supported by the equipment manufacturer.	1996	3.0
BPA System	System Events Monitor, Phase 6.	Continuing program to provide diagnostic tools for analyzing the causes of control scheme responses to system disturbances.	1996	1.8
BPA System	Operational Data Network, Phase 2.	Simplifies interconnection of control center data systems, reduces incremental communication costs, provides for data systems growth, improves field crew efficiency for restoring the power system after an outage.	1996	1.7
BPA System	Alternate Control Center, Data, Control and Comm.-Phase 1.	The control center building is being relocated. Power System Control equipment will need to be relocated or replaced with the building relocation.	1997	11.0
BPA System	Fiber Optic System Phase 2: Big Eddy-Alternate Control Center.	Upgrades the existing "A" microwave system to provide required channel capacity to serve increasing BPA system communications. (A Phase 3 to close the loop to Dittmer will be introduced as a later year proposal.)	1997	12.9 ²

² This estimated cost is based upon an assumption that the proposed Alternate Control Center (ACC) will be built at Moses Lake. The proposed fiber optic communication facilities are required even if the proposed ACC is not built which will most likely change the estimated cost. The estimated cost will also change if the proposed ACC is built at a location other than Moses Lake.

TSD PROGRAM
MAJOR BUILDINGS and SITE IMPROVEMENTS PROJECTS
MAJOR CONSTRUCTION ITEMS AND JUSTIFICATION

<u>LOCATION</u>	<u>DESCRIPTION</u>	<u>JUSTIFICATION</u>	<u>ON-LINE</u>	<u>BUDGET¹</u> <u>(\$millions)</u>
Ross Complex	Expand and Improve Covered Storage Building Z-669.	Additional square footage of storage area is required to store increasing inventory levels for insulators, PCB free bushings, and spare parts associated with transformers and breakers on the heatline. Emergency reserves will also be stored here.	1993	1.0
Ross Complex	Warehouse Z759, add High Density Storage.	Spare parts for SF6 gas circuit breakers require indoor storage with humidity control. The addition of high density storage will eliminate the need to continue to lease off site storage space.	1993	1.7
Ross Complex	New Storage Area North of Cold Creek.	Additional storage area is required to accommodate increasing stocking levels for construction work in progress and emergency reserve levels. Existing Warehouse outdoor storage areas will site additional proposed new storage facilities.	1993	1.6
Ross Complex	Expand Dittmer Basement	Additional space is required to relocate existing existing data processing systems, equipment operator area, and tape storage functions, and add needed air conditioned storage. Moving these functions away from the existing computer area will vacate needed space for equipment expansion, staging and testing areas.	1994	1.6

¹ Total Projected Cost. (Direct cost including escalation and inflation)

Ross complex	Utilities Upgrade.	The existing main trunk electrical and storm sewer systems need to be enlarged or expanded to accommodate the new building and site improvement projects planned at the Ross Complex.	1994	0.3
Ross Complex	Property Acquisition.	The existing complex is constrained for future development. The Division of Laboratories and the Warehousing activity are leasing off site facilities for storage. If additional property is not available for new storage facilities, leasing costs will continue and are likely to increase.	1994	1.3
Ross Complex	New Training and Support Services Building	As a result of changes in complexity of the regulatory environment and changes in technology, staffing increases have occurred at the Dittmer building creating over-crowded conditions. Support services activities have been pushed out of the Dittmer building and has hampered training , safety, personnel and materials management. Much of this support activity has contact with the public and needs to be centrally located and away from high security facilities, such as Dittmer.	1995	13.0
Alternate Control Center	Construct a new control center to replace the existing facility located at Moses Lake, Wash.	BPA needs to update its backup control monitoring capabilities to meet DOE requirements, prudent utility practices, and established reliability criteria.	1996	8.9

Ross Complex	New Parking Facility, Phase 1.	The construction of the proposed Training and Support Services Building (T&SS) will eliminate an existing parking area. Additional parking spaces are required to accommodate additional parking needs for T&SS along with existing parking for Dittmer. It is expected that increases in parking needs will come about from special activities such as training.	1997	0.5
Ross Complex	New Laboratory Facility, Phase I.	The space occupied by the existing laboratory facilities was not designed for its current use. The new facilities will eliminate overcrowding, poor ventilation, and inadequate storage and vehicle access. This facility will consolidate laboratory activities currently located in the North and South wings of the Ampre Building, Soils Laboratory and Carey Laboratory.	1998	11.8
Ross Complex	New Laboratory Facility, Phase II.	Phase II continues the facilities proposed in Phase I and coincides with the demolition and relocation schedule identified in the Ross Complex Building and Site Development Guide.	1998	4.2

SUMMARY, 10 YEAR TRANSMISSION SYSTEM DEVELOPMENT PROGRAM

(\$ IN MILLIONS)

MAY. 14, 1992 (PLAN) REV. 8

	FY 91 ACTL	FY 92	FY 93	FY 94	FY 95	FY 96	FY 97	FY 98	FY 99	FY 00	FY 01
BLI CCMG - MAIN GRID											
CR1027 EUGENE-MEDFORD	3.4	30.4	32.1	0.1							
CR1037 THIRD AC INTERTIE	21.7	23.6	10.9	1.0	0.3						
CR1214 E. WASHINGTON REINF.			0.7	0.6	26.0	34.6	54.1	16.0			
CR1225 E. CANADIAN INTERTIE			0.2	0.1	0.6	0.6	37.2	19.5	4.4		
CR1369 PORT ANGELES SYS. ADDN.	3.4	1.6	1.1								
CR1370 BELLINGHAM AREA REINF.	0.2	0.4	0.2	0.3	9.2	18.0	0.2				
CR1391 S.SEATTLE-OLY. REINF.		0.3	0.1	0.3	3.5	23.9	19.1	2.1			
CR1402 NW MONTANA/N.IDAHO SPT.	0.2	1.2	4.8	1.5	26.0	1.7					
CR1411 OLYMPIC PENIN. REINF.		0.1	0.1	0.1	0.1	0.2	0.2	0.3	13.3	9.7	2.2
CR1431 LONGVIEW SYSTEM REINF.	7.1	4.3	4.7	0.1	0.1						
CR1442 PUGET SOUND REINF.		1.1	0.5	0.5	0.5	2.0	80.2	96.9	51.8	41.8	
CR1452 N. SEATTLE TXF. REINF.		0.1				0.6	0.5	3.5	10.9	1.2	
CR1463 CHIEF JOSEPH TXF. ADDN.							0.5	1.2	9.8	1.5	
CR1473 KING COUNTY SYS. REINF.		0.1	0.1	1.1	2.6	2.4	2.6	13.1	10.5		
CR1481 ECHO LAKE REACTIVE STA.	2.2	9.6	7.1								
CR1492 SCHULTZ-PUGET REINF.		3.4	38.7	10.0	0.2						
CR1500 SYSTEM REACTIVE FAC.	12.8	68.5	18.3	11.6	12.0	12.7	13.3	14.0	14.8	16.0	17.0
CR154 STOCK MATERIAL	16.7	-1.9									
CR1600 TRANS/SUBS EFFICIENCY		1.2	3.4	4.0	4.0	4.2	4.4	4.6	4.8	4.8	5.0
CR1990 VARIOUS ADDITIONS *					10.0	20.0	20.0	30.0	60.0	80.0	100.0
BLI CCMG TOTAL	67.7	144.0	123.0	31.3	95.1	120.9	232.3	201.2	180.3	155.0	124.2
BLI CCAC - AREA & CUSTOMER SERVICE											
CR7088 TRI-CITIES AREA REINF.		0.1	0.1	0.1	0.7	0.8					
CR7119 GIG HARBOR AREA REINF.		0.2	0.3	5.7	5.9						
CR7261 HEYBURN-HAYMILL LINE	0.5	0.9	0.2								
CR7281 SNO-KING TRANSF. ADDN.	2.1	0.6									
CR7301 ALBANY TRANSF. SUPPORT		1.8	1.8								
CR7313 SNOHOMISH TRANSF. SPT.		0.1	3.5	1.1							
CR7322 WELLS AREA SERVICE		0.1	2.1	11.3	25.6	2.5					
CR7333 HUNGRY HORSE RE-BUILD		0.1	1.6	0.5	0.1						
CR7344 COLUMBIA FALLS 230-KV ADDN.				0.3	2.6	1.4					
CR7354 CHEHALIS TRANSFORMER SPT.					2.6	1.2					
CR7364 MOSSY ROCK GENERATION SPT.			0.1	0.5	4.1	3.6	1.1				
CR7372 MINIDOKA AREA SERVICE			1.4	0.9							
CR7385 SALEM-GRANDE RONDE RECON.				0.6	1.0	2.3	0.1				
CR7395 OKANOGAN VALLEY TXF SPT.						1.2	1.6	0.3			
CR7700 CUSTOMER SVC. ITEMS	1.8	4.0	4.0	3.3	3.4	3.5	3.7	3.8	3.9	4.0	4.2
CR7990 VARIOUS ADDITIONS *					5.0	10.0	10.0	11.0	12.0	15.0	20.0
BLI CCAC TOTAL	4.4	7.9	15.1	24.3	51.0	26.5	16.5	15.1	15.9	19.0	24.2

	FY 91 ACTL	FY 92	FY 93	FY 94	FY 95	FY 96	FY 97	FY 98	FY 99	FY 00	FY 01
<u>BLI CCGF - GEN. SYS. FACILITIES</u>											
CR8400 PREL. ENGINEERING	-0.6	0.9	0.8	0.8	0.8	0.9	1.1	1.1	1.2	1.2	1.2
	-0.6	0.9	0.8	0.8	0.8	0.9	1.1	1.1	1.2	1.2	1.2
BLI CCGF TOTAL											
<u>BLI CCSC - SYSTEM CONTROLS</u>											
CR2000 SYSTEM CONTROLS	11.1	16.0	22.0	24.0	25.0	27.5	21.2	22.0	22.8	23.6	24.6
	11.1	16.0	22.0	24.0	25.0	27.5	21.2	22.0	22.8	23.6	24.6
<u>BLI CCMA- MISC LINE & SUB ADDNS</u>											
CR3000 MISC LINE & SUB ADDNS	4.3	8.7	7.0	6.1	6.0	6.2	6.3	6.7	7.2	7.5	7.8
	4.3	8.7	7.0	6.1	6.0	6.2	6.3	6.7	7.2	7.5	7.8
<u>BLI CCMB MAJOR NEW BUILDINGS</u>											
CR8500 MAJOR NEW BUILDINGS			5.7	15.7	8.7	11.4	11.8	6.1	6.3	6.6	6.8
			5.7	15.7	8.7	11.4	11.8	6.1	6.3	6.6	6.8
<u>BLI CCMC- MISC. COMPLETIONS</u>											
CR9100 - COMP OF PRIOR YR ITEMS **	3.4	3.0	0.3	0.4	0.4	0.1	0.1	0.1	0.1	0.1	0.1
CR9130 CAPITAL TO EXPENSE ADJUST. ***		-5.0	-5.0	-5.0	-5.0	-5.0	-5.0	-5.0	-5.0	-5.0	-5.0
	3.4	-2.0	-4.7	-4.6	-4.6	-4.9	-4.9	-4.9	-4.9	-4.9	-4.9
<u>BLI CCAF - AFUDC DISTRIBUTION</u>											
CRAF AFUDC		15.0	11.0	12.9	12.3	9.4	6.8	6.6	7.0	7.2	7.4
		15.0	11.0	12.9	12.3	9.4	6.8	6.6	7.0	7.2	7.4
<u>BLI CCIC - INDIRECT CAPITAL</u>											
CR9600 INDIRECT (PL6'S)	4.4	4.9	6.4	6.8	7.1	7.5	7.7	8.0	8.2	8.4	8.6
	4.4	4.9	6.4	6.8	7.1	7.5	7.7	8.0	8.2	8.4	8.6
ACCOUNTING ADJUSTMENT	3.5										
TOTAL SUB-PROG. CAPITAL INVESTMENT	98.2	195.4	186.3	117.3	201.4	205.4	298.8	261.9	244.0	223.6	199.9
SUPPORT SERVICES	25.6	18.5	20.5	19.9	20.5	21.1	21.9	22.9	23.8	25.2	20.3
TOTAL CAPITAL BEFORE CORP. OH	123.8	213.9	206.8	137.2	221.9	226.5	320.7	284.8	267.8	248.8	220.2
GENERAL & ADMINISTRATIVE COSTS	5.2	4.5	7.1	6.7	6.3	6.8	7.1	7.3	7.6	7.8	7.1
TOTAL CAPITAL AFTER CORP. OH	129.0	218.4	213.9	143.9	228.2	233.3	327.8	292.1	275.4	256.6	227.3

	FY 91 ACTL	FY 92 PACS	FY 93	FY 94	FY 95	FY 96	FY 97	FY 98	FY 99	FY 00	FY 01
SUB-PROGRAM CB2 - EXPENSE											
BLI CCRD - R&D											
CR8460 RESEARCH & DEVELOPMENT	4.2	4.7	5.6	5.8	6.0	6.3	6.6	6.8	7.0	7.2	7.4
	4.2	4.7	5.6	5.8	6.0	6.3	6.6	6.8	7.0	7.2	7.4
BLI CCIE - INDIRECT EXPENSE											
CR9500 OTHER EXPENSE (950 PL6'S)	4.7	5.0	5.2	5.4	5.5	5.6	5.9	6.1	6.4	6.6	6.8
CR9999 INDIRECT (MS&A)	4.8	5.0	5.2	5.5	5.6	5.6	5.9	6.1	6.3	6.6	6.8
	9.5	10.0	10.4	10.9	11.1	11.2	11.8	12.2	12.7	13.2	13.6
CK9903 CAPITAL TO EXPENSE ADJ. ***	2.7	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.2
	2.7	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.0	5.2
TOTAL SUB-PROGRAM - EXPENSE (DIRECT)	16.4	19.7	21.0	21.7	22.1	22.5	23.4	24.0	24.7	25.4	26.2
SUPPORT SERVICES	3.2	9.2	10.0	10.3	10.7	11.0	11.4	11.8	12.2	12.7	13.1
TOTAL EXPENSE BEFORE CORP. OH	19.6	28.9	31.0	32.0	32.8	33.5	34.8	35.8	36.9	38.1	39.3
CORPORATE OVERHEAD	2.6	2.7	1.8	1.9	1.9	2.0	2.1	2.2	2.3	2.5	2.6
TOTAL EXPENSE AFTER CORP. OH	22.2	31.6	32.8	33.9	34.7	35.5	36.9	38.0	39.2	40.6	41.9
TOTAL TSD PROGRAM (DIRECT)	114.6	215.1	207.3	139.0	223.5	227.9	322.2	285.9	268.7	249.0	226.1
SUPPORT SERVICES	28.8	27.7	30.5	30.2	31.2	32.1	33.3	34.7	36.0	37.9	33.4
TOTAL PROGRAM BEFORE CORP. OH	143.4	242.8	237.8	169.2	254.7	260.0	355.5	320.6	304.7	286.9	259.5
CORPORATE OVERHEAD	7.8	7.2	8.9	8.6	8.2	8.8	9.2	9.5	9.9	10.3	9.7
TOTAL PROGRAM AFTER CORP. OH	151.2	250.0	246.7	177.8	262.9	268.8	364.7	330.1	314.6	297.2	269.2

* THIS LINE CONTAINS FORECAST COSTS FOR POTENTIAL PROJECTS WHICH ARE UNDEFINED AT THIS TIME, BUT HISTORICAL DATA TELLS US WILL MOST PROBABLY OCCUR.

** CAPITAL TO EXPENSE ADJUSTMENTS OF APPROXIMATELY \$5 MILLION ARE EXPECTED AT THE END OF THE YEAR. FORECAST FOR THIS ADJUSTMENT IS NOT SHOWN IN THE PLANNING, ACCOUNTING AND CONTROL SYSTEM (PACS).

*** INCLUDES ACTUALS AND FORECASTS TO RPA'S NO LONGER DETAILED IN BUDGET PRESENTATION.

SBICKFORD:SB:3152
(EXCEL-EB PLNREV8)

FY	BPA FTE		Engineering Contractor FTE	Dollars (Millions)
	Engineering FTE	Other FTE		
FY 1989	288	165	51	83
FY 1990	277	168	62	128
FY 1991	280	158	114	151
FY 1992	306	231	130	250
FY 1993	312	219	182	247
FY 1994	312	198	139	178
FY 1995	310	178	104	263
FY 1996	310	186	140	269
FY 1997	310	190	170	365
FY 1998	310	186	135	330
FY 1999	310	186	130	315
FY 2000	310	186	125	297
FY 2001	310	186	120	269

- NOTES:**
1. Amounts contain corporate overhead and inflation.
 2. One FTE is equivalent to one employee working full-time for one year.
 3. "Other FTE" includes all BPA employees from Offices other than Engineering whose work supports the Transmission System Development Program.

TOTAL REPLACEMENT PROGRAM \$ COMPARED TO ENGINEERING'S CONTRACT & IN-HOUSE FTE

FY	OFFICE OF ENGINEERING			Program Amount
	Contractors	Employees	Total FTE	
				(\$ Millions)
FY 1989	11	34	45	48
FY 1990	14	35	49	63
FY 1991	30	43	72	67
FY 1992	34	42	75	93
FY 1993	24	33	57	86
FY 1994	18	41	59	80
FY 1995	18	47	65	95
FY 1996	20	45	65	83
FY 1997	20	45	65	86
FY 1998	20	45	65	89
FY 1999	20	45	65	92
FY 2000	20	45	65	92
FY 2001	20	45	65	92

- NOTES:**
1. Amounts contain corporate overhead and inflation.
 2. FY 91-92 FTE peak reflects increase in contracting to accomplish carryover workload.

This table reflects Combined Program Dollars for FY 81-87 System Planning & Construction and FY 88-2001 TSD and System Replacements. Office of Engineering FTE is shown for FY 87-2001.

	Engineering FTE	(\$ Millions)
FY 1981		270
FY 1982		295
FY 1983		225
FY 1984		282
FY 1985		185
FY 1986		239
FY 1987	491	213
FY 1988	460	126
FY 1989	440	145
FY 1990	426	203
FY 1991	436	224
FY 1992	469	343
FY 1993	479	323
FY 1994	484	243
FY 1995	489	327
FY 1996	489	310
FY 1997	484	382
FY 1998	515	343
FY 1999	515	321
FY 2000	515	310
FY 2001	515	287

NOTES:

1. All amounts are shown in constant 1992 Dollars and contain corporate overhead.
2. Personnel data not available prior to 1987 due to changes in BPA's organizational structure.
3. FTE figures reflect allocations through FY 1997; estimated requirements are shown for FY 1998 through FY 2001.

**DATE
FILMED**
7/22/92