EGG-WTD-9985
December 1991

APR 27 1992

**Idaho
National
Engineering
Laboratory**

*Managed
by the U.S.
Department
of Energy*

INFORMAL REPORT

**Technical Issues Associated with In Situ
Vitrification of the INEL Subsurface Disposal
Area**

**Volume 1: A Systematic Approach for
Identification, Prioritization, and Closure of
Technical Issues**

**Carl M. Stoots
Steven O. Bates
Richard A. Callow
Kris A. Campbell
Richard K. Farnsworth
Gretchen K. Gratson
Michael G. McKellar
David F. Nickelson
Calvin E. Slater**

*Work performed under
DOE Contract
No. DE-AC07-76ID01570*

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

This document contains new concepts or the author(s) interpretation of new calculations and/or measurements; accordingly, EG&G Idaho, Inc. is required by the United States Government to include the following disclaimer:

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights. References herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

**Technical Issues Associated with In Situ Vitrification of the INEL
Subsurface Disposal Area**

**Volume 1: A Systematic Approach for Identification,
Prioritization, and Closure of Technical Issues**

Carl M. Stoots
Steven O. Bates
Richard A. Callow
Kris A. Campbell
Richard K. Farnsworth
Gretchen K. Gratson
Michael G. McKellar
David F. Nickelson
Calvin E. Slater

Published December 1991

Idaho National Engineering Laboratory
EG&G Idaho, Inc.
Idaho Falls, Idaho 83415

Prepared for the
U.S. Department of Energy
Office of Environmental Restoration and Waste Management
Under DOE Field Office, Idaho
Contract DE-AC07-76ID1570

REGISTERED

df
DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

**Technical Issues Associated with In Situ Vitrification of the INEL
Subsurface Disposal Area**

**Volume 1: A Systematic Approach for Identification,
Prioritization, and Closure of Technical Issues**

Prepared by:

Carl M. Stoots, Chairman ISV Steering Committee

12/4/91

Date

Peer review by:

David Nickelson

12/4/91

Date

Approved by:

S. Kenneth Merrill

12/6/91

Date

ABSTRACT

In situ vitrification (ISV) has been identified as an alternative technology for remediation of the Acid Pit and Transuranic Pits and Trenches (TRU-PTs) that are present at the Idaho National Engineering Laboratory (INEL) Subsurface Disposal Area (SDA). However, a number of technical issues exist that must be resolved before ISV can be considered applicable to these waste sites. To assist in the ISV technology evaluation, an ISV Steering Committee was formed to identify, prioritize, and develop closure roadmaps for technical issues associated with ISV application at the INEL SDA. The activities of the ISV Steering Committee are summarized in three volumes of this report. Volume 1 identifies the systematic approach used to identify and prioritize the ISV technical issues, and briefly discusses the methodology that will be employed to resolve these issues. Volumes 2 and 3 discuss each technical issue in greater detail and suggest specific closure roadmaps to be used in resolving technical issues associated with ISV at the SDA Acid Pit and TRU-PTs, respectively. The report is a working document that will be updated as necessary to reflect the current evaluation strategy for the ISV technology.

SUMMARY

The Idaho National Engineering Laboratory (INEL) is currently in the process of evaluating different technology alternatives for remediating waste sites at the INEL Subsurface Disposal Area (SDA). Currently, in situ vitrification (ISV) is being evaluated for two operable units within the INEL SDA, the Acid Pit and the Transuranic-contaminated Waste Pits and Trenches (TRU-PTs). While ISV is relatively well-developed for contaminated soils, there are a number of issues that need to be resolved before ISV can be applied to the Acid Pit. In addition, the ISV technology still needs to be developed and understood before it can be considered applicable to buried mixed-waste sites, such as the TRU-PTs.

As a result, an ISV Steering Committee was formed to assist in the evaluation of ISV technology for remediating the INEL SDA. The purpose of the ISV Steering Committee is to define, prioritize, and develop roadmaps for closure of technical issues associated with the proposed application of ISV to the SDA. The activities of the ISV Steering Committee are summarized in this report. Volume 1 of this report identifies the methods used for identifying and prioritizing ISV technical issues associated with the Acid Pit and TRU-PTs, while briefly discussing the methodologies that will be employed to resolve these issues. Volumes 2 and 3 discuss each technical issue and specifically address the suggested resolution for technical issues associated with the Acid Pit and the TRU-PTs, respectively.

In Volume 1, a total of 35 ISV technical issues were developed by the ISV Steering Committee. The 35 technical issues were identified by examining previous documentation of ISV technical issues for various applications, as well as identifying any additional issues that have arisen during recent ISV operations. The issues were identified with respect to global ISV applications on buried waste sites, rather than any particular operable unit. In particular, each issue was related to a specific mechanism associated with the generic ISV process. Following the identification process, the issues were classified as either an environmental issue or a safety issue, and then further categorized by each specific ISV mechanism (i.e., product quality, off-gas concerns, etc.). The report includes a brief discussion of each of the 35 issues.

Following identification, the technical issues were evaluated and prioritized for each of the two operable units (Acid Pit and TRU-PTs) within the SDA. Included in the evaluation was a determination of which issues were applicable to each operable unit. All 35 technical issues were found to be applicable to the TRU-PTs, while only 25 of the 35 issues were found to be applicable to the Acid Pit. Prioritization of the issues was performed by qualitatively evaluating each applicable issue against a weighted criteria that had been previously identified by the ISV Steering Committee. In general, it was found that issues associated with the TRU-PTs were of more concern than issues that were applicable to the Acid Pit. The prioritization results showed that the number one technical issue associated with ISV remediation of the Acid Pit was the potential of subsurface contaminant migration as a result of thermal gradients, while the number one technical issue for the TRU-PTs was the potential for a criticality to occur in the melt or off-gas system during ISV processing.

A roadmap consisting of requirements and steps to close an issue was then proposed for obtaining closure on the applicable technical issues for each operable unit. An ISV technical issue is considered closed when it no longer compromises the safety, feasibility, environmental compliance, and product quality of ISV application at a particular operable unit. This involves addressing the applicable Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) criteria in relation to that issue. To obtain closure, it is necessary to first identify the dominant variables affecting each issue and then review the existing data related to this issue. Some issues may be closed without further tests and studies if enough data of sufficient quality exists. However, if the data is not sufficient, further information can be obtained through analytical studies, computer modelling, single effects experiments, ISV laboratory tests, or ISV field tests. The specific activities necessary for closing each issue are summarized in the closure roadmaps contained in Volumes 2 and 3 of this report.

Because of the dynamic nature of the development process, the identification, prioritization, and proposed methods for closure of the ISV technical issues will change with time. Therefore, this report does not represent the final approach for resolving technical issues associated with ISV remediation of contaminated soils and buried waste sites. As conditions change, this report will need to be updated to reflect the current evaluation strategy for the ISV technology.

ACKNOWLEDGEMENTS

The authors would like to thank the following people for their contributions to the report: R. W. Bonnenberg, C. Casey, V. Esparza, L. L. Fritz, C. J. Graden, M. Herd, P. Nagata, N. L. Smith, P. A. Sloan, P. R. Stoots.

CONTENTS

ABSTRACT	iii
SUMMARY	v
ACKNOWLEDGEMENTS	vii
1. INTRODUCTION	1
1.1 ISV Program Objective	2
1.2 The ISV Steering Committee Mission	2
1.3 ISV Program Interfaces	3
1.4 Objectives of This Document	4
2. IDENTIFICATION OF TECHNICAL ISSUES	6
2.1 Environmental Issues	7
2.1.1 Product Durability and Quality	7
2.1.2 Subsurface Contaminant Migration During Processing	14
2.1.3 Residual Waste	14
2.1.4 Secondary Waste Streams	15
2.2 Safety Issues	15
2.2.1 Criticality	15
2.2.2 Containment of Hazardous and/or Radioactive Material	15
2.2.3 Underground Fires	20
2.2.4 Electrical Hazards	21
3. ISV EVALUATION CRITERIA	23
4. PRIORITIZATION OF CLOSURE OF THE IDENTIFIED TECHNICAL ISSUES	33
5. DISCUSSION OF THE TECHNICAL ISSUE CLOSURE PROCESS	41
6. CONCLUSIONS	44
7. REFERENCES	45

FIGURES

1. Relationships between ISV environmental and safety issues and CERCLA criteria	30
2. Flow chart of the issue prioritization process used by the ISV Steering Committee	36
3. Prioritization of ISV environmental and safety issues.	38

TABLES

1. ISV environmental and safety issues identified by the INEL ISV Steering Committee	8
2. ISV technical issues	11
3. Technical issue prioritization criteria and their statistical relative weights	34

Technical Issues Associated with In Situ Vitrification of the INEL Subsurface Disposal Area

Volume 1: A Systematic Approach for Identification, Prioritization, and Closure of Technical Issues

1. INTRODUCTION

The purpose of this document is to:

- Identify and briefly discuss global technical issues applicable to the in situ vitrification (ISV) technology
- Present the systematic approach used by the ISV Steering Committee for identification and prioritization of technical issues associated with application of ISV to the Idaho National Engineering Laboratory (INEL) Subsurface Disposal Area (SDA).

It is anticipated that although the technical issues confronting other technologies and other applications may differ, this same systematic approach can be utilized.

This document also serves to introduce the purpose and mission of the INEL ISV Steering Committee. The ISV Steering Committee is chartered to provide technical planning, control, and focus for the INEL ISV Demonstration Program, as well as a technical forum for consideration of issues, experimental testing, and analytical studies. The relationship between the ISV Steering Committee and the ISV Test Design Committee is detailed as well.

Volumes 2 and 3 of this document present discussions of the technical issues applicable to the Acid Pit and Transuranic Waste Pits and Trenches (TRU-PTs) at the INEL SDA. These discussions include technical issue priority, description, importance, influencing factors, and general roadmaps for closure.

1.1 ISV Program Objective

The INEL is currently in the process of evaluating different alternatives for the remediation of portions of the INEL SDA. One waste remediation technology being studied for SDA applications is ISV. Originally developed by the Pacific Northwest Laboratory (PNL), ISV is being studied in a collaborative manner by INEL, PNL, Oak Ridge National Laboratory (ORNL), and GeoSafe Corporation. ISV technology thermally treats contaminated soil and waste in place by electrically heating and melting the waste, then allowing it to cool and solidify into a glass-like matrix. This crystalline and glass product is stable and chemically inert, thereby reducing risk to the environment and public. During the process, most of the constituents in the waste are either destroyed by pyrolysis, encapsulated by the solidified end-product, consumed via combustion, or captured by a hood and off-gas processing system located above the waste area being treated.

The objective of the ISV Demonstration Project is to determine if ISV is a viable technology for remediation of the SDA. In particular, the project is determining the applicability of ISV to remediate the SDA Acid Pit and TRU-PTs operable units. The Acid Pit is a relatively homogeneous contaminated soil site with various acidic, alkaline, organic, and low-level radioactive waste. The TRU-PTs are comprised of a wide variety of wastes and waste forms, including transuranic radionuclides, large metal inclusions, sealed and breached steel containers, various volatile and semivolatile organic compounds, heavy metals, and significant voids. Originally, Pit 9 was selected for demonstration and evaluation of ISV technology on TRU-PTs. However, the selection of the demonstration site for ISV application on TRU-PTs is currently being reevaluated.

1.2 The ISV Steering Committee Mission

The ISV Steering Committee is chartered to provide technical planning, control, and focus for the ISV Demonstration Project. The missions of the ISV Steering Committee are to define technical issues associated with the proposed application of ISV to the SDA, evaluate the importance of the issue relative to the treatability study investigation, propose requirements for closing the issue, and develop a roadmap for obtaining closure of the issue where applicable. The

primary benefit to the ISV Demonstration Project is a strong technical forum to consider issues systematically and provide the foundation for further testing or study.

The committee is composed of technical leads and key support personnel of the ISV Demonstration Project. Specialized expertise required to evaluate certain issues is obtained as necessary to support the committee. Specific functions of the ISV Steering Committee include:

- Defining technical issues
- Prioritizing technical issues to assist test planning and budget allocation decisions
- Defining technical issue closure requirements
- Defining closure roadmaps for the specific technical issues where applicable
- Establishing ISV analytical study and experimental testing objectives
- Considering proposed changes to the ISV technical baseline from management, Department of Energy (DOE), and other interested parties (other governmental facilities or industry)
- Tracking closure progress for technical issues and recommending further actions required to achieve closure
- Reporting technical issue closure status on a quarterly basis.

1.3 ISV Program Interfaces

The success of the ISV Steering Committee mission depends on establishing successful interfaces with the customers of the ISV Demonstration Program. Primary customers include Department of Energy, Field Office, Idaho (DOE-ID); Department of Energy, Headquarters (DOE-HQ); EG&G management; the INEL Buried

Waste Program; the INEL Buried Waste Integrated Demonstration Activity; the ISV technical community; the Environmental Protection Agency (EPA); and the State of Idaho. However, the customer that has the most immediate impact to the requirements of the ISV Steering Committee is the ISV Demonstration Project. The ISV Demonstration Project includes such work elements as laboratory testing, field testing, analytical studies, safety analysis and risk assessment, data life cycles, ISV product performance, and equipment design requirements.^a One element of the ISV Demonstration Project that has important ties to the ISV Steering Committee is the ISV Test Design Committee.

The ISV Test Design Committee supports the design of experiments for laboratory and field testing. Its primary function is to ensure tests are focused on the objectives established by the ISV Steering Committee to optimize the data collection process. The ISV Steering Committee, acting in conjunction with the ISV Test Design Committee, will use an increasing knowledge base of the ISV process to influence the objectives and design of future tests.

1.4 Objectives of This Document

This document is Volume 1 of three volumes. The primary objective of this document is to identify and introduce the issues associated with the application of ISV to the INEL SDA and outline the systematic approach used in the issue identification process. Although issues concerning ISV¹ have been previously identified,^{b,c} the ISV Steering Committee decided that these issues should be reexamined with consideration to the SDA, and possibly new issues will be identified. At this time, two operable units have been defined within the SDA, the Acid Pit and TRU-PTs. A more comprehensive discussion of these particular

a. Unpublished research results of the Waste Technology Development Department, "In Situ Vittrification Demonstration Program Long-Range Project Plan," EG&G Idaho, Inc., Idaho Falls, Idaho, January 1991.

b. Unpublished research results of R. M. Nielsen, "ISV Critical Technical Issues," Draft Letter, EG&G Idaho, Inc., Idaho Falls, Idaho, August 1990.

c. Unpublished research results of C. E. Slater, C. M. Stoots, and R. J. McKinnon, "Discussion of Technical Issues Associated with the Application of ISV at the INEL and a Suggested Approach for their Resolution," Draft Report, EG&G Idaho, Inc., Idaho Falls, Idaho, Sept 1990.

technical issues and roadmaps for their closure are contained in Volume 2 for the Acid Pit and Volume 3 for TRU-PTs.

This paper also suggests criteria by which ISV will be evaluated as a remedial technology for the Acid Pit and TRU-PTs. Furthermore, this document presents prioritization criteria developed by the ISV Steering Committee and the resulting prioritizations of the identified technical issues as they apply to the Acid Pit and TRU-PTs. Finally, this paper briefly discusses the methodologies that will be employed to address and close these issues. The actual requirements and suggested roadmaps for closure of identified technical issues are detailed in Volumes 2 and 3.

2. IDENTIFICATION OF TECHNICAL ISSUES

A technical issue is defined as "any phenomena, process, or condition that must be understood and quantified to ensure that safety, feasibility, environmental compliance, and product quality of the proposed ISV application are not compromised."^a Some technical issues associated with ISV technology have been previously identified (see Reference 1).^{b,c} Using information from previous studies, the ISV Steering Committee reexamined these issues and determined their applicability with respect to global needs without consideration of a particular operable unit. During this process, several new technical issues were identified. Applicability, definitions, importance, and closure requirements for these global technical issues were then determined for the Acid Pit and TRU-PTs. Outlined below is the process used by the ISV Steering Committee to identify and organize the global technical issues associated with ISV technology. A brief discussion of each issue follows. More comprehensive discussions of issues specific to the Acid Pit and TRU-PTs are in Volumes 2 and 3.

The ISV Steering Committee anticipates that the list of technical issues will change with time and should be considered dynamic. The list of issues will change primarily for two reasons. First, as our understanding of the ISV process increases, some issues may become irrelevant while new issues may arise. Second, as the INEL ISV Project becomes increasingly integrated with other ISV technology programs (i.e., PNL, Savannah River Plant (SRP), ORNL, and Geosafe Corporation) there may arise issues specific to other DOE buried waste sites that need to be investigated.

The approach used by the ISV Steering Committee to identify and group technical issues involved first developing a conceptual model of the ISV process. The pathways were then examined by which contaminants could escape into the atmosphere, migrate through the soil, or remain unprocessed, etc., which could jeopardize worker or public safety or environmental compliance. Within this

a. See footnote b on page 4.

b. See footnote b on page 4.

c. See footnote c on page 4.

model each technical issue identified in EG&G Idaho unpublished research results (footnotes b and c, on page 4) and in a PNL letter report (see Reference 1) was examined and listed. Once this was done, the committee brainstormed to disclose any issues not previously identified. The advantage of this technique was that it naturally organized the issues into two groups or divisions. The two major divisions were environmental and safety issues. Within the environmental division the following subdivisions of technical issues were recognized: product durability and quality, subsurface contaminant migration, residual waste, and secondary waste streams generated by off-gas treatment. Within the safety division, the following subdivisions were identified: criticality, containment of hazardous and radioactive material, underground fires, and electrical hazards. In some cases these subdivisions necessitated further divisions. Table 1 outlines the environmental and safety issues identified by the ISV Steering Committee. Table 2 lists the 35 subdivided, technical issues.

A brief discussion of the environmental and safety issue categories follows. A more comprehensive discussion of each technical issue is found in Volumes 2 and 3.

2.1 Environmental Issues

2.1.1 Product Durability and Quality

Since the primary purpose of the ISV process is to stabilize, immobilize, and reduce the volume of radioactive and hazardous waste components, it is important to know accurately the durability and quality characteristics of the ISV product. Data concerning the release and radiological characteristics of the ISV product are necessary in the treatability study for evaluation in the Remedial Investigation/Feasibility Study (RI/FS) process to show that the product is an acceptable risk to human health and the environment. Criteria for evaluation of the ISV product include meeting regulatory requirements, comparison with other similar ISV products, and comparison with natural

Table 1. ISV environmental and safety issues identified by the INEL ISV Steering Committee

I. Environmental Issues

- A. The durability and quality of product is acceptable.
 - 1. Release characteristics of the product are an acceptable risk to the environment.
 - 2. The product is well characterized.
 - a. The homogeneity and other physical characteristics of the product are well characterized.
 - b. The degree and effects of metals pooling in the product are well characterized.
 - 3. The radiological characteristics of the product are acceptable.
- B. Subsurface contaminant migration during processing is within acceptable limits.
 - 1. Any enhancements to subsurface contaminant migration provided by subsurface structures (pipes, drum surfaces, voids, etc.) are within acceptable limits.
 - 2. Subsurface contaminant migration due to the effects of sealed containers is within acceptable limits.
 - 3. Subsurface contaminant migration due to thermal gradients into surrounding homogeneous soil is within acceptable limits.
- C. Any residual waste is acceptable. That is, the quantity of any waste that is left unprocessed in the soil is acceptable.
 - 1. The melt shape is predictable and suitable for capturing the waste intended to be captured.
 - a. The melt width and depth are such that it captures the desired waste.
 - b. Melt channelling or preferential flow of the melt through the path of least resistance is predictable and does not impact the capture of the waste intended to be captured.
 - c. The quantity of any uncaptured waste between adjacent vitrified blocks is acceptable.

Table 1. (continued)

2. The quantity of any waste that may be encapsulated (unprocessed) within the glass is acceptable.
- D. Secondary waste streams (effluents from the off-gas treatment system, scrub solutions, HEPA filters, decontamination solutions, etc.) are within acceptable limits.

II. Safety Issues

- A. The possibility of criticality is avoided.
- B. Hazardous and radioactive material is adequately contained by the equipment.
1. Hazardous and radioactive material is adequately contained by the hood.
 - a. Hood containment seals are adequate.
 - b. Any fires that may occur do not affect the integrity of the hood.
 - c. The hood covers adequate ground area to prevent releases.
 - (1) A sidewall collapse does not impact the seal between the hood skirt and the ground.
 - (2) The melt and thermally altered zone do not extend laterally beyond the hood boundaries.
 - d. The hood handles pressure transients adequately.
 - (1) Pressurizations due to explosions remain contained.
 - (2) Pressurizations due to the breach of pressurized sealed containers remain contained.
 - (3) Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface remain contained.
 - (4) Increases in off-gas due to the melt encountering voids remain contained.
 - (5) Off-gas generation caused by combustion within the hood is contained.
 - e. Any matter ejected from the melt is contained by the hood.

Table 1. (continued)

2. The off-gas treatment system provides adequate containment and maintains effluents to acceptable levels.
 - a. Off-gas treatment system containment seals are adequate.
 - b. Off-gas treatment system capacity for treatment of products from within the hood is adequate.
 - c. The off-gas treatment system handles pressure transients adequately.
 - (1) Pressurizations due to explosions remain contained.
 - (2) Increases in off-gas due to the breach of pressurized sealed containers are contained and processed adequately.
 - (3) Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface are contained and processed adequately.
 - (4) Increases in off-gas due to the melt encountering voids are contained and processed adequately.
 - (5) Excessive off-gas generation caused by combustion is contained.
 - d. Any corrosion within the off-gas treatment system does not affect containment or effluents.
 3. Risks due to any exposed waste are within acceptable limits.
 4. Post-processing hood containment is maintained as required.
 - C. Underground fires are avoided.
 - D. Electrical hazards are controlled.
-

Table 2. ISV technical issues

Environmental Issues

1. Release characteristics of the product are an acceptable risk to the environment.
2. The homogeneity and other physical characteristics of the product are well characterized.
3. The degree and effects of metals pooling in the product are well characterized.
4. The radiological characteristics of the product are acceptable.
5. Any enhancements to subsurface contaminant migration provided by subsurface structures (pipes, drum surfaces, voids, etc.) are within acceptable limits.
6. Subsurface contaminant migration due to the effects of sealed containers is within acceptable limits.
7. Subsurface contaminant migration due to thermal gradients into surrounding homogeneous soil is within acceptable limits.
8. The melt width and depth are such that it captures the desired waste.
9. Melt channelling or preferential flow of the melt through the path of least resistance is predictable and does not impact the capture of the waste intended to be captured.
10. The quantity of any uncaptured waste between adjacent vitrified blocks is acceptable.
11. The quantity of any waste that may be encapsulated (unprocessed) within the glass is acceptable.
12. Secondary waste streams (effluents from the off-gas treatment system, scrub solutions, HEPA filters, decontamination solutions, etc.) are within acceptable limits.

Safety Issues

13. The possibility of criticality is avoided.
14. Hood containment seals are adequate.
15. Any fires that may occur do not affect the integrity of the hood.

Table 2. (continued)

16. A sidewall collapse does not impact the seal between the hood skirt and the ground.
17. The melt and thermally altered zone do not extend laterally beyond the hood boundaries.
18. Pressurizations due to explosions remain contained within the hood.
19. Pressurizations due to the breach of pressurized sealed containers remain contained within the hood.
20. Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface remain contained within the hood.
21. Increases in off-gas due to the melt encountering voids remain contained within the hood.
22. Off-gas generation caused by combustion is contained within the hood.
23. Any matter ejected from the melt is contained within the hood.
24. Off-gas treatment system seals are adequate.
25. Off-gas treatment system capacity for treatment of products from within the hood is adequate.
26. Pressurizations due to explosions remain contained within the off-gas treatment system.
27. Increases in off-gas due to the breach of pressurized sealed containers are contained and processed adequately within the off-gas treatment system.
28. Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface are contained and processed adequately within the off-gas treatment system.
29. Increases in off-gas due to the melt encountering voids is contained and processed adequately within the off-gas treatment system.
30. Excessive off-gas generation caused within combustion is contained within the off-gas treatment system.
31. Any corrosion within the off-gas treatment system does not affect containment or effluents.
32. Risks due to any exposed waste are within acceptable limits.

Table 2. (continued)

- 33. Post-processing hood containment is maintained as required.
 - 34. Underground fires are avoided.
 - 35. Electrical hazards are controlled.
-

analogs. Other product characterization data such as homogeneity, susceptibility to fracture, and metal pooling are important for fundamental knowledge of the ISV process, as well as information for the public to know what is at a waste site once remediation is completed.

2.1.2 Subsurface Contaminant Migration During Processing

One pathway by which ISV could potentially harm workers, as well as jeopardize environmental compliance, is the migration of contaminants away from the area being processed through the surrounding soil. If sufficient migration occurs, certain portions of the soil may reach concentrations that classify as hazardous waste, as defined by the Code of Federal Regulations 40 CFR 261.3.² If this happens, further remediation or retrieval of the surrounding soil would be required before the site could be considered remediated, increasing the cost of the remediation process. The major mechanism for subsurface migration of contaminants is through thermal gradients. However, buried structures such as pipes, drum surfaces, and voids may offer enhanced pathways for subsurface migration. Also, the rupture of pressurized sealed containers may also affect contaminant migration.

2.1.3 Residual Waste

The quantity of any waste that is left unprocessed in the soil must be acceptable. During processing of a waste site, there may be a small quantity of residual waste that is left unprocessed in the soil. The principal requirements for minimization of this residual waste are process knowledge and control of the geometry of the melt in terms of shape, width, and depth. In particular, the melt width and depth must capture the targeted waste. This includes any waste between adjacent vitrified blocks. Incomplete encapsulation of the buried waste can also result from redirection of the melt's downward path due to obstacles and conduits encountered during processing. Since the molten soil is a fluid it will preferentially flow through the path of least resistance. This phenomenon of melt channelling should be predictable and not impact the waste intended to be captured. Some waste may be encapsulated by the melt but not dissolved into the

melt. The potential impact to the environment from this residual waste must be assessed.

2.1.4 Secondary Waste Streams

The ISV process generates secondary waste streams [effluents from the off-gas treatment system, scrub solutions, high efficiency particulate air (HEPA) filters, decontamination solutions, etc.] during the treatment of the gaseous effluents from the hood by the off-gas treatment system. These secondary waste streams must be within acceptable limits, including federal and state regulations for hazardous waste generation and disposal, and air emissions. Ultimately, data will be required on the amounts of secondary waste generated and the cost to characterize, treat, and dispose of these wastes. Such data are a factor in the overall evaluation of the ISV process.

2.2 Safety Issues

2.2.1 Criticality

The reported quantities of fissile materials disposed of in the SDA have prompted concerns of criticality during ISV processing. Mechanisms that can contribute to fissile materials concentration include: insolubility and pooling of fissile materials in the ISV glass, densification of fissile materials prior to melt encapsulation, and entrainment and resulting condensation on the confinement hood or in the off-gas treatment system. However, the strong convective mixing that characterizes the ISV process, as well as the solubility of plutonium oxide (the predominant fissile material at the SDA) in molten glass, indicates that any concentration of fissile materials is unlikely.

2.2.2 Containment of Hazardous and/or Radioactive Material

The ISV process produces gases and particulates that must be contained by the hood and treated by the off-gas treatment system. Sections 2.2.2.1 through 2.2.2.1.5 discuss the issues related to the containment of material released from

the melt into the hood, and Sections 2.2.2.2 through 2.2.2.4 discuss the issues related to containment and treatment of materials by the off-gas system.

2.2.2.1 Hazardous/Radioactive Material is Adequately Contained by the Hood. During ISV processing, gases and entrained particulates are captured by a hood placed over the vitrified zone. These effluents result from volatilization of waste constituents and pyrolysis within the melt. A negative pressure with respect to the outside environment is maintained in the hood to ensure effluent containment. Air that is simultaneously introduced into the hood provides the oxygen necessary for combustion of the gases before they are carried to the off-gas treatment system. The hood serves three important functions for the ISV process: containment for hazardous constituent emissions (gaseous, liquid, or solid), a combustion chamber for effluents from the melt, and a structural support for the electrode feed system. Issues identified concerning the containment of effluents by the hood include the adequacy of the hood seals, the ability of the hood to withstand fires, the size of the ground area covered by the hood, pressure transients and their effect upon the hood, and whether the hood maintains containment for any matter (such as molten soil) that may be ejected from the melt.

2.2.2.1.1 Hood Containment Seals are Adequate—Hood containment seals are used where pieces of metal in the hood are joined as well as for a skirt around the bottom of the hood to effectively seal the hood to the ground. During normal operation, there is a negative pressure inside the hood drawing outside air into the hood through a designated air inlet line and HEPA filter. In situations where the inside of the hood experiences a sudden positive pressurization, airflow may occur out of the hood. Hood containment seals must be sufficient so that the bulk of this outflow will occur through the air inlet line, with the HEPA filter providing a barrier against unrestricted release.

2.2.2.1.2 Fires That May Occur Do Not Affect the Integrity of the Hood—Some fires have occurred during the testing of ISV. Two of these fires involved fabric hoods which contained a combustible coating. The design and construction

materials of the hood must withstand the hood interior environment. This includes excessive temperatures due to combustion and melt splattering.

2.2.2.1.3 Hood Covers Adequate Ground Area to Prevent Releases—The hood must cover enough area to ensure that material released from the melt into the atmosphere is captured. Volatile constituents in the ISV-induced thermally-altered region of soil may vaporize and migrate to the surface through unprocessed soil. The hood must encompass this thermally-altered region of soil to capture these gases.

2.2.2.1.3.1 Sidewall Collapse Does Not Impact the Seal Between the Hood Skirt and the Ground—Since the density of molten soil is greater than normal soil, the liquid surface tends to subside below the surface of the surrounding soil. If this subsidence is large enough, some adjacent soil can collapse onto the melt. The area covered by the hood must be sufficient so that any sidewall collapses of soil into the melt do not jeopardize the seal between the hood skirt and the ground.

2.2.2.1.3.2 Melt and Thermally Altered Zone Do Not Extend Laterally Beyond the Hood Boundaries—The ground area covered by the hood must also be sufficiently large that the melt and thermally-altered zone do not extend laterally beyond the hood boundaries. The thermally-altered zones of interest are those areas where there is potential for hazardous constituent emissions to the atmosphere. If the hood is not sufficiently large, volatile constituents within these thermally-altered zones may diffuse through the soil and escape from the soil surface into the environment outside the hood. Such an escape would represent a hazard to operable personnel within the controlled zone, as well as to the environment.

2.2.2.1.4 Hood Handles Pressure Transients Adequately—The rate and composition of the gases released from the surface of the melt are an important parameter for determining the hood size and integrity. As stated earlier, the confinement hood serves as a containment vessel, as well as a combustion chamber for these gases. The hood's volumetric size and the flow rate through the hood

determine the residence time gases have within the hood to undergo full combustion. The off-gas rate is fairly constant during the processing of contaminated soil. However, random and inhomogeneous buried waste can cause transients in the off-gas rate, causing transients in the hood combustion processes and hood pressure. These transients can arise from rapid combustion within the melt or hood, sudden releases from buried sealed containers, waste falling from the sidewall onto the melt surface, the melt encountering a substantial void within the waste, or changes in the off-gas composition that accelerate combustion. If the hood design is not adequate, such pressurizations could lead to accidental emission releases via breach of the hood, lifting of the hood from the ground surface, or over-pressurization of the off-gas effluent treatment system.

2.2.2.1.5 Any Matter Ejected from the Melt is Contained by the Hood—A final issue related to hood containment concerns melt material that may be ejected from the melt during processing. Substantial bubbling of gases from the melt may cause ejection of melt material. This melt material may contact the hood, jeopardizing the integrity of the hood. Also, the sudden breach of a highly pressurized container within the melt could cause this container to be ejected and come in contact with the hood. The hood must be able to withstand contact with any matter that is likely to be ejected from the melt.

2.2.2.2 Off-Gas Treatment System Provides Adequate Containment and Maintains Effluents to Acceptable Levels. The off-gas treatment system cools, scrubs, and filters the effluents captured by the hood, reducing the hazards associated with these effluents to acceptable levels. During off-gas treatment, the off-gas system must also maintain containment. For this reason, the issues identified as having an impact upon the ability of the off-gas treatment system to treat effluents are similar to the issues impacting hood containment. However, it is anticipated that the closure requirements and process for off-gas treatment system issues will be significantly different than closure for hood containment issues. Hence, the ISV Steering Committee is distinguishing off-gas treatment system containment and performance issues from hood containment issues.

2.2.2.2.1 Off-Gas Treatment System Containment Seals are Adequate—

Containment seals will be used throughout the off-gas treatment system. Seals must protect workers within the trailer against unnecessary exposure risks and provide a barrier against unrestricted release to the environment.

2.2.2.2.2 Off-Gas Treatment System Capacity for Treatment of Products from Within the Hood is Adequate—The off-gas treatment system must have sufficient capacity to treat the anticipated steady state and transient effluent rates from the hood. Inadequate treatment of these effluents could result in an unacceptable level of emissions from the stack into the environment and pose a potential risk to personnel. Closure of this issue requires determining the maximum credible release rate of effluents from the melt, characterizing and monitoring the performance of the off-gas treatment system, and assessing the possibility of failure of a component of the off-gas treatment system.

2.2.2.2.3 Off-Gas Treatment System Handles Pressure Transients Adequately—The off-gas treatment system must function adequately during pressure transients. Pressure transients may arise from rapid combustion either within the melt, hood, or off-gas treatment system. They may also arise from the breach of a pressurized container, additional waste falling from the sidewall onto the melt surface, the melt encountering a substantial void, or changes in the rate of combustion within the hood. Failure to contain and properly treat such pressure transients could jeopardize workers near the off-gas treatment system trailer, cause the failure of a component in the treatment system, and allow hazardous effluents to escape unprocessed into the atmosphere.

2.2.2.2.4 Any Corrosion Within the Off-Gas Treatment System Does Not Affect Containment or Effluents—Corrosion within the off-gas treatment system could also result in the escape of unprocessed effluents into the atmosphere. Some of the corrosive gases that may be processed by the treatment system include acidic and caustic compounds (e.g., nitric acid and sodium hydroxide) and products (e.g., sulfur, chlorine, and carbon monoxide) of high-temperature pyrolysis of organic compounds. Some actinide oxides (e.g., uranium dioxide and plutonium dioxide) may be entrained by these gases and likewise processed. Treating these effluents

is similar to treating the products from an incinerator. Most of the present off-gas treatment system is made of austenitic stainless steel. Aqueous hydrochloric acid will pit austenitic stainless steel slowly over time.

2.2.2.3 Risks Due to Any Exposed Waste are Within Acceptable Limits. It is possible that the ISV process could expose untreated waste to the environment, posing a hazard to workers and the environment. Subsidence is the main concern when considering the risks of exposing waste due to ISV operations. The normal subsidence that occurs in the ISV process may expose untreated waste on the sidewalls above the melt surface. Also, waste may have been ejected out of the melt and onto either the hood surface or the ground around the melt. Worker safety and containment of exposed waste must be maintained when the hood is removed after processing.

2.2.2.4 Post-Processing Hood Containment Is Maintained as Required. An issue related to exposed untreated waste is maintaining the post-processing hood containment until emissions released from the melt drop below an established level. Once power to the electrodes is terminated, the contaminant release rate from the melt zone decreases with time. These residual vapors and particulates need to be processed by the off-gas treatment system before the hood can be safely removed. Determination of the correct time for hood removal requires careful monitoring with radiation and gas monitors. Premature access to the inside of the hood after the melt process is complete may cause serious injury to ISV workers. Premature hood removal also could produce an environmental release of airborne radiological or hazardous constituents, which might result in occupational exposure or the spread of contamination.

2.2.3 Underground Fires

Ignition and propagation of underground fires are a complex function of the waste composition, moisture content, available oxygen, and ambient pressure. An underground fire related to ISV processing of a waste site is not a problem unless it causes one of the following to occur:

- Surface settlement resulting from subsurface decomposition that may affect normal ISV operations, posing a risk to workers, or exposing previously buried waste.
- Venting of noxious vapors from the surface of the soil not covered by the hood. These vapors may pose a risk to operable personnel.
- A significant change to the site characteristics.

2.2.4 Electrical Hazards

Equipment used to date for ISV has been designed and built to the requirements of the National Electrical Code (NEC) and other codes and standards for electrical equipment. It can, therefore, be assumed that electrical hazards associated with normal operation of lights, heaters, transformers, and off-gas system pump motors are no greater than would be expected for any other industrial operation. However, some electrical hazards have been identified that are somewhat unique to ISV. These hazards include the following:

- The metal containment hood or surrounding support structure becomes electrically energized.
- The possibility of stray currents. This includes both the possibility of stray current corrosion and high energy stray currents that could be hazardous to personnel and equipment.
- Catastrophic failure of electrical power supply equipment, causing system shut-down during a time when off-gas processing is critical.
- Accidental power-up of the system when electrodes are being lengthened, jeopardizing worker safety.

These hazards can be substantially reduced simply through administrative control. However, the hazard of stray current corrosion is not completely understood at this time and, as a result, it is not known how significant a hazard it poses.

3. ISV EVALUATION CRITERIA

Evaluating the ISV technology for application at the INEL SDA requires assessing the possible risks and advantages of the technology as it relates to the following:

- The nine Comprehensive, Environmental, Response, Compensation, and Liability Act (CERCLA) evaluation criteria developed to address CERCLA requirements³
- Other remedial technologies
- The risks of leaving the site unremediated.

Some of the technical issues relate to the feasibility of the ISV process while others are perceived as having possible adverse consequences to human health or the environment. These consequences need to be assessed against the concerns listed above. Each technical issue is a factor that needs to be considered to get a comprehensive picture of the application of ISV at the SDA.

A threat or risk can result from the individual contributions of several technical issues. For instance, consider the risk posed by the ISV process to the health of workers in the immediate hood area. A large pressurization in the hood could possibly allow an escape of hazardous contaminants to the air. Depending on the nature of the release, the release could be a hazard to workers, the community, or the environment. Five issues are related to the ability of the hood to adequately handle pressure transients, (a) explosions causing pressurizations, (b) pressurizations due to the breach of sealed containers, (c) waste falling from the sidewall onto the melt surface, (d) the melt encountering voids, and (e) gases combusting within the hood. The nature of the waste buried at a site determines which of these technical issues are of concern.

The technical issues discussed in the previous section are general to ISV and were developed without consideration to any particular operable unit. Volumes 2

and 3 discuss those technical issues that are applicable to the Acid Pit and TRU-PTs, respectively. Applicable technical issues were determined using historical disposal records characterizing the waste in each operable unit. These records list transuranic radionuclides, inorganic and organic chemical contaminants, boxes, drums, metal, equipment, concrete, and other types of waste. Many significant issues raised by applying ISV to these types of wastes have not been adequately addressed by previous ISV studies and will need to be assessed relative to CERCLA criteria.

The first seven CERCLA criteria address effectiveness, implementability, and cost. That is, how well does ISV reduce the risk at the site while not causing unacceptable risks of its own? Can remediation be accomplished in a reasonable time with the available resources? Does the cost and benefit ratio compare favorably to other alternatives? A remedy is effective when it can achieve acceptable levels of risk (risk targets) both in implementing the remedy and in the product formed.

The regulatory version of the CERCLA is presented in Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA (see Reference 3). For the convenience of the reader a brief paraphrase of the criteria follows.

1. Overall protection of human health and the environment

Each remediation alternative is assessed to determine whether it can adequately protect human health and the environment from unacceptable risks by eliminating, reducing, or controlling exposures to levels established during development of remediation goals. Overall protection of human health and the environment draws on the assessments of other evaluation criteria, especially long-term effectiveness and permanence, short-term effectiveness, and compliance with applicable of relevant and appropriate requirements (ARARs)

2. Compliance with ARARs.

The alternatives are assessed to determine whether they attain ARARs under federal environmental laws and state environmental or facility siting laws [e.g., Clean Water Act, Safe Drinking Water Act, Clean Air Act, Resource Conservation and Recovery Act (RCRA), Standards for Protection Against Radiation, etc].

3. Long-term effectiveness and permanence

The alternatives are assessed for the long-term effectiveness they afford, along with the degree of certainty that the alternative will prove successful. Factors that are considered include the following:

- a. Magnitude of residual risk remaining from untreated waste or treatment residuals at the conclusion of the remedial activities. The characteristics of the residuals should be considered to the degree that they remain hazardous, taking into account their volume, toxicity, mobility, and propensity to bioaccumulate.
- b. Adequacy and reliability of controls such as containment systems and institutional controls that are necessary to manage treatment residuals and untreated waste.

4. Reduction of toxicity, mobility, or volume

The degree to which the alternatives reduce toxicity, mobility, or volume is assessed, including how the different treatments are used to address the principal threats posed by the site. Factors that are considered include the following:

- a. The treatment or recycling processes the alternatives employ and the materials they will treat.

- b. The amount of hazardous substances, pollutants, or contaminants that will be destroyed, treated, or recycled.
 - c. The degree of expected reduction in toxicity, mobility, or volume of the waste due to treatment or recycling and the specification of which reduction(s) are occurring.
 - d. The degree to which the treatment is irreversible.
 - e. The type and quantity of residuals that will remain following treatment.
 - f. The degree to which treatment reduces the inherent hazards posed by principal threats at the site.
5. Short-term effectiveness

The short-term impacts of alternatives are assessed considering the following:

- a. Short-term risks that might be posed to the community during implementation of an alternative.
- b. Potential impacts to workers during remedial action and the effectiveness and reliability of protective measures.
- c. Potential environmental impacts of the remedial action and the effectiveness and reliability of mitigating measures during implementation.
- d. Time until protection is achieved.

6. Implementability

The ease or difficulty of implementing the alternatives are assessed by considering the following types of factors as appropriate:

- a. Technical feasibility, including technical difficulties and unknowns associated with the construction and operation of a technology, the reliability of the technology, ease of undertaking additional remedial actions, and the ability to monitor the effectiveness of the remedy.
- b. Administrative feasibility, including activities needed to coordinate with other offices and agencies and the ability and time required to obtain any necessary approvals and permits from other agencies (for off-site actions).
- c. Availability of services and materials, including the availability of adequate off-site treatment, storage capacity and services; the availability of necessary equipment and specialists and provisions to ensure any necessary additional resources; the availability of services and materials; and availability of prospective technologies.

7. Cost

The types of costs that are assessed include the following:

- Capital costs, both direct and indirect costs (O&M).
- Annual operation and maintenance costs.
- Net present value of capital and O&M costs.

The last two CERCLA criteria are State Acceptance and Community Acceptance. These criteria are addressed in the Community Relations Plan.⁴

Potential technical issues were identified by the ISV Steering Committee and categorized as environmental or safety issues. A preliminary correlation was made between technical issues and CERCLA criteria. Consider the following safety issue as an example: "Off-gas treatment system capacity for treatment of products from within the hood is adequate." If the products within the hood are hazardous and the off-gas treatment system fails to adequately remove them prior to release to the atmosphere, they may pose a threat to the workers or even the community. A release of this nature may violate Clean Air Act, National Environmental Protection Act, State Air Quality, or Occupational Safety and Health Administration regulations. Finally, ensuring that the off-gas system is adequate may depend on the ability to buy or design necessary equipment. Thus, there are potential relationships between the issue of off-gas treatment system capacity and five CERCLA criteria:

- Overall Protection of Human Health and the Environment
- Compliance with ARARs
- Short-term Effectiveness
- Implementability
- Cost.

Closure of the issue in this example would require comparing the risk associated with possible releases to acceptable risk targets (10^{-6} cancer risk, Permissible Exposure Limits, INEL Radiation Exposure Limits, air emission standards, etc.). In some cases these acceptable risk targets have yet to be established. Note that it is not always necessary to collect new data to make this comparison if there is sufficient existing data or if the risks can be assessed through analysis.

To focus the technical issue closure process, the ISV Steering Committee has developed a matrix, shown in Figure 1, that shows the anticipated relationships between ISV technical issues and CERCLA criteria. The potential threats posed

by each issue were determined based upon currently available information about the ISV technology. Any potential relationship between the threats and the CERCLA criteria is represented by a dot on the matrix. Condensation of such a large amount of information onto several pages offers a useful organizational tool for focusing future ISV Steering Committee discussions. The matrix serves to document the technical thought processes delineated in this document. It also provides the scope of the project at a glance. With minor modification this same matrix can show the progress and status of technical issue evaluation and closure. For this reason, as more site characterization and risk baseline information becomes available, the matrix will require periodic revision.

ISV SAFETY ISSUES												
Hazardous/radioactive material is adequately contained by the equipment												
Hazardous/radioactive material is adequately contained by the hood.												
The possibility of criticality is avoided.												
Hood containment seals are adequate.												
Any fires that may occur do not affect the integrity of the hood.												
Hood covers adequate ground area to prevent releases.												
The hood handles pressure transients adequately.												
Any matter ejected from the melt is contained by the hood.												
Indicates Potential Relationship												
No Anticipated Relationship												
CERCLA CRITERIA	Overall Protection of Human Health and Environment											
	Compliance With ARARs											
	Long-Term Effectiveness and Permanence											
	Reduction of Toxicity Mobility and Volume Through Treatment											
	Short-Term Effectiveness											
	Implementability											
	Cost											
	State Acceptance											
	Community Acceptance											

Figure 1. (continued).

ISV SAFETY ISSUES

Hazardous/radioactive material is adequately contained by the equipment.

The off-gas treatment system provides adequate containment and maintains effluents to acceptable levels.

The off-gas treatment system handles pressure transients adequately.

Off-gas treatment system containment seals are adequate.

Off-gas treatment system capacity for treatment of products from within the hood is adequate.

Pressurizations due to explosions remain contained.	T S t
---	-------------

Increases in off-gas due to the breach of pressurized sealed containers are contained and processed adequately	The off-system heat transfer
--	------------------------------

Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface are contained and processed adequately.

Increases in off-gas due to the melt encountering voids are contained and processed adequately.

Excessive off-gas generation caused by combustion is contained.

Any corrosion within the off-gas treatment system does not affect containment of effluents.

Risks due to any exposed waste are within acceptable limits.

Post-processing hood containment is maintained as required.

Underground fires are avoided.

Electrical hazards are controlled:

☐

No Anticipated Relationship

[illegible]

Figure 1. (continued).

4. PRIORITIZATION OF CLOSURE OF THE IDENTIFIED TECHNICAL ISSUES

Although all the identified technical issues are important and must be addressed, the ISV Steering Committee has assigned each technical issue a priority. Technical issues are prioritized to focus the areas of study in this treatability investigation and to ensure the closure process effectively uses available resources while meeting schedule and other programmatic requirements. Furthermore, such a prioritization serves as a rational and technical basis for planning the experimental and analytical programs supporting the closure of these issues. Below is a description of the process the ISV Steering Committee used to identify the criteria for prioritizing the issues, application of these criteria to the technical issues, and the resulting prioritizations of the technical issues for two SDA operable units, the Acid Pit and TRU-PTs. The closure process is discussed in the next section of this document.

The ISV Steering Committee identified nine criteria for prioritizing the technical issues for the closure process. These criteria were weighted by the committee as well. Each committee member was asked to order the prioritization criteria from most important to least important. Each member then assigned the criteria identified as the most important a value of 10, the second most important a value of 9, etc. These ranks developed by the individual committee members were then summed up for each criteria. Table 3 presents the identified prioritization criteria and the resulting relative weights.

Since there are currently two operable units being considered for application of ISV, the issues were prioritized first for the Acid Pit and then for TRU-PTs. This required a listing of assumptions concerning the waste characteristics of each of these units. The assumptions used by the ISV Steering Committee for the Acid Pit are included in Volume 2 and for TRU-PTs in Volume 3.

Table 3. Technical issue prioritization criteria and their statistical relative weights

Applicable/Not Applicable	Yes/No
How probable is it that the issue will be considered relevant (or applicable) to a specific operable unit?	54
How does the issue impact the safety of the ISV process?	36
How does closure of the issue impact the ISV program schedule?	32
Is the issue of particular interest to our customers?	30
To what extent does the issue impact environmental compliance?	29
How far beyond the present bounds of the ISV process is the issue?	19
Is the issue of particular interest to the ISV Steering Committee?	15
What is the perceived cost of closing the issue?	15

The above prioritization criteria were applied to the technical issues in the following manner. A matrix of technical issues versus prioritization criteria was developed for each operable unit. The implications of each technical issue was first discussed among the committee. This was necessary due to the varied backgrounds and areas of expertise of the committee members. Once it was established that each committee member had a clear understanding of the technical issue, the applicability of that particular technical issue to the operable unit under consideration was determined. If the issue was not applicable, the committee continued to the next technical issue. If the issue was applicable, the committee determined the probability that the issue would be an issue for the particular operable unit and assigned it a value ranging from 0 to 4. Each of the other prioritization criteria was then discussed and voted upon as to whether closure of the issue was:

- 4 - Strongly related to the particular prioritization criterion
- 3 - Moderately related to the particular prioritization criterion
- 2 - Related to the particular prioritization criterion
- 1 - Weakly related to the particular prioritization criterion
- 0 - Not related to the particular prioritization criterion

The sum of the individual committee members votes was entered into the matrix and the committee continued to the next prioritization criterion or to the next technical issue. This prioritization process is shown in Figure 2.

Once the matrix was completed, the priority of each issue was calculated. The number specifying the degree of relationship of an issue to a criteria was weighted via multiplying it by the weight of the criteria (ranging from 36 to 15). These weighted numbers for an issue were then summed for all the prioritization criteria, multiplied by the probability that the issue would be an issue, and sorted. The issue that had the highest score received the highest

Figure 2. Flow chart of the issue prioritization process used by the ISV Steering Committee.

priority (#1), the issue with the second highest score received #2 priority, and so forth. As additional information for planning closure of issues, the perceived ease with which an issue can be closed was included with the prioritized list of issues.

Although in some cases the order of the issues was not what the committee would have expected, the committee does believe the order of the issues is technically defensible given the information presently available characterizing the ISV process as well as the operable units. However, as more information becomes available, the committee anticipates that the technical issues will need to be periodically reprioritized. Figure 3 presents the ISV Steering Committee's prioritization of the technical issues associated with application of ISV to the Acid Pit and TRU-PTs, respectively. Blocks with NA indicate that the particular technical issue was determined at this time not to be applicable to that operable unit.

ISV ENVIRONMENTAL ISSUES													
Priority NA = Not Applicable 1 = Highest Priority	Acid Pit Transuranic Pits & Trenches (TRU-PTs)	The durability/quality of the product is acceptable.				Subsurface contaminant migration during processing is within acceptable limits.			Any residual waste is acceptable. That is, the quantity of any waste that is left unprocessed in the soil is acceptable.			Secondary waste streams (effluents from the off-gas treatment system, scrub solutions, HEPA filters, decontamination solutions, etc.) are within acceptable limits.	
		Release characteristics of the product are an acceptable risk to the environment.	The homogeneity and other physical characteristics of the product are well characterized.	The degree and effects of metals pooling in the product are well characterized.	The radiological characteristics of the product are acceptable.	Any enhancements to subsurface contaminant migration provided by subsurface structures (pipes, drum surfaces, voids, etc.) are within acceptable limits.	Subsurface contaminant migration due to the effects of sealed containers is within acceptable limits.	Subsurface contaminant migration due to thermal gradients into surrounding homogeneous soil is within acceptable limits.	The melt width and depth are such that it captures the desired waste.	Melt channelling or preferential flow of the melt through the path of least resistance is predictable and does not impact the capture of the waste intended to be captured.	The quantity of any uncaptured waste between adjacent vitrified blocks is acceptable.		The quantity of any waste that may be encapsulated (unprocessed) within the glass is acceptable.

Figure 3. Prioritization of ISV environmental and safety issues.

ISV SAFETY ISSUES														
Priority NA = Not Applicable 1 = Highest Priority	Acid Pit	The possibility of critically is avoided.												
		Hazardous/radioactive material is adequately contained by the equipment.												
	Transuranic Pits & Trenches (TRU-PTs)	NA	8	Hood containment seals are adequate.	Any fires that may occur do not affect the integrity of the hood.	Hood covers adequate ground area to prevent releases.				The hood handles pressure transients adequately.	Any matter ejected from the melt is contained by the hood.			
						A sidewall collapse does not impact the seal between the hood skirt and the ground.	The melt and thermally altered zone do not extend laterally beyond the hood boundaries.	Pressurizations due to explosions remain contained.	Pressurizations due to the breach of pressured sealed containers remain contained.			Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface remain contained.	Increases in off-gas due to the melt encountering voids remain contained.	Off-gas generation caused by combustion within the hood is contained.
						1	20	23	25			32	4	13

Figure 3. (continued).

ISV SAFETY ISSUES																						
Priority NA = Not Applicable 1 = Highest Priority	Acid Pit Transuranic Pits & Trenches (TRU-PTS)	Off-gas treatment system containment seals are adequate. Off-gas treatment system capacity for treatment of products from within the hood is adequate. Pressurizations due to explosions remain contained. Increases in off-gas due to the breach of pressurized sealed containers are contained and processed adequately. Sudden increases in off-gas due to waste falling from the sidewall onto the melt surface are contained and processed adequately. Increases in off-gas due to the melt encountering voids are contained and processed adequately. Excessive off-gas generation caused by combustion is contained. Any corrosion within the off-gas treatment system does not effect containment or effluents.	The off-gas treatment system handles pressure transients adequately.	The off-gas treatment system provides adequate containment and maintains effluents to acceptable levels.	Hazardous/radioactive material is adequately contained by the equipment.	12	15	18	NA	20	NA	9	10	4	3	17	25	35				
						31	6	17	2	22	23	11	34	19	16	26						
						Post-processing hood containment is maintained as required.												Underground fires are avoided.			Electrical hazards are controlled.	

Figure 3. (continued).

5. DISCUSSION OF THE TECHNICAL ISSUE CLOSURE PROCESS

An ISV technical issue is considered closed when enough information concerning that issue has been gathered to address the CERCLA criteria applicable to that issue. Closure of the technical issues associated with ISV requires an integrated approach using existing data, performing analytical studies, laboratory testing of ISV, and field testing of the ISV technology.

The way that CERCLA criteria are generally addressed is through risk analysis. A baseline risk assessment is done to determine the risk the unremediated waste site poses to the environment, public, and workers near the site. Assessments are also done for the risks associated with remediation of that waste site using a technology such as ISV. Finally, assessments are done for the residual risks to the environment and public associated with the remediated waste site. These assessments may entail comparison of target values (i.e., contaminant migration before and after remediation), calculation of probabilities (the chance of encountering a full gas cylinder), or estimation of a level of uncertainty (the maximum likely surge in off-gas generation rate). Comparisons of these risk assessments determine whether a waste site should be remediated and what technology should be used to remediate the site. Therefore, the technical issue closure process is gathering information to determine the risks associated with that issue. The closure process is not necessarily solving the problems represented by that technical issue. In other words, if the risks associated with a particular technical issue are determined to be acceptable, then that technical issue does not necessarily need to be solved or eliminated.

Since many technical issues are common for different DOE waste sites, technical issue closure will be done through collaboration with the various ISV technology programs (PNL, SRP, ORNL, and Geosafe Corporation). The following paragraph describes a general roadmap of the closure process for a technical issue. The specific roadmaps for closure of the issues associated with the Acid Pit and TRU-PTs are presented in Volumes 2 and 3.

In general, the first step in developing a roadmap for closure of a technical issue is identifying the dominant variables affecting the particular technical issue. Then a review of existing data should be performed. This review involves gathering appropriate data from previous ISV tests and analytical calculations, comparison of the dominant variables in the previous data with the dominant variables in the present technical issue, and finally the determination of the relevance and quality of the existing data in conjunction with scaling considerations for the closure of the technical issue. If it is found that there is sufficient existing data, then the issue may be considered closed. If, however, it is found that either there is not sufficient existing data or that the data is not of sufficient quality, further steps must be taken for closure.

Where additional information is necessary for technical issue closure, it will be obtained through either analytical studies, special "single effects" experiments, laboratory testing, or field testing. Analytical studies can be either specific calculations or complex computer simulations of the ISV process. Currently, the INEL and PNL are working together to develop such simulations of the ISV technology. It may be necessary to design and perform single effects experiments which isolate the phenomena to be studied, hence simplifying the acquisition and evaluation of the desired data. Laboratory tests are actual scaled ISV experiments where the electrode spacing ranges from 8 to 14 in. These tests allow the study of scaled ISV phenomena such as off-gas generation rates and temperature profiles. For phenomena that can not be accurately or confidently scaled, it may be necessary to study the phenomena with field testing. ISV field tests consist of intermediate-scale as well as large-scale tests. Intermediate-scale tests have an electrode spacing of approximately 4 ft while large scale tests have spacings of greater than 15 ft. Field testing allows the study of full-scale phenomena in an environment more closely mimicking an actual site than laboratory conditions permit. Field tests also allow the final proof of principle for phenomena previously studied using analytical studies or laboratory tests.

The determination of whether analytical tools, laboratory tests, or field tests will be used to obtain data concerning a technical issue is not straightforward. Ideally, all technical issues would be studied at the field

scale. However, test costs and duration prohibit extensive field-scale testing. It is recognized that some field-scale tests will be necessary, primarily for the study of phenomena that are difficult to scale. ISV analytical capabilities are currently being developed and expanded to represent phenomena of greater and greater complexity. Current analytical tools are well enough developed to address certain technical issues. It is expected that as more experimental data becomes available to complement and validate these analytical tools, they will become capable of addressing more technical issues. A great deal of this experimental data will evolve from laboratory-scale ISV testing. The size of laboratory-scale tests permits relatively complete instrumentation, short test duration, and reasonable cost compared to field testing.

As is the case with the actual technical issues, the roadmaps for closure of these issues are dynamic and will change with time. For instance, as ISV analytical capabilities improve, more and more technical issues will be addressed through calculations. Also, as the scaling laws related to large-scale remediation become better established, some issues planned for study through field tests can be studied through laboratory-scale tests. Thus, the roadmaps for closure of ISV technical issues will also require periodic review and update.

6. CONCLUSIONS

Global technical issues associated with ISV technology are identified by the ISV Steering Committee. Technical issues applicable to the Acid Pit and TRU-PTs are identified and prioritized. It is recognized that these technical issues and their prioritization will change as knowledge of the ISV process and the operable units improves.

A criteria is suggested for evaluating ISV as a remediation technology. Matrices are presented showing the relationships between the CERCLA evaluation criteria and the various technical issues. These matrices are intended to focus the ISV Demonstration Project by outlining at a glance why each technical issue must be studied for evaluation of ISV application at the SDA.

The technical issue closure process is explained. An ISV technical issue is considered closed when it no longer compromises the safety, feasibility, environmental compliance, and product quality of ISV application at a particular operable unit. Technical issue closure also involves addressing the CERCLA criteria that are applicable to that issue. The closure process does not necessarily solve the problems posed by that technical issue.

7. REFERENCES

1. J. W. Shade, R. K. Farnsworth, and C. H. Kindle, Technical Issues for ISV Processing of Buried Waste Sites, Letter Report, PNL, April 1990.
2. Code of Federal Regulations, 40 CFR 261.3, "Definition of Hazardous Waste," U.S. Environmental Protection Agency, Office of the Federal Register, Washington D.C., Revision 9, February 1, 1990.
3. Environmental Protection Agency, Guidance for Conducting Remedial Investigations and Feasibility Studies Under CERCLA, Interim Final, Office of Emergency and Remedial Response, Washington D.C., EPA 540/G-89/004, October 1988, p. 6-7.
4. DOE-ID, Environmental Restoration Division, Interim Community Relations Plan for Remedial Investigations at the Idaho National Engineering Laboratory, DOE-ID, May 1991.

END

**DATE
FILMED
6 105192**