DOE/PC/90361--T5

CATALYTIC FABRIC FILTRATION FOR SIMULTANEOUS NO_x
AND PARTICULATE CONTROL

DOE/PC/90361--T5

DE92 012639

Quarterly Technical Progress Report
for the period October 1 - December 31, 1991

by

Greg F. Weber, Project Manager
Sumitra R. Ness, Research Engineer
Dennis L. Laudal, Research Engineer
Grant Dunham, Research Engineer

Energy and Environmental Research Center
University of North Dakota
Box 8213, University Station
Grand Forks, ND 58202-8213

Contracting Officer's Representative: Ms. Felixa Eskey

for

U.S. Department of Energy
Pittsburgh Energy Technology Center
626 Cochran Mill Road
Pittsburgh, PA 15236-0940

February 1992

Work Performed Under Contract No. DE-AC22-90PC90361

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

1-10-64 102

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

TABLE OF CONTENTS

	<u>Page</u>
1.0 INTRODUCTION	1
2.0 SCOPE OF WORK	2
3.0 GOALS AND OBJECTIVES	3
4.0 ACCOMPLISHMENTS	4
4.1 Task 2, Design and Construct Test Unit	4
4.2 Subtask 3.1, Fundamental Testing	4
4.3 Subtask 3.2, Process Testing/Reverse-Gas System	6
4.4 Subtask 3.4, Fabric Durability Testing/Pulse-Jet System	17
5.0 KEY PERSONNEL STAFFING REPORT	17
6.0 REFERENCES.	17

LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
1	NO removal efficiency as function of heat-treatment temperature. .	6
2	NO concentration in the flue gas before and after the catalyst-coated filter bags, as a function of time.	9
3	Respirable mass emissions as a function of time (Nov. 18).	10
4	Respirable mass emissions as a function of time (Nov. 19).	11
5	Respirable mass emissions as a function of time (Nov. 20).	11
6	Respirable mass emissions as a function of time (Nov. 21).	12
7	Multicyclone and Coulter Counter data for baghouse ash samples. .	14
8	Pressure drop as a function of time at an air-to-cloth ratio of 2 ft/min.	15
9	Pressure drop as a function of time at an air-to-cloth ratio of 3 ft/min.	15
10	Pressure drop as a function of time at an air-to-cloth ratio of 4 ft/min.	16

LIST OF TABLES

<u>Table</u>		<u>Page</u>
1	Results from Bench-Scale Tests for Evaluation of the Effects of Heat-Treatment Temperatures on Catalyst-Coated Fabric Samples . . .	5
2	Results of Bench-Scale Tests Evaluating the Effects of Operating Temperatures on Heat-Treated Catalyst-Coated Fabric Samples	7
3	Coal and Ash Analysis of Illinois #6 Bituminous Coal Used for Run PTC-IL-408	8
4	Ammonia Slip and SO ₂ Measurements for Run PTC-IL-408	9
5	Particulate Sampling Data	12
6	Multicyclone Data from Run PTC-IL-408	13
7	Ash Analysis of Reverse-Gas Baghouse Hopper Ash from Run PTC-IL-408	14
8	Vanadium Concentrations for Samples Collected during Run PTC-IL-408.	17
9	Planned Versus Actual Workhours for Key Personnel Through December 1991	18

CATALYTIC FABRIC FILTRATION FOR SIMULTANEOUS NO_x AND PARTICULATE CONTROL

1.0 INTRODUCTION

The University of North Dakota Energy and Environmental Research Center (EERC), Owens-Corning Fiberglas Inc. (OCF), and Stearns-Roger, a division of United Engineers & Constructors (UE&C) are conducting research to develop a catalytic fabric filter for simultaneous NO_x and particulate control. Funding for the project is being provided by the U.S. Department of Energy/Pittsburgh Energy Technology Center (DOE/PETC), Consolidated Edison Company of New York Inc. (Con Edison), and the Empire State Electric Energy Research Corp. (ESEERCO).

The DOE/PETC funding was secured as a result of a competitive award from the DOE/PETC Advanced NO_x Control program. The objective of this program is to develop advanced concepts for removal of NO_x from flue gas emitted by coal-fired utility boilers, or for the control of NO_x formation by advanced combustion modification techniques. Funded projects are required to focus on the development of technology that significantly advances the state of the art using a process or a combination of processes capable of reducing NO_x emissions to 60 ppm or less. The concept must have successfully undergone sufficient laboratory-scale development to justify scaleup for further evaluation at the pilot scale (not to exceed 5 MWe in size). Other requirements include production of a nonhazardous waste or a saleable by-product. The concept should have application to both new and retrofit coal-fired systems. The concept should also show the potential for a 50% cost savings when compared to a commercial selective catalytic reduction (SCR) process capable of meeting the 60-ppm NO_x emission limit.

The EERC approach to meeting the program objective involves the development of a catalytic fabric filter for simultaneous NO_x and particulate control. The idea of applying either permanent or throwaway catalysts to a high-temperature fabric filter for NO_x control is not new (1-4). However, advances at OCF have shown that a high-activity catalyst can be applied to a high-temperature woven glass cloth resulting in a fabric filter material that can operate at temperatures higher than the maximum operating temperatures of commercially available, coated glass fabric. The NO_x is removed by catalytic reduction with ammonia to form nitrogen and water. The catalyst employed at this time is vanadium/titanium, but the exact catalyst composition and the unique method of applying the catalyst to high-temperature glass fabric are the property of OCF (5). Other catalyst options are being evaluated by OCF in order to improve catalyst performance and minimize catalyst cost.

Bench-scale experimental results to date have shown that over 90% NO_x removal can be achieved, the catalyst/fabric has promising self-abrasion characteristics, and the potential exists for substantially reduced cost when compared with conventional SCR/fabric filtration technology (6,7). However, development of the technology requires further evaluation of air-to-cloth ratio, ammonia slip, SO₂ oxidation to SO₃, temperature cycling, catalyst-coated fabric preparation, fuel impacts, fabric cleaning (reverse-gas versus pulse-jet), catalyst life (poisoning and resistance to erosion), and filter performance/life (particulate control, differential pressure, and durability).

2.0 SCOPE OF WORK

The specific approach being used to address these issues is represented by the following:

- Task 1 - Program Definition
- Task 2 - Design and Construct Test Unit
- Task 3 - Experimental Program and Data Reduction
- Task 4 - Conceptual Design and Economic Evaluation
- Task 5 - Test Unit Removal

Task 1, Program Definition, required preparation of a Project Management Plan. This document contains a detailed scope of work, project schedule, and project budget; identifies key project personnel; and presents an appropriate QA/QC plan for the project. Task 2, Design and Construct Test Unit, is divided into three subtasks. Subtasks 2.1 and 2.2 involve the detailed design of the test facility on which the experimental program will be performed, the construction of the test facility, and an operational shakedown of the system prior to initiating the experimental effort. Subtask 2.3 involves OCF preparation of the catalyst-coated fabric filters that will be evaluated in the experimental effort.

Task 3, Experimental Program and Data Reduction, has four subtasks. Subtask 3.1, Fundamental Testing, is intended as a support effort to the primary experimental test plan. This effort should supply information needed to thoroughly understand the process mechanism, allow screening of additional fabric samples, address the issue of catalyst poisoning, and generally support the pilot-scale effort. Subtask 3.2, Process Testing/Reverse-Gas System, is intended to evaluate process performance in a pilot-scale reverse-gas fabric filter, identify and optimize important process variables, and provide data for a conceptual design. Subtask 3.3, Process Testing/Pulse-Jet System, will evaluate process performance in a pilot-scale pulse-jet fabric filter. Subtask 3.4, Fabric Durability Testing/Pulse-Jet System, will evaluate catalyst-coated fabric durability/performance for up to 12,000 hours in a slipstream pulse-jet baghouse.

Based on the results of Task 3, a technical and economic assessment of the catalytic fabric filter concept will be completed in Task 4, Conceptual Design and Economic Evaluation. Task 5, Test Unit Removal, requires the identification of all major test facilities, equipment, and instruments and hardware, and their condition, ownership, and proposed disposition.

EERC is the primary contractor for the project and is responsible for the management/direction of all technical and administrative project activities. EERC will specifically perform all work associated with Task 1, Subtasks 2.1 and 2.2, Task 3, and Task 5.

OCF will perform and/or supervise all work associated with Subtask 2.3, including manufacturing the "S" glass fabric, coating the fabric, and manufacturing the filter bags for the reverse-gas and pulse-jet systems. This effort, as well as technical support, will be provided by OCF as a cost share to the project.

UE&C, as a subcontractor to EERC, will provide technical support for Task 1 and will perform Task 4. EERC personnel involved in the Task 3 effort and OCF personnel will provide input to UE&C Task 4 activities.

The project schedule is based on a project start date of October 1, 1990, and assumes a project duration of 36 months. Therefore, the planned project completion date is September 30, 1993.

Federal funding accounts for roughly 56% of the total project budget. Commercial funding for the project makes up the remaining 44%. Con Edison and ESEERCO are each funding 12% of the project cost, and OCF is contributing 10% in the form of catalyst-coated filter bags and technical support for the project. The remaining 10% is uncommitted at this time, but EERC is pursuing funding options in an effort to obtain a formal commitment for the remaining commercial cost share as soon as possible.

3.0 GOALS AND OBJECTIVES

The overall objective of this project is the development of a catalytic fabric filter for simultaneous NO_x and particulate control. The catalytic fabric filter must provide high removal efficiency of NO_x and particulate matter. An acceptable bag and catalyst life must be demonstrated, and process economics must show a significant cost savings when compared to a commercial SCR process and conventional particulate control. Specific goals include the following:

- Reduce NO_x emissions to 60 ppm or less.
- Demonstrate particulate removal efficiency of >99.5%.
- Demonstrate a bag/catalyst life of >1 year.
- Control ammonia slip to <25 ppm.
- Show that catalytic fabric filtration can achieve a 50% cost savings over conventional fabric filtration and SCR control technology.
- Determine compatibility with SO_2 removal systems.
- Show that the concept results in a nonhazardous waste product.

Specific project activities during the past quarter (October through December 1991) were to include the following:

- Complete Task 2, Design and Construct Test Unit.
- Continue Subtask 3.1, Fundamental Testing.
- Continue Subtask 3.2, Process Testing/Reverse-Gas System.

4.0 ACCOMPLISHMENTS

4.1 Task 2: Design and Construct Test Unit

Although the design and construction of both the reverse-gas and pulse-jet baghouses were completed during the previous quarter (July through September 1991), minor modifications and repairs were required during the past quarter. These included installing additional heat tape and insulation to the reverse-gas baghouse. Although the initial shakedown tests were successful, a number of the heat tapes were found to be inoperative following the test. Several of these heat tapes were sent back to the manufacturer, and a defect was found. The replacement heating elements for one reverse-gas chamber were installed the first week in November. After installation, proper operation was verified by measuring current and electrical resistance. Unfortunately, after two days of operation during the first 100-hour test period, 15 of the 18 new elements failed, resulting in poor baghouse temperature control. Two approaches were taken to resolve this problem. New heating elements were ordered from a different vendor, and components were ordered allowing EERC personnel to fabricate the required heating elements in-house. The commercial elements are not scheduled to arrive before mid-January; therefore, the heating elements built in-house were installed in late December and will be used for the 100-hour test scheduled for the second week in January. Following the installation of the new heating elements, additional insulation was also added to each chamber to improve temperature control.

Setup of the Siemens on-line ammonia analyzer was completed with the analyzer, ammonia converter, and heated box mounted on a rack. The purpose of the heated box was to prevent water condensation in the sample lines and flowmeters. A dry vane centrifugal sample pump, designed to operate continuously at 200°-225°F, was purchased.

Since initial tests with the sulfur dioxide adsorbent supplied by Siemens did not justify the \$572/kg cost, a reactor was designed and constructed at EERC. The reactor and sorbent (heated granular sodium carbonate) were tested using Dupont sulfur dioxide analyzers and a 1171-ppm sulfur dioxide/nitrogen gas mixture. Initially, the sodium carbonate was heated to 700°F for 4 hours to develop surface area and then was maintained at 600°F once the gas flow was started. Tests indicated that the reactor controlled sulfur dioxide at undetectable levels for up to 18 hours with 1 kg of the sorbent.

To calibrate the ammonia analyzer, ammonia/nitrogen calibration gases were used (51-ppm ammonia and 93.5-ppm ammonia). Unfortunately, the instrument would not zero and calibrate properly; therefore, several calls were made to Siemens in Germany to gain a better understanding of how the instrument worked and to troubleshoot the problem. It was finally determined that the instrument was not working properly, so it was subsequently returned to Siemens. Until the instrument is working properly, ammonia slip measurements will be made using wet chemistry techniques.

4.2 Subtask 3.1, Fundamental Testing

In support of the first 100-hour pilot-scale test, 26 tests were made in the bench-scale reactor to evaluate the effects of heat treating on catalyst

activity. The first fabric type tested was a light-weight, 14 oz/yd², fabric with a single-beam weave (DE484). The second fabric was a heavier weight, 22 oz/yd², with a double-beam weave (DE992). As part of the catalyst-coating process, an organic binder is used. To obtain the optimum performance of the catalyst-coated fabric, the fabric must be heat-treated to remove the binder. The results of these heat-treatment tests are shown in Table 1. As shown in Figure 1, at a constant air-to-cloth ratio, operating temperature, heating time, and ammonia/NO molar ratio, the percent NO removal appears to increase linearly with heat treatment temperature. Although it is known that at high temperatures (>800°F) the catalyst begins to sinter, it appears that after 1 hour of heat-treating at 750°F, the percent NO removal is still increasing for both the DE992 and DE484 fabrics. Therefore, the optimum heat-treating temperature and heating time for the full-scale bags has yet to be determined, so further tests are needed. Tests are being planned to increase the heat-treatment temperature until the NO removal efficiency begins to deteriorate.

TABLE 1

Results from Bench-Scale Tests for Evaluation of the Effects of Heat-Treatment Temperatures on Catalyst-Coated Fabric Samples

Fabric Type	Treatment Temp. (°F)	Treatment Time (hours)	Operating Temp. (°F)	NO Removal (%)	Ammonia Slip (ppm)
DE484	504	1	650	48.0	400
DE484	563	1	650	64.0	170
DE484	589	1	650	67.0	280
DE484	613	1	650	68.0	180
DE484	636	1	650	70.0	170
DE484	669	1	650	70.0	180
DE484	693	1	650	77.0	130
DE484	718	1	650	82.6	44
DE484	747	1	650	90.0	7
DE992	504	1	650	71.0	105
DE992	523	1	650	75.5	85
DE992	563	1	650	82.0	40
DE992	589	1	650	86.2	28
DE992	613	1	650	86.5	25
DE992	636	1	650	87.0	25
DE992	669	1	650	87.0	25
DE992	693	1	650	90.0	15
DE992	718	1	650	93.4	14
DE992	745	2	650	89.0	26
DE992	747	1	650	91.6	13

Figure 1. NO removal efficiency as function of heat-treatment temperature.

Several of the test samples which were heat treated at temperatures below 650°F were tested both at the treatment temperature and at 650°F (Table 2). As would be expected, all showed a marked increase in NO removal efficiency at the higher temperature. In addition, the samples tested at 650°F did not reach steady-state after 30 minutes, but continued to show an increase in NO removal. This indicates that at lower temperatures (<600°F), the fabric samples had not been adequately heat treated, and the heat-treatment process continued when the temperature was increased to 650°F.

Ammonia slip measurements were made at the outlet of the reactor. As shown in Tables 1 and 2, the ammonia slip results were consistent, in most cases, with what would be expected at an ammonia/NO molar ratio of 0.9.

4.3 Subtask 3.2, Process Testing/Reverse-Gas System

Subtask 3.2, Process Testing/Reverse-Gas System, was initiated with completion of the first 100-hour test (PTC-IL-408). The purpose of the test was to determine the effectiveness of a catalyst-coated fabric filter in a pilot-scale reverse-gas baghouse to simultaneously control particulate and nitric oxide (NO) emissions. In the original test plan, twelve individual experimental periods were planned in order to address the effects of air-to-cloth ratio (1.5, 2, 3, 4 ft/min) and ammonia/NO molar ratio (0.8, 0.9, 1.0). Baghouse temperature was to be held constant at 650°, and flue gas was generated by firing a washed Illinois #6 bituminous coal in a pilot-scale pc-fired combustor. The ultimate, proximate, and sieve analyses for the washed Illinois #6 fuel used for this test are presented in Table 3.

TABLE 2

Results of Bench-Scale Tests Evaluating the Effects of Operating Temperatures on Heat-Treated Catalyst-Coated Fabric Samples

Fabric Type	Treatment Temp. (°F)	Treatment Time (hours)	Operating Temp. (°F)	NO _x Removal (%)	Ammonia Slip (ppm)
DE484	504	1	504	18.0	670
DE484	504	1	650	48.0	400
DE484	589	1	589	58.0	380
DE484	589	1	650	67.0	280
DE992	504	1	504	50.0	440
DE992	504	1	650	71.0	105
DE992	523	1	523	60.0	315
DE992	523	1	650	75.5	85
DE992	589	1	589	82.0	40
DE992	589	1	650	84.8	51

Owens-Corning Fiberglas Inc. provided three (two for testing and one spare) catalyst-coated reverse-gas filter bags (12 inches in diameter by roughly 26 feet long) for this test. The filter bags were prepared using a 14-oz/yd² high-temperature, woven-glass fabric. Seven coats of a vanadium/titanium catalyst were applied to the fabric corresponding to Fabric #17 (OCF-106A) in previous bench-scale tests.

In general, the results from the 100-hour test period were unsatisfactory due to inadequate temperature control in the reverse-gas baghouse and inadequate heat treatment of the catalyst-coated filter bags prior to bag installation for the 100-hour test. Baghouse temperature control problems were a direct result of the failure of new heating elements installed on both reverse-gas chambers prior to the 100-hour test.

Although temperature control was a problem, previous bench-scale results indicated that, with this fabric (OCF-106A), NO reduction should have ranged as high as 70% to 80% at a baghouse temperature of 550°F. During the week of operation, the average baghouse temperature ranged from roughly 530° to 650°F. The NO removal efficiency for 100-hour test is shown graphically in Figure 2. The removal efficiency varied between 10% and 50% depending on operating conditions. At a baghouse temperature of 635°F and an air-to-cloth ratio of 2 ft/min (two bags on-line), NO reduction was roughly 50%. When baghouse temperature fell to 600°F and air-to-cloth ratio was increased to 4 ft/min (one bag on-line), NO reduction was only 11%.

TABLE 3

Coal and Ash Analysis of
Illinois #6 Bituminous Coal Used for Run PTC-IL-408

	As-Received	Moisture-Free		
<u>Proximate Analysis (wt%)</u>				
Moisture	8.00	---		
Volatile Matter	34.29	37.26		
Fixed Carbon	45.81	49.82		
Ash	11.89	12.92		
<u>Ultimate Analysis (wt%)</u>				
Hydrogen	4.98	4.45		
Carbon	62.19	67.57		
Nitrogen	1.11	1.20		
Sulfur	3.30	3.58		
Oxygen	16.51	10.25		
Ash	11.89	12.92		
<u>Heating Value (Btu/lb)</u>	11,143	12,107		
<u>Oxides (% of ash)</u>				
SiO ₂	47.20			
Al ₂ O ₃	20.10			
Fe ₂ O ₃	16.70			
TiO ₂	0.79			
P ₂ O ₅	0.37			
CaO	4.92			
MgO	1.41			
Na ₂ O	0.78			
K ₂ O	1.94			
SO ₃	5.70			
<u>Ash Fusion</u>				
<u>Temp. (°F)</u>	Initial	Softening	Hemisphere	Fluid
	2,222	2,263	2,317	2,353
<u>Sieve Analysis</u>				
Screen Mesh Size	% Retained			
100	14.40			
140	12.02			
170	5.34			
200	8.55			
270	12.14			
325	1.00			
Pan	45.54			
Total %	98.99

Figure 2. NO concentration in the flue gas before and after the catalyst-coated filter bags, as a function of time.

Results from ammonia slip and SO₃ measurements using wet chemistry techniques are shown in Table 4. Ammonia-slip measurements were made during particulate-sampling periods and tended to confirm low NO removal efficiency. The SO₃ measurements were well within the range expected for a 3% sulfur coal. Little if any conversion of SO₂ to SO₃ occurred across the catalyst-coated filter bags.

TABLE 4

Ammonia Slip and SO₃ Measurements
for Run PTC-IL-408

Date	NO Removal (%)	Ammonia Slip (ppm)	SO ₃ Conc. (ppm)
11-18-91	13.0	511	--
11-18-92	20.2	380	--
11-19-92	21.0	--	1.3
11-20-91	29.3	187	7.5
11-21-91	28.8	230	1.0

When it became apparent that the catalyst-coated filter bags were not performing as anticipated, EERC personnel requested that OCF and/or Menardi-Criswell locate and expedite shipment of fabric samples left over from the construction of the catalyst-coated filter bags. EERC personnel used these fabric samples to perform bench-scale screening tests in an effort to determine if the fabric had been adequately heat-treated. The bench-scale tests confirm that the full-scale bags had not been adequately heat treated, which resulted in poor NO removal efficiency. However, the bench-scale results also indicated that, with proper treatment, up to 90% removal efficiency is expected with this fabric.

Although the tests were not successful in achieving high levels of NO removal, extensive pressure drop and particulate emissions data were obtained. Using an aerodynamic particle laser device (APS), respirable mass as a function of time was plotted for each day of the test. These results are shown in Figures 3-6. As can be seen, the outlet respirable mass emissions averaged about 0.01 mg/m^3 . This corresponds to a collection efficiency of 99.99%, based on an inlet respirable mass loading of 100 mg/m^3 . Tables 5 and 6 summarize EPA Method 5 and multicyclone particulate-sampling data. The particulate mass loading in the flue gas prior to the reverse-gas baghouse ranged from 2.5 to 3.3 grains/scf. The overall collection efficiency for the reverse-gas baghouse ranged from 99.79% to 99.97% depending on operating

Figure 3. Respirable mass emissions as a function of time (Nov. 18).

Figure 4. Respirable mass emissions as a function of time (Nov. 19).

Figure 5. Respirable mass emissions as a function of time (Nov. 20).

Figure 6. Respirable mass emissions as a function of time (Nov. 21).

TABLE 5

Particulate Sampling Data

Test Date	Test No.	Inlet (gr/scf)	Outlet (gr/scf)	H ₂ O (%)	Efficiency (%)
08-28-91	Shakedown	3.4774	---	10.5	---
08-28-91	Shakedown	---	0.0015	9.1	99.96
08-28-91	Shakedown	2.6611	---	10.2	---
11-18-91	IL6-408	3.1843	---	10.7	---
11-18-91	IL6-408	---	0.0028	8.1	99.91
11-18-91	IL6-408	---	0.0036	7.8	99.89
11-19-91	IL6-408	2.7771	---	5.2	---
11-19-91	IL6-408	---	0.0008	7.5	99.97
11-19-91	IL6-408	2.8891	---	7.6	---
11-20-91	IL6-408	3.1090	---	9.6	---
11-20-91	IL6-408	---	0.0065	7.9	99.79
11-21-91	IL6-408	3.3357	---	9.1	---
11-21-91	IL6-408	2.4938	---	3.9	---
11-22-91	IL6-408	---	0.0014	7.6	99.94
11-21-91	IL6-408	3.1910	---	8.1	---
11-22-91	IL6-408	---	0.0008	7.6	99.97

TABLE 6
Multicyclone Data from Run PTC-IL-408

11-19-91	CY1	CY2	CY3	CY4	CY5	Backup Filter
D ₅₀ (μm)	8.66	4.28	2.91	1.47	0.91	---
Mass Collected (g)	1.8436	0.2010	0.1243	0.0507	0.0250	0.0216
% Total Mass	81.35	8.87	5.49	2.24	1.10	0.95
Cumulative % Mass less than D ₅₀	18.65	9.78	4.29	2.05	0.95	---
Total Mass Collected = 2.2662 g Dust Loading = 2.7771 gr/scf						
11-19-91	CY1	CY2	CY3	CY4	CY5	Backup Filter
D ₅₀ (μm)	10.16	5.37	3.83	1.93	1.15	---
Mass Collected (g)	0.7680	0.0881	0.0938	0.0496	0.0439	0.0244
% Total Mass	71.92	8.25	8.78	4.11	4.11	2.29
Cumulative % Mass less than D ₅₀	28.08	19.82	11.09	6.40	2.29	---
Total Mass Collected = 1.0678 g Dust Loading = 2.4938 gr/scf						

conditions. Multicyclone sampling at the inlet of the baghouse was completed in order to determine the aerodynamic particle size of the fly ash in the flue gas stream entering the baghouse. Also from the multicyclone and Coulter Counter data, shown in Figure 7, the mass median diameter (volumetric median diameter) of the fly ash was determined to be about 17 micrometers.

Bulk ash samples collected from the hopper of the reverse-gas baghouse were analyzed for carbon and major elements. The carbon content of the ash as determined by loss on ignition averaged 3.7%. Table 7 presents the major elements, as determined by x-ray fluorescence (XRF) analysis.

The second aspect of fabric filtration performance evaluated was the operational pressure drop. The bags were cleaned such that the maximum pressure drop was approximately 4 inches W.C. As expected, the time between cleaning was dependent on the air-to-cloth ratio, as shown in Figures 8-10. Beginning with new bags, at an air-to-cloth ratio of 2 ft/min, it took 14 hours to reach 4 inches W.C. From that point on, the bags were cleaned every 8 hours. When the

Figure 7. Multicyclone and Coulter Counter data for baghouse ash samples.

TABLE 7

Ash Analysis of Reverse-Gas Baghouse Hopper Ash
from Run PTC-IL-408

	Reverse-Gas Baghouse Sample #1	Reverse-Gas Baghouse Sample #2
Loss on Ignition	3.56	3.84
Oxides (% of ash)		
SiO ₂	50.80	50.50
Al ₂ O ₃	20.70	20.90
Fe ₂ O ₃	16.30	16.10
TiO ₂	0.90	0.98
P ₂ O ₅	0.24	0.30
CaO	3.93	3.43
MgO	1.11	1.07
Na ₂ O	0.82	0.84
K ₂ O	1.99	1.98
SO ₃	3.23	3.77

Figure 8. Pressure drop as a function of time at an air-to-cloth ratio of 2 ft/min.

Figure 9. Pressure drop as a function of time at an air-to-cloth ratio of 3 ft/min.

Figure 10. Pressure drop as a function of time at an air-to-cloth ratio of 4 ft/min.

air-to-cloth ratio was increased to 3 ft/min, bag cleaning was required every 4 hours. When the air-to-cloth ratio was increased to 4 ft/min, the time interval between bag cleaning decreased to one-half hour. In addition, the pressure drop immediately following cleaning increased with increased air-to-cloth ratio, 0.3 inches, 1 inch, and 2 inches W.C., respectively.

A concern with the use of catalyst-coated bags is the possibility of catalyst erosion resulting in an increase in the vanadium content of the fly ash. Because vanadium is listed as a RCRA element and some vanadium compounds are considered to be hazardous materials, it is important to monitor vanadium concentration in the fly ash. Table 8 presents the vanadium content of the coal, fly ash from the inlet to the reverse-gas baghouse, and ash from the baghouse hopper as determined by atomic absorption analysis. From the results, it appears that during the 100-hour test period there was no erosion of the vanadium catalyst from the bags. When comparing the vanadium concentration in the inlet fly ash to the theoretical concentration based on the concentration of vanadium and ash in the coal, there is a distinct increase in the vanadium concentration in the fly ash. An explanation is that vanadium is known to be enriched in the fine particulate matter (8). Although the concentration of vanadium in the combustor bottom ash is not known, it is expected to be less than the concentration of the fly ash, which would provide an overall mass balance of vanadium.

TABLE 8.

Vanadium Concentrations for Samples Collected
during Run PTC-IL-408

Sample Source	Vanadium (ppm)
Inlet Sample #1	220
Inlet Sample #2	250
Outlet Sample #1	<10 ^a
Outlet Sample #2	<10 ^a
Hopper Ash Sample #1	240
Hopper Ash Sample #2	250
Coal Composite	19
Coal Ash (11.89% ash)	160 ^b

^a Since very little ash was collected on the dust loading filter, accurate measurements were not possible.

^b Calculated theoretical concentration base on concentration in the coal and the ash content.

4.4 Subtask 3.4, Fabric Durability Testing/Pulse-Jet System

Subtask 3.4 activities were initiated in September in order to prepare the baghouse slipstream system at the UND steam plant for operation. Preparation of the baghouse slipstream system has been completed, and the long-term catalyst-coated filter bag performance/durability test can begin as soon as a set of pulse-jet filter bags are available. Selection of a fabric type can hopefully take place during the project review meeting scheduled for the first week in March.

5.0 KEY PERSONNEL STAFFING REPORT

Table 9 presents planned versus actual workhours for key EERC and UE&C personnel involved in the Catalytic Fabric Filtration project through December 1991.

6.0 REFERENCES

1. Pirsh, E.A. U.S. Patent 4 220 633, September 2, 1980, assigned to Babcock and Wilcox Co.
2. Pirsh, E.A. U.S. Patent 4 309 386, January 5, 1982, assigned to Babcock and Wilcox Co.
3. Doyle, J.B. et al. U.S. Patent 4 793 981, December 27, 1988, assigned to Babcock and Wilcox Co.

TABLE 9

Planned Versus Actual Workhours
for Key Personnel Through December 1991

Key Personnel	Planned Hours	Actual Hours	% of Total Available Workhours Used
Greg Weber	1031	830	80
Dennis L. Laudal	1512	416	28
Chris Robie	29	16	55

4. Weber, G.F. "SO_x/NO_x Control, Low-Rank Coal Research under the UND/DOE Cooperative Agreement," Quarterly Technical Progress Report, University of North Dakota Energy and Environmental Research Center, Grand Forks, ND, DOE/FE/60181-1531, January 1984, Section 6.
5. Kalinowski, M.R.; Nishioka, G.M. "Method for Applying Porous Metal Oxide Coatings to Relatively Nonporous Fibrous Substrates," United States Patent No. 4 732 879, March 22, 1988.
6. Weber, G.F.; Laudal, D.L. "SO_x/NO_x Control - Catalytic Fabric Filtration for Simultaneous NO_x and Particulate Control," Final technical report for the period April 1, 1988, through June 30, 1989; Grand Forks, ND, DE-FC21-86MC10637, August 1989.
7. Weber, G.F.; Miller, S.J.; Laudal, D.L. "Flue Gas Cleanup," Final technical report for the period July 1, 1989, through June 30, 1990; Grand Forks, ND, DE-FC21-86MC10637, October 1990.
8. Markowski, G.W.; Filby, R. "Trace Element Concentration as a Function of Particle Size in Fly Ash from a Pulverized coal Utility Boiler," *Environmental Science and Technology* 1985, 19 (9).

END

**DATE
FILMED
6/12/92**