**Idaho
National
Engineering
Laboratory**

*Managed
by the U.S.
Department
of Energy*

EGG-WM-10109
February 1992

INFORMAL REPORT

Received by OSTI
APR 27 1992

**Full-Scale Tests of Sulfur Polymer
Cement and Non-Radioactive Waste
In Heated and Unheated
Prototypical Containers**

**G. Ross Darnell
Wesley C. Aldrich
John A. Logan**

*Work performed under
DOE Contract
No. DE-AC07-76ID01570*

This document contains new concepts or the author(s) interpretation of new calculations and/or measurements; accordingly, EG&G Idaho, Inc. is required by the United States Government to include the following disclaimer:

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights. References herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

EGG-WM--10109

DE92 012369

Full-Scale Tests of Sulfur Polymer Cement And Non-Radioactive Waste In Heated and Unheated Prototypical Containers

**G. Ross Darnell
Wesley C. Aldrich
John A. Logan**

Published February 1992

**Idaho National Engineering Laboratory
EG&G Idaho, Inc.
Idaho Falls, Idaho 83415**

**Prepared for the
U.S. Department of Energy
Assistant Secretary for Environmental Restoration and Waste Management
Under DOE Field Office, Idaho
Contract DE-AC07-76ID01570**

MASTER

EP

ABSTRACT

Sulfur polymer cement has been demonstrated to be superior to portland cement in the stabilization of numerous troublesome low-level radioactive wastes, notably mixed waste fly ash, which contains heavy metals. EG&G Idaho, Inc. conducted full-scale, waste-stabilization tests with a mixture of sulfur polymer cement and nonradioactive incinerator ash poured over simulated steel and ash wastes. The container used to contain the simulated waste for the pour was a thin-walled, rectangular, steel container with no appendages. The variable in the tests was that one container and its contents were at 65°F (18°C) at the beginning of the pour, while the other was preheated to 275°F (135°C) and was insulated before the pour. The primary goal was to determine the procedures and equipment deemed operationally acceptable and capable of providing the best probability of passing the only remaining governmental test for sulfur polymer cement, the Nuclear Regulatory Commission's full-scale test. The secondary goal was to analyze the ability of the molten cement and ash mixture to fill different size pipes and thus eliminate voids in the resultant 24 ft³ monolith.

ACKNOWLEDGMENTS

The authors want to thank Mr. William C. McBee, Principal, McBee and Associates, who was the primary developer of sulfur polymer cement. His constant support in providing answers to our questions was invaluable. Other contributing experts in various areas vital to these tests were: Mr. Harold H. Weber, Director of Industrial Programs, The Sulphur Institute; Dr. Gretchen E. Matthern, Senior Program/Project Engineer, EG&G Idaho, Inc.; Mr. Paul D. Kalb, Project Engineer, Waste Management Research and Development, Brookhaven National Laboratory; Mr. Frank E. Ward, President, F. E. Ward Constructors; Mr. William T. Dohner, Chairman, Chempruf Technical Committee; Mr. James A. Reece, President, J. A. Reece, Inc.; Mr. Thomas H. Saunders, Product Test Coordinator, Denver Equipment Company; and Ms. Brenda J. Wolfe, Applications Engineer, Denver Equipment Company. We also want to thank the Environmental Chemistry Unit of EG&G Idaho, Inc.

EXECUTIVE SUMMARY

The use of sulfur polymer cement (SPC) in solidification and stabilization of radioactive wastes is a most attractive prospect for treatment of incinerator ash which contains heavy metals that have been oxidized and readily combine with the molten SPC to form metal sulfides and sulfates that resist leaching. Brookhaven National Laboratory has combined SPC with 43wt% mixed-waste^a fly ash from the Waste Experimental Reduction Facility at the Idaho National Engineering Laboratory, and successfully passed all of the lab-scale tests required by the U.S. Environmental Protection Agency and U.S. Nuclear Regulatory Commission (NRC).^{1,2,3,4,5,6} The NRC's full-scale test is the only remaining test needed to prove SPC to be the strongest candidate for solidification and stabilization of hazardous, radioactive, and mixed waste incinerator ash, and many other troublesome wastes.⁷

In anticipation of the need for SPC in future radioactive waste treatment and disposal efforts, it is necessary to select equipment with fundamentally good performance and the least probability of failure in operating conditions and in conducting the NRC full-scale test. This report describes full-scale SPC tests conducted in the laboratory of the Denver Equipment Company in Colorado Springs, Colorado. The tests were designed to evaluate the performance of equipment for mixing SPC, a thermoplastic that melts at 230°F (110°C), while testing new concepts in reinforced, thin-walled, steel, waste disposal containers that will stack in concrete disposal vaults with virtually no voids between containers.

The tests were also intended to determine if a pour could be made in a waste disposal container with its carbon-steel pipe and hearth ash contents at room temperature and provide an essentially void-free concrete of good quality, or whether the container and its contents would have to be preheated

a. Mixed waste is a waste that is hazardous and is also radioactively contaminated.

for best results. The tests were conclusive. After sawing each of the resultant SPC castings into eight equal-sized blocks for examination, researchers found that the preheated container and contents definitely produced a better flow of SPC than the unheated container, and therefore left fewer voids. While the preheated system provided better concrete, it was found that the insulated container and its contents did cool as the 4-hour pour progressed; and therefore, voids increased progressively in the upper reaches of the container. These findings were convincing--the container and its contents should be preheated to, and maintained at, the optimum SPC temperature throughout the pour to eliminate all avoidable voids and provide a high-stability concrete. Doing this will also increase the cross-linking between the waste and the SPC.

The test mixer's throughput of molten SPC-and-ash mixture was 5.4 ft³/h. The researchers discussed a number of modifications that would increase the throughput dramatically, and at the same time ensure excellent blending of SPC and ash while improving the concrete's mechanical properties. These efforts would improve the probability of success in the NRC's full-scale test. Detailed test results and recommendations for future SPC tests are included in this report.

CONTENTS

ABSTRACT	iii
ACKNOWLEDGEMENTS	iv
EXECUTIVE SUMMARY	v
1. INTRODUCTION	1
2. OBJECTIVES FOR TESTS 1 AND 3	4
3. BACKGROUND AND PREPARATION FOR THE TESTS	7
3.1 Waste Disposal Containers	7
3.2 Mold-Form	8
3.3 Simulated Waste in the Disposal Containers	11
3.4 Ratios of Incinerator Hearth Ash and SPC	19
3.5 Mixer Characteristics	19
3.6 Testing for Temperature Influence on Pour Success	22
4. THE TESTS	26
4.1 Test 1	26
4.2 Test 3	33
4.3 Development of the Concrete Mass During Both Tests	39
4.4 Larger Fragments of Hearth Ash May Float Upward in Molten SPC	39
4.5 Checking Test Results	41
5. CONCLUSIONS	47
5.1 Improved Blending and Melting	48
5.2 Improving the SPC Concrete	48
5.3 Starting and Stopping Pour	52
5.4 Computer Controls for SPC Exit Temperature	52
6. RECOMMENDED FUTURE FULL-SCALE TESTS	56
6.1 Increased Throughput Test	56
6.2 Test 4	56
6.3 Test 5	61
6.4 Test 6	63
6.5 Test 7	64
8. REFERENCES	66

FIGURES

1. Drawing used to fabricate the prototypical waste disposal container	9
2. Drawing used to fabricate the mold-form	12
3. Drawing used to fabricate arrangements of test steel waste	17
4. Plan for cutting test disposal container into sections	20
5. Rotating shaft and its flites are heated with internal hot oil	24
6. Artist's drawing of the SPC pouring concept	53
7. Artist's drawing of SPC and ash flow control	54

CONTENTS (continued)

PHOTOGRAPHS

1.	A prototypical waste disposal container	10
2.	A waste container filled with the SPC-and-ash mixture	13
3.	Test Hearth ash, the large fraction	15
4.	Test hearth ash, the small fraction	15
5.	The top tier in the simulated waste stack, 1-in. pipes	18
6.	Waste container was cut along the center line	21
7.	The Holo-Flite Processor (SPC-and-ash mixer)	23
8.	Blending SPC and ash in the mixer	25
9.	The mold-form and contained disposal container	27
10.	Mating the mold-form and disposal container to the mixer	28
11.	SPC used in the tests	29
12.	A carpenter's level establishes 3/4 in. container tilt	30
13.	Stalagmites seen through gap between mixer and container	32
14.	Erratic SPC flow in room-temperature pour	34
15.	Ash being weighed for test	35
16.	Hand blending of SPC and ash in mixer's feed trough	36
17.	Insulation surrounds the mold-form and container	38
18.	Voids resulting from loss of heat	40
19.	Results of using room-temperature waste	42
20.	The bottom segment of concrete from room-temperature pour	43
21.	Results of the preheated test	44
22.	Results of using preheated container and waste	45
23.	Filled 1 in. pipes in preheated test	46
24.	The large shafts through which hot oil flows	49
25.	Blending and melting of SPC	50
26.	Mixing lugs on flites are proposed for next tests	51
27.	The mixer's off-gas system	58
28.	Horizontal centerline cut through room-temperature pour	59

APPENDIX

APPENDIX A.	BOTTOM ASH SAMPLES	A-1
-------------	------------------------------	-----

Full-Scale Tests of Sulfur Polymer Cement And Non-Radioactive Waste In Heated and Unheated Prototypical Containers

1. INTRODUCTION

The greatest enemy of hazardous and radioactive waste is water. Sulfur polymer cement (SPC) will not accommodate water in the concrete because steam vents will form as it hardens, thus weakening the concrete. SPC chemically bonds with the heavy metal oxides in incinerator ash, converting them to less-soluble metal sulfides and a small percentage of sulfates. SPC has proven superior to hydraulic cements in stabilizing mixed-waste fly ash.^{3,4,5} Hydraulic cements activated by water, routinely contain water, are not impermeable to water, and do not readily combine chemically with heavy metals.³ To create the best grade of SPC concrete, all water must be removed from the waste prior to mixing with SPC. The effort of removing that water goes hand in hand with the creation of SPC concrete in an operational facility because the ash is hot and devoid of water when removed from the incinerator and its heat can be maintained essentially with insulation until it is combined with SPC.

Choosing the best equipment for exemplary waste stabilization must be based on firm criteria. Ultimate success in disposal vaults such as the abovegrade, earth-mounded, concrete vault (AGEMCV)⁸ requires the use of an entirely new concept in waste disposal containers for concreted waste. Since the Idaho National Engineering Laboratory (INEL) plans to use concrete vaults, it was logical to establish a compatible system in the search for the best opportunity to pass the NRC's full-scale test. The new containers are intended to reduce cost, minimize human involvement, eliminate essentially all voids in the waste stack, eliminate subsidence, and maximize environmental protection.^{9,10} Therefore, a prototypical container was used in the tests described in this report.

To prepare for the tests, suppliers of Chempruf (trade name for SPC) were visited to discuss the idiosyncrasies of handling and mixing SPC.^{11,12,13} Manufacturers of heated mixers suitable for SPC were also visited.^{14,15} A pour in a 1m x 1m x 1m wooden box partially filled with simulated steel waste was successfully completed.¹⁶ Techniques, equipment, and limitations were discussed in a meeting with national SPC experts.¹⁷ Pours were completed on a small 3-in. diameter screw mixer.¹⁵ With the accumulated information, the next phase of testing was established and implemented.

The SPC mixers used by Brookhaven National Laboratory are of insufficient size and design to use in an operational waste treatment facility. SPC mixers used in the construction industry are too large and do not lend themselves to a contaminated environment. Therefore, a mixer was needed that would meet the operational goals of radioactive and mixed waste treatment facilities. The prototypical waste disposal container and support equipment need testing. Test goals were established and the required test equipment was manufactured and/or procured by EG&G Idaho, Inc. All test materials were shipped to the Denver Equipment Company in Colorado Springs, Colorado. The tests were conducted in their laboratory with their Holo-Flite Processor, hereafter referred to as the "mixer."

The driving force behind these full-scale tests is the successful testing accomplished by the U.S. Bureau of Mines (the developer of SPC), by the construction industry, and by Brookhaven National Laboratory (initially funded by the Defense Low-Level Waste Management Program at EG&G Idaho, and later by the Hazardous Waste Remedial Action Program (HAZWRAP)).¹⁵ All of the Environmental Protection Agency's (EPA's) and Nuclear Regulatory Commission's (NRC's) required laboratory tests have been successfully completed using the Waste Experimental Reduction Facility's (WERF's) mixed-waste fly ash.¹⁵ The only remaining test is the NRC's full-scale test with WERF's mixed-waste fly ash.

The tests reported here were multipurpose tests that (a) prepare for the full-scale test of SPC, (b) provide factual data for design of an operational SPC concreting system, (c) explore possibilities for improving SPC mixing

equipment and procedures. (d) evaluate the waste disposal container designed specifically for an abovegrade, earth-mounded, concrete vault (AGEMCV),¹⁶
(e) test the mold-form that supports the container during filling and curing, and determine whether or not a heated container is needed to minimize voids in the concrete and maximize cross-linking.

2. OBJECTIVES FOR TESTS 1 AND 3

As more test data are being accumulated, SPC is showing ever increasing potential as a waste stabilization agent. Most tests have been laboratory-scale tests. The tests reported here are intended to answer questions remaining in the full-scale test and operational arenas. The two tests reported here were intended to meet the following objectives:

1. First and foremost, ensure that a full-scale test with mixed-waste fly ash is warranted.
2. Develop a test scenario that will ensure a positive opportunity for passing NRC's full-scale test on the first try and for passing the EPA's Toxicity Characteristic Leaching Procedure (TCLP) test as well. (Note: even though the U.S. Department of Energy (DOE) is not required to comply with NRC's tests, they are reasonable tests and lend credence to efforts conducted by the DOE towards radioactive and mixed waste stabilization.)
3. Provide data for design, procurement, and construction of a viable full-scale test system that might be used in an operational SPC waste stabilization system.
4. Test the selected off-the-shelf mixing equipment against needs, and explore possibilities for mixing-equipment improvements.
5. Evaluate and address improvements for the waste disposal container designed specifically for placement in an AGEMCV, or any other concrete vault.
6. Evaluate and address improvements for the mold-form and its sprues.
7. Determine if having the container corner at the overflow sprue

3/4-in. higher than the corner with the input sprue will cause the SPC concrete to make full contact with the lid.

8. Determine if the SPC concrete filled the container enough to support the lid and five other similar containers stacked on top (visual inspection assessing the voids and general condition of the SPC concrete).
9. Determine the molten SPC-and-ash mixture throughput rate and look for methods to increase it.
10. Determine the blending capability of the mixer and look for methods to improve it, if required.
11. Determine to what degree the large-fraction hearth ash on the floor of the container will be "wetted" by the molten SPC and thus become an integral part of the concrete. To do this, establish two different temperature scenarios using the same test equipment:
 - a. Test-1 container and its contents are at room temperature at the start of the pour.
 - b. Test-3 container and its contents are heated overnight in an oven to 275°F (135°C) and are covered with insulation to help maintain the pre-heat temperature during the pour.

Note: Originally three tests were planned, with provisions for an optional fourth test (to be determined at the time of the testing). Test 2 was to be the same as Test 1, except that four 8-in. layers of SPC would be poured into a room-temperature container with 30 minute intervals between the pours. This test was cancelled.

12. Saw each concreted container into eight equal-sized sections and estimate the difference in quantity of voids between the cold-

container and the hot container. Also examine the concrete texture differences between the test specimens.

13. Determine if the container walls are flat after removal from the mold-form.

3. BACKGROUND AND PREPARATION FOR THE TESTS

To understand the tests it is important to know some background on previous tests, expectations, consequences, and the resultant preparation. The main drivers for the tests reported here are as follows.

3.1 Waste Disposal Containers

Waste Disposal Container Configuration

To stack cubic or rectangular waste disposal containers in a concrete vault and maintain a no-subsidence posture for hundreds of years, the containers need to be the same size and cubic or rectangular within very tight tolerances so they can be stacked tightly in an essentially void-free arrangement. They also need to be free of appendages. They should be full of concrete to the extent that the concrete makes contact with the top surface of the container, and that all six surfaces remain flat. This is believed achievable on a routine basis by maintaining the top surface in a rigid flat position while filling the container with SPC and allowing the heated sprues to continue filling the container while the molten SPC shrinks. (SPC linear shrinkage is 0.1%.) Should it prove impossible or impractical to maintain a flat top surface, there is an alternative; the container can be rotated 90 degrees so the uneven top surface is on the side, thus leaving the flat side-surface to support the next higher layers of containers in the vault. However, if and when the SPC-waste mass should fail and crumble, the voids left would permit some small subsidence, so the perfectly flat lid is a priority goal.

Waste Disposal Container Design

The cubic, thin-walled (12 gauge), carbon-steel container is a special design that has no forklift cleats and no lifting lugs. The only appendages are two sprues, which would be removed prior to disposal. The container is only useful for concreted waste. In an operational waste treatment facility,

sized-metal waste would be placed in the waste disposal container, large fragments of hearth ash would presumably be spread across the top of the metal waste, and then a lid would be welded on. Molten SPC laden with hearth ash fines will be poured into the container through an input sprue on one corner of the container until the SPC rises into the overflow sprue in the opposite corner. The container will then be allowed to cool and the contents solidify. During SPC filling, the container corner with the overflow sprue would be higher than the corner with the input sprue for the sole purpose of guaranteeing that the container is full to its top surface.

The container provides the required containment for concreted radioactive/hazardous waste. The original concept called for a 1- x 1- x 1-m waste disposal container.¹⁶ However, the fixed-in-place mixer would only permit a 32-in. height, so the test containers were built 3 x 3 x 2-2/3 ft, which offers 24 ft³ of volume, and was deemed adequate for the full-scale test and proof of principle demonstration. (See Figure 1 for material and dimensions and see Photo 1.) It is assumed that the eventual operational container would have two small heated-and-easily-cooled sprues in two opposite corners on top of the container.)

3.2 Mold-Form

Mold-Form Purpose

As indicated above, the waste disposal container is intended to be constructed of thin steel without any structural supports, and without any forklift cleats, lifting lugs, or other appendages. To ensure exact dimensions, exactly square corners, and flat side walls, the container will require that a mold-form surround and support it while it is being filled with waste and SPC, and until the SPC is cooled (solidified).

Mold-Form Design

The eventual mold-form for operational use would be designed to blend with the overall concreting system, and might use in-place, automated

- NOTES:
1. MATERIAL ASTM A36 UNLESS NOTED
 2. FILLER METAL E7018 PER AWS A 5.1 OR E70S-2,3 PER AWS A 5.18
 3. VISUAL INSPECT PER AWS D1.1 PARA 8.15.1
 4. PLACE MODEL OF SCRAP METAL INSIDE CONTAINER PRIOR TO WELDING LID ON
 5. USE THE MOLD FORM TO CONTROL THE OVERALL SIZE. THE CONTAINERS SHALL FIT INSIDE THE MOLD FORM WITH THE MAXIMUM ALLOWABLE GAP BETWEEN THE SIDES OF THE MOLD FORM AND THE CONTAINERS IS .080"
 6. PLACE SCRAP METAL MODEL (SKETCH No WCA-9-28-91) INTO CONTAINER PRIOR TO WELDING LID ON

Figure 1. The test disposal container was fabricated from this drawing.

SECTION A-A
(TYP JOINT)
SCALE 6"=1'-0"

SECTION B-B
(TYP JOINT)
SCALE 6"=1'-0"
ROTATED 45° CCW

E & G IDAHO INC
SKETCH No WCA-9-27-91
SPC
DISPOSAL CONTAINER

BY: W. C. ALDRICH
SCALE 1 1/2"=1'-0"

OCT 8, 1991
SHEET 1 OF 1

Photo 1. A waste disposal container that can be stacked in a concrete vault with virtually no voids between containers must be a standard size, square on every corner, flat sided, tight on tolerances, and, if subsidence is to be prevented, it must be appendage free. This test container is intended to meet most of those requirements sufficiently well to conduct the tests. The input sprue measures 8 x 11-1/2 in. Its sole purpose is to mate with the large rectangular mixer exit port. In an operational system, the mixer exit port and the input sprue would connect physically. The input sprue would probably be a 2-1/2 in. pipe placed very close to the container corner and be as much as 10 in. tall. The two sprues would probably be heated to keep the SPC molten so it could descend into the container to displace any shrinkage that might occur during the cooling process. It is assumed that the sprues would also be equipped with a cooling ring that could freeze the SPC quickly (See Figure 6) and allow quick detachment from the mixer.

As this test container is constructed, it would be difficult to remove the huge concrete-filled sprue and leave a flat surface. The much smaller pipe sprue can be removed. (All three-dimensional molds have at least two sprues, and there are ways to remove them and comply with contamination control requirements, but tests have not progressed to that point.)

mechanical systems to install the new empty container and retract the concreted monolith. For this test, a mold-form was designed and fabricated to mate with the in-place mixer in the Denver Equipment Company's laboratory. Its tare weight is 3550 lb. (See Figure 2 for materials and dimensions and see Photo 2) Half of the mold-form supports two side walls of the container and is welded to the base plate. The other half supports the other two walls of the container and swings on hinges attached to the first half. With the test container and its simulated, contaminated steel-and-ash waste in place in the mold-form, the hinged section is closed and locked. The container is then ready to receive the molten SPC-and-ash mixture.

3.3 Simulated Waste in the Disposal Containers

Waste Characteristics

In operational conditions, waste in the container prior to the pour will most likely be composed of size-reduced metals and incinerator hearth ash particle size greater than 3/8 in. but less than 1-1/4 in. If the metal were shredded prior to being placed in the container, there would be very few voids caused by the metal. Voids would only be expected under downward-facing concave surfaces. For example, a cup placed upside down in the waste would contain a void, but if the cup were shredded, there would be little chance of a void. Where shredding is not used in preparing the metal waste for disposal, long pipes and conduits of various sizes would be routinely included in the waste. SPC penetration into the pipes to fill the voids would be dependent on the size of the pipe and the fluidity of the SPC. Fluidity of SPC is determined by the aggregate it carries and by the temperature of the mass. The less internal voids in radioactively contaminated waste, the less chance of subsidence hundreds or thousands of years from now.

Design and Placement of Simulated Waste in the Disposal Container

To be as realistic as practicable, simulated radioactive waste was placed inside the containers prior to pouring the SPC and ash mixture. Following are

- NOTES: 1. MATERIAL ASTM A36 UNLESS NOTED
 2. FILLER METAL E7018 PER AWS A 5.1 OR
 E70S-2.3 PER AWS A 5.18
 3. VISUAL INSPECT PER AWS D1.1 PARA B.15.1
 4. TOLERANCES UNLESS SPECIFIED
 $X/X \pm 1/8$
 $.X \pm .1$
 $.XX \pm .03$
 $.XXX \pm .010$
 ANGLES $\pm 2^\circ$

Figure 2. This drawing was used to fabricate the mold-form. Photos 2 and 9 show the mold-form at the Denver Equipment Co's. test laboratory. Note in Section A-A that forklift tines can be inserted in the two channel irons. This

E G & G IDAHO INC
SKETCH No WCA-8-28-91
SPC
MOLD FORM
BASE WELDMENT

BY W C ALDRICH
SCALE 1 1/2"=1'-0"

OCT 3, 1991
SHEET 1 OF 1

permits lifting the mold-form and the full or empty test waste container.
Also note that the waste container rests on top of two longitudinal voids that
permit a forklift to recover or insert the test container.

Photo 2. Container No. 3 has already been filled with the SPC and ash mixture. With close scrutiny, the common edges of the container and the mold-form can be seen. The overflow sprue almost touches the sides of the container as will the eventual input sprue. The huge rectangular input sprue is only necessary for the current tests where it had to mate with existing equipment. In the operational world the two sprues will probably be 2-1/2 in. in diameter and will be 8 to 10 inches tall. They will probably be heated to allow them to continue feeding SPC into the container as the concrete settles. They may well be equipped with cooling devices to permit rapid freezing to allow detachment from the mixer.

the facts concerning placement of hearth ash and steel in the containers prior to the test pours.

Hearth Ash: Mixed-waste fly ash has been successfully "eliminated" at WERF by reintroducing it to the incinerator feed. (The Scientific Ecology Group, the world's leading processor of low-level waste, has applied to EPA for permission to do the same thing.) The fly ash contains approximately 50% carbon that is consumed in the second burning, and the non-carbon portion, mostly metal oxides and salt, evidently combines with the hearth ash since the quantity of fly ash does not increase in later burnings. Therefore, the term "eliminated" is not intended to imply that the molecules in the fly ash disappear; instead, it means that in that concept of operation, the only ash to be collected and treated is the hearth ash. Therefore, only hearth ash was used in the tests. Uncontaminated hearth ash was obtained from a school's coal-fired furnace and was subjected to two screenings that produced three size groupings of ash:

1. Ash that did not pass through a 1-1/4-in. screen was rejected. This simulates the ash that passes through a low-speed shredder with 1-1/4-in. wide knives that is used to break up large clinkers from the incinerator.
2. The previously described 1-1/4-in. and smaller ash that did not pass through a 3/8-in. screen was placed in the test container prior to pouring SPC. (See Photo 3.) This action simulated the non-fines hearth ash that will be recovered from a fines separator. The ash was weighed out in a 38-lb batch and a 40-lb batch for the two respective tests and was poured into both containers much the same as it would be in operational conditions--after the metal waste was in place. The majority of this ash is believed to have worked its way to the floor of the container through the pipes and channel irons, either initially or as molten SPC contacted it and carried it downward. One of the test goals was to determine the extent

Photo 3. Tests 1 and 3 included 38 and 40 lb of ash (respectively), which was dropped through the input sprue; most of the ash landed on the floor. Particle size ranged from 3/8- to 1-1/4-in. This photo is of Test 1, where the ash was not wetted by the molten SPC and thus did not become part of the SPC concrete. Photo 19 better depicts the results.

Photo 4. The hearth ash mixed with SPC mixture ranges from a powder to 3/8-in. particles. The ash was from a coal-fired furnace. The chemical composition was determined (see Appendix A). The bulk density was 45 lb/ft³, a fact that suggests that larger particles would tend to float in the molten SPC if given time.

that the molten cement would wet this ash and thus tie it up in the concrete matrix.

3. Ash that passed through the 3/8-in. screen (see Photo 4) was combined with the SPC as it entered the mixer. This action simulated the anticipated fines separation in an operational facility, and placed the "pass-through ash" in the SPC for blending and pouring.

First the fines (pass-through ash) needed to be totally wetted by the molten SPC to create the best possible leach-resistant concrete. Secondly, the only way to assure that the fines, particularly the dust portions, were wetted was to combine them with the incoming cement and allow them to be tumbled with the SPC fragments by the mixer flites (screws).

Hearth ash used in these tests was obtained from Rigby High School in Rigby, Idaho, and was analyzed for content at an EG&G Idaho laboratory. It bears a close resemblance to WERF hearth ash in chemical contents. Those findings are provided in Appendix A.

Incinerator ash is hygroscopic, so both the fines and the large-fraction portions were heated immediately prior to testing to drive off the water content (simulates ash kept hot after incineration). Water remaining in the ash was measured at 0.2% of the mass. Note: 0.0% is most desirable and should be the goal in the full-scale NRC test and in an operational situation.

Steel: To conduct worst case tests for filling voids, 1-, 2-, and 4-in. schedule-40 carbon-steel pipes, 30 in. long, were combined with 6-in. carbon-steel channel iron and welded in identical arrays within the test containers. The total weight of the simulated steel waste for each box was 800 lb and occupied a volume of 1.6 ft³. Tare weight of the test container and steel waste was 1150 lb. Two 2-in. pipes were placed vertically on centerline and the rest were laid horizontally. (See Figure 3 for materials and dimensions and see Photo 5.) They were arranged so that one pipe in each layer was on

- NOTES: 1. MATERIAL ASTM A36 UNLESS NOTED
2. TACK WELD ALL PIECES INTO PLACE AS SHOWN

Figure 3. This drawing was used to fabricate four identical arrangements of pipe and channel iron (simulated radioactive waste) that were welded into the four test boxes. The five 1-in. pipes shown at "c" in Section C-C were deemed

LIST OF MAT'L

ITEM	DESCRIPTION	WEIGHT	NUMBER	TOTAL WEIGHT	LAYER
A	4" SCH 40 X 2'-6" LG	27	2	54	1st
B	2" SCH 40 X 1'-9" LG	6	4	24	1st
C	1" SCH 40 X 1'-9" LG	3	5	15	1st
D	2" SCH 40 X 2'-0" LG	10	2	20	VERTICAL
E	4" SCH 40 X 2'-7 1/2" LG	28	10	280	2nd & 6th
F	C6 X 8.2 X 2'-6" LG	21	6	125	3rd
G	C6 X 8.2 X 2'-7 1/2" LG	22	6	132	4th & 8th
H	2" SCH 40 X 2'-6" LG	9	5	45	5th
J	1" SCH 40 X 2'-6" LG	4	5	21	7th

720 TOTAL

SECTION D-D
PLAN VIEW
OF 2nd LAYER

SECTION A-A

E G & G IDAHO INC
SKETCH No WCA-9-28-91
SPC
SIZED SCRAP MODEL

BY: W. C. ALDRICH
SCALE 1 1/2"=1'-0"

OCT 4, 1991
SHEET 1 OF 1

the most difficult to fill with molten SPC without leaving voids. Photo 5 is a view in the container after the simulated waste was welded in place and before the lid was welded on.

Photo 5. The 1-in. pipes are the seventh and top tier in the simulated waste stack. Note also the two vertical pipes, which are the only vertical pipes in the array. The array is identical in each test container. The exact design of the array can be seen in Figure 4. After this photo was taken, the 12-gauge steel lid with its two sprues was welded in place. The 38 and 40 lb batches of hearth ash were not placed in the containers until just before the tests began in Colorado Springs.

In an operational waste treatment facility envisioned for the future, all of the waste, including the large fraction hearth ash, would be placed in the container in random order prior to securing the lid with a robotic welder. It is also envisioned that the container itself would be fabricated in the waste treatment facility with precise jigs and a robotic welder. It is likely that the containers of the future would be constructed with steel half the thickness of 12 gauge steel.

the container's vertical center line. This array permitted the container to be sawn in half in all three planes making eight equal-sized blocks and in doing so split the pipes axially and cut others radially at the center line to expose the most likely areas for voids. (See Figure 4 and Photo 6) Of course in operational conditions the same metal waste used in these tests would simply be dumped in the container in random order.

3.4 Ratios of Incinerator Hearth Ash and SPC

The highest ratio of WERF mixed-waste-fly-ash to SPC that passed the EPA's TCLP test was 43wt%,³ so that ratio was selected for these tests, even though the test would use hearth ash rather than fly ash.

3.5 Mixer Characteristics

It is essential that the SPC mixer be a closed system that can contain contamination. A mixer with low-maintenance probability is also essential for an operational system and the hollow-flite mixer appears to be the best when all other requirements are considered. SPC starts changing from a solid material to a liquid at 230°F (110°C). At 320°F (160°C) SPC starts emitting hydrogen sulfide and becomes unpourable. The closed-system SPC mixer must be capable of maintaining the proper temperature of the molten SPC mass throughout the pour. SPC is a poor conductor (resistant to temperature change), so the mixer must be capable of generating heat around the exterior of the SPC-and-ash mixture and on the interior as well. One of the advantages of SPC is that it can be maintained in the mixer in the molten state for long periods of time and then continue the pour. Also, a properly configured mixer with a load of molten SPC inside could be shut down allowing the SPC to freeze, and then be reactivated to melt the contents and continue the aborted pour. The horizontal heater-screw mixer was chosen as the optimum SPC mixer for contaminated wastes. It is a mixer that can be configured to meet all the desired characteristics.

This type mixer is routinely manufactured in various sizes and configurations by several companies. The Denver Equipment Company allowed

Figure 4. Once the waste containers were filled with SPC, they were sawn into eight equal sized segments to generally expose the center of the mass, and to specifically expose the center of selected steel pipes. To make the investigation as precise as possible, each segment was identified with alphanumeric characters. For example, the identification "1A" was the segment from the first test, the room-temperature test, and it was the segment directly under the input sprue. There were 16 segments in all, and each has six sides, three of which are saw cuts, so it would be impractical to show each of the 96 cuts, or even all the segments. Photos of the more informative cuts into the mass are the only ones shown. (The authors will maintain a file of all photos not presented here.)

Photo 6. The waste container that weighed over 4000 lb was cut along the center line on all three planes which resulted in eight segments that each weighed approximately 500 lb. This exposed the center of many 1-, 2-, and 4-in. pipes to determine the quantity and nature of voids. The cuts also exposed incinerator hearth ash that ranged from $\frac{3}{8}$ to $1\frac{1}{4}$ in. and was dropped on the container floor prior to pouring the SPC. It too was exposed for examination by the saw cuts. There was little to be gained by removing the steel container from the concrete because all the voids were expected in the center of the pipes, in the center of the container. When looking at the photos of the sawn SPC concrete, saw marks should not be confused with concrete configuration--four progressively larger diameter saw blades were used in making the cuts, so different diameter marks are visible in some sections.

At the left side of the photo, note the hand holding a water injector that keeps water flowing onto the saw blade and down into the saw kerf. This effort produced an excellent finish to the SPC concrete. The cold-water cut creates a true cut as opposed to a melted cut. Without the water the blade would melt its way through the concrete mass making a "smear" cut and obscuring the concrete's true texture.

tests with SPC in their laboratory mixer for a reasonable fee. The mixer has hollow flites mounted on two hollow shafts that are both surrounded by a hollow jacket. (See Photo 7.) As with most mixers of this class, hot oil--up to 600°F (316°C)--is pumped through the flites, shafts (see Figure 5), and jacket (see Photo 8). This type mixer places a very large heated surface area within and around the SPC-and-ash mass, a feature that is essential for emergency shutdowns, power failures, and for planned shutdowns, when SPC and ash are still in the mixer. The intermeshed flites are 7 in. in diameter; the shafts rotate in opposite directions to promote mixing.

3.6 Testing for Temperature Influence on Pour Success

Control of Pour Temperature

Many construction pours of SPC into molds call for preheating the molds. Being a thermoplastic, SPC will freeze shortly after making contact with cold materials. A primary question to be answered in these tests was whether or not the cement mass would remain molten long enough to fill the voids both within the pipes and up under the channel irons.

Temperature Test Controls

Test 1 was to be conducted with the container and its contents at room temperature, approximately 65°F (18°C). It was anticipated that the SPC would not significantly penetrate the 1- and 2-in. pipe.

Test 3 was to be conducted with the container and its contents preheated to optimum SPC pour temperature, approximately 275°F (135°C), by placing the container and the mold-form in an oven over night. It was hoped that the SPC would penetrate the pipes and thus leave very few voids.

Photo 7. The Holo-Flite Processor (mixer) has a total length of 13 ft 6 in., including the drive system, and a tub length of 10 ft. The tub is 1 ft 5 in. wide and approximately 10 in. deep. The centerlines of its two 7-in. diameter screws (flites) are 6 in. apart. The flites have a 4-in. pitch, and the shafts rotate in opposite directions. The important measurements cited above are included in the Unit Size code, which is 1D710-4.

The gasketed lid was closed some 99% of the time during the tests, and would be bolted shut in a contaminated operation.

Figure 5. Hot oil is pumped into the end of the two rotating shafts where it is first directed through the hollow flutes to the far end of the shaft, and then routed back through the shaft. The heat loss from point of oil entry to point of exit is normally less than 10°F (6°C).

Photo 8. The blended SPC and ash is placed in the hopper at the left and is drawn into the mixer by the rotating flites. At the right, the SPC is starting to melt. Looking to the next tests, the following could be done. The melt temperature of SPC is 230°F (110°C). If the input ash was preheated to approximately 350°F (177°C), the SPC-ash mixture would become molten much more quickly than shown here, and it would allow the shaft speed, which is 1.7 rpm in the photo, to be increased significantly, thus allowing a greater throughput. See additional comments in Section 5.2, Improving the SPC Concrete.

4. THE TESTS

The first test was scheduled for December 10, 1991, but the ash had not been dried, so the day was spent drying it in the very mixer that was to be used for the SPC tests. Another delaying problem occurred because the test container was fabricated by using the mold form as a weld fixture. The mold-form was not precisely square as would be essential in an operational system. Consequently, the container would only fit into the mold form one way and allow the hinged mold-form "door" to close. The mold-form had been fabricated with channel-iron forklift guides. (See Photo 9.) The mixer could only be approached by a fork lift from one direction. The container, would not mate with the mixer so its SPC outlet port could be aligned with the container's input sprue. Therefore a welder was required to cut forklift-entry spaces crosswise through the original forklift channels. (See Photo 10.)

4.1 Test 1

SPC and Ash Ratios

For Test 1, the ash and SPC (See Photo 11) were weighed to the proper ratios, and placed in buckets, and the buckets were then marked with grease pencil at the top of the respective masses. The goal was an approximate ratio of 43wt% ash and 57wt% SPC. For the rest of the test the buckets were filled to those marks and the contents poured into the mixer. However, the method of measuring the material was not accurate. The total weight of ash used was 674 lb and the total weight of SPC used was 1257.5 lb. The actual weight ratio was 35:65.

On Wednesday, December 13, 1991, Test Container No. 1 was moved into the test area and 38 lb of incinerator hearth ash ranging between 3/8 and 1-1/4 in. was poured through the large input sprue. The volume of the ash was 0.7 ft³. The container was then moved under the mixer by forklift--a tight fit. (See Photo 10.) The overflow sprue corner of the container was raised 3/4 in. above the input-sprue corner. (See Photo 12.) The mixer's

Photo 9. As shown in this photo, the left half of the mold-form is welded to the steel base plate, while the right half is supported by the hinges in the foreground. With the container in place, both halves are secured by two Speed Ball Bolts at the far corner (out of sight). The mold-form's 6-3/4-in. thickness provides the rigidity that maintains the flatness of the four container-supporting sides as well as the exactness of the cubic shape.

The waste container and its mold-form are supposed to be square within tight tolerances so that any of the four sides of the waste container can be placed against any of the mold-form walls. However, this test mold form lacked being square by just enough that the containers would only fit in one direction. Because the mixer could only be approached from one direction, and because the large input sprue couldn't be placed under the mixer's output chute, a welding torch was used to cut forklift access openings crosswise through the two channel irons that were intended to receive the forklift tines. See photo 10 for final results.

Photo 10. A forklift is slowly moving the mold-form and its enclosed waste container under the mixer to begin the first test. For proper perspective, the rig is approximately one ft from its destination, and will be rotated to square up the mold-form with the mixer. Note that the forklift tines are 90 degrees from their intended entry point--the two channel irons originally intended to receive the forklift tines can be seen at the bottom of the nearest side. The container and its contents are at room temperature (approximately 65°F).

Photo 11. SPC used in these tests came in flat "flakes" (approximately 1/8-in. thick). The thin uniform cross-section permits rapid heat transfer and thus early melting. The SPC handled nicely: thinner flakes could create a dust problem and heavy chunks do not melt readily, so these seem to be optimized for best service and are much better than the cement used in the earlier test.

The ideal for SPC particles would be identical size, weight, and shape. If, for example, each particle of SPC were like an aspirin tablet, the melt duration at a given temperature would be the same for each pill. The fragments shown above were originally created in a flat sheet that was broken in a planned fall. Therefore, each fragment is different and some are quite small, as can be seen on the far side of the pile.

A casting process that would make smooth-sided pills should provide a cement with even less dust and a dependable, uniform melt rate. The proper concentration of dust suspended in the air can cause a small explosion (a "pop") if ignited. This happens occasionally in industrial applications with no resultant damage and no work stoppage. However, it should be noted that the cement was of much poorer quality than the SPC used in this test. Nevertheless, an even better form could be considered a must for our industry.

Photo 12. A carpenter's level was used to establish a tilt in the container so the corner with the overflow sprue (right) would be $\frac{3}{4}$ in. higher than the corner with the rectangular sprue (left). With both sprues only 2 in. high, the corner could not be lifted much higher. The container tilt is intended to ensure that the SPC concrete is pressed up against the lid--across the entire surface--before it can exit the elevated sprue. It was successful in Test 3, but logically could not have been in Test 1 because the SPC concrete must be flowing freely. Considering the voids that appeared in the upper region of the container in Test 3, it was surprising that the cement made total contact with the lid.

With 2-1/2-in. diameter sprues anticipated for an operational system that would stand probably 8 or 10 in. tall, the container could be raised several inches at the overflow sprue, thus putting a definite head into effect that would not only force the SPC concrete up against the entire lid, but would force the SPC into potential voids as long as it is in the liquid state. An artist's conception of this concept can be seen in Figure 6.

input oil temperature was elevated to 340°F (171°C), which resulted in an exit oil temperature of 330°F (166°C).

Note: Whereas the oil temperature in the mixer can be raised to 600°F (316°C), for safety reasons the oil temperature should not be raised above approximately 340°F (171°C) because it could raise the SPC temperature to 320°F (160°C) and cause a phase change in the SPC. The phase change causes the cement to become gummy and unpourable, and causes the creation of hydrogen sulfide. Target temperature for SPC is 275°F (135°C) plus or minus 10°F (6°C).

Shaft speed was set at 1.7 rpm and SPC and ash were poured into the mixer and blended by hand. After 35 min, the SPC was approximately 3 in. deep under the overflow sprue and was a liquid with islands of solidified SPC. The temperature was checked at the input sprue and was found to be 302°F (150°C), which meant it needed to be reduced. The oil temperature was reduced by 10 degrees, but the SPC temperature had not dropped after 5 minutes so the shaft speed was increased to 1.85 rpm to help reduce the SPC exit temperature. In approximately 15 min the temperature lowered to 275°F (135°C). Approximately 15 min later it was noticed that two stalagmites had formed on the uppermost pipes in the container and had extended up into the mixer's exit port. (See Photo 13.) The stalagmites required considerable force to break with a large steel bar--showed how quickly SPC gains strength, even with minor cooling. The SPC exit temperature was 245°F (118°C); there was very little flow. To raise the SPC's exit temperature, the shaft speed was reduced to the original setting of 1.7 rpm. (See Section 6.1, Increased Throughput Test, for further discussion on why the stalagmites developed and how they can be eliminated.)

Throughout the preceding portion of the test, the SPC exit temperature was being chased up and down. The optimum pour was finally stabilized with an input oil temperature of 330°F (166°C) and a shaft speed of 1.7 rpm. The lab director had never run such a substance as SPC through the mixer, and of course the authors had not, so it was a learning experience for all. (These mixers are normally used for heating/drying chemical solids, grain, and so forth.)

Photo 13. Two stalagmites can be seen (at the arrows) through the 2-in. gap between the container's rectangular sprue and the mixer's exit. A small amount of molten SPC can be seen running down the left side of the left stalagmite. The stalagmites, which are eight to ten in. long and 1 1/2 to 2 in. in diameter, are anchored to a 4-in. pipe down in the test container. Several blows from a heavy steel bar were required to break these stalagmites loose. The stalagmites were still quite hot, but had gained considerable strength.

At 2h, 20 min into the pour, the SPC was 14-1/2 in. deep under the overflow sprue. With a flashlight, the SPC could be viewed through the overflow sprue throughout the test. The SPC could be seen rising up to a pipe opening and then flowing very slowly into the pipe opening, and in the case of small pipes, coming to a halt and sealing the pipe ends so no more SPC could enter.

The test crew was satisfied that this test was going to cause too many voids, and that Test 2 would be cancelled altogether because it would be even worse with the planned 30 min break between four 8-in. pours. Therefore, at 3 h and 20 min into the test, with the SPC mix some 10 in. below the overflow exit and some 4 in. below the input sprue (See Photo 14.) the test was halted.

4.2 Test 3

SPC and Ash Ratios

On Thursday, December 14, 1991, after reviewing Test 1, the decision was made to weigh each bucket of ash and SPC to the specified amount for Test 3. (See Photo 15.) This resulted in a ratio of 43wt% incinerator hearth ash and 57wt% SPC. In keeping with the first test, after the ash and SPC were poured into buckets to the presumed correct quantity, they were poured into the mixer, one immediately after the other, and were then hand mixed before being drawn into the mixer. (See Photo 16.)

Heated Waste Disposal Container

Test Container No. 3 was prepared for the test. Some 40 lb of incinerator hearth ash ranging between 3/8 and 1-1/4 in. was poured through the large input sprue. The container, in its mold-form, was transported to an oven where it was heated overnight to 275°F (135°C). On Friday, December 15, 1991, Test Container No. 3 and its mold form were removed from the oven and covered with 6-1/2-in. thick R19 insulation. It was then moved to the laboratory and placed under the mixer. (See Photo 17.) As in the first test, the container was raised 3/4 in. at the overflow-sprue corner. Cuts were made

Photo 14. The input sprue was at the extreme left segment in the photo. In the center top portion the SPC is approximately one ft higher than at the right side. Erratic flow was observed through the input sprue during the last several minutes of the pour. Note the severe slope of the concrete on Segment 1D--the SPC was being cooled by room-temperature air flowing from the overflow sprue to the input sprue. These two segments, more than any other segments, proved to the researchers that cold air must not be allowed to flow through the container. Of course, the container and its two sprues would be part of the totally contained system in any waste treatment facility, as indicated in Figure 7.

Photo 15. Here ash is being shoveled into a bucket until the proper weight is established. The same procedure was used for measuring SPC. The bucket of ash is then poured into the mixer's feed hopper and, immediately afterward, a bucket of SPC flakes is poured in. Once the two buckets have been emptied, hand blending is performed. See Photo 16

Photo 16. SPC and ash were poured into the feed hopper separately and then hand blended with a scoop. In an operational contaminated system, these ingredients would be fed with closed screw augers, or a similar conveyance, that would automatically weigh in the correct percentages of both ingredients.

in the insulation to insert the thermocouple for periodic temperature readings. (See Photo 17.)

Test 3 Begins

An hour after the container was taken from the oven, the pour began at 7:45 AM. Since this test involved a container and mold-form that had been preheated to 275°F (135°C), a hand-held thermocouple was used to take temperature measurements at four locations on the assembly. Though temperatures were taken every 15 minutes, there were no significant changes worth mentioning in this report other than the first temperatures and the temperatures 4 h later at the conclusion of the test. The following temperatures were recorded at the specified locations at the beginning and at the end of the test.

- Location "A" on the top surface of the container, midway between the sprues: 260°F (127°C) beginning and 198°F (92°C) end
- Location "B" on the side of the mold-form, halfway between the top and bottom: 237°F (114°C) beginning and 202°F (94°C) end

Note that the beginning temperatures had all dropped considerably from the oven temperature of 275°F (135°C) during the hour required to move the test container from the oven to the mixer.) Also note that the two key temperatures were 77 and 73°F (25 and 23°C) below optimum melt temperature at the end of the test.

Improved Throughput

Test 3 began with the mixer's input oil temperature established at 334°F (168°C) and the shaft speed at 1.65 rpm. These were compatible with the 330°F (166°C) and 1.7 rpm established as optimum in the first test. However, a vertical flow restricter at the downstream end of the feed hopper had been lowered somewhat in the first test, and it was fully raised for this test, which allowed more ash and unmelted SPC to engage the heated surfaces

Photo 17. Insulation surrounds the mold-form and container on five sides; the bottom is not insulated. The mixer lid is rarely opened, but was opened here to provide some light at the input sprue for video pictures. Thermocouples used to take temperature readings at various spots on the container are on the container's insulation cover.

downstream. Since essentially nothing else changed during the entire pour, and since the throughput was improved by 25% over Test 1, it is assumed that raising the flow restricter was the cause of improvement. With the increased input, the exit SPC was too thick and its temperature was 255°F (124°C) when it should have been about 275°F (135°C), so the input oil temperature was increased to 339°F (171°C) and the shaft speed was increased to 1.7 rpm. The oil exit temperature was constant at 332°F (167°C). These two adjustments provided good SPC flow for the remainder of the test.

4.3 Development of the Concrete Mass During Both Tests

The overflow sprue is approximately 38 horizontal inches from the center of the inlet sprue. It was intriguing to observe the extremely slow rise of the concrete mass through the overflow sprue during both tests. It was like watching the development of the earth over millions of years. Most often the surface was crusted over and it was concluded that sometimes the surface was being slowly raised up by the molten core below. Valleys would form in the crust, only to be flooded by little molten lava rivers fed by the little volcanos that developed periodically, but unpredictably. The mass was often more fluid in Test 3 than Test 1.

In Test 1, as the SPC level raised to the next horizontal pipe end, the concrete could be seen solidifying as it gradually closed up the end of the cold 1-in. pipe. To define "gradually," it took 8 min, 37 sec to cover the opening of the 1-in. pipe; in Test 3, it required 7 min, 30 sec. In contrast, the preheated pipe of Test 3 allowed the molten concrete to stay molten and generally progress into the pipes. However, the top 1-in. pipe did not fill; it was blocked at the ends and is a topic of discussion in Section 5, Conclusions.

4.4 Larger Fragments of Hearth Ash May Float Upward in Molten SPC

A review of Photo 18 will show some interesting concrete formations that may be the result of floating ash fragments. Note in the photo that the pipes filled with SPC-and-ash concrete have a smooth texture in the bottom one third

Photo 18. The tests were set up to determine the quantity and location of voids due to the influence of heated and unheated pipes, ash, and container. In Test 3, when the container and its contents were preheated, most of the container had no voids; however, in Segment A3, shown here, which was directly below the input sprue, the SPC obviously did not stay molten long enough to fill all void space. Yet, at this location, the SPC could logically be expected to be at its hottest and most fluid state because it just dropped out of the mixer. The bottom of the preheated container was voidless, but as the pour developed, it is obvious that the preheat waned over a 5-hour period and more voids were left in the upper portions.

Note that the lower horizontal 2-in. pipe on the right was totally filled, while the 4-in. pipes above it were not totally filled, and note that the top 1-in. pipe did not fill at all. These three pipes demonstrate conclusively that heat in the SPC mass was being lost towards the end of the pour, at the top of the container. Also note that the concrete is pockmarked with tiny voids in the concrete itself, which did not appear in Segment 3E below it, or even in the bottom third of the filled pipes in this photo. These voids are assumed to have been caused by natural container heat loss and to one or both of two cooling factors that are discussed in Section 6.1.

to one half of the pipe and that the upper portions are rough, or pock marked. If this is indeed a separation of ash and SPC, it likely only occurs when the mixture stays molten long enough to allow the lower-density particles to float upward through the molten mass.

4.5 Checking Test Results

Both test containers were shipped back to Idaho Falls, where each container was sawn into 8 equal size blocks to expose the centers of pipes and the concrete mass in general. Photos numbered 18 through 23 and their captions describe the test results. The block coding is as follows: An arrow on the concrete block is a gravitational indicator, it points up towards what was the top during the pour. The key to alphanumerical symbols on the blocks can be seen in Figure 4.

Photo 19. In Test 1 with room-temperature waste, the molten SPC apparently froze in Segment 1E shortly after making contact with the "cold" ash pile and thus did not penetrate its mass very far to combine with the ash. However, some of the molten SPC made significant penetration a short distance away, as shown in Photo 20. In Test 3 with preheated ash, the results were markedly improved. (See Photos 21 and 22).

Photo 20. This segment of concrete is the bottom segment directly under the input sprue, Segment 1E. (The lower left corner is the center of the test container at the floor.) It is the room-temperature test. On the lower left side of the segment (also shown in Photo 19), it appears that none of the ash was penetrated by the molten SPC. Yet on the front side it is apparent that the molten SPC made a deep yet incomplete penetration of the ash. Note also that the 1-in. pipes at the bottom of the container were not filled. The 4-in. pipes that were obviously in a higher and hotter zone were totally filled.

Photo 21. In Test 3, the preheated test, the hot ash and steel kept the SPC molten long enough to allow full penetration of the ash and the pipes in the lower level. The concrete in Segments 3E and 3H looks very good and has no voids at all, not even in the 1-in. pipes on the floor of the container. The bottom of the original casting is on the upper left side as shown here.

Photo 22. In Test 3, the waste container and its contents were preheated to 275°F (135°F) before the pour. This higher temperature allowed the SPC to stay molten long enough in Segments 3H and 3E to penetrate the ash pile and make the ash part of the SPC concrete. After this photo was taken, the steel container was removed and at the bottom (foreground of the photo) the concrete was generally solid, but was very rough, indicating that the molten SPC "almost" achieved total penetration of the ash pile.

Photo 23. This preheated Segment 3G, was in the lower layer and was furthest from the input sprue. It looked very good. There were no visible voids or even pock marks. At the time this was poured, the container-and-ash temperature was still close to SPC melt temperature.

5. CONCLUSIONS

Test 3 was a positive indicator that SPC and incinerator ash can be poured effectively over realistic waste (steel) for a full-scale test to NRC's requirements. The difference between Test 1 and Test 3 showed that continued heating is required in the disposal container for an optimum pour.

General conclusions from Test 3 were that voids were nonexistent and the concrete was very good where the heat of the SPC concrete mass was high enough to allow flowing and settling before freezing. The tests suggest that the container must be heated to the optimum-pour temperature of SPC and be maintained there until the pour is complete. More discussion on this topic is included in Section 6, Recommended Future Full-Scale Tests.

The mixer worked very well. For a contaminated environment with more complex subsystems, computerized controls will be essential to maintain the correct heat at various locations in the overall system. Simple modifications in the fabrication of the mixer would make it compatible with a contaminated waste stream.

The mold-form worked very well in its intended function of supporting the container during filling and curing. The mold-form held the sides of the container flat, as intended. It opened very smoothly, especially considering its weight. Its lack of exact squareness was its only drawback, but it is quite adequate for a full-scale test. If the concept is used in an operational waste treatment facility, the mold-form can be constructed in a multitude of ways that will ensure exact squareness and thus provide a snug fit for the waste disposal containers.

Tilting the container so the corner at the input sprue was 3/4 in. higher worked as intended. The SPC concrete made contact with the entire lid, which ensures that the container would support many similar concreted containers stacked on top of it. However, it is suspected that some shrinkage did occur. The next phase of testing will most likely show that heating the container on

all six sides will be required. That can be done with a totally contained recycling-hot-air system that would direct the hot air through the mold-form's hollow walls, and of course hot oil and electricity offer heating options.

During the test pouring and at the conclusion of the tests, the Denver Equipment Company and EG&G Idaho test participants discussed the following problems and probable solutions.

5.1 Improved Blending and Melting

While it was assumed that the ash and SPC were thoroughly blended during the tests, the addition of a mixing lug to each of the flites would ensure a thorough blending of the ash and SPC. (See Photos 24, 25, 26) At the same time the mixing lugs would move some of the blend to the space between the blades where it would absorb more heat and speed the melting process.

5.2 Improving the SPC Concrete

The mixing speed was adequate to accommodate anticipated waste generation rates, but higher speeds are desirable if for no other reason than to get the job done and move on to the next. Maintaining the input ash at approximately 350°F (177°C) would not only speed the melting process, but would accomplish another important task, that of eliminating the last drop of moisture in the ash, thus ensuring the best possible mechanical strengths in the concrete. To further speed the process, temperatures should cause a quick melt. Where Tests 1 and 3 were conducted with a shaft speed of 1.7 rpm, the shafts can rotate at 8 rpm, which should increase the flow rate by a factor of 4.7. At that rate, the same 24 ft³ containers could be filled in approximately 51 minutes, at a rate of 2 min and 7 sec per ft³.

Only tests will tell, but with the improved conditions just cited, it is likely that the speed of pour would be greater than calculated, because (a) the molten cement would have a head at the input area that would tend to push the liquid ahead of the rotating flites, and (b) the addition of mixing lugs on the flites is also expected to increase the throughput. Increased

Photo 24. Hot oil runs through the large shafts and the hollow screws (flutes) to provide a very large heated surface area to melt the SPC and ash mixture while blending the mixture and transporting it to the waste container. Surrounding the trough is a jacket that also transports hot oil to melt the SPC. Nominal input oil temperature during the tests was approximately 338°F (170°C), and the exit temperature only a few degrees lower.

Photo 25. Some blending of SPC and ash occurred in the mixer feed hopper, as shown in Photo 16. Additional blending of SPC-and-ash solids occurs in the first half of transport as shown here; yet more blending occurs in the molten state in the second half of the mixer. However, total blending could be guaranteed if mixing lugs were affixed to the flites on both shafts. (See Photo 26.) If used in conjunction with pre-heated ash, that would add even more throughput capability. (See comments in Section 5.2, Improving the SPC Concrete, and see Photo 8.)

Photo 26. Mixing lugs similar to those shown on the flites (perhaps with more surface area) would agitate the SPC and ash and ensure total blending. At the same time, the mixing lugs will move more of the mixture to the space between the two shafts where more heat can be transferred to the SPC sooner. The Denver Equipment Company has welded mixing lugs onto the flites for other tests and they ground them off later. They recommended doing that for the next series of lab tests. For comparison, review Photo 24 and note the absence of mixing lugs in the mixer used in the tests.

throughput is in turn expected to reduce the voids by maintaining the heat longer. If greater flow rates are required, much larger off-the-shelf mixers are available with flite diameters up to 24 in.

5.3 Starting and Stopping Pour

Mixing radioactive waste in SPC must be done in a closed system that requires as little maintenance as practicable. One major concern is starting and stopping the SPC flow at the beginning and end of a pour into a container without causing any spills (leaks). There are many valves available, but all known valves are subject to routine failure. If metals are size reduced by a shredder, resulting small fragments ranging from dust to 3/8 in. will be razor sharp and will jam the valve. If metals are sized by torch, the splatter particles placed in the mixer will attack the valve. (Both of these fragmented, small-particle wastes need to be blended thoroughly with the molten SPC to ensure total wetting.) When dealing with SPC, a thermoplastic, the entire valve would have to be maintained close to the optimum pour temperature 275°F (135°C), or it will be concreted shut (or open).

For these reasons the old reliable weir seems very attractive. A mechanically rising and lowering weir at the point of SPC discharge would also jam. If the mixer itself were lifted and lowered at the drive end (opposite the weir), the weir could be welded in place. (See Figures 6 and 7 for artists' sketches of that concept.) The test personnel and SPC experts¹⁴ agree that the weir will work. If anything in the weir concept caused maintenance, it would not be in the contaminated waste zone of the equipment, it would be on the accessible uncontaminated exterior.

5.4 Computer Controls for SPC Exit Temperature

It was obvious that the operator could make minor control adjustments, like input oil temperature and shaft speed, and end up chasing the cause of peaks and valleys in the output SPC temperature. In the eventual waste treatment facility's operational equipment, there will likely be several more variables. This fact will require computer modeling to calculate in advance

Mixing and Pouring Sulfur Concrete With Contaminated Fines (Cross Section)

A91 0478

Figure 6. This artist's drawing of the pouring concept shows the sprues in approximately the proposed dimensions. Note that the test waste container is tipped to ensure that the container is full to the lid. The sunken area under the lid only illustrates what the sprues are for; they will contain enough molten SPC mix and have enough head that the molten concrete will be forced up against the lid to ensure that such a void does not form and to ensure that the lid is flat. The artist's weir is good enough to illustrate the concept. Freeze plugs will quickly seal the container when activated.

Sulfur Cement Mixing and Pouring

A91 0477

Figure 7. This artist's drawing illustrates the concept of flow control. The bottom of the weir (pipe) would maintain constant elevation (would be the pivot point). With a fully heated mixer, the power could be shut off in any of the three positions, until a restart was made. In the lower view, the freeze plug on the container as shown on Figure 6 would be activated.

the activities of automated controls required to maintain the mixer's oil temperature, shaft speed, input-SPC temperature, input-ash temperature, the container-and-contents temperature, and the weir height in order to optimize the SPC pour temperature and desired flow rate.

6. RECOMMENDED FUTURE FULL-SCALE TESTS

Based on the findings discussed in this report and the need to be fully prepared to pass the NRC's full-scale test the first time, the following tests are recommended.

6.1 Increased Throughput Test

Reasons for Increased Throughput Test

Presumably the eventual operators of the waste-treatment facility will be trained so they can perform different tasks. Speeding the waste stabilization process will free the operators for other tasks, or will allow more waste to be stabilized.

The Test

Pre-heat the ash to 350°F (177°C). Pour the SPC (60wt%) and preheated ash (40wt%) into the mixer and adjust the rotational speed of the hollow-flite shafts to determine optimum throughput rate with the output SPC temperature between 275 and 285°F (135 and 140°C). The test would be conducted prior to Tests 2 and 4.

Expected Results of Increased Throughput Test

This test would confirm the opinion of the test staff that the SPC throughput rate can be increased significantly. The optimum throughput rate would then be used for the two following tests.

6.2 Test 4

Note: The container numbers and the test numbers used in these recommended tests are in keeping with the test numbers in this report, where Tests 1 and 3 were conducted and Test 2 was canceled. In the

proposed tests, the first container test would be with Test Container No. 4 and would be called Test 4 to maintain clarity.

Reasons for Test 4

The driving force for conducting Tests 1 and 3 was to determine the impact of pouring SPC in a cold container with cold waste versus pouring in a preheated container with preheated waste. Both the creation of stalagmites that extended up through the input sprue, through the 2-in. air space, and up into the mixer's exit port; and the creation of voids in the upper portion of the container, indicate that sustained melt-temperature heat is required in the container.

1. Hot air rises and will create a draft through the hot container and its 800 lb of steel whether or not a mixer is involved. Specifically, the huge input sprue will overcome the small overflow sprue and hot air will flow freely out of it while drawing cold air down through the small sprue.
2. The off-gas system (See Photo 27.) operates at a negative-differential pressure that assists the natural hot air flow and draws even more cold air through the container and across the flowing SPC via the 2-in. gap between the mixer and the container's input sprue. That cold air accounts for the formation of stalagmites (See Photo 13.) and also for prematurely freezing the molten SPC, which creates voids in the upper regions of the container. (See Photo 28.)
3. Closing off the cold air routes would simulate the same environment that will be required in the closed system required in a radioactive waste treatment facility where the off-gas system operates with a negative-differential pressure in the contaminated zones to prevent contamination spread.

Photo 27. The mixer can be operated as a totally closed system that will contain the contaminated air. Shown here is the off gas piping complete with temperature gauges and dampers. This system causes a negative differential pressure inside the mixer, a feature that is essential to prevent contamination spread in a waste treatment facility.

The negative differential pressure is believed to cause a major portion of the heat loss that was evident in both Test 1 and Test 3. Heat rises, and given a small vent (overflow sprue) and a large vent (input sprue) and no other influence on the two, the large vent would dominate the upward flow of hot air and draw cold air down through the small vent. Adding to this heat-loss effect is the negative differential pressure that draws large quantities of air up into the mixer at the SPC exit port, which is only 2 in. above the large vent and is only slightly smaller in dimensions. (See more discussion on this subject in Section 6.1, "Expected Results of Test 2.")

The exterior heating jacket is seen clearly here. The word "Denver" is on the heating jacket.

Photo 28. This is the horizontal centerline cut through the room-temperature pour, Test 1. Its texture and appearance is quite similar to the heated container test, Test 3, in the same area of the container. While the bottom of the container contained loose ash and unfilled pipes, the molten SPC obviously provided enough heat to gradually warm the steel and assist in keeping the SPC molten long enough to fill the spaces between the channel iron, and to settle out air pockets before freezing.

4. With a much larger flow of SPC there will be more heat retention in the concrete mass that may very well allow the SPC to penetrate the large-fraction ash at the bottom of the container, and to flow through and fill the 1-in. pipes on the bottom of the container.

In Tests 1 and 3, the overflow sprue was elevated $3/4$ in. above the input sprue to promote complete filling of the container. An increased difference in height will create a greater head of molten SPC so some upward force is exerted on the lid. Due to test space limitations, the input sprue can only be 2 in. tall, but the small overflow sprue can be lengthened easily. By applying reverse technology, the container corner at the input sprue can be raised approximately 2 in. and the slope of the laboratory floor will allow some lowering of the small-sprue corner. The net result is expected to be an SPC head of $3-5/8$ in.

Test 4

Test Container No. 4 is to have heaters installed on the bottom and top surfaces and around the sprues. The two surfaces would be heated to 275°F (135°C) based on thermocouples secured inside the container at the centers of the bottom and top. Upon achieving those two temperatures, the pour would begin with optimum throughput of the SPC as established above. For both this test and Test 5, the flites would be altered by welding a steel mixing lug with a cross section of approximately one square inch to each flite on both shafts to promote blending and melting of the SPC and ash. (See Photo 26.)

For both this test and Test 5, the open space between the mixer's exit chute and input sprue would be sealed with insulation to eliminate cold air entry. To further eliminate cold air passage through the container and past the flowing SPC, the overflow sprue would be sealed to the extent that it too could be opened periodically to review the continuing development of the concrete mass below.

For both Test 4 and 5, lengthen the small overflow sprue to $4-1/4$ in. and lift the test container corner with the input sprue until it makes contact

with the mixer, and lower the overflow sprue. It is essential that the overflow sprue be no taller than 4-1/4 in. so it can indeed act as an overflow that will accept excess SPC from the mixer at the end of the pour. (No way to stop creating molten SPC and ash at the precise moment that the input sprue starts overflowing up into the mixer, so the excess must be allowed to exit at the overflow sprue where it will cause no damage.) To maintain the built-up heat from the molten SPC at the lid, the lid is to be insulated on Test 4.

Expected Results of Test 4

The assumption is that with preheated floor and lid and rapid filling (a greater mass of molten SPC injected quickly), the SPC mixture will remain molten long enough to fill the pipes and perhaps penetrate the ash fragments on the floor. Elimination of cold-air flow through the container may or may not solve the voids problem in the lower region of the container, but with the help of the rapidly rising hot concrete, the heated lid, and the elimination of cold air inside the container, it is expected that the voids in the upper region of the container will be eliminated.

Note: It is the consensus of the authors that in order to have quality assurance for every mix in an operational waste treatment facility, the waste disposal container and its contents will need to be heated above 212°F (100°C) to ensure that all water has been driven off prior to the pour. Test 4 when compared with Test 5 will provide an envelope of information that will help determine the optimum temperature of the preheat.

6.3 Test 5

Reasons for Test 5

An essentially voidless, self-supporting waste stack in a concrete vault requires the snug fit that is ensured by the mold-form and the prototypical waste disposal containers. Voids inside the container are of no consequence unless the stabilized waste starts crumbling hundreds of thousands of years

from now. When that occurs, a minute amount of subsidence might occur. Then too, any voids that can be eliminated will reduce the overall quality of waste for disposal.

Test 5

This container test would include the specified conditions cited for Test 4, with the exception that Test Container No. 5 and its simulated waste contents would be heated to and held at a sustained temperature of approximately 275°F (135°C), optimum pour temperature, by an applied heat source on all six sides. SPC and ash would be fed into the container at the optimum rate established above. With these conditions, the SPC-and-ash mixture can be maintained at optimum melt temperature throughout the pour and after. The top of the container and the sprues would be heated by a separate heat source to allow the top heat to remain activated while side-wall and floor heat are deactivated and the lower contents start cooling. This would allow the sprues to continue feeding molten SPC to the mass in the container as shrinkage continues.

Expected Results of Test 5

This test is expected to produce the best in solidification and stabilization of simulated contaminated metal-and-ash waste conducted in this series of tests. Heating the container and its contents to optimum pour temperature and holding the heat during the pour and holding the top and sprue heat after the pour is expected to cause the following improvements.

1. Holding the heat is believed to cause a more thorough chemical bonding between the SPC and the metal oxides that are always present in ash.
2. Physical bonding between SPC and the waste, particularly metals, may be better when both are at approximately the same temperature.

3. With the SPC, the waste, and the container all at optimum pour temperature, the SPC will remain fluid until the container heat is removed and will thus allow the molten SPC to fill all available voids like the full length of a horizontal 1-in. pipe at any elevation in the container.
4. With full heat, the concreted mass will cool slowly, which allows any shrinkage to occur slowly while the heated sprues keep feeding molten waste into the container. This will allow the SPC to make and maintain contact with the top surface of the container.

6.4 Test 6

Reasons for Test 6

In Tests 1 and 3, it seems that the larger ash particles stacked up at some pipe entrances, particularly small pipe, and that SPC filtered through the ash in an attempt to fill the pipe. With 3/8-in. and somewhat smaller particles suspended in the SPC, it is reasonable to assume that the flow from directly below the input sprue to the far corners of the container might well represent a separation of SPC from the ash. Specifically, the ash fragments would tend to catch and hang up on the steel causing bridges and dams, which in turn cause the liquid SPC to flow through the obstacles to fill voids. The SPC presumably carries with it the true fines from the ash. In other pipes, it appeared that the SPC and fines settled to bottom while the larger ash fragments floated to the top.

Separation of ash from SPC will be examined in Tests 1, 3, 4, and 5, but the facts may not be readily apparent. Test 6 is a very inexpensive test that should provide answers on SPC and ash separation that are simply not conclusive in the forgoing tests.

Test 6

This test can be conducted at the INEL or at Denver Equipment Company while conducting the tests cited above. It would require four separate test samples. In each test a mixture of 40wt% hearth ash and 60wt% SPC would be melted in identical test containers measuring approximately 6- x 6- x 12-in. high. Once the mixtures are poured at 275°F (135°C), they would be maintained at that temperature for 1 h. Upon cooling, they would be cut in half vertically with a water cooled blade as used to dissect Test Containers 1, 3, 4, and 5.

The difference in the four tests would be the maximum particle size of hearth ash. The first would duplicate Tests 1 and 3 with ash in the range from dust to 3/8-in. fragments. The second would have particle size ranging from dust to 1/4-in. fragments. The third would have particle size ranging from dust to 1/8-in. fragments. The fourth would have dust only.

Expected Results of Test 6

As reported in Section 4.4, larger ash fragments may be floating upward when the SPC stays molten long enough for this to occur. As part of the overall effort to test the best waste stabilization system, these tests are expected to provide valuable information on optimum particle size for the ash and information on the most desirable heat cycle. The best concrete will be a firm voidless homogeneous mass. If these tests show that smaller particle size is desirable, that change can be made in the eventual full-scale system.

6.5 Test 7

Reasons for Test 7

The concept of being able to keep molten SPC in the mixer for days on end and then continue the pour at some given moment is a very attractive attribute for SPC. Another equipment saving advantage could be established by proving that the mixer's heat source could be shut off and then be reactivated after

the SPC had been solidified, and bring the SPC back to a molten state to continue the pour without having to open up the totally contained system. This is a realistic test that would allow recovery from an inadvertent shutdown without equipment damage.

The operational mixer that could do that would require modification to continue the heat source around the entire circumference of the mixer's tub. The shafts already have hot oil traveling through the mixer's end plates, so the essential heated area already exists.

Test 7

This test would be conducted at the conclusion of Test 5. The mixer's exit port would be blocked off to accumulate a specified amount of the molten SPC-and-ash mixture (probably half full), and then the mixer's heat would be shut off overnight. In the morning the heat would be reapplied without rotating the flite shafts, and the time required to melt the solidified concrete to a condition that will permit shaft rotation would be determined.

It may be difficult to persuade Denver Equipment Company to conduct this test because approximately the last 16 in. of the mixer tub is not heated, nor are the ends of the mixer. To conduct this test they would definitely have to rig up some type of heating at those areas, otherwise they might have an unenviable chore of getting the mixer back to an operating condition.

Expected Results of Test 7

SPC is a poor conductor and is therefore resistant to temperature change, but there is no doubt that the SPC concrete will remelt if enough heat is provided to penetrate it sufficiently to cause melting. How long it will take is the question. It must be remembered that the heating surface cannot be raised so high that hydrogen sulfide is created; therefore, the melt will be gradual. Partly for these reasons, the hollow flite mixer was chosen: it has a large heated surface area in and around the cement mass. Proof of principle in this test would be a valuable selling point for both the mixer and SPC.

8. REFERENCES

1. U.S. Environmental Protection Agency, 40 CFR 261, Appendix II, EP Toxicity Test Procedures, 45 FR 33119, May 19, 1980, as amended by 48 FR 14293, April 1, 1983 and 50 FR 663, January 4, 1985, Washington, DC.
2. U.S. Nuclear Regulatory Commission, "Technical Position On Waste Form," (Revision 1), Low-Level Waste Management Branch, Division of Low-Level Waste Management and Decommissioning, January 1991.
3. Kalb, P.D., J.H. Heiser III, P. Colombo, "Encapsulation of Mixed Radioactive and Hazardous Waste Contaminated Incinerator Ash in Modified Sulfur Cement," BNL-43691.
4. Kalb, P.D., J.H. Heiser III, P. Colombo, "Comparison of Modified Sulfur Cement and Hydraulic Cement for Encapsulation of Radioactive and Mixed Wastes," Summary and Proceedings, Twelfth Annual U.S. DOE Low-Level Waste Management Conference, Chicago, Illinois, August 28 & 29, 1990, CONF-9008119-Proc.
5. Kalb, P.D., J.H. Heiser III, R. Pietzak, P. Colombo, "Durability of Incinerator Ash Waste Encapsulated in Modified Sulfur Cement," BNL-45292
6. Kalb, P.D., P. Colombo, et al., Modified Sulfur Cements Solidification of Low-Level Wastes, BNL 51923, October 1985.
7. Darnell, G.R. "Sulphur Polymer Cement, A New Stabilization Agent for Mixed and Low-Level Radioactive Waste," First Annual International Mixed Waste Symposium, Baltimore MD., August 1991.
8. Darnell, G. Ross, Milo M. Larsen, J. David Dalton, "Application of Existing Low-Level Waste Technology Offers 17-to-1 Volume Reduction and Enhanced Disposal at Low Cost," EGG-LLW-8054, October 1988.
9. Shuman, R., N. Chau, and E.A. Jennrich, Rogers and Associates Engineering Corporation, Salt Lake City, Utah, "Long-Term Structural and Radiological Performance Assessment for an Enhanced Abovegrade Earth-Mounded Concrete Vault," DOE/LLW-78T, December 1989.
10. Darnell, G. R., R. Shuman, N. Chau, E. A. Jennrich, "Abovegrade Earth-Mounded Concrete Vault--Structural and Radiological Performance," Emerging Technologies for Hazardous Waste Treatment, American Chemical Society I&EC Division Special Symposium, Atlantic City, NJ, June 1990.
11. Aldrich, W. C, EG&G Idaho, Inc., personal communication to Mr. J. A. Logan, EG&G Idaho, Inc., "Trip Report on the Trip to F. E. Ward Constructors and Brookhaven National Laboratory," WCA-6-10-90, June 10, 1990.

12. Aldrich, W. C, EG&G Idaho, Inc., personal communication to Mr. J. A. Logan, EG&G Idaho, Inc., "Trip Report on Visits to J. A. Reese Co.," WCA-08-21-90, August 21, 1990.
13. Aldrich, W. C., EG&G Idaho, Inc., personal communication to Mr. J. A. Logan, EG&G Idaho, Inc., "Trip Report on visits to F. E. Ward Constructors," WCA-07-90, September 25, 1990.
14. Darnell, G. R., EG&G Idaho, Inc., personal communication to Distribution, "Mixer for Sulfur Polymer Cement," GRD-21-90, September 14, 1990.
15. Darnell, G. R., EG&G Idaho, Inc., personal communication to Distribution, "Mixer for Sulfur Polymer Cement," GRD-23-90, October 29, 1990.
16. Aldrich, W.C., EG&G Idaho, Inc., personal communication to Mr. J.A. Logan, "Trip Report on Visits to F.E. Ward Co. to Pour Sulphur Cement into a 1-Cu-Meter Form & Visit Lone Star Cement Co. to Observe Their Filtering System for Removing Suspended Cement From the Wash Water," WCA-7-90, September 25, 1990.
17. Darnell, G. R., EG&G Idaho, Inc., personal communication to Distribution, "Trip Report for Hanford Technical Exchange, Sulfur Polymer Cement as a Stabilization/Solidification Agent," GRD-13-91, May 8, 1991.

APPENDIX A
BOTTOM ASH SAMPLES
OF WERF INCINERATOR ASH

"Providing research and development services to the government"

INTEROFFICE CORRESPONDENCE

DATE: February 13, 1992
TO: R. G. Darnell, MS 3950
FROM: M. C. Verwolf, MS 4107 *MC Verwolf*
SUBJECT: DIGESTION METHODS AND REVISED REPORT FOR BOTTOM ASH SAMPLES -
MCV-02-92

The EPA methods used for digestion of the bottom ash samples are primarily hotplate nitric and hydrochloric acid digestions. Hydrogen peroxide (30%) is also used in the digestions to break down organic constituents.

These methods are considered "total" digestions by the EPA for the purpose of solid waste methods, but the digestions do not break down and solubilize all of the inorganic compounds in the samples. Silicates, aluminates and other oxide compounds are not completely digested by these methods.

A copy of the sample report is enclosed, with the sample type for the Rigby ash corrected. Also enclosed is a 3.5" diskette with the Lotus 1-2-3 file (file name 910134-C.wk1) containing the data.

Please contact me or Shelly Sailer at 6-2730 if you have further questions regarding these data.

ss

Enclosures:
As Stated (2)

cc: J. T. Bennett *for JB*
S. J. Sailer
ECU Project File - WERF
Central Files, MS 1651
M. C. Verwolf File

[illegible]

()
 ()
 ()
 ()
 ()
 ()
 ()
 ()
 ()
 ()

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	524	5
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	---

[illegible][illegible][illegible][illegible]

Parameter	Method	Customer Sample ID:		Sample 1		Sample 2		Sample 1		Sample 2	
		Sample Type:	Lab Blank	Rigby Bottom Ash	Rigby Bottom Ash	WERF Bottom Ash	WERF Bottom Ash	Spike 91318001	Spike 91318001S	Spike 91318002S	% Recovery
		Lab Sample ID:	PrepBlank	Result	Result	Result	Result	% Recovery	% Recovery	% Recovery	% Recovery
Total Metals by ICP-AES or CVAAS											
Arsenic	EPA SW-846 6010	25.0 mg/kgD	< 25.0	< 34.0	< 22.8			80.1		67.4	
Barium	EPA SW-846 6010	20.0 mg/kgD	< 20.0	405	802			109.2		NC	
Cadmium	EPA SW-846 6010	0.50 mg/kgD	< 0.50	< 0.68	9.6			81.1		85.3	
Chromium	EPA SW-846 6010	1.0 mg/kgD	< 1.0	7.3	2170			85.6		NC P2	
Copper	EPA SW-846 6010	2.5 mg/kgD	0.71 J	12.2	555			78.4		NC P2	
Iron	EPA SW-846 6010	20.0 mg/kgD	8.6 J	6240	20900			NC		NC	
Lead	EPA SW-846 6010	15.0 mg/kgD	< 15.0	< 20.4	12900			84.0		NC	
Mercury	EPA SW-846 7471	0.08 mg/kgD	< 0.08	< 0.10	< 0.07			100.8		112.5	
Nickel	EPA SW-846 6010	4.0 mg/kgD	< 4.0	5.9	788			83.7		68.5 P2	
Selenium	EPA SW-846 6010	30.0 mg/kgD	< 30.0	< 40.8	< 27.4			80.4		NC	
Silver	EPA SW-846 6010	1.0 mg/kgD	< 1.0	< 1.4	23.6			62.6		NC P2	
Zinc	EPA SW-846 6010	2.0 mg/kgD	1.6 J	17.5	70300			87.7		NC	

pH	EPA SW-846 9045	pH units	N.A.	11.60	8.29			N.A.		N.A.	
Chloride, water-soluble	EPA 300.0 12/89	4.0 mg/kgD	< 4.0	24.4	16700			90.5		NC	
Total Organic Matter	ASAI, 2,29-4.1	Weight Percent	N.A.	32.5%	6.8% P1			N.A.		N.A.	
% Moisture	EPA 11M01.0	Weight Percent	N.A.	27.8%	1.0%			N.A.		N.A.	

Parameter	Method	Customer Sample ID:			True	% Recovery	95% C.I.
		Sample Type:	Lab Sample ID:	Found			
			MRU and Units	Found			
Total Metals by ICP-AES or CVAAS							
Arsenic	EPA SW-846 6010	25.0 mg/kgD	903	917	98.5	635 - 1199	
Barium	EPA SW-846 6010	20.0 mg/kgD	4.7 J	4.8	97.9	0 - 40	
Cadmium	EPA SW-846 6010	0.50 mg/kgD	38.1	45.4	83.9	35.7 - 55.1	
Chromium	EPA SW-846 6010	1.0 mg/kgD	95.4	99.6	95.8	79.2 - 120	
Copper	EPA SW-846 6010	2.5 mg/kgD	6160	6910	89.1	6006 - 7820	
Iron	EPA SW-846 6010	20.0 mg/kgD	21800	22430	97.2	17770 - 27080	
Lead	EPA SW-846 6010	15.0 mg/kgD	196	236	83.0	188 - 285	
Mercury	EPA SW-846 7471	0.08 mg/kgD	13.7	12.7	108.2	8.5 - 17.0	
Nickel	EPA SW-846 6010	4.0 mg/kgD	51.9	60.9	85.2	49.2 - 72.6	
Selenium	EPA SW-846 6010	30.0 mg/kgD	< 54.0	39.2	--	19.1 - 59.4	
Silver	EPA SW-846 6010	1.0 mg/kgD	20.1	22.2	90.5	15.5 - 29.0	
Zinc	EPA SW-846 6010	2.0 mg/kgD	180	187	96.2	138 - 236	

Parameter	Method	Customer Sample ID:		Sample 1		Sample 2	
		Sample Type:	Lab Blank	Rigby Bottom Ash	WERF Bottom Ash		
		Lab Sample ID:	PrepBlank	91318001	91318002		
		MRL and Units	Result	Result	Result		
Total Metals by ICP-AES or CVAAS							
Arsenic	EPA SW-846 6010	25.0 mg/kgA	< 25.0	< 50.3	< 24.5		
Barium	EPA SW-846 6010	20.0 mg/kgA	< 20.0	601	860		
Cadmium	EPA SW-846 6010	0.50 mg/kgA	< 0.50	< 1.0	10.3		
Chromium	EPA SW-846 6010	1.0 mg/kgA	< 1.0	10.8	2320		
Copper	EPA SW-846 6010	2.5 mg/kgA	0.71 J	18.1	595		
Iron	EPA SW-846 6010	20.0 mg/kgA	8.6 J	9240	22400		
Lead	EPA SW-846 6010	15.0 mg/kgA	< 15.0	< 30.2	13800		
Mercury	EPA SW-846 7471	0.08 mg/kgA	< 0.08	< 0.14	< 0.08		
Nickel	EPA SW-846 6010	4.0 mg/kgA	< 4.0	8.7	846		
Selenium	EPA SW-846 6010	30.0 mg/kgA	< 30.0	< 60.4	< 29.4		
Silver	EPA SW-846 6010	1.0 mg/kgA	< 1.0	< 2.0	25.3		
Zinc	EPA SW-846 6010	2.0 mg/kgA	1.6 J	25.9	75400		

Chloride, water-soluble	EPA 300.0 12/89	4.0 mg/kgA	< 4.0	36.2	17900		

LEGEND

N.A. = Not applicable.

NC = Not calculable: spike added amount is insignificant in comparison to sample concentration.

MRL = Minimum Reporting Limit. This is the lowest concentration reliably measurable (i.e., 3% maximum uncertainty in precision and accuracy at the one standard deviation confidence level) for normal samples during routine laboratory operations.

< = Less than. The value reported immediately following the less than symbol is the Minimum Reporting Limit (MRL) for the analyte. See the MRL definition for further explanation of the MRL. The reported MRL is adjusted for differences in sample weight, sample volume, sample moisture content, and analysis dilutions whenever those parameters differ from that specified for the standard analytical procedure.

mg/kgD Milligram per kilogram concentration determined on dry weight basis (i.e., adjusted for % moisture).

mg/kgA Milligram per kilogram concentration determined on ash weight basis (i.e., adjusted for % moisture and % organic matter).

COMMENTS

J Indicates estimated value. The concentration is below the MRL, but the analyte was detected in the sample.

P1 The relative percent difference (RPD) between duplicate laboratory analyses was 29%.

P2 The relative percent differences (RPDs) between duplicate matrix spikes for Cr, Cu, Ni, and Ag were 22.8%, 67.4%, 73.5%, 83.3%, respectively. These high RPDs may indicate severe matrix interference with the method, or may indicate that sample inhomogeneity caused nonrepresentative subsampling in the laboratory.

METHOD REFERENCES

Total Metals (As, Ba, Cd, Cr, Cu, Fe, Pb, Ni, Se, Ag, Zn) EPA SW-846, 3050A for digestion, 6010 for analysis (Inductively Coupled Plasma Atomic Emission Spectrometry)

Total Mercury EPA SW-846, 7471 (Cold Vapor Atomic Absorption Spectrometry)

pH EPA SW-846, 9045

Chloride, water-soluble EPA 300.0, 12/89 revision, Section 11.7 for solid extraction (Ion Chromatography)

Total Organic Matter Method of Soil Analysis, American Society of Agronomy, No. 9, Part 2, Section 29-4.1. Loss-on-ignition method, ignition carried out at 800 C instead of 550 C to make data more comparable to the TOC method used by commercial laboratories (combustion at 800 C).

Technical and Quality Review:

Shelly J. Sailer
Inorganic Technical Leader

END

**DATE
FILMED**

6 / 3 / 92

10/11/11