NOTICE

**CERTAIN DATA
CONTAINED IN THIS
DOCUMENT MAY BE
DIFFICULT TO READ
IN MICROFICHE
PRODUCTS.**

135
6/29/92 W.B. (2)

DOE/ID/12707-T1
(DE92011592)

**ADVANCED HEAT PUMP FOR THE RECOVERY OF VOLATILE ORGANIC
COMPOUNDS**

Final Report

**Phase 1: Conceptual Design of an Advanced Brayton Cycle Heat Pump for the
Recovery of Volatile Organic Compounds**

March 1992

Work Performed Under Contract No. FC07-88ID12707

**For
U.S. Department of Energy
Office of Industrial Technologies
Washington, D.C.**

**By
3M Corporate Research Laboratory
St. Paul, Minnesota**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615)576-8401.

Available to the public from the National Technical Information Service, U. S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

**ADVANCED HEAT PUMP FOR THE RECOVERY
OF VOLATILE ORGANIC COMPOUNDS**

Final Report

**Phase 1: Conceptual Design of an Advanced Brayton Cycle Heat Pump
for the Recovery of Volatile Organic Compounds**

March 1992

**Work Performed Under Cooperative Agreement
DE-FC07-88ID12707**

**Prepared for the
U.S. Department of Energy
Under DOE Idaho Field Office
Sponsored by the Office of the Assistant Secretary
for Conservation and Renewable Energy
Office of Industrial Technologies
Washington, D.C.**

**Prepared by
3M Division Engineering
P. O. Box 33331
St. Paul, Minnesota 55133-3331
612/733 1110**

EXECUTIVE SUMMARY

Emissions of Volatile Organic Compounds (VOC) from stationary industrial and commercial sources represent a substantial portion of the total U.S. VOC emissions. The 'Toxic-Release Inventory' of The U.S. Environmental Protection Agency estimates this to be at about 3 billion pounds per year (1987 estimates). The majority of these VOC emissions are from coating processes, cleaning processes, polymer production, fuel production and distribution, foam blowing, refrigerant production, and wood products production.

The U.S. Department of Energy's (DOE) interest in the recovery of VOC stems from the energy embodied in the recovered solvents and the energy required to dispose of them in an environmentally acceptable manner. This Phase I report documents 3M's work in close working relationship with its subcontractor Nuclear Consulting Services (Nucon) for the preliminary conceptual design of an advanced Brayton cycle heat pump for the recovery of VOC. Nucon designed Brayton cycle heat pump for the recovery of methyl ethyl ketone and toluene from coating operations at 3M Weatherford, OK, was used as a base line for the work under cooperative agreement between 3M and DOE. See appendix A and reference (4) by Kovach of Nucon.

This cooperative agreement report evaluates and compares an advanced Brayton cycle heat pump for solvent recovery with other competing technologies for solvent recovery and reuse. This advanced Brayton cycle heat pump is simple (very few components), highly reliable (off the shelf components), energy efficient and economically priced.

As a result of work and efforts under this DOE/3M cooperative agreement, Nucon has been successful in commercializing the Brayton cycle heat pump technology under its trade names of 'Braysorb' and 'Braycycle'. Nucon has designed and manufactured a small mobile truck mounted VOC recovery system. This was funded by DOE, Southern California Edison, Electrical Power Research Institute, and 3M (in-kind contribution). Both 3M and Nucon have presented technical papers on Brayton cycle heat pump at American Society of Mechanical Engineers, American Institute of Chemical Engineers, and DOE sponsored conferences.

3M's interest in this technology is for the recovery of solvents from its coating operations. 3M is working closely with DOE to implement the conceptual design of an advanced Brayton cycle heat pump for solvent recovery at its Greenville, SC operations. This installation will be used for data collection, analysis and technology demonstration by 3M and DOE.

TABLE OF CONTENTS

SECTION	PAGE
Executive Summary	i
Table of Contents	iii
List of Figures	iv
List of Tables	v
Report Outline	vi
1.0 Introduction	1
2.0 Objectives and Goals	2
3.0 Project Application	3
4.0 Description of Brayton Cycle Heat Pump	4
5.0 Project Background	7
6.0 Advanced Brayton Cycle	10
7.0 Competing Technologies	12
8.0 Summary	18

Appendix A Weatherford Brayton Cycle Heat Pump

Appendix B Mobile Brayton Cycle System Design

LIST OF FIGURES

FIGURES	PAGE
3.1 Small Mobile Brayton Cycle Heat Pump System	4
4.1 Description of Reverse Brayton Cycle with Solvent Recovery	6
5.1 Simplified 9000 SCFM 3M Hutchinson Brayton System	8
5.2 3M Weatherford Brayton/Concentrator System-Overall Process	10
6.1 Advanced Brayton/Adsorption System for 3M Greenville Plant (Nucon 'Braysorb'™ Process)	11
6.2 Temperature versus Pressure Plot of 'Braysorb'™ Process	12
7.1 Steam Regeneration System with Decanting Solvent/Water Separation	13
7.2 Reverse Rankine Cooled/Inert Gas Regeneration System	14
7.3 Regenerative Incineration System	14

LIST OF TABLES

NUMBER		PAGE
7.1	Cost and Performance Comparison of Four VOC Control Designs for the 3M Greenville, SC Plant	15
7.2	Brayton Regenerated System Cost breakdown	16
7.3	Steam Regenerated System Cost Breakdown	16
7.4	Rankine Regenerated System Cost Breakdown	17
7.5	Cost breakdown of Installation of VOC Control	17
8.1	Progression of Cost and Performance	19

REPORT OUTLINE

Cooperative Agreement No. DE-FCO7-88ID12707 between 3M and DOE is for Phase I of the three phase program. These three phases are defined as follows:

Phase I: Conceptual Design of an Advanced Brayton Cycle Heat Pump Solvent Recovery System.

Phase II: Final Design, Fabrication and Installation of the Brayton Cycle Heat Pump for Solvent Recovery at Greenville, SC.

Phase III: Testing, Data Reporting and Operational Evaluation

This report is for Phase I work only and is outlined as follows. Section 1.0 is an Introduction. Section 2.0 is DOE and 3M Objectives and Goals. Section 3.0 describes the Project Application. Section 4.0 is a description of the Brayton Cycle Heat Pump. Section 5.0 is Project Background. Section 6.0 describes the Advanced Brayton Cycle Heat Pump. Section 7.0 describes competing technologies with cost and performance comparisons for the Greenville installation. And section 8.0 is the summary.

1.0 INTRODUCTION

The use of solvents in industry is widespread. Solvent use affects a large cross-section of products such as adhesive tape, plastic foams, synthetic fibers, electronic components, furniture manufacturing and many more. Recently, environmental concerns have prompted stricter legislation to control VOC emissions (i.e. The Clean Air Act). At the same time the price of some solvents has increased significantly, forcing industry to search for cost effective alternatives to manufacture profitably, yet within environmental regulations. Industry is thus presented with the following choices:

- 1) Eliminate the need for solvents in the manufacture of their product.
- 2) Reduce VOCs by making the process "tighter" (i.e. prevent fugitive emissions).
- 3) Control VOCs by incineration or destruction.
- 4) Control VOCs by capturing and recycling them back to reusable solvent.

3M uses solvents to manufacture a variety of products (eg. adhesive tape, magnetic tape or discs, and other products requiring coating). A corporate wide effort has been implemented by the top management to reduce VOC emissions 90 percent by the year 2000. Therefore, all of the four choices above are being considered.

Controlling VOCs by capture on activated carbon adsorption beds is common in industry today. Although the number of solvent control devices is in the thousands in the U.S., the level of VOCs that are controlled is a small fraction of the total VOC emissions. The U.S. DOE recognizes the potential for solvent recycling throughout the nation as an opportunity to save a significant amount of

energy (50 trillion BTUs annually valued at over 200 million dollars). This energy savings will result from more energy efficient VOC control equipment to be brought to the marketplace, and the saving of the embodied energy of the solvent (i.e. the aggregate of the process energy and feedstock fuel heating value energy required to manufacture the solvent).

Work under Phase I of the 3M/DOE cooperative agreement addresses these concerns. The advanced Brayton cycle heat pump solvent recovery system at Greenville, SC (Phase II) will recover better than 95% of the VOC's emitted and will reuse this in the tape manufacturing process.

2.0 OBJECTIVES AND GOALS

Throughout Phase I work, both DOE and 3M had common objectives and goals to provide a conceptual design of an advanced Brayton cycle heat pump for solvent recovery, that is highly reliable, energy efficient and economically priced.

The first goal is to demonstrate economic solvent recovery for large VOC emission points (e.g. a 1000 ton per year VOC source). A payback of less than three years based on the total installed cost of the equipment with solvents moderately priced at 30 cents per pound, independent of environmental regulatory costs, is a target that DOE and 3M want to achieve.

The second goal is directed at small solvent users of less than 500 tons per year. The mobile BHP should demonstrate to small solvent users (100 tons per year on average) that the annualized

costs of this technology can control many different types of VOC sources at under \$1000 per ton.

Of course, these two goals must be achieved concurrent with reliable equipment, energy efficient equipment and equipment able to meet environmental regulations.

3.0 PROJECT APPLICATION

The Large VOC Control Application

3M and the U.S. DOE are working cooperatively to develop an advanced BCHP system. DOE and 3M will cost-share the design, manufacture and field testing an 8000 scfm BCHP system that will be installed at the 3M Greenville, SC, manufacturing plant to control a 1000 ton per year VOC emission source. Nucon International of Columbus, Ohio, is assisting 3M on this project by providing process engineering, equipment design and, manufacture and installation of the packaged BCHP regeneration/VOC adsorption system.

The Small VOC Control Application

The Greenville plant application is a relatively large VOC control application. Because VOC emission sources greater than 500 tons per year probably account for less than 10 percent of the total nationwide VOC emissions, DOE is also working with Nucon International to develop a cost effective BCHP to control small VOC emission points (e.g. less than 500 tons per year). This project will demonstrate the concept of a single mobile BCHP system to regenerate numerous concentration beds at scattered industrial

host site locations. In this way the capital cost of the mobile BCHP (estimated at \$300,000 to \$400,000) can be distributed amongst many industrial solvent users. Southern California Edison (SCE) and the Electric Power Research Institute (EPRI) are co-sponsoring this project with Nucon, 3M and the DOE, and therefore, the host sites will be located in the southern California area. Figure 3.1 shows the small mobile BCHP system that will initially be demonstrated to four companies in southern California. Applicability of the Brayton concept in solving their specific VOC recovery problem will be evaluated. See Appendix B for description of this system.

Figure 3.1 - Small Mobile Brayton Cycle Heat Pump System

4.0 DESCRIPTION OF BRAYTON CYCLE

The BCHP is an alternative means of condensing solvents from a gas stream by use of a reverse Brayton cycle. Many solvent streams must be refrigerated to temperatures below -50°F (-45°C) to condense more than 90 percent of the

solvent in a single pass through the condensing system. Other refrigeration methods, such as a reverse Rankine cycle using refrigerants in a closed cycle loop can also be and have been used to condense solvents to these low temperatures. (See table 7.1 for comparison of the Brayton cycle to the Rankine cycle and their costs).

To illustrate how refrigeration is accomplished with the reverse Brayton cycle, Figure 4.1 shows an ideal regenerative reverse Brayton cycle on a temperature/entropy diagram. At station 1 the solvent laden gas stream is compressed isentropically to station 2. Heat is extracted in the regenerator from station 2 to 3 at constant pressure. Because heat is extracted from station 2 to 3 the cycle is termed a reverse Brayton cycle. If heat was added by heat exchange or combustion (such as in a gas turbine power plant or jet engine), then the cycle would be a forward Brayton cycle. At station 3 the gas stream temperature will be cold enough to condense a majority of the solvents. From station 3 to 4 the gas stream has work extracted isentropically in an expander (turbine) to lower the gas stream temperature even further. (Temperatures as low as -150°F (-101°C) can be achieved in a single stage of compression and expansion). Essentially all of the remaining solvents are condensed at station 4. The work produced by the expander partially drives the compressor. The remainder of the compressor work requirement comes from mechanical shaft work input. The cold gases at station 4 are then passed through the other side of the regenerator to recoup heat at constant pressure to complete the cycle.

Figure 4.1 - Description of the Reverse Brayton Cycle with Solvent Recovery

Although the Brayton cycle requires high speed turbomachinery, this machinery is commonly used today. All air conditioning systems used on commercial and military jet aircraft use a reverse Brayton cycle system. For aircraft applications, the Brayton refrigeration method has been selected for reasons of low weight and high reliability. Another application of the reverse Brayton cycle is in cryogenic air separation plants. Here too, reliability has been good for over fifty years. At present, the most common application of the Brayton cycle is the automotive turbocharger.

5.0 PROJECT BACKGROUND

3M has actively pursued the BCHP for the past 15 years. Bryce Fox (a retired 3M engineer) was the champion of this technology and is named sole or joint inventor on three 3M patents.

In 1979 3M funded the AiResearch Manufacturing Company (a division of the Garrett Corporation) to provide a 2000 scfm prototype Brayton cycle system. This was used to process a solvent laden gas stream from an inert gas drier at 3M. In showing feasibility and successful operation of this system, the U.S. DOE decided to fund a larger 9000 scfm unit that was installed at 3M's Hutchinson, MN tape manufacturing plant. Both of these systems directly condense the solvents by processing the solvent laden air (SLA) from the coating process through the BCHP.

Both the 2000 and 9000 scfm systems designed by AiResearch used specially manufactured gear boxes that were costly. The system installed at the Hutchinson plant (see Figure 5.1) shows the gear box coupling the input shaft power (an electric motor running at 3600 RPM) to a high speed compressor/turbine unit running at 16,500 RPM.

Figure 5.1 - Simplified 9000 scfm 3M Hutchinson Brayton System

Learning from the experiences of the Hutchinson system, 3M worked with Nucon to design and install the second industrial Brayton cycle system at the 3M Weatherford, OK plant beginning in 1985. The Weatherford design differed from the Hutchinson design as follows:

- 1) Activated carbon beds are used to adsorb and concentrate solvent from the VOC stream.
- 2) The BCHP is used to regenerate the carbon bed with inert nitrogen gas. The higher VOC concentration allowed in nitrogen leads to a smaller BCHP system than is possible in a direct condensation system.

- 3) A molecular sieve is used as an intermediate step between the adsorption and regeneration of the carbon bed to eliminate water (and thus ice formation) from the BCHP solvent laden nitrogen stream.
- 4) A free spindle compressor-expander is used in combination with a rotary blower to provide the compressor/expansion package. That is, the shaft power input to the BCHP system was decoupled from the compressor/expander package to eliminate the high speed gear box used in the Hutchinson design thereby significantly reducing capital cost. This free spindle compressor/expander was a modified design of the Garrett Industrial Products Division's largest diesel turbocharger.

Figure 5.2 shows the overall solvent recovery process in which the two carbon beds are cycled between step 1 and steps 2 to 4. That is, while one bed is adsorbing solvents at step 1, the other is being regenerated by step 2 (carbon dehydration), step 3 (carbon solvent desorption with the reverse Brayton cycle) and step 4 (molecular sieve regeneration).

The Weatherford system has been operating for over 2 years with over 99 percent up time and at 99% efficiency. A more detailed description of the Weatherford process is presented in reference (4) by Kovach of Nucon and under appendix A.

Figure 5.2 - 3M Weatherford Brayton/Concentrator System - Overall Process

6.0 ADVANCED BRAYTON DESIGN

In considering the recycle of solvents, equipment selection will be dictated by capital and operating cost. The solvent type, VOC stream flow size, VOC concentration level and the degree to which the VOC must be controlled (i.e. percent recovery) are all factors influencing cost.

To illustrate the economics of solvent recycling, the Greenville plant installation costs will be detailed for the proposed advanced Brayton design and for three alternative approaches to controlling the VOC emissions from the coater at this plant. The VOC stream to be controlled at Greenville is an 8000 scfm SLA stream with a concentration of approximately 2000 ppmv. The solvents used are heptane, xylene, toluene and isopropylalcohol (IPA).

Figure 6.1 shows the preliminary design of the advanced Brayton system. The Brayton regeneration system will provide a dry inert nitrogen stream for solvent stripping to one of the two adsorbent beds and then will remove over 99 percent of the solvents from the solvent laden nitrogen (SLN) once the SLN is returned from the adsorption bed. (The other adsorption bed is adsorbing solvents from the SLA stream coming from the coater.) This process was developed by Nucon under Phase I of the DOE project. The process is trade marked BRAYSORB™. Figure 6.2 shows the temperature versus pressure plot of this system. Note that the temperature of the dry nitrogen returned to the adsorber is 320°F (160°C) and therefore no additional process heating is needed to regenerate the adsorbent beds. This means that electricity is only needed to drive the Brayton system, eliminating the need for steam production or auxiliary heating systems.

Figure 6.1 - Advanced Brayton/Adsorption System for 3M Greenville Plant
(Figure represents Nucon BRAYSORB™ process)

Figure 6.2 - Temperature versus Pressure Plot of BRAYSORB™ Process

7.0 COMPETING TECHNOLOGIES

Three competing technologies were evaluated and compared with the Brayton cycle heat pump solvent recovery system. For all these technologies, Greenville, SC, VOC emission data was used for cost comparisons. See tables 7.1 to 7.4 for these cost comparisons.

Figure 7.1 shows the generic steam regeneration system analyzed. If the solvents are not miscible or slightly miscible, a decanting system will separate the majority of the solvents from the steam condensate satisfactorily. The contaminated condensate, however, will need to be treated by an air stripper. If the solvents are miscible, a more costly distillation system is required.

Figure 7.1 - Steam Regeneration System with Decanting Solvent/Water Separation

Figure 7.2 shows a schematic of a reverse Rankine system. This system has two cooling systems, one with a 30°F (-1°C) and one with a -80°F (-62°C) evaporator coil cooling temperature. The SLN stream is cooled to -75°F (-59°C), which is the same temperature as that achieved by the Brayton system. This allows for equal comparison of the Brayton and Rankine systems since approximately the same percent solvent recovery should be accomplished.

Figure 7.2 - Reverse Rankine Cooled/Inert Gas Regeneration System

Finally, an incineration system is shown in Figure 7.3. This system is a high efficiency unit with heat regeneration. The system as shown provides for no heat recovery to provide heat to the plant's utilities needs. The solvents that are burned can account for over 50 percent of the fuel heating value in the combustion process.

Figure 7.3 - Regenerative Incineration System

Tables 7.1 compares cost and performance of these four systems. Tables 2 to 4 give a cost breakdown of the three recovery options. Table 5 estimates installation costs of the VOC control options.

Table 7.1 - Cost and Performance Comparison of Four VOC Control Designs for the 3M Greenville, SC Plant

	Brayton	Steam	Rankine	Incineration
Equipment Cost	\$ 565,000 (see Table 2)	\$ 500,000 (See Table 3)	\$ 625,000 (See Table 4)	\$ 540,000
Installation Cost (See Table 5)	\$ 700,000	\$ 800,000	\$ 760,000	\$ 360,000
Total Capital Cost	\$1,265,000	\$1,300,000	\$1,385,000	\$ 900,000
Depreciation & Period	\$ 180,714 7 Years	\$ 185,714 7 Years	\$ 197,857 7 Years	\$ 128,571 7 Years
Energy Requirement & (Type)	139 KW (E)	40 KW (E) 1.33 MMBH (NG)	180 KW (E) 0.75 MMBH (NG)	3.00 MMBH (NG)
Energy Cost *	\$ 48,000	\$ 56,000	\$ 97,200	\$ 77,800
Inert Gas Cost * & (Amount)	\$ 3,000 (800 scf/day)	0	\$ 3,000 (800 scf/day)	0
Labor Cost*	\$ 33,280 16 hrs/wk	\$ 33,280 16 hrs/wk	\$ 33,280 16 hrs/wk	\$ 16,640 8 hrs/wk
Maintenance Cost* (% of Equip Cost)	\$ 113,000 (20%)	\$ 100,000 (20%)	\$ 137,000 (20%)	\$ 108,000 (20%)
Total O&M Cost	\$ 197,280	\$ 189,280	\$ 270,480	\$ 202,440
Solvent Recovery (lbs per hour)	270	265	270	0
(lbs per year)	2.33 MM	2.28 MM	2.33 MM	0
Solvent Savings (\$'s per year)	\$ 279,600	\$ 274,000	\$279,600	
Annualized Cost (\$'s per year)	\$ 98,351	\$ 100,994	\$ 188,737	\$ 331,011
Simple Payback of Recovery over Incineration	1.57 Yrs	1.74 Yrs	3.4 Yrs	-
Simple Payback (solvent at 30 cents per lb)	2.5 Yrs	2.62 Yrs	3.23 Yrs	NA

Economic Factors

operation hours per year - 8640
electricity rate - 4 cents/Kw-Hr
natural gas cost - \$3.00/MM BTU
boiler efficiency - 75%
labor rate - \$40 per Hr
solvent recycle value - \$.12/lb

* Costs are annual   E = Electricity   NG = Natural Gas   MMBH = Million BTU/Hr

Table 7.2 - Brayton Regenerated System Cost Breakdown

Free-spindle Compressor/Expander	\$ 40,000
Drive Compressor	\$ 40,000
Regenerative Heat Exchanger	\$ 40,000
Precooler (water cooling)	\$ 10,000
Piping & Valves	\$ 50,000
Separators & Receivers	\$ 30,000
Instrumentation & Controls	\$ 90,000
Structural Skidding, Mounting, Misc.	\$ 40,000
Adsorber Structure (Carbon Steel)	\$ 60,000
Activated Carbon (20,000 lbs @ \$2/lb)	<u>\$ 40,000</u>
Total Equipment Cost	\$440,000
Engineering	\$ 75,000
Profit	<u>\$ 50,000</u>
Total Equipment Cost	\$565,000

Table 7.3 - Steam Regenerated System Cost Breakdown

Boiler (1000 lb/hr Steam)	\$ 20,000
Decanter & Condenser	\$ 50,000
Piping & Valves	\$ 50,000
Instrumentation & Controls	\$ 50,000
Structural Skidding, Mounting, Misc.	\$ 40,000
Adsorber Structure (304 Stainless)	\$ 80,000
Activated Carbon (20,000 lbs @ \$2/lb)	\$ 40,000
Cooling Tower	\$ 30,000
Water Treatment System	<u>\$ 50,000*</u>
Total Equipment Cost	\$ 410,000
Engineering	\$ 50,000
Profit	<u>\$ 40,000</u>
Total Equipment Cost	\$ 500,000

* Site dependent - Cost may be as high as \$500,000

Table 7.4 - Rankine Regenerated System Cost Breakdown

Precooler (water cooling)	\$ 10,000
Precooling Refrigeration Unit	\$ 20,000
Regenerative Heat Exchanger	\$ 20,000
Super-cooler Refrigeration Unit	\$ 150,000
Regenerator Blower	\$ 10,000
Heating Unit	\$ 10,000
Piping & Valves	\$ 50,000
Separators & Receivers	\$ 30,000
Instrumentation & Controls	\$ 90,000
Adsorber Structure (Carbon Steel)	\$ 60,000
Activated Carbon (20,000 lbs @ \$2/lb)	\$ 40,000
Total Equipment Cost	\$ 490,000
Engineering	\$ 75,000
Profit	\$ 60,000
Total Equipment Cost	\$ 625,000

Table 7.5 - Cost Breakdown of Installation of VOC Control

	<u>VOC Recovery</u>	<u>VOC Incineration</u>
Engineering	\$ 50,000	\$ 50,000
SLA Fan, Filter, Cooler, Ducting	\$ 100,000	\$ 100,000
Site Preparation *	\$ 250,000	\$ 120,000
Tank Farms	\$ 150,000	\$ 0
Equipment Installation	\$ 100,000	\$ 40,000
Process Instrumentation	\$ 50,000	\$ 50,000
Total Installation Cost	\$ 700,000	\$ 360,000

* Add \$60,000 for a building enclosure on the Rankine system

* Add \$100,000 for a cooling tower installation for a Steam system

A few conclusions can be made from the above tables:

- 1) All the solvent recovery technologies have lower annualized operating cost than incineration. Also, the incremental investment of all three recovery technologies over the cost of the incineration system yields a 1.5 to 3.5 years payback based on the aggregate savings of the recycled solvents and the difference in operating costs of the recovery options and incineration. In the future if the solvent price were, for instance, 30 cents

per pound for this application then the payback on Brayton and steam regeneration system would be less than 3 years.

- 2) The Brayton system costs are estimated to be competitive with the well established recovery technologies. This cost estimate of the Brayton system is for the third generation design. Further cost reduction can be expected in the future. For this reason, 3M is pursuing this technology so that their choices on controlling VOCs may be broadened. Likewise, the DOE sees the Brayton technology as a vehicle to reduce energy consumption of VOC control technologies and, to proliferate solvent recycling with more cost effective recycling with both large and small solvent users and thereby reduce demand for energy intensive solvent production nationwide.

8.0 SUMMARY

The main accomplishments over the last 15 years on the Brayton cycle solvent recovery technology have been to reduce capital cost, reduce energy consumption and improve reliability of the equipment. Table 8.1 summarizes the performance of the two 3M Brayton systems already installed (Hutchinson and Weatherford) and the expected performance of the planned Greenville plant installation.

**Table 8.1 - Progression of Cost and Performance
Improvements with the BCHP at 3M**

	<u>Hutchinson</u>	<u>Weatherford</u>	<u>Greenville</u>
SLA Stream Size (scfm)	9000	9000	8000
Time period designed & Built	1979 - 1984	1985 - 1987	1988 - 1991
Solvent Type	MEK, Toluene, Cyclohexanone	MEK, Toluene, Cyclohexanone	Heptane, Xylene Toluene, IPA
VOC Conc. (PPMV)	4000	2000	2000
Power Required (HP)	550	450	180
Equipment Cost	\$1,500,000 ⁽¹⁾	\$1,000,000 ⁽¹⁾	\$ 565,000 (From Table 2)

(1) Estimated equipment costs in 1990 dollars to replicate the installed equipment. This does not include installation cost.

In summary, substantial improvements have been made on the Brayton cycle technology, especially in the last two years. Stricter environmental regulations for VOCs creates a demand in industry for VOC control equipment at reduced cost. Higher solvent prices will also further enhance the economics of solvent recycling over incineration. The DOE and 3M therefore remain committed to this technology.

A three phase cooperative effort between the U.S. DOE, 3M, and Nucon International is about to enter the Phase II effort to design and fabricate a Brayton cycle heat pump system to control an 8000 scfm VOC air stream. Estimates from a preliminary design shows that the equipment cost and energy consumption have both been more than halved from the previous generation design at 3M. This new and advanced system is expected to be operational

sometime in 1992. This design will form the basis for other 3M facilities and other companies with similar VOC control needs to follow through with implementation of other cost competitive Brayton cycle heat pump installations.

References

- (1) Heat and Liquid Recovery Using Open Cycle Heat Pump System,
Bryce Fox, 3M; U.S. Patent #4,295,282, Dated October 20, 1981
- (2) Vapor Recovery Method and Apparatus,
Leslie R. Flink, Bryce J. Fox, Mary K. Witzel, 3M
U.S. Patent #4,480,393, Dated November 6, 1984
- (3) Heat and Liquid Recovery Using Open Cycle Heat Pump System
Bryce J. Fox, 3M; U.S. Patent #4,539,816, Dated September 10, 1985
- (4) Full Size Industrial Application of the Brayton Cycle Heat Pump in Adsorption Concentrator, J. L. Kovach, 1989 ASME Winter Annual Meeting, AES-Volume 8 (Advances in Industrial Heat Pumps Technology - 1989). December, 1989

APPENDIX A

Weatherford Brayton cycle solvent recovery system:

Weatherford solvent recovery system is based on BHP solvent recovery process using free spindle turbo compressors. This system was designed and fabricated by Nucon. Solvent is methyl ethyl ketone and toluene.

This appendix contains four P & ID drawings and a system component list.

NOTES: UNLESS OTHERWISE SPECIFIED

1. CORROSION COUPONS SP #1 TRU SP #6
2. INSTRUMENT TAPS - ALL 3/4" 1/2"-CLPG.

REVISION RECORD

	DATE	DR	CK	DESCRIPTION	PE	QA	PW
-	MAY 10 1990	CFA	JMS	INITIAL RELEASE	JLK 12 JUL 1989	SAF 12 JUL 1989	MMW 12 JUL 1989
A	06 DEC 1990	CFA	JMS	EDCN -1	DSK 12 DEC 1989	SAF 13 DEC 1989	MMW 11 DEC 1989
B	19 FEB 1990	CFA	HRS	EDCN -5	JMS 20 FEB 1990	SAF 20 FEB 1990	MMW 20 FEB 1990
C	09 APR 1990	CFA	HLS	EDCN -12	JMS 10 APR 1990	SAF 10 APR 1990	MMW 10 APR 1990
D							
E							

THE INFORMATION CONTAINED HEREIN IS NOT PUBLIC BUT BELONGS TO NUCON INTERNATIONAL, INC. WHO HAS PROVIDED IT SOLELY FOR AN EXPRESSLY RESTRICTED PRIVATE USE. ALL PERSONS, FIRMS OR CORPORATIONS WHO RECEIVE SUCH INFORMATION SHALL BE DEEMED BY THEIR ACT OF RECEIVING THE SAME TO HAVE AGREED TO MAKE NO DUPLICATION OR OTHER DISCLOSURE OR USE WHATSOEVER OF ANY OR ALL OF SUCH INFORMATION EXCEPT SUCH RESTRICTED USE AS IS EXPRESSLY AUTHORIZED IN WRITING BY NUCON INTERNATIONAL, INC.

NEXT ASSY

R.Y. DWG

0771-101-02
0771-101-04

TOLERANCES
except
as noted
DECIMALS

FRACTIONS

ANGLES

NUCON®

7000 Monterey Road, Columbus, Ohio 43229-1036

DOE/EPRI/3M/NUCON/SCE

DWG TITLE

P&ID - ADSORPTION/REGENERATION

SCALE

DWG No

0771-101-01

REV

C

REVISION RECORD

	DATE	DR	CR	DESCRIPTION	PF	QA	FW
D	MAY 8 1989	CFA	JMS	INITIAL RELEASE	JUL 12 1989	SAP 12 JUL 1989	MNM 12 JUL 1989
A	08 DEC 11:59	CFA	JMS	EDCN -2	DEC 12 1989	SAP 13 DEC 1989	MNM 11 DEC 1989
B	18 FEB 11:50	CFA	HRS	EDCN -6	FEB 20 1990	SAP 20 FEB 1990	MNM 20 FEB 1990
C	09 MAR 1990	CFA	HMS	EDCN -13	MAR 5 1990	SAP 17 MAR 1990	MNM 12 MAR 1990
D							
E							

THE INFORMATION CONTAINED HEREIN IS NOT PUBLIC BUT BELONGS TO NUCON INTERNATIONAL, INC. WHO HAS PROVIDED IT SOLELY FOR AN EXPRESSLY RESTRICTED PRIVATE USE. ALL PERSONS, FIRMS OR CORPORATIONS WHO RECEIVE SUCH INFORMATION SHALL BE LEGALLY BY THEIR ACT OF RECEIVING THE SAME TO HAVE AGREED TO MAKE NO DUPLICATION OR OTHER DISCLOSURE OR USE WHATSOEVER OF ANY OR ALL OF SUCH INFORMATION EXCEPT SUCH RESTRICTED USE AS IS EXPRESSLY AUTHORIZED IN WRITING BY NUCON INTERNATIONAL, INC.

NEXT ARRY

REF DWG

0771-101-01

0771-101-03

TOLERANCES

UNLESS

OTHERWISE

SPECIFIED

DECIMALS

FRACTIONS

ANGLES

SCALE

DWG No

REV

NUCON®

7000 Montebello Road, Columbus, Ohio 43220-1000

DOE/EPRI/3M/NUCON/SCE

P&ID -- REGENERATION

0771-101-02

C

10000

BATT. LIMIT
BY CLIENT

REVISION RECORD

	DATE	DR	CK	DESCRIPTION	PE	QA	PM
O	MAR 10 1989	CFA	JMS	INITIAL RELEASE	JLK 12 JUL 1989	SAF 12 JUL 1989	MNW 12 JUL 1989
A	08 DEC 1989	CFA	JMS	EDCN - 3	JLK 12 DEC 1989	SAF 13 DEC 1989	MNW 12 DEC 1989
B	19 FEB 1990	CFA	HRS	EDCN - 7	JMS 20 FEB 1990	SAF 20 FEB 1990	MNW 20 FEB 1990
C	19 MAR 1990	CFA	HLS	EDCN - 14	JMS 27 MAR 1990	SAF 28 MAR 1990	MNW 29 MAR 1990
D							
E							

THE INFORMATION CONTAINED HEREIN IS NOT PUBLIC BUT BELONGS TO NUCON INTERNATIONAL, INC. WHO HAS PROVIDED IT SOLELY FOR AN EXPRESSLY RESTRICTED PRIVATE USE. ALL PERSONS, FIRMS OR CORPORATIONS WHO RECEIVE SUCH INFORMATION SHALL BE DEEMED BY THEIR ACT OF RECEIVING THE SAME TO HAVE AGREED TO MAKE NO DUPLICATION OR OTHER DISCLOSURE OR USE WHATSOEVER OF ANY OR ALL OF SUCH INFORMATION EXCEPT SUCH RESTRICTED USE AS IS EXPRESSLY AUTHORIZED IN WRITING BY NUCON INTERNATIONAL, INC.

NEXT ASSY

TOLERANCES
except
as noted

7000 Hunting Road, Columbus, Ohio 43229-1000

REV DWG

0771-101-02

DECIMALS

FRACTIONS

ANGLES

DWG TITLE

PMO - REGENERATION
TURBO COMPRESSOR/EXPANDER

SCALE

DWG No.

0771-101-03

REV

C

ACAD FILE
V:\ACAD\DWG\DOE771\01-03\RC.DWG

10000

A
B
C
D
E
F
G
H

1

2

3

4

5

1

2

3

4

5

H

G

F

E

D

C

B

A

JUN 68

NOTES: UNLESS OTHERWISE SPECIFIED

REVISION RECORD

	DATE	DR	OK	DESCRIPTION	PE	QA	PM
-	08 DEC 1983	CFA		INITIAL RELEASE			
A							
B							
C							
D							
E							

THE INFORMATION CONTAINED HEREIN IS NOT PUBLIC BUT BELONGS TO NUCLEAR CONSULTING SERVICES, INC. WHO HAS PROVIDED IT SOLELY FOR AN EXPRESSLY RESTRICTED PRIVATE USE. ALL PERSONS, FIRMS OR CORPORATIONS WHO RECEIVE SUCH INFORMATION SHALL BE DEEMED BY THEIR ACT OF RECEIVING THE SAME TO HAVE AGREED TO MAKE NO DUPLICATION OR OTHER DISCLOSURE OR USE WHATSOEVER OF ANY OR ALL OF SUCH INFORMATION EXCEPT SUCH RESTRICTED USE AS IS EXPRESSLY AUTHORIZED IN WRITING BY NUCLEAR CONSULTING SERVICES, INC.

CAD FILE \ACAD\DWG\1006771\201-01	NEXT ASSY	TOLERANCES except as noted	NUCLEAR CONSULTING SERVICES, INC. P.O. Box 20181 Columbus, Ohio 43220	
	REF DWG	DECIMALS	DOE/EPRI/NUCON/SCE	
	0771-601-01	-----	DWG TITLE	
	0771-601-02	-----	PIPING & EQUIPMENT DIAGRAM	
	0771-601-03	-----	ANGLES	SCALE
		-----	-----	-----
			DWG NO.	REV
			0771-201-01	0

NOTES: UNLESS OTHERWISE SPECIFIED

1. NOTES REVISED

REVISION RECORD

	DATE	DR	OK	DESCRIPTION	PE	QA	PW
-	08 DEC 1989	CFA	HRS 08 JAN 1990	INITIAL RELEASE	JRS 08 JAN 1990	SAF 08 JAN 1990	MNW 08 JAN 1990
A	02 FEB 1989	CFA	HRS 17 FEB 1990	EDCN -5	JJS 14 FEB 1990	SAF 14 FEB 1990	MNW 14 FEB 1990
B							
C							
D							
E							

THE INFORMATION CONTAINED HEREIN IS NOT PUBLIC BUT BELONGS TO NUCON INTERNATIONAL, INC. WHO HAS PROVIDED IT SOLELY FOR AN EXPRESSLY RESTRICTED PRIVATE USE. ALL PERSONS, FIRMS OR CORPORATIONS WHO RECEIVE SUCH INFORMATION SHALL BE DEEMED BY THEIR ACT OF RECEIVING THE SAME TO HAVE AGREED TO MAKE NO DUPLICATION OR OTHER DISCLOSURE OR USE WHATSOEVER OF ANY OR ALL OF SUCH INFORMATION EXCEPT SUCH RESTRICTED USE AS IS EXPRESSLY AUTHORIZED IN WRITING BY NUCON INTERNATIONAL, INC.

OLD FILE
V-CAD/DWG/DOE771/601-01

NEXT ASSY	TOLERANCES except as noted	NUCON® 7900 Huntley Road, Columbus, Ohio 43229-1036	
REF DWG 0771-601-02 0771-601-03 0771-201-01	DECIMALS ----- FRACTIONS 1/16 ANGLES -----	DOE/EPRI/3M/NUCON/SCE DWG TITLE PIPING & EQUIPMENT LAYOUT SCALE 3/4"=1'	
		DWG No 0771-601-01	REV A

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

JOB No 10TH625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION
ISSUE DATE 18 JAN 1989
ISSUE No 1
PAGE 1

RUN DATE 18 JAN 1989

EQUIP-ID	SERVICE LOCATION	FLOW DIAG	ELEM DIAG	PIPE DIAG	SPEC No	RANGE	PO NUMBER	PO DATE	DEL DATE
AE -101	CO SAMPLE (TOP) D-1 V. L. TOWNER CO.	0616-101-01			616001		12264	16 SEP 85	25 OCT 85
AE -102	CO SAMPLE (BOTTOM) D-1 V. L. TOWNER CO.	0616-101-01			616001		12264	16 SEP 85	25 OCT 85
AE -103	HYDROCARBON SAMPLE D-1 AIR OUTLET V. L. TOWNER CO.	0616-101-01			616001		12264	16 SEP 85	25 OCT 85
AE -201	CO SAMPLE (TOP) D-2 V. L. TOWNER CO.	0616-101-01			616001		12264	16 SEP 85	25 OCT 85
AE -202	CO SAMPLE (BOTTOM) D-2 V. L. TOWNER CO.	0616-101-01			616001		12264	16 SEP 85	25 OCT 85
AE -203	HYDROCARBON SAMPLE D-2 V. L. TOWNER CO.	0616-101-01			616001		12264	16 SEP 85	25 OCT 85
AE -301	CO SAMPLE (TOP) D-3 V. L. TOWNER CO.	0616-101-01			616001		12264	16 SEP 85	25 OCT 85
AE -302	CO SAMPLE (BOTTOM) D-3 V. L. TOWNER CO.	0616-101-01			616001		12264	16 SEP 85	25 OCT 85
AE -303	HYDROCARBON SAMPLE D-3 V. L. TOWNER CO.	0616-101-01			616001		12264	16 SEP 85	25 OCT 85
AE -507	SLA INLET HYDROCARBON SAMPLE C-1 OUTLET V. L. TOWNER CO.	0616-101-01			616001		12264	16 SEP 85	25 OCT 85

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

JOB No 10TM625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION

ISSUE DATE 18 JAN 1989
ISSUE No 1

PAGE 2

RUN DATE 18 JAN 1989

EQUIP-ID	SERVICE LOCATION	FLOW DIAG	SPEC No	PO NUMBER
	VENDOR	PIPE DIAG	RANGE	DEL DATE
AE -512	REGEN GAS MOISTURE SAMPLE E-2 INLET V. L. TOWNER CO.	0616-101-02	616001	12264 16 SEP 85
AE -530	REGEN GAS OXYGEN CONTENT E-3 DISCH. V. L. TOWNER CO.	0616-101-02	616001	12264 16 SEP 85
DPI -517	MOL. SIEVE PRESSURE DROP D-4 Dwyer Instruments Inc.	0616-101-02	616002 0-10" U.C.	12289 11 OCT 85
DPI -571	F-4 FILTER PRESSURE DROP F-4 FILTER Dwyer Instruments Inc.	0616-602-01	616003 0-5" U.C.	12289 11 OCT 85
DPI -641	F-3 FILTER PRESSURE DROP F-3 FILTER Dwyer Instruments Inc.	0616-101-02	616060 0-10" U.C.	12289 11 OCT 85
DPI -651	SEKADO BED PRESSURE DROP F-1 FILTER SINCO CONTROLS	0616-101-01	616050 0-3" U.C.	13667 30 SEP 86
DPI -652	YORK PAD PRESSURE DROP F-1 FILTER SINCO CONTROLS	0616-101-01	616018 0-2" U.C.	13667 30 SEP 86
DPS -571	F-4 FILTER PRESSURE DROP F-4 FILTER Dwyer Instruments Inc.	0616-101-03	616061 3-11" U.C.	12289 11 OCT 85
DPS -641	F-3 FILTER PRESSURE DROP F-3 FILTER Dwyer Instruments Inc.	0616-101-02	616061 4-1.6" U.C.	12289 11 OCT 85
DPS -642	F-2 FILTER PRESSURE DROP F-2 FILTER RAUDON MYERS INC.	0616-101-05	616062 0-20 PSID	12450 21 OCT 85
		0616-602-05		20 DEC 85

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

JOB No 107M25
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION
ISSUE DATE 18 JAN 1989
ISSUE No 1
PAGE 3

RUN DATE 18 JAN 1989

EQUIP-ID

SERVICE
LOCATION
VENDOR

FLOW DIAG
ELEM DIAG
PIPE DIAG

SPEC No
RANGE
CHTL SIG

PO NUMBER
PO DATE
DEL DATE

DPT -555 TURBO SIDE DIFFERENTIAL PRESSURE

C-4\G-5

M. L. JOHNSON CO., INC.

616030

13162

10 APR 86

08 JUN 86

DPT -556 COMPRESSOR SIDE DIFFERENTIAL PRESSURE

C-4\G-5

M. L. JOHNSON CO., INC.

616031

13162

10 APR 86

08 JUN 86

EP -504

I TO P CONVERTER

C-1 BLOWER (VA-504)

M. L. JOHNSON CO.

616035

12122

05 AUG 85

30 SEP 85

EP -510

I TO P CONVERTER

TV-510 (E-6 EXCHANGER)

M. L. JOHNSON CO.

616035

12122

05 AUG 85

30 SEP 85

EP -514

I TO P CONVERTER

TV-514 (E-4 EXCHANGER)

M. L. JOHNSON CO.

616035

13162

10 APR 86

10 JUN 86

EP -521

I TO P CONVERTER

PV-521 (E-8 EXCHANGER)

M. L. JOHNSON CO.

616035

12122

05 AUG 85

30 SEP 85

EP -523

I TO P CONVERTER

TV-523 (E-7 EXCHANGER)

M. L. JOHNSON CO.

616035

12122

05 AUG 85

30 SEP 85

EP -533

I TO P CONVERTER

TV-533

M. L. JOHNSON CO.

616035

12122

05 AUG 85

30 SEP 85

EP -539

I TO P CONVERTER

PV-539

M. L. JOHNSON CO.

616035

12122

05 AUG 85

30 SEP 85

EP -552

I TO P CONVERTER

TV-552 (E-10 EXCHANGER)

M. L. JOHNSON CO.

616035

12122

05 AUG 85

30 SEP 85

NUCLEAR CONSULTING SERVICES INC.

PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

PAGE 4

ISSUE DATE 18 JAN 1989

1

JOB No 10TH625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION

RUN DATE 18 JAN 1989

EQUIP-ID

SERVICE
LOCATION
VENDOR

FLOW DIAG
ELEM DIAG
PIPE DIAG

SPEC No
RANGE
CHTL SIG

PO NUMBER
PO DATE
DEL DATE

616013

0616-101-06

CO SAMPLE
ANALYZER PANEL
FURNISHED WITH PANEL

616013

0616-101-07

HYDROCARBON SAMPLE
ANALYZER PANEL
FURNISHED WITH PANEL

616013

0616-101-08

OXYGEN SAMPLE
ANALYZER PANEL
FURNISHED WITH PANEL

12135
05 AUG 85
30 SEP 85

616004
0-5 GPM

0616-101-03

SOLVENT FLOW
S-1 DISCH.
GILSON SALES, INC.

12135
05 AUG 85
30 SEP 85

616004
0-2 GPM

0616-101-03

SOLVENT FLOW
S-2 DISCH.
GILSON SALES, INC.

12125
05 AUG 85
04 OCT 85

616005

0616-101-01

FIRE CONTROL WATER
D-1
FOX & DOLE INC.

12125
05 AUG 85
04 OCT 85

616005

0616-101-01

FIRE CONTROL WATER
D-2
FOX & DOLE INC.

12125
05 AUG 85
04 OCT 85

616005

0616-101-01

FIRE CONTROL WATER
D-3
FOX & DOLE INC.

12128
05 AUG 85
16 SEP 85

616006
100-500 SCFH

0616-101-02

OXYGEN PURGE FLOW
E-3 DISCH.
AQUAMATIC, INC.

616054
0-1500 SCCM

0616-101-06

CO SAMPLE FLOW
ANALYZER PANEL
FURNISHED WITH PANEL

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

JOB No 10TH625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT JM COMPANY DRP DIVISION
ISSUE DATE 18 JAN 1989
ISSUE No 1
PAGE 5

RUN DATE 18 JAN 1989

EQUIP-ID

SERVICE
LOCATION
VENDOR

FLOW DIAG
ELEM DIAG
PIPE DIAG
SPEC No
RANGE
CNTRL SIG
PO NUMBER
PO DATE
DEL DATE

FI -633 HYDROCARBON SAMPLE FLOW
ANALYZER PANEL
FURNISHED WITH PANEL

0616-101-07 616054
0-5000 SCCM

FI -639 OXYGEN SAMPLE FLOW
ANALYZER PANEL
FURNISHED WITH PANEL

0616-101-08 616054
0-300 SCCM

FI -653 C-1 FLOW
C-1 SLA BLOWER
SIMCO CONTROLS

0616-101-01 616032 13667
0-20400 SCFH 30 SEP 86
0616-601-01

F01 -581 S-1 SOLVENT FLOW
ANALYZER PANEL
GILSON SALES, INC.

0616-101-03 616004 12135
0-5 GPM 05 AUG 85
30 SEP 85

F01 -582 S-2 SOLVENT FLOW
ANALYZER PANEL
GILSON SALES, INC.

0616-101-03 616004 12135
0-2 GPM 05 AUG 85
30 SEP 85

FS -605 TURBO COMPRESSOR LUBE OIL FLOW
LUBE OIL SYSTEM (D-7)
SURKAMP & ROWE INC.

0616-101-05 616052 13159
0616-602-05 25 APR 86
06 JUN 86

FV -101 SLA INLET
D-1

0616-101-01 616007 12032
0-1 22 JUL 85
27 NOV 85

CARRIG & ASSOC. INC.

FV -102 AIR OUTLET
D-1

0616-101-01 616007 12032
0-1 22 JUL 85
27 NOV 85

CARRIG & ASSOC. INC.

FV -103 REGEN GAS INLET
D-1

0616-101-01 616007 12032
0-1 22 JUL 85
27 NOV 85

CARRIG & ASSOC. INC.

FV -104 REGEN GAS OUTLET
D-1

0616-101-01 616007 12032
0-1 22 JUL 85
27 NOV 85

CARRIG & ASSOC. INC.

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

PAGE 6

ISSUE DATE 18 JAN 1989
ISSUE No 1

JOB No 107N625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DEP DIVISION

RUN DATE 18 JAN 1989

EQUIP-ID	SERVICE LOCATION VENDOR	FLOW DIAG ELEN DIAG PIPE DIAG	SPEC No RANGE CHTL SIG	PO NUMBER PO DATE DEL DATE
FV -105	FIRE CONTROL WATER INLET D-1 OYL-AIR EQUIP. CO.	0616-101-01 0616-601-01	616008	12132 05 AUG 85 09 SEP 85
FV -106	D-1 FIRE CONTROL WATER DRAIN D-1 OYL-AIR EQUIP. CO.	0616-101-01 0616-601-01	616008	12132 05 AUG 85 09 SEP 85
FV -201	SLA INLET D-2 CARRIG & ASSOC. INC.	0616-101-01 0616-601-01	616007	12032 22 JUL 85 27 NOV 85
FV -202	AIR OUTLET D-2 CARRIG & ASSOC. INC.	0616-101-01 0616-601-01	616007	12032 22 JUL 85 27 NOV 85
FV -203	REGEN GAS INLET D-2 CARRIG & ASSOC. INC.	0616-101-01 0616-601-01	616007	12032 22 JUL 85 27 NOV 85
FV -204	REGEN GAS OUTLET D-2 CARRIG & ASSOC. INC.	0616-101-01 0616-601-01	616007	12032 22 JUL 85 27 NOV 85
FV -205	FIRE CONTROL WATER INLET D-2 OYL-AIR EQUIP. CO.	0616-101-01 0616-601-01	616008	12132 05 AUG 85 09 SEP 85
FV -206	FIRE CONTROL WATER DRAIN D-2 OYL-AIR EQUIP. CO.	0616-101-01 0616-601-01	616008	12132 05 AUG 85 09 SEP 85
FV -301	SLA INLET D-3 CARRIG & ASSOC. INC.	0616-101-01 0616-601-01	616007	12032 22 JUL 85 27 NOV 85
FV -302	AIR OUTLET D-3 CARRIG & ASSOC. INC.	0616-101-01 0616-601-01	616007	12032 22 JUL 85 27 NOV 85

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSURMENT LIST

PAGE 7

ISSUE DATE 18 JAN 1989

ISSUE No 1

JOB No 10TM625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DEP DIVISION

RUN DATE 18 JAN 1989

PO NUMBER
PO DATE
DEL DATE

SPEC No
RANGE
CHTL SIG

FLOW DIAG
ELEM DIAG
PIPE DIAG

SERVICE
LOCATION
VENDOR

EQUIP-ID

12032
22 JUL 85
27 NOV 85

616007

0616-101-01

FV -303 REGEN GAS INLET
D-3
CARRIG & ASSOC. INC.

12032
22 JUL 85
27 NOV 85

616007

0616-101-01

FV -304 REGEN GAS OUTLET
D-3
CARRIG & ASSOC. INC.

12132
05 AUG 85
09 SEP 85

616008

0616-101-01

FV -305 FIRE CONTROL WATER INLET
D-3
OYL-AIR EQUIP. CO.

12132
05 AUG 85
09 SEP 85

616008

0616-101-01

FV -306 FIRE CONTROL WATER DRAIN
D-3
OYL-AIR EQUIP. CO.

12032
22 JUL 85
27 NOV 85

616007

0616-101-02

FV -525 BYPASS FROM MOL SIEVE
PIPING
CARRIG & ASSOC. INC.

12032
22 JUL 85
27 NOV 85

616007

0616-101-02

FV -528 E-3 BYPASS
E-3
CARRIG & ASSOC. INC.

13058
26 MAR 86

616009

0616-101-02

FV -532 PURGE GAS BYPASS
E-3 DISCH.
A. E. EHRE CO.

12032
22 JUL 85
27 NOV 85

616007

0616-101-02

FV -534 BYPASS TO MOL SIEVE
PIPING
CARRIG & ASSOC. INC.

12132
13 AUG 85
09 SEP 85

616008

0616-101-04

FV -547 C.W. SUPPLY
E-8 INLET
OYL AIR EQUIPMENT CO.

12228
04 SEP 85
30 DEC 85

616007

0616-101-02

FV -554 E-6 BYPASS
E-6
CARRIG & ASSOC. INC.

0616-601-02

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

JOB No 107N625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION

ISSUE DATE 18 JAN 1989
ISSUE No 1

PAGE 8

RUN DATE 18 JAN 1989

EQUIP-ID	SERVICE LOCATION	FLOW DIAG	ELEM DIAG	PIPE DIAG	SPEC No	RANGE	CNTL SIG	PO NUMBER	PO DATE	DEL DATE
FV -640	C-2\3-BYPASS PIPING SINCO SUPPLY CO.	0616-101-02	0616-602-02		616008			12410	15 OCT 85	15 NOV 85
GA -512	REGEN GAS MOISTURE PANEL KING ASSOC. INC.	0616-101-02			616046			12123	05 AUG 85	28 OCT 85
GA -544	CO ANALYZER PANEL BECKMAN INDUSTRIAL INC.	0616-101-01			616047			12119	05 AUG 85	28 OCT 85
GA -545	HYDRO-CARBON ANALYZER PANEL BECKMAN INDUSTRIAL INC.	0616-101-01			616048			12119	05 AUG 85	28 OCT 85
GA -546	OXYGEN ANALYZER PANEL BECKMAN INDUSTRIAL INC.	0616-101-02			616049			12119	05 AUG 85	28 OCT 85
GA -668	NITROGEN PURITY NITROGEN GENERATOR	0616-101-02								
LC -541	LEVEL CONTROL S-2 SURKAMP & ROWE INC.	0616-101-03			616010	0-14"	3-15 PSIG	12120	05 AUG 85	01 NOV 85
LC -543	LEVEL CONTROL S-1 SURKAMP & ROWE INC.	0616-101-03			616010	0-14"	3-15 PSIG	12120	05 AUG 85	01 NOV 85
LC -585	LEVEL CONTROL D-6 SURKAMP & ROWE INC.	0616-101-03			616010			12120	05 AUG 85	01 NOV 85
LCV -541	LEVEL CONTROL S-2 DISCH. OVL-AIR EQUIP. CO.	0616-101-03			616011		3-15 PSIG	12124	05 AUG 85	01 NOV 85

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

JOB No 10TM625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION

ISSUE DATE 18 JAN 1989
ISSUE No 1

PAGE 9

RUN DATE 18 JAN 1989

EQUIP-ID	SERVICE LOCATION	FLOW DIAG ELEM DIAG PIPE DIAG	SPEC No RANGE CNTRL SIG	PO NUMBER PO DATE DEL DATE
LCV -543	LEVEL CONTROL S-1 DISCH. OYL-AIR EQUIP. CO.	0616-101-03 0616-602-01	616011 3-15 PSIG	12124 05 AUG 85 01 NOV 85
LG -563	SOLVENT LEVEL S-1 FISCHER PUMP & VALVE CO.	0616-101-03 0616-602-01	616012 0-14"	12134 05 AUG 85 06 SEP 85
LG -564	SOLVENT LEVEL S-2 FISCHER PUMP & VALVE CO.	0616-101-03 0616-602-01	616012 0-14"	12134 05 AUG 85 06 SEP 85
LG -602	TURBOCOMPRESSOR LUBE OIL RECEIVER LEVEL D-7 FISCHER PUMP & VALVE CO.	0616-101-05 0616-602-05	616053 0-12"	12134 05 AUG 85 06 SEP 85
LSL -601	TURBOCOMPRESSOR LUBE OIL RECEIVER LEVEL D-7 DUYER INSTRUMENTS INC.	0616-101-05 0616-602-05	616010	12289 18 SEP 85 13 DEC 85
MV -107	DRAIN SEAL LOOP BYPASS D-1 OYL-AIR EQUIP. CO.	0616-101-01 0616-601-01	616008	12132 05 AUG 85 09 SEP 85
MV -207	DRAIN SEAL LOOP BYPASS D-2 OYL-AIR EQUIP. CO.	0616-101-01 0616-601-01	616008	12132 05 AUG 85 09 SEP 85
MV -307	DRAIN SEAL LOOP BYPASS D-3 OYL-AIR EQUIP. CO.	0616-101-01 0616-601-01	616008	12132 05 AUG 85 09 SEP 85
MV -654	FIRE CONTROL WATER SUPPLY FIRE CONTROL DELUGE VALVE SUPPLIED BY CONTRACTOR	0616-101-01 0616-601-01	616017	12132 05 AUG 85 09 SEP 85
MV -657	REGEN LOOP AIR PURGE D-3 SUPPLIED BY CONTRACTOR	0616-101-01 0616-601-02	NUCON 168	

NUCLEAR CONSULTING SERVICES, INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

JOB No 107M625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION

ISSUE DATE 16 JAN 1989
ISSUE No 1

PAGE 10

RUN DATE 18 JAN 1989

EQUIP-ID	SERVICE LOCATION VENDOR	FLOW DIAG ELEM DIAG PIPE DIAG	SPEC No RANGE CHTL SIG	PO NUMBER PO DATE DEL DATE
NV -658	REGEN LOOP AIR PURGE E-7 SUPPLIED BY CONTRACTOR		0616-101-02 0616-602-01 0616-101-02 0616-601-01	NUCON 168 NUCON 168 NUCON 168
NV -659	NITROGEN SUPPLY D-5, 3" B2-P34 SUPPLIED BY CONTRACTOR		0616-101-03 0616-602-01	NUCON 168
PI -501	FILTER INLET PRESSURE F-1 Dwyer Instruments Inc.		0616-101-01 0616-601-01	616014 0-10" W.C. 12289 18 SEP 85 13 DEC 85
PI -502	FILTER OUTLET PRESSURE F-1 Dwyer Instruments Inc.		0616-101-01 0616-601-01	616014 0-10" W.C. 12289 18 SEP 85 13 DEC 85
PI -527	SUCTION PRESSURE C-2 INLET OYL-AIR EQUIPMENT CO.		0616-101-02 0616-602-01	616015 60-0-60" W.C. 12162 21 AUG 85 22 NOV 85
PI -529	E-3 DISCHARGE PRESSURE E-3 DISCH OYL-AIR EQUIPMENT CO.		0616-101-02 0616-602-01	616015 0-30 PSIG 12162 21 AUG 85 22 NOV 85
PI -537	DISCH. PRESSURE C-4/C-5 DISCH OYL-AIR EQUIPMENT CO.		0616-101-03 0616-602-01	616015 0-30 PSIG 12162 21 AUG 85 22 NOV 85
PI -540	DISCH. PRESSURE 8-2 DISCH OYL-AIR EQUIPMENT CO.		0616-101-03 0616-602-01	616015 0-5 PSIG 12162 21 AUG 85 22 NOV 85
PI -567	DISCH. PRESSURE C-3 DISCH OYL-AIR EQUIPMENT CO.		0616-101-02 0616-602-01	616015 0-30 PSIG 12162 21 AUG 85 22 NOV 85

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

JOB No 10TM625 ISSUE DATE 18 JAN 1989 PAGE 11
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION

RUN DATE 18 JAN 1989

EQUIP-ID	SERVICE LOCATION	FLOW DIAG	SPEC No	PO NUMBER
	VEHICLE	PIPE DIAG	RANGE	PO DATE
			CNTL SIG	DEL DATE
PI -580	NITROGEN PRESSURE D-5 OYL-AIR EQUIPMENT CO.		616015 0-160 PSIG	12162 21 AUG 85 22 NOV 85
PI -586	C.W. SUPPLY PRESS. E-10 OYL-AIR EQUIPMENT CO.		616015 0-100 PSIG	12162 21 AUG 85 22 NOV 85
PI -587	C.W. RETURN PRESS. E-10 OYL-AIR EQUIPMENT CO.		616015 0-100 PSIG	12162 21 AUG 85 22 NOV 85
PI -588	C.W. SUPPLY PRESS. E-3 OYL-AIR EQUIPMENT CO.		616015 0-100 PSIG	12162 21 AUG 85 22 NOV 85
PI -589	C.W. RETURN PRESS. E-3 OYL-AIR EQUIPMENT CO.		616015 0-100 PSIG	12162 21 AUG 85 22 NOV 85
PI -592	C.W. SUPPLY PRESS. E-1 OYL-AIR EQUIPMENT CO.		616015 0-100 PSIG	12162 21 AUG 85 22 NOV 85
PI -593	C.W. RETURN PRESS. E-1 OYL-AIR EQUIPMENT CO.		616015 0-100 PSIG	12162 21 AUG 85 22 NOV 85
PI -598	TURBOCOMPRESSOR LUBE OIL PRESSURE LUBE OIL SYSTEM OYL-AIR EQUIPMENT CO.		616015 0-100 PSIG	12162 21 AUG 85 22 NOV 85
PI -599	TURBOCOMPRESSOR LUBE OIL FILTER DISCH. PRESSURE LUBE OIL SYSTEM OYL-AIR EQUIPMENT CO.		616015 0-100 PSIG	12162 21 AUG 85 22 NOV 85
PI -600	TURBOCOMPRESSOR LUBE OIL SUPPLY PRESSURE LUBE OIL SYSTEM OYL-AIR EQUIPMENT CO.		616015 0-100 PSIG	12162 21 AUG 85 22 NOV 85

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

JOB No 10TH625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION

ISSUE DATE 18 JAN 1989
ISSUE No 1

PAGE 12

RUN DATE 18 JAN 1989

EQUIP-ID	SERVICE LOCATION	VENDOR	FLOW DIAG	ELEN DIAG	PIPE DIAG	SPEC No	RANGE	CNTL SIG	PO NUMBER	PO DATE	DEL DATE
PI -617	CO SAMPLE PRESSURE ANALYZER PANEL	FURNISHED WITH PANEL				616015	0-60 PSIG				
PI -629	HYDROCARBON SAMPLE PRESSURE ANALYZER PANEL	FURNISHED WITH PANEL				616015	0-60 PSIG				
PI -637	OXYGEN SAMPLE PRESSURE ANALYZER PANEL	FURNISHED WITH PANEL				616015	0-60 PSIG				
PI -649	C-2/C-3 PURGE AIR FILTER PRESSURE DROP					616067	0-1" W.C.		13724	17 OCT 86	
PI -650	C-6 SUCTION PRESSURE					616064	0-8" W.C.		13667	30 SEP 86	
PRV -505	PRESSURE RELIEF					616019			12436	25 OCT 85	
PRV -509	NITROGEN BLANKET SUPPLY					616020	2" W.C.		12436	25 OCT 85	
PRV -520	PRESSURE RELIEF					616019			13354	11 JUL 85	
PRV -548	PRESSURE RELIEF					616019			12290	18 SEP 85	
PRV -551	FV-532 CONTROL					616020			09 NOV 85		

NUCLEAR CONSULTING SERVICES, INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST		ISSUE DATE 18 JAN 1989		PAGE 13	
JOB No	10TH625	ISSUE No 1			
JOB DESCRIPTION	SOLVENT RECOVERY				
JOB CLIENT	3M COMPANY DRP DIVISION				
RUN DATE 18 JAN 1989					
EQUIP-ID		FLOW DIAG		PO NUMBER	
		ELEM DIAG		PO DATE	
		PIPE DIAG		DEL DATE	
		CMTL SIG			
SERVICE		SPEC No			
LOCATION		RANGE			
VENDOR					
PRV -597	TURBOCOMPRESSOR LUBE OIL PRESSURE CONTROL LUBE OIL SYSTEM A. H. EHRKE CO.	0616-101-05	616020	12300	25 SEP 85
		0616-602-05		23 NOV 85	
PRV -604	TURBOCOMPRESSOR LUBE OIL SUPPLY PRESSURE CONTROL LUBE OIL SYSTEM NIABCO EQUIPMENT CO.	0616-101-05	616019	12290	18 SEP 85
		0616-602-05		08 NOV 85	
PRV -620	CO SAMPLE ANALYZER PANEL FURNISHED WITH PANEL	0616-101-06	616063		
PRV -632	HYDROCARBON SAMPLE ANALYZER PANEL FURNISHED WITH PANEL	0616-101-07	616063		
PRV -635	OXYGEN SAMPLE ANALYZER PANEL FURNISHED WITH PANEL	0616-101-08	616063		
PRV -655	STEAM SUPPLY TO D-7 OIL HEATER D-7 COLECO INC.	0616-101-04	616020	13163	16 APR 86
		0616-602-01			
PS -594	NITROGEN PRESSURE D-5 RAWDON MYERS INC.	0616-101-02	616044	12450	21 OCT 85
		0616-601-01	0-100 PSIG	20 DEC 85	
PS -595	NITROGEN PRESSURE NITROGEN GENERATOR RAWDON MYERS INC.	0616-101-02	616044	12450	21 OCT 85
		0616-601-01	0-100 PSIG	20 DEC 85	
PS -596	INSTRUMENT AIR PRESSURE AIR SUPPLY HEADER RAWDON MYERS INC.	0616-101-01	616044	12450	21 OCT 85
			0-100 PSIG	20 DEC 85	
PS -618	CO SAMPLE PRESSURE ANALYZER PANEL FURNISHED WITH PANEL	0616-101-06	616058		
			0-50 PSIG		

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

MOLECULAR CONSULTING SERVICES, INC.									
PROJECT EQUIPMENT SYSTEM									
SYSTEM INSTRUMENT LIST									
JOB No 10TH625		ISSUE DATE 18 JAN 1989		PAGE 14					
JOB DESCRIPTION SOLVENT RECOVERY		ISSUE No 1							
JOB CLIENT 3M COMPANY DEP DIVISION									
*****									
EQUIP-ID	SERVICE	FLOW DIAG	SPEC No	PO NUMBER					
	LOCATION	ELEM DIAG	RANGE	PO DATE					
	VENDOR	PIPE DIAG	CHTL SIG	DEL DATE					
	*****								
PS -630	HYDROCARBON SAMPLE PRESSURE ANALYZER PANEL FURNISHED WITH PANEL	0616-101-07	616058 0-50 PSIG						
PS -638	OXYGEN SAMPLE PRESSURE ANALYZER PANEL FURNISHED WITH PANEL	0616-101-08	616058 0-50 PSIG						
PS -640	C-2\C-3 BYPASS C-2\C-3 BYPASS RAMDON MYERS INC.	0616-101-02 0616-602-02	616057 0-50 PSIG	12450 21 OCT 85 20 DEC 85					
PS -646	C-6 SUCTION PRESSURE C-6 INLET DUCT SIMCO CONTROLS	0616-101-02 0616-802-02	616066	13174 01 MAY 86					
PS -648	C-3 LUBE OIL PRESSURE C-3 COMPRESSOR FURNISHED WITH COMPRESSOR	0616-101-02							
PS -661	OIL PUMP P-3 AIR SUPPLY P-3 AIR SUPPLY RAMDON MYERS INC.	0616-101-05	616044 0-100 PSIG	13173 01 MAY 86					
PS -665	C-2 INLET PRESSURE C-2 INLET	616044 0616-101-02	4 0-80" W.C.D.						
PS -669	C-2 LUBE OIL PRESSURE C-2 COMPRESSOR	0616-101-02							
PT -504	C-1 SUCTION PRESSURE F-1 INLET M. L. JOHNSON CO.	0616-101-01 0616-601-01	616022	12122 05 AUG 85 30 SEP 85					
PT -521	MOL SIEVE PRESSURE E-8 DISCH. M. L. JOHNSON CO.	0616-101-02 0616-602-02	616023 0-20 PSIG	12122 05 AUG 85 30 SEP 85					

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

ISSUE DATE 18 JAN 1989
ISSUE No 1

JOB No 10TM625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION

PAGE 15

RUN DATE 18 JAN 1989

EQUIP-ID

SERVICE
LOCATION
VENDOR

FLOW DIAG
ELEN DIAG
PIPE DIAG

SPEC No
RANGE
CHTL SIG

PO NUMBER
PO DATE
DEL DATE

PT -533	NITROGEN SUPPLY E-2 INLET M. L. JOHNSON CO.	0616-101-02 0616-602-02	616024 0-10 PSIG	12122 05 AUG 85 30 SEP 85
PT -539	TURBOEXPANDER PRESSURE CONTROL M. L. JOHNSON CO.	0616-101-02 0616-602-01	616016 0-60 PSIG	13162 10 APR 86 10 JUN 86
PT -597	TURBOCOMPRESSOR LUBE OIL PRESSURE CONTROL C-4VC-5 INLET OYL-AIR EQUIPMENT CO.	0616-101-03 0616-602-01	616055 0-50 PSIG	12298 25 SEP 85 15 NOV 85
PT -667	NITROGEN PRESSURE D-5 NITROGEN RECEIVER	0616-101-02	0-100 PSIG.	
PV -521	MOL SIEVE PRESSURE E-8 DISCH. A. H. EHRKE CO.	0616-101-02 0616-602-02	616021 3-15 PSIG	12129 05 AUG 85 05 OCT 85
PV -533	NITROGEN SUPPLY E-3 A. H. EHRKE CO.	0616-101-02 0616-602-01	616021 3-15 PSIG	12129 05 AUG 85 05 AUG 85
PV -539	C-2VC-3 BYPASS C-2 INLET A. H. EHRKE CO.	0616-101-02 0616-602-02	616042 3-15 PSIG	12129 05 AUG 85 28 SEP 85
RD -101A	D-1 PRESSURE RELIEF D-1 HITT EQUIPMENT CO.	0616-101-01 0616-601-01	616025	13158 28 APR 86
RD -101B	D-1 VACUUM RELIEF D-1 HITT EQUIPMENT CO.	0616-101-01 0616-601-01	616025	13158 28 APR 86
RD -201A	D-2 PRESSURE RELIEF D-2 HITT EQUIPMENT CO.	0616-101-01 0616-601-01	616025	13158 28 APR 86

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

NUCLEAR CONSULTING SERVICES, INC.									
PROJECT EQUIPMENT SYSTEM									
SYSTEM INSTRUMENT LIST									
JOB No 10TH625		ISSUE DATE 18 JAN 1989		PAGE 16					
JOB DESCRIPTION SOLVENT RECOVERY		ISSUE No 1							
JOB CLIENT 3M COMPANY DRP DIVISION									
*****									
EQUIP-ID		SERVICE		FLOW DIAG		SPEC No		PO NUMBER	
		LOCATION		ELEN DIAG		RANGE		PO DATE	
		VENDOR		PIPE DIAG		CNTL SIG		DEL DATE	
*****									
RD -201B		D-2 VACCUUM RELIEF		0616-101-01		616025		13158	
		D-2						28 APR 86	
		HITT EQUIPMENT CO.		0616-601-01					
RD -301A		D-3 PRESSURE RELIEF		0616-101-01		616025		13158	
		D-3						28 APR 86	
		HITT EQUIPMENT CO.		0616-601-01					
RD -301B		D-3 VACCUUM RELIEF		0616-101-01		616025		13158	
		D-3						28 APR 86	
		HITT EQUIPMENT CO.		0616-601-01					
RDA -553		RUPTURE DISC ALARM SYSTEM		0616-101-01		616025		13158	
		INSTRUMENT PANEL						28 APR 85	
		HITT EQUIPMENT CO.							
RO -557		STEAM FLOW RESTRICTOR TO TRV-656		0616-101-04		DMQ 0616-803-01			
		D-7 STEAM SUPPLY		0616-602-01					
RV -101		PRESSURE RELIEF		0616-101-01		616033		13668	
		D-1						30 SEP 86	
		SCOTT EQUIPMENT		0616-601-01					
RV -201		D-2 PRESSURE RELIEF		0616-101-01		616033		13668	
		D-2						30 SEP 86	
		SCOTT EQUIPMENT		0616-601-01					
RV -301		D-3 PRESSURE RELIEF		0616-101-01		616033		13668	
		D-3						30 SEP 86	
		SCOTT EQUIPMENT		0616-601-01					
RV -671		PLANT STANDBY AIR PRESSURE SELECTOR		0616-101-05					
		AIR SUPPLY TO P-3							
SCR -522		E-9 TEMP. CONTROL		0616-101-02		616051		12017	
		PANEL						17 JUL 85	
		ANDERSON BOLDS INC.				4-20 mA		19 DEC 85	

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

JOB No 10TH625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION
ISSUE DATE 18 JAN 1989
ISSUE No 1
PAGE 17

RUN DATE 18 JAN 1989

EQUIP-10

SERVICE
LOCATION
VENDOR

FLOW DIAG
ELEN DIAG
PIPE DIAG
SPEC No
RANGE
CNTL SIG
PO NUMBER
PO DATE
DEL DATE

616026

0616-101-01

SV -508
FIRE CONTROL WATER
FIRE CONTROL DELUGE VALVE
FURNISHED W DELUGE VALVE

616026

0616-601-01

SV -550
FV-532 CONTROL
FV-532
SUPPLIED BY CONTRACTOR

616059

0616-602-02

SV -608
CO SPAN GAS
PANEL
FURNISHED WITH PANEL

616059

0616-101-06

SV -609
CO ZERO GAS
PANEL
FURNISHED WITH PANEL

13539
21 AUG 86

616059

0616-101-06

SV -610
CO SAMPLE D-1 (TOP)
PANEL
SIMCO CONTROLS

13539
21 AUG 86

616059

0616-101-06

SV -611
CO SAMPLE D-1 (BOTTOM)
PANEL
SIMCO CONTROLS

13539
21 AUG 86

616059

0616-101-06

SV -612
CO SAMPLE D-2 (TOP)
PANEL
SIMCO CONTROLS

13539
21 AUG 86

616059

0616-101-06

SV -613
CO SAMPLE D-2 (BOTTOM)
PANEL
SIMCO CONTROLS

13539
21 AUG 86

616059

0616-101-06

SV -614
CO SAMPLE D-3 (TOP)
PANEL
SIMCO CONTROLS

13539
21 AUG 86

616059

0616-101-06

SV -615
CO SAMPLE D-3 (BOTTOM)
PANEL
SIMCO CONTROLS

NUCLEAR CONSULTING SERVICES, INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

JOB No 10TH625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION

ISSUE DATE 18 JAN 1989
ISSUE No 1

PAGE 18

RUN DATE 18 JAN 1989

EQUIP-ID	SERVICE LOCATION	FLOW DIAG	ELEM DIAG	PIPE DIAG	SPEC No	RANGE	CHTL SIG	PO NUMBER	PO DATE	DEL DATE
SV -619	CO SAMPLE PANEL				0616-101-06			616059		
	FURNISHED WITH PANEL									
SV -622	HYDROCARBON SPAN GAS PANEL				0616-101-07			616059		
	FURNISHED WITH PANEL									
SV -623	THC ZERO GAS PANEL				0616-101-07			616059		
	FURNISHED WITH PANEL									
SV -624	SLA INLET HYDROCARBON SAMPLE PANEL				0616-101-07			616059	13539	21 AUG 86
	SINCO CONTROLS									
SV -625	D-1 HYDROCARBON SAMPLE PANEL				0616-101-07			616059	13539	21 AUG 86
	SINCO CONTROLS									
SV -626	D-2 HYDROCARBON SAMPLE PANEL				0616-101-07			616059	13539	21 AUG 86
	SINCO CONTROLS									
SV -627	D-3 HYDROCARBON SAMPLE PANEL				0616-101-07			616059	13539	21 AUG 86
	SINCO CONTROLS									
SV -631	HYDROCARBON SAMPLE PANEL				0616-101-07			616059		
	FURNISHED WITH PANEL									
SV -634	OXYGEN SAMPLE\SPAN PANEL				0616-101-08			616059		
	FURNISHED WITH PANEL									
SV -662	P-3 AIR SUPPLY				0616-101-05			616026		
	AIR SUPPLY TO P-3									
	SUPPLIED BY CONTRACTOR									

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

PROJECT EQUIPMENT SYSTEM						
SYSTEM INSTRUMENT LIST						
JOB No 10TM625		ISSUE DATE 18 JAN 1989	PAGE 19			
JOB DESCRIPTION SOLVENT RECOVERY		ISSUE No 1				
JOB CLIENT 3M COMPANY DRP DIVISION						
RUN DATE 18 JAN 1989						
EQUIP-10		FLOW DIAG	SPEC No	PO NUMBER		
SERVICE LOCATION VENDOR		ELEM DIAG	RANGE	PO DATE		
		PIPE DIAG	CNTL SIG	DEL DATE		
SV -663	ZERO GAS TO OXYGEN ANALYZER GAS ANALYZER PANEL FURNISHED WITH PANEL	0616-101-08	616059			
SV -664	SAMPLE GAS TO OXYGEN ANALYZER GAS ANALYZER PANEL FURNISHED WITH PANEL	0616-101-08	616059			
TA -643	C-2\C-3 MOTOR TEMPERATURE PANEL GILSON SALES INC.	0616-101-02	616065	12474 31 OCT 85 20 DEC 85		
TA -644	C-2\C-3 MOTOR TEMPERATURE PANEL GILSON SALES INC.	0616-101-02	616065	12474 31 OCT 85 20 DEC 85		
TA -645	C-2\C-3 MOTOR TEMPERATURE PANEL GILSON SALES INC.	0616-101-02	616065	12474 31 OCT 85 20 DEC 85		
TE -101	TEMPERATURE (TOP) D-1 ANDERSON-BOLDS INC.	0616-101-01	616027	12435 25 OCT 85 06 DEC 85		
TE -102	TEMPERATURE (BOTTOM) D-1 ANDERSON BOLD'S INC.	0616-101-01	616027	12435 25 OCT 85 06 DEC 85		
TE -201	TEMPERATURE (TOP) D-2 ANDERSON BOLD'S INC.	0616-101-01	616027	12435 25 OCT 85 06 DEC 85		
TE -202	TEMPERATURE (BOTTOM) D-2 ANDERSON BOLD'S INC.	0616-101-01	616027	12435 25 OCT 85 06 DEC 85		
TE -301	TEMPERATURE (TOP) D-3 ANDERSON BOLD'S INC.	0616-101-01	616027	12435 25 OCT 85 06 DEC 85		

NUCLEAR CONSULTING SERVICES, INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

JOB No 101M625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DEF DIVISION

ISSUE DATE 16 JAN 1989
ISSUE No 1

PAGE 20

RUN DATE 18 JAN 1989

EQUIP-ID
*****
SERVICE LOCATION
VENDOR
*****
FLOW DIAG
ELEN DIAG
PIPE DIAG
*****
SPEC No
RANGE
CHTL SIG
*****
PO NUMBER
PO DATE
DEL DATE
*****

TE -302	TEMPERATURE (BOTTOM) D-3 ANDERSON BOLDS INC.	0616-101-01 0616-601-01	616027	12435 25 OCT 85 06 DEC 85
TE -503	E-1 SLA INLET TEMPERATURE F-1 OUTLET ANDERSON BOLDS INC.	0616-101-01 0616-601-01	616027	12435 25 OCT 85 06 DEC 85
TE -506	SLA TEMPERATURE C-1 OUTLET ANDERSON BOLDS INC.	0616-101-01 0616-601-01	616027	12435 25 OCT 85 06 DEC 85
TE -510	REGEN GAS TEMP. E-6 OUTLET ANDERSON BOLDS INC.	0616-101-04 0616-601-02	616027	12435 25 OCT 85 06 DEC 85
TE -511	REGEN GAS RETURN TEMP. E-2 INLET ANDERSON BOLDS INC.	0616-101-02 0616-601-01	616027	12435 25 OCT 85 06 DEC 85
TE -514	SYSTEM LOW TEMP CONTROL C-4AC-5 ANDERSON BOLDS INC.	0616-101-03 0616-602-01	616027	12435 25 OCT 85 06 DEC 85
TE -514A	SYSTEM LOW TEMP. CONTROL E-4 ANDERSON BOLDS INC.	0616-101-03 0616-602-03	616027	13178 01 MAY 86
TE -516	E-8 ANDERSON BOLDS INC.	0616-101-02 0616-602-02	616027	12435 25 OCT 85 06 DEC 85
TE -518	MOL. SIEVE TEMP. D-4 ANDERSON BOLDS INC.	0616-101-02 0616-602-02	616027	12435 25 OCT 85 06 DEC 85
TE -519	C.W. TEMP E-3 COLESCO INC.	0616-101-04 0616-602-01	616041	12127 05 AUG 85 07 OCT 85

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

PAGE 21

ISSUE DATE 18 JAN 1989

ISSUE No 1

JOB No 10TH625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DEP DIVISION

RUN DATE 18 JAN 1989

EQUIP-ID	SERVICE LOCATION VEHICLE	FLOW DIAG ELEM DIAG PIPE DIAG	SPEC No RANGE CHTL SIG	PO NUMBER PO DATE DEL DATE
TE -522	E-9 TEMP. CONTROL E-9 ANDERSON BOLD'S INC.	0616-101-02 0616-602-02	616027	12435 25 OCT 85 06 DEC 85
TE -523	E-7 DISCH. TEMP. E-7 DISCH. ANDERSON BOLD'S INC.	0616-101-04 0616-602-01	616027	12435 25 OCT 85 06 DEC 85
TE -538	S-2 DISCH. TEMP. S-2 DISCH. ANDERSON BOLD'S INC.	0616-101-03 0616-602-02	616027	12435 25 OCT 85 06 DEC 85
TE -552	E-10 TEMP. CONTROL E-10 C.W. DISCH. ANDERSON BOLD'S INC.	0616-101-04 0616-601-02	616027	12435 25 OCT 85 06 DEC 85
TE -656	LUBE OIL HEATER COOLER LUBE OIL SYSTEM COLESCO INC.	0616-101-04 0616-602-01	616029	13163 16 APR 86
TI -101	TEMPERATURE (TOP) D-1 COLESCO INC.	0616-101-01 0616-601-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -102	TEMPERATURE (MIDDLE) D-1 COLESCO INC.	0616-101-01 0616-601-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -103	TEMPERATURE (BOTTOM) D-1 COLESCO INC.	0616-101-01 0616-601-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -201	TEMPERATURE (TOP) D-2 COLESCO INC.	0616-101-01 0616-601-01	616028 50-500 DEG. F.	12431 18 NOV 85 15 NOV 85
TI -202	TEMPERATURE (MIDDLE) D-2 COLESCO INC.	0616-101-01 0616-601-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85

NUCLEAR CONSULTING SERVICES, INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

ISSUE DATE 18 JAN 1989 PAGE 22
ISSUE No 1

JOB No 10TH625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION

RUN DATE 18 JAN 1989

EQUIP-ID

SERVICE
LOCATION
VENDOR

FLOW DIAG
ELEM DIAG
PIPE DIAG

SPEC No
RANGE
CHTL SIG

PO NUMBER
PO DATE
DEL DATE

TI -203	TEMPERATURE (BOTTOM) D-2 COLESCO INC.	0616-101-01 0616-601-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -301	TEMPERATURE (TOP) D-3 COLESCO INC.	0616-101-01 0616-601-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -302	TEMPERATURE (MIDDLE) D-3 COLESCO INC.	0616-101-01 0616-601-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -303	TEMPERATURE (BOTTOM) D-3 COLESCO INC.	0616-101-01 0616-601-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -513	REGEN GAS PREHEATER DISCH. TEMP. E-2 OUTLET COLESCO INC.	0616-101-02 0616-601-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -515	E-8 DISCH. TEMP. E-8 COLESCO INC.	0616-101-02 0616-602-01	616028 0-200 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -524	SHELL SIDE DISCH. TEMP. E-2 COLESCO INC.	0616-101-02 0616-602-01	616028 0-200 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -526	E-5 TUBESIDE DISCH. TEMP. E-5 COLESCO INC.	0616-101-03 0616-602-01	616028 0-200 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -531	E-3 DISCH. GAS TEMP. E-3 DISCH. COLESCO INC.	0616-101-02 0616-602-01	616028 0-200 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -535	E-4 DISCH TEMP. E-4 DISCH. COLESCO INC.	0616-101-03 0616-602-01	616028 0-200 DEG. F.	12431 18 OCT 85 15 NOV 85

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

JOB No 107625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION

ISSUE DATE 18 JAN 1989
ISSUE No 1

PAGE 23

RUN DATE 18 JAN 1989

SERVICE LOCATION VENDOR	FLOW DIAG ELEN DIAG PIPE DIAG	SPEC No RANGE	PO NUMBER PO DATE
*****	*****	*****	*****
*****	*****	*****	*****
*****	*****	*****	*****

TI -536	E-4 INLET TEMP. E-4 INLET COLESCO INC.	0616-101-03 0616-602-01	616028 0-200 DEG. F.	12431 18 OCT 85 15 NOV 85

TI -542	S-1 INLET TEMP. S-1 INLET COLESCO INC.	0616-101-03 0616-602-02	616028 -40-120 DEG. F.	12431 18 OCT 85 15 NOV 85

TI -558	TUBESIDE DISCH TEMP. E-6 COLESCO INC.	0616-101-02 0616-601-02	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85

TI -559	C.W. SUPPLY TEMP. E-10 COLESCO INC.	0616-101-04 0616-601-02	616028 0-200 DEG. F.	12431 18 OCT 85 15 NOV 85

TI -560	STEAM INLET TEMP. E-6 COLESCO INC.	0616-101-04	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85

TI -561	C.W. RETURN TEMP. E-10 COLESCO INC.	0616-101-04 0616-601-02	616028 0-200 DEG. F.	12431 18 OCT 85 15 NOV 85

TI -562	C.W. RETURN TEMP. E-8 COLESCO INC.	0616-101-04 0616-602-02	616028 0-200 DEG. F.	12431 18 OCT 85 15 NOV 85

TI -563	C.W. SUPPLY TEMP. E-8 COLESCO INC.	0616-101-04 0616-602-02	616028 0-200 DEG. F.	12431 18 OCT 85 15 NOV 85

TI -564	SHELL SIDE INLET TEMP. E-2 COLESCO INC.	0616-101-02 0616-601-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85

TI -565	TUBESIDE INLET TEMP. E-2 COLESCO INC.	0616-101-02 0616-602-01	616028 0-200 DEG. F.	12431 18 OCT 85 15 NOV 85

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

JOB No 10TM625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION

ISSUE DATE 18 JAN 1989
ISSUE No 1

10TM625
SOLVENT RECOVERY
3M COMPANY DRP DIVISION

RUN DATE 18 JAN 1989

EQUIP-ID	SERVICE LOCATION VENDOR	FLOW DIAG ELEM DIAG PIPE DIAG	SPEC No RANGE CNTRL SIG	PO NUMBER PO DATE DEL DATE
TI -568	DISCH TEMP. C-3 DISCH. COLESCO INC.	0616-101-02 0616-602-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -569	C.W. RETURN TEMP. E-3 COLESCO INC.	0616-101-04 0616-602-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -570	C.W. SUPPLY TEMP. E-13 COLESCO INC.	0616-101-04 0616-602-01	616028 0-200 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -572	TUBESIDE INLET TEMP. E-5 COLESCO INC.	0616-101-03 0616-602-01	616028 -100-100 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -573	C.W. SUPPLY TEMP. E-4 COLESCO INC.	0616-101-04 0616-602-01	616028 0-200 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -574	C.W. RETURN TEMP. E-4 COLESCO INC.	0616-101-04 0616-602-01	616028 0-200 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -575	TUBESIDE INLET TEMP. E-7 COLESCO INC.	0616-101-02 0616-602-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -576	STEAM INLET TEMP. E-7 COLESCO INC.	0616-101-04 0616-602-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -577	TUBESIDE DISCH. TEMP. E-7 COLESCO INC.	0616-101-02 0616-602-01	616028 50-500 DEG. F.	12431 18 OCT 85 15 NOV 85
TI -578	INLET TEMP. D-4 COLESCO INC.	0616-101-02 0616-602-01	616028 50-500 DEG. F.	14321 18 OCT 85 15 NOV 85

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSTRUMENT LIST

PAGE 25

ISSUE DATE 18 JAN 1989
ISSUE No 1

JOB No 10TH625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DEP DIVISION

RUN DATE 18 JAN 1989

*****
EQUIP-ID
*****
SERVICE
LOCATION
VENDOR
*****
FLOW DIAG
ELEM DIAG
PIPE DIAG
*****
SPEC NO
RANGE
CNTRL SIG
*****
PO NUMBER
PO DATE
DEL DATE
*****

TI -579 TUBESIDE INLET TEMP.
E-8
COLESCO INC.
616028
50-500 DEG. F.
12431
18 OCT 85
15 NOV 85

TI -590 C.V. SUPPLY
E-1
COLESCO INC.
616028
0-200 DEG. F.
12431
18 OCT 85
15 NOV 85

TI -591 C.V. RETURN TEMP.
E-1
COLESCO INC.
616028
0-200 DEG. F.
12431
18 OCT 85
15 NOV 85

TI -606 TURBOCOMPRESSOR LUBE OIL TEMP
LUBE OIL SYSTEM
COLESCO INC.
616028
0-200 DEG. F.
12431
18 OCT 85
15 NOV 85

TI -607 TURBOCOMPRESSOR LUBE OIL RECEIVER TEMP.
D-7
COLESCO INC.
616028
50-500 DEG. F.
12431
18 OCT 85
15 NOV 85

TI -608 C-2 DISCHARGE TEMP
C-2 DISCHARGE
616-101-02

TI -609 C-3 INLET TEMP
C-3 INLET
616-101-02

TRV -656 LUBE OIL HEATER COOLER
LUBE OIL SYSTEM
COLESCO INC.
616029
13163
16 APR 86

TS -603 TURBOCOMPRESSOR LUBE OIL TEMP.
D-7
RAUDON MYERS INC.
616056
100-250 DEG. F.
12450
21 OCT 85
20 DEC 85

TS -647 C-3 LUBE OIL TEMPERATURE
C-3 COMPRESSOR
FURNISHED WITH COMPRESSOR
616-101-02

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

PROJECT EQUIPMENT SYSTEM									
SYSTEM INSTRUMENT LIST									
JOB No	10TM625		ISSUE DATE 18 JAN 1989		PAGE 26				
JOB DESCRIPTION	SOLVENT RECOVERY		ISSUE No 1						
JOB CLIENT	3M COMPANY DRP DIVISION								
*****									
EQUIP-ID	SERVICE LOCATION VENDOR	FLOW DIAG ELEM DIAG PIPE DIAG	SPEC No RANGE CNTRL SIG	PO NUMBER PO DATE DEL DATE					
*****									
TS -666	C-3 DISCHARGE TEMPERATURE C-3 DISCHARGE	0616-101-02	616058 100-400 DEG F.						
TS -670	C-2 LUBE OIL TEMPERATURE C-2 COMPRESSOR	0616-101-02							
*****									
TT -510	REGEN GAS E-6 OUTLET M. L. JOHNSON CO.	0616-101-04 0616-601-02	616036 0-500 DEG. F.	12122 05 AUG 85 30 SEP 85					
TT -514	SYSTEM LOW TEMP. CONTROL C-4XC-5 M. L. JOHNSON CO.	0616-101-03 0616-602-01	616039 -100-100 DEG F.	12122 05 AUG 85 30 SEP 85					
TT -514A	SYSTEM LOW TEMP. CONTROL E-4 M. L. JOHNSON CO.	0616-101-02 0616-602-03	616034 0-500 DEG. F.	13162 10 APR 86					
TT -522	E-9 TEMP. CONTROL D-4 M. L. JOHNSON CO.	0616-101-02 0616-602-02	616037 0-500 DEG. F.	12122 05 AUG 85 30 SEP 85					
TT -523	E-7 DISCH. E-7 DISCH. M. L. JOHNSON CO.	0616-101-04 0616-602-01	616038 0-500 DEG. F.	12122 05 AUG 85 30 SEP 85					
TT -552	E-10 TEMP. CONTROL E-10 C.W. DISCH. M. L. JOHNSON CO.	0616-101-04 0616-601-02	616040 0-500 DEG. F.	12122 05 AUG 85 30 SEP 85					
TV -510	REGEN GAS TEMP. E-6 STEAM INLET A. H. EHRKE CO.	0616-101-04 0616-601-02	616042 3-15 PSIG	12129 05 AUG 85 05 OCT 85					
TV -514	SYSTEM LOW TEMP. CONTROL E-5 A. E. EHRKE & CO.	0616-101-04 0616-602-01	616042 3-15 PSIG	13161 25 APR 86					

NUCLEAR CONSULTING SERVICES INC.
PROJECT EQUIPMENT SYSTEM

SYSTEM INSURMENT LIST

ISSUE DATE 18 JAN 1989 PAGE 27
ISSUE No 1

JOB No 10TH625
JOB DESCRIPTION SOLVENT RECOVERY
JOB CLIENT 3M COMPANY DRP DIVISION

RUN DATE 18 JAN 1989

EQUIP-10

SERVICE
LOCATION
VENDOR

FLOW DIAG
ELEN DIAG
PIPE DIAG

SPEC No
RANGE
CNTRL SIG

PO NUMBER
PO DATE
DEL DATE

TV -519 COOLING WATER TEMP.
E-3

COLESCO INC.

616041

0616-101-04

12127

05 AUG 85
07 OCT 85

TV -523 E-7 TEMP. CONTROL
E-7
A. E. EHRKE & CO.

616042

0616-101-04

12129

13 AUG 85
05 OCT 85

TV -552 E-10 TEMP. CONTROL
E-10 C.W. SUPPLY
A. H. EHRKE & CO.

616042

0616-101-04

12225

04 SEP 85
07 DEC 85

VA -504 - SLA PRESSURE CONTROL
C-1 BLOWER

616043

0616-101-01

3-15 PSIG

3-15 PSIG

FURNISHED WITH ITEM C-1

APPENDIX B

Mobile Brayton cycle heat pump system:

Mobile solvent recovery system is based on BHP solvent recovery process using a free spindle turbo compressor. This system was designed, fabricated, and tested by Nucon under funding provided by the DOE, EPRI, 3M, Nucon, and SCE.

This appendix contains four P&ID drawings, two piping equipment diagrams, and a detailed component description.

Nuclear Consulting Services, Inc.

SYSTEM DESIGN DESCRIPTION

For

SMALL MOBILE VOC RECOVERY UNIT WITH BHP

For

U.S. Department of Energy
Office of Industrial Programs Project
Transportable Small Scale VOC Recovery System

Distribution:

SCE: Roger Sung

EPRI: Ammi Amarnath

3M: Nirmal Jain
Robert Nelson

NUCON: Master File - 10DE771
J. L. Kovach
R. S. Kingsley
J. C. Enneking
M. N. Magnus
J. M. Stephens
W. P. Freeman

NUCON 10DE771/03 Rev. 2

NUCON 10DE771/03

PREPARED BY

REVIEWED BY

QA APPROVAL

Original
Issue

23 Aug., 89

M.N. Magnus

R.S. Kingsley
R.S. Kingsley

S.A. Fratianne
S.A. Fratianne

Revision 1

19 Sept., 89

M.N. Magnus

R.S. Kingsley
R.S. Kingsley

S.A. Fratianne
S.A. Fratianne

PREPARED BY

REVIEWED BY

Revision 2
20 Dec., 89

M.N. Magnus

J.M. Stephens
J.M. Stephens

APPROVAL - QA

APPROVAL - MGMT.

S.A. Fratianne

R.S. Kingsley
R.S. Kingsley

SYSTEM DESIGN DESCRIPTION
For
SMALL MOBILE VOC RECOVERY UNIT WITH BHP

	Page
1.0 Summary	1
2.0 Functions	1
3.0 Performance Requirements	4
4.0 Modes of Operation	12
5.0 Codes, Standards, Regulatory Requirements	15
6.0 Design Conditions	16
7.0 Environmental Conditions	17
8.0 Interface Requirements	18
9.0 Material Requirements	18
10.0 Mechanical Requirements	19
11.0 Structural Requirements	19
12.0 Electrical Requirements	19
13.0 Failure Effects Requirements	20
14.0 Accessibility, Maintenance, Repair and In-Service Inspection Requirements	20
15.0 Personnel Requirements	20
16.0 Transportability Requirements	20
17.0 Fire Protection Requirements	20

1.0 SUMMARY

1.1 General

A transportable solvent recovery unit using the Brayton Cycle Heat Pump (BCHP) technology is to be constructed for plant site solvent recovery testing in the Southern California Edison sector of the state. The existing 250 CFM VOC recovery pilot plant built for 3M Co. is to be converted from 2-stage conventional refrigeration to BCHP cryogenic refrigeration for solvent recovery.

- 1.2 The 250 CFM VOC solvent recovery pilot plant built by NUCON (and now owned by NUCON) is to be returned to Columbus for refitting.
- 1.3 The system will be designed for continuous operation of adsorption of solvents from an air stream. The regeneration of the off-line carbon bed is performed automatically in a semi-continuous operation.
- 1.4 The adsorption media will be two types:
  - 1) VOC-type activated carbon selected for this process on the basis of laboratory studies,
  - 2) A noncarbonaceous , highly active adsorbent with hydrophobic properties meeting the requirements for gas phase operation.
- 1.5 The pilot plant will be mounted on a commercial trailer with standard fittings for attachment to a tractor for hauling.
- 1.6 The fittings for connection to client piping and ductwork will meet industrial standards for the service.
- 1.7 Instrumentation will be provided for both on-site readout (by computer) and off-site readout (at NUCON).

2.0 FUNCTIONS

The Small Mobile VOC Recovery Unit with BCHP will have the following principal components which have the identified functions:

2.1 Carbon Adsorber Vessels (D-1, D-2)

A dual bed carbon adsorption system will provide continuous operation capability for demonstration purposes. This is achieved by adsorbing on one bed while the second bed is isolated from the adsorption process and is regenerated with hot nitrogen. The beds are switched from the adsorb mode to regeneration mode by the pre-programed PLC (Programmable Logic Controller).

2.2 SLA Cooler (E-1)

Cools the incoming Solvent Laden Air (SLA) stream to ambient temperature.

2.3 Blower (C-1)

A forced draft fan to drive the Solvent Laden Air (SLA) through the carbon bed and out the exhaust stack.

2.4 Roughing Compressor (C-2)

Provides the motive force for the closed loop nitrogen circulation for regeneration of the carbon beds.

2.5 Mol Sieve Bed (D-3)

Provides for removal of moisture from the solvent-water vapor regen gas stream prior to the low temperature refrigeration step.

2.6 Turbo Compressor/Expander (C-3)

Provides for cryogenic cooling of the regen gas stream which results in direct condensation of the solvents stripped from the carbon bed.

2.7 Refrigeration Condenser (E-5)

A gas-to-gas heat exchanger for subcooling and partial condensing of solvents in the regen gas stream. This heat exchange is an energy saving (i.e., recuperation) process.

2.8 Regen Gas Preheater (E-2)

A gas-to-gas heat exchanger that provides heat (energy) recovery during regeneration of the carbon bed.

2.9 Turbo Compressor After Cooler (E-4)

Removes the heat of compression developed by the turbo compressor (C-3) by water cooling. It also serves as a means of temperature control of the turbo expander outlet gas.

2.10 Separators (S-1, S-2)

Provide phase separation between condensed (liquid) solvent and the regen gas stream.

2.11 Regen Gas Heater (E-6)

Raises the temperature of the regen gas to the desired operating level for solvent stripping.

2.12 Mol Sieve Heater (E-8)

Heats the regen gas to the operating temperature required for mol sieve regeneration (moisture stripping).

2.13 Compressor After Cooler (E-3)

Removes the heat of compression developed by the Roughing Compressor (C-2).

2.14 Gas Cooler (E-7)

Provides cooling of the regen gas (to ambient temperature) during the carbon bed cool-down cycle.

2.15 Gas Cooler (E-9)

Provides cooling of the mol sieve regen gas (to ambient temperature) during the mol sieve moisture stripping operation.

2.16 Gas Stream Analyzers (GA-509, GA-519, GA-521)

2.16.1 GA-509 Measures the solvent concentrations in the adsorption bed inlet SLA (Solvent Laden Air) stream and the adsorption bed exhaust air stream.

2.16.2 GA-519 Measures the dew point temperatures of the regen gas stream.

2.16.3 GA-521 Measures the oxygen concentration of the regen gas stream.

2.17 Instruments and Controls

The Small Mobile VOC Recovery Unit with BCHP will contain sufficient instrumentation and control to:

- safely operate the system
- monitor and control all process dependent variables
- store process independent and dependent variables
- transmit process values to Columbus
- monitor and store all process variables required to specify and design a full scale VOC recovery system with a BCHP.
- meter process utility consumption (i.e., power and cooling water)

3.0 PERFORMANCE REQUIREMENTS OF MAJOR EQUIPMENT

3.1 Adsorber Vessels (D-1, D-2)

Twenty four (24") inch diameter vessels designed for airflow of 250 CFM at a velocity of 76 FPM. The height of the bed is 30 inches.

3.2 Adsorber Beds

Each adsorber will have a 30 inch deep bed (7.9 cubic feet). Adsorbant described as follows:

- 1) One bed to be a selected grade of activated carbon.
- 2) The second bed will be a hydrophobic noncarbonaceous adsorbent (should it become available). Otherwise, both beds will have the same carbon.

3.3 SLA Cooler (E-1)

A finned-tube water cooled exchanger capable of cooling the incoming gas stream from 300°F to 90°F using 80°F cooling water.

3.4 SLA Blower (C-1)

The blower is rated for airflow at 250 CFM, 90°F, 21 inch static pressure. The drive is a 3 HP, 3,500 RPM, 460V, 3 PH, 60 Hz motor.

3.5 Roughing Compressor (C-2)

The compressor is a positive displacement type rated at 150 SCFM, 14.6 psi pressure rise, equipped with inlet and outlet silencers for sound attenuation, and speed control using sheaves. The drive is a 20 HP, 1800 RPM, 460V, 3 PH, 60 Hz motor. The motor enclosure is TEFC.

3.6 Mol Sieve Vessel (D-3) and Mol Sieve Bed

---+
[2]
---+
The mol sieve vessel is 24 inches diameter by 48 inches high. The mol sieve bed is 24 inches diameter by 24 inches deep and contains 280 pounds of Type 3A molecular sieve. The mol sieve is capable of adsorbing 28 pounds of water. The dew point of the regen gas will be reduced to -20°F or lower.

3.7 Turbo Compressor/Expander (C-3)

The turbo compressor/expander will provide cryogenic refrigeration. The regen gas flow consists of 639 lb/hr. of nitrogen and 29 lb/hr. (average) of solvent. The expander outlet gas temperature will be at -80°F or lower. Approximately one-half of the solvent will condense in the interstage refrigeration condenser (E-5) and the balance condenses in the expander outlet (Note: condensation is not complete and will be limited by the partial pressure of the solvent at the condensing temperature).

++
|2|
++

3.8 Refrigeration Condenser (E-5)

In this gas-to-gas exchanger, the turbo compressor discharge gas will be cooled to zero (0°) degrees F and the expander discharge gas temperature rises from -80°F to about 40°F. More than one-half of the solvent will condense under these conditions.

3.9 Regen Gas Preheater (E-2)

This gas-to-gas exchanger recovers the heat from the solvent laden regen gas leaving the adsorber. The exhaust gas is cooled from 350°F (max.) to 100°F. The stripping gas will be heated to about 300°F (max.).

3.10 Turbo Compressor After Cooler (E-4)

The regen gas temperature at the discharge of the compressor is expected to be 270°F. The after cooler (E-4) will cool the gas to 100°F using 80°F cooling water.

3.11 Separators (S-1, S-2)

The separator S-1 provides phase separation between a 639 lb/hr. N₂ gas stream up to 30 lb/hr. entrained liquid. The operating conditions are: pressure: 25 psig, temperature: 0°F.

++
|2|
++

Separator S-2 performs the same function as S-1. The gas flow is 639 lb/hr. and entrained liquid capacity of 30 lb/hr. The operating conditions are: pressure: 2 psig, temperature: -80°F.

3.12 Regen Gas Heater (E-6)

Provides up to 45,000 BTU/hr. to heat the regen gas to the operating temperature of 360°F. The heater is rated at 20 KW, 460V, 3 PH, 60 Hz. The expected power usage will be 10 to 15 KW.

3.13 Mol Sieve Heater (E-8)

Heats the regen gas stream to 450°F for regeneration of the mol sieve. The required heating capacity is 17 KW. The heater will be sized for 25 KW.

3.14 Roughing Compressor After Cooler (E-3)

Cools the compressed regen gas stream from 279°F to 100°F. The cooling water flow will be 4.0 gpm at 15°F temperature rise.

3.15 Gas Cooler (E-7)

Cools the 150 SCFM regen gas stream from 350°F (max.) to 100°F during the carbon bed cooldown. The cooling water flow will be 5.3 gpm at 15°F temperature rise.

3.16 Gas Cooler (E-9)

Cools the 150 SCFM mol sieve regen gas from 450°F to 100°F. The cooling water flow will be 7.5 gpm.

3.17 Gas Stream Analyzers (GA-509, GA-519, GA-521)

3.17.1 GA-509 VOC Analyzer

Beckman Model 400A Flame Ionization Detector (FID).

Measures the solvent concentration in the adsorber inlet SLA stream (as PPM (v) methane) in the range of 0-10,000 ppm and adsorber exhaust air stream in the range of 0-100 ppm(v). The automatic range change device provides options for 7 ranges for more accurate measurements: 0-10 ppm, 0-25 ppm, 0-100 ppm, 0-250 ppm, 0-1000 ppm, 0-2500 ppm and 0-10,000 ppm.

3.17.2 GA-519 Moisture Analyzer

Ondyne Model 1441 analyzer with Model DY-132 moisture probes and Model 101-S flow cell.

Moisture analyzer measures the dew point of the regen gas stream during the moisture stripping step. At a preset dew point (-20 to -25°F) the regen gas flow is redirected out of the mol sieve bed and into the turbo compressor for solvent stripping.

Range: -100°F to +80°F dew point.

3.17.3 GA-521 Oxygen Analyzer

Beckman Model 755 Oxygen Analyzer.

Measures the level of oxygen in the regen gas stream. The oxygen is purged from the system to a level of 5% (max.) before starting the stripping of moisture and solvents.

Range: 0-25%

3.18 Instruments and Controls

3.18.1 Computer

The computer provides the interface between the plant operator and all of the system control devices which are in the computer or are mounted on the pilot plant. Feedback information from the process operating variables is provided by the computer.

The computer is an IBM PC/AT (or equivalent) and is used to run "The FIX"™ software and serves as the operator interface to the system in-place of a control panel. Operating data collected is stored in the computer for future review. The computer also contains software for programming the programmable logic controller.

3.18.2 Programmable Logic Controller

The Programmable Logic Controller (PLC) is a Modicon 984-680 with all necessary input and output modules (analog and digital), and logic software to control the operation of the pilot plant.

3.18.3 Computer Software

3.18.3.1 "The FIX"™ Software

"The FIX"™ is an integrated software package which "talks" to the PLC, and serves as the control panel for the pilot plant. Various displays are provided which allow the operator to start-up and shutdown the system, view real-time process conditions, open and close valves, start and stop equipment, and view previous historical operating data. Alarms and various other status messages are output to a printer. Alarms and operating data are also stored on the computer's disk for recall and review at a later date.

"The FIX" is a Registered Trademark of Intellution, Inc.

"IBM PC/AT" is a Registered Trademark of International Business Machines, Inc.

3.18.3.2 PLC Programming Software

This software resides in the computer and provides the means for entering and de-bugging the software in the PLC. It provides on-line access to, and full hard-copy documentation of, the software.

3.19 Major Instruments

- DPI-101 Panel-mounted. Measures the pressure drop across the D-1 carbon bed.
Range: 0-15" w.c.
- DPI-201 Panel-mounted. Measures the pressure drop across the D-2 carbon bed.
Range: 0-15" w.c.
- DPI-502 Panel-mounted. Measures the pressure drop across the SLA fan C-1.
Range: 0-30" w.c.
- DPI-512 Field-mounted. Measures the pressure drop across the roughing compressor inlet strainer.
Range: 0-2" w.c.

- DPI-537 Field-mounted. Measures the pressure drop across the turbo compressor inlet filter F-4.
Range: 0-2" w.c.
- LT-543 Level transmitter for separator S-1.
Level control is in the computer.
Range: 0-12" w.c.
- LT-549 Level transmitter for separator S-2.
Level control is in the computer.
Range: 0-12" w.c.
- DPT-538 Turbo compressor differential. Pressure transmitter.
Range: 0-30 psid
- PT-532 Regen System pressure transmitter for pressure control of the regen loop.
Range: 0-3 psid
- PT-547 Turbo expander discharge pressure transmitter.
Range: 0-6 psig
- SCR-529 Power controller for both the mol sieve regen gas heater E-8 and the solvent strip regen gas heater E-6. These two process functions take place sequentially. The electrical rating of the SCR is 30 KW, 480V, 3 PH, 60 Hz.
(Note: This SCR was with the original pilot plant.)
- PT-514 Roughing compressor discharge pressure transmitter. A high pressure reading is a signal for compressor shutdown.
Range: 0-25 psia
- PT-539 Turbo compressor discharge pressure transmitter. A high pressure indicates plugging (freezing) of downstream heat exchangers.
Range: 0-30 psig

- TE-546 and TE-546A Turbo expander discharge temperature. The millivolt signal is transmitted directly to the PC. TE-546 and TE-546A are sensing points for cascade temperature control of the expander outlet temperature. The signals from TE-546 and TE-546A are transmitted to the controllers in the computer. The output signal from the computer positions the valve TV-546.
Operating Range: TE-546: -80°F to 0°F
TE-546A: 0°F to +120°F
- TV-546 Control of cooling water flow for exchanger E-4; directly controls the turbo expander inlet temperature.
Operating Range: 0-10 GPM

3.20 Instruments with Inputs to the Computer

+--+
|2|
+--+

Instruments are listed in groups according to process functions related to adsorption and regeneration of the carbon beds and the mol sieve bed as well as product recovery, refer to the P&IDs: 0771-101-01, -101-02 and -101-03.

<u>Instrument Number</u>	<u>Location</u>	<u>Function</u>
FE-504	Upstream C-1	Inlet SLA Stream Flow - CFM
FT-504	At FE-504	Transmits SLA Flow Signal
PT-566	Upstream C-1	Inlet SLA Stream Pressure/Transmitter
TE-501	Upstream C-1	Inlet SLA Stream Temperature
TE-101	Inside D-1	Carbon Bed Inlet Temperature
TE-106	Inside D-1	Carbon Bed Outlet Temperature
TE-201	Inside D-2	Carbon Bed Inlet Temperature
TE-206	Inside D-2	Carbon Bed Outlet Temperature
FE-561	Upstream E-2	Regen Gas Stream Flow - CFM

<u>Instrument Number</u>	<u>Location</u>	<u>Function</u>
FT-561	At FE-561	Transmits Regen Gas Flow Signal
PT-562	Upstream E-2	Regen Gas Stream Pressure/Transmitter
TE-508	Upstream E-2	Regen Gas Stream Temperature
PT-514	Downstream C-2	Compressor Discharge Pressure
TS-516	Downstream C-2	Over Pressure Signal
TE-554	Downstream E-3	Regen Gas Temperature
SV-524	Downstream E-3	O ₂ Purge Control
PT-532	Downstream E-5 or E-9	Regen Gas System Purge Pressure Control
PV-532	Nitrogen Line	Controls N ₂ Make Up for System Low Pressure
TE-529	Inlet to D-3	Temperature Signal to SCR-529 -Mol Sieve Regen Heater Control
TE-530	Outlet from D-3	Mol Sieve Outlet Gas Temperature
DPT-538	Turbo Comp. C-3	Pressure Rise Across the Compressor
PT-539	Downstream C-3	Compressor Discharge Pressure
DPT-545	Turbo Expander C-3	Pressure Drop Across the Expander
TE-541	Downstream E-5	Expander Inlet Temperature
TE-546A	Downstream E-4	Expander Temperature Control
TE-546	Downstream C-3	Expander Outlet Temperature
LT-543	At S-1	Level Control

<u>Instrument Number</u>	<u>Location</u>	<u>Function</u>
LT-549	At S-2	Level Control
FE-544	At S-1	Condensed Product Flow Measurement
FV-606	At S-1	Condensed Product Separating Valve
FE-550	At S-2	Condensed Product Flow Measurement
FV-607	At S-2	Condensed Product Separating Valve

4.0 MODES OF OPERATION

4.1 General

The pilot plant is intended to demonstrate the capability of the Brayton Cycle Heat Pump (BCHP) for the recovery of VOC's from exhaust air streams. Two modes of operation have been incorporated into the system for this purpose - (1) Carbon adsorption with BCHP regeneration (BRAYSORB), and (2) Direct condensation of solvents from the SLA stream (BRAYCYCLE).

4.2 BRAYSORB Mode

Solvent in the exhaust air (SLA) stream is concentrated by adsorption on carbon and recovered by regeneration of the saturated bed using the Brayton Cycle Heat Pump technology. The two bed arrangement provides for continuous adsorption of solvents. The regeneration cycle consists of four principal steps occurring sequentially:

- 1) Purging of oxygen from the regen loop.
- 2) Water stripping of the adsorbent and selective adsorption of moisture on the mol sieve.
- 3) VOC stripping and recovery.

- 4) Mol sieve water stripping and readsorption of the water on the adsorbent.

The regeneration cycle is semi continuous. When the regenerating cycle has been completed (step 4 above), the operation is shutdown and the regenerated bed goes on standby status.

4.2.1 Normal Operation (Adsorption and Regeneration)

The pilot plant operates in a completely automatic mode and is not time limited. Once the utilities are operational, the operator initiates the START function and from there on, the PLC and the computer will execute the programed commands for all functions. Shutdown of the system is executed by the operator command.

4.2.2 Emergency Operation

The adsorption cycle can function in the normal mode (conditions permitting) and continue to operate up to the point of solvent breakthrough. The SLA inlet and outlet valves and SLA fan can be manually operated from the computer.

The regeneration cycle is not intended to be operated manually. In the event of an emergency, the regeneration cycle will be shut down.

4.3 BRAYCYCLE Mode

++
|2|
--
The solvent laden air (SLA) enters the system at E-1 by draft from C-1 SLA blower. The adsorbers are bypassed and the SLA flows directly to the inlet to the roughing compressor C-2. The mol sieve is bypassed and the SLA passes to the Brayton Cycle Heat Pump (BCHP) C-3 and refrigeration condenser E-5 where solvent is condensed and collected in S-1 and S-2. The exhaust air stream is vented to atmosphere at the outlet of E-5. If the entering SLA contains moisture, the cryogenic section will eventually freeze due to the build up of ice and result in early shut down.

4.3.1 Normal Operation

Before starting the SLA flow, the cryogenic section is cooled to the operating temperature (-80°F) by closed loop recirculation. The flow is from C-2 to C-3 to E-5 and return to C-2. After cool down, the SLA flow is initiated and the flow path is C-1 to C-2 to C-3 to E-5 and the vent to the atmosphere.

If there is no moisture in the SLA, the operation can continue indefinitely. If the SLA contains moisture, the water will condense and freeze in E-5. Eventually, the ice will cause plugging of flow path and shutdown will be required. The pilot plant is not equipped to remove moisture as would be expected of a full scale plant.

4.3.2 Freeze/Thaw Operation

Freezing of the low temperature exchanger and related piping will result in a shut down of the process. Thawing of the equipment can be achieved by passing warm air through the return side of the exchanger E-5 and venting to atmosphere.

Alternatively, the thawing process can be achieved by normal conduction/convection by allowing the equipment to remain in the shutdown mode until thawing occurs.

The water resulting from the thawing operation is removed through the condensate piping at S-1.

5.0 CODES AND STANDARDS

The following codes, standards and regulatory requirements and other documents shall be utilized to the extent required by the design.

5.1 American Institute of Steel Construction (AISC) - Eighth Edition - 1988

5.2 American National Standards Institute (ANSI)
Chemical Plant Piping Code 1331.1 1976 as Amended

5.3 American Society of Mechanical Engineers (ASME) 1980

- Section VIII Division 1, Pressure Vessels
- Section IX Welding Specification
- Section II Ferrous Materials Specification
- Section IV Non-Ferrous Materials Specifications

5.4 National Fire Protection Association (NFPA)

- NFPA No. 70-1987 National Electric Code (NEC)

5.5 American Welding Society (AWS)

- AWS D1.1 - 1984 Structural Welding Code (NEMA)

5.6 National Electrical Manufacturer's Association (NEMA)

- NEMA 1C5-6-1983 Enclosures for Industrial Controls

5.7 Tubular Exchanger Manufacturer's Association (TEMA)

5.8 Air Movement Control Association (AMCA)

- AMCA 201-1985 Fans and Systems

6.0 DESIGN CONDITIONS

6.1 General

The pilot plant will be operated at a number of sites in Southern California - which have not been identified. In general, the system will be designed to be flexible and should handle the full spectrum of solvents and concentrations expected of candidate host sites. At this time, site specific operating conditions and specific solvents are not known. The computer and PLC programs will be accessible and will be modified to meet the local requirements before start-up.

6.2 Design Conditions

6.2.1 Adsorption

■ Inlet Conditions

Fluid - Solvent Laden Air (SLA)
Flow, SCFM 250
Temperature, °F Ambient to 300
Pressure, Inches w.c. 0 to -0.3

■ Solvent Loading

Solvent VOC
Solvent Concentration 0.1 lb/min. (max)

■ Exhaust Conditions

Breakthrough Control
of Solvents 0 to 50 ppm

6.2.2 Utilities

■ Electrical

Motors 460V/3 PH/60 HZ
Control 120V/1 PH/60 HZ
Hazardous Area
Classification Class 1, GrD, Div. 2

■ Other Utilities

Cooling Water
Pressure, psig 50 ± 10
Temperature, °F 70 ± 10
Compressed Air, psig 80 ± 10
Nitrogen
Pressure, psig 90 ± 10
Minimum Purity, % 99

7.0 ENVIRONMENTAL CONDITIONS

The following environmental conditions for Southern California will be considered in the design.

- The pilot plant will be located outdoors.

■ Dry Bulb Temperatures

Summer, °F	85-105 (Normal)
Winter, °F	30 (Design)

■ Relative Humidity, % R.H. 30-60

■ Plant Elevation, Ft. Sea Level to 300

8.0 INTERFACE REQUIREMENTS - Process & Utilities Furnished by Host Site

8.1 General

The portable pilot plant is intended to be installed on a temporary basis at several locations. Interfacing with each installation is to be managed by using standard fittings for utilities and process connections.

The fittings to be supplied are identified below.

8.2 Process Connections

- Solvent Laden Air (SLA) Inlet - 4" - 150# L.J. Forged Steel Flanged nozzle.
- Recovered Product Outlet - 1/2" - MNPT, Sched. 10 316 SS

8.3 Utilities Connections

- Cooling Water - 2" - 150# S.O. Flange, CS
- Nitrogen - 1/2" - MNPT, Sched. 40, CS
- Compressed Air - 1/2" - MNPT, Sched. 40, CS
- Electrical - 460V, 3 PH, 60 Hz, 100A
120V, 1 PH, 60 Hz, 30A

9.0 MATERIAL REQUIREMENTS

- 9.1 The solvents that will be in the SLA streams have not been fully identified, however, ketones, chlorides and trace quantities of their degradation products - acetic acid, formic acid and HCl - are anticipated. The absence of steam and water in the process reduces the risks of acid attack. Further, the limited life of the test program reduces the chance for failure of equipment.

The materials of construction of the equipment already in place on the skid that will be used for this program are made of Type 316 SS.

9.2 Materials of Construction for Various Equipment

- Adsorber Vessels - Type 316 SS
- Blower, SLA - CS
- Exchangers - Type 316 SS or Type 304 SS
- Turbo Compressor - Cast Iron with Teflon coating of wetted parts
- Turbo Expander - Compressor Expander
Housing: AL-356* Niresist
Wheel: AL-206* Inconel
- * Electroless Nickel Coated
- Instruments - Type 316 SS
- Gaskets - Fluorocarbon
- Piping - Type 316 SS or 304 SS

10.0 MECHANICAL REQUIREMENTS

- 10.1 There are no mechanical requirements due to shock or reaction forces.
- 10.2 Forces due to thermal stress will be reduced or eliminated by the use of expansion joints.

11.0 STRUCTURAL REQUIREMENTS

- 11.1 Supports for piping and equipment will be designed for the loads and for vibration related to transport of the pilot plant.

12.0 ELECTRICAL REQUIREMENTS

- 12.1 Power - 480V, 3 PH, 60 Hz - (Connected KW):

■ Blower C-1	2.2 KW
■ Compressor C-2	15 KW
■ Regen Heater E-6	12 KW
■ Mol Sieve Heater E-9	12 KW

- 12.2 Control - 120V, 1 PH, 60 Hz

■ Instrument Panel	30A

13.0 FAILURE EFFECTS REQUIREMENTS

- 13.1 Failure of any component of the system will be cause for shut down.
- 13.2 For any extended shut down of the system, the adsorber vessels will be isolated and purged with nitrogen to reduce the oxygen concentration to 5% or less.

14.0 ACCESSIBILITY, MAINTENANCE, REPAIR AND IN-SERVICE INSPECTION REQUIREMENTS

Layout of equipment will be such that all equipment is accessible and that high-maintenance items can be readily removed for service.

15.0 PERSONNEL REQUIREMENTS

- 15.1 The system will be completely automatic after start-up from the computer, by the operator.
- 15.2 Shut down is from the computer, by the operator.
- 15.3 The extent of operator monitoring will be addressed later.

16.0 TRANSPORTATION REQUIREMENTS

- 16.1 The pilot plant will be permanently mounted on a trailer for hauling around the country.
- 16.2 The legal limits for dimensions of the trailer and pilot plant are:
  - Overall Height (including trailer) - 13' - 6"
  - Width - 8' - 6"
  - Length - 48' - 0"

17.0 FIRE PROTECTION REQUIREMENTS

- 17.1 The system will be connected to a nitrogen supply to permit blanketing of the adsorbers in the event of a fire.
- 17.2 When a carbon bed contains oxygenated solvents, and shut down of the system is required, the bed will immediately be blanketed with nitrogen.

NUCON 10DE771/03 Rev. 2

17.3 Local plant regulations will be reviewed for compliance before start-up.

END

**DATE
FILMED**

7 / 9 / 92