LBL-PUB--5312

DE93 007652

LAWRENCE BERKELEY LABORATORY

TECHNICAL SITE INFORMATION

LAWRENCE BERKELEY LABORATORY
UNIVERSITY OF CALIFORNIA
BERKELEY, CA 94720

This work was supported by the U.S. Department of Energy under Contract DE-AC03-76SF00098

MASTER

DISSEMINATION OF INFORMATION

CONTENTS

Preface	vii
Director's Foreword	ix
Executive Summary	xi
Purpose	xi
Planning Objectives	xi
Management Issues	xi
Community Setting	xii
Laboratory Mission	xiii
Laboratory Conditions	xiv
Planning Analysis	xvi
Master 20-Year Plan	xvi
Five-Year Plan	xvii
1. Introduction and Setting	1-1
Background/History	1-2
Regional Overview	1-4
Vicinity Overview	1-5
Natural Features and Land Use	1-8
Relationship with the Community	1-10
Regulations and Planning Requirements	1-14
LBL Planning Process, Organization, and Goals	1-16
Site-Development Planning Goals	1-18
2. Existing Conditions	2-1
Summary of Existing Activities	2-2
Physical Environment	2-4
Land Use	2-11
Circulation and Parking	2-14
Buildings and Other Structures	2-15
Functional Areas	2-17
Utilities	2-20

Communications	2-27
Security Systems	2-29
Environment, Safety, and Health	2-29
Other Improvement Programs and Assessments	2-33
3. Planning Analysis	3-1
Strategic/Institutional Plan	3-2
Site Assessment	3-12
Alternatives	3-25
Alternatives Evaluations	3-25
Accommodation for Changes in Direction	3-26
4. Master 20-Year Plan	4-1
Land Use	4-2
Functional Areas	4-9
General-Purpose Construction Projects	4-14
Program-Related Construction Projects	4-21
General Plant Projects	4-21
Maintenance and Energy Conservation	4-22
5. Five-Year Plan	5-1
Planning Assumptions and Rationale	5-2
Five-Year Programmatic and MEL-FS Plans	5-4
General Plant Projects	5-9
General Purpose Equipment	5-10
In-House Energy Management	5-10
Maintenance Plans	5-10
Facilities Decommissioning Plan	5-11
Information Technology Resources	5-11
Appendix A Bibliography	A-1
Appendix B LBL Map with Building Numbers	B-1
Appendix C 1992 LBL Buildings and Rehabilitation Status	C-1
Appendix D LBL Land Leases	D-1
Appendix E Acronyms and Other Initialisms	E-1
Acknowledgments	E-4

FIGURES AND TABLES

Fig. 1-1.	Aerial view of the Lawrence Berkeley Laboratory	1-3
Fig. 1-2.	Regional map	1-5
Fig. 1-3.	Vicinity map	1-8
Fig. 1-4.	The adjacent land use	1-9
Fig. 1-5.	Public transportation map	1-13
Fig. 1-6.	Organization chart	1-17
Fig. 1-7.	Site planning process	1-18
Fig. 2-1.	Site constraints and opportunities map	2-5
Fig. 2-2.	Earthquake fault map	2-6
Fig. 2-3.	Storm drainage	2-8
Fig. 2-4.	Existing landscape buffer zones	2-12
Fig. 2-5.	On- and off-site bus service	2-16
Fig. 2-6.	Functional areas with existing buildings	2-18
Fig. 2-7.	LBL water distribution system	2-21
Fig. 2-8.	Sanitary sewer system	2-23
Fig. 2-9.	Natural gas system	2-25
Fig. 2-10.	Site electrical system	2-26
Fig. 2-11.	Integrated Communications System	2-28
Fig. 2-12.	Environmental monitoring locations	2-31
Fig. 3-1.	Sources of LBL operating funds since 1980	3-7
Fig. 3-2.	Schematic concept of the seven functional areas	3-8
Fig. 3-3.	The east-west circulation axis	3-9
Fig. 3-4.	Age distribution of main-site buildings	3-12

Fig. 3-5.	Current space usage	3-15
Fig. 3-6.	Age of LBL mechanical equipment	3-16
Fig. 3-7.	Age of LBL electrical equipment	3-17
Fig. 3-8.	Mechanical utility corridor improvements	3-18
Fig. 3-9.	Electrical, communications, and fire-alarm improvements	3-19
Fig. 3-10.	Landslide locations on the LBL site	3-20
Fig. 4-1.	Fifteen-year plan map	4-5
Fig. 4-2.	Future landscape buffer zones	4-6
Fig. 4-3.	Future land-use map	4-7
Fig. 4-4.	Functional areas in future building sites	4-8
Fig. 4-5.	88-Inch Cyclotron Research Area	4-9
Fig. 4-6.	Central Research and Administration Area	4-10
Fig. 4-7.	Bevalac Accelerator Complex	4-12
Fig. 4-8.	Light Source Research and Engineering Area	4-15
Fig. 4-9.	Shop and Support Facilities Area	4-16
Fig. 4-10.	Materials and Chemistry Research Area	4-17
Fig. 4-11.	Life Science Research Area	4-18
Fig. 5-1.	Five-year MEL-FS backlog	5-3
Fig. 5-2.	Five-year GPP backlog	5-4
Fig. 5-3.	Five-year GPE needs	5-5
Fig. 5-4.	Past MEL-FS and GPP funding	5-8

TABLES

Table 1-1.	Demographic and Economic Assumptions and Projections, San Francisco Bay Area	1-6
Table 1-2.	San Francisco Bay Area Housing Characteristics	1-7
Table 2-1.	Water Table Depths	2-7
Table 2-2.	LBL Temperature Normals (°F) by Month	2-9
Table 2-3.	LBL Wind Data	2-9
Table 2-4.	Rainfall Intensity and Probability	2-10
Table 2-5.	Transportation and Parking Characteristics	2-17
Table 2-6.	Site Mechanical Utilities—Water Distribution System	2-20
Table 2-7.	Site Mechanical Utilities—Sanitary-Sewer System	2-22
Table 2-8.	Site Mechanical Utilities—Natural-Gas Distribution System	2-24
Table 2-9.	Site Electrical Utilities	2-27
Table 3-1.	Analysis of Building Conditions	3-10
Table 3-2.	Resource Projections (Fiscal Year FTE)	3-11
Table 3-3.	Planned Electrical Utility Improvements	3-12
Table 3-4.	Electricity and Natural-Gas Forecasts by Functional Area	3-13
Table 3-5.	Future Electrical Utilities by Type of Services	3-14
Table 3-6.	General-Purpose Building Needs Summary	3-22
Table 4-1.	LBL Fifteen-Year Construction Plan (FY BA, \$M)	4-3
Table 4-2.	Current and Future Land Use	4-7
Table 5-1.	Programmatic Facilities (Fiscal Year/\$M)	5-2
Table 5-2.	Five-year Capital Improvement Plan (Fiscal Year, \$K)	5-3
Table 5-3.	LBL Five-Year Construction Plan	5-6
Table 5-4.	Facilities Decommissioning Plan (\$M)	5-11

PREFACE

The Lawrence Berkeley Laboratory 1992 Technical Site Information (TSI) document is a comprehensive summary of information that is the result of the site planning process, which, in conjunction with the Site Development Plan (SDP), acts as a guide for effective use of the Laboratory's land and facilities resources. The SDP and TSI provide a conceptual and operational framework for the rehabilitation of existing facilities and the development and siting of future buildings. It has been prepared for use by the management and staff of the Laboratory, the Department of Energy, the University of California, and the neighboring communities.

This TSI is based on previous planning documents and current studies and analyses.

Revisions are based on the Laboratory's annual Institutional Plan, SDP, and recent planning reviews and analyses. The document describes the physical setting, planning processes and underlying planning concepts, trends in Laboratory activity, facilities requirements, and future site development.

The TSI has been developed as part of a continuing planning and review process involving the Laboratory's 12 scientific and support divisions. The final preparation of the document was coordinated through the Office for Planning and Development, with site-plan elements and supporting materials prepared by the Plant Engineering Department of the office of the Associate Laboratory Director for Operations.

DIRECTOR'S FOREWORD

Charles V. Shank
LBL Director

The Lawrence Berkeley Laboratory's mission as a multiprogram national laboratory is to perform leading research, to develop and operate unique national experimental facilities, to train the next generation of scientists, and to enhance industrial innovation. The Technical Site Information (TSI) supports the Laboratory's Site Development Plan and addresses the major issues and the opportunities for site improvement that are critical to the continued fulfillment of this mission, under conditions that protect our staff, the public, and the environment.

The Laboratory occupies 81 permanent buildings on the main site and space in 19 buildings on the University of California, Berkeley (Main Campus and Richmond Field Station). This is a significant change since

1931, when the Laboratory consisted of a single campus building. During the past year LBL conducted more than 800 research programs and projects involving 3940 people, including 550 graduate students and 500 guests.

During the past several years the Laboratory's continuing evolution to a multiprogram laboratory has resulted in new building construction, the completion of the Advanced Light Source Building, and major improvements to utilities. The current TSI, like its predecessor, provides a strong framework for safe and environmentally sound future development. Implementation of the TSI will require the continuing collaboration of the U.S. Department of Energy, the University, and the Laboratory community.

CONTENTS

Executive Summary	xi
Purpose	xi
Planning Objectives	xi
Management Issues	xi
Community Setting	xii
Laboratory Mission	xiii
Laboratory Conditions	xiv
Planning Analysis	xvi
Master 20-Year Plan	xvi
Five-Year Plan	xvii

EXECUTIVE SUMMARY

PURPOSE

The Lawrence Berkeley Laboratory 1992 Technical Site Information (TSI) document provides analysis and policy guidance for the effective use and orderly future development of land and facilities at the LBL site. The TSI directly supports LBL's role as a multiprogram national laboratory operated by the University of California (UC) for the Department of Energy (DOE). The TSI is revised annually with major revisions consistent with DOE policy and review guidance. The specific purposes of the TSI are to:

- Summarize the physical and community setting of the Laboratory.
- Describe the existing Laboratory organization, programs, site, and facilities.
- Analyze programmatic trends and facilities requirements, shortfalls, and redevelopment needs.
- Provide policy guidance and 20-Year and 5-Year Plans to support effective use and orderly growth and development of the LBL site.

The TSI concisely expresses the policies for future development based on planning concepts, the anticipated needs of research programs, and site potential and constraints. This Executive Summary highlights management issues and outlines major sections of the document.

PLANNING OBJECTIVES

Site planning at the Laboratory reflects long-range institutional goals and values based on LBL's mission for the DOE. Planning objectives are to:

- Evaluate future mission projections and anticipate DOE national research facility needs;
- Ensure a safe and healthful workplace in full compliance with building and fire codes;
- Protect the environment and buffer activities to enhance adjacent land uses;
- Protect the national investment in valuable government-owned research and support facilities;

- Consolidate research and support services through proper siting of new buildings;
- Improve access and communications within and to the Laboratory; and
- Promote energy conservation and cost reductions through efficient building design, location, operation, parking and transportation, and maintenance.

MANAGEMENT ISSUES

LBL's site-planning management issues focus on developing the strategic framework for structures and utilities necessary to achieve the Laboratory's mission safely and protect the environment. These issues include improving the reliability of utility systems, ensuring a safe working environment, restoring and rehabilitating obsolete buildings, consolidating support functions, and accommodating the increasing numbers of scientific guests and visitors using LBL's national research facilities. Many LBL site-development issues stem from an obsolete, deteriorated infrastructure constructed during World War II and the immediate postwar

period. During the past several years, DOE has begun significant investments, to correct deficiencies in mechanical and electrical utility systems and programmatic facilities for materials research. The near-term (five years) and long-term (20 years) facilities issues being addressed by LBL and DOE include:

- *Building Replacement and Rehabilitation.* The 5-Year Plan and 20-Year Master Plan calls for construction to improve the safety and supply-services infrastructure and to improve general-purpose mechanical- and electrical-engineering facilities. Included in the plan are removal of obsolete, inefficient, and substandard facilities that cannot be made adequate and replacement of temporary structures for support activities.

- *Mechanical Utilities.* Mechanical utilities comprise domestic and cooling water, storm drains and sanitary sewers and natural gas, compressed-air, and vacuum systems. These utilities are up to 40 years old, and many are undersized for current Laboratory demands. The 5-Year and 20-Year Plans provide for the orderly replacement of these utilities. However, scheduled utilities improvements only correct existing deficiencies; any delays will engender further deterioration of these essential utilities.

- *Electrical Utilities.* LBL's power-distribution system comprises 24 substations and 32 km of 12-kV cable, most of which have exceeded their normal service lives, resulting in frequent power outages and increased maintenance requirements.

The electrical-utilities rehabilitation plan establishes priorities based on expected failure rates and the importance of equipment. In the next five years, the LBL main-site electrical power system rehabilitation plan calls for the completion of the first four phases and work to begin on the remaining two phases. This six-phase program will result in the complete rehabilitation of the underground 12-kV power distribution system and the installation of six new circuit breaker switching stations throughout the site. The upgraded switching and distribution system will provide the reliability, flexibility, and expandability necessary for efficient Laboratory operation and future growth.

- *Environment and Safety Improvements.* Safety and health improvements began in FY 1988 and include: fire protection upgrades; hazardous materials control upgrades; removal of asbestos; and improvements to safety services, medical services, building illumination, radiation protection, water-pollution control, and monitoring. Seismic stabilization of steep

slopes began in FY 1991. Road improvements include widening, replacement of base materials, and elimination of acute curves and blind spots.

- *Consolidation of Support Services.* The Site Development Plan (SDP) calls for consolidation of research and support activities in seven functional planning areas. This includes consolidation of the engineering and health-and-safety staffs and related research activities. This consolidation will facilitate plans for improving utility systems and traffic circulation along the east-west axis of the Laboratory.

COMMUNITY SETTING

The 54-hectare (134-acre) Laboratory site, located within 478 hectares (1180 acres) of University of California land, is leased by DOE through a series of 50-year lease agreements (Appendix D). The Laboratory is in Alameda County (population 1,280,000), with the eastern section in the City of Oakland (370,000) and the western section in the City of Berkeley (103,000). LBL works with these cities on matters of mutual concern, including fire protection and traffic management. Although the area is largely urban and is served by interstate highways and an extensive public transit system, the Laboratory site has a hilly topography and a backdrop of eucalyptus plantations and parks that give a rural character.

- *Land Use and Planning.* The Laboratory site is zoned governmental and institutional by the cities of Berkeley and Oakland. On all sides of the Laboratory is a buffer zone of University land. In addition, the SDP provides for landscape buffer zones between LBL facilities and the Laboratory boundary and includes guidelines to ensure compatibility with land use outside the University buffer zone.

- *Transportation Systems.* The Laboratory and the cities of Oakland and Berkeley are served by a network of public transit systems, three major airports (San Francisco, Oakland, and San Jose), two railroads, and a network of interstate freeways and state highways. In addition, LBL operates shuttle buses around the site and between the Laboratory and the UC Berkeley campus and the downtown Berkeley Bay Area Rapid Transit (BART) station.

- *Public Utilities and Community Services.* Electricity and natural gas are provided by the Pacific Gas and Electric Company (PG&E), which anticipates adequate capacity for the foreseeable future. Water is supplied by the East Bay Municipal Utilities District (EBMUD). The Laboratory implements a program of water-use reduction during periods of drought. Reservoirs adjacent to LBL provide water for anticipated emergency needs. EBMUD is currently expanding its

supplies and storage capacity to avoid future reductions in service. The Laboratory provides its own police and fire protection services, which on occasion provide emergency assistance to the University and the City of Berkeley. Several hospitals are nearby.

- *Community Involvement.* LBL efforts to enhance compatibility and to coordinate activities with the surrounding communities include three principal programs: (1) a Hill Area Fire Safety Program with the University and Berkeley fire department; (2) an LBL Traffic and Parking Management Plan to discourage single-occupant vehicles and to encourage other transportation options, and (3) a plan to ensure that historic buildings are preserved.

LABORATORY MISSION

The Laboratory, established in 1931 by Ernest O. Lawrence as a single-purpose accelerator-based University research facility, has evolved into a multiprogram national laboratory with a mission to:

- Perform leading multidisciplinary research in the energy sciences, general sciences, and biosciences in a manner that ensures employee and public safety and the protection of the environment. The energy sciences include materials

research, chemistry, geology, and conservation and renewable energy research. The general sciences include nuclear and high-energy physics and accelerator research. The biosciences include cell and molecular biology, genetics, and biomedical research.

- Develop and operate unique national experimental facilities for use by qualified investigators from throughout the world, including the Bevalac, the 88-Inch Cyclotron, the National Center for Electron Microscopy, and the National Tritium Labeling Facility. The Advanced Light Source (ALS) is scheduled for completion in 1993.
- Educate and train future generations of scientists and engineers. 500 graduate students pursue research at LBL with about 100 students receiving advanced degrees each year. Precollege programs are conducted for science educators and students.
- Foster productive relationships with industry. The Center for Advanced Materials and the Center for X-Ray Optics are examples of collaborations with industry. Technology transfer programs promote the application of research results.

LABORATORY CONDITIONS

- *Research and Technical Programs.* LBL programs are primarily supported by the DOE Office of Energy Research (62%). The largest programs are in Basic Energy Sciences, Nuclear Physics, High Energy Physics, and Health and Environmental Research. Conservation and Renewable Energy (6%) supports studies in building

energy conservation, energy storage, and solar and geothermal energy. Other DOE-sponsored programs (15%) include research on the Superconducting Super Collider (SSC), radioactive waste disposal, and fossil energy. Work for other agencies and institutions (17%) is primarily for the National Institutes of Health (NIH), Department of Defense (DOD), states, and private industry.

Projected costs for FY 1992, \$258

TSI 927-1

LBL 1989 space distribution 2.82 million gross square feet (mgsm) total.
Metric total: 0.19 million gross square meters (mgsm)

TSI 927-2

- *Condition of Buildings and Other Improvements.* LBL research and support activities are conducted in structures totaling 0.19 million gsm (2.02 mgsf), including 0.15 mgsm (1.62 mgsf) on the main site, 0.2 mgsm (0.26 mgsf) on the UC Berkeley Campus, and 0.01 mgsm (0.14 mgsf) leased off site. In FY 1992 the average age of the main-site buildings is 33 years. The inventory of building space, including current construction, is
 - Adequate: 55,300 gsm (595,300 gsf).
 - Substandard, can be made adequate: 75,400 gsm (811,200 gsf).
 - Substandard, cannot be made adequate: 19,900 gsm (214,600 gsf).

- *Utilities.* LBL's utilities distribution systems (mechanical, electrical, and communications) are all underground. Many portions were initially sized to serve large accelerators and can meet present and future requirements. However, aged segments require rehabilitation to improve flexibility and reliability. Utility systems undergoing rehabilitation include natural gas, domestic water, cooling water, low-conductivity water, electrical power, sanitary sewer, compressed air, storm drainage, standby and backup electricity, and alarm and security.

- *Circulation and Traffic.* LBL traffic circulates along an east-west central serpentine road, with north and south loops. Gates to the Laboratory are located at the ends of the central east-west road. These main roads were designed in the 1940s and early 1950s and no longer meet construction or safety standards. Nearly 7,000 vehicle trips per day are made to LBL, including 70 shuttle-bus trips off site and 98 on site. The off-site shuttle carries an average of about 1,350 passengers per day. Parking space is provided for 1,350 employee vehicles, with 1.7 employees and visitors per parking space.

- *Fire, Safety, and Emergency Preparedness.* LBL maintains fire protection, police, and emergency preparedness

facilities. The LBL Protective Services maintains 24-hour security with guard stations at the Laboratory gates, patrol vehicles, and a central dispatch and communication facility. The Fire Department provides fire-protection and ambulance services and operates the fire alarm and sprinkler systems. LBL has a Master Emergency Preparedness Plan and specific building emergency plans for dealing with disasters such as fires or earthquakes.

- *Planning Concepts.* The SDP is based on five LBL site-plan concepts. These concepts accommodate the facilities improvement needs within existing geophysical, environmental, and operational conditions. They provide a basis for understanding and evaluating the more detailed elements of the 20-Year and 5-Year Plans. The site-planning concepts are

- Consolidate activities within seven functional planning areas to enhance efficiency and effectiveness and to provide specialized research facilities.
- Redevelop obsolete buildings and infrastructure, eliminate temporary structures used for permanent functions, and improve building arrangements to increase safety and energy efficiency.

- Concentrate development along the east-west circulation and utilities axis to enhance transportation and service systems, e.g., develop off-road parking and improve pedestrian pathways.
- Improve and maintain perimeter and internal buffer zones to screen noise-generating activities and minimize potential incompatibility between adjacent operations.
- Provide off-site facilities for receiving, warehousing, and other support and research activities suitable for decentralization.

- *Design Guidelines.* Design guidelines in the SDP have been developed to achieve specific improvements while respecting site constraints and providing coherence between buildings and their surroundings. These guidelines address the following areas:

- Utilities Corridors
- Building Mass, Orientation, and Exteriors
- Energy and Operational Efficiency
- Safety Considerations
- Building Use Flexibility
- Circulation and Parking
- Topography and Grading
- Landscaping and Open Space
- Guideline Conformance Review

PLANNING ANALYSIS

Research and Support Trends. LBL's research and support trends are assessed and described in the 1992 Institutional Plan, published in December 1991. Over the next five years the Laboratory does not anticipate major growth, except that associated with the Advanced Light Source (ALS), the Human Genome Center, and further development of the Center for Advanced Materials (CAM).

Laboratory Population. In 1991, the Laboratory's employee population consisted of 3,330 full- and part-time employees. These employees included 795 staff scientists, 220 faculty scientists, 1,020 technical staff, 95 postdoctoral fellows, 450 graduate students,

LBL population—FY 1991, total 3940.

and approximately 160 undergraduates. There were 2,570 full-time equivalent (FTE) positions. LBL maintains a register of official guests, updated monthly, which contained 1,400 registered guests in 1991. About 610 of these guests were on site at any one time, so that total Laboratory population was 3,940. Of this total, 3055 were located at the main site, 765 located in UC Berkeley Campus buildings, and 120 located in off-site leased buildings. The 20-Year Plan would allow additional growth up to a total Laboratory average daily population of 4,750, including 640 on the UCB Campus.

Building Needs. Near-term needs in support of scientific programs include the Human Genome Laboratory, Chemical Dynamics Research Laboratory, Induction Linac Systems Experiment, ALS Life Sciences Center, ALS Beamline Initiative, and other new buildings and additions in many programs, including accelerator research, cell and molecular biology, and heavy-ion fusion. Longer-term needs include an Applied Science Laboratory and other new buildings and additions in many programs, including accelerator research, cell and molecular biology, and heavy-ion fusion. General-purpose-facility needs include new buildings for safety, material handling, and mechanical and electrical engineering. General-purpose facilities would replace existing obsolete structures and would not increase the size of the Laboratory.

Utilities Needs. As discussed earlier, mechanical and electrical utilities and roadways require improvements to meet existing standards for safety and efficiency. The 12-kV electrical system needs renovation to limit electrical-system failures to fewer facilities, reduce planned outages, improve maintenance, and permit the selection of the most economical electricity sources.

MASTER 20-YEAR PLAN

Land Use. 32.5 hectares (80.2 acres) of the site are currently open space and buffer areas; 31.5 hectares (77.8 acres) would be retained as open space and buffer if all projects identified in the 20-Year Plan were completed. The 20-Year Plan would change the proportion of the LBL main site improved with structures, utilities, or roads from the current 38% to 42%. Nine buffer zones are described in the SDP, with specific planning criteria identified.

Functional Areas. The functional planning areas are related groupings of facilities that enhance work efficiency and effectiveness. In general, parking is at the perimeter of these areas, and clusters of buildings form the core. The 20-Year Plan identifies changes to all of the functional planning areas to allow for potential research activities and to conform to SDP objectives, planning concepts, and design guidelines. The SDP calls for the removal of 0.02 mgsm (0.2 mgsf) of buildings and the

renovation of 0.07 mgsm (0.8 mgsf) of building space. Building sites are planned or reserved for 0.06 mgsm (0.6 mgsf) of new construction. *Development Potential.* If all the sites and buildings were developed in accordance with the 20-Year Plan, it would result in a net increase of approximately 0.04 mgsm (0.4 mgsf) to the existing main site of the Laboratory, for a total of approximately 0.19 mgsm (2.0 mgsf). For comparison, the 1992 total, including current construction, consisted of 0.15 mgsm (1.62 mgsf) at the main site. The 20-Year Plan increases provide for growth in life sciences, chemistry and materials sciences, conservation and renewable energy, earth sciences, and fossil-energy research. Many of these research areas were not a part of the Laboratory's mission during its period of growth during the 1950s and 1960s under the sponsorship of the Atomic Energy Commission. As indicated in the Planning Analysis section, increases are primarily for programmatic purposes. Proposed general-purpose facilities replace existing obsolete facilities.

FIVE-YEAR PLAN

The facilities issues being addressed by LBL and DOE during the five-year construction planning period include:

- *Programmatic Facilities.* Programmatic facilities primarily provide capability for DOE's Office of Energy Research. These facilities projects include the Chemical

Dynamics Research Laboratory and the Human Genome Laboratory, and the completion of existing space and additions are proposed for the ALS Life Sciences Center, ALS user facilities, and the ALS Beamline Initiative. Other programmatic projects include additions for heavy-ion accelerator research (the Induction Linac Systems Experiment), cell and molecular biology, biomedical isotope facilities, and magnetic fusion energy ion source test stands. Each programmatic facility, like general-purpose facilities, integrates the National Environmental Policy Act; the California Environmental Quality Act; and environment, safety, and health considerations into design and project review from the early conceptual phases through completion of construction and operation.

- *Accelerator Improvement Projects.* The Bevalac modernization program includes the installation of new controls and control systems for enhanced overall performance of the accelerator. The installation of the Electron Cyclotron Resonance (ECR) source at the 88-Inch Cyclotron has resulted in greater than fivefold increase in beam intensity. Design efforts for the next-generation, gyrotron-driven ECR source are under way. Improvement funds will be provided for additions to the ALS Project. These additions will enhance experimental

equipment and beamline components, provide photon beam stabilization, and include accelerator system upgrades to improve performance.

- *Environmental Restoration and Waste Management (ERWM).* LBL environmental management site projects and operating activities are essential to correct and restore environmental conditions and to improve the management of waste handling operations in support of DOE's national environmental objectives. The five-year ERWM Plan includes a corrective action program to achieve and maintain required exposure and risk levels to chemicals in soils and groundwater, in discharges to sewers, and in laboratory buildings. The environmental restoration program for facilities includes the assessment and remediation of chemical contamination, the closure of the existing hazardous waste handling facility, and planned decontamination and decommissioning activities for the Bevalac. The waste management program includes support for the construction of a new hazardous waste handling facility, the development of an aggressive waste minimization program and other projects. These ERWM project plans provide for continuing environmental protection for compliance with DOE and other Federal regulations and for meeting requirements established by state and local agencies.

- *Safety and Health (S&H) Plan.* The Laboratory is preparing a detailed Safety and Health 5-Year Plan for the FY 1994 budget process. The prioritized plan will strengthen DOE S&H management and improve the allocation of S&H resources.
- *Inactive Surplus Facilities Plan.* The development of new program directions for nuclear physics will result in the phase-out of LBL's Bevalac nuclear physics program in FY 1994. Unless support for the Space Exploration Initiative warrants continued use or funding is provided from another agency, the Bevalac will undergo decommissioning in accordance with the FY 1992-1997 LBL Decommissioning Plan. The major costs for decommissioning will be borne by ERWM. Associated preparation and transfer costs prior to ERWM acceptance will be borne by the Office of Energy Research.
- *Multiprogram Energy Laboratory Facility Support (MEL-FS).* The total proposed five-year (FY 1994-FY 1998) MEL-FS program will require budget authority of \$100 M for this period. This modernization program addresses needs primarily related to the many buildings and utilities that are 20-40 years old and need improved safety, mechanical, electrical, and structural systems to meet current design standards. Full modernization of the main site requires a long-term 20-year investment program. Individual projects are evaluated against generic Laboratory SDP priorities: (1) safety systems and safety facilities, (2) environmental protection, (3) utilities reliability, (4) design standards and obsolescence, and (5) delivery of research and support services.
 - *MEL-FS Building Replacement and Rehabilitation.* During the next five years LBL's modernization plans call for construction to improve the safety and support services infrastructure and to improve general-purpose mechanical and electrical-engineering facilities. The plan includes removal of obsolete, inefficient, and substandard facilities that cannot be made adequate and replacement of temporary structures for support activities.
 - *MEL-FS Safety Improvements.* Safety and Health improvements began in FY 1988 and include fire protection upgrades; hazardous materials control upgrades; removal of asbestos; and improvements to safety services, medical services, building illumination, radiation protection, water-pollution control, and monitoring. Seismic stabilization of steep slopes began in FY 1991. Road improvements include widening, replacement of base materials, and elimination of acute curves and blind spots.
- *MEL-FS Electrical Utilities*—In the next five years, the LBL main-site electrical power system rehabilitation plan calls for the completion of the first four phases and work to begin on the remaining two phases. This six-phase program will result in the complete rehabilitation of the underground 12-kV power distribution system and the installation of six new circuit breaker switching stations throughout the site. The upgraded switching and distribution system will provide the reliability, flexibility, and expandability necessary for efficient Laboratory operation and future growth.
- *MEL-FS Mechanical Utilities*—Mechanical utilities comprise domestic and cooling water, storm drains and sanitary sewers, natural gas, compressed-air, and vacuum systems. These utilities are up to 40 years old, and many are undersized for current Laboratory demands. The modernization plans provide for the orderly replacement of these utilities and will help prevent potential damage to the environment. Scheduled utilities improvements only correct existing deficiencies; any delays will engender further deterioration of these essential utilities.

- *General Plant Projects (GPP).* GPP funds have been provided by DOE's Nuclear Physics Division to fund priority construction projects that have a funding ceiling of \$1.2 M. Funding to date has been inadequate to meet the Laboratory needs within a timely schedule. This program has a significant backlog of projects exceeding \$20 M. Roughly a third of this backlog is for environment, health, and safety needs; a third is for utilities safety and reliability, building maintenance, and standards compliance; and a third for multiprogram support facilities and small programmatic projects and additions. In FY 1992 more than half of the \$3.1 M GPP budget will be used for ES&H-related projects. The remaining funds cannot meet current project needs and do not allow progress in reducing this backlog. Increasing GPP funding to \$6 M annually and increasing the ceiling from \$1.2 M to \$2.0 M would ensure the success of the Laboratory's safety reha-

bilitation program and help reduce the current backlog of projects over the next five years. Support and coordination for both programmatic and institutional GPP through the Office of Energy Research would facilitate effective management of GPP needs.

- *General Purpose Equipment (GPE).* Essential support equipment has been funded through DOE's Nuclear Physics Division. LBL's Five-Year GPE Plan identifies needs based on a range of criteria, including environment, safety, and health; legal requirements; failed, worn, inefficient, or obsolete equipment; substandard performance; or increased workload and demand. The current

funding level of \$1.7 M/year is inadequate to meet the Laboratory needs. Currently there is a \$38 M equipment backlog for environmental monitoring and fire safety, physical-plant maintenance, mechanical and electrical shops, transportation, and data processing and communications. Increasing GPE support \$3 M/year would provide a basis for reducing the backlog. Consolidated GPE management at the level of the Office of Energy Research would facilitate the implementation of an integrated and longer-range GPE plan.

1. INTRODUCTION AND SETTING

CONTENTS

1. Introduction and Setting	1-1
Background/History	1-2
Regional Overview	1-4
Vicinity Overview	1-5
San Francisco Bay Area	1-5
Cities of Oakland and Berkeley	1-7
Natural Features and Land Use	1-8
Relationship with the Community	1-10
Overview	1-10
Security and Fire Protection	1-10
Public Utilities	1-11
Transportation Systems	1-12
Regulations and Planning Requirements	1-14
Federal	1-14
State	1-14
Local	1-15
LBL Planning Process, Organization, and Goals	1-16
Site-Development Planning Goals	1-18

BACKGROUND/HISTORY

The Lawrence Berkeley Laboratory is a national laboratory operated by the University of California (UC) for the U.S. Department of Energy (DOE). The Laboratory is an independent academic unit of the University of California system and is located adjacent to the University of California, Berkeley (UCB) Campus.

LBL began as an accelerator laboratory in 1931, when Ernest O. Lawrence established the Radiation Laboratory with the construction of the 27-Inch Cyclotron on the UCB Campus. In 1939 the need for higher-energy accelerators resulted in the construction of the 184-Inch Cyclotron on a hill overlooking the campus and the City of Berkeley. Driven first by pioneering nuclear physics and biophysics research, then by the Manhattan Project during World War II and later by high-energy physics, the Laboratory's growth continued until about 1967. During the period of rapid growth, between 1940 and 1946, the original hillside Laboratory site became crowded with temporary wooden buildings hastily erected in response to national defense needs. However, development during the 1950s was more carefully planned, with the construction of

permanent concrete and steel-frame structures east and west of the earlier construction.

Figure 1-1 is an aerial view of the Laboratory. Under the auspices of the Atomic Energy Commission, LBL's largest accelerator, the Bevatron, became operational in 1954 as the nation's leading high-energy physics facility. The Heavy Ion Linear Accelerator (HILAC) was completed in 1958, and the 88-Inch Cyclotron was completed in 1964. These facilities have been modernized and have continued to make important contributions to nuclear physics research. However, the Bevalac's nuclear physics program is being phased out in FY 1993, and plans for decommissioning the facility are underway pending consideration of using the Bevalac for the nation's Space Exploration Initiative.

There was a period of reduced program activity at the Laboratory from the late 1960s through the early 1970s as much of the nation's high-energy physics research moved to other laboratories with larger accelerators. In 1974 the Bevatron was combined with the HILAC to form the Bevalac, and the Laboratory regained its position as one of the world's premier accelerator facilities, this time for heavy-ion nuclear physics research.

In response to the 1973 oil embargo, several

new research programs broadly relevant to national energy supply and end-use were initiated in 1975, following the reorganization of the Atomic Energy Commission into the Energy Research and Development Administration and the Nuclear Regulatory Commission. The Laboratory grew to its largest population in 1979, following the establishment of the DOE, but no permanent buildings were constructed to accommodate this growth; temporary buildings and leased space in the cities of Berkeley and Emeryville housed some research programs and most support services. By 1980 only 25% of the Laboratory's programs were in high-energy and nuclear physics, down from 75% in 1970. The Laboratory had become a multiprogram national laboratory, with a fundamental shift in mission since Long Range Development Plans were initially prepared during the 1950s.

From 1980 to 1982, Federal support for energy research dropped precipitously, and basic research declined, resulting in a 19% reduction in LBL's work force. Subsequently, the Laboratory's planning reemphasized basic, laboratory-based research founded on LBL's multidisciplinary scientific strengths. These plans called for the development of basic energy sciences and life sciences while

Fig. 1-1. Aerial view of the Lawrence Berkeley Laboratory.

maintaining historically important roles in high-energy and nuclear physics. In 1984 the National Center for Electron Microscopy was completed. The strongest of the energy-conservation and environmental-research programs in building sciences, energy storage, and indoor air quality that had developed during the 1970s were retained into the 1980s. Plans were initiated for facilities in support of research programs with long-term potential for contributing to the nation's capabilities in materials science, chemistry, biology, and the earth sciences.

This diversification toward multiprogram research activities and the development of the basic energy sciences are reflected in the Laboratory budgets over the past two decades. Over the past decade the Laboratory has emphasized the need for increased capital investment in its physical plant (compared to the low funding during the late 1960s and 1970s) to revitalize existing facilities and to build major new research facilities to support DOE's programs. The Technical Site Information (TSI) provides guidance for using these capital funds effectively and for accommodating the significant changes in the Laboratory's mission and updates the 1987 Long Range Development Plan (LRDP). The role of the Laboratory is now broad, and LBL provides national scientific leadership and technological innovation in support of the following mission to:

- Perform leading multidisciplinary research in the energy sciences, general sciences, and life sciences in a manner that ensures employee and public safety and the protection of the environment. The energy sciences include materials research, chemistry, geology, and conservation and renewable energy research. The general sciences include nuclear and high-energy physics and accelerator research. The life sciences include cell and molecular biology, genetics, and biomedical research.
- Develop and operate unique national experimental facilities for use by qualified investigators from throughout the world, including the 88-Inch Cyclotron, the National Center for Electron Microscopy, and the National Tritium Labeling Facility. The Advanced Light Source (ALS) is scheduled for completion in 1993. The Bevalac is planned to conclude its nuclear physics support in FY 1993, and may be decommissioned beginning in FY 1994 pending consideration as a part of NASA's Space Exploration program.
- Educate and train future generations of scientists and engineers. 500 graduate students pursue research at the LBL with about 100 students receiving advanced degrees each year. Precollege programs are conducted for science educators and students.

- Foster productive relationships with industry. The Center for Advanced Materials, the Center for X-Ray Optics, and the California Institute for Energy Efficiency are examples of collaborations with industry. Technology transfer programs promote the application of research results.

REGIONAL OVERVIEW

The western United States, notably California and the San Francisco Bay Area, strongly influence science and engineering research and development in the Pacific Basin. LBL has the advantage of being situated close to high-technology industries in the microelectronics, biotechnology, aerospace, telecommunications, petroleum, and advanced-materials-development fields (Figure 1-2). This exciting research and development environment is enhanced by the desire of Japan and the developing Pacific Rim countries to develop and use new technologies. High-quality academic, private, and Federal research and development programs create a San Francisco Bay Area job market that attracts a first-class labor pool. Interactions are facilitated by a regional transportation systems and comprehensive telecommunications and computing resources. Necessary raw and finished materials and equipment are in most cases readily available because of the high local demand

TSI 927-4

Fig. 1-2. Regional map.

these research activities generate. The demographic and economic assumptions represented in Table 1-1 indicate a high mean household income and an increasing population growth rate, and increasing labor force,

through the year 2005. San Francisco Bay Area housing characteristics are shown in Table 1-2.

Technology transfer to and from industry is enhanced in many cases by the proximity of

many industrial organizations. Graduate students, postdoctoral associates, and professors from many other U.S. and foreign universities benefit from involvement with LBL research programs and user facilities. The UC system comprises nine top-rated campuses, including four medical schools, with a wide variety of scientific strengths. The Laboratory has strong interactions with other top California universities, such as Stanford and the California Institute of Technology.

VICINITY OVERVIEW

San Francisco Bay Area

LBL is located five kilometers east of San Francisco Bay on the slopes of the Coast Range within 479 hectares (1183 acres) of contiguous UC land. Most of the Laboratory's main-site buildings are owned by DOE and were constructed on University land under long-term lease to the Federal government (Appendix D). The Laboratory's 54 hectare (134-acre) site is in Alameda County, with the eastern portion of the site in Oakland and the Western portion in Berkeley, largely a university and residential community with a population of 103,000.

Research is also conducted in buildings on the UCB campus, (student population 31,500), and at the Richmond Field Station, a University facility within the City of Richmond, about five kilometers north of Berkeley (Figure 1-3).

The San Francisco Bay Area is a cosmopolitan region comprising nine counties with a

Table 1-1. Demographic and Economic Assumptions and Projections, San Francisco Bay Area.^a

Demographic Projections	1985-1987	1988-1990	1991-2005
Annual Growth Rate in Labor Force Participation	2.1%	1.8%	1.2%
Net Annual Regional Migration	34,600	31,800	34,800
Population	5,531,950	5,911,200	6,492,400
Labor Force	3,035,600	3,332,300	3,912,100
Mean Household Income	\$39,200	\$41,300	\$47,400
Percent Change in Regional Household Size	-0.47%	-0.73%	-0.75%
Economic Projections			
Annual Growth Rate in All Gross Exports	3.2%	4.6%	5.0%
Annual Growth Rate in High Tech and Information Technology Exports	3.7%	6.0%	6.4%
Annual Energy Cost Increases in Current \$	Stable	5% greater than inflation	5% greater than inflation
Annual Growth in Capital Spending	5.4%	6.6%	4.6%
Annual Growth in Gross Regional Product	2.9%	2.9%	3.2%

^a Association of Bay Area Governments (ABAG), Projections for the San Francisco Bay Area to the Year 2005, July 1987.

total land area of 1.9 million hectares (4.6 million acres) and a population of 6.0 million. Although metropolitan areas are highly developed, only 12% of the total land has been developed as residential area, commercial, industrial, or highways. The highly diversified, technology- and service-oriented labor force of the region totals 3.3 million people. The industrial base is not oriented toward cyclically

sensitive heavy industry but toward high technology. Aerospace, computers, electronics, scientific instruments, and communications equipment comprise more than 50% of all manufacturing jobs.

The Bay's topography consists of a valley 145 kilometers (90 miles) long formed between two geological faults—the San Andreas fault, along the San Francisco Peninsula and

Marin County, and the Hayward Fault, along the East Bay Hills. The coastal ranges surrounding the Bay reach to 1283 meters (4,210 feet). The Bay itself covers 673 km² (260 square miles) and moderates the local climate. The East Bay, comprising the Counties of Alameda and Contra Costa, is a large and diversified area but shares such features as a common water-distribution system, unified public-transit systems for buses and rail transit, and a unified regional park system.

Alameda County, with a population of 1,280,000 and an area of 189,950 hectares (469,400 acres), has major educational, research, industrial, and agricultural resources, including six colleges and universities, large private and public research laboratories, heavy and light industry, and extensive nursery and viticulture acreage. Important industries include electronics, automobile assembly, biotechnology, and food processing. Alameda Naval Air station is home base for several aircraft carriers of the Pacific Fleet. The civilian labor force is approximately 600,000. The annual population growth rate during the mid-1980s was 7%. Most of the growth is projected for the southern area of the county. The Alameda County Planning Department prepares General Plans that are primarily directed toward the unincorporated areas of the County. The County General Plan for the Central Metropolitan, Eden, and Washington Units was prepared in 1981 and includes the communities and area surrounding LBL. These plans include land use, noise, scenic routes, and housing.

Cities of Oakland and Berkeley

Oakland is the county seat and, with a population of 372,000, is the sixth largest community in California. The port of Oakland can accommodate any vessel in the Pacific trade fleet, and three transcontinental railroads serve the city. The annual population growth rate during the mid-1980s was 1%. Growth in Oakland is expected to occur primarily in the vicinity of the airport, in the Harbor Bay Isle Business Park, and in Downtown Oakland. Oakland is a member of the Association of Bay Area Governments. The principal planning document of the City is the Oakland Master Plan.

Berkeley is a residential, university, and industrial city encompassing 2720 hectares (6720 acres). The City is best known for the University of California. Industries include major biotechnology, electronics, chemical and pharmaceutical companies; small foundries and fabrication companies; and other high-technology companies and service industries. The population of Berkeley has not changed during recent years. Berkeley is a member of the Association of Bay Area of Governments. The principal planning document of the city is the Berkeley Master Plan (1977), which is now being updated. Berkeley has also prepared a Draft Berkeley Downtown Plan, the Housing Element, and various neighborhood plans. The Laboratory is exempt from local zoning and planning regulations but cooperates with the

Table 1-2. San Francisco Bay Area Housing Characteristics.

County	Population	Total	Single	Housing Units (Thousands)			Mobile Homes	% Vacant	Pop. / H-Hold
				2 - 4	>5				
Alameda	1,313	507	300	60	141		6.9	4.8	2.6
Contra Costa	837	324	235	23	59		7.5	4.6	2.7
Marin	237	101	70	8	21		1.7	4.7	2.4
Napa	115	45	33	3	5		3.9	6.4	2.6
San Francisco	729	332	105	79	147		0.1	7.0	2.3
San Mateo	670	254	166	17	67		3.5	3.9	2.7
Santa Clara	1,532	548	354	42	131		20.8	3.7	2.8
Solano	365	125	90	11	19		4.6	4.7	3.0
Sonoma	407	167	124	11	21		11.9	7.2	2.6

California Department of Finance Demographic Research Unit, April 28, 1992.

Cities of Berkeley and Oakland, and with other local communities, on matters of mutual concern.

The Laboratory is sited on the ridges and draws of Blackberry Canyon, which forms the central part of the site, and Strawberry Canyon, which generally forms the southern boundary. The area to the south, which is University land, is maintained largely in a natural state and includes recreational facilities and the University Botanical Garden. Above and to the east of the Laboratory are located the University's Lawrence Hall of Science and the Mathemati-

cal Sciences Research Institute. LBL is bordered on the north by predominantly single-family homes and on the west by multiunit dwellings, student residence halls, and private homes.

The eastern section of the main Laboratory site is located along the northeast boundary of Oakland. Although the area is largely urban, the Laboratory site has a backdrop of botanical gardens and regional parks that preserve the rural character of the foothills.

The Laboratory is served by a network of state, county, city, University, and LBL road-

ways and public, University, and Laboratory transit services. The Laboratory is within commuting distance to the Lawrence Livermore National Laboratory and the Stanford Linear Accelerator Center. The DOE field office at San Francisco (DOE/SF) is located in Oakland. In addition DOE/SF maintains offices and staff at its Site Office at LBL.

NATURAL FEATURES AND LAND USE

LBL's hillside location, with elevations ranging from 150 to 300 meters above sea level, affords dramatic views of neighboring San Francisco Bay. The LBL site is drained by the west and south branches of Blackberry Creek and by Strawberry Creek and is underlain by folded sedimentary and volcanic rock that has weathered to form soils several feet thick.

The hillside topography and vistas are both an amenity and a constraint and add an important dimension to site planning at LBL. Grading and filling are necessary to provide most building sites, and a slope-stabilization program that includes shallow dewatering wells, vegetation cover, and soils management is critical to site management. The Hayward fault (a part of the active San Andreas fault system), which developed as the Berkeley Hills were uplifted, is at the western edge of the main LBL site. Buildings and building addi-

Fig. 1-3. Vicinity map.

tions will not be sited across the fault. Originally the site was coastal shrubland, but during the last 100 years the area was extensively grazed by cattle and, except near creeks, became primarily grassland. Since the 1950s the halt of grazing and subsequent land management have resulted in the growth of trees, especially eucalyptus, oak, and evergreens. Control of this vegetation is an impor-

tant element of the Hillside Fire Management Plan. Deer, various small mammals and reptiles, and birds populate the Laboratory site and the adjacent hills. There are no threatened or endangered species that have been identified in or adjacent to the LBL Site.

Adjacent land use consists of residential, institutional, and recreation areas (Figure 1-4). Development within the Laboratory site is

governed by guidelines (Chapter 2) that were developed with the understanding that operations must be compatible with the surrounding community. Visually the Laboratory is associated by the public with the UCB Campus, and the Laboratory works with municipal, county, and university planning staffs to maintain and improve relationships and to coordinate development plans.

Fig. 1-4. The adjacent land use.

RELATIONSHIP WITH THE COMMUNITY

Overview

UCB is immediately adjacent to LBL and is the largest employer in the City of Berkeley. It is the second largest campus of the 9-campus/3-laboratory UC system and has an enrollment of about 31,500 students. The academic staff is 4,344, and the total number of employees is 10,785. The University maintains its own planning department and is in the process of revising its Long Range Development Plan issued in 1990. The Laboratory works with the University on matters of mutual planning concern, provides advance notice during the planning stages of LBL construction projects, and seeks input from the University for LBL's SDP.

The Laboratory and UCB interact to develop plans and programs of mutual benefit. These involve elements of scientific program plans as well as facilities and environmental issues. The Laboratory's 1987 LRDP was presented for discussion before the UCB Campus Planning Office Staff and the Chancellor's Planning Committee. Three development programs have been identified during the SDP preparation and review process: fire-safety coordination, traffic and parking management, and historical preservation. The Laboratory's Site Development Plan and this TSI document maintain the same LBL population growth projection, Laboratory building area, and land

use plan consistent with the Regent's approved LRDP for LBL. The DOE planning documents provide the implementation framework for the Regent's approved plan.

A historic-preservation review, conducted by an independent consultant in 1987, documents LBL's facilities and makes recommendations to ensure LBL's compliance with environmental quality-assurance guidelines. Additional background and planning documents for fire prevention, parking and traffic control, and historical preservation are included in Appendix A.

The Laboratory also recognizes its responsibility to make its facilities available to the nonscientific public through tours and educational programs. For example, the Laboratory has established science education programs that operate in coordination with the Lawrence Hall of Science for extending precollege, as well as college and graduate level education programs, to both teachers and students. The Laboratory also provides an extensive schedule of tours, used by over 3000 visitors annually to learn about LBL research facilities and activities.

It is the policy of the Laboratory and the University to cooperate with local agencies on planning matters of mutual concern. The Laboratory's planning staff meets with the UC Berkeley Neighborhood Liaison committee to inform the citizens of bordering communities of major changes to the site. To facilitate smooth transitions in changes to the site, LBL planners communicate and coordinate activities with the cities of Berkeley and Oakland,

UCB, and DOE/SF planning staffs. In 1992, the Laboratory prepared a Supplemental Environmental Impact Report under the California Environmental Quality Act (CEQA) for the FY 1992-1997 Management and Operating Contract, and held a public hearing in Berkeley as a part of the CEQA process. This process involved close participation and review by the City of Berkeley and by other local and state agencies.

Security and Fire Protection

Security and fire-protection services in the area are provided by Police and Fire Departments of the cities of Oakland and Berkeley, by the Alameda County Sheriffs Department, and by the California Highway Patrol. The Oakland Police Department has a staff of 608 officers, and its central command center is in Downtown Oakland. The Oakland Fire Department has 483 firefighters organized into 23 engine companies and 7 truck companies. Three engine companies and a truck company are within 5 kilometers of the Laboratory. LBL, with its own fire services, has reciprocal agreements with Berkeley and Oakland to cooperate on fire response. In addition, LBL is part of the Alameda County mutual aid system.

The Berkeley Police Department has 176 officers and is located in the downtown Civic Center. The Berkeley Fire Department has 125 firefighters, 7 companies, and 2 ambulances. Three Berkeley engine companies are located

within 1.6 kilometers (one mile) of the Laboratory. Local emergency preparedness is coordinated through the Alameda County Office of Emergency Services, with a command center in Oakland. The area is a part of Region 2 of the State Office of Emergency Services, which has its regional command center in Pleasant Hill in Contra Costa County. LBL conforms to Region 2 emergency plans and has communications access to the statewide emergency communications network.

The Laboratory maintains a Fire Department, and the University maintains a Police Department on campus with a continuing dedicated patrol at LBL during all 3 daily 8-hour shifts to maintain 24-hour security at the Laboratory. Facilities and equipment include guard stations at the three gates and patrol vehicles.

The LBL Fire Department occupies two buildings totaling 700 gsm (7500 gsf). It provides fire-protection and ambulance services to the Laboratory and operates the fire-alarm and sprinkler systems in Laboratory buildings. In addition, it assists the UCB and local municipal fire departments in controlling an average of 3–4 fires annually in the neighboring communities. The Laboratory's fire-protection and ambulance capabilities will continue to be available to augment local community services. Fire, safety, and emergency-preparedness long-range plans are summarized in Chapter 4.

Fire-safety measures are designed to minimize the severity of fires originating along

roadways or from adjacent property. Although the natural-vegetation areas between LBL and nearby residences are outside LBL's jurisdiction, the Laboratory assists UCB and Berkeley and Oakland with fire-safety measures. The Laboratory has agreed to provide back-up fire control/patrol teams and equipment during controlled burns. Historically, the Laboratory's Fire Department has responded to calls for assistance from local fire departments and is committed to continue to do so. The Laboratory is cooperating and participating with the City of Berkeley and UCB in their Fire Management Plan for the UC Hill Area. In addition to scheduled controlled burns coordinated with UCB, plans include the planting and maintenance of fire-resistant vegetation to create a firebreak between the Laboratory fence line and adjacent grassy slopes. A specific program of fuel reduction is in place for FY 1992 following the 1991 fire in the Oakland Hills.

Public Utilities

The Laboratory's primary water supply is from the East Bay Municipal Utility District (EBMUD). Natural gas and electricity are provided by the Pacific Gas and Electric Company (PG&E). LBL's sanitary sewers connect to the City of Berkeley system, which terminates at a sewage treatment plant in Oakland. The LBL storm drains empty into Blackberry and Strawberry Creeks, which flow

into the City of Berkeley system and then into San Francisco Bay. A revitalization of on-site utilities has been initiated through the MEL-FS and GPP programs, as described in Chapters 4 and 5.

EBMUD supplies water to LBL primarily from large-capacity reservoirs (260 million m³) (68 trillion gallons or 210 thousand acre feet) in the Sierra Nevada foothills. Water is transported via 150 km (90 miles) of aqueducts to 5 local reservoirs. The system supplies 20 communities with 1.1 million people (348,000 water meters) in an 821 km² (317-square mile) service area. Average use is 830 million m³ (219 billion gallons) per day during high-use years. During a recent drought, customer conservation incentives reduced consumption to 685 million m³ (181 billion gallons) per day. Additional local storage capacity is planned with the construction of three new reservoirs. LBL uses approximately 380 m³ (100,000 gallons) of water per day.

Although electricity and natural gas are provided primarily by PG&E, electrical service has also been provided by the Bonneville Power Administration through the Western States Inter tie. PG&E supplies both firm and interruptible power to LBL. PG&E serves 48 counties in California with a population of 11 million and has a system-wide generating capacity of 21,700 MW. The East Bay service region of PG&E (Contra Costa and Alameda Counties) has a peak demand of 3,000 MW and annually consumes 15,000 billion kW hours of electricity. The Laboratory had a peak

demand of 20,000 kW and consumed 74,000 MW hours of electricity in FY 1991. Average demand was 14,000 kW. The Laboratory has its own 60-MW Substation. PG&E has ample capacity to meet anticipated demand for the foreseeable future. Electricity costs are not expected to increase more than 0.5% per year during the near future. Electricity rates are regulated by the California Public Utilities Commission. LBL consumed 4 million cubic meters (138 million cubic feet) of natural gas in FY 1991, also supplied by PG&E.

Public sewers connect to the Laboratory at Hearst Avenue and along Strawberry Canyon. The City of Berkeley is in its 8th year of a 20-year rehabilitation program to modernize and increase capacity of the sanitary-sewer drain system. Sanitary-sewer wastes are disposed of by EBMUD. The dry-weather primary treatment capacity is 1.1 million m³ (300 million gallons) per day. Secondary treatment capacity is 650,000 m³ (170 million gallons) per day. Typical daily treatment flows to the system are 340,000 m³ (90 million gallons) per day. Wet-weather flow can exceed capacity during some storms. The Utilities District has initiated a five-year program to construct additional wet-weather facilities to handle the expected increases from contributing communities. With the new facilities the peak wet-weather treatment capacity will be 1.6 million m³ (415 million gallons) per day, which, with the new retention capacity, will accommodate a total flow in the sewer system of 2.9 million m³ (775 million gallons) per day during storms.

The Laboratory owns and operates its own voice, data-communications, and computer-network telecommunications systems. The Integrated Communications System (ICS) provides voice and data services and links with external networks, including Pacific Bell (the local telephone company), AT&T, and the Federal Telecommunications System. LBLnet is a Laboratory-wide computer network connected through gateways to external networks, including Milnet, BARRNet, ESNET, and the UCB campus network.

Transportation Systems

The Laboratory and the City of Berkeley are served by the BART trains, regional and local bus services, many trucking companies, three major airports (the San Francisco, San Jose, and Oakland International Airports) with frequent ground transportation to Berkeley, and two major railroads (Figure 1-5). The Laboratory operates a shuttle-bus service to downtown Berkeley, which is served by 15 local transit routes.

BART is a fully automated rapid rail transit system with 115 km (71.5 miles) of double track serving 34 stations in Alameda, Contra Costa, and San Francisco Counties. The system provides approximately 200,000 passenger trips per day and maintains 440 rail cars. Three stations are located in Berkeley and are within 3.2 km (2 miles) of LBL. Laboratory shuttle buses provide transportation to and from the downtown station. Planned

extensions to San Mateo County and in Alameda and Contra Costa Counties include 6 new stations and 40 km (26 miles) of track.

The Alameda-Contra Costa Transit District is the largest bus transit service in the Bay Area and operates a fleet of 830 buses over a system with 3,540 directional street-kilometers (2,200 miles). The system provides service at 7000 bus stops for approximately 220,000 passengers per day. The bus stops adjacent to the Lawrence Hall of Science and at Hearst and Gayley roads are approximately 100 m (100 yards) from Laboratory entrances.

Access to LBL is via three gates: the main entrance, Blackberry Gate, off Hearst Avenue (which becomes Cyclotron Road), directly east of the UCB campus; Grizzly Gate, off Centennial Drive; and Strawberry Gate, also off Centennial Drive. The site is served by a serpentine road pattern that conforms to the hilly topography. Approximately 50% of LBL employees and guests live within a 6.5-km radius (15-minute driving time) of LBL. Although LBL is served by excellent public transportation systems and its own shuttle-bus service to the UCB Campus and downtown Berkeley, the majority of Laboratory employees and guests use automobiles for transportation to and from work.

LBL's Transportation Systems Management Committee has been working to identify ways to reduce LBL single-occupant vehicular traffic while fully meeting the transportation needs of LBL employees. A full-time Transportation Systems Management Coordinator develops

and promotes traffic and parking mitigation measures. Program development thus far has included a Laboratory-wide employee transportation survey, quarterly traffic counts at the three Laboratory gates, a computerized ride matching system, participation in a state-wide ride sharing promotional event, Laboratory newsletter features, and new-employee orientations.

Further program elements may include a two-person vs. three-person carpool system, preferential carpool parking, expanded bicycle paths, additional bicycle storage, encouraged use of flextime to reduce congestion during peak traffic periods, and subsidized transit passes. Long-term elements may include new parking structures, increased shuttle-bus service, off-site parking facilities, a mini-cafeteria to service outlying areas, and a telecommuting program.

The transportation and parking plans and safety services are intended to minimize neighborhood traffic congestion, to improve parking access within the site, and to protect University and DOE property. Traffic problems are a major concern to the City of Berkeley because of existing congestion on routes to the University and Laboratory. LBL has agreed with the City to limit the impact of additional staff in traffic during peak periods. The on-site and off-site shuttle buses greatly facilitate access to the Laboratory from the Campus and downtown Berkeley. Completion of existing parking and building projects should eliminate the need for roadside parking over the next 5

Fig. 1-5. Public transportation map.

years, and completion of the long-range parking improvements would provide adequate parking for estimated growth.

REGULATIONS AND PLANNING REQUIREMENTS

LBL conducts its planning, operation, and construction activities in full compliance with Federal laws and regulations and with applicable state and local regulatory requirements. Specific DOE requirements are provided in enabling legislation, the Code of Federal Regulations, and orders and guidelines provided by the DOE. Current planning activities and SDP requirements are specifically established in DOE Order 4320.16. In addition, the Laboratory's SDP has been developed in recognition of guidelines established in DOE's Site Development Planning Handbook and in planning management meetings and discussions held in 1991 and 1992.

LBL construction projects and site-development activities are reviewed by the DOE, other Federal agencies, and by state and local government and the public by procedures and documentation requirements established by the National Environmental Policy Act (NEPA). As required by the University of California in its management of the DOE laboratories, plans and specific projects may also undergo review consistent with the CEQA. These acts provide for the common development of environmental

documentation to minimize duplication and to provide for lead-agency jurisdiction by the DOE. Areas of regulatory and planning activities occur with the following principal agencies:

Federal

- Department of Energy — comprehensive oversight, audit, appraisal, and compliance responsibilities for program activities; site planning and construction; NEPA compliance; environmental, safety, and health planning and operations; radiation protection; facilities maintenance, personnel; legal affairs; and budgeting and other administrative activities. DOE requirements, reviews, and appraisal activities form an important basis for staffing levels and costs and the schedule of implementation of LBL direct and indirect operations. The DOE/SF Engineering and Facilities Management Division coordinates an annual review of LBL's site planning program.

- Environmental Protection Agency — standards for solid, liquid, and gaseous waste, National Pollution Discharge Elimination System permits, notification and emergency spill response, and requirements of the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA). Regulations promulgated by EPA help define LBL

environmental, health, and safety policies and affect costs and staffing of LBL programs.

- Department of Labor — occupational safety and health surveillance carried out by DOE in accordance with a Memorandum of Understanding with the Department of Labor. Occupational health and safety standards, including construction standards for the handicapped, are an essential part of LBL construction planning and program operations.
- Department of Transportation — shipping and waste-handling requirements and procedures. DOT standards define the requirements for shipping materials off site and influence schedules, costs, and activities for wastes from demolition, hazardous-waste handling, and other facilities and procedures.

State

- University of California — site planning and facilities design review and approval; environmental review procedures and approval; health and safety policies review and approval; personnel policies and procedures; budget policies and procedures review, approval, and audit; program review; and review and approval of other administrative policies and procedures.

- California Environmental Protection Agency (Cal-EPA) — established in 1991 and coordinates integrated waste management, water resources control, air resources, toxic substances control, pesticide regulation, and environmental health and hazard assessment.
- Department of Health Services — issues waste-handling-facility permits, reviews environmental reports for compliance with CEQA. Facility and permit requirements determine the capability, design, and operation of LBL sanitary and waste-handling facilities.
- California Water Quality Control Board and Regional Water Quality Control Board — as an element of Cal-EPA issues discharge permits, reviews environmental reports in compliance with NEPA or CEQA.
- California Air Resources Board — as an element of Cal-EPA, develops statewide air-quality policies, reviews environmental reports for NEPA or CEQA. Emissions regulations influence the costs of monitoring and emissions-control equipment.
- California Public Utilities Commission— governs rate structures and intrastate acquisition of natural gas and electricity.
- Department of Emergency Services — coordinates emergency response planning (local coordinating office in Contra Costa County).

- Water Resources Board — as an element of Cal-EPA, reviews environmental reports for NEPA and CEQA.

Local

- Bay Area Air Quality Management District — issues emissions permits, reviews environmental reports for NEPA or CEQA.
- East Bay Municipal Utilities District — provides water supply, establishes water-use and sewer fees, approves and monitors discharges to the sanitary sewers.
- Alameda County Health Care Services Agency — inspects sanitary facilities and food-handling operations, issues cafeteria operations permit.
- Cities of Berkeley and Oakland — maintain surrounding city infrastructure, including roadways, local sewers, and public services; monitors compliance program for subsurface tanks and groundwater. The cities review NEPA and CEQA documents and conduct a dialog with LBL and the University in planning, transportation, and environmental matters.

To implement programs consistent with applicable requirements established by these agencies, the Laboratory conducts a wide range of operational activities, including review, education, and report programs; for

example, environmental, safety, and health educational programs and the control and monitoring of all effluents, emissions, and solid-waste-handling activities.

The Laboratory also has established a Five-Year Long-Range Environmental Health and Safety Program that corrects existing deficiencies and makes longer-range projections (to the year 2010) for anticipated environmental requirements. These programs provide for utility systems improvements, such as improved ventilation and lighting, asbestos abatement, and soils clean up and the removal of groundwater contamination resulting from activities conducted during past decades. These programs are being established and conducted consistent with the policies promulgated by the responsible local, state, and Federal agencies.

LBL's construction schedules include provisions for NEPA as required by DOE and for CEQA review, as may be required by the University. These reviews allow for participation by all public and private agencies, groups, and individuals and afford the opportunity for public review and litigation, which can affect the schedule, mitigation measures, and the construction of facilities proposed in this plan. The general scope, total projected gross square feet, and the land use identified in this TSI are consistent with the 1987 LRDP, which has been approved by the UC Regents and has completed applicable Federal and state environmental review procedures, including issuance of an Environmental Impact Statement as required by UC.

For the renewal of the contract between DOE and the Regents of the University for management and operation of LBL, a supplemental Environmental Impact Report has been prepared. The report is based on information contained in the 1992 LBL Site Development Plan, which is the current implementation plan of the 1987 LRDP, and other planning documents.

LBL PLANNING PROCESS, ORGANIZATION, AND GOALS

Construction projects require approval of the DOE and the UC Board of Regents in terms of site location, design, appearance, and conformance with the LBL LRDP previously approved by the Board. An environmental evaluation of major projects is a prerequisite to these approvals. Although the Director of the Laboratory and the Chancellor of the Berkeley campus manage separate units of the University system, LBL projects that have a significant effect on overall planning for University property are coordinated with campus planners.

Site planning at LBL is coordinated by the LBL Associate Laboratory Director for Planning and Development and the LBL Associate Laboratory Director for Operations, who both report to the Laboratory Director (Figure 1-6). The LBL Institutional Plan, upon which the Site Plan is based, is the responsibility of the

Associate Laboratory Director for Planning and Development. Program goals and initiatives that form the basis for both the Institutional Plan and the SDP are developed with DOE by the LBL Director, the Associate Laboratory Directors, and the Directors of the nine LBL scientific divisions, in keeping with established Laboratory missions. The planning process at LBL includes the following steps (Figure 1-7).

- The Director's Office develops specific programmatic goals consistent with the LBL mission, research initiatives originating in the scientific divisions, and the objectives of the DOE.
- The Associate Laboratory Director for Planning and Development coordinates the development of the LBL Institutional Plan based upon input from the Laboratory Director, the other Associate Laboratory Directors, and the Division Directors. Major priorities are established by the Director in consultation with the Division Directors and the DOE.
- The Plant Engineering Department, of the Office of Operations, develops conceptual designs for the specific construction projects to be incorporated in the Institutional Plan. All conceptual designs are in conformance with the existing LBL LRDP and SDP.
- The Site Development Plan and plans for construction projects are reviewed by the Associate Laboratory Directors for

Operations and for Planning and Development, and are approved by the Director's Action Committee.

- Long-range planning is carried out by the Office for Planning and Development and the Plant Engineering Department with the assistance of specialized consultants in all appropriate fields. Plant Engineering has responsibility for the technical architectural and engineering information of this TSI document. Preparation of the SDP is coordinated by the Office of Planning and Development in conjunction with the preparation of the Institutional Plan and for integration with NEPA and CEQA.

At LBL, site planning is an integral element of a Comprehensive Planning Calendar. An annual cycle results in the definition of research needs and involves program review and planning that define facilities requirements. These requirements are reviewed by management as described above on an annual basis, which are closely evaluated against site plans and technical information (Figure 1-7). NEPA and CEQA reviews are an integral element of the LBL and UC/DOE reviews.

A Site Planning Working Group consisting of representatives of the three major LBL scientific program areas and relevant planning, operations, and administration representatives has been formed to advise the Planning and Analysis Office and the Plant Engineering Department. The Project Coordination Com-

mittee consists of the Head of the Plant Engineering Department and members from the Planning and Special Projects Office, Design Management Office; Environment, Health and Safety Division; Information and Computing Sciences Division, and Office of Assessment and Assurance. The committee reviews and coordinates initial project priorities for inclusion in SDP and TSI documents. Due to the hillside location and limited space available for development, LBL has made extensive use of functional area planning and detailed site-use studies to ensure the most beneficial long-term use of its available building sites.

- Proposed major revisions to the SDP and TSI are coordinated with the DOE/SF, UC System, and UC Berkeley Campus Planning Committee.
- Annual GPP work plans are developed by the Laboratory and are approved by DOE/SF.
- Annual validation reviews for major construction projects are held by DOE Headquarters staff.
- The SDP and TSI are continuously maintained and updated as a part of the normal annual planning cycle at LBL with review by, and input from, DOE/SF.

Fig. 1-6. Organization chart.

SITE-DEVELOPMENT PLANNING GOALS

The 1992 SDP and TSI are land-use guides for the main site that provide a comprehensive physical framework for carrying out the Laboratory's mission.

SDP planning is motivated by the need to rehabilitate existing obsolete facilities, to identify sites for anticipated programmatic growth, and to establish a planning framework under current environmental constraints in recognition of site amenities and the surrounding community. As a long-term guide for

development of the main site, the TSI includes the following goals and objectives.

The purpose of the TSI is to provide information for use by staff and technical personnel in the following areas:

- Summarize the Laboratory's history, setting, and planning processes.
- Define the physical environment for facilities improvements on the main site.
- Indicate redevelopment analysis and needs for buildings and utility systems.
- Summarize site amenities and constraints to protect the environment and landscape.
- Identify long-term master plan and needs for future improvements and outline a near-term 5-Year Plan.

The TSI presents a concise expression of the policy for the future physical development of the Laboratory, based upon anticipated operational needs of research programs and the environmental setting. It is a product of the ongoing planning processes and is a dynamic information source.

The 1992 TSI provides for new facilities associated with the Laboratory's redirection as a leading multiprogram laboratory. In addition, improvements are identified for rehabilitation and replacement of obsolete temporary buildings constructed since the 1940s. The site areas occupied by these proposed facilities are closely related to the 1987 LRDP, reaffirming the general framework established at that time.

Fig. 1-7. Schematic diagram of relationships among program planning, site planning, and budget planning and the review of facilities plans. Site and facilities plans are subject to continuing management review. NEPA and CEQA reviews are a part of LBL's Management review and UC and Federal Review.

2. EXISTING CONDITIONS

CONTENTS

2. Existing Conditions	2-1
Summary of Existing Activities	2-2
Physical Environment	2-4
Topography and Geology	2-4
Seismicity	2-7
Hydrogeology	2-7
Meteorology	2-9
Vegetation and Wildlife	2-10
Land Use	2-11
Circulation and Parking	2-14
Buildings and Other Structures	2-15
Functional Areas	2-17
Utilities	2-20
Water System	2-20
Sanitary-Sewer System	2-20
Natural-Gas System	2-22
Electrical Power System	2-24
Communications	2-27
Security Systems	2-29
Environment, Safety, and Health	2-29
Other Improvement Programs and Assessments	2-33

The Laboratory's research makes use of multidisciplinary collaboration and advanced engineering, computation, communications, fabrication, and other support facilities characteristic of a national laboratory. The Laboratory's facilities are planned, constructed, and maintained to support directly LBL's research programs and scientific goals, while maintaining compatibility with the University community and the physical setting.

SUMMARY OF EXISTING ACTIVITIES

In support of the National Energy Strategy, Lawrence Berkeley Laboratory research programs fortify the foundations of energy and environmental technology and will continue to be supported primarily from the Office of Energy Research (OER) and the Assistant Secretarial Offices of Conservation and Renewable Energy, Civilian Radioactive Waste Management, and Fossil Energy. The Assistant Secretary for Environmental Restoration and Waste Management will be increasingly important to support site-specific environmental restoration projects. In addition, other DOE offices, and the Nuclear Regulatory Commission, will support LBL programs. Work for

Others (WFO) supports about one-sixth of the Laboratory's programs. This section summarizes current LBL research programs, including anticipated program trends. LBL's scientific and technical programs are conducted under strengthened environmental, health, and safety guidelines for conduct of operations. Research facilities and programs are conducted to ensure the safety of all employees and the public, with environmental and safety management programs developed in close working relationships with OER.

Office of Energy Research

OER is the focus of fundamental science and engineering research activities at the Laboratory and is growing in selected areas of the Basic Energy Sciences and Life Sciences (see Chapter 3). Many of these programs are conducted in cooperation with industrial and academic research communities.

- For FY 1992 the Laboratory's contribution to national efforts in the Basic Energy Sciences (BES) includes completing and commissioning the Advanced Light Source (ALS) and developing advanced user facilities to support scientists in chemistry, biology, materials research, physics, and other fields.

- The 88-Inch Cyclotron, with its new Advanced Electron Cyclotron Resonance (AECR) ion source, provides the highest flux of heavy ions of any low-energy accelerator in the U.S. The Gammasphere detector, located at the Cyclotron, will open up new research opportunities in nuclear structure. The Bevalac is completing its pioneering studies of nuclear matter and advances in atomic physics, biomedical research, and related fields. The nuclear physics program at the Bevalac is projected to close in FY 1993 or FY 1994, completing 40 years of world-leading high-energy and nuclear physics accomplishments. The relativistic heavy-ion research program will be pursued with the STAR experiment at the Relativistic Heavy-Ion Collider (RHIC) and with lead beams at CERN (NA49).

- High-energy physics research continues to make major advances in detector systems with a sophisticated new detector for the SSC and plans for a B-factory detector. LBL contributes to the operation of current forefront facilities, including the D-Zero and Collider Detector Facility (CDF) at Fermilab.

- In the context of an advancing national program in health and environmental research, LBL's human genome, structural biology, and cell and molecular biology programs continue to provide the technical capabilities to improve the understanding of environmental and genetic control of diseases and normal functions. The biomedical program is improving diagnostic imaging systems and elucidating the metabolic basis of disease.

- In support of the national fusion research goals, LBL's programs in heavy-ion fusion accelerator research for inertial-confinement fusion and in neutral-beam development for magnetic-confinement fusion is expanding. These programs build on expertise in induction-linac systems and ion-source development.

- The Center for Advanced Materials (CAM) continues to pursue Laboratory goals for conducting longer-term research responsive to industrial needs and the transfer of the results of the work to industry. Expanded program activity in CAM is anticipated in thin-film research, studies of wear and mechanical properties of surfaces, atomic scale synthesis of materials, and enzymatic synthesis of materials.

- The National Center for Electron Microscopy (NCEM) continues to provide forefront research facilities for metallurgy, ceramics, and other materials research. Advanced microscopes for quantitative atomic resolution and analytical studies and studies of magnetic materials are under study to maintain the nation's research leadership.

LBL will continue providing OER programs with the most advanced engineering research for instrumentation, such as magnet technology devices and advanced control systems.

LBL continues to provide advanced engineering research in instrumentation and magnet technology. Stronger and more-precise magnets are being developed for many research applications based on emerging magnet materials and on composite coil designs.

LBL contributes to the magnetic-confinement fusion program through the development of neutral beams for heating and refueling reactor plasmas. LBL's work on both positive- and negative-ion-based neutral beams has been coupled with the research efforts at the Tokamak Fusion Test Reactor (TFTR) at Princeton, the Mirror Fusion Test Facility (MFTF) at Livermore, and the Doublet III at General Atomic Technologies in San Diego.

The Laboratory maintains a training and collaborative research program with Jackson State University (JSU), a historically Black institution, and with the Ana G. Méndez

Educational Foundation (AGMEF) in Puerto Rico, a major Hispanic institution of higher education. These cooperative research and training programs are expected to continue at the current level of effort. The newly formed Center for Science and Engineering Education has increasing numbers of programs for precollege and undergraduate students and faculty.

Conservation and Renewable Energy

The LBL program in Conservation and Renewable Energy (CRE) comprises a broad set of related activities that provides research support and technology development for energy conservation and renewable energy use, principally in the buildings and transportation sectors. The emphasis is on long-term laboratory-based research in the physical and chemical sciences. Program areas include energy storage and distribution, geothermal energy research and development, solar heat technology, energy use and building systems research, and state and local energy conservation assistance projects.

Office of Fossil Energy

LBL conducts research directed toward making coal more usable, including conversion to gaseous and liquid fuels and reduction of emissions. The research ranges from fundamental coal chemistry through laboratory-scale investigations of coal-conversion processes.

Office of Civilian

Radioactive Waste Management

LBL continues a strong multidisciplinary program of interrelated geoscience and geological engineering research important to the long-term underground storage of high-level nuclear wastes, e.g., characterization of deep geologic formations, determination of the physical and chemical processes occurring between waste-repository materials and the surrounding rocks, analysis of hydrologic and chemical transport mechanisms, and development of predictive techniques for repository performance.

Office of Policy, Planning, and Analysis

LBL continues a long-term project to collect and analyze energy-consumption information from less-developed countries (LDCs). Included in the study are twenty LDCs that account for most of the non-OECD oil imports and four large oil-exporting countries. The outputs of this study include a computerized database on LDC energy use and energy structure.

Work for Other DOE Facilities

LBL's contributions to research and development programs at other DOE facilities include studies of nucleation scavenging of smoke

particles and of laser-material interactions for LLNL; investigations of the direct absorption of solar energy for high-temperature receivers for Sandia National Laboratories; assistance to Oak Ridge National Laboratory (ORNL) in assessing renewable energy applications in developing countries; and support of Pacific Northwest Laboratory's efforts to develop energy-consumption standards for residences.

LBL's solar-biomass program, supported through ORNL, investigates the cultivation of hydrocarbon-producing plants, such as *Euphorbia*, with emphasis on crop yield, oil yield, process chemistry, and economics.

In addition, LBL is applying its building-energy expertise to Bonneville Power Administration (BPA) programs to develop cost-effective conservation measures and renewable resources to protect the environment while responding to growing demands for electricity.

Work for Others

Other Federal Agencies. Other federal agencies that fund research at LBL include the Agency for International Development, the Department of Defense (nonclassified research), the Department of Interior, the Environmental Protection Agency, the National Aeronautics and Space Administration, the National Institutes of Health, and the Nuclear Regulatory Commission.

Other Agencies and Institutions. Other agencies include the Electrical Power Research

Institute, the Gas Research Institute, the California Association for Research and Development, the California Energy Commission, and many private organizations. This work is reviewed by the Laboratory and DOE/SF to ensure that all applicable DOE regulations are satisfied.

PHYSICAL ENVIRONMENT

Topography and Geology

The Lawrence Berkeley Laboratory is site¹ on the western slope of the Berkeley Hills at elevations ranging from 500 to 1,000 feet above sea level. Building sites are constrained; 50% of the total Laboratory area has a slope greater than 25% (Figure 2-1).

Most of the LBL site is underlain by complex sedimentary and volcanic rock that has been folded and faulted since Cretaceous time. In general, the bedrock is relatively weak and weathers deeply; this weathering has produced a colluvial cover a few feet thick. Natural rock outcrops are few, although there are many rock exposures in cut slopes. The major geologic unit consists of poorly consolidated sandstones, siltstones, claystones, and conglomerates of relatively low strength and hardness. These rocks are blanketed by clay soils having high shrink-swell characteristics. The western and southern portions of the site are underlain by moderately well-consolidated shales,

TSI 927-9

Fig. 2-1. Site constraints and opportunities map.

TS 927-10

Fig. 2-2. Earthquake fault map.

siltstones, sandstones, and conglomerates. Throughout most of the upper elevations a volcanic unit overlays, and is interbedded with, the upper layers of the major geologic unit. Landslide deposits have been encountered in numerous locations within the LBL site. During the past 20 years the Laboratory has carried out a program of slope stabilization to reduce the risk of property damage due to soil movement.

The hilly terrain has often required grading and filling to provide suitable building sites. Consequently, landfills up to several tens of feet thick are present in some of the original ravines and depressions. Most of these fills were mechanically compacted during placement, and they have been satisfactory for foundation support.

Seismicity

The seismically active Hayward fault, a branch of the San Andreas fault system, trends northwest-southeast along the base of the hills below the Laboratory (Figure 2-2) and has the potential to produce an earthquake of approximately Richter magnitude 7.0.

The main part of the San Andreas fault system, which lies about 20 miles west of LBL, offshore beyond the Golden Gate, has a potential for a magnitude-8.3 earthquake. The Calaveras fault, another branch of the San Andreas, lies about 15 miles east of LBL. For an earthquake of given magnitude, the much-closer Hayward fault would produce the most-

intense ground shaking at the site.

To reduce the potential for damage from seismic activity, the Laboratory has carried out a comprehensive earthquake-safety program since 1971. All new facilities have been designed and constructed to resist the maximum credible earthquake estimated for the site. All existing LBL buildings were reviewed, and 32 were strengthened to meet current risk criteria.

Hydrogeology

Groundwater is of concern because of its potential effect on slope stability. The fractured bedrock underlying the Laboratory provides a percolation source that augments groundwater. Faults that cut through the bedrock tend to drain it, whereas clay layers act to impede flow. Water levels and hydrostatic pressure increase during the rainy season. The Laboratory has installed extensive groundwater detection and drainage systems (Figure 2-3) to increase slope stability. Water-table depths vary from 10 to over 90 feet across the site (Table 2-1).

Because of LBL's hillside location and moderate annual rainfall, surface runoff is a prevalent feature of the site. Two creeks and their tributaries provide natural drainage for the LBL site. The Laboratory has initiated an environmental restoration program to characterize and to remediate groundwater contamination, as indicated in subsequent sections on ES&H.

Table 2-1. Water Table Depths.

Functional Area	Depth (ft) ^a
88-Inch Cyclotron Research Area	>40
Central Research and Administration Area	16 – 30
Bevalac Accelerator Complex	18 – 50
Light Source Research and Engineering Area	>20
Shops and Support Facilities Area	65 – 100
Materials and Chemistry Research Area	10 – 15
Life Sciences Research Area	10 – 30

^a Depths represented as > X indicate existing borings have encountered no free water to that depth.

TSJ 927-11

Fig. 2-3. Storm drainage.

Meteorology

The climate of the LBL site is greatly influenced by the proximity of the Pacific Ocean and the maritime air that flows through the Golden Gate. Seasonal temperature variations are small; the mean summer and mean winter temperatures are 62°F and 51°F, respectively (Table 2-2). Generally, comfortable outdoor conditions prevail summer and winter.

Relative humidity ranges from 85–90% in the early morning to 65–75% in the afternoon. Annual insolation ranges from 65 to 75% of that theoretically available, and the average daytime cloudiness is about the same in summer and in winter. The number of heating degree-days is about 2,600 and of cooling degree-days about 150. Winds are generally less than 10 mph, usually blowing from the East in the morning and then switching to the West in the afternoon (Table 2-3).

Table 2-3. LBL Wind Data.

Direction	Speed (MPH)					%
	1-3	4-10	11-21	22-27		
N	0.59	0.97	0.05			1.61
NNE	0.61	0.61	.01			1.23
NE	0.89	1.10	0.20			2.19
ENE	1.10	1.52	.59	0.03		3.24
E	1.97	1.68	0.45	0.03		4.13
ESE	2.46	1.87	0.17			4.50
SE	3.31	3.53	0.39	0.01		7.24
SSE	3.59	4.76	1.13	0.01		9.49
S	3.12	4.44	0.70	0.01		8.27
SSW	3.36	3.86	0.18			7.40
SW	3.24	3.30	0.03			6.57
WSW	3.17	4.28	0.09			7.54
W	4.02	6.45	0.14			10.61
WNW	3.65	4.86	0.26			8.77
NW	3.33	3.19	0.13			6.65
NNW	1.64	2.24	0.08			3.96
CALM						6.60
TOTAL	40.05	48.66	4.60	0.09	0.09	100.00

About 95% of the average annual rainfall of 25 inches at the Laboratory occurs from October through April, and intensities are seldom greater than one-half inch per hour. Thunderstorms, hail, and snow are extremely rare. Consequently, LBL enjoys a Mediterranean-type climate, with favorable conditions for comfort control and energy efficiency. During the construction of the University's Lawrence Hall of Science and the Space Sciences Laboratory (in the late 1960s), a storm-sewer system was installed to provide for runoff intensities that could be experienced in a 25-year maximum-design storm. The system, with large conduits, special inlet and exit structures, energy dissipators, and hardened channels, was designed to accept runoff from future building sites in the easterly portion of LBL. These existing LBL storm drains are adequate to handle peak water runoff, based on a storm of 25-year recurrence and using the intensity-duration data for total seasonal rainfall (Table 2-4).

Table 2-2. LBL Temperature Normals (°F) by Month.

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Ann
Max	56.1	59.5	61.1	63.3	66.4	69.2	69.5	69.6	71.7	69.6	62.9	57.0	64.7
Min	43.2	45.8	46.0	47.6	50.3	53.0	53.9	54.7	55.6	52.9	48.3	43.9	49.6
Mean	49.7	52.7	53.6	55.5	58.4	61.1	61.7	62.2	63.7	61.3	55.6	50.4	57.2

Table 2-4. Rainfall Intensity and Probability.

Period (yr)	Intensity (in./hr)	24-Hour Duration (in.)
25	0.20	4.30
50	0.22	5.28
100	0.25	6.00

Vegetation and Wildlife

The most common and widespread types of vegetation are coyote brush, coast sagebrush scrub, oak-bay woodland, annual grassland, and eucalyptus plantations. In addition to these native or naturalized communities, landscaping around roads and buildings provides additional vegetation.

- **Baccharis Brushland.** This is the major vegetation cover type. It forms an open to dense shrub layer, approximately two meters tall in some areas. Coyote brush (*Baccharis pilularis* var. *consanguinea*) is the dominant plant species.
- **Coast Sagebrush Scrub.** This sparse-to-open, low (up to one meter tall) shrub type is found on the exposed south- and west-facing slopes of two spur ridges forming the northeastern boundary of the site. Coast sagebrush scrub is character-

ized by local dominance of California sagebrush (*Artemisia californica*).

- **Oak-Bay Woodland.** A dense woodland dominated by coast live oak (*Quercus agrifolia*) and California bay (*Umbellularia californica*) trees occurs in ravines. In general, the oak-bay woodland covers approximately 25% of the Berkeley Hills.
- **Annual Grassland.** Patches of grass generally occur within the project area on disturbed sites. The major grass species are introduced annuals such as soft chess (*Bromus mollis*), wild oats (*Avena* spp.), and wild barley (*Hordeum* spp.). Low broad-leaved plants commonly associated with annual grassland include rabbit-foot clover (*Trifolium arvense*), cut-leaved geranium (*Geranium dissectum*), and English plantain (*Plantago lanceolata*).
- **Eucalyptus Plantations.** Extensive stands of introduced eucalyptus trees occur in the project area. Blue gum (*Eucalyptus globulus*) occurs on west-facing slopes, and mixed stands of blue and red gum (*Eucalyptus tereticornis*) dominate the ravines. The trees reach a height of approximately 80 to 100 ft and are 10 to 40 in. in diameter. Eucalyptus plantations and other vegetation are being controlled under the Hill Area Fire Management Plan.

- **Landscape Plantings.** Extensive landscape plantings surround existing facilities. These plantings include Monterey pine (*Pinus radiata*), knobcone pine (*Pinus attenuata*), and redwood (*Sequoia sempervirens*). There are no naturally occurring stands of these trees on the site.

The surrounding area supports a variety of native wildlife including deer, fox, skunks, raccoons, and other mammals. Local birds include dove, quail, brown towhee, scrub and Steller's jay, common bushtit, Anna's hummingbird, wrenit, red-tailed hawk, and turkey vulture. The most-common reptiles and amphibians in the vicinity are the California slender salamander, ensatina, California newt, common garter snake, western fence lizard, and northern alligator lizard.

- **Oak-Bay Woodland Wildlife Habitat.** Among the most conspicuous and common wildlife using this habitat are black-tailed deer, western gray squirrel, deer mouse, bobcat, black-tailed jackrabbit, mountain lion, Steller's jay, acorn woodpecker, and bandtailed pigeon. Food, shade, and nesting sites are provided by the oak woodland. Other common birds include the California quail, mourning dove, and various hawks and owls.

- **Baccharis Brushland Wildlife Habitat.** Species using these areas include brush rabbit, gray fox, striped skunk, scrub jay, common bushtit, and coast garter snake.

- **Annual Grassland Wildlife Habitat.** These grassland areas provide suitable habitat for a number of small mammals and their predators, songbirds, and reptiles.

- **Eucalyptus/Bay Wildlife Habitat.** The ravines and drainage areas lined with these trees provide food, water, cover, nesting, and migration and movement routes for wildlife. Mammals such as raccoon and striped skunk are common residents. Black-tailed deer, gray fox, yellow warbler, tree swallow, great-horned owl, and red-tailed hawk are occasional visitors. Reptiles and amphibians such as the aquatic garter snake, Pacific tree frog, and bullfrog are common in and around quiet streams.

Portions of the area surrounding LBL have been designated natural-preservation and ecological-study areas by the University. The Laboratory has established landscape buffer zones to evaluate and manage the natural and introduced plantings within LBL's boundaries (Figure 2-4). No rare or endangered species are known to occur within the LBL site.

LAND USE

Laboratory activities are more efficiently conducted with buildings consolidated in core functional areas, with perimeters serving as buffer zones, transportation access, and parking; the SDP consolidates operations and facilities into seven functional areas to arrange new facilities for improved physical organization.

Eighty acres of the site are currently designated as buffer and open-preserve areas, whereas about fifty acres have been developed with buildings, roadways, and other improvements. Land-use planning analysis indicates that the Laboratory site has good potential, both for redevelopment of outmoded facilities (primarily in the Light Source Research and Engineering Area) and for future development. The compact LBL site enhances efficient interaction among support services and scientific program staff and encourages a more closely knit research community.

To facilitate appropriate siting of buildings and to enhance the relationship between land use, landscaping, and siting, the SDP establishes special buffer zones to protect valuable vegetation, to preserve important scenic vistas of the Bay, and to avoid unsightly exposures that face the city or UCB Campus. On the basis of these criteria and important geologic

TSI 927-12

Fig. 2-4. Existing landscape buffer zones.

Natural and introduced plantings provide buffers between Laboratory Functional Areas and adjacent communities.

and hydrologic limitations, including earth stability and hydrology, construction in the buffer zones is largely excluded.

Nine buffer zones are identified, eight of which are primarily adjacent to the Laboratory's boundary. The Bevalac Perimeter buffer zone includes the planted slopes around much of the Bevatron, because steep slopes make that area generally unsuitable for building sites. The West Strawberry Canyon buffer zone protects valued views and many of the cork oaks east of the cafeteria. The Light Source Buffer area, which includes a portion of the Original Laboratory Site and a section of the West Strawberry Canyon perimeter, contains a small grove of coast redwoods and dawn redwoods and several stands of eucalyptus. The East Strawberry Canyon buffer zone includes the dawn redwoods in that vicinity. These and other buffer zones, and the primary criteria that restrict their use as building sites, are identified in Figure 2-4.

Other factors considered in building location and land use include pedestrian and vehicular traffic circulation, views from the buildings, erosion control, surface-drainage patterns, fire control, landscape scale, and effective use of maintenance resources.

Although plans call for total building volume to increase, future building footprints will be more compact and in accordance with landscape plans; this, along with removal of outdated buildings, will enlarge open areas between future facilities. In addition, some

existing paved surfaces will be converted to landscaped open areas. Consequently, the Laboratory will be more attractive to its employees and to others alike. Planned entrances for new buildings, gathering areas, and other focal points will preserve or provide views across the Bay.

The Laboratory has developed a landscape plan and established landscape-related criteria for new building sites; e.g., many existing mature trees have been preserved to serve as design elements. Four categories of landscaping sustain or augment the natural grassland, shrub, and forest areas of the hillside.

- Natural-state areas are the most distant from buildings, consisting primarily of native grasses, low-growing ground cover, and trees (primarily in gullies and along north-facing slopes).
- Drought-tolerant low-cover areas are closer to buildings and consist of fire retardant evergreen plantings.
- Drought-tolerant high-cover areas incorporate fire-retardant trees and shrub masses, often adjacent to buildings.
- Introduced-planting areas requiring more intensive management and supplemental watering during the summer are immediately adjacent to buildings and, frequently, along pedestrian paths and around decks, picnic areas, and viewpoints.

The major landscaping goals are to complement the hillside setting, to protect against the potential of fire, to unify the site visually, to relate the site to adjacent vegetation, to prevent erosion, to provide amenities to users of the site, and to provide a buffer between functional areas, buildings, and adjacent properties.

CIRCULATION AND PARKING

The LBL site is served by an east-west traffic circulation system that conforms to the hilly topography. Vehicles enter LBL through gates attended by Laboratory Protective Services personnel. These gates are open for various periods according to the commuter patterns; only the main gate, near the east end of Hearst Avenue, is open 24 hours. The gates are situated to help channel traffic and to minimize on-site congestion. Due to LBL's compact site, many buildings are within walking distance of each other; the many footpaths and stairs provide good access between buildings and roads. The site is too steep and hilly, however, for a system of bicycle paths; the few bicyclists use the roads. The Laboratory's roads, parking, and pedestrian walkways generally provide for efficient movement of personnel and materials. In older areas of the Laboratory, however, the circulation system is substandard, with varied, narrow, and indirect vehicular and pedestrian access.

Parking space is provided for about 1,850 vehicles (including 275 Laboratory vehicles). A range of 1.7 to 2.0 persons per parking space with a recommended ratio of 1.7 persons per space will permit a 10% vacancy factor. The Laboratory has a three-level parking-permit system that provides for nearby parking for upper management, reserved spaces for employees with medical permits and for senior scientific and management staff, and general parking for all others. Van pooling and car pooling are encouraged by providing special parking for "pool" vehicles.

About 6,600 vehicle trips per day are made to LBL. Approximately 50% of LBL employees and guests live within a four-mile radius (15-minute driving time) of LBL. The peak vehicle traffic occurs between 4:30 and 5:30 p.m., reaching 650 vehicles per hour.

1987 traffic studies indicate that 64% of all LBL employees drive alone to the site (single-occupant autos). Seven percent use car pools or van pools; 13% use public transportation; 7% use bicycles; 7% walk; and 2% use two-wheel motor vehicles. Public transit users rely on the LBL off-site shuttle bus to reach the Lab.

Parking demand in the densely populated areas at LBL generally exceeds the number of

available spaces. Trailers serving as temporary office and storage space have also been located in parking lots, further reducing available parking space. The needs for building and parking space, combined with the sloping terrain and the cost of providing parking structures, place a premium on land occupied by existing parking lots.

Transportation by large semitrailer truck can be slow because of the many steep grades and sharp curves. This can cause traffic delays, for example, when a heavy truck is climbing at three miles per hour on the two-lane main entrance road, where passing is not permissible.

At present, the Laboratory operates both on-site and off-site buses to facilitate circulation and access (Figure 2-5), to minimize the use of personal vehicles for transportation, and to encourage use of mass-transit systems, such as BART and AC Transit. The on-site bus service, coupled with a system of pedestrian paths, helps reduce on-site vehicular traffic yet allows access to every building on the site within a reasonable amount of time. Plans call for increasing service commensurate with population increases (Table 2-5).

BUILDINGS AND OTHER STRUCTURES

The LBL building-and-space inventory includes many types of facilities, including on-site permanent buildings, on-site trailers and miscellaneous structures, off-site leased building space, and the UCB Campus space assigned to LBL. (An analysis of this space is presented in Table 3-2 in Chapter 3.)

The Laboratory's on-site space (about 78% of the gross) consists of approximately 1,621,100 gsf with an approximate 70% efficiency. The net usable on-site space is approximately 1,134,800 sq ft. With a typical daily on-site population of 3,000 employees and participating guests, the average net occupied office space is about 131 sq ft per person. About 4% of the on-site space consists of trailers or other temporary structures.

One of the Laboratory's divisions, Life Sciences, is partly housed on the UCB campus; a second, Structural Biology, is housed totally on campus, except for a small facility (the National Tritium Labeling Facility) in the Shops and Support Facilities Area. Together, these

two divisions occupy about 41,000 net sq. ft. LBL personnel also occupy other space on the UC campus, at the UC Richmond Field Station, leased space in the City of Berkeley, and at the Stanford Linear Accelerator Center (SLAC). Overall, about 22% of LBL personnel occupy off-site space.

On the main site, of the 1.6 million gsf in buildings, 37% are adequate buildings, 50% are substandard but can be made adequate, and 13% are substandard and should be demolished or removed (Appendix C).

Fig. 2-5. On- and off-site bus service.

Table 2-5. Transportation and Parking Characteristics.

Characteristic	1991	Future
Parking		
Total spaces	1,847	2,410
Population/space ratio	1.7	1.70
Peak Vehicle Trips (per hour)	642	950
Off-site Shuttle Service		
Trips/day	72	82
Passenger capacity/day	2,870	3,300
Passengers carried/day	1,400	1,950
Use (%)	49	59
On-site Shuttle Service		
Trips/day	96	110
Passenger capacity/day	1,862	2,090
Passengers carried/day	1,000	1,330
Use (%)	54	64

FUNCTIONAL AREAS

The natural constraints of the site coupled with the desirability of maintaining compact and interactive programmatic development have led to the delineation of the LBL site into seven functional planning areas (Figure 2-6). These subdivisions of the site, which are generally identified with specific research programs and/or support facilities, have been individually studied to ensure effective short- and long-range use (Appendix A). It is in this context that more-specific program premises are best described for relevance to site planning.

88-Inch Cyclotron Research Area

The functional area of 53,400 gsf designated as the 88-Inch Cyclotron Research Area is located on a hillside terrace near the main entrance to LBL. Functionally, the area is dedicated entirely to the 88-Inch Cyclotron and its close support facilities. Due to the topographical constraints of the site, expansion of the existing facilities is rather limited.

Central Research and Administration Area

This functional area of 488,900 gsf houses the LBL Director's Offices and the main offices for Administration, Applied Science, Earth Sciences, Engineering, Nuclear Science,

Physics, Accelerator and Fusion Research, Information and Computing Sciences, and Planning and Development. It includes the majority of LBL's light laboratories and support offices as well as the cafeteria.

The buildings in the 50-70 Complex provide the major portion of light laboratories for Applied Science, Physics, Earth Sciences, and Nuclear Science.

A shortage of light laboratories and offices for existing programs remains, and a number of laboratory spaces in the buildings of the 50-70 complex are still used for offices. An important element of the SDP is construction of economical additions to existing buildings to provide office space that will permit reclamation of valuable laboratory space.

Building 90 and its trailer complex currently house Plant Engineering, Personnel, Applied Science, and Mechanical Engineering. Since parking is severely limited in this area, the trailers will be removed as soon as replacement space becomes available.

Bevalac Accelerator Complex

This functional area of 355,000 gsf encompasses the Bevalac/SuperHILAC Accelerator Complex, including heavy-laboratory experimental areas, cryogenic support facilities, staging areas, associated offices, and facilities for advanced accelerator research and development. The area has an extensive array of support utilities, heavy handling equipment, and related resources.

TSI 927-14

Fig. 2-6. Functional areas with existing buildings.

Over many years, this area has been studied intensively in connection with major upgrading projects and experimental-area expansions. A number of initiatives for advanced accelerators were developed into conceptual designs incorporating the extensive support facilities that now serve the Bevatron Area (e.g., VENUS, Tevalac, Relativistic Nuclear Collider). Other site-related studies have been carried out for designs of existing and future large detector systems. These studies have established a thorough understanding of the potential for physical expansion and development of the Bevalac Accelerator Complex area for accelerator/detector-based physics beyond the 1994 potential decommissioning of the Bevalac.

Light Source Research and Engineering Area

This functional area encompasses 15 acres and includes buildings enclosing 362,300 gsf of space. The dominant feature of this area is the dome of Building 6, which originally enclosed the 184-inch Cyclotron and which is now being remodeled to contain the Advanced Light Source (construction began in 1987 and is scheduled to be completed in 1993). Generally, the area around Building 6 contains older buildings and extensive utilities that were developed in the 1940s.

In recent years, major research work housed in the Light Source Research and Engineering Area has been focused on the Magnetic Fusion

Energy (MFE) Program and the Biomedical Program. This functional area also includes the LBL medical-services facility, the new LBL fire station, central stores, and the electronic and mechanical technician shops. The newer buildings and a few of the older buildings, such as Building 6, are quality buildings that will be preserved. The others are obsolete and inadequate for modern research and development and must be replaced.

This area has excellent geographical and geotechnical qualities and natural topography especially suited to building sites for high-technology facilities. Presently, the site has a substandard traffic circulation system with varied, narrow, and indirect vehicular and pedestrian access. Parking, pathways, and service access are constrained, overlapping, and inefficient. Existing utilities systems and load centers have ample capacity but are aged, obsolete, and in need of rehabilitation.

The pressing need to replace or rehabilitate many of the existing buildings, roadways, and utilities in the Light Source Research and Engineering Area, coupled with its physical attributes, makes the area a prime candidate for new light- and heavy-laboratory development. In 1983 and 1988 comprehensive site utilization studies were conducted that are integrated with conceptual design reports for line-item projects, providing in-depth solutions for both short- and long-range redevelopment for the Light Source Research and Engineering Area.

Materials and Chemistry Research Area

This functional area of 124,000 gsf encompasses the Materials and Molecular Research Laboratory, the National Center for Electron Microscopy, and the Surface Science and Catalysis Laboratory (SSCL).

Life Sciences Research Area

This functional area of 69,200 gsf encompasses 7 acres in the upper reaches of Strawberry Canyon and includes potential sites for a Human Genome Laboratory and facilities to consolidate research in Cell and Molecular Biology. Existing buildings include the Biomedical Laboratory, the Laboratory for Cell Biology, and a new Waste Handling Facility. Potential sites were carefully considered in a comprehensive Site Utilization Study carried out in 1980, which was used in siting the Human Genome Laboratory. More recently a 1991 study established this area as a prime candidate for future growth.

Shops and Support Facilities Area

This functional area of 167,800 gsf encompasses the Craft Shops, Supply Services, Transportation, the Motor Pool, the Mechanical Shops, the Environmental Health and Safety Department, and the National Tritium Labeling Facility. Development of this functional area

began with construction of the LBL Corporation Yard in 1960, and, when the existing complex was essentially completed a few years later, the Corporation Yard was split up and moved to several locations within the LBL site.

UTILITIES

Water System

The Laboratory's primary water supply is the East Bay Municipal Utilities District (EBMUD) Shasta Reservoir. The Laboratory's high-pressure fire and domestic system is supplied from this reservoir. A secondary source is EBMUD's Berkeley View tank, with a capacity of approximately 3.0 million gallons, connected to LBL by EBMUD piping. Water mains have automatic shutoff valves in case of breaks.

The LBL water-distribution system contains several backup safety distribution loops and is valved to provide control in case of emergency. The system operates entirely by gravity flow, requiring no pumps or energy consumption for operation within the Laboratory (Table 2-6 and Figure 2-7). The Laboratory has two 200,000-gallon fire-protection storage tanks. One is located near Building 75 in the Shops and Support Facilities Area and the other near Building 71 in the Bevalac Accelerator Complex. Diesel-powered pumps will maintain a

reliable flow for the fire-protection system during emergencies.

Improvements to the water system are required, and Phase I of a mechanical utilities rehabilitation project addresses the most-critical needs. Chapter 4 provides an analysis of mechanical utilities.

Sanitary-Sewer System

The west-side LBL sanitary-sewer system connects to the City of Berkeley sewer main in Hearst Avenue. On the south side of the Laboratory, a second connection is also made to the City of Berkeley system. The Laboratory

Table 2-6. Site Mechanical Utilities—Water Distribution System.

Functional Area	Existing		Additions Planned
	Length (ft)	Utilization (%)	Life (yr)
88-Inch Cyclotron Research Area	1260	50	25+
Central Research and Administration Area	7405	50	25+
Bevalac Accelerator Complex	7060	50	25+
Light Source Research and Engineering Area	5360	50	25+
Shops and Support Facilities Area	9430	50	25+
Material and Chemistry Research Area	2650	50	25+
Life Sciences Research Area	1460	50	25+
			No
			Yes
			No
			Yes
			Yes
			Yes
			Yes

Fig. 2-7. LBL water distribution system.

monitors its discharges for the presence of certain chemicals and radioactivity (Table 2-7 and Figure 2-8).

Natural-Gas System

Natural-gas service to LBL is supplied by the Pacific Gas and Electric Company (PG&E) (Table 2-8 and Figure 2-9). A 6-in. main in Hearst Avenue feeds the PG&E-owned meter station at the entry to the LBL site. Additionally, a University-owned 2-in. main in Centennial Drive feeds only Buildings 73 and 74, which are supplied on a firm rate. Chapter 3 analyzes the condition of this system, and Chapters 4 and 5 describe plans for systematic replacement of aged and/or deteriorated components.

The Hearst Avenue meter station contains one meter for interruptible gas and one meter for firm gas, which is supplied to several LBL buildings. PG&E main pressure is about 40 psi, which is reduced to 13 psi at the Hearst Avenue meter station.

The 13-psi distribution pressure is further reduced at various regulator stations to serve either a group of buildings or in some cases a single building. Building pressure is in the range of 0.25 to 1.25 psi. Earthquake shutoff valves have been installed at the entrance main and outside major buildings to reduce the possibility of explosions following a quake. The natural gas is principally used for space and water heating; there is no central heating plant at LBL.

Table 2-7. Site Mechanical Utilities—Sanitary-Sewer System.

Functional Area	Existing			Additions Planned
	Length (ft)	Utilization (%)	Life (yr)	
88-Inch Cyclotron Research Area	880	50	25+	No
Central Research and Administration Area	4580	50	15–25+	Yes
Bevalac Accelerator Complex	3715	50	15–25+	No
Light Source Research and Engineering Area	2990	50	15–25+	Yes
Shops and Support Facilities Area	4330	50	15–25+	No
Material and Chemistry Research Area	1100	50	15–25+	No
Life Sciences Research Area	790	50	15–25+	Yes

TSI 927-16

Fig. 2-8. Sanitary sewer system.

Electrical Power System

The PG&E supply system consists of two overhead 115-kV, 3-phase, 60-Hz transmission lines with a joint capacity of approximately 100 MW. Both transmission lines feed power from PG&E's Sorbante switching station to the LBL Grizzly main substation.

Long- and short-term improvements to both mechanical and electrical utilities are identified in Chapters 4 and 5, respectively.

Table 2-8. Site Mechanical Utilities —Natural-Gas Distribution System.

Functional Area	Existing		Additions Planned
	Length (ft)	Utilization (%)	
88-Inch Cyclotron Research Area	970	50	0
Central Research and Administration Area	4770	50	750
Bevalac Accelerator Complex	1940	50	550
Light Source Research and Engineering Area	1740	50	1150
Shops and Support Facilities Area	2925	50	1000
Material and Chemistry Research Area	1320	50	800
Life Sciences Research Area	1655	50	1300

TSI 927-17

Fig. 2-9. Natural gas system.

TSI 927-18

Fig. 2-10. Site electrical system.

COMMUNICATIONS

Telephone System

The Laboratory owns and operates an Integrated Communications System (ICS) that provides both telephone and switched data services. The ICS includes an extensive system of underground ducts (Figure 2-11), manholes, copper and fiber-optic cables, building entries, distribution closets, and wiring. The underground duct system was significantly expanded as part of the ICS installation project, which

also included installation of an entirely new cable and wire plant. LBL underground ducts also contain the now-unused Pacific Bell cables, which can be removed, as necessary, to free space in the ducts. The ICS is based on an IntelCom IBX S/80 digital switch that provides switched voice and data services and trunks to external networks, including Pacific Bell (the local telephone company), AT&T, and the Federal Telecommunications System (FTS). The ICS supports a voice system that currently serves 4,500 stations, with a capacity of 7,500 voice lines.

Computer Network

LBLnet is a Laboratorywide computer network comprising underground fiber-optic cables, coaxial and wire systems in buildings, and active components. LBLnet is connected through gateways to external networks, including HEPnet, NSFnet, MILnet, BARRNet, ESNET, and the UCB Campus network. LBLnet currently supports more than 2,000 attached computers, workstations, and printers using various networking protocol suites, including the Internet, DECnet, and Xerox Network Services protocols.

Radio, Television, and Wide-Band Communications

The Laboratory has radio and wide-band communications systems operating on eight VHF channels and on two microwave channels. There are over 500 fixed and portable radio units operating to serve off-site and on-site transportation, a repeater link to LLNL, LBL Protective Services, the Fire Department, Crafts and Maintenance forces, individual radio paging, and the Director's Office and Building Managers Emergency Command Center. The two microwave channels operate at 7 GHz to provide computer-data and video-conferencing links to SLAC. A video-conferencing system using black-and-white television and remote monitors has been set up in several buildings. A television surveillance system is also used in computer rooms and high-radiation areas and for other security needs.

Table 2-9. Site Electrical Utilities.

Functional Area	Condition	Utilization	Remaining Life
88-Inch Cyclotron Research Area	Poor	Adequate	None
Central Research and Administration Area	Poor	Adequate	None
Bevalac Accelerator Complex	Poor	Adequate	None
Light Source Research and Engineering Area	Poor - Excel ^a	Adequate	20 years ^a
Shops and Support Facilities Area	Poor	Adequate	None
Materials and Chemistry Research Area	Poor	Adequate	None
Life Sciences Research Area	Poor	Adequate	None

^a ALS 12-kV Power System. The remainder of this area's 12-kV power system has exceeded its useful life and is in poor condition.

TSI 927-19

Fig. 2-11. Integrated Communications System.

Public-Address System

A Laboratory-owned public-address system links the entire LBL area, providing paging for Laboratorywide announcements related primarily to health, safety, and emergency situations. This system is expanded to each newly constructed building and facility through rigid conduits in underground raceways installed at the time of construction.

SECURITY SYSTEMS

Fire-Alarm System

The LBL fire-alarm system completed in 1985 uses solid-state programmable equipment and two main looped trunk lines with redundant paths. The looped trunk lines feed alarm information to the central supervising station in the Fire Station. Redundant drops from the main trunk loops serve each building. Both Loop #1 and Loop #2 serve the entire Laboratory area. The LBL-occupied buildings on the UCB campus are served by an isolated trunk from the Fire Station and by the UCB campus fire-alarm system. The Fire Station console consists of a prioritized CRT alarm display, a backup annunciator system, and a computer-aided dispatch system. The multialarm system monitors 1,650 points.

All major buildings and most minor buildings have local alarm (bell) evacuation systems. High-value areas have special protection systems with ionization-type smoke detectors as the primary detection means. Improvement of bell systems and smoke detection in several buildings is planned.

Plant-Protection Card-Key System

A magnetic card-key system monitors entry into Laboratory buildings and limits access to rooms or areas for reasons of security or health/safety. The card-key system is operated by LBL Protective Services using a dedicated computer that identifies the user and then records and controls access.

ENVIRONMENT, SAFETY, AND HEALTH

It is the policy of the Lawrence Berkeley Laboratory to integrate environment, safety, and health (ES&H) performance into LBL's plans and into the conduct of all of its operations to ensure employee and public safety and the protection of the environment. The Laboratory has developed institutional ES&H goals to guide its integrated ES&H program including site planning. The ES&H goals are to:

- Provide forefront solutions to the management of environment, health, and safety challenges;
- Identify and reduce risks to the environment and to the safety and health of employees and the public;
- Integrate and implement ES&H plans and programs through line management activities;
- Deliver ES&H services in full regulatory compliance with a highly qualified staff;
- Involve and train all employees in strengthening ES&H performance and programs.

Underlying these goals is a commitment to ES&H performance through planning and quality management of the Laboratory's programs and in its conduct of operations. LBL's current efforts respond to LBL's Corrective Action Plan for Tiger Team Assessment. The Laboratory has also developed a new health and safety five-year plan and is developing implementation programs for the DOE Environmental Restoration and Waste Management five-year plan. These efforts include a renewed commitment to ES&H through an effective Corrective Action Plan.

Environmental Evaluation and Status

Environmental monitoring (air, water, and land) is conducted by LBL's Environment, Health and Safety Division personnel. Monitoring stations for each component are represented in Figure 2-12. Off-site sampling is conducted to provide information regarding public safety. For a listing of regulatory agencies that govern environmental compliance see Chapter 1, Regulations and Planning Requirements.

Air

Potential air pollution consists of chemicals and radionuclides released from stacks at laboratories. Each building is actively monitored for compliance with applicable air-quality standards, and present release levels meet these safety standards. Experiments that could generate noxious fumes or vapors are confined to fume hoods. Airborne wastes are minimal due to the small amounts of chemicals involved in the research.

Processes with a potential for pollution are reviewed during conceptual stages to identify those that require "Permits to Construct" from the Bay Area Air Quality Management District.

Water

In chemical laboratories, small amounts of water-soluble chemical wastes are allowed to be discharged to sanitary-sewer drains, following guidelines published in the *LBL Health and Safety Manual*, PUB-3000. Wastes from plating or metal cleaning shops are collected and pretreated before discharge to sanitary drains. In accordance with LBL policy, non-water-soluble chemical wastes will be collected at their points of generation, segregated into compatible groups, placed in approved shipping containers, and transported to a DOE site for burial or recycling.

Chemical wastes are not discharged to storm drains or streams. Other potential water pollution sources are from contaminated soils, which are discussed in the following section. As noted below, LBL is conducting a labwide characterization study of water and soil contamination.

Land

Sources of potential soil pollution are accidental spills from routine operations, transportation of materials, or leaking underground tanks. Solvents, fuels, and other hazardous liquids are controlled through EH&S

Division procedures and training. Improvements include construction of new storage containers, the installation of overflow/leak containment, and the use of impervious materials.

Collection and processing of hazardous wastes are performed in a specially designed Hazardous Waste Facility that includes the proper equipment and configuration as defined by regulating authorities. Hazardous waste is consolidated and packaged to meet U.S. Department of Transportation regulations and then trucked to approved DOE disposal sites. Nonhazardous wastes are regularly collected at LBL by the University and transported to a recycling company, where 90% of the volume is recycled.

Environmental Restoration and Waste Management

LBL environmental management site projects are supported through the DOE Office of Environmental Restoration and Waste Management (EWRM). They are directed toward restoring environmental conditions at the Laboratory and to improving the management of waste handling operations in support of DOE's national environmental objectives.

TSI 927-20

Fig. 2-12. Environmental monitoring locations.

The corrective actions achieve and maintain required low exposure and risk levels; the environmental restoration program includes the assessment and characterization of contamination and the closure of the existing Hazardous Waste Handling Facility. Increased support for the waste management program is necessary for the proper management of radioactive and hazardous waste. The waste management program supports the construction of a new Hazardous Waste Handling Facility. These programs provide for compliance with DOE and other Federal regulations and for meeting requirements established by state and local agencies. The Environmental Management (EM) 5-year plan is focused on three Environmental EM programs for restoration and management activities:

- **Environmental Restoration.** Assessment, characterization, and remediation of chemical contamination of soils and groundwater and the closure of the existing LBL Hazardous Waste Handling Facility and the Bevalac.
- **Corrective Activities.** Corrective actions to achieve compliance with environmental regulations that protect soils, groundwater, and air and also prevent chemical discharges to sewers. Essential corrections are to laboratory ventilation systems, deionization systems, sanitary sewer systems, chemical storage tanks, and wastewater treatment units.

- **Waste Management.** Waste management program for continuity of hazardous and radioactive waste handling operations, disposal, waste minimization, planning, and the management of the construction of a new Hazardous Waste Handling Facility. Additional funding of waste management operations will be necessary to meet mandatory program requirements.

The Laboratory's systematic and prioritized input to the EM Five-Year Plan supports DOE's national environmental restoration and waste management goals. The plan responds to specific environmental conditions at the Laboratory and includes facilities and operating programs for managing those conditions to maintain air quality, surface water quality, and groundwater quality.

Operational Safety

No significant radiation levels are expected in accelerator experimental areas. Accidental exposure to personnel is limited primarily by passive systems (shielding) and by active engineering and administrative controls, such as electrical interlock systems to prevent access to radiation areas, audible and visible warnings, and surveillance of experimental operations. Radiation levels at the fence line are not expected to increase as a result of LBL operations.

Continuing reviews during the conceptual and design stages and preparation of an Operational Safety Procedure (OSP) are mandatory for all potentially hazardous experiments. The OSPs are reviewed by the LBL EH&S Division and the appropriate subcommittee(s) of the LBL Safety Review Committee. As a standard procedure of the LBL safety program, all areas are regularly inspected for compliance with Federal Occupational Safety and Health Administration (OSHA), DOE, and LBL standards. Routine design review of equipment and laboratory facilities and review of experimental procedures are expected to reduce all hazards to a "low-hazard" classification.

Corrective Action Plan

LBL's Tiger Team Assessment Corrective Action Plan, completed in September 1991, addresses the findings and concerns of the Tiger Team as well as the 1989 Technical Safety Appraisal. The Laboratory and DOE/SF developed 409 tasks with subsidiary milestones to correct the findings and concerns and eliminate the underlying root causes. These root causes addressed the need for:

- Greater formality of operations and effective verification of the accomplishment of environment, safety, and health requirements;

- More effectively addressing the challenge of the demands of ES&H and the urgency of incorporating these demands into LBL operation; and
- Providing DOE program direction and oversight that places adequate emphasis on environmental, safety, and health requirements.

LBL has closed out 60% of the OSHA findings and has fully corrected the Category II concerns or reduced them to lower levels. However, addressing all the root causes, concerns, and findings will require complete implementation of the Corrective Action Plan, which will require additional resources from the Office of Energy Research and the Office of Environmental Restoration and Waste Management. LBL is allocating significant new resources to the Corrective Action Plan, including additional office and support facilities described in subsequent chapters of this TSI.

Safety and Health Five-Year Plan

The Laboratory has developed a prioritized five-year plan for Safety and Health Activities that includes the existing core program of safety and health services and activities, additional core support, and specific projects needed to fully meet all LBL and DOE safety and health goals. LBL planning has contributed to the development of the ER

prioritization system to allocate and rank necessary activities based on quantitative risk reduction criteria. GPP and MEL-FS projects included in this TSI address the ES&H five-year plan needs.

Waste Minimization Plan

LBL's waste minimization program is an organized, comprehensive, and continual effort to systematically reduce hazardous, radioactive, and mixed waste generation. The Waste Minimization and Pollution Prevention Awareness Program are designed to eliminate or minimize pollutant releases to all environmental media from all aspects of the site's operations. These efforts offer increased protection of public health and the environment. They will yield the following additional benefits: reduce waste management and compliance costs; reduce resource usage; reduce or eliminate inventories and releases of hazardous chemicals; and reduce or eliminate civil and criminal liabilities under environmental laws.

Other Improvement Programs and Assessments

The Laboratory has implemented a long-range plan to improve the condition of the physical plant and operations with respect to maintenance, repair, safety, and the environ-

ment. Highlights of these improvements are described below. The 20-Year Plan goals for the Laboratory are presented in Chapter 4; specific implementation over the five-year planning period is described in Chapter 5.

Seismic Safety

All physical plant facilities have been reviewed for seismic safety (Appendix A). Since 1971 over 34 buildings with significant seismic deficiencies have been strengthened to meet the new standards. Other improvements in earthquake-resistant facilities and emergency preparedness include the following:

- Two on-site water-storage and emergency-pumping stations have been constructed to provide water for fire protection if public supplies are lost.
- Three emergency command centers have been established and hardened for earthquake safety.
- Emergency generators, communication systems, medical facilities, the firehouse, and other life-line systems have been obtained, or strengthened, for use following an earthquake.
- Earthquake shutoff valves have been installed on all natural-gas mains.
- An emergency telephone system has been installed.

Slope Stability

Fifteen areas of instability have been stabilized on a priority basis. A sophisticated groundwater-monitoring and soil-drainage system was installed, including many vertical wells and horizontal hydraugers that have been effective during extremely wet winters. In response to a 1974 analysis of potential slope instability during a major earthquake, critical underground water, natural-gas, and electrical lines have been relocated. Slope stability has been improved along the realigned portion of the Upper Hill Road as a result of the Roadway Safety Improvements Project (see below). A new Slope and Seismic Stability project is required to correct problems in the Building 51/71 area.

Underground Utilities Improvements

All underground water and sewer systems have been inspected photographically to determine preventive maintenance and replacement tasks for short- and long-term funding. A recently completed construction program replaced a major portion of the underground utilities (potable-water, low-conductivity-water, compressed-air, and sanitary-sewer systems), as well as above-ground cooling towers, in the Light Source Research and Engineering Area. Rehabilitation of all older 12-kV cables is planned as MEL-FS funds become available.

Roadway Safety Improvements

The Laboratory's road system was established when design and safety standards were less stringent and there were few pedestrians. Current conditions require improvements such as vertical and horizontal realignment of roads, widening of traffic lanes, replacement of base and paving materials, and separation of vehicle and pedestrian traffic. A roadway-safety improvement project was completed in 1986 in the Light Source Research and Engineering Area that provided a safer passageway for both vehicles and pedestrians. Three phases of Road Rehabilitation Projects are proposed to improve or replace the remaining Laboratory roadways systematically.

Energy Management Improvements

LBL energy use has been reduced over the last several years by improvements both in operations and in building design. The installation of natural-gas and electrical metering throughout the site includes an Energy Monitoring and Control System (EMCS), which employs 93 electric meters and 44 gas meters. Meters are regularly read, and a database has been established. This database is used in the In-House Energy Management Program to identify conservation opportunities and to monitor performance. The first load center became operational in FY 1985, and actual energy savings for the targeted cooling-

tower fans exceeded the original estimates. Additional funding has been received for EMCS II, which will result in an additional energy savings of 4,040 million Btu. Currently LBL is surveying improvements for:

- Boiler consolidation
- Outside air free cooling
- Chiller efficiency optimization
- Electrical peak load tracking; and
- Motor performance.

LBL has conducted many retrofits for energy conservation, including pumps, magnets, chillers, compressors, and lighting. LBL has reduced lighting-energy use through a delamping and re-lamping program initiated in the late 1970s. Old ballasts are replaced with energy-efficient units on an ongoing basis.

In FY 1991 the Energy Monitoring and Control System (EMCS) continued to expand. Included were the Building 2 Controls Upgrade, the final phases of EMCS at Buildings 46 and 55, the Building 88 HVAC Controls, Building 80 room pressure and temperature control, Building 71 HVAC EMCS and VFD installation, and the Building 83 HVAC Controls on the main supply fan. At the Building 50 Complex, retrofit work was substantially completed in FY 1991 on the lighting efficiency upgrades. Process energy was further reduced with the completion of the Bevalac Power Supply Main Rectifier Upgrade and the removal of the Plate Voltage Modulator at the

Linac RF Amplifier. Final phases of this project were completed in FY 1991. Automation designs for Buildings 74, 90, and 50 were also completed.

Load management continues to be an important aspect of the LBL energy-management program. The Laboratory uses both firm and interruptible power, which has allowed LBL to purchase less-expensive power directly from the Western Area Power Administration (WAPA). Use of computer-process control and tight manual scheduling involve coordination of the various loads, resulting in reduced demand and charges. LBL works in conjunction with the DOE/SF Office to negotiate utility contracts. Goals for utility acquisition are shown below.

- Monitor continuously evolving utility rate structures to seek the best power mix for LBL programs.
- Monitor the posture of WAPA for the post-1994 marketing plan and work in concert with DOE/SF and special consultants for increased allocation from the new marketing plan.
- Seek other unused or set-aside portions of WAPA power, as LBL has successfully done in the past.
- Monitor natural-gas purchasing options to ensure lowest rates. Consider direct purchase if and when cost effective.

Environmental Design Improvements

Landscaping. Improvements in esthetics and access have been made to the main entrance road and adjacent parking areas, the shuttle-bus terminal, and all the main intersections along Cyclotron Road and the Upper Hill Road. Bus shelters have been installed, and landscaped walkways, including improved lighting, have been provided from the main parking areas to main buildings. The site perimeter fence along Cyclotron Road has been moved to a less-obtrusive location below the road. Landscape plans are required for all new construction, and guidelines require low-maintenance, fire-resistant vegetation. A landscape architect firm has been retained to develop a comprehensive landscape plan for use in future development and redevelopment of the site.

Signs. Some standardized signs that are compatible with the natural setting and are easy to modify and maintain have been installed. However, many nonstandard and sometimes confusing signs need to be replaced. One element of the comprehensive landscape plan is a study of existing signs, a recommendation for future standards, and a schedule for implementation.

Painting and Roofing. A coordinated color scheme has been selected for the Laboratory's

In FY 1991, 47.9% of LBL's electricity was purchased through an interruptible power source. This provided a savings of over \$1.11 million dollars when compared with firm power costs. Interruptible power was purchased from the local utility, PG&E, as well as WAPA. Manual scheduling and coordination of the various unrelated energy-intensive processes were utilized to minimize the demand charges. The "interruptible" gas service allows for lower cost from PG&E. Plans were established to interconnect one of the other two meters into this system, potentially saving in excess of \$10,000 in charges.

Fire-Protection Improvements

Sprinkler systems have been installed in almost all buildings. Specialized equipment, such as computers, fume hoods, and experimental apparatus, is provided with appropriate specific fire-suppression systems. A new remote-detection and alarm system monitors Laboratorywide facilities.

Barrier Reduction for Handicapped Persons

Improved access to the LBL auditorium, medical clinic, cafeteria, central research laboratories, Director's Offices, and main administrative offices and suitable toilet facilities have been provided for handicapped persons.

buildings, including roofing materials and landscaping, that blends with the natural tones of the hillside. All LBL buildings have been repainted to conform to this scheme.

Maintenance

The goal of LBL's maintenance program is to provide a safe and reliable physical plant for LBL's research programs. Past budget constraints have resulted in curtailed maintenance, repairs, and replacements. Some progress in reducing backlogs has been achieved through MEL-FS funding, but increases in GPP and GPE are needed to ensure a reliable infrastructure.

LBL carries out a formalized maintenance-management program, and it has included a computerized scheduled-maintenance system. Budget requests are based upon inspections by LBL's Construction and Maintenance Department and consulting firms in specialized areas, such as cranes, elevators, boilers and pressure vessels, fire protection, slope stability, storm drainage, seismic safety, underground utilities photography, and energy-use, with review by LBL's Plant Engineering Department. An upgrade of the Plant Inspection and Maintenance System was begun in 1988 to improve facilities evaluations and to develop a plan for short- and long-range corrective actions.

The formulation of the maintenance budget is an iterative process that takes into account plans for noncapital alterations, general plant projects, multiprogram general-purpose line items, and regular line-item construction. This

process includes consideration of other operating-budget priorities, and culminates in a formal work plan for the fiscal year approved by the Associate Laboratory Director for Operations. Since maintenance and repair requirements also occur continuously throughout the fiscal year, allowances are made for meeting these requirements expeditiously.

Longer-range plans at LBL are developed for items of major maintenance, such as reroofing, paving, slope stabilization, major equipment overhaul, building rehabilitation, building exterior painting, and utilities replacements. A five-year projection is made with specific projects itemized over the first three years and lumped for the last two (see Chapter 5).

Plant operations and surveillance are carried out by the Maintenance Shops 24 hours a day, 7 days a week, under an area maintenance concept. Some maintenance projects, such as paving, reroofing, chiller overhauls, and exterior painting and certain specialized services, such as pest control, window washing, and refuse disposal, are subcontracted when cost savings and/or improved efficiencies result. Responsibility for engineering design of maintenance projects lies with the appropriate Plant Engineering Section Leader.

Site Deficiencies Summary

The older original area of the LBL site was developed in the 1940s, making it one of the oldest laboratory complexes in the DOE

system. With few exceptions, most of these older facilities are substandard or obsolete. Vehicle and pedestrian circulation routes are generally narrow, indirect, and substandard. Electrical and mechanical utility systems and load centers in the area have ample capacity but are aged, inflexible, and unreliable. Despite regular maintenance over the years, portions of these systems—water, electrical, gas, sewers, and compressed air—have exceeded their useful lives. Rehabilitation, modernization, or replacement is now necessary. Communication systems have been upgraded by the ICS Project and will only require extension to new facilities.

Present demands, in terms of energy conservation (reducing costs) and flexibility and reliability (responding to disruptions), greatly exceed the original design capabilities of the LBL electrical distribution system, and timely rehabilitation and modernization are imperative to serve current and projected research programs safely and efficiently. Shortages of both laboratory and office space at LBL have remained acute over the last 10 years, impeding the effective and efficient conduct of scientific research and adding significant operational costs. A continuing program of EH&S improvements is needed for full compliance and environmental restoration.

3. PLANNING ANALYSIS

CONTENTS

3. Planning Analysis	3-1
Strategic/Institutional Plan	3-2
Strategic View	3-2
Future Programmatic Research Areas	3-3
Summary of LBL Scientific Activities and Plans	3-5
Site-Planning Objectives, Concepts, and Guidelines	3-8
Resource Projections	3-11
Site Assessment	3-12
Background	3-12
Multiprogram Energy Laboratory Facilities Support (MEL-FS)	3-15
General Plant Projects	3-15
Utilities Needs	3-16
Maintenance Needs	3-17
Future Needs	3-21
Summary	3-24
Conclusions	3-24
Alternatives	3-25
Alternatives Development	3-25
Alternatives Evaluations	3-25
Restrict Growth	3-25
Satellite Locations	3-25
Intensify Use	3-26
Expand the Site	3-26
Accommodation for Changes in Direction	3-26

STRATEGIC/ INSTITUTIONAL PLAN

Strategic View

The Strategic View identifies external conditions and future national research directions relevant to Laboratory programs. The planning assumptions and trends described below are in agreement with the Laboratory's current Institutional Plan.

Facilities-Management Implications.

Maintaining the Laboratory's scientific leadership over the long term will require creative management and a sustained effort to revitalize the physical plant. The Laboratory's management seeks to provide effective and efficient plans for the next few decades, which promise to be highly productive for research scientists and engineers. The institutional- and site-planning processes will continue to be management focal points for developing the Laboratory's supporting infrastructure and achieving its research goals.

Internal flexibility and coordination with national programs are essential for responding to opportunities and directing resources to the most scientifically promising areas. This flexibility extends to operational resources, facilities, and management arrangements, e.g.,

revitalization of engineering and support facilities. A critical Laboratory role is to inform the DOE of significant research opportunities, and LBL management will continue to strengthen the dialogue on infrastructure needs.

The Laboratory will continue to place priority on new or improved facilities because these sustain national programs and provide an effective working environment. These facilities maintain vitality in the Laboratory, but, more importantly, they will also create new opportunities for collaboration with the university community and with industry.

Constrained budgets will continue to hinder LBL's ability to manage its site. Every effort is made to assist the DOE in justifications and analysis that support continued and increased spending for site and facilities improvements. Planning is based on estimates of future funding through close cooperation with DOE/SF and Headquarters personnel.

LBL has established focal points for graduate training and related educational support and for industry collaboration. These focal points include the Advanced Light Source, the National Center for Electron Microscopy, and the 88-Inch Cyclotron and other organizational units, such as the Center for Advanced Materials, the Center for Building Science, the Center for X-Ray Optics, and the Human Genome Center. In the future, stronger levels

of industry involvement are expected, and LBL and the other national laboratories will continue to establish additional collaborative centers, industry fellowships, and industry-laboratory research contracts. The longer-term trend will be a reduction of barriers to cooperation between industry and government.

The increased number of visiting researchers will require construction of additional user facilities including parking facilities, food-service facilities, conference rooms, and work areas. The DOE/SF should continue to work with the Laboratory and with other government agencies to provide innovative funding mechanisms to meet these needs.

Basic research will continue to be supported strongly at the national level. Since LBL primarily serves the DOE's basic-research programs, this strong support provides a constructive environment for LBL initiatives that have a new and fundamental research focus. The national laboratories will retain their capability to contribute to the energy mission of the DOE through their basic-research capability and their proposals to develop and build new facilities that serve university and industrial research communities. At LBL, future programs will emphasize the continued exploration of fundamental scientific and engineering questions that underlie, or lead to, new energy technologies.

The institutional planning process required of the national laboratories is one of the few formal and outwardly directed program-planning activities that takes place in DOE. At LBL the SDP will be coupled with the Institutional Plan and will continue to be a vital and primary mechanism to articulate internal goals and their relation to national scientific plans.

Future Programmatic Research Areas

The following sections identify important conditions affecting LBL's Energy Sciences, General Sciences, and Biosciences programs. As indicated above, these programs will be limited by fiscal constraints associated with Federal budget-deficit-reduction efforts, and the overall levels of Laboratory activity and staffing are not expected to grow significantly. The long-term strengths of DOE programs for research and advanced technology will include closer collaboration with industry and an enlarged role in educational support.

The major programs to implement LBL's mission are developed in response to DOE's national programs in the basic energy sciences, health and environmental research, high energy and nuclear physics, and conservation and renewable energy.

In response to national needs for high-brightness synchrotron radiation facilities, LBL is constructing the Advanced Light Source (ALS), which will be completed in FY 1993.

The ALS will provide the world's brightest beams of soft x-ray and ultraviolet light for use

in materials science research, chemistry, biology, and other fields. When completed and fully operational, the ALS will provide ports for up to 55 end stations, including use by up to 200 guests at any one time. LBL will provide the research and facilities infrastructure to support this user community.

LBL, in coordination with other national laboratories, has prepared conceptual designs for a Chemical Dynamics Research Laboratory for advanced studies in reaction science and combustion chemistry. Other future projects include improvements to the National Center for Electron Microscopy and strengthened programs in the Center for Advanced Materials, and in the life sciences.

Energy Sciences: The scientific outlook for the Energy Sciences is affected by developments in many scientific fields, but especially in chemistry, geology, materials science, and physics. The Laboratory views the following future research trends as important.

Materials science research growth areas will support key materials of national interest, including materials with reduced dimensionality, high-temperature superconductors, semiconductors, composites, ceramics, light alloys and polymers. The LBL Advanced Light Source, Center for Advanced Materials, National Center for Electron Microscopy, and Center for X-Ray Optics will be important elements of a national program directed toward improved materials synthesis and processing, including advanced x-ray lithography.

Chemistry of inorganic and complex organic molecules will require advanced techniques

using intense photon beams, nuclear magnetic resonance (NMR) spectroscopy, and laser spectroscopy. The defined programmatic needs for these techniques, including infrared free-electron laser facilities required for reactivity studies of molecular dynamics, is an important programmatic projection in the master plan.

Earth sciences research will include geophysical investigations of the continental crust and physical and chemical studies of geological materials, including petroleum and geothermal reservoirs, and processes involving the transport and transformation of chemicals in complex geological structures.

Energy-use research important to national energy security will emphasize advanced high-efficiency combustion, energy storage, electric lighting, energy-intensive chemical processes, and energy flows through walls and windows. Additional research facilities at LBL would improve the ability to meet these research goals. Continued reliance on fossil fuels and nuclear power will intensify problems with emissions and waste disposal and will be subjects of study at the national and international level, including developing countries.

General Sciences: LBL's general sciences programs are developed in conjunction with the high-energy and nuclear physics communities and with Federal programs in fusion research. LBL's general sciences includes the following developments:

Nuclear physics research will emphasize techniques that probe or alter the state of

nuclei to explore nucleonic, hadronic, and quark-gluon matter. The national Gammasphere project at the LBL 88-Inch Cyclotron is essential to understand the physics of nuclear structure. The Bevalac's nuclear physics operating program will be phased out in the middle of the decade. Collaborative experiments are being planned at the Relativistic Heavy Ion Collider under construction at Brookhaven National Laboratory and experimental facilities for studying unstable nuclei within an isospin laboratory are being considered at LBL.

LBL will continue its high-energy physics research programs at the Tevatron and Stanford Linear Collider (SLC) and at a proposed B-Factory upgrade at the Positron-Electron Project (PEP). Further progress will become possible through the construction of the SSC including the selection of the Solenoidal Detector Collaboration led by LBL.

LBL will continue its leading research in developing heavy-ion prototype accelerators for fusion in support of a technology that would ultimately employ accelerated beams of ions to ignite fusion fuel pellets. These research studies include the Induction Linac Systems Experiments. (The fuel pellet research will be conducted by other laboratories). The development of neutral beam testing facilities to evaluate supplemental plasma heating will continue in support of the magnetic-fusion program for the International Thermonuclear Experimental Reactor (ITER).

Biosciences: In health and environmental research, LBL was designated by the Secretary

of Energy in 1987 as a DOE Human Genome Center. The existing support for human genome research is expected to grow, requiring an expansion of life-sciences-related facilities, and specifically the construction of a proposed Human Genome Laboratory, as identified in the 1987 LRDP. In addition, LBL supports DOE's structural biology initiative through the Laboratory's proposed ALS Life Sciences Center, which will occupy existing buildings. Programmatic growth areas are the following:

Physical mapping and eventual sequencing of the human genome will be emphasized, including determination of human genome structure and expression, clonal library preparation, robotics, novel instrumentation, development of advanced computation and pattern-recognition techniques, and medical genetics.

Basic research in the molecular and cellular aspects of the control of gene expression, differentiation, DNA repair and carcinogenesis, and genomic stability in human as well as animal models systems will provide tools for an understanding of environmentally related disorders.

Structural biology research will be directed toward determining the relationship between the structure of biological macromolecules and their functions. The application of synchrotron radiation and advanced computational techniques will allow the determination of the three-dimensional structure of proteins and nucleic acids.

Biomedical research will continue the application of advanced technology to study,

diagnose, and treat human disease through innovations in positron emission tomography (PET), NMR, and charged-particle radiation therapy and radiosurgery. A Biomedical Isotope Facility is under construction at an existing building to advance PET research. Radiobiology research at the Bevalac is proposed to continue through the decade in support of the nation's Space Exploration Initiative.

Environmental and health-effects research will include atmospheric chemistry and transport, deposition, and ecological effects of combustion products. Studies of sources and transport of chemicals from the subsurface environment will cover contamination of groundwater, radon exposure and other pollutants. Research will include studies of potential global environmental changes.

Projected Trends: The most likely research trends would include several initiatives, primarily in DOE's Office of Energy Research. Some programs will grow substantially, such as materials science and structural biology research associated with the Advanced Light Source, chemical sciences research at the Chemical Dynamics Research Laboratory, Human Genome Center research, and Heavy Ion Fusion Accelerator Research program. Bevalac nuclear physics operations are expected to be significantly reduced in mid-decade. NASA support for the national Space Exploration Initiative is expected to grow during this time.

These trends indicate the continued development of LBL to a multiprogram energy

research laboratory with complementary research programs and supporting infrastructure. The proposed initiatives encompass the five-year planning period and span most of DOE's research program areas appropriate to this multiprogram national laboratory. These initiatives are identified in the LBL Initiatives Summary.

LBL has also projected a comprehensive, enhanced environmental restoration and waste management program. On global, regional, and local scales, strengthened environmental protection, improved waste management, and thorough safety practices are receiving increasing emphasis. DOE's national facilities are reviewing their policies and procedures to ensure full accountability and to set priorities to emphasize environment and safety. LBL has been actively involved in the formulation of environmental protection and safety plans and programs for improved compliance.

Summary of LBL Scientific Activities and Plans

A new major design and construction project at LBL is the ALS, which will become operational in 1993. This national user facility will provide ultraviolet and soft-x-ray (photon) beams of high spectral brightness, high flux, and partial coherence in pulses several picoseconds long. The ALS will serve many users from industry, academia, and other national laboratories and is the focus for redevelopment of the original Laboratory research facilities.

LBL PROGRAM INITIATIVES SUMMARY

Basic Energy Sciences

- Combustion Dynamics Initiative
- Atomic Scale Synthesis of Advanced Materials
- Advanced Transmission Electron Microscopes
- High Performance Computing and Communications
- Advanced Light Source Second Complement

High Energy and Nuclear Physics

- B Factory at PEP (at the Stanford Linear Accelerator Center, California)
- SSC Solenoidal Detector Collaboration (at the SSC, Texas)
- Relativistic Heavy-Ion Collider Program (at the Brookhaven National Laboratory, New York)

Health and Environmental Research

- Human Genome Laboratory
- ALS Life Sciences Center
- Global Change Research Program

Conservation and Renewable Energy

- Advanced Energy Design and Operations Technologies

Fusion Energy

- Induction Linac Systems Experiments
- Accelerator Test Facility for ITER

Multilaboratory Collaboration

- Energy Technologies for Developing Countries

Work for Others

- Space Exploration Initiative
- Advanced Lithography Initiative

LBL continues to initiate important new research programs on advanced accelerators and detectors for physics research. New experimental and fabrication facilities are being developed to support national high-energy physics programs. At LBL these support facilities include construction of ultrahigh-vacuum facilities and clean rooms and the rehabilitation and expansion of high-bay space for detector assembly and fabrication.

Materials and chemistry research now constitutes a significant share of activity at LBL. A focal point of these programs is materials science and chemistry research. The Center for Advanced Materials has established programs that integrate materials research on synthesis, processing, characterization, and instrumentation development in collaboration with U.S. industry. The Center for X-Ray Optics develops sources of radiation and techniques to transport, focus, disperse, and detect soft x-rays in support of research in many fields.

Life sciences research is conducted in six major program areas: molecular genetics and nucleic acid studies, gene expression and physiology, nuclear medicine, carcinogenesis and mutagenesis, structural biology, and environmental research. Most of this research is conducted at the Donner Laboratory, at the Laboratory for Chemical Biodynamics on the UCB campus, and at the LBL Life Sciences Research Area, where additional facilities for cell and molecular biology and human-genome research are planned.

Research in energy technology and energy conservation emphasizes potential new fusion-generation, electric-energy storage, and building systems. Examples include the evaluation of heavy-ion accelerators as drivers for inertial confinement fusion, new battery systems, and advanced concepts for fluorescent lamps. In the geosciences LBL has several thrusts, including, for example, a national leadership role in the Continental Scientific Drilling Program.

In the future the role of national laboratories as centers for research services to qualified users will grow to ensure the availability and efficient use of advanced research facilities. Complementary sources of coherent radiation, including those in the visible- and infrared-wavelength regions are also being studied.

Additional facilities for advanced accelerator physics research, biotechnology development, heavy-ion physics experimentation, and advanced engineering-support activities are currently being planned or are being considered as possibilities for future development. The Laboratory expects the trend toward advanced instrumentation, improved computational capabilities, and multidisciplinary scientific programs to continue.

Beyond the 1990s the nation will continue to face increasing demands for research and technical training programs that improve technical and economic competitiveness. To provide the required technological innovation and scientific expertise, the Laboratory will

emphasize fundamental research programs, advanced user facilities for the general scientific community, new educational and training activities, and increased interaction with industry. Figure 3-1 provides information on the sources of LBL operating funds for the years 1980 to 1989. With this approach, the Laboratory's expertise and facilities will help

meet national scientific and economic goals well into the next century.

This TSI is in concert with the Laboratory's Five-Year Institutional Plan and in conformance with the LRDP approved by The UC Regents in 1987. It incorporates a framework for long-range development that provides for flexibility in siting and protection of the environment and natural resources.

TSI 927-21

Fig. 3-1. Sources of LBL operating funds from 1980 to 1989.

Site-Planning Objectives, Concepts, and Guidelines

Site planning objectives at the Laboratory are based on long-range institutional goals that support the conduct of LBL's mission. The long-range institutional site-planning objectives are listed below.

- Provide research facilities and accommodate changes or growth required for anticipated national scientific needs.
- Protect the environment, plan for site amenities and constraints, and buffer activities from adjacent populations.
- Ensure a safe, healthful, and attractive workplace; improve access and communication with the University community; and provide transportation and parking systems for employees and the visiting public.
- Protect and sustain the investment in valuable government-owned research and support facilities.
- Improve support and research services through proper siting and consolidation of functions.
- Promote energy conservation and cost economies through efficient design, location, operation, and maintenance.

To achieve these six objectives, the SDP is based on five LBL planning concepts. These concepts accommodate the facilities requirements of the Laboratory within existing geo-

physical, environmental, and operational conditions. They provide a basis for understanding and evaluating the more-detailed elements of the actual site plan, which is characterized by specific buildings, utilities, and transportation elements. The site-plan concepts are the following.

- Consolidate activities within seven functional planning areas — related groupings of facilities and population centers — to enhance interaction and efficiency (Figure 3-2).

- Redevelop obsolete buildings and infrastructure, eliminate trailers for permanent functions, and improve building arrangements to increase open space in the original World War II Laboratory area.
- Coordinate development along the East-West circulation and utilities axis, which extends from the Life Sciences Research Area to the 88-Inch Cyclotron Research Area (Figure 3-3), to enhance transportation and service systems, develop off-

Fig. 3-2. Schematic concept of the seven functional areas.

TSI 927-22

Fig. 3-3. The east-west circulation axis.

road parking, and improve the system of pedestrian pathways.

- Improve and maintain perimeter buffer zones and natural beauty by, for example, restricting construction in highly valued landscape areas.
- Provide off-site "satellite" locations for receiving, warehousing, and other support and research activities well suited to decentralized locations.

The SDP provides a framework for the rehabilitation and replacement of obsolete and deteriorated structures, primarily in the original

World War II Laboratory, including the following. Table 3-1 provides an analysis of conditions by functional area, and Appendix D details planned additions and removals.

- Replacement of obsolete and substandard mechanical- and electrical-engineering buildings and accelerator-testing and fabrication facilities.
- Rehabilitation of electrical- and mechanical-utility systems and other infrastructures, including roadways (throughout the site).

- Replacement of trailers and obsolete wood-frame light-duty laboratory and office buildings, primarily to accommodate users of the Advanced Light Source.

The SDP allows for a relocation of support functions and some research activities for improved efficiency and safety.

- Relocation of the material-storage and supply-services personnel from the Light Source Research and Engineering Area to the Shop and Support Facilities Area, with the elimination of several trailers.
- Consolidation of reclamation and materials-handling activities to the eastern end of the Laboratory site.

- Relocation of selected research programs and the printing plant from off-site leased space to the main site.

The plan allows for potential additions for program-related or support projects.

- New buildings and additions to existing structures for anticipated program growth in molecular genetics and medicine, chemical dynamics research, and provision for sites for future growth in materials science programs.
- Additions to existing buildings for research and for administrative, shop, engineering, and other support functions, including essential EH&S activities, plant engineering and construction and maintenance activities and conference facilities

Table 3-1. Analysis of Building Conditions.

Area name	Adequate space	Substandard Can Be Made Adequate	Substandard Cannot Be Made Adequate
88-Inch Cyclotron Area	53,320	0	80
Central Research and Administration Area	50,710	410,110	28,070
Bevalac Accelerator Complex	133,320	187,320	34,370
Light Source Research and Eng. Area	186,880	40,210	135,200
Shops and Support Facilities Area	84,610	68,770	14,460
Materials and Chemical Research Area	62,350	59,700	1,910
Life Sciences Research Area	23,610	45,050	490
Environmental Monitoring Status	500		
Total^a	595,300	811,200	214,600

^aTotals are rounded to nearest 100.

for multiprogram support and for science-education programs.

Design guidelines in the SDP have been developed to achieve specific facilities-planning requirements while respecting site constraints and providing coherence among building elements and the landscape. These reference guidelines address the following areas.

- *Safety Considerations.* New and rehabilitated buildings will conform with applicable federal, state, and local code requirements to ensure compliance and to safeguard the staff and the community.
- *Utilities Corridors.* Utility distribution systems are, where feasible, to be placed in trenches and under roadways. Central and localized distribution stations and

feeder lines are located and sized for future building locations and anticipated demand and will be subject to design reviews for compatibility with general site developments and future site needs.

- *Building Mass, Orientation, and Exteriors.* Buildings are to be designed to fit well into the slope of the land, to conserve important landscape features and open

space, and to be closely integrated with the landscape plan. They are to be no more than five stories high and may not present an uninterrupted wall greater than four stories high. Exteriors of buildings are to be compatible in design with surrounding building elements and landscaping. Textures and colors, including those of roofs, are to be unobtrusive.

- **Energy and Operational Efficiency.** Buildings are to employ optimum energy strategies and efficiency features to include building orientation, natural illumination and sun control, and automated ventilation and climate-control systems, where feasible. In addition, building design considerations include efficiencies in maintainability of systems.

- **Building Use Flexibility.** Building systems cores for circulation space and utilities are to provide flexible and modular space to allow for changes in partitioning and function.

- **Circulation and Parking.** Circulation and parking plans are to provide compatibility between vehicle use and pedestrian safety. Pedestrian paths are to be separated from vehicles, where practicable, with distinct access and termination points so that bus stops, parking areas, loading docks, and building entrances are safe and efficient. Emergency-vehicle and handicapped-person access is incorporated into building and circula-

tion design. Shuttle-bus stops are provided with shelters.

- **Topography and Grading.** Grading and retaining walls are to contribute to the stability of slopes and soils, to allow for smooth topographic transition between hillsides and structures, and to be constructed of materials visually suitable for their locations.

- **Landscaping and Open Space.** Landscaping, along with designated open space, contributes to the compatibility of buildings with the vegetation of the hillside and generally includes native plants. It visually screens service areas, reduces fire danger, contributes to slope stability, provides summer shade, and creates new areas for the use and enjoyment of employees and visitors. Existing

natural landscaping is to be preserved to the extent possible.

- **Guideline Review Process.** Detailed design guidelines are to be established for each development site before design begins. Each project will be reviewed for conformance to these guidelines by the Laboratory's architects and engineers and by the Director's Architectural Consultant.

Resource Projections

Resource projections for the next 5 years are found in Table 3-2. Operating budgets are expected to be relatively stable, consistent with Federal budget trends, and increases in construction funding to accomplish the SDP goals are included. Specific information on resource projections is based on LBL's FY 1993–1998 draft *Institutional Plan* (PUB-5209).

Table 3-2. Resource Projections (Fiscal Year FTE).

Category	1987	1988	1989	1990	1991	1992	1993	1994
DOE Direct	1487	1514	1445	1356	1366	1375	1383	1391
WFO	279	287	304	305	307	308	296	283
Total Direct	1766	1801	1749	1662	1673	1683	1679	1674
Total Indirect	737	762	759	741	741	741	742	742
Total Lab Personnel	2503	2563	2508	2403	2414	2424	2420	2416

SITE ASSESSMENT

Background

LBL's facility-related problems stem from the obsolete design of its oldest buildings, deteriorating utilities, and the changes in scientific needs since 1940. Many laboratories and shops were originally designed for temporary service during World War II. Figure 3-4 shows the age distribution of main-site buildings. In addition, some buildings constructed during 1940–1960 are not adequate for today's highly technological scientific demands.

LBL has developed site assessment planning programs to identify and integrate facility maintenance and improvement projects, as well as identifying building and support structure needs. LBL's planning framework, identified in Chapter 1, includes a planning process scheduled through a comprehensive planning calendar, of which the assessment of facilities condition and needs forms a part. LBL retains planning consultants for independent review and performs planning evaluations of facilities needs. LBL evaluates its projects using Capital Asset Management planning criteria and performs assessments of facilities consistent with the goals of the DOE's planned Conditions Assessment Survey goals. The characteristics of shops and support facilities, such as environmental control (e.g., airborne particle concentrations) and adequate electrical and plumbing services, must be appropriate to current research programs. Electrical utilities projects are identified in Table 3-3. Forecasts

Fig. 3-4. Age distribution of main-site buildings.

Table 3-3. Planned Electrical Utility Improvements.

Functional Area	Existing			Planned		
	Xformer (no.)	Switch (no.)	Cable (miles)	Xformer (no.)	Switch (no.)	Cable (miles)
88-Inch Cyclotron Research Area	3	4	2	3	5	2
Central Research and Administration Area	7	11	3.75	8	21	2.75
Bevalac Accelerator Complex	20	30	12.5	20	47	17.5
Light Source Research and Engineering Area	14	25	5	14	40	8
Shops and Support Facilities Area	2	28	1	3	29	2
Materials and Chemistry Research Area	2	2	1	2	2	3.25
Life Sciences Research Area	1	1	0.75	5	14	1.25

for electricity and natural gas are shown in Table 3-4. Analysis by types of electrical service is presented in Table 3-5. An analysis of building conditions by type of space is presented in Figure 3-5.

As described in Chapter 4, the Laboratory has developed a rehabilitation and replacement program with a long-range schedule. The largest costs are for building and utilities rehabilitation or replacement.

Table 3-4. Electricity and Natural-Gas Forecasts by Functional Area

Functional Area	Electricity				Natural Gas			
	1994		2004		1994		2004	
	Area (gsf)	Usage (kWH) ^a	Area (gsf)	Usage (kWH) ^a	Area (gsf)	Usage (cu ft) ^b	Area (gsf)	Usage (cu ft) ^b
88-Inch Cyclotron Research Area	53,800	3,389,400	62,400	3,931,200	53,800	4,842,000	62,400	5,616,000
Central Research and Administration Area	493,380	31,082,940	500,950	31,559,850	493,380	44,404,200	500,950	45,085,500
Bevalac Accelerator Complex	352,400	22,201,200	471,900	29,729,700	352,400	31,716,000	471,900	42,471,000
Light Source Research and Engineering Area	409,510	25,799,130	498,070	31,378,410	409,510	36,855,900	498,070	44,826,300
Shops and Support Facilities Area	204,160	12,862,080	205,850	12,968,550	204,160	18,374,400	205,850	18,526,500
Materials and Chemistry Research Area	127,000	8,001,000	158,010	9,954,630	127,000	11,430,000	158,010	14,220,900
Life Sciences Research Area	98,700	6,218,100	147,910	9,318,330	98,700	8,883,000	147,910	13,311,900
TOTALS	1,738,950	109,553,850	2,045,090	128,840,670	1,738,950	156,505,500	2,045,090	184,058,100

^aBased on average usage of 63 kWH/gsf

^bBased on average usage of 90 cu ft/gsf

Table 3-5. Future Electrical Utilities by Type of Services.

Bldg / Description	Interruptable	Firm	Switchable	High Reliability
88-Inch Cyclotron Research Area				
All Buildings		•		•
Central Research and Administration Area				
50 Complex			•	•
54 Cafeteria			•	
55 Research Medicine		•		
70 Complex			•	
90 Complex			•	
Bevalac Accelerator Complex				
46/47 Complex			•	
51 Bevatron Accelerator	•	•		
58 Complex			•	
64 Accelerator Research	•			
71 Complex Hilac	•		•	
Light Source Research and Engineering Area				
2 Advanced Materials Lab		•		
4 & 5 Magnetic Fusion Energy	•	•	•	•
6 Advanced Light Source	•	•	•	•
10 Biology Research / Photo Lab	•	•	•	•
16 Magnetic Fusion Energy Lab		•		
25 Complex			•	
26 Medical Services		•		
37 Utilities and Service		•		
45 & 48 Fire Station	•	•	•	•
80 Center for X-Ray Optics	•	•	•	•
Shops and Support Facilities Area				
All Buildings			•	
Materials and Chemistry Research Area				
All Buildings			•	
Life Sciences Research Area				
All Buildings			•	

Other projects include environmental and health projects, roadway safety improvements, and slope stabilization. The costs of the general-purpose facilities-rehabilitation program for the FY 1993–2008 planning period are included in the construction cost table provided in Chapter 4.

Multiprogram Energy Laboratory Facilities Support (MEL-FS)

The MEL-FS program is vital for rehabilitating the Laboratory's deteriorated utility system and for modernizing, upgrading, and replacing obsolete facilities. The MEL-FS project priorities and schedule are prepared following careful planning and review by Laboratory management. The long-range profile is driven by budget constraints; for example, those utility projects scheduled to begin in 5–10 years correct existing, not future, problems.

General Plant Projects

The GPP program can provide a timely mechanism to fund priority projects; however, the amount of funds received have been inadequate to meet the Laboratory's needs. LBL will require significant GPP outlays for major replacements (such as 12-kV cabling, switching stations, cooling towers, boilers, chillers, gas lines, and water lines) and for small program modification and additions over the next several years. Progress in increasing GPP funds is important to the success of the Laboratory's rehabilitation program. MEL-FS

TSI 927.25

Fig. 3-5. Current space usage.

priorities, which subordinate replacing obsolete facilities to safety, health, and environmental concerns, make adequate GPP funds important to LBL.

Utilities Needs

Many of the Laboratory's utility systems were initially sized to serve the Laboratory's large accelerators, and they have the capacity to fulfill present and future electrical-power, gas, water, cooling, and waste requirements. However, many segments and load centers in the utility systems are aged and require rehabilitation to improve flexibility and reliability (see Figures 3-6 and 3-7). The utility systems that are undergoing rehabilitation include natural gas, potable water, cooling water, low-conductivity water, electrical power, sanitary sewers, compressed air, storm drains, standby and backup electricity, and alarm and security. New building construction (see Figure 3-8) will require some new utility corridors to link existing east- and west-site utilities. New corridors are being developed within the Light Source Research and Engineering Area, and extensions are needed to the Life Sciences Research Area. In general, these will include electric service as well as water and gas lines, sanitary sewers, and storm drains. Electrical, communication, and fire-alarm systems are shown in Figure 3-9. For existing and planned utility needs for water, sewer, natural gas, and electricity see Tables 2-7 through 2-10.

The LBL electrical-distribution system must be able to cope with power interruptions while

maintaining firm service to those LBL facilities that cannot tolerate interruptions. The present LBL system was not designed to distribute reliably the various levels of power that the electric companies now offer in their rate schedules. The basic elements for a flexible and reliable LBL distribution system exist already, however, and a cost-effective rehabili-

tation can be accomplished at a small fraction of the replacement value of the existing system. The six-phase rehabilitation program of the 12-kV electrical-power distribution system involves replacement of aging and hazardous electrical switching equipment and distribution cables. The existing single-service radial distribution system will be expanded to a

TSI 927-26

Fig. 3-6. Age of LBL mechanical equipment (reference year 1987).

TSI 927-27

Fig. 3-7. Age of LBL electrical equipment.

double-bus distribution system by extending the existing central double-bus system at the Grizzly main substation to seven centrally located switching stations. From these switching stations double feeder circuits will be extended to Laboratory buildings and other facilities. This arrangement will restrict electrical system failures to fewer facilities, reduce planned outages, enhance preventive-

maintenance activities, and permit the selection of the least-expensive electricity source by the users.

New building and other energy-using facilities will incorporate energy-conservation features that meet or exceed applicable Federal energy-use standards, incorporating cost-effective energy-conservation designs, whenever possible. Major facilities such as new

cooling towers and building HVAC and lighting systems will be optimized (for energy conservation) and placed under the Automated Energy Management System. Also, natural gas and electricity will be metered to provide data for identifying energy waste and for establishing priorities for potential energy-conservation projects.

Rehabilitation of mechanical utilities is required at several locations for potable-water, cooling-water, compressed-air, natural-gas, storm-drain, sanitary-sewer, and acid-waste systems. Portions of the outdated potable-water piping, as well as valves, backflow preventers, fire-sprinkler risers, and obsolete fire hydrants, will be replaced. The cooling-water system in several buildings will be rehabilitated. Security improvements will include extension of the card-key system and improvements to the fire-alarm network.

Maintenance Needs

The Laboratory is conducting maintenance-planning programs by formulating integrated plans for a long-range capital-improvements program and for operating expenditures. LBL is working with DOE to integrate the goals of the condition assessment survey and the capital asset management program into LBL's maintenance planning and project development planning.

GPP and MEL-FS projects include replacement and rehabilitation of facilities to maintain existing capability. GPP and MEL-FS funds, have been used to replace roofs, paving, and electrical, water-supply, and mechanical systems.

TSI 927-28

Fig. 3-8. Mechanical utility corridor improvements.

Fig. 3-9. Electrical, communications, and fire-alarm improvements.

Fig. 3-10 Landslide locations on the LBL site.

The operating expenses for maintenance include physical plant maintenance and noncapital alterations related to maintenance. Maintenance can be effectively managed by establishing priorities for maintenance projects and by replacing existing, obsolete, and high-maintenance-cost facilities with modern facilities and equipment. Laboratory management is directing its efforts toward rehabilitation of buildings with GPP and MEL-FS funds. The use of noncapital funds can then be efficiently allocated to maintain essential building and equipment investments.

Future Needs

Constraints to future sites in the development stem from the steepness of the terrain, the desire to preserve the environment, and the need to provide parking and service areas onsite to support the Laboratory population. The best use must be made of available building sites, and space adjacent to existing program and support facilities must be reserved for future expansion.

Planning for significant future growth of the Laboratory centers on three areas: Offices and supporting facilities for LBL infrastructure in the shop and support facilities area; redevelopment of the Light Source Research and Engineering Area (near Building 6), which was built up during the 1940s; expansion in the Life Sciences Research Area in the vicinity of the existing Biosciences (Buildings 74-83) complex.

The Shop and Support Facilities area is currently inadequate to support EH&S func-

tions, plant engineering functions, and construction and maintenance activities. Limitations have been identified by the Tiger Team assessment in 1991. Detailed programming analysis of these functions indicates that important functions are not being conducted, and the consolidation of existing space and activities is required.

The Light Source Research and Engineering Area contains about 15 acres and presents the greatest potential, through redevelopment, for sites for future research and support facilities. Recent consultant studies indicate that the Life Sciences Research Area has potential for additional development in building area and size, and this potential is under review for consideration in subsequent SDP document. Table 3-6 summarizes general-purpose building needs.

The Light Source Research and Engineering Area, which was developed around the old 184-Inch Cyclotron, has excellent geographical and geotechnical qualities and natural topography especially suited to building sites for high-technology facilities. Many buildings in the area are substandard or obsolete, but the newer buildings (such as Building 6) are quality structures that will be preserved for future use. Vehicle and pedestrian circulation routes are generally narrow, indirect, and substandard. Although utility systems and load centers have ample capacity, they are generally aged and inflexible. The pressing need to replace or rehabilitate many of the existing buildings, roadways, and utilities in the Light Source Research and Engineering Area,

coupled with its physical attributes and central location, makes the area a prime candidate for redevelopment.

During the last 10 years, LBL has carried out a rehabilitation program to upgrade its facilities for seismic safety, fire protection, industrial safety, and environmental enhancement. During this time, over one-half of its GPP funds have been expended for these improvements. Maintenance programs in painting, roofing, paving, slope stabilization, erosion control, and mechanical and electrical utility systems have been carried out to preserve and upgrade the physical plant.

Slope-stability projects have been identified and prioritized as shown in Figure 3-10. Funding for these projects will be requested from both MEL-FS and GPP sources depending on the scope of work. Priorities are based on potential threats to DOE structures, roads, and utility systems and on integration into ongoing maintenance plan.

Shortages of both laboratory and office space at LBL have remained acute over the last 10 years, impeding the progress of scientific research and adding significant operational costs for short-term responses to these shortages. Specific regulations exist for Administrative Offices; ES&H offices, training areas, and monitoring laboratories; facilities management offices for planning, design project management, construction management and maintenance program; for applied science energy research laboratory modernization, science education, and for visitors.

Table 3-6. General-Purpose Building Needs Summary.

Functional Need/Problem	Deficiency	Existing Requirements	Proposed Building
Workplace safety Fire safety Environmental protection	Contested operations Substandard woodframing Inadequate chemical storage	42,000 gsf of office, light Lab, and materials-handling and storage space	Safety and Support Services Facility
EH&S requirements monitoring requirements Industrial hygiene	Insufficient space Inadequate/no labs No training areas	33,000 gsf of office light lab, training library and conference space	Environment monitoring and Industrial Hygiene Building
Project Management Construction and Maintenance Facilities planning	Inadequate space Insufficient space temporary quarters	30,000 gsf of office space, conference area	Facilities Management Addition
Applied Science Energy research modernization	Temporary structures code compliance consolidation	20,000 gsf of light laboratories and offices	Applied Science Building
Science education visitors	insufficient space temporary structures	10,000 gsf of offices and conference area	science education and visitors center
Seismic safety Fire safety Environmental protection Obsolete utilities	Unreinforced masonry Substandard grounding Drain and plumbing, hoods Substandard electrical service	40,000 gsf shop, office & light assembly, and high bay w/full utilities	Future Engineering Replacement Project Phase I
Workplace safety Fire safety Environmental protection Obsolete utilities	Uncontrolled ventilation Substandard grounding Inadequate plumbing Substandard electrical service	40,000 gsf shop and office building w/full utilities	Future Engineering Replacement Project Phase II
Total General-Purpose Building Needs		235,000 gsf ^a	

^a General-Purpose Building Construction will be offset with removals and demolition, resulting in constant net LBL space.

Aerial view of the Shops and Support Facilities Area showing two slide areas temporarily stabilized with plastic sheeting as part of the Laboratory-wide slope-stabilization program.

The Laboratory has become increasingly active and successful in the fabrication of high-technology systems and precision windings for large detectors in support of DOE programs at LBL and at other national laboratories. The success of this work has produced needs for upgraded shop assembly and staging space environmentally designed for high-technology fabrication. Upgrades for engineering facilities are included as future projects in the long-range master plan.

Summary

Construction of all the projects represented in this plan would result in a net increase of approximately 405,000 gsf of buildings in the main Laboratory site, for a total of 2,045,090 gsf. For comparison, the 1992 total is 1,621,100 gsf (see Appendix C).

The increased need is due to the increased development of programs in materials science and chemistry, earth sciences, conservation and renewable energy, and fossil energy that were not a part of the Laboratory's mission in the early 1960s.

In addition, the specialized research facilities and program expansion in the physical sciences and the life sciences, such as electron microscopy and molecular genetics, and new facilities for the Advanced Light Source were not anticipated in the 1960s and have required, or will require, new buildings or extensive additions to existing buildings.

The TSI also emphasizes utility rehabilitation, improved parking and traffic circulation, and respect for nine buffer-zone landscape

areas that unify the site and enhance compatibility with the surrounding hillside. The major site-development proposals are (1) infrastructure and space improvements for support functions (2) redevelop the original Laboratory site to eliminate obsolete buildings and enhance the open space, (3) expand the Life Sciences area by acres, and (4) eliminate the use of 60,000 gsf of trailers. The SDP allows for a Laboratory staff size of 4,750 at all existing activity areas.

Conclusions

An analysis of the constraints and opportunities for future development and redevelopment of the LBL site has focused long-range planning on site potential (or build-out) for comparison with long-range program needs. Subportions of the site with potential for cost-effective development (or redevelopment) have been targeted for more-detailed studies. Thus, in the process of developing the LBL Site Plan, comprehensive site-use studies have been made to ensure the most-efficient and most-cost-effective use of available sites. In parallel, the Laboratory has studied the need for additional facilities beyond the 5-year institutional planning period on the basis of potential program initiatives. The environmental impacts of development have been studied extensively, including the cumulative effects related to traffic and parking. The site potential for reasonable development beyond the 5-year institutional plan is greater than currently projected long-range needs. Consequently, a population of 4,750 represents a realistic long-

term development level. Because there is room for physical alternatives in the long term, care has been taken to establish and preserve areas adjacent to existing facilities to permit future development.

About 50% of LBL's estimated maximum population growth is projected to take place during the next five-year institutional-planning period, during which time the present population will increase from 3,940 to 4,390 (including visitors). Over the long term the total population (including visitors) will level off at 4,750. This development level has been based upon conditions governed by geographical, environmental, and research factors. The main-site projected population for the Institutional Plan five-year period is 3,590; for the long-range Master 20-Year Plan period, 4,100. The 1992 main-site population was 3,055.

Solutions incorporated into the redevelopment plan are designed for mission-oriented functional relationships, but the plan also preserves a character appropriate to a highly visible and sensitive hillside area in an urban setting. Proposed building sizes and locations for research initiatives yet unknown have been selected to enhance modular development and flexibility.

Site and facility requirements to carry out program goals and related multiprogram support activities during the planning period have been developed in conceptual designs for individual projects.

New construction, renovations, removals, corrections, and other means to fulfill projected program activities are translated into

funding requirements and compared with personnel projections (Table 3-2).

The concept for future site development has been studied. Prerequisite studies and programs that have been carried out in this planning analysis are listed in Appendix A. LBL's SDP is responsive to DOE programs and the directions they are taking. The SDP is in agreement with the Laboratory's Institutional Plan and incorporates a framework for long-range development, site alternatives, and protection of the environment and natural resources.

ALTERNATIVES

Alternatives Development

To evaluate the potential of the site, the Laboratory has commissioned a number of site-use studies (Appendix A) in the past and is currently conducting a new study of the original site in what is now referred to as the Light Source Research and Engineering area. These studies have been used to create an ideal site development plan based on optimal functional relationships. This is represented by the Master 20-Year Plan in Chapter 4. Gains in efficiency of human and capital resources to improve the Laboratory's ability to carry out the DOE responsibilities, as exemplified by the Laboratory's mission statements, guide the development of the Master 20-Year Plan. The grouping of like functions, renovation, and replacement of obsolete or inadequate re-

search facilities and infrastructure, and the improvement of circulation for people and materials among work areas are cornerstones of the Master 20-Year Plan.

ALTERNATIVES EVALUATIONS

Restrict Growth

The Laboratory considers the restriction of growth in selected areas to be a normal part of management and operation. As discussed under Planning Process in Chapter 2, the Laboratory carefully reviews proposed research activities to ensure that existing capabilities will support the proposed activities and that they are consistent with the Laboratory mission. If existing capabilities are inadequate, a commitment must be made to increase them. This policy has resulted in growth during most of the Laboratory's history, with the exception of the previously discussed retrenchment in the early 1980s. As the site becomes more nearly saturated, new work will be more closely scrutinized to ensure that it does not unduly burden the Laboratory's performance capabilities.

Satellite Locations

Off-site, or satellite, facilities for support functions and research programs are used when decentralized locations are appropriate. The warehousing and receiving support

functions were moved in 1980 to the cities of Emeryville and Berkeley. Moving these functions to industrial areas near major freeways eliminated much of the LBL heavy-truck traffic that had added to the traffic congestion of Berkeley streets. In addition, LBL's Printing Plant was relocated to 24,000 gsf of space in an industrial park in West Berkeley in 1979 as a near-term solution to a space shortage. The Laboratory has leased 11,500 gsf of office space in downtown Berkeley to house administrative functions beginning in the winter of 1989.

LBL research programs also use off-site locations. For example, there are facilities at UCB's Richmond Field Station (RFS) for the Earth Science Division's research and for the Energy and Environment Division's indoor environment program. The indoor-environment program maintains at the RFS a research building known as the Radon Research House, a unique experimental facility used for the national radon-research program and other indoor-air-quality research. The Engineering Division monitors particle decay in a low-cosmic-radiation-background environment at the Oroville Dam powerhouse. In addition, other research programs are located in short-term-leased buildings when temporary space is required or when cost-effective facilities are not available at the main site.

LBL will continue to evaluate its needs for support services and for research-program facilities with respect to their appropriateness to the main site. Those needs that are charac-

terized as being well suited to decentralization will be placed off site when suitable space is available.

Intensify Use

To maximize the use of each building site, building massing has become increasingly important. Although low-rise development is less expensive, the land constraints that face LBL require that either multistory buildings be constructed (including possible multistory parking structures) or that single-story buildings be constructed so as to allow addition of upper stories. However, design guidelines include some limitations. For instance, one guideline states, "Buildings are to be designed to fit well into the slope of the land, to conserve important landscape features and open space, and to be closely integrated with the landscape plan. They are to be no more than five stories and may not present an uninterrupted wall greater than four stories high."

In addition, the plan calls for removal of most of the temporary structures built in the 1940s and all of the trailers. This will provide many of the building sites identified in the 5- and 20-year plans. Details of this reuse are in Chapters 4 and 5.

Expand the Site

Expanding the existing site to accommodate new development requirements is attractive in several ways. The use of functional-area

groupings provides Laboratory planners with the ability to expand building sites and improve traffic circulation and communication facilities. In addition, financial leverage can be applied in many cases. Infrastructure expansion to adjacent lands is also less costly and less difficult than establishing new infrastructure at new sites such as satellite locations. The Laboratory negotiates expansion of the boundaries of the site with the UC Regents as the need arises. New facilities are budgeted and proposed for this area as noted in the 5- and 20-Year Plans.

Additional expansion is potentially limited by competition with UCB for undeveloped land within the 11,000 acres owned by the Regents, by the current ceiling of 4,750 personnel, and by environmental considerations.

ACCOMMODATION FOR CHANGES IN DIRECTION

The Planning Concepts and Design Guidelines presented in this plan result in a functional-area arrangement that ensures that planning practices are exercised while allowing flexibility of use. Improvements to infrastructure (mechanical and electrical utilities, communications, traffic circulation, and support services) are uniform over the long term. This arrangement and the appropriate use of satellite and temporary space form the

basis for accommodating changes in direction. LBL has responded quickly and efficiently to changes in national research directions in the past and will continue to do so in the future, if necessary. Design guidelines and concepts include specialized research facility zones in proximity to major research facilities.

LBL does not rely solely on any one of the broadly based alternatives described above. Rather, its response to decisions on development and redevelopment involves the judicious use of an appropriate mix of alternatives. Satellite locations are used for certain support functions because they need not be close to scientific, technical, and research staff. Consolidation of other support services, such as Environmental Health and Safety, Materiel Management, and maintenance and repair units on the main site makes immediately available the skilled personnel required to support and safeguard research programs. The Planning Concepts and Design Guidelines and Processes ensure strategic planning for intensity and use factors in construction of new facilities and rehabilitation and additions to existing facilities. Laboratory management will continue to consider restriction of growth as a normal part of management and operations. The synergism among these alternatives provides a framework for controlled but flexible development and management of the site.

4. MASTER 20-YEAR PLAN

CONTENTS

4. Master 20-Year Plan	4-1
Land Use	4-2
Functional Areas	4-9
88-Inch Cyclotron Research Area	4-10
Central Research and Administration Area	4-10
Bevalac Accelerator Complex	4-13
Light Source Research and Engineering Area	4-14
Shop and Support Facilities Area	4-14
Materials and Chemistry Research Area	4-14
Life Science Research Area	4-14
General-Purpose Construction Projects	4-14
Funded Utility Projects	4-14
Proposed Electrical Utility Projects	4-16
Proposed Mechanical Utility Projects	4-20
Proposed Construction Projects — General Purpose	4-20
Other Health and Safety Projects	4-20
Program-Related Construction Projects	4-21
Proposed Construction Projects — Program Related	4-21
General Plant Projects	4-21
Maintenance and Energy Conservation	4-22

This plan specifies the Laboratory's prioritized use of its capital funds to replace obsolete facilities and the actions needed to protect these investments in the future. The plan calls for correction of current deficiencies as quickly as economically feasible and calls for a structured system of maintenance of the site and its capital assets throughout their normal service lives. Correction of current deficiencies, e.g., utilities and building rehabilitation, building replacements, road rehabilitation, and slope stabilization, will continue through FY 2010.

This planning is vital to the Laboratory's programs because of the need to use developable land efficiently, to replace obsolete facilities, and to plan for new construction within a realistic economic framework. Laboratory management has developed the plan with due regard to budgetary constraints. Funding below the projected levels will create an increasing backlog of rehabilitation projects creating a situation that will be difficult to correct.

The 20-Year Plan also identifies programmatic facilities. The Advanced Light Source received initial funding in FY 1987 and is currently being commissioned, with completion scheduled for FY 1993. This project is the first phase of a long-term plan to develop a national research facility. Beyond the construction of the Advanced Light Source (ALS)

itself, construction of additional beamlines and experimental areas and additional support facilities for users is anticipated. To accomplish this, the plan proposes that the ALS Structural Biology Support Facility and the ALS Beamline Initiative begin in FY 1994. The Chemical Dynamics Research Laboratory is also proposed for a FY 1994 construction start. Facilities for Human Genome Research, inertial confinement fusion (Induction Linar System Experiments) Magnetic Confinement Fusion (Accelerator Test Facility for ITER) are important elements of the master plan and contribute to DOE's research capabilities.

Other major needs at LBL are for special light-laboratory and test-facility space to accommodate current multiprogrammatic activities and for multipurpose office space. The shortage of office space has resulted in serious crowding and the continued use of converted laboratory space and inefficient, expensive trailers. Since 1982, LBL has been able to eliminate most of the costly off-site leased office space (about 50,000 sq ft), primarily as a result of personnel reductions combined with consolidation of personnel in existing office space and trailers. However, for the short term, administrative functions are being relocated to 11,500 gsf of leased space in downtown Berkeley, and 6,600 gsf have

been added to the life science program's leased area in the Berkeley Business Park. A major goal of the SDP is to provide space for essential safety, health, environmental, engineering, and maintenance functions. New laboratory space and lower-cost office additions that will allow laboratories now used for offices to be reclaimed.

The total LBL construction for FY 1993-2008, including funded construction, budgeted construction, and proposed construction, is shown in Table 4-1, and proposed building placement is shown in the site map, Figure 4-1.

LAND USE

Eighty acres of the site are currently designated as buffer and open areas, whereas about fifty acres have been developed with buildings, roadways, and other site improvements. Figure 4-2 shows the Buffer-Zone Landscape Map and Planning Areas. Special considerations are included in the table below Figure 4-2 and are used to ensure that these areas are effectively managed. Although plans call for the volume of building site to increase, future building footprints will be more compact and designed in accordance with landscape plans. Therefore, although the total amount of open space will decrease, the sizes of individual open

Table 4-1. Lawrence Berkeley Laboratory Fifteen-Year Construction Plan (FY BA, \$M).

Project	Subprog	TEC	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008
FUNDED PROGRAM RELATED PROJECTS:																				
Advanced Light Source		99.5	23.0	6.4																
Biomedical Isotope Facility		2.3	0.6	0.7	0.6															
SUBTOTAL - FUNDED PROGRAM RELATED		101.8	23.6	7.1	0.6															
FUNDED MEL-FS PROJECTS (KG):																				
Environmental Health & Safety Project		13.2	1.6	0.5	1.5	2.0														
Original Labsite Substation		3.0	0.0	2.7																
Instrument Support Lab Rehab		2.1	0.0	1.9																
Slope and Seismic Stabilization		3.7	2.4	0.8																
Building 90 Seismic Rehabilitation		6.8	3.7	2.7	0.4															
East Canyon Electrical Safety Proj		3.9		0.4	1.5	2.0														
Roof Replacements, Phase I		2.5		2.0	0.5															
SUBTOTAL - FUNDED MEL-FS		35.2	7.7	11.0	3.9	4.0														
FUNDED ERWM PROJECTS:																				
Hazardous Waste Handling Facility		12.0	0.0	1.6	0.0	5.8														
Environmental Health & Safety Project		1.8	0.0	0.0	0.0	0.7														
SUBTOTAL - FUNDED ERWM		13.8	0.0	1.6	0.0	6.5														
TOTAL FUNDED		150.8	31.3	19.7	4.5	10.5														
BUDGETED MEL-FS PROJECTS (KG)																				
Safety & Support Services Facility	GPF-EHS	9.9			3.0	4.5	2.4													
Fire & Safety Sys Upgrd Proj., Ph I	TTR	4.6			1.5	2.0	1.1													
Upgrd of Site Mech Util., Ph II - Sew Mon	GPF-Mech	7.1			0.8	3.4	2.9													
Hazardous Materials Safeguards, Ph I	TTR	5.1			1.5	3.6														
TOTAL BUDGETED MEL-FS		26.7	0.0	0.0	6.8	13.5	6.4													
TOTAL FUNDED and BUDGETED		177.5	31.3	19.7	11.3	24.0	6.4													
PROPOSED PROGRAM RELATED PROJECTS:																				
Human Genome Laboratory (KP)		24.7			2.2	15.6	5.9	1.0												
Induction Linac Systems Exper (AT)		61.0			8.3	13.1	14.0	13.5	12.1											
ALS Structural Biology Support Facility		7.9			0.6	4.7	2.6													
ALS Beamlines Initiative (KC)		43.9			9.6	15.0	13.0	6.3												
Chemical Dynamics Research Lab (KC)		104.6			11.7	28.2	29.8	24.4	10.5											
SUBTOTAL - PROPOSED PROGRAM RELATED		242.1	0.0	0.0	0.0	32.4	76.6	65.3	45.2	22.6										

Table 4-1. Continued

Project	Subprog	TEC	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008
PROPOSED MEL-FS PROJECTS:																				
Envir Monitor & Indus Hygiene Bldg	TTR	20.0																		
Roadway Safety & Stabilization, Ph I	GPF-EHS	5.4	1.5	0.5	15.0	3.0														
Sanitary Sewer Restoration, Ph I	GPF-Mech	2.1	0.6	2.1	2.7															
Elec Sys Rehab, Ph IV - Bkby Sw St Rplc	GPF-Elec	5.5	0.3	1.8																
Med Serv Asbestos Abatement & Rehab	TTR	2.1	0.5	2.7	2.3															
Mech Equip Replc, Ph I	GPF-Mech	3.8	0.4	1.7																
Fire & Safety Sys Upgrd Proj, Ph II	TTR	4.0	0.5	3.3																
Admin Servs Addn - Bldg 50E/F 2nd Fl	GPF-Bldg	7.0			2.1	1.5														
Roof Replacements, Ph II	GPF-Bldg	5.0			1.0	3.6	2.4													
Elec Sys Upgrd, Ph V - Cntrl Sw St & Fdrr	GPF-Elec	5.5			0.5	2.5	2.0													
Hazardous Materials Safeguards, Ph II	TTR	6.5			0.5	3.0	2.0													
Building Modernization Project, Ph I	GPF-Bldg	8.0			0.6	2.8	3.1													
Facilities Building	GPF-Bldg	9.0			1.1	3.8	3.1													
Roadway Safety & Stab, Ph II	GPF-EHS	4.7			0.9	4.5	3.6													
Fire & Safety Sys Upgrd, Ph III	TTR	5.0			0.5	2.6	1.6													
Mech Equip Upgrd, Ph II	GPF-Bldg	4.0			0.5	2.5	2.0													
Maintenance Building Addition	GPF-EHS	5.0			0.4	2.1	1.5													
Roof Replacements, Ph III	GPF-Mech	5.0			0.5	2.5	2.0													
Mech Util Upgrd, Ph II	GPF-Bldg	4.1			0.4	2.2	1.5													
Sanitary Sewer Restoration, Ph II	GPF-Mech	4.0			0.6	3.3	2.1													
Seismic Safety Improvement Project	GPF-EHS	4.0			0.4	2.1	1.5													
Energy & Environment Building	GPF-Bldg	20.0			0.4	2.1	1.5													
Elec Sys Upgrd, Ph VI - Uptr Bkby Sw Sta	GPF-Elec	6.7			12.0	1.0	5.0													
Roadway Safety & Stab, Ph III	GPF-EHS	6.0			0.7	3.0	3.0													
Science Education and Visitor Center	GPF-Bldg	8.0			0.6	3.6	1.8													
Building Modernization Project, Ph II	GPF-Bldg	8.4			0.8	4.5	2.7													
Site Electrical Equip Replc, Phase I	GPF-Elec	4.5			0.7	4.2	3.5													
Mech Eng Replc Bldg	GPF-Bldg	11.3			0.4	2.5	1.6													
Mech Util Rehab, Ph III	GPF-Mech	6.0			1.4	2.5	7.4													
Roof Replacements, Ph IV	GPF-Bldg	4.4			0.8	3.4	1.8													
Mech Util Rehab, Ph IV	GPF-Mech	5.0			0.4	2.4	2.4													
Rehab of Bldg. 90	GPF-Bldg	4.0			0.5	2.7	1.8													
Rehab of Bldg. 64	GPF-Bldg	6.0			0.4	3.6														
Mech Util Rehab, Ph V	GPF-Mech	7.0			0.6	3.0	2.4													
Rehab of Bldg. 50	GPF-Bldg	6.0			0.8	5.2	1.0													
Rehab of Bldg. 70	GPF-Bldg	7.0			0.7	3.6	1.7													
Rehab of Bldg. 70A	GPF-Bldg	7.0			0.8	2.9	3.3													
Rehab of Bldg. 62	GPF-Bldg	7.0			0.8	2.8	3.4													
Roadway Safety & Stab, Ph IV	GPF-EHS	5.0			0.5	2.7	3.5													
SUBTOTAL - PROPOSED MEL-FS		250.0	0.0	0.0	0.0	3.8	16.2	40.1	31.1	25.7	27.5	32.7	25.9	13.1	11.5	11.0	9.9	1.5	0.0	0.0

Escalated at 2.1%, FY92; 3.4%, FY93; 4.3%, FY94; 4.5%, FY95; 4.7%, FY96; 4.7%, FY97.

7/17/92

TSI 927-31

Fig. 4-1. Twenty-year plan map.

areas between buildings will increase, making the Laboratory more attractive to the research community and the community at large.

Future land use is depicted in Figure 4-3.

Table 4-2 shows the percentage of the site used for structures and sites, roads, parking and paved areas, and open space.

Facility and Land Requirements. If the full

TSI 927-32

Fig. 4-2. Future landscape buffer zones.

Buffer-Zone	Views or Exposure	Building Density	Planning & Protection Criteria	Hydrology & Stability	Vegetation & Landscaping	Special Considerations
A Central Blackberry Canyon						
B West Strawberry Canyon	•			•	•	Forested area with creek
C Light Source Area	•				•	Bayview; eucalyptus, dawn redwoods, and cork oaks
D East Strawberry Canyon	•	•			•	Sequoia redwoods, building density
E Life Sciences Area		•			•	Dawn redwoods, other evergreens
F Grizzly Gate Perimeter				•	•	Forested area; evergreen and eucalyptus
G Northeast Perimeter	•			•		Slope stability
H Bevalac Perimeter		•		•	•	Stability, drainage, and exposure
I Blackberry Canyon	•				•	Slope stability; evergreen trees Exposure, eucalyptus trees

Table 4-2. Current and Future Land Use.

Use Category	Acres	Percent
Structures & Sites	22.9	16.6
Roads	16.2	12.2
Parking and Paved Areas	17.2	12.9
Open Space	77.8	58.3
Total	134.0	100.0

Fig. 4-3. Future land-use map.

TSI 927-33

Plan would result in a net increase of 0.38 Mgsf to the existing main site of the Laboratory, for a total of approximately 2.0 Mgsf. For comparison, the 1992 total, including current construction, consists of 1.62 Mgsf at the main site. The Laboratory's on-site space is now

TSI 927-34

Fig. 4-4. Functional areas and future building sites

100% utilized at an approximate 70% net to gross area efficiency. The usable on-site space is approximately 1.1 M net square feet. The building utilization efficiency is not projected to change significantly, although the efficiency of land use is expected to improve with the replacement of obsolete single- and two-story buildings with three- to five-story structures.

FUNCTIONAL AREAS

The functional planning areas are related groupings of facilities that enhance work efficiency and effectiveness (Figure 4-4). In general, parking is at the perimeter of these areas, and clusters of buildings form the core. The Master Plan identifies changes to all of the functional planning areas to allow for potential research activities and to conform to SDP objectives, planning concepts, and design guidelines. The Master Plan calls for the removal of 0.2 Mgsf of buildings and the renovation of 0.8 Mgsf of building space. Building sites are planned or reserved for 0.6 Mgsf of new construction.

Category/Project	Area (gsf)	Staff (heads)
Existing Buildings	53,400	52
A 2nd-Floor Addition/Replacement		
B 2nd-Floor Addition II	8,900	32
Net Total	62,300	84

Note: Area and staffing plans are for general estimating purposes only.

Fig. 4-5. 88-Inch Cyclotron Research Area.

The natural constraints of the site coupled with the desirability of maintaining efficient programmatic development have led to the delineation of the LBL site into seven functional planning areas. These subdivisions of the site, which are generally identified with specific research programs and/or support facilities, have been individually studied to ensure effective short- and long-range use.

88-Inch Cyclotron Research Area

88-Inch Cyclotron Research Area, located on a hillside terrace near the main entrance to LBL, includes 53,400 gsf (Figure 4-5). Functionally, the area will continue to be dedicated entirely to the 88-Inch Cyclotron and its close support facilities. A second floor addition is planned to support users and complements the forthcoming national Gammasphere project.

Central Research and Administration Area

Central Research and Administration Area houses the LBL Director's Offices and the main offices for Accelerator and Fusion Research, Administration, Earth Sciences, Energy and Environment, Engineering, Information and Computing Sciences, Nuclear Science, Physics, and Planning and Development (Figure 4-6). It encompasses 488,900 gsf and includes the majority of LBL's light laboratories and support offices as well as the cafeteria. A shortage of light laboratories and offices for existing programs remains, and a number of laboratory spaces in the Building 50-70 complex are still

Fig. 4-6. Central Research and Administration Area.

TSI 927-36

Category/Project	Area (gsf)	Staff (heads)
Existing Buildings	488,900	1,319
Additions/Replacements:		
A 2nd-Floor Addition		130
B Cafeteria Addition	41,000	
C Future Addition		
D Conference Center		
E 65 Replacement		
Subtotal		
Planned Removals	501,800	1,399
Net Total		

Note: Area and staffing plans are for general estimating purposes only.

TSI 927-37

Fig. 4-7. Bevalac Accelerator Complex.

Category/Project	Area (gsf)	Staff (heads)
Existing Buildings	355,000	494
Additions/Replacements:	98,000	196
A Building Addition		
B ILSE		
C Future Building Site		
D High-Bay Additions		
E Building Replacement		
F 3rd Floor Offices		
G Building Addition		
Planned Removals		
Net Total	418,900	602

Note: Area and staffing plans are for general estimating purposes only.

used for offices. An important element of the SDP is the construction of economical additions to existing buildings to provide office space with an initial priority at the second for addition to Building 50E and 50F. Building 90 and its trailer complex currently house Administration, EH&S, Plant Engineering Department, Energy and Environment, and Engineering Division's offices. Several of these functions are to be relocated to the Shop and Support Facilities Area. A seismic rehabilitation of Building 90 is critical to the Master Plan, and since parking is limited in this area the trailers will be removed as replacement office space becomes available.

Bevalac Accelerator Complex

Bevalac Accelerator Complex encompasses 355,000 gsf, including the Bevalac, heavy-laboratory experimental areas, cryogenic support facilities, staging areas, associated offices, and facilities for advanced accelerator research and development (Figure 4-7). An addition to Building 64 is planned for the Induction Linac Systems Experiments. The area has an extensive array of support utilities, crane and hoisting equipment, and related resources for future program needs. The Master Plan allows for the decommissioning of the Bevatron and SuperHILAC accelerators and shielding, but retention of the buildings housing the facilities. The plan allows continuing use as a heavy laboratory depending on

the specific long-term programmatic needs for nuclear physics, space research, biomedical applications, and heavy-ion fusion research.

Light Source Research and Engineering Area

Light Source Research and Engineering Area encompasses 15 acres and includes buildings enclosing 362,300 gsf of space (Figure 4-8). The dominant feature of this area is the dome of Building 6, which originally enclosed the 184-Inch Cyclotron and which has been remodeled to contain the ALS (scheduled to be completed in 1993). This area has excellent geographical and geotechnical qualities and natural topography especially suited to building sites for high-technology facilities, including the Chemical Dynamics Research Laboratory. Important near-term projects for utilization of the ALS are the ALS Beamline Initiative and the ALS Structural Biology Support Facility.

Shop and Support Facilities Area

Shops and Support Facilities Area encompasses the Craft Shops, Supply Services, Transportation, Motor Pool, Mechanical Shops, the Environment, Health and Safety Division, and the National Tritium Labeling Facility, totaling 167,800 gsf (Figure 4-9). The Hazardous Waste Handling Facility is to be relocated from this area to the east canyon in the Life Sciences Research Areas. Consolidation of the support facilities is to continue with the construction of the Safety and Support Services

Facility, the Environmental Monitoring & Industrial Hygiene Building, and a proposed Facilities Management building.

Materials and Chemistry Research Area

Materials and Chemistry Research Area encompasses the Materials and Molecular Research Laboratory, the National Center for Electron Microscopy, and the Surface Science and Catalysis Laboratory, totaling 124,000 gsf (Figure 4-10). Upgrades are proposed to the National Center for Electron Microscopy, and building sites are reserved for future development.

Life Sciences Research Area

Life Sciences Research Area encompasses 11 acres in the upper reaches of Strawberry Canyon and includes sites for a Human Genome Laboratory and facilities to consolidate research in Cell and Molecular Biology (Figure 4-11). Existing buildings and new construction of the Hazardous Waste Handling Facility in the east canyon, totaling 69,200 gsf include the Biomedical Laboratory and the Laboratory for Cell Biology. This area has significant potential for future development, including the Human Genome Laboratory and office/bridge facility to separate pedestrian and increased traffic flow. In the future, long-term studies will be undertaken to assess future area expansion potential.

GENERAL-PURPOSE CONSTRUCTION PROJECTS

Funded Utility Projects

The following projects are described briefly to identify the major objectives of each in the context of the need to rehabilitate and systematically maintain labwide electrical systems.

- East Canyon Electrical Safety Project East-Site Substation and Feeders. The Life Science Research Area and the Materials and Chemistry Research Area are currently served by a single 12-kV cable system. This project will establish a 12-kV power-distribution center near the intersection of Centennial Drive and Cyclotron Road and provide new 12-kV cabling to each major facility. Also included will be a new substation for Building 72 (National Center for Electron Microscopy) and an upgrade of the existing substation at Building 74 (Biomedical Laboratory) that serves both Building 74 and Building 83 (Cell Culture Laboratory).
- Original-Laboratory-Site Substation Project. This project will provide a new 12-kV power distribution center and replace existing 12-kV feeder cables in the oldest part of the Laboratory. The existing power-distribution center and feeder cables are beyond their useful life and are unreliable.

TSI 927-38

Fig. 4-8. Light Source Research and Engineering Area.

Proposed Electrical Utility Projects

- Blackberry-Canyon 12-kV Switching Station and Feeder. This project includes a new 12-kV power distribution center near the Bevatron (Building 51) that will initially serve the Central Research and Administration Area and the Bevalac Accelerator Complex. The distribution center will improve the reliability and operational capability of the existing 12-kV distribution system. Also, the existing duct-bank system will be upgraded, and deteriorated cables will be replaced.

Category/Project	Area (gsf)	Staff (heads)
Existing Buildings	167,800	371
Additions/Replacements	103,900	218
A Environmental Monitoring Addition		
B 77 Addition		
C 78 2nd-Floor Addition		
D Support Facilities Addition		
E Facilities Management Addition		
Subtotal		
Planned Removals	14,500	32
Net Total	257,200	557

Note: Area and staffing plans are for general estimating purposes only.

Existing buildings
Proposed replacement building
Proposed additions

TSI 927-39

Fig. 4-9. Shop and Support Facilities Area.

- Central Switching Station and Feeders. A new 12-kV power-distribution center will be installed near the Building 50 complex to serve the Building 50 complex, Buildings 70 and 70A, the 88-Inch Cyclotron, Building 55 (Research Medicine), and Building 90. New 12-kV power-distribution cables and duct-bank additions will be installed as required to replace existing equipment or to provide increased capacity.

Category/Project	Area (gsf)	Staff (heads)
Existing Buildings	124,000	244
Addition/Replacements	35,800	55
A Future Bldg. Site		
B 62 High-Bay Addition		
C NCEM Addition		
D NCEM User Facility		
Planned Removals	1,900	18
Net Total	157,900	281

Note: Area and staffing plans are for general estimating purposes only.

TSI 927-40

Fig. 4-10. Materials and Chemistry Research Area.

- **Upper Blackberry Switch Replacement.** The Upper Blackberry Switching Station will provide 12-kV interruptible and uninterruptible power to the Building 71 research complex. Included in the project will be new 12-kV feeder cables from the Grizzly main substation, a unit substation to provide low-voltage power,

secondary feeder cables, and equipment for power-factor correction.

- **Sitewide Electrical Equipment Replacement.** This project will replace electrical equipment including transformers, power switches, circuit breakers, switchboards, and motor controls that is critical to LBL's

Fig. 4-11. Life Science Research Area.

Category/Project	Area (gsf)	Staff (heads)
Existing Buildings	69,200	103
Additions/Replacements	110,400	213
A Bridge/Office Annex		
B Cell & Biology Lab. II		
C Life Science Additions		
D Human Genome Lab.		
E Future Building Sites		
F Future Building Site		
G Future Building Site		
Subtotal	94,200	154
Planned Removals	500	0
Net Total	179,100	226

Note: Area and staffing plans are for general estimating purposes only.

operation and whose failure rate and useful remaining life warrant replacement.

Proposed Mechanical Utility Projects

- Rehabilitate Site Mechanical Utilities — Phase II. This project is a continuation of Phase I rehabilitation; it includes the addition of a 4-MW cooling-tower cell to the load center serving the Light Source Research and Engineering Area and upgrades to the compressed-air facilities in Buildings 51 and 70.
- Rehabilitate Site Mechanical Utilities — Phase III. This project extends the Light Source Research and Engineering Area, mechanical-utility corridor, and distribution system. Deteriorated underground piping will be replaced.
- Rehabilitate Site Mechanical Utilities — Phase IV. Mechanical utilities will be extended to the east canyon area. Deteriorated piping in certain hillside areas will be replaced.
- Rehabilitate Site Mechanical Utilities — Phase V. Portions of deteriorated utilities will be replaced statewide. A 300,000-gallon water tank above the Buildings 74-83 complex will be constructed for added fire protection.
- Replace Cooling Towers and Chillers — This project replaces 15 cooling towers

and 9 refrigeration chillers that are more than 20 years old.

- Sitewide Mechanical Equipment Replacement — Phase I. Portions of building mechanical equipment and systems having the most serious deficiencies will be replaced, including boilers, air handlers, automatic controls, deionized-water units, air compressors, ducts, and piping.

Proposed Construction Projects — General Purpose

- Building 50E & F Addition — This addition is vital for providing office space to house staff for meeting new DOE management and administrative requirements and to consolidate staff from off-site leased space for improved operational efficiency and overhead cost control.
- Facilities Management Building. This facility is vital for consolidation of Plant Engineering and Construction and Maintenance Personnel. The facilities would result in improved resource managements cost and overhead control, elimination of temporary trailers, and demolition of substandard structures.
- Energy and Environment Building — This facility will allow for consolidation of energy and environment and earth sciences research programs, and other research programs housed in substandard

facilities. This modernization project would result in the demolition of substandard space and temporary structures.

- Science Education and Visitor Center — This facility would provide for office, training, conference and displays for Science and Engineering Education Center personnel, for teacher and for students, and for visitors to the laboratory. The facility would allow for a consolidation of programs and provide adequate space for on-site functions that now may be relocated off site due to lack of space.

Other Health and Safety Projects

- Safety and Support Services Facility. This building will be a three-story structure of 42,000 gsf to be occupied by the Environmental Health and Safety, Materiel Management, and Electronics Engineering Departments. Three old substandard buildings and five trailers will be removed.
- Environmental Monitoring and Industrial Hygiene Building. This project will provide adequate space to meet DOE requirements for monitoring, safety seminars, industrial hygiene, occupational health, radiation safety, waste minimization, environmental protection and remediation, hazardous waste management, and EH&S training needs. The project responds to deficiencies in facilities and equipment identified by the

1990 Technical Safety Appraisal and the 1991 Tiger Team Assessment.

- Traffic Circulation and Parking Improvements. Road rehabilitation is required to facilitate the efficient and safe movement of people and materials throughout the site. Roads need to be widened, base materials need to be replaced to handle current traffic loadings, acute curves and blind spots need to be eliminated, and roadways on steep hillsides need to be stabilized. To improve safety and appearance a study of signs on the LBL site is being conducted. A sign plan will be developed based on the results of this study. The plan calls for two phases of road rehabilitation (funded by MEL-FS).

PROGRAM-RELATED CONSTRUCTION PROJECTS

Proposed Construction Projects — Program Related

- Human Genome Laboratory. This facility, an essential component of the Human Genome Center at LBL, will be located in the Life Sciences Research Area. This location provides direct access via Centennial Drive to the UCB Campus, where major LBL research facilities are situated at Donner Laboratory and the Chemical Biodynamics Laboratory. The Life Sci-

ences Research Area now includes existing cell and molecular biology research facilities in the Biomedical Laboratory, Building 74, and the Cell and Biology Laboratory, Building 83, that are used for related research on gene expression and hemopoiesis. Modifications and additions to these buildings are now underway to provide facilities for human genome research and for relocation of Life Sciences Research at Building 934 to this area.

- ALS Life Sciences Support Facility. The proposed facility will provide two ALS beamlines and support space for specimen preparation and support services for visiting university and industry scientists and core LBL personnel. Renovation of Building 80 and additional construction within Building 6 are proposed.
- Chemical Dynamics Research Laboratory. This proposed facility would combine photon beams from the ALS with advanced laser and molecular beam apparatus to explore the interaction of radiation with matter at the molecular level.
- Bevalac. The Bevalac is proposed for decommissioning unless there is programmatic support for space radiation studies. The initial phase of securing the facility will be funded by the office of Energy Research. The decommissioning program for the accelerator and its shielding would be supported by the office of Environmental Restoration and Waste Management.

GENERAL PLANT PROJECTS

Over the last 20 years, LBL has found it necessary to rely upon General Plant Projects (GPP) funding for almost all improvements, replacements, and maintenance and repair projects for physical-plant facilities that required capital funding. LBL has used its GPP funds to solve problems related to seismic safety, fire protection, and industrial safety. In addition, required small capital additions or modifications required for program initiatives were accomplished with GPP funds.

General deterioration and obsolescence of LBL facilities, which are among the oldest found at national laboratories, has been unarrested in the past, and the backlog of deficiencies has continued to grow. The average age of LBL buildings is now 30 years, and many basic utility load centers and distribution systems are now over 40 years old. The Laboratory is in a situation where very significant general-plant outlays for major replacement projects (such as 12-kV cabling, switching stations, cooling towers, roofs, boilers, chillers, gas lines, water lines, etc.) will be necessary on an emergency basis over the next several years.

With GPP funds at the \$3.1-M level, many maintenance and physical plant projects cannot be funded. However, progress in increasing GPP funding to \$6.0 M/year is needed to ensure the success of the Laboratory's rehabilitation program. These increased funds would be used for essential

environmental health and safety needs, and the remainder would continue to support both multiprogram and small programmatic initiatives.

MAINTENANCE AND ENERGY CONSERVATION

Many of LBL's facility-related maintenance costs stem from aged and obsolescent buildings and deteriorated utilities. (This plan calls for about 110,000 gsf of World War II structures that require excessive maintenance to be demolished as soon as economically practical.)

LBL has carried out a formal maintenance management program for over 30 years and has included a computerized scheduled maintenance system for more than 25 years. Budget requests are based upon plant facilities inspections coupled with special engineering studies and reviews by LBL's Plant Engineering Department and consulting firms in specialized areas such as cranes, elevators, boilers and pressure vessels, fire protection, slope stability, storm drainage, seismic safety, industrial safety, underground utilities, photography, and energy-use surveys. An annual work plan and a budget are developed and reviewed at three management levels before being approved at the directorate level.

LBL is undertaking activities to coordinate the current planning program to assure the goals of condition assessment survey (CAS) and the Capital Asset Management Program (CAMP) are being achieved. The formulation of the maintenance budget is an iterative process that takes into account related work plans for noncapital alterations, general plant projects, multiprogram general-purpose line items, and regular line-item construction. This process begins with a zero-base budget study, includes consideration for other operating budget priorities, and culminates in a formalized work plan for the fiscal year. Since maintenance and repair requirements are also generated continuously throughout the fiscal year, a formal system provides for timely consideration and processing of these requirements. Longer-range work plans are being developed for items of major maintenance, such as reroofing, paving, slope-stabilization projects, major equipment-overhaul projects, rehabilitation, building exterior painting, and utilities replacements. A five-year projection is made annually with specific projects itemized over the first three years and lumped for the last two.

The long-range plan addresses many of the major maintenance issues. The reroofing, road projects, slope stabilization, general-purpose facilities replacement projects, and some

environmental health and safety improvements are examples.

The strategy for accomplishing environmental improvements, required repairs, and upkeep relies on increasing capital outlays and streamlining the existing maintenance program and making it more cost effective. Emergency replacements that may be necessary during the next few years can only be achieved with GPP funding. Funding for longer-term general-purpose improvements to sustain utilities and other facilities has been requested under the MEL-FS program. Currently, the Laboratory is using noncapital alterations and GPP funding to the extent possible to augment maintenance-account funding. In addition, the Plant Engineering and Construction and Maintenance Departments have begun developing a comprehensive list of backlogged maintenance, repair, and replacement projects for both capital and noncapital funding. A maintenance engineer has improved LBL scheduled maintenance and repairs, to increase awareness of priorities for capital repairs and replacements, and to develop long-term planning mechanisms. Laboratory management is developing long-term plans for sustaining LBL facilities through GPP and MEL-FS programs.

5. FIVE-YEAR PLAN

CONTENTS

5. Five-Year Plan	5-1
Planning Assumptions and Rationale	5-2
Five-Year Programmatic and MEL-FS Plans	5-4
88-Inch Cyclotron Research Area	5-5
Central Research and Administration Area	5-5
Bevalac Accelerator Complex	5-5
Light Source Research and Engineering Area	5-9
Shops and Support Services Area	5-9
Materials and Chemistry Research Area	5-9
Life Sciences Research Area	5-9
Sitewide MEL-FS Projects	5-9
General Plant Projects	5-10
General Purpose Equipment	5-10
Maintenance Plans	5-10
In-House Energy Management	5-11
Facilities Decommissioning Plan	5-11
Information Technology Resources	5-11

PLANNING ASSUMPTIONS AND RATIONALE

The Master 20-Year Plan described in Chapter 4 provides the institutional and strategic planning framework for making informed decisions for the long term. Chapter 5 describes near-term facilities needs based on current assessment of requirements. Resources, and the resulting patterns of construction and development dependent on these resources, may vary from year to year, and priorities are adjusted accordingly. Specific construction projects, improvements, and demolitions and removals are described below.

Site and facilities planning for the 5-year period is based on the *LBL Draft Institutional Plan FY 1993-1998*, prepared in April 1992. Projects are derived from the Laboratory's response to DOE's national program plans and represent either important new facilities or the rebuilding of existing infrastructure to accommodate research and support activities. Five-year plans provided by the Office of Energy Research for each of its Research Program Offices and other DOE Assistant Secretarial Offices are also used.

To address critical needs, the Laboratory analyzes projects identified by both research and support staff as having environmental, health, and safety implications and/or as having the potential to interrupt research programs. The current funds from all sources are inadequate to fill all of the identified needs within a single fiscal year or even within the five-year planning period. From the available information, the Office for Planning and Development, the Plant Engineering Department, and the Environment, Safety & Health

Division propose priorities for each of the critical projects. Priorities are established by the Director's Action Committee and coordinated with the DOE San Francisco Field Office and UC.

The Five-Year Plan is based primarily on capital funding from Programmatic, MEL-FS, GPP, and GPE sources (Tables 5-1 & 5-2). Other sources of funding are the In-House Energy Management Funds and operating funds from the Environmental Restoration and Waste Management Program. A detailed

Table 5-1. Programmatic Facilities (Fiscal Year/\$M).

Project Title	TEC	Schedule
Advanced Light Source (KC)	99.5	1987-1993
Human Genome Laboratory (HA)	24.9	1994-1997
Induction Linac Systems Experiments (AT)	61.0	1994-1998
ALS Structural Biology Support Facilities (HA)	7.9	1994-1996
ALS Beamline Initiative (KC)	43.9	1994-1997
Chemical Dynamics Research Laboratory (KC)	104.6	1994-1998

Table 5-2. Five-year Capital Improvement Plan (Fiscal Year, \$M).

Category	1992	1993	1994	1995	1996	1997	1998
MEL-FS	11.0	10.7	21.1	20.8	33.7	25.0	23.2
GPP	2.5	3.1	4.0	4.0	4.0	4.0	4.0
GPE	1.7	1.7	1.8	1.8	1.8	1.8	1.8

analysis of needs has been completed by Laboratory staff for each of these funding categories. Needs for GPE and GPP far exceed the expected funding. For example, GPE needs over the next five years total \$38.2 M, whereas GPE funding levels are expected to be \$2-3 M per year. GPP and MEL-FS needs and funding resources have similar disparities. To maximize the strategic investment in plant and equipment, the Laboratory's MEL-FS, and GPE needs have been categorized and prioritized (Figures 5-1 and 5-2). MEL-FS and GPP funding from FY 1982 through FY 1991 is shown in Figure 5-3.

Fig. 5-1. Five-year MEL-FS backlog.

FIVE-YEAR PROGRAMATIC AND MEL-FS PLANS

Table 5-3 lists the capital funding profiles for individual projects for the next 5 years. Figure 5-4 shows the proposed changes to the site for this period. Actual project starts are subject to funding constraints and subsequent changes in priority. The Five-Year Plan is in concert with the Master 20-Year Plan in that incremental additions, replacements, or improvements are all tested for conformance to the established Design Guidelines and Site Planning Concepts. Furthermore, information such as the Old Town Site Utilization Study is continually incorporated into planning and analysis when made available. Table 5.3 lists construction projects under the current five-year plan, and Figure 5-4 identifies the locations of proposed major construction projects.

Fig. 5-2. Five-year GPE needs.

TSI 927-43

88-Inch Cyclotron Research Area

The changes planned for this area are included as elements of the sitewide MEL-FS projects for roads, roofs, and mechanical and electrical utilities. A GPP project will add a small second-story addition, and modifications to parking will add 7 parking spaces.

Central Research and Administration Area

The Instrument Support Laboratory Rehabilitation project is scheduled for completion in FY 1992. Other projects include Hazardous Materials Safeguards, Phase 1; Admin. Services addition, and elements of the sitewide projects. A small library addition is also planned.

Bevalac Accelerator Complex

Decommissioning of the Bevalac is being jointly evaluated by the Laboratory and the DOE. MEL-FS projects include elements of sitewide projects, Slope and Seismic Stabilization, and the Blackberry Switching Station and Feeders. Groundwater contamination problems require mitigation, and funding is proposed from the MEL-FS Program.

TSI 927-44

Fig. 5-3. Past MEL-FS and GPP funding.

Table 5-3. Lawrence Berkeley Laboratory Five-Year Construction Plan (FY BA, \$M)

Project	TEC*	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001
FUNDED PROGRAM RELATED PROJECTS:												
Advanced Light Source	99.5	23.0	6.4									
Biomedical Isotope Facility	2.3	1.0	0.7	0.6								
SUBTOTAL - FUNDED PROGRAM RELATED	101.8	24.0	7.1	0.6								
FUNDED MEL-FS PROJECTS (KG):												
Envir Health & Safety Proj (ER Program)	13.2	1.6	0.5	1.5	2.0							
Original Labsite Substation	3.0	0.0	2.7									
Instrument Support Laboratory Rehabilitation	2.1	0.0	1.9									
Slope and Seismic Stabilization	3.7	2.4	0.8									
Building 90 Seismic Rehabilitation	6.8	3.7	2.7	0.4								
East Canyon Electrical Safety Project	3.9		0.4	1.5	2.0							
Roof Replacements, Phase I	2.5		2.0	0.5								
SUBTOTAL - FUNDED MEL-FS PROJECTS	35.2	7.7	11.0	3.9	4.0							
FUNDED ERWM PROJECTS:												
Hazardous Waste Handling Facility	12.0	0.0	1.6		5.8							
Envir Health & Safety Proj (ERWM Program)	1.8	0.0	0.0	0.0	0.7							
SUBTOTAL - FUNDED ERWM PROJECTS	13.8	0.0	1.6	0.0	6.5							
TOTAL FUNDED	150.8	31.7	19.7	4.5	10.5							
BUDGETED MEL-FS PROJECTS (KG)												
Safety & Support Services Facility	9.9			3.0	4.5	2.4						
Fire & Safety Systems Upgrade Proj, Ph I	4.6			1.5	2.0	1.1						
Upgrad of Site Mech Util, Ph II - Sewer Monit	7.1			0.8	3.4	2.9						
Hazardous Materials Safeguards, Ph I	5.1			1.5	3.6							
TOTAL BUDGETED MEL-FS PROJECTS	26.7	0.0	0.0	6.8	13.5	6.4						
TOTAL FUNDED and BUDGETED	177.5	31.7	19.7	11.3	24.0	6.4						
PROPOSED PROGRAM RELATED PROJECTS:												
Human Genome Laboratory (KP)	24.7				2.2	15.6	5.9	1.0				
Induction Linac Systems Experiment (AT)	61.0				8.3	13.1	14.0	13.5	12.1			
ALS Structural Biology Support Facilities	7.9				0.6	4.7	2.6					
ALS Beamlines Initiative (KC)	43.9				9.6	15.0	13.0	6.3				
Chemical Dynamics Research Laboratory (KC)	104.6				11.7	28.2	29.8	24.4	10.5			
SUBTOTAL - PROPOSED PROGRAM RELATED	242.1	0.0	0.0	0.0	32.4	76.6	65.3	45.2	22.6			

Table 5-3. continued

	Project	Subprog	TEC*	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001
PROPOSED MEL-FS PROJECTS:														
FY 1994	Environ Monitoring & Industrial Hygiene Bldg	TTR	20.0											
	Roadway Safety & Stabilization, Phase I	GPF-EHS	5.4											
	Sanitary Sewer Restoration, Phase I	GPF-Mech	2.1											
	Elec Sys Rehab, Ph IV - Bldgby Swit Sta Replc	GPF-Elec	5.5											
	Medical Serv Asbestos Abatement & Rehab	TTR	2.1											
FY 1995	Mechanical Equipment Replacement, Ph I	GPF-Mech	3.8											
	Fire & Safety Systems Upgrd Project, Ph II	TTR	4.0											
	Admin Services Addn - Bldg 50E/F 2nd Fl	GPF-Bldg	7.0											
	Roof Replacements, Ph II	GPF-Bldg	5.0											
	Elec Sys Upgrd, Ph V - Cntrl Swit Sta & Feeds	GPF-Elec	5.5											
	Hazardous Materials Safeguards, Phase II	TTR	6.5											
	Building Modernization Project, Ph I	GPF-Bldg	8.0											
	Facilities Building	GPF-Bldg	9.0											
	Roadway Safety & Stabilization, Phase II	GPF-EHS	4.7											
	Fire and Safety Systems Upgrade, Phase III	TTR	5.0											
FY 1997	Mechanical Equipment Upgrade, Phase II	GPF-Mech	4.0											
	Maintenance Building Addition	GPF-Bldg	5.0											
	Roof Replacements, Ph III	GPF-Bldg	4.1											
	Mechanical Utilities Upgrade, Phase II	GPF-Mech	6.0											
	Sanitary Sewer Restoration, Phase II	GPF-Mech	4.0											
FY 1999	Seismic Safety Improvement Project	GPF-EHS	4.0											
	Energy & Environment Building	GPF-Bldg	20.0											
	Elec Sys Upgrd, Ph VI - Upper Bldgby Swit Sta	GPF-Elec	6.7											
	Roadway Safety & Stabilization, Phase III	GPF-EHS	6.0											
	Science Education and Visitor Center	GPF-Bldg	8.0											
	Building Modernization Project, Ph II	GPF-Bldg	8.4											
	SUBTOTAL - PROPOSED MEL-FS PROJECTS		169.8	0.0	0.0	0.0	3.8	16.2	40.1	31.1	25.7	24.9	23.0	5.0

Escalated at 2.1%, FY'92; 3.4%, FY'93; 4.3%, FY'94; 4.5%, FY'95; 4.7%, FY'96; 4.7%, FY'97.

* TEC includes costs prior to 1991.

7/17/92

TSI 927-45

Fig. 5-4. Proposed major construction projects FY 1993-FY 1995.

Light Source Research and Engineering Area

Four programmatic projects are funded or proposed for this area. The Advanced Light Source is to be completed by FY1993, and the ALS Structural Biology Support Facilities project is proposed to begin in FY 1994. Two additional ALS beamlines and associated support space for users are also proposed for FY 1994 under the ALS Beamline Initiative project. MEL-FS projects include elements of sitewide projects and Medical Services Abestos Abatement & Rehabilitation Project.

Shops and Support Services Area

The Safety and Support Services facility, an MEL-FS funded building, is budgeted for FY 1993 to consolidate Environmental, Safety and Health activities and to increase efficiencies in materiel management. The construction of this building is also related to the systematic restoration of the Original Laboratory Site within the Light Source Research and Engineering Area, since it involves removal of several 1940s wood-frame buildings and trailers. Other MEL-FS projects are the Environmental Monitoring and Industrial Hygiene Building and a Facilities Building. A portion of the Slope and Seismic Stabilization project will correct major landslide problems in the Shops and Support Services Area.

Materials and Chemistry Research Area

A combination office and light-duty laboratory, the Energy and Environment Building, consolidating related research personnel and activities, is planned to begin in FY 1998. Elements of the sitewide MEL-FS projects involve this area, including the East Canyon Electrical Safety project.

Life Sciences Research Area

One programmatically funded building is planned in this area, the Human Genome Laboratory. This primarily wet-laboratory building is proposed for FY 1994 and is needed to consolidate and house the activities of the Human Genome Center. The Hazardous Waste Handling Facility was funded under EWRM and is scheduled to be completed in FY 1995. Improvements in office space and circulation to improve efficiency and pedestrian safety are also planned, with an office annex/bridge addition between Buildings 74 and 83.

Sitewide MEL-FS Projects

As mentioned above, most functional areas benefit from sitewide funded or proposed projects: Electrical Systems Rehabilitation and Improvements, Sitewide Mechanical and Electrical Rehabilitation projects, and Roof and Road replacements.

GENERAL PLANT PROJECTS

General Plant Projects (GPP) funds have been provided by DOE's Nuclear Physics Division to fund priority construction projects that have a funding ceiling of \$1.2 M. Funding to date has been inadequate to meet the Laboratory needs in a timely schedule. This program has a significant backlog of projects exceeding \$20 M. One-half of this backlog is for environment, health, and safety needs and one-half is for general improvements and replacements. The Laboratory also classified the projects as institutional (50%) and programmatic (50%), although some of the projects related to programs serve safety needs such as PCB capacitor replacement. Increasing GPP funding to \$6 M annually and increasing the ceiling from \$1.2 M to \$2.0 M would ensure the success of the Laboratory's safety rehabilitation program and help reduce the current backlog of projects over the next five years. Support and coordination for GPP through the Office of Energy Research would facilitate effective management of GPP and overall facilities support needs. The current split between programmatic and non-programmatic projects is approximately 50/50.

GENERAL PURPOSE EQUIPMENT

Essential support equipment has been funded through DOE's Nuclear Physics Division. LBL's Five-Year GPE Plan identifies needs based on a range of criteria, including environment, safety, and health; legal requirements; failed, worn, inefficient, or obsolete equipment; substandard performance; or increased workload and demand. The current funding level of \$1.7 M/year is inadequate to meet the Laboratory needs. Currently there is a \$38 M equipment backlog for environmental monitoring and fire safety, physical-plant maintenance, mechanical and electrical shops, transportation, and data processing and communications. Increasing General Purpose Equipment (GPE) support to \$4 M/year would provide a basis for reducing the backlog. Consolidated GPE management at the level of the Office of Energy Research would facilitate the implementation of an integrated and longer-range GPE plan.

IN-HOUSE ENERGY MANAGEMENT

LBL has successfully applied In-House Energy Management funding to reduce electrical-power costs. Energy centers with automated sensing and control systems are being established. Lighting modifications have substantially lowered costs by allowing more individual control of work-space lighting and by using more-efficient fixtures, bulbs, and ballasts. New buildings are designed with energy-efficient components, and existing buildings are being systematically retrofitted.

MAINTENANCE PLANS

Maintenance plans and budgets are developed annually within an overall five-year planning and safety management strategy. The Laboratory has improved its current maintenance scheduling system and backlog of maintenance projects through implementation of the site-wide Plant Inspection and Maintenance

System Upgrade Program. These include noncapital alterations, general plant projects, and multiprogram general-purpose line items. Requirements are identified by periodic reviews and inspections, and new priorities are developed during the fiscal year.

The operating expenses for maintenance include physical-plant maintenance, mobile-equipment maintenance, and noncapital alterations related to maintenance. In addition, specialized maintenance related to shop, computer, and telecommunications facilities is also performed.

The current strategy for improving maintenance relies on strengthening the capital outlays, continuing the operating-costs efforts, and implementing the maintenance planning system. This allows the Laboratory to sustain DOE facilities while planning for maintenance-cost economies. These economies can be achieved through the replacement of existing obsolete and high-maintenance-cost facilities with modern facilities and equipment supported by increased MEL-FS, GPP, and GPE funds.

FACILITIES DECOMMISSIONING PLAN

The development of new program directions for nuclear physics will result in the phase-out of LBL's Bevalac nuclear physics program in FY 1994. Unless support for the Space Exploration Initiative or work for others (e.g., NASA) warrants continued use, the Bevalac will undergo decommissioning in accordance with the FY 1992-1996 LBL Decommissioning Plan (see Table 5-4). The major program costs for decommissioning will be borne by ERWM. Associated preparation and transfer costs prior to ERWM acceptance will be borne by the Office of Energy Research. The Laboratory

conducts periodic reviews of facilities that may become inactive. Other facilities to be decommissioned include cobalt irradiators and a standby propane storage facility.

INFORMATION TECHNOLOGY RESOURCES

The foundation of the LBL long-range computing strategy is the development and operation of a distributed computing network offering access to a large-scale, interactive, high-speed computing resource, shared archival mass storage, satellite computers, and workstations. The internal LBL computer

network (LBLnet) is supplemented by national and international networks. The specific components of LBL's distributed network are listed below.

- A flexible and efficient communications network able to connect existing and future components of the distributed system
- Access to DOE's OER high-speed computing resources at the National Magnetic Fusion Energy Computer Center (NMFECC) and Florida State University
- A modern mid-scale interactive computer system in the LBL Central Computing Facility (CCF) and distributed computers in the network that are available for specialized needs
- Workstations ranging from simple terminals to sophisticated microprocessor-based systems

- A large automated archival mass-storage facility that supports all the computational resources throughout the communications network

Although individual computing needs change frequently, the network system permits flexible and versatile use of computational resources. This strategy is being supported by continuing development of the CCF and the continuing extension and development of the LBLnet.

Table 5-4. Facilities Decommissioning Plan (\$M)

Project	FY 1993	FY 1994	FY 1995	FY 1996
Bevalac	—	5.0	23.4	42.1
Gamma Irradiators	—	0.3	—	—
Propane Plant	—	0.2	—	—
Decommissioning Base Program	0.07	0.4	0.6	0.6
Total	0.07	5.9	24	42.7

APPENDIX A

BIBLIOGRAPHY

Architectural Studies

Environmental Monitoring and Industrial Hygiene Building, Conceptual Design Report, Lawrence Berkeley Laboratory Plant Engineering Department, February 1992.

Human Genome Laboratory, Conceptual Design Report, Lawrence Berkeley Laboratory Plant Engineering Department, February 1992.

Induction Linac Systems Experiment, Conceptual Design Report, Lawrence Berkeley Laboratory Plant Engineering Department, April 1992.

ALS Structural Biology Support Facilities, Conceptual Design Report, Lawrence Berkeley Laboratory Plant Engineering Department, April 1992.

ALS Beamlines Initiative, Conceptual Design Report, Lawrence Berkeley Laboratory Plant Engineering Department, April 1992.

Chemical Dynamics Research Laboratory, Conceptual Design Report, Lawrence Berkeley Laboratory Plant Engineering Department, February 1992.

Safety & Support Services Facility, Conceptual Design Report, Lawrence Berkeley Laboratory, February 1991.

Hazardous Waste Handling Facility, Conceptual Design Report, Lawrence Berkeley Laboratory, April 1990.

Building 90 Seismic Rehabilitation, Conceptual Design Report, Lawrence Berkeley Laboratory, February 1990

Roof Replacements, Phase I, Conceptual Design Report, Lawrence Berkeley Laboratory, February 1990.

Instrumentation Support Laboratory Rehabilitation, Conceptual Design Report, Lawrence Berkeley Laboratory, January 1989.

1-2 GeV Synchrotron Radiation Source, *Conceptual Design Report*, Lawrence Berkeley Laboratory Plant Engineering Department, July 1986.

1-2 GeV Synchrotron Radiation Source, *Conceptual Design Report, Supplement A: Conventional Facilities Details*, Lawrence Berkeley Laboratory Plant Engineering Department, July 1986.

1-2 GeV Synchrotron Radiation Source, *Conceptual Design Report, Supplement B: Cost Estimate Details*, Lawrence Berkeley Laboratory Plant Engineering Department, July 1986.

Environment and Landscape Studies

Supplemental Environmental Impact Report for the Proposed Renewal of the Contract Between DOE and the Regents of UC for Operation and Management of LBL, Draft, prepared by Ira Fink and Associates, Inc., April 1992.

Construction of Replacement Hazardous Waste Handling Facility at LBL, Environmental Assessment, April 1992.

Operation Plan for Hazardous Waste Handling Facility, Lawrence Berkeley Laboratory, March 1991.

Landscape Master Plan, Phase I Report, LBL, prepared by Eldon Beck and Associates, May 1990.

Environmental Monitoring and Remediation Facilities, Phase I, Conceptual Design Report, Lawrence Berkeley Laboratory Plant Engineering Department, January 1989.

Slope and Seismic Stabilization Above Bevatron & Mechanical Shops, Conceptual Design Report, Lawrence Berkeley Laboratory Plant Engineering Department, January 1989.

1-2 GeV Synchrotron Radiation Source at Lawrence Berkeley Laboratory, *Environmental Assessment*, prepared by Lawrence Berkeley Laboratory Plant Engineering Department, assisted by Ira Fink and Associates, Inc., August 1989.

Storm Drainage Study, Strawberry Creek Watershed at University of California, Lawrence Berkeley Laboratory, G.T. Kuntz, Consulting Engineer, prepared for the Lawrence Berkeley Laboratory Plant Engineering Department, February 1980.

Buildings 62/72 Site Utilization Study, prepared for Lawrence Berkeley Laboratory by MBT Associates, November 1979.

Omnibus Environmental Assessment, Volume I, Lawrence Berkeley Laboratory, 1976.

Health and Safety Studies

Medical Services Building Asbestos Abatement and Rehabilitation, Conceptual Design Report, Lawrence Berkeley Laboratory, February 1992.

Environmental Health and Safety Project, Conceptual Design Report, Lawrence Berkeley Laboratory, February 1992.

Fire and Safety Systems Upgrade, Phase I, Conceptual Design Report, Lawrence Berkeley Laboratory, February 1991.

Hazardous Materials Safeguards, Phase I, Conceptual Design Report, Lawrence Berkeley Laboratory, February 1991.

Annual Environmental Monitoring Report of the Lawrence Berkeley Laboratory, 1986, prepared by the Engineering Division for the U.S. Department of Energy, April 1987.

Health and Safety Manual, PUB-3000, Lawrence Berkeley Laboratory, prepared for the U.S. Department of Energy by Lawrence Berkeley Laboratory, July 1986.

Energy Conservation and Utilities Studies

Electrical Systems Rehabilitation, Phase IV — Blackberry Switching Station Replacement, Conceptual Design Report, Lawrence Berkeley Laboratory Plant Engineering Department, February 1992.

Mechanical Equipment Replacement, Phase I, Conceptual Design Report, Lawrence Berkeley Laboratory, February 1992.

Sanitary Sewer Restoration, Phase I, Conceptual Design Report, Lawrence Berkeley Laboratory, February 1992.

Upgrade of Site Mechanical Utilities, Phase II, Conceptual Design Report, Lawrence Berkeley Laboratory, February 1991.

East Canyon Electrical Safety Project, Conceptual Design Report, Lawrence Berkeley Laboratory, February 1990.

Original Labsite Substation, Conceptual Design Report, Lawrence Berkeley Laboratory Plant Engineering Department, January 1989.

East Site Substation and Feeders, Conceptual Design Report, Lawrence Berkeley Laboratory Plant Engineering Department, March 1988.

Ten-Year In-House Energy Management Plan, FY 1985 to FY 2000, Lawrence Berkeley Laboratory, May, 1992.

Rehabilitate Utilities in the Original Laboratory Site, Conceptual Design Report, Lawrence Berkeley Laboratory, various consultants, 1983.

Parking and Traffic Studies

Roadway Safety and Stabilization, Phase I, Conceptual Design Report, Lawrence Berkeley Laboratory Plant Engineering Department, February 1992.

Lawrence Berkeley Laboratory, 1986 Staff and Guest Housing and Transportation Survey, 3 volumes, conducted for Lawrence Berkeley Laboratory by Ira Fink and Associates, Inc., Cross-Tabulations, July 1986 and September 1986.

General Planning Documents

LBL Institutional Plan, FY 1993–1998, Draft, May 1992.

FY 1992 Site Development Plan, Lawrence Berkeley Laboratory, March 1992.

LBL Site Planning Review, January 1992.

LBL Facilities Decommissioning Plan, FY 1992–1997, September 1991.

LBL Space and Personnel Database, 1991.

Strategic Facilities Initiative Report, Marginal Facilities Plan, FY 1989–1994, March 1989.

Fire Management Plan for the UC Hill Area, prepared for the University of California, Berkeley, Environmental Health and Safety, by Wildland Resource Management, Consultants, December 1986.

LBL Facilities Renewal Plan, FY 1988–2002, Lawrence Berkeley Laboratory, September 1986.

Supplement to the April 1984 Site Development Plan, Lawrence Berkeley Laboratory, December 1987.

Long Range Site Development Plan, Lawrence Berkeley Laboratory, April 1984.

University of California, Berkeley, Hill Area Dewatering and Stabilization Studies, conducted by Converse Consultants, May 1984.

Chemical and Materials Sciences Laboratory, Building 62, Conceptual Design Report, Lawrence Berkeley Laboratory, March 1979.

Long Range Development Plan, University of California, Berkeley, prepared by the Office of Architects and Engineers under the auspices of the Campus Planning Committee, June 1962.

Long Range Development Plan, Radiation Laboratory, University of California, November 1957.

Long Range Plan, Radiation Laboratory, Berkeley Hill Area, University of California, October 1953.

APPENDIX B

LBL MAP WITH BUILDING NUMBERS (See Appendix C for Building Descriptions)

LBL OFF-SITE BUILDING NUMBERS

Building Number	Building Name/Description	Building Number	Building Name/Description
Off-Site Leased Buildings			
901	Receiving/Warehouse — 1450 64th St., Emeryville	926	Morgan Hall
901A	Used Furniture; Excess Material — 1450 64th St., Emeryville	928	Haviland Hall
934	DYMO Bldg: Printing Plant, Cell & Molecular Biology — 91 Bolivar Dr., Berkeley	952	Moses Hall
		953	Earth Sciences
		983	Wurster Hall
936	CFO and OSRA — 2070 Allston Way, Berkeley	984	David Hall
		985	Garage
		986	Harmon Gym
		987	Warren Hall
		988	Boalt Hall
		989	Lawrence Hall of Science
		990	Evans Hall
		991	T-4 (Energy & Resources Program)
		992	Tolman
		993	T-9 (University-Wide Energy Research Group)
		994	McLaughlin Hall
		995	HA Barker Hall
		996	Campbell Hall
		997	Minor Hall
		998	Silver Laboratory
		999	Mathematical Sciences Research Institute
Campus Buildings Assigned LBL Numbers			
1	Donner Laboratory		
3	Melvin Calvin Laboratory		
B3A	Trailer (on roof of 3)		
3B	Modular Bldg. (on roof of 3)		
8	Hearst Mining		
11	Hildebrand Hall		
18	Gilman Hall		
19	LeConte Hall		
19A	Birge Hall		
20	Life Sciences Building		
21	Giauque Hall		
22	Latimer Hall		
24	Etcheverry Hall		
38	Lewis Hall		
39	Cory Hall		
57	Cowell Hospital — Donner Pavilion		
905	Hesse Hall		
921	Stanley Hall		
			Richmond Field Station Building Numbers
		991-177	Radon Research House
		911-180	Indoor Air Quality Laboratory
		911-198	Earth Sciences Laboratory

APPENDIX C

1992 LBL BUILDINGS AND REHABILITATION STATUS

Building Number	Building Name Description	Area gsm	Area gsf	Persons	Rehab Status (a)	Age
HILL-SITE BUILDINGS						
88-Inch Cyclotron Research Area						
88	88-Inch Cyclotron, Nuclear Science	4,848	52,188	52	1	32
B-88A	Storage	32	342	0	1	13
B-88B	Compressor Shelter & Storage	50	534	0	1	
B-88C	Flammable Gas/Liquid Storage	7	80	0	3	
B-88D	Emergency Generator Building	25	265	0	1	13
	Total (b)	4,961	53,400	52		
Central Research and Administration Area						
B-33B	Blackberry Canyon Gatehouse	9	97	1	3	27
50	Physics, AFR and LBL Library	4,406	47,421	130	2	49
50A	Director's Offc, Plan'g & Dvlpmnt, Admin Div, Patents, Lab Counsel	6,305	67,863	167	2	30
50B	Physics, Telephone Services, ICSD, Computer Center	6,049	65,108	146	2	25
50C	Public Information Department (PID)	282	3,037	29	1	12
50D	Nuclear Science & MCSD	465	5,010	21	1	13
50E	Earth Sciences	943	10,150	50	1	8
50F	Information Resources, Computing Services	780	8,396	41	1	7
54	Cafeteria	1,083	11,662	12	2	42
54 Addn*	Cafeteria Addition	204	2,200		1	
B-54A	Wells Fargo Express Service	18	195	0	1	10
55	Research Medicine and Radiation Biophysics (RMRB)	1,735	18,678	37	1	41
55A	Nuclear Magnetic Resonance (NMR)	143	1,535	0	1	7
B-55A	Office Trailer	48	517	5	3	14
B-55B	Emergency Generator	19	209	0	1	5

(a) Rehabilitation Status

1= Adequate

2= Substandard, can be made adequate

3 = Substandard, cannot be made adequate

(b) Area totals are rounded to the nearest hundred (square feet).

Building Number	Building Name Description	Area gsm	Area gsf	Persons	Status (a)	Rehab	Age
Central Research and Administration Area (continued)							
65	Data Processing Services	307	3,306	14	3		40
B-65A	DPS Office Trailer	132	1,425	18	3		8
B-65B	DPS Office Trailer	95	1,020	8	3		9
B-67B	Office Trailer	110	1,189	4	3		14
B-67C	Laboratory Trailer	110	1,189	0	3		14
B-67E	Laboratory Trailer	27	290	0	3		20
70	Nuclear Science, Applied Science, and Earth Sciences	5,782	62,237	134	2		37
70A	Nuclear Sci, Chemical Sci, Earth Sci, Cell & Molecular Biology	6,345	68,302	76	2		31
B-70A	Storage	16	173	0	1		5
B-70B	Telephone Terminal	35	382	0	1		13
B-70C	Storage Container	14	156	0	1		
B-70D	Storage Container	15	160	0	1		
B-70E	Storage Container	40	432	0	1		
90	Energy & Envir, Employment, Engineering, Personnel, Protective Serv	8,131	87,519	336	2		32
B-90A	Plant Engineering	134	1,440	8	3		15
B-90B	Plant Engineering	134	1,440	3	3		15
B-90C	Plant Engineering	110	1,183	8	3		15
B-90D	UC Auditors	18	192	7	3		15
B-90E	UC Auditors	17	188	3	3		15
B-90F	Plant Engineering	229	2,461	10	3		13
B-90G	Plant Engineering Department	172	1,847	9	3		14
B-90H	Plant Engineering	171	1,846	11	3		14
B-90J	Plant Engineering	264	2,840	17	3		14
B-90K	Plant Engineering	268	2,882	15	3		14
B-90P	Office Trailer	198	2,130	0	3		13
B-90Q	Rest Room Trailer	39	425	0	3		14
B-90R	Telephone Vault	15	160	0	3		14
Total(b)		45,420	488,900	1,320			

(a) Rehabilitation Status

1= Adequate

2= Substandard, can be made adequate

3 = Substandard, cannot be made adequate

(b) Area totals are rounded to the nearest hundred (square feet).

Building Number	Building Name Description	Area	Area	Persons	Status (a)	Rehab	Age
		gsm	gsf				
Bevalac Accelerator Complex							
46	Accelerator Electronics Dept, ALS	4,827	51,952	169	2		43
46A	Computer Systems Engineering Dept	511	5,504	34	1		15
B-46B	Office Trailer	117	1,260	4	3		13
B-46C	Office Trailer	95	1,024	5	3		15
B-46D	Office Trailer	73	786	5	3		8
47	Advanced Accelerator Study	567	6,098	26	3		35
51	Bevalac/Bevatron	7,970	85,788	0	2		42
51A	Bevatron Experimental Area	2,407	25,910	66	2		34
51B	External Particle Beam (EPB) Hall	3,909	42,075	0	1		30
B-51C	Bevatron Plumbers Storage	37	400	0	1		
B-51D	Bevatron Electricians Shop	48	512	5	1		
B-51E	Bevatron Electrical Storage	46	496	0	1		
B-51F	HISS Building	143	1,543	0	3		13
B-51G	HISS Building	117	1,263	0	3		13
B-51H	HISS Building	145	1,556	5	3		13
B-51L	VAX Trailer, User Facility	80	864	0	1		7
B-51M	Bevatron Trailer	52	560	0	3		9
B-51N	Bevalac Patient Facility	59	640	0	1		
B-51P	Carpenter Shack	36	384	1	1		
56	Cryogenic Facility	89	961	0	3		16
56 Addn*	Biomedical Isotope Facility	97	1,039		1		
58	Heavy Ion Fusion (HIF)	927	9,979	21	3		42
58A	Accelerator Research & Development Addition	1,067	11,484	2	1		23
60	High Bay Laboratory	316	3,400	0	1		13
63	Accelerator & Fusion Research	244	2,624	11	3		15
64	Accelerator & Fusion Research	2,199	23,667	48	2		41
B-64A	Bevatron Riggers	48	515	6	3		24

(a) Rehabilitation Status

1= Adequate

2= Substandard, can be made adequate

3 = Substandard, cannot be made adequate

(b) Area totals are rounded to the nearest hundred (square feet).

Building Number	Building Name Description	Area gsm	Area gsf	Persons	Rehab Status (a)	Age
Bevalac Accelerator Complex (continued)						
71	Heavy Ion Linear Accelerator (HILAC)	5,038	54,226	46	1	36
71A	HILAC Rectifier	343	3,696	0	1	29
71B	HILAC Annex	644	6,936	14	1	36
B-71B	Office Trailer	47	511	1	3	11
B-71C	Office Trailer	47	511	3	3	24
B-71D	Office Trailer	47	511	5	3	22
B-71E	Office Trailer	47	511	3	3	19
B-71F	Office Trailer	47	511	0	3	18
B-71G	Office Trailer	47	511	0	3	18
B-71H	Electronics Engineering Department Office	132	1,416	6	3	18
B-71J	Office Trailer (SAN Site Office)	115	1,239	5	3	14
B-71K	Office Trailer	45	484	2	3	13
81	Liquid Gas Storage	104	1,124	1	1	24
82	Lower Pump House	50	537	0	1	11
Total(b)		32,981	355,000	494		
Light Source Research and Engineering Area						
2	Advanced Materials Laboratory (AML), Center for X-Ray Optics (CXRO)	7,975	85,838	119	1	4
4	Magnetic Fusion Energy (MFE)	941	10,133	29	3	48
B-4A	Safety Equipment Storage	12	133	0	3	18
5	Magnetic Fusion Energy (MFE)	664	7,149	12	3	50
B-5A	Mechanical Storage	15	160	0	3	
B-5B	Electrical Storage	15	160	0	3	
6	Advanced Light Source (ALS) -under construction-	7,525	81,000		1	1
7	Central Stores & Electronics Shops	2,022	21,760	42	3	49
B-7A	Radio Shop	11	120	0	3	18
B-7B	Inventory Management	44	473	3	3	15

(a) Rehabilitation Status

1= Adequate

2= Substandard, can be made adequate

3 = Substandard, cannot be made adequate

(b) Area totals are rounded to the nearest hundred (square feet).

Building Number	Building Name Description	Area gsm	Area gsf	Persons	Rehab Status (a)	Age
Light Source Research and Engineering Area (continued)						
B-7C	Material Management	44	473	3	3	15
B-7E	Office Trailer	97	1,040	0	3	15
10	ALS and Photography	1,490	16,038	24	3	48
B-10A	Utility Building	22	242	0	3	
14	Accelerator and Fusion Research (AFR) and Earth Sciences	390	4,200	7	3	48
16	Magnetic Fusion Energy Laboratory	1,061	11,419	13	3	49
B-16A	Power Supply House	31	339	0	3	32
17	Environmental Health and Safety (EH&S)	185	1,993	0	3	43
B-17A	ALS Test Facility	15	160	0	3	
25	Mechanical Technology	1,867	20,101	27	3	45
25A	Electronics Shops	681	7,335	16	2	29
26	Medical Services	619	6,663	30	2	28
26 Addn*	EH&S	288	3,100		1	
27	Cable Shop & High Voltage Test Facility	305	3,288	0	3	44
29	Electronics Instru Dept, Res Medicine & Radiation Biophysics (RMRB)	983	10,576	28	3	45
B-29A	Electronics Engineering, Computer Sciences	155	1,673	10	3	14
B-29B	Electronics Drafting	132	1,420	6	3	14
B-29C	Energy & Environment	119	1,282	8	3	14
B-29D	Rest Room Trailer	26	283	0	3	14
37	Utilities Service	537	5,784	0	1	5
40	Electronics Development Laboratory	92	994	0	3	45
41	Magnetic Measurements Laboratory	92	994	5	3	44
43	Compressor Building	94	1,007	0	1	4
44	Indoor Air Pollution Studies	74	800	1	3	36
B-44A	Plant Engineering Inspectors	17	181	3	3	13
B-44B	Energy & Environment	132	1,420	6	3	13

(a) Rehabilitation Status

1= Adequate

2= Substandard, can be made adequate

3 = Substandard, cannot be made adequate

(b) Area totals are rounded to the nearest hundred (square feet).

Building Number	Building Name Description	Area gsm	Area gsf	Persons	Status (a)	Rehab	Age
Light Source Research and Engineering Area (continued)							
45	Fire Apparatus	305	3,278	0	1		22
B-45A	Smoke House	12	128	0	3		
48	Fire Station	392	4,221	23	1		11
48 Addn*	Fire Station Addition	158	1,700		1		
B-48A	Fire Station Storage	30	320	0	3		14
52	Magnetic Fusion Energy Laboratory	608	6,542	3	3		49
B-52A	MG House	48	516	0	3		31
B-52B	Magnetic Fusion	110	1,180	5	3		13
53	Super HILAC Development, Magnetic Fusion Energy	632	6,806	8	3		43
B-53A	Gardener's Storage	18	192	0	3		27
B-53B	Office Trailer	47	511	2	3		20
80	Electronics Engineering, Accelerator & Fusion Research	2,436	26,216	33	2		38
80A	Electronics Installation & Fabrication	88	947	5	1		15
	Total(b)	33,659	362,300	471			
Shop and Support Facilities Area							
31	Chicken Creek Maintenance Building	563	6,060	15	1		6
B-31A	Earth Sciences	58	624	1	3		
B-33C	Grizzly Peak Gatehouse	7	80	1	1		27
36	Grizzly Substation Switchgear Building						
42	Salvage	113	1,215	2	3		50
B-42A	Emergency Generator House	14	156	0	3		
61	Standby Propane Plant	30	323	0	1		23
68	Upper Pump House	46	500	0	1		13
69	Material Management, Purchasing, Mailroom	1,602	17,239	53	1		25

(a) Rehabilitation Status

1= Adequate

2= Substandard, can be made adequate

3 = Substandard, cannot be made adequate

(b) Area totals are rounded to the nearest hundred (square feet).

Building Number	Building Name Description	Area gsm	Area gsf	Persons	Rehab Status (a)	Age
Shop and Support Facilities Area (continued)						
75	Radioisotope Service, National Tritium Facility (NTF)					
75A	Compactor, Processing, and Storage Facility	794	8,545	13	1	31
B-75B	Office Trailer, EH&S	378	4,064	0	3	13
B-75C	Calibration Range	435	4,681	21	3	13
B-75D	Waste Storage	42	450	0	3	
B-75E	Office Trailer (Tritium Group)	96	1,035	4	3	
76	Craft & Maintenance Shops	38	410	4	3	28
B-76A	Paint Storage	2,876	30,960	137	1	
B-76B	Plumbing	15	160	0	1	7
B-76C	Maintenance Supplies	6	64	0	1	14
B-76D	Electrical	15	160	0	3	
B-76E	Electrical	15	160	4	3	
B-76F	Small Engine Shop	15	160	0	3	
B-76G	Battery Storage	5	56	0	3	
B-76H	Emergency Utility Storage					
77	Mechanical Fabrication Shops	6,389	68,768	107	2	29
77A	Ultra High Vacuum (UHV) Assembly Facility	1,008	10,854	2	1	4
B-77C	Welding Storage	2	23	0	1	
B-77D	Drum Liquid Storage	10	108	0	1	
B-77G	Mechanical Technology Department	66	710	2	3	16
B-77H	Auxiliary Plating Building	54	576	0	3	9
78	Craft Stores	499	5,373	2	1	26
79	Metal Stores	397	4,278	3	1	27
Total(b)		15,589	167,800	371		

(a) Rehabilitation Status

1= Adequate

2= Substandard, can be made adequate

3 = Substandard, cannot be made adequate

(b) Area totals are rounded to the nearest hundred (square feet).

Building Number	Building Name Description	Area gsm	Area gsf	Persons	Rehab Status (a)	Age
Materials and Chemistry Research Area						
62	Materials & Chemical Sciences	5,147	55,398	96	2	27
B-62A	Office Trailer	120	1,292	10	3	14
B-62B	ICS Modular Building					
66	Surface Science & Catalysis Laboratory (SSCL)	4,099	44,123	101	1	5
72	National Center for Electron Microscopy (NCEM)	493	5,308	11	1	31
72A	High Voltage Electron Microscope (HVEM)	235	2,532	0	1	12
72B	Atomic Resolution Microscope (ARM)	407	4,383	0	1	8
72C	ARM Support Laboratory	520	5,600	11	1	8
B-72D	Office Trailer	57	617	7	3	
73	Atmospheric Aerosol Research	400	4,304	8	2	31
B-73A	Utility Building	37	403	0	1	31
Total(b)		11,520	124,000	244		
Life Sciences Research Area						
B-33A	Strawberry Canyon Gatehouse	5	52	1	1	27
74	RMRB, Cell & Molecular Biology Lab.	4,186	45,054	77	2	30
74B	RMRB, Cell & Molecular Biology Lab. Annex	319	3,436	7	1	23
B-74C	Emergency Generator Building	17	180	0	1	
83	Cell & Molecular Biology	645	6,940	18	1	13
B-83A	Laboratory Trailer	46	493	0	3	27
85*	Hazardous Waste Handling Facility	1,208	13,000		1	
Total(b)		6,429	69,200	103		

(a) Rehabilitation Status

1= Adequate

2= Substandard, can be made adequate

3 = Substandard, cannot be made adequate

(b) Area totals are rounded to the nearest hundred (square feet).

* Proposed new construction to begin in FY'92.

Building Number	Building Name Description	Area gsm	Area gsf	Persons	Rehab Status (a)	Age
Environmental Monitoring Stations						
B-13A	Environmental Monitoring Station, West of Building 88	7	76	0	1	
B-13B	Environmental Monitoring Station, West of Building 90	7	76	0	1	
B-13C	Environmental Monitoring Station, South of Strawberry Clubhouse	7	76	0	1	
B-13D	Environmental Monitoring Station, North of Building 71	7	76	0	1	
B-13E	Environmental Monitoring Station, Southwest of Building 88	6	68	0	1	
B-13F	Environmental Monitoring Station, North of Strawberry Clubhouse	3	36	0	1	27
B-13G	Waste Monitoring Station, West of 70	13	140	0	1	
B-13H	Radiation Monitoring Station, Southeast of Building 37					
Total(b)		46	500	0		

Hillsite Grand Total 150,606 1,621,100 3,055

Off-Site Leased Buildings

901	Receiving/Warehouse, 1450 64th St., Emeryville	6,474	69,680	9		
901A	Used Furniture/Excess Material, 1450 64th St., Emeryville	2,490	26,802	0		
934	DYMO Bldg: Print Plant, Cell & Molecular Biology, 91 Bolivar Dr., Berkeley	2,854	30,720	46		
936	Berkeley Center: Accounting & Financial Mgmt, 2070 Allston Way, Berkeley	1,218	13,107	60		
940	Cholesterol Research Center, 3030 Telegraph Avenue, Berkeley	39	415	3		

Total(b) 13,072 140,700 118

(a) Rehabilitation Status

1= Adequate

2= Substandard, can be made adequate

3 = Substandard, cannot be made adequate

(b) Area totals are rounded to the nearest hundred (square feet).

Building Number	Building Name Description	Area nsm	Area nsf(c)	Persons	Status (a)	Rehab	Age
UCB Campus Buildings with assigned LBL Numbers							
1	Donner Laboratory	2,353	25,323	106			
3	Melvin Calvin Laboratory (includes Bldg 3B and B3A on roof)	2,187	23,543	109			
8	Hearst Mining	1,234	13,284	81			
11	Hildebrand Hall	2,123	22,848	120			
18	Gilman Hall	811	8,732	44			
19	LeConte Hall	454	4,888	24			
19A	Birge Hall	1,240	13,345	64			
20	Life Sciences Building (LSB) - under construction-						
20A	Life Sciences Building Addition	61	660	2			
21	Low Temperature Laboratory--Giauque Hall	879	9,458	28			
22	Latimer Hall	1,255	13,508	77			
24	Etcheverry Hall	515	5,547	20			
38	Lewis Hall	286	3,079	41			
39	Cory Hall	47	511	4			
57	Cowell Hospital--Donner Pavilion	243	2,614	10			
905	Hesse Hall	531	5,711	10			
921	Stanley Hall	168	1,804	11			
925	Giannini Hall						
926	Morgan Hall						
928	Haviland Hll						
952	Moses Hall						
953	Earth Sciences						
970	SCM Building - 6701 San Pablo Avenue, Berkeley						
980	Animal Behavior Building						
981	Experimental Thermal House - Walnut Creek						
982	Medical Research Laboratory - Oakland						
983	Wurster Hall	464	4,998	4			
984	Davis Hall	77	833	4			
985	Garage						
986	Harmon Gym						

(c) Survey used net square feet

Building Number	Building Name Description	Area nsm	Area nsf(c)	Persons Status (a)	Rehab Status (a)	Age
UCB Campus Buildings with assigned LBL Numbers (continued)						
987	Warren Hall	39	423			
988	Boalt Hall					
989	Lawrence Hall of Science					
990	Evans Hall	18	195	3		
991	T-4 (Energy & Resources Program)					
992	Tolman					
993	T-9 (University-Wide Energy Research Group)					
994	McLaughlin Hall					
995	Barker Hall	127	1,364	4		
996	Campbell Hall					
997	Minor Hall					
998	Silver Laboratory (Space Sciences Laboratory)					
999	Mathematical Sciences Research Institute					
	Total(b)	15,115	162,700	766		
Richmond Field Station						
911-177	Radon Research House	194	2,092	0		
911-180	Indoor Air Quality Laboratory	213	2,290	0		
911-198	Earth Sciences Laboratory	159	1,711	0		
	Total(b)	567	6,100	0		

(b) Area totals are rounded to the nearest hundred (square feet).

(c) Survey used net square feet

TOTAL ALL SITES	gsm	gsf	Persons
HILL-SITE BUILDINGS AND TRAILERS	150,606	1,621,100	3,055
OFF-SITE LEASED BUILDINGS	13,072	140,700	118
CAMPUS BUILDINGS ASSIGNED LBL NUMBERS(1)	23,254	250,300	766
RICHMOND FIELD STATION(2)	873	9,400	0
TOTAL ALL SITES	187,804	2,021,500	3,939

(1) Survey was taken in net square feet at approximately 0.65 ratio of net (162,700) to gross square feet = 250,300.

(2) Survey was taken in net square feet at approximately 0.65 ratio of net (6,100) to gross square feet = 9,400.

APPENDIX D

LBL LAND LEASES

LBL LAND LEASES

Parcel Number	Area (Acre)	Effective Date	Expiration Date
1	8.7	1949	1999
2	2.2	1948	1998
3	1.8	1948	1998
4	1.6	1953	2003
5	4.3	1950	2000
5A	1.8	1986	2036
6	2.3	1951	2001
7	4.4	1955	2005
9	5.4	1959	2009
10	3.9	1959	2009
11	2.3	1959	2009
12	4.5	1959	2009
13	1.5	1960	2010
13A	1.5	1985	2000
14	1.0	1960	2010
15	3.3	1961	2011
16	1.9	1960	2010
17	5.9	1962	2012
18	1.9	1962	2012
19	3.4	1962	2012
19A	1.8	1985	2035
20	0.6	1963	2013
21	1.7	1965	2015
22	0.2	1967	2017
23	0.3	1969	2019
24	1.0	1980	2030
25	3.7	1978	2028
26	4.1	1988	2037
27	2.0	1988	2037
998 (Occupancy Agreement)	3.6	1948	1993
999 (Contractor Controlled)	48.9	1948	1990
Total Acres	131.5		

APPENDIX E

Acronyms And Other Initialisms

ABAG	Association of Bay Area Governments
AC	Alameda County
AECR	Advanced Electron Cyclotron Resonance
AGMEF	Ana G. Méndez Educational Foundation
ALS	Advanced Light Source
AML	Advanced Materials Laboratory
BARRNet	Bay Area Regional Research Network (Consortium)
BART	Bay Area Rapid Transit system
BES	basic energy sciences
BPA	Bonneville Power Administration
Cal-EPA	California Environmental Protection Agency
CAM	Center for Advanced Materials
CCF	Central Computing Facility
CDF	Collider Detector at Fermilab
CERN	European Council for Nuclear Research (Geneva)
CEQA	California Environmental Quality Act
CERCLA	Comprehensive Environmental Response Compensation and Liability Act
CRE	Conservation and Renewable Energy
CRT	cathode ray tube
DECnet	Digital Equipment Corporation's networking system
DOD	Department of Defense
DOE	U.S. Department of Energy
DOE/SF	DOE Field Office at San Francisco
EBMUD	East Bay Municipal Utilities District
ECR	electron cyclotron resonance
EH&S	Environmental Health and Safety Department
EM	Environmental Management
EMCS	energy monitoring and control system
ERWM	Environmental Restoration and Waste Management
ES&H	Environment, Safety and Health (DOE)

ESNET
 FTE
 FTS
 GPE
 GPP
 gsf
 HILAC
 HVAC
 ICS
 JSU
 LBL
 LBLnet
 LDC
 LLNL
 LRDP
 MEL-FS
 MFE
 MFTF
 MILnet
 NCEM
 NEPA
 NIH
 NMFEC
 NMR
 OECD
 OER
 OHER
 ORNL
 OSHA
 OSP
 PEP
 PET
 PG&E
 PNL
 RFS

Energy sciences network
 (computer support for DOE energy research)
 full-time equivalent position
 Federal Telecommunications System
 General Purpose Equipment
 General Plant Projects
 gross square feet
 Heavy Ion Linear Accelerator
 heating, ventilating, and air conditioning
 Integrated Communications System
 Jackson State University
 Lawrence Berkeley Laboratory
 Laboratory-wide computer network
 less-developed country
 Lawrence Livermore National Laboratory
 Long Range Development Plan
 Multiprogram Energy Laboratory Facilities Support
 magnetic fusion energy
 Mirror Fusion Test Facility (Livermore)
 Military (DOD-sponsored) computer network
 National Center for Electron Microscopy
 National Environmental Protection Act
 National Institutes of Health
 National Magnetic Fusion Energy Computer Center
 nuclear magnetic resonance
 Organization for Economic Cooperation and Development (Europe)
 Office of Energy Research
 Office of Health and Environmental Research (DOE)
 Oak Ridge National Laboratory
 Occupational Safety and Health Administration
 Operational Safety Procedure
 Positron Electron Project
 positron emission tomography
 Pacific Gas & Electric Company
 Pacific Northwest Laboratories
 Richmond Field Station (UC)

RHIC	Relativistic Heavy Ion Collider
SDP	Long Range Site Development Plan
SFI	Strategic Facilities Initiative
SLAC	Stanford Linear Accelerator Center
SLC	Stanford Linear Collider
SSC	Superconducting Super Collider
SSCL	Surface Science and Catalysis Laboratory
TEC	total estimated cost
TFTR	Tokamak Fusion Test Reactor (Princeton)
TPC	Time Projection Chamber
TSI	Technical Site Information
UC	University of California
UCB	University of California, Berkeley
VHF	very high frequency
WAPA	Western Area Power Administration
WFO	Work for Others
WW II	World War II

ACKNOWLEDGMENTS

The Technical Site Information document was prepared with information provided by the Plant Engineering Department, Associate Laboratory Director for Operations, in coordination with the Office for Planning and Development.

Associate Laboratory Director for Planning and Development, Martha A. Krebs

Associate Laboratory Director for Operations, Klaus H. Berkner

Head, Plant Engineering Department, J. Robert Camper

Correspondence regarding this document should be directed to Michael A. Chartock, Office for Planning and Development, Building 50A, Room 4112, Lawrence Berkeley Laboratory, 1 Cyclotron Road, Berkeley, CA 94720. Telephone: 510-486-6669.

Site Planning Information Sources

Bruce R. Bagnoli, Construction and Maintenance

Laura J. Chen, Planning and Special Projects

James F. Koonce, Jr., Staff, Office of Assessment and Assurance

Richard McClure, Planning and Special Projects

Phillip D. Phythian, Budget and Resource Planning

Dale Sartor, Planning and Special Projects

Bert H. Schleifer, Design Management

Richard D. Scudero, Project Management

David A. Tudor, Planning and Special Projects

Robert G. Vitiello, Staff, Office for Planning and Development

Document Preparation and Production Technical Information Department

Marilee B. Bailey, Illustration Group
Alice S. Ramirez, Text Processing/Composition Group
Loretta R. Lizama, Technical Editing Group

Consultants

Donlyn Lyndon, Director's Architectural Consultant
Eldon Beck, Laboratory Landscape Consultant

END

**DATE
FILMED
5128193**