DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615)576-8401.

Available to the public from the National Technical Information Service, U. S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

DOE/PC/79873--T1

DE92 013482

**DEVELOPMENT OF THE LICADO
COAL CLEANING PROCESS**

**FINAL REPORT
FOR
OCTOBER 1, 1987 TO APRIL 2, 1990**

**CUSTOMER ORDER NO.
DE-AC22-87PC79873**

**WESTINGHOUSE ELECTRIC CORPORATION
ADVANCED ENERGY SYSTEMS
P.O. BOX 10864
PITTSBURGH, PA 15236-0864**

JULY 31, 1990

This report was prepared as an account of work sponsored by the United States Government. Neither the United States Government nor the United States Department of Energy, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Patents cleared by Office of Patent Counsel,
Chicago Operations Office on June 7, 1990.

ABSTRACT

Development of the liquid carbon dioxide process for the cleaning of coal was performed in batch, variable volume (semi-continuous), and continuous tests. Continuous operation at feed rates up to 4.5 kg/hr (10-lb/hr) was achieved with the Continuous System. Coals tested included Upper Freeport, Pittsburgh, Illinois No. 6, and Middle Kittanning seams. Results showed that the ash and pyrite rejections agreed closely with the washability data for each coal at the particle size tested (-200 mesh). A 0.91 metric ton (1-ton) per hour Proof-of-Concept Plant was conceptually designed. A 181 metric ton (200 ton) per hour and a 45 metric ton (50 ton) per hour plant were sized sufficiently to estimate costs for economic analyses. The processing costs for the 181 metric ton (200 ton) per hour and 45 metric ton (50 ton) per hour were estimated to be \$18.96 per metric ton (\$17.20 per ton) and \$11.47 per metric ton (\$10.40 per ton), respectively for these size plants. The costs for the 45 metric ton per hour plant are lower because it is assumed to be a fines recovery plant which does not require a grinding circuit or complex waste handling system.

TABLE OF CONTENTS

<u>Section</u>	<u>Page No.</u>
1.0 Introduction.....	1-1
2.0 Objectives.....	2-1
3.0 Experimental Program for Batch Tests.....	3-1
3.1 Fixed Volume Batch Tests.....	3-8
3.1.1 Equipment.....	3-8
3.1.2 Procedure.....	3-11
3.1.3 Results and Discussion.....	3-12
3.2 Variable Volume Batch Tests.....	3-23
3.2.1 Equipment.....	3-24
3.2.2 Procedure.....	3-24
3.2.3 Results and Discussion.....	3-27
3.2.4 Summary of Variable Volume Tests.....	3-47
3.2.5 Comparison with Washability Data.....	3-48
3.3 Agglomeration/Screening Tests.....	3-52
3.3.1 Equipment.....	3-52
3.3.2 Procedure.....	3-56
3.3.3 Results and Discussion.....	3-56
4.0 Continuous Research Unit.....	4-1
4.1 Equipment.....	4-1
4.1.1 Clean Coal/Refuse Separator.....	4-1
4.1.2 Premixing Tank.....	4-5
4.1.3 Slurry Preparation Unit.....	4-5
4.1.4 Clean Coal/Liquid CO ₂ Separator.....	4-5
4.1.5 Refuse/Water Separator.....	4-7

TABLE OF CONTENTS (Cont'd.)

<u>Section</u>	<u>Page No.</u>
4.2	Procedure..... 4-7
4.2.1	Continuous Operation Control Schemes..... 4-10
4.3	Results and Discussion..... 4-15
5.0	Continuous Unit..... 5-1
5.1	Equipment..... 5-1
6.0	Simulation Model..... 6-1
6.1	Description of Model..... 6-1
6.2	Results..... 6-6
6.2.1	Plant Studies..... 6-6
6.2.2	Separator/Mixer Studies..... 6-6
6.2.3	Continuous Research Unit Study..... 6-11
7.0	Conceptual Plant Design..... 7-1
7.1	Proof-of-Concept Plant..... 7-1
7.1.1	Requirements of the POC Plant..... 7-2
7.1.2	Process Consideration..... 7-5
7.1.3	Plant Subsystems..... 7-9
7.1.4	Instrumentation and Control System..... 7-14
7.1.5	Description of POC Plant..... 7-19
7.1.6	Plant Operation..... 7-36
7.1.7	Required Development..... 7-38
7.1.8	Conceptual Design Review of POC Plant..... 7-42
7.2	Commercial Plant (200 Ton/Hour)..... 7-42
7.2.1	Requirements..... 7-43
7.2.2	Discussion of System (Figure 7.2.2-1)..... 7-44

TABLE OF CONTENTS (Cont'd.)

<u>Section</u>	<u>Page No.</u>
7.2.3 Description of Plant.....	7-44
7.2.4 Budgetary Cost Estimate.....	7-49
7.3 Waste Stream Recovery Plant (50-Ton/Hour).....	7-50
7.3.1 Requirements.....	7-50
7.3.2 Discussion of System (Figure 7.3.2-1).....	7-52
7.3.3 Description of Plant.....	7-52
7.3.4 Budgetary Cost Estimate.....	7-55
8.0 Economic Studies.....	8-1
8.1 Economic Model.....	8-1
8.2 Economic Study Results.....	8-1
8.2.1 ROM Plant.....	8-3
8.2.2 Waste Recovery Plant.....	8-7
9.0 Summary, Conclusions, and Recommendations.....	9-1
9.1 Summary.....	9-1
9.2 Conclusions.....	9-4
9.3 Recommendations.....	9-6

Appendices

A	Washability Data
B	Results from Fixed Volume Batch Test
C	Results from Variable Volume Batch Test
D	Results from Continuous Research Unit
E	Listing for LIPSA
F	Listing for LIPSB
G	Conceptual Plant Details

LIST OF FIGURES

<u>Figure No.</u>		<u>Page No.</u>
3.0-1	Calibration for Particle Size for Coal #1 - Upper Freeport.....	3-3
3.0-2	Particle Size Distributions for Coal #1 - Upper Freeport.....	3-4
3.0-3	Kcal/Kg Versus Ash Content for Three Coals - Upper Freeport, Pittsburgh #8, and Illinois #6.....	3-7
3.1-1	Batch Research Unit (BRU).....	3-9
3.1-2	Photograph of Batch Research Unit.....	3-10
3.1.3-1	Effect of Impeller Speed in BRU Tests.....	3-13
3.1.3-2	Effect of Settling Time in BRU Tests.....	3-14
3.1.3-3	Effect of Contact Time in BRU Tests.....	3-16
3.1.3-4	Effect of Slurry Concentration in BRU Tests.....	3-17
3.1.3-5	Variation in Operation Parameters in BRU Tests.....	3-21
3.2.1-1	Variable Volume Batch Unit.....	3-25
3.2.1-2	Photograph of the Research Development Unit (RDU).....	3-26
3.2.3-1	Effect of Impeller Speed in RDU Tests.....	3-29
3.2.3-2	Effect of CO ₂ Flowrate in RDU Tests.....	3-31
3.2.3-3	Heating Value Recovery as a Function of Particle Size.....	3-33
3.2.3-4	Separation Characteristics as a Function of Particle Size - Illinois #6 Coal.....	3-35
3.2.3-5	Separation Characteristics as a Function of Particle Size - Middle Kittanning Coal.....	3-36
3.2.3-6	Multistage Separation Column.....	3-42
3.2.3-7	Single-Stage Versus Two-Stage Performance - Upper Freeport Coal (Pyrite Content).....	3-47

LIST OF FIGURES (Cont'd.)

<u>Figure No.</u>		<u>Page No.</u>
3.2.3-8	Single-Stage Versus Two-Stage Performance - Upper Freeport Coal (Ash Content).....	3-44
3.2.3-9	Moisture Content as Function of Speed.....	3-46
3.2.5-1	Comparison with Washability Curve for Coal #1 - Upper Freeport-A (Ash in Clean Coal).....	3-49
3.2.5-2	Comparison with Washability Curve for Coal #1 - Upper Freeport-A (Pyritic Sulfur in Clean Coal).....	3-50
3.2.5-3	Comparison with Washability Curve for Coal #3 - Upper Freeport-C (Ash in Clean Coal).....	3-51
3.2.5-4	Comparison with Washability Curve for Coal #6 - Middle Kittanning (Ash in Clean Coal).....	3-53
3.2.5-5	Comparison with Washability Curve for Coal #7 - Illinois No. 6-A (Ash in Clean Coal).....	3-54
3.3.1-1	Modified Batch Research Unit (Screen Agglomeration).....	3-55
4.1-1	Continuous Research Unit (CRU) Flow Diagram.....	4-2
4.1-2	Photograph of the CRU.....	4-3
4.1-3	Separation Column.....	4-4
4.1-4	Premixing Tank.....	4-6
4.1-5	Clean Coal Filter.....	4-8
4.2-1	Interface Position Control.....	4-12
4.2-2	Refuse Discharge Control.....	4-13
4.2-3	Liquid CO ₂ Flowrate Control.....	4-14
4.2-4	Clean Coal Discharge Control.....	4-16
4.3-1	Results of Test 31.....	4-19
4.3-2	Comparison with Washability Curve for 1.76×10^{-4} kg/s (1.4 lb/hr) with Upper Freeport Coal.....	4-26
4.3-3	Comparison with Washability Curve for 3.78×10^{-4} kg/s (3 lb/hr) Tests with Upper Freeport Coal...	4-28

LIST OF FIGURES (Cont'd.)

<u>Figure No.</u>		<u>Page No.</u>
4.3-4	Pyritic Sulfur in Product as Function of Heating Value Recovery for Upper Freeport Coal.....	4-29
4.3-5	Effect of Coal Feed Rate on Process Performance.....	4-30
4.3-6	Comparison with Washability Curve for Pittsburgh No. 8 Coal.....	4-31
4.3-7	Comparison with Washability Curve for Illinois No. 6 Coal.....	4-32
5.1-1	0.006 kg/s (50 lb/hr) Separation Column.....	5-2
6.1-1	Integrated Statepoint Diagram.....	6-2
6.2-1	Separator Radii, 1-Ton/Hr Plant 10% Slurry Concentration.....	6-7
6.2-2	Separator Radii, 1-Ton/Hr Plant 20% Slurry Concentration.....	6-8
6.2-3	Separator Radii, 1-Ton/Hr Plant 30% Slurry Concentration.....	6-9
6.2-4	Separator Radii, 1-Ton/Hr Plant 500 Seconds Residence Time.....	6-10
6.2-5	Separator Radii Vs. Residence Time 100 Lb/Hr and 30% Slurry Concentration.....	6-12
6.2-6	Separator Radii Vs. CO ₂ /Slurry Ratio.....	6-14
7.1.1-1	LICADO Plant Simulation, Upper Freeport Coal....	7-4
7.1.3-1	LICADO, 1-Ton/Hour Proof-of-Concept Piping & Instrumentation Diagram.....	7-11
7.1.5-1	LICADO, 1-Ton/Hour Proof-of-Concept Plant Preliminary Plant Arrangement, Waltz Mill Site..	7-23
7.1.5-2	LICADO, 1-Ton/Hour Proof-of-Concept Plant Preliminary Plant Arrangement, Waltz Mill Site Section A-A.....	7-25
7.1.5-3	Grinding Systems Elevation.....	7-27

LIST OF FIGURES (Cont'd.)

<u>Figure No.</u>		<u>Page No.</u>
7.1.5-4	Hydraulic Line Mixer.....	7-29
7.1.5-5	Mixer Orifice Details.....	7-31
7.1.5-6	Integral Multistage Separator.....	7-33
7.1.5-7	Continuous Auger Filter.....	7-35
7.1.7.2-1	Continuous Filter - Pressurized.....	7-40
7.1.7.2-2	Sections A-A and B-B.....	7-41
7.2.2-1	LICADO, 200 Ton/Hour Commercial Plant Flow Schematic.....	7-45
7.3.2-1	50 Ton/Hour CO ₂ Agglomeration Process Flow Sheet.....	7-53
8.2-1	LICADO Product Sales Price Effect of After Tax ROI.....	8-4
8.2-2	LICADO Product Sales Price Effect of Capital Cost on 200 Ton/Hour Plant....	8-5
8.2-3	LICADO Product Sales Price Effect of Plant Capacity.....	8-6
8.2-4	LICADO Product Sales Price Effect of Capital Cost on 50-Ton/Hour Waste Recovery Plant.....	8-8
8.2-5	LICADO Product Sales Price Effect of CO ₂ Cost on 50-Ton/Hour Waste Recovery Plant.....	8-9
8.2-6	LICADO Product Sales Price Effect of Plant Capacity on 50-Ton/Hour Waste Recovery Plant.....	8-11

LIST OF TABLES

<u>Table No.</u>		<u>Page No.</u>
3.0-1	Ash and Sulfur Contents of Test Coals.....	3-1
3.0-2	Contact Angle of Water on Coal Pellets.....	3-5
3.1.3-1	Statistical Experimental Arrangement.....	3-18
3.1.3-2	Values of Three Levels of Particle Size in BRU Experiments.....	3-19
3.1.3-3	Heating Value Recovery Analysis of Variance for Middle Kittanning Coal.....	3-20
3.1.3-4	Ash Reduction Analysis of Variance for Middle Kittanning Coal.....	3-20
3.1.3-5	Extent of Influence of Operating Variables on Heating Value Recovery and Ash Reduction Confidence Levels (%).....	3-23
3.2.3-1	Range of Process Operating Conditions in RDU Experiments.....	3-27
3.2.3-2	RDU Experiments with Upper Freeport Coal.....	3-28
3.2.3-3	Effect of Premixing Time in RDU Operation.....	3-32
3.2.3-4	Effect of Particle Size and Dispersant in RDU Operation.....	3-37
3.2.3-5	Effect of 1-Octanol on Test Coals.....	3-39
3.2.3-6	Two-Step Experiments with Illinois No. 6 Coal.....	3-40
3.2.3-7	Two-Step Experiments with Middle Kittanning Coal.....	3-41
3.2.4-1	Pyrite and Ash Content at 85% Heating Value Recovery.....	3-47
3.3.3-1	Screen Agglomeration Experiments with Various Coals.....	3-57
3.3.3-2	Effect of Agitation Speed.....	3-58

LIST OF TABLES (Cont'd.)

<u>Table No.</u>		<u>Page No.</u>
3.3.3-3	Effect of Agitation Speed on Samples of Narrow Particle Size Distribution (74 x 44 Microns).....	3-59
3.3.3-4	Screen-type Agglomeration Experiments with 1-Octanol.....	3-60
4.3-1	Range of Operating Conditions in CRU.....	4-17
4.3-2	CRU Tests with Upper Freeport Coal (coal #3)....	4-20
4.3-3	Contact Angle Results for Upper Freeport Coal Samples.....	4-21
4.3-4	Effect of Liquid CO ₂ Injection Rate into the Separation Column and the Slurry Injection Point Position.....	4-22
4.3-5	Effect of Liquid CO ₂ Injection into the Premixing Tank.....	4-23
4.3-6	Effect of the Interface Position.....	4-24
4.3-7	Effect of the Premixing Tank Mixing Speed.....	4-24
4.3-8	Effect of Liquid CO ₂ Distribution.....	4-25
7.1.4-1	Control System.....	7-16
7.1.4-2	Measurements Requirements List.....	7-18
7.1.4-3	Control Valve List.....	7-20
8.1-1	Parameters Used in Economic Model.....	8-2

1.0 INTRODUCTION

This is the Final Report summarizing technical progress from inception on October 1, 1987 through completion on April 2, 1990 on Development of the LICADO Coal Cleaning Process, Contract DE-AC22-87PC79873, sponsored by the U.S. Department of Energy, Pittsburgh Energy Technology Center (PETC). The Westinghouse Advanced Energy Systems Division is the prime contractor for this project, with the University of Pittsburgh as the major subcontractor.

The LICADO (Liquid Carbon DiOxide) process is a novel, advanced coal cleaning method conceived and patented by the University of Pittsburgh. Liquid carbon dioxide at high pressure (about 850 psia) and room temperature is used to separate clean coal from an aqueous suspension, leaving the ash and pyrite constituents in the water phase. Since liquid CO₂ is immiscible in water, wets clean coal particles, and does not wet ash or pyrite particles, these properties result in the separation of clean coal from the water, ash, and pyrite at the liquid CO₂-water interface. The effectiveness of this process has been demonstrated in bench-scale batch tests at the University of Pittsburgh prior to the initiation of this project. These initial tests resulted in removal of up to 90% of the ash and pyritic sulfur.

The program is organized into six tasks, which are listed below with the responsible organization and personnel for each task:

DOE Technical Project Officer: Dr. R. W. Lai

Westinghouse Project Manager: Dr. M. H. Cooper

University of Pittsburgh Project Manager: Dr. S. H. Chiang

University of Pittsburgh Principal Investigator: Dr. R. Venkatadri

- Task 1. Batch Research Unit - University of Pittsburgh
Dr. B. Morsi, Task Leader
Ms. M. T. Thach
Mr. D. X. He'
Mr. Y. Ou
- Task 2. Continuous Research Unit - University of Pittsburgh
Dr. G. E. Klinzing, Task Leader
Mr. G. Araujo
Mr. Y. Feng
- Task 3. Continuous Unit - University of Pittsburgh
Dr. G. E. Klinzing, Task Leader
Mr. G. Araujo
Mr. Y. Feng
- Task 4. Modeling and Evaluation - Westinghouse
Dr. M. H. Cooper, Task Leader
- Task 5. Proof-of-Concept Plant - Westinghouse
Dr. M. H. Cooper, Task Leader
Mr. H. O. Muenchow
Mr. D. W. Stimme1
- Task 6. Economic Analyses - Westinghouse
Mr. J. D. Mottley, Task Leader
Ms. E. H. Valkovic
Mr. C. W. Mycoff

This report provides a detailed description of the technical results of each of these tasks.

2.0 OBJECTIVES

The objectives of this project are: 1) the development of an effective and efficient advanced technique for cleaning fine coal based on the LICADO process, and 2) the testing of the major unit operations of this process on an integrated, continuous real time basis.

These goals will be achieved by establishment of technical feasibility through generation of a firm engineering data base from additional batch testing, small scale continuous unit testing (1-lb/hr to 10-lb/hr), economic analysis, and design of a one ton per hour Proof-of-Concept plant.

3.0 EXPERIMENTAL PROGRAM FOR BATCH TESTS

The experimental program for the batch tests consisted of three major components described in the following sections.

- Fixed volume batch tests in the 0.05 m (2-inch) Batch Research Unit (BRU).
- Variable volume batch tests using the 0.10 m (4-inch) Research Development Unit (RDU).
- Fixed volume agglomeration/screening tests in the 0.05 m (2-inch) Batch Research Unit (BRU).

COAL SAMPLES

Eight different coals were tested in the batch tests. Table 3.0-1 shows the ash and sulfur contents of each of these coals. The washability analysis for -74 microns (-200 mesh) samples of coals No. 1, 3, 6 and 7 are provided in Appendix A.

TABLE 3.0-1
ASH AND SULFUR CONTENTS OF TEST COALS

No.	Coal	Ash(%)	Total Sulfur(%)	Pyritic Sulfur(%)
1.	Upper Freeport (A)	24.4	1.4	1.1
2.	Upper Freeport (B)	22.7	1.4	1.1
3.	Upper Freeport (C)	13.5	2.2	1.7
4.	Pittsburgh-Bruceton	4.9	1.6	0.7
5.	Pittsburgh	31.5	1.9	1.3
6.	Middle Kittanning	7.9	5.0	3.8
7.	Illinois No. 6 (A)	26.0	3.9	2.7
8.	Illinois No. 6 (B)	12.6	3.1	2.0

In addition to the above, a Pittsburgh #8 coal was used in tests conducted in the Continuous Research Unit. The feed ash content of this coal was 12.2%, with total sulfur and pyritic sulfur contents of 4.3% and 3.15%, respectively.

SAMPLE PREPARATION AND PARTICLE SIZE ANALYSIS

All samples of coal were first ground in a jaw crusher to the size range 0.004m x 0 (3/16" x 0). Further size reduction was achieved by wet grinding with a stirred ball mill supplied by Fort Pitt Machine Company. A standard procedure was adopted for grinding. The feed to the stirred ball mill was varied from 0.227 kg (0.5 lb) to 1.81 kg (4 lbs), and the slurry concentration ranged from 5 to 40% solid. The grinding was achieved by using 0.004 m (3/16") stainless steel balls as the grinding medium. The speed of rotation of the impeller was fixed at 52.3 rad/s (500 rpm). The samples were ground for various periods ranging from 60 s to 2400 s. Samples were withdrawn at regular intervals during the grinding, and the particle size distribution was determined with a Leitz Orthoplan microscope coupled to an image analyzer. These results were used to construct a calibration curve for mean particle size of the coal sample as a function of grinding time. Based on this information, samples were ground to requisite times to obtain a desired particle size for subsequent beneficiation.

Figure 3.0-1 shows a typical grinding curve (Upper Freeport coal). A sharp decrease in the average particle size can be observed during the initial 300 s (5 min) of grinding as the weight mean diameter is reduced from 150 microns to approximately 50 microns. Subsequent grinding to 2400 s (40 min) resulted in a steady but slow decrease in particle size. The distribution in particle size for Upper Freeport coal is displayed for various grinding periods in Figure 3.0-2. The distribution of fine particles below 40 microns increases correspondingly with longer grinding periods concomitant with decreases in the percentage of large particles (above 150 microns).

SURFACE PROPERTY MEASUREMENTS

Surface wettability is an important property for the LICADO process and can be characterized by measurement of contact angle on coal surfaces. Contact angle measurements were carried out at room temperature and

Figure 3.0-1. Calibration for Particle Size for Coal #1

UPPER FREEPORT COAL

GRINDING TIME: 0 SEC.

GRINDING TIME: 180 SEC.

GRINDING TIME: 300 SEC.

GRINDING TIME: 600 SEC.

Figure 3.0-2. Particle Size Distributions for Coal #1

ambient pressure using a conventional goniometer by the standard sessile-drop technique. Coal samples were pelletized in a Buehler Pelletizer at 27.6 MPa (4000 psi), and the advancing contact angle of water on these pellets was measured. The contact angle of water was subsequently measured in a specially designed high pressure chamber in the presence of liquid CO₂. The results for three coals utilized in this project are compared in Table 3.0-2.

It can be observed from Table 3.0-2 that Upper Freeport coal and Middle Kittanning coal exhibit a hydrophobic character, as evidenced by the large contact angles at atmospheric pressure. Liquid CO₂ imparts further hydrophobicity to these coals since the contact angles exceed 140 degrees. However, the Illinois No. 6 coal exhibits zero contact angle at room temperature and pressure, which is indicative of the extreme hydrophilic nature of the sample. Even in the presence of liquid CO₂, a contact angle of only 75 degrees was registered, showing that the sample retained a substantial portion of its hydrophilic character. Experimental results from the Batch Research Unit (BRU), Research Development Unit (RDU) as well as the Continuous Research Unit (CRU) tests confirmed these observations.

TABLE 3.0-2
CONTACT ANGLE OF WATER ON COAL PELLETS

Coal	Equilibrium Contact Angle, Degrees	
	Atm pressure	In Liquid CO ₂
Upper Freeport (coal #1)	85	145
Middle Kittanning (coal #6)	108	150
Illinois No. 6 (coal #7)	0	75

PERFORMANCE CRITERIA

The performance of the LICADO process was characterized in terms of heating value recovery, ash reduction and pyritic sulfur reduction. Heating value (Btu) recovery is expressed in terms of the clean coal yield.

$$\text{Heating value recovery (\%)} = \text{Yield (\%)} \times \frac{(100 - \text{Clean Coal Ash})}{(100 - \text{Feed Coal Ash})}$$

The validity of this relationship was independently verified by experimentally measuring heating value recovery as a function of ash content in a companion DOE project (3-1). Figure 3.0-3 shows that the heating value is directly proportional to the ash-free coal (or clean coal yield). Based on this, the above relationship can be used to compute the heating value recovery for test results.

The ash and pyritic sulfur reduction are defined as:

$$\text{Ash Reduction (\%)} = 100 - \frac{\text{Product coal ash content}}{\text{Feed coal ash content}} \times 100$$

$$\text{Pyritic Sulfur Reduction (\%)} =$$

$$100 - \frac{\text{Product coal pyritic sulfur content}}{\text{feed coal pyritic sulfur content}} \times 100$$

Figure 3.0-3. Kcal/Kg Versus Ash Content for Three Coals

In addition, the process performance may also be measured by the ash and pyritic sulfur rejection, which are defined as follows:

$$\text{Ash Rejection (\%)} = 100 - \left(Y \times \frac{\text{ash in product}}{\text{ash in feed}} \right)$$

$$\begin{aligned} \text{Pyritic Sulfur Rejection (\%)} = \\ 100 - \left(Y \times \frac{\text{pyritic sulfur in product}}{\text{pyritic sulfur in feed}} \right) \end{aligned}$$

where Y is the experimentally measured yield in wt%.

The average diameters of coal feed samples were measured with a Leitz Orthoplan microscope coupled with an image analyzer. Two types of average diameters were measured: the volume surface mean diameter and the weight mean diameter. The equations defining these two quantities are provided in the last part of Appendix A. The volume surface mean diameter corresponds to the diameter of a sphere having the same ratio of volume/surface area as the particle. The weight mean diameter is the average of the weight distribution of the particles.

3.1 Fixed Volume Batch Tests

Extensive testing of the LICADO process was conducted in the fixed volume batch mode using the 0.05 m (2-inch) Batch Research Unit (BRU). This section describes the equipment and experimental procedure as well as the major conclusions from the fixed volume batch tests. In the fixed volume batch tests, the slurry volume is maintained constant, and liquid CO₂ does not leave the system during the duration of the test.

3.1.1 Equipment

The Batch Research Unit is shown in Figures 3.1-1 and 3.1-2. The apparatus, which has a capacity of about 0.003 m³ (3 liters), consists of two high-pressure cells of 0.05 m (2-inch) I.D. connected by a 0.05 m (2-inch) ball valve. The size of the opening of the ball valve was chosen to be the same as the internal diameter of the cells to eliminate any

Figure 3.1-1. Batch Research Unit (BRU)

rejection were achieved at
product leaves after 10/2

physical obstructions to the movement of coal slurry between the two cells. The valve allows a quick and complete isolation of the two high pressure vessels. Thus, clean coal and refuse can be removed completely without any remixing when the system is depressurized. Other features of the BRU include:

- Transparent windows on upper and lower cells for visual observation.
- Two variable speed mixers up to 314 rad/s (3000 rpm) to provide adequate mixing in both the liquid CO₂ and water phases.
- A micron-size fritted disc distributor located at the bottom of the lower cell to provide a uniform dispersion of the liquid CO₂ droplets within the water phase.

3.1.2 Procedure

The coal water slurry of 0.0009 m³ (0.9 liters) was prepared at various slurry concentrations of coal. It was mixed for a sufficient time to achieve complete wetting of the coal particles with water. The slurry was then manually fed to the BRU, and the system was pressurized to the desired operating pressure of 5.5-6.2 MPa (800-900 psig). Liquid CO₂ was introduced from the top cell until it saturated the slurry and the excess CO₂ forms a thin layer above the coal-water-liquid CO₂ interface. Premixing of the slurry was then carried out for 60 s at an agitation speed of 104 rad/s (1000 rpm) in both the upper and lower test cells. Subsequently, liquid CO₂ was injected into the slurry from the bottom of the unit while constant mixing was maintained in both phases. After a predetermined contact time (0-600 s), the mixing in both phases was stopped. The clean coal was allowed to separate from the refuse for a certain length of time, denoted as settling time (usually 300 s). The central ball valve was closed, and the system was depressurized to ambient pressure. The clean coal was removed from the top cell while the refuse was removed from the bottom cell.

3.1.3 Results and Discussion

Four different test coals were utilized in fixed volume batch tests conducted in the BRU. These included coals which have been designated in Table 3.0-1 as #1, #4, #6, and #7, respectively.

3.1.3.1 Initial Study

Initial experiments in the BRU were conducted using Upper Freeport coal (coal #1) with a nominal particle size of -74 microns. The effect of mixing in both liquid CO_2 and aqueous phases was examined by varying the impeller speed in both phases from 0-125 rad/s (0-1200 rpm). Figure 3.1.3-1 illustrates the results for the variation in the experimental yield and product quality with agitation speed. It can be observed that there is a significant reduction in the ash content when the impeller speed is maintained in the range of 62-105 rad/s (600-1000 rpm), while a reasonable yield was obtained. Higher speeds resulted in an increase in the ash content of the product. The impellers in the water phase assist in breaking and better dispersion of the liquid CO_2 droplets, while mixing in the upper phase improves the breaking of the agglomerates and releasing the entrained ash material from the product coal as well as reagglomeration of the particles. These results showed that mixing was necessary to the LICADO process operation. Yet, there is a range of mixing speed to achieve the most effective performance. Higher speeds result in undesirable transport of ash into the liquid CO_2 phase and thus, into the product. Subsequent tests were performed at an impeller speed of 105 rad/s (1000 rpm) in both phases.

The variation in the settling time after contact with liquid CO_2 was also studied with Upper Freeport coal. Figure 3.1.3-2 shows that the zero settling time (immediate closing of the ball valve at the end of mixing) produced a high ash content. Subsequent tests were carried out for a settling time of 300 s. The experimental results indicate that a settling period of 300 s was sufficient for a complete separation of bulk phases

Figure 3.1.3-1. Effect of Impeller Speed in BRU Tests

Figure 3.1.3-2. Effect of Settling Time in BRU Tests

(i.e., the liquid CO_2 and water phases) to provide a good product yield and quality. At a longer separation time, disengagement of finely dispersed liquid CO_2 droplets from the water phase in the bottom cell transported refuse material into the upper phase, resulting in an increase of the yield as well as the ash content of the product. When the settling time was increased further (say, beyond 1000 s), the yield tended to decrease, because of the settling of heavy agglomerates from the upper (liquid CO_2) phase to the lower (water) phase. Based on these observations, all subsequent tests were conducted with a settling time of 300 s.

A set of experiments was also carried out with Upper Freeport coal, wherein the injection/mixing (contact) time was varied. Figure 3.1.3-3 shows that when the injection time was maintained at about 900 s (15 minutes), higher yields were achieved at fairly good separation characteristics. Longer injection times at a constant liquid CO_2 flowrate increased the yield, owing to increased contact of droplets of liquid CO_2 with coal. However, a decrease in the product quality was observed, suggesting that entrapment of ash material in the clean coal agglomerates was taking place.

Tests carried out at slurry concentrations varying from 3 to 17 wt% indicated that there was essentially no effect on Upper Freeport coal. This is shown in Figure 3.1.3-4.

The important conclusions from the parametric studies in the BRU were that the mixing speed of 104 rad/s (1000 rpm) in both phases yielded improved results. A settling time of 300 s was desirable. Injection times of about 900 s provided favorable results. Slurry concentrations up to 17% has a relatively minor effect on the process performance. Strictly speaking, these conclusions are only valid for Upper Freeport coal (coal #1). However, they can serve as a basis for experimental design for each of the test coals in the fixed volume batch tests. They can also be used as design guidelines for subsequent tests in both the Research Development Unit and the Continuous Research Unit.

Figure 3.1.3-3. Effect of Contact Time in BRU Tests

Figure 3.1.3-4. Effect of Slurry Concentration in BRU Tests

3.1.3.2 Statistically Designed Experiments

For further investigation of the operation parameters, a 3x3x3 factorial design (3 factors, 3 levels) was employed to perform experiments for each of the three coals. This resulted in 27 experiments for each coal in addition to repeat runs. The influence of particle size, liquid CO₂ flowrate, and slurry concentration on process performance was evaluated by statistical analysis of the raw data. The statistical experimental design is shown in Table 3.1.3-1.

The particle size range varied for each coal and Table 3.1.3-2 shows the range studied for each coal in the BRU experiments. The volume surface mean diameters have been reported here.

Table 3.1.3-1
Statistical Experimental Arrangement

Factor	Level		
	1	2	3
Mean Particle Size *	Small	Medium	Large
Slurry Concentration (Wt%)	2.5	5	10
Liquid CO ₂ Flowrate m ³ /s x 10 ⁻⁶	0.41	0.83	1.66

* Particle sizes for each coal are given in Table 3.1.3-2.

The particle size distribution data of each coal after 180 s of grinding in the stirred ball mill are shown in Appendix B in Tables B-10 through B-12. The detailed experimental data for all the coals used in fixed volume batch tests is documented in Appendix B in Tables B-7, B-8, and B-9.

Table 3.1.3-2
Values of Three Levels of Particle Size in BRU Experiments

Coal	Particle Size (microns)		
	Small	Medium	Large
Pittsburgh-Bruceton	33	40	50
Middle Kittanning	28	38	97
Illinois No. 6	41	50	70

A summary of the analysis of variance results for Middle Kittanning coal is given in Tables 3.1.3-3 and 3.1.3-4. A complete description of the method of statistical analysis is provided in Appendix B. Details of statistical analysis for each coal are given in Tables B-1 through B-6 in Appendix B.

Here, SS refers to the sum of squares, s^2 to the mean square for each factor considered, and the term $s^2/(s_R)^2$ can be related to the confidence limits which determine the statistical significance of the parameter. This term is also defined as the F-ratio. The significance of each factor is determined by comparing the F-ratio with F-distribution values provided in statistical tables (see Appendix B). When the confidence interval for a particular F-ratio exceeds 99% (or when $s^2/(s_R)^2$ is greater than 5.85), the parameter is considered to exert a significant effect on the results.

Table 3.1.3-3 shows the analysis of variance of the heating value recovery results. The analysis of variance indicates that the heating value recovery results are influenced significantly only by the particle size at a 99% confidence level. The data show a clear trend suggesting that smaller particle size samples generate higher yields.

Table 3.1.3-3
Heating Value Recovery Analysis of Variance
Middle Kittanning Coal

Factor	Level Average			SS	s ²	s ² /s _R ²
	1	2	3			
Particle Size	52	63	75	2274	1137	6.73
Slurry Concentration	57	68	64	574	287	1.70
Liquid CO ₂ Flowrate	63	67	60	186	93	0.55
Residual				3380	169	

Table 3.1.3-4 summarizes the analysis of variance performed for the ash reduction results. The analysis indicates that none of the studied variables exert a significant effect on the ash reduction results. To further illustrate these effects, the ash reduction and heating value recovery are plotted as a function of particle size in Figure 3.1.3-5.

Table 3.1.3-4
Ash Reduction Analysis of Variance
Middle Kittanning Coal

Factor	Level Average			SS	s ²	s ² /s _R ²
	1	2	3			
Particle Size	45	46	45	6.3	3.2	0.30
Slurry Concentration	47	45	45	31.2	15.6	1.48
Liquid CO ₂ Flowrate	46	46	45	8.2	4.1	0.39
Residual				211.2	10.6

Figure 3.1.3-5. Variation in Operation Parameters in BRU Tests

The data were obtained at a liquid CO₂ flowrate of 0.41×10^{-6} m³/s (25 ml/min). The results are presented at three different slurry concentrations. It can be observed that the heating value recovery decreases with an increase in particle size at the lower slurry concentrations of 2.5% and 5%. The ash reduction remains virtually unaffected by changes in operating conditions. The heating value recovery appears to increase at the higher slurry concentration.

The detailed statistical analysis results for Pittsburgh-Bruceton coal (coal #4) and Illinois No. 6 coal (coal #7) are provided in Appendix B. For the Illinois No. 6 coal, the results are similar to those for Middle Kittanning coal. Smaller particle sizes generate improved heating value recoveries in the range studied. The effect on ash reduction by all process parameters is statistically insignificant. In the case of Pittsburgh-Bruceton coal, the variation in particle size (33-50 microns) was too narrow to observe any significant effect of particle size. However, the slurry concentration influenced both heating value recovery and ash reduction. Improved results were achieved at a slurry concentration of 5%.

To summarize the statistical analysis for the data from the fixed volume batch tests, Table 3.1.3-5 shows the confidence limits for each of the coals for heating value recovery and ash reduction. The main conclusions from Table 3.1.3-5 are that particle size significantly influences the heating value recovery, especially for coals #6 and #7. The slurry concentration effect is pronounced for coal #4 for both the heating value recovery and ash reduction. The CO₂ flowrate does not influence either heating value recovery or the ash reductions for the three coals studied.

It should be emphasized that the test matrices for the fixed volume batch tests were designed to determine the significant operating parameters and not to provide optimum separations and/or yield. While the yields and

separations from the fixed volume batch tests were far from the optimum values, these tests met their goal of providing guidelines for the operation of the Research Development Unit and the Continuous Research Unit.

Table 3.1.3-5
Extent of Influence of Operating Variables
on Heating Value Recovery and Ash Reduction
Confidence Levels (%)

Coal	Heating Value Recovery			Ash Reduction		
	Particle Size	Slurry Conc.	CO ₂ Flowrate	Particle Size	Slurry Conc.	CO ₂ Flowrate
Pittsburgh-Bruceton (#4)	80-90	>99	<75	<75	90-95	<75
Middle Kittanning (#6)	>99	75-80	<75	<75	<75	<75
Illinois No. 6 (#7)	>99	<75	<75	80-90	<75	<75

3.2 Variable Volume Batch Tests

A comprehensive series of tests were carried out in the variable volume batch mode using the Research Development Unit (RDU). In addition to the experiments specified in the project proposal, tests were also conducted to study the effects of chemical reagents, two-step cleaning and two-stage cleaning operations on process performance. In two-step cleaning, the product from a single-stage system is recycled through the column. Two-stage cleaning is accomplished in a single pass through the column which has two mixing/agglomeration stages. Excellent results for ash and pyrite

rejection were achieved at high heating value recoveries. The clean coal product leaves with liquid CO_2 , while the refuse remains in the separation column. The slurry volume in the column varies with time.

3.2.1 Equipment

A schematic diagram of the Research Development Unit is shown in Figure 3.2.1-1. The photograph of the experimental unit is shown in Figure 3.2.1-2. The main component in the RDU is the 4-inch separation column with a height of 0.76 m (2.5 ft). The volume of the column is about 0.0065 m^3 (6.5 liters). The pressure, temperature, and flowrate are monitored from an instrument panel adjacent to the apparatus. The separation column has an impeller shaft passing through it and the speed of agitation can be as high as 314 rad/s (3000 rpm). A spiral plate disperser at the bottom of the cell provides for better dispersion of the liquid CO_2 droplets. The unit is also equipped with three high pressure vessels which serve as the sample collectors for the clean coal-liquid CO_2 slurry exiting from the top of the separation column. Refuse is collected in a sampling port located at the bottom of the separation column.

3.2.2 Procedure

A slurry of about 0.0032 m^3 (3.2 liters) of coal and water was prepared and mixed well for complete wetting of the coal particles. The slurry concentration was maintained at about 5 wt% solids. The slurry was then manually introduced into the separation column of the RDU. Liquid CO_2 was injected into the column until it completely saturated the slurry. The mixture was preconditioned for a desired time period described as "premixing time", with a layer of liquid CO_2 present above the interface at an agitation speed in the range of 157-210 rad/s (1500-2000 rpm). Liquid CO_2 was injected from the bottom of the column at the desired flowrate through the disperser. The clean coal

1	column	5	product collector
2	flowmeter	6	settling tank
3	CO2 pump	7	CO2 tank
4	refuse collector	8	motor

Figure 3.2.1-1. Variable Volume Batch Unit

Figure 3.2.1-2. Photograph of the Research Development Unit (RDU)

was carried up to the top to an overflow cone and collected continuously in the product sampler, where the liquid CO_2 left the system through a back pressure valve. Refuse remained in the separation column and was removed to the refuse sampler at the termination of each test.

3.2.3 Results and Discussion

Eight test coals listed in Table 3.0-1 were examined in RDU tests. Experiments using the RDU were performed over a wide range of operating conditions. These are listed in Table 3.2.3-1.

Table 3.2.3-1
Range of Process Operating Conditions in RDU Experiments

Temperature, K	293-300 (70-80 °F)
Slurry Concentration, Wt% solid	5
Particle Size, microns (Surface-volume mean dia)	10-100
Pressure, MPa	5.5-6.5 (800-950 psig)
Contact Time for Liquid CO_2 , s	300-1200
Liquid CO_2 Flowrate, $\text{m}^3/\text{s} \times 10^{-6}$	6.6-16.6 (400-1000 ml/min)
Agitation Speed, rad/s	63-177 (600-1700 rpm)
Premixing Time, s	30-1800
Premixing Speed, rad/s	157-230 (1500-2200 rpm)

The results of experiments conducted in variable volume batch mode in the RDU represent a remarkable improvement over those obtained in the BRU (presented earlier in section 3.1.3). Experiments with Upper Freeport

coal (coal #1 in Table 3.0-1) were carried out at a slurry concentration of 5% while maintaining the nominal particle size constant at -74 microns for a contact time of 900 s. Table 3.2.3-2 shows that excellent ash and pyrite rejection could be achieved with high heating value recoveries. When the mixing speed was 63 rad/s (600 rpm), at a liquid CO₂ flow rate of 6.6 x 10⁻⁶ m³/s (400 ml/min), it was possible to recover nearly 70% of the original heating value. The ash and pyritic sulfur rejections were greater than 90%. When the mixing speed was altered to 104 rad/s (1000 rpm), the heating value recovery improved further to 82% with only a marginal decrease in ash/pyrite rejection. The longer column in the RDU appears to be more favorable for ash/pyrite rejection than the BRU. The agglomerates with entrapped ash material can be broken up to release the mineral matter before being reformed and removed as product from the column.

Table 3.2.3-2
RDU Experiments with Upper Freeport Coal

Mixing Speed (rad/s)	Liquid CO ₂ Flowrate m ³ x 10 ⁻⁶	Heating Value Recovery (%)	Product Ash (%)	Ash Rejection (%)	Pyrite Rejection (%)
63	6.6	69.1	2.1	95.3	95.1
138	6.6	86.6	4.5	87.5	85.4
177	6.6	88.5	9.5	71.3	78.8
104	9.1	83.6	4.0	89.3	90.6

Figure 3.2.3-1 shows the variation in the rejection of pyritic sulfur as a function of impeller speed for Upper Freeport coal in the RDU. The results suggest that lower impeller speeds provide more favorable conditions for rejection of pyritic sulfur. While higher stirring speeds contribute to better dispersion of the CO₂ droplets and improved contact with the

Figure 3.2.3-1. Effect of Impeller Speed in RDU Tests

coal particles (thereby increasing the heating value recovery), the entrapment of pyritic sulfur particles in the product is also increased. It should, however, be noted that even when the impeller speed was increased to 177 rad/s (1700 rpm), the pyritic sulfur rejection was close to 80% while the heating value recovery was nearly 90%.

Figure 3.2.3-2 depicts the variation of the rejection of pyritic sulfur as a function of flowrate for the same Upper Freeport coal in the RDU. The trend is similar to that shown in Figure 3.2.3-1 for variation in impeller speed. The flowrate of liquid CO_2 should be sufficiently high to wet the coal particles and act as a bridging liquid between clean coal particles. Excessively high flow rates cause entrapment and subsequently entrainment of the finely ground ash material (including pyrite) in the clean coal phase, with a concomitant increase in the ash and pyritic sulfur content of the product.

The effect of premixing on the cleaning characteristics of Illinois No. 6 coal, as well as Upper Freeport coal, was also investigated in the variable volume mode in the RDU. A relatively low ash Illinois No. 6 coal (coal #8 in Table 3.0-1) was utilized in these experiments while similar studies were conducted with the sample of Upper Freeport coal (coal #2 in Table 3.0-1). The flowrate of liquid CO_2 was maintained at $6.6 \times 10^{-6} \text{ m}^3/\text{s}$ (400 ml/min). The particle size of the two coals was nominally -74 microns. The premixing speed was maintained at 215 rad/s (2050 rpm) and a slurry concentration of 6.3% was employed in these experiments.

The results of varying the premixing time are summarized in Table 3.2.3-3. For the Upper Freeport coal, a final product ash content of 3.3% was obtained at a heating value recovery of 78% without any premixing in the system. When the premixing operation was performed for 600 s, the heating value recovery increased to 84% with a concomitant increase in ash content. However, a perceptible improvement in ash reduction was accom-

Figure 3.2.3-2. Effect of CO₂ Flowrate in RDU Tests

plished by premixing for only 30 s while using a low liquid CO₂/slurry ratio (0.16). The liquid CO₂/coal ratio that was usually maintained in the period promotes the formation of agglomerates of liquid CO₂/coal particles, thereby increasing the recovery. However, entrapment of ash in the agglomerates could decrease selectivity for clean coal. In the case of the Illinois No. 6 coal, Table 3.2.3-3 shows that the heating value recovery again increased for the longer premixing time with little change in ash rejection. These results demonstrate that premixing time is an important parameter in the process, and it is necessary to determine the optimum premixing period for each coal to achieve desired results. Generally, the hydrophobic coals (such as Upper Freeport coal) require less premixing time than the hydrophilic coals (such as Illinois No. 6 coal).

Table 3.2.3-3
Effect of Premixing Time in RDU Operation
Ash in Upper Freeport Coal: 22.7%
Ash in Illinois No. 6 Coal: 12.6%

Coal	Premixing Time (s)	Heating Value Recovery (%)	Product Ash (%)	Ash Rejection (%)	Pyrite Rejection (%)
Upper Freeport	0	78.4	3.3	90.8	82.8
Upper Freeport	30	78.3	2.6	92.7	85.0
Upper Freeport	600	84.5	5.7	82.5	74.4
Illinois No. 6	180	62.8	7.7	53.7	59.9
Illinois No. 6	600	70.5	7.4	50.2	56.8

Figure 3.2.3-3 shows the change in heating value recovery for the low ash Illinois No. 6 coal and the Middle Kittanning coal (coal #8 and #6 in Table 3.0-1, respectively) as the average particle size is increased from 20 to 75 microns. In these experiments, the coal slurry in water (concen-

Figure 3.2.3-3. Heating Value Recovery as a Function of Particle Size

tration: 6.5%) was premixed for 900 s with liquid CO_2 prior to performing the experiment. During the experiment, the flowrate of liquid CO_2 was fixed at $6.6 \times 10^{-6} \text{ m}^3/\text{s}$ (400 ml/min); and the agitation speed was 104 rad/s (1000 rpm).

Figure 3.2.3-3 shows that grinding the two coals to particle sizes below 40 microns is beneficial to achieving high heating value recoveries. A sharp decrease in the recovery is registered for an average particle size larger than 70 microns. The separation characteristics are plotted in Figure 3.2.3-4 for the same experimental conditions for the Illinois No. 6 coal. It can be observed from Figure 3.2.3-4 that the rejection of ash and pyritic sulfur is increased only at the larger particle sizes (exceeding 70 microns). This phenomena is unique for the coal- CO_2 system. Hence, there appears to be a trade-off between the heating value recovery and the ash and pyrite rejection. Fine grinding the particles down to smaller particle sizes appears to enhance the heating value recovery while a substantial portion of the finely ground mineral matter is entrapped in the clean coal-liquid CO_2 agglomerate structure. This conclusion is similar to that obtained in fixed volume batch tests, which have been discussed earlier in section 3.1. A two-stage separator, discussed later in this section, was designed to eliminate the trapping of ash material by breaking the agglomerates from the first stage and reforming them in the second stage.

Similar separation characteristics were observed for the Middle Kittanning coal as a function of particle size, as shown in Figure 3.2.3-5. An improvement in ash and pyrite rejection is achieved as the particle size is increased from 20 to 50 microns. It can also be observed from Figure 3.2.3-3 that the heating value recovery decreased by about 20 percentage points as the particle size increased, in this range of particle size.

3.2.3.1 Effect of Chemical Reagents

The effect of conditioning the various coals with selective chemical

Figure 3.2.3-4. Separation Characteristics as a Function of Particle Size

Figure 3.2.3-5. Separation Characteristics as a Function of Particle Size

reagents was also investigated in the variable volume batch studies. These studies were in addition to those specified in the project proposal and were primarily carried out to seek improved process performance.

The effect of fine grinding in the presence of different concentrations (in solution) of the dispersant SHMP (Sodium Hexametaphosphate) is shown in Table 3.2.3-4. For the sake of comparison, the results obtained by grinding without the reagent are included in Table 3.2.3-4. In the case of Upper Freeport coal (coal #1), the dispersant did not adversely affect the heating value recovery; but for the Illinois No. 6 coal (coal #8), a substantial drop in the recovery was observed for the sample having an average particle size of 36 microns. This suggests that the reagent was not effective. Furthermore, a substantial decrease in the ash rejection potential was registered for both the coals when the particles were ground

Table 3.2.3-4
Effect of Particle Size and Dispersant in RDU Operation
Dispersant: Sodium Hexametaphosphate

Coal	Dispersant Conc (ppm)	Particle Size (microns)	Heating Value Recovery (%)	Ash Rejection (%)
Upper Freeport	0	30	79.5	86.9
	30	30	81.0	86.3
	80	30	82.4	88.6
	30	13	77.0	38.6
Illinois No. 6	0	36	77.6	61.9
	30	36	54.5	78.0
	80	36	41.5	77.7
	30	18	82.6	26.9

finer than 20 microns. Another interesting observation was that the heating value recovery was significantly enhanced for the finer size Illinois No. 6 coal. This latter finding indicates that the fine ash material was being entrapped in the clean coal agglomerates. It was visually observed that the agglomerates appear to be of a larger size when the feed material contained very fine particles. It can be concluded that grinding the particles to very fine sizes is detrimental to the removal of ash from the product in this type of operation. It can also be inferred that the dispersant SHMP did not yield desirable results in terms of improvements in heating value recovery or ash rejection.

Experiments were also conducted with 1-Octanol. The results are shown in Table 3.2.3-5. In the case of the Upper Freeport coal (coal #2) and the high ash Pittsburgh coal (coal #5), it was interesting to note that the heating value recovery increased steadily with reagent dosage, indicating that 1-Octanol facilitated the attachment of the droplets of liquid CO_2 to the clean coal particles. Hence, 1-Octanol appears to behave as a coagglomerating agent in these instances. The effect on ash rejection is not significant for these coals.

The effect of 1-Octanol on Illinois No. 6 coal (coal #7) is also illustrated in Table 3.2.3-5. The experimental conditions were the same as those employed for the other coals. Tests were conducted with samples wet ground for 600 s to a weight mean diameter of 35 microns. The addition of 1-Octanol effected a marked improvement in the ash rejection.

3.2.3.2 Two-Step Cleaning Experiments

Variable volume batch two-step experiments were conducted in the RDU with the high ash Illinois No. 6 coal (coal #7). The clean coal product from the first step was utilized as the feed during the second cleaning step. The results are presented in terms of overall heating value recovery and ash and pyrite content of the product.

The results presented in Table 3.2.3-6 indicate that it was possible to reduce the ash content in the product to 6.9% for the extremely hydrophilic sample of Illinois No. 6 coal after two cleaning steps, while obtaining a heating value recovery exceeding 71% for the second step. The results demonstrate the effectiveness of the process for ash removal. The pyrite removal is, however, not as favorable and is likely due to the problem of liberating finely dispersed pyrite particles from the coal matrix. It should also be pointed out that the overall heating value recovery could be further improved if the refuse from the first step were subjected to a second reprocessing step.

Table 3.2.3-5
Effect of 1-Octanol on Test Coals

Coal	Reagent Conc. (ppm)	Heating Value Recovery (%)	Product Ash (%)	Ash Rejection (%)
Pittsburgh	0	67.4	7.6	87.9
	80	73.6	6.5	88.5
	170	74.4	7.3	87.5
Upper Freeport	0	79.6	4.5	88.4
	30	80.7	4.5	88.2
	115	84.8	4.1	88.9
Illinois No. 6	0	77.6	9.1	61.9
	80	73.8	7.1	84.1
	155	80.3	8.2	79.8

Table 3.2.3-6
Two-Step Experiments with Illinois No. 6 Coal
Feed Ash: 26.0%

Flowrate (m ³ /s) x 10-6	Step No.	Heating Value Recovery (%)	Product Ash (%)	Product Pyrite (%)
6.6	1	79.8	16.0	2.0
5.3	2	71.1	6.9	1.5
5.3	1	71.3	18.6	2.2
6.6*	2	46.2	6.3	1.4

* Sample deslimed with hot water.

To facilitate comparison, the results of experiments conducted with Middle Kittanning coal are presented in Table 3.2.3-7. It can be observed that a substantially improved removal of ash was achieved while maintaining a high heating value recovery. The pyrite removal after the two-step treatment is excellent. While the two-step treatment was necessary to achieve desirable results for Middle Kittanning coal, it was possible to obtain good separation of mineral matter and coal with the single step treatment for the Upper Freeport coal, as discussed earlier (Table 3.2.3-2). These results are in agreement with the conclusions drawn earlier from the contact angle measurements on these coals (Table 3.0-2). Since the Illinois No. 6 coal exhibited a hydrophilic nature even in the presence of liquid CO₂, it was difficult to achieve high ash/pyrite rejection with good heating value recovery even after the two-step treatment. The liberation characteristics of Illinois No. 6 coal could also be affected by the distribution of mineral matter in the coal.

Table 3.2.3-7
Two-Step Experiments with Middle Kittanning Coal
Feed Ash: 7.8%

Flowrate (m ³ /s) x 10 ⁻⁶	Step No.	Heating Value Recovery (%)	Product Ash (%)	Product Pyrite (%)
6.6	1	88.8	3.9	1.4
6.6	2	77.1	2.0	0.7
6.6*	1	84.5	4.6	1.7
6.6*	2	72.3	1.7	0.7

* Sample deslimed with hot water.

3.2.3.3 Two-Stage Cleaning Experiments

In order to seek a further improvement in process performance, a two-stage treatment unit for the RDU was designed and fabricated. This unit is shown in Figure 3.2.3-6. The same feed sample was utilized in this configuration. Two cylindrical draft tubes of 3 inch I.D. were installed inside the 4-inch separation column of the RDU with a conical section on top. A vortex inducing plate was attached to the top of each draft tube, and the impeller shaft passed through the two draft tubes. In this arrangement, the clean coal and refuse material were expected to be ejected tangentially from the vortex plates after being subjected to vigorous agitation of at least 104 rad/s (1000 rpm). The denser refuse material was expected to sink to the bottom after collision with the wall of the separation column. The lighter clean coal agglomerates were collected at the top after overflowing from the conical section.

Initial results for the two-stage cleaning device are presented in Figures 3.2.3-7 and Figure 3.2.3-8 for Upper Freeport coal (coal #3).

Figure 3.2.3-6. Multistage Separation Column

Figure 3.2.3-7. Single-Stage Versus Two-Stage Performance

Figure 3.2.3-8. Single-Stage Versus Two-Stage Performance

Figure 3.2.3-7 compares the pyrite content in the product for Upper Freeport coal cleaned in two stages with that cleaned in a single stage. The product pyrite content is significantly lower at equivalent heating value recoveries for the two-stage processing tests. For instance, at 85% heating value recovery, the clean coal pyrite content is 0.47 wt% for the single stage and 0.38 wt% for two stages. This corresponds to an increase in pyrite reduction from 58% to 66%, or an improvement of 13.7% for two-stage cleaning. From Figure 3.2.3-8, it is clear that the ash content in the product also decreases after two-stage treatment. This suggests that agglomerates from the first stage were being broken up to release the entrapped mineral matter before the agglomerates were reformed in the second stage. The data for two-stage treatment with Pittsburgh and Illinois coals also appears very promising. There is a substantial improvement in ash and pyrite reductions after incorporating the second stage.

Additional stages can be easily and economically incorporated into the separation column for the Research Development Unit as well as the Continuous Research Unit, since the stage hardware is simple and does not affect the separator column size. Further testing with multistage devices is proposed to be conducted in the next phase of the project. Finer grinding of particles is also proposed, since the heating value recovery has been shown to increase at smaller particle sizes (as discussed earlier). The negative impact of smaller particles causing an increase in the product ash content, due to entrapment in the larger agglomerates, will be eliminated through the multistage separator. In the case of hydrophilic coals such as Illinois No. 6 coal, preconditioning with 1-Octanol may be coupled with multistage treatment to achieve the desired results.

3.2.3.4 Moisture Content of Clean Coal Product

An outstanding feature of the LICADO process is the very dry clean coal product. Figure 3.2.3-9 shows the variation of moisture content of the clean coal product as a function of impeller speed for coal #1. It can be

Figure 3.2.3-9. Moisture Content as Function of Speed

observed that moisture contents as low as 5% were obtained at lower impeller speeds. The moisture content is less than 15% at a mixing speed of 104 rad/s (1000 rpm). Higher agitation speeds resulted in increased moisture in the product. Table 3.2.3-2 shows that at an impeller speed of 104 rad/s, the heating value recovery was 82%, while the ash and pyrite rejections were in the 90% range. It appears that 104 rad/s is the desired mixing speed for coal #1. There is also direct correspondence between the product moisture content and ash content. The ash content in the product increases with the moisture content (at the higher impeller speeds). Similar results were obtained in the operation of the Continuous Research Unit, as discussed in section 4.3.

3.2.4 Summary of Variable Volume Tests

In all cases, the results from experiments conducted in the variable volume batch mode in the RDU have demonstrated that high ash and pyrite rejections were possible at excellent heating value recoveries. A summary of the results at 85% heating value recovery for four coals is given below in Table 3.2.4-1.

Table 3.2.4-1
Pyrite and Ash Content at 85% Heating Value Recovery

Coal	Pyrite in Feed Wt%	Pyrite in Product Wt%	Pyrite Rejection %	Ash in Product %
Upper Freeport	1.1	0.17	89.5	5.0
Middle Kittanning	4.0	0.70	85.8	3.8
Pittsburgh	2.4	0.35	88.5	5.0
Illinois No. 6	2.7	1.10	72.7	6.1

It can be concluded that high pyrite and ash reductions were demonstrated at high heating value recoveries for most of the coals investigated by the

LICADO process. As stated earlier, future tests will involve use of multistage devices, fine grinding, and judicious use of additives to further improve process performance.

3.2.5 Comparison With Washability Data

Washability data for the -74 micron (-200 mesh) particle size were obtained for four of the coals investigated in this project. These included Upper Freeport coal (coal #2), Middle Kittanning coal (coal #6), and high ash Illinois No. 6 coal (coal #7). Washability data were also obtained for a low ash Upper Freeport coal (coal #3).

A plot of heating value recovery as a function of ash in the product is shown for the high ash Upper Freeport coal in Figure 3.2.5-1. Within experimental error, the process performance obtained with the RDU appears to match the washability curve closely for the -74 micron coal samples. The anomaly that the LICADO data appear to exceed the limits of the washability curve could be attributed to two possibilities. Firstly, significant experimental error could be introduced while conducting washability analysis for coals as fine as -74 microns. Secondly, the more likely explanation lies in the fact that the washability and the agglomeration process (LICADO) rely on two very different mechanisms and driving forces. The former is a gravity settling process depending on particle density. The latter depends on surface forces. Thus, the achievable separation by the LICADO process may indeed surpass the limit of washability. Figure 3.2.5-2 shows the comparison of the two sets of data for the heating value recovery as a function of pyritic sulfur in the product for the high ash Upper Freeport coal. Again, outstanding results for removal of pyritic sulfur are evident. Figure 3.2.5-3 depicts similar characteristics for product ash in the case of the low ash Upper Freeport coal. It can be concluded that excellent separation characteristics were achieved with the LICADO process at high heating value recoveries for Upper Freeport coal.

Figure 3.2.5-1. Comparison with Washability Curve for Coal #1

Figure 3.2.5-2. Comparison with Washability Curve for Coal #1

Figure 3.2.5-3. Comparison with Washability Curve for Coal #3

Figure 3.2.5-4 compares the performance of the LICADO process with the washability data for Middle Kittanning coal. The results compared favorably with the washability curve. Furthermore, it was possible to reduce the product ash to values under 2% at heating value recoveries of nearly 80%. Figure 3.2.5-5 demonstrates that, for the extremely hydrophilic Illinois No. 6 coal, it was difficult to approach the limit of separation represented by the washability curve. However, improvements in process performance could be achieved by conditioning the coal with 1-Octanol. Again, this demonstrates the importance of coal surface properties for the LICADO process.

3.3 Agglomeration/Screening Tests

The Batch Research Unit was modified in order to carry out agglomeration experiments to simulate the conventional oil agglomeration process. The procedure for operation of screen tests in the BRU is given below. The operation is slightly different from that used for batch tests. This section describes the results from the agglomeration screening tests. Again, this additional work was not specified in the original project proposal and was carried out after completing the work described in sections 3.1 and 3.2.

3.3.1 Equipment

The 2-inch Batch Research Unit (BRU), as described earlier in section 3.1, was modified by incorporating a 175 micron (80 mesh) screen inside the ball valve of the equipment. The screen was inserted inside the ball valve to capture and retain the clean coal agglomerates when the coal-liquid CO₂-water mixture was drained to the bottom through the ball valve. The equipment for the screen agglomeration tests is shown in Figure 3.3.1-1.

Figure 3.2.5-4. Comparison with Washability Curve for Coal #6

Figure 3.2.5-5. Comparison with Washability Curve for Coal #7

Figure 3.3.1-1. Modified Batch Research Unit
(Screen Agglomeration)

3.3.2 Procedure

The volume of coal slurry was maintained constant at 0.0005 m^3 (500 ml), and the slurry was introduced into the top cell after the ball valve was closed. The system was then pressurized with liquid CO_2 until a small amount of liquid CO_2 was observed to collect as a clear layer above the coal slurry. A systematic study of the influence of the volume of liquid CO_2 had indicated that a volume of 0.0001 m^3 (100 ml) above the interface would be adequate, and this volume of liquid CO_2 was used in all subsequent experiments. The mixing speeds were varied from 42 to 420 rad/s (400 to 4000 rpm) to examine the effect of agitation on process performance. The liquid CO_2 was mixed vigorously with the coal slurry for 60 s at the desired agitation speed. Subsequently, the slurry was drained by opening the ball valve. The clean coal agglomerates were captured on the screen and collected after depressurizing the system. The overall yield and ash content of the product were then determined.

3.3.3 Results and Discussion

The results of the screen-type agglomeration experiments with three different coals are shown in Table 3.3.3-1. The mixing speed was maintained at 346 rad/s (3300 rpm) during these tests. The volume surface mean diameters of the feed coals are also given in Table 3.3.3-1. The yield was not high except for the Middle Kittanning coal. The separation characteristics were quite poor, especially for the Illinois No. 6 coal. The effects of mixing speed, particle size, and dispersants on process performance were then examined with the coal which exhibited the worst characteristics, the hydrophilic Illinois No. 6 coal.

Table 3.3.3-2 shows the yield and ash in the product obtained for the Illinois No. 6 coal when the agitation speed was altered over a range of 157 to 420 rad/s (1500 to 4000 rpm). The yield appears to go through a

maximum, but the product ash is not much affected. It is apparent that no significant advantage could be gained by changing the mixing speed for the particle size employed. The overall process performance was quite poor under these conditions.

Table 3.3.3-1
Screen Agglomeration Experiments with Various Coals

Coal	Feed Ash (%)	Particle Size (microns)	Yield (%)	Product Ash (%)	Ash Reduction (%)
Upper Freeport (#2)	22.7	24.7	59.1	16.7	25.6
Middle Kittanning (#6)	7.8	24.0	84.5	5.5	29.4
Illinois No. 6 (#7)	26.0	33.3	42.1	23.1	11.0

The effect of particle size was also investigated on the Illinois No. 6 coal by selecting a narrow size distribution of particles (74 x 44 microns). The agitation speed was varied in these runs from 42 rad/s to 147 rad/s (400 rpm to 1400 rpm). Table 3.3.3-3 exhibits the experimental results for heating value recovery and the separation characteristics obtained when the agitation speed was altered in this range. It can be observed from Table 3.3.3-3 that the higher agitation speeds were conducive to achieving not only high heating value recoveries greater than 80%, but also lowered ash in the product, in sharp contrast to the results presented in Table 3.3.3-2. This indicates that improved dispersion and attachment of liquid CO₂ droplets to the clean coal were achieved at the higher agitation speeds for samples of narrow particle size distribu-

tion. The separation of mineral matter was increased by removing the very fine particles (below 44 microns). Thus, using a narrow size distribution and removing the fine slime coating gave rise to higher recoveries and improved separation. However, the study was not extended to higher agitation speeds, since the results in Table 3.3.3-2 demonstrated that reduced yields were obtained at higher agitation speeds.

Table 3.3.3-2
Effect of Agitation Speed
Particle Size (Surface Volume Mean Diameter): 33.3 microns
Illinois No. 6 coal

Agitation Speed (rad/s)	Yield (%)	Product Ash (%)	Ash Reduction (%)
157	11.7	20.8	19.9
260	46.4	22.9	12.0
346	42.1	23.1	11.0
420	25.6	22.5	13.6

The effect of dispersants on process performance in the screen type agglomeration studies was also investigated. Three different dispersants were employed at a concentration of 20 ppm in solution. These included Sodium Hexametaphosphate (SHMP), Sodium Silicate (SS), and 1-Octanol. Each of them was mixed vigorously with the slurry prior to the experiment. Illinois No. 6 coal was again utilized for these tests with an average particle size of 33 microns. The mixing speed was maintained constant at 346 rad/s (3300 rpm). The results indicated that there was no significant improvement in the yield in the presence of the dispersants SHMP and SS. However, pretreatment with 1-Octanol appeared to enhance the separation characteristics.

Table 3.3.3-3
Effect of Agitation Speed on Samples of
Narrow Particle Size Distribution (74 x 44 microns)
Illinois No. 6 Coal

No.	Agitation Speed (rad/s)	Heating Value Recovery (%)	Ash in Clean Coal (%)	Ash in Refuse (%)	Ash Reduction (%)
1.	42	40.1	25.8	32.0	17.8
2.	126	75.7	17.4	45.4	44.6
3.	147	87.1	14.3	56.9	54.5

Based on the above finding, further experiments were conducted in the presence of 1-Octanol with one additional coal listed in Table 3.3.3-1 (Middle Kittanning coal). The average particle size of the samples was nominally -74 microns. The results for Middle Kittanning coal and Illinois No. 6 coal are shown in Table 3.3.3-4. For Middle Kittanning coal, there was no lowering of ash in the product after conditioning with 1-Octanol. However, there was a steady increase in the heating value recovery, from 70% without the reagent to 87% with 220 ppm of 1-Octanol. In the case of Illinois No. 6 coal, a significant improvement was observed in both the heating value recovery and separation of mineral matter. The heating value recovery was enhanced from 48% to 84% after pretreatment with 1-Octanol solution at a concentration of 210 ppm, while the product ash content decreased from 15.8% to 14.3%. It could be speculated that the -OH group on the alcohol adsorbed preferentially on the coal surface, while the hydrocarbon tail group was oriented towards the bulk solution, thereby increasing the hydrophobicity of the coal particles. At a much higher dosage of 1000 ppm, the reagent behaved as a dispersant as the heating value recovery declined slightly to 77%, while the product ash decreased to 11.8%.

Table 3.3.3-4
Screen-type Agglomeration Experiments
Reagent: 1-Octanol

Coal	Dispersant Conc. (ppm)	Product Ash (%)	Heating Value Recovery (%)	Ash Reduction (%)
Middle Kittanning	0	3.9	70.7	50.4
	55	3.9	73.0	50.4
	105	3.9	80.9	50.4
	220	3.9	87.7	50.4
Illinois No. 6	0	15.8	48.3	39.9
	30	16.0	56.4	39.4
	120	14.1	81.6	45.9
	210	14.3	84.3	45.1
	1000	11.8	77.0	55.0

A comparison of the screen-type agglomeration experiments and the variable volume batch operation can be made for the high ash Illinois No. 6 coal (coal #7). The results obtained in the 0.10 m (4-inch) RDU were described in section 3.2.3 (Table 3.2.3-5) with and without conditioning the coal in 1-Octanol solutions. The RDU test results provided lower ash contents in the product compared to those obtained in the screen agglomeration tests. The heating value recoveries obtained after conditioning with 1-Octanol are comparable in both types of tests. It can be inferred that the variable volume batch operation is more favorable for achieving improved process performance. It must be emphasized that, while the screen-type agglomeration experiments provide a quick method to determine the trend of the results, the variable volume operation is the preferred method to provide desirable process performance.

REFERENCE

- 3-1. B. I. Morsi et al, "Coal Surface Control for Advanced Physical Fine Coal Cleaning Technologies" Annual Report (1988-89) submitted to the Department of Energy.

4.0 CONTINUOUS RESEARCH UNIT

A Continuous Research Unit (CRU) was designed, constructed, and operated to demonstrate the performance of an integrated LICADO process. The system was designed for a capacity of 0.45-4.53 kg/s (1-10 lb/hr). The design of the CRU is principally based on the experience gained from extensive testing in the RDU and BRU. The diameter of the separator in the RDU is also 0.10 m (4-inches), and the experimental data from RDU and BRU experiments were used as the basis for the design of the CRU. Cold model experiments and computer simulation of high pressure discharge operations were also utilized to simulate the critical operating components prior to construction. The operation is fully automated. Both process control and data logging are performed using a personal computer interfaced with the gauges, valves, and pumps in the system.

4.1 Equipment

A flow diagram of the CRU is shown in Figure 4.1-1. A photograph of the unit is provided in Figure 4.1-2. The CRU is mounted on a steel frame 3.04 m (10 ft) long, 1.52 m (5 ft) wide, and 5.5 m (18 ft) in height. A detailed description of the principal components of the system is given below.

4.1.1 Clean Coal/Refuse Separator

The central unit of the LICADO continuous system is the separation column shown in Figure 4.1-3. In this unit, the coal-water slurry is mixed with liquid CO_2 to separate the clean coal from the mineral matter. The separation takes place in a 0.10 m (4-inch) I.D. stainless steel column. Mixing is provided by a variable speed motor. Two injection points for liquid CO_2 and one for the coal-water slurry are provided, and their vertical positions can be adjusted along the column. Both column ends are of conical shape, in order to eliminate any solids accumulation and to facilitate their removal from the unit.

Figure 4.1-1. Continuous Research Unit (CRU) Flow Diagram

Figure 4.1-2. Photograph of the CRU

Figure 4.1-3. Separation Column

The clean coal-liquid CO_2 product stream is removed from the top of the unit through a tube leading to a high pressure clean coal filter. On the other hand, the refuse stream is continuously withdrawn from the bottom of the unit. The position of the liquid CO_2 -water interface is controlled using a capacitance probe coupled with a regulating valve for the withdrawal of the refuse/water slurry from the bottom of the separation column.

4.1.2 Premixing Tank

A premixing tank was designed and installed for high-shear agglomeration of feed coal with liquid CO_2 from the slurry injection to the separation column. This device was used to increase the capacity of the system and improve the quality of the clean coal product. Figure 4.1-4 shows the premixing unit of 0.101 m (4-inch) I.D. and a height of 0.51 m (20 inches) equipped with a mixer which can operate up to 210 rad/s (2000 rpm).

4.1.3 Slurry Preparation Unit

This unit consists of a 0.21 m^3 (55-gallon) plastic stirred tank and a high pressure slurry pump. The feed coal-water slurry is prepared in the tank. Mixing in the tank is provided using two four-pitched blade impellers driven by a 0.19 kW (1/4 hp) motor. The coal-water slurry is transported into the separation vessel by the slurry pump. The pump is specified to develop a maximum discharge pressure of 8612 kPa (1250 psig) and a maximum slurry flowrate of 0.075 m^3/s (72 gph).

4.1.4 Clean Coal/Liquid CO_2 Separator

The clean coal leaves the separation column in the form of an agglomerate with liquid CO_2 and a small amount of water. In order to remove the clean coal from the mixture with minimum losses, a high pressure filter

Figure 4.1-4. Premixing Tank

was designed and installed. The high pressure filter, shown in Figure 4.1-5, is composed of a porous tube enclosed in a 0.15 m (6-inch) I.D. stainless steel tee. The clean coal-liquid CO₂ slurry is fed inside the porous tube, and the liquid CO₂ is filtered out through its wall. The clean coal is removed by a variable pitch auger driven by an external high torque motor and falls into a 0.05 m (2-inch) I.D., 0.31 m (12-inch) long container. The container can be depressurized, emptied, and repressurized by operating a vent, a connection to a CO₂ source and two 2-inch pneumatically actuated ball valves at its ends. The liquid CO₂ leaving the clean coal filter is recycled into the separation column so that the required makeup is minimized.

4.1.5 Refuse/Water Separator

The refuse is removed from the bottom of the separation column in the form of a dilute coal-water slurry. The refuse removal unit consists of two stainless steel 0.15 m (6-inch) diameter flanged tanks 0.51 m and 1.02 m (20 and 40 inches) tall. The refuse slurry is discharged from the column to the tanks by hydrostatic pressure (see below).

4.2 Procedure

A brief description of the operating procedure for the CRU is given below:

1. Coal-Water Slurry Preparation

- a. The original coal sample is crushed in a jaw crusher and pulverizer to 0.003 m x 0 (1/8" x 0).
- b. Further size reduction is achieved by wet grinding using a stirred ball mill. For each batch, 1.81 kg (4 lb) of coal and 4.1 kg (9 lb) of water is ground using 1.36 kg (30 lb) of stainless steel balls of 0.009 m (3/8") size. The resulting slurry is wet screened to remove particles larger than +590 micron (+ 28 mesh).

Figure 4.1-5. Clean Coal Filter

- c. The slurry is loaded into the feed tank, and water is added to adjust the slurry concentration to a predetermined value. The mixer is turned on to prevent coal settling.

2. Continuous Operation Start-Up

- a. Turn on the main power for the CRU.
- b. Load liquid CO₂ into the liquid CO₂ tank.
- c. Check the pneumatic valves, the pumps, and gauges to insure their proper working condition.
- d. Run the continuous system program. This program interactively performs the following sequence of operations needed to start-up the unit:
 - Reset relays and regulating valves.
 - Display, set, and log operating conditions.
 - Determine control parameters.
 - Pressurize the system.
 - Add water to the separation column.
 - Turn on the stirrer motors.
 - Start liquid CO₂ injection into the premixing tank and separation column.
 - Start coal-water slurry injection into premixing tank.

3. Operation Management and Control

The operation of the CRU is controlled by a personal computer using a continuous system program. The program allows for the display of all the variables measured. It is also possible to adjust operating conditions in terms of the liquid CO₂ flowrate, the interface position in the separation column, and the clean coal discharge time interval without interrupting the operation.

4.2.1 Continuous Operation Control Schemes

The operation of the CRU is fully automated. A microcomputer furnished with a 32 channel A/D input board, an 8 channel D/A output board, and a 16 channel relay card is interfaced with the equipment control valves and measurement devices.

The signals from 16 measurement devices are used to control three regulating valves, eight ball valves, and two pumps. The signals from four pressure transducers, four thermocouples, two flowmeters, a liquid CO₂-water interface level indicator, and five level alarms are received by an A/D converter module and read by a microcomputer. The system information is processed and used to control the equipment operation. The 4-20 mA output signals are sent to the pneumatic regulating valves via a D/A converter module. The ball valves and the pumps are operated using a relay output card.

Eight pneumatic ball valves, the high pressure slurry pump, and the liquid CO₂ recirculation pump can be operated manually from a control panel or switched to computer control mode. The measurements from the pressure transducers, the level indicators, and the Coriolis type mass flowmeters are displayed on the control panel and also received by the computer via an A/D board.

Considerable efforts were devoted to updating and refining the process control schemes for the continuous operation of the LICADO process. These include:

1. Interface position control
2. Refuse discharge control
3. Liquid CO₂ flowrate control
4. Clean coal discharge control

A brief description of the main control loops is presented below.

4.2.1.1. Interface Position Control

Figure 4.2-1 shows the equipment used for the control of the interface position in the separation column. The position is read with a 0.73 m (29-inch) capacitance probe which transmits the signal to the computer. In turn, the computer positions a 0.02 m (1-inch) pneumatic regulating valve which is used to adjust the rate of underflow from the separation column and therefore, the position of the water-liquid CO₂ interface in the separation column. The controller was tuned by first determining calibration curves for the slurry pump (% stroke length vs flowrate) and the regulating valve (% open vs flowrate) using water and coal-water slurries. The system dynamic response was also studied. A software driven proportional controller was adopted.

4.2.1.2 Refuse Discharge Control

Figure 4.2-2 shows the refuse slurry discharge system. This section of the CRU operates cyclically by automatically operating the valves connected to the two refuse tanks. After each discharge, Tank 2 is repressurized by connecting it to the liquid CO₂ tank. When Tank 2 attains system pressure, the two tanks are reconnected again. While Tank 2 is discharged, the refuse slurry is continuously transferred from the separation column to Tank 1. This procedure was tested at low pressure and was also simulated using a model based on fundamental fluid mechanics equations that incorporated the results of these tests. The simulation results were used to design the high pressure refuse removal system.

4.2.1.3 Liquid CO₂ Flowrate Control

Figure 4.2-3 depicts the liquid CO₂ recirculation circuit. Liquid CO₂ is injected into the mixing tank and into the separation column. The flowrate of both streams is measured using Coriolis type mass flowmeters. The signals from these devices are used to position two 0.01 m (1/2-inch) pneumatic regulating valves. Because a gear pump is used to

Figure 4.2-1. Interface Position Control

Figure 4.2-2. Refuse Discharge Control

Figure 4.2-3. Liquid CO₂ Flowrate Control

recycle liquid CO_2 , a bypass to the liquid CO_2 tank must be provided to control the total flowrate of liquid CO_2 . The regulating valves are located on the bypass line and on the line carrying liquid CO_2 to the mixing tank. The total liquid CO_2 flowrate and the ratio between the two flowrates is calculated and used to position the valves. A manual regulating valve on the line leading to the separation column is adjusted before each experiment, depending on the flowrate values to be used in the test. A proportional-integral controller was adopted for the liquid CO_2 flowrate control.

4.2.1.4 Clean Coal Discharge Control

Figure 4.2-4 shows the clean coal vessel used for the separation of clean coal from liquid CO_2 and the discharge of the product. The clean coal is cyclically discharged at preset time intervals by isolating the clean coal container from the vessel, venting it, and unloading the product to a receiving vessel at atmospheric pressure. The container is then depressurized and connected to the clean coal vessel. Typical discharge intervals are 1800 s (30 min) long. The clean coal container is unloaded at 345 kPa (50 psig) to facilitate the coal discharge.

4.3 Results and Discussion

Most of the CRU experiments were performed with Upper Freeport coal (coal #3). The range of operating conditions in the CRU experiments are shown in Table 4.3-1.

Initial sets of experiments were conducted without a conical section on top of the separation column. Upper Freeport coal (#1 in Table 3.0-1) was utilized in these tests. Problems were experienced with the operation of the clean coal filter due to carryover of water from the separation vessel. Water intrusion into the pores of the filter resulted in clogging of the porous tube by the clean coal and has restricted usage of the filter. An improved design of the filter is required.

Figure 4.2-4. Clean Coal Discharge Control

The experiments confirmed the trend observed in the batch tests, suggesting that lower mixing speed yields a cleaner product. A phenomenon common to all these experiments was the strong correlation between the water content and the ash content in the clean coal samples. In general, the lower water content in the product correlated well with lower ash contents in the clean coal product. Mixing speeds higher than 125 rad/s (1200 rpm) caused water entrapment in the agglomerates and, consequently, a wet product. Mixing speeds below 63 rad/s (600 rpm) had a similar effect, which was likely caused by poor dispersion of the liquid CO₂ droplets in the slurry. The results obtained in the variable volume batch unit showed that the addition of a conical section on top of the separation column improves the process performance. A similar device was added to the separation column of the CRU.

Table 4.3-1
Range of Operating Conditions in CRU

Slurry Flowrate, m ³ /s x 10 ⁻⁶	0.3-15 (200-900 ml/ml)
Slurry Concentration, Wt%	5-10
Slurry Injection Point, m (below top of cone)	0.31-0.51 (12-20 in)
Interface position, m (below top of cone)	0.15-0.45 (6-18 in)
Liquid CO ₂ Flowrate, kg/s	
In Premixing Tank	0-0.01 (0-600 g/min)
In Separation Column	0.0016-0.04 (100-2500 g/m)
Mixing Speed, rad/s	
In Premixing Tank	125-209 (1200-2000 rpm)
In Separation Column	42-125 (400-1200 rpm)
Residence Time in Sep. Column, s	360-1440 (6-24 min)

Freshly ground samples of Upper Freeport coal (coal #3) were utilized to prepare new batches of 4.8% feed coal-water slurry. Tests 31 through 37 were carried out using these slurry samples. Experiments were performed using a mixing speed of 84 rad/s (800 rpm), a slurry flowrate of $3.6 \times 10^{-6} \text{ m}^3/\text{s}$ (220 ml/min), and an interface location of 0.30 m (12 inches) below the top of the cone. The results of these tests are shown in Table 4.3-2.

A large reduction in the amount of water present in the clean coal samples was observed in this set of experiments. The clean coal throughput increased above .0001 kg/s (0.8 lb/hr) when the liquid CO_2 was injected at a higher point in the separation column. It is believed that entrainment of liquid CO_2 in the refuse stream caused the lower yield observed in the lower injection point tests. The duration of these tests ranged from three to seven hours.

Figure 4.3-1 shows the results obtained during Test 31. The clean coal was discharged every 1800 s, and each sample was weighed out. As can be observed from Figure 4.3-1, the clean coal output rate increases to about 0.00075 kg/s (0.6 lb/hr) at the higher CO_2 flowrate of 0.016 kg/s (1000 gm/min). The ash content in the product was reduced to about 4% throughout the entire duration of the test. The clean coal solid content (the amount of dry product coal as a function of the product discharge consisting of coal, water, and some CO_2) was held nearly constant at 65% except toward the end of the test period.

Figure 4.3-1. Results of Test 31

Table 4.3-2
CRU Tests with Upper Freeport Coal (coal #3)
Coal Feed Rate = 0.00017 kg/s (1.4 lb/hr)

Test No.	Liquid CO ₂		Clean Coal			
	Injection m below cone top	Flowrate kg/s	Heating Value Recovery* %	Solid Content %	Ash Reduction %	Pyritic Sulfur Reduction %
31	1.11	0.013	35	75	71.8	76.8
31		0.016	44	70	71.1	76.8
34		0.020	48	61	77.5	78.5
37	0.81	0.013	58	69	74.0	79.2
36		0.016	69	65	71.8	76.2
34		0.020	63	64	77.5	78.0

* Average over duration of run

Further investigation of the aging effect on slurry samples showed that the contact angles obtained from samples taken immediately after wet grinding and two days after wet grinding remain above 90 degrees (i.e., the coal was hydrophobic) as indicated in Table 4.3-3. The contact angle decreased sharply after 3 days, and a zero reading was registered after 6 days (i.e., the coal was completely hydrophilic). These results strongly suggest that CRU tests should be carried out within two days of preparing the feed slurry in order to obtain meaningful and reproducible results. The alteration in surface property of the coal is thus an important variable affecting the process performance. The improved results obtained in Tests 31-37 could be attributed not only to better operating procedures but also to the fact that freshly ground hydrophobic coal was utilized.

Table 4.3-3
Contact Angle Results for Upper Freeport Coal Samples

Days After Slurry Preparation	Advancing Contact Angle (degrees)
0	119
1	96
2	104
3	49
6	0

For experiments conducted after installing the premixing tank, Upper Freeport coal (coal #3) with an ash content of 16.6% and a sulfur content of 2.6% was used. A coal feed rate of 0.00016 kg/s (1.3 lb/hr) and a slurry concentration of 5% were used in these tests. A mixing speed of 168 rad/s (1600 rpm) in the premixing tank and 84 rad/s (800 rpm) in the separation column was utilized.

The effects of the liquid CO₂ injection rate into the separation column, as well as the influence of the slurry injection point, were investigated. Table 4.3-4 shows the results of these tests.

Table 4.3-4 shows the importance of the liquid CO₂ injection rate into the separation column. In both cases, for slurry injection points of 0.30 and 0.41 m (12 and 16 inches), there is a linear relationship between the yield and the rate of liquid CO₂ injected in the separation column. In the experiments in which the slurry is injected above the interface at 0.30 m (12 inches) below the cone top, the effect of the liquid CO₂ rate on the yield is more pronounced than in the case of slurry injection below the interface. Table 4.3-4 shows that under this condition, a heating value recovery as high as 80% was achieved with good separation characteristics when the liquid CO₂ flowrate was maintained at 0.005 kg/s (300 g/min) in both the premixing tank and the separation column. When the slurry is injected above the interface, the

liquid CO₂ injected directly into the separation column is the only stream available for capturing agglomerates in the aqueous phase. In the case of the injection below the interface, the liquid CO₂ carried from the premixing tank also contributes to transferring agglomerates across the interface. In the latter case then, the liquid CO₂ injected into the column does not play a role as critical as in the case of injection above the interface. The above data also indicate that the water content of the product is higher when the slurry is injected below the interface. The additional water entrainment is caused by the carryover in liquid CO₂ from the premixing tank.

Table 4.3-4
Effect of the Liquid CO₂ Injection
Rate into the Separation Column and
the Slurry Injection Point Position
Interface Position: 0.36 m (14 inches) below top of cone

Slurry Injection Point, m below cone top	Liquid CO ₂ Flowrate, kg/s		Clean Coal			
	Mixing Tank	Separation Column	Heating Value Recovery %	Solid Content %	Ash Reduction %	Pyritic Sulfur Reduction %
0.30	0.005	0.0016	22	52	66.2	77.1
		0.0033	48	57	66.2	77.1
		0.0050	80	57	65.6	77.0
0.41	0.0033	0.0016	47	48	65.6	77.0
		0.0033	61	53	63.8	76.2
		0.0050	73	44	62.6	78.5

The effect of the liquid CO₂ injection rate into the premixing tank on the process results is shown in Table 4.3-5.

From the data in Table 4.3-5, it can be observed that conditioning of the slurry in the premixing tank increases the product recovery (also compared

with results in Table 4.3-2). The results show that only 0.83×10^{-3} kg/s (50 g/min) of liquid CO_2 are needed in the premixing tank to form agglomerates, and that a larger amount of liquid CO_2 does not significantly influence the process performance.

Table 4.3-5
Effect of Liquid CO_2 Injection into
the Premixing Tank

Separation Column Liquid CO_2 Flowrate: 0.005 kg/s

Premixing Tank Liquid CO_2 Flowrate kg/s $\times 10^{-3}$	Clean Coal			
	Heating Value Recovery %	Solid Content %	Ash Reduction %	Pyritic Sulfur Reduction %
0.0	44	67	72.9	75.0
0.83	72	61	70.5	74.4
1.66	77	62	66.3	73.8
5.0	68	61	66.3	73.8

The influence of the liquid CO_2 -water interface position in the separation column on the process performance was studied by conducting tests with the interface at 0.36, 0.41, and 0.46 m (14, 16, and 18 inches) below the top of the cone. These tests were carried out using a liquid CO_2 flowrate of 0.0083 kg/s (50 g/min) in the mixing tank and 0.083 kg/s (500 g/min) in the separation column. The slurry injection point was kept at 12 inches below the cone top. The results of these experiments are shown in Table 4.3-6. They indicate that a lower interface translates into a higher solid content in the product but at the expense of a lower product recovery.

Table 4.3-6
Effect of the Interface Position

Interface Position, m below cone top	Clean Coal			
	Heating Value Recovery %	Solid Content %	Ash Reduction %	Pyritic Sulfur Reduction %
0.36	69	49	66.3	72.6
0.41	64	61	69.3	73.8
0.46	57	69	72.3	74.4

The effect of the mixing speed in the premixing tank was studied in experiments carried out with the interface located 0.46 m (18 inches) below the top of the cone. The feed coal rate was 0.00017 kg/s (1.4 lb/hr) and the slurry injection point was located 0.30 m (12 inches) below the top of the cone. The liquid CO₂ injection rate into the mixing tank was 0.00083 kg/s (50 g/min) and 0.0083 kg/s (500 g/min) in the separation column. The results of these experiments are given in Table 4.3-7. The results show that the product recovery improves with lower mixing speed in the premixing tank with only a minor decrease in the product quality.

Table 4.3-7
Effect of the Premixing Tank Mixing Speed

Premixing Tank Mixing Speed, rad/s	Clean Coal			
	Heating Value Recovery %	Solid Content %	Ash Reduction %	Pyritic Sulfur Reduction %
125	67	69	69.3	73.8
166	57	69	72.3	74.4
210	46	72	73.5	75.0

The effect of the liquid CO₂ distribution was studied using a total liquid CO₂ flowrate of 0.015 kg/s (900 g/min). The mixing speed was kept at 63 rad/s (600 rpm) in the separation column and at 125 rad/s (1200 rpm) in the premixing tank. The interface was located at 0.36 m (14 inches) below the top of the cone. Table 4.3-8 illustrates that excellent heating value recoveries close to 80% were achieved at a flowrate of 0.005 kg/s (300 g/min) in the premixer. The heating value recovery increased steadily as the flowrate in the premixing tank was increased.

Experiments with Upper Freeport coal (coal #3) have also been conducted at higher capacities of 0.00076 kg/s and 0.0012 kg/s (6 lb/hr and 10 lb/hr). The system operated smoothly at its rated capacity of 0.0012 kg/s (10 lb/hr).

Table 4.3-8
Effect of Liquid CO₂ Distribution

Liquid CO ₂ Flowrate kg/s x 10 ⁻³		Clean Coal			
Premixing Tank	Separation Column	Heating Value Recovery %	Solid Content %	Ash Reduction %	Pyritic Sulfur Reduction %
1.66	13.3	57	63	66.3	72.6
3.33	11.6	71	58	65.7	72.6
5.00	10.0	78	63	67.5	74.4

Results with Upper Freeport coal (coal #3) were compared with data from the washability analysis of -74 micron size samples, and they are presented in Figure 4.3-2 for a feed rate of 0.00017 kg/s (1.4 lb/hr). It can be observed that the CRU results were close to the washability curve. It must be pointed out that the washability curve was obtained for a batch of coal #3 with a feed ash content of 13.5%, while the CRU experimental

Figure 4.3-2. Comparison with Washability Curve for 1.76×10^{-4} kg/s (1.4 lb/hr) with Upper Freeport Coal

results were obtained with another portion of the same sample exhibiting an ash content of 16.6% in the feed. In other words, the washability curve was obtained for a cleaner feed coal. The inherent differences in the results due to this factor must also be considered. A similar plot was generated for a feed rate of 0.00038 kg/s (3 lb/hr), as shown in Figure 4.3-3. The variation of pyritic sulfur in the product with heating value recovery for Upper Freeport coal is represented in Figure 4.3-4.

In Figure 4.3-5, the coal feed rate, up to 0.0012 kg/s (10 lb/hr), has been plotted as a function of heating value recovery and ash reduction for coal #3. The range of experimental results for various operating conditions at each capacity is represented in the graph in the form of bars. It can be observed that heating value recoveries are in the 80% range for capacities up to 0.00038 kg/s (3 lb/hr), but they decrease at higher feed rates. The effect on ash reduction is not so pronounced at higher feed rates, and the ash reduction remained in the 60-70% range. After completing an extensive number of tests with Upper Freeport coal (approximately 80 experiments in the CRU), two other coals were also tested in the CRU, utilizing the optimum values of parameters observed for Upper Freeport coal as a starting point in the investigation. Limited number of tests were carried out with Pittsburgh No. 8 coal and Illinois No. 6 coal.

The results obtained in processing Pittsburgh No. 8 coal in the CRU are shown in Figure 4.3-6, and comparison is made with the washability curve at the same particle size (-74 microns). The results shown in Figure 4.3-6 were for a capacity of 0.00017 kg/s (1.4 lb/hr). The graph reveals that the separation obtained is better than the washability curve for this particle size. Improved results were obtained by maintaining the interface position at 0.3 m (12 inches) below the top of the cone. Tests performed at higher feed rates again resulted in a decrease in the heating value recovery. A limited number of experiments were also conducted with Illinois No. 6 coal (coal #8). Figure 4.3-7 compares the experimental results at a capacity of 0.00017 kg/s (1.4 lb/hr) with the washability

Figure 4.3-3. Comparison with Washability Curve for 3.78×10^{-4} kg/s (3 lb/hr) Tests with Upper Freeport Coal

Figure 4.3-4. Pyritic Sulfur in Product as Function of Heating Value Recovery for Upper Freeport Coal

Figure 4.3-5. Effect of Coal Feed Rate on Process Performance

Figure 4.3-6. Comparison with Washability Curve for Pittsburgh No. 8 Coal

Figure 4.3-7. Comparison with Washability Curve for Illinois No. 6 Coal

curve for the -74 micron sample. Again, the performance of the LICADO process appears to be superior to that indicated by the washability analysis. Improved heating value recovery as well as separation were observed when the interface position was raised to 0.25 m (10 in) below the top of the cone.

The results indicate that for the present column design (including column dimensions and mixer), the CRU can achieve excellent process performance up to 0.00038 kg/s (3 lb/hr). Mechanical modifications are required to upgrade the performance characteristics of CRU for larger throughputs. Larger CO₂/coal ratios may be required to obtain improved process performance for throughputs exceeding 3 lb/hr. Minor modifications in the design of the clean coal filter will permit the handling of larger volumes of liquid CO₂.

In conclusion, the integrated LICADO process was successfully developed by constructing and operating the Continuous Research Unit up to its capacity of 10 lb/hr. The unit was operated smoothly in tests lasting up to 14 hrs. The different units in the CRU (i.e., the separation column, filter, premixing tank, and the various control schemes) functioned well in conjunction, and troublefree operation was achieved. The effects of various process parameters such as mixing speed, flowrate of CO₂ in premixer and separation column, and interface and slurry injection positions were investigated. The findings obtained in the CRU can be used to establish design criteria for the development of a 1 ton/hr proof-of-concept plant based on the LICADO process.

5.0 CONTINUOUS UNIT

The objective of this task was to design and develop a Continuous Unit to process up to 0.006 kg/s (50 lb/hr) of feed coal by the LICADO process.

5.1 Equipment

To upgrade the Continuous Research Unit to process up to 0.006 kg/s (50 lb/hr) of feed coal, a new separation column was designed and fabricated at the University of Pittsburgh. The separation column is shown in Figure 5.1-1. It has a diameter of about 0.15 m (6 inches) I.D. and a height of 0.93 m (37 inches). A conical section will be added to the top of this unit. Owing to time limitations, the test program was redirected; and the experimental program for the 0.006 kg/s (50 lb/hr) tests was not performed.

Figure 5.1-1. 0.006 kg/s (50 lb/hr) Separation Column

6.0 SIMULATION MODEL

A plant simulation model was developed to provide scale-up data for the Proof-of-Concept Plant and to provide equipment and process information for the commercial plant economic studies.

6.1 Description of Model

The plant simulation model (LICADO Plant Simulation), LIPS, provides material and energy balances around each of the unit operations in the LICADO Plant. This model, which is programmed in FORTRAN, is operational on any Personal Computer (PC) having FORTRAN IV software. Two programs are available, LIPSA, which is for Pittsburgh-Bruceton coal, and LIPSB, which is for Upper Freeport coal. The listings for these programs are attached to this report as Appendix E and F. Other coals can be modeled simply by using their properties as input to the program.

Input data for LIPS includes the identification of the coal being processed, its composition (ash, moisture, pyritic sulfur, organic sulfur, sulfates), and process separation factors for ash and pyritic sulfur. The desired clean coal production rate for the plant simulation is also specified. Other plant characteristics are also provided as input to the program. These data include coal particle size, feed slurry concentration, residence times in the mixer and separator, separation efficiencies at the filter, cyclone and dewatering unit, solubility of carbon dioxide in the water, solubility of water in the carbon dioxide, and ratio of liquid carbon dioxide flow to slurry flow rate. These plant characteristics for the model were based on the test data obtained from both the batch tests and the experiments with the Continuous Research Unit.

The unit operations for the simulation model are shown in Figure 6.1-1. The power required to grind the coal is calculated using an algorithm

LICADO PLANT SIMULATION
UPPER FREEPORT COAL
PRODUCTION RATE, LB/HR=2000.0

	1	2	3	4	5	6	7	8
	FEED	GRNDR	SLURRY	MIXER	CO2 RCY	SEP PR	SEP RF	CYL DV
RAW COAL	.2991E+04	.2991E+04	.2991E+04	.2991E+04		.2000E+04	.2991E+03	.7673E+02
CLN COAL							.2692E+05	
WATER	.2214E+02	.2665E+05	.2692E+05	.2692E+05	.5385E+02		.7479E+02	.9674E+04
CO2-llq				.1496E+05	.1496E+05	.1488E+05		
CO2-gas						.2558E+00		
ASH	.7299E+03	.7299E+03	.7299E+03	.7299E+03		.9854E+02	.6204E+03	
SULFUR	.9004E+02	.9004E+02	.9004E+02	.9004E+02		.3527E+02	.5085E+02	

	9	10	11	12	13	14	15	16
	PRODUCT	FLTR LIQ	REFUSE GAS	PRDD GAS	COMPRESS	REFUSE	RECYL WTR	MK UP WTR
RAW COAL								
CLN COAL	.2000E+04	.2557E+01				.2872E+03		
WATER	.9962E+00	.1042E+02				.2687E+03	.2665E+05	.2697E+03
CO2-llq		.5209E+04			.2713E+02		.7404E+02	
CO2-gas	.2558E+00		.2687E+02	.2558E+00		.7479E+00		
ASH	.9854E+02					.6204E+03		
SULFUR	.3527E+02					.5085E+02		

CC880608-2F

Figure 6.1-1. Integrated Statepoint Diagram

based on the final particle size. This algorithm and the supporting data are provided in Appendix E. The material balance at the slurry tank provides the makeup water that is required to be added to the recycle water to yield the required solids concentration in the slurry. The slurry pump power is calculated from the slurry flow and pressure differential across this pump.

The mixer and separator are sized to provide the specified residence time in each unit. The wall thicknesses of the shell and the head of each of these units are calculated using the ASME Code for Unfired Pressure Vessels. The Mixer and Separator are assumed to be fabricated of stainless steel clad carbon steel. Therefore, the mechanical properties of SA516, Grade 70 carbon steel, were used to calculate the required wall and head thicknesses for the pressure vessel. From the separator, the carbon dioxide/clean coal slurry flows to the cyclone. The cyclone, which is not included in the Continuous Research Unit, has been added to the Proof-of-Concept design as a result of the plant simulation studies. The cyclone removes about 65% of the liquid carbon dioxide from the carbon dioxide/clean coal stream leaving the separator. Removal of this liquid carbon dioxide reduces the liquid flow through the filter and reduces its size.

The cyclone is modeled using the overflow and underflow distributions recommended by the cyclone manufacturer. Since the small amount of coal entrained in the overflow is recycled to the process, the coal in the liquid carbon dioxide will reach a steady-state concentration; and its effect upon the clean coal production rate can be neglected.

Refuse and water, discharged from the bottom of the separator, enters a dewatering tank, where the liquid is depressurized, the refuse slurry is discharged, and the water is recycled to the wet grinder. The carbon dioxide in solution in the water flashes to vapor when the pressure is released in the dewatering unit. This vapor is recompressed and cooled to a liquid and recycled to the liquid carbon dioxide system.

The underflow from the cyclone flows to the filter in which the clean coal is separated from the liquid carbon dioxide. The liquid carbon dioxide from the filter flows to the liquid carbon dioxide system, while the clean coal passes to the clean coal depressurizer, where the clean coal is discharged and the absorbed liquid carbon dioxide flashes to vapor upon depressurization. This carbon dioxide vapor joins the carbon dioxide vapor released from the water and is liquefied by the compressor/cooler.

The output from LIPS is displayed in two arrangements. In the first, the output is presented in tabular form, together with the input and plant characteristics. A sample of this output is illustrated in the Appendix. In order to provide a graphic output that is visually linked to the plant flow diagram, the output file from LIPS can be transferred to the CADD system in which the plant flow diagram is programmed. The output file from LIPS is stored on a disk, and this file can be read into the CADD system, which then provides a plant flow diagram integrated with the state point data obtained from the LIPS output file. Figure 6.1-1 is an example of the plant flow diagram incorporating the LIPS output data using this method. The output data are presented in FORTRAN exponential notation for compactness and uniformity of the tables. In this notation, the decimal at the left is multiplied by 10 raised to the power indicated after the "E". The numbers in the column headings refer to the flow streams in the flow diagram.

In order to define the complete process, both the integrated statepoint/flow diagram and the tabular process summary must be used. The tabular process summary provides information specifying the coal characteristics and the process constraints and assumptions. The assumptions and constraints include constraints such as the CO_2 -to-coal slurry ratio, residence time in the mixer and separator, for example, and assumptions such as separation efficiencies at the various unit operations. The assumptions are based on experimental data from the batch tests and the Continuous Research Unit.

The process data, constraints and assumptions made for this analysis are:

Coal Properties:

Fract. Ash	0.244 (dimensionless)
Fract. Moisture	0.0074 (dimensionless)
Fract. Pyrite Sulfur	0.0104 (dimensionless)
Fract. Organic Sulfur	0.0039 (dimensionless)
Fract. Sulfates	0.0001 (dimensionless)

Process Data:

Clean Coal Production Rate	2,000 lb/hr
Coal Heating Value	13,000 Btu/lb
Coal Particle Size	73 microns
Slurry Concentration	0.10 (dimensionless)
Mixer Residence Time	100 sec
Separator Residence Time	500 sec
Fract. Ash Removed	0.90 (dimensionless)
Fract. Pyrite Removed	0.90 (dimensionless)
Fract. Water in CO ₂	0.002 (dimensionless)
Fract. CO ₂ in Water	0.005 (dimensionless)
System pressure	850 psia
CO ₂ to Slurry Ratio	0.50 (dimensionless)
Fract. Coal Separated by Filter	0.999 (dimensionless)
Fract. Water in CO ₂	0.002 (dimensionless)

6.2 Results

6.2.1 Plant Studies

Plants with clean coal capacities of 1-ton/hr (0.91 metric ton/hr), 50 tons/hr (45 metric tons/hr), and 200 tons/hr (181 metric tons/hr) were analyzed with LIPSA (for Pittsburgh Bruceton coal) and LIPSB (for Upper Freeport coal). These analyses were used for the design of the Proof-of-Concept Plant (0.91 metric ton/hr) and for economic analyses of 45 and 181 metric ton/hr commercial scale plants. Minor differences in the plants using Pittsburgh-Bruceton and Upper Freeport coal were observed. The differences result from the higher ash content of the Upper Freeport coal, which requires more feed coal, compared to Pittsburgh-Bruceton coal, to yield the same clean coal product. The higher feed requirement results in more water and liquid carbon dioxide for the same production rate. For the purposes of the Proof-of-Concept and plant economic studies, Upper Freeport coal was selected as the reference coal, since this coal resulted in the slightly higher flow requirements, and hence the more conservative design parameters.

6.2.2 Separator/Mixer Studies

The plant simulation code has been used to perform a parametric study of the radius of the Separator for the Proof-of-Concept Plant. Parameters which were investigated include slurry concentration, CO_2 -to-coal-water slurry ratio, and residence time. Figures 6.2-1 through Figure 6.2-3 show the correlation between Separator radius and residence time at three CO_2 -to-slurry flow ratios; each figure represents a coal concentration in the slurry of 10, 20, or 30 percent, respectively. Figure 6.2-4 shows the correlation between Separator radius and slurry concentration at a residence time of 500 seconds and at CO_2 -to-slurry flow ratios of 0.20, 0.35, and 0.50. The aspect ratio for the separator and mixer was fixed at 20 in these studies; i.e., the length is 20 times the radius.

Figure 6.2-1. Separator Radii, 1 Ton/Hr Plant
10% Slurry Concentration

Figure 6.2-2. Separator Radii, 1 Ton/Hr Plant
20% Slurry Concentration

Figure 6.2-3. Separator Radii, 1 Ton/Hr Plant
30% Slurry Concentration

Figure 6.2-4. Separator Radii, 1 Ton/Hr Plant
500 Seconds Residence Time

As expected, the Separator radius is a strong function of residence time and slurry concentration, and is a weaker function of CO₂ flow ratio. The parameters for the preliminary design for the Proof-of-Concept Plant Separator were selected based upon test data which had been obtained with the Continuous Research Unit (CRU) and the Research Development Unit (RDU) as follows:

Coal concentration in slurry	10%
CO ₂ to slurry flow ratio	0.50
Residence Time	300 seconds

With these parameters, the radius of the Separator for the Proof-of-Concept Plant is 26.7 cm (10.5 inches).

6.2.3 Continuous Research Unit Study

The potential maximum capacity of the Continuous Research Unit (CRU) was investigated using LIPS. Since the Separator Column is the critical component determining the maximum system capacity, a parametric study of the relationships among the column diameter, residence time, CO₂/slurry ratio, and coal concentration in the feed slurry was performed.

Figure 6.2-5 shows the Separator Column radius as a function of residence time at CO₂ to water/coal feed slurry, and a clean coal production rate (Pittsburgh-Bruceton coal) of 100-lb/hr. Since the radius of the CRU Separator Column is 5.1 cm (2-inches), residence times of 120 to 150 seconds can be achieved at a product rate of 45.4 kg/hr (100-lb/hr). The required Separator radius increases as the CO₂-to-feed slurry ratio rises. However, the CO₂-to-feed slurry ratio is not a strong factor in determining the Separator radius. For example, at 100 seconds residence time, the range of CO₂-to-feed slurry ratio of 250% (i.e., from 20% to 50%) only results in a difference of about 10% in the Separator Column radius.

Figure 6.2-5. Separator Radii Vs. Residence Time

The Separator radius is highly dependent upon the concentration of coal in the feed slurry. In Figure 6.2-6, the Separator radius increases by about 50% as the coal concentration in the feed slurry decreases from 30% to 10%.

The results of this study indicate that the CRU can be operated at a capacity of 45.4 kg/hr (100-lb/hr) and a Separator residence time of 100 seconds if the coal concentration in the feed slurry is 30%. However, since the design objective of the Continuous Unit is a clean coal capacity of 22.7 kg/hr (50-lb/hr), these results indicated that the Continuous Research Unit could be operated at this capacity without constructing a new system. Therefore, the proposed Continuous System was not required. In order to provide the capacity for longer residence times and lower coal concentrations in the slurry, a 15.24 cm (6-inch diameter) column was designed and constructed for the 22.7 kg/hr (50-lb/hr) capacity experiments. This column will provide an increase of more than a factor of two in residence time, compared to the 10.2 cm (4-inch) diameter column in the Continuous Research Unit.

Figure 6.2-6. Separator Radii Vs. CO₂/Slurry Ratio

7.0 CONCEPTUAL PLANT DESIGN

Three coal beneficiation plants were conceptually designed. Two plants use the LICADO process to clean "Run of Mine" coal while the third plant processes the residual coal in the waste stream from a mine mouth coal washing plant or from a waste pond.

Most effort was applied to the LICADO Proof-of-Concept (POC) plant, operation of which will supply scaling factors, design, operating and maintenance information needed for extrapolation to a large plant. This plant was developed in the most detail, since its construction is planned for the next phase of the LICADO process development.

A commercial 181 metric ton/hr (200 tons/hr) LICADO plant was conceived, roughly sized, and used to establish a budgetary cost estimate for the economic evaluation. This site plant will supply fuel for a 500 MWe generating plant.

The third, waste stream recovery plant, processes 45 metric tons/hr (50 tons/hr) using CO_2 to agglomerate coal fines in the waste of a washing plant stream or fines pumped from a waste pond. In this process, the agglomerated coal is recovered from the water phase by screening. A budgetary cost estimate of this plant was developed and used in the economic evaluations.

7.1 Proof-of-Concept Plant

Systems and components for a plant having the capacity to produce 0.91 metric ton (1 ton/hr) of clean coal provide a realistic first step scale-up from laboratory data and operation to the final commercial plant. Design and fabrication problems of components and systems are representative of those which will be encountered in a larger plant. Design, construction, and operation of the POC plant will provide system data, component and equipment design information, component scaling criteria, and operating and maintenance experience required for a pilot plant of approximately 45 metric tons/hr (50 tons/hr).

Experience will be obtained on the following plant operations and their subsystems:

- Coal Preparation: Preliminary cleaning to remove sand and other debris, grinding to a size of 200 mesh (85-90%), adding water to form the optimum slurry concentration.
- Separation: High pressure slurry pumps, CO₂ injection pumps, mixing and separation columns.
- Product Recovery: Clean coal product separation, CO₂ recycle, recovery of desorbed gaseous CO₂ from product, depressurization of product stream.
- Waste Treatment: Recovery of CO₂ from waste stream, separation of water and recycle to slurry subsystem, dewatering of waste solids, disposal of waste solids.
- Product Handling: Sampling, weighing, and packaging of product coal in a safe manner.

7.1.1 Requirements of the POC Plant

The plant has been designed to meet the following overall requirements:

- Production rate will be 0.91 metric ton/hr (1 ton/hr) of clean coal product.
- Feed material will be 5.1 cm (two-inch) top size bituminous coals, either Pittsburgh, Middle Kittanning, Upper Freeport, or Illinois No. 6.

- About 90% of the initial pyritic sulfur will be removed.
- The plant will operate using scaled versions of the same components, systems, and equipment to be installed in the commercial plant.
- Safe storage of the clean, powdered coal product will be provided using sealed, plastic lined drums with inert cover gas (argon).
- The waste produced by the process will be separated, the solids concentrated, and both liquids and solids will be disposed of in a lawful and safe manner.
- Sampling will be provided for the feed, product, and waste streams.
- A weighing and packaging station will be provided for shipment of clean coal. The components and system used in the POC plant will be different for this step in the process than that to be used in the commercial plant, which will pneumatically transport the product to storage silos. This operation will be performed in a CO₂ atmosphere as a precaution against coal dust explosions.

Figure 7.1.1-1 presents the stream flows and material balance, which is the basis for the system design and component sizing. A system computer model, discussed in Section 6, was developed to provide this information and to be used in scaling future larger plants. Input data used in the process flow sheet were based on the experimental data from the University

PRODUCTION RATE, LB/HR=2000.0								
	1 FEED	2 GRNDR	3 SLURRY	4 MIXER	5 CO2 RCY	6 SEP PR	7 SEP RF	8 CYL OV
RAW COAL	.3012E+04	.3012E+04	.3012E+04	.3012E+04		.2000E+04	.3012E+03	.7890E+02
CLN COAL							.5723E+05	
WATER	.2229E+02	.5666E+05	.5723E+05	.5723E+05	.1145E+03	.2997E+05	.1506E+03	.1948E+05
CO2-llq				.3012E+05	.3012E+05	.2630E+00		
CO2-gas								
ASH	.7349E+03	.7349E+03	.7349E+03	.7349E+03		.6614E+02	.6614E+03	
SULFUR	.4337E+02	.4337E+02	.4337E+02	.4337E+02		.1366E+02	.2819E+02	
	9 PRODUCT	10 FLTR LIQ	11 REFUSE GAS	12 PROD GAS	13 COMPRESS	14 REFUSE	15 RECYL WTR	16 MK UP WTR
RAW COAL	.2000E+04	.2630E+01				.2934E+03		
CLN COAL								
WATER	.1003E+01	.2098E+02				.5711E+03	.5666E+05	.5721E+03
CO2-llq		.1049E+05			.5730E+02		.1491E+03	
CO2-gas	.2630E+00		.5711E+02	.2630E+00		.1506E+01		
ASH	.6614E+02					.6614E+03		
SULFUR	.1366E+02					.2819E+02		

CC880608-2C

Figure 7.1.1-1. LICADO Plant Simulation, Upper Freeport Coal

of Pittsburgh Variable Volume Batch Tests and Continuous Tests. These input data were:

Slurry Concentration, % Solids. 10

Residence Time in Separator, minutes. . . . 5

CO₂ to slurry ratio (dimensionless. 0.5

Design Basis Coal. Upper Freeport

Upper Freeport coal was selected as the design basis coal, since it has the largest ash content. Therefore, Upper Freeport coal requires the maximum feed rate which must be processed to yield the required product rate and results in the largest plant components.

7.1.2 Process Consideration

Investigation of methods, consultation services, and equipment supplier discussions were considered in selecting processes or components for the system. At the beginning it appeared that there were various ways to accomplish a desired condition. However, upon examination, the choices were reduced because of previously experienced operating problems, economics, or safety. The resulting design is considered to produce an economical product from a plant which is easily operated and safe to the environment, community, and plant personnel.

Decisions were made on 1) the coal feed preparation method, 2) product recovery (coal/CO₂ separation), 3) maintaining the recycle water, pressurized or not.

7.1.2.1 Coal Feed Preparation

The coal preparation process has gone through three iterations. The first system used the standard atmospheric dry pulverizing which is generally

used throughout the coal industry. The coal prep subsystem contained a coal feed bin, crusher, conveyor, pulverizer, classifier, second conveyor, and fines storage hopper.

This system was chosen because it provides 200 mesh feed material with minimum capital expenditure, required 25% less power per ton to operate than a wet process, and the dry product flows relatively easily and could be transported and stored without much difficulty. However, after later data from the Coal Surface Control Project became available, it was decided to wet grind the coal feed to reduce surface oxidation and enhance CO_2 surface absorption during the contact process. From the safety aspect, wet grinding also reduces the potential for uncontrolled rapid fines oxidation which enhances the overall plant safety.

Flowability of wet coal fines are very poor; therefore, they are hydraulically transported at a solids concentration of 35 wt. % or less. The coal preparation system operates at about atmospheric pressure; and the transport water must be replaced by pressurized recycle process water which contains approximately 5% dissolved CO_2 . Thus, the majority of the transport water must be removed from the coal fines before they are charged to the process subsystem lock hopper.

During the conceptual plant design review, it was suggested that the best system for the feed size reduction would be to use a dry grinding system employing a CO_2 or N_2 atmosphere in the ball mill and maintaining that atmosphere to the lock hopper. In this way the fines would be dry, unoxidized, flow freely, transport easily, the correct slurry concentration could be simply obtained, the capital cost and reduced power consumption advantage would be regained, and plant safety would not be compromised. Later data from other programs indicate that dry grinding is detrimental to ash rejection, and therefore this option will not be pursued further.

7.1.2.2 Product Recovery (Coal/CO₂ Separation)

Cleaned coal is carried from the separator in the liquid CO₂ phase at approximately 5.86×10^6 Pascals (850) psig and 21.1°C (70°F). The next step must recover the coal from the liquid CO₂ while maintaining the CO₂ in the liquid state for recycling. To reduce system pressure and vaporizing the CO₂ would provide dry coal at atmospheric pressure; however, the CO₂ vented to the atmosphere would not be beneficial to the environment and would be prohibitively costly. To recompress the CO₂ for recycling would cost approximately one-third of the original cost; but because of the large volume, this process would still be too expensive. Therefore, CO₂/coal separation must be accomplished at CO₂ saturation pressure or greater.

Filter manufacturers were contacted to obtain performance and pricing information. Of those contacted, only two could supply a high pressure filter with the required capacity: Industrial Filter and Pump Mfg. Company and MEMTEC America Corporation. Both suppliers suggest the same type of filter, generally called a candle filter, in which tubular filtering elements are suspended within a pressure shell. The coal solids are deposited on the outside of the filtering tubes while the liquid flows through to the inside of the tube. All of the filter tubes are connected to a common header before the clean liquid exits the pressure vessel. The manufacturers use two different ways to recover the filter cake. One blows back from the filtrate side which dislodges the coal to the bottom of the vessel. The second manufacturer vibrates the coal cake from the filter tubes, and the coal drops to the vessel bottom. In both cases, the coal must be recovered from the vessel bottom.

The manufacturer of the least expensive filter, who also provided the dryer and more adaptable system, quoted 40 filter units at an uninstalled cost of approximately \$30 million to provide 200 ton/hr of coal product.

A system of pressurized settling tanks for concentrating the coal product, instead of filters, was considered. Plant capacity of 181 metric tons/hr (200 ton/hr) required a farm of 30, 2.14 m (7 ft.) diameter tanks. The filter cost was cut by approximately 1/3; however, the CO₂ recompression cost approached \$30/ton of product, which is too much.

Therefore, it appears that development of an efficient, high capacity, continuous filter system is required for a commercial plant. The continuous auger filter built by the University of Pittsburgh (Pitt) could be developed to fulfill the LICADO large plant requirement. However, during operation, the filter unit should be preceded by a cyclone to deslime the feed to the filter in order to reduce filter medium plugging.

For the POC plant, we have assumed that the auger type filter described in Section 7.1.5 will be developed for use at the commercial plant capacity.

7.1.2.3 Pressurized Recycle Water

A large volume of water is used to prepare the feed slurry in the LICADO process, therefore, requiring the water to be recycled both from an ecological and cost standpoint. During the reaction process, the water is intimately mixed with CO₂ at approximately 6.20×10^6 (900 psia) and 21.1°C (70°F) and becomes saturated at these conditions.

The solubilities of CO₂ in water are:

0.17% wt. at 1.01×10^5 (14.7 psia) and 21.1°C (70°F)

6.2% wt. at 6.21×10^6 Pascals (900 psia) and 21.1°C (70°F)

Should this water be allowed to return to an atmospheric holding pond from a pressurized refuse letdown tank, the lost CO₂ would amount to about \$96/ton of product. If the water were depressurized and the escaping CO₂ recompressed for recycling, the cost would be approximately \$32/ton of product. However, if the recycle water is maintained at 850 to 860 psia, the CO₂ cost is between 5 to 10 cents/ton of product; and

this is due to the CO_2 absorbed on the product and refuse and will always be lost no matter what method is used. Therefore, the LICADO plant is designed to operate with a pressurized recycle water system.

7.1.3 Plant Subsystems

The LICADO system is basically five subsystems integrated into a continuous operating plant which supplies cleaned fine coal for combustion, Figure 7.1.3-1. The plant is fully automated and is computer controlled. Subsystems are:

- Feed Coal Preparation
- Liquid CO_2 Processing
- Cleaned Coal Recovery
- Refuse Disposal
- Gaseous CO_2 Recycle
- Product Handling

The POC coal preparation subsystem reduces 5.1 cm (2 inch) top-size coal to 90% $\leq$ 200 mesh fines, which are used as feed stock to the LICADO plant. The subsystem can measure and control one ton per hour of coal as it is crushed to approximately 0.64 cm (1/4 inch) material, then wet ground to 200 mesh as feed to the slurry tanks. In the slurry tanks, pressurized water is added to the fines to obtain the correct slurry concentration. The slurry is continuously mixed to maintain a homogeneous feed. Slurry pumps take suction from the tanks and deliver a controlled slurry rate at an increased pressure of approximately 4.14×10^5 (60 psi) to the hydraulic mixer.

In the hydraulic mixer, liquid CO_2 is thoroughly mixed with the coal particles; and the mixture of coal- CO_2 -water is sent to the multi-stage separator to facilitate additional CO_2 contact and liquid phase separation. Here, the lighter CO_2 phase containing the clean coal particles rises to the top of the separator, while the heavier water phase with refuse sinks to the separator bottom.

UCADO, 1 TON/HOUR PROOF OF CONCEPT PIPING & INSTRUMENTATION DIAGRAM

CC-00000-10

Figure 7.1.3-1

In the next two operations, the coal product is recovered and packaged while the refuse is reduced to atmospheric conditions and prepared for waste disposal.

The coal in the liquid CO₂ phase is concentrated in a cyclone from around 6-1/2% solids to 16-1/2% solids before the coal product is stripped from the remaining CO₂ using a high pressure filter. The filter cake is reduced to atmospheric conditions, then is drummed for shipment. The drums will be provided with a plastic liner, and the drums will be filled with argon gas prior to sealing. The liquid CO₂ overflow from the cyclone and the filtrate from the filters is returned to the system pressurizer, from which it is recycled to the separator.

The refuse material (ash and pyritic sulfur) is concentrated through a cyclone from around 3-1/2% solids to an underflow of about 30 to 35% solids, and then allowed to settle from the water phase in a refuse letdown tank. The high pressure water from both the cyclone and the settled solids is sent to pressurized recycle water storage. The settled solids are extruded from the tank bottom into drums for refuse disposal.

Gaseous CO₂ from the product and refuse depressurization is accumulated, recompressed, cooled to liquid, and returned to the system for recycling.

The process operates at saturated CO₂ conditions of 21.1°C (70°F) and 5.88×10^6 Pascals (853 psia). Insulation and a CO₂ loop cooler maintain the system temperature at 21.1°C (70°F). A loop pressurizer through heating and cooling capability automatically maintains the required system pressure.

The CO₂/water liquid interface level in the separator is controlled through setting the flow rates of the inlet CO₂ and slurry to the mixer and controlling the outflow of the water/refuse from the separator

using the level signal. This also automatically establishes CO₂/coal flow from the separator. This control scheme is routinely used to control the interface in the Continuous Research Unit.

7.1.4 Instrumentation and Control System

The POC plant will be computer-controlled with operator attention in the control room and two operators in the plant to supply raw coal to the feed hopper, handle product and refuse drums, and survey equipment operations.

The control system computer will consist of an IBM PC/AT operating a multi-tasking version of DOS. The computer will be dedicated to the process control tasks necessary for the plant, with these functions taking precedence over the logging capabilities of the computer. Specifically, the system will have 640K memory with a floppy drive and a 20M hard drive. The hard drive will be used mainly to store data collected during plant runs. The computer will consist of plug-in boards in a standard PC/AT backplane encased in a rugged housing. The boards are identified below:

- 1) PC/AT Processor Card
- 2) 640K Memory Card
- 3) Disk Drive Controller Card
- 4) Graphics Controller Board
- 5) Digital I/O Board (24 Inputs)
- 6) Digital I/O Board (24 Outputs)
- 7) Analog I/O Board (16 Inputs)
- 8) Analog I/O Board (6 Inputs)

Several expansion slots will be left open for future requirements. The numerous different suppliers of these boards and the rapid growth of the market make the specific selection of the manufacturer unnecessary at this time. The final computer layout will not take place until the final design phase of the plant. In addition, the selection of a specific computer language (C, Basic, Fortran, etc.) to program functions will be delayed until a later date.

To properly isolate control system signals from the field devices, industry, standard I/O modules will be used. Signals to/from the computer I/O boards will be run through the modules for two purposes. First, to ensure optical isolation from the sensitive computer boards so that a failure or overvoltage does not do serious damage to the control system. Second, to provide a means to condition the computer board signals to the levels necessary for field activation of valves/motors.

Although a layout sketch of the control system was not undertaken at this time, a process I/O list for the control system was prepared and is shown in Table 7.1.4-1. This listing describes the process control inputs and outputs of the computer and does not cover the operator inputs (emergency stop, start, stop, continue buttons, etc.) and outputs (annunciators, control panel lights, etc.), which will be configured during the final design stage.

The Piping and Instrumentation Diagram (P&ID) is shown as Figure 7.1.3-1. The circle and bar symbol is used for functions included in the control room. The plain circle symbol for field mounted devices. The dashed line with an arrow symbol is used to indicate that the measurement/function is either input to or generated from the control system. The circle in a box symbol indicates a signal generated by the control system computer for the purpose of process control. No other attempt will be made, on the P&ID, to show the interaction between plant systems that take place in the control system computer. These interactions will be developed and documented later in the form of microprocessor software.

A Measurement Requirements List (MRL), shown in Table 7.1.4-2, was generated based on the preliminary P&ID. This listing defines the function or purpose for which each of the measurements shown on the P&ID is to be used. Each process measurement point shown on the P&ID is listed with a short word description of the parameter and the number of any valve or

CONTROL SYSTEM

<u>DIGITAL INPUTS</u>			<u>ANALOG INPUTS</u>		
<u>Description</u>	<u>Level</u>		<u>Description</u>	<u>Level</u>	<u>Qty</u>
1) Lo Separator Press.	115 VAC		1) Level Xmitter for Separator	4-20 mA	
2) Hi Separator Press.	115 VAC		2) Level Xmitter for CO ₂ Pressure Tank	4-20 mA	
3) Lo Depressurizer Tank #1 Pressure	115 VAC		3) Temp. for CO ₂ Pressure Tank		
4) Hi Depressurizer Tank #1 Pressure	115 VAC		4) Water to Slurry Tank Flow Rate	4-20 mA	
5) Lo Depressurizer Tank #2 Pressure	115 VAC		5) Slurry to Mixer Flow Rate	4-20 mA	
6) Hi Depressurizer Tank #2 Pressure	115 VAC		6) Liquid CO ₂ to Mixer Flow Rate	4-20 mA	
7) Lo Refuse Letdown Tank #1 Pressure	115 VAC		7) Coal to Slurry Tank Flow Rate	4-20 mA	2
8) Hi Refuse Letdown Tank #1 Pressure	115 VAC		8) Water to Coal Crusher Flow Rate	4-20 mA	
9) Lo Refuse Letdown Tank #2 Pressure	115 VAC		9) Level Xmitter for Recycle Water Tank	4-20mA	
10) Hi Refuse Letdown Tank #2 Pressure	115 VAC		10) Level Xmitter for Slurry Tank	4-20mA	3
11) Lo CO ₂ Tank Press	115 VAC		<u>ANALOG OUTPUTS</u>		
12) Hi CO ₂ Tank Press	115 VAC		<u>Description</u>	<u>Level</u>	
13) Lo Filter #2 Dif. Pressure	115 VAC		1) Temp. Control for CO ₂ Pressure Tank	0-5 V	
14) Hi CO ₂ Tank Press Pressure	115 VAC		2) Separator Interface Level Control Valve	4-20 mA	
15) Lo Filter #2 Dif. Pressure	115 VAC		3) Water to Slurry Tank Flow Control Valve	4-20 mA	
16) Hi Filter #2 Dif. Pressure	115 VAC		4) Slurry Pump Motor Speed Control	0-5 V	
17) CO ₂ Accumulator Pressure Switch (Lo)	115 VAC		5) Liquid CO ₂ to Mixer Flow Control Valve	4-20 mA	
18) CO ₂ Accumulator Pressyre Switch (Hi)	115 VAC		6) Coal to Slurry Tank Flow Control Valve	4-20 mA	6
			7) Water to Coal Crusher	4-20mA	

TABLE 7.1.4-1
CONTROL SYSTEM
DIGITAL OUTPUTS

<u>Description</u>			<u>Level</u>	<u>Qty</u>
1)	Depressurizer to Coal Bin Valve	(HS-01)	115 VAC	
2)	Depressurizer to Coal Bin Valve	(HS-02)	115 VAC	
3)	Filter #1 to Depressurizer Valve	(HS-03)	115 VAC	
4)	Filter #2 to Depressurizer Valve	(HS-04)	115 VAC	
5)	Filter #1 CO ₂ Recycle Line Valve	(HS-05)	115 VAC	
6)	Filter #2 CO ₂ Recycle Line Valve	(HS-06)	115 VAC	
7)	Cyclone to Filter #1 Valve	(HS-07)	115 VAC	
8)	Cyclone to Filter #2 Valve	(HS-08)	115 VAC	
9)	Depressurizer CO ₂ Recycle Valve	(HS-09)	115 VAC	
10)	Depressurizer CO ₂ Recycle Valve	(HS-10)	115 VAC	
11)	Refuse Tank #1 Water Drain Valve	(HS-11)	115 VAC	
12)	Refuse Tank #2 Water Drain Valve	(HS-12)	115 VAC	
13)	Seperator to Refuse Tank #1 Valve	(HS-13)	115 VAC	
14)	Seperator to Refuse Tank #2 Valve	(HS-14)	115 VAC	
15)	Refuse Tank #1 CO ₂ Recycle Valve	(HS-15)	115 VAC	
16)	Refuse Tank #2 CO ₂ Recycle Valve	(HS-16)	115 VAC	
17)	Water Make Up Valve	(HS-17)	115 VAC	
18)	Water Tank to Slurry Pump Valve	(HS-18)	115 VAC	
19)	CO ₂ Makeup Line Solenoid Valve	(HS-19)	115 VAC	
20)	CO ₂ Tank Cooling Solenoid Valve	(HS-20)	115 VAC	
21)	Water to Slurry Tank	(HS-21)	115 VAC	3
22)	Slurry Tank to Slurry Pump Valve	(HS-22)	115 VAC	3
23)	CO ₂ Compressor Motor Starter	(HS-23)	115 VAC	

TABLE 7.1.4-2
MEASUREMENTS REQUIREMENTS LIST

DEVICE	DESCRIPTION	CONTROL	INDICATE	ALARM	TYPE	OUTPUT	RANGE	RESPONSE	ACCURACY
PT01	SEPERATOR TANK PRESSURE	INTERLOCK/ ALARM	LOCAL REMOTE		DIAPHRAGM/ CAPACITIVE	4-20mA	0-1000 PSIG		
PT02	DEPRESSURIZING TANK #1 PRESSURE	INTERLOCK/ ALARM	LOCAL REMOTE		DIAPHRAGM/ CAPACITIVE	4-20mA	0-850 PSIG		
PT03	DEPRESSURIZING TANK #2 PRESSURE	INTERLOCK/ ALARM	LOCAL REMOTE		DIAPHRAGM/ CAPACITIVE	4-20mA	0-850 PSIG		
PT04	REFUSE LETDOWN TANK #1 PRESSURE	INTERLOCK/ ALARM	LOCAL REMOTE		DIAPHRAGM/ CAPACITIVE	4-20mA	0-200 PSIG		
PT05	REFUSE LETDOWN TANK #2 PRESSURE	INTERLOCK/ ALARM	LOCAL REMOTE		DIAPHRAGM/ CAPACITIVE	4-20mA	0-200 PSIG		
PT06	CO ₂ PRESSURE TANK PRESSURE	INTERLOCK/ ALARM	REMOTE		DIAPHRAGM/ CAPACITIVE	4-20mA	0-1000 PSIG		
PDT01	FILTER #1 DIFFERENTIAL PRESSURE	INTERLOCK/ ALARM	REMOTE		DIAPHRAGM/ CAPACITIVE	4-20mA	0-25 PSID		
PDT02	FILTER #2 DIFFERENTIAL PRESSURE	INTERLOCK/ ALARM	REMOTE		DIAPHRAGM/ CAPACITIVE	4-20mA	0-25 PSID		
LT02	CO ₂ PRESSURE TANK LEVEL (HV19)	REMOTE	REMOTE		CAPACITIVE INTERFACE	4-20mA			
TE01	CO ₂ PRESSURE TANK TEMP. (HV20,TIC01)	REMOTE	N/A						
PS01	H1/LO PRESSURE SWITCH CO ₂ ACCUMULATOR (HS21)	REMOTE	LOCAL		DIAPHRAGM	DIGITAL			
LT01	SEPERATOR TANK INTERFACE LEVEL (FCV-02)	REMOTE	REMOTE		CAPACITIVE INTERFACE	4-20mA			
FE01	WATER TO SLURRY TANK FLOW (FCV-01)	REMOTE	REMOTE		TURBINE FLOW METER	4-20mA	0-100 GPM		
FE02	SLURRY TO SEPERATOR TANK FLOW (MC-01)	REMOTE	REMOTE		FULL PORT MASS FLOW METER	4-20mA	0-100 GPM		
FE03	WATER TO COAL CRUSHER FLOW (FCV-03)		REMOTE		TURBINE FLOW METER				
FE04	LIQUID CO ₂ TO MIXER FLOW (FCV-04)	REMOTE	REMOTE		TURBINE FLOW METER	4-20mA	0-100 GPM		
LT03	RECYCLE WATER TANK LEVEL (HS24)	REMOTE	REMOTE		FLOAT/OTHER	4-20mA			
LT04	SLURRY TANK LEVEL (HV)								
FE05	COAL TO SLURRY TANK FLOW (FCF-05)		REMOTE						

motor controlled by the measurement shown in parentheses. The location and/or purpose of the control, indication, and alarm requirements is shown. Local and remote entries refer to field mounted devices and control room functions, respectively. The type of process instruments to be used has been identified along with the output signal and range. When more information is available, the response time and accuracy requirement of the parameter measurement will be added.

A Control Valve List (CVL), shown in Table 7.1.4-3, was generated based on the P&ID. This listing defines the valve number, type, size, and control system requirements. Each control valve is identified with a valve number and a description. An attempt was made to standardize the valve types and sizes in order to simplify the purchasing and maintenance of the system. The pipe size and pressure requirements are shown. This list includes only valves controlled by signals generated in the control system computer. The control column shows the type of computer signal (digital or analog) the valve requires. As would be expected, a digital signal commands the valve either to open or close; while an analog signal is used to proportionally control the valve stem position. At this time, the digitally-controlled valves use motor actuators (air actuators w/solenoid control is another option being considered); and the analog valves use air-operated diaphragm actuators.

7.1.5 Description of POC Plant

For the purposes of this design study, the Proof-of-Concept Plant was located in the GPL-1 Building at the Westinghouse Waltz Mill site.

A preliminary concept of the plant was arranged within the GPL-1 building which will require an additional structure on its roof to accommodate the height of the pressurized coal/water slurry feed system, separator column, and system pressurizer. Also, a new extension is required to cover the coal weight feeder, crusher, and part of the ball mill.

TABLE 7.1.4-3
CONTROL VALVE LIST

VALVE #	DESCRIPTION	PIPE SIZE	CONTROL	PRESSURE	TYPE	ACTUATOR
HS-01	Depressurizer to Coal Bin Valve	2 inch	Digital	850 PSIG	Full Port Ball Teflon Seals	Electric Motor
HS-02	Depressurizer to Coal Bin Valve	2 inch	Digital	850 PSIG	Full Port Ball Teflon Seals	Electric Motor
HS-03	Filter #1 to Depressurizer Valve	2 inch	Digital	850 PSIG	Full Port Ball Teflon Seals	Electric Motor
HS-04	Filter #2 to Depressurizer Valve	2 inch	Digital	850 PSIG	Full Port Ball Teflon Seals	Electric Motor
HS-05	Filter #1 CO ₂ Recycle Line Valve	2 inch	Digital	850 PSIG	Full Port Ball Teflon Seals	Electric Motor
HS-06	Filter #2 CO ₂ Recycle Line Valve	2 inch	Digital	850 PSIG	Full Port Ball Teflon Seals	Electric Motor
HS-07	Cyclone to Filter #1 Valve	2 inch	Digital	850 PSIG	Full Port Ball Teflon Seals	Electric Motor
HS-08	Cyclone to Filter #2 Valve	2 inch	Digital	850 PSIG	Full Port Ball Teflon Seals	Electric Motor
HS-09	Depressurizer CO ₂ Recycle Valve	1 inch	Digital	850 PSIG	Full Port Ball Teflon Seals	Electric Motor
HS-10	Depressurizer CO ₂ Recycle Valve	1 inch	Digital	850 PSIG	Full Port Ball Teflon Seals	Electric Motor
HS-11	Refuse Tank #1 Water Drain Valve	2.5 inch	Digital	200 PSIG	Full Port Ball Standard Seals	Electric Motor
HS-12	Refuse Tank #2 Water Drain Valve	2.5 inch	Digital	200 PSIG	Full Port Ball Standard Seals	Electric Motor
HS-13	Seperator to Refuse Tank #1 Valve	2.5 inch	Digital	850 PSIG	Full Port Ball Teflon Seals	Electric Motor
HS-14	Seperator to Refuse Tank #2 Valve	2.5 inch	Digital	850 PSIG	Full Port Ball Teflon Seals	Electric Motor
HS-15	Refuse Tank #1 CO ₂ Recycle Valve	1 inch	Digital	850 PSIG	Full Port Ball Teflon Seals	Electric Motor
HS-16	Refuse Tank #2 CO ₂ Recycle Valve	1 inch	Digital	850 PSIG	Full Port Ball Teflon Seals	Electric Motor
HS-17	Water Make Up Valve		Digital	850 PSIG		
HS-18	Water Tank to Slurry Pump Valve	1.5 inch	Digital	200 PSIG	Full Port Ball Standard Seals	Electric Motor
HS-19	CO ₂ Makeup Line Solenoid Valve	0.5 inch	Digital	850 PSIG	CO ₂ Service Solenoid	Solenoid
HS-20	CO ₂ Tank Cooling Solenoid Valve	0.5 inch	Digital	100 PSIG	Low Pressure Solenoid	Solenoid
HS-21	Water to Slurry Tank		Digital	850 PSIG		
HS-22	Slurry Tank to Slurry Pump Valve	1.5 inch	Digital	200 PSIG	Full Port Ball Standard Seals	Electric Motor

TABLE 7.1.4-3
CONTROL VALVE LIST (continued)

VALVE #	DESCRIPTION	PIPE SIZE	CONTROL	PRESSURE	TYPE	ACTUATOR
FCV-01	Water to Slurry Tank Flow Valve	2.5 inch	Analog	100 PSIG		Pneumatic/ Diaphragm
FCV-02	Seperator Level Control Valve	2.5 inch	Analog	850 PSIG	Right Angle	Pneumatic/ Diaphragm
FCV-03	Water to Coal Crusher	2 inch	Analog	40 PSIG		
FCV-04	CO ₂ to Mixer Flow Control Valve	2 inch	Analog	850 PSIG		Pneumatic/ Diaphragm
FCV-05	Wet Coal to Slurry Tank		Analog			

The plant area occupies approximately 371.6 m² (4000 ft²), not including a separate control room which is elevated 3.65 m (12 feet) and located adjacent to the operating area. The control room is air conditioned, which precludes computer and instrumentation contamination with coal dust.

Arrangement is such that the product, refuse, and coal feed are serviced by a fork lift or front loader from the site materials handling area adjacent to the building roller door. The bulk CO₂ storage tank and the raw coal storage are located outside the building. System makeup CO₂ is piped to the pressurizer from the tank. Additional building ventilation will be installed to prevent CO₂ buildup should a major CO₂ leak occur.

The plant is designed for operation by three technicians. One will be stationed in the control room to monitor operation, while a second will tend the raw coal feed. The product drum and refuse drum removal in the material handling area will require a third operator. Also, a shift supervisor and instrumentation specialist are required.

The following discussion of the plant refers to the components and their arrangement, as shown in the P&I diagram (Figure 7.1.3-1), Preliminary Plant Arrangement Plan (Figure 7.1.5-1) and Elevations (Figure 7.1.5-2), and the Grinding Systems Elevation (Figure 7.1.5-3).

Feed Coal Preparation

Feed Coal Preparation consists of a coal bin, crusher, weight indicator, wet grinder, slurry sump, coal/water slurry pumps, and the appropriate valves, cyclone classifier, feed storage, instrumentation, and controls. Here the coal is ground to 200 mesh for feed supply.

The coal/water slurry feed system employs pressurized recycle water. Maintaining the recycle water at high pressure reduces the substantial amount of absorbed CO₂ lost if the water were decompressed.

LICADO, 1 TON/HOUR PROOF OF CONCEPT PLANT PRELIMINARY PLANT ARRANGEMENT, WALTZ MILL SITE

CC890109-J

Figure 7.1.5-1

LICADO, 1 TON/HOUR PRO
PRELIMINARY PLAN
WALTZ MI

SECTION

OF OF CONCEPT PLANT
ARRANGEMENT,
L SITE

Figure 7.1.5-2

Figure 7.1.5-3. Grinding Systems Elevation

Some components of the pressurized water feed system require multiples based on plant requirements of 0.91 metric ton (1 ton/hr) coal feed slurry concentration of 10% weight solids, 6.89×10^6 Pascals (1000 psi) pressure, and vessel fabrication constraints of keeping the wall thickness between 2.54 to 5.08 cm (1 to 2 inches).

A bucket lift delivers the fine coal to the Coal Feed Receiver which is at atmospheric pressure. Coal passes into one of two Lock Hoppers through a pipe and ball valve. The Lock Hoppers hold a 40 minute feed coal supply. Each may feed coal to any of three slurry tanks which hold a 20 minute slurry supply at about 5.79×10^6 Pascals (840 psig). Mechanical mixers keep the coal/water slurry homogeneous in the on-stream tank, while the slurry pump drains the tank and supplies the hydraulic mixer.

Liquid CO₂ Processing

The liquid CO₂ Processing Loop pump circulates subcooled liquid CO₂ at approximately 5.93×10^6 Pascals (860 psig) and 21.1°C (70°F) through the hydraulic mixer, CO₂/water separator, CO₂ clean coal filter, and CO₂ loop cooler. Insulation covering the subsystem in conjunction with the CO₂ cooler allows loop temperature control. A pressurizer maintains CO₂ saturation pressure at about 5.79×10^6 Pascals (840 psig) through a temperature control system.

In the Hydraulic Mixer, liquid CO₂ first contacts the coal/water slurry, as shown in Figures 7.1.5-4 and 7.1.5-5. Coal/water slurry enters along the axis of the mixer pipe while the liquid CO₂ is injected into the water slurry through a multiholed nozzle. The 73 3.1 mm (one-eighth inch) diameter streams degrade to droplets due to the drag created on the CO₂ stream by the difference in velocities of the coal/water and liquid CO₂. This mixture of coal/water/CO₂ droplets flows through a series of orifice disks which further promote turbulence and thoroughly mix the stream. Orifice plates are of two patterns and alternate along the length of the mixer. The first plate has four 1.91 cm (3/4 inch) holes, and the second plate has a 6.35 cm (2-1/2 inch) wide cross.

SECTION A-A (F8)

SECTION C-C (B5)
TYP PATTERN FOR ROW B

SECTION B-B (C5)
TYP PATTERN FOR ROW A

HYDRAULIC LINE MIXER

Figure 7.1.5-4

DON-1

Figure 7.1.5-5. Mixer Orifice Details

Figure 7.1.5-6 is the preliminary design and layout drawing for the integral multistage separator. The unit has four separation stages within one pressurized column. The separator column has a pressure shell of 61 cm (24 inch) O.D. Schedule 40, 304 stainless steel pipe 6.71 m (22 feet) long. The column bottom is a steep conical section with a center discharge to facilitate fluid flow with a high solids concentration.

The coal/CO₂ exits the column through two diametrically opposed pipes 50.8 cm (20 inches) below the unit top. Water containing refuse and pyritic sulfur issues from the bottom. The raw coal/water/CO₂ feed nozzle is approximately 1/3 the distance up the column.

The top of the column is closed by a 600 lb. blind flange from which all of the column internals are supported or pass through. All of the internals are removed from the column when the top flange is raised.

Each stage consists of a conical flow tube through which the mixture of coal/water/CO₂ is accelerated by a propeller at the lower and larger diameter end. Also, attached to the lower or base end of the conical flow tube is a tubular ring with eight small holes directed toward the center of the cone and propeller. Either CO₂ or water may be injected through these holes to enhance coal/refuse separation. The mixer velocity, as it passes through the conical flow tube, will be increased by four items and be discharged at 45° toward the column periphery. The heavier refuse/water will travel further and concentrate near the column wall, while the lighter coal/CO₂ will remain nearer the center of the column. Stages are separated by a quiescent zone.

All mixing blades may be positioned along a single central shaft driven from above through a magnetic coupling to the externally mounted motor.

CC900201-1

Figure 7.1.5-6. Integral Multistage Separator

Cleaned Coal Recovery

Cleaned coal and CO₂ exit the top of the separators (approximately 12% wt. solids). The coal/CO₂ slurry flows through a cyclone into the auger filters (Figure 7.1.5-7), operating at saturated conditions. The feed slurry liquid level is maintained in the filter medium auger leg while saturated vapor is above the liquid in the remaining auger leg and in the vertical coal receiver leg. The auger is constantly turning at 1 to 3 RPM, stripping coal from inside the filter medium and delivering it to the top of the unit where it falls into the coal receiver leg. The coal in each filter is cyclically discharged into the Product Collection Vessel (Depressurizer Tank), in which it is depressurized. The CO₂ goes to a CO₂ Accumulator while the clean coal is packaged in drums; however, in a commercial operation, the product will be pneumatically transported to large storage silos.

Filtrate (liquid CO₂) from the filters is delivered to the CO₂ loop pressurizer.

Refuse Disposal

Refuse and water are constantly drawn from the bottom of the separator, at about 3-4% wt. solids concentration, through a level control valve and into a cyclone separator within the Refuse Letdown Tank. Water with absorbed CO₂ vents at the top of the cyclone and concentrated refuse at the bottom. Expanded CO₂ vents to the recycle subsystem while the water is decanted from over the refuse and passes to the pressurized recycle water tank. While the first tank is filling, refuse settling, and water being decanted, the second is discharging refuse sludge from the bottom for disposal.

Both the product and refuse tanks are duplicated to assure continuous plant operation by switching from Tank 1 after filling to Tank 2.

Figure 7.1.5-7. Continuous Auger Filter

Gaseous CO₂ Recycle

In this and larger plants, some CO₂ will accompany the refuse and product in the depressurizing operation. Economics require that this gaseous CO₂ be compressed and recycled to the liquid CO₂ loop. The gaseous CO₂ subsystem contains filters, accumulator, compressor, and after-cooler.

7.1.6 Plant Operation

Run of mine coal is loaded into the hopper outside the building and is fed onto a weigh feeder inside the building at the rate of 1 ton/hour. The feeder conveys the raw coal to a crusher where it is reduced to 1/4 inch and smaller. A ball mill wet grinds the 0.63 cm (1/4 inch) coal to a 200 mesh top size and discharges it into a sump from which a slurry pump delivers the coal fines to a wet cyclone classifier. The overflow from the cyclone carries the 200 mesh and smaller particles to feed storage, while the cyclone underflow returns oversized material to the ball mill.

From the feed storage, where the excess water drains back to the atmospheric recycle water tank, a bucket conveyer lifts the 200 mesh top size coal to the top of the building and deposits them into the feed receiver. The feed receiver supplies two lock hoppers, each sized to hold a 40 minute supply. Ball valves isolate the feed receiver from the lock hoppers to allow pressurization of the lock hoppers with CO₂ saturated vapor. From this point, the slurry tank, refuse letdown tank, coal depressurizer, and recycle water tank are interconnected with a pressure equalization system, which is connected to the vapor space in the pressurizer and maintains these vessels at CO₂ saturation pressure of 5.79×10^6 Pascals (840 psig) at 21.1°C (70°F). However, each tank may be isolated from the equalization system, if desired.

There are three slurry tanks, each holding a 20 minute process feed supply. While Tank 1 is on-stream, Tank 2 is mixing and Tank 3 is being filled. To fill a tank, water is first filled to a prescribed level, the stirrer turned on, and then the contents of a lock hopper is deposited into the slurry tank. The concentration may be changed by controlling the amount of coal added.

A slurry pump increases the feed pressure to approximately 6.21×10^6 Pascals (900 psig) to supply the hydraulic mixer. Liquid CO_2 is injected into the slurry within the mixer. The mixer has a series of eight orifice plates through which the coal/water/ CO_2 mixture passes. Pressure drop through the mixer is calculated to be approximately 3.44×10^5 Pascals (50 psi).

The mixture enters the separator which has four stages, each of which separate and concentrate the coal/ CO_2 and water/refuse phases of the previous stage.

The coal/ CO_2 phase concentrates near the center of the column and exits the unit at the top, while the heavier water/refuse phase accumulates at the column periphery and exits at the bottom of the column.

Slurry pump flow rate plus the CO_2 flow rate give the total separator "in" flow, while the "out" flow is balanced by control of the water/refuse stream exit rate through the bottom CO_2 /water interface level indication. Thus, the remaining coal/ CO_2 "out" flow is automatically established.

Water, refuse, and absorbed CO_2 are drawn from the bottom of the separation vessel and into the liquid cyclone within one of the two Refuse Letdown Tanks. Concentrated solids exit from the bottom of the cyclone, while water and absorbed CO_2 vent from the top. Solids will concentrate in the tank bottom while water is decanted from over the refuse and

returned to the pressurized recycle water tank. When a prescribed solids level is reached in the on-line tank, it will be isolated from the system; and flow will be diverted to the second tank. CO_2 will be vented to the accumulator from the first tank to reduce its pressure to about 1.72×10^5 Pascals (25 psig). This pressure will be used to force the refuse sludge out of the vessel into disposal drums.

At some time during operation of the plant, runs will be made to investigate continuous venting of refuse sludge and recycle water from one tank only; thus, the second tank will be held in reserve.

The same procedure will be used for the coal depressurizing tanks.

The product stream (~ 12% solids, coal/ CO_2) from the top of the separator is concentrated in a cyclone to about 25% solids before it enters one of two auger filters. The second filter is a standby unit. Any coal fines in the overflow are recirculated to the separator with the CO_2 flow.

Coal cake is delivered by the auger to the receiver leg and flows through into the depressurizer tank. At a prescribed level in the depressurizer tank, it is isolated from the system; CO_2 is vented to the accumulator until the tank has 10 psig remaining. Then this pressure is used to fill the product drums. Meanwhile, the coal filter cake continues to fill the receiver leg of the filter until the emptied receiving tank is put back into the system, at which time the cycle is repeated.

7.1.7 Required Development

Two areas which require development for success of the LICADO process are, 1) an efficient means for separating the two liquid phases (CO_2 and water), and 2) recovery of product from the process. These are presently

being examined in the Bench Research Unit and the Continuous Research Unit. Dewatering of the refuse is required also; however, conventional dewatering technologies will be applied.

7.1.7.1 Separator

The conceptual design for the separator should be tested in the Continuous Research Unit to demonstrate its expected performance improvement compared to a single-stage separator. The effectiveness of the design and parametric variation should be assessed before the 0.9 metric ton/hr (1-ton/hour) unit is finalized. Separator parameters such as mixture residence time, effect of fluid velocities within the separator; mechanical mixer speed, blade placement and relative size; necessity for the mechanical mixer; need for and location of CO₂ injection ports in the separator; need for and location of water injection ports; and optimum location of coal CO₂/water ash interface will be investigated.

The preliminary design for these components will be updated, based on the test results from the scaled unit during final design.

7.1.7.2 Product Recovery (Coal/CO₂ Separation)

High pressure filtration is necessary to remove the liquid CO₂ from the cleaned coal; and to date, only multiple candle-type filters cycling in a batch mode will provide the required capacity for a commercial plant. However, these candle filters are very expensive and potentially could require extensive maintenance. Therefore, it is necessary that a continuous high pressure filter be developed. The auger filter, Figure 7.1.5-7, is a good candidate for further investigation. However, if difficulty is encountered during scale-up to a commercial size, an alternative would be a moving belt filter within a pressure housing similar to Figures 7.1.7.2-1 and 7.1.7.2-2.

CC890831-1

Figure 7 1.7 2-1. Continuous Filter - Pressurized

CC890831-2

Figure 7.1.7.2-2. Sections A-A and B-B

7.1.8 Conceptual Design Review of POC Plant

A conceptual design review was held on July 13, 1989 at the Westinghouse Large, PA site. The review material presented was a condensed version of Section 7.1 of this report, "Proof-of-Concept Plant (1 Ton/Hour)."

The significant design modifications resulting from the review are:

- Dry grind the coal in a CO₂ atmosphere.
- Add a "Super Scalper" to remove slate and rock from the ROM coal before it is ground.
- Specify apex of cyclone to prevent plugging by coal particles. The apex diameter should be at least three times the largest particle diameter.
- Provide for individual operation of subsystems to check out and start-up the plant. These modifications will be implemented during the preliminary design phase.

A summary discussion of the significant questions is presented in Appendix 7.1.8.

7.2 Commercial Plant (200 Ton/Hour)

A commercial size plant was conceived to provide 181 metric ton/hr (200 ton/hour) of product feed for a 500 MW_e utility. This concept was used to provide a budgetary capital cost estimate that was input to the economic evaluation presented in Section 8.0.

The system and flow schematic for the commercial plant was based on the 0.9 metric ton/hr LICADO Proof-of-Concept system. From the 181 metric ton/hr schematic and material balances, plant components were sized; and a budgetary capital cost estimate was developed.

7.2.1 Requirements

The plant is designed to meet the requirements and assumptions which follow:

- The production rate is 181 metric tons/hr for cleaned coal (90% $\leq$ 200 mesh)
- Feed material ROM bituminous coal from Upper Freeport seam
- Cleaned coal ash content will be less than 2.0%
- Approximately 90% of the pyritic sulfur will be removed
- Feed is available in feed hopper, and product is ready for transport
- Feed coal/water slurry 20% wt. solids
- CO₂ slurry ratio is 0.5
- Coal residence time in separator is five minutes
- Utilities are site available

- All process wetted containment material is 304 stainless steel
- Vessel wall thickness is ≤ 5.72 cm (2-1/4 inches)
- Based on the discussion previously presented in Section 7.1.2.2, it is assumed that the auger filter is developed; and this component is used in this plant concept

7.2.2 Discussion of System (Figure 7.2.2-1)

The LICADO process system is basically the same as discussed in Section 7.1, with the exception of the feed coal preparation step. In the commercial plant the coal size reduction ball mill is air swept; and air is used to transport the coal fines to the classifier and bag house. This will be modified by replacing with a closed gaseous CO₂ system, which may be accomplished at minimal cost.

Also, this plant's separator allows refuse settling and concentration to approximately 19% solids in the bottom of the separator, with pressurized water being decanted for recycle before the refuse slurry exits to the refuse cyclone for further concentration. In the POC plant, refuse exits the separator at about 3-1/2% solids as it enters the cyclone. The assumption for this plant is that separator development will allow this approach.

7.2.3 Description of Plant

Raw coal is processed through one of five 49.5 metric ton/hr (55-ton/hour) feed preparation stations. From the rail car it passes through a coal hopper, to a weight feeder, and into an air swept Ball Mill. Crushed coal

LICADO, 200 TON/HOUR COI

AMERICAL PLANT FLOW SCHEMATIC

CC890505-1

Figure 7.2.2-1

is classified in a cyclone with bottoms (larger than 200 mesh) returning to the Ball Mill, and the 200 mesh and smaller material passing through a Bag House and into a Fines Storage Vessel which has an oxygen depleted atmosphere.

Coal fines pass from storage into one of two Lock Hoppers. Each Lock Hopper may feed one of two Coal Slurry Tanks and cycles between them. The pressure is equalized between the Lock Hopper and one Slurry Tank which contains high pressure CO_2 , and then the coal fines flow into the Slurry Tank. The tank is filled to a prescribed level with high pressure water (saturated with CO_2 at about 5.8%), isolated, and stirring initiated.

When the slurry is homogeneous, the slurry pump sends a 20% wt. solids water slurry to all four Hydraulic Mixers where liquid CO_2 is intimately mixed with the slurry. Each Hydraulic Mixer is connected to one Separator column. Within the column, CO_2 containing coal rises; and the refuse remains with the water and sinks. Residence time in the separator is five minutes.

Refuse and water are constantly drawn from the bottom of the separator at a 19 wt. % solids concentration. Part way up the column, water is decanted from the concentrated refuse and stored in two Recycle Water Vessels. Meanwhile, the refuse stream is further concentrated in a Refuse Cyclone, with the overflow water going to the Recycle Water Vessels and the concentrated refuse (34 wt. % solids) alternately filling one of the three Refuse Depressurizer Tanks. Again, water is decanted from the settled sludge and is sent to atmospheric water storage. The water may be filtered to remove waste particles entrained in the cyclone underflow, or it may be recirculated with these particles. The settled refuse paste (approximately 50% wt. solids) is forced from the bottom of the vessel into disposal cars. If necessary, flocculents may be used to achieve

these solids concentrations in the waste. While the first tank is filling, the second tank is settling and its water is being decanted; and the third is discharging refuse paste from the bottom into the cars.

Cleaned coal and CO_2 exit the top of the separators (23% wt. solids). The coal/ CO_2 slurry flows through a desliming cyclone (not shown) into the auger filters (16 units) operating at saturated conditions. The feed slurry liquid level is maintained in the filter medium auger leg, while saturated vapor is above the liquid in the remaining auger leg and in the vertical coal receiver leg. The auger is constantly turning at one to three RPM, stripping coal from inside the filter medium, and delivering it to the top of the unit where it falls into the coal receiver leg. Four filters are connected to one Product Coal Collection Vessel. The coal in each filter is cyclically discharged into the Product Collection vessel in which it is depressurized. The CO_2 goes to two CO_2 accumulators, while the clean coal flows to a closed rail car with depleted oxygen atmosphere.

Filtrate (liquid CO_2) from the filters is delivered to the process system pressurizer.

Gaseous CO_2 , at approximately 4.41×10^6 Pascals (640 psig) from the accumulators, is recompressed in a recycle compressor to 5.79×10^6 Pascals (840 psig), cooled to 21.1°C (70°F), and returned to the process system pressurizer.

The system pressure is maintained at saturated conditions 21.1°C (70°F) and 5.79×10^6 (840 psig) by automatic temperature control of the pressurizer through heating or cooling.

7.2.4 Budgetary Cost Estimate

The fixed capital cost was based on a method presented in Reference 7-1 and is used in the process industry to provide budgetary plant costs. Equipment and component costs are estimated, and then the remaining direct and indirect costs are calculated as a factor of that cost. The factors are based on historical data of chemical process plants, which were modified because of the high capital cost of this plant resulting from the costly grinding system and high pressure, stainless steel vessels. This approach was also used to provide the costs of Reference 2.

Vessel and tank fabricators were contacted; and a cost per pound of metal was obtained for code stamped vessels built to the ASME Pressure Vessel Code, Section VIII and made of 304 stainless steel. The cost estimates of standard equipment and components were provided by manufacturers and suppliers. The total of these costs were considered as Primary Equipment Costs and used as the basis for estimating the remaining direct and indirect Fixed Capital Costs.

The total Fixed Capital Cost for the commercial 181 metric ton/hr (200-ton/hour) LICADO plant is \$94,580,500. This cost (breakdown presented in Appendix G) is used in the economic studies presented in Section 8.0.

In this estimate for the fixed capital cost, there was no cost allocated for land or buildings because it was assumed outdoor construction would be used for the equipment on land furnished by the host coal mine or utility. Space for the control room was assumed to be available in existing buildings. Other factors, such as engineering and supervision and process contingencies, were estimated at about one-half the values used in previous studies because of the high capital cost of the equipment for this plant. Without this reduction, the costs for these factors would have been overestimated.

7.3 Waste Stream Recovery Plant (50-Ton/Hour)

A modified process was conceptually designed which used CO_2 for coal beneficiation differently than it is used in the LICADO process. In the LICADO process, sufficient CO_2 is used to form a coal-rich liquid CO_2 phase separate from the refuse-rich water phase. The CO_2 and water phases are separated, and the coal is then removed from the CO_2 phase.

In the modified process, just enough CO_2 is used to bridge or agglomerate the coal fines into particles which are larger than the refuse fines. The refuse fines are not affected and remain with the water phase. The mixture is then screened, and the coal agglomerate stays on the screen while the water with refuse passes through the screen.

Tests of the modified process were made with several coals in the 2-inch diameter batch system, which demonstrated the feasibility of this approach. This work is described in Section 3.3 of this report. Promising results were obtained with Illinois No. 6 coal, which is hydrophilic, as coal wastes may become after extended storage in water.

A conceptual design of a 45 metric ton/hr (50-ton/hour) plant was developed to be used as the basis for a budgetary cost estimate and comparison with the LICADO process. Feed to this 50-ton/hour plant is assumed to be the waste stream from a commercial coal washing plant and contains about 3% wt. solids in water. The coal feed was based on Upper Freeport coal with approximately 25% wt. refuse.

7.3.1 Requirements

The plant is designed to meet the requirements and assumptions which follow:

- Feed is 45 metric ton/hr (50-ton/hour) of 3% wt. solids from a waste stream of a Commercial Coal washing plant
- Feed is bituminous coal from the Upper Freeport seam at ≤ 200 mesh
- The plant will be designed for 50% ash rejection and 70% yield
- Feed coal/water stream concentrated to 20% wt. solids before CO₂ contact
- 20% wt. CO₂ per weight of coal used in process
- Limited water saturation with CO₂ at high pressure due to short residence time
- Coal residence time in separator is one minute
- Utilities are site available
- All process wetted containment material is 304 stainless steel
- Vessel wall thickness is ≤ 5.1 cm (2 inches)
- Concept sufficient to provide basis for budgetary capital cost estimate
- A pressurized moving screen continuous filter will be used for product recovery, similar to Figure 7.1.7.2-1 and -2.

7.3.2 Discussion of System (Figure 7.3.2-1)

The process appears to be simpler than the standard LICADO process, since there is no liquid CO₂ phase requiring separation from the water phase.

However, should more CO₂ be required than anticipated or be absorbed in the water phase, then a CO₂/water separator could be installed between the product filter and the refuse pond to reclaim the CO₂.

In the laboratory, separation of the larger size coal agglomerates from the refuse/water phase by screening has been very effective. Therefore, this method of product recovery is used in the plant, assuming that a continuous belt screen contained in a pressure housing has been developed.

This plant does not recycle the process water as is done in the standard LICADO process. Separation of the refuse from the water is no longer required, and both are dumped into the on-site refuse pond. The energy of the high pressure refuse water might be partially reclaimed by driving a coal/water slurry booster pump installed up stream of the regular slurry pump.

7.3.3 Description of Plant

The waste stream (containing 3% solids) from a coal washing plant is concentrated to 20% wt. solids in a cyclone. Underflow from the cyclone goes to a slurry feed tank from which a slurry pump pressurizes the feed into a mixer in which it contacts liquid CO₂ at approximately 5.89×10^6 (855 psig). The CO₂ agglomerates the coal fines into larger particles; and the mixture of agglomerated coal, smaller particle refuse and water passes onto a moving screen which allows the refuse and water to pass through while retaining the agglomerated coal particles. This moving screen filter is contained within a pressurized vessel which incorporates a separate filtrate receiver and clean coal storage in the

50 TON/HOUR CO₂ A FLOW

AGLOMERATION PROCESS SHEET

CC890522-1

Figure 7.3.2-1

vessel bottom. Filtrate (refuse and water) is returned to the refuse pond while the cleaned coal passes through the coal receivers into the depressurizer, and from there is ready for combustion.

Based on the requirements and the information given in Figure 7.3.2-1, the plant components were sized and a budgetary cost estimate was established for the plant.

7.3.4 Budgetary Cost Estimate

The same budgetary cost estimating procedure was used for this plant as is outlined in Section 7.2.4.

The total fixed capital cost for the commercial 45 metric ton/hr (50-ton/hr) Agglomeration Plant is \$9,670,000. This cost (details presented in Appendix 7.3.4) is used in the economic evaluations presented in Section 8.0.

REFERENCES

- 7-1. R. Miller and E. B. Miller, Translator, "Manual of Economic Analysis of Chemical Processes," McGraw-Hill Co., New York, 1981.
- 7-2. "Technical/Economic Assessment of the LICADO Process", by Burns and Roe Services Corporation, for U.S. DOE Pittsburgh Energy Center, March 1986.

8.0 ECONOMIC STUDIES

Economic studies of the LICADO process were made to determine the market potential for this process. Studies were made of the product sales price for two applications of this process: a 181 metric ton/hr (200-ton per hour) plant, such as would be located at a mine or utility, and a 45 metric ton/hr (50-ton per hour) waste recovery plant, which would process the fines in the waste stream from an existing conventional plant or would recover fines from a waste pond. The economics model and results of these studies are discussed in this section.

8.1 Economic Model

A process economics model was developed using a personal computer spreadsheet that calculated the required sales price per ton of coal processed by the LICADO process. This sales price was calculated from the capital cost of the plant, financing costs, taxes, return on investment, plant operating and maintenance costs, and refuse disposal costs. The sensitivity of the sales price to variations in key parameters was investigated.

This reference case parameters for the economic studies are summarized in Table 8.1-1. Sensitivity analyses were made to determine the effect upon the required sales price for variations in return on investment, capital cost, carbon dioxide usage, and plant capacity factor. An example of the program output is provided in Appendix 8-1.

8.2 Economic Study Results

Results of the economic studies of the 181 metric ton/hr per hour, ROM plant and the 45 metric ton/hr plant Waste Recovery Plants are discussed in this section.

TABLE 8.1-1
PARAMETERS USED IN ECONOMIC MODEL

	<u>Run-of-Mine Plant</u>	<u>Waste Recovery Plant</u>
Plant Capacity, tons/hr	200	50
Capital Cost, \$M	95	12.5
Carbon Dioxide Usage, wt. % of Product	1.0	2.0
Return-On-Investment (after taxes), %	20	20
Taxes, %	37	37
Plant Capacity Factor (Dimensionless)	0.80	0.80
Operating and Maintenance, \$M/yr	12.45	2.15
Plant Life, Years	20	20
Escalation, % per year	5	5
Interest during Construction, %	10	10
% Debt	0.75	0.75
Long Term Interest, %	12	12
Refuse Disposal Costs, \$ per ton of refuse	2.00	1.00

BREAKDOWN OF OPERATING AND MAINTENANCE COST

	<u>Run-of-Mine Plant</u>	<u>Waste Recovery Plant</u>
Labor, \$M/yr	3.0	0.92
Utilities, \$M/yr	6.0	0.188
CO ₂ , \$M/yr	0.91	0.595
Waste Disposal, \$M/yr	1.59	0.318
Replacement Equipment	1%, first 5 years 2%, last 15 years	1%, first 5 years 2%, last 15 years

8.2.1 ROM Plant

Economic analyses of the 181 metric ton per hour, ROM plant, were made using the computer-based model. The plant capital costs and operating/maintenance costs were estimated from the plant conceptual design and flow sheet described in Section 7.2

Results of the analyses for this plant are graphically correlated in Figures 8.2-1, 8.2-2, and 8.2-3. The required sales price for the reference case was \$17.10/ton (\$18.85/metric ton) (product). In Figure 8.2-1, the sales prices per ton of product for the base case is correlated with the return on investment after taxes. The sales price is not very sensitive of the return-on-investment; for example, the sales price decreases about \$0.70 per ton (\$0.77 per metric ton) for a 5% reduction in return-on-investment.

Similarly, the sales price is not strongly affected by the carbon dioxide loss or capital cost. From Figure 8.2-2, a decrease in capital cost of \$10M reduces the sales price by less than \$1.00 per ton (\$1.11 per metric ton). A doubling of the carbon dioxide loss from 1% to 2% per ton of product increases the sales price by only \$0.70 per ton (\$0.77 per metric ton) on product.

The sales price, however, is very sensitive to the plant capacity factor, as illustrated in Figure 8.2-3. A decrease in plant utilization from 0.8 to 0.7 results in about \$1.50 per ton (\$1.65 per metric ton) rise in sales price. The sensitivity to this parameter results from the large capital cost of the LICADO plant.

The estimated sales price for the LICADO process indicates that the process is in the same range as most of the deep cleaning processes based on price per ton of product. However, when prices are compared on the

Figure 8.2-1. LICADO Product Sales Price
Effect of After Tax ROI

Figure 8.2-2. LICADO Product Sales Price
Effect of Capital Cost on
200 Ton/Hour Plant

Figure 8.2-3. LICADO Product Sales Price
Effect of Plant Capacity

basis of heating value, the LICADO process will be 15 to 20% less because of the low (10% to 15%) moisture resulting from this process, compared to the high moisture contents of other physical cleaning processes (25% to 30% moisture).

8.2.2 Waste Recovery Plant

Process economics were investigated for a 45 metric ton/hr (50-ton per hour) plant that recovered fines from the waste stream of an existing, conventional working plant or from a waste pond. For both of these applications, the plant is that described in Section 7.3. The capital cost of the plant is much lower than the ROM plant not only because of the difference in size by a factor of four, but because of plant equipment not required in the waste stream or waste pond application. For these applications, the grinding circuit and most of the waste processing systems are not required. The grinding circuit, which can be as much as one-third of the total plant capital cost, is not required in these applications, since the coal is already in the form of fine particles. Refuse concentrating and handling systems are minimized in this design, since the wastes can be discharged directly into the waste pond for the existing plant or back into the waste pond, which is the source if pond waste is being processed.

The required processing sales price is \$10.40 per ton (\$11.46 per metric ton) for the 45 metric (50-ton) per hr plant operating to recover waste fines. The sales price per ton of product is correlated with the plant capital costs, with all the other parameters at their reference case values, in Figure 8.2-4. The sales price is not overly sensitive to the capital cost. For example, a change in capital cost of \$2M results in a change of only \$0.80 per ton (\$0.88 per metric ton) of product.

The sensitivity of the product sales price to the cost of carbon dioxide is illustrated in Figure 8.2-5. Changes in carbon dioxide cost of $\pm 50\%$

Figure 8.2-4. LICADO Product Sales Price
Effect of Capital Cost on 50 Ton/Hour
Waste Recovery Plant

Figure 8.2-5. LICADO Product Sales Price
Effect of CO₂ Cost on 50 Ton/Hour
Waste Recovery Plant

per ton of product result in about $\pm \$0.90$ per ton ($\$0.99$ per metric ton) change in the sales price of the product. These costs are the result of the small amount of carbon dioxide that is absorbed on the product surface and the dissolved carbon dioxide in the waste water discharged with the refuse.

The sales price per ton of product is correlated with the plant capacity factor in Figure 8.2-6. In this case, the sales price is affected significantly by a decrease in plant capacity factor. A decrease of 25% in plant capacity (from 0.80 to 0.60) results in an increase in sales price of about $\$2.00$ per ton ($\$2.20$ per metric ton).

This price per ton of recovered coal is very competitive, since a valuable product has been converted from waste materials. Compared to other processes that can recover and clean waste coals from the same sources, the LICADO process will have a 15-20% advantage because of the lower water content of its product.

Figure 8.2-6. LICADO Product Sales Price
Effect of Plant Capacity on 50 Ton/Hour
Waste Recovery Plant

9.0 SUMMARY, CONCLUSIONS, AND RECOMMENDATIONS

In this section, the summary of this final report is presented together with conclusions and recommendations.

9.1 Summary

The test program for this phase of the LICADO development program included batch tests using eight different coals: three Upper Freeport coals, two Pittsburgh seam coals, two Illinois No. 6 coals, and one Middle Kittanning coal. Initial tests were performed in a 5.1 cm (2-inch) diameter column in the fixed volume mode of operation. In these tests, a fixed volume of coal-water slurry was mixed with a fixed volume of liquid CO₂, and the two phases were separated and analyzed. Initial parametric tests demonstrated that a mixing speed of about 800 rpm provided the best separation and recovery.

Twenty-seven experiments were performed for each of three coals using a factorial matrix to examine the effect of particle size, liquid CO₂ flow rate, and slurry concentration upon process performance. The coals used in these experiments were Pittsburgh Bruceton, Middle Kittanning, and Illinois No. 6. Results of these tests showed:

- Finer particles increased heating value recovery.
- Higher slurry concentrations decreased heating value recovery and ash reduction for Pittsburgh-Bruceton coal, but not for the other coals.
- CO₂ flowrate did not affect either the heating value recovery or ash reduction for any coal tested.

More than 100 tests were made using variable liquid CO₂ volume operation. In these tests, a fixed volume of coal-water slurry was contacted by flowing CO₂. Clean coal was continuously removed from the top of the separator column. Thus, this variable volume (or semi-continuous operation) simulated the CO₂ portion of the process, but the coal-water slurry became depleted of coal and enriched in mineral concentration as the coal particles were carried out by the flowing CO₂. All eight of the coals were tested in the variable volume apparatus. Excellent results for these coals were obtained, with the best results of 95% ash and pyrite rejection being obtained with Upper Freeport coal. Results are very close to, and in some cases, better than the measured washability data for the same coal and particle size. The powdered coal product is relatively dry, containing 5 to 10% moisture. Use of 1-Octanol at 155 ppm improved the process performance for Illinois No. 6 coal from 70% Btu recovery and 50% ash rejection to 80% for both Btu recovery and ash rejection. Use of sodium hexametaphosphate did not benefit the process.

Two-step (i.e., use of the product as the feed for a second cleaning) cleaning resulted in higher overall ash and pyrite rejection, but at lower overall yields. The reduced yield resulted from the additional losses of coal particles during the second cleaning step.

Tests of an integral two-stage separation system in the variable volume batch apparatus resulted in noticeable improvements in ash rejection and about the same Btu recovery as for a single-stage at low impeller speeds. At higher impeller speeds, the ash rejection remained relatively unchanged, whereas ash rejection was significantly reduced at higher speeds in the single-stage system.

The Continuous Research Unit, which simulates an integrated LICADO process with continuous coal-water slurry feed, liquid CO₂ injection, product withdrawal and separation, and waste water withdrawal, has been successfully operated for periods as long as fourteen hours. Coal feed

rates of 0.45 to 4.5 kg/hr (1 to 10-lb/hr) have been tested. The heating value recovery increases when the feed rate increases from 0.45 kg/hr (1 lb/hr) to 1.35 kg/hr (3 lb/hr), but the heating value recovery decreases at feed rates greater than 2.70 kg/hr (6-lb/hr). This decrease at 2.72 kg/hr (6-lb/hr) is caused by the limit of the CO₂ flow rate through the column. This limit results from excessive coal carry-over from the coal product/CO₂ separator and is not a process limit. At 1.35 kg/hr (3-lb/hr) feed rate, heating value recoveries of 80%, ash reductions of 75%, and pyrite reductions of 80%, are achieved with a product that is relatively dry. These results indicate that the overall performance of the continuous system approaches the limit of washability for the particle size (-200 mesh) tested.

A LICADO Simulation Model has been developed for use with a personal computer which provides material balances for each of the unit operations. The model, which is programmed in FORTRAN IV, uses input data characterizing the feed coal and required production and process data such as slurry concentration, CO₂ flow rates, and separator/mixer residence times determined from the experimental program. In addition to material balances at each process unit, the program sizes the mixer and separator, including wall thicknesses, in compliance with the ASME Pressure Vessel Code. Piping sizes are also calculated.

Three conceptual plant designs have been developed, a 0.9 metric ton/hr (1 ton/hr) Proof-of-Concept Plant, a 181 metric ton/hr (200 ton/hr) commercial plant, and a 45 metric ton/hr (50 ton/hr) fines recovery plant. The 0.9 metric ton/hr Proof-of-Concept Plant conceptual design was developed in the most detail, including plant arrangement drawings, equipment layouts for the grinding system, mixer, separator, and filter, and control system instrumentation functions and schematic. A detailed cost estimate was prepared for the Proof-of-Concept Plant, since final design and construction of this plant is the next logical step in developing the LICADO technology. The 181 metric ton/hr and 45 metric ton/hr plant

designs were more conceptual and were used to provide budgetary capital and operating costs for use in economic studies of the process.

Economic studies have been made for a 181 metric ton/hr, stand-alone plant using run-of-mine coal as feed, and a 45 metric ton/hr plant processing waste fines from the waste stream of a conventional washing plant. The input parameters, other than capital and operating/maintenance cost, for the two studies were identical; i.e., 20% return on investment, 37% taxes, 20-year plant life, 12% interest, 5% inflation rate, and 0.80 plant capacity factor.

The required sales price for the LICADO process is \$17.20/ton for the 181 metric ton/hr (200-ton/hr) plant and \$10.40/ton for the 45 metric ton/hr (50-ton/hr) waste recovery plant. The sales price is not strongly sensitive to plant capital cost or return-on-investment, but is very sensitive to the plant capacity factor. These costs are competitive with other advanced physical coal cleaning processes, showing a 15-20% advantage on a cost per heating unit comparison because the lower moisture content of the LICADO process provides a higher heating value.

9.2 Conclusions

The following conclusions result from the work described in this report:

- The LICADO process effectively reduces ash and pyrite from all the coals tested, with typical heating value recoveries in the 80 to 85% range, and ash/pyrite rejections of 80 to 90%.
- Results in both variable volume batch tests and continuous tests have achieved results close to or exceeding the washability data. This indicates that the process is limited by mineral liberation, and higher ash/pyrite rejections

could be achieved with smaller particle sizes and multistage separation.

- Adequate ash/pyrite rejections at high Btu recoveries are achievable at a top size of -200 mesh. This particle size is more economical than finer sizes and is typical of the size used in pulverized coal boilers.
- Premixing the coal-water slurry with a portion of the CO_2 enhances yield and slightly decreases ash/pyrite rejection compared to mixing all of the CO_2 with the slurry in the Separation Column. For example, the yield of Illinois No. 6 increased about 12%, while the pyrite rejection decreased 5%, with an increase of premixing time from three to 10 minutes.
- Multistep variable volume batch operation improves ash/pyrite rejection at the expense of lower Btu recovery. Since the overall yields in this mode of operation are decreased, multistep operation is economically noncompetitive. For Middle Kittanning coal, the ash reduction increased by almost 50% after the second step, with the loss of about 14% in yield.
- Multistage operation in the Batch Variable Volume operation showed noticeably improved separation, (~13%) at equivalent heating value recoveries, and significantly less sensitivity to impeller speeds.

- Multistage operation shows promise in improving the performance of the LICADO process in larger systems.
- Steady-state operation of the Continuous Research Unit has been demonstrated for up to fourteen hours. Continuous operation is limited only by the supply of ground coal and the availability of the operators.
- The product is relatively dry (5 to 15% moisture) compared to other advanced physical cleaning processes (25 to 30% moisture). This eliminates the necessity of drying the coal product.
- Process costs, \$17.40/ton estimated for a stand-alone plant or \$10.40/ton for a waste recovery plant at an existing plant, are competitive with other advanced physical coal cleaning processes.
- On a cost per heating value basis, the LICADO processed coal will have a 15 to 20% cost advantage over processes with wet products because of its lower moisture content (lower moisture results in a higher heating value per pound and savings in drying cost).

9.3 Recommendations

The following recommendations result from the work performed in this phase of the LICADO development.

- Further experiments should be performed in the Continuous Research Unit at higher capacities, to

22.5 kg/hr (50-lb/hr), in the 15.2 cm (6-inch) diameter separator.

- The multistage separator with several CO₂ injections and mixing sections followed by agglomerating sections should be tested in the Continuous Research Unit.
- Performance assessments of the process in cleaning coal fines from several waste storage ponds should be made. Waste ponds containing several different coals should be investigated.
- The auger filter should be developed for larger capacities.
- A 0.9 metric ton (1-ton/hr) Proof-of-Concept Plant for the LICADO project should be constructed and operated to confirm the data obtained with the smaller scale systems, and to provide the data base for scale-up to a commercial scale demonstration plant.

APPENDIX A
WASHABILITY DATA

The washability data for four of the eight coals is presented
Tables A-1 through A-4.

Table A-1
Washability data for Upper Freeport coal (# 1)
Particle Size: 200 x 0 Mesh
Feed Ash : 23.8%
Feed total sulfur : 1.39%
Feed pyritic sulfur: 1.13%

Specific Gravity		Cumulative Float			Cumulative Sink		
Sink	Float	Yield (%)	Ash (%)	Pyritic Sulfur (%)	Yield (%)	Ash (%)	Pyritic Sulfur (%)
-	1.30	30.4	2.40	0.05	100.0	25.31	1.44
1.30	1.35	45.3	3.51	0.08	69.6	35.31	2.05
1.35	1.40	50.6	4.32	0.11	54.7	43.36	2.57
1.40	1.60	69.2	7.36	0.38	43.4	53.28	3.19
1.60	1.80	73.5	9.34	0.30	30.8	65.64	4.27
1.80	-	100.0	25.31	1.44	26.5	69.60	4.59

Table A-2
Washability data for Middle Kittanning coal (# 6)
Particle Size: 200 x 0 Mesh
Feed Ash : 6.9%
Feed total sulfur : 3.76%
Feed pyritic sulfur: 3.32%

Specific Gravity		Cumulative Float			Cumulative Sink		
Sink	Float	Yield (%)	Ash (%)	Pyritic Sulfur (%)	Yield (%)	Ash (%)	Pyritic Sulfur (%)
-	1.30	59.9	1.42	0.24	100.0	7.23	2.69
1.30	1.35	76.7	2.12	0.46	40.1	15.92	6.35
1.35	1.40	82.8	2.66	0.66	23.3	24.06	10.03
1.40	1.60	89.6	3.44	0.88	17.2	29.24	12.46
1.60	1.80	92.4	3.92	0.97	10.4	39.90	18.28
1.80	-	100.0	7.23	2.69	7.6	47.50	23.55

Table A-3
Washability data for Illinois No.6 coal (# 7)
Particle Size: 200 x 0 Mesh
Feed Ash : 25.8%
Feed total sulfur : 4.07%
Feed pyritic sulfur: 2.09%

Specific Gravity		Cumulative Float			Cumulative Sink		
Sink	Float	Yield (%)	Ash (%)	Pyritic Sulfur (%)	Yield (%)	Ash (%)	Pyritic Sulfur (%)
-	1.30	38.8	3.43	0.21	100.0	24.62	2.19
1.30	1.35	51.8	4.71	0.21	61.2	38.05	3.44
1.35	1.40	60.4	4.95	0.22	48.2	46.02	4.32
1.40	1.60	71.0	7.58	0.25	39.6	54.61	5.20
1.60	1.80	74.6	7.88	0.33	29.0	66.34	6.94
1.80	-	100.0	24.62	2.19	25.4	73.8	7.64

Table A-4
Washability data for Illinois No.6 coal (# 8)
Particle Size: 200 x 0 Mesh
Feed Ash : 13.5%
Feed total sulfur : 2.20%
Feed pyritic sulfur: 1.40%

Specific Gravity		Cumulative Float			Cumulative Sink		
Sink	Float	Yield (%)	Ash (%)	Pyritic Sulfur (%)	Yield (%)	Ash (%)	Pyritic Sulfur (%)
-	1.30	50.7	1.90	0.06	100.0	13.50	1.25
1.30	1.35	53.5	1.90	0.06	49.3	25.4	2.77
1.35	1.40	70.3	3.10	0.06	46.5	26.9	2.94
1.40	1.60	85.1	4.90	0.06	29.7	38.1	4.57
1.60	1.80	89.2	6.20	0.06	14.9	62.6	9.05
1.80	-	100.0	13.50	1.25	10.8	73.8	12.46

DEFINITION OF DIAMETERS

Volume-Surface Mean Diameter:

$$D_{vs} = \frac{\sum_{i=1}^n N_i D_i^3}{\sum_{i=1}^n N_i D_i^2}$$

Weight Mean Diameter:

$$D_w = \frac{\sum_{i=1}^n N_i D_i^4}{\sum_{i=1}^n N_i D_i^3}$$

Where N_i = Number of particles

D_i = Diameter of particles

DEFINITION OF DIAMETERS

Volume-Surface Mean Diameter:

$$D_{vs} = \frac{\sum_{i=1}^n N_i D_i^3}{\sum_{i=1}^n N_i D_i^2}$$

Weight Mean Diameter:

$$D_w = \frac{\sum_{i=1}^n N_i D_i^4}{\sum_{i=1}^n N_i D_i^3}$$

Where N_i = Number of particles
 D_i = Diameter of particles

APPENDIX B
RESULTS FROM FIXED VOLUME BATCH TESTS

STATISTICAL ANALYSIS OF THE FIXED VOLUME BATCH TESTS WITH THREE DIFFERENT COALS

A brief description of the methodology for statistical analysis is given below. This is followed by the presentation of the results for experiments conducted using the fixed volume batch unit.

The experiments in the fixed volume batch mode were designed at three levels and for three factors. These are indicated in Tables B-1 and B-6. The maximum number of tests (without replication) in this case is $3^3 = 27$.

Two parameters were analyzed:

(a) Btu Recovery, defined as

$$\text{Btu Recovery (\%)} = \text{Yield} * \frac{(100 - \text{Clean Coal Ash Content})}{(100 - \text{Feed Coal Ash Content})}$$

(b) Ash Reduction (AR), defined as

$$\text{AR(\%)} = 100 - \frac{\text{Clean Coal Ash Content}}{\text{Feed Coal Ash Content}} * 100$$

The data are analyzed for each factor as follows:

$$\text{Total for each level: } t_j = \sum_{i=1}^n y_{ij} \quad j = 1, 2, \dots, m$$

$$\begin{aligned} n &= \text{No. tests/level} = 9 \\ m &= \text{No. levels} = 3 \end{aligned}$$

$$\text{Total number of tests: } N = nxm = 27$$

$$\text{Sum of Squares: } SS = \sum_{j=1}^m t_j^2/n - SS_t$$

$$n \quad m$$

$$SS_t = (\sum_{i=1} \sum_{j=1} y_{ij})^2 / N$$

$$\text{Total Sum of squares: } SS_{TOT} = \sum_{i=1}^n \sum_{j=1}^m y_{ij}^2 - SS_t$$

Each factor has $f = m - 1 = 2$ degrees of freedom and the total number of degrees of freedom is $f_{TOT} = N - 1 = 26$.

The mean square for each factor can be calculated as

$$s^2 = SS/f$$

The residue is considered an estimation of the experimental error. The same parameters calculated for the factors can be determined for the residue:

$$SS_R = SS_{TOT} - \sum_{\text{factors}} SS$$

$$(s_R)^2 = SS_R / f_R$$

$$f_R = f_{TOT} - \sum_{\text{factors}} f = 20.$$

The significance of each factor is determined by comparing the ratio $s^2 / (s_R)^2$ with F distribution values with (f, f_R) degrees of freedom. In this case these values are:

% Confidence	F(2,20)
75	1.49
90	2.59
95	3.49
99	5.85

The analysis of variance was performed for the Btu recovery and the ash reduction results of the fixed volume batch experiments. This was carried out for all three coals investigated (i.e. coals designated as # 4, # 6 and # 7 in Tables 3.0-1).

A summary of the analysis of variance results for Pittsburgh-Bruceton coal is given in Tables B-1 and B-2.

Table B-1
Btu Recovery (%) Analysis of Variance
Pittsburgh- Bruceton Coal

FACTOR	LEVEL AVERAGE			SS	s^2	s^2/s_R^2
	1	2	3			
PARTICLE SIZE	71	77	74	208	104	1.95
SLURRY CONCENTRATION	77	81	68	865	433	8.12
LIQUID CO ₂ FLOWRATE	74	76	76	13	6	0.12
Residue				1066	53	

Table B-1 demonstrates that slurry concentration is the only factor that significantly affects the Btu recovery of Pittsburgh-Bruceton coal. This is especially significant at a slurry concentration of 5% when higher Btu recoveries were obtained. The effect of particle size does not play a dominant role, possibly due to the small variation in particle size investigated.

Table B-2
Ash Reduction (%) Analysis of Variance
Pittsburgh-Bruceton Coal

FACTOR	LEVEL AVERAGE			SS	s^2	s^2/s_R^2
	1	2	3			
PARTICLE SIZE	29	30	32	65	33	1.34
SLURRY CONCENTRATION	34	30	28	164	82	3.38
LIQUID CO ₂ FLOWRATE	33	30	29	80	40	1.64
Residue				486	24	

Table B-2 shows that none of the three factors exert a significant influence on the ash reduction characteristics of Pittsburgh-Bruceton coal. There is a marginal effect of slurry concentration at the lower value of 2.5% where the ash reduction appears to be higher.

Table B-3
Btu Recovery (%) Analysis of Variance
Middle Kittanning Coal

FACTOR	LEVEL AVERAGE			SS	s^2	s^2/s_R^2
	1	2	3			
PARTICLE SIZE	52	63	75	2274	1137	6.73
SLURRY CONCENTRATION	57	68	64	574	287	1.70
LIQUID CO ₂ FLOWRATE	63	67	60	186	93	0.55
Residue				3380	169	

Table B-3 shows the analysis of variance of the Btu recovery results. The analysis of variance indicates that the Btu recovery results are influenced significantly only by the particle size. This conclusion is significant at a 99% confidence level. These results show a clear trend suggesting that smaller particle size samples generate higher yields.

Table B-4
Ash Reduction (%) Analysis of Variance
Middle Kittanning Coal

FACTOR	LEVEL AVERAGE			SS	s^2	s^2/s_R^2
	1	2	3			
PARTICLE SIZE	45	46	45	6.3	3.2	0.30
SLURRY CONCENTRATION	47	45	45	31.2	15.6	1.48
LIQUID CO ₂ FLOWRATE	46	46	45	8.2	4.1	0.39
Residue				211.2	10.6	

Table B-4 depicts the analysis of variance performed to the ash reduction results. The analysis indicates that none of the studied variables exert a significant effect on the ash reduction results.

A summary of the analysis of variance results for Illinois No.6 coal (26.0% ash sample) is given in Tables B-5 and B-6.

Table B-5
Btu Recovery (%) Analysis of Variance
Illinois No. 6 Coal

FACTOR	LEVEL AVERAGE			SS	s^2	s^2/s_R^2
	1	2	3			
PARTICLE SIZE	52	54	68	1359	680	9.51
SLURRY CONCENTRATION	58	58	59	6	3	0.04
LIQUID CO ₂ FLOWRATE	57	57	60	54	27	0.37
Residue				1430	72	

Table B-5 shows the analysis of variance of the Btu recovery results. The analysis of variance indicates that the Btu recovery results are influenced significantly only by the particle size. This conclusion is significant at a 99.9% confidence level. The Btu recovery results show a clear trend suggesting that smaller particle size samples generate better results. This is similar to the conclusion drawn for Middle Kittanning coal.

Table B-6
Ash Reduction (%) Analysis of Variance
Illinois No. 6 Coal

FACTOR	LEVEL AVERAGE			SS	s^2	s^2/s_R^2
	1	2	3			
PARTICLE SIZE	48	50	53	109.5	54.8	2.28
SLURRY CONCENTRATION	49	51	52	48.3	24.2	1.01
LIQUID CO ₂ FLOWRATE	48	51	51	52.4	26.2	1.09
Residue				479.7	24.0	

Table B-6 depicts the analysis of variance performed to the ash reduction results on the high ash Illinois No.6 coal. No significant effect can be observed for the slurry concentration and the liquid CO₂ flowrate. There is a small effect of particle size on the ash reduction.

The raw data for the test results of 27 experiments with each of the three coals discussed above are presented in Tables B-7, B-8 and B-9.

Table B-7
Pittsburgh-Bruceton coal (# 4)
Fixed volume batch tests
Impeller Speed: 1000 rpm.

Test No.	Particle Size, microns	Slurry Conc. wt. %	Liquid CO2 Flowrate, ml/min	Ash Reduction %	Btu Recovery %	Pyritic Sulfur Reduction, %
1	50	2.5	100	29	87	36
2	40	5.0	100	33	82	44
3	33	10.0	25	29	76	42
4	40	2.5	50	35	89	38
5	33	5.0	100	27	88	38
6	33	5.0	50	31	81	33
7	40	10.0	100	31	67	23
8	33	2.5	50	35	62	30
9	50	10.0	25	39	73	23
10	33	5.0	25	29	79	26
11	50	5.0	100	35	82	26
12	50	10.0	100	24	65	20
13	40	5.0	25	35	71	29
14	50	5.0	50	29	84	24
15	33	2.5	25	33	69	29
16	33	2.5	100	39	62	32
17	40	2.5	25	33	80	33
18	40	2.5	100	29	84	21
19	50	2.5	25	39	75	26
20	50	10.0	50	35	68	27
21	33	10.0	50	27	61	20
22	50	5.0	25	31	75	26
23	33	10.0	100	18	64	18
24	40	5.0	50	22	86	29
25	50	2.5	50	37	86	32
26	40	10.0	50	18	66	24
27	40	10.0	25	33	69	32

Table B-8
Middle Kittanning Coal (# 6)
Fixed Volume Batch Test Results
Impeller Speed: 1000 rpm.

Test No.	Particle Size, microns	Slurry Conc. wt. %	Liquid CO2 Flowrate, ml/min	Ash Reduction %	Btu Recovery %	Pyritic Sulfur Reduction, %
1	97	2.5	100	46	53	59
2	38	5.0	100	44	73	58
3	28	10.0	25	42	92	56
4	38	2.5	50	45	71	59
5	28	5.0	100	47	82	62
6	28	5.0	50	50	80	68
7	38	10.0	100	45	65	62
8	28	2.5	50	47	88	59
9	97	10.0	25	46	71	60
10	28	5.0	25	38	87	54
11	97	5.0	100	47	54	61
12	97	10.0	100	44	65	63
13	38	5.0	25	41	56	57
14	97	5.0	50	42	70	57
15	28	2.5	25	49	66	62
16	28	2.5	100	47	57	62
17	38	2.5	25	51	59	61
18	38	2.5	100	49	58	63
19	97	2.5	25	44	21	61
20	97	10.0	50	49	52	64
21	28	10.0	50	41	58	58
22	97	5.0	25	45	42	59
23	28	10.0	100	41	62	58
24	38	5.0	50	46	73	60
25	97	2.5	50	44	43	60
26	38	10.0	50	49	65	61
27	38	10.0	25	45	49	58

Table B-9
Illinois No. 6 Coal (# 7)
Fixed Volume Batch Test Results
Impeller Speed: 1000 rpm.

Test No.	Particle Size, microns	Slurry Conc. wt. %	Liquid CO2 Flowrate, ml/min	Ash Reduction %	Btu Recovery %	Pyritic Sulfur Reduction, %
1	70	2.5	100	42	48	33
2	50	5.0	100	57	56	37
3	41	10.0	25	56	76	31
4	50	2.5	50	46	47	34
5	41	5.0	100	58	75	33
6	41	5.0	50	56	55	37
7	50	10.0	100	44	56	32
8	41	2.5	50	52	60	36
9	70	10.0	25	55	51	34
10	41	5.0	25	58	80	30
11	70	5.0	100	37	37	30
12	70	10.0	100	51	55	33
13	50	5.0	25	45	52	32
14	70	5.0	50	45	45	32
15	41	2.5	25	47	63	32
16	41	2.5	100	51	71	28
17	50	2.5	25	51	49	33
18	50	2.5	100	48	53	38
19	70	2.5	25	49	67	34
20	70	10.0	50	53	53	32
21	41	10.0	50	52	70	32
22	70	5.0	25	51	52	30
23	41	10.0	100	48	63	31
24	50	5.0	50	52	70	34
25	70	2.5	50	51	60	34
26	50	10.0	50	55	52	34
27	50	10.0	25	51	52	31

Table B-10
Particle Size Distribution after 3 min grinding
Middle Kittanning coal (# 6)

Size (microns)	Particles Over	No % Over	Weight % Over
2.0	8042	100.00	100.00
4.0	5007	62.26	99.89
6.3	2682	33.35	99.47
10.0	1259	15.66	98.44
12.6	868	10.79	97.69
15.8	622	7.73	96.74
19.9	429	5.33	95.28
25.1	305	3.79	93.39
31.6	211	2.62	90.53
39.8	147	1.83	86.64
50.1	101	1.26	81.07
63.1	60	0.75	71.14
79.4	30	0.37	56.65
100.0	15	0.19	42.19
125.8	7	0.09	26.82
158.4	0	0.00	0.00

Size Range	No % Range	Weight % Range
2.0-4.0	37.73	0.109
4.0-6.3	28.91	0.424
6.3-10.0	17.69	1.029
10.0-12.6	4.86	0.753
12.6-15.8	3.05	0.941
15.8-19.9	2.40	1.466
19.9-25.1	1.54	1.886
25.1-31.6	1.16	2.860
31.6-39.8	0.79	3.888
39.8-50.1	0.57	5.579
50.1-63.1	0.51	9.927
63.1-79.4	0.37	14.489
79.4-100.0	0.18	14.456
100.0-125.8	0.09	15.373
125.8-158.4	0.08	26.820

Length Diameter = 7.7 microns
Surface-Volume Diameter = 57.4 microns
Weight Diameter = 90.1 microns

Table B-11
Particle Size Distribution after 3 min grinding
Pittsburgh- Bruceton coal (# 4)

Size (microns)	Particles Over	No % Over	Weight % Over
2.0	15202	100.00	100.00
4.0	10326	67.93	99.93
6.3	6250	41.11	99.65
10.0	3145	20.69	98.78
12.6	2161	14.22	98.05
15.8	1493	9.82	97.06
19.9	1009	6.64	95.64
25.1	672	4.42	93.66
31.6	434	2.85	90.87
39.8	253	1.66	86.62
50.1	135	0.89	81.10
63.1	65	0.43	74.56
79.4	40	0.26	69.90
100.0	25	0.16	64.32
125.8	18	0.12	59.13
158.4	10	0.07	47.29
200.0	4	0.03	29.50
316.1	0	0.00	0.00

Size Range	No % Range	Weight % Range
2.0-4.0	32.07	0.068
4.0-6.3	26.81	0.287
6.3-10.0	20.43	0.866
10.0-12.6	6.47	0.732
12.6-15.8	4.39	0.986
15.8-19.9	3.18	1.419
19.9-25.1	2.21	1.979
25.1-31.6	1.56	2.795
31.6-39.8	1.19	4.245
39.8-50.1	0.77	5.524
50.1-63.1	0.46	6.542
63.1-79.4	0.16	4.661
79.4-100.0	0.09	5.580
100.0-125.8	0.04	5.192
125.8-158.4	0.05	11.831
158.4-200.0	0.04	17.796
200.0-316.6	0.00	11.757

Length Diameter = 8.4 microns
Surface-Volume Diameter = 70.5 microns
Weight Diameter = 145.8 microns

Table B-12.
Particle Size Distribution after 3 min grinding
Illinois No.6 coal (# 7)

Size (microns)	Particles Over	No % Over	Weight % Over
2.0	23420	100.00	100.00
4.0	18801	80.28	99.94
6.3	13476	57.24	99.59
10.0	6647	28.38	97.80
12.6	4015	17.14	95.95
15.8	2531	10.81	93.89
19.9	1550	6.62	91.19
25.1	982	4.19	88.05
31.6	608	2.60	83.92
39.8	358	1.53	78.41
50.1	215	0.92	72.11
63.1	123	0.53	64.03
79.4	64	0.27	53.68
100.0	30	0.13	41.79
125.8	12	0.05	29.23
158.4	5	0.02	19.49
200.0	2	0.01	11.13
251.1	0	0.00	0.00

Size Range	No % Range	Weight % Range
2.0-4.0	19.72	0.060
4.0-6.3	22.73	0.353
6.3-10.0	29.15	1.792
10.0-12.6	11.23	1.841
12.6-15.8	6.33	2.060
15.8-19.9	2.42	3.136
19.9-25.1	1.59	4.131
25.1-31.6	1.06	5.514
31.6-39.8	0.61	6.296
39.8-50.1	0.39	8.087
50.1-63.1	0.25	10.342
63.1-79.4	0.14	11.895
79.4-100.0	0.07	12.556
100.0-125.8	0.03	9.736
125.8-158.4	0.01	8.369
158.4-200.0	0.01	8.368
200.0-251.1	0.00	11.125

Length Diameter = 9.4 microns
Surface-Volume Diameter = 48.9 microns
Weight Diameter = 98.5 microns

APPENDIX C
RESULTS FROM VARIABLE VOLUME BATCH TESTS

*** Nomenclature ***

1. Af---- Ash Content of Feed (%)
2. Ap---- Ash Content of Product (%)
3. Ar---- Ash Content of Refuse (%)
4. ARD---- Ash Reduction (%)

$$ARD = (1 - Ap/Af) \times 100\%$$
5. ARJ---- Ash Rejection (%)

$$ARJ = (1 - Y \times Ap/(100 \times Af)) \times 100\%$$
6. BTUR---- BTU Recovery (%)

$$BTUR = Y \times [1 - (Ap/100)]/[1 - (Af/100)]$$
7. CS ---- Coal Seam
8. Co ---- Initial Slurry Concentration (%)
9. Dp --- Particle Size (microns)
10. D --- Diameter of Column (inches)
11. d ---- Impeller Diameter (inches)
12. H --- Slurry Layer Height (inches)
13. Nprem --- Premixing Speed (rpm)
14. N ---- Impeller Speed in Operating Period (rpm)
15. P ----- Operating Pressure (psi)
16. Q ---- Liquid CO2 Flow Rate (cc/min)
17. Sf---- Total Sulfur Content in Feed Coal (%)
18. Sp ---- Total Sulfur Content in Product (%)
19. Sr --- Total Sulfur Content in Refuse (%)
20. Spyrf --- Pyritic Sulfur Content in Feed Coal (%)
21. Spyrp ---- Pyritic Sulfur Content in Product Coal (%)
22. Spyr --- Pyritic Sulfur Content in Refuse (%)
23. Sorgn --- Organic Sulfur Content (%)
24. SRdpyr ---- Pyritic Sulfur Reduction (%)
25. SRjpyr --- Pyritic Sulfur Rejection (min)

$$SRdpyr = 1 - (Sp/Sf)$$

$$SRjpyr = 1 - (Y \times Spyrp/100 \times Spyrf)$$
26. Tmix --- Premixing Time (min)
27. Tinj --- Liquid CO2 Injection Time (min)
28. Y ---- Overall Yield (%)

RUN	Co %	Af %	Spyrf %	Nprem rpm	Tmix min	N rpm	Q cc/min	Ap %	Ar %	Y %	BTUR %	ARD %	ARJ %
UP1	7.5	24.4	1.14	1320	5.0	1320	400	6.6	50.0	59.0	72.9	73.0	84.0
UP2	7.5	24.4	1.14	1320	5.0	1320	400	8.8	50.9	62.9	75.9	63.9	77.3
UP3	7.5	24.4	1.14	1320	5.0	1320	400	4.4	67.5	68.3	86.4	82.0	87.7
UP4	7.5	24.4	1.14	1320	5.0	1700	400	11.9	60.8	74.4	86.7	51.2	63.7
UP8	6.4	24.4	1.14	1320	5.0	600	400	2.1	49.9	53.3	69.1	91.4	95.4
UP6	6.4	24.4	1.14	1320	5.0	1000	400	3.9	62.2	64.8	82.4	84.0	89.6
UP7	6.4	24.4	1.14	1320	5.0	1320	400	4.5	67.8	68.6	86.6	81.6	87.4
UP10	6.4	24.4	1.14	1320	5.0	1700	400	9.5	66.8	74.0	88.6	61.1	71.2
UP11	6.4	24.4	1.14	1320	5.0	1000	550	4.0	63.7	65.8	83.6	83.6	89.2
UP12	6.4	24.4	1.14	1320	5.0	1000	750	4.1	66.6	67.5	85.7	83.2	88.7
UP13	6.4	24.4	1.14	1320	5.0	1000	1000	5.7	67.1	69.5	86.7	76.6	83.8
UP64	6.4	22.7	1.14	0	0	1000	400	3.2	58.7	64.9	81.2	85.9	90.9
UP65	6.4	22.7	1.14	0	0	1000	400	3.4	55.2	62.7	78.4	85.0	90.6
UP63	7.5	24.4	1.14	2500	0.5	1000	400	2.7	55.7	59.1	76.0	88.9	93.5
UP66	6.4	24.4	1.14	2050	10.0	1000	400	5.9	59.8	65.7	81.7	75.8	84.1
UP36	4.7	24.4	1.14	1680	7.0	1000	400	4.5	58.2	62.9	79.5	81.6	88.4
UP39	4.7	22.7	1.14	1680	7.0	1000	400	4.8	57.1	65.8	81.0	78.9	86.1
UP68	4.7	24.4	1.14	1680	7.0	1000	400	4.3	62.0	65.2	82.5	82.4	88.5
UP69	4.7	26.6	1.14	1680	7.0	1000	400	22.4	37.9	72.9	77.1	15.8	38.6
UP70	4.7	24.4	1.14	1680	7.0	1000	400	4.5	59.6	63.9	80.7	81.6	88.2
UP71	4.7	24.4	1.14	1680	7.0	1000	400	4.1	65.3	66.8	84.8	83.2	88.8
UP49	6.4	22.7	1.14	2050	10.0	800	400	4.9	56.9	65.8	80.9	78.4	85.8
UP56	6.4	22.7	1.14	2050	10.0	1000	400	4.9	58.7	66.9	82.3	78.4	85.6
UP60	6.4	23.4	1.14	2050	10.0	1500	400	7.3	60.5	69.7	84.4	68.8	78.2
UP59	6.4	23.4	1.14	2050	10.0	2050	400	13.2	65.0	80.3	91.0	43.6	54.7
UP81	4.7	23.4	1.14	2050	7.0	1000	500	3.9	53.4	60.6	76.0	83.3	89.9
UP80	4.7	23.4	1.14	2050	7.0	1320	500	5.9	53.3	63.1	77.5	74.8	84.1
UP79	4.7	23.4	1.14	2050	7.0	1733	500	5.6	62.7	68.8	84.8	76.1	83.5
UP77	4.7	23.4	1.14	2050	7.0	2050	500	6.8	63.6	70.8	86.1	70.9	79.4
=====													
L-ILL7	6.4	10.2	2.01	2050	10.0	1000	400	7.4	16.2	68.2	70.3	27.5	50.5
L-ILL8	6.4	10.2	2.01	2050	3.0	1000	400	7.7	14.1	60.9	62.6	24.5	54.0
L-ILL1	6.4	11.9	2.01	2050	15.0	1000	400	5.0	18.9	50.4	54.3	58.0	78.8
L-ILL11	6.4	10.8	2.01	2050	15.0	1000	400	7.5	18.4	69.7	72.3	30.6	51.6
L-ILL4	9.5	12.5	2.01	2050	15.0	1000	400	7.6	24.0	70.1	74.0	39.2	57.4
L-ILL9	6.4	10.5	2.01	2050	15.0	1000	400	7.9	22.1	81.7	84.1	24.8	38.5
L-ILL12A	6.4	10.3	2.01	2050	10.0	1000	400	8.3	15.9	73.7	75.3	19.4	40.6
L-ILL12	6.4	12.8	2.01	2050	10.0	1000	400	11.6	18.5	82.6	83.7	9.4	25.1
L-ILL14	4.7	12.8	2.01	1680	7.0	1000	400	7.3	16.3	38.9	41.3	43.0	77.8
L-ILL13	4.7	12.8	2.01	1680	7.0	1000	400	5.6	20.1	50.3	54.5	56.3	78.0
=====													
ILL1	6.5	26.4	2.74	2050	20.0	1000	400	16.0	50.5	69.9	79.7	39.4	57.7
ILL2	2.1	16.0	2.74	2050	20.0	1000	400	7.0	53.7	80.7	89.4	56.3	64.7
ILL3	6.5	26.0	2.74	2050	20.0	1000	400	18.6	39.6	64.8	71.2	28.5	53.7
ILL4	1.5	18.6	2.74	2050	20.0	1000	400	6.3	34.4	56.3	64.8	66.0	80.9

APPENDIX D
RESULTS FROM CONTINUOUS RESEARCH UNIT

*** Nomenclature ***

1. Af ---- Ash Content of Feed (%)
2. Ap ---- Ash Content of Product (%)
3. ARD ---- Ash Reduction (%),
 $ARD = (1 - Ap / Af) * 100$
4. BTUR ---- BTU Recovery (%),
 $BTUR = Y * (1 - Ap) / (1 - Af)$
 $Y = (Wt.of Product / Wt.of Feed) * 100$
5. CT ---- Coal Throughput (g/hr)
6. FC ---- Feed Concentration (%)
7. FCO2m ---- CO2 Flowrate into the Mixing Tank (g/min)
8. FCO2s ---- CO2 Flowrate into the Separation Column (g/min)
9. FIP ---- Feed Inj. Point (Relative to Top of the Column, in)
10. I ---- Interface Position (Relative to Top of the Column, in)
11. ICO2 ---- CO2 Inj. Point (Relative to Top of the Column, in)
12. NMT ---- Mixing Speed in the Mixing Tank (rpm)
13. NSC ---- Mixing Speed in the Separation Column (rpm)
14. PSf ---- Pyritic Sulphur content of Feed (%)
15. PSp ---- Pyritic Sulphur Content of Product (%)
16. PSRD ---- Pyritic Sulphur Reduction (%),
 $PSRD = (1 - PSp / PSf) * 100$

TEST No	CT g/hr	FC %	FIP in	I in	FCO2m g/min	FCO2s g/min	NMT rpm	NSC rpm	BTUR %	Af %	Ap %	ARD %	PSf %	PSP %	PSRD %
31	654	4.8	--	12	---	800	---	800	36	14.2	4.0	72	1.7	0.39	76.8
31	654	4.8	--	12	---	1000	---	800	44	14.2	4.1	71	1.7	0.39	76.8
33	634	4.8	--	12	---	1200	---	800	37	14.2	3.5	75	1.7	0.37	78.0
34	761	5.9	--	12	---	1200	---	800	40	14.2	3.2	77	1.7	0.36	78.6
34	761	5.9	--	12	---	1200	---	800	52	14.2	3.2	77	1.7	0.37	78.0
53	554	4.6	16	14	0	1600	1600	800	50	16.6	5.2	69	--	--	--
53	554	4.6	16	14	115	1485	1600	800	57	16.6	5.9	64	--	--	--
53	554	4.6	16	14	230	1370	1600	800	69	16.6	6.6	60	--	--	--
53	554	4.6	16	14	230	970	1600	800	75	16.6	6.5	61	--	--	--
54	565	4.4	16	14	230	970	1600	800	74	16.6	6.1	63	--	--	--
54	565	4.4	16	14	115	1085	1600	800	69	16.6	6.1	63	--	--	--
54	565	4.4	16	14	0	1200	1600	800	59	16.6	6.1	63	--	--	--
54	924	4.4	16	14	0	1200	1600	800	55	16.6	6.1	63	--	--	--
54	924	4.4	16	14	115	1085	1600	800	52	16.6	6.1	63	--	--	--
55	1108	4.7	16	14	0	1600	1600	800	64	16.6	5.7	66	--	--	--
55	1108	4.7	16	14	115	1485	1600	800	55	16.6	5.7	66	--	--	--
55	1108	4.7	16	14	230	1370	1600	800	53	16.6	6.4	61	--	--	--
57	618	4.7	16	14	350	850	1600	800	50	16.6	6.3	62	--	--	--
57	618	4.7	16	14	350	1250	1600	800	93	16.6	6.4	61	--	--	--
57	618	4.7	16	14	350	850	1600	800	82	16.6	6.5	61	--	--	--
57	1083	4.7	16	14	350	850	1600	800	42	16.6	6.7	60	--	--	--
57	1083	4.7	16	14	230	970	1600	800	51	16.6	7.0	58	--	--	--
57	1083	4.7	16	14	115	1085	1600	800	52	16.6	6.7	60	--	--	--
59	600	4.9	16	8	50	350	1600	800	54	16.6	5.1	69	--	--	--
59	600	4.9	16	8	100	100	1600	800	55	16.6	5.6	66	--	--	--
59	600	4.9	16	6	50	150	1600	800	69	16.6	7.7	54	--	--	--

61	590	4.8	16	8	100	100	1600	800	75	16.6	6.5	61	--	--	--
61	590	4.8	16	10	100	100	1600	800	44	16.6	5.9	64	--	--	--
61	590	4.8	16	10	200	100	1600	800	71	16.6	6.3	62	--	--	--
62	565	4.6	16	8	100	100	1600	800	96	16.6	6.7	60	--	--	--
62	565	4.6	16	8	100	100	1600	600	80	16.6	7.8	53	--	--	--
62	565	4.6	16	8	200	100	1600	800	96	16.6	6.9	58	--	--	--
62	565	4.6	16	10	200	100	1600	800	83	16.6	6.2	63	--	--	--
62	565	4.6	16	12	200	100	1600	800	61	16.6	5.9	64	--	--	--
62	565	4.6	16	12	300	100	1600	800	70	16.6	6.1	63	--	--	--
64	544	4.6	20	8	100	100	1600	800	73	16.6	7.3	56	--	--	--
64	544	4.6	20	8	100	100	1200	800	69	16.6	7.4	55	--	--	--
65	558	4.6	20	8	100	100	1600	1000	63	16.6	7.5	55	--	--	--
65	558	4.6	20	8	100	100	1600	800	63	16.6	8.1	51	--	--	--
65	558	4.6	20	8	100	100	2000	800	80	16.6	8.7	48	--	--	--
66	599	4.6	16	10	200	100	1600	800	87	16.6	7.0	58	--	--	--
66	599	4.6	16	14	200	100	1600	800	48	16.6	6.0	64	--	--	--
67	647	4.9	16	14	200	100	1600	800	49	16.6	5.7	66	2.1	0.48	77.1
67	647	4.9	16	14	200	100	1600	800	45	16.6	5.8	65	2.1	0.48	77.1
67	647	4.9	16	14	200	200	1600	800	61	16.6	6.0	64	2.1	0.45	78.6
67	647	4.9	16	14	200	300	1600	800	73	16.6	6.2	63	2.1	0.50	76.2
67	647	4.9	16	18	200	300	1600	800	50	16.6	5.5	67	2.1	0.45	78.6
67	647	4.9	16	18	200	300	1600	800	51	16.6	5.4	67	2.1	0.44	79.0
67	647	4.9	16	18	300	300	1600	800	64	16.6	5.5	67	2.1	0.48	77.1
68	596	4.6	12	14	200	100	1600	800	25	16.6	5.6	66	2.1	0.47	77.6
68	596	4.6	12	14	300	100	1600	800	21	16.6	5.6	66	2.1	0.48	77.1
68	596	4.6	12	14	300	200	1600	800	48	16.6	5.6	66	2.1	0.48	77.1
68	596	4.6	12	14	300	300	1600	800	80	16.6	5.7	66	2.1	0.48	77.1
68	596	4.6	12	14	300	300	1600	800	63	16.6	5.3	68	2.1	0.49	76.7
68	596	4.6	12	14	300	300	1600	800	68	16.6	5.9	64	2.1	0.52	75.2

70	558	4.6	12	16	300	300	1600	800	56	16.6	5.3	68	2.1	0.45	78.6
71	609	5.0	12	14	300	300	1600	600	71	16.6	5.6	66	2.1	0.46	78.1
71	609	5.0	12	14	300	300	1600	600	64	16.6	5.7	66	2.1	0.46	78.1
71	609	5.0	12	14	100	300	1600	600	79	16.6	5.6	66	2.1	0.46	78.1
71	609	5.0	12	14	100	300	1600	600	74	16.6	5.8	65	2.1	0.48	77.1
71	609	5.0	12	14	50	300	1600	600	72	16.6	4.9	70	2.1	0.45	78.6
71	609	5.0	12	14	0	300	1600	600	43	16.6	4.5	73	2.1	0.44	79.0
71	609	5.0	12	14	0	600	1600	600	62	16.6	5.6	66	2.1	0.44	79.0
72	651	5.0	12	14	50	500	1600	800	68	16.6	5.6	66	2.1	0.48	77.1
72	651	5.0	12	16	50	500	1600	800	64	16.6	5.1	69	2.1	0.46	78.1
72	651	5.0	12	18	50	500	1600	800	57	16.6	4.6	72	2.1	0.45	78.6
72	651	5.0	12	18	50	500	2000	800	46	16.6	4.4	73	2.1	0.44	79.0
72	651	5.0	12	18	50	500	1200	800	66	16.6	5.1	69	2.1	0.46	78.1
72	651	5.0	12	18	50	500	1200	1000	34	16.6	4.5	73	2.1	0.44	79.0
73	1392	5.1	12	14	100	300	1600	800	41	16.6	5.4	67	2.1	0.47	77.6
73	1392	5.1	12	14	100	400	1600	800	47	16.6	5.4	67	2.1	0.46	78.1
73	1392	5.1	12	14	100	300	1600	800	53	16.6	5.6	66	2.1	0.48	77.1
74	1337	5.1	12	18	100	400	1600	800	28	16.6	5.6	66	2.1	0.45	78.6
74	1337	5.1	12	18	100	400	1200	800	31	16.6	5.2	69	2.1	0.44	79.0
74	1337	5.1	12	18	150	650	1200	800	46	16.6	5.3	68	2.1	0.45	78.6
75	1388	5.2	12	18	200	600	1200	800	35	16.6	5.4	67	2.1	0.46	78.1
75	1388	5.2	12	18	200	600	2000	800	35	16.6	5.5	67	2.1	0.47	77.6
75	1388	5.2	12	18	200	600	1200	600	45	16.6	5.1	69	2.1	0.43	79.5
75	1388	5.2	12	18	200	600	1200	1000	33	16.6	5.2	69	2.1	0.44	79.0
76	1235	4.9	12	14	100	800	1200	600	56	16.6	5.6	66	2.1	0.45	78.6
76	1235	4.9	12	14	200	700	1200	600	71	16.6	5.7	66	2.1	0.48	77.1
76	1235	4.9	12	14	300	600	1200	600	79	16.6	5.4	67	2.1	0.48	77.1
77	2493	9.4	12	14	300	600	1200	600	32	16.6	5.9	64	2.1	0.49	76.7

78	2596	10.3	12	14	300	500	2000	600	31	16.6	6.4	61	2.1	0.56	73.3
78	2596	10.3	12	14	600	200	1200	600	35	16.6	5.9	64	2.1	--	--

APPENDIX E

GRINDING ENERGY CORRELATION

Grinding energy per ton of coal was calculated using the following algorithm:

$$Y = 10^{2.27 - 1.673 (\log X) + 0.412 (\log X)^2 - 0.033 (\log X)^3}$$

where

Y = grinding cost, \$/ton

X = particle size, micron

log = logarithm to the base 10

This algorithm was obtained by curve fitting a plot of specific energy vs. product size obtained from the following reference:

"Comminution and Energy Consumption, National Materials Advisory Board, Publication NMAB-364, National Academy Press, Washington, DC, 1981

This plot is provided on the following page.

Reported Energy Requirements for Size Reduction Tasks

```

C      LICADO PLANT SIMULATION
      DIMENSION DATA(50),R(1000),AM(1000),LEM(1000),WT(100),
1      SR(1000),AS(100),LES(1000),DIAM(12,80),AR(12,80),VEL(12,80),
1      WTS(100),VM1(1000),VS1(1000),C1(12),RHO(12),C2(12),CL(11)
      INTEGER N,P,Q,QA,J1,J2,IND1,IND2,N1
      REAL M,MS,K1,K2,K3,L,LR,LM,PS,OS,A,SF,F1,F2,LEMM,LES,LESM,LEM,
1      MOIST,HV
      OPEN(5,FILE='INPUT.DAT')
      OPEN(6,FILE='OUTP.DAT')
      OPEN(7,FILE='FLOWST.DAT')
      WRITE(6,110)
110     FORMAT(24X,'LICADO PLANT SIMULATION')
      WRITE(6,111)
111     FORMAT(1X)
      DATA A /0.0398/, M /0.0074/, PS /0.0056/, OS /0.0048/,
1      F1 /0.90/, F2 /0.90/, SF /0.0001/, CA /2000.0/, SZ /73.0/,
1      SCONC /0.1000/, TM /100.0/, TS /500./, X1 /0.900/, Y /0.995/,
1      Z /0.002/, Z2 /0.990/, Z3 /0.005/, PR2 /850./, PR1 /14.7/
1      MS /1200./, LR /0.500/, X2 /0.999/, F4 /0.001/, F3 /0.95/, Y2 /0.0001/
1      RHO(1) /47.4/, RHO(2) /61.7/, RHO(3) /48.7/, RHO(4) /62.4/, RHO(5) /62.4/,
1      RHO(6) /47.4/, HV /13000./
      WRITE(6,120)
120     FORMAT(23X,'PITTSBURGH-BRUCETON COAL')
      WRITE(6,130)
130     FORMAT(6X,'ASH',5X,'MOISTURE',2X,'PYR SUL',3X,'ORG SUL',
1      2X,'SULFATES',2X,'FRACT ASH',2X,'FRAC PSUL')
      WRITE(6,140) A,M,PS,OS,SF,F1,F2
140     FORMAT(7F10.4)
      WRITE(6,160)
160     FORMAT(5X,'CLEAN COAL PRODUCTION RATE, LB/HR',10X,'COAL HEATING V
1      ALUE')
      WRITE(6,170) CA,HV
170     FORMAT(15X,1F10.1,23X,1F10.2)
      WRITE(6,171)
171     FORMAT(1X)
      WRITE(6,180)
180     FORMAT(26X,'PLANT CHARACTERISTICS')
      WRITE(6,200)
200     FORMAT(1X,'PART.SIZE',1X,'SLURRY CONC',1X,'MIXER TIME',
1      1X,'SEPAR TIME',1X,'FR COAL/CO2',1X,'FR CO2/CO2')
      WRITE(6,210) SZ,SCONC,TM,TS,X1,Y
210     FORMAT(6F11.4)
      WRITE(6,230)
230     FORMAT('FR H2O/CO2',1X,'FRH2O/DEW',1X,'FR CO2/H2O',
1      1X,'SEP PRESS',1X,'INIT PRES',1X,'MIX SPD',2X,'CO2/SLURRY')
      WRITE(6,240) Z,Z2,Z3,PR2,PR1,MS,LR
240     FORMAT(1F8.6,2F10.4,1F12.1,1F9.1,1F11.1,1F8.4)
      WRITE(6,231)
231     FORMAT(1X,'COAL FRAC SEP AT FILTER')
      WRITE(6,232) X2
232     FORMAT(6X,1F10.4)
C      CALCULATION OF GRINDING/WATER SLURRY SYSTEM
C      SLURRY CONCENTRATION (SCONC) = C/(C+W)
      FA=(1.-F1)*A
      FS=(1.-F2)*PS
      FM=(1.-F3)*M
      CL(1)=CA/X1+CA*(F1*A+F2*PS+F3*M)/X1
      DO 205 N1=1,10
      CL(N1+1)=CA/X1 + CL(N1)*(F1*A+F2*PS+F3*M)/X1
205     CONTINUE
      C=CL(11)
C      The above "do loop" is used to iteratively calculate the coal feed
      W=C*(1.-SCONC)/SCONC

```

```

WM=(1.-Z)*(1.-Z2)*W+(X1*C*(1.-F3)*M)
WR=W-WM
C WR is recycle water from the Dewatering Unit
C The equation below for the grinding power was obtained by curve
C fitting published data for grinding power as a function of C part

YX1=1.673*YX
YX2=0.412*YX*YX
YX3=0.033*YX*YX*YX
PX1=(10.0)**(2.27-YX1+YX2-YX3)
P1=PX1*(C/2000.0)
WRITE(6,233)
233 FORMAT(1X)
WRITE(6,234)
234 FORMAT(1X)
WRITE(6,241)
241 FORMAT(25X,'PLANT OPERATING DATA')
WRITE(6,235)
235 FORMAT(1X)
WRITE(6,242)
242 FORMAT(24X,'GRINDING/SLURRY SYSTEM')
WRITE(6,236)
236 FORMAT(1X)
WRITE(6,243)
243 FORMAT(10X,'COAL FEED',5X,'WATER RATE',5X,'MK-UP WTR',5X,
1 'GRINDER PW')
WRITE(6,237)
237 FORMAT(1X)
WRITE(6,244) C,W,WM,P1
244 FORMAT(9X,1F10.2,5X,1F10.2,3X,1F10.2,5X,1F10.2)
C CALCULATION OF THE MIXING SYSTEM
L=LR*(C+W)
LM=L-Y*L+(1.-Y)*Z3*L
C P2 =power required by the Slurry Pump
C K2 = conversion constant for slurry pump power
C Value of K2 assumed for now;also value of RHOC
K2=1544.
RHOC=52.
RHOW=62.4
RHOCL=87.4
C CHECK THESE VALUES BEFORE RUNNING PROGRAM
P2=K2*(W+C)*(PR2-PR1)
VF=(W/RHOW)+(L/RHOC)+(C/RHOCL)
VM=TM*VF*1728./3600.
C OPTIMIZATION OF MIXER AND SEPARATOR
C MATERIAL =SA 516,GRADE 70 CARBON STEEL
C ALLOWABLE STRESS=17500 psi:ASME UNFIRED PRESSURE VESSEL CODE
R(1)=0.0

DO 300 N=2,1000
  IF(VM.GE.60000.) THEN
    GOTO 302
  ENDIF
  CONTINUE
  R(N)=0.01+R(N-1)
  GOTO 303
302 R(N)=0.1+R(N-1)
303 AM(N)=3.1416*R(N)*R(N)
  LEM(N)= 20.*R(N)
  VM1(N)=3.1416*R(N)*R(N)*LEM(N)

300 CONTINUE

```

```

DO 310 J1=2,1000
IF(VM .LE.VM1(J1)) THEN

GOTO 315
ENDIF
310 CONTINUE
315 IND1=J1
RM=R(IND1)
LEMM=LEM(IND1)
TD=PR2*R(IND1)/(17500.-0.6*PR2)
TH=2.0*PR2*R(IND1)/(2.0*17500.-0.2*PR2)

C OPTIMIZATION OF SEPARATOR SYSTEM
VS=TS*VF*1728. /3600.

SR(1)=0.0
DO 400 Q=2,1000
IF(VS.GE.60000.) THEN
GOTO 402
ENDIF
CONTINUE

SR(Q)=0.01 +SR(Q-1)
GOTO 403
402 SR(Q)=0.1+SR(Q-1)
403 LES(Q)=20.0*SR(Q)
VS1(Q)=3.1416*SR(Q)*SR(Q)*LES(Q)
400 CONTINUE
DO 410 J2=1,1000
IF(VS .LE.VS1(J2)) THEN
GOTO 416
ENDIF
CONTINUE
410 IND2=J2
416 LESM=LES(IND2)
SRM=SR(IND2)
TSH=2.0*PR2*SR(IND2)/(2.0*17500.-0.2*PR2)
TSD=PR2*SR(IND2)/(17500.-0.6*PR2)
CONTINUE
C CO2 STREAM LEAVING SEPARATOR
CAS=X1*(1.-(FA+FS+FM+OS+SF))*C
CO2S=CAS+Y*L+Z*W
WATERS=(1.-Z)*W+(1.-Y)*L+(F1*A+F2*PS+F3*M)*C +(1.-X1)*C
CO1=Y*L
WAT1=Z*W
WRITE(6,417)
417 FORMAT(1X)
WRITE(6,450)
450 FORMAT(20X,'SEPARATOR FLOWS,LBS/HR')
WRITE(6,460)
460 FORMAT(25X,'CO2 STREAM')
WRITE(6,470)
470 FORMAT(12X,'CLEANED COAL',10X,'CO2',15X,'WATER')
WRITE(6,480) CAS,CO1,WAT1
480 FORMAT(12X,1F10.2,6X,1F10.2,14X,1F10.2)
WAT2=W
C The above equation for WAT2 assumes that the dissolved CO2 reaches
C steady-state
CO2=(1.-Y)*L
ASH=(F1*A+F2*PS)*C
COAL=(1.-X1)*C
WRITE(6,490)
490 FORMAT(24X,'WATER STREAM')
WRITE(6,500)

```

```

500  FORMAT(7X,'WATER',13X,'ASH',15X,'CO2',16X,'COAL')
    WRITE(6,510)WAT2,ASH,CO2,COAL
510  FORMAT(5X,1F10.2,5X,1F10.2,8X,1F10.2,8X,1F10.2)
C    CYCLONE FLOWS: 35% OVERFLOW,65%UNDERFLOW,3%SOLIDS OVERFLOW
    COCYO=0.65*CO1
    CASCYO=0.03*CAS
    COCYU=0.35*CO1
    CASCYU=CAS
    WRITE(6,501)
501  FORMAT(1X)
    WRITE(6,512)
512  FORMAT(24X,'CYCLONE FLOWS')
    WRITE(6,513)
513  FORMAT(2X,'CO2 OVERFLOW',5X,'COAL OVERFLOW',5X,'CO2 UNDERFLOW',
1    5X,'COAL UNDERFLOW')
    WRITE(6,514) COCYO,CASCYO,COCYU,CASCYU
514  FORMAT(2X,1F10.2,8X,1F10.2,7X,1F10.2,6X,1F10.2)
C    STREAMS LEAVING THE FILTER
    PROD=X1*C + Y2*X1*C
    CO3=(1.+Z)*COCYU-Y2*CASCYU+(1.-X2)*CASCYU
    CO4=CO3 -Z*COCYU-(1.-X2)*CASCYU
    CO5=Y2*CASCYU
C    CO3=TOTAL CO2 RECYCLE STREAM,CO4= CO2 FLOW IN CO2 RECYCLE STREAM
C    CO5=ADSORBED CO2 ON PRODUCT COAL
    WAT4=Z*COCYU
    COAL4=(1.-X2)*CASCYU
    ASH=X1*C*(1.-F1)*A
    MOIST=X1*C*(1.-F3)*M
    TSULF=X1*C*(1.-F2)*PS +(OS+SF)*X1*C
    SBTU=TSULF*1000000./(HV*CA)
    WRITE(6,511)
511  FORMAT(1X)
    WRITE(6,520)
520  FORMAT(22X,'FILTER FLOWS,LBS/HR')
    WRITE(6,530)
530  FORMAT(1X,'TOTAL CO2 STR',7X,'CO2',16X,
1    'WATER',11X,'COAL')
    WRITE(6,540)CO3,CO4,WAT4,COAL4
540  FORMAT(1F12.2,1X,1F12.2,7X,1F12.2,6X,1F12.2)
    WRITE(6,565)
565  FORMAT(1X)
    WRITE(6,550)
550  FORMAT(30X,'PRODUCT RATE')
    WRITE(6,560)
560  FORMAT(6X,'TOTAL PRODUCT',12X,'CLEAN COAL',13X,'ADSORBED CO2')
    WRITE(6,570)PROD,CA,CO5
570  FORMAT(3X,1F12.2,12X,1F12.2,12X,1F12.2)
    WRITE(6,571)
571  FORMAT(3X,'MOISTURE',10X,'ASH',10X,'TOTAL SULFUR',7X,
1    'LB S/MM BTU')
    WRITE(6,572) MOIST,ASH,TSULF,SBTU
572  FORMAT(1X,1F8.2,5X,1F10.2,7X,1F10.2,7X,1F10.2)
C    STREAMS LEAVING THE DEWATERING UNIT
    WAT6=(1.-Y)*L*Z2+(1.-Z)*Z2*W+F3*M*C
    WAT6N=(1.-Z)*(1.-Z2)*W
    CO6=Z2*(1.-Y)*L
C    WAT6=TOTAL FLOW IN THE WATER STREAM;WAT6N=WATER FLOW IN THE REFUSE
    COAL7=(1.-X1)*(1.-(FA+FS+FM))*C
    ASH7=(F1*A+F2*S)*C
    WAT7=(1.-Z2)*W+(1.-Z2)*(1.-F3)*M*C
    CO7=(1.-Z2)*(1.-Y)*L
    SOLTOT=COAL7+ASH7+WAT7+CO7
    WRITE(6,561)
561  FORMAT(1X)
    WRITE(6,580)
580  FORMAT(28X,'DEWATERING UNIT')

```

```

      WRITE(6,585)
585    FORMAT(30X,'SOLIDS')
      WRITE(6,590)
590    1  FORMAT('TOTAL SOLIDS STREAM',3X,'WATER',9X,'ASH',14X,'CO2',
      9X,'COAL')
      WRITE(6,600)SOLTOT,WAT7,ASH7,CO7,COAL7
600    FORMAT(5F14.2)
      WRITE(6,610)
610    FORMAT(29X,'WATER RECYCLE')
      WRITE(6,620)
620    FORMAT(7X,'TOTAL FLOW',19X,'WATER FLOW',19X,'CO2')
      WRITE(6,630)WAT6,WAT6N,CO6
630    FORMAT(7X,1F10.2,20X,1F10.2,12X,1F10.2)
      WRITE(6,640)
640    FORMAT(30X,'DEGASSED CO2')
      CO8=F4*(1.-Z)*W
      WRITE(6,650)CO8
650    FORMAT(25X,1F10.2)
      WRITE(6,651)
651    FORMAT(1X)
      WRITE(6,800)
800    FORMAT(16X,'MIXER DIMENSIONS,INCHES')
      WRITE(6,810)
810    FORMAT(5X,'LENGTH',5X,'RADIUS',3X,'WALL THICK',3X,'HEAD THICK')
      WRITE(6,820)LEMM,RM,TD,TH
820    FORMAT(4E12.4)
      WRITE(6,830)
830    FORMAT(15X,'SEPARATOR DIMENSIONS')
      WRITE(6,840)
840    FORMAT(5X,'LENGTH',5X,'RADIUS',3X,'WALL THICK',3X,'HEAD THICK')
      WRITE(6,850)LESM,SRM,TSD,TSH
850    FORMAT(4E12.4)
C      PROGRAM PIPOPT.FOR
C      THIS PART OF THE PROGRAM OPTIMIZES THE LICADO PLANT PIPING TO PROVIDE A
C      FLOW VELOCITY OF 5 FT/SEC
      WRITE(6,860)
860    FORMAT(1X)
      WRITE(6,861)
861    FORMAT(1X)
      WRITE(6,901)
901    FORMAT(30X,'PIPING DIMENSIONS')
      WRITE(6,903)
903    FORMAT(1X)
      WRITE(6,902)
902    FORMAT(30X,'LINE',8X,'DIAM')
      C1(1)=L
      C1(2)=W+C
      C1(3)=CO3
      C1(4)=W
      C1(5)=WAT6
      C1(6)=LM

      DIAM(1,1)=0.0
      DO 920 N1=1,6
      C2(N1)=C1(N1)/(RHO(N1)*3600.)
      DO 900 N2=2,80
      DIAM(N1,N2)=0.5 +DIAM(N1,N2-1)
      AR(N1,N2)=3.1416*DIAM(N1,N2)*DIAM(N1,N2)/(4.*144.)
      VEL(N1,N2)=C2(N1)/AR(N1,N2)
      IF(VEL(N1,N2)-5.0) 910,910,900

900    CONTINUE
910    WRITE(6,911) N1, DIAM(N1,N2)

```

```

911 FORMAT(30X,1I2,4X,1F10.2)
920 CONTINUE
    WRITE (6,931)
931 FORMAT(2X)
    WRITE (6,932)
932 FORMAT(20X,'LINE 1=CO2 FROM CYCLONE TO MIXER')
    WRITE (6,933)
933 FORMAT(20X,'LINE 2=FEED FROM SLURRY TANK TO MIXER')
    WRITE (6,934)
934 FORMAT(20X,'LINE 3=CO2/COAL FROM SEPARATOR TO CYCLONE')
    WRITE(6,935)
935 FORMAT(20X,'LINE 4=WATER FROM RECYCLE TANK TO GRINDER')
    WRITE(6,936)
936 FORMAT(20X,'LINE 5=WATER FROM REFUSE LETDOWN TO RECYCLE TANK')
    WRITE (6,937)
937 FORMAT (20X,'LINE 6=CO2 MAKE-UP LINE')
    AC=A*C
    SC=(PS+OS+SF)*C
    CM=M*C
    SRF=F2*PS*C
    CO9=CO5+CO8
    CORCY=COCYO+CO4
    ASHR=F1*A*C

C    THIS SECTION WRITES A SEPARATE FILE, FLOWST.DAT, FOR TRANSFER OF
C    THE DATA TO THE CADD SYSTEM
    WRITE(7,731)
731 FORMAT(24X,'LICADO PLANT SIMULATION')
    WRITE(7,732)
732 FORMAT(23X,'PITTSBURGH-BRUCETON COAL')
    WRITE(7,733) CA
733 FORMAT(22X,'PRODUCTION RATE, LB/HR=',1F6.1)
    WRITE(7,710)
710 FORMAT(14X,'1',9X,'2',9X,'3',9X,'4',9X,'5',9X,'6',9X,'7',9X,'8')
    WRITE(7,711)
711 FORMAT(13X,'FEED',4X,'GRNDR',6X,'SLURRY',4X,'MIXER',4X,'CO2 RCY',
14X,'SEP PR',3X,'SEP RF',5X,'CYL OV')
    WRITE(7,712) C,C,C,C
712 FORMAT('RAW COAL',E10.4,E10.4,E10.4,E10.4)
    WRITE(7,713) CA,COAL,CASCYO
713 FORMAT('CLN COAL',50X,3E10.4)
    WRITE(7,714) CM,WR,W, W,WAT1,WAT2
714 FORMAT('WATER',3X,2E10.4,E10.4,E10.4,E10.4,10X,1E10.4)
    WRITE(7,715) L,L,CO1,CO2,COCYO
715 FORMAT('CO2-liq ',30X,1E10.4,1E10.4,1E10.4,2E10.4)
    WRITE(7,716) CO5
716 FORMAT('CO2-gas ',50X,1E10.4)
    WRITE(7,717) AC,AC,AC,AC,ASH,ASHR
717 FORMAT('ASH',5X,4E10.4,10X,2E10.4)
    WRITE(7,718) SC,SC,SC,SC,TSULF,SRF
718 FORMAT('SULFUR',2X,4E10.4,10X,1E10.4,2E10.4)
    WRITE(7,719)
719 FORMAT(1X)
    WRITE(7,720)
720 FORMAT(1X)
    WRITE(7,721)
721 FORMAT( 14X,'9',9X,'10',8X,'11',8X,'12',8X,'13',8X,'14',8X,'15',8
1X,'16')
    WRITE(7,722)
722 FORMAT(10X,'PRODUCT',3X,'FLTR LIQ',2X,'REFUSE GAS',1X,'PROD GAS',
12X,'COMPRESS',3X,'REFUSE',3X,'RECYL WTR',2X,'MK UP WTR')
    WRITE(7,723)
723 FORMAT('RAW COAL')
    WRITE(7,724) CA,COAL4,COAL7
724 FORMAT('CLN COAL',2E10.4,30X,E10.4)
    WRITE(7,725) MOIST,WAT4,WAT6N,WR,WM

```



```
725  FORMAT('WATER',3X,2E10.4,30X,3E10.4)
      WRITE(7,726) CO4, CO9, CO6
726  FORMAT('CO2-liq',11X,1E10.4,20X,1E10.4,10X,1E10.4)
      WRITE(7,727) CO5, CO8, CO5, CO7
727  FORMAT('CO2-gas',1X,1E10.4,10X,2E10.4,10X,1E10.4)
      WRITE(7,728) ASH, ASHR
728  FORMAT('ASH',5X,1E10.4,40X,1E10.4)
      WRITE(7,729) TSULF, SRF
729  FORMAT('SULFUR',2X,1E10.4,40X,1E10.4)
```

```
CLOSE(UNIT=7)
CLOSE(UNIT=6)
CLOSE(UNIT=5)
STOP
END
```

LICADO PLANT SIMULATION

PITTSBURGH-BRUCETON COAL			
ASH	MOISTURE	PYR SUL	ORG SUL
.0398	.0074	.0056	.0048
CLEAN COAL PRODUCTION RATE, LB/HR		SULFATES	FRACT ASH
2000.0		.0001	.9000
		COAL HEATING VALUE	
		13000.00	

PLANT CHARACTERISTICS							
PART.SIZE	SLURRY	CONC	MIXER TIME	SEPAR TIME	FR COAL/CO2	FR CO2/CO2	
73.0000		.1000	100.0000	500.0000	.9000	.9950	
FR H2O/CO2	FRH2O/DEW	FR CO2/H2O	SEP PRESS	INIT PRES	MIX SPD	CO2/SLURRY	
.002000	.9900	.0050	850.0	14.7	1200.0	.5000	
COAL FRAC SEP AT FILTER							
.9990							

PLANT OPERATING DATA

GRINDING/SLURRY SYSTEM

COAL FEED	WATER RATE	MK-UP WTR	GRINDER PW
2347.11	21124.03	211.60	2.75

SEPARATOR FLOWS, LBS/HR

CO2 STREAM		WATER	
CLEANED COAL	CO2		
2091.68	11676.90		42.25
WATER STREAM		COAL	
WATER	ASH	CO2	
21124.03	95.90	58.68	234.71

CYCLONE FLOWS

CO2 OVERFLOW	COAL OVERFLOW	CO2 UNDERFLOW	COAL UNDERFLOW
7589.98	62.75	4086.91	2091.68

FILTER FLOWS, LBS/HR

TOTAL CO2 STR	CO2	WATER	COAL
4096.97	4086.70	8.17	2.09

PRODUCT RATE

TOTAL PRODUCT	CLEAN COAL	ADSORBED CO2
2112.61	2000.00	.21
MOISTURE	TOTAL SULFUR	LB S/MM BTU
.78	11.53	.44
ASH		
8.41		

DEWATERING UNIT

SOLIDS		WATER	
TOTAL SOLIDS STREAM	ASH	CO2	COAL
529.47	84.07	.59	233.56
WATER RECYCLE			
TOTAL FLOW	WATER FLOW	CO2	
20945.56	210.82	58.09	
DEGASSED CO2			
21.08			

MIXER DIMENSIONS, INCHES

LENGTH	RADIUS	WALL THICK	HEAD THICK
.1536E+03	.7680E+01	.3842E+00	.3749E+00
SEPARATOR DIMENSIONS			
LENGTH	RADIUS	WALL THICK	HEAD THICK
.2640E+03	.1320E+02	.6604E+00	.6443E+00

PIPING DIMENSIONS

LINE	DIAM
1	2.00
2	2.00
3	1.00
4	2.00
5	2.00
6	.50

LINE 1=CO2 FROM CYCLONE TO MIXER
 LINE 2=FEED FROM SLURRY TANK TO MIXER
 LINE 3=CO2/COAL FROM SEPARATOR TO CYCLONE
 LINE 4=WATER FROM RECYCLE TANK TO GRINDER
 LINE 5=WATER FROM REFUSE LETDOWN TO RECYCLE TANK
 LINE 6=CO2 MAKE-UP LINE

APPENDIX F

```

C      LICADO PLANT SIMULATION
      DIMENSION DATA(50),R(1000),AM(1000),LEM(1000),WT(100),
1      SR(1000),AS(100),LES(1000),DIAM(12,80),AR(12,80),VEL(12,80),
1      WTS(100),VM1(1000),VS1(1000),C1(12),RHO(12),C2(12),CL(11)
      INTEGER N,P,Q,QA,J1,J2,IND1,IND2,N1
      REAL M,MS,K1,K2,K3,L,LR,LM,PS,OS,A,SF,F1,F2,LEMM,LES,LESM,LEM,
1      MOIST,HV
      OPEN(5,FILE='INPUT.DAT')
      OPEN(6,FILE='OUTP.DAT')
      OPEN(7,FILE='FLOWST.DAT')
      WRITE(6,110)
110     FORMAT(24X,'LICADO PLANT SIMULATION')
      WRITE(6,111)
111     FORMAT(1X)
      DATA A /0.244/, M /0.0074/, PS /0.0200/, OS /0.0100/,
1      F1 /0.85/, F2 /0.85/, SF /0.0001/, CA /2000./, SZ /73.0/,
1      SCONC /0.1000/, TM /100.0/, TS /500./, X1 /0.900/, Y /0.995/,
1      Z /0.002/, Z2 /0.990/, Z3 /0.005/, PR2 /850./, PR1 /14.7/
1      MS /1200./, LR /0.500/, X2 /0.999/, F4 /0.001/, F3 /0.95/, Y2 /0.0001/
1      RHO(1) /47.4/, RHO(2) /61.7/, RHO(3) /48.7/, RHO(4) /62.4/, RHO(5) /62.4/,
1      RHO(6) /47.4/, HV /13000./
      WRITE(6,120)
120     FORMAT(23X,'UPPER FREEPORT COAL')
      WRITE(6,130)
130     FORMAT(6X,'ASH',5X,'MOISTURE',2X,'PYR SUL',3X,'ORG SUL',
1      2X,'SULFATES',2X,'FRACT ASH',2X,'FRAC PSUL')
      WRITE(6,140) A,M,PS,OS,SF,F1,F2
140     FORMAT(7F10.4)
      WRITE(6,160)
160     FORMAT(5X,'CLEAN COAL PRODUCTION RATE, LB/HR',10X,'COAL HEATING V
1      ALUE')
      WRITE(6,170) CA,HV
170     FORMAT(15X,1F10.1,23X,1F10.2)
      WRITE(6,171)
171     FORMAT(1X)
      WRITE(6,180)
180     FORMAT(26X,'PLANT CHARACTERISTICS')
      WRITE(6,200)
200     FORMAT(1X,'PART.SIZE',1X,'SLURRY CONC',1X,'MIXER TIME',
1      1X,'SEPAR TIME',1X,'FR COAL/CO2',1X,'FR CO2/CO2')
      WRITE(6,210) SZ,SCONC,TM,TS,X1,Y
210     FORMAT(6F11.4)
      WRITE(6,230)
230     FORMAT('FR H2O/CO2',1X,'FRH2O/DEW',1X,'FR CO2/H2O',
1      1X,'SEP PRESS',1X,'INIT PRES',1X,'MIX SPD',2X,'CO2/SLURRY')
      WRITE(6,240) Z,Z2,Z3,PR2,PR1,MS,LR
240     FORMAT(1F8.6,2F10.4,1F12.1,1F9.1,1F11.1,1F8.4)
      WRITE(6,231)
231     FORMAT(1X,'COAL FRAC SEP AT FILTER')
      WRITE(6,232) X2
232     FORMAT(6X,1F10.4)
C      CALCULATION OF GRINDING/WATER SLURRY SYSTEM
C      SLURRY CONCENTRATION (SCONC) = C/(C+W)
      FA=(1.-F1)*A
      FS=(1.-F2)*PS
      FM=(1.-F3)*M
      CL(1)=CA/X1+CA*(F1*A+F2*PS+F3*M)/X1
      DO 205 N1=1,10
      CL(N1+1)=CA/X1+CL(N1)*(F1*A+F2*PS+F3*M)/X1
205     CONTINUE
      C=CL(11)
C      The above "do loop" is used to iteratively calculate the coal feed
      W=C*(1.-SCONC)/SCONC

```

```

WM=(1.-Z2)*(1.-Z)*W+(X1*C*(1.-F3)*M)
WR=W-WM
C WR is the recycle water form the Dewatering Unit
C The equation below for the grinding power was obtained by curve
C fitting published data for grinding power as a function of
C particle size
YX=LOG10(SZ)
YX1=1.673*YX
YX2=0.412*YX*YX
YX3=0.033*YX*YX*YX
PX1=(10)**(2.27-YX1+YX2-YX3)
P1=PX1*(C/2000.0)
WRITE(6,233)
233 FORMAT(1X)
WRITE(6,234)
234 FORMAT(1X)
WRITE(6,241)
241 FORMAT(25X,'PLANT OPERATING DATA')
WRITE(6,235)
235 FORMAT(1X)
WRITE(6,242)
242 FORMAT(24X,'GRINDING/SLURRY SYSTEM')
WRITE(6,236)
236 FORMAT(1X)
WRITE(6,243)
243 FORMAT(10X,'COAL FEED',5X,'WATER RATE',5X,'MK-UP WTR',5X,
1 'GRINDER PW')
WRITE(6,237)
237 FORMAT(1X)
WRITE(6,244)C,W,WM,P1
244 FORMAT(9X,1F10.2,5X,1F10.2,3X,1F10.2,5X,1F10.2)
C CALCULATION OF THE MIXING SYSTEM
L=LR*(C+W)
LM=L-Y*L+(1.-Y)*Z3*L
C P2 =power required by the Slurry Pump
C K2 = conversion constant for slurry pump power
C Value of K2 assumed for now,also value of RHOC
K2=1544.
RHOC=52.
RHOW=62.4
RHOCL=87.4
C CHECK THESE VALUES BEFORE RUNNING PROGRAM
P2=K2*(W+C)*(PR2-PR1)
VF=(W/RHOW)+(L/RHOC)+(C/RHOCL)
VM=TM*VF*1728./3600.
C OPTIMIZATION OF MIXER AND SEPARATOR
C MATERIAL =SA 516, GRADE 70 CARBON STEEL
C ALLOWABLE STRESS=17500 psi:ASME UNFIRED PRESSURE VESSEL CODE
R(1)=0.0

DO 300 N=2,1000
  IF(VM.GE.60000.) THEN
    GOTO 302
  ENDIF
  CONTINUE
  R(N)=0.01+R(N-1)
  GOTO 303
302 R(N)=0.1+R(N-1)
303 AM(N)=3.1416*R(N)*R(N)
  LEM(N)= 20.*R(N)
  VM1(N)=3.1416*R(N)*R(N)*LEM(N)

300 CONTINUE

```

```

DO 310 J1=2,1000
IF(VM .LE.VM1(J1)) THEN

GOTO 315
ENDIF
310 CONTINUE
315 IND1=J1
RM=R(IND1)
LEMM=LEM(IND1)
TD=PR2*R(IND1)/(17500.-0.6*PR2)
TH=2.0*PR2*R(IND1)/(2.0*17500.-0.2*PR2)

C OPTIMIZATION OF SEPARATOR SYSTEM
VS=TS*VF*1728. /3600.

SR(1)=0.0
DO 400 Q=2,1000
IF(VS.GE.60000.) THEN
GOTO 402
ENDIF
CONTINUE

SR(Q)=0.01 +SR(Q-1)
GOTO 403
402 SR(Q)=0.1+SR(Q-1)
403 LES(Q)=20.0*SR(Q)
VS1(Q)=3.1416*SR(Q)*SR(Q)*LES(Q)
400 CONTINUE
DO 410 J2=1,1000
IF(VS .LE.VS1(J2)) THEN
GOTO 416
ENDIF
CONTINUE
410 CONTINUE
416 IND2=J2
LESM=LES(IND2)
SRM=SR(IND2)
TSH=2.0*PR2*SR(IND2)/(2.0*17500.-0.2*PR2)
TSD=PR2*SR(IND2)/(17500.-0.6*PR2)
CONTINUE
C CO2 STREAM LEAVING SEPARATOR
CAS=X1*(1.-(FA+FS+FM+OS+SF))*C
CO2S=CAS+Y*L+Z*W
WATERS=(1.-Z)*W+(1.-Y)*L+(F1*A+F2*PS+F3*M)*C +(1.-X1)*C
CO1=Y*L
WAT1=Z*W
WRITE(6,417)
417 FORMAT(1X)
WRITE(6,450)
450 FORMAT(20X,'SEPARATOR FLOWS,LBS/HR')
WRITE(6,460)
460 FORMAT(25X,'CO2 STREAM')
WRITE(6,470)
470 FORMAT(12X,'CLEANED COAL',10X,'CO2',15X,'WATER')
WRITE(6,480) CAS,CO1,WAT1
480 FORMAT(12X,1F10.2,6X,1F10.2,14X,1F10.2)
WAT2=W
C The above equation for WAT2 assumes that the water dissolved in
C CO2 has reached steady state.
CO2=(1.-Y)*L
ASH=(F1*A+F2*PS)*C
COAL=(1.-X1)*C
WRITE(6,490)
490 FORMAT(24X,'WATER STREAM')
WRITE(6,500)

```

```

500  FORMAT(7X,'WATER',13X,'ASH',15X,'CO2',16X,'COAL')
      WRITE(6,510)WAT2,ASH,CO2,COAL
510  FORMAT(5X,1F10.2,5X,1F10.2,8X,1F10.2,8X,1F10.2)
C    CYCLONE FLOWS: 35% OVERFLOW,65%UNDERFLOW,3%SOLIDS OVERFLOW
      COCYO=0.65*CO1
      CASCYO=0.03*CAS
      COCYU=0.35*CO1
      CASCYU=CAS
      WRITE(6,501)
501  FORMAT(1X)
      WRITE(6,512)
512  FORMAT(24X,'CYCLONE FLOWS')
      WRITE(6,513)
513  1  FORMAT(2X,'CO2 OVERFLOW',5X,'COAL OVERFLOW',5X,'CO2 UNDERFLOW',
      5X,'COAL UNDERFLOW')
      WRITE(6,514) COCYO,CASCYO,COCYU,CASCYU
514  C  FORMAT(2X,1F10.2,8X,1F10.2,7X,1F10.2,6X,1F10.2)
      STREAMS LEAVING THE FILTER
      PROD=X1*C + Y2*X1*C
      CO3=(1.+Z)*COCYU-Y2*CASCYU+(1.-X2)*CASCYU
      CO4=CO3 -Z*COCYU-(1.-X2)*CASCYU
      CO5=Y2*CASCYU
C    CO3=TOTAL CO2 RECYCLE STREAM,CO4= CO2 FLOW IN CO2 RECYCLE STREAM
C    CO5=ADSORBED CO2 ON PRODUCT COAL
      WAT4=Z*COCYU
      COAL4=(1.-X2)*CASCYU
      ASH=X1*C*(1.-F1)*A
      MOIST=X1*C*(1.-F3)*M
      TSULF=X1*C*(1.-F2)*PS +(OS+SF)*X1*C
      SBTU=TSULF*1000000./(HV*CA)
      WRITE(6,511)
511  FORMAT(1X)
      WRITE(6,520)
520  FORMAT(22X,'FILTER FLOWS,LBS/HR')
      WRITE(6,530)
530  1  FORMAT(1X,'TOTAL CO2 STR',7X,'CO2',16X,
      'WATER',11X,'COAL')
      WRITE(6,540)CO3,CO4,WAT4,COAL4
540  FORMAT(1F12.2,1X,1F12.2,7X,1F12.2,6X,1F12.2)
      WRITE(6,565)
565  FORMAT(1X)
      WRITE(6,550)
550  FORMAT(30X,'PRODUCT RATE')
      WRITE(6,560)
560  FORMAT(6X,'TOTAL PRODUCT',12X,'CLEAN COAL',13X,'ADSORBED CO2')
      WRITE(6,570)PROD,CA,CO5
570  FORMAT(3X,1F12.2,12X,1F12.2,12X,1F12.2)
      WRITE(6,571)
571  1  FORMAT(3X,'MOISTURE',10X,'ASH',10X,'TOTAL SULFUR',7X,
      'LB S/MM BTU')
      WRITE(6,572) MOIST,ASH,TSULF,SBTU
572  C  FORMAT(1X,1F8.2,5X,1F10.2,7X,1F10.2,7X,1F10.2)
      STREAMS LEAVING THE DEWATERING UNIT
      WAT6=(1.-Y)*L*Z2+(1.-Z)*Z2*W+F3*M*C
      WAT6N=(1.-Z)*(1.-Z2)*W
      CO6=Z2*(1.-Y)*L
C    WAT6=TOTAL FLOW IN THE WATER STREAM;WAT6N=WATER FLOW IN THE REFUSE
      COAL7=(1.-X1)*(1.-(FA+FS+FM))*C
      ASH7=(F1*A+F2*S)*C
      WAT7=(1.-Z2)*W+(1.-Z2)*(1.-F3)*M*C
      CO7=(1.-Z2)*(1.-Y)*L
      SOLTOT=COAL7+ASH7+WAT7+CO7
      WRITE(6,561)
561  FORMAT(1X)
      WRITE(6,580)
580  FORMAT(28X,'DEWATERING UNIT')

```



```

585     WRITE(6,585)
        FORMAT(30X,'SOLIDS')
        WRITE(6,590)
590     1  FORMAT('TOTAL SOLIDS STREAM',3X,'WATER',9X,'ASH',14X,'CO2',
        9X,'COAL')
        WRITE(6,600)SOLTOT,WAT7,ASH7,CO7,COAL7
600     FORMAT(5F14.2)
        WRITE(6,610)
610     FORMAT(29X,'WATER RECYCLE')
        WRITE(6,620)
620     FORMAT(7X,'TOTAL FLOW',19X,'WATER FLOW',19X,'CO2')
        WRITE(6,630)WAT6,WAT6N,CO6
630     FORMAT(7X,1F10.2,20X,1F10.2,12X,1F10.2)
        WRITE(6,640)
640     FORMAT(30X,'DEGASSED CO2')
        CO8=F4*(1.-Z)*W
        WRITE(6,650)CO8
650     FORMAT(25X,1F10.2)
        WRITE(6,651)
651     FORMAT(1X)
        WRITE(6,800)
800     FORMAT(16X,'MIXER DIMENSIONS,INCHES')
        WRITE(6,810)
810     FORMAT(5X,'LENGTH',5X,'RADIUS',3X,'WALL THICK',3X,'HEAD THICK')
        WRITE(6,820)LEMM,RM,TD,TH
820     FORMAT(4E12.4)
        WRITE(6,830)
830     FORMAT(15X,'SEPARATOR DIMENSIONS')
        WRITE(6,840)
840     FORMAT(5X,'LENGTH',5X,'RADIUS',3X,'WALL THICK',3X,'HEAD THICK')
        WRITE(6,850)LESM,SRM,TSD,TSH
850     FORMAT(4E12.4)
C      PROGRAM PIPOPT.FOR
C      THIS PART OF THE PROGRAM OPTIMIZES THE LICADO PLANT PIPING TO PROVIDE A
C      FLOW VELOCITY OF 5 FT/SEC
        WRITE(6,860)
860     FORMAT(1X)
        WRITE(6,861)
861     FORMAT(1X)
        WRITE(6,901)
901     FORMAT(30X,'PIPING DIMENSIONS')
        WRITE(6,903)
903     FORMAT(1X)
        WRITE(6,902)
902     FORMAT(30X,'LINE',8X,'DIAM')
        C1(1)=L
        C1(2)=W+C
        C1(3)=CO3
        C1(4)=W
        C1(5)=WAT6
        C1(6)=LM

        DIAM(1,1)=0.0
        DO 920 N1=1,6
        C2(N1)=C1(N1)/(RHO(N1)*3600.)
        DO 900 N2=2,80
        DIAM(N1,N2)=0.5 +DIAM(N1,N2-1)
        AR(N1,N2)=3.1416*DIAM(N1,N2)*DIAM(N1,N2)/(4.*144.)
        VEL(N1,N2)=C2(N1)/AR(N1,N2)
        IF(VEL(N1,N2)-5.0) 910,910,900

900     CONTINUE
910     WRITE(6,911) N1, DIAM(N1,N2)

```

```

911 FORMAT(30X,1I2,4X,1F10.2)
920 CONTINUE
    WRITE (6,931)
931 FORMAT(2X)
    WRITE (6,932)
932 FORMAT(20X,'LINE 1=CO2 FROM CYCLONE TO MIXER')
    WRITE (6,933)
933 FORMAT(20X,'LINE 2=FEED FROM SLURRY TANK TO MIXER')
    WRITE (6,934)
934 FORMAT(20X,'LINE 3=CO2/COAL FROM SEPARATOR TO CYCLONE')
    WRITE (6,935)
935 FORMAT(20X,'LINE 4=WATER FROM RECYCLE TANK TO GRINDER')
    WRITE (6,936)
936 FORMAT(20X,'LINE 5=WATER FROM REFUSE LETDOWN TO RECYCLE TANK')
    WRITE (6,937)
937 FORMAT (20X,'LINE 6=CO2 MAKE-UP LINE')
    AC=A*C
    SC=(PS+OS+SF)*C
    CM=M*C
    SRF=F2*PS*C
    CO9=CO5+CO8
    CORCY=COCYO+CO4
    ASHR=F1*A*C

C      THIS SECTION WRITES A SEPARATE FILE, FLOWST.DAT, FOR TRANSFER OF
C      THE DATA TO THE CADD SYSTEM
    WRITE(7,731)
731  FORMAT(24X,'LICADO PLANT SIMULATION')
    WRITE(7,732)
732  FORMAT(23X,'UPPER FREEPORT COAL')
    WRITE(7,733) CA
733  FORMAT(22X,'PRODUCTION RATE, LB/HR=',1F6.1)
    WRITE(7,710)
710  FORMAT(14X,'1',9X,'2',9X,'3',9X,'4',9X,'5',9X,'6',9X,'7',9X,'8')
    WRITE(7,711)
711  FORMAT(13X,'FEED',4X,'GPNDR',6X,'SLURRY',4X,'MIXER',4X,'CO2 RCY',
14X,'SEP PR',3X,'SEP RF',5X,'CYL OV')
    WRITE(7,712) C,C,C,C
712  FORMAT('RAW COAL',E10.4,E10.4,E10.4,E10.4)
    WRITE(7,713) CA,COAL,CASCYO
713  FORMAT('CLN COAL',50X,3E10.4)
    WRITE(7,714) CM,WR,W, W,WAT1,WAT2
714  FORMAT('WATER',3X,2E10.4,E10.4,E10.4,E10.4,10X,1E10.4)
    WRITE(7,715) L,L,CO1,CO2,COCYO
715  FORMAT('CO2-liq ',30X,1E10.4,1E10.4,1E10.4,2E10.4)
    WRITE(7,716) CO5
716  FORMAT('CO2-gas ',50X,1E10.4)
    WRITE(7,717) AC,AC,AC,AC,ASH,ASHR
717  FORMAT('ASH',5X,4E10.4,10X,2E10.4)
    WRITE(7,718) SC,SC,SC,SC,TSULF,SRF
718  FORMAT('SULFUR',2X,4E10.4,10X,1E10.4,2E10.4)
    WRITE(7,719)
719  FORMAT(1X)
    WRITE(7,720)
720  FORMAT(1X)
    WRITE(7,721)
721  FORMAT( 14X,'9',9X,'10',8X,'11',8X,'12',8X,'13',8X,'14',8X,'15',8
1X,'16')
    WRITE(7,722)
722  FORMAT(10X,'PRODUCT',3X,'FLTR LIQ',2X,'REFUSE GAS',1X,'PROD GAS',
12X,'COMPRESS',3X,'REFUSE',3X,'RECYL WTR',2X,'MK UP WTR')
    WRITE(7,723)
723  FORMAT('RAW COAL')
    WRITE(7,724) CA,COAL4,COAL7
724  FORMAT('CLN COAL',2E10.4,30X,E10.4)
    WRITE(7,725) MOIST,WAT4,WAT6N,WR,WM

```

```

725  FORMAT('WATER',3X,2E10.4,30X,3E10.4)
      WRITE(7,726) CO4, CO9, CO6
726  FORMAT('CO2-liq',11X,1E10.4,20X,1E10.4,10X,1E10.4)
      WRITE(7,727) CO5, CO8, CO5, CO7
727  FORMAT('CO2-gas',1X,1E10.4,10X,2E10.4,10X,1E10.4)
      WRITE(7,728) ASH, ASHR
728  FORMAT('ASH',5X,1E10.4,40X,1E10.4)
      WRITE(7,729) TSULF, SRF
729  FORMAT('SULFUR',2X,1E10.4,40X,1E10.4)

      CLOSE(UNIT=7)
      CLOSE(UNIT=6)
      CLOSE(UNIT=5)
      STOP
      END

```

LICADO PLANT SIMULATION

UPPER FREEPORT COAL

ASH	MOISTURE	PYR SUL	ORG SUL	SULFATES	FRACT ASH	FRAC PSUL
.2440	.0074	.0200	.0100	.0001	.8500	.8500
CLEAN COAL PRODUCTION RATE, LB/HR				COAL HEATING VALUE		
2000.0				13000.00		

PLANT CHARACTERISTICS

PART.SIZE	SLURRY CONC	MIXER TIME	SEPAR TIME	FR COAL/CO2	FR CO2/CO2
73.0000	.1000	100.0000	500.0000	.9000	.9950
FR H2O/CO2	FRH2O/DEW	FR CO2/H2O	SEP PRESS	INIT PRES	MIX SPD
.002000	.9900	.0050	850.0	14.7	1200.0
COAL FRAC SEP AT FILTER			CO2/SLURRY		
.9990			.5000		

PLANT OPERATING DATA

GRINDING/SLURRY SYSTEM

COAL FEED	WATER RATE	MK-UP WTR	GRINDER PW
2991.46	26923.13	269.69	3.50

SEPARATOR FLOWS, LBS/HR

CO2 STREAM		WATER	
CLEANED COAL	CO2		
2557.51	14882.51		53.85
WATER STREAM		COAL	
WATER	ASH	CO2	COAL
26923.13	671.28	74.79	299.15

CYCLONE FLOWS

CO2 OVERFLOW	COAL OVERFLOW	CO2 UNDERFLOW	COAL UNDERFLOW
9673.63	76.73	5208.88	2557.51

FILTER FLOWS, LBS/HR

TOTAL CO2 STR	CO2	WATER	COAL
5221.60	5208.62	10.42	2.56

PRODUCT RATE

TOTAL PRODUCT	CLEAN COAL	ADSORBED CO2
2692.58	2000.00	.26
MOISTURE	TOTAL SULFUR	LB S/MM BTU
1.00	35.27	1.36
ASH		
98.54		

DEWATERING UNIT

TOTAL SOLIDS STREAM	WATER	ASH	CO2	COAL
1177.61	269.24	620.43	.75	287.19
WATER RECYCLE		CO2		
TOTAL FLOW	WATER FLOW	CO2		
26695.66	268.69	74.04		
DEGASSED CO2				
26.87				

MIXER DIMENSIONS, INCHES

LENGTH	RADIUS	WALL THICK	HEAD THICK
.1664E+03	.8320E+01	.4162E+00	.4061E+00
SEPARATOR DIMENSIONS			
LENGTH	RADIUS	WALL THICK	HEAD THICK
.2860E+03	.1430E+02	.7154E+00	.6980E+00

PIPING DIMENSIONS

LINE	DIAM
1	2.00
2	2.50
3	1.50
4	2.50
5	2.50
6	.50

LINE 1=CO2 FROM CYCLONE TO MIXER
 LINE 2=FEED FROM SLURRY TANK TO MIXER
 LINE 3=CO2/COAL FROM SEPARATOR TO CYCLONE
 LINE 4=WATER FROM RECYCLE TANK TO GRINDER
 LINE 5=WATER FROM REFUSE LETDOWN TO RECYCLE TANK
 LINE 6=CO2 MAKE-UP LINE

APPENDIX G

APPENDIX G-1

LICADO Commercial Plant, 200 Ton/Hour Budgetary Cost Estimate, Fixed Capital

DIRECT COSTS

<u>Item/Components</u>	<u>Number of Units</u>	<u>Power (Hp)</u>	<u>Total Cost \$1000</u>
1. Raw Coal Preparation (Turn Key)	5 Systems	12,500	17,400.0
2. Filters (Pitt Auger)	16	240	3,491.7
3. Water Pump (Make-up) Piston	2	150	70.0
4. Water Pump (Recycle)	4	300	150.0
5. Slurry Feed Pump (Coal/Water)	2	400	450.0
6. CO ₂ Circulating Pump (Main)	2	300	325.0
7. CO ₂ Filtrate Pump (Not Shown)	4	40	315.0
8. Lock Hopper (Raw Coal)	2	-	455.4
9. Slurry Tanks (Coal/Water)	4	120	3,780.0
10. Hydraulic Mixer	4	-	40.0
11. Separator	4	-	1,583.6
12. Refuse Depressurizer	3	-	1,258.7
13. Recycle Water Vessel	2	-	1,850.0
14. Product Coal Vessel	2	-	1,775.8
15. Pressurizer	1	-	152.4
16. CO ₂ Accumulator	2	-	279.7
17. CO ₂ Recycle Compressor	2	700	550.0
18. Cyclones	10	-	325.0
19. Coolers	2	-	60.0
20. Filters (Gaseous)	5	-	40.0
21. Water Storage (Atmosphere)	1	-	150.0

		1000 Contingency	
(A) Total Components		15,750	34,502.3
(B) Installation (factor = 0.39A)			6,669.9
(C) Instrumentation (0.13A)			4,485.3
(D) Piping, Installed (0.31A)			10,695.6
(E) Electrical System (0.10A)			3,450.2
(F) Site Preparation (0.10A)			3,450.2
(G) Gen. Serv. & Utilities (Assumed)			5,000.0

Total Direct 68,253.3

INDIRECT COSTS

(H) Engineering & Supervision (0.20A)		6,900.4
(J) Construction (0.45A)		7,695.9
(Item 1 omitted, Turn Key)		
(K) Contractor's Fee (0.09A)		3,105.2
(L) Contingency (0.25A)		8,625.5

Total Indirect 26,327.0

Total Fixed Capital 94,580.5

APPENDIX G-2

Agglomeration Commercial Plant, 50 Ton/Hour Budgetary Cost Estimate, Fixed Capital

DIRECT COSTS

	<u>Item/Components</u>	<u>Number of Units</u>	<u>Power (Hp)</u>	<u>Total Cost \$1000</u>
1.	Cyclones	4-10's	-	100
2.	Slurry Feed Tanks	2	100	286
3.	Mixer	1	75	120
4.	Filter, Moving Screen	2	10	664
5.	Clean Coal Receiver	2	-	445
6.	Clean Coal Depressurizer	1	-	223
7.	CO ₂ Recycle Accumulator	1	-	70
8.	CO ₂ Recycle Compressor	1	800	397
9.	Pressurizer	1	-	77
10.	Water Pump, Concentration Adj'm't	1	5	1
11.	Slurry Pump, Coal/Water	1	150	173
12.	CO ₂ Circulating Pump	1	25	40
13.	Gas Filters	2	-	10
14.	Heat Exchanger	1	-	15
			235 Contingency	
			1400	2,621
(A)	Total Components			1,022
(B)	Installation (factor = 0.39A)			524
(C)	Instrumentation (0.20A)			813
(D)	Piping, Installed (0.31A)			262
(E)	Electrical System (0.10A)			262
(F)	Site Preparation (0.10A)			655
(G)	Gen. Serv. & Utilities (0.25A)			
	Total Direct			6,159

INDIRECT COSTS

(H)	Engineering & Supervision (0.40A)	1,048
(J)	Construction (0.45A)	1,179
(K)	Contractor's Fee (0.09A)	236
(L)	Contingency (0.40A)	1,048
	Total Indirect	3,511
	Total Fixed Capital	9,670

SUMMARY OF DISCUSSIONS AT LICADO CONCEPT REVIEW
JULY 13, 1989

QUESTION	ANSWER	ACTION
1. What is the target ash content of the product?	Emphasis is on pyritic sulfur removal. Ash contents are not as important as earlier. About 2% or 90% ash removal is target.	None required
2. Why does the coal not balance at Stream 4?	Residual coal builds up in the recirculating water system. The balance shown is at equilibrium and is affected by the accumulated coal in the recirculating water.	Will be explained in the final report.
3. Is the system multi-staged?	The separator is a single pass system with internal multi-staging in the same vessel.	None required
4. Will there be erosion of the let-down valves?	Will check valves used in expts at U. of Pitt. Expect to vent to about 50 psi before opening main valves.	Check valves. Vent before discharging.
5. Why was one ton per hour selected as the plant capacity?	Compromise among commercial size, scale-up from present data base, cost, and risk.	None required
6. How is plant equipment scaled to larger sizes?	<p>Separator-constant hold-up time and specific mixing power. Multiple units when wall thickness exceeds 1½ inch</p> <p>Vessels-increase diam until wall thickness is 1½ inch, then use multiple units.</p>	None required

QUESTION	ANSWER	ACTION
7. What is the largest particle?	90% less than 200 mesh; largest is 100 mesh.	None required
8. Cyclones may plug. Apex should be a minimum of 3X diam of largest particle in the system.	Include min diam of cyclone in design	Specify min diam of apex in all cyclone specs
9. Use "Super-Scalper" to remove slate and rock from ROM before grinding	Will include	Add "Super-Scalper" to the coal grinding system
10. Have you considered the use of barricades in the plant?	No.	Review with Safety Comm.
11. How will the ball mill be installed in the building?	It may be located on a pad extending outside the existing building or in a new building	None required
12. Have you handled wet coal in buckets? The loses will be high.	Consensus:dry grind in CO2 atmosphere.May help separation.	Change design to dry grind in CO2
13. Will feed flow out of lock hoppers? It has been stagnant for some time?	CO2 will be piped to the lock hoppers to aerate the coal if it jams.	Include aeration piping
14. Can the pressure be increased to assist the discharge of the lock hoppers?	Yes.	Provide piping

QUESTION	ANSWER	ACTION
15. How is the level in the filter maintained?	It is inclined at 30 degrees. CO2 readily flows through because of its low viscosity and surface tension. A back-pressure valve maintains 1-2 psi delta across the filter.	Will be demonstrated in Dev. Program
16. The solids in the Refuse Tanks may not settle. How will you handle?	In commercial plant, a rotary filter may be required. For Proof-of-Concept Plant, liquid-solids mixture will be drummed for disposal.	None required
17. What is the velocity through the hydraulic mixer?	About 1 ft/sec; higher through the orifices	Stellite face the orifices
18. How does this design compare with spiral mixers?	We have no information on spiral mixers.	None required
19. Have you looked at air sparged systems for the separator?	Air sparging is not feasible with CO2/water system. Separator is based on model being tested at the U. of Pitt.	None required
20. How is blowdown controlled?	Coal/water slurry and CO2 rates are constant. Refuse blowdown rate is controlled to maintain constant CO2/water interface.	None required
21. Coal particles will plug relief valves.	Yes.	Replace relief valves with rupture disks

QUESTION	ANSWER	ACTION
22. How is temperature controlled?	System is insulated and equipped with a water cooled heat exchanger. Temp. must be maintained below 85F, the critical temp.	None required
23. Can system be designed in segments so that individual can be tested?	Yes. We will provide the necessary piping/controls to operate subsystems independently.	Provide for independent subsystems operation. Review with McNally.
24. Roll mills may be less costly than hammer mills, because of lower maintenance.	We will investigate.	
25. A "Larox" (French) filter was used at Homer City to separate coal from Freon. There is also a German filter, Hyperbaric (Anders).	We will investigate.	Discuss with Homer City staff.
26. Fines must be re-agglomerated if product is to be shipped. Consol can agglomerate fines without binder. Starches, lignosulfates do not bind as well as asphalts. Cost is \$4 to \$10 per ton.	We recognize the need to bind; however, it is beyond the scope of the Proof-of Concept Plant.	None required
27. Can the statepoints (P&T) be added to the flow diagram?	The system is essentially isothermal except for mixing and pumping energies. We do not have sufficient details at this time to accurately calculate pressures and temperatures.	None required Provide in final design
28. Why isn't there a spare CO2 pump?	Spare is not shown.	Include spare CO2 pump.

QUESTION	ANSWER	ACTION
29. Does pump have sufficient NPSH?	Yes, from gravity (Pump is at ground level) and from over-pressure provided by the pressurizer.	None required
30. Can the separator be flanged in sections to facilitate unplugging?	This would be costly. All internals are suspended from the top flange and are removable by lifting this flange.	None required
31. How is the mixer sealed in the blind flange?	Electro-magnetic coupling	None required
32. How much CO2 is lost with the product?	We do not know. Measurement will be made on test products at U. of Pitt.	Measure CO2 in product at U. of Pitt.
33. Are there oxygen detectors to protect against oxygen depletion because of CO2 buildup at low points?	Not at the present.	Investigate with the Safety Committee

END

**DATE
FILMED**

8 / 7 / 92