DOE/PC/90156--1

DE93 000596

**DEVELOPMENT AND TESTING OF A COMMERCIAL-SCALE
COAL-FIRED COMBUSTION SYSTEM - PHASE III**

**Quarterly Technical Progress Report No. 1
Report Period: September 26, 1990 to December 31, 1990**

**By
A.F. Litka and R.W. Breault**

March 1991

Work Performed Under Contract No. DE-AC22-90PC90156

**Prepared for
PETC Project Manager: Mr. Douglas Gyorke
Pittsburgh Energy Technology Center
U.S. Department of Energy
P.O. Box 10940
Pittsburgh, Pennsylvania 15236-0940**

**Prepared by
Tecogen Inc.
45 First Avenue
P.O. Box 9046
Waltham, Massachusetts 02254-9046**

MASTER

TABLE OF CONTENTS

1. INTRODUCTION	1
2. PROJECT DESCRIPTION	4
2.1 DEVELOPMENT STAGE	4
2.2 PROOF-OF-CONCEPT STAGE	8
2.3 DEMONSTRATION STAGE	11
3. PROJECT STATUS	14
3.1 TASK 1.1 - COMPONENT DESIGN	14
3.2 TASK 1.2 - COMPONENT FABRICATION	41
4. PLANNED ACTIVITIES	44
5. SUMMARY	45
6. REFERENCES	46

LIST OF ILLUSTRATIONS

2.1	Work Breakdown Structure for Entire Project	5
2.2	Detailed Program Schedule	6
3.1	Process Flow Diagram	15
3.2	Residential Combustor Geometry	19
3.3	Particle Diameter Ratio vs. Inlet Velocity Ratio, 24-Inch Combustor	22
3.4	Pressure Drop Ratio vs. Inlet Velocity Ratio, 24-Inch Combustor . .	23
3.5	Particle Diameter Ratio vs. Inlet Velocity Ratio, 28-Inch Combustor	24
3.6	Pressure Drop Ratio vs. Inlet Velocity Ratio, 28-Inch Combustor . .	25
3.7	Particle Diameter Ratio vs. Inlet Velocity Ratio, 32-Inch Combustor	26
3.8	Pressure Drop Ratio vs. Inlet Velocity Ratio, 32-Inch Combustor . .	27
3.9	Particle Diameter Ratio vs. Inlet Velocity Ratio, 36-Inch Combustor	28
3.10	Pressure Drop Ratio vs. Inlet Velocity Ratio, 36-Inch Combustor . .	29
3.11	Reaction Rate Parameter vs. Temperature Ratio	32
3.12	Time Required for Water Evaporation Slurry Water Content 25 to 50 Percent	38
3.13	Time Required to Reach 1000°F Slurry Water Content 25 to 50 Percent	39
3.14	Combustor Test Facility Schematic	42
3.15	Combustor Test Facility Piping and Instrumentation Drawing	43

LIST OF TABLES

1.1	Performance Goals	2
3.1	System Heat Balance	16
3.2	Typical Composition Stoker Grade Coals for the Slurry Feed Stock	34
3.3	Properties of Coal Slurry Fuels Prepared From Rewashed Coals . .	35
3.4	Properties of Specially Washed Source Coals	36

1. INTRODUCTION

Coal is the most plentiful energy resource in the United States, and in 1987 it provided approximately one third of the quads of total energy consumed in the United States. Its use, however, has been largely restricted to utility power generation since World War II for environmental and economic reasons.

Within the commercial sector, oil and natural gas are the predominant fuels used to meet the space-heating needs of schools, office buildings, apartment complexes, and other similar structures. In general, these buildings require firing rates of 1 to 10 million Btu/hr. The objective of this program is to demonstrate the technical and economic viability of a coal-fired combustion system for this sector.

Fuel form is an important consideration in new combustion technologies aimed at restoring coal to the small-scale markets, particularly the commercial and residential sizes. Fuel form is important for two primary reasons – emissions and handling. In attempting to restore coal to the small markets, it is important to recognize ease of handling as an important criterion. Emissions levels, if not currently regulated, can be expected to be regulated by the government at low levels. The levels considered acceptable will be reduced over time, following the current environmental trends. Preparation and use of a coal-water slurry fuel can aid in meeting these criteria. Coal-water slurry eliminates the need to use dry pulverized coal with its attendant handling and dusting problems as well as its explosive potential. In addition, coal-water slurry is amenable to coal washing since coal cleaning technologies are generally water-based processes requiring fine grinding of the coal. For these reasons, the program objective will be met through the development of a coal-water slurry fired system.

The commercial-scale coal-water slurry (CWS)-fired space heating system will be a scale-up of a CWS-fired residential warm-air heating system developed by Tecogen under contract to the Department of Energy, Pittsburgh Energy Technology Center. This system included a patented nonslagging combustor known as IRIS, for Inertial Reactor with Internal Separation. This combustion technology, which has demonstrated high combustion efficiency using CWS fuels at input rates of 100,000 Btu/hr, will be scaled to operate at 2 to 5 million Btu/hr. Along with the necessary fuel storage and delivery, heat recovery, and control equipment, the system will include pollution control devices to meet targeted values of NO_x , SO_2 , and particulate emissions. In general, the system will be designed to match the reliability, safety, turndown, and ignition performance of gas or oil-fired systems. Table 1.1 summarizes the performance goals of the system.

TABLE 1.1
PERFORMANCE GOALS

- Thermal Input – 4 million Btu/hr
- Thermal Efficiency – >80%
- Combustion Efficiency – >99%
- Emissions – 1.2 lb SO₂/MMBtu
 0.3 lb NO_x/MMBtu
 0.03 lb Part./MMBtu
- Turndown – 3:1
- Ignition – Fully automatic startup with system purge
 and ignition verification
- Reliability/Safety – Comparable to oil-fired commercial
 boilers
- Ash Removal – Dust free and automatic or
 semi-automatic
- Routine Maintenance – Less than one manhour per day and an
 additional two manhours per week
- Service Life – >20 years

The successful development and future marketability of the heating system requires a strong, dedicated team with expertise in a broad range of areas including coal-water slurry preparation, coal combustion, pollution control, component manufacture, and systems integration. Such a team has been assembled and includes the following organizations: Tecogen, Donlee Technologies, AMAX Coal, and Southern Illinois University.

Tecogen is the prime contractor and is responsible for overall program management, combustor development, and integration of the subsystem components and installation of the system at the field test site. AMAX has extensive experience in coal-water slurry preparation and serves as the principal coal supplier. Donlee Technologies is responsible for the boiler/heat exchanger design and manufacture. Donlee has over 70 years experience in the commercial boiler business and is a potential commercializer of the technology. Southern Illinois University is the host for the field test portion of the program. The heating system will provide space heating at the SIU Coal Research Center.

The development program has been divided into three stages covering a time span of 39 months. During the first stage, which covers 14 months, the program will focus on component development. The second stage, which covers a 10-month period, will focus on proof-of-concept testing. The final stage covers a 15-month period and will focus on testing all the components as an integrated system in an actual installation.

This report documents the technical work carried out in the first quarter of the development program. During this period the system configuration was finalized, and a preliminary heat balance was developed. Properties of the CWS to be prepared from the selected coals were determined. Scaling laws were also developed to allow for an extension of the data base that has been established with the residential combustor and to provide guidelines for the scale-up of this combustor technology to larger sizes.

2. PROJECT DESCRIPTION

To achieve the program objective of demonstrating the technical and economic viability of a coal-fired commercial-scale space heating system, the program is divided into three stages: a development stage, a proof-of-concept stage, and a demonstration stage.

What follows is a description of the work to be performed in each of these stages and a brief description of the tasks and subtasks to be carried out. Figure 2.1 gives the work breakdown structure for the entire project. The schedule for the project is given in Figure 2.2.

2.1 DEVELOPMENT STAGE

The objective of the development stage is to design and construct an integrated system to permit proof-of-concept demonstration and testing.

Task 1 - Component Development (Design, Fabricate, and Integrate)

This task consists of three major subtasks - to design, fabricate, and integrate the components - thereby providing a commercial-scale space heating system capable of meeting all specified performance goals.

Subtask 1.1 - Component Design

This subtask consists of two major activities. The first activity involves conducting energy and material balances on the system to identify components and sizes, categorizing these components, and writing equipment specifications.

Equipment will be classified according to these categories: (a) commercially available, (b) fully developed, and (c) partially developed. Equipment in the first category must be commercially available and capable of operating in the system without the need to design or modify. Examples of equipment of this type are pumps, thermocouples, baghouses, etc. The equipment in the second category is fully developed. Such items have been shown through prior R&D to be capable of meeting the system performance goals. The third category of equipment comprises partially developed components. These are components that have demonstrated performance, but on a scale other than that intended for this project. The Tecogen IRIS combustor falls into this third category.

The second activity in this subtask is to design components in the partially developed category. These components will undergo design development to a level sufficient for fabrication by Tecogen. They will be modular to allow easy coupling to the other system components as well as modification and repair.

Figure 2.1 Work Breakdown Structure for Entire Project

Figure 2.2 Detailed Program Schedule

Subtask 1.2 – Component Fabrication

After review and approval of the Subtask 1.1 activities, Tecogen will fabricate all components that were designed in Subtask 1.1 as category (c) components (partially developed) and modify components identified as category (b) (fully developed), as well as procure all category (a) components (commercially available).

Subtask 1.3 – Component Integration

This subtask consists of two activities. The first will be conducted in parallel with Subtask 1.2 and will consist of preparing engineering drawings of the integrated system. The second activity will consist of assembling the hardware.

A complete set of engineering drawings will be supplied to DOE for approval. This set will consist of general arrangement drawings showing the interconnection of all components and utilities that form a working system. This set will also contain a piping and instrument diagram, an electrical diagram, and an updated process flow diagram. These will be presented to DOE for approval before assembly begins.

Task 2 – Perform Preliminary System Tests

This task consists of two major subtasks performed sequentially: Test Plan and System Tests. The objective of this task is to prepare a plan to explore the operation of the integrated system and to conduct a series of shakedown tests that provides a preliminary indication of the system performance and identifies key variables and their ranges. The primary goal of this task is to debug the system and establish an appropriate set of operating conditions for the proof-of-concept system tests.

Subtask 2.1 – Test Plan

This subtask will focus on preparing a test plan for preliminary system tests and forming a basis for future tests. The test plan will define program objectives and a schedule to achieve these objectives. Also, the type and range of test parameters as well as the nature of the data to be obtained will be identified. Operating conditions will be defined and a test matrix will be established. Sampling and analysis methods (appropriate instrumentation), together with methods for data acquisition and analysis, will be included. This test plan will be presented to DOE for approval to proceed to Subtask 2.2, System Tests.

Subtask 2.2 – System Tests

This subtask consists of four major activities: startup, testing, data analysis, and maintenance and repair. These activities will be conducted simultaneously, with data analysis and testing interacting greatly.

Startup will include a mechanical shakedown of the equipment to ensure that all ancillary equipment, fans, particulate collection, pumps, etc., function properly. This will be followed by operation of the system on the startup burner to ensure that operation under fired conditions is satisfactory. This will be followed by switching to the CWS fuel to ensure that ignition and stable combustion can be established before the test plan is begun.

Tests will be initiated according to the test matrix prepared in Subtask 2.1. Data produced during the tests will be analyzed, and the test matrix prepared under Subtask 2.1 may be modified to incorporate test results to obtain the best possible data. Also, maintenance and repairs will be made as needed.

This subtask will conclude with a presentation of the results to PETC to obtain approval to initiate Task 3 work. This is the first of two major decision points in the program.

2.2 PROOF-OF-CONCEPT STAGE

The objective of the proof-of-concept stage is to perform systems tests to demonstrate the technical feasibility of the concept. Based on the test results, an economic evaluation to determine the commercial viability of the system and market potential will be performed.

Task 3 – Perform Proof-of-Concept System Tests

This task consists of three major activities, all focused on proving that the concept is technically feasible, both from a performance standpoint and from a maintenance and reliability standpoint. The three major activities are to: prepare a test plan, refurbish necessary equipment, and test.

The test plan will be a revision of that produced under Subtask 2.1, incorporating revisions made during Subtask 2.2. However, it will explore the operation of the system in much greater detail to provide data sufficient to evaluate system performance. The test plan will focus on obtaining combustion and thermal efficiencies; tendencies to slag, foul, erode, and corrode; gaseous and particulate emissions; the capability to store, transport, and handle the coal-water slurry fuel

as well as the capability to handle and store the solid waste material; and operation over sustained periods of testing that simulate commercial operation. This test plan will be presented to DOE for review before system refurbishing or testing is begun.

The next activity is to refurbish the system and ready it to a degree sufficient to conduct the 500-hour test program and to provide reliable data.

Once the system has been readied, testing will begin. This activity consists of three work areas: operation, data analysis, and maintenance. Operation will involve setting up the test conditions established in the test matrix and allowing the system to obtain steady state. The data will be analyzed as they are collected, to facilitate reduction and make any necessary changes to the matrix in a timely manner. Maintenance will be conducted as needed. Specifically, the system will be opened approximately every 50 hours for inspection only. This will provide needed information on slagging and fouling characteristics with time. Since most of the tests will be conducted on an 8-hour shift, the system will operate for 6 to 7 days before it is opened. Also, one round-the-clock test of 50 hours will be conducted.

Task 4 - Evaluate Economics/Prepare Commercialization Plan

This task consists of two major subtasks; Economic Evaluation and Commercialization Plan. These two activities will assess the commercial viability of the system. The economic evaluation and the market potential are major factors which affect the commercial viability of the system. At the completion of this task a formal project review of the results to date will be presented to decide on future activities.

Subtask 4.1 - Economic Evaluation

The economic analysis of the system is conducted through three activities. These are capital cost estimates, operating cost estimates, and cash flow analysis.

Capital and operating cost estimates for a mass-produced system will be projected in parallel with each other. An economic cash flow analysis will be made to evaluate the profitability of the plant investment. The analysis will account for the cost of capital and include calculation of financial indicators. A sensitivity analysis will also be performed in order to determine the technical, operational, and risk factors bearing on the cost of the space heating system. Cost comparisons will be made with conventional fired space heaters after all economic factors are considered. The cost comparison will be broken down into the following categories:

- Direct investment expenditures for the coal-fired space heating system, to include materials, fabrication, assembly, and shipment
- Site modification costs, to include expenditures for removing existing equipment, obtaining permits, and other expenses required to prepare the site for a coal-fueled system
- Installation charges, to include expenses associated with placing the fully integrated system on site
- Engineering and design costs
- Startup costs, to include all costs incurred after system setup, but prior to useful operations
- Consumables, to include fuels, electricity, water, and any chemicals
- Operating and maintenance

The projected costs will then be compared with the current costs of a premium-fuel-fired system that is being used in an application comparable to that which is intended for the coal-fired unit.

Subtask 4.2 – Commercialization Plan

In a parallel effort with the Economic Analysis, a plan for rapid commercialization of this system will be prepared by all parties working together. This task is broken down into three activities: market identification, manufacturing, and demonstration site identification.

The commercial market will be reviewed to determine the projected market. This review will include an analysis of space heater user populations, including age, types of energy needed, types of systems used, and geographic concentration. This information will be used to assess the most favorable market sector and to develop a strategy to penetrate this sector plus the entire market.

Since the marketplace for combustion systems under 10×10^6 Btu/hr is rather diverse, the most expedient approach to introducing this equipment is to have manufacturers focus on producing these systems within their areas of expertise. Discussions with manufacturers will be conducted to encourage their involvement.

Also, discussions with the host site will continue in order to finalize their commitment for use of the site as well as to explore potential cost sharing.

2.3 DEMONSTRATION STAGE

The objective of the demonstration stage is to integrate the CWS-fired heating system into the host site infrastructure to replace or supplement the existing premium fuel system. The system will be operated for approximately 100 hours, and an evaluation of system performance and economics will be made.

Task 5 – Conduct Site Demonstration

This task consists of two subtasks aimed at demonstrating the technology in a real environment. The space heating system will be integrated into the host site infrastructure to replace or supplement the premium fuel system. The two subtasks required to accomplish this work are Demonstration Plan and Site Demonstration.

Subtask 5.1 – Demonstration Plan

Three major activities are conducted in this subtask. These are site design, test plan, and cost estimate update.

The first activity will provide a design of the demonstration site system. The design will include heat and mass balance predictions and emission estimates for NO_x , SO_2 , and particulate, as well as the control system. The balance of plant design will include receiving and storage for both fuel and sorbent auxiliary fuel systems, fly ash particulate control devices, and ash handling and storage systems. The following drawings will be made: PFD, P&ID, general arrangement, and detailed assembly. This activity will also include a general discussion of the host site.

The test plan will define the installation period as well as the test period. It will include the planned length of the demonstration and the projected labor and consumable requirements.

Finally, the demonstration cost estimate will be updated to include all information gained during the program.

Subtask 5.2 – Site Demonstration

This subtask consists of three activities; namely, installation, operation, and evaluation. The host site will be prepared for the installation of the proof-of-concept facility. Following installation of the facility, mechanical testing and inspection will be performed to ensure that the installation has been completed according to

design specifications and that all systems are operable. Prior to startup, the host site operators and personnel will be given training concerning all aspects of system operation, including safety.

Tecogen and Donlee research engineers will start up the demonstration facility in accordance with accepted operating practice. Following startup, steps will be taken to ensure that all subsystems and components are functionally operative within their intended design range. Operating modifications will be documented.

Short-term tests will be scheduled prior to continuous operation. During the initial baseline test period the system operation will be optimized with respect to all performance goals. Various operating alternatives and adjustments will be evaluated, and the general facility conditions will be set up for continuous operation by the host site operators. During the short-term test program, all major parameters will be monitored, and measurements will be made over the range of boiler operating conditions to validate the technical and economic characteristics of the system. Following the baseline and optimization tests, the demonstration facility will be continuously operated by the host site under normal steam demand conditions. Tecogen and Donlee engineers will be on call during this period should problems arise.

Evaluation of the demonstration facility will include all data reduction necessary for the following activities: emissions characterization, performance and reliability, efficiency, operability, upstream and downstream effects, identification of remaining commercial issues, and cost documentation.

During long-term operation, boiler performance and reliability will be documented through continuous monitoring of steam production, operating time, and outages. Other performance factors such as combustion efficiency, erosion, and corrosion will be measured during short-term test programs. System operability will also be monitored during long-term operation. Operator and maintenance requirements will be documented in terms of number and level of expertise. The performance of upstream and downstream equipment will be evaluated on several parameters including fuel and sorbent handling, particulate emission control, ash handling, and waste disposal. In addition, selected characterization of various waste streams will be made. All remaining issues affecting the successful commercialization of the concept will be documented.

Task 6 - Decommission Test Facility

This task consists of two activities: planning the decommissioning and executing the plan. Tecogen will prepare a test facility decommissioning plan. This plan will list all major test facilities, equipment, instruments and hardware, their condition, and proposed disposition. After DOE approval, the entire test facility will be dismantled and contractor-procured. Government-owned equipment and instrumentation will be protected until final disposition as directed by the DOE. Also, Tecogen will restore any DOE or host facility property affected by the contractor during the term of this contract.

Task 7 - Reporting

Monthly status reports will be provided to assess the progress of the program. In addition to these, quarterly technical reports will be provided during the project. Six major reports will be prepared; that is, three annual reports, two topical reports, and a final report.

Task 8 - Project Management

The objective of this task is to ensure timely completion of all program objectives within cost. To accomplish this, a program manager will be assigned to the project. The program manager will set goals, plan how to accomplish these goals, maintain effective personnel on the project, negotiate and execute agreements between all participants, including subcontractors, and deliver all contract commitments and respond to requests from program managers at DOE.

3. PROJECT STATUS

3.1 TASK 1.1 - COMPONENT DESIGN

Heat Balance

A preliminary heat balance for the space heating system was prepared to provide flow rate, heat extraction, gas composition and temperature data for initial component sizing. Figure 3.1 is a process flow diagram for the system, and Table 3.1 summarizes the results of the heat balance analysis. The heat balance will be revised and completed in more detail as actual component performance characteristics are determined as a result of the component design activities. The system will be configured for a design firing rate of 4 million Btu/hr.

Combustor

The combustion technology to be utilized in this program is one developed specifically for the combustion of CWS fuels. This combustion technology, known as IRIS (for Inertial Reactor with Internal Separation), was developed and demonstrated at the residential scale at input rates ranging from 60,000 to 240,000 Btu/hr.¹ When the residential-scale CWS combustor is scaled to input rates more typical of commercial-scale operation (2 to 5 million Btu/hr), similar performance can be expected if the commercial unit is designed to separate particles that are the same size as the particles separated in the residential unit, if it has the same gas phase residence time and degree of mixing (turbulence), and if it is operated under the same thermal conditions. Analyzing the fluid mechanics, particle dynamics, and chemical kinetics of the combustor has resulted in the development of scaling laws that allow the knowledge base established on the residential combustor to be extended to units that operate on larger scales.

Residential Combustor

In designing the commercial CWS combustor, particular attention must be paid to the way in which the residential combustor operates. The residential CWS combustor makes use of centrifugal forces, set up by a predominantly vortical flow field, to separate and confine larger unburned coal particles in the furnace upper chamber. Various partitions are used to retard the axial downward flow of these particles and thus maximize the residence time of these particles in the hottest section of the combustor.

As the particles burn and their size decreases, radial drag forces overcome the centrifugal forces, and the smaller particles are able to exit the primary

Figure 3.1 Process Flow Diagram

TABLE 3.1
SYSTEM HEAT BALANCE

Stream →	1	2	3	4	5	6	7	8
	Combustion Air, Blower Outlet	Combustion Air, First Stage	Combustion Air, Second Stage	Atomizing Air, Compressor Outlet	Coal Slurry, Pump Outlet	Combustion Products, Boiler Inlet	Combustion Products, Boiler Outlet	Sorbent
Temperature, °F	100	100	100	150	60	2000	325	70
Pressure, psig/in. wc	28"	25"	25"	60	40	-0.2"	-3.6"	-5.6
Liquid Flow Rate, GPM	-	-	-	-	1.0	-	-	-
Liquid Flow Rate, lb/hr	-	-	-	-	555	-	-	53 (Solids)
Gas Flow Rate, ft ³ /min	774	370	406	7.2	-	4940	1674	-
Gas Flow Rate, lb/hr	3548	1696	1862	166	-	4269	4269	-
Gas Composition (vol %)								
CO ₂	-	-	-	-	-	12.84	12.87	-
H ₂ O	-	-	-	-	-	14.93	14.98	-
NO	-	-	-	-	-	0.019	0.019	-
N ₂	79	79	79	79	-	68.53	68.63	-
O ₂	21	21	21	21	-	2.95	3.02	-
SO ₂	-	-	-	-	-	0.162	0.162	-

TABLE 3.1 (Continued)
SYSTEM HEAT BALANCE

Stream →	9	10	11	12	13	14	15
	Combustion Products, Baghouse Inlet	Flyash/ Gypsum	Combustion Products, Baghouse Outlet	Combustor Clg Water Inlet	Combustor Clg Water Outlet	Hot Water Outlet	Hot Water Return
Temperature, °F	325	325	300	180	200	180	160
Pressure, psig/in. wc	-5.6"	-	-13.6"	10	2	20	5
Liquid Flow Rate, GPM	-	-	-	150	150	350	350
Liquid Flow Rate, lb/hr	-	65 (solid)	-	75,000	75,000	175,000	175,000
Gas Flow Rate, ft ³ /min	1585	-	1471	-	-	-	-
Gas Flow Rate, lb/hr	4322	-	4257	-	-	-	-
Gas Composition (vol %)							
CO ₂	-	-	13.179	-	-	-	-
H ₂ O	-	-	13.122	100	100	100	100
NO	-	-	0.019	-	-	-	-
N ₂	-	-	70.11	-	-	-	-
O ₂	-	-	3.081	-	-	-	-
SO ₂	-	-	0.05	-	-	-	-

chamber. Combustion of these smaller particles is completed in a secondary chamber. A schematic diagram of the residential combustor along with details of the units geometry is shown in Figure 3.2. Typical performance data for the residential combustor are as follows:

Input Rate:	150,000 Btu/hr
Combustion Efficiency:	Greater than 99%
NO _x Emissions (staged):	As low as 0.285 lbm/MMBtu
Pressure Drop:	3.5 in. wc
Average Gas Temperature:	2,335°F

Scaling Law Principles

In developing the scaling laws for the combustor, one of the key factors that must be taken into account is particle separation efficiency. If a larger combustor is capable of capturing particles that are the same size as those captured by the residential unit, then with all other factor the same, comparable performance can be expected. In order to determine the theoretical particle size that can be detained within the combustor, a balance between centrifugal forces and drag forces at the radial location that coincides with the edge of the lower partition was conducted. This results in a relationship for particle diameter that is a function of the tangential and radial velocities fields within the combustor, as shown in equation 1:

$$D_p = \left(\frac{18 \mu V_{gr} r_{out}}{\rho_p V_t^2} \right)^{\frac{1}{2}} \quad (1)$$

where:

V_{gr} is the radial gas velocity

V_t is the tangential gas velocity

μ is the gas viscosity

ρ_p is the particle density

r_{out} is the radial position of the edge of the lower partition

The tangential velocity in a vortical flow field can be described by:

$$V_t = V_{in} (1-n)^{\frac{1}{2}} \left[\frac{r_o}{r} - n \left(\frac{r_o}{r} - \frac{r}{r_o} \right) \right] \quad (2)$$

where:

V_{in} is the inlet velocity

n is a constant between 0 and 1

r_o is the radius of the combustor wall

Residential Combustor Geometry

Do (in.)	8.38
Dout (in.)	4.0
Lp (in.)	15.0
Ltot (in.)	30.0
Air Inlets:	
primary (in. ²)	0.25
secondary (in. ²)	0.564

Figure 3.2 Residential Combustor Geometry

Based on experimental data Smolensky² found that n was related to the inlet area and the combustor radius by the following relationship:

$$n = 1 - 1.4 \left(\frac{\sqrt{A_{\text{inlet}}}}{r_o} \right)^{0.9} \quad (3)$$

In order to determine the radial velocity at the lower partition, it was assumed that the flow could be modeled as a point sink positioned at the combustor centerline.

$$V_s = \frac{\dot{m}}{2 \pi \rho_s} \left(\frac{1}{r^2} - \frac{1}{r_o^2} \right) \quad (4)$$

When these relationship are substituted into equation 1, the following expression for particle diameter can be written:

$$D_p = \left[\frac{\left(\frac{18 \mu}{\pi} \right) \left(\frac{\rho_s}{\rho_p} \right) \dot{m} (1 - D^*)}{D^* D_o \rho_{s, \text{in}}^2 V_{\text{in}}^2 (1 - n) \left[\frac{1}{D^*} - n \left(\frac{1}{D^*} - D^* \right) \right]^2} \right]^{\frac{1}{2}} \quad (5)$$

where:

$\dot{m}$ is the mass flow rate

D^* is the ratio of the lower partition diameter to the combustor diameter

The particle diameter predicted by equation 5 must be viewed as a theoretical diameter that the combustor can detain as opposed to an absolute value. This is due to the high degree of turbulence present in the combustor. Since turbulent fluctuations can be greater than the radial velocity predicted by equation 4 it is more appropriate to normalize D_p for the commercial combustor with that of the residential combustor. When this normalized particle diameter ratio is less than one, then the commercial combustor is capable of separating particles smaller than those separated by the residential combustor.

With a knowledge of the factors that affect the separation efficiency of the commercial combustor, it should quite easy to design a unit capable of separating particles equal in diameter to those separated by the residential combustor. The problem that accompanies this approach is the allowable pressure drop with which

the commercial combustor can operate. The commercial combustor operates at a much higher mass flow rate than does the residential unit, and as such, equation 5 indicates a decrease in its ability to capture smaller particles. In order to be able to capture the same size particle as the residential unit, the inlet velocity must increase. This can lead to a substantial increase in pressure drop unless the value of D^* is adjusted accordingly.

The pressure drop for a vortical flow device, such as the CWS combustor, was found from experimental investigations to be a function of inlet velocity, D^* , and n . Smolensky² determined this relationship to be:

$$\Delta p = \frac{\rho V_{in}^2}{2} (1 - n') \left[n^2 (1 - 0.36 D^{*2}) + (1 - n')^2 \left(2.78 \left(\frac{1}{D^*} \right)^2 - 1 \right) + n' (1 - n') \ln \left(\frac{1.67}{D^*} \right) \right] \quad (6)$$

where n' is the value n multiplied by 1.1 to best fit the data.

Using equations 5 and 6, both normalized to residential combustor operating conditions, a direct comparison of the effects of inlet velocity and combustor geometric ratios on particle capture diameter and pressure drop can be established for design purposes. This was done for the case of four different combustor diameters of 24, 28, 32, and 36 inches, where both particle diameter ratio ($D_{p\text{ com}}/D_{p\text{ res}}$) and pressure drop ratio are plotted against inlet velocity ratio, and is shown in Figures 3.3 through 3.10.

In addition to being able to capture particles that are approximately the same size as those captured by the residential combustor, the commercial combustor must have comparable gas phase residence times in both the primary and secondary zones to ensure comparable combustion efficiencies as well as NO_x emission levels. The effect of residence time becomes apparent in the height of the combustion chambers. In order to maintain residence time similitude, for the 24-, 28-, 32-, and 36-inch diameter units, combustor heights of 98, 72, 55, and 44 inches, respectively, are required.

The previous assumptions of the commercial combustor having the same gas phase residence time as well as the ability to capture particles of the same diameter as those captured by the residential combustor are quite conservative. This is due to the fact that the commercial combustor should operate at a higher temperature than the residential unit. The residential combustor has a surface area to volume

Figure 3.3 Particle Diameter Ratio vs. Inlet Velocity Ratio, 24-Inch Combustor

Figure 3.4 Pressure Drop Ratio vs. Inlet Velocity Ratio, 24-Inch Combustor

Figure 3.5 Particle Diameter Ratio vs. Inlet Velocity Ratio, 28-Inch Combustor

Figure 3.6 Pressure Drop Ratio vs. Inlet Velocity Ratio, 28-Inch Combustor

Figure 3.7 Particle Diameter Ratio vs. Inlet Velocity Ratio, 32-Inch Combustor

Figure 3.8 Pressure Drop Ratio vs. Inlet Velocity Ratio, 32-Inch Combustor

Figure 3.9 Particle Diameter Ratio vs. Inlet Velocity Ratio, 36-Inch Combustor

Figure 3.10 Pressure Drop Ratio vs. Inlet Velocity Ratio, 36-Inch Combustor

ratio of about $6 \text{ ft}^2/\text{ft}^3$ compared to less than $2 \text{ ft}^2/\text{ft}^3$ in the commercial combustor. For a refractory lined unit, the lower relative surface area for heat transfer in the commercial-scale combustor translates to higher average gas temperatures. These higher temperatures associated with the commercial combustor increase the chemical reaction rates, and as such, in order to achieve the same combustion efficiency, the commercial combustor does not have to be able to capture particles of the same size as those in the residential-scale combustor.

To obtain a quantitative feel for the effect of combustor operating temperature on particle diameter, consider a general heterogenous reaction to dominate the overall reaction scheme.

If we assume this reaction to be first order:

$$\frac{dm_B}{dt} = \frac{-A b M_B C_A}{\frac{1}{k_c} + \frac{1}{k_d}} \quad (8)$$

where:

- A is the particle surface area
- b is the stoichiometric coefficient
- M_B is the molecular weight of species B
- C_A is the concentration of species
- k_c is the resistance due to chemical kinetics
- k_d is the resistance due to diffusion

For the small particles being considered, it is assumed that diffusion is negligible. Further, if the reaction rate constant can be expressed as an Arrhenius relationship, then the effect of the elevated temperatures associated with the commercial combustor relative to the residential combustor can be evaluated. By introducing the Arrhenius assumption, and normalizing the reaction rate expression with that of the residential combustor, a reaction rate parameter can be defined as:

$$\Gamma = \left(\frac{D_{p_{res}}}{D_{p_{com}}} \right) \frac{\exp \left(\frac{-E T^*}{R T_{res}} \right)}{\exp \left(\frac{-E}{R T_{res}} \right)} \quad (9)$$

where:

E is the activation energy

R is the universal gas constant

T_{res} is the average temperature at which the residential combustor operates

T* is the absolute temperature ratio (residential/commercial)

If char oxidation is assumed to be the dominant reaction, then by using an activation energy of 21,900 kcal/kg-mole, typical of bituminous coals, a plot of reaction rate parameter can be made as a function of absolute temperature ratio and particle diameter ratio, as shown in Figure 3.11. The meaning of the reaction rate parameter is as follows: When this parameter is equal to one, the same degree of char oxidation should occur in both the commercial and residential combustors. When this parameter is greater than one, reaction rates favor the commercial combustor. When this parameter is less than one, the kinetics occurring in the residential combustor are favored.

Design Example

As an example of the use of the scaling laws, consider the case of a 28-in.-diameter combustor. In order to match the residence time of the residential combustor, the height of this unit would have to be 72 in. If we assume that the insulation in the commercial combustor provides an average operating temperature such that the ratio of the residential to commercial absolute temperature is 0.92, then by Figure 3.11, equal chemical reaction rates can be achieved when the commercial combustor is operated with particles that are 1.75 times that which can be separated in the residential unit. Using Figure 3.5, it can be found that for a particle diameter ratio of 1.75 and a lower partition-to-combustor diameter ratio of 0.6, a velocity ratio 1.5 times that of the residential combustor is required. The pressure drop ratio for this velocity and diameter ratio is found from Figure 3.6 to be approximately 6.5. Since the residential unit operates at a nominal pressure drop of 3.5 inches wc the commercial unit would operate at 22.8 inches wc to achieve the same performance.

Before a final combustor geometry based on the above scaling laws is selected, the impact on overall system performance and arrangement must be evaluated. Work is under way to determine the overall system pressure and combustor/boiler integration requirements.

Figure 3.11 Reaction Rate Parameter vs. Temperature Ratio

Slurry Preparation

In the commercial-scale marketplace, the fuel of choice will be a CWS. This is the case for a number of reasons. The most significant reason is ease of fuel handling and storage. The use of a dry ultrafine product promotes a dusty environment with explosive potential. Therefore, considering its ease of handling and stable state, CWS fuel is the best fuel for this scale.

It is recognized that CWS fuel is not easily obtained or widely produced at this time. CWS fuel is not a new technology; however, it is a young technology. At present, large companies are hesitant to invest in large beneficiation plants and accompanying slurry plants. This is because the market for slurry products is small at this time. On the other hand, without a demonstrated fuel reserve, customers will not purchase a space or process heater that relies on a fuel which is not available. Therefore, to get coal combustion into the commercial-scale marketplace, it will take a combined effort to develop the equipment and fuel supply simultaneously. It is for this reason that the design, installation, and operation of a slurry preparation site has been included as part of this development program.

CWS fuel for this program will be made from three coals. These are an Eastern Kentucky coal and two Illinois coals, with analysis shown in Table 3.2. The Eastern Kentucky coal will be used due to its low ash and low sulfur values to debug the system during the first level of testing and for initial testing in the proof-of-concept task. In all cases, slurry fuel will be made from washed mine products. After shakedown is complete, tests will be conducted on the higher ash coals from Illinois.

Table 3.3 lists the properties of micronized slurry fuels which will be produced from these coals. The typical values shown for Illinois No. 6 and Hazard coals are representative of recent production lots at AMAX. The data for Illinois No. 5 are from laboratory slurry preparation tests performed several years ago. The ranges given for each slurry property are projected from experience in preparing large batches of fuel from different lots of the same coal at different times.

Table 3.4 gives the estimated grinding energy requirements projected for the slurry fuel production. Grinding units with 20- to 30-hp drives are required to produce 300 pounds per hour of minus 325 mesh fuel from the Illinois coals. The capacity will be somewhat less with Hazard coal since it is significantly less grindable than most other coals.

Both wet and dry grinding systems are being investigated. Comparable coal receiving, storage, and feeding arrangements would be employed for both dry and wet grinding systems. The configuration of the remaining parts of the system will depend on the specific grinding system.

TABLE 3.2
TYPICAL COMPOSITION STOKER GRADE COALS
FOR THE SLURRY FEED STOCK

	Coal Seam		
	Hazard No. 5	Illinois No. 6	Illinois No. 5
Coal Rank	Bituminous	Bituminous	Bituminous
Mine Name	Bledsoe	Delta	Wabash
Proximate (%)			
Moisture	1	9	10
Ash	4.5	7	5.47
Volatiles	34.7	34.2	31.37
Fixed Carbon	59.1	47.6	53.15
Sulfur	0.7	2.2	1.45
Heating Value (Dry) Btu/lb			13,730
Ultimate (MAF) %			
C	84.36	82.27	81.59
H	5.67	5.49	5.41
N	1.52	1.56	1.58
S	0.73	2.80	1.74
O	7.72	8.03	9.53
Cl	N/A	0.15	0.16

TABLE 3.3
PROPERTIES OF COAL SLURRY FUELS PREPARED FROM REWASHED COALS

	Illinois No. 6 Delta Mine		Illinois No. 5 Wabash Mine		Hazard Kentucky Prince Mine	
	Typical	Range	Typical	Range	Typical	Range
Particle Size						
Passing 45 μm , Weight %	98.0	97.5 – 98.5	98.0	97.5 – 98.5	98.0	97.5 – 98.5
Mass Mean Diameter, μm	12.9	10 – 14	12.0	10 – 14	12.0	10 – 14
Coal, Weight %	53.5	52.5 – 54.0	51.5	50.5 – 52.0	54.0	53.0 – 55.0
Ash, Weight %	10.0	10 – 12	5.5	5 – 9	4.5	4 – 7
Volatile Matter, Dry Weight %	38.0	37.5 – 38.4	38.5	38.0 – 38.8	35.0	34.0 – 36.0
Sulfur, Dry Weight %	2.8	2.4 – 3.5	1.4	1.2 – 2.1	0.8	0.7 – 1.0
Ash Softening Temp., °F	2,085	2,060 – 2,250	2,100	2,060 – 2,250	2,700+	2,650+
Higher Heating Value, Btu/lb						
Dry Ash Free	14,800	14,300 – 14,500	14,600	14,500 – 14,700	14,900	14,800 – 15,000
Slurry Basis	7,000	6,800 – 7,250	7,215	6,950 – 7,250	7,740	7,500 – 7,850
Slurry Viscosity, cp						
at 100 sec^{-1}	200	150 – 250	200	150 – 250	200	150 – 250
at 500 sec^{-1}	260	<350	220	<350	240	<350
at 1,000 sec^{-1}	310	<450	240	<450	270	<450
Stability, Days	30	14 – 60	30	14 – 60	30	14 – 60

TABLE 3.4
PROPERTIES OF SPECIALLY WASHED SOURCE COALS

	Illinois No. 6 Delta Mine		Illinois No. 5 Wabash Mine		Hazard Kentucky Prince Mine	
	Typical	Range	Typical	Range	Typical	Range
Particle Size, inches	1-1/4 x 3/8	2 x 0	1-1/2 x 1/2	2 x 0	1-1/4 x 1/4	2 x 0
Moisture, %	9	7 - 11	12	10 - 14	6	4 - 8
Hardgrove Grindability Index	56	50 - 60	57	52 - 59	48	44 - 49
Product Particle Size						
Passing 45, μm %	98.0	97.5 - 98.5	98.0	97.5 - 98.5	98.0	97.5 - 98.5
Mass Mean Diameter, μm	12.9	10 - 14	12.0	10 - 14	12.0	10 - 14
Estimated Wet Grinding ^a Energy, hp-hr/dry ton	122		118		140	
Estimated Dry Grinding ^b Energy, hp-hr/dry ton	190		190		240	

^aBased upon AMAX R&D pilot fuel production in a 40-liter Draiswerke stirred ball mill.

^bFor main drive only and based upon grinding done using a Pulvocron PC-20 and Airtor 8A pulverizers, each with internal classification and supplemental heating.

Slurry Atomization

Modelling of the slurry atomization to determine droplet trajectories and evaporation rates has been performed to provide design data for atomizer performance, position, and number. To ensure stable and reliable operation, the slurry droplets, which are actually an agglomeration of coal particles and water, must ideally be raised to the ignition temperature prior to impact with the combustion chamber wall. Knowing the slurry droplet size, geometry of the combustor, amount of atomizing air and other operational parameters makes it possible to determine if this condition will be met.

A number of sophisticated models (both numerical and analytical) have been developed that can be used to calculate the droplet residence time and temperature. There is an abundance of experimental data, mostly published by Chigier,³ that characterize the atomizer and relate to the slurry particle size distribution, spray angle, etc. Also, Tecogen has obtained a great deal of data on gas and wall temperatures, gas velocities, and slurry properties through its work on other programs involved with CWS combustion and handling. This information was used to simplify the very complex heat transfer problem and perform the analysis.

A qualitative analysis shows that heat is being transferred under several modes: convection between the slurry particles and the hot gasses, radiation exchange between the particles and both the wall and the gasses, conduction, and vapor transfer due to evaporation and diffusion. A draft calculation showed that of the above phenomena, convection, radiation exchange with the wall, and vapor transfer due to evaporation dominate the process. The effect of the rest was assumed to be negligible.

The convection calculation treats the slurry spray as a packed bed of spheres. The heat transfer rate is grossly overpredicted if the average temperature difference between the slurry spray and the gasses is used. Instead, a log mean temperature difference is employed, which for the particular conditions, was estimated at 350°F. For the calculation of the radiation, the value of the view factor was set at one. In reality, the view factor is less than one, and in the center of the slurry spray it probably approaches zero. However, the radiative heat transfer is small compared to the convective, and thus only a small under prediction of the reaction time will result from this assumption.

The reaction time can be broken down into five intervals: heating of the droplet to 212°F, evaporation of moisture, heating to 600°F, devolatilization, and heating to 1000°F, at which temperature ignition is anticipated. Figures 3.12 and 3.13 show the results of the analysis. Figure 3.12 gives the time required to

Figure 3.12 Time Required for Water Evaporation
Slurry Water Content 25 to 50 Percent

Figure 3.13 Time Required to Reach 1000°F
Slurry Water Content 25 to 50 Percent

achieve complete evaporation of the water for various slurry droplet sizes and slurry coal content. A similar set of results plotting the residence time required to completely vaporize the water and raise the remaining coal to 1000° is shown in Figure 3.13. Included on the plots is the time required for a 50-micron droplet to reach the combustor wall. The time required for a particle to reach the combustor wall was obtained by several methods. Due to the uncertainties involved with this calculation, a range is given, instead of a single value. A 50-micron particle, according to a worst-case scenario, will reach the wall in 6.5 to 9 msec. For both cases, this time is for a center top-fired configuration with the slurry atomizer pattern having an included spray angle of 82°. Wall impact times for wall-fired configurations are comparable.

The predictions obtained using this method were compared to data published by Holve,⁴ who used the one-dimensional coal combustion model 1-DICOG. For one case, 1-DICOG predicts reaction time of 4 msec. The present method calculated 4.3 msec, which was considered acceptable.

Emissions Control

To meet the targeted emission goals of no more than 1.2 lb of SO₂ and 0.03 lb of particulates per million Btu, the CWS-fired commercial-scale space heating system must include flue gas pollution control equipment. Uncontrolled, the system will generate emissions of approximately 4 lb of SO₂ per million Btu and 6.25 lb of particulates per million Btu, depending on the exact coal composition. The control of nitrogen oxides (NO_x) to targeted levels will be achieved through control of the combustion process; therefore the pollution control equipment will not include NO_x reduction capabilities. NO_x control for the CWS combustor will be implemented by operating the combustor in a staged mode.

The reduction levels required to meet the design goals – 70 percent for SO₂ and 99.5 percent for particulates – are achievable with commercially available technologies. Two technologies are considered practical to meet the sulfur capture requirements of the system while satisfying the requirement that the equipment be capable of automatic operation, require a minimum of routine maintenance and attention, and not adversely affect the economics of the process. These are: duct injection and spray drying. Both these techniques are considered dry flue gas desulfurization processes, wherein the sulfur is captured as a dry material, namely calcium or sodium sulfate, depending on the sorbent injected.

Wet processes, in which the sulfur is captured in an alkaline solution, are capable of higher reduction efficiencies, but they are also high-cost, high-maintenance systems and are economical only in much larger sizes.

In spray drying, the reagent is introduced wet, as an alkaline slurry, and the SO_2 is absorbed onto the finely atomized slurry droplets to form liquid-phase salts which are dried by the heat of the flue gas. These solid reaction products, along with the flyash, are entrained in the flue gas and collected in a fabric filter (baghouse) or electrostatic precipitator (ESP). If a baghouse is used, additional SO_2 removal occurs as the flue gas passes through the built-up filter cake on the bags. In most cases, a spray dryer absorber will be provided to ensure complete contact and evaporation of the alkaline slurry.

In the duct injection process, a dry powdered sorbent is injected directly into the flue gas duct upstream of the particulate-control device. SO_2 is absorbed initially at the point of injection and further absorption of SO_2 occurs in a baghouse as the sulfur-laden gasses pass through the filter cake. For most duct injection applications the baghouse is considered an integral part of the SO_2 removal equipment. High SO_2 removal efficiencies require intimate and thorough contact of the SO_2 -laden flue gas with the sorbent, which generally requires alkali addition in excess of the stoichiometric ratio.

The particulate emission requirement of less than 0.02 lb particulate per million Btu can be met with either a fabric filter or ESP. Since additional SO_2 removal occurs as the flue gas passes through the built-up filter cake, a baghouse will be utilized as the particulate collection device. Baghouses are readily available for this gas and solids flow and are more economical than ESP's in this size range.

3.2 TASK 1.2 - COMPONENT FABRICATION

Modifications to the Tecogen large-scale combustion facility have been implemented to enable hot combustion tests to be made as part of the preliminary component design testing. The facility is being modified to meet the specific needs of the commercial-scale combustor. A schematic of the facility arrangement to be utilized for the component design tests is shown in Figure 3.14. For the component design tests an existing IRIS combustor will be utilized with modifications as required. A piping and instrumentation diagram for the system is given in Figure 3.15. This same arrangement will be utilized for initial combustor shakedown prior to complete system integration. In this way, combustor operation and performance can be verified without the attendant complexity of operating the downstream equipment, i.e., boiler and fabric filter, and the risk to this equipment associated with combustor off-design operation.

Figure 3.14 Combustor Test Facility Schematic

Figure 3.15 Combustor Test Facility Piping and Instrumentation Drawing

4. PLANNED ACTIVITIES

During the next reporting period, work will continue on the design of system components and subsystems. Final specifications for category a (commercially available) and category b (fully developed) components will be prepared and long-lead-time items ordered. Cold flow visualization and hot combustion tests will be performed to check out and document the performance of particular components prior to full system integration, where possible.

5. SUMMARY

During the first quarter of the program, work concentrated on the definition of the overall system configuration and the determination of the key parameters to be considered in scaling the residential CWS combustor to the commercial scale. A preliminary heat balance was developed to define the overall process and size of system components and piping. Coal properties were evaluated and predictions made for the CWS properties capable of being achieved with the selected coals.

Combustor scaling laws were developed to provide guidance in the design of the commercial-scale combustor. In particular, particle separation, reaction rate kinetics, pressure drop, and residence times were evaluated. From this analysis a preliminary geometry determination for the scaled-up unit was made.

6. REFERENCES

1. Balsavich, J., Becker, F., and Smolensky, L., "CWS-Fired Residential Warm-Air Heating System," Phase II Final Report, March 1990.
2. Smolensky, L.A., Convective Furnaces, Moscow, 1973.
3. Chigler, N. and Meyer, P.L., "The Atomization Process in Coal-Water Slurry Sprays," Eighth International Symposium on Coal Slurry Fuels Preparation and Utilization, May 1986.
4. Holve, D., Gomi, K., and Fletcher, T., "Comparative Combustion Studies of Ultrafine Coal/Water Slurries and Pulverized Coal," Seventh International Symposium on Coal Slurry Fuels Preparation and Utilization, May 1985.

END

**DATE
FILMED**

12 / 29 / 92