TECHNICAL PROGRESS REPORT

July - September 1988

For:

**U.S. Department of Energy
Pittsburgh Energy Technology Center**

Under:

**DOE Contract No. DE-AC22-87PC79654
Development of a Retrofit Coal Combustor for
Industrial Applications (Phase I-A)**

By:

**MANUFACTURING AND TECHNOLOGY CONVERSION
INTERNATIONAL, INC.**

P.O. Box 21, Columbia, Maryland 21045

October 1988

MASTER

do
DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

PREFACE

A detailed description of the background, technology and application for the development of a retrofit coal combustor for industrial applications was provided in the first quarterly report for the period January 1987 - March 1987. That material is omitted from this report. In June of 1988, DOE Contract No. DE-AC22-87PC79654 was modified with the addition of a new task, as a Phase IA, to bridge the gap between Phase I and II of the program. The descriptions of these tasks are now included in Section 1.1.

Phase IA was initiated on June 7, 1988 and this report therefore covers the period June 7, 1988 through October 2, 1988. This report does include a new Section 1.2, Task Descriptions, that provides the task structure for the Phase IA of the development effort.

A tandem-fired pulse combustion unit designed to fire at a nominal rate of 3.5-5 MMBtu/hr was designed and fabricated. The configuration includes two combustion chambers cast in a single monolith, tailpipes cast separately with annular air preheating capability, and a cyclonic decoupler. Design analysis and evaluations were performed to optimize the system with respect to minimizing heat losses, size, and cost. Heat losses from the combustor and decoupler walls are predicted to be approximately 3 percent. The final designs for the ancillary items (slag quench, tertiary air addition, scrubber and sampling system) were completed and fabrication and installation initiated. A Cleaver-Brooks 150 hp-4 pass boiler was delivered and installed and modifications for interfacing with the retrofit pulse combustor unit completed. A below-ground slag collection pit was excavated to permit direct in-line coupling of the combustor to the boiler and to reduce head-room requirements. The pit is 30 inches deep and lined with waterproof and fireproof siding. Combustor tuning tests were initiated and system shakedown tests are expected to be completed during the next quarter.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

ER80-24Q.PRE

TABLE OF CONTENTS

	<u>Page</u>
1.0 PROGRAM DESCRIPTION AND WORK STATUS	1
1.1 PROGRAM DESCRIPTION	1
1.2 TASK DESCRIPTIONS	3
1.2.1 Task 1: Optimization of the Laboratory-Scale Combustor	3
1.2.2 Task 2 (Modified): Integrated Small Industrial-Scale Pulse Combustor System (modified task)	3
1.3 PHASE 1A, INTEGRATED SMALL INDUSTRIAL- SCALE COMBUSTOR SYSTEM DEVELOPMENT	4
1.3.1 Task 1 (Phase 1A): Fabrication of the Integrated Small Industrial-Scale Combustor System	4
1.3.2 Task 2 (Phase 1A): Technical and Laboratory-Scale Support	6
1.3.3 Task 3 (Phase 1A): Scale-Up Pilot Unit Design	6
1.4 STATUS	7
2.0 TECHNICAL DISCUSSION OF WORK COMPLETED DURING THE REPORTING PERIOD	9
2.1 DESIGNS	9
2.2 DESIGN CALCULATIONS	19
2.3 FABRICATION	21
2.4 FUEL SELECTION	32
3.0 PLANNED ACTIVITY FOR THE NEXT PERIOD	34

LIST OF FIGURES

	<u>Page</u>
FIGURE 1 PROGRAM LOGIC FOR THE DEVELOPMENT OF AN ADVANCED PULSED-COAL COMBUSTOR FOR RETROFIT APPLICATIONS	2
FIGURE 2 CHAMBER DESIGN	11
FIGURE 3 TAILPIPE DESIGN ALTERNATIVES	12
FIGURE 4A SLANTED DECOUPLER	15
FIGURE 4B DECOUPLER	16
FIGURE 5 FLUIDIZED BED COAL FEEDER	18
FIGURE 6 CYCLONIC DECOUPLER	22
FIGURE 7 CHAMBERS	23
FIGURE 8 INDUSTRIAL RETROFIT SCRUBBER	25
FIGURE 9 TERTIARY AIR ADDITION	26
FIGURE 10 INTEGRATED SYSTEM LAYOUT	30
FIGURE 11 SORBENT COLLECTION AT END OF FIRE TUBE	31

LIST OF TABLES

TABLE 1 HEAT LOSS DATA	19
TABLE 2 ANTICIPATED COAL TEST FUELS	33

SECTION 1.0

PROGRAM DESCRIPTION AND WORK STATUS

1.1 PROGRAM DESCRIPTION

The objective of Phase I of the program for the development of a retrofit pulse coal combustor for industrial applications was to design, fabricate, test and evaluate advanced chamber designs at the laboratory-scale utilizing several fuels (Task 1). The activities were structured to provide design criteria for scaling up to the pilot-scale level for the demonstration of a pulse combustor fired with coal-water mixtures for industrial boiler and process heater retrofit applications. The program logic is depicted in Figure 1.

The design data and information acquired during Task 1 of the initial phase was to develop scale-up design criteria for scaling the laboratory-scale design to pilot-scale including interface requirements for the field demonstration. The scale-up pilot unit design was to be sufficiently developed to allow fabrication of the unit for testing in the existing test facility upon DOE exercising its option for the follow-on activities of this program. These follow-on activities included the fabrication, test, and engineering evaluation of the pilot-scale combustor as well as technical and laboratory test support activities for reducing the technical risks and costs of development at the pilot-scale. Based on the information, test, data and technical support activities, a retrofit combustor system was to be designed for field demonstration as shown on the left in Figure 1.

An additional effort - Phase IA - was added to the contract by modification A005. This modification substitutes the following for the original Task 2 of Phase I and added a Phase IA consisting of three technical tasks which are also subsequently described herein.

FIGURE 1: PROGRAM LOGIC FOR DEVELOPMENT OF A PULSE COAL COMBUSTOR FOR RETROFIT APPLICATIONS

1.2 TASK DESCRIPTIONS

1.2.1 TASK 1: OPTIMIZATION OF THE LABORATORY-SCALE COMBUSTOR

The specific objectives of this task are to optimize the chamber design of the feasibility units developed under Contract No. DE-AC22-83PC60419 for optimized performance with coal and coal-water slurry fuels and to reduce performance sensitivity to variations in fuel specifications.

To meet these objectives, two advanced combustion chamber configurations will be designed and fabricated at the laboratory-scale (1 - 2 MMBtu/hr) size. Design options will include both bare metal and refractory-lined units to permit both air-cooled and adiabatic operation. These advanced designs will be fabricated and then tested to evaluate the performance with respect to the following parameters:

- Combustion intensity and heat release rates,
- Staging capability,
- Dry sulfur capture and ash rejection performance,
- Carbon burnout efficiency,
- NO_x emissions performance, and
- Sensitivity to changes in fuel specifications.

Refractory-lined combustor tests will be conducted employing both the feasibility unit chamber design and one of the advanced chamber designs selected on the basis of the evaluation tests.

1.2.2 TASK 2 (MODIFIED): INTEGRATED SMALL INDUSTRIAL- SCALE PULSE COMBUSTOR SYSTEM (MODIFIED TASK)

Upon accrual of sufficient data from Task 1, Subtasks B and D, the Contractor shall develop the design for an integrated pulse combustor at the small industrial scale. The unit shall be equipped with a refractory-lined, cyclonic slag separator with a water-cooled slag collection vessel. The

design shall be in sufficient detail to allow fabrication and shall take into consideration all the requirements to interface with the boiler simulator to be used in testing under Phase IA.

1.3 PHASE 1A, INTEGRATED SMALL INDUSTRIAL- SCALE COMBUSTOR SYSTEM DEVELOPMENT

The following tasks were added by modification to the original contract and are comprised of four tasks, including a management and reporting task (Task 4). That task is not included in the following discussion.

1.3.1 TASK 1 (PHASE 1A): FABRICATION OF THE INTEGRATED SMALL INDUSTRIAL- SCALE COMBUSTOR SYSTEM

A development and test activity which is aimed at the demonstration of an integrated pulse coal combustor system fired with coal-water mixture and dry ultrafine coal for small industrial boiler and process heater applications shall be undertaken. In conducting the demonstration, the Contractor shall undertake the following two subtasks:

A. SUBTASK 1.1: INTEGRATED SMALL INDUSTRIAL- SCALE COMBUSTOR SYSTEM FABRICATION

The integrated small industrial-scale combustor system design, developed under Phase I, shall be fabricated and interfaced with a boiler simulator facility and prepared for conducting the testing and engineering evaluations described below under Subtask 1.2.

In fabricating the integrated small industrial-scale combustor system and interfacing it with the test facility, all the necessary materials, equipment, instrumentation and supplies for all facility modifications for fuel and air supplies and sound muffling provisions shall be procured.

B. SUBTASK 1.2: TESTING AND ENGINEERING EVALUATION

The Contractor shall initially conduct tests of the integrated small industrial-scale pulse combustor system with natural gas. This shall be followed by tests that employ coal-water mixtures and dry ultrafine coal.

In implementing this task, the Contractor shall prepare a test plan (for each test fuel) detailing the combustor design, facility modifications and the planned sequence, procedures and test data acquisition for conducting the test activities. The test plan shall be supplied to the DOE technical program monitor for review and approval.

Test activities shall include preliminary check-out runs to establish stable performance and overall facility readiness. Mass and energy balance calculations shall also be undertaken by the Contractor to develop procedures and methods suitable for reliable determination of the combustion efficiency.

During each test run, the Contractor shall periodically record the following measurements:

- Fuel mass flow rate and combustor pressure wave intensity
- Primary and secondary air flow rates (time average) and temperatures
- Unburned carbon loss
- Flue gas analysis (O_2 , CO_2 , CO , SO_x , NO_x , etc.)

In addition, the following test data will be taken on an as-required basis:

- Flue gas analysis of the pulsating combustor's exit gas stream using analytical equipment to determine the level of unburned hydrocarbons, if any
- Primary and secondary air flow rate vs. time
- Pressure measurements (locations determined during testing)
- Chemical and size analyses of fuel feedstock, slag and fly ash

- Heat absorbed by the furnace, flue gas flow rate, and furnace exit temperature

The Contractor shall reduce the test data and analyze and correlate the reduced data as a function of the combustor load. The data shall be compared with the combustor data obtained in Phase I to assess the effect of system integration on the combustor performance.

The Contractor shall also employ the test results to undertake an assessment of the applications to small industrial boilers and process heaters. In addition, the Contractor shall document all the operating experience including maintenance-related experiences and shall employ such information in the assessment of the commercial application of the combustor technology.

1.3.2 TASK 2 (PHASE 1A): TECHNICAL AND LABORATORY-SCALE SUPPORT

In support of the integrated system development and demonstration, defined in 1.3.1 above, the Contractor shall employ an empirical computer code for combustor performance and scale-up analysis developed in Phase I and shall employ supplemental component tests to address technical issues resulting from the integrated small industrial-scale system development work.

1.3.3 TASK 3 (PHASE 1A): SCALE-UP PILOT UNIT DESIGN

The Contractor shall develop design scale-up criteria for scaling the small industrial-scale design to pilot-scale. These criteria shall include consideration of the effect of scale-up on combustor operating frequency, firing intensity (in MMBtu/hr cu.ft.), and the intensity of pressure fluctuation with increased firing rate. The scale-up design shall also take into consideration all the interface requirements of the pilot-scale development activities at the subcontractor test site.

The combustor scale-up design developed under this task shall be in sufficient detail to allow fabrication should DOE exercise its option to proceed with Phase II.

1.4 STATUS

During this past quarter, two tandem-fired pulse combustors were designed to fire at a nominal rate of 3.5 to 5.5 MMBtu/hr under continuation of Phase I work on DOE project DE-AC22-87PC-79654.

In prior work, MTCI demonstrated the operation of a 1 - 2 MMBtu/h coal-fired tandem pulse combustor that is intended for small industrial applications. These component tests emphasized verification of key design issues such as combustor coupling, slag rejection, and staged air addition. The current work, which represents an extension of the Phase I effort, focuses on integrated testing of the tandem pulse combustor with a fire-tube boiler, and the addition of a slag quench vessel.

A tandem-fired pulse combustion unit designed to fire at a nominal rate of 3.5-5 MMBtu/hr was designed and fabricated. The configuration includes two combustion chambers cast in a single monolith, tailpipes cast separately with annular air preheating capability, and a cyclonic decoupler. Design analysis and evaluations were performed to optimize the system with respect to minimizing heat losses, size, and cost. Heat losses from the combustor and decoupler walls are predicted to be approximately 3 percent. The final designs for the ancillary items (slag quench, tertiary air addition, scrubber and sampling system) were completed and fabrication and installation initiated. A Cleaver-Brooks 150 hp-4 pass boiler was delivered and installed and modifications for interfacing with the retrofit pulse combustor unit completed. A below-ground slag collection pit was excavated to permit direct in-line coupling of the combustor to the boiler and to reduce head-room requirements. The pit is 30 inches deep and lined with waterproof and fireproof siding.

The small industrial, coal-fired pulse combustor is currently in the final stages of assembly.

Preliminary shakedown testing is anticipated to begin in early November. This will include combustor curing, check-out of burner control systems, and final combustor tuning. This will be followed by a test program to characterize the operation of the integrated system utilizing high ash, high sulfur pulverized, and slurry coal fuels. The test program is anticipated to extend through the first quarter of 1989.

SECTION 2.0
TECHNICAL DISCUSSION OF WORK COMPLETED
DURING THE REPORTING PERIOD

2.1 DESIGNS

A primary consideration in the design of the combustion chambers involved developing suitable scaling criteria for increasing the achievable firing rate by a factor of two. Tests conducted under the prior work defined the acceptable range of volumetric heat release rates for pulse combustors operating on micronized, pulverized, and slurry fuels. This data was utilized to establish minimum chamber volume requirements. Once the basic chamber volume was determined, specific dimensional relations were developed.

A. CHAMBERS

A cylindrical insert at the maximum chamber diameter can be employed, as previously shown, for modest increases in firing capacity (30%), the use of a simple insert was considered inappropriate for more substantial scale-up requirements (100%) due to the significantly different aerodynamic flow patterns which would result. If the length of the insert piece is indiscriminately increased, then the depth of the mixing zone will also increase, eventually resulting in non-uniform conditions within the chamber and excessive dissipation of the turbulent flow field prior to ignition. For this reason, the length of the cylindrical insert piece was unchanged from the prior configuration. In order to accommodate the larger chamber volume, the diameter of the insert was increased from 9 to 13 inches. This necessitated a decrease in the radius of curvature for the inlet diffuser portion of the chamber from 11 to 9 inches, and an increase in the diffuser sweep angle from 40 to 55 degrees.

In addition, the dimension of the chamber exhaust throat, and the aerovalve elements, were scaled according to the square root of the mass flow rate in order to maintain kinetic velocities approximately equivalent to the prior design.

To reduce heat loss from the chambers, it was decided to use a minimum of 3-inch thick high alumina refractory backed by an insulating layer of 2-inch thick low-density refractory. The high alumina refractory is a poor insulator with a thermal conductivity (K value measured in Btu/in/ft²/hr/°F) value of 10. This refractory is designed for high temperature (service to 3400°F). The insulating refractory has a K value of 2 to 2.5 with a working temperature to 2500°F. To design an effective insulating configuration for the two chambers, it was decided that they should be cast in a single monolith. The closer proximity of the chambers cast as a monolith will reduce potential problems relevant to coupling of the combustors. For ease of fabrication, it was decided the units should also be cast in a rectangular box. Figure 2 shows the final chamber configuration.

B. TAILPIPES

The conical tailpipes of the two chambers were increased in volume by scaling the cross-sectional area to the change in nominal throughput. The length was unchanged in order to preserve the same frequency of operation as the prior unit. Three different casings for the tailpipes were considered (see Figure 3a, b, and c) for the different designs. In the first design, the tailpipes are cast in a rectangular monolith. In the second design, the tailpipes are cast in separate pipes. In the third design, the tailpipes are cast in a monolith, but the casing includes non-rectangular end walls.

The first approach, shown in Figure 3-A, provides simplicity since only a single unit must be cast. The unit may also be easily constructed from flat steel plate. However, due to geometric constraints, this design required large amounts of refractory, and thus increases the combustor mass. In this design, it is intended that cooling air be passed through a 1/2-inch gap between the metal skin and an outside shield to provide air preheating and to

HIGH ALUMINA REFRACTORY

INSULATING REFRACTORY

FIGURE 2: CHAMBER DESIGN

FIGURE 3: TAILPIPE DESIGN ALTERNATIVES

Four basic designs were considered for the decoupler. The first design was a scaled-up model of the Phase 1 cyclonic decoupler. This design would utilize a horizontal cylinder with tangential entrances and a sloped bottom section as used in the initial tests in Phase 1. The slope would be increased for better slag drainage and the slag tap would be larger to avoid bridging.

The second design considered consisted of a half cylinder top with a lower section formed from a flat plate. The plate would be sloped at a 30-degree angle with sides either angled or vertical. The advantage of this design results from the reduction of the required amount of refractory which can be achieved without compromising the structural integrity imparted by the cylindrical geometry.

The third design consisted of a sloping cylinder with the chambers entering tangentially, opposing one another (Figure 4-A). This design deviates from the cyclonic flow concept, but provides a compact size, less complex fabrication and a sturdy support. The design incorporates an opposing tangential entrance at a 30-degree slant to the body (making it vertical). The outlet would be a refractory-lined horizontal pipe. The slag tap would be a refractory-lined vertical pipe.

The fourth and final design was a close simile of the initial design and is shown in Figure 4-B. The major distinction of the fourth design is that it is horizontal instead of angled. The final design utilizes tangential entrances for cyclonic slag removal. In the prior tests, the decoupler, due to high heat losses, operated at a lower temperature than anticipated for the better insulated version described here. Thus the slag viscosity in the prior tests was high and a sloped surface was necessary for proper slag flow. In the new unit, higher temperatures will be achieved and slag viscosities as low as 10 poise can be anticipated allowing efficient slag drainage in the horizontal state due to the high cyclonic velocities at the tailpipe exit. As the gases move down the decoupler they will move the slag towards the drain and into the slag quench vessel. It is now believed that the combination of high centrifugal forces in the decoupler and the higher temperature of operation will allow efficient slag capture without the need for slag screens.

FIGURE 4-A: SLANTED DECOUPLER

FIGURE 4-B: DECOUPLER

Also, since the slag screens pose a potential for bridging and plugging, they have been avoided.

D. COAL FEEDER

Although much of the testing will be performed using CWM, some of the shakedown testing will include the use of dry coal. Because of this, a need existed for a reliable continuous flow dry coal feeder. Screw feeders feed a metered amount of coal which is uniform over time scales of many seconds, but their short term uniformity is poor. As the screw turns, different amounts of coal are fed during the different part of the screw rotation. MTCI's pulse combustors run at a frequency of 60 cycles per second, therefore, some cycles would get much more coal than other cycles. An alternative concept, a fluidized bed coal feeder, was tested and appears to offer a significantly improved means for continuously feeding coal at a uniform rate.

The fluidized bed coal feeder uses an eductor to draw coal from the fluidized bed. As long as the supply pressure to the eductor and the fluidized bed height remain constant, the feed rate will be constant. Any variance caused from the pressure fluctuations of the pulse combustors will be at the same frequency as the pulse combustors, and should therefore not affect the feed rate per cycle. The fluidized bed coal feeder was built and tested during this period. The tests look very positive in a semi-batch mode. Work will be continued enabling the feeder to run in a continuous mode with the addition of a lock-hopper (Figure 5).

E. BOILERS

Several used industrial gas and oil-fired boilers have been considered for this project. The boilers considered were a 125 hp 2 pass boiler that would have to be re-tubed before being purchased, a 150 hp 4 pass boiler which was in working condition, a 200 hp 4 pass boiler that required significant refurbishing, and a 150 hp boiler which must be stripped of asbestos. A decision was made to purchase the 150 hp 4 pass gas-fired boiler which

FIGURE 5: FLUIDIZED BED COAL FEEDER

appeared to offer the most rapid turn around time of the various choices considered. The preliminary decision was also based on price, the condition of the boiler, and its suitability for the application.

2.2 DESIGN CALCULATIONS

Calculations were made to estimate the heat losses and skin temperatures of the tailpipes and decoupler. The design calculations were made for two different K values (thermal conductivity) of insulating refractory, 2 and 2.5. The flue gas temperature was assumed to be 3000°F and ambient room temperature 100°F. A summary of these calculations is provided in Table 1.

TABLE 1: HEAT LOSS DATA

	<u>MAXIMUM WALL TEMPERATURE (°F)</u>	<u>HEAT LOSS (BTU/HR)</u>
CHAMBERS	400	20,000
TAILPIPES		
Insulating Layer		
K = 2	430	60,000
K = 2.5	463	66,000
DECOUPLER		
Insulating Layer		
K = 2	451	74,000
K = 2.5	507	86,000
K = 2.5 + 1/4" paper	426	68,000

Two different insulating refractories are presently being considered. Both refractories have a working temperature of 2500°F. The first refractory has a higher density, 87 lbs/ft³, and a higher thermal conductivity, 2.5. The second refractory is less dense with a lower thermal conductivity, 2.0. The less dense refractory would raise the working temperature, the high temperature refractory interface, but would reduce the heat loss and therefore lower the outside wall temperature. The denser refractory would provide more

strength and give a lower interface temperature. The use of a layer of Kaowool Ultrafelt, 1/4-inch thick, with a thermal conductivity of 0.4 is also being considered to lower the outside wall temperature.

The decoupler, with 3 inches of high alumina refractory and 3 inches of an insulating refractory with a K value of 2.5 would have a skin temperature of 507°F and a heat loss of 86,000 Btu/hr. This would represent a heat loss of 2.5 percent firing at 3.5 MMBtu/hr. If the dense insulating refractory was replaced with an less dense insulating refractory with a K value of 2, the wall temperature would drop to 451°F. The heat loss in this case would be 74,000 Btu/hr. If a sheet of Kaowool Ultrafelt was used with the dense refractory, the wall temperature would drop to 426°F with a heat loss of 68,000 Btu/hr, or 2.0 percent. No attempts would be made for heat recovery from the decoupler in this phase.

A critical design criterion for the tailpipes is to keep the metal skin temperature below 600°F to prevent damage or excessive oxidation of the metal pipes. Heat will be recovered from the tailpipes by circulating air for combustion. Due to the conical design of the tailpipes, a minimum thickness of 3 inches of high alumina refractory was designed with a constant 2-inch layer of insulating refractory. No insulating paper will be used. At the hottest spot the metal temperature will be 550°F with the dense refractory. The heat recovered in preheating combustion air would be 66,000 Btu/hr. With the less dense refractory the highest temperature would be 501°F. The heat loss to the air in this case would be 60,000 Btu/hr. At least 30 percent combustion air will be passed through the preheater to insure adequate skin cooling.

Heat loss from the chamber section was approximated based on the insulation thickness and anticipated chamber temperature. The estimated value was 20,000 Btu/hr. The maximum wall temperature will be approximately 400°F.

The unit was designed for a nominal firing rate of 4 MMBtu/hr. It is anticipated that it may be capable of operating up to +5 MMBtu/hr. At an average 4 MMBtu/hr firing rate the coal throughput will be 267 lbs/hr dry

solids. The air requirement for this firing rate will be 683 scfm at stoichiometric conditions. The primary combustors will be run substoichiometric (approximately 80 percent) with air addition as the gases enter the boiler to bring the excess air up to 10 to 20 percent.

2.3 FABRICATION

Fabrication of the combustors and decoupler was initiated during this period. The metal casing has been constructed and the first layer of refractory has been poured. The molds for the high-temperature refractory were received and the fabrication was completed on these components and installation was begun.

Pictures of the cyclonic decoupler during assembly can be seen in Figures 6 and 7. The decoupler was fabricated in two sections to facilitate pouring. The cylindrical section protruding into the decoupler (as seen in Figure 6) promotes a vortex flow pattern for improved slag particulate removal. The chambers can be seen in Figure 7. They were cast in a single section with tubes creating orifices for pressure and temperature ports.

Three refractories were chosen for pouring the units. The first refractory, Kaolite 75, was an insulating refractory with a thermal conductivity of $2.5 \text{ Btu-in/}^{\circ}\text{F/ft}^2\text{/hr}$. This refractory was used as the insulating refractory for the decoupler and chambers. A paper insulation was placed between the wall and the refractory to reduce heat loss. The second refractory, Litecrete 2500, was an insulating refractory with a thermal conductivity of 2.0. This refractory was poured in the tailpipes where the use of paper insulation was impractical. The third refractory was the high alumina high-temperature refractory, Pyrotab 3300, used for all hot face surfaces.

The fluidized bed dry coal feeder was built and tested in-house. The system works well in the small batch mode (200 lbs) and will be integrated with a lock hopper for continuous use. In addition to the combustors, decoupler and coal feeder, several system ancillary items were also designed and fabricated.

FIGURE 6: CYCLONIC DECOUPLER

FIGURE 7: CHAMBERS

A. SCRUBBER

A scrubber rather than a baghouse was chosen to clean the flue gas after it exits the boiler due to the ease of fabrication and decreased pressure drop. Three scrubber designs were explored. The first design was to duplicate, at a larger scale, the scrubber used in Phase I of the project. In this design, the flue gases are passed through a layer of packing counter-current to a water stream to remove the ash and to quench the gases. The second and third designs employ a simple spray tower without packing, the second using a co-current spray scrubber and the third a counter-current spray scrubber. To simplify fabrication, the counter-current spray scrubber was chosen. The diameter of the scrubber will be 28 inches to allow for the greatest particulate capture (with smaller diameters, the gas velocity is too high for effective particle removal).

The counter-flow scrubber will be used following the boiler to provide a final level of particulate removal in order to ensure compliance with California emissions standards. Flue gas will flow through the scrubber at approximately 4 ft/s with a counter flow water rate of 40 GPM. The scrubber will employ a pump-around with a filter circuit to accommodate collected particulate matter and prevent plugging of the spray nozzles. Fabrication was initiated on the counter flow scrubber during this reporting period. Final installation of the scrubber will be completed in October. The scrubber design can be seen in Figure 8.

B. TERTIARY AIR

The tertiary air addition unit was fabricated during this reporting period. The tertiary air component serves three functions: to provide means for interfacing the decoupler with the boiler, to preheat and evenly mix the tertiary air with the combustion gases, and to allow free expansion of the hot internal flue gas conduit. The outlet was reduced from 24 in. in the original design to 18 in. to facilitate connection with the boiler. The final design is shown in Figure 9.

FIGURE 8: INDUSTRIAL RETROFIT SCRUBBER

FIGURE 9: TERTIARY AIR ADDITION

The tertiary air addition will pass the air through an annulus surrounding the main combustion gas port as it enters the boiler, as shown in Figure 9. The outside casing will be lined with a low temperature insulating refractory. Inside this refractory lined casing, a 1-inch air gap is formed to allow the tertiary air to pass into the boiler. A smaller diameter stainless steel tube which is lined with high-temperature refractory forms the main combustion gas port.

Passing the air through an annulus provides several advantages. First, air is evenly distributed around the combustion gases to allow effective mixing. Second, the annular space serves as a preheater, thus limiting any quenching that may be caused by adding cool air. Third, expansion of the transition section between the decoupler and boiler will be reduced due to the cooling effect of the tertiary air on the outside casing. The inside section will only be fixed on one end and therefore may expand freely. The outside casing, which is fixed at both ends, will be kept cool by the tertiary air and will therefore not expand greatly.

C. SPENT SORBENT REMOVAL

MTCI's advanced combustor has been configured to accept high ash pulverized grind (dry or slurry) fuels by rejecting slag in a molten state upstream of the boiler. In order to achieve effective slagging, temperatures above 2600°F are generally required in the slag tap zone. We anticipate that the combustor and decoupler will operate nominally at a fuel-rich stoichiometry of 80 percent and a temperature of 2800°F to 3000°F. While the principles of up-front ash rejection are straight forward, the issue relevant to capturing sulfur in an efficient and practical manner are less clear. Several approaches for sulfur capture are being considered. In one approach, the combustor is operated at approximately 80 percent stoichiometry and slag is rejected in the temperature range of 2800°F - 3200°F. Following the slag tap, a secondary fuel is injected into the flue gas stream to reduce the overall stoichiometry to about 60 percent and the temperature to 2300°F. At this lower temperature, calcium-based sorbents can be added to achieve sulfur capture as calcium sulfide with reasonably high efficiency. The dry calcium

sulfide particles are recovered in a cyclone before the hot flue gases are mixed with tertiary air to complete burnout prior to entering the boiler. While this approach offers the advantage of upstream rejection of both ash and sulfur, it appears to have some significant disadvantages. First, the use of premium fuel (up to 25% of the total fuel requirement) is anticipated to significantly and adversely effect the system's operating economics. Secondly, the combustor virtually becomes a gasifier at the specified 60 percent stoichiometry level. Since 40 percent of the carbon burnout must be completed after exiting the primary combustor, it is anticipated that the system's carbon burnout efficiency will suffer. Finally, sorbent is rejected in the less desirable calcium sulfide form which is costly to dispose.

The use of an alternative approach for commercial applications of the MTCI advanced combustor appears to be particularly well suited to the fire tube boiler applications which have been targeted.

The MTCI combustor will operate at approximately 80 percent stoichiometry and a temperature of 3000°F where slag viscosities are low enough to allow efficient ash rejection. The hot combustion products will then be mixed with preheated tertiary air downstream or the slag tap prior to entering the boiler fire tube. As the hot flue gases pass through the radiant fire tubes, they are cooled to approximately 2000°F at the cross-over to the convective fire tubes. This temperature is relatively constant for most boiler models, and is only moderately sensitive to boiler load.

Furthermore, this temperature represents a nearly optimum regime for capturing sulfur as CaSO_4 using inexpensive limestone sorbents. Due to these properties, we anticipate injecting sorbents into the fire tube where they will be calcined prior to passing through the optimum temperature window for sulfur capture. A simple extension piece will then be added to the fire tube to allow it to penetrate through the backwall of the boiler. The extension piece will then be terminated at a cyclone where the dry sorbent particles will be separated with high efficiency. The hot flue gases will then be returned to the cross-over of the boiler at the point of entry to the convective fire tubes. The necessary boiler modifications needed to accommodate

this approach are considered to be relatively minor. A schematic of the proposed system is shown in Figures 10 and 11.

This approach has several advantages compared to alternative schemes. First, no premium fuels, water injection, or flue gas recycle are necessary to achieve optimum temperatures for efficient sulfur capture. Rather, the existing boiler itself is utilized to remove heat to achieve the desired temperature regime. Second, no complex staging of the combustor is needed, and combustion efficiency is not compromised by imposing highly fuel rich conditions. Third, sulfur is rejected as stable calcium sulfate which can be inexpensively disposed.

For these reasons, it is anticipated that this approach to sulfur capture for commercial configurations will be more cost effective than alternative approaches in fire tube boiler applications. Furthermore, the basic operating principles of the combustor are not directly impacted by the requirement for sulfur capture and optimize combustor operation separately from sulfur capture considerations. Furthermore, there exist coal fuels which are low in sulfur but contain modest ash levels. Under these circumstances, ash rejection is required, however, sulfur emission levels may be within target goals even without sulfur removal. For these cases, only a front-end combustor with ash rejection is needed.

Although the extended Phase IA scope of work for this project does not specifically include the use of sulfur sorbents during the combustion tests, it is important to address these issues early on to ensure that the commercial configuration of the MTCI combustor is suitable for sulfur capture. The principles of sulfur capture in the proposed manner are considered to be a proven process, if time and funds allow, sorbent injection tests will be attempted toward the end of the test program.

FIGURE 10: INTEGRATED SYSTEM LAYOUT

FIGURE 11: SORBENT COLLECTION AT END OF FIRE TUBE

D. BOILER

During the month of September the boiler was delivered and installed. Before the boiler could be delivered, an insulating layer of asbestos was removed for safety reasons. Once in place, the boiler was leak tested and proper functioning of level control elements, dampers, and ports were verified. Modification to the boilers front end was also necessary for proper placement of the MTCI retrofit combustor.

After positioning the boiler and defining siting requirements for the scrubber, combustor and ancillaries, a slag pit was excavated to accommodate a below-ground slag collection vessel. The below-ground slag pit was employed to allow direct in-line coupling of the combustor to the boiler and to reduce headroom requirements. The slag collection pit is 30 in. deep, 24 in. wide and 66 in. long. The sides are lined with a waterproof and fireproof siding. Gravel was placed in the subfloor. A 30-gallon drum will be used for the water-quench slag collection vessel.

E. INSTRUMENTATION

The combustion system will be outfitted with a burner control unit which includes a UV flame sensor. Individual sensors will be provided for each combustion chamber. The controller will be configured to actuate a shutdown response upon detection of a flame failure. In addition, a PC-based combustion supervisor is being considered for automation of the start-up sequence.

2.4 FUEL SELECTION

Two primary fuels have been selected for the test program. These include a standard dry pulverized fuel and a pulverized grind slurry fuel. The specifications for these fuels are shown in Table 2. Both the dry and slurry fuels are derived from the same parent coal and contain 5.5 percent ash and 0.8 percent sulfur. We intend to order three tons of each from Energy International which will allow a minimum operation of about 20 hours for each

fuel. We also anticipate short runs with a dry pulverized lower Kittanning coal containing 12.39 percent ash and 2.17 percent sulfur. This coal will be more suitable for sulfur capture tests, should time and funds allow investigation of this aspect.

TABLE 2:
ANTICIPATED COAL TEST FUELS

	<u>LOWER KITTANNING</u>	<u>E.I. SUPPLY</u>	<u>E.I. SUPPLY</u>
Form	Dry Pulv.	Dry Pulv.	Pulv. Slurry
Ash %	12.38	5.5	5.5
Sulfur %	2.17	0.8	0.8
Quantity, Ton	1	3	3

SECTION 3.0

PLANNED ACTIVITY FOR THE NEXT PERIOD

The work schedule for the next quarter includes completing the installation of the units, fabricating the control panel, and preliminary tuning tests. The tuning tests and system shakedown tests are anticipated to be completed in November. An analysis of the data and operability during the shakedown testing may lead to some component design modifications. These modifications, if required, will be made and verification shakedown tests will be initiated.

END

DATE
FILMED
5/12/93