EMO Environmental
Management
Operations

Received
APR 2 - 1 1992

**Contingent Post-Closure Plan
Hazardous Waste Management Units
at Selected Maintenance Facilities
U.S. Army National Training Center
Fort Irwin, California**

January 1992

**Prepared for U.S. Army Toxic and Hazardous Materials
Agency and The National Training Center
Fort Irwin, California
Under Contract DE-AC06-76RLO 1830**

**Environmental Management Operations
Operated for the U.S. Department of Energy
by Battelle Memorial Institute**

Approved for Public Release; Unlimited Distribution

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor Battelle Memorial Institute, nor any of their employees, makes **any warranty, expressed or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.** Reference herein to any specific commercial product, process, or service by trade name, trademark manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government of any agency thereof, or Battelle Memorial Institute. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

ENVIRONMENTAL MANAGEMENT OPERATIONS

operated by

BATTELLE MEMORIAL INSTITUTE

for the

UNITED STATES DEPARTMENT OF ENERGY

under Contract DE-AC06-76RLO 1830

**Contingent Post-Closure Plan
Hazardous Waste Management Units
at Selected Maintenance Facilities
U.S. Army National Training Center
Fort Irwin, California**

January 1992

Prepared for the U.S. Army Toxic and Hazardous Materials
Agency and the National Training Center through a Related
Services Agreement with the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830

Prepared by Battelle, Pacific Northwest Division
for Environmental Management Operations
under a Related Services Agreement
with the U.S. Department of Energy

**Environmental Management Operations
Richland, Washington 99352**

MASTER

LIST OF ACRONYMS AND ABBREVIATIONS

AR	Averaged Replicate
ASC	Aboveground Storage Container
CFR	Code of Federal Regulations
DEH	Director of Engineering and Housing
DHS	Department of Health Services
DOT	Department of Transportation
DL	Detection Limit
EMO	Environmental Management Operations
EPA	Environmental Protection Agency
FFCA	Federal Facility Compliance Agreement
HAZCO	Hazardous Waste Management Contractor
HWMA	Hazardous Waste Management Area
HWMU	Hazardous Waste Management Unit
NON	Notice of Noncompliance, Notice of Necessity for Conference, and Proposed Compliance Schedule
MCL	Maximum Contaminant Level
ml	milliliter
NTC	National Training Center
N.T.U.	Nephelometric Turbidity Unit
NWWA	National Water Well Association
OSWER	Office of Solid Waste and Emergency Response
PC	Post-Closure
POL	Petroleum, Oil, and Lubricants
PVC	Polyvinyl Chloride
QA/QC	Quality Assurance/Quality Control
RCRA	Resource Conservation and Recovery Act
TEGD	Technical Enforcement Guidance Document
USATHAMA	U.S. Army Toxic and Hazardous Materials Agency
UST	Underground Storage Tank

CONTENTS

	<u>PAGE</u>
1.0 INTRODUCTION	1.1
1.1 BACKGROUND	1.1
1.2 INSTALLATION DESCRIPTION	1.2
1.3 PURPOSE AND OBJECTIVE OF POST-CLOSURE	1.8
1.4 SCOPE OF POST-CLOSURE ACTIVITIES	1.8
2.0 GROUNDWATER MONITORING	2.1
2.1 NUMBER, LOCATION, AND DESIGN OF WELLS	2.1
2.1.1 Number of Wells	2.1
2.1.2 Location of Wells	2.2
2.1.2.1 Hazardous Waste Management Area #1	2.2
2.1.2.2 Hazardous Waste Management Area #2	2.4
2.1.2.3 Hazardous Waste Management Area #3	2.5
2.1.2.4 Hazardous Waste Management Area #4	2.5
2.1.3 Well Design	2.6
2.1.3.1 Well Installation	2.9
2.1.3.2 Well Development	2.9
2.1.3.3 Well Surveying	2.11
2.2 SAMPLING AND ANALYSIS	2.12
2.2.1 Background Concentrations and Frequency of Sampling	2.12
2.2.2 Sampling Methods and Procedures	2.15
2.2.3 Field Measurements	2.16

CONTENTS
(Cont'd.)

	<u>PAGE</u>
2.2.4 Equipment Decontamination and Disposal of Residuals	2.16
2.2.5 Sample Containers and Preservation	2.17
2.2.6 Sample Documentation	2.17
2.2.6.1 Field Log Book	2.17
2.2.6.2 Sample Labeling	2.20
2.2.6.3 Sample Seals	2.21
2.2.6.4 Chain-of-Custody Procedures	2.21
2.2.7 Sample Packaging and Shipment	2.22
2.2.8 Quality Assurance/Quality Control	2.22
2.2.8.1 Field Quality Control Checks	2.22
2.2.8.2 Laboratory Quality Control Checks	2.23
2.2.8.3 Laboratory Quality Control Checks	2.24
3.0 EVALUATION AND RESPONSE	3.1
4.0 RECORDKEEPING AND REPORTING	4.1
5.0 MAINTENANCE INSPECTIONS AND ACTIVITIES	5.1
5.1 STRUCTURES AND FACILITIES	5.1
5.2 GROUNDWATER MONITORING SYSTEMS	5.1
5.3 FREQUENCY OF INSPECTIONS AND MAINTENANCE ACTIVITIES	5.3
5.4 SECURITY SYSTEMS	5.3
5.5 RESPONSIBLE PARTY	5.3

CONTENTS
(Cont'd.)

	<u>PAGE</u>
6.0 POST-CLOSURE NOTICES	6.1
7.0 POST-CLOSURE CERTIFICATION	7.1
8.0 REFERENCES	8.1
 APPENDIX A - CHAIN-OF-CUSTODY RECORD	
APPENDIX B - DESCRIPTION OF STUDENT'S T-TEST APPLIED TO GROUNDWATER SAMPLING STATISTICS	
APPENDIX C - OUTLINE OF GROUNDWATER ASSESSMENT PROGRAM	
APPENDIX D - HAZARDOUS WASTE MANAGEMENT AREA INSPECTION LOG	

FIGURES

1.1 Regional Location Map	1.3
1.2 Facility Map, Fort Irwin, California	1.5
2.1 Hazardous Waste Management Areas and Monitoring Well Locations Fort Irwin, California	2.3
2.2 Monitoring Well Construction Details	2.7
3.2 Evaluation and Response Decision Tree	3.2

TABLES

1.1 Summary of HWMUs at Selected NTC Maintenance Facilities	1.6
2.1 Well Design and Construction Data	2.10
2.2 Analytical Parameters and EPA Test Methods for Groundwater Sampling	2.13
2.3 Sample Containers, Preservations, and Holding Times for Groundwater Samples	2.18

1.0 INTRODUCTION

1.1 BACKGROUND

The National Training Center (NTC) at Fort Irwin, California, is a U.S. Army training installation that provides tactical experience for battalion/task forces and squadrons in a mid- to high-intensity combat scenario. Through joint exercises with the U.S. Air Force and other services, the NTC also provides a data source for improvements of training doctrines, organization, and equipment. To meet the training and operational needs of the NTC, several maintenance facilities provide general and direct support for mechanical devices, equipment, and vehicles. Maintenance products used at these facilities include fuels, petroleum-based oils, lubricating grease, various degreasing solvents, antifreeze (ethylene glycol), transmission fluid, brake fluid, and hydraulic oil. Used or spent petroleum-based products generated at the maintenance facilities are temporarily accumulated in underground storage tanks (USTs), collected by the NTC hazardous waste management contractor (HAZCO), and stored at the Petroleum, Oil, and Lubricant (POL) Storage Facility, Building 630, until shipped off site to be recovered, reused, and/or reclaimed. Spent degreasing solvents and other hazardous wastes are containerized and stored on-base for up to 90 days at the NTC's Hazardous Waste Storage Facility, Building 703.

On or about March 15, 1988, the U.S. Environmental Protection Agency (EPA) Region IX performed an inspection and reviewed the hazardous waste management operations of the NTC. Additionally, on or about March 6 and 7, 1989, the EPA conducted a sampling inspection of selected Hazardous Waste Management Units (HWMUs). Information gathered by the EPA during these inspections indicated that the NTC had violated one or more requirements of Subtitle C of the Resource Conservation and Recovery Act (RCRA) (42 U.S.C. 6921, et seq.), specifically Sections 3004 and 3005 of RCRA (42 U.S.C. 6924 and 6925). As a result of these violations, the U.S. Department of the Army was issued a Notice of Noncompliance, Notice of Necessity for Conference, and Proposed Compliance Schedule (NON) dated October 13, 1989.

The EPA and the Army have negotiated a Federal Facility Compliance Agreement (FFCA) in accordance with Executive Order 12088. This agreement provides a compliance-based approach for the NTC to respond to the regulatory violations cited in the NON. Through the FFCA process, the NTC will work with the EPA and the State of California to permanently resolve any and all issues contained in the NON, using the FFCA as an administrative guideline.

Battelle Environmental Management Operations (EMO) was retained by the U.S. Army Toxic and Hazardous Materials Agency (USATHAMA) to provide environmental support during the process of correcting the violations identified in the NON and preparing required submittals pursuant to the compliance schedule established in the FFCA.

This post-closure plan is being prepared in response to Item 30 of the FFCA and in accordance with the requirements specified in Title 40, Code of Federal Regulations, Part 265, Subpart G (40 CFR 265, Subpart G). The activities in the post-closure plan are contingent on the closure activities specified in the Closure Plan for Hazardous Waste Management Units at Selected Maintenance Facilities (Earth Technology, 1992). The Closure Plan was prepared by The Earth Technology Corporation (Earth Technology), under the direction of EMO, to address issues identified in Count 15 of the NON and the requirements of Item 30 of the Compliance Schedule in the Draft FFCA dated August 6, 1990. As specified in 40 CFR 265.197(b), post-closure care will be implemented if it is demonstrated during closure that all of the contaminated cannot be practicably removed or decontaminated.

1.2 INSTALLATION DESCRIPTION

The NTC is located at the Fort Irwin Military Reservation in San Bernardino County, California, approximately 35 miles northeast of the City of Barstow (Figure 1.1). The installation is geographically situated in the Mojave Desert, midway between Los Angeles, California and Las Vegas, Nevada. The U.S. Naval Weapons Center, China Lake, adjoins the NTC's western boundary. North, east, and south of the installation are federal lands under the jurisdiction of the U.S. Bureau of Land Management.

Post-Closure Plan for Maintenance Facility HWMUs
 Battelle Environmental Management Operations
 Project No: 90-352

REGIONAL LOCATION MAP

Figure 1.1

The NTC encompasses an area of approximately 970 square miles. Approximately 85 percent of this area serves as maneuver areas for training operations, artillery impact areas, and buffer safety zones. The cantonment area (troop housing and support areas) is located in the south-central portion of the installation at geographical coordinates 35°15' north latitude and 116°41' west longitude. Information regarding geologic and hydrogeologic conditions at the NTC is presented in the Closure Plan, Hazardous Waste Management Units at Selected Maintenance Facilities (Earth Technology, 1992). The NTC maintenance facilities are located throughout the cantonment area (Figure 1.2).

The HWMUs associated with each NTC maintenance facility were designed and constructed to store waste POL and antifreeze. These units include aboveground storage Containers (ASCs), underground storage tanks (USTs), and oil sumps. A summary of the HWMUs that are being addressed in this plan at each NTC maintenance facility is presented in Table 1.1. The table includes the facility number, the facility name or primary function, the type of HWMUs, and the HWMU design capacity.

Barstow Road serves as the only paved access to the NTC. Traffic patterns at the installation are confined to the cantonment area. Traffic within each maintenance facility containing HWMUs varies from moderate to heavy depending on current activities mandated by the base (e.g., rotational mobilization and training exercises). Access to the cantonment area is restricted by a gate and guardhouse on Barstow Road. The Military Police are responsible for security at the NTC and man the guardhouse 24 hours a day to monitor and control installation entrance and egress. All unauthorized personnel must register at the main gate and obtain a pass prior to entering the cantonment area.

Surface waters at the NTC are extremely scarce. Virtually no water exists in streambeds and riverbeds, except following infrequent, heavy rainfalls. Data supplied by the U.S. Army Corps of Engineers, Los Angeles district, indicate that the 100-year floodplain occurs at the 2,381-foot elevation. The elevation of the maintenance facilities containing HWMUs ranges from approximately 2,525 feet at the Self-Help Auto Shop (Building 910) to 2,395 feet at the General Support Maintenance Facility (Building 879).

North

Armored Battal

Infantry Battalion Maintenance
Bldg 680

5th Street

Special Support
Vehicle Maintenance Facility
Bldg 612

FLOOD CONTROL
LEVEE
DRAINAGE
CHANNEL

Goldstone Road

Roads and Grounds Vehicle
Maintenance Facility
Bldg 367

AAFES PX Service Station
Bldg. 909

Self-Help Car Wash
Bldg. 910

Range Vehicle
Maintenance
Bldg 626

Equipment Support
Light Track Maintenance
Bldgs. 611, 612

Inner Loop Rd.

Barstow Road

FLOOD CONTROL LEVEE

DRAINAGE
CHANNEL

South Loop Rd.

Mobil
Equip
Mainten

TABLE 1.1. Summary of HWMUs at NTC Maintenance Facilities
(Page 1 of 2)

<u>Facility Number</u>	<u>Facility Name</u>	<u>HWMU^(a)</u>	<u>Quantity</u>	<u>Design Capacity (gallons)</u>
367	Roads and Grounds Vehicle Maintenance Facility	ASC	1	400
612	Special Support Vehicle Maintenance Facility	ASC	1	400
614	Motorpool Vehicle Maintenance Facility	ASC	1	400
626	Range Vehicle Maintenance Facility	ASC	1	600
630	POL Storage Facility	Oil Sump	1	57,000
636	Vehicle Rough Wash Facility	UST	1	550
639-642	Wheel Vehicle Maintenance Facility	ASC	3	400
646-650	Equipment Support Division Light Track Maintenance Facility	ASC	1	600
		UST ^(b)	1	10,000
652	Vehicle Wash Rack Facility	UST	1	550
680	Infantry Battalion Maintenance Facility	ASC	3	600
		UST	1	2,000
		OWS	1	1,200
681	Infantry Battalion Maintenance Facility	ASC	3	600
		UST	1	2,000
		OWS	1	1,200
682	Vehicle Wash Rack Facility	UST	1	2,000
824	Vehicle Wash Rack Facility	UST	1	550
830	Heavy Track Maintenance Facility	ASC	2	400
		UST	1	600
		OWS	1	24,000

Notes: (See bottom of page 3 of this table).

TABLE 1.1. Summary of HWMUs at NTC Maintenance Facilities
(Page 2 of 2)

<u>Facility Number</u>	<u>Facility Name</u>	<u>HWMU^(a)</u>	<u>Quantity</u>	<u>Design Capacity (gallons)</u>
840	MATES Maintenance Facility	ASC	5	400
873	Direct Support Maintenance Facility	ASC	1	600
		UST	1	2,000
		UST	1	1,000
		OWS	1	700
		OWS	1	6,000
		Oil Sump	1	1,000
879	General Support Maintenance Facility	ASC	1	400
		UST	1	2,000
		UST	1	1,000
		OWS	1	700
		OWS	1	12,000
		Oil Sump	1	1,000
909	AAFES PX Service Station	UST	1	550
910	Self-Help Auto Shop	UST	1	550

(a) HWMU = Hazardous Waste Management Unit
 ASC = Aboveground Storage Tank
 UST = Underground Storage Tank
 OWS = Oil/Water Separator

(b) Tank has been removed, but closure of the site is required.

To protect the cantonment area against flash flooding from the nearby uplands, a levee composed of compacted earthfill was constructed around the northwest to southwest sides of the cantonment area.

1.3 PURPOSE AND OBJECTIVE OF POST-CLOSURE

The owner or operator of a HWMU is required to have a written closure plan. According to the closure plan for the HWMUs at the NTC, all hazardous waste residues and contaminated facility equipment, structures, containment system components and soils will be removed or completely decontaminated during closure (Earth Technology, 1992). However, in the event that all contaminated soils cannot be practicably removed or decontaminated, post-closure care, as outlined in this plan, must be implemented to minimize or eliminate releases of hazardous waste, hazardous waste constituents, leachate, contaminated run-off, or hazardous waste decomposition products to the ground, surface waters or atmosphere.

1.4 SCOPE OF POST-CLOSURE ACTIVITIES

The following sections address the contingent post-closure care requirements for the NTC. Section 2.0 describes groundwater monitoring plan including the number, location, and design standards of wells; the frequency of groundwater sampling; types of analyses; and procedures for sampling and analysis. Section 3.0 describes the evaluation of and response to the groundwater monitoring results. Recordkeeping and reporting requirements are presented in Section 4.0. Inspection and maintenance procedures are discussed in Section 5.0. The final two sections, 6.0 and 7.0, describe required post-closure notices and post-closure certification, respectively.

Post-closure care must be initiated after final closure and continue for 30 years. The Regional Administrator may shorten or extend the post-closure period at any time prior to or during the post-closure period. He may shorten the period if he finds that the reduced period is sufficient to protect human health and the environment. He may extend the period if he finds it is necessary to protect human health and the environment.

2.0 GROUNDWATER MONITORING

If it is demonstrated that all contaminated soil cannot be practicably removed or decontaminated during closure of the hazardous waste management units, a groundwater monitoring program must be implemented as part of post-closure care. The groundwater monitoring program must be capable of determining a HWMU's impact on the quality of the groundwater in the uppermost aquifer underlying the HWMU. The program will be based upon a thorough hydrogeological characterization of the site and will include the use of groundwater monitoring systems consisting of several monitoring wells. Methods and procedures presented in the following sections are in accordance with the National Water Well Association (NWWA)/EPA publication Manual of Groundwater Sampling Procedures (Salf, 1981) and EPA RCRA Groundwater Monitoring Technical Enforcement Guidance Document (TEGD) (Office of Solid Waste Emergency Response (OSWER)-9950.0). A description of the components of the groundwater monitoring systems and sampling and analysis procedures are presented in the following sections.

2.1 NUMBER, LOCATION, AND DESIGN OF WELLS

The number, location, and design of the monitor wells comprising the groundwater monitoring systems is based on the requirements specified in 40 CFR 265, Subpart F, and available information regarding depth to groundwater and groundwater flow direction obtained during 1988 (Wilson F. So, 1989). Prior to implementation of the post-closure plan, depths to groundwater and groundwater flow directions will be verified and the number, location, and design of wells modified accordingly.

2.1.1 Number of Wells

To meet the groundwater monitoring requirements specified in 40 CFR 265, Subpart F, a groundwater monitoring system must yield groundwater samples for analysis that are representative of the uppermost aquifer and must consist of the following:

1. At least one monitoring well installed hydrogeologically upgradient of the hazardous waste management area to obtain data on background groundwater quality. This well(s) must yield groundwater samples that are not affected by the HWMUs for which it is providing background data. Additionally, more than one upgradient well may be required to account for heterogeneity in background groundwater quality.
2. At least three monitoring wells installed hydrogeologically downgradient at the limit of the waste management area to provide for immediate detection of any statistically significant amounts of hazardous waste or hazardous waste constituents that migrate from the HWMU to the uppermost aquifer.

2.1.2 Location of Wells

The HWMUs have been grouped into four hazardous waste management areas (HWMAs) for groundwater monitoring purposes. Each HWMA will utilize individual groundwater monitoring systems. However, some wells may be used as a part of more than one system. Existing wells will not be utilized due to large perforation intervals and well depths in some of the existing wells and the lack of well construction information in others. A map of the cantonment area illustrating the HWMAs, the HWMUs within in each area, and the monitoring wells to be installed is presented in Figure 2.1.

2.1.2.1 Hazardous Waste Management Area #1. HWMA #1 consists of eleven HWMUs (three USTs, six ASCs, and two OWSs) located at three facilities. Based on available information, groundwater flow in the area is in a south to southwesterly direction. A hydrogeologically upgradient monitoring well (Post-Closure (PC)-1) will be installed approximately 650 yards northeast of the Building 681 entrance just south of Barstow road (Figure 2.1). The well location was selected to yield groundwater samples representative of groundwater unaffected by the HWMUs in HWMA #1.

The three downgradient monitoring wells will be located along the south and southwestern boundaries of the HWMA (Figure 2.1). Well PC-2 will be located on the north side of Barstow Road at the western-most limit of HWMA #1. Well PC-3 will be installed at the middle of the HWMA's southwestern limit, approximately 250 feet

1. All monitoring wells are shown as PC-1 symbols.
2. All monitoring wells are shown as PC-1 symbols.
3. All monitoring wells are shown as PC-1 symbols.
4. All monitoring wells are shown as PC-1 symbols.

EXPLANATION:

PC-1

MONITORING WELL

GROUNDWATER FLOW DIRECTION

southeast of Barstow Road. Well PC-4 will be located at the southern-most edge of the HWMA approximately 250 feet southeast of well PC-3. The locations of the three downgradient wells were selected to increase the possibility for detection of hazardous waste or hazardous waste constituents migrating into the groundwater from HWMA #1 regardless of slight variations in groundwater flow direction.

2.1.2.2 Hazardous Waste Management Area #2. HWMA #2 consists of twelve HWMUs (four USTs, seven ASCs, and one oil sump) at ten facilities. Based on available information, groundwater flow in the area is in a south to southwesterly direction. An upgradient well, PC-5 will be installed approximately 675 yards northeast of Buildings 639-642. This well will be installed so as not to be influenced by HWMA #1, which lies north of HWMA #2 (Figure 2.1), and to yield groundwater samples representative of background groundwater quality. If HWMA #1 requires post-closure, a downgradient well from the groundwater monitoring system for HWMA #1 will be monitored as a second upgradient well for HWMA #2. This well will be monitored because of variations in groundwater flow direction in the area of HWMA #2 and the potential influence of HWMA #1 on background groundwater quality.

The second upgradient well, PC-4, is a downgradient well for the groundwater monitoring system associated with HWMA #1. This well will be monitored to account for any changes in background groundwater quality due to the migration of hazardous waste or hazardous waste constituents into the groundwater from HWMA #1.

The three downgradient monitoring wells will be located along the south and southwestern boundaries of the HWMA (Figure 2.1). Well PC-6 will be located at the southwestern limit of HWMA #2, approximately 400 yards south of Building 367. Well PC-7 will also be installed at the southwestern limit of the HWMA, approximately 350 yards southeast of well PC-7. Well PC-8 will be located at the southern-most edge of the HWMA just south of Building 824. The locations of the three downgradient wells were selected to increase the possibility for detection of hazardous waste or hazardous waste constituents migrating into the groundwater from HWMA #2 regardless of slight variations in groundwater flow direction.

2.1.2.3 Hazardous Waste Management Area #3. HWMA #3 consists of 21 HWMUs (five USTs, nine ASCs, five OWSs, and two oil sumps) located at three facilities. Groundwater beneath HWMA #3 generally flows south-southeast. An upgradient well, PC-9 will be installed approximately 350 yards northeast of Building 873. This well will be located so as not to be influenced by HWMA #2, which lies north of HWMA #3 (Figure 2.1), and to yield groundwater samples representative of background groundwater quality. If post-closure care is also required for HWMA #2, a downgradient well from the groundwater monitoring system associated with HWMA #2 will be monitored as a second upgradient well for HWMA #3 because of extreme variations in groundwater flow direction in the area of HWMA #3 and the potential influence of HWMA #2 on background groundwater quality.

The second upgradient well, PC-8, is a downgradient well for the groundwater monitoring system associated with HWMA #2. This well will be monitored to account for any changes in background groundwater quality due to the migration of hazardous waste or hazardous waste constituents into the groundwater from HWMA #2.

The three downgradient monitoring wells will be located along the south and southeastern boundaries of HWMA #3 (Figure 2.1). Well PC-10 will be located at the southern-most limit of HWMA #3, approximately 150 yards south of Building 840. Well PC-11 will be installed at the southwestern limit of the HWMA, approximately 100 yards northeast of well PC-10. Well PC-12 will be installed at the southwestern limit of the HWMA, approximately 100 yards northeast of well PC-11 just south of Building 879. The locations of the three downgradient wells were selected to increase the possibility for detection of hazardous waste or hazardous waste constituents migrating into the groundwater from HWMA #3 regardless of slight variations in groundwater flow direction.

2.1.2.4 Hazardous Waste Management Area #4. HWMA #4 consists of 2 HWMUs (two USTs) located at two facilities. Based on available information, groundwater in the area generally flows in a southern direction. A hydrogeologically upgradient monitoring well, PC-13 will be installed approximately 200 yards north of the Building 909 (Figure 2.1). The well location was selected to yield groundwater samples representative of groundwater unaffected by the HWMUs in HWMA #4.

The three downgradient monitoring wells will be located along the south and southwestern boundaries of the HWMA (Figure 2.1). Well PC-14 will be located at the southwestern-most limit of the HWMA, near existing well I-5. Well PC-15 will be installed approximately 40 yards northeast of well PC-14, just south of Building 910. Well PC-16 will be located at the eastern-most edge of the HWMA approximately 40 yards northeast of well PC-15 to complete the groundwater monitoring system for HWMA #1. The locations of the three downgradient wells were selected to increase the possibility for detection of hazardous waste or hazardous waste constituents migrating into the groundwater from HWMA #4 regardless of slight variations in groundwater flow direction.

2.1.3 Well Design

The groundwater monitoring well design is based on available information regarding the elevations of the groundwater surface and the depth of the alluvial bedrock floor in the vicinity of each HWMA to be monitored (Wilson F. So, 1989; Earth Technology, 1990). Due to varying aquifer geometry within the cantonment area, well design (Figure 2.2) may differ depending on the location. The basic well design is patterned after monitoring wells that are currently installed at the NTC and the need to obtain representative water quality samples from each HWMA (Hinkle, 1990). The diameter of the well must be large enough to allow the sampling equipment to easily pass through. Therefore, the following design criteria will be standard for each well:

- Borehole diameter approximately 10 inches
- 4-inch schedule 80, polyvinyl chloride (PVC) blank casing
- 4-inch, flush-thread, schedule 80 PVC screen with approximately 20 feet of screen above the water table and 30 feet below
- PVC bottom cap.

The intake structure of the well consists of the filter-pack and the well screen. The well intake is a screening device used to keep materials other than water from entering the well and to stabilize the surrounding formation. The type and size of the filter-pack is based on the type and size of aquifer sediments and will provide the primary interface

Not to Scale all Measurements are Approximate

Post-closure Plan for Maintenance Facility HWMUs
Battelle Environmental Management Operations
Project No: 90-352

MONITORING WELL CONSTRUCTION DETAILS

Figure 2.2

1-92

between the monitor well and the aquifer. To be effective, the slot size of the screen must be matched to the filter-pack material. To select the appropriate filter-pack and screen sizes, representative soil samples will be obtained at 10-foot intervals within the aquifer during drilling. A sieve analysis will be performed on the soil samples, a sieve analysis curve will be constructed, and a filter-pack will be selected based on the finest materials present. The slot size for the well screen will be selected after the filter-pack is specified. The slot size must be small enough to retain 80 to 90 percent of the filter-pack in the annulus. The filter-pack will be placed from the total depth of the well to approximately 2 to 3 feet above the screened interval.

Proper vertical placement of the well intake is essential for the monitoring to allow for immediate detection of a release. Factors influencing pathways for contaminant migration and, therefore, perforation intervals are the characteristics of the geologic formations in the HWMA and the physical and chemical properties of the hazardous waste to be monitored. For each HWMA, the appropriate stratigraphic horizon will be identified and down-gradient wells will be screened, where possible, at the same stratigraphic horizon as the up-gradient well to ensure comparability of data. The properties and characteristics of the hazardous waste can greatly affect the movement of contamination in the aquifer. The types of hazardous waste of concern for monitoring of the HWMUs include mostly light, immiscible petroleum- and synthetic-based oils and other halogenated and non-halogenated volatile organic compounds. These compounds are expected to spread rapidly in the capillary zone just above the potentiometric surface. Therefore, unless the specific geology or potential contaminant properties vary significantly from those indicated above, the standard vertical screening placement will extend from 20 feet above the water table to 30 feet below.

The annular space above the filter-pack will be sealed to the ground surface. A bentonite seal approximately 2 to 4 feet thick will be placed on top of the filter-pack and hydrated according to manufacturer's specifications. Volclay grout will be placed above the bentonite seal to approximately 2 feet below ground surface (bgs). The well will be completed with 12-inch diameter steel casing extending approximately 36-inches aboveground surface with a hinged, locking cap. A concrete seal will be placed

from approximately 2 feet bgs to approximately 30 inches aboveground surface in the annular space between the 4-inch PVC casing and the 12-inch steel casing.

Table 2.1 presents the design criteria that are unique to each well including well depth and perforation interval. Available information regarding groundwater, surface, and basin bottom elevations that were used to develop the well designs is also presented. The information presented is based on current water levels and may be modified at the time of installation based on water levels and field conditions encountered at the time of drilling.

2.1.3.1 Well Installation. Wells will be installed using a hollow-stem auger drill rig. Because the monitor wells are being constructed with a 4-inch diameter casing, it will be necessary to use hollow-stem augers with an inside diameter of 8 inches. The screen and casing will be suspended from the ground surface and will not be allowed to rest on the borehole bottom. The hollow-stem auger will sufficiently center the screen and casing, therefore, centralizers will not be used.

Filter-pack material will be placed in the annular space by free-fall within the hollow-stem auger. The hollow-stem auger will be left on the bottom of the borehole during placement of the filter-pack material. The filter-pack material will be placed in lifts, sounded and any bridges broken by washing with potable water. The hollow-stem auger will be removed in 2-foot increments and the free-fall placement of filter-pack continued until the screen interval is covered.

A bentonite seal will be placed directly on top of the filter-pack by free-falling granular bentonite in the hollow-stem auger and properly hydrating the bentonite. The remaining annulus will be grouted by pumping grout into the hollow-stem auger. When the hollow-stem auger is filled with grout to ground surface, a section will be removed. This process will be continued until all of the hollow-stem augers have been removed.

2.1.3.2 Well Development. The purpose of well development is to restore natural hydraulic conditions after drilling to enhance yield and remove finer materials to enable water that is representative of the formation water to move into the zone to be monitored.

TABLE 2.1. Well Design and Construction Data

<u>WELLS</u>	<u>Groundwater Elevation (feet AMSL)⁽¹⁾</u>	<u>Surface Elevation (feet AMSL)</u>	<u>Bedrock Elevation (feet AMSL)</u>	<u>Depth to Water⁽²⁾ (feet bgs)⁽³⁾</u>	<u>Well Depth (feet bgs)</u>	<u>Perforation Interval (feet bgs)</u>	<u>Casing Diameter (inches)</u>	<u>Pump</u>
<u>HWMA #1</u>								
PC-1	2300	2440	2250	140	175	120-170	4	No
PC-2	2280	2460	2130	180	215	160-210	4	No
PC-3	2280	2450	2125	170	205	150-200	4	No
PC-4	2280	2440	2120	160	195	140-190	4	No
<u>HWMA #2</u>								
PC-5	2285	2410	2150	125	160	105-155	4	No
PC-5	2275	2465	2030	190	225	170-220	4	No
PC-6	2270	2440	2050	170	205	150-200	4	No
PC-7	2270	2425	2100	155	190	135-185	4	No
<u>HWMA #3</u>								
PC-8	2285	2400	2150	115	150	95-145	4	No
PC-9	2255	2430	2000	175	210	155-205	4	No
PC-10	2250	2420	2000	170	205	150-200	4	No
PC-11	2255	2410	2000	155	190	135-185	4	No
<u>HWMA #4</u>								
PC-12	2275	2510	2030	235	270	215-265	4	No
PC-13	2270	2490	2000	220	255	200-250	4	No
PC-14	2270	2480	2000	210	245	190-240	4	No
PC-15	2270	2475	2000	205	240	185-235	4	No

Notes: (1) AMSL - Above Mean Sea Level
(2) Depth to Water measured during 1988
(3) bgs - below land surface.

The development of monitoring wells will be performed after final grouting so that the cement cures adequately and is not drawn into the wellbore. Development will be accomplished using one of three methods; pumping and pump surging, air lifting and surging; or bailing and mechanical surging. Development will be initiated by removal of excess sediment in the well and will be started at the slowest possible rate and will be gradually increased as development proceeds. Development of the wells will be performed as guided by the following criteria and continued until these criteria are met:

1. Well water is visually clear
2. Well water has a turbidity of less than 5 Nephelometric Turbidity Units (N.T.U.) or is the best attainable, as determined by field personnel
3. Sediment remaining in the bottom of the wellbore does not exceed 5 percent of the total screened casing length
4. Removal of a minimum of 10 casing and filter pack (30 percent porosity assumed) volumes of water.

If recharge of the well is so slow that 10 casing volumes cannot be extracted within 48 hours, or if the water remains discolored, or if excess sediment remains after 10 casing volumes are removed, field personnel will decide on whether to abandon or use the well.

Groundwater residuals produced during development will be placed in Department of Transportation (DOT)-approved 55-gallon drums and stored on site in a secure location until analytical results for the residuals are received. Residuals will be disposed of as hazardous or nonhazardous waste in accordance with the analytical results and regulatory requirements. Drummed residuals will be sealed and labeled in permanent ink with the site name, monitor well number, type of residuals, depths (as appropriate), and date.

2.1.3.3 Well Surveying. Following completion of the monitor wells, a registered surveyor will be contracted to perform a wellhead elevation survey having an accuracy of plus or minus 0.01 feet. The survey is necessary to calculate the actual elevation of the groundwater and evaluate the direction of groundwater flow.

2.2 SAMPLING AND ANALYSIS

Groundwater samples will be obtained and analyzed from the groundwater monitoring systems. To accomplish this, the following sampling and analysis plan has been developed. The plan includes procedures and techniques for determining background concentrations and sampling frequencies, sample collection, sample preservation and shipment, analytical procedures, and chain-of-custody documentation.

2.2.1 Background Concentrations and Frequency of Sampling

To identify the frequency of groundwater sampling during post-closure, the owner or operator of the HWMUs will establish initial background groundwater concentrations. To establish background groundwater concentrations, the wells will be sampled quarterly during the initial year of post-closure or in the year prior to post-closure. The groundwater samples will be analyzed to establish background groundwater concentrations or values for the following parameters: the suitability of the groundwater as a drinking water supply, groundwater quality, and groundwater contamination. The analytical parameters and analytical methods presented in Table 2.2 will be used to establish these background groundwater concentrations. Based on the analytical results obtained during this year, regulatory requirements, and decisions of the Regional Administrator, the frequency of sampling will be established.

During the first year, at least four replicate analytical measurements will be obtained for each sample collected from the upgradient (background) well(s) for the chemical indicators of groundwater contamination. The sixteen measurements that are obtained from each upgradient well during the initial year will be pooled, and the initial background arithmetic mean and variance calculated.

The downgradient wells will also be sampled quarterly during the first year and analyzed for each of the previously mentioned parameters. As with the upgradient wells, four replicate analytical measurements of the indicators of groundwater contamination will be obtained. At the end of the first year, the arithmetic mean and variance for the

TABLE 2.2 Analytical Parameters and EPA Test
Methods for Groundwater Sampling
(Page 1 of 2)

<u>ANALYTICAL PARAMETER</u>	<u>EPA TEST METHOD</u>	<u>MCL^(a)</u>
DRINKING WATER SUITABILITY		
Arsenic	200.7	0.05
Barium	200.7	1.0
Cadmium	200.7	0.010
Chromium	200.7	0.05
Fluoride	340.2	1.4-2.4 ^(b)
Lead	200.7	0.05
Mercury	245.1	0.002
Nitrate (as N)	352.1	10.0
Selenium	200.7	0.01
Silver	200.7	0.05
Endrin	508	0.0002
Lindane	508	0.004
Methoxychlor	508	0.1
Toxaphene	508	0.005
2,4-D	515.1	0.1
2,4,5-TP Silver	515.1	0.01
Radium	900.1	5 ^(c)
Gross Alpha	9310	15 ^(c)
Gross Beta	9310	50 ^(c)
Coliform Bacteria	9131	1/100 ml
GROUNDWATER QUALITY PARAMETERS		
Chloride	325.2	250-500-600 ^(d)
Iron	200.7	0.3

Notes: (See bottom of page 2 of this table.)

**TABLE 2.2 Analytical Parameters and EPA Test
Methods for Groundwater Sampling**
(Page 2 of 2)

<u>ANALYTICAL PARAMETER</u>	<u>EPA TEST METHOD</u>	<u>MCL^(a)</u>
GROUNDWATER QUALITY PARAMETERS (Cont'd)		
Manganese	200.7	0.05
Phenols	420.1	0.005
Sodium	200.7	-- ^(e)
Sulfate	375.3	250-500-600 ^(d)
GROUNDWATER CONTAMINATION PARAMETERS		
pH	150.1	-- ^(f)
Specific Conductance	120.1	-- ^(f)
Total Organic Carbon	415.2	-- ^(f)
Total Organic Halogens	9020	-- ^(f)

Notes:

(a) MCL = Maximum Contaminant Level established by the California Office of Drinking Water or the EPA Interim Primary Drinking Water Standards whichever is lower in mg/l unless otherwise notes.

(b) The MCL for fluoride varies with temperature as follows:

<u>Temperature, F</u>	<u>MCL, (mg/l)</u>
< 53.7	2.4
53.8 - 58.3	2.2
58.4 - 63.8	2.0
63.9 - 70.6	1.8
70.7 - 79.2	1.6
79.3 - 90.5	1.4

(c) pCi/l = pico Curies per liter

(d) Recommended - Upper - Short term

(e) No MCL has been established by the California Office of Drinking Water

(f) The concentration of the parameters will be compared to the initial arithmetic mean and any statistically significant changes will be reported.

Source: 40 CFR 265, Appendix III-EPA Interim Primary Drinking Water Standards
California Office of Drinking Water.

groundwater contamination parameters will be calculated for each downgradient well from the sixteen measurements. This mean will be compared with the initial background arithmetic mean using the Student's T-test at the 0.01 level of significance as outlined in Appendix B to identify statistically significant increases in specific conductance, total organic carbon and/or total organic halogens or pH decreases.

After the first year, the upgradient and downgradient wells will be sampled at least twice a year. Samples will be analyzed for groundwater contamination parameters twice a year and groundwater quality parameters once a year. For each sample from each of the wells, four replicate measurements will be obtained during the groundwater contamination analyses. The arithmetic mean and the variance will be calculated and compared to the initial background arithmetic mean using the Student's T-test as described in Appendix B. In addition to sampling, groundwater elevation must be measured and recorded annually.

2.2.2 Sampling Methods and Procedures

The wells will be sampled quarterly during the first year of post-closure care and semi-annually thereafter. The groundwater samples will be collected using the following sampling procedures:

1. Depth to water will be measured from the top of the well casing to the top of the water surface to the nearest 0.01 foot during each sampling event.
2. The interval from the top of the water surface to the water-sediment interface will be measured to the nearest 0.01 foot to calculate total casing water volume for purging of the monitoring well prior to sampling.
3. The elevation of groundwater in feet will be calculated and recorded given the elevation of the ground surface at the wellhead and depth to water.
4. A minimum of three to five casing volumes of water will be purged or removed from the well prior to sampling using a PVC bailer or submersible pump.
5. Specific conductance, pH, and temperature will be recorded at a minimum of 5-gallon intervals. Samples will be collected when the three to five casing volumes of water are removed and the above parameters stabilize (10 percent or less difference between successive readings).

6. A groundwater sample will be collected immediately after purging is complete. Samples will be collected with a Teflon™ bailer having a controlled flow bottom-emptying device. If low yields are observed, a minimum of three casing volumes will be removed prior to sampling. If a well is pumped or bailed dry during removal of casing water (and recovery is slow), samples will be obtained as soon as possible after the well has recovered.
7. A sample may be collected in a slow recovery well if specific conductance, pH, and temperature parameters are stable, and the minimum casing volumes have not been removed. Departures from the standard sampling procedure described above will be documented and reported.
8. Samples to be analyzed for volatile compounds will be obtained so that the sample container is headspace-free. All such samples will be collected in 40-milliliter (ml) vials with Teflon™ septums. The container will be immediately capped so that volatilization is minimized. This will be achieved by filling the container to slightly overflowing, forming a meniscus, at the mouth of the container. The cap will be placed upon the convex meniscus and tightly sealed. To check that the sample is air-free, the container will be inverted and the cap gently tapped. The absence of entrapped air indicates a successful seal. When air is evident in the container, the entire sample will be discarded and another sample will be collected. Evacuation and sampling data for each well will be recorded in a log book at the time of sampling.

2.2.3 Field Measurements

Temperature, pH, and specific conductance measurements will be monitored and recorded while purging the well. When parameters have stabilized, the groundwater sample will be collected. Groundwater level measurements as well as physical characteristics of the groundwater, including color, odor, and turbidity, will also be recorded.

2.2.4 Equipment Decontamination and Disposal of Residuals

All sampling equipment will be cleaned prior to the sampling of each well. Cleaning will consist of washing in an Alconox™ (non-phosphate detergent) solution, rinsing with potable water, deionized water, and a third time with organic-free water. If a portable submersible pump is used to purge the well(s), the pump will be decontaminated by

pumping several volumes of Alconox™ solution, potable water, deionized water, and organic-free water through the pump prior to each sampling event at each well.

Groundwater and decontamination residuals produced during sampling will be placed in DOT-approved 55-gallon drums and stored on site in a secure location until analytical results for the residuals are received. Residuals will be disposed of as hazardous or nonhazardous waste in accordance with the analytical results. Drummed residuals will be sealed and labeled in permanent ink with the site name, monitor well number, type of residuals, depths (as appropriate), and date.

2.2.5 Sample Containers and Preservation

Sample containers will be supplied by the analytical laboratory selected to analyze the samples. The sample containers will be cleaned and prepared in accordance with I-Chem sample container cleaning procedures prior to receipt in the field. The type of containers, preservation requirements, and the maximum holding time for each analysis required during the first year and each successive year are presented in Table 2.3.

2.2.6 Sample Documentation

Appropriate sample documentation is necessary to ensure the completeness, accuracy, and repeatability of the sampling effort. The components of sample documentation include the field log book, sample labels, sample seals, and chain-of-custody records. Each of these components is discussed below.

2.2.6.1 Field Log Book. Field activities will be summarized and described in a bound log book. Documentation of all post-closure activities including groundwater sampling will be recorded in the log book. Information pertinent to the field program includes, but is not limited to the following items:

- Location of the site
- Site contact(s)

TABLE 2.3 Sample Containers, Preservation, and
Holding Times for Groundwater Samples
(Page 1 of 2)

<u>Parameter</u>	<u>Container^(a)</u>	<u>Preservation</u>	<u>Maximum Holding Time</u>
DRINKING WATER SUITABILITY			
Arsenic	500 ml HDPE	HNO ₃ to pH < 2	6 months
Barium	500 ml HDPE	HNO ₃ to pH < 2	6 months
Cadmium	500 ml HDPE	HNO ₃ to pH < 2	6 months
Chromium	500 ml HDPE	HNO ₃ to pH < 2	6 months
Fluoride	500 ml HDPE	None Required	28 days
Lead	500 ml HDPE	HNO ₃ to pH < 2	6 months
Mercury	250 ml HDPE	HNO ₃ to pH < 2	28 days
Nitrate (as N)	250 ml HDPE	H ₂ SO ₄ to pH < 2 Cool 4°C	48 hours
Selenium	500 ml HDPE	HNO ₃ to pH < 2	6 months
Silver	500 ml HDPE	HNO ₃ to pH < 2	6 months
Endrin	2-1 L G	Cool 4°C, pH 5-9	7 days until extraction 14 days after extraction until analysis
Lindane	2-1 L G	Cool 4°C, pH 5-9	7 days until extraction 14 days after extraction until analysis
Methoxychlor	2-1 L G	Cool 4°C, pH 5-9	7 days until extraction 14 days after extraction until analysis
Toxaphene	2-1 L G	Cool 4°C, pH 5-9	7 days until extraction 14 days after extraction until analysis
2,4-D	1 L G	Cool 4°C	14 days until extraction 28 days after extraction until analysis
2,4,5-TP Silvex	1 L G	Cool 4°C	14 days until extraction 28 days after extraction until analysis
Radium	2 L HDPE	HNO ₃ to pH < 2	6 months

TABLE 2.3 Sample Containers, Preservation, and
Holding Times for Groundwater Samples
(Page 2 of 2)

<u>Parameter</u>	<u>Container</u>	<u>Preservation</u>	<u>Maximum Holding Time</u>
DRINKING WATER SUITABILITY (cont'd)			
Gross Alpha	2 L HDPE	HNO ₃ to pH < 2	6 months
Gross Beta	2 L HDPE	HNO ₃ to pH < 2	6 months
Turbidity	250 ml HDPE	Cool 4°C	48 hours
Coliform Bacteria	250 ml HDPE	0.008% NA ₂ S ₂ O ₃ , Cool 4°C	6 hours
GROUNDWATER QUALITY PARAMETERS			
Chloride	125 ml HDPE	None Required	28 days
Iron	500 ml HDPE	HNO ₃ to pH < 2	6 months
Manganese	500 ml HDPE	HNO ₃ to pH < 2	6 months
Phenols	1 L G	H ₂ SO ₄ to pH < 2	7 days until extraction 40 days after extraction until analysis
Sodium	500 ml HDPE	HNO ₃ to pH < 2	6 months
Sulfate	1 L G	Cool 4°C	28 days
GROUNDWATER CONTAMINATION PARAMETERS			
pH	125 ml G	None Required	Analyze immediately
Specific Conductance	250 ml HDPE	Cool 4°C	28 days
Total Organic Carbon	125 ml G	Cool 4°C H ₂ SO ₄ to pH < 2	28 days
Total Organic Halogens	125 ml G	Cool 4°C Headspace Free	28 days

Note:

- (a) HDPE - High Density Polyethylene Bottle
- (b) G - Glass Bottle with Teflon™-lined lid

- Purpose of sampling
- Description of the field activities
- Names of the personnel on site
- Date and time of the entries
- Sample matrix
- Date and time of collection
- Sampling locations, sample ID number, and sampling methodology
- Number and volume of samples collected
- Field observations (e.g. sample description)
- Sample distribution
- Maps, photographs, and/or drawings
- Field measurements
- Sampling personnel
- Signature and date at the bottom of each page of the person(s) making the entries.

The field log book will be routinely maintained on a daily basis by field staff and all entries will be legibly recorded using indelible ink. Additionally, all pages will be consecutively numbered and no pages will be removed from the field log book during or after the sampling program.

2.2.6.2 Sample Labeling. Samples of groundwater collected in the field will be labeled immediately. Labels with adhesive backing will be completed with indelible ink and affixed to the side of the sample container. Information written on the label for groundwater samples will include:

1. Site location
2. Well identification number
3. Required analyses
4. Added chemical preservations
5. Initials of sampler
6. Date
7. Time.

The label will be attached securely to the sample container to minimize loss or mutilation. Each label will be filled out as completely as possible prior to taking the sample.

2.2.6.3 Sample Seals. In order to discourage and detect unauthorized tampering with the samples, seals will be placed over the container lids across the juncture between the lid and the sampling container. The sample seals will include the following information:

1. Sample number
2. Initials of sampler
3. Date
4. Time.

2.2.6.4 Chain-of-Custody Procedures. The chain-of-custody for possession and responsibility of samples must be documented from the time and place of sample acquisition to the time and place of their final destination. A typical chain-of-custody record used for this documentation is presented in Appendix A. To maintain and document sample possession, chain-of-custody procedures will be followed that include the completion of chain-of-custody records and other requirements.

1. Chain-of-custody is defined as a documented record of the transfer of responsibility for the care and safekeeping of acquired samples from one person or organization to another.
2. A sample is under custody if: 1) it is physically in one's possession, 2) it is in plain view after being placed in one's physical possession, or 3) it is locked in a designated and identified secure area where tampering is prevented.
3. The personnel initially collecting the sample are responsible for the care and custody of the sample until it is properly transferred to delivery or laboratory personnel.
4. Records will be kept in the log book concerning sample handling and transportation.
5. A chain-of-custody record will be filled out completely. Each sample will be described completely on separate lines. No duplication or ditto marks will be used. An individual record will be completed for each final destination.
6. All samples will be accompanied by the original chain-of-custody record during transport. The chain-of-custody record will provide the sample number, site location, sample matrix, number of containers, and the analysis required. The sampler and all laboratory personnel who relinquish and/or receives responsibility for the samples shall sign, date, and retain one copy of the record for his/her files. If the transport company refuses to sign the chain-of-custody, the transporter's package tracking number will be recorded.

7. All ice chests will be sealed by the sampler with tape. To detect unauthorized tampering, the ice chests will remain sealed until received by the laboratory receiving agent.

2.2.7 Sample Packaging and Shipment

Samples will be wrapped in shock-absorbing material, sealed in self-sealing plastic bags, stored in portable ice chests containing ice, and transported to the laboratory for analysis. Empty space in the cooler will be filled with inert material to cushion the samples and prevent breakage during shipment. Sampling personnel or a courier service will hand deliver the samples to the laboratory as soon as practicable after sample collection. Shipping containers will meet applicable state and federal DOT requirements for safe transportation. Additionally, the containers will be sealed in a manner such that obvious tampering can be detected immediately upon receipt by the testing laboratory. If samples need to be stored overnight, they will be stored in a secure, indoor area and the cooler will be sealed in such a manner as to detect tampering.

2.2.8 Quality Assurance/Quality Control

Quality Assurance/Quality Control (QA/QC) procedures are an integral part of each sampling methodology. These procedures focus upon the collection of representative samples that are free from external contamination and ensure the reliability and validity of data gathered as part of the overall groundwater monitoring program. QA/QC procedures include both field and laboratory activities. Quality control checks for both types of activities are discussed in the following sections.

2.2.8.1 Field Quality Control Checks. Although different sampling procedures have method-specific QC requirements, certain general quality control procedures are applicable to all methods. These include the following quality control samples which will be collected during this sampling program:

- Trip blanks will accompany every batch of samples sent to the laboratory for analysis of total organic halogens to check for cross-contamination of samples during shipping and handling. The trip blanks will be prepared by the analytical laboratory using deionized water and will be analyzed for total organic halogens using EPA Method 9020.
- One equipment blank will be collected each sampling day to ensure that sampling equipment has been effectively cleaned. After decontamination, the equipment blank will be obtained by pouring deionized water over the sampling tool and collecting the water in an appropriate sample container. The equipment blank will then be transported to the laboratory and analyzed for the parameters presented in Table 2.2.
- One duplicate sample per matrix will normally be collected or 10% of the total number of samples per matrix, if more than 10 samples are collected. Care must be taken to see that as true a duplicate sample as possible will be obtained. The duplicate sample will be collected, numbered, packaged and sealed in the same manner as the other samples so that the laboratory personnel performing the analysis do not know they are duplicates. The duplicates will be analyzed for the same parameters as their corresponding groundwater samples.

Other QC checks that will be implemented include sample chain-of-custody records which will accompany all samples from acquisition to final destination, and equipment decontamination procedures to prevent cross-contamination of the samples.

2.2.8.2 Laboratory Quality Control Checks. Laboratory QC focuses on ensuring that each chemical measurement has the highest probability of exceeding method protocol in terms of precision and accuracy. Laboratory QC samples, including method blanks, spiked blanks, matrix spikes, duplicates, and spiked duplicates must be evaluated on a routine basis. The minimum QC requirements are as follows:

- One method blank per batch (up to 20 samples)
- One laboratory control sample per batch
- One matrix spike/spike duplicate analysis for each batch or 20 samples, or duplicate analysis at 10% frequency
- Calibration verified using mid-range standard at least every 10 samples except for GC, where calibration is verified every 24 hours.

2.2.8.3 Quality Assurance. Quality Assurance is all of the planned and systematic actions necessary for ensuring the validity, the integrity, the preservation, and the retrievability of the data. The QA program will ensure that the quality control data will be compared on a regular basis to establish laboratory QC limits which are updated on a quarterly schedule. Laboratory logbooks will be maintained to document QC data and QC charts will be prepared when at least 20 data points have been generated. Quality control sample data will be compared to establish data at the time of analysis.

3.0 EVALUATION AND RESPONSE

Results of groundwater monitoring will be evaluated throughout the post-closure care period. The results will be evaluated by calculating the arithmetic mean and variance for each of the wells in a groundwater monitoring system. The mean and variance will then be compared to the initial background arithmetic mean for that system using the Student's T-test (Appendix B) at the 0.01 level of significance.

Appropriate responses, as described in the following sections and summarized on Figure 3.1 will be made if the comparisons indicate statistically significant differences.

If the comparisons for the upgradient wells indicate statistically significant differences between the initial background arithmetic mean and the results from the most recent sampling event, no immediate action will be taken. However, the owner or operator will submit the information in accordance with the recordkeeping and reporting requirements as described in Section 4.0. If the comparisons for the downgradient wells indicate a statistically significant increase in specific conductance, total organic carbon, and/or total organic halogens, or pH decrease, additional groundwater samples from the downgradient wells where the difference was observed will be collected and analyzed. Each sample will be split in two and analyzed to determine if the difference was a result of laboratory error.

As specified in 40 CFR 265.93(d), if the additional analyses confirm any statistically significant difference as noted above, the Regional Administrator and the Regional Water Quality Control Board (RWQCB) will be notified in writing within 7 days that the facility may be affecting groundwater. Within 15 days of this notification a plan that specifies a groundwater quality assessment program will be submitted to the Regional Administrator. This plan will be based on the outline presented in Appendix C. This plan will be implemented as soon as technically feasible and will determine the rate and extent of migration and concentration of the hazardous waste or hazardous waste constituents in the groundwater. When the initial determination of the rate and extent of migration of

Post-Closure Plan for Maintenance Facility HWMUs
Battelle Environmental Management Operations
Project No: 90-352

EVALUATION AND RESPONSE DECISION TREE

FIGURE 3.1

hazardous waste into the groundwater has been made, the owner or operator will submit the information within 15 days to the Regional Administrator as described in Section 4.0. The groundwater monitoring program will then continue as described in Section 2.0 of this document incorporating any changes specified by the Regional Administrator.

4.0 RECORDKEEPING AND REPORTING

During the post-closure care period, results of analyses, evaluations, and associated groundwater surface elevations will be recorded and reported to the EPA as specified in 40 CFR 265.94. If the groundwater monitoring program is being conducted on a semi-annual basis as part of post-closure care and no cause for implementation of a groundwater assessment program has been identified, the owner or operator will keep records of and submit:

- Analytical results of all samples collected from each monitoring well during the first year when background concentrations are being established and information regarding the statistical evaluations.
- Analytical results for all samples collected after the first year throughout post-closure care
- Results of groundwater surface elevation evaluations
- Comparisons of analytical results to the initial background arithmetic mean using the Student's T-test at the 0.01 level of significance.

The results recorded in the first year will be reported to the EPA within 15 days of completing each quarterly analysis. Results from each monitoring well in which parameters have exceeded maximum contaminant levels will be reported separately. After the first year, all results of samples collected and the required evaluations will be reported annually. Any significant variation from the initial background found in the upgradient wells will be identified separately and included in the annual report. The annual reports will be submitted no later than March 1, of the following calendar year. All records will be kept throughout the post-closure care period.

If a groundwater assessment program is being implemented as described in Section 3.0, the owner or operator will submit to the EPA, the results of the groundwater quality assessment program including the rate of migration of hazardous waste or hazardous waste constituents in the groundwater during the reporting period no later than March 1 of the following calendar year. The owner or operator will also keep records of all analyses and evaluations specified above throughout the post-closure care period.

5.0 MAINTENANCE INSPECTIONS AND ACTIVITIES

The HWMA's will be inspected periodically to identify conditions that may pose a threat to the integrity of the HWMA. Additionally, maintenance activities will be conducted to prevent threats to the HWMA integrity.

5.1 STRUCTURES AND FACILITIES

The HWMA will be inspected during each sampling event. The buildings within the HWMA, the final cover, and surrounding ground surface will be inspected for noticeable disturbances. All buildings in the area will be inspected for indications of structural damage. Structural damage to the buildings may indicate a natural disaster such as an earthquake which may have caused damage to the groundwater monitoring system.

The final cover of the HWMA will be inspected for conditions such as depressions in the ground surface, standing water in the HWMA, stressed vegetation, cracks in concrete or asphalt, or any other indications that appear to pose a threat to the integrity of the HWMA. If the final cover appears to be recessed, additional fill will be added to prevent the accumulation of liquid in the HWMA. Additionally, the cause of the depression will be identified and, if possible, eliminated.

5.2 GROUNDWATER MONITORING SYSTEMS

The groundwater monitoring systems will be periodically inspected and maintained to ensure that the wells are in working condition throughout post-closure care and continue to yield groundwater samples that remain representative of the uppermost aquifer underlying the HWMA.

The wells will be inspected quarterly during the first year of post-closure and semi-annually thereafter. The inspections will coincide with the sampling events. During the first inspection, the inspection results will be recorded in the field log book. The first inspection will provide the data with which all future inspection data will be compared.

The following activities will be conducted and recorded during each inspection:

- The depth of the well will be recorded and the depths will be compared with previous water level data to identify possible filling of the well with sediment. If sediment build-up occurs that interferes with sample collection and analysis, the sediment will be removed using a hose with a foot valve or a bailer prior to purging and sampling. The sediment will be sampled and analyzed to identify appropriate disposal procedures.
- Turbidity of the well will be measured annually. If the turbidity of the well interferes with sample collection and analysis, sediment will be removed from the well, if appropriate, and one additional sample will be collected to confirm the turbidity. If the turbidity does not decrease, redevelopment of the well will be considered. If turbidity persists, installation of a new well and abandonment of the existing well will be considered.
- A pump test will be performed once every five years. If the tests indicate that the performance of the well is deteriorating, redevelopment of the well will be performed.
- Piezometric surface will be plotted and reviewed annually.
- High and low water-level data for each well will be examined every 2 years to ensure that well location and design remains appropriate.
- Exposed well casing will be inspected for structural integrity, cracks, and corrosion.
- Well cap will be removed and inspected for spider webs, molds, fungi, or other problems that may affect the water samples.
- The well cap and upper portions of the well casing will be cleaned with a long-handled brush after sample collection and will be followed by purging of the well.
- All surface seals will be inspected for settling and cracking. Damaged seals will be replaced.

If, during the inspections, it is determined that a well is inoperable due to collapsed casing, significant changes in groundwater level, or other difficulties, the well will be abandoned in accordance with applicable state and federal regulations. A new well will be installed using the methods specified in Section 2.1.

5.3 FREQUENCY OF INSPECTIONS AND MAINTENANCE ACTIVITIES

Inspections and maintenance activities will be conducted at the time of each sampling event. Therefore, inspections will be conducted a minimum of twice a year. However, if conditions are observed that indicate the possible occurrence of problems at a later date, inspections and maintenance will be performed more frequently until it has been determined that there is no longer a threat to the integrity of the HWMA.

5.4 SECURITY SYSTEMS

Chain-link fencing equipped with locking gates currently surround and secure each of the maintenance facilities listed in this Post-Closure Plan. Each of the gates will be closed and locked, securing the site, whenever post-closure activities have ceased for the day and whenever the site is not occupied. The fence at each facility will remain in place from the initiation of post-closure care through post-closure approval and certification.

5.5 RESPONSIBLE PARTY

Lieutenant Colonel David Schnabel, Director of Engineering and Housing (D.E.H.) or the current D.E.H., is the contact person at the NTC. Lieutenant Colonel Schnabel or the D.E.H. will be responsible for appointing and overseeing the individual or individuals who will perform the inspection and maintenance activities.

6.0 POST-CLOSURE NOTICES

Upon certification of closure, three steps of notification will be taken. First, no later than 60 days after certification of closure of each HWMU, a record of the type, location, and quantity of hazardous wastes disposed of within each HWMU will be submitted to the local zoning authority and the EPA. Second, within 60 days of certification of closure of both the first HWMU and the last HWMU, a notation will be recorded on the deed to the property or some other instrument which is examined during title search. According to 40 CFR Part 265.119, this notation will serve to inform any potential purchaser of the property that:

- the land has been used to manage hazardous wastes;
- its use is restricted under 40 CFR Subpart G regulations; and
- the survey plat and record of the type, location, and quantity of hazardous wastes disposed of in each HWMU have been filed with the local zoning authority and with the EPA.

Also, certification of the notation described above and a copy of the document in which the notation was placed will be submitted to the EPA. The third step of notification will be taken if after closure, any hazardous wastes, hazardous waste residues, liners, contaminated structures, equipment, or soils are to be removed from the HWMU. In this case, a modification to the approved post-closure plan will be requested, and it will be demonstrated as stated in 40 CFR 265.117(c) that the removal of hazardous wastes is either:

- necessary to the proposed use of the property, and will not increase the potential hazard to human health or the environment; or
- necessary to reduce a threat to human health or the environment.

The contact person for the notifications will be Major David Schnabel or the current D.E.H.

7.0 POST-CLOSURE CERTIFICATION

As part of the post-closure activities, an independent registered professional engineer and the Army will submit to the EPA certification that the post-closure care period has been conducted in accordance with this Post-closure Plan. The certification will be submitted by registered mail and will be furnished no later than 60 days after the completion of the established post-closure care period for each HWMU. Documentation submitted with the certification will include:

- evidence of the certification of the registered professional engineer
- a record of post-closure activities
- results of all testing and analyses.

8.0 REFERENCES

- California Department of Health Services, 1986. The California Site Migration Decision Tree Manual. Toxic Substances Control Division, Sacramento, CA.
- Dale Hinkle, P.E., Inc., 1990. Field Procedures for Drilling, Sampling and Abandonment of SH-7S and SH-85, Fort Irwin Wastewater Treatment Facility, February.
- Hinkle, 1990. See Dale Hinkle, P.E., Inc.
- ICF Incorporated, 1987. RCRA Guidance Manual for Subpart G Closure and Post-Closure Care Standards and Subpart H Cost Estimating Requirements. Prepared for U.S. Environmental Protection Agency; OSWER Policy Directive No. G476100-5, January 1987.
- Salf, M.R., McNabb, J.F., Dunlap, W.J., Cosby, R.L., Fryberger, J.S., 1981. Manual of Groundwater Sampling Procedures, National Water Well Association/EPA.
- U.S. Environmental Protection Agency, 1985. RCRA Groundwater Monitoring Technical Enforcement Guidance Document (TEGD).
- The Earth Technology Corporation, 1992. Closure Plan Hazardous Waste Management Units at Selected Maintenance Facilities, prepared for Battelle, Environmental Management Operations under a Related Services Agreement with the U.S. Department of Energy, February.
- Wilson F. So. & Associates, 1989. Water Basin Development Plan. Final Report prepared for U.S. Army National Training Center, June 1989.

APPENDIX A
CHAIN-OF-CUSTODY RECORD

(714) 892-2565 FAX (714) 890-4032

Samplers: (Signature)

Method of Shipment: _____ Shipment No. _____ Special Instructions: _____ _____	Comments: _____ _____ _____ _____	After analysis, samples are to be: ☐ Disposed of (additional fee) ☐ Stored (90 days max) ☐ Stored over 90 days (additional fee) ☐ Returned to customer
---	--	---

APPENDIX B

DESCRIPTION OF STUDENT'S T-TEST APPLIED TO GROUNDWATER SAMPLING STATISTICS

APPENDIX B

DESCRIPTION OF STUDENT'S T-TEST APPLIED TO GROUNDWATER SAMPLING STATISTICS

The 40 CFR 265 regulations for groundwater monitoring for interim status facilities specify that a Student's T-test be used to determine whether there has been a statistically significant increase in any indicating parameter. A specific T-test is not required, however the averaged replicate (AR) T-test is recommended to comply with the statistical analysis requirements of 40 CFR 265. This test is preferred mainly because of its tendency to reduce the occurrence of false positive results.

The AR T-test is applied to both the background samples taken quarterly in the first year and to all the samples collected after the first year. The basic procedure is to determine an average concentration and variance for each measurement. These values are then used to calculate a test statistic (t) which can be compared to critical values to evaluate whether contamination has occurred.

The first step is to calculate the mean concentration (X) for the replicate measurements for each well. The method for calculating the mean depends on the number of measurements below the detection limit (DL) as follows:

- 1) If all measurements are $< DL$, then $X < DL$,
- 2) If no measurements are $< DL$, then $X = \text{arithmetic mean}$,
- 3) If only some measurements are $< DL$, then use Cohen's Method.

For the first two cases above, the average concentration is then used to calculate the variance for each replicate measurement using the standard definition of variance. The third case however, requires an adjustment of the values for the mean and variance to account for the number of measurements below the detection limit. Cohen's Method provides this adjustment by assuming a normal distribution for the data. Once the groundwater data is adjusted and summarized with appropriate values for mean and

variance, the test statistic calculation is straightforward. Critical values for comparison depend upon the chemical contaminant and number of upgradient and downgradient wells. R.G. Miller discusses methods for estimating critical values in Simultaneous Statistical Inference, (1981). A more complete explanation of the AR T-test method with examples is given in the RCRA Groundwater Monitoring Technical Enforcement Guidance Document, (EPA, August 1985).

APPENDIX C
OUTLINE OF GROUNDWATER ASSESSMENT PROGRAM

APPENDIX C

OUTLINE OF GROUNDWATER ASSESSMENT PROGRAM

The NTC must have an outline of a comprehensive groundwater assessment program that can be used to develop a specific plan if a statistically significant change is observed in groundwater quality using the statistical analysis outlined in Appendix B. The following outline specifies elements of a comprehensive groundwater assessment program:

- I. Determine if hazardous waste constituents have migrated into the groundwater:
 1. Collect groundwater samples and analyze for the hazardous waste constituents that may have entered the groundwater using EPA Methods 601/602.
 - a. The existing groundwater monitoring system may be used if it is capable of detecting low part per billion levels of the hazardous waste constituents of interest.
 - b. If the existing ground-monitoring system is not capable of detecting low levels of the hazardous waste constituents (i.e. wells with large perforation intervals), additional monitoring wells capable of providing the required samples will be installed in the area of the well in which the significant change was observed using the procedures specified in Section 2.1.
 2. If sampling indicates that hazardous waste constituents have not entered the groundwater, the original groundwater monitoring program will continue on a semi-annual basis.
 3. If sampling indicates that hazardous waste constituents have entered the groundwater, procedures to characterize the rate and extent of migration and the concentrations of the constituents in the groundwater must be implemented.
- II. Implementation of a groundwater assessment program
 1. A cluster of wells will be installed in the area of the well(s) in which concentrations of hazardous waste constituents were detected.
 - a. Initially, two to three wells will be installed in the area of each well in which the hazardous waste constituents were detected.
 - c. Based on analytical information collected from the initial cluster of wells, additional wells may be installed during the assessment to evaluate the lateral extent of contamination.

- d. The wells will be drilled to 30-40 feet below the water table using the well design and well installation procedures specified in Section 2.1.3 of the post-closure plan.

2. Sampling and analytical methods for the hazardous waste constituents

- a. Initial sampling of the wells will be performed approximately 3-7 days after installation of the wells using a depth specific sampler to evaluate vertical extent of contamination.
- b. Sampling methods and analytical procedures specified in Section 2.2 of the post-closure plan will generally be followed. However, background concentrations as specified in Section 2.2.1 will not be measured. Additionally, analytical methods will be specific to the hazardous waste or hazardous waste constituents of interest.
- c. All groundwater samples will be analyzed for the hazardous waste constituents that may have migrated into the groundwater from the HWMA's at the NTC. The hazardous wastes of concern are primarily solvents, therefore, the groundwater samples will be analyzed using EPA Method 601/602.

III. Evaluation of rate and extent of migration of the hazardous waste constituents

1. After the initial sampling effort, the installed cluster of wells will be sampled on a regular basis.
 - a. Sampling frequency will be determined at the time of closure based on the groundwater gradient and the concentrations of hazardous waste constituents in the groundwater.
 - b. Sampling will continue on a regular basis until it is determined that there is sufficient data to evaluate the rate and extent of migration and the concentrations of hazardous waste constituents in the groundwater.
2. When the data has been gathered and evaluated, a report will be submitted to the Regional Administrator summarizing the results of the groundwater assessment program.
3. After submission of the report, groundwater monitoring utilizing the initial monitoring system for the HWMA will continue on a semi-annual basis incorporating any changes or corrective actions requested by the Regional Administrator.

III. Schedule of Implementation

1. The plan will be implemented and the first determination of the rate and extent of migration and concentrations of hazardous waste or hazardous waste constituents in the groundwater will be made as soon as technically feasible following confirmation of statistically significant increases (or pH decreases) over initial background.
2. Fifteen days after the first determination, a written report documenting the assessment of groundwater quality will be submitted to the Regional Administrator and the Regional water Quality Board.

APPENDIX D

**HAZARDOUS WASTE MANAGEMENT AREA
INSPECTION LOG**

**HAZARDOUS WASTE MANAGEMENT AREA
INSPECTION LOG**

<u>Inspection Item</u>	<u>Comment</u>	<u>Action</u>
1. Inspection of the Buildings		
Are there any indications of structural damage to buildings in the HWMA ?		
2. Inspection of the Final Cover.		
Are there any depressions in the ground surface ?		
Is there any standing water in the HWMA ?		
Is there any sign of stressed vegetation in or around the HWMA ?		
Are there any cracks in concrete, asphalt or other surface cover that indicates a threat to the integrity of the HWMA ?		
3. Inspection of the Groundwater Monitoring System		
Water level		
Total depth of the well		
Turbidity of the well		
Structural integrity of the exposed well casing		
Is the well cap free of spider webs, molds, fungi, and other problems that may affect water samples ?		
Condition of surface seals		

DISTRIBUTION

No. of
Copies

OFFSITE

- 2 Robert H. Decker
Environmental Compliance Division
USATHAMA
Attention: CETHA-EC3
Arberdeen Proving Grounds, MD 21010-5401
- 8 Thomas DeCosta
Department of Engineering and Housing
National Training Center
Fort Irwin, California
- 6 David Grisa
The Earth Technology Corporation
1501 West Fountainhead Parkway
Suite 350
Tempe, Arizona 85282

No. of
Copies

ONSITE

- 5 Environmental Management Operations

Peter J. Mellinger
Darby C Stapp (3)
Project File
- 6 Pacific Northwest Laboratory

Publishing Coordination
Technical Report Files (5)

END

**DATE
FILMED**

6 / 4 / 92