**DOE/PC/89909-T6
(DE92009917)**

**IN-PLANT TESTING OF MICROBUBBLE COLUMN FLOTATION
Final Report**

**By
R.-H. Yoon
G. H. Luttrell
G. T. Adel
M. J. Mankosa**

July 31, 1991

Work Performed Under Contract No. AC22-89PC89909

**For
U.S. Department of Energy
Pittsburgh Energy Technology Center
Pittsburgh, Pennsylvania**

**By
Virginia Polytechnic Institute and State University
Blacksburg, Virginia**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615)576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U. S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

Final Report:

IN-PLANT TESTING OF MICROBUBBLE COLUMN FLOTATION

by

R.-H. Yoon, G. H. Luttrell, G. T. Adel, and M. J. Mankosa

**Virginia Center for Coal and Minerals Processing
Department of Mining and Minerals Engineering
Virginia Polytechnic Institute and State University
Blacksburg, Virginia 24061-0258**

Contract Number:

DE-AC22-89PC89909

Prepared for:

**Thomas J. Feeley III
United States Department of Energy
Pittsburgh Energy Technology Center
P.O. Box 10940
Pittsburgh, Pennsylvania 15236**

July 31, 1991

EXECUTIVE SUMMARY

Microbubble column flotation (MCF) was developed at the Virginia Center for Coal and Minerals Processing (VCCMP) for the selective recovery of fine particles. Bench-scale test work conducted at VCCMP, largely under the sponsorship of the U.S. Department of Energy (DOE), showed that the technology worked well for both coal and mineral applications. For the technology to be commercially successful, however, a full-scale demonstration of the MCF technology was deemed necessary. This report summarizes the results of work performed under the DOE project entitled "In-plant Testing of Microbubble Column Flotation." The objectives of this research and development effort were to duplicate the bench-scale performance of the MCF process in a full-scale unit, to verify the scale-up procedure developed in an earlier project (DE-AC22-86PC91274), and to demonstrate the applicability of the MCF technology to the coal industry.

The project was conducted in three phases. In *Phase I - Preliminary In-Plant Testing*, a pilot-scale MCF cell with a 30-inch diameter and 25-foot height was constructed and installed at the Tug Valley Processing Plant near Naugatuck, West Virginia. This coal preparation facility is owned and operated by the Marrowbone Development Company, a subsidiary of the Shell Mining Corporation. The test work was conducted using a slip-stream from the classifying cyclone overflow containing mostly -150 mesh material and assaying 50-60% ash. Past attempts by Shell Mining to upgrade this stream by conventional flotation were unsuccessful. The Phase I effort was financed by VCCMP and Shell Mining Company, although the cost of the pilot-scale column was subsequently reimbursed by the DOE in Phase II.

The MCF test results showed that for this particular coal the maximum volumetric throughput of the 30-inch column was approximately 100-120 gpm, which was equivalent to about 1.4 tph of dry feed at 4-6% solids. Typical operating conditions were: 25 gpm of wash water, 16 scfm of air, 0.7 lb/ton of diesel fuel collector, and 1.0 lb/ton of Betz M-150 frother. Under these conditions, a clean coal product assaying less than 10% ash was readily obtainable at a 60% combustible recovery. The corresponding reject stream typically assayed 76% ash. The heating value of the product was in the range of 12,900-13,700 Btu on a dry-basis. The grade vs. recovery curve obtained using the 30-inch diameter column was similar to that obtained with a 2-inch diameter laboratory column.

The scale-up procedures developed in the earlier project were used to estimate the number and size of columns required to process the entire classifying cyclone overflow stream at the Marrowbone plant. From the performance data obtained in the laboratory and pilot-scale columns, it was estimated that eight 8-foot or five 10-foot diameter columns would be necessary. Approximate operating costs for these full-size columns were also estimated from the test data. The cost of reagents required to obtain the desired results were projected to be about \$1.15/ton of feed. The power consumption associated with the bubble generation system was estimated to be 3.6 kwhr/ton of feed, which is approximately one-third of that required by conventional flotation cells.

Based on the scale-up projections and the initial cost estimates, it was estimated that approximately 35 tph of additional saleable clean coal (excluding the loss of fine coal in the

screen-bowl centrifuge) could be produced at the Marrowbone preparation plant by the MCF technology. Even if the penalty associated with the higher moisture content of the flotation product is considered, the effective production gain would be approximately 20 tph. At a market price of \$30/ton for the clean coal product, the plant could have an additional revenue of over \$3 million per annum, which gives rise to a payback period of less than 8 months for this new investment.

Following the successful completion of the Phase I effort, a close-out report was submitted to DOE in November 1989. Based on the results of the technical and economic feasibility studies presented in the Phase I report, authorization was given to proceed with Phase II and Phase III efforts.

The *Phase II - Continued In-Plant Testing* effort involved detailed testing of the 30-inch column to provide additional information on column operation, optimization, scale-up and control. The objectives of this work were to establish the viability of the MCF technology and to further verify the scale-up procedure developed in the previous project.

Control systems were installed to provide stabilizing control of the column operation and data acquisition capabilities. These capabilities were integrated into a single programmable logic controller that was capable of controlling and monitoring the operation of the 30-inch diameter column. The control system included instrumentation for the following measurements:

- 1) the volumetric flow rates of the feed, reject, wash water and air, and the mass flow rate of the feed;
- 2) the differential pressure at two points along the height of the column to control the pulp level and to estimate the air holdup and bubble size; and
- 3) the pressure drop across the static mixer bubble generators and the power draw on the pump motor as a means of monitoring the performance of the bubble generation system.

In addition, a sequencing routine was developed for the 8-foot column which allowed for automated start-up and shut-down of the prototype unit. The performance of both control systems was exemplary; the columns were operated without supervision for extended periods of time. The system allowed both columns to respond well to large fluctuations in the volumetric flow rate and solids content of the feed stream.

After completing the column installation and initial shakedown tests, an extensive, 54 test Box & Behnken experimental design technique was employed to evaluate the performance of the 30-inch diameter column. In each test, column performance was quantified in terms of the separation efficiency, which was defined as recovery of combustibles minus the recovery of ash in the froth product. The significant trends resulting from this analysis are:

- 1) The height of the stabilized froth zone has a minimal impact on the separation efficiency, except under high feed rates where separation efficiency drops rapidly due to a sharp decrease in overall recovery.

- 2) High gas flow rates improve the separation efficiency; however, high gas rates require high frother dosages to maintain small bubble sizes.
- 3) Higher gas flow rates generally require higher wash water flow rates in order to maintain desired ash rejection levels. As the gas rate increases, the amount of feed water reporting to the froth product (clean coal) also increases, causing a higher degree of entrainment. In order to maintain a desired ash level in the product, the entrainment must be reduced by increasing the wash water rate.
- 4) Higher frother dosages increase the separation efficiency. Too low a frother dosage produces large unstable bubbles and, hence, results in a loss of recovery (which reduces the separation efficiency). However, an excessive frother dosage rate creates a froth that is too stable. This type of froth carries a large amount of feed water and, hence, entrained ash into the froth product, resulting in a decrease in the separation efficiency.

Also of interest during the Phase II effort was the performance of the bubble generation circuit in terms of wear. Visual examination of the static mixer bubble generators showed that there was no significant wear in this particular application, indicating that maintenance requirements for the MCF system would be minimal.

The *Phase III - Testing of a Prototype Column* effort, which was conducted concurrently with the Phase II effort, involved the scale-up, design, engineering, installation, and testing of a full-size prototype MCF cell. The preliminary scale-up projections made in Phase I were revalidated using a detailed computational procedure incorporating the effects of bubble diameter, air hold-up, carrying capacity, axial mixing, and various superficial velocities. The results of these calculations suggested that a prototype column should be built having a diameter of 8-feet and a height of 25-feet in order to process approximately 15 tph of the -150 mesh cyclone overflow. This full-scale column would be capable of producing 5-5.5 tph of clean coal assaying 8-10% ash. The column design specifications called for a set of four 4-inch static mixer bubble generators, through which approximately 1,700 gpm of flotation pulp would be recirculated by means of a 32 HP centrifugal pump. At an aeration rate of 160 cfm, this system would produce an average bubble diameter of 0.26 mm and an air hold-up of approximately 41% at the exit of the bubble generators.

The structural components of the full-size MCF cell were designed by ICF Kaiser Engineers. The column was installed by Shell Mining Corporation in April, 1990, and has been in operation since that time. Long term test runs demonstrated that the column was capable of achieving all of the projected performance goals in terms of product recovery, quality, and throughput capacity. Dewatering of the clean coal product was achieved using a screen-bowl centrifuge, which had already been in operation at the plant. The loss of fine clean coal product in the plant dewatering circuit was estimated to be approximately 10%. However, detailed economic calculations conducted after the installation of the full-scale column indicated that fines losses as large as 30% would still yield a highly attractive rate of return.

The performance of the 8-foot diameter prototype column was optimized using the factorial design technique. The results of the statistical analysis of the column performance are

summarized as follows:

- 1) *Product Ash Content* - An increase in the aeration rate has a more significant impact on the product ash content than does the frother addition rate. This suggests that the aeration rate has a larger influence on entrainment than does the frother addition rate. The entrainment problem can be partially offset by increasing the wash water addition rate. An increase in the collector addition rate also tends to increase the product ash content. This increase is probably due to the increased flotation rate of middlings and the increased entrapment of mineral matter in coal agglomerates.
- 2) *Product Yield* - An increase in either the frother addition or aeration rate increases the product yield. At very high collector addition rates, however, neither the frother nor the aeration rate has significant impact on yield. At a given throughput, an increase in the wash water flow rate results in a decrease in yield. The loss in yield can be attributed to a decrease in the slurry retention time and a decrease in the stability of the froth at the higher wash water addition rates.
- 3) *Separation Efficiency* - An increase in either the aeration rate or frother addition rate gives rise to a higher separation efficiency, i.e., an increase in either parameter produces a large increase in yield with only a small increase in product ash. An increase in collector addition rate also increases the separation efficiency for the same reason. In general, the maximum separation efficiency can be achieved by selecting the appropriate combination of operating conditions which allow the column to operate at the "elbow" in the grade vs. recovery curve.

Based on the information obtained in the present work, a number of general observations have been made. These include:

- 1) For a given sample, column performance closely approximates, but never exceeds, the results obtained from a release analysis test. This finding is in agreement with previous studies which demonstrate that release analysis provides information regarding the maximum flotation recovery obtainable at a desired product ash content.
- 2) The results obtained using a 2-inch laboratory flotation column can be used to predict the performance of a full-size industrial column in terms of throughput, retention time, reagent consumption, grade, and recovery. The availability of a reliable scale-up procedure makes it possible to design full-size columns which can duplicate the grade and recovery results obtained using laboratory columns.
- 3) A properly designed coal flotation column should operate at its maximum froth carrying capacity limit. This limit is largely determined by the particle size distribution and density of particles to be recovered in the froth product. Sufficient particle retention time should be allowed so that the mass rate of solids from the pulp to the froth phase matches or slightly exceeds the maximum carrying capacity. This procedure maximizes column capacity and minimizes column volume.

The information summarized in Table 1 represents the average of test results obtained during the course of a 3-day period using the 8-foot diameter MCF cell. The column was operating at the optimum conditions established using the statistical techniques employed in the present work. Also shown in Table 1 are the scale-up projections made for the 30-inch and 8-foot diameter columns based on the 2-inch diameter column test results. In this particular series of tests, the actual volumetric feed flow rate and, hence, the superficial feed rate to the 8-foot diameter column were significantly lower than predicted. This discrepancy was due to the fact that the solids content of the feed stream to the 8-foot diameter column was considerably higher than that used in the 2- and 30-inch diameter column tests. Nevertheless, the actual solids throughput (feed mass flow rate) of the 8-foot column was the same as that predicted, because the column was operating under carrying capacity limited conditions.

Based on the test results obtained with the 30-inch and the 8-foot diameter MCF cells, two possible fine coal flotation circuits have been suggested for the Marrowbone preparation plant. The first corresponds to the original plan, in which the -150 mesh cyclone overflow stream is fed to a bank of eight 8-foot or five 10-foot diameter columns. This arrangement would produce 30-35 tph of additional saleable clean coal of approximately 8-10% ash. The second possibility is to by-pass the classifying cyclones and to feed the -28 mesh screen underflow directly to the flotation circuit. At present, the cyclone underflow (-28+150 mesh) is processed by the fine dense-medium cyclone circuit, which is presently the most costly cleaning circuit in the plant. If the MCF circuit can effectively process the 28 mesh x 0 coal with an acceptable recovery, significant savings in operating cost can potentially be realized. Although this alternative appears promising, further work is needed to verify this concept.

Table 1. Scale-up predictions for the 8-foot diameter microbubble column flotation cell.

Parameter	2-inch Measured	30-inch Predicted	30-inch Measured	8-foot Predicted	8-foot Measured
Superficial Feed Rate	0.82 cm/s	1.59 cm/s	1.69 cm/s	1.55 cm/s	1.24 cm/s
Volumetric Flow Rate	0.26 gpm	113 gpm	120 gpm	1147 gpm	921 gpm
Feed Mass Flow Rate	6.7 lb/hr	1.44 tph	1.40 tph	14.6 tph	14.6 tph
Product Ash	10.3%	10.1%	9.46%	10.1%	7.33%
Recovery	61.8%	61.8%	61.2%	61.8%	59.6%

In conclusion, the project has demonstrated that the MCF technology is useful for processing difficult-to-clean fine coal streams that are typically rejected in many coal preparation plants. Also, the testing of the technology using a full-size column in an operating plant validates the scale-up procedure developed at VCCMP. Furthermore, the economic analysis conducted in the present work indicates that the adoption of the MCF technology offers a very favorable return on investment.

TABLE OF CONTENTS

EXECUTIVE SUMMARY	i
TABLE OF CONTENTS	vii
LIST OF FIGURES	ix
LIST OF TABLES	xii
INTRODUCTION	1
PHASE I - PRELIMINARY IN-PLANT TESTING	3
Task 1.1 Site Evaluation	3
Task 1.2 Laboratory Testing	4
Task 1.3 Column Design, Fabrication, and Installation	9
Task 1.4 Shakedown Testing	13
Task 1.5 Data Analysis	13
Task 1.6 Scale-Up Projections	17
Task 1.7 Feasibility Analysis	18
PHASE II - CONTINUED IN-PLANT TESTING	21
Task 2.1 Project Planning	21
Task 2.2 Advanced Instrumentation	21
2.2.a - Installation of Instrument Package	22
2.2.b - Installation of Control Loops	26
2.2.c - Installation of Data Acquisition System	27
Task 2.3 Detailed Testing	28
2.3.a - Test Plan Development	28
2.3.b - Perform Exploratory Tests	28
2.3.c - Perform Parametric Tests	39
Task 2.4 Design Evaluation/Modification	57
2.4.a - Evaluate Column Design Features	57
2.4.b - Measure Wear of Key Components	72
Task 2.5 Control Systems	75
2.5.a - Pulp Level	76
2.5.b - Air Hold-Up and Bubble Size Control	77
PHASE III - PROTOTYPE TESTING	83
Task 3.1 Project Planning	83
3.1.a - Feasibility Study	83
3.1.b - Economic/Cost Analysis	97
Task 3.2 Column Installation	99
3.2.a - Column Fabrication	99
3.2.b - Site Preparation and Column Installation	99

3.2.c - Develop Test Plan	100
Task 3.3 Column Testing	105
3.3.a - Shakedown Tests	105
3.3.b,c,d - Initiate Task 3.2 Test Plan	109
3.3.e - Scale-Up Validation	120
Task 3.4 Cost Analysis	121
Task 3.4.a - Data Analysis	121
Task 3.4.b - Economic/Cost Analysis	122
Task 3.4.c - Assess Future Applications	126
Task 3.5 Final Recommendations	127
ACKNOWLEDGEMENTS	129
BIBLIOGRAPHY	130
Appendix 1: Material balances for the 30-inch column exploratory tests	132
Appendix 2: Material balances for the 30-inch column long-term test	145
Appendix 3: Material balances for the 2-inch column particle size tests	161
Appendix 4: Material balances for the 30-inch column cyclone feed tests	179
Appendix 5: Summary of the statistical data analysis computations for the 30-inch column parametric test program	193
Appendix 6: Response surface plots for the 30-inch column parametric test program	215
Appendix 7: Ladder logic program for column control	237
Appendix 8: Material balances for the 8-foot column long-term test	275
Appendix 9: Summary of the statistical data analysis computations for the 8-foot column parametric test program	285
Appendix 10: Predicted response surfaces for product ash percent (Figs. A), product yield (Figs. B), and separation efficiency (Figs. C)	299
Appendix 11: Cash flow analyses	317

LIST OF FIGURES

Figure 1.	Schematic representation of the laboratory microbubble column flotation cell.	6
Figure 2.	Schematic representation of the in-line microbubble generator.	7
Figure 3.	Recovery versus product ash obtained using Betz 1012 and Oreprep 303 frothers for various feed slurry conditions.	8
Figure 4.	CAD drawing of the 30-inch diameter microbubble column flotation cell.	10
Figure 5.	Cut-away view of the bottom section of the microbubble column flotation cell.	11
Figure 6.	Recovery versus product ash as a function of feed slurry rate for two levels of wash water addition.	14
Figure 7.	Recovery versus product ash obtained with 2- and 30-inch diameter columns over a wide range of operating conditions.	15
Figure 8.	Recovery versus product ash obtained with 2-inch and 30-inch diameter columns over a wide range of operating conditions.	16
Figure 9.	Projected capacity (gpm) as a function of column diameter required to obtain a 10% ash product and 60% combustible recovery.	19
Figure 10.	Simplified schematic of the proposed instrumentation package for the 30-inch microbubble flotation column.	23
Figure 11.	Effect of feed rate on combustible recovery and product ash content.	29
Figure 12.	Effect of feed rate on the solids content of the product, reject, and feed streams.	30
Figure 13.	Effect of air flow rate on combustible recovery and product ash content.	32
Figure 14.	Effect of air flow rate on the solids content of the product, reject and feed streams.	33
Figure 15.	Effect of froth depth rate on combustible recovery and product ash content.	34
Figure 16.	Effect of froth depth on the solids content of the product, reject and feed streams.	35
Figure 17.	Variations in combustible recovery and product ash content as a function of time for the 30-inch column.	36
Figure 18.	Combustible recovery and product ash values obtained with various size fractions using a laboratory microbubble flotation column.	37
Figure 19.	Combustible recovery and product ash values obtained during the processing of classifying cyclone feed.	38
Figure 20.	Yield and energy recovery obtained for each of the replicate tests conducted throughout the parametric testing program.	44
Figure 21.	Btu recovery and combustible recovery as a function of ash rejection for all the test conditions examined in the parametric study.	46
Figure 22.	Btu recovery and combustible recovery as a function of total sulfur rejection for all the test conditions examined in the parametric study.	47

Figure 23.	Combustible separation efficiency and overall separation efficiency as a function of ash rejection for all the test conditions examined in the parametric study.	48
Figure 24.	Combustible separation efficiency and overall separation efficiency as a function of total sulfur rejection for all the test conditions examined in the parametric study.	49
Figure 25.	Relationship between ash rejection and total sulfur rejection for tests results obtained during the parametric study.	51
Figure 26.	Comparison of experimental results with predictions made by the empirical model developed to describe energy recovery as a function of the various operating parameters.	54
Figure 27.	Comparison of experimental results with predictions made by the empirical model developed to describe product ash content as a function of the various operating parameters.	55
Figure 28.	Comparison of experimental results with predictions made by the empirical model developed to describe product sulfur rejection as a function of the various operating parameters.	56
Figure 29.	Comparison of experimental results with predictions made by the empirical model developed to describe separation efficiency as a function of the various operating parameters.	57
Figure 30.	Schematic showing the different wash water distributor designs evaluated during the testing of the 30-inch microbubble flotation column.	61
Figure 31.	Schematic diagram of experimental set-up for RTD studies.	64
Figure 32.	Typical normalized RTD for the 30-inch column.	65
Figure 33.	Measured versus predicted values of Peclet number.	67
Figure 34.	Fractional air content as a function of gas flow rate for 2, 3 and 4 bubble generators in the absence of frother.	68
Figure 35.	Total volumetric flow rate and flow per generator as a function of the total number of bubble generators.	70
Figure 36.	Fractional air content as a function of gas flow rate for 2, 3 and 4 bubble generators with 3×10^{-5} M Betz 1012.	71
Figure 37.	Calculated bubble size as a function of gas flow rate for 2, 3 and 4 bubble generators in the absence of frother.	73
Figure 38.	Calculated bubble size as a function of gas flow rate for 2, 3 and 4 bubble generators with 3×10^{-5} M Betz 1012.	74
Figure 39.	Schematic diagram of column level control system.	76
Figure 40.	Schematic diagram of the laboratory frother control system.	79
Figure 41.	Results of 2-inch laboratory frother control studies.	80
Figure 42.	Results of 30-inch in-plant frother control studies.	81
Figure 43.	Summary of test results obtained using microbubble flotation columns of various diameters.	84
Figure 44.	Proposed microbubble flotation column flowsheet for the Marrowbone Preparation Plant.	85
Figure 45.	Pressure versus flow curve for the microbubble generation pump	94
Figure 46.	Schematic representation of the full-scale (8-foot diameter) microbubble flotation column.	96

Figure 47.	Combustible recovery as a function of product ash percent using the 30-inch column.	103
Figure 48.	Combustible recovery as a function of feed ash rejection using the 30-inch column.	104
Figure 49.	Combustible recovery as a function of separation efficiency using the 30-inch column.	105
Figure 50.	Expected performance of the microbubble flotation column at low and optimum wash water addition rates.	107
Figure 51.	Feed ash, product ash and combustible recovery as a function of time for the 8-foot microbubble column.	108
Figure 52.	Product grade versus recovery curve for column flotation using 2-inch, 6-inch, 30-inch and 8-foot diameter cells.	109
Figure 53.	Yield and product ash obtained for each of the replicate tests conducted throughout the factorial testing program.	112
Figure 54.	Combustible recovery as a function of product ash percent for the 8-foot column factorial test program.	113
Figure 55.	Yield as a function of product ash percent for the 8-foot column factorial test program.	114
Figure 56.	Combustible recovery and separation efficiency as a function of ash rejection for the 8-foot column factorial test program	115
Figure 57.	Combustible recovery as a function of product ash percent for all column flotation tests conducted on the Coalburg seam coal.	116
Figure 58.	Comparison of experimental results with predictions made by the empirical model developed to describe separation efficiency as a function of the various operating conditions.	117
Figure 59.	Comparison of experimental results with predictions made by the empirical model developed to describe product ash percent as a function of the various operating conditions.	118
Figure 60.	Comparison of experimental results with predictions made by the empirical model developed to describe product yield as a function of the various operating conditions.	119
Figure 61.	Net cash flow predicted over ten year basis for 10, 20, 30 percent loss of fines during the dewatering stage.	124
Figure 62.	Internal rate of return for various cash flow scenarios, for different percentages of lost fines.	125
Figure 63.	Proposed flowsheet for column flotation of 150 mesh x 0 cyclone overflow material.	127
Figure 64.	Proposed flowsheet for column flotation of -28 mesh cyclone feed.	128

LIST OF TABLES

Table 1.	Recommended levels for the detailed parametric testing.	39
Table 2.	Standard conditions used for parametric test plan.	40
Table 3.	Parametric test plan utilized in the in-plant optimization studies.	41
Table 4.	Test results obtained during the parametric testing.	43
Table 5.	Estimated values of standard deviation for various assays used in the parametric test work.	45
Table 6.	Results of frother addition point tests.	59
Table 7.	Results of wash water addition point tests.	60
Table 8.	Results of RTD testing.	65
Table 9.	Scale-up predictions for the 30-inch and 8-foot diameter microbubble column flotation cells.	89
Table 10.	Design dimensions for the full-scale microbubble flotation column.	90
Table 11.	Summary of bubble generation calculations.	91
Table 12.	Summary of head loss values for each component in the bubble generation circuit.	93
Table 13.	Cost-benefit analysis for a full-scale microbubble flotation column (all values approximate)	98
Table 14.	Standard conditions used for parametric test plan.	101
Table 15.	Levels utilized in the factorial test program.	101
Table 16.	Factorial test program.	102
Table 17.	Preliminary test results obtained from the full-scale microbubble flotation column.	106
Table 18.	Results of factorial design for 8-foot column.	110
Table 19.	Scale-up predictions for the 8-foot diameter microbubble column flotation cell.	120
Table 20.	Predicted expenditures for one 10-foot diameter Microcel.	123

INTRODUCTION

Froth flotation has long been recognized as a practical and low-cost technique for upgrading fine coal. Unfortunately, the effectiveness of conventional coal flotation equipment is limited to a relatively narrow particle size range, between 100-500 microns. Because of this limitation, a significant quantity of the fine coal produced by today's mechanized mining equipment is often lost in conventional flotation circuits. In addition, fine coal streams may contain disproportionate amounts of ultrafine minerals, such as clay, that are easily carried into the froth product by hydraulic entrainment. As a result, conventional coal flotation circuits are often characterized by a high-product-ash content.

In order to overcome some of the deficiencies common to conventional coal flotation circuits, a novel process known as microbubble column flotation (MCF) was developed at Virginia Tech in the early 1980's. The development of this process originated from hydrodynamic studies that suggested that smaller air bubbles could be used to improve the capture rate and, hence, the recovery of fine particles. It was also discovered that these bubbles could best be utilized in a flotation column where countercurrent wash water could be used to prevent the nonselective entrainment of mineral fines.

Although column flotation has emerged as an attractive method for upgrading ores in the minerals industries, many uncertainties still exist in regard to the development of criteria for the design, operation, and scale-up of columns. This is particularly true for the microbubble column flotation of coal, where the operational characteristics may be quite different from those of mineral columns. In addition, guidelines need to be developed for

the design and operation of large-scale columns in the coal industry, where few commercial applications have been attempted.

This study, which addresses these concerns, was broken down into three phases:

Phase I - Preliminary In-Plant Testing involved the testing of a 30-inch diameter microbubble flotation column. The work was carried out as a joint effort between the Shell Mining Corporation and the Virginia Center for Coal and Minerals Processing (VCCMP). The test work was performed on-site at the Marrowbone Preparation Plant, located near Naugatuck, West Virginia. The Phase I work was carried out without funding from the Department of Energy (DOE).

Phase II - Continued In-Plant Testwork involved the testing of the 30-inch column to obtain detailed information about the operation, optimization, scale-up, and control of the microbubble flotation column. This phase of the test work was carried out as a joint venture between the VCCMP, DOE and the Shell Mining Corporation.

Phase III - Testing of a Prototype Column involved a preliminary study of the technical and economic feasibility of installing a full-scale prototype column in the Marrowbone plant; the design, construction, installation, and testing of an 8-foot unit; and a final analysis of column performance, cost, and potential applicability of the microbubble column flotation technology.

PHASE I - PRELIMINARY IN-PLANT TESTING

Task 1.1 Site Evaluation

The Marrowbone Preparation Plant, which is located near Naugatuck, West Virginia, was selected for the preliminary in-plant test program. Raw coal is supplied to the plant from three underground mines and one surface mine that work the Coalburg, Clarion, and No. 5 Block coal seams in southern West Virginia. The plant has a capacity of 1500 tph of raw feed and operates at an overall recovery of approximately 55%. The clean coal product assays about 10-12% ash, 0.66% sulfur and 12,000 Btu/lb.

Approximately 7% of the raw coal feed is present in the -150 mesh classifying cyclone overflow. The material contained in this stream is difficult to upgrade by conventional processes because of its fine size (-150 mesh), high-ash content (58%) and low-solids content (4-6%). The low solids content of this stream requires the processing of a large volumetric flow of slurry in order to obtain an acceptable throughput of solids. It is estimated that approximately 9,000-10,000 gpm of slurry must be handled by the fines cleaning circuit. The separation is further complicated by the presence of large quantities of ultrafine clay minerals, or slimes, which are contained in the feed coal.

Early attempts to recover the fine coal contained in the -150 mesh classifying cyclone overflow were unsuccessful. The original plant flowsheet developed by Dravo Engineers included four 4-cell banks of 300 ft³ conventional flotation cells. However, the conventional flotation cells were unable to produce an acceptable product grade or recovery because of the aforementioned difficulties. These cells have since been removed from the plant. For lack of a better processing scheme, the fine coal fraction is presently being discarded.

During 1989, personnel from the Shell Mining Group contacted VCCMP at Virginia Tech seeking new and effective methods for recovering the fine coal being lost in the classifying cyclone overflow. As a result of these discussions, a preliminary test program was outlined in which a 1-2 tph MCF cell would be installed and tested in the Marrowbone Preparation Plant. The objective of the test program was to determine the applicability of the MCF technology for producing a product assaying less than 10% ash at an acceptable level of recovery. The on-site test work was performed by personnel from the VCCMP in conjunction with a senior preparation engineer from Shell Mining Corporation. Preliminary inspection of the plant site indicated that the 1-2 tph column could be installed along the interior wall of the plant filter-press room, which was not then being utilized. This area was ideally suited for installation of columns because it was in close proximity to the transfer line for the classifying cyclone overflow, sufficient head room was available, and it did not interfere with normal day-to-day operation of the plant. In addition, the vacated filter-press control room served as an ideal area for installing the electronic instrumentation required to monitor and control the operation of the MCF cell.

Task 1.2 Laboratory Testing

Prior to installing the 1-2 tph column, a series of small-scale laboratory tests were performed to establish the general applicability of the MCF technology for upgrading this coal. The material used in these tests was obtained directly from a sampling port installed in the mid-section of the cyclone overflow transfer line. The samples were collected in 55 gallon drums and transported to the laboratories at Virginia Tech for testing.

A 2-inch diameter MCF cell with a height-to-diameter ratio of 20 was used for the laboratory test work. A schematic representation of the laboratory column is shown in Figure 1. Feed slurry is introduced to the column at a point just below the froth-pulp interface. As the slurry flows down the column, hydrophobic particles contained in the feed slurry are collected by the rising air bubbles. This section of the column behaves like a rougher cell in a conventional flotation circuit. The particle-laden bubbles enter the froth layer where they rise against a countercurrent flow of wash water. Acting as a cleaner stage, this section of the column prevents entrained particles of mineral matter from entering the froth product. Particles that are not sufficiently hydrophobic to be collected in the main section of the column eventually become part of the slurry that is recycled through the bubble generators for producing microbubbles. The co-current flow of particles and bubbles through the turbulent region inside the bubble generator enhances the contact between bubbles and particles and allows for the additional recovery of fine coal. This section of the column behaves much like a scavenger cell in a conventional flotation circuit. Hydrophilic particles eventually pass to the bottom of the column where they are rejected via an overflow weir.

A schematic representation of the microbubble generator used in the laboratory test work is shown in Figure 2. In order to generate microbubbles, air is mixed with a portion of the flotation pulp and pumped under pressure through a single in-line motionless mixer. Inside the generator, multiple small blades are arranged to cause a rapid change in the direction of fluid flow along the length of the generator. The shear induced into the liquid by this action breaks larger bubbles into smaller ones in a very uniform manner. The generator is capable of producing a relatively narrow distribution of bubble sizes in the range of 0.1-0.4 mm in diameter.

Figure 1. Schematic representation of the laboratory microbubble column flotation cell.

Figure 2. Schematic representation of the in-line microbubble generator.

Flotation samples were prepared by adding approximately 0.5 lb/ton of fuel to the well-mixed slurry. Because of problems associated with conditioning large volumes of slurry in the plant, the conditioning time was kept very short in the laboratory tests. For most tests, conditioning time was less than 30 seconds. Two different frothers, Betz 1012 and Oreprep 303, were utilized in the test work. Typical frother dosages varied between 0.5 and 1.0 lb/ton for Betz 1012 and between 2.0 and 3.0 lb/ton for Oreprep 303. Unless otherwise specified, the aeration rate was held constant at 1.2 liter/min. It should be noted that these values do not necessarily represent the best conditions for treating this coal. Unfortunately, neither the reagent package nor the operating parameters could be optimized because of the short amount of time allotted for this particular subtask.

Since the classifying cyclones in the plant were subject to frequent plugging, the laboratory tests were conducted using both fine (i.e., normal cyclone operation) and coarse (i.e., plugged cyclone) coal feeds. In order to remove extremely coarse material that had no chance of being recovered during flotation, each sample was screened at 28 mesh, and the oversize was discarded prior to testing.

The results of the laboratory flotation tests are shown in Figure 3. The results shown in this figure clearly demonstrate the ability of the MCF process to produce a 10% ash product while maintaining a combustible recovery of at least 60%. These results are encouraging in light of the difficult nature of this coal and the fact that none of the operating parameters had been optimized. The preliminary data also indicated that both the Betz 1012

Figure 3. Recovery versus product ash obtained using Betz 1012 and Oreprep 303 frothers for various feed slurry conditions.

and Oreprep 303 reagents produce essentially the same recovery-ash curve, although the Oreprep frother required more than twice the reagent dosage in order to achieve the same results. Since the commercial prices of Oreprep and Betz are \$0.86/lb and \$1.09/lb, respectively, the Betz appears to be the more attractive alternative.

Task 1.3 Column Design, Fabrication, and Installation

In light of the promising laboratory test results, steps were taken to begin the construction of the 1-2 tph MCF cell. Preliminary scale-up projections indicated that a 30-inch diameter column would be required to achieve the desired throughput capacity. Conceived by the staff of the VCCMP, the basic cell design was passed to ICF-Kaiser Engineers in Pittsburgh, Pennsylvania, for further development. This group was responsible for the development of the engineering/fabrication prints, evaluation of structural integrity, and specification/acquisition of the various column components.

A computer-generated schematic of the selected column design is shown in Figure 4. The column consists of three basic sections. The top section of the column serves as the froth collection launder as well as a support brace for the feed and wash water distribution piping. The intermediate portion of the column consists of modular subsections, each measuring 5 feet in length, that can be added or removed to accommodate changes in column height. The bottom section of the column, which is shown in greater detail in Figure 5, houses the microbubble generation system and provides a means for collecting and removing refuse from the column. In addition, this section provides the structural footing that supports the column weight. When three intermediate subsections are utilized the total height of the column is 26 feet.

Figure 4. CAD drawing of the 30-inch diameter microbubble column flotation cell.

Figure 5. Cut-away view of the bottom section of the microbubble column flotation cell.

Feed is introduced into the column by means of an interchangeable central feed pipe. The use of feed pipes of different lengths allows one to easily vary the location of the feed injection point. The top section of the column is also equipped with a 2-inch wide plexiglas window that runs vertically along the length of the column. This window allows easy monitoring of the location of the froth-pulp interface and provides the operator with a rough visual estimate of the size of bubbles present in the column. The wash water distribution manifold is suspended from the support brace and can be easily raised or lowered as required. A final notable feature of the column design is the inclusion of bolt mounted flanges in each section so that various types of instrumentation, e.g., pressure sensors, can be installed when deemed necessary.

The design for the microbubble generation circuit consists of a 10-HP centrifugal pump that passes flotation pulp through several parallel in-line microbubble generators. Although the column is equipped with six 2-inch diameter generators, scale-up projections indicated that only three would be required for normal operating conditions. Equal distribution of air and slurry to each generator was facilitated by cylindrical distribution rings that are concentric with the lower section of the column. Gate valves were placed on both sides of each generator in order to allow servicing and/or replacement of the generators without shutting down the column. The inlet port for frother solution was placed in the suction line of the centrifugal pump to improve mixing prior to passage through the bubble generators.

The only instrumentation included as part of the original column design was that deemed essential to the operation of the column. Rotameters were used to monitor the flow rates of air and wash water to the column. The feed rate of slurry to the column was monitored by a magnetic flow meter installed ahead of the column in the discharge line from the conditioning sump. An automatic control circuit maintained the pulp level in the column by monitoring the pressure in the column adjusting an automatic control valve in the reject line. The addition rates of frother and diesel fuel were controlled using chemical metering pumps.

After approval of the final engineering prints, construction of the column was initiated by Ceramic Technologies Incorporated of Wardell, Virginia. This group was responsible for ordering raw materials, fabricating the column sections, and transporting the column to the plant site. Contractors hired locally by Shell Mining were responsible for installation of the major column components. Personnel from the VCCMP were responsible for installing minor column components (i.e., valves, hoses, fittings, etc.) as well as the various instruments required to monitor the operation of the process unit.

Task 1.4 Shakedown Testing

Several different sets of operating conditions were examined during the preliminary testing of the 30-inch diameter MCF cell. These included aeration rate, reagent dosage, wash water flow rate, and feed slurry flow rate. In each of these tests, column feed was prepared by conditioning the slurry in an agitated 200-gallon tank into which diesel fuel was added at a controlled rate. The longest conditioning time was approximately 1 minute, although most of the tests were performed with considerably shorter conditioning times. The conditioned slurry flowed by gravity into the column at a point about 4 feet below the overflow lip. Clarified plant water was introduced to the column through a distributor located just below the overflow lip of the product discharge. The frother dosages used during the testing varied from approximately 0.7 to 1.1 lbs/ton of feed. Betz 1012 was used as the frother for the majority of the test work. Although slight variations were noted, the dosage of diesel fuel was generally held at approximately 0.7 lbs/ton, while the aeration rate was maintained in the range of 12 to 20 scfm.

Task 1.5 Data Analysis

Figure 6 shows the first series of test results obtained with the 30-inch diameter column. A feed slurry flow rate of 100-120 gpm was used for the majority of the tests. Because of line-pressure restrictions on the fresh water feed, the first tests were conducted using a sub-optimal wash water flow rate of only 15 gpm (i.e., a superficial velocity of 12.5 cm/min). These results show that a combustible recovery of 60% can be obtained only at a product ash content of approximately 12%. After the line-pressure problems on the wash water supply were corrected, a second series of tests was performed at the proper wash water

Figure 6. Recovery versus product ash as a function of feed slurry rate for two levels of wash water addition.

flow rate of 25 gpm (i.e., 19 cm/min). As shown in Figure 6, this adjustment reduced the product ash content by an additional 2%-3%, thus shifting the recovery-ash curve. These results support the findings of the laboratory test work, which indicated that a 60% combustible recovery is possible at a product ash content of 10%. The heating values of the products obtained from the 30-inch diameter column tests ranged from 12,900 to 13,700 Btu/lb (dry).

Figure 7 summarizes the test results obtained using the 30-inch diameter MCF cell under a wide variety of operating conditions. The 2-inch diameter test results are also included on this figure as a source of reference. The same results are also shown in Figure 8, but the scale representing product ash has been expanded so that the degree of data scatter can be better observed. The resultant data scatter was primarily due to changing feed characteristics brought about by intermittent plugging of the classifying cyclones.

Figure 7. Recovery versus product ash obtained with 2- and 30-inch diameter columns over a wide range of operating conditions.

Figure 8. Recovery versus product ash obtained with 2-inch and 30-inch diameters columns over a wide range of operating conditions.

Nevertheless, these results show that the recovery-ash curve is essentially the same for both columns despite the wide range of operating conditions. In fact, the test data indicate that the 30-inch column produced slightly better results than those obtained using the laboratory column.

Based on the aforementioned results, a reasonable operating capacity for the 30-inch column appears to be approximately 100-120 gpm. This corresponds to a feed solids throughput of 1.6 tph. These results can be sustained at reagent dosages of approximately 0.7 lb/ton for diesel fuel and 1.0 lb/ton for Betz 1012. Under these conditions, it is expected that a full-scale column can produce a 10% product ash while maintaining a combustible recovery of at least 60%. The reject stream would have a corresponding ash content in the range of approximately 76%.

Task 1.6 Scale-Up Projections

During the past several years, considerable attention has been given to the development of an effective and reliable scale-up procedure for column flotation. The most recent version of the scale-up procedure allows the required column diameter and length to be determined for any desired throughput capacity. The scale-up methodology is based on maintaining a constant recovery and grade during scale-up. The procedure is also based on the assumption that the bubble size and the characteristics of the feed material do not change for the larger scale unit.

In order to validate the scale-up procedure, the test data obtained from the 2-inch diameter column tests were used to project the column geometry required to achieve the throughput obtained in the 1-2 tph column. The scale-up procedure indicated that the

maximum allowable superficial velocity of feed slurry through the large-scale column could not exceed 1.56 cm/s. At this superficial rate, the column diameter required to maintain a volumetric flow rate of 100 gpm is 29.8 inches. This value agrees quite well with the actual column diameter of 30 inches used in the test work. A preliminary estimate of the column length was found to be only about 20 feet for this particular application.

The preliminary scale-up projections for larger column cells are shown in Figure 9. As shown, the scale-up data indicate that approximately eight 8-foot diameter columns would be needed in order to handle the total flow of the classifying cyclone overflow. Little or no increase in the column length is expected over that used for the 30-inch diameter column. These values are derived from the assumption that the columns are being designed to obtain a product quality of about 10% ash at a combustible recovery of 60%.

Task 1.7 Feasibility Analysis

The test work outlined in this report demonstrates that the microbubble column flotation process can be used to successfully upgrade the classifying cyclone overflow from the Marrowbone Preparation Plant. At a feed throughput of 100-120 gpm, the 30-inch diameter column was able to produce a combustible recovery of approximately 60% with product and reject ash contents of 10% and 76%, respectively.

Rough estimates of the operational costs for a full-scale MCF cell can be figured from the data collected from the preliminary test work. The cost of reagents required to obtain the desired results is estimated to be about \$1.15 per ton of feed. Energy consumption associated with the operation of the microbubble generation pump has been shown to be approximately 1/3 that of the power consumed by conventional flotation circuits of the same

Figure 9. Projected capacity (gpm) as a function of column diameter required to obtain a 10% ash product and 60% combustible recovery.

capacity. The power consumption of the 30-inch diameter column was found to be only 3.6 kW-hr per ton of feed. The capital cost of the equipment and expenses associated with column installation will be presented in Task 3.4.

Based on the test data collected in the present work, approximately 35 tph of salable clean coal can be produced at the Marrowbone Preparation Plant by the MCF technology. Unfortunately, the higher moisture content of the fine coal from the flotation circuit indicates that the gravity of the coarse-coal heavy media circuit may need to be decreased slightly to compensate for the higher moisture content. As a result, the net recovery of clean coal from the plant has been estimated to be in the range of approximately 20 tph. Nevertheless, at this level of production an additional revenue of over \$3 million annually should be realized. The payback period for the MCF cells has been estimated to be considerably less than one year.

PHASE II - CONTINUED IN-PLANT TESTING

Task 2.1 Project Planning

This project was originally divided into three phases. Phase I - Preliminary In-Plant Testing, was a joint effort between the VCCMP and Shell Mining Corporation to test the feasibility of using the MCF process to treat fine coal on a commercial scale. This task utilized a 30-inch diameter column and was carried out at the Marrowbone Preparation Plant near Naugatuck, West Virginia. Following the successful completion of the Phase I work, a close-out report was issued to the DOE on November 13, 1989, detailing the results of this test work and providing preliminary information on the technical and economic feasibility of the MCF process. The DOE then gave authorization to proceed with Phase II - Continued In-Plant Testing and Phase III - Testing of a Prototype Column.

The Phase II work involved the continued testing of the 30-inch column to obtain detailed information on the operation, optimization, scale-up, and control of the microbubble flotation column. The Phase III effort involved the scale-up, engineering, design, and testing of the full-scale prototype column. Both phases of the test work were carried out as a joint venture between the VCCMP, the DOE, and the Shell Mining Corporation.

Task 2.2 Advanced Instrumentation

In order to properly instrument the column according to the requirements of Task 2.2, the following three areas were addressed:

- i) measurement of pressure, density, and volumetric flow rates,
- ii) loop control for bubble size and pulp level, and
- iii) microprocessor-based data acquisition.

Although each of these tasks could be handled independently, it was determined that a single, integrated system would be more efficient and would interface most readily with existing plant control systems. In addition, the system should accommodate sequencing operations so as to provide the operator with push-button start-up, shut-down, and control of the column. Based on discussions with Shell Mining's control and instrumentation experts, a programmable logic controller (PLC) based system was selected and installed for control of the 30-inch and 8-foot columns. An Allen-Bradley 5/25 programmable controller was selected for this application. The 5/25 system is a rack-mounted unit containing the required I/O cards, the process controller and the power supply in one self-contained unit. This system should be capable of handling all control requirements for both columns.

All process instrument signals were supplied to the PLC via 4-20 mA current signals. Loop control for level, bubble size, and flow was also maintained by means of the PID capabilities of the PLC. All of the associated motor starters, solenoid valves (i.e., feed, wash water and air) and limit switches were also terminated at the PLC to provide sequencing capabilities. This arrangement provided one centralized system for column control. Local access to the system was provided through an Allen-Bradley Panel View control monitor located in the immediate vicinity of the column. Panel View is a CRT display equipped with limited operator access for control of column operation.

2.2.a - Installation of Instrument Package

A simplified schematic of the proposed instrumentation package for the 30-inch column is shown in Figure 10. As shown, the package consists of volumetric flow measurements on the feed, reject, and wash water streams to aid in determining the material

Figure 10. Simplified schematic of the proposed instrumentation package for the 30-inch microbubble flotation column.

balance around the column. Feed mass flow rate was also determined through a combination of volumetric flow rate and density, the latter determined by means of a Coriolis density/mass flow meter. The Coriolis-type mass flow meter was selected over a nuclear-based instrument due to government restrictions regarding interstate transportation of radioactive materials. Pressure sensors mounted on the side of the column were used to control pulp level and to determine air hold-up for estimating and controlling bubble size. Several sensors were also located around the bubble generation system in order to monitor air flow rate, pressure on the static mixers, and power draw on the pump motor. The

information obtained from these instruments was used to characterize the performance of the bubble generation system. These results are presented under Task 2.4. Controllable reagent pumps were used to maintain constant addition rates for frother and diesel fuel. Finally, a conductivity probe was located in the column reject line to determine the residence time distribution in the column by means of salt tracer tests. Accommodations were also made to incorporate this same sensor into the 8-foot column for additional RTD testing.

Initially, the flow rates of air and wash water were measured using mechanical rotometers. Prior to the installation of these meters, however, it was found necessary to install pressure regulators on both the air and fresh water feed lines to prevent fluctuations in flow rate due to changes in the plant pressure supply. In general, the mechanical rotameters performed quite well except for one problem. The presence of condensed water in the air line frequently made the flow rate difficult to measure accurately. Remounting the air flow meter ahead of the pressure regulator on the high pressure side of the supply line helped reduce this problem. A Poro-Stone air filter/moisture trap has since been installed on the air feed line and has eliminated the moisture problems. Electronic sensors were also installed on these lines in order to provide an output signal for the PLC system; however, the rotameters were left operational for purposes of instrument calibration.

Volumetric air flow rate was measured using an RCM Industries differential pressure, direct reading flow meter. This instrument provides a local display of the air flow rate for a specified instrument pressure as well as a 4-20 mA output signal for remote sensing. The display reading must be corrected for the actual input pressure according to the following equation:

$$Q_a = Q_m \sqrt{\left(\frac{P_a + 14.7}{P_c + 14.7} \right)} \quad [1]$$

where,

Q_a = actual flow rate [SCFM],

Q_m = measured flow rate [CFM],

P_a = actual gas pressure [psig], and

P_c = calibrated gas pressure [psig].

Wash water and feed slurry flow rates were measured using Brooks Series 7400 electromagnetic flow meters. These meters were calibrated to provide a $\pm 1.0\%$ flow accuracy over a range from 20-200 gpm. In addition, frother and collector were added using Metronics chemical metering pumps. Both the feed flow meters and the reagent pumps were equipped with 4-20 mA output signals, which were connected to the PLC. Each of these flows was controlled using pneumatic valves, actuated remotely by means of the PLC system.

In order to control column level and monitor air hold-up, twin differential pressure transducers (Honeywell ST 3000) were installed in the upper and lower sections of the 30-inch and 8-foot diameter columns. The upper transducer was mounted approximately 6 feet from the top of the column for use in sensing the pulp level, while the lower transducer was installed just above the inlets for the microbubble generators. The lower sensor was used in conjunction with the upper to determine air hold-up in the column. The air hold-up and flow rate measurements provide an on-line method for determining the average size of bubbles within the column.

Feed density was determined by means of a Coriolis mass flow meter. This instrument determines the bulk density of a fluid as it passes through a pair of S-shaped sensor elements. In the current project, these elements are continuously oscillated by means of an electro-mechanical driver system. As the fluid passes through the elements, a shift occurs in their natural vibrational frequency. Detected by magnetic pick-ups, this phase shift was proportional to the mass of the fluid passing through the sensor and can be converted to fluid density.

Finally, allowances were made to install a conductivity sensor in the tailings discharge line for both the 30-inch and 8-foot diameter columns. This sensor was located just prior to the level control valve. The probe was used to detect changes in conductivity of the column tailings stream as a function of time. When a salt tracer was added with the column feed, it provided a means for on-line measurement of the residence time distribution for each column. The output signal from this device was also connected to the PLC system for data logging purposes.

2.2.b - Installation of Control Loops

Two main loops were installed for control of the 30-inch column, as shown in Figure 10. The first control loop was designed to maintain a constant level in the column and was successfully installed and tested. A 4-20 mA signal from the pressure transducer was fed to a Honeywell UDC 2000 Mini-Pro digital controller. Using PID control logic, the controller determines the required adjustments to the reject control valve. The valve selected for tailings control was a 2-inch diameter pneumatic "pinch" valve manufactured by the Red

Valve Corporation. This system is capable of holding level to within ± 1 inch during normal operation.

The second control loop installed on the column was designed to maintain a constant bubble size in the pulp. This system consists of a controller that determines differential pressure from the two DP cells mounted on the column and converts readings to fractional air hold-up. Air hold-up values are used in conjunction with the air, wash water and reject flow rates to provide on-line estimates of bubble size. The procedure for estimating bubble size from column operating conditions has been described previously (M.J. Mankosa *et al.*, 1990). They found that if the bubble size is too large, the air hold-up will fall below a set-point value and the addition rate of frother will be increased. If the bubble size becomes too small, the air hold-up will overshoot the desired set point and the frother flow rate will be decreased.

In the case of the 30-inch cell, bubble size control is conducted by the PLC system. The differential pressure measurements are recorded by the PLC and directly converted to fractional air hold-up by the ladder logic routine used for data collection. The ladder logic program construction is explained in greater detail under Task 2.5. The bubble diameter within the column is determined based on the measured air fraction and flow conditions. This value is used as the measured process variable for purposes of control. The controlled output is the column frother addition pump.

2.2.c - Installation of Data Acquisition System

Data was also acquired through the Allen-Bradley PLC system. This system is capable of handling 1024 input/output instrument signals. These signals can be either analog

(i.e., 4-20 mA, 0-10 volts, 0-5 volts) or discrete (48 VDC, 120 VAC). All instrument signals used in this project were 4-20 mA current proportional signals. Data logging, trending, manipulation, and display were achieved through the Control View software package obtained from Allen-Bradley. This software contains built-in subroutines that are specifically designed for data acquisition using a PLC-based system. The software can accommodate a wide variety of data acquisition functions by simply specifying I/O port addresses for specific instrument signals.

Task 2.3 Detailed Testing

2.3.a - Test Plan Development

A detailed test plan describing the parametric study to be carried out on the 30-inch column was submitted to the DOE on January 22, 1990. This test plan consisted of two parts: an exploratory test plan and a parametric test plan. The exploratory test program was designed to establish the appropriate levels at which the various operating parameters would be set for the detailed parametric study. The detailed parametric study was designed to establish mathematical relationships between column operating parameters and column performance.

2.3.b - Perform Exploratory Tests

Several preliminary tests were performed to determine the overall response of the 30-inch column to changes in key operating variables. The tests were performed by varying one test parameter at a time while holding all others constant. The standard test conditions were:

- 1) feed rate 100 gpm
- 2) wash water rate 23 gpm
- 3) aeration rate 16.4 cfm
- 4) froth depth 40 inches
- 5) frother dosage 1.25 lb/ton
- 6) collector dosage 1.25 lb/ton

The metallurgical balance sheets for these tests are provided in Appendix 1.

The effect of feed rate on the performance of the column is shown in Figure 11. As shown, combustible recovery decreased slightly from 65.7% to 59.8% when the feed rate was increased from 78 to 120 gpm. A corresponding decrease in product ash content was observed over the same range of feed rates. The slight dip in the ash curve at 100 gpm was due primarily to a momentary decrease in the feed ash to the column, which resulted in a

Figure 11. Effect of feed rate on combustible recovery and product ash content.

slightly improved clean coal quality. That feed rate had only a limited impact on column performance tends to indicate that the column is operating under rate limited conditions. Under such conditions, changes in retention time slightly affect overall column recovery.

The solids content of the feed, product, and reject streams for the various feed flow rates is shown in Figure 12. In general, the solids content of the feed and reject streams remained relatively constant. The product stream, on the other hand, appeared to decrease as the feed rate increased. The decrease in the product solids content may be a result of several interactions. The first is an increase in the frother concentration in the column. Since the lb/ton dosage of frother was held constant, a higher feed rate resulted in a larger volumetric flow rate of frother to the cell. However, the wash water flow rate remained constant as feed rate was increased. Therefore, the ratio of frother flow to total volumetric

Figure 12. Effect of feed rate on the solids content of the product, reject, and feed streams.

flow increased with an increase in feed rate. This resulted in a higher concentration of frother in the cell. The increased frother concentration, in turn, reduced the bubble size in the froth, producing a wetter froth and a lower solids content in the product.

In addition to the frother concentration effect, the increase in feed rate brought the column closer to the carrying capacity limitation of the cell. The concept of froth carrying capacity will be discussed in greater detail in the following sections of this report.

Laboratory results indicate that as the carrying capacity limitation is approached coarse particles are preferentially rejected from the froth. This, in turn, results in a decrease in the product mass flow rate and, hence, the froth percent solids.

The response of the column to changes in aeration rate is shown in Figure 13. As shown, the combustible recovery was relatively insensitive to changes in aeration rate over a range of 12.3 to 19.9 scfm. This is most likely a result of an increase in bubble size with increasing gas rate. In contrast, the product ash content increased significantly from 8.0% to over 10.5% by increasing the air flow rate. The increased product ash was probably due to an increase in nonselective entrainment of fine particles of mineral matter as air rate was increased. In general, higher air rates produce an increase in the water recovery rate, which in turn decreases the effectiveness of the wash water. This conclusion is supported by examination of the solids content plot shown in Figure 14. As the air rate increased, the solids content of the product dropped from 14.1% to 10.9%, despite the fact that the solids content of the feed stream was increasing during this period. This result indicates that the effectiveness of the wash water is impacted by a very strong relationship between product grade and factors such as frother addition, aeration rate, wash water rate and wash water injection point. This may be an area that will require further study.

Figure 13. Effect of air flow rate on combustible recovery and product ash content.

The effect of froth depth on combustible recovery is shown in Figure 15. As shown, a froth depth of 31 inches produced a combustible recovery of 52.2%, while an increase in froth depth by 16 inches increased the combustible recovery to 66.5%. The product ash content, on the other hand, remained relatively unchanged over the same range of froth depths. The exact cause of the improved recovery with a deep froth bed is not yet fully understood. However, preliminary indications suggest that this response may be due to a shift in the split of wash water that enters the column. As shown in Figure 16, the froth appears to become wetter as the froth depth is increased. This implies that a larger percentage of the wash water is reporting to the product stream and that a smaller portion is diluting the pulp. This behavior may have many implications on column performance. First, since less wash water reports to the pulp when using a deep froth, less dilution of the

Figure 14. Effect of air flow rate on the solids content of the product, reject and feed streams.

frother occurs. This produces a higher residual concentration of frother in the cell, which allows smaller bubbles to be produced. The smaller bubbles may account for the higher recovery rates. It may also be possible that the increased water content of a deep froth may reduce bubble coalescence. This would result in a larger bubble surface area available for carrying particles, thus, increasing the carrying capacity of the froth. Nevertheless, the results shown in Figures 15 and 16 do demonstrate the importance of maintaining a deep and stable froth in order to achieve good recoveries while keeping a low product ash content.

In addition to the exploratory tests conducted for the purpose of establishing parameter levels for the detailed parametric study, a long-term test was conducted to determine whether column performance would remain stable during normal feed fluctuations occurring over the period of several plant shifts. This long-term test was carried out over a

Figure 15. Effect of froth depth rate on combustible recovery and product ash content.

period of 48 hours, during which samples were taken approximately every three hours. The feed rate was fixed at 100 gpm during the entire run. The aeration rate and wash water rates were held constant at 16.4 scfm and 23 gpm, respectively. Both collector and frother addition rates were set at 1.25 lb/ton.

Figure 17 shows the combustible recovery and product ash values obtained during the extended test run. The metallurgical balance sheets for these tests are shown in Appendix 2. For reference, the feed ash content is also provided to show the large variations in the feed stream quality during testing. As can be seen, the product ash content remained relatively constant and well within the target value of 10% during the entire duration of the test. The

Figure 16. Effect of froth depth on the solids content of the product, reject and feed streams.

average values of the combustible recovery and product ash for the entire test run were 61.2% and 9.46%, respectively. The major impact of fluctuations in the ash content of the feed stream appeared to be reflected only in the combustible recovery. From a plant operation point-of-view, this is a very significant finding since it indicates that product quality is always maintained.

The results shown in Figure 17 also demonstrate the importance of adding a proper amount of diesel collector. At one point in the test run, the supply tank for the diesel fuel ran empty. Recovery immediately fell in response to the loss of collector. However, product grade still remained stable. These results are very encouraging and suggest that the

Figure 17. Variations in combustible recovery and product ash content as a function of time for the 30-inch column.

column should be able to maintain product grade within a close tolerance specification despite the presence of system disturbances.

Another objective of the preliminary test work was to determine whether coarse particles could be effectively treated by microbubble column flotation without sacrificing either recovery or grade. This may have several advantages in the existing operation including improved dewatering, improved classification performance, and simplification of the plant flowsheet. Initial test work was conducted using a 2-inch laboratory column and a sample collected at the plant site from the classifying cyclone feed stream. The sample, as received, was split into four representative lots and then screened to produce four different

size distributions. The sizes selected for the preliminary work included -28 mesh, -48 mesh, -65 mesh and -150 mesh.

Figure 18 shows the results of this test work, while the metallurgical balance sheets for these tests are provided in Appendix 3. As shown, the coarser material generally appeared to produce a higher overall grade-recovery curve. Contrary to preliminary estimates, these results imply that the coarse size fractions contain substantial quantities of low ash coal that can be recovered by flotation.

The potential benefits to plant operation resulting from processing coarser material by flotation made it worthwhile to conduct additional follow-up test work with the 30-inch column at the plant site. In order to get a coarser size distribution at the plant site, a portion

Figure 18. Combustible recovery and product ash values obtained with various size fractions using a laboratory microbubble flotation column.

of the cyclone feed stream was used as feed to the column. Several different sets of operating conditions were examined in an attempt to duplicate the laboratory data. The results of this work are shown in Figure 19, and the metallurgical balance sheets are provided in Appendix 4. As shown, a combustible recovery greater than 45% was never achieved in any of the test work. Several possible explanations may be given for the discrepancy between the laboratory and in-plant test results. The most likely reason, however, was the inability to maintain a reliable feed size distribution. Because of upstream problems with classification, a substantial portion of +1/8-inch material was generally present in the feed stream to the cyclones. At times, this accounted for nearly 60-70% of the feed stream by weight. Additional testing would be required in order to resolve this discrepancy. However, that was considered to be beyond the scope of this project.

Figure 19. Combustible recovery and product ash values obtained during the processing of classifying cyclone feed.

2.3.c - Perform Parametric Tests

General: As a result of the data collected in the exploratory test program, the appropriate levels were determined for the parametric test work. The recommended settings for each parameter are summarized in Table 1. It should be noted that the measured parameter settings are very close to those initially suggested in the original work outline. The only major change is in the frother and collector addition rates, which have been changed from a weight ratio (i.e., lb/ton) to a flow rate (ml/min). This change is necessitated by difficulties in maintaining a fixed solids content in the feed stream. Since the feed solids content is variable, a lb/ton dosage cannot be determined until after the samples are obtained. However, the levels recommended in Table 1 for the flow rates of frother and collector should provide lb/ton dosages very close to those which were originally proposed. The standard operating conditions for the remaining variables are listed in Table 2. A statistical design and data analysis program (DESIGN-EXPERT, developed by Stat-Ease of Minneapolis, Minnesota) was used to set-up the experimental design and to perform all

Table 1. Recommended levels for the detailed parametric testing.

Parameter	Unit	Low	Normal	High
pulp height	inches	20	40	60
frother rate	ml/min	6	11	16
collector rate	ml/min	6	11	16
feed rate	gpm	60	100	140
wash water rate	gpm	20	25	30
aeration rate	cfm	10	16	22

Table 2. Standard conditions used for parametric test plan.

Parameter	Setting
Column Diameter	30 inches
Column Length	26 feet
Wash Water Addition Point	
Upper Ring	3 inches above lip
Lower Ring	16.5 inches below lip
Generator Length	17 inches
Generator Diameter	2 inches
Number of Generators	3
Frother Type	Betz 1012
Collector Type	#2 Diesel
Baffles	None

required statistical computations and regressions. A Box-and-Behnken experimental design was selected for use in the present work. This type of design is well suited for the study of flotation systems since it:

- 1) provides a means of measuring the contribution of each parameter to the given response,
- 2) allows the influence of joint interactions between the various test parameters to be estimated, and
- 3) minimizes the number of test runs necessary to complete the test program.

The specific tests required by the Box-and-Behnken design are summarized in Table 3. The statistical design requires that 54 individual flotation tests be conducted in order to quantify

Table 3. Parametric test plan utilized in the in-plant optimization studies.

Test No.	Feed Rate	Wash Water Rate	Aeration Rate	Frother Dosage	Collector Dosage	Froth Height
42	1	0	-1	0	0	-1
33	0	-1	0	0	-1	-1
24	0	0	1	1	0	1
29	-1	0	0	-1	1	0
4	1	1	0	-1	0	0
35	0	-1	0	0	1	-1
20	0	0	1	1	0	-1
49	0	0	0	0	0	0
3	-1	1	0	-1	0	0
21	0	0	-1	-1	0	1
17	0	0	-1	-1	0	-1
47	-1	0	1	0	0	1
16	0	1	1	0	1	0
5	-1	-1	0	1	0	0
6	1	-1	0	1	0	0
9	0	-1	-1	0	-1	0
28	1	0	0	1	-1	0
45	-1	0	-1	0	0	1
54	0	0	0	0	0	0
51	0	0	0	0	0	0
43	-1	0	1	0	0	-1
52	0	0	0	0	0	0
31	-1	0	0	1	1	0
44	1	0	1	0	0	-1
36	0	1	0	0	1	-1
50	0	0	0	0	0	0
11	0	-1	1	0	-1	0

Test No.	Feed Rate	Wash Water Rate	Aeration Rate	Frother Dosage	Collector Dosage	Froth Height
14	0	1	-1	0	1	0
13	0	-1	-1	0	1	0
39	0	-1	0	0	0	1
30	1	0	0	-1	1	0
22	0	0	1	-1	0	1
7	-1	1	0	1	0	0
27	-1	0	0	1	-1	0
37	0	-1	0	0	-1	1
53	0	0	0	0	0	0
38	0	1	0	0	-1	1
48	1	0	1	0	0	1
12	0	1	1	0	-1	0
18	0	0	1	-1	0	-1
10	0	1	-1	0	-1	0
25	-1	0	0	-1	-1	0
19	0	0	-1	1	0	-1
8	1	1	0	1	0	0
46	1	0	-1	0	0	1
15	0	-1	1	0	1	0
41	-1	0	-1	0	0	-1
34	0	1	0	0	-1	-1
2	1	-1	0	-1	0	0
26	1	0	0	-1	-1	0
32	1	0	0	1	1	0
23	0	0	-1	1	0	1
40	0	1	0	0	1	1
1	-1	-1	0	-1	0	0

the effects of the 6 specified test parameters. The specific test levels utilized in the design were selected using the exploratory test results as a guideline. All tests were conducted in random order to minimize experimental bias, and the results were analyzed and adjusted using a single-node material balance program to produce a consistent set of results prior to proceeding to the next step. In most cases, only minor adjustments to the experimental data were required, indicating that the measured assay values were reliable.

Parametric Test Overview: The results obtained from the parametric test work are summarized in Table 4. In order to obtain a consistent set of experimental data, all test values were analyzed and adjusted using a single-node material balance program.

Baseline Tests: As indicated in Tables 3 and 4, six replicate "baseline" tests were performed at various times throughout the test program. These replicate tests were required so that the amount of pure experimental error could be assessed. In the present work, the experimental errors consisted of random errors associated with the testing procedure, data collection, and sample analysis. The yield and energy recovery data obtained from these replicate tests are plotted in Figure 20. As shown, the variation within the data set for the first four replicate tests is within the range that can be expected for in-plant studies. These differences can be accounted for by the natural variations in the system (e.g., slight changes in the feed material, surges in the reagents pumps or feed rate, inaccuracies in reading metering gauges, etc.). Figure 20 also indicates that there is a slight difference in the data from replicate tests 5 and 6 as compared to the first four replicate tests. Two possibilities can be given for this

Table 4. Test results obtained during the parametric testing.

ID	Feed Ash	Prod Ash	Tail Ash	Feed Sulfur	Prod Sulf	Reject Sulfur	Feed Btu	Prod Btu	Tail Btu	Prod Yield	Comb Recvry	Ash Recvry	Btu Recvry	Ash Reject	Sulfur Reject	Comb SE	Total SE
42	61.03	9.46	74.04	0.21	0.50	0.14	4836	13522	2646	20.15	46.80	3.12	56.32	96.88	53.24	43.68	9.56
33	59.97	13.23	79.92	0.21	0.45	0.11	4959	12953	1546	29.91	64.84	6.60	78.14	93.40	36.71	58.24	14.85
24	60.41	8.70	72.78	0.21	0.47	0.15	4962	13564	2904	19.30	44.52	2.78	52.76	97.22	57.64	41.74	10.40
29	61.50	7.85	76.66	0.25	0.50	0.18	4734	13831	2165	22.03	52.73	2.81	64.36	97.19	56.14	49.92	20.50
4	61.74	6.93	70.28	0.25	0.47	0.21	4708	13994	3262	13.48	32.79	1.51	40.07	98.49	72.68	31.28	12.74
35	63.29	13.22	78.15	0.25	0.50	0.18	4383	12930	1847	22.89	54.10	4.78	67.51	95.22	55.52	49.32	23.03
20	62.34	15.97	73.38	0.21	0.49	0.14	4482	12460	2583	19.23	42.91	4.93	53.46	95.07	53.85	37.98	7.30
49	60.61	8.99	71.79	0.24	0.45	0.20	4918	13668	3023	17.80	41.13	2.64	49.47	97.36	68.50	38.49	17.97
3	59.37	6.97	67.18	0.26	0.50	0.22	5090	13934	3771	12.97	29.70	1.52	35.51	98.48	73.64	28.18	9.15
21	58.92	6.89	62.53	0.23	0.42	0.22	5148	14000	4533	6.49	14.71	0.76	17.65	99.24	89.45	13.95	7.09
17	58.82	8.19	68.15	0.25	0.46	0.21	5177	13777	3592	15.56	34.69	2.17	41.41	97.83	70.93	32.52	12.33
47	58.87	10.81	83.51	0.25	0.48	0.13	5211	13348	1040	33.89	73.50	6.22	86.82	93.78	34.38	67.27	21.20
16	57.79	11.12	79.86	0.28	0.50	0.18	5494	13237	1832	32.11	67.61	6.18	77.35	93.82	43.65	61.43	21.00
5	59.32	13.74	82.55	0.23	0.46	0.12	5011	12813	1035	33.76	71.59	7.82	86.31	92.18	34.56	63.77	20.87
6	58.46	9.07	75.44	0.26	0.48	0.18	5246	13566	2385	25.58	56.00	3.97	66.16	96.03	51.52	52.03	17.68
9	59.26	7.60	74.53	0.24	0.46	0.17	5125	13858	2543	22.81	51.75	2.93	61.69	97.07	54.67	48.82	16.36
28	56.32	8.95	66.78	0.33	0.48	0.29	5724	13528	4001	16.09	37.70	2.87	42.74	97.13	71.98	34.83	14.73
45	63.65	8.00	72.31	0.20	0.47	0.16	4298	13758	2825	13.47	34.08	1.69	43.10	98.31	69.23	32.39	12.33
54	65.68	11.45	72.94	0.19	0.46	0.16	3867	13221	2613	11.81	30.46	2.06	40.37	97.94	74.27	28.40	14.64
51	62.76	10.78	72.60	0.22	0.47	0.17	4381	13350	2683	15.92	38.13	2.73	48.51	97.27	64.97	35.40	13.48
43	62.04	27.80	77.35	0.22	0.40	0.14	4644	10540	2007	30.90	58.77	13.85	70.13	86.15	43.97	44.92	14.10
52	64.17	11.02	70.65	0.20	0.42	0.17	4134	13257	3023	10.87	26.99	1.87	34.85	98.13	75.76	25.12	10.61
31	63.62	17.68	74.80	0.21	0.43	0.16	4253	12234	2311	19.57	44.29	5.44	56.30	94.56	61.28	38.85	17.58
44	63.24	23.05	76.53	0.21	0.39	0.16	4372	11306	2079	24.85	52.02	9.06	64.26	90.94	57.26	42.96	21.52
36	62.45	23.08	79.45	0.23	0.41	0.16	4615	11287	1735	30.16	61.78	11.15	73.75	88.85	48.59	50.63	22.34
50	64.84	8.46	76.30	0.22	0.54	0.16	4179	13660	2251	16.89	43.98	2.20	55.22	97.80	60.44	41.78	15.66
11	65.33	12.90	79.14	0.23	0.57	0.14	4132	13000	1796	20.85	52.38	4.12	65.58	95.88	48.18	48.26	13.76
14	64.00	7.84	75.53	0.25	0.60	0.18	4356	13847	2408	17.03	43.61	2.09	54.15	97.91	59.74	41.52	13.88
13	64.17	7.89	73.81	0.24	0.61	0.18	4300	13750	2681	14.62	37.59	1.80	46.76	98.20	64.03	35.80	10.79
39	63.25	11.45	71.11	0.24	0.57	0.19	4205	13211	2838	13.17	31.74	2.38	41.39	97.62	68.74	29.36	10.12
30	69.37	8.98	78.86	0.20	0.60	0.14	3479	13647	1881	13.58	40.36	1.76	53.26	98.24	60.49	38.60	13.75
22	65.68	11.34	67.16	0.23	0.55	0.22	4046	13238	3795	2.65	6.85	0.46	8.68	99.54	93.12	6.39	1.79
7	66.98	9.69	87.30	0.21	0.56	0.09	3881	13082	618	26.18	71.61	3.79	88.25	96.21	31.64	67.82	19.88
27	65.76	13.29	88.30	0.26	0.65	0.09	4216	12935	470	30.05	76.10	6.07	92.19	93.93	24.21	70.02	16.40
37	65.95	9.53	76.65	0.23	0.57	0.16	3975	13573	2155	15.94	42.36	2.30	54.43	97.70	58.48	40.05	12.91
53	64.46	8.36	80.42	0.24	0.60	0.14	4418	14191	1638	22.15	57.11	2.87	71.13	97.13	45.41	54.24	16.54
38	63.94	12.68	72.96	0.22	0.57	0.16	4491	13078	2975	14.99	36.30	2.97	43.66	97.03	61.82	33.33	5.48
48	62.29	9.53	74.48	0.26	0.57	0.19	4755	13539	2725	18.77	45.03	2.87	53.44	97.13	59.36	42.16	12.80
12	72.63	17.13	85.09	0.18	0.57	0.10	2832	12238	721	18.33	55.51	4.32	79.22	95.68	45.37	51.19	24.59
18	72.76	12.66	82.87	0.17	0.60	0.10	2894	13019	1190	4.40	46.17	2.51	64.77	97.49	50.35	43.66	15.12
10	72.99	10.61	81.82	0.17	0.61	0.10	2799	13372	1304	12.40	41.04	1.80	59.22	98.20	51.53	39.24	10.75
25	72.82	9.29	79.23	0.17	0.60	0.12	2874	13556	1796	9.17	30.59	1.17	43.22	98.83	64.12	29.42	7.34
19	73.24	13.43	84.17	0.17	0.60	0.09	2753	12884	901	15.45	49.98	2.83	72.31	97.17	44.76	47.15	17.07
8	73.12	11.25	80.55	0.17	0.59	0.12	2684	13245	1417	10.72	35.40	1.65	52.90	98.35	63.02	33.75	15.92
46	70.99	8.57	75.17	0.18	0.58	0.15	3100	13720	2389	6.28	19.78	0.76	27.77	99.24	78.10	19.02	5.87
15	60.79	14.56	79.39	0.25	0.52	0.14	4870	12741	1701	28.69	62.32	6.87	75.06	93.13	39.93	55.65	15.00
41	58.74	15.45	79.80	0.26	0.53	0.13	4978	12625	1258	32.73	67.06	8.61	83.00	91.39	33.64	58.46	16.64
34	60.47	11.85	79.28	0.25	0.54	0.13	4736	13188	1485	27.90	62.21	5.47	77.68	94.53	37.49	56.74	15.17
2	59.99	8.28	72.96	0.25	0.54	0.17	4747	13527	2544	20.05	45.97	2.77	57.14	97.23	54.36	43.20	11.51
26	63.36	7.71	74.88	0.25	0.57	0.18	4434	13651	2526	17.15	43.20	2.09	52.80	97.91	59.65	41.11	12.46
32	64.20	9.96	80.31	0.23	0.55	0.14	4288	13521	1547	22.90	57.59	3.55	72.19	96.45	46.93	54.04	19.12
23	63.93	8.75	80.61	0.23	0.54	0.13	4334	13418	1589	23.21	58.72	3.18	71.85	96.82	43.40	55.54	15.26
40	63.53	9.73	80.46	0.24	0.56	0.14	4464	13493	1623	23.94	59.25	3.67	72.34	96.33	44.37	55.58	16.71
1	63.71	10.20	81.93	0.24	0.57	0.13	4314	13411	1217	25.40	62.85	4.07	78.96	95.93	40.41	58.79	19.37

Figure 20. Yield and energy recovery obtained for each of the replicate tests conducted throughout the parametric testing program.

inconsistency. First, during "miners vacation," detailed maintenance was performed on the plant. The maintenance included rebuilding and replacing several of the classifying cyclones in the circuit ahead of the test column. Since the feed material to the column comes from the cyclone overflow, the modifications performed may have changed the characteristics of the feed material. Second, the feed to the column for the first four replicate tests came from a single cyclone. This was done to reduce the variations in the feed material. However, this cyclone was removed during the maintenance program. Therefore, the feed to the fifth and sixth replicate tests came from a bank of cyclones.

Even though changes to the plant introduced additional variation, the estimated standard deviations were reasonable. The estimated standard deviations for each of the assays determined in the present work are tabulated in Table 5. The relatively low values indicate that the test data acquired from the parametric testing program are reliable and reproducible. It should be noted that the product assays appear to be the most reliable, while the reject assays are the least dependable. This result was not unexpected since the reject stream contains a low concentration of solids and a disproportionate amount of very fine clay particles.

Performance Overview: The effects of the various operating conditions on the recovery and ash rejection relationship are plotted in Figure 21 for each of the tests conducted in the

Table 5. Estimated values of standard deviation for various assays used in the parametric test work.

Component	Estimated Standard Deviation
Yield	4.32
Product Ash (%)	1.39
Reject Ash (%)	3.82
Feed Ash (%)	1.70
Product Sulfur (%)	0.15
Reject Sulfur (%)	0.12
Feed Sulfur (%)	0.07
Product Btu	365
Reject Btu	513
Feed Btu	362

Figure 21. Btu recovery and combustible recovery as a function of ash rejection for all the test conditions examined in the parametric study.

parametric study. For comparison, both the values of energy (i.e., Btu) recovery and combustible recovery have been plotted in the figure. Although there is a considerable degree of scatter among the various test points, most of the points tend to group along a single grade-recovery curve. The separation curve indicates that very high rejections of ash can be obtained with this coal. At the desired market ash content of 10%, a combustible recovery of over 60% and an ash rejection of more than 93% were attainable using the microbubble flotation column. The high ash rejections can be attributed to the high concentration of fine clays in the feed stream, which are readily rejected by the microbubble flotation column process. It should also be noted that, as with most coals, the energy

recoveries tend to fall slightly above the combustible recoveries for the same level of ash rejection for this coal.

Figure 22 shows the effects of the various operating conditions on recovery and sulfur rejection. In contrast to the ash rejection, an increase in the rejection of sulfur was only possible by sharply decreasing the recovery. This result was expected since the majority of the sulfur in the feed material is associated with the organic fraction of the coal. The slight upward bend in the recovery-sulfur rejection curve does, however, indicate that flotation produced a slight improvement in coal quality.

The effects of the operating parameters on separation efficiency are demonstrated in Figures 23 and 24. Two different separation efficiencies have been calculated, one based on

Figure 22. Btu recovery and combustible recovery as a function of total sulfur rejection for all the test conditions examined in the parametric study.

Figure 23. Combustible separation efficiency and overall separation efficiency as a function of ash rejection for all the test conditions examined in the parametric study.

the separation of combustibles from ash and the other based on the overall separation of energy and sulfur. Combustible efficiency (SE_{comb}) has been calculated using the expression:

$$SE_{comb} = 100Y \left(\frac{100 - A_p}{100 - A_f} - \frac{A_r}{A_f} \right) \quad [2]$$

in which Y is the product yield, and A_p , A_r and A_f are the ash contents of the product, reject and feed streams, respectively. The energy-sulfur separation efficiency ($SE_{overall}$) was calculated from:

Figure 24. Combustible separation efficiency and overall separation efficiency as a function of total sulfur rejection for all the test conditions examined in the parametric study.

$$SE_{overall} = Y \frac{BTU_p}{BTU_f} + (100-Y) \frac{S_r}{S_f} - 100 \quad [3]$$

in which BTU_p and BTU_f are the respective calorific (BTU) values for the product and reject streams, and S_r and S_f are the respective sulfur contents of the reject and feed streams. A more appropriate form of this equation would utilize pyritic sulfur in place of total sulfur, but those assays were not determined for this study.

Figure 23 shows that most of the separation efficiency values fall along two distinct curves. In both cases, however, a maximum separation efficiency could be obtained at an ash rejection of approximately 95%. This value appears to be independent of whether the separation efficiency was calculated on a combustible or overall basis. This level of ash

rejection corresponds to the linear portion (above 95% ash rejection) in the recovery-ash rejection curve shown in Figure 21. Therefore, it can be concluded that the maximum separation efficiency occurs at the point just before the large deterioration in yield. In the present work, the maximum separation efficiency-ash rejection relationship appears to be a function of the coal characteristics. As a result, various combinations of operating conditions can be utilized to obtain the same maximum separation efficiency.

Figure 24 shows the separation efficiency values calculated for the various tests as a function of sulfur rejection. As before, most of the points fall along two distinct curves. However, Figure 24 shows that as sulfur rejection increases, both SE_{comb} and $SE_{overall}$ decrease. This finding indicates that the sulfur is intimately associated with the coal and that the only way to reject more sulfur is to simultaneously recover less coal. This phenomenon is demonstrated more clearly in Figure 25, in which sulfur rejection has been plotted as a function of ash rejection. As shown, there is a distinct relationship between ash rejection and sulfur rejection. If both sulfur and ash were rejected equally, the points should fall along the dashed line shown in the figure. Since this is clearly not the case, this plot once again demonstrates that the ash-bearing components in this coal are more readily rejected than the sulfur-bearing components (i.e., the sulfur is more closely associated with the organic fractions in the coal). The data plotted in Figure 25 suggest that the best separation point for this particular coal would be at an ash rejection of 92% and a sulfur rejection of 30%.

Although the experimental test program was carried out over a wide range of operating conditions, the performance curves shown in Figures 21-24 indicate that most of the data points fall roughly along a single grade-recovery curve. In fact, a close inspection

Figure 25. Relationship between ash rejection and total sulfur rejection for tests results obtained during the parametric study.

of the test data indicates that a great deal of the experimental scatter can be attributed to the tests in which the bias flow rate (i.e., flow rate of wash water downward through the stabilized froth phase) was affected by the test variables. It is now believed that when a flotation separation is made over a range of operating conditions, only those parameters that can alter entrainment (i.e., the hydraulic carry-over of feed water into the product launder) are capable of substantially impacting the grade-recovery curve for a given sample. Therefore, the grade-recovery relationship obtained from a properly operated flotation column should be primarily determined by the characteristic nature of the coal sample, i.e., the degree of liberation and hydrophobicity of the various components in the feed stream. It must be stressed, however, that this general conclusion holds true only if the wash water that

is added to the column is effective in preventing entrainment. Changes in any of the operational parameters that would produce a change in the bias flow rate could produce a sharp change in the performance of the column.

Statistical Data Analysis and Response Surface Development: The assay values were also analyzed using the DESIGN-EXPERT statistical data analysis program. The overall objective of this effort was to develop an empirical relationship between the various operating parameters (i.e., feed rate, wash water, etc.) and a variety of response, or dependent, variables (e.g., recovery). This goal was accomplished via the following steps:

- 1) **Data Analysis** - After the specified experimental data were collected, the response data were entered into the DESIGN-EXPERT software package. The data analysis was an iterative process since, in most cases, several analyses were required to obtain a suitable response surface. When deemed necessary, data transformations were conducted in order to obtain the response surface that best described the experimental data. In the present work, either no transformation or a log transformation was found to provide the best fits for the experimental data. After an appropriate transformation and response surface were selected, the initial model fitting was performed by the DESIGN-EXPERT software. The available models included standard linear, quadratic and cubic models. After selecting an appropriate model, a variety of statistical routines were executed to identify the goodness-of-fit. For all runs, the values of regression coefficients, standard errors, variances, t-tests, etc., were determined as means of quantifying the statistical significance of each of the coefficients in the model.

2) Response Surface Plotting - After a reasonable mathematical model of the desired response was analyzed in light of the various operational parameters, the resultant response surface was plotted using a surface contour program. When combined with the modeling expressions, these plots provide the final product from the parametric test work. The influence of key operating parameters and the joint interaction of various parameters on the process performance can be visualized from the response surface plots.

The following performance indicators have been analyzed using the aforementioned procedures:

- 1) energy recovery,
- 2) product ash,
- 3) total sulfur rejection, and
- 4) combustible separation efficiency.

A summary of the statistical data analysis computations is provided in Appendix 5 for each of the performance indicators. Comparisons between the results predicted by the modeling exercise and results obtained from the experimental measurements are shown in Figures 26-29. In general, very good correlations were obtained between the predictions gained from the empirical model predictions and the experimental test results.

Appendix 6 provides the response surface plots for each of the four performance indicators. Because of the relatively large amount of response data contained in Appendices 5 and 6, it is not practical within this report to discuss the wealth of information that can be obtained from the parametric test program. However, because separation efficiency is important in establishing the trade-off between grade and recovery, a detailed examination of

Figure 26. Comparison of experimental results with predictions made by the empirical model developed to describe energy recovery as a function of the various operating parameters.

these response surfaces should provide information about the appropriate level for each of the operating parameters (gas rate, frother dosage, collector dosage, etc.).

A number of significant trends can be observed from an analysis of the separation efficiency response curves. These include:

- 1) The height of the stabilized froth zone appears to have only a limited impact on the separation efficiency, except under conditions of high feed rates. Under this condition, the separation efficiency drops rapidly due to a sharp decrease in overall recovery.
- 2) Higher gas flow rates appear to have a beneficial effect on separation efficiency for all cases. However, the response surface plots appear to suggest

Figure 27. Comparison of experimental results with predictions made by the empirical model developed to describe product ash content as a function of the various operating parameters.

that higher frother dosages may be required when using the high gas rates, in order to obtain the highest possible separation efficiencies. This result can probably be attributed to the fact that large amounts of bubble surface area are generated at the higher gas rates. Higher frother dosages could then be required to maintain a small bubble size.

- 3) Higher gas rates generally dictate the use of larger wash water flow rates. At the higher gas rates, more water is carried into the froth launder by the increased flow of air bubbles. In order to maintain the desired bias flow rate for removing entrained particles, additional wash water must be added to compensate for water lost at higher gas rates.

Figure 28. Comparison of experimental results with predictions made by the empirical model developed to describe product sulfur rejection as a function of the various operating parameters.

- 4) Separation efficiency was found to increase at the higher frother dosages. In general, too low a frother dosage resulted in the production of large bubbles and a loss of recovery (which reduced the separation efficiency). Low frother dosages also contributed to a decrease in froth stability, which also adversely affected the flotation recovery. On the other hand, the increased production of small bubbles at higher frother dosages enhanced the stability of the froth. It should be noted, however, that if the frother dosage exceeds a critical amount, too stable a froth can be produced. As indicated previously, this condition results in an excessive flow of water into the product stream and, in many cases, a decrease in the separation efficiency.

Figure 29. Comparison of experimental results with predictions made by the empirical model developed to describe separation efficiency as a function of the various operating parameters.

Task 2.4 Design Evaluation/Modification

2.4.a - Evaluate Column Design Features

A number of key design features of the microbubble flotation column were evaluated in order to determine whether the design was appropriate for full-scale industrial operation. These included launder design, frother injection point, wash-water addition point and mixing conditions within both the 30-inch and 8-foot diameter columns. Additionally, the scale-up and performance relationships that describe the operating characteristics of the bubble generation circuit were also verified.

Launder Design: One concern regarding the original column design was whether the froth product would flow unrestricted from the launder through the product collection line. High-pressure, low-flow water sprays were mounted just above the launder to break the froth should problems arise. In addition, a very smooth ceramic coating was used in the launder construction to help in product removal. After conducting a wide range of tests, it was found that the ceramic coating was sufficiently slick to prevent hold-up of the froth and that little or no additional water was required in the launder to break the froth.

However, froth handling problems were encountered with the 8-foot cell. Although the froth flowed freely through the launder, build-up tended to occur at the point of discharge. This was probably a result of either the product line being too small in diameter to handle the large flow of froth, or the vertical drop being very short relative to the total span of the pipe. The latter problem is a physical restriction of the plant due to the location of the column with respect to the feed distribution box for the screen bowl centrifuges.

Frother Addition Systems: As discussed in the original project work plan, frother was to be added in several different locations in order to determine the optimum addition point. The results of these tests are shown in Table 6. It can be seen that the best result has been obtained when the frother is added directly into the bubble generation circuit. The worst result occurred when the frother was added with the wash water. In this instance, the decrease in recovery was probably a result of a portion of the frother being lost with the wash water that reports to the column product. Because the column wash water splits after it is introduced to the column, the portion of the frother associated with the water reporting to the column product will be not be available for bubble generation.

Table 6. Results of frother addition point tests.

Test No.	Addition Point	Product Ash (%)	Combustible Recovery (%)
1	Pump (10)	8.38	67.49
2	Feed (10)	7.89	64.53
3	Pump/Feed (5/5)	9.65	63.22
4	Pump/Wash Water (5/5)	9.42	61.47
5	Wash Water (10)	7.72	49.99

Note: (#) represents the flow of frother in ml/min.

Wash Water Addition System: A similar series of tests was conducted for the wash water addition point. As mentioned above, the wash water will split in the column with a certain portion reporting to the column product and the remainder to the tailings. The percentage of the total flow reporting to the column tailings, known as the bias factor, is controlled, in part, by the linear position along the column axis of the wash water distributor. For example, if the water distributor is located close to the cell lip, the majority of the wash water will report to the column product. As the distributor is lowered deeper into the cell, more of the water will report to the column tailings. As a result, the froth percent solids will increase and froth will tend to become unstable. Under extreme conditions (i.e., coarse or weakly hydrophobic coal) the froth structure may begin to collapse. As such conditions are encountered the column recovery will begin to decline. This point is illustrated in Table 7. It can be seen that as the water distributor is lowered from 6.5 to 26.5 inches, the combustible recovery drops nearly 10 percent.

Table 7. Results of wash water addition point tests.

Test No.	Addition Point	Product Ash (%)	Combustible Recovery (%)
1	6.5"	9.79	61.93
2	16.5"	10.93	53.08
3	26.5"	9.64	52.33

Three different wash water distributors were constructed and tested in the 30-inch column. These three designs are shown in Figure 30. As a result of this test work, it was found that the original design (Figure 30a) did not provide sufficient distribution of wash water across the top of the froth. A second distributor with more wash water "legs" (Figure 30b) was constructed and installed to provide better wash water distribution; however, this distributor presented a new problem. In a normal laboratory test, the wash water injection point is usually 1-3 inches below the froth surface. This allows the portion of froth above the wash water injection point to dewater slightly before it leaves the column, and it tends to allow more water to pass down through the froth for improved cleaning action.

However, on larger diameter columns, the center of the froth tends to drain too much and collapse when the wash water distributor is positioned below the top of the froth. When the wash water distributor is raised high enough to prevent the collapse of the center of the froth, the wash water becomes less effective in removing entrained mineral matter.

One industrial column manufacturer has tried to solve this problem by introducing a patented froth crowder into the center of the column. This device is simply an inverted cone which directs material to the cell overflow lip. Unfortunately, the presence of the froth

Figure 30. Schematic showing the different wash water distributor designs evaluated during the testing of the 30-inch microbubble flotation column.

crowder tends to reduce the column carrying capacity, since carrying capacity is directly proportional to the available cross-sectional area. As a result, a twin ring design (Figure 30c) was developed to maximize the washing action while improving the stability of the center of the froth. In this design, the center ring was positioned just above the froth to maintain a very wet and stable froth in this region, while the outer ring was positioned just below the cell lip. This arrangement allowed the froth to drain slightly just before it spilled over the cell lip. Also, the wash water split could be easily altered by adjusting the depth of the outer ring. For example, if the outer ring were positioned too deep, less wash water reported to the product, the product solids content increased and better washing action was

achieved. However, the resultant bubble coalescence in the froth reduced the amount of available bubble surface area for particle attachment and decreased the overall product yield. If the outer ring was positioned too high, more wash water reported to the product and improved froth stability was observed. However, this decreased the effectiveness of the wash water in removing entrained particles. Thus, by properly adjusting the depth of the outer ring, an optimum balance between yield and grade could be achieved. Because of the excellent results and flexibility provided by this system, a similar type of wash water distribution system was designed and installed on the full-scale column.

Other Distribution Systems: The other distribution systems in the column were found to operate quite well. The feed slurry seemed to distribute within just a few feet of depth within the column. The turbulence caused by the bubble generators near the bottom of the column also provided an excellent method for properly distributing the air across the column cross-section.

Mixing Conditions: The three most influential factors in column scale-up are the rate of flotation, particle retention time and axial dispersion (mixing) conditions within the column. Although the flotation rate constant and retention time have been quantified for a wide range of conditions, mixing conditions in large diameter columns have not been thoroughly examined.

Typically, mixing in a vessel is quantified by the axial dispersion coefficient. The axial dispersion coefficient is related to the non-dimensional Peclet number as follows:

$$P_e = \frac{\mu L}{D} \quad [4]$$

In this form, a Peclet number of zero represents perfectly mixed conditions, while a Peclet number approaching infinity represents an ideal plug-flow reactor. The Peclet number is determined from a residence time distribution (RTD) test conducted in an operating cell. The RTD curve represents the measured response of a slug of tracer as it makes its way through the vessel. The tracer material is usually an aliquot of salt solution (KCl in water) which is injected with the vessel feed. The corresponding change in conductivity of the column tailings is indicative of the mixing conditions within the cell.

In this case, conductivity changes were determined with an in-line conductivity probe located in the column tailings discharge line. This provided quantitative information on the mixing conditions within the column collection zone. It was also necessary to determine the fractional air hold-up during the test period. This was accomplished by means of the differential pressure measurements described previously. A schematic diagram of the column arrangement is shown in Figure 31.

RTD studies were conducted for both the 30-inch and 8-foot diameter units. A typical normalized RTD is shown in Figure 32. The data have been corrected for background noise and normalized with respect to the total area under the initial response curve. The mean residence time, τ_m , can be calculated from the normalized RTD using the following equation:

$$\tau_m = \frac{\sum C_i t_i \Delta t}{\sum C_i \Delta t} \quad [5]$$

Figure 31. Schematic diagram of experimental set-up for RTD studies.

where C_i represents the concentration (or conductivity) at time t_i . The Peclet number can then be determined by a sum-of-squares fit to the cumulative version of the normalized response curve according to the following equation:

$$\frac{C}{C_o} = \frac{1}{2} \left(1 - \operatorname{erf} \left[\frac{1}{2} \sqrt{P_e} \frac{1 - t/\tau_m}{t/\tau_m} \right] \right) \quad [6]$$

The Peclet number and retention time determined for both the 30-inch and 8-foot diameter columns are shown in Table 8. Also shown in Table 8 are the predicted Peclet numbers. These values were determined based on the following relationship:

30-minute RTD Test

Figure 32. Typical normalized RTD for the 30-inch column.

$$P_e = 0.7 \left[\left(\frac{L}{D} \right)^{0.63} \left(\frac{\mu_l}{V_s} \right)^{0.50} \right] \quad [7]$$

Table 8. Results of RTD testing.

	Measured Retention Time	Calculated Retention Time	Measured Pe	Predicted Pe
30-inch	10.2	9.72	1.94	2.52
8-foot	4.02	4.31	2.21	1.39

where L and D are column length and diameter, respectively, μ_i is interstitial liquid velocity and V_g is superficial gas rate. The derivation of equation 7 is based on a dimensional analysis procedure and has been described elsewhere (Mankosa *et al.* 1991).

It can be seen from Table 8 that the measured and calculated retention times correspond quite closely. This provides a good indication of the relative accuracy of the RTD test. In other words, if the measure retention time does not closely correspond to the calculated value, the RTD is probably not accurate. It should also be noted that the measured and predicted values of Pe are also quite similar. This is particularly encouraging since only a limited amount of data is available for large-scale industrial columns. This result is shown in Figure 33 along with previously determined laboratory results. It can be seen that the data collected for both the 30-inch and 8-foot diameter columns correlates well with the laboratory results. This implies that the mixing conditions in large-scale columns can be predicted based on column geometry and flow conditions.

Bubble Generation Circuit: Performance of the bubble generation circuit was evaluated by measuring the fractional air content within the column recovery zone for various gas flow rates, number of mixers and frother concentrations. Tests were conducted using 2, 3, and 4 generators over a range of gas flow rates from 0 to 50 SCFM. Tests were attempted using 5 and 6 generators; however, under these conditions the bubble generation pump would overload and trip its circuit breaker. This is a result of the low back pressure on the pump when 5 or more generators are used. Therefore, it was not possible to collect data for more than 4 bubble generators.

Figure 33. Measured versus predicted values of Peclet number.

The air fraction within the column was determined by means of differential pressure. The pressure measurements were collected using Honeywell pressure transducers. By determining the differential pressure the fractional air hold-up can be determined as follows:

$$\epsilon = 1 - \frac{\Delta P}{\Delta H} \quad [8]$$

where ΔP is the measured differential pressure in inches of water and ΔH is the separation distance of the transducers in inches.

The results of air fraction studies for 2, 3 and 4 in-line mixers in the absence of frother are shown in Figure 34. It can be seen that the fractional air hold-up in the cell

Figure 34. Fractional air content as a function of gas flow rate for 2, 3 and 4 bubble generators in the absence of frother.

increases from 0 to 20 percent over a range of 0 to 45 CFM. It is interesting to note that there is little difference in performance in regards to the number of bubble generators until a gas flow rate of approximately 25 CFM is exceeded. At higher gas flow rates, the fractional air hold-up increases with the number of generators. The increase in air fraction is due to the larger total volume flow of liquid through the system as a result of the reduced back-pressure on the bubble generation pump. This provides a larger volume of liquid for dispersing the same quantity of air. Therefore, the bubbles are not as densely packed and the amount of coalescence is reduced. This results in an overall higher air fraction within the column.

The change in volume flow is further illustrated by Figure 35, which shows the total system flow and the flow per generator as a function of the number of mixers. It can be seen that by increasing the number of generators from 2 to 4 the total flow through the system increases from 200 to nearly 400 GPM. The flow through each generator, however, remains nearly constant. This indicates that bubble size does not change significantly as the number of generators is increased.

The effect of surfactant addition on air fraction is illustrated in Figure 36. In this instance, the fractional air hold-up within the column was increased by more than 75% by adjusting the frother concentration within the cell to 3×10^{-5} M Betz 1012. It is also interesting to note that an upper limit of approximately 30 CFM was encountered. Beyond this limit, flooding conditions were observed. Such conditions are a result of the higher air fractions and smaller bubble sizes created by the addition of frother. Under these conditions, bubbles enter the column more quickly than they are capable of rising out of the cell. This enhances the degree of coalescence, resulting in the formation of large slugs of air. At this

Figure 35. Total volumetric flow rate and flow per generator as a function of the total number of bubble generators.

point, the column is no longer operating in the bubbly-flow regime, and cell performance drastically deteriorates.

It is also interesting to note that the highest air fraction within the cell was obtained with three in-line mixers, as opposed to four in the case of no frother addition. This is a result of the decrease in bubble size provided by the addition of surfactant. In this case, as the total flow through the system increases, the amount of air which is recirculated also increases due to the low bubble rise velocity. This results in deterioration of the pump performance and the total system flow decreases. Therefore, an optimum number of bubble generators exists for a given set of operating conditions.

Figure 36. Fractional air content as a function of gas flow rate for 2, 3 and 4 bubble generators with $3 \times 10^{-5} \text{ M}$ Betz 1012.

Using a population balance model of the air phase within the column, the average bubble size within the cell was back-calculated from the measured air fraction and the gas flow rate. These results are shown in Figures 37 and 38 as a function of the gas flow rate through the cell. It can be seen that the average bubble diameter produced in the absence of frother is approximately 1700 microns. This value increases to nearly 2400 microns at gas flow rates in excess of 30 CFM. In the presence of frother, however, the average bubble diameter increases from 500 to 1200 microns over a range of gas flow rates of 0 to 30 CFM. These latter results are representative of the range of bubble sizes which are typically encountered in normal operation.

2.4.b - Measure Wear of Key Components

The major components for which wear is a concern include bubble generators, the centrifugal bubble generation pump, tailing discharge valve, and associated piping. The wear rates of the centrifugal pump, discharge control valve, and associated piping are expected to be in line with that of other similar systems within the plant. As a result, the life expectancy of these components has been well documented by plant personnel and is now believed to be of no great concern. However, because of the tortuous path and relatively high slurry velocity through the bubble generators, it was believed that wear might be of particular concern in these devices. In fact, the original column design called for quick-release couplings so that the generators could be removed, inspected, and replaced if necessary on a routine basis. However, throughout the course of this investigation, examinations of both the 30-inch and 8-foot diameter columns qualitatively indicate that the wear of the generators is

Figure 37. Calculated bubble size as a function of gas flow rate for 2, 3 and 4 bubble generators in the absence of frother.

Figure 38. Calculated bubble size as a function of gas flow rate for 2, 3 and 4 bubble generators with 3×10^{-5} Betz 1012.

not a major concern. Estimates now suggest that the hardened-steel generators will have a life of at least 6-12 months. It should also be noted, however, that microbubble generators can also be cast from wear-resistant urethane. Tests carried out in a separate project have demonstrated that these new wear-resistant generators last at least 4 times longer than the original hardened-steel mixers. In addition, the urethane mixers are nearly 1/3-1/2 the cost of their hardened-steel counterparts.

Task 2.5 Control Systems

As previously described in Section 2.3, both the 30-inch and 8-foot diameter columns were controlled through an Allen-Bradley programmable logic controller. This system provided an automated start-up, shut-down and interlock sequence for all equipment associated with the 8-foot column. The interlock sequence provides a means of selectively removing a single piece of equipment from the automated start/stop sequence. This system provided operators and maintenance personnel with a means of servicing equipment without disrupting column operation. The system also controlled all PID loops and data acquisition for both columns. The listing for the ladder logic program is provided in Appendix 7.

A Panelview plant floor terminal was installed as an operator interface. This station allows the operator limited access to the column for manipulation of reagent dosages and column pulp level. The operator terminal has been programmed to provide a graphic display of the column and all ancillary equipment. The equipment graphic symbols are displayed in either green or red to provide the operator with information about the current state of each unit.

2.5.a - Pulp Level

The pulp level control system was installed and integrated with the PLC control system. A schematic diagram of the current level control system is shown in Figure 39.

This system uses a pressure measurement determined from a Honeywell DP cell as the input

Figure 39. Schematic diagram of column level control system.

to the PID controller. Based on a given set-point, the controller automatically actuates a pneumatic pinch valve in order to maintain a constant level within the cell. This system is capable of maintaining level within ± 1 inch.

2.5.b - Air Hold-Up and Bubble Size Control

In addition to the DP cell used for level control, a second DP cell has been added for the purpose of determining differential pressure within the column recovery zone. Utilizing the two-point measurement, the fractional air hold-up, ϵ_m , can be determined according to equation 8. The fractional air hold-up is used in conjunction with the measured gas and liquid flow rates to calculate the average bubble diameter in the column collection zone. The bubble diameter can be determined from the following differential equations derived from a volumetric air balance around the recovery zone:

$$\frac{de_1}{dt} = [Q_1 e_2 - (Q_1 e_1 + U_1 e_1)]/V_z, \quad [9]$$

$$\frac{de_2}{dt} = [(Q_g + Q_d e_2 + U_1 A e_1) - (Q_1 e_2 + U_2 A e_2)]/V_z, \quad [10]$$

where Q_g and Q_1 represent the gas and tailings flow rates, respectively; Q_d is the difference between the gas and tailings flow rates; U_1 is the bubble hindered rise velocity, and V_z is the theoretical zone volume.

By utilizing a numerical resubstitution technique, the fractional air hold-up that should exist for a predetermined bubble diameter and column flow conditions can be determined. Direct comparison of the calculated air fraction and the measured air fraction provides an error signal from which the new frother addition rate can be determined. This signal is used in conjunction with the standard proportional/integral control algorithm, which is described as follows:

$$m(t) = K_c \left[e + \frac{1}{T_i} \int e \, dt \right] \quad [11]$$

where $m(t)$ is the controller output, K_c is the proportional gain, T_i is the integral time constant and e is the error signal expressed as:

$$e = C_R - c(t) \quad [12]$$

where C_R is controller set-point and $c(t)$ is the measured process variable.

In order to refine the frother control system prior to implementation in the 30-inch cell, preliminary tests, utilizing the above relationships, were conducted in a 2-inch laboratory column. A schematic diagram of the system used for the laboratory tests is shown in Figure 40. The system hardware for the 2-inch cell parallels that installed on the 30-inch cell.

Preliminary results for the case of simple, untuned proportional control are shown in Figure 41. In this case, the objective of the control strategy was to maintain a constant bubble size when a step change in aeration rate was encountered. As expected, a decrease in the column aeration rate resulted in a decrease in the fractional air content. The simulated

Figure 40. Schematic diagram of the laboratory frother control system.

air rate in the process controller was also decreased simultaneously with the column aeration rate, while the bubble diameter was held constant. The new value of fractional air hold-up determined by the simulator was then used as the set-point value, C_R , for the laboratory column control loop. This action resulted in a decrease in the controller output (i.e., reduction in frother addition rate), which reduced the fractional air hold-up in the 2-inch cell. It can also be seen from Figure 41 that an increase in aeration rate resulted in a similar response by the controller. The offset between the measured and calculated values of air fraction are attributed to the fact that only proportional control was used for the laboratory

Figure 41. Results of 2-inch laboratory frother control studies.

cell. This type of offset is characteristic of a controller that utilizes only proportional control.

Based on the encouraging results of this initial lab work, a similar control system was installed and tested on the 30-inch column. In this case, full PI (proportional/integral) control was used in conjunction with the PLC system in order to initiate bubble size control in the 30-inch column. The model equations were loaded directly into the PLC's C language processor. The C language processor operates under a multi-tasking environment, thus allowing for data collection and other process control loops to continue to operate.

Results of the in-plant bubble size control studies are shown in Figure 42. As shown, the 30-inch column responded in a similar fashion to the laboratory study. The step increase

Figure 42. Results of 30-inch in-plant frother control studies.

in column aeration rate resulted in an increased air fraction within the column. In this instance, the air hold-up increased from 20 to nearly 30 percent. The controller responded by decreasing the frother addition rate in order to compensate for this increase. It can be seen that within approximately 20 minutes the column air fraction had returned to normal operating conditions.

This system provides an important degree of stabilizing control to the column. This is particularly important in light of the wide fluctuations in feed volumetric flow rate and percent solids that are encountered in a plant environment. For instance, during the course of one day, the feed percent solids from the classifying cyclone overflow (i.e., column feed) decreased from nearly 7 percent to 3.7 percent. This reduction in percent solids represents a

decrease in solids mass flow rate from 180 tph to 94 tph. The lower solids feed rate results in the net frother addition rate increasing from 0.7 to 1.4 lb/ton in the column flotation circuit. As discussed before, these circumstances result in a dramatic increase in the rate of water recovery to the column froth product. In this instance, if a correction is not made (i.e., increase wash water, decrease aeration rate or decrease frother addition) the product ash can increase significantly beyond the contract specification of 10 percent. Therefore, the frother/bubble size control system adds a degree of stability to the column operation that helps maintain a constant product ash content.

PHASE III - PROTOTYPE TESTING

Task 3.1 Project Planning

3.1.a - Feasibility Study

Prior to initiating this phase of the work, a detailed feasibility study was conducted to determine whether a full-scale prototype of the microbubble flotation column should be installed in the Marrowbone Preparation Plant for recovery of fine coal. The study was conducted jointly by the engineering staff of the Shell Mining Group and by personnel from the Virginia Center for Coal and Minerals Processing. In addition, ICF-Kaiser Engineers provided data related to the structural design of the column and fabrication specifications.

Several meetings were required in order to resolve many of the uncertainties related to the further development, testing and commercialization of this technology. In these meetings, several topics were discussed in regard to the expected performance of the large-scale unit (i.e., recovery, grade and throughput) and specific details concerning the engineering design. This section provides a summary of the test results and engineering calculations that were considered in the detailed analysis of the microbubble column flotation process.

Coal Quality: The first step of the feasibility study was to closely examine the preliminary test data obtained from the 30-inch diameter column tests to determine whether the desired product quality could be obtained at acceptable recoveries. The test data obtained from 2-inch laboratory columns and 6-inch and from 30-inch pilot-scale columns are summarized in Figure 43. Also shown on this figure are the results of a release analysis test which was conducted using a composite sample taken over an extended period of time from

Figure 43. Summary of test results obtained using microbubble flotation columns of various diameters.

the plant classifying cyclone overflow. The release analysis data provide an estimate of the best possible flotation results attainable with this particular sample (Dell, 1953; Dell *et al.*, 1972; Pratten *et al.*, 1989), and the curve is often described as being the flotation equivalent of the washability curve of gravity separations. As shown, nearly the same metallurgical performance, i.e., grade-recovery curve, was achieved in each series of tests. It should also be noted that the various column results are very close to the maximum cleanability predicted by release analysis. In general, it was estimated that when the column was operated properly a combustible recovery of approximately 60% could be achieved while still meeting the target grade of 10% ash or less.

Proposed Flowsheet: Figure 44 shows the flowsheet proposed for the retrofit of the microbubble flotation column into the Marrowbone Preparation Plant. Prior to installation of the column, the -28 mesh material from the preparation plant was fed to multiple banks of classifying cyclones, the 28 x 150 mesh underflow fraction from these cyclones was processed using a fine coal heavy media cyclone circuit, and the overflow was discarded without treatment. At present, it is estimated that the cyclone underflow stream contains 100 tph of fine solids at approximately 4 percent solids (i.e., total flow of 9000 GPM). For the proposed flowsheet, part of the -150 mesh fraction would be passed directly to the microbubble flotation column. The reject from this column would flow by gravity to the

Figure 44. Proposed microbubble flotation column flowsheet for the Marrowbone Preparation Plant.

thickener for water clarification. The clean coal flotation product would be mixed into one of the coarser streams and then dewatered using a screen bowl centrifuge already in operation at the plant.

Column Capacity: One of the major focuses of the feasibility study was to determine whether the microbubble column was capable of producing the desired product quality and recovery at acceptable throughputs. This was an area of particular concern because of the very fine size (-150 mesh) and low solids content (3-5% solids) of the flotation feed from the classifying cyclones. In addition, since this was a high-volume stream (over 9000 gpm of slurry), some questions were raised as to whether an excessive number of columns would be required to handle the large volumetric flow. Therefore, the main goal of this analysis was to provide a preliminary estimate of the capacity of a full-scale column and to estimate the number of full-scale units required to process this entire cyclone overflow stream.

Based on the test results obtained in the 2- and 30-inch pilot-scale columns, the capacity of the full-scale column was calculated using scale-up procedures developed at Virginia Tech. Although the full details of this procedure are too extensive for inclusion in this report, portions of the scale-up calculations are presented below for sake of completeness. Specific details related to the scale-up strategy have been described in the final report submitted to DOE in August, 1990 for a related project entitled "Pilot-Scale Testing of Microbubble Flotation" (DE-AC22-86PC91274).

The first step of the scale-up procedure required that a series of small-scale laboratory tests be conducted until the desired level of performance, i.e., grade and recovery, was obtained. The laboratory tests were conducted in a relatively short column so that carrying

capacity restrictions did not limit throughput, i.e., the column throughput was determined only by the flotation rate. The data collected in these tests became the basis for the scale-up calculations.

After completing the laboratory scale-up tests, two expressions were used to determine the capacity of the full-scale columns. The first of these describes the operation of the column when the capacity is limited by the flotation rate and is given by:

$$V_f = L(1-\epsilon)/\tau_p - V_b \quad [13]$$

where V_f is the superficial feed rate of slurry; L is the column length, ϵ is the fractional air hold-up; τ_p is the mean particle retention time and V_b is the superficial bias flow of wash water. This expression assumes that the flotation rate constant remains unchanged during scale-up, which implies that the superficial gas rate (V_g) and bubble diameter (D_b) should be the same for both the laboratory and full-scale units. This dictated an air flow rate of approximately 160 cfm for the full-scale unit.

The second expression used for determining scale-up capacity is given by:

$$V_f = \frac{4V_g D_p S_p \beta}{Y D_{bf}} \left[\frac{1}{S_f} + \frac{1}{P} - 1 \right] \quad [14]$$

in which V_g is the superficial aeration rate; D_p and S_p are the respective diameter and specific gravity of particles in the froth product; β is the particle packing factor; Y is the product yield by weight; D_{bf} is the bubble size in the froth; S_f is the specific gravity of particles in the feed slurry, and P is the fractional solids content of the feed. This expression represents the restriction on column throughput due to carrying capacity limitations. The carrying capacity

constraint is related to the fact that a larger portion of the bubble surface area becomes covered with particles when more material is fed to the column. At some point, more particles are fed to the column than can be removed by the available bubble surface area. This condition defines the upper limit on the feed rate to the column.

Equations [13] and [14] were used to determine the maximum superficial feed rate that could be processed under the specified conditions. These values were checked using an air fraction model developed at Virginia Tech to ensure that the flooding limit of the column would not be exceeded. Flooding occurs when the superficial velocity of slurry passing down the column exceeds the average rise velocity of the bubbles. If flooding occurs, air enters the column faster than it can rise out, the air fraction in the column rapidly approaches unity, and bubbles are either washed out of the column with the reject or the column begins to "burp" or "slug." In order to verify that the predicted scale-up values would not cause column flooding, the fractional air hold-up was calculated as a function of bubble diameter and gas and liquid flow rates in the column. A system of simultaneous differential equations must be solved to determine the change in fractional air hold-up during scale-up. Using these equations, it was possible to verify that the predicted scale-up flow rates would not violate the flooding limit.

The superficial feed rates calculated from the scale-up procedure were used to predict the expected capacity of the 30-inch and 8-foot diameter columns, as shown in Table 9. Also shown in this table are the average test values obtained using the 30-inch column. As shown, the scale-up predictions are very close to the actual test results. The slight offset between the predicted and measured values can be attributed to a minor decrease in the plant feed percent solids relative to the value used for scale-up, the latter being determined from the 2-inch laboratory column testing.

Table 9. Scale-up predictions for the 30-inch and 8-foot diameter microbubble column flotation cells.

Parameter	2-inch Measured	30-inch Predicted	30-inch measured	8-foot Predicted
Superficial Feed Rate	0.82 cm/s	1.59 cm/s	1.69 cm/s	1.55 cm/s
Volumetric Flow Rate	0.26 gpm	113 gpm	120 gpm	1147 gpm
Feed Mass Flow Rate	6.7 lb/hr	1.44 tph	1.40 tph	14.6 tph
Product Ash	10.3%	10.1%	9.46%	10.1%
Recovery	61.8%	61.8%	61.2%	61.8%

Column Geometry: Equations [13] and [14] were also used to determine the column height necessary to achieve the desired recovery in the full-scale columns. The calculations indicated that a collection zone (i.e., the zone between the feed inlet and bubble injection point) 87 inches long would be needed to provide a sufficiently long retention time to collect the particles. However, extra length had to be added to this value to accommodate the froth zone (i.e., the zone above the wash water inlet) and the stabilized froth or cleaning zone (i.e., the zone between the wash water inlet and the pulp/froth interface of the collection zone). In addition, an allowance was also necessary for the distribution of the bubbles and feed into the column and for the collection of reject material in the bottom of the column. A distance of half the column diameter was estimated for the distribution of each of these streams. A total column height of 24.3 feet was required to satisfy the above criteria. The final design selected for the full-scale column is summarized in Table 10.

Bubble Generation: The most important feature of the microbubble column flotation cell is its novel air sparging system. At Virginia Tech, a great deal of effort has gone

Table 10. Design dimensions for the full-scale microbubble flotation column.

Zone	Height
Froth	12 inches
Stabilized Froth	36 inches
Feed Distribution	48 inches
Collection	87 inches
Air Distribution	48 inches
Reject Collection	61 inches
Total	292 inches (24.3 ft)

towards the development of expressions that can be used to scale-up the microbubble generation circuit. In general, the performance of the generators can be described by:

$$D_b = \frac{2190 D_g}{K We^{0.71}} \quad [15]$$

in which D_b is the bubble diameter at the generator exit; D_g is the generator diameter; We is the dimensionless Weber number and K is the generator pressure-drop constant. The K value for a given mixer can be experimentally determined from plots of pressure drop versus volumetric liquid flow rate. A second factor to be considered is whether the generator can handle the required air fraction. This phenomenon can be quantified by the expression:

$$e_g = V_g / (V_r + V_g) \quad [16]$$

in which V_g is the superficial gas rate to the generator and V_r is the recycle flow of liquid through the bubble generator. Studies conducted using large-scale generators indicate that ϵ_g should not exceed approximately 40% for effective air sparging.

Using Equation [16], a recycle flow of approximately 2000 gpm was selected for the initial test flow for the full-scale column. After examining standard charts developed for various generator geometries, it was determined that four 4-inch diameter microbubble generators would be required to pass the desired flow while maintaining a Weber number large enough to produce small bubbles. The results of the bubble generation calculations are summarized in Table 11.

Table 11. Summary of bubble generation calculations.

Required Number of Generators	4
Generator Diameter	4 inch
Total Recycle Flow	1700 gpm
Recycle Flow/Generator	425 gpm
Total Aeration Rate	160 cfm
Aeration Rate/Generator	40 cfm
Exit Air Fraction	0.41
Exit Bubble Diameter	0.26 mm
Operating Pressure	44 ft (19 psi)
Operating Efficiency	0.70
Required Brake Horsepower	27 HP
Estimated Motor Efficiency	0.85
Estimated Motor Horsepower	32 HP

The next step in the design of the bubble generation circuit was the selection of a centrifugal pump. The primary head loss to be overcome in the pumping circuit is that across the microbubble generators. Studies conducted at Virginia Tech have shown that the pressure drop (P) across a generator is given by:

$$P = K \frac{0.316}{Re^{.25}} \left[\frac{L_g}{D_g} \right] \left[\frac{SV^2}{2} \right] \quad [17]$$

where K is the mixer constant; Re is the Reynolds number; S is the slurry specific gravity; V is the superficial slurry velocity through the generator and L_g and D_g are the generator length and diameter, respectively. This expression provides a means of determining pressure loss through the mixer as a function of volumetric flow rate.

In addition to the pressure drop across the generator, head losses in the piping network of the bubble generation circuit must also be taken into account in order to select an appropriate pump. In the present work, standard values available in Cameron Hydraulic Data, published by the Ingersoll-Rand Company, have been used to quantify the head losses in the piping network. These calculations are relatively straightforward once the geometric arrangement of the piping system has been identified. Head loss values for each component in the piping network are summarized in Table 12 for the required flow rate of 1700 gpm. The total system head was determined to be 44 feet (19 psi). Using these values, various pump curves were examined and a Warman International 10x8 centrifugal pump was selected. The pressure-flow curve for this pump is shown in Figure 45. As shown, a pump speed of approximately 520 rpm was required to obtain the desired flow and pressure. A pumping efficiency of approximately 70% was possible at this operating point.

Table 12. Summary of head loss values for each component in the bubble generation circuit.

MICROBUBBLE COLUMN FLOTATION
TOTAL PRESSURE HEAD CALCULATIONS

Total Estimated Flow Rate (gpm) = 1700
Absolute Pipe Roughness (ft) = .0005
Generator K = 150

Description	Run	Length (ft)	Diameter (inch)	Velocity (ft/s)	Reynolds Number	f-Factor	K-Factor	Velocity Head (ft)	Head Loss (ft)
Suction Inlet	1		10	6.9454708			.78	.74976009	.58481287
90 Elbow	1		10	6.9454708			.22	.74976009	.16494722
Suction Pipe	2	5	10	6.9454708	477941.00	.01829119	.27436784	.74976009	.20571005
90 Elbow	2		10	6.9454708			.22	.74976009	.16494722
Suction Pipe	3	10	10	6.9454708	477941.00	.01829119	.54873567	.74976009	.41142011
90 Elbow	3		10	6.9454708			.22	.74976009	.16494722
Suction Pipe	4	2	10	6.9454708	477941.00	.01829119	.10974713	.74976009	.08228402
Discharge Pipe	5	20	8	10.8522298	597426.25	.01894834	1.1369003	1.8304690	2.0810607
22.5 Elbow	5		8	10.8522298			.09	1.8304690	.16474221
Discharge Pipe	6	2	8	10.8522298	597426.25	.01894834	.11369003	1.8304690	.20810607
90 Elbow	6		8	10.8522298			.22	1.8304690	.40270318
Discharge Pipe	7	1	8	10.8522298	597426.25	.01894834	.05684501	1.8304690	.10405303
22.5 Elbow	7		8	10.8522298			.09	1.8304690	.16474221
Discharge Pipe	8	2	8	10.8522298	597426.25	.01894834	.11369003	1.8304690	.20810607
90 Tee (branch)	8		8	10.8522298			.84	1.8304690	1.5375939
Ring Pipe	12	6	8	5.4261491	298713.12	.01950083	.35101501	.45761724	.16063052
90 Tee (thru)	12		8	5.4261491			.28	.45761724	.12813283
Ring Pipe	13	4	8	2.7130745	149356.56	.02046541	.24558488	.11440431	.02809597
90 Tee (thru)	13		8	2.7130745			.28	.11440431	.03203321
Ring Pipe	14	4	8	2.7130745	149356.56	.02046541	.24558488	.11440431	.02809597
90 Tee (branch)	15		4	10.8522298			1.02	1.8304690	1.8670784
Contraction	15		4	10.8522298			.5	1.8304690	.91523449
Pipe	15	.5	4	10.8522298	298713.12	.02246460	.03369690	1.8304690	.06168113
Valve	15		4	10.8522298			.14	1.8304690	.25626566
Pipe	15	1	4	10.8522298	298713.12	.02246460	.06739380	1.8304690	.12336225
Generator	15	1.5	4	10.8522298	298713.12	.02246460	15.163604	1.8304690	27.756507
Valve	15		4	10.8522298			.14	1.8304690	.25626566
Pipe	15	.5	4	10.8522298	298713.12	.02246460	.03369690	1.8304690	.06168113
Elbow	15		4	10.8522298			.51	1.8304690	.93353918
Pipe	15	1	4	10.8522298	298713.12	.02246460	.06739380	1.8304690	.12336225
Expansion	15		4	10.8522298			1	1.8304690	1.8304690

Total Static Head (ft)	2.5
Total Suction Head (ft)	1.7790687
Total Discharge Head (ft)	4.8711074
Total Ring Head (ft)	.37698849
Total Generator Head (ft)	34.185446
TOTAL SYSTEM HEAD (ft)	43.712611

• GUIDE LINE ONLY, CONSULT FACTORY WHEN APPROACHING THESE LIMITS 40

Figure 45. Pressure versus flow curve for the microbubble generation pump

The brake horsepower for the pump motor was calculated from the expression:

$$\text{Brake HP} = \frac{QHS}{3960E}, \quad [18]$$

in which Q is the volumetric flow; H is the required head; S is the slurry specific gravity and E is the pump efficiency. For the given conditions, a brake (shaft) horsepower of 27 was estimated. The required motor horsepower was determined to be approximately 32 by assuming a motor efficiency of 85%. However, in order to allow for flexibility in testing the bubble generators, an oversized motor with a 50 HP rating was selected for testing the first full-scale unit.

Engineering and Fabrication: Based on the column geometry conceived from the scale-up projections, ICF-Kaiser Engineers developed a detailed set of specifications for the bidding and construction of the full-scale microbubble flotation column. A schematic representation of the full-scale column design is shown in Figure 46. (The specifications prepared by ICF-Kaiser Engineers covered the requirements for furnishing labor, piping, hoses, valves, structural steel, platework, materials, and transportation and to shop-detail, furnish, fabricate, shop prime, finish coat and deliver the full-scale column.) The fabrication prints included all parts, supplies, and miscellaneous supports required for the assembly/installation of the column. A detailed set of standards were also specified by ICF-Kaiser Engineers regarding guidelines for fabrication workmanship. All specifications conformed to material codes and standards specified by the American Society for Testing and Materials (ASTM).

Figure 46. Schematic representation of the full-scale (8-foot diameter) microbubble flotation column.

3.1.b - Economic/Cost Analysis

After the above engineering feasibility study was completed, a simple cost analysis was conducted to estimate the benefits of installing a full-scale microbubble flotation column. In these values, summarized in Table 13, a fixed market price is assumed for the clean coal product of \$30/ton. A penalty of 1.4 tph has also been applied in the cost estimates to account for losses of clean coal in the heavy media circuit when the gravities are adjusted to maintain a fixed overall product moisture. All costs are presented on a per column basis.

These preliminary calculations indicate that a typical payback period on the capital investment for a microbubble flotation circuit is on the order of 8-9 months. As such, continued development of this technology appears to be very attractive. However, this analysis did not consider such items as the cost of capital, depreciation, and manpower requirements. These items will be included in the final analysis presented in section 3.4.b. The analysis also did not consider additional costs that might be associated with dewatering the fine coal product, which could be significant, since the dewatering circuit presently in service at the Marrowbone plant was believed to have sufficient surplus capacity to handle the additional fine coal product.

The Shell Mining Group also generated a detailed cost analysis for the microbubble flotation circuit. In their analysis, additional factors were considered that were specific to the characteristics of the Marrowbone plant production and sales contracts. As a result, their analysis was far more detailed and considered several factors not accounted for in the analysis presented above. Unfortunately, these data cannot be included for public disclosure due to the proprietary nature of the cost figures used in the analysis. However, in light of the commitment by Shell Mining to continue the testing and development of a full-scale unit, it was apparent that this analysis was also favorable.

Table 13. Cost-benefit analysis for a full-scale microbubble flotation column (all values approximate)

Yield	30%
Column Capacity	14.6 tph
Recoverable Fines	4.4
Moisture Penalty	1.4 tph
Net Recoverable Tons	3.0 tph
Plant Availability	85%
Hours/Shift	8 hours
Shifts/Day	3 shift
Operating Days/Year	230 days
Operating Hours/Year	4692 hours
Net Tonnage/Year	14,076 tons
Reagent Costs	\$1/ton
Pump/Compressor Power Costs	\$0.20/ton
Coal Worth	\$30/ton
Net Worth/Year	\$422,300
Reagent Cost/Year	\$68,500
Power Cost/Year	\$13,700
Maintenance Cost/Year ¹	\$7,500
Net Return/Year	\$332,600
Column Equipment Cost	\$60,000
Compressor Equipment Cost ²	\$15,000
Installed Cost ³	\$225,000
Expected Payback	0.7 years

1 - Estimated as 10% of the total equipment costs annually.

2 - Estimated compressor costs per column for a full-scale plant installation.

3 - Total estimated capital cost is based on Hoffman-Munter Report No. EPA-600/7-78-124, "An Engineering/Economic Analysis of Coal Preparation Plant Operation and Cost." This report estimates that the installed capital cost can be obtained by multiplying the total equipment cost by a factor of 3.

Task 3.2 Column Installation

3.2.a - Column Fabrication

The fabrication specifications were issued by ICF-Kaiser Engineers on March 19, 1990. After obtaining bids from several firms, Ironston Steel of Charleston, West Virginia was chosen as the fabricator on the basis of their submission of the lowest bid. Column fabrication began shortly after the award notification was provided to the fabricator, and the column was delivered to the Marrowbone Preparation Plant on April 6, 1990.

In order to reduce costs, several standard components were also procured separately by personnel at the Marrowbone Preparation Plant. These items included the bubble generation pump, reject control valve, and associated instruments to monitor and control the column performance.

3.2.b - Site Preparation and Column Installation

The retrofit of the microbubble flotation column into the existing flowsheet of the Marrowbone Preparation Plant required extensive modification. A private engineering firm was contracted to examine possible locations for the installation of the column. Two primary sites were identified as possible locations for the installation. The first recommendation was to install the columns outside the northern wall of the plant. The second was to locate the column inside the plant within filter press bays which are now idle. After considering several factors related to pipe routing, demolition costs, effects of weather, available head pressures, etc., the interior plant location was selected.

In order to make room for the full-scale column, one of the filter press bays had to be cleared. The disassembly and removal of the filter press was carried out concurrently with the fabrication of the microbubble flotation column. After removing the filter press, the bay

was widened slightly and a subfloor was built to support the base of the column. Additional steel beams were added to support the weight of the column and slurry. Once the column arrived, panels were removed from the side of the preparation plant, and the column was hoisted into place one section at a time. Sections were assembled and the necessary runs of piping were installed for the feed, product, and reject streams. Electrical connections were made by a separate contractor hired by Shell Mining. Control switches were located in the filter press control room.

Installation of the key components of the microbubble flotation column was completed on May 16, 1990.

3.2.c - Develop Test Plan

The parametric test results from the 30-inch column (Task 2.4) were analyzed in detail by personnel from VCCMP and Shell Mining. Based on these discussions, it was determined that gas flow rate, wash water flow rate, frother addition, and collector dosage were the major parameters that influence column separation efficiency, and it was decided that these factors would be used in the parametric study for the prototype 8-foot column. The standard operating conditions for this study are given in Table 14. The test levels for the prototype 8-foot column and the corresponding parametric test program are presented in Tables 15 and 16, respectively.

The feed size distribution that was to be used for the 8-foot column testwork was also discussed in great detail. As noted earlier, significant savings could be realized in the operating expenses associated with the fine heavy medium circuit if the column were to be fed with cyclone feed material (28 mesh x 0), rather than with the cyclone overflow stream (150 mesh x 0). Preliminary results, shown in Figure 47, indicate that the coarser feed, i.e.,

Table 14. Standard conditions used for parametric test plan.

Parameter	Setting
Column Diameter	8 feet
Column Length	24 feet
Wash Water Addition Point	
Upper Ring	3 inches above lip
Middle Ring	3 inches above lip
Lower Ring	10 inches below lip
Generator Length	30 inches
Generator Diameter	4 inches
Number of Generators	4
Frother Type	Betz 1012
Collector Type	#2 Diesel
Baffles	None

Table 15. Levels utilized in the factorial test program.

Parameter	Low	Normal	High
Frother Dosage (ml/min)	50	75	100
Collector Dosage (ml/min)	50	100	150
Aeration Rate (SCFM)	120	160	200
Wash Water Rate (GPM)	150	200	250

Table 16. Factorial test program.

Test No.	Frother (cc/min)	Collector (cc/min)	Aeration (SCFM)	Wash Water (GPM)
1	50	50	120	250
2	75	100	160	200
3	100	150	200	250
4	75	100	160	200
5	100	50	120	150
6	50	150	200	150
7	100	150	200	150
8	50	50	200	250
9	50	50	200	150
10	100	150	120	250
11	75	100	160	200
12	50	150	200	250
13	75	100	160	200
14	50	150	120	250
15	100	50	200	250
16	100	50	200	150
17	100	50	120	250
18	50	150	120	150
19	100	150	120	150
20	50	50	120	150

Figure 47. Combustible recovery as a function of product ash percent using the 30-inch column.

cyclone feed (by zero) or scalped cyclone feed (-28 mesh) actually provided a lower product ash than the cyclone overflow. This indicates that the +150 mesh fractions in the cyclone feed contain significant quantities of low ash coal. Also, there appeared to be no reduction in product recovery or separation efficiency for the coarser particle sizes.

The separation efficiency of the 30-inch column also appears to be maintained for the coarser sizes, as indicated by Figures 48 and 49. These diagrams show combustible recovery as a function of ash rejection and separation efficiency, respectively. It can be seen that the cyclone feed and the true -28 mesh fraction both fall on the same curve as the cyclone overflow results. This indicates that the efficiency of separation has not been affected by the addition of coarse material. Unfortunately, an extensive data base for the coarse feed was not established, primarily because of the extreme variability in the size

Figure 48. Combustible recovery as a function of feed ash rejection using the 30-inch column.

distribution of the cyclone feed stream. For example, the cyclone feed top size varied on an hourly basis from 28 mesh up to 3/8 inch. To accurately test this stream would require the installation of an additional sieve bend that would be dedicated to the 8-foot column. Since this was not practical, it was decided to conduct the prototype parametric testing on the minus 150 mesh cyclone overflow stream. This alternative had the added advantage of permitting direct comparison of the performances of the 30-inch and 8-foot test columns. It also provided the opportunity to further validate the established column scale-up procedure.

Figure 49. Combustible recovery as a function of separation efficiency using the 30-inch column.

Task 3.3 Column Testing

3.3.a - Shakedown Tests

Shakedown tests by personnel from the VCCMP and ICF-Kaiser Engineers began shortly after installation of the column was completed. These tests were conducted primarily to identify possible shortcomings in the design of the column. Several problems were encountered during this phase of the work, including mechanical problems with the plant air compressors, instabilities in column level because of an oversized reject control valve, plugging of the feed line by coarse particles, an inability to obtain reliable feed flow rate readings, and poor distribution of the wash water due to an insufficient number of holes in the wash water ring. With the help of personnel from the Marrowbone Preparation Plant, most of these problems were resolved within a two-week period.

Preliminary data collected from the 8-foot diameter column are provided in Table 17. In general, the column performed well. All three samples collected during the second and third full days of testing gave recovery values greater than the target value of 60%. Although the target value for the product ash content of 10% was not achieved during the preliminary testing, it should be pointed out that this was due to piping problems that dictated lower than desired wash water flow rates. As shown in Figure 50, a similar result was obtained for the 30-inch test work when a low wash water addition rate was utilized. After the piping problem was corrected, there were no further problems with achieving target grade and recovery.

Additional tests were conducted over a three-day period to assess column stability. Results from these tests are presented in Figure 51. It can be seen that the 8-foot column consistently produced a clean coal product containing less than 10 percent ash at an average combustible recovery of 60 percent. The product consistency is particularly impressive when considering that the feed ash percent varied from 45 to 60 during the test program.

These same results are presented in the product grade versus recovery curve shown in Figure 52. It is interesting to note that the product grade from these tests was somewhat

Table 17. Preliminary test results obtained from the full-scale microbubble flotation column.

Test #	Ash Percent			Yield (%)	Combustible Recovery
	Feed	Product	Reject		
1	62.74	12.79	80.63	26.37	61.72
2	62.11	13.17	80.90	27.74	63.58
3	62.38	12.03	81.38	27.40	64.07

Figure 50. Expected performance of the microbubble flotation column at low and optimum wash water addition rates.

Figure 51. Feed ash, product ash and combustible recovery as a function of time for the 8-foot microbubble column.

improved over those previously reported for the 2-, 6- and 30-inch columns. It is believed that the plant was processing a different blend of coals during the time when this data was collected. This is not unlikely, since the Tug Valley plant processes coal from three mines and three different coal seams. The possibility that a different brand of coal was processed is further supported by the fact that the ash content of the product from the 8-foot column averaged 2 to 3 percentage points lower than expected from the release analysis work. The complete material balance information for each test is given in Appendix 8.

Figure 52. Product grade versus recovery curve for column flotation using 2-inch, 6-inch, 30-inch and 8-foot diameter cells.

3.3.b,c,d - Initiate Task 3.2 Test Plan

Once commissioning and shakedown testing had been completed, VCCMP staff initiated the factorial design testwork outlined in Task 3.2.c. This test program required that 20 individual flotation tests be conducted in order to quantify the effects of the four specified test parameters. The specific test levels utilized in the design were selected based on the exploratory test results that were obtained in the earlier stages of this project. The tests were conducted in random order to minimize experimental bias.

A complete proximate analysis was performed on each sample collected in the factorial test program. These results are summarized in Table 18. The feed, product and

Table 18. Results of factorial design for 8-foot column.

Sample	Feed					Product					Tail				
	% Solids	Volatile Matter	% Ash	Fixed Carbon	% Solids	Volatile Matter	% Ash	Fixed Carbon	% Solids	Volatile Matter	% Ash	Fixed Carbon	Yield %	Combust Recov %	Sep Eff %
1	6.78	14.51	60.56	24.93	14.75	24.01	6.03	69.96	3.73	13.42	66.89	19.69	10.4	24.78	23.75
2	6.65	14.54	60.06	25.37	13.14	24.34	7.7	67.96	4.32	12.57	70.69	16.74	16.83	38.92	36.76
3	5.03	14.11	60.89	25.0	11.95	24.77	8.0	67.23	3.21	11.11	76.17	12.72	22.41	52.73	49.78
4	5.88	14.34	60.18	25.48	13.08	25.05	6.9	68.05	3.71	12.44	71.33	16.23	17.31	40.46	38.48
5	4.26	15.65	56.67	27.68	14.43	25.15	6.61	68.24	3.29	13.34	67.62	19.04	17.95	38.68	36.59
6	5.1	15.77	55.96	28.27	12.56	25.36	7.8	66.84	3.37	12.92	69.67	17.41	22.16	46.39	43.30
7	4.0	15.11	56.57	28.32	12.66	24.63	8.67	66.7	2.74	11.29	76.15	12.56	29.02	61.02	56.57
8	4.85	15.21	55.71	29.08	13.52	24.72	8.28	67.0	2.27	11.6	73.77	14.63	27.58	57.11	53.01
9	4.44	15.51	55.81	28.68	12.59	24.72	8.72	66.56	2.97	12.71	70.62	16.67	23.93	49.42	45.68
10	3.48	15.26	56.56	28.18	13.40	26.0	7.16	66.84	1.62	11.73	74.3	13.97	26.42	56.47	53.12
11	3.26	15.67	54.84	29.49	12.91	25.46	7.39	67.15	1.79	11.58	73.88	14.54	28.64	58.72	54.86
12	3.16	15.72	54.82	29.46	12.40	25.47	7.9	66.63	1.61	11.7	74.39	13.91	29.43	59.10	55.76
13	4.93	15.37	55.14	29.49	12.79	24.91	7.35	67.74	2.27	12.15	71.76	16.09	25.80	53.29	49.85
14	4.59	15.74	54.52	29.74	12.34	25.25	6.24	68.51	2.65	13.56	66.97	19.47	20.5	42.26	39.92
15	4.44	15.32	53.89	30.79	12.76	24.44	8.4	67.16	2.28	11.08	76.07	12.85	32.78	65.11	60.00
16	4.03	15.81	54.15	30.04	14.03	24.72	8.83	66.45	2.31	11.07	76.8	12.13	3.32	66.26	60.83
17	4.12	15.57	54.75	29.68	13.46	25.1	6.41	68.49	2.37	13.15	68.38	18.47	21.99	45.49	42.92
18	3.68	15.79	54.42	29.79	15.78	25.07	6.96	67.97	2.55	13.31	67.61	19.08	21.75	44.39	41.61
19	2.51	15.74	56.25	28.01	14.57	25.61	7.66	66.73	2.44	12.99	70.1	16.91	22.18	46.82	43.80
20	4.02	16.78	54.2	29.02	14.65	25.13	6.72	68.15	2.76	13.79	64.87	21.34	18.36	7.37	35.10

reject percent solids are also given. Product yield and combustible recovery were calculated from the product assays and are also given in Table 18.

As indicated in Table 16, four replicate tests (Tests 2, 4, 11, and 13) were performed at various times throughout the program. The replicate tests were required in order to determine the amount of pure error. The product yield and ash percent for the replicate tests are given in Figure 53. It can be seen that the amount of variation between tests is insignificant relative to product ash, but a slight bias is indicated by the product yield. This is a result of a drift in the feed ash percent during the time frame in which the tests were conducted. It can be seen from Table 18 that the column feed ash slowly declined from 60 percent to nearly 54 percent throughout the course of the test program. The decrease in feed ash resulted in a higher fractional yield for the latter tests. The drift in column feed ash has been observed on more than one occasion and appears to be within normal fluctuations of plant performance. Unfortunately, this does detract somewhat from the reliability of the model.

The grade versus product recovery curve for all of the data collected in the factorial test program is shown in Figure 54. It can be seen that even with the sharp changes in operating conditions, the column continued to operate on the grade versus recovery curve. This result is particularly encouraging due to the wide fluctuations in pressure and flow that are encountered in day-to-day operation of the plant. These results are also shown in Figure 55 in terms of clean coal yield as a function of product ash percent. It can be seen that a maximum of nearly 35 percent yield can be obtained while maintaining a product ash of slightly under 10 percent.

Figure 53. Yield and product ash obtained for each of the replicate tests conducted throughout the factorial testing program.

Figure 56 shows the product combustible recovery as a function of feed ash rejection.

Ash rejection is defined as the percent of the feed ash which reports to the column tails.

Mathematically it is represented as follows:

$$\text{Ash Rejection} = (1 - Y_p) \frac{A_t}{A_f} \quad [19]$$

where Y_f is the fractional yield and A_t and A_f are the tailings and feed ash, respectively. In this approach, the results are normalized for a change in feed ash percent. It can be seen in Figure 56 that an ash rejection of over 90 percent was achieved at a combustible recovery of approximately 65 percent.

Figure 54. Combustible recovery as a function of product ash percent for the 8-foot column factorial test program.

The column separation efficiency is also shown in Figure 56 as a function of ash rejection. Separation efficiency is defined as the combustible recovery minus the ash recovery to the product. Mathematically, separation efficiency is defined as follows:

$$\text{Separation Efficiency} = Y_f \left(\frac{(100 - A_p)}{(100 - A_f)} - \frac{A_p}{A_f} \right) \quad [20]$$

where A_p is the product ash percent. It can be seen from Figure 56 that the optimum separation efficiency occurs at the elbow of the recovery versus ash rejection curve. In this case, the maximum separation efficiency was 60 percent.

Figure 55. Yield as a function of product ash percent for the 8-foot column factorial test program.

The above results agree quite closely with those obtained from previous tests conducted on the 8-foot column. This is supported by the grade versus recovery data shown in Figure 57. In this figure, the data from the 2-, 6- and 30-inch, as well as the 8-foot column are shown. It can be seen that all of the data lie on the same grade versus recovery curve, indicating that the different columns provide the same level of metallurgical performance.

Statistical Data Analysis and Model Development: After conducting all of the flotation tests, the results were also analyzed using the DESIGN-EXPERT statistical data analysis program. This software was used to set up the experimental design and to perform all

Figure 56. Combustible recovery and separation efficiency as a function of ash rejection for the 8-foot column factorial test program

required statistical computations and regression analyses. The overall objective of this effort was to develop empirical relationships between the various operating parameters and response variables: product yield, ash percent, and separation efficiency. It was felt that these parameters would provide the best indication of column performance relative to the change in operating conditions. A data analysis was then conducted to determine the best approach for representing the results in terms of the appropriate model and data transformation. Data transformations are often required to improve the model fit. In this instance, none was required.

Figure 57. Combustible recovery as a function of product ash percent for all column flotation tests conducted on the Coalburg seam coal.

The **DESIGN-EXPERT** package offers three different models for data representation: linear, quadratic and cubic models. After selecting the appropriate model, a variety of statistical routines were executed to identify the goodness-of-fit. For all runs, the values of regression coefficients, standard errors, t-tests, etc. were determined as means of quantifying the statistical significance of the model. After a reasonable mathematical model of the desired response was selected, the resultant response surface was plotted using a surface contour routine. The influence of key operating parameters and the joint interaction of various parameters on the process performance were determined from this information.

A summary of the statistical data analysis computations is provided in Appendix 9 for each of the different responses. Comparisons between the results predicted by the modeling exercise and results obtained from the experimental measurements are shown in Figures 58 through 60. In general, good correlations were obtained in each case.

The response surface plots for each of the three performance indicators are shown in Appendix 10, in Figures A - C. A number of significant trends can be observed from an analysis of the different response surfaces.

Figure 58. Comparison of experimental results with predictions made by the empirical model developed to describe separation efficiency as a function of the various operating conditions.

Figure 59. Comparison of experimental results with predictions made by the empirical model developed to describe product ash percent as a function of the various operating conditions.

Response: Product Ash Percent (Figure A)

An increase in the column aeration rate has a more significant impact on the product ash percent than does frother addition rate. This is probably a result of an increase in water recovery rates as the gas flow rate is increased. As shown in Figure A, however, an increase in wash water addition rate tends to counteract this effect. Figure A also shows that an increase in collector addition tends to provide a slight increase in product ash percent. This is probably a result of floating an increased quantity of middlings.

Response: Product Yield (Figure B)

In this instance, both frother addition rate and aeration rate have similar effects on product yield. However, at higher collector additions the yield appears to reach a maximum,

Figure 60. Comparison of experimental results with predictions made by the empirical model developed to describe product yield as a function of the various operating conditions.

at which point an increase in either frother addition or aeration appears to have little effect.

An increase in the wash water flow rate tends to slightly reduce product yield. This is probably a result of a decrease in the cell retention time due to the additional water.

Response: Separation Efficiency (Figure C)

These response surfaces tend to indicate that an increase in either aeration rate or frother addition rate results in a higher separation efficiency. This is due to the fact that an increase in either parameter results in an increase in recovery. Likewise, as shown in Figure A, only a small increase in product ash is observed over the same range. An increase in collector addition also contributes to an increase in separation efficiency. As described above, this is a result of the increased yield.

3.3.e - Scale-Up Validation

The data collected during the course of the 8-foot test program were analyzed in light of the previously described scale-up procedure. In order to validate the previously described scale-up procedure, results for tests conducted on the 8-foot column under similar operating conditions were averaged and compared to the projected scale-up calculations. These values are shown together with the projected values in Table 19.

It should be noted that the measured volumetric feed flow rate and, hence, the superficial rate, are somewhat lower than predicted. This is a result of the increase in feed percent solids during the course of the test program, as indicated in Table 19. This caused a significant increase in the mass of solids in the measured feed to the 8-foot column. Therefore, the feed volumetric flow rate to the 8-foot column was adjusted in order to match the feed solids flow rate on which the scale-up calculations were based.

Table 19. Scale-up predictions for the 8-foot diameter microbubble column flotation cell.

Parameter	2-inch Measured	30-inch Predicted	30-inch Measured	8-foot Predicted	8-foot Measured
Superficial Feed Rate	0.82 cm/s	1.59 cm/s	1.69 cm/s	1.55 cm/s	1.24 cm/s
Volumetric Flow Rate	0.26 gpm	113 gpm	120 gpm	1147 gpm	921 gpm
Feed Mass Flow Rate	6.7 lb/hr	1.44 tph	1.40 tph	14.6 tph	14.6 tph
Product Ash	10.3%	10.1%	9.46%	10.1%	7.33%
Recovery	61.8%	61.8%	61.2%	61.8%	59.6%

Although this difference changed the column retention time, it did not affect performance since the 8-foot column was operating under carrying capacity limited conditions. This is supported by the fact that combustible recovery was held constant even though the slurry retention time was increased by 25 percent. Normally, under rate limited conditions, the increase in slurry retention time should result in an increased recovery.

Additionally, it is interesting to note that although the combustible recovery dropped slightly, the product yield was constant. This is due to the fact that the increase in percent solids was a result of additional coal and not mineral matter. This can be verified by examining the feed ash percent. During the course of the test period the feed ash averaged 51.9 percent, as compared to 63.7 percent for the 30-inch parametric test. The increase in percent solids coupled with a decrease in feed ash percent indicates the presence of more coal in the column feed. Accordingly, this will result in a decrease in both combustible recovery and product ash content.

Task 3.4 Cost Analysis

Task 3.4.a - Data Analysis

All of the data collected during this investigation have been made available to Shell Mining's engineering staff. This included information on overall column and control system performance, column throughput, product grades and yields, reagent consumption, and scale-up validation. Based on a review of this data with Shell personnel, it was concluded that:

- 1) Both the 30-inch and 8-foot diameter units had performed as specified by the scale-up procedure.
- 2) There had been no significant wear to the bubble generators and ancillary mechanical systems on either system.

- 3) The PLC-based control system developed for the 8-foot column provided a simple operator interface that was readily accepted by plant personnel.

In addition, the PLC-based control system developed for the 8-foot column provided a simple operator interface that was readily accepted into the plant environment. The design of this system allows for additional flotation columns to be easily incorporated into the existing system.

Task 3.4.b - Economic/Cost Analysis

A detailed economic analysis has been conducted in order to assess the impact of column flotation on total plant economics. This analysis was based on total expenditures and expected revenues for a 10-foot diameter Microcel column flotation unit, retrofitted into an existing facility. This size of column was selected simply because of the economy of scale (i.e., increased throughput for a minimal cost increase), and was based on cost estimates for different size units provided by Kaiser Engineers. The estimated capital and operating costs for this unit are presented in Table 20. The equipment list includes only those items of equipment and instrumentation that are essential for column operation, and costs were based on actual expenditures incurred during the project. The installation costs also reflect those experienced on this project, i.e. on a retrofit application. Operating costs were based on the predicted performance for one 10-foot diameter column.

Complete cash flow analyses were conducted for several different coal prices. The results of these calculations are presented in Figure 61. This diagram shows the total net cash flow for a ten year period, assuming 10, 20 and 30 percent loss of fine coal during subsequent dewatering of the product. It can be seen that even the worst case (30%

Table 20. Predicted expenditures for one 10-foot diameter Microcel.

FIXED COST	
Column	85,000
Compressor	15,000
Ancillary	
- Reagent Pumps (2)	3,000
- Instrumentation	
* Control Valve	1,000
* DP Cell	1,500
* PID Controller	500
* Air Flow Meter	500
* Water Flow Meter	750
* Actuator Valves (2)	2000
Total Equipment	109,250
Installation Costs (@50%)	54,625
OPERATING COST (yearly basis)	
Reagents	
- Collector	14,976
- Frother	59,907
Power	19,233
Maintenance (10% of installed cost)	10,925
Labor	85,560
Total Operating Cost	190,601

Note: Collector based on 106,865 tons per year and 0.7 lb/ton #2 diesel @ \$0.20/lb.

Frother based on 106,865 tons per year and 0.7 lb/ton ShurCoal 214 @ \$0.80/lb.

Power expenditures based on \$0.06/kwh, 4692 hrs/year, 80% diversity and a total connected power draw of 85.4 HP.

Manpower expenditures based on one (1/2 time) class A equipment operator with salary and benefits @ 55%.

Figure 61. Net cash flow predicted over ten year basis for 10, 20, 30 percent loss of fines during the dewatering stage.

dewatering losses and \$20/ton) gives an anticipated break-even point of less than one year. To further illustrate this point, the internal rate of return for each cash flow scenario was also determined. These results are illustrated in Figure 62 for different percentages of lost fines. It can be seen from Figure 62 that the internal rate of return is dramatic, ranging from 150 to over 400 percent. The detailed cash flows for each case are presented in Appendix 11.

Figure 62. Internal rate of return for various cash flow scenarios, for different percentages of lost fines.

Task 3.4.c - Assess Future Applications

The work conducted in the Marrowbone Development Corporation's preparation plant has shown that the Microcel flotation column can be successfully used to treat difficult-to-clean, fine coal streams, i.e., streams that are typically rejected by present day preparation plants. The following guidelines can be used when applying the microbubble column flotation process in these situations:

- 1) Column performance on a given sample closely approaches that predicted by a standard release analysis test on that sample. The release analysis test determines the maximum product yield for a specified product ash content in a flotation separation process, and parallels the washability analysis used to evaluate and specify heavy media separations.
- 2) The potential performance of a large-scale industrial flotation column can be determined from testwork conducted in a 2-inch laboratory column. Information on factors such as column throughput, reagent addition rates, combustible recovery, product yield and product ash content, can be obtained from these tests and used to design large-scale columns.
- 3) A flotation column should be designed to operate at its maximum froth carrying capacity. Because froth carrying capacity (or the maximum tons per hour of product per square foot of column area) is strongly influenced by product particle size and density, each column installation will be unique. In general, however, a column processing a -150 mesh cyclone overflow stream will have a much lower throughput than one processing -28 mesh feed.
- 4) Dewatering of the clean coal product from the column must be given careful consideration. Extremely fine flotation products can be lost during dewatering in the

typical screen bowl centrifuge and the installation of additional dewatering equipment may markedly increase overall treatment costs. However, even at losses as high as 30%, the payback period on the capital investment remains relatively short.

Task 3.5 Final Recommendations

Based on the results of this test program, two separate flow sheets were suggested for the Marrowbone column flotation circuit. The first is shown in Figure 63. In this case, the entire -150 mesh cyclone overflow stream is fed directly to a bank of five 10-foot diameter flotation columns. This scheme will provide an additional 30 to 35 tons per hour of clean coal having an ash content of approximately 8 percent.

Figure 63. Proposed flowsheet for column flotation of 150 mesh x 0 cyclone overflow material.

The second conceptual design involves feeding the entire -28 mesh cyclone feed stream directly to column flotation. Currently, the 28 x 150 mesh fraction is discharged to a bank of 150 mesh Derrick screens for additional desliming and the screen overflow sent to a fine heavy-media circuit. However, this circuit tends to be expensive to operate due to media losses and excessive screen wear. Therefore, consideration has been given to eliminating the fine heavy media circuit in favor of column flotation. This concept needs to be further validated with additional coarse coal flotation studies. The flowsheet for this arrangement is shown in Figure 64.

Figure 64. Proposed flowsheet for column flotation of -28 mesh cyclone feed.

ACKNOWLEDGEMENTS

The Principal Investigators would like to express their thanks to the Shell Mining Corporation, its Marrowbone Development subsidiary and Dennis Phillips, Senior Mining Engineer, for their support and encouragement of this project. Gratitude is also expressed to Ed Jackson, Elbert "Big E" Hunt, Julie Glavin, Oscar Triplett, and Sam Diamond for their technical assistance throughout the investigation. The investigators wish to thank Richard E. Hucko and Thomas J. Feeley, III, of the DOE's Coal Preparation and Solids Transportation Division, for their advice during the course of this investigation.

BIBLIOGRAPHY

- C.C. Dell, 1953, "Release Analysis, A New Tool for Ore Dressing Research," *Recent Developments in Mineral Dressing*, Institution of Mining and Metallurgy, London, pp. 109-118.
- C.C. Dell, M.J. Bunyard, W.A. Rickelton and P.A. Young, 1972, "Release Analysis: A Comparison of Techniques," *Trans. IMM (Sect. C: Min. Proc. & Extr. Met.)*, **81**, pp. C89-C96.
- M.J. Mankosa, G.A. Adel, G.H. Luttrell and R-H. Yoon, 1990, "Modeling of Column Flotation with a View Toward Scale-Up and Control," *Control '90 - Mineral and Metallurgical Processing* (R.K. Rajamani and J.A. Herbst, Eds.), SME, Inc., Littleton, CO, pp. 35-41.
- M.J. Mankosa, G.H. Luttrell, G.T. Adel and R-H. Yoon, 1991, "A Study of Axial Mixing in Column Flotation," accepted for publication: *International Journal of Minerals Processing*.
- S.J. Pratten, C.N. Bensley and S.K. Nicol, 1989, "An Evaluation of the Flotation Response of Coals," *International Journal of Mineral Processing*, **27**, pp. 243-262.
- R-H. Yoon, G.T. Adel, G.H. Luttrell and M.J. Mankosa, 1990, "Pilot Scale Testing of Microbubble Flotation," Final Report of Work Performed Under DOE Contract No. DE-AC22-86PC91274, 325 pp.

Appendix 1: Material balances for the 30-inch column exploratory tests

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plnt. (Feed Rate) In-Plant	Test No: 1

Sample Characteristics:	
Percent Solids (As Received)	5.6
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.77	Diesel
Frother	1.09	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.4 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	78		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	9.72	90.28			
Reject	81.18	18.82			
Feed	60.76	39.24			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	28.58	4.57	65.74			
Reject	71.42	95.43	34.26			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plant (Feed Rate) In-Plant	Test No: 2

Sample Characteristics:	
Percent Solids (As Received)	5.6
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.13	Diesel
Frother	1.59	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.4 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb.(%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.06	91.94			
Reject	72.74	27.26			
Feed	51.49	48.51			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	32.85	5.14	62.27			
Reject	61.15	94.86	37.73			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plant (Feed Rate) In-Plant	Test No: 3

Sample Characteristics:	
Percent Solids (As Received)	5.6
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.77	Diesel
Frother	1.09	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.1 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	120		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.96	91.04			
Reject	76.05	23.95			
Feed	57.58	42.42			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	27.53	4.28	59.08			
Reject	72.47	95.72	40.92			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plant (Aeration Rate) In-Plant	Test No: 1

Sample Characteristics:	
Percent Solids (As Received)	5.6
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	30 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.11	Diesel
Frother	1.58	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	12.3 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.02	91.98			
Reject	75.39	24.81			
Feed	55.29	44.71			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	29.74	4.31	61.19			
Reject	70.26	95.69	38.81			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plant (Aeration Rate) In-Plant	Test No: 2

Sample Characteristics:	
Percent Solids (As Received)	5.6
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.13	Diesel
Frother	1.59	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.4 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.06	91.94			
Reject	72.74	27.26			
Feed	55.29	44.71			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	32.85	4.79	62.27			
Reject	61.15	95.21	37.73			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plant (Aeration Rate) In-Plant	Test No: 3

Sample Characteristics:	
Percent Solids (As Received)	5.6
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.85	Diesel
Frother	1.20	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	19.9 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	10.52	89.48			
Reject	78.94	21.06			
Feed	60.43	39.57			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	27.05	3.60	61.18			
Reject	72.95	96.4	38.82			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plant (Froth Height) In-Plant	Test No: 1

Sample Characteristics:	
Percent Solids (As Received)	5.6
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	31 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.99	Diesel
Frother	1.40	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.4 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	7.41	92.59			
Reject	69.65	30.35			
Feed	53.27	46.73			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	26.32	3.66	52.15			
Reject	73.68	96.34	47.85			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plant (Froth Height) In-Plant	Test No: 2

Sample Characteristics:	
Percent Solids (As Received)	5.6
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.13	Diesel
Frother	1.59	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.4 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.06	91.94			
Reject	72.74	27.26			
Feed	51.49	48.51			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	32.85	5.14	62.27			
Reject	61.15	94.86	37.73			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plant (Froth Height) In-Plant	Test No: 3

Sample Characteristics:	
Percent Solids (As Received)	5.6
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	46 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.22	Diesel
Frother	1.72	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.4 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.19	91.81			
Reject	77.92	22.08			
Feed	55.37	44.63			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	32.34	4.78	66.53			
Reject	67.66	95.22	33.47			
Feed	100	100	100	100	100	100

Appendix 2: Material balances for the 30-inch column long-term test

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Long-Term) In-Plant	Test No: 1

Sample Characteristics:	
Percent Solids (As Received)	3.56
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.26	Diesel
Frother	2.50	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	17.2 (scfm)		
Wash Water Flowrate	20		
Feed Flowrate	98		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	9.85	90.15			
Reject	78.50	21.50			
Feed	57.91	42.09			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	29.99	5.10	64.24			
Reject	70.01	94.90	35.76			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Long-Term) In-Plant	Test No: 2

Sample Characteristics:	
Percent Solids (As Received)	4.13
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.08	Diesel
Frother	1.52	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.8 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	98		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	9.44	90.56			
Reject	78.21	21.79			
Feed	57.79	42.21			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	29.69	4.87	63.71			
Reject	70.31	95.13	36.29			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Long-Term) In-Plant	Test No: 3

Sample Characteristics:	
Percent Solids (As Received)	4.80
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.93	Diesel
Frother	1.09	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.4 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	98		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	9.24	90.76			
Reject	76.58	23.42			
Feed	58.86	41.14			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	26.31	4.13	58.05			
Reject	73.69	95.87	41.95			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Long-Term) In-Plant	Test No: 4

Sample Characteristics:	
Percent Solids (As Received)	4.62
Particle Size	- 150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.02	Diesel
Frother	1.24	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.8 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	98		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.69	91.31			
Reject	76.32	23.68			
Feed	59.16	40.84			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	25.37	3.72	56.73			
Reject	74.63	96.28	43.27			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Long-Term) In-Plant	Test No: 5

Sample Characteristics:	
Percent Solids (As Received)	3.89
Particle Size	

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.02	Diesel
Frother	1.32	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	17.2 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	10.29	89.71			
Reject	76.07	23.93			
Feed	57.89	42.11			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	27.64	4.91	58.88			
Reject	72.36	95.09	41.12			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Long-Term) In-Plant	Test No: 6

Sample Characteristics:	
Percent Solids (As Received)	4.73
Particle Size	- 150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.48	Diesel
Frother	1.14	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.0 (scfm)		
Wash Water Flowrate	20		
Feed Flowrate	104		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.29	91.71			
Reject	65.18	34.82			
Feed	58.57	41.43			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	11.62	1.48	25.72			
Reject	88.38	98.52	74.28			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Long-Term) In-Plant	Test No: 7

Sample Characteristics:	
Percent Solids (As Received)	4.44
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.94	Diesel
Frother	1.22	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.4 (scfm)		
Wash Water Flowrate	17		
Feed Flowrate	104		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	9.13	90.87			
Reject	74.57	25.43			
Feed	51.57	48.43			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	35.15	6.22	65.95			
Reject	64.85	93.78	34.05			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Long-Term) In-Plant	Test No: 8

Sample Characteristics:	
Percent Solids (As Received)	4.47
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.98	Diesel
Frother	1.26	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.8 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.67	91.33			
Reject	73.06	26.94			
Feed	51.53	48.47			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	33.44	3.97	63.00			
Reject	66.56	96.03	37.00			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Long-Term) In-Plant	Test No: 9

Sample Characteristics:	
Percent Solids (As Received)	4.07
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.15	Diesel
Frother	1.35	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.4 (scfm)		
Wash Water Flowrate	18		
Feed Flowrate	102		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	10.20	89.80			
Reject	80.14	19.86			
Feed	62.56	37.44			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	25.14	4.10	60.29			
Reject	74.86	95.90	39.71			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Long-Term) In-Plant	Test No: 10

Sample Characteristics:	
Percent Solids (As Received)	3.93
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.01	Diesel
Frother	1.43	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.0 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	10.72	89.28			
Reject	81.39	18.61			
Feed	64.75	35.25			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	23.55	3.90	59.64			
Reject	76.45	96.10	40.36			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Long-Term) In-Plant	Test No: 11

Sample Characteristics:	
Percent Solids (As Received)	3.73
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.07	Diesel
Frother	1.51	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.8 (scfm)		
Wash Water Flowrate	20		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	10.33	89.67			
Reject	72.83	27.17			
Feed	51.97	48.03			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	33.38	6.63	62.31			
Reject	66.62	93.37	37.69			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Pit. (Long-Term) In-Plant	Test No: 12

Sample Characteristics:	
Percent Solids (As Received)	4.31
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.01	Diesel
Frother	1.31	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.4 (scfm)		
Wash Water Flowrate	20		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.86	91.14			
Reject	72.15	27.85			
Feed	56.22	51.92			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	25.17	3.97	52.40			
Reject	74.83	96.03	47.60			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Long-Term) In-Plant	Test No: 13

Sample Characteristics:	
Percent Solids (As Received)	3.59
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.17	Diesel
Frother	1.51	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.4 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	104		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.92	91.08			
Reject	75.16	24.84			
Feed	53.71	48.08			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	32.38	5.38	63.72			
Reject	67.62	94.62	36.28			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Long-Term) In-Plant	Test No: 14

Sample Characteristics:	
Percent Solids (As Received)	3.24
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.54	Diesel
Frother	1.68	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.0 (scfm)		
Wash Water Flowrate	21		
Feed Flowrate	104		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.64	91.36			
Reject	77.22	22.78			
Feed	54.31	45.69			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	33.41	5.32	66.80			
Reject	66.59	94.68	33.20			
Feed	100	100	100	100	100	100

Appendix 3: Material balances for the 2-inch column particle size tests

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 1

Sample Characteristics:	
Percent Solids (As Received)	5.2
Particle Size	-28 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	72 inches
Diameter	2.0 inches
Feed Entry Point	18.5 inches
Froth Height	

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.25	Diesel
Frother	1.39	DF1012
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	1000 (cc/min)		
Wash Water Flowrate	400		
Feed Flowrate	1000		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	16.09	83.91			
Reject	84.17	15.83			
Feed	46.94	53.06			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	54.74	18.76	86.51			
Reject	42.26	81.24	13.49			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 2

Sample Characteristics:	
Percent Solids (As Received)	5.2
Particle Size	-28 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	72 inches
Diameter	2.0 inches
Feed Entry Point	18.5 inches
Froth Height	

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.25	Diesel
Frother	1.68	DF1012
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	1300 (cc/min)		
Wash Water Flowrate	400		
Feed Flowrate	1500		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	11.98	88.02			
Reject	81.05	18.95			
Feed	46.77	53.23			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	49.63	12.71	82.07			
Reject	50.37	87.29	17.93			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 3

Sample Characteristics:	
Percent Solids (As Received)	5.2
Particle Size	-28 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	72 inches
Diameter	2.0 inches
Feed Entry Point	18.5 inches
Froth Height	

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.25	Diesel
Frother	2.12	DF1012
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	1200 (cc/min)		
Wash Water Flowrate	400		
Feed Flowrate	2000		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	9.81	90.19			
Reject	72.12	27.88			
Feed	48.55	51.45			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	37.83	7.64	66.31			
Reject	62.17	92.36	33.69			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 4

Sample Characteristics:	
Percent Solids (As Received)	5.9
Particle Size	-28 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	72 inches
Diameter	2.0 inches
Feed Entry Point	18.5 inches
Froth Height	

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.25	Diesel
Frother	1.25	DF1012
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	1000 (cc/min)		
Wash Water Flowrate	400		
Feed Flowrate	2000		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	7.47	92.53			
Reject	73.81	26.19			
Feed	50.33	49.67			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	35.39	3.58	65.93			
Reject	64.61	96.42	34.07			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 1

Sample Characteristics:	
Percent Solids (As Received)	4.3
Particle Size	-48 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	72 inches
Diameter	2.0 inches
Feed Entry Point	18.5 inches
Froth Height	

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.25	Diesel
Frother	1.25	DF1012
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	2140 (cc/min)		
Wash Water Flowrate	400		
Feed Flowrate	1000		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	11.48	88.52			
Reject	82.06	17.94			
Feed	58.82	41.18			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	32.96	6.43	70.78			
Reject	67.04	93.57	29.22			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 2

Sample Characteristics:	
Percent Solids (As Received)	4.3
Particle Size	-48 mesh

Column Geometry:	
Overall Height	72 inches
Diameter	2.0 inches
Feed Entry Point (bubble generators to feed point)	18.5 inches
Froth Height	

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.25	Diesel
Frother	1.25	DF1012
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	2140 (cc/min)		
Wash Water Flowrate	400		
Feed Flowrate	1500		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	12.21	87.79			
Reject	85.10	14.90			
Feed	58.82	41.18			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	36.05	7.48	76.86			
Reject	63.95	92.52	23.14			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 3

Sample Characteristics:	
Percent Solids (As Received)	4.3
Particle Size	-48 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	72 inches
Diameter	2.0 inches
Feed Entry Point	18.5 inches
Froth Height	

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.25	Diesel
Frother	1.25	DF1012
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	2140 (cc/min)		
Wash Water Flowrate	400		
Feed Flowrate	2000		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	12.81	87.19			
Reject	80.51	19.49			
Feed	58.82	41.18			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	32.04	6.98	67.83			
Reject	67.96	93.02	32.17			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 1

Sample Characteristics:	
Percent Solids (As Received)	5.5
Particle Size	-65 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	72 inches
Diameter	2.0 inches
Feed Entry Point	18.5 inches
Froth Height	

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.00	Diesel
Frother	0.63	DF1012
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	1500 (cc/min)		
Wash Water Flowrate	400		
Feed Flowrate	500		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	10.45	89.55			
Reject	80.44	19.56			
Feed	56.94	43.06			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	33.58	6.16	69.83			
Reject	66.42	93.84	30.17			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 2

Sample Characteristics:	
Percent Solids (As Received)	5.5
Particle Size	-65 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	72 inches
Diameter	2.0 inches
Feed Entry Point (bubble generators to feed point)	18.5 inches
Froth Height	

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.00	Diesel
Frother	0.90	DF1012
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	1500 (cc/min)		
Wash Water Flowrate	400		
Feed Flowrate	1000		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	10.05	89.95			
Reject	78.27	21.73			
Feed	57.19	42.81			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	30.90	5.43	64.93			
Reject	69.10	94.57	35.07			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 3

Sample Characteristics:	
Percent Solids (As Received)	5.5
Particle Size	-65 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	72 inches
Diameter	2.0 inches
Feed Entry Point	18.5 inches
Froth Height	

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.00	Diesel
Frother	1.02	DF1012
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	1500 (cc/min)		
Wash Water Flowrate	400		
Feed Flowrate	1500		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Rtu/lb
Product	10.68	89.32			
Reject	75.40	24.60			
Feed	57.26	42.74			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	28.03	5.23	58.58			
Reject	71.97	94.77	41.42			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 4

Sample Characteristics:	
Percent Solids (As Received)	5.5
Particle Size	-65 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	72 inches
Diameter	2.0 inches
Feed Entry Point	18.5 inches
Froth Height	

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.00	Diesel
Frother	0.87	DF1012
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	1500 (cc/min)		
Wash Water Flowrate	400		
Feed Flowrate	2000		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.80	91.20			
Reject	71.40	28.60			
Feed	56.94	43.06			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	22.52	3.48	48.11			
Reject	77.48	96.52	51.89			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 1

Sample Characteristics:	
Percent Solids (As Received)	4.9
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	72 inches
Diameter	2.0 inches
Feed Entry Point	18.5 inches
Froth Height	

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.00	Diesel
Frother	0.85	PSM
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	1500 (cc/min)		
Wash Water Flowrate	400		
Feed Flowrate	500		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	11.85	88.15			
Reject	78.13	21.87			
Feed	57.50	42.50			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	31.13	6.42	64.56			
Reject	68.87	93.58	35.44			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 2

Sample Characteristics:	
Percent Solids (As Received)	4.9
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	72 inches
Diameter	2.0 inches
Feed Entry Point	18.5 inches
Froth Height	

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.00	Diesel
Frother	1.12	PSM
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	1500 (cc/min)		
Wash Water Flowrate	400		
Feed Flowrate	1000		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	11.61	88.39			
Reject	76.47	23.53			
Feed	56.61	43.39			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	30.62	6.28	62.38			
Reject	69.38	93.72	37.62			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 3

Sample Characteristics:	
Percent Solids (As Received)	4.9
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	72 inches
Diameter	2.0 inches
Feed Entry Point	18.5 inches
Froth Height	

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.00	Diesel
Frother	1.31	PSM
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	1500 (cc/min)		
Wash Water Flowrate	400		
Feed Flowrate	1500		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	11.34				
Reject	74.26				
Feed	57.06				

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	27.33	5.43	56.44			
Reject	72.67	94.57	43.56			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone Prep. Plt. (Feed Sz. Distr.) Lab Test	Test No: 1

Sample Characteristics:	
Percent Solids (As Received)	3.54
Particle Size	28 x 150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	72 inches
Diameter	2.0 inches
Feed Entry Point	18.5 inches
Froth Height	15 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.25	Diesel
Frother	0.12	DF1012
pH Modifier		
Dispersant		

Column Flows:	ml/min	gms/min	% solids
Gas Flowrate	760 (cc/min)		
Wash Water Flowrate	560		
Feed Flowrate	1500		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	21.39	78.61			
Reject	83.77	16.23			
Feed	31.38	68.62			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	83.99	57.25	96.21			
Reject	16.01	42.75	3.79			
Feed	100	100	100	100	100	100

Appendix 4: Material balances for the 30-inch column cyclone feed tests

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date: Cyclone Feed
Sample: Marrowbone (Feed Size Distribution) In-Plant, Cyclone Feed	Test No: 1

Sample Characteristics:	
Percent Solids (As Received)	6.17
Particle Size	coarse (-28 mesh)

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	42 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.76	Diesel
Frother	1.14	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	18.5 (scfm)		
Wash Water Flowrate	23		
Feed Flowrate	95 (+/- 10 gal)		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	10.88	89.12			
Reject	58.64	41.36			
Feed	42.39	42.97			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	34.02	8.73	52.63			
Reject	65.98	91.27	47.37			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date: Cyclone Feed
Sample: Marrowbone (Feed Size Distribution) In-Plant, Cyclone Feed	Test No: 2

Sample Characteristics:	
Percent Solids (As Received)	8.68
Particle Size	coarse (-28 mesh)

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	42 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.73	Diesel
Frother	0.99	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	18.5 (scfm)		
Wash Water Flowrate	23		
Feed Flowrate	95 (+/- 10 gal)		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	10.44	89.56			
Reject	58.14	41.86			
Feed	46.14	53.86			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	24.78	5.61	41.34			
Reject	75.22	94.39	58.66			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date: Cyclone Feed
Sample: Marrowbone (Feed Size Distribution) In-Plant, Cyclone Feed	Test No: 3

Sample Characteristics:	
Percent Solids (As Received)	8.16
Particle Size	coarse (-28 mesh)

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point (bubble generators to feed point)	4.5 feet
Froth Height	42 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.78	Diesel
Frother	0.72	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	18.5 (scfm)		
Wash Water Flowrate	23		
Feed Flowrate	95 (+/- 10 gal)		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	9.97	90.03			
Reject	57.18	42.82			
Feed	44.66	55.34			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	26.52	5.92	43.14			
Reject	73.48	94.08	56.86			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date: Cyclone Feed
Sample: Marrowbone (Operating Par./Froth Add.) In-Plant, Cyclone Feed	Test No: 1

Sample Characteristics:	
Percent Solids (As Received)	6.52
Particle Size	-28 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.30	Diesel
Frother	0.79	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.4 (scfm)		
Wash Water Flowrate	23		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	12.68	87.32			
Reject	61.33	38.67			
Feed	49.69	50.31			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	23.93	6.11	41.53			
Reject	76.07	93.89	58.47			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date: Cyclone Feed
Sample: Marrowbone (Operating Par./Froth Add.) In-Plant, Cyclone Feed	Test No: 2

Sample Characteristics:	
Percent Solids (As Received)	7.41
Particle Size	-28 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.14	Diesel
Frother	1.04	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.4 (scfm)		
Wash Water Flowrate	23		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	10.21	89.79			
Reject	56.94	43.06			
Feed	49.37	50.63			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	16.20	3.35	28.73			
Reject	83.80	96.64	71.27			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date: Cyclone Feed
Sample: Marrowbone (Operating Par./Froth Add.) In-Plant, Cyclone Feed	Test No: 3

Sample Characteristics:	
Percent Solids (As Received)	8.00
Particle Size	-28 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.05	Diesel
Frother	1.60	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	16.4 (scfm)		
Wash Water Flowrate	23		
Feed Flowrate	120		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	9.92	90.08			
Reject	57.54	42.46			
Feed	50.12	49.88			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	15.58	3.08	28.14			
Reject	84.42	96.92	71.86			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date: Cyclone Feed
Sample: Marrowbone (Operating Par./Froth Add.) In-Plant, Cyclone Feed	Test No: 4

Sample Characteristics:	
Percent Solids (As Received)	7.79
Particle Size	-28 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.08	Diesel
Frother	1.64	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	18.5 (scfm)		
Wash Water Flowrate	23		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	10.35	89.65			
Reject	54.27	45.73			
Feed	46.25	53.75			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	18.26	4.09	30.46			
Reject	81.74	95.91	69.54			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date: Cyclone Feed
Sample: Marrowbone (Operating Par./Froth Add.) In-Plant, Cyclone Feed	Test No: 5

Sample Characteristics:	
Percent Solids (As Received)	8.53
Particle Size	-28 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.99	Diesel
Frother	0.90	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	18.5 (scfm)		
Wash Water Flowrate	23		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	10.66	89.34			
Reject	61.07	38.93			
Feed	52.25	47.75			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	17.50	3.57	32.74			
Reject	82.50	96.43	67.26			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date: Cyclone Feed
Sample: Marrowbone (Operating Par./Froth Add.) In-Plant, Cyclone Feed	Test No: 6

Sample Characteristics:	
Percent Solids (As Received)	9.87
Particle Size	-28 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.85	Diesel
Frother	0.51	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	18.5 (scfm)		
Wash Water Flowrate	23		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	9.63	90.37			
Reject	57.69	42.31			
Feed	51.14	48.86			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	13.63	2.57	25.21			
Reject	86.37	97.43	74.79			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date: Cyclone Feed
Sample: Marrowbone (Operating Par./Froth Add.) In-Plant, Cyclone Feed	Test No: 7

Sample Characteristics:	
Percent Solids (As Received)	9.20
Particle Size	-28 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.69	Diesel
Frother	0.55	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	18.5 (scfm)		
Wash Water Flowrate	23		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	10.33	89.67			
Reject	57.72	42.28			
Feed	51.65	48.35			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	12.81	2.56	23.75			
Reject	87.19	97.44	76.25			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date: Cyclone Feed
Sample: Marrowbone (Operating Par./Froth Add.) In-Plant, Cyclone Feed	Test No: 8

Sample Characteristics:	
Percent Solids (As Received)	9.20
Particle Size	+ 28 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.69	Diesel
Frother	0.83	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	18.4 (scfm)		
Wash Water Flowrate	23		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	11.69	88.31			
Reject	55.69	44.31			
Feed	52.08	47.92			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	8.20	1.84	15.12			
Reject	91.80	98.16	84.88			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date: Cyclone Feed
Sample: Marrowbone (Operating Par./Froth Add.) In-Plant, Cyclone Feed	Test No: 9

Sample Characteristics:	
Percent Solids (As Received)	9.20
Particle Size	-28 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	21.5 feet
Diameter	29.25 inches
Feed Entry Point	4.5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	1.38	Diesel
Frother	0.69	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	18.4 (scfm)		
Wash Water Flowrate	23		
Feed Flowrate	100		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	11.60	88.40			
Reject	56.81	43.19			
Feed	51.53	48.47			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	11.68	2.63	21.30			
Reject	88.32	97.37	78.70			
Feed	100	100	100	100	100	100

**Appendix 5: Summary of the statistical data analysis computations for the 30-inch column
parametric test program**

=====

Response: Energy Rec.: File = INPLT Run on 11/01/90 at 13:24:01

=====

VAR	VARIABLE	UNITS	-1 LEVEL	+1 LEVEL
X1	Feed Rate	(gpm)	-1.000	1.000
X2	Wash Water	(gpm)	-1.000	1.000
X3	Air Rate	(scfm)	-1.000	1.000
X4	Frother	(lb/ton)	-1.000	1.000
X5	Diesel	(lb/ton)	-1.000	1.000
X6	Froth Hite	(inches)	-1.000	1.000

Results of Linear Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	6858.05	6	1143.0091	5.333	0.0003
ERROR	10072.63	47	214.3112		
COR TOTAL	16930.68	53			
ROOT MSE	14.6394		R-SQUARED	0.4051	
DEP MEAN	58.8439		ADJ R-SQUARED	0.3291	
C.V.	24.88%				

Predicted Residual Sum of Squares (PRESS) = 13316.38

Results of Quadratic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	11573.92	27	428.6638	2.081	0.0328
ERROR	5356.76	26	206.0293		
COR TOTAL	16930.68	53			
ROOT MSE	14.3537		R-SQUARED	0.6836	
DEP MEAN	58.8439		ADJ R-SQUARED	0.3550	
C.V.	24.39%				

Predicted Residual Sum of Squares (PRESS) = 24964.61

Results of Cubic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	15260.05	45	339.1122	1.624	0.2401
ERROR	1670.63	8	208.8293		
COR TOTAL	16930.68	53			
ROOT MSE	14.4509		R-SQUARED	0.9013	

DEP MEAN 58.8439 ADJ R-SQUARED 0.3463
 C.V. 24.56%

Predicted Residual Sum of Squares (PRESS) = 224428.49

ANOVA Summary of models fit

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
LINEAR	6858.05	6	1143.01	5.333	0.0003
QUADRATIC	4715.67	21	224.57	1.090	0.4127
CUBIC	3686.13	18	204.78	0.9806	0.5437
ERROR	1670.63	8	208.83		
COR TOTAL	16930.68	53			

Lack of Fit tests

MODEL	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
LINEAR	9274.18	42	220.81	1.383	0.3902
QUADRATIC	4558.31	21	217.06	1.359	0.3950
CUBIC	872.18	3	290.73	1.821	0.2603
PURE ERR	798.45	5	159.69		

=====

Response: Energy Rec.: File = INPLT Run on 11/01/90 at 13:26:24

VAR	VARIABLE	UNITS	-1 LEVEL	+1 LEVEL
X1	Feed Rate	(gpm)	-1.000	1.000
X2	Wash Water	(gpm)	-1.000	1.000
X3	Air Rate	(scfm)	-1.000	1.000
X4	Frother	(lb/ton)	-1.000	1.000
X5	Diesel	(lb/ton)	-1.000	1.000
X6	Froth Hite	(inches)	-1.000	1.000

Results of Cubic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	15260.05	45	339.1122	1.624	0.2401
ERROR	1670.63	8	208.8293		
COR TOTAL	16930.68	53			

ROOT MSE 14.4509 R-SQUARED 0.9013
 DEP MEAN 58.8439 ADJ R-SQUARED 0.3463
 C.V. 24.56%

Predicted Residual Sum of Squares (PRESS) = 224428.49

VARIABLE	PARAMETER ESTIMATE	DF	STANDARD ERROR	t FOR H0 PARAMETER=0	PROB > t
Intercept	49.9250	1	5.8996	8.462	

X1	-4.3850	1	5.1092	-0.3593	0.4157
X2	3.2450	1	5.1092	0.6351	0.5431
X3	-2.9437	1	5.1092	-0.5762	0.5803
X4	14.7338	1	5.1092	2.884	0.0204
X5	0.1350	1	5.1092	2.64E-02	0.9796
X6	-10.1262	1	5.1092	-1.982	0.0828
X1*X1	8.7671	1	4.5059	1.946	0.0876
X2*X2	8.4471	1	4.5059	1.875	0.0977
X3*X3	1.5896	1	4.5059	0.3528	0.7334
X4*X4	-3.9767	1	4.5059	-0.8926	0.4032
X5*X5	4.9171	1	4.5059	1.091	0.3069
X6*X6	0.3233	1	4.5059	7.18E-02	0.9446
X1*X2	1.3975	1	5.1092	0.2735	0.7914
X1*X3	0.3450	1	5.1092	6.75E-02	0.9478
X1*X4	-4.3925	1	3.6127	-1.216	0.2587
X1*X5	5.5825	1	5.1092	1.093	0.3064
X1*X6	-2.0200	1	5.1092	-0.3954	0.7029
X2*X3	1.3762	1	5.1092	0.2694	0.7945
X2*X4	6.1500	1	5.1092	1.204	0.2631
X2*X5	2.9331	1	3.6127	0.8119	0.4403
X2*X6	1.8000	1	5.1092	0.3523	0.7337
X3*X4	-6.5413	1	5.1092	-1.280	0.2363
X3*X5	3.4512	1	5.1092	0.6755	0.5184
X3*X6	2.6094	1	3.6127	0.7223	0.4907
X4*X5	-3.5050	1	5.1092	-0.6860	0.5121
X4*X6	9.8362	1	5.1092	1.925	0.0904
X5*X6	3.7750	1	5.1092	0.7389	0.4811
X1*X1*X1	ALIASED	0			
X2*X2*X2	ALIASED	0			
X3*X3*X3	ALIASED	0			
X4*X4*X4	ALIASED	0			
X5*X5*X5	ALIASED	0			
X6*X6*X6	ALIASED	0			
X1*X1*X2	-12.2250	1	7.2255	-1.692	0.1291
X1*X1*X3	11.0012	1	7.2255	1.523	0.1664
X1*X1*X4	-8.5113	1	7.2255	-1.178	0.2727
X1*X1*X5	1.7600	1	7.2255	0.2436	0.8137
X1*X1*X6	2.3037	1	7.2255	0.3188	0.7580
X2*X2*X3	12.3675	1	7.2255	1.712	0.1253
X2*X2*X4	4.0200	1	7.2255	0.5564	0.5932
X2*X2*X5	ALIASED	0			
X2*X2*X6	-0.5312	1	7.2255	-7.35E-02	0.9432
X3*X3*X4	ALIASED	0			
X3*X3*X5	-1.6837	1	7.2255	-0.2330	0.8216
X3*X3*X6	ALIASED	0			
X4*X4*X5	ALIASED	0			
X4*X4*X6	ALIASED	0			
X5*X5*X6	ALIASED	0			
X1*X2*X2	-4.7100	1	7.2255	-0.6519	0.5328
X1*X3*X3	-5.7725	1	7.2255	-0.7989	0.4474
X1*X4*X4	ALIASED	0			
X1*X5*X5	ALIASED	0			
X1*X6*X6	ALIASED	0			
X2*X3*X3	-0.6388	1	7.2255	-8.84E-02	0.9317
X2*X4*X4	ALIASED	0			
X2*X5*X5	ALIASED	0			
X2*X6*X6	ALIASED	0			
X3*X4*X4	ALIASED	0			
X3*X5*X5	ALIASED	0			
X3*X6*X6	ALIASED	0			

X1**X5	ALIASED	0			
X4**X6	ALIASED	0			
X5**X6	ALIASED	0			
X1**X2**X3	ALIASED	0			
X1**X2**X4	-5.1975	1	5.1092	-1.017	0.3388
X1**X2**X5	ALIASED	0			
X1**X2**X6	ALIASED	0			
X1**X3**X4	ALIASED	0			
X1**X3**X5	ALIASED	0			
X1**X3**X6	-4.8575	1	5.1092	-0.9507	0.3696
X1**X4**X5	10.7525	1	5.1092	2.105	0.0685
X1**X4**X6	ALIASED	0			
X1**X5**X6	ALIASED	0			
X2**X3**X4	ALIASED	0			
X2**X3**X5	-2.6513	1	5.1092	-0.5189	0.6179
X2**X3**X6	ALIASED	0			
X2**X4**X5	ALIASED	0			
X2**X4**X6	ALIASED	0			
X2**X5**X6	4.3775	1	5.1092	0.8568	0.4165
X3**X4**X5	ALIASED	0			
X3**X4**X6	4.0112	1	5.1092	0.7851	0.4550
X3**X5**X6	ALIASED	0			
X4**X5**X6	ALIASED	0			

Std ERROR 1.9665

Obs Ord	ACTUAL VALUE	PREDICTED VALUE	RESIDUAL	LEVER	STUDENT RESID	COOK'S DIST	t VALUE	Run Ord
1	78.9600	79.3475	-0.3875	0.938	-0.107	0.004	-0.303	54
2	57.1400	56.7525	0.3875	0.938	0.107	0.004	0.303	49
3	35.5100	35.8975	-0.3875	0.938	-0.107	0.004	-0.303	9
4	40.0700	39.6825	0.3875	0.938	0.107	0.004	0.303	5
5	86.3100	85.9225	0.3875	0.938	0.107	0.004	0.303	14
6	66.1300	66.5475	-0.3875	0.938	-0.107	0.004	-0.303	15
7	88.2500	87.8625	0.3875	0.938	0.107	0.004	0.303	33
8	52.9000	53.2875	-0.3875	0.938	-0.107	0.004	-0.303	44
9	61.6900	64.8094	-3.1194	0.938	-0.863	0.243	-2.326	16
10	59.2200	56.1006	3.1194	0.938	0.863	0.243	2.326	41
11	65.5800	68.6994	-3.1194	0.938	-0.863	0.243	-2.326	27
12	79.2200	76.1006	3.1194	0.937	0.863	0.243	2.326	39
13	46.7600	43.6406	3.1194	0.937	0.863	0.243	2.326	29
14	54.1500	57.2694	-3.1194	0.938	-0.863	0.243	-2.326	28
15	75.0600	71.9406	3.1194	0.937	0.863	0.243	2.326	46
16	77.3500	80.4694	-3.1194	0.937	-0.863	0.243	-2.326	13
17	41.4100	48.0906	-6.6806	0.937	-1.849	1.115	-3.958	11
18	64.7700	58.0894	6.6806	0.937	1.849	1.115	3.958	40
19	72.3100	78.9906	-6.6806	0.937	-1.849	1.115	-3.958	43
20	53.4600	46.7794	6.6806	0.937	1.849	1.115	3.958	7
21	17.6500	10.9694	6.6806	0.937	1.849	1.115	3.958	10
22	8.6800	15.3606	-6.6806	0.937	-1.849	1.115	-3.958	32
23	71.8500	65.1694	6.6806	0.937	1.849	1.115	3.958	52
24	52.7600	59.4406	-6.6806	0.937	-1.849	1.115	-3.958	3
25	43.2200	42.8325	0.3875	0.937	0.107	0.004	0.303	42
26	52.8000	53.1875	-0.3875	0.937	-0.107	0.004	-0.303	50
27	92.1900	92.5775	-0.3875	0.937	-0.107	0.004	-0.303	34
28	42.7400	42.3525	0.3875	0.937	0.107	0.004	0.303	17
29	64.3600	63.9725	0.3875	0.937	0.107	0.004	0.303	4
30	53.2600	53.6475	-0.3875	0.937	-0.107	0.004	-0.303	31
31	56.3000	56.6875	-0.3875	0.937	-0.107	0.004	-0.303	23

71	72.1500	71.8025	0.3875	0.937	0.107	0.004	0.303	51
72	78.1400	75.0206	3.1194	0.937	0.863	0.243	2.326	2
74	77.6800	80.7994	-3.1194	0.937	-0.863	0.243	-2.326	48
75	67.5100	70.8294	-3.1194	0.937	-0.863	0.243	-2.326	6
76	73.7500	70.8306	3.1194	0.937	0.863	0.243	2.326	25
77	54.4300	51.3106	3.1194	0.937	0.863	0.243	2.326	35
78	43.6600	46.7794	-3.1194	0.937	-0.863	0.243	-2.326	37
79	41.3900	44.5094	-3.1194	0.937	-0.863	0.243	-2.326	30
80	72.3400	69.2206	3.1194	0.937	0.863	0.243	2.326	52
81	83.0000	76.3194	6.6806	0.938	1.849	1.115	3.958	47
82	56.3200	49.8394	6.6806	0.938	1.849	1.115	3.958	1
83	70.1300	76.8106	-6.6806	0.938	-1.849	1.115	-3.958	21
84	64.2600	70.9406	-6.6806	0.938	-1.849	1.115	-3.958	24
85	43.1000	49.7806	-6.6806	0.938	-1.849	1.115	-3.958	18
86	27.7700	34.4506	-6.6806	0.938	-1.849	1.115	-3.958	45
87	86.8200	80.1394	6.6806	0.938	1.849	1.115	3.958	12
88	53.4400	46.7594	6.6806	0.938	1.849	1.115	3.958	38
89	49.4700	49.9250	-0.4550	0.167	-0.034	0.000	-0.098	8
90	55.2200	49.9250	5.2950	0.167	0.401	0.001	1.124	26
91	48.5100	49.9250	-1.4150	0.167	-0.107	0.000	-0.303	20
92	34.8500	49.9250	-15.0750	0.167	-1.143	0.006	-2.957	22
93	71.1300	49.9250	21.2050	0.167	1.607	0.011	3.741	36
94	40.3700	49.9250	-9.5550	0.167	-0.724	0.002	-1.980	19

=====

Response: ProdAsh: File = INFLT Run on 11/01/90 at 14:06:45

=====

VAR	VARIABLE	UNITS	-1 LEVEL	+1 LEVEL
X1	Feed Rate	(gpm)	-1.000	1.000
X2	Wash Water	(gpm)	-1.000	1.000
X3	Air Rate	(scfm)	-1.000	1.000
X4	Frother	(lb/ton)	-1.000	1.000
X5	Diesel	(lb/ton)	-1.000	1.000
X6	Froth Hite	(inches)	-1.000	1.000

Results of Linear Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	469.2246	6	78.20409	7.935	0.0001
ERROR	463.2281	47	9.85592		
COR TOTAL	932.4526	53			

ROOT MSE	3.13941	R-SQUARED	0.5032
DEP MEAN	11.33185	ADJ R-SQUARED	0.4398
C.V.	27.70%		

Predicted Residual Sum of Squares (PRESS) = 624.0079

Results of Quadratic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	720.8070	27	26.69656	3.280	0.0017
ERROR	211.6456	26	8.14022		
COR TOTAL	932.4526	53			

ROOT MSE	2.85311	R-SQUARED	0.7730
DEP MEAN	11.33185	ADJ R-SQUARED	0.5373
C.V.	25.18%		

Predicted Residual Sum of Squares (PRESS) = 1069.0864

Results of Cubic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	873.7413	45	19.41647	2.646	0.0732
ERROR	58.7113	8	7.33891		
COR TOTAL	932.4526	53			

ROOT MSE	2.70904	R-SQUARED	0.9370
----------	---------	-----------	--------

DEP MEAN 11.33195 ADJ R-SQUARED 0.5829
C.V. 23.91%

Predicted Residual Sum of Squares (PRESS) = 12564.5901

ANOVA Summary of models fit

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
LINEAR	469.2246	6	78.2041	7.935	0.0001
QUADRATIC	251.5824	21	11.9801	1.472	0.1737
CUBIC	152.9343	18	8.4964	1.158	0.4370
ERROR	58.7113	8	7.3389		
COR TOTAL	932.4526	53			

Lack of Fit tests

MODEL	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
LINEAR	453.5427	42	10.7986	5.575	0.0311
QUADRATIC	201.9603	21	9.6172	4.965	0.0417
CUBIC	49.0260	3	16.3420	8.436	0.0211
PURE ERP	9.6853	5	1.9371		

Response: ProdAsh: File = INFLT

Run on 11/01/90 at 14:08:07

VAR	VARIABLE	UNITS	-1 LEVEL	+1 LEVEL
X1	Feed Rate	(gpm)	-1.000	1.000
X2	Wash Water	(gpm)	-1.000	1.000
X3	Air Rate	(scfm)	-1.000	1.000
X4	Frother	(lb/ton)	-1.000	1.000
X5	Diesel	(lb/ton)	-1.000	1.000
X6	Froth Hite	(inches)	-1.000	1.000

Results of Cubic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	873.7413	45	19.41647	2.646	0.0732
ERROR	58.7113	8	7.33891		
COR TOTAL	932.4526	53			

ROOT MSE 2.70904 R-SQUARED 0.9370
DEP MEAN 11.33185 ADJ R-SQUARED 0.5829
C.V. 23.91%

Predicted Residual Sum of Squares (PRESS) = 12564.5901

VARIABLE	PARAMETER ESTIMATE	DF	STANDARD ERROR	t FOR H0 PARAMETER=0	PROB > t
Intercept	9.84333	1	1.10596	8.900	

X1	-1.56375	1	0.95779	-1.633	0.1412
X2	1.23875	1	0.95779	1.293	0.2320
X3	1.42625	1	0.95779	1.489	0.1748
X4	0.97125	1	0.95779	1.014	0.3402
X5	1.27375	1	0.95779	1.330	0.2202
X6	-1.82125	1	0.95779	-1.902	0.0937
X1*X1	1.50903	1	0.84469	1.786	0.1118
X2*X2	-0.00264	1	0.84469	-3.12E-03	0.9976
X3*X3	0.42069	1	0.84469	0.4980	0.6319
X4*X4	-1.83347	1	0.84469	-2.171	0.0618
X5*X5	0.94486	1	0.84469	1.119	0.2958
X6*X6	2.31069	1	0.84469	2.736	0.0256
X1*X2	1.01375	1	0.95779	1.058	0.3208
X1*X3	-0.07625	1	0.95779	-7.96E-02	0.9385
X1*X4	-0.79750	1	0.67726	-1.178	0.2728
X1*X5	-0.08375	1	0.95779	-8.74E-02	0.9325
X1*X6	1.25375	1	0.95779	1.309	0.2269
X2*X3	-0.27125	1	0.95779	-0.2932	0.7842
X2*X4	0.33875	1	0.95779	0.3537	0.7327
X2*X5	-0.27250	1	0.67726	-0.4024	0.6980
X2*X6	-0.98125	1	0.95779	-0.9201	0.3844
X3*X4	-0.80375	1	0.95779	-0.8392	0.4257
X3*X5	-0.23375	1	0.95779	-0.2441	0.8133
X3*X6	-1.54875	1	0.67726	-2.287	0.0515
X4*X5	0.69625	1	0.95779	0.7269	0.4880
X4*X6	-1.16625	1	0.95779	-1.218	0.2581
X5*X6	-1.57125	1	0.95779	-1.599	0.1485
X1*X1*X1	ALIASED	0			
X2*X2*X2	ALIASED	0			
X3*X3*X3	ALIASED	0			
X4*X4*X4	ALIASED	0			
X5*X5*X5	ALIASED	0			
X6*X6*X6	ALIASED	0			
X1*X1*X2	-2.04500	1	1.35452	-1.510	0.1695
X1*X1*X3	2.28750	1	1.35452	1.689	0.1297
X1*X1*X4	1.03500	1	1.35452	0.7641	0.4667
X1*X1*X5	-0.62000	1	1.35452	-0.4577	0.6593
X1*X1*X6	-3.03500	1	1.35452	-2.241	0.0554
X2*X2*X3	1.29500	1	1.35452	0.9561	0.3670
X2*X2*X4	-0.58500	1	1.35452	-0.4319	0.6772
X2*X2*X5	ALIASED	0			
X2*X2*X6	-0.42750	1	1.35452	-0.3156	0.7604
X3*X3*X4	ALIASED	0			
X3*X3*X5	-2.12750	1	1.35452	-1.571	0.1549
X3*X3*X6	ALIASED	0			
X4*X4*X5	ALIASED	0			
X4*X4*X6	ALIASED	0			
X5*X5*X6	ALIASED	0			
X1*X2*X2	0.93000	1	1.35452	0.6866	0.5117
X1*X3*X3	0.13250	1	1.35452	9.78E-02	0.9245
X1*X4*X4	ALIASED	0			
X1*X5*X5	ALIASED	0			
X1*X6*X6	ALIASED	0			
X2*X3*X3	-0.77000	1	1.35452	-0.5685	0.5853
X2*X4*X4	ALIASED	0			
X2*X5*X5	ALIASED	0			
X2*X6*X6	ALIASED	0			
X3*X4*X4	ALIASED	0			
X3*X5*X5	ALIASED	0			
X3*X6*X6	ALIASED	0			

X4*X5*X5	ALIASED	0			
X4*X6*X6	ALIASED	0			
X5*X6*X6	ALIASED	0			
X1*X2*X3	ALIASED	0			
X1*X2*X4	0.54375	1	0.95779	0.5677	0.5858
X1*X2*X5	ALIASED	0			
X1*X2*X6	ALIASED	0			
X1*X3*X4	ALIASED	0			
X1*X3*X5	ALIASED	0			
X1*X3*X6	-0.38625	1	0.95779	-0.4033	0.6973
X1*X4*X5	-0.76125	1	0.95779	-0.7948	0.4497
X1*X4*X6	ALIASED	0			
X1*X5*X6	ALIASED	0			
X2*X3*X4	ALIASED	0			
X2*X3*X5	-0.57625	1	0.95779	-0.6016	0.5641
X2*X3*X6	ALIASED	0			
X2*X4*X5	ALIASED	0			
X2*X4*X6	ALIASED	0			
X2*X5*X6	-2.01375	1	0.95779	-2.102	0.0687
X3*X4*X5	ALIASED	0			
X3*X4*X6	-0.32125	1	0.95779	-0.3354	0.7459
X3*X5*X6	ALIASED	0			
X4*X5*X6	ALIASED	0			

SIG ERROR 0.36865

Obs Ord	ACTUAL VALUE	PREDICTED VALUE	RESIDUAL	LEVER	STUDENT RESID	COOK'S DIST	t VALUE	Run Ord
1	10.20000	9.54625	0.65375	0.938	0.965	0.304	2.566	54
2	8.29000	8.93375	-0.65375	0.938	-0.965	0.304	-2.566	49
3	6.97000	6.31625	0.65375	0.938	0.965	0.304	2.566	9
4	6.93000	7.58375	-0.65375	0.938	-0.965	0.304	-2.566	5
5	13.74000	14.39375	-0.65375	0.938	-0.965	0.304	-2.566	14
6	9.07000	8.41625	0.65375	0.938	0.965	0.304	2.566	15
7	9.69000	10.34375	-0.65375	0.938	-0.965	0.304	-2.566	33
8	11.25000	10.59625	0.65375	0.938	0.965	0.304	2.566	44
9	7.60000	8.66875	-1.06875	0.938	-1.578	0.812	-3.704	16
10	10.61000	9.54125	1.06875	0.938	1.578	0.812	3.704	41
11	12.90000	13.96875	-1.06875	0.938	-1.578	0.812	-3.704	27
12	17.13000	16.06125	1.06875	0.937	1.578	0.812	3.704	39
13	7.89000	6.82125	1.06875	0.937	1.578	0.812	3.704	29
14	7.84000	8.90875	-1.06875	0.938	-1.578	0.812	-3.704	28
15	14.56000	13.49125	1.06875	0.937	1.578	0.812	3.704	46
16	11.12000	12.18875	-1.06875	0.937	-1.578	0.812	-3.704	13
17	8.19000	6.96750	1.22250	0.937	1.805	1.062	3.931	11
18	12.66000	13.88250	-1.22250	0.937	-1.805	1.062	-3.931	40
19	13.43000	12.20750	1.22250	0.937	1.805	1.062	3.931	43
20	15.97000	17.19250	-1.22250	0.937	-1.805	1.062	-3.931	7
21	6.89000	8.11250	-1.22250	0.937	-1.805	1.062	-3.931	10
22	11.34000	10.11750	1.22250	0.937	1.805	1.062	3.931	32
23	9.75000	9.97250	-1.22250	0.937	-1.805	1.062	-3.931	52
24	8.70000	7.47750	1.22250	0.937	1.805	1.062	3.931	3
25	9.29000	9.94375	-0.65375	0.937	-0.965	0.304	-2.566	42
26	7.71000	7.05625	0.65375	0.937	0.965	0.304	2.566	50
27	13.29000	12.63625	0.65375	0.937	0.965	0.304	2.566	34
28	8.95000	9.60375	-0.65375	0.937	-0.965	0.304	-2.566	17
29	7.85000	8.50375	-0.65375	0.937	-0.965	0.304	-2.566	4
30	8.98000	8.32625	0.65375	0.937	0.965	0.304	2.566	31
31	17.68000	17.02625	0.65375	0.937	0.965	0.304	2.566	23

32	9.95000	10.61375	-0.65375	0.937	-0.965	0.304	-2.566	51
33	13.23000	12.16125	1.06875	0.937	1.578	0.812	3.704	2
34	11.85000	12.91875	-1.06875	0.937	-1.578	0.812	-3.704	48
35	13.22000	14.28875	-1.06875	0.937	-1.578	0.812	-3.704	6
36	23.08000	22.01125	1.06875	0.937	1.578	0.812	3.704	25
37	9.53000	8.46125	1.06875	0.937	1.578	0.812	3.704	35
38	12.68000	13.74875	-1.06875	0.937	-1.578	0.812	-3.704	37
39	11.45000	12.51875	-1.06875	0.937	-1.578	0.812	-3.704	30
40	9.73000	8.66125	1.06875	0.937	1.578	0.812	3.704	53
41	15.45000	16.67250	-1.22250	0.938	-1.805	1.062	-3.931	47
42	9.46000	10.68250	-1.22250	0.938	-1.805	1.062	-3.931	1
43	27.80000	26.57750	1.22250	0.938	1.805	1.062	3.931	21
44	23.05000	21.82750	1.22250	0.938	1.805	1.062	3.931	24
45	8.00000	6.77750	1.22250	0.938	1.805	1.062	3.931	18
46	8.57000	7.34750	1.22250	0.938	1.805	1.062	3.931	45
47	10.81000	12.03250	-1.22250	0.938	-1.805	1.062	-3.931	12
48	9.53000	10.75250	-1.22250	0.938	-1.805	1.062	-3.931	38
49	8.99000	9.84333	-0.85333	0.167	-0.345	0.001	-0.969	8
50	8.46000	9.84333	-1.38333	0.167	-0.559	0.001	-1.551	26
51	10.78000	9.84333	0.93667	0.167	0.379	0.001	1.062	20
52	11.02000	9.84333	1.17667	0.167	0.476	0.001	1.327	22
53	8.36000	9.84333	-1.48333	0.167	-0.600	0.002	-1.658	36
54	11.45000	9.84333	1.60667	0.167	0.650	0.002	1.788	19

Response: Sul. Rel.: File = INPLT

Run on 11/01/90 at 13:37:03

VAR	VARIABLE	UNITS	-1 LEVEL	+1 LEVEL
X1	Feed Rate	(gpm)	-1.000	1.000
X2	Wash Water	(gpm)	-1.000	1.000
X3	Air Rate	(scfm)	-1.000	1.000
X4	Frother	(lb/ton)	-1.000	1.000
X5	Diesel	(lb/ton)	-1.000	1.000
X6	Froth Hite	(inches)	-1.000	1.000

Results of Linear Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	4376.84	6	729.4734	5.059	0.0004
ERROR	6776.71	47	144.1853		
COR TOTAL	11153.55	53			
ROOT MSE	12.0077		R-SQUARED	0.3924	
DEF MEAN	55.6941		ADJ R-SQUARED	0.3149	
C.V.	21.56%				

Predicted Residual Sum of Squares (PRESS) = 8872.01

Results of Quadratic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	7764.48	27	287.5734	2.206	0.0236
ERROR	3389.07	26	130.3489		
COR TOTAL	11153.55	53			
ROOT MSE	11.4170		R-SQUARED	0.6961	
DEF MEAN	55.6941		ADJ R-SQUARED	0.3806	
C.V.	20.50%				

Predicted Residual Sum of Squares (PRESS) = 15365.63

Results of Cubic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	9838.66	45	218.6369	1.330	0.3540
ERROR	1314.89	8	164.3612		
COR TOTAL	11153.55	53			
ROOT MSE	12.6203		R-SQUARED	0.8821	

MEP MEAN	55.6941	ADJ R-SQUARED	0.2190
C.V.	23.023		

Predicted Residual Sum of Squares (PRESS) = 179178.44

ANOVA Summary of models fit

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
LINEAR	4376.84	6	729.47	5.059	0.0004
QUADRATIC	3387.64	21	161.32	1.238	0.3000
CUBIC	2074.18	18	115.23	0.7011	0.7482
ERROR	1314.89	8	164.36		
CDR TOTAL	11153.55	53			

Lack of Fit tests

MODEL	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
LINEAR	6158.26	42	146.63	1.185	0.4734
QUADRATIC	2770.62	21	131.93	1.067	0.5229
CUBIC	696.44	3	232.15	1.877	0.2512
PURE ERR	618.45	5	123.69		

Response: Sul. Rej.: File = INFLT

Run on 11/01/90 at 13:38:52

VAR	VARIABLE	UNITS	-1 LEVEL	+1 LEVEL
X1	Feed Rate	(gpm)	-1.000	1.000
X2	Wash Water	(gpm)	-1.000	1.000
X3	Air Rate	(scfm)	-1.000	1.000
X4	Frother	(lb/ton)	-1.000	1.000
X5	Diesel	(lb/ton)	-1.000	1.000
X6	Froth Hite	(inches)	-1.000	1.000

Results of Cubic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	9838.66	45	218.6369	1.330	0.3540
ERROR	1314.89	8	164.3612		
COR TOTAL	11153.55	53			
ROOT MSE	12.8203		R-SQUARED	0.8821	
DEF MEAN	55.6941		ADJ R-SQUARED	0.2190	
C.V.	23.02%				

Predicted Residual Sum of Squares (PRESS) = 179178.44

VARIABLE	PARAMETER ESTIMATE	DF	STANDARD ERROR	t FOR H0 PARAMETER=0	PROB > t
Intercept	64.8917	1	5.2339	12.40	
X1	4.1625	1	4.5327	0.9183	0.3853
X2	-3.3975	1	4.5327	-0.7496	0.4750
X3	0.8025	1	4.5327	0.1770	0.8639
X4	-13.0250	1	4.5327	-2.874	0.0207
X5	2.8400	1	4.5327	0.6266	0.5484
X6	7.9650	1	4.5327	1.757	0.1169
X1*X1	-7.0981	1	3.9974	-1.776	0.1137
X2*X2	-7.2568	1	3.9974	-1.815	0.1070
X3*X3	-2.3618	1	3.9974	-0.5908	0.5709
X4*X4	2.1919	1	3.9974	0.5483	0.5984
X5*X5	-4.3856	1	3.9974	-1.097	0.3045
X6*X6	-1.7843	1	3.9974	-0.4464	0.6672
X1*X2	-0.0612	1	4.5327	-1.35E-02	0.9895
X1*X3	1.2250	1	4.5327	0.2703	0.7938
X1*X4	4.3056	1	3.2051	1.343	0.2160
X1*X5	-6.6625	1	4.5327	-1.470	0.1798
X1*X6	0.1200	1	4.5327	2.65E-02	0.9795
X2*X3	1.0425	1	4.5327	0.2300	0.8239
X2*X4	-5.3712	1	4.5327	-1.185	0.2700
X2*X5	-1.8775	1	3.2051	-0.5858	0.5742
X2*X6	-1.8600	1	4.5327	-0.4104	0.6923
X3*X4	5.0300	1	4.5327	1.110	0.2994
X3*X5	-3.4425	1	4.5327	-0.7595	0.4693
X3*X6	-2.4085	1	3.2051	-0.7515	0.4739
X4*X5	2.3950	1	4.5327	0.5294	0.6116
X4*X6	-7.3575	1	4.5327	-1.623	0.1432

X5*X6	-4.6375	1	4.5327	-1.023	0.3362
X1*X1*X1	ALIASED	0			
X2*X2*X2	ALIASED	0			
X3*X3*X3	ALIASED	0			
X4*X4*X4	ALIASED	0			
X5*X5*X5	ALIASED	0			
X6*X6*X6	ALIASED	0			
X1*X1*X2	10.9137	1	6.4102	1.703	0.1271
X1*X1*X3	-5.7075	1	6.4102	-0.8904	0.3992
X1*X1*X4	8.5250	1	6.4102	1.330	0.2202
X1*X1*X5	-2.2300	1	6.4102	-0.3479	0.7369
X1*X1*X6	-1.3450	1	6.4102	-0.2098	0.8391
X2*X2*X3	-7.4075	1	6.4102	-1.156	0.2812
X2*X2*X4	-3.0438	1	6.4102	-0.4748	0.6476
X2*X2*X5	ALIASED	0			
X2*X2*X6	-1.0775	1	6.4102	-0.1681	0.8707
X3*X3*X4	ALIASED	0			
X3*X3*X5	-1.8900	1	6.4102	-0.2948	0.7756
X3*X3*X6	ALIASED	0			
X4*X4*X5	ALIASED	0			
X4*X4*X6	ALIASED	0			
X5*X5*X6	ALIASED	0			
X1*X2*X2	3.5038	1	6.4102	0.5466	0.5996
X1*X3*X3	4.1800	1	6.4102	0.6521	0.5326
X1*X4*X4	ALIASED	0			
X1*X5*X5	ALIASED	0			
X1*X6*X6	ALIASED	0			
X2*X3*X3	2.5825	1	6.4102	0.4029	0.6976
X2*X4*X4	ALIASED	0			
X2*X5*X5	ALIASED	0			
X2*X6*X6	ALIASED	0			
X3*X4*X4	ALIASED	0			
X3*X5*X5	ALIASED	0			
X3*X6*X6	ALIASED	0			
X4*X5*X5	ALIASED	0			
X4*X6*X6	ALIASED	0			
X5*X6*X6	ALIASED	0			
X1*X2*X3	ALIASED	0			
X1*X2*X4	3.6662	1	4.5327	0.8088	0.4420
X1*X2*X5	ALIASED	0			
X1*X2*X6	ALIASED	0			
X1*X3*X4	ALIASED	0			
X1*X3*X5	ALIASED	0			
X1*X3*X6	2.8025	1	4.5327	0.6183	0.5536
X1*X4*X5	-8.8675	1	4.5327	-1.956	0.0861
X1*X4*X6	ALIASED	0			
X1*X5*X6	ALIASED	0			
X2*X3*X4	ALIASED	0			
X2*X3*X5	0.9600	1	4.5327	0.2118	0.8376
X2*X3*X6	ALIASED	0			
X2*X4*X5	ALIASED	0			
X2*X4*X6	ALIASED	0			
X2*X5*X6	-2.5000	1	4.5327	-0.5516	0.5963
X3*X4*X5	ALIASED	0			
X3*X4*X6	-2.3875	1	4.5327	-0.5267	0.6127
X3*X5*X6	ALIASED	0			
X4*X5*X6	ALIASED	0			

Std EPRDF 1.7446

Job Ord	ACTUAL VALUE	PREDICTED VALUE	RESIDUAL	LEVER	STUDENT RESID	COOK'S DIST	t VALUE	Run Ord
1	40.4100	40.2969	0.1131	0.938	0.035	0.000	0.100	54
2	54.3600	54.4731	-0.1131	0.938	-0.035	0.000	-0.100	49
3	73.6400	73.5269	0.1131	0.938	0.035	0.000	0.100	9
4	72.6800	72.7931	-0.1131	0.938	-0.035	0.000	-0.100	5
5	34.5600	34.6731	-0.1131	0.938	-0.035	0.000	-0.100	14
6	51.5200	51.4069	0.1131	0.938	0.035	0.000	0.100	15
7	31.6400	31.7531	-0.1131	0.938	-0.035	0.000	-0.100	33
8	63.0200	62.9069	0.1131	0.938	0.035	0.000	0.100	44
9	54.6700	52.1200	2.5500	0.938	0.796	0.206	2.159	16
10	51.5300	54.0800	-2.5500	0.938	-0.796	0.206	-2.159	41
11	48.1800	45.6300	2.5500	0.938	0.796	0.206	2.159	27
12	45.3700	47.9200	-2.5500	0.937	-0.796	0.206	-2.159	39
13	64.0300	66.5800	-2.5500	0.937	-0.796	0.206	-2.159	29
14	59.7400	57.1900	2.5500	0.938	0.796	0.206	2.159	28
15	39.9300	42.4800	-2.5500	0.937	-0.796	0.206	-2.159	46
16	43.6500	41.1000	2.5500	0.937	0.796	0.206	2.159	13
17	70.9300	64.8463	6.0838	0.937	1.898	1.175	3.980	11
18	50.3500	56.4337	-6.0838	0.937	-1.898	1.175	-3.980	40
19	44.7600	38.6762	6.0838	0.937	1.898	1.175	3.980	43
20	53.8500	59.9338	-6.0838	0.937	-1.898	1.175	-3.980	7
21	39.4500	95.5338	-6.0838	0.937	-1.898	1.175	-3.980	10
22	93.1200	87.0362	6.0838	0.937	1.898	1.175	3.980	32
23	43.4000	49.4838	-6.0838	0.937	-1.898	1.175	-3.980	52
24	57.6400	51.5562	6.0838	0.937	1.898	1.175	3.980	3
25	64.1200	64.2331	-0.1131	0.937	-0.035	0.000	-0.100	42
26	59.6500	59.5369	0.1131	0.937	0.035	0.000	0.100	50
27	24.2100	24.0969	0.1131	0.937	0.035	0.000	0.100	34
28	71.9800	72.0931	-0.1131	0.937	-0.035	0.000	-0.100	17
29	56.1400	56.2531	-0.1131	0.937	-0.035	0.000	-0.100	4
30	60.4900	60.3769	0.1131	0.937	0.035	0.000	0.100	31
31	61.2800	61.1669	0.1131	0.937	0.035	0.000	0.100	23
32	46.9300	47.0431	-0.1131	0.937	-0.035	0.000	-0.100	51
33	36.7100	39.2600	-2.5500	0.937	-0.796	0.206	-2.159	2
34	37.4900	34.9400	2.5500	0.937	0.796	0.206	2.159	48
35	55.5200	52.9700	2.5500	0.937	0.796	0.206	2.159	6
36	48.5900	51.1400	-2.5500	0.937	-0.796	0.206	-2.159	25
37	58.4800	61.0300	-2.5500	0.937	-0.796	0.206	-2.159	35
38	61.8200	59.2700	2.5500	0.937	0.796	0.206	2.159	37
39	68.7400	66.1900	2.5500	0.937	0.796	0.206	2.159	30
40	44.3700	46.9200	-2.5500	0.937	-0.796	0.206	-2.159	53
41	33.6400	39.7238	-6.0838	0.938	-1.898	1.175	-3.980	47
42	53.2400	59.3238	-6.0838	0.938	-1.898	1.175	-3.980	1
43	43.9700	37.8862	6.0838	0.938	1.898	1.175	3.980	21
44	57.2600	51.1762	6.0838	0.938	1.898	1.175	3.980	24
45	69.2300	63.1462	6.0838	0.938	1.898	1.175	3.980	18
46	78.1000	72.0162	6.0838	0.938	1.898	1.175	3.980	45
47	34.3800	40.4638	-6.0838	0.938	-1.898	1.175	-3.980	12
48	59.3600	65.4438	-6.0838	0.938	-1.898	1.175	-3.980	38
49	63.5000	64.8917	3.6083	0.167	0.308	0.000	0.867	8
50	60.4400	64.8917	-4.4517	0.167	-0.380	0.001	-1.066	26
51	64.9700	64.8917	0.0783	0.167	0.007	0.000	0.019	20
52	75.7600	64.8917	10.8683	0.167	0.929	0.004	2.481	22
53	45.4100	64.8917	-19.4817	0.167	-1.665	0.012	-3.807	36
54	74.2700	64.8917	9.3783	0.167	0.801	0.003	2.174	19

Response: SeComb: File = INPLT

Run on 11/01/90 at 13:51:14

VAR	VARIABLE	UNITS	-1 LEVEL	+1 LEVEL
X1	Feed Rate	(gpm)	-1.000	1.000
X2	Wash Water	(gpm)	-1.000	1.000
X3	Air Rate	(scfm)	-1.000	1.000
X4	Frother	(lb/ton)	-1.000	1.000
X5	Diesel	(lb/ton)	-1.000	1.000
X6	Froth Hite	(inches)	-1.000	1.000

Results of Linear Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	3080.399	6	513.39983	3.806	0.0036
ERROR	6339.908	47	134.89165		
COR TOTAL	9420.307	53			
ROOT MSE	11.61429		R-SQUARED	0.3270	
DEF MEAN	43.40722		ADJ R-SQUARED	0.2411	
C.V.	26.76%				

Predicted Residual Sum of Squares (PRESS) = 8392.980

Results of Quadratic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	6065.757	27	224.65767	1.741	0.0807
ERROR	3354.550	26	129.02113		
COR TOTAL	9420.307	53			
ROOT MSE	11.35875		R-SQUARED	0.6439	
DEF MEAN	43.40722		ADJ R-SQUARED	0.2741	
C.V.	26.17%				

Predicted Residual Sum of Squares (PRESS) = 15483.700

Results of Cubic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	3272.536	45	183.98969	1.290	0.3735
ERROR	1140.771	8	142.59632		
COR TOTAL	9420.307	53			
ROOT MSE	11.94137		R-SQUARED	0.8789	

DEF MEAN 43.40722 ADJ R-SQUARED 0.1977
C.V. 27.51%

Predicted Residual Sum of Squares (PRESS) = 154676.777

ANOVA Summary of models fit

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
LINEAR	3080.399	6	513.400	3.806	0.0036
QUADRATIC	2985.358	21	142.160	1.102	0.4027
CUBIC	2213.779	18	122.988	0.8625	0.6260
ERROR	1140.771	8	142.596		
TOTAL	9420.307	53			

Lack of Fit tests

MODEL	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
LINEAR	5800.308	42	138.103	1.280	0.4312
QUADRATIC	2814.950	21	134.045	1.242	0.4412
CUBIC	601.171	3	200.390	1.857	0.2544
PURE ERR	539.600	5	107.920		

Response: SeComb: File = INFLT

Run on 11/01/90 at 13:52:28

VAR	VARIABLE	UNITS	-1 LEVEL	+1 LEVEL
X1	Feed Rate	(gpm)	-1.000	1.000
X2	Wash Water	(gpm)	-1.000	1.000
X3	Air Rate	(scfm)	-1.000	1.000
X4	Frother	(lb/ton)	-1.000	1.000
X5	Diesel	(lb/ton)	-1.000	1.000
X6	Froth Hite	(inches)	-1.000	1.000

Results of Cubic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	3279.536	45	183.98969	1.290	0.3735
ERROR	1140.771	8	142.59632		
COR TOTAL	4420.307	53			

ROOT MSE	11.94137	R-SQUARED	0.8789
DEF MEAN	43.40722	ADJ R-SQUARED	0.1977
C.V.	27.51%		

Predicted Residual Sum of Squares (PRESS) = 154676.777

VARIABLE	PARAMETER ESTIMATE	DF	STANDARD ERROR	t FOR H0 PARAMETER=0	PROB > t
Intercept	37.23833	1	4.87504	7.639	
X1	-2.45375	1	4.22191	-0.5812	0.5771
X2	2.41375	1	4.22191	0.5717	0.5832
X3	-2.42375	1	4.22191	-0.5741	0.5817
X4	10.73625	1	4.22191	2.543	0.0345
X5	-0.43375	1	4.22191	-0.1027	0.9207
X6	-5.46125	1	4.22191	-1.294	0.2319
X1*X1	6.40167	1	3.72338	1.719	0.1239
X2*X2	6.30208	1	3.72338	1.693	0.1290
X3*X3	0.65000	1	3.72338	0.1746	0.8658
X4*X4	-2.58958	1	3.72338	-0.6955	0.5064
X5*X5	3.54833	1	3.72338	0.9530	0.3685
X6*X6	-0.43250	1	3.72338	-0.1162	0.9104
X1*X2	-0.45500	1	4.22191	-0.1078	0.9168
X1*X3	0.13500	1	4.22191	3.20E-02	0.9753
X1*X4	-3.35562	1	2.98534	-1.124	0.2936
X1*X5	3.42125	1	4.22191	0.8104	0.4412
X1*X6	-2.71750	1	4.22191	-0.6437	0.5378
X2*X3	1.57125	1	4.22191	0.3722	0.7194
X2*X4	3.53750	1	4.22191	0.8379	0.4264
X2*X5	3.36875	1	2.98534	1.128	0.2918
X2*X6	2.46125	1	4.22191	0.5830	0.5760
X3*X4	-3.31875	1	4.22191	-0.7861	0.4545
X3*X5	3.54625	1	4.22191	0.8400	0.4253
X3*X6	3.05938	1	2.98534	1.025	0.3354
X4*X5	-3.74375	1	4.22191	-0.8867	0.4011
X4*X6	3.49875	1	4.22191	2.013	0.0789

X5*X6	3.32375	1	4.22191	0.7873	0.4538
X1*X1*X1	ALIASED	0			
X2*X2*X2	ALIASED	0			
X3*X3*X3	ALIASED	0			
X4*X4*X4	ALIASED	0			
X5*X5*X5	ALIASED	0			
X6*X6*X6	ALIASED	0			
X1*X1*X2	-9.50875	1	5.97069	-1.593	0.1499
X1*X1*X3	7.89375	1	5.97069	1.322	0.2227
X1*X1*X4	-5.90000	1	5.97069	-0.9882	0.3520
X1*X1*X5	1.18750	1	5.97069	0.1989	0.8473
X1*X1*X6	1.81375	1	5.97069	0.3038	0.7690
X2*X2*X3	8.81750	1	5.97069	1.477	0.1780
X2*X2*X4	2.15375	1	5.97069	0.3607	0.7276
X2*X2*X5	ALIASED	0			
X2*X2*X6	-1.61500	1	5.97069	-0.2705	0.7936
X3*X3*X4	ALIASED	0			
X3*X3*X5	1.29500	1	5.97069	0.2169	0.8337
X3*X3*X6	ALIASED	0			
X4*X4*X5	ALIASED	0			
X4*X4*X6	ALIASED	0			
X5*X5*X6	ALIASED	0			
X1*X2*X2	-4.83375	1	5.97069	-0.8096	0.4416
X1*X3*X3	-4.44875	1	5.97069	-0.7451	0.4775
X1*X4*X4	ALIASED	0			
X1*X5*X5	ALIASED	0			
X1*X6*X6	ALIASED	0			
X2*X3*X3	-1.80750	1	5.97069	-0.3027	0.7698
X2*X4*X4	ALIASED	0			
X2*X5*X5	ALIASED	0			
X2*X6*X6	ALIASED	0			
X3*X4*X4	ALIASED	0			
X3*X5*X5	ALIASED	0			
X3*X6*X6	ALIASED	0			
X4*X5*X5	ALIASED	0			
X4*X6*X6	ALIASED	0			
X5*X6*X6	ALIASED	0			
X1*X2*X3	ALIASED	0			
X1*X2*X4	-5.12750	1	4.22191	-1.214	0.2592
X1*X2*X5	ALIASED	0			
X1*X2*X6	ALIASED	0			
X1*X3*X4	ALIASED	0			
X1*X3*X5	ALIASED	0			
X1*X3*X6	-3.07000	1	4.22191	-0.7272	0.4879
X1*X4*X5	9.17375	1	4.22191	2.173	0.0615
X1*X4*X6	ALIASED	0			
X1*X5*X6	ALIASED	0			
X2*X3*X4	ALIASED	0			
X2*X3*X5	-1.55625	1	4.22191	-0.3686	0.7220
X2*X3*X6	ALIASED	0			
X2*X4*X5	ALIASED	0			
X2*X4*X6	ALIASED	0			
X2*X5*X6	3.76625	1	4.22191	0.8921	0.3984
X3*X4*X5	ALIASED	0			
X3*X4*X6	1.75875	1	4.22191	0.4166	0.6879
X3*X5*X6	ALIASED	0			
X4*X5*X6	ALIASED	0			

Std. ERROR 1.62501

Obs Ord	ACTUAL VALUE	PREDICTED VALUE	RESIDUAL	LEVER	STUDENT RESID	COOK'S DIST	t VALUE	Run Ord
1	58.79000	59.59937	-0.80937	0.938	-0.271	0.024	-0.763	54
2	43.20000	42.39062	0.80938	0.938	0.271	0.024	0.763	49
3	28.18000	28.98937	-0.80937	0.938	-0.271	0.024	-0.763	9
4	31.28000	30.47062	0.80938	0.938	0.271	0.024	0.763	5
5	63.77000	62.96062	0.80938	0.938	0.271	0.024	0.763	14
6	52.03000	52.83938	-0.80937	0.938	-0.271	0.024	-0.763	15
7	67.82000	67.01062	0.80938	0.938	0.271	0.024	0.763	33
8	33.75000	34.55937	-0.80937	0.938	-0.271	0.024	-0.763	44
9	48.82000	49.92000	-1.10000	0.938	-0.368	0.044	-1.033	16
10	39.24000	38.14000	1.10000	0.938	0.368	0.044	1.033	41
11	48.26000	49.36000	-1.10000	0.938	-0.368	0.044	-1.033	27
12	51.19000	50.09000	1.10000	0.937	0.368	0.044	1.033	39
13	35.80000	34.70000	1.10000	0.937	0.368	0.044	1.033	29
14	41.52000	42.62000	-1.10000	0.938	-0.368	0.044	-1.033	28
15	55.65000	54.55000	1.10000	0.937	0.368	0.044	1.033	46
16	61.43000	62.53000	-1.10000	0.937	-0.368	0.044	-1.033	13
17	32.52000	38.49563	-5.97563	0.937	-2.002	1.307	-4.000	11
18	43.66000	37.68437	5.97563	0.937	2.002	1.307	4.000	40
19	47.15000	53.12563	-5.97563	0.937	-2.002	1.307	-4.000	43
20	37.98000	32.00437	5.97563	0.937	2.002	1.307	4.000	7
21	13.95000	7.97437	5.97563	0.937	2.002	1.307	4.000	10
22	6.39000	12.36563	-5.97563	0.937	-2.002	1.307	-4.000	32
23	55.54000	49.56437	5.97563	0.937	2.002	1.307	4.000	52
24	41.74000	47.71563	-5.97563	0.937	-2.002	1.307	-4.000	3
25	28.42000	28.61062	0.80938	0.937	0.271	0.024	0.763	42
26	41.11000	41.91937	-0.80937	0.937	-0.271	0.024	-0.763	50
27	70.02000	70.82938	-0.80937	0.937	-0.271	0.024	-0.763	34
28	34.83000	34.02062	0.80938	0.937	0.271	0.024	0.763	17
29	49.92000	49.11062	0.80938	0.937	0.271	0.024	0.763	4
30	38.60000	39.40937	-0.80937	0.937	-0.271	0.024	-0.763	31
31	38.85000	39.65937	-0.80937	0.937	-0.271	0.024	-0.763	23
32	54.04000	53.23062	0.80938	0.937	0.271	0.024	0.763	51
33	58.24000	57.14000	1.10000	0.937	0.368	0.044	1.033	2
34	56.74000	57.84000	-1.10000	0.937	-0.368	0.044	-1.033	48
35	49.32000	50.42000	-1.10000	0.937	-0.368	0.044	-1.033	6
36	50.63000	49.53000	1.10000	0.937	0.368	0.044	1.033	25
37	40.05000	38.95000	1.10000	0.937	0.368	0.044	1.033	35
38	33.33000	34.43000	-1.10000	0.937	-0.368	0.044	-1.033	37
39	29.36000	30.46000	-1.10000	0.937	-0.368	0.044	-1.033	30
40	55.58000	54.48000	1.10000	0.937	0.368	0.044	1.033	53
41	58.46000	52.48437	5.97563	0.938	2.002	1.307	4.000	47
42	43.68000	37.70437	5.97563	0.938	2.002	1.307	4.000	1
43	44.92000	50.89562	-5.97563	0.938	-2.002	1.307	-4.000	21
44	42.96000	48.93563	-5.97563	0.938	-2.002	1.307	-4.000	24
45	32.39000	38.36563	-5.97563	0.938	-2.002	1.307	-4.000	18
46	19.02000	24.99563	-5.97563	0.938	-2.002	1.307	-4.000	45
47	67.27000	61.29437	5.97563	0.938	2.002	1.307	4.000	12
48	42.16000	36.18437	5.97563	0.938	2.002	1.307	4.000	38
49	38.49000	37.23833	1.25167	0.167	0.115	0.000	0.324	8
50	41.78000	37.23833	4.54167	0.167	0.417	0.001	1.166	26
51	35.40000	37.23833	-1.83833	0.167	-0.169	0.000	-0.476	20
52	25.12000	37.23833	-12.11833	0.167	-1.112	0.005	-2.891	22
53	54.24000	37.23833	17.00167	0.167	1.560	0.011	3.680	36
54	22.40000	37.23833	-9.83833	0.167	-0.811	0.003	-2.197	19

Appendix 6: Response surface plots for the 30-inch column parametric test program

Appendix 7: Ladder logic program for column control

Rung #000

FREE RUNNING
TIMER
T4:1

T4:1
DN

[0]

T4:1.DN - -] [- - File #2 - 3,6
-]/[- - File #2 - 0

FREE RUNNING
TIMER
T4:1

---TON-----+
+TIMER ON DELAY +-(EN)-+
|TIMER: T4:1|
|BASE (SEC): 1.0+-(DN)|
|PRESET: 1|
|ACCUM: 0|
+-----+

Rung #001

AUTO START
FROM PANELVIEW
AUTO_START

I:10

AUTO STOP FROM
PANELVIEW
PANELVIEW_STOP

I:10

START COUNTER
FOR COLUMN
START_CTU

C5:1

AUTO START BIT

B3

+-----] [------] [------] [------] ()-----+
| 00 | | 01 | | DN | | 1 |
+-----+

AUTO START BIT
B3

+-----] [------+
| 1 |
+-----+

[1]

B3/1 - -] [- - File #2 - 1,3,5,7,9,11,14,15,17,18,20,21,23
-() - - File #2 - 1

Rung #002

START COUNTER
FOR COLUMN
START_CTU
C5:1

START COUNTER
FOR COLUMN
START_CTU
C5:1

+-----] [------] [RES]-----+
| DN |
+-----+

[2]

C5:1 - CTU - File #2 - 3
C5:1.ACC - GRT - File #2 - 7, 9, 11, 14, 17, 20,
23
C5:1.DN - -] [- - File #2 - 2
-]/[- - File #2 - 1

AUTO STOP
STORAGE BIT
AUTO_STOP
B3

+-----] [------+
| 2 |
+-----+

[4]

Rung #003

FREE RUNNING
TIMER
T4:1

AUTO START BIT

T4:1

B3

+-----] [------] [------] +-----+
| DN | | 1 |
+-----+

[0]

[1]

START COUNTER
FOR COLUMN
START_CTU

---CTU-----+
+COUNT UP +-(CU)-+
|COUNTER: C5:1|
|PRESET: 40+-(DN)|
|ACCUM: 0|
+-----+

C5:1 - CTU - File #2 - 3
 RES - File #2 - 2
 C5:1.ACC - GRT - File #2 - 7,9,11,14,17,20,23
 C5:1.DN - -] [- - File #2 - 2
 -]/[- - File #2 - 1

Rung #004

AUTO STOP FROM PANELVIEW PANELVIEW_STOP I:10 -] [- 01	AUTO START FROM PANELVIEW AUTO_START I:10 -]/[- 00	COUNTER RES. FOR AUTO STOP STOP_RES C5:2 -]/[- DN	AUTO STOP STORAGE BIT AUTO_STOP B3 -] [- 2
[5]			
AUTO STOP STORAGE BIT AUTO_STOP B3 -] [- 2			
[4]			

C5:2 - -] [- - File #2 - 2,6
 -]/[- - File #2 - 7,9,11,14,17,20,23
 -] [- - File #2 - 4

Rung #005

COUNTER RES. FOR AUTO STOP STOP_RES C5:2 -] [- DN	COUNTER RES. FOR AUTO STOP STOP_RES C5:2 -] [- DN
[5]	
C5:2 - CTU - File #2 - 6 C5:2.ACC - LES - File #2 - 7, 9, 11, 14, 17, 20, 23 C5:2.DN - -] [- - File #2 - 5 -]/[- - File #2 - 4	
AUTO START BIT B3 -] [- 1	
[1]	

Rung #006

FREE RUNNING TIMER T41 T4:1 -] [- DN	AUTO STOP STORAGE BIT AUTO_STOP B3 -] [- 2	COUNTER RES. FOR AUTO STOP STOP_RES C5:2 -] [- DN
[0]		[4]
FREE RUNNING TIMER T41 T4:1 -] [- DN		COUNTER RES. FOR AUTO STOP STOP_RES C5:2 -] [- DN
AUTO STOP STORAGE BIT AUTO_STOP B3 -] [- 2		COUNTER RES. FOR AUTO STOP STOP_RES C5:2 -] [- DN
[0]		[4]

C5:2 - CTU - File #2 - 6
 RES - File #2 - 5
 C5:2.ACC - LES - File #2 - 7,9,11,14,17,20,23
 C5:2.DN - -] [- - File #2 - 5
 -]/[- - File #2 - 4

Rung #007 AIR COMPRESSOR

Rung #008

Runa Hood

AUTO START BIT	START COUNTER FOR COLUMN START_STU	WASH WATER MANUAL STOP FROM PANELVIEW WASH-MAN-STOP	AUTO STOP STORAGE BIT AUTO_STOP	WASH WATER VALVE OPEN CR2
83	+-GRT-----+	I:11	83	0:04
1	GREATER THAN (A>B)	01	2	01
(1)	SOURCE A: C5:1.ACC		(4)	
	SOURCE B:			
	C5:1.ACC - (3)			
			COUNTER RES. FOR AUTO STOP STOP_RES	WASH WATER OUTPUT FROM PANELVIEW PAN_WASH
			+-LES-----+	0:11
WASH WATER MANUAL START FROM PANELVIEW WASH-MAN			++LESS THAN (A<B) ++	02
I:11			SOURCE A: C5:2.ACC	
			419	
			SOURCE B: 1801	
			1801	
			C5:2.ACC - (6)	
00				
WASH WATER VALVE OPEN CR2				
0:04				
01				
(9)				

Rung #010

WASH WATER OUT OF INTERLOCK SELECT FROM PANELVIEW WASH_W_OUT_IL_P I:10	WASH WATER IN INTERLOCK SELECT FROM PANELVIEW WASH_W_IN_IL_PV I:12	WASH WATER OUT OF INTERLOCK B3
12	02	19
WASH WATER OUT OF INTERLOCK B3		WASH WATER VALV OUT OF INTERLOC TO PANELVIEW WASH_W_OUT_PV O:10
19		01

242

Rung #011

AIR VALVE

0:004/02 - -] [- - File #2 - 11,15
 -() - - File #2 - 11

Rung #012

B3/3 - -] [- - File #2 - 11

Rung NO13

AIR VALVE OUT OF INTERLOCK SELECT PANELVIEW AIR_V_OUT_IL_PV I:10	AIR VALVE IN INTERLOCK SELECT PANELVIEW AIR_V_IN_IL_PV I:12	AIR VALVE OUT OF INTERLOCK AIR_V_OUT_IL B3
---	--	--

[13]

B3/17 - -] [- - File #2 - - 13,13
-() - - File #2 - - 13.

Rung NO14

FEED VALVE

AUTO START BIT B3	START COUNTER FOR COLUMN START_CTS	MANUAL CLOSE FEED VALVE FROM PANELVIEW FEED-CLOSE-MAN I:11	FEED VALVE INTERLOCK VERIFY FEED_V_IV B3	AUTO STOP STORAGE BIT AUTO_STOP B3	FEED VALVE OPEN CR4 D:04
----------------------	--	--	--	---	-----------------------------------

FEED VALVE
OPEN
CR4

D:04

03

[14]
MANUAL START
FOR FEED VALVE
FROM PANELVIEW
FEED-OPEN-MAN
I:11

15

COUNTER RES.
FOR AUTO STOP
STOP_RES

LESS THAN (A/B)

SOURCE A: C5:2.ACC
419

SOURCE B: 1

C5:2.ACC - [6]

FEED OUTPUT
FOR PANELVIEW
FEED_OUT
D:11

00

D:004/03 - -] [- - File #2 - - 14,19,21
-() - - File #2 - - 14

Rung #015

Rung #016

COLLECTOR PUMP

SECRET NO 19

```
COLLECTOR_PUMP
OUT_OF
INTERLOCK_BIT
COLLECT_OUT_IL
BC
```

1:12

61

05

22
COLLECTOR PUMP
OUT OF INTERLOC
TO PANELVIEW
COLLECT_OUT_PV
0:10

١٧٤

0:10

$$+ \dots +] \quad [$$

()

22

04

[19]

EC/22 - -] [- - File #2 - 19,21

- () - - File #2 - 19

Rung #020

FROTHER PUMP

AUTO START BIT	START COUNTER FOR COLUMN START_CYU	FROTHER PUMP MANUAL STOP FROM PANELVIEW FROT-STOP-MAN	FROTHER PUMP INTERLOCK VERIFY FROT-PUMP_IV	AUTO STOP STORAGE BIT AUTO_STOP	FROTHER PUMP START CR5
B3	+-GRY-----+	I:11	B3	B3	0:04
1	GREATER THAN (A>B)	11	16	2	04
(1)	SOURCE A: C5:1.ACC		[21]	[4]	
	SOURCE B: 35				
	35				
	C5:1.ACC - [3]				
				COUNTER RES.	
				FOR AUTO STOP	0:11
				STOP_RES	()
				+-LES-----+	04
				+-LESS THAN (A<B) +-+	
				SOURCE A: C5:2.ACC	
				419	
				SOURCE B: 1	
				1	
				C5:2.ACC - [6]	
FROTHER PUMP MANUAL START FROM PANELVIEW FROT-START-MAN					
I:11					
10					
FROTHER PUMP START CR5					
0:04					
04					

[20]

0:004/04 - -) [- - File #2 - 18

- () - - File #2 - 20

Rung #021

Rung #022

Run #023

BUBBLE GENERATOR PUMP

0:004/00 - -] [- - File #2 - 15
 -()- - File #2 - 23

Run #024

[24]
 B3/23 - -] [- - File #2 - 15
 -()- - File #2 - 24

Rung #025

```

ANALOG INPUT #1
ANALOG_IN
+---BTR-----+
+BLOCK TRANSFER READ +--(EN)+
|Mod Type:      1771-IFE|
|12 Bit Analog Input+--(DN)|
|Rack:          0|
|Group:         0+--(ER)|
|Module:        0|
|Control Block: N7:1|
|Data File:     N7:11|
|LENGTH:       7|
|Continuous:   Y|
+---+---+

```

Rung #026

```

ANALOG INPUT #1
CONFIGURATION
WRITE
ANALOG_IN_BTW
+---BTW-----+
+BLOCK TRANSFER WRITE +--(EN)+
|Mod Type:      1771-IFE|
|12 Bit Analog Input+--(DN)|
|Rack:          0|
|Group:         0+--(ER)|
|Module:        0|
|Control Block: N7:6|
|Data File:     N7:31|
|LENGTH:       11|
|Continuous:   Y|
+---+---+

```

Rung #027

```

MAIN LEVEL PID
CONTROL FROM
UPPER LEVEL
D/P CELL
PID_LEVEL
+---PID-----+
+PID+---+
|CONTROL BLOCK:  N7:101|
|PROCESS VARIABLE: N7:15|
|TIEBACK:        0|
|CONTROL VARIABLE: N7:81|
+---+---+

```

```

_F:N7:111%7 - BTR - File #2 - 25
N7:81 - BTW - File #2 - 29
PID - File #2 - 27
_F:N7:811%13 - BTW - File #2 - 29

```

Rung #028

ANALOG OUT #1
BTR
ANALOG_OUT_BTR

---BTR---+
+BLOCK TRANSFER READ +--(EN)--+
|Mod Type: 1771-OFB|
| 12 Bit Analog Output+--(DN)|
|Rack: 0|
|Group: 1+--(ER)|
|Module: 0|
|Control Block: N7:76|
|Data File: N7:94|
|LENGTH: 5|
|Continuous: N|
+-----+

Rung #029

ANALOG OUT #1
BTW
ANALOG_OUT_BTW

---BTW---+
+BLOCK TRANSFER WRITE +--(EN)--+
|Mod Type: 1771-OFB|
| 12 Bit Analog Output+--(DN)|
|Rack: 0|
|Group: 1+--(ER)|
|Module: 0|
|Control Block: N7:76|
|Data File: N7:94|
|LENGTH: 5|
|Continuous: N|
+-----+

Rung #030

---(EN)---+

Rack	Group	Slot	Comp	Card Type	PLC-5 Addr	Card Description
0	0	0	N	1771-IFE 8IXfr		Analog Inp
0	1	0	N	1771-OFE 8IXfr		ANALOG OUTPUT #1

Quantity	Card Type	Card Description	I/O Points
1	1771-IFE	12 Bit Analog Input	
1	1771-OFE	12 Bit Analog Output	

I/O Unit I/O (Symbol) Description

Device Description

Upper DES Lower DES

Address	Symbol	Description
0:004/00	CR7 -) { - (2) 15,23 - () - (2) 23	BUBBLE GEN. PUMP OUTPUT
0:004/01	CR2 -) { - (2) 9,15 - () - (2) 9	WASH WATER VALVE OPEN
0:004/02	CR3 -) { - (2) 11,15 - () - (2) 11	AIR VALVE OPEN
0:004/03	CR4 -) { - (2) 14,18,21 - () - (2) 14	FEED VALVE OPEN
0:004/04	CR5 -) { - (2) 18,20 - () - (2) 20	FROTHER PUMP START
0:004/05	CR6 -) { - (2) 17,21 - () - (2) 17	COLLECTOR PUMP START
0:004/06	CR1 -) { - (2) 7,12 - () - (2) 7	AIR COMP. START
0:010/00	AIR_COMP_OUT_PV - () - (2) 8	AIR COMPRESSOR OUT OF INTERLOC TO PANELVIEW
0:010/01	WASH_W_OUT_PV - () - (2) 10	WASH WATER VALV OUT OF INTERLOC TO PANELVIEW
0:010/02	AIR_V_OUT_PV - () - (2) 13	AIR VALVE OUT OF INTERLOC TO PANELVIEW
0:010/03	FEED_V_OUT_PV - () - (2) 16	FEED VALVE OUT OF INTERLOC TO PANELVIEW
0:010/04	COLLECT_OUT_PV - () - (2) 19	COLLECTOR PUMP OUT OF INTERLOC TO PANELVIEW
0:010/05	FROTH_OUT_PV - () - (2) 22	FROTHER PUMP OUT OF INTERLOC TO PANELVIEW
0:010/06	BUB_GEN_OUT_PV - () - (2) 24	BUBBLE GEN PUMP OUT OF INTERLOC TO PANELVIEW
0:011/00	FEED_OUT - () - (2) 14	FEED OUTPUT FOR PANELVIEW
0:011/01	PAN_AIR - () - (2) 7	AIR COMP. OUTPUT FOR PANELVIEW
0:011/02	PAN_WASH - () - (2) 9	WASH WATER OUTPUT FROM PANELVIEW
0:011/03	- () - (2) 11	AIR VALVE FROM PANELVIEW OUTPUT
0:011/04	- () - (2) 20	FROTHER PUMP OUTPUT FROM PANELVIEW
0:011/05	- () - (2) 17	COLLECTOR PUMP FROM PANELVIEW
0:011/06	- () - (2) 23	BUBBLE GEN. PUMP FROM PANELVIEW
I:010/00	AUTO_START -) { - (2) 1 -) / { - (2) 4	AUTO START FROM PANELVIEW
I:010/01	PANELVIEW_STOP -) { - (2) 4	AUTO STOP FROM PANELVIEW

Address	Symbol	Description
	-)/(- - (2) 1	
I:010/04	BUB_GEN_OUT_IL_	BUBBLE GEN PUMP OUT OF INTERLOC SELECT FROM PANELVIEW
	-) (- - (2) 24	
I:010/06	AIR_V_OUT_IL_PV	AIR VALVE OUT OF INTERLOCK SELECT PANELVIEW
	-) (- - (2) 13	
I:010/07	AIR_COM_OUT_IL_	AIR COMP OUT OF INTERLOCK SELECT FROM PANELVIEW
	-) (- - (2) 8	
I:010/12	WASH_W_OUT_IL_P	WASH WATER OUT OF INTERLOCK SELECT FROM PANELVIEW
	-) (- - (2) 10	
I:010/14		MANUAL START FOR BUBBLE GEN.
	-) (- - (2) 23	
I:010/15	COLLECT_OUT_IL_	COLLECTOR PUMP OUT OF INTERLOC FROM PANELVIEW
	-) (- - (2) 19	
I:010/16		MANUAL STOP FOR BUBBLE GEN.
	-)/(- - (2) 23	
I:010/17	FROTH_OUT_IL_PV	FROTHER PUMP OUT OF INTERLOC SELECT FROM PANELVIEW
	-) (- - (2) 22	
I:011/00	WASH-MAN	WASH WATER MANUAL START FROM PANELVIEW
	-) (- - (2) 9	
I:011/01	WASH-MAN-STOP	WASH WATER MANUAL STOP FROM PANELVIEW
	-)/(- - (2) 9	
I:011/02	AIR-MAN-START	MANUAL START FOR AIR VALVE
	-) (- - (2) 11	
I:011/03	AIR-MAN-STOP	MANUAL CLOSE STOP AIR VALVE FROM PANELVIEW
	-) (- - (2) 11	
	-)/(- - (2) 11	
I:011/06	AIR-C-START-MAN	AIR COMP MANUAL START FROM PANELVIEW
	-) (- - (2) 7	
I:011/07	AIR-C-STOP-MAN	AIR COM MANUAL STOP FROM PANELVIEW
	-)/(- - (2) 7	
I:011/10	FROT-START-MAN	FROTHER PUMP MANUAL START FROM PANELVIEW
	-) (- - (2) 20	
I:011/11	FROT-STOP-MAN	FROTHER PUMP MANUAL STOP FROM PANELVIEW
	-)/(- - (2) 20	
I:011/12	COLL-START-MAN	COLLECTOR PUMP MANUAL START FROM PANELVIEW
	-) (- - (2) 17	
I:011/13	COLL-STOP-MAN	COLLECTOR PUMP MANUAL STOP FROM PANELVIEW
	-)/(- - (2) 17	
I:011/15	FEED-OPEN-MAN	MANUAL START FOR FEED VALVE FROM PANELVIEW
	-) (- - (2) 14	
I:011/16	FEED-CLOSE-MAN	MANUAL CLOSE FEED VALVE FROM PANELVIEW
	-)/(- - (2) 14	
I:012/00	AIR_V_IN_IL_PV	AIR VALVE IN INTERLOCK SELECT PANELVIEW
	-)/(- - (2) 13	
I:012/01	FEED_IN_IL_PV	FEED VALVE IN INTERLOCK SELECT PANELVIEW
	-)/(- - (2) 16	
I:012/02	WASH_W_IN_IL_PV	WASH WATER IN INTERLOCK SELECT FROM PANELVIEW
	-)/(- - (2) 10	
I:012/03	AIR_COM_IN_IL_P	AIR COMP IN INTERLOCK SELECT FROM PANELVIEW
	-)/(- - (2) 8	
I:012/04	FROTHER_IN_IL_P	FROTHER PUMP IN INTERLOCK FROM PANELVIEW
	-)/(- - (2) 22	
I:012/05	COLLECT_IN_IL_P	COLLECTOR PUMP IN INTERLOCK FROM PANELVIEW
	-)/(- - (2) 19	

Address	Symbol	Description		
I:012/06	BUB_GEN_IN_IL_P	BUBBLE GEN PUMP IN INTERLOCK	SELECT FROM	PANELVIEW
	-)/[- (2) 24			
B3/1		AUTO START BIT		
	-) [- (2) 1,3,5,7,9,11,14,15,17,18,20,21,23			
	-() - (2) 1			
B3/2	AUTO_STOP	AUTO STOP	STORAGE BIT	
	-) [- (2) 2,4,6			
	-)/[- (2) 7,9,11,14,17,20,23			
	-() - (2) 4			
B3/3	AIR_V_IV	AIR VALVE	INTERLOCK	VERIFY
	-) [- (2) 11			
	-() - (2) 12			
B3/4	FEED_V_IV	FEED VALVE	INTERLOCK	VERIFY
	-) [- (2) 14			
	-() - (2) 15			
B3/15	COL_PUMP_IV	COLLECTOR PUMP	INTERLOCK	VERIFY
	-) [- (2) 17			
	-() - (2) 18			
B3/16	FROTH_PUMP_IV	FROTHER PUMP	INTERLOCK	VERIFY
	-) [- (2) 20			
	-() - (2) 21			
B3/17	AIR_V_OUT_IL	AIR VALVE	OUT OF	INTERLOCK
	-) [- (2) 13,15			
	-() - (2) 13			
B3/18	FEED_V_OUT_IL	FEED VALVE OUT OF	INTERLOCK	
	-) [- (2) 16,18,21			
	-() - (2) 16			
B3/19		WASH WATER OUT OF	INTERLOCK	
	-) [- (2) 10,15			
	-() - (2) 10			
B3/20	AIR_COMP_OUT_IL	AIR COMP OUT	INTERLOCK	
	-) [- (2) 8,12			
	-() - (2) 8			
B3/21	FROTHER_OUT_IL	FROTHER PUMP	OUT OF	INTERLOCK BIT
	-) [- (2) 18,22			
	-() - (2) 22			
B3/22	COLLECT_OUT_IL	COLLECTOR PUMP	OUT OF	INTERLOCK BIT
	-) [- (2) 19,21			
	-() - (2) 19			
B3/23	BUB_GEN_OUT_IL	BUBBLE GEN PUMP OUT OF	INTERLOCK	
	-) [- (2) 15,24			
	-() - (2) 24			
T4:1	T41	FREE RUNNING	TIMER	
	TON - (2) 0			
T4:1.DN		FREE RUNNING	TIMMER	
	-) [- (2) 3,6			
	-)/[- (2) 0			
CS:1	START_CTV	START COUNTER	FOR COLUMN	
	CTU - (2) 3			
	FES - (2) 0			
CS:1.ACC				
	GR - (2) 7,9,11,14,17,20,23			
CS:1.DN		AUTO START	COUNTER	
	-) [- (2) 0			

Address	Symbol	Description
C5:2	-)/(- (2) 1 STOP_RES	COUNTER RES. FOR AUTO STOP
	CTU - (2) 6	
	RES - (2) 5	
C5:2.ACC		
	RES - (2) 7,9,11,14,17,20,23	
C5:2.DN		AUTO STOP COUNTER
	-)/(- (2) 5	
	-)/(- (2) 4	
N7:1	ANALOG_IN	ANALOG INPUT #1
	BTR - (2) 25	
	BTR - (2) 25	
N7:6	ANALOG_IN_BTW	ANALOG INPUT #1 CONFIGURATION WRITE
	BTW - (2) 26	
	BTW - (2) 26	
N7:11		
	BTR - (2) 25	
	BTR - (2) 25	
N7:15	UPPER_LEVEL	#1 LEVEL UPPER D/P CELL FOR PID LEVEL CONTROL
	PID - (2) 27	
	BTR - (2) 25	
N7:31		
	BTW - (2) 26	
	BTW - (2) 26	
N7:71	ANALOG_OUT_BTW	ANALOG OUT #1 BTW
	BTW - (2) 29	
	BTW - (2) 29	
N7:75	ANALOG_OUT_BTR	ANALOG OUT #1 BTR
	BTR - (2) 29	
	BTR - (2) 28	
N7:81	TAILINGS_VALVE	OUTPUT TO TAILINGS VALVE
	BTW - (2) 29	
	PID - (2) 27	
	BTW - (2) 29	
N7:94		
	BTR - (2) 29	
	BTR - (2) 28	
N7:101	PID_LEVEL	MAIN LEVEL PID CONTROL FROM UPPER LEVEL D/P CELL
	PID - (2) 27	
	PID - (2) 27	

Number of Data Files:311

Name	Description	File Type	Mode	Size:Elms	Words
0	O output	Global		32	32
1	I input	Global		32	32
2	S status	Global		32	32
3	B binary	Global		2	2
4	T timer	Global		2	6
5	C counter	Global		5	15
6	R control	Global		1	3
7	M integer	Global		124	124
8	F float	Global		1	2
310	B binary	Global		1	1

Data File #0 Type : O output Elements : 32 Words : 32

Address	17 ---- Data ---- 0	Address	17 ---- Data ---- 0
O:0000	0000 0000 0000 0000	O:0020	0000 0000 0000 0000
O:0001	0000 0000 0000 0000	O:0021	0000 0000 0000 0000
O:0002	0000 0000 0000 0000	O:0022	0000 0000 0000 0000
O:0003	0000 0000 0000 0000	O:0023	0000 0000 0000 0000
O:0004	0000 0000 0100 0111	O:0024	0000 0000 0000 0000
O:0005	0000 0000 0000 0000	O:0025	0000 0000 0000 0000
O:0006	0000 0000 0000 0000	O:0026	0000 0000 0000 0000
O:0007	0000 0000 0000 0000	O:0027	0000 0000 0000 0000
O:0010	0000 0000 0000 0000	O:0030	0000 0000 0000 0000
O:0011	0000 0000 0100 1110	O:0031	0000 0000 0000 0000
O:0012	0000 0000 0000 0000	O:0032	0000 0000 0000 0000
O:0013	0000 0000 0000 0000	O:0033	0000 0000 0000 0000
O:0014	0000 0000 0000 0000	O:0034	0000 0000 0000 0000
O:0015	0000 0000 0000 0000	O:0035	0000 0000 0000 0000
O:0016	0000 0000 0000 0000	O:0036	0000 0000 0000 0000
O:0017	0000 0000 0000 0000	O:0037	0000 0000 0000 0000

Data File #1 Type : I input Elements : 32 Words : 32

Address	17 ---- Data ---- 0	Address	17 ---- Data ---- 0
I:0000	0000 0000 0000 0000	I:0020	0000 0000 0000 0000
I:0001	0000 0000 0000 0000	I:0021	0000 0000 0000 0000
I:0002	0000 0000 0000 0000	I:0022	0000 0000 0000 0000
I:0003	0000 0000 0000 0000	I:0023	0000 0000 0000 0000
I:0004	0000 0000 0000 0000	I:0024	0000 0000 0000 0000
I:0005	0000 0000 0000 0000	I:0025	0000 0000 0000 0000
I:0006	0000 0000 0000 0000	I:0026	0000 0000 0000 0000
I:0007	0000 0000 0000 0000	I:0027	0000 0000 0000 0000
I:0010	0000 0000 0000 0000	I:0030	0000 0000 0000 0000
I:0011	0000 0000 0000 0000	I:0031	0000 0000 0000 0000
I:0012	0000 0000 0000 0000	I:0032	0000 0000 0000 0000
I:0013	0000 0000 0000 0000	I:0033	0000 0000 0000 0000
I:0014	0000 0000 0000 0000	I:0034	0000 0000 0000 0000
I:0015	0000 0000 0000 0000	I:0035	0000 0000 0000 0000
I:0016	0000 0000 0000 0000	I:0036	0000 0000 0000 0000
I:0017	0000 0000 0000 0000	I:0037	0000 0000 0000 0000

Data File #3 Type : B binary Elements : 2 Words : 2

Address	15 ---- Data ---- 0	Address	15 ---- Data ---- 0
B3/00000	0000 0000 0001 1100	B3/00016	0000 0000 0000 0000

Data File #4 Type : T timer Elements : 2 Words : 6

Address	EN	TT	DN	BASE	PRE	ACC
T4:0	0	0	0	.01	0	0
T4:1	1	1	0	1.0	1	0

Data File #5 Type : C counter Elements : 5 Words : 15

Address	CU	CC	DN	OV	UP	PRE	ACC
-----	---	---	---	---	---	---	---

Address	CU	CD	DN	OV	UH	PRE	ACC
C5:0	0	0	0	0	0	0	0
C5:1	0	0	0	0	0	40	0
C5:2	0	0	0	0	0	1810	419
C5:3	0	0	0	0	0	60	0
C5:4	0	0	0	0	0	1	0

Data File #6 Type : R control Elements : 1 Words : 3

Address	EN	EU	DN	EM	ER	UL	IN	FD	LEN	POS
R6:0	0	0	0	0	0	0	0	0	0	0

Data File #7 Type : N integer Elements : 124 Words : 124

Address	0	1	2	3	4	5	6	7	8	9
N7:0	0	-8576	7	0	7	11	-2704	11	0	7
N7:10	31	0	0	0	0	0	0	0	0	0
N7:20	0	0	0	0	0	0	0	0	0	0
N7:30	0	0	0	1285	0	0	0	0	0	0
N7:40	0	0	0	0	0	0	0	0	0	0
N7:50	0	0	0	0	0	0	0	0	0	0
N7:60	0	0	0	0	0	0	0	0	0	0
N7:70	0	-8576	10	0	7	31	-10622	5	0	7
N7:80	94	0	0	0	0	0	0	16533	0	16533
N7:90	0	16533	0	16533	0	0	0	0	0	0
N7:100	0	-24528	0	0	1200	1000	0	0	0	0
N7:110	0	0	100	0	10	0	0	0	0	0
N7:120	0	0	0	0	0	0	0	0	0	0

Data File #8 Type : F float Elements : 1 Words : 2

Address	0	1	2	3	4
FB:0	0	0	0	0	0

Data File #310 Type : B binary Elements : 1 Words : 1

Address	15	----	Data	----	0	Address	15	----	Data	----	0
B310/00000 0000 0000 0000 0000											

Data File #0 Type : O output Elements : 32 Words : 32

Address	17 ---- Data ---- 0	Address	17 ---- Data ---- 0
O:0000	0000 0000 0000 0000	O:0020	0000 0000 0000 0000
O:0001	0000 0000 0000 0000	O:0021	0000 0000 0000 0000
O:0002	0000 0000 0000 0000	O:0022	0000 0000 0000 0000
O:0003	0000 0000 0000 0000	O:0023	0000 0000 0000 0000
O:0004	0000 0000 0XXX XXXX	O:0024	0000 0000 0000 0000
O:0005	0000 0000 0000 0000	O:0025	0000 0000 0000 0000
O:0006	0000 0000 0000 0000	O:0026	0000 0000 0000 0000
O:0007	0000 0000 0000 0000	O:0027	0000 0000 0000 0000
O:0010	0000 0000 0XXX XXXX	O:0030	0000 0000 0000 0000
O:0011	0000 0000 0XXX XXXX	O:0031	0000 0000 0000 0000
O:0012	0000 0000 0000 0000	O:0032	0000 0000 0000 0000
O:0013	0000 0000 0000 0000	O:0033	0000 0000 0000 0000
O:0014	0000 0000 0000 0000	O:0034	0000 0000 0000 0000
O:0015	0000 0000 0000 0000	O:0035	0000 0000 0000 0000
O:0016	0000 0000 0000 0000	O:0036	0000 0000 0000 0000
O:0017	0000 0000 0000 0000	O:0037	0000 0000 0000 0000

Data File #1 Type : I input Elements : 32 Words : 32

Address	17 ---- Data ---- 0	Address	17 ---- Data ---- 0
I:0000	0000 0000 0000 0000	I:0020	0000 0000 0000 0000
I:0001	0000 0000 0000 0000	I:0021	0000 0000 0000 0000
I:0002	0000 0000 0000 0000	I:0022	0000 0000 0000 0000
I:0003	0000 0000 0000 0000	I:0023	0000 0000 0000 0000
I:0004	0000 0000 0000 0000	I:0024	0000 0000 0000 0000
I:0005	0000 0000 0000 0000	I:0025	0000 0000 0000 0000
I:0006	0000 0000 0000 0000	I:0026	0000 0000 0000 0000
I:0007	0000 0000 0000 0000	I:0027	0000 0000 0000 0000
I:0010	XXXX 0000 XX0X 00XX	I:0030	0000 0000 0000 0000
I:0011	0XXX 0XXX XX00 XXXX	I:0031	0000 0000 0000 0000
I:0012	0000 0000 0XXX XXXX	I:0032	0000 0000 0000 0000
I:0013	0000 0000 0000 0000	I:0033	0000 0000 0000 0000
I:0014	0000 0000 0000 0000	I:0034	0000 0000 0000 0000
I:0015	0000 0000 0000 0000	I:0035	0000 0000 0000 0000
I:0016	0000 0000 0000 0000	I:0036	0000 0000 0000 0000
I:0017	0000 0000 0000 0000	I:0037	0000 0000 0000 0000

Data File #3 Type : B binary Elements : 2 Words : 2

Address	15 ---- Data ---- 0	Address	15 ---- Data ---- 0
B3/00000	X000 0000 000X XXX0	B3/00016	0000 0000 XXXX XXXX

Data File #4 Type : T timer Elements : 2 Words : 6

Address	0 1 2 3 4 5 6 7 8 9 0 1 2 3 4 5 6 7 8 9 0 1 2 3 4 5 6 7 8 9
T4:0	X

Data File #5 Type : C counter Elements : 5 Words : 15

Address	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9
CS:0																														

Data File #6 Type : R control Elements : 1 Words : 3

Address	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9
R6:0																														

Data File #7 Type : N integer Elements : 124 Words : 124

Address	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9
N7:0																														
N7:10																														
N7:20																														
N7:30																														
N7:40																														
N7:50																														

Data File #8 Type : F float Elements : 1 Words : 2

Address	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9
F8:0																														

Data File #9 Type : B binary Elements : 1 Words : 1

Address	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0	Address	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
B9:0	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	B9:0	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000	0000

Address	Symbol	Description			
B3/0	INLOCK_BIT	INTERLOCK	STORAGE BIT		
B3/1		AUTO START BIT			
B3/2	AUTO_STOP	AUTO STOP	STORAGE BIT		
B3/3	AIR_V_IV	AIR VALVE	INTERLOCK	VERIFY	
B3/4	FEED_V_IV	FEED VALVE	INTERLOCK	VERIFY	
B3/5		STORAGE BIT FOR	INTERLOCK		
B3/6		STORAGE BIT FOR	NOT IN	INTERLOCK	
B3/7		STORAGE BIT FOR	INTERLOCK		
B3/8		STORAGE BIT FOR	NOT INTERLOCK		
B3/9		STORAGE BIT FOR	INTERLOCK		
B3/10		STORAGE BIT FOR	NOT INTERLOCK		
B3/11		STORAGE BIT FOR	INTERLOCK		
B3/12		STORAGE BIT FOR	NOT INTERLOCK		
B3/13		STORAGE BIT FOR	MANUAL START		
B3/14		STORAGE BIT FOR	MANUAL STOP		
B3/15	COL_PUMP_IV	COLLECTOR PUMP	INTERLOCK	VERIFY	
B3/16	FROTH_PUMP_IV	FROTHER PUMP	INTERLOCK	VERIFY	
B3/17	AIR_V_OUT_IL	AIR VALVE	OUT OF	INTERLOCK	
B3/18	FEED_V_OUT_IL	FEED VALVE OUT	OF INTERLOCK		
B3/19		WASH WATER OUT	OF INTERLOCK		
B3/20	AIR_COMP_OUT_IL	AIR COMP OUT	INTERLOCK		
B3/21	FROTHER_OUT_IL	FROTHER PUMP	OUT OF	INTERLOCK BIT	
B3/22	COLLECT_OUT_IL	COLLECTOR PUMP	OUT OF	INTERLOCK BIT	
B3/23	BUB_GEN_OUT_IL	BUBBLE GEN PUMP	OUT OF	INTERLOCK	
B3/24	AUTO_BIT				
C5:1	START_CTO	START COUNTER	FOR COLUMN		
C5:1.ON		AUTO START	COUNTER		
C5:2	STOP_RES	COUNTER RES.	FOR AUTO STOP		
C5:2.ACC					
C5:2.ON		AUTO STOP	COUNTER		
C5:3	C5:3	AUTO STOP	COUNTER		
C5:4	C5:4	AUTO START COUNTER			
I:04					
I:04/00		IN INTERLOCK	BIT FROM BUBBLE GEN.		
I:04/01		IN INTERLOCK	BIT FROM WASH WATER		
I:04/02		IN INTERLOCK	BIT FROM AIR VALVE		
I:04/06		IN INTERLOCK	BIT FROM AIR COMPRESSOR		
I:010					
I:010/00	AUTO_START	AUTO START	FROM PANELVIEW		
I:010/01	PANELVIEW_STOP	AUTO STOP FROM	PANELVIEW		
I:010/02	MAN_START	MANUAL START	FROM PANELVIEW		
I:010/03	FEED_V_OUT_IL_P	FEED VALVE	OUT OF INTERLOCK	SELECT FROM	PANELVIEW
I:10/04	BUB_GEN_OUT_IL	BUBBLE GEN PUMP	OUT OF INTERLOCK	SELECT FROM	PANELVIEW
I:10/06	AIR_V_OUT_IL_PV	AIR VALVE OUT	OF INTERLOCK	SELECT	PANELVIEW
I:10/07	AIR_COM_OUT_IL	AIR COMP OUT	OF INTERLOCK	SELECT FROM	PANELVIEW
I:10/12	WASH_W_OUT_IL_P	WASH WATER OUT	OF INTERLOCK	SELECT FROM	PANELVIEW
I:10/14		MANUAL START	FOR BUBBLE GEN.		
I:10/15	COLLECT_OUT_IL	COLLECTOR PUMP	OUT OF INTERLOCK	FROM PANELVIEW	
I:10/16		MANUAL STOP FOR	BUBBLE GEN.		
I:10/17	FROTH_OUT_IL_PV	FROTHER PUMP	OUT OF INTERLOCK	SELECT FROM	PANELVIEW

Address	Symbol	Description				
I:11						
I:11/00	WASH-MAN	WASH WATER	MANUAL START	FROM PANELVIEW		
I:11/01	WASH-MAN-STOP	WASH WATER	MANUAL STOP	FROM PANELVIEW		
I:11/02	AIR-MAN-START	MANUAL START	FOR AIR VALVE			
I:11/03	AIR-MAN-STOP	MANUAL CLOSE	STOP AIR VALVE	FROM PANELVIEW		
I:11/06	AIR-C-START-MAN	AIR COMP	MANUAL START	FROM PANELVIEW		
I:11/07	AIR-C-STOP-MAN	AIR COM MANUAL	STOP FROM	PANELVIEW		
I:11/10	FROT-START-MAN	FROTHER PUMP	MANUAL START	FROM PANELVIEW		
I:11/11	FROT-STOP-MAN	FROTHER PUMP	MANUAL STOP	FROM PANELVIEW		
I:11/12	COLL-START-MAN	COLLECTOR PUMP	MANUAL START	FROM PANELVIEW		
I:11/13	COLL-STOP-MAN	COLLECTOR PUMP	MANUAL STOP	FROM PANELVIEW		
I:11/15	FEED-OPEN-MAN	MANUAL START	FOR FEED VALVE	FROM PANELVIEW		
I:11/16	FEED-CLOSE-MAN	MANUAL CLOSE	FEED VALVE	FROM PANELVIEW		
I:12						
I:12/00	AIR_V_IN_IL_PV	AIR VALVE IN	INTERLOCK	SELECT	PANELVIEW	
I:12/01	FEED_IN_IL_PV	FEED VALVE IN	INTERLOCK	SELECT	PANELVIEW	
I:12/02	WASH_W_IN_IL_PV	WASH WATER IN	INTERLOCK	SELECT FROM	PANELVIEW	
I:12/03	AIR_COM_IN_IL_P	AIR COMP IN	INTERLOCK	SELECT FROM	PANELVIEW	
I:12/04	FROTHER_IN_IL_P	FROTHER PUMP	IN INTERLOCK	FROM PANELVIEW		
I:12/05	COLLECT_IN_IL_P	COLLECTOR PUMP	IN INTERLOCK	FROM PANELVIEW		
I:12/06	BUBBLE_GEN_IN_IL_P	BUBBLE GEN PUMP	IN INTERLOCK	SELECT FROM	PANELVIEW	
N7:1	ANALOG_IN	ANALOG INPUT #1				
N7:6	ANALOG_IN_BTW	ANALOG INPUT #1	CONFIGURATION	WRITE		
N7:15	UPPER_LEVEL	#1 LEVEL	UPPER D/P CELL	FOR PID LEVEL	CONTROL	
N7:16	LOWER_LEVEL	#2 LEVEL	LOWER D/P CELL			
N7:17	FEED_FLOW	FEED FLOWMETER				
N7:71	ANALOG_OUT_BTW	ANALOG OUT #1	BTW			
N7:76	ANALOG_OUT_BTR	ANALOG OUT #1	BTR			
N7:81	TAILINGS_VALVE	OUTPUT TO	TAILINGS VALVE			
N7:82	FROTHER_SETTING	OUTPUT TO	FROTHER PUMP			
N7:83	COLLECTOR_SET	OUTPUT TO	COLLECTOR PUMP	SETTING		
N7:84	FEED_VALVE_SET	OUTPUT TO	PROPORTIONAL	FEED VALVE		
N7:101	PID_LEVEL	MAIN LEVEL PID	CONTROL FROM	UPPER LEVEL	D/P CELL	
N7:111		TAILINGS VALVE	OPENS IF LOOP	CRASHES		
0:0000		Analog Input #1				
0:004						
0:004/00	CR7	BUBBLE GEN.	PUMP OUTPUT			
0:004/01	CR2	WASH WATER	VALVE OPEN			
0:004/02	CR3	AIR VALVE	OPEN			
0:004/03	CR4	FEED VALVE	OPEN			
0:004/04	CR5	FROTHER PUMP	START			
0:004/05	CR6	COLLECTOR PUMP	START			
0:004/06	CR1	AIR COMP.	START			
0:10/00	AIR_COMP_OUT_PV	AIR COMPRESSOR	OUT OF INTERLOC	TO PANELVIEW		
0:10/01	WASH_W_OUT_PV	WASH WATER VALV	OUT OF INTERLOC	TO PANELVIEW		
0:10/02	AIR_V_OUT_PV	AIR VALVE	OUT OF INTERLOC	TO PANELVIEW		
0:10/03	FEED_V_OUT_PV	FEED VALVE	OUT OF INTERLOC	TO PANELVIEW		
0:10/04	COLLECT_OUT_PV	COLLECTOR PUMP	OUT OF INTERLOC	TO PANELVIEW		
0:10/05	FROTHER_OUT_PV	FROTHER PUMP	OUT OF INTERLOC	TO PANELVIEW		
0:10/06	BUBBLE_GEN_OUT_PV	BUBBLE GEN PUMP	OUT OF INTERLOC	TO PANELVIEW		

Address	Symbol	Description				
0:0100		ANALOG OUT	PUT #1			
0:011						
0:011/00	FEED_OUT	FEED OUTPUT	FOR PANELVIEW			
0:011/01	PAN_AIR	AIR COMP.	OUTPUT FOR	PANELVIEW		
0:011/02	PAN_WASH	WASH WATER	OUTPUT FROM	PANELVIEW		
0:011/03		AIR VALVE FROM	PANELVIEW	OUTPUT		
0:011/04		FROTHER PUMP	OUTPUT FROM	PANELVIEW		
0:011/05		COLLECTOR PUMP	FROM PANELVIEW			
0:011/06		BUBBLE GEN.	PUMP FROM	PANELVIEW		
S:0/0		Processor	Arithmetic	Carry	Flag	
S:0/1		Processor	Arithmetic	Underflow/	Overflow	Flag
S:0/2		Processor	Arithmetic	Zero	Flag	
S:0/3		Processor	Arithmetic	Sign	Flag	
S:1/0		RAM Checksum	is invalid	at power up		
S:1/1		PLC-5 in	RUN Mode			
S:1/2		PLC-5 in	TEST Mode			
S:1/3		PLC-5 in	PROG Mode			
S:1/4		PLC-5 is	Burning an	EEPROM		
S:1/6		Test Edit Mode	Enabled			
S:1/7		Key switch in	Remote	Position		
S:1/8		Forces	Enabled			
S:1/9		Forces	Present			
S:1/10		PLC-5	Successful,	Burned	EEPROM	
S:1/11		PLC-5 is	performing an	on-line	programming	operation
S:1/12		PLC-5	performing	First	Program Scan	
S:7/0		Rack 0 Faulted				
S:7/1		Rack 1 Faulted				
S:7/2		Rack 2 Faulted				
S:7/3		Rack 3 Faulted				
S:7/4		Rack 4 Faulted				
S:7/5		Rack 5 Faulted				
S:7/6		Rack 6 Faulted				
S:7/7		Rack 7 Faulted				
S:7/8		Block Xfer	queue to rack	0 is full		
S:7/9		Block Xfer	queue to rack	1 is full		
S:7/10		Block Xfer	queue to rack	2 is full		
S:7/11		Block Xfer	queue to rack	3 is full		
S:7/12		Block Xfer	queue to rack	4 is full		
S:7/13		Block Xfer	queue to rack	5 is full		
S:7/14		Block Xfer	queue to rack	6 is full		
S:7/15		Block Xfer	queue to rack	7 is full		
S:8		Current Ladder	for SFC	Scan Time		
S:9		Maximum Ladder	for SFC	Scan Time		
S:10/0		Low Battery				
S:10/1		PCL Table	Change-	Station gone	offline or	come online
S:10/2		STI Interrupt	Overlap			
S:10/3		EEPROM Memory	Transferred	at power-up		
S:10/4		Edits Prevent	SFC Continue			
S:10/5		I/O Status File	doesn't exist	or not large	enough	
S:10/6		Corrupt	Program File			

Address	Symbol	Description				
S:11/1		Bad Address	in ladder	program		
S:11/2		Programmer	Error			
S:11/3		SFC Fault				
S:11/4		Error while	assembling	a ladder	program file	
S:11/5		Power up	Protection	Fault		
S:11/7		User Generated	Fault			
S:11/8		Watchdog	Timer Fault			
S:11/9		Bad System	Configuration			
S:11/10		Hardware	Error			
S:11/13		Bad STI File				
S:11/14		Bad Fault File				
S:11/15		Non Ladder File				
S:12		Fault Code				
S:13		Program File	Where Fault	Occured		
S:14		Rung Number	Where Fault	Occured		
S:15		Real Time Clock	YEAR			
S:16		Real Time Clock	MONTH			
S:17		Real Time Clock	DAY			
S:18		Real Time Clock	HOURL			
S:19		Real Time Clock	MINUTE			
S:20		Real Time Clock	SECOND			
S:21		Indexed	Addressing	Offset		
S:22		Adapter	Image	File		
S:23		SFC	Restart/	Continue		
S:24		Start-up	protection	after power	loss	
S:25		Rack 0	Inhibit			
S:26		Rack 1	Inhibit			
S:27		Rack 2	Inhibit			
S:28		Rack 3	Inhibit			
S:29		Rack 4	Inhibit			
S:30		Rack 5	Inhibit			
S:31		Rack 6	Inhibit			
S:32		Rack 7	Inhibit			
S:33		Rack 8	Inhibit			
S:34		Rack 9	Inhibit			
S:35		Rack 10	Reset			
S:36		Rack 11	Reset			
S:37		Rack 12	Reset			
S:38		Rack 13	Reset			
S:39		Rack 14	Reset			
S:40		Rack 15	Reset			
S:41		Rack 16	Reset			
S:42		Rack 17	Reset			
S:43		Rack 18	Reset			
S:44		Rack 19	Reset			
S:45		Rack 20	Reset			
S:46		Rack 21	Reset			
S:47		Rack 22	Reset			
S:48		Rack 23	Reset			
S:49		Rack 24	Reset			
S:50		Rack 25	Reset			
S:51		Rack 26	Reset			
S:52		Rack 27	Reset			
S:53		Rack 28	Reset			
S:54		Rack 29	Reset			
S:55		Rack 30	Reset			
S:56		Rack 31	Reset			
S:57		Rack 32	Reset			
S:58		Rack 33	Reset			
S:59		Rack 34	Reset			
S:60		Rack 35	Reset			
S:61		Rack 36	Reset			
S:62		Rack 37	Reset			
S:63		Rack 38	Reset			
S:64		Rack 39	Reset			
S:65		Rack 40	Reset			
S:66		Rack 41	Reset			
S:67		Rack 42	Reset			
S:68		Rack 43	Reset			
S:69		Rack 44	Reset			
S:70		Rack 45	Reset			
S:71		Rack 46	Reset			
S:72		Rack 47	Reset			
S:73		Rack 48	Reset			
S:74		Rack 49	Reset			
S:75		Rack 50	Reset			
S:76		Rack 51	Reset			
S:77		Rack 52	Reset			
S:78		Rack 53	Reset			
S:79		Rack 54	Reset			
S:80		Rack 55	Reset			
S:81		Rack 56	Reset			
S:82		Rack 57	Reset			
S:83		Rack 58	Reset			
S:84		Rack 59	Reset			
S:85		Rack 60	Reset			
S:86		Rack 61	Reset			
S:87		Rack 62	Reset			
S:88		Rack 63	Reset			
S:89		Rack 64	Reset			
S:90		Rack 65	Reset			
S:91		Rack 66	Reset			
S:92		Rack 67	Reset			
S:93		Rack 68	Reset			
S:94		Rack 69	Reset			
S:95		Rack 70	Reset			
S:96		Rack 71	Reset			
S:97		Rack 72	Reset			
S:98		Rack 73	Reset			
S:99		Rack 74	Reset			
S:100		Rack 75	Reset			
S:101		Rack 76	Reset			
S:102		Rack 77	Reset			
S:103		Rack 78	Reset			
S:104		Rack 79	Reset			
S:105		Rack 80	Reset			
S:106		Rack 81	Reset			
S:107		Rack 82	Reset			
S:108		Rack 83	Reset			
S:109		Rack 84	Reset			
S:110		Rack 85	Reset			
S:111		Rack 86	Reset			
S:112		Rack 87	Reset			
S:113		Rack 88	Reset			
S:114		Rack 89	Reset			
S:115		Rack 90	Reset			
S:116		Rack 91	Reset			
S:117		Rack 92	Reset			
S:118		Rack 93	Reset			
S:119		Rack 94	Reset			
S:120		Rack 95	Reset			
S:121		Rack 96	Reset			
S:122		Rack 97	Reset			
S:123		Rack 98	Reset			
S:124		Rack 99	Reset			
S:125		Rack 100	Reset			
S:126		Rack 101	Reset			
S:127		Rack 102	Reset			
S:128		Rack 103	Reset			
S:129		Rack 104	Reset			
S:130		Rack 105	Reset			
S:131		Rack 106	Reset			
S:132		Rack 107	Reset			
S:133		Rack 108	Reset			
S:134		Rack 109	Reset			
S:135		Rack 110	Reset			
S:136		Rack 111	Reset			
S:137		Rack 112	Reset			
S:138		Rack 113	Reset			
S:139		Rack 114	Reset			
S:140		Rack 115	Reset			
S:141		Rack 116	Reset			
S:142		Rack 117	Reset			
S:143		Rack 118	Reset			
S:144		Rack 119	Reset			
S:145		Rack 120	Reset			
S:146		Rack 121	Reset			
S:147		Rack 122	Reset			
S:148		Rack 123	Reset			
S:149		Rack 124	Reset			
S:150		Rack 125	Reset			
S:151		Rack 126	Reset			
S:152		Rack 127	Reset			
S:153		Rack 128	Reset			
S:154		Rack 129	Reset			
S:155		Rack 130	Reset			
S:156		Rack 131	Reset			
S:157		Rack 132	Reset			
S:158		Rack 133	Reset			
S:159		Rack 134	Reset			
S:160		Rack 135	Reset			
S:161		Rack 136	Reset			
S:162		Rack 137	Reset			
S:163		Rack 138	Reset			
S:164		Rack 139	Reset			
S:165		Rack 140	Reset			
S:166		Rack 141	Reset			
S:167		Rack 142	Reset			
S:168		Rack 143	Reset			
S:169		Rack 144	Reset			
S:170		Rack 145	Reset			
S:171		Rack 146	Reset			
S:172		Rack 147	Reset			
S:173		Rack 148	Reset			
S:174		Rack 149	Reset			
S:175		Rack 150	Reset			
S:176		Rack 151	Reset			
S:177		Rack 152	Reset			
S:178		Rack 153	Reset			
S:179		Rack 154	Reset			
S:180		Rack 155	Reset			
S:181		Rack 156	Reset			
S:182		Rack 157	Reset			
S:183		Rack 158	Reset			
S:184		Rack 159	Reset			
S:185		Rack 160	Reset			
S:186		Rack 161	Reset			
S:187		Rack 162	Reset			
S:188		Rack 163	Reset			
S:189		Rack 164	Reset			
S:190		Rack 165	Reset			
S:191		Rack 166	Reset			
S:192		Rack 167	Reset			
S:193		Rack 168	Reset			
S:194		Rack 169	Reset			
S:195		Rack 170	Reset			
S:196		Rack 171	Reset			
S:197		Rack 172	Reset			
S:198		Rack 173	Reset			
S:199		Rack 174	Reset			
S:200		Rack 175	Reset			
S:201		Rack 176	Reset			
S:202		Rack 177	Reset			
S:203		Rack 178	Reset			
S:204		Rack 179	Reset			
S:205		Rack 180	Reset			
S:206		Rack 181	Reset			
S:207		Rack 182	Reset			
S:208		Rack 183	Reset			
S:209		Rack 184	Reset			
S:210		Rack 185	Reset			
S:211		Rack 186	Reset			
S:212		Rack 187	Reset			
S:213		Rack 188	Reset			
S:214		Rack 189	Reset			
S:215		Rack 190	Reset			
S:216		Rack 191	Reset			
S:217		Rack 192	Reset			
S:218		Rack 193	Reset			
S:219		Rack 194	Reset			
S:220		Rack 195	Reset			
S:221		Rack 196	Reset			
S:222		Rack 197	Reset			
S:223		Rack 198	Reset			
S:224		Rack 199	Reset			
S:225		Rack 200	Reset			
S:226		Rack 201	Reset			
S:227		Rack 202	Reset			
S:228		Rack 203	Reset			
S:229		Rack 204	Reset			
S:230		Rack 205	Reset			
S:231		Rack 206	Reset			
S:232		Rack 207	Reset			
S:233		Rack 208	Reset			
S:234		Rack 209	Reset			
S:235		Rack 210	Reset			
S:236		Rack 211	Reset			
S:237		Rack 212	Reset			
S:238		Rack 213	Reset			
S:239		Rack 214	Reset			
S:240		Rack 215	Reset			
S:241		Rack 216	Reset			
S:242		Rack 217	Reset			
S:243		Rack 218	Reset			
S:244		Rack 219	Reset			
S:245		Rack 220	Reset			
S:246		Rack 221	Reset			
S:247		Rack 222	Reset			
S:248		Rack 223	Reset			
S:249		Rack 224	Reset			
S:250		Rack 225	Reset			
S:251		Rack 226	Reset			
S:252		Rack 227	Reset			
S:253		Rack 228	Reset			
S:254		Rack 229	Reset			
S:255		Rack 230	Reset			
S:256		Rack 231	Reset			
S:257		Rack 232	Reset			
S:258		Rack 233	Reset			
S:259		Rack 234	Reset			
S:260		Rack 235	Reset			
S:261		Rack 236	Reset			
S:262		Rack 237	Reset			
S:263		Rack 238	Reset			
S:264		Rack 239	Reset			
S:265		Rack 240	Reset			
S:266		Rack 241	Reset			</

Addr : RUNG002-0007
RUNG DESCRIPTION:
AIR COMPRESSOR

Addr : RUNG002-0009
RUNG DESCRIPTION:
WASH WATER VALVE
Addr : RUNG002-0011
RUNG DESCRIPTION:
AIR VALVE

Addr : RUNG002-0014
RUNG DESCRIPTION:
FEED VALVE

Addr : RUNG002-0017
RUNG DESCRIPTION:
COLLECTOR PUMP
Addr : RUNG002-0020
RUNG DESCRIPTION:
FROTHER PUMP

Addr : RUNG002-0023
RUNG DESCRIPTION:
BUBBLE GENERATOR PUMP

Address	Symbol	Description				
B3/0	INLOCK_BIT	INTERLOCK	STORAGE BIT			
B3/5		STORAGE BIT FOR INTERLOCK				
B3/6		STORAGE BIT FOR NOT IN INTERLOCK				
B3/7		STORAGE BIT FOR INTERLOCK				
B3/8		STORAGE BIT FOR NOT INTERLOCK				
B3/9		STORAGE BIT FOR INTERLOCK				
B3/10		STORAGE BIT FOR NOT INTERLOCK				
B3/11		STORAGE BIT FOR INTERLOCK				
B3/12		STORAGE BIT FOR NOT INTERLOCK				
B3/13		STORAGE BIT FOR MANUAL START				
E3/14		STORAGE BIT FOR MANUAL STOP				
B3/0	AUTO_BIT					
C5/3		AUTO STOP	COUNTER			
C5/4		AUTO START COUNTER				
I/04						
I/04/00		IN INTERLOCK	BIT FROM BUBBLE GEN.			
I/04/01		IN INTERLOCK	BIT FROM WASH WATER			
I/04/02		IN INTERLOCK	BIT FROM AIR VALVE			
I/04/03		IN INTERLOCK	BIT FROM AIR COMPRESSOR			
I/04/02	MAN_START	MANUAL START	FROM PANELVIEW			
I/04/02	FEED_OUT	FEED VALVE	OUT OF INTERLOCK	SELECT FROM	PANELVIEW	
I/04/02						
I/04/02						
N7/01	LOWER_LEVEL	NO LEVEL	LOWER D/P CELL			
N7/07	FEED_FLOW	FEED FLOWMETER				
N7/02	FROTHER_SETTING	OUTPUT TO	FROTHER PUMP			
N7/03	COLLECTOR_SET	OUTPUT TO	COLLECTOR PUMP	SETTING		
N7/04	FEED_VALVE_SET	OUTPUT TO	PROPORTIONAL	FEED VALVE		
N7/01		TAILINGS VALVE	OPENS IF LOOP CRASHES			
S/0/0		Processor	Arithmetic	Carry	Flag	
S/0/0		Processor	Arithmetic	Underflow/	Overflow	Flag
S/0/0		Processor	Arithmetic	Zero	Flag	
S/0/0		Processor	Arithmetic	Sign	Flag	
S/1/0		RAM Checksum	is invalid	at power up		
S/1/1		PLC-5 in	RUN Mode			
S/1/2		PLC-5 in	TEST Mode			
S/1/3		PLC-5 in	PROG Mode			
S/1/4		PLC-5 is	Burning an	EEPROM		
S/1/6		Test Edit Mode	Enabled			
S/1/7		Key switch in	Remote	Position		
S/1/8		Forces	Enabled			
S/1/9		Forces	Present			
S/1/10		PLC-5	Successfully	Burned	EEPROM	
S/1/11		PLC-5 is	performing an	on-line	programming	operation
S/1/15		PLC-5	performing	First	Program Scan	
S/7/0		Rack 0 Faulted				
S/7/1		Rack 1 Faulted				
S/7/2		Rack 2 Faulted				
S/7/3		Rack 3 Faulted				
S/7/4		Rack 4 Faulted				

Address	Symbol	Description				
S:7/5		Rack 5 Faulted				
S:7/6		Rack 6 Faulted				
S:7/7		Rack 7 Faulted				
S:7/8		Block Xfer	queue to rack	0 is full		
S:7/9		Block Xfer	queue to rack	1 is full		
S:7/10		Block Xfer	queue to rack	2 is full		
S:7/11		Block Xfer	queue to rack	3 is full		
S:7/12		Block Xfer	queue to rack	4 is full		
S:7/13		Block Xfer	queue to rack	5 is full		
S:7/14		Block Xfer	queue to rack	6 is full		
S:7/15		Block Xfer	queue to rack	7 is full		
S:8		Current Ladder	or SFC	Scan Time		
S:9		Maximum Ladder	or SFC	Scan Time		
S:10/0		Low Battery				
S:10/1		PCL Table	Change-	Station gone	offline or	come online
S:10/2		STI Interrupt	Overlap			
S:10/3		EEPROM Memory	Transferred	at power-up		
S:10/4		Edits Prevent	SFC Continue			
S:10/5		I/O Status File	doesn't exist	or not large	enough	
S:11/0		Corrupt	Program File			
S:11/1		Bad Address	in ladder	program		
S:11/2		Programmer	Error			
S:11/3		SFC Fault				
S:11/4		Error while	assembling	a ladder	program file	
S:11/5		Power up	Protection	Fault		
S:11/7		User Generated	Fault			
S:11/8		Watchdog	Timer Fault			
S:11/9		Bad System	Configuration			
S:11/10		Hardware	Error			
S:11/13		Bad STI File				
S:11/14		Bad Fault File				
S:11/15		Non Ladder File				
S:12		Fault Code				
S:13		Program File	Where Fault	Occured		
S:14		Rung Number	Where Fault	Occured		
S:18		Real Time Clock	YEAR			
S:19		Real Time Clock	MONTH			
S:20		Real Time Clock	DAY			
S:21		Real Time Clock	HOURL			
S:22		Real Time Clock	MINUTE			
S:23		Real Time Clock	SECOND			
S:24		Indexed	Addressing	Offset		
S:25		Adapter	Image	File		
S:26/0		SFC	Restart/	Continue		
S:26/1		Start-up	protection	after power	loss	
S:27/0		Rack 0	Inhibit			
S:27/1		Rack 1	Inhibit			
S:27/2		Rack 2	Inhibit			
S:27/3		Rack 3	Inhibit			
S:27/4		Rack 4	Inhibit			

Address	Symbol	Description				
S:27/5		Rack 5	Inhibit			
S:27/6		Rack 6	Inhibit			
S:27/7		Rack 7	Inhibit			
S:27/8		Rack 0	Reset			
S:27/9		Rack 1	Reset			
S:27/10		Rack 2	Reset			
S:27/11		Rack 3	Reset			
S:27/12		Rack 4	Reset			
S:27/13		Rack 5	Reset			
S:27/14		Rack 6	Reset			
S:27/15		Rack 7	Reset			
S:28		Watchdog	Timer	Setpoint		
S:29		Fault Routine	File Number			
S:30		STI Setpoint				
S:31		STI File Number				

Current Program Revision # 35
PLC-5 Ladder Logistics Revision last used:v5.04

Rev#35	04/05/91	15:59:07	Des:
Rev#34	04/05/91	15:40:04	Des:
Rev#33	04/05/91	10:36:38	Des:
Rev#32	04/05/91	10:09:12	Des:
Rev#31	04/05/91	08:10:45	Des:
Rev#30	04/05/91	08:08:07	Des:
Rev#29	04/05/91	07:02:05	Des:
Rev#28	04/04/91	22:44:04	Des:
Rev#27	04/04/91	20:51:26	Des:
Rev#26	04/04/91	20:43:57	Des:
Rev#25	04/04/91	15:58:47	Des:
Rev#24	04/04/91	14:28:31	Des:
Rev#23	04/02/91	09:06:45	Des:
Rev#22	04/01/91	12:44:09	Des:
Rev#21	04/01/91	12:32:03	Des:
Rev#20	04/01/91	12:23:05	Des:
Rev#19	03/15/91	09:06:42	Des:
Rev#18	03/11/91	09:43:13	Des:
Rev#17	03/11/91	08:04:42	Des:
Rev#16	03/11/91	07:55:15	Des:
Rev#15	03/11/91	07:44:13	Des:
Rev#14	03/05/91	08:57:10	Des:
Rev#13	03/04/91	09:50:57	Des:
Rev#12	03/02/91	06:27:41	Des:
Rev#11	03/01/91	13:19:07	Des:
Rev#10	03/01/91	13:04:52	Des:
Rev#9	03/01/91	09:51:59	Des:
Rev#8	02/28/91	14:13:15	Des:
Rev#7	02/28/91	10:21:56	Des:
Rev#6	02/28/91	08:02:30	Des:
Rev#5	02/27/91	15:56:08	Des:
Rev#4	02/27/91	15:13:04	Des:
Rev#3	02/27/91	15:05:37	Des:
Rev#2	02/27/91	13:30:55	Des:
Rev#1	02/27/91	10:01:15	Des:

Page	Rung	Description
1	0	Program File List
2	0	Ladder Diagram Dump
2	0	File #2 Proj:COLUMN
15		I/O Part List
18		Cross Reference Report
22		Data Table Dump Report
25		Data Table Usage Report
27		Data Base Usage Form
32		Unused Address Report
35		Revision History Report

PLC-5 Program Information

Program Name.....: C:\PLC5\COLUMN
Processor Type.....: PLC-5/25 Series:A Revision:H
311 Data Table Files use: 249 Words
3 Program Files use....: 361 Words
Total number of rungs.....: 30
PLC-5 Memory Free.....: 1326 Words
PLC-5 Memory Size.....: 2570 Words
Time done printing Report: 17:41:30
Company Name.....: MARROWBONE TECH. CENTER
Ladder Report Symbol Key

Rung #xxx <-- Rung Number being Printed

Rung Description - Up to 64K of text in either 80 columns or 132 columns (Depends on Configuration)

...
5 Line by 15... <-- Instruction Description Text
character Desc-
ription for....
each Instruc-..
tion.....
SYMBOL..... <-- 15 Character Symbol (if in Normal Mode)
I:15 <-- Instruction's Address - NOTE: If Symbol REPLACE mode is enabled Symbol will be here instead
----- () -----
17
IAD <-- The Type of I/O Card if address is a real I/O Point
(5:123) <-- Input Cross Reference (if enabled) '5:' is the file # and 123 is the rung #
that the contact is used as an output
Output Cross Reference - Each address used in each output instruction is displayed and cross
referenced here.

Right power rail can selectively be enabled/disabled

Appendix 8: Material balances for the 8-foot column long-term test

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone (Shell Mining Co.) Naugatuck, WV, Long Term	Test No: 1

Sample Characteristics:	
Percent Solids (As Received)	3.76
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	24 feet
Diameter	8 feet
Feed Entry Point	5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.66	Deisel
Frother	0.59	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	160 (cfm)		
Wash Water Flowrate	225		
Feed Flowrate	1000		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	6.81	93.19			
Reject	66.76	33.24			
Feed	45.66	54.34			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	35.20	5.25	60.36			
Reject	64.80	94.75	39.64			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone (Shell Mining Co.) Naugatuck, WV, Long Term	Test No: 2

Sample Characteristics:	
Percent Solids (As Received)	3.90
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	24 feet
Diameter	8 feet
Feed Entry Point	5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.70	Diesel
Frother	0.63	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	160 (cfm)		
Wash Water Flowrate	206		
Feed Flowrate	908		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	6.47	93.53			
Reject	71.65	28.35			
Feed	59.07	40.93			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	19.30	2.11	44.10			
Reject	80.70	97.89	55.90			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone (Shell Mining Co.) Naugatuck, WV, Long Term	Test No: 3

Sample Characteristics:	
Percent Solids (As Received)	3.90
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	24 feet
Diameter	8 feet
Feed Entry Point	5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.70	Diesel
Frother	0.63	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	160 (cfm)		
Wash Water Flowrate	206		
Feed Flowrate	908		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.83	91.17			
Reject	73.01	26.99			
Feed	55.18	44.82			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	27.78	4.45	56.51			
Reject	72.22	95.55	43.49			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone (Shell Mining Co.) Naugatuck, WV, Long Term	Test No: 4

Sample Characteristics:	
Percent Solids (As Received)	3.90
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	24 feet
Diameter	8 feet
Feed Entry Point	5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.70	
Frother	0.63	
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	160 (cfm)		
Wash Water Flowrate	206		
Feed Flowrate	908		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	7.46	92.54			
Reject	73.96	28.04			
Feed	55.14	44.86			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	28.30	3.82	58.38			
Reject	71.70	96.18	41.62			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone (Shell Mining Co.) Naugatuck, WV, Long Term	Test No: 5

Sample Characteristics:	
Percent Solids (As Received)	3.91
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	24 feet
Diameter	8 feet
Feed Entry Point	5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.66	Diesel
Frother	0.60	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	160 (cfm)		
Wash Water Flowrate	230		
Feed Flowrate	955		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	7.40	92.60			
Reject	72.03	27.97			
Feed	52.29	47.71			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	30.54	4.32	59.28			
Reject	69.46	95.68	40.72			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone (Shell Mining Co.) Naugatuck, WV, Long Term	Test No: 6

Sample Characteristics:	
Percent Solids (As Received)	3.90
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	24 feet
Diameter	8 feet
Feed Entry Point	5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.71	Diesel
Frother	0.68	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	160 (cfm)		
Wash Water Flowrate	225		
Feed Flowrate	861		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	6.49	93.51			
Reject	71.84	28.16			
Feed	49.28	50.72			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	34.52	4.55	63.65			
Reject	65.48	95.45	36.35			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone (Shell Mining Co.) Naugatuck, WV, Long Term	Test No: 7

Sample Characteristics:	
Percent Solids (As Received)	3.90
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	24 feet
Diameter	8 feet
Feed Entry Point	5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.66	Diesel
Frother	0.63	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	160 (cfm)		
Wash Water Flowrate	225		
Feed Flowrate	908		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	6.89	93.11			
Reject	73.03	26.97			
Feed	46.65	53.35			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	39.88	5.89	69.61			
Reject	60.12	94.10	30.39			
Feed	100	100	100	100	100	100

MICROBUBBLE COLUMN FLOTATION TESTWORK	Date:
Sample: Marrowbone (Shell Mining Co.) Naugatuck, WV, Long Term	Test No: 8

Sample Characteristics:	
Percent Solids (As Received)	3.92
Particle Size	-150 mesh

Column Geometry:	
Overall Height (bubble generators to cell lip)	24 feet
Diameter	8 feet
Feed Entry Point	5 feet
Froth Height	40 inches

Reagent Additions:	Dosage (lbs/ton)	Type
Collector	0.37	Diesel
Frother	0.39	DF1012
pH Modifier		
Dispersant		

Column Flows:	gpm	gms/min	% solids
Gas Flowrate	160 (cfm)		
Wash Water Flowrate	215		
* Feed Flowrate	1347*		
Product Flowrate			
Reject (Tailings) Flowrate			

Assays:	Ash (%)	Comb. (%)	Tot. S (%)	Pyr. S (%)	Btu/lb
Product	8.29	91.71			
Reject	80.25	19.75			
Feed	59.58	40.42			

Recoveries (%):	Yield	Ash	Comb.	Tot. S	Pyr. S	Btu
Product	28.72	3.99	65.17			
Reject	71.28	96.01	34.83			
Feed	100	100	100	100	100	100

Appendix 9: Summary of the statistical data analysis computations for the 8-foot column
parametric test program

Design Expert Data Analysis for Yield

=====

Response: Yield; File = MICROCEL

=====

VAR	VARIABLE	UNITS	-1 LEVEL	+1 LEVEL
X1	Frother	cc/min	50.000	100.000
X2	Collector	cc/min	50.000	150.000
X3	Aeration	scfm	120.000	200.000
X4	Wash Water	gpm	150.000	250.000

Results of Linear Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	301.2185	4	75.30463	3.374	0.0370
ERROR	334.7655	15	22.31770		
COR TOTAL	635.9840	19			
ROOT MSE	4.72416		R-SQUARED	0.4736	
DEP MEAN	23.43750		ADJ R-SQUARED	0.3333	
C.V.	20.16%				

Predicted Residual Sum of Squares (PRESS) = 576.9949

Results of Quadratic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	421.2056	11	38.29142	1.426	0.3138
ERROR	214.7783	8	26.84729		
COR TOTAL	635.9840	19			
ROOT MSE	5.18144		R-SQUARED	0.6623	
DEP MEAN	23.43750		ADJ R-SQUARED	0.1979	
C.V.	22.11%				

Predicted Residual Sum of Squares (PRESS) = 1292.4295

Results of Cubic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	528.1775	15	35.21183	1.306	0.4360
ERROR	107.8065	4	26.95163		
COR TOTAL	635.9840	19			
ROOT MSE	5.19150		R-SQUARED	0.8305	
DEP MEAN	23.43750		ADJ R-SQUARED	0.1948	
C.V.	22.15%				
Predicted Residual Sum of Squares (PRESS) =				353.3429	

ANOVA Summary of models fit

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
LINEAR	301.2185	4	75.3046	3.374	0.0370
QUADRATIC	119.9871	7	17.1410	0.6385	0.7161
CUBIC	106.9718	4	26.7430	0.9923	0.5029
ERROR	107.8065	4	26.9516		
COR TOTAL	635.9840	19			

Lack of Fit tests

MODEL	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
LINEAR	227.5950	12	18.9662	0.5309	0.8138
QUADRATIC	107.6078	5	21.5216	0.6024	0.7109
CUBIC	0.6360	1	0.6360	1.78E-02	0.9023
PURE ERR	107.1705	3	35.7235		

=====

Response: Yield; File = MICROCEL

=====

VAR	VARIABLE	UNITS	-1 LEVEL	+1 LEVEL
X1	Frother	cc/min	50.000	100.000
X2	Collector	cc/min	50.000	150.000
X3	Aeration	scfm	120.000	200.000
X4	Wash Water	gpm	150.000	250.000

Results of Cubic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	528.1775	15	35.21183	1.306	0.4360
ERROR	107.8065	4	26.95163		
COR TOTAL	635.9840	19			

ROOT MSE	5.19150	R-SQUARED	0.8305
DEP MEAN	23.43750	ADJ R-SQUARED	0.1948
C.V.	22.15%		

Predicted Residual Sum of Squares (PRESS) = 353.3429

VARIABLE	PARAMETER ESTIMATE	DF	STANDARD ERROR	t FOR H0 PARAMETER=0	PROB > t
Intercept	22.14500	1	2.59575	8.531	
X1	1.99813	1	1.29787	1.540	0.1985
X2	0.47313	1	1.29787	0.3645	0.7339
X3	3.81813	1	1.29787	2.942	0.0423
X4	0.17813	1	1.29787	0.1372	0.8975
X1*X1	1.61563	1	2.90213	0.5567	0.6074
X2*X2	ALIASED	0			
X3*X3	ALIASED	0			
X4*X4	ALIASED	0			
X1*X2	-1.22437	1	1.29787	-0.9434	0.3989
X1*X3	-0.19437	1	1.29787	-0.1498	0.8882
X1*X4	-0.03687	1	1.29787	-2.84E-02	0.9787
X2*X3	-2.29687	1	1.29787	-1.770	0.1515
X2*X4	0.27812	1	1.29787	0.2143	0.8408
X3*X4	0.29312	1	1.29787	0.2259	0.8324
X1*X1*X1	ALIASED	0			
X2*X2*X2	ALIASED	0			
X3*X3*X3	ALIASED	0			
X4*X4*X4	ALIASED	0			
X1*X1*X2	ALIASED	0			
X1*X1*X3	ALIASED	0			
X1*X1*X4	ALIASED	0			
X2*X2*X3	ALIASED	0			
X2*X2*X4	ALIASED	0			

X3*X3*X4	ALIASED	0			
X1*X2*X2	ALIASED	0			
X1*X3*X3	ALIASED	0			
X1*X4*X4	ALIASED	0			
X2*X3*X3	ALIASED	0			
X2*X4*X4	ALIASED	0			
X3*X4*X4	ALIASED	0			
X1*X2*X3	-0.61938	1	1.29787	-0.4772	0.6581
X1*X2*X4	-1.01187	1	1.29787	-0.7796	0.4792
X1*X3*X4	-2.22187	1	1.29787	-1.712	0.1621
X2*X3*X4	-0.58437	1	1.29787	-0.4503	0.6759

Std ERROR 1.16085

Obs Ord	ACTUAL VALUE	PREDICTED VALUE	RESIDUAL	LEVER	STUDENT RESID	COOK'S DIST	t VALUE	Run Ord
1	18.35000	18.54938	-0.19938	0.937	-0.154	0.022	-0.306	20
2	17.95000	17.75063	0.19937	0.937	0.154	0.022	0.306	5
3	21.75000	21.55063	0.19937	0.937	0.154	0.022	0.306	18
4	22.18000	22.37938	-0.19938	0.937	-0.154	0.022	-0.306	19
5	23.93000	23.73063	0.19937	0.937	0.154	0.022	0.306	9
6	33.32000	33.51938	-0.19938	0.937	-0.154	0.022	-0.306	16
7	22.16000	22.35938	-0.19938	0.937	-0.154	0.022	-0.306	6
8	29.02000	28.82063	0.19937	0.937	0.154	0.022	0.306	7
9	10.40000	10.20063	0.19937	0.937	0.154	0.022	0.306	1
10	21.99000	22.18938	-0.19938	0.937	-0.154	0.022	-0.306	17
11	20.50000	20.69938	-0.19938	0.937	-0.154	0.022	-0.306	14
12	26.42000	26.22063	0.19937	0.937	0.154	0.022	0.306	10
13	27.58000	27.77938	-0.19938	0.937	-0.154	0.022	-0.306	8
14	32.78000	32.58063	0.19937	0.937	0.154	0.022	0.306	15
15	29.43000	29.23063	0.19937	0.937	0.154	0.022	0.306	12
16	22.41000	22.60938	-0.19938	0.937	-0.154	0.022	-0.306	3
17	16.83000	22.14500	-5.31500	0.250	-1.182	0.029	-1.907	2
18	25.80000	22.14500	3.65500	0.250	0.813	0.014	1.486	13
19	17.31000	22.14500	-4.83500	0.250	-1.075	0.024	-1.813	4
20	28.64000	22.14500	6.49500	0.250	1.445	0.043	1.998	11

Design Expert Data Analysis for Product Ash

=====

Response: Product Ash; File = MICROCEL

=====

VAR	VARIABLE	UNITS	-1 LEVEL	+1 LEVEL
X1	Frother	cc/min	50.000	100.000
X2	Collector	cc/min	50.000	150.000
X3	Aeration	scfm	120.000	200.000
X4	Wash Water	gpm	150.000	250.000

Results of Linear Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	11.64992	4	2.912481	20.85	0.0001
ERROR	2.09553	15	0.139702		
COR TOTAL	13.74545	19			
ROOT MSE	0.373767		R-SQUARED	0.8475	
DEP MEAN	7.486500		ADJ R-SQUARED	0.8069	
C.V.	4.99%				

Predicted Residual Sum of Squares (PRESS) = 3.88715

Results of Quadratic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	13.15147	11	1.195589	16.10	0.0003
ERROR	0.59398	8	0.074248		
COR TOTAL	13.74545	19			
ROOT MSE	0.272484		R-SQUARED	0.9568	
DEP MEAN	7.486500		ADJ R-SQUARED	0.8974	
C.V.	3.64%				

Predicted Residual Sum of Squares (PRESS) = 3.32622

Results of Cubic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	13.40350	15	0.893567	10.45	0.0177
ERROR	0.34196	4	0.085489		
COR TOTAL	13.74545	19			
ROOT MSE	0.292385		R-SQUARED	0.9751	
DEP MEAN	7.486500		ADJ R-SQUARED	0.8818	
C.V.	3.91%				

Predicted Residual Sum of Squares (PRESS) = 4.74062

ANOVA Summary of models fit

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
LINEAR	11.64992	4	2.91248	20.85	0.0001
QUADRATIC	1.50155	7	0.21451	2.889	0.0802
CUBIC	0.25203	4	0.06301	0.7370	0.6127
ERROR	0.34196	4	0.08549		
COR TOTAL	13.74545	19			

Lack of Fit tests

MODEL	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
LINEAR	1.76983	12	0.14749	1.358	0.4496
QUADRATIC	0.26828	5	0.05366	0.4942	0.7707
CUBIC	0.01626	1	0.01626	0.1497	0.7246
PURE ERR	0.32570	3	0.10857		

=====

Response: Product Ash; File = MICROCEL

=====

VAR	VARIABLE	UNITS	-1 LEVEL	+1 LEVEL
X1	Frother	cc/min	50.000	100.000
X2	Collector	cc/min	50.000	150.000
X3	Aeration	scfm	120.000	200.000
X4	Wash Water	gpm	150.000	250.000

Results of Cubic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	13.40350	15	0.893567	10.45	0.0177
ERROR	0.34196	4	0.085489		
COR TOTAL	13.74545	19			

ROOT MSE	0.292385	R-SQUARED	0.9751
DEP MEAN	7.486500	ADJ R-SQUARED	0.8818
C.V.	3.91%		

Predicted Residual Sum of Squares (PRESS) = 4.74062

VARIABLE	PARAMETER ESTIMATE	DF	STANDARD ERROR	t FOR HO PARAMETER=0	PROB > t
Intercept	7.335000	1	0.146193	50.17	
X1	0.193125	1	0.073096	2.642	0.0575
X2	0.024375	1	0.073096	0.3335	0.7555
X3	0.800625	1	0.073096	10.95	0.0004
X4	-0.221875	1	0.073096	-3.035	0.0386
X1*X1	0.189375	1	0.163448	1.159	0.3111
X2*X2	ALIASED	0			
X3*X3	ALIASED	0			
X4*X4	ALIASED	0			
X1*X2	0.130625	1	0.073096	1.787	0.1485
X1*X3	-0.043125	1	0.073096	-0.5900	0.5869
X1*X4	-0.003125	1	0.073096	-4.28E-02	0.9679
X2*X3	-0.256875	1	0.073096	-3.514	0.0246
X2*X4	-0.001875	1	0.073096	-2.57E-02	0.9808
X3*X4	0.041875	1	0.073096	0.5729	0.5974
X1*X1*X1	ALIASED	0			
X2*X2*X2	ALIASED	0			
X3*X3*X3	ALIASED	0			
X4*X4*X4	ALIASED	0			
X1*X1*X2	ALIASED	0			
X1*X1*X3	ALIASED	0			
X1*X1*X4	ALIASED	0			
X2*X2*X3	ALIASED	0			
X2*X2*X4	ALIASED	0			

X3*X3*X4	ALIASED	0				
X1*X2*X2	ALIASED	0				
X1*X3*X3	ALIASED	0				
X1*X4*X4	ALIASED	0				
X2*X3*X3	ALIASED	0				
X2*X4*X4	ALIASED	0				
X3*X4*X4	ALIASED	0				
X1*X2*X3	-0.038125	1	0.073096	-0.5216	0.6295	
X1*X2*X4	-0.065625	1	0.073096	-0.8978	0.4201	
X1*X3*X4	-0.091875	1	0.073096	-1.257	0.2772	
X2*X3*X4	0.039375	1	0.073096	0.5387	0.6187	

Std ERROR 0.065379

Obs Ord	ACTUAL VALUE	PREDICTED VALUE	RESIDUAL	LEVER	STUDENT RESID	COOK'S DIST	t VALUE	Run Ord
1	6.720000	6.751875	-0.031875	0.937	-0.436	0.178	-0.851	20
2	6.610000	6.578125	0.031875	0.937	0.436	0.178	0.851	5
3	6.960000	6.928125	0.031875	0.937	0.436	0.178	0.851	18
4	7.660000	7.691875	-0.031875	0.937	-0.436	0.178	-0.851	19
5	8.720000	8.688125	0.031875	0.937	0.436	0.178	0.851	9
6	8.830000	8.861875	-0.031875	0.937	-0.436	0.178	-0.851	16
7	7.800000	7.831875	-0.031875	0.937	-0.436	0.178	-0.851	6
8	8.670000	8.638125	0.031875	0.937	0.436	0.178	0.851	7
9	6.030000	5.998125	0.031875	0.937	0.436	0.178	0.851	1
10	6.410000	6.441875	-0.031875	0.937	-0.436	0.178	-0.851	17
11	6.240000	6.271875	-0.031875	0.937	-0.436	0.178	-0.851	14
12	7.160000	7.128125	0.031875	0.937	0.436	0.178	0.851	10
13	8.280000	8.311875	-0.031875	0.937	-0.436	0.178	-0.851	8
14	8.400000	8.368125	0.031875	0.937	0.436	0.178	0.851	15
15	7.900000	7.868125	0.031875	0.937	0.436	0.178	0.851	12
16	8.000000	8.031875	-0.031875	0.937	-0.436	0.178	-0.851	3
17	7.700000	7.335000	0.365000	0.250	1.441	0.043	1.998	2
18	7.350000	7.335000	0.015000	0.250	0.059	0.000	0.118	13
19	6.900000	7.335000	-0.435000	0.250	-1.718	0.061	-1.759	4
20	7.390000	7.335000	0.055000	0.250	0.217	0.001	0.432	11

Design Expert Data Analysis for Separation Efficiency

=====

Response: Seperation; File = MICROCEL

=====

VAR	VARIABLE	UNITS	-1 LEVEL	+1 LEVEL
X1	Frother	cc/min	50.000	100.000
X2	Collector	cc/min	50.000	150.000
X3	Aeration	scfm	120.000	200.000
X4	Wash Water	gpm	150.000	250.000

Results of Linear Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	1054.434	4	263.60838	5.662	0.0055
ERROR	698.402	15	46.56016		
COR TOTAL	1752.836	19			
ROOT MSE	6.82350		R-SQUARED	0.6016	
DEP MEAN	46.08550		ADJ R-SQUARED	0.4953	
C.V.	14.81%				

Predicted Residual Sum of Squares (PRESS) = 1205.037

Results of Quadratic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	1286.678	11	116.97076	2.007	0.1660
ERROR	466.157	8	58.26969		
COR TOTAL	1752.836	19			
ROOT MSE	7.63346		R-SQUARED	0.7341	
DEP MEAN	46.08550		ADJ R-SQUARED	0.3684	
C.V.	16.56%				

Predicted Residual Sum of Squares (PRESS) = 2815.743

Results of Cubic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	1520.262	15	101.35082	1.743	0.3140
ERROR	232.574	4	58.14339		
COR TOTAL	1752.836	19			
ROOT MSE	7.62518		R-SQUARED	0.8673	
DEP MEAN	46.08550		ADJ R-SQUARED	0.3698	
C.V.	16.55%				

Predicted Residual Sum of Squares (PRESS) = 725.282

ANOVA Summary of models fit

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
LINEAR	1054.434	4	263.608	5.662	0.0055
QUADRATIC	232.245	7	33.178	0.5694	0.7638
CUBIC	233.584	4	58.396	1.004	0.4984
ERROR	232.574	4	58.143		
COR TOTAL	1752.836	19			

Lack of Fit tests

MODEL	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
LINEAR	467.055	12	38.921	0.5047	0.8294
QUADRATIC	234.810	5	46.962	0.6090	0.7075
CUBIC	1.227	1	1.227	1.59E-02	0.9076
PURE ERR	231.347	3	77.116		

=====

Response: Seperation; File = MICROCEL

=====

VAR	VARIABLE	UNITS	-1 LEVEL	+1 LEVEL
X1	Frother	cc/min	50.000	100.000
X2	Collector	cc/min	50.000	150.000
X3	Aeration	scfm	120.000	200.000
X4	Wash Water	gpm	150.000	250.000

Results of Cubic Response Surface Model Fitting

ANOVA for Selected Model

SOURCE	SUM OF SQUARES	DF	MEAN SQUARE	F VALUE	PROB > F
MODEL	1520.262	15	101.35082	1.743	0.3140
ERROR	232.574	4	58.14339		
COR TOTAL	1752.836	19			

ROOT MSE	7.62518	R-SQUARED	0.8673
DEP MEAN	46.08550	ADJ R-SQUARED	0.3698
C.V.	16.55%		

Predicted Residual Sum of Squares (PRESS) = 725.282

VARIABLE	PARAMETER ESTIMATE	DF	STANDARD ERROR	t FOR H0 PARAMETER=0	PROB > t
Intercept	44.99000	1	3.81259	11.80	
X1	4.09313	1	1.90630	2.147	0.0983
X2	1.62437	1	1.90630	0.8521	0.4422
X3	6.75688	1	1.90630	3.545	0.0239
X4	0.92437	1	1.90630	0.4849	0.6531
X1*X1	1.36938	1	4.26261	0.3213	0.7641
X2*X2	ALIASED	0			
X3*X3	ALIASED	0			
X4*X4	ALIASED	0			
X1*X2	-1.25688	1	1.90630	-0.6593	0.5457
X1*X3	-0.41437	1	1.90630	-0.2174	0.8386
X1*X4	0.08062	1	1.90630	4.23E-02	0.9683
X2*X3	-3.38812	1	1.90630	-1.777	0.1501
X2*X4	0.73938	1	1.90630	0.3879	0.7179
X3*X4	0.59688	1	1.90630	0.3131	0.7698
X1*X1*X1	ALIASED	0			
X2*X2*X2	ALIASED	0			
X3*X3*X3	ALIASED	0			
X4*X4*X4	ALIASED	0			
X1*X1*X2	ALIASED	0			
X1*X1*X3	ALIASED	0			
X1*X1*X4	ALIASED	0			
X2*X2*X3	ALIASED	0			
X2*X2*X4	ALIASED	0			

X3*X3*X4	ALIASED	0			
X1*X2*X2	ALIASED	0			
X1*X3*X3	ALIASED	0			
X1*X4*X4	ALIASED	0			
X2*X3*X3	ALIASED	0			
X2*X4*X4	ALIASED	0			
X3*X4*X4	ALIASED	0			
X1*X2*X3	-0.59937	1	1.90630	-0.3144	0.7689
X1*X2*X4	-1.10937	1	1.90630	-0.5820	0.5918
X1*X3*X4	-3.50688	1	1.90630	-1.840	0.1397
X2*X3*X4	-0.84312	1	1.90630	-0.4423	0.6811

Std ERROR 1.70504

Obs Ord	ACTUAL VALUE	PREDICTED VALUE	RESIDUAL	LEVER	STUDENT RESID	COOK'S DIST	t VALUE	Run Ord
1	35.10000	35.37687	-0.27687	0.937	-0.145	0.020	-0.290	20
2	36.59000	36.31312	0.27688	0.937	0.145	0.020	0.290	5
3	41.61000	41.33312	0.27688	0.937	0.145	0.020	0.290	18
4	43.80000	44.07687	-0.27687	0.937	-0.145	0.020	-0.290	19
5	45.68000	45.40312	0.27688	0.937	0.145	0.020	0.290	9
6	60.83000	61.10687	-0.27687	0.937	-0.145	0.020	-0.290	16
7	43.30000	43.57687	-0.27687	0.937	-0.145	0.020	-0.290	6
8	56.57000	56.29312	0.27688	0.937	0.145	0.020	0.290	7
9	23.75000	23.47312	0.27688	0.937	0.145	0.020	0.290	1
10	42.92000	43.19687	-0.27687	0.937	-0.145	0.020	-0.290	17
11	39.92000	40.19687	-0.27687	0.937	-0.145	0.020	-0.290	14
12	53.13000	52.85312	0.27688	0.937	0.145	0.020	0.290	10
13	53.01000	53.28687	-0.27687	0.937	-0.145	0.020	-0.290	8
14	60.00000	59.72312	0.27688	0.937	0.145	0.020	0.290	15
15	55.76000	55.48312	0.27688	0.937	0.145	0.020	0.290	12
16	49.78000	50.05687	-0.27687	0.937	-0.145	0.020	-0.290	3
17	36.76000	44.99000	-8.23000	0.250	-1.246	0.032	-1.949	2
18	49.85000	44.99000	4.86000	0.250	0.736	0.011	1.369	13
19	38.48000	44.99000	-6.51000	0.250	-0.986	0.020	-1.715	4
20	54.87000	44.99000	9.88000	0.250	1.496	0.047	1.986	11

Appendix 10: Predicted response surfaces for product ash percent (Figs. A), product yield (Figs. B), and separation efficiency (Figs. C)

Model:
Cubic

Response:
Product Ash

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 50.00
Wash Water = 150.0

Model:
Cubic

Response:
Product Ash

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 50.00
Wash Water = 200.0

Figure A: Predicted response surfaces for product ash percent for various column operating conditions (continued).

Figure A: Predicted response surfaces for product ash percent for various column operating conditions (continued).

Model:
Cubic

Response:
Product Ash

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 100.0
Wash Water = 200.0

Model:
Cubic

Response:
Product Ash

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 100.0
Wash Water = 250.0

Figure A: Predicted response surfaces for product ash percent for various column operating conditions (continued).

Model:
Cubic

Response:
Product Ash

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 150.0
Wash Water = 150.0

Model:
Cubic

Response:
Product Ash

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 150.0
Wash Water = 200.0

Figure A: Predicted response surfaces for product ash percent for various column operating conditions (continued).

Figure A: Predicted response surfaces for product ash percent for various column operating conditions.

Model:
Cubic

Response:
Yield

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 50.00
Wash Water = 150.0

Model:
Cubic

Response:
Yield

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 50.00
Wash Water = 200.0

Figure B: Predicted response surfaces for product yield for various column operating conditions (continued).

Model:
Cubic

Response:
Yield

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 50.00
Wash Water = 250.0

Model:
Cubic

Response:
Yield

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 100.0
Wash Water = 150.0

Figure B: Predicted response surfaces for product yield for various column operating conditions (continued).

Model:
Cubic

Response:
Yield

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 100.0
Wash Water = 200.0

Model:
Cubic

Response:
Yield

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 100.0
Wash Water = 250.0

Figure B: Predicted response surfaces for product yield for various column operating conditions (continued).

Model:
Cubic

Response:
Yield

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 150.0
Wash Water = 150.0

Model:
Cubic

Response:
Yield

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 150.0
Wash Water = 200.0

Figure B: Predicted response surfaces for product yield for various column operating conditions (continued).

Figure B: Predicted response surfaces for product yield for various column operating conditions.

Model:
Cubic

Response:
Seperation

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 50.00
Wash Water = 150.0

Model:
Cubic

Response:
Seperation

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 50.00
Wash Water = 200.0

Figure C: Predicted response surfaces for separation efficiency for various column operating conditions (continued).

Model:
Cubic

Response:
Seperation

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 50.00
Wash Water = 250.0

Model:
Cubic

Response:
Seperation

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 100.0
Wash Water = 150.0

Figure C: Predicted response surfaces for separation efficiency for various column operating conditions (continued).

Model:
Cubic

Response:
Seperation

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 100.0
Wash Water = 200.0

Model:
Cubic

Response:
Seperation

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 100.0
Wash Water = 250.0

Figure C: Predicted response surfaces for separation efficiency for various column operating conditions (continued).

Model:
Cubic

Response:
Seperation

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 150.0
Wash Water = 150.0

Model:
Cubic

Response:
Seperation

Variables:
X = Frother
Y = Aeration

Constants:
Collector = 150.0
Wash Water = 200.0

Figure C: Predicted response surfaces for separation efficiency for various column operating conditions (continued).

Figure C: Predicted response surfaces for separation efficiency for various column operating conditions.

Appendix 11: Cash flow analyses

Cash Flow and Rate of Return Comparisons
Estimate: \$20/ton, 10% Loss of Fines
IRR = 2.42

	Initial	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	Total
Capital Investment	163875											-163875
Estimated revenues 29090 tons @\$20		581800	610890	641435	673506	707182	742541	779668	818651	859584	902563	7317818
Operating costs		190601	200131	210138	220644	231677	243261	255424	268195	281604	295685	2397359
Annual cash flow	-163875	391199	410759	431297	452862	475505	499280	524244	550456	577979	606878	4756584
Cash flow - prior yr		-163875	227324	638083	1069380	1522242	1997746	2497026	3021271	3571727	4149706	
Total net cash flow	-163875	227324	638083	1069380	1522242	1997746	2497026	3021271	3571727	4149706	4756584	

Cash Flow and Rate of Return Comparisons
Estimate: \$20/ton, 20% Loss in Fines
IRR = 1.97

	Initial	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	Total
Capital Investment	163875											-163875
Estimated revenues 25524 tons @\$20		510480	536004	562804	590944	620492	651516	684092	718297	754211	791922	6420763
Operating costs		190601	200131	210138	220644	231677	243261	255424	268195	281604	295685	2397359
Annual cash flow	-163875	319879	335873	352667	370300	388815	408256	428668	450102	472607	496237	3859529
Cash flow - prior yr		-163875	156004	491877	844544	1214843	1603658	2011914	2440583	2890684	3363291	
Total net cash flow	-163875	156004	491877	844544	1214843	1603658	2011914	2440583	2890684	3363291	3859529	

Cash Flow and Rate of Return Comparisons

Estimate: \$20/ton, 30% Loss in Fines

IRR = 1.6

	Initial	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	Total
Capital Investment	163875											-163875
Estimated revenues 22334 tons @\$20		446680	469014	492465	517088	542942	570089	598594	628524	659950	692947	5618293
Operating costs		190601	200131	210138	220644	231677	243261	255424	268195	281604	295685	2397359
Annual cash flow	-163875	256079	268883	282327	296443	311266	326829	343170	360329	378345	397263	3057059
Cash flow - prior yr		-163875	92204	361087	643414	939857	1251123	1577952	1921122	2281451	2659797	
Total net cash flow	-163875	92204	361087	643414	939857	1251123	1577952	1921122	2281451	2659797	3057059	

Cash Flow and Rate of Return Comparisons

Estimate: \$25/ton, 10% Loss in Fines

IRR = 3.29

	Initial	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	Total
Capital Investment	163875											-163875
Estimated revenues 29090 tons @ \$25	727250	763613	801793	841883	883977	928176	974585	1023314	1074479	1128203	1182203	9147272
Operating costs	190601	200131	210138	220644	231677	243261	255424	268195	281604	295685	3097359	2397359
Annual cash flow	-163875	536649	563481	591656	621238	652300	684915	719161	755119	792875	832519	6586038
Cash flow - prior yr	-163875	372774	372774	936255	1527911	2149149	2801449	3486365	4205526	4960645	5753520	
Total net cash flow	-163875	372774	936255	1527911	2149149	2801449	3486365	4205526	4960645	5753520	6586038	

Cash Flow and Rate of Return Comparisons

Estimate: \$25/ton, 20% Loss in Fines

IRR = 2.75

	Initial	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	Total
Capital Investment	163875											-163875
Estimated revenues 25524 tons @\$25		638100	670005	703505	738681	775615	814395	855115	897871	942764	989903	8025953
Operating costs		190601	200131	210138	220644	231677	243261	255424	268195	281604	295685	2397359
Annual cash flow	-163875	447499	469874	493368	518036	543938	571135	599691	629676	661160	694218	5464719
Cash flow - prior yr		-163875	283624	753498	1246866	1764902	2308839	2879974	3479666	4109342	4770502	
Total net cash flow	-163875	283624	753498	1246866	1764902	2308839	2879974	3479666	4109342	4770502	5464719	

Cash Flow and Rate of Return Comparisons
Estimate: \$25/ton, 30% Loss in Fines
IRR = 2.26

	Initial	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	Total
Capital Investment	163875											-163875
Estimated revenues 22334 tons @ \$25		558350	586268	615581	646360	678678	712612	748242	785655	824937	866184	7022866
Operating costs		190601	200131	210138	220644	231677	243261	255424	268195	281604	295685	2397359
Annual cash flow	-163875	367749	386136	405443	425715	447001	469351	492819	517460	543333	570499	4461632
Cash flow - prior yr		-163875	203874	590010	995454	1421169	1868170	2337522	2830340	3347800	3891133	
Total net cash flow	-163875	203874	590010	995454	1421169	1868170	2337522	2830340	3347800	3891133	4461632	

Cash Flow and Rate of Return Comparisons

Estimate: \$30/ton, 10% Loss in Fines

IRR = 4.18

	Initial	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	Total
Capital Investment	163875											-163875
Estimated revenues 29090 tons @\$30	872700	916335	962152	1010259	1060772	1113811	1169501	1227977	1289375	1353844	10976727	
Operating costs	190601	200131	210138	220644	231677	243261	255424	268195	281604	295685	2397359	
Annual cash flow	-163875	682099	716204	752014	789615	829096	870550	914078	959782	1007771	1058159	8415493
Cash flow - prior yr		-163875	518224	1234428	1986442	2776057	3605153	4475703	5389781	6349563	7357333	
Total net cash flow	-163875	518224	1234428	1986442	2776057	3605153	4475703	5389781	6349563	7357333	8415493	

Cash Flow and Rate of Return Comparisons
Estimate: \$30/ton, 20% Loss in Fines
IRR = 3.52

	Initial	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	Total
Capital Investment	163875											-163875
Estimated revenues 25524 tons @\$30		765720	804006	844206	886417	930737	977274	1026138	1077445	1131317	1187883	9631144
Operating costs		190601	200131	210138	220644	231677	243261	255424	268195	281604	295685	2397359
Annual cash flow	-163875	575119	603875	634069	665772	699061	734014	770714	809250	849713	892198	7069910
Cash flow - prior yr		-163875	411244	1015119	1649188	2314960	3014021	3748034	4518749	5327999	6177712	
Total net cash flow	-163875	411244	1015119	1649188	2314960	3014021	3748034	4518749	5327999	6177712	7069910	

Cash Flow and Rate of Return Comparisons

Estimate: \$30/ton, 30% Loss in Fines

IRR = 2.94

	Initial	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	Total
Capital Investment	163875											-163875
Estimated revenues 22334 tons @ \$30	670020	703521	738697	775632	814413	855134	897891	942785	989925	1039421	1039421	8427440
Operating costs	190601	200131	210138	220644	231677	243261	255424	268195	281604	295685	295685	2397359
Annual cash flow	-163875	479419	503390	528559	554987	582737	611874	642467	674591	708320	743736	5866206
Cash flow - prior yr	-163875	315544	818934	818934	1347493	1902481	2485218	3097091	3739559	4414149	5122469	
Total net cash flow	-163875	315544	818934	1347493	1902481	2485218	3097091	3739559	4414149	5122469	5866206	

END

**DATE
FILMED**

5 / 13 / 92