OPTIMIZATION OF REACTOR CONFIGURATION IN COAL LIQUEFACTION

FOURTH QUARTERLY REPORT FOR THE PERIOD

1 JULY 1992 - 30 SEPTEMBER 1992

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

A.G. Comolli
E.S. Johanson
L.K. Lee
R.M. Stalzer

WORK PERFORMED UNDER CONTRACT

DE-AC22-91PC-91052

HYDROCARBON RESEARCH, INC.
100 OVERLOOK CENTER, SUITE 400
PRINCETON, NEW JERSEY 08540

DECEMBER 1992

MASTER

DISSEMINATION OF THIS DOCUMENT IS UNLIMITED

DOE-91052-4

**OPTIMIZATION OF REACTOR CONFIGURATION
IN COAL LIQUEFACTION**

**FOURTH QUARTERLY REPORT FOR THE PERIOD
1 JULY 1992 - 30 SEPTEMBER 1992**

A.G. Comolli
E.S. Johanson
L.K. Lee
R.M. Stalzer

**WORK PERFORMED UNDER CONTRACT
DE-AC22-91PC-91052**

**HYDROCARBON RESEARCH, INC.
100 OVERLOOK CENTER, SUITE 400
PRINCETON, NEW JERSEY 08540**

RECEIVED

MAR 24 1993

OSTI

DECEMBER 1992

PRINTED IN THE UNITED STATES OF AMERICA

AVAILABLE FROM:

**National Technical Information Center
U.S. Department of Energy
5285 Port Royal Road
Springfield, Virginia 22161**

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Department of Energy, nor any of their employees, makes any warranty, expressed or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, mark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendations, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

	TABLE OF CONTENTS	<u>PAGE</u>
ABSTRACT		1
SUMMARY		2
INTRODUCTION		3
TASK 2 - LABORATORY SUPPORT		4
TASK 3 - LABORATORY SCALE OPERATIONS-REACTOR CONFIGURATION		7
TASK 4 - TECHNICAL ASSESSMENT		16
TASK 5 - PROJECT MANAGEMENT		17

LIST OF FIGURES AND TABLES

FIGURE	TITLE	<u>PAGE</u>
1	HRI 3/8" Fixed Bed Reactor System Upflow Mode (Unit 254)	10
2	Optimization of Reactor Configurations: Work Plan	18
TABLE	TITLE	<u>PAGE</u>
1	Feed Slurry (L-722) Inspection Pressure Filter Liquid	5
2	Feed Slurry (L-722) Inspection Pressure Filter Cake	6
3	Hexahydropyrene as Solvent for Liquefying Coal and Filter Cake	8
4	Fixed Bed Operation: Run 254-01 Shell S-317 1/20" Trilobe Catalyst (HRI-6030)	13
5	Fixed Bed Operation: Run 254-02 Shell S-317 1/16" Extrudate Catalyst (HRI-5903)	14
6	Fixed Bed Operations (Run ACL-01 & 2)	15

ABSTRACT

This quarterly report covers activities of Optimization of Reactor Configuration in Coal Liquefaction during the period July 1 - September 30, 1992, at Hydrocarbon Research, Inc. in Lawrenceville and Princeton, New Jersey. This DOE contract period is from October 1, 1991 to September 30, 1993.

The overall objective of the program is to achieve a new approach to liquefaction that generates an all distillates product slate at reduced cost of about \$25 per barrel of crude oil equivalent.

The quarterly report covers work on Laboratory Support, Laboratory Scale Operations, Technical Assessment, and Project Management.

SUMMARY

Work undertaken in the fourth quarter concerned mostly with the commissioning of a laboratory scale fixed bed unit and testing of the fixed bed reactor configuration. Two catalysts, a trilobe and an extrudate catalyst, were evaluated in both upflow and downflow operation modes.

Results from the microautoclave tests using hexahydropyrene as solvent for determining the ultimate convertibility of coal are also discussed in this report.

A paper on reactor configuration in coal liquefaction was prepared for presentation for the Ninth Annual International Pittsburgh Coal Conference to be held in Pittsburgh on October 12-16, 1992.

INTRODUCTION

The studies conducted in this the fourth quarterly report of Contract No. DE-AC22-91PC-91052 is reported by task and in sequence.

Task 1 is the Project Work Plan and is complete. Task 2 is for Laboratory Support which includes feed and product characterization and general analytical support for Task 3. Task 3 is for Laboratory Scale Operations evaluating three reactor configurations: fixed bed reactor as a 'finishing' reactor, three-stage close-coupled Back-Mixed Reactor System, and interstage product stream concentration. Task 4 is the Technical Assessment, including modelling, design and economics. Task 5 is Project Management.

The contract period is October 1, 1991 to September 30, 1993.

TASK 2 - LABORATORY SUPPORT

The partially converted coal slurry (L-772) used in the earlier microautoclave screening tests was characterized. Its properties are summarized in *Tables 1 and 2*.

L-772 slurry composites of 84.6 W% of distillable and quinoline soluble oils, 12.1 and 3.35 W% of unconverted coal (quinoline insoluble organic matter) and SO₃-free ash, respectively. The coal conversion in respect to the fresh coal feed to the PDU operation is 74.6 W% (*Table 1*).

The pressure filter liquid derived from L-772 has an initial boiling point of 536°F and contains 11.1 W% of hydrogen. It also has a very low sulfur (0.019 W%) and nitrogen (0.05 W%) contents.

This partially converted slurry will be used in the laboratory scale operations for evaluating different reactor configurations in both microautoclave and continuous flow microreactor systems.

TABLE 1
FEED SLURRY (L-772) INSPECTION

Pressure Filter Liquid

Pressure Filtration, W%

Filter Liquid	74.73
Filter Cake	25.27

Filter Liquid

API Gravity	16.0
-------------	------

ASTM D-1160 Distillation, Vol% vs °F

IBP	536
5	591
10	618
20	644
30	666
40	687
50	708
60	730
70	756
80	807
90	938
92	975

B.P. Distribution, W%

IBP-650 °F	20.42
650-850 °F	62.30
850-1000 °F	8.85
1000 °F+	8.44

Elemental Analysis, W%

Carbon	88.65
Hydrogen	11.14
Nitrogen	0.050
Sulfur	0.019
H/C Ratio	1.51

TABLE 2
FEED SLURRY (L-772) INSPECTION

Pressure Filter Cake

	<u>Weight %</u>
Quinoline Solubles	39.03
Quinoline Insolubles (Ash-free)	47.71
Ash	15.21
Sulfur in Ash	5.14
SO ₃ -free Ash	13.21
Coal/Ash (SO ₃ -free)	3.60
Coal Conversion, maf W%	74.6
<u>Mineral Analysis of Ash</u> (W% of Ignited Sample)	
Silica, SiO ₂	33.33
Alumina, Al ₂ O ₃	18.72
Titania, TiO ₂	1.40
Ferric Oxide, Fe ₂ O ₃	7.86
Lime, CaO	19.92
Magnesia, MgO	3.96
Potassium Oxide, K ₂ O	0.35
Sodium Oxide, NaO	0.50
Sulfur Trioxide, SO ₃	9.83
Phosphorous Pentoxide, P ₂ O ₅	0.65
Strontium Oxide, SrO	0.10
Barium Oxide, BaO	1.62
Manganese Oxide, Mn ₃ O ₄	0.07
Undetermined	1.63

TASK 3 - LABORATORY SCALE OPERATIONS - REACTOR CONFIGURATION

A. MICROAUTOCLAVE SCREENING TESTS

Following reports by Sandia Laboratories that they have obtained high conversion with (96.2 W%) of Wyodak Coal in their microautoclave tests using hexahydropyrene, a pair of microautoclave tests have been carried out with this solvent, to find if the ultimate convertibility of such coals can be established by modification of HRI's microautoclave procedure with this solvent.

The coal conversions from this pair of tests did not differ greatly from those of HRI's standard tests which use coal liquefaction liquid as solvent. Further tests are planned to repeat the test with hexahydropyrene using the Sandia procedure as close as possible.

Test Results

Two tests were completed using fresh Black Thunder Mine coal and filter cake product from PDU Run 260-03 for the 30 minutes tests, at 800°F, and 2000 psig H₂ pressure.

The conversion of Black Thunder Mine coal in Test CM-120 was lower than obtained with the HRI-5887 coal in the standard coal evaluation tests, 91.7 and 91.4 W%, using HRI-5198 coal liquefaction liquid, *Table 3*.

The incremental coal conversion in Test CM-119 with Run 260-03 filter cake was virtually identical to that obtained in Microautoclave Test CM-115, which used the same solids as produced in the native liquid of the PDU operations (L-772 slurry containing 17.1 W% solids), where the conversion level was increased from 75.7 of the original coal to the PDU operation to 88.9% conversion.

TABLE 3
HEXAHYDROPYRENE AS SOLVENT
FOR LIQUEFYING COAL AND FILTER CAKE

Test	CM-119	CM-120
Test Conditions		
Feed Solid	Filter Cake	Black Thunder (HRI-5887)
Feed Solid, gm	2.00	2.00
Hexahydropyrene, gm	1.20	1.21
Decalin, gm	6.80	6.80
Catalyst, gm	2.00	2.00
Ash Recovery, W%	94.7	107.3
Coal Conversion, W%		
Feed Solid	75.5	0.0
Solids Product	89.1	87.2
Residuum		
W% Conv. Coal	35.9	

Note: Catalyst was presulfided (Ni/Mo catalyst HRI-5359P2).

B. SMALL FIXED BED REACTOR TESTS

Two continuous flow tests were completed using a partially converted slurry (L -772) generated from PDU Run 260-03 during this reporting period. Two different shaped and size, a 1/20" trilobe and a 1/16" extrudate, Ni/Mo supported catalysts were tested in both upflow and downflow mode of operations. Results from these tests are discussed in this report.

Objective

The main purpose of the these small scale flow tests were to evaluate the viability of using fixed bed reactor as a 'finishing' reactor in coal liquefaction.

Specifically, Run ACL-01 and ACL-02 was to determine space velocities at which solids in the feed slurry will not settle in the fixed bed reactor.

Equipment and Operations

The test system consists of one or two 3/8" I.D. fixed bed reactors connected in either upflow or downflow mode, *Figure 1*. The reactor(s) was uniformly heated by a fluidized sandbath heater. In the upflow mode of operation the feed slurry was preheated in an downcomer prior to entering the reactor at the bottom location. Contrarily, in the downflow mode the slurry entered the top of the reactor without any preheating. In the latter case the differential temperature between the reactor internal and sandbath heater may be considerable.

The slurry feed to the reactor system was provided by a positive displacement metering pump. This pump was initially sized for the lower end of the range of space velocity tested and subsequently boosted to a higher flow range by increasing both the gear ratio and the plunger diameter. Due to the high stoke frequency at high flow rate, there were excessive leakages through the pump packing hence affected the actual flow through the reactor substantially.

Each run had a total slurry feed duration of approximately 60 hours. However, there were five to six interruptions during each run. These interruptions were mostly due to high pressure build-up as a result of solid deposition in the reactor or transfer lines. In most cases the interruption were immediately preceded by a reduction in feedrate, or loss in slurry feed, due to excessive leakage at feed or low pressure circulating systems.

FIGURE 1

Run Summary

Run summary for ACL-01 and ACL-02 are presented in *Tables 4 and 5*, respectively.

In Run ACL-01, Shell S-317 1/20" trilobe catalyst was tested. This catalyst was obtained from Wilsonville in a presulfided form. Three test conditions were evaluated in 5 mass balance periods with run durations varying from 6.3 to 20.5 hours. The longest run duration was achieved in Period 5 when the reactor configuration consisted of one reactor connected in downflow mode. Periods 1 to 4 were in upflow mode with two reactors connected in series. The average reactor temperatures (sandbath mid-point temperature) ranged from 402-422 °F in Periods 1 to 4 and at 369 °C in Period 5. The space velocity was in the range of 2100 to 5050 Kg/h/M².

To simplify the operation only one reactor was used in Run ACL-02. Four test conditions were tested. Periods 1 to 4 were in downflow mode while Period 5 was in upflow mode. The space velocities investigated in this test were higher than those in ACL-01 ranging from 4900 to 8900 Kg/h/M². However, the temperature was around 370 °F for majority of the Periods.

Feed Slurry

The feed slurry used in these tests was partially converted coal slurry (L-772) from PDU Run 260-03. The properties of L-772 are listed in *Table 1*. It contains 12.06 and 3.35 W% of unconverted coal and ash (SO₃-free basis).

Results and Discussion

With the exception of ACL-02 Periods 1 and 2, most mass balances were low varying from 82.0 to 92.9 W%, *Tables 4 and 5*. It is mainly due to the small scale of the operations as well as the relatively short duration of each Period.

The ash balance was low for ACL-01 Periods 1 to 3 with ash recovery of only 18.3 to 31.7 W%. These Periods were in upflow mode with a relatively low space velocity ranging from 2090 to 2500 Kg/h/M². At space velocities of greater than 4410 Kg/h/M², as in ACL-01 Period 5, ACL-02 Periods 2 and 3, the ash recovery were much higher and closer to complete recovery (100%). In ACL-01 Period 4 the initial product was contaminated by product from the start-up conditions in which a solid-free gas oil feed was used. As a result the ash recovery (35.4 W%) in ACL-01 Period 4 was not in the expected range of high recovery.

Normalized product distribution for selected mass balance periods are presented in Table 6. The normalization procedure used in this calculation assumed that the low mass balance was mainly due to the over estimation of the amount of feed slurry fed to the system. This is a reasonable assumption in view of the leakage or unaccountable loss at both the circulation and feed pumps.

Coal conversion of the feed slurry (L-772) was 74.6 W% in reference to the coal fed to the PDU. Due to the relatively low reactor temperature in all Periods the incremental conversion was minimum, less than 5 W%.

Conclusion

Based on the results of the first two fixed bed tests, it appears that the downflow mode of operation is more preferable in terms of minimizing solid settling in the bed. Also, a space velocity of greater than 5,000 kg/h/m² is needed to sustain continuous operation. Due to the presence of solid matter in the feed, the fixed bed operation will be limited to a narrow range of operation parameters, e.g. a small turn-down ratio.

Recommendation

Although the operation of the first two fixed bed tests was intermittent with relatively short on-stream time (less than 20 hours for each condition), an additional test with a bituminous coal feed slurry is recommended. The proposed conditions are:

-	Feed Slurry:	CAS Bottom from run CC-16 or Run CC-9
-	Preheater Outlet Temperature:	380°C
-	Reactor Temperature:	400°C
-	No. of Reactors:	2
-	Operation Mode:	Downflow

The reactivity of the feed slurry should be characterized using a 20 ml microautoclave system and a 300 ml Robinson-Mahoney unit prior to the proposed fixed bed test.

TABLE 4

Fixed Bed Operation: Run 254-01
Shell S-317 1/20" Trilobe Catalyst (HRI-6030)

Run Summary

Condition	1	1	1	2	3
Period	1	2	3	4	5
No. of Reactor	2	2	2	2	1
Mode of Operation	Upflow	Upflow	Upflow	Upflow	Downflow
Duration, hours	9.4	6.3	12.8	11.5	20.5
Reactor Temperature (°C)*	402	417	416	404	369
Space Velocity Kg/h/M²	2090	2650	2500	5040	4410
DMDS, W% Feed	2.8	2.8	2.8	2.8	2.8
Mass Recovery, W%	56.0	83.5	82.0	92.9	90.8
Ash Recovery, W%		18.3	31.7	35.4	93.8

* Mid-point temperature of the fluidized sandbath heater.

TABLE 5

Fixed Bed Operation: Run 254-02
Shell S-317 1/16" Extrudate Catalyst (HRI-5903)

Run Summary

Condition	1	1	2	3	4
Period	1	2	3	4	5
No. of Reactor	1	1	1	1	1
Mode of Operation	Downflow	Downflow	Downflow	Downflow	Upflow
Duration, hours	9	21	11	4	9.4
Reactor Temperature (°C)*	372	371	396	372	407
Space Velocity Kg/h/M²	5170	4890	5630	8870	8510
DMDS, W% Feed	2.8	2.8	2.8	5.0**	2.8
Mass Recovery, W%	95.5	110.0	92.4	88.0	88.8
Ash Recovery, W%		107.7	104.3		180

* Mid-point temperature of the fluidized sandbath heater.

TABLE 6

Fixed Bed Operations (Run ACL-01 & 2)

Normalized Product Distribution (Basis: 100 part of L-772)

Run No. Period No. ⁺	1 2B	1 3B	1 4 ⁺⁺	1 5B	2 2B	2 3B	L-772 Slurry
Gases							
C ₁ -C ₃	1.77	2.03	1.00	0.38	0.49	0.38	
C ₄ -C ₇	1.55	1.78	1.04	0.00	0.00	0.41	
H ₂ S	1.12	1.28	1.72	1.19	1.16	3.46	
Others	0.00	0.00	0.03	0.00	0.04	0.08	
Total	4.44	5.09	3.79	1.56	1.70	4.32	
Filtrate (PFL)							
IBP-650°F	24.24	31.12	24.07	14.03	16.37	19.34	15.26
650-850°F	48.69	41.62	46.00	44.24	42.67	40.70	46.55
850-975°F	19.00	9.54	13.41	7.10	5.83	7.67	6.61
975°F ⁺	1.05	7.10	4.60	6.31	6.35	5.40	6.31
Total	92.98	89.37	88.08	73.15	72.21	73.10	74.73
Filter Cake (PFS)							
Quinoline Solubles	2.11	3.11	4.58	11.91	13.13	10.36	9.86
Quinoline Insolubles*	2.07	3.29	4.67	10.92	12.52	11.56	12.06
Ash (SO ₃ -free)	0.61	1.06	1.19	3.14	3.61	3.49	3.35
Total	4.79	7.45	10.44	25.97	29.26	25.42	25.27
Total Product**	102.2	101.9	102.3	100.7	102.2	102.8	100.0
Coal Conversion							
W% maf Coal ***	76.0	78.2	72.3	75.4	75.4	76.6	74.6
Incremental Conv.							
W% change over L-772	1.9	4.8	-3.1	1.1	1.1	2.7	0.0

⁺ Each period was divided into two 12-hour sub-periods A and B.

⁺⁺ Averaged result using data from sub-periods A and B.

^{*} Quinoline insolubles do not include ash.

^{**} Total Product = 100 part of L-772 + 2.88 parts of DMDS + amount of H₂ consumed.

^{***} In reference to the coal feed to the PDU Run 260-03.

TASK 4 - TECHNICAL ASSESSMENT

No activity undertaken during this reporting period.

TASK 5 - PROJECT MANAGEMENT

A paper was prepared for the Ninth Annual International Pittsburgh Coal Conference to be held at Pittsburgh on October 13 - 16, 1992.

An updated work schedule is attached, *Figure 2*.

FIGURE 2

END

DATE
FILMED

4 / 28 / 93

100