NOTICE

**CERTAIN DATA
CONTAINED IN THIS
DOCUMENT MAY BE
DIFFICULT TO READ
IN MICROFICHE
PRODUCTS.**

Savage Island Project Borehole Completion Report

**M. A. Chamness
T. J. Gilmore
S. S. Teel**

February 1993

**Prepared for
the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830**

**Pacific Northwest Laboratory
Richland, Washington 99352**

MASTER

ds
DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

Summary

Three wells were drilled in 1990 and 1991 in support of Pacific Northwest Laboratory's Ground-Water Surveillance Project. These wells were intended to monitor the Rattlesnake Ridge Interbed aquifer and the deeper portion of the unconfined aquifer to determine whether ground-water contamination emanating from the Hanford Site was migrating offsite through these aquifers. This report discusses well construction, lithologies encountered, and other data collected during drilling. At least three reports have been or are being prepared to discuss the results of this well monitoring project.

Contents

Summary	iii
Conversion Table	ix
Introduction	1
Scope	1
Methodology	3
Discussion	7
Well 699-42-E9A	7
Drilling Operations	7
Sediment Sampling	7
Microbiology Samples	9
Basalt Samples	9
Ground-Water Sampling During Drilling	9
Completion	9
Development/Aquifer Tests	10
Well 699-42-E9B	11
Drilling Operations	11
Sample Collection	11
Completion	14
Development/Aquifer Tests	14

Well 699-32-22B	15
Drilling Operations	15
Sample Collection	15
Completion	17
Development/Aquifer Tests	18
References	21
Appendix A - Geologic and Geophysical Logs	A.1
Appendix B - Design Field Changes and Nonconformance Reports	B.1

Figures

1	Savage Island Well Location Map	2
2	Key to Computer-Drawn As-Built Diagrams	4
3	As-Built Diagram for Well 699-42-E9A	8
4	As-Built Diagram for Well 699-42-E9B	12
5	As-Built Diagram for Well 699-32-22B	16

Tables

1	List of Geophysical Logs Run for Each Well	5
2	Summary of Well Construction Information	6
3	Ground-Water Analytical Results for Well 699-42-E9A	10
4	Ground-Water Analytical Results for Well 699-42-E9B	13
5	Ground-Water Analytical Results for Well 699-32-22B	17

Conversion Table

English units are used as the primary convention in the text, figures, and tables. The following conversion table may be used to convert English units to associated metric values.

<u>Multiply</u>	<u>By</u>	<u>To Obtain</u>
inches	2.540	centimeters
feet	0.3048	meters
miles	1.6093	kilometers
gallons	3.7854	liters
gallons/min	0.0631	liters/sec
cubic feet	0.0293	cubic meters

Introduction

In 1990 and 1991 three wells, 699-42-E9A, 699-42-E9B, and 699-32-22B, were constructed on and adjacent to the Hanford Site for the Pacific Northwest Laboratory's (PNL's) Ground-Water Surveillance Project (Figure 1). The construction of these wells was in support of the U.S. Department of Energy (DOE) Quality, Safety and Health Programs Division mission. Environmental surveillance is conducted by PNL to monitor the effects, if any, of DOE activities to onsite and offsite environmental and natural resources (DOE Order 5400.1). The primary objective in constructing these wells is to determine if chemical and radiological constituents resulting from operations at the Hanford Site are migrating offsite in the Rattlesnake Ridge interbed, an upper confined aquifer. A secondary objective is to determine the vertical gradient across the basalt unit confining the Rattlesnake Ridge interbed.

The uppermost confined aquifer is contained in the Rattlesnake Ridge interbed between two members of the Columbia River Basalt Group, the Elephant Mountain and Pomona Members. Two of the three wells, 699-42-E9B and 699-32-22B, were completed in the Rattlesnake Ridge interbed while the third well, 699-42-E9A, was completed in the sediments immediately above the basalt. Wells 699-42-E9A and 699-42-E9B are located approximately 100 ft apart, on the east side of the Columbia River near Savage Island and directly across the river from the highest reported concentration of tritium in the unconfined aquifer. Well 699-32-22B is located on the Hanford Site approximately 5 miles east of the 200 East Area. The location of this well is downgradient of reported contamination in the Rattlesnake Ridge hydrogeologic unit at wells 699-42-40C and 699-47-42 (Early et al. 1986; Jaquish and Bryce 1989). Well 699-32-22B is located approximately 50 ft south of well 699-32-22A, which monitors the uppermost unconfined aquifer discharging to the Columbia River. This location was chosen to take advantage of well 699-32-22A for analytical and water level comparisons between the two aquifers.

Scope

This report provides a summary of the drilling, well completion, well development, geology, geophysical logs, and analytical results of chemical and radiological analyses of ground-water samples collected during drilling. A companion report discusses the hydrologic testing of these wells and their results (Spane 1992).

S9205085.26

Figure 1. Savage Island Well Location Map

Methodology

PNL supervised the drilling and installation of the wells and Kaiser Engineers Hanford (KEH) provided contract management of the drilling subcontractors. Under contract to KEH, Basin and Range Drilling Company of Spanish Fork, Utah, drilled and constructed well 699-42-E9A, and Jensen Brothers Drilling Company of Eugene, Oregon, drilled and constructed wells 699-32-22B and 699-42-E9B.

Geologic samples were collected and described in accordance with PNL procedures (PNL 1989). Geologic samples were collected from each well at 5-ft intervals or at major changes in lithology, and described on geologists' logs along with daily activities at the well site. These logs, the field as-built diagrams, and well-completion summaries are presented in Appendix A for each of the wells. Figure 2 provides a key to the computer-drawn as-built diagrams included with the discussion of each well. In addition to a field description of the lithology, two pint jars were collected at each sample depth for archival in the sample library at the 2101-M building in the 200 East Area of the Hanford Site. Geophysical logs were run on each of the wells to help identify geologic units, diameter of the borehole, and zones of water inflow. Table 1 lists the types of logs and the interval logged for each of the wells. The gross gamma and caliper logs are provided in Appendix A with their respective geologic logs. Table 2 provides a summary of well construction information for each of the wells, including 699-32-22A. Design Field Changes and Nonconformance Reports are provided in Appendix B.

Lithology Classification Pattern Key

	M	Mud		G	Gravel		GS	Gravelly Sand
	SM	Sandy Mud		SG	Sandy Gravel		(G)S	Slightly Gravelly Sand
	GM	Gravelly Mud		MG	Muddy Gravel		GMS	Gravelly Muddy Sand
	(G)M	Slightly Gravelly Mud		MSG	Muddy Sandy Gravel		(G)MS	Slightly Gravelly Muddy Sand
	GSM	Gravelly Sandy Mud		S	Sand		(M)GS	Slightly Muddy Gravelly Sand
	(G)SM	Slightly Gravelly Sandy Mud		MS	Muddy Sand		(GM)S	Slightly Gravelly Muddy Sand
	MISSING	Data Unknown		(M)S	Slightly Muddy Sand		B	Basalt
							CA	Caliche

Ternary Diagram for Sediment Code Names

* Sampling Method Column

	R	Rotary		H	Hard Tool
	AR	Air Rotary		D	Drive Barrel
	MR	Mud Rotary		S	Split Spoon
	B	Back Hoe		A	Auger
	AP	Air Percussion		X	Other Method

Mud/Sand/Gravel Column

Well Construction Pattern Key

	CG	Cement Grout		BP	Bentonite Pellets		Perforated Permanent Casing
	GB	Granular Bentonite		CE	Chemical Grout		Pump Location
	GP	Gravel Pack		SP	Sand Pack		Most Recent Water Level
	BF	Backfill		CO	Concrete		Initial Water Level
	BE	Bentonite Slurry		VG	Vulcay Grout		
		Other Fill Type			Screen		

Figure 2. Key to Computer-Drawn As-Built Diagrams

Table 1. List of Geophysical Logs Run for Each Well

<u>Well Number</u>	<u>Date</u>	<u>Probe Type</u>	<u>Interval Logged (ft)</u>
699-42-E9A	12/4/90	GROSS GAMMA	0.5 - 138.3
"	12/13/90	GROSS GAMMA	1.0 - 230.6
"	12/14/90	TEMPERATURE	0.0 - 230.0
"	12/14/90	CALIPER	90.0 - 228.0
"	12/14/90	GROSS GAMMA	130.0 - 230.3
699-42-E9B	2/28/91	CALIPER	4.9 - 227.3
"	2/28/91	SP&R	0.0 - 227.0
"	2/28/91	GROSS GAMMA	0.0 - 227.0
"	2/28/91	SONIC BOND	30.0 - 222.0
"	2/28/91	TEMPERATURE	0.0 - 227.0
"	3/4/91	GROSS GAMMA	1.4 - 228.6
"	3/7/91	SONIC BOND	2.6 - 195.0
"	3/18/91	GROSS GAMMA	200.0 - 284.8
"	3/18/91	CALIPER	220.0 - 284.8
"	3/18/91	MAGNETIC	220.0 - 284.0
"	3/18/91	SP&R	220.0 - 284.1
"	3/25/91	CALIPER	0.0 - 353.0
"	3/25/91	SP&R	0.0 - 352.3
"	3/25/91	GROSS GAMMA	209.8 - 353.7
"	3/27/91	GROSS GAMMA	320.0 - 388.0
"	3/27/91	CALIPER	220.0 - 387.0
"	3/27/91	SP&R	225.0 - 387.4
"	3/27/91	MAGNETIC	215.0 - 387.1
699-33-22B	5/20/91	CALIPER	4.4 - 648.0
"	5/20/91	GROSS GAMMA	2.6 - 656.0
"	6/18/91	GROSS GAMMA	620.0 - 838.5
"	6/18/91	CALIPER	620.0 - 837.0
"	6/18/91	TEMPERATURE	500.0 - 837.0
"	10/18/91	GROSS GAMMA	2.6 - 831.0
"	10/18/91	CALIPER	4.1 - 829.0

Table 2. Summary of Well Construction Information

Well Number	Hanford Coordinates	Casing Elevation (ft)	Drilled Depth (ft)	Completed Depth (ft)	Initial Depth to Water	Well Diameter	Screened Interval	Comments
699-42-E9AO	N41,970 E8,350	387.13	233	41.55	28.01	2	21.13-41.55	
699-42-E9AP	N41,970 E8,350	387.13	233	0	26.67	3		Abandoned.
699-42-E9B	N41,775 E8,452	386.42	390	384	22	6	354-384	
699-32-22A	N32,003 W21,995	517.55	171	168	115	6	111-169	
699-32-22B	N31,935 W21,982	516.93	841.5	836	110	6	774.6-836	

Discussion

Well 699-42-E9A

Drilling Operations

Well 699-42-E9A was drilled using a Bucyrus Erie 22-W cable tool drilling rig using the drive barrel, split-spoon, and hard-tool methods. Drilling operations began on November 12, 1990, and continued until December 12, 1990. The well was drilled to a final depth of 233 ft below land surface (bls) at the top of the Elephant Mountain Member basalt. Temporary carbon steel 12-in. diameter casing was placed from the surface to a depth of 15.5 ft. Temporary 10-in. casing was placed from the surface to 139.7 ft, and temporary 8-in. casing was placed from the surface to 194.91 ft.

Sediment Sampling

Lithologic sediment samples were collected at 5-ft intervals in two pint jars from the surface to the final depth of the well. In addition, split-spoon sediment samples were collected over approximately 2-ft intervals in a few locations. The locations of the split-spoon samples are identified in the sampling method column in Figure 3. Split-spoon samples collected from this borehole were used for a variety of analyses and measurements including microbiology, hydraulic conductivity, sieve size, and background sediment chemistry.

Vertical Hydraulic Conductivity Measurements

Laboratory vertical hydraulic conductivity was determined for two split-spoon samples collected at 43.3 ft and from 149.5 to 151.2 ft. The upper sample was a sandy gravel, packed into the test cylinder at a density of 1.78 g/cm^3 and had an average hydraulic conductivity of 4.6 E-3 cm/sec . The lower sample was a sandy mud with 20% very fine sand that was tested within the sample collection tube and had an average hydraulic conductivity of 1.0 E-6 cm/sec .

Background Sediment Samples

To help determine background levels of various constituents in soil at the Hanford Site, soil samples were collected by Westinghouse Hanford Company personnel in the unsaturated zone. The results from these and other samples are provided in DOE (1992).

WELL NAME	699-42-E9A	COMPLETION DATE	12/12/90
CASING ELEV.	387.13 Feet	INITIAL	
WELL DEPTH	PIEZOMETERS	DEPTH TO WATER	27.10 ft
DRILL DEPTH	233.00 Feet		
COORDINATES	N-S 41970 P		
	E-W -8350 P		
			PAGE 1 of 1

Figure 3. As-Built Diagram for Well 699-42-E9A

Microbiology Samples

Microbiologic sampling of two split-spoon samples was performed within the Ringold Formation. These sample locations are identified on Figure 3 by the "MB" in the sample method column. Special sampling procedures were followed to assure aseptic sampling conditions to reduce the risk of contaminating the samples with microbes. The results of these samples have not yet been documented.

Basalt Samples

Basalt samples were sent to Dr. Peter Hooper of Washington State University for X-ray fluorescence analysis and determination of basalt flow stratigraphy. All of the samples were identified as basalt from the Elephant Mountain Member.

Ground-Water Sampling During Drilling

During drilling, ground-water samples were collected for nitrate and tritium to determine whether contamination existed in the unconfined zone, and if so, to define the specific contaminated hydrogeologic unit(s). The results were also to be used to help determine the completion interval(s). These sample depths and results are presented in Table 3. No significant zones of elevated concentrations of either tritium or nitrate were identified. Because no contamination was observed, the secondary objective of determining the vertical gradient through the basalt unit was used in choosing the two completion intervals.

Completion

The well was initially completed at two intervals, one at the bottom of the borehole located just above the basalt surface (699-42-E9AP) and the other at the top of the unconfined water table (699-42-E9AO). For more detailed completion information, an as-built diagram of the well is shown in Figure 3, and the geologists' logs are provided in Appendix A. The deeper completion was constructed of 3-in. dia fiber glass casing and screen with a 0.08-in. wall thickness and a screened interval from 220.25 and 231.25 ft bls. The shallow completion was constructed of 2-in. dia PVC casing with a 20-slot screen set from 21.1 to 41.5 ft bls. The annular seals outside the two permanent casings are shown in Figure 3 and are specifically listed on the well completion summary in Appendix A. Each of the screened intervals was surrounded by sand pack and sealed off from the other by bentonite slurry and pellets. The annular seal meets the Washington State codes for monitoring wells (WAC 173-160). Protective casing and guardposts were installed at the surface, along with a locking well cap. A brass marker was installed in the concreted pad and was stamped with the well number, which was also stenciled on the protective casing.

Table 3. Ground-Water Analytical Results for Well 699-42-E9A

Date	Drill Depth (ft)	Open Interval (ft)	Nitrate (ppm) (a)	Tritium (pCi/L) (b)
11/15/90	44	43.5 - 44.0	1	<500
11/26/90	50	43.5 - 50.0	1.26	<500
11/27/90	85	43.5 - 85.0	1.26	<500
12/3/90	115	94.3 -115.0	1	<500
12/4/90	145	138.0 -145.0	0.4	<500
12/5/90	180	None	1.64	<500
12/10/90	205	195.0 - 205.0	0.4	<500
12/11/90	230	195.0 - 230.0	6	<500
12/13/90	239	195.0 - 239.0	6.4	<500

(a) Nitrate detection level is 0.2 ppm.

(b) Tritium detection level is 437 pCi/l.

Well development and a pumping test were attempted in the deeper completion. The water level rapidly drew down to the level of the pump intake and the pump stopped. Although the water level came back up after the pump stopped, the pump would not work. When efforts were made to pull the pump out of the well, it was found that the fiber glass casing had collapsed inward. There were at least two tight spots in the casing at 157 and 176 ft, and one hole in the casing was verified by a downhole camera at 157 ft. The pump used during the well development/pumping test could not be removed from the well because of the collapsed casing at 157 ft.

The manufacturer's specifications for the casing strength and size were rated to be compatible with this application. A Nonconformance Report (PNL-91-002) details the occurrence of the casing failure (Appendix B). The deeper completion (699-42-E9AP) was abandoned by pushing the pump down the well to 220 ft bls and the 3-in. casing was filled with volclay grout. The well was completed on January 10, 1991. The shallow completion (699-42-E9AO) remains as a functioning monitoring well at this site.

Development/Aquifer Tests

Following completion of the well, the shallow completion was developed by overpumping on January 23, 24, and February 5, 6, and 7. A Hydrostar pump was used for the well development. The discharge rate ranged from 5 to 7 gpm. The initial turbidity readings were off the scale of the turbidimeter at 100 NTU. A final turbidity reading of 14 NTU was reached following approximately 40 hours of pumping. The inability to clean the water to a lower NTU level resulted from the fine-grained nature of the sediment matrix over the screened interval.

Two aquifer tests were scheduled for the borehole: a slug test near the interval to be screened and a pumping test in the screened interval of the deeper completion. The slug test was performed in the open borehole over the 195- to 232-ft interval. The results are discussed in Spane (1992). The pumping test was not completed due to failure of the pump and collapse of the deeper completion's casing.

Well 699-42-E9B

Drilling Operations

Drilling of well 699-42-E9B began on February 14, 1991, and was completed on April 10, 1991. The well was drilled by Jensen Brothers using a Speedstar SS-15 III rotary drilling rig with both mud and air rotary and an air percussion hammer. Air rotary drilling and sampling was conducted from 0 to 40 ft and from 354 to 390 ft. Mud rotary drilling and sampling was conducted from 40 to 230 ft. The air percussion hammer was used to drill through the basalt, from 230 to 354 ft. The well was drilled through the Elephant Mountain Member into the top of the Pomona Member of the Columbia River Basalt Group at a depth of 390 ft. The well monitors the water-bearing zone between the two basalt flows. Ground water was initially encountered at 28 ft. Final depth to water was 22 ft. Aquifer tests were performed on the zone between the two Elephant Mountain flows (the interflow zone) between March 18 and 19, 1991, and on the completion interval (i.e., the Rattlesnake Ridge interbed/interflow zone) on April 18, 1991. The specific details and results of these tests are discussed in Spane (1992).

Sample Collection

Geologic samples were collected every 5 ft or at major changes in lithology. Sediment samples were collected from the air rotary and the air percussion discharge line with a sieve. Consequently, some of the finer-grained materials were probably lost by being washed through the sieve. A similar problem occurred with the mud rotary samples. During mud rotary drilling, the sediments were collected from the end of the shaker table, a large screen that the drilling mud flows across and through while the larger sediment particles fall off the far end. Most mud rotary samples had to be washed to remove excess drilling mud before the sediments could be viewed; this also removed some of the finer-grained sediment particles. On a few occasions, no sample was collected because of poor mud returns or because the sample was pulverized into such small particles that they washed through the sieve or shaker table. Samples are described in the geologists' logs in Appendix A, and are summarized in Figure 4.

Ground-water samples were collected as time series during the two aquifer tests performed on March 19 and April 18, 1991. Altogether, nine samples were analyzed for ICP metals, tritium, bicarbonate, carbon dioxide, and anions from the March test; the same constituents were analyzed for six samples collected in April (Table 4). The last sample from each aquifer test was also analyzed for iodine-129. Iodine concentrations are somewhat elevated compared

WELL NAME	699-42-E9B	COMPLETION DATE	04/10/91
CASING ELEV.	386.42 Feet	INITIAL	
WELL DEPTH	384.00 Feet	DEPTH TO WATER	22 ft
DRILL DEPTH	390.00 Feet		
COORDINATES	N-S 136265.4 LAMBERT NAD83		
	E-W 592466.7 LAMBERT NAD83		
		PAGE	1 of 1

Figure 4. As-Built Diagram for Well 699-42-E9B

Table 4. Ground-Water Analytical Results for Well 699-42-E9B^(a)

Time »	20:09	21:00	22:15	23:23	0:56	2:30	5:00	9:00	11:30	Detection
Date »	3/18/91	3/18/91	3/18/91	3/18/91	3/19/91	3/19/91	3/19/91	3/19/91	3/19/91	Limit
Nitrate (ppm)	<0.2	<0.2	<0.2	<0.2	<0.2	0.95	0.81	1.33	<0.2	0.2
Carbon Dioxide (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.01
Bicarbonate (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.03
Boron (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.01
Calcium (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.002
Chromium (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.01
Copper (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.002
Iron (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.01
Sodium (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.2
Magnesium (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.08
Manganese (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.005
Nickel (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.02
Potassium (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	1.5
Barium (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.001
Silver (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.01
Cadmium (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.005
Cobalt (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.02
Molybdenum (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.02
Lead (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.05
Zinc (mg/L)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.02
Fluoride (ppm)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.2
Chloride (ppm)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.2
Phosphate (ppm)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.2
Sulfate (ppm)	NA	NA	NA	NA	NA	NA	NA	NA	NA	0.2
Iodine (E-6 pCi/L)	NA	NA	NA	NA	NA	NA	NA	NA	309.071 (b)	
Tritium (pCi/L)	NA	NA	NA	NA	NA	NA	NA	NA	<500	500
Volatile Organics	All volatile organics were below detection limits.									

Time »	13:20	15:05	17:00	19:00	21:00	23:30	Detection
Date »	4/18/91	4/18/91	4/18/91	4/18/91	4/18/91	4/18/91	Limit
Nitrate (ppm)	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	0.2
Carbon Dioxide (mg/L)	10.5	6	4.8	7.3	5.3	8.8	0.01
Bicarbonate (mg/L)	143	147	150	145	150	142	0.03
Boron (mg/L)	0.05	0.12	0.12	0.05	0.1	0.09	0.01
Calcium (mg/L)	5.82	6.04	5.82	5.92	5.87	5.84	0.002
Chromium (mg/L)	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	0.01
Copper (mg/L)	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	0.002
Iron (mg/L)	0.04	0.03	0.03	0.04	0.04	0.19	0.01
Sodium (mg/L)	77.4	80.4	78.8	81.3	80.1	78.5	0.2
Magnesium (mg/L)	1.3	1.37	1.39	1.42	1.4	1.39	0.08
Manganese (mg/L)	0.009	0.008	0.007	0.007	0.008	0.007	0.005
Nickel (mg/L)	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	0.02
Potassium (mg/L)	10	10.4	9	8.7	10.7	9.3	1.5
Barium (mg/L)	0.014	0.014	0.014	0.012	0.014	0.014	0.001
Silver (mg/L)	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	0.01
Cadmium (mg/L)	<0.05	<0.005	<0.005	<0.005	<0.005	<0.005	0.005
Cobalt (mg/L)	<0.02	<0.02	<0.02	<0.02	<0.02	<0.02	0.02
Molybdenum (mg/L)	0.04	0.05	0.05	0.05	0.05	0.05	0.02
Lead (mg/L)	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	0.05
Zinc (mg/L)	0.08	<0.02	0.02	<0.02	<0.02	0.02	0.02
Fluoride (ppm)	1.5	1.56	1.57	1.55	1.54	1.55	0.2
Chloride (ppm)	20.6	20	19.8	19.8	19.2	19.2	0.2
Phosphate (ppm)	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	0.2
Sulfate (ppm)	44	43.7	43.6	43.7	43.6	43.7	0.2
Iodine (E-6 pCi/L)	NA	NA	NA	NA	NA	522.736	
Tritium (pCi/L)	NA	NA	NA	NA	NA	<500	500
Volatile Organics	All volatile organics were below detection limits.						

(a) Samples were collected over time during pumping tests.

(b) Duplicate sample result: 317.519.

to offsite confined aquifers. The source of the elevated concentrations is unclear and resampling is scheduled.

Completion

Figure 4 shows the as-built diagram for well 699-42-E9B, including construction information and geology. Copies of the well completion summary, field as-built diagrams, and geologists' logs are included in Appendix A. A summary of the well completion efforts is described here.

Temporary 16-in. carbon steel casing was placed to a depth of 39.6 ft. Permanent 10-in. carbon steel casing was placed to a depth of 231.45 ft and sealed in place with cement grout. This method involved attaching a float shoe to the bottom of the casing. Cement grout was pumped through this shoe and up the annulus to the surface, permanently cementing the casing in place and sealing off the unconfined aquifer. The unconfined aquifer had to be isolated before drilling any deeper to prevent communication between aquifers. The open borehole penetrating the basalt below the 10-in. casing was filled with cement grout twice and redrilled with a smaller bit to provide an additional seal against aquifer intercommunication. These cemented zones were from 205.6 to 285 ft, and 262 to 354 ft. Permanent 6-in. carbon steel casing was set at a depth of 354 ft. A telescoping stainless steel 10-slot screen with a 5-ft stainless steel blank with a packer on top and nominal diameter of 6 in. was placed from 354 to 384 ft.

The screened interval was surrounded by a sand pack. The remainder of the borehole was sealed with bentonite slurry and cement grout (see Figure 4 and Appendix A). To protect the well, a concrete pad 0.5 ft above ground to ground surface, an 8-in. protective casing, and four guardposts were installed. A brass marker was stamped with the well number, which was also stenciled on the casing.

Deviation surveys were run at approximately 110, 200, and 325 ft, and all were within the requirements of being no more than 1 degree/50 ft off of the vertical. The last deviation survey showed a deviation of 1.9 degrees over 325 ft. The well was considered completed and accepted on April 10, 1991.

Development/Aquifer Tests

After the screen and annular seal fill were installed, the well was developed using a 1 1/2-hp submersible pump with a check valve set at 80-ft depth pumping at approximately 30 gpm. The well was developed continuously for 3 hours in this configuration, and then periodically with the pump being turned off and on over 1 1/2 hours to surge the well. The water was discharged to the ground approximately 1000 ft to the south. The pump was then set at a depth of 350 ft, with a flow rate of from 43 to 45 gpm and pumped for a little over an hour, pumping a total of 2025 gal. Turbidity was measured during the development and went from a

high of over 15 NTU to 0.8 NTU. The development pump was pulled out, and the 3/4-hp submersible sampling pump was installed on February 19, 1992, with the inlet at 340 ft.

Well 699-32-22B

Drilling Operations

Well 699-32-22B was drilled using a Speedstar SS-15 III rotary drilling rig. The air rotary drilling method was used from depths of 0 to 101 ft and from 655.7 to 841.5 ft. The mud rotary drilling method was used from 101 to 655.7 ft. Drilling began on April 11, 1991, and continued until June 17, 1991, when a total depth of 841.5 ft was reached.

During drilling, a 16-in. carbon steel casing was used to a depth of 87.9 ft. No casing is needed when drilling with mud rotary because the mud is sufficiently dense to keep the borehole open. The borehole was advanced to a depth of 655.7 ft within the hard, dense portion of the Elephant Mountain Member. At this point, an unsuccessful attempt was made to remove the 16-in. carbon steel casing. A casing cutter was then used to cut the casing at 22.2 ft bls, and the upper portion of the casing was removed after installation of the 10-in. casing to ensure that a proper cement grout seal could later be installed. Permanent 10-in. carbon steel casing was installed from the surface to 655.4 ft and a float shoe was attached to the bottom of the casing. Cement grout was pumped through this shoe and up the annulus to the surface, permanently cementing the casing in place and sealing off the unconfined aquifer. The unconfined aquifer had to be isolated before drilling any deeper to prevent communication between aquifers. The zone penetrating the basalt and below the 10-in. casing was filled with cement grout and redrilled with a smaller bit to provide an additional seal against aquifer intercommunication.

Sample Collection

Sediment samples were collected from the air rotary discharge hose with a sieve. Consequently, some of the finer-grained materials were probably lost by being washed through the sieve. A similar problem occurred when sampling during mud rotary drilling. The finer-grained particles were lost through the shale shaker or when washed to remove drilling mud. Occasionally, no samples could be collected because of loss of air or mud circulation. Adding lost circulation material to the borehole during mud rotary drilling to prevent loss of mud to the formation also prevented sample collection. Lost circulation material that was used included cedar chips, cellophane, or paper. Samples are described on the geologists' logs (Appendix A) and included in Figure 5.

Time-series ground-water samples were collected during pump testing of the Elephant Mountain interflow zone at 686 ft bls. They were analyzed for nitrate and tritium. All results

WELL NAME	699-32-22B	COMPLETION DATE	08/06/91
CASING ELEV.	516.93 Feet	INITIAL	
WELL DEPTH	836.00 Feet	DEPTH TO WATER	110 ft
DRILL DEPTH	841.50 Feet		
COORDINATES	N-S 133240.3 LAMBERT NAD83		
	E-W 583200 LAMBERT NAD83	PAGE	1 of 1

NOTE: ANNULAR SEAL
IS SHOWN AS INITIALLY
INSTALLED. PRESENT
CONTACT BETWEEN SAND
PACK AND BENTONITE
SLURRY IS UNCERTAIN.

Figure 5. As-Built Diagram for Well 699-32-22B

Table 5. Ground-Water Analytical Results for Well 699-32-22B

Time » Date »	8:15 6/1/91	10:20 6/1/91	14:00 6/1/91	17:30 6/1/91	10:10 6/13/91	13:50 9/30/91	Detection Limit
Nitrate (ppm)	<0.2	<0.2	<0.2	<0.2	<0.2	NA	0.2
Flouride (ppm)	NA	NA	NA	NA	1.16	NA	0.2
Chloride (ppm)	NA	NA	NA	NA	23.9	NA	0.2
Phosphate (ppm)	NA	NA	NA	NA	<0.2	NA	0.2
Sulfate (ppm)	NA	NA	NA	NA	36.8	NA	0.2
Tritium (pCi/l)	<500	<500	<500	4110(a)	NA	<500	500
Iodine (E-6 pCi/L)	NA	NA	NA	138.504(b)	NA	NA	

(a) This result was due to an analytical problem. Well was resampled in September to confirm the result.

(b) Duplicate sample result: 143.868.

were below detection limits except for one tritium result (Table 5). The high amount of tritium is thought to be due to an analytical problem, since a resample on September 30, 1991, showed levels below detection limits. Iodine-129 was analyzed for in the last time-series sample. The levels detected are within the previously reported range for offsite confined aquifers; however, because of concern over concentrations observed at well 699-42-E9B, resampling has been scheduled. One sample was collected from within the lower Elephant Mountain flow at 712 ft bls where water appeared to be coming into the borehole from the contact between the entablature and colonnade. This sample was analyzed for anions but not for tritium. No samples were collected from the second pump test of the Rattlesnake Ridge interbed because the test was terminated early.

Completion

Figure 5 shows the as-built diagram for well 699-32-22B, including construction information and geology. A copy of the well completion summary, field as-built, and geologists' logs are included in Appendix A. A summary of the well completion efforts follows.

During the initial installation of the permanent 6-in. casing, a 699-ft-long section of casing and tremie pipe fell to the bottom of the hole. The cable that was suspending the casing in the well was attached to pairs of centralizers welded to the outside of the casing. The casing was dropped when one of the centralizers broke off. All of the casing was recovered, but 84 ft of tremie pipe could not be retrieved. The undamaged sections of casing were reused and the casing was reinstalled to a depth of 780.9 ft, where a tight spot in the borehole prevented deeper placement. A 5 7/8-in.-dia drill bit was used with air rotary to drill through this tight spot from 780.9 to 836 ft. During the redrilling, evidence of the lost tremie pipe was not seen until a depth of 836 ft was reached. The 6-in. permanent casing was installed down to the bottom of the basalt at a depth of 821 ft. A 5.5-in. (outside diameter) telescoping stainless steel 10-slot

screen was installed from 774.6 to 836 ft. A neoprene packer outside the top of the screen provided a seal against the inside of the permanent casing. The 6-in. casing was then backpulled to 778.7 ft to fully expose the screen.

Annular seal materials that were added included silica sand, bentonite slurry, cement grout, and bentonite crumbles (see Figure 5 and Appendix A). Annular seal materials (except granular bentonite) were placed in the well via a water slurry that was pumped down a tremie pipe located on the outside of the casing in the borehole annulus. A 5-hp submersible pump, set inside the carbon steel casing at a depth of 504 ft, pumped water from the well to facilitate settling of the sand pack and to mix with bentonite to make the bentonite slurry.

Silica sand was placed around the outside of the screen as a filter. The depth to the sand was difficult to measure during sand pack installation because of the depth and a possible restriction between the formation wall and the screen at approximately 806 ft. The sand pack was placed from 761 to 836 ft using a total of 11.80 ft³ of silica sand. Water was pumped from the well at a rate of 20-30 gpm during installation of the sand pack. A small portion of this water (approximately 2 gpm) was recirculated back down the annulus via the tremie pipe to facilitate sand movement down to the bottom of the borehole. Approximately 20,000 gal were pumped from the well during installation of the sand pack. Water that was not recirculated back to the well was discharged to the ground surface at approximately 1000 ft from the well. In addition, approximately 9000 gal were pumped after placement of the sand pack and before installing the bentonite slurry seal in order to "settle" the sand pack. Typically, the water appeared turbid for a few minutes after the pump was turned on and then cleared.

To protect the well, a concrete pad, 10-in. protective casing, and four guardposts were installed. A brass marker was stamped with the well number, which was also stenciled on the well casing.

Deviation surveys were run approximately every 100 ft, and all were within the requirements of being no more than 1 degree/50 ft off the vertical.

Development/Aquifer Tests

The well was initially developed during placement of the annular seal materials, with approximately 29,000 gal of water pumped from the well during installation of the sand pack and another 600 gal pumped during placement of the bentonite slurry.

To further develop the well and to test the hydraulic properties of the aquifer, a constant discharge test was attempted on September 30, 1991. During the first 4 min of pumping, the water was a light green color, which was thought to result from greenish clays within the Rattlesnake Ridge interbed. After the first 4 min, the water became a very turbid light brown. After 30 min of pumping, the well stopped producing water. The pumping rate was

approximately 31 gpm for this portion of the test. The pump was restarted after 30 min but discharge was significantly reduced (8.6 gpm) and the water remained a brown color. This test was terminated due to the decrease in ground-water production and the presence of what appeared to be bentonite in the water. A total of 2125 gal were pumped during the entire test.

Further investigation confirmed the presence of some bentonite in the water. Although the cause has not been conclusively determined, the bentonite is thought to be caused by a downward migration of the bentonite slurry into the screened interval. This migration may have occurred by additional settling of the sand pack due to a possible bridge (void area) in the sand pack giving way. Because no bentonite was seen when the well was being pumped during and immediately after installation of the annular seal materials, the bridge may have broken during the pumping test, allowing the sand pack to settle and the bentonite to move down into the screened interval.

When all of the ground-water analytical results are reviewed, a decision will be made on whether this well can be monitored as is or whether remediation is required.

References

DOE. 1992. *Hanford Site Soil Background*. DOE/RL-92-24, U.S. Department of Energy, Richland, Washington.

Early T. O., G. D. Spice, and M. D. Mitchell. 1986. *A Hydrochemical Data Base for the Hanford Site, Washington*. SD-BWI-DP-061, Rockwell Hanford Operations, Richland, Washington.

Jaquish, R. E., and R. W. Bryce, eds. 1989. *Hanford Site Environmental Report for Calendar Year, 1988*. PNL-6825, Pacific Northwest Laboratory, Richland, Washington.

PNL (Pacific Northwest Laboratory). 1989. *Procedures for Ground-Water Investigations*. PNL-6894, Pacific Northwest Laboratory, Richland, Washington.

Spane, F. A., Jr. 1992. *Hydraulic Test Results for Savage Island Wells: 699-32-22B, 699-42-E9A, and 699-42-E9B*. PNL-8173, Pacific Northwest Laboratory, Richland, Washington.

Washington Administrative Code (WAC). 1988. "Minimum Standards for Construction and Maintenance of Wells." WAC 173-160, Olympia, Washington.

Appendix A

Geologic and Geophysical Logs

WELL COMPLETION SUMMARY

Project <u>Swase Island</u>	Well No. <u>WA-42-E9A</u> Temp. Well No. _____
Location <u>N. of Ringold Fish Hatchery</u>	Coordinates <u>N41970 E8350</u>
Drilling Co. <u>Basin + Range</u>	Elevation: Casing <u>387.13</u> Brass Marker <u>384.54</u>
Driller <u>Robert Perry, Les Kunkle</u>	
Other (companies) _____	
Geologist(s) <u>T.J. Gilmore</u>	
<u>MA Chamness</u>	
<u>SS Teel</u>	

DRILLING METHOD

Drilling Method(s) cable tool

Drilling Fluid water from hatchery

Other DB 0-33' HT 33-233'

COMPLETION DATA

Drilled Depth 233'

Completed Depth "O" 41.55' "P" abandoned

Date Started 11/12/90

Date Completed 11/11/91

Static Water Level/Date 26.84' 11/26/90

OTHER (check if performed)

☒ Well Abandonment	☒ Downhole TV Inspection
☒ Well Development	☐ Driller's Logs
☒ Aquifer Testing	☒ Pad
☒ Geophysical Log(s)	☒ Guardposts
☒ Lock and Cap	☒ Protective Casing

SCREEN

Type	Outer Diameter	Length	Slot Size	Interval
"O" PVC	2"	20'	20	21.13 - 41.55
"P" Fiberglass (abandoned)	3"	20'	10	221.2 - 232.2

TEMPORARY CASING

Type	Nominal Diameter	Max. Outer Diameter	Interval
Carbon Steel	12"		+0.75 - 15.5
Carbon Steel	10"		+0.5 - 139.7
Carbon Steel	8"		+4.1 - 194.91

PERMANENT CASING

Type	Nominal Diameter	Max. Outer Diameter	Interval
"O" PVC	2"		+3.8 - 21.13
"P" Fiberglass (abandoned)	3"		+1.8 - 221.2

ANNULAR SEAL/FILL

Type	Interval	Quantity	Volume
Silica sand	212.8 - 233	9 50 lb bags	
bentonite pellets	210.5 - 212.8	1 5 gal bucket	
bentonite slurry	50 - 210.5	750 gal	
Silica sand - 10-20 mesh	46.3 - 50	3 bags	
bentonite pellets	44.6 - 46.3	2/3 bucket (5 gal)	
Silica sand 10-20 mesh	17.0 - 44.6	15 1/2 50 lb bags	

See back

PUMP

Type _____ Depth to Inlet _____ Date Set _____

ACCEPTANCE

Completed Well: Accept _____ Conditionally Accept _____

Reject _____

COMMENTS

* "O" B.W. = 28.01' 11/24/91 "P" B.W. = 26.67' 12/13/90

"P" well casing broke, & with a pump stuck in the well. The well was abandoned by pushing the pump down the hole & filling the casing with wet clay grout.

Seal fill continued

Type
bentonite pellets
cement grout
concrete pad

Interval
12.0 - 17.0
1.0 - 12.0
+0.3 - 1.0

Quantity Volume
5 1/2 5gal buckets

5-11-92

WELL INSPECTION REPORT

Well No. 44-42-E9A0 Procedure D0-5 Rev. 0 Specification No. B-8113-C2 Rev. 0
 Geologist(s) T. Gilmore, MA Charnness, SS Teel ECNs (list) _____

CLEANING/DECONTAMINATION		Inspection Method	Criteria	Accept	Reject	Date
Rig/Tools (initial)	Visual/Wipe (optional)		7.1	<u>MAC</u>	NA	11/12/90
Temporary Materials	Visual/Wipe (optional)		4.1	<u>MAC</u>	NA	12/18/90
Permanent Materials	Visual/Wipe (optional)		4.2.2	<u>MAC</u>	NA	1/9/91
Mtls Brought Onsite Later	Visual/Wipe (optional)				NA	
					NA	
MATERIAL STORAGE/PACKING		Inspection Method	Criteria	Accept	Reject	Date
Material Storage	Visual		7.5	<u>MAC</u>	NA	1/9/91
Material Packing/Seals	Visual		4.2, 7.5	<u>MAC</u>	NA	1/9/91
Other					NA	
LUBRICANTS/ADDITIVES/AIDS		Inspection Method	Criteria	Accept	Reject	Date
Lubricants	Visual		7.2	<u>MAC</u>	NA	11/12/90
Additives/Aids	Visual		7.4	<u>MAC</u>	NA	12/18/90
DRILLING METHOD		Inspection Method	Criteria	Accept	Reject	Date
Method	Visual		5.2	<u>MAC</u>	NA	12/18/90
Drilling Fluid	Visual		7.3	<u>MAC</u>	NA	12/18/90
STRAIGHTNESS TEST		Inspection Method	Criteria	Accept	Reject	Date
Well Straightness	Visual		7.3	<u>SST</u>	NA	12/13/90
COMPLETION		Inspection Method	Criteria	Accept	Reject	Date
Drilled Depth	Steel Tape # L300-16		G-W Mon. Plan	<u>SST</u>	NA	12/13/90
Completed Depth	Steel Tape # L300-16		G-W Mon. Plan	<u>MAC</u>	NA	1/9/91
PERMANENT SCREEN/CASING		Inspection Method	Criteria	Accept	Reject	Date
Screen Type/Slot/Length	Engineers Tape, Visual		4.2	<u>MAC</u>	NA	1/9/91
Screened Interval	Steel Tape # L300-16			<u>MAC</u>	NA	1/9/91
Casing Type/Size/Length	Engineers Tape, Visual		4.2	<u>MAC</u>	NA	1/9/91
Centralizers/Location	Engineers Tape, Visual		4.2	<u>MAC</u>	NA	1/9/91
Other				<u>N/A</u>	NA	
FILTER PACK/ANNULAR SEAL		Inspection Method	Criteria	Accept	Reject	Date
Primary Filter Mtl/Place	Visual/Steel Tape # L300-16		4.2, 5.4	<u>MAC</u>	NA	1/9/91
Second Filter Mtl/Place	Visual/Steel Tape #		4.2, 5.4	<u>MAC</u>	NA	
Annular Seal Mtl/Place	Visual/Steel Tape # L300-16		4.2, 5.4	<u>MAC</u>	NA	1/9/91
Install Annul Seal	Visual/Steel Tape #		4.2, 5.4	<u>MAC</u>	NA	
Cement Type/Placement	Visual/Steel Tape #		4.2, 5.4	<u>SST</u>	NA	1/10/91
Overdrill Seal Method	Visual/Steel Tape #		N/A		NA	
WELL PROTECTION		Inspection Method	Criteria	Accept	Reject	Date
Surface Pad Mtl/Place	Visual/Engineers Tape		4.2	<u>MAC</u>	NA	1/10/91
Surface Casing Mtl/Place	Visual/Engineers Tape		4.2	<u>MAC</u>	NA	1/10/91
Cap/Hasp/Lock	Visual			<u>MAC</u>	NA	1/10/91
WELL SURVEYING/MARKING		Inspection Method	Criteria	Accept	Reject	Date
Well ID Stamped/Correct	Visual		4.2		NA	
Well Surveyed/Toler Met	Review Survey Data				NA	
PUMP INSTALLATION		Inspection Method	Criteria	Accept	Reject	Date
Pump Decon/Preparation	Visual		N/A	<u>MAC</u>	NA	
Installation/Placement	Visual/Engineers Tape		N/A	<u>MAC</u>	NA	
Pump Operational	Observed Running			<u>MAC</u>	NA	

Technical Review Complete RL McLeanDate 12-4-92

Dev D

WELL INSPECTION REPORT

Well No. 60-40-E-47 Procedure D-5 Rev. 0
Geologist(s) W. J. McLean, MA (License 2572)

Specification No. P-6112-C2 Rev. 0
ECNs (list) _____

CLEANING/DECONTAMINATION	Inspection Method	Criteria	Accept	Reject	Date
Rig/Tools (initial)	Visual/Wipe (optional)	2.1	☒	☐	11/12/90
Temporary Materials	Visual/Wipe (optional)	4.1	☒	☐	12/15/90
Permanent Materials	Visual/Wipe (optional)	4.2.2	☒	☐	3/7/91
Mtls Brought Onsite Later	Visual/Wipe (optional)				

MATERIAL STORAGE/PACKING	Inspection Method	Criteria	Accept	Reject	Date
Material Storage	Visual	7.5	☒	☐	3/7/91
Material Packing/Seals	Visual	4.2, 7.5	☒	☐	3/7/91
Other					

LUBRICANTS/ADDITIVES/AIDS	Inspection Method	Criteria	Accept	Reject	Date
Lubricants	Visual	7.2	☒	☐	11/12/90
Additives/Aids	Visual	7.4	☒	☐	12/15/90

DRILLING METHOD	Inspection Method	Criteria	Accept	Reject	Date
Method	Visual	5.2	☒	☐	12/15/90
Drilling Fluid	Visual	7.2	☒	☐	12/15/90

STRAIGHTNESS TEST	Inspection Method	Criteria	Accept	Reject	Date
Well Straightness	Visual	2.2	☒ SST	☐	12/13/90

COMPLETION	Inspection Method	Criteria	Accept	Reject	Date
Drilled Depth	Steel Tape # <u>L3 10-14</u>	G-W Mon. Plan	☒ SST	☐	12/13/90
Completed Depth	Steel Tape # <u>L3 10-14</u>	G-W Mon. Plan	☒ N/A	☐	

PERMANENT SCREEN/CASING	Inspection Method	Criteria	Accept	Reject	Date
Screen Type/Slot/Length	Engineers Tape, Visual	4.2	☒ N/A	☐ N/A	1/14/91
Screened Interval	Steel Tape # <u>L300-16</u>		☒ N/A	☐ N/A	1/14/91
Casing Type/Size/Length	Engineers Tape, Visual	4.2	☒ N/A	☐ N/A	
Centralizers/Location	Engineers Tape, Visual	4.2	☒ N/A	☐ N/A	
Other <u>Well Abandoned</u>					

FILTER PACK/ANNULAR SEAL	Inspection Method	Criteria	Accept	Reject	Date
Primary Filter Mtl/Place	Visual/Steel Tape# <u>L300-16</u>	4.2, 5.4	☒ N/A	☐ N/A	1/14/91
Second Filter Mtl/Place	Visual/Steel Tape# <u>L300-16</u>	4.2, 5.4	☒	☐	1/2/91
Annular Seal Mtl/Place	Visual/Steel Tape# <u>L300-16</u>	4.2, 5.4	☒	☐	1/3/91
Install Annul Seal	Visual/Steel Tape# <u>L300-16</u>	4.2, 5.4	☒	☐	
Cement Type/Placement	Visual/Steel Tape#	4.2, 5.4	☒ SST	☐	1/10/91
Overdrill Seal Method	Visual/Steel Tape#		☒ N/A	☐ N/A	

WELL PROTECTION	Inspection Method	Criteria	Accept	Reject	Date
Surface Pad Mtl/Place	Visual/Engineers Tape	4.2	☒ N/A	☐ N/A	
Surface Casing Mtl/Place	Visual/Engineers Tape	4.2	☒ N/A	☐ N/A	
Cap/Hasp/Lock	Visual		☒ N/A	☐ N/A	

WELL SURVEYING/MARKING	Inspection Method	Criteria	Accept	Reject	Date
Well ID Stamped/Correct	Visual	4.2	☒ N/A	☐ N/A	
Well Surveyed/Toler Met	Review Survey Data				

PUMP INSTALLATION	Inspection Method	Criteria	Accept	Reject	Date
Pump Decon/Preparation	Visual	NA	☒ N/A	☐ N/A	
Installation/Placement	Visual/Engineers Tape	NA	☒ N/A	☐ N/A	
Pump Operational	Observed Running		☒ N/A	☐ N/A	

Technical Review Complete W. J. McLean

Date 12-4-92

AS-BUILT DIAGRAM

Boring or Well Number 1694-42-E7A

Sheet 1 of 2

Location Sevast Island

Project _____

Logged by T Gilmore, S Teel, M Chamness

Date Well Started 11/12/90

Reviewed by V L. Nathan

Date 12-4-92

Date Well Completed 1/10/91

Well Construction Data

Geologic/Hydrologic Data

Description	Drill Bit Construction Diagram	Depth in Feet	Sample Method	
			Lithologic Diagram	Lithologic Description
Cement grout to		5		SILT
12" carbon steel casing to 15.5'		10		SLIGHTLY GRAVELLY SILT
Valclay pellets to 13.0'		15		SILTY GRAVEL
10-20 mesh sand to 17.4'		20		" "
		25		MUDDY GRAVEL
		30		MUDDY SANDY GRAVEL
10" carbon steel casing		35		SANDY GRAVEL
(+2.5' - 139.7')		40		SAND (starts at 37')
		45		-44' Gravelly Sand
		50		" "
		55		SLIGHTLY MUDDY GRAVELLY SAND (start @ 53.5')
		60		" " " "
		65		SLIGHTLY MUDDY SAND
		70		MUDDY SAND
		75		" "
		80		" " (to 80.5')
		85		SAND (starts @ 80.5')
		90		MUDDY SAND
		95		" " to 95'
		100		starts at 95' CLAYEY SILT TO SILTY CLAY
		105		missed sample
		110		SANDY MUD TO MUDDY SAND
		115		SAND
		120		SLIGHTLY MUDDY SAND
		125		" " "
		130		" " "
		135		Sand @ 130'
		140		" "
		145		SANDY MUD
		150		MUD @ 147.5' SANDY MUD (starts @ 148.3)
		155		" "
		160		SLIGHTLY MUDDY SAND
		165		SAND

Drill Bit/Sample Method Used:

☐ Rotary ☒ Air Rotary ☒ Mud Rotary ☐ Air Percussion ☐ Back Hoe ☐ Auger ☐ Drive Barrel ☐ Hard Tool ☐ Split-Barrel

AS-BUILT DIAGRAM

Boring or Well Number 699-42-E9A

Sheet 2 of 2

Location Savage Island

Project _____

Logged by _____

Date Well Started 11/12/90

Reviewed by _____

Date _____

Date Well Completed _____

Well Construction Data

Geologic/Hydrologic Data

Description	Construction Diagram	Depth in Feet	Sample Method	
			Lithologic Diagram	Lithologic Description
		165		
		170		SLIGHTLY MUDDY SAND
		175		" " "
		180		SAND
		185		"
		190		SLIGHTLY MUDDY SAND
		195		SANDY MUD
		200		GRAVELLY SANDY MUD
		205		SLIGHTLY GRAVELLY MUD
		210		MUD (predom. clay)
		215		" " "
		220		" (incr. in silt)
		225		" (more clay & color change @ 229')
		230		MUDDY SAND (starts at 229.5') SLIGHTLY GRAVELLY SLIGHTLY MUDDY SAND (230-231')
				Basalt (starts @ 231')

8" temporary casing
(+4.1 - 194.91)

Total drill depth = 233'

Drill Bit/Sample Method Used:

☐ Rotary ☒ Air Rotary ☐ Mud Rotary ☐ Air Percussion ☐ Back Hoe ☐ Auger ☐ Drive Barrel ☐ Hard Tool ☐ Split-Barrel

699-42-E9A

--	--

DAILY BOREHOLE LOG									
Boring or Well Number		699-42-E9A		Depth		10' - 20'		Sheet 1 of 1	
Location		Not Ringold		Project		Savage Island			
Logged by		Tyler Calinec		Date		11/13/90			
Reviewed by		Print		Sign		Date			
Lithologic Classification Scheme		Folk		Procedure		DO-1		Rev No 1	
Measuring Equipment		N/A		Drilling Contractor		Bosch and Range			
				Driller		Bob Perry			
				Rig/Method		Cabletool BE 22w / Drive barrel			
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS (DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUIDS, ETC.)	
10'					Measured w/ HNU (PID) in breaching zone - no reading - 0 ppm	725		16' 4"	Arrive at Site
					Gravel layer 1' thick 10'-11' up to 730				Calibrate HNU (PID) w/
					Medium cobbles				Spore Gas
									Drilling
15'	Lith 2	PID	0 ppm		SILTY GRAVEL 35% Gravel	845			
	Moist 1				80% Sand; 57% Silt; 20% CP, 5% MP,				
					5% FP, 5% VEP, 8% VES, 57% Silt; poor				
					set; Gravel; 30% BSIT 30% Felsic; rd -				
					subbed; dry color 10PR 6/2 + brashy				
					strong rxn in HCL, More Gravel than				
					previous	915			RPT arrives at site; measure
20'	Lith 2	PID	0 ppm		SILTY GRAVEL 40% Gravel, 10% Sand,	945			Spill pile form 0' - 15' no
	Moist 1				50% Silt, 15% CP, 10% MP, 10% F, 5%				readings above background
					VEP, 3% VES, 7% VES, 50% Silt, VEP set,				
					Gravel; 75% BSIT, 25% Felsic, rd - sh				
					10PR 6/2 + brashy, strong rxn in HCL				
					No can set similar to previous				
					Drillers Quit for Day to attend Training	1115			End of Day
					Class				

W = wet, M = moist, D = dry

Project Savage Is.

970-867-3177

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG

Boring or Well Number 099-42-EGA Depth 30'-35' Sheet 2 of 2
 Location Savage Island (N. of Ringold) Project Savage Is

Logged by NA Chavness Sign NA Chavness Date 11/14/90
 Print
 Reviewed by Folk Sign NA Chavness Date 11/14/90
 Lithologic Classification Scheme Folk Procedure NO-1, DO-5 Rev No 1, D
 Measuring Equipment JA

Drilling Contractor Basin + Range
 Driller Robert Perry, Les Kunkle
 Rig/Method Cable tool, BE-220

Measuring Equipment DA										DRILLING COMMENTS (DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)	
DEPTH	SAMPLES		CONTAMINATION		MOIS- TURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASINGS	
	TYPE	NO.	INSTRUMENT	READING							
							30' cont'd. - 50% gtz, 25% ck frags, VA-SR. Very slight rxn in HCL, wet color fines - 2.5Y4/2 (dk grayish brown). Unconsolidated.

35'	Wth	2			Wet		STUDY GRAVEL - 50% gravel, 48% sand, 2% mud. 1% = cobbles, 10% vcg, 18% cg, 10% mg, 6% fg, 5% vfg, 3% w, 10% cs, 20% ms, 10% fs. 5% vls, 2% mud. VP tested. Gravel - mostly unbroken.			1445 Sampled 35'	
	Moist	1					25% base of 10% ign/metam, 15% gtz/qltz, VA-WR. Sand - 15% basalt, 70% gtz, 15% rk frags, tr. biotite, VA-SR. wet color fines - 2.5Y4/2 (dk grayish brown). Unconsolidated.			1520 Tried measuring DA + DW, but no steel tape or e-tape, used nylon surveyors tape, and found hole had sloughed in to 27.4' w/ water on top.	
										1515 Changing to jss for split tube sampler tomorrow.	
										1545 Picking up, locking stuff away	
										1600 Left site	

DAILY BOREHOLE LOG

Boring or Well Number 1099-42-EGA
 Location Savage Island

Sheet 1 of 2
 Project _____

Logged by MA Chawin
 Print

MA Chawin
 Sign

Drilling Contractor Boston + Range

Checked by _____
 Print

 Sign

Driller Robert Perry
 Rite/Method cable tool - RS 220

Lithologic Classification Scheme Folk

Procedure DO-1

Rev No. 1

Measuring Equipment 200-lb steel logs, 10997 tape

DEPTH	SAMPLES	CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.	TIME	H ₂ O ADDED (gal)	DRILLING COMMENTS (DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)	
	TYPE	NO.	INSTRUMENT	READING					CASING	
						Calibrated HNU w/ 1506418 ggs, span at 5.74	730		28.7' of	On site
							740		10"	Checked w/ HNU + LEL, both ok
			HNU	0						DB = 28.2' - 4' stickup + 2.0' =
			LEL	2083.0						27.3' w/ steel tape
										ΔW = 31.1' - 4' = 27.1' w/ tape
							750			Have to take jgs back off to
										mid hcl - 1 set line cleaned
										out for split tube sample.
							820		19.2'	Welding on 9.2' of 10"
									37.9'	
							715			Driving casing, marking cable
							935			Drilling
							1035			Finishing rig
							1045			Drilling added 500' H ₂ O
										from split tube log.
							1210			Drum casing, added 500' H ₂ O
			HNU	0			1250			Failed, added 500' H ₂ O
			LEL	2083.0			1270			Chasing to set of split tube
										sample
							1250			Driving split tube casing, etc.
										81' blow w/ jgs + steel
							1420			Sampled 25' - 26.5'

35.5
 34.5
 33.5
 32.5
 31.5
 30.5
 29.5
 28.5
 27.5
 26.5
 25.5
 24.5
 23.5
 22.5
 21.5
 20.5
 19.5
 18.5
 17.5
 16.5
 15.5
 14.5
 13.5
 12.5
 11.5
 10.5
 9.5
 8.5
 7.5
 6.5
 5.5
 4.5
 3.5
 2.5
 1.5
 0.5
 0.0
 -0.5
 -1.0
 -1.5
 -2.0
 -2.5
 -3.0
 -3.5
 -4.0
 -4.5
 -5.0
 -5.5
 -6.0
 -6.5
 -7.0
 -7.5
 -8.0
 -8.5
 -9.0
 -9.5
 -10.0
 -10.5
 -11.0
 -11.5
 -12.0
 -12.5
 -13.0
 -13.5
 -14.0
 -14.5
 -15.0
 -15.5
 -16.0
 -16.5
 -17.0
 -17.5
 -18.0
 -18.5
 -19.0
 -19.5
 -20.0
 -20.5
 -21.0
 -21.5
 -22.0
 -22.5
 -23.0
 -23.5
 -24.0
 -24.5
 -25.0
 -25.5
 -26.0
 -26.5
 -27.0
 -27.5
 -28.0
 -28.5
 -29.0
 -29.5
 -30.0
 -30.5
 -31.0
 -31.5
 -32.0
 -32.5
 -33.0
 -33.5
 -34.0
 -34.5
 -35.0
 -35.5
 -36.0
 -36.5
 -37.0
 -37.5
 -38.0
 -38.5
 -39.0
 -39.5
 -40.0
 -40.5
 -41.0
 -41.5
 -42.0
 -42.5
 -43.0
 -43.5
 -44.0
 -44.5
 -45.0
 -45.5
 -46.0
 -46.5
 -47.0
 -47.5
 -48.0
 -48.5
 -49.0
 -49.5
 -50.0
 -50.5
 -51.0
 -51.5
 -52.0
 -52.5
 -53.0
 -53.5
 -54.0
 -54.5
 -55.0
 -55.5
 -56.0
 -56.5
 -57.0
 -57.5
 -58.0
 -58.5
 -59.0
 -59.5
 -60.0
 -60.5
 -61.0
 -61.5
 -62.0
 -62.5
 -63.0
 -63.5
 -64.0
 -64.5
 -65.0
 -65.5
 -66.0
 -66.5
 -67.0
 -67.5
 -68.0
 -68.5
 -69.0
 -69.5
 -70.0
 -70.5
 -71.0
 -71.5
 -72.0
 -72.5
 -73.0
 -73.5
 -74.0
 -74.5
 -75.0
 -75.5
 -76.0
 -76.5
 -77.0
 -77.5
 -78.0
 -78.5
 -79.0
 -79.5
 -80.0
 -80.5
 -81.0
 -81.5
 -82.0
 -82.5
 -83.0
 -83.5
 -84.0
 -84.5
 -85.0
 -85.5
 -86.0
 -86.5
 -87.0
 -87.5
 -88.0
 -88.5
 -89.0
 -89.5
 -90.0
 -90.5
 -91.0
 -91.5
 -92.0
 -92.5
 -93.0
 -93.5
 -94.0
 -94.5
 -95.0
 -95.5
 -96.0
 -96.5
 -97.0
 -97.5
 -98.0
 -98.5
 -99.0
 -99.5
 -100.0
 -100.5
 -101.0
 -101.5
 -102.0
 -102.5
 -103.0
 -103.5
 -104.0
 -104.5
 -105.0
 -105.5
 -106.0
 -106.5
 -107.0
 -107.5
 -108.0
 -108.5
 -109.0
 -109.5
 -110.0
 -110.5
 -111.0
 -111.5
 -112.0
 -112.5
 -113.0
 -113.5
 -114.0
 -114.5
 -115.0
 -115.5
 -116.0
 -116.5
 -117.0
 -117.5
 -118.0
 -118.5
 -119.0
 -119.5
 -120.0
 -120.5
 -121.0
 -121.5
 -122.0
 -122.5
 -123.0
 -123.5
 -124.0
 -124.5
 -125.0
 -125.5
 -126.0
 -126.5
 -127.0
 -127.5
 -128.0
 -128.5
 -129.0
 -129.5
 -130.0
 -130.5
 -131.0
 -131.5
 -132.0
 -132.5
 -133.0
 -133.5
 -134.0
 -134.5
 -135.0
 -135.5
 -136.0
 -136.5
 -137.0
 -137.5
 -138.0
 -138.5
 -139.0
 -139.5
 -140.0
 -140.5
 -141.0
 -141.5
 -142.0
 -142.5
 -143.0
 -143.5
 -144.0
 -144.5
 -145.0
 -145.5
 -146.0
 -146.5
 -147.0
 -147.5
 -148.0
 -148.5
 -149.0
 -149.5
 -150.0
 -150.5
 -151.0
 -151.5
 -152.0
 -152.5
 -153.0
 -153.5
 -154.0
 -154.5
 -155.0
 -155.5
 -156.0
 -156.5
 -157.0
 -157.5
 -158.0
 -158.5
 -159.0
 -159.5
 -160.0
 -160.5
 -161.0
 -161.5
 -162.0
 -162.5
 -163.0
 -163.5
 -164.0
 -164.5
 -165.0
 -165.5
 -166.0
 -166.5
 -167.0
 -167.5
 -168.0
 -168.5
 -169.0
 -169.5
 -170.0
 -170.5
 -171.0
 -171.5
 -172.0
 -172.5
 -173.0
 -173.5
 -174.0
 -174.5
 -175.0
 -175.5
 -176.0
 -176.5
 -177.0
 -177.5
 -178.0
 -178.5
 -179.0
 -179.5
 -180.0
 -180.5
 -181.0
 -181.5
 -182.0
 -182.5
 -183.0
 -183.5
 -184.0
 -184.5
 -185.0
 -185.5
 -186.0
 -186.5
 -187.0
 -187.5
 -188.0
 -188.5
 -189.0
 -189.5
 -190.0
 -190.5
 -191.0
 -191.5
 -192.0
 -192.5
 -193.0
 -193.5
 -194.0
 -194.5
 -195.0
 -195.5
 -196.0
 -196.5
 -197.0
 -197.5
 -198.0
 -198.5
 -199.0
 -199.5
 -200.0
 -200.5
 -201.0
 -201.5
 -202.0
 -202.5
 -203.0
 -203.5
 -204.0
 -204.5
 -205.0
 -205.5
 -206.0
 -206.5
 -207.0
 -207.5
 -208.0
 -208.5
 -209.0
 -209.5
 -210.0
 -210.5
 -211.0
 -211.5
 -212.0
 -212.5
 -213.0
 -213.5
 -214.0
 -214.5
 -215.0
 -215.5
 -216.0
 -216.5
 -217.0
 -217.5
 -218.0
 -218.5
 -219.0
 -219.5
 -220.0
 -220.5
 -221.0
 -221.5
 -222.0
 -222.5
 -223.0
 -223.5
 -224.0
 -224.5
 -225.0
 -225.5
 -226.0
 -226.5
 -227.0
 -227.5
 -228.0
 -228.5
 -229.0
 -229.5
 -230.0
 -230.5
 -231.0
 -231.5
 -232.0
 -232.5
 -233.0
 -233.5
 -234.0
 -234.5
 -235.0
 -235.5
 -236.0
 -236.5
 -237.0
 -237.5
 -238.0
 -238.5
 -239.0
 -239.5
 -240.0
 -240.5
 -241.0
 -241.5
 -242.0
 -242.5
 -243.0
 -243.5
 -244.0
 -244.5
 -245.0
 -245.5
 -246.0
 -246.5
 -247.0
 -247.5
 -248.0
 -248.5
 -249.0
 -249.5
 -250.0
 -250.5
 -251.0
 -251.5
 -252.0
 -252.5
 -253.0
 -253.5
 -254.0
 -254.5
 -255.0
 -255.5
 -256.0
 -256.5
 -257.0
 -257.5
 -258.0
 -258.5
 -259.0
 -259.5
 -260.0
 -260.5
 -261.0
 -261.5
 -262.0
 -262.5
 -263.0
 -263.5
 -264.0
 -264.5
 -265.0
 -265.5
 -266.0
 -266.5
 -267.0
 -267.5
 -268.0
 -268.5
 -269.0
 -269.5
 -270.0
 -270.5
 -271.0
 -271.5
 -272.0
 -272.5
 -273.0
 -273.5
 -274.0
 -274.5
 -275.0
 -275.5
 -276.0
 -276.5
 -277.0
 -277.5
 -278.0
 -278.5
 -279.0
 -279.5
 -280.0
 -280.5
 -281.0
 -281.5
 -282.0
 -282.5
 -283.0
 -283.5
 -284.0
 -284.5
 -285.0
 -285.5
 -286.0
 -286.5
 -287.0
 -287.5
 -288.0
 -288.5
 -289.0
 -289.5
 -290.0
 -290.5
 -291.0
 -291.5
 -292.0
 -292.5
 -293.0
 -293.5
 -294.0
 -294.5
 -295.0
 -295.5
 -296.0
 -296.5
 -297.0
 -297.5
 -298.0
 -298.5
 -299.0
 -299.5
 -300.0
 -300.5
 -301.0
 -301.5
 -302.0
 -302.5
 -303.0
 -303.5
 -304.0
 -304.5
 -305.0
 -305.5
 -306.0
 -306.5
 -307.0
 -307.5
 -308.0
 -308.5
 -309.0
 -309.5
 -310.0
 -310.5
 -311.0
 -311.5
 -312.0
 -312.5
 -313.0
 -313.5
 -314.0
 -314.5
 -315.0
 -315.5
 -316.0
 -316.5
 -317.0
 -317.5
 -318.0
 -318.5
 -319.0
 -319.5
 -320.0
 -320.5
 -321.0
 -321.5
 -322.0
 -322.5
 -323.0
 -323.5
 -324.0
 -324.5
 -325.0
 -325.5
 -326.0
 -326.5
 -327.0
 -327.5
 -328.0
 -328.5
 -329.0
 -329.5
 -330.0
 -330.5
 -331.0
 -331.5
 -332.0
 -332.5
 -333.0
 -333.5
 -334.0
 -334.5
 -335.0
 -335.5
 -336.0
 -336.5
 -337.0
 -337.5
 -338.0
 -338.5
 -339.0
 -339.5
 -340.0
 -340.5
 -341.0
 -341.5
 -342.0
 -342.5
 -343.0
 -343.5
 -344.0
 -344.5
 -345.0
 -345.5
 -346.0
 -346.5
 -347.0
 -347.5
 -348.0
 -348.5
 -349.0
 -349.5
 -350.0
 -350.5
 -351.0
 -351.5
 -352.0
 -352.5
 -353.0
 -353.5
 -354.0
 -354.5
 -355.0
 -355.5
 -356.0
 -356.5
 -357.0
 -357.5
 -358.0
 -358.5
 -359.0
 -359.5
 -360.0
 -360.5
 -361.0
 -361.5
 -362.0
 -362.5
 -363.0
 -363.5
 -364.0
 -364.5
 -365.0
 -365.5
 -366.0
 -366.5
 -367.0
 -367.5
 -368.0
 -368.5
 -369.0
 -369.5
 -370.0
 -370.5
 -371.0
 -371.5
 -372.0
 -372.5
 -373.0
 -373.5
 -374.0
 -374.5
 -375.0
 -375.5
 -376.0
 -376.5
 -377.0
 -377.5
 -378.0
 -378.5
 -379.0
 -379.5
 -380.0
 -380.5
 -381.0
 -381.5
 -382.0
 -382.5
 -383.0
 -383.5
 -384.0
 -384.5
 -385.0
 -385.5
 -386.0
 -386.5
 -387.0
 -387.5
 -388.0
 -388.5
 -389.0
 -389.5
 -390.0
 -390.5
 -391.0
 -391.5
 -392.0
 -392.5
 -393.0
 -393.5
 -394.0
 -394.5
 -395.0
 -395.5
 -396.0
 -396.5
 -397.0
 -397.5
 -398.0
 -398.5
 -399.0
 -399.5
 -400.0
 -400.5
 -401.0
 -401.5
 -402.0
 -402.5
 -403.0
 -403.5
 -404.0
 -404.5
 -405.0
 -405.5
 -406.0
 -406.5
 -407.0
 -407.5
 -408.0
 -408.5
 -409.0
 -409.5
 -410.0
 -410.5
 -411.0
 -411.5
 -412.0
 -412.5
 -413.0
 -413.5
 -414.0
 -414.5
 -415.0
 -415.5
 -416.0
 -416.5
 -417.0
 -417.5
 -418.0
 -418.5
 -419.0
 -419.5
 -420.0
 -420.5
 -421.0
 -421.5
 -422.0
 -422.5
 -423.0
 -423.5
 -424.0
 -424.5
 -425.0
 -425.5
 -426.0
 -426.5
 -427.0
 -427.5
 -428.0
 -428.5
 -429.0
 -429.5
 -430.0
 -430.5
 -431.0
 -431.5
 -432.0
 -432.5
 -433.0
 -433.5
 -434.0
 -434.5
 -435.0
 -435.5
 -436.0
 -436.5
 -437.0
 -437.5
 -438.0
 -438.5
 -439.0
 -439.5
 -440.0
 -440.5
 -441.0
 -441.5
 -442.0
 -442.5
 -443.0
 -443.5
 -444.0
 -444.5
 -445.0
 -445.5
 -446.0
 -446.5
 -447.0
 -447.5
 -448.0
 -448.5
 -449.0
 -449.5
 -450.0
 -450.5
 -451.0
 -451.5
 -452.0
 -452.5
 -453.0
 -453.5
 -454.0
 -454.5
 -455.0
 -455.5
 -456.0
 -456.5
 -457.0
 -457.5
 -458.0
 -458.5
 -459.0
 -459.5
 -460.0
 -460.5
 -461.0
 -461.5
 -462.0
 -462.5
 -463.0
 -463.5
 -464.0
 -464.5
 -465.0
 -465.5
 -466.0
 -466.5
 -467.0
 -467.5
 -468.0
 -468.5
 -469.0
 -469.5
 -470.0
 -470.5
 -471.0
 -471.5
 -472.0
 -472.5
 -473.0
 -473.5
 -474.0
 -474.5
 -475.0
 -475.5
 -476.0
 -476.5
 -477.0
 -477.5
 -478.0
 -478.5
 -479.0
 -479.5
 -480.0
 -480.5
 -481.0
 -481.5
 -482.0
 -482.5
 -483.0
 -483.5
 -484.0
 -484.5
 -485.0
 -485.5
 -486.0
 -486.5
 -487.0
 -487.5

DAILY BOREHOLE LOG

Boring or Well Number 109-42-EGA
Location Sample Island C.N. of P.

Project Savage Is.

Sheet 2 of 2

Logged by JAF Chowness Print

MA Chavannes

Date 11/15/50

Checked by _____
Print

Sign

Date _____

Lithologic Classification Scheme

Procedure ~~20~~ 1

Rev No. 1

Measuring Equipment 1200-16 steel tape

[illegible]

W = wet, M = moist, D = dry

A-1800-003 (01/90)

Boring or Well Number 699-42-£9A Depth 41.7-44 Sheet 1 of 2
 Location N of Ringold (Savage Is.) Project Savage Island

Logged by SS Teel Print SS Teel Sign Date 11/26/90
 Reviewed by _____ Print _____ Sign Date _____
 Lithologic Classification Scheme Folk Procedure DO-1 Rev No 1
 Measuring Equipment Steel Tape L300-16

DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASING	DRILLING COMMENTS (DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
	TYPE	NO.	INSTRUMENT	READING							
							Well is sealed w/ a welded cap (done on 11/15/90)	0950		47.55'	Arrive onsite. Driller is already on site and is setting-up rig.
							MNU Spun @ 5.80	1100			Calibrated MNU. 0 ppm at borehole
							0/water = 30.24 - 3.4 = 26.84 b.l.s.	1102			21% O ₂ / 0% LEL at borehole
							0/bottom = 42.10 - 3.4 + 3.02 = 41.72	1105			
								1115			Sample w/ split spoon
											16 blows / 1.5'; 10% recovery. Did not save.
											Reattempted split spoon.
							Gravelly Sand (15% gravel, 82% sand, 3% silt)	1130			100% recovery. 36 blows / 1.5 ft
							4% CP, 5% MP, 4% FP, 2% VFP, 5% VCS, 10% CS,				Interval 42-44'
							52% MS, 10% FS, 5% VFS, 3% silt/clay.				Bottom of casing @ 44.1'
							Poorly sorted, (Gravel) - 35% basalt/natics.				Changing to Hard Tool
							65% gtzite + Si-rich rock frags, SR-WR,	1140			Drilling w/ Hard Tool
							(Sand) - 20% basalt/natics, 80% gtz, gtzite, +	1155			
							Si-rich rock fragments, A-R. Dry color:				
							SYR 6/1 (light gray). Unconsolidated,				
							No reaction to 10% HCL. Only saved the				
							lower 0.7 ft of the core - the upper				
							part did not seem representative. Sample				
							was collected in a bag and placed in the				
							core box.				

W = wet, M = moist, D = dry

A-1800-003 (05/90)

Logged by

SS Teel

Print

Reviewed by

Print

Lithologic Classification Scheme

Folk

Procedure

DO-1

Rev No

1

Measuring Equipment

Steel Tape L 300-16

Drilling Contractor

Basin & Range

Driller

Robert Perry, Les Kunkle (helper)

Rig/Method

Cable Tool / 22W Hard Tool

DEPTH		SAMPLES		CONTAMINATION		MOIS- TURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS (DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)	
	TYPE	NO.	INSTRUMENT	READING							CASING	
47.5	Lith	2	HNU	0 PPM			46.5	Gravelly Sand (15% gravel, 82% sand, 3% mud)	1330		47.55	Sample w/ Dart Bailer
			Lithus Paper	6.8			0 0					

12

DAILY BOREHOLE LOG				Boring or Well Number <u>699-43-E9A</u>		Depth <u>50' - 60'</u>	Sheet <u>1</u> of <u>4</u>
Location <u>North of Ringold</u>				Project <u>Swage Island</u>			
Logged by <u>Tyler Gilmore</u>		Sign <u>Tyler Gilmore</u>		Date <u>11/23/90</u>		Drilling Contractor <u>Basin and Range</u>	
Reviewed by _____		Sign _____		Date _____		Driller <u>Robert Rony / Les Kuakle</u>	
Lithologic Classification Scheme <u>Folk</u>				Procedure <u>Do - 1</u>		Rev No <u>1</u>	
Measuring Equipment <u>Steel Tape</u>				<u>L 300-16</u>		Rig/Method <u>Cabletool 22W / Hand tool</u>	

DEPTH	SAMPLES	CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS (DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
		NO.	INSTRUMENT						
						Depth to Bottom <u>46.8'</u>	<u>715</u>		<u>57.15'</u> Arrive at Site
						Depth to Water <u>43.3'</u> (Plug in Well)	<u>730</u>		Measure water level
						Calibrate Photo ionizing detector (HAKU)	<u>735</u>		Drilling
						Spoon at 5.6 to read SS on 0-200 scale	<u>740</u>		Measure at Borehole w/ HNU and LEL
<u>50'</u>	<u>L4H 2</u>	<u>PID</u>	<u>Ø ppm</u>	<u>N/A</u>		<u>GRAVELLY SAND 15% gravel, 80% sand, 5% mud; 5% Fp, 10% VFP, 10% UCS, 15% CS; 40% MS, 10% FS, 5% UFS, 5% Silt; VP Srt; Gravels: 60% Matrix (predom) 40% Felvic (predom wht - clt qtz) Some 40% Matrix 60% Felvic (predom qtz) Subang where preserved & fragmented (Not representative) 10% R 4/1 dk gy (wet color) No rxn in HCl sl consol</u>			Describe sample forms 11/24
<u>55'</u>	<u>L4H 2</u>	<u>PID</u>	<u>Ø ppm</u>	<u>N/A</u>		<u>SLIGHTLY MUDDY GRAVELLY SAND 15% gravel, 80% sand, 5% mud; 5% Fp, 10% VFP, 10% UCS, 15% CS; 40% MS, 10% FS, 5% UFS, 5% Silt; VP Srt; Gravels: 60% Matrix (predom) 40% Felvic (predom wht - clt qtz) Some 40% Matrix 60% Felvic (predom qtz) Subang where preserved & fragmented (Not representative) 10% R 4/1 dk gy (wet color) No rxn in HCl sl consol</u>			Driller suggested a change in Lithology at 53.5'

W = wet, M = moist, D = dry

F

Project Savage Island

Drilling Contractor Besic and Bore

Driller Robert Perry

Rig/Method	Cable tool	Head tool
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		
51		
52		
53		
54		
55		
56		
57		
58		
59		
60		
61		
62		
63		
64		
65		
66		
67		
68		
69		
70		
71		
72		
73		
74		
75		
76		
77		
78		
79		
80		
81		
82		
83		
84		
85		
86		
87		
88		
89		
90		
91		
92		
93		
94		
95		
96		
97		
98		
99		
100		

DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL ETC.)	TIME	H ₂ O ADDED	CASING	DRILLING COMMENTS (DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
	TYPE	NO.	INSTRUMENT	READING							
60'	L4h	2	PID	0 ppm	N/A	66'	SLIGHTLY MUDDY GRAVELLY SAND 15% gravel, 30% Sand, 52% Mud; 10% Fp, 5% VFp, 5% VF, 5% CS, 20% MS, 30% FS 10% VF, 15% Mud (prod. clay, cohesive form clay balls) Subang, 10% R6/s yellow, Abs rxn in HCl, sl consol similar to previous - faster drilling SLIGHTLY MUDDY SAND 5% Gravel, 80% Sand, 15% 15% Mud 5% Fp, 5% VF, 5% CS, 15% MS, 30% FS 25% VF, 15% Mud (50-50 silt/clay) some "clay balls" sl cohesive, 10% R 1/5 yellow No rxn in HCl, less gravel than previous Subang MUDDY SAND 5% Gravel, 70% Sand, 20% 25% Mud (50-50 clay/silt) 5% Fp, 5% CS, 10% MS, 30% FS, 25% VF, 25% Mud, some cohesive platy clay pieces, 10% R 0/s yel brow; Subang sands No rxn in HCl; sl consol (~15' open hole) More Mud than previous	1030		57.15	Sample
65'	L4h	2	PID	0 ppm		65'					Sample
70'	L4h	2	PID	0 ppm		70'					Sample

A-1800-003 (05/90)

Boring or Well Number 699-42-E9A

Boring or Well Number 699-
Location N of Ringold

Boring or Well Number 699-42-E9A
 Location Not Ringed
the Salmore Date 11/23/90
 Sian

Depth 70' - 80' Project Savage

Sheet 12445 I 240/16 I

7 10

7

Logged by Tyler Gilmore
Print

Tyler Salmore Sign

Date 11/23/90

Drilling Contractor Basik and Rance

Reviewed by _____
Print _____

Sign

Date _____

Driller Robert Perry

Lithologic Classification Scheme	Folk
Measuring Equipment	Steel Tape

Procedure Do.
L 300-16

Rev No 1

Rig/Method	Cable-Loop	BEOW/Haw
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		
51		
52		
53		
54		
55		
56		
57		
58		
59		
60		
61		
62		
63		
64		
65		
66		
67		
68		
69		
70		
71		
72		
73		
74		
75		
76		
77		
78		
79		
80		
81		
82		
83		
84		
85		
86		
87		
88		
89		
90		
91		
92		
93		
94		
95		
96		
97		
98		
99		
100		

Measuring Equipment Steel Tape L300-16

1

2022/05/06 10:00

[illegible]

W = wet, M = moist, D = dry

A-1800-003 (05/90)

DAILY BOREHOLE LOG

Boring or Well Number 699-43-E94
Location North of Ringold

Depth 80'-85' Sheet 4 of 4
Project Savage Island

Logged by _____
 1 x lev Oil movement before & after
 Print _____

Date 11/27/90

Basin and Range

Reviewed by _____
Print _____
Sign _____

Date _____

Pathologic Classification Scheme

Rev No 1

Rig/Method	Code	Top	BE 22W	Hard top
	Cable	100		

Rev No 1

Pathologic Classification Scheme

Measuring Equipment

DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASSING	DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.
	TYPE	NO.	INSTRUMENT	READING							
80'-81.5'	Split Spoon	PID	0 ppm	N/A			SIFTY SAND 60-80.5' AA SAND from 80.5'-81' Abundant Mica w/set;	1445		57.15	Split Spoon
							80% air, 20% ES, 10 PR % No rxn in HCl No visible structures Massive			+19.70	84 blows 1.5' 95% Recovery
							(1) MP (bolt) Abnt clv qtz grains			76.85	Lithology change @ 80.5' to Sand
81.5'-82.5'	Split Spoon	PID	0 ppm	N/A			81.5-82.5 SAND Some Gray (N4) Clay mottling No Sand Grains are present qtz Subang No rxn in HCl sl - no consol (Open hole ~23')	1415			Split Spoon
											71 blows 1.5'
											Switch to Hand tool
											Poly FM grease used
											Sample (Hand Tool)
85'	Lith 2	PID	0 ppm	N/A			SAND 95% Sand, 5% Silt; 10 PR MS, 60 PR ES; 25 GRUES, 5% Silt; well set; Subang;	1450			
							30% Matrix, 70% Felsic (predom qtz)				Water Samples (bail 4 times)
							10 PR 4/6 No rxn in HCl; Abnt Mica;	1505			COC #112790
							Similar to 81.5-82.5 Split spoon sample				Check hole w/ LEL - OK
							sl - No consol (beginning to lose open hole)			76.85	Add 19.7 at 10" casing
								1510			Welding
								1610			End of Day

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-42-89A</u>			Depth <u>85'-90'</u> Sheet <u>1</u> of <u>1</u>			Location <u>North of Ringold</u> Project <u>Savage Island</u>			
Logged by <u>SS Teel</u>		Print		Sign		Date <u>11/28/90</u>		Drilling Contractor <u>Basin + Range</u>	
Reviewed by		Print		Sign		Date		Driller <u>Robert Perry / Los Kunkle (helper)</u>	
Lithologic Classification Scheme <u>Folk</u>		Procedure <u>DD-1</u>		Rev No <u>1</u>		Rig/Method <u>Cable Tool / BE 22w / Hard Tool</u>			
Measuring Equipment <u>Steel tape L300-06 / E-type</u>									
DEPTH	SAMPLES	CONTAMINATION	MOIS- TURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASING	DRILLING COMMENTS (DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
						0740		76.85	Arrive on site
					$P_{water} = 50.0 - 23.7 = 26.3$ (mass, w/ E-tape)	0745			
						0750			Driving Casing
						0820			Drilling w/ Hard Tool
						0830			Calibrate HNU - spacer at
									5.82, Calib. w HNU cal. gas lot #
									28627 (100 ppm ISO C ₄ H ₁₀ / Air)
						0845			Checked borehole w/ HNU and
									LEL/O ₂ (10.2 ev - HNU)
									Sample w/ Dart Bailer
90' Lith	2	HNU	0 ppm	4/A	SILTY SAND (1% gravel, 79% sand, 20% mud)	1010			
		pH paper 6.5			1% FP + VFP, 91% CS, 25% MS, 25% FS,				
					20% VFS, 20% mud. Mod. well-sorted. 5% mafics				
					5% mica, 40% qtz, 3% Fe-stained - highly				
					weathered rock fragments, A-R. Wet color:				
					2.5 Y 4/4 (olive brown). No reaction to 10% HCL				
						1150			Preparing to add casing
		O ₂	21%			1200			Check borehole w/ HNU - LEL
		HNU	0 ppm			1210			Drill rig starter fails -
		LEL	0%						attempting to fix
									Will be down until it is fixed

W = wet, M = moist, D = dry

Welding cap on the A-1800-003 (05/90)
borehole

1245

1315

Boring or Well Number 699-42-E9A Depth 89' Sheet 1 of 2
Location W. of Ringold Project Savage Island

Daily Borehole Log
Logged by SS Teel Print _____ Date 11/29/90
Reviewed by _____ Sign _____
Lithologic Classification Scheme Folk Procedure D0-1 Rev No 1
Measuring Equipment Steel Tape L300-06

DEPTH	SAMPLES		CONTAMINATION		MOIS- TURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASING	(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
	TYPE	NO.	INSTRUMENT	READING							
								1300		76.85	Arrive on Site. Driving
										+19.90	Casing. Driller replaced the
										96.75	starter earlier today and
											added 19.9' of 10" casing.
								1310			Casing drove down to a 89'
											Will drill the plug out and
											then advance the hole to
											~ 95' where a split-spoon
											will be collected for microbe
											analysis.
								1315			Drilling w/ Hard Tool bit
								1330			Microbiologists arrive on site.
								1335			Calibrate HNU. Span still
											set @ 5.82 - used same
											cal. gas as previous.
								1340			Check hole w/ monitoring equipment
								1345			Bailing
								1350			Drilling w/ Hard Tool
								1400			Brief L. Doremus and
											GW McClellan on the HASP &
											JSP.
								1430			Brief Jeff Gale on the HASP

DAILY BOREHOLE LOG

Boring or Well Number 699-42-E9A Depth 93.5' - 95' Sheet 1 of 2
Location North of Ringold Project Savage Island

Logged by Tyler Guilmore Print Tyler Guilmore Date 11/30/80
Reviewed by Robert Perry Sign Robert Perry Date 11/30/80
Lithologic Classification Scheme Folk Procedure DP-1 Rev No 1
Measuring Equipment Steel Tape 6500-16 and E-Tape 11034 Rgm Method Cable Tool BE32w/Houston

Measuring Equipment										Steel Tape 6300-16 and E-Tape 11034																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASING	DRILLING COMMENTS (DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
	TYPE	NO.	INSTRUMENT	READING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
95'	Lith 2		PID					740		96.75	Arrive at Site																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											

DAILY BOREHOLE LOG									
Boring or Well Number <u>659-42-EQA</u>			Depth <u>99'-115'</u>		Sheet <u>1</u> of <u>3</u>		Project <u>Severe Island</u>		
Location <u>N. of Ringold</u>			Date <u>12/3/50</u>			Drilling Contractor <u>Bain + Range</u>			
Logged by <u>MA Chambers</u>			Sign <u>MA Chambers</u>			Driller <u>Robert Perry + Les Kunkle</u>			
Reviewed by <u>Folk</u>			Sign <u>Folk</u>			Rig/Method <u>cable tool BE220/hard tool</u>			
Lithologic Classification Scheme <u>Folk</u>			Procedure <u>NO-1, NO-5</u>			Rev No <u>1, D</u>			
Measuring Equipment <u>2-tape 11034</u>			Steel tape <u>1300-16</u>						
DEPTH	SAMPLES	CONTAMINATION		MODS-TURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION PARTICLE SIZE DIST., SPLITTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.	TIME	H ₂ O ADDED	DRILLING COMMENTS (DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
		INSTRUMENT	READING						
						Calibrated HNUA to 100ppm ISO-CyHoleir,	735		96.75'
						span set at 5.36			
						measured NW at 33.3' w/ E-tape, tried	745		
						5 times w/ steel tape and couldn't get			
						good reading.			
							800		
						CLAYEY SILT TO SILTY CLAY-(MUD)-difficult	805		
						to tell properties, can see fine dark			
						particles, so there must be some silt. wet			
						color - 10YR 5/4 (yellowish brown), unconsolidated			
						to slightly consolidated, maintains open			
						hole (well doesn't let water in. No run in HCl			
						samey mud to MUDY SAND - to gravel, 50% sand, 835			
						50% silt. fr. vfg. 1% veg. 2% cs. 2% ms. 10% fs,			
						30% vfg. 50% mud. Gravel - in sand - micaceous,			
						20% dk minerals, 80% H. minerals. Wet color			
						10YR 5/4 (yellowish brown). Unconsolidated. No run			
						50% silt - fr. gravel, 90% sand, 2% mud. 1% veg,	900		
						100% 40% ms, 50% fs, 15% vfg. 2% mud. wet			
						sorted. Sand. 90% gtz & talus, 5% mica.	920		
						5% dk minerals. No run in HCl. Wet color -			
						10YR 6/2 (H brownish gray). Unconsolidated.			

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG

Boring or Well Number 603-42-576

Depth 115'-130'

Sheet 2 of 2

Location Savage Island

Project Savage Island

Logged by MA Chamness

MA Chamness

Date 12/3/90

Drilling Contractor Basin + Range

Reviewed by

Sign

Date

Driller Robert Perry + Les Kuntle

Lithologic Classification Scheme Folk

Procedure DD-1

Rev No 10

Rig/Method Cable tool BE 22W / hand tool

Measuring Equipment 1/2" tape 11034 steel tape 1300-16

DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS (DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)	
	TYPE	NO.	INSTRUMENT	READING						CASING	
120'	Lith	2			110		SLIGHTLY MUDGY SAND - 85% sand, 15% mud, 2% cs, 43% ms, 20% fs, 20% bk, 15% mud. Mod sorted. Wet clay 10' to 15' (brown). 90% sand + feldspar, 5% dk minerals, 5% mica. Very runny, slightly concol. No rim in HCL.	1010			910.75' Sampled 120' w/d cast bailer.
125'	Lith	2			112		SLIGHTLY MUDGY SAND - similar to above, sand is 1050 more 30% ms, 30% fs, 25% bk, 15% mud. Sl. consolidated, holding open hole.				Sampled 125' w/d cast bailer
130'	Lith	2			113		SLIGHTLY MUDGY SAND - 90% sand, 10% mud, 2% cs, 50% ms, 25% fs, 13% bk, 10% mud. Wet. Mod. Sorted. Sand - 85% silt + feldspar, 13% dk minerals, 2% mica. Sl. consolidated. May not be holding open hole as well. No rim in HCL. Some brown + yellow stained minerals. Wet color - 10YR5/2 (brown).	1130 1155 1300 1415 1500			Sampled 130' w/d cast bailer + 19.0' Working on 19' at 10' casing 115.75 Drilling casing, hard to drive + 17.0' Working on 17' at 10' casing 132.75 Drilling casing, still hard to drive Measured 110' after casing was driven to ~111' @ ~30' wire-tape, may not be accurate due to sloughing of material into borehole Started drilling, casing to ~124' failed Drilling Stopped for clay, did not fail not hole but think hole is cleaned out

Note: The gravel found in the 102-109" sample is probably similar to the gravel found @ ~145'. There it's at the top of a fining-upward sequence w/ well - rounded gravels floating in a clay. Probably dep. at beginning of the next fining-up sequence.

W = wet, M = moist, D = dry

A-1800-003 (05/90)

DAILY BOREHOLE LOG

Boring or Well Number

699-42-E9A

Depth

130'-140'

Sheet

1

of

2

Location

North of Road

Project

SARPA E Island

Logged by

Tyler Gilmore

Print

Reviewed by

John Gilmore

Sign

Date

12/4/90

Lithologic Classification Scheme

Folk

Procedure

DO-1

Rev No

1

Measuring Equipment

Steel tape L 300-16

Steps

11054

Drilling Contractor

Basin and Sange

Driller

Robert Perry

Rig/Method

Cable tool BE 22w / hand tool

Split size

Split size

DEPTH	SAMPLES		CONTAMINATION	MOISTURE		GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS (DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
	TYPE	NO.		INSTRUMENT	READING					
							Depth to water 44.9 ft E. hole	715		132.75 On site
							Depth to water 123 ft Sand hole	725		Depth to water / 32 ft
							Depth to water 132.9' - mud in well			
							may have cut water off - Depth to bottom indicated set water bottom			
							Thin Facies Sandstone - mud in well			
							for water level			
								745		
								750		
130-							D/B 132.9' in Sand (w Steel wire)	915		Switch to Split barrel sampler
132.4							Split spoon 130.9' - 132.4' (Heavy Sand)			(For grade grease used)
							Fine sand - medium sand; cut wire	950		Split Spoon Sample
							Store in Aluminum box			Switch 40215
							Heavy Sands will drill past sand to take next Split spoon	1015		Drill
							SAND 100% Sand 203 MS, 203 FS, 100% 1030			Sample
							clean well set; shed - sandy; Sand is 75% qtz and feldspar, 25% matrix, some mica			
							next hole 514's. 100% sand; 100% 1001			

A-1800-003 (05/90)

DAILY BOREHOLE LOG

Boring or Well Number 699-42-E9A Depth 143.7' Sheet 1 of 1
 Location SAVAGE ISLAND Project SAVAGE ISLAND

Logged by S. A. Goodman Sign A. M. Shul Date 11/5/90
 Reviewed by Print Sign Print Date
 Lithologic Classification Scheme Folk Procedure Do-1 Rev No 1
 Measuring Equipment E-TAB #11093, STEEL TAPE 1300-16 Rig/Method CABLE TOOL BE 22.0

DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASING	DRILLING COMMENTS (DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
	TYPE	NO.	INSTRUMENT	READING							
143.7						CLEANED OUT HOLE w/ DART BAILEY; D/W = 48.9' BL.	1010		142.2'	BOTTOM OF 10" = 139.9'	
						PLACED TRACER IN WHOLE PAC BAG BETWEEN CUTTER HEAD & SPACER.	1015			DECON. SPLIT SPIND, CORE	
						TRACER CONSISTS OF ALUMINUM, TUNGSTEN CARBIDE, & GLASS BEADS.				CATCHER, SPACER, & CUTTER HEAD.	
							1020			REMOVING BIT FROM DRILL	
										STAINLESS & PLACING DRILLING	
										TRACER	
							1049			BEGIN SPLIT SPIND SAMPLING	
						RECOVERED 1.8' of CORE; TOP 8" APPEARS TO BE SAND & GRADES INTO A SANDY MUD. 143.7' - 145.5'	1051			4" BLUES / 18"	
							1055			CORE TAPPED & PLACED IN	
							1100			PLASTIC BAG FILLED w/ AQUA	
										DECON. SPLIT SPIND, ETC.	
							1105			TO PREPARE FOR 2 ND SAMPLE	
						GRANIC TRACER AS ABOVE	1115			ADDITIONAL TRACER	
							1123			BEGIN SAMPLING	
						HAVING DIFFICULTY PENETRATING SAMPLER DUE TO TIGHT FM.	1126			8" BLUES / 18"	
						RECOVERED 2.0' of CORE (FOR	1125			CORE TAPPED & PLACED IN	
										PLASTIC BAG - FILLED BAG.	

DRILLING COMMENTS
(DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)

A: 1800.003 (05/90)

W = wet, M = moist, D = dry

DEEP MICROBIOLOGY CORE DATA LOG

Core Interval: 143.7-145.5 Logger: BJORNSTAD

Date: 12/5/90

Depth Below Surface	Depth Below Bottom	Samples	Lithology	Class	Moisture	% Malle	Soring	Roundness (Model)	Color	Consistency	Cementation	Structure	HCl Reaction	Range in Particle Size	Maximum Particle Size	Comments
143.7		133	Tracer	S	W	S=5	W-W	11 A (50)	Grayish brown (10 YR 5/2)	Uncol	N	H	N	20% fin. sand 80% mod. sand	MS	Trace in bag (broken)
144		134		gM		G=50	W	6 SR-R	Brown (10 YR 5/3)	Med-stony (rough)				20% clay, 60% silt, 20% gravel	VCP	slings contact clayey silt streak, well rounded pebbles
145		135		M	N/A	N/A	VW	11 A	Lt yellowish brown (10 YR 6/4)					5% v. fin sand 95% silt	VFS	coarsening downward
145		128														
145		129														
145		109														
145		105														
145		125														
145		117														
145		126														
145		127														
145		106														
145		104														
145		103														
145		102														
145		101														
145		121a														

RINGOLD FM

DEEP MICROBIOLOGY CORE DATA LOG																
Core Interval: 145.5-147.5					Logger: BJORNSTAD											
Date: 12/5/90																
Depth Below Surface	Depth Below	Samples	Lithology	Class	Molave	% Mafic	Sorting	Roundness (Model)	Color	Consistency	Cementation	Structure	HCl Reaction	Range in Particle Size	Maximum Particle Size	Comments
11.1	112	112	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N	20% gravel, 40% sand, 40% mud	MP		
11.1	111	111	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N	40% v. fn. fr. sand, 60% silt	FS		Micaceous, (non-siliceous) downward
5	234	234	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N	50% v. fn. fr. sand, 50% silt			
11.1	233	233	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N	70% v. fn. fr. sand, 30% silt			
11.1	232	232	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	231	231	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	230	230	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	229	229	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	228	228	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	227	227	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	226	226	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	225	225	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	224	224	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	223	223	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	222	222	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	221	221	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	220	220	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	219	219	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	218	218	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	217	217	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	216	216	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	215	215	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	214	214	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	213	213	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	212	212	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	211	211	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	210	210	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	209	209	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	208	208	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	207	207	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	206	206	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	205	205	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	204	204	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	203	203	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	202	202	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	201	201	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	200	200	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	199	199	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	198	198	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	197	197	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	196	196	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	195	195	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	194	194	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	193	193	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	192	192	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	191	191	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	190	190	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	189	189	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	188	188	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	187	187	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	186	186	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	185	185	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	184	184	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	183	183	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	182	182	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	181	181	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	180	180	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	179	179	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	178	178	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	177	177	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	176	176	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	175	175	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	174	174	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	173	173	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	172	172	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	171	171	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	170	170	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	169	169	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	168	168	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	167	167	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	166	166	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	165	165	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	164	164	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	163	163	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	162	162	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	161	161	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	160	160	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	159	159	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	158	158	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	157	157	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	156	156	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	155	155	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	154	154	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	153	153	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	152	152	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	151	151	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	150	150	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	149	149	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	148	148	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	147	147	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	146	146	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				
11.1	145	145	gms	W	6-50	P	G-5R	Brown (10R 5/3)	Uncon	N	II	N				

Boring or Well Number 699-42-E9A

23

Logged by MA Channess Print

MA Channer
Sign

Date 12/5/96

Project Savage 1-10-11

100

Reviewed by _____ Print _____
 Pathologic Classification Scheme **FOI**

Sign	Sign
------	------

Date 1/5/96

Drilling Contractor Basin & Range
Driller Robert Perry & Co. Kani

66

Measuring Equipment 2 - tag # 11053, steel tape 6300 - 16

DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASING	DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
	TYPE	NO.	INSTRUMENT	READING							
							calibrated HAN UV ISO-C4 Hg/Lar (100 ppm), span @ 5.64	730		140.75' ± 10"	
			LEL	<det			D/W at 31.05' bgs, D/R @ 127.44', hole apparently heaved in, D/W is probably not very accurate	745			
			HAN	<det			Drilling casing ~ 2.5', bottom at 128.45' Bailed hole, water dec. not seen to be coming in, finish drilling and hole.	815			
							Water sample yesterday was collected at 144' instead of 149'. The hole was only 145' deep according to driller.	900			142.2' Only 3' of casing was put off yesterday. actual casing is 142.2' driller slunker, which makes bottom of casing @ 135.5'
							Bailed hole, D/R is soft but @ ~ 112.7' bgs, D/W at 48.9' bgs	1000			
							SANDY mud - 20% wk, 80% mud. Some clay.				Used polyEM grease on tools
							No run in HCL, fr. mica. Moist color - 101R 5/4	1045			Start split spoon drilling
							Yellowish brown. Full description - thin sample later	1055			Taking core out 142.7' - 145.5'
							mud - 10% wk, 90% mud. Some clay. No run	1115			Start split spoon drilling
							in HCL fr. mica. Moist color - 101R 5/4 yellowish	1120			Taking core out 145.5' - 147.5'
							(brown) Both samples from chert sample, vein	1145			Chamberlain Goodwin & Son
							(brown) Full description of interval will come from microanalysis. description				Frederickson Drill, clearing spl.

W = wet, M = moist, D = dry

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG

Boring or Well Number 149-42-FSA
Location Savage Island

Depth 148.3'-160' Sheet 2 of 3
Project Savage Island

Logged by MA Chambers
Print
Reviewed by _____
Print

MA Chambers
Sign
Date
Date
Rev No 1,0

Drilling Contractor Razin + Range

Driller Robert Perry + Les Kunkle

Rig/Method cable tool (EZZU)/hard tool + split tube

Lithologic Classification Scheme Folk

Measuring Equipment steel tape 149-42-FSA

Drilling Comments
(Casing Rate, Down Time, Blows Counts, Water Level, Drill Fluid, ETC.)

DEPTH	SAMPLES	CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL ETC.)	TIME	H ₂ O ADDED	CASING	
		NO.	INSTRUMENT	READING						
147.5'	1				148.0	SANDY mud - 20% mud, 80% mud, some clay.			142.2'	Hard to get sampler off hole.
148.0'	1				148.0	No rxn in HCL. Moist color - pinkish (yellowish brown). Compacted, coherent, hole had sloughed in some sand, mud, most of that ran out of split tube; sampled under 125C from 144.5 on seems to be unsaturated or at least not fully saturated. Under 125C, mud not dripping w/ HCL. Sampled from 144.5 to 148.0. Similar to above. No rxn in HCL. 148.0				135 blows/10" - 148.0 to top
148.5'	1				148.5	Similar to above. No rxn in HCL. 148.5				Clearing out hole w/ core barrel + bailer.
149.0'	1				149.0	Similar to above. No rxn in HCL. 149.0				Putting jaw back on.
149.5'	1				149.5	Similar to above. No rxn in HCL. 149.5				
150.0'	1				150.0	Similar to above. No rxn in HCL. 150.0				148.2' - 149.5'
150.5'	1				150.5	Similar to above. No rxn in HCL. 150.5				
151.0'	1				151.0	Similar to above. No rxn in HCL. 151.0				100% sampler - 1.7' w/ 100% flow.
151.5'	1				151.5	Similar to above. No rxn in HCL. 151.5				149.5' - 151.2'
152.0'	1				152.0	Similar to above. No rxn in HCL. 152.0				Drilling w/ hard tool.
152.5'	1				152.5	Similar to above. No rxn in HCL. 152.5				Sampled 155' w/ split tube.
153.0'	1				153.0	Similar to above. No rxn in HCL. 153.0				
153.5'	1				153.5	Similar to above. No rxn in HCL. 153.5				
154.0'	1				154.0	Similar to above. No rxn in HCL. 154.0				
154.5'	1				154.5	Similar to above. No rxn in HCL. 154.5				
155.0'	1				155.0	Similar to above. No rxn in HCL. 155.0				
155.5'	1				155.5	Similar to above. No rxn in HCL. 155.5				
156.0'	1				156.0	Similar to above. No rxn in HCL. 156.0				
156.5'	1				156.5	Similar to above. No rxn in HCL. 156.5				
157.0'	1				157.0	Similar to above. No rxn in HCL. 157.0				
157.5'	1				157.5	Similar to above. No rxn in HCL. 157.5				
158.0'	1				158.0	Similar to above. No rxn in HCL. 158.0				
158.5'	1				158.5	Similar to above. No rxn in HCL. 158.5				
159.0'	1				159.0	Similar to above. No rxn in HCL. 159.0				
159.5'	1				159.5	Similar to above. No rxn in HCL. 159.5				
160.0'	1				160.0	Similar to above. No rxn in HCL. 160.0				

W = wet, M = moist, D = dry

Depth 140' - 180'

Project Carrie Island

Sign

3

Rev No 1

1

3

ETC.¹

165-1-5

University

1. 2. 3. 4. 5. 6. 7. 8. 9. 10. 11. 12. 13. 14. 15. 16. 17. 18. 19. 20. 21. 22. 23. 24. 25. 26. 27. 28. 29. 30. 31. 32. 33. 34. 35. 36. 37. 38. 39. 40. 41. 42. 43. 44. 45. 46. 47. 48. 49. 50. 51. 52. 53. 54. 55. 56. 57. 58. 59. 60. 61. 62. 63. 64. 65. 66. 67. 68. 69. 70. 71. 72. 73. 74. 75. 76. 77. 78. 79. 80. 81. 82. 83. 84. 85. 86. 87. 88. 89. 90. 91. 92. 93. 94. 95. 96. 97. 98. 99. 100. 101. 102. 103. 104. 105. 106. 107. 108. 109. 110. 111. 112. 113. 114. 115. 116. 117. 118. 119. 120. 121. 122. 123. 124. 125. 126. 127. 128. 129. 130. 131. 132. 133. 134. 135. 136. 137. 138. 139. 140. 141. 142. 143. 144. 145. 146. 147. 148. 149. 150. 151. 152. 153. 154. 155. 156. 157. 158. 159. 160. 161. 162. 163. 164. 165. 166. 167. 168. 169. 170. 171. 172. 173. 174. 175. 176. 177. 178. 179. 180. 181. 182. 183. 184. 185. 186. 187. 188. 189. 190. 191. 192. 193. 194. 195. 196. 197. 198. 199. 200. 201. 202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218. 219. 220. 221. 222. 223. 224. 225. 226. 227. 228. 229. 230. 231. 232. 233. 234. 235. 236. 237. 238. 239. 240. 241. 242. 243. 244. 245. 246. 247. 248. 249. 250. 251. 252. 253. 254. 255. 256. 257. 258. 259. 260. 261. 262. 263. 264. 265. 266. 267. 268. 269. 270. 271. 272. 273. 274. 275. 276. 277. 278. 279. 280. 281. 282. 283. 284. 285. 286. 287. 288. 289. 290. 291. 292. 293. 294. 295. 296. 297. 298. 299. 300. 301. 302. 303. 304. 305. 306. 307. 308. 309. 310. 311. 312. 313. 314. 315. 316. 317. 318. 319. 320. 321. 322. 323. 324. 325. 326. 327. 328. 329. 330. 331. 332. 333. 334. 335. 336. 337. 338. 339. 340. 341. 342. 343. 344. 345. 346. 347. 348. 349. 350. 351. 352. 353. 354. 355. 356. 357. 358. 359. 360. 361. 362. 363. 364. 365. 366. 367. 368. 369. 370. 371. 372. 373. 374. 375. 376. 377. 378. 379. 380. 381. 382. 383. 384. 385. 386. 387. 388. 389. 390. 391. 392. 393. 394. 395. 396. 397. 398. 399. 400. 401. 402. 403. 404. 405. 406. 407. 408. 409. 410. 411. 412. 413. 414. 415. 416. 417. 418. 419. 420. 421. 422. 423. 424. 425. 426. 427. 428. 429. 430. 431. 432. 433. 434. 435. 436. 437. 438. 439. 440. 441. 442. 443. 444. 445. 446. 447. 448. 449. 450. 451. 452. 453. 454. 455. 456. 457. 458. 459. 460. 461. 462. 463. 464. 465. 466. 467. 468. 469. 470. 471. 472. 473. 474. 475. 476. 477. 478. 479. 480. 481. 482. 483. 484. 485. 486. 487. 488. 489. 490. 491. 492. 493. 494. 495. 496. 497. 498. 499. 500. 501. 502. 503. 504. 505. 506. 507. 508. 509. 510. 511. 512. 513. 514. 515. 516. 517. 518. 519. 520. 521. 522. 523. 524. 525. 526. 527. 528. 529. 530. 531. 532. 533. 534. 535. 536. 537. 538. 539. 540. 541. 542. 543. 544. 545. 546. 547. 548. 549. 550. 551. 552. 553. 554. 555. 556. 557. 558. 559. 560. 561. 562. 563. 564. 565. 566. 567. 568. 569. 570. 571. 572. 573. 574. 575. 576. 577. 578. 579. 580. 581. 582. 583. 584. 585. 586. 587. 588. 589. 590. 591. 592. 593. 594. 595. 596. 597. 598. 599. 600. 601. 602. 603. 604. 605. 606. 607. 608. 609. 610. 611. 612. 613. 614. 615. 616. 617. 618. 619. 620. 621. 622. 623. 624. 625. 626. 627. 628. 629. 630. 631. 632. 633. 634. 635. 636. 637. 638. 639. 640. 641. 642. 643. 644. 645. 646. 647. 648. 649. 650. 651. 652. 653. 654. 655. 656. 657. 658. 659. 660. 661. 662. 663. 664. 665. 666. 667. 668. 669. 670. 671. 672. 673. 674. 675. 676. 677. 678. 679. 680. 681. 682. 683. 684. 685. 686. 687. 688. 689. 690. 691. 692. 693. 694. 695. 696. 697. 698. 699. 700. 701. 702. 703. 704. 705. 706. 707. 708. 709. 710. 711. 712. 713. 714. 715. 716. 717. 718. 719. 720. 721. 722. 723. 724. 725. 726. 727. 728. 729. 730. 731. 732. 733. 734. 735. 736. 737. 738. 739. 740. 741. 742. 743. 744. 745. 746. 747. 748. 749. 750. 751. 752. 753. 754. 755. 756. 757. 758. 759. 760. 761. 762. 763. 764. 765. 766. 767. 768. 769. 770. 771. 772. 773. 774. 775. 776. 777. 778. 779. 780. 781. 782. 783. 784. 785. 786. 787. 788. 789. 790. 791. 792. 793. 794. 795. 796. 797. 798. 799. 800. 801. 802. 803. 804. 805. 806. 807. 808. 809. 810. 811. 812. 813. 814. 815. 816. 817. 818. 819. 820. 821. 822. 823. 824. 825. 826. 827. 828. 829. 830. 831. 832. 833. 834. 835. 836. 837. 838. 839. 840. 84

June 4

...f. f.

27-11-16

100%

1

1000

10

1.

1

1

1

—

Proc.

A-1800-003 (01/90)

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-42-69A</u>				Depth <u>185' - 194.3'</u> Sheet <u>1</u> of <u>3</u>		Project <u>Basin & Range</u>			
Location <u>SS Tool</u>				Date <u>12/10/90</u>		Drilling Contractor <u>Robert Perry</u>			
Print				Sign		Driller <u>Robert Perry</u>			
Lithologic Classification Scheme <u>Folk</u>				Date		Rig/Method <u>Cable Tool Bearings Hard Tool</u>			
Measuring Equipment <u>Steel Tape</u>				Procedure <u>DO-1</u>		Rev No <u>1</u>			
L300-16									
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)	
TYPE	NO.	INSTRUMENT	READING					CASING	
					D/Water = 34.47 - 4.17 = 30.30	0750		189.6	Driller + Seal arrive on site
					D/Bottom = 178.6	0810			
					Bottom of 8" @ 185.5				
					($\approx$ 7' of plug)				
					Span set @ 5.68	0825			Calibrated HNU
					Check hole w/ HNU, LEL/O ₂	0830			
					D/Bottom = 186.0 + 3.0 - 4.1 = 184.9	0835			Drilling w/ Hard Tool
					($\approx$ 0.5 ft of plug)	0850			
					Will go ahead and rig-up for split-
spoon sampling				
					D/Bottom same as previous - not sure if
this is real or if the tape is not finding
the hole made by the split-tube	0925			Reamed split-spoon
						0930			
						0935			When driller lowered the
split-tube to repeat sampling
he found that the hole has
healed. Will have to change
tools and drill out A-1800-003 (05/90)

DAILY BOREHOLE LOG

Boring or Well Number 69-42-E9A Depth 2 of 3
 Location U of Ringold Project Savage Island
 Logged by SS Tool Print SS Tool Date 12/10/90
 Reviewed by Folk Print Folk Date 12/10/90
 Lithologic Classification Scheme Folk Procedure D-1 Rev No 1
 Measuring Equipment Steel Tape L300-16
 Drilling Contractor Basin & Range
 Driller Robert Perry
 Rig/Method BE22W Cable Tool

Measuring Equipment <u>Steel Tape</u> <u>L200-16</u>										LITHOLOGIC CLASSIFICATION	
DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDEDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)	
	TYPE	NO.	INSTRUMENT	READING						CASING	
185-187	Lith	1	HNU	0 ppm		185	SLIGHTLY MUDDY SAND
- 10 (assume 185-187')			189.6	Drilling w/ Hard Tool
187'	Lith	2				186	SAND 90% recovery, 60 blows to advance
1.5 ft. Sample in leg line - lithology
samples taken from shoe. Upper half of tube
is med-coarse sand - lower half is a finer
grained sand that may be slightly silty - appears
to coarsen again at the very bottom of the tube.	0930
1020			Cannot maintain open hole -
will continue to drill ahead and
let casing follow.
			HNU	0 ppm		187	Lith sample: 90% sand, 10% silt, 0% clay
59% CS, 60% MS, 20% FS, 59% VS, 10% SILT
Mod- well sorted. 5% basalt, mica, mica;
95% sand, mica, A-SR	1050		199.41
199.01	Will have trouble casing. Check
borehole.
Adding 7.511' of 8" casing
							Wet color: 10YR 1/2 (Jaw' or similar), No
reaction to 10% HCL. Homogeneous structure,
uncemented, moderately consolidated	1150			Drilling w/ Hard Tool
190'	Lith	2	HNU	0 ppm		190'	SLIGHTLY MUDDY SAND (49% gravel, 26% sand,
10% mud) 18% MP, 22% FP, 12% VP, 8% CS, 65% MS,
17% FS, 60% VS, 10% mud. Mod- well sorted,
(Gravel) - 30% basalt fragments, 70% fine silt,
+ Si-rich rock fragments, Angular, (Gravel) -
- 5% mica, 5% Fe-stained mica, 1% basalt
90% fine silt, 10% sand, A-SR, Wet color: 10YR 1/2 (Jaw' or similar), No reaction to 10% HCL. Homogeneous to previous	1245			Sample w/ Dart Bailer (190')
			PH	6.5							

DAILY BOREHOLE LOG

Boring or Well Number 699-42-69A

Location N of Ringold

Sheet 3 of 3

Project

Logged by SS Teel

Print

Checked by

Print

Lithologic Classification Scheme Folk

Procedure DO-1

Rev No. 1

Measuring Equipment Steel Tape

L300-16

Drilling Contractor Basin & Range

Driller Robert Perry

Rig Method BE22W Cable Tool

DEPTH

SAMPLES

CONTAMINATION

MOISTURE

GRAPHIC LOG

LITHOLOGIC DESCRIPTION

TIME

H₂O ADDED

CASING

DRILLING COMMENTS

195-197

Split Tube

1

197-199

Split Tube

1

200'

lith

2

205'

lith

2

H₂O

2

2

195-197

197-199

200'

205'

H₂O

Driller noticed a clump of clay and coarse pebble when he brought the bit out of the hole to bail. Bailed material is still same as previous however. Depth ≈ 194'

"

(195-197')

SANDY MUD (90% sand, 70% mud)

Difficult to tell proportions & mineralogy

Wet color: 10YR 6/2 (light brownish gray)

No reaction to 10% HCL. Mod - strongly consol.

Homogeneous. No visible structure. U. well sorted.

SANDY MUD (197-199') same as above

GRAVELLY SANDY MUD (10% gravel, 25% sand, 65% mud) same as above except 10% gravel - up to CP size, well rounded

SLIGHTLY GRAVELLY MUD (5% gravel, 15% sand, 80% mud) similar to above - hard to tell exact proportions - varying

to have more clay and less gravel & sand than prev

1345

1500

1530

1550

1600

1620

1630

199.01

197.01

Driving casing - will drive to bottom of hole and then clean-out and get a split- spoon, casing is driving easily.

Split spoon 195-197'

41 blows / 18" ; 80% recovery

Split spoon 197-199'

100% recovery, 143 blows / 18"

Drilling w/ Hard Tool

200' sample - collected by scraping mud off of bit

205' sample - collected by scraping mud off bit

Collected H₂O Samples

have ≈ 10' open hole A-1800-003 (01/90)

C of C # 121090 SI

W = wet, M = moist, D = dry

205'

to have more clay and less gravel & sand than
prev

have $\approx 10'$ open hole A-1800-003 (0190)
CofC # 121090SI

DAILY BOREHOLE LOG

Boring or Well Number 699-42-F9A

Location Norfolk Ringold

Project Savage Island

Sheet 2 of 3

Logged by Tyler Moore
Print

Tyler Moore
Sign

Date 12/1/90

Checked by Folk
Print

Sign

Date

Lithologic Classification Scheme Folk [Cly ASTM]

Procedure DO-1; DO-5

Rev No. 10

Measuring Equipment Steel tape L300-16

Drilling Contractor Bain and Perry

Driller Robert Perry

Rig/Method Electric BT 2200 / hand and auger

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-------|---------|-----|---------------|---------|----------|-------------|---|------|------------------------|--|--------------|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | CASING | |
| 220" | Lith | 2 | HNU | Approx | | | 215' Cont. Sands Subang; wet color
10PR 6/3 pale brown; No rxn in HCL
mod (argol (hole staying open) similar
to previous; on present clip form
bit 4' are about streaks and nodules
of Fe iron staining of org. origin
Some have chlorite-like green mottled
MUD 12% Gravel, 9% Sand, 90% Mud 1115
(predom cly iron silt content) 12% Mip
3 1/2% MS, 30% FS, 30% VFS, 20% MUD;
sl soluble in water low dry strength;
low - med toughness (incr in Silt);
10PR 6/2 pale brown; dec in Fe str
no rxn in HCL more silt "clayey" texture
than previous
MUD 12% Gravel 5% Sand 74% silt (predom
cly) 12% CP, 5% FS, 94% Mud (predom
cly) Mud dry strength; Mud toughness
few Fe str "pockets" 10PR 6/3 iron stain
No rxn in HCL mostly cly less silt than
before rec subord pebble in clay | | | | Sample cont. |
| 225" | Lith | 2 | HNU | Approx | | | | | | | Sample |

W = wet, M = moist, D = dry

A-1800-003 (01/90)

DAILY BOREHOLE LOG

Boring or Well Number

699-42-F9A

Sheet

3

of

3

Location

Apakah at Rengh

Project

Savage Island

Logged by

Tyler Gilmore

Print

Checked by

Tyler Gilmore

Print

Lithologic Classification Scheme

Folk

Procedure

DD-1

Rev No.

1

Measuring Equipment

Silco Tape

L 300 - 16

Drilling Contractor

Basin and Range

Driller

Ross + Perry

Rig/Method

BE 22W 'electric / Hand tool

| DEPTH | SAMPLES | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O
ADDED | CASING | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) |
|--------|---------|---------------|-----|----------|-------------|--|------|---------------------------|--------|---|
| | | TYPE | NO. | | | | | | | |
| 229' | Lith 2 | | | | | MUD 50% Sand 99% Mud;
50% FS, 95% Mud, good cly.
High Strength High toughness "Fat cly"
about Fe sil and mottling, Tr blk
"Coal" organic seen; N5 Gray w/
brn mottling, Sand predom bslt;
angular; (No rxn to HCL, Mod consol;
bslt grns may indicate we are close
to bslt top | 1300 | | | Sample |
| 229.5' | Lith 2 | | | | | MUDDY SAND 70% Sand 30% Mud;
15% CS, 30% MS, 20% FS, 5% VES, 30%
Mud (slt cly) Mod sand wet color
10% R 2% brn Sand to 40' BSLT
60' Full of mud (2-3) 35% Tons
is even less from mud, silice
sand no rxn to HCL no consol | 1340 | | | Hit Sand @ 229.5' |
| 230' | Water 2 | | | | | | | | | Water sample Dec 12/190 |
| | | | | | | Need to Build Bit up Speed rest
of day during 12/190 | 1340 | | | |
| | | | | | | | 1400 | | | End of Day |

W = wet, M = moist, D = dry

A-1800-003 (01/90)

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-42-594</u>				Sheet <u>1</u> of <u>2</u>		Project _____			
Logged by <u>SS Teel</u>		Print _____		Date <u>12/12/90</u>		Drilling Contractor <u>Basin & Range</u>			
Checked by _____		Print _____		Date _____		Driller <u>Robert Perry / Lee Kuntze</u>			
Lithologic Classification Scheme <u>Folk</u>				Procedure <u>DD-1</u>		Rev No. <u>1</u>		Rig/Method <u>EE 200W Coda 7231</u>	
Measuring Equipment <u>Star 1 Tape</u>				<u>L300-16</u>		<u>E-tape 11034</u>			
DEPTH	SAMPLES		CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
	TYPE	NO.							
							0730		Driller on site - preparing to drill; replacing bit
						D/water = 31.0 - 4.10 = 26.9 (E-tape)	0750		Driller was able to "work" bit down to 230"
						D/Bottom = 230.0 + 3.0 - 4.1 = 228.9 (very soft)			Drilling w/ Hard Tool
						Bottom of 8" casing @ 194.91	0807		Calibrated HNU / LEL - Q ₂
						Span set @ 5.43.	0810		check borehole. HNU
						(230'-231')	0815		batter is low.
						SLIGHTLY GRAVELY SLIGHTLY MUDDY SAND	0855		In much harder material now - part of the old 14th bit
						5% gravel, 15% clay/silt chips, 80% sand.	0920		was bent. Depth is 231' 232'
						Silt/clay chunks are probably carry-down from above. 3% FP, 2% VFP, 80% VFS, 30% FS.			Driller thinks now in basalt.
						20% MS, 5% FS, 5% VFS, (Gravel) - 4% basalt, 1% gfriter, (Sand) 35% basalt,	0930		Bailing drew water level down to 60 ft - re-bailing at
						50% gfr + quartz, 4% silt-rich, 14% mudst., 19% mud.	0950		rate is 1 ft/min.
						Sands are A-R. Wet color: 10YR 4/2 (dark grayish brown).	1000		Will continue drilling and cleaning out the hole in order to get a good basalt-chip sample for dating.

W = wet, M = moist, D = dry

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-42-E9A
Location North of Ringold

Sheet 1 of 1
Project Source Island

Logged by MA Chaurney
Print

MA Chaurney Date 12/19/90
Sign

Reviewed by _____
Print

Measuring Equipment PNL 1300-16 Steel Tape Date _____
Sign

Procedure DO-1, DO-5 Rev No. 1, 2

Drilling Contractor Basin and Range

Driller Robert Perry, Les Kunkel

Rig/Equipment BE 220 / Cabletool Rig

Time	Casing/Screen				Annular Fill				Over-lap	Comments
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup	Add-on	Depth
730										No work yesterday, blizzard
										On site, pulling water tank out, trying to
										throw it out "O" rings delivered
										yesterday are 2 diff. sizes. Have to
										go to Paris & pick some more up. Les
										is trying to warm up rig enough to
										start it.
										Back from Paris w/ more "O" rings. Rig
										is started + warm.
										One piece of screen is plugged on both ends,
										the other plugged on female end so the male
										lifting bail we have will not work. Trying
										to make another one.
										RB = 231.8' bags
										Based on rat & log, top of sand is @ 224.5'
										will use 20-40 mesh sand to three, 100-100
										mesh sand to 221.5'
										The 2 piles don't fit together, the threads
										are different types. Took these 2 pieces
										back out, talked to Tam Nemer +
										manufacturer, got new casing will be
										sent out.
										Left site after hearing John A-1800-004 (05:00)
										rip

1245 Fiberglass 10 slot 3" 10' 85' } removed
Casing 3' 20' 04' }

1530

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-42-E9H
Location North of Rimold

Project Sunape Island Sheet 2 of 2

Logged by Tyler Gilmore Date 1/2/91

Reviewed by [Signature] Sign _____ Date _____

Measuring Equipment Pull L3000-16 Steel 14.50 Sign _____ Date _____

Procedure D-1 Rev No. 11

Drilling Contractor Bazin and Porey
Driller Robert Porey
Rig/Equipment Cable Tool

Time	Casing/Screen				Annular Fill					Over-lap	Comments		
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup	Add-on			Depth	
1505	Fiberglass	3"	~234'	1.8'	232'						228'	N/A	bottom of 8" 135.0'
						CSS 10-30	1 bag (100 lb)				226.3'		Need sand to 217'-218'
1535						"	1 bag				226.0'		
						"	2 bags				223.2'		
						"	1 bag				221.5'		
						"	2 bags				219.0'		
						CSS 40-140	1 bag				217.3'		Some sand may settle overnight
1630													End of Day
													Total (8) 100 lb bags 20-40 Sand
													(1) 100 lb bag 40-140 Sand
										</			

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-42-E9A
Location North of Ringold

Project Savage Island Sheet 1 of 1

Logged by Tyler Gilmore Print Signature Date 1/3/91

Drilling Contractor Basin and Range
 Driller Robert Perry / Les Kunkle
 Rig/Equipment Cristal BE 32W

[illegible]

DAILY BOREHOLE/WELL COMPLETION LOG				Boring or Well Number <u>699-42-EG A</u>		Sheet <u>1</u> of <u>1</u>	
				Location <u>N. of Ringold</u>		Project <u>Savage Island</u>	
Logged by <u>SS Teel</u>		Print		Date <u>1-4-91</u>		Drilling Contractor <u>Basin + Range</u>	
Reviewed by		Print		Date		Driller <u>Robert Perry / Les Kunkle</u>	
Measuring Equipment <u>Steel Tape</u>		Procedure <u>DD-1</u>		Rev No. <u>1</u>		Rig/Equipment <u>Cable Tool / BG-22W</u>	

Time	Casing/Screen				Annular Fill				Over-lap	Comments		
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup			Add-on	Depth
0800	Carbon Steel	8"	199.0'	4'	195.0'							Driller-fetching water (fish hatchery)
0922						8-20
crumbles	(50# bag)					Driller back on site
1000						"	1/2					Added 1 batch of slurry (95 gal / 1/2 bag)
1010						"	2.5					" (95 gal / 2.5 bags)
1020						"	2.5					" (95 gal / 2.5 bags)
						"	2.5					"
						"	2					Mud level is $\approx$ 3' above ground.
												Circulating mud in hole - mud wt
												is 9.5-9.6 but is not fully
												hydrated. The pump will not pump
												mud much thicker than this.
												wt = 9.4
1120												wt = 9.1 (appears to be fully hydrated)
1145												Removing tremie pipe
1215												Pulling casing. (Dead-pulling)
1430												Removed remaining 8" casing
1445												Pumped remaining slurry down hole
												($\approx$ 40 gal)
												Checked level of mud "mirror" - appears to
												be $\approx$ 50' down. Added water to hole
												Welded plate on borehole.
1450												Left site. Ready to start pulling 10" casing
1500												$\approx$ 50'

DAILY BOREHOLEWELL COMPLETION LOG

Boring or Well Number 699-42-69A
Location N. of Ringold

Sheet 1 of 1
Project Savage Island

Logged by SS Teel Date 1-7-91
Print Sign
Reviewed by _____ Date _____
Print Sign
Measuring Equipment Steel Tape # 1300-16 Procedure DO-1 Rev No. 1

Drilling Contractor Basin + Range
Driller Robert Perry / Les Kunkle
Rig/Equipment Cable Tool / BE22W

Time	Casing/Screen				Annular Fill				Over-lap	Comments
	Type	Diameter	Length	Stickup	Depth	Type	Quantity	Stickup		
1130			142.2	(not incl. puller head)		Bentonite Slurry	—			Driller on site - setting up jacks
1320										Begin pulling casing. Jacks are not working very well because the oil level is low and because it is cold.
1340										Robert goes to town for oil. Continuing pulling w/ jacks.
1350										Have pulled 8" so far
1450										Robert arrives - fill hydraulic res.
										9" w still ≈ 26 - very difficult to tell where bottom is - appears to be thicker starting at ≈ 60', Have pulled ≈ 2' so far.
1500										Pulling w/ Jacks
1505										Hydraulic hose broke - will be shut down for rest of day. No oil contacted the borehole. Spilled oil was scooped up and placed in a drum.
1523										Have re-arranged the hoses so that the jacks can continue to run - Robert leaves for town to get another hose.
1615										Robert on site - removed filter - pulling much better
1645			132.75	6.9	125.9					Exposed 132.75' well

End of Day

DAILY BOREHOLE/WELL COMPLETION LOG				Boring or Well Number <u>1099-42-E9A</u>				Sheet <u>1</u> of <u>1</u>					
				Location <u>N of Ringold</u>				Project <u>Savage Island</u>					
Logged by <u>MA Chamness</u> Print
Reviewed by _____ Sign
Measuring Equipment <u>Steel tape 1200-16</u> Procedure <u>DO-1, DO-5</u> Date <u>1/8/91</u> Rev No. <u>1, 0</u>				Drilling Contractor <u>Basin + Range</u>
Driller <u>Robert Perry + Les Kunkle</u>
Rig/Equipment <u>cable tool BE22W + hyd. jacks</u>									
Time	Casing/Screen			Annular Fill			Over-lap	Comments					
	Type	Diam-eter	Length	Stickup	Depth	Type			Quan-tity	Stickup	Add-on	Depth	
7:20	CS casing	10"	142.2'	7.1'	125.1'	Bentonite slurry							On site, working up rig, preparing to cut off casing
8:00													Ran out of O ₂ + acetylene, will have to get more before finishing cutting casing
10:50													Back w/ O ₂ + acetylene, setting up
11:20													Safety man, Ed Endace (RED) came by, safety and
11:40													NB difficult get stiff at ~103' bgs.
11:50													HNSA < det. LEL ok
12:55		10"	115.75'	6.9'	108.9'	Bentonite slurry							Pulled back to expose 115.75' weld
													Mixed bentonite slurry, 2 1/2 50 lb bags
													bentonite crumbles mixed in ~90 gal. H ₂ O,
													reads 9.3 on mud balance, Robert says
													can't pump it much thicker. Put a 2nd
													batch of ~90 gal using same quantities.
1:20													Pulling back casing to expose 96.75' weld
1:50		10"	91.75'	6.9'	89.9'								Mixed another batch, 2 1/2 bags in ~90 gal @ 9.3 weight
													76.85' weld exposed
10:40		10"	76.85'	7'	69.85'								Will pull a little more to let good push
													out as much as possible over night
10:55													Pulled ~4'-5', stopped for day.

DAILY BOREHOLE/WELL COMPLETION LOG										Boring or Well Number <u>609-42-EQA</u>		Sheet <u>1</u> of <u>2</u>	
										Location <u>N of Ringold</u>		Project <u>Savage Island</u>	
Logged by <u>MA Chamness</u>		Print		MA Chamness		Date <u>1/5/51</u>		Drilling Contractor <u>Bein & Range</u>					
Reviewed by		Print				Date		Driller <u>Robert Perry + Les Kunkle</u>					
Measuring Equipment <u>steel tape</u>		<u>L300-16</u>		Procedure <u>NO-1</u>		Rev No. <u>1</u>		Rig/Equipment <u>cable tool RE 22w/hydr. jacks</u>					
Time	Casing/Screen			Annular Fill					Over-lap	Comments			
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup			Add-on	Depth	
7:20													
7:45	C-steel	10"	76.85										
9:05			57.15	6.2'	50.85	Bentomite slurry					150'		
						Silica sand	1 bag				52.7'		
						10-20 mesh	1 1/2 bag				48.0'		
	Carbon steel	10"	57.15	9.2'	48.0'						48.8'		
10:05							1/2 bag				47.3'		
			52.15	5.5'	46.7'						48.5'		
			52.15	6.4'	45.8'						46.3'		
					44.3'	volcanic pellets	2 1/3 bags	2.4'			44.7'		
			19.3'	5.2'	44.1'								
	Fiberglass	2"		5.2'	230.0'			.5			44.6'		
11:55			49.3'	5.2'	44.1'	Silica sand 10-20 mesh	2 50lb bags				40.3'		
					41.4'						41.7'		
			47.55'	6'	41.55'	Silica sand	1/2 bag				40.4'		
	PVC, 20 slot	2"	10' 5"										
	" screen	"	10'										
	PVC casing		10'										
			10'										

DAILY BOREHOLE/WELL COMPLETION LOG				Boring or Well Number <u>1699-42-EGA</u>		Sheet <u>2</u> of <u>2</u>	
				Location <u>RD of Ringold</u>		Project <u>Savage Island</u>	
Logged by <u>MA Chamness</u> Print <u>MA Chamness</u> Sign Date <u>1/9/91</u>				Drilling Contractor <u>Barin + Range</u>			
Reviewed by _____ Print _____ Sign Date _____				Driller <u>Robert Perry & Les Kunkle</u>			
Measuring Equipment <u>L300-16 steel tape</u> Procedure <u>DD-1</u> Rev No. <u>1</u>				Rig/Equipment <u>Cable tool BF72W/hydr. jacks</u>			

Time	Casing/Screen			Annular Fill				Over-lap	Comments			
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity			Stickup	Add-on	Depth
1240	PVC	2"	Total
45	3.8'	41.6'	Silica sand	2 1/2 bags		2.5	35.6		
					10-20 mesh							
1250	C steel	10"	47.55	7.9'	59.7'	100 lb bag				36.6'		
			47.55	9.2'	38.35'	"	5 bags		"	25.8		
			37.9	10.7'	31.2'	"				28.4		Exposed 37.9' weld
						"	5 bags			16.0		
			28.7'	10.5'	22.2'	"	1 bag		"	18.7	3.5'	Pulled back to expose 28.7' weld
					20.8					16.7		
1300					19.4					16.7		
		10'	23.1	5'	18.1'					17.2		
					17.2'					17.7'		Cut off 5.6' of casing
						Volley pulley 3 1/2 bucket				17.0		Casing pulled up but then large open hole, apparent by some slough came in
						(5 gal)				12.2		
1340			23.1	16.6'	14.5'					12.7		
			23.1	9.5'	13.6'					12.8		
			23.1	9.5'	13.6'	"	1 bucket			12.3		
			19.1'	7.1'	12'					13.1		Cut off 4' of 10", pulled rest of 10" out
1405	C steel	12"	16.1'	3'	12.1'					13.1		+ helped pull 12" up
1420					12.1	"	1 bucket			12.0		Filled open hole w/ bentonite pellets
												will pour cement grout tomorrow
1440												Moving jacks off hole

DAILY BOREHOLEWELL COMPLETION LOG

Logged by SS Teel SS Teel Sign _____ Date 1-10-91
 Reviewed by _____ Sign _____ Date _____
 Measuring Equipment Engineers Tape Procedure DO-1 Rev No. 1

Drilling Contractor	<u>Basin & Range</u>
Driller	<u>Robert Perry / Les Kunkle</u>
Rig/Equipment	<u>BE22w Calk Tool</u>

Time	Casing/Screen				Annular Fill					Over-lap	Comments
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup	Add-on		
0820											Mixing Cement Grout
0820											Adding Cement Grout to borehole
0930											Removed 12" casing, will have to get more water for mixing additional cement - grout level is $\approx 5'$ b.l.s.
											When 12" casing was removed approximately $\frac{1}{2}$ bucket of bentonite pellets were stuck to the bottom inside of the casing.
											Summary of Grout added so far
						<u>Cement Grout</u>					
						Portland Cement	6 bags	(94 lbs ea)			
						8-20 bentonite	2 bags	(50 lbs ea)			
						Water	80 gal				
						Gypsum	1.3 bags	(20 lbs ea)			
1020											Driller returns with water
1030											Mixing and pouring grout
1050											Teamsters arrive w/ pump column pipe. It has not been steam cleaned. They will take it back and return it when cleaned.
											Finished pouring cement grout. Grout level is 0.5' b.l.s. It may settle some into the formation.
1100						Portland Cement	3 bags				
						8-20 Bentonite	$1\frac{2}{3}$ bags				
						Water	40 gal				
						Gypsum	$\frac{1}{2}$ bag				

Project Savage Island Sheet 2 of 2

Date 1-10-91

Date _____

Rev No. 1

A-1800-004 (05/90)

DAILY BOREHOLE LOG

Boring or Well Number 69A-42-E9A Depth 1 Sheet 1 of 2
 Location North of Road Project Soloje Island

Logged by Tyler G. Jones Sign Tyler G. Jones Date 11/12/91
 Reviewed by N/A Sign N/A Date 11/12/91
 Lithologic Classification Scheme N/A Procedure DD-1 Rev No 1
 Measuring Equipment Steel Tape PNT 130-16

Drilling Contractor Basin and Range
 Driller Ross + Perry
 Rig/Method Cable Tool

| DEPTH | SAMPLES | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-------|---------|---------------|------------|----------|-------------|---|------|------------------------|--|--|
| | TYPE | NO. | INSTRUMENT | READING | | | | | CASING | |
| | | | | | | Pump stuck in well - pumping abruptly stopped yesterday. Well flow tried to pull pump out - Pump stuck at ~ 176 ft - Water level in Fiberglass casing at 49' on 11/11/91 on 11/12/91 43.5' Water level inside casing column was 28.0' on 11/12/91 Pump steel tape into pump column to 175.5 ft - To check for backbite inside pump column for a ledge in to try for a "core" sample - backbite at end of tape Will collect sample at pump column - 845 Water in case up lose well | 800 | | | A' meas movements from casing casing stick up = 2.8' |
| | | | | | | Set up sample innermost (acts as set of jaws) to pump column to work pump out of well - pulled new joint of tape the during get at sample | 725 | | | Collected (2) 125ml samples from pump discharge line |
| | | | | | | | 950 | | | |

Depth N/A Sheet 2 of 2

Project

Date 1/24/91

;

Rev No

[illegible]

A-1800-003 (05/90)

Depth N/A Sheet 1 of 1

Project Sulfas Ichni

Date 1/15/91

Date _____

Rev No 1

[illegible]

A-1800-003 (05/90)

DAILY BOREHOLE LOG											
Boring or Well Number 69A-42-E9A			Depth 11 ft		Sheet 1 of 2		Location Navaho P-101d				
Logged by T. J. Dillmore			Date 1/17/91		Drilling Contractor Basins and Range						
Reviewed by			Date		Driller Robert Perry / Dale Jones (WTK)						
Lithologic Classification Scheme N/A			Procedure DO-1		Rig/Method Cable Tool						
Measuring Equipment Steel Tape L320-16			Rev No 1								
DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)	
	TYPE	NO.	INSTRUMENT	READING						CASING	
							Technical Forum is having	1800			All measurements below
							Consensus was to run 1" pipe in well				Casing (unless noted)
							to get sand out and circulate down				
							water 2) Run TV camera in well				
							3) Stop and decide next action				
							-Basins and Range will be released after				
							today				
							- Measured in 2" well to determine	1820			
							status D/B 43.4 ft D/W 86.3 ft				
							took water sample - water looks dirty				
							It has but did not look like gray				
							whit bentonite. Well looks in good shape				
							D/B in 3" well is 145.7 ft. Sand	1850			
							Came in ~ 16 ft since yesterday. The				
							steel has been found in bentonite				
							W/L 11'				
							Set up to run 1" pipe in well	1850			
							2 1/2" 2 1/2" (Ave 2 1/2")				
							Use (F) 2 1/2" + (1) 1 1/2" for total of 160'				

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG									
Boring or Well Number <u>69-43-E9A</u>				Depth <u>NA</u>		Sheet <u>2</u> of <u>2</u>		Project <u>Savage Island</u>	
Location <u>N. Road</u>				Drilling Contractor <u>W. J. J. J.</u>		Driller <u>W. J. J. J.</u>		Rig/Method <u>W. J. J. J.</u>	
Logged by <u>T. J. J. J.</u>				Date <u>1/1/1</u>		Sign <u>T. J. J. J.</u>			
Reviewed by <u>T. J. J. J.</u>				Date <u>1/1/1</u>		Sign <u>T. J. J. J.</u>			
Lithologic Classification Scheme <u>N/A</u>				Procedure <u>DO-1</u>		Rev No <u>1</u>			
Measuring Equipment <u>Elapre - Steel tape L300.10</u>									
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)	
TYPE	NO.	INSTRUMENT	READING					CASING	
					Circulate water out of hole; first batch was dirty, looked like some bentonite was in the water - Took break in circulation - W/L dropped to 22' plug of sand at pump broke loose - Circulating entire well now	400			Across Street showed up w/ TV camera
					Filled the water tank w/ again (1000 gal) and ran water through well; cleaned up more or sand - water clean enough for TV camera	440			Pull pipe
					Ran TV camera thru water - level was 24ft. A break in the casing was observed at 152.25ft. bentonite and sand went were entering the casing at this point (see video log)				
						1540			End Day

DAILY BOREHOLE LOG

Boring or Well Number 699-42-E9A
 Location North of Ringold

Sheet 1 of 2
 Project Savage Island

Logged by John P. McDonald Sign [Signature] Date 7/17/92
 Checked by [Signature] Sign [Signature] Date

Drilling Contractor N/A
 Driller N/A
 Rig/Method N/A

Lithologic Classification Scheme Folk Procedure QO-1 Rev No. 1

Measuring Equipment N/A

| DEPTH | SAMPLES | CONTAMINATION | | MONI-
TURE | GRAPHIC
LOG | LITHOLOGIC DESCRIPTION
PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O
ADDED | CATING | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) |
|---------|---------|---------------|------------|---------------|----------------|---|------|---------------------------|--------|---|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | |
| 197' ST | | | | | | Re-description of core 197' 199'
200' and 205' samples for
percentage breakdown. Samples
originally collected on 12/10/90. | | | | |
| | | | | | | Muddy SAND (70% sand, 30% mud) | | | | |
| | | | | | | 10% fs, 60% vfs, 30% mud, well sorted. | | | | |
| | | | | | | Sand: 58 mafic; 70% qtz, 25%
other, 3% mica, 2% basalt. Dry | | | | |
| | | | | | | color: lt. gray (10YR7/2). Some Fe
staining. | | | | |
| 199' ST | | | | | | MUD (10% sand, 90% mud) 10% vfs,
90% mud, v. well sorted. Unable to
distinguish sand well enough to
determine composition. Dry | | | | |
| | | | | | | color: white (10YR8/2). | | | | |
| 200' HT | | | | | | Gravelly Sandy MUD (15% gravel,
20% sand, 65% mud) 58% sp,
48% mp, 48% fs, 23% vfs, 58% fs, 15%
vfs, 65% mud, mod. sorted. | | | | |

W = wet, M = moist, D = dry

Boring or Well Number	699-42-89A
Location	North of Ringold

Project Savage IS/and Sheet 2 of 2

Signature: [Signature] Date: 7/17/92

Sign

Date

Procedure 00-1 Rev No. 1

[illegible]

W = wet, M = moist, D = dry

A-1800-003 (01/90)

WELL DEVELOPMENT LOG

Well Number 99-42-E9A
 Location Savage Island
 Procedure PNL-MA-567, GC-7, Rev. 0

Start Date/Time 1-23-91 1022
 End Date/Time 1-23-91 1500
 Page 1 of 1

Well Depth 41.8 ^{TOC} Pump Depth (Intake) 39' Initial Water Level _____

Date	Time	Flow Rate	Turbidity	Person Meas.	Rec.	Comments
1-23	1023	5 ⁺ gpm	NA			
"	1050	5gpm	100%+			very dirty
Not in range of meter on 100
"	1100	-	-			Air cylinder changed off 5 min
"	1115	5gpm	Not Readable			Very dirty yet
Set of samples taken "0"
"	1150	4.6gpm				
"	1245	4.6gpm	Not Readable			Some Rin being pumped - recovery at about
the pumping rate (still very dirty)
"	1358		"			water level ~29' TOC
"	1400	5gpm	"			sample set taken "1"
"	1500	-	-			Terminated for today

Note: Unless otherwise noted,
 the following units are assumed:
 Flow rate - gpm
 Turbidity - NTU
 Water Level - ft

Equipment:
 Make: Hydrastor
 Model: H5C01
 Serial #: _____

WELL DEVELOPMENT LOG

Well Number 699-42-E9A
 Location Ringold Area (Sav. Island)
 Procedure PNL-MA-567, GC-7, Rev. 0

Start Date/Time 1-24-91 0930
 End Date/Time 1-24-91 1515
 Page 1 of 1

Well Depth 41.8 Pump Depth (Intake) 39 Initial Water Level 28.01

Date	Time	Flow Rate	Turbidity	Person Meas.	Rec.	Comments
1-24	0930	5gpm	N/A			Start pumping (water 28' TOC)
"	1000	5gpm				Start Pump actuator froze up
"	1015	5gpm	Not (4:1) Readable			Restart 4:1 dilution still too turbid
"	1100		(4:1) mix 70			5ml + 20ml D.I. reads ~70 on meter
"	1200	5gpm	4:1 mix reads 75			—
"	1300	5gpm	4:1 mix 95			—
"	1500	5gpm	4:1 0:1 47			Sample set taken (2')
"	1515	—	—			Terminated pumping for today

Note: Unless otherwise noted,
 the following units are assumed:
 Flow rate - gpm
 Turbidity - NTU
 Water Level - ft

Equipment:
 Make: _____
 Model: _____
 Serial #: _____

Continuation

608

DRILL LOG			Rig	Well Number	Computer Number	Project or Work Order No.
Total Casing	Depth	Drill Method	Wet/Dry Sample	LITHOLOGIC DESCRIPTION
% Each Grain Size, Color, Roundness, Caliche, Etc.	Time	Drilling Comments
				69A-42-E9A
Sav. Island		
				Well to Development		
				Start Pumping	0830	
				~ 5 gpm		
				75 strokes/min		
				pumping rate increased to ~ 6 gpm	0845	
				Checked Sample for turbidity but could		
				not read without dilution 3:1 = 50 NTU	0935	
				pumping rate increased to ~ 7 gpm this is the		
				max for Hydrostar	1015	
				Sample for turbidity undiluted = 95 NTU	1045	
				Sample for turbidity undiluted = 63 NTU	1145	
				1045 sample saved and re-read just before		
				1145 Sample and reading had dropped to 81 NTU		
				The samples when initially taken seem to have a lot of		
				air mixed with the water - after standing they seem less		
				cloudy but no sediment is obvious on bottom of tube		
				Sampled for turbidity undiluted = 50 NTU	1245	
				Sampled for turbidity undiluted = 39 NTU	1345	
				Sampled for turbidity undiluted = 31 NTU	1430	
				Terminate for Day	1445	

REMARKS:

End of Log

DRILL LOG				By	Rig	Well Number	Computer Number	Project or Work Order No.
				Date	Pump	Depth		Subcontract No.
				Glover	2-7-91	Well		
						Development		
LITHOLOGIC DESCRIPTION								
Total Casing	Depth	Drill Method	Wet/Dry Sample	% Each Grain Size, Color, Roundness, Caliche, Etc.	Time	Drilling Comments		
				start pumping ~ 79pm	1030			
				First Sample for turbidity = undiluted 26 NTU	1048			
				Sampled for turbidity undiluted = 25 NTU	1200			
				Sampled for turbidity - undiluted = 24 NTU	1300			
				pumping rate ~ 79pm	—			
				Sampled for turbidity - undiluted 20 NTU	1400			
				Set of regular Samples taken	1415			
				Terminate pumping to make time to				
				order more sample bottles	1430			
REMARKS:								
G. W. Glover								

WELL COMPLETION SUMMARY

Project <u>Savage Island</u>	Well No. <u>699-42-698</u> Temp. Well No. <u>N/A</u>
Location <u>N of Ringold</u>	Coordinates <u>N41.775 E 8.452</u>
Drilling Co. <u>Jensen Bros</u>	Elevation: Casing <u>386.42</u> Brass Marker <u>383.52</u>
Driller <u>Art Gwin, Joe Roach, Dennis Mingo</u>	
Other (companies) _____	
Geologist(s) <u>TJ Gilmore, MA Channess, SS Teel</u>	

DRILLING METHOD

Drilling Method(s) Mud Rotary / Air Rotary

Drilling Fluid Bentonite and water / water
Other _____

COMPLETION DATA

Drilled Depth 390'
Completed Depth 384'
Date Started 2/14/91
Date Completed 4/2/91
Static Water Level/Date 32' 4/1/91

OTHER (check if performed)

☐ Well Abandonment	☐ Downhole TV Inspection
☒ Well Development	☐ Driller's Logs
☒ Aquifer Testing	☒ Pad
☒ Geophysical Log(s)	☒ Guardposts
☒ Lock and Cap	☒ Protective Casing

SCREEN

Type	Outer Diameter	Length	Slot Size	Interval
<u>6" Stainless Steel Telescoping Screen 10 Slot</u>	<u>5 9/16"</u>	<u>21.19</u>	<u>10 Slot</u>	<u>354 - 354</u>
<u>6" Stainless Steel Blank</u>	<u>5 9/16"</u>	<u>5.02</u>	<u>N/A</u>	<u>354 - 349</u>

TEMPORARY CASING

Type	Nominal Diameter	Max. Outer Diameter	Interval
<u>Carbon steel w/ shoe</u>	<u>MAC 39.16"</u>		<u>0 - 39.6</u>
<u>Carbon steel 76</u>	<u>6" 76</u>		<u>+1.5' - 354 76 4/1/91</u>

PERMANENT CASING

Type	Nominal Diameter	Max. Outer Diameter	Interval
<u>Carbon steel</u>	<u>10"</u>		<u>0' - 332.45 231.45 MAC 7/21/92</u>
<u>Carbon Steel</u>	<u>6"</u>		<u>+1.5 - 354</u>

ANNULAR SEAL/FILL

Type	Interval	Quantity	Volume
<u>Cement Grout (drilled - out)</u>	<u>0' - 232'</u>	<u>900 gal</u>	<u>120 ft³</u>
	<u>205.63' - 232'</u>	<u>320 gal</u>	<u>43 ft³</u>
<u>Colo. Silica Sand (20-40 mesh)</u>	<u>388.67' - 348.355.6'</u>	<u>13.5 bags (100 lbs ea)</u>	<u>15.12 ft³</u>
<u>Colo. Silica Sand (40-100 mesh)</u>	<u>355.6' - 348.355.6'</u>	<u>2 bags (100 lbs ea)</u>	<u>2.28 ft³</u>
<u>Bentonite Slurry</u>	<u>348.2 - 17'</u>	<u>915 gal (9.3 lb/gal av.)</u>	<u>122.32 ft³</u>
<u>Cement Grout</u>	<u>17' - 0'</u>	<u>40 gal (14 lb/gal)</u>	<u>5.35 ft³</u>
<u>Concrete pad</u>	<u>0' - 0'</u>		

PUMP

Type 3/4 H.P. Submersible Depth to Inlet 340' Date Set 2/19/92

ACCEPTANCE

Completed Well: Accept TJ Gilmore 4/6/91 Conditionally Accept _____
Reject _____

COMMENTS

WELL INSPECTION REPORT

Well No. 699-42-E9B Procedure DO-1, 5 Rev. 1, 0 Specification No. KEI-5236 Rev. 0
Geologist(s) TJ Gilmore, MA Chamness, SS Teel ECNs (list) _____

CLEANING/DECONTAMINATION	Inspection Method	Criteria	Accept	Reject	Date
Rig/Tools (initial)	Visual/Wipe (optional)		<u>MAC</u>		<u>2/12/91</u>
Temporary Materials	Visual/Wipe (optional)		<u>MAC</u>		<u>2/25/91</u>
Permanent Materials	Visual/Wipe (optional)		<u>MAC</u>		<u>2/12/91</u>
Mtls Brought Onsite Later	Visual/Wipe (optional)		<u>MAC</u>		<u>4/1/91</u>

MATERIAL STORAGE/PACKING	Inspection Method	Criteria	Accept	Reject	Date
Material Storage	Visual	2.1	<u>MAC</u>		<u>4/1/91</u>
Material Packing/Seals	Visual	2.1	<u>MAC</u>		<u>4/1/91</u>
Other					

LUBRICANTS/ADDITIVES/AIDS	Inspection Method	Criteria	Accept	Reject	Date
Lubricants (Well Guard)	Visual	3.7	<u>MAC</u>		<u>4/1/91</u>
Additives/Aids	Visual	3.7	<u>MAC</u>		<u>4/1/91</u>

DRILLING METHOD	Inspection Method	Criteria	Accept	Reject	Date
Method	Visual	3.3	<u>MAC</u>		<u>2/23/91</u>
Drilling Fluid	Visual	3.3, 3.7	<u>MAC</u>		<u>2/14/91</u>

STRAIGHTNESS TEST	Inspection Method	Criteria	Accept	Reject	Date
Well Straightness	<u>Deviation surveys</u>	3.6.1	<u>MAC</u>		<u>4/1/91</u>

COMPLETION	Inspection Method	Criteria	Accept	Reject	Date
Drilled Depth	Steel Tape # <u>500'</u> , no #	G-W Mon. Plan	<u>MAC</u>		<u>3/27/91</u>
Completed Depth	Steel Tape # <u>500'</u> , no #	G-W Mon. Plan	<u>EST</u>		<u>3/27/91</u>

PERMANENT SCREEN/CASING	Inspection Method	Criteria	Accept	Reject	Date
Screen Type/Slot/Length	Engineers Tape, Visual	2.1, 7, 3.3	<u>MAC</u>		<u>3/29/91</u>
Screened Interval	Steel Tape # <u>unmarked 500'</u>		<u>EST</u>		<u>3/29/91</u>
Casing Type/Size/Length	Engineers Tape, Visual	2.1, 7, 3.3	<u>MAC</u>		<u>3/28/91</u>
Centralizers/Location	Engineers Tape, Visual		<u>MAC</u>		<u>3/28/91</u>
Other					

FILTER PACK/ANNULAR SEAL	Inspection Method	Criteria	Accept	Reject	Date
Primary Filter Mtl/Place	Visual/Steel Tape#	2.1, 2, 3.3	<u>MAC</u>		<u>4/2/91</u>
Second Filter Mtl/Place	Visual/Steel Tape#	2.1, 2, 3.3	<u>MAC</u>		<u>4/2/91</u>
Annular Seal Mtl/Place	Visual/Steel Tape#	2.1, 2, 3.3	<u>MAC</u>		<u>4/1/91</u>
Install Annul Seal	Visual/Steel Tape#	2.1, 2, 3.3	<u>MAC</u>		<u>4/1/91</u>
Cement Type/Placement	Visual/Steel Tape#	2.1, 2, 3.3	<u>MAC</u>		<u>4/1/91</u>
Overdrill Seal Method	Visual/Steel Tape#	N/A			

WELL PROTECTION	Inspection Method	Criteria	Accept	Reject	Date
Surface Pad Mtl/Place	Visual/Engineers Tape	2.1, 2, 3.3	<u>MAC</u>		<u>4/1/91</u>
Surface Casing Mtl/Place	Visual/Engineers Tape	2.1, 2, 3.3	<u>MAC</u>		<u>4/1/91</u>
Cap/Hasp/Lock	Visual		<u>MAC</u>		<u>4/1/91</u>

WELL SURVEYING/MARKING	Inspection Method	Criteria	Accept	Reject	Date
Well ID Stamped/Correct	Visual		<u>MAC</u>		<u>7/21/92</u>
Well Surveyed/Toler Met	Review Survey Data		<u>MAC</u>		<u>7/21/92</u>

PUMP INSTALLATION	Inspection Method	Criteria	Accept	Reject	Date
Pump Decon/Preparation	Visual		<u>EST</u>		<u>7/19/92</u>
Installation/Placement	Visual/Engineers Tape				
Pump Operational	Observed Running				

Technical Review Complete MAC

Date 8-19-92

AS-BUILT DIAGRAM		Boring or Well Number <u>699-42-E9B</u>		Sheet <u>1</u> of <u>3</u>	
		Location <u>N. of Ringold</u>		Project <u>Savage Island (Sitewide)</u>	
Logged by <u>MA Channess, TJ Gilmore, SS Teel</u>
Reviewed by <u>[Signature]</u>				Date Well Started <u>2/14/91</u>
Date Well Completed <u>4/2/91</u>	
Well Construction Data			Geologic/Hydrologic Data		
Description	Construction Diagram	Drill Bit	Depth in Feet	Sample Method	
				Lithologic Diagram	Lithologic Description
		☐	5	☒	MUDDY SAND
16" carbon steel casing - 0'-39.6' →		☐	10	☒	MUDDY GRAVEL ? @ 8'
		☐	15	☒	" " ?
		☐	20	☒	SANDY GRAVEL
		☐	25	☒	" "
		☐	30	☒	" "
		☐	35	☒	" "
		☐	40	☒	GRAVELLY SAND ?
10" carbon steel casing - 0'-231.45' →		☐	45	☒	SANDY GRAVEL
		☐	50	☒	SAND, some gravel
		☐	55	☒	SAND, some gravel
		☐	60	☒	SAND, very little gravel
16" carbon steel casing + 1.6'-354' →		☐	65	☒	SAND & SILT
		☐	70	☒	" "
		☐	75	☒	" "
		☐	80	☒	" "
		☐	85	☒	SAND, hit GRAVEL @ 84'
bentonite slurry 17'-348.2' →		☐	90	☒	CLAY @ 88'
		☐	95	☒	"
		☐	100	☒	CLAYEY SILT 99' incr drill rate
10" carbon steel casing cemented in place w/ cement grout →		☐	105	☒	SILTY SAND
		☐	110	☒	SILT
		☐	115	☒	"
		☐	120	☒	SILTY SAND
		☐	125	☒	" "
		☐	130	☒	" "
		☐	135	☒	" "
		☐	140	☒	GRAVELY SAND @ 133'
		☐	145	☒	CLAYEY SILT
		☐	150	☒	" "
		☐	155	☒	" "
		☐	160	☒	SAND
		☐		☒	GRAVELY SAND

Drill Bit/Sample Method Used:

☐ Rotary
 ☒ Air Rotary
 ☐ Mud Rotary
 ☐ Air Percussion
 ☐ Back Hoe
 ☐ Auger
 ☐ Drive Barrel
 ☐ Hard Tool
 ☐ Split-Barrel

AS-BUILT DIAGRAM			Boring or Well Number <u>699-42-E9B</u>		Sheet <u>2</u> of <u>3</u>	
			Location <u>N. of Ringold</u>		Project <u>Savage Island</u>	
Logged by <u>MA Charnness, TJ Gilmore, SS Teel</u>				Date Well Started <u>2/14/91</u>		
Reviewed by <u>[Signature]</u>				Date <u>8-19-92</u>		
Well Construction Data				Geologic/Hydrologic Data		
Description	Construction Diagram	Drill Bit	Depth in Feet	Sample Method	Lithologic Diagram	Lithologic Description
			165			GRAVELLY SAND
			170			" "
			175			SL. GRAVELLY SAND
			180			SANDY GRAVEL
			185			GRAVEL SAND & SILT BALLS
			190			SL. GRAVELLY CLAY
			195			GRAVELLY CLAY
			200			" "
			205			" "
			210			" "
			215			SL. SANDY CLAY
			220			" " "
			225			SL. GRAVELLY CLAY
10" carbon steel casing 0'-231.45'			230			Basalt @ 226', dense nonvesicular
open hole, cemented & drilled out			235			@ 232, vesicular, oxidized red
			240			Basalt - dense, fresh
6" carbon steel casing 116'-354'			245			@ 243' interflow zone, vesicular
			250			Basalt, more dense
			255			" "
			260			Basalt, dense
bentonite slurry 17'-348.2'			265			" "
			270			Basalt, dense + green clay
			275			Basalt, dense
			280			" "
			285			" " colonnade/platy zone?
			290			" "
			295			" "
			300			" "
			305			" "
			310			" "
			315			" "
			320			" "
			325			" "

Drill Bit/Sample Method Used:

☐ Rotary
 ☒ Air Rotary
 ☒ Mud Rotary
 ☒ Air Percussion
 ☒ Back Hoe
 ☒ Auger
 ☐ Drive Barrel
 ☐ Hard Tool
 ☐ Split-Barrel

AS-BUILT DIAGRAM

Boring or Well Number 699-42-E9B

Sheet 3 of 3

Location N. of Ringold

Project Savage Island

Logged by MA Chamness, T.J. Gilmore, SS Teel

Reviewed by Bill Post

Date 8-19-92

Date Well Started 2/14/91

Date Well Completed _____

Well Construction Data

Geologic/Hydrologic Data

Description	Construction Diagram	Drill Bit	Depth in Feet	Sample Method	
				Lithologic Diagram	Lithologic Description
16" carbon steel casing + 1.6' - 354'		▼	330		Basalt, dense
open hole, cemented to 354' and drilled out			335		" "
			340		" "
bentonite slurry 17' - 348.2'			345		" "
			350		" "
neoprene packer 342.48' - 342.97'			355		Vesicular basalt @ 354'
telescoping 5" st steel blank 347.99' - 342.47'			360		Red brown vesicular basalt @ 359'
telescoping 16" 10 slot st. steel screen 347.99' - 384.2'			365		Hard dense basalt @ 360'
			370		Red brown vesicular basalt @ 364'
sand pack from 343.2' - 388.67'			375		Basalt, dense, phytic
			380		" "
			385		Vesicular basalt, dk gray/black
			390		Vesicular basalt + sandstone
					Basalt, dense

TD = 388.67'

Drill Bit/Sample Method Used:

☐ Rotary ☒ Air Rotary ☒ Mud Rotary ☒ Air Percussion ☒ Back Hoe ☒ Auger ☒ Drive Barrel ☒ Hard Tool ☒ Split-Barrel

699-42-E9B

Sheet 1 of 2

[illegible]

Drilling Contractor Jensen Brothers

Driller _____

Riq/Method	Rotary R19	and	F

[illegible]

A-1800-003 (01/90)

Sheet 2 of 2

Rig Method Rotary Rig and Pipe

A-1800-003 (05/90)

Depth Surface - 5' sheet 1 of 7

Project Savage Island

Drilling Contractor Teague Bros

Driller Art Gwin

Rig/Method Mud rotary / Speed star SS-15 III

—

| DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)	
CASING	
	RPT check
	lunch
	Mud Pump model # FVNDMA
	Liner 7 1/4, stroke 116 in.
19.83	Preparing to install starter
at 11"	casing
	Begin Drilling
	Sample taken using air rotary

A-1800-003 (05/90)

[illegible]

A-1800-003 (05/90)

DAILY BOREHOLE LOG

Boring or Well Number 199-42-E9B
 Location North of Ringold

Depth 14' - 16' Sheet 1 of 2
 Project Savage Island

Logged by MA Chamness T Gilmore
 Print Sign

Date 2/15/91

Reviewed by _____
 Print Sign

Date _____

Lithologic Classification Scheme Folk

Procedure DO-1, DO-5 Rev No 1, D

Measuring Equipment NA

Drilling Contractor Jensen Brothers

Driller Art basin

Rig/Method Mud fair rotary Speedster SS-15
III

| DEPTH
: | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|------------|---------|-----|---------------|---------|----------|-------------|---|------|------------------------|--|------------------------------|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | CASING | |
| | | | | | | | Geologists and Drillers on site at 7:00 | 710 | | 19.83' | Calibrated HNU to 100 ppm |
| | | | | | | | Driller finish prep work | | | of 16" | 150 C4 Hg/air w/ span @ 7.23 |
| | | | | | | | | | | | Can't monitor borehole until |
| | | | | | | | Start Drilling with work started | 755 | | | the air hammer is removed |
| | | | | | | | Casing through gravel | | | | Drilling |
| | | | | | | | | 820 | | | stopped drilling going with |
| | | | | | | | Drilling Hand through gravel | 920 | | | water truck to fish hatchery |
| | | | | | | | MUDDY GRAVEL (?) Sample not representative | 940 | | | Start Drilling |
| | | | | | | | fine; Very fine powder from rotary | | | | |
| | | | | | | | val run in HCL 5 1/2" away | | | | |
| | | | | | | | Drilling hard ~ 10 min/ft | | | | |
| | | | | | | | Filling Mud tanks with water in | 945 | | | |
| | | | | | | | preparation to mud up; water is being | | | | |
| | | | | | | | hauled in water truck rented from | | | | |
| | | | | | | | Acme Concrete Co. Water source is | | | | |
| | | | | | | | Ringold fish hatchery stand pipe | 1050 | | | |
| | | | | | | | | | | | |
| | | | | | | | Tyler lift w/ Pat Collier | 1150 | | | |
| | | | | | | | | 1405 | | | |

W = wet, M = moist, D = dry

material, A-1800-003 (05/90)

[illegible]

A-1800-003 (05/90)

2

TIME _____

Arrive on site, Starting equipment

Span gas Lot 28734, 100 ppm

ISO C₄ H₈ / Air

Calibrate HNU. Span is set

@ 3.19 to read SS ppm w/ 10.2 eV probe

Site w/ HNU = LEL: Background

Life is a part of wall read

1

1

11

	T

1

1

T

T

1

T	

T	

050

1

W = wet, M = moist, D = dry

A-1800-003 (05/90)

DAILY BOREHOLE LOG

Boring or Well Number 699-42-E9B

Location North of Ringold

Depth 16' - 18' Sheet 1 of 1

Project Savage Island

Logged by Tyler Gilmore / Mickie Chamness Sign [Signature] Date 2/19/91

Reviewed by [Signature] Sign [Signature] Date 2/19/91

Lithologic Classification Scheme Folk Procedure DO-1, DO-5 Rev No 1.0

Measuring Equipment N/A

Drilling Contractor Jensen Drilling Co

Driller Art Guin

Rig/Method Mud/Air Rotary Spectator SS-15 III

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-------|---------|-----|---------------|---------|----------|-------------|---|--------|------------------------|--|--------------------------------------|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | CASING | |
| 16' | | | | | | | Geologists and Drillers at Site | 700 | | 16.7' | Arrive |
| | | | | | | | HNU span at 29 for Benzene Spun Gas | 710 | | at 16" | Calibrate HNU and HEL 103 |
| | | | | | | | Lot 28734 100 ppm TSCG Hg/Air - 102400 | | | | |
| | | | | | | | Casing delivered includes | | | | |
| | | | | | | | (12) 20' 10" Carbon Steel [24004] | 830 | | | Hook up mud lines |
| | | | | | | | (18) 20' 6" Carbon Steel [36004] | 930 | | | Build guards for Mud Tanks |
| | | | | | | | (1) 10' 1120' 102400 Series 5612561 | 1030 | | | Hook up Mud controls on Rig |
| | | | | | | | All material is covered w/ plastic and off | 1045 | | | Mud wt 8.7 Vis 43 |
| | | | | | | | 41e ground | | | | (will add ~10 more sacks of Hydrate) |
| | | | | | | | | | | | Fix Pump Switch Seal |
| | | | | | | | | | | | Lunch |
| | | | | | | | Lost ~ 3500 gal | 12-235 | | | Drilling Pump Pressure 400 |
| | | | | | | | losing Mud to hole; Stop drilling and | 1245 | | | Lost Circulation |
| | | | | | | | make water runs; drilled approx 4' | 1310 | | | Stop Drilling |
| | | | | | | | D/B ~ 19' lost | 1500 | | | Mixing more Mud |
| | | | | | | | will try to drill again with thicker | | | | |
| | | | | | | | Mud | 1615 | | | Mud wt 8.6 Vis 163 |
| | | | | | | | testing circulation | | | | |
| | | | | | | | lost ~ 3500 gal | 1620 | | | Started drilling again |
| | | | | | | | Mix more Mud; anticipate mud in well | 1645 | | | Stop drilling |
| | | | | | | | will gel tonight | | | | |
| | | | | | | | | 1730 | | | End of Day |

W = wet, M = moist, D = dry

Boring or Well Number 1699-42-E9B
Location N. of Ringold

Depth 18'-21' Sheet 1 of 1
Project Lawrence 12/1/12

Sheet 1 of 1

Logged by MA Chamness Printed

MA Channers Sign

Date 2/20/91

Drilling Contractor Jensen Bros.

Reviewed by _____ Printed _____

Page 10 of 10

Date _____

Driller Art Gunn

Lithologic Classification Scheme Folk

Procedure LO-1, LO-5

Rev No 1,0

Rig/Method Alind volkay - fraction 2-15 the

Measuring Equipment L'A

1. A

[illegible]

W = wet, M = moist, D = dry

A-1800-003 (05/90)

2023

Sheet 2 of 2

Drilling Contractor Tensen Drilling

Driller Art Gwin

31-12-1935

11

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O
ADDED | CASING | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) |
|-------|---------|-----|---------------|---------|----------|-------------|--|------|---------------------------|--------|---|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | | |
| 35' | Lith | 2 | | | N/A | | SANDY GRAVEL (?) Fragments -
not representative, largest grain -
cp subbed - rd when preserved
65% matrix, 35% felsic. Matrix ind
pardon b/c w/ about volcanics
ed various colors, overall wet color
N34 E 60 N, no rxn in HCl necessary
similar to previous, more volcanics
(Air Pottery) | 1355 | | | Drill rate increased at ~
28' (water table) |
| 40' | Lith | 2 | | | N/A | | GRAVELLY SAND (?) Fragmented more
coarse sand and less pebble fractions
fining up from previous; preserved grains
are subbed, 60% matrix 40% felsic; about
multicolored volcanics here in unit
and blk qtz monzonites slightly more
qtz illuvial previous no rxn in HCl
(Air Pottery) Note: There was a trace of oil in
the mud from the sample. May be from crop cover
oil. - Pat Gillier called requesting verbal
approval for Tension Drilling 1, use a (water table)
oil in the mud even previous - Stuart L. called for
The new oil is a synthetic petroleum base. Dec'd by | 1450 | | | Drill rate change at 35' to
finer grained material and silt |
| | | | | | | | | | | | Prepare to cement casing at
surface |
| | | | | | | | | | | | Am MSDS was sent to Pat Gillier.
End of Day 1600 |

A-1800-003 (05/90)

DAILY BOREHOLE LOG										
Boring or Well Number <u>699-42-E9B</u>			Depth <u>46'-SD</u>		Sheet <u>1</u> of <u>3</u>		Location <u>North of Ringold</u>			
Logged by <u>T Gilmore / M. Chambers</u>			Date <u>2/25/91</u>		Drilling Contractor <u>Tensen Drilling Co</u>					
Reviewed by <u>Falk</u>			Date <u>2/25/91</u>		Driller <u>Art Gwin</u>					
Lithologic Classification Scheme <u>Falk</u>			Procedure <u>Do-1, Do-5</u>		Rig/Method <u>Mud Rotary / Spoolstar 55-15 III</u>					
Measuring Equipment <u>N/A</u>			Sign <u></u>		Sign <u></u>					
DEPTH	SAMPLES	CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASING	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, IN-OWN COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
		INSTRUMENT	READING							
						Geologist and Drilling crew at the site	700			At site
						Switch over to Mud rotary - Change				
						out the Air hammer (Well Guard				Switch to Mud rotary
						Lubricant used)				
						Calibrate HALL's Meter Probe w/ in-situ	715			Calibrate HALL's LEL
						is Catty/Air Calibration gas Spore				
						Mit Chamness on site	850			
							1000			We'd on well head
						Ed Enloe KEH safety visits site	1130			KEH Safety
							1230			Lunch
						Mud too thick - running over sink-shaker	1230			Run drill string in hole
						need to thin it out	1400			Drilling Mud W-186 vis 80
						Replace Homestick sand w/ 20-40 mesh	1415			New delivery of sand
						Sandy Gravel - ~40% basalt, 60% granitic	1420			Sampled from poreum belly
						quartzite etc. Sample not representative				Some nylon fibers, rod's nest?
						Sand, some gravel - ~40% basalt, 60%	1430			Sampled from shaker
						qtz rich. Samples not representative.				
										8 1/2' into for 45'-50'
										pumping at 100 PSI

W = wet, M = moist, D = dry

A-1800-003 (05/90)

Depth 50'-65' Sheet 2 of

Drilling Contractor Lucas Bros.

三

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100

100

[illegible]

A-1800-003 (05/90)

Boring or Well Number 699-42-159B Depth 65-85' Sheet 3 of 3
Location N. of Ringold Project Savage Island

Logged by MA Chambers Print Sign 2/25/11
Reviewed by _____ Date _____
Lithologic Classification Scheme COLIA Procedure DO-1, DO-5 Rev No LD
Measuring Equipment NA

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDEDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | CASINGS | DRILLING COMMENTS
(DOWLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) |
|-------|---------|-----|---------------|---------|----------|-------------|---|------|------------------------|---------|---|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | | |
| 70' | Lith | 2 | | | | | Sand + silt. Seems to be more silt than before, more "mud balls". Still brown. Samples not representative. | 1715 | | | Sampled from shale shaker |
| 75' | Lith | 2 | | | | | Sand + silt, same as above, samples not representative. | 1720 | | | Sampled from shale shaker |
| 80' | Lith | 2 | | | | | Sand + silt, same as above, even heavier, samples not representative. | 1728 | | | Sampled from shale shaker |
| 85' | Lith | 2 | | | | | Sand, micaceous, ^{silt-rich} obviously different & much coarser than previous samples, vc + c sand abundant. Color said to grayish-brown. Driller says he hit gravel at 84'. | 1735 | | | Sampled from shale shaker |
| | | | | | | | Mud column up about 16" above, will get a sample tomorrow to pump it into tank or back into flow mud tanks. | | | | Sampled for test |

A-1800-003 (05/90)

Boring or Well Number 074-42-1312

Location N. of Rinedd

Depth 90' - 110' Sheet 2 of 7
Project Seware Island

Logged by MAA CHANNELS SSTEEL
Print

MA Channery SS Co. Date 2/26/91

Reviewed by _____ Printed _____

Date _____

Sign _____

Lithologic Classification Scheme

Procedure DO-1 DO-5 Rev No 1.0

Measuring Equipment

[illegible]

W = wet, M = moist, D = dry

A-1800-003 (05/90)

Depth 110' - 125' Sheet 3 of 7

Project Small Business

Drilling Contractor Tjensen Bros.

Driller Art Gwin

Rig/Method Mud Rotary SS-15 III

[illegible]

W = wet, M = moist, D = dry

A-1800-003 (05/90)

[illegible]

A-1800-003 (05/90)

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-42-E96</u>			Depth <u>140 - 160</u> Sheet <u>5</u> of <u>7</u>		Project <u>Savage Island</u>				
Location <u>N. of Ringold</u>			Date <u>2/26/91</u>		Drilling Contractor <u>Jensen Bros</u>				
Logged by <u>MA Chomney</u> <u>CS Teel</u>			Date <u>2/26/91</u>		Driller <u>Art Gavin</u>				
Reviewed by <u>Print</u>			Date <u>Print</u>		Rig/Method <u>Mud rotary SS SSTI</u>				
Lithologic Classification Scheme <u>Folk</u>			Procedure <u>FO-1, FO-5</u>		Rev No <u>1, 0</u>				
Measuring Equipment <u>NA</u>									
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)	DRILLING COMMENTS
145'	Lith 2				SILTY CLAY OR CLAYEY SILT, some
gravel, possibly from down "Mud ball"
the very stiff when pressure is applied
brown, washed, not representative	1615			76 strokes/min = 107.5 ft/min
annular velocity
150'	Lith 2				SILT, some clay (CLAYEY SILT?),
similar to above sample, washed,
not representative	1619			sampled from shale shaker
155'	Lith 2				CLAYEY SILT, 10% gravel (carrydown?)
some stiff clay balls. Same color as previous
washed, not representative	1623			sampled from shale shaker
160'	Lith 2				sand-micaceous silt, some sand
gravel & mud balls, some fine gravel,
washed, not representative	1628			sampled from shale shaker

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG										
Boring or Well Number <u>699-42-EAB</u>			Depth <u>160-180'</u>			Sheet <u>6</u> of <u>7</u>		Project <u>Savage Island</u>		
Location <u>N. of Ringold</u>										
Logged by <u>MA CHAMBERS</u> <u>ss</u> <u>Teel</u>			Date <u>2/26/91</u>			Drilling Contractor <u>Jensen Bros</u>				
Print			Sign			Driller <u>Art Guin</u>				
Reviewed by			Date			Rig/Method <u>mud rotary</u>				
Lithologic Classification Scheme <u>Folk</u>			Procedure <u>DO-1 DO-5</u>			Rev No <u>1, D</u>				
Measuring Equipment <u>NA</u>			Sign							
DEPTH	SAMPLES	CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	CASING	DRILLING COMMENTS
(DRILLING RATE, BOPPM, TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)
		INSTRUMENT	READING							
165'	165' Lith 2					GRAVELLY SAND - m-vfg, sand
similar to above, but rich in mica
Ground vix. Sample washed, not
representative. Still some mud balls.	1650			Drilling
Slightly washed, sampled
from shale shaker
170'	170' Lith 2					GRAVELLY SAND - similar to above,
Hard to say whether gravel, sand, or
mud balls. This firm olive sample not
washed, not representative.	1655			Driller says it's drilling at
a constant rate
sampled from shale shaker
175'	175' Lith 2					SAND - gte rich, micaceous. Some
gravel, mostly broken up or much
as above. Some good lumps, also not
so much. Sample not washed, not
representative.	1658			6.5 vis, 9.5 mud vit
Sampled from shale shaker
180'	180' Lith 2					SANDY GRAVEL - gravel very abundant, 70%
sand micaceous. Gravel 10%
Violet, the rest quite clear. Sample
not washed, not representative.	1659			Sampled from shale shaker
Gravel 10%
18.2'

Depth 180-185 Sheet 7 of 7

III

[illegible]

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-42-E9B</u>			Depth <u>185-200'</u>			Sheet <u>1</u> of <u>4</u>			
Location <u>North of Riggall</u>			Project <u>Savage Island</u>						
Logged by <u>T. G. L. Steel</u>			Date <u>2/27/91</u>			Drilling Contractor <u>Tension Drilling</u>			
Reviewed by <u>Print</u>			Date <u> </u>			Driller <u>Art Guin</u>			
Lithologic Classification Scheme <u>Folk</u>			Procedure <u>DO-1, DO-5</u>			Rig/Method <u>Mud rotary / Spinslog 95-15 III</u>			
Measuring Equipment <u>M/A</u>			Sign <u> </u>			Rev No <u>1, 0</u>			
DEPTH	SAMPLES	CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING RATE, BOREHOLE TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.
		NO.	INSTRUMENT						
						Geologists and Driller at Site	700		
						Prepare to switch to a hydraulic hose			
						Deviation Survey on 2/26/91 @ ~100'			
						was less than 1/2° tilt			
						Spinnet @ 8.86 to read 55 ppm.	0800		Calibrate HNU + LEL/O ₂
						Some spargers as previous			Check outside of borehole
							0820		Circulating Mud
						On 2/26/91 the drilling mud serviced	0850		Making Connection
						the soil contained small amounts of	0905		
						fluid from 2/26/91 - 1 way also picked up			
						small oil and hydraulic leaks from other			
						places on site. The absorbent material used			
						on 2/25 was put in plastic bags. The			
						drum is marked w/ contents, date and			
						origin			
190'	lith 2					CLAY Lt Brn sl water soluble	935		Sample
						w/ 10% wgt B&T and quartz in clay			
195'	lith 2					CLAY A/A w/ 10% Gravel v slicky	939		Sample
						grummy clay No rxn in HCl			
200'	lith 2					CLAY A/A w/ 10% Gravel - 20-30mm -	943		Sample
						size and - shd 50-70 mic / calc 10TR 5/2			

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG

Boring or Well Number 699-43-E9B
 Location North of Rivard

Depth 200'-225' Sheet 2 of 4
 Project Seavage Island

Logged by T. Gilmore / Steel Sign T. Gilmore Date 2/27/91

Reviewed by Folk Sign Folk Date 2/27/91

Lithologic Classification Scheme Folk Procedure DO-1, DO-5 Rev No 1.0

Measuring Equipment N/A

Drilling Contractor Tensen Drilling
 Driller Art Gwin
 Rig/Method Mud Rotary / Spindlestar 55-15 III

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-----------|---------|-----|---------------|---------|----------|-------------|---|------|------------------------|--|------|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | CASING | |
| 205' Lith | 2 | | | | | | CLAY A/A (as above) | 0950 | | | Smpl |
| | | | | | | | Still Drilling fast - gravels in clay keep | | | | |
| | | | | | | | hit from belline - mud vis going up | | | | |
| 210' Lith | 2 | | | | | | CLAY A/A still contains gravels | 0954 | | | |
| | | | | | | | Deviation Survey at 200'; 1° off | 1003 | | | |
| | | | | | | | (within contact zone at 1°/50') | 1122 | | | |
| | | | | | | | Adding water to cut viscosity in Mud | | | | |
| | | | | | | | | 1132 | | | |
| | | | | | | | | 1133 | | | |
| 215' Lith | 2 | | | | | | CLAY lost most Gravels ~ 10% CS | 1138 | | | |
| | | | | | | | clay sl. soluble in H ₂ O 10% R 5/2 WORK | | | | |
| | | | | | | | in HCL | | | | |
| 220' Lith | 2 | | | | | | CLAY A/A 10% R 5/2 | 1148 | | | |
| 225' Lith | 2 | | | | | | CLAY change in color to NS Gray | 1157 | | | |
| | | | | | | | lost most of the gravels ~ 5% Belt | | | | |
| | | | | | | | gravels, ang - subbed - sampled again | | | | |
| | | | | | | | and found fragmentary in B&T clip | | | | |
| | | | | | | | angular blk v. few vesicles, clay in | | | | |
| | | | | | | | this sample has a blue blk but is still | 1230 | | | |
| | | | | | | | NS dr. gy | 1240 | | | |

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG

Boring or Well Number 699-42-E9B
 Location North of Rinefold

Depth 225'-232' Sheet 3 of 4
 Project Swamp Island

Logged by T. Gilmore / S. Teal Date 2/23/91
 Print

Reviewed by T. Gilmore Sign T. Gilmore Date 2/23/91
 Print

Lithologic Classification Scheme Folk Procedure DD-1, D-13 Rev No 1.0

Drilling Contractor Tension Drilling Co
 Driller Art Gustin
 Rig/Method Mud rotary / Sparker SS-15 III

Measuring Equipment

| DEPTH | SAMPLES | CONTAMINATION | | MONI-
TURE | GRAPHIC
LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O
ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) | |
|-------|---------|---------------|------------|---------------|----------------|---|------|---------------------------|---|---|
| | | NO. | INSTRUMENT | READING | | | | | CASING | |
| 227 | L4h | 1 | | | | Balt - approx 80% of sample is rest
is considered carry down; balt is dense
(not vesicular) predom blk w/ some
grn and some coloring. A number
of "fish" not weathered | 1300 | | | Driller says it is "a lot firmer"
at about 226' |
| | | | | | | | 1314 | | | Sample |
| | | | | | | Will drill to ~232' and stop to
cement, will give us 5' ft of good balt. | | | | Desanding mud to condition
mud before pulling drill rod |
| | | | | | | | 1325 | | | Mud wt 9.0; 56 vis |
| | | | | | | Tim Young of KEH stopped by to label
and number the drums (2 drums in total
91-16-1 and 91-16-2. Drums waste is
designated non-vegetated | 1340 | | | Stopped drilling - tightening
seal on the Kelly - bentonite
is leaking out. |
| | | | | | | | 1345 | | | Drilling |
| 232' | L4h | 2 | | | | BOLT rd btm 10R 3/4 Dusty and w/ | 1451 | | | Sample L4h changed 232' |
| | | | | | | about mineral filled vesicles very
vesicular, cavity fillings are sand to
yellow to grn, about pale brn clay
filling the cavities, vesicles are about
5mm across, no matrix | | | | Drill mud has western streaks |
							1451			Mud @ 8' Int 53 vis
										Sweep hole w/ logs gel
										Circulate and work hole

Boring or Well Number
699-112-E98

Location	N. of	Ringold
1	100	100
2	100	100
3	100	100
4	100	100
5	100	100
6	100	100
7	100	100
8	100	100
9	100	100
10	100	100
11	100	100
12	100	100
13	100	100
14	100	100
15	100	100
16	100	100
17	100	100
18	100	100
19	100	100
20	100	100
21	100	100
22	100	100
23	100	100
24	100	100
25	100	100
26	100	100
27	100	100
28	100	100
29	100	100
30	100	100
31	100	100
32	100	100
33	100	100
34	100	100
35	100	100
36	100	100
37	100	100
38	100	100
39	100	100
40	100	100
41	100	100
42	100	100
43	100	100
44	100	100
45	100	100
46	100	100
47	100	100
48	100	100
49	100	100
50	100	100
51	100	100
52	100	100
53	100	100
54	100	100
55	100	100
56	100	100
57	100	100
58	100	100
59	100	100
60	100	100
61	100	100
62	100	100
63	100	100
64	100	100
65	100	100
66	100	100
67	100	100
68	100	100
69	100	100
70	100	100
71	100	100
72	100	100
73	100	100
74	100	100
75	100	100
76	100	100
77	100	100
78	100	100
79	100	100
80	100	100
81	100	100
82	100	100
83	100	100
84	100	100
85	100	100
86	100	100
87	100	100
88	100	100
89	100	100
90	100	100
91	100	100
92	100	100
93	100	100
94	100	100
95	100	100
96	100	100
97	100	100
98	100	100
99	100	100
100	100	100

Logged by Alan Pearson

Class Pearson

Date 2/28/91

Reviewed by _____

Print Sign

Pathologic Classification Scheme

Procedure NA

Rev No 12A

Measuring Equipment N/AWA[illegible]

W = wet, M = moist, D = dry

A-1800-003 (05/90)

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-42-ENB</u>
Location <u>N. of Finnold</u>				Depth <u>232'</u> Sheet <u>1</u> of <u>1</u>		Project <u>Savage Island</u>			
Logged by <u>MA Charnock</u> Sign _____				Date <u>3/4/91</u>		Drilling Contractor <u>Jensen Bros</u>			
Reviewed by _____ Sign _____				Date _____		Driller <u>Art Guin</u>			
Lithologic Classification Scheme <u>NA</u>				Procedure <u>NA</u>		Rev No <u>NA</u>			
Measuring Equipment <u>NA</u>				Rig/Method <u>Mud rotary SS IS III</u>					
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASING	DRILLING COMMENTS
(GIRLLING DATE, DOWN TIME, RECORDS, WATER LEVEL, DRILL FLUID, ETC.)
	TYPE	NO.	INSTRUMENT	READING					
					checked around site, HNU calculated	700			Picking up after wind storm
					to some gas as before, span @ B.O.	735			
						745			Start trapping in tool's again,
						950			were V.I.I. found in joints
						1040			start conditioning hole
						1110			Ed Enbe on site, left @ 1105
						1150			Bob Jones on site
						1210/1245			Pat Collier + vern on site
					Driller was asked to use environmentally				lunch, safety met, letting mud
					safe / non-petroleum based grease in lube	1255			circulate + clean out cuttings
					gun.	1510			Mud has cleaned up enough,
					Tyler called, wants 10" set 2'-3' off bottom	1520			trapping at Vis @ 72
					to allow for cement integrity check. When I				
					told this to driller, he was concerned w/				
					breaking the seal. Called back to office,				
					had ~ 1/2 hr standby until decision				
					was made to set 10" approx. 1' off bottom,				
					will try to drill 10" into cement joint + then				
					test it.	1630			Preparing to work first thing tomorrow
						1730			quit for day

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-42-E93</u>			Depth <u>232'</u>		Sheet <u>1</u> of <u>1</u>				
Location <u>Not Rugged</u>			Project <u>Savage Island</u>						
Logged by <u>T. G. ...</u>			Date <u>3/5/91</u>		Drilling Contractor <u>Texas Drilling Co</u>				
Reviewed by <u>Print</u>			Date		Driller <u>Art Gwin</u>				
Lithologic Classification Scheme <u>NA</u>			Procedure <u>NA</u>		Rig/Method <u>Mud rotary SS 15 III</u>				
Measuring Equipment <u>NA</u>									

| DEPTH | SAMPLES | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-------|---------|---------------|---------|----------|-------------|---|-------------------------------|------------------------|--|--------------------------------|
| | | INSTRUMENT | READING | | | | | | CASING | |
| | | | | | | | | | | |
| | | | | | | Discuss work for the Day | 900 | | | |
| | | | | | | Need to dispose of cement bucket | | | | |
| | | | | | | Mud before use drill into the Test-sink | | | | |
| | | | | | | Ridge | | | | |
| | | | | | | Caliente H ₂ N's w/ Benzene Calibration | 735 | | | Check site and bore hole |
| | | | | | | Gas Spool reads Slippage at 7.48 ppm | | | | |
| | | | | | | Run 10" Casing in - Will list pipe | 800 | | | Warning |
| | | | | | | Tally after casing runs in well | | | | |
| | | | | | | Will add water to inside casing while | | | | |
| | | | | | | placing casing in well | | | | |
| | | | | | | Tab Centralizers placed every 30 ft | | | | |
| | | | | | | (Wm) 21.5 w/Slur | 1230 | | | Lunch |
| | | | | | | 20.253 | 20.231 | | | KEH Swabber expended 6 bottles |
| | | | | | | 20.098 | 20.280 | | | |
| | | | | | | 20.255 | 20.050 | | | |
| | | | | | | 20.232 | (Total) 20.345 (10.5 stickup) | | | |
| | | | | | | 20.038 | 243.453 Total | | | Finish last weld |
| | | | | | | 20.050 | - 10.5 stickup | | | Cement 10" in morning |
| | | | | | | 20.055 | 232.953 in ground | | | End of Day |

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG				Boring or Well Number <u>699-42-F9B</u>		Depth <u>282</u>		Sheet <u>2</u> of <u>3</u>	
Location <u>Northern Ridge Rd</u>				Project <u>Savage Island</u>					
Logged by <u>T. Gilmore</u>				Signature <u>T. Gilmore</u>		Date <u>3/6/91</u>		Drilling Contractor <u>Tessens Drilling Co</u>	
Reviewed by <u>Print</u>				Signature <u>Print</u>		Date <u>Print</u>		Driller <u>A.T. Gwilt</u>	
Lithologic Classification Scheme <u>N/A</u>				Procedure <u>Gravimetric Procedure</u>		Rev No <u>N/A</u>		Rig/Method <u>Mud Rotary / Spudlog 33-15 III</u>	
Measuring Equipment <u>NA</u>				developed for Project					
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)	
	TYPE	NO.	INSTRUMENT	READING				CASING	
					Run Drill rod in well; will circulate mud before running cement	830			
					Spill hydraulic fluid on ground from grout pump; capture most of spill with absorbent material; Barrel rest is already prepared	940			
					Try Pump will not work	1030			
					Bob Jones (WHEC) is checking to bring a backup, found a pump at another site - Drillers shut down until pump can arrive				
						1215			Lunch
					New Pump arrives	1315			
					Test Pump - getting volume in well				
					Mix Grout 3 bags Bost	1325			
					3 bags CalCl ₂				
					900 gal water				
					12,300 lb cement				
					Grout Weight after mixing for 15 min 146	1355			Mix Grout
					Looking for 14.7 wt (lb/gal)				
					Weight Grout 14.6 wt before pumping	1410			Pump Grout

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-42-E9B</u>			Depth <u>232'</u>		Sheet <u>1</u> of <u>3</u>		Project <u>Seage Island</u>		
Location <u>N of Rickland</u>			Date <u>3/6/91</u>			Drilling Contractor <u>Tension Drilling</u>			
Logged by <u>T. Gilmore</u>			Sign <u>[Signature]</u>			Driller <u>Art Guin</u>			
Reviewed by _____			Date _____			Rig/Method <u>Mud Rotary / Speedstar SS 15 III</u>			
Lithologic Classification Scheme <u>N/A</u>			Procedure <u>N/A</u>			Rev No <u>N/A</u>			
Measuring Equipment <u>N/A</u>									

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | CORRECTION COMMENTS
(FILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-------|---------|-----|---------------|---------|----------|-------------|---|------|------------------------|---|-------------------------------|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | CASING | |
| | | | | | | | Total length of 10" in well | 700 | | | Drill bits and casing on site |
| | | | | | | | 243.453 - 10.5 (stickup) = 232.953 | | | | |
| | | | | | | | will cut off ~ 7' to leave 3' stickup | | | | |
| | | | | | | | will also pull up 1.5' old bottom to | | | | |
| | | | | | | | allow room for an integrity test after | | | | |
| | | | | | | | cement placed in well | | | | |
| | | | | | | | Calibrate HNLs w/ Benzene Span | 710 | | | Check site out borehole |
| | | | | | | | gas spacer 5.50; in note LEL | | | | |
| | | | | | | | Note: depth to bottom is 232.95' | | | | |
| | | | | | | | as measured w/ 10' is approx 0.9' | | | | |
| | | | | | | | deeper than calculated w/ casing | | | | |
| | | | | | | | Cement will use Portland type 1012 | | | | |
| | | | | | | | resistant, 2% Benzene, no acceler | | | | |
| | | | | | | | Calcium chloride at 2% | | | | |
| | | | | | | | Cut off 8' well below casing 1.5' | | | | |
| | | | | | | | above where casing resistance begins | | | | |
| | | | | | | | depth will be 231.45' | | | | |
| | | | | | | | Set Rig down on casing to prevent | | | | |
| | | | | | | | casing from floating up when setting | | | | |
| | | | | | | | cement | | | | |

2

A-1800-003 (05/90)

FIELD ACTIVITY REPORT - CEMENT CALCULATIONS

Page 1 of 1

Date 3/6/91 Well Number 699-42-E98 Continuation of Report No. _____

1.0 CEMENT STAGE VOLUME CALCULATIONS

1.1 Cement Volume - Open Hole/Casing 14 3/4" ID of casing or diameter of hole, inches = D
 _____ feet x 0.0408 x _____ D² = _____ Gallons of cement required
 _____ feet x 0.005454 x _____ D² = _____ Cubic feet of cement required

1.2 Cement Volume - Annular Spaces

- ☐ Between Tubing and Hole (D = Hole diameter, inches; d = OD of Tubing, inches)
☒ Between Casing and Hole (D = Hole diameter, inches; d = OD of Casing, inches)
☐ Between Tubing and Casing (D = ID of Casing, inches; d = OD of Tubing, inches)
☐ Between Casings (D = ID of outer Casing, inches; d = OD of inner Casing, inches)

D = 14 3/4" d = 10 3/4" n = Number of tubing strings

232 feet x 0.0408 x [217.5 D² - (115.5 d² x 1 n)] = 964.8 Gallons of cement required
232 feet x 0.005454 x [217.5 D² - (115.5 d² x 1 n)] = 129 Cubic feet of cement required

2.0 SLURRY MIX CALCULATIONS

2.1 Calculate Sacks of Cement Type: 1-2 lbs/sack: 94 ft³/sack (mixed): 1.36

129 ft³ (cement - from 1.0) + 1.36 ft³/sack (mixed) = 94.8 sacks

94 sacks + 48 sacks excess (50 % required) = 142 Total sacks required
 (13,348 lbs) Truck has 13,300 lbs

2.2 Calculate Mix Water

142 Total sacks cement x 6.5 gallons water/sack = 923 gallons of mix water required

2.3 Calculate Additive Amounts

Type Bentonic 142 Total sacks x 94 lbs/sack x 2 % = 267 lbs. required
 Cement Additive
 Type CaCl₂ 142 Total sacks x 94 lbs/sack x 2 % = 267 lbs. required
 Cement Additive

High Yield SS: = 227

3.0 DISPLACEMENT VOLUME CALCULATIONS

3.1 Balanced Plug Displacement

N/A ft. (top of cement) - N/A ft. (water level) = _____ feet to be displaced
100 ft. (to be displaced) x 0.499 gal/ft. = 49.9 gallons of displacement water required

4.0 REMARKS

Acme Cement Truck delivered 13,300 lbs dry Portland type 1 and 2 Cement
will mix additives at site

Report By T. G. Moore

Title _____

Signature _____

Reviewed By _____

Title _____

Signature _____

Date _____

1

Project Savage Island

Jensen Drilling Contractor

Driller Art Gwin

Rev No 1.0

420

Abstract

DAILY BOREHOLE LOG											
Boring or Well Number <u>699-42-69B</u>			Depth <u>190' (Cement plug)</u> Sheet <u>1</u> of <u>2</u>			Location <u>N of Ringold</u> Project <u>Savage Island</u>					
Logged by <u>SS Teel</u>		Print		Date <u>3/13/91</u>		Drilling Contractor <u>Jensen Drilling</u>					
Reviewed by		Print		Date		Driller <u>Art Guin</u>					
Lithologic Classification Scheme <u>N/A</u>						Procedure <u>DO-1, DO-5</u>		Rev No <u>1, 0</u>			
Measuring Equipment <u>N/A</u>						Rig/Method <u>Air Rotary</u>					
DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)	
	TYPE	NO.	INSTRUMENT	READING						CASING	
							Driller is working on rig	0710			Geologist on site
							D/water = 0.72' below top of casing	0805			
							Bottom of 10" @ 231.45' b.l.s.				
							Total 10" casing = 235.45'				
							Want to drill to 232.0' and then run integrity test.				
							D/Bottom inside 10" = 193.5 + 2.4 - 4' = 191.9	0950			
							Driller meas. bottom @ 198 - 4' = 194'				
							He has a heavy weight on his tape				
							The bottom feels very soft - the driller speculates that the check valve on the shoe may have leaked some bentonite through.				
								1000		Adding drill string	
								1040		P. Collier & V. Chamberlain arrive	
								1045		Blow water out of well	
								1050		Drilling w/ air rotary	
								1100		Stop drilling - talking to P. Collier	
								1130		Adding section of drill pipe	
								1137		Drilling	
								1145		P. Collier, V. Chamberlain leave site	
								1148			
								1200/1230		Lunch	

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG				Boring or Well Number <u>699-42-E9B</u>		Depth <u>232'</u>		Sheet <u>2</u> of <u>2</u>			
Location <u>N. of Ringold</u>				Project <u>Savage Is. - Site wide</u>							
Logged by <u>SS Teel</u>		Print		Sign		Date <u>3/13/91</u>		Drilling Contractor <u>Jensen Bros.</u>			
Reviewed by		Print		Sign		Date		Driller <u>Art Swin</u>			
Lithologic Classification Scheme <u>NA</u>		Procedure <u>D-1, D-5</u>		Rev No <u>1,0</u>		Log Method <u>Air Rotary</u>					
Measuring Equipment <u>0-1000 11053</u>											
DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	%O
ADDED	CASING	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
	TYPE	NO.	INSTRUMENT	READING							
								1300			Drilling
							Penetrate float shoe. Stop drilling.	1345			
							Add water to hole for integrity test	1400			
							D/water = 148.25 (from top of casing)	1412			
							meas. w/ 200' E-tape. Will wait 1 hr. for recovery.				
							D/water = 146.8 - not sure if first meas. was inaccurate (the casing was very wet and it was difficult to mass.) or if water is coming in.	1425			Recharge rate = 0.11 ft/min
											Wapato Fruit tank truck arrives to haul drill mud
							D/water = 145.55	1447			Recharge rate = 0.06 ft/min
							D/water = 144.85	1505			Recharge = 0.04 ft/min
							D/water = 144.62	1511			Recharge = 0.04 ft/min
							D/water = 144.25	1527			Recharge = 0.02 ft/min
							Truck was about 1000 gal short of emptying the tank - it will have to make a 2nd load	1535			Wapato truck leaves
							D/water = 143.55	1540			Recharge = 0.05 ft/min
							D/water = 143.33	1546			" = 0.04 ft/min
							D/water = 142.9	1557			
							D/water = 141.55	1630			
								1645			Leave site. Drillers will stay until Wapato truck comes back

W = wet, M = moist, D = dry

A-1800-003 (05/90)

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-43-E9B</u>			Depth <u>233-233</u>		Sheet <u>1</u> of <u>2</u>		Project <u>Savage Island</u>		
Location <u>N. of Ringsold</u>									
Logged by <u>MA Chamness</u>			Drilling Contractor <u>Jensen Drilling</u>						
Print <u>Tyler Gilmore</u>			Driller <u>Art Gwin</u>						
Reviewed by <u>MA Chamness</u>			Rig Method <u>Air Rotary / Speed Star 415 III</u>						
Lithologic Classification Scheme <u>N/A</u>									
Measuring Equipment <u>N/A</u>									
Procedure <u>DP-1, DP-5</u>									
Rev No <u>1.0</u>									
Date <u>3/4/91</u>									

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | CASINGS | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) |
|-------|---------|-----|---------------|---------|----------|-------------|---|------|------------------------|---------|--|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | | |
| | | | | | | | Drilled ~1' more cement before we hit bit - lost drilling slow | | | | |
| | | | Hake | Appr | | | Switch to Air Hammer | 950 | | | Stop Drilling |
| | | | LEL | OK | | | Trip out of hole | | | | |
| | | | | | | | All pipe out | 1022 | | | |
| | | | | | | | Rodney Nordquist and Scott Mackinnon are approved to work in Central Zone | 1050 | | | KEH safety approves Tinning |
| | | | | | | | Daily oils and lubricants approved were used to switch tools (RDN, Rockdrilling oil) and well guard | | | | |
| | | | | | | | 6 7/8" Air Hammer
1 1/2" Thread | 1190 | | | Run well with Drill string |
| | | | | | | | | | | | |
| | | | | | | | All going 20' long | 1230 | | | Lunch |
| | | | | | | | MA Chamness arrives | 1230 | | | Start on Compressor |
| | | | | | | | | | | | Drill |
| | | | | | | | | 1410 | | | Stopped drilling, adjusting compressor |
| | | | | | | | | 1415 | | | Drilling |
| | | | | | | | | 1425 | | | Stopped water hose, back |
| | | | | | | | | 1430 | | | Finished drilling |
| | | | | | | | Air Hammer stopped because of great chips falling in from drill stem | 1435 | | | Air Hammer stopped 1800.003 (0590) have to pull tools back out of hole |

W = wet, M = moist, D = dry HMA Oppm
LEL of

DAILY BOREHOLE LOG

Boring or Well Number 699-42-E9B
 Location North of Ryepld

Depth 233 - 250 Sheet 1 of 4
 Project Sevage Island

Logged by SS Teel / MA Chavness SS Teel MA Chavness Date 3/15/91
 Print Sign

Reviewed by _____ Date _____
 Print Sign

Lithologic Classification Scheme N/A Procedure Do-1, Do-5 Rev No 1.0

Measuring Equipment N/A

Drilling Contractor Jensen Drilling
 Driller Art Gwinn, Rod Nordquist
 Rig/Method Air Hammer / Speedstar 55-15 III

| DEPTH | SAMPLES | | CONTAMINATION | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O
ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) | |
|-------|---------|-----|----------------|----------|-------------|--|------|---------------------------|---|--|
| | TYPE | NO. | INSTRUMENT | READING | | | | | CASING | |
| | | | | | | | 0715 | | | On-site, Drillers cleaning |
| | | | | | | | | | | Air hammer |
| | | | | | | | 0730 | | | Calibrate HNU + LEL/O ₂ meter |
| | | | HNU | Open | | Span set @ 4.70 to read 56 ppm | 0850 | | | Check borehole |
| | | | LEL | 0% | | | 0900 | | | Hammer is cleaned-out. Starting |
| | | | O ₂ | 20.850 | | Note: Air compressor discharge rate is | | | | to trip-in. Well guard or |
| | | | | | | 250 psi (1250 cfm) and no surfactants | | | | RDN oil used on tool joints. |
| | | | | | | are being used. | 1015 | | | Drilling |
| | | | | | | Basalt - ^{porphyritic} black, fresh, slightly vesicular, | 1038 | | | Sampled from air discharge. |
| | | | | | | microphenocrysts. Water is still somewhat rust- | | | | Driller says some water is coming- |
| | | | | | | colored. Small vesicles. Filled w/ green/blue | | | | in - more water can be seen in the |
| | | | | | | (56-42 to 525/1 grayish green to bluish | | | | discharge than he is adding |
| | | | | | | gray) clay, chlorophyllite (?), fine-grained | | | | Sample from air discharge hose |
| | | | | | | Hit interflow zone at 242', dk brown to | 1043 | | | Water-bearing zone @ 243' |
| | | | | | | reddish brown, clayey, vesicular, with rust | | | | Drills very easily |
| | | | | | | vesicles. Filled w/ ^{pyrite} pieces of | | | | |
| | | | | | | baked, siliceous sediment or precipitate. | | | | |
| | | | | | | Microphytic | 1045 | | | Adding drill stem |
| | | | | | | | 1116 | | | Drilled |
| | | | | | | Still interflow zone, more dense basalt | 1125 | | | Sampled from air discharge |
| | | | | | | pieces, may be getting into base of hole | | | | |
| | | | | | | fine-grained. | | | | |

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-42-E4B</u>		Depth <u>250-260'</u>		Sheet <u>2</u> of <u>4</u>					
Location <u>North of Riggold</u>		Project <u>Savage Island</u>							
Logged by <u>SS Teel / MA Chalmers</u>		SS Teel		Date <u>2/15/90</u>		Drilling Contractor <u>Jensen Drilling</u>			
Reviewed by _____		Sign _____		Date _____		Driller <u>Art Gwinn, Rnd Nordquist</u>			
Lithologic Classification Scheme <u>N/A</u>		Procedure <u>DO-1, DO-5</u>		Rev No <u>1.0</u>		Rig/Method <u>Air Hammer / Speedstar SS-15 III</u>			
Measuring Equipment <u>N/A</u>									
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE, SHAPE, MINERALOGY,
GROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	CASING	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)
					250 cont'd vesicle fillings + baked sed.				
					chunks are more blue/green, whereas last				
					sample ranged from white to blue green,				
					nd gray-green sed. chunks				
					Basalt - some is still reddish brown, most	1120			Sampled from air discharge
					is purplish black, pieces of siliceous rock				Driller estimates water flow
					precipitate are 55-60% (pale green), remaining				at 40-50 psi/min out of hole,
					less common. Purplish basalt is denser, some				is only adding 2 gal/min.
					vesicles, microphonic, not glassy. The	1155			Stopped to adjust rig + air discharge
					redder, more vesicular basalt may be				
					carried down from above.				
						1150			Rocks have fallen in at top of
									air hammer, can't move it
									up, stopped for lunch
									Drilling, getting hammer free.
						1230			Sampled from air discharge,
					Basalt, black to greenish black, some pieces	1240			drilling slower
					are vesicular, others are solid, vesicular pieces				
					have green/blue clay filling vesicles. Some				
					blue/green clay material + reddish				
					basalt probably from 1230. Microphonic, all,				
					fine-grained.				

W = wet, M = moist, D = dry

A-1800-003 (05/90)

DAILY BOREHOLE LOG

Boring or Well Number 699-42-E9B
 Location W of Pingold

Depth 260 - 280 Sheet 3 of 4
 Project Savage Island

Logged by SS Teel / MA Channess
 Print

MA Channess Date 2/15/91
 Sign

Reviewed by _____
 Print

 Sign

Lithologic Classification Scheme NA

Procedure D-1, D-5 Rev No 1, D

Measuring Equipment 2-tape 11053

Drilling Contractor Jensen Bros.
 Driller Art Gunn, Rod Nordquist
 Rig/Method air hammer SS 15 JII

| DEPTH | SAMPLES | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-------|---------|---------------|------------|----------|-------------|---|------|------------------------|--|---|
| | TYPE | NO. | INSTRUMENT | READING | | | | | CASING | |
| 265 | lith | 2 | | | | Basalt - probably still black to greenish black, fresh, dense to slightly vesicular. There is a lot of material from above mixed in though, so sample is not very representative. | 1250 | | | Sampled from air discharge, driller received hole just before getting sample, so there is a lot of material from above. |
| 270 | lith | 2 | | | | Basalt - sample ~ 1/2 slightly vesicular, black, fresh, fine-grained w/ microphenocrysts. The other 1/2 is 55-60% (pale green) clay. Apparently have hit another pocket of clay material since it drills so easy & there is great increase in amount of clay. | 1314 | | | Drilling harder, measuring water, coming in ~ 5' / 15 sec. |
| 275 | lith | 2 | | | | Basalt - dense, slightly vesicular in some places, much less green clay. Black, fine-grained w/ microphenocrysts. Many of the vesicles are empty. | 1322 | | | Sampled from air discharge, tested drilling very easy @ 266.5' |
| 280 | lith | 2 | | | | Basalt, dense, fresh, fine-grained w/ micro-phenocrysts. Fracture surfaces (old) show some clay. Black, no clay at all. There is a little of greenish material. | 1327 | | | Sampled from air discharge starts drilling harder @ 277', hardest so far. |
| | | | | | | | | | | Sampled from air discharge, drilling hard. |

W = wet, M = moist, D = dry

Depth 280' - 285 Sheet 4 of 4

Drilling Contractor Sensen Bros.

Driller Art Gwin, Rod Nordquist

Rig Method A/C Hammer ≤ 15 III

[illegible]

A-1800-003 (05/90)

DAILY BOREHOLE LOG

Boring or Well Number

699-42-E9B

Depth

285'

Sheet

1

of

3

Location

N of Ringold

Project

Swavage Island

Logged by

SS Teel

Print

Drilling Contractor

Jensen Drilling

Reviewed by

Print

Driller

Art Gwin

Lithologic Classification Scheme

N/A

Procedure

GL-1, GL-3, GL-7, GL-8 Rev No 00000

Rig/Method

Speedstar SS-15 III / Air Hammer

Measuring Equipment

500' tape LS00-16 e tape 11053

Date

3/18/91

| DEPTH | SAMPLES | | CONTAMINATION | | % DIS-
TURE | GRAPHIC
LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O
ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) |
|-------|---------|-----|---------------|---------|----------------|----------------|--|------|---------------------------|---|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | |
| | | | | | | | SS Teel + AW Pearson arrive on site | 0708 | | |
| | | | | | | | P/water = 26.7 - 4.0' = 22.7 w/ | 0130 | | |
| | | | | | | | C-tape # 11053 | | | |
| | | | | | | | D/bottom = 286.5' + 2.83' - 4.0' = 285.33' | | | |
| | | | | | | | v/1 PNL 500' tape # LS00-16 | | | |
| | | | | | | | Calibrate HNU + LEL/02. HNU span set | 0755 | | Begin Natural Gamma Logging |
| | | | | | | | @ 8.17 to read 56 ppm. | 0756 | | |
| | | | | | | | Interval 284.8 - 200.0' | 0820 | | Check borehole |
| | | | | | | | | 0822 | | Completed Natural Gamma Log |
| | | | | | | | | 0915 | | Begin Caliper Log |
| | | | | | | | | 0922 | | Ed Enloe on Site |
| | | | | | | | Interval 284.4 - 220.0' | 0940 | | Completed caliper log |
| | | | | | | | | 1010 | | Begin Magnetic log. Ed leaves site. |
| | | | | | | | Interval 284.0 - 220.0' | 1030 | | Completed Magnetic log |
| | | | | | | | | 1115 | | Begin SP + R Log |
| | | | | | | | Interval 284.1 - 220.0' | 1150 | | Complete SP + R Log |
| | | | | | | | Span set @ 9.08 to read 56 ppm (different | 1300 | | Calibrate HNU + LEL/02 |
| | | | | | | | probe than previously used | | | Bob Jones + Dennis Minale on |
| | | | | | | | | | | site |
| | | | | | | | | | | Check Borehole |
| | | | | | | | | | | |

W = wet, M = moist, D = dry

A-1800-003 (05/90)

Boring or Well Number 699-42-C9B
Location N of Ringold

Depth 285' Sheet 2 of 3
Project Savage Island

Logged by SS Teel Print Sign Date 3/18/91

Reviewed by _____ Date _____
 _____ Sign _____
 _____ Print _____

Lithologic Classification Scheme N/A Procedure AT-6 Rev No 0

Measuring Equipment Steel Tape L300-16

| DEPTH | SAMPLES | | CONTAMINATION | | MOD-
TURE | GRAPHIC
LOG | LITHOLOGIC DESCRIPTION
PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL ETC.) | TIME | H ₂ O
ADDED | CASING | DRILLING COMMENTS
DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) |
|-------|---------|-----|---------------|---------|--------------|----------------|--|------|---------------------------|--------|--|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | | |
| | | | | | | | Tyler Gilmore / Jane Braghese on Site | 1400 | | | |
| | | | | | | | Set up to run Slug test; Slug and Pump | | | | |
| | | | | | | | on site; run irrigation line (~1000') | | | | |
| | | | | | | | ent away from Rig | | | | |
| | | | | | | | For aquifer test see Aquifer test | | | | |
| | | | | | | | logs 3/18/91 | | | | |
| | | | | | | | Note on Sediments from investigation zone | | | | |
| | | | | | | | Many chunks of bslt are rounded, | | | | |
| | | | | | | | well-sorted, very vesicular filled w/ clay; | | | | |
| | | | | | | | pieces of bslt 2" across survived bit; | | | | |
| | | | | | | | Zone appears very "runny" | | | | |
| | | | | | | | After slug test will develop well for | 1400 | | | Slug Test |
| | | | | | | | water samples | | | | |
| | | | | | | | Pump is Givens type 255 5hp | 1430 | | | Run discharge line out |
| | | | | | | | Model Number 22450370004 | | | | |
| | | | | | | | Set pump at 82' b/s; (4) 21' pipe + | 1450 | | | Set pump |
| | | | | | | | 2.5' to intake | | | | |
| | | | | | | | ~ possible | | | | |

W = wet, M = moist, D = dry

A-1800-003 (05/90)

47

DAILY BOREHOLE LOG					Boring or Well Number <u>699-45-E9B</u>		Depth <u>285'</u> Sheet <u>3</u> of <u>3</u>			
Location <u>North of Ringold</u>					Project <u>Seage Island</u>					
Logged by <u>Tyler Gilmore</u>
Print					Date <u>3/18/91</u>
Sign		Drilling Contractor <u>Jensen Drilling</u>			
Reviewed by <u>Tyler Gilmore</u>
Print					Date <u>3/19/91</u>
Sign		Driller <u>Art Gwin</u>			
Lithologic Classification Scheme <u>N/A</u>					Procedure <u>AT-6</u>		Rev No <u>0</u>			
Measuring Equipment <u>Campbell II Scientific Transducer System</u>							Rig/Method <u>Air Rotary / Speedstar SS-15 III</u>			
DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
PARTICLE SIZE DIST. SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
	TYPE	NO.	INSTRUMENT	READING						
							(1) Corehole Volume = ~ 100 gal H ₂ O			Static 324
D/S 315 = 26.3' x 4.08 gal/ft =
1020 gal
							Take samples at 3 corehole volume (BHV)			
							[Test Plan] 6 BHV			
							(way vary) 9 BHV	1715		Test Pump - works
							See Aquifer test notes 12 BHV			Set up Flowmeter
							50 BHV			
							75 BHV			
							100 BHV			
							+ End of Test			
							Will Monitor Turbidity, pH and Conductivity			
							to determine water zone			
							Test Starts	1816		Start Development Test
							Pump rate 40 gpm still drawing down	1830		
							slowly			
							Alan Pearson / Steve Teel arrive	1830		
							to run test is until 1200 MW			
							Steve Auland / Terrell Levenson			
							Arrive to run test until 1200 3/19	1900		New Day 3/19/91
							Seven water samples collected by			
							0700			
							T Gilmore / Jane Boylston arrive	1900		

42

DAILY BOREHOLE LOG

Boring or Well Number 699-42-E9B Depth 285 Sheet 1 of 1
 Location Northeast Ridge Project Savage Island

Logged by T Gilmore Print

Drilling Contractor Jensen Drilling
 Driller Art Gwilt

Reviewed by _____

Date 3/19/91

Lithologic Classification Scheme N/A

Procedure D-1, D-5 Rev No 1.0

Measuring Equipment N/A

| DEPTH | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-------|---------------|-----|----------|-------------|---|------|------------------------|--|-------------------------------|
| | TYPE | NO. | | | | | | CASING | |
| | | | | | Pen Agiler test/Development Test All | 700 | | | Testing Interflow Zone |
| | | | | | Wig by Jane Boese/Tyler Gilmore | | | | |
| | | | | | Arrive to Relieve S. A. Hunt/D. Newman | | | | |
| | | | | | Drillers on Site | 700 | | | |
| | | | | | K. Olsen on Site | | | | |
| | | | | | Water Samples each Suite includes - | | | | |
| | | | | | I-129; H ₂ ; Ispenebals; Blank; Alkalinity; Biot; . | | | | |
| | | | | | Anions - Samples taken at | | | | |
| | | | | | Time 10:00 4:5 = 1500 gal | 1130 | | | Turn Pump off |
| | | | | | 2100 8 | 1205 | | | Recovery Test |
| | | | | | 2215 10 | 1310 | | | Pull equipment out |
| | | | | | 2323 12 | 1315 | | | Pull pump out of well |
| | | | | | 0056 18 | | | | D/B 285 6 ft bls |
| | | | | | 0230 22 | | | | (Did not lose any hole) |
| | | | | | 0506 28 | 1345 | | | Rover Tremmie inc agent |
| | | | | | 0910 34 | 1345 | | | Tremmie In |
| | | | | | 1130 45 | 1430 | | | Mix Cement (See Cement Notes) |
| | | | | | Add 180 gal (1.2 x 150 gal) to 230' | 1500 | | | Finish Cement |
| | | | | | Weight was 14.6 lb/gal - | | | | |
| | | | | | water-level rose to 10 ftls time interval back | 1510 | | | Pull 50' of Tremmie Pipe |
| | | | | | the static alk'ls in about 15 min | | | | |
| | | | | | | 1.3 | | | End of Day |

W = wet, M = moist, D = dry

A-1800-003 (05/90)

FIELD ACTIVITY REPORT - CEMENT CALCULATIONS

Page 1 of 1

Date

Well Number

Continuation of Report No.

1.0 CEMENT STAGE VOLUME CALCULATIONS

1.1 Cement Volume - Open Hole/Casing 10 ID of casing or diameter of hole, inches = D

55 feet x 0.0408 x 100 D² = 224 Gallons of cement required

55 feet x 0.005454 x 100 D² = 30 Cubic feet of cement required

1.2 Cement Volume - Annular Spaces

☐ Between Tubing and Hole (D = Hole diameter, inches; d = OD of Tubing, inches)

☐ Between Casing and Hole (D = Hole diameter, inches; d = OD of Casing, inches)

☐ Between Tubing and Casing (D = ID of Casing, inches; d = OD of Tubing, inches)

☐ Between Casings (D = ID of outer Casing, inches; d = OD of inner Casing, inches)

D = _____ d = _____ n = Number of tubing strings

_____ feet x 0.0408 x [_____ D² - (_____ d² x _____ n)] = _____ Gallons of cement required

_____ feet x 0.005454 x [_____ D² - (_____ d² x _____ n)] = _____ Cubic feet of cement required

2.0 SLURRY MIX CALCULATIONS

2.1 Calculate Sacks of Cement Type: I+II lbs/sack: 94 ft³/sack (mixed): 1.36

30 ft³ (cement - from 1.0) ÷ 1.36 ft³/sack (mixed) = 22.0588 sacks

22 sacks + 5.5 sacks excess (25 % required) = 27.5 Total sacks required

2.2 Calculate Mix Water (@ 28 Gal.)

27.5 Total sacks cement x 6.5 gallons water/sack = 178.84 gallons of mix water required

2.3 Calculate Additive Amounts

Type Bent 27.5 Total sacks x 94 lbs/sack x 2 % = 51.7 lbs. required
Cement Additive

Type CaCl₂ 27.5 Total sacks x 94 lbs/sack x 2 % = 51.7 lbs. required
Cement Additive

85% = 43.9

3.0 DISPLACEMENT VOLUME CALCULATIONS

3.1 Balanced Plug Displacement

230 ft. (top of cement) - 22 ft. (water level) = 208 feet to be displaced

208 ft. (to be displaced) x 0.11632 gal/ft. = 33.9 gallons of displacement water required

4.0 REMARKS

Cement delivered dry in truck and mixer at Site
Weight 14.6 lb/gal

Report By B. Palmer 3/19/91

Title _____

Signature _____

Reviewed By Bob Jones WMC

Title _____ Date 3/19/91

Signature _____

DAILY BOREHOLE LOG					Boring or Well Number <u>699-42-59B</u>		Depth <u>354</u> Sheet <u>2</u> of <u>2</u>	
					Location <u>North of Ringold</u>		Project <u>Savage Island</u>	
Logged by <u>T. Guilmore</u> Print					Signature <u>[Signature]</u> Sign		Date <u>3/25/91</u>	
Reviewed by _____ Print					Signature _____ Sign		Date _____	
Lithologic Classification Scheme <u>N/A</u>					Procedure <u>Do-1, Do-5</u>		Rev No. <u>1,0</u>	
Measuring Equipment <u>e. tape 11053</u>								
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)
	TYPE NO.	NO.	PERCENT	READING				
					See form for Cement calculations	1235		Set up for Cement
					will use 32 Bags, 2700 Gal. G			
					Set up time will be 18 hours			
					w/ 32 Bags; psi strength at 18 hrs			
					is about 412			
					Flow water at 4562 to start cement	1300		D/W 28.4
					Tried to circulate water in borehole 1325			
					to determine approx amount of cement			
					we might lose to formation, pumped			
					~ 100 gal raised w/h to 15' below			
					casing			Mix Cement
					Water level came up slowly for ~ 600 gal	1415		Pump Cement (Cement at 1325 ft)
					then faster (= rate pumping)			
					Water level dropping very slowly in	1500		Stopped pumping cement
					well			
					Having problem w/ pump can't pump			
					displacement water to chase cement			
					Tremmie at 222' - Circulate cement above	1615		
					222' end of hole - cement sealed off formation			
					Pull Tremmie out	1700		
						1730		End of Day

W = wet, M = moist, D = dry

FIELD ACTIVITY REPORT - CEMENT CALCULATIONS

Page 1 of 1

Date 3/25/91 Well Number 69A-42-E9B Continuation of Report No. _____

1.0 CEMENT STAGE VOLUME CALCULATIONS

1.1 Cement Volume - Open Hole/Casing 10" ID of casing or diameter of hole, inches = D

$$\underline{124} \text{ feet} \times 0.0408 \times \underline{100} D^2 = \underline{505.92} \text{ Gallons of cement required}$$

$$\underline{124} \text{ feet} \times 0.005454 \times \underline{100} D^2 = \underline{67.62} \text{ Cubic feet of cement required}$$

1.2 Cement Volume - Annular Spaces

☐ Between Tubing and Hole (D = Hole diameter, inches; d = OD of Tubing, inches)

☐ Between Casing and Hole (D = Hole diameter, inches; d = OD of Casing, inches)

☐ Between Tubing and Casing (D = ID of Casing, inches; d = OD of Tubing, inches)

☐ Between Casings (D = ID of outer Casing, inches; d = OD of inner Casing, inches)

D = _____ d = _____ n = Number of tubing strings

$$\text{_____ feet} \times 0.0408 \times [\text{_____} D^2 - (\text{_____} d^2 \times \text{_____} n)] = \text{_____} \text{ Gallons of cement required}$$

$$\text{_____ feet} \times 0.005454 \times [\text{_____} D^2 - (\text{_____} d^2 \times \text{_____} n)] = \text{_____} \text{ Cubic feet of cement required}$$

2.0 SLURRY MIX CALCULATIONS

2.1 Calculate Sacks of Cement Type: I & II lbs/sack: 94 ft³/sack (mixed): 1.455

$$\underline{67.6} \text{ ft}^3 \text{ (cement - from 1.0)} \div \underline{1.36} \text{ ft}^3/\text{sack (mixed)} = \underline{49.7} \text{ sacks}$$

$$\underline{50} \text{ sacks} + \underline{45.7} \text{ sacks excess (} \underline{105} \% \text{ required)} = \underline{95} \text{ Total sacks required}$$

2.2 Calculate Mix Water

$$\underline{95} \text{ Total sacks cement} \times \underline{7.15} \% \text{ } \underline{6.5} \text{ gallons water/sack} = \underline{679.25} \text{ gallons of mix water required}$$

2.3 Calculate Additive Amounts

$$\text{Type } \underline{\text{Bent}} \quad \underline{95} \text{ Total sacks} \times \underline{94} \text{ lbs/sack} \times \underline{2} \% = \underline{178} \text{ lbs. required}$$

$$\text{Type } \underline{\text{CaCl}_2} \quad \underline{95} \text{ Total sacks} \times \underline{94} \text{ lbs/sack} \times \underline{2} \% = \underline{178} \text{ lbs. required}$$

3.0 DISPLACEMENT VOLUME CALCULATIONS

3.1 Balanced Plug Displacement

$$\text{_____ ft. (top of cement)} - \text{_____ ft. (water level)} = \text{_____ feet to be displaced}$$

$$\text{_____ ft. (to be displaced)} \times \text{_____ gal/ft.} = \text{_____ gallons of displacement water required}$$

4.0 REMARKS

Report By _____
Title _____
Signature _____

Reviewed By _____
Title _____ Date _____
Signature _____

DAILY BOREHOLE LOG

Boring or Well Number 699-42-E9B
Location North of Ringfield

Depth 354' Sheet 1 of 4
Project Savage Island

Logged by T. Billmore
Print

J. J. Billmore
Sign Date 5/26/91

Drilling Contractor Jensen Drilling
Driller Art Gwilt

Reviewed by _____
Print

Lithologic Classification Scheme N/A
Procedure Do-1, Do-5 Rev. No. 1, 2

Rig/Method Speedstar 35-153E Air rotary

Measuring Equipment 300-16 Steel Tape

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-------|---------|-----|---------------|---------|----------|-------------|---|------|------------------------|--|----------|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | CASING | |
| | | | | | | | Geologist and Driller, Art Gwilt and Dennis Mingo on site | 300 | | | |
| | | | | | | | Depth to Cement 202' bls | 305 | | | |
| | | | | | | | No TEL or HNL readings because borehole is cemented | | | | |
| | | | | | | | Switch to tri-cone bit to drill cement | 310 | | | |
| | | | | | | | Tri-cone should stay in borehole better than Air-hammer (Well Guard used as lubricant) | | | | |
| | | | | | | | Note: An iridescence on water in borehole same hydraulic fluid from pump? | | | | |
| | | | | | | | Talked to driller and Pat Geller (KEH) to switch out grout pump. The pump on site has had problems each time we grout and leaks hydraulic fluid | | | | |
| | | | | | | | Cement coming up is slightly "green" it is not fully set up. chips are soft can be crushed, not hard and brittle | 1019 | | | Drilling |
| | | | | | | | ~ 1000 ft | | | | |

DAILY BOREHOLE LOG				Boring or Well Number <u>699-42-E9B</u>		Depth <u>354'</u>	Sheet <u>2</u> of <u>4</u>
Location <u>Not Ringed</u>				Project <u>Savage Island</u>			
Logged by <u>T Gilmore</u>		Print		Sign <u>T. Gilmore</u>		Date <u>3/26/91</u>	
Reviewed by		Print		Sign		Date	
Lithologic Classification Scheme <u>N/A</u>		Procedure <u>Do-1, Do-5</u>		Rev No. <u>1.0</u>			
Measuring Equipment <u>L-300-16 Steel tape</u>						Drilling Contractor <u>Tensen Drilling</u>	
						Driller <u>Art Gussner</u>	
						Rig/Method <u>Speedstar 33-157M / Air Rotary</u>	

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | CASING | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) |
|-------|---------|-----|---------------|---------|----------|-------------|--|------|------------------------|--------|--|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | | |
| | | | | | | | At 265' still drilling cement - water is not coming in and no trace of either cement or bit in discharge | 1100 | | | |
| | | | | | | | At 270' picked up 10% bit w/ gravelly in discharge, very slight increase in water - Drilling slower | 1145 | | | |
| | | | | | | | At 275' approx 25% bit in discharge approx 1 gal/min | 1200 | | | |
| | | | | | | | At 285' add wt to drill string, bit went back into original borehole all discharge was cement - no bit | 1244 | | | |
| | | | | | | | Water discharge increased at about 315' to 5 gpm | 1330 | | | |
| | | | | | | | At 355' Measured in w/ Steel Tape 1425 to double check | | | | |
| | | | | | | | At 355' drilled out of cement and into bit - very wetland, vesicular, gray clay, to be gray and 11 g clay fillings | | | | |
| | | | | | | | | | | | Drilling slow |

62

DAILY BOREHOLE LOG				Boring or Well Number <u>699-42-E9B</u>		Depth <u>354-375</u>	Sheet <u>3</u> of <u>4</u>
				Location <u>North of Rungold</u>		Project <u>Savage Island</u>	
Logged by <u>T Gilmore</u>				Sign <u>T Gilmore</u>		Date <u>3/26/91</u>	
Reviewed by <u>Print</u>				Sign <u>Print</u>		Date <u>Print</u>	
Lithologic Classification Scheme <u>N/A</u>				Procedure <u>Do-1, DO-5</u>		Rev No <u>1.0</u>	
Measuring Equipment <u>300-16</u>				State <u>Tape</u>			
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE, SORTING, MINERALOGY,
ROUNDEDNESS, etc. REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED
360'	Lith 2				At 359' pick up rd-brn. vesicular
rubby lsst - water changed color
Welded Tuff? - very hard drills like
basalt dk gray N/4 granular w/
clasts of clg mineral (clivine) alteration
clys, Fe stn minerals, formation
producing some more water w/ spin
Vesicular Blt at 364' 20-30 gpm 1517
Basalt - Rd brn, very vesicular
Vesicles form 2mm up to 10mm
across, vesicles not clay filled
formation contains water, granular
matrix, some gran mineral grains
(clivine)
Basalt - Black (tr red brn), coarse
grained some clv - milky wht crystals
in cavities up to 3mm long
(Smadine?) some vesicles various
sizes
Basalt - BLK w/ shades of grn, granular 1638
w/ visible olivine and plagioclase crystals
drilling hard producing some amount of
water as previous	1448	
365'	Lith 2						
370'	Lith 2						
375'	Lith 2						

DRILLING COMMENTS
DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)

CASING

A-1800-003 (05/90)

W = wet, M = moist, D = dry

604

DAILY BOREHOLE LOG

Boring or Well Number 699-42-E9B
Location N. of RingoldDepth 388.67' Sheet 1 of 2
Project Savage IslandLogged by NA Channery
PrintNA Channery
SignDate 3/27/91Drilling Contractor Jensen BrosReviewed by _____
Print

Sign

Date _____

Driller Art Gwin, Dennis Mingo, Joe BeachLithologic Classification Scheme NAProcedure NO-1, NO-5 Rev No. 1, 0Rig/Method SS 15 IIIMeasuring Equipment 2-tape 11053 500' steel tape, no #

| DEPTH | SAMPLES | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-------|---------|---------------|------------|----------|-------------|---|------|------------------------|--|--|
| | TYPE | NO. | INSTRUMENT | READING | | | | | CASING | |
| | | | | | | | 700 | | | Pulling drill rod + bit out of hole. |
| | | | | | | Calibrated H ₂ O w/ same gas as before to slappm @ 9.6 spm | 745 | | | |
| | | | | | | Alan Pearson logging borehole w/ nat. K, caliper, SP+R, & magnetic probes. Nat. K indicates beds (vertical / interbed?) at 252'-254' + 380'-384'. | 820 | | | |
| | | | | | | NW=29.9' from top of casing, 3.93' stickup | 825 | | | |
| | | | | | | DW=25.87' bgs | | | | |
| | | | | | | Finished running caliper probe, hole usually 9.75" in diam., 12.5" @ ~375' is largest dia. | 1010 | | | The welded tuff at 300' yesterday is actually coarse-grained, pyritic basalt. Red brown vermicular basalt at 259' may be its flow top. Next Panama flow top prob. @ 305' at red brown vermicular zone. Possibly another flow begins @ 382' w/ the sandstone fragments incorporated w/ vermicular basalt. |
| | | | | | | Finished running magnetic probe, not much shown | 1110 | | | |
| | | | | | | Finished running SP+R, running camera thru interbed zone | 1210 | | | |
| | | | | | | DB 300' from top of casing + 2.6' (top) - 3.93' stickup = 208.67' bgs | 1320 | | | |
| | | | | | | DW=29.5'-3.93' = 25.57' bgs | 1325 | | | |
| | | | | | | | 1330 | | | |
| | | | | | | | 1340 | | | Preparing to weld 6" casing, OD = 6.6" Naking landing plate, |

A-1800-003 (05/90)

W = wet, M = moist, D = dry

DAILY BOREHOLEWELL COMPLETION LOG

Boring or Well Number 699-42-E9B
Location N. of Ringold

Sheet 1 of 2
Project Savage Island

Logged by MA Chamness Print MA Chamness Sign MA Chamness Date 3/28/91
Reviewed by _____ Print _____ Sign _____ Date _____
Measuring Equipment e-tape 11053 Procedure DO-5 Rev No. 0

Drilling Contractor Jensen Brothers
Driller Art Guin, Dennis Ninge, Joe Roach
Rig/Equipment SS15 III

Time	Casing/Screen				Annular Fill				Over-lap	Comments
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup	Add-on	Depth
720	Carbon Steel w/centralizers on back side	6"	61.85'							Calibrated HNU w/ same gas as before, 50 ppm w/ span @ B, E, HNU = Oppm, LEL ok
730	Carbon Steel w/ Centralizer	6"	20.85'							Welding 16"
	"	"	20.1'	✓						
	"	"	20.85'	✓						
	"	"	19.9'	✓						
	"	"	19.9'	✓						
	"	"	20.7'	✓						
	"	"	20.85'	✓						
	"	"	20.7'	✓						
	"	"	19.85'	✓						Casing is tight @ ~200'-285', have to push it;
1130	"	"	20.9'	✓						this is where bit wandered drilling out cement
1155	"	"	21'	✓						RPT came by, surveyed samples from 295'-350'
1200	"	"	20.95'							lunch.
	"	"	19.95'							will hold off putting sand for backfill in until casing is at 354', in case pieces of cement fall in while pushing casing down.
1255										N/W = 24.8' bgs, may not have equil. yet
1300										HNU = Oppm LEL ok
1305										calling around for generator for pumping tomorrow

DAILY BOREHOLE/WELL
COMPLETION LOG	Boring or Well Number	699-42-E9B	Sheet	2	of	2
	Location	N of Bards	Project	Seepage	Channel	

Boring or Well Number 699-42-E9B

Location N of Raleigh

Sheet 2

Project Swage Island

Logged by MA Chamness Pri

MA Channery
Sign

Date 3/28/91

Reviewed by _____ Print _____

Date _____
Sign _____

Date _____

Measuring Equipment steel tape (500', no #)

Procedure Do-S

Rev No. 0

Drilling Contractor Jensen Brothers

Driller Art Guin, Dennis Mayo, Joe Ragach

Rig/Equipment SS 15 III[illegible]

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-42-E9B
Location N. of Ringold

Project Sauvige Island Sheet 1 of 2

Logged by MA Chamness Print

MA Chawness Sign

Date 3/29/91

Reviewed by _____ Print _____

Sign

Date _____

Measuring Equipment 500' steel tape, no #
c. tape 11053

Procedure D-5

Rev No. Q

Time	Casing/Screen				Annular Fill				Over-lap	Comments	
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup			Add-on
7:50											HAUL calibrated, 50 ppm @ 8.6 span
											HAUL 0 ppm, LEL ok
											Art went to steam clean 5' st. steel blank that was shipped in.
											NS below ground surface
								1.6	2.6	383.8	DW = 24.1 kgs
9:40											Art back, preparing to cut packer off of screen w/ a grinder
	st. steel blank	5" ID	5.02'								
	10" slot st. steel	"	10.45'	15.56'							
	Screen + neoprene	6" ID	0.49'								
	packer										
10:45	st. steel screen,	5" ID									welding packer onto blank + blank onto short screen section
	10 slot	5" ID	20.25'	40.25'							making hook for lifting bail
11:30				36.21'							Running screen down hole, used some
12:45											WSP Guard lubricant around outside of packer to keep it from catching on welds
17:50											HAUL = 0 ppm, LEL ok
18:15											Bottom inside 2" tremmie =
											387.2 + 2.6 - 5.6 = 384.2' b/s
	st steel screen				384.2						Bottom of screen @ 384.2'

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-42-69B
Location N. of Ringold

Project Savage Island Sheet 2 of 2

Logged by SS Teel SS Teel Date 3/29/91
Print Sign
Reviewed by _____ Date _____
Print Sign
Measuring Equipment N/A Procedure N/A Rev No. N/A

Drilling Contractor Jensen Drilling
Driller Art Swin
Rig/Equipment Speedstar SS-15 III

Time	Casing/Screen				Annular Fill				Over-lap	Comments
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup	Add-on	Depth
1600										Tried to meas. D/Bottom in the annulus between the 6" and borehole wall.
										Tape kept hanging-up @ 257'. Tried several times to get past this - tape gets stuck at 257'. Call GV last to involve tech. Forum. The consensus was to pull the tape tight and go ahead and pour sand. If we keep pulling on the tape and it breaks it could cause the sand to bridge.
1615										Pulling tremie pipe.
1640						20-40 Sand	11 bags			Adding 20-40 sand - adding sand with a mason jar.
1725							1 bag			Adding 40-100 sand.
1735										Sand is Colorado Silica Sand, 100 lb bag
										Completed pouring sand; seal borehole with drill tools.
1740										Leave site

DAILY BOREHOLE LOG				Boring or Well Number <u>699-42-E9B</u>		Depth <u>388'</u> Sheet <u>1</u> of <u>4</u>					
				Location <u>North of Ringold</u>		Project <u>Seage Island</u>					
Logged by <u>T. Gilmore</u> Print				Sign <u>[Signature]</u>		Date <u>4/1/91</u>					
Reviewed by				Sign		Date					
Lithologic Classification Scheme <u>N/A Completion</u>				Procedure <u>DO-1 DO-5</u>		Rev No. <u>1, 2</u>					
Measuring Equipment <u>Steel tape</u>				L300-16							
DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASING	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
	TYPE	NO.	INSTRUMENT	READING							
							Drillers - Art Guin, Joe Beach and	700			
							Dennis Miner on site				
							Steel tape left in well from Friday 3/31				
							Calibrate HNU				
							Fish for steel tape down hole	710			
							Pull tape out; secure on Rig				
							Prepare to run 1" Tremmie Pipe				
							(So we can run steel tape through it)				
							(and be in a position to go out through tremmie)				
							While moving tremmie in, steel tape feed	910			
							Tremmie can not go past 75'				
							(Tremmie is 1" and 1 1/2 couplings)				
							Measure through tremmie w/ steel				
							tape, make it to 281.6' - this is				
							right at the dogleg in the well. This				
							also indicates sand went past this				
							dogleg				
							Will free 6" from 10" to maneuver	946			
							around to allow tremmie down past				
							tight spot (Put rags in well to catch				
							slag from cutting torch)				

DAILY BOREHOLE LOG										Boring or Well Number <u>699-42-E9B</u> Depth <u>388</u> Sheet <u>2</u> of <u>4</u>									
Location <u>North of Ringold</u>										Project <u>Savage Island</u>									
Logged by <u>T Gilmore</u> Print					Date <u>4/1/91</u>					Drilling Contractor <u>Tensen Drilling</u>									
Reviewed by					Date					Driller <u>Art Gwin</u>									
Lithologic Classification Scheme <u>N/A Completion</u> Procedure <u>DO-1 DO-5</u> Rev No. <u>1.0</u>										Rig/Method <u>Speedslow 33-15 III / Air rotary</u>									
Measuring Equipment <u>Steel Tape L300-16</u>																			
DEPTH		SAMPLES		CONTAMINATION		MOISTURE		GRAPHIC LOG		LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)		TIME		H ₂ O ADDED		DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)			
										Calculate top of sand to be at 345.3'									
										Top of screen at ~354'		10:15							
										Still cannot move tremmie down to						Ed Enloe (KEH safety) on site			
										few - catches at 239' - decide to									
										run pump in well and pump to									
										settle sand pack (pump is 1/2 hrs approx) 1109						Run pump in well			
										Call office for tech forum - talk to Stuart									
										Luttrell - need to verify level of sand and									
										cannot measure w/ steel tape options are									
										1) Geophysical log inside 6" 2) smaller tremmie									
										pipe 3) add more sand to ensure above screen									
										1) we don't have sonic log - gamma logs are						Note: If there was a bridge, moving 6" casing			
										being used on RCP wells 2) smaller tremmie						would have broken it			
										will not fit - steel tape could go past 281'									
										3) add more sand and there is a bridge below									
										281' it compounds problems									
										The pump will settle sand and if									
										there is a bridge it may break it.						Start Pump			
												12:05							

A-1800-003 (05/90)

73

Sheet 4 of 4

Project Savage Island

Date 4/1/91

Date _____

Rev No. 10Rev No. 10

A-1800-004 (05/90)

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-42-E9B

Boring or Well Number 0
Location N of Ringold

Project
Savage Island

Sheet 1 of 1

Date 4/2/91

Thibault *Thibault*
Print

Logged by - Calvin Print

Sign

Date _____

Reviewed by _____ Printed _____

Sign

Rev No. 170

Procedure

1-300

Most deaths are calculated because of gunshot

Casing/Screen						Annular Fill			Overtop		Comments
Time	Type	Diam-eter	Length	Stickup	Depth	Type	Quantity	Stickup	Add-on	Depth	
700						Slurry (46)				~24'	Measure w/ Steel Tape approx 24'
Prepare to mix more grout
No D/L because pump inline way
No H/W needed w/ grout in well
Calculated depths; Pump slurry below
fully hydrated
Pull 42' of Tremmie out now at 231'
740	Note: Pumping water from well while mixing Slurry
Start Pump at 740 (approx 30 gal) after 10:30
Pump Slurry Hydrate!										
800						Slurry	75 gal	(wt ~9.3 lb/gal)		~23'	
810						Slurry	75 gal	(wt ~9.3 lb/gal)		~19'	
825						Slurry	75 gal	(wt ~9.3 lb/gal)		~16'	
835						Slurry	95 gal	(wt ~9.3 lb/gal)		~13'	
845						Slurry	80 gal	(wt ~9.3 lb/gal)		~9'	Pull Tremmie out now at 105'
848						Slurry	80 gal	(wt ~9.3 lb/gal)		~6'	measure w/ steel Tape
900						Slurry	80 gal	(wt ~9.3 lb/gal)		~4'	measure w/ steel Tape
910						Slurry	80 gal	(wt ~9.3 lb/gal)		~5'	measure w/ steel Tape
925						Slurry	80 gal	(wt ~9.3 lb/gal)		17'	Prepare to mix cement Grout
935						Slurry	80 gal	(wt ~9.3 lb/gal)		17'	Grout returned to surface
1035						Cement Grout	40 gal	(wt ~14 lb/gal)		surface	Clean Equipment - Jane Berggren on Site
1040											to Direct Development Test - Phase See
											Aquifer Test notes this date

WELL DEVELOPMENT LOG

Well Number 229-42-E9B
 Location Six Mile Island
 Procedure PNL-MA-567, GC-7, Rev. 0

Start Date/Time 7/2/91 1354
 End Date/Time 1439 250
 Page 1 of 1

Well Depth 394.2 ^{bottom} Pump Depth (Intake) 349 Initial Water Level 26.35
 from TOC

Date	Time	Flow Rate	Turbidity	Person Meas.	Rec.	Comments
4/1	1323			JUR		at present level to 0-92 NTA
	1354	58.2/6.60m				1 standard 10200 12.5 NTA
	1355		15			sample for Turbidity
	1410		3.5			sampled - 10 ft to 16 ft below
						unable to sample - 10 ft to 16 ft below
						at this time are cloudy
						standard 5-12-2000
						1 standard 5-11-2000
						sample 2000-2000
			1.2 x 2 = 2.4			1410 sample
	1419		1 x 2 = 2			1419 sample
	1424	58.2/6.90m				
	1434		.4 x 2 = .8			sample

Note: Unless otherwise noted,
 the following units are assumed:
 Flow rate - gpm
 Turbidity - NTU
 Water Level - ft

Equipment:
 Make: HACH
 Model: 10200
 Serial #: 222903404

Jane V. Borker 7/2/91

cooling 354 - start 254
 bottom of pump 349'

1063 76

DRILL LOG		By <i>Borghese</i>	Rig <i>Servis</i>	Well Number <i>699-42-EG B</i>	Computer Number	Project or Work Order No.
Total Casing	Depth	Date <i>4/2/91</i>		Depth		Subcontract No.
Drill Method	Wet/Dry Sample	LITHOLOGIC DESCRIPTION
% Each Grain Size, Color, Roundness, Caliche, Etc.				
		Information for <i>Well Development</i>				
		<i>4 1/2 pump out at 30' - 1/2 hp pump</i>				
		<i>mix of fine clay @ 230 gpm</i>				
		<i>wt put to pump start 23' - 1/2 hp</i>				
		<i>w/ E-tape</i>				
		<i>using surges 1 1/2 hp pump</i>				
		<i>with back valve</i>				
		<i>Top of casing 1.6' above ground</i>				
		<i>D/B screen 33' 1/2' from ground surface</i>				
		<i>Bottom of casing at 354' -</i>				
		<i>will set pump at 350 for development</i>				
		<i>used to maintain the pump in pump on</i>				
		<i>+ while pumping, the surge rate, grab samples</i>				
		<i>Samples - used to monitor drops below</i>				
		<i>5 WTC + 400 pump 90' - 1/2 hp</i>				
		<i>recovers - 1/2 hp pump 90' - 1/2 hp</i>				
REMARKS:						
<i>See Log 1063</i>						

2 of 3

17

| DRILL LOG | | | | BY
<i>Boyd</i> | Rig
<i>Jensen's</i> | Well Number
<i>697-42-51B</i> | Computer Number | Project or Work Order No. |
|----------------------------|-------|--------------|----------------|--|------------------------|----------------------------------|-----------------|---------------------------|
| | | | | Date
<i>4/2/91</i> | | Depth | | Subcontract No. |
| Total Casing | Depth | Drill Method | Wet/Dry Sample | LITHOLOGIC DESCRIPTION
% Each Grain Size, Color, Roundness, Caliche, Etc. | | | | Drilling Comments |
| | | | | notes. pump was running | | | | |
| | | | | continuously from 4/1/91 7:30 to | | | | |
| | | | | 10:30 - then on at 11 | | | | |
| | | | | to when equipment from for | | | | |
| | | | | about 1 1/2 hrs - broke for | | | | |
| | | | | Lunch - 12:05 to 12:45 | | | | |
| | | | | began setting vibrational pump when | | | | 12:45 |
| | | | | needed to get to 350 | | | | |
| | | | | OK 26.35 | | | | 1338 |
| | | | | bun 70C 26.32 | | | | 1348 |
| | | | | pump on @ 1354 47.50 | | | | 1358 |
| | | | | flow rate @ 1354 (500 lb/hr) 45.4 gpm 49.70 | | | | 1401 |
| | | | | 51.0 | | | | 1407 |
| | | | | 51.95 | | | | 1419 |
| | | | | flow rate @ 1424 (500 lb/hr) 43.5 | | | | 1424 |
| | | | | 52.70 | | | | 1434 |
| | | | | 32.00 | | | | 1441 |
| REMARKS: | | | | | | | | |
| <i>See 1/2 page 4/2/91</i> | | | | | | | | |

3063

| DRILL LOG | | | By
Brykese
Date
4/12/91 | Rig
Jenn | Well Number
699-42-E9B | Computer Number | Project or Work Order No. |
|--|-------|--------------|----------------------------------|--|---------------------------|-----------------|---------------------------|
| | | | Date | Depth | | | Subcontract No. |
| Total Casing | Depth | Drill Method | Wet/Dry Sample | LITHOLOGIC DESCRIPTION
% Each Grain Size, Color, Roundness, Caliche, Etc. | | Time | Drilling Comments |
| | | | | WL - | 30.3 | 1444 | |
| | | | | | 20.0 | 1446 | |
| | | | | | 28.95 | 1449 | |
| | | | | | 28.70 | 1450 | |
| | | | | Act 6ft to have train repaired | | | |
| | | | | drill will pull pump and | | | |
| | | | | acure will when he returns | | | |
| | | | | @ 24:30 | | | |
| | | | | E-tape stuck @ about 26' | | | |
| | | | | below TOC - drilling will | | | |
| | | | | remove when pulling pipe. | | | |
| | | | | Volume pumped 45 gal/min x 15 min = 2025 gal | | | |
| | | | | NOTE: water was reading 35 gpm when we measured | | | |
| | | | | 45 gpm | | | |
| REMARKS: | | | | | | | |
| <div style="text-align: right;"> <i>Joe P. [Signature]</i>
 4/12/91 </div> | | | | | | | |

DAILY BOREHOLE LOG		Boring or Well Number <u>699-43-ENB</u>		Sheet <u>1</u> of <u>1</u>	
Location <u>North of Ringold</u>		Project <u>Savage Island</u>			
Logged by <u>T Gilmore</u>
Print		Drilling Contractor <u>Jensen Drilling</u>			
Checked by _____
Print		Driller <u>N/A</u>			
Lithologic Classification Scheme <u>N/A</u>		Rig/Method <u>N/A</u>			
Measuring Equipment <u>N/A</u>		Rev No. <u>N/A</u>			

[illegible]

A-1800-003 (01/90)

WELL COMPLETION SUMMARY

Project <u>Savage Island</u>	Well No. <u>699-32-22B</u> Temp. Well No. _____
Location <u>SE 8E 200E</u>	Coordinates <u>N31935 W21982</u>
Drilling Co. <u>Jensen Drilling</u>	Elevation: Casing <u>516.93</u> Brass Marker <u>514.53</u>
Driller <u>Art Gurn</u>	
Other (companies) _____	
Geologist(s) <u>TJ Gilmore, SS Teel, MA</u>	
<u>Chamness, AW Pearson</u>	

DRILLING METHOD

Drilling Method(s) air / mud rotary
air 0-101' 655.7' - 841.5' mud 101' - 655.7'
 Drilling Fluid 200E water, hydrogel (bent.) mud
 Other cedar chips, cellophane, paper

COMPLETION DATA

Drilled Depth 841.5
 Completed Depth 836.0
 Date Started 4/11/91
 Date Completed 8/16/91
 Static Water Level/Date 110.0 8/2/91

OTHER (check if performed)

☐ Well Abandonment	☐ Downhole TV Inspection
☒ Well Development	☒ Driller's Logs
☒ Aquifer Testing	☒ Pad
☒ Geophysical Log(s)	☒ Guardposts
☒ Lock and Cap	☒ Protective Casing

SCREEN

Type	Outer Diameter	Length	Slot Size	Interval
<u>6" telescoping st. steel screen</u>		<u>61.4</u>	<u>10</u>	<u>774.6 - 836</u>

TEMPORARY CASING

Type	Nominal Diameter	Max. Outer Diameter	Interval
<u>carbon steel</u>	<u>16"</u>		<u>22.17' - 0'</u>
<u>carbon steel MAC 8/14/91</u>			

PERMANENT CASING

Type	Nominal Diameter	Max. Outer Diameter	Interval
<u>carbon steel</u>	<u>16"</u>		<u>22.17' - 87.9'</u>
<u>carbon steel</u>	<u>10"</u>		<u>0' - 665.4' (OVER)</u>

ANNULAR SEAL/FILL

Type	Interval	Quantity	Volume
<u>silica sand (20-40 + 40-100)</u>	<u>760.8' - 836'</u>		
<u>backfill (slough)</u>	<u>836' - 841.5'</u>		
<u>bentonite slurry</u>	<u>73' - 760.8'</u>		
<u>cement grout</u>	<u>53' - 73'</u>		
<u>bentonite crumbles</u>	<u>21' - 53'</u>		
<u>cement grout</u>	<u>2' - 21'</u>		

PUMP

Type _____ Depth to Inlet _____ Date Set _____

ACCEPTANCE

Completed Well: Accept _____ Conditionally Accept MAC 12/8/92
 Reject _____

will accept well if ground water samples and purpose/use of well is unaffected by bentonite in the well. If there is an adverse effect, the well may be changed or abandoned.

Reviewed by J. McNamee Date 12-4-92 Depths are below land surface unless noted.

Permanent Casing

carbon steel 6"

- 778.68'

Annular Seal/Fill

Concrete
Cement grout (filled hole +
rebarbed)

- 0.5' - 2'

13 bags

0 - 772.65'

WELL INSPECTION REPORT

Well No. 699-32-22B Procedure DO-5 Rev. 0 Specification No. KEH-5236 Rev. 0
 Geologist(s) T.J. Gilmore, SS Teel, MA Chamness ECNs (list) _____

CLEANING/DECONTAMINATION	Inspection Method	Criteria	Accept	Reject	Date
Rig/Tools (initial)	Visual/Wipe (optional)		SST		4/3/91
Temporary Materials	Visual/Wipe (optional)		SST		4/4/91
Permanent Materials	Visual/Wipe (optional)		SST		7/31/91
Mtls Brought Onsite Later	Visual/Wipe (optional)		SST		7/31/91

MATERIAL STORAGE/PACKING	Inspection Method	Criteria	Accept	Reject	Date
Material Storage	Visual	2.1	SST		7/31/91
Material Packing/Seals	Visual	2.1	SST		7/31/91
Other _____					

LUBRICANTS/ADDITIVES/AIDS	Inspection Method	Criteria	Accept	Reject	Date
Lubricants	Visual	3.7 Food Grade Lubricants	75		4/15/91
Additives/Aids	Visual	3.7			

DRILLING METHOD	Inspection Method	Criteria	Accept	Reject	Date
Method	Visual	3.3	SST		7/18/91
Drilling Fluid	Visual	3.2, 3.7	MAC		7/18/91

STRAIGHTNESS TEST	Inspection Method	Criteria	Accept	Reject	Date
Well Straightness	Deviation survey every 100'		SST		7/18/91

COMPLETION	Inspection Method	Criteria	Accept	Reject	Date
Drilled Depth ^{Measured w/ logging truck and/or drill rig}	Steel Tape # N/A	G-W Mon. Plan	SST 75		6/17/91
Completed Depth	Steel Tape # N/A	G-W Mon. Plan	AWP		7/26/91

PERMANENT SCREEN/CASING	Inspection Method	Criteria	Accept	Reject	Date
Screen Type/Slot/Length	Engineers Tape, Visual	2.1.7, 3.3	SST		7/18/91
Screened Interval	Steel Tape #				
Casing Type/Size/Length	Engineers Tape, Visual		SST		7/18/91
Centralizers/Location	Engineers Tape, Visual		N/A		
Other _____					

FILTER PACK/ANNULAR SEAL	Inspection Method	Criteria	Accept	Reject	Date
Primary Filter Mtl/Place	Visual/Steel Tape# ^{Measured w/ drill rig}		SST		7/31/91
Second Filter Mtl/Place	Visual/Steel Tape# ^{Measured w/ drill rig}		SST		7/31/91
Annular Seal Mtl/Place	Visual/Steel Tape#	2.1.2, 3.3	AWP		8/2/91
Install Annul Seal	Visual/Steel Tape#	2.1.2, 3.3	AWP		8/2/91
Cement Type/Placement	Visual/Steel Tape#	2.1.2, 3.3	AWP		8/5/91
Overdrill Seal Method	Visual/Steel Tape#	N/A			

WELL PROTECTION	Inspection Method	Criteria	Accept	Reject	Date
Surface Pad Mtl/Place	Visual/Engineers Tape	2.1.2, 3.3	MAC		8/19/91
Surface Casing Mtl/Place	Visual/Engineers Tape	2.1.2, 3.3	MAC		8/19/91
Cap/Hasp/Lock	Visual		MAC		8/19/91

WELL SURVEYING/MARKING	Inspection Method	Criteria	Accept	Reject	Date
Well ID Stamped/Correct	Visual				
Well Surveyed/Toler Met	Review Survey Data		MAC		5/10/92

PUMP INSTALLATION	Inspection Method	Criteria	Accept	Reject	Date
Pump Decon/Preparation	Visual	N/A	N/A		
Installation/Placement	Visual/Engineers Tape	N/A	N/A		
Pump Operational	Observed Running		N/A		

Technical Review Complete 7/2/91

Date 12-4-92

AS-BUILT DIAGRAM

Boring or Well Number 699-32-27B

Sheet 1 of 5

Location SE of 200 E

Project Savage Island

Logged by T.J. Gilmore, SS Teel, NAC 40111-33

Date Well Started 4/1/91

Reviewed by W. J. McElroy

Date 12-4-92

Date Well Completed 8/10/91

Well Construction Data

Geologic/Hydrologic Data

| Description | Drill Bit
Construction
Diagram | Depth
in Feet | Sample Method | |
|-------------------------------------|--------------------------------------|------------------|-----------------------|---------------------------------------|
| | | | Lithologic
Diagram | Lithologic Description |
| concrete -0.5'-2' | | 5 | | SAND |
| cement grout 2'-21' | | 10 | | " |
| | | 15 | | " |
| 16" carbon steel casing | | 20 | | " |
| 22.17 to 87.9 ft | | 25 | | " |
| (Removal 0 to 22.17 ft) | | 30 | | " |
| | | 35 | | " |
| bentonite crumbles 21'-53' | | 40 | | " |
| | | 45 | | " |
| | | 50 | | " |
| | | 55 | | " |
| cement grout 53'-73' | | 60 | | " (low circulation at 53' to 60' 25') |
| | | 65 | | " |
| | | 70 | | " |
| | | 75 | | " |
| | | 80 | | " |
| | | 85 | | " |
| | | 90 | | " |
| | | 95 | | " |
| | | 100 | | " |
| hole drilled w/14 3/4" bit | | 105 | | GRAVEL |
| | | 110 | | SANDY GRAVEL |
| 10" Carbon Steel Casing | | 115 | | " |
| 0'-665.4' | | 120 | | " |
| | | 125 | | " |
| | | 130 | | " |
| | | 135 | | " |
| | | 140 | | " |
| | | 145 | | " |
| | | 150 | | " |
| 16" carbon steel casing to 778.6 ft | | 155 | | SANDY GRAVEL |
| | | 160 | | " |
| | | 165 | | " |
| | | 170 | | " |
| | | 175 | | " |
| | | 180 | | " |
| | | 185 | | " |
| | | 190 | | " |
| | | 195 | | " |
| | | 200 | | " |
| bentonite slurry 73'-760.8' | | 205 | | SANDY GRAVEL? (poor cuttings returns) |
| | | 210 | | " |
| | | 215 | | " |
| | | 220 | | " |
| | | 225 | | " |
| | | 230 | | " |
| | | 235 | | " |
| | | 240 | | " |
| | | 245 | | " |
| | | 250 | | " |

Drill Bit/Sample Method Used:

☐ Rotary

☒ Air Rotary

☐ Mud Rotary

☐ Air Percussion

☐ Back Hoe

☐ Auger

☐ Drive Barrel

☐ Hard Tool

☐ Split-Barrel

AS-BUILT DIAGRAM

Boring or Well Number 699-32-22B

Sheet 2 of 5

Location SE of 200E

Project Savage Is.

Logged by MA Chamness, TJ Gilmore, SE Teel

Date Well Started 4/11/91

Reviewed by J. M. Schan

Date 12-4-92

Date Well Completed

Well Construction Data

Geologic/Hydrologic Data

Description	Construction Diagram	Drill Bit	Depth in Feet	Sample Method	Lithologic Diagram	Lithologic Description
			170			SANDY GRAVEL? (poor cutting returns)
			175			" "
			180			" "
			185			" "
			190			(Decrease in grain size or % of gravel @ 186')
			195			" "
10" carbon steel casing			200			" "
0'-665.4'			205			" "
			210			" "
Percent Gravel 0'-772.65'			215			" "
			220			" "
hole drilled 1 1/4" bit			225			" "
			230			BLUE CLAY (starts @ 224'?)
			235			
			240			
			245			SANDY GRAVEL (starts @ 244')
			250			" "
6" carbon steel casing to 778.68'			255			" "
			260			" "
			265			" "
			270			(265-270' decrease in gravel size)
Bentonite slurry 73'-760.8'			275			SANDY GRAVEL
			280			" "
			285			" "
			290			" "
			300			" " (Lost circ. @ 300')
			305			MUDDY SAND 302'-304'
			310			SANDY GRAVEL
			315			" "
			320			MUDDY SANDY GRAVEL
			325			" "
			330			" "
			335			" "

Drill Bit/Sample Method Used:

☐ Rotary

☒ Air Rotary

☒ Mud Rotary

☒ Air Percussion

☒ Back Hoe

☒ Auger

☒ Drive Barrel

☒ Hard Tool

☒ Split-Barrel

AS-BUILT DIAGRAM

Boring or Well Number 699-32-22B Sheet 3 of 5
 Location SE of 2nd East Project Source Is

Logged by TJ Gilmore, SS Teel, MA Chamness

Date Well Started 4/11/91

Reviewed by J. K. McArthur

Date 12-4-92

Date Well Completed _____

| Well Construction Data | | | Depth
in Feet | Geologic/Hydrologic Data | |
|-----------------------------------|-------------------------|-----------|------------------|--------------------------|------------------------|
| Description | Construction
Diagram | Drill Bit | | Sample Method | Lithologic Description |
| | | | 340 | | MUDDY SANDY GRAVEL |
| | | | 345 | | " |
| | | | 350 | | GRAVELY SANDY MUD |
| | | | 355 | | MUDDY GRAVEL |
| | | | 360 | | " |
| | | | 365 | | SANDY GRAVEL |
| 10" Carbon Steel Casing | | | 370 | | GRAVEL |
| 0'-665.4' | | | 375 | | SANDY GRAVEL |
| | | | 380 | | " |
| Pervious Grout 0'-772.65' | | | 385 | | " |
| | | | 390 | | " |
| | | | 400 | | " |
| | | | 405 | | " |
| | | | 410 | | GRAVEL |
| 6" carbon steel casing to 778.68' | | | 415 | | MUDDY SANDY GRAVEL |
| | | | 420 | | GRAVELY CLAYSTONE |
| | | | 425 | | CLAYEY GRAVEL |
| | | | 430 | | CLAYSTONE |
| | | | 435 | | " |
| bentonite slurry 73'-760.8' | | | 440 | | CLAY |
| | | | 445 | | GRAVELY CLAY |
| | | | 450 | | " |
| | | | 455 | | " |
| | | | 460 | | MUDDY SANDY GRAVEL |
| | | | 465 | | " |
| hole drilled w/ 14 3/4" bit | | | 470 | | SANDY GRAVEL |
| | | | 475 | | GRAVEL |
| | | | 480 | | MUDDY SANDY GRAVEL |
| | | | 485 | | " |
| | | | 490 | | " |
| | | | 495 | | " |
| | | | 500 | | " |
| | | | 505 | | SANDY GRAVEL |

Drill Bit/Sample Method Used:

☐ Rotary ☒ Air Rotary ☐ Mud Rotary ☐ Air Percussion ☐ Back Hoe ☐ Auger ☐ Drive Barrel ☐ Hard Tool ☐ Split-Barrel

AS-BUILT DIAGRAM

Boring or Well Number 699-32-22B

Sheet 4 of 5

Location SE of 200 E

Project Savage Island

Logged by SS Teel, MA Chamness, TJ Gilmore

Date Well Started 4/11/91

Reviewed by JL MacLean

Date 12-4-92

Date Well Completed _____

Well Construction Data

Geologic/Hydrologic Data

Description	Construction Diagram	Drill Bit	Depth in Feet	Sample Method	Lithologic Diagram	Lithologic Description
			505'			
			510'			GRAVELLY MUD (starts @ 508')
			515'			"
			520'			"
Center unit 0'-772.65' →			525'			SLIGHTLY GRAVELLY MUD
10-in. Packer Pipe			530'			" " "
Packer 0'-665.4' →			535'			" " "
			540'			MUDY GRAVEL
			545'			CL. GRAVELLY MUD
			550'			GRAVELLY MUD
			555'			MUD
			560'			"
6" carbon steel casing to 772.65' →			565'			"
			570'			"
			575'			SANDY MUD
hole drilled w/ 14 3/4" bit →			580'			CL. SANDY MUD
			585'			GRAVELLY MUDY SAND
			590'			CL. GRAVELLY SANDY MUD
			595'			Mixed Sand & Gravel
			600'			SANDY MUD
			605'			" "
montmorillonite slurry 72'-770.8' →			610'			SANDY GRAVEL
			615'			" "
			620'			MUDY SANDY GRAVEL
			625'			" " "
			630'			" " "
			635'			BASALT (weathered)
			640'			" "
			645'			BASALT (less weathered 645-650')
			650'			BASALT (fresher)
			655'			" "
grouted + redrilled w/ 10" bit			660'			BASALT (fresh)
665.4' - 781'			665'			BASALT
			670'			BASALT? (no sample - incr. in drill rate @ 665')

Drill Bit/Sample Method Used:

☐ Rotary ☒ Air Rotary ☒ Mud Rotary ☒ Air Percussion ☒ Back Hoe ☒ Auger ☒ Drive Barrel ☒ Hard Tool ☒ Split-Barrel

AS-BUILT DIAGRAM		Boring or Well Number <u>699-32-22B</u>		Sheet <u>5</u> of <u>5</u>	
		Location <u>SE of 200E</u>		Project <u>Savage Is</u>	
Logged by <u>SS Teel, MA Chamness, TJ Gilmore</u>				Date Well Started <u>4/11/91</u>	
Reviewed by <u>J. J. [Signature]</u>				Date Well Completed <u>12-4-92</u>	
Well Construction Data		Geologic/Hydrologic Data			
Description	Drill Bit	Depth in Feet	Sample Method		Lithologic Description
	Construction Diagram		Lithologic Diagram		
		670			
		675			BASALT (vesicular w/ abundant clay)
		680			No sample
		685			BASALT (finegr, fresh)
		690			" "
		695			" "
		700			" "
		705			" "
		709			BASALT (slightly coarser + lighter color)
		715			BASALT (colanade?) water @ 712?
		720			BASALT
		725			"
		730			"
		735			BASALT - med grained
		740			BASALT
		745			"
		750			" (coarser gr. and pyrite on fract. surf. @ 751')
		755			BASALT
		760			" (med. crystalline @ 761')
		765			"
		770			"
		775			" (slightly coarser)
		781			BAKED CLAYEY TUFF/PUMICE (starts @ 776?)
		785			SILTY SAND
		790			" "
		795			" "
		800			" "
		805			" "
		810			CLAYEY SILTY SAND
		815			" " "
		820			SILTY SAND
		825			CLAYSTONE
		830			SILTSTONE
		835			SANDSTONE/SILTSTONE
		840			BASALT (w/ @ 838')

Well Construction Data:

- 6" carbon steel casing to 778.60'
- bentonite slurry 73' - 760.8'
- 40-100 silica sand to 760.8'
- neoprene packer
- 6" telescoping steel screen, 10 slot 774.6' - 836'
- 20-40 silica sand to ~ 764'

Drill Bit/Sample Method Used:

☐ Rotary
 ☒ Air Rotary
 ☐ Mud Rotary
 ☐ Air Percussion
 ☐ Back Hoe
 ☐ Auger
 ☐ Drive Barrel
 ☐ Hard Tool
 ☐ Split-Barrel

699-32-22B

CALIPER INCHES 5 20 0 GROSS GAMMA CPS 200

CALIPER INCHES 5 20 0 GROSS GAMMA CPS 200

699-32-22B

[illegible]

A-1800-003 (05/90)

DAILY BOREHOLE LOG

Boring or Well Number 699-32-22B Depth 0-15' Sheet 1 of 4
 Location SE of 200 E Project Sitewide

Logged by SS Teel Print _____ Date 4/11/91
 Reviewed by _____ Sign _____ Date _____
 Lithologic Classification Scheme Folk Procedure D0-1, 5 Rev No. L10
 Measuring Equipment N/A

Drilling Contractor Tensen Drilling
 Driller Art Ewin - Driller, Dennis Mingle - helper
 Rig/Method Speedstar SS-15 III, rotary

| DEPTH | SAMPLES | | CONTAMINATION | | MOIS-
TURE | GRAPHIC
LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O
ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) | | |
|-------|---------|-----|---------------|---------|---------------|---|--|------|---------------------------|---|--------------------------------|------------------------|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | CASING | | |
| | | | | | | 5' | Bit is 14 3/4" OD, tri-cone type | 0700 | | 20.12 | On site | |
| 5' | lith | 2 | | | Dry | | SAND (49% sand, 1% gravel) 1% VFP, 9% MS | 0750 | | | | Drilling w/ Air rotary |
| | | | | | | | 50% FS, 40% VFS, trace silt. Very well sorted. | | | | | Sample from air hose |
| | | | | | | | 25% platies, 75% qtz & si-rich. Unconsol. | | | | | |
| | | | | | | | 2.5V 1/2 light brownish gray. Strong reaction to | | | | | |
| | | | | | | 10% HCL, well representative | | | | | | |
| | | | | | | 15' | | | | | | |
| 10' | lith | 2 | | | Dry | | SAND (48% sand, 2% gravel) 1% VFP + FP, | 0800 | | | | Sample from air hose |
| | | | | | | | 1% MP, 10% VFS, 30% CS, 40% MS, 13% FS, | | | | | |
| | | | | | | | 5% VFS, trace silt. Mod-well sorted. 50% | | | | | |
| | | | | | | | matrics & basalt, 50% qtz & si-rich. Unconsol. | | | | | |
| | | | | | | 2.5V 1/2 (grayish brown). NO HCL reaction | | | | | | |
| 15' | lith | 2 | | | Dry | SAND (48% sand, 2% gravel) 1% VFP + FP, | 0805 | | | | Sample from air hose | |
| | | | | | | 1% MP, 5% VFS, 13% CS, 40% MS, 30% FS, | | | | | | |
| | | | | | | 10% VFS, trace silt. 40% matrics, 60% qtz & si-rich | | | | | | |
| | | | | | | Unconsol. Mod-well sorted very sim to prev. | | | | | | |
| | | | | | | 2.5V 1/2, no HCL reaction. Well-rep. | | | | | | |
| | | | | | | Span is set @ 8.82 to read 56 ppm w/ 10.2eV | 0815 | | | | Calibrate HNU | |
| | | | | | | lamp. Spans gas is 100 ppm 150. C4H8 / Air | | | | | | |
| | | | | | | Lat 28734 | | | | | | |
| | | | | | | Check Borehole | | | | | Stopped drilling to add casing | |

W = wet, M = moist, D = dry

A-1800-003 (05/90)

DAILY BOREHOLE LOG										
Boring or Well Number <u>699 - 32-22B</u>			Depth <u>15' - 39'</u> Sheet <u>2</u> of <u>4</u>			Location <u>SE of 200E</u> Project <u>Sitewide</u>				
Logged by <u>SS Teel</u> Print		Sign <u>SS Teel</u>		Date <u>4/11/91</u>		Drilling Contractor <u>Jensen Drilling</u>				
Reviewed by		Sign		Date		Driller <u>Art Guin</u>				
Lithologic Classification Scheme <u>Folk</u> Procedure <u>DO-1,5</u> Rev No. <u>1,0</u>						Rig/Method <u>Speedstar SS-15 III / Rotary</u>				
Measuring Equipment <u>Engineers Tape</u>										
DEPTH	SAMPLES TYPE	NO.	CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE, SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS (DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
			INSTRUMENT	READING						
20'	lith	2			Dry		Adding 19.21' of 16" casing	1005		20.12 16" casing
+ 19.21 Drilling
39.33
							SAND, Same as previous sample.	1007		Sample from air hose
							Also trace mica. Well-representative.			
25'	lith	2			Dry		SAND trace VCS, 15% CS, 70% MS, 15% FS	1008		Sample from air hose
							Very well sorted, 50% basalt/mafics, trace mica			
							50% qtz + si-rich, 2.5V 1/2 (dark greyish brown)			
							No reaction to 10% HCL. Unconsol., sim			
							to previous. Well representative sample			
30'	lith	2			Dry		SAND trace MP and FP, 5% VCS, 20% CS,	1012		sample from air hose
							65% MS, 10% FS, trace VCS and silt.			
							Med - well sorted, 50% basalt/mafics, 50%			Hit gravel @ 30.5'
							qtz - si-rich, trace mica, 2.5 1/2 (greyish brown)			Slow drilling
							Unconsolidated. No reaction to 10% HCL.			
							Well representative sample			
35'	lith	1			Dry		SANDY GRAVEL Bit is grinding gravels			Sample from air hose
							up into rock flour. Samples are not			
							representative. Driller est. max size of			
							gravels are 10-12" dia.			

DAILY BOREHOLE LOG											
Boring or Well Number <u>697-32-22B</u>				Depth <u>39'-55'</u> Sheet <u>3</u> of <u>4</u>			Location <u>SE of 200 E</u> Project <u>Site wide</u>				
Logged by <u>SS Teel</u>		Print		Date <u>4/11/91</u>		Drilling Contractor <u>Jensen Drilling</u>					
Reviewed by		Print		Date		Driller <u>Art Gwin</u>					
Lithologic Classification Scheme <u>Folk</u>				Procedure <u>DO-1, S</u>		Rev No <u>1, 0</u>		Rig/Method <u>Speedstar SS-15 PL / Rotary</u>			
Measuring Equipment <u>Engineers Tape</u>											
DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)	
	TYPE	NO.	INSTRUMENT	READING						CASING	
								1100		39.33	Post Collar + Laborers on site
										+19.50	to deliver jars + eye wash
								1105		58.83	Stop drilling to add casing
											Check Borehole
											Adding 19.5' of 16"
								1209 1/2			Lunch
											Drilling w/air rotary,
40	Lith	1			Dry	0.00	Sandy Gravel. Grain sizes not representative	1350			Sample from air hose,
						0.00	Gravels are ground to powder size.	1400			
						0.00					
45'	-	-			Dry	0.00	Sandy Gravel. Same as previous. No	1440			
						0.00	sample collected.				
						0.00					
50'	Lith	2			Dry	0.00	SANDY GRAVEL. Grain sizes not rep. - however	1525			Driller says that it is drilling
						0.00	was able to get some good gravel samples.				"hard". Max orig. grain sizes of
						0.00	50% coarse + fine-grained basalt + volcanics,				gravels appears to be CP to VCP
						0.00	50% quartzite, granite/monzonite, and Si-rich.				Driller can drill up to 3' ahead
						0.00	Original surfaces are sub-angular to well rounded				but can only drive casing ± 1'
55'	Lith	2			Dry	0.00	SANDY GRAVEL. Grain sizes not rep.	1605			Gravel is consolidated?
						0.00	More basalt than prev. 70% basalt (fine-gr),				Gravel is consolidated?
						0.00	and volcanics (incl. porphyry), 30% quartzite,				(but not cemented?)
						0.00	granite, + Si-rich. Ab evidence of cementation.				
						0.00	Gravels are rounded to well-rounded on wing. Surf.				

DAILY BOREHOLE LOG

Boring or Well Number 689-32-226 Depth 60'-50' Sheet 2 of 4

Location SE of 800 East Project Swage Island

Logged by T Gilmore Print

Reviewed by Print

Lithologic Classification Scheme Falk

Measuring Equipment Steel Tape L300-16

Drilling Contractor Tensen Drilling

Driller Art Gault

Rig/Method Speedster 55-155M / Air Rotary

Sign T Gilmore Date 4/15/91

Sign Date

Procedure DD-1, DD-3 Rev No 1.0

Drilling Rate, Down Time, Blow Counts, Water Level, Drill Fluid, Etc.)

CASING

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DISTRIBUTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS |
|-------|---------|-----|---------------|---------|----------|-------------|---|-------|------------------------|----------------------------------|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | |
| 71' | Lith | 2 | HNU | 0 ppm | | | No returns - Sediment may be very gravelly. No 65' sample. | 9:50 | | 8423' Drilling |
| | | | | | | | SANDY GRAVEL 65% Gravel, 33% Sand, 2% Silt, 10% UCP, 46% MP, 10% Fp. | 9:55 | | Stop to Connect Drill pipe again |
| | | | | | | | 15% Fp, 10% UCP, 5% FS, 3% UFS, 2% Silt | 10:30 | | Drilling |
| | | | | | | | Gravels: 65% BSIT, 35% Felsic silt | | | |
| | | | | | | | when preserved, SANDS: 75% BSIT, 25% Felsic | | | |
| | | | | | | | Felsic subang, NS dk gy, no sand | | | |
| | | | | | | | No rxn in HCl | | | |
| 75' | Lith | 2 | HNU | 0 ppm | | | SANDY GRAVEL A/A 65% Gravel, 33% Sand, 2% Silt, "Blk Sands arel | 11:40 | | |
| | | | | | | | Gravel" Felsic incl about 90% quartz, amorphous | | | |
| | | | | | | | quartz (qtzite, agate etc.) Tr blk and wht | | | |
| | | | | | | | granites, Rd volcanics | | | |
| 80' | Lith | 2 | HNU | 0 ppm | | | SANDY GRAVEL 65% Gravel, 34% Sand, 1% Silt, 25% MP, 35% Fp, 5% UFS | 11:55 | | |
| | | | | | | | 15% Fp, 4% FS, 10% Silt, 2% UCP, 65% BSIT | | | |
| | | | | | | | 35% Felsic Gravels subbed when preserved, | | | |
| | | | | | | | Sands strong, Norm in HCl unconsol | 12:30 | | Lunch |

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG									
Boring or Well Number <u>697-32-22B</u> Depth <u>80'-80'</u> Sheet <u>3</u> of <u>4</u>					Location <u>SE of 200 East</u> Project <u>Swage Island</u>				
Logged by <u>T. Gilmore</u> Print		Signature <u>T. Gilmore</u> Date <u>4/15/91</u>		Drilling Contractor <u>Tension Drilling</u>		Driller <u>Art Gullik</u>			
Reviewed by <u>Folk</u> Print		Signature <u>Folk</u> Date <u>4/15/91</u>		Rig/Method <u>Speedstar 55-15 III / Air rotary</u>		Drilling Comments (Drilling Rate, Down Time, Blow Counts, Water Level, Drill Fluid, ETC.)			
Lithologic Classification Scheme <u>Folk</u>		Procedure <u>DD-1, DD-5</u> Rev No. <u>1, D</u>							
Measuring Equipment <u>300-16</u>									
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION (PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASING	DRILLING COMMENTS
					Water in hole	1230		84.23	Prepare to weld
					Measure D/W 53' b/s w/ E-Tape	1235		19.10	Take water sample
					water-level stable; Take water sample in glass - water recharged over lunch			103.33	
					after discharging water from well				
					Call Stuart but well for Technical Forum	1330			Tech Forum
					request RPT to check samples,				
					will weld casing while awaiting design from Tech Forum			103.33	Add 19.10'
					Will blow water out and wait for recovery startup as Static 52.4'	1515			Note: not much water cement possible bridge of sediment?
					min depth				No Perched water?
					1:30 53.3'				
					4:00 53.2'				
					Water did not come out of discharge, E-Tape reads 53.2'; Steel tape goes to 80' b/s (bottom) - tape comes back very muddy				
					Sediment may not circulate out of well and forms bridge at drill collars				
					Continue to drill No cuttings coming out - Difficult drilling like gravels				

W = wet, M = moist, D = dry

A-1800-003 (05/90)

Boring or Well Number 699-32-228
Location SE of 200 East

Boring or Well Number 699-32-228
Location SE of 200 East

Depth 80'
Project

Sheet 4

4

Logged by T Gilmore Print T Gilmore Sign T Gilmore Date 4/15/91

John D. Dineen Date 4/15/91
Sign

Reviewed by _____ **Date** _____
 Print **Sign**

Date _____

Signature

Lithologic Classification Scheme Folk Procedure Do-1, Do-5 Rev No. 10

Procedure Do-1, Do-5 Rev No. 1,0

Measuring Equipment Steel Tape L300-16

[illegible]

W = wet, M = moist, D = dry

A-1800-003 (05/90)

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22 B</u>			Depth <u>90' - 90'</u> Sheet <u>1</u> of <u>2</u>			Project <u>Savage Island</u>			
Location <u>SE of 200 East</u>			Drilling Contractor <u>Jensen Drilling</u>			Driller <u>Aut Gwinn (Driller) w/ Dennis Mingo</u>			
Logged by <u>T. B. more</u> Print			Date <u>4/16/91</u>			Rig/Method <u>Speedster SS-15 III / Air Rotary</u>			
Reviewed by _____ Print			Sign _____			Rev No. <u>1</u>			
Lithologic Classification Scheme <u>Folk</u>			Procedure <u>Do-1</u>						
Measuring Equipment <u>Steel Tape L300-16</u>									
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)	
90'					Geologist and Drillers on Site	655		CASING	
					Calibrate HNU w/ Spang Gas 100ppm iso-CyHg	725			103.33'
					and Air (Lot 27447) Spang reads 7.51				Drilling
		HNU 0 ppm			No water came out of discharge line,				
		LEL 0%			hole does not appear to have water in it				
					(Casing too high to measure in w/ E-Tape)				
					Sediment coming out and very wet (water is				
					soaked to drill) Approx 2' open hole in				
					coarse gravels	755			Stop Drilling
					Casing not advancing past 89' probable	840			Pull Bit
					boulders/cobbles at that depth)				
					Driller talking w/ home office to determine				
					if they want to pull casing and (overhaul)				
					Pull bit to see if it is dull and needs changing	930			-10.3' Cut off 10.3' of 16"
					Tyler thinks it may be material	945			93.03' of 16" carbon steel
					accumulating in hole because we lose				MA Chalmers to replace Tyler
					too much circulation out to formation				DW 100.4' from ground surface
									DE 77.5' from ground surface
									Finished changing bits, are now
									straightening out hydraulic lines
									lunch
									Started drilling, poor returns

Looks like a little oil was on the water, flushed
but water trough + refilled.

DAILY BOREHOLE LOG										Boring or Well Number <u>639-32-22B</u>		Depth <u>101' - 105'</u> Sheet <u>1</u> of <u>2</u>	
Location <u>SE of 200E</u>										Project <u>Savage Island</u>			
Logged by <u>SS Teel</u>		Print		Date <u>4/18/91</u>		Drilling Contractor <u>Jensendrilling</u>							
Reviewed by		Print		Date		Driller <u>Art Swin, Dennis Mingo, Joe Ranch</u>							
Lithologic Classification Scheme <u>Folk</u>		Procedure <u>D0-1, D0-5</u>		Rev No. <u>1, 0</u>		Rig/Method <u>Mud Rotary / Speedstar SS-15 III</u>							
Measuring Equipment <u>N/A</u>													
DEPTH	SAMPLES	CONTAMINATION	MONITORING	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASING	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)				
					Drillers have made a seal for the rotating head -	0830			Geologist on site				
					- preparing to run drill rod in hole			93.03	Total 16" casing				
					Span set @ 7.52 to read 56 ppm of 100ppm	0845			Calibrate HNU + LEL/02				
					ISO, C ₄ H ₈ / Air Lot # 27447.								
						0915			Adding drill rod. Using Well -				
									Guard as fool lubricant				
						1105			Check Borehole (inside of				
									drill rod)				
									Ed Enloe visits site, delivers				
									new LEL/02 meter				
						1115			Ed leaves.				
					Casing was wrapped w/ tarp. 5" screen				Truck arrives w/ 6" Carbon -				
					is wrapped in plastic.				Steel Casing and 5"				
									Telescoping Screen.				
						1125			Unloading Truck				
						1200			Truck unloaded; stop for lunch				
						1345			Drilling w/ Mud Rotary				
						1355			bit is same as prev. -				
					SANDY GRAVEL Grainsizes not rep - don't				14 3/4" tri-cone				
					have much of the < 2mm portion. Driller est				Sample from stake stake				
					max dia of cobbles is 1', Gravel comp 40%				84 vis mud				
					basalt/volcanics, 60% gte.ite + S. - rich								
					ig/mud rocks.								

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22B</u>			Depth <u>110' - 115'</u> Sheet <u>2</u> of <u>2</u>			Project <u>Savage Island</u>			
Location <u>SS of 200E</u>			Date <u>4/18/91</u>			Drilling Contractor <u>Jensen Bros.</u>			
Logged by <u>SS Teel</u>			Sign _____			Driller <u>Art Gwin / Dennis Minge / Joe Ranch</u>			
Reviewed by _____			Sign _____			Rig/Method <u>Mud Rotary / Speedstar SS-15 III</u>			
Lithologic Classification Scheme <u>Folk</u>			Procedure <u>DO-1, 5</u>			Rev No. <u>1, 0</u>			
Measuring Equipment <u>N/A</u>									
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	CASING	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)
110'	Lith 2			105	SANDY GRAVEL Can't tell % of sand & silt
Gravel comp same as prev. Angular gravel frags
are up to MP size. Trace red volcanic and
porphyry.	1403			Sample from shale staker
115'	Lith 2			115	Sandy Gravel. Can't tell sand & silt %.
Same comp as prev. Appears to be a
decrease in gravel grain sizes - abundant (23%)
whole, well-rounded MP size gravels. i.e.
unconsolidated.	1415			Sample from shale staker
seems to be drilling easy.
									Stop drilling to add rod.
									Mud tanks are empty - will
try to mix it thicker to retain
more mud.
									Have decided to wait until
LCM is on site before starting
to drill. Drillers will pick
up LCM at WHC slab-yard
tomorrow morning.
									Leave site

DAILY BOREHOLE LOG				Boring or Well Number <u>699-32-22B</u>		Depth <u>115'-117'</u> Sheet <u>1</u> of <u>3</u>		
Location <u>SE of 300 East</u>				Project <u>Sevage Island</u>				
Logged by <u>T Gilmore</u>				Drilling Contractor <u>Teaster Drilling</u>				
Reviewed by <u>Folk</u>				Driller <u>Art Grubik</u>				
Lithologic Classification Scheme <u>Folk</u>				Rig/Method <u>Speedstar 33-15TH/Mud Rotary</u>				
Measuring Equipment <u>Steel Tape L-300-16</u>				Date <u>4/19/91</u>				
Procedure <u>DP-1</u>				Rev No. <u>1</u>				
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE, COLOR, TEXTURE, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
	TYPE	NO.	INSTRUMENT	READING				CASING
					Drillers picked-up lost Circulation	7-9		Mix Mud and LCM
					Material and are mixing about			
					batch of Mud			
					Geologist arrives on site	830		
					yesterday lost mud at rate of			
					1" / min. in 5000 gal Mud Tank			
					started losing as soon as drilling			
					started at 10'; stopped at 115'			
					Calibrate HNU to Span Gas (same as	910		
					previous gas) Span at 7.5			
					Mud is made only w/ water from			
					East Standpipe and Hydrogel;			
					LCM added is Ground paper, and wood			
					fiber			
						1015		Circulate Mud
						1030		Drill
						1035		Connection
						1050		Drill
					Drill collar down - stop and change			Stop to change rotating head
					rotating head	1105		

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22B</u>			Depth <u>117'-155</u>			Sheet <u>2</u> of <u>3</u>			
Location <u>SE of 200 East</u>			Project						
Logged by <u>T.G. Ware</u>		Print		Date <u>4/19/91</u>		Drilling Contractor <u>Tensar</u>			
Reviewed by		Print		Date		Driller <u>Aust Gaskin</u>			
Lithologic Classification Scheme <u>Folk</u>				Procedure <u>D-1</u>		Rev. No. <u>1</u>		Rig/Method <u>Speedstar SS-15 III / Mud rotary</u>	
Measuring Equipment <u>Steel Tape L 300-16</u>									

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-------|---------|-----|---------------|---------|----------|-------------|---|---------|------------------------|--|-------------------------|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | CASING | |
| 120' | N/A | | | | | | No Sample w/ LCM in Mud we are bypassing shale shaker - drilling like gravels 115'-120' (Big bouncing around) smoother drilling 120'-125' | 1120 | | | Drill |
| | | | | | | | Mud seems to be holding steady, not being noticeable amount | 1125 | | | |
| | | | | | | | Drill had sticking at 127' - Drilling cobbles? | 1130 | | | Vis 170 |
| | | | | | | | No Sample LCM in mud bypass shaker - Drilling like gravels lots of wood fiber returning in mud | 12-1240 | | | ult 8.7 |
| 125' | N/A | | | | | | No Sample Drilling easier | 1245 | | | PP 450 psi |
| | | | | | | | No Sample | | | | unch |
| 130' | N/A | | | | | | No Sample By-Pass Shaker | 1310 | | | Drilling |
| 135' | N/A | | | | | | No Sample " " " | 1319 | | | |
| | | | | | | | No Sample " " " | 1330 | | | Circulate work drilling |
| 140' | N/A | | | | | | No Sample Begin to sand mud over shaker and drop out LCM | 1354 | | | Connection |
| 145' | N/A | | | | | | | 1400 | | | |
| 150' | N/A | | | | | | | 1408 | | | |
| 155' | N/A | | | | | | | 1412 | | | |

[illegible]

A-1800-003 (05/90)

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22 B</u>			Depth <u>170'-182'</u> Sheet <u>1</u> of <u>1</u>			Project <u>Savage Island</u>			
Location <u>SE of 200 East</u>			Date <u>4/22/91</u>			Drilling Contractor <u>Jensen Drilling</u>			
Logged by <u>T Gilmore</u>			Sign _____			Driller <u>Art Gwilt</u>			
Reviewed by _____			Sign _____			Rig/Method <u>Spedster SS-15 III / Mud Rotary</u>			
Lithologic Classification Scheme <u>Folk</u>			Procedure <u>D-1</u>			Rev No. <u>1</u>			
Measuring Equipment <u>N/A</u>									
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)	
	TYPE	NO.	INSTRUMENT	READING				CASING	
					Drillers on Site - Re-mix Drilling	700			
					Mud				
					Geologist on Site	815			
					Drillers working on hose (Mudline)				
					Circulate to condition hole	855			Circulate
					California HNLK w/ New Spom Gas	905			Mud vis 102
					100ppm I-Catlg and Air Tot 30434				wt
					Alphagaz Cambridge, MD 21613				Pumpless 570 psi
					Reading 63ppm w/ Spans at 7.51	910			Drilling
					Readings at shale shaker				
					No Sample Still too much LCM in Mud				
					Cannot get a good sample. Drilling				Stop Drilling / Make connection
					like Sandy Gravels, Drill stem is not	932			Drilling
					bouncing around too much	1032			Hose broke on Mud line
						1039			Stop Drilling
					Geologist leaves for office and wait for	1115			
					call when new hose arrives				

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22B</u> Depth <u>182' - 195'</u> Sheet <u>1</u> of <u>5</u>
Location <u>SE of 200 E</u> Project <u>Savage Is.</u>					Drilling Contractor <u>Tensen Drilling</u>
Driller <u>Art Gwin / Dennis Mingo / Joe Roach</u>
Rig/Method <u>Speedstar SS-15 III / Mud Rotary</u>				
Logged by <u>SS Teel</u> Print <u> </u> Sign <u> </u> Date <u>4/23/91</u>		Reviewed by <u> </u> Print <u> </u> Sign <u> </u> Date <u> </u>			Lithologic Classification Scheme <u>N/A</u> Procedure <u>D0-1, 5</u> Rev No. <u>1, 10</u>				
Measuring Equipment <u>N/A</u>									
DEPTH	SAMPLES	CONTAMINATION	MOD-
TURE	GRAPHIC
LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	CASING	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)
						0700			Drillers on site - firing hose
						0750			Geologist on site
					HNU Span set @ 7.44 to Road 56ppm	0820			Calibrate instruments
					Span set same comp as prev; Lot # 30434	0855			Circulating
						0900			Drilling w/ Mud
185'	N/A			182'	Sandy Gravel? Still bypassing shales -	0910			
				0 2 0	Lots of wood chips still in mud. No sample				
				0 2 0	taken.	0925			Vis = 115; wt = 9.0
				0 2 0					Drilling Smoother @ 188'
190'				195'	Drill rate change @ 188' - drills smoother -	0928			Increase in drill rate @ 188'
					- don't see any cuttings larger than sand				Bob Taylor KGH arrives
					size. Still lots of LCM material in mud				
					no sample taken.				
195'					Don't see any pieces larger than FP (angular)	0943			
					in cuttings. Appears to be clean sand.				
					Gravelly sand? Now putting cuttings over				
					shaker but still lots of wood chips. No				
					sample taken.				

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22B</u>			Depth <u>195'-219'</u> Sheet <u>2</u> of <u>5</u>			Project <u>Savage Island</u>			
Location <u>SE of 200E</u>			Date <u>4/23/91</u>			Drilling Contractor <u>Tensen Drilling</u>			
Logged by <u>SS Teal</u> Sign _____			Date _____			Driller <u>Art Guin</u>			
Reviewed by _____			Date _____			Right Method <u>Speedstar SS-15 II / Mud Rotary</u>			
Lithologic Classification Scheme <u>Folk</u>			Procedure <u>D-1, 5</u>			Rev No. <u>1, 0</u>			
Measuring Equipment <u>N/A</u>									
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)	
	TYPE	INSTRUMENT	READING					CASING	
					Driller says slight increase in gravel content @ 196'. Don't see any change in cuttings.	0955			
						1045			Circulating, Taping hose
						1046			Adding drill rod. B. Taylor leaves
						1050			Check Borehole
						1055			Drilling
200'	N/A					1058			Still partially bypassing
205'	N/A				195-205' No change in cuttings - largest is angular FP - appears to be dom by sand size material - drilling fairly rapid. Still lots of wood in mud. No samples taken.				shaker because of LCM
					Still Gravelly sand? No change in cuttings.				Helper went to get water - need to thin mud more.
210'	N/A				No sample taken. Comp of cuttings is roughly 50% basalt/volcanics, 50% gte - Si-rich frags.	1118			
									188-210' Drills "smooth"
									Driller thinks we are still in dom. small-size gravels.
									Stop for lunch
						1200			Drilling w/ Mud
215' lith	1				Sandy Gravel. Angular gravels up to MP size. 50% basalt/volcanics, 50% gte + Si-rich rock fragments. Partial jar filled.	1300			sample from shaker - still
						1310			partially bypassing
						1320			stopped drilling
						1330			Preparing to run dev. survey

DAILY BOREHOLE LOG

Boring or Well Number 694-32-22B
 Location SE of 2006

Depth 219'-235' Sheet 3 of 5
 Project Savage Is.

Logged by BS Teel Print _____ Sign _____ Date 4/23/91
 Reviewed by _____ Print _____ Sign _____ Date _____
 Lithologic Classification Scheme Folk Procedure DO-1, 5 Rev No. 1, 0
 Measuring Equipment N/A

Drilling Contractor Tensen Bros.
 Driller Art Guin
 Rig/Method Speedstar SS-15 Dr / Mud Rotary

| DEPTH | SAMPLES
TYPE NO. | CONTAMINATION | | MOIS-
TURE | GRAPHIC
LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O
ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) | |
|-------------|---------------------|----------------|---------|---------------|----------------|--|------|---------------------------|---|---------------------------|
| | | INSTRUMENT | READING | | | | | | CASING | |
| | | HNU | Oppm | | | | 1335 | | | Check Borehole |
| | | LEL | 0% | | | | 1357 | | | Survey complete. Meas. is |
| | | O ₂ | 20.8% | | | | 1400 | | | 1.1' from true @ 200' |
| | | | | | | | 1420 | | | Adding drill rod. |
| | | | | | | | 1421 | | | Drilling w/ Mud |
| 220' | — | | | | 219' | Same as prev. | 1423 | | | Drilling Fast @ 219', |
| 225' Lith 2 | 2 | | | | 220' | SANDY GRAVEL same as prev | | | | No 220' sample |
| | | | | | 228' | | | | | Sample 225' from shaker |
| | | | | | 228' | | | | | |
| | | | | | 228' | | | | | |
| | | | | | 228' | | | | | |
| | | | | | 228' | | | | | |
| 230' Lith 2 | 2 | | | | 228' | BLUE CLAY (SG 4/1) ~ 25% sand & | 1425 | | | Sample from shaker |
| | | | | | 228' | NFP (carry-down?) 15-20% silt? | | | | Clay starts @ 228? |
| | | | | | 228' | | | | | |
| | | | | | 228' | | | | | |
| | | | | | 228' | | | | | |
| | | | | | 228' | | | | | |
| | | | | | 228' | | | | | |
| 235' Lith 2 | 2 | | | | 235' | BLUE CLAY same as prev. less | 1430 | | | Sample from shaker |
| | | | | | 235' | amount of sand. Tends to form | | | | Vis = 74, wt = 9.2 |
| | | | | | 235' | more "clay balls" | | | | Cleaning hole |
| | | | | | 235' | | 1435 | | | Adding Rod |

25

Depth 235' - 255' Sheet 4 of 5
Project Savage IS

Drilling Contractor Tensen Bros

Driller Art Gwin

RigMethod	
Same as prev.	

| DATE | H ₂ O
ADDED | CASING | DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC. | DRILLING COMMENTS |
|-------|---------------------------|--------|--|----------------------------|
| 11-33 | | | | Drilling w/ Mud |
| 11-35 | | | | Sample from shaker |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 11-38 | | | | Sample from shaker |
| | | | | Gravel starts @ 244' |
| | | | | |
| | | | | |
| | | | | |
| | | | | Sample from shaker |
| 11-39 | | | | Driller est cobble size is |
| | | | | 4" to 10" dia. |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

A-1800-003 (05/90)

DAILY BOREHOLE LOG				Boring or Well Number <u>699-32-22B</u>		Depth <u>275'</u> Sheet <u>2</u> of <u>3</u>	
Location <u>SE of 200E</u>				Project <u>Savage I's</u>			
Logged by <u>SS Teel</u>		Print		Sign		Date <u>4/24/91</u>	
Reviewed by		Print		Sign		Date	
Lithologic Classification Scheme <u>Folk</u>		Procedure <u>DD-1, S</u>		Rev No. <u>1, 0</u>			
Measuring Equipment <u>W/A</u>							
Drilling Contractor <u>Tensen Drilling</u>				Driller <u>Same as prev.</u>			
Rig/Method <u>Same as prev.</u>							

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | CASING | DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC. |
|-------|---------|-----|---------------|---------|----------|-------------|---|------|------------------------|--------|---|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | | |
| 280' | Lith | 2 | | | | | SANDY GRAVEL Sim to prev. Gravel comp 55% basalt, porphyry (v. small phenocrysts) and other volcanics. 35% Si-rich (dom qtzite) | 1124 | | | Working on rig |
| 285' | Lith | 2 | | | | | SANDY GRAVEL (65% gravel, 35% sand) 58% CP, 40% MP, 10% FP, 10% VFP, 10% VCS, 15% CS, 5% MS, 5% FS & VFS. (Gravel) - 65% basalt, volcanics, & fine gr porphyry, 35% dom qtzite. Angular except for ooc. rounded MP. (Sand) - same comp as gravels. Most grains are angular - some rounded MS-CS | 1132 | | | Sample from shaker |
| 290' | Lith | 2 | | | | | SANDY GRAVEL Same as prev. Grain sizes not rep. | 1141 | | | Allowed 2 min for lag |
| 295' | Lith | 2 | | | | | SANDY GRAVEL Same as prev. Also see red volcanic and trace coarser-sizc porphyry in gravels. Grain sizes not rep. | 1150 | | | Sample from shaker |
| | | | | | | | | | | | Allowed 2 min for lag |
| | | | | | | | | | | | Sample from shaker |
| | | | | | | | | | | | Allowed 2 min for lag |
| | | | | | | | | | | | vis = 94; wt = 9.3 |

DAILY BOREHOLE LOG				Boring or Well Number <u>UA9-32-22B</u>		Depth <u>295'-310'</u> Sheet <u>1</u> of <u>2</u>		Location <u>SE of 200E</u>		Project <u>Savage Island</u>	
Logged by <u>MA Chalmers</u>		Print		MA Chalmers		Date <u>4/25/11</u>		Drilling Contractor <u>Jensen Bros.</u>			
Reviewed by		Print				Date		Driller <u>Art Gwin, Dennis Mingo, Joe Roach</u>			
Lithologic Classification Scheme <u>Folk</u>		Procedure <u>DD-1, DO-S</u>		Rev No. <u>1.0</u>				Rig/Method <u>SS15 III, mud rotary</u>			
Measuring Equipment <u>NA</u>											
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	CASING	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)		
						800			Geologist on site, shakers still
changing block		
					Calibrated H ₂ O to 100ppm gal, same as
before stepping @ span of 7.04	1000			Circulating mud		
						1155					
						1200					
						1308			Sampled from shakers.		
200' with 2					SANDY GRAVEL - Most gravel broken, some
were up to vcp size. Muscovite abundant
as pieces up 2-3 mm across. Percent ~ 35%,
rk frags SS's, 10% gls. silt - musc. Blobs
of blue-gray muddy sand, micaceous, start
showing up at ~ 302', Samples washed,
not representative. @ 1255				A at 302', slower drilling		
					back into gravel at ~ 304'				lost ~ 1/2 tank of mud, added
2 bags of paper to prevent
lost circulation		
305' none					Apparently still in fine-grained seds,
can't take sample w/ lost circulation
mat. in mud.	1330					
310' none					More gravel, some whole pieces up to fp.
Others broken from larger pieces. Still too
much lost circulation mat. for samples.
Gravels have more basalt than before.	1405			Added cedar chips, 1 bag, +
1/2 bag cellophane		

DAILY BOREHOLE LOG				Boring or Well Number <u>044-32-228</u>		Depth <u>310' - 323'</u> Sheet <u>2</u> of <u>2</u>			
Location <u>SE of 200E</u>				Project <u>Savage Island</u>					
Logged by <u>MA Channery</u>		MA Channery		Date <u>4/25/91</u>		Drilling Contractor <u>Jensen Bros</u>			
Reviewed by		Sign		Date		Driller <u>Art Gustin, Dennis Mingo, Joe Beach</u>			
Lithologic Classification Scheme <u>Folk</u>		Procedure <u>D-1, D-5</u>		Rev No. <u>1, D</u>		Rig/Method <u>SS IS III, mud rotary</u>			
Measuring Equipment <u>NA</u>									
DEPTH	SAMPLES	CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DIRELING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)
		INSTRUMENT	READING						
315'	none				?	SANDY GRAVEL(?) - lots of broken gravel
to vis. particles mixed w/ paper &
wood chips. ~40% basalt, white/lt
maybe up to 30% rk frags 20%	1435		Still too much lost circulation
not to collect samples
							1445		Stopped drilling to work on
mud pump
							1525		Started drilling
							1555		Preparing to run straightness
test, off by 1.75° at 318'
									Adding drill rod.
							1630		Drilling
							1637		
320' lith	1					SANDY GRAVEL to SAND. Gravel is
40% basalt, 10% qtz-rich, 50% dk rk frags,
mostly ign., some dk red porphyries. There
are abundant pieces of sand clumps, cl.
muddy vit-f sand, 50-75% dk greenish
gray. 1 piece of old wood, to small
to try to do anything with. Note
that most of the rk frags are dk, unlike
most previous samples w/ lt ign. rks.	1655		Sampled from shaker, still
a lot of LCM, but washed
most of it out.
							1720		Total for day - 25'
									Conditioning hole for night
							1730		Quit for day

W = wet, M = moist, D = dry

A-1800 003 (05/90)

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22B</u>			Depth <u>323'-335'</u> Sheet <u>1</u> of <u>3</u>			Project <u>Savage Island</u>			
Location <u>SE of 200 East</u>			Date <u>4/26/91</u>			Drilling Contractor <u>Jensen Drilling</u>			
Logged by <u>T. Calmore</u>			Sign <u>T. Calmore</u>			Driller <u>Art Gushin</u>			
Reviewed by <u>T. Calmore</u>			Sign <u>T. Calmore</u>			Rig/Method <u>Speedstar 55-1577 / Mud Rotary</u>			
Lithologic Classification Scheme <u>Falk</u>			Procedure <u>DO-1</u>			Rev No. <u>1</u>			
Measuring Equipment <u>1300-16</u>									
DEPTH	SAMPLES	CONTAMINATION	MOD-
TURE	GRAPHIC
LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	CASING	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)
					Drillers on site - Art Gushin, Dennis Mung	300			
					and Joe Beach				
					Geologist on site	345			
						355			Drill
345	Lith 1	HNH	Open		MUDDY SANDY GRAVEL 35% Gravel, 45% Sand, 20% Mud (with silt and clay)	810			
					15% MP, 15% FP, 5% FP, 10% VS, 10% FS				
					10% MS, 15% FS, 20% Silt and clay, clay present indicated by ductility; some clay balls, water soluble, mixed w/ sand				
					Sand and Gravel very broken up sand when preserved N4 deg				
					No coarse shells like it at gravel and sand - samples poor lots of LCM				
330	No Sample				No Sample - Muddy SAND drilled smoothly and fast too much LCM	820			No Sample too much LCM
335	Lith 1	HNH	Open		MUDDY SANDY GRAVEL 45% Gravel, 55% Sand, 20% Mud, 10% MP, 15% FP, 10% VS, 10% FS, 10% MS, 10% FS, 20% Silt w/ Tr Clay - Clung to clay in 25' 4" 1/4 plu brn smaller gravel sizes 8' to	833			Color change at ~335 pick-up more clys
									Circulate

Boring or Well Number: 699-32-22B Depth 360'-360' Sheet 1 of 1
Location SE of 200E Project Savage Is.

DAILY BOREHOLE LOG

Logged by SS Teel Print SS Teel Sign SS Teel Date 4/29/91

Reviewed by _____ Date _____
 _____ Sign _____
 _____ Print _____

Lithologic Classification Scheme N/A Procedure DD-1, S Rev No. 1, 0

Measuring Equipment	N/A

ESTD
Date 4/29/91

Sign

Date

ture DO-1,5 Rev No. 1,0

100

Drilling Contractor Jensen Drilling

Driller: Art Gwin / Dennis Mingo / Joe Roach

Speedstar SS-15 III / Mud Rotary

| DEPTH | SAMPLES | | CONTAMINATION | | MOD-
TURE | GRAPHIC
LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O
ADDED | CASING | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) |
|-------|---------|-----|---------------|---------|--------------|----------------|--|------|---------------------------|--------|---|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | | |
| | | | | | | | | 0700 | | | Drillers on site - |
| | | | | | | | (Bit is wore-out) | | | | pulling drill rod to change |
| | | | | | | | | | | | bit |
| | | | | | | | | 0945 | | | Geologist on site - all rod is |
| | | | | | | | | | | | out of hole - changing bits |
| | | | | | | | | | | | KEH personnel are expanding |
| | | | | | | | | | | | mud pit w/ backhoe, 1 |
| | | | | | | | | 1000 | | | Art Collier arrives |
| | | | | | | | | 1015 | | | Calibrate HANU & check |
| | | | | | | | | | | | borehole |
| | | | | | | | | | | | |
| | | | | | | | | 1030 | | | |
| | | | | | | | Bit will not arrive until tomorrow - the | | | | |
| | | | | | | | bit Co. sent it 2 nd day air instead of | | | | |
| | | | | | | | overnight. No drilling until tomorrow | | | | |
| | | | | | | | | 1100 | | | KEH personnel complete |
| | | | | | | | | | | | mud pit. |
| | | | | | | | | | | | Pjt barricade around pit |
| | | | | | | | | | | | |
| | | | | | | | 4/30/91 Receive word that bit will not | | | | |
| | | | | | | | arrive until tonight. Will run the bit | | | | |
| | | | | | | | in the hole first thing tomorrow (5/1/91) | | | | |

W = wet, M = moist, D = dry

Λ 1800 003 (05/90)

DAILY BOREHOLE LOG									
Boring or Well Number		699-32-22B		Depth		365-380		Sheet 2 of 4	
Location		SE of 2 East		Project		Savage Is.			
Logged by		T. B. Moore		Date		5/1/91		Drilling Contractor	
Reviewed by		Print		Date				Driller	
Lithologic Classification Scheme		Folk		Procedure		D-1		Rev No. 1	
Measuring Equipment		N/A		Rig/Method		Mud rotary			

| DEPTH | SAMPLES | CONTAMINATION | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC. | TIME | H ₂ O
ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLANK COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) | |
|-------|---------|---------------|----------|-------------|---|------|---------------------------|--|--|
| | | | | | | | | CASING | |
| 370 | L4h 1 | | | 370-380 | SANDY GRAVEL 65% Gravel, 35% Sand, 10% silt
V frag not sep largest gravel appears to be
G.P. Gravel 65% BSIT, 35% other subd
Sand 65% silt (Traces of w/srt
fg sand w/ gr dy matrix) mostly p/srt
about rd-grn volcanics yellowish siliceous
rich material sl rxn in HCL (especially in
Sand and grn clay) color A/A | 1135 | | N/A | |
| 375 | L4h 1 | | | 375-380 | GRAVEL 95% Gravel, 5% Sand, 15% silt
Gravel 15% CP, 40% MP, 30% FP, 15% BSIT, 12-13%
silt when preserved 65% BSIT, 35% other 12-13%
about grn-rd volcanics, about silica,
Traces grn-blu cly in samp Mud-p/srt
N4 gy, No rxn in HCL no consol
more gravel than previous | 1355 | | | Drilling slowed at ~ 373'
Lunch
Drill - drill note picked-up
at ~ 375'
Connection
Drill |
| 380 | L4h 1 | | | 380-390 | SANDY GRAVEL 80% Gravel 20% Sand
70% BSIT 30% other subd, very
fragmented p/srt N4 dk gy, w/srt
1% HCL no consol sl more sand than
previous | 1310 | | | |

W = wet, M = moist, D = dry

| DAILY BOREHOLE LOG | | | | | Boring or Well Number
699-32-22B | Depth
380' | Sheet
3 of 4 | | | |
|--|---------|------|---------------|---------|-------------------------------------|---------------|--|------|------------------------|--|
| Location
SE of East Fork Savoy Island | | | | | | | | | | |
| Logged by
<i>Tailor</i> | | | | | Date
5/1/91 | | | | | |
| Reviewed by
<i>Folk</i> | | | | | Date | | | | | |
| Lithologic Classification Scheme
Folk | | | | | Procedure
DD-1 | Rev No.
1 | | | | |
| Measuring Equipment
N/A | | | | | | | | | | |
| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENT:
(DRILLING RATE, DOWN TIME, BLOCK COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) |
	TYPE	N.O.	INSTRUMENT	READING						
385	Lith	1					SANDY GRAVEL (as above)	1315		Mud vis 78
390	Lith	1					SANDY GRAVEL 75% Gravel 25% Sand	1325		wk 8.9
							40% MP, 45% Fp, 10% VEP, 50% VC, 15% CS,			Drilling very fast
							5% MS, 7% SP, 70% BS&T, 30% other			
							probable matrix N4 clay varmin			
							HCl			
395	Lith	1					SANDY GRAVEL (as above)	1335		Drill bit sticking at ~396'
400	Lith	1					SANDY GRAVEL 30% Grav 25% Sand	1340		(Gravels?)
							5% Mud (good cly) 15% GP, 25% MP,			To Gen/cay cly w/ sand
							40% Fp, 10% Sp 10% VC, 5% CS, 30% MS			LCM is almost gone from MUD
							& sand rd-subbed when processed,			go back to 2 Lth samples per interval after 400'
							5' 5/1 (Tr of gen) sl run-in-HCl			
							No cement - some gen/cly mixed			~375 - 400 high water levels
							w/ + sands forms cly balls in sample			of cly mixed w/ + g sand
										Circulate
							Driller call office	1355		
							weld hose clamp back on Rig	1415		
							Note 4 sacks of Soda Ash added to			
							the mud since the beginning of the well			

A-1800-003 (05/90)

DAILY BOREHOLE LOG

Boring or Well Number 699-33-32B Depth 415' - 425' Sheet 1 of 4

Location SE of 200 East Project Savage Island

Logged by	MA Channess	Print	MA Channess	Sign	Date	5/2/91
Reviewed by		Print		Sign	Date	
Lithologic Classification Scheme	MA	Print		Sign	Procedure	DO-5
Measuring Equipment	N/A	Print		Sign	Rev No.	1,0

Drilling Contractor	Jensen Bros
Driller	Art Gwilt, Dennis Mingo, Joe Roach
Rig/Method	Mud Rotary SS/STH

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | CASING | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) |
|-------|---------|-----|---------------|---------|----------|-------------|---|------|------------------------|--------|--|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | | |
| | | | HNIA | ppm | | | Calibrated HNIA w/ gas, 50 ppm @ 7.08 | 745 | | | Circulated mud, adding new |
| | | | LEL | pk | | | span. | | | | drill rod |
| | | | | | | | | 750 | | | Started drilling |
| | | | | | | | | 815 | | | Preparing to run straightness |
| | | | | | | | | 850 | | | Hole is ~1.1° off, straighter than at 300' |
| | | | | | | | | 955 | | | Welding on hose bracket. |
| | | | | | | | | 1010 | | | Started drilling, toe is clean |
| | | | | | | | | | | | shaker screen, can't get 420' sample |
| | | | | | | | | | | | sampled from shaker |
| | | | | | | | | | | | mud wt = 9.10 |
| | | | | | | | | | | | vis @ 0 + (he's adding H ₂ O now) |
| | | | | | | | | 1020 | | | Drilling easier @ 423' |
| | | | | | | | | 1025 | | | Hose leaking mud, stopped to fix |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | Drilling again |
| | | | | | | | | | | | sampled from shaker. |
| | | | | | | | | | | | |
| | | | | | | | | | | | Ed Enloe picked up logs |
| | | | | | | | | | | | When mud has broken fix |
| 121' | lith | 2 | | | 421 | ~~~~~ | GRAVELLY CLAYSTONE-Primer!! and (cemented?) | 1015 | | | |
| | | | | | | ~~~~~ | pieces up to 3cm long of green (58% 4/1) | | | | |
| | | | | | 422 | ~~~~~ | clay frags, can scratch w/ fingernail, brittle, run | | | | |
| | | | | | | ~~~~~ | run when damp in HCL, gravel are v-f- | 1020 | | | |
| | | | | | | ~~~~~ | exp. - many are broken. Gravel may be | 1025 | | | |
| | | | | | | | coming from ~422' drilling rate increased | | | | |
| | | | | | | | thud. gravel - 25% break, 20% qtz/gtate, 55% | | | | |
| | | | | | | | cl frags (ign mostly). Samples not washed. | 1100 | | | |
| | | | | | 425 | ~~~~~ | CLAYEY GRAVEL - Gravel c-vf, 25% break, | 1105 | | | |
| | | | | | | ~~~~~ | 15% qtz/gtate, 10% primarily dk cl frags, | | | | |
| | | | | | | ~~~~~ | many ign. Clay is dk greenish gray (56% 4/1) | 1115 | | | |
| | | | | | | ~~~~~ | + 5% silty silt + vf sand in pieces. v-f- to 10 | 1120 | | | |
| 425' | lith | 2 | | | 426 | ~~~~~ | | | | | |

W = wet, M = moist, D = dry

A-1800-003 (05/90)

DAILY BOREHOLE LOG									
Boring or Well Number <u>1099-32-22B</u>			Depth <u>425'-440'</u> Sheet <u>2</u> of <u>4</u>			Project <u>Savage Island</u>			
Location <u>SE of ZONE</u>			Drilling Contractor <u>Jensen Drilling</u>						
Logged by <u>MA Chawwa</u> Print			Date <u>5/12/91</u>			Driller <u>Art Gwin, Dennis Mingo, Joe Roach</u>			
Reviewed by _____ Print			Date _____			Rig/Method <u>Mud rotary SS15 III</u>			
Lithologic Classification Scheme <u>11A</u>			Procedure <u>DO-1, DO-5</u> Rev No. <u>1,0</u>						
Measuring Equipment <u>NA</u>									
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOCK COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)	
430'	with 2		430	~ ~ ~ ~ ~	CLAYSTONE w/ gravel - primarily pieces
of mod. consolidated clay can scratch
easily w/ fingernail, brittle. Gravel is
~ 35% of sample; m-vf, K-A, 40% basalt,
20% qtz/gtzite, 20% variety of rk frags,
mostly ign. Samples not washed, drilling
gray	1150
1145			Sample from shaker
Started drilling
			431						
									lunch
									RPT's came by everything ok
									sampled from shaker
									Drilling slower again because
of clay.
									Stopped to fix another hose leak
									Started up + another hose
									started to leak.
									Started drilling, drilling slow
437' NOM					Increase in clay content, very soft, ~5-10%
gravel, clay 5G5/1 (greenish gray)				
					CLAY, slight amt (3%) gravel. Clay is
greenish gray, 5G5/1 when wet. Soft,
pliable. Samples were unwashed some.	1305
1310
1320
1415			Sampled from shaker
									Started drilling faster @ 442'

DAILY BOREHOLE LOG

Boring or Well Number 699-32-22B
 Location SE of 200E

Depth 440'-470' Sheet 3 of 4
 Project Savage Island

Logged by MA Chalmers
 Print

MA Chalmers
 Sign

Date 5/2/51

Reviewed by _____
 Print

Date _____

Lithologic Classification Scheme NA

Procedure D-1, D-5 Rev No. L, D

Measuring Equipment NA

Drilling Contractor Jensen Drilling
 Driller Art Guin, Dennis Ningo, Joe Roach
 Rig/Method SS IS III mud rotary

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | CASING | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) |
|-------|---------|-----|---------------|---------|----------|-------------|--|-------|------------------------|--------|--|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | | |
| 445' | Lith | 2 | | | | | GRAVELLY CLAY - 20% gravel, R-A, most not broken, variety of lithologies. Clay has some sand, 50% 1/4" (ok greenish gray) when wet, friable, soft. Samples washed some | 11544 | | | Sampled from shaker |
| 450' | Lith | 2 | | | | | GRAVELLY CLAY - more gravel, silt + sand than above, but still primarily clay, slight color change to 5/5/1 (gray) still friable, soft. Washed samples | | | | Drilling rate still increasing |
| 455' | Lith | 2 | | | | | GRAVELLY CLAY - similar to above, still increasing gravel content, gravel up to 1/2", mostly m-fp, we-A. Color similar to above. Samples not washed. | | | | Sampled from shaker |
| 460' | Lith | 2 | | | | | MUNDY SANDY GRAVEL - increased sand + gravel, mud is still mostly clay. Samples not washed. | 11620 | | | Sampled from shaker |
| 465' | Lith | 2 | | | | | MUNDY SANDY GRAVEL - similar to above. Samples not washed | | | | Sampled from shaker |
| 470' | Lith | 2 | | | | | SANDY GRAVEL - a few chunks of brown to gray mud. Gravel ~ 75% 1/4" sample or more, 45% basal + 50% in bottom, 50% gray. Most gravels are dk colored, 1 m cf. | 11620 | | | Sampled from shaker |

W = wet, M = moist, D = dry

W = wet, M = moist, D = dry

[illegible]

A-1800 003 (05/90)

DAILY BOREHOLE LOG

Boring or Well Number 699-32-22B
 Location SE of 200 East

Depth 478' - 490' Sheet 1 of 3
 Project Swage Island

Logged by T Gilmore

Date 5/6/91

Sign

Reviewed by

Date

Sign

Lithologic Classification Scheme Folk

Procedure DO-1

Rev No. 1

Measuring Equipment N/A

Drilling Contractor Tension Drilling

Driller Art Gault / Dennis Mingo / Joe Reade

Rig/Method Mud Rotary

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-------|---------|-----|---------------|---------|----------|-------------|---|----------------------|------------------------|--|--|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | CASING | |
| 480' | Lith | 2 | HNK | | | | Switchout Mud hose
Mud connections with drill string back in hole | 700
850 | | | Circulate
Note: No Drilling 5/3/91 -
Broken hose
Drilling |
| 485' | Lith | 2 | | | | | Calibrated HNLK | 950 | | | |
| 490' | Lith | 2 | | | | | MUDDY SANDY GRAVEL 35% Gravel, 40% Sand, 25% Mud 5% CP, 10% AMP, 15% EP 5% GUF, 5% RES, 15% MS, 5% FS, 25% Mud/clay solid 45% BSST, 55% other 2.5' 5/8 Gyp br no rxn in HCL sl cement | 955
1005
1020 | | | Mica in sample - no mica added to Mud as LCM (some collapse was) |
| 495' | Lith | 2 | | | | | MUDDY SANDY GRAVEL 50% Gravel, 40% Sand, 10% Mud (less clay) very frag gravel not representative sand also very fragmented, 55% BSST, 45% other about 1/2 gran volcanic color N3 vdky No rxn in HCL, sl cement, less clay than previous | 1020
1130
1140 | | | Mud hose broke / Stop Drilling
Drill |
| | | | | | | | MUDDY SANDY GRAVEL 40% Gravel, 45% Sand, 15% Mud, very fragmented not representative 50% BSST 50% other N4 dk gy 10% rxn, sl cement | 1230 | | | Lunch |

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG

Boring or Well Number 699-33-32 B

Location SE of 200 East

Depth 490'-510' Sheet 2 of 3

Project Savage Island

Logged by T Gilmore

Print

Date 5/6/91

Sign

Reviewed by FBK

Print

Date

Sign

Lithologic Classification Scheme FBK

Procedure 20-1

Rev No 1

Measuring Equipment N/A

Drilling Contractor Jensen

Driller Art Gwilt

Rig/Method Mud Rotary

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, BOUNDRINESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | CASING | DRILLING COMMENTS
(TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) |
|-------|---------|-----|---------------|---------|----------|-------------|--|------|------------------------|--------|--|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | | |
| 500' | Lith. | 2 | | | | | Drilling rate slow 198'-500' Slow steady drilling - consolidated? | 1320 | | | Drill |
| | | | | | | | Muddy SANDY GRAVEL 60% Gravel, 30% Sand, 10% Mud, very fragmented, not representative, formation may be consolidated and bit is grinding sediment up, 40% BSL 60% other (problem gran volcanics) 5 1/2" clv gy, Traces of wht cly - v strong rxn in HCL sl-mod cased more gran volcanics (same previous + appearance of wht dyes | 1335 | | | Circulate for connection |
| | | | | | | | | 1337 | | | Drill |
| | | | | | | | | | | | Hard Formation? Trace caliche? |
| | | | | | | | | | | | Mud 98 wt's |
| | | | | | | | | | | | 9 wt |
| 505' | Lith. | 2 | | | | | SANDY GRAVEL 50% Gravel, 45% Sand, 5% Mud very fragmented not representative | | | | |
| | | | | | | | 50% BSL 50% other 5 1/2" sl-mod cased wh rxn in HCL similar to previous sample Tr less mud | | | | |
| 510' | Lith. | 2 | | | | | GRAVELLY MUD 25% Gravel 5% Sand, 70% Mud (some cly chunks) ductile | 1340 | | | |
| | | | | | | | less stronger Gravel 50% BSL/Gallae, subbed 5 1/2" olv gy Mud's both cly and silt sl cased slow drilling Bit balling up no rxn in HCL | | | | |
| | | | | | | | | | | | 508' lith cly to Clays |

W = wet, M = moist, D = dry

A-1800-003 (05/90)

A-1800-003 (05-90)

Depth 510-515' sheet 3 of 3

Project Seward Is

Drilling Contractor *Tension*

Driller Ar + Gush

Rev No. 1

1

D R I L L I N G C O M M E N T S
(D R I L L I N G R A T E, D O W N T I M E, B L O W C O U N T S, W A T E R L E V E L, D R I L L F L U I D,
E T C.)

CASING

Stop Drilling / Work on Mud Pump
Replace a seal
End of Day

A-1800 003 (05/90)

Depth 510' - 520' sheet 1 of 3
Project Savage Is.

DAILY BOREHOLE LOG

Logged by SS Teel SS Teel

Print

Reviewed by _____ Printed _____

Lithologic Classification Scheme Folk

U/A
Measuring Equipment

Date 5/7/91

Date _____

Procedure DD-1,5 Sign Rev No. 1,0

Rev No. 1,0

Tensen Drilling
Drilling Contractor

Driller Art Gwin / Joe Roach / Dennis Mingo

Mud Rotary / Speedstar SS-15 III

[illegible]

W = wet, M = moist, D = dry

A-1800 003 (05-90)

65

Logged by SS Teel Print _____
 Reviewed by _____ Sign _____
 Lithologic Classification Scheme Folk Procedure DO-1,5 Rev No. 1,0
 Measuring Equipment N/A

Drilling Contractor Same
 Driller Same
 Rig/Method Same

Date 5/7/91

[illegible]

W' = wet, M = moist, D = dry

A-1800-003 (05/90)

DAILY BOREHOLE LOG

Boring or Well Number 699-32-22B
 Location SE of 200E

Depth 535'-545' Sheet 1 of 2
 Project _____

Logged by SS Teel Print _____
 Reviewed by _____
 Lithologic Classification Scheme FoK
 Measuring Equipment N/A

Date 5/14/91
 Sign _____
 Date _____
 Sign _____
 Procedure D0-1, 5 Rev No. 1, 0

Drilling Contractor Jensen Drilling
 Driller Art Gwin / Joe Roach / Dennis Mingo
 Rig/Method Mud Rotary / Speedstar SS-15 TL

| DEPTH | SAMPLES | | CONTAMINATION | | MOIS-
TURE | GRAPHIC
LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O
ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) | |
|-------|---------|-----|---------------|---------|---------------|----------------|--|------|---------------------------|---|------------------------------|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | CASING | |
| | | | | | | | Note: Rig has been down since 5/7/91 | 1030 | | | Geol. on site. Drillers |
| | | | | | | | | | | | making final repairs to rig |
| | | | | | | | | | | | Ike Spivey, KE4 also on site |
| | | | | | | | | 1050 | | | Spivey leaves site |
| | | | | | | | HNU span set @ 6.48. Same span gas as prev. | 1055 | | | Calibrate instruments |
| | | | | | | | | 1515 | | | Pat Collier on site |
| | | | | | | | | 1545 | | | Circulating |
| | | | | | | | | 1600 | | | Adding drill rod |
| | | | | | | | | | | | Check borehole |
| | | | | | | | | | | | |
| | | | | | | | | 1607 | | | Drilling |
| | | | | | | | MUDDY GRAVEL (35% gravel, 15% sand, 50% mud) | 1608 | | | Bit @ 540' |
| | | | | | | | prev. 61 1/4" (dark gray) | 1612 | | | Collect sample |
| | | | | | | | | | | | Pat Collier leaves |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | 1615 | | | Bit @ 545' |
| | | | | | | | SLIGHTLY GRAVELLY MUD (5% gravel, 5% sand, 90% mud) | 1620 | | | Collect sample |
| | | | | | | | Mud portion seems to have more clay than silt (plastic). | | | | |
| | | | | | | | Very sim. to 536' sample. 51 1/4" dark gray | | | | |

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG				Boring or Well Number <u>699-32-22B</u>		Depth <u>545-565'</u> Sheet <u>2</u> of <u>2</u>	
Location				Project		Drilling Contractor <u>Jensen Drilling</u>	
Logged by <u>SS Teel</u> Print				Date <u>5/14/91</u>		Driller <u>Art Gwin</u>	
Reviewed by _____ Print				Sign _____		Rig/Method <u>Same</u>	
Lithologic Classification Scheme <u>Folk</u>				Procedure <u>D-1, S</u>		Rev No. <u>1, 0</u>	
Measuring Equipment <u>N/A</u>							
DEPTH	SAMPLES	CONTAMINATION	MOSS-TURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED
		INSTRUMENT	READING				
550' Lith 2				550' ~ 565'	GRAVELLY MUD (10% gravel, 5% sand, 85% mud). Mud portion has more silt than clay - 65:35? Gravel are angular and are dom. glite. Silt is beginning to look consolidated, 5Y 4/1 dark gray.	1624	
555' Lith 2				555' ~ 565'	MUD. Dominated by silt. Thinly bedded? - 1634 - find compacted chunks 5-10 mm thick	1636	
					mod-well consolidated 5Y 4/1 dark gray, silt/clay ratio 80:20? Abn - trace gravel.		
560' Lith 2				560' ~ 565'	MUD. Same as prev. Still mod-well cons., thinly bedded, and dom by silt 5Y 4/1 dark gray	1640	
565' Lith 2				565' ~ 570'	MUD. Same as prev.	1645	
						1650	
						1700	
						1730	
					DRILLING COMMENTS:
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)		
					CASING		
					Bit @ 550'		
					Collect sample - 550'		
					Bit @ 555'		
					Increase in drill rate @ 550'		
					Collect sample - 555'		
					Bit @ 560'		
					Collect sample - 560'. Bit @ 565'		
					Vis = 126. Everything is going over shaker.		
					Collect sample - 565'		
					Driller put drill rod on backwards - will have to switch before adding rod.		
					Cleaning-up site		
					Drillers leave site		
					Total of 30'	A-1800-003 (05/90)	

DAILY BOREHOLE LOG

Boring or Well Number

699-22-22B

Depth

585'

Sheet

1

of

4

Location

SE of 200E

Project

Savage Island

Logged by

MA Chaviness

Print

Reviewed by

Print

Lithologic Classification Scheme

NA

Measuring Equipment

NA

Date

5/15/11

Drilling Contractor

Jensen Drilling

Driller

Art Giron, Dennis Mingo, Joe Roach

Rig/Method

SS IS III, mud string

| DEPTH | SAMPLES | | CONTAMINATION | | MODS-TURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE, TEXTURE, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-------|---------|-----|---------------|---------|-----------|-------------|---|------|------------------------|--|---------------------------------|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | CASING | |
| | | | | | | | Calibrated HNU to standard and span | 700 | | | Picking up water truck |
| | | | | | | | @ 6.94 w/ reading of 56 ppm | 805 | | | Geologist on site |
| | | | | | | | | 835 | | | |
| | | | | | | | | 845 | | | Water truck here, changing test |
| | | | | | | | | | | | fill red, adding mud, etc. |
| | | | | | | | | | | | drilling rate ~ 105' / min |
| | | | | | | | | | | | Start drilling |
| | | | | | | | | 945 | | | Sampled from shaker |
| 570' | lith | 2 | | | 570 | | Mud - lg. chunks of dk gray (54/1) | 1000 | | | Chris Eastley, Kell safety on |
| | | | | | 572 | | mud w/ abundant pieces of sandy silt | 1005 | | | site black sandy silt may |
| | | | | | | | 10122/1 (black). The latter water mud back | | | | be organic rich? |
| | | | | | | | dk brown ~ 3% vf-f gravel SA-IR, mostly | | | | |
| | | | | | | | of lithologies. Sample washed slightly. | | | | |
| | | | | | 575 | | SANDY MUD - 1% greenish gray (56/5/1) | 1011 | | | Sampled from shaker |
| | | | | | | | 45% vf-f 55% mud. Unconsolidated. No gravel. | | | | |
| | | | | | 577 | | Sample washed slightly. Strong run in HCl | 1020 | | | Chris left |
| | | | | | 580 | | SLATE-LITH. SANDY MUD ~ 25% vf-f, 75% mud | 1021 | | | Sampled from shaker |
| 580' | lith | 2 | | | | | | | | | vf-f of mud, int 8.9 |
| | | | | | 582 | | mud, 56/4/1 (dk greenish gray). Unconsolidated. | | | | run in HCl |
| | | | | | | | idated. No gravel. Samples washed slightly. Mud-st. | | | | |
| | | | | | 585 | | GRAVELLY MUDGY SAND - 25% gravel | 1028 | | | Sampled from shaker |
| 585' | lith | 2 | | | | | (mostly vf-f-m), 46% sand, 35% mud (some | | | | |
| | | | | | 587 | | clay (slightly), 56/4/1 (dk greenish gray) | | | | |
| | | | | | | | Sample washed slightly. Unconsolidated. | 1035 | | | drilling still |

W = wet, M = moist, D = dry

A-1800-003 (05/90)

DAILY BOREHOLE LOG				Boring or Well Number <u>69A-32-22B</u>		Depth <u>585' - 610'</u> Sheet <u>2</u> of <u>4</u>	
Location <u>SE of 200E</u>				Project <u>Savage Island</u>			
Logged by <u>MA Chalmers</u>		Print		MA Chalmers		Date <u>5/15/91</u>	
Reviewed by		Print				Date	
Lithologic Classification Scheme <u>NA</u>				Procedure <u>DD-1, DD-5</u>		Rev No <u>1, 0</u>	
Measuring Equipment <u>NA</u>							
Drilling Contractor <u>Service Industries</u>				Driller <u>Art Gwin, Dennis Mingo, Lee Karch</u>			
Rig/Method <u>Mud rotary, S.C.T.M.</u>							

| DEPTH | SAMPLES
TYPE NO. | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
PARTICLE SIZE DIST. SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC. | TIME | H ₂ O
ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) |
|--|---------------------|---------------|---------|----------|-------------|---|------|---------------------------|---|
| | | INSTRUMENT | READING | | | | | | |
| 590' | Lith 2 | | | 590 | | SLIGHTLY GRAVELLY SANDY MUD - 5% gravel (mostly v-f), 35% v-f-mc, 60% mud. Dk greenish gray (504/1). Un-
consolidated. Samples washed slightly in HCl | 1104 | | Drilling |
| 600' | Lith 2 | | | 600 | | SANDY MUD - 35% v-f, 65% mud. Two separate colors - 544/1 (dk gray) in
small sl. coarse chunks, + 544/1
(dk greenish gray) in slightly coarser
sandier chunks. Very little gravel. Samples
washed slightly, sl. rxn in HCl. | 1112 | | Sampled from water |
| 605' | Lith 2 | | | 605 | | SANDY MUD - similar to above but with
1 color - dk bluish gray (584/1). Unconsolidated.
Samples washed slightly. No rxn in HCl. | 1145 | | Sampled from water |
| 610' | Lith 2 | | | 610 | | SANDY GRAVEL - coarse, sl. chunks in
mostly v-f-mc, 5A-1, 15% gravel, 30% v-f
gravel, 55% fine / medium. v-f from same
sand. mud chunks mixed in. Samples
washed slightly, No rxn in HCl. | 1245 | | Stopped for lunch |
| | | | | | | | 1257 | | Sampled from water -
hit gravel @ 610' |
| <p>Apparent I missed a sample in this drill log. I believe it was the 595' sample + was numbered accordingly. A-1800-003 (05/90)</p> | | | | | | | | | |

DAILY BOREHOLE LOG				Boring or Well Number <u>69A-22-22B</u>		Depth <u>610'</u> - <u>035'</u> Sheet <u>2</u> of <u>4</u>	
				Location <u>SE of 70DE</u>		Project <u>Savage Island</u>	
Logged by <u>MA Channing</u>		Print		MA Channing		Date <u>5/15/91</u>	
Reviewed by		Print				Date	
Lithologic Classification Scheme <u>N/A</u>				Procedure <u>D0-1, D0-5</u>		Rev No. <u>1, D</u>	
Measuring Equipment <u>N/A</u>							
DEPTH	SAMPLES		CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)
	TYPE	NO.	INSTRUMENT	READING			
615'	With 2						EARLY GRAVEL - similar to last sample 1334
Sample washed same. No rxn in HCL.
MUDRY SANDY GRAVEL to SANDY GRAVEL 1338
Similar to above. some b.b. nodules
Gravels slightly larger of c.g. Samples
washed same.
Same as above, increase in H-CA.
Samples washed same, sl. increase in basal.
MUDRY SANDY GRAVEL? - mostly m-vcg
coming across shaker, some of it broken,
the rest s.s.-k. 15% basalt, 15% glt/grite,
70% ign/metam. rk brs.
Basalt? - Drills fine sand by jumping 1410
around, but the basalt was fine very
similar to one another. a 80% wash, not
of it angular, nicely layered, coarse-grained
a few vesicles but not really vitric,
some blue green clay in some vesicles.
620'	With 2						
625'	With 2						
630'	With 2						
635'	With 2						
640'	With 2						
645'	With 2						
650'	With 2						
655'	With 2						
660'	With 2						
665'	With 2						
670'	With 2						
675'	With 2						
680'	With 2						
685'	With 2						
690'	With 2						
695'	With 2						
700'	With 2						
705'	With 2						
710'	With 2						
715'	With 2						
720'	With 2						
725'	With 2						
730'	With 2						
735'	With 2						
740'	With 2						
745'	With 2						
750'	With 2						
755'	With 2						
760'	With 2						
765'	With 2						
770'	With 2						
775'	With 2						
780'	With 2						
785'	With 2						
790'	With 2						
795'	With 2						
800'	With 2						
805'	With 2						
810'	With 2						

A-1800-003 (05/90)

66

Depth 635' - 640 Sheet 4 of 4
Project Cowage Island

MH Chambers Date 5/15/91

Date _____

Procedure NO-1 DO-5 Rev No. 10

Procedure NO-1 DO-5 Rev No. 10

11/1/91	22	12/1/91

A-1800-003 (05/90)

56

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22B</u>			Depth <u>640'-645'</u> Sheet <u>1</u> of <u>2</u>			Project			
Location <u>SE of 200E</u>			Date <u>5/16/91</u>			Drilling Contractor <u>Jensen Drilling</u>			
Logged by <u>SS Teel</u> Print			Sign			Driller <u>Art Swin / Joe Roach / Dennis Mingo</u>			
Reviewed by			Sign			Rig/Method <u>Speedstar - SS-15 TH / Mud Rotary</u>			
Lithologic Classification Scheme <u>Folk</u>			Procedure <u>DO-1, S</u>			Rev No. <u>L 0</u>			
Measuring Equipment <u>N/A</u>									
DEPTH	SAMPLES	CONTAMINATION	MOD-
TURE	GRAPHIC
LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOCK COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)	
						0700			
					Upon further examination of the 645' sample				Drillers tripping-out 3 sections
					SS Teel + MacHamess have decided that it is				of rod - will add a short
					BASALT rather than gravel. There is a lot of "rotten"				piece, and then trip-in
					basalt material in the matrix. Gravels are carry-	0854			again.
					down from above	0945			Drilling
645' Lith 2					BASALT SS 5/23/91				Bit @ 645'
					moist sandstone gravel. Difficult to tell	0951			Collect sample from shaker
					9% of mud & sand - appear to be getting a				
					lot of carry-down from above mud units. Gravels				
					are rounded - well rounded on orig. surf. and				
					appear to have a max grain size of at least 1/4",				
					See several whole or nearly whole MP gravels.				
					Gravels are 40% basalt, 60% granite and meta-				
					sed, trace red. g. f. z. e. Well-consolidated -				
					drilling very slow. Wet color of mud - 5Y 4/1	1010			Stopped drilling to tighten
					(dark gray).				seal.
						1012			Drilling
					Note: Checked samples about every 1-ft	1017			Mud hose breaks - stop
					between 640 and 645' - think that it				drilling
					is gravel rather than basalt, looks very				Vis = 102; wt = 9.4
					sim. to 645'.				

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG	Boring or Well Number	699-32-22B	Depth	645'-655.7'	Sheet	2	of	2
	Location	SE of 200E		Project	Savage Is			

[illegible]

W = wet, M = moist, D = dry

Total of 15.7' A-1800 003 (05/90)

1 of 1

1 of 1

DA

1000

A-1800 003 (05/90)

59

DAILY BOREHOLE LOG										Boring or Well Number <u>699-32-22B</u>		Depth <u>655.7</u> Sheet <u>1</u> of <u>1</u>	
Location <u>SE of 200E</u>										Project <u>Savage Is.</u>			
Logged by <u>SS Teel</u>		NA Chambers		SS Teel		NA Chambers		Date <u>5/21/91</u>		Drilling Contractor <u>Jensen Drilling</u>			
Reviewed by		Print		Sign		Date		Driller <u>Art Gwin / Joe Roach / Dennis Mingo</u>					
Lithologic Classification Scheme <u>NA</u>		Procedure <u>D0-1, D0-2</u>		Rev No. <u>1.0</u>		Rig/Method <u>SS-15 III / Mud Rotary</u>							
Measuring Equipment <u>NA</u>													
DEPTH	SAMPLES	TYPE	NO.	CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE, SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASING	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)	
				INSTRUMENT	READING								
								Drillers will trip-in and then trip-out today	0700				Preparing to trip-in
								to clean-out the hole in preparation for					
								adding the carbon steel casing.					
								Span is set @ 6.54 to read 56 ppm	0730				Calibrate instruments
									0735				Check Borehole
									0745				Tripping-in
									0755				Christine Bartley (K&H Safety)
													arrives and delivers a new
													LEL/O ₂ meter.
									0800				Christine Bartley leaves.
									0850				Bob Jones (WHC) on site
									0920				Bob Jones leaves site
									1130				Bit at bottom of hole -
													- circulating
									1255				NA Chambers taking over for
													Steve Teel, start tripping
									1325				
									1410				Finished tripping out
									1455				Removal rotating head, rigging
													14. Casing cutter
									1725				Quit for day

A-1800 003 (05/90)

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG

Boring or Well Number 699-22-22B Depth 655.7' Sheet 1 of 2
 Location SE of ZOE Project Savage Island

Logged by MA Chavannes Print

Reviewed by _____ Print

Lithologic Classification Scheme NA

Measuring Equipment 11A

Drilling Contractor Seismic Drilling

Driller Art Guin, Carlos Hago, Sr. Rocio

Rig/Method SE 15 III, rotary

Date 5/22/71

Sign

Date

Rev No. 1.0

Procedure LO-1, DO-S

| DEPTH | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-------|---------|-----|---------------|---------|----------|-------------|---|------|------------------------|--|--------------------------|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | CASING | |
| | | | | | | | | | | 203.49' | at 10" casing |
| | | | | | | | | | | | Expanded 10" casing line |
| | | | | | | | | | | | Geologist on site |
| | | | | | | | | | | | Finished vulcanize line |
| | | | | | | | | | | 20.21' | |
| | | | | | | | | | | 20.21' | |
| | | | | | | | | | | 20.31' | |
| | | | | | | | | | | 20.13' | |
| | | | | | | | | | | 20.21' | |
| | | | | | | | | | | 20.08' | |
| | | | | | | | | | | 22.194' | Stop for lunch |
| | | | | | | | | | | 21.15 | |
| | | | | | | | | | | 21.13 | |
| | | | | | | | | | | 21.15 | |
| | | | | | | | | | | 21.15 | |
| | | | | | | | | | | 21.15 | |
| | | | | | | | | | | 21.17 | |
| | | | | | | | | | | 21.17 | |
| | | | | | | | | | | 21.01 | |
| | | | | | | | | | | 16.15 | Drilling 10' - 100' |

W = wet, M = moist, D = dry

A-1800-003 (05/90)

1 of 1

very brilliant

Dennis M.relaxing

DRILLING COMM

| DEPTH | CONTAMINATION | | MOIS-
TURE | GRAPHIC
LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O
ADDED | CASING | (DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) |
|-------|---------------|-----|---------------|----------------|--|------|---------------------------|---------|--|
| | TYPE | NO. | | | | | | | |
| | | | | | | 705 | | 594.25' | Geologist on site |
| | | HNH | | | HNH calibrated to Supram w/ span @ 6.33 | 715 | | + 20.25 | Welding ears on casing |
| | | LEL | | | | 755 | | 20.27 | Welding casing |
| | | | | | | | | 20.13 | |
| | | | | | | | | 654.9' | of 10" carbon steel casing |
| | | | | | | | | | Should be just about the |
| | | | | | | | | | right amount. |
| | | | | | | 845 | | | Unshod cut inside of clasp |
| | | | | | | 940 | | 2.5' | on water tank w/ 205 E H ₂ O |
| | | | | | | | | 657.4' | |
| | | | | | | 1015 | | | Running drill rot in hole 661' |
| | | | | | | 1205 | | | lunch |
| | | | | | | 1220 | | | Unshod cut inside of clasp |
| | | | | | | 1420 | | | Mixing grout 1st batch w/ 205 |
| | | | | | | | | | 14.7 used 205 E H ₂ O for refueling |
| | | | | | | | | | batch ~ 1800 gal. |
| | | | | | | 1505 | | | Start pumping 1st batch, 2nd batch |
| | | | | | Casing is sitting on bottom of hole, at | | | | out at 14.05. |
| | | | | | w/ 55.4. | | | | Grout coming up thru annulus, |
| | | | | | | 1615 | | | used ~ 3450 gal of grout |
| | | | | | | | | | Galled 16" out, cut at 22' |
| | | | | | Pulling out drill rod | 1645 | | | below ground |
| | | | | | | 1715 | | | |

A 1800 0003 (05 00)

6

Boring or Well Number 699-32-22B
CC of 2006

DAILY BOREHOLE LOG

SS Steel Sign

Sign	

DO-1

**LITHO
PARTICLE SIZE**

[illegible]

W = wet, M = moist, D = dry

A-1800-003 (05/90)

Boring or Well Number 699-22-220
Location SE of 201E

Boring or Well Number 699
Location SE of 2011 E

Depth 655.7' - 660' Sheet
Project Survey 2 Land Land

of 2

Logged by CAA Channels Print

MA Charness
SignDate 5/26/91

Reviewed by _____ Print _____

Sign

Date _____

Lithologic Classification Scheme 11A

Procedure 10-110-5

Rev No. 1,0Measuring Equipment 1) A

1

| DEPTH | SAMPLES | | CONTAMINATION | | MOD-
TURE | GRAPHIC
LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL ETC.) | TIME | H ₂ O
ADDED | CASING | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) |
|-------|---------|-----|---------------|---------|--------------|----------------|--|------|---------------------------|--------|--|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | | |
| | | | | | | | Calibrated HNUA to ±6 ppm w/ span 20 | 715 | | | Geologist on site. |
| | | | | | | | G.C.B. | 730 | | | Driller fixing drill rig |
| | | | | | | | | 804 | | | Pushing water added after grinding out of hole. |
| | | | | | | | | 825 | | | Start drilling out grout + float shoe. |
| | | | | | | | Have cotton virtually no returns, fine-toothed tri-cone rock bit is grinding basalt into very small pieces and this is sticking to the tools instead of blowing out. | 1000 | | | Told Art - the use of MHS-1 foaming agent would be ok. |
| | | | | | | | BASALT - only got a few chips, dk gray med-coarse grained, macrocrystalline to dihydroxite, microphytic. Fresh. | 1050 | | | Finally got ~10 chips up to 2 mm in diam. Returns very poor. Will use an extra pump to put more water in ~25 gal/min instead of 5 gal/min. |
| | | | | | | | | 1120 | | | Start drilling. The last leaks stop to replace. |
| | | | | | | | | 1130 | | | Laborers bring out aquifer test equipment. Lookie ok |
| | | | | | | | | 1145 | | | Start drilling, little water, no chips or returns |
| | | | | | | | | 1740 | | | lunch |

W = wet, M = moist, D = dry

A-1800-003 (05/90)

DAILY BOREHOLE LOG

Boring or Well Number 699-37-22B Depth 660' - 687' Sheet 2 of 2
Location SE of 700E Project Savage Island

Logged by MA Channess
Print

MA Channess Date 5/29/11
Sign

Reviewed by _____

Date _____

Lithologic Classification Scheme NA

Procedure 10-1, DO-5 Rev No. 1, 0

Measuring Equipment V.1A[illegible]

W = wet, M = moist, D = dry

A-1800-003 (05/90)

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22B</u>				Depth <u>686.2</u>		Sheet <u>1</u> of <u>1</u>		Project <u>Savage Island</u>	
Location <u>SE of 200E</u>				Date <u>5/30/91</u>		Drilling Contractor <u>Jensen Drilling</u>			
Logged by <u>SS Teel</u> Print				Sign		Driller <u>Art Gwin / Joe Roach / Dennis Mingo</u>			
Reviewed by				Date		Rig/Method <u>SS-15 III / Air Rotary</u>			
Lithologic Classification Scheme <u>Folk</u>				Procedure <u>DO-1, 5</u>		Rev No. <u>1, 0</u>			
Measuring Equipment									
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLANK COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)	
	TYPE	NO.	INSTRUMENT	READING				CASING	
						0730			Geologist on site
					Span is set @ 5.82 to read 56 ppm.				Calibrate Instruments
						0737			Check Borehole
					D/water = 113.7 - 3.0 = 110.7 b.l.s. w/ slope 0.115				
					D/bottom = 686.2 meas. w/ geophysical logging truck.	0845			
						0850			D. Newcomer arrives to perform slug test.
									Begin slug injection test
					Check Borehole	1016			Withdrawal slug rod
						1240			Pull transducer from well.
						1340			Waiting on driller to return from getting generator.
									Driller returns w/generator
						1430			Setting Pump
						1500			D. Newcomer leaves
					5HP pump is set - bottom of pump is at 299 Ft. Connecting discharge pipe + flowmeter.	1620			Flowmeter @ 76050 (Hemmet McCrometer)
									Driller tried to get generator going - need plug for pump wiring -
						1730			Will start aquifer test tomorrow

DAILY BOREHOLE LOG				Boring or Well Number <u>699-32-22B</u>		Depth <u>686.2</u> Sheet <u>1</u> of <u>1</u>				
Location <u>SE of 200E</u>				Project _____						
Logged by <u>SS Teel</u>		Print		Date <u>5/31/91</u>		Drilling Contractor <u>Jensen Drilling</u>				
Reviewed by _____		Print		Date _____		Driller <u>Art Gwin / Joe Roach / Dennis Mingo</u>				
Lithologic Classification Scheme <u>N/A</u>		Procedure <u>DO-1, 5</u>		Rev No. <u>110</u>		Rig/Method <u>SS-15-III / Air Rotary</u>				
Measuring Equipment <u>N/A</u>										
DEPTH	SAMPLES	CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASING	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
		NO.	INSTRUMENT							
							0700			Drillers on site - waiting for plug for generator
							1100			Art Gwin arrives with plug - attaching to pumpwires
							1120			Pump ready to go - D. Newcomer
							1130			setting up equipment
							1150			SS Teel on site
										SS Teel delivers mud sample to 183KE Lab
							1250			SS Teel on site
							1300			Pump on
							1345			Pump keeps kicking - out - will not run for more than 5 min. Bad control box?
										Pat Collier on site
							1400			Pat leaves to get another box
							1405			
										Check Borehole
							1410			Pat cannot find a box -
							1500			Art goes to town to get one.
										Art on site w/ Box
							1700			Leave site - pump is working OK
							1900			

Calibrate instruments - span set @ 5.15 to read 56 ppm

Note: Foam has arrived - MLS no 1, Mitchell, Lewis and Staver CO

9935 S.W. Commerce Circle, Wilsonville, OR, 97070

W = wet, M = moist, D = dry

[illegible]

A-1800 003 (05/90)

DAILY BOREHOLE LOG

 Boring or Well Number 699-32-22B Depth 686.2 Sheet 1 of 1
 Location SG of 200E Project Savage Is.
Logged by SS Teel

Print

SS Teel

Sign

Date 6/3/91

Reviewed by _____

Print

Sign

Date _____

Lithologic Classification Scheme N/AProcedure DC-1, 5Rev No. 1.0Measuring Equipment N/ADrilling Contractor Jensen DrillingDriller Art Gwin / Joe Roach / Dennis MingoRig/Method SS-15 III / Air Rotary

| DEPTH | SAMPLES | | CONTAMINATION | | MOIS-
TURE | GRAPHIC
LOG | LITHOLOGIC DESCRIPTION
PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O
ADDED | CLOGGING | DRILLING COMMENTS
(FORMLING DATE, INLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) |
|-------|---------|-----|---------------|---------|---------------|----------------|---|-----------|---------------------------|----------|---|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | | |
| | | | | | | | | 0700 | | | Drillers on site - pulling pump. |
| | | | | | | | | 0915 | | | Calibrate instruments |
| | | | | | | | | 0930 | | | Pump is out - preparing to add tremie pipe for grouting |
| | | | | | | | | 0945 | | | Adding tremie pipe |
| | | | | | | | | 1145 | | | Tremie set |
| | | | | | | | | 1209/1230 | | | Preparing for grouting |
| | | | | | | | | 1245 | | | Lunch |
| | | | | | | | | | | | Mixing grout |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | 1308 | | | Pumping Grout |
| | | | | | | | | 1310 | | | Mixing 2 nd Batch |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | 1320 | | | Pumping Grout |
| | | | | | | | | 1340 | | | Pumping 3 rd Batch |
| | | | | | | | | | | | Pumping displacement water |
| | | | | | | | | 1350 | | | Pulling tremie to 565' |
| | | | | | | | | 1405 | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |

Circulating - cleaning - out tremie pipe

Leave Site

A-1800-003 (05/90)

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG									
Boring or Well Number <u>69-32-22B</u>				Depth <u>1066.2'</u> - <u>700'</u> Sheet <u>1</u> of <u>2</u>		Project <u>Savage Island</u>			
Location <u>SE of 200E</u>				Date <u>6/4/91</u>		Drilling Contractor <u>Jensen Drilling</u>			
Logged by <u>MA Chawners</u>				Sign		Driller <u>Art Guin, Dennis Mingo, Joe Roach</u>			
Reviewed by				Date		Rig/Method <u>SSIS III, rotary w/ foam</u>			
Lithologic Classification Scheme <u>NA</u>				Procedure <u>DO-1, DO-5</u>		Rev No. <u>1, D</u>			
Measuring Equipment <u>NA</u>									
DEPTH	SAMPLES	CONTAMINATION	MODS-TURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE, SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	CASING	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
						700			Driller tagged <u>10' of gravel</u> , @ <u>1654'</u> <u>logs</u> , pulling out
						730			traverse pipe
						855			Running drill rod in
						1055			Cleaning out hole, starting to drill out gravel, forming agent added to drill water
									Adding drill rod
						1108			drilling
						1112			Back down to bottom of hole
						1148			Drilling
						1152			lunch/safety mtg w/ Ed Enloe
						1200/1245			Drilling
						1245			Sampled from air discharge
						1302			Drilling slow
									Still drilling slow
						1345			
						1415			Don Berg on site for video
						1423			

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG				Boring or Well Number <u>699-32-22B</u>		Depth <u>712' - 730'</u> Sheet <u>1</u> of <u>2</u>		Project <u>Savage Island</u>	
Logged by <u>MA Chumness</u> Print				MA Chumness Sign		Date <u>6/5/91</u>		Drilling Contractor <u>Jensen Drilling</u>	
Reviewed by				Sign		Date		Driller <u>Art Gwin, Dennis Mingo, Joe Roach</u>	
Lithologic Classification Scheme <u>NA</u>				Procedure <u>DO-1</u>		Rev No. <u>1.0</u>		Rig/Method <u>Rotary (air), SS IS III</u>	
Measuring Equipment <u>2-tape</u>									
DEPTH	SAMPLES	CONTAMINATION	MOS-
TURE	GRAPHIC
LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)	
	TYPE	NO.	INSTRUMENT	READING				CASING	
					<u>NO 111.4' bgs. Cannot tell right now</u>	<u>715</u>			
					<u>whether water is from interflow zone</u>				
					<u>above or a new zone at 717'</u>				
					<u>Calibrated HNU to Slappm w/ span</u>	<u>725</u>			<u>* Reading ~ 1 ppm @ discharge,</u>
					<u>at 6.2</u>				<u>probably due to high air velocity</u>
									<u>from discharge</u>
						<u>735</u>			<u>Drilling</u>
					<u>BASALT - pulverized to sand size & finer</u>	<u>750</u>			<u>Sampled from air discharge</u>
					<u>Probably carbonate based on coarser texture</u>				
					<u>and lighter color of pieces collected</u>				
					<u>at ~ 717' yesterday.</u>				
					<u>BASALT - pulverized to sand & finer</u>	<u>840</u>			<u>Sampled from air discharge</u>
									<u>Drilling slow but smoothly</u>
						<u>920</u>			<u>Rotu-Rooter man here to take</u>
									<u>mud to Pit 10 near 300 Area</u>
					<u>BASALT - same as above, too fine to</u>	<u>930</u>			<u>Sampled from air discharge</u>
					<u>tell much</u>				<u>Drilling rougher in places</u>
					<u>BASALT - same as above, too fine to</u>	<u>1011</u>			<u>Sampled from air discharge</u>
					<u>see much</u>				
									<u>Hydraulic hose broke, cleaning</u>
						<u>1043</u>			<u>up and that spilled</u>
									<u>Started drilling again</u>
						<u>1315</u>			

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22B</u>				Depth <u>730'-750'</u> Sheet <u>2</u> of <u>2</u>				Project <u>Savage Island</u>	
Location <u>SE of ZONE</u>				Drilling Contractor <u>Jensen Drilling</u>				Driller <u>SAME</u>	
Logged by <u>MA Chaurasia</u> Sign _____				Date <u>10/5/91</u>				Rig/Method <u>SEMI</u>	
Reviewed by _____				Date _____				Drilling Rate, Down Time, Blow Counts, Water Level, Drill Fluid, ETC.)	
Lithologic Classification Scheme <u>DA</u>				Procedure <u>DD-1</u> , <u>DD-5</u>				Rev No. <u>1, 2</u>	
Measuring Equipment <u>NA</u>									
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	CASING	
725'	lith 1			(S)	BASALT - Got some chips at 735' med.-grained microporphic, dk grayish black. Some fracture surfaces w/ greenish black lining seen.	1440		sampled from air discharge	
740'	lith 1			(S)	BASALT - pulverized to sand + silt. Can't tell much from this.	1510		sampled from air discharge	
				(-)	NOTE - The sample collected from interflow zone was apparently oxidized. The blue-green clay has become olive green and there are now red areas on the basalt where there were none before. Must be anaerobic at depth?			Drilling slow + smooth	
745'	none			(S)	BASALT - ground to f-vfs + silt size, 1605. didn't get enough returns to be worth collecting. A lot of metal chips, either from bit or from stainless steel weight dropped in hole a few days ago.	1605			
750'	lith 1			(S)	BASALT - ground to sand + silt. 1714. BASALT chips, looking air clean out hole; dk grayish-black, coarse-grained, microporphic, pignite on some fracture surfaces.	1714			
751'	none			(S)		1720			
				(S)		1720			
								Quit for day	

W = wet, M = moist, D = dry

Depth 130-165 Sheet _____
Project Savage Is.

Logged by SS Teel

Print

1

Design

Date 6/6/91

Reviewed by

Print

1

Sign

Date _____

Lithologic Classification Scheme

Procedure DO-1,5

Rev No. 110

Measuring Equipment

DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WASH
FLUID)

DRILLING COMMENTS
E. DOWN TIME, BLOW COUNTS, WATER LEVEL, D
FIG 1

COMMENTS
V COUNTS, WATER LEVEL, DRILL FLUID,
°C)

| DEPTH | SAMPLES | | CONTAMINATION | | MODS-
TURE | GRAPHIC
LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O
ADDED | CASING | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) |
|-------|---------|-----|---------------|---------|---------------|----------------|--|------|---------------------------|--------|---|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | | |
| | | | | | | | No water level taken - driller says water was pretty high - probably same as yesterday | 0730 | | | Draining water from hole |
| | | | | | | | Span set @ 5.36 to read 56ppm | 0745 | | | Drilling w/ air rotary |
| | | | | | | | | 0830 | | | Calibrate instruments |
| | | | | | | | | 0835 | | | Check discharge pipe |
| | | | | | | | | | | | |
| 755' | — | — | | | | 750' | BASALT - no samples - no good returns - still drilling slow. | 0845 | | | |
| | | | | | | | | | | | |
| 760' | Lith | 1 | | | | | BASALT - VFS - silt size fragments
SY 2.5/2 (black) - wet; SY 4/1 dry color | 0937 | | | Sample @ discharge pipe |
| | | | | | | | | | | | |
| 761' | Lith | 1 | | | | | BASALT - cleaning out hole - was able to get some bigger chips. Dry color 14/ (dark gray) med. xelling, looks rel. "fresh" play phenocrysts, also black "spots" (alt products? - clay?). | 0955 | | | Sample at discharge pipe |
| | | | | | | | | 1000 | | | Adding drill rod |
| | | | | | | | | | | | |
| 765' | — | — | | | | | BASALT - ground to VFS - silt size
Dry color: SY 4/1 (dark gray)
Wet color: SY 2.5/1 (black) | | | | No sample collected |
| | | | | | | | | | | | Still drilling @ 5' / hr. |

W = wet, M = moist, D = dry

A-1800 003 (05/90)

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22B</u> Depth <u>765'-781'</u> Sheet <u>2</u> of <u>3</u>
Location <u>SE of 200E</u> Project <u>Savage Is.</u>				Drilling Contractor <u>Jensen Drilling</u>
Driller <u>Art Gwin / Dennis Mingo / Joe Roach</u>
Rig/Method <u>SS-15 III / Air Rotary</u>					
Logged by <u>SS Teel</u> Print Date <u>6/6/91</u>
Reviewed by _____ Sign Date _____
Lithologic Classification Scheme <u>N/A</u> Procedure <u>DO-1, S</u> Rev No. <u>1, 0</u>
Measuring Equipment <u>N/A</u>									
DEPTH	SAMPLES	CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
		NO.	INSTRUMENT						
770'	Lith 1					Note: Submersible pump previously used was a Grundfos 8822 type 25S 25 USGPM @ 519' BASALT - ground to VFs - silt size wet color - SY 2.5/1 (black) dry color - SY	1150		Consistent drill rate ~ 5'/hr.
							1210		Sample at discharge pipe
							1240		Lunch
							1245		Drilling
									Aquifer is producing ~ 10 gal/min.
							1255		Check discharge pipe
775'	Lith 1		HMU	0ppm		BASALT - slightly coarser than 761' sample, still dark gray, rel. fresh, med kalline, black "spots", very sim to 761' sample.	1400		Sample from discharge pipe
			LEC	0.90					still drilling @ 5'/hr
			OZ	20.8%					
781'	Lith 2					CLAYEY PYMICE/TUFF - 5Y4/1 to 5GY5/1 (wet) (Dry color N6.5) stickier clay. Finestuff is very light in density and has abundant small vesicles and is very coarse-grained. Sample also contains trace fresher-looking, denser pieces of basalt with 2-3 mm size clay-filled vesicles	1430		Sample from discharge pipe
									Big increase in drill rate @
									776' - drilled from 776 to
									781 in about 2 min.
									Pulling drill rod in prep. for grouting

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22B</u>			Depth <u>779.3</u>		Sheet <u>1</u> of <u>2</u>				
Location <u>SE of 200E</u>			Project <u>Savage Is</u>						
Logged by <u>SS Teel</u>			Date <u>6/7/91</u>		Drilling Contractor <u>Tensen Drilling</u>				
Reviewed by _____			Date _____		Driller <u>Art Gwin / Dennis Mingo / Joe Foeach</u>				
Lithologic Classification Scheme <u>N/A</u>			Procedure <u>DD-1,5</u>		Rig/Method <u>SS-15 TIL / Air Rotary</u>				
Measuring Equipment <u>Logging truck</u>			Rev No. <u>1,0</u>						

| DEPTH | SAMPLES | | CONTAMINATION | | MONITORING | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) |
|-------|---------|-----|---------------|---------|------------|-------------|---|------|------------------------|--|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | |
| | | | | | | | Measuring D/Bottom w/ geophysics logging | 0730 | | |
| | | | | | | | truck to check height of sand backfill | | | |
| | | | | | | | D/Bottom = 772.65 | 0800 | | |
| | | | | | | | D/water = 117.65 - 3.75 = 113.9' | | | |
| | | | | | | | meas. w/ E-tape #11053 | 0830 | | |
| | | | | | | | | 0900 | | |
| | | | | | | | | 0915 | | |
| | | | | | | | LEL O ₂ meter that Ed dropped off today | 0930 | | |
| | | | | | | | doesn't work - called him for replacement | | | |
| | | | | | | | | 0935 | | |
| | | | | | | | Tremmie pipe for cement set @ 771' b.i.s. | 1015 | | |
| | | | | | | | | 1130 | | |
| | | | | | | | Acme cement truck arrives - truck is | 1238 | | |
| | | | | | | | loaded w/ 6250 lbs of cement (66 sacks) | | | |
| | | | | | | | Will mix 6.0 gal / sack (400 gal) | | | |
| | | | | | | | Added 1-50 lb bag CFM (additive) | | | |
| | | | | | | | 190 CaCl (60 lbs) | | | |
| | | | | | | | 190 Hydrogel (60 lbs) | | | |
| | | | | | | | Total water added was ~ 403 gal | 1320 | | |
| | | | | | | | Cement wt = 14,7 | | | |
| | | | | | | | | 1350 | | |
| | | | | | | | | | | Pumping grout |

DAILY BOREHOLE LOG										Sheet 1 of 1	
Boring or Well Number 1099-22-22B
Location SE of 200E				Project Savage Island							
Logged by <u>MA Chavannes</u> Print
Checked by _____
Lithologic Classification Scheme <u>NA</u>
Measuring Equipment <u>NA</u>				Drilling Contractor <u>Jensen Drilling</u>
Driller <u>Art Gunn, Dennis Mingo, Joe Roach</u>
Rig/Method <u>Air rotary SSIS III</u>							
Date <u>10/8/91</u>
Date _____
Sign _____
Procedure <u>D-1, D-5</u> Rev No. <u>1.0</u>											
DEPTH	SAMPLES		CONTAMINATION		MOIS-
TURE	GRAPHIC
LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)	
	TYPE	NO.	INSTRUMENT	READING							
								745		Geologist on site, drillers just finished running drill rod in.	
								750		Start drilling, using new bit slightly larger than old one.	
								755			
								805			
								840		Started drilling and into base of at ~684' getting a little inter- flow material.	
								915		Stopped drilling, stopped adding water, hole is making ~3 gal/min PB = 691'	
								1020		Art went to get more cement. Art back, will place grout three drill rods.	
								1045		Mixed 20 100 lb bags Portland Type I + II + type IP cement w/ 120 gal of water, displaced w/ ~500 gal water.	
								1325			
								1700		Picking up site, getting for day, back Tues.	

[illegible]

A-1800-003 (01/90)

DAILY BOREHOLE LOG

Boring or Well Number 699-32-22B
 Location SE of 200E

Sheet 1 of 1

Project Savage IS

Logged by SS Teel Sign SS Teel Date 6/12/91
 Checked by Print Sign Print Date
 Lithologic Classification Scheme N/A Procedure DO-1, S Rev No. 1, 0

Drilling Contractor Jensen Drilling
 Driller Art Gwin / Joe Roach
 Rig/Method Speedstar SS-15 III / Air Rotary

| Measuring Equipment | | | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|---------------------|----------|----------------|---------|----------|-------------|---|-----------|------------------------|--|--|
| DEPTH | SAMPLES | CONTAMINATION | READING | | | | | | CASING | |
| | TYPE NO. | INSTRUMENT | | | | | | | | |
| | | | | | | Bit is tri-cone, 9 7/8 OD, "rock-bit" (mill-tooth) | 0830 | | | Bit is on site - preparing to run down hole |
| | | | | | | Span is set @ 4.08 to read 56 ppm - same spargers as prev. | 0900 | | | Calibrate instruments |
| | | HMU | 0 ppm | | | | 0915 | | | Check borehole |
| | | LEL | 0% | | | | 1015 | | | Adding drill rod |
| | | O ₂ | 20.81% | | | | 1100-1105 | | | Ed Enloe on site |
| | | | | | | | 1320 | | | Drilling w/ air rotary |
| | | | | | | Depth = 660' - 100% grout returns | 1330 | | | |
| | | | | | | 660-690' - 100% grout - no water | 1430 | | | Driller has to hold back on the brake quite a bit in order to have a smooth hole because it is biting into the basalt. |
| | | | | | | 705' - 75% grout - 25% basalt - no water | 1500 | | | |
| | | | | | | 705-715' much more basalt - 50-60% slower drilling | | | | Cleaning - out hole |
| | | | | | | Depth = 716' - still x 50% basalt - driller thinks we are 1/2 in and 1/2 out of original hole | 1720 | | | |
| | | | | | | Can't tell if water is in hole or not - will take a WL measurement tomorrow morning. | 1800 | | | Leave site |

DAILY BOREHOLE LOG

Boring or Well Number 699-32-22B
Location SE of 200EProject Savage Island Sheet 1 of 2 84Logged by SS Teel Print SS Teel Date 6/13/91
Checked by Art Gwin / Joe Roach Sign Art Gwin / Joe Roach Date 6/13/91
Lithologic Classification Scheme N/A Procedure DD-1, 5 Rev No. 1, 1DDrilling Contractor Jensen Drilling
Driller Art Gwin / Joe Roach
Rig/Method Speedstar SS-15 II / Air Rotary

Measuring Equipment

| DEPTH | SAMPLES | | CONTAMINATION | | MOIS-
TURE | GRAPHIC
LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O
ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.) | |
|-------|---------|-----|---------------|---------|---------------|----------------|--|------|---------------------------|---|---|
| | TYPE | NO. | INSTRUMENT | READING | | | | | | CASING | |
| | | | | | | | | 0700 | | | Drillers on site |
| | | | | | | | | 0725 | | | Preparing to run straightness
test |
| | | | | | | | | | | | |
| | | | | | | | | 0830 | | | |
| | | | | | | | | 0835 | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | Waiting for Tech Forum decision |
| | | | | | | | | 0840 | | | |
| | | | | | | | | 0905 | | | Note: Air compressor has been
loosing oil into the air stream.
It has lost a total of approximately
5-gal over the past week or
two. This oil is an approved
synthetic oil (non-petroleum) |

V = wet, M = moist, D = dry

A-1800-003 (01/90)

DAILY BOREHOLE LOG

Boring or Well Number	699 - 32-22B	Sheet	2 of 285
Location	SE of 200E	Project	Savage Is

DAILY BOREHOLE LOG

Boring or Well Number 699-32-22B Sheet 2 of 2

Location SE of 200E Project Savage Is

Drilling Contractor Jensen Drilling

Driller Art Gwin / Joe Roach

Rig/Method SS-15 TIL / Air Rotary

[illegible][illegible]

A-1800-003 (01/90)

Boring or Well Number 699-32-22B Sheet 1 of 1 86
Location SE of 200E Project Savage Is.

Checked by _____ **Date** _____
Print _____ **Sign** _____

E-tape
Measuring Equipment

SAMPLES	CONTAMINATION	DATE	REMARKS	LITHOLOGIC DESCRIPTION

DEPTH	SAMPLES		CONTAMINATION	MOISTURE	GRAPHIC LOG	PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.
	NUMBER	ANALYSIS				
10	10	10				
20	20	20				
30	30	30				
40	40	40				
50	50	50				
60	60	60				
70	70	70				
80	80	80				
90	90	90				
100	100	100				
110	110	110				
120	120	120				
130	130	130				
140	140	140				
150	150	150				
160	160	160				
170	170	170				
180	180	180				
190	190	190				
200	200	200				
210	210	210				
220	220	220				
230	230	230				
240	240	240				
250	250	250				
260	260	260				
270	270	270				
280	280	280				
290	290	290				
300	300	300				
310	310	310				
320	320	320				
330	330	330				
340	340	340				
350	350	350				
360	360	360				
370	370	370				
380	380	380				
390	390	390				
400	400	400				
410	410	410				
420	420	420				
430	430	430				
440	440	440				
450	450	450				
460	460	460				
470	470	470				
480	480	480				
490	490	490				
500	500	500				
510	510	510				
520	520	520				
530	530	530				
540	540	540				
550	550	550				
560	560	560				
570	570	570				
580	580	580				
590	590	590				
600	600	600				
610	610	610				
620	620	620				
630	630	630				
640	640	640				
650	650	650				
660	660	660				
670	670	670				
680	680	680				
690	690	690				
700	700	700				
710	710	710				
720	720	720				
730	730	730				
740	740	740				

[illegible]

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100

[illegible]

	synthetic compressor oil

[illegible][illegible]

"it will arrive Sun night and drilling can

resume on Monday (6/9):

[illegible][illegible][illegible][illegible][illegible]

[illegible][illegible][illegible][illegible][illegible][illegible][illegible]

[illegible][illegible]

— wet, M = moist, D = dry

A-1800-003 (01/90)

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22B</u>					(Report) <u>712' - 785'</u> Sheet <u>1</u> of <u>5</u>				
Location <u>SE of 200 East</u>					Project <u>Swaga Island</u>				
Logged by <u>T Gilmore</u> Print					Drilling Contractor <u>Jensen</u>				
Reviewed by <u>Talk</u> Print					Driller <u>Art Gwin / Joe Rood</u>				
Lithologic Classification Scheme <u>Folk</u>					Rig/Method <u>Robur</u>				
Measuring Equipment <u>Logging Truck</u>									
DEPTH	SAMPLES	CONTAMINATION	MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY,
ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O
ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID,
ETC.)	
	TYPE	NO.	INSTRUMENT	READING				CASING	
					Arrive at site	715			
					Drillers adding new compressor oil				
					to Air compressor Oil used was				
					AEON 6000 Flt - Food grade Synthetic				
					oil manufactured for Gardner - Denver				
					Note: Foaming Agent still being added				
					Run drill rods in hole	735			
					Drilling - D/B 712' Drilling through	740			Drill
					against back to interbed at ~776'				
					Drilling up approx 50' cement / 50' Bit				
					Slowly add weight	840			Add weight to drill string
					Moved back into hole Drilling mostly				
					Cement				
					Depth 736'	920			Connection
					Depth 762'	1100			Connection
					KEH suddenly stopped by (Ed Enloe)				
					Drilling ~ 100' Cement Cement				
					Hit Silica sand (added) just below cement	1136			Hit change Drill bit dropping

W = wet, M = moist, D = dry

A-1800-003 (05/90)

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22 B</u>			Depth <u>785' - 790'</u> Sheet <u>2</u> of <u>3</u>			Location <u>SE of 200 East Savage Island</u>			
Logged by <u>T. G. Williams</u>			Date <u>10/17/91</u>			Drilling Contractor <u>Jensen</u>			
Reviewed by <u>Folk</u>			Date _____			Driller <u>Art Gause</u>			
Lithologic Classification Scheme <u>Folk</u>			Procedure <u>D-1 D-5</u> Rev No <u>1, 2</u>			Rig/Method <u>Air Rotary / Speedstar 35-1577</u>			
Measuring Equipment _____									
DEPTH	SAMPLES	CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
		INSTRUMENT	READING						
785	1148					log time for sand to reach surface. 1148			Discharge water cleanup
						was (7 min) measured at discharge line			
						SILTY SAND - 55% Gr. Sand, 35% BSlt, 10% Silt	1150		sample Interbed
						Added Silicon Sand - Gr. Sand is 60% UFS			
						40% Silt/V. well srt, probab qtz, Tr of Fsp			
						(arg specks) wet color 5 GR 3/4 dk greenish			
						gray, norm in HCL mud consol, sands			
						mod friable - Traces of added silica			
						Sand in Sample			
						Water flow at discharge increased	1200		
						Producing ~ 5-10 gpm	1210-1230		Lunch
						The Sample is so fine most of it lost in discharge line	1300		Drill
						SILTY SAND 85% UFS, 15% Silt, probab	1310		Sample
						qtz sand Tr of bslt and Fsp, some			
						grayly interbeds, some? wet color			
						N5 dk gy Muvu in HCL, no consol			
						cly some more sand V well srt			
790	1148								

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG									
Boring or Well Number <u>699-32-22B</u>			Depth <u>785'-820'</u> Sheet <u>3</u> of <u>5</u>		Location <u>SE of 200 East</u> Project <u>Seawage Island</u>				
Logged by <u>T. Blum</u> Sign _____ Date <u>6/19/91</u>			Drilling Contractor <u>Jensen</u>		Driller <u>Art Jensen</u>				
Reviewed by _____ Sign _____ Date _____			Rig/Method <u>Av. Rotary</u>						
Lithologic Classification Scheme <u>Folk</u> Procedure <u>DD-1 D0-5</u> Rev No <u>1, 2</u>									
Measuring Equipment _____									
DEPTH	SAMPLES	CONTAMINATION		MOISTURE	GRAPHIC LOG	LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DATA, SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.)	TIME	H ₂ O ADDED	DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.)
		TYPE	NO.						
795	Lith 1				795	SILTY SAND A/A Almost no return	1325		
800	Lith 1				800	SILTY SAND Predom qtz NS, no m	1335		
805	Lith 1				805	SILTY SAND Inconsp. Gm cly, ply	1345		
						predom qtz sand 55% sand 10% silt			
						cly stone fragments NS no min in HCL no conc			
810	Lith 1				810	CLAYEY SILTY SAND 10% cly/ash, 15% silt, 75% sand, traces of cly crystals	1350		
						quartzine? in cly; 56% silt/sand			
						in HCL; sl consol; traces of buff			
						colored ash/tuff			
815	Lith 1				815	CLAYEY SILTY SAND 20% cly, 15% silt, 14% 60% sand, 10% silt, sandier qtz	1414		
						Tr buff and silty, cly; degn-buff			
						sl consol in HCL, sl consol			
820	Lith 1				820	SILTY SAND 5% cly 15% silt 80% sand	1420		
						pred cly qtz Traces of another cly mineral			
						quartzine? high reflective talc-like, bl			
						fresh surfaces common, sl-no rhen do			
						HCL			
825	Lith 1				825	CLAYSTONE Sample is 50/50 mix of gm	1433		
						cly and buff-buff cly (56% and			
						100% 1/2 1/2 long) Altered Ash? silt			

W = wet, M = moist, D = dry

DAILY BOREHOLE LOG

Boring or Well Number 699-32-22B
 Location SE of 300 East

Depth 830' - 840' Sheet 4 of 5
 Project SAVAGE Island

Logged by T Gilmore
 Print

Sign

Date 6/17/91

Reviewed by Folk
 Print

Sign

Date

Lithologic Classification Scheme Folk

Procedure D-1; D-5

Rev No 1, D

Measuring Equipment

Drilling Contractor Tensen

Driller Art Gm

Rig/Method Speedstar 55-15III / Air Rotary

| DEPTH | | SAMPLES | | CONTAMINATION | | MOISTURE | GRAPHIC LOG | LITHOLOGIC DESCRIPTION
(PARTICLE SIZE DIST., SORTING, MINERALOGY, ROUNDNESS, COLOR, REACTION TO HCL, ETC.) | TIME | H ₂ O ADDED | DRILLING COMMENTS
(DRILLING RATE, DOWN TIME, BLOW COUNTS, WATER LEVEL, DRILL FLUID, ETC.) | |
|-------------|--------|------------|---------|---------------|--|----------|-------------|---|------|------------------------|--|---|
| TYPE | NO. | INSTRUMENT | READING | CASING | | | | | | | | |
| | | | | | | | | 825 cont. blocky shapes, silty sand, no rxn in HCl no change in drill rate - not as mushy" V well sort
Change in color and texture from previous | | | | Sett fast drilling at 829' |
| 830' | Lith 1 | | | | | | | SILTSTONE Coarse grained less grainy more silty some v. sand in siltstone
no rxn in HCl coarser grain than previous | 1445 | | | |
| 835 | Lith 1 | | | | | | | SANDSTONE/SILTSTONE v.w. sort, 1500
100% silt 40% sand, gy NS; No rxn in HCl silty sand, silty coarser grained than previous | | | | Stop Drilling |
| | | | | | | | | Still in Interbed and out of drill rod 510
need to find subs to adapt to different size rod | 510 | | | Drill |
| 840 - 34h 1 | | | | | | | | Basalt dense blk, some gran. clstone
few vesicles, some cly lined, micro - walline drills fractured | 1610 | | | Change in Drill rate 838'
Lith change - Basalt |

W = wet, M = moist, D = dry

A-1800-003 (05/90)

| DAILY BOREHOLE/WELL
COMPLETION LOG				Boring or Well Number <u>699-32-22B</u>		Sheet <u>1</u> of <u>2</u>	
				Location <u>SE of 200 East Area</u>		Project <u>Savage Island</u>	
Logged by <u>A.W. Pearson</u>		Print		Alan Pearson		Date <u>6/19/91</u>	
Reviewed by		Print		Sign		Date	
Measuring Equipment		Procedure <u>DD-5</u>		Rev No. <u>0</u>			
Drilling Contractor <u>Jensen Drilling Company</u>				Driller <u>Art Gavin</u>			
Rig/Equipment <u>Speedstar SS-15M</u>							

Time	Casing/Screen			Annular Fill			Over-lap	Comments						
	Type	Diam-eter	Length Total	Stickup	Depth	Type			Quan-tity	Stickup	Add-on	Depth		
0700														
0740														Geologist and Drillers at site
0745														Calibrated HWL Span 5.7 Read 55ppm
0730	Carbon Steel	6"	20.74'											Check Wireline HWL = 0ppm, 0.2 = 20.8, EL = 0.2
0805	" "	6"	40.68'											Add 20.74' of Permanent 6" C.S. Casing
0830	" "	6"	60.62'											Add 19.94' of " " " "
0900	" "	6"	80.24'											Add 19.62' of " " " "
0920	" "	6"	100.20'											Add 19.96' of " " " "
0950	" "	6"	121.01'											Add 20.81' of " " " "
1040														Pat Callier (KEH) visits site: informs
														driller that well must be completed
														by July 1, 1991 to meet DOE Milestone
1020	" "	6"	140.80'											Add 19.79' of " " " "
1040	" "	6"	161.37'											Add 20.57' of " " " "
1055	" "	6"	181.97'											Add 20.60' of " " " "
1110	" "	6"	201.90'											Add 19.83' of " " " "
1130	" "	6"	221.04'											Add 19.24' of " " " "
1200	" "	6"	242.07'											Add 21.03' of " " " "
1215														Lunch
1245														Resume Welding
1315	" "	6"	263.01'											Add 20.94' of " " " "
1340	" "	6"	283.71'											Add 20.70' of " " " "

Boring or Well Number 699-32-22B
Location SE of 200 East

Project Savage Island Sheet 2 of 2

Logged by A.W. Pearson Alan Pearson Date 6/19/91
Print Sign
Reviewed by _____ Date _____
Print Sign
Measuring Equipment DD-5 Rev No. 0

Drilling Contractor Jensen Drilling Company
Driller Art Gwin
Rig/Equipment Speedstar SS-15 III

[illegible]

DAILY BOREHOLE/WELL COMPLETION LOG				Boring or Well Number <u>69-32-22B</u>				Sheet <u>1</u> of <u>1</u>						
				Location <u>SE of 200 East Area</u>				Project <u>Savage Island</u>						
Logged by <u>A.W. Pearson</u> Print
Reviewed by _____ Sign
Measuring Equipment <u>DO-5</u> Procedure _____ Rev No. <u>0</u>				Drilling Contractor <u>Jensen Drilling Company</u>
Driller <u>Art Gwin</u>
Rig/Equipment <u>Speedster SS-15 III</u>										
Time	Casing/Screen			Annular Fill			Over-lap	Comments						
	Type	Diam. eter.	Length (feet)	Stickup	Depth	Type			Quan- tity	Stickup	Add-on	Depth		
0700														
0705														Drillers & Geologist on site
0715														Calibrate HWL 755 AM w/SPAN @ 5.7
														Monitor borehole HWL = Open 21.8° O ₂ & O ₂ LEL w/OVA
	Carbon Steel	6"	448.17											Added 20.15' of 6" C.S. Casing Yesterday
0750	"	6"	468.41											Added 20.24' of 6" C.S. Casing
0830	"	6"	489.13											Added 20.02' of " " "
0850	"	6"	508.10											Added 20.17' of " " "
0910	"	6"	529.64											Added 21.04' of " " "
0930	"	6"	550.74											Added 21.10' of " " "
0955	"	6"	571.92											Added 21.08' of " " "
1020	"	6"	592.72											Added 20.90' of " " "
1040	"	6"	613.68											Added 20.96' of " " "
1125														Nickie Chomness replacing Main Pearsm
1125	"	6"	633.76											Added 20.08'
1305	"	6"	654.28											" 20.52'
1320	"	6"	677.10											" 22.82'
1400	"	6"	699.02											" 21.92' Alan Pearson Replacing Chomness
1430														Centralizers holding casing broke -
														Casing & Tremie pipe fell to bottom of well.
1615														Arton Chatz (WAC) TV Surveys Well
1730														End of Shift

will feel for tremie & casing tomorrow

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-22B Sheet 1 of 2

Location SE of 200E Project Savage Is.

Logged by SS Teel Date 6/21/91

Print Sign

Reviewed by N/A Date _____

Print Sign

Measuring Equipment N/A Procedure DO-1, 5 Rev No. 110

Drilling Contractor Jensen Drilling

Driller Art Gwin / Joe Rauch

Rig/Equipment Speedstar SS-15 III Rotary

Time	Casing/Screen				Annular Fill			Over-lap	Comments
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity		
0800									Drillers on site w/casing spear fabricating a plate to measure top of 6" casing
0840									Geologist on site
0910									Calibrate instruments (HNU & LEL)
0915									and check borehole - it is OK
					142.95				Drillers are using the plate, connected to the sand line, with a nylon tape to meas.
	Top of 6" casing				841.9'				D/top of 6" casing = 142.95, ∴ bottom of casing is at 841.9' (based on length of casing before being dropped).
	Bottom of 6" casing								Preparing to run spear down hole.
									Adding spear & drill rod. MA Chamness on site
1100									Lunch - MAC leaves site.
1200/1230									Casing is successfully speared. - Pulling casing w/ casing line. The casing came up ~ 8' before tightening-up. Pull an additional 10' using the casing line in conjunction with raising and lowering the rig's hydraulic leveling jacks. Casing is tight.
1330									Jke Spivey / Vern Chamberlin on site
1415									

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-22B
Location SE of 200E

Project Savage Is. Sheet 2 of 2

SS Tool

SS Tool

Date 6/21/91

logged by _____
Print
Sign

Date _____

Reviewed by _____
Print Sign

Sensen Drilling
Drilling Contractor

Driller
Art Gwin / Joe Roach

Rig/Equipment Speedstar SS-15 III Rotary

[illegible]

98

Sheet 1 of 7

Drilling Contractor Tensen Drilling
 Driller Art Gwin / Joe Roach
 Rig/Equipment 2 roadster 85-15-m B-1

[illegible]

DAILY BOREHOLE/WELL
COMPLETION LOGBoring or Well Number 699-32-22B
Location SE of 200 ESheet 1 of 2
Project _____Logged by SS Teal SS Teal Date 6/26/91

Reviewed by _____ Sign _____ Date _____

Measuring Equipment N/A Procedure DD-1, S Rev No. 1.0Drilling Contractor Jensen DrillingDriller Art Swin / Joe RoachRig/Equipment Speedstar SS-15 III / Hydraulic Jacks
100-Ton Cap

Time	Casing/Screen				Annular Fill				Over-lap	Comments	
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup			Add-on
0700											Drillers on site - breaking-down rig and moving off of hole so hydraulic jacks can be set up.
0745											Rig is off of hole and is moved forward ~ 3 ft. Calibrate HUU + LEL/O2
											Span is set @ 4.20 to read 56 ppm
0750											Check borehole - it is OK
0805											Placing jacks over borehole + blocking and setting-up rig.
0822											Pulling casing w/ Jacks
1030											slip collar is bending - will have to stop until it is reinforced. Have pulled about 1.5' so far - it is pulling fairly easy. Drillers will go to town to get some used heavy steel plate to use for reinforcing.
											Geologist back on site.
1300											Drillers arrive
1315											Lunch
1315/1345											Check borehole - OK
1400											Welding reinforcement plate
1455											Pulling Casing

A-1801 004 (05/90)

Project Savage Is. Sheet 2 of 2

Drilling Contractor Tensen Drilling
 Driller Art Gwin / Joe Roach
 Rig/Equipment SpeedStar SS-15 III / 100' Ton Hydraulic Jacks

[illegible]

DAILY BOREHOLE/WELL COMPLETION LOG										Sheet 1 of 3	
Boring or Well Number 697-32-22B
Location SE of 200 E										Project Savage I 2	
Logged by SS Teel		Print		Date 6/27/91		Sign		Drilling Contractor Jensen Drilling		Driller Art Gwin / Joe Roach	
Reviewed by		Print		Date		Sign		Rig/Equipment Speedster SS-15 III / 100-Ton Hyd. Jacks			
Measuring Equipment N/A		Procedure DO-1, S		Rev No. 1, 0							

Time	Casing/Screen				Annular Fill				Over-lap	Comments	
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup			Add-on
0700											Drillers on site - changing over to 6"- casing collar + slips
0800											Calibrate instruments - Span is set @ 4.20 to read 56ppm.
0805											Check borehole - OK
0815											Pulling casing w/ Jacks
0845											Cutting off casing spear & removing drill rod.
0940											Pulling casing w/ rig - pull approx 10' - hear part of tremmie fall down well. 677' weld exposed
0950											Removing casing from spear
1050											Pulling casing w/ rig
1100											654' weld exposed
1106											638' weld exposed
1125											613' weld exposed
1135											592' weld exposed
1150											571' weld exposed
1300											550' weld exposed
1305											529' weld exposed
1312											508' weld exposed
1321											488' weld exposed

| DAILY BOREHOLE/WELL
COMPLETION LOG				Boring or Well Number <u>699-32-22B</u>				Sheet <u>2</u> of <u>3</u>	
				Location <u>SE of 200 E</u>				Project <u>Savage Is</u>	
Logged by <u>SS Teel</u>		Print		Date <u>6/27/91</u>		Drilling Contractor <u>Jensen Drilling</u>			
Reviewed by		Print		Date		Driller <u>Art Swin / Tee Roach</u>			
Measuring Equipment <u>N/A</u>		Procedure <u>DO-1,5</u>		Rev No. <u>1,0</u>		Rig/Equipment <u>Speedstar SS-15 TII Rotary</u>			

Time	Casing/Screen				Annular Fill				Over-lap	Comments	
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup			Add-on
1332											Check Borehole 1/4" HW-LEL. - OK
1336											Exposed 468' weld
1344											Exposed 448' weld
1352											Exposed 428' weld
1400											Exposed 407' weld. Pat Collier on site
1408											Exposed 388' weld
1415											Exposed 365' weld
1440											Exposed 345' weld Pat Collier leaves site
1445											Exposed 325' weld
1453											Expose 305' weld
1500											Expose 283' weld
											Moving Jacks; stacking casing
1600											Expose 263' weld
1608											Expose 242' weld
1616											Expose 221' weld
1621											Expose 201' weld
1628											Expose 181' weld
1634											Expose 161' weld
1700											Expose 140' weld
1705											Expose 121' weld
1710											Expose 100' weld

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 69-32-22B
Location SE of 200E

Project Savage Is Sheet 3 of 3

[illegible]

DAILY BOREHOLE/WELL COMPLETION LOG

Location SE of 200 East Area

Drilling Contractor Jensen Drilling

Date _____

Rev No. 1, D

Driller Art Gavin / Joe Roach

Rig/Equipment: Speedstar SS-15 III

Rig/Equipment Speedstar SS-15 III

	A-1800-004 (05/90)

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-22B

Location _____

Project Savage Is Sheet 1 of 1

Logged by SS Teel Date 7/1/91
Print Sign

Reviewed by _____
Print Sign Date _____

Measuring Equipment V/A Procedure DO-1,5 Rev No. 1,0

Drilling Contractor Tensen Drilling
Driller Art Swin / Joe Roach
Rig/Equipment Speedstar 55-15 III Rotary

[illegible]

Project Savage IS

Sheet 1 of 1

Sheet 1 of 1

Sheet 1 of 1

Drilling Contractor Jensen Drilling

Driller Art Gwin

Rig/Equipment Speedstar SS-15-III Rotary

A-1800-004 (05/90)

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-22B
Location SE of 200E

Project Savage Is Sheet _____

Sheet 1 of 1

Logged by SS Teel Print SS Teel Sign Date 7/3/91
 Reviewed by _____ Print _____ Sign Date _____
 Measuring Equipment N/A Procedure DD-1,5 Rev No. 110
 Drilling Contractor Jensen Drilling
 Driller Art Gwin / Joe Roach
 Rig/Equipment Speedstar - 55-15 III Rotary

Drilling Contractor Jensen Drilling
Driller Art Swin / Joe Roach
Rig/Equipment Speedator - 55-15 III Rotary

Time	Casing/Screen				Annular Fill				Over-lap	Comments	
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup			Add-on
0700											Driller on site
0730											Using magnet to fish for tremie
0830						←	Fishing tool				Calibrate instruments - span set @ 4.0 to read 56 ppm.
			1 - 20' - 1				baffles @ 4', 6', + 8'				check Borehole - OK
0845											
0900											
											Lampson Crane arrives to move pump and mud tanks off-site. Equip. was released by PNL HPTs yesterday.
0930											Trucks arrive - begin loading
											Art leaves site to get supplies
0950											Crane and trucks leave with pump and mud tanks
1200											
											Art arrives on site - preparing to attach fishing tool to drilling rod,
1230											Geologist leaves site. Driller will be welding for rest of day - will not be working in the bore hole until Monday
1530											

Project Savage IS. Sheet 1 of 1

SS Tool Date 7/8/91

Signature Date Rev No. 10

Drilling Contractor Tensen Drilling Co.
 Driller Art Gwin / Joe Leach
 Rig/Equipment Speedstar SS-15 III Rotary

A-1800-004 (05/90)

Project Savage Is Sheet 1 of 1

Drilling Contractor Jensen Drilling
 Driller Art Gwin / Joe Roach
 Rig/Equipment Speedstar SS-15 III

Comments
Drillers on site - pulling drilled
Calibrate instruments - span of HNU
set @ 4.30 to read 56 ppm - same
spans as previous.
Check borehole w/ HNU + LGL02 - OK
Scott McKinnon, Jensen Drilling, arrives on site
Drilled and Fishing - tool out of hole -
- all tremie is still down-hole,
Driller calls his boss to see what to do next
SS Teel informs Tech Forum
Check borehole w/ HNU + LGL02 - OK
Drillers attaching piece of 10" casing for
Casing hammer to rest on

Boring or Well Number 699-32-22B
Location SE of 200 E

699-32-22B
1503 002 of 35

Project Savage Is. She

Sheet 2 of 2

2

Logged by A.W. Pearson Print

Alex Pearson Sign

Date 7/10/91

Reviewed by

Print

Sign

Date

7/10/91

Measuring Equipment

DA

Procedure

DD-1,5

Rev No.

10

Drilling Contractor

Driller Art Gwin

Rig/Equipment Speedstar SS-15III Rotary

[illegible]

DAILY BOREHOLEWELL COMPLETION LOG				Boring or Well Number <u>69-32-22B</u>				Sheet <u>1</u> of <u>1</u>			
Location <u>SE of 200 East</u>				Project <u>Savage Is.</u>							
Logged by <u>A.W. Pearson</u> Print				Sign <u>Alan Pearson</u> Date <u>7/11/91</u>				Drilling Contractor <u>Jensen Drilling Co.</u>			
Reviewed by <u>NA</u> Print				Sign <u>DD-1.5</u> Date <u>7/11/91</u>				Driller <u>Art Guvin/Joe Roach (H)</u>			
Measuring Equipment <u>NA</u>				Procedure <u>DD-1.5</u> Rev No. <u>1.0</u>				Rig/Equipment <u>Speedstar SS-15 III</u>			

Time	Casing/Screen			Annular Fill				Over-lap	Comments			
	Type	Diameter	Length Total	Stickup	Depth	Type	Quantity			Stickup	Add-on	Depth
0700												Calibrate HNU to 55 ppm w/spm 3.4
0710												4 Drillers arrive
0730												Check borehole w/ HNU & LGL = 7 OK
0800												Resume welling joint from yesterday
0850	Carbon Steel	6"	364.27'									Welding ears on (7) pieces of casing
0910	"	6"	384.34'									Add 20.04' of 6" C.S. Casing
0930	"	6"	404.35'									Add 20.01' " " " " " "
0945	"	6"	424.39'									Add 20.04' " " " " " "
1120												Weld ears on casing
1150	"	6"	444.43'									Add 20.04' of 6" C.S. Casing
1150	"	6"	464.49'									Add 20.05' " " " " " "
1300	"	6"	484.52'									Add 20.04' " " " " " "
1325	"	6"	504.59'									Add 20.06' " " " " " "
1430	"	6"	527.49'									Add 22.90' " " " " " "
1550	"	6"	546.6'									Add 19.13' " " " " " "
1650	"	6"	566.78'									Add 20.17' " " " " " "
1715	"	6"	586.95'									Add 20.17' " " " " " "
1730												End of Shift.

DAILY BOREHOLE/WELL COMPLETION LOG				Boring or Well Number <u>699-32-228</u>				Sheet <u>1</u> of <u>2</u>	
				Location <u>SE of 200E</u>				Project <u>Savage Is.</u>	
Logged by <u>SS Teel</u>		Print		Date <u>7/12/91</u>		Drilling Contractor <u>Tensen Drilling</u>			
Reviewed by		Print		Date		Driller <u>Art Gwin / Joe Roach</u>			
Measuring Equipment <u>N/A</u>		Print		Date		Rig/Equipment <u>Speedstar SS-15 II / Rotary</u>			
		Sign		Date					
		Sign		Date					
		Procedure <u>DO-1,5</u>		Rev No. <u>1,0</u>					

Time	Casing/Screen			Annular Fill			Over-lap	Comments			
	Type	Diam-eter	Length-Total	Stickup	Depth	Type			Quan-tity	Stickup	Add-on
0700	Carbon Steel	6"	586.95								Drillers on site
0751	"	"	607.63								Add 20.58' of 6" C.S. Casing
											Calibrate instruments - HNU span set
											@ 3.71 to read 56ppm.
0840											Check borehole w/ HNU & CEL/02 - OK
											Ed Enloe on site
											PNL HPTs on site to survey trash
0855											Ed Enloe / HPTs off site
0900	Carbon Steel	6"	628.09								Add 20.46' of 6" C.S. casing
0940	"	"	650.86								Add 22.77' of 6" C.S. casing
1031	"	"	670.80								Add 19.94' of 6" C.S. casing
1130	"	"	691.58								Add 20.78' of 6" C.S. casing
											Scott McKinnon on site
1150	"	"	712.48								Add 20.90' of 6" C.S. casing
1245	"	"	732.48								Add 20' of 6" C.S. casing
1345	"	"	753.46								Add 20.98' of 6" C.S. casing
											Pat Collier / Vern Chamberlin visit site
1410	"	"	774.48								Add 21.02' of 6" C.S. Casing
1435	"	"	794.56								Add 20.08' of 6" C.S. Casing

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-22B
Location SE of 200E

Sheet 2 of 2
Project Savage IS,

Logged by SS Teel Print _____ Sign _____ Date 7/12/91

Reviewed by _____ Print _____ Sign _____ Date _____

Measuring Equipment N/A Procedure DD-1, 5 Rev No. 1, 0

Drilling Contractor Tensen Drilling
 Driller Art Gwin / Joe Roach / Scott McKinnon
 Rig/Equipment Speedstar SS-15 TIL Rotary

[illegible]

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-22B
Location SE of 200E

Project Savage Is. Sheet _____

Sheet 1 of 1

Logged by SS Teel Print SS Teel Sign Date 7/15/91
 Reviewed by _____ Print _____ Sign _____ Date _____
 Measuring Equipment N/A Procedure DO-1, S Rev No. 1, 0

Drilling Contractor Jensen Drilling
 Driller Art Swin / Joe Roach
 Rig/Equipment Speedstar SS-15 III, Rotary

[illegible]

DAILY BOREHOLE/WELL
COMPLETION LOGBoring or Well Number 699-32-22B
Location SE of 200ESheet 1 of 2
Project Savage IsLogged by SS Teel Print SS Teel Date 7/16/91
Reviewed by N/A Print N/A Date
Measuring Equipment N/A Procedure D0-1,5 Rev No. 1,0Drilling Contractor Jensen Drilling
Driller Art Guin / Joe Roach
Rig/Equipment Speedstar SS-15 III / Rotary

Time	Casing/Screen				Annular Fill			Over-lap	Comments
	Type	Diam-eter	Length
of a	Stickup	Depth	Type	Quan-tity		
	Carbon Steel	6"	774.48						
1045			+ 20.04						Drillers on site
			794.52						Fixing air hose
1145									Adding casing & drillrod. Added
	"	"	794.52						20.04 of 6" C.S. casing. Total drill
1255									rod now ~ 798'
									Calibrate instruments - span set @ 13.50
1300									to read 56 ppm.
1400									Check borehole w/ HUV + LEL/02 - OK
									Determining how to hold casing during
1515									drilling
1530									Welding ears on casing
1550									Pat Collier / Vern Chamberlin on site
1608									Blowing - out hole w/air
1620									Drilling w/air rotary
									Casing is advanced to ~ 798' - no sign
									of metal so far. Preparing to weld
									casing.
	"	"	794.52						Adding 21.06' of 6" C.S. casing
	"	"	21.06						Drilling w/air rotary
1813	"	"	815.58						Drive casing 800-806' - tight spot at
	"	"							~ 803' that sealed off the water - driller
	"	"	815.58						thinks it's clay.

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-22B
Location SE of 200E

Project Savage Is
s

Sheet 2 of 2

Logged by SS Teel Print SS Teel Sign _____ Date 7/16/91

Reviewed by _____ Print _____ Sign _____ Date _____

Measuring Equipment N/A Procedure DO-1, S Rev No. 1,0

Drilling Contractor Jensen Drilling
 Driller Art Gwin / Joe Roach
 Rig/Equipment Speedstar SS-15 III / Rotary

[illegible]

DAILY BOREHOLE/WELL COMPLETION LOG									
Boring or Well Number <u>699-32-22B</u>
Location <u>SE of 200E</u>					Sheet <u>1</u> of <u>2</u>
Project <u>Savage IS</u>				
Logged by <u>SS Teel</u>
Reviewed by <u>Print</u>		Date <u>7/17/91</u>
Sign <u>SS Teel</u>		Drilling Contractor <u>Jensen Drilling</u>
Driller <u>Art Gwin / Joe Roach</u>		Rpt/Equipment <u>Speedator 25-12 111</u>			
Measuring Equipment <u>N/A</u>
Procedure <u>DO-1, S</u>		Date <u>7/17/91</u>
Sign <u>SS Teel</u>		Date <u>7/17/91</u>
Sign <u>SS Teel</u>		Rev No. <u>1, 0</u>			

Time	Casing/Screen			Annular Fill			Over-lap	Comments					
	Type	Diam-eter	Length Total	Stickup	Depth	Type			Quan-tity	Stickup	Add-on	Depth	
0700	Carbon Steel	6"	815.58										Drillers on site. Preparing to add casing.
0745			+20.91
836.49										Calibrate instruments - HNU span set at 3.78 to read 56 ppm.
0750													Check borehole - OK
0830													Blowing-out borehole w/air
0835													Cleaning-out hole etc
0845	"	"	836.49										Adding casing and drill rod. Adding 20.91' at 6"-dia. C.S. Casing
0945			-13.30
823.19										Drilling w/air rotary
													Casing seems to be stopped @ ~ 821'
													Bit can drill ~ 5' ahead of casing
													Driving casing - casing is not moving
													Cycling air flow / Raising & lowering bit
1044													Will cut off stick-up and then drill out hole to TD. Don't think drill bit has contacted any metal yet, but don't know why casing is not following.
													Cut off 13.3' of casing
1130			823.19										Blowing-out borehole w/air
1143													Drilling w/air rotary
1145													Appears to be hitting tremie @ 8'36"
1150													Lunch

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-22B
Location SE of 200 E

Project Savage Is Sheet 2 of 2

logged by GC Teel Print

800-55 _____ Date 7/17/91

Reviewed by _____
Print _____

Sign

Date

Measuring Equipment NA

Rig/Equipment Speedstar 55-15 III

Drilling Contractor Jensen Drilling

Driller Art Gwin / Joe Roach

[illegible]

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-22B
Location SE of 200E

Project Savage IS Sheet 1 of 2

Logged by SS Teel Print SS Teel Sign SS Teel Date 7/18/91
Reviewed by _____ Print _____ Sign _____ Date _____
Measuring Equipment N/A Procedure DO-1, 5 Rev No. 1, 0

Drilling Contractor Tenser Drilling
Driller Art Gwin
Rig/Equipment Specular SS-15 II

Time	Casing/Screen				Annular Fill				Over-lap	Comments
	Type	Diam-eter	Length Total	Stickup	Depth	Type	Quan-tity	Stickup	Add-on	Depth
0700	Carbon Steel	6"	823.19	2.7	820.49					
0830										Drillers on site
0930										Preparing to run dev. survey
0950										Deviation survey - 0.5° @ 815'
										Spooling line
										Tripping-out drill rods
										Calibrate instruments - HNU set
										@ 3.80 to read 56 ppm - same span
1000										gas as prev.
1135										Check borehole - OK
1145									~836.5	All drill rod out of hole
						20-40 Sand	2 bags			Adding 20-40 mesh Colo Silica Sand (100-16 bags)
1330									832.2	D/Sand meas. w/ logging truck
1407									829.4	" " "
1422									829.0	" " "
1430										Welding tabs on screens
1445	10-slot	.42 ID	20.29			(w/ bottom plate)				Setting screen. Screens are continuous
	Stainless-steel	.460 D								wire wrap, threaded joints with
	Screen		20.04							O-rings. OD of packer is 0.52 ft.
			10.04							
			11.0			(w/neoprene packer)				Packer is 0.25' wide, screen starts
										0.6' from top of packer.

Rev No. 170

A-1800-004 (05-90)

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-22B
Location SE of 200E

Sheet 1 of 2
Project Savage Is

Logged by SS Teel Date 7/19/91
Reviewed by Print Sign
Measuring Equipment N/A Procedure D0-1,5 Rev No. 1,0

Drilling Contractor Jensen Drilling
Driller Art Gwin / Joe Roach
Rig/Equipment SpeedStar SS-15 III

Time	Casing/Screen				Annular Fill				Over-lap	Comments
	Type	Diam-eter	Length	Stuckup	Depth	Type	Quan-tity	Stuckup	Add-on	Depth
0700	Carbon Steel Casing	6"	823.19	2.7	820.49					
0730										
0800	10-slot screen	5"	61.37		829.9					
0805										
0840										
0845										
0905										
0910										
1130	Casing	6"			816.09					
1230										
1316	Carbon steel	6"	815.58	2.2	813.38					
1330		6"	815.58	3.3	812.28					

Drillers on site
Measuring O/screen w/ logging truck
Top of screen is at 768.53
Installing tremie pipe to hold down screen while backpulling casing,
Calibrate instruments. HUU span is set @ 3.80 to read 56 ppm.
Check borehole - OK
Tremie is installed. 200' of 2" tremie attached to the sandline is resting at the bottom of the hole.
Pulled casing 1.3', screen has dropped to ~ 833.1
Pull to 817.09; screen @ 832.1
Pull to 816.09; screen @ 831.1
Lunch - let screen stabilize - hopefully the hole will backfill below the screen
Lowering tremie to hold screen
Pull casing
Pull casing

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-22B

Sheet

Project Savage Is.

Logged by SS Teel Print

SS Teel
u815

Date 7/19/91

Reviewed by _____ Print _____

Sign

Date _____

Measuring Equipment N/A

Procedure DO-1,5

Rev No. 1,0

Jensen Drilling
Drilling Contractor

Driller Art Gwin / Joe Roach

Speedster SS-15 III

[illegible]

Sheet / of

COMPLETION LOG

Location SE of 200E

Project Savage Is.

Boring or Well Number 699-32.22B

AW Pearson
SS Teel

Alan Pearson
SS Steel

Date 7/22/91

Drilling Contractor Jensen Drilling

Print

Sign

Measuring Equipment

Procedure DO-15

Rev. No. 1.0

Rig/Equipment Speedstar SS-15 TIL

Time	Casing Screen				Annular Fill				Over-lap	Comments	
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup			Add-on
0730	C.S. Casing	6"	815.58'	3.3	812.28'						SS Teel + Joe Roach on site
0800	S.S. Screen	5"	61.37'		827.4'						Art Guin on site
	Top of Screen @				766.03'						Removing tremie pipe
0945											Tremie removed. Building a nozzle to
											jet the screen to loosen the sand-hitch.
1100											Calibrate instruments. Span set @
											3.58 to read SG ppm.
1115											Check borehole - OK
1145											AW Pearson arrives on site to relieve
											SS Teel
1300											Attach (5238) of 2" tremie pipe to
											bottom of drill rod, will be used
											to jet screen clear if required
1315											Begin running drill rod (25' lengths
											+ D.H. adapter (14 1/4" = 300.41'
1450											Begin running drill rod (20' lengths)
											(14 1/4" 14 1/4" 14 1/4" + 14' adapter = 481.40
											Total Drill rod 781.81'
											Top of Screen @ 766.03'
											Should contact Top of Screen when
											S.W. of drill rod = 15.78'
1650										767.50'	Did not feel like rod contacted screen

DAILY BORFHOLE/WELL COMPLETION LOG

Boring or Well Number

609-32-22B

Location

SE of 200 East Area

Boring or Well Number

Savac Is.

Sheet 2 of 2

Designed by A. W. Pearson
Print

Print

Alan Fleeson Sign

Sign

Date 7/22/91

Reviewed by

Print

Date _____

Measuring Equipment

Procedure

Rev No.

Drilling Contractor

Tensen Drilling Co.

Driller

win

Rig/Equipment

Speedstar SS-15 III

[illegible]

DAILY BOREHOLEWELL COMPLETION LOG				Boring or Well Number <u>69A-32-22B</u>				Sheet <u>1</u> of <u>1</u>			
				Location <u>SE of 200 East Area</u>				Project <u>Savage Is.</u>			
Logged by <u>A.W. Pearson</u>				Date <u>7/23/91</u>				Drilling Contractor <u>Jensen Drilling Co.</u>			
Reviewed by <u>Print</u>				Sign <u>Alan Pearson</u>				Driller <u>Ant Gwin</u>			
Measuring Equipment <u>NA</u>				Procedure <u>DO-1,5</u>				Rig/Equipment <u>Speedstar SS-15 III</u>			

Time	Casing/Screen				Annular Fill				Over-lap	Comments	
	Type	Diameter	Length	Stickup	Depth	Type	Quantity	Stickup			Add-on
0700											
0715											
0830	Carbon Steel	6"	794.58'	2.8'	791.78'						Calibrate HNU 55 ppm w/Spn @ 3.6
0900	Top of Screen	5"	61.37'	NA	772.6'						Resume Backpulling 6" C.S. Casing
	Bottom of Screen	5"	61.37'	NA	833.97'						Cut 210' of 6" C.S. Casing
1015	Carbon Steel	6"	779.88'	2.2'	777.68'						Tag top of Screen w/ Drill Rod
1045											∴ Set 9/8 6" Casing @ 777.6'
1100											Cut 14.7' of 6" C.S. Casing
											Begin pulling drill rod.
1130											Try to run TV Camera to
											inspect screen → water is turbulent
	Top of Screen	5"			772.0'						Run Geophysical Logging tool down
	Bottom of Screen	5"			833.1'						hole. Tagged Top of screen
											Bottom of Screen = Measurements
1510											may be slightly off.
											Talked w/ Mickie Charness = 7
											decided to run 3/4" premie on
											outside of the 6" C.S. Casing
											then examine screen w/ camera
											tomorrow am
1545											Begin running 3/4" premie pipe
1730											End of Shift

DAILY BOREHOLE/WEELL COMPLETION LOG

Boring or Well Number 699-32-22 Sheet 1 of 1

Location SE of 200 East Area Project Savage Is

Logged by A.W. Pearson Date 7/24/91

Drilling Contractor Jensen Drilling Co.

Reviewed by Print Sign Alan Pearson Driller Art Gwin

Measuring Equipment NA Procedure DD-1, 5 Rig Equipment Speedstar SS-15 III

Time	Casing/Screen				Annular Fill			Over-lap	Comments
	Type	Diam-eter	Length	Stuckup	Depth	Type	Quan-tity		
0710									Calibrate HAU 55ppm w/ Span 0.31
0720									Check borehole OK
0730									Prepare to run TV camera
0800									Water is still too turbid to view w/ TV camera
0815	Tremie Pipe	3/4"	672'	2.0	670'				(32) pieces of 21' long 3/4" in
	Top of screen	5"	61.37	NA	772.6				tremie pipe have been placed
	Bottom of screen	5"	61.37	NA	833.97				in annulus = 652' total
	Carbon Steel	6"	779.88	2.2	777.68	(5.1' overlap)			Preparing to set submersible pump
0900									SS Teel on site, AW Pearson leaves
0930									Setting submersible pump - same
1000									pump that was previously used.
									(5HP Grunfos, 25 stage)
									Pump is set @ 504'
1200									Attempt to meas. down tremie -
									rod is too thick - change to 5/8"
									rod
									Can only get down to 700' - stuck
1400									on a centralizer - will move
									easing to free it
									Probe and line are out of hole.
1730									Leave site

DAILY BOREHOLE/WELL COMPLETION LOG				Boring or Well Number <u>699-32-22B</u>				Sheet <u>1</u> of <u>2</u>				
				Location <u>SE of 200E</u>				Project <u>Savage Is</u>				
Logged by <u>Alvin Pearson</u>
<u>SS Teel</u>				Date <u>7/25/91</u>
<u>SS Teel</u>				Drilling Contractor <u>Jensen Drilling</u>				
Reviewed by <u>Print</u>				Sign <u>Print</u>				Driller <u>Art Gwin / Joe Raach</u>				
Measuring Equipment <u>N/A</u>				Procedure <u>DO-1,5</u>				Rig Equipment <u>Speedstar SS-15 III</u>				
Time	Casing/Screen				Annular Fill				Over-lap	Comments		
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup			Add-on	Depth
0800	Tremie Pipe	3/4"	672'	2.0	670.0							Driller picking-up cable at Columbia Rigging Co.
0900	Top of screen	5"	61.37	NA	772.6							Driller on site - changing sand line to use 3/4" dia cable. We will use this line instead of the logging truck to measure in with. The cable on the logging truck has a tendency to kink too easily.
	Bottom of screen	5"	61.37	NA	893.97							Calibrate instruments. Span is set?
	Carbon steel	6"	779.88	2.2	777.68		(5.1' overlap)					2.18 to read 56 gpm. Spangas lot # 28627
	5HP Pump	NA	NA	NA	504'							Check borehole w/ HNU + LEL/O2 - OK
1000												Measuring - in sand line
1005												D/BOTTOM = 806.5
1030												Sand line out of hole - preparing to add sand.
1115	Bottom of hole (measurable)									806.5		Pump on (Flowmeter 82420)
1135												20 gpm
1326												D/Water 150'
1334												Adding sand (pumping 15 gpm)
1335												(Colo. Silica sand, 100 lb bags)
1430												Alvin Pearson takes over for SS Teel
1500												Increase pump rate to 20 gpm
1610												Finished adding sand

DAILY BOREHOLEWELL COMPLETION LOG

Boring or Well Number 699 - 32 - 22B

Sheet 2 of 2

Location	SE of 200 East Area

Project Savage Is.

Logged by AW Pearson
Print

Alum Pearson Date 7/25/91
Sign

Reviewed by

Print

Sign

Date _____

Measuring Equipment N/A

Procedure DO-1,5

Rev No. 116

Drilling Contractor Jensen Drilling

Driller Art Swin / Joe Roach's

Rig/Equipment Speeds for SS-15 III

[illegible]

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-22 Sheet 1 of 2

Location SE of 200 East Area Project Savage Jr

Logged by A.W. Pearson Print AW Pearson Date 7/26/91

Reviewed by NA Print NA Date 7/26/91

Measuring Equipment NA Procedure DO-1.5 Rev No. 1.0

Drilling Contractor Jensen Drilling Co.

Driller Ant Gwin / Joe Roach

Rig/Equipment Speedstar SS-15 III

Time	Casing/Screen				Annular Fill			Over-lap	Comments
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity		
0700									Calibrate HNU @ 55 gpm w/ Span @ 2.95
0710									Check borehole = 7 Oppm w/ HNU L & R
0715									218% O ₂ & O ₂ IEL w/ MSA
0800									Take 9W = 113.0' b/s
0801					744.0				Take 9B = 744.0' b/s = Bridge 1
0802									Take 9B = 776.0' b/s = 7 Sand @
0805									Top of Interbed - Sand was not bridged but had difficulty getting weight past the centralizers
0810									More 6" C.S. casing up & down to take any sand that may be caught in annular
0815									Start pump / flow meter not attached
0820									~30 gpm
0825					790.0		2.6'	O.D' 790.0	Take O/R = 790.0'
0830									Attach flow meter 869BD gal (25 gpm)
0835									Add (3) 100 lb. bags sand
0840									Finished adding sand - let settle
0845									Increase pump rate to 35 gpm
0850									More casing up & down to help sand settle
0855									Take O/R 763.5
0900									More casing up & drain

DAILY BOREHOLEWELL COMPLETION LOG

Boring or Well Number

Location

699-32-22

200 East Ave

Sheet

Is

21

Abstract

Logged by A.W. Pearson
Print

Alan Carson Sign

Date 7/26/11

Reviewed by

Print

U.S.

Date

Measuring Equipment

WA

Procedure

✓

Rev No. 14

Drilling Contractor Tensen Drilling Co.

Driller Ant Gwin / Ice Reach

Speedstar SS-15 III

Time	Casing Screen					Annular Fill					Over-lap	Comments
	Type	Diam-eter	length	Stickup	Depth	Type	Quan-tity	Stickup	Add-on	Depth		
1242												Try to take D/B, cannot get weight to bottom.
1305												Move casing up & down
1445	S.S. Screen	5"	61.3'		836.0'						764.4'	Take D/B = 759.5 bls
1525												Take D/B inside screen = 836.0'
												Take 6' w = 250.6 (have been pumping continuously for 6.5 hrs @ ~35 gpm)
												Water appears to have cleared up considerably since this AM.
1550											764.4'	Take D/B = 764.4' bls sand settled
1609	Carbon Steel	6"	779.88'	1.2'	778.68'							Drop 6" Casing 1.0' to give extra overlap w/ screen.
1635												Turn off pump.
1700												End of shift.

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-22B

Location SE of 200E

Sheep

1012

Project Savage Is

Tagged by SS Tee Print SS Tee Date 7/29/91 \$ion

Reviewed by _____ **Date** _____
 Print **Sign**

Measuring Equipment N/A Procedure DQ-1.5 Rev No. 1.0

Jensen Drilling
Drilling Contractor

Driller Art Gwin

Rig Equipment Speedstar SS-15 III

[illegible]

DAILY BOREHOLEWELL COMPLETION LOG

Boring or Well Number 699-32-22B

Location

Sheet

Project Savage Is

Logged by SS Teel Print

SS-Tool
Sign

Date 7/29/91

Reviewed by _____ Printed _____

Sign

Date _____

Measuring Equipment N/A

Procedure D0-1,5

Rev No. 110

Drilling Contractor Jensen Drilling

Driller Art Swin

Rig/Equipment Speedstar SS-15 III

[illegible]

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-228
 Location SE of 2006

Sheet 1 of 2
 Project Savage Is

Logged by SS Teel Date 7/31/91
 Reviewed by Print Sign SS Teel
 Measuring Equipment Drilling sand line Procedure DO-1, S Rev No. 1, 0

Drilling Contractor Jensen Drilling
 Driller Art Gwin / Rod Nordquist
 Rig/Equipment SS-15 III, rotary

Casing/Screen					Annular Fill				Over-lap	Comments	
Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup	Add-on	Depth		
0700											Drillers on site
0730					40-100 sand	-	-	-	760.8		D/sand = 760.8 - preparing to mix bentonite slurry.
0805											Calibrate HNU + LGL/O ₂ . Span for HNU set @ 3.04 to read 56ppm
0810											Check Borehole - OK
0845					crumbles 8-20	1-5015 Bag	-	-	-		Pump 1 batch slurry, wt = 9.0 lb/gal
0915					water	35 gal			-		Pump Bentonite slurry, wt = 8.8 lb/gal (using well water to mix slurry)
1000					Hydrogel	80 lbs					Pump slurry, wt = 8.8 lb/gal
1045					water	70 gal					Pump slurry, wt = 8.8 lb/gal
					Hydrogel	70 lbs					Note: well was pumped yesterday from 7:30 to 2:30 and 4:30 to 5:30 to settle the sand pack
					water	70 gal					Pump slurry, wt = 8.8 lb/gal
1130					Hydrogel	70 lb					Pump slurry, wt = 2.9 lb/gal
					water	70 gal					
1200					Hydrogel	70 lb					
					water	70 gal					Remove 2 joints of tremie
1230											

Remove 2 joints of tremie

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number **699-32-22B**

Sheet 2 of 2

Location	SE of 2006

Project Savage Is

Triggered by SS Teel

0015
J00255

Date 7/31/91

Print

Reviewed by

Print

Measuring Equipment

Procedure DO-1,5

Rev No. 1,0

Rev No. 1,0

Drilling Contractor Jensen Drilling

Driller Art Gwin / Rod Nordquist

Rig/Equipment SS-15 III, Rotary

[illegible]

DAILY BOREHOLE/WELL COMPLETION LOG				Boring or Well Number <u>699-32-22B</u>		Sheet <u>1</u> of <u>3</u>	
				Location <u>SE of 200 E</u>		Project <u>Savage Is.</u>	
Logged by <u>A.W. Pearson</u>
Print				Sign <u>Alan Pearson</u> Date <u>8/1/91</u>			
Reviewed by <u>NA</u>
Print				Sign _____ Date _____			
Measuring Equipment <u>NA</u>				Procedure <u>DO-1.5</u> Rev No. <u>1.0</u>			
Drilling Contractor <u>Jensen Drilling Co.</u>				Driller <u>Art Gwin/Rod Nordquist</u>			
Rpt/Equipment <u>Speedstar SS-15III, rotary</u>							

Time	Casing/Screen			Annular Fill			Over-lap	Comments	
	Type	Diam-eter	Length	Stickup	Depth	Quan-tity			Type
0700									Calibrate HWU = 55 ppm w Span @ 290
0705									Check borehole - OK
0715									Take $\rho_w = 114.5'$ bls
0720									Take ρ_w in annulus = 116.5' bls
0730									Begin mix slurry / use H ₂ O from water tank
0805						70 lbs			Pump Slurry; wt = 8.9 ρ_w before = 116.5'
						70 gal			ρ_w after = 92.5'
0830						70 lbs			Pump Slurry; wt = 8.8 ρ_w before = 104.6'
						70 gal			ρ_w after = 77.1'
0850						70 lbs			Pump Slurry; wt = 8.9 ρ_w before = 90.9'
						70 gal			ρ_w after = 62.0'
0905						70 lbs			Pump Slurry; wt = 8.8 ρ_w before = 70.0'
						70 gal			ρ_w after = 47.4'
0925						35 lbs			Pump Slurry; wt = 9.0 ρ_w before = 58.7'
						35 gal			ρ_w after = 50.7 only pumped 1/2 batch (Slurry too thick)
0940						60 lbs			Pump slurry; wt = 8.8 ρ_w before = 55.7'
						60 gal			ρ_w after = 34.4'
1000						70 lbs			Pump slurry; wt = 8.9 ρ_w before = 45.7'
						70 gal			ρ_w after = 21.0'

138

DAILY BOREHOLE/WELL COMPLETION LOG				Boring or Well Number <u>699-32-22B</u>				Sheet <u>2</u> of <u>3</u>	
				Location <u>SE of 200E</u>				Project <u>Savage Is.</u>	
Logged by <u>A.W. Pearson</u>		Print		Date <u>8/1/91</u>		Drilling Contractor <u>Jensen Drilling Co</u>			
Reviewed by <u>AJA</u>		Print		Date		Driller <u>Ant Guin / Red Nordquist</u>			
Measuring Equipment		Procedure <u>DO-1, 5</u>		Rev No. <u>1, 2</u>		Rig/Equipment <u>Speedstar SS-15 III, Rotary</u>			

Time	Casing/Screen			Annular Fill				Over-lap	Comments		
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity			Stickup	Add-on
1020						Hydrogel	70 lbs				Pump Slurry; wt = 8.8 %w before = 29.5' %w after = 5.0'
1040						Water	70 gal				Pump Slurry; wt = 8.8 %w before = 29.0' %w after = water to surface & after 1/2 batch pumped
1110						Hydrogel	70 lbs				Pump Slurry; wt = 8.8 %w before = 10.5' %w after = surface
1135						Water	70 gal				Pump Slurry; wt = 8.8 %w before = 10.9' %w after = surface
1155						Hydrogel	70 lbs				Pump Slurry; wt = 8.9 %w before = 5.0' %w after = surface
1320	4remie	3/4"	210"			Water	70 gal				Remove (9) pieces of 3/4" tremie
1335						Hydrogel	70 lbs				Pump Slurry; wt = 8.8 %w before = 18.0' %w after = surface
1355						Water	70 gal				Pump Slurry; wt = 8.9 %w before = 3.3' %w after = surface
1410						Hydrogel	70 lbs				Pump Slurry; wt = 8.8 %w before = 2.5' %w after = surface
1425						Water	70 gal				Pump Slurry; wt = 8.8 %w before = 2.0' %w after = surface
1445						Hydrogel	70 lbs				Pump Slurry; wt = 8.8 %w before = 3.0' %w after = surface

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-32-B

Sheet

Sheet 3 of 3

Logged by A.W. Pearson Print

Alan Pearson
Sign

Date 8/1/91

Reviewed by _____ Print _____

Print	Sign

Date _____

Measuring Equipment

Procedure DQ-15

Rev No. 1 ~~1~~

Drilling Contractor Tensen Drilling Co.

Art Gwin / Rob Nordquist

Rig/Equipment Speedstar SS-15III Pottery

[illegible]

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number	Location

3002 30 35
699-32-22B

Project Saving Is Sheet

Sheet

10

2

Logged by A.W. Pearson
Print

Alex Pearson
Sign

Date 8/2/91

Reviewed by _____
Measuring Equipment _____
Print _____

Procedure

Sign

Date _____

Rev No. | 0

Measuring Equipment

Procedure

Rev No. 10

Drilling Contractor

Jensen Drilling Co

Driller Art (

Driller Art Gwira / Red Norlgaist

Rio/Equipment

Requiem SS-157-SS 10/27/00

[illegible]

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 69-32-22B
Location SE of 200E

Project Savage Is. Sheet _____

Logged by A.W. Pearson Mam Pearson Date 8/5/61
Print Sign

Reviewed by _____ **Date** _____
Print _____ **Sign** _____

Measuring Equipment NA Procedure DD-1.5 Rev No. 1.0

Drilling Contractor Jensen Drilling Co.

Driller Art Guzin

Rig/Equipment Speidelstar SS-15 III / Rotary

Time	Casing/Screen				Annular Fill				Over-lap	Comments	
	Type	Diam-eter	Length	Stickup	Depth	Type	Quan-tity	Stickup			Add-on
0900											Take Dr = 53.0' Will add 8-20 mesh Bentonite Crumbles to fill annulus to ~ 20' b/s
0910						8-20 mesh (11) bags				21.0'	Add Crumbles (53.0'-21.0')
0930						Type I & II Portland Cement					Mixing Cement grout
						Water	(5) 94 lbs. Bags				
						Hydrage	(3) 94 gals.				
							(10) lbs.				
0935											Take Dr = 112.0' b/s.
1000											Fill Grout
1025											Take Dr of Grout 0.7' It may settle. more (will check Dr again) get to casing surface fast
1045											Geologist off site - Driller will break down rig & clean site the rest of the day
							</				

1113

| DRILL LOG | | BY
D.R. Newcomer | Rig | Well Number
699-32-22B | Computer Number | Project or Work Order No. | |
|--------------|--------------|---------------------|--|---------------------------|-----------------|---------------------------|--|
| Total Casing | Depth | Date
17 Oct 91 | | Depth
To | | Subcontract No. | |
| | Drill Method | Wet/Dry Sample | LITHOLOGIC DESCRIPTION
% Each Grain Size, Color, Roundness, Caliche, Etc. | | | Time | |
| | | | | | | Drilling Comments | |
| | | | Arrived at Well Site 699-32-22B | | | 1300 | |
| | | | Begin pulling pump out of hole | | | 1305 | 2 Kaiser drillers removed pump shoe is Kelly Olsen ish brown |
| | | | Sample of water in discharge line (7th 21' length)
DEN | | | 1330 | Water is green as color |
| | | | Driller said pump is coming out fine | | | | Water came out of 4th riser pipe (Check valve on pump) |
| | | | A little bit of Green mud on outside of 8th length of riser pipe | | | 1338 | |
| | | | 10 lengths of 21-ft pipe have been removed thus far | | | 1350 | |
| | | | Greenish mud is visible at some ^{some of the} pipe joints | | | | |
| | | | 21 lengths of 21-ft pipe + pump pulled | | | 1445 | All pipe is black |
| | | | Pump looks clean, greenish-black mud ^{sample taken from} 2nd to last | | | | pipe length |
| | | | Leave site (cap put on well) | | | 1450 | |
| | | | Pump was set at 21x21x5 = 446' below top of casing | | | | |
| | | | Dark Greenish-colored mud was on some of the pipe joints below the water level in the well. | | | | |
| | | | Appears to have been a stringer of mud down the last 20-30' of pipe length, (i.e. mud on one side of pipe down ^{down} most of its length). Mud was seen ^{seen} on other pipe lengths above, however, was very minor amounts (not enough to obtain a sample). Most of the sample was mud | | | | |
| | | | taken from 2nd to last pipe. Used jar lid to scrape it off pipe. It appears that most of the pipe was clean. Pump was very clean with no visible sediment or green mud. | | | | |
| REMARKS: | | | | | | | |

DAILY BOREHOLE/WELL COMPLETION LOG

Boring or Well Number 699-32-22B

Location _____

Project Savage Island Sheet 1

Logged by Alan W. Pearson Alan Pearson Date 10/21/91

Reviewed by _____ Sign _____ Date _____

Measuring Equipment NA Procedure GL-15 Rev No 0

Drilling Contractor Jensen Drilling
 Driller Art Gwin
 Rig/Equipment _____

[illegible]

Appendix B

Design Field Changes and Nonconformance Reports

DESIGN FIELD CHANGE		DFC No.
<u>Savage Island-2</u>	
TASK NO.
5	PROJECT TITLE
Ground-Water Surveillance\ 11246
Savage Island Well Installation Activity		FINAL APPROVAL DATE
DOCUMENTS AFFECTED - Geologist's logs.			
DESCRIPTION OF CHANGE - The DO-1 procedure will not be followed in all ways for the two mud/air rotary wells being drilled for the Savage Island Project.
1. The depth to bottom and the depth to water cannot be measured every day because the drilling heads and/or mud block access to the borehole. Depth to bottom is estimated using the length of the drill tools until then.
2. The cuttings are not being surveyed for hazardous or radioactive constituents, although the borehole is surveyed twice a day for hazardous constituents and once a week for radioactive constituents.
3. Sedimentary structures and odor cannot be detected and described. Mineralogy, roundness, color, HCl reaction, and/or consolidation can only be described sometimes.		DISTRIBUTION
RW Bryce
MA Chamness
TJ Gilmore
GV Last
SP Luttrell
DL Stewart
SS Teel	
JUSTIFICATION - The mud rotary drilling method uses a rotating bit to grind up sediments, and mud or air is used to bring the cuttings to the surface. The mud is used instead of casing to prevent the sides of the borehole from collapsing. It also prevents water from entering the borehole, and is too thick to measure depth to bottom through. The drilling process makes the samples not representative for several parameters normally detected and described. Where possible, the samples will be described fully.			
REMARKS - This Design Field Change does not affect the quality of the data collected. It is meant to indicate those areas where a procedure cannot be followed due to the method of drilling.			
INITIATOR/AUTHOR
M. A. Chamness <i>MA Chamness</i>	PHONE
376-1964	ORGANIZATION
Site Assess.	DATE
3/6/91
APPROVALS			
PROJECT MANAGER
TJ Gilmore <i>TJ Gilmore</i>		QAD REPRESENTATIVE
DL Stewart <i>D. S. Stewart</i> 3/13/91	
SENIOR TECHNICAL REVIEWER
GV Last <i>GV Last</i>			

DEFICIENCY REPORT

Page 1 of 1

1. DR #:
91-047	2. Date:
6/26/91	3. QA Plan #:
EES-059
4. Impact Level:
11	5. Project/Activity #:
11246/MBS05	6. Section #:
D7081
7. PROJECT/ACTIVITY TITLE:
Ground-Water Surveillance Project/Confined Aquifer Off-Site Migration Well
Installation-Well 699-32-228		
7a. CLIENT NAME:
DOE		
8. REQUIREMENT AND SOURCE OF REQUIREMENT:
KEN-5236, General Requirements for contract number KEN-5236
Two characterizations wells at Savage Island and 600 Area Hanford Site.		
9. DESCRIPTION OF DEFICIENCY: During installation of 6-inch casing into the open borehole, an attachment to the casing, by which the casing is held and lowered into place, broke. As a result, the casing string dropped to the bottom of the borehole. This 6-inch casing was not to be dropped nor set to the bottom of the borehole. Further, the casing may have been damaged.		
10. NCR Required? Yes ☐ No ☐	11. <i>John P. [Signature]</i>
Originator's Signature/Date
6/27/91	
12. EVALUATION AND CORRECTIVE ACTION:
a. CAUSE OF DEFICIENCY:
Insufficient strength of casing support, resulting in the support breaking off.		

12b. EFFECT OF DEFICIENCY ON VALIDITY AND INTEGRITY OF RESULTS:
☐ None ☒ Unknown ☐ Some ☐ Significant
 Explain:
 It has not been determined if the casing was damaged when it hit the borehole bottom.

12c. IF SOME, SIGNIFICANT, OR UNKNOWN EFFECT; IDENTIFY RESULTS EFFECTED (or potentially effected):
 Casing may have been bent, or weld(s) may have been broken

12d. ACTION TO CORRECT DEFICIENCY: Casing will be removed and inspected, borehole will be inspected with either a camera or caliper log, and non-damaged casing will be reinstalled.

12e. ACTION TO PRECLUDE RECURRENCE: Drilling subcontractor will be required to provide an improved method to support the casing or take additional necessary precautions to prevent recurrence.

Expected Completion Date: July 30, 1991

12f. CONTACT CLIENT? Yes ☒ No ☐
 If Yes:

Contacted: R. D. Hildebrand On: 6/24/91
 (Name) (Date)

By: R. V. Bryce
 (Name)

CLIENT'S RESPONSE:
 Client requested to be kept up to date with progress.

12g. *[Signature]* 7/2/91 12h. *[Signature]* 7/8/91

Cognizant Manager Signature/Date PDB Representative Signature/Date

Distribution: QSR PDB Rep. Originitor
 For Mgr.

13a. Criteria # 7 13b. Def. Code U 13c. Cause Code X 13d. Sig. Category IV

14. Closeout/Corrective Action Complete:
 Comments:

DISTRIBUTION

| <u>No. of
Copies</u> | | <u>No. of
Copies</u> | |
|--------------------------|---|--------------------------|-------------------------------------|
| <u>OFFSITE</u> | | 10 | <u>Pacific Northwest Laboratory</u> |
| 2 | DOE/Office of Scientific and
Technical Information | | R. W. Bryce K6-96 |
| | John Erickson | | R. E. Jaquish K1-30 |
| | Washington State Department of
Health | | F. A. Spane K6-96 |
| | Division of Radiation | | Publishing Coordination K1-06 |
| | Protection | | Technical Report Files (5) |
| | Airustrial Center | | <u>Routing</u> |
| | Building 5, M.S. L-13 | | R. M. Ecker SEQUI |
| | Olympia, WA 98503 | | M. J. Graham K6-78 |
| | | | C. J. Hostetler K6-81 |
| | | | P. M. Irving K6-98 |
| | | | R. L. Skaggs K6-77 |
| | | | C. S. Sloane K6-04 |
| | | | P. C. Hays (last) K6-86 |
| <u>ONSITE</u> | | | |
| 2 | <u>DOE Richland Field Office</u> | | |
| | E. D. Goller A5-19 | | |
| | R. D. Hildebrand A5-55 | | |
| 2 | <u>Westinghouse Hanford Company</u> | | |
| | R. L. Jackson H6-06 | | |
| | A. J. Knepp H6-06 | | |

END

**DATE
FILMED**

7 / 9 / 93