AIM

Association for Information and Image Management

1100 Wayne Avenue, Suite 1100
Silver Spring, Maryland 20910
301/587-8202

Centimeter

Inches

MANUFACTURED TO AIM STANDARDS
BY APPLIED IMAGE, INC.

1 of 1

PNL-8554

RECEIVED
MAR 19 1993
OSTI

**Cover Sheet for a Hanford
Historical Document
Released for Public Availability**

Released 1993

**Prepared for the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830**

**Pacific Northwest Laboratory
Operated for the U.S. Department of Energy
by Battelle Memorial Institute**

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This is a **historical document** that is being released for public availability. This was made from the best available copy. Neither the United States Government nor any agency thereof, nor Battelle Memorial Institute, nor any of their employees, makes **any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.** The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

PRELIMINARY EVALUATION OF THE GASEOUS
EFFLUENT SAMPLING SYSTEM AT THE
296-A-17 Stack - A, AX, AY, TANK
FARM

J. A. Glissmeyer
L. C. Schwendiman

December 1976

Battelle
Pacific Northwest Laboratories
Richland, Washington 99352

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

CONTENTS

1.0	INTRODUCTION	1
2.0	SUMMARY	1
3.0	DESCRIPTION OF SAMPLING SYSTEM	2
3.1	SAMPLE COLLECTION	2
3.2	SAMPLE MONITORING	8
4.0	PRELIMINARY EVALUATION	10
4.1	SAMPLE COLLECTION SYSTEM OPERATION	10
4.2	SAMPLE ALIQUOT SELECTION	11
4.3	SAMPLE COLLECTION SYSTEM PERFORMANCE	13
4.4	EVALUATION OF MONITORING SYSTEM	15
5.0	CONCLUSIONS	17
6.0	RECOMMENDATIONS FOR CORRECTION ACTION	18
	NOMENCLATURE	21
	REFERENCES	22
	APPENDIX A - INTERIM RADIOACTIVE GASEOUS EFFLUENT SAMPLING AND MONITORING CRITERIA FOR ATLANTIC RICHFIELD HANFORD COMPANY FACILITIES, ARH-CD-498	A-1
	APPENDIX B - FLOWMETER CORRECTIONS	B-1
	APPENDIX C - RADIOACTIVE GASEOUS DISCHARGES, TANK FARMS, ARH 222-2.3.12	C-1

PRELIMINARY EVALUATION OF THE GASEOUS EFFLUENT SAMPLING
SYSTEM AT THE 296-A-17 STACK - A, AX, AY, TANK FARM

1.0 INTRODUCTION

This evaluation of the 296-A-17 stack sampling system is part of a larger study, sponsored by ARHCO and conducted by Battelle-Northwest, of gaseous effluent sampling systems in ARHCO facilities. The objectives of this study are:

- Evaluate the compliance of the existing effluent particulate sampling system with ARHCO's Interim Criteria for such systems by using sampling theory and radioactivity counting statistics,
- Make recommendations for corrective action which will lead to a particulate sampling system in compliance with the Interim Criteria.

This study is considered preliminary because no experiments have been conducted to verify the sampling system's performance.

The following report includes a brief summary , a detailed description and evaluation of the sampling system, conclusions about satisfactory or deficient areas of the sampling system and recommendations for corrective action. The appendices contain a copy of the Interim Criteria, flowmeter correction calculations and applicable ARHCO Emergency Procedures.

2.0 SUMMARY

The gaseous effluent sampling system for the A, AX and AY tank farms has been evaluated for compliance with ARHCO's Interim Criteria for such systems and good sampling practices. The evaluation is not based on experimental findings but rather on observations of the system and sampling theory and radioactivity counting statistics. The existing sampling system has several deficiencies which are listed in the conclusions. Among these are poor sampling location, long and complicated sample piping, inadequate

flowrate measurements and insufficiently characterized monitoring instrumentation. Extensive recommendations were given outlining the elements of the replacement sampling systems. A few of these recommendations included defining appropriate measurement accuracy for certain releases, characterizing the effluent, designing new and separate inventory and monitor sampling systems and measuring flowrates properly. Some recommendations were made for interim improvements such as shutting off the hot air in-bleed system. Many of the recommendations, though specific for the installation in question, can be generally applied to many of the sampling systems already studied as part of this program.

3.0 DESCRIPTION OF SAMPLING SYSTEM

The gaseous effluent from the vessel vent system for the A, AX and AY tank farms is discharged through the 296-A-17 stack.^(1,2) The radioactive particulates most likely to be found in the effluent are cesium-137 and strontium-90.⁽³⁾ Before discharge to the stack the effluent has passed through condensers to remove excess moisture, a deentrainer, a heater and HEPA filters as diagrammed in Figure 1. The airstream has an approximate dewpoint of 65°F* and is heated to approximately 132°F**. The airflow is about 7200 ft³/min⁽⁴⁾ (at stack conditions) with an air velocity of about 4200 ft/min at the sampling probe. The effluent particulate sampling system consists of the sample collection and sample monitoring components to be described.

3.1 SAMPLE COLLECTION

A sample of the 296-A-17 stack particulate effluent is continuously extracted from the 15-ft level of the 50-ft tall, 18-in. diameter stack.⁽⁵⁾ The sampler installation is shown in Figures 2 and 3 and diagrammed in

*This needs to be confirmed because of the uncertainty of the location and calibration of the relative humidity and temperature sensor near the heater.

**This temperature was observed in the flow balance bypass on October 21, 1976.

FIGURE 1. A, AX, AY Tank Farm Ventilation Discharge Components
In and Adjacent to 241-A-702 Building (1)

FIGURE 2. Photograph of Inside of 241-A-702 Building Showing 296-A-17 Stack, Exhaust Fan, Sampling Enclosure, Sampler Penetration and Hot Air In-Bleed Heater. PNL neg. no. 7610920-14.

FIGURE 3. Photograph Showing Contents of Stack Sampler Enclosure at Base of 296-A-17 Stack.
PNL neg. no. 7610920-10.

in Figure 4. Table 1 lists the piping that the extracted sample passes through from the probe to the collector/detector.

The sample airstream is extracted subisokinetically through the three-nozzle probe. Hot air is added to the sample airstream just outside the stack. The sample airstream is piped inside the stack insulation to the collector/detector in the sampling enclosure. The particulates are filtered from the airstream by the 2-in. diameter asbestos fiber filter paper (Hollingsworth and Vose, HV-70) in the collector detector. Before reaching

TABLE 1. Sampler Piping

From Probe Inlet to Hot Air In-Bleed:

One	90° Bends	0.483 in. ID
Two	45° Bends	0.483 in. ID
One	45° Bend	0.622 in. ID
16 in.	Horizontal	0.622 in. ID
Three Nozzles	4 in. Vertical	0.483 in. ID

From Hot Air In-Bleed to Collector/Detector:

Three	90° Elbows	0.436 in. ID
Three	90° Bends	0.436 in. ID
Five	45° Bends	0.436 in. ID
One	45° Bends	0.622 in. ID
Three	90° Bends	@ 0.376 in. ID plastic tubing
18-in.	Horizontal	0.436 in. ID
96-in.	Vertical	0.436 in. ID
5-in.	Vertical	0.622 in. ID
4-in.	45° Slope	0.436 in. ID
3-in.	45° Slope	0.622 in. ID

FIGURE 4. Detailed Sketch of 296-A-17 Stack Sampling System^(2,6,7,8)

the collector/detector the particulate sample has passed through seventeen bends and about 12-ft of various sized plastic and stainless steel tubing.

The flowrates of the in-bleed feed air and the total sample airstream are measured with variable area flowmeters (Dwyer, Model RMB-54) calibrated for air at standard conditions--70°F, 29.92 in. of mercury. The in-bleed feed air flowmeter reads 50-55 SCFH and the total sample flowmeter reads 120 SCFH. Approximate corrections to these readings will be discussed later. The in-bleed feed air flowmeter has a pressure gauge (on the pressure regulator) and a bi-metal thermometer (held to the pipe by putty) at its inlet. There is no such instrumentation at the total sample flowmeter to allow corrections to the readings.

There is provision for emergency electrical power to the sample collection system and it is tied into the same back-up electrical power available to the exhausters fans.⁽¹⁷⁾ Therefore, if there is an electrical power failure the ventilation system will function and an effluent sample will be obtained.

3.2 SAMPLE MONITORING

The collected particulates are continuously monitored for beta-gamma emitting particles. The collected samples are changed every working day and are sent to the 222-S Building Air Sample Counting Room for analysis of total beta and alpha emitters according to the procedures in references 9 and 10. Total emission limits are set in the ARHCO emergency procedure (Appendix 3).

The monitoring system is diagrammed in Figure 5. The detector is a mica window GM tube⁽¹¹⁾ housed in the collector/detector which is a Hanford design.⁽¹²⁾ The signal is amplified and then discriminated to reduce the background. The usual background is around 5 c/sec. The higher energy pulses are converted to counts per second which is displayed on the count rate meter and strip chart recorder. The count rate ranges have maxima from 10 to 100,000 c/sec and the instrumentation is nominally set on the 0-20 c/sec range. A high release level alarm light is actuated when the strip chart recorder reaches 80% of full scale or 16 c/sec.⁽¹¹⁾

FIGURE 5. Schematic Diagram of Stack Sampler Monitoring System

The counting efficiency of the detector has not been determined but may be about 5%. The instrumentation response is checked monthly and there are no instrumentation malfunction alarms provided. The monitoring instrumentation is provided with emergency power from the same source that serves the exhausters fans. The instrumentation (except the detector) is found in the tank farm control room, the 241-A-271 Building, which is not continuously occupied.

4.0 PRELIMINARY EVALUATION

In this preliminary evaluation of the 296-A-17 stack sampling system the following discussion will center around the areas considered deficient. Those areas of the sampling system that are satisfactory will be listed later, along with the deficiencies, in the conclusion.

4.1 SAMPLE COLLECTION SYSTEM OPERATION

The use of the monitor sample as an inventory sample, the method of measuring flowrates and the application of the hot air in-bleed are the deficiencies in the operation of the sample collection system. There is not much to be discussed about the first of these deficiencies except that it makes it difficult to collect a quantitative sample for inventory purposes. The other two deficiencies will be discussed in the next paragraphs.

Neither of the variable area flowmeters described earlier are properly instrumented to allow accurate corrections to the flowmeter readings. However, the corrected flowrates can be estimated using a few assumptions. Assuming that the readings on the bimetal thermometer, putted to the pipe at the inlet to the air in-bleed flowmeter, really are correct for the inlet air (i.e. @ 40°C) the estimated in-bleed flowrate is about 1.34 SCFM (the calculations are found in Appendix 2). Assuming that the inlet conditions at the total sample flowmeter are 150°F and 5-6 in. Hg vacuum the corrected total flowrate is 1.68 SCFM. This leaves a net sample flowrate of only 0.34 SCFM or 0.376 CFM at the assumed probe inlet conditions of atmospheric pressure and 132°F. These

corrected flowrates are only estimates but they will be assumed as correct for calculations later in the report.

The net sample flowrate of 0.34 SCFM is a far cry from the 2 SCFM used by ARHCO in release calculations. This results in ARHCO reported releases being nearly six times too low if the collected sample is ideally representative. It would not take too much of an error in the estimated corrections to result in heated air actually being blown out the sample probe!

There is little justification for having a hot air in-bleed. The relative humidity and temperature measurements mentioned earlier yield a dewpoint of 65°F. There seems little reason to expect moisture condensation in the sample piping because the effluent is heated to about 132°F and much of the sample piping is enclosed in the insulation around the stack. Moisture condensation may occur if the effluent heater, which is steam powered, failed; but, thermostatically controlled electrical heating is a better alternative than the hot air in-bleed for heating the sample airstream and filter.

4.2 SAMPLE ALIQUOT SELECTION

The sample aliquot that is withdrawn from the effluent is characterized by its size, as determined by sample flowrate and sampling time, and whether or not it is a representative fraction of the total effluent. The representativeness of the sample aliquot may become distorted, through anisokinetic sample extraction and particle deposition, by the time the particulates are collected on the filter (and these distortions or biases will be addressed later); but, it should at least start out being representative. Whether or not the sample starts out representative is largely determined by the sampling location.

The present sampling location is a poor one because sample withdrawal occurs only one stack diameter from the airflow balance bypass and only three stack diameters from the effluent inlets to the stack. The stack is sufficiently tall to locate the sampling probe ten stack diameters downstream and five diameters upstream from major flow disturbances which may cause inadequate particulate mixing and flow development. Flow straighteners could be used if such a location is inconvenient.

The sample aliquot size is too small to allow a sufficiently accurate measurement of the release that must be measurable with a 24-hr sampling time as specified in Sampling Criterion No. 1. The criterion states that when an average ^{90}Sr concentration of $3 \times 10^{-11} \mu\text{Ci/ml}^*$ occurs during a 24-hr sample that the collected sample must contain sufficient activity for an appropriately accurate determination of the release. Let us assume that a sample counting accuracy of $\pm 10\%$, 95% confidence level is appropriate and that the collected sample is ideally representative. The current counting room method for calculating release concentration is⁽¹⁰⁾

$$\begin{aligned} \frac{\mu\text{Ci}}{\text{ml}} = & \text{net } \frac{\text{c}}{\text{min}} \times \frac{\text{d}^{**}}{0.383\text{c}} \times \frac{\text{min}}{\text{sample flowrate, ft}^3} \times \frac{\text{ft}^3}{28,320\text{ml}} \\ & \times \frac{1}{0.7^+} \times \frac{\mu\text{Ci-min.}}{2.22(10^6)\text{d}} \times \frac{1}{1440\text{min}^{++}} \end{aligned} \quad (1)$$

The accuracy of the sample analysis at the 95% confidence level is established by Equation 2.

$$\pm \text{Interval} = 1.96 \sqrt{\frac{\text{net c/min} + \text{background c/min}}{\text{sample counting time, min}}} + \frac{\text{background c/min}}{\text{background counting time, min}} \quad (2)$$

Assuming an average beta counting background of 15 c/min and a one minute counting time a net count of 400 c/min is required for a $\pm 10\%$ accuracy. Substituting the 400 c/min and the estimated sample flowrate of 0.376 CFM

* Here we assume the volume and flowrate units to be in terms of effluent conditions, i.e., 132°F and 29.92 in. Hg. This concentration limit is the most restrictive "Table II"⁽¹³⁾ limit for the expected radionuclides. This limit is more restrictive than the $1/2 \times$ Class I Action Level of the Emergency Procedure.

** The counting efficiency for total beta is 0.382 c/d.

+ The estimated collection efficiency of the HV-70 filter is assumed to be 70%.

++ The duration of the sampling period is one day or 1440 min.

(effluent conditions) into Equation 1 yields a measureable concentration of $4.38(10^{-11})$ $\mu\text{Ci/ml}$ provided the collected sample is ideally representative. To have a measurable concentration of $3(10^{-11})$ $\mu\text{Ci/ml}$ requires a sample flowrate of at least 0.55 CFM (using the same assumptions as before) as measured at stack conditions.

4.3 SAMPLE COLLECTION SYSTEM PERFORMANCE

As already discussed, the particulate sample withdrawn from the 296-A-17 stack is not likely to be representative of the effluent because of the poor sampling location. The sample ultimately reaching the filter paper is probably even less representative because of subisokinetic sampling and deposition of particles; however, these two effects cancel each other somewhat. The magnitude of the effect of these two mechanisms upon the sample bias depends on the particle sizes present, but the particle size distribution in the effluent is unknown. Therefore, we can only estimate the magnitude of sample bias for some likely particle sizes using methods developed in an earlier report.⁽¹⁵⁾

The estimated biases caused in the sample by subisokinetic extraction are estimated in Table 2 for various monodispersed aerosols. The assumptions used in the calculations are also listed in the table.

The actual biases may even be worse than calculated because the inlet nozzles are blunt rather than knife edged. If the nozzles were knife edged the total sample flowrate would have to be 15.5 CFM at effluent conditions (or 13.9 SCFM) to eliminate biasing the sample due to nonisokinetic sampling.

The particulate sample bias caused by deposition is roughly estimated in Table 3. The effects of pipe fittings and the collector/detector are ignored in the calculations although we know these have significant detrimental effect.⁽¹⁶⁾ The fractional delivery of the particulates through the sampler piping is shown for both monodispersed and polydispersed aerosols with geometric mean diameters as listed. Clearly, the many bends are the worst contributors to particle deposition.

TABLE 2. Anisokinetic Sampling Bias

Effluent Flowrate = 7,191 CFM Sample Flowrate = 0.125 CFM per nozzle
 Effluent Velocity = 4,069 ft/min Sample Velocity = 98.2 ft/min
 Effluent Temperature = 132°F Probe Nozzle ID = 0.483 in.
 Stack ID = 18 in.

<u>Particle Size,</u> <u>μm AED*</u>	<u>Concentration</u> <u>Bias</u>
0.5	1.20
1.0	1.78
2.0	3.95
5.0	14.3
8.0	23.6
10.0	27.8

TABLE 3. Fractional Delivery of Aerosols Through Sample Transport Piping

<u>Particle</u> <u>Size</u> <u>μm AED</u>	<u>Monodispersed Aerosols</u>				<u>Polydispersed</u> <u>Aerosols</u>
	<u>Probe to</u> <u>Hot Air</u> <u>In-Bleed</u>	<u>Bends</u>	<u>Vertical and</u> <u>Horizontal</u> <u>Lines</u>	<u>Total</u> <u>System</u>	<u>Total</u> <u>System</u>
0.5	1.00	.98	1.00	.98	.92
1	1.00	.94	1.00	.93	.80
2	.99	.77	.99	.76	.60
5	.97	.20	.94	.18	.34
8	.92	.02	.85	.01	.22
10	.87	.002	.77	.001	.17
Total Flow- rate, CFM	0.376	1.93	1.93		
Assumed Tem- perature, °F	132°F	150°	150°		

* AED refers to aerodynamic equivalent diameter, i.e., the diameter of a sphere with density 1g/cm³.

The subisokinetic sampling bias and the total fractional delivery for monodispersed aerosols can be multiplied to give a rough estimate of the combined bias for various particle sizes as shown in Table 4.

TABLE 4. Combined Monodispersed Aerosol Sampling Bias

<u>Particle Size</u> <u>μm, AED</u>	<u>Combined</u> <u>Fractional Bias</u>
0.5	1.18
1	1.66
2	3.00
5	2.57
8	0.24
10	0.028

Although a firm estimate of sample bias cannot be given the above calculations and discussions indicate that the samples collected by the existing sampling system are not representative for the likely effluent particulate sizes.

4.4 EVALUATION OF MONITORING SYSTEM

The present sample monitoring instrumentation seems to be appropriate and adequate in many respects although some of its important characteristics are unknown. The beta-gamma detector is satisfactory for the expected radioactive particulates; however, because the counting efficiency and energy discrimination levels are unknown it is difficult to assess if the signals from the decay of the radionuclides of interest are monitored and if the instrumentation is sensitive enough to detect release levels of interest. It is likely that the counting efficiency of the detector is about 5%. With this as an assumption some estimates of sensitivity can be made.

The Monitoring Criteria require that the samples collected at release levels of one half and hundred times Class I, II Action Levels (see

emergency procedure in Appendix 3) be within the range of the monitoring instrumentation*. The release level concentration consistent with the Class I, II Action Levels is

$$\begin{aligned} \text{Conc } \frac{\mu\text{Ci}}{\text{ml}} &= \frac{\text{Limit, } 0.01 \text{ Ci}}{\text{wk}} \times \frac{\text{wk}}{10,080 \text{ min}} \times \frac{10^6 \mu\text{Ci}}{\text{Ci}} \times \frac{\text{min}}{7200 \text{ ft}^3} \times \frac{\text{ft}^3}{28,320 \text{ ml}} \times \frac{1}{10} \\ &= 4.87 \times 10^{-10} \mu\text{Ci/ml} \end{aligned} \quad (3)$$

where the effluent flowrate, 7200 CFM, and the concentration are measured at the previously assumed effluent conditions (p. ?). During a 24-hr constant release of $4.87(10^{-10})\mu\text{Ci/ml}$ the c/sec collected on the sample are

$$\begin{aligned} \text{Class I, II} \\ \text{Collected c/sec} &= \frac{4.87(10^{-10})\mu\text{Ci}}{\text{ml}} \times \frac{0.376 \text{ ft}^3}{\text{min}} \times 1440 \text{ min} \times \frac{28,320 \text{ ml}}{\text{ft}^3} \\ &\times \frac{2.22(10^6)\text{d}}{\mu\text{Ci-min}} \times \frac{0.05\text{c}}{\text{d}} \times \frac{\text{min}}{60 \text{ sec}} \\ &= 13.8 \text{ c/sec} \end{aligned} \quad (4)$$

assuming the 5% counting efficiency, an ideal sample and a net sample flow-rate of 0.376 CFM (p. 10). Therefore, the material ideally collected during releases one-half or one hundred times Class, I, II levels are 6.9 c/sec and 1380 c/sec respectively. Only the latter of these is well above the 5 c/sec background, but both are within the range of the instrumentation. These responses should be reestimated once the detector calibration and discrimination energy level are known. There is the possibility that the background level will need further discrimination or reduction.

With the assumptions made in the last paragraph about sampling and monitoring system performance the present alarm level is slightly high to comply with Monitoring Criterion No. 7. According to the Criterion and the

* Both Class I and II Action Levels are concerned with measuring the same daily release levels. The only difference is that for a Class I Action the release is exceeded for only one day and for a Class II Action the daily release is exceeded two days in a row.

assumptions made the alarm should should at 13.8 c/sec rather than 16 c/sec. That is a small difference and this point should be reevaluated when more is known about the instrumentation.

There are some definite inadequacies in the monitoring system. There is an absence of malfunction alarms and audible alarms. Also the alarms are actuated in an intermittently occupied area.

5.0 CONCLUSIONS

The following is a list of conclusions reached as a result of this preliminary evaluation of the 296-A-17 stack sampling system.

1. There is no provision for separate inventory and monitor sampling systems as required by Sampling Criterion No. 5.
2. The collected radioactive particulate samples are not likely to be representative of the effluent because of the poor sampling location, subsokinetic sampling and particle deposition. A firm estimate of bias in the sample could not be given because of the lack of particle size information.
3. The measurement of sample flowrate is improperly made because of the lack of pressure and temperature instrumentation to allow corrections to the flowmeter readings.
4. The estimated net sample flowrate is too small to allow an accurate determination of a 24-hr average ^{90}Sr release of $3 \times 10^{-11} \mu\text{Ci/ml}$ even if the collected sample is assumed to be representative.
5. The use of the hot air in-bleed system is inappropriate for this sampling system.
6. There are no alarms to indicate loss of vacuum or the malfunction of sampling or monitoring system components.

7. The control room where the high release level alarm is located is not continuously occupied.
8. The counting efficiency and energy discrimination level of the monitor system is unknown.
9. There is adequate provision for emergency power to the sampling and monitoring components.
10. The beta-gamma detector is appropriate for the radioactive particulates expected.
11. No firm conclusions could be reached about the sensitivity of the monitoring system because sufficient information was not available as mentioned above in point eight. However, the lowest required measurable release (Monitoring Criterion No. 1) may not be detectable above background as discussed on pg. 16.

6.0 RECOMMENDATIONS FOR CORRECTIVE ACTION

The following is a list of recommendations which, if implemented, should result in a sampling system which will comply with the Interim Criteria. A new sampling system needs to be designed. The following should be elements of that design or must be considered before proceeding with the design work.

1. The new sampling program should include separate inventory and monitor sample collection systems.
2. Both sample collection systems will need new probes with knife edged nozzles which will sample isokinetically with a net sample flowrate in the 2-10 SCFM range. The probes should be installed at least ten stack diameters downstream and five stack diameters upstream of significant flow disturbances. An installation on the roof of the 241-A-702 building may be convenient.
3. For the inventory system the sample collector should be in the stack or short coupled to it. For the monitor system the collector/detector should be short coupled to the stack. There should be no more than two bends or 180° of total bend in either system's delivery piping.

4. A new collector/detector design with significantly lower particle deposition is recommended as a valuable improvement for the monitor system.
5. The sample delivery piping should be electrically and thermostatically heated if the effluent heater fails or the sampling system collectors are not short coupled to the stack.
6. Provision should be made to periodically clean the sampling system piping to account for deposited radioactive particles.
7. Both sample collection systems must be properly instrumented for the measurement and control of sample flowrates. The temperature and pressure conditions for the measurement of effluent flowrate, sample flowrate and the calculation of releases must be defined and, when these conditions differ, corrections must be applied to calculations and measurements. Commercially available mass flowmeters would be ideal for sample flow measurement and can be easily made part of a feedback control loop. If other flowmetering devices are used (e.g., rotameters) they should be properly instrumented to allow corrections to be made when they are used in conditions different from the calibration conditions. Consideration should be given to flow totalizers such as gas meters or flowrate recorders.
8. The alarms for high level release and system component malfunctions must be visual and audible in a continuously occupied area.
9. The counting efficiency and other characteristics of the monitoring instrumentation must be obtained and a reassessment of monitor sensitivity made similar to that on p. 16.
10. It is desirable to test sampling system performance and bias when suitable testing techniques become available.

11. The effluent characteristics at the sample withdrawal locations should be studied. These characteristics include velocity profile, temperature, pressure, dewpoint and particle size if desirable.
12. The personnel authorized to make adjustments in the sampling system operations must be thoroughly trained in the system's operation and design features.
13. Define what constitutes appropriate accuracy for the measurement of releases required in Sampling Criterion No. 1. The size of the sample aliquot required for that accuracy should then be reevaluated as shown on page 12.
14. Inasmuch as the immediate implementation of the above recommendations is not likely the following interim improvements are recommended:
 - a. shut-off the hot air in-bleed system,
 - b. maintain a sample flowrate of around 2 SCFM and communicate this value (corrected to effluent conditions if desired) to the air sample counting room,
 - c. add temperature and vacuum pressure gauges to inlet side of the flowmeter and provide a chart for correction of readings,
 - d. short couple the collector/detector to the sample delivery piping at the point where it emerges from the stack insulation, and
 - e. measure effluent temperature and reestimate effluent and sample flowrates at both effluent and standard conditions.

NOMENCLATURE

AED - aerodynamic equivalent diameter
c - counts
CFM - cubic feet per minute at other than standard conditions
Ci - curies
d - disintegrations
ft - feet
hr - hour
ID - inside diameter
in - inch
in. Hg - inches of mercury pressure
min - minutes
ml - milliliter
psia - pounds per square inch, absolute
psig - pounds per square inch, gauge
SCFH - standard cubic feet per hour @ 70°F, 29.92 in. Hg
SCFM - standard cubic feet per minute @ 70°F, 29.92 in. Hg
sec - seconds
wk - week
 μCi - micro (10^{-6}) curies
 μm - micro (10^{-6}) meters, microns

REFERENCES

1. Drawing H-2-35749, "Vent System, Tank Farms A-AX-AY", ARHCO Engineering Files.
2. Drawing H-2-62895, "Instrument Engineering Flow Diagram, Building 241-A-702 Vent System Expansion", ARHCO Engineering Files.
3. N. P. Willis, Private Communications, ARHCO (November, 1976).
4. J. H. Palmer, Private Communications, ARHCO (November, 1976).
5. Drawing H-2-62883, "Architectural, Structural Sections and Details", ARHCO Engineering Files.
6. Drawing H-2-35770, "241-A-702 Building Stack Air Sampler", 2 Sheets, ARHCO Engineering Files.
7. Drawing H-2-35771, "241-A-702 Building Stack Sampler Installation", ARHCO Engineering Files.
8. Drawing H-2-62896, "Instrument-Impulse and Sample Piping, Vent System Expansion-241-A-702 and 241-A-271 Buildings", ARHCO Engineering Files.
9. Emergency and Holiday Coverage of 222-S Counting Room, Technical Services Section, Laboratory Operations Procedure No. ECOVCR-01A, ARHCO, (October 1973).
10. An Outline of Environmental Air Sample Analysis, ARH-869, ARHCO (October 1968).
11. B. G. Powaukee, Private Communications, ARHCO (December, 1976).
12. Drawing H-2-33904, "Stack Monitor-Air Sampler Assembly and Details", ARHCO Engineering Files.
13. ERDA Manual Chapter 0524, "Standards for Radiation Protection," Appendix 0524, Annex A, (April 1975).
14. L. J. Shinker, Private Communications, ARHCO (November, 1976).
15. L. C. Schwendiman, G. E. Stegen, J. Mishima, J. A. Glissmeyer, Interim Report: An Analysis of the Gaseous Effluent Sampling System - 225-B, Waste Encapsulation and Storage Facility, Appendix, BNWL-B-408, Battelle-Northwest, Richland, WA, (April, 1975).

16. L. C. Schwendiman, J. Mishima, J. A. Glissmeyer, Evaluation of the Sampling of Radioactive Particles in Gaseous Effluents-Monthly Progress Report, January, 1975 (February, 1975).
17. H. Hadley, Private Communications, ARHCO, (December 1976).

APPENDIX 1

INTERIM RADIOACTIVE GASEOUS EFFLUENT SAMPLING AND
MONITORING CRITERIA FOR ATLANTIC RICHFIELD HANFORD
COMPANY FACILITIES, ARH-CD-498

INTERIM RADIOACTIVE
GASEOUS EFFLUENT SAMPLING AND MONITORING CRITERIA
FOR ATLANTIC RICHFIELD HANFORD COMPANY FACILITIES

INTRODUCTION

To ensure that gaseous radioactive releases to the environment are kept as low as practicable, it is necessary to sample all of the radioactive or potentially radioactive gaseous effluent streams in the 200 Areas. Specific gaseous effluent streams that have the potential for release of large quantities of radioactive materials must also be monitored by radiation detection instrumentation.

The criteria listed below are intended to be used as guidelines to aid in the design of new systems or the upgrading of existing systems. It is highly desirable that new or upgraded systems be able to meet or nearly approach as many of the following criteria as is practicable.

SAMPLING CRITERIA

The term "sampling" applies to the extraction, transport and collection of a sample of the radionuclides present in the gaseous effluent stream on a collection media suitable for subsequent laboratory analysis. Gaseous effluent sampling systems shall:

1. extract in a 24-hour period a representative fraction of the effluent stream such that an activity release at least as low as the concentration guides given in ERDA Appendix 0524, Annex A, Table II can be measured with appropriate accuracy upon subsequent laboratory analysis.*
2. be designed, fabricated, and operated so that the particles extracted and transported to the collector will be representative to the degree that particles 10 micrometers and smaller in the sample collected will be at least 90 percent of the 10 micrometer and smaller particles in the same volume of a truly representative sample. At least 90 percent of the radioactive gases withdrawn shall be collected on the media selected or delivered to the activity sensing chamber in flow through monitors.
3. operate in a continuous mode, except for short periods when the sample collection media is being changed, whenever the facility is exhausting to the atmosphere.
4. extract samples of particles and gases that are a representative aliquot of the actual effluent stream.

* If one half of the Class I Action Level in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility) is less than the Table II concentration guides, use one half of the Class I Action Level from the appropriate Emergency Procedure as the basis for this criterion.

5. collect at least two samples, one of which will be designated and used exclusively as an inventory sample.
6. shall provide particulate and gaseous samples that have not been adversely affected by condensation of moisture.
7. be equipped with a vacuum system for sample extraction that has the same number of back-up power systems as the exhaust fans of the facility. The vacuum system shall be provided with an alarm that is activated upon the loss of vacuum.
8. provide an inventory sample which is an accurate aliquot, within a factor of two, of the absolute radioactive materials of the effluent stream. (Note: This statement relates only to the sample extraction and delivery capability, not to the accuracy of detection and measurement.)
9. provide inventory samples with less than 25 percent variation from the mean of several similar samplings at the 95 percent confidence level.
10. have at least an annual check to ensure that variation in effluent characteristics (particle size, mass activity concentrations, etc.) have not changed significantly.

MONITORING CRITERIA

The term "monitoring" applies to the use of radiation detection instrumentation to measure the amount of radioactivity collected by the collection media. Gaseous effluent monitoring systems shall:

1. monitor the samples collected (except for the designated inventory sample) as detailed in items 1-10 under Sampling Criteria. The monitoring system shall be able to detect an activity release at least as low as one half that required for the Class I Action Level listed in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility).
2. detect the radiation from radionuclides in the effluent stream with appropriate sensitivity for the radiation emitted.
3. operate in a continuous mode, except for short periods while samples are being changed, whenever the facility is exhausting to the atmosphere.
4. be equipped with the same number of back-up power systems as the exhaust fans of the facility.
5. incorporate a permanent recorder to document the level of radioactivity measured by the radiation detection instrument.

11/14/75
DJC:bac

6. be provided with a "fail-safe" system that alarms when a malfunction occurs in the radiation detection instrument or upon loss of vacuum.
7. alarm at a pre-set "trip" point that is consistent with a Class II Action Level as specified in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility).
8. be able to detect a Class II Action Level as specified in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility) in less than 24 hours.
9. alarm visually and audibly in a continuously occupied area for both the "fail-safe" alarm(s) and the emergency alarm(s).
10. be equipped with sufficient range to detect activity levels up to 100 times the Class II Action Level in ARH-222, ARHCO Emergency Procedure 1.9 (or the Emergency Procedure that governs gaseous discharges for the specific facility).
11. have the radiation detection instrumentation calibrated on at least a quarterly basis.

APPENDIX 2

FLOWMETER CORRECTIONS

FLOWMETER CORRECTIONS

HOT AIR IN-BLEED FLOWMETER

The following readings were observed:

Oct. 21, 1976: Temp. = 43°C = 109°F; Press. = 22 psig;
Flow = 55 SCFH

Nov. 11, 1976: Temp. = 35°C = 95°F; Press. = 22 psig;
Flow = 50 SCFH

The absolute pressure = 22 psig + 14.7 psia = 36.7 psia = 74.7 in. Hg.

Corrected flow rates:

$$\begin{aligned}\text{Oct. 21, 1976 SCFH} &= 55 \text{ SCFH} \sqrt{\frac{74.7 \text{ in. Hg}}{29.92 \text{ in. Hg}}} \times \frac{530^{\circ}\text{R}}{(460 + 109)^{\circ}\text{F}} \\ &= 83.9 \text{ SCFH}\end{aligned}$$

$$\begin{aligned}\text{Nov. 11, 1976 SCFH} &= 50 \text{ SCFH} \sqrt{\frac{74.7 \text{ in. Hg}}{29.92 \text{ in. Hg}}} \times \frac{530^{\circ}\text{R}}{(460 + 95)^{\circ}\text{F}} \\ &= 77.2 \text{ SCFH}\end{aligned}$$

$$\text{Ave.} = 80.6 \text{ SCFH} = 1.34 \text{ SCFM}$$

TOTAL SAMPLE FLOWMETER

The flow reading on both Oct. 21 and Nov. 11, 1976 was 120 SCFH.

The assumed conditions are: Temp. = 150°F; Vacuum = 5.6 in. Hg;
Pressure = 24.3 in. Hg.

$$\begin{aligned}\text{Estimated corrected flowrate} &= 120 \text{ SCFH} \sqrt{\frac{24.32 \text{ in. Hg}}{29.92 \text{ in. Hg}}} \times \frac{530^{\circ}\text{R}}{(460 + 150)^{\circ}\text{F}} \\ &= 100.8 \text{ SCFH} = 1.68 \text{ SCFH}\end{aligned}$$

NET SAMPLE FLOWRATE

$$\text{Net Sample Flowrate} = \frac{(100.8 - 80.6) \text{ SCFM}}{60} = 0.337 \text{ SCFM}$$

$$= 0.337 \text{ SCFM} \times \frac{(460 + 132)^{\circ}\text{R}}{530^{\circ}\text{R}} = 0.376 \text{ CFM}$$

GENERAL EQUATION

$$\text{Corrected Flowrate SCFH} = \text{Reading SCFH} \sqrt{\frac{P_R}{P_S} \cdot \frac{T_S}{T_R}}$$

P_R and P_S are the absolute pressures at the flowmeter inlet and standard conditions respectively. T_R and T_S are the absolute temperatures at the flowmeter inlet and standard conditions respectively. The standard conditions for the rotameters in question are 70°F (530°R) and 29.92 in. Hg.

APPENDIX 3

RADIOACTIVE GASEOUS DISCHARGES, TANK FARMS, ARH 222-2.3.12

ISSUED BY THE MANAGER	SUBJECT	CLASSIFICATION	
Tank Farm Operations	RADIOACTIVE GASEOUS DISCHARGES TANK FARMS	ARH-222	
<p>A. <u>Introduction</u></p> <p>Gases discharged from the various Tank Farm stacks are monitored for radioactivity. Some of the emissions are measured and recorded continuously while others are monitored by periodic counts of air samples. Laboratory measurements are used for final determination and record all stack samples.</p> <p>Certain actions and notifications are required in the event of a significant discharge of radioactivity.</p> <p>B. <u>Gaseous Discharge-Radioactivity Level Determination</u></p> <p>First indication that a release of radioactive material to the atmosphere may have occurred will come from a monitoring instrument alarm or preliminary radiation instrument reading on a stack air sample.</p> <p>Operating supervision is to be notified at the first indication of an abnormal reading or alarm and will proceed to determine actions as outlined in section C, below.</p> <p>Table 1 and 2 attached provide some information to assist in preliminary evaluation of release levels.</p> <p>C. <u>Action Required</u></p> <p>1. <u>Supervisor's Responsibilities</u></p> <p>a. Upon receiving an alarm, the responsible supervisor will immediately notify radiation monitoring, then proceed to investigate or determine whether the alarm was due to high radioactivity or an instrument malfunction.</p> <p>b. The supervisor will request replacements of the air sample and an immediate count of the sample by radiation monitoring.</p>			
DATE ISSUED JUN 1 1976	SUPERSEDES ISSUE DATED 5-20-75	PAGE 1 OF 6	EMERGENCY PROCEDURE 2.3.12

EMERGENCY PROCEDURE

- c. The supervisor will notify his management if the alarm is found to be due to a radioactivity level that exceeds the levels described in section D, below.
- d. The supervisor will initiate an investigation to determine the source of radioactive emissions.
- e. The supervisor will keep management informed throughout the progress of his investigations. He will consult with management upon the course of action to resolve the problem. He will prepare a written report of the investigation and findings.

2. Radiation Monitoring Responsibilities

Radiation monitoring will provide assistance by changing air samples, counting samples and evaluating data.

3. Tank Farm Process Engineering

Operations Support Engineering will provide assistance as required during the investigation, isolation and resolution of problems.

4. Management Responsibilities

- a. Tank Farm Operations (TFO) management will provide guidance as required during the investigation, isolation and resolution of problems.
- b. The Manager, TFO will determine when environmental discharges warrant defining the situation as being in the emergency category.
- c. TFO Management will implement activities required of personnel under emergency conditions.
- d. The Manager, TFO will communicate all information to Departmental Management required under emergency conditions.

DATE ISSUED	SUPERSEDES ISSUE DATED	PAGE	EMERGENCY PROCEDURE
JUN 1 1976	5-20-75	2 OF 6	NO. 2.3.12

D. Situation Definitions and Action

1. Class I

Definition

Daily environmental discharge exceeds ten percent of the release level values specified in section 5 of Radiation Protection Standards and returns to less than ten percent within 48 hours. ARH-220 (see table 2, attached).

Action

Notify plant and department management. Investigate to determine the cause. Document investigation and conclusions.

2. Class II

Definition

Daily environmental discharge exceeds ten percent of the release level values in section 5 of Radiation Protection Standards for more than 48 hours.

Action

Notify plant, department and division management. Investigate to determine the cause. Document the investigation and conclusions.

3. Class III An Emergency

Definition

Environmental discharge exceeds the release level value in section 5 of Radiation Protection Standards.

Action

Notify plant, department, division management and the U. S. Energy Research and Development Administration. Promptly investigate to determine the cause and corrective action.

DATE ISSUED	SUPERSEDES ISSUE DATED	PAGE	EMERGENCY PROCEDURE
JUN 1 1976	5-20-75	3 OF 6	NO. 2.3.12

EMERGENCY PROCEDURE

4. Class IV An Emergency

Definition

Environmental discharge that exceeds ten times the release level values in section 5 of Radiation Protection Standards.

Action

Notify plant, department, division management and the U. S. Energy Research and Development Administration immediately. Investigate promptly to determine the cause and corrective actions. If control cannot be immediately established or the discharge has exceeded 100 times the release level values, the facility shall be shut down. Document the investigation and conclusions. Take positive action to prevent recurrence.

PREPARED BY J. S. Ferguson DATE 3-25-76

REVIEWED BY C. J. Hocking DATE 4-20-76
(TFO)

APPROVED BY B. J. Sammons DATE 5/18/76
(RMS)

APPROVED BY T. H. Nelson DATE 5-25-76
(MPP)

ISSUED BY J. S. Ferguson DATE 1 June 76
(MTFO)

DATE ISSUED	SUPERSEDES ISSUE DATED	PAGE	EMERGENCY PROCEDURE
JUN 1 1976	5-20-75	4 OF 6	NO. 2.3.12

TABLE I

CONVERSION FACTORS FOR
SELECTED TANK FARM STACKSCONVERSION FACTORS
for Ci emitted per sampling period

Stack Code Number	Ident.	Location	Filter Size inia.	Sample Flow Rate Cu. Ft/Min	Stack Flow Rate Cu. Ft/Min	EGM Ci per c/m	P11 Probe Ci per c/m	CP Ci per Mrads/hr at contact	Alpha Ci per d/m
6	91-F	291-S	4"	3	40,000	6×10^{-7}	1.5×10^{-7}	4×10^{-4}	6.0×10^{-9}
52	ARCS	244-AR	2"	1	20,000	9×10^{-7}	2.3×10^{-7}	6×10^{-4}	9×10^{-9}
58	ARVVS	AR-Vessel	2"	1	380	1.8×10^{-8}	4.5×10^{-9}	1.2×10^{-5}	1.8×10^{-10}
59	702-A	AXFS	2"	1	6,900	3×10^{-7}	8×10^{-8}	2×10^{-4}	3×10^{-9}

DATE ISSUED	SUPERSEDES ISSUED DATED	PAGE	EMERGENCY PROCEDURE
JUN 1 1976	5-20-75	5 OF 6	NO. 2.3.12
84-5000-086 (2-73)			

TABLE 2
GASEOUS WASTES
(Ref. ARH-220)

Gaseous radioactive wastes (mists or gases) shall be controlled so that the amounts released will be kept as small as practicable and should not average greater than the following amounts:

<u>Radionuclide</u>	<u>AMOUNT IN CURIES PER WEEK</u>	
	<u>Released from 200-ft. Stack</u>	<u>Released from Shorter Stacks or Vents</u>
^{90}Sr	0.1	0.01
^{131}I	0.03	0.003
Plutonium (total)	0.001	0.0001
Uranium (natural)	0.004	0.0004
Total of all others (excluding ^3H , ^{14}C , and noble gases)	0.5	0.05

In addition, the total amount of ^{131}I released from all 200 Area sources shall not exceed 1 curies per calendar quarter.

DATE ISSUED: JUN 1 1976	SUPERSEDES ISSUE DATED: 5-20-75	PAGE 6 OF 6	EMERGENCY PROCEDURE NO. 2.3.12
----------------------------	------------------------------------	----------------	-----------------------------------

**DATE
FILMED**

7 / 22 / 93

END