DOE/MC/23167--3321

DE93 000257

Advanced Coal-Fueled Gas Turbine Systems

**Annual Report
July 1991 - June 1992**

September 1992

Work Performed Under Contract No.: DE-AC21-86MC23167

**For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
Morgantown, West Virginia**

**By
Westinghouse Electric Corporation
Power Generation Business Unit
Orlando, Florida**

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from (615)576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

Advanced Coal-Fueled Gas Turbine Systems

**Annual Report
July 1991 - June 1992**

Work Performed Under Contract No.: DE-AC21-86MC23167

**For
U.S. Department of Energy
Office of Fossil Energy
Morgantown Energy Technology Center
P.O. Box 880
Morgantown, West Virginia 26507-0880**

**By
Westinghouse Electric Corporation
Power Generation Business Unit
4400 Alafaya Trail
Orlando, Florida 32826-2399**

September 1992

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1 EXECUTIVE SUMMARY	1-1
2 INTRODUCTION	2-1
2.1 Scope of Report	2-1
2.2 Program Objectives	2-2
2.3 Combustor Concept	2-3
2.4 Development Progress and Plan	2-6
3 SUBSCALE SLAGGING COMBUSTOR TEST: APPARATUS, PLAN AND METHOD	3-1
3.1 Test Facility and Apparatus	3-1
3.2 Fuel Feed Systems	3-1
3.3 Combustor Test Rig	3-2
3.4 Gas Sampling System	3-5
3.5 Sorbent Feed System	3-5
3.6 Description of Combustor Configuration Tested	3-6
3.7 Coals Tested	3-8
3.8 Sorbents Tested	3-10
3.9 Nominal Test Conditions	3-10
4 SUBSCALE SLAGGING COMBUSTOR: TEST RESULTS AND DISCUSSION	4-1
4.1 Char Quantification	4-4
4.1.1 Results of Char Quantification Tests CR1-1 through CR1-6.....	4-9
4.1.2 Helium-Neon Laser Diagnostic Addition.....	4-10
4.2 Sulfur Capture Tests	4-12
5 GENERIC TURBINE STUDIES.....	5-1
6 CONCLUSIONS	6-1
7 REFERENCES	7-1

LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
2-1 Schematic of Slagging Combustor Concept, Including Slag and Spent Sorbent Removal Subsystem	2-4
2-2 Slagging Combustor Original Configuration.....	2-6
3-1 Schematic of Subscale Slagging Combustor Test Rig with Real-Time Slag-Tapping Capability and Slagging Cyclone.....	3-2
3-2 Schematic of Subscale Slagging Combustor Test Rig as Configured for Char Quantification Tests CR1-2 Through CR1-4.....	3-3
3-3 Curved Body Impact Separator with Slag Tap and Collection Vessel	3-4
3-4 Sketch of Vibrating Louver Apparatus Added to Sorbent Feed System	3-6
4-1 Measured Primary Zone Carbon Conversions.....	4-27
4-2 NO _x Exhaust Emissions.....	4-28

LIST OF TABLES

<u>Table</u>	<u>Page</u>
3-1 Combustor Configuration Employed for All Tests During the Period of August 30, 1991 to June 30, 1992	3-7
3-2 Centerbody Impact Separator Installed for Tests CR1-2 Through CR1-4, Test Period July 10, 1991 to August 21, 1992....	3-7
3-3 Ultimate and Proximate Analyses of Coals Tested During This Reporting Period - (Dry Basis)	3-8
3-4 Ash Analysis for Coals Tested During This Reporting Period - (Dry Basis)	3-9
3-5 Sorbents Evaluated During This Reporting Period	3-10
3-6 Nominal Test Conditions	3-10
4-1 Chronology of Testing During the Report Period	4-2
4-2 NSP Coal Test Matrix.....	4-23
4-3 Nominal Test Conditions.....	4-23
4-4 Analyses for Coals Tested to Date.....	4-24
4-5 Ash Analysis and T-250's.....	4-25
4-6 Carbon Burnout and Combustion Efficiency.....	4-26
4-7 Particulate Emissions Levels and Collection Efficiencies.....	4-29
4-8 Alkali Levels.....	4-30
4-9 Heat Loss Data.....	4-32
4-10 Combustor Subsystem Pressure Losses.....	4-32
4-11 Composition of Fuel-Rich Gases.....	4-33
4-12 Fuel Heating Values.....	4-33
5-1 Effect of Change in Ambient Temperature with 1600°F BOT.....	5-2
5-2 Effect of Change in PCFB Pressure Drop with 1600°F BOT.....	5-3
5-3 Effect of Change in Fuel Composition with 1600°F BOT.....	5-4

LIST OF TABLES (Cont'd.)

<u>Table</u>		<u>Page</u>
5-4	Effect of Change in Ambient Temperature with 1950°F BOT.....	5-5
5-5	Effect of Change in PCFB Pressure Drop with 1950°F BOT.....	5-6
5-6	Effect of Change in Fuel Composition with 1950°F BOT.....	5-7

EXECUTIVE SUMMARY

Slagging Combustor

Westinghouse's Advanced Coal-Fueled Gas Turbine System Program (DE-AC21-86MC23167) was originally split into two major phases - a Basic Program and an Option. The Basic Program also contained two phases. The development of a 6 atm, 7 lb/s, 12 MMBtu/hr slagging combustor with an extended period of testing of the subscale combustor, was the first part of the Basic Program. In the second phase of the Basic Program, the combustor was to be operated over a 3-month period with a stationary cascade to study the effect of deposition, erosion and corrosion on combustion turbine components.

The Option phase was to have been devoted towards performing a verification test of a 70 MMBtu/hr combustor.

Participants in this Westinghouse-led effort included: Westinghouse's Power Generation Business Unit, and Science and Technology Center; Avco Research Laboratory/Textron (now referred to as Textron due to an internal reorganization); Gilbert/ Commonwealth, Inc.; and, AMAX Extractive Research and Development, Inc.

It was decided by DOE/METC to terminate the experimental portion of this program at the conclusion of the slagging combustor tests in 1991. In December of 1991 slagging combustor testing was suspended for three months, in order to perform combustion tests on Northern States Power Company (NSP) coals. These tests were paid for by Westinghouse, NSP and Textron in order to evaluate combustor performance while burning western subbituminous coals. The results of these tests are being used to guide commercialization efforts by Westinghouse and NSP in the commercialization of the slagging combustor technology. At the conclusion of this testing it was decided by Westinghouse that no further testing would be conducted at Textron using the slagging combustor. Instead, further testing would continue as part of the overall W/NSP commercialization plan. This testing will be done during the pilot plant phase at NSP.

The testing of the concept, in subscale, has demonstrated its ability to handle high- and low-sulfur bituminous coals, and low-sulfur subbituminous coal. Feeding the fuel in the form of PC has proven to be superior to CWM type feed. The program objectives relative to combustion efficiency, combustor exit temperature, NO_x emissions, carbon burnout, and slag rejection have been met. Objectives for alkali, particulate, and SO_x levels leaving the combustor were not met by the conclusion of testing at Textron. It is planned to continue this testing, to achieve all desired emission levels, as part of the W/NSP program to commercialize the slagging combustor technology.

During the previous annual reporting period the slagging combustor had been fitted with a slagging cyclone. Immediately after the integration of the slagging cyclone to the system, noticeable quantities of char began to appear in the cyclone slag bucket and in the combustor exhaust gases. Therefore a series of tests, CR1-X, were devised to quantify the amount of char being produced in the subscale slagging combustor system. The secondary purpose of this test series was to quantify the slag separation efficiency of the curved body impact separator and to acquire more information on the operation of the slagging cyclone separator.

Based on the results of the CR1-X tests conducted, 2-3% (wgt) of the coal was not being burned-out, resulting in the observed char. Several possible mechanisms for the occurrence of char subsequent to the integration of the slagging cyclone were determined. The most likely cause was thought to be that the elevation of the system for the purpose of cyclone integration probably upset the distribution of coal to the four coal/air injectors issuing into the primary zone. This would lead to spatial non-uniformities in primary zone stoichiometry, which could lead to char production.

The corrective action eventually defined and implemented during the sulfur reduction series of tests (SL2-X) was to increase conveying velocities by replacing all conveying line hoses with smaller inside diameter (ID) hoses, while keeping the carrier gas flow rate constant. Gaseous nitrogen from a high pressure tube trailer was used as the coal carrier gas for test SL2-2A so that higher supply pressures could be achieved. Although a non-oxidizing gas was being injected with the coal during test SL2-2A, test results showed that char production had been significantly reduced. The increased pressure losses introduced by the smaller ID conveying lines required operating the coal delivery system at its pressure limit. Since this was not acceptable, the corrective action defined for test SL2-3 was to increase conveying line velocities by increasing the flow rate of carrier gas through the original, larger ID conveying lines.

The results of test SL2-3 were dramatic; essentially no char was found in the cyclone slag bucket and particle collection filters. These results suggested that the system elements influencing char production and plausible mechanisms for char production had been identified, and that the corrective steps taken were very effective.

It was also determined that the required delivery system operating parameters for sorbent injection couldn't be achieved with the system as it was then configured. What was needed was higher conveying velocities, which meant higher sorbent carrier air mass flows were needed. This was the same remedy that was used to achieve stable coal delivery system behavior. It had become clear that changes made to the combustor system when the slagging cyclone was installed had affected the behavior of both the coal and sorbent delivery

systems. The required carrier air flow rates for the sorbent delivery system were achieved by using the air tube trailer source that was supplying air to the coal delivery system.

Overall slag collection efficiencies for the combined performance of the curved body impact separator and slagging cyclone separator were determined to be 98%-99%. This represents a significant improvement over the 90% efficiency of the pre-cyclone, centerbody impact separator. Based on gas analyzer derived carbon burnout results, the system appeared to be producing carbon conversion efficiencies nominally the same as those measured before the cyclone separator was installed. Carbon conversion efficiencies of 98.5 to 97.5 were measured as the equivalence ratio was varied between $\phi = 1.2$ to 1.5. It should be noted that essentially no char was detected in the cyclone bucket or exhaust particle probe filters since the char problem was corrected by decreasing the coal to carrier-air loading ratio from nominally 6 to 3.

Generic Turbine Studies

During April 1991, the workscope for the Advanced Coal-Fueled Gas Turbine Systems Program was modified. Part of the modification was the addition of Task 12, Generic Turbine Studies. This additional workscope was added to support the gas turbine design effort for the then Wisconsin Dairyland Program which was an award of CCT 3. The CTT 3 program has since changed hands, first to Northern States Power and now to Pyropower/Iowa Power Des Moines Energy Center Project.

The Task 12 workscope was divided into six (6) technical subtasks. These subtasks are to do conceptual analyses for turbine and plant performance, optimum blading and cooling arrangements, casing arrangements for interface with the off-base combustion and turbine systems modifications. Conceptual efforts on the start-up combustion system and interconnecting piping system are also to be done.

Due to the changes in the location of the CCT 3 project and a delayed decision as to whether or not to include a 2nd generation topping combustor, a considerable delay was encountered in getting this work started. In March of this year a request to DOE for a four (4) month extension was submitted and granted. The program end date is now the end of April 1993.

Barring the delays, considerable progress has been made on Task 12. Turbine and plant performance calculations have been completed for a low flow 251B12 combustion turbine. Calculations were performed at various ambient temperatures, pressure drops in PCFB and fuel compositions.

INTRODUCTION

This is the fifth annual technical progress report for the Advanced Coal-Fueled Gas Turbine Systems Program. This program was initiated by the Department of Energy as an R&D effort to establish the technology base for the commercial application of direct coal-fired combustion turbines. The combustion system under consideration incorporates a modular three-stage slagging combustor concept. Fuel-rich conditions inhibit NO_x formation from fuel nitrogen in the first stage; also in the first stage, sulfur is captured with sorbent; coal ash and sulfated sorbent are removed from the combustion gases by inertial means in the second stage by the use of an impact separator and slagging cyclone separator in series. Final oxidation of the fuel-rich gases, and dilution to achieve the desired turbine inlet conditions are accomplished in the third stage, which is maintained sufficiently lean so that here, too, NO_x formation is inhibited.

Prior to this reporting period the slagging combustor had been configured to operate on pulverized coal (PC) and was then modified to operate on coal-water mixture (CWM). The slagging combustor system was then redesigned to accommodate a slagging cyclone and a modified impact separator with real-time slag removal. Because PC fuel proved to be the preferred fuel over CWM, the slagging combustor has been operated for the past two (2) years with PC.

2.1 SCOPE OF REPORT

This report covers work performed under DOE METC Contract DE-AC21-86MC23167, Advanced Coal-Fueled Gas Turbine Systems, for the period July 1991 through June 1992. During this time frame, effort has been divided between Task 3.1, Subscale Combustion System and Task 3.3, On Line Alkali Monitoring. The additional workscope not directly related to the slagging combustor testing, Task 12, Generic Turbine Design Studies and Task 1.3, System Scoping and Feasibility Studies for Advanced Turbines Systems, was also being performed during this reporting period.

Task 3.1 involves the design, fabrication, testing and evaluation of a 12 MMBtu/hr slagging combustor for utility gas turbine applications. Task 3.3 required the monitoring of alkali levels in the combustor product gases using the Fiber Optic Alkali Monitor developed under DOE contract with the University of Iowa Ames Laboratory. The Generic Turbine Design studies, Task 12, is to produce a conceptual design of a gas turbine power plant suitable for burning coal-derived fuels. Task 1.3 involves the conceptual design of a high efficiency, advanced natural gas-fired turbine cycle that can be converted to operate on coal-derived fuels after the turn of the century. Also included in Task 1.3 is a program development plan to accomplish a demonstration plant in the 1998-2000 time frame.

Although the cooperative agreement between Westinghouse, NSP and Textron to test NSP subbituminous coals with the slagging combustor was independent of this contract, the testing itself was germane to the operating performance of the combustor and the goals of this program. Therefore, the results of the NSP coal testing are presented in this report.

2.2 PROGRAM OBJECTIVES

The primary objective of this work was to verify the feasibility of a direct coal-fueled combustion system for combustion turbine applications. This has been accomplished by the design, fabrication, testing and operation of a subscale development-type coal combustor. Because this was a complete departure from present-day combustion turbine combustors and fuels, it was considered necessary to make a thorough evaluation of this design, and its operation in subscale, before applying it in commercial combustion turbine power systems.

Another objective was to keep fuel costs acceptably low by burning raw or moderately cleaned coal, as is normal utility practice. Both bituminous and subbituminous coals have been tested. Coal grinding has been, and, is to be, consistent with that considered practical and economical for electric utility utilization. The coal was burned exclusively as dried PC during the 1988-1989 reporting period and then burned as CWM during much of the 1989-1990 period. Testing revealed PC to be the preferred fuel both from performance and economic standpoints. Therefore, the slagging combustor system was reconfigured to burn PC for the balance of the program.

The ultimate goal for the coal combustion system was to attain efficient combustion of the coal, and simultaneously to satisfy all of the environmental emission regulations (e.g., EPA's New Source Performance Standards [NSPS] for coal-fired steam generators) and combustion turbine power system requirements.

Objectives

1. Attain high efficiency with emphasis on effective fuel utilization (burn-out) and low pressure and heat losses.
2. Achieve stable and reliable operation.
3. Control and limit NO_x formation in the gas to meet or better NSPS.
4. Remove sulfur to meet or better NSPS.
5. Demonstrate efficient removal of slag and all particulates in the gas with the ultimate objective to meet or better NSPS.
6. Retain alkalies in ash/slag removed from the combustor.

Specific Performance Goals

1. Demonstrate self-sustaining coal combustion at the thermal design rating of 12 MMBtu/hr.
2. Burn utility grade bituminous and subbituminous coal, both in the pulverized form, and as coal-water mixture.
3. Produce a lean-zone exit gas stream having an average temperature of at least 1850°F, and having a uniformity such that the exit temperature pattern factor will be 20 percent or less.
4. Achieve combustion efficiency of greater than 98 percent.
5. Demonstrate stable and reliable operation and acceptable refractory performance.
6. Show that heat and pressure losses are acceptable; (interim values of 8 and 7 percent, respectively are being used in Task 8.0, for example).
7. Operate with NO_x emissions of less than the NSPS limit of 0.6 lb/MMBtu.
8. Limit SO_x per the NSPS to a maximum of 1.2 lb/MMBtu, where 90 percent reduction is required for SO_x greater than 0.6 lb/MMBtu, and 70 percent reduction is required for SO_x less than 0.6 lb/MMBtu.

2.3 COMBUSTOR CONCEPT

The slagging combustor is a modular unit with three combustor stages and a slag/sorbent removal train of several stages. Figure 2-1 is a schematic representation of these stages. (It should be noted that the cyclone and third stage of the subscale combustor is water-cooled, instead of air-cooled as shown in this figure.) The stages are:

First Combustor Stage	- All the coal, the sorbent, and about one-third of the gas turbine compressor discharge air enter this stage. Rich burning takes place; hot, fuel-rich gases and melted slag and spent sorbent exit downward, towards Stage 2.
Second Combustor Stage	- Here the melted solids are separated from the hot, fuel-rich gases by inertia, in either an impact separator, or in a cyclone separator, immediately downstream. The hot gases go to Combustor Stage 3, while

Figure 2-1. Schematic of Slagging Combustor Concept, Including Slag and Spent Sorbent Removal Subsystem

the melted solids flow by gravity out through a tap hole into a water spray, and on, into a water collection vat.

Third Combustor Stage

- Here the hot, fuel-rich gases from Stage 2, are mixed with the balance of the gas turbine compressor discharge air. The gases burn, but at such a lean fuel-to-air ratio that little NO_x is formed. Relatively clean, hot gas flows from this stage to the expander, where the shaft work is extracted.

First Slag Removal Stage	- This is where the slag is quenched and crushed. A water spray cools the molten slag, causing it to solidify and fracture. The resulting fragments are further reduced in size by underwater roller-crushers.
Second Slag Removal Stage	- The slag and spent sorbent particles are conveyed under water, away from the combustor, to a point where they are slurried by an impeller.
Third Slag Removal Stage	- Here the slag/sorbent slurry is let down to 1 atmosphere pressure through a valve and dewatered. The water is returned to the system, and the dry particles, which are stable, are conveyed to a landfill.

Test Combustor Concept

Figure 2-2 shows the subscale slagging combustor as it was originally configured, in a simplified section view. Although there was no slag/sorbent removal system, the first, second, and third combustion modules were all included.

The first stage is the primary combustion zone. Coal and preheated air enter the primary zone coaxially through four injection nozzles which are equally spaced around the combustion chamber. This coaxial injection promotes intense air/coal mixing and rapid particle heat-up/devolatilization, which minimizes carbon burnout time.

The four incoming coal-air jets converge at the combustor center line and form one vertical jet which impacts the combustor dome. This forms a toroidal vortex which provides the mechanisms for flame stabilization and centrifugal separation of larger ash/slag particles. This separated ash/slag forms a stable flowing layer on the combustor walls. The vertical geometry of this stage allows gravity to assist in the removal of the molten slag.

Fuel-rich conditions in this stage inhibit NO_x formation from fuel-bound nitrogen. It also provides the necessary reducing conditions for removal and capture of sulfur. The sulfur sorbent, limestone, dolomite, or one of various iron oxides is counter-flow injected into the downstream end of the primary zone. The first stage was designed for a coal particle residence time of about 100 ms (for 75-micron sized particles).

Figure 2-2. Slagging Combustor Original Configuration

The second stage is an efficient impact separator which is closely coupled to the first stage. The impact separator removes particulates carried over with the gas from the primary zone, whether they are sorbent or fine particles of ash. The impact separator alone did not demonstrate the ability to satisfy the turbine particulate loading requirements. Additional gas cleanup to meet NSPS particulate standards was provided by adding a slagging cyclone separator in series with the impact separator (Section 3.3).

The third stage is used to complete combustion and to temper the products to meet turbine inlet requirements. The rapid mixing between gases coming from the second stage and secondary air insures that the peak gas temperatures and hence thermal NO_x formation is minimized. This stage is designed based on conventional gas turbine combustor practice.

2.4 DEVELOPMENT PROGRESS AND PLAN

Initial development of the direct coal-fired combustion turbine combined cycle power plant revolved around Task 3.1, Subscale Combustor Development. It then was to have moved to Task 7.0, Subscale Stationary Cascade Test, and next to Optional Task 6.0, Utility System Prototype Combustor Evaluation. In parallel

with these major tasks, shorter tasks were undertaken to supply particular data needs. Below are descriptions of the major task work done during this period.

Task 3.1, Subscale Combustor Development. During this reporting period the subscale combustor development has been devoted to continued evaluation of the slagging cyclone and modified impact separator that was added in the fall of 1990. These evaluations have been done with regards to particulate and sulfur removal efficiency. Resolving the char carry-over problem that developed after modification of the system, became the objective of the CR1-X Series of tests.

Task 3.3 On-Line Alkali Monitoring. The objective of this task was to install and operate the alkali monitoring probe developed by the Ames Laboratory of Iowa State University. The probe was fabricated and installed at the Textron Haverhill facility during the latter part of 1991 and early 1992. The probe was actually operated by the personnel from the Ames Laboratory while testing was being performed on the Northern States Power coals. Although the probe was used only during one test sequence and minor problems were experienced, there were indications by the Ames probe that the vapor alkali had an upper limit of 100 ppb. These indications were corroborated by previous test alkali measurements made by the Westinghouse alkali probe.

Task 8.0 Update of Reference System Definition. In a previous DOE program (Reference 2), studies showed that the lowest-cost environmentally acceptable method of generating electricity from coal was a coal-fired combustion turbine combined cycle plant employing on-site coal preparation. With the passage of several years time, it was felt necessary to update these economic studies, to maintain their validity. This was done during the previous reporting period and the final report was submitted to DOE in September 1991.

Task 10.0 Slag Tap. The objective of this effort was to design and procure slag tapping and improved impact separation components to address three concerns: (1) Testing times were limited, due to a buildup of molten slag and spent sorbent in the bottom of the impact separator vessel; (2) The impact separator had experienced heat loss caused by poor refractory retention on the convex surface around the inlet nozzle and, by over-sizing of the slag retention zone; (3) Slag entrainment on the walls of the impact separator vessel in the vicinity of the gas exit port has caused approximately 20 percent of the collected slag to flow to the lean-zone, out of the impact separator. In the fall of 1990, an improved impact separator including real-time slag tapping and a slagging cyclone were installed and tested. Continued testing evaluation of these components occurred during this reporting period.

SUBSCALE SLAGGING COMBUSTOR: TEST APPARATUS, PLAN, AND METHOD

3.1 TEST FACILITIES AND APPARATUS

All combustion tests during this reporting period were conducted at the Textron facility located in Haverhill, MA (Reference 3). This facility supplies unvitiated combustion air to the burner test rig at up to 120 psia and 7 lb/sec, and at a temperature of up to 800°F.

3.2 FUEL FEED SYSTEMS

During the initial year of subscale slagging combustor testing, and also in the first, three tests of the 1989-1990 reporting period, PC was utilized as fuel. This fuel was fed to the combustor from a 10,000 lb capacity, conical-bottom tank. Coal is carried from the tank to the combustor in a stream of high velocity air. PC loadings in the carrier air are high, with the coal to air mass ratio being as high as eight. The feed rate of coal is controlled by the flow rate of transport air, and the difference in pressure between the tank and the feed line.

The coal feed rate is measured by monitoring the weight change of the coal feed tank using load cells which support the tank. Coal feed to the combustor has been through four injectors, equally spaced around the primary zone. A fluid dynamic flow splitter near the combustor divides the carrier gas, with its entrained coal, to supply equal fuel streams to each injector.

For the balance of the 1989-1990 reporting period, the fuel was fed as CWM. The CWM was stored, heated, and continually recirculated, in a 500 gallon tank located inside the test building. A pumping, metering, and control system for the CWM was built up on a skid, and located next to the test rig. A progressive cavity pump was used for the CWM. The same four injection stations in the primary zone were used for CWM as PC, and all the primary combustion air was introduced coaxially around the CWM injection nozzles. High pressure compressed air from a storage trailer outside the building was used to operate the four air-atomizing CWM nozzles.

The slagging combustor system was retrofitted in the summer and early fall of 1990 (Reference 5), to again burn pulverized coal for the balance of subscale combustor testing. The change over was done at the same time the slagging cyclone was added to the system.

3.3 COMBUSTOR TEST RIG

The combustor test rig configuration used during this reporting period for char quantification and sulfur reduction tests is shown schematically in Figure 3-1. This is the same configuration as was used in test CR1-1 of June 1991 to establish the baseline data for the char production problem. In the upper left of the figure is the dome-topped primary zone. Air and PC are injected upward into this primary zone through four angled fuel injectors, equally spaced around the zone. For simplicity, only one is shown in the figure. When needed, pulverized sorbent, with carrier air, is also injected into the primary zone. Four smaller injectors handle this task.

Rich combustion occurs in the primary zone, and melted coal ash (slag) and hot, fuel-rich gases exit downward out of the zone through the small diameter nozzle shown. The nozzle leads the rich gases into the curved body impact separator with slag tap, shown at the lower left. A sudden change of

Figure 3-1. Schematic of Subscale Slagging Combustor Test Rig With Real-Time Slag-Tapping Capability and Slagging Cyclone

direction, and gravity, separate slag and particles. Leaving the liquid and solid matter behind, the cleaned, hot fuel-rich gases move out of the top right-hand side of the impact separator. The primary zone, the impact separator, the internals of the impact separator, and the connecting passages are water-cooled, high-pressure, steel vessels, lined with refractory.

Having left the impact separator, the hot gases pass to the right and enter into the slagging cyclone separator where the particulate emissions are further reduced. The cyclone separator is water-cooled and refractory-lined, so that the slag and sorbent particles it collects are liquid, and flow to the bottom. Cleaned, very hot, fuel-rich gases then pass out the center tube and directly into the lean-burn zone. The lean-burn zone is a cylindrical water-cooled section having 32 inclined air jet inlets. The first 16 of these bring combustion air in, to oxidize the fuel-rich gases which burn spontaneously. The second 16 inlet jets admit dilution air, which drops the burning gases to a temperature acceptable to a turbine, (1850°F to 2000°F).

Following the lean-burn zone, the hot gases pass through a water-cooled instrumentation section, and then through a water-cooled orifice plate which drops them to near atmospheric pressure. Emissions, pressure, and temperature profile are detected in the instrumentation section. Following the orifice plate, the gases pass through a water spray, and to the exhaust.

Figure 3-2. Schematic of Subscale Slagging Combustor Test Rig as Configured for Char Quantification Tests CR1-2 through CR1-4

Figure 3-2 shows a schematic of the subscale combustor rig as configured for char quantification tests CR1-2 to CR1-4. For tests CR1-2 to CR1-4 the curved body impact separator and slag tap were removed and the centerbody impact separator with slag bath were installed. This was done in order to recheck the relative influence of the curved body impact separator and slag tap on char production. The results of these tests qualitatively suggested that the curved body impact separator and slag tap bath components didn't influence char production significantly.

As described in Reference 4, the curved body impact separator was designed to minimize slag droplet re-entrainment, to better control the bucket wall slag flow and also reduce heat losses. The curved body impact separator also includes a slag tap and is illustrated schematically in Figure 3-3. Separated slag flows out of the bucket via the centrally located slag tap hole and is collected in a water bath below the tap. The exhaust housing has been re-designed to reduce the exit gas velocities and also to reduce heat losses by reducing surface area. Also, with the slag now being collected in a separate slag vessel, the slag bucket itself has been reduced in size considerably, again reducing heat losses.

The problem of slag flow out of the bucket exit has been addressed by both re-contouring the exit duct and by re-designing the centerbody to be asymmetric. The intention here is to direct the high momentum inlet jet away

Figure 3-3. Curved Body Impact Separator with Slag Tap and Collection Vessel

from the bucket exit. Inertial separation of slag will take place both on the asymmetric centerbody and on the bucket walls in the region of jet impingement. By intent, the slag is separated onto the wall opposite the exit, and the upper part of the asymmetric centerbody acts as a shield to prevent slag being directed towards the exit. The strong re-circulation in the vicinity of the slag tap will also help to keep the slag tap clear by increasing the heat flux in that region.

3.4 GAS SAMPLING SYSTEM

Gas sampling was done both to obtain discrete samples for off-line analysis, and continuously for on-line instruments. Either a heated sample line or a drier was employed, to avoid loss of SO_2 due to moisture condensation. A hot sample was fed to the SO_2 , H_2S , and NO_x analyzers. For the CO , CO_2 and O_2 analyzers, there was a cold trap in the line just before the instruments. Ethylene glycol, cooled by dry ice, was used in the cold trap to drop out moisture upstream of the instruments. The on-line gas analysis instruments were:

<u>Gas</u>	<u>Analysis Instrument</u>
CO	Beckman Model 868-18 Non-Dispersive Infrared
CO_2	Beckman Model 868-23 Non-Dispersive Infrared
SO_2	Thermo Electron Model 40 Pulsed Fluorescence
O_2	Beckman Model 755 Paramagnetic
NO/NO_x	Thermo Electron Model 10 Chemiluminescence
H_2S	Thermo Electron Model 340 H_2S Converter
H_2S	Western Research Model 721-A U-V Absorption $\text{H}_2\text{S}/\text{SO}_2$ Analyzer

In addition to continuous gas sampling using the above instrumentation, rapid samples were taken during the combustor tests for off-line analysis using a Perkin-Elmer Sigma II gas chromatograph.

3.5 SORBENT FEED SYSTEM

Sorbent was carried into the combustor by streams of air, densely packed with particles, in response to the pressure difference between the sorbent hopper and the combustor. A conical-bottom feed tank, fluid-dynamic flow splitter, and a set of four small injectors for the combustor are employed. This system is satisfactory for large sorbent flows. A different system was needed to

handle small flows, and was installed during the last reporting period. It utilizes a vibrating horizontal louvered plate to meter the sorbent, rather than air pressure differential.

Figure 3-4 shows a sketch of the vibrating louver system used to improve sorbent feed. A pressure shell houses the feeder, and attaches to the bottom of the conical sorbent feed hopper. The key feature of the feeder is a set of variable speed vibrating louvers which meter the solid material into a sheet metal cone. This cone guides the sorbent into a carrier line. Feeder speed is determined by a 4-20 mA signal from the combustor programmable logic controller.

Figure 3-4. Sketch of Vibrating Louver Apparatus Added to Sorbent Feed System

3.6 DESCRIPTION OF COMBUSTOR CONFIGURATION TESTED

At the start of this testing period, the slagging combustors was configured as seen in Figure 3-1. Table 3-1 shows hardware data for this subscale slagging combustor configuration.

During early July 1991, the combustor test rig was reconfigured to include the centerbody impact separator as discussed in Section 3.3 and shown in

Table 3-1. Combustor Configuration Employed for All Tests During the Period of August 30, 1991 to June 30, 1992.

Primary Zone	Diameter:	16.75 in.
	Length/Diameter:	1.25/1.50
	Injector Horizontal Angle:	55 deg.
	Injector Vertical Angle:	0 deg.
	Nominal Injection Velocity:	200 ft/s
Impact Separator	Type:	Curved Body
	Radius of Curvature:	19.0 in.
	Arc Length:	17.6 in.
	Width:	12.0 in.
	Jet/Impactor-Plate Separation:	6.0 in.
	Nozzle Diameter:	3.5 in.
	Nominal Inlet Velocity:	450 ft/s
Slag Tap/Bath	Height:	48.0 in.
	Diameter:	24.0 in.
	Tap Diameter:	4.5 in.
Slagging Cyclone	Nominal Inlet Velocity:	120 ft/s
	Overall Height:	85.0 in.
	Maximum Diameter (ID):	14.5 in.
	Slag Bucket Height:	17.2 in.
Lean-Burn Zone	No. of Secondary Injectors:	16
	Secondary Injector Diameter:	1.02 in.
	Secondary Injection Velocity:	260 ft/s
	No. of Dilution Injectors:	16
	Dilution Injector Diameter:	1.02 in.
	Dilution Injection Velocity:	260 ft/s

Table 3-2. Centerbody Impact Separator Installed for Tests CR1-2 Through CR1-4, Test Period July 10, 1991 to August 21, 1991.

Impact Separator	Type:	Centerbody
	Nozzle Diameter:	3.5 in.
	Nominal Inlet Velocity:	450 ft/s
	Jet/Impactor Plate Spacing:	4.8 in.

Figure 3-2. The data for the centerbody impact separator is shown in Table 3-2, while the other components remained as shown in Table 3-1.

3.7 COALS TESTED

Two coals were used during this reporting period for the slagging combustor tests. They were a low sulfur bituminous coal, Dorchester, from Virginia, and a high sulfur eastern bituminous coal, Pittsburgh No. 8. Both were used as utility grind, with the particle size such that 95% would pass through a 200 mesh screen. Table 3-3 shows the ultimate and proximate analyses, along with the ash fusion data (which is of special concern in a slagging combustor), for the two coals used. Table 3-4 provides the ash analysis for each coal.

Due to the char carry-over phenomenon that appeared after the slagging cyclone was added to the system, and the subsequent investigation into the coal that had been being used for the combustor testing, two fresh loads of Dorchester and Pittsburgh No. 8 coal were ordered. The last two combustor tests conducted during the previous reporting and all tests this period utilized these fresh loads of coal but proved not to be the cause of the char carry-over, even though the chemical compositions of each of the older, respective coal types had shown some degradation over a couple years while being stored in barrels.

Table 3-3. Ultimate and Proximate Analyses of Coals Tested During This Reporting Period - (Dry Basis)

	<u>COAL TYPE</u>	
	EASTERN BITUMINOUS (DORCHESTER, VIRGINIA)	EASTERN BITUMINOUS (PITTSBURGH, NO. 8)
<u>PERCENT</u>		
ASH	6.49	7.71
VOLATILE MATTER	34.02	38.86
FIXED CARBON	59.49	53.43
	<u>100.00</u>	<u>100.00</u>
SULFUR	1.04	2.39
CHLORINE	0.04	0.14
CARBON	80.80	77.89
HYDROGEN	5.37	5.29
NITROGEN	1.43	1.36
OXYGEN, (BY DIFFERENCE)	4.83	5.22
ASH	6.49	7.71
HEATING VALUE, BTU/LB	14,390	14,031
ASH FREE HTG. VAL., BTU/LB	15,389	15,203
PERCENT MOISTURE IN THE AS-RECEIVED CONDITION	6.13	1.49

Table 3-3. (Cont'd.)

ASH FUSION TEMPERATURES IN REDUCING ATMOSPHERE FOR COALS
TESTED DURING THIS REPORTING PERIOD, (°F):

INITIAL DEFORMATION	2183	1900
SOFTENING	2305	2080
HEMISPHERICAL DROP FORMATION	2379	2140
BECOMES FLUID	2466	2210
VISCOSITY = 250	2340	2295

RELATED DATA

BASE ACID RATIO	0.46	0.41
WATER SOLUBLE SODIUM (PPM)	110.00	200.00
WATER SOLUBLE POTASSIUM (PPM)	52.50	22.80
CALCIUM (CALCULATED)	-	-
ASH BASIS	3.14	4.68

Table 3-4. Ash Analysis for Coals Tested During This Reporting
Period - (Dry Basis)

CONSTITUENT	COAL TYPE	
	EASTERN BITUMINOUS (DORCHESTER, VIRGINIA)	EASTERN BITUMINOUS (PITTSBURGH NO. 8)
SiO ₂	44.78	39.40
Al ₂ O ₃	20.89	21.80
Fe ₂ O ₃	22.65	22.79
CaO	4.40	6.55
MgO	1.20	2.10
Na ₂ O	0.51	1.45
K ₂ O	1.85	1.51
TiO ₂	1.51	1.27
P ₂ O ₅	0.52	0.40
SO ₃	1.54	--
Undetermined	0.15	2.73

3.8 SORBENTS TESTED

Table 3-5 shows the sorbents that were used with the various tests conducted during this reporting period. Calcia-based and iron-oxide based sorbent mixtures were evaluated. Sorbent was injected into the system as a dry powder through separate sorbent injectors with Cabosil being added during the last two tests, SL2-5 and SL2-6, to improve flow.

Table 3-5. Sorbents Evaluated During This Reporting Period

<u>SORBENT TYPE</u>	<u>TEST RUNS (NO.)</u>
Limestone (CaCO_3) and Hematite (Fe_2O_3) Mixture 1:1 (by wgt)	SL2-1
Limestone (CaCO_3) and Hematite (Fe_2O_3) Mixture 2:1 (by wgt)	SL2-3 SL2-4
Limestone (CaCO_3) and Hematite (Fe_2O_3) Mixture 4:1 (by wgt), Cabosil added to improve flow.	SL2-5 SL2-6

3.9 NOMINAL TEST CONDITIONS

The nominal Test conditions in the subscale slagging combustor were set to essentially the same values for each Test during this reporting period, and are summarized in Table 3-6.

Table 3-6. Nominal Test Conditions

Combustion Chamber Pressure, psia	80 to 87
Combustion Air Temperature, °F	600 to 660
Primary Air Mass Flow Rate, lb/s	1.9 to 2.3
Secondary Air Mass Flow Rate, lb/s	2.0 to 2.3
Dilution Air Mass Flow Rate, lb/s	2.0 to 2.4
Pulverized Coal Mass Flow Rate, lb/s	0.2 to 0.3

SUBSCALE SLAGGING COMBUSTOR: TEST RESULTS AND DISCUSSION

During this reporting period, July 1, 1991 through June 30, 1992, 12 tests were conducted with the subscale slagging combustor.

At the beginning of the reporting period, the slagging combustor system was in the process of being disassembled for modification. To determine if the curved body impact separator and slag tap were having an influence on char production, the system was reconfigured with the older center body impact separator with its integral slag bath, as shown in Figure 3-2. The system remained in this configuration for three test runs, CR1-2 through CR1-4. At the conclusion of these test runs the system was restored to the configuration as seen in Figure 3-1, which again included the slagging combustor with the curved body impact separator and slag tap. The system remained in this configuration through the end of testing.

The primary and secondary objectives of the first five (5) tests of this period were first, to quantify the char being produced in the slagging combustor system and secondly to quantify the slag separation efficiency of the curved body impact separator and acquire more information on the operation of the slagging cyclone separator. Specific details of the char quantification tests are discussed in Section 4.1. A second series of seven (7) tests was then conducted. This series of tests also had two objectives: optimization of sorbent based sulfur reduction and evaluation of system modifications made for eliminating the char problem. These tests are discussed in detail in Section 4.2. All the tests conducted during this reporting period, along with brief remarks, are listed in Table 4-1.

4.1 CHAR QUANTIFICATION TESTS

During the first three months of this reporting period five char quantification tests (CR1-2 through CR1-6) were conducted. Test CR1-1, which was reported on in the September 1991 Annual Technical Progress Report, will again be detailed in this report for the sake of providing continuity in reporting on the CR1-X series of tests.

Table 4-1. Chronology of Testing During the Report Period

Designation, Date, and Time Burning 100% Coal:	Coal:	Sorbent:	Remarks:
Test CR1-2 7/10/91 44 Min.	Dorchester, VA Pulverized Coal 1.04% S, (dry basis); 95% through 200 Mesh	No Sorbent	Center Body Impact Separator Reinstalled. $\phi = 1.2$, Char Production $\approx 2.5\%$ (wgt) of Coal
Test CR1-3 8/5/91 47 Min.	Dorchester, VA Pulverized Coal 1.04% S, (dry basis); 95% through 200 Mesh	No Sorbent	Center Body Impact Separator Installed. $\phi = 1.2$, Char Production $\approx 2.5\%$ (wgt.) of Coal.
Test CR1-4 8/21/91 49 min.	Dorchester, VA Pulverized Coal 1.04% S, (dry basis); 95% through 200 Mesh	No Sorbent	Center Body Impact Separator Installed. $\phi = 1/2$, Char Production $\approx 2.5\%$ (wgt.) of Coal.
Test CR1-5 8/30/91 51 Min.	Dorchester, VA Pulverized Coal 1.04 S, (dry basis); 95% through 200 Mesh	No Sorbent	Curved Body Impact Separator Reinstalled. $\phi = 1.2$, Char Production $\approx 2\%$ (wgt.) of Coal.
Test CR1-6 9/9/91 62 Min.	Dorchester, VA Pulverized Coal 1.04 S, (dry basis); 95% through 200 Mesh	No Sorbent	Curved Body Impact Separator Installed $\phi = 1.2$, Char Production $\approx 2\%$ (wgt.) of Coal.
Test SL2-1 9/19/91 61 Min.	Pittsburgh No. 8 Pulverized Coal 2.4% S, (dry basis); 95% through 200 Mesh	Limestone Magnetite 1:1 Mix	Sulfur Capture 30 - 50% Exit to Combustor. Total Sulfur Capture Undetermined.
Test SL2-2 9/26/91 N/A	Pittsburgh No. 8 Pulverized Coal 2.4% S, (dry basis); 95% through 200 Mesh	No Sorbent	Sulfur Capture/ Char Reduction Test. Coal Delivery System Modified. Air compressor Inadequate for Test. Test Aborted.

Table 4-1. (Cont'd.)

Designation, Date, and Time Burning 100% Coal:	Coal:	Sorbent:	Remarks:
Test SL2-2A 10/4/91 56 Min.	Pittsburgh No. 8 Pulverized Coal 2.4% S, (dry basis); 95% through 200 Mesh	No Sorbent	Continuation of Test SL2-2. ϕ = 1.0 to 1.3. Difficulties Resulted in Test Being Dedicated to Adjusting Operating Parameters.
Test SL2-3 10/18/91 81 Min.	Pittsburgh No. 8 Pulverized Coal 2.4% S, (dry basis); 95% through 200 Mesh	Limestone/ Magnetite 2:1 Mix.	Char Problem Resolved with Increased Coal Carrier Velocities. ϕ = 1.1 to 1.3.
Test SL2-4 11/12/91 82 Min.	Pittsburgh No. 8 Pulverized Coal 2.4% S, (dry basis); 95% through 200 Mesh	Limestone/ Magnetite 2:1 Mix.	Sulfur Capture 30% Max. ϕ = 1.1 to 1.2.
Test SL2-5 11/21/91 73 Min.	Pittsburgh No. 8 Pulverized Coal 2.4% S, (dry basis); 95% through 200 Mesh	Limestone/ Magnetite 4:1 Mix. Cabosil Added to Improve Flow.	Sulfur Capture 30% Max. ϕ = 1.1 to 1.2.
Test SL2-6 11/27/91 56 Min.	Pittsburgh No. 8 Pulverized Coal 2.4% S, (dry basis); 95% through 200 Mesh	Limestone/ Magnetite 4:1 Mix. Cabosil Added to Improve Flow.	ϕ = 1.0 to 1.5 : Sulfur Capture 40% when 1.1 < ϕ < 1.2.

Test CR1-1

This was the first test in a series of six tests to investigate the char problem. Test CR1-1, performed in June 1991, was conducted with a fully configured system, i.e., the curved body impact separator, slag tap bath, and slagging cyclone were installed. The CR1-1 data constituted a baseline for the char production problem. New Pittsburgh No. 8 coal was burned during the previous test and a considerable amount of char was produced. The amount of char produced was not entirely out of line with what had been observed since the installation of the slagging cyclone. It was decided to test the char behavior of the new Dorchester seam coal during this test, rather than perform a repeat of the conditions selected for the previous test. No sorbent was injected during this test. During this test 657 lbs of new Dorchester seam coal were burned. The coal combustion portion of this run lasted 50 minutes and the equivalence ratio was held nearly constant at $\phi = 1.2$. Overall, no aberrant behavior accompanied this run.

The particle sampling probe was operated in a slightly different manner in this test relative to prior tests. A nitrogen flow was driven through the probe into the combustor exhaust duct until the desired equivalence ratio was achieved. Before the coal ran-out and the system was shutdown, the flow to the probe filter was valved off. The amount of coal burned during the time the probe was sampling was recorded. This procedure was defined in order to ensure that elevated particle loading that may occur during startup or shutdown is not influencing particle sampling. During particle sampling 426 lbs of coal were burned. The change in particle filter weight implied that 4.3 lbs of char were exhausted from the system (examination of the filter suggested that most of the material collected was char). These results indicate that 1.0% (4.3 lbs-char/426 lbs-coal) of coal passed through the system unburned. This is roughly the same as measured in previous tests. The material in the cyclone slag bucket was separated into slag (8.3 lbs) and char (21.7 lbs). The amount of unburned, non-slag material collected by the cyclone turned out to be 3.3% of the total coal burned.

Test CR1-2

CR1-2 was the second char quantification test conducted. The system was reconfigured for this run. The curved body impact separator and slag tap bath were removed and the centerbody impact separator was installed. During this test, 512 pounds of fresh Dorchester coal were burned. The length of the coal combustion portion of the run was 44 minutes. The equivalence ratio was nominally $\phi = 1.2$.

The primary reason for installing the centerbody impact separator was to verify that the curved body impact separator and slag tap bath components were not causing the char production problem. It was thought that the latter components could have been causing a flow oscillation to feed back into the primary zone which may have been causing the coal injection jets to oscillate,

resulting in coal issued directly to the exit of the primary zone. Similar tests were conducted earlier in 1991, but were repeated for two reasons. The first reason related to the operation of the downstream particulate sampling probe, which has been changed. The probe now is not being back purged until steady coal combustion is achieved. The purge flow is then stopped and exhaust gases are allowed to flow through it. The flow through the probe is stopped just before coal combustion is halted. The amount of coal burned during sampling and sampling elapse time are recorded. This mode of operation was adopted in order to make certain that startup and shutdown transients did not load the particle filter with significant amounts of particulate matter. The former mode of operation had allowed the particulate probe to sample all of the time. The second reason was that a systematic approach towards identifying the cause of char carryover was adopted.

It was found that determining the collection efficiency of the curved body impact separator via component weight differences and collected or removed slag was not very accurate. The curved body impact separator configuration required too many weights to be measured. The collection efficiency of the curved body impact separator can be deduced with a greater degree of accuracy by deriving it from total collection efficiency and slagging cyclone efficiency. Total collection efficiency was determined from particle collection measurements via the downstream particle collection probe. The collection efficiency of the slagging cyclone is best derived from overall collection efficiency and the efficiency of the centerbody impact separator. The collection efficiency of the centerbody impact separator was determined via the difference in centerbody impact separator housing weight, as measured before and after a test run. Thus, a secondary reason for installing the centerbody impact separator was to verify the separation efficiency of the centerbody impact separator and the slagging cyclone separator.

The weight change in the centerbody impact separator housing for test CR1-2 was 33 lbs. The total coal burned was 612 lbs, which contained 38 lbs of ash. The measured collection efficiency of the centerbody impact separator was, therefore, 87%. This was consistent with previous results. The efficiency of the slagging cyclone could not be derived because the overall collection efficiency measurement failed. The overall collection efficiency is determined via the weight increase of the particle collection problem filter, which broke sometime during the test.

The total amount of slag/char collected by the slagging cyclone bucket was 23 lbs for test CR1-2. This material was sent out to have it separated into slag and char. Once separated, the weight of the char was used to quantify the char production for the centerbody impact separator, slagging cyclone configuration. These results are discussed under Section 4.1.1.

By applying proximate analysis to the material collected by the particle collection probe, the ash/carbon weight ratio for material exhausted from the system can be determined. This, together with the total amount of ash and

char exhausted from the system, would give the total amount of unburned coal passing all the way through the system. The total amount exhausted is also determined from particle collection probe filter weight increase measurements. The exhausted amount of unburned coal plus the char collected in the cyclone bucket will give the total amount of unburned coal, thus carbon conversion and quantification of the char problem.

Test CR1-3

CR1-3 was the third char quantification test conducted. The system was operated with the centerbody impact separator installed. A new diagnostic was added to the system which provided a real-time indication of exhaust gas particle loading (see Helium-Neon Laser Diagnostic Addition, Section 4.1.2). During this test run, 658.5 lbs of Dorchester seam coal were burned. The coal burned during this run was from the first new shipment received in June 1991. The duration of the coal combustion segment of this run lasted 47 minutes. This test run was performed operating at an equivalence ratio of $\phi = 1.2$. No sorbent was injected during this run. Weights of the slag collected in the impact separator and cyclone were acquired. The slag/char mixture in the cyclone bucket was separated and weights for each was obtained. Slag samples from these components were sent out for elemental analysis, so that the amount of char entrained in the slag and collected by the impact separator housing and slagging cyclone could be determined.

During this test a hole formed in the particle probe filter. It was not possible to directly determine the amount of char and ash exhausted from the system. Using the He-Ne extinction diagnostic data, the elemental analysis and particle filter results from other test runs, a reasonably accurate estimate of the exhausted char and ash for this run was possible. The char production results are discussed in Section 4.1.1 under Char Production.

The secondary goal of the char quantification test sequence was to determine the slag removal efficiencies of the impact separators and the slagging cyclone. Since the amounts of slag collected by the centerbody impact separator and slagging cyclone are available from the char production analysis, it was possible to derive preliminary efficiency results. The preliminary slag collection efficiency results are discussed under Section 4.1.1.

Test CR1-4

CR1-4 was the fourth char quantification test conducted. The system was operated with the centerbody impact separator installed. The new He-Ne extinction diagnostic was used during this run. During this test run, 684.5 lbs of new Dorchester seam coal were burned. The duration of the coal combustion segment of this run lasted 49 minutes. This test run was performed operating at an equivalence ratio of $\phi = 1.2$. No sorbent was injected

during this run. This test was the same as CR1-3 and the same types of data collected and associated procedures for this test were used as for test CR1-3.

From an operational point of view test CR1-4 was not as smooth a run as CR1-3. Two difficulties were encountered, one occurring at the start of the run, the other detected after the run. When coal combustion was attempted at the beginning of CR1-4, no coal combustion took place when the coal flow was started. The system was shutdown and possible causes investigated. It was found that a leak had opened up at the junction of the coal carrier line and coal storage tank. A very small amount of pulverized coal was discharged onto the floor. The seal at this junction had developed a small leak and was responsible for the failed coal combustion attempt. Once fixed, the remainder of the run proceeded smoothly. After completing this run, it was discovered that one of the particle collection probe filters that had failed during the previous two test runs had failed again (i.e., the ceramic filter had developed a hole). The hole developed because a 1/8" diameter bar applied a small amount of pressure on one end of the filter that held the filter in its seat. Apparently there was enough motion, either from the gas flow through the filter housing or from mechanical vibration, to cause this bar to chafe the end of the ceramic filter, eventually causing breakthrough. The housing for this filter was reworked to eliminate this problem.

Test CR1-5

Test CR1-5 was the fifth char quantification test conducted. The system was reconfigured by replacing the centerbody impact separator with the curved body impact separator and slag tap/bath components. During this test run 711.5 lbs of new Dorchester seam coal were burned. The duration of the coal combustion segment of this run lasted 51 minutes. This test run was performed operating at an equivalence ratio of $\phi = 1.2$. No sorbent was injected.

The main purposes of this test were the same as for test CR1-3. The only difference being that data was acquired to evaluate the behavior of the new system configuration. Specifically, the purpose of this test was to:

1) acquire data to quantify combustor char production with the curved body separator, slag/tap bath in place and 2) acquire data to quantify the slag collection efficiencies of the curved body impact separator, slag tap/bath, and slagging cyclone. These test results are discussed under the Section 4.1.1, titled Results of Char Quantification Tests CR1-1 through CR1-6.

An additional goal was added for test run CR1-5. It was noticed after the previous run (CR1-4) that some of the hoses from the coal splitter to the four primary zone coal/air injectors had different end-fittings than the others. Further inspection revealed that two of the hoses had end-fittings that had a cross-sectional area twice that of the end-fittings on the other two hoses. A factor of two area difference could produce an increased flow of coal to two of the coal/air injectors and reduced flow to the other two. This would cause half of the dome region of the combustor to run extremely fuel-rich, thus

producing char, while the other half of the dome would run fuel-lean. These hoses were modified so that all end fittings, as well as their lengths, were all the same. The exits of the coal delivery tubes inside the coal/air injectors were moved halfway up the air passages of the coal/air injectors at this time. Before this, the coal delivery tubes were discharging coal into the primary air at the entrance of the air passages in the injectors.

The entrance region of the air passages is a highly disturbed flow region, which could have been biasing the dispersion of the coal to the underside of the resulting coal/air jets. This would provide a path for coal to be directed to the exit of the combustor once the coal/air jets were injected into the primary zone. Unfortunately, no change in char production was detected as a result of these changes. A noticeable increase in primary zone CO levels (roughly 2%) was detected. Even though these modifications did not remove the char problem, the change in CO levels suggested that coal injection behavior was a possible candidate for inspection in subsequent runs. More specifically, when the system was elevated to allow for installation of the slagging cyclone, the coal splitter was elevated also. This additional increase in height was thought to have possibly been affecting the uniformity of coal distribution to the four coal/air injectors, which could have led to non-uniform primary zone stoichiometry.

From an operational point of view test, CR1-5 was a reasonably smooth run. Only one difficulty was encountered, which occurred at the start of the run. During initiation of the coal combustion segment of this test, the coal flow rate was started at a rate lower than desired (i.e., coal combustion was initiated fuel-lean). The reason for this was to ensure complete carbon burnout while the system was coming up to operating temperature. If the coal flow rate jumps up to the operating flow rate during coal combustion initiation, poor carbon burn-out occurs. This occurred during the startup of the coal combustion segment of this run. Also, good slag flow at the tap did not occur as early as it should have. For this reason, the distribution of slag among the various components of the system changed. Weights of slag in the various components was different than what was measured in the next run CR1-6. Regarding the particle collection probe filters that failed during the previous three runs, both filters survived this run intact. The fix applied to the particle filter problem seemed to have eliminated filter failures.

Test CR1-6

This was the sixth and last char quantification test in the test series CR1-X. The system was operated with the curved body impact separator and slag tap/bath installed. During this run 863 lbs of Dorchester seam coal were burned. The duration of the coal combustion segment of the run lasted 62 minutes. This test run was performed operating at an equivalence ratio of $\phi = 1.2$. No sorbent was injected during this run. No unusual behavior was experienced during this run.

4.1.1 Results of Char Quantification Tests CR1-1 Through CR1-6.

Char Quantification

After installation of the curved-body impact and slagging cyclone separators the slagging combustor system produced a significant amount of char. Several different approaches were taken to correct this problem, such as changing coal feed conditions, coal/air injector configuration, coal seam, etc., but none had any effect. While developing an explanation and additional corrective actions it was decided to perform a series of char quantification test runs (CR-1 through CR1-6). These were intended to document the extent of combustor char production for the purpose of guiding corrective action schemes and, if the problem was not correctable, to quantitatively define combustor performance in the presence of char production.

The char quantification test runs, CR1-1 through CR1-6, were conducted during the period June through September 1991. No sorbent was injected during these runs. Dorchester and Pittsburgh No. 8 seam coals were burned. Quantification of char production was to be achieved through the following measurements:

1. Measuring exhaust particle emissions (via an isokinetic particle sampling probe) and analyzing collected material for carbon content. These steps quantify exhausted char.
2. Separating the material collected in the slag bath and cyclone separator bucket into slag and char by a sifting process. Weighing the amounts of slag and char collected. Analyzing the collected slag and char material for carbon content. These steps quantify char collected by slag separation stages.

Carbon content analyses were performed on collected material samples by an outside analytical firm. The results of these analyses plus other more detailed analyses were not returned to Textron until November 1991. In the time that elapsed between completion of the char quantification tests and receipt of the results from the outside analytical firm, a solution was implemented that eliminated the char problem. Since the char problem was corrected and it would require a significant amount of time to scrutinize and digest the analyses and weight results to derive char quantification results,

no attempt has been made to produce the char quantification results. These results could be generated, since the raw data has been properly logged, but now that the combustor is operating with essentially zero char production the pertinence of these results is questionable. Consequently, no final char quantification results for the combustor system have been derived and no plan exists to pursue this course. Albeit, a quick look at the slag/char analyses and weight results for tests CR1-5 and CR1-6 indicate that 2.5% of the carbon in the coal was not being burned when the system was producing char.

Separation Efficiency of Curved-Body and Centerbody Impact Separators

A single, non-slag tapping, centerbody impact separator was included in the first configuration of the slagging combustor system. The solids (ash) removal efficiency of this device was measured to be 90%, i.e., it removed 90% of the solids from the combustion gases. Although this unit performed well, higher ash removal efficiencies are required for direct fired gas turbines. In order to minimize the release of sulfur from spent sorbent, which will occur if the spent sorbent remains in the high temperature region of the impact separator for more than a few minutes, impact separator slag tapping was determined to be important. To achieve higher separation efficiencies and slag tapping, a curved-body impact separator (with a slag tap) and a slagging cyclone separator were installed in the combustor system. The installation of these components was completed in early 1991.

The quantification of the separation efficiencies of the new components was to be undertaken during the summer of 1991. While performing the char quantification test runs (CR1-1 through CR1-6), provisions were made that would acquire the data needed to obtain the required separation efficiencies. The procedure for obtaining the necessary data follows.

1. Assume that the centerbody impact separator efficiency remains 90%.
2. Configure the combustor system so that it includes the centerbody impact separator and slagging cyclone.
3. Measure the exhaust particle emissions using the isokinetic particle sampling probe.
4. Have isokinetic probe material analyzed for carbon content.
5. Configure the combustor system so that it includes the curved-body impact separator and slagging cyclone.
6. Measure the exhaust particle emissions using the isokinetic particle sampling probe.
7. Have isokinetic probe material analyzed for carbon content.

In principle, the information obtained by following the above procedure should be sufficient to extract slagging cyclone and curved-body impact separator efficiencies. However, during three (3) of the six (6) CR1-X tests, the ceramic filter in the isokinetic probe broke during sampling. When this happens the exhausted ash result derived from the isokinetic probe data is meaningless. This left only one (1) test including the centerbody impact separator and two (2) tests including the curved-body separator. Based on the accuracy of these measurements and the limited number of data points, we could only conclude that the separation efficiency of the curved-body separator was approximately the same as the centerbody impact separator. It should be remembered that the char problem was present during these test runs. Because of this, overall slag separation efficiencies ranged from 96 to 97%. The data used to construct this efficiency range was corrected to remove the weight of carbon present in each isokinetic particle probe ash sample. This was done to remove the effect of char. Combustion tests performed after the char problem had been eliminated, which was after the CR1-X test series, indicated that the curved-body impact separator and slagging cyclone separator combination have a collective separation efficiency of 97.5 to 99.0%. If the curved-body impact separator is assumed to have an efficiency between 85 and 90%, the slagging cyclone must have an efficiency in the range 85 to 90% also (i.e., to achieve overall separation efficiencies between 97.5 and 99.0%).

4.1.2 Helium-Neon Laser Diagnostic Addition

As previously mentioned, a new diagnostic was added to the system just prior to test run CR1-3, namely a He-Ne laser extinction diagnostic. This diagnostic was installed in the exhaust duct downstream of the lean-burn/quench combustor. This diagnostic provides a real-time measure of exhaust duct particle loading by monitoring the decrease in the power of a low power He-Ne laser beam passed through the exhaust gas stream (normal to the exhaust gas flow direction). The laser beam enters and leaves the exhaust duct via optical windows. The exit beam power is measured via a photo diode detector. Reference power levels are acquired before and after the coal combustion segment of a test run. During coal combustion, the laser beam power monitored by the photo diode will decrease due to light scattering by the particles present in the exhaust gas stream. The natural logarithm of the ratio of the decreased laser beam power (when scattering occurs) to the reference power level (no scattering occurring) provides a measure of the number density of particles in the exhaust gas stream, which can be correlated with exhaust gas particle loading (i.e., mass flow rate of particles in the exhaust gas stream).

Since the extinction diagnosis has a frequency response of order 10 kHz, this diagnostic was installed primarily to determine if exhaust char was being produced on a continuous basis or whether there existed some periodic structure to char production. Periodic, unsteady char production suggested that the coal/air injection jets in the primary zone may have been oscillating spatially. If this occurred, the coal/air jets may have been bending downward

the exit nozzle of the primary zone, thereby sending coal directly to the exit of the primary zone, rather than upward into the toroidal vortex in the dome of the primary zone. The decrease in burn-out time due to this phenomena could cause char production. If steady-state char production was detected, other types of phenomena had to be considered that could result in the reproduction of char, such as biased coal injection. Biased coal injection occurs when the coal flow rates supplied to each of the four primary zone coal/air injectors differ. This can cause different regions of the primary zone to have different stoichiometries, thus producing char locally. It was important, therefore, to determine if the char production was steady or unsteady in order to begin isolating the source of the problem.

The extinction diagnostic serves several other purposes also, making this diagnostic a valuable asset. If it is assumed that the particle size distribution of the particles in the exhaust stream are very close from test run to test run, then a direct measure of the relative change in particle loading from one run to the next can be easily determined. In fact, the extinction diagnostic can be calibrated based on the exhaust particle loadings derived from data from the particle collection probe sampling the exhaust gas stream. Thus, if a particle probe filter breaks during a run, exit particle loading data can still be acquired by information derived from the extinction diagnostic. It also supplies a real-time technique for determining whether operating parameter changes affected char production. It was then possible to see the effects of stoichiometry, coal carrier gas flow rate, etc., changes on char production.

4.2 SULFUR CAPTURE TESTS

Two sulfur capture test sequences were planned for 1991. The first sequence, designated SL1-X, consisted of test runs SL1-1 through SL1-3, which were performed during June. Sulfur capture testing was suspended during July and August in order to perform the char quantification test runs.

Test SL2-1

Test SL2-1, run on September 19, was the first sulfur capture test to be performed from test sequence SL2-X. The system was operated with the curved body impact separator and slag tap/bath installed; 852 lbs of Pittsburgh No. 8 coal were burned. The duration of the coal combustion segment of the run lasted 61 minutes. This test run was performed operating at an equivalence ratio of $\phi = 1.2$. Sorbent was injected during the latter part of the coal combustion segment of the run. The sorbent was a 1:1 mixture (by weight) of limestone and Magnetite. During the sulfur capture test, 91 lbs of the sorbent mixture were injected into the primary combustor. The total duration of the sulfur capture test was 14 minutes. Sorbent flow rates of 4, 6, and 8 pounds per minute were achieved, which corresponds to Ca/S molar ratios of 1.9, 2.8, and 3.7, respectively.

System behavior prior to sorbent injection was good, except for the usual production of char, which was monitored via the He-Ne extinction diagnostic. The behavior of the sorbent injection system during sulfur capture testing was excellent. Smooth control of sorbent flow rate was easily achieved. This has been achieved by: 1) diluting the limestone sorbent, which has poor pneumatic conveying properties, with Magnetite which has good pneumatic conveying properties, 2) agitating the sorbent mixture at the exit nozzle of the sorbent hopper via cyclic injection of nitrogen gas through an array of nozzles in the exit nozzle of the sorbent hopper, and 3) applying proper filtering to the sorbent flow rate readout unit.

Five minutes after initiating sorbent injection, however, a cooling water leak developed in the curved body impact separator. The leakage of cooling water into the impact separator housing was substantial. Although sulfur capture levels ranging from 30 to 50 percent were measured in the combustor exhaust gas stream, the measured sulfur capture levels should not be taken as trustworthy. This is because the leak introduced large amounts of water vapor into the exhaust stream being sampled for SO_x . Since it is not known if sample line dryers removed all the water vapor, it is possible that some SO_2 /water reactions may have occurred in the sample lines before reaching our analyzers. The curved body impact separator cooling water leakage had occurred only once before. The leak, however, seems to occur just after initiating sorbent injection. It is suspected that the sorbent diluent (i.e., Magnetite, which is an effective fluxing agent for reducing slag viscosity) is removing a substantial amount of the slag layer on the curved body separator, thereby changing heat transfer rates significantly. This phenomena could be generating thermal stresses that cause welded seams to crack. The curved body impact separator leak was easily fixed by rewelding the cracked seam. It was determined that sorbent mixtures containing less Magnetite would be used in future tests to reduce the effects of this fluxing agent on impact separator integrity.

Test SL2-2

Test SL2-2, conducted on September 26, was to be the second sulfur capture test performed from test sequence SL2-X. However, this run was a combined sulfur-capture/char-reduction test. A meeting among test facility personnel and Textron senior staff scientists took place on September 16 to review the results of the char test sequence, i.e., sequence CR1-X.

During test CR1-6, a video camera was positioned so that it was viewing combustion occurring at the top of the primary zone. This tape was reviewed during the September 16 meeting where it was concluded that primary zone combustion appeared to be unsteady. During test CR1-6, the four coal injector delivery tubes were repositioned inside each coal/air injector passage to see if this had an effect on char production. The coal carrier line from the coal tank to the four-way coal splitter was elevated before beginning test CR1-6 in order to see if changes in splitter elevation could affect coal delivery

behavior. (It should be noted that the entire combustor, including the coal splitter, was elevated by nominally 30 in. when the cyclone was installed and that the char problem appeared after installation of the cyclone.)

Repositioning the coal delivery tubes in the coal/air injectors and raising/lowering the coal carrier line between the coal tank and splitter did not change char production rates during CR1-6. However, every time a coal delivery system element was moved, a noticeable change in coal flow rate was observed. This observation implied that the stability of the coal delivery system may have been marginal, if not unstable. It was thought that this instability was responsible for the unstable combustion observed in the primary zone combustion video, and was possibly leading to the char production.

As a result of the September 16 meeting, it was decided to change the coal delivery system in such a way as to improve coal flow stability. After determining the actual flow velocities in the lines conveying the pulverized coal from the coal tank to the coal/air injectors, it was concluded that these velocities were low relative to those needed to produce very stable two-phase flow. These velocities were increased to the desired levels by replacing all hoses on the coal delivery system with smaller ID hoses. Increasing carrier line velocities this way assumed that the carrier air and coal mass flow rates could be kept constant.

It was recognized that keeping the carrier air flow rate constant may not be possible, because of the supply pressure limitation of the carrier air compressor. A small change in hose ID could significantly increase the pressure drop over the delivery system lines. The first option considered was to rent a higher pressure compressor to ensure that sufficient pressure would be available to achieve the carrier air flow rates desired. Since it would have taken time to acquire and install a rental compressor system, it was decided to modify the coal delivery system hoses to experimentally determine what coal delivery flow conditions could be achieved with the resident carrier air compressor.

Results from test SL2-2 demonstrated that the resident carrier air compressor could not supply the pressure head needed to maintain proper carrier air flow. Either a higher pressure compressor system or a high pressure air tube trailer would need to be rented. A permanent higher pressure carrier air supply would not be installed until it had been demonstrated that this approach would correct the char problem.

Test SL2-2A

Test SL2-2A, conducted on October 4, a continuation of test SL2-2, was intended to be a sulfur reduction test. This test was conducted with the curved body impact separator and slag tap/bath installed. During this run 569 lbs of Pittsburgh No. 8 coal were burned. The equivalence ratio during this test varied from $\phi = 1.0$ to 1.3. The sorbent to be injected during

this run was 2:1 mixture of limestone and Magnetite. Sorbent mixture flow rates of 4, 6 and 8 lbs per minute were planned for this test, which corresponded to Ca/S molar ratios of 1.9, 2.8, and 3.7 respectively.

At the time prior to Test SL2-2A, it was thought that unstable combustion may be occurring due to two-phase flow instabilities in coal conveying lines, and that unstable combustion may be responsible for the char being generated by the combustor system. Just prior to test SL2-2, the hoses conveying coal from the coal hopper to the coal splitter and on to the four coal/air injectors, were replaced with smaller ID hoses. This was done to increase conveying velocities, which should have yielded a more stable two-phase flow in the conveying lines. The previous test, test SL2-2, was aborted because the carrier air flow rate through the conveying lines ceased when coal was introduced into the conveying lines. This was not unexpected, since it was recognized that the pressure losses in the conveying lines scales as d^{-5} and that the primary compressor may not have had the pressure head necessary to overcome the increased pressure losses.

Subsequent to test SL2-2, arrangements were made to lease an air tube trailer, rated at 40,000 SCF air and 2000 psig, which would be regulated down to nominally 150-180 psig and used as the air source for the coal delivery system. This air source would overcome pressure loss limitations. Since receipt and installation of this air source was expected to take nominally two weeks, it was decided to use gaseous nitrogen from an existing tube trailer to convey the coal through the coal delivery system. This approach was tried during test SL2-2A. This approach was not altogether satisfactory since an inert, non-oxidizing gas was injected with the coal into the combustor. Although the coal carrier air flow is only 2% of the primary air flow, substitution of nitrogen in place of air for coal conveying could affect combustion since it could produce a non-oxidizing atmosphere in dense coal region in the combustor.

The first part of test SL2-2A was to be used for establishing coal delivery system operating parameters, with the remainder of the test dedicated to sulfur reduction tests. Due to difficulties encountered, the entire test was dedicated to establishing operating parameters. Consequently no sorbent was injected during this run. The difficulties revolved around very erratic coal flow rates, which were 14 ± 5 lbs per minute. The erratic flow rate problem was later traced to a loose wiring connection between the load cells on the coal hopper and the weight/rate readout unit.

After achieving coal combustion, the nitrogen carrier flow rate and coal hopper pressure were adjusted to give the desired coal flow rate (14 lbs per minute) and the same carrier flow rate used prior these modifications (2.6 pounds per minute). Under these conditions the coal tank was at maximum pressure (175 psig). It should be noted that it took almost the entire run to achieve these conditions, so the operating conditions for most of the run were not optimum. After reaching the desired conditions, the He-Ne extinction

diagnostic was indicating that the particulate loading in the exhaust gases was down by 40% from previous runs. Post-test system breakdown revealed that the cyclone bucket contained less char than observed in previous runs conducted after installation of the slagging cyclone. These results suggested that the system elements influencing char production may have been identified, and that steps being taken to correct the problem were effective.

Since the reduced ID hosing installed in the coal delivery system had increased the required operating pressure of the coal hopper to its limit, which was not desirable, all of the original hoses (larger ID hoses) were reinstalled for future tests. Increased carrier velocities were achieved by increasing the carrier gas mass flow rate.

Test SL2-3

Test SL2-3, which took place on October 18, was the third sulfur capture test to be performed from test sequence SL2-X. The configuration of the system was the same as for test SL2-2A, except for modifications to the coal delivery system. During this run, 1044 lbs of Pittsburgh No. 8 coal were burned. The equivalence ratio during this test varied from $\phi = 1.1$ to 1.3. The sorbent injected was a 2:1 mixture of limestone and Magnetite. Sorbent mixture flow rates from 4 to 8 lbs per minute were achieved during this test, which correspond to Ca/S molar ratios from 1.9 to 3.7. A total of 147 lbs of sorbent mixture were injected. The coal combustion portion of the test lasted 81 minutes and sorbent was injected for 27 minutes.

For this test, all reduced ID hoses installed in the coal delivery system for the previous test were replaced with the original larger ID hoses. In order to install the reduced ID hoses for the previous test, however, the coal splitter had to be modified slightly, yet not permanently. This modification consisted of inserting a 0.375-in. OD stainless steel tube up through the inlet port of the splitter, and blending it into the internal surroundings via a conically shaped bushing. This was needed because the inlet port of the splitter is a 0.75-in. diameter by 6-in. bore; and transitioning from a 0.32-in. ID line from the coal hopper to the 0.75-in. bore at the entrance of the coal splitter inlet port would probably produce a poorly behaved two-phase jet inside the splitter assembly. This would have been undesirable. Rather than changing this modification back to the original configuration, it was left untouched. This was done because it was felt this modification would improve the behavior of the two-phase jet in the splitter, which would give more uniform distribution of coal between the four coal/air injectors. Since the conveying lines were returned to their larger ID parts, it was believed that leaving this one smaller bore section in the system would not introduce unacceptable pressure losses during operation.

As soon as coal combustion was initiated during the SL2-3 test run, the system entered a long period (several seconds) of combustion oscillation mode. This occurred because the coal hopper pressure was set to low. The difference

between the coal hopper pressure and the coal carrier pressure determines the flow rate of coal out of the hopper. The coal carrier line pressure increases significantly when coal combustion begins, thus reducing the pressure difference between the hopper and the carrier line. If this pressure difference becomes zero or changes sign, the coal flow stops, the combustor pressure drops, and the cycle repeats. This was corrected by increasing the coal hopper pressure until the oscillation ceased.

By systematically increasing the coal carrier flow rate in conjunction with the coal hopper pressure, it was possible to achieve the operating conditions desired, namely 14 lbs per minute coal flow and a carrier air flow rate 40% greater than levels achieved in tests before coal delivery system modification. Contrary to our initial thoughts, the short length of reduced ID line at the inlet of the coal splitter did lead to significant pressure losses in the conveying line. As a result, the coal hopper pressure needed to obtain the desired operating condition was quite high (nominally 15 psi below the hopper limit). The reduced ID line entering the coal splitter was replaced with the original line for future tests in order to allow operation at lower hopper pressures. After this change, more stable two-phase coal flow was achieved by using elevated carrier air flow rates.

The desired operating conditions were achieved in approximately 24 minutes after coal combustion initiation. Combustion without sorbent injection was allowed to proceed for another 20 minutes, after which sorbent-injection/sulfur-capture experiments were conducted. After initiating sorbent injection, sorbent flow rates of 4, 6 and 8 lbs per minute were easily set and maintained. Each sorbent flow rate was maintained for nominally 8-9 minutes. At the end of the test the data acquisition computer crashed due to a hard disk full error, and the data acquired during sulfur capture tests was lost. Thus, no statement could be made regarding sulfur capture performance. This disk error unexpected since sufficient room on the disk was made prior to beginning this run. The reason this error occurred was due to the fact the computer was acquiring data for nominally 4.5 hours during this run. The run was long because of the time required to resolve an interlock problem involving the coal flow which could not be started unless the carrier air throttle valve was open greater than 20%. Since the carrier air flow rates needed were achieved with this valve less than 20% open, the coal flow could not be started. This situation was eventually resolved. Regardless, the data accumulated was greater than what was available for storage space on the hard disk.

Post-test system breakdown revealed that essentially no char was produced during this run. The cyclone slag bucket contained only slag. The particle probe filters contained very little char material. The particle filters for the gas analyzer probes also contained very little char material. Much of the slag which has been accumulating over previous runs was removed from combustor

sections and flowed into either the slag tap bath or the cyclone bucket, which suggests that higher temperatures were being achieved. These results implied that the steps taken to correct the char problem were very effective.

It was reasonably safe to say that the char problem had been corrected. It was corrected by increasing coal carrier air velocities, thereby producing more stable coal delivery. It is expected that better combustion will lead to better sulfur capture results by virtue of higher primary zone temperatures. To date, and since installing the slagging cyclone, sulfur reductions of only 50% have been achieved. Pre-cyclone sulfur capture experiments conducted in 1989 indicated that sulfur reductions of 90% had been achieved in the primary zone. It was expected that better combustion would improve the sulfur reduction results for the present system configuration, but it was unlikely that this alone would yield the previously observed 90% sulfur reduction results. Examination of the logs discussing the 1989 90% sulfur reduction test revealed that certain sorbent delivery system operating conditions must exist in order to achieve a good "fan-pattern" from the sorbent injectors in the primary zone. It was believed that the sorbent injection system was not operating in the parameter range that would give the desired fan-pattern needed for good sorbent dispersion, thus good sulfur capture. The required conditions could be achieved by increasing the sorbent delivery system carrier air flow rate above the levels currently being used. In subsequent tests higher sorbent carrier air flow rates were achieved by connecting this system to the air tube trailer source now used for supplying carrier air to the coal delivery system. This modification was made before the test SL2-4 was conducted.

Test SL2-4

This test, which was conducted on November 12, 1991, was the fourth sulfur capture test to be performed from test sequence SL2-X. It was also the first sulfur reduction test to be conducted after eliminating the char problem. During this run, 1051 lbs of Pittsburgh No. 8 coal were burned. The equivalence ratio varied from $\phi = 1.1$ to 1.2. The coal combustion portion of the test lasted 82 minutes. Sorbent was injected for 30 minutes. The sorbent injected during this run was a 2:1 (by wgt) mixture of limestone and Magnetite. Sorbent mixture flow rates between 3 and 6 lbs per minute were achieved during this test, which corresponded to Ca/S molar ratios between 3 and 6. The main thrust of this test was to try to reproduce the 90% sulfur capture observed during Test 8-7 conducted in 1989. A log of Test 8-7 indicated that a sorbent to carrier-air loading ratio of one or less was required to achieve a good fan pattern from the sorbent injectors in the primary zone. Since the Textron primary air compressor was delivering lower supply pressures than what was achievable in 1989, it was assumed that the good fan pattern was not being achieved since it was not possible to achieve a loading ratio less than one. To correct this, the air tube trailer supply installed to drive the coal carrier air was connected to the sorbent carrier air circuit also. This modification allowed sorbent to carrier-air ratios

less than one. During this test, the required loading ratio was easily achieved and sorbent flow rate control was very good. The only difficulty that arose was that a cooling water leak developed in the curved body impact separator. When this problem occurred in the past, a local patch weld was made. This time the entire seam, which covers the entire perimeter of the curved body impact separator, was rewelded.

Test SL2-5

This test, which was conducted on November 21, was the fifth sulfur capture test to be performed from test sequence SL2-X. During this run 971 lbs of Pittsburgh No. 8 coal were burned. The equivalence ratio during this test varied from $\phi = 1.1$ to 1.2. The coal combustion portion of the test lasted 73 minutes and sorbent was injected for 38 minutes. The sorbent injected during this run was a 4:1 (by wgt) mixture of limestone and Magnetite. One pound of Cabosil (fumed silica of submicron size) was added to the 255 lbs total weight sorbent mixture. Cabosil is an extremely effective agent for improving the flow behavior of limestone. It was added to the sorbent mixture to see if it would further improve sorbent flow rate control. Sorbent mixture flow rates between 2.5 and 7.5 lbs per minute were achieved during this test, which corresponded to Ca/S molar ratios between 2.8 and 8.6, respectively. The main thrust of this test was to try to reproduce the 90% sulfur capture observed during Test 8-7 in 1989. After Test 8-7, the sorbent injectors were sleeved with a 0.25-in. stainless steel tube. This was done to keep the two-phase sorbent/carrier-air mixture at higher velocities, thereby maintaining mixture homogeneity to prevent plugging due to condensation forming on the water cooled walls of the main bores of the injector tubes. Since this was done after the 1989 90% sulfur capture results were achieved, it was decided to remove these sleeves and return the system as closely as possible to the 1989 configuration. During this run a parametric study was done involving varying sorbent flow rate and sorbent carrier air mass flow rate. This was done to explore their effect on primary zone sorbent dispersion. Addition of Cabosil improved sorbent flow control significantly. The only difficulty that arose during this run was a water leak that developed in the cyclone exit tube (i.e., the cyclone vortex finder tube). This part experiences extreme thermal loads which can cause a thermal stress induced weld fatigue. As with the curved body impact separator, the leaking weld seam was rewelded entirely, which should postpone future water leak problems in this area.

Test SL2-6

This test, which was conducted on November 27, was the sixth sulfur capture test to be performed from test sequence SL2-X. During this run 725 lbs of Pittsburgh No. 8 coal were burned. The equivalence ratio during this test varied from $\phi = 1.0$ to 1.5. The coal combustion portion of the test lasted 56 minutes and sorbent was injected for 25 minutes. The sorbent injected during this run was a 4:1 (by wgt) mixture of limestone and Magnetite with 0.4% (by wgt) Cabosil (fumed silica used for flow control improvement).

Sorbent mixture flow rates of 1.8 and 4.7 lbs per minute were set and maintained during this test, which corresponded to Ca/S molar ratios of 2.1 and 5.4. The main thrust of this test was to explore the apparently strong sulfur capture detected during test SL2-5, which occurred when $\phi < 1.1$. This is why ϕ was varied between $1.0 < \phi < 1.5$ and only two Ca/S ratios were used. This was a smooth, very well behaved test. No difficulties were encountered.

Carbon Burnout Results

Reducing the coal to carrier-air loading ratio by increasing carrier mass flow rate has had a significant impact on eliminating the char problem plaguing this system since installing the slagging cyclone in the latter half of 1990. Essentially no char was detected in the cyclone bucket or in the particle probe sampling filters after the system was dismantled after tests SL2-4 through SL2-6. Based on gas analyzer results, carbon burnout varied between 98.5 and 97.5% as ϕ was varied between $1.2 < \phi < 1.5$. These estimates are known to be slightly low since no account was taken for moisture present in the primary combustion air, which should not be very significant. The moisture in the air must be taken into account because the combustion gases are dried before entering the gas analyzers. Regardless, it appears that the system is producing carbon burnout results very much the same as before the cyclone was installed.

Slag Collection Efficiency

Based on the amount of coal burned while the exhaust particle collection probes were sampling, it was possible to derive an overall slag/ash collection efficiency for the curved body impact separator, slagging cyclone separator combination. When no sorbent was being injected, the overall collection efficiency was $97.5\% \pm 1\%$. The modest variance on this result is due to the relatively small size of ash collected in the particle probe filter. When sorbent was injected, the overall collection efficiency varied between 98.0 and 98.7% with a variance of nominally $\pm 0.3\%$. This indicates that the combined, overall slag/ash collection efficiency of the separators is 98 to 99%.

Sulfur Capture

During tests SL2-4 and SL2-5, the maximum sulfur reduction observed was nominally 30%. This reduction was measured both in the primary zone and in the exhaust downstream of the lean-burn/quench combustor. Although these are low relative to the goal of 90% for Pittsburgh No. 8 coal, it does imply that slag tapping is effective for preventing the spent sorbent from releasing captured sulfur back into the exhaust gas stream. During test SL2-5, sulfur reductions of apparently $< 90\%$ were observed when the equivalent ratio dropped just below $\phi = 1.1$. This phenomena was further studied during test SL2-6. Upon close review of 1989 data, it was found that the same trend had been

observed. No explanation was given for this phenomena then and no new ideas have been formulated. It is suspected that this is probably a gas analyzer idiosyncrasy, rather than true sulfur capture. This effect may be of some academic interest, but is not germane to this effort. If it really is sulfur capture, it occurs at stoichiometries where NO_x production is unacceptable. Other interesting sulfur captures were observed when $1.1 < \phi < 1.2$, namely a 20% sulfur reduction was observed in the primary zone and, at the same time, a 40% reduction was observed in the exhaust downstream of the lean-burn/quench combustor. The mesh size of the limestone used for tests SL2-5 and SL2-6 was increased from 325 mesh, which has been used consistently before, to 200 mesh. This change was made to see if using a larger mesh would decrease the amount of sorbent passing through the system. It did not seem to have an effect on exhaust particle loading, but it may be affecting sulfur capture. By increasing sorbent particle size, limestone calcination times should increase. If complete calcination is not occurring in the primary zone, maximum sulfur reduction will not occur there either, and some sulfur capture may take place in the impact separator section. This could explain the greater sulfur reduction measured in the exhaust relative to that measured in the primary zone. Regardless, the 325 mesh limestone will be used in all future ratios to eliminate calcination time scale effects.

4.3 NORTHERN STATES POWER COAL TESTING

The subbituminous coal testing at Textron's Haverhill facility was done as a cooperative activity between Northern States Power, Westinghouse and Textron; this was independent of the work sponsored by DOE/METC. Two different NSP provided Wyoming subbituminous coals, were burned in the pressurized slagging combustor over a series of seven test runs. Two of these tests were done with Textron funding and the remaining five tests in which limestone sorbent was injected were paid for by Westinghouse and NSP.

The Antelope and Rochelle seam coals were found to burn easily and completely. Carbon burnouts based on the amount of carbon in the quenched slag and the flyash were $\geq 99.99\%$. CO levels were found to be between 60 -70 ppm at a primary zone fuel to air equivalence ratio(ϕ)equal to 1.2.

NO_x emissions were controlled to < 0.2 lb/MMBtu, which is significantly below the 0.6 lb/MMBtu NSPS limit, by staging combustion and running the primary zone $\phi \geq 1.1$.

Interestingly the limestone sorbent injected seemed to have little effect on sulfur capture. With or without sorbent addition the sulfur capture in the primary zone was 45 to 65%; the lean/quench emissions levels showed only a 30% reduction. It appears that the inherent Ca found in these coals is causing the sulfur capture.

Although particulate emissions exceeded NSP limits of 0.03 lb/MMBtu, the mean size of the particles coming through the slagging cyclone separator was 2

microns with a top size ≤ 5 microns. Based on these results, it appears that the loading of particulates, although greater than NSPS levels, are quite small in size and unlikely to cause erosion damage to the turbine blades. Westinghouse's alkali probe measurements were taken during each run and gave vapor alkali levels < 100 ppb. Ames alkali probe measurements were taken on only one run and indicated that the vapor alkali had an upper limit of 100 ppb.

Test Objectives

The objectives of the test series with the Rochelle and Antelope seam subbituminous coals were to include:

- Demonstration of high combustion efficiencies
- Determine particulate and particle size distributions of gases exiting the lean quench combustor
- Determine vapor and particulate alkali concentrations in the gases exiting the lean quench combustor using a Westinghouse alkali probe
- Assess the emissions of particulates, sulfur dioxide and oxides of nitrogen at the exit to the lean quench combustor
- Assess the slag removal characteristics
- Determine the gas composition and the Btu value of the fuel rich gas exiting the primary combustor

Operating Experience

Nominal NSP test conditions for the subscale combustor tests in Table 4-2 are given in Table 4-3; please note that Textron expresses the stoichiometry in terms of a fuel to air equivalence ratio (ϕ), which is the reciprocal of the normal utility boiler equivalence ratio. From the outset of NSP combustor testing a stable, flowing slag layer was formed on the primary zone dome walls. No obstruction or fouling of any of the primary zone coal/air injectors or of the relative small diameter primary zone exit nozzle with slag was observed. The combustor has demonstrated stable and intense combustion, excellent carbon conversion, very low NO_x emissions, efficient slag capture, retention of most of the alkali in the slag and low pressure and heat losses.

Fuel Specifications

Table 4-4 and 4-5 give the coal and ash analysis of the Rochelle and Antelope coals which were provided by NSP for the test program. Along with these coals are also included the analyses for the previous coals studied in the DOE work.

Table 4-2. NSP Coal Test Matrix

<u>Run No.</u>	<u>Date</u>	<u>Coal</u>	<u>Sorbent</u>	<u>Ca/S Ratio</u>
R-001A	12/23/91	Rochelle	Linwood	2;4
R-001B	1/03/92	Rochelle	Linwood	2;4
R-002	1/14/92	Rochelle	Linwood	2;4
A-001	2/06/92	Antelope	Linwood	2;4
A-002	2/14/92	Antelope	Linwood	2;4
R-0	IRAD test	Rochelle	none	
A-0	IRAD test	Antelope	none	

Table 4-3. Nominal Test Conditions

Coal Thermal Input	12 MMBtu/hr
Coal Feed	95% < 200 mesh PC
Oxidizer	650 deg F (620 K)
Primary Zone Equivalence Ratio (ϕ)	1.2 to 1.4
Total Mass Flow Rate	7 lb/s (3.2 kg/s)
Exit Temperature	2000 deg F
Pressure	6 atm
Sorbent	-325 mesh limestone
Sorbent Molar Ratio	Ca/S = 2;6

Table 4-4. Analyses for Coals Tested to Date

	Dorchester, Va	Pittsburgh, WV	Hanna, WY	Antelope, WY	Rochelle, WY
Heating Value (Btu/lb)	14,234	13,822	11,784	9,515	9,456
Proximate Analysis (wt %)					
Moisture	1.0	1.5	9.1	20.2	21.8
Ash	6.2	7.6	5.4	4.9	5.2
Ultimate Analysis (wt %)					
Carbon	80.4	76.7	67.1	56.4	56.0
Hydrogen	4.8	5.2	5.1	3.9	3.7
Nitrogen	1.7	1.3	1.4	0.9	0.8
Oxygen	4.8	5.2	11.3	13.5	12.2
Sulfur	1.0	2.4	0.57	0.30	0.40
Size	95% thru 200 mesh				

Table 4-5. Ash Analysis and T-250's

Ash Properties	Dorchester, Va	Pittsburgh, WVa	Hanna, WY	Antelope, WY	Rochelle,
SiO ₂	44.78	39.40	31.46	20.09	30.20
Al ₂ O ₃	20.89	21.80	15.92	11.17	14.09
Fe ₂ O ₃	22.65	22.79	8.97	9.25	5.87
CaO	4.40	6.55	24.86	13.87	9.32
MgO	1.20	2.10	8.86	6.37	5.97
Na ₂ O	0.51	1.45	1.38	1.90	1.91
K ₂ O	1.85	1.51	1.02	0.30	0.33
TiO ₂	1.51	1.27	0.74	1.72	2.06
P ₂ O ₅	0.52	0.40	0.58	N/A	N/A
T-250 deg.F	2340	2295	2190	2195	2215

Carbon Burnout and Combustion Efficiency

Isokinetic particulate samples collected from the exit to the lean quench combustor and slag samples collected from the water quench tank were for chemical analysis. Based on the carbon composition in these samples the carbon burnout/carbon combustion efficiency was determined. Table 4-6 shows the results of these analyses to be $\geq 99.99\%$.

Table 4-6. Carbon Burnout and Combustion Efficiency

<u>Test Number</u>	Carbon Burnout %	
	<u>Quenched Slag</u>	<u>Fly ash</u>
Rochelle Coals		
R0	99.990	99.990
R001A	99.994	99.998
R001B	99.993	99.995
R002	99.994	99.999
Antelope Coals		
A0	99.981	99.999
A001	99.989	99.999
A002	99.989	99.999

Figure 4-1 plots the measured carbon conversion after the rich zone combustor for the Antelope and Rochelle coals along with previous results from the DOE testing. It should be noted that the DOE results are based on gas analysis while the NSP coals are based on the actual carbon content in the quenched slag.

Textron installed a CO analyzer which could measure in the ppm level. This was operated on the last NSP test run, A002. CO levels were found to be between 60 - 70 ppm at $\phi = 1.2$.

All of the above results imply that the NSP pulverized coals (95% thru 200 mesh) are very effectively burned in the pressurized slagging combustor.

NOx Emissions

The NSP coals evaluated in this testing contained from 0.85 to 1.6% nitrogen. If all of this nitrogen was converted to NOx there would be exhaust emissions in the pounds per million Btu level. However, by staging the combustion the NOx levels with the slagging combustor were minimized to ≤ 0.2 lb/MMBtu.

It is known that the main source of NO in the combustion of coal is fuel-bound nitrogen. Part of the fuel nitrogen is released with the volatiles in the

Figure 4-1. Measured Primary Zone Carbon Conversions

early stages of combustion, while the remainder is released with the subsequent char oxidation. NO formation from fuel-bound nitrogen is very sensitive to the combustion stoichiometry; depending on the available O_2 , the HCN and NH_3 volatilized can be oxidized to NO or can react with NO to form harmless N_2 . For staged combustion to be effective we must not carry over volatile or char nitrogen to the final lean-quench zone, where they could be converted to NO. The intense and rapid mixing caused by the toroidal vortex design leads to rapid devolatilization of the coal, homogeneous combustion conditions and efficient oxidation of the char to fuel-rich gases in the primary zone. These conditions favor conversion of fuel-bound nitrogen to N_2 and minimizes the carry-over of volatile or char nitrogen to the lean-quench combustor.

Previously (Loftus et al; 1991) we determined that the bulk of the NO is generated in the primary zone from the fuel-bound nitrogen. This is verified in the present tests (at a $\phi = 1.2$), if one observes the primary zone NOx

analyzer (~ 200 ppm) versus the exhaust NOx analyzer (50 - 60 ppm). Remembering that 2/3 of the air is added in the lean-quench combustor zone; thus, if the primary zone NO formation was the only source of NOx then this value would be reduced to 1/3 its value by dilution.

Figure 4-2 gives a plot of NOx emissions as a function of the primary (rich) zone equivalence ratio (ϕ) for the NSP tests and for the pulverized coal DOE tests.

As long as the $\phi > 1.0$ the NOx values are below the NSPS requirements of 0.6 lbs/MMBtu. With $\phi \geq 1.1$ the NOx levels are < 0.2 lb/MMBtu.

Particulate Emissions

Isokinetic samples collected at the exit to the lean-quench combustor were used to determine the particulate emissions levels. These fly ash samples were sent for a total quantitative analysis so as to determine the carbon burnout and the alkali concentration in the particulates.

Table 4-7 gives the emissions levels after the lean-quench combustor and also gives the collection efficiency of all particulate collection systems.

Figure 4-2. NOx Exhaust Emissions

Table 4-7. Particulate Emissions Levels and Collection Efficiencies

<u>Test Number</u>	<u>Collection Efficiency %</u>	<u>Emissions Levels</u>	
		<u>ppmw</u>	<u>lb/MMBtu</u>
R0	95	131	0.27
R001A	97	80	0.18
R001B	97	150	0.33
R002	99	70	0.15
A0	97	66	0.14
A001	98	115	0.25
A002	99	61	0.13

Based on these test results it will be necessary to add either a barrier filter or a scrubber to meet the NSP particulate levels of 0.03 lbs/MMBtu.

The particle size distributions of the fly ash samples were determined qualitatively by a scanning electron microscope (SEM) and quantitatively by the Malvern analyzer. From the SEM's it appears that the bulk of the particles are < 1 micron.

A typical particle size distribution given by the Malvern analyzer showed a mean size around 2 microns and the top size of about 5 microns.

Based on these results, it appears that the loading of particulates, although greater than NSPS levels, are quite small in size and unlikely to cause erosion damage to the turbine blades.

Alkali Levels

During the Rochelle test runs, a Westinghouse alkali probe was placed in the downward duct section after the lean/quench combustor and just before the orifice plate. The temperatures here were around 1200° to 1500°F. It was suggested by Stone & Webster that we might be condensing some alkali at these temperatures. During the Antelope test runs, the probe was placed just after the lean/quench combustor, where it would experience higher temperatures. Unfortunately, at the later location, the probe operated only for minutes due apparently to plugging. After some troubleshooting, the problem was traced to a faulty regulator in the Westinghouse alkali probe supply system.

The Westinghouse probe was used to determine the vapor alkali levels in the exhaust gases. The particulate alkali levels were determined by chemical analysis of the isokinetic collected fly ash. Table 4-8 gives the results of these studies.

Table 4-8. Alkali Levels

<u>Test No.</u>	<u>Vapor Alkali ppb</u>	<u>Particulate Alkali ppb</u>
RO	11	5270
R001A	34	3420
R001B	18	9170
R002	9	7000
A0	61	5210
A001	74	9630
A002	209	7030

Except for the A002 tests all vapor alkali values measured by the Westinghouse probe were below 100 ppb. Although not quantitative because of shakedown problems, the Ames alkali probe measurements, taken during Test A002, gave indications that the vapor alkali had an upper limit of 100 ppb. Based on the Ames results and the short duration of sampling before apparent plugging of the Westinghouse probe, Textron does not believe the 209 ppb result of the Westinghouse probe. In fact all the Antelope vapor alkali results are questionable due to the apparent plugging problems experienced after short sampling periods.

At best the vapor alkali results indicate lower than expected levels which is encouraging. However, it was recommended that further alkali testing be done with the Ames alkali probe to provide more definitive data.

SOx Emissions and Sulfur Capture

A limestone sorbent was fed into the primary combustor for sulfur capture during five of the tests. The sorbent Ca/S molar ratio was run at 2 and 6. The subbituminous coals tested had a significant amount of Ca inherent with the coal; it varied from $1 < \text{Ca/S} < 2$.

Since the sulfur content of either coal was $\leq 0.4\%$, it was necessary to dilute the limestone with fly ash to allow us to feed the sorbents with any

degree of accuracy. Unfortunately the fly ash contained ~0.5% sulfur; however, this was accounted for in analyzing the test data.

It should be noted that of the five (5) sorbent runs made, it was only possible to get meaningful data from two of them. Fortunately there was a good sorbent run on each of the coals tested. This is not uncommon in our experience on the DOE work. It is caused by difficulty in maintaining a steady sorbent feed and in difficulty of measuring SO_2 and H_2S accurately in the limited number of experiments performed.

Unlike the DOE sponsored work at a $\phi = 1.2$ on the eastern bituminous coals, where SO_2 was the dominant sulfur specie, these tests on the NSP western subbituminous coals showed the H_2 to be the dominant specie. Although surprising it can be understood by the fact that the peak flame temperatures in the primary zone should be significantly lower with these western coals with high moisture content. Thermochemical equilibrium calculations tell us that as the flame temperatures decrease we should expect more H_2S to be present.

Interestingly, the sorbent injected seemed to have little effect on sulfur capture. With or without sorbent addition the sulfur capture in the primary zone was 45 to 65% and the lean/quench emissions levels showed only a 30% reduction.

This is not very surprising because as the sulfur gas composition decreases in the gas phase, it becomes more difficult for it to react with the limestone; plus the nonequilibrium sulfur capture work done by Abichandani et al; 1989 showed lower captures with H_2S then with SO_2 .

It appeared that the inherent Ca found in these coals was causing the sulfur capture. The resulting concentration of the H_2S seems to be too low to allow for further significant reaction with the limestone sorbent fed.

Previous DOE sponsored sulfur capture work was done with the Pittsburgh seam coal which contained 7.2% ash with a 6.6% CaO content. It can only be speculated that the remaining sulfur gases are so low that the sorbent does not effectively capture it.

Heat Loss and Pressure Loss

Since the pressurized slagging combustor is water cooled, we are able to measure the change in the cooling water temperatures and thus determine the heat loss from the various stages of the system (See Table 4-9).

Table 4-9. Heat Loss Data

	Equivalence Ratios (ϕ)	
	<u>1.2</u>	<u>1.4</u>
Heat Loss in:		
Primary Zone	10%	8%
Impact Separator	7%	5%
Slagging Cyclone	11%	8%
Lean/Quench Zone	4%	5%

Transducers are used to monitor the pressure changes in the system on each of the components. Table 4-10 lists the typical pressure drops seen during the NSP testing. The total pressure drop through the lean/quench combustor was 7.9%.

Table 4-10. Combustor Subsystem Pressure Losses

<u>Component</u>	<u>Percent Pressure Loss (%)</u>
Primary Zone Air Injector	2.7
Primary Zone Nozzle & Impact Separator	2.6
Slagging Cyclone Separator	2.2
Lean/Quench Combustor	0.4

Composition and Heating Value for Fuel-Rich Gases Prior to the Lean-Quench Combustor

Gas samples were taken from the primary zone and from the impact separator exit. These samples were analyzed by a gas chromatograph (GC) for hydrogen, nitrogen, carbon monoxide and carbon dioxide concentrations. Table 4-11 gives these concentrations on a mole percent dry basis as measured by the GC and as a mole percent wet basis, where we have calculated the water concentration based on thermochemical equilibrium calculations at the equivalence ratio set experimentally. It should be noted that this gas obviously contains water vapor and sulfur gases. The sulfur gases are in the ppm levels and should not significantly effect the heating value calculation of the gases.

Table 4-11. Composition of Fuel-Rich Gases

<u>Species</u>	At Equivalence Ratio of 1.2	
	<u>Mole (% dry)</u>	<u>Mole (% wet)</u>
H ₂	1.49	1.28
N ₂	77.39	66.64
CO	5.67	4.88
CO ₂	15.46	13.31
H ₂ O	0.0	13.89

<u>Species</u>	At Equivalence Ratio of 1.25	
	<u>Mole (% dry)</u>	<u>Mole (% wet)</u>
H ₂	1.55	1.32
N ₂	77.28	66.10
CO	5.91	5.06
CO ₂	15.26	13.05
H ₂ O	0.0	13.61

<u>Species</u>	At Equivalence Ratio of 1.45	
	<u>Mole (% dry)</u>	<u>Mole (% wet)</u>
H ₂	5.10	4.45
N ₂	70.69	61.73
CO	13.64	11.91
CO ₂	10.57	9.23
H ₂ O	0.0	12.68

Converting this over to a heating value by using the specific heating value per pound only for hydrogen and carbon monoxide. The resulting Fuel Heating Values for the constituent gases are given below in Table 4-12 as a function of the equivalence ratio.

Table 4-12. Fuel Heating Values

<u>Equivalence ratio</u>	<u>LHV (Btu/lb)</u>	<u>Btu/SCF</u>
1.2 - 1.3	250 - 350	42 - 58
1.4	700	117

GENERIC TURBINE STUDIES

Performance data has been calculated for the Westinghouse 251B12 combustion turbine with a nominal inlet flow of 220 lb/sec. The 220 lb/sec is representative of the 251B12 with the first two stages of compressor blades removed. Flow data was developed for the following variables:

- Burner Outlet Temperature
- Ambient Temperature
- Pressure Drop Across the Pressurized Circulating Fluidized Bed
- Fuel Composition

The following six tables (Tables 5-1 thru 5-6) summarize the data calculated for the above mentioned variables.

Performance calculations for 370 lb/sec flow, which is representative of a standard Westinghouse 251B12 combustion turbine, has begun using the same variables. A comparative analysis will be made with the low flow calculations once completed.

TABLE 5-1

EFFECT OF CHANGE IN AMBIENT TEMPERATURE
WITH 1600°F BOT

Ambient Pressure	14.3 psia
Relative Humidity	65%
PCFB Pressure Drop	18.85 psi
Burner Outlet Temperature	1600°F

Fuel Analysis (% wt)

Carbon	37.96
Hydrogen	8.14
Sulphur	0.03
Nitrogen	0.54
Oxygen	53.32
Ash	0.01

Two Stages Removed
Cooling Air 8% of Compressor Flow
Turbine Vane Closed by 11.38%

	Ambient Temperature		
	59°F	80°F	90°F
Net Power Output (kW)	20,250	17,870	16,780
Heat Rate (Btu/Kwh) (LHV)	14,000	14,830	15,270
Fuel Lower Heating Value (Btu/lb)	2203	2187	2188
Inlet Pressure Loss ("H ₂ O)	9	8.6	8.6
Exhaust Temperature (F)	801	815	821
Scroll Pressure Drop (psi)	1.84	1.68	1.62
Compressor Inlet (lb/s)	229	219	214

TABLE 5-2

**EFFECT OF CHANGE IN PCFB PRESSURE DROP
WITH 1600°F BOT**

Ambient Pressure	14.3 psia
Ambient Temperature	59°F
Relative Humidity	65%
Burner Outlet Temperature	1600°F

Fuel Analysis (% wt)

Carbon	37.96
Hydrogen	8.14
Sulphur	0.03
Nitrogen	0.54
Oxygen	53.32
Ash	0.01

**Two Stages Removed
Cooling Air 8% of Compressor Flow
Turbine Vane Closed by 11.38%**

	PCFB Pressure Drop		
	1.3 Bar	0.9 Bar	0.5 Bar
Net Power Output (kW)	20,250	20,700	21,240
Heat Rate (Btu/Kwh) (LHV)	14,000	13,770	13,520
Fuel Lower Heating Value (Btu/lb)	2203	2217	2230
Inlet Pressure Loss ("H ₂ O)	9.0	9.0	9.0
Exhaust Temperature (F)	801	801	800
Scroll Pressure Drop (psi)	1.84	1.74	1.67
Compressor Inlet (lb/s)	229	229	229

TABLE 5-3

**EFFECT OF CHANGE IN FUEL COMPOSITION
WITH 1600°F BOT**

Ambient Pressure	14.3 psia
Ambient Temperature	59°F
Relative Humidity	65%
PCFB Pressure Drop	18.85 psia
Burner Outlet Temperature	1600°F

Two Stages Removed
Cooling Air 8% of Compressor Flow
Turbine Vane Closed by 11.38%

Fuel Analysis (% wt)

Carbon	37.96	44.04
Hydrogen	8.14	7.65
Sulphur	0.03	0.03
Nitrogen	0.54	0.63
Oxygen	53.32	47.64
Ash	0.01	0.01

Net Power Output (kW)	20,250	18,300
Heat Rate (Btu/Kwh) (LHV)	14,000	14,760
Fuel Lower Heating Value (Btu/lb)	2203	2427
Inlet Pressure Loss ("H ₂ O)	9.0	9.0
Exhaust Temperature (F)	801	807
Scroll Pressure Drop (psi)	1.84	1.7
Compressor Inlet (lb/s)	229	229

TABLE 5-4

**EFFECT OF CHANGE IN AMBIENT TEMPERATURE
WITH 1950°F BOT**

Ambient Pressure	14.3 psia
Relative Humidity	65%
PCFB Pressure Drop	18.85 psia
Burner Outlet Temperature	1950°F

Fuel Analysis (% wt)

Carbon	37.96
Hydrogen	8.14
Sulphur	0.03
Nitrogen	0.54
Oxygen	53.32
Ash	0.01

**Two Stages Removed
Cooling Air 12% of Compressor Flow
Turbine Vane Closed by 8.73%**

	Ambient Temperature		
	59°F	80°F	90°F
Net Power Output (kW)	27,980	25,200	23,920
Heat Rate (Btu/Kwh) (LHV)	13,150	13,715	14,010
Fuel Lower Heating Value (Btu/lb)	2987	2981	2989
Inlet Pressure Loss ("H ₂ O)	9.0	8.6	8.3
Exhaust Temperature (F)	1000	1013	1019
Scroll Pressure Drop (psi)	1.81	1.73	1.7
Compressor Inlet (lb/s)	229	219	214

TABLE 5-5

**EFFECT OF CHANGE IN PCFB PRESSURE DROP
WITH 1950°F BOT**

Ambient Pressure	14.3 psia
Ambient Temperature	59°F
Relative Humidity	65%
Burner Outlet Temperature	1950°F

Fuel Composition (% wt)

Carbon	37.96
Hydrogen	8.14
Sulphur	0.03
Nitrogen	0.54
Oxygen	53.32
Ash	0.01

**Two Stages Removed
Cooling Air 12% of Compressor Flow
Turbine Vane Closed by 8.73%**

	PCFB Pressure Drop		
	1.3 Bar	0.9 Bar	0.5 Bar
Net Power Output (kW)	27,980	28,510	29,040
Heat Rate (Btu/Kwh) (LHV)	13,150	12,955	12,795
Fuel Lower Heating Value (Btu/lb)	2987	3000	3013
Inlet Pressure Loss ("H ₂ O)	9.0	9.0	9.0
Exhaust Temperature (F)	1000	998	997
Scroll Pressure Drop (psi)	1.81	1.74	1.66
Compressor Inlet (lb/s)	229	229	229

TABLE 5-6**EFFECT OF CHANGE IN FUEL COMPOSITION
WITH 1950°F BOT**

Ambient Pressure	14.3 psia
Ambient Temperature	59°F
Relative Humidity	65%
PCFB Pressure Drop	18.85 psi
Burner Outlet Temperature	1950°F

Two Stages Removed
Cooling Air 12% of Compressor Flow
Turbine Vane Closed by 8.73%

Fuel Analysis (% wt)

Carbon	37.96	44.04
Hydrogen	8.14	7.65
Sulphur	0.03	0.03
Nitrogen	0.54	0.63
Oxygen	53.32	47.64
Ash	0.01	0.01

Net Power Output (kW)	27,980	25,870
Heat Rate (Btu/Kwh) (LHV)	13,150	13,590
Fuel Lower Heating Value (Btu/lb)	2987	3301
Inlet Pressure Loss ("H ₂ O)	9.0	9.0
Exhaust Temperature (F)	1000	1003
Scroll Pressure Drop (psi)	1.81	1.73
Compressor Inlet (lb/s)	229	229

CONCLUSIONS

During the period covered by this report, a fourth year of testing the subscale slagging combustor at Textron was completed. The subscale slagging combustor was reconfigured twice during the period: 1) prior to the first tests the curved body impact separator and slag tap were removed and the original centerbody impact separator reinstalled, and 2) after tests CR1-2 through CR1-4, the curved body impact separator and real-time slag removal system were reinstalled. As a result of four years of active testing in this program, the following conclusions may be drawn:

- It was possible to achieve the full design thermal capacity of 12 MMBtu/hr with the subscale slagging combustor, while burning 100% PC and operating at the design pressure of 6 atm.
- Because of the separate-chamber, rich-lean design of the subscale slagging combustor, NO_x emissions that easily meet the NSPS limits are readily achieved.
- Because of its refractory-lined, toroidal-vortex design, the subscale slagging combustor readily achieves in excess of 99% carbon burn-out efficiency when 100% coal-fired.
- Objectives for third-stage exit temperature (1850°F), and exit temperature pattern factor (14%) were readily achieved.
- Overall pressure loss is currently an acceptable 6 to 8% with the cyclone separator.
- Sulfur reductions at the exit of the third stage up to 50% have been achieved. The NSPS goal is 70 to 90% reduction, depending on the coal's sulfur content.
- Feeding pulverized coal and sorbent into the combustor against 6 atm pressure has been shown achievable.
- Slag collection with the curved centerbody impact separator was only slightly degraded relative to the centerbody impact separator which has a 90% slag capture efficiency.
- Addition of the cyclone separator has provided exit particulate loadings on the order of 10 to 50 ppmw. When compared to test operating conditions, NSPS emissions limit of 0.03 lbs/MMBtu would correspond to approximately 15 ppmw. This confirms that the cyclone is operating at approximately 90% collection efficiency, providing an overall slag collection efficiency of approximately 99%.

- The curved body impact separator has a lower heat loss (approximately 3%) compared to the symmetrical centerbody design, 11% versus 14%, respectively.
- The real time slag tap has been effective in removing spent sorbent from the system and preventing reentrainment of the captured sulfur.
- The char carry-over problem that developed when the slagging cyclone was added to the system was resolved by increasing the coal carrier air velocities, thus producing more stable coal delivery to the combustor.

The Reference System Definition Update report prepared and submitted as part of Task 8.0 shows the reference cost-of-electricity (COE) standard for this report is a 220 MW conventional pulverized coal-fired steam turbine generator plant with a flue gas desulfurizer (PC-FGD). This plant is fueled with Pittsburgh No. 8 coal (\$1.80/MMBtu). The COE margin, which is the difference between the COE of a candidate system and the COE of the PC-FGD, showed margins of 17.9 and 11.0% for the direct coal-fired combustion turbine combined cycle plants (CFCTCC) fueled with PC and CWM, respectively. Both the CWM- and PC-fired CFCTCCs and the PC-FGD steam plant have higher COEs than a combined cycle plant fueled by natural gas or oil at \$4.00/MMBtu (i.e., \$4.11/1000 SCF and \$23.30/barrel for No. 2 oil). However, an increase in gas or oil prices makes the CFCTCC less expensive to operate than its gas or oil fueled counter part. In fact, when comparing coal prices against a rising price in gas or oil, the economics switch immediately to any coal-fueled based power generation process. In addition this report reveals that coal beneficiation, with respect to the CFCTCC plant, provides no economic benefit.

REFERENCES

1. "Advanced Coal-Fueled Gas Turbine Systems Annual Technical Progress Report for Period July 1988 - 1989," U.S. Department of Energy, Contract No. DE-AC21-86MC23167, Morgantown, WV, July 1989.
2. "Gas Turbine Systems Research and Development Program Topical Report," U.S. Department of Energy, Contract No. DE-AC21-83MC20324, Morgantown, WV, January 1985.
3. "Advanced Coal-Fueled Gas Turbine Systems Annual Technical Progress for Period July 1989 - June 1990," U.S. Department of Energy, Contract No. DC-AC21-86MC23167, Morgantown, WV, July 1990.
4. "Slag Utilization and Behavior in a Pressurized Gas Turbine Coal Combustor," Loftus, P.J., Diehl, R.C., Stickler, D.B., and Bannister, R.L., presented at Engineering Foundation Conference on Inorganic Transformations and Ash Deposition During Combustion, Palm Coast, FL, March 10-15, 1991.
5. "Advanced Coal-Fueled Gas Turbine Systems Annual Technical Progress Report for Period July 1990 - June 1991," U.S. Department of Energy, Contract No. DC-AC21-86MC23167, Morgantown, WV, September 1991.
6. "NO_x Control in a Slagging Combustor for a Direct Coal-Fired Utility Gas Turbine," Loftus, P.J., Diehl, R.C., Bannister, R.L., and Pillsbury, P.W., presented at Joint EPA/EPRI Symposium on Stationary Combustion NO_x Control, Washington, D.C., March 1991.
7. "Nonequilibrium Sulfur Removal from High Temperature Gases," Abichandari, J.S., Loftus, P.J., Diehl, R.C., Woodroffe, J.A., and Holcombe, N.T., presented at 6th Annual Pittsburgh Coal Conference, Pittsburgh, PA, September 1989.

END

**DATE
FILMED**

5 / 12 / 93