MARTIN MARIETTA

ORNL/ER-116

**ENVIRONMENTAL
RESTORATION
PROGRAM**

**Work Plan to Assess Treatment of
Trench Water from Waste Area
Grouping 6 at Oak Ridge
National Laboratory,
Oak Ridge, Tennessee**

P. A. Taylor

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

MANAGED BY
MARTIN MARIETTA ENERGY SYSTEMS, INC.
FOR THE UNITED STATES
DEPARTMENT OF ENERGY

UCN-17560 (6 7-91)

ENERGY SYSTEMS

This report has been reproduced directly from the best available copy.

Available to DOE and DOE contractors from the Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831; prices available from 615-576-8401, FTS 626-8401.

Available to the public from the National Technical Information Service, U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161.

ORNL/ER--116

DE92 013478

Environmental Restoration Division
ORNL Environmental Restoration Program

**Work Plan to Assess Treatment of Trench Water from Waste Area
Grouping 6 at Oak Ridge National Laboratory,
Oak Ridge, Tennessee**

P. A. Taylor

Date Issued—March 1992

Prepared by
Chemical Technology Division
Oak Ridge National Laboratory

Prepared for
U.S. Department of Energy
Office of Environmental Restoration and Waste Management
under budget and reporting code EW 20

OAK RIDGE NATIONAL LABORATORY
Oak Ridge, Tennessee 37831-6285
managed by
MARTIN MARIETTA ENERGY SYSTEMS, INC.
for the
U.S. DEPARTMENT OF ENERGY
under contract DE-AC05-84OR21400

MASTER

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED
423

Author Affiliation

P. A. Taylor is a member of the Chemical Technology Division, Oak Ridge National Laboratory, Martin Marietta Energy Systems, Inc.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

CONTENTS

EXECUTIVE SUMMARY	iv
PROJECT SUMMARY	1
PROJECT DESCRIPTION AND SITE BACKGROUND	1
REMEDIAL TECHNOLOGY DESCRIPTION	1
TEST OBJECTIVES	4
PILOT PLANT INSTALLATION AND START-UP	4
PILOT PLANT OPERATION	7
PARAMETERS TO BE TESTED	7
SAMPLING PLAN	7
DATA MANAGEMENT	8
HEALTH, SAFETY, AND QUALITY ASSURANCE	8
RESIDUALS MANAGEMENT	8
PROJECT STAFF	8
SCHEDULE	9
REFERENCES	9

EXECUTIVE SUMMARY

Water from a selected waste disposal trench in Waste Area Grouping (WAG) 6 will be used to conduct a pilot-scale treatment assessment. The experiment will be designed to demonstrate whether adding WAG 6 trench water to the wastewater treatment facilities at Oak Ridge National Laboratory (ORNL) will change the regulatory status of the solid wastes produced by these facilities. Laboratory-scale treatability tests conducted in 1990 showed that the existing ORNL wastewater treatment facilities could successfully treat the WAG 6 trench water to meet discharge requirements, but the tests did not address the regulatory status of the solid wastes produced by the treatment processes. A longer-term, larger-scale test will be performed to determine if these solid wastes will become hazardous as defined by the Resource Conservation and Recovery Act when WAG 6 trench water is mixed with the existing process wastewater. These data are needed to determine the feasibility of adding the WAG 6 trench water to the treatment facilities.

PROJECT SUMMARY

Water from a selected waste disposal trench in Waste Area Grouping (WAG) 6 at Oak Ridge National Laboratory (ORNL) will be used to conduct a pilot-scale treatment assessment. The experiment will be designed to demonstrate whether adding WAG 6 trench water to the wastewater treatment facilities at ORNL will change the regulatory status of the solid wastes produced by these facilities.

PROJECT DESCRIPTION AND SITE BACKGROUND

The ORNL Environmental Restoration Program is examining methods for final closure of WAG 6. It is possible that the closure work will require that the waste disposal trenches be dewatered, so a method for disposing of this water is needed. Extensive characterization data are available for the trench water.¹⁻³ Laboratory-scale treatability tests conducted in 1990 showed that the existing ORNL wastewater treatment facilities could successfully treat the WAG 6 trench water to meet discharge requirements,³ but the tests did not address the regulatory status of the solid wastes produced by the treatment processes. A longer-term, larger-scale test will be performed to determine if these solid wastes will become hazardous as defined by the Resource Conservation and Recovery Act (RCRA) when WAG 6 trench water is mixed with the existing process wastewater. These data are needed to determine the feasibility of adding the WAG 6 trench water to the treatment facilities.

REMEDIAL TECHNOLOGY DESCRIPTION

Current plans are to add any water generated by the WAG 6 closure to the ORNL process wastewater system. The water will be treated at the Process Wastewater Treatment Plant (PWTP) to remove radionuclides and then at the Nonradiological Wastewater Treatment Plant (NRWTP) to remove organics.

The PWTP treats water that may contain low concentrations of radionuclides, mostly ^{90}Sr and ^{137}Cs . The flowsheet for the PWTP is shown in Fig. 1. Most of the calcium and about 50% of the ^{90}Sr are removed by precipitation at a pH of 11.5 in the softener. The clarified water is then treated with a strong-acid cation resin (Dowex HCR-S), which removes the remaining ^{90}Sr . For the normal PWTP flowrate of 480 L/m, the empty-bed contact time for the water in the resin columns is 6.2 min. If the water needs to be treated to remove ^{137}Cs , then chabazite zeolite columns are used, either in series or parallel with the routine PWTP processes. The discharge limits for the effluent from the PWTP are listed in DOE Order 5400.5.⁴

The NRWTP is a new facility that started operation in March 1990. The flowsheet for the NRWTP is shown in Fig. 2. Most of the wastewater that enters the plant, including the PWTP effluent, is routed to the nonmetals tank and is treated only for organics removal. The air stripper is filled to a height of 8 m with a high-efficiency packing (3.5-in. Lanpac, Lantec Products, Inc., Agoura Hills, California). At normal operating conditions the air stripper has about nine net transfer units for aromatic compounds. The carbon columns each contain

Fig. 1. Process Wastewater Treatment Plant (PWTP).

ORNL DWG 89A-955

Fig. 2. Nonradiological Wastewater Treatment Plant (NRWTP).

about 10,000 kg of activated carbon (Atochem, Inc., Cecarbon GAC-30). The carbon columns, which are operated two in series with the third column in standby, have an empty-bed contact time of about 40 min at the normal NRWTP flowrate of 1100 L/m. The discharge limits for the NRWTP are given in the National Pollutant Discharge Elimination System (NPDES) permit issued to the facility by the Tennessee Department of Environment and Conservation (TDEC).

TEST OBJECTIVES

A pilot-scale treatment facility will be built and operated to determine how the addition of WAG 6 trench water to the ORNL process wastewater system will affect the regulatory status of the secondary solid wastes produced by the PWTP and the NRWTP. A flow diagram of the proposed treatment facility is shown in Fig. 3. The test equipment will model the softener, filter, and ion exchange columns of the PWTP, and the air stripper and carbon columns of the NRWTP. Water from trench T-16, which previous analyses have shown to contain the highest concentration of organics of any of the trenches sampled,³ will be used in the tests. The trench water will be added to ORNL process wastewater at a concentration of 1.5 vol%, which corresponds to one 3000-gal tanker of trench water added to the process wastewater system each day, the maximum expected transfer rate from WAG 6.

Chemical data (volatile and semivolatile organics, metals, and radionuclides) on the water will be collected periodically at each stage of the treatment process. These data will be used to track the operation of the pilot plant, to demonstrate that it is accurately modeling the full-scale treatment plants. At the conclusion of the test period, samples of clarifier sludge and activated carbon from the pilot plant, and corresponding samples from the full-scale treatment plants, will be analyzed for toxicity through use of the toxicity characteristic leaching procedure (TCLP). These analytical results are the primary objective of the treatability study and will determine if adding WAG 6 trench water to the ORNL process wastewater system will change the regulatory status of the secondary wastes from the treatment plants.

PILOT PLANT INSTALLATION AND START-UP

A new trailer, which will be located adjacent to the PWTP, will be used to house the treatability test equipment. The trailer will be equipped with a HEPA-filtered ventilation system. A pilot-scale softener, which has previously been operated as part of an alternatives study for upgrading the PWTP, has been improved for use in this study. The pilot-scale air stripper will be constructed of clear polyvinyl chloride and will use the same packing as was used in the 1990 treatability tests³ (1/4-in. ceramic saddles). The previous tests showed that one transfer unit required a packing height of 0.5 m at test conditions comparable to the NRWTP air stripper. The new air stripper will have a packing height of 4.5 m (split between two columns), so it should have nine transfer units like the NRWTP air stripper. The new activated carbon column will use the same type of granular activated carbon used in the NRWTP columns and will have the same empty-bed contact time.

The pilot-scale equipment will be tested extensively with clean water to ensure proper operation before contaminated wastewater is introduced. The equipment is designed for

continuous operation with minimal operator attention and will be located in secondary containment pans with leak detection devices.

Fig. 3. Flow diagram for WAG 6 treatability study pilot-scale facility.

PILOT PLANT OPERATION

Approximately 500 L of water from trench T-16, which previous analyses have shown to contain the highest concentration of organics of any of the trenches sampled, will be used in this test. The trench water will be added to ORNL process wastewater (influent to the PWTP) at a concentration of 1.5 vol% (500 mL/min process water and 7.5 mL/min trench water), which corresponds to one 3000-gal tanker of trench water added to the process wastewater system each day (the maximum expected transfer rate).

The combined wastewater will be dosed with 0.008 mL/min Ferrifloc (2.5 mg/L Fe), and sodium hydroxide will be added to a pH of 11.4–11.6. Betz-1100 polymer will be added at a concentration of 0.3 mg/L to flocculate the precipitated solids. The solids will be settled, and the clarified wastewater will be filtered and treated using Dowex HCR-S cation exchange resin. All chemical additions and treatment times match the corresponding full-scale treatment at the PWTP.

The wastewater will then be adjusted to pH 7.0–7.5 with sulfuric acid before being treated for organics removal by air stripping and activated carbon adsorption as happens at the NRWTP. Since the packing used in the NRWTP air stripper is not available in small sizes, the operating conditions of the NRWTP air stripper cannot simply be duplicated in the pilot plant. The goal is to have the same concentration of organics exiting the pilot-scale air stripper as would be present in the effluent from the NRWTP air stripper treating the same wastewater. This can be accomplished by designing and operating the pilot-scale air stripper to provide nine transfer units, as is the case at the NRWTP. The experimental data from the laboratory-scale treatability tests³ show that 4.5 m of 1/4-in. ceramic saddles, with a gas-to-liquid volume ratio of 40:1, will provide the same organic removal as the NRWTP air stripper. The pilot-scale activated carbon column will use the same type of carbon and will provide the same contact time as do the NRWTP carbon columns.

PARAMETERS TO BE TESTED

The goal of this test is to model the operation of the full-scale treatment plants, so the treatment parameters will not be varied during the course of the test.

SAMPLING PLAN

Water samples from each step in the process will be analyzed for radionuclides, dissolved metals, and organics (volatile and semivolatile) during the course of the test to document that the pilot facility is operating comparably to the full-scale facilities. At the end of the test, samples of softener sludge and activated carbon will be analyzed by TCLP for toxicity. Samples of sludge from the PWTP and activated carbon from the NRWTP will also be TCLP tested for comparison. These TCLP results are the primary purpose for the pilot-scale treatability tests.

DATA MANAGEMENT

All procedures, calculations, observations, etc. will be entered directly in a hard cover, bound notebook registered to the principal investigator by the ORNL Laboratory Records Department. Each page will be dated and signed. Operational data will include flowrates, water and air temperatures, water pH, and run time. All analytical results will also be entered in the notebook.

HEALTH, SAFETY, AND QUALITY ASSURANCE

All research activities conducted at ORNL are required to have a Safety Summary, which describes equipment and procedures to be used, safety precautions, and compliance with ORNL safety procedures and environmental control policies. The Safety Summary is reviewed and approved by a Section Safety Committee, the Section Safety Officer, and the Section Head. The Safety Summary also includes a Quality Assurance (QA) Assessment, as specified in the ORNL Quality Assurance Manual, which is reviewed by the Section and Division QA Coordinators. The risk of significant QA failures for this project was determined to be insignificant because of the routine nature of the experiments.

RESIDUALS MANAGEMENT

All residuals from these experiments, including water, sludge, spent activated carbon, and ion exchange resins, will be disposed of in accordance with the procedures in the ORNL Environmental Protection Manual. The treated water from the pilot plant will be returned to the inlet of the PWTP. It is expected that the test will generate 20 kg of sludge and 15 kg of activated carbon. The TCLP testing will determine if these solids are RCRA-hazardous. If the sludge is nonhazardous, it can be disposed of as low-level waste, along with the sludge from the PWTP. The ion-exchange resin will be regenerated and dried for disposal, as is done with the resin at the PWTP. The activated carbon can be disposed of with the NRWTP activated carbon if it is determined to be nonhazardous. If either secondary waste is RCRA-hazardous, it will be handled as mixed waste.

PROJECT STAFF

The Project Manager is D. D. Van Hoesen of the Engineering Division, ORNL. The Principal Investigators are C. M. Kendrick, T. E. Kent, and P. A. Taylor, all of the Chemical Technology Division, ORNL.

SCHEDULE

Item	Completion
1. Construct experimental equipment	3/15/92
2. Complete preoperational testing	3/31/92
3. Complete experimental work	5/15/92
4. Receive analytical results	6/30/92
5. Analyze results and draft report	7/31/92

REFERENCES

1. D. K. Solomon, R. C. Haese, T. V. Dinsmore, and A. D. Kelmars, *Sampling and Analysis of SWSA 6 Trench Leachates and Groundwaters*, ORNL/TM-10813, Oak Ridge National Laboratory, Oak Ridge, Tennessee, December 1988.
2. B. P. Spalding, G. K. Jacobs, and E. C. Davis, *Demonstrations of Technology for Remediation and Closure of Oak Ridge National Laboratory Waste Disposal Sites*, ORNL/TM-11286, Oak Ridge National Laboratory, Oak Ridge, Tennessee, September 1989.
3. P. A. Taylor, *Treatability Study for WAG 6 (SWSA 6) Trench Water*, ORNL/ER-17, Oak Ridge National Laboratory, Oak Ridge, Tennessee, August 1991.
4. *Radiation Protection of the Public and the Environment*, U.S. Department of Energy Order 5400.5, February 8, 1990.

DISTRIBUTION

1. L. D. Bates	14-15. P. T. Owen
2. C. H. Brown	16. S. M. Robinson
3. K. W. Cook	17. G. E. Rymer
4. M. F. P. Delozier	18. P. A. Schrandt
5. N. W. Durfee/L. V. Asplund	19. D. W. Swindle
6. S. B. Garland	20-23. P. A. Taylor
7. C. D. Goins	24. S. D. Van Hoesen
8. P. J. Halsey	25. D. R. Watkins
9. C. M. Kendrick	26. R. K. White
10. T. E. Kent	27. Central Research Library
11. S. L. Laman	28-32. ER Document Management Center
12. V. Legg	33-34. Laboratory Records Dept.
13. A. G. Owens	35. ORNL Patent Section
-
- 36. Office of Assistant Manager for Energy Research and Development, DOE Oak Ridge Field Office, P.O. Box 2001, Oak Ridge, TN 37831-8600
 - 37. P. H. Edmonds, Radian Corporation, 120 South Jefferson Circle, Oak Ridge, TN 37830
 - 38-41. W. E. Murphie, Department of Energy, Office of Environmental Restoration, Eastern Area D&D Branch, EM-423 (GTN), Washington, DC 20545
 - 42-43. S. S. Perkins, DOE Oak Ridge Field Office, Information Resource Center, 105 Broadway, Oak Ridge, TN 37830
 - 44-45. R. C. Sleeman, DOE Oak Ridge Field Office, P.O. Box 2001, Oak Ridge, TN 37831-8540
 - 46. S. P. Riddle, DOE Oak Ridge Field Office, P.O. Box 2001, Oak Ridge, TN 37831-8541
 - 47-48. Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831

END

DATE
FILMED

6126192